osFinancials5 / TurboCASH5-Business Class Help

Table of contents

AI / ETL 57
AI/ETL - Bank import 59
AI/ETL - Chart of Accounts 63
AI/ETL - Debtors/Creditors 64
AI/ETL - Stock / Inventory 66
AI/ETL - Documents 67
AI/ETL - Journals (Batches) 72
Release notes 74
osFinancials-development merge-install 108
TurboCASH-development merge-install 121
TurboCASH-Version control 149
TurboCASH-development-Chinese 151
osFinancials-development 166
2024-osFinancias5.1 - Build 5.1.0.189 Release notes 186
2024-osFinancias5.1 - Build 5.1.0.189 Known issues 189
Translations outstanding 203
Translations - Record buttons 221
Translations - Access control 222
Translations - Bank recon (Default) 228
Translations - Bank import plugin 232
Translations - Batches 237
Translations - Budgets 243
Translations - Calendar 247

Translations - Debtors / Creditors 250
Translations - Documents 255
Translations - Import / Export 265
Translations - Open item 269
Translations - Reports 273
Translations - Report designer 277
Translations - Setup ribbon 286
Translations - Spreadsheets 293
Translations - Stock 295
Translations - Stock-BOM 303
Translations - Point of Sale (Standard) 307
Translations - Plugins 310
Translations - Plugin - Activa 310
Translations - Plugin - Charter 314
Translations - Plugin - CRM 317
Translations - Plugin - DrillDown 327
Translations - Plugin - E-commerce 332
Translations - Plugin - Emailpro 333
Translations - Plugin - FreeFields 339
Translations - Plugin - HandyTools 342
Translations - Plugin - Location-Serial-Batch 347
Translations - Plugin - Multimedia 350
Translations - Plugin - Multi-User-Calendar 354
Translations - Plugin - Mijnwinkel / Myshop 359
Translations - Plugin - Office Pro 362

Translations - Plugin - Price Agreement 364
Translations - Plugin - Reminders 368
Translations - Plugin - SQL-Browser 373
Translations - Plugin - Subscriptions 375
Translations - Plugin - RetailPOS 384
Translations - Plugin - HORECAPOS 399
Translations - Plugin - Belgische BTW Plugin - Shop description 402
Translations - Plugin - Stock check 404
Translations - Plugin - Quick Order 408
Translations - Plugis - Documents export / import 415
Translations - Plugin - FileAndXMLImportExport 416
Translations - Plugin - Workflow 424
FIXED - reports - GENERAL - documents 425
ADDED - GDI scaling (Graphics Device Interface scaling) support 426
FIXED / ADDED - Themes 437
FIXED - Themes 443
Themes screenshots 448
FIXED - Firebird databases - Upgraded to Firebird 2.1 ODS 11.1. 482
FIXED - Cannot Open / Create MSSQL Databases 483
ADDED / Fixed - Languages labels 484
Known issues - Language label inconsistencies 488
NEW - Empty Sets of Books - Supports up to 8 digit main accounts and 3 digit sub accounts 490
Customise Empty Books 502
Known issues - Calendar - Contacts - Resource 517

FIXED - Access violations (osF5.1.0.100) 518
FIXED - Missing Configuration Files - Full install - (osF5.1.0.16) 519
FIXED - Password change (osF5.1.0.16) 520
FIXED - Documents - Debtor / Creditor Lookup 521
FIXED - F8:Discount - Documents 524
FIXED - Bank recon - Last total 525
FIXED - Bank recon options - label 527
FIXED - Unicode setting - Currencies - Default setting 529
Known issues 535
Known issues - Clear/Reset 535
Known issues - Digit separator symbol - Documents - Spreadsheet import 535
Known issues - Decimal symbol - Create receipts (Batch entry) 539
Known issues - No Delete confirmation messages 541
Known issues - Access violations 543
Known issues - Cost centres - Access Violations 543
Known issues - Default language setting 545
Known issues - Customise your own Set of Books (Advanced)? - Missing Groups and Paper types 546
Known issues - Screen layout 551
Known issues - Books - Delete 553
Known issues - Debtors / Creditors - Multimedia 555
Known issues - Lookups - Main accounts 555
Known issues - Batches 558
Known issues - Documents 563
Known issues - Stock 570

Known issues - Checking unposted items - No data 572
Known issues - Print - Batch type report - Posted batches - COS 573
Known issues - Import / Export 574
Known issues - Convert quote to one unprocessed invoice per client 580
Known issues - Confirm Quotes and Orders - Remove button 580
Known issues- Create backorders to deliver 581
Known issues - Search - BOM (Production) 584
Known issues - Reports 597
Known issues - Stock sidebar reports - Report - Print single item 606
Known issues - Creditor remittance advices - SMESSAGE - CREDITOR table .. 607
Known issues - Reports - Debtor list - Details / Creditor list - Details 610
Known issues - SQL Compatibility MSSQL and Firebird Database types 612
Known issues - SQL Compatibility MSSQL and Firebird Database types - Reports 612
Known issues - SQL Compatibility MSSQL and Firebird Database types - Plugins 613
Known issues - Outstanding at date reports - MSSQL 617
FIXED-Reports 621
FIXED - Graphs - Posted and Confirmed Quotes and Orders 629
FIXED - MSSQL Graphs per Month - Axis labels (Axis titles) 631
FIXED - Graphs per week - 'WEEK' is not a recognized built-in function name. 639
FIXED-ADDED - Layout files 655
FIXED-ADDED - Stock In / Out reports - Document reference number (Show details) 660
FIXED-ADDED - Stock sidebar reports - Report - Print single item 661
FIXED - Reports - Location-Serials-Batches 672

FIXED - Reports - Price agreement 673

FIXED - Creditor Remittance advice - Not printing postal address 675

FIXED - Report Batch type - Documents Static redundant Expression in Page-HEADER 678

FIXED - Access violation errors - Reports menu 679

FIXED - Budget vs actual + This year vs Last year budgetvsactsimple.rep 680

FIXED - Reports - GENERAL/documents 681

FIXED - Reports - Projects 682

FIXED - Due Ageing 683

FIXED - Debtor statements Period 2 includes Period 1 688

FIXED - Spreadsheet reports – Transactions per period 694

FIXED - Reports - Support for MSSQL database types - March 2022 695

FIXED - Reports - 8x3 Digit account codes - Reports 702

FIXED - Reports layout long descriptions and data 718

FIXED - Debtor Statements and Creditor Remittance advices 776

FIXED - Document layout files 784

FIXED - Reports layout long descriptions and data - Layout files-Labels-Statements 793

FIXED - Reports - Numbering format 796

FIXED - User reports 797

FIXED - Remittance - reports plugin 809

FIXED - Subscriptions - reports 818

Known issues - Plugins 827

Known-issues - Plugin - Stock Adjustments 847

Known issues - Plugin - Activa Setup - Select Accounts 915

Known issues - Plugin - Bank import plugin 917
Known issues - Plugin - Charter 919
Known issues - Plugin - Remittance 920
Known issues - Plugin - Subscriptions 924
Known issues - Drill down plugin - Stock item Invoice AV Error 927
Known issues - SQL Browser Plugin 929
Known issues - Serials / Patches / Location 930
Known issues - Plugin - E-MailPro 930
Known issues - Plugin - Multimedia 937
Known issues - Plugin - Multi-language accounts 939
Known issues - Plugin - FileAndXMLImportExport 941
Known issues - Plugin - StockCheck - Bulkcheck tab - Errors 942
Known issues - Plugin - QuickOrder - Stockcount tab 944
Welcome 947
Scope of this documentation 951
New features in osFinancials5 955
Features 960
Getting started 988
System requirements 994
System settings - Screen resolution 995
System settings - Number format 997
System settings - Default app for csv file types 1001
Unicode settings in osFinanacials5/TurboCASH5 1006
Unicode -Context menu on forms 1022
Install osFinancials5 - Single user 1028

Install TurboCASH5-3 - Single user 1038
Migrate existing data into TurboCASH5-3 1050
Install osFinancials5 - Updates (Help menu) 1050
Install osFinancials5 - Updates (Manually) 1053
Install Updates - Go back to osFinancials4 1057
Uninstall osFinancials5 1059
Start osFinancials5 1062
Launch osFinancials5 for the first time 1064
Register osFinancials5 1067
Customise osFinancials5 1069
Themes 1070
Themes - New theme -change icon colours at one go 1072
Languages 1079
Switch language 1084
Customise language 1085
Customising terminology for VAT/GST/Sales tax 1093
Customising document type terminology - Invoice 1098
Customising document type terminology - Credit note 1105
Customising document type terminology - Quote 1108
Customising document type terminology - Purchase 1112
Customising document type terminology - Supplier return 1117
Customizing document type terminology - Order 1121
Set language for a Set of Books 1126
Accounting process in osFinancials5 1127
New to Computers 1129

Peripherals 1131
Barcode basics 1133
Printer basics 1139
RFID technology 1143
ODF (Open Document Format) / PDF (Portable Document Format) 1146
Document formats and printing options 1148
Document formats for export options 1150
Print on Demand and PDF documents 1151
New to Accounting 1153
Importance of accounting 1156
History of accounting 1157
Accounting process 1158
Methods of recording 1159
Manual system 1160
Computerised system 1162
Accounting cycle and the transaction cycle 1167
Double-entry accounting system 1171
Debits and Credits 1172
Transaction cycle 1173
Accounting equation and Financial categories 1180
Accounting equation - Balance sheet 1182
Accounting equation - Income statement 1183
Expanded accounting equation - Balance sheet and Income statement 1184
Account groups - Financial categories 1186
Account groups - Financial categories - Income statement 1187

Account groups - Financial categories - Balance sheet 1188
Charts of accounts in osFinancials/TurboCASH 1189
Balance sheet accounts - Chart of accounts 1190
Income / Expense accounts - Chart of accounts 1193
General ledger structure 1196
Control accounts 1198
Structure of osFinancials 1200
Research and Development (R&D) 1202
Common errors made in accounting 1207
osFinancials and Small businesses, Medium sized businesses and Large businesses . 1207
Financial Analysis and Valuation 1209
Financial Ratios 1210
Liquidity Ratios 1215
Current Ratio / Working Capital Ratio 1216
Quick Ratio (Acid-Test Ratio) 1217
Cash Ratio 1218
Solvency Ratios 1219
Debt-to-Equity Ratio (D/E) 1220
Debt Ratio 1221
Interest Coverage Ratio 1222
Debt Service Coverage Ratio (DSCR) 1223
Profitability Ratios 1224
Gross Profit Margin 1225
Operating Profit Margin 1226

Net Profit Margin 1227
Return on Assets (ROA) 1228
Return on Equity (ROE) 1229
Return on Investment (ROI) 1230
Efficiency Ratios 1231
Inventory Turnover Ratio 1233
Accounts Receivable Turnover Ratio 1234
Accounts Payable Turnover Ratio 1235
Asset Turnover Ratio 1236
Fixed Asset Turnover Ratio 1237
Market Ratios 1238
Price-to-Earnings Ratio (P/E Ratio) 1240
Price-to-Book Ratio (P/B Ratio) 1241
Dividend Yield 1242
Earnings per Share (EPS) 1243
Price-to-Sales Ratio (P/S Ratio) 1244
Total Asset Turnover Ratio 1246
Market Capitalization 1247
Time Value of Money (TVM) 1248
Branches in Accounting 1250
Financial Accounting 1252
Cost Accounting 1254
Management Accounting 1255
Tax Accounting 1256
Forensic Accounting 1258

Auditing 1259
Non-profit Accounting 1260
International Accounting 1262
Government and Public Sector Accounting 1263
Fund Accounting 1264
Trust Accounting 1266
Accounting frameworks 1271
Accounting standards - GAAP vs IFRS 1272
Differences between GAAP and IFRS 1293
Differences of between in IFRS (full) and IFRS for SMEs 1294
Accounting principles - GAAP 1295
Accounting principles that apply to IFRS full and IFRS for SMEs 1298
Accounting principles that apply to IFRS for SMEs 1300
IFRS for SME's - Countries - Optional / Mandatory 1301
Differences in accounting terminology in countries 1302
Accounting in China 1302
Designing a Chart of Accounts 1313
Chart of Accounts - Definition and objectives 1316
Chart of Accounts - Number of digits 1318
Chart of Accounts - Optimising 4-,5-,6-,7- and 8-digit main accounts 1320
Chart of Accounts - Sub-accounts 1325
Chart of Accounts - Recommendations to configure - GAAP and IFRS 1332
Chart of Accounts - Recommendations to configure - IFRS for SMEs 1335
Chart of Accounts - Legislation ownership 1336
Chart of Accounts - Business ownership 1337

United Kingdom (UK) - Chart of Accounts - GAAP 1345
United Kingdom (UK) - Standard Chart of Accounts (SCOA) 1353
South Africa - Chart of Accounts - SA GAAP and SA GAAP for SMEs 1355
South Africa - Chart of Accounts - Small business 1366
South Africa - Chart of Accounts - Retail business 1371
South Africa - Chart of Accounts - Service business 1374
South Africa - Chart of Accounts - Mixed Retail and Service business 1378
South Africa - Chart of Accounts - Manufacturing 1381
South Africa - Chart of Accounts - Church 1385
South Africa - Chart of Accounts - NPO or NGO 1388
New Zealand - Chart of Accounts - NZ IFRS 1391
Australia - Chart of Accounts - Australian Accounting Standards 1395
Canada - Chart of Accounts 1402
USA - Chart of Accounts 1407
Example and notes for a 4-digit Chart of Accounts 1410
Notes on specific accounts and financial categories 1451
Short-term assets (Current assets) and Long-term assets (Non-current assets) 1451
Short-term liabilities (Current liabilities) / Long-term liabilities (Non-current liabilities) 1456
Operating expenses and Non-operating expenses 1457
Expense classifications 1462
Insurance proceeds 1466
Suspense accounts 1468
Commissions paid 1471
Subsistence and travel allowances and advances 1472

Discounts allowed 1473
Discounts received 1477
Delivery charges 1479
Directors' remuneration 1482
Financial Intelligence Centre Act (FICA) 1484
Federal Insurance Contributions Act (FICA) 1487
Risk management 1489
Internal control 1492
Credit notes and Debit notes 1493
Returns and Discounts 1494
Customer Returns and Credit notes - Default Contra account 1495
Purchase Returns and Credit Notes issued by Suppliers - Default Contra account 1497
List of Accounts - Classification 1498
List of Accounts - Assets 1500
List of Accounts - Fixed Assets 1507
List of Accounts - Current Assets 1509
List of Accounts - Intangible Assets 1511
List of Accounts - Liabilities 1513
List of Accounts - Equity / Capital 1527
List of Accounts - Income 1533
List of Accounts - Expenses 1538
Stock / Inventory 1561
Inventory systems 1563
Inventory valuation 1564

LIFO and FIFO 1565
COS, COGS and COSR 1567
Work in Progress (WIP) 1570
Amortization 1572
RICA and related laws 1574
Taxes - Types 1578
Accounts SIT 1581
Federal Income Tax (FIT) 1582
Capital gains tax 1585
Customs Duties / Excise tax 1588
Business tax 1593
Corporate tax 1594
Franchise tax 1595
Withholding tax 1598
Provisional tax 1603
Turnover tax 1606
Taxes, Levies and Chages 1608
Taxes in South Africa 1609
Taxes in United Kingdom 1612
Taxes in Australia 1616
Taxes in New Zealand 1620
Taxes in Canada 1623
Taxes in United States of America (USA) 1627
VAT/GST/Sales Tax 1630
VAT/GST/Sales tax schemes 1634

Invoice - Requirements 1636
VAT/GST/Sales Tax - Configure Chart of Accounts 1642
VAT/GST/Sales Tax - New Registered Vendor in osFinancials 1643
VAT/GST/Sales Tax - New to osFinancials without Tax Registration 1646
VAT/GST/Sales Tax - Existing User Opting for Tax Deregistration 1648
VAT/GST/Sales Tax - Registration / Deregistration 1651
VAT/GST/Sales - Compulsory registration / Voluntary registration 1654
VAT/GST/Sales Tax - Tax codes and Tax returns 1658
VAT/GST/Sales Tax - Selecting the No Tax Code 1660
Reverse Charge Mechanism - Reverse Charge Mechanism..... 1663
Value Added Tax (VAT) - South Africa 1666
Goods and Services Tax (GST) - Australia 1677
Goods and Services Tax (GST) - New Zealand 1691
Value Added Tax (VAT) - United Kingdom 1704
European Union (EU) value-added tax (VAT) system 1724
VAT MOSS 1728
Destination-Based Taxes 1730
Online Sales Tax and Online Purchase Tax 1734
Sales tax and use tax in the USA 1736
Sales tax in the US 1738
Sales tax / Use tax - Delaware (DE) 1749
Sales tax / Use tax - Montana (MT) 1751
Sales tax / Use tax - New Hampshire (NH) 1755
Sales tax / Use tax - Oregon (OR) 1758
Sales tax / Use tax - Alabama (AL) 1760

Sales tax / Use tax - Alaska (AK) 1765
Sales tax / Use tax - Arizona (AZ) 1768
Sales tax / Use tax - Arkansas (AR) 1772
Sales tax / Use tax - California (CA) 1774
Sales tax / Use tax - Colorado (CO) 1778
Sales tax / Use tax - Connecticut (CT) 1782
Sales tax / Use tax - Florida (FL) 1786
Sales tax / Use tax - Georgia (GA) 1790
Sales tax / Use tax - Idaho (ID) 1794
Sales tax / Use tax - Illinois (IL) 1797
Sales tax / Use tax - Indiana (IN) 1801
Sales tax / Use tax - Iowa (IA) 1804
Sales tax / Use tax - Kansas (KS) 1808
Sales tax / Use tax - Kentucky (KY) 1812
Sales tax / Use tax - Louisiana (LA) 1814
Sales tax / Use tax - Maine (ME) 1818
Sales tax / Use tax - Maryland (MD) 1822
Sales tax / Use tax - Massachusetts (MA) 1825
Sales tax / Use tax - Michigan (MI) 1828
Sales tax / Use tax - Mississippi (MS) 1831
Sales tax / Use tax - Missouri (MO) 1834
Sales tax / Use tax - Nebraska (NE) 1836
Sales tax / Use tax - New York (NY) 1838
Sales tax / Use tax - North Carolina (NC) 1845
Sales tax / Use tax - North Dakota (ND) 1848

Sales tax / Use tax - Ohio (OH) 1851
Sales tax / Use tax - Oklahoma (OK) 1853
Sales tax / Use tax - Rhode Island (RI) 1855
Sales tax / Use tax - Pennsylvania (PA) 1858
Sales tax / Use tax - South Carolina (SC) 1860
Sales tax / Use tax - South Dakota (SD) 1863
Sales tax / Use tax - Tennessee (TN) 1865
Sales tax / Use tax - Texas (TX) 1867
Sales tax / Use tax - Utah (UT) 1869
Sales tax / Use tax - Vermont (VT) 1871
Sales tax / Use tax - Virginia (VI) 1873
Sales tax / Use tax - Washington (WA) 1875
Sales tax / Use tax - West Virginia (WV) 1877
Sales tax / Use tax - Wisconsin (WI) 1879
Sales tax / Use tax - Wyoming (WY) 1881
General Excise Tax / Use tax - Hawaii (HI) 1883
Use tax in the US 1885
Trade and Investment Incentives and Regulations 1887
Diesel refunds 1891
Industrial Development Zones and Economic Development Zones 1895
Incentives for generation and use of green energy 1900
Government assistance and support for crises 1906
Pandemics such as Covid 1908
Disaster Management and Acts of God 1913
SASRIA - South African Special Risks Insurance Association 1916

osFinancials5/TurboCASH5 Program 1922
Ribbons 1925
Start ribbon 1927
Default ribbon 1929
Reports ribbon 1933
Setup ribbon 1937
Export / Import 1943
Setup menu 1945
Company info 1949
Reporting dates 1953
Groups 1956
Salespersons 1959
Payment types 1962
Languages 1964
System parameters 1965
Internet 1968
Countries 1971
Currencies 1972
Point-of-Sale 1973
Printer 1974
Tools 1976
Calculator 1977
Close active forms 1978
Global processes menu 1978
Clear/Reset 1980

Reverse posted batch/document 1983
Copy from Set of Books 1984
User tab ribbon 1988
Show / Hide ribbon options 1990
Resizing screens 1992
Keyboard navigation 1993
Keyboard navigation - Changes from osfinancials4 1994
Record buttons 1995
Filters 1996
Help and Support 2001
TurboCASH - Releases 2002
Help 2007
Support 2010
Show welcome 2011
Forum 2012
Webshop 2012
Bug report 2013
Manage Sets of Books 2013
Open Set of Books 2016
Sets of Books - Download 2027
Sets of Books - Turorials 2038
Close Set of Books 2040
Delete Set of Books 2041
Exit osFinancials5 2045
Create Set of Books 2046

Copy an existing Set of Books 2047
Let osFinancials5/TurboCASH5 help you to create a Set of Books 2051
Let osFinancials5/TurboCASH5 help you to create a Set of Books - Download 2057
Customise your own Set of Books (Advanced) 2063
Converting Sets of Books 2089
Save as 2090
Data integrity check 2091
Backup / Restore Sets of Books 2095
Backup a Set of Books 2097
Backup a Set of Books to E-mail 2100
Restore a Set of Books 2102
Accounts (Ledger) 2104
Planning your Chart of Accounts 2110
Considerations when designing a chart of accounts 2112
Account groups 2115
Account groups (Setup - Groups) 2120
Account groups (Setup - Accounts) 2122
Financial categories 2125
Financial categories (Setup - Accounts) 2126
Financial categories (Setup) 2128
Edit - Accounts 2131
Edit Bank accounts 2136
Create Bank accounts 2138
Create / Edit Tax accounts 2141
Delete accounts 2147

Export / Import - General ledger accounts 2149
Export General ledger accounts (Setup ribbon) 2150
Import General ledger accounts (Setup ribbon) 2152
Open exported text file - Spreadsheet 2162
Import Accounts - Spreadsheet Export / Import 2166
Spreadsheet - Export - General ledger accounts 2167
Spreadsheet - Import - General ledger accounts 2171
Change Tax rates 2178
Debtor (customer / client) accounts 2207
Debtor groups 2210
Debtors filter and search options 2213
Debtor - Context menu 2223
Debtor Context menu - Set Debtor group 1/2 2224
Debtor - Context menu - Reports 2225
Debtor - Context menu - Copy account 2227
Debtor accounts edit form 2229
Debtor accounts - Delivery address tab 2232
Debtor accounts - Accounting information tab 2233
Debtor accounts - Contacts tab 2237
Debtor accounts - Appointments tab 2238
Debtor accounts - Documents tab 2239
Debtor accounts - Transactions tab 2242
Debtor accounts - Bank accounts tab 2248
Debtor accounts - Backorders tab 2248
Debtor accounts - Stock items tab 2251

Delete Debtor accounts 2252
Export / Import Debtor accounts 2253
Export Debtor accounts 2255
Import Debtor accounts 2257
Export Debtor accounts - Open text file in spreadsheet 2260
Export Debtor accounts - Export grid 2265
Spreadsheet Export / Import - Debtor / Creditor accounts 2271
Spreadsheet - Export - Debtors / Creditor accounts 2272
Spreadsheet - Import - Debtors / Creditor accounts 2277
Creditor (supplier / vendor) accounts 2281
Creditor groups 2284
Creditors filter and search options 2286
Creditor - Context menu 2297
Creditor - Context menu - Set Creditor Group 1/2 2298
Creditor - Context menu - Reports 2299
Creditor - Context menu - Copy account 2301
Creditor accounts edit form 2302
Creditor accounts - Delivery address tab 2305
Creditor accounts - Accounting information tab 2307
Creditor accounts - Contacts tab 2310
Creditor accounts - Appointments tab 2311
Creditor accounts - Documents tab 2311
Creditor accounts - Transactions tab 2313
Creditor accounts - Bank accounts tab 2319
Creditor accounts - Stock items tab 2320

Delete Creditor accounts 2321
Export / Import Creditor accounts 2322
Export Creditor accounts 2322
Import Creditor accounts 2324
Export Creditor accounts - Open text file in spreadsheet 2327
Export Creditor accounts - Export grid 2332
Spreadsheet Export / Import - Debtor / Creditor accounts 2338
Contacts 2339
Stock (Inventory / Products) 2341
Planning stock codes 2346
Stock item types 2347
Stock groups 2349
Stock information 2352
Units 2354
Add Account / Tax classes 2359
Create Cost of sales 2362
Cost of Sales and FIFO / LIFO 2365
Selling prices 2368
Options setup 2370
Stock item list screen 2372
Filter options (Stock) 2376
Stock list screen - Default mode 2379
Stock list screen - Advanced mode 2380
Import / Export tab 2382
Adjust stock tab 2383

Settings tab 2384
Show / Hide columns 2385
Group columns 2389
Stock items - Context menu 2390
Context menu - Print single item 2391
Print single item - Barcode 2392
Print single item - Yagoda barcode 2394
Print single item - Historical value 2396
Print single item - Outstanding orders 2399
Print single item - Outstanding quotes 2401
Print single item - Production list 2403
Print single item - Reorder quantities 2405
Print single item - Reporting group 1 2407
Print single item - Reporting group 2 2409
Print single item - Stock movement 2411
Print single item - Stock item listing 2413
Print single item - Stock item listing - Active items 2415
Print single item - Transaction details 2417
Print single item - Value stock account 2422
Print single item - Price list - Large retail - Sales 2425
Print single item - Price list - Large retail - Purchases 2429
Set Stock reporting group 1/2 2433
Copy / Paste 2434
Mass check 2437
Copy from a Stock item 2438

Adjust stock menu 2441
Stock items edit form 2441
Stock items - Ledger tab 2444
Stock items - Document groups tab 2447
Stock items - Transactions tab 2450
Stock items - Image tab 2453
Stock items - Multi-group tab 2455
Stock items - Backorders tab 2456
Use tabs for stock 2457
Create / Edit Stock item types 2460
Create / Edit Stock items - Trading stock - Default 2462
Create / Edit Stock items - Sales 2467
Create / Edit Stock items - Sales (no stock) 2470
Create / Edit Stock items - Purchases 2473
Create / Edit Stock items - Purchases (no stock) 2476
Create / Edit Stock items - Financial entry 2479
Create / Edit Stock items - Option item 2482
Create / Edit Stock items - Option item (no stock) 2485
Create / Edit Stock items - BOM 2488
Create / Edit Stock items - BOM (Production) 2492
Create / Edit Stock items - Linked sale 2514
Delete stock items 2514
Export / Import - Stock items 2516
Export - Stock items (Setup ribbon) 2516
Import - Stock items (Setup ribbon) 2519

Exported stock items - Open text file in spreadsheet 2525
Spreadsheet Export / Import - Stock items 2529
Spreadsheet - Export - Stock items 2531
Spreadsheet - Import - Stock items 2533
Change stock code 2541
Change stock quantites 2541
Backorders 2547
Batches (Journals) 2553
Batch types (setup) 2569
Sales journal / Sales returns journal 2572
Purchase journal / Purchase returns journal 2575
Receipts / Payments journals 2576
Cost of Sales journal 2577
General journal 2579
Specialised journals 2585
Depreciation journal / Amortization journal 2585
Accruals journal 2587
Inventory adjustment journal 2588
Inter-company transactions journal 2589
Point-of-Sales journal 2590
Batch entry selection screen 2591
Batch entry selection screen - Context menu 2593
Batch entry form 2595
Batch entry screen - Context menu 2600
Batch entry - Context menu - Lookup document 2602

Batch entry - Context menu - Lookup document with amount 2603
Batch entry - Context menu - Lookup debtor 2604
Batch entry - Context menu - Lookup creditor 2605
Batch entry - Context menu - Copy 2606
Batch entry - Context menu - Select from account open item list 2607
Batch entry - Context menu - Edit accounts 2608
Accounts lookup - Batches 2610
Batch entry screen - Posted batches tab 2617
Batch setup 2622
F10:Batch setup - Standard tab 2623
F10:Batch setup - Advanced tab 2627
F9:Batch processing options 2629
Abbreviation definition 2634
Change alias (Batch name) 2635
Balance batch 2637
List batch 2640
Post batch 2644
Totals for each period 2651
Edit unposted batch transactions 2652
Erase batch 2653
Insert transactions in a batch 2653
Delete transactions in a batch 2654
Reverse batch (D<-->C) 2655
F9:Batch processing options - Transactions 2658
Generate multiple transactions 2659

Balance debtors with amount < x.xx 2661
Fixed amount to all debtors 2663
Debtors with charge amount 2665
Creditors with charge amount 2667
Interest on overdue debtors 2669
Create receipts (Receipt batches) 2670
Creditor balances to date (Payments batches) 2675
Automatic payments 2677
Automatic receipts 2685
Payroll import 2696
Repeating transactions 2697
Enter / Edit - Repeating transactions 2698
Repeating transactions import 2701
Batch transactions / Journal transactions 2704
Take-on Opening Balances 2706
Take-on General Ledger Opening Balances 2714
Take-on Debtor Opening Balances 2728
Take-on Creditor Opening Balances 2738
Print a Trial Balance for Opening Balances 2748
Sales transactions 2752
Sales journal 2758
Purchase transactions 2771
Purchase journal 2775
Cash transactions 2787
Cashbook transactions 2791

Receipts journal 2792
Payments journal 2803
Petty cash transactions 2813
General journal 2822
Export / Import batch transactions 2826
Export posted batches 2827
Import a posted batch 2828
Write delimited file 2832
Delimited file import 2834
Batch transactions - Spreadsheet Export / Import 2840
Batch transactions - Spreadsheet Export 2840
Batch transactions - Spreadsheet Import 2844
Reverse posted batches 2851
Documents (Sales and Purchases) 2856
Documents setup 2860
Documents setup - Invoices 2865
Documents setup - Credit notes 2867
Documents setup - Quotes 2868
Documents setup - Purchases 2870
Documents setup - Supplier returns 2871
Documents setup - Orders 2873
Documents setup - Change document numbers 2874
Documents setup - Statement setup 2876
Documents setup - General numbers 2877
Documents setup - Change document type names 2879

Documents setup - POS layout 2883
Documents settings - Check list 2886
Steps - Document processing 2888
Salespersons 2888
Document groups 2890
Documents list screen 2893
Document types 2896
Document status 2901
Filter options (Documents) 2902
Single line mode 2906
Show / Hide columns 2908
Group columns 2911
Documents - Graphs 2913
Export - Documents grid 2920
Documents - Context menu 2922
Context menu - Salesperson 2924
Context menu - Set reporting group 1/2 2925
Context menu - Documents 2926
Context menu - Copy document 2936
Context menu - Copy to 2939
Context menu - Convert invoice to an order 2943
Context menu - Create purchase on default supplier1 2945
Context menu - Convert invoice to credit note / supplier return 2947
Context menu - Confirm quotes and orders - Quotes 2951
Context menu - Confirm quotes and orders - Orders 2953

Context menu - Convert quote to one unprocessed invoice per client .. 2955
Context menu - Convert documents to a single document 2956
Context menu - Change account 2960
Context menu - Edit account 2962
Context menu - Create account from document details 2964
Context menu - Redo discount on document 2967
Context menu - Adjustment 2969
Create backorders to deliver 2970
Context menu - Confirm 2974
Context menu - Spreadsheet import 2975
Context menu - Print 2977
Context menu - Print barcodes 2977
Context menu - Print labels 2978
Context menu - Others 2979
Context menu - Others - Import 2979
Context menu - Others - Totals 2982
Context menu - Others - Show details 2983
Context menu - Others - Open item link 2985
Context menu - Document links 2986
Document entry 2987
Document entry form - Unposted documents 2987
Delete transactions / comments in documents 2993
Insert transactions / comments in documents 2994
Tax Inclusive / Exclusive - Documents 2994
Discount - Documents 2997

Insert comments - Documents 3003
Delete all transactions and comments - Documents 3006
Copy transactions / comments - Documents 3007
Item lookup 3010
Item lookup - Default 3012
Item lookup - Fast add 3014
Item lookup - Financial entry 3017
Document entry form - Posted documents 3020
Document entry form - Context menu 3022
Document processing options 3026
Append notes below item 3030
Add Posting and Delete buttons 3033
Default inclusive for documents 3035
Cannot edit price 3035
Cannot edit description 3036
Go to quantity 3036
No backorder 3036
Cannot sell out of stock 3036
Check reference used 3037
Cannot create items 3037
Button lookup 3037
No out of stock message 3040
Use colours for out of stock 3040
SQL only for stock lookup 3040
Merge invoice to orders 3040

Merge items per tax on ledger 3041
Calculate BOM stock 3041
Warning backorders 3041
Limit stock purchase only for default supplier or non 3041
Force stock type check 3041
Auto-post documents on print 3042
Set tax lookup On/Off 3043
Document printing options 3043
Document print confirmation 3045
Printing logo on documents 3046
Document layout files 3050
Document layout files (English) - (static text) 3052
Document layout files - Translatable 3062
NO-TAX Document layout files - Translatable 3068
Document layout file - Delivery notes (Translatable) 3073
Document layout files - POS - Translatable 3079
Document layout files (Netherlands) 3083
Document layout files - Plugins 3093
Quotes 3093
Invoices 3099
Credit notes 3106
Orders 3111
Purchases 3117
Supplier returns 3123
Confirm Quotes and Orders 3128

Confirm Quotes 3129
Confirm Orders 3132
Repeating invoices 3135
Delete documents 3138
Update / Post documents 3142
Reverse posted documents 3147
Export Documents - Export grid 3153
Export / Import documents 3160
Export documents 3160
Import documents 3162
Exported documents in Spreadsheets 3164
Exported documents - Headers files in Spreadsheets 3165
Exported documents - Lines files in Spreadsheets 3169
Calendar / Planner 3171
Calendar- Resource name 3176
Set the Calendar as default 3177
Create / Add events (Appointments) 3178
Create documents - Events (Appointments) 3182
Repeating invoices - Calendar 3184
Invoices - Hours - Calendar 3190
Create invoices - Debtor appointments 3194
Create quotes - Debtor appointments 3195
Bulk time entry 3197
Tasks - Calendar 3202
Add / Create task - Calendar 3203

Edit task - Calendar 3204
Delete task - Calendar 3205
Contacts - Calendar 3205
Add / Create contacts - Calendar 3206
Edit contacts - Calendar 3209
Delete contacts - Calendar 3209
Reminders 3210
Open item link 3210
Open item link - Settings 3214
Open item link - Disable / Enable in batches 3215
Open item link - Totals tab 3217
Open item link - Transactions tab 3220
Adjust payment date 3224
Receive payment 3225
Open item processing - Selected accounts 3226
Open item processing - Ledger accounts 3231
Open item - Debtors 3238
Open item - Debtor - Statements 3243
Open item - Debtor - Receive payments 3248
Open item - Debtors - Link / allocate transactions in batches 3252
Open item - Creditors 3254
Open item - Creditor - Remittance advises 3258
Open item - Creditor - Receive payments 3262
Open item - Creditors - Link / allocate transactions in batches 3267
Open item link - Unposted batches tab 3268

Open item link - Due tab 3270
Open item link - Export to spreadsheets 3275
Open item link - Totals tab - Spreadsheet 3275
Open item link - Transactions tab - Spreadsheet 3279
Open item link - Selected account - Spreadsheet 3285
Bank reconciliation 3289
Hints when doing the bank reconciliation 3293
Reconciling your cashbook with bank statements 3293
Bank charges and items on the bank statement 3300
Bank reconciliation reports 3301
Troubleshooting differences 3303
Bank import plugin 3305
Access control 3306
Access control - Passwords 3308
Create passwords 3310
Delete passwords 3312
Enter passwords (Login) 3313
Access control - Standard security tab 3314
Access control - Reports access tab 3320
Access control - Batches access tab 3321
Access control - Others tab 3325
Access control - Documents tab 3329
Access control - Groups tab 3331
Access control - User tabs 3334
Access control - Log report 3337

Budgets 3340
Enter budget figures (Setup - Accounts) 3341
Enter budget for special events (Setup - Accounts) 3343
Budgets (Reports ribbon) 3345
Budgets - Budget tab (Reports ribbon) 3348
Budgets - Enter budget figures for special events 3350
Budgets - Transactions details tab (Reports ribbon) 3351
Budgets - Pivot tab (Reports ribbon) 3353
Budgets - Pivot - Ledger analyser 3359
Budget listing reports 3370
Budget performance reports 3372
Budget listing - T-Account viewer 3377
Search - Investigator 3379
Payroll - Salaries and wages 3382
Bad debts 3386
Credit control and bad debts 3389
Write-off of Bad debts 3396
Write-off bad debts - Uneconomical to recover 3405
Recovery of bad debts written-off 3413
Provision for Bad debts 3429
Provision for bad debts - Calculation methods 3434
Create Provision for Bad Debts 3436
Decrease Provision for Bad Debts 3440
Increase Provision for Bad Debts 3440
Depreciation 3440

Legislation for depreciation or wear an tear allowances 3447
Common methods to calculate depreciation 3447
Purchase of fixed assets 3449
Fixed Asset Register 3450
Insurance for fixed assets 3452
Disposal of fixed assets 3455
Depreciated fixed assets - Nominal value or Token value principle 3459
Month-end and year-end procedures 3463
Cash basis and accrual basis 3465
Accrual basis adjustments 3468
Accrued income / Outstanding income / Income receivable 3472
Income received in advance / Unearned revenue / Deferred revenue..... 3476
Accrued expenses / Outstanding expenses 3481
Prepaid expenses / Expenses paid in advace 3486
Accrued expenses / Outstanding expenses 3491
Consumable stores on hand 3494
Consumable stores shortages / losses 3498
Correction of Errors / Adjustments 3500
Private expenses 3503
Correction of Errors - General journal / Specific Journals 3514
Month-end procedures 3521
Year-end procedures 3522
Do year end 3525
Year-end closing transactions 3529
Reports (Reports ribbon) 3530

Checking for unposted items 3535
Settings for reports - Number format 3536
Reports - Page headers and Page footers 3540
Reportman reports - Print options 3541
Reportman reports - Send to printer 3542
Reportman reports - Save as PDF 3542
Reportman reports - Printer setup 3545
Reportman output - Send to screen 3551
Reportman output - Print 3555
Reportman output - E-mail 3558
Reportman output - Save metafile as PDF 3559
Reportman output - Save metafile as text file 3564
Reportman output - Save metafile as html 3569
Reportman output - Save metafile as Excel file 3579
Reportman output - Save metafile as csv 3579
Reportman output - Save metafile as bitmap 3582
Reportman output - Save metafile as svg 3586
Reportman output - Save metafile as custom text file 3591
Reportman output - Save metafile as metafiles 3591
Ledger analyser 3592
Ledger analyser - Trial balance 3599
Ledger analyser - Income statement 3608
Ledger analyser - Balance sheet 3614
Ledger analyser - Standard column balances 3621
Ledger analyser - Budget vs actual 3627

Ledger analyser - This year vs last year 3634
Ledger analyser - Unposted batches 3640
Ledger analyser - Column balances - Spreadsheets 3643
Column balances 3644
Column balances - Debit / Credit 3651
Column balances debtors 3655
Column balances debtors - Debit / Credit 3659
Column balances creditors 3662
Column balances creditors - Debit / Credit 3665
SBR (Standard Business Reporting) 3668
Pivot 3677
Zoom in / Zoom out + / - buttons 3689
T-Account viewer 3690
T-Account viewer- Open exported transactions in other Spreadsheet applications 3696
Ledger analyser - Open exported files in other Spreadsheet applications 3704
Reports menu 3709
Ledger (Reports menu) 3714
Budget vs actual (Reports menu) 3715
Ledger - Listing (Reports menu) 3718
Ledger - Transactions (Reports menu) 3721
Ledger - Transactions (Reports menu) 3721
Ledger - Transactions - Standard / Extra details (Reports menu) 3726
Debtors (Reports menu) 3734
Debtor statements 3735

Debtor statements (Reports menu) 3737
Debtor statements - Outstanding (Reports menu) 3740
Debtors - Age analysis 3743
Debtors - Age analysis - Balances detail 3744
Debtors - Age analysis - Balances detail (open item) 3747
Debtors - Age analysis - Balances 3752
Debtors - Listing (Reports menu) 3753
Debtor listing - Contacts (Reports menu) 3754
Debtor listing (Reports menu) 3756
Debtor listing - Delivery address (Reports menu) 3757
Debtor listing - Postal address (Reports menu) 3759
Debtor listing - List details (Reports menu) 3761
Debtor listing - Credit Control Listing (Reports menu) 3764
Debtor listing - Tax and Company Registration Numbers (Reports menu) ... 3766
Debtors - Print labels (Reports menu) 3768
Debtors - Transactions (Reports menu) 3770
Debtors - Transactions (Reports menu) 3771
Debtors - Transaction list reports (Reports menu) 3774
Debtors - Transactions - Standard / Extra details (Reports menu) 3782
Creditors (Reports menu) 3786
Creditor remittance advises 3786
Creditor remittance advises (Reports menu) 3787
Creditor remittance advises - Outstanding (Reports menu) 3790
Creditors - Age analysis 3793

Creditors - Age analysis - Balances detail 3793
Creditors - Age analysis - Balances detail (open item) 3797
Creditors - Age analysis - Balances 3802
Creditors - Listing (Reports menu) 3803
Creditor listing - Contacts (Reports menu) 3804
Creditor listing (Reports menu) 3806
Creditor listing - Delivery address (Reports menu) 3807
Creditor listing - Postal address (Reports menu) 3809
Creditor listing - List details (Reports menu) 3811
Creditor listing - Credit Control Listing (Reports menu) 3814
Creditor listing - Tax and Company Registration Numbers (Reports menu) . 3816
Creditors - Print labels (Reports menu) 3818
Creditors - Transactions (Reports menu) 3820
Creditors - Transactions (Reports menu) 3820
Creditors - Transaction list reports (Reports menu) 3823
Creditors - Transactions - Standard / Extra details (Reports menu) 3829
Contacts (Reports menu) 3833
Batch entry (Reports menu) 3835
Batch report - Documents (Reports menu) 3836
Batch transactions per period (Reports menu) 3839
Tax (Reports menu) 3843
Tax per period (Reports menu) 3844
Tax report - Reference / Document no. (Reports menu) 3848
Tax list debtor with taxid (Reports menu) 3850

Tax list creditor with taxid (Reports menu) 3852
Tax - Transactions (Reports menu) 3853
Stock (Reports menu) 3856
Stock - Reorder (Reports menu) 3858
Stock - Reorder (Reports menu) 3858
Stock - Reorder - Current stock levels (Reports menu) 3860
Stock - Print labels (Barcodes) (Reports menu) 3862
Stock - Stock item listing (Reports menu) 3864
Stock - Stock item listing - All selling prices (Reports menu) 3864
Stock - Stock item listing (Reports menu) 3866
Stock - Stock item listing - Tax classes (Reports menu) 3868
Stock - Backorder (Reports menu) 3869
Stock - In / Out (Reports menu) 3871
Stock - In / Out - Documents (Reports menu) 3872
Stock - In / Out (Reports menu) 3878
Documents (Reports menu) 3881
Document listing (Reports menu) 3883
Document listing per account (Reports menu) 3884
Document listing per account - Sales documents (Reports menu) 3885
Document listing per account - Purchase documents (Reports menu) .. 3886
Unprinted document listing (Reports menu) 3889
Unprinted document listing - Sales documents (Reports menu) 3889
Unprinted document listing - Purchase documents (Reports menu) 3891
Sales - (Reports menu) 3893
Sales - Invoices (Reports menu) 3894

Invoices - Debtors (Reports menu) 3894
Invoices - Sales (Reports menu) 3896
Invoices - Items (Reports menu) 3898
Sales - Credit notes (Reports menu) 3899
Credit notes - Debtors (Reports menu) 3899
Credit notes - Sales (Reports menu) 3900
Credit notes - Items (Reports menu) 3902
Sales - Quotes (Reports menu) 3903
Quotes - Debtors (Reports menu) 3904
Quotes - Sales (Reports menu) 3905
Quotes - Items (Reports menu) 3906
Sales analysis (Reports menu) 3908
Quotes per period (Reports menu) 3909
Invoices per period (Reports menu) 3912
Credit notes per period (Reports menu) 3914
Sales per period (Reports menu) 3917
Sales per product (Reports menu) 3920
Purchases (Reports menu) 3924
Purchase - Purchases (Reports menu) 3926
Purchases - Creditors (Reports menu) 3926
Purchases - Items (Reports menu) 3927
Purchases - Purchases (Reports menu) 3929
Purchase - Orders (Reports menu) 3930
Orders - Creditors (Reports menu) 3930
Orders - Items (Reports menu) 3932

Orders - Purchases (Reports menu) 3933
Purchase - Supplier returns (Reports menu) 3934
Supplier returns - Creditors (Reports menu) 3934
Supplier returns - Items (Reports menu) 3936
Supplier returns - Purchases (Reports menu) 3937
Purchase analysis (Reports menu) 3938
Purchases and Supplier returns per period (Reports menu) 3940
Orders per period (Reports menu) 3943
Purchases per period (Reports menu) 3946
Supplier returns per period (Reports menu) 3949
Purchases per product (Reports menu) 3951
Calendar (Reports menu) 3955
Company info (reports menu) 3958
Currencies (Reports menu) 3961
Plugins (Reports menu) 3962
Spreadsheets 3963
Spreadsheet reports 3964
Spreadsheet - Debtors 3966
Spreadsheet - Creditors 3966
Spreadsheet - Transactions per period 3967
Spreadsheet - General ledger - Budget - Column Balances 3969
Spreadsheet - General ledger - Budget - Column balances - Reporting group 1 3970
Spreadsheet - General ledger - Budget - Column balances - This year . 3971
Spreadsheet - General ledger- Column balances 3973

Spreadsheet - General ledger - Column balances - Reporting group 1 . 3973
Spreadsheet - General ledger- Column balances - This year 3974
Spreadsheet - Sales analysis 3976
Spreadsheet - Sales analysis - Stock movement 3976
Spreadsheet - Sales analysis - Sales per period 3978
Spreadsheet sales 3979
User reports (Reports ribbon) 3979
Custom reports 3982
Tax (Tax codes - Tax rates) 3984
Debtors 3989
Debtors - Outstanding 3989
Debtors - Outstanding - Due date 3990
Debtors - Outstanding - Outstanding at date 3993
Creditors 3996
Creditors - Outstanding 3996
Creditors - Outstanding - Due date 3997
Creditors - Outstanding - Outstanding at date 4000
Graphs 4002
Graphs per week 4003
Graph - Profit / Loss per week 4004
Graph - Debtors per week 4006
Graph - Creditors per week 4009
Sales - Graphs per week 4011
Graph - Sales (Invoices - Credit notes) per week 4012
Graph - Invoices per week 4016

Graph - Credit notes per week 4020
Graph - Quotes per week 4024
Purchases - Graphs per week 4027
Graph - Purchases - (Purchases - Supplier returns) per week 4029
Graph - Purchases per week 4033
Graph - Supplier returns per week 4037
Graph - Orders per week 4041
Graphs per month 4044
Graph - Profit / Loss per month 4045
Graph - Debtors per month 4047
Graph - Creditors per month 4050
Sales - Graphs per month 4052
Graph - Sales (Invoices - Credit notes) per month 4053
Graph - Invoices per month 4057
Graph - Credit notes per month 4061
Graph - Quotes per month 4065
Purchases - Graphs per month 4068
Graph - Purchases - (Purchases - Supplier returns) per month 4070
Graph - Purchases per month 4074
Graph - Supplier returns per month 4078
Graph - Orders per month 4082
Report designer (Reportman) 4085
Report man interface options 4091
Reports - File structure 4095
Reports - systemreports - Reports menu file names 4099

Reports - excelreports - Spreadsheet reports menu file names 4117
Reports - userreports - User reports menu fille names 4119
Reports - userreports - Graphs file names 4122
Report designer menu structure 4129
Report designer - Add / Insert objects 4136
Report designer - Edit / Move / Align objects 4137
Report designer - Add / Insert expressions 4138
Report designer - Report Structure and Data 4140
Report designer - Structure tab 4140
Report designer - Data tab 4141
Report designer - Data objects 4142
Report designer - Data access configuration 4142
Report designer - Writing SQL 4144
Report designer - Add a Dataset 4146
Report designer - View Dataset 4148
Report man interface 4149
Reportman output 4152
Reportman - Select test document id 4154
Reportman output - Transparent setting 4156
Report designer - Customise layout files 4159
Designing custom layout files for documents 4160
Report designer - Company logo 4161
Report designer - Add unit descriptions to layout files 4165
Reportman - Create new empty reports from Empty report 4169
Page header - COMPANYDATA 4173

Page footer - Information 4180
Reportman - Save reports 4184
Reportman - Create new blank reports from New report 4184
Reportman - Add COMANYDATA Dataset 4186
Reportman - Add footer data 4198
Reportman - Print settings 4201
Reportman - Two pass report setting 4201
Reportman - Force print setting 4202
Reportman - Print-only if data is available 4203
Reportman - Add content - Detail 4204
Reportman - Translatable label expressions 4223
Reportman - Auto Expand / Auto Contract setting 4227
Parameters (Report options) 4229
Parameters - Sort sequences 4231
Parameters - Move / resize 4249
Parameters - Lookup 4251
Parameters - Groups 4279
Expressions - Add Account type 4287
Expressions - Add line break / new line 4290
Add new report to User reports menu 4294
Rename reports 4297
Delete reports 4300
Create a new report from an existing report 4302
Reportman - References - Data structure 4318
Reportman - References - Groups 4327

Reportman - SQL Changelog for MSSQL 4330
Multi-currency 4330
Cost centres 4338
Projects 4408
Blockchain 4476
Plugins 4483
Activate plugins 4487
Register plugins 4490
Plugins menu (Setup ribbon) 4491
Plugins menu - Document plugins 4495
Document e-mail pro plugin 4498
Document Export / Import plugin 4543
Price agreement plugin 4549
Subscriptions plugin 4565
Activate subscriptions 4567
Setup subscriptions 4570
Process subscriptions 4574
Process subscriptions - E-mail setup - configuration 4581
Process subscriptions warnings - E-mail 4587
Process subscriptions - E-mail 4595
Processed subscriptions - Invoices and Quotes 4607
Subscriptions - Reports 4611
Subscriptions - Copy / Paste - Debtors 4615
Subscriptions - Search options 4617
Plugins menu - External system links 4623

Plugins menu - Financial tools 4626
Activa plugin 4630
Activate the Activa plugin and setup 4634
Add Fixed assets to the Activa plugin 4638
Process Fixed assets in the Activa plugin 4642
Activa reports 4651
Types of fixed assets 4659
Methods to calculate depreciation 4662
Activa transactions 4673
Activa transactions in Ledger analyser 4678
Activa transactions in the T-Account viewer 4680
Charter plugin 4685
Drill Down plugin 4690
Remittance plugin 4709
Plugins menu - Generic plugins 4733
Multi-user Agenda plugin 4736
*Freefields plugin 4749
Multimedia plugin 4763
CRM plugin 4790
Plugins menu - Point-of-Sale 4800
POSDisplay plugin 4804
RetailPOS plugin 4806
HorecaPOS 4808
Plugins menu - Stock plugins 4810
Serials-Batches-Location plugin 4812

Stock check 4835
QuickOrder 4849
Plugins menu - Tools 4864
SQL Browser plugin 4868
Other Plugins / Products 4887
Support products 4898
Field length 4903
Shipping plugins 4905
E-mail plugins 4907
Bank import plugin 4909
Bank import plugin - Petty cash transactions (Manual entry) 4946
Bank import plugin - Petty cash transactions (Import - CSV) 4954
Petty cash transactions (Import - CSV) 4974
Multi-user plugins 4991
Multi-user Windows install 4994
Multi-user Linux Server install 5007
Translations - Plugins - Dynareg 5012
Dynareg plugins 5041
Dynareg - Email address per document 5043
Dynareg - Delivery dates 5046
Dynareg - Numbers based on date and date 2 5049
Dynareg - Checkbox in documents 5049
Dynareg - Additional field for an account in documents 5051
Dynareg - Payment discount invoice plugin 5051
Dynareg - Shipping costs separately on invoice plugin 5067

Dynareg - Bruto margin in documents plugin 5083
Dynareg - Selling prices in purchase documents plugin 5084
Dynareg - Free lookup 5085
Dynareg - Inactive items 5086
Dynareg - Transitional data 5088
Dynareg - Extra document types 5089
Dynareg - Extra documnent types - BUG - Stock items 5099
Dynareg - Stock in and Stock out document type 5110
Dynareg - Extra stock of correction document (Stock in / Stock out) document type) 5126
Dynareg - Stock in document type 5137
Dynareg - Numbers based on multiplication factor 5149
Dynareg - Numbers based on division factor 5152
Dynareg - Limit by Creditor with selection list plugin 5155
Multi-language accounts 5157
Multi-language setup 5159
Add Multi-language users 5160
Add Multi-language groups 5162
Translate Multi-language groups 5164
Translate Multi-language types 5168
Translate Multi-language batch types 5173
Translate Multi-language chart of accounts 5176
Translate Multi-language stock descriptions 5177
Multi-Language reports 5179
Multi-language - Chart of accounts listing 5181

Multi-language - Trial balance 5184
Print documents in Debtor (customer / client) language 5191
Print documents in Creditor (supplier/ vendor) language 5193
Workflow plugin 5195
Taxonomies and XBRL 5210
Database types 5215
Firebird databases 5215
Firebird install 5216
FlameRobin install 5222
Flame Robin - Firebird connection 5226
Firebird database upgrade 5230
Microsoft SQL Server (MSSQL) Databases 5236
Create Set of Books (Advanced - MSSQL) 5237
MSSQL Server's backup and restore options 5265
Development - MySQL and Postgress databases 5266
Banking abbreviations / acronyms in osFinancials 5266

AI / ETL

AI/ETL in osFinancials5.1/TurboCASH5-3 - Roadmap

The combination of OpenAI and ETL (Extract, Transform, Load) for the Imports of bank statements in the Bank import plugin is introduced in osFinancias5.1.0.0.233.

What is ETL?

ETL stands for Extract, Transform, Load. It's a process used in data integration to:

- Extract: Pull data from one or multiple sources (e.g., databases, files, APIs).
- Transform: Clean, organize, and convert the data into a consistent format.
- Load: Store the transformed data in a target system (e.g., data warehouse, data lake).

Resources

Activate OpenAI in osFinancialos5.1/TurboCASH5-3

To activate OpenAI and ETL (Extract, Transform, Load) functionality in osFinancials5.1 or TurboCASH5-3, follow these steps:

1. Open the Application:
2. Launch osFinancials5.1 or TurboCASH5-3 on your local machine.
3. Navigate to Setup:
    - Access Company Info: In the Setup menu, click on Setup → Company info (Setup ribbon). This will open a window where you can configure company-specific information and settings.
    - Go to the Options Tab: In the Company Info window, navigate to the Options tab. This is where you can enter your OpenAI credentials.



- Enter OpenAI Credentials:
  - § OpenAI Token: Enter your valid OpenAI API token. This token is provided when you subscribe to OpenAI's services.
  - § OpenAI Company Key: Enter your OpenAI company key, which is also provided as part of your OpenAI subscription.
  - § Save the Settings:
  - § Click Save to store your OpenAI token and OpenAI company key. Then, click OK to close the window.

4. Credentials Storage: Your OpenAI token and company key will be securely stored in the Registry of your local machine under the osFinancials5 folder. This allows the credentials to be used across any Set of Books in both osFinancials5.1 and TurboCASH5-3.
5. Verification: Once the credentials are saved, the OpenAI and ETL functionalities should be activated and ready for use within the application.

Important Notes:

- Ensure that your OpenAI token and company key are valid and active. If you encounter any issues, double-check the credentials and your OpenAI subscription status.

- The credentials are stored locally on your machine, so if you move to a different computer, you will need to re-enter the credentials on that machine.

By following these steps, you should be able to successfully activate OpenAI and ETL functionalities in osFinancials5.1 or TurboCASH5-3.

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

AI/ETL - Bank import

AI / ETL / Bank statements

The bank statement is indeed a form of ETL (Extract, Transform, Load). Let me break it down and explain how your system aligns with the ETL process:

What is ETL?

ETL stands for Extract, Transform, Load. It's a process used in data integration to:

- Extract: Pull data from one or multiple sources (e.g., databases, files, APIs).
- Transform: Clean, organize, and convert the data into a consistent format.
- Load: Store the transformed data in a target system (e.g., data warehouse, data lake).

How Your System Fits Bank Statement files into ETL:

1. Extract:

- Your system extracts data from bank statement files (e.g., OFC, MT940) stored in a specific directory:

  C:\TCASH5-3\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS\2024-03-Bank-Statement-ABC-Bank.ofc

- These files contain raw transaction data that needs to be processed.

2. Transform:

- The system uses OpenAI's language model to transform the raw data into a structured JSON format.
- Specific transformations include:
  - Parsing dates, amounts, and descriptions.
  - Reversing debit and credit values based on instructions.
  - Handling missing values (e.g., using `0.00` for numeric fields and empty strings for text fields).
- The transformation is guided by system prompts and user prompts stored in the root directory of your osFinancials5.1 or TurboCASH5-3 installation folder:
  - `accounting_banksystemprompt.txt`
  - `accounting_bankuserprompt.txt`

3. Load:

- The transformed data (in JSON format) is stored or made available for further use in your financial system (e.g., `osFinancials5.1` or `TurboCASH5-3`).
- This data can then be used for reporting, analysis, or integration with other systems.

Your System as an ETL Process:

ETL Stage	*Your System Example*
Extract	*Read raw data from OFC/MT940 files in the BANK-STATEMENTS folder.*
Transform	*Use OpenAI to convert raw data into JSON, reverse debit/credit, and handle missing values.*
Load	*Store the JSON output in the system for further use (e.g., financial reporting).*

Why This is ETL:

1. Data Integration: You're combining data from bank statements into a single, consistent format (JSON).
2. Data Cleaning: You're handling missing values, reversing debit/credit, and ensuring data consistency.

3. Automation: The process is automated using AI, reducing manual effort and improving accuracy.
4. Target System: The transformed data is loaded into your financial system for storage and analysis.

Example Workflow:

Input (Extract):

Raw OFC file (`2024-03-Bank-Statement-ABC-Bank.ofc`):

```
:61:2301010101D100,NTRFNONREF//Payment for services
:61:2301050101C200,NTRFNONREF//Refund
```

Transformation:

Parse the data.

Reverse debit (`D100`) to credit and credit (`C200`) to debit.

Handle missing fields (e.g., `emailaddress`).

Output (Load):

json

```
[
  {
     "transactionDate": "01-03-2024",
     "amountDebit": 0.00,
     "amountCredit": 100.00,
      "bankAccountNumber": "NL91ABNA0417164300",
     "emailaddress": "",
     "description": "Payment for services"
  },
  {
     "transactionDate": "05-03-2024",
     "amountDebit": 200.00,
     "amountCredit": 0.00,
      "bankAccountNumber": "NL91ABNA0417164300",
     "emailaddress": "",
     "description": "Refund"
```

```
  }
]
```

Next Steps:

- Refine the ETL Process:
  - Update the prompts (`accounting_banksystemprompt.txt` and `accounting_bankuserprompt.txt`) to improve accuracy.
  - Test with different bank statement formats (e.g., MT940, OFC).
- Automate Further: Schedule the ETL process to run automatically when new bank statements are added to the folder.
- Integrate with Downstream Systems: Load the JSON data into a database, data warehouse, or reporting tool for further analysis.



Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

AI/ETL - Chart of Accounts

The combination of OpenAI and ETL (Extract, Transform, Load) can be extended to support a wide range of functionalities in osFinancials5.1/TurboCASH5-3, including bank statements

Chart of Accounts

- Exports and Imports (e.g., Chart of Accounts, Debtors, Creditors, Stock Items/Inventory, Journals, Documents).
- Integration with Other Accounting Software (e.g., migrating data from other systems into osFinancials5.1/TurboCASH5-3).

Here's how OpenAI and ETL can be developed and applied to these functionalities:

Chart of Accounts

Use Case:

- Migrate or synchronize the Chart of Accounts from another accounting software (e.g., QuickBooks, Xero, Sage) into osFinancials5.1/TurboCASH5-3.
- Clean and transform the data to match the required format.

ETL Process:

- Extract: Pull the Chart of Accounts data from the source system (e.g., Excel, CSV, or API).
- Transform: Use OpenAI to:
    - Map account codes, names, and types to the target format.
    - Handle discrepancies (e.g., missing fields, different naming conventions).

- Ensure compliance with osFinancials5.1/TurboCASH5-3 requirements.

· Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

Example:

- Input (Extract): Chart of Accounts from QuickBooks (CSV):

```
Account Code,Account Name,Account Type
1001,Cash,Bank
2001,Accounts Payable,Liabilities
```

- Transformation (OpenAI):
  - Map `Account Code` to `Code`, `Account Name` to `Description`, and `Account Type` to `Category`.
  - Handle any missing or mismatched fields.
- Output (Load): Transformed data ready for import:

```
Code,Description,Category
1001,Cash,Bank
2001,Accounts Payable,Liabilities
```

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

AI/ETL - Debtors/Creditors

AI/ETL - Debtors/Creditors

The combination of OpenAI and ETL (Extract, Transform, Load) can be extended to support a wide range of functionalities in osFinancials5.1/TurboCASH5-3, including debtors/creditors:

Use Case:

- Import or export Debtors (Customers) and Creditors (Suppliers) data.
- Clean and standardize data from different sources.

ETL Process:

- Extract: Pull data from Excel, CSV, or other accounting software.
- Transform: Use OpenAI to:
  - Map fields like `Customer Name`, `Address`, `Contact Details`, and `Payment Terms`.
  - Standardize formats (e.g., phone numbers, addresses).
  - Handle duplicates or inconsistencies.
- Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

Example:

- Input (Extract): Debtors data from Xero (Excel):

```
Name,Email,Phone,Balance
John Doe,john@example.com,123-456-7890,1000.00
```

- Transformation (OpenAI):
  - Map `Name` to `Customer Name`, `Email` to `Contact Email`, Phone to `Contact Phone`, and `Balance` to `Outstanding Balance`.
  - Standardize phone numbers (e.g., `123-456-7890` to `+1 123 456 7890`).
- Output (Load): Transformed data ready for import:

```
Customer Name,Contact Email,Contact Phone,Outstanding Balance
John Doe,john@example.com,+1 123 456 7890,1000.00
```

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

AI/ETL - Stock/Inventory

The combination of OpenAI and ETL (Extract, Transform, Load) can be extended to support a wide range of functionalities in osFinancials5.1/TurboCASH5-3, including stock/inventory:

Use Case:

- Import or export Inventory/Stock Items data.
- Clean and transform data from suppliers or other systems.

ETL Process:

- Extract: Pull data from Excel, CSV, or supplier files.
- Transform: Use OpenAI to:
  - Map fields like `Item Code`, `Description`, `Unit Price`, and `Quantity`.
  - Handle unit conversions (e.g., packs to units).
  - Standardize descriptions and categories.
- Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

Example:

- Input (Extract): Inventory data from supplier (CSV):

```
SKU,Product Name,Price,Units
12345,Widget A,10.00,100
```

- Transformation (OpenAI):
  - Map SKU to `Item Code`, `Product Name` to `Description`, `Price` to `Unit Price`, and `Units` to `Quantity`.
  - Convert prices to the correct currency format.

- Output (Load): Transformed data ready for import:

> *Item Code,Description,Unit Price,Quantity*
>
> *12345,Widget A,10.00,100*

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

AI/ETL - Documents

AI/ETL - Documents

The combination of OpenAI and ETL (Extract, Transform, Load) can be extended to support a wide range of functionalities in osFinancials5.1/TurboCASH5-3, including documents.

Sales documents (invoices, credit notes, quotes) and purchase documents (purchases, supplier returns, orders)

The OpenAI and ETL (Extract, Transform, Load) approach can be extended to handle sales documents (e.g., invoices, credit notes, quotes) and purchase documents (e.g., purchases, supplier returns, orders). This would allow you to automate the processing, transformation, and integration of these documents into osFinancials5.1/TurboCASH5-3.

1. Sales Documents:

a. Invoices:

- Use Case: Import or export customer invoices from other systems or Excel.
- ETL Process:
  - Extract: Pull invoice data from Excel, CSV, or other systems.
  - Transform: Use OpenAI to:
    - Map fields like `Invoice Number`, `Customer Code`, `Date`, `Total Amount`, and `Line Items`.

        - Handle currency conversions, tax calculations, and missing fields.
    - Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

b. Credit Notes:

- Use Case: Import or export credit notes issued to customers.
- ETL Process:
    - Extract: Pull credit note data from Excel, CSV, or other systems.
    - Transform: Use OpenAI to:
        - Map fields like `Credit Note Number`, `Customer Code`, `Date`, `Total Amount`, and `Reason`.
        - Ensure the credit note references the correct invoice.
    - Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

c. Quotes:

- Use Case: Import or export customer quotes.
- ETL Process:
    - Extract: Pull quote data from Excel, CSV, or other systems.
    - Transform: Use OpenAI to:
        - Map fields like `Quote Number`, `Customer Code`, `Date`, `Valid Until`, and `Line Items`.
        - Handle currency conversions and missing fields.
    - Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

---

2. Purchase Documents:

a. Purchases:

- Use Case: Import or export purchase orders or supplier invoices.
- ETL Process:
    - Extract: Pull purchase data from Excel, CSV, or other systems.
    - Transform: Use OpenAI to:
        - Map fields like `Purchase Order Number`, `Supplier Code`, `Date`, `Total`

`Amount`, and `Line Items`.

- Handle currency conversions, tax calculations, and missing fields.

- Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

b. Supplier Returns:

- Use Case: Import or export supplier return documents.
- ETL Process:
  - Extract: Pull supplier return data from Excel, CSV, or other systems.
  - Transform: Use OpenAI to:
    - Map fields like `Return Number`, `Supplier Code`, `Date`, `Total Amount`, and `Reason`.
    - Ensure the return references the correct purchase order or invoice.
  - Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

c. Orders:

- Use Case: Import or export purchase orders.
- ETL Process:
  - Extract: Pull order data from Excel, CSV, or other systems.
  - Transform: Use OpenAI to:
    - Map fields like `Order Number`, `Supplier Code`, `Date`, `Total Amount`, and `Line Items`.
    - Handle currency conversions and missing fields.
  - Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

Example Workflow for Invoices:

Input (Extract):

Raw invoice data from Excel:

```
Invoice Number,Customer Code,Date,Total Amount,Line Items
INV-001,CUST-001,2024-01-01,1000.00,"Product A:500.00,Product B:500.00"
```

Transformation (OpenAI):

- Map `Invoice Number` to `Document Number`, `Customer Code` to `Customer ID`, `Date` to `Invoice Date`, and `Line Items` to individual line items.
- Handle currency conversions (if needed).
- Ensure tax calculations are applied correctly.

Output (Load):

Transformed data ready for import:

json

```
{
  "Document Number": "INV-001",
  "Customer ID": "CUST-001",
  "Invoice Date": "2024-01-01",
  "Total Amount": 1000.00,
  "Line Items": [
    {
      "Product": "Product A",
      "Amount": 500.00
    },
    {
      "Product": "Product B",
      "Amount": 500.00
    }
  ]
}
```

Example Workflow for Purchase Orders:

Input (Extract):

Raw purchase order data from CSV:

```
Order Number,Supplier Code,Date,Total Amount,Line Items
PO-001,SUPP-001,2024-01-01,1500.00,"Product X:750.00,Product Y:750.00"
```

Transformation (OpenAI):

- Map `Order Number` to `Document Number`, `Supplier Code` to `Supplier ID`, `Date` to `Order Date`, and `Line Items` to individual line items.
- Handle currency conversions (if needed).
- Ensure tax calculations are applied correctly.

Output (Load):

Transformed data ready for import:

json

```
{
  "Document Number": "PO-001",
  "Supplier ID": "SUPP-001",
  "Order Date": "2024-01-01",
  "Total Amount": 1500.00,
  "Line Items": [
    {
      "Product": "Product X",
      "Amount": 750.00
    },
    {
      "Product": "Product Y",
      "Amount": 750.00
    }
  ]
}
```

Benefits of Using OpenAI and ETL for Sales and Purchase Documents:

1. Automation: Reduces manual effort in processing invoices, credit notes, quotes, purchase orders, and supplier returns.
2. Flexibility: Handles various file formats and data sources.
3. Accuracy: Ensures data is clean, consistent, and compliant with osFinancials5.1/TurboCASH5-3

requirements.

4. Scalability: Can process large volumes of documents from multiple sources.

Next Steps:

1. Define Requirements: Identify the specific fields, formats, and rules for each document type (e.g., invoices, purchase orders).
2. Develop Prompts: Create system and user prompts to guide the OpenAI model for each use case.
3. Test the ETL Process: Test with sample data to ensure accuracy and reliability.
4. Deploy and Automate: Integrate the ETL process into your workflow for ongoing use.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

AI/ETL - Journals (Batches)

AI/ETL - Journals (Batches)

The combination of OpenAI and ETL (Extract, Transform, Load) can be extended to support a wide range of functionalities in osFinancials5.1/TurboCASH5-3, including journals/batches:

Use Case:

- Import or export Journal Entries from other accounting software or Excel.
- Clean and transform journal data to match osFinancials5.1/TurboCASH5-3 requirements.

ETL Process:

- Extract: Pull journal data from Excel, CSV, or other systems.
- Transform: Use OpenAI to:
  - Map fields like `Date`, `Account Code`, `Debit`, `Credit`, and `Description`.
  - Ensure debits and credits are balanced.
  - Handle missing or inconsistent data.
- Load: Import the transformed data into osFinancials5.1/TurboCASH5-3.

Example:

- Input (Extract): Journal data from Sage (Excel):

  Date,Account,Debit,Credit,Narrative

  2024-01-01,1001,500.00,0.00,Sales

- Transformation (OpenAI):
  - Map `Date` to `Transaction Date`, `Account` to `Account Code`, `Narrative` to `Description`.
  - Ensure debits and credits are correctly formatted.
- Output (Load): Transformed data ready for import:

  Transaction Date,Account Code,Debit,Credit,Description

  2024-01-01,1001,500.00,0.00,Sales

Benefits of Using OpenAI and ETL for These Functionalities:

- Automation: Reduces manual effort in data migration and integration.
- Flexibility: Handles various file formats and data sources.
- Accuracy: Ensures data is clean, consistent, and compliant with osFinancials5.1/TurboCASH5-3 requirements.
- Scalability: Can process large volumes of data from multiple sources.

Next Steps:

- Define Requirements: Identify the specific fields, formats, and rules for each functionality (e.g., Chart of Accounts, Debtors, Inventory).
- Develop Prompts: Create system and user prompts to guide the OpenAI model for each use case.

- Test the ETL Process: Test with sample data to ensure accuracy and reliability.
- Deploy and Automate: Integrate the ETL process into your workflow for ongoing use.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Release notes

Saturday, 24 May 2025- 01:50:48

TurboCASH5-3 - Release-Candidate-10

Languages - FIXED Typo in 27 English languages

- Label id 2047 - Name -> Last name - Contacts - information for Debtors Creditors aligns with First name. (Also in Afrikaans)
- Label ID 3690 - Enter email adress seperate with ; => Enter email address separate with ;
- Label ID 906000 - In spite of previous reminders, according to our records your account is still overdue. => Despite previous reminders, according to our records your account is still overdue.
- Label ID 1398 - Comfirm printing => Confirm printing
- Label ID 1959 - Authentification failed! => Authentication failed!
- Label ID 2251 - No Window's timers are available! => No Windows timers are available!
- Label ID 3073 - Group still has nesteled groups remove them first! => Group still has nested groups remove them first!
- Label ID 3078 - Account code already exist! => Account code already exists!
- Label ID = 3276 = Bank import extra link functions. Enter bank account for exact match on account. Enter text with a # prefix to look inside a imported bank line to see if the text is in that string. Text will be searched in the uppercase. => Bank import extra link functions. Enter bank account for exact match on account. Enter text with a # prefix to look inside an imported bank line to see if the text is in that string. Text will be searched in the uppercase.
- Label ID = 3349 - There is document input asossiated with this project! Do you wish to continue ? All project data will be lost! => There is document input associated with this project! Do you wish to

continue ? All project data will be lost!

- Label ID 3350 - There is transaction input asossiated with this project! Do you wish to continue ? All project data will be lost! => There is transaction input associated with this project! Do you wish to continue ? All project data will be lost!
- Label ID 3364 - No remaker entered process aborted! => No remark entered, process aborted!
- Label ID 3424 - Delete not local (Books this PC can not find) = Delete not local (Books this PC cannot find)
- Label ID 3471 - I have read this instruction and I understand the action! => I have read this instruction, and I understand the action! (added a comma)
- Label ID 2935 - Poll display => Pole display
- Label ID 2936 - Poll display connected => Pole display connected
- Label ID 2938 - Default POS Poll => Default POS Pole
- Label ID 2939 - 2 X 20 chars POS Poll => 2 X 20 chars POS Pole
- Arabic.dfm updated - Full translation in the accounting context relating to osFinancials5.1/TurboCASH5-3.

Std Bank account no.

4-DIGIT-BOOKS - Fixed TADE => TRADE in the Chart of Accounts in the following Sets of Books:

- 4-EN-SOUTH-AFRICA-GENERIC
- 4-EN-UK-GENERIC

TurboCASH5-3 - Release-Candidate-7

Compiled TurboCASH5-3-Release-Candidate-7 - after POS Fixes.

Updated osFinancials5.1.0.233 (from osFinancials5.1.0.227)

ADDED / Include OpenAI

OpenAI import on bank import form. Set the values in Setup -> Company data second tab and press save.

FIXED : tcash.ini files AppName=TurboCASH5-2025

AppName=TurboCASH5 change from TurboCASH5-2025 in all Language files of the TurboCASH5-MERGE

Install sorce - Labels cut off in some screens and in some languages - Also changed in Inno Setup script.

FIXED POS : Compiled TurboCASH5-Release-Candidate-6 with the POS invoice now displaying

Works can see screen and interface is now displaying.

FIXED issues:

- POS Invoice discount - Not working - For example, if add 10% discount it is not displays on the POS Invoice screen and Payment does not reduce discount.
- Quantities entered e.g. 2 does not change the selling price - x2 showing in Quantity column - Payment = 1 item only.
- Printing POS Invoice / Reprinting POS Invoices / Setup -> POS - Cannot print Invoices or test printer - Prints blank with 0kb - I use Microsoft print PDF and cannot open these prints in Edge web browser. Think the last time got the Invoices printing was in TurboCASH4/osFinancials4.

FIXED : Budgets MSSQL Error

Entering Budgets (Reports ribbon) and click on the Apply to selection button produces the following error:

> Incorrect syntax near 'a'.

On Setup → Accounts you can enter budgets

Adjusted Settings.dfm file to Exclude extra EN-UK (Blue font) Set of Books

Adjusted the Settings.dfm file in the bin folder. Upon install the EN-UK Set of Books will no longer display in the BLUE FONT COLOR as a duplicate of the normal EN-UK Set of books installed via the Install script from the .../bin/Repository folder.



Installation

Install file : TurboCASH5-2025-Release-Candidate-4-setup.exe = *Download from Sourceforge*

FIXED Install Script - Install no overwrite message displayed in a clean install. NOTE: This seems to be correct - When installing TurboCASH5-2025-Release-Candidate-4 in the same existing directory you may receive two messages:

1. Directory exists - Confirm to install in the existing directory or select no to choose a different directory.
2. Set of Books exists - Confirm to keep the existing Set of Books or choose to overwrite (replace the files in the Set of Books.

Needs updates in next release - TurboCASH5-2025-Release-Candidate-5-setup.exe - To Update install source

Compile of TutboCASH5-2025-Release-Candidate-4 not compiled on TC5-2025-MERGE-Install -Source-Release-Candidate-3.7z - Lots of fixes were done and hours spent on these between 18 December 2024 and 25 December 2025.

Updated Sets of Books (Firebird Databases)

Updated the Year to 2025

Set the RESOURCES from osFinancials to TurboCASH in the Calendar for TurboCASH installtion.

Updated Setsof Books in the bin folder:

- 4-DIGIT-BOOKS
- CUSTOMISE-BOOKS-ADVANCED

Updated Help file (EngHelp.chm)

- Updated the Help file to include TurboCASH in text e.g. osFinancials5/TurboCASH5. The reason for this is to get it ready for ChatGPT Search and other AI searches on the web.
- Release Candidate 3 source = Wednesday, 25 December 2024 - 03:55:54 - osFinancials5/TurboCASH5 - Business Class - Help
- Help file outdated = Wednesday, 18 December 2024 - 06:23:01 - osFinancials5/TurboCASH5 - Business Class - Help

Fixes in progress - Debtor Statements / Creditor Remittance Advices and Age analysis reports cut-off Description text

- Firebird databases - Debtor Statements / Creditor Remittance Advices and Debtor Age analysis / Creditor Age analysis reports not updated with Fixes to Descriptions not printing fully (Characters cut-off) in nounicode=FALSE setting (Unicode enabled for most users). References Such as the Document number and references entered in batch entry screens - still n cuts-off only in Firebird databases. Need to add similar sgl "`cast(messages.SDescription as varchar(255)) as SDESCRIPTION_1 " for the SREFERENCE - I may need some guidance and pointers to fix these.`
- MSSQL databases - Prints correct in all these reports - Prints the full References and Descriptions.

Folders not included

execute\localfiles\dbname folder not included.

Bank import - Shows the Reconcile button and Match log tab not correct

Neet to check the configuration / activation of the bank import plugin. The Reconcile button should not be displayed as in osFinancials5.1.0.227.



The Match log may display incorrect data

FIXED : Outstanding : Debtor Statements / Creditor Remittance Advices and Age analysis reports SREFERENCE cut off text

In Firebird Databases, the Reference only displays 7 Characters - not the full document number or reference as entered in the Reference field of batch entry screens. The Descriptions were fixed in TurboCASH5-2025-Release-Candidate-3 (Also replicated in osFinancials5-MERGE-7)

Replicated in nounicode=FALSE setting (installs for most users)

In MSSQL Databases, it displays the full characters and does not replicate these Reference and Description labels not fully printed.

Example of Debtors statement - Outstanding. NOTE the Debtor statement prints the full characters, while the Debtor Age analysis and Creditor Remittance advices - Outstanding and Creditors Age analysis reports, replicates the same issues with the Reference not printing in Firebird databases fully.

NOTE the Debtor statement prints the full characters but not the Debtor statement - Outstanding



The Descriptions is fixed in TurboCASH5-2025-Release-Candidate-3 (Also fixed in osFinancials5-MERGE-7)

FIXED : Transactions sequence by date : After fixing the SReference for the Document number and References entered in Batches, the transactions prints according to "*order by 11*" instead of "*order by 12*" to print the transactions by date (TN_906552) fixed in all reports updated.

FIXED : Debtor Statements / Creditor Remittance Advices and Age analysis reports cut off text

On Debtors statements, the TrExpression26 = TRANSACTDETAIL.SDESCRIPTION_1 displays only 20 characters if nounicode=FALSE setting also in Data configuration and on printed report.

If the nounicode=FALSE setting is set to nounicode=TRUE, the full descriptions on Debtor statements will

be printed.

Similar Descriptions issues were replicated in the following reports:

Debtors

- Debtor statements
  - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090 \TRN_1090 - Debtor statement
  - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090 \TRN_906552 - Debtor statement - Outstanding
- Debtors - Age analysis (Rreports)
  - Location : plug_ins\reports\userreports\TRN_160\TRN_906142 - Balances detail
  - Location : plug_ins\reports\userreports\TRN_160\TRN_906143 - Balances detail history (open item)
  - Location : plug_ins\reports\userreports\TRN_160\TRN_906147 - Balances

Creditors

- Creditor remittance advices
  - Location : plug_ins\reports\systemreports\TRN_161\TRN_1090 \1089 - Creditor remittance advises
  - Location : plug_ins\reports\systemreports\TRN_161\TRN_1090 \TRN_906551 - Creditor remittance advises - Outstanding
- Creditors - Age analysis (Reports)
  - Location : plug_ins\reports\userreports\TRN_160\TRN_906142 - Balances detail
  - Location : plug_ins\reports\userreports\TRN_160\TRN_906143 - Balances detail history (open item)
  - Location : plug_ins\reports\userreports\TRN_160\TRN_906147 - Balances

Added cast message field length to Descriptions in TRANSACTDETAIL

```
SELECT
cast(transact.FAmount  as decimal(12,2)) p1,
transact.*,Account.*,
cast(messages.SDescription  as varchar(255))  as  SDESCRIPTION_1
```

```
FROM  transact

   LEFT OUTER JOIN  account

   ON   (transact.WAccountID  =  account.WAccountID)

join Messages on (transact.WDescriptionid  = messages.WMessageID)
```

FIXED - Access control - User tabs - Default -> Caravan planning

Default -> Caravan planning item in User tabs - Probably for a plugin. Need to remove it. Needs to be available only if the plugin is activated. (osFinancials5.1.0.230)



MSSQL ERROR - Budget

Incorrect syntax near 'a'.

Included in the next merge install

Document layout file

TRN_906277.rep Document layout file (15 code) Moved the Document type in the Header to the centre as printing to much to the right of the layout file.

Readme.txt android

In TurcoCASH5 root directory but not in osfinancials5 root installation directory

Deleted file in TurboCASH5 install as Android app never took off (discontinued)

Subscriptions MSSQL Error

Operand type clash: date is incompatible with int

MSSQL - Set default language

In MSSQL / Firebird the Apply button does not save the language if selected in Access control for no users.

Next release Fixes Updates

Languages updated

Fixed typo in Afrikaans language file

LabelID 337 Verskafferreoere => Verskafferretoere missing "t".

Scheduled for next installs compile.

Tutorials Updated

Images

All tutorials - Added the Compressor and Drill press images to Stock items for tutorial and documentation purposes.

These images were not included, since these tutorials was created from scratch on a blank database.

Resource name in Calendar

For TurboCASH5 changed the resource shipped in the Calendar from

osFinancials/ TurboCASH in Tutorials shipped with TurboCASH5

For osFinancials, the resource remains osFinancials.

Unicode install and nounicode setting

Unounicode=FALSE

If you check both the Unicode and Unicode Check tick-boxes, the Unicode setting will be set as false in the osf.ini file:

```
nounicode=false
```



This will cause the MSSQL error, when opening a Set of Books (MSSQL database type).

UNICODE SETTING in FIREBIRD ERRORS

Unicode setting will be set as false in the osf.ini file:

```
nounicode=false
```

Entering an ê (Alt+0136) or ë (Alt+0137) in for example Company name (Registered company names may include these characters, including existing users) replicates this error:

```
Dynamic SQL Error
SQL error code = -303
arithmetic exception, numeric overflow, or string truncation
```

This error is not replicated in the following options

Setup → Accounts

Setup → Batches

Setup → Groups

Budgets (Reports ribbon)

Setup → Reporting dates

Debtors

Creditors

Documents NOTE The companyname (Setup → Company info with this error prints these characters incorrectly on document layout files

Need to check some more forms - or maybe this could be checked out in osFinancials core and plugins

nounicode=TRUE

If you do not check the Unicode checkbox (leave blank) and only select (tick) the Unicode Checked tick-box, the Unicode setting will be set as false in the osf.ini file:

```
nounicode=true
```



This will resolve the MSSQL error, when opening a Set of Books (MSSQL database type). Can open all Set

of Books (MSSQL database type).

Unounicode=True setting

MSSQL Database

Open Set of Books - MSSQL database- nounicode=TRUE

Can open Sets of Books in Firebird and MSSQL databases. This solves the issue with Opening a Set of Books error if nounicode=FALSE.

> "Invalid object name 'OPREPORT'."

Unicode setting needs to be set to nounicode=TRUE.

Replicates the error in osf5.1.0.227 with the Install nounicode=FALSE setting =

> "Invalid object name 'OPREPORT'."

Cannot open MSSQL all books in both in osFinancials5.1.0.227 and in osFinancials5.1.0.189. This error has to do with the nounicode=FALSE setting is set to false in the osf.ini file.

> nounicode=false.

Changing the nounicode=TRUE setting in the osf.ini file to true, then all MSSQL Sets of Books can be opened:

> nounicode=true

In osFinancials5.1.0.227, the Unicode settings is implemented in the install. Instead of editing the Unicode settings in the osf.ini file using a text editor, you can set the Unicode settings in the install.

Reports - MSSQL database- nounicode=TRUE

All reports and layout files including spreadsheet reports, seems to print fine and neatly except for the following 4 reports:

1. systemreports -Stock in / out

   Location : ...\plug_ins\reports\systemreports\TRN_1999\TRN_906112 (Stock in / out)

2. REPORTS/STOCK -Stock sidebar reports - Historical value

   Location : ...\plug_ins\reports\REPORTS\STOCK\LANG_906031 (Historical value)

3. userreports - Debtors - Outstanding at date

Location : plug_ins\reports\userreports\TRN_160\TRN_947\TRN_906104 - Debtors outstanding at date

4. userreports - Creditors - Outstanding at date

   Location : plug_ins\reports\userreports\TRN_161\TRN_947\TRN_906103 - Creditors outstanding at date

Plugins - MSSQL database- nounicode=true

Subscriptions MSSQL Error

Operand type clash: date is incompatible with int

Colours Select for Reporting groups

Setup → Groups

Setting Colous in Groups does not change easily - MSSQL databases is more sticky than in Firebird databases

Cannot set the Account group 1 colours - Loses selected colours

Standard Theme palette - Hard colours - Cannot make softer colours using Custom colours

Debtor groups, Creditor groups, Document groups and Stock groups works but sticky - If the grids is open, you may select Tools → Close active forms and access the grid to display the colours.

Customise Languages - Rest tab - Empty account / Empty Group

Replicated in both Firebird and MSSQL databases.

The Customise languages - Rest tab does not store "*Groups empty account*" when you click on the Change button (second button).

It displays "*Empty account*" from the first "*Description of Zero account*". It does not save correctly.

Difficult for translations or customisation.

Need to change the first Change button and confirm to change it to for example no group have to enter "*No group"* and click Change (second button). Thereafter need to reopen the Set of Books for changes to have an effect.





Access control

Posting / Delete buttons

Need to update documentation

Access control - Documents tab - Document posting tick-box - Add Posting and Delete buttons to the Documents grid sidebar. Does not work for single users - Need to setup users before this Document posting will be available for a user.

It is just a entry in the database with user id 0

Default language for a Set of Books

In Firebird and MSSQL database types cannot change the language on Setup → Access control (System language) and click the Apply button as the default language for the Set of Books. It reverts back to the original language e.g. Afrikaans if you change it to English.

Workaround - You have to use the Switch language option on the Start ribbon to update the System language in Setup Setup → Access control.

Language can be set at user level. So user a can login with language a and user b with language b

System language - Default language for the Set of Books

Language - Cannot select a language (empty / blank). You need to use the Multi-language Set of Books plugin (Manual - Shop) to select a language added in the Setup → Groups - Languages reporting group.

Access Violations - Reports

Ledger analyser - Balance sheet

Produces Access violation error

> Access violation at address 525C8283 in module 'rtl290.bpl'. Read of address 2E300858

Balance sheet prints after second attempt

Graphs

Some Graphs print Access violations click 1 or sometimes 2xtimes then it prints.

Cost centres

Cost centres were producing similar Access violation errors in the Balance sheet and some reports. Need to click 1 or more tipes then the report prints.

Export - Accounts

Spreadsheet import - Accounts

- Spreadsheet export import - No Sub-accounts Workaround delete accounts and recreate accounts.
- Export (Setup ribbon) Export tab txt file imports well - Need to delete the first tax account (No tax tab) and zero-rated items.

You can check the Tax percentages (User reports → Tax to see incorrect tax percentages such as the first Tax code (sub-account), which does not incluse a Tax tab and percentage.

Import Stock

Stock - Import - Tab-delimited .txt file

> The statement has been terminated. - Tab delimited *.txt file

> The INSERT statement conflicted with the FOREIGN KEY constraint "FK_DOCLINE_STOCK". The conflict occurred in database "MSSQL-TOETS-NUTSMAN", table "dbo.Stock", column 'WStockID'.

Spreadsheet Export from Firebird databases and Import to MSSQL works.

Imported Batches

Replicated in both Firebird and MSSQL Database types.

F8: Batch list Empty accounts on the Unposted batch report.

Balancing the batch will print only the balanced accounts - need to reselect or confirm the imported accounts

Reselect the accounts - list on Batch F8:List Unposted batches report.

Bank import - Import Bank statement

Delete Bank account with Posted transactions

Bank statement - Import Account from spreadsheet - Cannot delete bank account

> The statement has been terminated.
> The DELETE statement conflicted with the REFERENCE constraint "FK_TRANSACT_ACCOUNT". The conflict occurred in database "MSSQL-MY-BOOKS", table "dbo.TransAct", column 'WAccountID'.

If you have posted transactions to a bank account, you first need to cancel reverse posted batch and erase the batch to process the import bank statement

Similar errors in Firebird databases.

Bank-Import Open Item link

When allocating transactions for an Open item account, the Open item selection screen.

> The statement has been terminated.
> The INSERT statement conflicted with the FOREIGN KEY constraint "FK_OILINKSPRE_BATCH". The conflict occurred in database "MSSQL-MY-BOOKS", table "dbo.BatCon", column 'WBatchID'.

Imported Documents

Document Export Import plugin used to export documents from a Set of Books (Firebird Database). Imported into a Set of Books (MSSQL database).

Import Exported documents

Financial entry

Financial Entry - Need to reselect the Ledger Account and confirm it is correct.

Can select a main account (with sub accounts).

Tax by default looks like the Tax is codes is correct, Tax amount on Documents grid - When opening the document the tax code may be blank. Need to select the correct tax code.

Update Documents

When updating documents, some errors were replicated in MSSQL databases. Some of these similar errors is replicated in Firebird databases.

> Fault in rounding please set your rounding margin document:AK000001 of 150
> You cant post to the zero tax account!

Need to select the correct Tax account.

AK000001	Algemene Grootboek	1000	0

Financial Entry - Imported Documents - Need to select a Ledger account

Languages

Language files updated

The Afrikaans and 26 English language files were updated with fixes to typos, etc. See - Language-files-changelog.docx

- Location on GitHub : Changelog - https://github.com/Digidanosf/osfinancials-development/blob/main/changelog-merge/Language-files-changelog.docx
- Language files needs to be merged in " .../bin/languages " directory.
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/languages

Known issues - Language Files Label Inconsistencies

Some Language Files Label Inconsistencies: were found:

- Bank import plugin:

- Receipt column LabelID 1100 Receipt may need to be changed to labelID 2233 to reflect Receipts to be consistent with the plural LabelID 2233 reflecting Payments.
- Changing LabelID 1100 Receipt to Receipts will cause the Receipt options screen to print Receipts instead of Receipt.

- Document Status: In the Document entry form's header refers to Open (LanguageID's 163, 20120 or 21042)., which is used for the Open button on most screens. There is LabelID 580, Open for posting. Unposted (LabelID's 962 or 1097 shows in the Status column of documents grid.

Outstanding Translations

All the Outstanding translations which is not translatable in the osFinancials5 source, including plugins are listed with screenshots, notes and possible LabelID's. These outstanding translations is listed in various documents according to function and each of the plugins.

- Outstanding Translations osFinancials Core:
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/translations
- Outstanding Translations Plugins:
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/plugins-translations
- Outstanding Translations DynaReg Plugins:
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/plugins-dynabreg

Reports, document layout files

All reports and document layout files are translatable via the language files, except specific document layout files designed for the Dutch market.

Meticulous efforts have been exercised to resolve any language inconsistencies and include fixes for example, some lost in translation labels not printing in the Debtor or Creditor preferred language in the Report designer.

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports This repository contains all updated reports, document layout files, including those related to plugins. This repository can be merged with the '...\plug_ins\reports\' directory.

Themes

- Obsolete folders and files to Delete in ...bin/themes folder:
  - My-Material
  - svg-theme
  - svg-theme.zip
- Known issues - Classic Report icons display in SVG themes: The classic report icons are still displaying in SVG themes. This issue is addressed Compatible Theme Skins available for a download on GitHub to be to ensure consistency across themes.
  - Issue: Classic report icons are still displaying in SVG themes, which affects consistency across themes.
  - Resolution: Compatible theme skins are available for download on GitHub to address this issue and ensure consistency. These need to be updated and included in the next osFinancials installation.
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/themes
- FIXED - Creditor control icon not loading correctly
  - The creditor icon - does not change when creating an image strip in all themes - Setup → Accounts and in Ledger viewer - It is not correctly rendered / displayed.
  - Checked properties of creditor svg files and replaced the Acccreditors.svg icons and created new image strips in all themes containing svg icons with the correct colour.
  - Creditor control icon not loading correctly - Classic icon in some themes - Fixed in osFinancials5.1.0.109 - but with the osFinancials5.1.0.127 / osFinancials5.1.0.189 update does not include these fixes.
- Compatible Theme Skins - Each theme folder includes a customizable theme skin. There are 34 custom themes available for osFinancials5/TurboCASH5. You can view screenshots of the available themes to help you make your choice.
  - Installed Themes: These 7 themes are included in the osFinancials5 installations and may include fixes. They can be downloaded as a zip file and copied to the `.../bin/themes` folder of your osFinancials5 installation directory.
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-

development/blob/main/themes/themes-installed.zip

- New Themes - A collection of 27 themes. These themes are available for download as a zip file. Once unzipped, you can copy the themes you need to the `…/bin/themes` folder of your osFinancials5 installation directory. These themes are not included in the osFinancials5 installs..
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/themes/themes-new.zip

- Change the colour of your svg icons in one go - In osFinancials5, you have the option to easily customize the colour of all 227 icons (in the SVG "*Scalable Vector Graphics*" file format) used in the interface. This customization process can be completed in less than a minute by utilizing a text editor such as Notepad++ and the Search and Replace feature. By replacing the default black colour with a colour of your preference, you can personalize the appearance of the icons in a copy of the "*Material*" theme to suit your taste.

Documentation Update Overview

The Help documentation for osFinancials has undergone significant updates to enhance usability, accuracy, and relevance. This update is structured into two main sections: Release Notes and Core Functionalities. Below is a detailed breakdown of the recent changes and improvements made to the documentation.

Release Notes

The Release Notes section provides a comprehensive overview of known issues, fixes, and updates for osFinancials core, reports, and plugins. This section is particularly useful for tracking changes across different versions of the software, such as migrations from Delphi 10 to Delphi 11 and Delphi 12. Key features include:

- Known Issues and Fixes: Detailed notes and screenshots of bugs found and fixed in pre-release versions.
- Retesting: Each known issue is retested with every install and update to ensure ongoing stability and reliability.
- Firebird and MSSQL Compatibility: Updates and notes on compatibility with Firebird and MSSQL databases across the core, reports, plugins, and other components.

Core Functionalities

This section covers all core functionalities of osFinancials5.1/TurboCASH5-3, including reports, the report designer, and plugins. The documentation is currently being updated to provide a more comprehensive

guide to testing all features. Given that osFinancials and TurboCASH share the same source code, this documentation can also serve as a useful reference for future releases of TurboCASH.

Specific Updates in the osFinancials Help System

The following specific updates have been made to the osFinancials Help system:

- Webshop Links: Fixed approximately 400 links that were previously pointing to http://www.osf-boekhoudpakket-administratie.nl/en/webshop to https://www.osfinancials.org/en/webshop in the English Online Help and Afrikaans Online Help. This update applies to both the English Online Help and Afrikaans Online Help, as well as the CHM help files.
- Afrikaans Language: Enhanced the Afrikaans content with more translations and modernized language. This update aims to improve the accessibility and readability of the documentation for Afrikaans-speaking users.
- SEO Metatags: Added and updated metatags to improve the search engine optimization (SEO) of the documentation, making it easier for users to find relevant information through search engines.
- New and Updated Topics: Added and updated several topics, including:
    - Blockchain: Introduced new content related to blockchain technology and its integration with osFinancials.
    - Activa: Updated information on managing assets within the system.
    - Price agreements: Expanded documentation on setting up and managing price agreements.
    - Stock Sidebar Reports: Added new sections on generating and interpreting stock sidebar reports.

These updates will be included in the next release of the help files, ensuring that users have access to the most current and accurate information.

Conclusion

The recent updates to the osFinancials Help documentation reflect a commitment to providing users with a comprehensive, accurate, and user-friendly resource. By addressing known issues, updating core functionalities, and enhancing language support, the documentation aims to support users in effectively utilizing osFinancials and TurboCASH.

Firebird and MSSQL Compatibility

Ensuring compatibility with different database systems is crucial for the flexibility and scalability of

osFinancials5.1/TurboCASH5-3. The following updates and notes pertain to Firebird and MSSQL compatibility:

Core

- Database Connectivity: Enhanced database connectivity modules to support both Firebird and MSSQL.
- Performance Optimization: Optimized core functionalities for improved performance on both Firebird and MSSQL databases.

Reports

- Query Compatibility: Ensured that all SQL queries used in reports are compatible with both Firebird and MSSQL syntax.
- Report Generation: Tested and verified that report generation processes run smoothly on both database systems.
- Error Handling: Implemented robust error handling mechanisms to manage potential issues specific to each database system.

Plugins

- Database-Specific Features: Added support for database-specific features and functions in plugins to maximize compatibility.
- Configuration Options: Provided configuration options within plugins to allow users to specify their preferred database system.
- Cross-Database Compatibility: Ensured that plugins can operate effectively regardless of the underlying database system.

Other Components

- User Interface: Updated the user interface to provide clear feedback on database connectivity and compatibility status.
- Documentation: Included detailed documentation on setting up and configuring osFinancials with Firebird and MSSQL databases.
- Support and Troubleshooting: Expanded support resources and troubleshooting guides to assist users with any compatibility issues.

Conclusion

By incorporating Firebird and MSSQL compatibility updates into the Release Notes, we aim to provide users with a more comprehensive understanding of the software's capabilities and ensure a smoother experience when working with different database systems. These updates will be included in the next release of the help files, ensuring that users have access to the most current and accurate information.

Updated Reports - Larger Database Fields

The Sets of Books for the Firebird Database type now supports larger field lengths for data entry, catering to the specific requirements of larger businesses or organisations. This enhancement allows for more detailed and comprehensive data management, particularly in scenarios where extensive account codes and descriptions are necessary.

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/CUSTOMISE-BOOKS-ADVANCED

- *CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS.zip*

osFinancials Field length - Shop - Payment per request - In addition to these options, you may shop for customised field lengths.

The extended field lengths in osFinancials provide greater flexibility for creating and customizing the Chart of Accounts. This customization is designed to meet specific requirements, accounting frameworks, and standards, including taxonomies such as GAAP, IFRS (full), and IFRS for SMEs. The customization also considers language variations and jurisdiction-specific considerations.

- Relevant Standards:
  - Generally Accepted Accounting Principles (GAAP)
  - International Financial Reporting Standards (IFRS)
- Universal Chart of Accounts:
  - Suitable for use with IFRS, US GAAP, and other comparable accounting standards. See -

https://www.ifrs-gaap.com/universal-chart-accounts

- IFRS Sustainability Disclosure Standards:
  - IFRS® Sustainability Disclosure Standards around the world - See - https://www.ifrs.org/ifrs-sustainability-disclosure-standards-around-the-world/

New Sets of Books

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/4-DIGIT-BOOKS

These Sets of Books, based on the Firebird database type, include a basic Chart of Accounts supporting 4-digit main account and 3-digit sub-account codes, along with larger database fields.

4-DIGIT-BOOKS

- 4-EN-SOUTH-AFRICA-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes, aligned with the VAT201-return.
- 4-AF-SUID-AFRIKA-GENERIES.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts in Afrikaans. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes (Belasting op Toegevoegde Waarde (BTW) Suid-Afrika (Afrikaans), aligned with the VAT201-return.
- 4-EN-UK-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-accounts, based on the United Kingdom (UK) Chart of Accounts. It incorporates specific UK terminology and includes Value Added Tax (VAT) - United Kingdom accounts based on the VAT Standard rate scheme. The VAT-account and VAT-codes structure in the Chart of Accounts is designed to match the various boxes on the UK VAT return. NOTE: Various schemes for VAT may be applicable for various scenarios.

Conclusion

These examples provide a comprehensive guide to structuring VAT accounts and codes in the Chart of Accounts to match the requirements of different VAT returns. By aligning the VAT accounts with the relevant fields or boxes on VAT returns, businesses can ensure compliance and accuracy in their VAT reporting. This documentation is particularly useful for users in South Africa and the United Kingdom, offering detailed insights tailored to their specific VAT schemes and requirements. See topic - NEW - Empty Sets of Books - Supports up to 8 digit main accounts and 3 digit sub accounts.

Options to create and customise your own Set of Books

- "Customise your own Set of Books (Advanced)?" (Firebird database) - Only includes 3 control accounts (Retained earnings / Debtors control and Creditors control). Using this option, the account descriptions is limited to 35 characters and 64 characters, depending of the number of digits you select. In addition to this, you need to update the "*TYPES*" table with Paper types and may need to add the Groups for Cost centre 1 / Cost centre 2 / Projects and Languages.
- CUSTOMISE-EMPTY-BOOKS (Pre-configured Firebird database) - Only includes 3 control accounts (Retained earnings / Debtors control and Creditors control). The field length for Account descriptions and Groups description length is set to 128 characters. The "*TYPES*" table with Paper types and may need to add the Groups for Cost centre 1 / Cost centre 2 / Projects and Languages. The basic journals (such as Sales journal, Purchase journal and General journal) have been added and the basic settings for documents (such as Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders) is already set.

The basic Sets of Books created using this option will include the essential three main accounts: Debtor's Control, Creditor's Control, and Retained Earnings.

Before you start to add your own accounts to fit in with your chart of accounts, you may change the account codes and their descriptions, if necessary.

The remaining Chart of Accounts can be fully customized according to your specific requirements. This flexibility enables you to tailor the Sets of Books to suit your unique accounting needs.

Adjustments for Larger Field Lengths on Reports

The larger field lengths may result in overlapping and untidy reports. To address this, all reports and document layout files in the Report designer were accordingly adjusted and fixed where necessary. These adjustments cater to Sets of Books used by existing customers, including those with up to 8-digit main account codes and 3-digit sub-accounts, as well as larger account descriptions and input fields.

TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456.zip

A specialized test file, "*TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456.zip*", is available on GitHub for the Firebird Database type. This file is designed to test and adjust expressions, labels, and other elements across all reports and plugins when dealing with extreme field lengths.

Key Features

- Extreme Field Lengths: The file includes fields with extreme lengths to rigorously test the handling of

long descriptions and data entries.

- Comprehensive Testing: It is used to ensure that all reports and plugins can accommodate and correctly display these extended field lengths without overlapping or formatting issues.
- Adjustments for Expressions and Labels: The test file helps in fine-tuning expressions, labels, and other report elements to maintain readability and functionality even with very long data entries. All reports and document layout files were adjusted where necessary using the Report designer.
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/firebird-databases/TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456.zip

Conclusion

The TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456.zip file is an essential tool for ensuring that osFinancials can handle extreme field lengths effectively. By using this test file, developers and users can verify the robustness and flexibility of the system, particularly in scenarios where detailed and extensive data entries are required. This ensures that all reports and plugins remain functional and visually coherent, even with the most demanding data management needs.

Compatibility with Firebird and MSSQL Databases

- Firebird Databases: The larger field lengths have been thoroughly tested and are fully compatible with Firebird databases. This ensures that users can leverage the extended field lengths without compromising the integrity or performance of their Firebird-based systems.
- MSSQL Databases: Similarly, the larger field lengths have been tested and verified for compatibility with MSSQL databases. This dual compatibility ensures that users across different database environments can benefit from the enhanced data entry capabilities.

Conclusion

These updates enhance the flexibility and usability of osFinancials5.1/TurboCASH5-3, particularly for larger businesses and organizations that require more detailed and comprehensive data management. By supporting larger field lengths and adjusting reports accordingly, osFinancials ensures that users can effectively manage their accounting needs while adhering to various accounting standards and frameworks. The compatibility with both Firebird and MSSQL databases further broadens the applicability and reliability of these enhancements.

Updated Reports and Layout files to accommodate larger database field length

All reports and document layout files, when printed, now support larger database fields to accommodate the extended data entry requirements. The following updates were included in the osFinancials5.1.0.189 update:

1. systemreports - Location : " ...\plug_ins\reports\systemreports\ " See - List of Fixes to reports for screenshots and notes -
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/systemreports
2. GENERAL - Location : " ...\plug_ins\reports\GENERAL\ "
    - documents - Location : " ...\plug_ins\reports\GENERAL\documents\ "
        - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/GENERAL/documents
    - ledgerview - Location : " ...\plug_ins\reports\GENERAL\ledgerview\ "
        - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/GENERAL/ledgerview
3. REPORTS - Location : "...\plug_ins\reports\REPORTS\" REPORTS/STOCK - Sidebar reports
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/REPORTS/STOCK

Reports fixed - after osFinancials5.1.0.127 / osFinancials5.1.0.189 Update install

These updated reports were included in theosFinancials5.1.0.127 / osFinancials5.1.0.189 update installations. These Reports were retested in both Firebird database types and in MSSQL database types in osFinancials5.1.0.127 / osFinancials5.1.0.189. The reports include standardised Headers and Footers.

See - FIXED - After osFinancials5.1.0.127 update - Details / Notes and screenshots

The following reports were updated and fixed:

1. systemreports - These updated reports were included in the osFinancials5.1.0.127 update installation. Fixed some adjustments to text (labels expressions) and data expressions were made in about 7 reports. Also tested and fixed - To print on MSSQL and Firebird databases See - screenshots and notes after

a) Reports → Debtors → Listing - List delivery address

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_160/TRN_66/TRN_906138.rep

b) Reports → Debtors → Listing - List postal address

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_160/TRN_66/TRN_906139.rep

c) Reports → Creditors → Listing - List delivery address

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_161/TRN_66/TRN_906138.dfm

d) Reports → Creditors → Listing - List postal address

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_161/TRN_66/TRN_906139.rep

e) Reports → Stock → Stock In / Out - Stock in / Out

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_1999/TRN_906112/TRN_906112.rep

f) Reports → Documents → Document listing

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_38/TRN_45/TRN_45.rep

g) Reports → Tax - Tax per period

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_906020/TRN_906105.rep

2. GENERAL - These updated reports were included in the osFinancials5.1.0.127 update installation.

- documents - Reports for various functions in osFinancials such as, abbreviations, batch reports, logreports, groups,etc. (to name a few). Hope every report fixed is listed, but here are the changes that could be remembered:

- § groups,rep
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/GENERAL/documents/groups.rep
- § batch.rep
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/GENERAL/documents/batch.rep
- § postedbatch.rep
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/GENERAL/documents/postedbatch.rep
- § paycreditor.rep
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/GENERAL/documents/paycreditor.rep
- § recon.rep
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/GENERAL/documents/recon.rep
- § Userlog.rep
  - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/GENERAL/documents/Userlog.rep

- o ledgerview - Ledger analyser 1 / 2 - Reports for Trial balance, Income statement, Balance sheet, Budget vs actual, This year vs last year, Standard column balances, T-Account viewer and Age analysis on the Reports ribbon. (budvsactsimple.rep, colbal.rep, colbalopen.rep, colbalopenonly.rep, colbalsimple.rep, detail.rep, ledgerdetail.rep, openitemdays.rep)

3. REPORTS/STOCK - Sidebar reports - Stock movement - This report prints similar data to the "*Voorraad verloop*" report.
   - o Renamed text report name to LANG_906038 to be translatable via the language files. Added

report name "*Stock movement - Average cost - Grid*" in Header section.

- Total print on Page 2 and Total - Data type = Currency as " ##,###,###,##0.00" in Detail of Group section (e.g. 1,000.00) - Set the Group footer data type for the Total (e.g. 1000.00) to display similar than the Detail report section.

4. REPORTS/DEBTOR/Subscriptions.rep - New - Included in the osFinancials5.1.0.189 update installation

   - Menu access : Debtors grid - Context menu - Reports → Subscriptions
   - Location : ...\plug_ins\reports\REPORTS\DEBTOR\reports\TRN_9061000.rep - Subscriptions
   - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/REPORTS/DEBTOR/reports/LANG_901000.rep
   - See - Subscriptions for notes and screenshots of fixes.

5. excelreports - Spreadsheet reports → Sales analysis → Sales per period -

   - Firebird database type error fixed - This report now prints in both Firebird and MSSQL database types.
   - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/excelreports/TRN_85/TRN_906122/trn_1296.sql

Reports Added / Fixed - Excluded in osFinancials5.1.0.127 / osFinancials5.1.0.189 Update install

These reports were not included in theosFinancials5.1.0.127 / osFinancials5.1.0.189 update installations. These Reports were retested in both Firebird database types and in MSSQL database types in osFinancials5.1.0.127 / osFinancials5.1.0.189. The reports include standardised Headers and Footers.

1. userreports - Reports in the user reports menu. Restructured and fixed overlapping labels, etc.

   - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/userreports

2. DOCUMENTS/DOCUMENTS - All document layout files updated to fix overlapping labels, remarks, etc. to accommodate databases with larger input fields. Standardised the Company and Tax registration numbers before contact details, etc. Standardised the Company and Tax registration numbers before contact details, etc.

   In addition to this, the following document layout files are included in the '...

\plug_ins\reports\DOCUMENTS\DOCUMENTS' folder:

- Added : Layout files for NON-Standard document types
  - Adjustment - TRN_1767
  - BOM (Production) Stock Item Type - TRN_3266
  - Project - TRN_3556 - Project - Quote
- Added : Layout files for NON-Standard document types : Plugins
  - Stock in - TRN_906178
  - Stock out - TRN_906179
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/DOCUMENTS/DOCUMENTS

3. userreports - Reports in the user reports menu. Restructured and fixed overlapping labels, etc.
4. New.rep - Blank report with no Datasets. SubReport-0 consists of three blank sections Page header, detail and Page footer.
   - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/New.rep
5. Empty.rep - Tidied and standardised report Page header and Page footer to be consistent for all to be consistent with other reports such as on the Reports menu, User reports menu and stock sidebar reports (Print single item - context menu). Includes an empty Detail section. Updated and standardised Page header and Page footer. It is aligned with all Reports, User reports to accommodate databases with larger input fields.
   - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/Empty.rep

Reports for plugins Added / Fixed - Excluded in osFinancials5.1.0.127 / osFinancials5.1.0.189 Update install

The following plugins Excluded in osFinancials5.0.189 Update in the ...\osfinancials5\plug_ins\reports\ folder:

1. CRM - Location : ...\plug_ins\reports\CRM\ - Not updated - Need to activate and configure the CRM plugin before any reports could be printed. - MSSQL Errors in print preview

   "DOCUMENTHEAD:Incorrect syntax near '|'."

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/CRM

2. EMailInvoice
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/EMailInvoice
3. remittance
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/remittance
    - See - Reminders / Remittace plugin for notes on Reminders / Remittance plugin.
4. Subscriptions
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/Subscriptions
    - See - Subscriptions for notes and screenshots of fixes.

FIXED - MSSQL Database support - Reports

Fixed - To print on MSSQL and Firebird databases

Debtors

- Debtor statements
    - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090 \TRN_906552 - Debtor statement - Outstanding
    - Location on GitHub :
- Debtors - Age analysis (Reports)
    - Location : plug_ins\reports\userreports\TRN_160\TRN_906143 - Balances detail history (open item)
    - Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/userreports/TRN_160/TRN_65/TRN_906143.rep

Creditors

- Creditor remittance advices

- Location : plug_ins\reports\systemreports\TRN_161\TRN_1090 \TRN_906551 - Creditor remittance advises - Outstanding
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_161/TRN_1089/TRN_906551.rep

· Creditors - Age analysis (Reports)

- Location : plug_ins\reports\userreports\TRN_161\TRN_906143 - Balances detail history (open item)
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_161/TRN_65/TRN_906143.rep

Outstanding - Fixed - To print on MSSQL and Firebird databases - Period 2 includes Period 1

Debtor statements

- Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090 - Debtor statement
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_160/TRN_1090/TRN_1090.rep

Creditor Remittance advises

- Location : plug_ins\reports\systemreports\TRN_161\TRN_1090\TRN_1089 - Creditor remittance advises
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_161/TRN_1089/TRN_1089.rep

Debtor age analysis (Userreports)

- Location : plug_ins\userreports\userreports\TRN_160\TRN_906142 - Balances detail
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_160/TRN_65/TRN_906142.rep
- Location : plug_ins\reports\userreports\TRN_160\TRN_906147 - Balances

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_160/TRN_65/TRN_906147.rep

Creditor age analysis (Userreports)

- Location : plug_ins\userreports\userreports\TRN_161\TRN_906142 - Balances detail
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_161/TRN_65/TRN_906142.rep
- Location : plug_ins\reports\userreports\TRN_161\TRN_906147 - Balances
- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/reports/plug_ins/reports/systemreports/TRN_161/TRN_65/TRN_906147.rep

---

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

osFinancials-development merge-install

TurboCASH5 - Base type1

This changes the base type to 1 - It changes the following:

- Blank icon on Start menu



- Title bar captions, etc. refers to TurboCASH5.1.0.189 instead of osFinancials5.1.0.189.
- Addresses is ADDRESS1 + ADDRESS2+ ADDRESS3 + POSTAL CODE in forms such as debtors / creditors and documents.



That is then correct - could this be implemented for the osFinacials5 international install?

Install osFinancials - Added Unicode Setting

We've adjusted the installation script to include a new Unicode setting for Unicode databases. This setting

allows you to control the `nounicode` parameter in the INI file during installation. Additionally, we've added options to update or retain the existing `osf.ini` file based on your Unicode preferences for your Unicode databases.

Unicode Settings for Older Databases:

For existing users with Firebird Databases version ODS 10.1, the new Firebird databases will be upgraded to version ODS 11.1 as part of the 2025 installs for osFinancials5.1 and TurboCASH5-3. This upgrade is mandatory and should be carefully considered, especially for users with older databases.

Default Setting:

To ensure the safest option for users with older databases, we recommend setting the Unicode option to "*checked*" by default. However, it's crucial that users confirm their choice to avoid any unintended changes.

Installation Options:

During the osFinancials installation, you will see the following tick-boxes:

- Unicode Tick Box - Confirmation:

  By checking the Unicode box, you acknowledge that you understand the `unicode` parameter and confirm your choice. This step is designed to prevent any accidental changes without proper consideration. If you leave this checkbox unticked and the select the Unicode checkbox ticked, the Unicode setting will be set as true in the osf.ini file:

  ```
  nounicode=true
  ```

- Unicode Checked - If this checkbox is not selected, a Runtime error message is displayed:

  ```
  "Please check and confirm your unicode option."
  ```

If you need to check both the Unicode and Unicode Check tick-boxes, the Unicode setting will be set as false in the osf.ini file:

```
nounicode=false
```

We strongly advise consulting with a professional before enabling the Unicode setting. This ensures that you fully understand the implications and make an informed decision.


Setup - osFinancials 5 version 5.0
Select Additional Tasks
Which additional tasks should be performed?
OSF
Select the additional tasks you would like Setup to perform while installing osFinancials 5, then click Next.
Additional shortcuts:
Create a desktop shortcut
Use unicode on advice of osFinancials. Please consult the professional
Unicode
You understand the unicode parameter and confirm your choice
UnicodeChecked
Back
Next
Cancel



This setting will determine the encoding of characters in Unicode setting:

- ANSI Encoding: If the file is saved in ANSI encoding, the characters " " might not be correctly represented on systems that do not support the appropriate code page.
- UTF-8 Encoding: If the file is saved in UTF-8 encoding, the characters " " will be correctly represented on any system that supports Unicode.

Upgraded Firebird Databases

Sets of Books is upgraded from Firebird database ODS version 10.1 = Firebird version 1.5 to Firebird database ODS version 11.1 = Firebird version 2.1 using FlameRobin. The following sets of books is upgraded Firebird database ODS version 11.1 = Firebird version 2.1:

- All Sets of Books download in "*Let osFinancials help you to create a Set of Books?*" options.
- Sets of Books in the ...\bin\Tutorials folder.

Microsoft Server SQL (MSSQL) Database Support

osFinancials5/TurboCASH5 now supports Microsoft Server SQL (MSSQL) Databases. You may create a MSSQL Sets of Books database using the "*Customise your own Set of Books (Advanced)?*" option.

Updated - Tutorials from 2023 to 2024

Based on the 3-digit main accounts and 3-digit sub-accounts now supports larger field-lengths for descriptions.

These Sets of Books were rebuilt by using the CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS Set of Books template and imported the following files Accounts, Debtors, Creditors and Stock exported files. The descriptions of accounts, etc. were edited to accommodate more meaningful descriptions, etc. of abbreviations.

ENGLISH Tutorials

HANDYMAN

HANDYMAN-A

HANDYMAN-B

Bank Import plugin

HANDY-BANK-IMPORT-A

HANDY-BANK-IMPORT-B

HANDY-BANK-UNPOSTED-BANK-STATEMENT

Cost Centres

COST CENTRE-A

COST CENTRE-B

Afrikaans Handleidings

NUTSMAN

NUTSMAN-A

NUTSMAN-B

Bank Invoer-inprop

NUTSMAN-BANK-INVOER-A

NUTSMAN-BANK-INVOER-B

NUTSMAN-BANK-INVOER-STATE

Languages

Updated

- Fixed typos and added translations in 27 English languages and Afrikaans. Language files includes a few more language labels.
- Includes <@APPNAME@> tag for Basetype0 for osFinancials / Basetype1 for TurboCASH. Within Website-links to the shop the <@APPURL@> is not used as it causes broken links. Currently it points to the osFinancials website.

FULL INSTALL SCRIPT

Details of MERGE Setup

- Inno Setup version: Inno Setup Compiler 6.3.3. is used to compile the osFinancials5.1.0.189
- Output file name: OutputBaseFilename=osfinancials5-MERGE-1 (For next compiles will increase the last digit 1 to 2) for the setup file to osfinancials5-MERGE-2, etc.
- Inno Setup No icons - uses the default InnoScript icon. Do not have the icons or bmp image files for the install - Commented the install

```
;SetupIconFile=F:\osfSource\GIT\sources\OSFinancials\OSFinancials_Icon.ico
;WizardImageFile="F:\osfinancials5-install\osfinancials5Del\osfimage.bmp"
;WizardSmallImageFile="F:\osfinancials5-install\osfinancials5Del\OSFinancialssmall.bmp"
```

- SETS of BOOKS Installed - Books folder:
  - English Sets of Books: HELP-DEMO (needs updating)
  - Netherlands Sets of Books (Need updated or correct books to install.
    - BTW_VOORBEELD_BELGIE - Installed instead - BE_BELGIE
    - BTW21VOORBEELD_A_20XX - Installed instead - BTW09VOORBEELD_A_2019PLUS
  - Files not found and installed:
    - OFFICEPRO.FDB

- officeprotemplates

- Unlicensed install:

  OK - Open Set of Books - the confirmation message is there

  > This software is limited to 500 transactions or 500 documents! Please register and buy a licence for osFinancials.

  Need to register osFinancials5.1.0.189

Merged - GitHub

Resources on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main -

Merged - bin/languages

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/languages

- Fixed: Typos and translations in 28 languages (27 English and 1 in Afrikaans).

- Added: Languages labels - Number of records - 4071 - after new labels (Precious record count was 4061 - 10 labels added - count now 4071

  - TRN_906588 - Value stock account
  - TRN_906587 - Document reference
  - TRN_906586 - Stock - Expected quantities
  - TRN_906585 - Stock item list - Active stock
  - TRN_906584 - Production list
  - TRN _902008 - Price list - Large retail - Sales = Added in Plugin range
  - TRN _902009 - Price list - Large retail - Purchases = Added in Plugin range
  - TRN_906589 - NO-TAX Layout file
  - TRN_906590 - NO-TAX Document layout
  - TRN_906591 - NO-TAX Document layout (15-code)

- Deleted: Obsolete / out dated language files - Deleted from languages folder (" *...\bin\languages* ")

Language file	*Date of last changes*	*Replaced and updated with*	*Books download*

African.dfm	*2020/03/06*	*Afrikaans.dfm*	
en-Trinandad.dfm	*2020/03/06*	*en-Trinidad.dfm*	*EN-TRINIDADTOBAGO*
Nederlands.dfm.bak	*2020/05/08*		
testlang.dfm	*2020/03/06*		
Zeng.dfm	*2020/03/06*		

These language files is not linked to any Firebird Sets of Books and linked languages available as a free download. from the Download option on the "*Creation wizard*".

bin/themes

- Fixed: Themes with no icons and image strips. The Blue, Glass, Silver Soft-blue themes with custom colors looses the reports material icons and on Reports menu it reverse back to classic icons. When Creating the image strip. (only image strips and no svg icons were included in these respective theme folders). Added the icons to the respective themes folders to display the original svg icon (after image strip was created).
- Fixed: Acccreditors.svg icon in some themes the classic icon was displayed for Creditors on reports (e.g. Ledger analyser, while the debtors and other icons were displaying the correct theme svg icons. The properties of the Acccreditors.svg icon were adjusted accordingly to be inline with other icons (after image strip was created).
- Fixed: VS2010 theme - revered to display the Classic icon sets as were included in previous versions of osFinancials5/TurboCASH5.2.
- Fixed: Background images in osFinancials theme's (Material-blue, Material-maroon and Material-navy) The background images were reflecting TurboCASH instead of osFinancials branding..
- Deleted: Obsolete folders and files in …bin/themes folder
  - My-Material
  - svg-theme
  - svg-theme.zip
- Added: In addition to the Material theme with black icons, similar Material themes with Material icons in different colors:
  - Material-blue

- Material-green
- Material-maroon
- Material-navy
- Material-pink

Merged - plugins/reports

Merged: All reports were merged in plug_ins\reports folder.

Moved: Age analysis from userreports to systemreports folder. In addition to the opendays.rep report accessible on the Age analysis (Reports ribbon) or on the Due tab on the Open item link (Default ribbon). The following age analysis reports were added on the Reports menu (moved from the User reports menu).

These reports are compatible with both Firebird and MSSQL database types.

Reports → Debtors → Age analysis

These Age analysis reports for debtors provides alternative views and options to the Debtor statements. This is now similar to the Debtors → Age analysis on osFinancials 4.0.1093 Last release.

Debtors → Age analysis - Balances detail -

New	Location : ...\plug_ins\reports\systemreports\TRN_160\TRN_65\TRN_906142.rep

Debtors → Age analysis - Balances detail history (open item) -

New	Location : ...\plug_ins\reports\systemreports\TRN_160\TRN_65\TRN_906143.rep

Debtors → Age analysis - Balances -

New	Location : ...\plug_ins\reports\systemreports\TRN_160\TRN_65\TRN_906147.rep

Reports → Creditors → Age analysis

These Age analysis reports for creditors provides alternative views and options to the Creditor Remittance advices. This is now similar to the Creditors → Age analysis on osFinancials 4.0.1093 Last release.

Creditors → Age analysis - Balances detail -

New	Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_65\TRN_906142.rep

Creditors → Age analysis - Balances detail history (open item) -

New	Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_65\TRN_906143.rep

Creditors → Age analysis - Balances -

New Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_65\TRN_906147.rep

Firebird Databases Sets of Books - larger field lengths

Generic templates - books-directory

Generic template based on 4-Digit Sets of Books for South Africa in English and Afrikaans and the United Kingdom (UK)

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/4-DIGIT-BOOKS -

These Sets of Books, based on the Firebird database type, include a basic Chart of Accounts supporting 4-digit main account and 3-digit sub-account codes, along with larger database fields.

- 4-EN-SOUTH-AFRICA-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes, aligned with the VAT201-return.
- 4-AF-SUID-AFRIKA-GENERIES.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts in Afrikaans. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes (Belasting op Toegevoegde Waarde (BTW) Suid-Afrika (Afrikaans), aligned with the VAT201-return.
- 4-EN-UK-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-accounts, based on the United Kingdom (UK) Chart of Accounts. It incorporates specific UK terminology and includes Value Added Tax (VAT) - United Kingdom accounts based on the VAT Standard rate scheme. The VAT-account and VAT-codes structure in the Chart of Accounts is designed to match the various boxes on the UK VAT return. NOTE: Various schemes for VAT may be applicable for various scenarios.

Firebird Databases - Empty Sets of Books templates - larger field lengths - bin/CUSTOMISE-EMPTY-BOOKS-directory

The Sets of Books for the Firebird Database type now supports larger field lengths for data entry, catering to the specific requirements of larger businesses or organizations. This enhancement allows for more detailed and comprehensive data management, particularly in scenarios where extensive account codes and descriptions are necessary.

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-

databases/CUSTOMISE-BOOKS-ADVANCED

- *CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS.zip*

Hands-on Tutorials - Bin Tutorials directory

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/documentation - osFinancials5 installation provides tutorial Sets of Books in both English and Afrikaans. These tutorial books allow users to explore different settings, transactions, and reports within the software. Here are the available tutorial sets:

Accounting Made Easy	***Accounting Made Easy - Bank Import***	***Rekeningkunde Met Gemak (Afrikaans)***
English tutorials (using separate receipt and payments journals for banking / cash transactions)	*English tutorials (using the BankImport plugin for banking / cash transactions)*	*Afrikaanse handleidings (gebruik aparte ontvangste- en betalingsjoernale vir bank- / kontanttransaksies)*
		
The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\ENGLISH\" folder: - *HANDYMAN (No transactions)*	*The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\BANK-IMPORT\" folder:*	*Die volgende Stel Boeke gebaseer op die Afrikaanse handleidings, is in die "…\bin\Tutorials\AFRIKAANS\"-lêergids geïnstalleer:*

- *HANDYMAN-A (Unposted transactions)*
- *HANDYMAN-B (Posted transactions)*
- *HANDY-BANK (No transactions).*
- *HANDY-BANK-A (Unposted transactions)*
- *HANDY-BANK-B (Posted transactions).*
- *HANDY-BANK-UNPOSTED-BANK-STATEMENT – Posted transactions, excluding bank / cash transactions. Bank statement needs to be imported from the "…\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS" folder.*
- *NUTSMAN (Geen transaksies).*
- *NUTSMAN-A (Ongeposteerde transaksies)*
- *NUTSMAN-B (Geposteerde transaksies).*

2024 Versions in LibreOffice (*.odt) format of these publications can be downloaded in English and Afrikaans

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS-AME -

Sets of Books and Supporting files for Tutorials

Firebird database type Sets of Books (in English and Afrikaans), including supporting files for export and import, for these tutorials can be downloaded.
Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS -

Help Documentation

The last published help documentation were published on Friday, 24 March 2023 - 11:09:33

This include the EngHelp,chm context-sensitive Help using the F1 key to launch associated topics with most screens or fields within functionalities of the osFinancials core.

Published Online documentation - osFinancials website

English Online help *Afrikaans Online help*

Development Online osFinancials

These Online Help system will be regularly updated as more topics is retested and fixed and translations are done in the Afrikaans Help.
This documentation updates includes tests on updates of osFinancials core and plugins including Firebird and MSSQL Compatibility.
The Help file is structured as follows:

- Release notes
- Known issues
    - Translations outstanding
    - Translations outstanding - Plugins
    - Fixed and Known issues on various functionalities in the osFinancials core, including reports, plugins and Firebird and MSSQL Compatibilit .
    - Fixed items - Many previous known issues and possible bugs were addressed is listed for record to assist with retesting and reference purposes.
    - Known issues - There are various outstanding issues or possible bugs in osFinncials core and in Plugins.
    - To be advised - About 59 to be advised tags are currently in documentation topics.

Various fixes to languages, themes, MSSQL and Firebird compatibility, reports, etc. may be followed in the Release notes.

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

TurboCASH-development merge-install

Untranslated items on Inno Setup Compiler

Select destination folder

Installasie

Kies bestemming ligging

At least 2.38 GB of free disk space is required.

Select Components

Kies komponente

Watter komponente moet geinstalleer word?

Custom installation

Install local single user Firebird database (Needed to run TurboCASH local 1 user only)

Install Firebird database server (Needed to run TurboCASH on a server or client) 6.5 MB

Install FlameRobbin Version 0.90(SQL browser type) (optional) 1.8 MB

Current selection requires at least 1.77 GB of disk space.

Select Additional Tasks

Installasie

Kies Bykomende take

Watter bykomente take moet uigevoer word?

Kies die bykomende take wat jy wil he die Installeerder moet uitvoer tydens die TurboCASH5 installasie, en kliek dan Volgende.

Additional icons:

Create a desktop icon

Create a Quick Launch icon

Use Unicode on advice of osFinancials. Please consult the professional.

Unicode

You understand the unicode parameter and confirm your choice.

Unicode Checked

Installasie

Ready to Install

Gereed om te installeer

Die installeerder is nou gereed om TurboCASH5 op jou rekenaar te installeer.

Kliek Installeer om voort te gaan met die installasie, of kliek Terug indien jy enige keuses wil hersien of

verander.

Installasie tipe:

Full installation

Geselekteerder komponente:

Install local single user Firebird database (Needed to run TurboCASH local 1 user only)

Start Menu gids: TurboCASH5

Bykomende take:

Additional icons:

Create a desktop icon

Create a Quick Launch icon

To read old TurboCASH Databases. If you are unsure Please consult the professional.

Unicode

You understand the unicode parameter and confirm your choice.

Unicode Checked

Installasie

Completing the TurboCASH5 installation

Voltooi die TurboCASH5 Installasie assistent

Die TurboCASH5 installasie is voltooi. Die program kan uitgevoer word deur die geinstalleerde ikone te gebruik.

Kliek Voltooi om die installeerder te verlaat.

Launch TurboCASH5

Fixed - Licence

.... liable to you ore any other party ....

Changed to

-- liable to you or any other party --

-- The Vendors mak no representations or warranties --

Changed to

-- The Vendors make no representations or warranties --

Getting Ready for 2025

TurboCASH5 is based on osFinancials5.1.0..233. It is based on Delphi 12 (Upgraded from Delphi 10 / Delphi 11)

Latest Release : osFinancials5.1/TurboCASH5-3 version 5.1.0.233.

TurboCASH Updated install script

Location : bin\Languages

Updated 140 tcash.ini files in the install languages folder for each country.

Default install theme

Updating 140 `tcash.ini` files in the installation languages folder for each country, you're ensuring consistency across all installations.

Changing the default install theme from `theme=3 (Material)` to `theme=7 (Material navy)` provides a fresh look.

This means that any new installations will now default to the Material-navy theme, improving the visual experience for all users.

Ensuring that previous installations of TurboCASH5 also respect this theme change by updating their settings is a great move to maintain a consistent user interface.

This attention to detail will likely be appreciated by users who value a cohesive look and feel in their TurboCASH5-3 software.

Users may personalise their TurboCASH5-3 interface by selecting from available themes on the Themes menu (Setup ribbon) makes the experience more enjoyable and tailored to individual preferences.

Changes - AppCondig settings

Added some specific configurations to the tcash.ini file for TurboCASH5-3:

- Unicode settings is included in the Installation of TurboCASH5-3. You may now choose if you need to enable or disable Unicode during the installation of TurboCASH5-3. The options is as follows:
    - nounicode=FALSE: This setting enables Unicode support, which might be necessary for TurboCASH5-3 to handle a wide range of characters from different languages, ensuring proper display and processing of multilingual text.

      The Unicode settings as set during the installation process will confirm the FALSE setting or set it to TRUE based on the selected installation options.
    - nounicode=TRUE: This setting will disable Unicode support, which might be necessary for compatibility with certain older databases or systems that don't fully support Unicode.

Install TurboCASH5-3 - Unicode Setting

Added Unicode options to update update the tcash.ini file.

Unicode settings -

- *Older databases mean existing users with Firebird Databases version 10.1 -*
- *New Firebird databases is upgraded to Firebird Databases version 11.1 included in the 2025 installs for osFinancials5.1 and TurboCASH-3 Its a choice for old users. maybe set it to checked by default?*

- ;BIDIMODE=RTL: This setting, likely intended to enable Right-to-Left text display, is currently commented out with a semicolon (;). If you want to enable RTL mode, you'll need to remove the semicolon at the beginning of this line. This is useful for languages like Arabic and Hebrew.
- OB1BOX=False: This setting likely controls a specific feature or option within TurboCASH5-3. Setting it to False disables that feature.

These settings can help customise the behaviour of TurboCASH5-3 to better fit your needs.

Removed about 20 blank lines in all tcash.ini files

This will allow for better display in the Preview pane of the File Explorer to view the tcash.ini files before opening it.

TurboCASH Version

Changed the TurboCASH5.2 version to TurboCASH5-3 in the 140 tcash.ini files to avoid confusion with previous TurrboCASH5.2 installations.

All 140 tcash.ini files can be changed in one go within minutes when necessary, using Notepad++ - Search and Replace in files in the inno installation languages folder.

See - TurboCASH-Version control.

Document layout file

TRN_906277.rep Document layout file (15 code) Moved the Document type in the Header to the centre as printing to much to the right of the layout file.

Readme.txt - Android

In TurboCASH5-3 root directory but not in osfinancials5 root installation directory

Deleted file in TurboCASH5 install as Android app never took off (discontinued)

TurboCASH5 - Base type1

This changes the base type to 1 - It changes the following:

- Blank icon on Start menu



- Title bar captions, etc. refers to TurboCASH5.1.0.189 instead of osFinancials5.1.0.189.
- Addresses is ADDRESS1 + ADDRESS2+ ADDRESS3 + POSTAL CODE in forms such as debtors / creditors and documents.



That is then correct - could this be implemented for the osFinacials5 international install?

INSTALL Repository now included in TurboCASH5 (build 5.1.0.227)

- ET-ESTONIAN

- TH-THALAND
- TR-TURKEY

Licence

Licence agreement updated

license.rtf file and a html version as license.html

Licensed install:

Registered to 2025/02/27 and includes the following licensed plugins:

- Document email PRO
- Multi-workstation
- TurboCASH5-3-subscription
- BankImport
- Multimedia Pack

At first after installing, seems like an unlicensed version. You may need to go to the Online registration to confirm your subscription. To do this click on the Show licence agreement and click the Send button.

Unlicensed install:

OK - Open Set of Books - the confirmation message is there

> This software is limited to 500 transactions or 500 documents! Please register and buy a licence for osFinancials.

Need to register TurboCASH5.1.0.189

Unlicensed nag screens

Multi-workstation

> Multi-workstation ({653DFM75-2C90-4810-85C5-90658618AB66}) Time license expired! Please visit https://www.osfinancials.org/en/webshop

Subscription

> TurboCASH5-2-subscription ({982DF989-0553-404C-B08E-4FFBA8A074CF}) Time license expired! Please visit https://www.osfinancials.org/en/webshop

Help documentation

Added : TurboCASH5 banner in the main pages (next to the osFinancials banner).

Added : References to osFinancials5.1 added TuirboCASH5-3 in content.

Added : Help title and footers to include TurboCASH5-3.

- Title - "osFinancials5 .1 / TurboCASH5-3"
- Footers - "osFinancials5 .1 / TurboCASH5-3 - © Dan van Zyl - Special thanks to Pieter Valentijn (Delphi Dreams) and Philip Copeman (TurboCASH)"

The reason for the TurboCASH5-3 versioning is to make it clear and understanding the new versions such as TurboCASH3, TurboCASH4, TurboCASH5, TurboCASH5-2 of the legacy versions.

Plugins menu - Updated pluginsload.txt

Some plugins were set to false such as plugins only applicable to the Dutch market.

Plugins for TurboCASH5 that will display in the Plugins menu, will only list the Plugins shipped ind included with the TurboCASH5-3 subscription.

Plugins in osFinancials5 and TurboCASH5

Plugins Specific to TurboCASH5

- Plugins Set to False: Some plugins are specifically designed for the Dutch market and are set to false in TurboCASH5. These plugins are not available in the TurboCASH5 subscription.
- Plugins Menu: The Plugins menu in TurboCASH5 will only list the plugins that are shipped and included with the TurboCASH5 subscription.

Included Plugins in osFinancials5 / Subscription TurboCASH5 Subscription

- EmailInvoice Document E-mail Pro: Allows for the emailing of invoices directly from the software.
- Bank Import: Enabled in Setup → Data parameters by ensuring the "*Default bank reconciliation method*" field is not ticked.

Marketable Plugins

These plugins are functional and can be used with both osFinancials5 and TurboCASH5. Some may require additional licenses.

- Activa: Plugin for managing assets.
- Charter: Specific functionality for generating charts.
- Document Export Import: Allows for the export and import of documents.
- DrillDown: Enables drill-down functionality for detailed data analysis.
- Freefields: Adds customisation of fields to various forms.
- LocationBatchAndSerials: Manages locations, batches, and serial numbers.
- Multimedia: Integrates multimedia elements into the software.
- Multi-user Agenda: Provides a shared agenda for multiple users.
- Remittance: Facilitates remittance processes.
- Price agreement: Manages pricing agreements.
- Subscriptions: Handles subscription-based billing.

Essential Plugins

These plugins are crucial for specific functionalities within osFinancials5 and TurboCASH5.

- ReportMan - Report designer: Essential for customising layout files and reports.
- Register plugins: Adds licenses to plugins.
- SQL Browser: Essential for adding reporting groups when Customising your own Set of Books.
- HandyTools: Advanced tools for experienced users.

Plugins That Cannot Be Disabled

- DYNADBREG: This plugin cannot not be disabled and is essential for certain functionalities within the software.

Summary

The plugins available in TurboCASH5 are tailored to meet the needs of users while excluding those specific to the Dutch market. Both osFinancials5 and TurboCASH5, includes Essential plugins like Report designer, SQL Browser, and HandyTools are included to ensure core functionalities are maintained. Marketable plugins offer additional features that can be licensed as needed, enhancing the osFinancials5 and

TurboCASH5 capabilities.

Version number

Version need to sort the version number

TurboCASH5 build 5.1.0.233 as this seems lower than the TurboCASH5-2 (build 4.0.0453) shipped since 2021.

Root folder logos

Updated Images, logos to be consistent with TurboCASH branding in the root folder of the TurboCASH5 installation folder.
This will display in options such as Create Set of Books, etc.

- logo.jpg
- logohor.jpg
- logosm.jpg
- logosmall.png

Themes

Location : bin/themes

- Fixed: Checked and updated Background pictures in themes to use the TurboCASH branding in Background images.
- Fixed: Themes with no icons and image strips. The Blue, Glass, Silver Soft-blue themes with custom colors looses the reports material icons and on Reports menu it reverse back to classic icons. When Creating the image strip. (only image strips and no svg icons were included in these respective theme folders). Added the icons to the respective themes folders to display the original svg icon (after image strip was created).
- Fixed: Acccreditors.svg icon in some themes the classic icon was displayed for Creditors on reports (e.g. Ledger analyser, and in Setup → Accounts; while the debtors and other icons were displaying the correct theme svg icons. The properties of the Acccreditors.svg icon were adjusted accordingly to be inline with other icons (after image strip was created).
- Fixed: VS2010 Theme to display Classic icons to be consistent with previous releases of TurboCASH / osFinancials

- Replaced: BackGround1.Jpg + BackGround2.Jpg images in themes in line with TurboCASH branding.
- Deleted: Obsolete folders and files in …bin/themes folder
    - My-Material
    - svg-theme
    - svg-theme.zip
- Added: In addition to the Material theme with black icons, similar Material themes with Material icons in different colors:
    - Material-blue
    - Material-green
    - Material-maroon
    - Material-navy
    - Material-pink
- New Image strips created in Tools → Customise language. These image strips fixes the TurboCASH5 icon in the Help menu on Start ribbon.

Languages

Updated

Includes <@APPNAME@> tag for Basetype0 for osFinancials / Basetype1 for TurboCASH. Within Website-links to the shop the <@APPURL@> is not used as it causes broken links. Currently it points to the osFinancials website.

Merged - bin/languages

- Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/languages
- Fixed: Typos and translations in 28 languages (27 English and 1 in Afrikaans).
- Added: Languages labels - Number of records - 4071 - after new labels (Precious record count was 4061 - 10 labels added - count now 4071
    - TRN_906588 - Value stock account
    - TRN_906587 - Document reference
    - TRN_906586 - Stock - Expected quantities

- TRN_906585 - Stock item list - Active stock
- TRN_906584 - Production list
- TRN _902008 - Price list - Large retail - Sales = Added in Plugin range
- TRN _902009 - Price list - Large retail - Purchases = Added in Plugin range
- TRN_906589 - NO-TAX Layout file
- TRN_906590 - NO-TAX Document layout
- TRN_906591 - NO-TAX Document layout (15-code)

- Deleted: Obsolete / out dated language files - Deleted from languages folder (" *...\bin\languages* ")

Language file	*Date of last changes*	*Replaced and updated with*	*Books download*
African.dfm	*2020/03/06*	*Afrikaans.dfm*	
en-Trinandad.dfm	*2020/03/06*	*en-Trinidad.dfm*	*EN-TRINIDADTOBAGO*
Nederlands.dfm.bak	*2020/05/08*		
testlang.dfm	*2020/03/06*		
Zeng.dfm	*2020/03/06*		

These language files is not linked to any Firebird Sets of Books and linked languages available as a free download. from the Download option on the "*Creation wizard*".

Updated - Tutorials from 2023 to 2024

Based on the 3-digit main accounts and 3-digit sub-accounts now supports larger field-lengths for descriptions.

These Sets of Books were rebuilt by using the CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS Set of Books template and imported the following files Accounts, Debtors, Creditors and Stock exported files. The descriptions of accounts, etc. were edited to accommodate more meaningful descriptions, etc. of abbreviations.

ENGLISH Tutorials

HANDYMAN

HANDYMAN-A

HANDYMAN-B

Bank Import plugin

HANDY-BANK-IMPORT-A

HANDY-BANK-IMPORT-B

HANDY-BANK-UNPOSTED-BANK-STATEMENT

Afrikaans Handleidings

NUTSMAN

NUTSMAN-A

NUTSMAN-B

Bank Invoer-inprop

NUTSMAN-BANK-INVOER-A

NUTSMAN-BANK-INVOER-B

NUTSMAN-BANK-INVOER-STATE

Sets of Books in Repository folder Updated

Location : ...\bin\Repository

Sets of Books in the ...\bin\Repository folder is still based on Firebird 1.5 is designated (ODS 10.1).

Is upgraded to Firebird 2.1 (ODS 11.1).

In osFinancials5.1/TurboCASH5-3 all other older databases, including tutorials, is Upgraded to Firebird 2.1 ODS 11.1.

All databases (Sets of Books) available for download in the Creation wizard, is updated to Firebird 2.1 ODS 11.1 and the start of the Financial year is set to 2025/XX/XX.

Upgraded Firebird Databases

Sets of Books is upgraded from Firebird database ODS version 10.1 = Firebird version 1.5 to Firebird database ODS version 11.1 = Firebird version 2.1 using FlameRobin. The following sets of books is upgraded Firebird database ODS version 11.1 = Firebird version 2.1:

- All Sets of Books download in "*Let osFinancials help you to create a Set of Books?*" options.
- Sets of Books in the …\bin\Tutorials folder. Sets of Books financial year starts with 2024/03/01
- All Sets of Books in the …\bin\Repository folder. Sets of Books financial year starts with 2025/01/01, except the following Sets of Books:
    - Books staring with 2024/04/06
        - EN-UK
        - EN-ISLEOFMAN
    - Books staring with 2024/07/01
        - EN-AUSTRALIA
        - EN-BELIZE
        - EN-CANADA-CORPORATION
        - EN-CANADA-OTHER
        - EN-NEW_ZEALAND
        - EN-TONGA

Merged - GitHub

Resources on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main -

Merged - plugins/reports

Merged: All reports were merged in plug_ins\reports folder.

Moved: Age analysis from userreports to systemreports folder. In addition to the opendays.rep report accessible on the Age analysis (Reports ribbon) or on the Due tab on the Open item link (Default ribbon). The following age analysis reports were added on the Reports menu.

These reports are compatible with both Firebird and MSSQL database types.

Reports → Debtors → Age analysis

These Age analysis reports for debtors provides alternative views and options to the Debtor statements. This is now similar to the Debtors → Age analysis on osFinancials 4.0.1093 Last release.

Debtors → Age analysis - Balances detail -

New Location : …\plug_ins\reports\systemreports\TRN_160\TRN_65\TRN_906142.rep

Debtors → Age analysis - Balances detail history (open item) -

New	Location : ...\plug_ins\reports\systemreports\TRN_160\TRN_65\TRN_906143.rep

Debtors → Age analysis - Balances -

New	Location : ...\plug_ins\reports\systemreports\TRN_160\TRN_65\TRN_906147.rep

Reports → Creditors → Age analysis

These Age analysis reports for creditors provides alternative views and options to the Creditor Remittance advices. This is now similar to the Creditors → Age analysis on osFinancials 4.0.1093 Last release.

Creditors → Age analysis - Balances detail -

New	Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_65\TRN_906142.rep

Creditors → Age analysis - Balances detail history (open item) -

New	Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_65\TRN_906143.rep

Creditors → Age analysis - Balances -

New	Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_65\TRN_906147.rep

Document layout files

Location : ...\plug_ins\reports\DOCUMENTS\DOCUMENTS\

Netherlands Document layout files excluded from TurboCASH release

...\plug_ins\reports\DOCUMENTS\DOCUMENTS\

Kassabon VM.rep

POS.rep

RMBestelling.rep

RMCreditnota.rep

RMfactuur BE.rep

RMFactuur.rep

RMFactuurbtwAanEinde.rep

RMInkoop.rep

RMOfferte.rep

RMPakbon.rep

RMPOS.rep

RMRetourzending.rep

RMSTARTSP100.rep

Reviewed and updated - Document layout files updated to accommodate larger data fields

Scheduled for next install after osFinancials5.1.0.233 and TurboCASH5-2025-Release-Candidate-8

File location in installations : .../plug_ins/reports/DOCUMENTS\DOCUMENTS\

GitHub link - osFinancials5 Documents : - https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/DOCUMENTS/DOCUMENTS -

GitHub link - TurboCASH5 Documents : - https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/document-layout-files-turbocash5/DOCUMENTS -

LabelID	*Layout file name*	*Comments*
-	*BTW Faktuur - Afrikaans.rep*	
-	*GEEN-BTW Faktuur - Afrikaans.rep*	
-	*NO-TAX Invoice - English.rep*	
-	*TAX Invoice English.rep*	
TRN_1313.rep	*Delivery note*	
TRN_1341.rep	*Default*	*Added*
TRN_1767.rep	*Adjustment*	*NEW - For Stock adjustments*
TRN_1910.rep	*Layout file*	

TRN_3174.rep	*Document layout*	
TRN_3266.rep	*BOM (Production)*	*Layout file for the BOM (Production) stock item type. Assemble and Disassemble functions*
TRN_3556.rep	*Project*	*Project Quotes*
TRN_9061 78.rep	*Stock in*	*Stock in plugin*
TRN_9061 79.rep	*Stock out*	*Stock out plugin*
TRN_9061 83.rep	*POS - STARTSP100*	
TRN_9061 84.rep	*POS 1*	
TRN_9061 85.rep	*POS 2*	
TRN_9062 77.rep	*Document layout (15 code)*	
TRN_9065 89.rep	*NO-VAT Layout file*	
TRN_9065 90.rep	*NO-VAT Document layout*	
TRN_9065 91.rep	*NO-VAT Document layout (15-code)*	

FIXED - Document layout files NEED update to accommodate larger data fields

The following document layout files were fixed with the following issues:

- MSSQL errors in DOCUMENTLINE Dataset

DOCUMENTLINE:Incorrect syntax near '|'.

Replaced the || (double pipe characters) with the {concat} function. Prints in both MSSQL and Firebird databases.

- Updated these document layout files to accommodate larger data fields. These document layout files may appear untidy when using databases which supports larger data fields.
- Checked and fixed debtor / creditor language - Some labels not translating in the debtor / creditor preferred language.
- FIXED : MSSQL Error in document layout files (TRN_906276 Document layout file (10 codes) and (TRN_906278 Document layout file (no codes)):

  CLIENTLANG:'getuserlang' is not a recognized built-in function name.

- FIXED : Error in Firebird databases in document layout files TRN_906218 Invoice A4 (10 code) and TRN_906224 (Invoice A4 (15 code) Expressions referred to DOCUMENTHEAD.TAXNO instead of DOCUMENTHEAD.TAXNR

  Unknown identifier: :DOCUMENTHEAD.TAXNO 'DOCUMENTHEAD.TAXNO':Expression TRpExpression57

- FIXED : Serial/Batches printing the label with no data in stock items without serial/batch entries for stock items. Document layout file (Default (10 codes) fixed.

List of Layout files only in TurboCASH5 updated:

LabelID	*Layout file name*
TRN_906180.rep	*Open drawer*
TRN_1341.rep	*Default*
TRN_906181.rep	*Delivery note (no codes)*
TRN_906182.rep	*Delivery note (15 code)*
TRN_906186.rep	*POS A4*
TRN_906187.rep	*Default A4*

p

TRN_906188.re *Default A4 (10 code)*

p

TRN_906189.re *Default A4 (15 code)*

p

TRN_906190.re *Invoice test*

p

TRN_906191.re *Invoice English (15 code)*

p

TRN_906192.re *Invoice Bank details (no codes)*

p

TRN_906193.re *Invoice Bank details (15 code)*

p

TRN_906194.re *Invoice (no codes)*

p

TRN_906195.re *Credit note (no codes)*

p

TRN_906196.re *Quote (no codes)*

p

TRN_906197.re *Purchase (no codes)*

p

TRN_906198.re *Supplier return (no codes)*

p

TRN_906199.re *Order (no codes)*

p

TRN_906200.re *Invoice (10 code)*

p

TRN_906201.re *Credit note (10 code)*

p

TRN_906202.re *Quote (10 code)*

p

TRN_906203.re *Purchase (10 code)*

p

TRN_906204.re *Supplier return (10 code)*

p

TRN_906205.re *Order (10 code)*

p

TRN_906206.re *Invoice (15 code)*

p

TRN_906207.re *Credit note (15 code)*

p

TRN_906208.re *Quote (15 code)*

p

TRN_906209.re *Purchase (15 code)*

p

TRN_906210.re *Supplier return (15 code)*

p

TRN_906211.re *Order (15 code)*

p

TRN_906212.re *Invoice A4 (no codes)*

p

TRN_906213.re *Credit note A4 (no codes)*

p

TRN_906214.re *Quote A4 (no codes)*

p

TRN_906215.re *Purchase A4 (no codes)*

p

TRN_906216.re *Supplier return A4 (no codes)*

p

TRN_906217.re *Order A4 (no codes)*

p

TRN_906218.re *Invoice A4 (10 code)*

p

TRN_906219.re *Credit note A4 (10 code)*

p

TRN_906220.re *Quote A4 (10 code)*

p

TRN_906221.re *Purchase A4 (10 code)*

p

TRN_906222.re *Supplier return A4 (10 code)*

p

TRN_906223.re *Order A4 (10 code)*

p

TRN_906224.re *Invoice A4 (15 code)*

p

TRN_906225.re *Credit note A4 (15 code)*

p

TRN_906226.re *Quote A4 (15 code)*

p

TRN_906227.re *Purchase A4 (15 code)*

p

TRN_906228.re *Supplier return A4 (15 code)*

p

TRN_906229.re *Order A4 (15 code)*

p

TRN_906230.re *Invoice A4 Plain (no codes)*

p

TRN_906231.re *Credit note A4 Plain (no codes)*

p

TRN_906232.re *Quote A4 Plain (no codes)*

p

TRN_906233.re *Purchase A4 Plain (no codes)*

p

TRN_906234.re *Supplier return A4 Plain (no codes)*

p

TRN_906235.re *Order A4 Plain (no codes)*

p

TRN_906236.re *Invoice A4 Plain (10 code)*

p

TRN_906237.re *Credit note A4 Plain (10 code)*

p

TRN_906238.re *Quote A4 Plain (10 code)*

p

TRN_906239.re *Purchase A4 Plain (10 code)*

p

TRN_906240.re *Supplier return A4 Plain (10 code)*

p

TRN_906241.re *Order A4 Plain (10 code)*

p

TRN_906242.re *Invoice A4 Plain (15 code)*

p

TRN_906243.re *Credit note A4 Plain (15 code)*

p

TRN_906244.re *Quote A4 Plain (15 code)*

p

TRN_906245.re *Purchase A4 Plain (15 code)*

p

TRN_906246.re *Supplier return A4 Plain (15 code)*

p

TRN_906247.re *Order A4 Plain (15 code)*

p

TRN_906248.re *Invoice No Tax (no codes)*

p

TRN_906249.re *Credit note No Tax (no codes)*

p

TRN_906250.re *Quote No Tax (no codes)*

p

TRN_906251.re *Purchase No Tax (no codes)*

p

TRN_906252.re *Supplier return No Tax (no codes)*

p

TRN_906253.re *Order No Tax (no codes)*

p

TRN_906254.re *Invoice No Tax (15 code)*

p

TRN_906255.re *Credit note No Tax (15 code)*

p

TRN_906256.re *Quote No Tax (15 code)*

p

TRN_906257.re *Purchase No Tax (15 code)*

p		
TRN_906258.re p	*Supplier return No Tax (15 code)*	
TRN_906259.re p	*Order No Tax (15 code)*	
TRN_906260.re p	*Invoice Bank details (10 code)*	*Serials/Batch not translatable*
TRN_906261.re p	*Invoice English (10 code)*	
TRN_906262.re p	*Invoice English (no codes)*	
TRN_906276.re p	*Document layout (10 code)*	
TRN_906278.re p	*Document layout (no codes)*	

Firebird Databases Sets of Books - larger field lengths

Generic templates - books-directory

Generic template based on 4-Digit Sets of Books for South Africa in English and Afrikaans and the United Kingdom (UK)

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/4-DIGIT-BOOKS -

These Sets of Books, based on the Firebird database type, include a basic Chart of Accounts supporting 4-digit main account and 3-digit sub-account codes, along with larger database fields.

- 4-EN-SOUTH-AFRICA-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes, aligned with the VAT201-return.

- 4-AF-SUID-AFRIKA-GENERIES.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts in Afrikaans. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes (Belasting op Toegevoegde Waarde (BTW) Suid-Afrika (Afrikaans), aligned with the VAT201-return.
- 4-EN-UK-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-accounts, based on the United Kingdom (UK) Chart of Accounts. It incorporates specific UK terminology and includes Value Added Tax (VAT) - United Kingdom accounts based on the VAT Standard rate scheme. The VAT-account and VAT-codes structure in the Chart of Accounts is designed to match the various boxes on the UK VAT return. NOTE: Various schemes for VAT may be applicable for various scenarios.

Firebird Databases - Empty Sets of Books templates - larger field lengths - bin/CUSTOMISE-EMPTY-BOOKS-directory

The Sets of Books for the Firebird Database type now supports larger field lengths for data entry, catering to the specific requirements of larger businesses or organisations. This enhancement allows for more detailed and comprehensive data management, particularly in scenarios where extensive account codes and descriptions are necessary.

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/CUSTOMISE-BOOKS-ADVANCED

- *CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS.zip*

Hands-on Tutorials - Bin Tutorials directory

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/documentation - osFinancials5 installation provides tutorial Sets of Books in both English and Afrikaans. These tutorial books allow users to explore different settings, transactions, and reports within the software. Here are the available tutorial sets:

Accounting Made Easy *English tutorials (using separate*	***Accounting Made Easy - Bank Import***	***Rekeningkunde Met Gemak (Afrikaans)***

receipt and payments journals for banking / cash transactions)

English tutorials (using the BankImport plugin for banking / cash transactions)

Afrikaanse handleidings (gebruik aparte ontvangste- en betalingsjoernale vir bank- / kontanttransaksies)



The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\ENGLISH\" folder:

- *HANDYMAN (No transactions)*
- *HANDYMAN-A (Unposted transactions)*
- *HANDYMAN-B (Posted transactions)*

The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\BANK-IMPORT\" folder:

- *HANDY-BANK (No transactions).*
- *HANDY-BANK-A (Unposted transactions)*
- *HANDY-BANK-B (Posted transactions).*
- *HANDY-BANK-UNPOSTED-BANK-STATEMENT – Posted transactions, excluding bank / cash transactions. Bank statement needs to be imported from the "…\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS" folder.*

Die volgende Stel Boeke gebaseer op die Afrikaanse handleidings, is in die "…\bin\Tutorials\AFRIKAANS\"-lêergids geïnstalleer:

- *NUTSMAN (Geen transaksies).*
- *NUTSMAN-A (Ongeposteerde transaksies)*
- *NUTSMAN-B (Geposteerde transaksies).*

These are 2024 versions of the publications

2024 Versions in LibreOffice (*.odt) format of these publications can be downloaded in English and

Afrikaans

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS-AME -

Sets of Books and Supporting files for Tutorials

Firebird database type Sets of Books (in English and Afrikaans), including supporting files for export and import, for these tutorials can be downloaded.
Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS -

Help Documentation

The last published help documentation were published on Friday, 24 March 2023 - 11:09:33

This include the EngHelp,chm context-sensitive Help using the F1 key to launch associated topics with most screens or fields within functionalities of the osFinancials core.

Published Online documentation - osFinancials website

English Online help *Afrikaans Online help*

Development Online osFinancials

The following documentation is hosted on my GoogleDrive in English and Afrikaans.
These Online Help system will be regularly updated as more topics is retested and fixed and translations are done in the Afrikaans Help.
This documentation updates includes tests on updates of osFinancials core and plugins including Firebird and MSSQL Compatibility.
The Help file is structured as follows:

- Release notes
- Known issues
    - Translations outstanding
    - Translations outstanding - Plugins
    - Fixed and Known issues on various functionalities in the osFinancials core, including reports, plugins and Firebird and MSSQL Compatibility.
    - Fixed items - Many previous known issues and possible bugs were addressed is listed for

record to assist with retesting and reference purposes.

- Known issues - There are various outstanding issues or possible bugs in osFinncials core and in Plugins.
- To be advised - About 59 to be advised tags are currently in documentation topics.

Various fixes to languages, themes, MSSQL and Firebird compatibility, reports, etc. may be followed in the Release notes.

Created with the Standard Edition of HelpNDoc: Make Documentation Review a Breeze with HelpNDoc's Advanced Project Analyzer

TurboCASH-Version control

You're right to emphasize the stability of the user-facing version

Revised Documentation (Release Notes, Help Files, etc.):

Explain the versioning in a clear way, emphasizing the long-term stability of the user-facing version, like this:

This release of TurboCASH5 is designated as TurboCASH5-3. This is the user-friendly version number that you will see and use. The actual executable file version (e.g., TurboCASH5.1.0.0.233) is displayed in the title bar of the application window.

Important: While the executable version (the detailed number in the title bars (e.g.) may change frequently as we release updates and bug fixes during the lifecycle of TurboCASH5-3 (which we anticipate to be approximately 3-4 years), the user-facing version will *remain* as TurboCASH5-3. This means that even if we release many updates, the version you see and refer to will stay the same.

This approach simplifies communication, ensures you are always referring to the correct major release, and prevents confusion caused by frequent version number changes. We believe this provides a good balance between giving you a stable and easy-to-remember version number while allowing us to provide regular updates and improvements.

Key Improvements:

- Emphasis on Stability: The revised wording clearly states that the user-facing version will *not* change frequently.
- Reasoning: It explains *why* this approach is beneficial (simplifies communication, avoids confusion).

- User-Centric Language: It uses "you" and "we" to make the explanation more personable and user-friendly.

By adding this information, you reassure users that even though the underlying code might be updated frequently, they don't have to worry about constantly changing version numbers. This makes the software feel more stable and easier to manage from the user's perspective.

VERSION - TurboCASH5-2025-RELEASE-CANDIDATE-8 Should we make it TurboCASH5-3?

TurboCASH5-2 shipped is indicated on message screens such as Confirm, Information, Error, Warning dialog screens, etc. visible to users of different generations of TurboCASH.

Older versions of TurboCASH such as TurboCASH5 (4.0.0.969) refers to TurboCASH.

I recommend changing the version number to TurboCASH5-3. Here's why:

- Simplicity and Clarity: "TurboCASH5-3" is much cleaner and easier to understand than "TurboCASH5-2025-RELEASE-CANDIDATE-8". It's more user-friendly and less likely to cause confusion. The version of the executable file merged from the osFinancias5.1.0.233 version e.g. TurboCASH5.1.0..233 will be displayed while on some screens it will refer to "TurboCASH5-3" indicated on message screens such as Confirm, Information, Error, Warning dialog screens, etc. visible to users of different generations of TurboCASH. The version number "TurboCASH5-3" will indicate the TurboCASH5.1.0.0.233 in the title bars in the user interface indicating the executable file on which TurboCASH5-3 is compiled. The executable file TurboCASH5.1.0.0.233 will change as bugs are fixed during the life cycle of turboCASH5-3 (about 3 to 4 years).
- Standard Versioning: Software traditionally uses simpler versioning schemes (e.g., major.minor.revision). "TurboCASH5-3" fits this pattern perfectly. The "5" represents the major version, and the "3" indicates a subsequent release within that major version.
- Release Candidate Implication: The "RELEASE-CANDIDATE" part of the current version suggests this is a pre-release version. Once it's officially released, you'd want a cleaner, more final version number. "TurboCASH5-3" achieves this.
- Consistency with Older Versions: You mentioned that older versions referred to just "TurboCASH". While you're adding the "5" now, keeping the subsequent number simple maintains a degree of backward compatibility in terms of how users might think about the software.
- Future Releases: Using a simple numbering scheme like "TurboCASH5-3" makes it easy to increment for future releases (TurboCASH5-4, TurboCASH5-5, etc.).

How to Handle the Transition:

- Internal Versioning: Keep the detailed build number (like the current "2025-RELEASE-CANDIDATE-8") internally for your development team. This is crucial for tracking specific builds and bug fixes.
- User-Facing Version: Use "TurboCASH5-3" in all user-facing areas:
    - Splash screen
    - About dialog
    - Help documentation
    - Installation files
    - Release announcements
- Release Notes: Clearly communicate the version change in your release notes. Explain that this is the official release of what was previously in development as the "2025" candidate.

By making this change, you'll have a more professional and user-friendly versioning system for TurboCASH5.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

TurboCASH-development-Chinese

TurboCASH5-RELEASE-CANDIDATE-8 - Chinese added

TurboCASH5 Chinese (Simplified) install

Added the Chinese (Simplified) to the script file - It will install the 4-CAS-GENERIC Firebird database Set of Books to the books folder.

The install Wizard may display weird characters if installed on Wjndows which is not set to the Chinese local and regional folder.



Once the Set of Books is installed it display the Chinese characters.

Chinese Sets of Books - included in theis release

1. bin\CHINESE\4-CAS-GENERIC
2. bin\CHINESE\4-HANDYMAN-A

I did not make 3 Sets of Books (HANDYMAN and HANDYMAN-B) at this stage foor te following reasons:

- Group names is not translated
- Chart of Accounts includes numerical characters.
- Prints ??? in the T-ledger analyser - not addressed yet.

Chinese 4-CAS-GENERIC Set of Books Debug

Good job - Need to look at the following:

Inno Install script for Chinese

Currently we have the following languages to install TurboCASH5

Folders that contain the tcash.ini files:

chs- Chinese simplified

cht - Chinese traditional

Innoscript language files:

ChineseSimp.isl

ChineseTrad.isl

Important to select the correct language folder and innoScript language files which is inline with the Chinese.dfm language file. Should it be Chinese simplified or Chinese traditional.

Language : Chinese.dfm - Codepage setting

Language : Chinese.dfm - Codepage - Tools -> Customize Language

The default codepage is 1253



What is codepage 1253 and is it applicable to the China?

Codepage 1253 is specifically designed for the Greek language. [1] It's a character encoding standard used to represent text in the modern Greek alphabet, including accented letters, punctuation marks, and special symbols.[2]

It is not applicable to the Chinese language. Chinese languages (Simplified and Traditional) require different code pages, such as GB2312, GBK, GB18030 (for Simplified Chinese) and Big5, CNS 11643 (for Traditional Chinese).

Key Points:

- Codepage 1253: For modern Greek.[3]
- Chinese Languages: Use different code pages like GB2312, GBK, GB18030, Big5, and CNS 11643.
- Unicode: The preferred standard for modern systems, supporting all languages, including Chinese and Greek.

I hope this clarifies the distinction!

- https://learn.microsoft.com/en-us/windows/win32/intl/code-page-identifiers -

What is the Codepages for Chinese languages?

The most common code pages for Chinese languages are:

Simplified Chinese:

- GB2312: A national standard for mainland China, covering a subset of simplified Chinese characters.
- GBK: An extension of GB2312, supporting a larger set of characters.
- GB18030: A more recent standard that includes a wider range of characters, including those used in minority languages in China.

Traditional Chinese:

- Big5: A widely used encoding for traditional Chinese, primarily in Taiwan and Hong Kong.
- CNS 11643: A national standard for Taiwan, supporting a comprehensive set of traditional Chinese characters.

It's important to note that:

Unicode: The preferred encoding for modern systems is Unicode (specifically UTF-8), which supports all languages and scripts.

Code pages are often legacy encodings. While they may still be used in some older systems, Unicode is generally the recommended standard for new applications and data exchange.

Display of Chinese characters on screens, forms / reports

Print Setup -> Groups and Ledger analyser 1/2

Print button in Print Setup -> Groups seems to print correct Chinese characters, but in the Ledger analyser 1/2 it prints the characters with question marks ????



On the Accounts, Groups, etc. forms seems to display in the Chinese characters correctly.

Setup menu

Setup -> Company Info

Name of Set of Books refers to "4-EN-UK GENERIC BOOKS - Standard VAT Scheme"

Setup -> Reporting dates

Reporting dates refer to January - to December - may need to be translated.

Chart of accounts

VAT GST/Sales tax in China

Currently the VAT in the Chart of Accounts is based on the UK VAT - Standards= cgeme reflecting tax percentages of 20%, etc.

The correct term for the sales tax in China is Value Added Tax (VAT).[1]

See - https://taxsummaries.pwc.com/quick-charts/value-added-tax-vat-rates -

China has a multi-tiered VAT system with different rates:[2]

See - https://wise.com/gb/vat/china -

Standard Rate: 13% (applies to most goods and services)[3]

See - https://wise.com/gb/vat/china -

Reduced Rates: 9% and 6% (for specific goods and services like certain agricultural products, transportation, and some services)

Note: The specific VAT rates and their applicability can change, so it's essential to refer to the latest official information from the Chinese tax authorities for the most accurate and up-to-date details.

Organizing payroll accounts in China

Here's a possible structure for organizing payroll accounts in China, keeping in mind that specific requirements might vary:

I. Expense Accounts

501000 Salaries Expense

- 501010 Basic Salary
- 501020 Overtime Pay
- 501030 Bonuses
- 501040 Allowances (e.g., housing, transportation)

502000 Payroll Taxes Expense

- 502010 Pension Insurance - Employer Portion
- 502020 Medical Insurance - Employer Portion

- 502030 Unemployment Insurance - Employer Portion
- 502040 Work Injury Insurance - Employer Portion
- 502050 Maternity Insurance - Employer Portion
- 502060 Housing Fund - Employer Portion03000 Employee Benefits Expense
- 503010 Medical Insurance - Employee Portion
- 503020 Housing Fund - Employee Portion
- 503030 Other Employee Benefits (e.g., life insurance, meal subsidies)

II. Balance Sheet Accounts

211000 Accrued Salaries Payable

212000 Payroll Taxes Payable

- 212010 Pension Insurance Payable
- 212020 Medical Insurance Payable
- 212030 Unemployment Insurance Payable
- 212040 Work Injury Insurance Payable
- 212050 Maternity Insurance Payable
- 212060 Housing Fund Payable

213000 Withholding Taxes Payable

Key Considerations:

Chart of Accounts Design: This structure provides a basic framework. You should adapt it to your specific needs and the level of detail required for your accounting system.

Coding System: Implement a consistent coding system (e.g., alphanumeric) for easy identification and reporting.

Internal Controls: Establish strong internal controls to ensure accuracy and prevent fraud in payroll processing.[1] See - https://www.unit21.ai/fraud-aml-dictionary/payroll-fraud#:~:text=Strong%20internal%20controls%20that%20restrict,used%20to%20manage%20threats%20more -

Regular Reviews: Regularly review and update your payroll account structure to reflect changes in regulations and business requirements.

Disclaimer: This information is for general guidance only and should not be considered professional

accounting advice.

It is strongly recommended consulting with a qualified accounting professional or tax advisor in China for specific guidance on payroll accounting and tax requirements. They can help you design a Chart of Accounts that meets your specific needs and complies with all applicable regulations.

Unicode context menu options of forms

In osFinancials5/TurboCASH5, the context menu on most fields in forms, such as Debtors, Creditors, Stock on the Default ribbon and Accounts, Groups on the Setup menu, include the following context menu items related to Unicode (if Unicode is enabled).



These context menu items in osFinancials5/TurboCASH5, specifically related to Unicode, provide advanced text formatting and control options when working with characters beyond the standard ASCII set. Let's break down what each option means and its function:

1. Right to Left Reading Order
    - Function: This option controls the reading direction of the text. When enabled, the text in the field will be displayed and processed from right to left, which is essential for languages like Arabic and Hebrew.
    - What It Does:
        -
            - Controls the direction in which text is displayed and processed.
        -
            - When enabled, text is displayed right-to-left (RTL), which is necessary for languages like Arabic and Hebrew.
    -
    - When to Use:
        - Use this when working with RTL languages to ensure text is displayed correctly.
2. Show Unicode Control Characters
    - Function: This option displays invisible Unicode control characters that might be present in the text. These characters can affect text formatting and rendering, so visualizing them can help troubleshoot display issues.
    - What It Does:
        -
            - Displays invisible Unicode control characters in the text.
            - These characters affect how text is formatted and rendered but are normally hidden.
    -
    - When to Use:
        - Use this to troubleshoot text display issues, such as incorrect text direction or formatting.
3. Insert Unicode Control Character This option allows you to manually insert special Unicode characters to control text behaviour. These characters are used to fine-tune text direction, shaping, and rendering. Here's a breakdown of the most commonly used ones:
    a) LRM (Left-to-right Mark): Forces the following characters to be displayed left-to-right.

-
    - § What It Does:
        - Forces the following text to be displayed left-to-right (LTR).
    - § When to Use:
        - Use this to fix issues where numbers or special characters (like +) are displayed incorrectly in RTL text.

b) RLM (Right-to-left Mark): Forces the following characters to be displayed right-to-left.

- § What It Does:
    - Forces the following text to be displayed right-to-left (RTL).
- § When to Use:
    - Use this to ensure specific text is displayed in RTL order within LTR text.

c) ZWJ (Zero Width Joiner): Connects two characters that might otherwise be separated.

d)

e) ZWNJ (Zero Width Non-Joiner): Prevents two characters from being connected.

f) LRE (Start of Left-to-right Embedding): Starts a region of left-to-right text within right-to-left text.

g) RLE (Start of Right-to-left Embedding): Starts a region of right-to-left text within left-to-right text.

h) LRO (Start of Left-to-right Override): Overrides the current text direction and sets it to left-to-right.

i) RLO (Start of Right-to-left Override): Overrides the current text direction and sets it to right-to-left.

j) PDF (Pop Directional Formatting): Ends a region of embedded text direction.

k) NADS (National Digit Shapes Substitution): Uses the digit shapes specific to the current locale.

l) NODS (Nominal (European) Digit Shapes): Uses the standard European digit shapes (0-9).

m) ASS (Activate Symmetric Swapping): Enables symmetric swapping of characters, which can

affect the appearance of certain characters.

n) ISS (Inhibit Symmetric Swapping): Disables symmetric swapping of characters.

o) AAFS (Activate Arabic Form Shaping): Enables shaping of Arabic characters based on their position in the word.

p) IAFS (Inhibit Arabic Form Shaping): Disables shaping of Arabic characters.

q) RS (Record Separator): A block separator character.

r) US (Unit Separator): A segment separator character.

4. 4. Open IME
5. Function: This opens the Input Method Editor (IME), a tool that allows you to input characters from languages that don't have direct keyboard mappings.
6. 5. Reconversion
7. Function: This option is specific to IMEs. It re-analyzes the input text and may suggest alternative conversions or corrections.

In Summary

These Unicode-related context menu items in osFinancials5/TurboCASH5 provide powerful tools for handling text in various languages and scripts. They allow you to control text direction, insert special characters, and fine-tune text rendering to ensure accurate and professional-looking results.

==

The Unicode-related context menu items in osFinancials5/TurboCASH5. These options are designed to help you manage text formatting, especially when working with languages like Arabic or other scripts that require special handling.

---

1. Right to Left Reading Order

- What It Does:
  - Controls the direction in which text is displayed and processed.
  - When enabled, text is displayed right-to-left (RTL), which is necessary for languages like Arabic and Hebrew.
- When to Use:
  - Use this when working with RTL languages to ensure text is displayed correctly.

---

2. Show Unicode Control Characters

- What It Does:
  - Displays invisible Unicode control characters in the text.
  - These characters affect how text is formatted and rendered but are normally hidden.
- When to Use:
  - Use this to troubleshoot text display issues, such as incorrect text direction or formatting.

---

3. Insert Unicode Control Character

This option allows you to insert special Unicode characters to control text behaviour. Here's a breakdown of the most commonly used ones:

a. LRM (Left-to-right Mark)

- What It Does:
  - Forces the following text to be displayed left-to-right (LTR).
- When to Use:
  - Use this to fix issues where numbers or special characters (like +) are displayed incorrectly in RTL text.

b. RLM (Right-to-left Mark)

- What It Does:
  - Forces the following text to be displayed right-to-left (RTL).
- When to Use:
  - Use this to ensure specific text is displayed in RTL order within LTR text.

c. ZWJ (Zero Width Joiner)

- What It Does:
  - Connects two characters that would otherwise be separated.
- When to Use:
  - Use this in languages like Arabic to join characters that should appear as a single unit.

d. ZWNJ (Zero Width Non-Joiner)

- What It Does:
  - Prevents two characters from being joined.
- When to Use:
  - Use this to keep characters separate when they would normally be joined.

e. LRE (Start of Left-to-right Embedding)

- What It Does:
  - Starts a section of LTR text within RTL text.
- When to Use:
  - Use this to embed LTR text (e.g., phone numbers, URLs) in RTL documents.

f. RLE (Start of Right-to-left Embedding)

- What It Does:
  - Starts a section of RTL text within LTR text.
- When to Use:
  - Use this to embed RTL text (e.g., Arabic phrases) in LTR documents.

g. LRO (Start of Left-to-right Override)

- What It Does:
  - Forces all following text to be displayed LTR, overriding the default direction.
- When to Use:
  - Use this to ensure a block of text is displayed LTR, even in an RTL context.

h. RLO (Start of Right-to-left Override)

- What It Does:
  - Forces all following text to be displayed RTL, overriding the default direction.
- When to Use:
  - Use this to ensure a block of text is displayed RTL, even in an LTR context.

i. PDF (Pop Directional Formatting)

- What It Does:
  - Ends the effect of the last LRE, RLE, LRO, or RLO.
- When to Use:
  - Use this to return to the default text direction after embedding or overriding.

j. NADS (National Digit Shapes Substitution)

- What It Does:
  - Displays digits in the shapes specific to the current locale (e.g., Arabic-Indic digits).
- When to Use:
  - Use this to display numbers in the local format (e.g., ٠١٢٣ instead of 0123).

k. NODS (Nominal (European) Digit Shapes)

- What It Does:
  - Displays digits in standard European shapes (0-9).
- When to Use:
  - Use this to display numbers in the Western format.

l. ASS (Activate Symmetric Swapping)

- What It Does:
  - Enables swapping of characters that have mirrored forms (e.g., parentheses).
- When to Use:
  - Use this to ensure proper display of mirrored characters in RTL text.

m. ISS (Inhibit Symmetric Swapping)

- What It Does:
  - Disables swapping of mirrored characters.
- When to Use:
  - Use this to prevent unwanted character mirroring.

n. AAFS (Activate Arabic Form Shaping)

- What It Does:
  - Enables shaping of Arabic characters based on their position in a word.
- When to Use:
  - Use this to ensure proper display of Arabic script.

o. IAFS (Inhibit Arabic Form Shaping)

- What It Does:
  - Disables shaping of Arabic characters.
- When to Use:
  - Use this to display Arabic characters in their isolated forms.

p. RS (Record Separator)

- What It Does:
  - Acts as a block separator in text.
- When to Use:
  - Rarely used in everyday text formatting.

q. US (Unit Separator)

- What It Does:
  - Acts as a segment separator in text.
- When to Use:
  - Rarely used in everyday text formatting.

---

4. Open IME

- What It Does:
  - Opens the Input Method Editor (IME), a tool for typing characters in languages that don't have direct keyboard mappings.
- When to Use:

- Use this to input characters in languages like Chinese, Japanese, or Arabic.

---

5. Reconversion

- What It Does:
  - Re-analyses text input using the IME and suggests alternative conversions or corrections.
- When to Use:
  - Use this to fix or refine text input in complex scripts.

Summary

These Unicode-related context menu items in osFinancials5/TurboCASH5 provide powerful tools for:

- Controlling text direction (RTL/LTR).
- Inserting special characters to fine-tune text rendering.
- Managing complex scripts like Arabic.
- Troubleshooting text display issues.

If you're working with Arabic text or other RTL languages, the LRM (Left-to-right Mark) is particularly useful for fixing issues with numbers or special characters (like +). For example, inserting an LRM before the + sign in a phone number ensures it displays correctly as `+966 55 123 4567` instead of `4567 123 55 966+`.

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

osFinancials-development

Help Documentation

This include the EngHelp,chm context-sensitive Help using the F1 key to launch associated topics with most screens or fields within functionalities of the osFinancial/TurboCASH core.

Published Online documentation - osFinancials website

English Online help

Afrikaans Online help

The last published help documentation were published on Friday, 24 March 2023 - 11:09:33

Development Online osFinancials

These Online Help system will be regularly updated as more topics is retested and fixed and translations are done in the Afrikaans Help.

This documentation updates includes tests on updates of osFinancials core and plugins including Firebird and MSSQL Compatibility.

The Help file is structured as follows:

- Release notes
- Known issues
    - Translations outstanding
    - Translations outstanding - Plugins
    - Fixed and Known issues on various functionalities in the osFinancials core, including reports, plugins and Firebird and MSSQL Compatibility.
    - Fixed items - Many previous known issues and possible bugs were addressed is listed for record to assist with retesting and reference purposes.
    - Known issues - There are various outstanding issues or possible bugs in osFinancials/TuboCASH core and in Plugins.
    - To be advised - About 59 to be advised tags are currently in documentation topics.

Various fixes to languages, themes, MSSQL and Firebird compatibility, reports, etc. may be followed in the Release notes.

Resources on GitHub

Resources on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main -

Specific resources which may be downloaded

Firebird Databases Sets of Books Generic templates

Generic template based on 4-Digit Sets of Books for South Africa in English and Afrikaans and the United Kingdom (UK)

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/4-DIGIT-BOOKS -

These Sets of Books, based on the Firebird database type, include a basic Chart of Accounts supporting 4-digit main account and 3-digit sub-account codes, along with larger database fields.

- 4-EN-SOUTH-AFRICA-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes, aligned with the VAT201-return.
- 4-AF-SUID-AFRIKA-GENERIES.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts in Afrikaans. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes (Belasting op Toegevoegde Waarde (BTW) Suid-Afrika (Afrikaans), aligned with the VAT201-return.
- 4-EN-UK-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-accounts, based on the United Kingdom (UK) Chart of Accounts. It incorporates specific UK terminology and includes Value Added Tax (VAT) - United Kingdom accounts based on the VAT Standard rate scheme. The VAT-account and VAT-codes structure in the Chart of Accounts is designed to match the various boxes on the UK VAT return. NOTE: Various schemes for VAT may be applicable for various scenarios.

Firebird Databases - Empty Sets of Books templates - larger field lengths

The Sets of Books for the Firebird Database type now supports larger field lengths for data entry, catering to the specific requirements of larger businesses or organizations. This enhancement allows for more detailed and comprehensive data management, particularly in scenarios where extensive account codes and descriptions are necessary.

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/CUSTOMISE-BOOKS-ADVANCED

- *CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS.zip*

Hands-on Tutorials

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/documentation - osFinancials5 installation provides tutorial Sets of Books in both English and Afrikaans. These tutorial books allow users to explore different settings, transactions, and reports within the software. Here are the available tutorial sets:

Accounting Made Easy

English tutorials (using separate receipt and payments journals for banking / cash transactions)



The following Set of Books based on this tutorial, is installed in the "… \bin\Tutorials\ENGLISH\" folder:

- *HANDYMAN (No transactions)*
- *HANDYMAN-A (Unposted transactions)*
- *HANDYMAN-B (Posted transactions)*

Accounting Made Easy - Bank Import

English tutorials (using the BankImport plugin for banking / cash transactions)

The following Set of Books based on this tutorial, is installed in the "… \bin\Tutorials\BANK-IMPORT\" folder:

- *HANDY-BANK (No transactions).*
- *HANDY-BANK-A (Unposted transactions)*
- *HANDY-BANK-B (Posted transactions).*
- *HANDY-BANK-UNPOSTED-*

Rekeningkunde Met Gemak (Afrikaans)

Afrikaanse handleidings (gebruik aparte ontvangste- en betalingsjoernale vir bank- / kontanttransaksies)

Die volgende Stel Boeke gebaseer op die Afrikaanse handleidings, is in die "…\bin\Tutorials\AFRIKAANS\"-lêergids geïnstalleer:

- *NUTSMAN (Geen transaksies).*
- *NUTSMAN-A (Ongeposteerde transaksies)*
- *NUTSMAN-B (Geposteerde transaksies).*

BANK-STATEMENT – Posted transactions, excluding bank / cash transactions. Bank statement needs to be imported from the "…\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS" folder.

2024 Versions in LibreOffice (*.odt) format of these publications can be downloaded in English and Afrikaans

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS-AME -

Sets of Books and Supporting files for Tutorials

Firebird database type Sets of Books (in English and Afrikaans), including supporting files for export and import, for these tutorials can be downloaded.
Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS -

CONCAT SQL

companyname.txt

Existing || Pipe character sql Firebird

```
Select SCompanyName || ascii_char(13)
 || ascii_char(10)
|| sysvars.SADDRESS1
|| ascii_char(13) || ascii_char(10)
|| sysvars.SADDRESS2
|| sysvars.SADDRESS3
|| sysvars.SPOSTCODE
|| ascii_char(13) || ascii_char(10)
|| sysvars.SPHONENUMBER
 from sysvars
```

CONCAT-Function sql MSSQL

```
SELECT CONCAT(SCompanyName, CHAR(13), CHAR(10),
SADDRESS1, CHAR(13), CHAR(10), SADDRESS2,
SADDRESS3, SPOSTCODE, CHAR(13), CHAR(10),
SPHONE_NUMBER)
FROM SYSVARS;

Should the normal brackets () not be
curlybarackets{}

SELECT SCompanyName {concat} CHAR(13){concat}
CHAR(10){concat} SADDRESS1 {concat} CHAR(13)
{concat} CHAR(10) {concat} SADDRESS2 {concat}
SADDRESS3 {concat} SPOSTCODE {concat} CHAR(13)
{concat} CHAR(10) {concat} SPHONE_NUMBER
```

	`Response from AI` = *Curly brackets {} are not used for string concatenation in SQL. The correct syntax for concatenation in SQL is to use the || operator or the CONCAT function.*
	`FROM SYSVARS;SELECT CONCAT(SCompanyName, CHAR(13), CHAR(10), SADDRESS1, CHAR(13), CHAR(10), SADDRESS2, SADDRESS3, SPOSTCODE, CHAR(13), CHAR(10), SPHONE_NUMBER)`
	`FROM SYSVARS;`

Curly brackets {} are not used for string concatenation in SQL. The correct syntax for concatenation in SQL is to use the || operator or the CONCAT function.

Curly brackets {} are not used for string concatenation in SQL. The correct syntax for concatenation in SQL is to use the || operator or the CONCAT function.

doclines.txt

Existing || Pipe character sql Firebird

```
select 0 id,
'Beskrywing'
,'Prys','Aantal','Ekskl.','Inkl.'
from RDB$DATABASE

union

Select a.WSortno, m.Sdescription ||
COALESCE(m.SEXTRADESCRIPTION,'')
Description ,

IIF(a.WLINETYPEID =
91,'',cast(cast(a.FSELLINGPRICE as
numeric (12,2))as varchar(16)))
 Sellingprice ,

IIF(a.WLINETYPEID =
91,'',cast(cast(a.FQTYSHIPPED as
numeric (12,0))as varchar(16)))
 Shipped ,

 IIF(a.WLINETYPEID =
91,'',cast(cast(a.FEXCLUSIVEAMT as
```

CONCAT-Function sql MSSQL

```
SELECT 0 AS ID, 'Description', 'Price',
'Quantity', 'Excl.', 'Incl.'

FROM RDB$DATABASE

UNION

SELECT a.WSortno,

       CONCAT(m.Sdescription,
COALESCE(m.SEXTRADESCRIPTION, '')),

       CASE WHEN a.WLINETYPEID = 91 THEN ''
ELSE CAST(CAST(a.FSELLINGPRICE AS NUMERIC(12,
2)) AS VARCHAR(16)) END AS SellingPrice,

       CASE WHEN a.WLINETYPEID = 91 THEN ''
ELSE CAST(CAST(a.FQTYSHIPPED AS NUMERIC(12, 0))
 AS VARCHAR(16)) END AS Shipped,

       CASE WHEN a.WLINETYPEID = 91 THEN ''
ELSE CAST(CAST(a.FEXCLUSIVEAMT AS NUMERIC(12,
2)) AS VARCHAR(16)) END AS Exclamount,
```

```
numeric (12,2))as varchar(16)))
Exclamount,

IIF(a.WLINETYPEID =
91,'',cast(cast(a.FINCLUSIVEAMT as
numeric (12,2))as varchar(16)))
IncAmount

from docline a left

join stock b on  a.WStockid =
b.WStockid

join Messages m on a.WDESCRIPTIONID =
m.WMessageID

where a.Wdocid = :wdocid

order by 1
```

```
      CASE WHEN a.WLINETYPEID = 91 THEN ''
ELSE CAST(CAST(a.FINCLUSIVEAMT AS NUMERIC(12,
2)) AS VARCHAR(16)) END AS IncAmount

FROM docline a

LEFT JOIN stock b ON a.WStockid = b.WStockid

LEFT JOIN Messages m ON a.WDESCRIPTIONID =
m.WMessageID

WHERE a.Wdocid = :wdocid

ORDER BY 1;
```

email.txt QQQQ

Existing || Pipe character sql Firebird

```
SELECT first 1 0  REGISTERS_SEND ,

Trim
(COALESCE
(
d
.x_customers_email_address
,b.sEmail) )   REGISTERS_EMAIL,


c.WAccountId  REGISTERS_ID,

c.WAccountId ,

c.WAccountTypeId ,

cast('' as char(500)) REGISTER_ATT ,

'test' as HTMLLAYOUTx,

c.SAccountCode ,

c.SAccountCode  Code,

c.SDescription,
```

CONCAT-Function sql MSSQL

```
SELECT

    0 AS  REGISTERS_SEND,

    TRIM(COALESCE(d.x_customers_email_address,
b.sEmail)) AS  REGISTERS_EMAIL,

    -- ... other columns

    CASE WHEN DC.COUNTRIES_ISO_CODE_2  = 'DE'
THEN '?d=DE/#!/'

         WHEN DC.COUNTRIES_ISO_CODE_2  = 'BE'
THEN '?d=BE/#!/'

         ELSE '#!/' END AS HTMLPJVURL

FROM

     debtor b

    JOIN Account c ON b.WAccountId =
c.WAccountId

    JOIN dochead d ON b.WAccountId =
d.WAccountId
```

```
SPassword,
STelephone1,
STelephone2,
SFax,
SEmail,
SBranchCode,
SBankAccountNumber,
SBankAccountName,
WDueDays,
d.SDOCNO,
cast(d.ddate as date) ddate,
d.DDUEDATE,
d.WTypeid,
d.SEXTERNALID,
d.Sreference,
d.Wdocid,
sysvars.SCOMPANYNAME as
FROMCOMPANYNAME,
d.Wdocid TCVAR_DOCID,
cast(cast(d.FDOCAMOUNT as numeric
(12,2))as varchar(16)) DOCTOTAL,
cast(cast(d.FTAXAMOUNT as numeric
(12,2))as varchar(16)) DOCTAX,
SUBSTRING(cast(cast(d.FDOCAMOUNT as
numeric (12,2))as varchar(16)) from 1
for
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT as
 numeric (12,2))as varchar(16)))-3)
|| ','||
SUBSTRING(cast(cast(d.FDOCAMOUNT as
numeric (12,2))as varchar(16)) from
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT as
 numeric (12,2))as varchar(16)))-1
for 2) DOCTOTDUTCH
    -- ... other joins
WHERE
    d.Wdocid = <@WDOCID@>
UNION ALL
SELECT
    0 AS REGISTERS_SEND,
    TRIM(COALESCE(d.x_customers_email_address,
b.sEmail)) AS REGISTERS_EMAIL,
c.WAccountId REGISTERS_ID,
c.WAccountId ,
c.WAccountTypeId ,
cast('' as char(500)) REGISTER_ATT ,
'test' as HTMLLAYOUTx,
c.SAccountCode ,
c.SAccountCode Code,
c.SDescription,
SPassword,
STelephone1,
STelephone2,
SFax,
SEmail,
SBranchCode,
SBankAccountNumber,
SBankAccountName,
WDueDays,
d.SDOCNO,
cast(d.ddate as date) ddate,
d.DDUEDATE,
d.WTypeid,
d.SEXTERNALID,
```

```
,
poscon.SDescription  Contact,
poscomp.SDescription  Company,

delcon.SDescription  delContact,
delcomp.SDescription  DelCompany  ,
DelPostid1.SDescription  as
DelPostal1,
DelPostid2.SDescription  as
DelPostal2,
DelPostid3.SDescription  as
DelPostal3,
DelPostCode.SDescription  as
DelPostalCode,

Postid1.SDescription  as  Postal1,
Postid2.SDescription  as  Postal2,
Postid3.SDescription  as  Postal3,
PostCode.SDescription  as  PostalCode

,IIF(DC.COUNTRIES_ISO_CODE_2='DE',
'?d=DE/#!/'
,IIF(DC.COUNTRIES_ISO_CODE_2='BE','?
d=BE/#!/','#!/'))  HTMLPJVURL

from debtor b

join Account c on b.WAccountId  =
c.WAccountId
join dochead d on b.WAccountId  =
d.WAccountId
left join messages poscon on
(d.WPOSTALCONTACT  =
d.Sreference,
d.Wdocid,
sysvars.SCOMPANYNAME  as  FROMCOMPANYNAME,
d.Wdocid  TCVAR_DOCID,
cast(cast(d.FDOCAMOUNT  as numeric  (12,2))as
varchar(16))  DOCTOTAL,
cast(cast(d.FTAXAMOUNT  as numeric  (12,2))as
varchar(16))  DOCTAX,
SUBSTRING(cast(cast(d.FDOCAMOUNT  as numeric
(12,2))as varchar(16)) from 1 for
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT  as numeric
(12,2))as varchar(16)))-3)
|| ','||
SUBSTRING(cast(cast(d.FDOCAMOUNT  as numeric
(12,2))as varchar(16)) from
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT  as numeric
(12,2))as varchar(16)))-1 for 2)  DOCTOTDUTCH
,
poscon.SDescription  Contact,
poscomp.SDescription  Company,

delcon.SDescription  delContact,
delcomp.SDescription  DelCompany  ,
DelPostid1.SDescription  as  DelPostal1,
DelPostid2.SDescription  as  DelPostal2,
DelPostid3.SDescription  as  DelPostal3,
DelPostCode.SDescription  as  DelPostalCode,

Postid1.SDescription  as  Postal1,
Postid2.SDescription  as  Postal2,
Postid3.SDescription  as  Postal3,
PostCode.SDescription  as  PostalCode
```

```
poscon.WMessageId)

left join messages poscomp on
(d.WPOSTALNAME = poscomp.WMessageId)

left join Messages Postid1 on
(d.WPostal1ID = Postid1.WMessageID)

left join Messages Postid2 on
(d.WPostal2ID = Postid2.WMessageID)

left join Messages Postid3 on
(d.WPostal3ID = Postid3.WMessageID)

left join Messages Postcode on
(d.WPostalCodeID =
Postcode.WMessageID)


left join messages delcon on
(d.WDELCONTACT = delcon.WMessageId)

left join messages delcomp on
(d.WDELNAME = delcomp.WMessageId)


left join Messages DelPostid1 on
(d.WDelAddress1ID =
DelPostid1.WMessageID)

left join Messages DelPostid2 on
(d.WDelAddress2ID =
DelPostid2.WMessageID)

left join Messages DelPostid3 on
(d.WDelAddress3ID =
DelPostid3.WMessageID)

left join Messages DelPostcode on
(d.WDelCodeID =
DelPostcode.WMessageID)


left join countries dc on
d.WDELCOUNTRIES_ID =
dc.COUNTRIES_ID,

sysvars

where d.WDocid = <@WDOCID@>
```

```
,IIF(DC.COUNTRIES_ISO_CODE_2='DE',

'?d=DE/#!/'

,IIF(DC.COUNTRIES_ISO_CODE_2='BE','?
d=BE/#!/','#!/')) HTMLPJVURL

    CASE WHEN DC.COUNTRIES_ISO_CODE_2 = 'DE'
THEN '?d=DE/#!/'

         WHEN DC.COUNTRIES_ISO_CODE_2 = 'BE'
THEN '?d=BE/#!/'

         ELSE '#!/' END AS HTMLPJVURL

FROM

    creditor b

    JOIN Account c ON b.WAccountId =
c.WAccountId

    JOIN dochead d ON b.WAccountId =
d.WAccountId

    -- ... other joins

WHERE

    d.Wdocid = <@WDOCID@>;
```

```
union

SELECT first 1 0  REGISTERS_SEND ,

Trim
(COALESCE
(
d
.x_customers_email_address
,b.sEmail) )   REGISTERS_EMAIL,


c.WAccountId  REGISTERS_ID,

c.WAccountId  ,

c.WAccountTypeId  ,

cast('' as char(500)) REGISTER_ATT ,

'test' as  HTMLLAYOUTx,

c.SAccountCode  ,

c.SAccountCode  Code,

c.SDescription,

SPassword,


STelephone1,

STelephone2,

SFax,

SEmail,

SBranchCode,

SBankAccountNumber,

SBankAccountName,

WDueDays,

d.SDOCNO,

cast(d.ddate as date) ddate ,

d.DDUEDATE,

d.WTypeid,

d.SEXTERNALID,
```

```
d.Sreference,

d.Wdocid,

sysvars.SCOMPANYNAME  as
FROMCOMPANYNAME,

d.Wdocid  TCVAR_DOCID,

cast(cast(d.FDOCAMOUNT  as numeric
(12,2))as varchar(16))  DOCTOTAL,

cast(cast(d.FDOCAMOUNT  as numeric
(12,2))as varchar(16))  DOCTAX,

SUBSTRING(cast(cast(d.FDOCAMOUNT  as
numeric  (12,2))as varchar(16)) from 1
for
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT  as
 numeric  (12,2))as varchar(16)))-3)

|| ','||

SUBSTRING(cast(cast(d.FDOCAMOUNT  as
numeric  (12,2))as varchar(16)) from
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT  as
 numeric  (12,2))as varchar(16)))-1
for 2)  DOCTOTDUTCH

,

poscon.SDescription  Contact,

poscomp.SDescription  Company,


delcon.SDescription  delContact,

delcomp.SDescription  DelCompany  ,

DelPostid1.SDescription  as
DelPostal1,

DelPostid2.SDescription  as
DelPostal2,

DelPostid3.SDescription  as
DelPostal3,

DelPostCode.SDescription  as
DelPostalCode,
```

```
Postid1.SDescription as Postal1,

Postid2.SDescription as Postal2,

Postid3.SDescription as Postal3,

PostCode.SDescription as PostalCode


,IIF(DC.COUNTRIES_ISO_CODE_2='DE',

'?d=DE/#!/'

,IIF(DC.COUNTRIES_ISO_CODE_2='BE','?
d=BE/#!/','#!/')) HTMLPJVURL

from creditor b


join Account c on b.WAccountId =
c.WAccountId

join dochead d on b.WAccountId =
d.WAccountId

left join messages poscon on
(d.WPOSTALCONTACT =
poscon.WMessageId)

left join messages poscomp on
(d.WPOSTALNAME = poscomp.WMessageId)

left join Messages Postid1 on
(d.WPostal1ID = Postid1.WMessageID)

left join Messages Postid2 on
(d.WPostal2ID = Postid2.WMessageID)

left join Messages Postid3 on
(d.WPostal3ID = Postid3.WMessageID)

left join Messages Postcode on
(d.WPostalCodeID =
Postcode.WMessageID)


left join messages delcon on
(d.WDELCONTACT = delcon.WMessageId)

left join messages delcomp on
(d.WDELNAME = delcomp.WMessageId)
```

```
left join Messages DelPostid1 on
(d.WDelAddress1ID =
DelPostid1.WMessageID)

left join Messages DelPostid2 on
(d.WDelAddress2ID =
DelPostid2.WMessageID)

left join Messages DelPostid3 on
(d.WDelAddress3ID =
DelPostid3.WMessageID)

left join Messages DelPostcode on
(d.WDelCodeID =
DelPostcode.WMessageID)


left join countries dc on
d.WDELCOUNTRIES_ID = dc.COUNTRIES_ID,

sysvars

where d.WDocid = <@WDOCID@>
```

HTMcompanyname.txt

Existing || Pipe character sql Firebird

```
Select SCompanyName || '<br/>'

|| sysvars.SADDRESS1 || '<br/>'

|| sysvars.SADDRESS2 || '<br/>'

|| sysvars.SADDRESS3 || '<br/>'

|| sysvars.SPOSTCODE || '<br/>'

|| sysvars.SPHONENUMBER || '<br/>'

 from sysvars
```

CONCAT-Function sql MSSQL

```
SELECT CONCAT(SCompanyName, CHAR(13), CHAR(10),
SADDRESS1, CHAR(13), CHAR(10), SADDRESS2,
SADDRESS3, SPOSTCODE, CHAR(13), CHAR(10),
SPHONE_NUMBER)

FROM SYSVARS;
```

HTMdoclines.txt

Existing || Pipe character sql Firebird

CONCAT-Function sql MSSQL

```
select 0 id,
'<B>Description</B>','<P
ALIGN=RIGHT><B>Price</B></P>','<P
ALIGN=RIGHT><B>Quantity</B></P>','<P
ALIGN=RIGHT><B>Excl.</B></P>','<P
ALIGN=RIGHT><B>Incl.</B></P>' from
RDB$DATABASE

union

Select a.WSortno,m.Sdescription ||
COALESCE(m.SEXTRADESCRIPTION,'')
Description ,

'<P  ALIGN=RIGHT>' ||
IIF(a.WLINETYPEID =
91,'',cast(cast(a.FSELLINGPRICE as
numeric (12,2))as varchar(16))) ||
'</P>' Sellingprice ,

'<P  ALIGN=RIGHT>' ||
IIF(a.WLINETYPEID =
91,'',cast(cast(a.FQTYSHIPPED as
numeric (12,0))as varchar(16))) ||
'</P>' Shipped ,


'<P  ALIGN=RIGHT>' ||
IIF(a.WLINETYPEID =
91,'',cast(cast(a.FEXCLUSIVEAMT as
numeric (12,2))as varchar(16))) ||
'</P>'Exclamount,

'<P  ALIGN=RIGHT>' ||IIF(a.WLINETYPEID
= 91,'',cast(cast(a.FINCLUSIVEAMT as
numeric (12,2))as varchar(16))) ||
'</P>'IncAmount

from docline a left

join stock b on  a.WStockid =
b.WStockid

join Messages m on a.WDESCRIPTIONID =
m.WMessageID

where a.Wdocid = :wdocid

order by 1
```

```
SELECT

    0 AS ID,

    '<B>Description</B>',

    '<P   ALIGN=RIGHT><B>Price</B></P>',

    '<P   ALIGN=RIGHT><B>Quantity</B></P>',

    '<P   ALIGN=RIGHT><B>Excl.</B></P>',

    '<P   ALIGN=RIGHT><B>Incl.</B></P>'

FROM

     RDB$DATABASE

UNION

SELECT

    a.WSortno,

    CONCAT(m.Sdescription,
COALESCE(m.SEXTRADESCRIPTION, '')),

    CONCAT('<P  ALIGN=RIGHT>', IIF(a.WLINETYPEID
= 91, '', CAST(CAST(a.FSELLINGPRICE AS
NUMERIC(12, 2)) AS VARCHAR(16))), '</P>'),

    CONCAT('<P  ALIGN=RIGHT>', IIF(a.WLINETYPEID
= 91, '', CAST(CAST(a.FQTYSHIPPED AS
NUMERIC(12, 0)) AS VARCHAR(16))), '</P>'),

    CONCAT('<P  ALIGN=RIGHT>', IIF(a.WLINETYPEID
= 91, '', CAST(CAST(a.FEXCLUSIVEAMT AS
NUMERIC(12, 2)) AS VARCHAR(16))), '</P>'),

    CONCAT('<P  ALIGN=RIGHT>', IIF(a.WLINETYPEID
= 91, '', CAST(CAST(a.FINCLUSIVEAMT AS
NUMERIC(12, 2)) AS VARCHAR(16))), '</P>')

FROM

     docline a

    LEFT JOIN stock b ON a.WStockid =
b.WStockid

    JOIN Messages m ON a.WDESCRIPTIONID =
m.WMessageID

WHERE

    a.Wdocid = :wdocid
```

```
ORDER BY 1;
```

HTMparcel.txt

Existing || Pipe character sql Firebird

```
SELECT '<A
href="https://securepostplaza.tntpost
.nl/TPGApps/tracktrace/findByBarcodeS
ervlet?BARCODE='||
SSHIPMENT_IDENTCODE  ||  '&ZIPCODE='
||
parcel.SPOSTALCODE  ||
'">https://securepostplaza.tntpost.nl
/TPGApps/tracktrace/findByBarcodeServ
let?BARCODE='||  SSHIPMENT_IDENTCODE
||  '&ZIPCODE=' ||
parcel.SPOSTALCODE  || '</a>' FROM
PARCEL_XDBSEND,  PARCEL
where SDOCNO = :SDOCNO
and PARCEL.WDocid = :WDOCID
```

CONCAT-Function sql MSSQL

```
SELECT CONCAT(
    '<A
href="https://securepostplaza.tntpost.nl/TPGApp
s/tracktrace/findByBarcodeServlet?BARCODE=',
     SSHIPMENT_IDENTCODE,
    '&ZIPCODE=',
    parcel.SPOSTALCODE,
    '">' ,
    'https://securepostplaza.tntpost.nl/TPGApps
/tracktrace/findByBarcodeServlet?BARCODE=',
     SSHIPMENT_IDENTCODE,
    '&ZIPCODE=',
    parcel.SPOSTALCODE,
    '</a>'
) AS  TrackingLink
FROM  PARCEL_XDBSEND
INNER JOIN PARCEL ON  PARCEL_XDBSEND.WDocid =
PARCEL.WDocid -- Assuming the join condition
where SDOCNO = :SDOCNO
```

parcel.txt

Existing || Pipe character sql Firebird

```
Select
'https://securepostplaza.tntpost.nl/T
```

CONCAT-Function sql MSSQL

```
SELECT CONCAT(
  'https://securepostplaza.tntpost.nl/TPGApps/t
```

```
PGApps/tracktrace/findByBarcodeServle
t?BARCODE='||  SSHIPMENT_IDENTCODE  ||
  '&ZIPCODE='  ||  parcel.SPOSTALCODE
FROM  PARCEL_XDBSEND,   PARCEL  where
SDOCNO  =  :SDOCNOand  PARCEL.WDocid  =
:WDOCID
```

```
racktrace/findByBarcodeServlet?BARCODE=',
    SSHIPMENT_IDENTCODE,
  '&ZIPCODE=',
   parcel.SPOSTALCODE
) AS  TrackingLink
FROM  PARCEL_XDBSEND,  PARCEL
WHERE  SDOCNO  =  :SDOCNO
AND  PARCEL.WDocid  =  :WDOCID;
```

SelectLayout.txt

Existing || Pipe character sql Firebird

```
select  '\DOCUMENTS\DOCUMENTS\'  ||
soptionValue  ,  2 a from  opreport
where  stroption  =
'SDocLayoutNameCreditNote'and
:WTYPEID=11

union select  '\DOCUMENTS\DOCUMENTS\'
||soptionValue  ,  2 a from  opreport
where  stroption  =
'SDocLayoutNameGret'and  :WTYPEID=13

union select  '\DOCUMENTS\DOCUMENTS\'
||soptionValue  ,  2 a from  opreport
where  stroption  =
'SDocLayoutNameQuote'and  :WTYPEID=14

union select  '\DOCUMENTS\DOCUMENTS\'
||soptionValue  ,  2 a from  opreport
where  stroption  =
'SDocLayoutNameOrder'and  :WTYPEID=15

union select  '\DOCUMENTS\DOCUMENTS\'
||soptionValue  ,  2 a from  opreport
where  stroption  =
'SDocLayoutNameInv'and  :WTYPEID=10

union select  '\DOCUMENTS\DOCUMENTS\'
||soptionValue  ,  2 a from  opreport
where  stroption  =
```

CONCAT-Function sql MSSQL

```
SELECT
    CONCAT('\DOCUMENTS\DOCUMENTS\',
soptionValue),
    2 AS a
FROM
     opreport
WHERE
     stroption = 'SDocLayoutNameCreditNote'
    AND :WTYPEID  =  11
UNION ALL
SELECT
    CONCAT('\DOCUMENTS\DOCUMENTS\',
soptionValue),
    2 AS a
FROM
     opreport
WHERE
     stroption = 'SDocLayoutNameGret'
```

```
'SDocLayoutNamePurchases'and
:WTYPEID=12

union select '\DOCUMENTS\DOCUMENTS\'
|| SLAYOUTINVOICE , 1 from debtor
where waccountid = :WACCOUNTID and
SLAYOUTINVOICE <> '' and :WTYPEID=10

union select '\DOCUMENTS\DOCUMENTS\'
|| SLAYOUTINVOICE , 1 from creditor
where waccountid = :WACCOUNTID and
SLAYOUTINVOICE <> '' and :WTYPEID=12

union select '\DOCUMENTS\DOCUMENTS\'
|| SLAYOUTCREDITNOTE , 1 from debtor
where waccountid = :WACCOUNTID and
SLAYOUTCREDITNOTE <> '' and
:WTYPEID=11

union select '\DOCUMENTS\DOCUMENTS\'
|| SLAYOUTCREDITNOTE , 1 from
creditor where waccountid =
:WACCOUNTID and SLAYOUTCREDITNOTE <>
'' and :WTYPEID=13

union select '\DOCUMENTS\DOCUMENTS\'
|| SLAYOUTQUOTE , 1 from debtor where
waccountid = :WACCOUNTID and
SLAYOUTQUOTE <> '' and :WTYPEID=14

union select '\DOCUMENTS\DOCUMENTS\'
|| SLAYOUTQUOTE , 1 from creditor
where waccountid = :WACCOUNTID and
SLAYOUTQUOTE <> '' and :WTYPEID=15


order by 2
    AND :WTYPEID = 13

UNION ALL

SELECT

    CONCAT('\DOCUMENTS\DOCUMENTS\',
soptionValue),

    2 AS a

FROM

    opreport

WHERE

    stroption = 'SDocLayoutNameQuote'

    AND :WTYPEID = 14

UNION ALL

SELECT

    CONCAT('\DOCUMENTS\DOCUMENTS\',
soptionValue),

    2 AS a

FROM

    opreport

WHERE

    stroption = 'SDocLayoutNameOrder'

    AND :WTYPEID = 15

UNION ALL

SELECT

    CONCAT('\DOCUMENTS\DOCUMENTS\',
soptionValue),

    2 AS a

FROM

    opreport

WHERE

    stroption = 'SDocLayoutNameInv'

    AND :WTYPEID = 10
```

```
UNION ALL

SELECT

    CONCAT('\DOCUMENTS\DOCUMENTS\',
soptionValue),

    2 AS a

FROM

     opreport

WHERE

     stroption = 'SDocLayoutNamePurchases'

    AND :WTYPEID = 12

UNION ALL

SELECT

    CONCAT('\DOCUMENTS\DOCUMENTS\',
SLAYOUTINVOICE),

    1 AS a

FROM

     debtor

WHERE

     waccountid = :WACCOUNTID

    AND SLAYOUTINVOICE <> ''

    AND :WTYPEID = 10

UNION ALL

SELECT

    CONCAT('\DOCUMENTS\DOCUMENTS\',
SLAYOUTINVOICE),

    1 AS a

FROM

     creditor

WHERE

     waccountid = :WACCOUNTID

    AND SLAYOUTINVOICE <> ''
```

```
    AND :WTYPEID = 12
UNION ALL
SELECT
    CONCAT('\DOCUMENTS\DOCUMENTS\',
SLAYOUTCREDITNOTE),
    1 AS a
FROM
    debtor
WHERE
    waccountid = :WACCOUNTID
    AND SLAYOUTCREDITNOTE <> ''
    AND :WTYPEID = 11
UNION ALL
SELECT
    CONCAT('\DOCUMENTS\DOCUMENTS\',
SLAYOUTCREDITNOTE),
    1 AS a
FROM
    creditor
WHERE
    waccountid = :WACCOUNTID
    AND SLAYOUTCREDITNOTE <> ''
    AND :WTYPEID = 13
UNION ALL
SELECT
    CONCAT('\DOCUMENTS\DOCUMENTS\',
SLAYOUTQUOTE),
    1 AS a
FROM
    debtor
WHERE
```

```
        waccountid = :WACCOUNTID
        AND SLAYOUTQUOTE <> ''
        AND :WTYPEID = 14
    UNION ALL
    SELECT
        CONCAT('\DOCUMENTS\DOCUMENTS\',
    SLAYOUTQUOTE),
        1 AS a
    FROM
        creditor
    WHERE
        waccountid = :WACCOUNTID
        AND SLAYOUTQUOTE <> ''
        AND :WTYPEID = 15
    ORDER BY 2;
```

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

2024-osFinancias5.1 - Build 5.1.0.189 Release notes

ADDED - GDI scaling (Graphics Device Interface scaling) support

osFinancials5.1.0.109 supports GDI scaling, or Graphics Device Interface scaling. It refers to the process of adjusting the size of graphical elements on a computer screen based on the display resolution and pixel density. The Graphics Device Interface (GDI) is a component of the Windows operating system responsible for rendering graphical elements such as text, images, and graphical user interface (GUI) elements.

As display technologies advance, screen resolutions increase, and devices with different pixel densities

become more prevalent, it becomes essential to scale the graphical elements appropriately. GDI scaling helps ensure that these elements appear at a reasonable size and are visually consistent across various displays.

Windows operating systems include a feature called Display Scaling, which allows users to adjust the size of text, apps, and other items on the screen. GDI scaling plays a role in this process by ensuring that the graphical elements are resized correctly without losing clarity or becoming pixelated.

In essence, GDI scaling helps provide a more consistent and visually pleasing user experience on displays with different resolutions and pixel densities, ensuring that the graphical elements are appropriately sized and easy to read or interact with.

Windows Registry - REGEDIT osFinancials5

Windows Registry - REGEDIT Added osFinancials5 in osFinancials5.1.0.127

All previous installations or updates of osFinancials5.1 (before osFinancials5.1.0.127) and osFinancials4.0.1093 will update the "*Computer\HKEY_CURRENT_USER\Software\osfinancials*" in the Windows registry.

"*Computer\HKEY_CURRENT_USER\Software\osfinancials5*" will since installations or updates of osFinancials5.1.0.127 be created and or updated.

See - FIX for Debtor accounts / Creditor accounts lookup when creating documents

It also fixed the Debtor / Creditor accounts lookup when creating documents in osFinancials5-453 osFinancials4.0.0.1093

Deleting the HKEY_CURRENT_USER\SOFTWARE\osfinancials in the Windows Registry

FIXED - osFinancials5.1.0.127

User ribbon tab - Auto-learn - selected

```
Incorrect syntax near ')'.
Incorrect syntax near the keyword 'select'.
```

Similar to the Firebird error

```
Dynamic SQL Error
SQL error code = -104
Token unknown - line 1, column 157
select
```

Budgets (Reports ribbon) - (MSSQL Errors)

FIXED Budgets on Reports ribbon in Firebird Database types - osFinancials5.1.0.127 update

ERROR MSSQL Databases - Budgets on Reports ribbon in MSSQL Database types - osFinancials5.1.0.127 update still produces error:

> Incorrect syntax near 'a'.

In MSSQL databases cannot enter and save budgets (Apply to selection button) in Budgets (Reports ribbon).

But can enter budget figures in Setup → Accounts (Setup ribbon).

FIXED - Access violations - POS Input - POS on Default ribbon (Ctrl + F6) Standard POS

Fixed in osFinancials5.1.0.127 - If no Sales account is selected, a message will be displayed:

> Default customer account not setup! Please setup!

When click on OK it will launch the POS setup (Setup → Point-of-Sale).

Replicated In osF5.1.0.99 and osF5.1.0.100

> Access violation at address 5F3580AA in module 'rtl280.bpl'. Write of address 00000240

Replicated In osF5.1.0.93

> Access violation at address 08D6542C in module 'osfresource.bpl'. Read of address 000001F0

POS (Standard screen flickers New Invoice / Display area

Replicated in osFinancials5.1.0.127 since osFinancials5.1.0.109

MSSQL Error - Plugin - Location-Serials-Batches

Came right probable when updated the object 'dbo.BatCon'

MSSQL Error Post Batch Purchase Document - Error

The statement has been terminated.

> Violation of PRIMARY KEY constraint 'PK__BatCon__DB7D61DFCE4DB78F'. Cannot insert duplicate key in object 'dbo.BatCon'. The duplicate key value is (61).

Posted after second attempt

MSSQL - Create Books

Groups Print button error

> GROUPDATA:Parameter 'GROUPTYPEID' not found

Import accounts

Tax - Only the Tax control account and the first tax account is imported without the tax tab. You need to delete the Tax code and recreate it.

Import Debtors / Creditors (Setup ribbon form Text file

Produces error (This is if the Date of the Signature date field on Accounting information tab

Error on import with message('1899/12/30' is not a valid date and time) Do you want to continue?

Click Yes the debtors creditors will be imported.

Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

2024-osFinancias5.1 - Build 5.1.0.189 Known issues

Base type 0 - Address1 / Postal code / Address 2 / Address 3

In this documentation, the Postal address and Delivery address will be displayed Address1 / Postal code / Address 2 / Address 3 in the following forms:

Debtors, Creditors, Documents, Calendar (also Reports → Calendar)

The Netherlands document layout files prints in this format.

In base type 1 probably osFinancials International (like TurboCASH5.2) the Postal address and Delivery address will be displayed Address1 / Address 2 / Address 3 / Postal code. The layout files , Debtor statements , Creditor remittance advises and Report headers is displayed in this sequence.

osFinancials5.1.0.127 Interface - Delphi 12

Setup groups - Colours - groups does not retain colours

If the Background colors is set, and no Font colors is set, the groups does not retain colours set in Setup → Groups in Account group 1 and Account group 2 as well as other groups.

Solution: To retain and save the selected colors, you also need to set both the Back color and the Font color.

Close active forms or reopen Set of Books or use Report button (Ledger analyser 1 / 2) Account group1 / Account group2 to see the changed colors.

In the case of Documents, Debtors, Creditors and Stock items, the changed colors on the grids will be available when you click on the Filter button.

osFinancials5 - Delphi12 / Delphi11

Setup Goups



osFinancials5 - Reportman (Setup background colours) /- similar to osFinancials4



Radio buttons Selection not consistent

The radio buttons on some screens appears to be Delphi11 and on other screens Delphi12

Old look and New look radio buttons on 1 screen



Examples



Old look Radio button



Old look Radio button

- Stock information
- Creation wizard
- Update ledger and many screens

New look Radio button



New look Radio button

- Customize languages
- Input-> Confirm

Expand / Collapse options not consistent



+ / - Expand / Collapse also on Groups and Document entry forms

Customize language

Customize language - Rest tab

Customize language - Rest tab Change descriptions

Description of Zero account and Group empty account 2 change buttons only saves 1 description.

Work around change both to Empty



Customise Language - number of Characters

In Customise Languages - Can only enter 10 characters for new language (Some languages up to 15 characters in the " *...\bin\languages* " folder). To use more than 10 characters, you may rename it manually in File Explorer to 15 characters.

Obsolete / out dated language files

Obsolete / out dated language files - May be deleted from languages folder (" *...\bin\languages* ")

Language file	*Date of last changes*	*Replaced and updated with*	*Books download*
African.dfm	*2020/03/06*	*Afrikaans.dfm*	
en-Trinandad.dfm	*2020/03/06*	*en-Trinidad.dfm*	*EN-TRINIDADTOBAGO*
Nederlands.dfm.bak	*2020/05/08*		
testlang.dfm	*2020/03/06*		
Zeng.dfm	*2020/03/06*		

These language files is not linked to any Firebird Sets of Books and linked languages available as a free download. from the Download option on the "*Creation wizard*".

Bank accounts

Bank Accounts - Payment and Receipt batches F10:Setup

Default reconciliation method (Setup → System parameters) Deactivated Bank import plugin

Default = Allow both - Cannot change to Debit or Credit in the Advanced tab.

Bank Accounts - Select bank account changes label

Bank account name changes to Write102, etc. the record (accountid) number selecting a bank account.



Calendar - Appointments

Creating Debtor Appointment 2 and selecting stock item produced the following error:

> "QEvents: Cannot perform this operation on a closed dataset"

Exit osFinancials and Reopen the Set of Books, could recreate the appointment.

Think it may be the Stock item. If a stock item is selected, the last Empty space in the Event screen, if typed over, it will revert back to Empty.

Budgets (Reports ribbon) - MSSQL Errors

FIXED Budgets on Reports ribbon in Firebird Database types - osFinancials5.1.0.127 update

ERROR MSSQL Databases - Budgets on Reports ribbon in MSSQL Database types - osFinancials5.1.0.127 update still produces error:

> Incorrect syntax near 'a'.

In MSSQL databases cannot enter and save budgets (Apply to selection button) in Budgets (Reports ribbon).

But can enter budget figures in Setup → Accounts (Setup ribbon).

Licence Typo - Not In Language File

osFinancials 5.1.0.102

> {99XXX-PX99-9999-X9X9-99999999 X99}Multi-user max 7 to retieve Time license 2023/12/29 :Time license

expires in 21 days! Please visit https://www.osfinancials.org/en/webshop

Message license typo retieve in stead of retrieve - Typo not in language files

Themes - Updated Creditors control icon - imagestrips

Fixes and Supported themes:

- Theme screenshots - Screenshots of the installed themes and new themes (about 34 themes). A sideshow of the themes rotating is available in osfinancials-themes-slides.zip file
- Known issues - Themes - Imagestrips excludes reports path. If images is removed from the theme folder, the imagestrip defaults to the classic theme, or other theme.
- Creditor control icon not loading correctly - Classic icon in some themes - Fixed - replaced the Acccreditors.svg icons (icon properties did not load the Acccreditors.ico) and re-created imagestrips in osFinancials5.1.0.109 - but with the osFinancials5.1.0.127 update does not include these fixes. The updated Creditors control icon - imagestrips is not included in the osFinancials5.1.0.127 update.

Screens - Display issues

osFinancials5.1.0.127 update issues with the following screens:

POS - Input → POS Invoice

Screen flickers in the New Invoice / Total/Subtotal area of the screen.



FIXED - Access violations - POS Input - POS on default ribbon (Ctrl + F6) Standard POS

Fixed in osFinancials5.1.0.127 - If no Sales account is selected, a message will be displayed:

> Default customer account not setup! Please setup!

When click on OK it will launch the POS setup (Setup → Point-of-Sale).

Replicated In osF5.1.0.99 and osF5.1.0.100

> Access violation at address 5F3580AA in module 'rtl280.bpl'. Write of address 00000240

Replicated In osF5.1.0.93

> Access violation at address 08D6542C in module 'osfresource.bpl'. Read of address 000001F0

POS (Standard screen flickers New Invoice / Display area

Replicated in osFinancials5.1.0.127 since osFinancials5.1.0.109

Setup → Workflow



No Delete confirmation messages

Calendar - Delete process repeating invoices

No delete confirmation message



Click on Delete button and the item is removed from the "*Process list*".

NOTE

For events there is a confirmation message to delete the event

> Delete "Repeating invoices" from your schedule?
> This operation cannot be undone!

Debtors / Creditors tab - Delete contact - No confirmation message

Click Delete button and gone is the contact



NOTE

On Contacts screen (Default ribbon) the Delete confirmation message is displayed:

> Do you want to delete this contactperson?

On Calendar - Contacts screen the Delete confirmation message is displayed:

> Delete Ben Best from your list of contacts?
> This operation cannot be undone!

Change Reporting groups 1 / Reporting group 2

Change Reporting groups 1 / Reporting group 2 for Debtors / Creditors and Documents no confirmation message is displayed from the context menu options on the grid.

Using the context menu on Stock items Change Reporting groups 1 / Reporting group 2 a confirmation message is displayed e.g.:

> Set reporting group 2

MSSQL Error - Plugin - Location-Serials-Batches

Came right probable when updated the object 'dbo.BatCon'

MSSQL Error Post Batch Purchase Document - Error

The statement has been terminated.

> Violation of PRIMARY KEY constraint 'PK__BatCon__DB7D61DFCE4DB78F'. Cannot insert duplicate key in object 'dbo.BatCon'. The duplicate key value is (61).

Posted after second attempt

MSSQL Error - Import Stock

Setup ribbon Import - Stock - Tab delimited (*.txt) file

> Error 3The statement has been terminated.
> The INSERT statement conflicted with the FOREIGN KEY constraint "FK_DOCLINE_STOCK". The conflict occurred in database "MSSQL-HANDYMAN", table "dbo.Stock", column 'WStockID'.

Default " nounicode=true " - Setting in osf.ini file Errors in Firebird Database types

Replicated in osF5.1.0.127 since osFinancials5.1.0.16 displayed incorrectly, since unicode was introduced.

Currencies

osf.ini - " *nounicode=true* " - Default setting is Not Commented or Set to False

Database types

- Firebird Replicated issues
- MSSQL - Works

The Currency symbols is not displayed correctly (displayed as a " I " character) on Setup → Currencies screen. In Reports → Currencies and printed Document layout files, it displays the currency symbol as " ".

NOTE : To be able to use Currencies the Default setting " *nounicode=true* " needs to be changed to " *nounicode=false* " or commented (in Firebird databases).

This will cut-off the Reference number / Descriptions when printing some reports e.g. of Debtor Statements,, Creditor remittance advices, etc., if the Default setting osf.ini - " *nounicode=true* " is changed.

Setup Countries - Displays incorrect character " land Islands "

See - Setup Countries - Displays incorrect character " land Islands "

If the default setting " *nounicode=true* " is not uncommented in the osf.ini file, this replicate the error not displaying correctly.

Database types

- Firebird Replicated issues
- MSSQL - Works

If the default unicode setting in the osf.ini file is changed to " ;*nounicode=true* " is uncommented or set to false " *nounicode=false* " in the osf.ini file, these settings does not change the display of " land Islands ".

land Islands Displays incorrect character irrespective of unicode settings

Also replicated in the "Country field of Debtor / Creditor accounts s well as Delivery address tab.

Reports (Firebird)

Known issues - Firebird Reports - Nounicode settings - osf.ini-file

osf.ini - " *nounicode=true* " Default setting is Not Commented or Set to False the Reference number /

Descriptions will display 100% when printing some reports e.g. of Debtor Statements,, Creditor remittance advices, etc.

Database types

- Firebird Replicated issues
- MSSQL - Works

On the other hand to use Currencies in osFinancials5.1.0.100, the Currency symbols is not displayed correctly (displayed as a " I " character) on Setup → Currencies screen, Reports → Currencies and Document layout files.

To be able to use Currencies the Default setting " *nounicode=true* " needs to be changed to " *nounicode=false* " or commented.

This will cut-off the Reference number / Descriptions when printing some reports e.g. of Debtor Statements,, Creditor remittance advices, etc., if the Default setting osf.ini - " nounicode=true " is changed.

Sets of Books in the Setup → Reporting dates - Cannot Update - Unicode - Error - Refresh failed. Found 0 records

See - Sets of Books in the Setup → Reporting dates - Cannot Update - Unicode - Error - Refresh failed. Found 0 records

Database types

- Firebird Replicated issues
- MSSQL - Works

Default unicode setting in osf.ini file =" *nounicode=true* "

> Unicode - Error - Refresh failed. Found 0 records

Cannot set reporting dates in Setup → Reporting dates - produces errors when default setting in the osf.ini files is set to

> nounicode=true

Before in earlier versions in 2022 this error was replicated since the nounicode setting was implemented in osFinancials5.1.0.49

Help topics

English

Added:

- Blockchain
- Activa
- Price agreements

Updated:

Stock sidebar reports

Metatags for SEO

Afrikaans - More modern Afrikaans

Reports-GENERAL-documents Fixes

Fixed - batch.rep

Location : plug_ins\reports\GENERAL\documents\batch.rep

Multi page print - Print report name and batch name on each new page.

Fixed - postedbatch.rep

Location : plug_ins\reports\GENERAL\documents\postedbatch.rep

Fixed - Overlapping labels accounts

Fixed - No data available to print! setting

To do

MSSQL Database reports

FIXED - MSSQL Database support - Reports

Fixed - To print on MSSQL and Firebird databases

Debtors

Debtor statements

Location : plug_ins\reports\systemreports\TRN_160\TRN_1090 \TRN_906552 - Debtor statement - Outstanding

Debtors - Age analysis (Reports)

Location : plug_ins\reports\userreports\TRN_160\TRN_906143 - Balances detail history (open item)

Creditors

Creditor remittance advices

Location : plug_ins\reports\systemreports\TRN_161\TRN_1090 \TRN_906551 - Creditor remittance advises - Outstanding

Creditors - Age analysis (Reports)

Location : plug_ins\reports\userreports\TRN_161\TRN_906143 - Balances detail history (open item)

Outstanding - Fixed - To print on MSSQL and Firebird databases - Period 2 includes Period 1

Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090 - Debtor statement

Location : plug_ins\reports\systemreports\TRN_161\TRN_1090\TRN_1089 - Creditor remittance advises

Debtor age analysis

Location : plug_ins\userreports\userreports\TRN_160\TRN_906142 - Balances detail

Location : plug_ins\reports\userreports\TRN_160\TRN_906147 - Balances

Creditor age analysis

Location : plug_ins\userreports\userreports\TRN_161\TRN_906142 - Balances detail

Location : plug_ins\reports\userreports\TRN_161\TRN_906147 - Balances

---

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Translations outstanding

Obsolete / out dated language files

Obsolete / outdated language files - May be deleted from languages folder (" *...\bin\languages* ")

Language file	*Date of last changes*	*Replaced and updated with*	*Books download*
African.dfm	*2020/03/06*	*Afrikaans.dfm*	
en-Trinandad.dfm	*2020/03/06*	*en-Trinidad.dfm*	*EN-TRINIDADTOBAGO*
Nederlands.dfm.bak	*2020/05/08*		
testlang.dfm	*2020/03/06*		
Zeng.dfm	*2020/03/06*		

These language files is not linked to any Firebird Sets of Books and linked languages available as a free download. from the Download option on the "*Creation wizard*".

Translations-Plugins

2024-osf-development\2024-03

2024-osf-development\2024-03\Translations-Plugins\

osf-5-1-127-Translations-Plugins-Activa.docx

osf-5-1-127-Translations-Plugins-DrillDown.docx

osf-5-1-127-Translations-Plugins-EMailPro.docx

osf-5-1-127-Translations-Plugins-HandyTools.docx

osf-5-1-127-Translations-Plugins-Location-Serial-Batch.docx

osf-5-1-127-Translations-Plugins-Multimedia.docx"

osf-5-1-127-Translations-Plugins-Multi-User-Calendar.docx

osf-5-1-127-Translations-Plugins-Price-Agreement.docx

osf-5-1-127-Translations-Plugins-Remittance.docx

osf-5-1-127-Translations-Plugins-Subscriptions.docx

Translations-Plugins

2024-osf-development\2024-03

Translations-Plugins\

Activa.docx

DrillDown.docx

EMailPro.docx

HandyTools.docx

Location-Serial-Batch.docx

Multimedia.docx"

Multi-User-Calendar.docx

Price-Agreement.docx

Remittance.docx

Subscriptions.docx

Bugs

Batches

Global processes -> Cancel posted batches/documents -

Cancel / Reverse posted batches/documents - Batches line number stars with line 2 instead of line 1.

Spreadsheet sales (Default ribbon)

Error message

> Erro Batch not found. Please setup a batch in POS setup.

Select the Sales journal "*Ledger*" section of the Setup → Point-of-Sale. Once this is done, you can access the Spreadsheet sales blank spreadsheet

Copy / Confirm documents - Comments / Remarks

Edit → Repeating invoices - Remarks not copied

Copies Comments but No remarks is copied on Edit → Repeating invoices

In the Calendar - Repeating invoices appointment process - Copies remarks as well as comments.

Input → Confirm - Comments and Remarks not copied

Copies no Comments and Remarks on Input → Confirm (Shift+F3) -

In Documents - Quotes context menu - Confirm quotes and orders - Copies remarks as well as comments.

Documents setup - Print standard logo

Documents setup - Print standard logo Setting does not work

- To print the logo need to Load the logo in Setup → Company info - Options tab
- If you do not want the logo to print, simply remove (clear) the logo in Setup → Company info - Options tab

Debtors / Creditors / Contacts - Freefield7 missing



Export Lookups

Export - Stock (Setup ribbon) - Lookup



On the Stock items option, sometimes the Lookup is not displaying well



Relaunching or reopen Set of Books Lookup displays correct.



Export - Posted batches (Setup ribbon) - Lookup



On the Posted batches option, sometimes the Lookup is not displaying well



Relaunching or reopen Set of Books Lookup displays correct.

Code list includes stock items search filter options



Footers does not update document quantities and prices for stock

Translations Outstanding

Outstanding labels screenshots and notes by function (Language ids of existing labels included where available)

Translations-Access-Control

Translations-Bank

Translations-Bank-Import

Translations-Batches

Translations-Budgets

Translations-Calendar

Translations-Debtors-Creditors

Translations-Documents

Translations-Report-Designer

Translations-Import-Export

Translations-Reports

Translations-POS-Standard

Translations-Setup

Translations-Spreadsheets

Translations-Stock

Delete record confirmation message

Tax classes (Setup - Stock information)

Setup - Countries

Setup - Currencies

Setup - Workflow

Setup - Accounts - Budget tab

Setup - Accounts - Bank links tab

Reportman - Delete button to delete report



Translated in the Delete option on Budget - Transactions tab with the screen theme

LabelID 20002 -

Skrap rekord?

Delete record

Grids columns (Global All grids)

* Click here to show/hide/move bands (Mouse over) first asterisk

* Click here to show/hide/move columns (Mouse over) second asterisk

(All)

(Sorted)

Ribbons Minimize / Collapse / Hide

- Minimize the Ribbon (Right click on ribbon tab)
- Collapse the Ribbon



- Pin the Ribbon



Start ribbon



Registration



Update



Open Set of Books



Context menu

- Purge not in this folder
- Reinit version

Error message

file is not a valid database

Create Set of Books





Browse For Folder 2110

Customise your own Set of Books (Advanced)

Message for Reporting dates screen

> Periods not there

MSSQL server database type





Backup / Restore



Search for unposted items



Buttons

- OK 21093
- Details 2428
- Columns 20007 / 20064
- Debit 211
- Credit 212

Data integrity check



Recalc totals

Print (21052)

Browse for folder (2110)

Update ledger

Documents tab



Batches tab



Context menu

- Update 358
- Edit Batch
- Delete Batch

Edit - Documents - Delete



Context menu

- Set as From Option
- Set as To Option
- Update 358

Search (Investigator)



Found

Context menu

- Show detail 392 / 2191

Type column - Account, Stock, Document, Batch

Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Translations - Record buttons

The ten record buttons is found in many screens in osFinanvcials core and also in various plugins. The mouse over text of these is only in English:

1. First record
2. Prior record
3. Next record
4. Last record

5. Insert record

6. Delete record

"Delete record?" 20002
This translation 20002 is translate in a few options, but not on all options

7. Edit record

8. Post edit

9. Cancel edit

10. Refresh data

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Translations - Access control

Setup - Access control

osFinancials program Statusbar

Universal administrator (If NO users were setup in Access control)



User: Name (If users were setup in Access control)



Standard security



Tabs

- Groups 1846
- Usertabs 3563

Users

User 1072

System language

Language 3112

User Password 1972 / 1980 / Password confirmation 3204

System menu

No costinfo

Error message incorrect password

Password do not match

Batches access



Selection - Also on context menu

- Select All
- Invert selection
- deselect all

Other options



Edit calendar

Link to salesperson - All users (on list) the rest on the list will be populated for the Multiuser Agenda plugin Resource name added in the Calendar)

Stock access type

- Default (all rights)
- Wharehouse (Barcode / Weight dish) Typo => arehouse



Add all button 1890

Documents



General tab 1367 / 3205

- Cost centre in doc
- Readonly tax
- Doc no 1120
- Direct edit fields
- scan print mode
- Start doc on (Invoice, Quote, Purchase, Order)

Limit sql tab



Limit sql tab

- Disable on doc form
    - Limit actions
- Limit deb/cred
- Limit layouts

Usertabs

User ribbon



Groups Plural = LabelID 345 is used Set to singular Groepe => Groep

ID1072 - Gebruiker (User)

Usertabs 3563



Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Translations - Bank recon (Default)

Bank account "*Bankrekening*" label changes to Write6 (Sometimes to Read6) when a Bank account is selected (where 6 is the record name ACCOUNTID in the ACCOUNT Table of the selected bank account.



Process

- Apply reconciled
- Transfer Unreconciled to Batches



FIXED - Bank reconciliation report as at

Location: " ... \plug_ins\reports\GENERAL\documents\recon



Unposted payments 906447

Unposted receipts 906448

Language : Kasboekverslag LabelID3014 changed in Afrikaans => Bankrekonsiliasie verslag soos op

Expressions changed :

TRpExpression55 CUSTOM('GETTEXTLANG',906447,'Unposted payments',0,0,0)

TRpExpression56 CUSTOM('GETTEXTLANG',906448,'Unposted receipts',0,0,0)



If the setting Print only if data available - Set to True for the following unposted subreports.

(SubReport-1UNPOSTEDPAYMENTS)

(SubReport-2UNPOSTEDRECEIPTS)

the Difference column will display a value as a result of the Reconciled balance

For this reason this setting is not applied.

MSSQL Error - Bank reconciliation report

Location : " ...\ plug_ins \ reports \GENERAL \documents \ recon

Prints in Firebird databases

In MSSQL databases produces error:

```
OPREPORT:Incorrect syntax near '|'.
```

OPREPORT Dataset SQL

```
select * from OPREPORT where STROPTION like  :BANKACCOUNT || 'BankBal%'
```

Tried to change SQL to accommodate the CONVAT Function (concatenate):

```
SELECT * FROM OPREPORT WHERE STROPTION LIKE CONCAT(:BANKACCOUNT, 'BankBal%')
```

Then it produces Error in MSSQL databases:

```
Type conversion error 'Val':Expression TRpExpression11
```

Could not did not fix the error in MSSQL at this stage

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Translations - Bank import plugin

Bank account selection (from Cash / Bank on the Default ribbon)

Bank account "*Bankrekening*" label changes to Write6 (Sometimes to Read6) when a Bank account is selected (where 6 is the record name ACCOUNTID in the ACCOUNT Table of the selected bank account.



Language label 2186 Bankrekonsiliasie verslagopsies / Bank account recon options

Screen caption could read Bankstaat opsies - Bank statement options

Should then be fit to accommodate the [Bank import plugin]

And Bank reconciliation default method (since reconciling the bank transactions with bank statements



Batch entry screen



Match log tab

Context menu

- Payment diverence 3473
- Match ideal bank @*@

Balance = balance - Filter

Import bank statement



Country 2207 / 2388 / 2421

Auto detect

Cur recalc - Std / Default

Valutas tab - 3470 Currencies

Context menu

- Zet op onverwerkt
- Zet Zet op verwerkt

Toets tab (title bar caption)



Toets / Check 897 (title bar caption) Translating this changes the Test button on Tools -> Data integrity

check. In Afrikaans changed to Kontroleer.

- Account code
- Split (901500 Probably in different context as this is used for HORECAPOS Plugin)
- Merge 3629
- Remove double suspects

Split amount



Account bank references



Std Bankrekeningnr. + n.v.t.

- Language label = 906016 - BIC*
- Language label = 906016 - IBAN*

Delete record conformation message



LabelID 20002 - Delete record ?

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Translations - Batches

Batch setup



Batches - icon spreadsheet



Post to retained earnings account confirmation message

Do you wish to post on the retained earnings account?

Batch filter



Batch open item - Copy to search



Copy to search

Edit - Repeating transactions



Day 2179 - Should be - Date 238

Balance = balance

Posted batch report

Fix unique id button

Filter options

- All
- Sorted

* Click here to show/hide/move columns (Mouse over)



F9:Batch Process options

Cancel Error message

Creditor balances at date - click Cancel error message

Operation aborted

Automatic payments



Betalingstransaksie	Beskrywing	Bedrag	Uitstaande	Adres	Adres 2
	Openingsbalanse - Krediteure	1,000.00-	1,000.00-		
	BEST Verskaffers	100.00-	100.00-	Posbus 45532	Halfweghuis
	BEST Verskaffers	200.00-	200.00-	Posbus 45532	Halfweghuis
	BEST Verskaffers	100.00-	100.00-	Posbus 45532	Halfweghuis
	BEST Verskaffers	2,300.00-	2,300.00-	Posbus 45532	Halfweghuis
	ABC-Kantooruitrusters	1,725.00-	1,725.00-	Posbus 8888	Lakeview
	ABC-Kantooruitrusters	1,725.00-	1,725.00-	Posbus 8888	Lakeview
	ABC-Diensstasie	460.00-	460.00-	Posbus 9999	Lakeside
	ABC-Diensstasie	1,150.00-	1,150.00-	Posbus 9999	Lakeside
	ABC-Diensstasie	690.00-	690.00-	Posbus 9999	Lakeside
	A-1 Verskaffers	200.00-	200.00-	Posbus 31318	Marshalltown
	A-1 Verskaffers	300.00-	300.00-	Posbus 31318	Marshalltown
	A-1 Verskaffers	100.00-	100.00-	Posbus 31318	Marshalltown
	A-1 Verskaffers	1,725.00-	1,725.00-	Posbus 31318	Marshalltown
22			-15400.00		



Language label = 906016 - BIC*

Language label = 906015 - IBAN*

Automatic receipts



Language label = 906016 - BIC*

Language label = 906015 - IBAN*

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Translations - Budgets

Budgets (Reports ribbon)

Budget 1027

Messages

Add amount - Confirmation message

Add amount to selection?

Delete all - Confirmation message

Delete data for this period?

Import Budget / Actual previous period - Confirmation message

Delete data for this period?

Budget grid

Budget tab



* Click here to show/hide/move columns (Mouse over)

Pivot tab

Dataset



Transactions tab



Pivot tab

Entire Pivot tab + Columns + Context menus



The Prefilter is translated except the column options

Setup - Accounts - Budget tab

Add new budget total



Delete budget record



Delete record? 20002

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Translations - Calendar

Calendar



Change in Agenda

Quote



Change to Agenda This is applicable to the Multi-User Agenda Plugin - If activated and purchased should then be displayed as more resource names can be added.

Appointment



Location 3681 but for consistency on the Appointments screen it includes a colon : then 716 / 1829 includes a colon Location :

Processno:

Salesperson: - label cuts off in Afrikaans - LabelID1718 Verkoopspersoon => Verkoper:

Repeating invoice options



Tasks



Complete

Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Translations - Debtors / Creditors

Debtors grid

* Click here to show/hide/move bands (Mouse over) first asterisk

* Click here to show/hide/move columns (Mouse over) second asterisk



Reports 123

Copy account

Also on Debtor accounts when New document is created

Creditors grid

* Click here to show/hide/move bands (Mouse over) first asterisk

* Click here to show/hide/move columns (Mouse over) second asterisk



Reports 123

Copy account

Also on Creditor accounts when New document is created

Debtor / Creditor tabs

Accounting information



Language label = 906016 - BIC*

Language label = 906015 - IBAN*

Contacts form

Freefield7 field missing on Telephone tab


Ben Best - Kontak
Hoof
Telefoon
Notas
Voornaam
Ben
Initials
B
Naam
Best
Titel
Birthday
Specialday
Gender
Adres
Posbus 45532
Adres 2
Halfweghuis
Adres 3
Poskode
1685
Land
Leeg
Besigheid
BEST Verskaffers
Posisie
Kategorie
Besigheid
E-pos
best@sypos.com
Doctype
Goed
Kanselleer



Birthday

Specialday

Gender 3198

Male 3199

Female 3200

Doctype (Document type) 1087 / 1869



Copies 732

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Translations - Documents

Reverse posted documents log

Reversing AK000001
Reversing AK000002
Reversing AK000003
Reversing AK000004
Done.

Document labels cuts-off

F8: Discount icon



On the F8:Discount icon, the screen cuts the following label-off in both languages:

2151 - Sleutel oorhoofse korting in / Enter overall discount

Enter total



On the context menu, select "*Enter total*" / "*Sleutel totaal in*". The screen cuts the following label-off in both languages:

3322 Sleutel nuwe inklusiewe totaal in / Enter new inclusive total

Document grid columns



Documents grid - context menus

Documents grid - context menu - Invoices

* Click here to show/hide/move bands (Mouse over) first asterisk

* Click here to show/hide/move columns (Mouse over) second asterisk



Layout file 3 - 3111

Layout file 4

Spreadsheet import 3720

Documents grid - context menu - Quotes



Documents grid - context menu - Credit notes



Documents grid - context menu - Purchases



Documents grid - context menu - Orders



Documents grid - context menu - Supplier returns



Document grid - Graphs



Document entry

Form - Header

Currency

Rate 3455



Document lines - Context menu

Sort on stockcode

Sort on stockcode (Duplicated)

Sort on supplier code

Document - Footer - Context menu

Cancel Next

Cancel Prev

Documents - Contra account: Standard

Lookup - Select account - Titlebar caption


* (011) 310-1677 1SMITH Faktuur FA000013 Mnr. Roger Smith, -3.00 voorraaditems..
Jou verwysing
K-102
Dokumentgroep 1
Dokumentgroep 1B
Datum
2024/03/19
Kontrarek.:Standaard
Status
Maak oop
Verkoopspersoon
Tracy
Dokumentgroep 2
Posadres
Besigheid
Mnr. Roger Smith
Kontak
Roger Smith
Adres
Boxerweg 539
Poskode
1685
Adres 2
Glen Austin Uitbreiding 3
Adres 3
Midrand
Land
Leeg
+Maak Kitsbyvoeg oop
^D: Skrap
F12: ^N: Invoeg
Itemnr.
Beskrywing
3-KOMP
Kompressor
Met bybehore
Serienommer : KOMP1234567890
Debiteure
1SM-ITH
Faktuurnommer
Huidige balans
Beskikbaar
Kredietlimiet
Std korting%
Kitsbyvoeg (kode/strepieskode/serienommer)
Select account
Kode
Geen
Soek
Skoonmaak
Sleep 'n kolom na hier (met jou muis) om kolomme te groepeer.
Kode
Beskrywing
T
Leeg
G010000
Verkope
G100000
Koste van verkope
G200000
Bankkoste
G205000
Depresiasie
G210000
Voertuiguitgawes
G210010
Motorvoertuie - Brandstof & Olie
G210020
Motorvoertuie - Onderhoud
G210030
Motorvoertuie - Herstelwerk
G215000
Onderhoud - gereedskap
G220000
Huur
G225000
Salarisse en lone
G230000
Skryfbehoeftes
G235000
Diverse uitgawes
G505000
Kapitaal
G510000
Behoue inkomste
G520000
Afbetalingsooreenkomste
Soek per
Kode
Beskrywing
Outo-kies

Input → Confirm Shift+F3



Reference (LanguageID 607 / 1285 / 1719 / 1974)

Show posted

Documents context menu - XML import settings

Documents grid - context menu



Confirmation message empty



Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Translations - Import / Export

Import



Step 1 - static on all 3 screens enter click next buttons

Excel import button - ID3270 = Spreadsheet import

File format (File type) selection on list

Export

Increment Export (Stock, Accounts, Debtors, Creditors and Posted batches)

File format (File type) selection on list

Export - Documents



File format (File type) selection on list

Include Documents since

Export - Stock



Increment Export (Also on Accounts, Debtors, Creditors)

Export - Stock - Lookup -



Footers does not update document quantities for stock

Export - Stock - Lookup - Sometimes the Stock lookup is empty but Footers displays update stock totals quantities and prices for stock (in the same database)



Export - Posted batches

Increment Export

Export - Posted batches - Lookup -

Inactive

multilang

Filter Code , etc. - includes stock options - Supplier code





Footers does not update document quantities and prices for stock

---

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Translations - Open item

Open item link - Totals tab



Limitrows 3562

Context menu all items



Open item link - Transactions tab



Limitrows 3562

Group

Open item link - Unposted batches tab

OK

Open item link - Due tab

OK

Open item link - Selected account



Filter 20097



Open item link - Selected account - Statement



Unlink 934

Filter 20097

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Translations - Reports

Reports ribbon

Ledger analyser



Ledger analyser - D / C - Debit Credit indicator



T-Account viewer



Show contra 2092

Pivots



SBR-view

SBR - Setup - Accounts



SBR reference button



Add new

Select from list - Search in Titlebar

Ok button

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Translations - Report designer

Report designer

Select test document

Select test document id (3580)

No id so dropped the id in the label 3580 - Kies toetsdokument (in Afrikaans)

Lookup - Select doc (Titlebar caption) 3580



Reportman error parameter



Page setup

Also accessed from the Reportman Preview screen.



Options tab 1012

Width 1340

Height 3545

Force form name

Printer setup



Paper source (Windows)

Duplex source (Windows)

Printable margins in preview

Open drawer before

Open drawer before

Options

Preferred save format



Reportman menus

Reportman menu - File

The Print and Print Setup screens is translated via your operating system's language.

Also on the Print option on the Reportman Preview screen is translated via your operating system's language.

Druk (Ctrl+P) – Dit sal die “*Print*”-skerm begin. Jy kan 'n ander drukker (as jou stelsel se verstekdrukker) kies, 'n spesifieke bladsy kies en die aantal kopieë verander, indien nodig. In hierdie voorbeeld is die "*Microsoft Print to PDF*" die verstekdrukker.



Printer to PDF when click OK, the Save Print Output AS title bar caption is not translatable. The rest of the file explorer is translatable.



In Operating system language these options from the File menu in the Report designer is translatable.





Reportman menu - Edit



Undo

Reportman menu - Preferences



Structure / Data tabs



Structure

Data 1296

Database connections and datasets



Database browser

Open on Start

Reportman Parameters



Type of control

Text default search

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Translations - Setup ribbon

Setup Accounts

Changing groups - Update groups of Sub-accounts within selected Main accounts

Update subaccounts with this group?

Documents setup



NOTE Print standard logo not working

- Save / load layout in local files
- Append notes below item

Setup - Printer

Accessed from

- Documents setup - Page setup button
- Printer (Reports ribbon)
- Setup → Printer menu
- Report designer / Reportman



Setup groups



- Find 22434
- Clear 1016 (with Ampersand &Clear)

Excel import button - ID3270 = Spreadsheet import

- See Import on Setup ribbon - Excel import button
- On Batch entry and Stock grid - Export / Import tab

+ - om context menu collapse / expand and not consistent with > arrows on Setup → Accounts / Ledger analyser 1/2 and other screens.

Company info

Company info - Address



ID906015 - IBAN*

ID906016 - BIC*

ID906017 - SWIFT *

Companydata tab (SYSVARSEXT - table)

Company info - Options



- Debug sql
- Paths
- Save button 726
- Clear button 1016 (with Ampersand &Clear)

Setup - Countries



Column headings

Countries list only in English - Also in Debtors / Creditors / Documents

Setup - Currencies



Close button 828

Setup - Internet



Setup - System parameters



DateTime settings

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Translations - Spreadsheets

Spreadsheet sales (Default ribbon)

Error message

> Erro Batch not found. Please setup a batch in POS setup.

Select the Sales journal "*Ledger*" section of the Setup → Point-of-Sale. Once this is done, you can access the Spreadsheet sales blank spreadsheet

Spreadsheet Import / Export

Data Import Export



On the View tab most labels is translatable - but on the other tabs no data is translated.

Spreadsheet import - Find account

Find account - lookup titlebar



Created with the Standard Edition of HelpNDoc: Create cross-platform Qt Help files

Translations - Stock

Stock

Stock grid

* Click here to show/hide/move bands (Mouse over) first asterisk

* Click here to show/hide/move columns (Mouse over) second asterisk





Stock grid tabs



File types list



3583 = Save grid layout

Stock item tabs

Ledger tab



Document groups tab / Transactions tab

Context menu - Open document



Backorders tab

Also see Backorders on

- Debtors - Backorders tab
- Edit → Backorders
- Documents - Backorders

Unit 1131 / 1775

Description 1708



Documents - Backorders





backorder 906050

list 903011

Source 3202

Unit 1131 / 1775



Debtors - Backorders tab

Unit 1131 / 1775

Exp. Geselekteerde (Exp. Selected)

Setup Stock

Stock information



Lookup - Production account

Select account (Lookup - Titlebar caption)

Tax classes (Lookup - Title bar captions)

Input 1787

Output 1788

Sales account 223

Cost account

Stock account

Linked sale (stock type)

Lined items



Linked sale

Form

- Group
- Groupitem
- Linkedstock
- Example (button)

- Price type 902007
- Extra price 3150
- Sortid

Columns

- Group
- Item 1410
- Linked stock
- Extra price 3150
- Price type 902007
- Sort order

Example button screen

Linked detail (titlebar caption)



Description 1708

Exclusive 906011

Inclusive 906012

Qty 1710

"*rgoptions*"

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Translations - Stock-BOM

Stock - BOM (Production)

Stock grid

* Click here to show/hide/move bands (Mouse over) first asterisk

* Click here to show/hide/move columns (Mouse over) second asterisk



Setup Stock information



Production Contra account

Lookup - Select account (Titlebar caption)

Lookup - Production Contra account

Select account (Lookup - Titlebar caption)

Enter quantity



Messages

Assemble / Disassemble context menu confirmation message -

> Please setup production contra accout in stocksetup.

error message

> Total of salespercentage BOM not 100% auto adjusting for 98

Assemble / Disassemble confirmation-log included in this message



Processing lvl

Processing trans qty

Processing costofsales

Search (Central search)



Show details (context menu)

Found

Type column - Account, Stock, Document, Batch

Description and details alignment with document types

- Dissable details (Should be "*Assemble*" or "*Production Details*")
- Production details (Should be "*Production Details*" or "*Disassemble*")

See Stock item - Document groups tab + Transactions tab - The search descriptions does not match the translatable document type on these tabs.



Opening Qty :

Open document (context menu option) on Stock item - Document groups tab + Transactions tab)

Created with the Standard Edition of HelpNDoc: Converting Word Docs to eBooks Made Easy with HelpNDoc

Translations - Point of Sale (Standard)

POS Setup

Settings



Peripherals tab



Barcode Scanner tab

Control String

Printer



Same applies to Second printer

Force cut

Papercut / endline

POS Invoicing



Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Translations - Plugins

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Translations - Plugin - Activa

Activa

Activa Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Activa messages

No batch selected

If you did not select a batch and you are trying to add an Activa assets or manually add an Asset an error message will be displayed.

"No batch selected please select batch in setup!"

Batch contains transactions

Should there be any transactions in the batch type (selected from this list), e.g. General journal, an error message will be displayed.

"Batch is not empty!"

Add Consolidated - context menu

Field 'WTRANSACTIONID' must have a value

Activa - List

Activa 3384 / 3518



Filter 20097

Stop check for

Days 2331

Tabs

- Detail 930
- Report
    - Pivot
    - Data 1296

Activa - Pivot



Activa - Reports - Data



Transaction type

Date 238 / 1802 / 1875 / 1973

Amount 946 / 1712

Reference 607 / 1285 1719 / 1974 /

Description 178 / 355 / 606 /653 / 1708 / 1773

Account code

Account description 1108

Account type 1109 / 1935

Rest amount 3508

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Translations - Plugin - Charter

Known issues - Charter plugin

Charter Plugin - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Access violation error - Creditors - Charter tab - Creditor detail

Build button produces error

> Access violation at address 60DB848E in module 'Charter.of5'. Read of address 00000000

Charter Plugin - Debtors for Purchase document types

Within the Documents grid - You may right-click to launch the "*Charter*" screen from the on the Plugin action → Charter context menu to launch the "*Doc value*" or "*Debtors*" chart.

In the document entry screen for posted and unposted sales documents such as invoices, credit notes and quotes it seems correct.

Debtors - In the document entry screen for posted and unposted purchase documents such as purchases, supplier returns and orders, an icon will be available to launch the "*Charter*" screen. Should launch the Creditors option.

Graph details - title captions on X-axis- and Y-axis

Graph details such as titles captions on X-axis- and Y-axis need to be translated and depends on the graph.

Charter Plugin

Menu: Plugins → Financial tools → Charter (Setup ribbon).

On the entire screen only the titlebar caption and Menu item is translatable - Rest not translatable.





diget should read digit

Save as screen Save as image button Save as screen is translatable via the Windows system - except the Save as type "*Bitmap and WMF will be saved! (*.bmp,*.wmf)*"



Charter - Charts available from other options

Debtors - Charter tab

Debtors

Context menu access: From the Debtors item grid, similar charts may be generated on the Plugin action → Charter context menu for a selected debtor (customer / client) account.

Creditors - Charter tab

Creditors

Creditor detail

Creditor Group current value

Context menu access: From the Creditors item grid, similar charts may be generated on the Plugin action → Charter context menu for a selected creditor (supplier / vendor) account.

Stock - Charter tab

Stock value

Stock Days

Stock Sales

Creditor Group current value

Creditor

Creditor detail

Context menu access: From the Stock item grid, Similar charts may be generated on the Plugin action → Charter context menu for a selected stock item

Documents - Plugin action - Charter

Doc value

Debtor (Note on Sales documents such as Invoices, credit notes and quotes this is option displays charts. On purchase documents such as purchases, supplier returns and orders the charts does not display any detail in charts.

Charter Plugin integration

The "*Charter*" plugin is also available in other plugins in supporting the "*Charter*" plugin.

Created with the Standard Edition of HelpNDoc: Converting Word Documents to eBooks: A Step-by-Step Guide with HelpNDoc

Translations - Plugin - CRM

CRM plugin

CRM - Customer Relations Management - Manual - Shop - Licence : Annual licence-

CRM Customer relations management plugin for osFinancials and TurboCASH.

Menu: Plugins → External links → CRM (Setup ribbon).

CRM - Setup



Save 726

Projects mode

End status

Start status

start timer status

CRM - Activity - Dashboard view tab

Refresh 3056

Totals 1360

Treeview 3147 = View as tree



CRM - Leads tab

Search tab

Tag - marker alignment

Tabs

- Search 1204 / 1760 / 1763
- Import / Export
- Mass tag
- Conversion



Import / Export tab

Pull from outlook

From date 286 / 1208

Conversion tab

Conversion tab

Filter sales conversion

CRM - Activity

Search tab

CRM Activity status

Tag

Id



Columns

* Click here to show/hide/move columns (Mouse over)

(All) 20055

(Sorted) 20056

CRM Activity status

CRM Activity



CRM - Activity - Delete tab



Delete records

Visible

Selected 1070

CRM - All accounts tab

Actions tab

Search tab



Columns

* Click here to show/hide/move columns (Mouse over)

(All) 20055

(Sorted) 20056

Type 1079

Changed Afrikaans label 3587 - Voeg merker toe - Changed label to + Merker - Afrikaans to fit in button

CRM Plugin

CRM - All accounts- Plugins - Multimedia tab

Plugins - Multimedia (See Multimedia plugin)



* Click here to show/hide/move columns (Mouse over)

(All) 20055

(Sorted) 20056

Refid

File date 903003

Change date 2352 / 2367



Past from clipboard 21014

Scan

All accounts - Mass tags

Tag

All accounts - Mass activity

Startdate time

End datetime

CRM Activity

CRM Activity status



CRM - Invoice matrix tab

Username 1899 / 3671

User 0

CRM Activity

CRM - Calendar tab

All users

real use

Sync to outlook



CRM reports

CRM Plugin in mostly translatable - but reports only in Nederlands language. Need to add translatable reports.

These may be selected on All accounts - Mass contacts tab to print these files and to email these emailltemplates.

actlayout1 folder

Location : ...\plug_ins\reports\CRM\actlayout1

1. act 1.rep
2. act 2.rep
3. layout 1.rep
4. remote support.rep

These 4 reports replicates similar error

> Type conversion error 'Round':Expression TRpExpression27

actlayout2 folder

Location : ...\plug_ins\reports\CRM\actlayout2

1. act 1.rep
2. act 2.rep
3. layout1.rep

Prints intern nummer and a barcode

printouts folder

Location : ...\plug_ins\reports\CRM\printouts

1. act 1.rep
2. act 2.rep
3. layout1.rep

Prints news letter in dutch

Emails templates

Emails templates only supports the Nederlands language.

email1

Location : ...\plug_ins\reports\CRM\emails\email1

emailaction

Location : ...\plug_ins\reports\CRM\emailaction\emailtemplates

---

Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

Translations - Plugin - DrillDown

TC Drill Down - Plugin

DrillDown plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Drill Down 3387



Drill down main (titlebar caption) Drill Down 3387

Show on ribbon

View data

TC Drill Down

TC Drill Down - Transactions

TC Drill Down (titlebar caption)



Account type 1109 / 1935

Journaal 906074

Export (context menu) 20063

TC Drill Down Transactions Filters

Columns * Click here to show/hide/move columns (Mouse over)

(All) 20055

(Sorted) 20056



In the Periods column :

Last year 604

Opening for Opening balances

TC Drill Down - Client invoice



Euro sign

Count : (2143 Translated on Transactions option)

Export 20063 (context menu)

TC Drill Down - Invoice stock item



Euro sign

Count : (2143 Translated on Transactions option)

Export 20063 (context menu)

TC Drill Down - Stock item invoice



Euro sign

Incl. 1201

Export 20063 (context menu)

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Translations - Plugin - E-commerce

E-commerce plugin

Menu: Plugins → External links → E-Commerce (Setup ribbon).





Name of config -screen buttons not completely visible

Error message

ZQImportSource: Cannot perform this operation on a closed dataset

---

Created with the Standard Edition of HelpNDoc: Free Kindle producer

Translations - Plugin - Emailpro

Email Pro Plugin

Document EMail Pro Plugin - Manual - Shop - Licence : Once-off - This Plugin is included in the osFinancials5 subscription / TurboCASH5 subscription.

Documentation : Help documentation

Messages

Massmail button – This button will launch the following message:

> " This feature needs a separate serial please request your trail at *http://www.osf-boekhoudpakket-administratie.nl* "

This message may be hard-coded - Already changed language files from boekhoudpakket in stead of osFinancials.org

E-mail Pro icon on Document entry screen message

> "E-mail can be sent via the context menu in the Document list."

Email Pro Setup



Send mail



Columns

- ID 906446
- Email 191 / 2387
- Send 3215
- Datetime 306445

Edit

Setup wizzard (not Activated cannot launch it)

Send mail - Settings tab



Setup wizzard (not activated)

Send test mails

Rest of blocks and lists in red rectangle on right hand side of screen

Send mail - Free fields tab



Preciew att

Extra attachment

Columns

- ID 906446
- Email 191 / 2387
- Send 3215
- Datetime 306445

Edit

Setup wizzard

Mass email selection

Entire screen



Documents - Plugin action



Message E-mail can be sent via the context menu in the Document list. 3219

On documents context menu the Plugin action - E-mail pro is translatable



Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Translations - Plugin - FreeFields

Free Fields Plugin

Freefields plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Menu: Plugins → Generic → Free Fields (Setup ribbon).

Design search fields 3541



Similar to Reportman Parameters

- Type of control
- Text default search


Ontwerp soekvelde
Tipe
Detail
Naam
PROJECTS
Naam
PROJECTS
Soek SQL
Select p.*, p.SJOBPROJECTCODE TRN2123, p.SDESCRIPTION TRN178, DSTARTDATE TRN577, DENDDATE TRN579, BENABLED TRN1322 , s.SDESI
Opsoek taal
Stoor as...
Laai van lêer
Export as Insert script
Memo1

Design edit fields 3540



Created with the Standard Edition of HelpNDoc: Make Documentation Review a Breeze with HelpNDoc's Advanced Project Analyzer

Translations - Plugin - HandyTools

HandyTools

HandyTools - Licence : Free.

Caution: Make backups of your Set of Books before use

HandyTools

3402 (titlebar caption)

Countries (tab) 3691

Remove tab


HandyTools (Slegs vir gevorderde gebruikers)
'Patches'
Loop SQL
Maak joernale skoon
Kleurkondisies
Countries
Verwyder
Voorraad
Korreksies
Grootboektransaksies
Sysvars
Onreëlmatighede
Invoer
MSG
Verwyder debiteure
Anonimize db
Oorplaas rekeningdata
Verwyder krediteure
Scramble names in db
Verwyder voorraaditems
Oorplaas voorraaddata
Verwyder kontakte
Maak boodskappe skoon
Oorplaas van duplikate na min id en skrap
Konsolideer geslote jare
Konsolideer geslote jare - dokumente en voorraad
Cosolideer op jaar
Clean Registry(layouts of grids etc)
Stop

Run SQL tab


HandyTools (Slegs vir gevorderde gebruikers)
Verwyder
Voorraad
Korreksies
Grootboektransaksies
Sysvars
Onreëlmatighede
Invoer
MSG
'Patches'
Loop SQL
Maak joernale skoon
Kleurkondisies
Countries
Stel term
Delete if correct
Do trunc all tables
Alter frirebird ddl
Kode (Script)
Uitvoer

Countries tab



Stock tab


HandyTools (Slegs vir gevorderde gebruikers)
'Patches'
Loop SQL
Maak joernale skoon
Kleurkondisies
Countries
Verwyder
Voorraad
Korreksies
Grootboektransaksies
Sysvars
Onreëlmatighede
Invoer
MSG
Afrond sente
5
Proses
Tipe ID
0
Create Taxtypes for all unlinked stock
Laaste voorraadkode
Wysig voorraadkodetipe
Verwyder groepe nie in voorraad
Verwyder voorraad nie in dokumente
50
Voeg ekstra beskrywing tot voorraad
Genereer voorraad per grootboek
Verwyder ekstra beskrywing tot voorraad
Tipe ID
9
Bereken totaal in voorraad
Verwyder van komponente wat nie komponente is nie
Toets verhoging
Opdateer voorraad hoeveelheid vir opsie items

Import tab



Created with the Standard Edition of HelpNDoc: Make Your PDFs More Secure with Encryption and Password Protection

Translations - Plugin - Location-Serial-Batch

Localisation-Batches-Serials Plugin

Localisation-Batches-Serials - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Translatable output files

Document layout files will print Serials / Batches and Locations in the Italic font.

Reports is translatable Reports → Plugins → Locations-Batches-Serials. (Reports ribbon).

1. On hand report
2. Stock movement report
3. Outdated batch
4. Bought from supplier
5. Sold to customer

Stock items Location / Serial / Batch tab

Fast mode selected



Filter

Fastmode

WLINEID

Fast mode not selected



Filter

Fastmode

WLINEID

Split qty (title bar caption)

Enter qty to split

Context menu



Documents select



Serial selection (titlebar caption)

Select all (context menu option)

Sales

In document

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Translations - Plugin - Multimedia

Multimedia Plugin

Multimedia plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Multimedia setup

General tab

Multimedia titlebar caption translated via label 3379



Save 726 button

General 3205

Image 3186

Default groups

Export stock

Import files to Stock

Import files to std group

Extract Files from db to file

Show search list

Check stock files button

Image tab



Image to Jpg

minimum compression1..100

Show preview

Make all same size

Max size on convert

Width 1340

Height 3545

Watermark

Stock / Debtors / Creditors tabs

Multimedia tab translated via label 903000

URL 903007

Past from clipboard 21014 - Paste from clipboard

File date 903003

Change date 2352 / 2367

Messages paste from clipboard

No picture found!

Scan



Multimedia - Show detail

Delete no confirmation message



Multimedia context menu option on other tabs

Multimedia context menu on other tabs is not translatable

Stock - Document groups / Transaction tabs

Debtors / Creditors - Documents / Transaction tabs



Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Translations - Plugin - Multi-User-Calendar

Multi-user Calendar

Multi-User Calendar (Agenda) - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Errors Multi-user Calendar

Calendar edit resource - error - Delete

Access violation at address 67DCE4D8 in module 'osfresource.bpl'. Read of address 00000054

Access violation at address 6B420082 in module 'rtl290.bpl'. Read of address 00000008

Add resource - error

Access violation at address 6B420082 in module 'rtl290.bpl'. Read of address 00000008

Error 2

List index out of bounds (2). TList range is 0..1

REPORTINGGROUP ROOT

This Database PI-MULTI_USER-AGENDA was created when Groups was still using REPORTING GROUP ROOT in Setup -> Groups.

Since then it has changed to new group


Ongetiteld - Afspraak
Afspraak
Inprop
Afspraak
Onderwerp G | | REPORTING GROUP ROOT | Leeg
Kategorie Afspraak
Location
Verkoper: REPORTING GROUP ROOT
Processno:
Hele dag afspraak
Begintyd 2024-03-25 10:00
Eindtyd 2024-03-25 10:30
Afspraak herhaling:
Geen
Interval (dae):
0
Herhaal tot:
Aanmaning 15 Minute
Voorraaditem Leeg
osFinancials
Goed
Kanselleer


G | | REPORTING GROUP ROOT | Leeg - Afspraak
Afspraak
Inprop
Afspraak
Onderwerp G | | REPORTING GROUP ROOT | Leeg
Kategorie Debiteurafspraak
Debiteure: D1MDAVI | Mr. Mike Davies
Location
Verkoper: Russell
Processno:
Hele dag afspraak
Begintyd 2024-03-24 08:00
Eindtyd 2024-03-24 08:30
Afspraak herhaling:
Geen
Interval (dae):
0
Herhaal tot:
Aanmaning 15 Minute
Voorraaditem Leeg
Russell
Goed
Kanselleer

Calendar context menu



Change to Agenda

Quote

Calendar resources



add / edit button

Resource Maintenance

Edit

Resource Edit (titlebar caption)

Resource tab

Description:

Notes: 2437

Use as default for this user

Calendar Special days



Select color 903164

Special days (entire screen)

Calendar - Select colors

Colors options translatable via Windows language settings



Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Mijnwinkel.nl plugin

Mijnwinkel.nl Plugin is included in osFinancials5 installations but Myshop.com not included in osFinancials in the Plugin → External links - menu. Myshop.com plugin is documented in the osFinancials shop

Menu: Plugins → External links → Mijnwinkel (Setup ribbon).



Standaard artikel lookup ewfers to account should probably refer to stock item



Myshop.com

Myshop.com Plugin not available in English or Translatable version in osFinancials installation.

Documentation on Webshop in English for Myshop.com

https://www.osfinancials.org/en/webshop/e-commerce/myshop.com-plugin

Myshop.com plugin (osf-boekhoudpakket-administratie.nl)

"Myshop.com plugin

This plugin can do this:

Selected products from osF can be exported into a csv file, which can be read by myshop.com.
The upload to Myshop.com can also be automated with this plugin.
Product image can be uploaded to a FTP server of your choose.
As an extra service we can host a FTP location for you.
You can import the orders based on products uploaded by osF, customer information and order status.
After importing sales into osF, you need to uplaod the productlist for updating the stock quantity in Myshop.com

If you got an existing Myshop.com webshop, you can select the productlist import for osF as an option.
We'll generate the Myshop products in osF for you, after that, you can sync the sales.

Last development:

Automatic stock update after a sale in Myshop.com.
Automatic stock update after a sale in osF (fysical shop/POS)
Importing sales direct as an invoice
Further whishes send in by users.

Plug-ins don´t need to be downloaded they are allready present in osF.

You will receive an unlocking code per email within one day after receiving payment.
WIth a push on the button you´ll activate the bought plugin."

Created with the Standard Edition of HelpNDoc: Elevate your documentation to new heights with HelpNDoc's built-in SEO

Translations - Plugin - Office Pro

Office pro plugin

Office Pro - Manual - Shop - Licence : Annual subscription -

Broken link in documentation

Office pro on the Plugins menu - Is this the same as Bookkeeping pro on the shop?

http://www.osf-boekhoudpakket-administratie.nl/index.php/en/webshop/accountancy/office-pro

404 - Error: 404 (osf-boekhoudpakket-administratie.nl)

Could this have changed to https://www.osfinancials.org/en/webshop/branch-specific-solutions/bookkeeping-pro

Bookkeeping Pro (osfinancials.org) -

Menu: Plugins → Financial tools → Office pro (Setup ribbon)

Not translated





Created with the Standard Edition of HelpNDoc: Effortlessly Create Encrypted, Password-Protected PDFs

Translations - Plugin - Price Agreement

Price Agreement Plugin

Price Agreement Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Price Agreement - Translatable reports

Reports is translatable Reports → Plugins → Price agreement. (Reports ribbon).

- Debtor price agreement
- Creditor price agreement

Stock items (Default ribbon) - Reports button on sidebar, or Print single item context menu option.

- Price list - Large retail - Sales
- Price list - Large retail - Purchases

Price agreement setup

All labels except the Activate for debrors on / off.



Select Account... button and Lookup title bar caption

Tabs

Tabs - Stock item



Add record - All accounts

Delete record?

Lookup button - Select Account Lookup title bar caption

Tabs - Debtor / Creditor



Add record - All stock

Delete record?

Lookup button - Select stock Lookup title bar caption



Import from doc button

Select document (Titlebar caption)



Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Translations - Plugin - Reminders

Reminders / Remittance plugin

Remittance - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Reminders Messages

Sent e-mail message

> Sending email test Done please check you email adres...

Internet access not available error message:

> osfinancials1@gmail.com Socket Error # 11001
> Host not found.

Skiped typo Skipped

> Skiped not found layout for osfinancials1@gmail.com

Email selected

> Cannot perform this operation on a closed dataset

Reminders - Email Setup

Reminders - Email Setup - See EmailPro plugin

Reminders - Setup



LabelID3537 Popup if there are transactions = > Opspring as daar geen transaksies is

The label cuts off in other languages e,g. Afrikaans 3 charavters of the label not displayed - need some stretching

Document style

Reminders - Setup - List



Print selectie

View multimedia (context menu)

Columns * Click here to show/hide/move columns (Mouse over)

(All)

(Sorted)



Reminders (Action ribbon)



Show print

Set checked

Edit - Messages

Statement message 1 is populated as Statement message 1 on Debtors - Delivery address tab

Statement message is not included



Document layout

remittance1/remittance2/remittance3/remittance4 report names not translatable via language files.

Location : "... \plug_ins\reports\remittance\doctype\layouts\

Show print - Print preview error if "Show all" box is not ticked and data list is empty - Open reportman screen produces error

DOCUMENTKOP:Could not convert variant of type (UnicodeString) into type (Integer)

Show print - Print preview error if "Show all" box is list and an debtor invoice is selected it prints the Open item selection layout



Does not support TRN_3400 or LANG_3400 for example.

Remittance - Email templates updated

Language	*Location*	*Changes*
Netherlands	*\plug_ins\reports\remittance\doctype\nl\emailtemplates*	*No changes*
English	*\plug_ins\reports\remittance\doctype\en\emailtemplates*	*Translated from Netherlands to English*
Afrikaans	*\plug_ins\reports\remittance\doctype\af\emailtemplates*	*Added folder "af" for Afrikaans and translated from English to Afrikaans.*

Each folder contains the osFinancials logo and 4 remittance-html files with 4 accompanying ini files:

1. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\logo.jpg"
2. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\remittance1.html"
3. " … \plug_ins\reports\remittance\doctype\af\emailtemplates\remittance1.ini"
4. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\remittance2.html"
5. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\remittance2.ini"
6. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\remittance3.html"
7. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\remittance3.ini"
8. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\remittance4.html"
9. " … \plug_ins\reports\remittance\doctype\nl\emailtemplates\remittance4.ini"

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Markdown Content with HelpNDoc

Translations - Plugin - SQL-Browser

SQLBrowser Plugin - Translations

SQLBrowser - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Menu: Plugins → Tools → SQLBrowser (Setup ribbon).

Menus



General 1367 / 3205

Export import (Maybe JSON can be added - Already have Export option on File menu

Export to JSON

Create from JSON



Set path





Select all

Copy 3293 / 21010

Past (Paste) 21011



Export as SQL insert

Export record as Sql insert

Extract update or insert on field1

Columns

* Click here to show/hide/move columns (Mouse over)



(All) 20055

(Sorted) 20056

Created with the Standard Edition of HelpNDoc: Free Kindle producer

Translations - Plugin - Subscriptions

Subscriptions Plugin

Subscriptions - Manual - Shop - Licence : Annual licence -

Documentation : Help documentation

Subscriptions plugin MSSQL Error

Operand type clash: date is incompatible with int

Subscriptions plugin - MSSQL Compatibility

CONCAT - in sql files

The || double pipe characters works in Firebird databases but is not compatible in MSSQL databases - causes errors.

```
Select SCompanyName || ascii_char(35) || ascii_char(25)
||  sysvars.SADDRESS1
|| ascii_char(13) || ascii_char(10)
||  sysvars.SPOSTCODE
|| ' ' || sysvars.SADDRESS2
|| ascii_char(13) || ascii_char(10)
||  sysvars.SPHONENUMBER
 from sysvars
```

...\plug_ins\reports\Subscriptions\nl\Sql

Reminders - Email Setup - See EmailPro plugin

Setup Subscription



Tabs

Setup 124

Activate (Enabled 1322) to be consistent with other plugins)

On 3256

Off 3257

Invoice Periode

type 1079

Day 901017

Week 901018

Month 901019

Quarter 901020

Half year 901021

Year 901022

Due days 2221 / 2241

Period 600

Build reference string

Add description

Add description on op

Base folder email

Show for this user 3521

Save 726

Color conditions 903107

Expression 903175

Background color 3337

Font color 3338

Debtors - Subscription tab



Filter 20097

All 21019

Warnings 901002

Post warning

Subscript to process 901003

Enabled 1322

Column headings

- (All) 20055
- (Sorted)
- Id 906446



Double-click on Post warnings per invoice



Close button 828



default 1341

Log file entries e.g. "*Processing account xxxxxxxxxx*" / "*Skip processing account xxxxxxxxxx*" , etc.

Process subscriptions



Setup email

No document (already invoiced) No document 2992

Log file entries e.g. "*Processing account xxxxxxxxxx*" / "*Skip processing account xxxxxxxxxx*" , etc.

Search



The Country column heading "*Land*" should be Address 3 since the data entered in Address 3 field is displayed in thee Country column.

Address 3 (2420)

Subscriptions - Reports

Parameters

- From date 286 / 2108
- To date 287





Need to add a heading for last column Amount exclusive (translatable expression in Report designer.

Amount excl. 650 added

Location : " … \plug_ins\reports\REPORTS\SUBSCRIPT\

Language ID	*Report name*	*Report name on printed report*
LANG_1323.rep	*Reporting group 1*	*Subscriptions - Reporting group 1*
LANG_1325.rep	*Reporting group 2*	*Subscriptions - Reporting group 2*
LANG_901000.rep	*Subscriptions*	*Subscriptions*
LANG_901001.rep	*Subscriptions list*	*Subscriptions list*





Error message in Processing - Process warnings

Logfile -entry - "*Processing accountD1SM-ITH Mnr. Roger Smith*" produces error message

ZQWarnings: Cannot perform this operation on a closed dataset

Subscriptions Next run / Transaction dates 1900 year

Subscriptions to process



Debtors - Subscriptions tab



Quote



Invoice



Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's Efficient User Interface

Translations - Plugin - RetailPOS

RetailPOS plugin

Menu: Plugins →Point-of-Sales → RetailPOS (Setup ribbon).

RetailPOS - Setup

Setup retail pos (Titlebar caption)



Activate

On

Off

Save 726

Tabs and all options

RetailPOS - Setup - Payment types



RetailPOS - Setup - Images and reports



RetailPOS - Access - Plugins menu

RETAILPOS - Also see Tools -> Activate Plugins



RetailPOS - Default ribbon

Also see Titlebar captions in Retail POS screens



RetailPOS - Invoice - All orders

RetailPOS - Invoice - New order

Reference 1708

Lookup / barcode

* Click here to show/hide/move columns (Mouse over)



(All) 20055

(Sorted) 20056

WDOCID

Code



Scan will be negative (Mouse over)



Delete message

Document groups button - Documents



Document groups button - Documents

Lookup titlebar caption - Document groups

- Quotes a to convert to an invoice - Lists Quote documents
- Invoices - Lists POS invoice documents



RetailPOS - Invoice - Context menu

Get dish value F6



RetailPOS - Invoice - Select account

Select account (Titlebar caption)



RetailPOS - Quotes



New button

Column headings

- Docno

- Reference 1708
- Doc amount
- date 238
- Salesman
- Repgroup

Context menu

- Quotes
- Confirm / Unconfirm
- Make invoice

Stock group 1 refers to Document groups



RetailPOS - Reports



Last changed

Group report

Dayview

RetailPOS - Receive payment

Openamount



RetailPOS - Invoice - Setup

Launch - RetaiPOS icon on Default ribbon



Vertical POS layout

Horizontal POS layout

Color Editor - Not translatable via Windows operating system



RetailPOS - Reports



Notes on reports

- These reports may not fully translatable
- Report names may need to be added to the print-outs to show if it is Cashup report, Sales per period or Posted payments report

- Address will be displayed Address1 / Postal code / Address 2 / Address 3 for the Nederlands basetype 0

  for international base type 1 - Address will be displayed Address1 / Address 2 / Address 3 / Postal code

- Printed from Salesperson tab options and when Close POS option prints automatically.

Location : ...\plug_ins\reports\REPORTS\HORECAPOS\DAYVIEW

Cashup report



Sales per period



Posted payments



Dayview



POS Document type

Most document number prefixes starts with PVV in Afrikaans or POS in English (8-digit document numbers)

PY00001 (7-digit document number) number prefix generated for 0.00 document



Document status



Postype - Select Retail / Horeca

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

Translations - Plugin - HORECAPOS

HORRECAPOS - Errors

Error reading Series1.Marks.OnTop: Property

Error reading Series1.Marks.OnTop: Property OnTop does not exist Error in Plugin
C:\osfinancials5\plugins\HORECAPOS.of5



Click OK then opens the books but does not load HORECAPOS in Default ribbon

SQL error - Seats

Dynamic SQL Error
SQL error code = -206
Column unknown
ROOM
At line 1, column 37

SQL Error - Order setup

Dynamic SQL Error
SQL error code = -204
Table unknown
HORECAPOS_OPENTIMES
At line 1, column 15

HORECAPOS Setup

HORECAPOS Setup - General



HORECAPOS Setup - Paymentstypes



HORECAPOS Setup - Buttons



Color picker is translatable via Windows operating system, while it is not in RetailPOS, and Setup - Groups.



HORECAPOS Setup - Order setup



Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

Translations - Plugin - Belgische BTW Plugin - Shop description

---

Belgische BTW Plugin - Shop Description

Menu: Plugins → Financial tools → BtwBE (Setup ribbon)

There us no description on the Shop = http://www.osf-boekhoudpakket-administratie.nl/en/webshop/accountancy/belgische-btw-plugin changed link to en webshop = https://www.osfinancials.org/en/webshop/accountancy/belgische-btw-plugin

AI generated description

BtwBE - Belgische BTW Plugin - Manual - Shop - Licence : Once-off - Supported language: Netherlands

De Belgische BTW Plugin biedt ondersteuning voor de specifieke BTW-regelgeving in België. Met deze plugin kunt u eenvoudig en nauwkeurig BTW-berekeningen uitvoeren volgens de Belgische voorschriften en rapportagevereisten.

Belangrijkste kenmerken:

- Automatische BTW-berekening: De plugin automatiseert het berekeningsproces voor BTW op basis van de Belgische BTW-tarieven en regels.
- BTW-rapportage: Het genereert rapporten die voldoen aan de BTW-rapportagevereisten van België, waardoor u tijd bespaart en nalevingsrisico's vermindert.
- Periodieke BTW-aangiften: Vereenvoudigde en nauwkeurige generatie van periodieke BTW-aangiften, waardoor u kunt voldoen aan de wettelijke verplichtingen voor het indienen van BTW-aangiften.

Met de Belgische BTW Plugin kunt u moeiteloos voldoen aan de complexe BTW-regelgeving in België, terwijl u tegelijkertijd uw BTW-processen stroomlijnt en risico's minimaliseert.

English text

Belgian BTW Plugin (English version of the Shop text) Plugin remains in Ditch for the Dutch market)

The Belgian VAT Plugin provides support for the specific VAT regulations in Belgium. With this plugin, you can easily and accurately perform VAT calculations according to Belgian regulations and reporting requirements.

Key Features:

- Automatic VAT Calculation: The plugin automates the VAT calculation process based on Belgian VAT rates and rules.
- VAT Reporting: It generates reports that comply with Belgium's VAT reporting requirements, saving you time and reducing compliance risks.
- Periodic VAT Returns: Simplified and accurate generation of periodic VAT returns, allowing you to comply with legal obligations for filing VAT returns.

With the Belgian VAT Plugin, you can effortlessly meet the complex VAT regulations in Belgium while streamlining your VAT processes and minimizing risks.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Translations - Plugin - Stock check

Stock check

Menu: Plugins → Stock → StockCheck (Setup ribbon).

Stock check / Stock correction plugin

Stock check / Stock correction - Manual - Shop - Licence: Once-off

Documentation : Help documentation

Activation



Entire setup screen

Save button 726

Default ribbon icon



Voorraad controle - Stock control 225 used in titlebar captions and on Plugins menu

Stock check tabs

List



Columns

- Code 605
- Barcode 990 / 991 / 1774 / 1801

- Desc 1708
- Extra desc 2919
- Inactive
- Supplier code
- id 906446
- Unit 1131 / 1775

Close button 828

Correctie tab



Correctie tab

Example text for generated document.

> Genereer document
> Stock code 3-BOOR diverence 8
> Stock code 3-KOMP diverence 12
> Correction credit note Ready!

Tabel schonen - Clear table

Confirmation message

> Delete all stock checks? Warning this cannnot be reversed!

Confirmation message

Are you sure you want to post the new inventory data?

Bulkcheck tab



Delete line - No Confirmation message



Confirmation message Post difference button.

Are you sure you want to post the new inventory data?

Post difference button - Access violation error on Bulk check tab

violation of FOREIGN KEY constraint "FK_DOCLINE_STOCK" on table "DOCLINE"
Foreign key reference target does not exist

Documents Credit notes

Your reference - Text - Correction

Document lines description - Text - Stock count correction.



Created with the Standard Edition of HelpNDoc: Easy EBook and documentation generator

Translations - Plugin - Quick Order

QuickOrder Plugin

Menu: Plugins → Stock → QuickOrder (Setup ribbon).

Quick Order

Quick Order - Manual - Shop - Licence: Once-off

Documentation : Help documentation

Simplify your product ordering process with our "*Quick Order*" plugin. This plugin offers a quick and convenient method for ordering products from your PC or using a handheld PC or smart phone (through Remote Desktop / Terminal Services or RDP).

- You walk with a handheld through your warehouse, and scan or selected the product to order while standing next to the shelf.
- You see immediately actual stock numbers so that a good decision of the quantity to order can be made.
- After pressing a button it creates an order with the specified numbers.
- After which only a few clicks of the mouse will break down the order by vendor.

Optimize your ordering workflow with the "*Quick Order*" plugin, providing you with a seamless and efficient solution for managing your product orders.

Activation

Setup QuickOrder

Entire setup screen

Save button 726

Drop data messages

The message screens is already translatable but not the confirmation and error messages.







Default ribbon icon

QuickOrder - used in titlebar captions

On Activate plugins the Plugins Stock is already translated as Kits Bestelling (LabelID 3382)

QuickOrder 3382 (Title bar captions)

QuickOrder tabs

List 903011

Aanmaken (Generate 1888 / 3145)

Orders 798 / 1871

Voorraadtelling 415

List tab



Columns

- Code 605
- Aantal voorraad
- Trigger aantal
- Aantal aanvullen tot
- Onder voorraad

- Aantal voorraad berekend
- Barcode 990 / 991 / 1774 / 1801
- Desc 1708
- Extra desc 2919
- Inactive
- Sup code
- id 906446
- Unit 1131 / 1775

Buttons

Bestel +1

Bestel + 5

Bestel + 10

Bestel tot nivo

Verwijder Delete 173/ 293 / 984 / 1842 / 2248 / 21150

Verwijder confirmation message - Delete confirmation

> Weet u het zeker? 903178

Bekijk (View 3700)

Bottom columns

Code 605

Aantal

Datum

Totaal voorraad na bestellen

Close button 828

Aanmaken tab



Aanmaken tab

Genereer document(en)

Example text for generated document.

voorraad code 3-BOOR	aantal 10	document Leeg
voorraad code 3-KOMP	aantal 5	document Leeg
Bestelling aangemaakt!		

Orders tab



Nuwe - Selecteer rekening (lookup titlebar caption)

Type action

- Move 21022
- Copy 3293 / 21010

Dubbleclick = action

Edit qty and price

Columns

- (All) 20055
- (Sorted)
- WDOCID
- Factuur btw
- Afgedrukt 2964

Voorraadtelling tab



Voorraadtelling 415

Initializeer

Openingbalanse datum

Eindbalans datum

Corrigeer

Columns

Artikel (Item 1140)

Aantal op startdatum

Aantal op einddatum

Huidig aantal

Documents Orders

Seems totally translated

Created with the Standard Edition of HelpNDoc: Converting Word Docs to eBooks Made Easy with HelpNDoc

Translations - Plugis - Documents export / import

Document Export / Import Plugin

Document Export / Import Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Menu: Plugins → Documents → Document Export / Import (Setup ribbon).

Activation



Enable export import

Close button

The rest of the plugin functionality is translatable.

The "Save as" screen should be consistent with the Windows system language.

The "Open" screen should be consistent with the Windows system language.

Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Translations - Plugin - FileAndXMLImportExport

FileANDXMLExportImport

FileandXML Export Import - Manual - Shop - Licence : Once-off

Know issues : FileAndXMLImportExport

Effortlessly manage file and XML imports with our FileandXML Export Import Plugin. With a one-time licence, this plugin provides an editor mode where you can create custom file and XML imports tailored to your specific needs.

Key Features:

- Create custom file and XML imports
- Ideal for managing price lists with suppliers and other data imports
- Option for personalized import creation services by our team

Streamline your import processes and customise data imports according to your requirements with FileandXML Export Import Plugin.

Shop description

"File and xml import editor plugin

with this editor mode, you can create your own file en XML imports.

You cab use them for example for pricelists wich you supplier

If you are not unable to make the imports yourselve, you can also choose to let us make them."

FileAndXMLImportExport plugin errors

FileAndXMLImportExport plugin error - folder not found

Menu : Plugins → Tools → FileAndXMLImportExport

> Import export folder not found!
> C:\osfinancials5\importdefs\FXMLEXPORT

Solution : Added a folder "*importdefs*" and subfolder "*FXMLEXPORT*" in the osFinancials5 root directory.

Then the plugin setup could be launched.

List index of bounds error

> List index out of bounds (-1). TComboBoxStrings is empty

Translations outstanding

Activation



Export editor



Parameters - Type tab

This is similar to the outstanding translations for Report designer (reportman).


Tipe
Detail
Naam
PROJECTS
Naam
PROJECTS
Soek SQL
Select p.*, p.SJOBPROJECTCODE TRN2123, p.SDESCRIPTION TRN178, DSTARTDATE TRN577, DENDDATE TRN579, BENABLED TRN1322 , s.SDESI
Opsoek taal
Stoor as...
Laai van lêer
Export as Insert script
Memo1

Parameters - Detail tab





Parameters - Debug



Export data







Documents context menu - Import XML

Could these be a dependency of this FileAndXMLImportExport pugin



Documents grid - context menu Import XML setting



Documents context menu - Import XML

Confirmation message empty



Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Translations - Plugin - Workflow

Workflow

Workflow - Manual - Shop - Licence : Once-off -

Workflow Bank Import Plugin - Shop - Licence : Once-off

Workflow Editor Plugin - Shop - Licence : Once-off

Documentation : Help documentation

Workflow setup



Workflow setup 3469 (Title bar caption)

Workflow 3716 (Title bar caption)

Workflow (Action ribbon)

From date 286 / 2108



Workflow Error

violation of FOREIGN KEY constraint "FK_WORKFLOWWORK_STEP" on table "WORKFLOWWORK"
Foreign key reference target does not exist

Created with the Standard Edition of HelpNDoc: Easily convert your WinHelp HLP help files to CHM with HelpNDoc's step-by-step guide

FIXED - reports - GENERAL - documents

Changelog of Reports

Updated -\reports\GENERAL\documents

Bank recon report

Location : ...\plug_ins\reports\GENERAL\documents

recon.rep

Unposted payments and Unposted receipts - labels - made translatable.

Expressions changed :

TRpExpression55 CUSTOM('GETTEXTLANG',906447,'Unposted payments',0,0,0)

TRpExpression56 CUSTOM('GETTEXTLANG',906448,'Unposted receipts',0,0,0)



Created with the Standard Edition of HelpNDoc: Upgrade your help files and your workflow with HelpNDoc's WinHelp HLP to CHM conversion

ADDED - GDI scaling (Graphics Device Interface scaling) support

ADDED - GDI scaling (Graphics Device Interface scaling) support

osFinancials5.1.0.109 / TurboCASH5-2025 supports GDI scaling, or Graphics Device Interface scaling. It refers to the process of adjusting the size of graphical elements on a computer screen based on the display resolution and pixel density. The Graphics Device Interface (GDI) is a component of the Windows operating system responsible for rendering graphical elements such as text, images, and graphical user interface (GUI) elements.

As display technologies advance, screen resolutions increase, and devices with different pixel densities become more prevalent, it becomes essential to scale the graphical elements appropriately. GDI scaling helps ensure that these elements appear at a reasonable size and are visually consistent across various

displays.

Windows operating systems include a feature called Display Scaling, which allows users to adjust the size of text, apps, and other items on the screen. GDI scaling plays a role in this process by ensuring that the graphical elements are resized correctly without losing clarity or becoming pixelated.

In essence, GDI scaling helps provide a more consistent and visually pleasing user experience on displays with different resolutions and pixel densities, ensuring that the graphical elements are appropriately sized and easy to read or interact with.

Additional Zoom in / Zoom out features

In addition to the Display resolution and scaling settings, in osFinancials5.1 / TurboCASH5, there is an additional feature in some components that supports the zoom in and zoom out functionality. This feature allows users to adjust the font size in Spreadsheet reports, Spreadsheet Export/Import functions, and the Ledger analyser to view and analyse financial reports (such as the Trial balance, Income Statement and Balance sheet). By using the zoom in feature, users can increase the font size for better readability, while the zoom out feature enables a decrease in font size.

This flexibility in adjusting the data font size enhances the user experience when working with Spreadsheet reports and financial statements in osFinancials5.1 / TurboCASH5-2025, providing customization options to suit individual preferences or specific viewing needs.

Windows Display Settings - Scaling



Windows Display Settings

The basic Windows Display Settings may depend on your device, system settings and monitors connected and configures on your system.

Some common options is:

- Display resolution = 1920 x 1080 (Recommended) + Scaling 125% (Recommended) + Scaling 150% + Scaling 175%
- Display resolution = 1680 x 1050 + Scaling 125% (Recommended) + Scaling 150% + Scaling 175%
- Display resolution = 1600 x 900 + Scaling 125% (Recommended) + Scaling 150% + Scaling 175%
- Display resolution = 1400 x 1050 + Scaling 125% (Recommended) / Scaling 150% / Scaling 175%
- Display resolution = 1400 x 900 + Scaling 100% (Recommended) + Scaling 125% / Scaling 150%
- Display resolution = 1360 x 768 + Scaling 100% (Recommended) + Scaling 125%

Some additional information on these settings:

1. Display Resolution: This represents the number of pixels on your screen, typically denoted by the width and height in pixels. For example, "1920 x 1080" means the screen has a resolution of 1920 pixels in width and 1080 pixels in height.
2. Scaling: Scaling is the adjustment of the size of text, apps, and other items on the screen. This is particularly important on high-DPI (dots per inch) displays to ensure that content appears at an optimal size. The scaling percentages you mentioned (e.g., 125%, 150%, 175%) indicate how much the interface elements are scaled compared to their original size.
3. Recommended Settings: The "Recommended" settings are often suggested by the operating system based on your hardware configuration and display properties. These settings are intended to provide an optimal balance between readability and screen real estate.
4. Custom Settings: Users can customize display settings based on their preferences and the capabilities of their monitors. For example, choosing a lower resolution with higher scaling can make text and icons larger, which may be useful for individuals with visual impairments.
5. High-DPI Displays: Scaling becomes especially important on high-DPI displays, where the pixel density is higher. Without proper scaling, text and graphical elements might appear too small and be challenging to read or interact with.

Users often choose display settings based on their preferences, the size of their monitor, and individual visual comfort. The goal is to find a balance between having enough screen real estate and ensuring that the displayed content is easily readable and usable. Keep in mind that the specific options available may vary depending on your version of Windows and the capabilities of your graphics hardware.

Windows Display Settings Tested in osFinancials5.1.0.109 / TurboCASH5-2025

osFinancials5.1's default themes and configuration settings are optimized for a display resolution of 1920 x 1080 with a scaling of 125%. If you decide to use a higher scaling percentage (e.g., 150%, 175%) or choose a different display resolution and / or scale settings, you may encounter display issues with some large grid and forms (e.g. Debtors, Creditors, Stock items and Documents) within the osFinancials5/TurboCASH5-2025 interface.

Adjusting these settings should help ensure a proper display and functionality when using different scaling options or display resolutions beyond the recommended 1920 x 1080 with 125% scaling.

Display resolution = 1920 x 1080 (Recommended) + Scaling 125% (Recommended)

osFinancials5.1.0.109 interface, grids and forms display great.

But when scaling of 150% or 175% is applied, similar display issues as with the Display resolution = 1366x768 + Scaling 100% on certain grid / forms may occur.

When opening these Debtor / Creditor form Stock item grid and form Documents grid and form the Unpin Ribbon or the Tablet mode setting in the Colors.ini file in the Theme folder may address some of these issues.

When opening these forms and grids, in the default mode (Pin the ribbon - Show ribbon) there could be rendering display issues.

To address this, you can follow these steps:

1. Unpin - Hide the ribbon or use Tablet mode before accessing these grids and forms.
2. If a form is already opened close all active forms (Tools → Close active forms (Setup ribbon)).
3. Unpin - Hide the ribbon or use Tablet mode (style=4) in the colors.ini file.
4. Automatically hide Taskbar
5. Relaunch the grids and / or forms. The display should be OK.

Stock item form - Display resolution = 1920 x 1080 (Recommended) + Scaling 125% (Recommended)

It appears that the Stock Edit form at Display resolution = 1920 x 1080 (Recommended) + Scaling 125% (Recommended) list some grid columns after the last tab (in this example, Location-Batches-Serials tab).



Grids and Forms Display resolution = 1366 x 768 + Scaling 100%

Similar issues appear at various Windows Display Settings for all options up to Display resolution = 1920 x 1080 (Recommended) + Scaling 150% / 175%, but

Display resolution = 1920 x 1080 (Recommended) + Scaling 125% seems to display correct.

Debtors / Creditors

Hide Ribbon tabs (Unpin before opening form) - OK



Hide Ribbon tabs (Pin before opening form) - double-click to hide - Display issues



Hide Ribbon tabs (Pin after opening form) - Display issues - e.g. on Delivery address tab, only the Message first line is displayed - Message 1, Message 2, Message 3 is not displayed and cannot scroll.



Stock items

Stock item grid

Hide Ribbon tabs (Unpin before opening form) - OK



Hide Ribbon tabs (Pin before opening form) - double-click to hide - Display issues



Hide Ribbon tabs (Pin after opening form) - Display issues - e.g. on Delivery address tab, only the Message first line is displayed - Message 1, Message 2, Message 3 is not displayed and cannot scroll.



Hide Ribbon tabs (Pin after opening form) - Display issues



Stock item form

Hide Ribbon tabs (Unpin after opening form) - Display issues



Documents

Document grid

Hide Ribbon tabs (Unpin before opening form) - OK - But Layout file 4 is not displayed on the sidebar.

NOTE - if Display resolution = 1920 x 1080 (Recommended) + Scaling 125% (Recommended) is selected, Layout file 4 is displayed on the sidebar



Hide Ribbon tabs (Pin after opening form) - Display issues



Document edit form

Hide Ribbon tabs (Unpin before opening form) - OK



Hide Ribbon tabs (Pin after opening form) - Display issues



Hide Ribbon tabs (Pin after opening form) - Display issues - e.g. on Footer - Current balance and Invoice total is displayed, rest of the Credit limit, Available limit, etc. including the OK / Cancel buttons not displayed.



Show Ribbon tabs (Pin after opening form) - Display issues - e.g. on Footer - Current balance and Invoice total is displayed, rest of the Credit limit, Available limit, etc. including the OK / Cancel buttons not displayed.



Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

FIXED / ADDED - Themes

Themes

Theme screenshots - Screenshots of the installed themes and new themes (about 34 themes). A sideshow of the themes rotating is available in osfinancials-themes-slides.zip file

Known issues - Themes - Image strips excludes reports path. If images is removed from the theme folder, the imagestrip defaults to the classic theme, or other theme.

Creditor control icon not loading correctly - Classic icon in some themes - Fixed in osFinancials5.1.0.109 - but with the osFinancials5.1.0.127 update does not include these fixes.

FIXED - Themes

FIXED - Creditor control icon not loading correctly

The creditor icon - does not change when creating an image strip in all themes - Setup → Accounts and in Ledger viewer - It is not correctly rendered / displayed.

Checked properties of creditor svg files

Replaced the Acccreditors.svg icons and created new image strips



FIXED - Help.svg with osF icon

The osF icon is displayed on most themes instead of Help.svg icons.



For consistency the Help.svg icon was removed to display the osF icon from the following themes folders:

1. Glass
2. Silver
3. Soft-blue

4. Material-Blue
5. Material-Navy
6. Material-Maroon

New image strips created to update the changes.

Designing Themes with SVG Material icons

Designing themes with SVG Material icons can add a visually appealing and consistent look to your website or application. Material icons are a set of scalable vector icons created and maintained by Google. They are designed to work well with Material Design, providing a clean and unified visual language. Here's a guide on how you can integrate SVG Material icons into your theme design:

1. Include Material Icons Library: Start by including the Material Icons library in the <head> section of your HTML document. You can do this by adding the following line:

   html

   ```
   <link rel="stylesheet" href="https://fonts.googleapis.com/icon?family=Material+Icons">
   ```

2. Choose Icon(s): Visit the Material Icons website to explore and choose the icons that best fit your theme. You can search for icons and click on them to get the SVG code.
3. Embed SVG Code: Once you've selected an icon, copy the SVG code provided on the Material Icons website. Paste the SVG code directly into your HTML where you want the icon to appear. For example:

   html

   ```
   <i class="material-icons">icon_name</i>
   ```

   Replace icon_name with the actual name of the icon you chose.

4. Styling: Apply styles to your icons using CSS. You can customize the size, color, and other properties. For example:

   css

   ```
   .material-icons {
      font-size: 24px; /* Adjust the size as needed */
      color: #333;     /* Set the color */
   }
   ```

5. Responsive Design: Ensure that your icons are responsive. You can use media queries or relative units (e.g., percentage) to make sure the icons adapt to different screen sizes.

6. Icon Theming: If your theme has specific color schemes, you can adjust the icon colors to match. You may also consider creating variations of icons for different states (e.g., active, inactive).
7. Accessibility: Ensure your icons are accessible. Add appropriate ARIA roles and labels for screen readers to enhance accessibility.
8. Animation (Optional): If you want to add some interactivity, you can use CSS animations or JavaScript to create animated effects when interacting with the icons.
9. Testing: Test your theme across different browsers and devices to ensure consistent and reliable performance.

By following these steps, you can effectively integrate SVG Material icons into your theme design, providing a visually cohesive and user-friendly experience.

Current Themes

Themes Blue, Glass, Silver Soft-blue with custom colors the Create image strip looses the reports material icons and on Reports menu it reverse back to classic icons.

Theme	*Icon set*	*Skin*	*Style*	*colorname*	*coloraccent*
Classic	*Classic*	*Metropolis*	*style=3 (2016)*	*Colorful*	*1 (Blue)*
Blue	*Material (Blue)*	*Blue*	*style=2 (2013)*	*Colorful*	*1 (Blue)*
Glass	*Material (Blue)*	*GlassOceans*	*style=0 (2007)*	*GlassOceans*	*1 (Blue)*
Material	*Material (Black)*	*Lilian*	*style=3 (2016)*	*White*	*1 (Blue)*
Silver	*Material (Black)*	*Silver*	*style=2 (2013)*	*Silver*	*1 (Blue)*
Soft-blue	*Material (Blue)*	*MoneyTwins //Metropolis*	*style=3 (2016)*	*MoneyTwins //Colorful*	*1 (Blue)*
VS2010	*Classic*	*VS2010*	*style=5 (2019)*	*colorname=VS 2010*	*1 (Blue)*

New Themes skins

A total of 27 new skins

Theme	Icon set		Skin	Style	colorname	coloraccent
Caramel	Material (Black)		Caramel	style=5 (2019)	White	0 (Yellow)
Coffee	Material (Black)		Coffee	style=5 (2019)	White	0 (Yellow)
DevExpressStyle	Material (Black)	#000000	DevExpressStyle	style=5 (2019)	White	4 (Purple)
Foggy	Material (Black)	#000000	Foggy	style=5 (2019)	White	0 (Yellow)
iMaginary	Material (Black)	#000000	iMaginary	style=5 (2019)	White	2 (Green)
Lilian	Material (Black)	#000000	Lilian	style=5 (2019)	White	1 (Blue)
LiquidSky	Material (Black)	#000000	LiquidSky	style=5 (2019)	White	1 (Blue)
LondonLiquidSky	Material (Black)	#000000	LondonLiquidSky	style=5 (2019)	White	1 (Blue)
Material-Black	Material (Black)	#000000	Office2007Black	style=5 (2019)	White	3 (Orange)
Material-Blue	Material (Blue)	#0000ff	Office2007Blue	style=5 (2019)	White	1 (Blue)
Material-Green	Material (Green)	#008000	Office2007Green	style=5 (2019)	White	2 (Green)
Material-Maroon	Material (Maroon)	#800000	Metropolis	style=5 (2019)	White	3 (Orange)

Material-Navy	*Material (Navy)*	*#000080*	*Office2007Blue*	*style=5 (2019)*		*1 (Blue)*
Material-Pink	*Material (Ruby)*	*#E0115F*	*Office2007Pink*	*style=5 (2019)*	*White*	*3 (Orange)*
Material-White	*Material (Black)*	*#000000*	*Office2013White*	*style=5 (2019)*	*White*	*1 (Blue)*
McSkin	*Material (Black)*	*#000000*	*McSkin*	*style=5 (2019)*	*White*	*1 (Blue)*
Metropolis	*Material (Black)*	*#000000*	*Metropolis*	*style=5 (2019)*	*White*	*1 (Blue)*
MoneyTwins	*Material (Black)*	*#000000*	*MoneyTwins*	*style=5 (2019)*	*White*	*1 (Blue)*
Seven	*Material (Black)*	*#000000*	*Seven*	*style=5 (2019)*	*White*	*1 (Blue)*
SevenClassic	*Material (Black)*	*#000000*	*SevenClassic*	*style=5 (2019)*	*White*	*1 (Blue)*
Springtime	*Material (Black)*	*#000000*	*Springtime*	*style=5 (2019)*	*White*	*2 (Green)*
Stardust	*Material (Black)*	*#000000*	*Stardust*	*style=5 (2019)*	*White*	*1 (Blue)*
Summertime	*Material (Black)*	*#000000*	*Summer2008*	*style=5 (2019)*	*White*	*0 (Yellow)*
TheAsphaltWorld	*Material (Black)*	*#000000*	*TheAsphaltWorld*	*style=5 (2019)*	*White*	*1 (Blue)*
TheBezier	*Material (Black)*	*#000000*	*TheBezier*	*style=5 (2019)*	*White*	*1 (Blue)*
Valentine	*Material (Ruby)*	*#E0115F*	*Valentine*	*style=5 (2019)*	*White*	*3 (Orange)*

Whiteprint	*Material (Black)*	*#000000*	*Valentine*	*style=5 (2019)*	*White*	*1 (Blue)*

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

FIXED - Themes

Themes fixed for 2025 osFinancials5.1/TurboCASH5-3 installs - osFinancials5.1/TurboCASH5-2025

Obsolete folders and files to Delete in ...bin/themes folder

- My-Material
- svg-theme
- svg-theme.zip

Known issues - Classic Report icons display in SVG themes

If all the all icons is deleted in a theme folder just to include image strips (fst and dfm files) - then the Reports menu, Userreports menu and Spreadsheet reports menu display classic icons and not the svg icons.

NOTE with the latest installs and updates, the Blue, Glass, Silver Soft-blue themes with custom colors looses the reports material icons and on Reports menu it reverse back to classic icons. When Creating the image strip. (only image strips and no svg icons were included in these respective theme folders).

To Fix this - Had to bring back the svg icons from external source (folders) into these theme folders to display the original svg icon (after image strip was created.

theme folder with no icons content:

1. BatchEnabledButtons.fst
2. ilbandlarge.fst

3. ilbandsmall.fst
4. ImageList1.fst
5. BatchEnabledButtons.dfm
6. ilbandlarge.dfm
7. ilbandsmall.dfm
8. ImageList1.dfm
9. BackGround1.Jpg
10. BackGround2.Jpg
11. colors.ini

Classic icons for Reports menu, User reports menu and Excel reports menu displayed when no images is included in the respective themes folder:



To display the correct svg icons for Reports menu, User reports menu and Excel reports menu, the icons needs to be included in the respective themes folders:



sDefaultPainters - Displays obsolete icon in Batch entry screens

sDefaultPainters - Displays icon in all Batch entry screens.



Theme skins - Incompatible

Blueprint - Messages and some labels unreadable

DarkSide - Pivot table too dark and some text not readable

DevExpressDarkStyle - Messages and some labels unreadable

HighContrast - Messages and some labels unreadable + Pivot table too dark and some text not readable

MetropolisDark - Messages and some labels unreadable + Pivot table too dark and some text not readable

Pumpkin - Pivot table too dark and some text not readable

Office2016Dark - Messages and some labels unreadable + Pivot table too dark and some text not readable

Sharp - Pivot table too dark and some text not readable

SharpPlus - Pivot table too dark and some text not readable

VisualStudio2013Dark - Messages and some labels unreadable + Pivot table too dark and some text not readable

Dark themes - Some screenshots

VisualStudio2013Dark







Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Themes screenshots

Current themes

Classic



Blue


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
START
DEFAULT
REPORTS
SETUP
USER TAB
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Budget
Viewer Debtors / Creditors
Include opening balances
Opening balances only
SBR view
Pivot
REPORTING GROUP ROOT 0.00 |
#Current assets 98,390.00 |
G700000 Debtors control 76,390.00 |
#Debtor group 1C 46,215.00 |
D1ABGRE Mr. AB Green 43,840.00 |
D1MACDS MAC Shop Decor Specialists 2,375.00 |
#Debtor group 1B 30,175.00 |
D1MDAVI Mr. Mike Davies 10,675.00 |
D1ROGSM Mr. Roger Smith 19,500.00 |
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Glass


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Report
Export
Print
SBR view
Per period
Free selection
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Pivot
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Budget
Viewer Debtors / Creditors
Include opening balances
Opening balances only
REPORTING GROUP ROOT 0.00 |
#Current assets 98,390.00 |
G700000 Debtors control 76,390.00 |
#Debtor group 1C 46,215.00 |
D1ABGRE Mr. AB Green 43,840.00 |
D1MACDS MAC Shop Decor Specialists 2,375.00 |
#Debtor group 1B 30,175.00 |
D1MDAVI Mr. Mike Davies 10,675.00 |
D1ROGSM Mr. Roger Smith 19,500.00 |
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
G860000 VAT - Control - 15% 660.00 |
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Material


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Budget
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Silver


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
START
DEFAULT
REPORTS
SETUP
USER TAB
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Budget
Viewer Debtors / Creditors
Include opening balances
Opening balances only
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Soft-blue


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Budget
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

VS2010


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
SBR view
Pivot
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Budget
Viewer Debtors / Creditors
Include opening balances
Opening balances only
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
2
1
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5L

New Themes

Caramel



Coffee


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Ledger analyser 1
Per period
Free
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
SBR view
Pivot
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Budget
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
G860000 VAT - Control - 15% 660.00 |
T860010 Output VAT - 15% | 990.00
T860020 Input VAT - Standard rate -15% 1,650.00 |
G900000 Creditors control 23,350.00 |
#Creditor group 1C 6,600.00 |
C2ABCOS ABC-Office-Supplies 6,600.00 |
#Creditor group 1B 16,750.00 |
C2AONES A-ONE Suppliers 23,000.00 |
C2BESTS BEST Suppliers | 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

DevExpressStyle



Foggy


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
SBR view
Pivot
+
-
REPORTING GROUP ROOT 0.00 |
#Current assets 98,390.00 |
G700000 Debtors control 76,390.00 |
#Debtor group 1C 46,215.00 |
D1ABGRE Mr. AB Green 43,840.00 |
D1MACDS MAC Shop Decor Specialists 2,375.00 |
#Debtor group 1B 30,175.00 |
D1MDAVI Mr. Mike Davies 10,675.00 |
D1ROGSM Mr. Roger Smith 19,500.00 |
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
2
1
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

iMaginery


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Ledger analyser 1
Per period
Free
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Budget
Viewer Debtors / Creditors
Include opening balances
Opening balances only
SBR view
Pivot
+
-
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
G860000 VAT - Control - 15% 660.00 |
T860010 Output VAT - 15% | 990.00
T860020 Input VAT - Standard rate -15% 1,650.00 |
G900000 Creditors control 23,350.00 |
#Creditor group 1C 6,600.00 |
C2ABCOS ABC-Office-Supplies 6,600.00 |
#Creditor group 1B 16,750.00 |
C2AONES A-ONE Suppliers 23,000.00 |
C2BESTS BEST Suppliers | 6,250.00
2
1
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Lilian


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Budget
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

LiquidSky


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
SBR view
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Pivot
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

LondonLiquidSky



Material-Black



Material-Blue



Material-Green



Material-Maroon



Material-Navy



Material-Pink



Material-White



McSkin


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
SBR view
Pivot
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
G860000 VAT - Control - 15% 660.00 |
T860010 Output VAT - 15% | 990.00
T860020 Input VAT - Standard rate -15% 1,650.00 |
G900000 Creditors control 23,350.00 |
#Creditor group 1C 6,600.00 |
C2ABCOS ABC-Office-Supplies 6,600.00 |
#Creditor group 1B 16,750.00 |
C2AONES A-ONE Suppliers 23,000.00 |
C2BESTS BEST Suppliers | 6,250.00
2
1
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE1

Metropolis


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP

MoneyTwins


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Budget
Viewer Debtors / Creditors
Include opening balances
Opening balances only
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Seven


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
SBR view
Pivot
+
-
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
G860000 VAT - Control - 15% 660.00 |
T860010 Output VAT - 15% | 990.00
T860020 Input VAT - Standard rate -15% 1,650.00 |
G900000 Creditors control 23,350.00 |
#Creditor group 1C 6,600.00 |
C2ABCOS ABC-Office-Supplies 6,600.00 |
#Creditor group 1B 16,750.00 |
C2AONES A-ONE Suppliers 23,000.00 |
C2BESTS BEST Suppliers | 6,250.00
2
1
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5L

SevenClassic



Springtime


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Report type
Trial balance
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Budget
SBR view
Pivot
+
-
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
G860000 VAT - Control - 15% 660.00 |
T860010 Output VAT - 15% | 990.00
T860020 Input VAT - Standard rate -15% 1,650.00 |
G900000 Creditors control 23,350.00 |
#Creditor group 1C 6,600.00 |
C2ABCOS ABC-Office-Supplies 6,600.00 |
#Creditor group 1B 16,750.00 |
C2AONES A-ONE Suppliers 23,000.00 |
C2BESTS BEST Suppliers | 6,250.00
2
1
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Stardust


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

Summertime


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
SBR view
Pivot
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

TheBezier


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Ledger analyser 1
Per period
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
SBR view
Pivot
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
G750000 Stock control 11,000.00
B810000 ABC - Bank 11,000.00
#Income 117,400.00
*G010000 Sales 117,400.00
#Capital 5,000.00
G505000 Capital 5,000.00
#Current liabilities 24,010.00
G860000 VAT - Control - 15% 660.00
T860010 Output VAT - 15% 990.00
T860020 Input VAT - Standard rate -15% 1,650.00
G900000 Creditors control 23,350.00
#Creditor group 1C 6,600.00
C2ABCOS ABC-Office-Supplies 6,600.00
#Creditor group 1B 16,750.00
C2AONES A-ONE Suppliers 23,000.00
C2BESTS BEST Suppliers 6,250.00
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE1

TheAsphaltWorld



Valentine


MY-BOOKS-MSSQL-B - osFinancials 5.1.0.109
Start
Default
Reports
Setup
User tab
Reports
User reports
Spreadsheet reports
Ledger analyser 1
Ledger analyser 2
Age analysis
T-Account viewer
Printer
Budgets
Reports
Per period
Free selection
Report
Export
Print
Display
2021/03/01 / 2022/02/28
Periods
Month
2 Months
3 Months
4 Months
6 Months
Year
Groups
Reporting group 1
Ignore zero balances
Viewer Debtors / Creditors
Include opening balances
Opening balances only
Report type
Trial balance
Budget
SBR view
Pivot
+
-
G750000 Stock control 11,000.00 |
B810000 ABC - Bank 11,000.00 |
#Income | 117,400.00
*G010000 Sales | 117,400.00
#Capital | 5,000.00
G505000 Capital | 5,000.00
#Current liabilities 24,010.00 |
G860000 VAT - Control - 15% 660.00 |
T860010 Output VAT - 15% | 990.00
T860020 Input VAT - Standard rate -15% 1,650.00 |
G900000 Creditors control 23,350.00 |
#Creditor group 1C 6,600.00 |
C2ABCOS ABC-Office-Supplies 6,600.00 |
#Creditor group 1B 16,750.00 |
C2AONES A-ONE Suppliers 23,000.00 |
C2BESTS BEST Suppliers | 6,250.00
2
1
Net Profit/Loss C -117,400.00
Balance D 117,400.00
Universal Administrator
MY-BOOKS-MSSQL-B
LAPTOP-I5LE

WhitePrint



Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

FIXED - Firebird databases - Upgraded to Firebird 2.1 ODS 11.1.

Upgraded to Firebird 2.1 ODS 11.1.

Creating a blank osFinancials5 database, defaults to Firebird 2.1 ODS 11.1. Also implemented in TurboCASH5-2025

Firebird 1.5 is designated ODS 10.1

All other older databases, including tutorials, is Upgraded to Firebird 2.1 ODS 11.1.

All databases (Sets of Books) available for download in the Creation wizard, is updated to Firebird 2.1 ODS 11.1 and the start of the Financial year is set to 2022/XX/XX.

If the set of books for your language and or country, is not available in the books directory, you may select any of the available Firebird Sets of Books and linked languages available as a free download.

All firebird database types available for download (Create a Set of Books -default option), is upgraded from firebird version 1.5 (ODS version - 10.1) to Firebird version 2.1 - (ODS version - 11.1)

Created with the Standard Edition of HelpNDoc: Protect Your Confidential PDFs with These Simple Security Measures

FIXED - Cannot Open / Create MSSQL Databases

FIXED - Cannot Open / Create MSSQL Databases in osFinancials5.1.0.102 / TurboCASH5-2025

FIXED - Cannot Open MSSQL Databases

Cannot Open MSSQL Databases after updating osF5.1.0.93 to osF5.1.0.99 and osF5.1.0.100

Can open MSSQL Sets of Books in all versions since osF5.1.0.49 to osF5.1.0.93

Could not retest bugs and reports in osF5.1.0.100

Could open all the same MSSQL Set of Books in osF5.1.0.93 but after the update to osF5.1.0.99 cannot open any Set of Books for the MSSQL Database types

Login screen in osF5.1.0.99

> Error connecting to MY-BOOKS-MSSQL-B
> TCP Provider: No connection could be made because the target machine actively refused it.

Could not locate file to fix

FIXED - Cannot Create a new MSSQL Database type in osFinancials5.1.0.100 / TurboCASH5-2025

Create a new Database Customize your own Set of Books (Advanced)? option for MSSQL Database type produces similar errors on the Creation wizard.

TCP Provider: No connection could be made because the target machine actively refused it.

Next button

TCP Provider: No connection could be made because the target machine actively refused it.
select count(*) from transact

NOTE Can Create a new MSSQL Database type in osFinancials5.1.0.93 / TurboCASH5-2025

Created with the Standard Edition of HelpNDoc: Don't Let Unauthorized Users View Your PDFs: Learn How to Set Passwords

ADDED / Fixed - Languages labels

Language changelog

The language files updates may need to be merged after osFinancials5.1.0.189 - Changes to language files before osFinancials5.1.0.127 update not included in osFinancials5.1.0.189 update install.

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/languages

Updates languages

Location : " ... \ bin \ languages \

Update Afrikaans language

- LabelID3642 Maak tafelbewegings skoon => Maak tabelbewegings skoon - Changed back to Maak tafelbewegings skoon since this is related to tables and seats for the HORECAPOS plugin.
- LabelID21073 - Shows the system print dialog, or a custom print dialog => Wys die stelseldrukdialoog, of 'n pasgemaakte drukdialoog
- LabelID906105 - BTW per priode changed to BTW per periode (Fixed languages typo in Afrikaans)
- LabelID345 is set to singular Groepe => Groep
- LabelID1718 Verkoopspersoon => Verkoper: - Salesperson: - label cuts off in Afrikaans - on Calendar appointments screen.
- LabelID3587 - Voeg merker toe - Changed label to + Merker - Afrikaans to fit in button CRM Plugin

- LabelID3014 - Kasboekverslag => in Afrikaans to Bankrekonsiliasie verslag soos op
- LabelID2186 Bankrekonsiliasie verslagopsies => Bankstaat opsies -
- LabelID2205 Verstek bankrekonsiliasie metode changed to Verstek bankrekonsiliasie - Label was too long for System parameters screen Default bank reconciliation

Update English languages and Afrikaans language

Changed Receipts options -

LabelID 1314 Receipts options changed to singular, => Receipt options. The Receipt options screen select the options to print one receipt.

Bank account recon options - Caption in titlebar - English language

Language labelID 2186 Bank account recon options => Bank statement options -

The changed caption in the titlebar "*Bank statement options*" should then be fit to accommodate both options :

1. Bank import plugin where bank transactions is imported from bank statements, or;
2. Bank reconciliation default method (since reconciling the bank transactions with bank statements).

LabelID3275 - Show refs for account => Show references for account

List of changed language files :

1. Afrikaans
2. English
3. en-Australia
4. en-Bangladesh
5. en-Barbados
6. en-Belize
7. en-Botswana
8. en-Cameroon
9. en-Canada
10. english-usa
11. en-Ireland

12. en-Isle-of-Man
13. en-Lesotho
14. en-Malawi
15. en-Malta
16. en-Mauritius
17. en-Namibia
18. en-New-Zealand
19. en-Rwanda
20. en-South-Africa
21. en-Tanzania
22. en-Tonga
23. en-Trinidad
24. en-Uganda
25. en-UK
26. en-Zambia
27. en-Zimbabwe

Languages labels added

Number of records - 4071 - after new labels (Precious record count was 4061 - 10 labels added - count now 4071

TRN_906588 - Value stock account

TRN_906587 - Document reference

TRN_906586 - Stock - Expected quantities

TRN_906585 - Stock item list - Active stock

TRN_906584 - Production list

TRN _902008 - Price list - Large retail - Sales = Added in Plugin range

TRN _902009 - Price list - Large retail - Purchases = Added in Plugin range

TRN_906589 - NO-TAX Layout file

TRN_906590 - NO-TAX Document layout

TRN_906591 - NO-TAX Document layout (15-code)

Obsolete / out dated language files

Obsolete / out dated language files - May be deleted from languages folder (" *...\bin\languages* ")

Language file	*Date of last changes*	*Replaced and updated with*	*Books download*
African.dfm	*2020/03/06*	*Afrikaans.dfm*	
en-Trinandad.dfm	*2020/03/06*	*en-Trinidad.dfm*	*EN-TRINIDADTOBAGO*
Nederlands.dfm.bak	*2020/05/08*		
testlang.dfm	*2020/03/06*		
Zeng.dfm	*2020/03/06*		

These language files is not linked to any Firebird Sets of Books and linked languages available as a free download. from the Download option on the "*Creation wizard*".

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Known issues - Language label inconsistencies

Receipt / Receipts

Bank import plugin it refers to Receipt LabelId 1100 used for Receipt. Receipts label ID 2233 is used in other screens such as Receipts journal and label ID 2232 such as Payments journal.



Receipt LabelId 1100 is in the singular form, changing this label, causes Receipts to display when the Print receipt option is used.

This label in the Receipt column may need to be changed in the osFinancials5.exe to be consistent with the Payments column. Also replicated in / TurboCASH5-2025.

This will resolve issues relating to other language dialects, such as Afrikaans, French, Spanish, etc.



Receipts options (LabelID 1314) title bar caption is changed in the language file to Receipt options since this options screen is used to generate a single transaction and print a receipt.



This inconsistency can lead to confusion in other language dialects like Afrikaans, French, Spanish, etc.

Document Status - Open

Open uses the same Label as is used in Open buttons. The LabelID could be LabelID 163,, LabelID 20120 or LabelID 20142 - The document status for Open documents is Unconfirmed in Documents grid.



In the Document entry form's header refers to Open (LanguageID's 163, 20120 or 21042)., which is used for the Open button on most screens. There is LabelID 580, Open for posting. Unposted (LabelID's 962 or 1097 shows in the Status column of documents grid.

This inconsistency can lead to confusion in other language dialects like Afrikaans, French, Spanish, etc.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

NEW - Empty Sets of Books - Supports up to 8 digit main accounts and 3 digit sub accounts

---

NEW – 4 Digit Chart of Accounts – with larger description fields

These account codes and longer descriptions in osFinancials5/TurboCASH5-2025 provide flexibility for creating and customizing the Chart of Accounts to meet specific requirements, accounting frameworks, and standards, including taxonomies such as GAAP, IFRS (full), and IFRS for SMEs. This customization takes into account language variations and jurisdiction-specific considerations.

See - Generally Accepted Accounting Principles (GAAP) and International Financial Reporting Standards (IFRS)

- Universal chart of accounts is suitable for use with IFRS, US GAAP and other comparable accounting standards. https://www.ifrs-gaap.com/universal-chart-accounts

- IFRS® Sustainability Disclosure Standards around the world - https://www.ifrs.org/ifrs-sustainability-disclosure-standards-around-the-world/

The following databases were created using the EMPTY-BOOKS-4X3-DIGITS Firebird Database type which supports longer descriptions:

- 4-EN-SOUTH-AFRICA-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes, aligned with the VAT201-return.
- 4-AF-SUID-AFRIKA-GENERIES.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts in Afrikaans. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes (Belasting op Toegevoegde Waarde (BTW) Suid-Afrika (Afrikaans), aligned with the VAT201-return.
- 4-EN-UK-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-accounts, based on the United Kingdom (UK) Chart of Accounts. It incorporates specific UK terminology and includes Value Added Tax (VAT) - United Kingdom accounts based on the VAT Standard rate scheme. The VAT-account and VAT-codes structure in the Chart of Accounts is designed to match the various boxes on the UK VAT return. NOTE: Various schemes for VAT may be applicable for various scenarios.

An example of a Firebird database is NL_RGS2019PLUS (Netherlands) where longer descriptions is used in the chart of Accounts (can be downloaded from through the "*Let osFinancials help you to create a Set of Books?*" option.

Chart of Accounts - Download options

Sets of Books - The Chart of Accounts in osFinancials supports up to 11-digits (8-digits for the main accounts and 3 digits for the sub-accounts). You have the flexibility to choose from a range of templates for Sets of Books, including a 6-digit structure consisting of 3 digits for the main accounts and 3 digits for the sub-accounts. These templates can be downloaded through the "*Let osFinancials help you to create a Set of Books?*" option.

Alternatively, if you prefer to start with a basic empty Sets of Books, you can utilize the "*Customise your own Set of Books (Advanced)?*" option. This advanced feature allows you to define the number of digits, with a maximum of 11 digits (8 digits for the main accounts and 3 digits for the sub-accounts).

The basic Sets of Books created using this option will include the essential three main accounts: Debtors control, Creditors control, and Retained earnings. The remaining Chart of Accounts can be fully customized according to your specific requirements. This flexibility enables you to tailor the Sets of Books to suit your

unique accounting needs.

Chart of Accounts - Number of digits and length of description fields

A chart of accounts serves as a comprehensive list of all the accounts utilized by an organization for financial reporting. It enables the systematic classification and summarization of financial transactions in a consistent and logical structure. In osFinancials5.1/TurboCASH5-3 the Chart of Accounts is organized by linking accounts to account groups 1 and/or account group 2. This structuring facilitates the generation of financial statements such as the Trial Balance, Income Statement, Balance Sheet, and other reports.

While some accounting software provides for up to 100 characters of account descriptions, in osFinancials the EMPTY-BOOKS range of basic Chart of Accounts, supports:

- Account code: The account code number of digits, with a maximum of 11 digits (8 digits for the main accounts and 3 digits for the sub-accounts).
- Account description: The account and group descriptions of up to 128 characters

These account codes and descriptions provide flexibility for creating and customizing the Chart of Accounts to meet specific requirements, accounting frameworks, and standards, including taxonomies such as GAAP, IFRS (full), and IFRS for SMEs. This customization takes into account language variations and jurisdiction-specific considerations.

See - Generally Accepted Accounting Principles (GAAP) and International Financial Reporting Standards (IFRS)

- Universal chart of accounts is suitable for use with IFRS, US GAAP and other comparable accounting standards. https://www.ifrs-gaap.com/universal-chart-accounts
- IFRS® Sustainability Disclosure Standards around the world - https://www.ifrs.org/ifrs-sustainability-disclosure-standards-around-the-world/

Options to create and customise your own Set of Books:

- "Customise your own Set of Books (Advanced)?" (Firebird database) - Only includes 3 control accounts (Retained earnings / Debtors control and Creditors control). Using this option, the account descriptions is limited to 35 characters and 64 characters, depending of the number of digits you select. In addition to this, you need to update the "*TYPES*" table with Paper types and may need to add the Groups for Cost centre 1 / Cost centre 2 / Projects and Languages.
- CUSTOMISE-EMPTY-BOOKS (Pre-configured Firebird database) - Only includes 3 control accounts (Retained earnings / Debtors control and Creditors control). The field length for Account descriptions

and Groups description length is set to 128 characters. The "*TYPES*" table with Paper types and may need to add the Groups for Cost centre 1 / Cost centre 2 / Projects and Languages. The basic journals (such as Sales journal, Purchase journal and General journal) have been added and the basic settings for documents (such as Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders) is already set.

The basic Sets of Books created using this option will include the essential three main accounts: Debtor's Control, Creditor's Control, and Retained Earnings. The remaining Chart of Accounts can be fully customised according to your specific requirements. This flexibility enables you to tailor the Sets of Books to suit your unique accounting needs.

Comparison of description field lengths

"Customise your own Set of Books (Advanced)?"			*EMPTY-BOOKS (Pre-configured Firebird database)*		
Number of digits Account code	*Account description length*	*Groups description length*	*Number of digits Account code*	*Account description length*	*Groups description length*
3X3-DIGITS	*35*	*30*	*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS*	*128*	*128*
4X3-DIGITS	*35*	*30*	*CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS*	*128*	*128*
5X3-DIGITS	*35*	*30*	*CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS*	*128*	*128*
6X3-DIGITS	*64*	*30*	*CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS*	*128*	*128*
7X3-DIGITS	*64*	*30*	*CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS*	*128*	*128*
8X3-DIGITS	*64*	*30*	*CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS*	*128*	*128*

Document layout files and reports adjusted to accommodate the larger descriptions

All document layout files and reports, whether accessible through the osFinancials5.1 / TurboCASH5-2025 interface, documents, or on menus such as Reports and User Reports, have been meticulously adjusted

using the Report designer. These adjustments aim to prevent issues such as overlapping labels and untidy appearances, ensuring seamless accommodation of the maximum field length when users input their data.

You can find all these document layout files and reports in the " ...\plug_ins\reports\ " directory within the osFinancials5.1 / TurboCASH5-2025 installation folder.

Test databases

Firebird database - TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456.zip

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/blob/main/firebird-databases/TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456.zip

Tested text length to check and align reports where necessary

1234567890 1234567890 1234567890 1234567890 1234567890 1234567890 1234567890 1234567890 1234567890 1234567890 1234567890 123456

Also tested in MSSQL database type.

Description length increased and Added missing entries in the Types table

This is an Empty Set of Books created with the "*Customise your own Set of Books (Advanced)?*" option on the Creation wizard. The following Sets of Books only include the 3 control accounts (i.e. Debtors control + Creditors control + Retained earnings) accounts in the Chart of Accounts.

See - Designing a Chart of Accounts in this documentation.

Changed the number of characters in the Descriptions (Account description and Groups description) to 128 characters for the following books:

- CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS - Description Accounts =35 - GROUPS = 30 -
- CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS - Description Accounts =35 - GROUPS = 30 -
- CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS - Description Accounts =35 - GROUPS = 30 -
- CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS - Description Accounts =64 - GROUPS = 30 -
- CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS - Description Accounts =64 - GROUPS = 30 -
- CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS - Description Accounts =64 - GROUPS = 30 -

Descriptions - supports longer descriptions

Before adding your own accounts in the Chart of Accounts, you may edit the account codes to fit in the structure of your own Chart of Accounts.

- Accounts

- Ledger / Bank, Tax account types - 128 characters (Setup ® Accounts (Setup ribbon))
- Debtor (customer / client) accounts - 128 characters (Debtors (Default ribbon)) Debtor account codes - Prefix the first digit with a specific character e.g. 1 for debtors and use the remaining 6 digits in the case of a 4-digit main accounts Set of Books and up to 10-digit for an 8-digit main accounts Set of Books) for the rest of the account code.
- Creditor (supplier / vendor) accounts - 128 characters (Creditors (Default ribbon)) Creditor account codes - Prefix the first digit with a specific character e.g. 2 for creditors and use the remaining 6 digits in the case of a 4-digit main accounts Set of Books and up to 10-digit for an 8-digit main accounts Set of Books) for the rest of the account code.

· Stock (Inventory / Products) (Stock (Default ribbon))

- Stock code - 15 characters
- Stock description - 64 characters
- Stock extra description - 255 characters

· Groups - 128 characters (Setup ® Groups (Setup ribbon))

· Updated Types table

- Added Groups for Projects -1000, Cost centre 1 -1002, Cost centre 2 - 1003 and Languages - 1004.
- Added paper types - 55 - Till slip and 56 New plain paper types

groups.rep - set Wordwrap to true

Location: plug_ins\reports\GENERAL\documents

Changes to Firebird SQL files

Location: \bin\SQL\FIREBIRD

The Firebird SQL files pertinent to osFinancials5.1 / TurboCASH5-2025 are located in the " *…\bin\SQL\FIREBIRD* " directory.

To customize your own Set of Books using the "*Customise your own Set of Books (Advanced)?*" option for Firebird database types, you may need to edit the SQL files found in the " *…\bin\SQL\FIREBIRD* " directory within your osFinancials5.1 / TurboCASH5-2025 installation folder.

Before proceeding with any edits, it is strongly recommended to create a backup copy of these files on your system. This precautionary step ensures that you have a safeguard in case any issues arise during the

editing process.

The edited field lengths within these SQL files, particularly in the Accounts table and Groups table sections, dictate the required number of characters when creating your customized Firebird database for your Set of Books.

Specifically, the field lengths were adjusted in the following files located in the " *...\bin\SQL\FIREBIRD* " directory of your osFinancials5.1 / TurboCASH5-2025 installation folder:

- CreateDatabase.txt
- CreateDatabase_MILI.txt

CreateDatabase.txt

Account table

Changed to 128 - ,SDescription {chartype}(64)

```
CREATE TABLE Account(
WAccountID integer not null
,SAccountCode {chartype}(<@ACCOUNTCODE@>)
,SMainAccountCode {chartype}(<@MAINACCOUNTCODE@>)
,SSubAccountCode {chartype}(3)
,SDescription {chartype}(128)
,WAccountTypeID integer DEFAULT 0 not null
,WReportingGroup1ID integer DEFAULT 0 not null
,WReportingGroup2ID integer DEFAULT 0 not null
,BSubAccounts SmallInt DEFAULT 0 not null
,BIncomeExpense SmallInt DEFAULT 0 not null
,BOpenItem SmallInt DEFAULT 0
,BInActive SmallInt DEFAULT 0
,DSysDate {timestamptype}
,WProfileID integer
,WLinkAccount integer,
PRIMARY KEY (WAccountID));
```

Groups table

Changed to 128 ,SDescription {chartype}(30)

```
CREATE TABLE Groups(
WGroupID integer not null
,WGroupTypeID integer
,SDescription {chartype}(128)
,WParentGroup2ID integer
,WParentGroup1ID integer
,DSysDate {timestamptype}
,WSortNo integer,
primary key (WGroupID)
);
```

CreateDatabase_MILI.txt

Accounts table

changed from 35 ,SDescription varchAr(128)

```
CREATE TABLE Account(
WAccountID integer not null
,SAccountCode varchAr(<@ACCOUNTCODE@>)
,SMainAccountCode varchAr(<@MAINACCOUNTCODE@>)
,SSubAccountCode varchAr(3)
,SDescription varchAr(128)
,WAccountTypeID integer DEFAULT 0 not null
,WReportingGroup1ID integer DEFAULT 0 not null
,WReportingGroup2ID integer DEFAULT 0 not null
,BSubAccounts SmallInt DEFAULT 0 not null
,BIncomeExpense SmallInt DEFAULT 0 not null
,BOpenItem SmallInt DEFAULT 0
```

```
,BInActive  SmallInt DEFAULT 0

,DSysDate  {timestamptype}

,WProfileID  integer

,WLinkAccount  integer,

PRIMARY KEY  (WAccountID));
```

Groups table

Set description from 30 to 128

```
CREATE TABLE Groups(

WGroupID  integer not null

,WGroupTypeID  integer

,SDescription  varchAr(128)

,WParentGroup2ID  integer

,WParentGroup1ID  integer

,DSysDate  timestamp

,WSortNo  integer,

primary key (WGroupID)

);
```

Adjusting Field Lengths in Firebird Database Types of Existing Sets of Books

Always make sure to have a backup of your database before performing any structural changes to avoid data loss or corruption.

Always exercise caution and perform alterations during maintenance windows or low-impact periods to minimize disruptions.

Once you have created your Set of Books for the Firebird Database type using the "*Customise your own Set of Books (Advanced)?*" option or have an existing database for which you need to change field lengths, the 'ALTER TABLE' statement is crucial. It is important to make a backup of your Set of Books and possess sufficient knowledge and skills to handle table changes.

The broad basic process to adjust field lengths of tables in Firebird Database types is outlined

below:

In Firebird databases, altering the length of a field in a table involves using the ALTER TABLE statement. However, it's important to note that changing the field length can lead to potential data loss or corruption if not done carefully. Before proceeding, make sure to backup your database.

Assuming you want to change the description field length for the ACCOUNT table and the GROUPS table, here are the steps:

Changing Account Description Field Length:

sql

```
-- Backup your database before making any changes
BACKUP DATABASE TO 'your_backup_location';
-- Alter the table to modify the field length
ALTER TABLE ACCOUNT
  ALTER COLUMN description TYPE VARCHAR(128);
```

In the above example, assuming the original field type is VARCHAR, the length is set to 128. Adjust the type and length according to your requirements

Again, adjust the type and length as needed. Keep in mind that altering a column may fail if there are existing values in the column that would be truncated or cannot fit into the new length. It's essential to review the data in the table before making such changes.

Changing Groups Description Field Length:

sql

```
-- Backup your database before making any changes
BACKUP DATABASE TO 'your_backup_location';
-- Alter the table to modify the field length
ALTER TABLE GROUPS
  ALTER COLUMN description TYPE VARCHAR(128);
```

In the above example, assuming the original field type is VARCHAR, the length is set to 128. Adjust the type and length according to you.r requirements.

Remember that altering a column may fail if there are existing values in the column that would be truncated or cannot fit into the new length. It's essential to review the data in the table before making such

changes.

Always make sure to have a backup of your database before performing any structural changes to avoid data loss or corruption.

Adjusting Field Lengths in MSSQL Database Types of Existing Sets of Books

Always make sure to have a backup of your database before performing any structural changes to avoid data loss or corruption.

Always exercise caution and perform alterations during maintenance windows or low-impact periods to minimize disruptions.

In Microsoft SQL Server (MSSQL), you can change the length of a field in a table using the ALTER TABLE statement. Here's how you can change the description field length for the ACCOUNT table and the GROUPS table:

Changing Account Description Field Length:

sql

```
-- Backup your database before making any changes
BACKUP DATABASE YourDatabaseName TO DISK = 'your_backup_location';
-- Alter the table to modify the field length
ALTER TABLE ACCOUNT
  ALTER COLUMN description VARCHAR(128);
```

In the above example, assuming the original field type is VARCHAR, the length is set to 128. Adjust the type and length according to your requirements.

In the above example, I assumed the original field type is VARCHAR, and I set the length to 128. Adjust the type and length according to your requirements.

Changing Groups Description Field Length:

sql

```
-- Backup your database before making any changes
BACKUP DATABASE YourDatabaseName TO DISK = 'your_backup_location';
-- Alter the table to modify the field length
```

```
ALTER TABLE GROUPS

  ALTER COLUMN description VARCHAR(128);
```

In the above example, assuming the original field type is VARCHAR, the length is set to 128. Adjust the type and length according to your requirements.

In the above example, it is assumed the original field type is VARCHAR, and is set the length to 128. Adjust the type and length according to your requirements.

Again, adjust the type and length as needed.

Please note that altering a column may fail if there are existing values in the column that would be truncated or cannot fit into the new length. It's essential to review the data in the table before making such changes.

Examples of VAT accounts codes and longer descriptions to match the descriptions on VAT returns

The following examples of the "*Full Structure of VAT accounts and VAT-codes in the Chart of Accounts*" and the alignment to the relevant fields or boxes on VAT Returns or VAT-declarations is available in this documentation:

Generic Sets of Books - 4-Digit Chart of Accounts

- 4-EN-SOUTH-AFRICA-GENERIC - Value Added Tax (VAT) - South Africa - The "Full Structure of VAT accounts in the Chart of Accounts and the VAT Return" The stricture South African VAT-accounts and VAT-codes of the Chart of Accounts is aligned with the VAT201-return.



- 4-AF-SUID-AFRIKA-GENERIES - Belasting op toegevoegde waarde (BTW) Suid-Afrika (Afrikaans) - Refer to the Afrikaans documentation. The "Full Structure of VAT accounts in the Chart of Accounts and the VAT Return" The stricture South African VAT-accounts and VAT-codes of the Chart of Accounts is

aligned with the VAT201-return.



- 4-EN-UK-GENERIC - Value Added Tax (VAT) - United Kingdom - Various schemes for VAT may be applicable for various scenarios. The most commonly used VAT Standard rate scheme is documented as an example of the VAT-account and VAT-codes structure in Chart of Accounts for the United Kingdom (UK) to match the various Boxes on the UK VAT return. "VAT Standard Rate Scheme - Structure of VAT Accounts in the Chart of Accounts"



Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Customise Empty Books

CUSTOMISE-BOOKS-ADVANCED

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/CUSTOMISE-BOOKS-ADVANCED

The Sets of Books for the Firebird Database type now supports larger field lengths for data entry, catering

to the specific requirements of larger businesses or organizations. This enhancement allows for more detailed and comprehensive data management, particularly in scenarios where extensive account codes and descriptions are necessary.

The following Sets of Books is created using the "*Creation wizard*" (F10) from the Create Set of Books (Start ribbon) the "*Customise your own Set of Books (Advanced)?*" option for Firebird database type:

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/CUSTOMISE-BOOKS-ADVANCED

- *CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS.zip*
- *CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS.zip*

osFinancials Field length - Shop - Payment per request - In addition to these options, you may shop for customised field lengths.

Translate the "*CUSTOMISE-EMPTY-BOOKS*" template

To work in the language of your choice, after you have use the Browse button on the Open Set of Books. Navigate to the bin/CUSTOMISE-EMPTY-BOOKS folder. Select from 3-digits to 8-digits main accounts templates of your choice and click Open.

Basic Steps to customise or translate your Set of Books, based on one of the "*CUSTOMISE-EMPTY-BOOKS*" templates into the language of your choice:

1. Open the Set Books ("*CUSTOMISE-EMPTY-BOOKS*" template).
2. Save the Set of Books with a name of your choice. To do this go to the Save as option on the Start ribbon and enter a unique name for your Set Books.
3. Select language of your choice in the Switch language option (Start ribbon). If you have selected language of your choice, your Set of Books will automatically open in your selected language.
4. The customisation or translation is basic simple actions:
    - Translate the descriptions of records in the *'Types'* tab of Tools → Customize language (Setup ribbon). This will include, document types available in "*English*" language, (i.e. "*Invoice, Credit note, Quote, Purchase, Supplier return*" and "*Order*"). You can customise or translate it into your selected language or customise the document types for your specific language, industry or according to your unique needs.

- This will also include the Reporting groups' group descriptions, e.g. "Account Group1" to "Account Group 1", etc. in Setup → Groups, (Setup ribbon) update.
- Translate the three control accounts i.e. "*Debtors control*, *Creditors control*" and "*Retained earnings*" In the Setup → Accounts (Setup ribbon).

Your basic Set of Books has been customised and translated, and you can take the rest of the actions such as creating or importing your General ledgers accounts, Debtor accounts, Creditor accounts and Stock items (Inventory items or Products).

Sets of Books created on these templates

4-Digit main accounts and 3-Digit sub-accounts

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/4-DIGIT-BOOKS

The following Sets of Books, based on the "*CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS.zip*" (with a 4-digit main accounts and 3 digit sub-accounts) were created:

- 4-EN-SOUTH-AFRICA-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes, aligned with the VAT201-return.
- 4-AF-SUID-AFRIKA-GENERIES.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts in Afrikaans. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes (Belasting op Toegevoegde Waarde (BTW) Suid-Afrika (Afrikaans), aligned with the VAT201-return.
- 4-EN-UK-GENERIC.zip: This generic Set of Books includes 4-digit main account and 3-digit sub-accounts, based on the United Kingdom (UK) Chart of Accounts. It incorporates specific UK terminology and includes Value Added Tax (VAT) - United Kingdom accounts based on the VAT Standard rate scheme. The VAT-account and VAT-codes structure in the Chart of Accounts is designed to match the various boxes on the UK VAT return. NOTE: Various schemes for VAT may be applicable for various scenarios.

3-Digit main accounts and 3-Digit sub-accounts

The TUTORIALS Sets of Books, based on the "*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS*" (with a 3-digit main accounts and 3 digit sub-accounts) were created for ENGLISH and AFRIKAANS.

TUTORIALS/ENGLISH/

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS/ENGLISH

1. Sets of Books
    - HANDYMAN - Starting with the "*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*" template, the HANDYMAN Set of Books contains only the 3 basic control accounts (Debtors control, Creditors control and Retained earnings accounts). The ledger accounts (chart of accounts), debtor accounts, creditor accounts and stock items were imported using the "*(*.txt) Tab delimited*" files (exported from older HANDYMAN tutorials).
    - HANDYMAN-A - UNPOSTED batch transactions and UNPOSTED documents.
    - HANDYMAN-B - POSTED batch transactions and POSTED documents.
2. Supporting files
    - EXPORTED-ACCOUNTS-STOCK folder - The following data imported in the Import option on the Setup ribbon using the "*(*.txt) Tab delimited*" files (i.e. "*Export-ACCOUNTS, Export-DEBTORS, Export-CREDITORS*" and "*Export-STOCK*") created from the Export option on the Setup ribbon in older Tutorials Set of Books.
    - EXPORTED-BATCH-Delimited-File folder - The batch transactions was imported using the files in this folder using the "*Delimited file import*" Batch processing option.
    - EXPORTED-BATCH-Spreadsheets folder - You can also use the Excel workbook files to import batch transactions Spreadsheet import icon on the Batch entry screen to open the Excel workbook (*xlsx) file and import the batch transactions into the respective batches.
3. Documentation - Accounting Made Easy - 2024-osF-5-1-AME-Revision1.odt (Book created in LibreOffice in English). Since basically all reports have been tidied and fixed to minimise overlapping labels to accommodate data to full size of allowed fields and to accommodate larger descriptions that may be required for Sets of Books with up to 8-digit main accounts these reports have been retested in English and in Afrikaans.

TUTORIALS/AFRIKAANS

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/firebird-databases/TUTORIALS/AFRIKAANS

1. Sets of Books (Handleidings)
    - NUTSMAN - Starting with the "*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*" template, the

NUTSMAN Set of Books contains only the 3 basic control accounts (Debtors control, Creditors control and Retained earnings accounts. Starting with the "*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS.zip*" template, the HANDYMAN Set of Books contains only the 3 basic control accounts (Debtors control, Creditors control and Retained earnings accounts). The ledger accounts (chart of accounts), debtor accounts, creditor accounts and stock items were imported using the "*(*.txt) Tab delimited*" files (exported from older HANDYMAN tutorials).

- NUTSMAN-A - UNPOSTED batch transactions and UNPOSTED documents.
- NUTSMAN-B - POSTED batch transactions and POSTED documents.

2. Supporting files
   - UITVOER-REKENINGE-VOORRAAD folder - The following data imported in the Import option on the Setup ribbon using the "*(*.txt) Tab delimited*" files (i.e. "*Debiteure.txt, Krediteure.txt , Rekeninge.txt*" en "*Voorraad.txt*") created from the Export option on the Setup ribbon in other Tutorials Set of Books.
   - JOERNAAL-GEDELIMITEERDE-UITVOER folder - The batch transactions was imported using the files in this folder using the "*Delimited file import*" Batch processing option.
   - JOERNAAL-SIGBLAD-UITVOER folder - You can also use the Excel workbook files to import batch transactions Spreadsheet import icon on the Batch entry screen to open the Excel workbook (*xlsx) file and import the batch transactions into the respective batches.
3. Documentation - Rekeningkunde Met Gemak - 2024-osF-5-1-RMG-AFRIKAANS-Weergawe1.odt - (Book created in LibreOffice in Afrikaans). Since basically all reports have been tidied and fixed to minimise overlapping labels to accommodate data to full size of allowed fields and to accommodate larger descriptions that may be required for Sets of Books with up to 8-digit main accounts these reports have been retested in English and in Afrikaans.

CUSTOMISE-EMPTY-BOOKS - Sets of Books properties

The basic properties of these "*CUSTOMISE-EMPTY-BOOKS*", is as follows:

1. Field length - Set maximum Account and Group descriptions to 128-characters.
2. Account codes - Character length and the default control accounts. Depending on your choice of "*CUSTOMISE-EMPTY-BOOKS*"-template for the number of digits, the number of digits for the control accounts and the debtor accounts as well as the creditor accounts will be as follows:

Number of digits	*Books name*	*Retained earnings*	*Debtors control*	*Creditors control*	*Number of account code*	*Number of account code*

Account code					*digits - Debtor accounts*	*digits - Creditor accounts*
3X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS*	*G510-000*	*G700-000*	*G900-000*	*D + 5-characters D00001*	*C + 5-characters C00000*
4X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS*	*G3100-000*	*G1100-000*	*G2000-000*	*D + 6-characters D000001*	*C + 6-characters C000000*
5X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS*	*G31000-000*	*G11000-000*	*G20000-000*	*D + 7-characters D0000001*	*C+ 7-characters C0000000*
6X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS*	*G310000-000*	*G110000-000*	*G200000-000*	*D + 8-characters D00000001*	*C + 8-characters C00000000*
7X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS*	*G3100000-000*	*G1100000-000*	*G2000000-000*	*D + 9-characters D000000001*	*C + 9-characters - C000000000*
8X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS*	*G31000000-000*	*G11000000-000*	*G20000000-000*	*D + 10-characters - D0000000001*	*C + 10-characters - C0000000000*

3. ADDED / FIXED - Updated TYPES table Groups and Paper types:
    - Groups Added records - for Type 2 in the WTYPEPARENT column:
        - 1000 - Projects
        - 1002 - Cost centre 1
        - 1003 - Cost centre 2
        - 1004 - Languages
    - Add Paper types - Added records - for Type 5 in the WTYPEPARENT column:
        - 55 - Till slip
        - 56 - New plain

4. TYPES table - Edited the descriptions of records in the Types tab of Tools → Customise language (Setup ribbon) such as document types (i.e. Invoice, Credit note, Quote, Purchase, Supplier return and Order), groups names, etc. This is consistent with other templates (Sets of Books that can be downloaded). When you overtype the group name descriptions e.g. "*Account Reporting Group1 Name*" to "*Account group 1*", etc. in Setup → Groups, it will update the record's description in the Types tab of the "*Customize languages*" screen.

5. Documents setup - Layout file point-of-sale: "*DefaultA4*" is the default setting and is not available in the " *...\plug_ins\reports\DOCUMENTS\DOCUMENTS* " folder- changed the default layout file to "*POS - STARTSP100*".

6. Calendar resource - The default Resource name is set to osFinancials5/TurboCASH5. The resource name links the events, tasks, etc. to a specific name in the Calendar. It will also print on the Calendar report. When you purchase and activate the *Multi-User calendar (agenda)* plugin, you will be able to define a resource for each user.

CUSTOMISE-EMPTY-BOOKS - Sets of Books - Accounts

The basic properties of these "*CUSTOMISE-EMPTY-BOOKS*", is as follows:

Ledger accounts

Accounts Setup → Accounts - Only the 3 control accounts (i.e. Debtors control + Creditors control + Retained earnings) accounts in the Chart of Accounts is included in the Chart of Accounts.

NOTE : You cannot delete these 3 control accounts. An error message will be displayed:

> "You cannot delete a control account!"

You can edit the account code and description for each of these 3 control accounts.

Depending on your choice of "*CUSTOMISE-EMPTY-BOOKS*"-template for the number of digits, the number of digits for the control accounts will be as follows:

Number of digits	*Books name*	*Retained earnings*	*Debtors control*	*Creditors control*
Account code				
3X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS*	*G510-000*	*G700-000*	*G900-000*
4X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-4X3-*	*G3100-000*	*G1100-000*	*G2000-000*

	DIGITS			
5X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS*	*G31000-000*	*G11000-000*	*G20000-000*
6X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS*	*G310000-000*	*G110000-000*	*G200000-000*
7X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS*	*G3100000-000*	*G1100000-000*	*G2000000-000*
8X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS*	*G31000000-000*	*G11000000-000*	*G20000000-000*

Control accounts - You can edit the account code and account description for each of these 3 control accounts. It is important to note that you need to keep in mind that these control accounts need to be linked to account groups and financial categories:

Control account name	*Financial category*	*Account groups*
Retained earnings	*Capital*	*Equity / Capital*
Debtors control	*Assets*	*Current assets*
Creditors control	*Liabilities*	*Current liabilities*

If you import general ledger accounts from a Tab delimited file, you may:

- Change the account codes and descriptions to meet your specific requirements and needs. In the case of accounts, which contains sub-accounts, you cannot change the sub-accounts account codes. You first need to delete the sub-accounts and rename the account codes and account descriptions and recreate sub-accounts where necessary.
- Review your imported ledger accounts descriptions. You may use longer account descriptions (longer than the default 35-characters or 64-characters) , where necessary.
- Disabled (inactive) accounts imported - review and decide to keep these disabled (inactive) accounts or delete them if not required.
- Tax (VAT/GST/Sales tax) accounts - The first sub-account (tax code) may not include the Tax tab and Tax percentage - You need to delete and recreate the tax account (tax code) as a Tax account. Zero-rated Tax codes. You need to confirm the percentage.

- If Account groups 1 and / or Account group 2 is imported, these account groups may not be linked to the 5 financial categories. You may need to link these account groups to the five financial categories.

Imported or copied text in osFinancials5/TurboCASH5 screens from external files - Account / Group descriptions in Accounts description lines in batches

When importing or copying text for account. group descriptions or any other screens, or forms, the fields from external programs such as spreadsheet, word documents, etc. the hyphenation character "–" may be displayed as a pipe character " | " in lookups and some screens or as " " in some screens and in reports, document layout files, etc.

For example, Motor vehicles Net value if copied or imported into Setup - Accounts as Motor vehicles – Net value (with the hyphenation format) it will be displayed as Motor vehicles Net value on some screens and in reports and as Motor vehicles | Net value on lookup screens.

You need to use the dash sign "-" to be displayed correctly.

Solution:

To ensure hyphens display correctly in osFinancials5/TurboCASH5, use the standard dash character ("-") instead of the hyphenation character when copying or importing text from external files.

Debtor / Creditor accounts

Depending on your choice of "*CUSTOMISE-EMPTY-BOOKS*"-template for the number of digits, the number of digits for the control accounts and the debtor accounts as well as the creditor accounts will be as follows:

Number of digits *Account code*	*Books name*	*Number of account code digits - Debtor accounts*	*Number of account code digits - Creditor accounts*
3X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS*	*D + 5-characters* *D00001*	*C + 5-characters* *C00000*
4X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS*	*D + 6-characters* *D000001*	*C + 6-characters* *C000000*
5X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS*	*D + 7-characters* *D0000001*	*C+ 7-characters* *C0000000*
6X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS*	*D + 8-characters* *D00000001*	*C + 8-characters* *C00000000*

7X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS*	*D + 9-characters D000000001*	*C + 9-characters - C000000000*
8X3-DIGITS	*CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS*	*D + 10-characters - D0000000001*	*C + 10-characters - C0000000000*

When creating or adding Debtor accounts and Creditor accounts, it is important that you use a different prefix for the account codes:

The first Debtor code (e.g. D00001, etc.), will automatically be generated. It is important to prefix Debtor codes with a unique prefix. In this documentation, the accounts is prefixed as follows:

- *Debtor code = 1*
- *Creditor code = 2*

The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens on "Batch entry" screens.

CUSTOMISE-EMPTY-BOOKS - Sets of Books configuration

Language settings

The language specific settings is as follows:

Language - "*English*" is the default language. You may select your language and country in Switch language (Start ribbon).

Set the default language for your Set of Books - You may select your language and country in Setup → Access control. When reopening your Set of Books, the language will be displayed in the osFinancial interface, reports, etc.

- Customise language - "*English*" is a default language. If you wish to customise your own language, you may select a different available language for your country language, tax regime or industry. Tools → Customise language (Setup ribbon).

  If you decide to customise your own language, and wish to edit these labels, it is important that you use a copy of the available language files. This will prevent overwriting your language file when you install osFinancials5/TurboCASH5 updates.

- Types tab - The entries on this tab is database specific and will update the "*TYPES*" table in your Set of

Books. You may edit, translate or change the descriptions as necessary.

- Reporting groups - The default descriptions for the 16 reporting groups - Setup → Groups is "Account group 1, Account group 2, Debtor group 1, Debtor group 2, Creditor group 1, Creditor group 2, Stock group 1, Stock group 2, Document group 1, Document group 2, Payment types, Salespersons, Projects, Cost centre 1, Cost centre 2 and Languages". These descriptions may be changed, edited, translated in the Types tab.
- Document types - The default descriptions for the standard 6 document types for sales documents (Invoices, Credit notes and Quotes and for purchase documents (Purchases, Supplier returns and Orders). These descriptions may be changed, edited, translated for your country language, tax regime or industry in the Types tab. In your language file, you may search and edit / translate the language labels for each of these document types.
- Tax terminology - Tax account is the default description for VAT/GST/Sales tax/Consumption tax in the Types tab. You may change this description for your country language, tax regime or industry. In your language file, you may search and edit / translate the language labels for the for the tax terminology.

· Rest tab - The entries on this tab is database specific. The Customize language - Rest tab Change descriptions of the "*Description of Zero account*" and "*Group empty account*". The 2 change buttons only saves 1 description. Work around change both to "*Empty*".

Company info

Company info - Depending on your selection of the CUSTOMISE-EMPTY-BOOKS number of digits, the similar text will display in the Titlebar and in reports e.g. "*3x3-DIGIT CUSTOMISE EMPTY BOOKS*", etc. Enter the name contact details and registration numbers of your business in Setup → Company info.

Financial year and accounting periods

Reporting dates - The default start of the financial year is "*1 January 2024*" - You may change this in Setup → Reporting dates control for the start of your financial year and set the accounting periods.

The default is the "*English*" months of the year - If have you selected a different language, you need to translate the months of your financial year.

Batches / Journal types

Batches / Journal types - Setup → Batch types the General journal, Sales journal and Purchase journal is added.

No Receipts and Payments batches for Bank accounts and Petty cash accounts is added.

When you add or create your own accounts, the Payments and Receipt batches will be created and added and linked to each Bank account and Petty cash account.

You may add any additional batch types (journal types) to accommodate your specific needs and requirements.

Documents setup

The defaults settings in the Setup → Documents setup is as follows:

1. Global settings - Documents setup
    - Layout file point-of-sale : "*DefaultA4*" is the default setting and is not available in the "*...\plug_ins\reports\DOCUMENTS\DOCUMENTS*" folder- changed the default layout file to "*POS - STARTSP100*".
    - Append notes below item: By default this option is selected. The default sequence in which the document lines will be displayed on document entry forms and printed in document layout files, is Item/Remark/Comment. If you deselect this option, the sequence in which the document lines will be displayed on document entry forms and printed in document layout files, will be Comment, Item, Remark.
    - Auto-post documents on print: By default this option is not selected. This means that you need to manually launch the Update ledger option to post or update documents to the ledger.
2. Settings for specific document types. The basic configuration for each document type, is as follows:

Field	*Sales documents*			*Purchase documents*			
Document type	*Invoice*	*Credit note*	*Quote*	*Purchase*	*Purchase returns*	*Orders*	
Next Document number	*IN000001*	*CR000001*	*QU000001*	*PU000001*	*SR000001*	*OR000001*	*This is an 8-character alpha-numeric field. You may use prefixes for each document type. Prefixes will make it easier to identify the document type in search and filters, on reports and on exported data in spreadsheets.*

Batch type	*Sales jnl*	*Sales jnl*	*Not applicable*	*Purchase journal*	*Purchase journal*	*Not applicable*	*The default batch (journal) type in which the documents will be updated to the ledger. You may rename these journals or set a different journal.* *Batches (Journals) is not applicable to Quotes and Orders.*
Layout file	*Layout file*	*Layout file*	*Layout file*	*Layout file*	*Layout file*	*Layout file*	*The Layout file is one standard generic layout file applicable to all document types (Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders) and is translated via the language files. This is a global setting. Custom or other layout files may be set as default for specific debtor or creditor accounts.*
Layout file 2	-	-	-	-	-	-	*This option is not selected. You may select other layout files or the delivery note to print after the Layout file.*
Heading	*Tax Invoice no.*	*Credit note no.*	*Quote no.*	*Purchase no.*	*Supplier return no.*	*Order no.*	*You may change the headings of each document headings to match your country language, tax regime or industry.*
Message 1/2/3	-	-	-	-	-	-	*Messages is left blank. You may enter up to 3 lines as a global message that will be displayed on the "Messages" field of the document entry screens and printed on document layout files for each document type. Custom messages may be set as default for specific debtor or creditor accounts.*

Statement message - You may enter global standard message for Debtor statements to print on Debtor statements.

Post / Confirm and Delete buttons on Documents grid - By default, only the New, Edit and Print buttons are available on the Documents grid screen's sidebar. You may add the Posting and Delete buttons underneath the Print button. To add the Posting and Delete buttons to the Document grid screen, select (tick) the "*Document posting*" field on the Documents tab in Setup → Access control.

Stock items / Inventory items

Before you add or import your stock items / inventory items / products you may need to configure some important basic settings such as Cost of sales, Create tax classes / account classes and Selling prices.

At this point, your chart of accounts (general ledger accounts) should have already been finalised.

Activate Cost of Sales

By default cost of sales is not activated. You need to configure cost of sales as follows:

1. Cost of Sales journal - Create a cost of sales batch (journal) type (Setup → Batch types) to update the transactions for cost of sales to the ledger when you post documents.
2. Cost of sales settings (Setup → Stock information) - Select the following:
    - Create cost of sales - To activate cost of sales, select (tick) the "*Create cost of sales*" tick box.
    - Cost of sales batch - Select the Cost of sales batch (journal) in which the cost of sales transactions will be posted.
    - Use "*Average cost*" or "*Latest cost*" option.

The method you use to calculate the value of your stock is crucial for determining its impact on your profit and loss figures. It is important to consider whether to use the "average cost" or the "latest cost" method.

If you are unsure which method to use, it is recommended that you seek guidance from your accountant.

Create tax classes / account classes

At this point, your chart of accounts (general ledger accounts) should have already been finalised.

You need to link each stock item / inventory item / product to the applicable ledger accounts (i.e. Input tax, Output tax, Sales account, Cost of sales account and Stock control account).

Tax classes may be set and linked to each category of tax and various tax rates such as Output tax, Input tax - Standard rate, Input tax - Capital goods, Zero rated goods, Exempt supplies applicable to the stock items / inventory items / products in your country and tax jurisdiction, etc.

Tax classes is defined and managed in the Tax classes tab in Setup → Stock information. When you create add or import your stock items / inventory items / products you may select a pre-configured Tax class to automatically link the 5 accounts (i.e. Input tax, Output tax, Sales account, Cost of sales account and Stock control account) applicable to the stock item / inventory item / product.

Selling prices

osFinancials5/TurboCASH5 supports up to 3 selling prices (i.e. Selling price 1, Selling price 2 and Selling price 3). You may change the descriptions of these selling prices on the "Selling price descriptions" section of the Default tab of Setup → Stock information to suit your specific requirements and set one of these Selling prices as the default Selling price (global setting) for your Set of Books.

In addition to this, you may set one of these Selling prices as the default Selling price on the Accounting information tab for specific debtor (customer / client) accounts.

Price agreement plugin - Manual - Shop - Licence : Once-off -

In addition to the standard 3 selling prices in odFinancials, Price agreement plugin, allows you to set up to five (5) levels of quantity discounts that can be applied to specific debtors or groups of debtors. Additionally, you can set a special price for individual debtors per product. These prices will overrule the default Selling price 1 / 2 / 3 and can be set per debtor (customer / client). The price agreement may also be activated for creditor (supplier / vendor) accounts.

Units of stock

Add and define the units such as each, hours, etc. for your stock items / inventory / products. You may add these descriptions on the Units tab in Setup → Stock information.

Reporting groups - Stock group 1 / Stock group 2

In osFinancials5/TurboCASH5, you have the option to set up to 2 reporting groups for your stock items / inventory items / products, allowing you to categorise search, filter and report on your products more effectively. These reporting groups provide a way to organize and analyse your inventory based on specific criteria.

You may add these Stock groups in Setup → Groups can be linked to each stock item (inventory item / product).

Set the Calendar as default

You have the option to activate the Calendar to be launched instead of the Welcome screen whenever you open a Set of Books, This means that the Calendar will be automatically displayed as the default screen.

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

Calendar - Contacts - Add resource name

Calendar - Add resource name. When accessing the Contacts in the Calendar for the first time in the *"CUSTOMISE-EMPTY-BOOKS*", (or using the Customise your own Set of Books (Advanced)? option (for Firebird database type or the MSSQL database type), no contacts will be listed.

To add the existing contacts:

Right-click on the Contacts and select "*Add contact...*" on the context menu.



A confirmation message will be displayed:

> No resource have been defined! Would you like to add one now?

Click Yes to add a resource.



On the "Select a Resource" screen, Click Add New Resource. Selecting and editing an existing resource from the list will not add the contacts.

Enter a new resource name the contacts will be listed. When adding the new resource name, somewhere the Calendar appointments will be blank.

Deleting the new resource name for Contacts in "RESOURCES" table (SQL Browser) and exit osFinancials and reopen the Set of Books, the Calendar appointments will be listed. and the Contacts will be empty again.



Created with the Standard Edition of HelpNDoc: Free help authoring tool

FIXED - Access violations (osF5.1.0.100)

Access violations

Ledger analyser

Fixed in osF5.1.0.100

> Access violation at address 091DD72F in module 'osfresource.bpl'. Read of address 00000040

Replicated with the + / - zoom buttons in Trial Balance

> Access violation at address 091DD72F in module 'osfresource.bpl'. Read of address 00000040

> Access violation at address 66E66593 in module 'osfresource.bpl'. Read of address 00000040

Setup Groups

> Access violation at address 50D3B6B2 in module 'vcl280.bpl'. Read of address FEA0274F

Created with the Standard Edition of HelpNDoc: Easily share your documentation with the world through a beautiful website

FIXED - Missing Configuration Files - Full install - (osF5.1.0.16)

FIXED - Full clean install 25 June 2022 Missing Configuration Files

Configuration file missing: - C:\osfinancials5\dbxdrivers.ini

Accessing Database Connections and Datasets

Added - dbxdrivers.ini and dbxconnections.ini to root directory of new osFinancials installation.

Configuration file missing: - C:\osfinancials5\dbxdrivers.ini

Accessing Database Connections and Datasets on a full clean install - in Reportman - copied these to files from older installation into the root directory of clean full install of osfinancials - then it works

---

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Intuitive Interface

FIXED - Password change (osF5.1.0.16)

Password change

osFinancials5.1.0.16 - Change password - Cannot open Set of Books

After changing the Set of Books Password (Access control) in osFinancials5.1.0.16 - Illegal password - Open Set of Books

To access open the Set of Books, I used FlameRobin to Delete the password





Only then on the login screen with only username and no password I can access (open) the Set of Books

In osFinancials5 - 453 can change the password works 100%

Also when copy the Set of Books to the osFinancials5 / books directory (osFinancials5.1.0.16) and open the Set of Books open the new password changed in osFinancials5 - (453) is used to open a Set of Books

---

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

FIXED - Documents - Debtor / Creditor Lookup

Create new Document - Select Debtor / Creditor

When creating a New sales document (e.g. Invoice, Credit note or Quote), the Debtor accounts screen list the last line. You need to use the scroll bar to view the search filter options to find an account.

Similarly when created a New purchase document (i.e. Purchase, Supplier return or Order), the Creditor accounts screen list the last line. You need to use the scroll bar to view the search filter options to find an account.



To use the filter options you need to scroll up



FIX for Debtor accounts / Creditor accounts lookup when creating documents

It also fixed the Debtor / Creditor accounts lookup when creating documents in osFinancials5-453 osFinancials4.0.0.1093

Deleting the HKEY_CURRENT_USER\SOFTWARE\osfinancials

To Delete the HKEY_CURRENT_USER\SOFTWARE\osfinancials in Windows Registry:

1. Close osFinancials5/TurboCASH5.
2. Right-click on the Start icon of your Windows operating system and select "*Run*".



3. Click OK to open the "*Registry editor*". Your system may ask for permissions and click Yes.



4. Navigate to the "HKEY_CURRENT_USER\SOFTWARE\osfinancials" key.

5. On "*osfinancials*" key right-click and select Delete on the context menu.

6. A "*Confirm Key Delete*" message will be displayed:

> Are you sure you want to permanently delete this key and all of its subkeys?

7. Make absolutely sure that the correct entry is selected and click Yes.

8. Close the "*Registry Editor*" and launch osFinancials5/TurboCASH5. It will create a new key and subkeys. The Debtor accounts / Creditor accounts lookup will display correctly when when creating new documents.



Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

FIXED - F8:Discount - Documents

F8:Discount icon. The "*Enter overall discount*" does not change discount in all lines - need to enter them manually on next lines



Normal percentage

Subtracts from selling price

Invoice: IN000035			Date:	2022/05/01	Account no.:		D1MDAVI
Description	Unit	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inclusive
Drill press	Each	1	1,150.00	10.00%	900.00	15.00%	135.00	1,035.00
	Total				900.00		135.00	1,035.00

Negative percentage

Adds to selling price

Invoice: IN000035			Date:	2022/05/01	Account no.:		D1MDAVI
Description	Unit	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inclusive
Drill press	Each	1	1,000.00	-10.00%	1,100.00	15.00%	165.00	1,265.00
	Total				1,100.00		165.00	1,265.00

Negative discount percentages is not allowed. In osFinancials5 (443); if a negative discount percentage is entered; an error message is displayed:

> Invalid discount! Amount must be positive!

In previous versions (earlier than osFinancials5 (443), - it will cause problems in transactions and on layout files.

Invoice: IN000023			Date:	2021/07/30	Account no.:		D1ABGRE
Description	Unit	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inclusive
Drill press	Each	1	1,000.00	-10.00%	1,000.00	15.00%	150.00	1,150.00
Compressor	Each	1	1,500.00		1,500.00	15.00%	225.00	1,725.00
	Total				2,500.00		375.00	2,875.00

Created with the Standard Edition of HelpNDoc: Easily create EPub books

FIXED - Bank recon - Last total

Bank recon Last total

Bank recon Last total was always showing the payment and receipt batches of the first account reconciled.

When doing a bank recon on a second or different account the first bank accounts last total is displayed and printing the recon.rep it always printed the incorrect total of the first bank account. The recon.rep was then always not balancing.

Some technical code

"it should be in that table

```
OPREPORT with bankid then BankBal dbedtBankBal.Value :=
StrToFloat(StringReplace(ReadReportOp((VarToStr(DBLBanks.EditValue)) + 'BankBal', 0).AsString, '.',
FormatSettings.DecimalSeparator, [rfReplaceAll]));
```

```
LCurBalance.Value := TDataBaseRoutines.GetBalans(StrToIntDef(VarToStr(DBLBanks.EditValue), 0),
StrToDateDef(dbdtUntilDate.Text, 0))
```

====

on exit this code executes if DBLBanks.ItemIndex <> -1 then

```
writeReportOp(intToStr(DBLBanks.EditValue) + 'BankBal', StringReplace(FloatToStr(dbedtBankBal.Value),
FormatSettings.DecimalSeparator, '.', [rfReplaceAll]));
```

"

Report changed it is outdated with TurboCASH5.2 / osFinancials5 code.

- the recon.rep report ok but the totals on the recon-options - Also replicate the totals of the incorrect Bank account using the BankImportPlugin - same as with the Default Bank method

Initially the Last total is displayed incorrectly but after the second time printing the recon it is correct on screen the Last total is updated



Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

FIXED - Bank recon options - label

Resolved in osFinancials 5.1.0.189

Cash/Bank entry (Default ribbon) - Bank account label changes to "read 21" / "read 58" / "read 61" When selecting a bank account from the list = looks like the Id of the bank account name.

It is replicated irrespective of the selection on the "*Default bank reconciliation method*" option on Setup → System parameters menu:

- Selected - Bank import plugin not activated
- Not selected - Bank import plugin activated


Bank account recon options
read 21
ABC - Bank
Include items until
2023/11/28
Last total
8,423.00
Bank balance
8,998.00
Reference
Description
Date
Number
Cum
******** Bank charges - Bank statement no.5 2023/03/31 45.00- 8,423.00
******** Payment on account 2023/03/30 750.00- 8,468.00
******** Petrol - Mercedez Benz 2023/03/30 150.00- 9,218.00
******** Waltons - Paper and pens 2023/03/30 230.00- 9,368.00
******** Rent - April 2023/03/30 575.00- 9,598.00
******** Petty cash - Increase float 2023/03/30 100.00- 10,173.00
******** Payment received - Thank you 2023/03/16 1,000.00 10,273.00
******** Payment received - Thank you 2023/03/16 2,000.00 9,273.00
******** 1 x Desk 2023/03/01 575.00- 7,273.00
******** 2 x Chairs 2023/03/01 345.00- 7,848.00
******** Cash received from owner 2023/03/01 5,000.00 8,193.00
JNL1 Opening balance - Take-on 2023/02/28 3,193.00 3,193.00
Open
Close


Bank account recon options
read 21
ABC - Bank
Last total
0.00
Bank balance
8,998.00
Reference
Description
Date
Number
Cum
<No data to display>
Open
Close



Created with the Standard Edition of HelpNDoc: How to Protect Your PDFs with Encryption and Passwords

FIXED - Unicode setting - Currencies - Default setting

Setup currencies

FIXED - osFinancials5.1.0.233 install / TurboCASH5-3 Install allows you to select to enable or disable Unicode settings.

Replicated in osF5.1.100 since osFinancials5.1.0.16 displayed incorrectly, since unicode was introduced.

To use Currencies in osFinancials5 you need to change the osf.ini file

Only works correctly if " ;nounicode=true " is uncommented or set to false nounicode=false in the osf.ini file.

If the default setting " nounicode=true " is not uncommented in the osf.ini file, this replicate the error not displaying correctly.

Default setting " nounicode=true " in the osf.ini file, this replicate the error not displaying correctly



See - Alt Code Shortcuts for Currency Symbols - List of Alt+Numeric keys for generating theCurrencies in the various countries. Example Works if the Alt+0165 for Yen, etc.

To display currencies correctly in Currencies setup and print the Currency report correctly in you need to change the osf.ini file.

" ;nounicode=true " setting to uncomment it or set it to false nounicode=false in the osf.ini file

After changing it back to the default setting " nounicode=true " is not uncommented in the osf.ini file, The error is not replicated and is displayed correctly correctly in Setup → Currencies and Reports → Currencies report or on document layout files.



Layout file incorrect

If the default setting " nounicode=true " is not uncommented in the osf.ini file, this replicate the error not displaying correctly.



Layout file correct

Only works correctly if " ;nounicode=true " is uncommented or set to false nounicode=false in the osf.ini

file.



Was correct in osFinancials5 (Build 453)

See

https://www.osfinancials.org/htmlhelp_eng/multi-currency-documents.html

https://www.osfinancials.org/htmlhelp_eng/multi-currency-documents.html

Euro and Pound symbol displaying incorrectly = osFinancials5.1.0.16



Currencies - Report prints incorrectly



Layout file also prints currency symbol incorrectly



Last version was displaying correctly = osFinancials5 (Build 453)



Currencies - Report prints correctly

Layout file also prints currency symbol correctly



Could not update or confirm Reporting dates (Setup menu) produce errors - In some Firebird databases

Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

Known issues

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Known issues - Clear/Reset

Clear/reset a Set of Books - Budget figures not cleared

Clears all transactions an documents/stock, if selected.

- Budget totals is not cleared. Existing Budget figures still available - Budgets (Reports ribbon) and Setup -> Accounts (Budget tab)
  After Clear/reset a Set of Books you can use the Delete all button (Budgets on the Reports ribbon) to delete all Budget figures for a selected period. If you have more than 1 period, for example more than 1 financial year, you need to select the periods and repeat the process.' = Maybe I should add it as a note in Clear/Reset and Budgets topics
- We would need some tick-boxes then on what to delete. Maybe a Confirmation message could be added to clear or retain budget figures.
- Bank imports are not deleted.

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Known issues - Digit separator symbol - Documents - Spreadsheet import

Number format 123,456.00



If the number format is set to Decimal symbol is set to a full stop and the digit separator as a comma, as in the example of the "*Customize Format*" screen, the file exports and imports correct in most of the options.

Spreadsheet import - Document entry - context menu - Documents → Spreadsheet import

When an Export file is created based on the 123,456.00 number format, and the Export file is opened in the "*Data Import Export*" using the Spreadsheet import option, the amounts columns is blank.



	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P
1	id	Document no.	Date	Due date	Accid	Printed	Amount excl.	Amount incl.	Due	Tax amount	Reference	Document group 1	Document group 2	Account no.	Description	Salespersc
2	72	IN000022	30/06/202	30/07/202	54	45					C-103	Document group 1E	Empty	D1ABGRE	Mr. AB Green	Russell
3	67	IN000021	30/06/202	30/07/202	54	1					C-103	Document group 1E	Empty	D1ABGRE	Mr. AB Green	Russell
4	56	IN000020	30/06/202	30/07/202	54	14					A-103-2	Document group 1E	Empty	D1ABGRE	Mr. AB Green	Russell
5	55	IN000019	30/06/202	30/07/202	54	0					D-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Tracy
6	54	IN000018	24/06/202	24/07/202	28	0					D-102	Document group 1E	Empty	D1ROGSM	Mr. Roger Smith	Tracy
7	53	IN000017	20/06/202	20/07/202	27	0					C-103	Document group 1E	Empty	D1MDAVI	Mr. Mike Davies	Russell
8	52	IN000016	17/06/202	17/07/202	28	0					C-102	Document group 1E	Empty	D1ROGSM	Mr. Roger Smith	Tracy
9	51	IN000015	15/06/202	15/07/202	27	0					D-101	Document group 1E	Empty	D1MDAVI	Mr. Mike Davies	Tracy
10	50	IN000014	12/06/202	12/07/202	28	0					D-102	Document group 1E	Empty	D1ROGSM	Mr. Roger Smith	Tracy
11	49	IN000013	10/06/202	10/07/202	27	0					C-103	Document group 1E	Empty	D1MDAVI	Mr. Mike Davies	Russell
12	48	IN000012	07/06/202	07/07/202	28	0					C-102	Document group 1E	Empty	D1ROGSM	Mr. Roger Smith	Tracy
13	47	IN000011	05/06/202	05/07/202	54	0					D-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Tracy
14	46	IN000010	08/05/202	07/06/202	27	0						Document group 1A	Empty	D1MDAVI	Mr. Mike Davies	Russell
15	44	IN000009	07/05/202	06/06/202	54	3					PH-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Russell
16	43	IN000008	11/04/202	11/05/202	28	2					D-102	Document group 1E	Empty	D1ROGSM	Mr. Roger Smith	Tracy
17	42	IN000007	10/04/202	10/05/202	27	0					C-103	Document group 1E	Empty	D1MDAVI	Mr. Mike Davies	Russell
18	41	IN000006	09/04/202	09/05/202	28	2					C-102	Document group 1E	Empty	D1ROGSM	Mr. Roger Smith	Tracy
19	40	IN000005	07/04/202	07/05/202	27	0					D-101	Document group 1E	Empty	D1MDAVI	Mr. Mike Davies	Tracy
20	35	IN000004	16/03/202	15/04/202	27	0					IB-102	Document group 1A	Empty	D1MDAVI	Mr. Mike Davies	Tracy
21	34	IN000003	15/03/202	14/04/202	54	0					PH-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Russell
22	33	IN000002	14/03/202	13/04/202	56	0					IB-101	Document group 1A	Empty	D1MACDS	MAC Shop Decor Specialists	Tracy
23	32	IN000001	13/03/202	12/04/202	54	0					AB-IN110	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Russell
24																

Number format 123456,00

When an Export file is created based on the 123 456,00 number format, and the Export file is opened in the "*Data Import Export*" using the Spreadsheet import option, the amounts columns is correct.



id	Document no.	Date	Due date	Accid	Printed	Amount excl.	Amount incl.	Due	Tax amount	Reference	Document group 1	Document group 2	Account no.	Description	Salesperson	Status	Messa
72	IN000022	30/06/2021	30/07/2021	54	45	5000	5750	5750	750	C-103	Document group 1B	Empty	D1ABGRE	Mr. AB Green	Russell	0	30 Da
67	IN000021	30/06/2021	30/07/2021	54	1	5000	5750	5750	750	C-103	Document group 1B	Empty	D1ABGRE	Mr. AB Green	Russell	0	30 Da
56	IN000020	30/06/2021	30/07/2021	54	14	5000	5750	2875	750	A-103-2	Document group 1B	Empty	D1ABGRE	Mr. AB Green	Russell	1	30 Da
55	IN000019	30/06/2021	30/07/2021	54	0	5000	5750	0	750	D-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Tracy	1	30 Da
54	IN000018	24/06/2021	24/07/2021	28	0	2000	2300	2300	300	D-102	Document group 1B	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1	30 Da
53	IN000017	20/06/2021	20/07/2021	27	0	2500	2875	2875	375	C-103	Document group 1B	Empty	D1MDAVI	Mr. Mike Davies	Russell	1	30 Da
52	IN000016	17/06/2021	17/07/2021	28	0	3000	3450	3450	450	C-102	Document group 1B	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1	30 Da
51	IN000015	15/06/2021	15/07/2021	27	0	1000	1150	1150	150	D-101	Document group 1B	Empty	D1MDAVI	Mr. Mike Davies	Tracy	1	30 Da
50	IN000014	12/06/2021	12/07/2021	28	0	2000	2300	2300	300	D-102	Document group 1B	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1	30 Da
49	IN000013	10/06/2021	10/07/2021	27	0	1500	1725	1725	225	C-103	Document group 1B	Empty	D1MDAVI	Mr. Mike Davies	Russell	1	30 Da
48	IN000012	07/06/2021	07/07/2021	28	0	3000	3450	3450	450	C-102	Document group 1B	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1	30 Da
47	IN000011	05/06/2021	05/07/2021	54	0	1000	1150	1150	150	D-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Tracy	1	30 Da
46	IN000010	08/05/2021	07/06/2021	27	0	1000	1150	1150	150		Document group 1A	Empty	D1MDAVI	Mr. Mike Davies	Russell	1	30 Da
44	IN000009	07/05/2021	06/06/2021	54	3	1000	1150	1150	150	PH-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Russell	1	30 Da
43	IN000008	11/04/2021	11/05/2021	28	2	2000	2300	2300	300	D-102	Document group 1B	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1	30 Da
42	IN000007	10/04/2021	10/05/2021	27	0	1500	1725	1725	225	C-103	Document group 1B	Empty	D1MDAVI	Mr. Mike Davies	Russell	1	30 Da
41	IN000006	09/04/2021	09/05/2021	28	2	3000	3450	3450	450	C-102	Document group 1B	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1	30 Da
40	IN000005	07/04/2021	07/05/2021	27	0	1000	1150	1150	150	D-101	Document group 1B	Empty	D1MDAVI	Mr. Mike Davies	Tracy	1	30 Da
35	IN000004	16/03/2021	15/04/2021	27	0	1500	1725	1725	225	IB-102	Document group 1A	Empty	D1MDAVI	Mr. Mike Davies	Tracy	1	30 Da
34	IN000003	15/03/2021	14/04/2021	54	0	1000	1150	0	150	PH-101	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Russell	1	30 Da
33	IN000002	14/03/2021	13/04/2021	56	0	1500	1725	1725	225	IB-101	Document group 1A	Empty	D1MACDS	MAC Shop Decor Specialists	Tracy	1	30 Da
32	IN000001	13/03/2021	12/04/2021	54	0	1000	1150	300	150	AB-IN110	Document group 1A	Empty	D1ABGRE	Mr. AB Green	Russell	1	30 Da

Other errors

To use the Import check

Access violation at address 5140CB64 in module 'dbrtl260.bpl'. Read of address 00000009

Spreadsheet import context menu

Confirmation

> Field(s) not found do you wish to add them?

SSTOCKCODE

SACCOUNT

FQTY

SSTOCKDESCRIPTION

FSELLINGPRICE

STAX

DDATE

SDOCREFERENCE

BEXCLUSIVE

BDESCRIPTIONLINE

SJOBCODE

SCOSTGROUP1

SCOSTGROUP2

SACCOUNTCODE

SDESCRIPTION

SCONTACTNAME

Error

'Ref:IN000021 Ref:IN000020' is not a valid floating point value

---

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

Known issues - Decimal symbol - Create receipts (Batch entry)

Launched from Receipts batch – Create receipts – F9: Process

Create receipts option in receipt batches - "*Receipts options*" screen



Amount - Enter the amount in figures. You may enter up to Nine billion, nine hundred and ninety nine million, nine hundred and ninety nine thousand nine hundred and ninety nine (Rands, Euros, Pounds or

Dollars) and ninety nine cents in this field (9,999,999,999.99).

If your system's digit separator is set to a comma and your system's Decimal symbol is set to a period (full stop), do not enter a comma as the decimal separator.

If a comma is used as a digit separator, it will print and generate the transaction amount as 115,000.00 instead of 1,150.00.

An example of the printed "*Receipt*", is as follows:



Receipt batch transactions



Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Known issues - No Delete confirmation messages

Calendar - Delete process repeating invoices

No delete confirmation message



Click on Delete button and the item is removed from the "*Process list*".

NOTE

For events there is a confirmation message to delete the event

> Delete "Repeating invoices" from your schedule?
> This operation cannot be undone!

Debtors / Creditors tab - Delete contact - No confirmation message

Click Delete button and gone is the contact



NOTE

On Contacts screen (Default ribbon) the Delete confirmation message is displayed:

> Do you want to delete this contactperson?

On Calendar - Contacts screen the Delete confirmation message is displayed:

> Delete Ben Best from your list of contacts?
> This operation cannot be undone!

Change Reporting groups 1 / Reporting group 2

Change Reporting groups 1 / Reporting group 2 for Debtors / Creditors and Documents no confirmation message is displayed from the context menu options on the grid.

Using the context menu on Stock items Change Reporting groups 1 / Reporting group 2 a confirmation message is displayed e.g.:

> Set reporting group 2

Created with the Standard Edition of HelpNDoc: Elevate your documentation to new heights with HelpNDoc's

built-in SEO

Known issues - Access violations

Access violation errors - Blockchain

Access violation at address 05C1545B in module 'osfresource.bpl'. Read of address 00000000

Access violation - Closing TurboCASH with active reminder in Calendar

Access violation at address 056E363E in module 'V103_D60.bpl'. Read of address 0000004D.

Access violation – Spreadsheet import

Access violation at address 5140CB64 in module 'dbrtl260.bpl'. Read of address 00000009

Made a Spreadsheet export save as XLXS Excel workbook in a Set of Books

Try to import the Spreadsheet into a Set of Books created Advanced option .

Click Ok and on the Import Check imported the spreadsheet into new blank books Import successful

Tax percentages 0,00

Bank Batches imported

Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

Known issues - Cost centres - Access Violations

Cost centres - Access Violation errors

Balance sheet

May need to click on the Report and Priny button a few times to print the Balance sheet and Income statement

Access violation at address 78168283 in module 'rtl290.bpl'. Read of address 00000008

Income statement produces similar Access violation errors, but less frequent.

Changing the System settings - Number format solves the Type conversion error in the Budget vs actual report on the Ledger analyser.

Type conversion error 'Val':Expression TRpExpression46

It also solves issue with the character (printed in stead of a space in the System settings - Number format of the Standard column balances report on the Ledger analyser.



Code	Name	Trial balance	Income statement		Balance sheet		
G010000	Sales	0,00	17♦500,00	0,00	17♦500,00	0,00	0,00
G100000	Cost of sales	4♦500,00	0,00	4♦500,00	0,00	0,00	0,00
G210010	Fuel and oil	120,00	0,00	120,00	0,00	0,00	0,00
G210020	Maintenance	400,00	0,00	400,00	0,00	0,00	0,00
G210030	Repairs	600,00	0,00	600,00	0,00	0,00	0,00
G220000	Rent	500,00	0,00	500,00	0,00	0,00	0,00
G225000	Salaries and wages	600,00	0,00	600,00	0,00	0,00	0,00
G510000	Retained income	0,00	0,00	0,00	0,00	0,00	0,00
G600010	Furniture & fittings @ cost	1♦500,00	0,00	0,00	0,00	1♦500,00	0,00
G700000	Debtors control	20♦125,00	0,00	0,00	0,00	20♦125,00	0,00
G750000	Stock control	3♦500,00	4♦500,00	0,00	0,00	0,00	1♦000,00
B810000	ABC - Bank	0,00	1♦295,00	0,00	0,00	0,00	1♦295,00
T860010	Output VAT - 15%	0,00	2♦625,00	0,00	0,00	0,00	2♦625,00
T860020	Input VAT - Standard rate -15%	975,00	0,00	0,00	0,00	975,00	0,00
G900000	Creditors control	0,00	6♦900,00	0,00	0,00	0,00	6♦900,00
	Net Profit/Loss			10♦780,00	0	0	10♦780,00
	Totals	32♦820,00	32♦820,00	17♦500,00	17♦500,00	22♦600,00	22♦600,00

It does not resolve the Access violations in the Balance Sheet and Income statement when the System settings - Number format solves the Type conversion error in the Budget vs actual report on the Ledger analyser is fixed.

Type conversion error 'Val':Expression TRpExpression46

Save metafile as - Excel (one sheet)

Error replicated in all reports in the Save metafile as - Excel (one sheet) option on the Reportman preview screen.

Unable to set the HorizontalAlignment property of the Range class

Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Known issues - Default language setting

Changed from previous osFinancials4, osFinancials5 and TurboCASH5.2 (453) releases - Set the default language in a Set of Books - Could save the language with no user in each database in Setup → Access control.

In osFinancials5.1.0.227 you cannot set it by default if no users were added. Now you can only set the language for each user.

Currently you cannot set the default language in a Set of Books. When opening a Set of Books from the Bin Repository folder in TurboCASH5 or Download it from the download option in Let osFinancials help you to create a Set of Books (in both TurboCASH5 and osFinancials5.1.0.227), the System language in Setup → Access control is blank.



In Firebird and MSSQL database types cannot change the language on Setup → Access control (System language) and click the Apply button as the default language for the Set of Books. It reverts back to the original language e.g. Afrikaans if you change it to English.

The Set of Books will not open in the previous default language set in Previous versions of osFinancials5/TurboCASH5. It will open in a different language (e.g. English)

After opening the Sets of Books, you need to go to Switch language option (Start ribbon). The selected language will then be updated and displayed in Setup → Access control.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Known issues - Customise your own Set of Books (Advanced)? - Missing Groups and Paper types

---

Customise your own Set of Books (Advanced)? - Missing Groups and Paper types

When creating a Set of Books using the "*Customise your own Set of Books (Advanced)?*" option, you begin with a clean slate and have to build your chart of accounts from scratch. The initial setup process will only include three main control accounts: the Debtor's control account, Creditor's control account, and Retained earnings account.

The Types table does not include the following in the newly created Set of Books for Firebird database types and MSSQL database types:

- Groups is by default not included in the Types table - Projects (1000), Cost Centre 1 (1002), Cost Centre 2 (1003) and Languages (1004) need to be added as WTYPEPARENT (Type 2) -
- Paper types Till Slip (55) and New Plain (56) need to be added as WTYPEPARENT (Type 5) -

These Missing records in the Types table Groups and Paper types needs to be manually added Using the SQL Browser Plugin.

Steps after creating the Set of Books (Advanced)

Customise labels for Document types

You may need to customise labels and fix records.

Change the descriptions on the Types tab on Tools → Customise languages (Setup ribbon). If you have a different language than English, you need to translate the descriptions for your language or specific requirements.

Document types





"*Goods Returned*" - change to Supplier return to be consistent with the other labels in the language file.



The Document type (i.e. Invoice, Credit note, Quote, Purchase, Supplier return or Order) is stored and edited in the Tools → Customize language (Setup ribbon).

It should print the Document type (i.e. Invoice, Credit note, Quote, Purchase, Supplier return or Order) as this is more correct for the recipient of these documents.

If you need to print documents using the document layout files supporting one (1) Layout file for all document types), it is recommended that the Document types are edited and/or translated to the singular in the Types tab Tools → Customize language menu (Setup ribbon).

Change Edit Groups

Change the reporting group names (descriptions) of the Groups (Setup ribbon).

You may also add groups for reporting groups, if necessary.



The name must not already exist and may not be longer than 50 characters. This name will help you to identify the Set of Books on your system. You will need to select this name whenever you need to open the Set of Books or perform some other functions on the Set of Books.

The following groups are not included if the Set of Books was created using Create Set of Books (Advanced) option:

- Projects - You may create groups for Projects. These Projects may be activated in batches and documents. Once the batches and/or documents are posted (updated to the ledger), you may generate various reports for each Projects on the Sidebar of the Default menu.
- Cost centre 1 and/or Cost centre 2 -
- Languages - *Multi-Language accounts*

Multi-Language accounts - *Manual* - *Shop* - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

Add missing Groups and Paper types in the Types table

To add missing groups:

If you intend to use Projects, Cost centres and/or Multi-language Set of Books, you need to add these Groups manually:

1. Activate the SQLBrowser plugin in Tools → Activate plugins (Setup ribbon)
2. Launch the SQLBrowser plug-in Plugins → Tools → SQLBrowser (Setup ribbon).
3. Select the "*TYPES*" table.
4. Right-click and select "*Open*" on the context menu.



5. Select the last record WTYPEID - 93 in the TYPES table. Insert or Add a new record (you may also use the down arrow on your keyboard).
6. Add Groups - Optional - If you are planning to use any of the following features in osFinancials5, you

may add the groups, as required. To do this, type the following records and type 2 in the WTYPEPARENT column:

- 1000 - Projects
- 1002 - Cost centre 1
- 1003 - Cost centre 2
- 1004 - Languages

7. Add Paper types - Type the following records and type 5 in the WTYPEPARENT column:
   - 55 - Till slip
   - 56 - New plain
8. Close the SQLBrowser

> *SQLBrowser - Manual - Shop - Licence : Once-off -*
>
> *Activate the SQLBrowser plug-in Tools → Activate Plugins (select Tools → SQLBrowser and click Activate plugin) on the Setup ribbon.*

The groups will be added on Setup → Groups



Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Known issues - Screen layout

Documents – Enter inclusive total

Documents – Enter inclusive total to small for most translations (Context menu – “Enter total”)

Label ID 3322 - Enter new inclusive total (also to small for default English language)

Support



Workflow setup



FIXED - Cancel button cut-off icon

Was like this in osFinancials4 / TurboCASH5.1

Calendar – Create invoice for hours	Open item – Adjust payment date
	

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Known issues - Books - Delete

Delete Set of Books

Replicated in osFinancials5.1.0.189

Delete with No Password

Error when deleting Set of Books No Password

18

Error when Deleting set of books

C:\osfinancials5\books\DELETE-BOOKS-NO-PASSWORD\

Delete confirmation

Set of Books C:\osfinancials5\books\DELETE-BOOKS-NO-PASSWORD\Books.fdb deleted!

Set of Books list RED font



After second time Delete button removes it from the list.

books folder Stet of Books completely removed from folder.

Delete Set of Books - Cannot delete with password

Error when deleting Set of Books With Password

1

Error when Deleting set of books

C:\osfinancials5\books\PI-SUBSCRIPTIONS\

Delete confirmation

Set of Books C:\osfinancials5\books\PI-SUBSCRIPTIONS\Books.fdb deleted!

Books could not be deleted - Still available in books folder -



Need to delete the entire SET OF BOOKS in the books folder.

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Known issues - Debtors / Creditors - Multimedia

Debtors / Creditors - Documents and Transactions tabs - Multimedia on Context menu

Debtors / Creditors - Documents and Transactions tabs - Multimedia on Context menu if Multimedia is not activated in a Set of Books.



Document no.	Date	Printed	Amount inclusive	Reference
IN000004	2020-03-16	3	1 725,00	IB-102
IN000005	2020-0		1 150,00	D-101
QU000002	2020-0		1 150,00	D-101
IN000007	2020-0		1 725,00	C-103
IN000010	2020-05-08	0	1 150,00	AP-7/5/2020
IN000011	2020-05-13	0	1 150,00	D-101
QU000004	2020-05-15	12	6 325,00	
IN000013	2020-05-20	4	5 175,00	C-103
CR000001	2020-05-25	4	3 450,00	C-103

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Known issues - Lookups - Main accounts

Debtor / Creditor - Default account lookup - Main accounts

Use default account - blank lookup Fixed

Disabled accounts not listed - correct

Debtors control, Creditors control or Retained earnings - Correct - Error "*This account type cannot be used. Continue?*"

Lookup should not list Main accounts or control accounts not disabled - like in batches.



Default - Tax lookup correct Fixed

Can select a tax account

Financial entry - Lookup - Main accounts

The Accounts lookup displays only list debtors and creditor accounts - No ledger accounts

Should list only ledger accounts, excluding debtors and creditors

Fixed - now lists all accounts but also includes main accounts and allows to select should not list main accounts and control accounts.

Disabled accounts should be excluded.



Only when trying to post blocks works producing messages.

Error post to control account

You cant post to a control account! IN000016 Debtors control

Error post to sub-account

You cant post a account With subaccounts! IN000016 Furniture & fittings - Net value 600-000

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Known issues - Batches

Inactive Batch processing icons on Batch entry screens - Processes

Should the processing icons on the *"Batch entry"* screen is inactive during this process, you may need to close and reopen the batch.

This may occur after specific processes is performed in the Batch entry screen.



This may occur in the following options:

- F9:Process - Import a posted batch - This option allows you to import the transactions from a posted batch in the same Set of Books.
- F9:Process - Delimited file import - Select and open a valid comma separated value file format to import the transactions in a an unposted batch. This feature will import batch transactions exported using the Write delimited file option.
- F9:Process - Reverse batch (D<-->C) - If transactions were entered incorrectly in the debit column in stead of entering the transactions in the credit column, and *vice versa*, you may transfer (switch) the transaction amounts as entered into the credit columns to the debit columns and *vice versa* for any unposted batch.

Repeating Transactions

Clear / Reset a Set of Books - Repeating transactions not cleared

Clear / Reset a Set of Books - (Setup → Global processes → Clear / Reset) clears all batches but not the Repeating transactions entered in Edit → Repeating transactions on the Default ribbon.

Need to manually Erase (Delete) the batch.

Edit → Repeating transactions (Default ribbon)

F10:Setup select the contra account - Does not display when click OK - Only after balancing the batch, the contra account is updated.

Date column displays Day instead of Date



F9:Process - Repeating transactions

On the Batch entry screen, select the batch type for which Repeating transactions have been entered or processed on the Edit → Repeating transactions menu (Default ribbon).

On the F9:Process icon, select Repeating transactions option and click OK.

If no repeating transactions exists for the selected batch, nothing will happen.

Maybe a error or confirmation message, similar to the following, could be displayed:

> No transactions to import!



If no repeating transactions exists for the selected batch, nothing will happen.

Maybe a error or confirmation message, similar to the following could be displayed:

> No transactions to import!

The options is as follows:

- Year -
  - Last year - If this option is selected, only the previous financial year's periods will be listed.
  - This year - If this option is selected, the previous financial year's periods and the current financial year's periods will be listed.
- Add this to descriptions - NOTE that the descriptions entered in this field, will be added after the existing descriptions in the "*Description*" column. The "*Description*" column supports up to 35 characters. The for existing descriptions entered in this field may not be displayed in the Batch entry screen after import.
- New reference - NOTE that the new reference entered in this field, will replace the existing descriptions in the "*Reference*" column on the Repeating batch.



If the "*Increment reference*" option on the F10:Setup (Options for this batch) is selected, the reference number will be increased (e.g. "*REF1*" as entered). For example "*REF2*" and "*REF3*".

Once imported into a normal batch the line No. starts with 2 instead of 1 (as in other import options on Batch entry screens.

Contra account - may not be correct after Repeating entries is processed (imported) into a normal Batch entry screen.

You may need to reselect the correct contra account in F10:Setup (Options for this batch) and F5:Balance the batch.



Generate Multiple transactions - Select Contra account

All batches (except Payments and Receipts batches)

Replicated in the following options:

- F9:Process - Generate multiple transactions - Balance debtors with amount < x.xx - (e.g. Write-off bad debts - Uneconomical to recover)
- F9:Process - Generate multiple transactions - Fixed amount to all debtors
- F9:Process - Generate multiple transactions - Debtors with charge amount
- F9:Process - Generate multiple transactions - Creditors with charge amount
- F9:Process - Generate multiple transactions - Interest on overdue debtors

Need to select the contra account on F10:Setup.

For example, "Fixed amount to all debtors" option if the Contra account is selected as "*Sales*" account.



After processing the generated transactions, into the batch, the contra account is displayed on the batch as "*Sales*".



When the batch is balanced, the contra account, changes back to the contra account, as selected in the previous batch.



If balancing transactions is generated, when balancing the batch, delete these balancing transactions and go to F10:Setup and select the contra account for the Generate multiple transactions.



After the contra account is selected on the F10:Setup (Options for this batch) screen, rebalance the batch to the correct contra account.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Known issues - Documents

Create new Document - Select Debtor / Creditor

When creating a New sales document (e.g. Invoice, Credit note or Quote), the Debtor accounts screen list the last line. You need to use the scroll bar to view the search filter options to find an account.

Similarly when created a New purchase document (i.e. Purchase, Supplier return or Order), the Creditor accounts screen list the last line. You need to use the scroll bar to view the search filter options to find an account.



To use the filter options you need to scroll up



FIX for Debtor accounts / Creditor accounts lookup when creating documents

It also fixed the Debtor / Creditor accounts lookup when creating documents in osFinancials5-453 osFinancials4.0.0.1093

Deleting the HKEY_CURRENT_USER\SOFTWARE\osfinancials

To Delete the HKEY_CURRENT_USER\SOFTWARE\osfinancials in Windows Registry:

1. Close osFinancials5/TurboCASH5.
2. Right-click on the Start icon of your Windows operating system and select "*Run*".



3. Click OK to open the "*Registry editor*". Your system may ask for permissions and click Yes.



4. Navigate to the "HKEY_CURRENT_USER\SOFTWARE\osfinancials" key.
5. On "*osfinancials*" key right-click and select Delete on the context menu.
6. A "*Confirm Key Delete*" message will be displayed:

Are you sure you want to permanently delete this key and all of its subkeys?

7. Make absolutely sure that the correct entry is selected and click Yes.

8. Close the "*Registry Editor*" and launch osFinancials. It will create a new key and subkeys. The Debtor accounts / Creditor accounts lookup will display correctly when when creating new documents.



Documents Cancel - Confirm message incorrect document type name

When creating a new document, and you want to cancel it, it refers to invoice, and not to credit note, quote, purchase, supplier return or order.



If an unposted document is opened and being cancelled it still display invoice, irrespective of the document type.

When printing the document, when click on OK, the correct document type name is displayed for the correct document type, e.g.

> Do you wish to print this purchase?

Documents - Projects column

Project column by default available - only when Projects are activated in documents, the column should be added (similar to the Projects tab on Debtor /Creditor accounts).

Resize Documents screen

Hide ribbons double-click documents screen not resizing - Need to re-open Set of Books after the Ribbons are turned off to launch correct



Copy Documents - Unit descriptions not copied and not printing on layout files

Options to copy documents from the Documents context menu

Documents → Copy document

Documents → Copy to → Invoice, Credit note, Quote, Purchase, Supplier return and Order

The Unit descriptions (including remarks and comments, if exists on the source document) copies and will be printed on Document layout files.

The F11:Copy option on the document entry screen - No Unit descriptions copied and will not be included in the document layout files. To have the unit descriptions printed on document layout files, you need to edit the document and reselect the stock items on the Stock lookup.

Calendar - Bulk time entry Hours and Hours type - Units not copied

These were also replicated and needs to be rechecked

F11:Copy - No Unit descriptions copied

When printing the source document, the Unit descriptions is printed on layout file

When printing the copied document, the Unit descriptions is not printed on layout file.

Fixed Remarks and Comments is copied and prints on layout files

copied document document Excludes Unit descriptions



Work around : Once a document is copied, need to reselect the stock item then the units will print on layout file.

source document includes Unit descriptions



Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Known issues - Stock

Financial entry = Stock type - Label inactive button active



Buttons inactive but labels are active

Cost of Sales inactive but label active

Stock Control inactive but label active also Account not greyed out

Stock - BOM errors - Need to retest

Creating a new BOM item Adds the BOM tab -

Selecting the Stock type and Enter Stock code - produces errors

Error 1

> Total of salespercentage BOM not 100% auto adjusting for 100

Error 2

> validation error for column WSTOCKID, value "*** null ***"

Linked sale - need to test

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Known issues - Checking unposted items - No data

Checking unposted items not launching if there are no unposted batches and /or documents

On the Default ribbon, Input → Checking unposted items.

Checking unposted items not launching if there are no unposted batches and /or documents

Could launch with

<No data to display>

Batch Entry - Trial balance option - Batch entry selection screen context menu

On the Batch entry selection screen's context menu, Select the "*Trial balance*" option. You may select to include only unposted batches or to include posted batches.

The following known issues:

1. The Print button will by default, not be displayed. To initialise the Print button, select Income statement or Balance sheet and then Trial balance in the "*Report type*" field.
2. Click report type select Income statement or Balance sheet to add the print button - then report can be printed.
3. If there no unposted transactions in batches, (and the "*Unposted only?*" option is selected) the Unposted batches trial balance will still be launched with a zero.



FIXED - The "*Unposted batches*" screen may disappear behind other programs or applications. If this happens, click on the osFinancials5 icon on the Windows task bar.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Known issues - Print - Batch type report - Posted batches - COS

Reverse posted document - Print - COS not printed

Te Cost of Sales transactions is listed, but is not included in the "*Batch type report - Posted batch*" report.

- Reverse Posted batches/documents - Details screen
- Debtors - Documents tab - Show transactions context menu option

- Debtors - Transactions tab - Show transactions context menu option



The reason for this is that the invoice will post the transactions in 2 separate batches, i.e.

Sales journal will post the transactions to Debit the Debtor account and Credit the Sales account and Tax (VAT/GST/Sales tax) accounts

Cost of Sales journal (only if Cost of Sales is applicable to the Stock item selected) it will Debit the Cost of Sales account and Credit the stock control account.

Created with the Standard Edition of HelpNDoc: Powerful and User-Friendly Help Authoring Tool for Markdown Documents

Known issues - Import / Export

Spreadsheet import / export - Works

This feature may be used to import exported "*Excel Workbook (*.xlsx) file type* Spreadsheet files into:

- Into the same Set of Books.
- Into a different Set of Books.
- Into a new Set of Books -Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types.

- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

Debtors / Creditors

osFinancials5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet export and import feature.

- Spreadsheet export - You may export debtor (customer / client) accounts and creditor (supplier / vendor) accounts and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import debtor (customer / client) accounts and creditor (supplier / vendor) accounts from a saved "*Excel Workbook (*.xlsx) file type.*

Stock

osFinancials5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export feature.

- Spreadsheet export - You may export stock items and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import stock items from a saved "*Excel Workbook (*.xlsx) file type.*

Batches

osFinancials5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export feature.

- Spreadsheet export - You may export unposted batch transactions and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import batch transactions from a saved "*Excel Workbook (*.xlsx) file type.*

This feature may be used to import transactions into:

- Batches into the same Set of Books - Also handy to handle Repeating transactions.
- Batches into a different Set of Books with a similar accounts.
- Batches into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types.
- Batches into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

Spreadsheet import / export - Not working

Accounts

Spreadsheet export / import

osFinancials5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export feature.

- Spreadsheet export - You may export ledger accounts and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import ledger accounts from a saved "*Excel Workbook (*.xlsx) file type.*

Imports accounts but no Sub accounts, etc. Sub-accounts greyed out but ticked for Main accounts

Imports tax accounts with Tax tabs but no tax percentages.





Setup ribbon - Tab delimited - export / import

Export as Tab delimited (creates a txt as well as an xml file)

Import as Tab delimited. Sub accounts is correctly imported but first Tax code (Sub account does not have a Tax tab and percentage. Zero-rated percentages needs to be confirmed.

See - After Import in topic - Import General ledger accounts (Setup ribbon) -

Documents

Spreadsheet export / import

Spreadsheet import option not launched - Launches the "*Data Import Export*" screen -

Import and Export icons is static.



Import XML

Import XML and Import XML setting is added to the Documents context menu - in osFinancials5.1.0.4 -

Blank confirmation screen - cannot select xml file to import



Context menu - Others - Import

Context menu - Import

TXF file required to import - Export on the Setup ribbon does not create a TXF file (default)

Only creates an XML file type

Select all file types then the xml file - it does import



Documents - Other export options

Export Documents - Export grid Creates a csv or txt file (for a document type, document status, filter options, etc..) which can be opened in spreadsheets.

Import (Setup ribbon)

Error

> cdDoubles: Cannot perform this operation on a closed dataset

Import Stock (Tools - Setup ribbon)

Import stock from a Tab delimited Text file created In Tools - Export ribbon)

> Error 3The statement has been terminated.
> The INSERT statement conflicted with the FOREIGN KEY constraint "FK_DOCLINE_STOCK". The conflict occurred in database "MSSQL-HANDYMAN", table "dbo.Stock", column 'WStockID'.

Export / Import Posted batches

Export Posted Batches only creates a XML file type

Cannot use the Posted batches import option on Process options in Batch entry screens.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Known issues - Convert quote to one unprocessed invoice per client

---

Convert quote to one unprocessed invoice per client Documents context menu Progress indicator

but when finished cannot see or find the new invoice.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Known issues - Confirm Quotes and Orders - Remove button

Menu : Input → Confirm (Default ribbon)

Remove button is static and does not seem to work on the Confirm quotes and Confirm orders options.



Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Known issues- Create backorders to deliver

Create backorders to deliver creates a new Invoice or Quote for a Debtor (customer / client) account

Uses Input Tax instead of Output tax for selling prices

If created from Quotes it creates an Invoice in the Quotes document type

Backorders to deliver - Quotes



To create an Invoice from the Quotes document type for Backorders to deliver:

To create backorders to deliver:

1. Select the "*Quotes*" document type.

2. Select the document to create backorders to deliver.

3. Right-click and select Documents → Backorders to deliver option on the context menu. A new Invoice will be created in the Quotes document type.

4. You may need to edit the Invoice / Quote.



WARNING - Input Tax / Output tax

In the case of Invoices, the Input tax is used instead of the Output tax. You need to check this, and change it to the Output Tax.



Delete documents

Both the source document from which the Backorder was created from Quotes document type is listed in the Delete Documents - All option

with the same Document number.



Delete Quotes -



Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Known issues - Search - BOM (Production)

Search (Central search) Description Inaccuracies

To locate specific assemble or disassemble transactions or document numbers:

- Search for keywords such as "*assemble*", "*disassemble*", or document numbers starting with "*SA*".
- In the search results, double-click on the "*Batch*" type to display the transactions in the T-Account viewer.
- To print a document, double-click on a document for the "*Document*" type.



NOTE: On the Search (central search), the "*Description*" column for the "*Document*" type, is indicated as follows:

- Dissable Details - Should be "*Production Details*" since the document e.g. "*SA00001*" is created using the "*Assemble*" option. The document type is listed as "*Assemble*" on the Document groups and Transactions tabs of the stock item for the BOM (Production) stock item type.
- Production Details - Should be "*Disassemble Details*" since the document e.g. "*SA00002*" is created using the "*Disassemble*" option. The document type is listed as "*Disassemble*" on the Document groups and Transactions tabs of the stock item for the BOM (Production) stock item type.

Search Description Inaccuracy:

- Central Search shows "*Dissable Details*" for "Assemble" documents (e.g., "SA00001"). This should be *"Production Details*".
- Conversely, "*Production Details*" are shown for "*Disassemble*" documents (e.g., "SA00002"). This should be "*Disassemble Details*".

Correct Descriptions:

- "*Assemble*" documents: Use "*Production Details*".
- "*Disassemble*" documents: Use "*Disassemble Details*".

These descriptions are consistent with the document types listed on the stock item's "Document groups" and "Transactions" tabs (BOM (Production) stock item type).

Document type descriptions is correct

BOM (Production) Document groups / Transactions tabs

The "*Assemble*" and "*Disassemble*" functions for BOM (Production) items create posted documents. These transactions will be listed under the Document groups tab and the Transactions tab.

Documents generated by these functions will have a document prefix "*SA*" (e.g., "*SA00001*"), using a similar 7-digit format.

BOM (Production) Document Groups Tab

The Document Groups tab for BOM (Production) stock items shows documents related to assembly and disassembly. These documents are automatically posted when you perform the Assemble and Disassemble actions.



On the Document groups tab, you can:

- Print a document: Double-click on the document to print it.
- Open a posted document: Right-click on the document and select "*Open document*" from the context menu.

BOM (Production) Transactions Tab

The Transactions tab includes posted documents generated by the assembly and disassembly of BOM (Production) items.



On the Transactions tab, you can:

- Open a posted document: Right-click on the document and select "Open document" from the context menu.

By following these instructions, you can efficiently manage and review the documents and transactions related to the assembly and disassembly of BOM (Production) items.

Viewing Posted Documents for BOM (Production) Items

Opening a Posted document

On the BOM (Production) Document groups and Transactions tabs, you can open posted documents generated by the "*Assemble*" and "*Disassemble*" functions as follows:

1. Right-click on the desired document.
2. Select "Open document" from the context menu.



Identifying the Document type

- The "*Your reference*" field and the "*Description*" column in the posted document will indicate whether the document was generated using the "*Assemble*" or "*Disassemble*" options for BOM (Production) items.
- Documents generated by these functions will have a document prefix "SA" (e.g., "SA00001"), using a similar 7-digit format.

By using these steps, you can easily access and identify the specific documents related to the assembly and disassembly of BOM (Production) items.

Print a Posted document

You may print selected posted document generated by the "*Assemble*" and "*Disassemble*" of BOM (Production) items from the following options:

- BOM (Production) - Document groups tab : (Double-click to print).
- Search (central search) : Locate these posted document generated by the "*Assemble*" and "*Disassemble*" of BOM (Production) items. (Double-click to print).



The "*POS Tax Invoice*" will print the correct document number, but will print the system date and time

stamp of your operating system and not the actual transaction date.

The default document layout file which will be used to print documents generated by the "Assemble" and "Disassemble" of BO is the "Layout file point-of-sale" selected in Setup → Documents setup.

WARNING: Point-of-sale document layouts might not be ideal for printing "Assemble" and "Disassemble" documents for BOM types due to:

- *Date: POS invoices show your system's date, not the actual processing date.*
- *Document Name: Might say "POS Tax Invoice" instead of something relevant.*
- *Footer: Contains data like cashup amounts, not relevant for BOM operations.*

Recommendation: Select a different document layout file for BOM (Production) transactions (Setup → Documents setup).



NOTE: Selecting the document layout files, which supports the "TYPES.SDESCRIPTION" document name from the "TYPES" table, document name as "Delivery note" for "Assemble" option and "Remittance" for "Disassemble" option. Selecting the following do will replicate the document names:

- *Layout file - (TRN_1910)*
- *Document layout - (TRN_3174)*

- *Document layout (15codes) - (TRN_906277)*
- *NO-TAX Layout file - (TRN_906589)*
- *NO-TAX Document layout - (TRN_906590)*
- *NO-TAX Document layout (15codes) - (TRN_906591)*

Recommendation: You may select the BOM (Production) Layout file (TRN_3266) for the Stock item type to print layout file "Assembly" or "Disassembly".

Document prefix: "SA" (e.g., "SA00001"), with a similar 7-digit format.

Example : Assemble



Delivery note accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```


BOM (Production)

BOM (Production) Page no.: 1 / 1

Empty account

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195
Company reg. no.: 336012345
Tax reg. no.: 446010111
Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Delivery address

Document no.: SA00001 **Date: 2024/05/21** **Account no.: T**

Code / Description	Units	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inc
BOMPRODUCTION Assemble BOM (Production)		5	1 500,00		7 500,00			

Total

Due date:
Your reference: Assemble BOM (Production)
Tax reference:
Message:

Salesperson: No group

BOM (Production) accepted:

Name: _____

Date: _____

Signature: _____

Printed/Reprinted *2024/09/04 04:47:14*

Example : Disassemble



Remittance accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Viewing BOM (Production) Transactions

The transactions generated by assembling and disassembling BOM (Production) items are posted to the "BOM (Production) Contra account" as configured in Setup → Stock Information.

These transactions are recorded in the ledger and can be viewed through various reports and tools. Here's how you can view, print, and export these transactions:

1.

1. Reports Menu: To view these transactions, navigate to the Reports menu and select Reports → Ledger → Transactions. You can choose from the following reports:
    - Transactions
    - Transactions - Standard

- Transactions - Extra details

2. Batch entry: Cost of Sales journal: Open the Batch entry (F2) and select Cost of Sales journal. In the Cost of Sales journal, click on the posted batches tab and select the batch. You can print the transactions in the "*Batch type report - Posted batch*".

3. T-Account Viewer: Access the T-Account viewer and select the "*BOM (Production) Contra account*". This allows you to view, print, and export the transactions.

4. Ledger Analyser: Alternatively, you can print a Trial Balance in Ledger Analyser 1 or Ledger Analyser 2. Double-click on the desired account or use the "*Show details*" option from the context menu to view detailed transactions.

5. Central Search: To locate specific assemble or disassemble transactions or document numbers. In the search results, double-click on the Batch type to display the transactions in the T-Account viewer.

Example : Ledger transactions - BOM (Production) Contra account



BOM (Production) - Assemble and Disassemble options will automatically generate transactions, which is posted to the ledger.

The Document no. for a BOM (Production) - Assemble and Disassemble options is automatically generated as a seven-digit number (consisting of a prefix SA followed by 5 numerical digits).

The Document type is "Assemble" or "Disassemble"

Example : Batch type report - Posted batch - BOM (Production) Batch transactions

Open the Batch entry (F2) and select Cost of Sales journal. In the Cost of Sales journal, click on the posted batches tab and select the batch.



Click the Print button to print the transactions in the "*Batch type report - Posted batch*".



Example : Batch type report - Posted batch report - Assemble transactions



Example : Batch type report - Posted batch report - Disassemble transactions



T-Account viewer

In addition to the transaction reports on the Reports menu; you may view, print and export transactions in the T-Account viewer from the following options.

- T- Account viewer : On the reports menu, select the T-Account viewer icon and select the "*BOM (Production) Contra account*".
- Alternatively, you may print a Trial balance in the Ledger analyser 1 / Ledger analyser 2 and double-click or use the "*Show details*" option on the context menu.



You may filter the transactions by batch number, e,g, "*34*" or "*35*".

Click on the Print button to print a T-account view of the transactions.



Should you wish to export these transactions to a spreadsheet click Export. If you need to include Contra accounts, in your spreadsheet, select the "*Show contra*" option

---

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Known issues - Reports

Updated reports - maximum databases fields

osFinancials5.1.0.127 - Reports in the folder (accessed via the Reports menu) were updated and included in the osFinancials5.1.0.127 update.folder were updated and included in the osFinancials5.1.0.127 update. These updated reports were included in the osFinancials5.1.0.127 update installation

1. systemreports - Location : " ...\plug_ins\reports\systemreports\ "
2. GENERAL - Location : " ...\plug_ins\reports\GENERAL\ "
    - documents - Location : " ...\plug_ins\reports\GENERAL\documents\ "
    - ledgerview - Location : " ...\plug_ins\reports\GENERAL\ledgerview\ "
3. REPORTS - Location : "...\plug_ins\reports\REPORTS\" REPORTS/STOCK - Sidebar reports

Reports fixed - After osFinancials5.1.0.127 Update install

These updated reports were included in theosFinancials5.1.0.127 update installation. These Reports were retested in both Firebird database types and in MSSQL database types in osFinancials5.1.0.127.

See - FIXED - After osFinancials5.1.0.127 update - Details / Notes and screenshots

The following reports were updated and fixed.

1. systemreports - Fixed some adjustments to text (labels expressions) and data expressions were made in about 7 reports.
    a) Reports → Debtors → Listing - List delivery address
    b) Reports → Debtors → Listing - List postal address
    c) Reports → Creditors → Listing - List delivery address
    d) Reports → Creditors → Listing - List postal address
    e) Reports → Stock → Stock In / Out - Stock in / Out
    f) Reports → Documents → Document listing
    g) Reports → Tax - Tax per period
2. REPORTS/STOCK - Sidebar reports - Stock movement - This report prints similar data to the "*Voorraad verloop*" report
    - Renamed text report name to LANG_906038 to be translatable via the language files. Added report name "*Stock movement - Average cost - Grid*" in Header section.
    - Total print on Page 2 and Total - Data type = Currency as " ##,###,###,##0.00" in Detail of Group section (e.g. 1,000.00) - Set the Group footer data type for the Total (e.g. 1000.00) to display similar than the Detail report section.
3. excelreports - Spreadsheet reports → Sales analysis → Sales per period - Fixed - Error in Firebird databases to be updated.

    Location : " *...\plug_ins\reports\excelreports\TRN_85\TRN_906122/trn1296.sql*"

Reports not included in osFinancials5.1.0.127 update install

The following reports were fixed in osFinancials5.1.0.109 update but in osFinancials5.1.0.127 update install:

1. DOCUMENTS/DOCUMENTS - Document layout files updated to fix overlapping labels, remarks, etc. Standardised the Company and Tax registration numbers before contact details, etc.
2. userreports - Reports in the user reports menu. Restructured and fixed overlapping labels, etc.
3. New.rep
4. Empty.rep - Updated and standardized header and footer not updated in osFinancials5.1.0.127.

Reports Fixed after osFinancials5.1.0.127 update install

1. Reminders / Remittace plugin - Location : *...\plug_ins\reports\remittance* - Fixed overlapping labels

Auto Expand / Auto Contract and word wrap settings. Fixed MSSQL error in doctype layouts - MSSQL Error DOCUMENTREGEL Dataset

> DOCUMENTREGEL:Incorrect syntax near '|'.

2. Subscriptions plugin - Reports in 2 different locations, it is:

   a) Reports - Location *: ...\plug_ins\reports\REPORTS\SUBSCRIPT* - Fixed overlapping labels Auto Expand / Auto Contract and word wrap settings.

   b) layouts -

      § English layout - Location : ...\plug_ins\reports\Subscriptions\en\layouts\default.rep

      § Netherlands layout - Location : ... \plug_ins\reports\Subscriptions\nl\layouts\default.rep

3. CRM plugin- Location : ...\plug_ins\reports\CRM\ - Not updated - Need to activate and configure the CRM plugin before any reports could be printed. - MSSQL Errors in

> "DOCUMENTHEAD:Incorrect syntax near '|'."

Reports - Firebird Errors

Ledger - Transactions

Prints in most databases in Firebird and MSSQL without errors –

Error only replicated in 1 Firebird Database (Set of Books) = TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456

Location : ...\plug_ins\reports\systemreports\TRN_1372\TRN_74\TRN_74.rep

> TRANSACTION_DETAIL:arithmetic exception, numeric overflow, or string truncation

Reports - MSSQL Errors

SUM MSSQL ERRORS

systemreports - MSSQL ERRORS - Stock - Stock In / Out

Reports → Stock → Stock In / Out - Stock In / Out

Location : ...\plug_ins\reports\systemreports\TRN_1999\TRN_906112\TRN_906112.rep

> Unknown identifier: :END.SUM 'END.SUM':Expression TRpExpression2

STOCK - MSSQL ERRORS - Sidebar reports - Historical value

Location : ...\plug_ins\reports\REPORTS\STOCK\TRN_906031.rep - Historical value

> Unknown identifier: VERKOOP.SUM 'VERKOOP.SUM':Expression TRpExpression12

userreports - MSSQL ERRORS

Prints in Firebird database types, but produces error in MSSQL database types.

Debtors outstanding at date

User reports → Debtors → Outstanding → Debtors outstanding at date

Location : ...\plug_ins\reports\userreports\TRN_160\TRN_947\TRN_906104.rep

> TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found

Creditors outstanding at date

User reports → Creditors → Outstanding → Creditors outstanding at date

Location : ...\plug_ins\reports\userreports\TRN_161\TRN_947\TRN_906103.rep

> TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found

Plugin – CRM

CRM plugin - Location : ...\plug_ins\reports\CRM\ - Not updated - Need to activate and configure the CRM plugin before any reports could be printed. - MSSQL Errors in

> "DOCUMENTHEAD:Incorrect syntax near '|'."

Plugin – Remittance layouts

Firebird Error - default.rep in English and Nederland

English - Location : ...\plug_ins\reports\remittance\en\layouts\default.rep

Nederlands - Location : ...\plug_ins\reports\remittance\nl\layouts\default.rep

> Could not convert variant of type (UnicodeString) into type (Double)

and within Reportman

```
Could not convert variant of type (UnicodeString) into type (Double)
TODATE=11-10-2006
```

The error message "*Could not convert variant of type (UnicodeString) into type (Double*)" in Firebird databases suggests that there is an issue with data conversion, particularly involving a Unicode string and a Double data type.

In your provided information, you also mentioned "*TODATE=11-10-2006*." It seems like there might be an attempt to convert a string ("*11-10-2006*") to a Double data type using the TODATE function in Firebird.

Here are a few steps you can take to troubleshoot and resolve the issue:

1. Check the Data Type Compatibility: Ensure that the data types used in your expressions are compatible. If you are using the TODATE function, make sure that the input is a valid date format.

   Example: sql

   ```
   SELECT TODATE('11-10-2006', 'DD-MM-YYYY') FROM YourTable;
   ```

2. Verify Data Formats: Double-check the format of the date string. In the example above, the format is 'DD-MM-YYYY'. If your date string follows a different format, adjust the format accordingly.

3. Handle NULL Values: If your data might contain NULL values, consider adding conditions to handle them appropriately. For instance, use the COALESCE function to replace NULL values with a default or handle them in another way.

4. Explicit Type Conversion: If you're dealing with mixed data types, explicitly convert the data types using appropriate functions. For example, you can use the CAST or CONVERT function to explicitly convert a string to a Double if needed.

   Example: sql

   ```
   SELECT CAST('11-10-2006' AS DOUBLE PRECISION) FROM YourTable;
   ```

5. Review the SQL Statement: Check the entire SQL statement or query for any other potential issues. Look for areas where data types might conflict.

Without seeing the full query or knowing more about the database structure, these are general suggestions. If the issue persists, providing more details about the relevant part of your SQL query and the database schema would be helpful for further assistance.

FIXED -NEED TO RECHECK MSSQL Graphs per Week / Graphs per Month MSSQL- Axis labels (Axis titles)

Example Graphs per month - 204121 Should display the month and year e.g. 202103, 202104 , 202105, 202106, etc. like in Firebird databases

Example Graphs per week - 204121 Should display the week and year e.g. 09 for first week March , etc. like in Firebird databases

Need to look at and recheck the "order by and having sum issues



DOCUMENTLINE SQL Graphs per month -> Graph - Profit / Loss per month

```
SELECT 1 WTYPEID,

{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,

sum(-transact.FAMOUNT) Total

FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT > 0
```

```
group by

{if interbase}extract(year from ddate){else}year(ddate){endif} ,

{if interbase}extract(month from ddate){else}month(ddate){endif}

union

SELECT 2 WTYPEID,

{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,

sum(-transact.FAMOUNT) Total

FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT < 0

group by

{if interbase}extract(year from ddate){else}year(ddate){endif} ,

{if interbase}extract(month from ddate){else}month(ddate){endif}

order by 2,1,3
```

Tidy report errors

Cannot change or Set the Properties such as word wrap, cut text, etc. Long Debtor / Creditor account names or descriptions may overlap

Reports → Debtors → Debtor transactions - Extra details - Location: …
\plug_ins\reports\systemreports\TRN_160\TRN_74\TRN_906107.rep

Reports → Creditors → Creditor transactions - Extra details - Location:…
\plug_ins\reports\systemreports\TRN_161\TRN_74\TRN_906109.rep



Firebird = arithmetic exception, numeric overflow, or string truncation

If "nounicode=False" in the osf.ini files, the error is produced in Firebird databases

> arithmetic exception, numeric overflow, or string truncation

Reports - Only prints if is set to nounicode=true in osf.ini files

Debtor Statements

Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090 - Debtor statement

Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_906552 - Debtor statement - Outstanding

Debtor Age analysis

Location : plug_ins\userreports\userreports\TRN_160\TRN_65\TRN_906142 - Balances detail

Location : plug_ins\reports\userreports\TRN_160\TRN_65\TRN_906143 - Balances detail history (open item)

Location : plug_ins\reports\userreports\TRN_160\TRN_65\TRN_906147 - Balances

Debtors Outstanding at date

Location : \plug_ins\reports\userreports\TRN_160\TRN_947\TRN_906104 - Debtors outstanding at date

Prints irrespective of unicode setting

Remittance advises

Location : plug_ins\reports\systemreports\TRN_161\TRN_1089\TRN_1089 - Creditor remittance advise

Location : plug_ins\reports\systemreports\TRN_161\TRN_1089\TRN_906551 - Creditor remittance advise - Outstanding

Similar reports prints irrespective of nounicode setting

Creditor Age analysis

Location : plug_ins\userreports\userreports\TRN_161\TRN_65\TRN_906142 - Balances detail

Location : plug_ins\reports\userreports\TRN_161\TRN_65\TRN_906143 - Balances detail history (open item)

Location : plug_ins\reports\userreports\TRN_161\TRN_65\TRN_906147 - Balances

Creditor transactions

Location : plug_ins\reports\systemreports\TRN_161\TRN_74 - Creditor transactions

User reports fixes

Debtor / Creditor - Age analysis - Balances reports

FIXED - No data to print message

Location : plug_ins\reports\userreports\TRN_160\TRN_65\TRN_906147 - Balances

Location : plug_ins\reports\userreports\TRN_161\TRN_65\TRN_906147 - Balances

Linked the "*Subreport*-1" to the TRANSACTION_DETAIL Dataset - changed to "*Subreport--1 (TRANSACTION_DETAIL)*" and "*P.Only data avail.*"=True setting.

Stock Sidebar reports

Historical value MSSQL Error

Location ...\plug_ins\reports\REPORTS\STOCK\TRN_906031.rep

> Unknown identifier: VERKOOP.SUM 'VERKOOP.SUM':Expression TRpExpression12

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Known issues - Stock sidebar reports - Report - Print single item

---

Outstanding to do - Changelog - Report button - Print single item context menu

See - FIXED-ADDED - Stock sidebar reports - Report - Print single item

Some issues needs to be rechecked

LANG_906585 - Stock - Expected quantities

test barcode.rep - Error - Access violation

test barcode.rep - Error -

> Access violation at address 500634CB in module 'rtl280.bpl'. Read of address 00000060

Barcode ean13 11352

Error :

> Wrong Barcode Type:5050526062535051525251525060505061606061535OG

No data available to print!

Order List - No data available to print!

Sales Hours.rep - No data available to print!

Stock Movement.rep - No data available to print!

Voorraad verloop.rep - No data available to print!

Print Barcodes in Stock items right-click context menu

Other reports does not print to screen - goes directly to PDF

Opened books as well as other books - Had to restart PC to print other reports to screen.

Created with the Standard Edition of HelpNDoc: Transform your help documentation into a stunning website

Known issues - Creditor remittance advices - SMESSAGE - CREDITOR table

---

Creditor remittance advices - SMESSAGE - CREDITOR table

Creditor Remittance advises

- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Location : plug_ins\reports\systemreports\TRN_161\TRN_1089 -
- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Outstanding - Location : plug_ins\reports\systemreports\TRN_161\TRN_906551 -

Messages - Creditor remittance message (Delivery address tab) 4 Message lines SMESSAGE - 50 characters is included in the CREDITOR table - but is currently not used to enter messages on the Delivery address tab of the Creditor account. This will print a blank empty space (line) in the Message section of the Creditor remittance advice and is therefore removed at this stage. Remittance messages is entered on the Statement message 1, Statement message 2 and Statement message 3 of up to 64 characters each for SFREEFIELDS1, SFREEFIELDS2 and SFREEFIELDS3 updated in the CREDITOR table.


FlameRobin Database Admin
Database View Server Object Help
CREDITOR
WACCOUNTID integer not null
SCODE varchar(6)
WCONTACTID integer not null
SPASSWORD varchar(8)
SPOSTAL1 varchar(30)
SPOSTAL2 varchar(30)
SPOSTAL3 varchar(30)
SPOSTALCODE varchar(8)
WPOSTCOUNTRIES_ID integer
SDELIVERY1 varchar(30)
SDELIVERY2 varchar(30)
SDELIVERY3 varchar(30)
WDELCOUNTRIES_ID integer
STELEPHONE1 varchar(20)
STELEPHONE2 varchar(20)
SFAX varchar(20)
SEMAIL varchar(50)
WBANKNAME varchar(20)
SBRANCHCODE varchar(10)
SBANKACCOUNTNUMBER varchar(45)
SBANKACCOUNTNAME varchar(30)
FCREDITLIMIT numeric(12,2)
FCHARGEAMOUNT numeric(12,2)
BOPENITEM smallint
BPOSTBBF smallint
DLASTACTIVITY timestamp
WCURRENCYID integer
WFOREXACCOUNTID integer
SMESSAGE varchar(50)
SREFERENCE varchar(20)
FDISCOUNT numeric(12,2)
WDEFAULTPRICETYPEID integer
DSYSDATE timestamp
WDUEDAYS integer
WDEFAULTACCOUNT integer
WDEFAULTTAX integer
SCOMPANYREGNO varchar(64)
SFREEFIELD1 varchar(64)
SFREEFIELD2 varchar(64)
SFREEFIELD3 varchar(64)
sysdba@localhost:C:\osfinancials5\books\EMPTY-BOOKS-8X3-DIGITS\bo...



On Creditor Remittance advices messages the SMESSAGE field Expressions is removed.



Created with the Standard Edition of HelpNDoc: Maximize Your Reach: Convert Your Word Document to an ePub or Kindle eBook

Known issues - Reports - Debtor list - Details / Creditor list - Details

Debtor list details

Debtor / Creditor - Accounting information - Bank account no. - Field focus

By default the cursor focus after 4 blank spaces. To enter need to select the blank spaces to enter the bank account no.

A bit sticky but can enter up to 13 characters which will print on the report



Debtor list - Details report / Creditor list - Details report

Location : ...\plug_ins\reports\systemreports\TRN_160\TRN_66\TRN_906140 (Reports → Debtors→ Listing - List details)

Also see

Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_66\TRN_906140 (Reports → Creditors→ Listing - List details)



FIXED

1. Account disabled - did not change from No to Yes when disabled
2. Open item account - change from No to Yes when disabled

Outstanding issues

1. Selling price - Description not displayed - Only selling price ID
2. Salesperson - Description not displayed - Only Salesperson ID

3. Document layout files - TRN_1910 and not the translation i.e. "*Layout file*"

4. Bank - BIC - Branch code Displays the BIC account details.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Known issues - SQL Compatibility MSSQL and Firebird Database types

---

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Known issues - SQL Compatibility MSSQL and Firebird Database types - Reports

---

Outstanding errors : MSSQL Database support - Reports

Prints in FIREBIRD Databases

Errors in MSSQL Databases

systemreports

Stock in / out

Location : ...\plug_ins\reports\systemreports\TRN_1999\TRN_906112 (Stock in / out)

TRN_906112.rep

```
Unknown identifier: :END.SUM 'END.SUM':Expression TRpExpression2
```

END - Dataset

```
Select sum(Fqty) from stocktrn
left join dochead on stocktrn.Wdocid = dochead.wdocid
where WStockid = :Nr and stocktrn.ddate <= :ddatetofl
```

REPORTS/STOCK

Stock sidebar reports - Historical value

Location : ...\plug_ins\reports\REPORTS\STOCK\LANG_906031 (Historical value)

```
Unknown identifier: VERKOOP.SUM 'VERKOOP.SUM':Expression TRpExpression12
```

SQL =

```
(VOORRAAD.AantalAanw +
VERKOOP.SUM - INKOOP.SUM
) * VOORRAAD.LAATSEPRIJS
```

userreports

Debtors / Creditors - Outstanding at date

```
TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found
```

Debtors - Outstanding at date

Location : plug_ins\reports\userreports\TRN_160\TRN_947\TRN_906104 - Debtors outstanding at date

Creditors - Outstanding at date

Location : plug_ins\reports\userreports\TRN_161\TRN_947\TRN_906103 - Creditors outstanding at date

---

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Known issues - SQL Compatibility MSSQL and Firebird Database types - Plugins

---

Known issues - SQL Compatibility MSSQL and Firebird Database types - Plugins

The double pipe characters (||) for concatenation are not supported in Microsoft SQL Server. To ensure compatibility with both Firebird and SQL Server, you should use the CONCAT function instead.

Reminders plugin - MSSQL Compatibility

Email

```
Invalid column name 'REGISTER_ATT'.
Invalid column name 'REGISTERS_ID'.
Invalid column name 'REGISTERS_EMAIL'.
Invalid column name 'REGISTERS_SEND'.
```

Edit report

OPENITEMS:Column 'COUNTRIES.countries_name' is invalid in the select list because it is not contained in either an aggregate function or the GROUP BY clause.

CONCAT - in sql files

The || double pipe characters works in Firebird databases but is not compatible in MSSQL databases - causes errors.

```
Select SCompanyName || ascii_char(35) || ascii_char(25)
|| sysvars.SADDRESS1
|| ascii_char(13) || ascii_char(10)
|| sysvars.SPOSTCODE
|| ' ' || sysvars.SADDRESS2
|| ascii_char(13) || ascii_char(10)
|| sysvars.SPHONENUMBER
 from sysvars
```

Subscriptions plugin

SQL folder in the templates need update for compatibility in both MSSQL and Firebird Database types

Location : ...\plug_ins\reports\Subscriptions\en\SqlInvoice

Location : ...\plug_ins\reports\Subscriptions\en\Sql

Language templates : nl folder for Netherlands and en folder for English and af for Afrikaans folder

Current SQL Firebird database types

The double pipe characters (||) is currently supported in Firebird database types included in the SqlInvoice and Sql folders, which supports Firebird database types only.

Sample of the current SQL code (companyname.txt file) that will work in Firebird database types only:

```
Firebird database type SQL

Select SCompanyName || ascii_char(13) || ascii_char(10)
|| sysvars.SADDRESS1
```

```
|| ascii_char(13) || ascii_char(10)
|| sysvars.SPOSTCODE
|| ' ' || sysvars.SADDRESS2
|| ascii_char(13) || ascii_char(10)
|| sysvars.SPHONENUMBER
 from sysvars
```

Change SQL - Compatibility = MSSQL database types and Firebird database types

The double pipe characters (||) for concatenation are not supported in Microsoft SQL Server. To ensure compatibility with both Firebird and SQL Server, you should use the CONCAT function instead.

Sample of the modified SQL code (companyname.txt file) that will work in both database types:

MSSQL database type SQL

```
SELECT CONCAT(SCompanyName, CHAR(13), CHAR(10), sysvars.SADDRESS1, CHAR(13), CHAR(10),
sysvars.SPOSTCODE, ' ', sysvars.SADDRESS2, CHAR(13), CHAR(10), sysvars.SPHONENUMBER)
FROM sysvars;
```

Subscription plugin Files to be converted to CONCAT function (concatenation)

`Location :` …\plug_ins\reports\Subscriptions\nl

`Location on GitHub :` osfinancials-development/reports/plug_ins/reports/Subscriptions/nl at main · Digidanosf/osfinancials-development · GitHub

The double pipe characters (||) need to be converted and updated in the following files:

- companyname.txt
- email.txt
- HTMcompanyname.txt
- HTMlogo.txt
- HTMparcel.txt
- logo.txt
- parcel.txt

- Updsql.txt

EmailInvoice Plugin

Current SQL Firebird database types

The double pipe characters (||) is currently supported in Firebird database types included in the SqlInvoice and Sql folders, which supports Firebird database types only.

Sample of the current SQL code (companyname.txt file) that will work in Firebird database types only:

Firebird database type SQL

```
Select   SCompanyName || '<br/>'
|| sysvars.SADDRESS1 || '<br/>'
|| sysvars.SPOSTCODE || ' ' || sysvars.SADDRESS2   || '<br/>' ||
sysvars.SPHONENUMBER || '<br/>'
 from sysvars
```

Change SQL - Computability = MSSQL database types and Firebird database types

The double pipe characters (||) for concatenation are not supported in Microsoft SQL Server. To ensure compatibility with both Firebird and SQL Server, you should use the CONCAT function instead.

Sample of the modified SQL code (companyname.txt file) that will work in both database types:

MSSQL database type SQL

```
SELECT CONCAT(SCompanyName, '<br/>', sysvars.SADDRESS1, '<br/>',
sysvars.SPOSTCODE, ' ', sysvars.SADDRESS2, '<br/>', sysvars.SPHONENUMBER)
FROM sysvars;
```

EmailInvoice plugin Files to be converted to CONCAT function (concatenation)

`Location :` ...\plug_ins\reports\EMailInvoice\nl\Sql

`Location on GitHub :` osfinancials-development/reports/plug_ins/reports/EMailInvoice/nl/Sql at main · Digidanosf/osfinancials-development · GitHub

Language templates : nl folder for Netherlands and en folder for English and af for Afrikaans folder

The double pipe characters (||) need to be converted and updated in the following files:

- companyname.txt
- doclines.txt
- email.txt
- ExtraFiles.txt
- HTMcompanyname.txt
- HTMdoclines.txt
- HTMlogo.txt
- HTMparcel.txt
- logo.txt
- parcel.txt
- selectLayout.txt
- Updsql.txt

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Known issues - Outstanding at date reports - MSSQL

Outstanding at date reports

These Outstanding at date reports prints in Firebird database types, but in MSSQL database types it produces an error:

```
TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found
```

Debtors outstanding at date

Location : ...\plug_ins\reports\userreports\TRN_160\TRN_947\TRN_906104.rep

Creditors outstanding at date

Location : ...\plug_ins\reports\userreports\TRN_161\TRN_947\TRN_906103.rep

Debtors outstanding at date - Current SQL - TRANSACTION_DETAIL Dataset

```
SELECT

cast(transact.FAmount as decimal(12,2)) p1,

transact.*,Account.*,messages.SDescription

FROM transact

   LEFT OUTER JOIN account

   ON  (transact.WAccountID = account.WAccountID)

join Messages on (transact.WDescriptionid = messages.WMessageID)

WHERE WAccountTypeId  = :ACCID

and account.waccountid = :WACCOUNTID

and (transact.DDate <=

{if interbase}

dateadd(1 day to dateadd(- 1 second to  :ddatetofl  ) )

{endif}

 {if mysql}

date_add(date_add(:ddatetofl, interval -1 second), interval 1 day)

{endif}

 {if postgresql}

(:ddatetofl::timestamp -  interval '1 second') + interval '1 day'

{endif}

)

and (transact.DDate >=  :ddatefromfl

 )

union

SELECT

sum(transact.FAmount ) p1,

0,max( transact.WBATCHID),max( transact.WBATCHTYPEID),max( transact.WLINEID),

max(transact.BCARRIEDFORWARD),

max(transact.BLASTYEAR),max( transact.BLINKSUSED), max(transact.BMULTIPLEITEMS),
```

```
max( transact.WACCOUNTID),max( transact.DDATE),

max(transact.WPERIODID),max( transact.WYEARID), 'Opening',
max(transact.FTAXRATE),max( transact.WTAXACCOUNTID),

sum(transact.FAMOUNT), sum(transact.FTAXAMOUNT),sum( transact.FOUTSTANDINGAMOUNT),
max(transact.BRECONCILED),

0, 0, 0,

0,max( transact.WUSERID),0,max( transact.DSYSDATE),

0,0,0,0,

0,0, 0,0,

0, 0, 0, 0,

max(transact.DPAYMENTDATE),0,0,

Account.WACCOUNTID, Account.SACCOUNTCODE, Account.SMAINACCOUNTCODE,

Account.SSUBACCOUNTCODE, Account.SDESCRIPTION, Account.WACCOUNTTYPEID,

Account.WREPORTINGGROUP1ID, Account.WREPORTINGGROUP2ID,

Account.BSUBACCOUNTS, Account.BINCOMEEXPENSE, Account.BOPENITEM,

Account.BINACTIVE, Account.DSYSDATE, Account.WPROFILEID,

Account.WLINKACCOUNT, Account.WTAXACCOUNT, Account.WCURRENCYID,'Opening' FROM transact
   LEFT JOIN account
   ON (transact.WAccountID = account.WAccountID)
WHERE WAccountTypeId = :ACCID
and account.waccountid = :WACCOUNTID
and (transact.DDate < :ddatefromfl )
and (transact.WREPORTINGGROUP1ID = :WREPORTINGGROUP1ID or :WREPORTINGGROUP1ID = 0)
and (transact.WREPORTINGGROUP2ID = :WREPORTINGGROUP2ID or :WREPORTINGGROUP2ID = 0)
group by Account.WACCOUNTID, Account.SACCOUNTCODE, Account.SMAINACCOUNTCODE,

Account.SSUBACCOUNTCODE, Account.SDESCRIPTION, Account.WACCOUNTTYPEID,

Account.WREPORTINGGROUP1ID, Account.WREPORTINGGROUP2ID,

Account.BSUBACCOUNTS, Account.BINCOMEEXPENSE, Account.BOPENITEM,

Account.BINACTIVE, Account.DSYSDATE, Account.WPROFILEID,

Account.WLINKACCOUNT, Account.WTAXACCOUNT, Account.WCURRENCYID
```

```
having sum(transact.FAmount ) <> 0

 order by @ORDER,11
```

Debtors outstanding at date - Current SQL - ACCLIST Dataset

```
SELECT  account.waccountid,account.SAccountcode,

sum(transact.FAmount )

FROM transact

    JOIN account

   ON  (transact.WAccountID = account.WAccountID)

WHERE WAccountTypeId  = :ACCID

and SAccountcode <= trim(substring('@SACCOUNTCODETOTX  ' from 2 for {if mysql}if{else}
IIF{endif}(position (' ' in '@SACCOUNTCODETOTX  ')=0,0,position (' ' in
'@SACCOUNTCODETOTX  ')-1)) )

and SAccountcode >= trim(substring('@SACCOUNTCODETX  ' from 2 for  {if mysql}if{else}
IIF{endif}(position (' ' in '@SACCOUNTCODETX  ')=0,0,position (' ' in '@SACCOUNTCODETX
')-1)))

and (transact.DDate <=

{if interbase}

dateadd(1 day to dateadd(- 1 second to  :ddatetofl  ) )

{endif}

 {if mysql}

date_add(date_add(:ddatetofl, interval -1 second), interval 1 day)

{endif}

 {if postgresql}

(:ddatetofl::timestamp -  interval '1 second') + interval '1 day'

{endif}

)

group by account.waccountid,account.SAccountcode

having sum(transact.FAmount ) <> 0


union all
```

```
select 0,'ZZZZZZZZ' , 0 from rdb$database

order by 2
```

Changed lookup section of ACCLIST to

Changed to

```
and SAccountcode <= trim(substring('@SACCOUNTCODETOTX  ' {ssfrom} 2 {ssfor} {iif}

({pos} (' ' {posin} '@SACCOUNTCODETOTX  ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETOTX
')-1)) )

and SAccountcode >= trim(substring('@SACCOUNTCODETX  ' {ssfrom} 2 {ssfor}

IIF ({pos} (' ' {posin} '@SACCOUNTCODETX  ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETX
')-1)))
```

Created with the Standard Edition of HelpNDoc: Free Web Help generator

FIXED-Reports

FIXED - After osFinancials5.1.0.127 update / osFinancials5.1.0.189 update - Details / Notes and screenshots

excelreports

osf.ini file : " *nounocode=true* " setting prints in Firebird database types and MSSQL database types.

Retested in osFinancials5.1.0.127 and osFinancials5.1.0.189 update on Spreadsheet reports menu.

Fixed file Excluded from osFinancials5.1.0.189 update. Firebird error replicated in all updates since osfinancials5.1.0.93.

Fixed firebird error in Spreadsheet reports → Sales analysis → Sales per period

Location : ...\plug_ins\reports\excelreports\TRN_85\TRN_906122\trn_1296.sql

```
Dynamic SQL Error
SQL error code = -104
Token unknown - line 8, column 60
)
```

NOTE : Can print in MSSQL Databases Replicated since osF5.1.0.49 up to osFinancials5.1.0.127

Fixed SQL - Removed the double closing bracket form line 60

> "group by {if interbase}Extract(year from ddate),Extract(month from ddate){else}Year(ddate),Month(ddate) {endif}"

- now it prints in both MSSQL and Firebird

```
select {if interbase}Extract(year from ddate){else}Year(ddate) {endif}
TRN_901022_Year,

{if interbase}Extract(month from ddate){else}Month(ddate) {endif} TRN_901019_MONTH ,

 sum(fdocamount) TRN_1866_IncAmt,

 sum(FTAXAMOUNT) TRN_1138_TaxAmt,

 sum(fdocamount-FTAXAMOUNT) TRN_1200_ExcAmt

 from dochead where

<@DDATE@>

group by {if interbase}Extract(year from ddate),Extract(month from ddate){else}
Year(ddate),Month(ddate) {endif}
```

FIXED = Removed Bracket (duplicated) in col60 of line 8

systemreports (Fixes to be updated)

osf.ini file : " *nounocode=true* " setting prints in Firebird database types and MSSQL database types.

These systemreports have been updated and included in osFinancials5.1.0.109.

Retested in osFinancials5.1.0.127 on Reports menu (systemreports folder) some minor fixes regarding overlapping labels and consistency in 7 reports were fixed -

Alignment headings and detail - Debtors listing

Reports → Debtors → Listing - List delivery address - Location : ...
\plug_ins\reports\systemreports\TRN_160\TRN_66\TRN_906138.rep

Reports → Debtors → Listing - List postal address - Location : ...
\plug_ins\reports\systemreports\TRN_160\TRN_66\TRN_906139.rep

Alignment headings and detail - Creditors listing

Reports → Creditors → Listing - List delivery address - Location : ...

\plug_ins\reports\systemreports\TRN_161\TRN_66\TRN_906138.rep

Reports → Creditors → Listing - List postal address - Location : …

\plug_ins\reports\systemreports\TRN_161\TRN_66\TRN_906139.rep

Stock - In/Out - Show details - Overlapping labels

Reports → Stock → Stock In / Out - Stock in / Out

Location : …\plug_ins\reports\systemreports\TRN_1999\TRN_906112

Before fix



After fix

Moved Quantity, Cost price, Selling price / Cost price and Document type to right

Added line break in Selling price / Cost price expression

Set Auto expand/ Auto Contract and Word wrap



Documents - Document listing - Overlapping labels

Reports → Documents → Document listing

Location : ...\plug_ins\reports\systemreports\TRN_38\TRN_45\TRN_45.rep

Before fix



After fix

Added // in descriptions and expressions Your reference Link tax - to Your reference // Link tax

This is to be consistent with other tax reports (e.g. Tax - Transactions and Tax report - Reference / Document no.) and easier on the eye to separate the fields.



Tax - Tax per period

Reports → Tax - Tax per period

Location : .../plug_ins\reports\systemreports\TRN_906020\TRN_906020

Before fix



After fix

Added // in descriptions and expressions Code / Description Country / Tax reference - to Your reference // Link tax

This is to be consistent with other tax reports (e.g. Tax - Transactions and Tax report - Reference / Document no.) and easier on the eye to separate the fields.



STOCK - Sidebar reports -

STOCK - Sidebar reports - Stock movement

Stock movement report (Stock turnover)

Renamed text report name to LANG_906038 to be translatable via the language files. Added report name "*Stock movement - Average cost - Grid*" in Header section.

Total print on Page 2 and Total - Data type = Currency as " ##,###,###,##0.00" in Detail of Group section (e.g. 1,000.00) - Set the Group footer data type for the Total (e.g. 1000.00) to display similar than the Detail

report section.

Location : ...\plug_ins\reports\REPORTS\STOCK\Stock Movement.rep New location : ... \plug_ins\reports\REPORTS\STOCK\LANG_906038.rep with translated file name.

Fixed - Total print on Page 2



Fixed 2 - Total - Data type = Currency as " ##,###,###,##0.00" in Detail of Group section (e.g. 1,000.00) - Set the Group footer data type for the Total (e.g. 1000.00) to display similar than the Detail report section.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

FIXED - Graphs - Posted and Confirmed Quotes and Orders

Quotes / Orders Posted / Confirmed on Reports

To be consistent with Sales reports (Quotes) and Purchase reportsOeders) Graphs should also include posted and confirmed quotes but excludes open (unconfirmed) quotes

```
where dochead.BPosted = 1
```

Changed to include posted and confirmed quotes but excludes open (unconfirmed) quotes

```
where dochead.BPosted in (1,-1)
```

Posted - Status

1. 0 – Invoices and Credit notes are not yet posted (updated) to the ledger.
2. 0 – Quotes are not yet confirmed (Converted to an Invoice).
3. 1 – Invoices and Credit notes are posted (updated) to the ledger.

4. 1 – Quotes are confirmed (Converted to an Invoice).
5. -1 - Quotes which are still open.

```
where dochead.BPosted = 1
```

Changed to include posted and confirmed quotes but excludes open (unconfirmed) quotes

```
where dochead.BPosted in (1,-1)
```

Location - Graphs for Quotes and orders in the User reports menu:

Graphs → Graphs per week → Sales menu:

Location : ...\plug_ins\reports\userreports\TRN_906557\TRN_906558\TRN_1792\TRN_3568

Quotes per week

TRN_906323 - Graph - Quotes per week - Quantities

TRN_906324 - Graph - Quotes per week - Amount

Graphs → Graphs per week → Purchases menu:

Location : ...\plug_ins\reports\userreports\TRN_906557\TRN_906558\TRN_302\TRN_3572

Orders per week

TRN_906325 - Graph - Orders per week - Quantities

TRN_906326 - Graph - Orders per week - Amount

Graphs → Graphs per month → Sales menu:

Location : ...\plug_ins\reports\userreports\TRN_906557\TRN_906559\TRN_1792\TRN_3568

Quotes per month

TRN_906563 - Graph - Quotes per month - Quantities

TRN_906564 - Graph - Quotes per month - Amount

Graphs → Graphs per month → Purchases menu:

Location : ...\plug_ins\reports\userreports\TRN_906557\TRN_906559\TRN_302\TRN_3572

Orders per month

TRN_906573 - Graph - Orders per month - Amount

TRN_906574 - Graph - Orders per month - Quantities

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

FIXED - MSSQL Graphs per Month - Axis labels (Axis titles)

Graphs per week - Graphs per month - X and Y axis values labels (titles)

ORDER BY

2, 1, 3;

FIXED - ORDER 1,2,3

ORDER is 1 = YEAR, 2 = MONTH, 3= TOTAL

Changed from 1,2,3 to 1,2 (YEAR, MONTH)



year , month , type (2,3,1)

FIXED PRINT - X and Y axis values labels correct



Order by 1,2,3 (Type, Year Month) or 2,1,3 (Year, Type, Month)

If order is set to 2,3,1 (Year, Month. Type) it prints as follows:



a

BUG - BEFORE FIXES

Example - MSSQL Graphs per Month - Axis labels (Axis titles)

Firebird databases - All Graphs per week and Graphs per month reports prints correct values in Firebird databases.

In MSSQL databases - All Graphs per week and Graphs per month reports prints incorrect values in the X-axis and Y-axis.

The Reason for this is that MSSQL is case sensitive and needs WEEK, MONTH, YEAR to be in the UPPERCASE to print the correct values in MSSQL database types.

Example Graphs per month - 204121 Should display the month and year e.g. 202103, 202104 , 202105, 202106, etc. like in Firebird databases

Example Graphs per month - 204121 Should display the week and year e.g. 09 for first week March , etc. like in Firebird databases



DOCUMENTLINE SQL Graphs per month -> Graph - Profit / Loss per month - SQL

```
SELECT 1 WTYPEID,

{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,

sum(-transact.FAMOUNT) Total

FROM transact  join account on transact.Waccountid = Account.Waccountid  and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT > 0

group by

{if interbase}extract(year from ddate){else}year(ddate){endif} ,

{if interbase}extract(month from ddate){else}month(ddate){endif}

union

SELECT 2 WTYPEID,
```

```
{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,

sum(-transact.FAMOUNT) Total

FROM transact  join account on transact.Waccountid = Account.Waccountid  and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT < 0

group by

{if interbase}extract(year from ddate){else}year(ddate){endif} ,

{if interbase}extract(month from ddate){else}month(ddate){endif}

order by 2,1,3
```

Changed the needs MONTH, YEAR to be in the UPPERCASE to print the correct values in MSSQL database types

```
SELECT 1 WTYPEID,

{if interbase}extract(YEAR from ddate){else}YEAR(ddate){endif} dyear,

{if interbase}extract(MONTH from ddate){else}MONTH(ddate){endif} dmonth,

sum(-transact.FAMOUNT) Total

FROM transact  join account on transact.Waccountid = Account.Waccountid  and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT > 0

group by

{if interbase}extract(YEAR from ddate){else}YEAR(ddate){endif} ,

{if interbase}extract(MONTH from ddate){else}MONTH(ddate){endif}

union

SELECT 2 WTYPEID,
```

```
{if interbase}extract(YEAR from ddate){else}YEAR(ddate){endif} dyear,

{if interbase}extract(MONTH from ddate){else}MONTH(ddate){endif} dmonth,

sum(-transact.FAMOUNT) Total

FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT < 0

group by

{if interbase}extract(YEAR from ddate){else}YEAR(ddate){endif} ,

{if interbase}extract(MONTH from ddate){else}MONTH(ddate){endif}

order by 2,1,3
```

Error - dmonth - = YYYY

Changed to UPPERCASE and changed year to month

```
{if interbase}extract(MONTH from ddate){else}MONTH(ddate){endif} dmonth,
```



Changelog - Graphs per month (TRN_906559)

Location : ...\plug_ins\reports\userreports\TRN_906557\TRN_906559\

Changed the needs MONTH, YEAR to be in the UPPERCASE to print the correct values in MSSQL database types in all Graph per month reports

Graphs per month (TRN_906559) - File names

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
Ledger	TRN_1372				
		Graph - Profit Loss per month	TRN_906560.rep		
Debtors	TRN_160				
		Graph - Debtors per month	TRN_906561.rep		
Creditors	TRN_161				
		Graph - Creditors per month	TRN_906562.rep		
Sales	TRN_1792				
	Quotes per period	TRN_3568			
		Graph - Quotes per month - Quantities	TRN_906563.rep		
		Graph - Quotes per month - Amount	TRN_906564.rep		
	Credit notes per period	TRN_3569			
		Graph - Credit notes per month -	TRN_906565.rep		

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
		Quantities			
		Graph - Credit notes per month - Amount	TRN_906566.rep		
	Invoices per period	TRN-3570			
		Graph - Invoices per month - Quantities	TRN_906567.rep		
		Graph - Invoices per month - Amount	TRN_906568.rep		
	Sales per period	TRN_906122			
		Graph - Invoices - Credit notes per month - Quantities	TRN_906569.rep		
		Graph - Invoices - Credit notes per month - Amount	TRN_906570.rep		
Purchases		TRN_302			
	Purchases				
		Graph - Purchases - Supplier returns per month - Quantities	TRN_906571.rep		
		Graph - Purchases - Supplier returns per month - Amount	TRN_906572.rep		
	Orders per period				
		Graph - Orders per month - Quantities	TRN_906574.rep		
		Graph - Orders per month - Amount	TRN_906573.rep		

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
	Supplier returns per period				
		Graph - Supplier returns per month - Quantities	TRN_906576.rep		
		Graph - Supplier returns per month - Amount	TRN_906575.rep		
	Purchases per period				
		Graph - Purchases per month - Quantities	TRN_906578.rep		
		Graph - Purchases per month - Amount	TRN_906577.rep		

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with a Help Authoring Tool

FIXED - Graphs per week - 'WEEK' is not a recognized built-in function name.

SCOPE - X-axis and Y-axis labels Graphs per week

MSSQL - X-axis and Y-axis - fixed



MSSQL - X-axis and Y-axis - incorrect



DOCUMENTLINE Dataset SQL - DATEPART - It s the line 3 DATEPART in SQL and related lines

```
{if interbase}extract(week from ddate){else}datepart(week,ddate){endif}  week,
```

Firebird database types

In Firebird database types, the Graph - Profit / Loss per week - displays the week number on the x-axis - correctly



Firebird - DOCUMENTLINE Dataset - Show Data - correct



MSSQL database types

In MSSQL database types, the Graph - Profit / Loss per week - displays the Year instead of the week number on the x-axis - incorrectly



Existing SQL - DOCUMENTLINE DATASET

```
SELECT 1 WTYPEID,

{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,

{if interbase}extract(week from ddate){else}year(ddate){endif} week,

sum(-transact.FAMOUNT) Total

FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1

where
```

```
(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)
and transact.FAMOUNT > 0
group by
{if interbase}extract(year from ddate){else}year(ddate){endif} ,
{if interbase}extract(month from ddate){else}month(ddate){endif} ,
{if interbase}extract(week from ddate){else}datepart(week,ddate){endif}
union
SELECT 2 WTYPEID,
{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,
{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,
{if interbase}extract(week from ddate){else}year(ddate){endif} week,
sum(-transact.FAMOUNT) Total
FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1
where
(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)
and transact.FAMOUNT < 0
group by
{if interbase}extract(year from ddate){else}year(ddate){endif} ,
{if interbase}extract(month from ddate){else}month(ddate){endif} ,
{if interbase}extract(week from ddate){else}datepart(week,ddate){endif}
order by 1,2,3
```

MSSQL - DOCUMENTLINE Dataset - Show Data - incorrect



MONTH (Originally "dmonth" was showing the Year value "2021")

Changing YEAR to MONTH (2nd line)

```
{if interbase}extract(MONTH from ddate){else}YEAR(ddate){endif} dmonth,
```

to

```
{if interbase}extract(MONTH from ddate){else}MONTH(ddate){endif} dmonth,
```

After changes - displays "dmonth" was showing the Month value "03" for March, etc.)

WEEK

Changing YEAR to WEEK + add datepart (3rd line)

```
{if interbase}extract(week from ddate){else}year(ddate){endif} week,
```

to

```
{if interbase}extract(week from ddate){else}datepart(week,ddate){endif} week,
```

Updated DOCUMENTLINE SQL

NOTE - For year, month, datepart week UPPERCASE / lowercase no effect on results in SQL foe Firebird database types and MSSQL database types

```
SELECT 1 WTYPEID,

{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}month(ddate){endif} dmonth,

{if interbase}extract(week from ddate){else}datepart(week,ddate){endif} week,

sum(-transact.FAMOUNT) Total

FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT > 0

group by

{if interbase}extract(year from ddate){else}year(ddate){endif} ,

{if interbase}extract(month from ddate){else}month(ddate){endif} ,

{if interbase}extract(week from ddate){else}datepart(week,ddate){endif}

union

SELECT 2 WTYPEID,

{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,

{if interbase}extract(week from ddate){else}datepart(week,ddate){endif} week,

sum(-transact.FAMOUNT) Total

FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1

where

(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)

and transact.FAMOUNT < 0

group by

{if interbase}extract(year from ddate){else}year(ddate){endif} ,

{if interbase}extract(month from ddate){else}month(ddate){endif} ,

{if interbase}extract(week from ddate){else}datepart(week,ddate){endif}

order by 1,2,3
```

TESTS - AFTER FIXES in DATABASES

MSSQL

Database MY-BOOKS-MSSQL-B

Graph - Profit /Loss per week



Order by 1,2,3

It probably has to do with SELECT 1 WTYPEID, and SELECT 2 WTYPEID,

year , month , week, type

order by 2,3,4,1


Database connections and datasets
Connections
Datasets
Parameters
COMPANYDATA
DOCUMENTLINE
Connection
SETOFBOOKS
Master dataset
Open on start
Show data
SQL
Database browser
SETOFBOOKS
where
(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)
and transact.FAMOUNT > 0
group by
{if interbase}extract(YEAR from ddate){else}YEAR(ddate){endif},
{if interbase}extract(MONTH from ddate){else}MONTH(ddate){endif} ,
{if interbase}extract(WEEK from ddate){else}DATEPART(WEEK,ddate){endif}
union
SELECT 2 WTYPEID,
{if interbase}extract(YEAR from ddate){else}YEAR(ddate){endif} dyear,
Data
WTYPEID 2
dyear 2021
dmonth 3
week 10
Total 1100
{if interbase}extract(WEEK from ddate){else}DATEPART(WEEK,ddate){endif}
order by 2,3,4,1
OK
Cancel


Report manager designer-C:\osfinancials5\plug_ins\reports\userreports\TRN_906557\TRN_906558\TRN_1372\TRN_906169.rep
MY-BOOKS-MSSQL-B
ADDRESS1 90 1234567890 1234567
ADDRESS2 90 1234567890 1234567
ADDRESS3 90 1234567890 1234567
12345678
Company reg. no.: CR34567890123456789012345678 90
Tax reg. no.: CR34567890123456789012345678 90
Phone:
Fax:
E-mail: EMAIL567890123456789012345678901234567890123456789012345
Website: WEB4567890123456789012345678901234567890123456789012345
Graph - Profit / Loss per week
Period:
2021/03/01 - 2022/02/28
2021
25,000
20,000
15,000
10,000
5,000
0
10
11
12
19
26
27
2021 - Income
2021 - Expenses
2021 - Income
2021 - Expenses
2021 - Income
Income 115,800.00
Expenses -1,850.00
Net Profit/Loss 113,950.00

Graph - Creditors per week



Graph - Sales per week / Graph - Sales per week (Invoices - credit notes)



FIREBIRD

Database : HELPDEMO



Database HULP-AFR



Changelog - File names - Graphs per week (TRN_906558)

Menu item	*Sub-menu item 1*	*Internal folder name / Report name*	*Internal report name*	*Classic theme*	*Material theme*
Ledger	*TRN_1372*				
		Graph - Profit Loss per week	*TRN_906169.rep*		
Debtors	*TRN_160*				
		Graph - Debtors per week	*TRN_906168.rep*		
Creditors	*TRN_161*				
		Graph - Creditors per week	*TRN_906167.rep*		

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
Sales	TRN_1792				
	Quotes per period	TRN_3568			
		Graph - Quotes per week - Quantities	TRN_906323.rep		
		Graph - Quotes per week - Amount	TRN_906324.rep		
	Credit notes per period	TRN_3569			
		Graph - Credit notes per week - Quantities	TRN_906319.rep		
		Graph - Credit notes per week - Amount	TRN_906320.rep		
	Invoices per period	TRN-3570			
		Graph - Invoices per week - Quantities	TRN_906170.rep		
		Graph - Invoices per week - Amount	TRN_906171.rep		
	Sales per period	TRN_906122			
		Graph - Invoices - Credit notes per week - Quantities	TRN_906579.rep		
		Graph - Invoices - Credit notes per week - Amount	TRN_906580.rep		
Purchases		TRN_302			
	Purchases				

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
		Graph - Purchases - Supplier returns per week - Quantities	TRN_906581		
		Graph - Purchases - Supplier returns per week - Amount	TRN_906582		
	Orders per period				
		Graph - Orders per week - Quantities	TRN_906325.rep		
		Graph - Orders per week - Amount	TRN_906326.rep		
	Supplier returns per period				
		Graph - Supplier returns per week - Quantities	TRN_906321.rep		
		Graph - Supplier returns per week - Amount	TRN_906322.rep		
	Purchases per period				
		Graph - Purchases per week - Quantities	TRN_906289.rep		
		Graph - Purchases per week - Amount	TRN_906290.rep		

Created with the Standard Edition of HelpNDoc: Keep Your PDFs Safe from Unauthorized Access with These Security Measures

FIXED-ADDED - Layout files

Uploads for fixes to languages and layout files

languages location : " ...\bin\languages "

document layout files location = ...\plug_ins\reports\DOCUMENTS\DOCUMENTS

FIXED LAYOUT FILES

See Examples and notes on Layout files in Documentation - Document layout files.

% instead of Discount%

Document layout TRN_3174 refers to % instead of Discount percentage (Changed % to "CUSTOM('GETTEXTLANG',1865,'Discount',ACCOUNTINFO.SLANGUAGE,0,0)"

Added Unit descriptions to layout file

Added: SUNIT Dataset

```
Select * from unit where cast(WUnitid as  char(10)) = :SUNIT
```

Added Unit Label in Layout file headings

Unit label not translating

layout file TRN_1910

```
CUSTOM('GETTEXTLANG',1131,'Unit',ACCOUNTINFO.SLANGUAGE,0,0)
```

Changed to

```
CUSTOM('GETTEXTLANG',1131,'Qty',CLIENTORDEFLANG.SLANGUAGE,0,0)
```

MSSQL Layout file translations

In Firebird document layout files changes the description if you do a Switch Language

In MYSQL databases the document layout files does not change the labels when you Switch language. It only changes when the Language for Debtor / Creditor is selected it seems great working in both databases

In MSSQL "CUSTOM('GETTEXTLANG',1710,'Qty',CLIENTORDEFLANG.SLANGUAGE,0,0)" expressions is supported.

Feature to these debtor statement creditor remittance advise reports

In MSSQL all reports prints in Debtor Statements and Creditor remittance advises - Should we add the CLIENTORDEFLANG feature to these debtor statement creditor remittance advise reports yo print the reports in the Language selected for Debtor / Creditor account

So they can receive the statements and remittance advices in their preferred language like the receive layout files?

to 'GETTEXTLANG',1710,'Qty',CLIENTORDEFLANG.SLANGUAGE,0,0) the selected language.

POS in Dutch + POS translatable TRN_906184

When selecting the POS it only prints the Dutch version

To solve this change the language description to POS 1 (LanguageID 906184) from POS to POS 1 so both layouts can be selected.

ADDED LAYOUT FILES for NO TAX and Labels for report names

If you are not required to register for VAT/GST/Sales Tax due to not meeting the compulsory threshold, or if you've chosen not to voluntarily register as a vendor for such taxes, you have the option to use specific document layout files that exclude any VAT/GST/Sales Tax components:

1. NO-TAX Layout File TRN_906589
2. NO-TAX Document Layout TRN_906590
3. NO-TAX Document Layout (15 Code) TRN_906591

ALSO ADDED an English Document layout file for NO-TAX

1. NO-TAX Invoice - English
2. GEEN-BTW Faktuur

The "NO-TAX Invoice" layout file is designed as a straightforward layout file featuring fixed text labels in the English language. Unlike translatable expressions enabled by language files and settings in osFinancials5/TurboCASH5, this layout utilizes static text labels. The document pulls data from various fields entered during the document processing phase, and it establishes connections to tables and expressions within the Database fields to present the data accurately.

Use these and the Tax versions to Help tutorials as to get started with static text labels - then use these to introduce dynamic expressions for translation.

Layout files added (Previous releases after osF5 (Build 453)

TRN_1313 - Delivery note

Added Translation of stock descriptions to Delivery note for Multi-language accounts

TRN_1313 - Delivery note was not translating stock descriptions for Multi-language accounts - Other invoices translated the stock description in layout files

All layout files - After using Multi-language translations of Types (Customise language DOCTYPES seems not to print on those layout files in other Sets of Books

```
trim(TYPES.SDESCRIPTION)+':  '+(DOCUMENTHEAD.SDocNo)
```

TRN_1910 - Layout file

(for all document types (Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders).

Added layout file with the following fixes



Supports

Translations

Multi language

Multiple tax rates

Unit added

Comments - long

Remarks - long

Currency

Fixed longer messages in footer last Message 3 overlaps

Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

FIXED-ADDED - Stock In / Out reports - Document reference number (Show details)

Stock In / Out reports (Reports menu)

When documents are generated using Stock adjustments, BOM Production (Assemble / Disassemble) and Project quote, the detail for these transactions is included in the "*Your reference*" field of the posted documents screen. For example, if Stock adjustments is processed, this report needs to indicate the remarks entered in the "*Change remarks*" screen (e.g. Surplus / Shortage or Auto correction).

Added Document reference number to the Show details option on the following reports:

Location : plug_ins\reports\systemreports\TRN_1999\TRN_906112

- Reports → Stock - Stock in / Out → Documents (TRN_38)
- Reports → Stock - Stock in / Out → Stock In / Out (TRN_906112)

This will display the document reference and specifically display the details for documents generated using stock adjustments, BOM Production (Assemble / Disassemble) and Project quote.

Stock adjustments	*+ Surplus* *- Shortage* *+ / - Auto correction*	*ST00001, etc. - Document numbers - Auto prefixed with ST followed by seven (7) numerical digits.* *Stock adjustments - Remarks entered in the "Change remarks" screen (e.g. Surplus / Shortage or Auto correction).*
Stock in / Stock+	*Stock+*	*SI00001, etc. - Document numbers - Auto prefixed with SI followed by seven (7) numerical digits.*
Disassemble - BOM (Production)	*+*	*BOM (Production) stock item type - Disassemble option on context menu.* *SA00001, etc. - Document numbers - Auto prefixed with SA followed by seven (7) numerical digits.*
Assemble - BOM (Production)	*-*	*BOM (Production) stock item type - Assemble option on context menu.* *SA00001, etc. - Document numbers - Auto prefixed with SA followed by seven (7) numerical digits.*

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

FIXED-ADDED - Stock sidebar reports - Report - Print single item

Stock sidebar reports - Report - Print single item

Changelog - Report button - Print single item context menu

Stock sidebar reports - Print single item context menu

Location : ...\plug_ins\reports\REPORTS\STOCK

The following reports are now translatable, report names (also translatable) tidied word wrap, headers and footers.

Report name language id	*Report name*	*Description*	*Notes*
LANG_906584	*Production list*	*Production list report lists the transactions of all items (other stock item types) linked to the BOM and BOM (Production) stock item type on the BOM tab.*	*New report*
LANG_906585	*Stock item list - Active stock*	*The "Stock item listing - Active stock" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. Only active (enabled) Stock items will be listed. Inactive (disabled) Stock items not will be listed.*	*New report* *Added - Unit type*
LANG_84	*Stock item listing*	*The "Stock item listing" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. All active (enabled) Stock items as well as inactive (disabled) Stock items will be listed.*	*Added - Unit type* *Disabled Yes / No*

LANG_1774	Barcode	The "Barcode" report prints barcodes for all stock items or a selected stock item.	
LANG_906040	Yagoda barcode	The "Yagoda barcode" report prints Yagoda barcodes for all stock items or a selected stock item.	
LANG_1323	Reporting group 1	The Reporting group 1 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.	Added - Disabled Yes / No Removed: Column Number to words for Selling price 2 - IIF(STR(VOORRAAD.VerkoopPrijs2)='','',CUSTOM('NUMBERTOWORDS',VOO

			RRAAD.VerkoopPrijs2,'','',''))
LANG_1325	Reporting group 2	The Reporting group 2 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.	Added - Disabled Yes / No Removed: Column Number to words for Selling price 2 - IIF(STR(VOORRAAD.VerkoopPrijs2)='','',CUSTOM('NUMBERTOWO

			RDS', VOORRAAD.VerkoopPrijs2,'','','','',''))
LANG_906031	*Historical value*	*The "Historical value" report The Reporting group 1 for stock items, will list the Stock code, Stock description, Quantities and Total value for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.*	*Deleted - Replaced - Historische waarde.rep* *Added - Disabled Yes / No* *Fixed - Changed SQL to Reporting group 1 from Reporting group 2 in*

			VOORRAAD data set
LANG_906033	Outstanding orders	The Unconfirmed orders report will list all outstanding orders, which is not yet confirmed (converted to a purchase document). This report will list all unconfirmed orders for each creditor (supplier / vendor) account by order number, order date stock quantities, stock item code, stock item description and document reporting group 1.	Print single item - prints all unconfirmed orders and items.
LANG_906034	Outstanding quotes	The Unconfirmed quotes report will list all outstanding quotes, which is not yet confirmed (converted to invoices). This report will list all unconfirmed quotes for each debtor (customer / client) account by quote number, quote date stock quantities, stock item code, stock item description and document reporting group 1.	Print single item - prints all unconfirmed quotes and items.
LANG_906036	Reorder quantities	The "Reorder quantities" report will list the Stock code, Stock description, Quantity, and Average cost price selected stock item.	
LANG_906038	Stock movement	The "Stock movement" report will list the Stock code, Stock	Rena

		description, Quantity on hand, Unposted Invoices/Purchases, Reorder level and quantity to order for each stock item.	*med Stock movement report text name to LANG_906038 for report name to be translatable via language files*
LANG_906039	*Transaction details*	*The "Transaction details" report list the document date (and time, if available) document number, document type, quantities, salesperson and document reference for each stock item.*	*Deleted - Replaced - Transaction Details.rep and transactie details.rep* *Added -*

Disabled

Yes / No

Added - Document reference - this will list the document references, including those for:

- *Stockadjustments - R*

e m a r k s e n t e r e d i n t h e " C h a n g e r e m a r k s " s c r e e n (e .

g. Surplus/Shortage or Autocorrection).

- BOM (P

r o d u c t i o n) s t o c k i t e m t y p e - A s s e m b l e / D i s a s s e m b

			Ieoptiononcontextmenu.
LANG_906588	*Value stock account*	*The "Value stock account" report lists the total value of the stock control account. If the "Show details" option is selected, it will list the the value of each stock item.*	
LANG_902008	*Price list - Large retail - Sales*	*The "Price list - Large retail - Sales" report will list quantity discount up to five (5) price levels for your debtors (customers / clients).*	*Deleted: Prijzenlijst groothandel and Price List - Large Retail*

			Added: Price levels 4 and 5 (was only supporting 3 price levels.
LANG_902008	*Price list - Large retail - Purchases*	*The "Price list - Large retail - Purchases" report will list quantity discount up to five (5) price levels for your creditors (suppliers / vendors).*	*New report: Price levels up to 5 - for purchases (Creditor / Supplier Vendor) accounts.*

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

FIXED - Reports - Location-Serials-Batches

FIXED - Reports - Location-Serials-Batches

Reports → Plugins → Location-Serials-Batches reports menu.

See Documentation - Serials-Batches-Location plugin

Location : ...plug_ins\reports\systemreports\TRN_1805\TRN_3398

```
CUSTOM('GETTEXTLANG',3398,'Batch-serials-batches',0,0,0)+ ' - '+CUSTOM('GETTEXTLANG',906555,'Batch purchased from Creditor',0,0,0)+ ' - '+CUSTOM('GETTEXTLANG',1777,'On hand',0,0,0)
```

```
CUSTOM('GETTEXTLANG',3398,'Batch-serials-batches',0,0,0)+ ' - '+CUSTOM('GETTEXTLANG',906556,'Batch sold to Debtor',0,0,0)+ ' - '+CUSTOM('GETTEXTLANG',1777,'On hand',0,0,0)
```

Removed - On hand - + ' - '+CUSTOM('GETTEXTLANG',1777,'On hand',0,0,0) from report name. This is not on hand but report shows the quantities sold or quantities purchased from suppliers.

Also set HEADER - BATCH to print headings on second and consecutive pages. Also fixed this in other Serials-Batches-Location-reports.

Retested in Firebird databases in osF5.1.0.99 and MSSQL in osF5.1.0.93.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's User-Friendly UI

FIXED - Reports - Price agreement

Price Agreement Plugin reports

See - Price Agreement Plugin

FIXED - TRN_3380 Price agreement

Reports → Plugins → Price agreement

Location : ...plug_ins\reports\systemreports\TRN_1805\TRN_3380\TRN_906035

Location : ...plug_ins\reports\systemreports\TRN_1805\TRN_3380\TRN_906088

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/systemreports/TRN_1805/TRN_3380

Updated on GIT - 2020/02/22

		Error	Comments
TRN_906035.rep	*Debtor – Price agreement*	*Type conversion error 'Val':Expression TRpExpression2*	*Click OK on error and select Debtor*
TRN_906088.rep	*Creditor – Price agreement*	*Type conversion error 'Val':Expression TRpExpression2*	*Click OK on error and select Creditor*

Stock sidebar reports - Report - Print single item

FIXED and Added similar reports to the Stock sidebar reports - Report - Print single item context menu.

Location : ...\plug_ins\reports\REPORTS\STOCK

Location on GitHub : https://github.com/Digidanosf/osfinancials-development/tree/main/reports/plug_ins/reports/REPORTS/STOCK

The following reports are now translatable, report names (also translatable) tidied word wrap, headers and footers.

Report name language id	*Report name*	*Description*	*Notes*
LANG_902008	*Price list - Large retail - Sales*	*The "Price list - Large retail - Sales" report will list quantity discount up to five (5) price levels for your debtors (customers / clients).*	*Deleted: Prijzenlijst groothandel and Price List - Large Retail* *Added: Price*

			levels 4 and 5 (was only supporting 3 price levels.
LANG_902009	*Price list - Large retail - Purchases*	*The "Price list - Large retail - Purchases" report will list quantity discount up to five (5) price levels for your creditors (suppliers / vendors).*	*New report: Price levels up to 5 - for purchases (Creditor / Supplier / Vendor) accounts.*

Created with the Standard Edition of HelpNDoc: Transform your help documentation into a stunning website

FIXED - Creditor Remittance advice - Not printing postal address

Creditor Remittance advice - Outstanding - not printing postal address

FIXED - Reports → Creditor Remittance Advises - Outstanding

This error crept in when converted reports supported only Firebird database types to support both MSSQL and Firebird database types.

Between osFinancials5.1.0.49 and fixed in osFinancials5.1.0.81

Location : ...\plug_ins\reports\systemreports\TRN_161\TRN_1089\TRN_906551

Changed "ACCOUNTLOOKUP" dataset sql from debtor to creditor

Now

```
SELECT  creditor.SDELIVERY1
,creditor
.SDELIVERY2
,creditor
.SDELIVERY3
,creditor
.SDELIVERYCODE
,creditor
.SWebsite
,creditor
.FCreditLimit
,creditor
.SMessage
,creditor
.SFreeField1
,creditor
.SFreeField2
,creditor
.SFreeField3
,creditor
.SBankName
,creditor
.SBankAccountName
,creditor
.WTransmissionType
,creditor
.SCreditCardNumber,creditor.SCreditCardHolder,creditor.DExpiryDate,dc.COUNTRIES_NAME
delcountry,pc.COUNTRIES_NAME  poscountry,  account.SDescription,  account.SAccountCode,
```

```
SPostal1,

  SPostal2,SPostal3, SPostalCode, STelephone1, STelephone2,

  SFax, SEmail, SBranchCode, SBankAccountNumber,

   DLastActivity, SReference, WDueDays,account.WAccountID,Firstname , LastName,
Groups1.SDescription GroupDesc1,Groups1.WSortNo GroupSort1, Groups2.SDescription
GroupDesc2, Groups2.WSortNo GroupSort2

,Groups1.WColor,Groups1.WTextColor,

account.WReportingGroup2ID,SCompanyRegNo

  FROM creditor JOIN account ON (creditor.WAccountID = account.WAccountID) left OUTER
 JOIN Contacts Contacts

    ON (creditor.WContactID = Contacts.RecordID)

    left JOIN Groups Groups2 ON (account.WReportingGroup2ID = Groups2.WGroupID)

    left JOIN Groups Groups1 ON (account.WReportingGroup1ID = Groups1.WGroupID)

    left JOIN COUNTRIES pc on pc.COUNTRIES_ID = creditor.WPOSTCOUNTRIES_ID

    left JOIN COUNTRIES dc on dc.COUNTRIES_ID = creditor.WDELCOUNTRIES_ID

    where account.WAccountId = :Waccountid

Order by 19
```

Was

```
SELECT debtor.SDELIVERY1 ,debtor.SDELIVERY2,debtor.SDELIVERY3,
debtor
.SDELIVERYCODE
,debtor
.SWebsite
,debtor
.FCreditLimit
,debtor
.DRemittance
,debtor
.SMessage,debtor.SFreeField1,debtor.SFreeField2,debtor.SFreeField3,dc.COUNTRIES_NAME
delcountry,pc.COUNTRIES_NAME poscountry, account.SDescription, account.SAccountCode,
SPostal1,

  SPostal2,SPostal3, SPostalCode, STelephone1, STelephone2,

  SFax, SEmail, SBranchCode, SBankAccountNumber,

   DLastActivity, SReference, WDueDays,account.WAccountID,Firstname , LastName,
```

```
Groups1.SDescription  GroupDesc1,Groups1.WSortNo  GroupSort1,  Groups2.SDescription
GroupDesc2,  Groups2.WSortNo  GroupSort2

,Groups1.WColor,Groups1.WTextColor,

account.WReportingGroup2ID,SCompanyRegNo

  FROM debtor JOIN account ON  (debtor.WAccountID  =  account.WAccountID) left OUTER
JOIN Contacts Contacts

    ON  (debtor.WContactID  =  Contacts.RecordID)

    left JOIN Groups Groups2 ON  (account.WReportingGroup2ID  =  Groups2.WGroupID)

    left JOIN Groups Groups1 ON  (account.WReportingGroup1ID  =  Groups1.WGroupID)

    left JOIN COUNTRIES pc on pc.COUNTRIES_ID  =  debtor.WPOSTCOUNTRIES_ID

    left JOIN COUNTRIES dc on dc.COUNTRIES_ID  =  debtor.WDELCOUNTRIES_ID

    where  account.WAccountId  =  :Waccountid

Order by 14
```

Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

FIXED - Report Batch type - Documents Static redundant Expression in Page-HEADER

Batch entry – Documents report

Report Batch type - Documents Static redundant Expression in Page-HEADER

The Batch type - Documents report refers to Sales batch when Purchase Batch is also listed (TRN_298\TRN_38) - Removed TRpExpression73

Batch type is duplicated on the REPORTHEAD static - Header- Doc included for document type



Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

FIXED - Access violation errors - Reports menu

Ledger - Listing - Chart of Accounts

TRN_1372 - TRN_73

Access violation at address 76F77C63 in module 'ntdll.dll'. Read of address 11FE5000

Contacts

Before the Print button on the Contacts (screen) on the Default ribbon was not printing.

Access violation errors fixed.

Reports → Contacts produced access violation errors

> Access violation at address 76F77C63 in module 'ntdll.dll'. Read of address 0AFEF000

Click OK then the report prints

Could not replicate them after GIT is merged

Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

FIXED - Budget vs actual + This year vs Last year budgetvsactsimple.rep

---

Budget vs actual + This year vs Last year budgetvsactsimple.rep

Fixed in TurboCASH5.2 (build 240) - Need to check and add report to osF5

Used the budgetvsactsimple.rep in osFinancials - Seems fixed in osFinancials - see

Budget vs actual

This year vs last year



Code	Name						
G010000	Sales						
G100000	Cost of sales						
G200000	Bank charges						
G205000	Depreciation						
G210010	Fuel and oil						
G210020	Maintenance						
G210030	Repairs						
G220000	Rent						
G225000	Salaries and wages						
G230000	Stationery						
G505000	Capital						
G600010	Furniture fittings @ cost						
G600020	Furniture fittings -Acc. depre						
G610020	Motor vehicles -Accum. depr						
G700000	Debtors control						
G750000	Stock control						
B810000	ABC - Bank						
B820000	Petty cash						
T860010	Output VAT - 15%						
T860020	Input VAT - Standard rate -1						
T860030	Input VAT - Capital goods -15%	120.00	0.00	0.00	0.00	-120.00	100.00
G900000	Creditors control	0.00	9,025.00	0.00	0.00	9,025.00	100.00
	Net Profit/Loss	0	9,905.00		57,800.00	-47,895.00	
	Totals		0.00		57,800.00	-57,800.00	

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

FIXED - Reports - GENERAL/documents

Changes to reports - GENERAL/documents

paycreditor.rep

TRN_906449 - Automatic payments report (changed report name from Creditor payments report) to be

consistent with paycreditor.rep (it can also include refunds to debtors

TRN_906097 - Automatic receipts report

batch.rep

List batch - Unposted batch (launched from F8:List icon on Batch entry screens)

Date timestamp overlapping with Reference column - Changed Word wrap to True



Created with the Standard Edition of HelpNDoc: Elevate Your Help Documentation with a Help Authoring Tool

FIXED - Reports - Projects

Projects reports

Location : .... \ plug_ins\reports\REPORTS\PROJECTS

Changed LANG_ to TRN_ displays translated report names in titlebars of reports

Language ID	*Report name*

1.	*TRN_27*	*Stock Item*
2.	*TRN_354*	*Statement*
3.	*TRN_960*	*Total*
4.	*TRN_2330*	*Hours*
5.	*TRN_20069*	*Transactions*

Tidied Headers and Footers (standardised with system reports)

Added report names

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

FIXED - Due Ageing

Added the 3 old age analysis reports in TurboCASH5.1 and osFinancials4 to Reports menu → Debtors and Creditors menu

Moved: Age analysis reports to support Debtor Statements and Creditor Remittance advices from the User reports menu to Reports menu.

The Help → Update option when a stable release of osFinancials is updated in TurboCASH5.2 it does not clash with osFinancials source in the "*system reports*" folder.

Age analysis reports osFinancials 4 / TurboCASH5.1 vs TurboCASH5.2

As from TurboCASH5.2 / osFinancials5 – the age analysis reports were changed as follows:

- Age analysis reports which were on the Reports → Debtors and Reports → Creditors menu, have been dropped.
- The Age analysis on the Reports ribbon was introduced. This age analysis report lists all non-open-item accounts; if the Date of ageing - “Current date” is changed to a selected date.

Discontinued Debtor / Creditor ageing reports in osFinancials4 added in TurboCASH5.2

Since osFinancials / TurboCASH4, TurboCASH5.1 / osFinancials4 the age analysis reports were included in all releases.

Added the following age analysis reports in TurboCASH5.2 (which were excluded from osFinancial5 releases) in the User reports menu.

See MODULE P - OPENITEM PROCESSING of Accounting Made Easy

These ageing reports are in addition to the one on the (Reports ribbon)

TRN_160 Debtors → TRN_65 Age analysis

Report name	*Report description*
TRN_906142.rep	*Balances detail*
TRN_906143.rep	*Balances detail history (open item)*
TRN_906147.rep	*Balances*

TRN_161 Creditors → TRN_65 Age analysis

Report name	*Report description*
TRN_906142.rep	*Balances detail*
TRN_906143.rep	*Balances detail history (open item)*
TRN_906147.rep	*Balances*

NOTE

These ageing reports adds different options, views and details to the Debtor statement and Creditor remittance advises on the Reports menu.

Age analysis (Reports ribbon)

This Age analysis option on the Reports ribbon is also available on the Due tab of Open item (Default ribbon)

openitemdays.rep (... \ plug_ins \ reports \ GENERAL \ ledgerview)

Added - Report name (updated on osFGit 2020/12/27)

65 - Age analysis added report name for the openitemdays.rep

Comments column

COR - Corrections of missing transactions

Label 3692 Correction transaction ageing (before was Correction of missing transactions)

Maybe need to change it to

Add Non-open item account balances / or maybe better ADD BB/F account balances.

Date option selected reverts back to the Date option does not save or change the data

Date of ageing = Current date lists only the Accounts set as open item:

Date of ageing = Current date lists only the Accounts set as open item:



Account type	Account	Name	Description	Reference	Date	Due date	Org amount	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+	Comments
D	1ABGRE	Mr. AB Green	Paint - Exterior	INV003	2020/03/10	2020/04/09		300.00	300.00				
D	1ABGRE	Mr. AB Green	Invoice /AB-IN110	IN000001	2020/03/13	2020/04/12		1,150.00	1,150.00				
D	1ABGRE	Mr. AB Green	Invoice /PH-101	IN000003	2020/03/15	2020/04/14		1,150.00	1,150.00				
D	1MDAVI	Mr. Mike Davies	Debtor opening balances - Dec 2019	JNL2	2019/12/31	2020/01/30		100.00				100.00	
D	1MDAVI	Mr. Mike Davies	Debtor opening balances - Jan 2020	JNL2	2020/01/31	2020/03/01		200.00			200.00		
D	1MDAVI	Mr. Mike Davies	Debtor opening balances - Feb 2020	JNL2	2020/02/29	2020/03/30		500.00		500.00			
D	1MDAVI	Mr. Mike Davies	Install - Built-in cupboard	INV004	2020/03/12	2020/04/11		1,725.00	1,725.00				
D	1MDAVI	Mr. Mike Davies	Invoice /IB-102	IN000004	2020/03/16	2020/04/15		1,725.00	1,725.00				
D	1MDAVI	Mr. Mike Davies	Invoice /D-101	IN000005	2020/04/07	2020/05/07		1,150.00	1,150.00				
D	1MDAVI	Mr. Mike Davies	Invoice /C-103	IN000007	2020/04/10	2020/05/10		1,725.00	1,725.00				
	10							9725.00	8925.00	500.00	200.00	100.00	

Date of ageing = Selected date - e.g. System date = 2020/04/01 and selected date of ageing = 2020/04/01 lists all the Accounts set as open item as well as non open item accounts.

The example in this database; Debtors and Creditors - set as Open item on the "*Accounting information*" tab.:

- Debtors - only two debtor accounts (i.e. "*AB Green*" and "*Mike Davies*") and
- Creditors – only two creditor accounts (i.e. "*ABC Office Supplies*" and "*A-One Suppliers*"),

For the non open item accounts, it adds COR in the description and Corrections with the Amount.

Selecting a date



In this database no Ledger accounts is set to Open item. If the Ledger option is selected, and selected date of ageing = 2020/04/01, it lists all ledger account balances



See MODULE P - OPENITEM PROCESSING

These ageing reports are in addition to the one on the (Reports ribbon)

TRN_160 Debtors → TRN_65 Age analysis

	TC5	*osF5*

TRN_906142. rep	*Balances detail*	
TRN_906143. rep	*Balances detail history*	*Renamed to Balances detail (open item)*
TRN_906144. rep	*Outstanding Open item Transaction Totals*	*Removed in TC5 and unpublished in help*
TRN_906145. rep	*Outstanding Transaction Totals*	*Removed in TC5 and unpublished in help*
TRN_906147. rep	*Balances*	
TRN_906148. rep	*Balances - Detail1*	*Removed in TC5 and unpublished in help*

TRN_161 Creditors → TRN_65 Age analysis

		TC5	*osF5*
TRN_906142. rep	*Balances detail*		
TRN_906143. rep	*Balances detail history*	*Renamed to Balances detail (open item)*	
TRN_906144. rep	*Outstanding Open item Transaction Totals*	*Removed in TC5 and unpublished in help*	
TRN_906145. rep	*Outstanding Transaction Totals*	*Removed in TC5 and unpublished in help*	
TRN_906147. rep	*Balances*		
TRN_906148. rep	*Balances - Detail1*	*Removed in TC5 and unpublished in help*	

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

FIXED - Debtor statements Period 2 includes Period 1

Debtor statements Period 2 includes Period 1

Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090 - Debtor statement

FIXED in osFinacials5.1.0.102

TRpExpression 37 changed to

```
IIF(ALIASLOCATE('TRANSACTIONSPERIODE2','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRANSACTIONSPERIODE2.FAMOUNT,0)-
IIF(ALIASLOCATE('TRANSACTIONSPERIODE1','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRANSACTIONSPERIODE1.FAMOUNT,0)
```

from

```
IIF(ALIASLOCATE('TRANSACTIONSPERIODE2','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRANSACTIONSPERIODE2.FAMOUNT,0)
```

If this is changed then Firebird balances (seems fixed), but MSSQL is out in PERIOD2

The transaction on 1 April for PERIOD1 is also Included in PERIOD2 Double count.


Report manager designer-C:\osfinancials5\plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090.rep
Mr. Mike Davies
P O Box 333
Halfway House
1685
FIREBIRD Database
Handyman Hardware Store
27 Olifants Road
Emmarentia
Johannesburg
2195
Phone: (011) 310-1390
Fax: (011) 310-2000
E-mail: mymail@myisp.net
Website: osfinancials.org
Company reg. no.: 336012345
Tax reg. no.: 446010111
Account no. : D1MDAVI
Contact : Mike Davies
Tax reg. no. : 336012345
Company reg. no. : 543212345
Telephone 1 : (011) 315-1225
Telephone 2 : 083 286-8763
Fax : (011) 315-1226
E-mail : mike@hismail.com
Website : osfinancials.org/erv
Statement
Page: 1
Statement to: 2023/04/30
Period 1 : 2023/04/30
Period 2 : 2023/03/31
Period 3 : 2023/03/01
Due amount: 7,125.00
Due date: 2023/05/30
Date Reference Description Amount Payment date
2023/02/28 Opening Opening Period3 800.00 2023/03/30
2023/03/11 INV004 Install - Built-in cupboard Period2 1,725.00 2023/04/10
2023/03/16 IN000004 Invoice /B-102 1,725.00 2023/04/15
2023/04/07 IN000005 Invoice /D-101 Period1 1,150.00 2023/05/07
2023/04/10 IN000007 Invoice /C-103 1,725.00 2023/05/10
Due amount Period 1 (30) Period 2 (30) Period 3 (60) +
7,125.00 2,875.00 3,450.00 800.00
TRpExpression 37 changed to
IIF(ALIASLOCATE
('TRANSACTIONSPERIODE2','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRANSACTIONSPERIODE2.
FAMOUNT,0)-
IIF(ALIASLOCATE
('TRANSACTIONSPERIODE1','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRANSACTIONSPERIODE1.
FAMOUNT,0)
from
IIF(ALIASLOCATE
('TRANSACTIONSPERIODE2','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRANSACTIONSPERIODE2.
FAMOUNT,0)



Period 2 + Period 1 in Period 2 total



Debtor statements - Outstanding Incorrect reports needs to be fixed once period2 is resolved -

Location : plug_ins\reports\systemreports\TRN_161\TRN_1090\TRN_1089 - Creditor remittance advises

Location : plug_ins\userreports\userreports\TRN_160\TRN_906142 - Balances detail

Location : plug_ins\reports\userreports\TRN_160\TRN_906147 - Balances

Location : plug_ins\userreports\userreports\TRN_161\TRN_906142 - Balances detail

Location : plug_ins\reports\userreports\TRN_161\TRN_906147 - Balances

NOTE : Location : plug_ins\reports\systemreports\TRN_160\TRN_1090 \TRN_906552 - Debtor statement - Outstanding is correct for Period 2= 3450

Debtor statements Outstanding + Creditor remittance advices - Outstanding + Age analysis - Fixed MSAQL and Firebird - fixed reports (to upload)

Location : plug_ins\reports\userreports\TRN_160\TRN_906143 - Balances detail history (open item)

Location : plug_ins\reports\systemreports\TRN_161\TRN_1090 \TRN_906551 - Creditor remittance advises

- Outstanding

Location : plug_ins\reports\userreports\TRN_161\TRN_906143 - Balances detail history (open item)

Old Debtor statement before fixed to MSSQL and After Fix to MSSQL - Correct



Open item duedays.rep is correct

Age analysis on the Due tab supports up to 4 periods for ageing - Period 3 on Age analysis of 800.00 is correct on Debtor statements - Outstanding report but is correctly broken down to 4 periods (e.g. Period 3 = 700.00 and period 4 = 100.00

Open item duedays.rep - Current date



openitemdays

Age analysis - Due report

Date of report: 2023/04/30 — Date of ageing: Current date

D1ABGRE Mr. AB Green	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
NV003 Paint - Exterior	2023/03/10	2023/04/09	300.00	0.00	300.00	0.00	0.00
N000001 Invoice /AB-IN110	2023/03/13	2023/04/12	1,150.00	0.00	1,150.00	0.00	0.00
N000003 Invoice /PH-101	2023/03/15	2023/04/14	1,150.00	0.00	1,150.00	0.00	0.00
Total			2,600.00	0.00	2,600.00	0.00	0.00

D1MDAVI Mr. Mike Davies	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
JNL2 Debtor opening balances - Dec 2022	2022/12/31	2023/01/30	100.00	0.00	0.00	0.00	100.00
JNL2 Debtor opening balances - Jan 2023	2023/01/31	2023/03/02	200.00	0.00	0.00	200.00	0.00
JNL2 Debtor opening balances - Feb 2023	2023/02/28	2023/03/30	500.00	0.00	0.00	500.00	0.00
NV004 Install - Built-in cupboard	2023/03/11	2023/04/10	1,725.00	0.00	1,725.00	0.00	0.00
N000004 Invoice /IB-102	2023/03/16	2023/04/15	1,725.00	0.00	1,725.00	0.00	0.00
N000005 Invoice /D-101	2023/04/07	2023/05/07	1,150.00	1,150.00	0.00	0.00	0.00
N000007 Invoice /C-103	2023/04/10	2023/05/10	1,725.00	1,725.00	0.00	0.00	0.00
Total			7,125.00	2,875.00	3,450.00	700.00	100.00
Total			**9,725.00**	**2,875.00**	**6,050.00**	**700.00**	**100.00**

Open item duedays.rep - Selected date of ageing



openitemdays

Age analysis - Due report

Date of report: 2023/04/30 — Date of ageing: 2023/04/30

D1ABGRE Mr. AB Green	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
NV003 Paint - Exterior	2023/03/10	2023/04/09	300.00	0.00	300.00	0.00	0.00
N000001 Invoice /AB-IN110	2023/03/13	2023/04/12	1,150.00	0.00	1,150.00	0.00	0.00
N000003 Invoice /PH-101	2023/03/15	2023/04/14	1,150.00	0.00	1,150.00	0.00	0.00
Total			2,600.00	0.00	2,600.00	0.00	0.00

D1MACDS MAC Shop Decor Specialists	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
Correction transaction ageing COR	2023/04/30	2023/04/30	2,450.00	2,450.00	0.00	0.00	0.00
Total			2,450.00	2,450.00	0.00	0.00	0.00

D1MDAVI Mr. Mike Davies	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
JNL2 Debtor opening balances - Dec 2022	2022/12/31	2023/01/30	100.00	0.00	0.00	0.00	100.00
JNL2 Debtor opening balances - Jan 2023	2023/01/31	2023/03/02	200.00	0.00	0.00	200.00	0.00
JNL2 Debtor opening balances - Feb 2023	2023/02/28	2023/03/30	500.00	0.00	0.00	500.00	0.00
NV004 Install - Built-in cupboard	2023/03/11	2023/04/10	1,725.00	0.00	1,725.00	0.00	0.00
N000004 Invoice /IB-102	2023/03/16	2023/04/15	1,725.00	0.00	1,725.00	0.00	0.00
N000005 Invoice /D-101	2023/04/07	2023/05/07	1,150.00	1,150.00	0.00	0.00	0.00
N000007 Invoice /C-103	2023/04/10	2023/05/10	1,725.00	1,725.00	0.00	0.00	0.00
Total			7,125.00	2,875.00	3,450.00	700.00	100.00

D1ROGSM Mr. Roger Smith	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
Correction transaction ageing COR	2023/04/30	2023/04/30	6,750.00	6,750.00	0.00	0.00	0.00
Total			6,750.00	6,750.00	0.00	0.00	0.00
Total			**18,925.00**	**12,075.00**	**6,050.00**	**700.00**	**100.00**

The SQL changes in Debtor statements old Firebird and Changed for MSSQL

Only Firebird

```
SELECT
 sum(transact.FAmount ) FAmount,
account.WAccountID
FROM transact
   LEFT OUTER JOIN account
   ON  (transact.WAccountID =
account.WAccountID)
WHERE WAccountTypeId  = 1
and (transact.DDate <
 (:DDATEFL{if
postgresql}::timestamp{endif} -
((periode1){if postgresql} || '
DAY'{endif}){if
postgresql}::interval{endif})
 and transact.DDate >=
 (:DDATEFL{if
postgresql}::timestamp{endif} -
((periode1+periode2){if postgresql} || '
DAY'{endif}){if
postgresql}::interval{endif})


)
group by
account.WAccountID
having   sum(transact.FAmount ) <> 0
```

Prints in Firebird and MSSQL - P2 incorrect

```
SELECT
 sum(transact.FAmount ) FAmount,
account.WAccountID
FROM transact
   LEFT OUTER JOIN account
   ON  (transact.WAccountID =
account.WAccountID)
WHERE WAccountTypeId  = 1
and (transact.DDate <
  dateadd(day,periode1,:DDATEFL)
 and transact.DDate >=
 dateadd(day,-
(periode1+periode1),:DDATEFL)


)
group by
account.WAccountID
having   sum(transact.FAmount ) <> 0
```

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

FIXED - Spreadsheet reports – Transactions per period

Spreadsheet reports – Transactions per period

If a Spreadsheet report Sheet tab in the base.xlsx ("Excel 2007 -365") spreadsheet file is named in the lowercase (e.g. trn_1296) instead of the uppercase (e.g. TRN_1296) the label will not translate and populate with the data.

An additional sheet with the translated label "*Data*" is added. The osFinancials5 code now supports the uppercase / lowercase.

(Transactions per period (Spreadsheet report .../excelreports\TRN_20069\TRN_3314)



Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

FIXED - Reports - Support for MSSQL database types - March 2022

FIXED - Spreadsheet - Reports - Stock → Sales Analysis (Reports ribbon)

Location : plug_ins\reports\excelreports\TRN_85\TRN_906122\trn_1296.sql

Firebird error

> Dynamic SQL Error
> SQL error code = -104
> Token unknown - line 8, column 60

FIXED - Spreadsheet reports - Stock → Sales per period

NOTE - before we fixed for MSSQL = Populates the Spreadsheet in MSSQL Database

plug_ins\reports\excelreports\TRN_85\TRN_906122\trn_1296.sql

Fixed SQL - Removed the double closing bracket form "line 60 group by {if interbase}Extract(year from ddate),Extract(month from ddate){else}Year(ddate),Month(ddate) {endif}" - now it prints in both MSSQL and Firebird

```
select {if interbase}Extract(year from ddate){else}Year(ddate) {endif}
TRN_901022_Year,

{if interbase}Extract(month from ddate){else}Month(ddate) {endif} TRN_901019_MONTH ,

 sum(fdocamount) TRN_1866_IncAmt,

 sum(FTAXAMOUNT) TRN_1138_TaxAmt,

 sum(fdocamount-FTAXAMOUNT) TRN_1200_ExcAmt

 from dochead where

<@DDATE@>

group by {if interbase}Extract(year from ddate),Extract(month from ddate){else}
Year(ddate),Month(ddate) {endif}
```

FIXED = Removed Bracket (duplicated) in col60 of line 8

Old Firebird SQL

```
select Extract(year from ddate) TRN_901022_Year,

Extract(month from ddate) TRN_901019_MONTH ,

 sum(fdocamount) TRN_1866_IncAmt,

 sum(FTAXAMOUNT) TRN_1138_TaxAmt,

 sum(fdocamount-FTAXAMOUNT) TRN_1200_ExcAmt

 from dochead where

<@DDATE@>

group by Extract(year from ddate),Extract(month from ddate)
```

FIXED - Age analysis (Reports ribbon)

Location : /plug_ins/reports/GENERAL / ledgerview / openitemdays.rep

Error - PARAMS:Invalid column name 'current_connection'.

FIXED - MSSQL Errors - Spreadsheet reports

Location : /plug_ins/reports/excelreports

Transactions → Per period

Error :

> Incorrect syntax near '|'.

Current SQL

```
case  Mainaccount.WACCOUNTTYPEID  when 0 then
'G'   when 1 then 'D'   when 2 then 'C'    when 3 then
'B' else 'T' end || coalesce(Mainaccount.SMAINACCOUNTCODE,'') ||
coalesce(Mainaccount.SSUBACCOUNTCODE,'')  TRN_34,
Mainaccount.SDESCRIPTION  TRN_1213,
```

Changed to

```
case  Mainaccount.WACCOUNTTYPEID  when 0 then
'G'   when 1 then 'D'   when 2 then 'C'    when 3 then
'B' else 'T' end ,'') {concat}  coalesce(Mainaccount.SMAINACCOUNTCODE,'') {concat}
coalesce(Mainaccount.SSUBACCOUNTCODE,'')  TRN_34,
Mainaccount.SDESCRIPTION  TRN_1213,
```

Sales analysis → Sales per period - Error

Error :

> 'Extract' is not a recognized built-in function name.

Current SQL

```
select Extract(year from ddate)  TRN_901022_Year,
Extract(month from ddate)  TRN_901019_MONTH  ,
 sum(fdocamount)  TRN_1866_IncAmt,
```

```
 sum(FTAXAMOUNT)  TRN_1138_TaxAmt,

 sum(fdocamount-FTAXAMOUNT)  TRN_1200_ExcAmt

 from dochead where

<@DDATE@>

group by Extract(year from ddate),Extract(month from ddate)
```

Changed to

```
select {if  interbase}Extract(year from ddate){else}Year(ddate) {endif}
TRN_901022_Year,

{if  interbase}Extract(month from ddate){else}Month(ddate) {endif}  TRN_901019_MONTH  ,

 sum(fdocamount)  TRN_1866_IncAmt,

 sum(FTAXAMOUNT)  TRN_1138_TaxAmt,

 sum(fdocamount-FTAXAMOUNT)  TRN_1200_ExcAmt

 from dochead where

<@DDATE@>

group by {if  interbase}Extract(year from ddate),Extract(month from ddate)){else}
Year(ddate),Month(ddate) {endif}
```

FIXED = ASCII_CHAR Changed to {char}

General Ledger → Budget → Column balances → Reporting group1

General Ledger → Budget → Column balances → This year

General Ledger → Column balances → Reporting group1

General Ledger → Column balances → This year

FIXED SQL

ASCII_CHAR

Changed To

{char}

Used Notepad++ to change the SQL in plug_ins\ reports \ excelreports folder

Seems to fix this error



FIXED - MSSQL Errors - Reports menu

Location : /plug_ins/reports/system/reports

Calendar

HOURES:Invalid column name 'minuteduration'.

```
Select events.*,

cast (events.STARTTIME as time) xstarttime,

cast(ENDTIME as time)  xendtime,

dochead.Sdocno,

{if postgresql}

 (DATE_PART('day', ENDTIME::timestamp - STARTTIME::timestamp) * 24 +
```

```
                DATE_PART('hour', ENDTIME::timestamp - STARTTIME::timestamp)) * 60 +

                DATE_PART('minute', ENDTIME::timestamp - STARTTIME::timestamp)
```

Changed to

```
Select events.*,

cast (events.STARTTIME as time) xstarttime,

cast(ENDTIME as time)  xendtime,

dochead.Sdocno,

datediff (minute {ssfrom} STARTTIME {if interbase}in {else},{endif} ENDTIME)
minuteduration

from events

left join dochead on cast(dochead.Wdocid as char(100)) = events.userfield1

where events.STARTTIME  >=  :DDATEFROMFL

and events.STARTTIME  <=  :DDATETOFL

order by resourceid , events.STARTTIME
```

Debtors / Creditor Listing reports

ACCOUNTS:Incorrect syntax near '|'.

Ledger → Budget

CONTACTS:Incorrect syntax near the keyword 'for'.

Debtors → Listing - Contacts

Creditors → Listing - Contacts

ACCOUNT:Incorrect syntax near the keyword 'for'.

Debtors → Listing - Listing (Rest of 6 listing reports)

Creditors → Listing - Listing (Rest of 6 listing reports)

TRANSACTION_DETAIL:Incorrect syntax near the keyword 'for'.

Debtors → Transactions - Transaction list

Creditors → Transactions - Transaction list

Ledger → Transactions (systemreports\TRN_1372\TRN_74/TRN_74.rep

Existing SQL

```
and account.SAccountcode <= trim(substring('@SACCOUNTCODETOTX ' from 2 for {if mysql}
if{else}IIF{endif}(position (' ' in '@SACCOUNTCODETOTX ')=0,0,position (' ' in
'@SACCOUNTCODETOTX ')-1)) )

and account.SAccountcode >= trim(substring('@SACCOUNTCODETX ' from 2 for {if mysql}
if{else}IIF{endif}(position (' ' in '@SACCOUNTCODETX ')=0,0,position (' ' in
'@SACCOUNTCODETX ')-1)))
```

NOTE and or where = if sql stars with and - all accounts is listed - If starts with where only selected account will be listed

Changed to

```
and SAccountcode <= trim(substring('@SACCOUNTCODETOTX ' {ssfrom} 2 {ssfor} {iif}

({pos} (' ' {posin} '@SACCOUNTCODETOTX ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETOTX
')-1)) )

and SAccountcode >= trim(substring('@SACCOUNTCODETX ' {ssfrom} 2 {ssfor}

IIF ({pos} (' ' {posin} '@SACCOUNTCODETX ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETX
')-1)))
```

Price agreement

CREDITLOOKUP:Incorrect syntax near '|'.

Creditor - Price agreement

FIXED

```
select Saccountcode Code,SaccountCode {concat} ' ' {concat} sdescription SDescription
from account where waccountTypeid = 2
```

Debtor - Price agreement

FIXED

```
select Saccountcode Code,SaccountCode {concat} ' ' {concat} sdescription SDescription
from account where waccountTypeid = 1
```

Ledger - Control accounts - SQL error

Ledger → Transactions - Standard

Ledger → Transactions - Extra details

systemreports\TRN_1372\TRN_74/TRN_906110.rep + TRN_906111.rep



No accounts can be selected - Books created as MSSQL Database type

but prints

Parameters = SQL

```
Select

WRetainedINCOMEID  Id
,Account.SAccountcode  ||' ' ||
SDescription{if
postgresql}::varchar(255){endif}
aName

from Sysvars join account on
account.Waccountid  =
WRetainedINCOMEID
```

Changed to

```
Select

WRetainedINCOMEID  Id
,Account.SAccountcode  {concat}'
'  {concat}SDescription  aName

from Sysvars join account on
account.Waccountid  =
WRetainedINCOMEID
```

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

FIXED - Reports - 8x3 Digit account codes - Reports

8x3 Digit accounts - Reports Test

On some reports, if the Chart of Accounts consisting of 8-digit main accounts and 3-digit sub-accounts is created with the "*Customise your own Set of Books (Advanced)?*" option, and transactions and data is processed, the reports, seemed to have many overlapping columns and text on the printouts. In the

Report designer, these reports were realigned, and properties of expressions changed, where necessary.

The following tables (highlighted with yellow text) indicates the changelog of reports which is fixed.

Reports menu = plug_ins\reports\systemreports\

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Notes / Added	FIXED
Ledger			TRN_1372			
	Budget		TRN_1027			
			Budget vs actual (3 periods)	TRN_3372.rep		
	Listing		TRN_66			
			Chart of Accounts	TRN_73.rep		FIXED
	Transactions		TRN_74			
			Transactions	TRN_74.rep		
			Transactions - Standard	TRN_906110.rep		
			Transactions - Extra details	TRN_906111.rep		
Debtors			TRN_160			
	Debtor statement		TRN_1090			
			Debtor Statements	TRN_1090.rep		
			Debtors statement - Outstanding	TRN_906552.rep		
	Listing		TRN_66			
			Contacts	TRN_2876.rep		FIXED
			Listing	TRN_66.rep	+ ' ' + ACCOUNT.SPOSTALCODE	FIXED

					Added , between Expressions	
			List delivery address	TRN_906138.rep		FIXED
			List postal address	TRN_906139.rep		FIXED
			List details	TRN_906140.rep		FIXED
			Credit control listing (Credit limit vs Current balance)	TRN_906338.rep		FIXED
			Tax and Company registration numbers	TRN_906339.rep		FIXED
	Print labels		TRN_68			
			Delivery address labels	TRN_906064.rep		
			Postal address labels	TRN_906137.rep		
	Transactions		TRN_74			
			Transactions	TRN_74.rep		FIXED
			Transaction List - Open item	TRN_906061.rep		FIXED
			Transactions - Standard	TRN_906106.rep		
			Transactions - Extra details	TRN_906107.rep		
			Transaction List	TRN_906440.rep		FIXED
Creditors			TRN_161			
	Creditor remittance advises		TRN_1089			

			Creditor remittance advise	TRN_1089.rep		
			Creditor remittance advise - Outstanding	TRN_906551.rep		
	Listing		TRN_66			
			Contacts	TRN_2876.rep		FIXED
			Listing	TRN_66.rep	+ ' ' + ACCOUNT.SPOSTALCODE Added , between Expressions	FIXED
			List delivery address	TRN_906138.rep		FIXED
			List postal address	TRN_906139.rep		FIXED
			List details	TRN_906140.rep		FIXED
			Credit control listing (Credit limit vs Current balance)	TRN_906338.rep		FIXED
			Tax and Company registration numbers	TRN_906339.rep		FIXED
	Print labels		TRN_68			
			Delivery address labels	TRN_906064.rep		
			Postal address labels	TRN_906137.rep		
	Transactions		TRN_74			
			Transactions	TRN_74.rep		FIXED
			Transaction List - Open item	TRN_906061.rep		FIXED
			Transactions - Standard	TRN_906108.re		

				p		
			Transactions - Extra details	TRN_906109.rep		
			Transaction List	TRN_906440.rep		FIXED
Sales			TRN_1792			
	Quotes		TRN_1870			
		Debtors	TRN_160			
			Quotes per period - Quantities	TRN_906315.rep		
		Sales	TRN_1792			
			Quotes per period - Quantities	TRN_906315.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
	Invoices		TRN_300			
		Debtors	TRN_160			
			Invoices per period - Quantities	TRN_906155.rep		
		Sales	TRN_1792			
			Invoices per period - Quantities	TRN_906155.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
	Credit notes		TRN_47			
		Debtors	TRN_160			

			Credit notes per period - Quantities	TRN_906311.rep	Set account code + Description to Font size 10 (was 11) In line with similar reports	FIXED
		Sales	TRN_1792			
			Credit notes per period - Quantities	TRN_906311.rep	Added missing Code + Item description - column headings	FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
Plugins			TRN_1805			
	Price agreement		TRN_3380			
			Debtor – Price agreement	TRN_906035.rep		
			Creditor – Price agreement	TRN_906088.rep		
	Location-Serials-Batches		TRN_3398			
			On hand	TRN_1777.rep		
			Stock movement	TRN_906038.rep		
			Outdated batch	TRN_906554.rep		
			Batch bought from supplier	TRN_906555.rep		
			Batch sold to customer	TRN_906556.rep		

Stock		TRN_1999			
	Reorder	TRN_1778			
		Reorder report	TRN_83.rep		
		Current stock levels	TRN_906268.rep		
	Print labels	TRN_68			
		Barcode	TRN_1774.rep		
		Yagoda barcode	TRN_906040.rep		
	Stock item listing	TRN_84			
		All selling prices	TRN_1056.rep		
		Tax classes	TRN_3465.rep		FIXED
		Stock item listing	TRN_84.rep		
	Backorder	TRN_906050			
		Backorder	TRN_906050.rep		
	Stock In / Out	TRN_906112			
		Stock In / Out - Documents	TRN_38.rep		
		Stock In / Out	TRN_906112.rep		
Point-of-Sale		TRN_2200			
	Standard	TRN_1990			
		Sales	TRN_1792.rep		
		Receipts	TRN_182.rep		
	Cash slip printer	TRN_906160			

			Sales	TRN_1792.rep		
			Receipts	TRN_182.rep		
Contacts			TRN_2876			
			Contacts	TRN_2876.rep		FIXED
Calendar			TRN_2879			
			Hours	TRN_2330.rep		
Batch entry			TRN_298			
			Documents	TRN_38.rep		FIXED
			Batch transactions per period	TRN_906141.rep		FIXED
Purchases			TRN_302			
	Purchase documents		TRN_1269			
		Creditors	TRN_161			
			Purchases per period - Quantities	TRN_906150.rep	Set account code + Description to Font size 10 (was 11) In line with similar reports	FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep	Shrink unnecessary space	FIXED
		Purchases	TRN_302			
			Purchases per period - Quantities	TRN_906150.rep	Shrink unnecessary space	FIXED
	Orders		TRN_1871			

		Creditors	TRN_161			
			Orders per period - Quantities	TRN_906317.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep	Shrink unnecessary space	FIXED
		Purchases	TRN_302			
			Orders per period - Quantities	TRN_906317.rep	Align Stock description with Description heading + Shrink unnecessary space	FIXED
	Supplier returns		TRN_303			
		Creditors	TRN_161			
			Supplier returns per period - Quantities	TRN_906313.rep	Set account code + Description to Font size 10 (was 11) In line with similar reports	FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep	Shrink unnecessary space	FIXED
		Purchases	TRN_302			
			Supplier returns per period - Quantities	TRN_906313.rep		
Company info			TRN_320			

			Bank accounts	TRN_183.rep		
			Information	TRN_629.rep		
Currencies			TRN_3470			
			Currencies	TRN_3470.rep		
Documents			TRN_38			
	Document listing		TRN_45			
			Document listing	TRN_45.rep	Description word wrap	FIXED
	Document listing per account		TRN_906161			
		Sales documents	TRN_1268			
			Invoices	TRN_300.rep		FIXED
			Quotes	TRN_418.rep		FIXED
			Credit notes	TRN_706.rep		FIXED
		Purchase documents	TRN_1269			
			Purchases	TRN_302.rep		FIXED
			Supplier returns	TRN_303.rep		FIXED
			Orders	TRN_798.rep		FIXED
	Unprinted document listing		TRN_906162			
		Sales documents	TRN_1268			
			Invoices	TRN_300.rep		FIXED

			Quotes	TRN_418.rep		FIXED
			Credit notes	TRN_706.rep		FIXED
		Purchase documents	TRN_1269			
			Purchases	TRN_302.rep		FIXED
			Supplier returns	TRN_303.rep		FIXED
			Orders	TRN_798.rep		FIXED
Sales analysis			TRN_85			
	Quotes per period		TRN_3568			
			Quotes per period - Debtor group 1	TRN_906301.rep		FIXED
			Quotes per period - Debtor group 2	TRN_906302.rep		FIXED
			Quotes per period - Document group 1	TRN_906303.rep		FIXED
			Quotes per period - Document group 2	TRN_906304.rep		FIXED
			Quotes per period - Salesperson	TRN_906305.rep		FIXED
	Invoices per period		TRN_3570			
			Invoices per period - Debtor group 1	TRN_906157.rep		FIXED
			Invoices per period - Debtor group 2	TRN_906158.rep		FIXED
			Invoices per period - Document group 1	TRN_906159.rep		FIXED
			Invoices per period - Document group 2	TRN_906165.rep		FIXED

		Invoices per period - Salesperson	TRN_906166.rep		FIXED
	Credit notes per period	TRN_3569			
		Credit notes per period - Debtor group 1	TRN_906291.rep		FIXED
		Credit notes per period - Debtor group 2	TRN_906292.rep		FIXED
		Credit notes per period - Document group 1	TRN_906293.rep		FIXED
		Credit notes per period - Document group 2	TRN_906294.rep		FIXED
		Credit notes per period - Salesperson	TRN_906295.rep		FIXED
	Sales per product	TRN_3571			
		Sales per product - Stock group 1	TRN_906174.rep		
		Sales per product - Stock group 2	TRN_906175.rep		
	Sales per period	TRN_906122			
		Sales per period - Debtor group 1	TRN_906332.rep		FIXED
		Sales per period - Debtor group 2	TRN_906333.rep		FIXED
		Sales per period - Document group 1	TRN_906334.rep		FIXED
		Sales per period - Document group 2	TRN_906335.rep		FIXED
		Sales per period - Salesperson	TRN_906336.rep		FIXED
Tax		TRN_906020			

			Transactions	TRN_20069.rep		FIXED
			Tax list debtor with tax id	TRN_3675.rep		FIXED
			Tax per period	TRN_906105.rep		
			Tax report - Reference / Document no.	TRN_906550.rep		FIXED
			Tax list creditor with tax id	TRN_906553.rep		FIXED
Purchase analysis			TRN_977			
	Orders per period		TRN_3572			
			Orders per period - Creditor group 1	TRN_906306.rep		FIXED
			Orders per period - Creditor group 2	TRN_906307.rep		FIXED
			Orders per period - Document group 1	TRN_906308.rep		FIXED
			Orders per period - Document group 2	TRN_906309.rep		FIXED
			Orders per period - Salesperson	TRN_906310.rep		FIXED
	Purchases per period		TRN_3573			
			Purchases per period - Creditor group 1	TRN_906152.rep		FIXED
			Purchases per period - Creditor group 2	TRN_906153.rep		FIXED
			Purchases per period - Document group 1	TRN_906154.rep		FIXED
			Purchases per period - Document group 2	TRN_906163.rep		FIXED

		Purchases per period - Salesperson	TRN_906164.rep		FIXED
	Supplier returns per period	TRN_3574			
		Supplier returns per period - Creditor group 1	TRN_906296.rep		FIXED
		Supplier returns per period - Creditor group 2	TRN_906297.rep		FIXED
		Supplier returns per period - Document group 1	TRN_906298.rep		FIXED
		Supplier returns per period - Document group 2	TRN_906299.rep		FIXED
		Supplier returns per period - Salesperson	TRN_906300.rep		FIXED
	Purchases per product	TRN_3575			
		Purchases per product - Stock group 1	TRN_906172.rep		
		Purchases per product - Stock group 2	TRN_906173.rep		
	Purchases and Supplier returns per period	TRN_906337			
		Purchases documents per period - Creditor group 1	TRN_906327.rep		FIXED
		Purchases documents per period - Creditor group 2	TRN_906328.rep		FIXED
		Purchases documents per period - Document group 1	TRN_906329.rep		FIXED
		Purchases documents per period - Document group 2	TRN_906330.rep		FIXED
		Purchases documents per period - Salesperson	TRN_906331.rep		FIXED

User reports menu = plug_ins\reports\userreports

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
Custom reports					
			2cred-sku-det.rep		
			2deb-sku-det.rep		
Ledger		TRN_1372			
	Graph	TRN_1091			
		Graph - Profit Loss per week	TRN_906169.rep		
Debtors		TRN_160			
	Graph	TRN_1091			
		Graph - Debtors per week	TRN_906168.rep		
	Age analysis	TRN_65			
		Balances detail	TRN_906142.rep		FIXED
		Balances detail history (open item)	TRN_906143.rep		FIXED
		Balances	TRN_906147.rep		FIXED
	Outstanding	TRN_947			
		Due date	TRN_2222.rep		FIXED
		Debtors Outstanding at date	TRN_906104.rep		FIXED
Creditors		TRN_161			
	Graph	TRN_1091			

		Graph - Creditors per week	TRN_906167.rep		
	Age analysis	TRN_65			
		Balances detail	TRN_906142.rep		FIXED
		Balances detail history (open item)	TRN_906143.rep		FIXED
		Balances	TRN_906147.rep		FIXED
	Outstanding	TRN_947			
		Due date	TRN_2222.rep		FIXED
		Creditors Outstanding at date	TRN_906103.rep		FIXED
Sales		TRN_1792			
	Graph	TRN_1091			
		Graph - Invoices per week - Quantities	TRN_906170.rep		
		Graph - Invoices per week - Turnover	TRN_906171.rep		
		Graph - Credit notes per week - Quantities	TRN_906319.rep		
		Graph - Credit notes per week - Turnover	TRN_906320.rep		
		Graph - Quotes per week - Quantities	TRN_906323.rep		
		Graph - Quotes per week - Turnover	TRN_906324.rep		
Purchases		TRN_302			
	Graph	TRN_1091			
		Graph - Purchases per week - Quantities	TRN_906289.rep		

		Graph - Purchases per week - Cost	*TRN_906290.rep*		
		Graph - Supplier returns per week - Quantities	*TRN_906321.rep*		
		Graph - Supplier returns per week - Cost	*TRN_906322.rep*		
		Graph - Orders per week - Quantities	*TRN_906325.rep*		
		Graph - Orders per week - Cost	*TRN_906326.rep*		
Tax		*TRN_906020*			
			TAX-LIST-RATES.rep		*FIXED*
Batch type report		*TRN_906098*			*FIXED*
Tutorial reports					*FIXED*

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

FIXED - Reports layout long descriptions and data

Renamed the "C:\osfinancials5\plug_ins\reports\ folder to 109-reports folder before installing the osFinacials5.1.0.127 update file to see if all the files is correctly installed in the clean reports folder.

Update installed - reports - only the following updated reports is installed:

1. excelreports - Firebird error in Sales analysis -> Sales per period

```
Dynamic SQL Error
SQL error code = -104
Token unknown - line 8, column 60
)
```

File for fix : ...\plug_ins\reports\excelreports\TRN_85\TRN_906122\trn_1296.sql (1 file fix error)

2. GENERAL- updated in osFinancials5.1.0.127
3. REPORTS - updated in osFinancials5.1.0.127
4. systemreports - updated in osFinancials5.1.0.127

Added - Reports folders and Reports not installed:

1. Empty.rep - Updated and standardized header and footer
2. New.rep
3. DOCUMENTS/DOCUMENTS/ - Layout files not installed in update
4. userreports/ - not installed in update - User reports restructured

Added - Other Reports folders not installed:

5. CRM
6. EMailInvoice
7. remittance - Fixed output overlapping labels after osFinancials5.1.0.127 update
8. Subscriptions - Fixed output overlapping labels after osFinancials5.1.0.127 update Location : ... \plug_ins\reports\REPORTS\SUBSCRIPT\

Firebird Errors

Ledger - Transactions

Prints in most databases in Firebird and MSSQL without errors

Error only replicated in 1 Database

Set of Books = TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456

Location : ...\plug_ins\reports\systemreports\TRN_1372\TRN_74\TRN_74.rep

> TRANSACTION_DETAIL:arithmetic exception, numeric overflow, or string truncation

MSSQL Errors

Stock In/Out

Location : ...\plug_ins\reports\systemreports\TRN_1999\TRN_906112\TRN_906112.rep

> Unknown identifier: :END.SUM 'END.SUM':Expression TRpExpression2

MSSQL Graphs per Week / Graphs per Month MSSQL - Axis labels (Axis titles)

Example Graphs per month - 204121 Should display the month and year e.g. 202103, 202104 , 202105, 202106, etc. like in Firebird databases

Example Graphs per month - 204121 Should display the week and year e.g. 09 for first week March , etc. like in Firebird databases



DOCUMENTLINE SQL Graphs per month -> Graph - Profit / Loss per month

```
SELECT 1 WTYPEID,

{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,

{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,

sum(-transact.FAMOUNT) Total

FROM transact  join account on transact.Waccountid = Account.Waccountid  and
Account.BincomeExpense = 1

where
```

```
(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)
and transact.FAMOUNT > 0
group by
{if interbase}extract(year from ddate){else}year(ddate){endif} ,
{if interbase}extract(month from ddate){else}month(ddate){endif}
union
SELECT 2 WTYPEID,
{if interbase}extract(year from ddate){else}year(ddate){endif} dyear,
{if interbase}extract(month from ddate){else}year(ddate){endif} dmonth,
sum(-transact.FAMOUNT) Total
FROM transact join account on transact.Waccountid = Account.Waccountid and
Account.BincomeExpense = 1
where
(transact.ddate >= :DDATEFROMFL and transact.ddate <= :DDATETOFL)
and transact.FAMOUNT < 0
group by
{if interbase}extract(year from ddate){else}year(ddate){endif} ,
{if interbase}extract(month from ddate){else}month(ddate){endif}
order by 2,1,3
```

Tidy report errors

Cannot change or Set the Properties such as word wrap, cut text, etc.

Debtor transactions - Extra details - Location : …
\plug_ins\reports\systemreports\TRN_160\TRN_74\TRN_906107.rep

Creditor transactions - Extra details - Location : …
\plug_ins\reports\systemreports\TRN_161\TRN_74\TRN_906109.rep

Long Debtor / Creditor account names or descriptions may overlap



Scope of Fixes

Test Books : TEST-REPORTS-4-DIGIT-DESCRIPTION-1234567890123456.zip

Overlapping labels and expressions overall is fixed mainly in report headers and footers. Database tables and fields lengths were noted and some data is entered to the maximum length to see where fields data labels and expressions caused reports to print untidy. Reports in the default English languages, Afrikaans, Netherlands and some other languages were tested and adjusted where necessary.

For example, Purchase analysis reports prints fine in English and in Afrikaans, but in the Netherlands language labels for Aantal (Quantity) and Kosten per eenheid (Unit cost) overlaps. Some adjustments were done to fix overlapping expressions to fit most language choices. Some other reports were also tidied where similar issues were found.

Report headers and Footers

Upload folder contents : 2024-osf-development\Reports-Tidy

1. Empty.rep - Standardised header and footer
2. DOCUMENTS-29 Layout-files - Document layout files Not the standard headers and footers - But standardised Company registration and Tax registration information after Company address and contact details and telephone 1 / 2 and lastly email and websites. Word wrap for Document lines. Message boxes also tidied.
3. GENERAL-documents -
4. GENERAL-ledgerview - Ledger viewer
5. REPORTS-CREDITOR-reports - 2 Postal and Delivery address labels for Creditors grid - context menu
6. REPORTS-DEBTOR-reports - 2 Postal and Delivery address labels for Debtors grid - context menu
7. REPORTS-PROJECTS - 5 Reports for Projects
8. REPORTS-STOCK - 22 Reports for Stock grid contest menu "Print single item" and Report button
9. systemreports - 18 Reports menus and submenus for the Reports menu. All reports includes updates to the Report Headers and Report Footers to the layout and overlapping labels.
10. userreports - All user reports, including Graphs per month and Graphs per week.

Report headers

Company registration and Tax (VAT/GST/Sales tax) registration numbers - Resized to 9 font size *Italic* and Cut text - will print all characters

Email address and Websites - Resized to 8 font size *Italic* and Cut text - will print up to 55 characters Moved.



Report footers



Company names up to 64 characters in the Setup -> Company info overlap with the time stamp - Aligned the Date-stamp on which report is printed from left to right.

Data the Full path where the Set of Books is stored must print up to 50 characters if Created a Set of Books or Save as option.

System user and osFinancials5 user - System user field length depends on the users system configuration and osFinancials5 user up to 20 characters - Setup - Access control - Moved Page and last page to right.

Some footers not standardised - Reports ->Batch

After fixes -

Empty.rep updated and applied to all report headers and footers



GENERAL

GENERAL - Ledgerview

Location : ...\plug_ins\reports\GENERAL\ledgerview

Report name	*Header / Footer tidied*
budvsactsimple.rep	*YES*
colbal.rep	*YES*
colbalopen.rep	*YES*
colbalopenonly.rep	*YES*
colbalsimple.rep	*YES*
detail.rep	*YES*
ledgerdetail.rep	*YES*
openitemdays.rep	*YES*

GENERAL - documents

Location : ...\plug_ins\reports\GENERAL\documents

Translatable files used in the osFinancials interface

Report name	*Print options*		*Header / Footer tidied*
abbreviations.rep	*Batch - F9:Process - Abbreviation definition*		*YES*
batch.rep		*Error Print preview in Batch entry screen F8:List* TRANSACTIES:Dynamic SQL Error SQL error code = -204 Table unknown BAT4T3 At line 6, column 8	*YES*
barcodes.rep	*Print from Context menu from Documents Grid*		*NOT Standard Header and Footer - Fixed Account name wrap up to 2 lines and support to 34 characters of stock item description*
datacheck.rep	*Setup - Tools - Data integrity*		*YES*
groups.rep	*Setup - Groups*		*YES*
labels.rep	*Print from Context menu from Documents Grid*		*NOT Standard Header and Footer - Fixed Stock item name wrap up to 2 lines and support to 64 characters of stock item descriptions*
labelsdelivery.rep	*Print from Context menu from*		*NOT Standard Header and Footer - Fixed Account name wrap up to 2 lines and support to 64 characters of account name*

	Documents Grid		
paycreditor.rep	*Batch - F9:Process - Automatic payments*		*YES*
paydebtor.rep	*Batch - F9:Process - Automatic receipts*		*YES*
payments.rep		*Error Error Print preview in Reportman* Type conversion error 'Abs':Expression TRpExpression13	*NOT Standard Header and Footer* *Moved Company and Tax registration numbers before Telephone, Fax, E-mail and Website* + *Cut text - Website and E-mail*
oldposcashup.rep	*Not used*		*YES*
oldpossales.rep	*Not used*		*YES*
postedbatch.rep	*Batch - Posted batches tab - Print and Debtot Creditor - Transactions tab*		*YES*
postedbatchold.rep	*Not used*		*YES*
receipt.rep	*Batch - F9:Process - Ptint teceipts on Receipt batches*		*NOT Standard Header and Footer* *Moved Company and Tax registration numbers before Telephone, Fax, E-mail and Website* + *Cut text - Website and E-mail*

recon.rep	*Need to print in Bank reconciliation if Bank import plugin is not activated*	*Error Print preview in Reportman -* TRANSACTIES:Dynamic SQL Error SQL error code = -204 Table unknown RECON0 At line 2, column 1	*YES*
Userlog.rep	*Setup Access control - Log report*		*YES*

Other specific non-translatable files

			Header / Footer tidied
aanvdigi.rep	*Aanvraag: Envelopcertificaten t.b.v. de Belastingdienst Digitale Handtekening en Encryptie*		*NOT Standard Header and Footer*
icl.rep		*Error Print preview in Reportman* Could not convert variant of type (UnicodeString) into type (Double):Expression TRpExpression2	*NOT Standard Header and Footer* *Set COMPANYDATA.SCOMPANYNAME font size from 18 to font size 14 - Prints Company name up to 64 characters*
icl2.rep		*Error Print preview in Reportman* Could not convert variant of type (UnicodeString) into type (Double):Expression TRpExpression2 LINKLEV:Dynamic SQL Error SQL error code = -206 Column unknown X.ICLCODE At line 1, column 77	*NOT Standard Header and Footer* *Set COMPANYDATA.SCOMPANYNAME font size from 18 to font size 14 - Prints Company name up to 64 characters - Added Line break between Company name and Duitse website*
icldetails.rep			*Set*

			COMPANYDATA.SCOMPANYNAME font size from 18 to font size 14 - Prints Company name up to 64 characters
machtform.rep	*Machtigingsformulier (volmacht)*		*NOT Standard Header and Footer*
ob.rep			*Set COMPANYDATA.SCOMPANYNAME font size from 18 to font size 14 - Prints Company name up to 64 characters*
ob2.rep			*Set COMPANYDATA.SCOMPANYNAME font size from 18 to font size 14 - Prints Company name up to 64 characters - Added Line break between Company name and Hoofdgroep*
ob2_KR.rep			*Set COMPANYDATA.SCOMPANYNAME font size from 18 to font size 14 - Prints Company name up to 64 characters - Added Line break between Company name and Hoofdgroep*
obdetails.rep			*Set COMPANYDATA.SCOMPANYNAME font size from 18 to font size 14 - Prints Company name up to 64 characters*
verklzelf.rep	*Verklaring Zelfstandig Bevoegd*	*Error Print preview in Reportman* No space to print SubReport:0 Section:0 *Moved details up then it prints*	

Stock Sidebar reports

Location : ...\plug_ins\reports\REPORTS\STOCK\

Language ID	Report name	Errors	Header / Footer tidied
LANG_1323.rep	Reporting group 1		YES
LANG_1325.rep	Reporting group 2		YES
LANG_1774.rep	Barcode		NOT Standard Header and Footer
LANG_84.rep	Stock item listing		YES
LANG_902008.rep	Price list - Large retail - Sales		YES
LANG_902009.rep	Price list - Large retail - Purchases		YES
LANG_906031.rep	Historical value		YES
LANG_906033.rep	Outstanding orders		YES - Different includes a logo
LANG_906034.rep	Outstanding quotes		YES - Different includes a logo
LANG_906036.rep	Reorder quantities		YES
LANG_906039.rep	Transaction details		YES
LANG_906040.rep	Yagoda barcode		NOT Standard Header and Footer
LANG_906584.rep	Production list		YES
LANG_906585.rep	Stock item list - Active stock		YES
LANG_906586.rep	Stock - Expected quantities		YES
LANG_906588.rep	Value stock account		YES

Order List.rep	No data available to print!	*NO - COMANYDATA not used but ADMINISTRATIEINFO*
Sales Hours.rep	No data available to print!	*NO - COMANYDATA not used but ADMINISTRATIEINFO*
Stock Movement.rep		*YES Update Footer and set Two phase report setting*
test barcode.rep	Access violation at address 6AF73777 in module 'rtl290.bpl'. Read of address 00000060	*NOT Standard Header and Footer*
Voorraad verloop.rep		*NOT Standard Header and NO Footer*
Barcode ean13 11352.rep	Wrong Barcode Type:50515160805170506 2535051525050505152705 17150G	

Projects

Location : ...\plug_ins\reports\REPORTS\PROJECTS\

Language ID	*Report name*	*Header / Footer tidied*
TRN_20069.rep	*Transactions*	*YES*
TRN_27.rep	*Stock items*	*YES*
TRN_354.rep	*Statements*	*YES*
TRN_960.rep	*Total*	*YES*

TRN_2330.rep	*Hours*	*YES*

Reports Test

However these Sets of Books in Firebird databases (and MSSQL databases) the various longer fields, if longer data is is entered in the various fields (e,g Debtors, Creditors Stock items descriptions most of the reports, may appear to have overlapping labels and data text that may make the reports unreadable.

The aim of this exercise is to identify, fix and align reports printed in the Reports menu, User reports menu, Ledger analyser and from various functionalities within the osFinancials interface to accommodate neat and usable reports when longer data and characters is entered by users.

For example, if you create your own Set of Books from scratch, using the "*Customise your own Set of Books (Advanced)?*" option, and you select the 3-digit, 4-digit and 5-digit number of for the Chart of Accounts, the SCompanyname field will accommodate of 35 characters.

By default, the the SCompanyname field will accommodate of 64 characters if the 6-digit, 7-digit or 8-digit number of for the Chart of Accounts is selected.

Should a user enter more than 35 characters (up to the max of 64-characters) in the company name in Setup → Company info, the Company name will not display correctly on some reports, suck as document layout files and debtor statements and creditor remittance advises.

The field length is automatically set when some databases (Set of Books) is created. In addition to this, the field lengths may also be changed in Firebird and MS SQL databases using the ALTER TABLE or equivalent command processes and options by advanced users.

Field lengths in osFinancials databases

Table		*Field*	*Most Books templates - Download option*	*"Customise your own Set of Books (Advanced)?" option - 3 to 8 Digit books*	*EMPTY-BOOKS - 3 to 8 Digit main accounts*	*NL_RGS2019PLUS*
ACCOUNT	*Ledger accounts / Debtor / Creditor accounts*	*SDescription*	*35*	*64*	*128*	*128*

SYSVARS	*SCOMPANYNAME*	*35*	*64*	*64*	*35*
GROUPS	*SDESCRIPTION*	*30*	*30*	*128*	*128*

EMPTY BOOKS

These basic EMPTY-BOOKS templates for the Firebird Database type consists only of the 3 Control accounts in the Chart of Accounts following:

EMPTY-BOOKS - 3 to 8-Digit main accounts

	Debtor's control	*Creditor's control*	*Retained earnings*
EMPTY-BOOKS-3x3-DIGITS	*700-000*	*900-000*	*510-000*
EMPTY-BOOKS-4x3-DIGITS	*1100-000*	*2200-000*	*3100-000*
EMPTY-BOOKS-5x3-DIGITS	*11000-000*	*20000-000*	*31000-000*
EMPTY-BOOKS-6x3-DIGITS	*110000-000*	*200000-000*	*310000-000*
EMPTY-BOOKS-7x3-DIGITS	*1100000-000*	*2000000-000*	*3100000-000*
EMPTY-BOOKS-8x3-DIGITS	*11000000-000*	*20000000-000*	*31000000-000*

Based on the EMPTY-BOOKS-4x3-DIGITS template, the following Books were created:

- 4-EN-UK-GENERIC
- 4-EN-SOUTH-AFRICA-GENERIC
- 4-AF-SUID-AFRIKA-GENERIES

EMPTY-BOOKS-3 to 8 Digit Sets of Books - Properties

These EMPTY-BOOKS-3 to 8 Digit Sets of Books solves some issues and include the following basic settings:

1. Field length - The "*SDESCRIPTION*" field "*ACCOUNT*" table and in the "*GROUPS*" table Account descriptions supports up to 128-characters
2. TYPES table - Add Groups (1000 - Projects, 1002 - Cost centre 1, 1003 - Cost centre 2, and 1004 - Languages) and Paper Types (55 - Till slip and 56 - New plain) which is not included when creating your own Set of Books from scratch using the "Customise your own Set of Books (Advanced)?" option. These entries in the "*TYPES*" table is included in most template Set of Books - downloaded with the "*Let osFinancials help you to create a Set of Books?"* - Downloads option.
3. Accounts - (Setup → Accounts) Only of the 3 Control accounts - (Debtors control, Creditors control and Retained earnings) is included in the Chart of Accounts. You may change their account numbers and descriptions to fit in your specific plan of your Chart of Accounts. You may add Account group 1 and Account group 2 (Setup → Groups) and link these accounts, including other accounts you add to your Chart of Accounts, to structure the layout of the financial statements (trial balance, income statement and balance sheet).
4. Debtor accounts / Creditor accounts - No debtor accounts or creditor accounts have been added.

When you add debtor accounts or creditor accounts, you need to start the account code with a character to distinguish debtor accounts from creditor accounts. Although the next Debtor code (e.g. D00001) and the the next Creditor code (e.g. C00001) depending of the number of digits of the Set of Books), will automatically be generated. It is important to prefix Debtor codes with a unique prefix.

In this documentation, the accounts is prefixed as follows:

- *Debtor code = 1*
- *Creditor code = 2*

The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens.

5. Stock items (Inventory items) - No stock items / inventory items or products have been added. You may add Stock group 1 and Stock group 2 reporting groups to group your stock items / inventory items / products. You may add your stock items / inventory items / products for up to 11 stock item types and link these to the Stock group 1 and Stock group 2 reporting groups.

6. Basic settings -

    - Reporting dates - (Setup → Reporting dates) The default start of the financial year is set to 1 January 2024. You need to set the starting date of your financial year..

    - Groups - (Setup → Groups) The Reporting Group names have been renamed to the basic standard names, (Account group 1, Account group 2, Debtor group 1, Debtor group 2, Creditor group 1, Creditor group 2, Stock group 1, Stock group 2, Document group 1, Document group 2, Payment types, Salespersons, Projects, Cost centre 1, Cost centre 2 and Languages. You need to add your own groups for each of these reporting groups.

    - Batch types - (Setup → Batch types) Only 3 batch types or journal types (Sales journal, Purchase journal and General journal) is included. You may rename these to suit your own requirements. You may add your own batch types or journal types as required. When creating Bank accounts, the Payments and Receipt batches will be created and linked to each bank account.

    - Documents setup - (Setup → Documents setup) The basic settings includes the following:

        - Document numbers - The default document number for each document type consists of 8-digits, and is prefixed by 2 alphabetical characters - IN for invoices, CR for credit notes, PU for purchase documents, SR for supplier return documents, OR for orders, and QU for quotes. However, you can change this to match your specific requirements.

        - Batch types linked to document types - The Sales journal is linked to the Invoices and Credit note document types. The Purchase journal is linked to the Purchase and Supplier returns document types.

        - Layout files - The default layout file (global setting) to print all document types (Invoices, Credit notes, Purchases, Supplier returns, Quotes and Orders) is set to "*Layout file*". This is a universal layout file which supports all document types and available languages in osFinancials5/TurboCASH5. You may select other layout files or your own customised layout file for each document type. The "*Layout file point-of-sale*", is selected as "*POS - STARTSP100*" since the "*DefaultA4*" layout file, which does not exist, is automatically selected after creating a Set of Books using the "*Customise your own Set of Books (Advanced)?*" option.

- Document headings and messages - You may overtype the Document headings to match your specific requirements. The messages for each document type is blank. You may enter up to 3 message lines for each document type to be included in reports and document layout files.
- Statements setup - Enter up to 3 Statement message lines to print on Debtor statements.

Support for Larger descriptions and data in Databases

There are currently some databases which can use larger descriptions and data in fields in the various forms in osFinancials in Firebird databases as well as MSSQL Databases.

Some fields such as SCompanyName allows for 64 characters to be entered

Currently when creating a Set of Books with the "*Customise your own Set of Books (Advanced)?*" option (in both Firebird and MSSQL Database types), the 6-digit main accounts and 3-digit sub-accounts, 7-digit main accounts and 3-digit sub-accounts and 8-digit main accounts and 3-digit sub-accounts supports up to 64-character Account names and descriptions.

8x3 Digit accounts - Reports Test

On some reports, if the Chart of Accounts consisting of 8-digit main accounts and 3-digit sub-accounts is created with the "*Customise your own Set of Books (Advanced)?*" option, and transactions and data is processed, the reports, seemed to have many overlapping columns and text on the printouts. In the Report designer, these reports were realigned, and properties of expressions changed, where necessary. These were addressed and fixed - See FIXED - Reports - 8x3 Digit account codes - Reports. Since there are some Sets of Books in the Firebird database type, for example "*NL_RGS2019PLUS*" and many users who may use longer field lengths, in their Sets of Books in the Firebird and MSSQL Database types, and to accommodate various aspects in larger businesses and accounting frameworks and accounting standards such as GAAP, IFRS for SME's and IFRS Full, all reports in osFinancials is reviewed and tidied, where necessary, to display and print correctly.

Scope for tidying reports in osFinancials5/TurboCASH5, addressing the issues with overlapping text and accommodating longer field lengths

Key Objectives:

- Identify affected reports: Compile a comprehensive list of reports generated from the Reports menu, User Reports menu, Ledger Analyser, and other functionalities that exhibit overlapping text or formatting issues due to longer data entries.

- Fix overlapping text: Adjust report layouts and formatting to ensure readability and prevent overlapping text, even when longer data is entered. This may involve:
    - Expanding field widths
    - Adjusting font sizes
    - Implementing word wrapping
    - Repositioning text elements and or data elements (expressions)
- Test and validate: Thoroughly test all modified reports with various data lengths to ensure proper formatting and readability.
- Document changes: Create clear documentation outlining the changes made to report designs and any potential implications for users.

Specific Considerations:

- Report Designer: Understand the design principles and capabilities of Reportman to effectively modify report layouts and formatting.
- Database Field Lengths: Be mindful of the varying field lengths in different database setups and account for these differences during report adjustments.
- Advanced User Modifications: Consider potential impacts of field length changes made by advanced users using ALTER TABLE commands and ensure compatibility with modified reports.
- Document Layout Files: Address formatting issues in document layout files, such as debtor statements and creditor remittance advice, to ensure correct company name display.
- User Guidance: Provide clear instructions to users on how to enter data appropriately to avoid formatting problems and ensure optimal report output.

Additional Recommendations:

- Prioritize critical reports: Focus initial efforts on reports that are frequently used or essential for decision-making.
- Utilize Reportman features: Leverage Reportman's capabilities for dynamic formatting and conditional logic to create more adaptable reports.
- Involve users in testing: Engage users in testing and feedback to ensure the revised reports meet their needs and expectations.
- Consider future needs: Design reports with potential future field length extensions in mind to

minimize rework.

- Explore alternative solutions: If Reportman limitations restrict optimal formatting, consider exploring alternative reporting tools or custom development options.

FIXED osFinancials5.1.0.102 Files

Folder to update - uploads-osf-5-1-102

Set of Books with long data use to test reports - TEST-REPORTS-4-DIGIT-DESCRIPTIONS.zip

Content

1. reports\excelreports - trn_1296.sql - Copy to - ...\plug_ins\reports\excelreports\TRN_85\TRN_906122\
2. reports\GENERAL -
    - documents - groups.rep - Setup -> Groups - Print button
    - documents - postedbatch.rep - Batch entry - Posted Batches tab - Print button
    - ledgerview - ledgerdetail.rep - T-Account viewer
3. reports\DOCUMENTS-Layout files - Only one layout file TRN_1910.rep Layout file is changed for an example. (Location : plug_ins\reports\DOCUMENTS\DOCUMENTS\TRN1910.rep)
4. reports\systemreports" - See changelog vatious fixes to layout and properties of reports on the Reports menu
5. reports\userreports" - See changelog various fixes to layout and properties of reports on the Reports menu
6. reports\REPORTS - Stock sidebar reports - Print single item context menu

FIXED osFinancials5.1.0.102 Reports

These Fixes to Reports are rechecked and fixed in both Firebird and MSSQL Database types.

FIXED - Spreadsheet reports - SQL Errors - Firebird databases

Spreadsheet reports - Sales analysis - Sales per period

Location : ...\plug_ins\reports\excelreports\TRN_85\TRN_906122\trn_1296.sql

```
Dynamic SQL Error
SQL error code = -104
Token unknown - line 8, column 60
```

```
)
```

NOTE : Can print in MSSQL Databases Replicated since osF5.1.0.49

NOTE : Can print in MSSQL Databases in osFinancials5.1.0.93

Fixed SQL - Removed the double closing bracket form "line 60 group by {if interbase}Extract(year from ddate),Extract(month from ddate){else}Year(ddate),Month(ddate) {endif}" - now it prints in both MSSQL and Firebird

```
select {if interbase}Extract(year from ddate){else}Year(ddate) {endif}
TRN_901022_Year,

{if interbase}Extract(month from ddate){else}Month(ddate) {endif}  TRN_901019_MONTH
,

 sum(fdocamount)  TRN_1866_IncAmt,

 sum(FTAXAMOUNT)  TRN_1138_TaxAmt,

 sum(fdocamount-FTAXAMOUNT)  TRN_1200_ExcAmt

 from dochead where

<@DDATE@>

group by {if interbase}Extract(year from ddate),Extract(month from ddate){else}
Year(ddate),Month(ddate) {endif}
```

FIXED = Removed Bracket (duplicated) in col60 of line 8

FIXED - Reports - Debtor Statements Period Error - Period 2 includes Period 1

Debtor statement – Period 2

Incorrect - Debtor statements Period 2 includes Period 1 - TRN_1090

Fixed to support MSSQL and Firebird databases – 7 February 2023 Since then Period 2 + Period 1 is included in Period 2 total

Reports → Debtors → Debtor statements - Debtor statement - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090 -

FIXED in osFinacials5.1.0.102

TRpExpression 37 changed to

```
IIF(ALIASLOCATE('TRANSACTIONSPERIODE2','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRAN
SACTIONSPERIODE2.FAMOUNT,0)-
IIF(ALIASLOCATE('TRANSACTIONSPERIODE1','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRAN
```

```
SACTIONSPERIODE1.FAMOUNT,0)
```

from

```
IIF(ALIASLOCATE('TRANSACTIONSPERIODE2','WACCOUNTID',TRANSACTION_DETAIL.WACCOUNTID),TRAN
SACTIONSPERIODE2.FAMOUNT,0)
```

MSSQL Database - This report may need some rechecking in MSSQL Databases

If this is changed then Firebird balances (seems fixed), but MSSQL is out in PERIOD2

The transaction on 1 April for PERIOD1 is also Included in PERIOD2 Double count.

See - osF5-1-0-100-Reports-Debtor-statement-period-2-period-1.docx

FIXED - MSSQL ERRORS TRANSACTIONSPERIODE1:Operand type clash: datetime2 is incompatible with int

MSSQL ERROR

```
TRANSACTIONSPERIODE1:Operand type clash: datetime2 is incompatible with int
```

Creditor Age analysis

User reports → Creditors → Age analysis - Balances detail - Location : plug_ins\userreports\userreports\TRN_161\TRN_906142 -

User reports → Creditors → Age analysis - Balances detail history (open item) - Location : plug_ins\reports\userreports\TRN_161\TRN_906143 -

User reports → Creditors → Age analysis - Balances - Location : plug_ins\reports\userreports\TRN_161\TRN_906147 -

FIXED - Firebird and MSSQL Databases - Postal address blank refers to debtors table instead of creditors table

In Firebird and MSSQL Databases - Postal address blank refers to debtors table instead of creditors table

See - Creditor Remittance advice - Outstanding - not printing postal address

Remittance advice

Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Outstanding - Location : plug_ins\reports\systemreports\TRN_161\TRN_906551 -

Creditor Age analysis (Show contact details)

User reports → Creditors → Age analysis - Balances detail - Location :

plug_ins\userreports\userreports\TRN_161\TRN_906142 -

User reports → Creditors → Age analysis - Balances detail history (open item) - Location : plug_ins\reports\userreports\TRN_161\TRN_906143 -

Known issues

Unicode settings in osf.ini files may currently have an impact on some reports. It is replicated since osFinancials5.1.0.81 and up to osFinancials5.1.0.100 and osFinancials5.1.0.102.

Migrating from Delphi 11 to Delphi 12 - in osFinancials the unicode settings may need special checking

Need to figure out if nounicode=false or true - See

- Known issues - Unicode setting - Currencies - Default setting
- Known issues - Unicode setting - Setup Countries
- Known issues - Unicode setting - Reporting dates Error - Refresh failed. Found 0 records
- Known issues - Firebird Reports - Nounicode settings - osf.ini-file
- Known issues - Unicode - Language file names
- Known issues - Unicode setting - Reports - Other languages

Known issues - Firebird Databases - SQL Error - arithmetic exception, numeric overflow, or string truncation

Error produced in Firebird databases -

This has to do with the Unicode settings in Firebird Databases - Print in osFinancials5.1.0.93

Since osFinancials5.1.0.100 and osFinancials5.1.0.102 - this error is replicated in Firebird databases Maybe the " *nounicode=true* " setting changed since these later releases in the osf.ini file.

> arithmetic exception, numeric overflow, or string truncation

Reports - Only prints if is set to nounicode=true in osf.ini files

Reports → Ledger → Transactions - Transactions

Location : plug_ins\reports\systemreports\TRN_1372\TRN_74\TRN_74.rep

> TRANSACTION_DETAIL:arithmetic exception, numeric overflow, or string truncation

Prints in osFinancials5.1.0.93 with the *" nounicode=true* " setting. In osFinancials5.1.0.102 it replicates this errror.

Remittance advises

- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Location : plug_ins\reports\systemreports\TRN_161\TRN_1089 -
- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Outstanding - Location : plug_ins\reports\systemreports\TRN_161\TRN_906551 -

Creditor Age analysis

- Reports → User reports → Age analysis - Balances detail - Location : plug_ins\userreports\userreports\TRN_161\TRN_906142 -
- Reports → User reports → Age analysis - Balances detail history (open item) - Location : plug_ins\reports\userreports\TRN_161\TRN_906143 -
- Reports → User reports → Age analysis - Balances - Location : plug_ins\reports\userreports\TRN_161\TRN_906147 - Balances

Known issues - MSSQL ERROR - TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found

Prints on Firebird databases - MSSQL ERROR - NOT FIXED

MSSQL ERROR -

> TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found

- User reports → Debtors → Outstanding → Debtors Outstanding at date - Location : plug_ins\reports\userreports\TRN_160\TRN_906104 -
- Reports → User reports → Outstanding → Creditors Outstanding at date - Location : plug_ins\reports\userreports\TRN_161\TRN_906103 -

Known issues - Transactions - Extra details reports - ACCOUNT DESCRIPTION - NOT FIXED

The Account description will display correct if less than 56 characters is used for Debtor desctiptions. If more characters is used for the Account description on the Debtor / Creditor form, it will overlap with the amounts. Is this is part of the SQL in the ACCGROUP and Expressions - Currently, cannot set the Expression properties such as Word wrap, etc.

Reports → Debtors → Transactions → Transactions - Extra details - Location : plug_ins\reports\systemreports\TRN_160\TRN_906107 -

Reports → Creditors → Transactions → Transactions - Extra details - Location : plug_ins\reports\systemreports\TRN_161\TRN_906109 -

Changelog - Reports

Location : ... \plug_ins\reports\GENERAL\ledgerview \ledgerdetail.rep

Long debtor account name descriptions may not be displayed correctly on the report.

Changed settings where necessary such as Word wrap, Auto Contract, Auto Expand, etc.

Before fixes



After fixes - Long account descriptions or account names now Expands the expression and contracts the Expression for shorter account descriptions or account names.



Location : \plug_ins\reports\GENERAL\documents \ groups.rep

GROUPDATA.INDENT - Word wrap true and Data under MAINGROUP set Auto Expand and Auto Contract settings

Location : \plug_ins\reports\GENERAL\documents \ postedbatch.rep

Some settings to word wrap and Cut text

Before fix


C:\osfinancials5-93\plug_ins\reports\GENERAL\documents\postedbatch.rep
Batch type report - Posted batch
Batch type : Sales jnl.
Alias (batch name) : SALES1234567890
Batch id : 6
Batch type id : 10
Batch no. : B0000005
File name : bat0t10
Date Reference Description Account / Contra account VAT VAT amount Debit Credit
2023/03/07 INV001 Paint - Exterior Empty, Empty D1ABG-REE Mr. AB Green 1234567890 1234567890 1234567890 G4000-000 1234567890 1234567890 1234567890 1234567890 1234567890 12345 1234567890 2400-010 150.00 1,150.00 0.00
Total 1,150.00 0.00
Date Reference Description Account / Contra account VAT VAT amount Debit Credit
2023/03/09 INV002 Install - Built-in cupboard Empty, Empty D1MAC-SHO MAC Shop Decor Specialists 1234567890 1234567890 G4000-000 1234567890 1234567890 1234567890 1234567890 123 1234567890 1234567890 2400-010 225.00 1,725.00 0.00
Total 1,725.00 0.00
Date Reference Description Account / Contra account VAT VAT amount Debit Credit
2023/03/10 INV003 Paint - Exterior Empty, Empty D1ABG-REE Mr. AB Green 1234567890 1234567890 1234567890 G4000-000 1234567890 1234567890 1234567890 1234567890 1234567890 12345 1234567890 2400-010 150.00 1,150.00 0.00
Total 1,150.00 0.00
Date Reference Description Account / Contra account VAT VAT amount Debit Credit
2023/03/11 INV004 Install - Built-in cupboard Empty, Empty D1MIK-EDA Mr. Mike Davies 1234567890 1234567890 1234567890 2400-010 225.00 1,725.00 0.00

After fixes



Batch type report - Posted batch
Batch type : Salesjnl.
Alias (batch name) : Sales 123456789

Batch id : 38
Batch type id : 10
Batch no. : B0000037
File name : bat0t10

Date	Reference	Description	Account / Contra account	VAT	VAT amount	Debit	Credit
2023/03/07	INV001	Paint - Exterior 1 1234567890 1234567890 1234567890 1234567890 1 Empty, Empty	D1ABG-REE Mr. AB Green 1234567890 1234567890 1234567890 1234567890 1234567890 G4000-000	2400-010	150.00	1,150.00	0.00
				Total		**1,150.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**VAT**	**VAT amount**	**Debit**	**Credit**
2023/03/09	INV002	Install - Built-in cupboard Empty, Empty	D1MAC-SHO MAC Shop Decor Specialists 1234567890 1234567890 1234567890 1234567890 G4000-000	2400-010	225.00	1,725.00	0.00
				Total		**1,725.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**VAT**	**VAT amount**	**Debit**	**Credit**
2023/03/10	INV003	Paint - Exterior Empty, Empty	D1ABG-REE Mr. AB Green 1234567890 1234567890 1234567890 1234567890 1234567890 G4000-000	2400-010	150.00	1,150.00	0.00
				Total		**1,150.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**VAT**	**VAT amount**	**Debit**	**Credit**
2023/03/11	INV004	Install - Built-in cupboard Empty, Empty	D1MIK-EDA Mr.Mike Davies 1234567890 1234567890 1234567890 1234567890 1234567890 G4000-000	2400-010	225.00	1,725.00	0.00
				Total		**1,725.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**VAT**	**VAT amount**	**Debit**	**Credit**
2023/03/07	******	*Paint - Exterior 1 1234567890 1234567890 1234567890 1234567890 1 Empty, Empty	T2400-010 - Output VAT - Standard rate (Sales) - Field 1 - 15% -	-	0.00	0.00	150.00
2023/03/07	******	*Paint - Exterior 1 1234567890 1234567890 1234567890 1234567890 1 Empty, Empty	G4000-000 Sales revenue -	2400-010	-150.00	0.00	1,000.00

Examples of fixes

Stock item listing reports

Before fixes



After fixes

Stock code - Supports up to 15 characters

Stock description - Word wrap and Auto EXpand

Show details - INNER

Reorganised and set details Expression properties to word wrap, etc. where necessary.

Cut text = Set to true - Some labels cut text displayed small amount of data



Changelog - Reports menu = plug_ins\reports\systemreports\

The following tables (highlighted with yellow text) indicates the changelog of reports which is fixed.

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Notes / Added	FIXED
Ledger			TRN_1372			
	Budget		TRN_1027			
			Budget vs actual (3 periods)	TRN_3372.rep		
	Listing		TRN_66			
			Chart of Accounts	TRN_73.rep		OK
	Transactions		TRN_74			
			Transactions	TRN_74.rep		OK
			Transactions - Standard	TRN_906110.rep		FIXED
			Transactions - Extra details	TRN_906111.rep		OK
Debtors			TRN_160			
	Debtor statement		TRN_1090			
			Debtor Statements	TRN_1090.rep	Debtor account description word wrap and moved address and contact details down 2 lines and contact word wrap	FIXED Also Period 2 includes Period 1 Totals in Expression37
			Debtors statement - Outstanding	TRN_906552.rep	Debtor account description word wrap and	FIXED

					moved address and contact details down 2 lines and contact word wrap	
	Listing		TRN_66			
			Contacts	TRN_2876.rep	Groups on Options screen resized width to 300	FIXED
			Listing	TRN_66.rep	Groups on Options screen resized width to 300	FIXED
			List delivery address	TRN_906138.rep	Groups on Options screen resized width to 300	FIXED
			List postal address	TRN_906139.rep	Groups on Options screen resized width to 300	FIXED
			List details	TRN_906140.rep	Groups on Options screen resized width to 300	FIXED
			Credit control listing (Credit limit vs Current balance)	TRN_906338.rep	Groups on Options screen resized width to 300	FIXED
			Tax and Company registration numbers	TRN_906339.rep	Groups on Options screen resized width to 300	FIXED
	Print labels		TRN_68			
			Delivery address labels	TRN_906064.rep	Groups on Options screen	CHECK

					resized width to 300	
			Postal address labels	TRN_906137.rep	Groups on Options screen resized width to 300	CHECK
	Transactions		TRN_74			
			Transactions	TRN_74.rep		FIXED
			Transaction List - Open item	TRN_906061.rep		FIXED
			Transactions - Standard	TRN_906106.rep		FIXED
			Transactions - Extra details	TRN_906107.rep	ACCOUNT DESCRIPTION	CHECK
			Transaction List	TRN_906440.rep		FIXED
Creditors			TRN_161			
	Creditor remittance advises		TRN_1089			
			Creditor remittance advise	TRN_1089.rep	Creditor account description word wrap and moved address and contact details down 1 lines and contact word wrap and cut text	FIXED
			Creditor remittance advise - Outstanding	TRN_906551.rep	Postal address blank refers to debtors table instead of creditors table See - Creditor	FIXED

					Remittance advice - Outstanding - not printing postal address Creditor account description word wrap and moved address and contact details down 2 lines and contact word wrap and cut text	
	Listing		TRN_66			
			Contacts	TRN_2876.rep	Groups on Options screen resized width to 300	FIXED
			Listing	TRN_66.rep	Groups on Options screen resized width to 300	FIXED
			List delivery address	TRN_906138.rep	Groups on Options screen resized width to 300	FIXED
			List postal address	TRN_906139.rep	Groups on Options screen resized width to 300	FIXED
			List details	TRN_906140.rep	Groups on Options screen resized width to 300	FIXED
			Credit control listing (Credit limit vs Current balance)	TRN_906338.rep		FIXED

			Tax and Company registration numbers	TRN_906339.rep		FIXED
	Print labels		TRN_68			
			Delivery address labels	TRN_906064.rep	Groups on Options screen resized width to 300	CHECK
			Postal address labels	TRN_906137.rep	Groups on Options screen resized width to 300	CHECK
	Transactions		TRN_74			
			Transactions	TRN_74.rep		FIXED
			Transaction List - Open item	TRN_906061.rep		FIXED
			Transactions - Standard	TRN_906108.rep		FIXED
			Transactions - Extra details	TRN_906109.rep	ACCOUNT DESCRIPTION	CHECK
			Transaction List	TRN_906440.rep		FIXED
Sales			TRN_1792			
	Quotes		TRN_1870			
		Debtors	TRN_160			
			Quotes per period - Quantities	TRN_906315.rep		FIXED
		Sales	TRN_1792			
			Quotes per period - Quantities	TRN_906315.rep		FIXED
		Items	TRN_2052			

			Items per period	TRN_906115.rep		FIXED
	Invoices		TRN_300			
		Debtors	TRN_160			
			Invoices per period - Quantities	TRN_906155.rep		FIXED
		Sales	TRN_1792			
			Invoices per period - Quantities	TRN_906155.rep		FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep		FIXED
	Credit notes		TRN_47			
		Debtors	TRN_160			
			Credit notes per period - Quantities	TRN_906311.rep	Set account code + Description to Font size 10 (was 11) In line with similar reports	FIXED
		Sales	TRN_1792			
			Credit notes per period - Quantities	TRN_906311.rep	Added missing Code + Item description - column headings	FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep		FIXED
Plugins			TRN_1805			
	Price agreement		TRN_3380			

			Debtor – Price agreement	TRN_906035.rep		FIXED
			Creditor – Price agreement	TRN_906088.rep		FIXED
	Location-Serials-Batches		TRN_3398			
			On hand	TRN_1777.rep		FIXED
			Stock movement	TRN_906038.rep	UNICODE setting off e.g. only 5 digits like IN000 is printed in osFinancials5.1.0.102 but in osFinancials5.1.0.93 all 8 digits like IN000009 is	FIXED
			Outdated batch	TRN_906554.rep		FIXED
			Batch bought from supplier	TRN_906555.rep	Removed “On Hand” from Report name	FIXED
			Batch sold to customer	TRN_906556.rep	Removed “On Hand” from Report name	FIXED
Stock			TRN_1999			
	Reorder		TRN_1778			
			Reorder report	TRN_83.rep		FIXED
			Current stock levels	TRN_906268.rep		FIXED
	Print labels		TRN_68			
			Barcode	TRN_1774.rep	Supports longer descriptions Word wrap	FIXED

			Yagoda barcode	TRN_906040.rep	Supports up to 35 characters Cut text	OK
	Stock item listing		TRN_84			
			All selling prices	TRN_1056.rep	Groups on Options screen resized width to 300	
			Tax classes	TRN_3465.rep		FIXED
			Stock item listing	TRN_84.rep	Redone detail layout Groups on Options screen resized width to 300	
	Backorder		TRN_906050			
			Backorder	TRN_906050.rep		FIXED
	Stock In / Out		TRN_906112			
			Stock In / Out - Documents	TRN_38.rep	Groups on Options screen resized width to 550	FIXED
			Stock In / Out	TRN_906112.rep	Groups on Options screen resized width to 550	FIXED
Point-of-Sale			TRN_2200			
	Standard		TRN_1990			
			Sales	TRN_1792.rep	NOT TESTED	
			Receipts	TRN_182.rep	NOT TESTED	
	Cash slip printer		TRN_906160			

			Sales	TRN_1792.rep	NOT TESTED	
			Receipts	TRN_182.rep	NOT TESTED	
Contacts			TRN_2876			
			Contacts	TRN_2876.rep		FIXED
Calendar			TRN_2879			
			Hours	TRN_2330.rep		OK
Batch entry			TRN_298			
			Documents	TRN_38.rep		FIXED
			Batch transactions per period	TRN_906141.rep		FIXED
Purchases			TRN_302			
	Purchase documents		TRN_1269			
		Creditors	TRN_161			
			Purchases per period - Quantities	TRN_906150.rep	Set account code + Description to Font size 10 (was 11) In line with similar reports	FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep	Shrink unnecessary space	FIXED
		Purchases	TRN_302			
			Purchases per period - Quantities	TRN_906150.rep	Shrink unnecessary space	FIXED
	Orders		TRN_1871			

		Creditors	TRN_161			
			Orders per period - Quantities	TRN_906317.rep		FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep	Shrink unnecessary space	FIXED
		Purchases	TRN_302			
			Orders per period - Quantities	TRN_906317.rep	Align Stock description with Description heading + Shrink unnecessary space	FIXED
	Supplier returns		TRN_303			
		Creditors	TRN_161			
			Supplier returns per period - Quantities	TRN_906313.rep	Set account code + Description to Font size 10 (was 11) In line with similar reports	FIXED
		Items	TRN_2052			
			Items per period	TRN_906115.rep	Shrink unnecessary space	FIXED
		Purchases	TRN_302			
			Supplier returns per period - Quantities	TRN_906313.rep		FIXED
Company info			TRN_320			

			Bank accounts	TRN_183.rep		
			Information	TRN_629.rep		
Currencies			TRN_3470			
			Currencies	TRN_3470.rep		OK
Documents			TRN_38			
	Document listing		TRN_45			
			Document listing	TRN_45.rep		OK
	Document listing per account		TRN_906161			
		Sales documents	TRN_1268			
			Invoices	TRN_300.rep		FIXED
			Quotes	TRN_418.rep		FIXED
			Credit notes	TRN_706.rep		FIXED
		Purchase documents	TRN_1269			
			Purchases	TRN_302.rep		FIXED
			Supplier returns	TRN_303.rep	Access violation at address 771CC983 in module 'ntdll.dll'. Read of address 115C3000	FIXED
			Orders	TRN_798.rep	DOCUMENTLINE:Dynamic SQL Error	FIXED

					SQL error code = -303 arithmetic exception, numeric overflow, or string truncation Need to select the accounts and / or confirmed settings	
	Unprinted document listing		TRN_906162			
		Sales documents	TRN_1268			
			Invoices	TRN_300.rep		FIXED
			Quotes	TRN_418.rep		FIXED
			Credit notes	TRN_706.rep		FIXED
		Purchase documents	TRN_1269			
			Purchases	TRN_302.rep		FIXED
			Supplier returns	TRN_303.rep		FIXED
			Orders	TRN_798.rep		FIXED
Sales analysis			TRN_85			
	Quotes per period		TRN_3568			
			Quotes per period - Debtor group 1	TRN_906301.rep		FIXED
			Quotes per period - Debtor group 2	TRN_906302.rep		FIXED

		Quotes per period - Document group 1	TRN_906303.rep		FIXED
		Quotes per period - Document group 2	TRN_906304.rep		FIXED
		Quotes per period - Salesperson	TRN_906305.rep		FIXED
	Invoices per period	TRN_3570			
		Invoices per period - Debtor group 1	TRN_906157.rep		FIXED
		Invoices per period - Debtor group 2	TRN_906158.rep		FIXED
		Invoices per period - Document group 1	TRN_906159.rep		FIXED
		Invoices per period - Document group 2	TRN_906165.rep		FIXED
		Invoices per period - Salesperson	TRN_906166.rep		FIXED
	Credit notes per period	TRN_3569			
		Credit notes per period - Debtor group 1	TRN_906291.rep		FIXED
		Credit notes per period - Debtor group 2	TRN_906292.rep		FIXED
		Credit notes per period - Document group 1	TRN_906293.rep		FIXED
		Credit notes per period - Document group 2	TRN_906294.rep		FIXED
		Credit notes per period - Salesperson	TRN_906295.rep		FIXED
	Sales per product	TRN_3571			
		Sales per product - Stock group 1	TRN_906174.rep		FIXED

			Sales per product - Stock group 2	TRN_906175.rep		FIXED
	Sales per period		TRN_906122			
			Sales per period - Debtor group 1	TRN_906332.rep		FIXED
			Sales per period - Debtor group 2	TRN_906333.rep		FIXED
			Sales per period - Document group 1	TRN_906334.rep		FIXED
			Sales per period - Document group 2	TRN_906335.rep		FIXED
			Sales per period - Salesperson	TRN_906336.rep		FIXED
Tax			TRN_906020			
			Transactions	TRN_20069.rep		FIXED
			Tax list debtor with tax id	TRN_3675.rep		OK
			Tax per period	TRN_906105.rep		OK
			Tax report - Reference / Document no.	TRN_906550.rep		FIXED
			Tax list creditor with tax id	TRN_906553.rep		OK
Purchase analysis			TRN_977			
	Orders per period		TRN_3572			
			Orders per period - Creditor group 1	TRN_906306.rep		FIXED
			Orders per period - Creditor group 2	TRN_906307.rep		FIXED
			Orders per period -	TRN_906308.re		FIXED

		Document group 1	p		
		Orders per period - Document group 2	TRN_906309.rep		FIXED
		Orders per period - Salesperson	TRN_906310.rep		FIXED
	Purchases per period	TRN_3573			
		Purchases per period - Creditor group 1	TRN_906152.rep		FIXED
		Purchases per period - Creditor group 2	TRN_906153.rep		FIXED
		Purchases per period - Document group 1	TRN_906154.rep		FIXED
		Purchases per period - Document group 2	TRN_906163.rep		FIXED
		Purchases per period - Salesperson	TRN_906164.rep		FIXED
	Supplier returns per period	TRN_3574			
		Supplier returns per period - Creditor group 1	TRN_906296.rep		FIXED
		Supplier returns per period - Creditor group 2	TRN_906297.rep		FIXED
		Supplier returns per period - Document group 1	TRN_906298.rep		FIXED
		Supplier returns per period - Document group 2	TRN_906299.rep		FIXED
		Supplier returns per period - Salesperson	TRN_906300.rep		FIXED
	Purchases per product	TRN_3575			
		Purchases per product - Stock	TRN_906172.re		FIXED

			group 1	p		
			Purchases per product - Stock group 2	TRN_906173.rep		FIXED
	Purchases and Supplier returns per period		TRN_906337			
			Purchases documents per period - Creditor group 1	TRN_906327.rep		FIXED
			Purchases documents per period - Creditor group 2	TRN_906328.rep		FIXED
			Purchases documents per period - Document group 1	TRN_906329.rep		FIXED
			Purchases documents per period - Document group 2	TRN_906330.rep		FIXED
			Purchases documents per period - Salesperson	TRN_906331.rep		FIXED

Report button - Print single item context menu

Stock sidebar reports - Print single item context menu

Location : ...\plug_ins\reports\REPORTS\STOCK

The following reports are now translatable, report names (also translatable) tidied word wrap, headers and footers.

Stock movement	The "Stock movement" report will list the Stock code, Stock description, Quantities and Average cost for a selected stock item.

Report name language id	Report name	Description	Notes
LANG_906584	Production list	Production list report lists the transactions of all items (other stock item types) linked to the BOM and BOM	New repo

		(Production) stock item type on the BOM tab.	rt
LANG_906585	Stock item list - Active stock	The "Stock item listing - Active stock" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. Only active (enabled) Stock items will be listed. Inactive (disabled) Stock items not will be listed.	New repo rt Adde d - Unit type
LANG_84	Stock item listing	The "Stock item listing" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. All active (enabled) Stock items as well as inactive (disabled) Stock items will be listed.	Adde d - Unit type Disa bled Yes / No
LANG_1774	Barcode	The "Barcode" report prints barcodes for all stock items or a selected stock item.	
LANG_906040	Yagoda barcode	The "Yagoda barcode" report prints Yagoda barcodes for all stock items or a selected stock item.	
LANG_1323	Reporting group 1	The Reporting group 1 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.	Adde d - Disa bled Yes / No Rem oved : Colu mn Num ber to word

			s for Selling price 2 - IIF(STR(VOORRAAD.VerkoopPrijs2)='','',CUSTOM('NUMBERTOWORDS',VOORRAAD.VerkoopPrijs2,'','','','''))
LANG_1325	Reporting group 2	The Reporting group 2 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.	Added - Disabled Yes / No Removed: Column Number

			to words for Selling price 2 - IIF(STR(VOORRAAD.VerkoopPrijs2)='','',CUSTOM('NUMBERTOWORDS',VOORRAAD.VerkoopPrijs2,'','','',''))
LANG_906031	Historical value	The "Historical value" report The Reporting group 1 for stock items, will list the Stock code, Stock description, Quantities and Total value for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.	Deleted - Replaced - Historische waarde.rep Adde

			d - Disabled Yes / No Fixed - Changed SQL to Reporting group 1 from Reporting group 2 in VOORRAAD data set
LANG_906033	Outstanding orders	The Unconfirmed orders report will list all outstanding orders, which is not yet confirmed (converted to a purchase document). This report will list all unconfirmed orders for each creditor (supplier / vendor) account by order number, order date stock quantities, stock item code, stock item description and document reporting group 1.	Print single item - prints all unconfirmed orders and items.

LANG_906034	Outstanding quotes	The Unconfirmed quotes report will list all outstanding quotes, which is not yet confirmed (converted to invoices). This report will list all unconfirmed quotes for each debtor (customer / client) account by quote number, quote date stock quantities, stock item code, stock item description and document reporting group 1.	Print single item - prints all unconfirmed quotes and items.
LANG_906036	Reorder quantities	The "Reorder quantities" report will list the Stock code, Stock description, Quantity on hand, Unposted Invoices/Purchases, Reorder level and quantity to order for each stock item.	
LANG_906038	Stock movement	The "Stock movement" report will list the Stock code, Stock description, Quantities and Average cost for a selected stock item.	Added report name "Stock movement - Average cost - Grid" in Header section

Fixed Total print on last page (page2) instead at the end of the detail section. Total format not showing digit separator symbol as in details section of report.

Two pass report and Auto

			Expand / Auto contract settings *Word wrap*
LANG_906039	*Transaction details*	*The "Transaction details" report list the document date (and time, if available) document number, document type, quantities, salesperson and document reference for each stock item.*	*Deleted - Replaced - Transaction Details.rep and transactie details.rep* *Added - Disabled Yes / No* *Added - Document reference - this will list*

the document references, including those for:

- Stock adjustments - Remarks entered

in the "Change remarks" screen (e.g. Surplus/Sho

rtageorAutocorrection).

- BOM (Production) sto

cktemtypeAssembleDisassembleoptiononcon

			text menu.
LANG_906588	*Value stock account*	*The "Value stock account" report lists the total value of the stock control account. If the "Show details" option is selected, it will list the the value of each stock item.*	
LANG_902008	*Price list - Large retail - Sales*	*The "Price list - Large retail - Sales" report will list quantity discount up to five (5) price levels of a selected stock item for a selected debtor (customer / client) account.*	*Deleted: Prijzenlijst groothandel and Price List - Large Retail* *Added: Price levels 4 and 5 (was only supporting 3 price*

			levels .
LANG_902008	*Price list - Large retail - Purchases*	*The "Price list - Large retail - Purchases" report will list quantity discount up to five (5) price levels of a selected stock item for a selected creditor (supplier / vendor) account.*	*New report: Price levels up to 5 - for purchases (Creditor / Supplier Vendor) accounts.*

Created with the Standard Edition of HelpNDoc: Elevate your documentation to new heights with HelpNDoc's built-in SEO

FIXED - Debtor Statements and Creditor Remittance advices

Debtor Statements and Creditor Remittance advices

Debtor statements

Debtor statements

- Reports → Debtors → Debtor statements - Debtor statement - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090 -
- Reports → Debtors → Debtor statements - Debtor statement - Outstanding - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_906552 -

Before Fixes



Some fixed expressions and element properties:

1. Company name - Company data " *SCompanyName {chartype}(64)* " field in the SYSVARS table allows for 64-characters to be entered. Overlaps with Company data COMPANYDATA.SCOMPANYNAME such as COMPANYDATA.SADDRESS1 if More than 40 characters is entered. Moved address and contact details down 1 line and contact word wrap. For shorter Company names it will leave a blank line between Company name and Address 1

2. Debtor account name - Description Word wrap and moved address and contact details down 1 line and contact word wrap and cut text. Debtor names will print up to 45 characters in the first line and about 45 characters on the next line (total of 90 characters).

3. Standardised the Placement of Company registration numbers and Tax (VAT/GST/Sales tax) registration numbers - for consistency across all reports - Common Practices and User Expectations:
    - Company Name and Address First: These are typically the most prominent elements in the header, establishing the invoice issuer's identity.
    - Registration Numbers After Address: Placing registration numbers immediately after the address is a common practice, making them easily accessible for reference.
    - Contact Details Last: Phone, fax, email, and website usually follow registration numbers, providing additional means of communication.
4. E-mail addresses - Company e-mail address and Debtor e-mail address Cut text up to 40 characters would print.
5. Websites - Company website address and Debtor website address Cut text up to 40 characters would print.
6. Logo - Resized from 9.5cm by 5.7cm (approximately 3.74 inches x 2.24 inches or 5385 twips x 3231 twips) to include space to include Company registration and Tax (VAT/GST/Sales tax) information on logos.
7. Transaction detail - Prints too close to amount - Applied Word wrap and Auto Expand and Auto Contract.
8. Messages
    - Debtor statements global messages (Setup → Documents setup) - Statements tab) SYSVARS table - SSTATEMENTMESSAGE1, SSTATEMENTMESSAGE2 and SSTATEMENTMESSAGE3 supports up to 30 Characters each. Prints fine.
    - Debtor statement message (Delivery address tab) 4 Message lines SMESSAGE - 50 characters and 64 characters each for SFREEFIELDS1, SFREEFIELDS2 and SFREEFIELDS3 on DEBTOR table. Cuts off text around 50 characters and overlaps with the global messages. FIX Resized tie Rectangular square frame Combined message fields in 1 expression and set Word wrap.

```
ACCOUNTLOOKUP.SMESSAGE+#13+#10+ACCOUNTLOOKUP.SFREEFIELD1+#13+#10+ACCOUNTLOOKUP.SFREEFIELD2+#13+#10+ACCOUNTLOOKUP.SFREEFIELD3 "
```

9. Banking details - Company banking details - Expression " COMPANYDATA.SCOMPANYNAME+' - '+CUSTOM('GETTEXTLANG',29,'Bank account',0,0,0)+': ' " Resized length to accommodate up to 2 lines with Word wrap.

After Fixes



Creditor remittance advices

Creditor Remittance advises

- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Location : plug_ins\reports\systemreports\TRN_161\TRN_1089 -
- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Outstanding - Location : plug_ins\reports\systemreports\TRN_161\TRN_906551 -

Before Fixes



Some fixed expressions and element properties:

1. Company name - Company data " *SCompanyName {chartype}(64)* " field in the SYSVARS table allows for 64-characters to be entered. Overlaps with Company data COMPANYDATA.SCOMPANYNAME such as COMPANYDATA.SADDRESS1 if More than 40 characters is entered. Moved address and contact details down 1 line and contact word wrap. For shorter Company names it will leave a blank line between Company name and Address 1

2. Creditor account name - Description Word wrap and moved address and contact details down 1 line and contact word wrap and cut text. Debtor names will print up to 45 characters in the first line and about 45 characters on the next line (total of 90 characters).

3. Standardised the Placement of Company registration numbers and Tax (VAT/GST/Sales tax) registration numbers - for consistency across all reports - Common Practices and User Expectations:

- Company Name and Address First: These are typically the most prominent elements in the header, establishing the invoice issuer's identity.
- Registration Numbers After Address: Placing registration numbers immediately after the address is a common practice, making them easily accessible for reference.
- Contact Details Last: Phone, fax, email, and website usually follow registration numbers, providing additional means of communication.

4. E-mail addresses - Company e-mail address and Creditor e-mail address Cut text up to 40 characters would print.
5. Websites - Company website address and Creditor website address Cut text up to 40 characters would print.
6. Logo - Resized from 9.5cm by 5.7cm (approximately 3.74 inches x 2.24 inches or 5385 twips x 3231 twips) to include space to include Company registration and Tax (VAT/GST/Sales tax) information on logos.
7. Transaction detail - Prints too close to amount - Applied Word wrap and Auto Expand and Auto Contract.
8. Messages - Creditor remittance message (Delivery address tab) 4 Message lines SMESSAGE - 50 characters is included in the CREDITOR table - but is currently not used to enter messages on the Delivery address tab of the Creditor account. This will print a blank empty space (line) in the Message section of the Creditor remittance advice and is therefore removed at this stage. Remittance messages is entered on the Statement message 1, Statement message 2 and Statement message 3 of up to 64 characters each for SFREEFIELDS1, SFREEFIELDS2 and SFREEFIELDS3 updated in the CREDITOR table.

Other older fixes

Postal address blank refers to debtors table instead of creditors table

See - Creditor Remittance advice - Outstanding - not printing postal address

```
CUSTOM('GETTEXTLANG',348,'Statement Message',0,0,0)+': '
```

Changed to

```
CUSTOM('GETTEXTLANG',681,'Remittance message',0,0,0)+': '
```

After Fixes


Report manager designer-C:\osfinancials5\plug_ins\reports\systemreports\TRN_161\TRN_1089\TRN_1089.rep
A-ONE Suppliers 1234567890 1234567890 1234567890 1234567890 1234567890 1234567890 1234567890
P O Box 31318
Marshalltown
Johannesburg
2000
South Africa
Account no. : C2AONESU
Contact :
Tax reg. no. : 906012345
Company reg. no. : 123459060
Telephone 1 : (011) 838-9221
Telephone 2 : (011) 838-9222
Fax : (011) 838-9223
E-mail : aones@hismail.com 567890123456789012345678901234567
Website : WEBAONES8123456789012345678901234567890123456
4-EN-SOUTH-AFRICA-GENERIC 7890 1234567890 1234567890 12345678901
ADDRESS 90 1234567890
ADDRESS 1 90 1234567890
ADDRESS 3 90 1234567890
2000
Company reg. no.: CR34567890123456789012345678901
Tax reg. no.: TR3456789012345678901234567890
Phone: TEL456789012345678901234567890
Fax: FAX456789012345678901234567890
E-mail: EMAIL678901234567890@1234567890123456789C
Website: WEB456789012345678901234567890123456789012
Creditor remittance advise
Page: 1
Remittance advise to: 2023/12/05
Period 1 : 2023/12/05
Period 2 : 2023/11/05
Period 3 : 2023/09/06
Due amount: 1,125.00
Due date: 2024/01/04
Date Reference Description Amount Payment date
2023/04/01 Opening Opening -2,325.00 2023/05/01
2023/12/05 SR000003 Supplier returns /REF 567890 1234567890 1234567890 12 1,725.00 2024/01/04
2023/12/05 SR000005 Supplier returns /REF 567890 1234567890 1234567890 12 1,725.00 2024/01/04
Due amount Period 1 (30) Period 2 (60) Period 3 (90) +
1,125.00 3,450.00 0.00 -2,325.00
Credit limit: 12,000.00
Balance : 1,125.00
Available : 10,875.00
Remittance message:
2.5% Early settlement discount 1234567890 1234567890 12345678901
Remittance message 2 1234567890 1234567890 1234567890 1234567890
Remittance message 2 1234567890 1234567890 1234567890 1234567890
Due amount: 1,125.00 Due date: 2024/01/04

Detail of the SMESSAGE filed in the CREDITOR table not in Delivery tab of Creditor account





Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

FIXED - Document layout files

Document layout files

Document layout files

Fixed - Websites added to layout files

Added - Added Website to be consistent with other layout files, Debtor statements, Creditor remittance advises and other reports. Affected layout files:

- TRN_1910 - Layout file
- TRN_3174 -Document layout
- TRN_906589 - NO-TAX Layout file

- TRN_906590 - NO-TAX Document layout file

COMPANYINFO - Dataset Updated SQL to include SWebsite field

Added Expression for the Label

```
CUSTOM('GETTEXTLANG',3212,'Website',CLIENTORDEFLANG.SLANGUAGE,0,0)+': '
```

Added Expression for the SWebsite field

```
COMPANYINFO.SWEBSITE
```

Fixed - Labels not translating

TRN_1313 Delivery note - Label is system language or Debtor language not translating " *Delivery note accepted:* "

Changed Expression

```
CUSTOM('GETTEXTLANG',1150,'DeliveryNoteAccepted',ACCOUNTINFO.SLANGUAGE,0,0)+': '
```

to

```
CUSTOM('GETTEXTLANG',1150,'DeliveryNoteAccepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+': '
```

Layout files - Fixed layout output presentation

Location : plug_ins\reports\DOCUMENTS\DOCUMENTS\

Document layout files (Translatable)

LanguageID	*Layout file name*
TRN_1313.rep	*Delivery note*
TRN_1910.rep	*Layout file*
TRN_3174.rep	*Document layout*
TRN_906183.rep	*POS - STARTSP100*
TRN_906184.rep	*POS 1*

TRN_906185.rep	*POS 2*
TRN_906277.rep	*Document layout (15 code)*
TRN_906589.rep	*NO-TAX Layout file*
TRN_906590.rep	*NO-TAX Document layout*
TRN_906591.rep	*NO-TAX Document layout (15-code)*

Non Translatable Static text

Used for tutorials and customisation for users who wish to make simpler layout files.

Similar formatting and tiding is applied as with the translatable layout files.

- BTW Faktuur - Afrikaans.rep
- GEEN-BTW Faktuur - Afrikaans.rep
- TAX Invoice English.rep
- NO-TAX Invoice - English.rep

Before fixes

The layout file (TRN_1910.rep) Layout file illustrates the changes and fixes to tidy layout files.

Location : plug_ins\reports\DOCUMENTS\DOCUMENTS\TRN1910.rep

Long descriptions currently may overlap similar to this example.

Debtor and Creditor accounts can be entered with a description of up to 128 characters.

Layout files can only print about 45 characters without overlapping into the company address fields.



Some fixed expressions and element properties:

1. Company name - Company data " *SCompanyName {chartype}(64)* " field in the SYSVARS table allows for 64-characters to be entered. Overlaps with Company data COMPANYDATA.SCOMPANYNAME such as COMPANYDATA.SADDRESS1 if More than 40 characters is entered. Moved address and contact details down 1 line and contact word wrap. For shorter Company names it will leave a blank line between Company name and Address 1. Up to 64 characters would print on layout files.

2. Debtor account name - description word wrap and moved address and contact details down 1 line and contact word wrap and cut text. Debtor names will print up to 45 characters in the first line and about 45 characters on the next line (total of 90 characters). It may leave 2 lines blank for smaller descriptions. Studies suggest 5-10% of business names in some countries exceed 60 characters. About 90 characters should be sufficient to print on layout files.

3. Standardised the Placement of Company registration numbers and Tax (VAT/GST/Sales tax) registration numbers - for consistency across all reports - Common Practices and User Expectations:

    - Company Name and Address First: These are typically the most prominent elements in the

header, establishing the invoice issuer's identity.

- Registration Numbers After Address: Placing registration numbers immediately after the address is a common practice, making them easily accessible for reference.
- Contact Details Last: Phone, fax, email, and website usually follow registration numbers, providing additional means of communication.

4. E-mail addresses - Company e-mail address and Debtor e-mail address Cut text up to 40 characters would print.
5. Websites - Company website address and Debtor website address Cut text up to 40 characters would print.
6. Logo - Resized from 9.5cm by 5.7cm (approximately 3.74 inches x 2.24 inches or 5385 twips x 3231 twips) to include space to include Company registration and Tax (VAT/GST/Sales tax) information on logos.

   Set logo image TRpImage0 , TRpImage1 "To Front" when a logo is set the text does not print over the logo if a logo is set.
7. Document lines -
   - Stock code - 15 characters - Full
   - Stock Description - 64 characters - Word wrap
   - Comments - Word wrap as basically long comments of more than 128 characters can be entered.
   - Remarks - Word wrap as basically long remarks of more than 128 characters can be entered. Set the Remarks font size to 9 and *Italic* font style.
   - Location/batches/serials - 40 characters - Word wrap
   - Options - SReference 20 characters or 35 characters - Word wrap
8. Footer - Reduced font size from 10 to 9 and set to italic. This is done to strike a balance of the characters in the data and printing.
   - Your reference - Up to 35 characters can be entered and will be printed. stretched expression to print the full 35-characters
   - Tax reference - Tax reference from Debtor / Creditor edit form can only enter up to 20 characters would be printed in the Tax reference field. On the Doc Head up to 64 characters can be entered in an unposted document. When the document is saved with the long description and or printed the layout file defaults to the Tax reference as entered or edited on

the Debtor / Creditor form.

- Messages - Message 1, Message 2 and Message 3 these are the default messages of up to 30 characters as entered in the Setup → Documents setup for each document type.

  Cut text - is applied for cases when creating or editing documents Messages can be over-typed longer descriptions can be added up to 60 characters. Up to 45 characters would be printed.

  Message 3 line is used for the reference of the source document quotes is converted to invoices, orders is converted to purchase documents or when documents is copied, etc. More than 4 Reference numbers may be generated when processing documents. Message line 3 is set to Word wrap and Cut text to print more details such as reference numbers.

- Salesperson - Word wrap = Salesperson descriptions as entered in Setup → Salespersons or Setup → Groups - Salespersons supports longer descriptions - Cut text - Only up to 50 characters will be printed.

9. Banking details - Company banking details - Expression " COMPANYDATA.SCOMPANYNAME+' - '+CUSTOM('GETTEXTLANG',29,'Bank account',0,0,0)+': ' " Resized length to accommodate up to 2 lines with Word wrap. Only applicable to specific document layout files.

After fixes



Netherlands Layout files

Company name and Debtor / Creditor account descriptions support longer descriptions.

Set Word wrap to Document lines (Comments, Remarks, Location/Batches/Serials) where necessary.

1. POS.rep - Factuur - Only includes ADMINISTRATIEINFO.Logo and no Company name.

   Added Company name expression since it is not printed on POS layout file

   ```
   ADMINISTRATIEINFO.BEDRIJFSNAAM
   ```

2. RMBestelling.rep
3. RMCreditnota.rep
4. RMfactuur BE.rep - Other fixes

- DOCUMENTKOP.MESSAGE3 - Message overlapping with box Word wrap
- Footer Wrap last line of description to print longer company names up to 64 characters

5. RMFactuur.rep
6. RMFactuurbtwAanEinde.rep
7. RMInkoop.rep
8. RMOfferte.rep
9. RMPakbon.rep - No date on document print
    - Added Static label Datum:
    - Added Expression *'FORMATSTR('dd-mm-yyyy',DOCUMENTKOP.DDate)'*
10. RMPOS.rep
11. RMRetourzending.rep
12. RMSTARTSP100.rep

NOTE - Not done

- Kassabon VM.rep - To print this layout file, the HORECAPOS plugin need to be activated and configured.
- Removed 2 layout files for specific users.

Document layout files saved as the html file type

Before fixes

Example of overlapping and untidy presentation in document layout files when a document is saved as an html file and opened in a web browser:



After Fix

The overlapping and untidy presentation in document layout files when a document is saved as an html file and opened in a web browser is fixed:



Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's HTML5 template

FIXED - Reports layout long descriptions and data - Layout files-Labels-Statements

Company data " SCompanyName {chartype}(64) "

Company name supports up to 64 characters in Setup → Company info - this will print ok on most reports. In the case of Creating a Set of Books from scratch, using the "*Customise your own Set of Books (Advanced)?*" option - for 3-Digits to 8-Digit main accounts in the Chart of Accounts, the Company data " SCompanyName {chartype}(64) " field in the SYSVARS table allows for 64-characters to be entered. Only about 42-characters will print on the debtor statements, creditor remittance advices, layout files. More than 42-characters may not print or overlap with the address details.

The following reports and layout files is adjusted:

Debtor statements

- Reports → Debtors → Debtor statements - Debtor statement - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_1090 -
- Reports → Debtors → Debtor statements - Debtor statement - Outstanding - Location : plug_ins\reports\systemreports\TRN_160\TRN_1090\TRN_906552 -

Remittance advises

- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Location : plug_ins\reports\systemreports\TRN_161\TRN_1089 -
- Reports → Creditors → Creditor remittance advise - Creditor remittance advise - Outstanding - Location : plug_ins\reports\systemreports\TRN_161\TRN_906551 -

Debtor / Creditor - Print labels - FIXED

These labels does not support longer account descriptions and Contact names and needs to be rechecked.

Debtor labels

- Reports → Debtors → Print labels - Delivery address labels - Location : plug_ins\reports\systemreports\TRN_160\TRN_68\TRN_906064 -
- Reports → Debtors → Print labels - Postal address labels - Location : plug_ins\reports\systemreports\TRN_160\TRN_68\TRN_906137 -

Creditor labels

- Reports → Creditors → Print labels - Delivery address labels - Location : plug_ins\reports\systemreports\TRN_161\TRN_68\TRN_906064 -
- Reports → Creditors → Print labels - Postal address labels - Location : plug_ins\reports\systemreports\TRN_161\TRN_68\TRN_906137 -

Context menu - Print labels

- Debtors grid - context menu - Reports → Selected debtor label - Location : plug_ins\reports\REPORTS\DEBTOR\reports]LANG_TRN_906062 -
- Debtors grid - context menu - Reports → Selected debtor delivery label - Location : plug_ins\reports\REPORTS\DEBTOR\reports]LANG_TRN_906065 -
- Creditors grid - context menu - Reports → Selected creditor label - Location :

plug_ins\reports\REPORTS\CREDITOR\reports]LANG_TRN_906063 -

- Creditors grid - context menu - Reports → Selected creditor delivery label - Location : plug_ins\reports\REPORTS\CREDITOR\reports]LANG_TRN_906066 -

Example



Combine expressions will contact spaces and auto expand

The combined expressions will only allow to set the FontStyle to Bold or Regular

In Reportman in osFinancials does not support mixed FontStyle control inside the same expression

Studies suggest: Around 5-10% of business names in some countries exceed 60 characters.

```
LABEL.SDESCRIPTION+#13+#10+IIF((LABEL.SDESCRIPTION  <> LABEL.FIRSTNAME+ LABEL.LASTNAME)
 and (trim(LABEL.FIRSTNAME+ LABEL.LASTNAME) <> ''), +''+
CUSTOM('GETTEXTLANG',2048,'Name',0,0,0)+':   '  +LABEL.FIRSTNAME  +LABEL.LASTNAME  +
#13+#10,'')

+ LABEL.SPOSTAL1

+  #13+#10  +  LABEL.SPOSTAL2

+  #13+#10  +  LABEL.SPOSTAL3+  #13+#10  +  LABEL.SPOSTALCODE
```

Looking for a solution to add the Bold FontStyle only to be applicable to the first field (LABEL.SDESCRIPTION) and the rest of the combined expression to apply the Regular FontStyle.

Maybe this could be done in the Print condition



Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with a Help Authoring Tool

FIXED - Reports - Numbering format

Stock - Sidebar reports

Value stock account

Can also be printed for selected stock items - Context menu - Print single item.

Location : ...\plug_ins\reports\REPORTS\STOCK\LANG_906588.rep -

TRpExpression3 - = ##,###,###,##0.00

Changed the following expressions to = ##,###,###,##0.00 as in the Details section to be consistent number formatting in TOTALS and GRAND TOTALS sections

TRpExpression11 - 0.00

TRpExpression28 - 0.00

Created with the Standard Edition of HelpNDoc: Effortlessly optimize your documentation website for search engines

FIXED - User reports

FIXED - User reports - No data to print message

Prints the reports without data. If an invalid selection or periods is selected on the report parameters screen, a message will be displayed:

"No data to print!"

Debtor - Age analysis - Balances

Location : ...\plug_ins\reports\userreports\TRN_160\TRN_65\TRN_906147.rep

Creditor - Age analysis - Balances

Location : ...\plug_ins\reports\userreports\TRN_161\TRN_65\TRN_906147.rep

Linked the "Subreport-1" to the TRANSACTION_DETAIL Dataset - changed to "Subreport-1 (TRANSACTION_DETAIL)" and "P.Only data avail."=True setting.

MSSQL ERRORS -userreports

Debtors outstanding at date

User reports → Debtors → Outstanding → Debtors outstanding at date

Location : ...\plug_ins\reports\userreports\TRN_160\TRN_947\TRN_906104.rep

TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found

Creditors outstanding at date

User reports → Creditors → Outstanding → Creditors outstanding at date

Location : ...\plug_ins\reports\userreports\TRN_161\TRN_947\TRN_906103.rep

TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found

userreports translation of folders launch systemreports reports

Userreports - Using translations for folders e.g. Tax - TRN_906020 in the userreports folder

Accessing Tax as in this example, from the User reports menu, the Tax reports in the systemreports folder will be accessed.

		Internal report name		
Tax	*TRN_906020*			
	Transactions	*TRN_20069.rep*		
	Tax list debtor with tax id	*TRN_3675.rep*		
	Tax per period	*TRN_906105.rep*		
	Tax report - Reference / Document no.	*TRN_906550.rep*		
	Tax list creditor with tax id	*TRN_906553.rep*		

To Work around this - Need to use

- Choose a different Language label in Tools → Customise language (Setup ribbon) which is not used in the systemreports folder, for example TRN_609 - Tax
- Use Text for the folder name

Restructured - User reports menu = plug_ins\reports\userreports

Folder / Menu	*Report name*		
Custom reports	*Creditor-Purchases.rep*	*2cred-sku-det.rep - Renamed*	*This report prints the Purchases and Supplier return as well as Orders for a selected creditor (supplier / vendor) account.*
	Debtor-Sales.rep	*2deb-sku-det.rep - Renamed*	*This report prints the Invoices and Credit notes as well as Quotes for a selected debtor (customer / client) account.*

Tax	*TRN_609*	*TRN_906583*	*TAX-LIST-RATES.rep*	*Tax list and tax rates with percentages and status (active / inactive). This report is used to indicate if tax (VAT/GST/Sales tax) percentages and status is correct. After import of accounts. the first tax sub-account (tax code) may not include the Tax tab. Zero-rated Tax percentages if not listed, needs to be entered and saved in Setup → Accounts.*
Tutorial reports				*These reports is used in this documentation to illustrate some basics in Report designer and parameters. See - Reportman - Create new empty reports from Empty report.*
	Afrikaans		*Merged from / Replaced - MY - Verslae*	
		Debiteure	*Debiteurlys*	
		Krediteure	*Krediteurlys*	
	English		*Merged from / Replaced - My Reports*	
		Debtors	*My Debtor List*	
		Creditors	*My Creditor List*	

Age analysis reports

In addition to the Age analysis report (on the Reports ribbon) or accessed from the Open item link - Due tab, the Debtor Age analysis and Creditor age analysis reports on the User reports menu provides a different view to manage the data contained in the Debtor statements and Creditor remittance advices on the Reports menu.

NOTE : In osFinancials5 these Age analysis reports is included in the User reports menu.

NOTE : In osFinancials4 these Age analysis reports were included in the Reports menu.

These ageing reports are in addition to the one on the (Reports ribbon)

User reports → Debtors → Age analysis

Location : ...\plug_ins\reports\userreports\TRN_160\TRN_65\

	osFinancials5	*osFinancials4*	
Language ID	*Debtor age analysis report name* *userreports/TRN_160/TRN_65/*	*Debtor statement report name* *systemreports/TRN_1090/*	*Debtor statement*
TRN_906142.rep	*Balances detail*	*TRN_1090*	*Debtor statement*
TRN_906143.rep	*Balances detail history (open item)*	*TRN_906552*	*Debtors statement - Outstanding*
TRN_906147.rep	*Balances*		

User reports → Creditors → Age analysis

Location : ...\plug_ins\reports\userreports\TRN_161\TRN_65\

	osFinancials5	*osFinancials4*	
Language ID	*Creditor age analysis report name* *userreports/TRN_161/TRN_65/*	*Creditor remittance advice report name* *systemreports/TRN_1089/*	*Creditor remittance advice*
TRN_906142.rep	*Balances detail*	*TRN_1089*	*Creditor remittance advice*
TRN_906143.rep	*Balances detail history (open item)*	*TRN_906551*	*Creditor remittance - Outstanding*
TRN_906147.rep	*Balances*		

Outstanding - userreports

NOTE : In osFinancials5 these Outstanding reports is included in the User reports menu.

NOTE : In osFinancials4 these Outstanding reports were included in the Reports menu.

User reports → Debtors → Outstanding

Location : ...\plug_ins\reports\userreports\TRN_160\TRN_947\

	osFinancials5		osFinancials4	
Language ID	Debtors → outstanding report name userreports/TRN_160/TRN_947/		Debtors → outstanding report name systemreports/TRN_160/947/	Outstanding
TRN_2222	Due date		TRN_2222	Due date
TRN_906104	Debtors outstanding at date	osFinancials5 MSSQL Error TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found	TRN_906104	Debtors outstanding at date

User reports → Creditors → Outstanding

Location : ...\plug_ins\reports\userreports\TRN_161\TRN_947\

	osFinancials5		osFinancials4	
Language ID	Creditors → Outstanding report name userreports/TRN_161/TRN_947/		Creditors → Outstanding - report name systemreports/TRN_161/947/	Outstanding
TRN_2222	Due date		TRN_2222	Due date
TRN_906103	Creditors outstanding at date	osFinancials5 MSSQL Error TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found	TRN_906103	Creditors outstanding at date

OLDER - Changelog - User reports menu = plug_ins\reports\userreports

The following tables (highlighted with yellow text) indicates the changelog of reports which is fixed.

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
Custom reports					
			2cred-sku-det.rep	Renamed Creditor-Purchases	FIXED
			2deb-sku-det.rep	Renamed Debtor Sales	FIXED
My reports			My Creditor List	Delete - Merge with Tutorial reports - English	FIXED
			My Debtor List	Delete - Merge with Tutorial reports - English	FIXED
My versIae					
			Debiteurlys	Delete - Merge with Tutorial reports - Afrikaans	FIXED
			Krediteurlys	Delete - Merge with Tutorial	FIXED

				reports - Afrikaans	
Debtors		TRN_160			
	Age analysis	TRN_65			
		Balances detail	TRN_906142.rep	MSSQL ERROR TRANSACTIONSPERIODE1: Operand type clash: datetime2 is incompatible with int	FIXED
		Balances detail history (open item)	TRN_906143.rep	PRINTS MSSQL and Firebird	FIXED
		Balances	TRN_906147.rep	MSSQL ERROR RANSACTIONSPERIODE1: Operand type clash: datetime2 is incompatible with int	FIXED
	Outstanding	TRN_947			
		Due date	TRN_2222.rep		FIXED
		Debtors Outstanding at date	TRN_906104.rep	MSSQL ERROR TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found	Prints on Firebird databases - MSSQL ERROR - NOT FIXED
Creditors		TRN_161			
	Age analysis	TRN_65			

		Balances detail	*TRN_906142.rep*	*TRANSACTIONSPERIODE1: Operand type clash: datetime2 is incompatible with int*	*FIXED* *UNICODE SETTING arithmetic exception, numeric overflow, or string truncation*
		Balances detail history (open item)	*TRN_906143.rep*	*PRINTS MSSQL and Firebird*	*FIXED* *UNICODE SETTING arithmetic exception, numeric overflow, or string truncation*
		Balances	*TRN_906147.rep*	*TRANSACTIONSPERIODE1: Operand type clash: datetime2 is incompatible with int*	*FIXED* *UNICODE SETTING arithmetic exception, numeric overflow, or string truncation*
	Outstanding	*TRN_947*			
		Due date	*TRN_2222.rep*		*FIXED*
		Creditors Outstanding at date	*TRN_906103.rep*	*MSSQL ERROR* *TRANSACTION_DETAIL:ACCLIST:Parameter 'DDATETOFL' not found*	*Prints on Firebird databases - MSSQL ERROR - NOT FIXED*
Tax		*TRN_906020*			

			TAX-LIST-RATES.rep		FIXED
Tutorial reports					FIXED

User reports menu - Graph - File names

Graphs (TRN_906557)

Graphs is currently added in the User reports menu.

Graphs per week (TRN_906558)

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
Ledger	TRN_1372				
		Graph - Profit Loss per week	TRN_906169.rep		OK
Debtors	TRN_160				
		Graph - Debtors per week	TRN_906168.rep		OK
Creditors	TRN_161				
		Graph - Creditors per week	TRN_906167.rep		OK
Sales	TRN_1792				
	Quotes per period	TRN_3568			
		Graph - Quotes per week - Quantities	TRN_906323.rep		OK
		Graph - Quotes per week - Amount	TRN_906324.rep		OK

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
	Credit notes per period	TRN_3569			
		Graph - Credit notes per week - Quantities	TRN_906319.rep		OK
		Graph - Credit notes per week - Amount	TRN_906320.rep		OK
	Invoices per period	TRN-3570			
		Graph - Invoices per week - Quantities	TRN_906170.rep		OK
		Graph - Invoices per week - Amount	TRN_906171.rep		OK
	Sales per period	TRN_906122			
		Graph - Invoices - Credit notes per week - Quantities	TRN_906579.rep		OK
		Graph - Invoices - Credit notes per week - Amount	TRN_906580.rep		OK
Purchases		TRN_302			
	Purchases				
		Graph - Purchases - Supplier returns per week - Quantities	TRN_906581		OK
		Graph - Purchases - Supplier returns per week - Amount	TRN_906582		OK
	Orders per period				
		Graph - Orders per week - Quantities	TRN_906325.rep		OK

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
		Graph - Orders per week - Amount	TRN_906326.rep		OK
	Supplier returns per period				
		Graph - Supplier returns per week - Quantities	TRN_906321.rep		OK
		Graph - Supplier returns per week - Amount	TRN_906322.rep		OK
	Purchases per period				
		Graph - Purchases per week - Quantities	TRN_906289.rep		OK
		Graph - Purchases per week - Amount	TRN_906290.rep		OK

Graphs per month (TRN_906559)

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
Ledger	TRN_1372				
		Graph - Profit Loss per month	TRN_906560.rep		OK
Debtors	TRN_160				
		Graph - Debtors per month	TRN_906561.rep		OK
Creditors	TRN_161				
		Graph - Creditors per month	TRN_906562.rep		OK
Sales	TRN_1792				

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
	Quotes per period	TRN_3568			
		Graph - Quotes per month - Quantities	TRN_906563.rep		OK
		Graph - Quotes per month - Amount	TRN_906564.rep		OK
	Credit notes per period	TRN_3569			
		Graph - Credit notes per month - Quantities	TRN_906565.rep		OK
		Graph - Credit notes per month - Amount	TRN_906566.rep		OK
	Invoices per period	TRN-3570			
		Graph - Invoices per month - Quantities	TRN_906567.rep		OK
		Graph - Invoices per month - Amount	TRN_906568.rep		OK
	Sales per period	TRN_906122			
		Graph - Invoices - Credit notes per month - Quantities	TRN_906569.rep		OK
		Graph - Invoices - Credit notes per month - Amount	TRN_906570.rep		OK
Purchases		TRN_302			
	Purchases				
		Graph - Purchases - Supplier returns per month - Quantities	TRN_906571.rep		OK

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name		
		Graph - Purchases - Supplier returns per month - Amount	TRN_906572.rep		OK
	Orders per period				
		Graph - Orders per month - Quantities	TRN_906574.rep		OK
		Graph - Orders per month - Amount	TRN_906573.rep		OK
	Supplier returns per period				
		Graph - Supplier returns per month - Quantities	TRN_906576.rep		OK
		Graph - Supplier returns per month - Amount	TRN_906575.rep		OK
	Purchases per period				
		Graph - Purchases per month - Quantities	TRN_906578.rep		OK
		Graph - Purchases per month - Amount	TRN_906577.rep		OK

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

FIXED - Remittance - reports plugin

FIXED - Remittance - reports plugin

Remittance - reports plugin - doctype - layouts

Location : ...\plug_ins\reports\remittance\doctype\layouts

- Remittance 1
- Remittance 2
- Remittance 3
- Remittance 4

These "*Open item selection*" layout files can also be printed from the Remittance plugin on the Default ribbon and edited in Report designer in the " ...\plug_ins\reports\remittance\doctype\layouts " folder

Updated ADMINISTRATIEGEGEVENS

Updated ADMINISTRATIEGEGEVENS to add the SYSVARSEXT table to the sql - This add Website, Mobile and Contact name fields.

First line

```
Select a.*,
```

last line

```
from sysvars,
sysvarsext a
```

Added - Dataset for REMARKS and lined to DOCUMENTREGEL

SQL

```
select scomment from docline_comment where wdocid = :wdocid and wlineid =:wdoclineid
```

Added expression to Detail_2 (Subreport-2)

```
DATASETASSTRING('REMARKS')
```

MSSQL Error DOCUMENTREGEL Dataset

In MSSQL Databases error in doctype - layouts

```
DOCUMENTREGEL:Incorrect syntax near '|'.
```

Current SQL

```
Select
messages.sdescription || coalesce(messages.sExtradescription,'') Description,
WDOCLINEID, WDOCID, WSTOCKID, WLINETYPEID,
WDESCRIPTIONID, FQTYORDERED, FQTYSHIPPED,
FSELLINGPRICE, FITEMDISCOUNT,docline.WTAXID,
FEXCLUSIVEAMT, FINCLUSIVEAMT, FTAXAMOUNT,
docline.DSYSDATE, SUNIT, SSTOCKCODE,
WPROFILEID, WSERIALNOID,
tax.FRate
from docline left join messages on (docline.WDescriptionid = messages.WMessageID)
left join tax on (docline.WTaxID = tax.WAccountID)
where WDocId=:TCVAR_DocID
```

Changed || to +prints in MSSQL databases but produces error in Firebird database types

DOCUMENTREGEL:Dynamic SQL Error
expression evaluation not supported

Change to CONCAT function, which is available in MSSQL and is specifically designed for string concatenation. The + operator can also be used for concatenation, but make sure that the types involved are compatible for concatenation.

This SQL prints in both MSSQL database types and Firebird database types

```
Select
messages.sdescription {concat} coalesce(messages.sExtradescription,'') Description,
WDOCLINEID, WDOCID, WSTOCKID, WLINETYPEID,
WDESCRIPTIONID, FQTYORDERED, FQTYSHIPPED,
FSELLINGPRICE, FITEMDISCOUNT,docline.WTAXID,
FEXCLUSIVEAMT, FINCLUSIVEAMT, FTAXAMOUNT,
docline.DSYSDATE, SUNIT, SSTOCKCODE,
WPROFILEID, WSERIALNOID,
```

```
tax.FRate

from docline left join messages on (docline.WDescriptionid  = messages.WMessageID)

left join tax on (docline.WTaxID = tax.WAccountID)

where WDocId=:TCVAR_DocID
```

Before fix



After fix



Remittance - reports plugin Reminders

Headers and Footers - Standardised with Empty.rep and all reports

- Headers updated - COMPANYDATA dataset to include Website
- Footers - Two pass report setting

Remittance list

Location : ...\plug_ins\reports\remittance\list.rep

Before fix



After fix - Standardised Headers and Footers with Data



After refix

Added report name "*Remittance = List*" and Applied Word wrap and Auto Expand / Auto Contract settings



Remittance - reports plugin - language folders

English

Location : ...\plug_ins\reports\remittance\en\layouts

1. default.rep
2. Reminder.rep
3. Reminder2.rep
4. Remittance.rep
5. Remittance2.rep

Before fix

These reports will be populated with data when reminders is processed.

Header - Company address standardised with other reports

Debtor address Address1 - Address2 - Address 3 and Postal code



After fix



Nederlands

Location : ...\plug_ins\reports\remittance\nl\layouts

1. default.rep
2. Aanmaning.rep
3. Aanmaning2.rep

4. Herinering.rep

5. Herinering2.rep

Before fix

These reports will be populated with data when reminders is processed.

Aanmaning - Similar than the English Reminders.

Header - Company address standardised with Nederland document layout files

Debtor address Address1 - Postal code -Address2 - Address 3

After fix



Firebird Error - default.rep in English and Nederland

English

Location : ...\plug_ins\reports\remittance\en\layouts\default.rep

Nederlands

Location : ...\plug_ins\reports\remittance\nl\layouts\default.rep

> Could not convert variant of type (UnicodeString) into type (Double)

and within Reportman

> Could not convert variant of type (UnicodeString) into type (Double)
> TODATE=11-10-2006

The error message "*Could not convert variant of type (UnicodeString) into type (Double*)" in Firebird databases suggests that there is an issue with data conversion, particularly involving a Unicode string and a Double data type.

In your provided information, you also mentioned "*TODATE=11-10-2006*." It seems like there might be an attempt to convert a string ("*11-10-2006*") to a Double data type using the TODATE function in Firebird.

Here are a few steps you can take to troubleshoot and resolve the issue:

1. Check the Data Type Compatibility: Ensure that the data types used in your expressions are compatible. If you are using the TODATE function, make sure that the input is a valid date format.

   Example: sql

   ```
   SELECT TODATE('11-10-2006', 'DD-MM-YYYY') FROM YourTable;
   ```

2. Verify Data Formats: Double-check the format of the date string. In the example above, the format is 'DD-MM-YYYY'. If your date string follows a different format, adjust the format accordingly.

3. Handle NULL Values: If your data might contain NULL values, consider adding conditions to handle them appropriately. For instance, use the COALESCE function to replace NULL values with a default or handle them in another way.

4. Explicit Type Conversion: If you're dealing with mixed data types, explicitly convert the data types using appropriate functions. For example, you can use the CAST or CONVERT function to explicitly convert a string to a Double if needed.

   Example: sql

   ```
   SELECT CAST('11-10-2006' AS DOUBLE PRECISION) FROM YourTable;
   ```

5. Review the SQL Statement: Check the entire SQL statement or query for any other potential issues. Look for areas where data types might conflict.

Without seeing the full query or knowing more about the database structure, these are general suggestions. If the issue persists, providing more details about the relevant part of your SQL query and the database schema would be helpful for further assistance.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

FIXED - Subscriptions - reports

NEW : Reports → Subscriptions - Added in osFinancials5.1.0.193

Menu access : Debtors grid - Context menu - Reports → Subscriptions

Location : …\plug_ins\reports\REPORTS\DEBTOR\reports\TRN_9061000.rep – Subscriptions

Location on GitHub : *osfinancials-development/reports/plug_ins/reports/REPORTS/DEBTOR/reports/LANG_901000.rep at main · Digidanosf/osfinancials-development · GitHub*

FIXED

Translated "*Bedrag*" Static text label TrPExpression19 to include customer language translation Amount Incl. LabelID 651.

```
CUSTOM('GETTEXTLANG',651,'Amount   Incl.',0,0,0)
```

On this report, these amounts prints inclusive of Tax (VAT/GST/Sales tax), while on other Subscription reports (i.e. "Reporting group1, Reporting group 2, Subscriptions and Subscription list" in the …/plug_ins\reports\REPORTS\SUBSCRIPT folder, the Amounts are printed exclusive of Tax (VAT/GST/Sales tax).

Added Label for Total LabelID 960 to be consistent with other Subscription reports.

Report Header - Standardised Header in line with other reports to accommodate larger field lengths in databases overlapping text.

Report Footer - Standardised Footer in line with other reports to accommodate larger field lengths in databases overlapping text.

Report footer was not printing - Setup page - Two-pass report setting.

Display format : Expression amount format Amount was set to 0.00 – Changed to ###,###,##0.00 to be consistent with document layout files and other reports in the systemreports folder (accessible from Reports menu and userreports folder accessible from the User reports menu on Reports ribbon), etc.

Before Fix



After Fix



This will also support the required Windows Number format setting when you click on the Print button of the “Budget vs actual” and “This year vs last year” reports.

Subscription plugins layouts

English layout

Location : …\plug_ins\reports\Subscriptions\en\layouts\default.rep

Location on GitHub : osfinancials-development/reports/plug_ins/reports/Subscriptions/en/layouts/default.rep at main · Digidanosf/osfinancials-development · GitHub

Before fix



After fix



Display format : Expression amount format Amount was set to 0.00 – Changed to ###,###,##0.00 to be consistent with document layout files and other reports in the systemreports folder (accessible from Reports menu and userreports folder accessible from the User reports menu on Reports ribbon), etc.

This will also support the required Windows Number format setting when you click on the Print button of the “Budget vs actual” and “This year vs last year” reports.

Netherlands layout

Location : …\plug_ins\reports\Subscriptions\nl\layouts\default.rep

Location on GitHub : osfinancials-development/reports/plug_ins/reports/Subscriptions/nl/layouts at main · Digidanosf/osfinancials-development · GitHub

Before fix



After fix



Display format : Expression amount format Amount was set to 0.00 – Changed to ###,###,##0.00 to be consistent with document layout files and other reports in the systemreports folder (accessible from Reports menu and userreports folder accessible from the User reports menu on Reports ribbon), etc.

This will also support the required Windows Number format setting when you click on the Print button of the “Budget vs actual” and “This year vs last year” reports.

Subscriptions plugin reports

Location : ...\plug_ins\reports\REPORTS\SUBSCRIPT

Location on GitHub : osfinancials-development/reports/plug_ins/reports/REPORTS/SUBSCRIPT at main · Digidanosf/osfinancials-development · GitHub

Report print options : Subscriptions on Default ribbon, if activated.



Report names added to output print

Report language ID	*Report name*	*Added report name to output*
LANG_1323	*Reporting group 1*	*Subscriptions - Reporting group 1*
LANG_1325	*Reporting group 2*	*Subscriptions - Reporting group 2*
LANG_901000	*Subscriptions*	*Subscriptions*
LANG_901001	*Subscriptions list*	*Subscriptions list*

Headers and Footers - Standardised with Empty.rep and all reports

- Headers updated - COMPANYDATA dataset to include Website
- Footers - Two pass report setting

Added Report headings on report output

Display format : Expression amount format Amount was set to 0.00 – Changed to ###,###,##0.00 to be consistent with document layout files and other reports in the systemreports folder (accessible from Reports menu and userreports folder accessible from the User reports menu on Reports ribbon), etc.

This will also support the required Windows Number format setting when you click on the Print button of the “Budget vs actual” and “This year vs last year” reports.

Subscriptions - Reporting group 1

Before fix



After fix



Subscriptions - Reporting group 2

Before fix



After fix



Subscriptions

Before fix



After fix



Subscriptions list

Before fix



After fix



Created with the Standard Edition of HelpNDoc: Converting Word Docs to eBooks Made Easy with HelpNDoc

Known issues - Plugins

Links to Manuals on from osFinancials shop

FIXED : Aover 400 broken links in documentation English Help online and Afrikaans Help online and in EngHelp.chm for both versions

English Online help | Afrikaans Online help

Outstanding - Other apps

App at Google play - osFinancials simple POS scanner -

App at Google play - Chords and lyrics flow - For the music lovers

Error 404 Broken links

osF local webserver download now link - http://www.osf-boekhoudpakket-administratie.nl/index.php/nl/downloaden

http://www.osf-boekhoudpakket-administratie.nl/index.php/nl/downloaden Error 404

Broken links

https://www.osfinancials.org/en/webshop/debtor-creditor-control/pain/sepa-incasso-export Error 404

http://www.osf-boekhoudpakket-administratie.nl/index.php/en/webshop/best-sellers/bankimport-plug-in Error 404

Manual links on Plugins shop cause errors in some Web browsers

refers to - osf-boekhoudpakket

Microsoft Edge Web browser Launch the webshop

On the CRM Shop page - links to The Shop (https://www.osfinancials.org/index.php/en/webshop/industry-specific/crm-%28customer-relations-managament%29} but links from the Manual tab to the boekhoudpaket webpage (not secure - Maybe the certificate has expired (http://www.osf-boekhoudpakket-administratie.nl/index.php/en/plugin-manuals/425-crm-customer-relations-management-plugin)

Error 404

Category not found

- Please try one of the following pages:
- If difficulties persist, please contact the System Administrator of this site and report the error below.

- info@osf-boekhoudpakket-administratie.nl

Page from this link displays correct on can load Firefox and Chrome Web browsers but not in MS Edge - Edge or other browsers may block the manuals page)

Notes and screenshots

It appears that you're experiencing difficulties accessing links to various Manuals on the osFinancials shop website, particularly those originating from the osf-boekhoudpakket webpages. This issue is specific to Microsoft Edge, where you encounter a 404 error (Category not found) when attempting to access these manuals. In contrast, these links load correctly in Firefox and Chrome web browsers.

The issue seems to be related to the fact that the manuals webpage links start with `http://`, which may cause compatibility problems in certain web browsers, including Microsoft Edge. In contrast, the osFinancials webshop pages, which start with `https://`, load correctly in most web browsers.

Other users might also encounter similar issues depending on their browser settings. It's recommended to check and adjust your browser settings or use an alternative browser like Firefox or Chrome as a temporary workaround.

Example CRM webshop Webpage - start with https://



Example CRM Webpage - Link to Manual start with http:// - Error in Manuals link on Microsoft Edge



Example CRM Webpage - Link to Manual start with http:// - Manuals link in Chrome refers to "Not secure" but Manuals page loads.



Example CRM Webpage - Link to Manual start with http:// - Manuals link in Firefox refers to "Connection is not secure" but Manuals page loads.

osFinancials.org - Broken links

https://www.osfinancials.org/en/webshop/most-sold/bankimport-plug-in

launched from webshop link from https://www.osfinancials.org/en/plugin-manuals/171-document-email-pro - "To work with the document email pro, the plugin needs to be activated. There are two ways of activating the document email pr plug-in. You can get a trial version of the plugin *or* you can buy a licence. For getting a trail or a licence you have to go to our web shop. If you have purchased a licence or requested for a trail you can collect the licence codes immediately. Follow the steps of the manual Plugin activation to retrieve your licence codes."

Documentation for Plugins

Plugins menu structure

On the Setup ribbon, select Plugins.



When all Plugins are activated from the Tools → Activate plugins option on the Setup ribbon, the Plugins menu is structured and grouped into seven categories: Document plugins, External system links, Financial tools, Generic plugins, Point-of-Sale, Stock plugins, and Tools.

Document plugins

Plugin name	*External links / Licence*	*B u g s*	*T r a n*

			Known issues / Solutions
	Document EMail Pro Plugin	Manual - Shop - Licence : Once-off - This Plugin is included in the osFinancials5 subscription.	Known issues / Outstanding
	Document Export / Import plugin	Manual - Shop - Licence: Once-off	Known issues / Outstanding
	Subscriptions plugin	Manual - Shop - Licence : Annual fee	Known / Out

				Wish list / Issues / Standing
	Price agreement plugin	Manual - Shop - Licence : Once-off	-	Out standing

External system links

Plugin name	External links / Licence	Bugs / Known issues	Translations

	E-Commerce Plugin -	*E-Commerce manual - osCommerce manual - Shop - Licence : Annual licence*	*N/A*
	Mijnwinkel plugin / MyShop	*Manual - Shop - Licence : Once-off*	*N/A*
	Web Export Plugin	*Manual - Shop - Licence : Once-off*	*N/A*
	Postalcode / tax id / reg. no. lookup Plugin - (Postal Code / Tax ID / Registration Number Lookup) -	*Shop - Licence :*	*N/A*

Supported Languages: Netherlands

	Promeetec Export Plugin	*Shop - Licence : Annual subscription.*	*N/A*
	Send Package Plugin	*Manual - Shop - Licence : Once-off*	

Supported language: Netherlands

Financial tools

	Plugin name	*External links / Licence*	*Bugs / Trans*

			Known issues	Installation issues
	Activa plugin	Manual - Shop - Licence : Once-off	Known issues	Outstanding
	Charter plugin	Manual - Shop - Licence : Once-off	Known issues	Outstanding
	DrillDown plugin	Manual - Shop - Licence : Once-off	Known	Outs

			Outstanding Issues
	Office Pro *Bookkeeping Pro*	*Manual - Shop - Licence : Annual subscription* *Manual - Shop - Licence : Annual subscription*	Known Outstanding Issues
	Remittance	*Manual - Shop - Licence : Once-off*	Outstanding
	BtwBE - Belgische BTW Plugin	*Manual - Shop - Licence :*	Support

Netherlands language:

XML Audit file Plugin - Manual - Shop - Licence :

Supported language:

				Netherlands

Generic plugins

Generic plugins (Plugins menu)

	Plugin name	External links / Licence	Bugs / Known issues	Translations
	CRM (Customer Relations Management)	Manual - Shop - Licence : Annual licence		Outsta

			Outstanding
	Freefields plugin	Manual - Shop - Licence : Once-off	Outstanding
	Multi-User Calendar (Agenda)	Manual - Shop - Licence : Once-off	Outstanding
	Multimedia	Manual - Shop - Licence : Once-off	Outstanding

			[ing](#)

Other Generic plugins (Other)

	Plugin name	External links / Licence	Bugs/Known issues	Translations
	Multi Media Pack	Manual - Shop - Licence : Once-off		
	Paperless Office Multimedia Plugin	Manual - Shop - Licence : Once-off		

Point-of-Sale

	Plugin name	External links / Licence	Bugs/	Trans

Installations

Known issues

Supported language: Netherlands

Manual - Shop - Licence :

CCV Pin - PIN

	Customer on hold	*Manual - Shop - Licence : Once-off*	
	HORECAPOS -See	*Shop - Licence : Annual subscription - The HORECAPOS Plugin is sold with the support contract and multi-user plugin for free.* *See - Video of the latest version(Dutch) Video of an older version(Dutch) .*	
	HorecaPOS addition quantity on hand adjustment	*Manual - Shop - Licence : Annual subscription*	* * * *
	POSDisplay Plugin	*Manual - Shop - Licence : Once-off*	
	POS Points - Customer loyalty points	*Manual - Shop - Licence : Once-off*	
	RetailPOS -	*Manual - Shop - Licence : Annual subscription*	

Stock plugins

	Plugin name	*External links / Licence*	*Bugs/Known issues*	*Transaction notes*

			s u e s
	Localisation-Batches-Serials	Manual - Shop - Licence: Once-off	Outstanding
	Stock check / Stock correction	Manual - Shop - Licence : Once-off	Outstanding
	Quick Order	Manual - Shop - Licence : Once-off	Outstanding

Tools

	Plugin name	External links / Licence	Bugs/Known issues	Translations
	AndroidConnector	Install manual - App manual - Shop - Licence : Once-off		
	FileandXML Export Import	Manual - Shop - Licence : Once-off		
	Export / Import	Manual - Shop - Licence : Once-off		
	HandyTools	Licence : Free. Caution: Make backups of your Set of Books before use		Outstand

			ing
	Reportman	Manual - Licence : Free Accessible from the Report designer icon on the Setup ribbon	Outstanding
	SQLBrowser	Manual - Shop - Licence : Once-off	Outstanding

DYNABREG

Register plugins

Register plugins - When you have purchased a plugin and you have received the registration code, you need to enter and add the codes to "*Register the plugins*"-screen.

Created with the Standard Edition of HelpNDoc: Effortlessly optimize your documentation website for search engines

Known-issues - Plugin - Stock Adjustments

ADDED - Document layout files for NON Standard document types

The following Document layout files for NON Standard document types were fixed in osFinancials5.1.0.109 update but not included in osFinancials5.1.0.127 / osFinancials5.1.0.189 update install:

DOCUMENTS/DOCUMENTS - Document layout files updated to fix overlapping labels, remarks, etc. to accommodate databases with larger input fields. Standardised the Company and Tax registration numbers before contact details, etc.

Selecting layout files for dedicated NON-Standard document types

In addition to the global setting for the six standard document types (i.e. Quotes, Invoices, Credit notes, Orders, Purchases and Supplier returns), layout files selected for each document type on the Setup → Documents setup menu (Setup ribbon), the "*Point-of-sale layout file*" field on the Documents setup screen could also be used to change layout files for NON-Standard document types in the osFinancials core and when specific plugins are activated.

For some NON-Standard document types, the , the "*Point-of-sale layout file*" field on the Documents setup screen does not print the selected layout file.



An option to change document numbers and customise descriptions such as "*Stock count correction*" for the StockCount plugin and "*Actief-Q-cor*" for the QuickOrder plugin.

Added : Layout files for NON-Standard document types : osFinanciald core

Adjustment - TRN_1767

Input → Adjust stock - Stock adjustments



BOM (Production) Stock Item Type - TRN_3266

Generated as a posted document for BOM stock items during Assemble or Disassemble options on the context menu of a BOM (Production) stock item type.

Document prefix: "SA" (e.g., "SA00001"), with a similar 7-digit format.

BOM (Production) - Assemble



BOM (Production) - Disassemble



Project - TRN_3556 - Project - Quote

Created from the Project Quotes tab for specific Projects.

Document prefix: "D" (e.g., "D000001"), following a 7-digit format.



Layout files for NON-Standard document types : Plugins

Stock in - TRN_906178

Stock in (TRN_906178) This layout file may be selected on the Documents grid or Creditors - Documents tab



Stock out - TRN_906179

Stock out (TRN_906179) This layout file may be selected on the Documents grid or Debtors - Documents tab



Comparison / Notes of Stock adjustments and plugins

	Document type	*Reports -> Stock In / Out Document type*	*Document number prefix*	*Search central - Document type*	*Posted / Unposted*	*Your reference*	*Item description*	*COS journal*	*Layout file heading*
Input → Adjust stock Stock adjustments	*Stock -*	*Stock in*	*ST - Stock adjustments: for example, "ST00001" .*	*Stock out Details*	*Posted*		*Auto correction (or remark entered in Change remark screen for example "Surplus"*		

					or "Shortage":	
	Stock in	*ST - Stock out*	*Stock out Details*		*Auto correction*	
Stock grid - Quantity column	*Stock in*	*ST - Stock out*	*Stock out Details*	*Posted*		

Plugins using the Point-of-sale layout file setting in Documents setup

Plugin name	*Document type*	*Reports -> Stock In / Out Document type*	*Search central - Document type*	*Document number prefix*	*Posted / Unposted*	*Your reference*	*Item description*	*Layout file heading*
Plugin - StockCheck - Generate	*Credit note*	*Credit note*	*Credit note Details*	*CR - Prefix - Documents setup*	*Unposted*	*Correction*	*Stock count correction*	*Credit note*
Plugin - QuickOrder - Generate	*Order*	*Order*	*Order Details*		*Unposted*	*Creditor account code*		*Order*
Plugin - QuickOrder - Stock count tab	*Stock-*	*Stock in*	*Stock out Details*	*ST - Stock out*	*Posted*	*Actief-Q-cor*	*Actief-Q-cor*	*POS Invoice*
Dynareg - Stock in document	*Stock-*			*SI -*	*Unpos*			*Stat*

type - 				Stock in	ted	eme nt
Dynareg - Stock in and Stock out document type - 	Stock in / Stock+ Stock out / Stock-	Stock out Stock in	Stock in Details Stock out Details	SI - Stock in ST - Stock out		Stat eme nt Adju stme nt
Dynareg - Extra stock of correction document (Stock in / Stock out document type) - 	Stock in	Stock in	Stock out Details	ST - Stock out		Adju stme nt
Input → Stock in menu - launches a stand-alone screen. New	Disass emble	BOM (Productio n)	Production Details	IN - Invoice	Canno t post or	Remi ttan ce

		delete documents	
Plugin - Dynanreg - Stock in document type	*Stock in*		*Statement*

Changing the Layout File for Point-of-Sale (POS) Documents

The default setting in the "*Point-of-sale layout file*" field on the "*Documents setup*" screen is "*POS - STARTSP100*," a till slip document layout file. To select a different layout file from the default document layout files included in the osFinancials installation or your own if you have created one, the document layout will be printed in that format.

When you alter the default Point-of-Sale (POS) layout file (or any other selected layout file), the changes will also impact documents generated with specific prefixes in various scenarios:

- *ST - Stock adjustments: Generated when stock quantities are modified within the Input → Adjust stock menu on the Default ribbon, these documents are prefixed with "ST," for example, "ST00001." Notably, the document number consists of 7 digits, including 4 zeros instead of 5.*
- *SA - BOM (Production) stock item type: Document numbers with the "SA" prefix, such as "SA00001," are generated for BOM (Production) stock items when they are Assembled or Disassembled. Similar to stock adjustments, the document number follows a 7-digit format with 4 zeros.*
- *D - Project Quotes: These documents are automatically created with a 7-digit format, starting with "D" followed by 6 numeric digits.*

the "*Point-of-sale layout file*" field on the "*Documents setup*" screen is "*POS -STARTSP100*,"

Print / Reprint document layout files

Documents can be printed/reprinted at any stage. To be able to print documents, you can select the document layout files stored in the " … \ *plug_ins* \ *reports* \ *DOCUMENTS* \ *DOCUMENTS* \ " directory or folder of your osFinancials5 installation on your system.

When you want to customize document layout files according to your requirements, it is recommended to make a copy of the existing document layout file, and save it under your unique name. To be able to select your own document layout files to print, print it must be " … \ *plug_ins* \ *reports* \ *DOCUMENTS* \ *DOCUMENTS* \" directory or file folder of your osFinancials5 installation stored on your system.

Options to print Document layout files

Documents may be printed / reprinted at any stage using the following options on the Default ribbon:

1. Documents - Selection screen (Print button). This will print the documents for the selected document for a specific document type.
2. Debtors (Documents tab) - Select a list on a document and print it. Allows you to search and filter for and locate specific document.
3. Creditors (Documents tab) - Select a list on a document and print it. Allows you to search and filter for and locate specific document.
4. Stock items (Document groups tab of a selected stock item) - Select a document and double-click to print it.
5. Search (Investigator) – Search and double click on a document.

Select layout files

Layout files for Standard document types

The layout files selected for each document type on the Setup → Documents setup menu (Setup ribbon) are the global default layout files that will be used to print documents. You may select up to two (2) Layout files for each document type (i.e. Quotes, Invoices, Credit notes, Orders, Purchases and Supplier returns).

Specific layout files may also be selected on the Default ribbon for:

1. Debtors - Delivery address tab - Each debtor (customer / client) account by selecting a different layout file in the Layout file 1 (Invoices), Layout file 2 (Credit notes), Layout file 3 (Quotes).

2. Creditors - Delivery address tab - Each creditor (supplier / vendor) account by selecting a different layout file in the Layout file 1 (Purchases), Layout file 2 (Supplier return), Layout file 3 (Orders).

The global settings will be over-ruled.

In addition to these settings, you may also select a different layout file when printing documents on the "*Layout file*" fields of the following options (Default ribbon):



- Documents - Selection screen (Print button) - You may select up to four (4) layout files. If you have selected a layout file for Layout file 2, Layout file 3 and/or Layout file 4, and you no longer want to print these layout files, you can select the blank option.
- Debtors (Documents tab)
- Creditors (Documents tab)

Point-of-sale layout file setting in Documents setup

Standard POS system (Input → POS Invoice [Ctrl+F6])

The default setting in the "*Point-of-sale layout file*" field on the Documents setup screen is "*POS - STARTSP100*," a till slip document layout file. To select a different layout file from the default document layout files included in the osFinancials installation or your own if you have created one, the document layout will be printed in that format. This file is specifically used for till slip documents, printed as "*POS Tax Invoice*" when using the standard POS system (Input → POS Invoice [Ctrl+F6]).



In the central search (Search on the Default ribbon), it will print this "*POS - START-SP100*" (TRN_906183). If any other layout file, is selected. the name of the report is not translated, but will display for example TRN_906183 in Setup → Point of-Sale - Printers tab



Changing the layout file in Setup → Documents setup will update the layout file in Setup → Point of-Sale - Printers tab but it still prints Stock in and Stock out using the POS - START-SP100 (TRN_906183) layout file.

Layout files for NON-Standard document types

In addition to the global setting for the six standard document types (i.e. Quotes, Invoices, Credit notes, Orders, Purchases and Supplier returns), layout files selected for each document type on the Setup → Documents setup menu (Setup ribbon), the "*Point-of-sale layout file*" field on the Documents setup screen could also be used to change layout files for NON-Standard document types in the osFinancials core and when specific plugins are activated.



An option to change document numbers and customise descriptions such as "*Stock count correction*" for the StockCount plugin and "*Actief-Q-cor*" for the QuickOrder plugin.

Document Scenarios and Prefixes in the Core

Stock Adjustments (ST)

- Generated as a posted document when stock quantities are adjusted (via Input → Adjust stock menu or by manually changing stock quantities on the stock item grid).
- Document prefix: "*ST*" (e.g., "*ST00001*"), with a 7-digit format including 4 zeros.
- Remarks entered in the "*Change remark*" screen (e.g., "*Surplus*" or "*Shortage*") or "*Auto correction*" are reflected in these documents.
- Selecting a different layout file on the "*Point-of-sale layout file*" field of the Documents setup screen, still defaults to the POS Invoice. This setting may not work as the alignment of the Document type on the Document groups tab of the Stock item reflected as Stock- and on the Reports → Stock In / Out reports it is reflected as Stock in. On Search (central search) the Details is reflected as Stock out Details.
- NOTE: The default POS Invoice does not include the Stock code. The Stock description will be replaced with remarks such as "*Surplus*", "*Shortage*" or "*Auto correction*".

Example : Adjustment (POS Layout file)



- NEW Layout file Added: Adjustment - TRN_1767 - This translatable layout file is specifically designed for adjustment documents, ensuring that all necessary details, including the stock code, are accurately represented and the document is correctly labelled as an "*Adjustment.*"

Example : Selecting Adjustment layout file - Adjustment (TRN_1767)



- Selecting Other Layout files to Print Adjustments: To print this document layout file; or other translatable document layout files for these stock adjustments, you can go to the Report designer and select the adjustment document from the Select test document id button and select the layout file such as "*Adjustment*" or any other layout file which includes the stock code such as Document layout (15codes) - (TRN_906277) or NO-TAX Document layout (15codes) - (TRN_906591). NOTE: The following layout files does not include the Stock code:
  - Layout file - (TRN_1910)
  - Document layout - (TRN_3174)
  - NO-TAX Layout file - (TRN_906589)
  - NO-TAX Document layout - (TRN_906590)

  NOTE : The stock code and stock description are not printed on these layout files. As a result, there is no audit trail to link or trace the stock items from these printed layout files.

BOM (Production) Stock Items (SA)

- Generated as a posted document for BOM stock items during Assemble or Disassemble options on the context menu of a BOM (Production) stock item type.
- Document prefix: "*SA*" (e.g., "*SA00001*"), with a similar 7-digit format.
- Selecting a different layout file on the "*Point-of-sale layout file*" field of the Documents setup screen,

prints the "*Assemble*" or "*Disassemble*" options on the selected document layout file. If a document layout file supporting the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Delivery note*" for "*Assemble*" option and "*Remittance*" for "*Disassemble*" option.

Example : Selecting existing layout files - Types description

Selecting the document layout files, which supports the " *TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Delivery note*" for "*Assemble*" option and "*Remittance*" for "*Disassemble*" option.

Example : Selecting existing layout files - Types description - Assemble

TYPES table - Delivery note - RecordID = 19 - WTYPEPARENT = 1



Example : Selecting existing layout files - Types description - Disassemble

TYPES table - Remittance - RecordID = 18 - WTYPEPARENT = 1



- NEW Layout file Added: BOM (Production) Stock Item Type - TRN_3266 - This translatable layout file will print the document name as BOM (Production) with the applicable "*Assemble*" or "*Disassemble*" options.

Example : BOM (Production) Assemble - Layout file (TRN_3266)



Example : BOM (Production) Disassemble - Layout file (TRN_3266)



- On Search (central search) the Details is reflected as follows:
  - Dissable Details - Should be "*Production Details*" since the document e.g. "*SA00001*" is created using the "*Assemble*" option. The document type is listed as "*Assemble*" on the Document groups and Transactions tabs of the stock item for the BOM (Production) stock item type and in Reports → Stock In / Out reports.
  - Production Details - Should be "*Disassemble Details*" since the document e.g. "SA00002" is created using the "*Disassemble*" option. The document type is listed as "*Disassemble*" on the Document groups and Transactions tabs of the stock item for the BOM (Production) stock item type and in Reports → Stock In / Out reports.



Project Quotes (D)

- Created from the Project Quotes tab for specific Projects.
- Document prefix: "*D*" (e.g., "*D000001*"), following a 7-digit format.



- Selecting a different layout file on the "*Point-of-sale layout file*" field of the Documents setup screen,

prints the "*Projects*" on the selected document layout file. If a document layout file supporting the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Projects*" for for project quotes. This does not reflect Project quote, except for the document number prefixed by "*D*" (e.g., "*D000001*").



- NEW Layout file Added: Project - TRN_3556 - Project - Quote - This translatable layout file is specifically designed for project quotes documents, ensuring that all necessary details are accurately represented and the document is correctly labelled as an "*Project - Quote*". NOTE: The document name "*Project - Quote"* is singular since it only includes a specific "*Project - Quote*".



- On the Document groups tab of the Stock item and on the Reports → Stock In / Out reports, the Document type is blank (empty). On Search (central search) the Details is reflected as Invoice Details.



Comparison / Notes of Stock adjustments and plugins

Document type *Document*	*Reports -> Stock In / Out Docu*	*Document number prefix*	*Search central - Document type*	*Posted / Unposted*	*Your reference*	*Item description*	*Layout file heading*

	group s tab	ment type						
Input → Adjust stock Stock adjust ments	Stock-	Stock in	ST - Stock adjust ments: for examp le, "ST000 01".	Stock out Details	Posted		Auto correcti on (or remark entere d in Chang e remark screen for examp le "Surpl us" or "Short age":	POS Layout file
		Stock in	ST - Stock out	Stock out Details			Auto correcti on	
Stock grid - Quanti ty colum n		Stock in	ST - Stock out	Stock out Details	Posted			

Document Scenarios and Prefixes in Plugins

Various plugins extend the functionality and support for different document types.

QuickOrder Plugin

Order corrections

When Stock quantities are adjusted on the StockCount tab (Voorraadtelling tab).

- Document prefix: "*ST*" (e.g., "*ST00001*"), with a 7-digit format including 4 zeros).
- Description: The description is automatically generated as "*Actief-Q-cor*".
- Print Order Corrections:
  - Layout file setting: Selecting a different layout file on the "*Point-of-sale layout file*" field of the Documents setup screen, does not work. It still prints the document using the POS - STARTSP100 "*POS Tax Invoice*" on the selected document layout file.
  - Print options: Can be printed from the following options:
    - Stock item form - Document groups tab: Double-click the document.
    - Stock item form - Transactions tab: Double-click the document.
    - Search (Default ribbon): On the central search, find the reference ("*Actief-Q-cor*"), document number, or prefix ("*ST*"), and double-click on the document. The document type will be indicated as "Stock out Details".
  - Print using different layout file: To print translatable documents for these stock adjustments or corrections, you can go to the Report designer and select the adjustment document from the Select test document id button and select the layout file such as "*Adjustment*" or any other layout file which includes the stock code such as Document layout (15codes) - (TRN_906277) or NO-TAX Document layout (15codes) - (TRN_906591). NOTE: The following layout files does not include the Stock code:
    - Layout file - (TRN_1910)
    - Document layout - (TRN_3174)
    - NO-TAX Layout file - (TRN_906589)
    - NO-TAX Document layout - (TRN_906590)
- Document type: Search (central search) the Details is reflected correctly as Stock out Details and on the Document groups tab and Transactions tab of the Stock item it is reflected as Stock-.

  Stock item - Document groups tab - Document type = Stock-



Stock item - Transactions tab - Document type = Stock-



QuickOrder - Orders

QuickOrder Plugin generates Orders on the Generate (Aanmaken) tab.

- Document prefix: "*ST*" (e.g., "O*R000001*"), with a 8-digit format including 5 zeros).
- Orders will be generated for the default supplier as set in the "*Preferred supplier1*" field of the Stock item form.
- Orders may be edited and confirmed (converted to a purchase document).
- Print Orders: Orders generated by the QuickOrder Plugin will by default print to the layout file selected on the Orders tab within Setup → Documents setup or the layout file selected "*Layout file 3*" field of the Delivery address tab of the Creditor account.

Dynareg Plugins

Stock in Document type

- Dynareg - Stock in document type - One additional document type Stock in. Documents processed for the Stock in document type.



- Document prefix: "*SI*" (e.g., "*SI00001*"), with a 7-digit format including 4 zeros).
- Document type: Stock in - Can be selected on the Document grid in addition to the six standard document types (i.e. Quotes, Invoices, Credit notes, Orders, Purchases and Supplier returns),
- New document: Select creditor account.
- Input menu: Input → Stock out launches the document entry as a separate window and lists all documents processed in the Documents grid for the Stock in document type. The Input → Stock out menu option should read Input → Stock in.
- Print documents: Selecting a different layout file on the "*Point-of-sale layout file*" field of the Documents setup screen, does not work. It still prints the document name as "*Statement*" on the selected document. If a document layout file supporting the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Statement*" for the Stock in document type. To print the Stock in documents, you can select a different layout file from the Documents grid or from the Documents tab of the Creditor account.

> TYPES table - Statement - RecordID = 17 - WTYPEPARENT = 1



- On Search (central search) the Details is reflected correctly as "Stock in Details" and on the Stock item tabs of the Creditor account, the document type is Stock-. On the Document groups tab of the Stock item it is reflected as Stock+.

Creditors - Stock item tab - Document type = Stock-



Stock item - Document groups tab - Document type = Stock+



Stock in and Stock out Document types

- Dynareg - Stock in and Stock out document type - Two additional document types Stock out and Stock in Documents processed for two document types:



Stock in document type

- Documents processed for the Stock in document type.
    - Document prefix: "*SI*" (e.g., "*SI00001*"), with a 7-digit format including 4 zeros).
    - Print documents: Selecting a different layout file on the "*Point-of-sale layout file*" field of the Documents setup screen, does not work. It still prints the document name as "*Statement*" on the selected document. If a document layout file supporting the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Statement*" for the Stock in document type. To print the Stock in documents, you can select a different layout file from the Documents grid or from the Documents tab of the Creditor account.

TYPES table - Statement - RecordID = 17 - WTYPEPARENT = 1



Stock out document type

Documents processed for the Stock out document type.

- Document prefix: "*ST*" (e.g., "*ST00001*"), with a 7-digit format including 4 zeros).
- Print documents: Selecting a different layout file on the "*Point-of-sale layout file*" field of the Documents setup screen, does not work. It still prints the document name as "*POS Tax Invoice*" on the selected document. If a document layout file supporting the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Statement*" for the Stock in document type. To print the Stock out documents, you can select a different layout file from the Documents grid or from the Documents tab of the Creditor account. .
- Print using different layout file: To print translatable documents for the Stock out document type, you can go to the Report designer and select the adjustment document from the Select test document id button and select the layout file such as "*Stock out*" or any other layout file which includes the stock code such as Document layout (15codes) - (TRN_906277) or NO-TAX Document layout (15codes) - (TRN_906591). NOTE: The following layout files does not include the Stock code:
  - Layout file - (TRN_1910)

§ Document layout - (TRN_3174)

§ NO-TAX Layout file - (TRN_906589)

§ NO-TAX Document layout - (TRN_906590)

Stock In / Out Document type

- Dynareg - Extra stock of correction document (Stock in / Stock out document type) - One additional Stock In / Out document type. Documents processed for the Stock In / Out document type.



- Document prefix: "*ST*" (e.g., "*ST00001*"), with a 7-digit format including 4 zeros).
- Document type: Stock In / Out - Can be selected on the Document grid in addition to the six standard document types (i.e. Quotes, Invoices, Credit notes, Orders, Purchases and Supplier returns),
- New document: Select debtor account.
- Input menu: Input → Stock in launches the document entry as a separate window. No documents processed for the Stock In / Out document type from the Documents grid, is listed in the document entry as a separate window launched from the Input → Stock in menu and lists all documents processed in the Documents grid for the Stock in document type. New document select debtor account and it creates an Invoice (e.g. IN000025) for the Disassemble document type.
- Same document (Invoice) different Document type - Disassemble on Document groups tab of Stock items and Assemble on Stock item tab of Debtors.

Stock item - Document groups tab - Document type = Disassemble



Date	Items	Document no.	Description	Price	Discount	Exclusive	Inclusive	Unit price	Units	Description	Number	Name	Document type	Posted
2022/04/16	-5	ST00004	Auto correction	0,00				0,00				Empty	Stock-	1
2022/05/12	1	IN000025	Drill press	1000,00	0	1000,00	1150,00	1000,00	1	Each	1CASHC	CASH CUSTOMERS	Disassemble	0
2022/05/12	1	IN000025	Drill press	1000,00	0	1000,00	1150,00	1000,00	1	Each	1CASHC	CASH CUSTOMERS	Disassemble	0
2022/05/12	1	IN000025	Drill press	1000,00	0	1000,00	1150,00	1000,00	1	Each	1CASHC	CASH CUSTOMERS	Disassemble	0
2022/05/12	1	ST00006	Drill press	1100,00	0	1100,00	1265,00	1100,00	1	Each	1DOPEN	Opening Balances - Debtor	Stock-	1
2022/05/20	1	IN000026	Drill press	1100,00	0	1100,00	1265,00	1100,00	1	Each	1DOPEN	Opening Balances - Debtor	Disassemble	0
2023/07/06	1	QU000006	Drill press	1000,00	0	1000,00	1150,00	1000,00	1	Each	1ROGSM	Mr. Roger Smith	Quotes	0
2024/04/23	1	PU000008	Drill press	500,00	0	500,00	575,00	500,00	1	Each	2AONES	A-ONE Suppliers	Purchases	0
2024/06/08	1	IN000027	Drill press	1000,00	0	1000,00	1150,00	1000,00	1	Each	1CASHC	CASH CUSTOMERS	Disassemble	0
	38			47,00		49 700,00	56 855,00							

Debtors - Stock item tab - Document type = Assemble



- The Input → Stock in menu option should read Input → Stock In / Out.

Plugins using the Point-of-sale layout file setting in Documents setup

Plugin name	*Document type*	*Reports -> Stock In / Out Document type*	*Search central - Document type*	*Document number prefix*	*Posted / Unposted*	*Your reference*	*Item description*	*Layout file heading*
Plugin - StockCheck -	*Credit note*	*Credit note*	*Credit note Details*	*CR - Prefix - Documents setup*	*Unposted*	*Correction*	*Stock count correction*	*Credit note*
Plugin - QuickOrder - Generate	*Order*	*Order*	*Order Details*		*Unposted*	*Creditor account code*		*Order*
Plugin - QuickOrder - Stock count tab	*Stock-*	*Stock in*	*Stock out Details*	*ST - Stock out*	*Posted*	*Actief-Q-cor*	*Actief-Q-cor*	*POS Invoice*
Dynareg - Stock in document type -	*Stock-*			*SI - Stock in*	*Unposted*			*Statement*



Dynareg - Stock in and Stock out document type -	*Stock in / Stock+ Stock out / Stock-*	*Stock out Stock in*	*Stock in Details Stock out Details*	*SI - Stock in ST - Stock out*		*Statement Adjustment*



Dynareg - Extra stock of correction document (Stock in / Stock out document type) -	*Stock in*	*Stock in*	*Stock out Details*	*ST - Stock out*		*Adjustment*



Input → Stock in menu - launches a stand-alone screen. New	*Disassemble*	*BOM (Production)*	*Production Details*	*IN - Invoice*	*Cannot post or delete*	*Remittance*

	docum *ents*

Layout file document names issues

The plugin prints the layout file selected in the "*Layout file point-of-sale*" field within Setup → Documents setup. This setting does not work for the "*Stock in*" or "*Stock out*" document types By default, the "*Stock in*" or "*Stock out*" will print the till slip layout file "*POS Tax invoice*".

Selecting document layout files for Stock adjustments and Plugins

The Print button on the Documents grid prints specific layout files for Invoices, Credit notes, Purchases, Supplier returns, Quotes, and Orders as configured in the Documents setup.
You may select different document layout files on the Documents grid, or on the Documents tab of Debtor / Creditor accounts.

Document layout files using document name from the "TYPES" table

Certain document layout files support dynamic document names from the "*TYPES.SDESCRIPTION*" field in the "*TYPES*" table. These files adapt the document name based on the document type being printed.

If the following document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, is selected:

- Layout file - (TRN_1910) NS
- Document layout - (TRN_3174) NS
- Document layout (15codes) - (TRN_906277)
- NO-TAX Layout file - (TRN_906589) NS
- NO-TAX Document layout - (TRN_906590) NS
- NO-TAX Document layout (15codes) - (TRN_906591)

It will print "*Adjustments*" for the "*Adjustments*" and "*Stock out*" document type and "*Statement*" for the "*Stock in*" document type. In some cases, the document name may be printed as "*Remittance*".

Document layout files using designated document names

Other document layout files use static or translatable expressions for the six standard document types (Invoices, Credit notes, Purchases, Supplier returns, Quotes, and Orders). These expressions do not change dynamically based on the "*TYPES*" table but are predefined for consistency and translation purposes.

Added Dedicated Document Layout Files for Adjustments, BOM (Production), Stock in, and Stock out

To enhance the accuracy and clarity of printed documents, it is suggested that dedicated, translatable document layout files specifically for "*Adjustments*", "*BOM (Production)*" and the "*Stock in*" and "*Stock out*" document types. This addition ensures that each document type is printed with the correct format and naming conventions, reducing the potential for confusion and errors.

Newly Added Document Layout Files

Added : Document layout files for Non-Standard document types

Adjustment - Document Layout File

Certain document layout files support dynamic document names from the "*TYPES.SDESCRIPTION*" field in the "*TYPES*" table. These files adapt the document name based on the document type being printed.

Generated when stock quantities are adjusted (via Input → Adjust stock menu or by manually changing stock quantities on the stock item grid).
These adjustments replaces the stock item description in the document lines in some layout files.
Layout files, such as "POS - START-SP100" (TRN_906183), Layout file (TRN_1910), Document layout (TRN_3174), NO-TAX Layout file (TRN_906589) and NO-TAX Document layout (TRN_906590) don't contain the stock code. When the stock description in some layout files is replaced with entered remarks (e.g., "*Surplus*", "*Shortage*", etc.) or "*Auto correction*" (using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid), those remarks are displayed on the printed layout file.
For an audit trial to which stock items is included in the adjustments, select the following document layout files:

- Document layout (15codes) - (TRN_906277)
- NO-TAX Document layout (15codes) - (TRN_906591)

Generated when stock quantities are adjusted (via Input → Adjust stock menu or by manually changing stock quantities on the stock item grid).
Document prefix: "*ST*" (e.g., "*ST00001*"), with a 7-digit format including 4 zeros.

Remarks entered in the "*Change remark*" screen (e.g., "*Surplus*" or "*Shortage*") or "*Auto correction*" are reflected in these documents.

Adjustment - TRN_1767

This layout file is specifically designed for adjustment documents, ensuring that all necessary details are accurately represented and the document is correctly labelled as an "Adjustment."

The date reflects the correct transaction date.

Stock code is printed on the layout file. This provides an audit trial linking the "*Adjustment*" document layout file to the adjusted stock item.

Remarks entered in the "*Change remark*" screen (e.g., "*Surplus*" or "*Shortage*") or "*Auto correction*" are reflected in these document layout files.

Example : Adjustment "*Surplus*"

TYPES table - Adjustment - RecordID = 16 - WTYPEPARENT = 1



BOM (Production) - Document Layout File

Added : BOM (Production) Stock Item Type - TRN_3266

Generated for BOM stock items during Assembly or Disassembly.

Document prefix: "SA" (e.g., "*SA00001*"), with a similar 7-digit format.

Selecting the document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Delivery note*" for "*Assemble*" option and "*Remittance*" for "*Disassemble*" option.

To solve this, an additional layout file is added to print the BOM (Production) stock type.

Example : Assemble



Delivery note accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```


BOM (Production)
BOM (Production)
Page no.: 1 / 1
Empty account
Delivery address
Handyman Hardware Store
27 Olifants Road
Emmarentia
Johannesburg
2195
Company reg. no.: 336012345
Tax reg. no.: 446010111
Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/
Document no.: SA00001
Date: 2024/05/21
Account no.: T
Code / Description
Units
Qty
Price
Disc%
Exclusive
Tax%
Tax
Inclusive
BOMPRODUCTION
Assemble BOM (Production)
5
1 500,00
7 500,00
Total
Due date:
Your reference: Assemble BOM (Production)
Tax reference:
Message:
Salesperson: No group
BOM (Production) accepted:
Name:
Date:
Signature:
Printed/Reprinted
2024/09/04 04:47:14

Example : Disassemble



Remittance accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Example : Selecting existing layout files - Types description

Selecting the document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Delivery note*" for "*Assemble*" option and "*Remittance*" for "*Disassemble*" option.

Example : Selecting existing layout files - Types description - Assemble

TYPES table - Delivery note - RecordID = 19 - WTYPEPARENT = 1



Example : Selecting existing layout files - Types description - Disassemble

TYPES table - Remittance - RecordID = 18 - WTYPEPARENT = 1



The document layout file using the "*Layout file point-of-sale*" field within Setup → Documents setup prints the "*Project - Quote*" or "*Projects*" document types By default, the "*Project - Quotes*" or "*Projects*" will print the till slip layout file "*POS Tax invoice*".

Project Quote - Document Layout File

Generated when processing project quotes on the Project Quotes tab for specific projects in addition to the normal quotes standard document type.

Document prefix: "*D*" (e.g., "*D000001*"), with a 7-digit format including 5 zeros.

Project - TRN_3556 - Project - Quote

This layout file is specifically designed for project quotes documents, ensuring that all necessary details are accurately represented and the document is correctly labelled as an "*Project - Quote*".

The date reflects the correct transaction date.

Stock code is printed on the layout file. This provides an audit trial linking the "*Project - Quote*" document layout file to the stock item.

Example : Project - Quote



Projects accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print Project - Quote accepted:

```
CUSTOM('GETTEXTLANG',3556,'Project',CLIENTORDEFLANG.SLANGUAGE,0,0)+'  -
'+CUSTOM('GETTEXTLANG',2169,'Quote',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Example : Selecting existing layout files - Types description - Project - Quote

Selecting the document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Projects*" for the "*Project - Quote*" option.

TYPES table - Projects - RecordID = 1000 - WTYPEPARENT = 2 (reporting group name)



Example : Layout file point-of-sale setting - Not printing the selected layout file

Prints the "*Project - Quote*" document layout file using the "*Layout file point-of-sale*" field within Setup → Documents setup. This setting does not work for the "*Project - Quote*" or "*Projects*" document types By default, the "*Project - Quotes*" or "*Projects*" will print the till slip layout file "*POS Tax invoice*".

This is replicated in the following print options:

- Search (central search) on the Default ribbon.
- Debtors - Documents tab (NOTE: You may select a layout file from the Documents tab)
- Stock item - Document groups tab



The possible reason for this, could be that the Document type column is empty in the Document groups tab of the Stock item and related options:



Added : Plugins - Document layout files for Non-Standard document types

Stock in - Document Layout File

Generated for Stock in document type

Selecting the document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Statement*" for "*Stock in*" option.

Document prefix: "*SI*" (e.g., "*SI00001*"), with a similar 7-digit format.

Stock in - TRN_906178

This layout file is dedicated to "*Stock in*" documents, printing them with the appropriate document name and format, thus providing clear and precise documentation of stock intake.



Statement accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print Stock in accepted:

```
CUSTOM('GETTEXTLANG',906178,'Stock in',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Stock out - Document Layout File

Generated for Stock out document type

Selecting the document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Adjustment*" for "*Stock out*" option.

Document prefix: "*ST*" (e.g., "*ST00001*"), with a similar 7-digit format.

Stock out - TRN_906179

This layout file is tailored for "*Stock out*" documents, ensuring that they are printed with the correct document name and layout, accurately reflecting stock outflow transactions.



Adjustment accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print Stock out accepted:

```
CUSTOM('GETTEXTLANG',906179,'Stock in',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Important Considerations for Point-of-Sale Layout Files in osFinancials

While configuring the "*Point-of-sale layout file*" in osFinancials5/TurboCASH5 it is crucial to understand its limitations and appropriate use cases. Specifically, POS layout files should not be used for certain documents due to the following reasons:



The following document types will print using the default setting in the "*Point-of-sale layout file*" field on the "*Documents setup*" screen is "*POS -STARTSP100*," a till slip document layout file.

Other features

Changing the Layout File for Point-of-Sale (POS) Documents

The default setting in the "*Point-of-sale layout file*" field on the "*Documents setup*" screen is "*POS -STARTSP100*," a till slip document layout file. To select a different layout file from the default document layout files included in the osFinancials installation or your own if you have created one, the document layout will be printed in that format.

Print layout files for Stock adjustments, BOM (Production, Project - Quotes and Stock in and Stock out document types

The configurations related to printing layout files for different document types, particularly focusing on stock adjustments, stock in, and stock out scenarios. Currently in the Setup → Documents setup, you can only set or select document layout files only for the six standard document types (i.e. Quotes, Invoices, Credit notes, Orders, Purchases and Supplier returns),
Document layout files to print "*Adjustments*" or to print the new "*Stock in*" and / or "*Stock out*" document types, if plugins is activated, cannot be set on the Setup → Documents setup.

- Default layout file setting for Adjustments
  - Currently adjustments made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid , prints the layout file selected in the "*Layout file point-of-sale*" field within Setup → Documents setup.
    This means that users using the standard Point-of-sale system on Input → POS Invoice (Ctrl+F6) will print the till slip layout file "*POS - START-SP100*" (TRN_906183) with document name "*POS Tax invoice*".
    In the central search (Search on the Default ribbon), it will also print this "*POS - START-SP100*" (TRN_906183) with document name "*POS Tax invoice*".
    NOTE : Using the Layout file point-of-sale document layout files to print stock adjustments will print the system date and not the document date on which stock corrections or stock adjustments were generated. WARNING: Point-of-sale document layouts might not be ideal for printing stock corrections or stock adjustments "Assemble" and "Disassemble" documents for BOM (Production) item types due to:
    - Date: POS invoices show your system's date, not the actual processing date.
    - Document Name: Might say "POS Tax Invoice" instead of something relevant.
    - Item Description: Some layout files, such as "*POS - START-SP100*" (TRN_906183), don't contain the stock code. When the stock description in some layout files is replaced with entered remarks (e.g., Surplus, Shortage) (using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid), those remarks are displayed on the printed layout file. In the case of some plugins, such as the StockCheck plugin, it will replace the stock item description with "*Actief-Q-cor*" will be displayed on the printed layout file. This means the printed layout file doesn't indicate which stock item was corrected.
    - Footer: Contains data like cashup amounts, not relevant for stock adjustments, BOM operations, project quotes some actions on some plugins.

    Recommendation: Select a different document layout file for BOM (Production) transactions (Setup →

Documents setup).

- Stock adjustments (using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid), the "*POS Tax invoice*" will also be printed for the new "*Stock in*" and / or "*Stock out*" document types, if plugins is activated.
- If the following document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, is selected, it will print "*Adjustments*" for the "*Adjustments*" and "*Stock out*" document type and "*Statement*" for the "*Stock in*" document type.
  - Layout file - (TRN_1910)
  - Document layout - (TRN_3174)
  - Document layout (15codes) - (TRN_906277)
  - NO-TAX Layout file - (TRN_906589)
  - NO-TAX Document layout - (TRN_906590)
  - NO-TAX Document layout (15codes) - (TRN_906591)
  - Other available layout files use static or translatable expressions for document layout files of the six standard document types.
- Added layout files for Adjustments / "*Stock in*" and "*Stock out*" document types - For this reason, the following dedicated translatable document layout files is added for Adjustments and the "*Stock in*" and "*Stock out*" document types:
  - Adjustment (TRN_1767)
  - BOM (Production) (TRN_3266)
  - Project - Quotes (TRN_3556)
  - Stock in (TRN_906178)
  - Stock out (TRN_906179)

- Setup → Documents setup - Adjustments - Within Setup → Documents setup, in addition to the six standard document types (invoices, credit notes, quotes, purchases, supplier returns and orders) and extra document tab like Adjustments could be added. On this "*Adjustments*" tab, initially, you would select the "*Adjustment*" layout file for Stock adjustments (using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid). May need to add options to select a layout file for Projects layout file and BOM (Production (Assemble and Disassemble).
  - If a user activates a plugin that supports "*Stock in*" an extra field would be added where a user can select the "*Stock in*" layout file for the "*Stock in*" document type.
  - Similarly, if a user activates a plugin that supports "*Stock in*" and the "*Stock out*" document types, the "*Stock out*" layout file could be selected for both the "*Stock in*" document layout file and the "*Stock out*" layout file.

Layout file document names issues

The plugin prints the layout file selected in the "*Layout file point-of-sale*" field within Setup → Documents setup. This setting does not work for the "*Stock in*" or "*Stock out*" document types By default, the "*Stock in*" or "*Stock out*" will print the till slip layout file "*POS Tax invoice*".

In the central search (Search on the Default ribbon), it will print this "*POS - START-SP100*" (TRN_906183). If any other layout file, is selected. the name of the report is not translated, but will display for example TRN_906183 in Setup → Point of-Sale - Printers tab



Changing the layout file in Setup → Documents setup will update the layout file in Setup → Point of-Sale - Printers tab but it still prints Stock in and Stock out using the POS - START-SP100 (TRN_906183)layout file.



NOTE If "*Layout file*" is selected as the option within Documents setup for other document types, the "*Default*" option on Document grid does not work. You need to select the "*Layout file*" or other layout file. You have the option to choose a different layout file for "*Stock in*" or "*Stock out*" document types.

Layout file - The default "*Layout file*" for all document types, will print the headings in the Types tab on Tools → Customise language.

Stock out - Adjustment



Stock in - Statement



Layout files added for Stock in / Stock out document types

To fix this, added two translatable Document layout files from the Stock in / Stock out document types:

- Stock in (TRN_906178) This layout file may be selected on the Documents grid or Creditors - Documents tab



- Stock out (TRN_906179) This layout file may be selected on the Documents grid or Debtors - Documents tab



BOM (Production) Stock Item Type

Added : TRN_3266 BOM (Production) Stock Item Type

Generated for BOM stock items during Assembly or Disassembly.

Document prefix: "SA" (e.g., "*SA00001*"), with a similar 7-digit format.

Selecting the document layout files, which supports the "*TYPES.SDESCRIPTION*" document name from the "*TYPES*" table, will print the document name as "*Delivery note*" for "*Assemble*" option and "*Remittance*" for "*Disassemble*" option.

To solve this, an additional layout file is added to print the BOM (Production) stock type.

Example : Assemble



Delivery note accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Example : Disassemble



Remittance accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Print a Posted document

You may print selected posted document generated by the "*Assemble*" and "*Disassemble*" of BOM (Production) items from the following options:

- BOM (Production) - Document groups tab : (Double-click to print).
- Search (central search) : Locate these posted document generated by the "*Assemble*" and "*Disassemble*" of BOM (Production) items. (Double-click to print).



The "*POS Tax Invoice*" will print the correct document number, but will print the system date and time stamp of your operating system and not the actual transaction date.

The default document layout file which will be used to print documents generated by the "Assemble" and "Disassemble" of BO is the "Layout file point-of-sale" selected in Setup → Documents setup.

WARNING: Point-of-sale document layouts might not be ideal for printing "Assemble" and "Disassemble" documents for BOM types due to:

- *Date: POS invoices show your system's date, not the actual processing date.*
- *Document Name: Might say "POS Tax Invoice" instead of something relevant.*
- *Footer: Contains data like cashup amounts, not relevant for BOM operations.*
- *Additional Note: The standard POS (initiated from Input → POS Invoice (CTRL+F6)) uses the "Layout file point-of-sale" Documents setup. If different document layout files is selected, this may change the POS invoicing functionality.*

Recommendation: Select a different document layout file for BOM (Production) transactions (Setup → Documents setup).



NOTE: Selecting the document layout files, which supports the "TYPES.SDESCRIPTION" document name from the "TYPES" table, document name as "Delivery note" for "Assemble" option and "Remittance" for "Disassemble" option. Selecting the following do will replicate the document names:

- *Layout file - (TRN_1910)*
- *Document layout - (TRN_3174)*
- *Document layout (15codes) - (TRN_906277)*
- *NO-TAX Layout file - (TRN_906589)*
- *NO-TAX Document layout - (TRN_906590)*
- *NO-TAX Document layout (15codes) - (TRN_906591)*

Recommendation: You may select the BOM (Production) Layout file (TRN_3266) for the Stock item type to print layout file "Assembly" or "Disassembly".

Document prefix: "SA" (e.g., "SA00001"), with a similar 7-digit format.

Example : Assemble



Delivery note accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```


BOM (Production)

BOM (Production) Page no.: 1 / 1

Empty account

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195
Company reg. no.: 336012345
Tax reg. no.: 446010111
Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Delivery address

Document no.: SA00001 **Date: 2024/05/21** **Account no.: T**

Code / Description	Units	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inc
BOMPRODUCTION Assemble BOM (Production)		5	1 500,00		7 500,00			

Total

Due date:
Your reference: Assemble BOM (Production)
Tax reference:
Message:

Salesperson: No group

BOM (Production) accepted:

Name: _____

Date: _____

Signature: _____

Printed/Reprinted *2024/09/04 04:47:14*

Example : Disassemble



Remittance accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Created with the Standard Edition of HelpNDoc: Upgrade your help files and your workflow with HelpNDoc's WinHelp HLP to CHM conversion

Known issues - Plugin - Activa Setup - Select Accounts

Known issues - Activa Plugin

Activa Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation Online Help documentation : Activa plugin

Translations : Outstanding

Activa plugin - Open old existing books

Firebird error

```
Dynamic SQL Error
SQL error code = -204
Table unknown
ACTIVAREG
At line 1, column 25
```

Activa Plugin Setup

On the Plugins → Financial tools → Activa (Activate Plugins) you can set or add accounts correctly.

On the Default ribbon, Add manual button, the Search screen is static.

Cannot set accounts - Blank Search screen to add accounts

osFinancials5.1.0.4 Also replicated in osFinancials5 (453)

Before in osFinancails4 in could add the accounts - See = Activa Manual -



behind with HelpNDoc

Known issues - Bank import plugin

Balance batch option

Balancing batches

If a batch is not balanced, the Tax amounts in not included in the F8: Batch list List batch - Unposted batch report. Once batches are balanced, the F8:List on the List batch - Unposted batch report, will include the Tax amounts.

As with normal batches, the F5:Balance icon is accessible on the Batch entry (normal batches for Bank accounts).

In the Bank import there is no F5:Balance icon but it is accessible in the F9:Process and select Balance batch option.

In the Bank import plugin, it only populates the Contra account when a bank account is balanced.



In Firebird databases could not find any issues with dates causing issues with the unbalanced and balanced batches.

Balancing and Posting a Bank Import plugin batch and the Posting the Batch does not duplicate transactions when Posting a Balanced Bank import batch.

Maybe the F5:Balance icon could be moved to the top with the other icons in Bank import plugin batches.

List the transactions in the batch (Exclude Tax amounts)

Once the transactions is imported and allocated to accounts, including Tax (VAT/GST/Sales tax) the Tax amounts is not included in the F8:List on the List batch - Unposted batch report.



List batch - Unposted batch

Batch name ABC-Payments
Alias (batch name) ABC-Bank-St.5

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/01	24042101	CHAIRS 1234567890202403303	G600-010 B810-000	T860-030	0,00	300,00	0,00
2024/03/01	24042101	DESK 1234567890202403013	G600-010 B810-000	T860-030	0,00	500,00	0,00
2024/03/01	24042101	Capital Jack Daniels 12345678902024	G505-000 B810-000	T	0,00	0,00	5 000,00
					Total	800,00	5 000,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/16	24042101	PAYMENT AB GREEN IN000003 123456789	D1AB-GRE B810-000	T	0,00	0,00	2 000,00
2024/03/16	24042101	PAYMENT MAC Shop Decor Specialists	D1MA-CDS B810-000	T	0,00	0,00	1 000,00
					Total	0,00	3 000,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/30	24042101	PETTYCASH REPLENISHMENT 12345678902	B820-000 B810-000	T	0,00	100,00	0,00
2024/03/30	24042101	WALTONS PENS AND PAPER STATIONERY 1	G230-000 B810-000	T860-020	0,00	200,00	0,00
2024/03/30	24042101	ABC Service Station PETROL 12345678	G210-010 B810-000	T	0,00	150,00	0,00
2024/03/30	24042101	PAYMENT ABC-OFFICE SUPPLIES 1234567	C2AB-COS B810-000	T	0,00	750,00	0,00
2024/03/30	24042101	Rent ERF 2192 1234567890202403306	G220-000 B810-000	T860-020	0,00	500,00	0,00
					Total	1 700,00	0,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/31	24042101	Bank Charges ADMIN FEE 123456789020	G200-000 B810-000	T	0,00	45,00	0,00
					Total	45,00	0,00

To include the Tax transactions, you need to go to F9:Process and select Balance batch option.

Once this is done, you need to access the unposted batch and Delete the balancing entries.

This will include the Tax (VAT/GST/Sales tax) in the F8:List on the List batch - Unposted batch report.

List the transactions in the batch (Include Tax amounts)

Click on the F8: List icon to print a list of the imported and allocated transactions in the unposted bank

account batch.



F:\osfinancials5-MERGE-1\plug_ins\reports\GENERAL\documents\batch.rep

List batch - Unposted batch

Batch name ABC-Payments
Alias (batch name) ABC-Bank-St.5

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/01	24042101	CHAIRS 1234567890202403303	G600-010 B810-000	T860-030	45,00	300,00	
2024/03/01	24042101	DESK 123456789020240301 3	G600-010 B810-000	T860-030	75,00	500,00	
2024/03/01	24042101	Capital Jack Daniels 12345678902024	G505-000 B810-000		0,00		5 000,00
					Total	800,00	5 000,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/16	24042101	PAYMENT AB GREEN IN000003 123456789	D1AB-GRE B810-000		0,00		2 000,00
2024/03/16	24042101	PAYMENT MAC Shop Decor Specialists	D1MA-CDS B810-000		0,00		1 000,00
					Total	0,00	3 000,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/30	24042101	PETTYCASH REPLENISHMENT 12345678902	B820-000 B810-000		0,00	100,00	
2024/03/30	24042101	WALTONS PENS AND PAPER STATIONERY 1	G230-000 B810-000	T860-020	30,00	200,00	
2024/03/30	24042101	ABC Service Station PETROL 12345678	G210-010 B810-000		0,00	150,00	
2024/03/30	24042101	PAYMENT ABC-OFFICE SUPPLIES 1234567	C2AB-COS B810-000		0,00	750,00	
2024/03/30	24042101	Rent ERF 2192 1234567890202403306	G220-000 B810-000	T860-020	75,00	500,00	
					Total	1 700,00	0,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/31	24042101	Bank Charges ADMIN FEE 123456789020	G200-000 B810-000		0,00	45,00	
					Total	45,00	0,00

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Known issues - Plugin - Charter

Known issues - Charter plugin

Charter Plugin - Manual - Shop - Licence : Once-off

Documentation : Help documentation Online Help documentation : Charter plugin

Translations : Outstanding

Access violation error - Creditors - Charter tab - Creditor detail

Build button produces error

> Access violation at address 60DB848E in module 'Charter.of5'. Read of address 00000000

Charter Plugin - Debtors for Purchase document types

Within the Documents grid - You may right-click to launch the "*Charter*" screen from the on the Plugin action → Charter context menu to launch the "*Doc value*" or "*Debtors*" chart.

In the document entry screen for posted and unposted sales documents such as invoices, credit notes and quotes it seems correct.

Debtors - In the document entry screen for posted and unposted purchase documents such as purchases, supplier returns and orders, an icon will be available to launch the "*Charter*" screen. Should launch the Creditors option.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Output with HelpNDoc's Advanced Project Analyzer

Known issues - Plugin - Remittance

Known issues - Remittance plugin

Remittance - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Translations : Outstanding

Remittance - Edit - Messages

Statement message 1 is populated as Statement message 1 on Debtors - Delivery address tab



First message on Debtors - Delivery address tab is not included



Remittance - Document layout

remittance1/remittance2/remittance3/remittance4 report names not translatable via language files.

Location : "... \plug_ins\reports\remittance\doctype\layouts\

Show print - Print preview error if "Show all" box is not ticked and data list is empty - Open reportman screen produces error

> DOCUMENTKOP:Could not convert variant of type (UnicodeString) into type (Integer)

Show print - Print preview error if "Show all" box is list and an debtor invoice is selected it prints the Open item selection layout



Does not support TRN_3400 or LANG_3400 for example.

Remittance plugin - Firebird Error - default.rep in English and Nederland

English

Location : ...\plug_ins\reports\remittance\en\layouts\default.rep

Nederlands

Location : ...\plug_ins\reports\remittance\nl\layouts\default.rep

Could not convert variant of type (UnicodeString) into type (Double)

and within Reportman

```
Could not convert variant of type (UnicodeString) into type (Double)
TODATE=11-10-2006
```

The error message "*Could not convert variant of type (UnicodeString) into type (Double*)" in Firebird databases suggests that there is an issue with data conversion, particularly involving a Unicode string and a Double data type.

In your provided information, you also mentioned "*TODATE=11-10-2006*." It seems like there might be an attempt to convert a string ("*11-10-2006*") to a Double data type using the TODATE function in Firebird.

Here are a few steps you can take to troubleshoot and resolve the issue:

1. Check the Data Type Compatibility: Ensure that the data types used in your expressions are compatible. If you are using the TODATE function, make sure that the input is a valid date format.

   Example: sql

   ```
   SELECT TODATE('11-10-2006', 'DD-MM-YYYY') FROM YourTable;
   ```

2. Verify Data Formats: Double-check the format of the date string. In the example above, the format is 'DD-MM-YYYY'. If your date string follows a different format, adjust the format accordingly.

3. Handle NULL Values: If your data might contain NULL values, consider adding conditions to handle them appropriately. For instance, use the COALESCE function to replace NULL values with a default or handle them in another way.

4. Explicit Type Conversion: If you're dealing with mixed data types, explicitly convert the data types using appropriate functions. For example, you can use the CAST or CONVERT function to explicitly convert a string to a Double if needed.

   Example: sql

   ```
   SELECT CAST('11-10-2006' AS DOUBLE PRECISION) FROM YourTable;
   ```

5. Review the SQL Statement: Check the entire SQL statement or query for any other potential issues. Look for areas where data types might conflict.

Without seeing the full query or knowing more about the database structure, these are general suggestions. If the issue persists, providing more details about the relevant part of your SQL query and the database schema would be helpful for further assistance.

Created with the Standard Edition of HelpNDoc: Simplify Your Help Documentation Process with a Help Authoring Tool

Known issues - Plugin - Subscriptions

Known issues - Subscriptions plugin

Subscriptions - Manual - Shop - Licence : Annual licence -

Documentation : Help documentation Online Help documentation : Subscriptions plugin

Translations : Outstanding

Subscriptions - Splash screen on top

Replicated in osFinancials5.1.0.189 Update install.

If Subscriptions activated and when starting osFinancials5 and opening a Set of Books, the osFinancials splash screen stays on top.

There is a Building process behind the Subscriptions that does not finish.



To resolve this, you need to close the Subscriptions screen to complete the Building process.

You may need to Manually launch the Subscriptions from the Default ribbon.

This is only replicated when opening a Set of Books in a new osFinancials session. Reopening the Set of Books in a current session, does not replicate this error.

Subscriptions - Search - Column Country / Address 3



The Country column heading "*Land*" should be Address 3 since the data entered in Address 3 field is displayed in thee Country column.

Address 3 (2420)

Subscriptions Next run / Transaction dates 1900 year

Subscriptions to process



Debtors - Subscriptions tab



Quote



Invoice



Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Known issues - Drill down plugin - Stock item Invoice AV Error

---

Known issues - Drill down plugin

DrillDown plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation - Online Help documentation : Drill down plugin

Translations : Outstanding

Drill down plugin - Stock item Invoice AV Error

Stock items invoice option includes serial numbers - When Filter select a Stock item on the filter, produces Access violation error (usually happens once a Stock item is filtered and select the (All) option on the filter list)

Access violation at address 61618965 in module 'TCDrillDown.of5'. Read of address 00000000



Need to close osFinancials with the End task on Windows Task Manager

You cannot print invoice on the Stock item Invoice option

Other options (i.e Customer invoice and Invoice stock item)

No access violation error produced.

No remarks and comments is displayed on the grid.

On the other options you can double-click to print the invoice.



Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Known issues - SQL Browser Plugin

Known issues - SQL Browser Plugin

SQL

SQLBrowser - Manual - Shop - Licence : Once-off

Documentation : Help documentation Online Help documentation : SQL-Browser plugin

Translations : Outstanding

Firebird SQL Error SQL Browser plugin

Extract modal for wiki (Tables-context menu) error

```
Dynamic SQL Error
SQL error code = -104
Token unknown - line 1, column 15
GLOBAL
```

Export file formats

Create JASON-files not creating XML, HTML, Excel, or Text files, if selected.

Documentation needs to be updated to include JSON-files option.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Known issues - Serials / Patches / Location

Comments - if the Serial/Batches Location plugin is activated

Can edit it in normal Set of Books but - cannot edit comments if the Serial/Batches Location plugin is activated - cannot edit comments - it launches the Serial Selection screen - maybe should be launched if you double-click on a comment line if the Serial/Batches Location plugin is activated

Think it pushes the data in the comment.

Add a new comment and double-click still launches the Serial selection screen - Maybe the comment line must be deleted and recaptured and edited when adding a new comment.

Created with the Standard Edition of HelpNDoc: Effortlessly optimize your documentation website for search engines

Known issues - Plugin - E-MailPro

Known issues - E-MailPro

Document EMail Pro Plugin - Manual - Shop - Licence : Once-off - This Plugin is included in the osFinancials5 subscription.

Documentation : Help documentation Online Help documentation : Document email pro

Translations : Outstanding

Attach files (Invoices not attached to mail message)

Invoice (or other documents not attached)

Invoice not attached to Mail message could possibly be a result of the EMailheader text not refresh with the Invoice details (*EHeaderText=Faktuur <#SDOCNO#> vanaf <#FROMCOMPANYNAME#>)* does not add the company name before sending mail

Preview att button does not launch the Invoice.

UBL setting

UBL setting - All – Attach the UBL for the Invoice as UBL prefixed with the Invoice number e.g. IN000031UBL2.xml

UBL setting – With SQL field UBL – does not attach the UBL file.

Templates may need updating

Dates - date of invoice and system date. No dates are included in the 10 Invoice html. And other document types.

Only comments ate imported. May need to add remarks, if included in the document.

Mass mail button on Email Pro Setup



Launch "*Mass mail selection*" screen. Click on Open button, produces sql error

> Dynamic SQL Error
> SQL error code = -104
> Token unknown - line 1, column 1
> Msql

Screen not translatable.

Before the point to the shop was initiating a message.

> *Massmail button Initiated the following message:*
>
> > This feature needs a separate serial please request your trail at
> > *https://www.osfinancials.org/en/webshop/* "

Setup Wizard (Not launched)

In addition to the Settings tab, you may also launch the "*Setup Wizzard*" to configure your connection details, for your SMTP and POP servers:



The options, is as follows:

Field	*Description*
SMTP server:	*Enter a valid SMTP (outgoing mail server) as registered with your ISP (Internet Service Provider) for your e-mail account settings.* *Note - with POP before SMTP (usually if you do not send e-mails via your provider) it is best to create an e-mail box that no one else will read. This is because if mail is read with multiple IPS on the mail box, the pop for SMTP will not work properly.* *It is best to use an account that is not used by anyone else.*
SMTP Port:	*The default port is "25". This is determined by the default configuration of your operating system.*
SMTP username:	*Enter the SMTP username as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
SMTP password:	*Enter the SMTP password as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
POP server:	*Enter the POP server as registered with your ISP (Internet Service Provider) for your e-mail account settings.*

POP Username:	*Enter the POP username as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
POP password:	*Enter the POP password as registered with your ISP (Internet Service Provider) for your e-mail account settings.*

Click Next.



The options, is as follows:

Field	*Description*
Return e-mail:	*This field is optional. You may enter your own e-mail address.*
Return name:	*Enter your name.*
E-mail header text:	*Add the text you need to send as the e-mail subject.*
CC: (multiple separate with ;)	*This abbreviation CC "Carbon Copy" indicates secondary recipients of a message. Those recipients who are to receive a copy of a message directed to another. The list of recipients in the CC field is visible to all other recipients of the message.* *Enter a valid e-mail address, if necessary.*
BCC: (multiple separate with ;)	*This abbreviation BCC "Blind Carbon Copy" allows you to send a copy of your correspondence to a third party when you do not want to let the recipient know*

	that you are doing this (or when you do not want the recipient to know the third party's e-mail address). You may also wish to enter this filed, when sending an e-mail to multiple recipients, you can hide their e-mail addresses from each other. *Enter a valid e-mail address, if necessary.*
Send test mail to:	*Here you can enter your own email address for the test.*
Send test mail to:	*Thick this option if a valid e-mail address is entered in the "Send test mail to" field.*
Copy basis file for:	*The default setting is "nl for the Dutch language. Select "en" for English.*
Certificate password:	*If you have selected a certificate, you need to enter a valid password for that certificate.*
UBL:	*From osFinancials version 4.0.0.1102 and TurboCASH5.2 (365) it is possible to send UBL2.0 files with the document.* *The option can be enabled on the settings tab and has 3 settings* • *Do not send UBL (standard)* • *Always send a UBL* • *Based on a UBL field in the dataset that contains the value T.* *The output can be checked for validity via this website* *https://peppol.helger.com/public/locale-en_US/menuitem-validation-bis2* *By default, EUR is used for currency exports.* *For stock unit standard SK is used or the first 2 letters of the stock unit.*

Click Next to check your settings.

If there are any errors, you need to click Back and correct your settings and configuration.

Access violations Plugin - E-MailPro

Access violation – Sudden Internet connection lost

osFinancials 5.0.0.374

Replicated when we had a Load shedding and lost Wifi connection all of a sudden whilst busy with email pro processes

> Access violation at address 0F30F000 in module 'accounting.exe'. Read of address 0F30F000.

Replicated Access violation from the E-Mail Pro tab on Debtors account

osFinancials 5.0.0.374

> Access violation at address 5005FD90 in module 'rtl260.bpl'. Read of address 0E5D7248.

Copied a layout file (TRN_3174 Document layout) from DOCUMENTS / DOCUMENTS to

D: \ osfinancials5 \ plug_ins \ reports \ REPORTS\DEBTOR \ reports folder – Available for selection then selected and then produced the access violation error clicking on the Email pro screen.

The files in that folder is LANG_906062 – Selected debtor label and LANG_906065 – Selected debtor delivery label

Access violation – UBL - With SQL UBL

If the With SQL UBL is selected on the Settings tab of E-mail Pro access violation error:

> "Access violation at address 124D52F6 in module 'emailDll.tpd'. Read of address 00000000"

UBL Setting (Not saving correctly) en – Defaults to nl

Setup Wizzard not launching.



Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Known issues - Plugin - Multimedia

Known issue - Multimedia plugin

Multimedia plugin - Manual - Shop - Licence : Once-off -

Search - View details for BATCH type

Search does not view details for BATCH type (EMPTY) multimedia screen. All other Types (GROUP, STOCK, DEBCR) list the details of Multimedia files



Could possibly mean that the Batch number "*00000001*" does not include a prefix while in many Sets of Books the batch number may include a prefix "*B0000001*" or "*J0000001*"



Delete confirmation

Delete multimedia files there is no confirmation message.

Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Known issues - Plugin - Multi-language accounts

Known issues - Multi-language accounts

Multi-language Set of Books plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation Online Help documentation : Multi-language accounts

Translation : Not checked at this stage

See - Multi-Language accounts

Multi-language accounts - Translate batch types

Setup ® Batch type - Languages - translations - Labels invisible need to focus before language is available - Batch name not visible if Text is selected, the Batch name is visible.

Languages Multi language - has also a display issue also in D10 Build 453 of Setup batch types where the text is sometimes unreadable - need to select the text to see the text

White text in White Background

Also in Classic theme - Translations

osFinancials5.1.0.4 Also replicated in osFinancials5.1.100 - since osFinancials5 (453)

Other screens is OK



Multi-language accounts - Translate Stock item descriptions -Languages - OpenOffice

See Translate Stock descriptions - Languages tab on Stock items.



osFinancials 5.1.0.100 - DOES NOT LAUNCH - ooEdit.html - OpenOffice Writer/Web (Replicated not launching ooEdit.html - OpenOffice Writer/Web in all versions of osFinancials5.1.0.XXX and in osFinancials5 (Build 453)

osFinancials 4.0.0.1093 - Launches ooEdit.html - OpenOffice Writer/Web (Still working correct in osFinancials4) This probably indicates that the installation of OpenOffice and Windows 11 updates is correct.

Tested in osFinancials4.10.0.1093 in The installed version is OpenOffice 4.1.12. and new updated install of OpenOffice 4.1.14.

If you have OpenOffice installed on your system, you may double-click in the Description field of any language, to launch Open



Write your text and use OpenOffice to format your text, etc., if necessary. A message will be displayed:

"Press ok if you are done with the document to continue!

Once finished, click the OK button to transfer your text to the "Description" field.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Known issues - Plugin - FileAndXMLImportExport

Known issues - FileANDXMLExportImport

FileandXML Export Import - Manual - Shop - Licence : Once-off

Translations : FileAndXMLImportExport

FileAndXMLImportExport plugin errors

FileAndXMLImportExport plugin error - folder not found

Menu : Plugins → Tools → FileAndXMLImportExport

> Import export folder not found!
> C:\osfinancials5\importdefs\FXMLEXPORT

Solution : Added a folder "*importdefs*" and subfolder "*FXMLEXPORT*" in the osFinancials5 root directory.

Then the plugin setup could be launched.

List index of bounds error

> List index out of bounds (-1). TComboBoxStrings is empty

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Known issues - Plugin - StockCheck - Bulkcheck tab - Errors

Known issues - StockCheck Plugin

StockCheck Plugin - Bulkcheck tab - Errors

Stock check / Stock correction - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Translations : Translations outstanding

To be advised.

The Post difference button, generate blank credit notes with no adjustments or corrections on the unposted credit notes.



Delete line - No Confirmation message



Confirmation message

> There ao check active do you want to see this? No wil make a new check and all current check data will be lost!

Post difference log entry on Correctie tab

> Correction credit note Done!

Confirmation message Post difference button.

> Are you sure you want to post the new inventory data?

Post difference button - Access violation error on Bulk check tab

This is replicated by typing text, e.g. "*Drill*" and enter. The when click in the Check button or the Post

difference button the Access violation error occurs.

violation of FOREIGN KEY constraint "FK_DOCLINE_STOCK" on table "DOCLINE"
Foreign key reference target does not exist

The Post difference button, generate blank credit notes with no adjustments or corrections on the unposted credit notes.



Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Known issues - Plugin - QuickOrder - Stockcount tab

Known issues - StockCheck plugin

QuickOrder StockCount (Voorraadtelling) tab

Quick Order - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Translations : Translations outstanding

Error - Closed Dataset

ZQGenSearch: Cannot perform this operation on a closed dataset error is replicated when clicking on the Voorraadtelling tab.



Orders tab

When the Quick order plugin is initiated, and the "*Just quickorder*" option on the "*Setup QuickOrder*" screen is not selected, the entire QuickOrder module (comprising three tabs: List, Generate documents, and Orders) will be available. You may click on the Orders tab.

When the Quick order plugin is initiated, and the "*Just quickorder*" option on the "*Setup QuickOrder*" screen is selected, only the Orders component of the entire QuickOrder plugin module will be available.



Nuwe - Selecteer rekening (lookup titlebar caption)

Type action

- Move 21022
- Copy 3293 / 21010

Dubbleclick = action

Edit qty and price

Columns

- (All) 20055
- (Sorted)
- WDOCID
- Factuur btw
- Afgedrukt 2964

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Welcome

osFinancials5/TurboCASH5 - Business Class

Saturday, 24 May 2025- 01:50:47 - osFinancials5 / TurboCASH5-Business Class Help

English Online help Afrikaans Online help

- osFinancials - Videos -

- TurboCASH - Videos - All videos -

osFinancials5/TurboCASH5 Business Class is the most comprehensive accounting software package available on the market today. With its powerful features, intuitive user interface, and support for 87 Sets of Books, it is an all-in-one solution for managing your financial requirements. It is also capable of supporting 79 different languages and tax regimes. With osFinancials5/TurboCASH5, you can easily take control of your finances and achieve success.
Thank you for exploring osFinancials5/TurboCASH5. We wish you all the best in your accounting journey!

osFinancials5/TurboCASH5 - Business Class

After years of development and support for osFinancials and TurboCASH, the current model is no longer working effectively. To address this issue, the team is introducing osFinancials5/TurboCASH5 Business Class a new version with additional features and capabilities.

While osFinancials 4 remains free to use, users seeking more advanced functionality can upgrade to osFinancials5/TurboCASH5 Business Class. This version is available free of charge for users with fewer than 500 transactions or documents. For those with more, a yearly contribution of 50 euros (excluding taxes) or 60 dollars will be required.

For users with existing subscriptions for multi-user or retail POS, the license for osFinancials5/TurboCASH5 Business Class will be included as part of their existing subscription.

Included in the registered version of osFinancials5/TurboCASH5 - Business Class

osFinancials5/TurboCASH5 Subscription

Process unlimited (more than 500) transactions and documents.

Every time an unregistered version of osFinancials5/TurboCASH5 is started, the following confirmation message will be displayed:

- This software is limited to 500 transactions or 500 documents. Please register and buy a license for osFinancials5.1/TurboCASH5-3.
  This copy of osFinancials/TurboCASH is not registered! Do you wish to register it now?

Unregistered versions will allow you to process up to 500 transactions and/or documents. Once this limit is reached, osFinancials5/TurboCASH5 will not allow any processing of transactions, in batches and/or documents.

Once you have registered osFinancials5/TurboCASH5, you will receive an unlocking code and will be able to process further transactions and/or documents.

Plugins included in the osFinancials5/TurboCASH5 Subscription

Bank import

BankImport Plugin -

Licence : Included in osFinancials5/TurboCASH5 Subscription.

Documentation : Help topic.
Documentation : osFinancials website - Bank import plugin -
Documentation : osFinancials website - Bank Reconciliations Plugin -

The Bank Import plugin included with the osFinancials5/TurboCASH5 Subscription is a handy tool for managing and processing the transactions in your bank and credit card accounts. You can download electronic bank statement files directly from your online banking services at your bank or financial institution. After that, you can use the Bank Import plugin to import these bank statements into your bank accounts. This process saves you a lot of time and effort as you do not have to manually enter and process the transactions of your bank accounts and credit card accounts in separate Payment journals and Receipt Journals.

Additionally, the Bank Import Plugin has the ability to use bank references to automatically assign

transactions to the appropriate accounts, This automation not only saves time, but also reduces the risk of human error associated with manual data entry. Overall, using this Bank Import plugin is a smart choice for businesses or individuals who want to optimize their financial workflow within osFinancials5/TurboCASH5.

Document E-mail Pro

Document E-mail Pro Plugin - Manual - Shop -

Licence : Included in osFinancials5 Subscription / TurboCASH5 Subscription.

Documentation : Help topic.

Documentation : osFinancials website - Document email pro plugin -

Document E-mail Pro Plugin - Streamline your document handling and communication processes with our Document Email Pro Plugin. With a licence which is included in osFinancials5 Subscription / TurboCASH5 Subscription, you can effortlessly email invoices, quotes, and more directly from the program.

Customise email layouts to match the document type, ensuring a professional and tailored communication experience for your clients and suppliers. Send multiple documents simultaneously with ease, simplifying your workflow and saving valuable time.

Experience the convenience of sending digital sales and purchase documents in PDF format, enhancing efficiency and communication with customers and suppliers alike. Upgrade your document management with the Document Email Pro Plugin.

Budget Plugin

Budget Plugin - Manual - Shop - Help documentation

Licence : Included in osFinancials5 Subscription.

Effortlessly manage budgets for accounts, cost centres, and projects with the Budget Plugin, now included as a standard feature in the osFinancials5/TurboCASH5 Subscription. Access the Budgets option on the Reports ribbon for seamless integration.

Key Features:

- Flexible Budget Entry: Easily input budgets for accounts, cost centres, and projects directly within the osFinancials5/TurboCASH5 interface. Copy budget figures from the previous year of actual account balances.
- Comprehensive Budgeting: Cover all aspects of financial planning by setting budgets for various entities, including accounts, cost centres, and projects.

- Integrated Solution: Seamlessly integrate budget management into your overall financial workflow within osFinancials5/TurboCASH5.
- Advanced Filtering and Pivot Options: Utilize advanced filtering and pivot functionalities to analyse budget data effectively and gain deeper insights into your financial performance.
- Streamlined Processes: Simplify budgeting tasks and ensure accuracy by leveraging the intuitive interface and advanced features of the Budget Plugin.
- Comprehensive Reporting: Generate budget listing reports (Trial balance, Income statement, Balance sheet, or Standard column balances report types) and budget performance reports (Budget vs Actual to compare the budget figures versus the actual posted transactions). Export reports to spreadsheets and utilize powerful pivot features for in-depth analysis. Print and export budgets in the T-Account viewer.

Enhance your financial planning capabilities and streamline your budgeting processes with the Budget Plugin, empowering you to make informed decisions and drive financial success within your organisation.

Support Contract and Extra Tickets

Support Contract and Extra Tickets - Shop -

Support Contract:

The support contract grants you direct access to our team for issue resolution, subject to a "*fair use*" policy. Support is provided via telephone and/or email. Additionally, you'll receive interim updates of osFinancials where bugs are fixed and new features introduced.

Extra Tickets:

Additional support tickets beyond the "*fair use*" allocation can be purchased at a discounted rate for contract holders.

Please note that development or modification of osFinancials and document layouts are not included in the support contract.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Scope of this documentation

osFinancials5/TurboCASH5 Business Class

Saturday, 24 May 2025 - 01:50:47

Differences in osFinancials5 and TurboCASH5

The documentation provided for both osFinancials5 and TurboCASH5 is designed to be comprehensive and applicable to both software versions, despite their minor differences. Here's a summary of the key points and differences:

Shared Source and Primary Differences

- Shared Source: Both osFinancials5 and TurboCASH5 share the same source code, which means they have a lot of common features and functionalities.
- Primary Difference: The primary difference between the two is the base, which influences some of the interface and address formats.

Address Layout Differences

- osFinancials5: The address format is displayed as:
  - Address 1, Postal code, Address 2, Address 3.
- TurboCASH5: The address format is displayed as:
  - Address 1, Address 2, Address 3, and Postal code.

Business Class Subscription

- Basic Subscription: Both versions include processing of more than 500 transactions and some plugins are included in the subscription.
- Plugins: Some plugins are designed specifically for the Dutch market and are not available in TurboCASH5. Plugins designed for the international market are included in both osFinancials5 and TurboCASH5.

Documentation Formats

- EngHelp.chm File: This context-specific help file can be launched using the F1 key from most screens in the osFinancials5 and TurboCASH5 interfaces.
- Online Help: Available in English Online help and Afrikaans Online help, This online help will be updated later and may include additional or updated help topics. This is supplementary to the EngHelp.chm file included in the installations.

Applicability

- Documentation Coverage: The documentation covers all features in both osFinancials5 and TurboCASH5, ensuring that users of either software can find the information they need.
- Screens and Text: While the documentation may refer to osFinancials5 in screenshots and text, the information is generally applicable to TurboCASH5 as well.

Conclusion

The documentation is designed to be flexible and comprehensive, catering to users of both osFinancials5 and TurboCASH5. The minor differences in address formats and available plugins are noted, but the core functionalities and features are shared between the two software versions.

Plugins in osFinancials5 and TurboCASH5

Plugins Specific to TurboCASH5

- Plugins Set to False: Some plugins are specifically designed for the Dutch market and are set to false in TurboCASH5. These plugins are not available in the TurboCASH5 subscription.
- Plugins Menu: The Plugins menu in TurboCASH5 will only list the plugins that are shipped and included with the TurboCASH5 subscription.

Included Plugins in osFinancials5 Subscription / TurboCASH5 Subscription

- EmailInvoice Document E-mail Pro: Allows for the emailing of invoices directly from the software.
- Bank Import: Enabled in Setup → Data parameters by ensuring the "*Default bank reconciliation method*" field is not ticked.

Marketable Plugins

These plugins are functional and can be used with both osFinancials5 and TurboCASH5. Some may require additional licenses.

- Activa: Plugin for managing assets.
- Charter: Specific functionality for generating charts.
- Document Export Import: Allows for the export and import of documents.
- DrillDown: Enables drill-down functionality for detailed data analysis.
- Freefields: Adds customisation of fields to various forms.
- LocationBatchAndSerials: Manages locations, batches, and serial numbers.
- Multimedia: Integrates multimedia elements into the software.
- Multi-user Agenda: Provides a shared agenda for multiple users.
- Remittance: Facilitates remittance processes.
- Price agreement: Manages pricing agreements.
- Subscriptions: Handles subscription-based billing.

Essential Plugins

These plugins are crucial for specific functionalities within osFinancials5 and TurboCASH5.

- ReportMan - Report designer: Essential for customising layout files and reports.
- Register plugins: Adds licenses to plugins.
- SQL Browser: Essential for adding reporting groups when Customising your own Set of Books.
- HandyTools: Advanced tools for experienced users.

Plugins That Cannot Be Disabled

- DYNADBREG: This plugin cannot not be disabled and is essential for certain functionalities within osFinancials5/TurboCASH5.

Summary

The plugins available in TurboCASH5 are tailored to meet the needs of users while excluding those specific to the Dutch market. Both osFinancials5 and TurboCASH5, includes Essential plugins like Report designer, SQL Browser, and HandyTools are included to ensure core functionalities are maintained. Marketable plugins offer additional features that can be licensed as needed, enhancing the osFinancials5 and TurboCASH5 capabilities.

Icons are used in this documentation

The following icons are used in this documentation:

Spreadsheet Export / Import

Next

Important

Note

Tip

Accounting equation (Debits = Credits)

Warning

Bug

	Bug fixed
	Bug history
	Plugins
	New
	Webshop
	Help (Press F1 /Search in Help file)
	See / Read more

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

New features in osFinancials5

osFinancials5/TurboCASH5 Business Class

Saturday, 24 May 2025- 01:50:47

English Online help

Afrikaans Online help

osFinancials5/TurboCASH5 Business Class

After years of development and support of osFinancials and TurboCASH we came to the conclusion the current model does not work. To break through this glass ceiling we are introducing osFinancials5/TurboCASH5 Business Class.

osFinancials 4 / TurboCASH 4 is free to use but if you want more out of your software then osFinancials5/TurboCASH5 Business Class is the version you want to use.

If you have less then 500 transactions / documents you can use this version free of charge. Above that we ask you for a contribution of 50 euro (excl.)/ 60 dollars per year.

If you have any subscription already like multi-user or retail POS, etc., the licence will also be included.

Included in the registered version of osFinancials5/TurboCASH5 - Business Class

osFinancials5/TurboCASH5 Subscription

Process unlimited (more than 500) transactions and documents.

Every time an unregistered version osFinancials5/TurboCASH5 is started, the following confirmation message will be displayed:

> This software is limited to 500 transactions or 500 documents. Please register and buy a licence for osFinancials
> This copy of osFinancials is not registered! Do you wish to register it now?

Unregistered versions will allow you to process up to 500 transactions and /or documents. Once this limit is reached, osFinancials5/TurboCASH5 will not allow any processing of transactions, in batches and/or documents.

Once you have registered osFinancials5/TurboCASH5, you will receive an unlocking code and will be able to process further transactions and or documents.

Bank import

BankImport Plugin -

Licence : Included in osFinancials5/TurboCASH5 Subscription.

Documentation : Help topic.
Documentation : osFinancials website - Bank import plugin -
Documentation : osFinancials website - Bank Reconciliations Plugin -

The Bank Import plugin included with the osFinancials5/TurboCASH5 Subscription is a handy tool for managing and processing the transactions in your bank and credit card accounts. You can download electronic bank statement files directly from your online banking services at your bank or financial institution. After that, you can use the Bank Import plugin to import these bank statements into your bank accounts. This process saves you a lot of time and effort as you do not have to manually enter and process the transactions of your bank accounts and credit card accounts in separate Payment journals and Receipt journals.

Additionally, the Bank Import Plugin has the ability to use bank references to automatically assign transactions to the appropriate accounts, This automation not only saves time, but also reduces the risk of human error associated with manual data entry. Overall, using this Bank Import plugin is a smart choice for businesses or individuals who want to optimize their financial workflow within osFinancials5/TurboCASH5.

Document E-mail Pro

Document E-mail Pro Plugin - Manual - Shop -

Licence : Included in osFinancials5 Subscription / TurboCASH5 Subscription.

Document E-mail Pro Plugin - Streamline your document handling and communication processes with our Document Email Pro Plugin. With a licence which is included in osFinancials5/TurboCASH5 Subscription, you can effortlessly email invoices, quotes, and more directly from the program.

Customise email layouts to match the document type, ensuring a professional and tailored communication experience for your clients and suppliers. Send multiple documents simultaneously with ease, simplifying your workflow and saving valuable time.

Experience the convenience of sending digital sales and purchase documents in PDF format, enhancing efficiency and communication with customers and suppliers alike. Upgrade your document management with Document Email Pro Plugin.

Budget Plugin

Budget Plugin - Manual - Shop - Help documentation

Licence : Included in osFinancials5 Subscription / TurboCASH5 Subscription.

Effortlessly manage budgets for accounts, cost centres, and projects with the Budget Plugin, now included as a standard feature in the osFinancials5 Subscription / TurboCASH5 Subscription. Access the Budgets option on the Reports ribbon for seamless integration.

Key Features:

- Flexible Budget Entry: Easily input budgets for accounts, cost centres, and projects directly within the osFinancials5/TurboCASH5 interface. Copy budget figures from the previous year of actual account balances.
- Comprehensive Budgeting: Cover all aspects of financial planning by setting budgets for various entities, including accounts, cost centres, and projects.
- Integrated Solution: Seamlessly integrate budget management into your overall financial workflow within osFinancials5/TurboCASH5.
- Advanced Filtering and Pivot Options: Utilize advanced filtering and pivot functionalities to analyse budget data effectively and gain deeper insights into your financial performance.
- Streamlined Processes: Simplify budgeting tasks and ensure accuracy by leveraging the intuitive interface and advanced features of the Budget Plugin.
- Comprehensive Reporting: Generate budget listing reports (Trial balance, Income statement, Balance sheet, or Standard column balances report types) and budget performance reports (Budget vs Actual to compare the budget figures versus the actual posted transactions). Export reports to spreadsheets and utilize powerful pivot features for in-depth analysis. Print and export budgets in the T-Account viewer.

Enhance your financial planning capabilities and streamline your budgeting processes with the Budget Plugin, empowering you to make informed decisions and drive financial success within your organisation.

Other features

Bulk time entries - See video on Bulk time entries

Bulk time entries may be added for selected debtors (customers / clients) accounts. For example, if a debtor (customer / client) books a training course or workshop for a week, you may schedule the appointments for every day of the week.

These bulk time entries will add the multiple appointments for a selected debtor (customer / client) account to the calendar as hours type events for selected dates and time slots.

Quotes can be created for these events. These quotes can be edited, if necessary and sent to the debtor (customer / client).

Once these appointments are completed, you may convert the quotes to invoices.

Spreadsheet reports osFinancials5/TurboCASH55 and the power of Spreadsheets

- Spreadsheet sales (Default ribbon)

- Spreadsheet reports (Reports ribbon) - See video on Spreadsheet reports.

Spreadsheet Export / Import - See video on Improved Export/Import -

The Spreadsheet Export / Import spreadsheet feature allows to easily export data into spreadsheets, edit the data and import it.

Excel Export / Import is available in the following options:

Setup ribbon:

- Setup → Accounts
- Setup → Groups
- Import Accounts, Import Debtors/Creditors, Import Stock

Default ribbon

- Batch entry (all batches)
- Edit → Repeating transactions
- Stock (Import / Export tab)
- Documents - Context menu - Documents → Spreadsheet import

Ledger analyser 1 and Ledger analyser 2

- *Zoom in / Zoom out + / - buttons added to resize (increase / decrease the font) the reports (i.e. Trial balance, Balance sheet and Income statement) on screen. This Zoom feature is similar to that in Spreadsheets.*
- *Pivot - View, filter and analyse your report on screen, view graphs, customise datasets and types of graphs.*
- *SBR view - Add SBR references for accounts and reporting groups in Setup → Accounts. Once the references are set, and generate reports on screen, click on the SBR view button, check, filter and copy to clipboard. Open your spreadsheet program, and copy the contents into your spreadsheet, save the data, etc.*

Documents - Graph

Click on the Graph button to view the documents in a graph. Use the filter options on the Documents list screen, to view graphs for specific filtered results in documents.

See video on Themes. The values for the themes are set in the colors.ini file in the themes folder. The "Material" theme with black icons (based of SVG (Scalable Vector Graphics) icons is introduced in osFinancials5.1 (Build 518) and TurboCASH5.2 (Build 363).

The Blue, Glass, Silver, Soft-blue theme includes a similar set of icons as in the Material theme (navy-blue icons).

The "Classic" theme (default theme) and "VS2010" theme displays the same set of icons (located in the "...\bin\themes\Classic" folder.

Age analysis See video on new age analysis reporting and open item.

View and choose options for the new Age analysis report on screen and print it on the Reports ribbon and on the Open Item - Due tab (Default ribbon).

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Features

osFinancials5/TurboCASH5 Business Class

Saturday, 24 May 2025 - 01:50:47

Some features in the basic version of osFinancials5/TurboCASH5, are:

4K monitor support

osFinancials5/TurboCASH5 supports displays which can handle content in a resolution known as 4K. 4K resolution refers to a display with approximately 4,000 pixels in the horizontal direction, usually specified as 3840 pixels × 2160 lines (8.3 megapixels) or 4096 pixels × 2160 lines (8.8 megapixels). It provides a higher level of detail and clarity compared to lower-resolution displays.

Themes

Selecting supported themes

osFinancials5/TurboCASH5 allows you to personalise the interface by selecting different themes from the Theme menu on the Setup ribbon.

By default, osFinancials5 is installed in the "*Classic*" theme (default theme) and TurboCASH5 is installed in the "*Material-navy*" theme . If you prefer a different look, you can choose the "*Blue, Glass, Silver, Soft-blue" or "VS2010"* theme in osFinancials5/TurboCASH5. These themes feature a navy-blue colour scheme and offer a collection of icons similar to those in the "*Material*" theme. In addition to the Material theme's black icons, you may select other coloured variants such as "*Material-blue, Material-green, Material-maroon, Material-navy"* or *"Material-pink*". Selecting a different theme from the Theme menu allows you to customise the interface to your preferences.

Customising themes

In osFinancials5/TurboCASH5, you have the option to edit the "colors.ini" file to customize various aspects of the theme, including theme style, ribbon colours, tablet mode, and more. To make changes, you can open the "colors.ini" file in your preferred system text editor such as Notepad or Notepad++. Within this file, you can modify the values of the settings to suit your specific requirements.

Custom themes

In osFinancials5, you have the option to easily customise the colour of all 227 icons (in the SVG "*Scalable Vector Graphics*" file format) used in the interface. This customization process can be completed in less than a minute by utilizing a text editor such as Notepad++ and the Search and Replace feature. By replacing the default black colour with a colour of your preference, you can personalise the appearance of the icons in the "*Material*" theme to suit your taste.

If you opt for the "Blue, Glass, Silver," or "Soft-blue" theme in osFinancials5/TurboCASH5, you will encounter a set of icons resembling those found in the "Material" theme, but featuring a navy-blue colour palette. These themes offer an alternative visual presentation with cohesive icons, enabling you to personalise the interface by selecting a different theme from the Theme menu on the Setup ribbon.

Unlimited Sets of Books

Unlimited Sets of Books - In osFinancials5/TurboCASH5, you may create and manage multiple independent Sets of Books (Accounting databases) within the same osFinancials5/TurboCASH5 installation. Each set of books has its own independent chart of accounts, general ledger, subsidiary ledgers, and transactional data.

Languages

osFinancials5/TurboCASH5 is a comprehensive financial management solution that supports multiple languages and tax regimes. With its intuitive user interface and powerful features, it provides an all-in-one solution for managing your financial requirements.

There are 87 Sets of Books (databases) available, which can be downloaded and customised, through the "*Let osFinancials help you to create a Set of Books?*" option, to meet specific language and tax requirements. These Sets of Books are pre-configured with language and terminology specific to certain countries and tax regimes.

When you open a Set of Books, osFinancials5/TurboCASH5 automatically displays the user interface and reports in the associated language. However, you have the flexibility to change the language by selecting from the "Switch language" option.

Furthermore, you can set a specific language as the default for a Set of Books, ensuring consistent language usage throughout the financial management process.

In addition to the pre-configured languages, you have the ability to create your own language and customize it according to your specific needs, industry requirements, and preferred terminology.

Plug-in: Multi-Language accounts

Help topic: Plug-in: Multi-Language accounts - Manual - Shop - Licence : Once-off -

The Multi-Language accounts plugin in osFinancials5/TurboCASH5 provides the functionality to translate ledger, group, and stock (inventory/product) names into multiple languages. This plugin is a separate feature that can be added to osFinancials5/TurboCASH5 to enhance language customisation and support.

With the Multi-Language accounts plugin, you can define translations for various account names, group names, and stock items in different languages. This allows users to work with osFinancials5/TurboCASH5 in their preferred language and ensures that the financial information is accurately represented in the desired language.

The plugin enables you to select different languages for different users, allowing each user to work in their preferred language for accounting purposes. It facilitates multilingual accounting, making it easier for employees and stakeholders who may be more comfortable working with specific languages.

By offering the Multi-Language accounts plugin, osFinancials5/TurboCASH5 enhances its flexibility and adaptability to meet the diverse language requirements of its users, making it a versatile financial management solution for international organizations and users operating in multilingual environments.

Print documents in the language of debtors (customers/clients) and creditors (suppliers/vendors)

osFinancials provides the capability to print documents in the language of debtors (customers/clients) and print documents in the language of creditors (suppliers/vendors). This feature allows you to generate and send sales documents such as quotes, invoices and credit notes and purchase documents such as orders, purchases and supplier returns in the language preferred by your debtors and creditors.

When creating documents, you can set the language preference for each debtor and creditor individually. This ensures that the printed documents are generated in the appropriate language for each party, enhancing communication and facilitating smoother transactions.

By supporting debtor and creditor language preferences, osFinancials5/TurboCASH5 enables you to provide a more personalized and professional experience for your customers and suppliers. It helps to eliminate language barriers and improve clarity in financial communication, which can contribute to stronger business relationships and customer satisfaction.

Whether you need to print documents in multiple languages for a global customer base or cater to specific language preferences of local clients and suppliers, osFinancials5/TurboCASH5 offers the functionality to meet your requirements and streamline your document management process.

RTL (Right-to-Left) languages

osFinancials5/TurboCASH5 has the capability to support RTL (Right-to-Left) languages. RTL languages are languages that are written and read from right to left, such as Arabic, Hebrew, and Persian. osFinancials5/TurboCASH5 ensures that its user interface, reports, and other components are properly aligned and displayed to accommodate RTL language requirements.

By supporting RTL languages, osFinancials5/TurboCASH5 enables users who work with these languages to have a seamless and user-friendly experience. The interface elements, text alignment, and overall layout are designed to cater to the specific reading and writing direction of RTL languages.

This feature enhances the usability and accessibility of osFinancials5/TurboCASH5 for users in regions where RTL languages are prevalent, allowing them to effectively manage their financial tasks in their preferred language orientation.

MSSQL Database type Set of Books

osFinancials5/TurboCASH5 supports both MSSQL (Microsoft SQL Server) and Firebird database types for Sets of Books. To create a basic empty Sets of Books for the MSSQL (Microsoft SQL Server) database type from scratch, you may select the database type in the option to "Customise your own Set of Books (Advanced)?".

Ledger

The general ledger is a core component of the accounting system in osFinancials5/TurboCASH5. It serves as a central repository for recording and storing all financial transactions and budgets of a business. The general ledger contains individual accounts that track various types of financial activities, such as revenue, expenses, assets, liabilities, and equity.

Each account in the general ledger represents a specific category or type of transaction, such as sales, purchases, expenses, etc. Transactions are recorded in the general ledger using a double-entry bookkeeping system, where every transaction has an equal debit and credit entry, ensuring that the accounting equation remains in balance.

Assets = Liabilities + Equity

The general ledger provides a detailed and chronological record of all financial activities, allowing businesses to track and analyse their financial performance. It serves as the foundation for generating important financial reports such as the trial balance, income statement, and balance sheet.

In osFinancials5/TurboCASH5, the general ledger module allows users to create and manage their chart of accounts, record transactions, manage budgets, generate financial reports, and perform other essential

accounting tasks. It provides a comprehensive view of a company's financial position and financial performance. This helps to facilitate accurate and reliable financial management and decision-making.

Accounting standards, Accounting framework and Legislation

osFinancials5/TurboCASH5 offers flexibility in configuring the chart of accounts to comply with various accounting standards, accounting frameworks, and legislation, including the languages applicable to your country. This ensures that you can customize the system to meet the specific requirements and language preferences of your business and the regulatory environment in which you operate. This includes adapting the chart of accounts structure, account classifications, and financial categories to meet the requirements of local accounting practices.

Here's an overview of how osFinancials5/TurboCASH5 supports compliance:

1. Accounting standards: osFinancials5/TurboCASH5 allows you to configure your chart of accounts to align with different accounting standards such as GAAP (Generally Accepted Accounting Principles), IFRS (International Financial Reporting Standards) full, and IFRS for SMEs (Small and Medium-sized Enterprises). This ensures that your financial records and reporting adhere to the specific requirements of the chosen accounting standard.
2. Accounting frameworks: osFinancials5/TurboCASH5 supports the customisation of the chart of accounts to comply with your preferred accounting framework. Whether you follow a specific accounting framework or have unique reporting requirements, osFinancials can be configured to meet those needs. This allows for consistent and standardised financial reporting practices within your organization.
3. Tax regulations: osFinancials5/TurboCASH5 enables you to configure your chart of accounts to comply with tax regulations specific to your country or region. This includes setting up tax accounts, defining tax rates, and ensuring that financial transactions are properly categorized for tax reporting purposes. By aligning with tax regulations, osFinancials5/TurboCASH5 helps you accurately calculate and report taxes.
4. Legal compliance: osFinancials5/TurboCASH5 assists in complying with legal requirements related to financial management and reporting. By configuring the chart of accounts to reflect the applicable legal framework, osFinancials5/TurboCASH5 helps ensure that your financial statements and reports meet the necessary legal standards.

Additionally, osFinancials5/TurboCASH5 allows you to work with the software in different languages. This means that you can choose the language that is applicable to your country or region, making it easier for users to navigate the system, input data, and generate reports in their preferred language.

By providing this flexibility, osFinancials5/TurboCASH5 enables businesses to maintain accurate financial

records, generate compliant financial statements, and meet the reporting obligations in their local accounting standards, frameworks, and legislation while working in their preferred language.

Account groups and Financial Categories

In osFinancials5/TurboCASH5, you can add reporting groups for Account Group 1 and/or Account Group 2 to categorise your accounts further. These groups allow you to classify and organise accounts based on their nature or function. Each account can be mapped or linked to the appropriate reporting group (Account group 1 and/or Account group 2). The category or classification for Balance sheet accounts and Income statement accounts could be as follows:

1. Balance sheet accounts (ledger accounts, bank accounts, and tax accounts for VAT/GST/sales tax) could be linked to the appropriate reporting group (Account Group 1 and/or Account Group 2) such as Cash and cash equivalents, Fixed assets or Non-current assets, PP&E - Property, Plant, and Equipment, Current assets or Non-current assets, Intangible assets, Current liabilities, Non-current liabilities, Long-term liabilities, Equity.
2. Income statement accounts (income accounts and expense accounts) could be linked to the appropriate reporting group (Account Group 1 and/or Account Group 2) such as Operating revenue, Other revenue, Cost of Sales (COS) / Cost of Goods Sold (COGS) / Cost of Services Rendered (COSR), Operating expenses, Non-operating revenue, Non-operating expenses.

Financial categories: Each reporting group can be assigned to one of the five financial categories: assets, liabilities, equity, revenue, and expenses. This ensures that the accounts are properly categorized and aligned with the standard financial reporting structure.

Sequence/order: In the Setup → Groups (Setup ribbon), you have the flexibility to change the sequence order of the reporting groups. This allows you to structure the layout of the chart of accounts in the trial balance, balance sheet, and income statement according to your preferences.

By utilising reporting groups, financial categories, and sequence order, osFinancials5/TurboCASH5 enables you to effectively organize and analyse your chart of accounts, providing a clear representation of your financial data in various financial reports.

Chart of Accounts - Number of digits

Sets of Books - The Chart of Accounts in osFinancials5/TurboCASH5 supports up to 11-digits (8-digits for the main accounts and 3 digits for the sub-accounts). You have the flexibility to choose from a range of templates for Sets of Books, including a 6-digit structure consisting of 3 digits for the main accounts and 3 digits for the sub-accounts. These templates can be downloaded through the "*Let osFinancials help you to create a Set of Books?*" option.

Alternatively, if you prefer to start with a basic empty Sets of Books, you can utilize the "*Customise your own Set of Books (Advanced)?*" option. This advanced feature allows you to define the number of digits, with a maximum of 11 digits (8 digits for the main accounts and 3 digits for the sub-accounts).

The basic Sets of Books created using this option will include the essential three main accounts: Debtor's Control, Creditor's Control, and Retained Earnings. The remaining Chart of Accounts can be fully customized according to your specific requirements. This flexibility enables you to tailor the Sets of Books to suit your unique accounting needs.

Cash books (bank accounts)

In osFinancials5/TurboCASH5, there is no limitation on the number of cash books (bank accounts) you can have in a Set of Books. You can create and manage as many cash books as needed to accommodate your organization's financial requirements. This allows for flexibility in tracking and managing multiple bank accounts within your accounting system.

Cash books, also referred to as bank accounts in osFinancials5/TurboCASH5, are a fundamental component of the accounting system that tracks and manages a company's cash transactions. A cash book represents a specific bank account maintained by the business, typically linked to an actual bank account where cash inflows and outflows occur.

In osFinancials5/TurboCASH5, the cash book module allows users to record and monitor various cash-related activities, including deposits, withdrawals, payments, receipts, and bank transfers. It provides a centralised location to track the movement of funds in and out of specific bank accounts.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - Licence : Once-off -

The Bank import plugin is included with the osFinancials5 Business Class licence / TurboCASH5 Business Class licence, meaning you have access to it without any additional cost or separate licence requirement.

With the plugin, you can download bank statement files from your online banking app or portal provided by your bank or financial institution. These files can be imported into the appropriate bank accounts (cash books) in osFinancials5/TurboCASH5.

You can download statements for multiple bank accounts and credit cards, as long as you have them linked to your online banking. Each bank account or credit card should have its corresponding Payments and Receipts journals set up in osFinancials5/TurboCASH5.

Importing the bank statements automatically populates the transactions into the Payments and Receipts columns, saving you time and reducing the risk of errors associated with manual entry.

The plugin offers a user-friendly interface with context menus that make it easy to locate, select, and search

for specific transactions, debtors, creditors, or general ledger accounts. This simplifies the navigation and management of your bank transactions.

You can link debit transactions to credit transactions and vice versa, allowing for accurate tracking of outstanding balances and efficient management of payments and receipts. You can also link a portion of a payment or receipt to multiple outstanding transactions if needed.

Additionally, the plugin allows you to link accounts to specific debtors, creditors, or general ledger accounts. This ensures that subsequent bank statement imports automatically allocate transactions correctly based on the predefined account linkages, improving accuracy and saving time.

The plugin utilizes bank references to automatically allocate or link various transactions to the correct accounts in your Set of Books. It supports automatic receipts for debit orders from your debtors and automatic payments for managing supplier payments.

In summary, the Bank import plugin in osFinancials simplifies the import of bank statements, automates transaction allocation, and efficiently manages and reconciles your bank accounts. It reduces manual data entry, improves accuracy, and streamlines your financial management processes.

Reporting groups

osFinancials5/TurboCASH5 supports the usage of up to two reporting groups for various categories such as ledger accounts, debtors, creditors, stock (inventory/products), and documents. This feature allows you to categorize and classify your financial data based on different criteria or attributes that are relevant to your business.

By assigning reporting groups to these entities, you can generate reports and analyse your financial information based on specific groupings. This capability enhances your ability to track and analyse data at a more granular level, providing valuable insights into different aspects of your business operations.

Debtors (customers / clients)

The Debtors feature in osFinancials5/TurboCASH5, is specifically designed to manage and maintain debtor (customer / client) accounts. This feature provides a range of functionalities to effectively manage these accounts and ensure smooth customer relationship management. Here are some key aspects of the Debtors feature:

1. Account Management: You can create new debtor accounts, modify existing ones, delete or disable accounts based on your requirements. This gives you control over the debtor database and allows you to keep it up to date.
2. Account Details: Within each debtor account, you have the flexibility to make changes to various aspects, such as the debtor's name, contact details, addresses, and messages on the debtor form. You

can also manage the delivery address and select specific document layout files on the Delivery address tab. Additionally, you can set accounting and payment terms, including discounts and interest percentage charges, on the Accounting information tab. This ensures that you maintain accurate and up-to-date information for each debtor.

3. Activities Tracking: The Debtors feature allows you to efficiently manage various activities related to debtor accounts. It provides dedicated tabs for tracking Contacts, Appointments, and transactions on the Documents, Transactions, Bank accounts, Backorders and Stock items tabs. These capabilities enable you to gain a comprehensive view of interactions and transactions with each debtor, enhancing your ability to manage and maintain fruitful relationships.
4. Filtering and Search: osFinancials5/TurboCASH5 provides filtering and search options within the Debtors feature, enabling you to easily locate specific debtor accounts based on various criteria such as name, contact details, or other relevant information.
5. Reporting Groups: You can create up to two custom reporting groups for debtor accounts, categorizing them by attributes like geographic regions, customer types, or sales channels. This enables you to generate insightful views of your debtor data. It allows you to slice and dice the information based on multiple dimensions and conduct detailed analysis, providing a comprehensive view of your debtor data and supporting better decision-making and strategic planning.

By leveraging the Debtors feature in osFinancials5/TurboCASH5, you can efficiently manage customer accounts, streamline communication, track transactions, and maintain precise financial records. This enhances customer service, boosts efficiency, and strengthens financial management within your organization.

Creditors (suppliers / vendors)

The Creditors feature in osFinancials5/TurboCASH5 is specifically designed to manage and maintain creditor (supplier/vendor) accounts. This feature provides a range of functionalities to effectively manage these accounts and ensure smooth supplier/vendor relationship management. Here are some key aspects of the Creditors feature:

1. Account Management: You can create new creditor accounts, modify existing ones, delete or disable accounts based on your requirements. This gives you control over the creditor database and allows you to keep it up to date.
2. Account Details: Within each creditor account, you have the flexibility to make changes to various aspects, such as the creditor's name, contact details, addresses, and messages on the creditor form. You can also manage the delivery address and select specific document layout files on the Delivery address tab. Additionally, you can set accounting and payment terms, including discounts and charges, on the Accounting information tab. This ensures that you maintain accurate and up-to-date

information for each creditor.

3. Activities Tracking: The Creditors feature allows you to efficiently manage various activities related to creditor accounts. It provides dedicated tabs for tracking Contacts, Appointments, and transactions on the Documents, Transactions, Bank accounts and Stock items tabs. These capabilities enable you to gain a comprehensive view of interactions and transactions with each creditor, enhancing your ability to manage and maintain fruitful relationships.
4. Filtering and Search: osFinancials provides filtering and search options within the Creditors feature, enabling you to easily locate specific creditor accounts based on various criteria such as name, contact details, or other relevant information.
5. Reporting Groups: You can create up to two custom reporting groups for creditor accounts, categorizing them by attributes like geographic regions, supplier types, or purchase channels. This enables you to generate insightful views of your creditor data. It allows you to slice and dice the information based on multiple dimensions and conduct detailed analysis, providing a comprehensive view of your creditor data and supporting better decision-making and strategic planning.

By leveraging the Creditors feature in osFinancials5/TurboCASH5, you can efficiently manage supplier/vendor accounts, streamline communication, track transactions, and maintain precise financial records. This enhances supplier/vendor relationships, boosts efficiency, and strengthens financial management within your organization.

Contacts

The Contacts feature in osFinancials5/TurboCASH5 refer to individuals or entities associated with debtor (customer/client) and creditor (supplier/vendor) accounts. The Contacts feature allows you to maintain a list and details of contacts linked to these accounts for easy reference and communication.

Contacts play a crucial role in processing sales and purchase documents within osFinancials5/TurboCASH5. They help specify the relevant contact person or entity associated with a particular transaction. Here's how contacts are utilised in the process:

1. Sales documents: When creating sales documents such as invoices, credit notes, quotes, the default contact linked to the debtor (customer/client) account will be automatically selected. This ensures that the appropriate contact is associated with the transaction. The contact specified in the sales document represents the person responsible for the transaction or serves as the primary point of contact for the customer.
2. Purchase documents: Similarly, when generating purchase documents like purchases, supplier returns, orders, the default contact linked to the creditor (supplier/vendor) account will be automatically selected. This ensures that the relevant contact information is associated with the transaction. The

contact specified in the purchase document represents the person responsible for the transaction or serves as the primary point of contact for the supplier.

By assigning the correct contacts to the respective accounts, osFinancials5/TurboCASH5 ensures that the appropriate contact information is readily available when processing sales and purchase transactions. This helps maintain accurate and effective communication with customers, clients, suppliers, and vendors throughout the transactional process.

Including contact information on document layout files for sales and purchase documents is a valuable feature in osFinancials5/TurboCASH5. By printing contacts on these documents, you provide additional information for the recipient or reference, enhancing the clarity and professionalism of the transaction. This ensures that the necessary contact details, such as the name, phone number, email address, or any other relevant information, are readily available for easy communication or reference purposes. It allows recipients to quickly reach out to the relevant contact person or entity in case of any queries, clarifications, or further discussions related to the transaction.

Stock items (Inventory items / products)

The Stock items / Inventory items / products) in osFinancials5/TurboCASH5 features a comprehensive inventory system designed to manage and track stock items, inventory items or products. It supports an unlimited number of stock items and allows for detailed item-specific information. The inventory system also offers up to two reporting groups, enabling efficient data organisation and analysis.

With eleven different stock item types available, osFinancials5/TurboCASH5 provides flexibility in managing various types of products. When processing documents for debtors or creditors, or generating reports, the stock item lookup function helps in selecting the appropriate products. The system utilizes the chosen stock item's details to calculate selling and cost prices based on specified quantities, ensuring accurate pricing information on documents and reports.

The Stock items feature in osFinancials5/TurboCASH5 allows for easy management of inventory items or products. You can create, edit, delete, or disable items as needed, and the feature provides filtering and search options for efficient item location. Within each item, you can make changes to important details such as stock code, description, quantities, reorder levels, and more.

Additionally, the inventory system offers various settings on the Ledger tab and allows for managing activities on the Document groups, Transactions, Image, Multi-group, and Backorders tabs. This comprehensive set of features ensures efficient inventory tracking, accurate pricing, and streamlined document and report generation, making osFinancials5/TurboCASH5 a reliable solution for managing and optimizing your inventory management processes.

Documents

In osFinancials5/TurboCASH5 the Documents feature provides a comprehensive solution for processing and managing sales documents and purchase documents related to debtor (customer/client) and creditor (supplier/vendor) accounts. It offers a range of functionalities to streamline document management and automate source document and transaction generation. Additionally, osFinancials supports the usage of up to two reporting groups for documents. This feature allows you to categorize and classify your documents based on different criteria or attributes that are relevant to you. This categorization and classification feature enhances your document organization capabilities, making it easier to manage and retrieve specific documents when needed. Here's an overview of the key aspects of the Documents feature:

1. Sales documents: This includes (invoices, credit notes, quotes), associated with debtor accounts. You can create, process, and manage these sales documents (invoices, credit notes, quotes) within osFinancials5/TurboCASH5. The Documents option provides a centralized interface to handle all sales documents efficiently. Additionally, the Documents option provides a centralized interface to process sales documents (invoices, credit notes, quotes) for debtors (customers/clients).

2. Purchase documents: This comprises purchases, supplier returns, orders relevant to creditor accounts. Similarly, you can create, process, and manage these purchase documents using the Documents option. It allows for seamless handling of purchase transactions and associated records. Furthermore, the Documents option provides centralized management for purchase documents (purchases, supplier returns, orders) for creditors (suppliers/vendors).

3. Transaction generation: When you create sales documents or purchase documents, osFinancials automatically generates the required transactions and source documents based on the document details. This ensures accurate and consistent recording of financial transactions in your accounting system. Moreover, in addition to the normal processing options, the context menus provide quick access to process various options for easy copying, converting documents, and more to process documents.

4. Layout files: The Documents feature allows you to choose from various layout files for printing or reprinting your sales and purchase documents. You can use the Report designer to customize the appearance and format of these documents to align with your business branding or specific requirements.

5. Print and Reprint: With osFinancials5/TurboCASH5, you have the ability to print or reprint your sales and purchase documents as needed. This allows for easy distribution of invoices, credit notes, quotes, purchases, supplier returns, orders, and delivery notes relevant to your customers, suppliers, or internal stakeholders. Additionally, the powerful grid for documents contains the data for each document, allowing you to filter and search for specific documents according to the criteria you specify.

Overall, the Documents feature in osFinancials5/TurboCASH5 simplifies the management of sales documents and purchase documents. It automates transaction generation, provides options for selecting layout files, and enables printing or reprinting of these documents. By leveraging this functionality, you can streamline your document workflows, ensure accurate financial records, and effectively communicate with your customers and suppliers.

Journals / Batches

The Batch Entry / Journal Entry feature in osFinancials5/TurboCASH5 provides versatile functionality for creating customized batch or journal types tailored to your specific requirements. These batch types enable structured transaction organization, ensuring precise allocation to the appropriate ledger and debtor accounts. Here's an overview of this feature:

1. Batch Types Customization: In osFinancials5/TurboCASH5, you can define various batch types to match your unique needs. While many Sets of Books and templates include standard basic batches like sales journal, purchase journal, payments journal, receipts journal, and general journals (accessible through the "*Let osFinancials help you to create a Set of Books?*" / "*Let TurboCASH help you to create a Set of Books?*" option), osFinancials5/TurboCASH5 allows unlimited specific batch types. Examples of specialise journals, include Payroll journals, Depreciation journals, Fixed assets journals, Accrual journals, or any custom type necessary. Each batch type is designed for specific transaction categories or sets of related transactions, granting precise control over your accounting processes.
2. Batch / Journal Configuration: The Batch Entry / Journal Entry feature offers options to configure settings, reducing errors during batch transaction entry and processing: Journal configuration: The Standard tab and Advanced tab in the "*Options for this batch*" offer several options to configure default settings such as the default Contra account, Tax (VAT/GST/Sales tax) settings and other parameters for each type of journal. Configuring these settings, which reduce errors when processing transactions in journals:
    - Contra Account: Assign each batch (journal) to a specific contra account for easy identification and assignment of transactions to the corresponding contra account. This account will be the balancing account. When you balance the batch, the contra transactions will be generated to this contra account in the journal.
    - Lookup Accounts Configuration: You can set a journal so that you can select all accounts for the general ledger, debtors, creditors or only accounts for the general ledger or only debtors or only creditors in the journal. So for example, in the Sales journal you can choose to list only the debtor accounts in the Lookup and can choose when you enter invoices in the Sales journal. This speeds up the allocation of transactions so that only the relevant account type can be listed and selected.

3. Open Item Transactions: This is particularly useful for matching receipts or payments transactions with outstanding amounts. When you allocate transactions against open item accounts, you can choose to link the transactions against outstanding transactions. Link specific transactions to open item accounts for extra accuracy. This is especially useful for linking receipts or payment transactions with outstanding amounts. For example, when a payment is received from a debtor, you can assign the payment to a specific outstanding invoice.

4. Repeating Transactions: The Repeating transactions feature allows you to enter transactions occurring on a periodic basis (weekly, monthly, quarterly, annually, etc.). Enter transactions once in the Edit → Repeating transactions menu and, when due, process them into the standard batch, edit (if amounts have changed), delete, or add an entry. This time-saving feature simplifies recurring transaction handling.

5. Export and Import Feature: Export posted or unposted batches using delimited file options. osFinancials5/TurboCASH5 also supports Spreadsheet export and Spreadsheet Import options for batch transactions:

    - Posted Batches: Use the Import a posted batch option (F9:Process) of the "*Batch entry*" screen to select a posted batch on the Posted batches tab for import.

    - Spreadsheet Import/Export: osFinancials5/TurboCASH5 supports Excel Workbook (*.xlsx) file type Spreadsheet import and export features. You can export unposted batch transactions and save them as Excel Workbook files, or import batch transactions from saved Excel Workbook files.

    - Unposted Batches: Export batch transactions using the "Write delimited file" option (F9:Process) to create a Comma Separated Value (.csv) file. Import batch transactions via the "Delimited file import" option (F9:Process) by selecting the Comma Separated file (.csv) file.

6. Ledger Updates: You don't need to post or update transactions in batches every time. Close a batch and reopen it as needed to add or edit transactions. When finalizing batch processing and posting to the ledger, osFinancials5/TurboCASH5 automatically updates ledger accounts, including debtor and creditor accounts where applicable. This ensures financial statements, such as the trial balance, balance sheet and the income statement including relevant reports accurately include and reflect these transactions.

By utilising the Batch Entry / Journal Entry feature in osFinancials5/TurboCASH5, you can efficiently manage and allocate transactions across various batch types, maintaining accurate and up-to-date accounting records with precision.

Open item processing

The Open item processing feature in osFinancials is a method used in accounting and financial management to track and manage outstanding or unresolved transactions, often referred to as open items. An open item represents a transaction or a payment that has not yet been fully cleared or reconciled.

In osFinancials5/TurboCASH5, the open item processing module allows businesses to efficiently handle and monitor these open items, ensuring accurate tracking, reconciliation, and resolution of outstanding transactions. The module typically includes the following functionalities:

1. Recording Open Items: Users can enter details of transactions or payments that are not yet fully reconciled or resolved. This may include invoices issued to customers, bills received from suppliers, outstanding payments, or any other transaction that requires further processing.
2. Matching and Reconciliation: The open item processing module enables users to match open items with corresponding transactions or payments. For example, matching a customer payment with an outstanding invoice or reconciling a bank statement with recorded transactions. This helps identify and resolve discrepancies or differences between recorded transactions and actual financial records.
3. Ageing Analysis: The module provides ageing analysis functionality, allowing users to categorize and analyse open items based on their age or duration since the transaction occurred. This helps monitor the time it takes to clear or resolve outstanding items and prioritize actions accordingly.
4. Follow-up and Communication: Users can add notes or comments to open items, facilitating communication and collaboration within the organization. This feature allows employees involved in the resolution process to leave messages, update statuses, or provide additional information related to specific open items.
5. Reporting: The open item processing module offers reporting capabilities to generate summaries and detailed reports on open items. These reports provide insights into the status of outstanding transactions, ageing analysis, unresolved balances, and other relevant information.

By effectively utilizing open item processing in osFinancials5/TurboCASH5, businesses can streamline their reconciliation processes, ensure accuracy in financial records, track and resolve outstanding transactions efficiently, and maintain up-to-date and reliable financial information.

Reports

Ledger analyser

In osFinancials5/TurboCASH5, the Ledger analyser feature offers two options: the Ledger analyser 1 or

Ledger analyser 2 . These options allow users to view, analyse, and print various financial reports, including the Trial balance, Income statement, Balance sheet, Standard column balances, Budget vs actual and This year vs last year report types. You can also generate Budget listing reports using this feature.

Additionally, the Ledger analyser provides six column balance report types that are not directly printable but are available for analysis. In addition to analysis, you can also launch the T-account viewer from the Ledger analyser to print and export transactions for selected accounts and periods. This feature allows you to further examine and manage transactions associated with specific accounts and timeframes. These include Column balances and Column balances D/C for ledger accounts; Column balances debtors and Column balances debtors D/C for all the individual debtor (customer client) accounts; and Column balances creditors and Column balances creditors D/C for all the individual creditor (supplier/vendor) accounts.

When using the Ledger analyser feature, you have the option to export any of these reports to a spreadsheet for further analysis or customisation. Clicking the Export button within the Ledger analyser 1 or Ledger analyser 2 options will generate an "*Export.txt*" file in CSV format. This exported file will automatically open in Microsoft Excel or your preferred spreadsheet program, based on the default program associated with CSV files on your system.

CSV files provide a structured format that is compatible with spreadsheet applications, allowing you to conveniently view and work with the exported financial data. You can save the CSV file in different formats, perform calculations, apply formatting, and utilize various spreadsheet functionalities to analyse the column balances or other exported reports.

In summary, the Ledger analyser feature in osFinancials enables you to generate and export financial reports and column balances to CSV format, which can be opened and further processed in Microsoft Excel or other spreadsheet programs associated with CSV files on your system.

Pivot tables

osFinancials5/TurboCASH5 provides its own built-in pivot table functionality, allowing users to view and analyse reports such as the Trial balance, Income statement, Balance sheet, Standard column balances, Budget vs actual and This year vs last year report types and Budgets directly within osFinancials5/TurboCASH5. This means that you don't necessarily need to export the reports to a spreadsheet to utilise pivot tables.

In addition to the mentioned six report types, you may generate six column balances report types, such as Column balances and Column balances D/C for ledger accounts; Column balances debtors and Column balances debtors D/C for all the individual debtor (customer / client) accounts; and Column balances creditors and Column balances creditors D/C for all the individual creditor (supplier / vendor) accounts in a spreadsheet format to use the built in pivot table functionality in osFinancials5/TurboCASH5.

By using the pivot table feature within osFinancials5/TurboCASH5, you can perform dynamic analysis and customization on the data directly in the software. You can define rows, columns, values, and filters within the pivot table to organize and summarize the data according to your specific needs. This enables you to gain insights, identify patterns, and make informed decisions based on the financial information presented in these reports.

Furthermore, if you choose to export the reports to a spreadsheet, you can still leverage the pivot table functionality within the spreadsheet software to further analyse and manipulate the data. This provides you with the flexibility to use either osFinancials5/TurboCASH5 built-in pivot tables or the pivot table features of your preferred spreadsheet software, depending on your preferences and requirements.

In summary, osFinancials5/TurboCASH5 offers its own pivot table functionality for viewing and analysing reports, and if desired, you can also export the reports to a spreadsheet to utilize the pivot table features of the spreadsheet software. Both options allow you to perform dynamic and customizable analysis on your financial data.

T-Account viewer

The T-Account viewer feature in osFinancials5/TurboCASH5 allows you to view and analyse transactions in a T-account format. A T-Account is a visual representation of an account in bookkeeping, showing the transaction details and debits and credits associated with that account.

With the T-Account viewer, you can select a specific account from your chart of accounts and view all the transactions related to that account. The transactions are organised in a T-account layout, where debits are displayed on the left side and credits on the right side.

The T-account viewer provides a clear and concise overview of the transactions affecting a particular account, allowing you to analyse the account's balance and activity. You can see the transaction details such as the date, description, and amounts for each entry.

This feature is particularly useful for account reconciliation, identifying errors or discrepancies in transactions, and gaining insights into the financial activity of specific accounts. It provides a visual representation of the account's balance and helps in understanding how transactions have impacted the account over time.

The T-account viewer in osFinancials simplifies the process of reviewing and understanding account transactions, facilitating accurate financial analysis and reporting.

T-account viewer access on Reports ribbon

You may access the T-account viewer option or from the Ledger analyser 1 or Ledger analyser 2 options (right-click or double-click on specific accounts or groups) for the Trial balance, Income statement, Balance

sheet, Standard column balances, Budget vs actual and This year vs last year report types on the Reports ribbon.

In addition to the mentioned six report types, you may generate six column balances report types, such as Column balances and Column balances D/C for ledger accounts; Column balances debtors and Column balances debtors D/C for all the individual debtor (customer / client) accounts; and Column balances creditors and Column balances creditors D/C for all the individual creditor (supplier / vendor) accounts in a spreadsheet view.

On any of these six column balances report types, you may select an account and double-click on any period. This will launch the T-Account viewer with a list of all the transactions for the selected account and period. You may print and/or export the transactions.

T-account viewer access on other options

In addition to launching the T- account viewer from the Reports ribbon, you may also launch the T-account viewer from the following options on the Default ribbon:

1. Search - Investigator - Account or Batch type searched items.
2. Debtors - Transactions tab - Click on the Show transactions button
3. Creditors - Transactions tab - Click on the Show transactions button.

T-account viewer for Budget listing

In addition to the Budget vs actual budget performance report, you may list or print the budget figures (Budget listing reports), on the Trial balance, Income statement, Balance sheet, Standard column balances report types.

T-account viewer export

When you click the Export button in the T-account viewer in osFinancials5/TurboCASH5, it will generate an "*Export.txt*" file in CSV (Comma-Separated Values) format. The exported file will automatically open in Microsoft Excel spreadsheet or in your preferred spreadsheet program, depending on the default program associated with CSV files on your system.

CSV files are widely supported by spreadsheet applications, including Microsoft Excel, Google Sheets, and others. By opening the exported CSV file in a spreadsheet program, you can conveniently view and manipulate the transaction data in a tabular format. This allows for further analysis, sorting, filtering, and other operations using the features provided by the spreadsheet software.

You can also save the CSV file in a different format or perform any necessary adjustments before sharing

or utilising the exported data in other applications or processes.

In summary, the T-Account viewer in osFinancials5/TurboCASH5 allows you to export transactions as a CSV file, which can be opened and processed in spreadsheet programs such as Microsoft Excel or other applications associated with CSV files on your system.

Reports menus

Standard reports

The Reports for ledger, debtors, creditors, stock, sales, purchases, sales analysis, purchase analysis, documents, graphs, etc.

Spreadsheet reports

osFinancials5/TurboCASH5 supports the generation of Spreadsheet reports in Excel format, which can be opened in the powerful spreadsheet feature. These reports include:

1. Creditors and Debtors listing: These reports import postal address information into Excel.
2. Transactions per period: This report lists transactions, such as sales invoices, credit notes, purchases, and supplier returns, including transactions processed in journals, for a selected period.
3. General ledger - Budget: Reports on column balances for reporting groups and the current year.
4. General ledger (Transaction totals): Reports on column balances for reporting groups and the current year, displayed in separate columns or rows per period.
5. Sales analysis: Provides insights into stock movement and sales per period.

Users can recalculate the spreadsheet by pressing F9. These spreadsheet reports offer enhanced flexibility for data analysis and customization within osFinancials5/TurboCASH5.

Report designer

The Report designer in osFinancials provides a powerful tool for creating and customising reports according to your specific needs. It is integrated and customised within osFinancials5, utilising the Reportman reporting engine. The Report designer offers a wide range of components, functions, and features to design and modify reports and document layout files.

All reports and document layout files included in your osFinancials5 installation / TurboCASH5 installation are created using the Report manager designer. These reports and layout files are built on the Firebird database type and should also support other database types such as MSSQL.

The reports and document layout files are organized in a file structure in various folders within the

following directory of your osFinancials5 installation / TurboCASH5 installation:

```
"... \plug_ins\reports"
```

Here are the commonly used report categories:

1. Document layout files: The document layout files in osFinancials5/TurboCASH5 are stored in the following folder.

   ```
   "...\plug_ins\reports\DOCUMENTS\DOCUMENTS"
   ```

   Among the shipped document layout files are the "*Layout file, Document layout, Document layout (15-code)*" and "*Delivery note*" layout files. These layout files can be translated using language files.

   The "*Layout file, Document layout, Document layout (15-code)*" files are designed to support various types of sales documents and purchase documents, such as invoices, credit notes, quotes, delivery notes, purchases, supplier returns, and orders. When you open your Set of Books, the layout files will be printed in the language associated with that Set of Books. If you choose to change the language in osFinancials5/TurboCASH5, the layout files will be printed in the selected language.

   Furthermore, you have the flexibility to select from different layout files for printing or reprinting your sales documents and purchase documents. You can even create copies of existing layout files and customize their appearance and format to align with your business branding or meet specific requirements. This allows you to tailor the document layout files according to your preferences and ensure they reflect your desired visual style.

2. Reports menu: The Reports menu in osFinancials5/TurboCASH5 provides access to a comprehensive range of standard reports that are essential for managing various aspects of your business. These reports cover areas such as the ledger, debtors, creditors, stock items, documents, sales, sales analysis, purchases, purchase analysis, and more.

   All of these standard reports are stored in the following folder:

   ```
   " ...\plug_ins\reports\systemreports"
   ```

   The reports are organized into folders and subfolders within this directory to facilitate easy navigation and retrieval.

   To access these reports, you can simply go to the Reports menu on the Reports ribbon. From there, you can explore the different menu options and sub-menu options to locate the specific report you need. The Reports menu provides a convenient and centralised hub for accessing the wide range of reports available in osFinancials5, making it easier for you to generate the necessary financial and operational insights for your business.

3. User reports menu: The User reports menu in osFinancials5 provides a dedicated space for storing

and accessing custom reports that you create or customise according to your specific needs. These User reports are stored in the following folder:

"...\plug_ins\reports\userreports" ,

The User reports is separate from the standard reports folder.

To add your own custom reports, you should place them in the "*userreports*" folder. This folder serves as a repository for your personalised reports, allowing you to organize and manage them effectively.

Once your custom reports are added to the "*userreports*" folder, you can access them from the User reports menu on the Reports ribbon. This menu provides a convenient structure for accessing and printing your custom reports.

The User reports menu includes a range of pre-defined reports such, as Graphs per week or month for Custom reports, Debtors, Creditors, Tax listing, etc. Additionally, there are basic sample reports like Debtor listing and Creditor listing, which serve as tutorials to guide you in creating new reports using the Report designer in the osFinancials5/TurboCASH5 environment. These sample reports demonstrate various features, including parameters, lookups, and more.

The User reports menu empowers you to tailor your reporting capabilities to suit your unique business requirements, allowing you to create, access, and print custom reports seamlessly within the osFinancials5/TurboCASH5 system.

4. Ledger analyser: On the Reports ribbon in osFinancials5, you will find the Ledger analyser options, namely Ledger analyser 1, Ledger analyser 2, and T-Account viewer. These options provide a range of report types for generating and printing various financial statements and analyses.

   The available reports include the Trial balance, Income statement, Balance sheet, Standard column balances, This year vs last year, Budget vs actual, Budget listing and the transactions in the T-Account viewer. These reports offer valuable insights into your financial data and help you analyse the performance and financial position of your business.

   The reports within the Ledger analyser options are stored in the following folder:

   "...\plug_ins\reports\GENERAL\ledgerview"

   It's important to note that these reports are preset and should not be customised. They are designed to provide standard financial analyses and should be used as intended.

   Additionally, the reports generated through the Ledger analyser options can be exported and opened in spreadsheet applications, allowing for further analysis and customisation of the data.

   By utilising the Ledger analyser options, you can easily generate and access a variety of essential financial reports and analyses within osFinancials5/TurboCASH5, providing valuable insights into your

company's financial performance.

5. Spreadsheet reports menu: The Spreadsheet reports menu on the Reports ribbon in osFinancials5/TurboCASH5 provides access to reports that open in the integrated spreadsheet component. These reports are stored and organized in the following folder:

   "...\plug_ins\reports\excelreports" .

   Each report consists of a base.xlsx file, SQL files, and possibly parameter files. It's important to note that these spreadsheet reports cannot be edited using the Report designer tool. The available shipped spreadsheet reports include Creditors listing, Debtors listing, Transactions per period, General ledger - Budget, General ledger (Transaction totals), Sales analysis, and Stock movement.

The Report designer utilises different tables in osFinancials to generate reports. The document outlines the commonly used tables and their relationships to help you build reports effectively.

Overall, the Report designer in osFinancials provides a flexible and comprehensive solution for creating, customising, and managing reports to meet your specific reporting requirements.

Backup / Restore

The Backup / Restore process supports the options

Small backup

Small backup (books) - If you wish to e-mail the backup, you may select the "*Small backup (books)*" option to create a backup of your Set of Books database in a single file only (e.g. books.fdb - for the Firebird database). If this option is selected, no images or other files linked to your Set of Books will not be included in your backup. This will reduce the size of your backup file.

Uni dump

If your Set of Books in osFinancials5/TurboCASH5 is created as a Microsoft SQL Server (MSSQL) database type, the "uni dump" file created as an SQL file type can be used to restore the Set of Books.

The "*uni dump*" file contains SQL statements that represent the structure and data of the database. By executing these SQL statements, you can recreate the database and restore it to its previous state.

To restore a Set of Books from a "*uni dump*" file in osFinancials using MSSQL, you would typically follow these steps:

1. Ensure that you have a compatible version of MSSQL installed and running.
2. Create an empty database in MSSQL that will serve as the destination for the restored Set of Books.

3. Open the "*uni dump*" file in a text editor or an SQL client.
4. Execute the SQL statements from the "uni dump" file in the MSSQL database. This can be done using an SQL client or by running a script.
5. Once the SQL statements have been executed successfully, the Set of Books should be restored in the MSSQL database.

It's important to note that the specific steps and tools for restoring the database from a "*uni dump*" file may vary depending on your environment and the version of MSSQL you are using. It's recommended to consult the documentation or resources specific to your version of MSSQL for accurate instructions on restoring a database from an SQL file. Additionally, it's always a good practice to backup your database before performing any restoration to ensure data integrity.

Budgets

Budgets - New powerful way of processing budget figures in addition to the Budgets processed in the Setup → Accounts on the Setup ribbon,osFinancials5/TurboCASH5 introduces a new and powerful way of processing budget figures (Budgets on the Reports ribbon), enhancing the existing budget functionality available in the Setup → Accounts section of the Setup ribbon.

With this new feature, you can streamline the process of creating and managing budgets within osFinancials5/TurboCASH5. It offers a more dynamic and flexible approach to budgeting, allowing for easier entry and customisation of budget figures. The enhanced budgeting functionality enables you to:

1. Import budget or actual figures from the previous year: The user-friendly interface makes it easy to import and adjust budget figures as needed.. This saves time and ensures consistency across your budgeting process.
2. Allocate budget figures: Allocate enter and adjust budget figures to specific accounts, cost centres, or projects within your organization. This allows for granular budgeting and accurate tracking of expenses and revenues.
3. Adjust budget figures for seasonal fractionation or special events: osFinancials5/TurboCASH5 provides the functionality to enter budget figures, allowing businesses to account for seasonal fluctuations. This feature enables users to adjust and allocate budget amounts based on specific periods or seasons that may experience variations in financial activity. By accommodating seasonal fluctuations in budget planning, businesses can enhance their financial forecasting and decision-making processes. osFinancials allows users to enter budget figures specifically for special events, such as special sales. This feature enables businesses to allocate budget amounts specifically for these events, taking into account the anticipated increase or decrease in sales and expenses during that

time. By incorporating budget figures for special events, businesses can better track and analyse the financial impact of these occasions, aiding in strategic planning and performance evaluation.

4. Grid and Pivot tables - osFinancials5/TurboCASH5 provides several tools for analysing and viewing budget figures, including the Budget Grid, Pivot Table, and various report types.

    a) Budget grid: The Budget grid allows users to filter and organize budget figures entered on the Transactions tab. This feature provides flexibility in analysing specific budget categories, periods, or accounts, enabling users to focus on relevant information.

    b) Pivot table: osFinancials5/TurboCASH5 includes a built-in Pivot table feature that allows users to create dynamic and interactive reports based on budget figures. Pivot tables enable users to summarize, analyse, and manipulate budget data by various dimensions, such as accounts, periods, and categories. This feature provides a powerful tool for in-depth budget analysis and of your budget.

5. Budget listing reports Additionally, osFinancials5/TurboCASH5 offers the built-in pivot table functionality in the the Ledger analyser 1 or Ledger analyser 2 for the report types such as Trial balance, Income statement, Balance sheet, Standard column balances, to generate Budget listing reports for in-depth budget analysis and of your budget in a dynamic and interactive manner. These reports can be generated to print and review budget figures, providing a comprehensive view of the budget's impact on financial statements. These reports offer a structured format for analysing and comparing budgeted amounts across different accounts and periods. Furthermore, if you choose to export the reports to a spreadsheet, you can still leverage the pivot table functionality within the spreadsheet osFinancials5/TurboCASH5 to further analyse and manipulate the data. You may This provides you with the flexibility to use either osFinancials5/TurboCASH5 built-in pivot tables or the pivot table features of your preferred spreadsheet software, depending on your preferences and requirements. You can also export these reports to a spreadsheet program such as Microsoft Excel. This allows for further customization and analysis using the powerful tools and features available in spreadsheet applications.

6. Budget vs. Actual reports: In osFinancials5/TurboCASH5 you may also print and export Budget vs actual and report that compare actual financial data with budgeted figures, providing insights into variances and helping you evaluate performance against your budget targets. On the Reports → Ledger → Budget menu, you may print a budget performance report of the Budget vs realisation report to compare your budget figures to the actual figures for three selected periods.

With the pivot table functionality, users can customize the layout and presentation of the report data, apply filters and groupings, and perform calculations and aggregations. This flexibility enables users to gain deeper insights into the financial information and perform in-depth analysis.

By incorporating this new approach to budgeting, osFinancials empowers businesses to streamline their

budgeting processes, improve accuracy, and gain better visibility into their financial planning and control. Whether it's for annual budgeting, departmental budgets, or project-specific budgets, osFinancials5/TurboCASH5 provides a robust solution to effectively manage and monitor your organization's financial goals.

Calendar

osFinancials5/TurboCASH5 provides comprehensive support for a Calendar feature that includes agenda, contacts, and tasks functionality. With the Calendar feature, you can conveniently schedule and manage various events and appointments, set reminders within your Set of Books.

The Calendar feature in osFinancials5/TurboCASH5 allows you to schedule and manage events and appointments for different categories. These categories include debtor appointments (up to six different categories), creditor appointments, repeating invoices, process quotes and invoices for appointments, and process invoices for bulk time entries. By categorizing your appointments, you can easily distinguish and organize different types of activities within the Calendar.

With the Calendar, you can efficiently manage your schedule, track important appointments with debtors and creditors, set up repeating invoices for recurring transactions, handle process appointments for appointments, and manage bulk time invoices. This comprehensive functionality enables you to streamline your workflow and stay organized within your Set of Books.

Whether you need to keep track of client meetings, follow up on payment schedules, automate recurring invoices, or efficiently process appointments and bulk time invoices, the osFinancials Calendar feature provides a robust solution for managing your scheduling and task management needs.

Multi user Agenda plugin - Manual - Shop - Licence : Commercial : Once-off payment -

The Multi-user Agenda plugin in osFinancials5/TurboCASH5 enhances the functionality of the Calendar by providing support for multiple agendas. This allows you to have separate agendas for each employee, salesperson, or user in your organization. With this plugin, you can create invoices directly from each user's agenda with a simple click, streamlining the invoicing process.

Each agenda within the plugin has its own calendar and task list, providing a dedicated space for managing appointments and tasks. By adding agendas and linking them to specific users, you can easily view and track the appointments of other agendas within osFinancials5/TurboCASH5.

To utilise this plugin, you can create users in the Setup → Access control menu and associate each user with their respective agenda on the Access Control - Others tab. This ensures that each user has access to their own agenda and can manage it accordingly.

The Multi-user Agenda plugin supports ten main categories of events that can be managed for each user's agenda. These categories include:

1. *Appointment (general): Schedule appointments such as meetings with bank managers or lunch appointments.*
2. *Repeating invoices: Schedule and manage the processing of repeating invoices.*
3. *Debtors appointment: Schedule appointments with debtors or customers for specific purposes, such as discussing special arrangements or accounts.*
4. *Creditors appointment: Schedule appointments with creditors or suppliers for purposes like discussing orders or accounts.*
5. *Hours: Schedule and track the hours spent on projects or tasks for invoicing debtors or customers. This feature allows you to generate quotes for the hours and later convert them into invoices.*
6. *Bulk entry: Schedule and manage multiple appointments for salespersons and debtors (customers/clients). It enables the creation of quotes, smooth transition to invoices, and simplifies the workflow for tracking and billing services.*

The Multi-user Agenda plugin provides a comprehensive solution for managing multiple agendas, appointments, and invoicing within osFinancials5/TurboCASH5. It enhances productivity and organization by allowing each user to have their own agenda and streamlining the invoicing process directly from the agendas.

Projects

Projects - osFinancials5/TurboCASH5 provides support for projects, allowing you to effectively track and manage financial activities and expenses associated with specific projects within your organization.

With osFinancials' project functionality, you can create and define individual projects, assign relevant financial transactions and expenses to each project, and track the financial performance and progress of each one.

This feature enables you to accurately allocate costs, track project-related expenses, and monitor the profitability of each project or job. You can easily generate reports and statements that provide detailed insights into the financial status, budget utilization, and overall performance of your projects or jobs.

By utilizing osFinancials5/TurboCASH5 project capabilities, you can make informed decisions, effectively manage resources, and ensure that your projects are on track financially. This functionality is particularly beneficial for organizations that engage in project-based work, such as construction companies, consulting firms, or any business that needs to track and manage financial activities at a project level.

With osFinancials5/TurboCASH5' support for projects or job costing, you can enhance your financial management processes and gain better visibility into the financial aspects of your organization's projects.

Cost centres

Cost centres - osFinancials5/TurboCASH5 provides support for up to two cost centre groups, allowing you to effectively organize and analyse your financial data based on cost centres within your organization.

With the capability to define and assign cost centre groups in osFinancials5/TurboCASH5, you can categorize your expenses, revenues, and other financial transactions according to different cost centres. This enables you to track and analyse the financial performance of specific departments, projects, locations, or any other divisions within your organization.

By assigning transactions to appropriate cost centres, you can generate reports and statements that provide detailed insights into the financial activities and performance of each cost centre group. This information can be valuable for budgeting, decision-making, and evaluating the profitability or efficiency of different areas within your organization.

Whether you need to allocate costs, track expenses, or analyse financial data across multiple cost centres, osFinancials5/TurboCASH5 support for up to two cost centre groups provides you with the flexibility and capability to effectively manage and analyse your organization's financial information.

Document E-mail Pro plugin

The Document E-mail Pro plugin in osFinancials5/TurboCASH5 allows you to send documents by email directly from the program. This plugin is included in the osFinancials5 Business class subscription or can be purchased separately with a once-off licence.

With the Document Email Pro plugin, you can easily send documents such as invoices, quotes, credit notes, and order lists to customers or wholesalers. Different email templates can be created to match the specific document being sent. For example, the email text sent to a customer with an invoice will differ from the text sent to a wholesaler with an order list.

The Document E-mail Pro plugin can also be used in conjunction with other plugins like remittance, subscriptions and newsletter.

When sending documents as email attachments, you have the option to choose different file formats, including PDF and UBL 2.1. Here's an explanation of each format:

1. PDF (Portable Document Format): PDF is a widely used file format that preserves the formatting, fonts, and layout of a document. It ensures that the recipient sees the document exactly as intended, regardless of their software or operating system. PDF files are typically read-only, allowing recipients to view and print the document but not easily edit its content. Sending documents as PDF attachments guarantees compatibility and easy viewing for recipients.
2. UBL 2.1 (Universal Business Language): UBL is an XML-based standard for exchanging business

documents electronically. UBL 2.1 is a specific version of the UBL standard. UBL files follow a predefined structure and contain structured information about various business documents such as invoices, purchase orders, and payment instructions. UBL files are commonly used in business-to-business (B2B) transactions to facilitate automated processing and interoperability between different software systems. By sending documents as UBL 2.1 attachments, you provide recipients with machine-readable data that can be easily processed by their business systems.

When emailing documents, you can attach both a PDF file for human-readable viewing and a UBL 2.1 file for machine-readable data. This offers flexibility to the recipient in interacting with the information based on their specific needs and systems.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Getting started

osFinancials5/TurboCASH5 Business Class

Saturday, 24 May 2025- 01:50:47

---

osFinancials5/TurboCASH5 is a very powerful accounting system with a wide range of features and options.

English Online help -

Afrikaans Online help -

To get started with osFinancials5/TurboCASH5, I understand that I need to first install the software and then open the HANDYMAN Set of Books associated with the default English language.

If I am a registered user of osFinancials5/TurboCASH5, my licence will still be valid for this release. However, if I am a new or unregistered user, I can register for an osFinancials5 subscription / TurboCASH5 subscription, purchase a licence for the desired plugins, or participate in the shared forum to find solutions and participate in discussions.

I also understand that if I am using an unregistered version of osFinancials5/TurboCASH5, there is a limit of 500 transactions or documents. Once this limit is reached, I will need to register and buy a licence to continue processing transactions and documents.

If I already have a Set of Books from osFinancials4, osFinancials5, TurboCASH4, TurboCASH5, or TurboCASH5-2, I can copy it to the "*books*" directory of my osFinancials5 installation / TurboCASH5 installation using File Explorer. Alternatively, I can restore a Set of Books from a valid backup file in osFinancials5/TurboCASH5.

For a new Set of Books, I can download and customize one of the 87 available databases to meet my requirements. If my language or country is not available, I can select any of the available Firebird Sets of Books and linked languages as a free download.

Finally, there are tutorial Sets of Books available in the "*bin/Tutorials*" directory to help me get started with osFinancials5/TurboCASH5.

Welcome to osFinancials5/TurboCASH5 Business class. osFinancials is very extensive accounting system. osFinancials5/TurboCASH5 can cater for various industry specific solutions. A wide range of plugins is available to expand the power and functionality.

osFinancials5/TurboCASH5 supports 79 different languages and tax regimes languages liked to 87 Sets of Books (databases) which may be downloaded and customised to meet your requirements.

Install osFinancials5/TurboCASH5

After installing osFinancials5, / installing TurboCASH5, you may open the HANDYMAN Set of Books associated with the default "*English*" language.

Register osFinancials5/TurboCASH5

Registered users of osFinancials5/TurboCASH5

Registered users of osFinancials5/TurboCASH5 licences will still be valid for this release.

New and unregistered users

New and unregistered users may register osFinancials for:

1. osFinancials5 subscription / TurboCASH5 subscription - The annual subscription includes the bankimport and email document email pro plugins.
2. Webshop - To use any of the powerful plugins, you need to purchase a licence for most of the Plugins. Before you can Register plugins, you first need to Register osFinancials5 / Register TurboCASH5.

3. Forum - On the shared forum, you may find topics (posts), post questions or issues, find solutions and participate in any discussions.

Every time an unregistered version of osFinancials5/TurboCASH5 is started, the following confirmation message will be displayed:

> This software is limited to 500 transactions or 500 documents. Please register and buy a licence for osFinancials5!
> This copy of osFinancials5 is not registered! Do you wish to register it now?

Unregistered versions will allow you to process up to 500 transactions and /or documents. Once this limit is reached, osFinancials5/TurboCASH5 will not allow any processing of transactions, in batches and/or documents.

Once you have registered osFinancials5/TurboCASH5, you will receive an unlocking code and will be able to process further transactions and or documents.

Open a Set of Books in which 500 transactions and or documents have been processed:

> osFinancials5 the limit of 500 transactions or 500 document is reached! Please register and buy a licence.
> Once you have registered osFinancials5, you will receive an unlocking code and will be able to process further transactions and or documents.

Add / Create Sets of Books

Already have Set of Books

osFinancials4 (4.0.0.1093), osFinancials5, TurboCASH4, TurboCASH5 (4.0.0.969) and TurboCASH5-2 Sets of Books do not need to be converted to osFinancials5.

You may copy the Sets of Books using File Explorer to the "*books*" directory of your osFinancials5 installation.

You may also Restore a Set of Books from a valid Backup file in osFinancials5/TurboCASH5.

All available Sets of Books is set to Firebird Version 2.1 - ODS 11.1 database version.

Older databases Sets of Books of exiting users may use mostly Firebird Version 1.5 - ODS 10.1 database version.

These Sets of Books is may be used in osFinancials5/TurboCASH5.

New Set of Books

osFinancials5/TurboCASH5 supports 79 different languages and counties / tax regimes languages liked to 87 Sets of Books (databases) which may be downloaded and customised to meet your requirements.

If the set of books for your language and or country, is not available in the books directory, you may select any of the available Firebird Sets of Books and linked languages available as a free download.

Options to configure your Set of Books for VAT/GST/Sales Tax

VAT/GST/Sales Tax Registration / Cancellation of Registration options:

1. New Registered Vendor in osFinancials: If you're new to osFinancials5/TurboCASH5 and are a registered VAT/GST/Sales Tax vendor, this option is for you. You'll follow the steps to set up your VAT/GST/Sales Tax accounts, configure tax codes and percentages, and customize document layouts to meet your tax jurisdiction's requirements. This ensures accurate tax calculations and proper tax invoicing in your transactions.
2. New User in osFinancials without Tax Registration: If you're new to osFinancials5/TurboCASH5 and not a registered VAT/GST/Sales Tax vendor, this choice is appropriate. You'll need to adjust the system's default settings for tax accounts to reflect your non-registered status. This includes disabling or removing VAT/GST/Sales Tax accounts, configuring layouts to reflect non-taxable transactions, and updating document names if necessary. This option ensures accurate transaction documentation without tax-related elements.
3. Existing User Opting for Tax Deregistration: If you're an existing osFinancials5/TurboCASH5 user who has decided to cancel your VAT/GST/Sales Tax registration, this is your selection. Following this route involves steps to update your tax accounts' status to *'Disabled*,' and possibly remove them if unposted transactions are absent. Additionally, you need to process all tax-related transactions until the date of cancellation of registration, ensuring accurate records. After the date of deregistration, it's crucial to adjust your system to process transactions without Tax (VAT/GST/Sales tax) to reflect the updated tax-related changes accurately. Managing this process diligently will help maintain the integrity of your financial records.

Open Tutorials

Tutorial Sets of Books, will be installed in the "*bin / Tutorials*" directory. you need to click on the Browse icon and select the Sets of Books tutorials.

Hands-on Tutorials

osFinancials5 installation provides tutorial Sets of Books in both English and Afrikaans. These tutorial books

allow users to explore different settings, transactions, and reports within the software. Here are the available tutorial sets:

Accounting Made Easy

English tutorials (using separate receipt and payments journals for banking / cash transactions)



The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\ENGLISH\" folder:

- *HANDYMAN (No transactions)*
- *HANDYMAN-A (Unposted transactions)*
- *HANDYMAN-B (Posted transactions)*

Accounting Made Easy - Bank Import

English tutorials (using the BankImport plugin for banking / cash transactions)

The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\BANK-IMPORT\" folder:

- *HANDY-BANK (No transactions).*
- *HANDY-BANK-A (Unposted transactions)*
- *HANDY-BANK-B (Posted transactions).*
- *HANDY-BANK-UNPOSTED-BANK-STATEMENT – Posted transactions, excluding bank / cash transactions. Bank statement needs to be imported from the "…\bin\Tutorials\BANK-*

Rekeningkunde Met Gemak (Afrikaans)

Afrikaanse handleidings (gebruik aparte ontvangste- en betalingsjoernale vir bank- / kontanttransaksies)

Die volgende Stel Boeke gebaseer op die Afrikaanse handleidings, is in die "…\bin\Tutorials\AFRIKAANS\"-lêergids geïnstalleer:

- *NUTSMAN (Geen transaksies).*
- *NUTSMAN-A (Ongeposteerde transaksies)*
- *NUTSMAN-B (Geposteerde transaksies).*

IMPORT\BANK-STATEMENTS"
folder.

To open the tutorial Sets of Books, installed in the "*bin / Tutorials*" directory, you need to click on the Open icon on the Start ribbon. On the "*Set of Books*" screen, click on the Browse icon and select the desired tutorial Set of Books that you wish to follow.

Additionally, there are other tutorial folders available with relevant files for import into batches. The following folders contains files which may be imported into batches:

- *EXPORTED-BATCH-Delimited-File – Exported batch transactions using the "Write delimited file" option and may be imported into a batch using the "Delimited file import" option (F9:Process icon) on batches.*
- *EXPORTED-BATCH-Spreadsheets – Exported batch transactions in the *.xlsx (Excel 2007-365) file format. These transaction files may be opened in the Spreadsheet import icon on batches, and imported into a selected batch.*

These tutorials are designed to guide users, regardless of their accounting experience, through the basics of accounting and demonstrate how to effectively use osFinancials5/TurboCASH5 for managing business finances. The tutorials cover various aspects, including osFinancials5/TurboCASH5 features, chart of accounts setup, transaction creation, processing sales and purchase documents, and report generation. They also serve as a reference guide to osFinancials5/TurboCASH5.

By the end of these tutorials, users will have gained a solid understanding of the accounting process and will be able to confidently utilize osFinancials5/TurboCASH5 for managing their business finances.

OTHER TUTORIALS

Additionally, there are other tutorials for exploring the activation, processing, and reporting of Cost centres and Projects within osFinancials5/TurboCASH5.

COST-CENTRES

Tutorials / examples to explore the activation, processing and reporting of Cost centres in osFinancials5/TurboCASH5. See - Cost centres in this Help file.

The following Set of Books based on this tutorial, is installed in the "*...\bin\Tutorials\COST-CENTRES*" folder:

- COST-CENTRES-A (transactions and documents not posted to the ledger)
- COST-CENTRES-B (transactions and documents posted to the ledger).

PROJECTS

Tutorials / examples to explore the activation, processing and reporting of Projects in osFinancials5/TurboCASH5. See - Projects in this Help file.

The following Set of Books based on this tutorial, is installed in the "*...\bin\Tutorials\PROJECTS*" folder:

- PROJECTS-A (transactions and documents not posted to the ledger)
- PROJECTS-B (transactions and documents posted to the ledger).

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

System requirements

The system requirements for osFinancials5/TurboCASH5 are as follows:

1. Operating System: A 32-bit or 64-bit Microsoft Windows operating system is required. Supported versions include Windows 98, Windows 2000, Windows ME, Windows NT, Windows XP, Windows Vista, Windows 7, Windows 8, Windows 10, or Windows 11.
2. RAM: For a single-user setup, at least 256 MB of RAM is required. For a multi-user setup, a minimum of 512 MB of RAM is recommended.
3. Hard Disk Space: Approximately 1 GB of available hard disk space is needed to install and run osFinancials5/TurboCASH5.
4. USB Port and Drives: A USB port is required, and available USB drives are needed to save and store backups.
5. Screen Resolution: An SVGA/LCD/LED screen with a resolution of 1440 x 900 or higher is recommended.

Screen Resolution Adjustments: If your device has a screen resolution of 1366 x 768, you may need to adjust your Screen resolution when working in forms or screens such as Documents, Debtors, Creditors, Stock, etc. using the following options:

- *Collapse the ribbons (automatically hide the ribbons)*
- *Set the "Style values for ribbon" to Tablet mode.*

This adjustment ensures proper display and functionality.

6. System Number Format: Configuring the System number format setting to print reports like "*Budget*

vs actual" and "*This year vs last year*".

7. Spreadsheet Software: Microsoft Excel or other spreadsheet programs such as LibreOffice, OpenOffice or UltraOffice should be installed to save reports or export data from the Ledger analyser and other options.

8. Recommended Device: While osFinancials5/TurboCASH5 may run on older devices, it is recommended to use a better device for more secure and efficient operation. Modern devices are significantly more powerful than older ones, making them more suitable for running osFinancials smoothly.

Please note that the information provided here is specific to osFinancials5/TurboCASH5. Always refer to the official documentation and system requirements provided by the osFinancials team to ensure accurate and up-to-date information. Additionally, consider using the most recent and supported operating system and hardware for optimal performance and security.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's CHM Help File Creation Features

System settings - Screen resolution

The minimum recommended screen resolution is 1440 x 900 screen or higher).

On devices with a 1366 x 768 screen resolution, you may need to:

- Collapse the ribbons (automatically hide the ribbons) when working in forms or screens such as Documents, Debtors, Creditors, Stock, etc.
- Set the theme to tablet mode - Set the "*Style values for ribbon*" to "*Style=4*" in the Colors.ini file in your theme folder to 4 =2016Tablet

Collapse (hide) ribbons

Double click on a ribbon tab, or click the "*Collapse the ribbon*" option (on the bottom right of the ribbon bar).



If the screens of debtors, creditors, stock items or documents is not displayed correctly, you may need to go to Tools → Close active forms (Setup ribbon) and relaunch the screens when the ribbon is collapsed.

Pin (show) ribbons



Tablet mode setting

To set the ribbon to the Tablet mode:

1. Open your selected theme folder in "*... / bin / Themes / Material*" folder (as per this example).
2. Open the "*colors.ini*" file.
3. Change the "*Style values for ribbon*" by replacing "style=x" value with "*style=4*" (where 4 =2016Tablet).



4. Save the "colors.ini" file.

5. Exit osFinancials5/TurboCASH5 and RestartosFinancials5/TurboCASH5 .

6. When osFinancials is restarted, the ribbons will display as follows (Default tab) as per this example).



Created with the Standard Edition of HelpNDoc: Full-featured Help generator

System settings - Number format

You may need to set the number format of your operating system to print some reports.

When printing the "*Budget vs actual*" and "*This year vs last year*" reports, you may encounter the following error message:

"Type conversion error 'Val':Expression TRpExpression46"

Batch processing options - Create receipts (Receipt batches) option - If your system's digit separator is set to a comma and your system's Decimal symbol is set to a period, do not enter a comma as the decimal separator in the "Amount" field.

For example, if an amount of 1150,00 is entered using a comma as a digit separator, it will print and generate the transaction amount as 115,000.00 instead of 1,150.00.

The "*Customize Format - Numbers*" of your Windows operating system number format needs to be set as follows:

- Decimal symbol - set to period (.)
- Digit grouping symbol - set to comma (,) (If Digit grouping symbol is set to blank it does not print but produces an error.

The Region and Language settings of your operating system should launch if you click on the Setup → Company info - Options - Set Windows date format/style button on the Setup ribbon.

This is a global setting for all Sets of Books on your operating system.

To change the number format of your operating system:

1. In any active (opened) Set of Books, select Setup → System parameters (Setup ribbon).



2. On the "*System Parameters*" click on the DateTime settings button.



3. On the Formats tab, click on the Additional settings ... button.



4. On the Numbers tab, the default settings (as per new installaion of Windows or on some new devices), the settings that need to be changed is as follows:

    - Decimal symbol set to period (.)
    - Digit grouping symbol set to comma (,)

> *If Digit grouping symbol is set to blank; and when you click on the Print button of the "Budget vs actual" and "This year vs last year" reports; it does not print but produces same error; i.e.*
>
> "Type conversion error 'Val':Expression TrpExpression46"

5. After changing the number formats, the "*Example*" on the Numbers tab of the "*Customize Format*" screen, should display as follows:



6. Click on the Apply and OK buttons of the "*Customize Format*" - Numbers tab, as well as the "*Region*" - Formats screen.

7. You may need to exit (close) osFinancials5/TurboCASH5 for these changes to be updated when generating and printing reports.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

System settings - Default app for csv file types

Open saved Export.txt files in your system's app (program) associated with the CSV (Comma Separated Values) file type

The Export button on the following features will open the saved "*Export.txt*" text file in your system's app (program) associated with the CSV (Comma Separated Values) file type:

- Ledger analyser 1 - Trial balance, Income statement, Balance sheet, Standard column balances (column view of the Trial balance, Income statement and Balance sheet in one report), Budget vs actual, This year vs last year as well as six (6) report types for Column balances. which cannot be printed, but exported to a spreadsheet only.
- T-Account viewer - In addition to launching the T-Account viewer from the Ledger analyser 1 / Ledger analyser 2, on the Reports ribbon; the T-Account viewer may also be accessed on the following options on the Default ribbon:
    - Search - Investigator - Account or Batch type searched items.
    - Debtors - Transactions tab / Creditors - Transactions tab - Click on the Show transactions button.
- Open item link - Totals tab and Transactions tab or a selected open item account.
- Debtors - Export button on the Debtors list screen - You may enter the File name with a *.txt file type extension.
- Creditors - Export button on the Creditors list screen - You may enter the File name with a *.txt file type extension.
- Documents - Export button on the Documents list screen - This will launch the "Save As" screen with the default Export.csv file type.

If you click on Export buttons on various screens, the "*Save As*" screen will be launched to save a comma separated value text file, with the default "*Export.txt*" file name.



Once you have saved the "*Export.txt*" file with your own file name, the Exported file will, by default open in your system's default app associated with csv files.



Open saved Export.txt files in another app (program) for CSV (Comma Separated Values) file type

If you wish to open saved Export.txt files in another app (program) for CSV (Comma Separated Values) file type, than Microsoft Excel, you may use the spreadsheet components of other apps (programs) e.g. LibreOffice, OpenOffice or UltraOffice installed on your system.

To do this, select the saved Export.txt file and right click on LibreOffice Calc.



To open a Export.txt file in LibreOffice, it may, by default, open the saved Export.txt file in LibreOffice Writer (Word processing) component instead of the Spreadsheet component LibreOffice Calc.

To add LibreOffice Calc to the Open with > context menu, you need to select Choose another app on the context menu.

Go to Look for another app on this PC. On the "*Open with...*" screen, browse to where your preferred app is installed. In this example, LibreOffice install folder is selected.

Go to the program folder and select scalc.exe.

Click Open button and the app will be added to the Open with ... context menu of your system's File Explorer.





Opening a saved Export.txt file in LibreOffice Calc will display the "Text Import - {Export.txt} or [your file name.txt].

You may need to check and configure the options for the Comma Separated Values file.



When you click OK, the file will be opened in a spreadsheet.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Unicode settings in osFinanacials5/TurboCASH5

Install osFinancials5/TurboCASH5 - Added Unicode Setting

We've adjusted the installation script to include a new Unicode setting for Unicode databases. This setting allows you to control the nounicode parameter in the osf.ini file during installation. Additionally, we've added options to update or retain the existing osf.ini file based on your Unicode preferences for your Unicode databases. This allows you to set the Unicode settings via the installation process without editing

the osf.ini file in the osFinancials5 installation's root directory.

If you are using TurboCASH5, you may set the Unicode settings via the installation process without editing the tcash.ini file in the TurboCASH5 installation's root directory.

Unicode Settings in osFinancials5/TurboCASH5

In osFinancials5, the osf.ini (or in TurboCASH the tcash.ini file) includes the setting nounicode=FALSE or nounicode=TRUE to control Unicode settings. Here's what these settings mean:

- Enable Unicode setting: nounicode=FALSE: This setting enables Unicode support. When Unicode is enabled, the software can handle a wide range of characters from different languages, ensuring proper display and processing of multilingual text.
- Disable Unicode setting: nounicode=TRUE: This setting disables Unicode support. When Unicode is disabled, the software may not correctly handle special characters or characters from languages other than the default one.

Enabling Unicode (nounicode=FALSE) is generally recommended if you need to work with multiple languages or special characters to ensure data integrity and proper functionality.

Unicode settings / System locale and Keyboard layout

When would that be necessary to use the nounicode=TRUE setting?

Disabling Unicode support with nounicode=TRUE may be necessary or beneficial in certain specific scenarios. Here are a few examples:

- Legacy Systems: If you are working with older, legacy systems or applications that do not support Unicode, disabling Unicode might be necessary to ensure compatibility. Some older software and databases were designed to work with specific code pages and might not handle Unicode characters correctly.
- Performance Considerations: In some cases, using non-Unicode (single-byte or multi-byte character encodings) can be more efficient in terms of storage and performance, particularly if all the text data falls within a single codepage or character set. Disabling Unicode could reduce the storage size and improve performance for certain operations.
- Specific Language Use: If you are working exclusively with a language or character set that is fully supported by the non-Unicode codepage, and there is no need to handle characters from multiple languages, you might choose to disable Unicode. This can simplify the configuration and maintenance

of osFinancials5/TurboCASH5.

- Data Migration and Conversion: When migrating data from a non-Unicode system to a Unicode system, or vice versa, it might be necessary to temporarily disable Unicode support to ensure data integrity during the conversion process.
- Software Integration: If osFinancials5/TurboCASH5 needs to integrate with other software or systems that do not support Unicode, it might be necessary to disable Unicode to ensure proper data exchange and compatibility.

However, keep in mind that using nounicode=TRUE can lead to limitations in handling special characters and multilingual text. It's generally recommended to use Unicode (nounicode=FALSE) for better flexibility and accuracy in a modern, globalised context.

Ultimately, the decision to enable or disable Unicode support should be based on your specific requirements and the systems you are working with.

How does Unicode settings, System locale (language settings) and keyboard layout relate to these special characters?

Great question! The relationship between Unicode settings, system locale (language settings), and keyboard layout is crucial for typing and displaying special characters correctly. Here's how they interact:

- Unicode is a universal character encoding standard that assigns a unique code to every character, regardless of the platform, program, or language. It ensures that special characters like ê, ë, and Å are represented consistently across different systems and devices.
- System Locale (Language Settings) - System locale determines the language and regional settings for your operating system. It affects the default language for system messages, the date and time format, currency, and other regional preferences.

  When you set your system locale to a specific language, it can also influence the availability and behaviour of certain characters and symbols in applications and text input.

- Keyboard layout defines the arrangement of keys on your keyboard and determines which characters appear when you press specific keys. Different languages and regions have their own keyboard layouts that include characters specific to those languages.

  For example, if your keyboard layout is set to "*US*," you might not see characters like ê or ë directly on the keyboard. However, if you switch to a layout like "*Afrikaans*", "*French*" or "*Dutch*," these characters will be more accessible.

Many operating systems allow you to switch between different keyboard layouts, making it easier to type special characters. You can usually switch layouts via a keyboard shortcut or through the language settings in your system preferences.

- Putting It All Together
    - Unicode ensures that the characters you type are represented correctly in text across different systems.
    - System locale influences how these characters are displayed and interpreted based on your regional settings.
    - Keyboard layout determines the ease of typing these characters by providing access to language-specific keys and shortcuts.

By configuring these settings appropriately, you can seamlessly type and display special characters in any language you need.

If you ever run into issues with special characters not displaying correctly, checking these settings can often help resolve the problem!

In osFinancials5/TurboCASH5 can the Unicode settings have implications and differences in Firebird database types and MSSQL database types?

Unicode settings can have implications and differences when using accounting software like osFinancials5/TurboCASH5 with Firebird and MSSQL databases. Here are some key points to consider:

Firebird Databases (See - Character Sets and Unicode in Firebird)

- Character Sets: Firebird supports various character sets and collations. Properly configuring these settings is crucial to ensure that special characters like *'ê', 'ë'*, and *'Å'* are stored and retrieved correctly.
- Unicode Support: Firebird 2.1 and later versions support Unicode, which allows for the storage of characters from multiple languages. Ensuring that your database is set up to use Unicode can help avoid issues with character encoding. All Sets of Books for the Firebird database type is upgraded from Firebird 1.5 to Firebird 2.1. The updated Sets of Books based on Firebird 2.1 is available in the following options:
    - TurboCASH5 in the bin/Repository folder.
    - osFinancials5.1 - The similar Firebird database type Sets of Books, including Sets of Books for

the Dutch markets, is available as a free download from the Online option in the Creation Wizard (Let osFinancials / TurboCASH help you to create your own Set of Books? from the osFinancials website.

Existing users of osFinancials5/TurboCASH5 running Firebird 1.5 Sets of Books, may need to upgrade their databases from Firebird 1.5 to Firebird 2.1.

MSSQL Databases

- Collation: MSSQL databases use collations to define rules for sorting and comparing characters. Choosing the right collation is important for correctly handling special characters.
- Unicode Support: MSSQL also supports Unicode through the use of `nvarchar` and `nchar` data types, which can store any Unicode character. Ensuring that your database columns are set to use these data types can help maintain character integrity.

Implications

- Data Consistency: Properly configuring Unicode settings ensures that special characters are consistently stored and displayed across different systems and applications.
- Compatibility: Ensuring that both the database and the application are set up to use Unicode can prevent issues with character encoding mismatches, which can lead to data corruption or display issues.
- Performance: While Unicode support is essential for handling multilingual data, it can also have performance implications. Proper indexing and optimisation are necessary to maintain performance levels.

By carefully configuring Unicode settings and ensuring that both your database and application are set up to handle Unicode characters, you can avoid many common issues related to special characters in accounting software.

Codepage settings in osFinancials5/TurboCASH5

Codepage settings in osFiosFinancials5/TurboCASH5 set in the Tools → Customise language option (Setup ribbon) for your selected language.

osFinancials and TurboCASH allow you to customise language settings, including codepage settings, through the Tools → Customise language option (Setup ribbon). This is essential for ensuring that the software correctly displays and processes text in your chosen language, especially for languages with special characters or different writing systems.

By adjusting these settings, you can enhance your user experience and make sure that all financial data and reports are presented accurately, regardless of the language or character set you are using.

Microsoft Windows Codepages

- 874 Thai
- 932 Japanese
- 936 Simplified Chinese
- 949 Korean
- 950 Traditional Chinese
- 1250 Central European
- 1251 Cyrillic
- 1252 Western European
- 1253 Greek
- 1254 Turkish
- 1255 Hebrew
- 1256 Arabic
- 1257 Baltic
- 1258 Vietnamese

Microsoft Windows Codepages are used to map characters to bytes for various languages, ensuring proper display and input of text. Each codepage is designed to handle specific scripts or groups of languages.

For example:

- 1250 Central European includes languages like Polish, Czech, and Hungarian.
- 1251 Cyrillic is used for languages like Russian, Bulgarian, and Serbian.
- 1252 Western European covers languages like English, French, and German.
- 1253 Greek is specifically for the Greek language.
- 1255 Hebrew and 1256 Arabic handle those respective languages and their unique writing systems.

These codepages are essential for ensuring that text is correctly encoded and displayed, especially in applications like accounting software, where accurate representation of financial data in multiple languages is critical.

If you're setting up osFinancials or TurboCASH, choosing the correct codepage for your specific language ensures that all characters are displayed correctly, avoiding any data corruption or display issues.

In osFinancials accounting software supports LTR languages and RTL languages ?

Yes, osFinancials accounting software supports both Left-to-Right (LTR) and Right-to-Left (RTL) languages! This makes it versatile and suitable for users in different regions and linguistic backgrounds.

For TurboCASH5, this RTL setting is not included in the tcash.ini file. However it is included in the osf.ini file.

```
;BIDIMODE=RTL
```

For Left to Right to Left language and interface support, the ;BIDIMODE=RTL may need to be uncommented.

Tests Unicode Settings

TESTS nounicode=TRUE

MSSQL Support - Can open Sets of Books for the MSSQL Database type.

TESTS nounicode=FALSE

MSSQL Support - Can open Sets of Books for the MSSQL Database type. This seems to display the osFinancials5/TurboCASH5 interface and reports correctly.

Prints correctly om all screens and reports tested, including currencies.

Entering an ê (Alt+0136) or ë (Alt+0137) in for example Company name (Registered company names may include these characters, including existing users) does not replicate an error:

NOTE - If data is entered when nounicode=TRUE , the reports do not print correctly - you may have to reenter the data on the forms.

Setup -> Company information

If your data in the forms was entered when nounicode=TRUE and you change the unicode settings to nounicode=FALSE you may need to reenter the special characters, for example; ê (Alt+0136) or ë (Alt+0137). This resolves the display issues in the osFinancials5/TurboCASH5 interface, reports and layout files.

REMEMBER to close and relaunch osFinancials5/TurboCASH5 you have edited the setting in the osf.ini or tcash.ini files.

Alternatively you may rerun the osfiancials5/TurboCASH5 installation.

Company info correct display

Company info and titlebar



Company info and report Currencies



Setup -> Countries

By default, the land Islands will display the character irrespective of your Unicode settings if the nounicode=FALSE (for Firebird database type Set of Books) or nounicode=TRUE (for MSSQL database type Set of Books). Åland does not seem to be included in the countries.xml file in the osfinancials5/TurboCASH5 root installation folder.



Typing special characters can vary depending on your keyboard and operating system. Here are a few methods for typing the Å character in Windows:

1. Using Alt Code:
    - Hold down the `Alt` key.
    - While holding down `Alt`, type `0197` on the numeric keypad.
2. Keyboard Shortcuts:
    - Ensure you're using a keyboard layout that includes Scandinavian characters (like Swedish or Finnish).
    - Press `Shift` + `Ctrl` + `;` and then A.



The Åland Islands - This fascinating archipelago belongs to Finland but has a large degree of autonomy. The unique letter “Å” is a telltale sign of the Scandinavian influence.

Errors Firebird database type - nounicode=TRUE

If the Unicode setting is set to nounicode=TRUE and data is entered in forms and screens, it will cause

display errors in the forms, reports and layout files.

Some screenshots of incorrect data display.



Error in documents, if no items are selected titlebar captions company name displayed incorrectly on all confirmation, warning, error messages across the entire program..



Accounts



Stock



Enter correctly - when saving the record, the characters displays incorrectly on the stock grid.



OLDER UNICODE TESTS

Firebird databases nounicode=TRUE

Retested:

All reports seems to print fine and neat.

Display errors when data is entered in some screens and reports

If the nounicode=TRUE setting is set to true - it also produces incorrect display of data in some screens and reports.

Setup Countries - Displays incorrect character " land Islands "

Replicated in osF5.1.100 since osFinancials5.1.0.16 displayed incorrectly, since unicode was introduced.

If the default setting " nounicode=true " is in the osf.ini file, this replicate the error not displaying correctly.

If the default unicode setting in the osf.ini file is changed to " ;nounicode=true " is uncommented or set to false nounicode=false in the osf.ini file, these settings does not change the display of " land Islands ".

land Islands Displays incorrect character irrespective of unicode settings

Setup → Countries



Last version was displaying correctly = Build 453

Currencies

Replicated in osF5.1.100 since osFinancials5.1.0.16 displayed incorrectly, since unicode was introduced.

To use Currencies in osFinancials5 you need to change the osf.ini file

Only works correctly if nounicode=FALSE in the osf.ini file.

If the default setting nounicode=TRUE in the osf.ini file, this replicate the error not displaying correctly.

Default setting nounicode=TRUE in the osf.ini file, this replicate the error not displaying correctly

Euro sign - € - (Alt+0128) Initially it displays correctly, but when the record is saved, it displays a | pipe symbol in the Currency screen.

When printing a report the Euro sign - € id incorrectly displayed as character.



See - Alt Code Shortcuts for Currency Symbols - List of Alt+Numeric keys for generating theCurrencies in the various countries. Example Works if the Alt+0165 for Yen, etc.

To display currencies correctly in Currencies setup and print the Currency report correctly in you need to change the osf.ini file.

nounicode=TRUE setting set it to false nounicode=FALSE in the osf.ini file

After changing it back to the default setting nounicode=FALSE in the osf.ini file, The error is not replicated and is displayed correctly correctly in Setup → Currencies and Reports → Currencies report or on document layout files.



Layout file incorrect

If the default setting nounicode=TRUE in the osf.ini file, this replicate the error not displaying currency symbol correctly.



Layout file correct

Only works correctly if nounicode=TRUE is set to false nounicode=FALSE in the osf.ini file.



Was correct in osFinancials5 (Build 453)

Plugins Multimedia

Character input ë (Alt+137) displays correctly for added multimedia files in File explorer in the Windows system. When file is added in the Plugins, e.g. Multimedia, the file names displays incorrect characters in the fields loaded in the when nounicode=TRUE



Firebird Database - nounicode=FALSE

If the nounicode=FALSE it does not replicate the errors found in when the nounicode=TRUE

MSSQL databases cannot open in the MSSQL Server. To open and work in MSSQL databases, the Unicode setting must be set to nounicode=TRUE

In Firebird databases the Unicode setting must be set to nounicode=FALSE

Retested:

- Reports : All reports and document layout files including spreadsheet reports print correctly and looks neat.
- Screens : Currencies is fixed but not Countries
- Plugins : Displays correctly

Character input ë (Alt+137) displays correctly for added multimedia files in File explorer in the Windows system. When file is added in the Plugins, e.g. Multimedia, the file names displays correct characters in the fields loaded in the when nounicode=FALSE



Unicode -Context menu on forms

Unicode context menu options of forms

In osFinancials5/TurboCASH5, the context menu on most fields in forms, such as Debtors, Creditors, Stock on the Default ribbon and Accounts, Groups on the Setup menu, include the following context menu items related to Unicode (if Unicode is enabled).



These context menu items in osFinancials5/TurboCASH5, specifically related to Unicode, provide advanced text formatting and control options when working with characters beyond the standard ASCII set.

Explanation of Context Menu Items

Let's break down what each option means and its function:

1. Right to Left Reading Order
    - Function: This option controls the reading direction of the text. When enabled, the text in the field will be displayed and processed from right to left, which is essential for languages like Arabic and Hebrew.
2. Show Unicode Control Characters
    - Function: This option displays invisible Unicode control characters that might be present in the text. These characters can affect text formatting and rendering, so visualizing them can help troubleshoot display issues.
3. Insert Unicode Control Character
    - Function: This allows you to manually insert specific Unicode control characters into the text. These characters are used to fine-tune text direction, shaping, and rendering:
        a) LRM (Left-to-right Mark): Forces the following characters to be displayed left-to-right.
        b) RLM (Right-to-left Mark): Forces the following characters to be displayed right-to-left.
        c) ZWJ (Zero Width Joiner): Connects two characters that might otherwise be separated.
        d) ZWNJ (Zero Width Non-Joiner): Prevents two characters from being connected.
        e) LRE (Start of Left-to-right Embedding): Starts a region of left-to-right text within right-to-left text.
        f) RLE (Start of Right-to-left Embedding): Starts a region of right-to-left text within left-to-right text.
        g) LRO (Start of Left-to-right Override): Overrides the current text direction and sets it to left-to-right.
        h) RLO (Start of Right-to-left Override): Overrides the current text direction and sets it to right-to-left.
        i) PDF (Pop Directional Formatting): Ends a region of embedded text direction.
        j) NADS (National Digit Shapes Substitution): Uses the digit shapes specific to the current locale.
        k) NODS (Nominal (European) Digit Shapes): Uses the standard European digit shapes (0-9).
        l) ASS (Activate Symmetric Swapping): Enables symmetric swapping of characters, which can affect the appearance of certain characters.
        m) ISS (Inhibit Symmetric Swapping): Disables symmetric swapping of characters.
        n) AAFS (Activate Arabic Form Shaping): Enables shaping of Arabic characters based

on their position in the word.

o) IAFS (Inhibit Arabic Form Shaping): Disables shaping of Arabic characters.

p) RS (Record Separator): A block separator character.

q) US (Unit Separator): A segment separator character.

4. Open IME

   - Function: This opens the Input Method Editor (IME), a tool that allows you to input characters from languages that don't have direct keyboard mappings.

5. Reconversion

   - Function: This option is specific to IMEs. It re-analyses the input text and may suggest alternative conversions or corrections.

In Summary

These Unicode-related context menu items in osFinancials5/TurboCASH5 provide powerful tools for handling text in various languages and scripts. They allow you to control text direction, insert special characters, and fine-tune text rendering to ensure accurate and professional-looking results.

Break down and simplify the explanation of the Unicode-related context menu items

These options are designed to help you manage text formatting, especially when working with languages like Arabic or other scripts that require special handling.

---

1. Right to Left Reading Order

   - What It Does:
     - Controls the direction in which text is displayed and processed.
     - When enabled, text is displayed right-to-left (RTL), which is necessary for languages like Arabic and Hebrew.
   - When to Use: Use this when working with RTL languages to ensure text is displayed correctly.

---

2. Show Unicode Control Characters

   - What It Does: Displays invisible Unicode control characters in the text. These characters affect how text is formatted and rendered but are normally hidden.
   - When to Use: Use this to troubleshoot text display issues, such as incorrect text direction or formatting.

3. Insert Unicode Control Character

This option allows you to insert special Unicode characters to control text behavior. Here's a breakdown of the most commonly used ones:

a) LRM (Left-to-right Mark)

- What It Does: Forces the following text to be displayed left-to-right (LTR).
- When to Use: Use this to fix issues where numbers or special characters (like +) are displayed incorrectly in RTL text.

b) RLM (Right-to-left Mark)

- What It Does: Forces the following text to be displayed right-to-left (RTL).
- When to Use: Use this to ensure specific text is displayed in RTL order within LTR text.

c) ZWJ (Zero Width Joiner)

- What It Does: Connects two characters that would otherwise be separated.
- When to Use: Use this in languages like Arabic to join characters that should appear as a single unit.

d) ZWNJ (Zero Width Non-Joiner)

- What It Does: Prevents two characters from being joined.
- When to Use: Use this to keep characters separate when they would normally be joined.

e) LRE (Start of Left-to-right Embedding)

- What It Does: Starts a section of LTR text within RTL text.
- When to Use: Use this to embed LTR text (e.g., phone numbers, URLs) in RTL documents.

f) RLE (Start of Right-to-left Embedding)

- What It Does: Starts a section of RTL text within LTR text.
- When to Use: Use this to embed RTL text (e.g., Arabic phrases) in LTR documents.

g) LRO (Start of Left-to-right Override)

- What It Does: Forces all following text to be displayed LTR, overriding the default

direction.

- When to Use: Use this to ensure a block of text is displayed LTR, even in an RTL context.

h) RLO (Start of Right-to-left Override)

- What It Does: Forces all following text to be displayed RTL, overriding the default direction.
- When to Use: Use this to ensure a block of text is displayed RTL, even in an LTR context.

i) PDF (Pop Directional Formatting)

- What It Does: Ends the effect of the last LRE, RLE, LRO, or RLO.
- When to Use: Use this to return to the default text direction after embedding or overriding.

j) NADS (National Digit Shapes Substitution)

- What It Does: Displays digits in the shapes specific to the current locale (e.g., Arabic-Indic digits).
- When to Use: Use this to display numbers in the local format (e.g., ٠١٢٣ instead of 0123).

k) NODS (Nominal (European) Digit Shapes)

- What It Does: Displays digits in standard European shapes (0-9).
- When to Use: Use this to display numbers in the Western format.

l) ASS (Activate Symmetric Swapping)

- What It Does: Enables swapping of characters that have mirrored forms (e.g., parentheses).
- When to Use: Use this to ensure proper display of mirrored characters in RTL text.

m) ISS (Inhibit Symmetric Swapping)

- What It Does: Disables swapping of mirrored characters.
- When to Use: Use this to prevent unwanted character mirroring.

n) AAFS (Activate Arabic Form Shaping)

- What It Does: Enables shaping of Arabic characters based on their position in a word.
- When to Use: Use this to ensure proper display of Arabic script.

o) IAFS (Inhibit Arabic Form Shaping)

- What It Does: Disables shaping of Arabic characters.
- When to Use: Use this to display Arabic characters in their isolated forms.

p) RS (Record Separator)

- What It Does: Acts as a block separator in text.
- When to Use: Rarely used in everyday text formatting.

q) US (Unit Separator)

- What It Does: Acts as a segment separator in text.
- When to Use: Rarely used in everyday text formatting.

---

4. Open IME

- What It Does: Opens the Input Method Editor (IME), a tool for typing characters in languages that don't have direct keyboard mappings.
- When to Use: Use this to input characters in languages like Chinese, Japanese, or Arabic.

---

5. Reconversion

- What It Does: Re-analyses text input using the IME and suggests alternative conversions or corrections.
- When to Use: Use this to fix or refine text input in complex scripts.

Summary

These Unicode-related context menu items in osFinancials5/TurboCASH5 provide powerful tools for:

- Controlling text direction (RTL/LTR).
- Inserting special characters to fine-tune text rendering.
- Managing complex scripts like Arabic.

- Troubleshooting text display issues.

If you're working with Arabic text or other RTL languages, the LRM (Left-to-right Mark) is particularly useful for fixing issues with numbers or special characters (like +). For example, inserting an LRM before the + sign in a phone number ensures it displays correctly as +966 55 123 4567 instead of 4567 123 55 966+.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Install osFinancials5 - Single user

Install osFinancials - Added Unicode Setting

We've adjusted the installation script to include a new Unicode setting for Unicode databases. This setting allows you to control the nounicode parameter in the osf.ini file during installation. Additionally, we've added options to update or retain the existing osf.ini file based on your Unicode preferences for your Unicode databases. This allows you to set the Unicode settings via the installation process without editing the osf.ini file in the osFinancials5 installation's root directory.

Unicode Settings in osFinancials5/TurboCASH5

In osFinancials5, the osf.ini (or in TurboCASH the tcash.ini file) includes the setting nounicode=FALSE or nounicode=TRUE to control Unicode settings. Here's what these settings mean:

- Enable Unicode support: nounicode=FALSE: This setting enables Unicode support. When Unicode is enabled, the software can handle a wide range of characters from different languages, ensuring proper display and processing of multilingual text.
- Disable Unicode support: nounicode=TRUE: This setting disables Unicode support. When Unicode is disabled, the software may not correctly handle special characters or characters from languages other than the default one.

Enabling Unicode (nounicode=FALSE) is generally recommended if you need to work with multiple languages or special characters to ensure data integrity and proper functionality.

Unicode Settings for Older Databases

For existing users with Firebird Databases version 10.1, the new Firebird databases are upgraded to version 11.1 as part of the 2025 installs for osFinancials5.1 and TurboCASH5-3. This upgrade is mandatory

and should be carefully considered, especially for users with older databases.

Default Setting:

To ensure the safest option for users with older databases, we recommend setting the Unicode option to "*checked*" by default. However, it's crucial that users confirm their choice to avoid any unintended changes.

Installation Options:

During the osFinancials installation, you will see the following tick-boxes:

- Unicode Tick Box - Confirmation:

  By checking the Unicode box, you acknowledge that you understand the `unicode` parameter and confirm your choice. This step is designed to prevent any accidental changes without proper consideration. If you leave this checkbox unticked and the select the Unicode checkbox ticked, the Unicode setting will be set as true in the osf.ini file:

  ```
  nounicode=true
  ```

- Unicode Checked - If this checkbox is not selected, a Runtime error message is displayed:

  ```
  "Please check and confirm your unicode option."
  ```

If you need to check both the Unicode and Unicode Check tick-boxes, the Unicode setting will be set as false in the osf.ini file:

```
nounicode=false
```

We strongly advise consulting with a professional before enabling the Unicode setting. This ensures that you fully understand the implications and make an informed decision.

Single user installation

- *This documentation will describe to do a standard installation to run osFinancials5 locally on one computer for 1 user only.*
- *Multi-user installation and configuration are described in the following documentation:*
  - *Multi-user Windows installation*
  - *Multi-user Linux server install*
  - *Multi-user installation (TurboCASH website)*

- *Multi-user is limited in this edition! You will need to buy a multi-user licence.*

To Install osFinancials5 Single-user:

1. Once the osFinancials5 installation file is downloaded, select the file and open it. The "*Select Setup Language*" screen is displayed:



The default installation language is set to English. "Nederlands" language is also available to launch the osFinancials5 install option.

2. Select "*English*" and click OK. The "*License Agreement"* screen will be displayed.

3. Please read the agreement carefully. If you agree with the terms and conditions of the licence agreement, select the "*I accept the agreement*" option and click Next. The "*Select Destination Location"* screen is displayed:



The default path is C:/osFinancials5 on your system's default drive.

You may click on the Browse button to select any other folder than the default path where you wish to install osFinancials5 on the "Browse for Folder" screen.

If you need to install osFinancials5 on a device with a small default system drive (e.g. 32GB solid state drive), it is recommended to select a larger drive on your system.

DO NOT Install in PROGRAM (Program Files, Program Files (x86) or Program Data) folders.

If osFinancials5 is installed into the Programs directories (folders) (i.e. Program Files, Program Files (x86) or Program Data folders), it may not run properly. It may cause issues to launch osFinancials5, connection and performance issues with Firebird and FlameRobin, etc.

The Program directories is a protected directories of the Windows system.

4. Once finished, click Next. The "*Select Start Menu Folder*" screen is displayed:



5. The default option is "*(Default)*". You may select or specify a different folder.

6. Once finished, click Next. The "*Select Additional Tasks*" screen is displayed:



7. By default, the "*Select Additional Tasks*" options is not selected. The options is as follows:

   a) Additional shortcuts: Select the "*Create a desktop shortcut*", if you wish to add the osFinancials5 icon on your desktop, from where you may start or launch the *osFinancials5* program.

   b) Unicode settings: - Select both the "*Unicode*" and "*Unicode Checked*" options. This will enable Unicode support.

> *We strongly advise consulting with a professional before enabling the Unicode setting. This ensures that you fully understand the implications and make an informed decision.*

> *Unicode Checked - If this mandatory checkbox is not selected, a Runtime error message is displayed:*
>
> "Please check and confirm your unicode option."

> *To enable Unicode support (recommended for most users), both the "Unicode" and "Unicode*

Checked" tick boxes need to be selected. This option will set the nounicode=FALSE parameter in the osf.ini file.

This is a very important setting, as this will determine the display of special characters in the osFinancials interface, reports document layout files, etc. in most databases.

To Disable Unicode support option, the "Unicode" check box must not be selected. Only the "Unicode Checked" tick box need to be selected.

This setting is intended for users who require non-Unicode support. This option will set the nounicode=TRUE parameter in the osf.ini file.



Using this setting, (Disable Unicode), the system relies on specific codepages to handle text. Some examples would be:

- *French (Codepage 1252): Handles Western European characters, but may have limitations with special symbols unique to other languages.*
- *Spanish (Codepage 1252): Similar to French, it manages Spanish characters well but might struggle with characters from non-Western languages.*

- *Arabic (Codepage 1256): Supports Arabic characters effectively, but may not handle characters from Latin-based languages as efficiently.*

In osFinancials5, the codepage can be set in the Tools → Customise language on the Setup ribbon.

If your Unicode settings, is incorrect, you may re-run the installation process.

Alternatively, you may locate the osf.ini file in the osfinancials5 installation directory and edit the nounicode=true and set it to nounicode=false, and vice versa. In this case you may need to close and restart osfinancials5.

8. Once finished, click Next. The "*Ready to Install*" screen is displayed:



9. Please check the settings.

This is your last chance to change anything to be installed. If you are not satisfied with your selection, click on the Back buttons to change the Installation directory, or the Start menu folder or select / deselect the necessary options.

10. Click on the Install button. The osFinancials5 installation process will start.

Overwrite confirmation message:

A confirmation message will be displayed if you have installed osFinancials5 over an existing (previous) osFinancials5 installation.

You then need to choose the following actions:

- *Overwrite the existing file - Select this option, the Set of Books will be replaced with the Set of Books in this installation.*
- *Keep the existing file - Select this option, if you have worked (changed or added data) to the Set of Books (with the same Name as installed) and wish to keep the existing Set of Books.*

11. Once the *osFinancials5* installation process is finished, the "*Completing the osFinancials 5 Setup Wizard*" screen is displayed:



12. Please select or deselect (remove the tick) to Launch osFinancials 5 - If this option is selected (ticked), the *osFinancials5* program will automatically be launched, when you click on the Finish button.

13. Once finished selecting or deselecting the necessary options, click on the Finish button. The *osFinancials5* program will be started if you did not remove (deselect) the tick on the "*Launch osFinancials 5*" option.

14. After launching osFinancials, after installation, the "*Set of Books*" screen will be displayed.

Every time an unregistered version of osFinancials5 is started, the following confirmation message will be displayed:

> This software is limited to 500 transactions or 500 documents. Please register and buy a licence for osFinancials5!
> This copy of osFinancials5 is not registered! Do you wish to register it now?

Unregistered versions will allow you to process up to 500 transactions and /or documents. Once this limit is reached, osFinancials5 will not allow any processing of transactions, in batches and/or documents.

Once you have registered osFinancials5, you will receive an unlocking code and will be able to process further transactions and or documents.

After installing osFinancials5, the following optional additional components, is included in the "installs" folder of the osFinancials5 root installation directory:

- *Firebird Version 2.1 - Advanced users may wish to install.*

  Later releases of Firebird Versions 3 and Versions 4 is currently not supported in osFinancials5 databases (Sets of Books).

- *FlameRobin Version 0.9.3 - FlameRobin Database Admin software to manage and explore your osFinancials5 databases (Sets of Books). To use FlameRobin, you need to install Firebird Version 2.1.*

After installing osFinancials5.1 in a new directory - manually migrate your existing data from previous versions

After installing osFinancials5.1 in a new directory, you'll need to manually migrate your existing data from previous versions (osFinancials4, osFinancials5, The following data should be migrated:

1. Set of Books: You have several options:

- Copy: Using File Explorer, copy your Set of Books from the "*books*" folder of your older osFinncials installation to the "*books*" folder of your new osFinancials5.1 installation.
- Save as: Use the "Save as" option on the Start ribbon within your older osFinancials version and select the "*books*" folder within your new osFinancials5.1 installation directory (e.g., osFinancials5-1/books).
- Backup/Restore: Create a backup of your Set of Books in the older osFinancials5 version. Then, restore this backup in the "*books*" directory of your osFinancials5.1 installation.

2. Custom Document Layout Files: Copy any custom document layout files to the following directory in your osFinancials5.1 installation:

```
/plug_ins/reports/DOCUMENTS/DOCUMENTS/
```

3. Custom Reports: Copy any custom reports from your older osFinancials5 version to the "User reports" menu directory in your osFinancials5.1 installation:

```
/plug_ins/reports/userreports
```

Important Note: This migration process is required because osFinancials5.1 are not updates to previous versions; is entirely a new installation.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Install TurboCASH5-3 - Single user

The TurboCASH5-3 installation process should only take a few minutes. During this process you may need to select a few options. The most important options, you may need to select is your country and language, reading and accepting the licence agreement.

Important Note for Existing TurboCASH Users : Installing TurboCASH5-3 or TurboCASH5-2025

If you are currently using a previous version of TurboCASH (e.g., TurboCASH3, TurboCASH4, TurboCASH 4.0.0.969, TurboCASH5, or TurboCASH5-2), it's crucial to understand that TurboCASH5-3 are *not* updates. They are entirely new versions. Therefore, you must not install them in the same directory as your existing TurboCASH installation.

Installing the new versions in the same directory as an older version can lead to errors. For instance, If you install TurboCASH5-3, in an existing directory in which TurboCASH5 4.0.0.969 is installed, you might encounter errors such as:

```
Application Error
Exception EReadError in module rtl150.bpl at 00074FF4.
Error reading TGlobalDataObject.Registration.PluginsChecksum: Property
PluginsChecksum
```

To avoid such issues, please choose a different installation directory for TurboCASH5-3.

Installing TurboCASH5-3 into *any* existing TurboCASH folder (like TCASH, TurboCASH5, TurboCASH5-2, or any other) is likely to cause problems. The core issue is that these are completely new versions, not updates, and they need their own clean installation space. Trying to mix them with older files will almost certainly lead to conflicts and errors.

When installing TurboCASH5-3 or TurboCASH5-2025 into an existing folder, you may see the following warning message:

> Folder Exists
> The folder:
> *C:\TCASH5*
> already exists. Would you like to install to that folder anyway?

If you click Yes, you may encounter problems.

It is strongly recommended that you click "No" and choose a different installation directory. Installing into an existing TurboCASH folder (even if it's for a seemingly related version) can lead to software conflicts and errors. These TurboCASH5-3 are new versions are not updates and require a clean installation.

Unicode Settings

Install TurboCASH - Added Unicode Setting

We've adjusted the installation script to include a new Unicode setting for Unicode databases. This setting allows you to control the nounicode parameter in the tcash.ini file during installation. Additionally, we've added options to update or retain the existing tcash.ini file based on your Unicode preferences for your Unicode databases. This allows you to set the Unicode settings via the installation process without editing the tcash.ini file in the TurboCASH5 installation's root directory.

Unicode Settings in TurboCASH5

In TurboCASH5, the tcash.ini file includes the setting nounicode=FALSE or nounicode=TRUE to control Unicode settings. Here's what these settings mean:

- Enable Unicode support: nounicode=FALSE: This setting enables Unicode support. When Unicode is enabled, TurboCASH5 can handle a wide range of characters from different languages, ensuring proper display and processing of multilingual text.
- Disable Unicode support: nounicode=TRUE: This setting disables Unicode support. When Unicode is disabled, TurboCASH may not correctly handle special characters or characters from languages other than the default one.

Enabling Unicode (nounicode=FALSE) is generally recommended if you need to work with multiple

languages or special characters to ensure data integrity and proper functionality.

See - Unicode settings in osFianacials5/TurboCASH5 for explanation of unicode options and tests.

Install *Turbo*CASH5 single-user

The TurboCASH5 should, by default, install in the TurboCASH5 directory (e.g. C : / TurboCASH5. If you choose to install TurboCASH5 in different directory or folder on your system, DO NOT install TurboCASH5 in any Program files directories.

If you wish to install TurboCASH5 on a device that has a Solid State Drive which is small, e.g. 32GB as the C: drive, you need to select the D: drive that is bigger in size.

This documentation will describe to do a standard installation to run TurboCASH5 locally on one computer for 1 user only.

- *Multi-User installation and configuration will be dealt with in separate documentation.*
- *Multi-user is limited in this edition! You will need to buy a multi-user license.*

After installing TurboCASH5-3, the following optional additional components, is included in the " *installs*" folder of the TurboCASH5-3 root installation directory:

- Firebird Version 2.1 - Advanced users may wish to download and install a later version of the discontinued downloads - Firebird version 2.5.9.

Later releases of Firebird Versions 3 and Versions 4 is currently not supported in TurboCASH5-3 databases (Sets of Books).

- FlameRobin Version 0.9.3 - Advanced users may wish to download and install a later version of FlameRobin (version 0.9.6) FlameRobin Database Admin software to manage and explore your TurboCASH5-3 databases (Sets of Books).

To install *Turbo*CASH5 single-user:

1. Once the TurboCASH5-3 installation file is downloaded, select the file and open it. The "*Select country and language*" screen is displayed:

2. Select your country and language. Click OK. The "*Welcome to the TurboCASH5-3 Setup Wizard"* screen is displayed:



3. Click Next. The "*License Agreement*" screen will be displayed.

4. Please read the agreement carefully. If you agree with the terms and conditions of the license agreement, select the "*I accept the agreement*" option and click Next. The "*Select Destination Location*" screen is displayed:



5. The default path is TCASH5 on your system's default drive, (e.g. C:/TCASH5-3).

When installing TurboCASH5-3 into an existing folder, you may see the following warning message:

> Folder Exists
> The folder:
> *C:\TCASH5*
> already exists. Would you like to install to that folder anyway?

If you click Yes, you may encounter problems.

It is strongly recommended that you click "No" and choose a different installation directory. Installing into an existing TurboCASH folder (even if it's for a seemingly related version) can lead to software conflicts and errors. These TurboCASH5-3 is a new version is not an update and require a clean installation.

You may click on the Browse button to select any other folder than the default path where you wish to install TurboCASH5 on the "Browse For Folder" screen.

If you wish to install TurboCASH on a device that has a Solid State Drive which is small e.g. 32GB as the C: drive, you need to select the D: drive that is bigger in size.

You may over type this with your own description, if necessary. This will create an item on the Start → Programs menu list with items for TurboCASH5-3, Uninstall TurboCASH5-3 on your Windows™ Task bar.

6. Once finished, click Next. The "*Select Components*" screen, is displayed:



7. A list of the components will be displayed. Select or deselect (remove the tick) for the following options, if necessary:

   a) Install Firebird Database Server (Needed to run *Turbo*CASH5 local 1 user only) - If you are installing *Turbo*CASH5 for the first time, you need to make sure that this option is selected.

Select this option if you need to run TurboCASH5 locally for 1 user only.

   b) Install Firebird Database Server (Needed to run *Turbo*CASH5 on a server or client).

For the purpose of the single-user installation, do not select this option.

c) Install FlameRobin SQL Browser Type - (Optional) - This will install the FlameRobin Database Admin software to manage your *Turbo*CASH5-3 databases (Sets of Books).

For the purpose of the single-user installation, do not select this option.

The FlameRobin software is used to browse, check and edit data. The installation of FlameRobin is optional and is not required to run TurboCASH5-3. The use of FlameRobin is not recommended for users which have insufficient knowledge and expertise.

8. Once finished, selecting the components to be installed, click Next. The "*Select Additional Tasks*" screen is displayed:



9. By default no options are selected. Select the following options, if you wish them to be installed:

a) Create desktop icon - This will create an icon on your desktop from where you may start or launch the *Turbo*CASH5-3 program.

b) Create Quick Launch icon - This will create an icon on your Quick Launch Toolbar on your Windows™ Task bar. You may then start or launch the *Turbo*CASH5-3 program directly from the Quick Launch Toolbar.

c) Unicode settings - Select both the "*Unicode*" and "*Unicode Checked*" options. This will enable Unicode support.

We strongly advise consulting with a professional before enabling the Unicode setting. This ensures that you fully understand the implications and make an informed decision.

Unicode Checked - If this mandatory checkbox is not selected, a Runtime error message is displayed:

"Please check and confirm your unicode option."

To enable Unicode support (recommended for most users), both the "Unicode" and "Unicode Checked" tick boxes need to be selected. This option will set the nounicode=FALSE parameter in the tcash.ini file.

This is a very important setting, as this will determine the display of special characters in the TurboCASH5 interface, reports document layout files, etc. in most databases.

To Disable Unicode support option, the "Unicode" check box must not be selected. Only the "Unicode Checked" tick box need to be selected.

This setting is intended for users who require non-Unicode support. This option will set the nounicode=TRUE parameter in the tcash.ini file.



Using this setting, (Disable Unicode), the system relies on specific codepages to handle text. Some examples would be:

- *French (Codepage 1252): Handles Western European characters, but may have limitations with special symbols unique to other languages.*
- *Spanish (Codepage 1252): Similar to French, it manages Spanish characters well but might struggle with characters from non-Western languages.*
- *Arabic (Codepage 1256): Supports Arabic characters effectively, but may not handle characters from Latin-based languages as efficiently.*

In TurboCASH5, the codepage cannot be set in the Tools → Customise language on the Setup ribbon.

If your Unicode settings, is incorrect, you may re-run the installation process.

Alternatively, you may locate the tcash.ini file in the TurboCASH5 installation directory and edit the nounicode=true and set it to nounicode=false, and vice versa. In this case you may need to close and restart TurboCASH5.-3

10. Once finished, click Next. The "*Ready to Install*" screen is displayed:



11. Please check the following selections to be installed:

    a) Destination location

    b) Setup type

    c) Selected components

    d) Start Menu folder

    e) Additional tasks (icons)

    f) Unicode Settings

This is your last chance to change anything to be installed. If you are not satisfied with your selection, click on the Back buttons to select or deselect the necessary options.

Overwrite confirmation message:

A confirmation message will be displayed if you have installed TurboCASH5 over an existing

(previous) TurboCASH installation. If you have worked (changed or added data) to the Set of Books (with the same Name as installed) and wish to retain the existing Set of Books, click No to retain your existing data. The Set of Books will not be replaced by the installation.

12. If you click on the Yes button, the Set of Books will be replaced with the Set of Books in this installation.

13. Click Install. The *Turbo*CASH5 installation process will start. Once the *Turbo*CASH5-3 installation process is finished, the "*Completing the TurboCASH5-3 Setup Wizard*" screen is displayed:



The following Components will not be listed, if it was not selected in the "Select Components" screen:

- *Install Firebird*
- *Install FlameRobin SQL Browser Type*

14. If the Launch *Turbo*CASH5-3 option is selected, the *Turbo*CASH5-3 program will automatically be launched.

If you do not select this option (remove the tick), you may then launch or start TurboCASH5 from the following options (if selected or where specified): -

- *Desktop icon.*
- *Quick Launch icon (on the Quick Launch Toolbar on your Windows™ Task bar).*
- *Start → Programs → TurboCASH5-3 menu from the Windows™ Start button.*

15. Once finished selecting or deselecting the necessary options, click Finish. The *Turbo*CASH program will be started if you did not remove the tick on the "*Launch TurboCASH5-3*" option.

After installing TurboCASH5-3 in a new directory - manually migrate your existing data from previous versions

After installing TurboCASH5-3 in a new directory, you'll need to manually migrate your existing data from previous versions (TurboCASH4, TurboCASH5, or TurboCASH5-2). The following data should be migrated:

1. Set of Books: You have several options:

   Copy: Using File Explorer, copy your Set of Books from the "*books*" folder of your older TurboCASH installation to the "*books*" folder of your new TurboCASH5-3 installation.
   Save as: Use the "Save as" option on the Start ribbon within your older TurboCASH version and select the "books" folder within your new TurboCASH5-3 installation directory (e.g., `TurboCASH5-3/books`).
   Backup/Restore: Create a backup of your Set of Books in the older TurboCASH version. Then, restore this backup in the "*books*" directory of your TurboCASH5-3 installation.

2. Custom Document Layout Files: Copy any custom document layout files to the following directory in your TurboCASH5-3 installation:

   ```
   /plug_ins/reports/DOCUMENTS/DOCUMENTS/
   ```

3. Custom Reports: Copy any custom reports from your older TurboCASH version to the "User Reports" menu directory in your TurboCASH5-3 installation:

   ```
   /plug_ins/reports/userreports
   ```

Important Note: This migration process is required because TurboCASH5-3 are not updates to previous versions; is entirely a new installation.

Created with the Standard Edition of HelpNDoc: Maximize Your Reach: Convert Your Word Document to an ePub or Kindle eBook

Migrate existing data into TurboCASH5-3

After installing TurboCASH5-3 in a new directory, you'll need to manually migrate your existing data from previous versions (TurboCASH4, TurboCASH5, or TurboCASH5-2). The following data should be migrated:

1. Set of Books: You have several options:
   - Copy: Using File Explorer, copy your Set of Books from the "*books*" folder of your older TurboCASH installation to the "*books*" folder of your new TurboCASH5-3 installation.
   - Save as: Use the "Save as" option on the Start ribbon within your older TurboCASH version and select the "books" folder within your new TurboCASH5-3 installation directory (e.g., `TurboCASH5-3/books`).
   - Backup/Restore: Create a backup of your Set of Books in the older TurboCASH version. Then, restore this backup in the "*books*" directory of your TurboCASH5-3 installation.
2. Custom Document Layout Files: Copy any custom document layout files to the following directory in your TurboCASH5-3 installation:

   ```
   /plug_ins/reports/DOCUMENTS/DOCUMENTS/
   ```

3. Custom Reports: Copy any custom reports from your older TurboCASH version to the "User Reports" menu directory in your TurboCASH5-3 installation:

   ```
   /plug_ins/reports/userreports
   ```

Important Note: This migration process is required because TurboCASH5-3 are not updates to previous versions; is entirely a new installation.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Install osFinancials5 - Updates (Help menu)

Install osFinancials5 Updates from the Help menu

Installation files / changelog link : osFinancials-Turbocash-Business-version

After years of developing and supporting osFinancials and TurboCASH, we have realized that the current model is not sustainable. Therefore, we are introducing a new version called "osFinancials 5 Business" to break through this glass ceiling.

osFinancials 4 will continue to be available for free use. However, if you want to access additional features and functionalities, we recommend upgrading to "osFinancials 5 Business". If your business has fewer than 500 transactions/documents, you can use this version free of charge. For businesses with more than 500 transactions/documents, we ask for a contribution of 50 euros (excluding taxes) or 60 US dollars per year.

If you already have a subscription for a multi-user or retail POS, the osFinancials 5 Business licence will be included.

Once you install osFinancials 5 on your system, updates will be released from time to time, containing bug fixes, new features, and other improvements.

To Install osFinancials 5 Updates

The Update option will list all the installation files available for download. By default, the Update will be launched when starting *osFinancials 5*. To disable the check for update at start, select this field and remove the tick.

It is important to make a backups of your Set of Books. It is strongly recommended that you make a backup copy of the entire installation folder of your existing installation osFinancials 5 before proceeding with the update.

The Updates option may manually be launched from Help → Updates (Start ribbon).





You may select to install the Official versions or Beta versions.

Once you have selected your version, click on the Install (selected version) button. The following confirmation message is displayed:

> This action will close osFinancials5 and install the selected version (e.g. 5.0.0.408 we recommend you make a backup of the whole folder of osFinancials5.
> Do you wish to continue?

If you wish to proceed, tick the option "*I have read this instruction and understand the action!*". The Yes and No buttons will be activated.

If you click on the Yes button (of the confirmation screen), the following process will start:

- Download the install file for the selected version and text file with the change log and store it in the "*.../installs*", e.g. "*D:\osfinancials5\installs* folder of your current osFinancials5 installation.
- Automatically install the selected version and close the current osFinancials5 session.

If there are any other osFinancials5 installation files in the ".../installs" folder of your current osFinancials5 installation, the installation process will not start. The following error message will be displayed:

> The setup files are corrupted. Please obtain a new copy of the program.

Click OK and delete the install files from the installs folder.

Restart osFinancials5 and select the file from the Updates screen and click on the Install (version) button.

Once the installation is finished, you may launch osFinancials 5 from your system.

The selected version of osFinancials5 will be displayed in the title-bar of the selected version of the installed upda

---

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Install osFinancials5 - Updates (Manually)

Install osFinancials5 Updates - Manually

Installation files / changelog link : osFinancials-Turbocash-Business-version

It is important to make a backups of your Set of Books. It is strongly recommended that you make a backup copy of the entire installation folder of your existing installation osFinancials5 before proceeding with the update.

The Updates option may manually be launched from Help → Updates (Start ribbon).

The Update option will list all the installation files available for download. By default, the Update will be launched when starting osFinancials5. To disable the check for update at start, select this field and remove the tick.



To Install osFinancials5 Updates from a downloaded file

1. Once the osFinancials5 Update installation file is downloaded, select the file and open it. The "*Select Setup Language*" screen is displayed:



> *The default installation language is set to English. "Nederlands" language is also available to launch the osFinancials5 install options.*

2. Select your country and language and click OK. The "*License Agreement"* screen will be displayed.

3. Please read the agreement carefully. If you agree with the terms and conditions of the licence agreement, select the "*I accept the agreement*" option and click Next. The "*Select Destination Location"* screen is displayed:



The default path is C:/osFinancials5 on your system's default drive.

This should be the same folder in which the Full version of osFinancials5 is installed..

4. Once finished, click Next. The "*Ready to Install*" screen is displayed:



5. Please check the settings.

> *This is your last chance to change anything to be installed. If you are not satisfied with your selection, click on the Back buttons to change the Installation directory, or the Start menu folder or select / deselect the necessary options.*

6. Click on the Install button. The osFinancials5 update installation process will start.

7. Once the osFinancials5 installation process is finished, the "*Completing the osFinancials 5 Setup Wizard*" screen is displayed:



8. Please select or deselect (remove the tick) to Launch osFinancials 5 - If this option is selected (ticked), the *osFinancials5* program will automatically be launched, when you click on the Finish button.

9. Once finished selecting or deselecting the necessary options, click on the Finish button. The *osFinancials5* program will be started if you did not remove (deselect) the tick on the "*Launch osFinancials 5"* option.

Created with the Standard Edition of HelpNDoc: Converting Word Docs to eBooks Made Easy with HelpNDoc

Install Updates - Go back to osFinancials4

Install osFinancials5 Updates from the Help menu - Downgrading to osFinancials4

After years of development and support of osFinancials and TurboCASH we came to the conclusion the current model does not work. To break true this glass ceiling we are introducing "*osFinancials 5 Business*".

osFinancials 4 is free to use but if you want more out of your software then "osFinancials 5 Business" is the

version you want to use.

If you have less then 500 transactions / documents you can use this version free of charge. Above that we ask you for a contribution of 50 euro (excl.)/ 60 dollars per year.

If you have any subscription already like multi-user or retail POS, etc., the licence will also be included.

Once osFinancials5 is installed on your system, Update to osFinancials5 is released from time to time. These updates of osFinancials5, contain certain bugfixes, etc.

If you wish to revert back to the osFinancials 4 (the free to use version of osFinancials), you may use the Update option.

The Update option will list all the installation files available for download. By default, the Update will be launched when starting osFinancials5/TurboCASH5. To disable the check for update at start, select this field and remove the tick.

It is important to make a backups of your Set of Books. It is strongly recommended that you make a backup copy of the entire folder of your existing installation before proceeding with the update.

The Updates option may manually be launched from Help → Update (Start ribbon).

To downgrade to osFinancials 4:

Launch the Updates.

Select osFinancials 4.0.0.1093



Click on the Install 4.0.0.1093 button. The following confirmation message is displayed:

"This action will close osFinancials and install version 4.0.0.1093 we recommend you make a backup of the whole folder of osFinancials.
Do you wish to continue?"

If you wish to proceed, tick the option "*I have read this instruction and understand the action!*"

The Yes and No buttons will be activated.

If you click on the Yes button (of the confirmation screen), the following process will start:

- Download the install file for the selected version and text file with the change log and store it in the "*.../installs*", e.g. "*D:\osfinancials5\installs*" folder of your current osFinancials installation.
- Automatically install the osFinancials 4 and close the current osFinancials session.

If there are any other osFinancials installation files in the ".../installs", e.g. "D:\osfinancials5\installs" folder of your current osFinancials installation, the installation process will not start. You may then select the osFinancials 4 file and install it manually.

Once the installation is finished, you may launch 

from your system.

Note the selected osFinancials4.0.0.193 will be displayed in the title-bar.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Uninstall osFinancials5

Uninstall osFinancials5

If you need to uninstall osFinancials5, go to the Start button on your Windows Taskbar and select osFinancials5.

All apps option	*Pinned*



The Program and features - Uninstall or change a program of the Windows Control Panel will be launched.



You may also double-click on the "Uninstall000.exe" file in the Installation folder of osFinancials5.

To uninstall osFinancials5:

1. Select osFinancials5 and click on the Uninstall option.



2. Click on the Yes button to uninstall osFinancials5.

3. Wait for the process to complete. Once finished, the following information screen is displayed.



4. Click on the OK button.

5. Once the Uninstall process is finished, you need to use File Explorer or your system's default file

browser to select the osFinancials5 (or other installation directory).

The files which have been created, or edited by the user after the original installation, will not be deleted or removed. Some examples are;

- *books folder - Any Sets of Books created, copied, saved, etc.*
- *Bin/Themes - Any changes to themes (e.g. background pictures, icons, etc.).*
- *plug_ins/reports/ - any reports added after the original installation, etc.*
- *Registration.ini file - Only if you have registered this version of osFinancials5.*

You may need to copy these files somewhere else on your system. If you do not wish to keep these files, you may delete the entire osFinancials5 folder.

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Start osFinancials5

Start / Launch osFinancials5

When you first install the full version of osFinancials5 or install updates for it, and you select the "*Launch osFinancials 5*" option on the "*Completing the osFinancials 5 Setup Wizard*" screen, osFinancials5 will automatically start up. However, after that initial launch, you will need to manually launch osFinancials5 each time you want to use it.

To start osFinancials5:

1. To start osFinancials5, double click on the

icon created for you on your Desktop (if the "*Create a desktop*" icon option was selected during the installation).

   Or select osFinancials5 on the Start menu - All apps (Programs) → osFinancials5 (or Pinned, if you have already pinned osFinancials5 to the Start.

   Pin osFinancials5 to the Quick access area (Windows 11):



After installation, you may need to add the osFinancials5 to the Quick access area of the Start button.

The osFinancials5 icon should be displayed as Recommended or Recently added. On the osFinancials5 icon, right-click an select Pin to Start.

You may also select to add osFinancials5 to the taskbar (Pin to taskbar).

2. Once osFinancials5 is started, the osFinancials5 splash-screen will display the version number and a progress indicator.



3. Once you have opened osFinancials5, the Start ribbon tab is displayed.

4. Click on the Reports ribbon to load the reports.

At first only the items under the Start ribbon tab is available. Before you can select any of the other ribbon tabs or ribbon options, you will need to "Open a Set of Books" (Click Open on the Start ribbon).

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Launch osFinancials5 for the first time

Launch osFinancials5 for the first time

In osFinancials5, the interface language will be displayed based on the language associated with the Set of Books for the country. Each Set of Books can have a specific language linked to it, and when you open that Set of Books in osFinancials5, the interface language will be displayed in the language associated with that particular Set of Books by default.

Default languages have already been pre-set for each Set of Books. (Setup → Access control on the Setup ribbon).

When opening a Set of Books, it will automatically load the language file. All screens, reports and layout files are translatable via the language files.

Some languages may not display correctly if your system locale in the Regional and Language Settings option in the Control Panel of your system may not support the language and system locale (unicode).

English is the default (driver language file – used as the basis for translation, and to Customise language files). For example, the American and the English files contain specific label, text, currency and tax terminology for each country.

Should you select the incorrect language at this stage, you may change the language in Switch language

on the Start ribbon).

Once osFinancials5 is launched, the "*Set of Books*" screen is displayed. To display the interface of osFinancials5 in the default "*English*" language, select the "*HANDYMAN*" Set of Books and click on the Open button.

Open Set of Books

After a new osFinancials5 installation, the following Sets of Books will be available to open:



To display the interface of osFinancials5 in the default "English" language, select the "HANDYMAN" Set of Books and click on the Open button.

Auto-open when starting osFinancials - Select this option to automatically open a selected Set of Books when you start or launch osFinancials5/TurboCASH5.

Add Sets of Books

By default, osFinancials5 installs with the "books" directory, which includes the "HANDYMAN" Set of Books that opens in English.

The Books are by default installed in the following directories:

- *books - The Sets of Books in this directory, is installed when installing osFinancials5, is HANDYMAN which will open in the English language.*

  If your language or country's Set of Books is not available in the "books" directory, you can download and customize any of the available Firebird Sets of Books and linked languages for free.
  osFinancials5 supports 79 different languages and countries/tax regimes languages linked to 87 Sets of Books (databases), which you can download and customize to meet your requirements.

- *Tutorials*

  - *ENGLISH - The "ENGLISH" folder in the "...bin/Tutorials/" directory includes examples and tutorials to explore osFinancials5 in English. This includes English tutorials (i.e. HANDYMAN (no transactions), HANDYMAN-A (transactions and documents not posted to the ledger) and HANDYMAN-B (transactions and documents posted to the ledger).*
  - *AFRIKAANS - The "AFRIKAANS" folder in the "...bin/Tutorials/" directory includes examples and tutorials to explore osFinancials5 in Afrikaans. This includes Afrikaans tutorials (i.e. NUTSMAN (no transactions), NUTSMAN-A (transactions and documents not posted to the ledger) and NUTSMAN-B (transactions and documents posted to the ledger).*
  - *BANK-IMPORT - The "BANK-IMPORT" folder in the "...bin/Tutorials/" directory includes examples and tutorials to explore the BANK-IMPORT plugin for importing and processing bank statements into your cashbook in osFinancials5 using English. This includes English tutorials (i.e. HANDY-BANK (no transactions), HANDY-BANK-A (transactions and documents not posted to the ledger) and HANDY-BANK-B (transactions and documents posted to the ledger). The HANDY-BANK-UNPOSTED-BANK-STATEMENT (all transactions and documents posted to the ledger, except the bank transactions).*
  - *COST-CENTRES -The "COST-CENTRES" folder in the "...bin/Tutorials/" directory includes examples and tutorials to explore the activation, processing, and reporting of cost centres in osFinancials5.. This includes Cost centre tutorials (i.e. COST-CENTRES-A (transactions and documents not posted to the ledger) and COST-CENTRES-B (transactions and documents posted to the ledger). See - Cost centres in this Help file.*
  - *PROJECTS - The "PROJECTS" folder in the "...bin/Tutorials/" directory includes examples and tutorials to explore the activation, processing, and reporting of projects in*

osFinancials5. This includes Projects tutorials (i.e. PROJECTS-A (transactions and documents not posted to the ledger) and PROJECTS-B (transactions and documents posted to the ledger). See - Projects in this Help file Projects

---

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Register osFinancials5

---

osFinancials and TurboCASH share the same codebase. So we decided to rejoin together to make a single place of content, forum, registrations and a global shop to purchase your products. To get to this, all you need to visit the osFinancials website.

Every time an unregistered version of osFinancials5 is started, the following confirmation message will be displayed:

> This software is limited to 500 transactions or 500 documents. Please register and buy a licence for osFinancials5
> This copy of osFinancials5 is not registered! Do you wish to register it now?

Unregistered versions of osFinancials5 will allow you to process up to 500 transactions and/or documents. Once this limit is reached, osFinancials5 will not allow any processing of transactions, in batches and/or documents.

Once you have registered osFinancials5, you will receive an unlocking code and will be able to process further transactions and/or documents.

You need to register osFinancials5 for:

1. osFinancials5 subscription - The annual subscription includes the bankimport and email document email pro plugins.
2. Webshop - To use any of the powerful plugins, you need to purchase a licence for most of the Plugins. Before you can Register Plugins, you first need to Register osFinancials5.
3. Forum - On the shared forum, you may find topics (posts), post questions or issues, find solutions and participate in any discussions.

To register osFinancials5:

1. On the Start ribbon, select Online registration.



2. Enter the Username and password.

3. Click on the Register button. On the register webpage, you need to enter your Name, Username, Password and Email address.

4. Click on the Send button. An information message is displayed:

   "Registration send success!"

5. Click on the OK button. The message "*You have registered successfully!*" (email address and username) as well as the "*Code*" (Serial number) will be displayed below the User password field, Send and Show licence buttons. If you have purchased any plugins, these plugins will be listed in the "*To register plugins, you need to register osFinancials first!*" section of the screen.

Existing registered users may also Reset the password, change the password or access the webshop directly.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Customise osFinancials5

osFinancials5 installs, by default, in the Classic theme. The Material theme (black icons) is used for most of the topics in this documentation. This is set in Theme on the Setup ribbon.

The Blue, Glass, Silver, Soft-blue theme includes a similar set of icons as in the Material theme (navy-blue icons).

The "Classic" theme (default theme) and "VS2010" theme displays the same set of icons (located in the "...\bin\themes\Classic" folder.

The osFinancials interface will display in the default "*English*" language.

osFinancials5 supports 79 different languages and tax regimes languages liked to 87 Sets of Books (databases) which may be downloaded and customised to meet your requirements.

You may Switch language (Start ribbon) to choose a different language.



Depending on the Set of Books template downloaded when Creating a Set of Books (Creation wizard); or downloaded from the Product information → Technical information → Databases page on the osFinancials website); osFinancials will automatically display the interface language of the language file which have already been linked to each Set of Books. (Setup → Access control).

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's CHM Help File Creation Features

Themes

By default, osFinancials5 is installed in the "*Classic*" theme (default theme) and TurboCASH5 is installed in the "*Material-navy*" theme.

If you prefer a different look, you can choose the "*Blue, Glass, Silver or Soft-blue" or "VS2010"* theme in osFinancials5/TurboCASH5. These themes feature a navy-blue colour scheme and offer a collection of icons similar to those in the "*Material*" theme. In addition to the Material theme's black icons, you may select other coloured variants such as "*Material-blue, Material-green, Material-maroon, Material-navy"*or *"Material-pink*".

Selecting a different theme from the Theme menu allows you to customize the interface to your preferences.

The Material theme (black icons) is implemented in osFinancials5. (in build 518). In TurboASH5 the "Material" theme is shipped with TurboCASH5 (build-453)

The "Blue, Glass, Silver" or "Soft-blue" theme includes a similar set of icons as in the Material theme (navy-blue icons).

The "Classic" theme (default theme) and "VS2010" theme displays the same set of icons (located in the "... \bin\themes\Classic" folder.

See video on Themes. The values for the themes are set in the colors.ini file in the themes folder.

For most of these themes, the icons on the ribbons and screens will also change to blend with the selected theme.

The “Material” theme is used for screen captures in this documentation.

You may change the default Background1.jpg with your own image (photo, logo, products), etc.

Select a theme

To select a theme:

1. On the Setup ribbon, select Theme and select the theme of your choice.

   osFinancials is by default installed in the "*Classic*" theme.



The "*Material*" theme is selected and used for most screenshots in this documentation.



2. Select the theme you like the best. The program will display the selected matching icon set.

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Themes - New theme -change icon colours at one go

In osFinancials5/TurboCASH5, you have the option to easily customize the colour of all 227 icons (in the SVG "*Scalable Vector Graphics*" file format) used in the interface. This customization process can be completed in less than a minute by utilizing a text editor such as Notepad++ and the Search and Replace feature. By replacing the default black colour with a colour of your preference, you can personalize the appearance of the icons in the "*Material*" theme to suit your taste.

If you opt for the "Blue, Glass, Silver," or "Soft-blue" theme in osFinancials5/ TurboCASH5, you will encounter a set of icons resembling those found in the Material theme, but featuring a navy-blue colour palette. These themes offer an alternative visual presentation with cohesive icons, enabling you to personalize the interface by selecting a different theme from the Theme menu on the Setup ribbon.

Process to customise the colour of icons - Overview

An overview of the process to customize the colour of icons in the osFinancials5/TurboCASH5 interface:

1. Start by creating a copy of the "*Material*" theme folder located in the "*.../bin/themes*" folder of your osFinancials5/TurboCASH5 installation directory.
2. Rename the copied folder to your desired theme name, replacing "*Material - Copy*" with your chosen name.
3. Within your new theme folder, delete the eight files responsible for loading the images (icons). These files will be recreated during the final step of the icon customization process (See step 6).
4. Use a program editor like Notepad++ to open the files in your new theme folder. Look for the hexadecimal colour code "#000000" (representing black) and replace it with the hexadecimal colour code of your choice. This will update the colour of the icons to your preferred colour.
5. Launch osFinancials5/TurboCASH5 and navigate to the Setup ribbon. Select your newly created theme from the Theme menu.
6. Lastly, it is important to create a new image strip loader. Go to Tools → Customise language on the Setup ribbon and follow the instructions to create the new image strip loader.

By following these steps, you can enjoy a customised set of coloured icons in the osFinancials5/TurboCASH5 interface, reflecting your chosen theme and colour scheme.

Process to customize the colour of icons - Detailed steps

The process is as follows:

The black colour icons is displayed in the osFinancials5/TurboCASH5 interface when the default "*Material*" theme is selected.



Close osFinancials5/TurboCASH5.

In your File explorer, navigate to the "*.../bin/themes*" folder of your osFinancials5/TurboCASH5 installation directory.

Select the "*Material*" theme and create a copy of the folder. It should create a new folder "*Material - Copy*"

folder.

Rename that folder to for your own name., e.g. "*My-Material*".

In your new theme folder, you may wish to change the view settings to View → Medium icons and set the Sort by → Type file type options

Delete the following eight (8) files (4 *.dfm file types: BatchEnabledButtons.dfm, ilbandlarge.dfm, ilbandsmall.dfm, ImageList1.dfm, and 4 *.fst file types: BatchEnabledButtons.fst, ilbandlarge.fst, ilbandsmall.fst, ImageList1.fst). Note in the "Colors.ini" file.

> "For fast loading images osF uses the .fst files.
> If you want to edit the icons remove these files so the icons are loaded from the files again."

Once you have completed changes to your icons, you will need to create an image strip to recreate the deleted files.



Open your Notepad editor - In this example Notepad++ is selected to replace the black colour ("#000000 Color Hex Black") hook in all 227 icon files to the colour of your choice in a few seconds. You may open the "*Colors.ini*" file in your theme folder as in this example with Notepad++

In Notepad++, go to "Search -> Replace"

Click on the Find in Files tab

Select your the of your new theme folder (e.g. "*My-Material*").

In the "*Find what :*" field enter the hex value for black colour, i.e. "#000000"

In the "*Replace with :*" field enter the hex value for the colour of your choice. In this example, the hex value for blue colour, i.e. "#0000ff" is selected.


Blue Color Codes
https://html-color.codes/blue
Blue Color Codes
There are plenty of shades of blue, which all contain their own unique color attributes. A few examples of named color codes that could be considered a shade of blue are: palatinate blue, midnight blue, picton blue, sapphire and powder blue!
A List of Blue Shades
Blue
#0000ff | rgb(0,0,255)
Light Blue
#add8e6 | rgb(173,216,230)
Light Steel Blue
#b0c4de | rgb(176,196,222)
Light Sky Blue
#87cefa | rgb(135,206,250)


Find in Files
Find
Replace
Find in Files
Find in Projects
Mark
Find what : #000000
Replace with : #0000ff
Filters : *.*
Directory : C:\osfinancials5\bin\themes\My-Material
Find All
Replace in Files
Close
Follow current doc.
In all sub-folders
In hidden folders
Match whole word only
Match case
Search Mode
Normal
Extended (\n, \r, \t, \0, \x...)
Regular expression
. matches newline
Transparency
On losing focus
Always

Click on the Find All button to check the number of files to be changed. This should list 227 icon files with the *.svg file extension.



Click on the Replace in Files button. This will replace all of the 227 icon files in one shot.



When you open your new theme folder in your file explorer, all the of the 227 icon files will be displayed in

the new colour as your chosen colour. In this example, blue was used.



Please note that certain icons in the osFinancials interface will remain unchanged to ensure their visibility and distinctiveness. These include:

1. *Inactive icons:*
   - *BWBatch.svg*
   - *BWInvoice.svg*
   - *NwOpenLink.svg*
   - *BwRecon.svg*
2. *Message dialog icons:*
   - *Confirmation.svg*
   - *Error.svg*
   - *No.svg*
   - *Warning.svg*
   - *yes.svg*
   - *yestoall.svg*
3. *TCASHlogo.svg*

These icons are intentionally retained in their original form and colour to maintain their specific purpose and recognition within the osFinancials5/TurboCASH5 interface.

Once the themes is changed, and displays the correct colour for your liking, you may start osFinancials5 and select your new theme for example"*My-Material*" in the Theme menu on the Setup ribbon.

Your new colour icons should display at this stage, in the osFinancials interface.



The last important step to do, is to create an image strip. To do this, select Tools → Customise language on the Setup ribbon and click on the Create image strip button.



A message will be displayed:

> "Creating new image strip loader"

Click OK.

Close the "*Customize Languages*" screen.

After completing these steps, the eight deleted files (4 *.dfm file types: BatchEnabledButtons.dfm, ilbandlarge.dfm, ilbandsmall.dfm, ImageList1.dfm, and 4 *.fst file types: BatchEnabledButtons.fst, ilbandlarge.fst, ilbandsmall.fst, ImageList1.fst) will be recreated.

Created with the Standard Edition of HelpNDoc: How to Protect Your PDFs with Encryption and Passwords

Languages

Multi-Language accounts - Manual - Shop - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

To display the interface of osFinancials5/TurboCASH5 in the default "English" language, select the "HANDYMAN" Set of Books and click on the Open button.

Should you have selected the incorrect language when installing osFinancials5/TurboCASH5, you may select the language applicable to your country.

The osFinancials5/TurboCASH5 interface will display in the selected language in Switch language (Start ribbon). Depending on the Set of Books template downloaded when Creating a Set of Books (Creation wizard); or downloaded from the Product information → Technical information → Databases page on the osFinancials website); osFinancials5/TurboCASH5 will automatically display the interface language of the language file which have already been linked to each Set of Books. (Setup → Access control).

When opening a Set of Books, it will automatically load the language file. All screens, reports and layout files are translatable via the language files.

The following options are available to change the language:

1. Set the global language: Switch language (Start ribbon) and select the correct language for your country, state, province, etc.
2. Set the language for a specific Set of Books: Setup → Access control - System language field on the Standard security tab (Setup ribbon).
3. Languages may also be customised in Tools → Customise language (Setup ribbon).

You may customise any language for your own personal or industry specific needs.

List of all available languages

Language files		
English	*Spanish*	*French*
English (Default language file)	*Español*	*Français*
American	*es-Argentina*	*fr-Benin*
Australia, en-Australia	*es-Chile*	*fr-Burkina*

en-Bangladesh	es-Ecuador	fr-C-African-Rep
en-Barbados	es-ElSalvador	fr-Cameroun
en-Belize	es-Honduras	fr-Comores
en-Botswana	es-Mexico	fr-France
en-Cameroon	es-Panama	fr-Gabon
en-Ireland	es-Paraguay	fr-Guinee
en-Isle-of-Man	es-Peru	fr-Haiti
en-Lesotho	es-Spain	fr-Mali
en-Malawi	es-Uruguay	fr-Maurice
en-Malta	es-Venezuela	fr-Niger
en-Mauritius	Other languages	fr-Rep-Congo
en-Namibia	Afrikaans	fr-Rwanda
en-New-Zealand	de-German	fr-Senegal
en-Rwanda	German	fr-Tchad
en-South-Africa	et-Estonian	fr-Vanuatu
en-Tanzania	hr-Bosnia	Portuguese
en-Tonga	hr-Croatia	Portuguese

en-Trinidad	*hr-Montenegro*	*pt-Angola*
en-Uganda	*id-Indonesia*	*pt-Brazil*
en-UK	*it-Italian*	*pt-Cabo Verde*
en-Zambia	*lt-Lithuanian*	*pt-Guiné-Bissau*
en-Zimbabwe	*nl-Nederlands*	*pt-Moçambique*
	sl-Slovenian	*pt-Portugal*
Turkish	*sv-Sweden*	*pt-São Tomé*
tr-Cyprus	*sv-Swedish*	*pt-Timor Leste*
tr-Marcedonia	*sw-Swahili*	
tr-Turkey	*xh-Xhosa*	
Other languages		
el-Cyprus		
el-Greece		
th-Thai		

ar-Arabic

List of English Tax terminology

English (Default language file) refers to Tax. If you select the following English languages, it will

refer to the following tax terminology:

English VAT	English GST	English Sales tax / Consumption tax
en-Bangladesh	en-Australia	en-American (Sales tax)
en-Barbados	en-Belize	en-Tonga (Consumption tax)
en-Botswana	en-New-Zealand	
en-Cameroon		
en-Ireland		
en-Isle-of-Man		
en-Lesotho		
en-Malawi		
en-Malta		
en-Mauritius		
en-Namibia		
en-Rwanda		
en-South-Africa		
en-Tanzania		
en-Trinidad		
en-Uganda		

en-UK

en-Zambia

en-Zimbabwe

Created with the Standard Edition of HelpNDoc: Save time and frustration with HelpNDoc's WinHelp HLP to CHM conversion feature

Switch language

When you install and start osFinancials5/TurboCASH5 for the first time, the select a Language window is displayed on which you may select the language and country. If you have selected the incorrect language / country, when launching osFinancials5/TurboCASH5 for the first time, you may change it.

English - This is the driver language file.

You may customise any language for your own personal or industry specific needs.

To choose a language:

1. On the Start ribbon, select Switch language. The "*Choose a language*" screen is displayed:



2. Select the Language of your choice.

3. Click on the OK button. A progress indicator at the bottom of the screen will display the progress. When the process is completed, the ribbons and the screens will be displayed in the selected language.

Users in Access control can have their language set in the "System lang" field. Upon logging into osFinancials5/TurboCASH5, the user interface and reports will be displayed in the language assigned to that user.

To access the Customise language option:

1. *Right-click in any area of the list of languages (on the "Choose a language" screen).*
2. *Click on the Customize context menu option. This will directly access the selected (highlighted) language on the "Customize Languages" screen (Tools → Customise language menu on the Setup ribbon).*

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Customise language

---

osFinancials5/TurboCASH5 offers the flexibility to customise the language used within the software to cater

to specific industries and regional requirements. This customisation allows businesses to tailor the terminologies and labels used in osFinancials5/TurboCASH5 to match their industry jargon, corporate preferences, and local language requirements.

What are the options to customise languages?

Here's how you can customise the language in osFinancials5/TurboCASH5:

1. Editing labels and terminologies: osFinancials5/TurboCASH5 allows you to modify the labels and terminologies used for various fields and functions within osFinancials5/TurboCASH5. For example, you can change the label "*Stock*" to "*Inventory*" if that's the term commonly used in your industry. Similarly, you can edit labels for accounts, transaction types, business processes, and more to align with your industry's specific terms.
2. Customising types: In addition to editing labels, osFinancials5/TurboCASH5 also allows you to customise field types to suit your industry's needs. You may have specific data requirements relevant to your industry that can be modified to streamline data entry and reporting. For example, the default document types in osFinancials5/TurboCASH5 is invoice, credit note and quote for sales documents and purchase, supplier return and order for purchase documents. For example, you can change the Document type for "*Quote*" to "*Estimates*" if that's the term commonly used in your country and industry.
3. Localising for country-specific languages: osFinancials supports various languages to cater to users from different regions. You can choose the language that best matches your country's official language or the language preferred by your employees. This localisation enhances user experience and ensures clear communication within osFinancials5/TurboCASH5.
4. Tax regime customisation: Tax regimes can vary significantly between countries and industries. In osFinancials5/TurboCASH5, you can configure tax settings based on your specific tax requirements, such as Value Added Tax (VAT), Goods and Services Tax (GST), Sales Tax rates, tax codes, tax reporting, and compliance rules.

These changes will customise the user interface elements like buttons, menus, and navigation. Adjusting the interface layout to match your industry's workflow can improve productivity and reduce the learning curve for new users. These changes will also be reflected in the reports and the translatable document layout files.

By customizing the language and settings in osFinancials5/TurboCASH5, businesses can enhance usability, accuracy, and compliance with industry-specific requirements. This customization empowers companies to effectively manage financial data and gain valuable insights for better decision-making and financial control.

What is affected by customising the language?

When you customise the language in osFinancials5/TurboCASH5, the changes you make to labels, field types, and document types will be reflected not only in the user interface but also in the reports and translatable document layout files. This ensures consistency throughout the entire system, providing a seamless experience for users and stakeholders.

Let's explore how these changes are reflected:

1. User interface: The customised language will be visible in the user interface of osFinancials5/TurboCASH5, including menus, buttons, input fields, and other elements. The modified labels and field types will appear according to your preferences, making it easier for users to interact with the software.

2. Reports: Any customisations made to the language, including changes to labels and field types, will be reflected in the reports generated by osFinancials5/TurboCASH5. This means that report headers, column names, and other relevant information will be displayed in the customised language, making the reports more user-friendly and relevant to your business.

3. Translatable document layout files: In osFinancials5/TurboCASH5, document layout files such as the "*Layout file, Document layout file", and the "Document layout (15-codes) file*" are designed to be versatile and support various types of documents such as invoices, credit notes, quotes, purchases, supplier returns, orders. Changing the document types in Tools → Customise language - Types tab on the Setup ribbon, will print as the Document name when these documents are printed. For example, when you make changes to document types, such as renaming "*Quotes*" to "*Estimates*," these changes will be automatically reflected in the respective document layouts.

   The the customised language will be visible in the these mentioned documents types, including the "*Delivery notes"* and "*Point-of-Sale layout files*". These layout files provide the flexibility to customise the appearance and content of documents such as invoices, credit notes, quotes, purchases, supplier returns, orders, delivery notes, and more. osFinancials5/TurboCASH5 allows you to customise the layout of documents such as invoices, quotes, purchase orders, etc. This ensures that the documents generated by osFinancials5/TurboCASH5 use the language you have customized, improving consistency and professionalism in your business communications.

By having consistent language across the entire osFinancials system, you create a more cohesive and efficient financial management experience. Customising the language to align with your industry's terminology and business practices allows your team to work seamlessly with the software, leading to improved productivity and accuracy in financial transactions and reporting.

How to set your customised language file as default?

In osFinancials5/TurboCASH5, you have the option to set or change the default language or your own customized language for the Set of Books through the Switch language option on the Start ribbon. This enables you to have your preferred language automatically loaded whenever you open the Set of Books. After selecting the desired language, save the changes. osFinancials5/TurboCASH5 will now use the selected language as the default whenever you open the Set of Books.

By setting your preferred language or customising the language settings through the Switch language option on the Start ribbon, osFinancials5/TurboCASH5 will display all labels, terminologies, and interface elements, reports and document layout files in the selected language whenever you access your Set of Books. This makes it more convenient and user-friendly, especially when you have customized the language to suit your industry or regional requirements.

How to set language files as default for users?

Users in Access control (Setup → Access control menu on the Setup ribbon) can have their language set in the "*System lang*" field. Upon logging into osFinancials5/TurboCASH5, the user interface and reports will be displayed in the language assigned to that user.

Important notes on Customising language files

The language files in osFinancials5/TurboCASH5 are stored in the **.dfm* file type, and they can be found in the "*...\Bin\Languages*" directory or another directory where osFinancials5/TurboCASH5 is installed. When you first launch osFinancials5/TurboCASH5 after installation, it will automatically display the default language based on the country and language of the Set of Books you selected to open.

However, if you want to use a different language, you can switch to any of the available languages by going to Switch language in the Start ribbon. This allows you to choose from a list of supported languages, including English for various countries, Afrikaans, and others.

When editing language files, it is essential to exercise caution to avoid modifying existing labels in the master language ("English.dfm" file) or an existing layout file. Instead, create a new name for the language file you wish to edit. This ensures that the original language files remain intact, and your customizations are separate and can be easily managed.

If you create or edit a language file with your customisations, it is advisable to save a copy of the language file elsewhere on your system. This precautionary step ensures that you have a backup in case you install an update of osFinancials5/TurboCASH5, uninstall osFinancials5/TurboCASH5 or install new versions that

might not include your customised language file.

Overall, osFinancials provides a straightforward way to switch between different languages and allows users to customize the language settings to match their preferences or regional requirements. By using this feature, businesses can operate efficiently and effectively in their preferred language, making the software more user-friendly and accessible.

Structure of language labels

The following series of LabelID's have been reserved for the following:

- 901000 - Plugins - Subscriptions
- 902000 - Plugins - Price agreements
- 903000 - Multimedia
- 906000 - Reportman reports and document layout files
- 1000000 - Welcome screen (discontinued)

Create, Edit language files

To create, Edit or Translate Language Labels or Descriptions:

1. On the Setup ribbon, select Tools → Customise language.



2. The options are as follows:

   a) Language - You may select any of the available languages from the drop-down list. The selected language will be displayed on the list.

   b) Create - If you click on the Create button, new language will be displayed in this field. You may then enter the name for your own language.

   c) Reload using code page - see http://en.wikipedia.org/wiki/Code_page for more information. Some codes that need to be entered for languages, are:

      § 720 – Arabic

      § 737 – Greek

      § 775 – Estonian, Lithuanian and Latvian

      § 855 – Cyrillic

      § 857 – Turkish

      § 860 – Portuguese

      § 861 – Icelandic

      § 862 – Hebrew

- § 863 – French (Quebec French)
- § 865 – Danish/Norwegian
- § 866 – Cyrillic
- § 869 – Greek
- § 874 – Thai

d) Unify - To be advised.

e) ID - The number records of the descriptions that is used by the osFinancials5/TurboCASH5. (This is the label's record number in the Language table.)

f) Message/text - Displays the descriptions of the selected language labels.

g) Default (English) - Displays the original default English. This is the master file, and it is recommended that it should not be amended in any way.

h) Translation (Edit) - You may type in or edit your own translation in this field.

i) Search in - Select to search in the current language or in the English language. You then need to type the word or phrase to search for. You may also further refine your search, to find unchanged words or phrases, to view the unedited labels only.

The number of records matching your search text will be displayed.

You may also click on the Types tab to view the translations of the selected message text (label) in other available languages.

j) Search and Replace - Enter a word or phrase to find. You then need to enter a word or phrase to edit (change the label or message text), and click on the Go button to replace all the words or phrases in the language file.

k) E-mail your language file to us - Once finished creating or editing your language file, click to send the language file to the osFinancials5/TurboCASH5 developers. This will automatically launch your system's default e-mail program and attach your language file in the e-mail message. The developers will then add your language file in the next osFinancials5/TurboCASH5 release.

l) Create image strip - This will create a new image strip for fast loading of icons. For fast

loading images, osFinancials5/TurboCASH5 uses the *.fst (i.e. "*BatchEnabledButtons.fst, ilbandlarge.fst, ilbandsmall.fst*" and "*ImageList1.fst*") files. If you want to edit the icons in a specific theme, remove these files. After editing the icons, you need to click on the Create image strip button, so the icons are loaded from the files again.

m) Add missing from Eng translation - If your language file has less records than the number of records in the English language files, (for example if the English language file has 4061 records; and the language file you are editing or translating has less records than 4071); click on this button to add the missing English labels to your translation file.

3. Click on the Types tab to edit the translations of the Descriptions in the Types table. You may need to edit the following types:

a) Account types (i.e. General ledger, Bank, Tax, Debtor and Creditor).

b) Document types (i.e. Invoice, Credit notes, Purchases, Supplier returns, Quotes and Orders) and Adjustments.

c) Statement and Remittance.

d) Groups names / descriptions (Setup → Groups) (i.e. Account group 1 / 2, Debtor group 1 / 2, Creditor group 1 / 2, Stock group 1 / 2, Document group 1 / 2, Payment type group, Salesperson group, Projects group, Cost Centre 1/ 2 and Languages for Stock.

e) Colour descriptions -

These types have been removed from the Sets of Books in the osFinancials4 Build 1093 installation.

This is not applicable to TurboCASH4 and osFinancials5 series (i.e. Classic, Brilliant, Pastel, Keywest, NewSA and Windows Default).

f) Paper types - Pre-printed, Plain A4, Plain eyeline, Forty and Till slip.

g) User report row types -

This is not applicable to the osFinancials4, osFinancials5 or TurboCASH5 or TurboCASH5.2 (i.e. Account, Blank, Column line, Group 1, Group 1 Detail, Group 2, Group 2 Detail, Single line, Text, Budget, Formula, Last year and This year).

h) Stock - Stock item, Comment, Serial number and Financial entry.

4. Click on the Rest tab to change the Description of Zero account. This is usually the "*Empty*" option in

Lookups, lists, etc. displaying in osFinancials5/TurboCASH5. It is also used for the Groups empty account. This is usually the Unallocated option in Lookups, lists, etc. displaying in osFinancials5/TurboCASH5.

5. Once finished, click on the Close button.

It is strongly recommended that the label, which is edited or entered, is not longer than the "Default English" labels' length. If your label is too long, it may cause some options in the program not to function or display properly. Do not use the Delete button to remove any of the existing edited labels.

E-Mail message file to be included in next release

To E-mail your language file to us

1. Enter your E-mail address and Name on the "*Customize language*" screen.
2. Click on the Email your language file to us button. Your system's default email program will be launched.
3. Check that it is the correct Language file. You may need to enter any content in the message field, if necessary.
4. Click on the Send button of your E-Mail program.

Edit Language files externally

You may export the Language file and edit it in a spreadsheet. Tab Delimited Export and Import -

To create an export file, click on the ExportFromTab button.

When saving the edited file in OpenOffice, select the options save as text and set txt delimiter to empty.

Once the file is saved, you may click on the ImportFromTab button to import the edited text.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Customising terminology for VAT/GST/Sales tax

The language associated with each Set of Books determines the specific tax labels used to cater to different countries or tax regulations. For instance, en-UK and en-South Africa use terminology related to VAT, while in South Africa, Afrikaans refers to BTW. Australia and New Zealand use GST-related

terminology, whereas the United States and Canada employ Sales tax terms.

These tax-related labels are visible within the osFinancials5/TurboCASH5 interface when you access a Set of Books. They are also present in reports and document layout files generated by the system.

To adapt the tax terminology to suit your country, jurisdiction, and industry, you can customize and modify the tax-related labels via the *"Customize Languages*" screen. This screen is accessible through the Tools → Customise Language menu on the Setup ribbon.

You may also find it helpful to utilize the search options available. This enables you to search for a specific label either in the currently active language file you're editing or in the default "*English*" language file. This assists you in identifying and modifying specific text to better suit your requirements.

For your convenience, the default "*English*" language file contains a total of 82 tax-related labels, which are listed in the table below:

LabelID	*Description for TAX*
33	*Tax account*
63	*&Tax*
202	*Tax reference*
219	*Input tax*
220	*Output tax*
254	*Tax accounts*
314	*Tax method*
317	*Tax reg. no.*
390	*Tax report options*
391	*Tax code*
407	*Show tax transactions*
409	*Show tax separately*
469	*This is not a tax account!*
529	*This tax account has transactions! Do you wish to transfer the transactions to another tax account?*

609 *Tax*

687 *Tax excluded*

688 *Tax included*

750 *Tax Invoice no.*

816 *May not have a tax type for a debtor or creditor in the payments based system!*

821 *The payments based method of tax treats tax purely on a cash basis. Tax is payable to the revenue authorities only when it is received from the customer. Do you wish to continue?*

1130 *Customer tax ref.*

1135 *TAX registration*

1138 *Tax amount*

1789 *Tax accounts*

1863 *Tax*

1925 *Tax*

1982 *No tax*

1985 *Remember tax on contra account*

2037 *TAX INVOICE*

2043 *TAX-AMT*

2051 **Indicates non-TAX item*

2177 *Tax amount found but tax account is deleted!*

2203 *Edit tax*

3027 *Use default tax*

3028 *Default tax account*

3035 *Use link tax*

3036 *Link tax*

3037 *Contra tax*

3050 *Use default tax*

3053 *Use link tax*

3054 *Link tax*

3055 *Contra tax*

3160 *Merge items per tax on ledger*

3169 *Strict tax on account*

3178 *Link tax*

3294 *Show tax in documents*

3297 *Hide this tax*

3345 *Consolidating lines and using tax will mess up your tax report! Please make sure you do not use tax or do not consolidate lines!*

3352 *Sales, Purchase, Cost of sales and Tax accounts*

3409 *Postal code / tax id / reg. no. lookup*

3410 *Dutch Tax plugin*

3438 *Belgium Tax Returns*

3465 *Tax classes*

3466 *Tax class*

3675 *Tax list debtor with tax id*

3735 *You are putting profit/loss on ledger with tax! This will messup tax reports! Do you wish to continue?*

903147 *Update Dochead FTaxAmt*

903154 *Correct Incl. Excl. Tax amount (Reverse bug)*

906014 POS Tax Invoice

906020 Tax

906069 Your tax reference

906084 Document tax

906085 Tax on tax account

906105 Tax per period

906248 Invoice No Tax (no codes)

906249 Credit note No Tax (no codes)

906250 Quote No Tax (no codes)

906251 Purchase No Tax (no codes)

906252 Supplier return No Tax (no codes)

906253 Order No Tax (no codes)

906254 Invoice No Tax (15 code)

906255 Credit note No Tax (15 code)

906256 Quote No Tax (15 code)

906257 Purchase No Tax (15 code)

906258 Supplier return No Tax (15 code)

906259 Order No Tax (15 code)

906265 Tax report

906280 Ledger and tax

906339 Tax and company registration numbers

906550 Tax report - Reference / Document no.

906553 Tax list creditor with tax id

906583 Tax codes - Tax rates

906589 NO-TAX Layout file

906590 NO-TAX Document layout

906591 NO-TAX Document layout (15-code)

If '%s ' is included in a label description in the language file, please refrain from translating this. This placeholder is reserved for specific data that will be dynamically populated within the label. For example, 'Cur : %s Quote : %s Order : %s Exp : %s' signifies that the current, quote, order, and expected quantities will be inserted and displayed within the program.

If you come across "<@APPNAME@>" within a label description, be aware that it will be replaced with "osFinancials" in the program's interface. In your customized language file, which you are currently editing, you have the option to substitute "<@APPNAME@>" with "osFinancials" to accurately reflect the application's name within the interface.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Customising document type terminology - Invoice

The language associated with each Set of Books determines the specific labels used to cater to different countries or tax regulations. In most languages, the term *'Invoice'* or its equivalent will be displayed. For instance, en-UK and en-South Africa use terminology related to *'Invoice*,' while in South Africa, Afrikaans refers to *'Faktuur'* or *'Fakture'*.

These invoice-related labels are visible within the osFinancials5/TurboCASH5 interface when you access a Set of Books. They are also present in reports and document layout files generated by the system.

To adapt the invoice terminology to suit your country, jurisdiction, and industry, you can customize and modify the invoice-related labels via the "*Customize Languages*" screen. This screen is accessible through the Tools → Customise Language menu on the Setup ribbon.

You may also find it helpful to utilize the search options available. This enables you to search for a specific label either in the currently active language file you're editing or in the default "*English*" language file. This assists you in identifying and modifying specific text to better suit your requirements.

Document type names for layout files that support all document types

osFinancials5/TurboCASH5 supports a single document layout file which utilizes translatable expressions facilitated by language file settings. They dynamically display the appropriate document type names such as "Invoice," "Credit note," "Quote," "Purchase," "Supplier return," or "Order" based on the specific document being printed. The document types are sourced from the "TYPES.SDESCRIPTION" expressions within the layout.

To change the document type names, you need to change the descriptions on the Types tab of the "Customize Languages" screen (accessible from the Tools → Customise Language menu on the Setup ribbon).

Preview of available document layout file samples that support all document types

To assist in choosing a layout file for your needs, you may preview some screenshots of document layout files:

1. *Translatable Document Layout Files with Dynamic Document Types*
    - *"Layout File"*
    - *"Document Layout"*
    - *"Document Layout (15 Code)"*
2. *Translatable Document Layout Files with Dynamic Document Types without VAT/GST/Sales Tax*
    - *"NO-TAX Layout File"*
    - *"NO-TAX Document Layout"*
    - *"NO-TAX Document Layout (15 code)"*

If you are not registered for VAT/GST/Sales tax or have chosen not to opt for voluntary registration, these layout files exclude VAT/GST/Sales tax information. They also dynamically display the appropriate document type names based on the specific type of document being printed.

For your convenience, the default "*English*" language file contains a total of 110 invoice-related labels, which are listed in the table below:

LabelID	*Description for Invoice*
26	*Repeating &invoices*
39	*Delete invoices*
48	*&Invoices*
60	*&Invoices*

78 &Invoice listing

86 &Invoiced details

87 &Invoiced summary

162 Invoice history

165 Invoice

222 Apply invoice discount

229 Last invoice

230 From invoice

231 To invoice

234 Invoice no.

284 From invoice no.

285 To invoice no.

300 Invoices

321 Next invoice no.

322 Invoice batch

324 Invoice heading

325 Invoice message

405 Update invoices

495 Error posting invoice! Please restore backup!

505 Do you wish to print this Invoice now?

508 Are you sure you want to clear all the entries in this Invoice?

587 Invoice entry

646 Invoice total

678 *There is no invoice to print!*

750 *Tax Invoice no.*

1110 *Invoice based*

1133 *Invoice accepted*

1145 *Invoice address*

1223 *Quotes to convert to invoice*

1270 *POS Invoice*

1410 *&Use invoice messages*

1714 *Point-of-Sale invoice entry*

1721 *New invoice*

1736 *Do you want to close and cancel this invoice now?*

1738 *This will close the invoice entry screen and post all POS invoices for ...*

1741 *Closing shift and posting all invoices*

1751 *&Reprint last invoice*

1886 *Invoice history*

1887 *Invoices to repeat*

1889 *Search by invoice number*

1895 *Set new invoice as repeating*

2036 *<@APPNAME@> Invoice*

2037 *TAX INVOICE*

2056 *Use invoice print*

2098 *You still have amount receive. %s Cannot leave unpaid amount for POS invoice!*

2155 *Invoice*

2156 *Invoice totals :*

2167 *Search by invoice no.*

2198 *Invoice/Accounting*

2858 *Repeating invoices*

2880 *Please save this repeating invoice first! After reopening you can add clients to the invoice.*

2883 *Repeating invoice*

2884 *Invoice date*

2987 *Show invoice no.*

3020 *Convert invoice to order*

3096 *Create invoices for hours*

3098 *Include unposted invoices*

3159 *Merge invoice to orders*

3170 *Post warning per invoice*

3304 *New invoice*

3308 *Reopen invoice*

3570 *Invoices per period*

20070 *Customer invoice*

20071 *Invoice stock item*

20072 *Stock item invoice*

901005 *Invoice in days before subscription date*

901506 *Please close all open invoices first!*

903157 *Delete all invoices*

903159 *Remove zero invoices*

906001 The next subscription will start soon. The invoice for the new period will follow shortly.

906014 POS Tax Invoice

906125 Posted invoices

906126 Unposted invoices

906155 Invoices per period - Quantities

906156 Invoices per period - Amount

906157 Invoices per period - Debtor group 1

906158 Invoices per period - Debtor group 2

906159 Invoices per period - Document group 1

906165 Invoices per period - Document group 2

906166 Invoices per period - Salesperson

906170 Graph - Invoices per week - Quantities

906171 Graph - Invoices per week - Amount

906190 Invoice test

906191 Invoice English (15 code)

906192 Invoice Bank details (no codes)

906193 Invoice Bank details (15 code)

906194 Invoice (no codes)

906200 Invoice (10 code)

906206 Invoice (15 code)

906212 Invoice A4 (no codes)

906218 Invoice A4 (10 code)

906224 Invoice A4 (15 code)

906230 Invoice A4 Plain (no codes)

906236 Invoice A4 Plain (10 code)

906242 Invoice A4 Plain (15 code)

906248 Invoice No Tax (no codes)

906254 Invoice No Tax (15 code)

906260 Invoice Bank details (10 code)

906261 Invoice English (10 code)

906262 Invoice English (no codes)

906567 Graph - Invoices per month - Quantities

906568 Graph - Invoices per month - Amount

906569 Graph - Invoices - Credit notes per month - Quantities

906570 Graph - Invoices - Credit notes per month - Amount

906579 Graph - Invoices - Credit notes per week - Quantities

906580 Graph - Invoices - Credit notes per week - Amount

If '%s ' is included in a label description in the language file, please refrain from translating this. This placeholder is reserved for specific data that will be dynamically populated within the label. For example, 'Cur : %s Quote : %s Order : %s Exp : %s' signifies that the current, quote, order, and expected quantities will be inserted and displayed within the program.

If you come across "<@APPNAME@>" within a label description, be aware that it will be replaced with "osFinancials" in the program's interface. In your customized language file, which you are currently editing, you have the option to substitute "<@APPNAME@>" with "osFinancials" to accurately reflect the application's name within the interface.

Created with the Standard Edition of HelpNDoc: Why Microsoft Word Isn't Cut Out for Documentation: The Benefits of a Help Authoring Tool

Customising document type terminology - Credit note

The language associated with each Set of Books determines the specific labels used to cater to different countries or tax regulations. In most languages, the term *'Credit note'* or its equivalent will be displayed. For instance, en-UK and en-South Africa use terminology related to *'Credit note'*, while in South Africa, Afrikaans refers to *'Kredietnota'* or *'Kredietnotas'*.

These credit note-related labels are visible within the osFinancials5/TurboCASH5 interface when you access a Set of Books. They are also present in reports and document layout files generated by the system.

To adapt the credit note terminology to suit your country, jurisdiction, and industry, you can customize and modify the credit note-related labels via the "Customize Languages" screen. This screen is accessible through the Tools → Customise Language menu on the Setup ribbon.

You may also find it helpful to utilize the search options available. This enables you to search for a specific label either in the currently active language file you're editing or in the default "*English*" language file. This assists you in identifying and modifying specific text to better suit your requirements.

Document type names for layout files that support all document types

osFinancials5/TurboCASH5 supports a single document layout file which utilizes translatable expressions facilitated by language file settings. They dynamically display the appropriate document type names such as "Invoice," "Credit note," "Quote," "Purchase," "Supplier return," or "Order" based on the specific document being printed. The document types are sourced from the "TYPES.SDESCRIPTION" expressions within the layout.

To change the document type names, you need to change the descriptions on the Types tab of the "Customize Languages" screen (accessible from the Tools → Customise Language menu on the Setup ribbon).

Preview of available document layout file samples that support all document types

To assist in choosing a layout file for your needs, you may preview some screenshots of document layout files:

1. *Translatable Document Layout Files with Dynamic Document Types*
    - *"Layout File"*
    - *"Document Layout"*
    - *"Document Layout (15 Code)"*
2. *Translatable Document Layout Files with Dynamic Document Types without VAT/GST/Sales Tax*
    - *"NO-TAX Layout File"*

- *"NO-TAX Document Layout"*
- *"NO-TAX Document Layout (15 code)"*

If you are not registered for VAT/GST/Sales tax or have chosen not to opt for voluntary registration, these layout files exclude VAT/GST/Sales tax information. They also dynamically display the appropriate document type names based on the specific type of document being printed.

For your convenience, the default "*English*" language file contains a total of 52 credit note-related labels, which are listed in the table below:

LabelID	*Description for Credit note*
47	*&Credit notes*
77	*&Credit note listing*
299	*Credit note no.*
326	*Next credit note no.*
327	*Credit note batch*
328	*Credit note heading*
329	*Credit note message*
670	*Credit note entry*
671	*F10: Delete credit note*
673	*Do you wish to print this credit note now?*
674	*Update credit notes*
675	*From credit note*
676	*To credit note*
689	*Credit note history*
695	*Delete credit notes*
706	*Credit notes*

758 *Credit note no.*

1146 *Credit note accepted*

2152 *Credit note*

2157 *Credit note totals :*

3181 *Convert to credit note / supplier return*

3569 *Credit notes per period*

906024 *Credit note date*

906121 *Credit notes per period*

906127 *Posted credit notes*

906128 *Unposted credit notes*

906195 *Credit note (no codes)*

906201 *Credit note (10 code)*

906207 *Credit note (15 code)*

906213 *Credit note A4 (no codes)*

906219 *Credit note A4 (10 code)*

906225 *Credit note A4 (15 code)*

906231 *Credit note A4 Plain (no codes)*

906237 *Credit note A4 Plain (10 code)*

906243 *Credit note A4 Plain (15 code)*

906249 *Credit note No Tax (no codes)*

906255 *Credit note No Tax (15 code)*

906291 *Credit notes per period - Debtor group 1*

906292 *Credit notes per period - Debtor group 2*

906293 Credit notes per period - Document group 1

906294 Credit notes per period - Document group 2

906295 Credit notes per period - Salesperson

906311 Credit notes per period - Quantities

906312 Credit notes per period - Amount

906319 Graph - Credit notes per week - Quantities

906320 Graph - Credit notes per week - Amount

906565 Graph - Credit notes per month - Quantities

906566 Graph - Credit notes per month - Amount

906569 Graph - Invoices - Credit notes per month - Quantities

906570 Graph - Invoices - Credit notes per month - Amount

906579 Graph - Invoices - Credit notes per week - Quantities

906580 Graph - Invoices - Credit notes per week - Amount

If '%s ' is included in a label description in the language file, please refrain from translating this. This placeholder is reserved for specific data that will be dynamically populated within the label. For example, 'Cur : %s Quote : %s Order : %s Exp : %s' signifies that the current, quote, order, and expected quantities will be inserted and displayed within the program.

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Customising document type terminology - Quote

The language associated with each Set of Books determines the specific labels used to cater to different countries or tax regulations. In most languages, the term *'Quote'* or its equivalent will be displayed. For instance, en-UK and en-South Africa use terminology related to *'Quote'*, while in South Africa, Afrikaans refers to *'Kwotasie'* or *'Kwotasies'*. The United States and Canada employ the term *'Estimates'*.

These quote-related labels are visible within the osFinancials5/TurboCASH5 interface when you access a

Set of Books. They are also present in reports and document layout files generated by the system.

To adapt the quote terminology to suit your country, jurisdiction, and industry, you can customize and modify the quote-related labels via the "Customize Languages" screen. This screen is accessible through the Tools → Customise Language menu on the Setup ribbon.

You may also find it helpful to utilize the search options available. This enables you to search for a specific label either in the currently active language file you're editing or in the default "*English*" language file. This assists you in identifying and modifying specific text to better suit your requirements.

Document type names for layout files that support all document types

osFinancials5/TurboCASH5 supports a single document layout file which utilizes translatable expressions facilitated by language file settings. They dynamically display the appropriate document type names such as "Invoice," "Credit note," "Quote," "Purchase," "Supplier return," or "Order" based on the specific document being printed. The document types are sourced from the "TYPES.SDESCRIPTION" expressions within the layout.

To change the document type names, you need to change the descriptions on the Types tab of the "Customize Languages" screen (accessible from the Tools → Customise Language menu on the Setup ribbon).

Preview of available document layout file samples that support all document types

To assist in choosing a layout file for your needs, you may preview some screenshots of document layout files:

1. *Translatable Document Layout Files with Dynamic Document Types*
    - *"Layout File"*
    - *"Document Layout"*
    - *"Document Layout (15 Code)"*
2. *Translatable Document Layout Files with Dynamic Document Types without VAT/GST/Sales Tax*
    - *"NO-TAX Layout File"*
    - *"NO-TAX Document Layout"*
    - *"NO-TAX Document Layout (15 code)"*

If you are not registered for VAT/GST/Sales tax or have chosen not to opt for voluntary registration, these layout files exclude VAT/GST/Sales tax information. They also dynamically display the appropriate document type names based on the specific type of document being printed.

For your convenience, the default "*English*" language file contains a total of 48 quote-related labels, which are listed in the table below:

LabelID	Description for Quote
341	Next quote no.
342	Quote heading
343	Quote message
418	Quotes
692	Quote history
710	Do you wish to print this quote?
751	Quote no.
771	Quote no.
772	From quote
839	&Quotes
1018	Delete quotes
1148	Quote accepted
1223	Quotes to convert to invoice
1870	Quotes
1874	Confirm quotes and orders
2169	Quote
2983	Quotes / Orders
3079	Quote(s) generated!
3133	If you want to reserve some stock for sales this field will be deducted from current stock levels in a quote!
3139	Cur : %s Quote : %s Order : %s Exp : %s
3330	Quote
3568	Quotes per period

906006 Quote date

906034 Outstanding quotes

906133 Confirmed quotes

906134 Unconfirmed quotes

906196 Quote (no codes)

906202 Quote (10 code)

906208 Quote (15 code)

906214 Quote A4 (no codes)

906220 Quote A4 (10 code)

906226 Quote A4 (15 code)

906232 Quote A4 Plain (no codes)

906238 Quote A4 Plain (10 code)

906244 Quote A4 Plain (15 code)

906250 Quote No Tax (no codes)

906256 Quote No Tax (15 code)

906301 Quotes per period - Debtor group 1

906302 Quotes per period - Debtor group 2

906303 Quotes per period - Document group 1

906304 Quotes per period - Document group 2

906305 Quotes per period - Salesperson

906315 Quotes per period - Quantities

906316 Quotes per period - Amount

906323 Graph - Quotes per week - Quantities

906324 Graph - Quotes per week - Amount

906563 Graph - Quotes per month - Quantities

906564 Graph - Quotes per month - Amount

If *'%s* ' is included in a label description in the language file, please refrain from translating this. This placeholder is reserved for specific data that will be dynamically populated within the label. For example, *'Cur : %s Quote : %s Order : %s Exp : %s'*signifies that the current, quote, order, and expected quantities will be inserted and displayed within the program.

Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Customising document type terminology - Purchase

The language associated with each Set of Books determines the specific labels used to cater to different countries or tax regulations. In most languages, the term *'Purchase'* or its equivalent will be displayed. For instance, en-UK and en-South Africa use terminology related to *'Purchase'*, while in South Africa, Afrikaans refers to *'Aankoop'* or *'Aankope'*.

These purchase-related labels are visible within the osFinancials5/TurboCASH5 interface when you access a Set of Books. They are also present in reports and document layout files generated by the system.

To adapt the purchase document type terminology to suit your country, jurisdiction, and industry, you can customize and modify the purchase-related labels via the "*Customize Languages*" screen. This screen is accessible through the Tools → Customise Language menu on the Setup ribbon.

You may also find it helpful to utilize the search options available. This enables you to search for a specific label either in the currently active language file you're editing or in the default "*English*" language file. This assists you in identifying and modifying specific text to better suit your requirements.

Document type names for layout files that support all document types

osFinancials5/TurboCASH5 supports a single document layout file which utilizes translatable expressions facilitated by language file settings. They dynamically display the appropriate document type names such as "Invoice," "Credit note," "Quote," "Purchase," "Supplier return," or "Order" based on the specific document being printed. The document types are sourced from the "TYPES.SDESCRIPTION" expressions within the layout.

To change the document type names, you need to change the descriptions on the Types tab of the "Customize Languages" screen (accessible from the Tools → Customise Language menu on the Setup ribbon).

Preview of available document layout file samples that support all document types

To assist in choosing a layout file for your needs, you may preview some screenshots of document layout files:

1. *Translatable Document Layout Files with Dynamic Document Types*
    - *"Layout File"*
    - *"Document Layout"*
    - *"Document Layout (15 Code)"*
2. *Translatable Document Layout Files with Dynamic Document Types without VAT/GST/Sales Tax*
    - *"NO-TAX Layout File"*
    - *"NO-TAX Document Layout"*
    - *"NO-TAX Document Layout (15 code)"*

If you are not registered for VAT/GST/Sales tax or have chosen not to opt for voluntary registration, these layout files exclude VAT/GST/Sales tax information. They also dynamically display the appropriate document type names based on the specific type of document being printed.

For your convenience, the default "*English*" language file contains a total of 81 purchase-related labels, which are listed in the table below:

LabelID	*Description for Purchase*
40	*Delete purchases*
49	*&Purchases*
61	*&Purchases*
79	*&Purchases listing*
302	*Purchases*
330	*Next purchase no.*
331	*Purchase batch*

332 Purchase heading

333 Purchase message

685 Are you sure you want to clear all the entries in this purchase?

686 Print a purchase document now?

691 Purchases history

694 From purchase

700 Update purchase

703 Purchase no.

709 Do you wish to print this purchase?

759 Purchase no.

861 Purchases per supplier

862 Purchases per product

929 Purchases

977 Purchase analysis

1077 Purchases per product options

1078 Purchases per supplier options

1147 Purchase document accepted

1225 Order to convert to purchase

1269 Purchase documents

2153 Purchases

2160 Purchase totals :

2163 Sales analysis - Purchases per supplier

2922 Purchase (no stock)

3185 Create purchase on default supplier 1

3296 Purchase/Credit

3302 Limit stock purchase only for default supplier or non

3311 Create purchase on default supplier 1

3352 Sales, Purchase, Cost of sales and Tax accounts

3504 Purchase date

3517 Purchase amount

3573 Purchases per period

3575 Purchases per product

902009 Price list - Large retail - Purchases

903144 Reset purchase to basis of last document

903165 Set Selling Price 1 at 1.5 X of Purchase Price and Selling Price 2 at1.3 X of Purchase Price

906026 Purchase document

906027 Purchase date

906114 Purchases per period

906129 Posted purchases

906130 Unposted purchases

906150 Purchases per period - Quantities

906151 Purchases per period - Amount

906152 Purchases per period - Creditor group 1

906153 Purchases per period - Creditor group 2

906154 Purchases per period - Document group 1

906163 Purchases per period - Document group 2

906164 Purchases per period - Salesperson

906172 Purchases per product - Stock group 1

906173 Purchases per product - Stock group 2

906197 Purchase (no codes)

906203 Purchase (10 code)

906209 Purchase (15 code)

906215 Purchase A4 (no codes)

906221 Purchase A4 (10 code)

906227 Purchase A4 (15 code)

906233 Purchase A4 Plain (no codes)

906239 Purchase A4 Plain (10 code)

906245 Purchase A4 Plain (15 code)

906251 Purchase No Tax (no codes)

906257 Purchase No Tax (15 code)

906289 Graph - Purchases per week - Quantities

906290 Graph - Purchases per week - Amount

906327 Purchase documents per period - Creditor group 1

906328 Purchase documents per period - Creditor group 2

906329 Purchase documents per period - Document group 1

906330 Purchase documents per period - Document group 2

906331 Purchase documents per period - Salesperson

906337 Purchases and supplier returns per period

906571 Graph - Purchases - Supplier returns - month - Quantities

906572 Graph - Purchases - Supplier returns - month - Amount

906577 Graph - Purchases per month - Amount

906578 Graph - Purchases per month - Quantities

906581 Graph - Purchases - Supplier returns per week - Quantities

906582 Graph - Purchases - Supplier returns per week - Amount

If '%s ' is included in a label description in the language file, please refrain from translating this. This placeholder is reserved for specific data that will be dynamically populated within the label. For example, 'Cur : %s Quote : %s Order : %s Exp : %s' signifies that the current, quote, order, and expected quantities will be inserted and displayed within the program.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Customising document type terminology - Supplier return

The language associated with each Set of Books determines the specific labels used to cater to different countries or tax regulations. In most languages, the term *'Supplier return'* or its equivalent will be displayed. For instance, en-UK and en-South Africa use terminology related to *'Supplier return'*, while in South Africa, Afrikaans refers to *'Verskafferretoer'* or *'Verskafferretoere'*.

These purchase-related labels are visible within the osFinancials5/TurboCASH5 interface when you access a Set of Books. They are also present in reports and document layout files generated by the system.

To adapt the *'Supplier return'* document type terminology to suit your country, jurisdiction, and industry, you can customize and modify the *'Supplier return'*-related labels via the "*Customize Languages*" screen. This screen is accessible through the Tools → Customise Language menu on the Setup ribbon.

You may also find it helpful to utilize the search options available. This enables you to search for a specific label either in the currently active language file you're editing or in the default "*English*" language file. This assists you in identifying and modifying specific text to better suit your requirements.

Document type names for layout files that support all document types

osFinancials5/TurboCASH5 supports a single document layout file which utilizes translatable expressions facilitated by language file settings. They dynamically display the appropriate document type names such as "Invoice," "Credit note," "Quote," "Purchase," "Supplier return," or "Order" based on the specific document

being printed. The document types are sourced from the "TYPES.SDESCRIPTION" expressions within the layout.

To change the document type names, you need to change the descriptions on the Types tab of the "Customize Languages" screen (accessible from the Tools → Customise Language menu on the Setup ribbon).

Preview of available document layout file samples that support all document types

To assist in choosing a layout file for your needs, you may preview some screenshots of document layout files:

1. *Translatable Document Layout Files with Dynamic Document Types*
    - *"Layout File"*
    - *"Document Layout"*
    - *"Document Layout (15 Code)"*
2. *Translatable Document Layout Files with Dynamic Document Types without VAT/GST/Sales Tax*
    - *"NO-TAX Layout File"*
    - *"NO-TAX Document Layout"*
    - *"NO-TAX Document Layout (15 code)"*

If you are not registered for VAT/GST/Sales tax or have chosen not to opt for voluntary registration, these layout files exclude VAT/GST/Sales tax information. They also dynamically display the appropriate document type names based on the specific type of document being printed.

For your convenience, the default "*English*" language file contains a total of 48 Supplier return-related labels, which are listed in the table below:

LabelID	*Description for Supplier return*
41	*Delete supplier returns*
303	*Supplier returns*
335	*Supplier return batch*
336	*Supplier return heading*
337	*Supplier return message*
419	*Supplier returns*

690 *Supplier return history*

701 *Update supplier returns*

702 *From supplier return*

708 *Do you wish to print this supplier return?*

752 *Supplier return no.*

2154 *Supplier returns*

2161 *Supplier return totals :*

3181 *Convert to credit note / supplier return*

3574 *Supplier returns per period*

906028 *Supplier return date*

906029 *Supplier return document*

906030 *Supplier return accepted*

906120 *Supplier returns per period*

906131 *Posted supplier returns*

906132 *Unposted supplier returns*

906198 *Supplier return (no codes)*

906204 *Supplier return (10 code)*

906210 *Supplier return (15 code)*

906216 *Supplier return A4 (no codes)*

906222 *Supplier return A4 (10 code)*

906228 *Supplier return A4 (15 code)*

906234 *Supplier return A4 Plain (no codes)*

906240 *Supplier return A4 Plain (10 code)*

906246 Supplier return A4 Plain (15 code)

906252 Supplier return No Tax (no codes)

906258 Supplier return No Tax (15 code)

906296 Supplier returns per period - Creditor group 1

906297 Supplier returns per period - Creditor group 2

906298 Supplier returns per period - Document group 1

906299 Supplier returns per period - Document group 2

906300 Supplier returns per period - Salesperson

906313 Supplier returns per period - Quantities

906314 Supplier returns per period - Amount

906321 Graph - Supplier returns per week - Quantities

906322 Graph - Supplier returns per week - Amount

906337 Purchases and supplier returns per period

906571 Graph - Purchases - Supplier returns - month - Quantities

906572 Graph - Purchases - Supplier returns - month - Amount

906575 Graph - Supplier returns per month - Amount

906576 Graph - Supplier returns per month - Quantities

906581 Graph - Purchases - Supplier returns per week - Quantities

906582 Graph - Purchases - Supplier returns per week - Amount

If '%s ' is included in a label description in the language file, please refrain from translating this. This placeholder is reserved for specific data that will be dynamically populated within the label. For example, 'Cur : %s Quote : %s Order : %s Exp : %s' signifies that the current, quote, order, and expected quantities will be inserted and displayed within the program.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Customizing document type terminology - Order

The language associated with each Set of Books determines the specific labels used to cater to different countries or tax regulations. In most languages, the term *'Order'* or its equivalent will be displayed. For instance, en-UK and en-South Africa use terminology related to *'Order'*, while in South Africa, Afrikaans refers to *''Bestelling'* or *'Bestellings'*.

These order-related labels are visible within the osFinancials5/TurboCASH5 interface when you access a Set of Books. They are also present in reports and document layout files generated by the system.

To adapt the order document type terminology to suit your country, jurisdiction, and industry, you can customize and modify the order-related labels via the "*Customize Languages*" screen. This screen is accessible through the Tools → Customise Language menu on the Setup ribbon.

You may also find it helpful to utilize the search options available. This enables you to search for a specific label either in the currently active language file you're editing or in the default "*English*" language file. This assists you in identifying and modifying specific text to better suit your requirements.

Document type names for layout files that support all document types

osFinancials5/TurboCASH5 supports a single document layout file which utilizes translatable expressions facilitated by language file settings. They dynamically display the appropriate document type names such as "Invoice," "Credit note," "Quote," "Purchase," "Supplier return," or "Order" based on the specific document being printed. The document types are sourced from the "TYPES.SDESCRIPTION" expressions within the layout.

To change the document type names, you need to change the descriptions on the Types tab of the "Customize Languages" screen (accessible from the Tools → Customise Language menu on the Setup ribbon).

Preview of available document layout file samples that support all document types

To assist in choosing a layout file for your needs, you may preview some screenshots of document layout files:

1. *Translatable Document Layout Files with Dynamic Document Types*
    - *"Layout File"*
    - *"Document Layout"*
    - *"Document Layout (15 Code)"*
2. *Translatable Document Layout Files with Dynamic Document Types without VAT/GST/Sales Tax*

- *"NO-TAX Layout File"*
- *"NO-TAX Document Layout"*
- *"NO-TAX Document Layout (15 code)"*

If you are not registered for VAT/GST/Sales tax or have chosen not to opt for voluntary registration, these layout files exclude VAT/GST/Sales tax information. They also dynamically display the appropriate document type names based on the specific type of document being printed.

For your convenience, the default "*English*" language file contains a total of 83 order-related labels, which are listed in the table below:

LabelID	*Description for Order*
36	*Order confirmation*
76	*&Backorder listing*
83	*&Reorder report*
221	*Reorder level*
338	*Next order no.*
339	*Order heading*
340	*Order message*
655	*Qty order*
693	*Orders history*
707	*Do you wish to print this order?*
762	*Order no.*
773	*From order*
798	*Orders*
844	*&Backorders*
1019	*Delete orders*

1082 Reorder options

1083 Backorder options

1149 Order accepted

1190 Items on backorder

1191 Backorders

1224 Order no.

1225 Order to convert to purchase

1778 Reorder

1861 Order

1871 Orders

1874 Confirm quotes and orders

2170 Order

2930 No backorder

2983 Quotes / Orders

3020 Convert invoice to order

3024 Open osCommerce order in browser

3129 Reorder at

3131 Reorder level - your items will be reordered until this quantity!

3132 If your stock goes below this, then the system will reorder until the reorder quantity!

3139 Cur : %s Quote : %s Order : %s Exp : %s

3159 Merge invoice to orders

3182 Open e-Commerce order in browser

3323 Create backorders to deliver

3333 *Order*

3382 *QuickOrder*

3572 *Orders per period*

3623 *Order is placed!*

3625 *Please add items to your order!*

3626 *This list shows what you already ordered*

3627 *This list shows what you are going to order when you press the order button*

3628 *Select a product to add to your order list*

3631 *All orders*

3647 *Telephonic orders*

3648 *Orders to deliver list*

3661 *Document without border*

3664 *New order*

21158 *Table and order*

906005 *Order date*

906032 *Order list*

906033 *Outstanding orders*

906036 *Reorder quantities*

906050 *Backorder*

906056 *Bar order*

906057 *Kitchen order*

906135 *Confirmed orders*

906136 *Unconfirmed orders*

906199 Order (no codes)

906205 Order (10 code)

906211 Order (15 code)

906217 Order A4 (no codes)

906223 Order A4 (10 code)

906229 Order A4 (15 code)

906235 Order A4 Plain (no codes)

906241 Order A4 Plain (10 code)

906247 Order A4 Plain (15 code)

906253 Order No Tax (no codes)

906259 Order No Tax (15 code)

906306 Orders per period - Creditor group 1

906307 Orders per period - Creditor group 2

906308 Orders per period - Document group 1

906309 Orders per period - Document group 2

906310 Orders per period - Salesperson

906317 Orders per period - Quantities

906318 Orders per period - Amount

906325 Graph - Orders per week - Quantities

906326 Graph - Orders per week - Amount

906573 Graph - Orders per month - Amount

906574 Graph - Orders per month - Quantities

If '%s ' is included in a label description in the language file, please refrain from translating this. This placeholder is reserved for specific data that will be dynamically populated within the label. For example, 'Cur : %s Quote : %s Order : %s Exp : %s' signifies that the current, quote, order, and expected quantities will be inserted and displayed within the program.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Set language for a Set of Books

When you open a Set of Books, osFinancials5/TurboCASH5 will automatically load the language file linked to that Set of Books. This ensures that all screens, reports, and document layout files associated with the Set of Books are presented in the selected language.

You may set or change the language file as the default language for a Set of Books. When opening a Set of Books, it will automatically load the language file. All screens, reports and layout files are translatable via the language files.

You may set the language file for each user. When a user Open a Set of Books, the Set of Books will automatically be opened in the language set for that user.

To set a language for an user Set of Books:

1. On the Setup ribbon, select Access control.



2. System lang - The default language set for each user for will be displayed in this field. You may set another language for each of your users. The selected language will be displayed every time a specific user opens the Set of Books.

3. Language - The languages added in the Languages tab in Groups (Setup ribbon) may be selected for the *Multi-Language accounts* plugin. Languages may also be set in the this field for debtors /creditors.

Multi-Language accounts - Manual - Shop - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

4. Click on the Apply button to save the changes for this user.

5. Once finished, click on the Close button to exit the "*Access control*" screen.

Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

Accounting process in osFinancials5

If you choose to work with one of the pre-created Sets of Books in osFinancials5/TurboCASH5, most of the settings and defaults have already been set.

You may download an existing template for your country and language (in a matter of a few seconds about 3 clicks) from the Let osFinancials help you to create a Set of Books - Download option / Let TurboCASH help you to create a Set of Books - Download option.

Each of these Sets of Books is already set to a specific language for your country and language.

See a list of available Firebird Sets of Books and linked languages available as a free download. You may then Customise the Set of Books to meet your own requirements.

Getting started entails little more than the entry of a few basic details and the selection of some basic options:

1. Create your Set of Books - osFinancials5/TurboCASH5 allows you to create a Set of Books within minutes by copying an existing structure.

2. Settings and defaults - osFinancials5/TurboCASH5 will use these parameters and defaults to display and perform certain functions for you.

a) Company info - Enter your contact information and registration details and set the defaults for your Tax (if you are registered for Tax (VAT/GST/Sales tax)).

b) Reporting dates - Set the starting date for your financial year and the accounting periods for which you may generate financial reports.

c) Reporting groups - Add or edit any reporting account groups for your Accounts to further classify the five Financial categories. You may also add up to two (2) reporting groups for your Debtor (customer / client) accounts, Creditor (supplier / vendor) accounts, Stock items (products), Documents, Salespersons.

d) Financial categories - Link your Reporting account groups (e.g. Income, Other income, Expenses, Capital, Long-term liabilities, Current liabilities, Fixed assets and Current assets) to the 5 Financial categories (i.e. Income, Expenses, Capital, Assets and Liabilities).

e) Batch types - Add, edit or delete any batch types (journals) in which you wish to enter transactions.

f) Access control and passwords (Optional) - Set passwords and access control for your users.

g) Internet (Optional) - Configure your e-mail account to send reports, lists and documents over the Internet.

h) Documents setup - Set the Document numbers, messages and check the Batch types for your sales documents (Invoices, Credit notes and Quotes for debtors (customers / clients) and purchase documents (Purchases, Supplier returns and Orders for creditors (suppliers / vendors).

   You may also add a standard message (on the Statement setup tab) to print on all statements you wish to send to your debtors (customers / clients).

i) Salespersons - Add any salespersons that may sell your stock or products.

j) Stock information - Define your selling prices and units of stock. You also need to set the Cost of sales settings for your stock items / inventory items / products.

k) Set preferences -

   i) Printer - Set the default printer and paper sizes.

   ii) System parameters - Set the defaults for both entry and display.

3. Customise your Chart of Accounts - Your Set of Books will have a standard Chart of Accounts, which should reflect all your accounts.

4. Configure your Tax (VAT/GST/Sales tax) to according to your Tax Registration - The status of your Tax (VAT/GST/Sales tax) registration with your Tax authorities, jurisdiction may need some adjustments in the Chart of Accounts.

5. Add Debtor (customer / client) accounts.
6. Add Creditor (supplier / vendor) accounts.
7. Add Stock items (Inventory items / products) - Add your stock items / inventory items / products.
8. Enter Opening Balances for your accounts and trading stock items, if you have any.
9. Start processing your daily transactions in batches (journals) and or documents.
10. Print reports to evaluate your activities.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

New to Computers

When choosing a computer system for your accounting what should be considered?

When choosing a computer system for accounting, there are several important factors to consider to ensure that it meets the specific needs of your accounting tasks and provides a smooth and efficient workflow. Here are the key considerations:

1. Accounting Software Compatibility: The computer system should be compatible with the accounting software you plan to use. Verify that the software runs smoothly on the chosen operating system (e.g., Windows, macOS, Linux) and hardware specifications.
2. Performance and Processing Power: For efficient accounting operations, consider a computer with sufficient processing power, RAM, and storage. This will ensure that the accounting software runs smoothly, especially when handling large datasets or complex calculations.
3. Storage Capacity: Accounting involves managing a significant amount of data, so having ample storage space is crucial. Consider whether you need a larger hard drive or if opting for solid-state drives (SSD) for faster data access and improved system responsiveness.
4. Security Features: Accounting data often contains sensitive financial information. Look for computers with robust security features, such as biometric authentication (fingerprint or facial recognition) and encryption, to protect against data breaches.
5. Backup and Recovery: Ensure the computer system has a reliable backup solution to safeguard accounting data. Automatic backup mechanisms or cloud-based storage options can be highly beneficial for data recovery in case of hardware failure or accidental data loss.
6. Display and Screen Size: A large and high-resolution display can enhance productivity by allowing you to view multiple documents or spreadsheets simultaneously. Consider whether a dual-monitor setup

would be beneficial for your accounting tasks.

7. Connectivity Options: Ensure that the computer has sufficient USB ports, HDMI, and other connectivity options to connect peripherals like printers, scanners, external hard drives, etc.
8. Portability (If Needed): If you need to work on the go or in different locations, consider the portability of the computer. Laptops or 2-in-1 devices may be more suitable in such cases.
9. Budget: Set a budget for your computer system and try to find the best balance between performance, features, and cost.
10. Warranty and Support: Choose a reputable brand that offers a good warranty and customer support. This ensures prompt assistance in case of any hardware or software issues.
11. Scalability: Consider whether the computer system can be easily upgraded or expanded in the future to accommodate changing accounting needs.
12. Reviews and Recommendations: Read reviews and seek recommendations from other accounting professionals or businesses to get insights into the performance and reliability of different computer systems.

By considering these factors, you can select a computer system that meets your accounting requirements, enhances productivity, and provides a secure and reliable platform for managing financial data effectively.

What is the considerations in a multi user environment?

For a multi-user accounting environment, additional considerations are needed to ensure the computer system can handle the demands of multiple users accessing accounting software simultaneously. Here are some specific factors to consider in a multi-user setup:

1. Network Infrastructure: A robust and reliable network infrastructure is essential for smooth communication and data sharing between multiple users. Ensure your network supports fast data transfer rates and has sufficient bandwidth to accommodate simultaneous user access.
2. Server Capability: In a multi-user environment, it's often advisable to have a dedicated server to host the accounting software and data. The server should have ample processing power, memory (RAM), and storage capacity to handle multiple user requests efficiently.
3. Server Redundancy: Consider implementing server redundancy to minimize downtime. Redundant hardware, backup power supplies, and RAID configurations can help ensure continuous access to accounting data even in the event of hardware failures.
4. Account Access Control: Implement strict user access controls to protect sensitive financial data. Different users should have appropriate access levels based on their roles and responsibilities within the accounting system.

5. Remote Access and VPN: If users need to access the accounting system remotely, ensure that the server setup supports secure remote access, such as through a Virtual Private Network (VPN).
6. Backup and Disaster Recovery: Implement a robust backup and disaster recovery plan to protect accounting data in case of accidental data loss, system failures, or cybersecurity incidents.
7. Data Synchronization: Ensure that data is synchronized in real-time across all users to avoid conflicts and ensure consistency in financial records.
8. Hardware Compatibility: Ensure that all user devices are compatible with the accounting software and meet the necessary hardware requirements.
9. Performance Testing: Before deploying the system in a production environment, conduct thorough performance testing to ensure that the server and network can handle the expected load.
10. Scalability: Consider the future growth of your business and accounting needs. Choose a system that can scale easily to accommodate additional users and increased data volumes.
11. User Training and Support: Properly train all users on the accounting software and the multi-user setup. Provide ongoing support and assistance to resolve any user-related issues promptly.
12. Software Licensing: Ensure compliance with software licensing requirements for multi-user access. Some accounting software may have specific licensing terms for multiple users.

By addressing these considerations, you can create a stable and efficient multi-user accounting environment that fosters collaboration, data accuracy, and security across your organization. Working with experienced IT professionals can be beneficial to design and implement a reliable multi-user computer system for your accounting needs.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Peripherals

What is peripherals?

Peripherals, in the context of computers and technology, refer to external devices or components that are connected to a computer or other main computing device to expand its capabilities or functionality. These devices serve specific purposes and often complement the central processing unit (CPU) or main system. Peripherals are typically connected to the computer through various ports such as USB, HDMI, or Bluetooth. They can be easily added or removed as needed.

Here are some common examples of peripherals:

1. Keyboard: A device used to input text and commands into a computer.
2. Mouse: A pointing device used to navigate and interact with graphical user interfaces.
3. Monitor: A display device that shows the output from the computer, allowing users to see information and perform tasks.
4. Printer: An output device that produces physical copies of documents or images from the computer.
5. Scanner: An input device used to convert physical documents or images into digital formats that can be stored and manipulated on a computer.
6. External Hard Drive: An additional storage device that is connected to a computer to expand its storage capacity.
7. Speakers: Output devices used to produce sound or audio from the computer.
8. Headphones: Audio output devices worn over the ears to listen to audio privately.
9. Webcam: A camera device used for video conferencing, live streaming, or recording video content on a computer.
10. Microphone: An input device used to capture audio and record voice or other sound inputs.
11. External Optical Drive: An external device used to read CDs, DVDs, or Blu-ray discs.
12. USB Flash Drive: A portable storage device that connects to the computer's USB port to transfer and store data.
13. Graphics Tablet: An input device used by artists and designers to draw directly on the surface of the tablet and have the drawing mirrored on the computer screen.

Peripherals are essential for enhancing the usability and functionality of computers and other devices, allowing users to interact with and utilize technology effectively.

Peripherals for POS systems

Point of Sale (POS) systems are used in various businesses, such as retail stores, restaurants, and hospitality establishments, to process transactions and manage sales. Peripherals for POS systems are external devices that enhance the capabilities of the system and enable efficient and seamless operations. Some common peripherals used with POS systems include:

1. Barcode Scanner: A barcode scanner reads barcodes on products, allowing quick and accurate item identification during the checkout process. This speeds up transactions and reduces the risk of manual entry errors.

2. Receipt Printer: A receipt printer generates printed receipts for customers after a transaction is completed. It provides a tangible record of the purchase and can include details like item names, prices, taxes, and payment method.
3. Cash Drawer: A cash drawer is used to store cash and coins securely during transactions. It is typically connected to the POS system and can be automatically opened after a sale to provide change to customers.
4. Card Reader or Payment Terminal: This peripheral allows customers to make card payments, including credit and debit cards. Modern card readers may also support contactless and mobile payment methods like Apple Pay or Google Pay.
5. Customer Display: A customer display is a screen facing the customer that shows transaction details like the total amount, items purchased, and payment options. It helps customers verify the transaction before completing the payment.
6. Pole Display: A pole display is a similar display to the customer display but is mounted on a pole and often faces the cashier or salesperson. It shows transaction details for verification before finalizing the sale.
7. Kitchen Display System (KDS): In restaurants or food service businesses, a KDS allows the kitchen staff to receive and manage orders electronically. It helps streamline order preparation and reduces the need for paper tickets.
8. Kitchen Printer: Alternatively to a KDS, a kitchen printer can be used to print order tickets in the kitchen. It provides a physical copy of the order to the kitchen staff for preparation.
9. Scale: In businesses that sell products by weight, such as grocery stores or delis, a scale integrated with the POS system ensures accurate pricing and automatic calculation of the total cost.
10. Mobile Devices: Some POS systems support mobile devices like tablets or smartphones, allowing employees to process sales and take orders anywhere on the premises.

These peripherals work in conjunction with the POS software to create a complete and efficient point of sale system. Businesses can choose the peripherals that best suit their specific needs and industry requirements to improve customer service and enhance operational efficiency.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Barcode basics

What is barcodes?

Barcodes are a method of representing data in a visual, machine-readable format. They consist of a series of parallel lines, bars, or dots of varying widths and spacing that encode information. The information encoded in a barcode can be numeric or alphanumeric, and it can represent various types of data, such as product numbers, inventory details, or tracking information.

Barcodes are widely used in various industries and applications, primarily for automating data capture and identification processes. When scanned or read by a barcode scanner or mobile device with a camera, the encoded information is quickly retrieved and processed by computer systems.

There are several types of barcodes, and the most common ones include:

1. UPC (Universal Product Code): Used primarily for retail products, especially in North America.
2. EAN (European Article Numbering): Similar to UPC but used more internationally.
3. Code 39: Widely used in industrial applications and for asset tracking.
4. Code 128: A high-density barcode used in logistics and shipping industries.
5. QR Code (Quick Response Code): A 2D barcode that can store more data, often used in marketing, advertising, and mobile applications.

Barcodes have significantly improved efficiency in supply chain management, inventory control, retail checkout processes, and many other applications where quick and accurate data entry is essential. They have become an integral part of modern business operations, providing a cost-effective and reliable means of tracking and managing information.

What is the validation rules for barcodes?

Validation rules for barcodes ensure that the encoded data is accurate and can be reliably read by barcode scanners or other reading devices. These rules help prevent errors during data entry and scanning processes, ensuring the integrity of the information represented by the barcode. The specific validation rules for barcodes depend on the type of barcode being used. Here are some general principles and considerations:

1. Correct Barcode Type: Ensure that the correct barcode symbology is used for the specific application. Different barcode types have different encoding capacities and formats, so selecting the appropriate type is essential.
2. Valid Characters: Each barcode type has a specific set of characters that can be encoded. Make sure that the data being encoded matches the allowed characters for the chosen barcode format.

3. Length: Check that the data being encoded matches the required length for the specific barcode symbology. Some barcodes have fixed lengths, while others allow variable lengths within certain limits.
4. Checksums: Many barcode types include checksum digits, which are calculated based on the other encoded data. The barcode scanner can use these checksums to validate the accuracy of the scanned data. Ensure that the checksum algorithm is applied correctly during barcode generation and scanning.
5. Quiet Zones: Barcode readers need clear areas (quiet zones) before and after the barcode to accurately read the data. These zones should be free of any printing, text, or other markings to avoid interference with the scanning process.
6. Print Quality: Barcode scanners require well-printed, high-contrast barcodes for accurate reading. Check that the barcode is printed clearly, without smudging, fading, or distortion.
7. Scanning Environment: Ensure that the scanning environment is suitable for barcode reading. Adequate lighting and proper positioning of the scanner are important factors to consider.
8. Encoding Format: Some barcodes can encode data in different formats, such as binary or alphanumeric. Ensure that the correct encoding format is used based on the data being represented.
9. Data Structure: Verify that the data within the barcode follows the required structure for the particular application. For instance, if the barcode is used for product identification, it should include the appropriate product identifiers.

Overall, adhering to these validation rules helps maintain the accuracy and reliability of barcodes, ensuring seamless data capture and processing in various industries and applications.

Which barcodes use the check character(s)?

Several barcodes use check characters (also known as checksums) to enhance data accuracy and reliability during scanning. Check characters are extra digits or characters calculated from the encoded data and are included in the barcode to detect and prevent errors in reading or data entry. When a barcode scanner reads a barcode, it uses the check character to verify that the decoded data matches the expected checksum value. If there is a discrepancy, the scanner can signal an error, and corrective actions can be taken.

Some of the common barcode symbologies that utilize check characters include:

1. Code 39: Code 39 barcodes often include a modulo-43 check character to verify the accuracy of the encoded data.
2. Code 128: Code 128 barcodes can use different types of check characters, such as C, B, and A. Each type of check character serves a specific purpose in error detection.

3. EAN-13: The EAN-13 barcode system used for product identification often includes a check digit at the end. The check digit helps verify the accuracy of the other digits in the barcode.
4. UPC-A: Similar to EAN-13, the UPC-A barcode system used primarily in North America includes a check digit for error detection.
5. ITF-14: The ITF-14 barcode, commonly used for packaging and logistics applications, includes a modulo-10 check digit.
6. MSI (Modified Plessey): MSI barcodes may include a check digit to enhance accuracy.
7. Codabar: Codabar barcodes can use a start/stop character check to ensure proper barcode reading.

It's important to note that not all barcode symbologies include check characters. Some barcode types, like QR codes, do not inherently include a check character, but data redundancy and error correction are built into their design, allowing for error detection and correction.

The inclusion of check characters significantly improves the reliability of barcode scanning and data integrity, making them an essential feature in many barcode systems.

Can you design your own barcodes?

Designing a barcode involves choosing the appropriate barcode symbology, determining the data to be encoded, and using a barcode generator to create the visual representation of the barcode. Here are the general steps you can follow to design your own barcode:

1. Choose the Barcode Symbology: Decide which type of barcode symbology is suitable for your application. Consider factors like the type of data to be encoded, the required data capacity, and the scanning environment.
2. Determine the Data to Encode: Decide what information you want to encode in the barcode, such as product numbers, IDs, or URLs. Different barcode types have specific rules and limitations for the type and length of data they can encode.
3. Select a Barcode Generator: There are various online barcode generators and barcode design software available that can help you create barcodes easily. Some of these tools are free, while others offer more advanced features at a cost.
4. Input Data and Generate Barcode: Enter the data you want to encode into the barcode generator and specify the barcode symbology you have chosen. The generator will create the barcode image for you.
5. Customize the Barcode (Optional): Depending on the generator or software you are using, you might have the option to customize the appearance of the barcode, such as adjusting the size, color, or adding text around the barcode.

6. Save and Print: Once you are satisfied with the design, save the generated barcode in the desired format (e.g., PNG, JPEG) and print it on your desired medium (labels, packaging, etc.).

Please note that when designing barcodes for commercial use or products, it is essential to ensure that the barcodes comply with industry standards and regulations to ensure proper scanning and interoperability with different systems and scanners. Additionally, if you are using barcodes for specific applications like retail products, you might need to obtain a unique identifier (e.g., UPC or EAN) from the appropriate governing organization.

Barcode scanners and Barcode printers?

Barcode Scanners

Barcode scanners are electronic devices used to read and decode information from barcodes. They are commonly used in various industries, including retail, logistics, healthcare, and manufacturing. Barcode scanners are essential for automating data entry processes, tracking inventory, and managing products efficiently.

There are different types of barcode scanners based on their technology and form factor:

1. Handheld Barcode Scanners: These are the most common type of barcode scanners. They are lightweight, portable devices that can be easily held and pointed at barcodes for scanning.
2. Stationary/Countertop Barcode Scanners: These scanners are designed to be fixed in a specific location, such as a retail checkout counter. They are often integrated into the counter or point-of-sale system.
3. Mobile Barcode Scanners: These scanners are built into smartphones or tablets, using the device's camera to scan barcodes. Mobile barcode scanning is popular in inventory management and retail applications.
4. Industrial Barcode Scanners: These rugged scanners are designed for heavy-duty use in industrial environments. They can withstand harsh conditions and are commonly used in warehouses and manufacturing facilities.

Barcode scanners use laser or image-based technology to capture the barcode data. Once scanned, the information is sent to a connected computer, point-of-sale system, or mobile device for further processing and data retrieval.

Barcode Printers

Barcode printers are devices used to produce physical labels or tags with printed barcodes. They are used in a wide range of applications, such as product labelling, shipping labels, asset tracking, and more.

Barcode printers come in different types, and the choice depends on the volume of labels needed, the printing technology, and the label size:

1. Direct Thermal Printers: These printers use heat-sensitive paper to print barcodes. They are ideal for temporary labels and are commonly used in shipping applications.
2. Thermal Transfer Printers: These printers use a ribbon to transfer ink onto the label material. They produce more durable and long-lasting labels, suitable for product and asset labeling.
3. Desktop Printers: Compact and affordable printers suitable for low to medium volume printing needs.
4. Industrial Printers: Sturdy and robust printers designed for high-volume and continuous printing in industrial settings.

Barcode printers can be connected to a computer or integrated into a network, enabling easy label design and printing. Software programs are used to create and format the barcode labels with the necessary information before sending them to the printer for output.

Options to configure barcode scanners and barcode printers?

Configuring barcode scanners and barcode printers involves setting up various parameters and options to ensure optimal performance and compatibility with specific applications. The configuration options may vary depending on the brand and model of the scanner or printer. Here are some common configuration options for barcode scanners and barcode printers:

Barcode Scanners:

1. Data Format: Choose the output data format for scanned barcodes, such as plain text or specific data structures like CSV or XML.
2. Prefix/Suffix: Configure the scanner to add specific characters before or after the scanned data. This is useful for automatically appending identifiers or delimiters.
3. Barcode Symbologies: Enable or disable specific barcode symbologies according to the requirements of your application.
4. Data Validation: Set up the scanner to check the validity of scanned data using checksums or other validation methods.
5. Decode Options: Adjust decode settings, such as sensitivity, resolution, or aiming mode, to improve the scanning performance.
6. Interface Configuration: Configure the scanner's interface (e.g., USB, Bluetooth, RS-232) and adjust communication settings as needed.
7. Beep/Vibration Settings: Customize the scanner's feedback options, like beeping or vibrating, to

indicate a successful scan.

Barcode Printers:

1. Label Size and Orientation: Set up the printer to match the label size and orientation required for your specific labels.
2. Printing Technology: Configure the printer for direct thermal or thermal transfer printing, depending on the label material and durability needed.
3. Print Density and Speed: Adjust the print density and speed settings to optimize the print quality and performance.
4. Barcode Symbology and Height: Select the appropriate barcode symbology and adjust the barcode height to meet your application's requirements.
5. Label Positioning: Fine-tune label positioning to ensure accurate printing on the label material.
6. Label Margins: Define margins for the labels to ensure there is enough space around the barcode for proper scanning.
7. Communication Interfaces: Configure the printer's communication interfaces, such as USB, Ethernet, or serial ports, to connect to the desired devices.
8. Language and Fonts: Choose the language and fonts for label printing, especially if you need to include human-readable text on the labels.
9. Label Design Templates: Some printers come with label design software that allows you to create custom label templates.

Both barcode scanners and barcode printers often come with specific software or programming guides that allow you to access and adjust these configuration options. Manufacturers provide documentation and manuals to help users set up their devices according to their unique requirements.

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

Printer basics

Types of printers

Printers are devices used to produce physical copies of digital documents, images, or graphics on paper or other printable materials. They are commonly used in offices, homes, and various industries for a wide range of printing needs. There are several types of printers available, including:

1. Inkjet Printers: These printers use liquid ink cartridges to create images or text on paper. They are popular for general-purpose printing, photo printing, and are often more affordable than other types of printers.
2. Laser Printers: Laser printers use a toner cartridge and a laser beam to create images or text on paper. They are known for their fast printing speeds, high-quality text output, and are commonly used in offices for high-volume printing.
3. All-in-One Printers: Also known as multifunction printers, these devices combine the capabilities of a printer, scanner, copier, and sometimes a fax machine, all in one unit. They are versatile and space-saving solutions for homes and offices.
4. 3D Printers: These printers can create three-dimensional objects by depositing material layer by layer. They are commonly used in various industries, including manufacturing, engineering, and healthcare.
5. Thermal Printers: Thermal printers use heat to print on special heat-sensitive paper. They are commonly used in retail environments for printing receipts, labels, and barcodes.
6. Dot Matrix Printers: These printers use a series of pins to create characters by striking an ink ribbon against the paper. They were more popular in the past but are now less common due to their lower print quality and noise.
7. Dye-Sublimation Printers: Dye-sublimation printers use a special ink that turns into a gas when heated, bonding the ink onto the printing surface. They are commonly used for high-quality photo printing.

When choosing a printer, factors to consider include print quality, speed, connectivity options, size, and cost of consumables (e.g., ink or toner cartridges). It's essential to select a printer that matches your specific printing needs and budget.

Cost of ownership and choosing the printer for your business

When choosing a printer for your business, considering the total cost of ownership (TCO) is crucial. The TCO encompasses not only the upfront purchase cost of the printer but also ongoing expenses like consumables (ink, toner, and paper), maintenance, and energy consumption. Here are some factors to consider when evaluating the TCO and choosing the right printer for your business:

1. Printing Volume: Determine your business's average monthly printing volume. Higher printing volumes usually call for more robust and efficient printers. Consider printers designed for higher duty cycles if you have substantial printing needs.
2. Printer Type: Each printer type (inkjet, laser, etc.) has different TCO considerations. Inkjet printers might have a lower upfront cost but can have higher ink costs, especially for high-volume printing.

Laser printers tend to be more cost-effective for larger print jobs.

3. Cost of Consumables: Compare the cost of ink or toner cartridges for the printer models you are considering. Some printers have higher-capacity cartridges that may provide a lower cost per page.
4. Maintenance and Repairs: Research the typical maintenance requirements for the printers you are interested in. Consider the availability and cost of replacement parts if your printer needs repairs.
5. Energy Efficiency: Look for printers with energy-saving features. Energy-efficient printers can significantly reduce your business's electricity bills over time.
6. Multifunction Capability: All-in-one or multifunction printers combine printing, scanning, copying, and sometimes faxing in a single device. If your business requires multiple functions, a multifunction printer might be more cost-effective than buying separate devices.
7. Warranty and Support: Consider the length and coverage of the printer's warranty. Good customer support and readily available service centers can reduce downtime and maintenance costs.
8. Print Quality and Speed: Assess the print quality and speed requirements for your business. For some businesses, high-quality photo printing might be essential, while others may prioritize faster text printing.
9. Networking and Connectivity: Consider printers that offer easy integration with your business's network and various devices. Wireless and mobile printing capabilities can enhance productivity.
10. Longevity and Durability: Choose a printer from a reputable brand known for its reliability and durability. A longer-lasting printer will require fewer replacements and incur lower TCO.
11. Environmental Impact: Eco-friendly printers with energy-saving features and recycling programs can contribute to lower operational costs and environmental responsibility.

By carefully considering the TCO and assessing your business's specific printing needs, you can make a well-informed decision when choosing the right printer. Additionally, reading reviews and seeking recommendations from other businesses in your industry can provide valuable insights into the actual performance and cost-effectiveness of different printer models.

Preventative maintenance for printers

Preventive maintenance is crucial for keeping printers in optimal working condition and prolonging their lifespan. Regular maintenance can help prevent common issues, reduce downtime, and improve print quality. Here are some preventive maintenance tips for printers:

1. Cleaning the Printer: Regularly clean the exterior and interior of the printer. Use a soft, lint-free cloth to wipe dust and dirt off the printer's surfaces. Avoid using abrasive materials or harsh cleaning agents that could damage the printer.

2. Cleaning the Print Heads: If you have an inkjet printer, clean the print heads periodically. Most inkjet printers have a built-in utility for print head cleaning. Follow the printer's manual or software instructions for the cleaning process.
3. Cleaning the Rollers: For laser printers, clean the paper rollers to ensure smooth paper feeding. Consult the printer's manual on how to access and clean the rollers properly.
4. Check for Firmware/Software Updates: Periodically check for firmware updates for your printer model on the manufacturer's website. Keeping the printer's firmware and software up-to-date can improve performance and resolve known issues.
5. Use High-Quality Paper: Use high-quality paper that is suitable for your printer type. Low-quality paper can lead to paper jams, increased wear on printer components, and poor print quality.
6. Replace Consumables Timely: Replace ink or toner cartridges before they completely run out. Running a printer with empty cartridges can cause damage to the print heads in inkjet printers or toner-related issues in laser printers.
7. Maintain Proper Environment: Ensure the printer is placed in a clean and dust-free environment. Avoid exposure to extreme temperatures, direct sunlight, or excessive humidity.
8. Check for Paper Jams: Regularly inspect the printer for any paper jams. If a paper jam occurs, follow the manufacturer's instructions to remove the jam properly.
9. Monitor Printer Usage: Keep track of the printer's usage, especially in office environments. High-volume printers might need more frequent maintenance.
10. Professional Servicing: Consider scheduling professional servicing for your printer, especially if it's a high-end or industrial printer. Professional technicians can perform more in-depth maintenance and identify potential issues.

Remember to always refer to the printer's user manual for specific maintenance instructions tailored to your printer model. By following these preventive maintenance practices, you can ensure your printer operates efficiently and experiences fewer downtime-related problems.

What is printers used for in accounting software?

Printers play a crucial role in accounting software applications by enabling businesses to produce physical copies of financial documents and reports. Here are some common uses of printers in accounting software:

1. Financial Reports: Accounting software generates various financial reports, such as balance sheets, income statements, cash flow statements, and profit and loss statements. These reports are often required for financial analysis, tax purposes, and presenting financial information to stakeholders.

Printing these reports allows accountants and business owners to have physical copies for review and record-keeping.

2. Invoices and Purchase Orders: Accounting software is used to create invoices for customers and purchase orders for vendors. Printing these documents helps in providing hard copies for mailing or record-keeping purposes.
3. Payroll and Payslips: Payroll information, including payslips for employees, is often generated using accounting software. Printing payslips allows businesses to distribute them to employees and maintain a physical record.
4. Bank Reconciliation: Accountants use accounting software to reconcile bank statements with the company's financial records. Printed bank reconciliation reports can be useful for auditing and verification purposes.
5. Checks: Some accounting software can print checks directly, allowing businesses to pay vendors and employees with physical checks. These checks can then be signed and mailed or handed out as needed.
6. Tax Forms: During tax season, accounting software may generate tax forms such as W-2s for employees and 1099s for contractors. Printing these forms ensures compliance with tax regulations and provides necessary documentation for tax filing.
7. General Ledger and Journals: The general ledger and various journals (e.g., sales journal, purchase journal) are essential components of accounting software. Printing these records allows accountants to review and analyze financial transactions.
8. Financial Statements for Meetings: In board meetings, shareholder meetings, or when discussing financial matters with stakeholders, having printed financial statements can be useful for presenting and sharing information.

It's important to note that as technology advances, many businesses are adopting paperless or digital document management practices. Instead of printing documents, they might choose to save them as PDFs or other digital formats for archiving and distribution. This approach can reduce printing costs, storage space, and environmental impact while still providing easy access to necessary financial records.

Created with the Standard Edition of HelpNDoc: Revolutionize your documentation process with HelpNDoc's online capabilities

RFID technology

What is RFID technology?

RFID (Radio Frequency Identification) is a technology that uses radio waves to wirelessly identify and track objects or people. It is based on the principle of using electromagnetic fields to transfer data between an RFID tag and a reader. RFID systems consist of three main components:

1. RFID Tag: The RFID tag is a small electronic device that contains a unique identifier, often called the Electronic Product Code (EPC) or RFID code. It can be passive (without its own power source) or active (with its own power source). Passive tags draw power from the RFID reader's electromagnetic field when it comes within range, while active tags have their own internal power source, allowing them to transmit signals over longer distances.
2. RFID Reader: The RFID reader is a device that emits radio waves and reads the data stored in RFID tags. When an RFID tag enters the reader's range, it receives the tag's unique identifier and can also write information to the tag. The reader is responsible for communication with the RFID tags and relaying the data to a central system.
3. RFID Middleware and Database: The data collected by the RFID reader is typically processed by middleware software that acts as an interface between the reader and the enterprise applications. The middleware helps filter and format the data before passing it on to the relevant systems, such as inventory management, access control, or supply chain management databases.

RFID technology finds applications in various industries and sectors, including:

1. Inventory and Supply Chain Management: RFID helps improve the accuracy and efficiency of inventory tracking, asset management, and supply chain operations by providing real-time visibility into the movement and location of goods.
2. Retail and Logistics: RFID is used in retail stores to track products and prevent theft. It also streamlines the shipping and receiving process by automating data capture and reducing manual efforts.
3. Access Control and Security: RFID-based access control systems are used in buildings, offices, and secure areas to manage employee access and monitor movement.
4. Healthcare: RFID is utilized in hospitals and healthcare facilities to manage medical equipment, track patients, and enhance medication administration processes.
5. Animal Tracking: RFID tags are implanted in livestock and pets for identification and tracking purposes.
6. Library Management: RFID technology helps libraries automate the borrowing and returning of books, improving the overall efficiency of the library system.

RFID technology offers several benefits, including increased efficiency, reduced human error, real-time tracking, and enhanced data accuracy. However, it also raises privacy and security concerns due to the potential for unauthorized access or tracking of individuals and objects. As with any technology, it is essential to implement appropriate security measures to protect the data and ensure its ethical and responsible use.

Can RFID technology be used in a business for Managing Fixed assets and inventory?

Yes, RFID technology can be highly beneficial for managing fixed assets and inventory in a business. RFID provides several advantages over traditional barcode or manual tracking systems, making it a popular choice for asset and inventory management applications. Here are some ways in which RFID is used for this purpose:

1. Improved Efficiency: RFID enables faster and more efficient data capture compared to manual methods. With RFID, assets and inventory can be automatically scanned without line-of-sight requirements, allowing for bulk scanning and reducing the time spent on inventory counts.
2. Real-time Tracking: RFID provides real-time visibility into the location and status of assets and inventory. This ensures accurate and up-to-date information, helping businesses make informed decisions regarding stock levels, reordering, and asset allocation.
3. Accuracy and Reduction of Errors: RFID technology is known for its high accuracy rates compared to traditional methods. It reduces human errors associated with manual data entry, ensuring that the inventory and asset database remain precise.
4. Streamlined Auditing and Compliance: RFID simplifies the auditing process by automating asset and inventory verification. It can aid businesses in complying with regulatory requirements and internal auditing procedures.
5. Theft Prevention and Security: RFID tags can be used in conjunction with access control systems to monitor the movement of assets and inventory, thereby reducing the risk of theft and unauthorized access.
6. Asset Maintenance and Life-cycle Management: RFID tags can be integrated with maintenance systems to track asset service history, warranty periods, and scheduled maintenance, allowing businesses to optimize asset lifecycle management.
7. Analytics and Business Insights: RFID-generated data can be analyzed to identify patterns, optimize stock levels, and make data-driven decisions to improve overall efficiency and profitability.
8. Integration with Enterprise Systems: RFID systems can be seamlessly integrated with existing

enterprise resource planning (ERP) or warehouse management systems (WMS), providing a holistic view of the business's assets and inventory.

While RFID technology offers significant benefits, implementing an RFID-based asset and inventory management system requires careful planning and investment. Businesses need to consider factors such as tag selection, reader placement, and data integration to ensure a successful and efficient deployment.

As with any technology, businesses should also be mindful of data security and privacy concerns when implementing RFID systems. Access controls and encryption should be in place to protect sensitive asset and inventory information from unauthorized access.

Created with the Standard Edition of HelpNDoc: Powerful and User-Friendly Help Authoring Tool for Markdown Documents

ODF (Open Document Format) / PDF (Portable Document Format)

Advantages of ODF documents?

ODF (Open Document Format) documents offer several advantages over other proprietary formats like Microsoft Office's .docx, .xlsx, and .pptx. ODF is an open standard for storing and exchanging electronic documents, including text documents, spreadsheets, and presentations. Here are some key advantages of using ODF documents:

1. Interoperability: ODF is an open standard supported by various office productivity software, including LibreOffice, Apache OpenOffice, UltraOffice, or Calligra Suite. This ensures that ODF documents can be opened and edited across different platforms and software, reducing compatibility issues.
2. Vendor-Neutral: ODF is not tied to any specific vendor or company, making it a vendor-neutral format. This promotes fair competition and avoids vendor lock-in, giving users the freedom to choose different software applications for working with ODF documents.
3. Long-Term Accessibility: As an open standard, ODF is designed to be accessible and usable for an extended period. Its format specifications are publicly available, allowing developers and users to understand the structure of the files, ensuring long-term document access and preservation.
4. No Licensing Costs: Using ODF documents does not require any licensing fees or royalties. This can lead to cost savings for businesses and organizations that opt for open-source office productivity software supporting ODF.
5. Platform Independence: ODF documents can be created, edited, and viewed on different operating systems, such as Windows, macOS, Linux, and more. This cross-platform compatibility makes

collaboration and document sharing easier among users with diverse computing environments.

6. Future-Proofing: Since ODF is an open standard, it is less likely to become obsolete or unsupported in the future. This provides a level of future-proofing for documents created and stored in the ODF format.
7. Reduced File Size: ODF documents tend to have smaller file sizes compared to some proprietary formats, which can help in saving storage space and reducing file transfer times.
8. Security and Privacy: As an open standard, ODF allows security researchers to inspect and scrutinize the format for vulnerabilities. This enhances security and privacy, as potential issues can be identified and fixed promptly.
9. Accessibility Compliance: ODF documents can be made more accessible for users with disabilities, as they allow for structured content and support for assistive technologies.
10. International Standard: ODF is an international standard (ISO/IEC 26300), giving it official recognition and acceptance worldwide.

It's worth noting that while ODF has many advantages, different use cases and organizational requirements may still warrant the use of other file formats. In some scenarios, interoperability with proprietary formats might be necessary due to specific software dependencies or external collaboration needs. Nevertheless, adopting ODF as an open standard can offer significant benefits, especially in promoting data longevity, interoperability, and vendor independence.

Advantages of PDF documents?

PDF (Portable Document Format) documents have become widely popular for various applications due to the numerous advantages they offer. Here are some of the key advantages of using PDF documents:

1. Platform Independence: PDF documents can be viewed and opened on different operating systems, including Windows, macOS, Linux, Android, and iOS, without any compatibility issues. This platform independence ensures that the document's formatting remains consistent across devices.
2. Consistent Formatting: PDFs preserve the original formatting, fonts, images, and layout of a document regardless of the device or software used to open it. This ensures that the document appears the same to all users, avoiding layout discrepancies that may occur with other formats.
3. Security Features: PDF documents can be secured with passwords, encryption, and digital signatures, providing enhanced security for sensitive or confidential information. This makes PDFs suitable for sharing confidential documents securely.
4. Compact File Size: PDFs can compress large files without significant loss of quality, resulting in smaller file sizes compared to other formats. This makes them ideal for efficient document storage and faster

file transfers.

5. Read-Only Format: PDFs are typically read-only, meaning they can be opened and viewed by anyone but cannot be easily edited. This feature is beneficial for distributing documents that should not be altered, ensuring data integrity.
6. Print-Ready: PDFs are print-ready files, meaning they are designed to produce high-quality printouts. The format retains the original resolution and formatting, making it suitable for printing documents like brochures, posters, and professional reports.
7. Hyperlinks and Navigation: PDFs can include hyperlinks, bookmarks, and table of contents, enabling easy navigation within the document. This feature is helpful for lengthy documents, eBooks, and technical manuals.
8. Optical Character Recognition (OCR): PDFs can be made searchable through OCR technology, which converts scanned images or non-searchable text into selectable and searchable text.
9. Annotation and Markup: Users can add comments, highlights, and annotations to PDFs, making it a useful tool for collaborative document review and feedback.
10. Archival Stability: PDF is an ISO standard (ISO 32000-2), providing a level of assurance that the format will remain viable for the long term. This makes PDFs a suitable choice for archiving important documents and ensuring data longevity.
11. Multimedia Support: PDFs can incorporate multimedia elements such as audio, video, and interactive forms, making them suitable for interactive presentations and rich media content.

Overall, PDF documents offer a versatile and reliable format for a wide range of applications, including business documents, academic papers, legal contracts, eBooks, and more. Their ability to maintain document integrity, cross-platform compatibility, and security features make them an essential tool for efficient and secure document sharing and distribution.

Created with the Standard Edition of HelpNDoc: Effortlessly Create Encrypted, Password-Protected PDFs

Document formats and printing options

What document formats and printing options is used in businesses?

In businesses, various document formats and printing options are used based on the type of document, its purpose, and the specific requirements of the business. Here are some common document formats and

printing options used in businesses:

Document Formats:

1. PDF (Portable Document Format): PDF is widely used for creating documents that need to retain their formatting across different platforms. It is suitable for sharing and printing documents with consistent layout and design.
2. Microsoft Word (.docx): Word documents are commonly used for creating and editing text-based documents, such as letters, memos, reports, and other textual content.
3. Microsoft Excel (.xlsx): Excel spreadsheets are used for organizing and analyzing numerical data, financial calculations, and creating tables or charts.
4. Microsoft PowerPoint (.pptx): PowerPoint is used for creating presentations with slides, graphics, and multimedia elements.
5. Google Docs, Sheets, and Slides: Cloud-based alternatives to Microsoft Office applications, which offer collaborative document editing and sharing capabilities.
6. OpenDocument Format (ODF): An open standard format used for office productivity applications, similar to Microsoft Office formats.
7. Plain Text (.txt): Simple text files used for basic note-taking, code, or data storage.

Printing Options:

1. Single-Sided Printing: Printing on one side of the paper. Suitable for documents with minimal content or when cost-saving is a priority.
2. Double-Sided (Duplex) Printing: Printing on both sides of the paper. Reduces paper usage and is eco-friendly.
3. Color Printing: Printing documents in color to enhance visual appeal, highlight important information, or add graphics.
4. Grayscale Printing: Printing documents without color, using only shades of gray. Useful for saving color ink or when color is unnecessary.
5. High-Quality Printing: Printing with higher resolution and image quality, suitable for documents like marketing materials, presentations, and brochures.
6. Draft Printing: A quick, low-quality print option, often used for proofreading or reviewing documents before the final print.
7. Print to PDF: Converting documents into PDF format directly from the software, useful for sharing documents digitally or archiving.

8. Print Copies: Printing multiple copies of the same document, such as reports or flyers for distribution.
9. Print on Demand: Printing copies of documents as needed instead of large print runs. Useful for personalized materials or small quantities.
10. Wide Format Printing: Printing large-scale documents like posters, banners, or engineering drawings.

The choice of document format and printing options depends on factors such as the document's purpose, audience, distribution method, budget, and environmental considerations. Many businesses opt for a combination of digital formats and print options to meet their specific needs.

Created with the Standard Edition of HelpNDoc: Easily Add Encryption and Password Protection to Your PDFs

Document formats for export options

What document formats for export options is used in businesses?

In businesses, various document formats are commonly used for export options, depending on the type of data being exported and the intended use of the exported file. Exporting data allows businesses to share information with clients, partners, and employees in formats that are compatible with different software and systems. Here are some common document formats used for export options in businesses:

1. PDF (Portable Document Format): PDF is a widely used format for exporting various types of documents. It preserves the formatting, fonts, and layout of the original file, making it an excellent choice for sharing documents that should look consistent across different devices and platforms.
2. CSV (Comma-Separated Values): CSV is a plain-text format used to export tabular data, such as spreadsheets or databases. It is commonly used for data exchange between different software applications and can be easily imported into spreadsheet software.
3. Excel (.xlsx): Microsoft Excel format is widely used for exporting data from databases, accounting software, and other business applications. It allows users to work with the exported data in spreadsheet form, perform calculations, and create charts.
4. Word (.docx): Microsoft Word format is used for exporting text-based documents, such as reports, proposals, and contracts.
5. PowerPoint (.pptx): Microsoft PowerPoint format is used for exporting presentation slides, making it easy to share visual content with others.
6. HTML (Hypertext Markup Language): HTML format is used for exporting content to be displayed on websites or web-based applications. It is commonly used for online publishing and sharing

information on the internet.

7. XML (Extensible Markup Language): XML is a markup language used for exporting structured data that can be easily processed and parsed by other software applications.
8. JSON (JavaScript Object Notation): JSON is a lightweight data interchange format used for exporting and exchanging structured data between different systems and programming languages.
9. RTF (Rich Text Format): RTF is used for exporting formatted text documents that can be opened by various word processing applications.
10. Image Formats (JPG, PNG, GIF): Image formats are used for exporting graphical content, such as charts, diagrams, and illustrations.
11. CAD Formats (DWG, DXF): For businesses dealing with engineering and architectural designs, CAD formats like DWG and DXF are used for exporting technical drawings.

The choice of document format for export depends on factors such as the type of data, the recipient's software compatibility, the need for data structure, and the level of interactivity required. Businesses often provide multiple export options to cater to the preferences and needs of their clients, partners, and stakeholders.

Created with the Standard Edition of HelpNDoc: Make your documentation accessible on any device with HelpNDoc

Print on Demand and PDF documents

What is Print on Demand (POD) and PDF documents?

Print on Demand (POD) and PDF documents are two related concepts often used in the context of digital publishing and printing.

Print on Demand (POD)

Print on Demand is a publishing and printing model where copies of a book, document, or other printed materials are produced individually or in small batches in response to specific orders. Instead of printing a large quantity of copies upfront and storing them in inventory, POD allows for printing copies as needed. This approach is particularly useful for self-publishing authors or small publishers, as it reduces upfront costs and eliminates the need for large print runs.

Here's how POD works:

1. Order Placement: When a customer places an order for a book or document, the order is sent to the POD service provider.
2. Printing: The POD service provider prints the requested number of copies using digital printing technology. Each copy is printed on-demand, typically within a short timeframe.
3. Shipping: Once the printing is complete, the printed copies are shipped directly to the customer or the designated recipient.

POD is commonly used for books, manuals, reports, and other types of printed materials. It allows for greater flexibility, reduced wastage, and the ability to keep content up-to-date since revisions can be easily incorporated into new printings.

PDF Documents

A PDF (Portable Document Format) is a file format used to present documents in a manner independent of software, hardware, and operating systems. It was created by Adobe and has become a widely used format for sharing and distributing documents. PDFs preserve the original formatting, fonts, and images of a document, ensuring consistent display across different devices and platforms.

PDF documents are commonly used for various purposes, including:

1. Electronic Distribution: PDFs are often used for distributing digital documents, such as ebooks, reports, whitepapers, and brochures, over the internet or via email.
2. Printing: PDFs are also used for high-quality printing. When a document is saved in PDF format, it ensures that the printed version will retain the intended layout and appearance.
3. Archiving: PDFs are a popular choice for archiving documents due to their stability and compatibility over time.
4. Forms and Contracts: PDFs can be used for creating interactive forms and contracts that users can fill out electronically.

When it comes to POD, PDF documents are often used as the source files for printing. The POD service provider receives the PDF files and uses them to generate the printed copies of the document. This process ensures that the printed version of the document matches the digital version precisely, maintaining consistent formatting and layout.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

New to Accounting

Welcome to the world of accounting with osFinancials5/TurboCASH5 accounting software! Whether you are starting a new business or taking over the financial management of an existing one, osFinancials5/TurboCASH5 provides a powerful and easy-to-use accounting solution for your needs. With osFinancials5/TurboCASH5, you can easily manage your finances, keep track of transactions, generate reports, and more. This software is designed to simplify accounting tasks and provide accurate financial information to help you make informed decisions. As a beginner to accounting and osFinancials5/TurboCASH5, we will guide you through the basics of the software and help you get started on your journey towards financial management success.

osFinancials5/TurboCASH5 accounting software can help you save time and reduce errors, allowing you to focus on other important aspects of your business. In this introduction, we will discuss the benefits of using osFinancials5/TurboCASH5 accounting software and how it can help simplify your accounting tasks, even if you have little to no experience with accounting.

Many accounting systems have been marketed as "*easy-to-use*," but their main function is to present financial reports or statements to investors, bank managers, creditors, and consultants in an understandable format. These reports provide crucial financial information that is essential for decision-making.

However, systems that take shortcuts and fail to comply with accounting principles often fail to communicate important financial information to accountants. Accountants have their own language, and if you are not familiar with it, accounting systems like osFinancials5/TurboCASH5 may seem obscure at first. You don't need to be fluent in accounting language, but it's important to understand the basics.

Fortunately, osFinancials5/TurboCASH5 is a Generally Accepted Accounting Practice (GAAP) compliant system. It follows accounting principles and standards that have been widely accepted and adopted by the accounting profession. Moreover, osFinancials5/TurboCASH5 provides steps and features that can guide users in the right direction and minimize the need for extensive accounting knowledge.

Online Help - Documentation

osFinancials5/TurboCASH5 accounting software provides a comprehensive online help system in both English and Afrikaans. This help system is designed to assist users in understanding and navigating the osFinancials5/TurboCASH5 accounting software, as well as to provide guidance on accounting principles and practices. Whether you are new to accounting or an experienced professional, the help system offers a wealth of information to help you get the most out of osFinancials5/TurboCASH5. With easy-to-follow instructions and detailed explanations, the help system is an invaluable resource for anyone using

osFinancials5/TurboCASH5 for their accounting needs.

Hands-on Tutorials

osFinancials5/TurboCASH5 installation provides tutorial Sets of Books in both English and Afrikaans. These tutorial books allow users to explore different settings, transactions, and reports within the software. Here are the available tutorial sets:

Accounting Made Easy

English tutorials (using separate receipt and payments journals for banking / cash transactions)



The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\ENGLISH\" folder:

- *HANDYMAN (No transactions)*
- *HANDYMAN-A (Unposted transactions)*
- *HANDYMAN-B (Posted transactions)*

Accounting Made Easy - Bank Import

English tutorials (using the BankImport plugin for banking / cash transactions)

The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\BANK-IMPORT\" folder:

- *HANDY-BANK (No transactions).*
- *HANDY-BANK-A (Unposted transactions)*
- *HANDY-BANK-B (Posted transactions).*
- *HANDY-BANK-UNPOSTED-*

Rekeningkunde Met Gemak (Afrikaans)

Afrikaanse handleidings (gebruik aparte ontvangste- en betalingsjoernale vir bank- / kontanttransaksies)

Die volgende Stel Boeke gebaseer op die Afrikaanse handleidings, is in die "…\bin\Tutorials\AFRIKAANS\"-lêergids geïnstalleer:

- *NUTSMAN (Geen transaksies).*
- *NUTSMAN-A (Ongeposteerde transaksies)*
- *NUTSMAN-B (Geposteerde transaksies).*

BANK-STATEMENT – Posted transactions, excluding bank / cash transactions. Bank statement needs to be imported from the "…\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS" folder.

To open the tutorial Sets of Books, installed in the "*bin / Tutorials*" directory, you need to click on the Open icon on the Start ribbon. On the "*Set of Books*" screen, click on the Browse icon and select the desired tutorial Set of Books that you wish to follow.

Additionally, there are other tutorial folders available with relevant files for import into batches. The following folders contains files which may be imported into batches:

- *EXPORTED-BATCH-Delimited-File – Exported batch transactions using the "Write delimited file" option and may be imported into a batch using the "Delimited file import" option (F9:Process icon) on batches.*
- *EXPORTED-BATCH-Spreadsheets – Exported batch transactions in the *.xlsx (Excel 2007-365) file format. These transaction files may be opened in the Spreadsheet import icon on batches, and imported into a selected batch.*

These tutorials are designed to guide users, regardless of their accounting experience, through the basics of accounting and demonstrate how to effectively use osFinancials5/TurboCASH5 for managing business finances. The tutorials cover various aspects, including software features, chart of accounts setup, transaction creation, processing sales and purchase documents, and report generation. They also serve as a reference guide to osFinancials5/TurboCASH5.

By the end of these tutorials, users will have gained a solid understanding of the accounting process and will be able to confidently utilize osFinancials for managing their business finances.

OTHER TUTORIALS

Additionally, there are other tutorials for exploring the activation, processing, and reporting of Cost centres and Projects within osFinancials5/TurboCASH5.

COST-CENTRES

Tutorials / examples to explore the activation, processing and reporting of Cost centres in osFinancials5/TurboCASH5. See - Cost centres in this Help file.

The following Set of Books based on this tutorial, is installed in the "...\bin\Tutorials\COST-CENTRES\" folder:

- COST-CENTRES-A (transactions and documents not posted to the ledger)
- COST-CENTRES-B (transactions and documents posted to the ledger).

PROJECTS

Tutorials / examples to explore the activation, processing and reporting of Projects in osFinancials5/TurboCASH5. See - Projects in this Help file.

The following Set of Books based on this tutorial, is installed in the "...\bin\Tutorials\PROJECTS\" folder:

- PROJECTS-A (transactions and documents not posted to the ledger)
- PROJECTS-B (transactions and documents posted to the ledger).

Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with a Help Authoring Tool

Importance of accounting

Accounting is important for several reasons:

1. Keeping track of financial transactions: Accounting provides a structured way to keep track of financial transactions such as sales, purchases, expenses, and revenues. Without accounting, it would be difficult to know how much money is coming in and going out of a business, making it hard to make informed decisions.
2. Making informed decisions: Accounting provides the financial information necessary for making informed decisions. For example, a business owner can use financial statements to analyze their company's financial performance, identify areas of improvement, and make decisions that will improve the financial health of their business.
3. Complying with regulations: Accounting is necessary for complying with tax laws and other regulations. Financial records must be kept in accordance with accounting principles and standards, which helps ensure that a business is in compliance with the law.
4. Attracting investors: Investors are often interested in a company's financial performance before making a decision to invest. Accounting provides the necessary financial information to potential investors to make an informed decision about investing in a business.
5. Facilitating communication: Accounting facilitates communication between different stakeholders in a

business, such as managers, employees, investors, and lenders. Financial reports and statements provide a common language for stakeholders to understand a company's financial position and performance.

Overall, accounting is essential for the effective management of a business, compliance with regulations, making informed decisions, and attracting investors. Without accounting, it would be difficult to keep track of financial transactions, assess a company's financial performance, and communicate financial information to stakeholders.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

History of accounting

The history of accounting dates back thousands of years, with the earliest known records of accounting practices dating back to ancient civilizations such as Mesopotamia and Egypt. These early accounting systems were primarily manual, involving the use of clay tablets, papyrus scrolls, and other primitive record-keeping methods.

In manual accounting systems, transactions were recorded by hand in a ledger or journal, and account balances were calculated manually using a pen and paper. This process was time-consuming and prone to errors, and it often required a team of trained accountants to manage a company's financial records.

With the advent of computers in the 20th century, accounting systems began to shift towards automation. The first computerized accounting systems were developed in the 1950s and 1960s, and they quickly gained popularity among businesses looking to streamline their financial processes.

During the 1980s and 1990s, accounting software became more sophisticated and widely available, making it easier for businesses to transition from manual bookkeeping to computerized accounting systems. The advantages of computerized accounting systems, such as increased efficiency, accuracy, and productivity, made them a popular choice among businesses of all sizes. As technology continued to advance, computerized accounting systems became even more powerful and customizable, allowing businesses to tailor their financial processes to their specific needs and requirements. Today, computerized accounting systems are the norm for most businesses, and they continue to evolve and improve with advances in technology.

Automated systems like accounting software can process large volumes of data quickly and accurately, which can help reduce the risk of errors that can occur when data is entered manually. This can save business owners and accountants a significant amount of time, allowing them to focus on other important tasks such as analysis, strategy, and decision-making. In addition, automated systems can also provide

real-time insights into a company's financial health, allowing business owners to make informed decisions about their business.

One of the most significant advantages of computerized accounting systems is their ability to generate real-time financial reports, allowing businesses to make informed decisions based on up-to-date financial data. Additionally, computerized systems can help businesses stay compliant with tax laws and other financial regulations, reducing the risk of penalties or legal issues.

Overall, while manual accounting systems have a long and rich history, computerized accounting systems have revolutionized the way businesses manage their finances, making accounting faster, more accurate, and more accessible than ever before.

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Accounting process

The accounting process is a set of steps that businesses and organisations follow to record, analyse, and report their financial transactions. It involves several stages, which typically include:

1. Recording transactions: This is the first step in the accounting process, where all financial transactions are documented and recorded in the company's books as they occur. These transactions can include sales, purchases, expenses, and any other financial activity.
2. Classifying transactions: After recording, the transactions are categorised into different accounts based on the type of transaction. Each transaction is classified according to the appropriate account in the chart of accounts. The chart of accounts is a list of all the accounts used by the business to record transactions.
3. Posting transactions: Once the transactions are recorded and classified, they are then posted to the general ledger, which is a master record of all the company's accounts.
4. Adjusting entries: At the end of the accounting period, adjusting entries are made to ensure that the financial statements accurately reflect the company's financial position. These entries may include accruals or deferrals of expenses or revenue.
5. Preparing financial statements: Financial statements, such as the income statement, balance sheet, and statement of cash flows, are then prepared to provide an overview of the company's financial position and performance.
6. Closing the books: After the financial statements are prepared, the books are closed for the accounting period, and the cycle starts again for the next period.

Overall, a computerised accounting system can streamline the accounting process, provide accurate and timely financial information to stakeholders, including investors, creditors, and management, and improve the efficiency of the business.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Methods of recording

In manual accounting, transactions are recorded by hand using physical documents such as paper ledgers and journals. The process is time-consuming and relies heavily on human effort and accuracy. Here are some key points about manual accounting:

1. Recording: Transactions are manually recorded in journals or books of original entry, such as cash receipts, cash payments, sales, and purchases. This involves writing down the details of each transaction, including the date, description, and amounts.
2. Calculation: Manual calculations are performed to determine the debit and credit amounts for each transaction. This requires careful attention to detail and accuracy in adding, subtracting, and balancing the accounts.
3. Posting: After recording the transactions in the journals, the information is transferred to the general ledger and subsidiary ledgers. Each transaction is posted to the appropriate accounts, updating the balances.
4. Trial Balance: A trial balance is prepared to ensure the equality of debit and credit balances. It lists all the accounts and their balances, serving as a preliminary check on the accuracy of the recorded transactions.
5. Financial Statements: Based on the information from the general ledger, financial statements such as the income statement (profit and loss statement), balance sheet, and cash flow statement are manually prepared. These statements provide an overview of the financial performance and position of the business.
6. Safeguarding Records: In manual accounting, it is important to keep physical records and supporting documents safe from unauthorized access, damage, or loss. This may involve storing documents in secure locations, using lockable cabinets, or implementing backup procedures.

On the other hand, computerized accounting involves using specialized software to automate and streamline the accounting processes. Here are some key points about computerized accounting:

1. Data entry: Financial transactions are entered into the accounting software using a computer. This eliminates the need for manual writing and calculations, reducing the chances of errors.

2. Processing: The accounting software automatically processes the transactions, updates the relevant accounts, and performs calculations. This ensures accuracy and consistency in the accounting records.
3. Financial reports: Computerized accounting systems can generate various financial reports, such as the trial balance, income statement, balance sheet, and various reports, with just a few clicks. These reports can be customized and analyzed more easily than in manual accounting.
4. Automation: Computerized accounting systems automate tasks such as posting transactions, calculating balances, and generating reports. This saves time and reduces the risk of errors.
5. Data Security: Computerized accounting systems provide options for data security and backup. Data can be stored securely and regular backups can be taken to protect against data loss.
6. Scalability: Computerized accounting systems are scalable and can handle a large volume of transactions and data. They can accommodate the growing needs of a business as it expands.

Ultimately, the choice between manual and computerized accounting depends on factors such as the size of the business, the complexity of transactions, available resources, and the need for accuracy and efficiency. Larger businesses with a high volume of transactions generally benefit more from computerized accounting, while smaller businesses may find manual accounting sufficient for their needs.

Created with the Standard Edition of HelpNDoc: Free Web Help generator

Manual system

In a manual accounting system, financial transactions are recorded by hand in a journal or ledger. The process typically involves the following steps:

1. Identify the transaction: The first step is to identify the transaction that needs to be recorded, such as a sale, purchase, payment, or receipt of funds.
2. Record the transaction: Once the transaction has been identified, it is recorded in a journal or ledger. This involves writing down the date, amount, and description of the transaction.
3. Post to accounts: The next step is to post the transaction to the appropriate accounts in the ledger. For example, a sale would be recorded in the sales account, while a purchase would be recorded in the purchases account.
4. Reconcile accounts: At the end of a period, the accounts are reconciled to ensure that they balance. This involves comparing the totals of the debits and credits in each account to ensure that they are equal.
5. Prepare financial statements: Finally, the financial statements are prepared based on the information

in the ledger. These may include a balance sheet, income statement, and cash flow statement.

Overall, the manual accounting system can be time-consuming and prone to errors, as it relies on human input and calculations. However, it can be useful for small businesses or individuals who have a limited number of transactions to record.

In a manual accounting system, transactions are recorded and processed using physical documents and handwritten entries. The manual system can be illustrated as follows:



Here is a summary of the basic processes involved in a manual system:

Step	*Process*	*Description*
1.	*Input*	*All transaction data, such as cash slips, deposits, cheques, and invoices, are sorted according to their type. Then, the information from these documents is manually written into specific journals.*
2.	*Process*	*The journals, which contain the recorded transactions, are balanced by ensuring the debits and credits are equal. The information from the journals is then posted manually to the general ledger and subsidiary ledgers. This process can be time-consuming and prone to errors due to manual calculations and entries.*
3.	*Output*	*A trial balance is prepared to verify the accuracy of the recorded transactions by listing the debit and credit balances. Financial reports and statements, including the trial balance, income statement, balance sheet, debtor statements, creditor remittance advice, and others, are then drafted based on the information recorded in the ledgers.*
4.	*Safeguard records*	*It is crucial to protect the books of accounts and supporting documents from unauthorized access, fire, theft, and other risks. Proper measures should be taken to secure physical records to ensure their integrity and availability for future reference.*

Overall, while manual accounting systems can be suitable for small businesses or individuals with a limited number of transactions, they are time-consuming and more susceptible to errors compared to computerized accounting systems.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Computerised system

In a computerized accounting system, financial transactions are entered and processed using accounting software such as osFinancials5/TurboCASH5. The system allows for the pre-configuration of the accounting database and includes processes for journal or batch processing, sales documents (quotes, invoices, and credit notes), and purchase documents (orders, purchases, and supplier returns). Transactions are captured and processed in the software, which automatically updates the relevant records when transactions are posted to the ledger.

The computerised system can be illustrated as follows:



The basic processes in a computerised system involves the following steps:

Step	*Process*	*Description*
1.	*Input*	*Identify the transaction from source documents, such as a sale, purchase, payment, or receipt of funds, and enter it into the accounting software using a keyboard and mouse. osFinancials5/TurboCASH5 provides specific forms and templates to guide the user in entering the required information for transactions.* *To capture transactions in osFinancials5/TurboCASH5, there are two options available: journals or batches, and documents.* · *Journals or Batches: osFinancials5/TurboCASH5 allows users to capture transactions using journals or batches. Batch types can be preconfigured to provide specific options that minimize errors during transaction entry. This means that different types of transactions can be grouped together in a batch for easier processing and tracking.* · *Documents: osFinancials5/TurboCASH5 also supports the creation and processing of sales documents (such as quotes, invoices, and credit notes) and purchase documents (such as orders, purchases, and supplier returns). Users can enter the required information for these*

Step	Process	Description
		documents using specific forms and templates provided by osFinancials5/TurboCASH5. Additionally, users have the option to print a source document using document layout files, which allows for easy documentation and record-keeping.
		Both options aim to simplify the process of capturing transactions by providing structured forms, templates, and preconfigured batch types. This helps ensure that the required information is entered accurately and efficiently into the accounting software.
2.	*Process*	*Once the transactions are entered or captured in the respective journals or documents using osFinancials5/TurboCASH5, the transaction data is automatically stored in the system. Users have the option to review and check these journals and documents and make any necessary edits or modifications.*
		After the transactions are captured and reviewed, the next step is to balance the journals. Balancing the journals ensures that the debits and credits of each transaction match and that the accounting equation remains in balance.
		Once the journals are balanced, the processed sales documents (quotes, invoices, credit notes) and purchase documents (orders, purchases, supplier returns) are processed. During this processing, the relevant accounts in the general ledger and subsidiary ledgers, such as the debtor's ledger and creditor's ledger, are automatically updated.
		In addition to updating the financial accounts, the computerized accounting system, like osFinancials5/TurboCASH5, also automatically updates the stock (inventory) records when processing documents. This means that the stock levels and values are adjusted based on the transactions related to purchases, sales, returns, and any other inventory-related activities.
		By automatically updating these records, the computerized accounting system ensures that the financial and inventory information is accurate and reflects the current state of the business. It eliminates the need for manual calculations and reduces the risk of errors or discrepancies in the records.
3.	*Output*	*After the transactions have been processed and posted to the ledger, osFinancials5/TurboCASH5 automatically updates all applicable records. This ensures that the financial information is up to date and accurately reflects the transactions that have taken place.*
		Once the updates are made, osFinancials5/TurboCASH5 provides various outputs and reports that can be easily accessed by the user. These reports can be generated with just a few keystrokes or mouse clicks, making it convenient and efficient to obtain the necessary information. Some of the available reports include:
		• *Trial balance: This report summarizes the balances of all accounts in the general ledger, showing the total debits and credits for each account. It helps in verifying that the*

Step	Process	Description

accounting equation (Assets = Liabilities + Equity) is in balance.

- *Income statement: Also known as the profit and loss statement, this report shows the revenues, expenses, and net income or net loss for a specific period. It provides an overview of the company's financial performance.*
- *Balance sheet: This report presents the financial position of the business at a specific point in time. It includes the assets, liabilities, and equity of the company, giving a snapshot of its financial health.*
- *Debtor statements: These statements provide details of outstanding customer balances, including invoices, payments, and any outstanding amounts. They help in monitoring and managing accounts receivable.*
- *Creditor remittance advises: These reports provide information about amounts owed to suppliers, including invoices, payments, and any outstanding balances. They assist in managing accounts payable.*

These are just a few examples of the reports that osFinancials5/TurboCASH5 offers. There may be additional options and customization features available within the software to cater to specific reporting requirements or preferences.

Spreadsheets - In addition to generating reports within the osFinancials5/TurboCASH5 software, you have the option to export certain reports and data grids to spreadsheets for further analysis or sharing. Here are some key points regarding exporting reports and data from osFinancials:

- *Reports: Reports such as the Trial balance, Income statement and Balance sheet can be exported to spreadsheet formats like Excel or CSV (Comma-Separated Values) files. This allows you to manipulate the data, create custom charts or graphs, and perform additional calculations as needed.*
- *Data grids: Within the software, there are grids that display information on various modules, including Debtors, Creditors, Documents and Stock (Inventory). These grids provide a tabular view of the data, and you have the ability to apply specific filters to refine the displayed information based on your requirements.*
- *Filtering and exporting: Within the data grids, you can apply filters to display specific subsets of data that match your criteria. Once you have applied the desired filters and have the relevant data displayed, you can export the filtered data to a spreadsheet file. This export functionality allows you to work with the data in spreadsheet software for further analysis, reporting, or integration with other systems.*

Step	Process	Description

- *Spreadsheet compatibility: The exported data is typically compatible with popular spreadsheet software like Microsoft Excel, Google Sheets, or other similar applications. This ensures that you can seamlessly import the exported data into these tools without any compatibility issues.*

By exporting reports and data grids to spreadsheet files, you have the flexibility to analyse and manipulate the information further based on your specific needs. This enables you to perform customized calculations, create visualizations, or combine the data with other sources for comprehensive reporting and decision-making purposes.

Pivot tables

osFinancials5/TurboCASH5 provides its own built-in pivot table functionality, allowing users to view and analyse reports such as the Trial Balance, Income statement, Balance sheet, and Budgets directly within the software. This means that you don't necessarily need to export the reports to a spreadsheet to utilize pivot tables.

By using the pivot table feature within osFinancials5/TurboCASH5, you can perform dynamic analysis and customization on the data directly in the software. You can define rows, columns, values, and filters within the pivot table to organize and summarize the data according to your specific needs. This enables you to gain insights, identify patterns, and make informed decisions based on the financial information presented in these reports.

Furthermore, if you choose to export the reports to a spreadsheet, you can still leverage the pivot table functionality within the spreadsheet software to further analyse and manipulate the data. This provides you with the flexibility to use either osFinancials5/TurboCASH5' built-in pivot tables or the pivot table features of your preferred spreadsheet software, depending on your preferences and requirements.

In summary, osFinancials offers its own pivot table functionality for viewing and analyzing reports, and if desired, you can also export the reports to a spreadsheet to utilize the pivot table features of the spreadsheet software. Both options allow you to perform dynamic and customizable analysis on your financial data.

4.	*Backups*	*It is important to safeguard the books of account and supporting documents from unauthorized access, fire, theft, and other risks. Computerized accounting systems often offer features like automatic backups, data encryption, and audit trails to enhance data security and reliability.*

Safeguarding the books of account and supporting documents is crucial to protect sensitive financial information and ensure business continuity. Here are some key considerations:

1. *Unauthorized access: Implement proper access controls to restrict access to the accounting*

Step	Process	Description

system and sensitive data. Use strong passwords, user permissions, and authentication mechanisms to prevent unauthorized individuals from accessing the system.

2. *Fire and theft: Store physical documents and backup files in a secure location that is protected from fire and theft risks. This could include using fireproof safes or off-site storage facilities with appropriate security measures.*
3. *Backup files: Regularly create backups of your accounting database and store them in a safe external location. This could involve using external hard drives, cloud storage, or backup services. Ensure that backups are performed consistently and verify their integrity periodically.*
4. *Disaster recovery plan: Develop a comprehensive disaster recovery plan that outlines procedures for restoring the accounting system in the event of unforeseen circumstances. This plan should include steps for recovering data from backup files and restoring the system to a functional state.*
5. *Test backups and restoration: Periodically test the backup files and restoration process to ensure they are working correctly. This helps identify any issues or discrepancies in the backup files and allows for adjustments or improvements to be made.*
6. *Data encryption: Consider encrypting sensitive financial data to add an extra layer of protection. Encryption ensures that even if unauthorized individuals gain access to the data, they won't be able to decipher or use it without the encryption key.*

By implementing these measures, you can enhance the security and integrity of your accounting system and be prepared to recover quickly in the event of any unforeseen circumstances or data loss.

Overall, the computerised accounting system is faster, more efficient, and less prone to errors than a manual system. It can handle a large number of transactions and provide real-time updates on the financial status of the business.

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Accounting cycle and the transaction cycle

Is there a difference between the accounting cycle and the transaction cycle?

Yes, there is a difference between the accounting cycle and the transaction cycle.

The transaction cycle involves the process of recording and processing business transactions from their occurrence to their inclusion in the financial statements. This includes identifying, measuring, recording, and verifying the transactions. The transaction cycle includes activities such as journalizing, posting, preparing trial balances, and making adjusting entries.

On the other hand, the accounting cycle refers to the process of recording, classifying, and summarizing financial transactions during a specific accounting period. The accounting cycle involves a series of steps that are completed in a specific order, including analyzing and recording transactions, adjusting entries, preparing financial statements, and closing the books.

In summary, the transaction cycle is focused on the process of recording individual transactions, while the accounting cycle is concerned with the overall process of preparing financial statements for a specific accounting period.

The basics of accounting include the accounting equation and transaction cycle

The accounting equation is the foundation of double-entry accounting, which states that assets are equal to liabilities plus equity. This equation must always balance, and any changes to one side of the equation must be reflected in the other side.

The transaction cycle involves the process of recording and processing business transactions, from their occurrence to their inclusion in the financial statements. The transaction cycle begins with the identification of a business transaction, such as a sale or a purchase, which is then analyzed to determine the accounts affected and the amount of the transaction. The transaction is then recorded in a journal or a computer system, posted to the relevant accounts in the general ledger, and a trial balance is prepared to ensure that the accounts are in balance.

Adjusting entries may be made at the end of the accounting period to ensure that the accounts accurately reflect the financial position of the company, and the adjusted account balances are used to prepare financial statements such as the income statement, balance sheet, and cash flow statement. Finally, the temporary accounts are closed and the permanent accounts are updated to prepare for the next accounting period.

By following the accounting equation and transaction cycle, companies can ensure that their financial

records are accurate and up-to-date, which is essential for making informed business decisions.

The accounting cycle

The accounting cycle is the process of recording and processing all financial transactions of a company, from when the transaction occurs, to its representation on the financial statements, to closing the accounts. The accounting cycle consists of eight steps:

1. Transactions - This step involves identifying a business transaction, which can be a sale, purchase, payment, or receipt of funds.
2. Journal Entries
3. Posting
4. Trial Balance
5. Worksheet
6. Adjusting Entries
7. Financial Statements
8. Closing Entries

The transaction cycle

The transaction cycle is a set of procedures that companies follow to ensure that all transactions are recorded accurately and completely1. It includes four stages4:

Authorization

Recording

Verification

Reporting

What is the steps in the accounting cycle?

The steps in the accounting cycle can vary depending on the company and its specific needs, but generally, the accounting cycle involves the following steps:

1. Analyzing and recording transactions: This step involves identifying and recording all business transactions that occurred during the accounting period, using source documents such as invoices,

receipts, and bank statements.

2. Posting to the ledger: In this step, the recorded transactions are posted to the relevant accounts in the general ledger, where all accounts are organized by category.
3. Preparing a trial balance: A trial balance is a listing of all the account balances at a specific point in time. This step helps to ensure that the total debits and credits recorded in the ledger are equal and that the accounts are in balance.
4. Making adjusting entries: Adjusting entries are made to ensure that the accounts accurately reflect the financial position of the company at the end of the accounting period. These entries include accruals, prepayments, and depreciation.
5. Preparing financial statements: The adjusted account balances are used to prepare financial statements such as the income statement, balance sheet, and cash flow statement.
6. Closing the books: This step involves transferring the balances of temporary accounts such as revenue and expenses to the permanent accounts such as retained earnings. This step resets the temporary accounts to zero to prepare for the next accounting period.
7. Post-closing trial balance: This is a final check to ensure that all temporary accounts have been closed and the permanent accounts have been updated.

These steps are repeated each accounting period to ensure accurate and up-to-date financial records.

What is the steps in the transaction cycle?

The transaction cycle involves the process of recording and processing business transactions from their occurrence to their inclusion in the financial statements. The steps in the transaction cycle generally include:

1. Identifying the transaction: This step involves identifying a business transaction, which can be a sale, purchase, payment, or receipt of funds.
2. Analyzing the transaction: In this step, the transaction is analyzed to determine the accounts affected and the amount of the transaction.
3. Recording the transaction: The transaction is recorded in a journal or a computer system to create a permanent record of the transaction.
4. Posting to the ledger: The recorded transaction is posted to the relevant accounts in the general ledger.
5. Preparing a trial balance: A trial balance is prepared to ensure that the total debits and credits recorded in the ledger are equal and that the accounts are in balance.

6. Making adjusting entries: Adjusting entries may be made at the end of the accounting period to ensure that the accounts accurately reflect the financial position of the company.
7. Preparing financial statements: The adjusted account balances are used to prepare financial statements such as the income statement, balance sheet, and cash flow statement.
8. Closing the books: This step involves transferring the balances of temporary accounts such as revenue and expenses to the permanent accounts such as retained earnings. This step resets the temporary accounts to zero to prepare for the next accounting period.

These steps ensure that all business transactions are accurately recorded and included in the financial statements. The transaction cycle is an ongoing process that occurs throughout the accounting period.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Double-entry accounting system

What is the double-entry accounting system?

The double-entry accounting system is a method of recording financial transactions that has been used for centuries by businesses, accountants, and bookkeepers. It is based on the principle that every financial transaction has two equal and opposite effects on the accounting equation, which must be recorded in two accounts.

Under the double-entry accounting system, every transaction is recorded in at least two accounts: a debit account and a credit account. Debits and credits must always balance, meaning that the total amount debited must equal the total amount credited.

For example, let's say that a company receives $1,000 in cash from a customer for a product sale. The double entry accounting system would record this transaction as follows:

- The company's Cash account is debited for $1,000, which increases the Cash balance.
- The company's Sales Revenue account is credited for $1,000, which increases the Sales Revenue balance.

In this example, the debits and credits are equal and balance each other out, which ensures that the company's accounting equation remains in balance.

Assets = Liabilities + Capital

The double entry accounting system is important because it provides a systematic and accurate way to record financial transactions and generate financial statements. It allows businesses to track their financial performance, monitor their cash flow, and make informed financial decisions based on reliable data.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Debits and Credits

What are debits and credits?

Debits and credits are the two basic and opposite accounting entries used to record financial transactions in double-entry bookkeeping.

In a financial transaction, there is always an equal amount of debits and credits. Debits represent an increase in assets or a decrease in liabilities or capital, while credits represent a decrease in assets or an increase in liabilities or capital.

For example, if a company purchases inventory for cash, the entry would be a debit to inventory (an increase in the company's assets) and a credit to cash (a decrease in the company's assets).

The following example illustrates debits and credits:

Debit	Credit
The account receiving the value is debited.	The account giving the value is credited.

On 1 March your business sells goods to the value of 100 to a customer, Tom on credit and issues a sales invoice for the transaction:

1. On 1 March the customer receives the goods to the value of 100 from the business.

Debit	*Customer Tom's Account*				Credit
Date	Description	Amount	Date	Description	Amount
1 March	Sales Account - Goods	100			

2. On 1 March the business gives the goods to the value of 100 to the customer.

Debit	***Sales Account***				Credit
Date	Description	Amount	Date	Description	Amount
			1 March	Tom's Account - Goods	100

The customer account is debited and the sales account is credited.

What happens if the customer settles his account with the business on 20 March? Your business will issue a receipt of 100 as a source document.

1. On 20 March Tom gives the money to the value of 100 to the business.

Debit			Customer Tom's Account		Credit
Date	Description	Amount	Date	Description	Amount
			20 March	Bank	100

2. On 20 March the business receives the money to the value of 100 from Tom.

Debit			Bank		Credit
Date	Description	Amount	Date	Description	Amount
20 March	Tom's Account	100			

You will debit the bank and credit the customer account.

Only transactions between the business and another entity (i.e. the purchasing of a computer for office use) should be recorded.

Personal transactions made by the business owner should not be included in the business's accounting records.

This is because the business and the owner are considered separate entities in the eyes of the law.

Created with the Standard Edition of HelpNDoc: Keep Your Sensitive PDFs Safe with These Easy Security Measures

Transaction cycle

What is the transaction cycle?

The transaction cycle in accounting refers to the process of recording financial transactions in a systematic manner. This process typically includes several steps:

1. Identification: This step involves identifying the financial transactions that need to be recorded. Transactions can include purchases, sales, payments, receipts, and other financial activities.
2. Recording: Once the transactions have been identified, they are recorded in a journal. This step involves recording the details of each transaction, such as the date, amount, and accounts involved.

3. Posting: After the transactions have been recorded, they are posted to the appropriate accounts in the general ledger. This step involves transferring the information from the journal to the ledger accounts.

4. Trial balance: A trial balance is prepared to ensure that the total debits equal the total credits. This step is important to identify any errors that may have been made during the recording or posting process.

5. Adjusting entries: Adjusting entries are made to update the accounts for any items that were not recorded during the regular transaction cycle. Examples include depreciation, prepaid expenses, and accruals.

6. Financial statements: Finally, financial statements are prepared to summarize the financial transactions for a specific period. These statements include the income statement and balance sheet. Financial information is the summary of all this financial data into the following two basic reports:

    - Income statement reflecting how well or poor the business or organisation has performed over a specific period.
    - Balance sheet reflecting the business or organisations financial position as at a specific date.
    - Additional summarised information with respect to certain items and budgets may also be necessary to determine performance or financial position.

      osFinancials5/TurboCASH5 contains many of these reports and includes a report designer to supplement your own reports.

The transaction cycle is an important part of the accounting process as it ensures that all financial transactions are recorded accurately and in a timely manner.

The transaction cycle and transactions

Financial data is created through various business transactions, including investments by the owner, purchases of assets, payment of expenses, and sales of goods or services. These transactions impact the accounting equation, which is:

Assets = Capital + Liabilities

This equation must always remain balanced. If assets increase, either capital or liabilities must also increase, and if assets decrease, capital or liabilities must also decrease.

Each type of transaction affects the equation in a specific manner. For instance, when the owner invests

cash, the bank account (asset) and capital increase. If the business purchases an asset with cash, the vehicle (asset) increases and the cash account (asset) decreases. When the business buys assets on credit, the asset account increases and the creditor account (liability) also increases.

In the same vein, if the business incurs expenses and pays for them with cash, the expense account increases and the cash account (asset) decreases. If expenses are incurred on credit, the expense account increases, and the creditor account (liability) also increases. If the business sells services or goods for cash, the cash account (asset) and the income (sales) account increase. When the business sells goods or services on credit, the debtor account (asset) increases, and the sales account (income) also increases.

It is essential to comprehend these basic transactions and their impacts on the accounting equation for effective financial management. This enables businesses to track their financial position and performance accurately and make informed decisions based on that information.

Illustration of common business transactions in the transaction cycle



The diagram above provides a clear illustration of common transactions that occur in a business, involving various parties. These basic transactions impact the accounting equation, and their effects can be demonstrated as follows:

Transaction cycle:

1. The owner invests in the business:

    a) Owner invests cash: When the owner invests cash into the business, both the asset account (cash) and the capital account increase, resulting in an increase in both assets and capital.





b) Owner invests assets: The business receives an asset e.g. a motor vehicle from the owner and it increases the business assets. On the other hand it also increases the owners interest in the business (Capital).



2. Purchase of assets:

a) Purchase of assets and pay cash: The business receives an asset e.g. a motor vehicle, stock; etc. from another party (the supplier) and it increases the business assets. On the other hand it also decreases the assets (cash in the bank).



b) Purchase assets on credit: The business receives an asset e.g. a motor vehicle, etc. from another party (the supplier) and it increases the business assets. On the other hand it also increases the liabilities towards the supplier, which will then be referred to as the creditor.



3. Incur expenses:

a) Incur expenses and pay cash: The business receives the value of goods and services, which

the business will consume or use up in the normal business activities, e.g. placing of an advertisement, fuel for the motor vehicle, etc. and it increases the business nominal accounts, the expense accounts. On the other hand it also decreases the assets (cash in the bank).

b) Incur expenses on credit: The business receives the value of goods and services, which the business will consume or use up in the normal business activities, e.g. placing of an advertisement, fuel for the motor vehicle, etc. and it increases the business nominal accounts, the expense accounts. On the other hand it also increases the liabilities towards the supplier, which will then be referred to as the creditor.



4. Purchase of stock or goods for resale:

a) Purchase of stock or goods and pay cash: The business receives an asset (stock) from another party (the supplier) and it increases the business assets. On the other hand it also decreases the assets (cash in the bank).



b) Purchase of stock or goods on credit: The business receives an asset (stock) from another party (the supplier) and it increases the business assets. On the other hand it also increases

the liabilities towards the supplier, which will then be referred to as the creditor.



5. Sell services or goods:

a) Sell services for cash: The business receives an asset (cash) from another party (the customer) and it increases the business assets. On the other hand it also increases the nominal accounts (income).



b) Sell services on credit: The business receives an asset (debtor) from another party (the customer) and it increases the business assets. On the other hand it also increases the nominal accounts (income).



c) Sell trading stock for cash: The business gains an asset (cash) from another party (the customer) and it increases the business assets. On the other hand it also increases the nominal accounts (income). The business loses an asset (stock at cost price) and it decreases the business assets. On the other hand it also decreases the nominal accounts (cost of sales).





d) Sell stock on credit: The business gains an asset (debtor) from another party (the customer) and it increases the business assets. On the other hand it also increases the nominal accounts (income). The business loses an asset (stock at cost price) and it decreases the business assets. On the other hand it also decreases the nominal accounts (cost of sales).





6. Receive cash from debtors: The business gains an asset (cash) from another party (the customer) and it increases the business assets. On the other hand it also decreases the business assets (debtors).



7. Payment of creditors: The business decreases a liability (creditor) with the money paid to the other

party (the creditor) and it decreases the business assets (cash).

Understanding how these basic transactions affect the accounting equation is essential for proper financial management. It enables businesses to accurately track their financial position and performance, make informed decisions based on that information, and ensure that the accounting equation always remains balanced.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Accounting equation and Financial categories

What is the Accounting equation for the 5 financial categories?

The accounting equation is a fundamental principle in accounting that shows the relationship between a company's assets, liabilities, and capital.

The accounting equation is important because it provides a framework for recording and analysing financial transactions. It helps businesses to understand their financial position and make informed decisions about their operations. The equation is used to prepare financial statements such as the balance sheet, which summarises a company's assets, liabilities, and capital at a given point in time.

The accounting equation, also known as the Balance sheet equation, represents the fundamental relationship between the five financial categories in accounting. The equation is as follows:

Here's a breakdown of what each component represents:

- Assets: These are the economic resources owned or controlled by a business entity. Assets can include

cash, inventory, property, equipment, investments, and accounts receivable. They are classified into two main categories: current assets (short-term) and non-current assets (long-term).

- Liabilities: These are the obligations or debts owed by a business to external parties. Liabilities can include loans, accounts payable, accrued expenses, and long-term debt. Like assets, liabilities are also categorized into current liabilities (short-term) and non-current liabilities (long-term).
- Equity: Also known as owner's equity or shareholders' equity, equity represents the residual interest in the assets of a business after deducting liabilities. It reflects the ownership interest of the owners or shareholders in the business. Equity can be further divided into different components, such as contributed capital (e.g., investments by owners) and retained earnings (accumulated profits or losses retained in the business).

The accounting equation ensures that the resources (assets) owned by a business are financed either by liabilities (obligations to external parties) or by the owners' equity. It demonstrates the fundamental principle of double-entry bookkeeping, where every transaction must have an equal effect on both sides of the equation to maintain balance.

By keeping the accounting equation in balance, businesses can accurately track their financial position, analyse changes in their financial structure, and ensure proper record-keeping and reporting.

How does Income statement financial categories fit in the accounting equation?

The Income statement financial categories, namely Income and Expenses, are an integral part of the accounting equation indirectly.

The Income statement summarizes the revenues and expenses incurred by a business during a specific period. While the accounting equation primarily focuses on the Balance sheet, which represents the financial position of a business at a specific point in time, the Income statement reflects the financial performance of the business over a defined period.

The net income (or net loss) reported on the Income statement ultimately affects the Equity component of the accounting equation. Here's how it fits into the equation:

- Net Income: Net income is calculated by subtracting total expenses from total revenues. If the revenues exceed the expenses, it results in a net income, which increases the Equity component of the accounting equation. Net income represents the profit generated by the business and contributes to the owners' equity or retained earnings.
- Net Loss: Conversely, if the total expenses exceed the total revenues, it results in a net loss, which decreases the Equity component of the accounting equation. Net loss represents the loss incurred by

the business during the period and reduces the owners' equity or retained earnings.

Therefore, the Income statement provides valuable information about the revenues earned and expenses incurred by a business, which directly impacts the owners' equity component of the accounting equation. It showcases the profitability or performance of the business and how it influences the financial position reflected in the equation.

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Accounting equation - Balance sheet

In accounting, the balance sheet typically reflects three main types of accounts: proprietary accounts, asset accounts, and liability accounts. These accounts provide a snapshot of the business's worth on a specific date, by showing the value of assets held (such as motor vehicles, stock, equipment and machinery), monies owed, and the capital and loan accounts of the owners. The balance sheet is an important financial statement that provides a summary of a company's financial position, and helps stakeholders make informed decisions about investing, lending, and doing business with the company.

Financial category	*What do they tell us?*	*Examples of accounts*
Proprietary accounts	*Proprietary accounts are used to record all personal transactions between the business owner(s) and the business itself. This includes investments made by the owner(s) into the business, as well as any withdrawals taken out of the business by the owner(s).*	*Capital* *Drawings* *Retained income / earnings*
Asset accounts	*Asset accounts are used to record all of the assets owned by the business, which are used in the course of conducting business activities. This includes tangible assets such as property, plant, and equipment, as well as intangible assets such as patents, trademarks, and goodwill.*	*Land and Buildings* *Vehicles* *Furniture and fittings* *Machinery* *Debtors* *Bank*

		Petty cash Trading stock
Liability accounts	Liability accounts are used to record all of the liabilities of the business, which represent amounts owed by the business to third parties. This includes both short-term liabilities such as accounts payable and long-term liabilities such as loans or bonds payable.	Loans Bank overdrafts Creditors

The balance between the assets and liabilities of the business is an important determinant of the financial health and stability of the business.

CAPITAL = ASSETS – LIABILITIES

The balance sheet is a financial statement that presents a list of all the assets owned by the business and how these assets are financed. It provides a snapshot of the financial position of the business at a specific point in time.

The sources used to finance the assets of the business are listed on the balance sheet under the categories of owner's equity and liabilities. Owner's equity represents the capital invested by the owner in the business, while liabilities represent amounts owed by the business to third parties. Together, owner's equity and liabilities are referred to as the "*sources of financing*" or "*capital employed*".

The assets that the business owns are listed on the balance sheet as the "*employment of capital*". These assets are financed by the capital and liabilities of the business. The balance sheet provides a clear picture of the financial health of the business, by showing the relationship between its assets and the sources used to finance those assets.

Created with the Standard Edition of HelpNDoc: Free Web Help generator

Accounting equation - Income statement

The income statement is a financial statement that shows all the income and expense accounts of a business, which are also called nominal accounts. It is divided into two main financial categories: income accounts and expense accounts. It consists of two basic Financial categories:

Financial category	*What do they tell us?*	*Examples of accounts*
Income accounts	*Income accounts represent the sources of income for the business.*	*Sales* *Interest received*
Expense accounts	*On the other hand, expense accounts reflect the expenses incurred by the business in order to generate income.*	*Motor vehicle expenses* *Rent* *Telephone* *Salaries and wages* *Water and Lights*

The difference between the total of the income and the total of the expense accounts will reflect how much profit/loss the business made.

The profit is the return or remuneration the owner or owners of the business receives on their investment in the business. This difference (Profit / Loss) is transferred to the Balance sheet (Retained income / earnings account) as it will increase the owner / owners equity (capital interest) in the business.

PROFIT = INCOME – EXPENSES

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Expanded accounting equation - Balance sheet and Income statement

---

The expanded accounting equation takes into account the impact of all transactions on assets, liabilities, capital, income, and expenses. When sales are made, assets such as cash in the bank or accounts receivable increase, along with income. Conversely, expenses like advertising decrease assets, such as cash in the bank, or increase liabilities, like accounts payable. Income increases profit while expenses decrease profit.

Given that most transactions affect both the income statement and balance sheet, it's necessary to look at

the full accounting equation.

The expanded accounting equation is as follows:



This equation must always be in balance for the financial statements to be accurate.

Balance sheet

The balance sheet is one of the main financial statements that presents the company's financial position at a specific point in time. It shows the assets, liabilities, and equity of the company, and the balance sheet is based on the accounting equation.



Income statement

The income statement is another important financial statement that reports a company's financial performance over a period of time, typically one year. It summarizes the revenues, expenses, and net income of the company for that period.

The income statement is a crucial financial statement that reports a company's financial performance during a specified period, usually one year. It provides a summary of the company's revenues, expenses, and net income for that period.

The accounting equation plays a vital role in the income statement. The net income reported on the income statement is calculated by subtracting total expenses from total revenues. This net income is then added to the equity section of the balance sheet, affecting the retained earnings balance. Thus, the accounting equation, which states that assets = liabilities + equity, is also impacted by the income statement.



Balance sheet

The balance sheet and income statement are connected through the accounting equation. The net income reported on the income statement affects the equity section of the balance sheet by flowing into the retained earnings balance. Additionally, changes in assets and liabilities on the balance sheet are reflected in the income statement through revenues and expenses.

All transactions impact either assets, liabilities, capital, income, or expense items. Sales increase assets, such as bank or debtors, and income. On the other hand, expenses like advertisements decrease assets, such as cash in the bank, or increase liabilities, like creditors.

Income increases profit, while expenses decrease profit. Since most transactions affect both the income statement and the balance sheet, it's essential to consider the full accounting equation or expand the accounting equation.

Expanded accounting equation

The accounting equation will then be as follows:



Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Account groups - Financial categories

Each account included in the chart of accounts in osFinancials5/TurboCASH5 Sets of Books (templates) is linked to account groups, which in turn are linked to the five financial categories (INCOME, EXPENSES, CAPITAL, ASSETS, and LIABILITIES).

Each of these financial categories is further divided into groups that classify the financial transactions according to their nature. This provides the basic structure for the chart of accounts to generate various financial reports based on account number or account group 1 or account group 2.

The classification of financial categories and account groups for the income statement and balance sheet is briefly explained in the following topics:

- Account groups - Financial categories - Income statement
- Account groups - Financial categories - Balance sheet

Created with the Standard Edition of HelpNDoc: How to Protect Your PDFs with Encryption and Passwords

Account groups - Financial categories - Income statement

Each of the Income statement Financial categories, which are INCOME and EXPENSES, are further classified into reporting groups for accounts, which are described as follows:

FINANCIAL CATEGORY	*REPORTING GROUPS FOR ACCOUNTS*	*DESCRIPTION*	**DR / CR*
NET PROFIT	*RETAINED INCOME*	*Income received is greater than incurred expenses.*	*CREDIT*
/ NET LOSS		*Incurred expenses are greater than income received.*	*DEBIT*
INCOME	*INCOME*	*This category includes revenue generated from the sale of goods and services.*	*CREDIT*
	OTHER INCOME	*This category includes revenue from ventures and activities outside of the normal business activities.*	*CREDIT*
EXPENSES	*EXPENSES*	*This category includes expenses incurred in the normal business activities to generate income.*	*DEBIT*

RETAINED INCOME, at the beginning of the financial year, the income/expense accounts are zeroed and the resulting balance transferred to the retained income account.

Income / Expense accounts created (in osFinancials5/TurboCASH5) should be assigned to an appropriate reporting group and linked to a financial category in osFinancials5/TurboCASH5.

INCOME or EXPENSES

The Financial results influence the net worth of a business. A profit will increase the capital value of a business; the opposite is true for a loss.

*The DR/CR column in the table indicates whether the account has a debit or credit balance. The NET PROFIT or NET LOSS is calculated by subtracting the total expenses from the total income. At the

beginning of the financial year, the income/expense accounts are zeroed, and the resulting balance is transferred to the RETAINED INCOME account.

Accounts created in osFinancials5/TurboCASH5 should be assigned to an appropriate reporting group and linked to a financial category (INCOME or EXPENSES) in osFinancials5/TurboCASH5. The financial results influence the net worth of a business, with a profit increasing the capital value of a business and a loss decreasing it.

Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Account groups - Financial categories - Balance sheet

Each of the Balance sheet Financial categories CAPITAL, ASSETS and LIABILITIES, are further classified or grouped as follows:

FINANCIAL CATEGORY	*REPORTING GROUPS FOR ACCOUNTS*	*DESCRIPTION*	*DR / CR*
CAPITAL	*CAPITAL* *MEMBERS' CONTRIBUTION* *SHARE CAPITAL*	*The value of the owners' equity.* *Sole Proprietor or Partnership* *Close Corporation* *Companies*	*CREDIT*
ASSETS	*FIXED ASSETS* *CURRENT ASSETS*	*Physical items with a value,* *e.g. Land and Buildings, Plant and Machinery, Motor Vehicles, Furniture and Fittings, Computers, etc.* *Cash in the Bank, Petty cash, and Value of the Debtors ledger, stock holding and prepaid expenses.*	*DEBIT*
LIABILITIES	*LONG-TERM LIABILITIES*	*All amounts owed to third parties or financial obligations repayable normally*	*CREDIT*

		more than one year.	
	CURRENT LIABILITIES	*All amounts owed by the business to Creditors, Taxes payable, accounts payable and provisions for expenses.*	

Each Balance sheet account type created in osFinancials should be assigned to an appropriate REPORTING ACCOUNT GROUP and linked to a FINANCIAL CATEGORY in osFinancials5/TurboCASH5.

CAPITAL, ASSETS or LIABILITIES

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Charts of accounts in osFinancials/TurboCASH

---

osFinancials5/TurboCASH5 provides pre-set Sets of Books (templates) that can be used to create your own Set of Books. These templates are already available to download using the "*Let osFinancials help you to create a Set of Books?*" option / "*Let TurboCASH help you to create a Set of Books?*" option and all necessary settings are pre-configured to make it easier for you. The chart of accounts can be customised according to your business needs and all accounts must be linked to either a Balance sheet or Income statement category. It is recommended to print the Chart of Accounts and verify that all necessary accounts are present. Accounts and sub-accounts can be added, edited or deleted to fit specific requirements.

The "Customize your own Set of Books (Advanced)?" option on the "Creation wizard" screen (Create Set of Books on the Start ribbon), allows you to create a Set of Books with up to 8-digit main accounts.

When creating a Set of Books with the option to choose the number of digits for main accounts, you have the flexibility to select a structure that suits your needs. Here are the available options and the corresponding number of digits for the general ledger main accounts:

4-Digit General ledger main accounts: Enter a 4-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100, 1100, and 3100). This option includes 3-digit sub-accounts as well as 7-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger.

5-Digit General ledger main accounts: Enter a 5-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000, 11000, and 31000). This option includes 3-digit sub-accounts as well as 8-Digit account codes for Debtor accounts in the debtors ledger and

Creditor accounts in the creditors ledger

6-Digit General ledger main accounts: Enter a 6-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 210000, 110000, and 310000). This option includes 3-digit sub-accounts as well as 9-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

7-Digit General ledger main accounts: Enter a 7-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100000, 1100000, and 3100000). This option includes 3-digit sub-accounts as well as 10-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

8-Digit General ledger main accounts: Enter an 8-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000000, 11000000, and 31000000). This option includes 3-digit sub-accounts as well as 11-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

When designing and planning your Chart of Accounts, it's important to carefully consider and define the codes or numbers for these accounts based on the structure you have chosen. This will help ensure consistency and organization in your financial reporting and analysis.

The "*EN-SOUTHAFRICA*" Set of Books contains a chart of accounts that is divided into two parts: Income statement accounts and Balance sheet accounts for your convenience.

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Balance sheet accounts - Chart of accounts

Every transaction has an impact on the assets, liabilities, capital, income, or expense items of an entity. For instance, sales increase assets such as bank balance or debtors and income. On the other hand, expenses like advertising decrease assets (cash in the bank) or increase liabilities (creditors). Income increases the profit, whereas expenses decrease it. Since most transactions affect both the Income statement and the Balance sheet, it is necessary to consider the entire accounting equation or expand it.

The expanded accounting equation is as follows:

This equation shows that the assets of an entity are equal to the sum of its liabilities, capital, income, and expenses. The equation must always balance, which means that the total value of the assets must be equal to the sum of liabilities, capital, income, and expenses. This is a fundamental principle in accounting, and it

ensures that the financial statements are accurate and reliable.



Account	Description	Account Group1	Type
G505	SHARE CAPITAL	CAPITAL	
G510	RETAINED INCOME	CAPITAL	Retained income
G550	Long Term Loans	LONG TERM LIABILITIES	
G560	Installment Sale - Creditors	LONG TERM LIABILITIES	
G600	FURNITURE AND FITTINGS	FIXED ASSETS	
G600010	Furniture and Fittings at Cost	FIXED ASSETS	
G600020	Furniture/Fittings Accum. Deprec.	FIXED ASSETS	
G610	OFFICE EQUIPMENT	FIXED ASSETS	
G610010	Office Equipment at Cost	FIXED ASSETS	
G610020	Office Equipment Accum. Depreciation	FIXED ASSETS	
G620	MOTOR VEHICLES	FIXED ASSETS	
G620010	Motor Vehicles at Cost	FIXED ASSETS	

Account	Description	Account Group1	Type
G620020	Motor Vehicles Accum. Depreciation	FIXED ASSETS	
G700	DEBTORS CONTROL ACCOUNT	CURRENT ASSETS	Debtors control
G730	DEPOSITS PAID	CURRENT ASSETS	
G740	POS-Till Account	CURRENT ASSETS	
G745	POS-Cheque Payments Account	CURRENT ASSETS	
G750	STOCK CONTROL ACCOUNT	CURRENT ASSETS	
B810	CURRENT BANK ACCOUNT	CURRENT ASSETS	Bank account
B820	PETTY CASH	CURRENT ASSETS	Bank account
G900	CREDITORS CONTROL ACCOUNT	CURRENT LIABILITY	Creditors control
G920	SALARIES CONTROL	CURRENT LIABILITY	
G920001	Salaries	CURRENT LIABILITY	
G920005	UIF Payable	CURRENT LIABILITY	
G920010	PAYE Payable	CURRENT LIABILITY	
G920015	Skills Development Levy	CURRENT LIABILITY	
G950	VAT CONTROL ACCOUNT	CURRENT LIABILITY	
T950005	Output (Sales) VAT 14%	CURRENT LIABILITY	Tax account

Account	Description	Account Group1	Type
T950010	Input VAT (Exp) - 14%	CURRENT LIABILITY	Tax account
T950015	Zero Rated VAT - 0%	CURRENT LIABILITY	Tax account
G950100	VAT PAYMENT ACCOUNT	CURRENT LIABILITY	
G999	SUSPENSE ACCOUNT	CURRENT LIABILITY	

The chart of accounts may be customised to suit your specific needs. You may change descriptions, add new accounts and sub-accounts. osFinancials5/TurboCASH5 allows you to create up to 999 main accounts. For each of these main accounts you may also create up to 999 sub-accounts.

In a Set of Books consisting of a 4-Digit Main Accounts, you may create up to 9999 main accounts.

In a Set of books consisting of 5-digit main accounts, you may create up to 99999 main accounts.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Income / Expense accounts - Chart of accounts

The first section of the chart of accounts reflects the income and expense accounts, which are reported on the income statement.

NETT PROFIT / NET LOSS = INCOME – EXPENSE ACCOUNTS

Income statement Financial categories - (Income and Expenses):

Account	Description	Account Group1	Type
G010	Sales	INCOME	Inc / Exp
G050	Other Sales	INCOME	Inc / Exp

Account	Description	Account Group1	Type
G060	Bad Debts Recovered	OTHER INCOME	Inc / Exp
G065	Cash Discount Received	OTHER INCOME	Inc / Exp
G070	Interest Received	OTHER INCOME	Inc / Exp
G075	Profit/Loss- Sale of Fixed assets	OTHER INCOME	Inc / Exp
G080	Sundry Income	OTHER INCOME	Inc / Exp
G100	Cost of Sales	COST OF SALES	Inc / Exp
G180	Delivery Charges	EXPENSES	Inc / Exp
G200	Accountancy Fees	EXPENSES	Inc / Exp
G205	Advertising	EXPENSES	Inc / Exp
G210	Audit Fees	EXPENSES	Inc / Exp
G215	Bad Debts Written-off	EXPENSES	Inc / Exp
G220	Bank Charges	EXPENSES	Inc / Exp
G225	Cleaning	EXPENSES	Inc / Exp
G230	Commissions Paid	EXPENSES	Inc / Exp
G235	Consultancy Fees	EXPENSES	Inc / Exp

Account	Description	Account Group1	Type
G240	Depreciation	EXPENSES	Inc / Exp
G245	Entertainment	EXPENSES	Inc / Exp
G250	Finance Charges	EXPENSES	Inc / Exp
G255	Gifts and Donations	EXPENSES	Inc / Exp
G260	Insurances	EXPENSES	Inc / Exp
G262	Interest Paid	EXPENSES	Inc / Exp
G265	Legal Fees	EXPENSES	Inc / Exp
G270	Lights and Water	EXPENSES	Inc / Exp
G275	Medical Expenses	EXPENSES	Inc / Exp
G280	Motor Vehicle Expenses	EXPENSES	Inc / Exp
G280001	Fuel	EXPENSES	Inc / Exp
G280005	Motor Repairs	EXPENSES	Inc / Exp
G280010	Motor Costs - Other	EXPENSES	Inc / Exp
G285	Printing Postage and Stationery	EXPENSES	Inc / Exp
G290	Rent Paid	EXPENSES	Inc / Exp

Account	Description	Account Group1	Type
G295	Repairs and Maintenance	EXPENSES	Inc / Exp
G300	Salaries - Directors	EXPENSES	Inc / Exp
G305	Salaries - Staff	EXPENSES	Inc / Exp
G310	Salaries/Wages- Employers Contrib.	EXPENSES	Inc / Exp
G315	Subscriptions	EXPENSES	Inc / Exp
G320	Telephone and Fax	EXPENSES	Inc / Exp
G330	Travelling Expenses	EXPENSES	Inc / Exp

Created with the Standard Edition of HelpNDoc: Make your documentation accessible on any device with HelpNDoc

General ledger structure

The Ledger consists of the General ledger (Chart of accounts), the Debtor's ledger; the Creditor's ledger and the Stock ledger. The ledger can be illustrated as follows:



1. General ledger - consists of the Income and Expense accounts and Capital, Assets and Liabilities (Balance sheet) accounts. It also includes a control account for the debtors, creditors and stock items.
2. Debtor's ledger - consists of the individual debtor accounts. Each individual debtor's account contains the contact information, messages and accounting information. The total outstanding balance of all the debtor accounts in the debtor's ledger is automatically updated and reported in the Debtor's control in the General ledger.
3. Creditor's ledger - consists of the individual creditor accounts. Each individual creditor's account contains the contact information, messages and accounting information. The total outstanding balance of all the creditor accounts in the creditor's ledger is automatically updated and reported in the Creditor's control account in the General ledger.
4. Stock ledger - consists of the individual stock item records. Each individual stock item records contain specific information, such as quantities, cost prices, selling prices, units, re-order levels, etc. The total outstanding cost price value of all the stock item records in the stock ledger is automatically updated and reported in the Stock control account in the General ledger. It also includes a control account for the debtors, creditors and stock items.

The outstanding balances of the individual accounts and records in the Debtor's ledger, the Creditor's ledger and the Stock ledger is automatically updated and reported in the respective Control accounts in the General ledger.



Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Control accounts

Control accounts are used to keep track of the total amounts owed by debtors and owed to creditors, as well as the total value of stock items. Instead of creating individual ledger accounts for each debtor, creditor, and stock item, a single control account is created in the general ledger. The control account shows the total amounts owed by all debtors or owed to all creditors, and the total value of all stock items.

To keep track of individual debtor accounts, creditor accounts, and stock items, separate subsidiary ledgers are created for each. The subsidiary ledgers contain individual ledger accounts for each debtor, creditor, and stock item. The subsidiary ledgers are managed by the debtors clerk or the purchases department, who maintain the individual ledger accounts for each debtor, creditor, and stock item.

At the end of a period, the balances in the individual ledger accounts are totalled, and the total is compared to the balance in the corresponding control account in the general ledger. If the balances match, it means that all individual ledger accounts have been properly recorded and reconciled. The same principles apply to the purchases department.

Using control accounts and subsidiary ledgers allows for more efficient management of accounting records, especially in large business enterprises with many debtors, creditors, and stock items. It also enables effective credit control and debt collection.

Using control accounts and subsidiary ledgers allows for a more organised and efficient system of managing and storing information about debtors, creditors, and stock items. It also enables businesses to delegate the management of subsidiary ledgers to specific clerks or departments, allowing for greater control and oversight. The subsidiary ledgers and the general ledger can be illustrated as follows:



General ledger - The general ledger is a comprehensive record that includes your chart of accounts, income and expenses, capital, assets, and liabilities. The chart of accounts comprises control accounts for debtor accounts, creditor accounts, and stock items (inventory items) in the form of stock ledgers. The individual subsidiary ledgers, such as the debtor's ledger, creditor's ledger, and stock ledger, contain specific details.

1. Debtor's control account

The debtor's control account is a record in the general ledger that shows the total amount of money owed by all the individual debtors. The balance of the debtor's control account must match the total amount of money owed by each individual debtor, which is obtained from the various subsidiary ledger accounts for each debtor. The subsidiary ledger that tracks the individual balances for each debtor is known as the debtors' ledger.

In the debtors' ledger, you can store transaction details and additional information about each debtor, such as their personal and contact information, credit limit, payment terms, and more. The debtor's

ledger also serves as a register of all the transactions between you and a specific debtor, allowing you to track each purchase and payment made by that debtor.

2. Creditor's control account

The creditor's control account is an account in the general ledger that reflects the total amount owed to all individual creditors. Its balance must equal the total of the creditors' list, which represents the amounts owed by the individual creditors obtained from the individual balances in the various subsidiary ledger accounts for each creditor.

In the creditors' ledger, you can store transaction details and additional information regarding each creditor, such as their personal and contact information, credit limit, terms, etc. The creditors' ledger is also a register of each and every transaction that you and a specific creditor entered into.

3. Stock control account

The stock control account keeps track of the overall value or amount of all the stock items a business has. It's important that the balance of each individual stock item ledger account matches the total value of the stock item list, which is made up of the amounts or values of all the individual stock items obtained from the various subsidiary ledger accounts for each item. This subsidiary ledger is called the stock ledger.

The stock ledger contains transaction details and additional information for each stock item, such as its cost price, selling price, quantity, and location on the shelves. This ledger serves as a record of every stock transaction, including purchases and sales.

Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Structure of osFinancials

---

osFinancials5/TurboCASH5 is a software that is straightforward to set up and use. You only need to create a Set of Books once, add your master records, set some defaults, and begin processing your transactions. Whenever you need to manage your financial activities, you can generate, print, or export various reports.

The user interface of osFinancials5/TurboCASH5 is designed to be user-friendly and intuitive, making it easy for users to perform most functions with just a few clicks and minimal typing. In certain fields, search facilities are available to help you select transaction details or report selection criteria quickly.

The financial data in osFinancials5/TurboCASH5 is processed, stored, and reported on using a specific structure in the osFinancials5/TurboCASH5 file system:

1. Sets of Books

   The osFinancials file system consists of various components that are used to manage and monitor financial activities for different entities. You can create an unlimited number of Sets of Books, which are sets of computerized files used to enter, process, summarize, and report financial data for a business entity or organization. Each Set of Books is stored in a separate directory or folder on your system, and the list of these Sets of Books is kept in the "*books.fdb*" file.

2. Company info, defaults and settings

   For each Set of Books, the entity's information and defaults or settings are stored. This information is reflected on reports, and the defaults or settings are used to enter, process, and report on the data.

3. Accounting periods

   The accounting periods are used to report on financial activities for a specific period. The financial year is divided into accounting periods, usually representing the calendar months. All transactions of an entity must be recorded in the accounting period in which they occurred. The accounting periods are used to generate reports on the transaction data, and osFinancials5/TurboCASH5 stores the totals and other financial information for any number of years to allow for comparison between reports for this year and last year.

   The "*totals*" table in osFinancials5/TurboCASH5 stores the total amounts for each accounting period of the current year and the previous year. This table is used to cross-reference and ensure that the Set of Books is balanced. For each account, the total of the debits (positive numbers) and credits (negative numbers) for any given period must be equal to zero, as every transaction should have an equal amount debited and credited.

4. Accounts

   The Chart of Accounts is the core component of a Set of Books. This data is kept in the "*accounts*" table, and there are five types of Accounts files specific to each type:

   a) General ledger accounts - Assets, Capital, Liabilities, Income or Expense accounts.

   b) Bank accounts - Cashbook payments and receipts journals.

   c) Creditor accounts - Creditor contact information, remittance advice messages, credit limits, charge amounts, tax references, groups, etc.

   d) Debtor accounts - Debtor contact information, statement messages, credit limits,

charge amounts, interest percentage, tax references, groups, etc.

e) Tax accounts - Percentages for VAT/GST/Sales Tax and effective dates for which these percentages apply.

5. Stock items

   osFinancials5/TurboCASH5 stores specific data of your stock items (inventory items / products) in the "*stock*" table, including codes, descriptions, selling prices, and barcodes, tax accounts, sales, cost of sales, and stock account information.

6. Transactions

   All transactions are entered in batches and documents, such as, invoices, credit notes, purchases and supplier returns), and these batches are posted to the ledger. The information of each transaction is kept in the "*transact*" table, including the batch type, date and period of the transaction, reference number, description, amount, tax amounts, account, and contra account.

7. Documents

   The details of documents such as invoices, credit notes, quotes, purchases, supplier returns, and orders are stored in various tables. These tables contain information about the inventory items and quantities as selected on the documents. When documents are updated or posted to the general ledger, osFinancials5/TurboCASH5 will generate transactions and update the appropriate accounts with these transactions. This saves you the effort of unravelling the complex relationships between transactions.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Research and Development (R&D)

Research & Development (R&D) Section: Exploring Accounting Complexities and Customizing osFinancials

The Research & Development section of the osFinancials5/TurboCASH5 documentation has two primary objectives: to navigate the intricate landscape of accounting complexities and to offer guidance on effectively integrating and customizing a chart of accounts for specific countries, regions, and jurisdictions. This section is intended to be a valuable resource for individuals who are new to accounting, students, and

professionals seeking to optimize their osFinancials5/TurboCASH5 experience.

1. Exploring Accounting Complexities: In this section, we delve into the multifaceted aspects of accounting, including accounting frameworks, standards, taxation regulations, ownership types, and financial reporting practices across the globe. The objective is to provide a comprehensive understanding of the challenges and opportunities posed by these complexities, and how they impact financial reporting and analysis. Key topics covered include:
    - Comparative analysis of accounting frameworks and standards (GAAP, IFRS, local standards) in different regions.
    - Examination of tax implications for various ownership types and financial transactions.
    - Insights into global variations in financial reporting practices and their influence on financial analysis and decision-making.
2. Customizing osFinancials5/TurboCASH5 for Specific Jurisdictions: In this section, we focus on leveraging the capabilities of osFinancials to tailor the chart of accounts to the unique requirements of different countries, regions, and jurisdictions. The goal is to provide practical guidance on designing a chart of accounts that aligns with local regulations, business needs, and reporting standards. Key topics covered include:
    - Understanding the significance of a chart of accounts and its role in financial reporting.
    - Strategies for structuring accounts to accommodate diverse needs and regulatory requirements.
    - Exploring options to integrate taxation considerations, industry-specific practices, and ownership type nuances into the chart of accounts.

Compliance and Professional Advice: While this section aims to provide valuable insights and recommendations, it's crucial to emphasize the importance of compliance with local laws and regulations. Readers are encouraged to consult official tax websites, seek guidance from legal professionals, and collaborate with local accounting experts to ensure adherence to applicable standards and requirements. Ownership type considerations, tax implications, and accounting practices can vary significantly, and professional advice is essential to ensure accurate and compliant financial reporting.

By addressing these objectives, the Research & Development section of the osFinancials5/TurboCASH5 documentation aims to empower users with a deeper understanding of accounting complexities and the tools to customize osFinancials for optimal financial management while adhering to legal and regulatory standards.

Research and Development (R&D) - Key components

The Research and Development (R&D) section of the osFinancials5/TurboCASH5 plays a crucial role in exploring and developing strategies to address the intricate complexities that arise from variations in accounting frameworks, accounting standards, chart of accounts design, account structure concepts, taxation regulations, and ownership types across different global regions. This section aims to provide a comprehensive understanding of these factors and how they impact financial reporting and analysis. Let's break down the key components and objectives of this R&D section:

1. Accounting Frameworks and Standards Research: This involves studying and analysing the various accounting frameworks and standards used in different countries and regions. Different countries may adopt different accounting principles (e.g., Generally Accepted Accounting Principles [GAAP], International Financial Reporting Standards [IFRS], local standards), which can lead to variations in financial reporting practices. The R&D section should explore the similarities, differences, and implications of these frameworks for financial reporting.
2. Branches in Accounting: Detail the various specialized branches of accounting, such as management accounting, cost accounting, and forensic accounting. Explain how each branch serves a specific purpose in providing meaningful insights for decision-making and compliance.
3. Chart of Accounts Design: A chart of accounts is a critical element of financial reporting that defines the structure of accounts used to record financial transactions. The R&D section should research and propose options for designing a chart of accounts that accommodates the diverse needs and reporting requirements of different regions while ensuring consistency and comparability.
4. Account Structure Concepts: Understanding how accounts are structured and classified is essential for accurate financial reporting. This section should delve into the different approaches to structuring accounts, such as by asset type, liability type, equity, revenue, and expense. It should also explore how these concepts vary across regions and their impact on financial analysis.
5. Ownership Types Analysis: Different ownership structures (e.g., sole proprietorship, partnership, corporation) have distinct financial reporting requirements and implications. This part of the R&D section should investigate the advantages, disadvantages, and accounting considerations associated with each ownership type, while highlighting how they differ across global jurisdictions.
6. Trade and Investment Incentives and Regulations: Discuss the impact of trade agreements, investment incentives, and regulations on financial reporting and decision-making. Explain how these factors can influence a company's international operations and financial strategies.
7. Taxation Considerations: Taxation rules and regulations vary significantly across countries, impacting how financial transactions are recorded and reported. This section should examine the tax implications of different ownership types, business structures, and financial transactions, offering insights into how

they affect financial statements and tax liabilities.

8. Tax VAT,GST/Sales Tax: Delve into the intricacies of Value Added Tax (VAT), Goods and Services Tax (GST), and Sales Tax in different regions. Discuss the concepts, calculations, and implications of these types of taxation on financial reporting and business operations.
9. Global Variations in Financial Reporting: This section should provide a comparative analysis of how accounting practices, financial reporting standards, and ownership types vary across different parts of the world. It should highlight the challenges and opportunities posed by these variations and suggest strategies to address them in a comprehensive and harmonized manner.
10. Impact on Financial Analysis and Decision-Making: The R&D section should conclude by discussing how these complexities influence financial analysis and decision-making. It should emphasize the need for accurate, consistent, and transparent financial reporting practices to enable meaningful comparisons and informed business decisions in a global context.
11. Financial Analysis and Valuation: Explore the methodologies and techniques used in financial analysis and valuation, including ratio analysis, discounted cash flow (DCF) analysis, and market comparable analysis. Discuss how these tools are employed to assess a company's financial performance, health, and intrinsic value.
12. Stock / Inventory: Explain the significance of managing and accounting for stock and inventory. Cover topics like inventory valuation methods (FIFO, LIFO, weighted average), inventory turnover ratios, and how different industries handle inventory management.

Overall, the Research and Development section of the Financials documentation should provide valuable insights and recommendations for navigating the intricate landscape of accounting frameworks, standards, chart of accounts design, account structure concepts, taxation, and ownership types across diverse regions. This will help organizations develop effective strategies for maintaining accurate financial records, complying with regulations, and making informed financial decisions on a global scale.

Leveraging the capabilities of the ChatGPT in Research

Leveraging the capabilities of the ChatGPT - AI 3.5 platform can be extremely beneficial for understanding basic complexities in various accounting concepts and applications worldwide. Here's how you can use this platform to aid newcomers to accounting, students, and anyone looking to optimize their financial understanding:

1. Concept Explanation: Use prompts to ask for explanations of fundamental accounting concepts such as assets, liabilities, equity, revenue, and expenses. You can ask for plain language explanations or delve into more technical details as needed.
2. Accounting Standards Comparison: Ask for a comparison between different accounting standards like

GAAP and IFRS. Explore the key differences in how they treat various financial transactions and reporting elements.

3. Chart of Accounts Design: Seek guidance on designing an effective chart of accounts that suits your organization's needs. Ask for pointers on how to structure accounts for different types of transactions.
4. Tax Implications: Inquire about how different ownership types (sole proprietorship, partnership, corporation) impact taxation. Get insights into deductible expenses, tax credits, and how to navigate tax regulations.
5. International Operations: If your business operates globally, you can ask about how to handle currency conversion, translation of financial statements, and accounting for transactions in different countries.
6. Financial Analysis: Request explanations on how financial ratios (e.g., liquidity, profitability, solvency) are calculated and what they indicate about a company's financial health.
7. Costing Methods: Understand different costing methods such as FIFO, LIFO, and weighted average, and their implications on inventory valuation and cost of goods sold.
8. Financial Statement Interpretation: Seek guidance on how to interpret income statements, balance sheets, and cash flow statements to make informed business decisions.
9. Consolidation: If dealing with group or subsidiary companies, ask how to consolidate financial statements to present a comprehensive view of the entire organization's financial position.
10. Ethical Considerations: Explore prompts about ethical considerations in accounting, such as the importance of transparency, avoiding conflicts of interest, and adhering to professional codes of conduct.
11. Accounting Software: Inquire about the use of accounting software, its benefits, and how to choose the right software for your organization's needs.
12. Industry-Specific Accounting: If you're in a specialized industry (e.g., healthcare, manufacturing, technology), ask for insights into industry-specific accounting practices and regulations.

Remember that while ChatGPT can provide valuable explanations and guidance, it's also a good practice to consult official accounting textbooks, resources, and professionals to deepen your understanding and ensure accuracy. Additionally, continuously optimizing your financial knowledge involves staying up-to-date with evolving accounting standards and industry practices.

ChatGPT - AI 3.5 platform - Upgrading to ChatGPT4

The research is based on ChatGPT's last knowledge update in September 2021.

If there have been developments since then, I recommend checking OpenAI's official website or reliable news sources for the latest information on their AI models and platforms. They typically provide announcements about new releases and upgrades.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Common errors made in accounting

There are several common errors that can occur in accounting, including:

1. Data entry errors: These errors occur when transactions are entered incorrectly, such as transposing numbers or recording the wrong amount.
2. Timing errors: These errors occur when transactions are recorded in the wrong period, such as recording a transaction in the wrong month or year.
3. Omission errors: These errors occur when a transaction is not recorded at all, such as forgetting to record a sale or purchase.
4. Reversal errors: These errors occur when debits and credits are reversed, such as debiting an account that should be credited.
5. Overstatement or understatement errors: These errors occur when transactions are recorded with the wrong amount, such as overstating revenue or understating expenses.
6. Duplication errors: These errors occur when a transaction is recorded twice, resulting in an overstatement of assets or income.
7. Incorrect account errors: These errors occur when a transaction is recorded in the wrong account, resulting in misstatements in financial statements.

It is important for businesses to have internal controls in place to prevent these common errors from occurring. Regular review and reconciliation of accounts can help identify and correct any errors that do occur. It is also important to have well-trained accounting staff and to use reliable accounting software, such as osFinancials5/TurboCASH5 to minimize the risk of errors.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

osFinancials and Small businesses, Medium sized businesses and Large businesses

---

Accounting software such as osFinancials5/TurboCASH5 how can it be useful to Small businesses, Medium sized businesses and Large businesses?

Accounting software like osFinancials5/TurboCASH5 can be highly beneficial to small, medium-sized, and large businesses by providing a range of features and functionalities that improve financial management, efficiency, and decision-making. Here's how it can be useful to each business size:

1. Small Businesses:
    - User-Friendly Interface: Accounting software designed for small businesses often has a user-friendly interface, making it easy for non-accounting professionals to navigate and use the software effectively.
    - Cost-Effective: Accounting software eliminates the need for manual bookkeeping and reduces the cost of hiring a dedicated accountant or outsourcing accounting tasks.
    - Invoicing and Billing: Small businesses can create professional invoices, track payments, and manage billing efficiently, helping improve cash flow.
    - Expense Tracking: The software allows businesses to record and categorize expenses, providing a clear overview of where money is spent.
    - Tax Compliance: Accounting software can calculate taxes, generate tax reports, and help small businesses meet their tax obligations.
2. Medium-Sized Businesses:
    - Scalability: Accounting software can scale with the growth of a medium-sized business, accommodating a higher volume of transactions and expanding functionalities as needed.
    - Integration: Many accounting software solutions can integrate with other business tools such as CRM systems, inventory management software, and payroll systems, streamlining operations and data flow.
    - Financial Reporting: Medium-sized businesses benefit from comprehensive financial reporting capabilities, providing insights into performance, profitability, and cash flow.
    - Budgeting and Forecasting: Accounting software allows for budget creation and financial forecasting, aiding in planning and decision-making.
    - Inventory Management: Some accounting software includes inventory management features to help medium-sized businesses track stock levels and manage their inventory efficiently.

3. Large Businesses:
    - Enterprise-Level Capabilities: Accounting software for large businesses often offers robust enterprise-level features, handling complex accounting needs, multiple currencies, and international operations.
    - Multi-Entity Support: Accounting software can handle multiple entities or subsidiaries, consolidating financial data for large conglomerates.
    - Customization: Large businesses may have unique accounting requirements, and the software's customization options can accommodate specific needs and workflows.
    - Audit Trail and Security: Advanced accounting software provides strong audit trail features and heightened security measures to protect sensitive financial data.
    - Integration with ERP Systems: Large businesses often integrate accounting software with enterprise resource planning (ERP) systems for seamless data flow across various departments.

In summary, accounting software like osFinancials5/TurboCASH5 is a versatile tool that can be tailored to meet the specific needs of small, medium-sized, and large businesses. It automates accounting processes, improves data accuracy, enhances financial reporting, and facilitates decision-making, regardless of the size and complexity of the organization.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Financial Analysis and Valuation

What is Financial Analysis and Valuation?

Financial Analysis and Valuation is a process used by investors, analysts, and businesses to assess the financial health and value of a company. It involves the examination and interpretation of a company's financial statements, performance metrics, and other relevant data to gain insights into its financial position, profitability, efficiency, and overall viability. The primary objective of financial analysis and valuation is to determine the intrinsic value of a company's securities, such as its stocks or bonds, and make informed investment decisions.

Key components of Financial Analysis and Valuation include:

1. Financial Statements Analysis: Reviewing and analyzing a company's financial statements, including the income statement, balance sheet, and cash flow statement. This involves assessing revenue,

expenses, assets, liabilities, and equity to understand the company's financial performance and position over time.

2. Ratio Analysis: Calculating and interpreting various financial ratios, such as liquidity ratios, profitability ratios, solvency ratios, and efficiency ratios. Ratios provide valuable insights into a company's financial performance and help compare it to industry benchmarks and peers.
3. Time Value of Money (TVM): Understanding the impact of the timing of cash flows on the value of money over time is crucial in investment analysis and financial decision-making.
4. Valuation Models: Using various valuation models to determine the intrinsic value of a company's securities, such as discounted cash flow (DCF) analysis, price-to-earnings (P/E) ratios, price-to-book (P/B) ratios, and others. These models help estimate the fair value of a company's stocks and bonds.
5. Industry and Market Analysis: Considering the company's position within its industry, market trends, competitive landscape, and macroeconomic factors that can impact its financial performance.
6. Risk Assessment: Evaluating the potential risks associated with investing in the company, including financial risks, market risks, operational risks, and regulatory risks.

Financial Analysis and Valuation play a crucial role in investment decision-making, merger and acquisition transactions, financial planning, and corporate strategy. It helps investors and stakeholders make well-informed choices about allocating resources, identifying investment opportunities, and understanding the overall financial health of a company. Additionally, financial analysis and valuation are essential for companies to understand their strengths and weaknesses and make data-driven decisions to improve their financial performance and long-term sustainability.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Financial Ratios

What is Financial Ratios?

Financial ratios are quantitative measures used to analyze and assess a company's financial performance, health, and position. They provide valuable insights into various aspects of a company's operations, profitability, liquidity, solvency, and efficiency. Financial ratios are calculated by dividing one financial metric by another and are expressed as a percentage, a proportion, or a rate.

Financial ratios are essential tools for investors, creditors, management, and other stakeholders as they help in making informed decisions and understanding the overall financial health and performance of a

company. Some common categories of financial ratios include:

1. Liquidity Ratios: Measure a company's ability to meet short-term obligations and assess its liquidity position.
    - Current Ratio: Measures a company's ability to pay its short-term obligations using its current assets. A ratio above 1 indicates the company has more current assets than current liabilities, which is generally seen as a sign of good liquidity.

      Current Assets / Current Liabilities

    - Quick Ratio (Acid-Test Ratio): Similar to the current ratio but excludes inventory from current assets. It provides a more stringent assessment of a company's ability to meet short-term obligations without relying on inventory sales.

      (Current Assets - Inventory) / Current Liabilities

2. Solvency Ratios: Evaluate a company's long-term financial stability and ability to meet long-term debt obligations.
    - Debt-to-Equity Ratio: Measures the proportion of a company's financing that comes from debt compared to equity. A higher ratio indicates higher financial leverage and higher risk.

      Total Debt / Total Equity

    - Debt-to-Assets Ratio: Measures the percentage of a company's assets that are financed by debt. It indicates the level of debt exposure relative to total assets.

      Total Debt / Total Assets

3. Profitability Ratios: Measure a company's ability to generate profits in relation to sales, assets, and equity.
    - Gross Profit Margin: Calculates the percentage of sales revenue that exceeds the cost of goods sold. It reflects the company's ability to produce goods or services efficiently.

      (Gross Profit / Total Revenue) x 100

    - Net Profit Margin: Measures the percentage of each dollar of revenue that represents profit after all expenses, including taxes. It shows how much profit the company earns from its total revenue.

      (Net Income / Total Revenue) x 100

4. Efficiency Ratios: Assess how effectively a company utilizes its assets to generate sales and manage its operations.

- Inventory Turnover: Measures how many times a company sells and replaces its inventory in a given period. A higher turnover ratio indicates efficient inventory management.

  Cost of Goods Sold / Average Inventory

- Accounts Receivable Turnover: Measures how quickly a company collects its accounts receivable from customers. A higher turnover ratio indicates more efficient cash collection.

  Net Credit Sales / Average Accounts Receivable

5. Market Ratios: Provide insights into a company's market value and investors' perceptions.

   - Price-to-Earnings (P/E) Ratio: Compares a company's market value to its book value (net asset value). It indicates whether the stock is overvalued or undervalued based on the company's net worth.

     Market Price per Share / Earnings per Share

   - Price-to-Book (P/B) Ratio: Compares a company's market value to its book value (net asset value). It indicates whether the stock is overvalued or undervalued based on the company's net worth.

     Market Price per Share / Book Value per Share

Financial ratios should be interpreted in the context of the industry, company size, and business model. They are most useful when compared over time (trend analysis) and against industry benchmarks or competitors (benchmarking). Regular analysis of financial ratios helps identify trends, strengths, weaknesses, and potential areas for improvement in a company's financial performance.

These financial ratios are essential tools for assessing a company's financial performance, health, and efficiency. They provide valuable insights to investors, creditors, and management to make informed decisions and evaluate the company's financial standing in comparison to industry benchmarks or competitors.

To optimise the use of financial ratios, it is essential to plan and link your chart of accounts to the correct account classifications and map them to the correct financial categories

Absolutely, optimizing the use of financial ratios requires careful planning and proper organization of a company's chart of accounts. The chart of accounts is a structured list of all the accounts used to record financial transactions in a company's accounting system. By linking the chart of accounts to the correct account classifications and mapping them to the appropriate financial categories, businesses can ensure

accurate financial reporting and effective financial analysis. Here's why it is essential:

1. Consistency in Financial Reporting: By using a well-structured chart of accounts with clear account classifications, financial data can be consistently recorded and reported. This consistency is crucial for making meaningful comparisons over time and across different companies or divisions within an organization.
2. Accurate Financial Analysis: Financial ratios rely on accurate and reliable financial data. Linking accounts to the correct classifications helps ensure that the relevant data is included in the calculations, leading to more accurate financial analysis and performance evaluation.
3. Relevant Financial Categories: Mapping accounts to the correct financial categories is vital for meaningful ratio analysis. For example, when calculating liquidity ratios, it is crucial to include all relevant current assets and current liabilities in the calculations.
4. Ease of Financial Analysis: A well-organized chart of accounts simplifies the process of extracting the required data for ratio analysis. It enables financial analysts to access and analyze the relevant financial information efficiently.
5. Better Decision Making: Properly categorized and mapped financial data allows management to make informed decisions based on accurate financial analysis. It helps identify areas of strength and weakness, enabling the organization to take appropriate actions.
6. Compliance and Auditing: A well-structured chart of accounts aids in meeting regulatory requirements and facilitates auditing processes. Properly classified accounts make it easier to verify financial data and ensure compliance with accounting standards and tax regulations.

To optimize the use of financial ratios, businesses should periodically review and update their chart of accounts to reflect changes in the business's operations and reporting needs. Additionally, ensuring that the accounting team is well-trained on the chart of accounts and its proper usage is essential to maintain data accuracy and consistency.

By implementing these practices, businesses can enhance the effectiveness of financial analysis, make better-informed decisions, and have a solid foundation for financial reporting and planning.

Before analyzing financial ratios, it is important to do the necessary accrual adjustments, depreciation, bad debts, etc.

Absolutely, before analyzing financial ratios, it is essential to make necessary adjustments to the financial statements to ensure that the data accurately reflects the company's financial position and performance. Some of the common adjustments include:

1. Accrual Adjustments: Accrual accounting requires recognizing revenues and expenses when they are

earned or incurred, regardless of when the cash is received or paid. Therefore, adjusting entries are needed to account for accrued revenues (revenues earned but not yet received) and accrued expenses (expenses incurred but not yet paid).

2. Prepaid Expenses and Deferred Revenues: Adjustments may be necessary to recognize prepaid expenses as expenses and deferred revenues as revenues.
3. Depreciation: Depreciation is the systematic allocation of the cost of tangible assets (such as buildings and equipment) over their useful lives. It is a non-cash expense that reduces the book value of assets over time. Adjusting for depreciation ensures that the financial ratios reflect the economic impact of asset usage.
4. Amortization: Similar to depreciation, amortization is the process of allocating the cost of intangible assets (such as patents and copyrights) over their useful lives.
5. Bad Debts: Bad debts arise when customers are unable to pay their credit obligations. Adjusting for bad debts ensures that accounts receivable on the balance sheet are reported at their estimated net realizable value.
6. Inventory Valuation: Inventory may need to be adjusted for obsolescence, spoilage, or lower of cost or market (LCM) considerations.
7. Non-Recurring Items: Extraordinary gains or losses and non-recurring items should be considered for adjustments to provide a clearer picture of the company's ongoing financial performance.
8. Non-Cash Items: Some items, such as stock-based compensation, may not involve cash outflows and may need to be adjusted for proper analysis.

By making these adjustments, financial analysts ensure that the financial ratios are based on consistent and comparable data, providing a more accurate representation of the company's financial health and performance. Moreover, these adjustments help in understanding the underlying economics of the business and provide insights into its ongoing operations.

Are these ratios for small businesses and larger businesses?

The financial ratios mentioned in the previous response can be used for both small businesses and larger businesses. Financial ratios are valuable tools for assessing the financial health and performance of companies of all sizes. However, the significance and interpretation of these ratios may vary based on the specific characteristics of the business and the industry it operates in.

For small businesses, financial ratios can be particularly helpful in providing insights into their liquidity, profitability, and overall financial stability. Small businesses often have limited resources and may face different challenges compared to larger businesses. Therefore, analyzing financial ratios can assist small

business owners in making informed decisions, identifying areas for improvement, and understanding their financial position relative to their goals and competitors.

On the other hand, larger businesses may use financial ratios to assess their operational efficiency, leverage, and market position. Larger companies usually have more complex financial structures, diverse revenue streams, and greater access to capital markets. Financial ratios play a crucial role in helping management, investors, and stakeholders gauge the performance and efficiency of larger businesses.

While the fundamental financial ratios apply to businesses of all sizes, it is essential to consider the scale and scope of operations when interpreting the results. Additionally, industry-specific benchmarks and comparisons with similar-sized companies in the same sector are valuable for obtaining meaningful insights from the ratios.

Ultimately, financial ratios are versatile tools that can be applied across different business sizes and industries to gain a deeper understanding of a company's financial performance and make well-informed decisions.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Liquidity Ratios

Liquidity ratios are financial metrics used to assess a company's ability to meet its short-term obligations and convert assets into cash to fund its immediate needs. These ratios provide insight into the company's short-term liquidity position and its capacity to handle financial challenges or unexpected expenses. Three common liquidity ratios are:

1. Current Ratio (Working Capital Ratio): The Current Ratio (or Working Capital Ratio) measures the company's ability to pay off its current liabilities using its current assets. The formula is:

   Current Ratio = Current Assets / Current Liabilities

   A current ratio above 1 indicates that the company has more current assets than current liabilities and is generally considered financially healthy.

2. Quick Ratio (Acid-Test Ratio): The Quick Ratio is a more stringent liquidity ratio that excludes inventory from current assets. It focuses on the company's ability to pay off its current liabilities using its most liquid assets. The formula is:

   Quick Ratio = (Current Assets - Inventory) / Current Liabilities

   A quick ratio of 1 or higher is generally considered financially healthy.

3. Cash Ratio: The Cash Ratio is the most conservative liquidity ratio, as it only considers the company's cash and cash equivalents to pay off current liabilities. The formula is:

Cash Ratio = Cash and Cash Equivalents / Current Liabilities

A cash ratio of 1 or close to 1 indicates that the company can cover its short-term obligations using only its cash reserves.

Liquidity ratios are essential for creditors, investors, and other stakeholders to assess the company's short-term financial health and its ability to weather financial downturns or unexpected events. It's crucial to interpret these ratios in the context of the company's industry, business model, and specific financial circumstances. Different industries may have varying liquidity requirements, and a single ratio may not provide a complete picture of the company's overall financial condition. Therefore, it's essential to analyze liquidity ratios alongside other financial ratios and indicators for a comprehensive evaluation of the company's financial health.

Created with the Standard Edition of HelpNDoc: Effortlessly Create Encrypted, Password-Protected PDFs

Current Ratio / Working Capital Ratio

The Working Capital Ratio, also known as the current ratio, is a financial metric used to assess a company's short-term liquidity and its ability to meet its current obligations. It measures the company's ability to pay off its current liabilities using its current assets. The formula for calculating the Working Capital Ratio is as follows:

Working Capital Ratio = Current Assets / Current Liabilities

Where:

- Current Assets refer to assets that are expected to be converted into cash or used up within one year from the reporting date. Examples include cash, accounts receivable, inventory, and short-term investments.
- Current Liabilities refer to obligations that are due within one year from the reporting date. Examples include accounts payable, short-term debt, and other short-term liabilities.

The ideal range for the Working Capital Ratio varies across industries, but generally, a ratio of 1.5 or higher is considered healthy. A ratio below 1 implies that the company may have difficulties meeting its short-term obligations, while a ratio significantly higher than 1 may indicate that the company is not efficiently using its short-term assets.

It's essential to interpret the Working Capital Ratio in the context of the specific industry and the company's

unique circumstances. A high ratio may not always be desirable, as it could signify excess idle assets, while a lower ratio may not necessarily mean financial distress if the company can manage its short-term obligations effectively.

As with any financial metric, it's crucial to analyze the Working Capital Ratio in conjunction with other financial ratios and performance indicators to gain a comprehensive understanding of a company's financial health.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Quick Ratio (Acid-Test Ratio)

The Quick Ratio, also known as the Acid-Test Ratio, is another financial metric used to assess a company's short-term liquidity and its ability to meet its immediate obligations without relying on the sale of inventory. It is a more stringent measure of liquidity than the Working Capital Ratio because it excludes inventory from current assets. The Quick Ratio provides insight into a company's ability to cover its current liabilities using its most liquid assets.

The formula for calculating the Quick Ratio is as follows:

Quick Ratio = (Current Assets - Inventory) / Current Liabilities

Where:

- Current Assets: These are the same as in the Working Capital Ratio and include cash, accounts receivable, short-term investments, and other assets expected to be converted into cash within one year from the reporting date.
- Inventory: This refers to the value of the company's unsold products or goods that are still in the process of being manufactured.
- Current Liabilities: These are the same as in the Working Capital Ratio and represent the obligations due within one year from the reporting date.

The Quick Ratio provides a more conservative measure of a company's short-term liquidity because it excludes inventory, which may not be readily convertible into cash in case of financial difficulties or an economic downturn. Generally, a Quick Ratio of 1 or higher is considered financially healthy, as it indicates that the company can pay off its current liabilities using its most liquid assets without relying on selling inventory.

Similar to the Working Capital Ratio, the ideal Quick Ratio may vary across industries, and it's essential to consider other financial ratios and performance indicators to get a comprehensive view of a company's

financial situation. Companies in industries with more stable and predictable cash flows may have lower Quick Ratios, while those in industries with uncertain or cyclical cash flows may aim for higher Quick Ratios to ensure they can meet their obligations in challenging times.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Cash Ratio

The Cash Ratio, also known as the Cash Asset Ratio or the Cash Coverage Ratio, is a liquidity ratio that assesses a company's ability to pay off its current liabilities using only its cash and cash equivalents. It provides a conservative measure of a company's short-term liquidity, focusing solely on its most liquid assets.

The formula for calculating the Cash Ratio is as follows:

Cash Ratio = (Cash and Cash Equivalents) / Current Liabilities

Where:

- Cash and Cash Equivalents include cash on hand and highly liquid assets that are easily convertible to cash within a short period, typically within 90 days. Examples include cash in hand, cash in bank accounts, and short-term investments with maturities of 90 days or less.
- Current Liabilities represent the company's obligations that are due within one year from the reporting date. Examples include accounts payable, short-term debt, and other short-term liabilities.

The Cash Ratio indicates how well a company can meet its short-term debt obligations without relying on other current assets, such as accounts receivable or inventory. A higher Cash Ratio implies a stronger ability to pay off current liabilities using only cash and cash equivalents, which is generally considered favourable as it shows a conservative approach to liquidity management.

However, it's essential to interpret the Cash Ratio in the context of the specific industry and the company's unique circumstances. Industries with stable and predictable cash flows may have lower Cash Ratios, while those with uncertain or cyclical cash flows may aim for higher Cash Ratios to ensure they can meet their short-term obligations in challenging times.

Like any financial ratio, the Cash Ratio should be analysed alongside other liquidity ratios and financial performance indicators to gain a comprehensive understanding of a company's financial health and liquidity position.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Output with HelpNDoc's Advanced Project Analyzer

Solvency Ratios

Solvency ratios are financial metrics that assess a company's long-term financial stability and its ability to meet its long-term debt obligations. These ratios provide insight into a company's capacity to repay its debt and continue its operations in the long run. Some common solvency ratios include:

1. Debt-to-Equity Ratio (D/E): The Debt-to-Equity Ratio measures the proportion of a company's total debt to its total shareholders' equity. The formula is:

Debt-to-Equity Ratio = Total Debt / Total Shareholders' Equity

   A higher debt-to-equity ratio indicates that the company relies more on debt financing, which can increase financial risk. Conversely, a lower ratio suggests a more conservative financing approach.

2. Debt Ratio: The Debt Ratio evaluates the company's total debt in relation to its total assets. The formula is:

Debt Ratio = Total Debt / Total Assets

   A higher debt ratio implies a larger portion of the company's assets is funded by debt, which can be a sign of higher financial leverage and risk.

3. Interest Coverage Ratio: The Interest Coverage Ratio (also known as Times Interest Earned) measures the company's ability to meet its interest payments on outstanding debt. The formula is:

Interest Coverage Ratio = Earnings Before Interest and Taxes (EBIT) / Interest Expense

   A higher interest coverage ratio indicates that the company generates sufficient operating income to cover its interest expenses comfortably.

4. Debt Service Coverage Ratio (DSCR): The Debt Service Coverage Ratio assesses a company's ability to cover its total debt service obligations, including principal and interest payments. The formula is:

DSCR = (Net Operating Income + Depreciation & Amortization) / Total Debt Service

   A DSCR greater than 1 indicates that the company generates enough cash flow to meet its debt service requirements.

Solvency ratios are crucial for investors, lenders, and other stakeholders to gauge the company's long-term financial health and its ability to manage its debt obligations. A company with strong solvency ratios is generally considered more financially stable and less risky.

However, it's essential to analyze solvency ratios in conjunction with other financial indicators and ratios to gain a comprehensive understanding of the company's overall financial position. Moreover, industries with different capital structures and risk profiles may have varying acceptable ranges for these ratios.

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Debt-to-Equity Ratio (D/E)

The Debt-to-Equity Ratio (D/E) is a financial ratio that measures a company's capital structure by comparing its total debt to its total shareholders' equity. It provides insights into the company's financial leverage and the proportion of debt and equity financing used to fund its operations.

The formula for calculating the Debt-to-Equity Ratio is as follows:

Debt-to-Equity Ratio = Total Debt / Total Shareholders' Equity

Where:

- Total Debt refers to the sum of all the company's outstanding debt obligations, including short-term and long-term debt, loans, and other borrowings.
- Total Shareholders' Equity represents the residual interest in the company's assets after deducting liabilities. It includes common equity, preferred equity, retained earnings, and other equity components.

The Debt-to-Equity Ratio provides a view of how much debt a company is using relative to its equity. A higher D/E ratio indicates that the company relies more on debt financing, which can increase financial risk and the company's sensitivity to changes in interest rates. On the other hand, a lower D/E ratio suggests a more conservative financing approach with a larger portion of the company's assets being funded by equity.

Interpretation of the Debt-to-Equity Ratio depends on various factors, including the company's industry, business model, and risk tolerance. Different industries may have varying levels of acceptable leverage, and it's essential to consider the company's specific circumstances when analyzing the ratio.

For example:

- A D/E ratio below 1 suggests that the company has more equity than debt, indicating a lower financial risk and a conservative capital structure.
- A D/E ratio above 1 indicates that the company has more debt than equity, suggesting a higher

financial risk and a leveraged capital structure.

Investors and analysts use the Debt-to-Equity Ratio to assess a company's financial risk and the extent to which it relies on debt financing. However, it should be used in conjunction with other financial ratios and metrics to gain a comprehensive understanding of a company's overall financial health and risk profile.

Created with the Standard Edition of HelpNDoc: Free Web Help generator

Debt Ratio

The Debt Ratio, also known as the Debt-to-Assets Ratio, is a financial ratio that measures the proportion of a company's assets that are financed through debt. It provides insights into the company's overall leverage and the extent to which debt is used to fund its operations and acquire assets.

The formula for calculating the Debt Ratio is as follows:

Debt Ratio = Total Debt / Total Assets

Where:

- Total Debt refers to the sum of all the company's outstanding debt obligations, including both short-term and long-term debt, loans, and other borrowings.
- Total Assets represent the total value of all the company's assets, including current and non-current assets.

The Debt Ratio indicates the percentage of a company's assets that are funded by debt. A higher Debt Ratio implies that a larger portion of the company's assets is financed through debt, which can increase financial risk and make the company more sensitive to changes in interest rates or adverse economic conditions.

On the other hand, a lower Debt Ratio suggests that the company relies more on equity financing and has a more conservative capital structure, which may be viewed as less risky.

Interpretation of the Debt Ratio depends on the industry and the company's specific circumstances. Industries with stable and predictable cash flows, such as utilities, may have higher Debt Ratios, while companies in more cyclical industries may aim for lower Debt Ratios to mitigate risk.

For example:

- A Debt Ratio of 0.50 indicates that 50% of the company's assets are financed through debt.
- A Debt Ratio of 0.25 indicates that only 25% of the company's assets are financed through debt.

Investors and analysts use the Debt Ratio to assess a company's level of leverage and its financial risk. However, as with any financial ratio, it should be used in conjunction with other financial metrics and industry analysis to gain a comprehensive understanding of a company's financial health and risk profile.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Interest Coverage Ratio

The Interest Coverage Ratio, also known as the Times Interest Earned (TIE) ratio, is a financial metric used to assess a company's ability to meet its interest obligations on its outstanding debt. It provides insights into the company's capacity to cover its interest expenses with its operating income.

The formula for calculating the Interest Coverage Ratio is as follows:

Interest Coverage Ratio = Earnings Before Interest and Taxes (EBIT) / Interest Expense

Where:

- Earnings Before Interest and Taxes (EBIT) represents the company's operating income before deducting interest and taxes. It indicates how much profit the company generates from its core operations before considering financing and tax-related factors.
- Interest Expense refers to the total interest paid on the company's outstanding debt during a specific period.

The Interest Coverage Ratio quantifies the number of times a company's operating income can cover its interest expenses. A higher Interest Coverage Ratio indicates that the company generates enough operating income to comfortably meet its interest obligations, which suggests lower financial risk and a greater ability to service its debt.

For example:

- An Interest Coverage Ratio of 5 means that the company's EBIT is five times higher than its interest expense, suggesting that it can cover its interest payments five times over.
- An Interest Coverage Ratio of 1 implies that the company's EBIT is just sufficient to cover its interest expenses, leaving little margin for unforeseen events or changes in business conditions.

A low Interest Coverage Ratio may raise concerns for investors and creditors, as it indicates a higher risk of potential difficulties in servicing the company's debt obligations. Companies with low interest coverage may face challenges in obtaining favourable financing terms and might be considered riskier investments.

The Interest Coverage Ratio is an essential financial metric used by investors, creditors, and analysts to

assess a company's financial health and its ability to meet its debt obligations. However, as with any financial ratio, it should be analyzed alongside other performance indicators and industry benchmarks to gain a comprehensive understanding of a company's financial position and risk profile.

Created with the Standard Edition of HelpNDoc: Protect Your Confidential PDFs with These Simple Security Measures

Debt Service Coverage Ratio (DSCR)

The Debt Service Coverage Ratio (DSCR) is a financial metric used to assess a company's ability to meet its debt service obligations, including both principal and interest payments. It is a critical measure for creditors and lenders as it indicates the company's capacity to generate sufficient cash flow to service its debt.

The formula for calculating the Debt Service Coverage Ratio is as follows:

DSCR = (Net Operating Income + Depreciation & Amortization) / Total Debt Service

Where:

- Net Operating Income (NOI) refers to the company's operating income after deducting operating expenses, but before deducting interest and taxes. It represents the cash generated from the company's core operations.
- Depreciation & Amortization are non-cash expenses that are added back to NOI since they do not involve cash outflows.
- Total Debt Service includes all principal and interest payments that the company is required to make on its outstanding debt during a specific period.

The Debt Service Coverage Ratio measures the number of times a company's operating income (including non-cash expenses) can cover its debt service payments. A DSCR greater than 1 indicates that the company generates enough cash flow to comfortably cover its debt obligations, which suggests a lower risk of default.

For example:

- A DSCR of 1.5 means that the company's cash flow is 1.5 times greater than its total debt service, implying a comfortable margin of safety.
- A DSCR of less than 1 suggests that the company's cash flow is not sufficient to meet its debt obligations fully, indicating a higher risk of default.

Lenders and creditors typically require a minimum DSCR when evaluating a company's creditworthiness. The required DSCR may vary depending on the industry, the type of loan or credit facility, and the perceived risk associated with the borrower.

A high DSCR is generally favorable, indicating a strong ability to manage debt, while a low DSCR raises concerns about the company's ability to meet its debt obligations and may affect its borrowing capacity and interest rates.

The Debt Service Coverage Ratio is a critical financial metric used in loan underwriting, credit analysis, and investment decisions. However, it should be used alongside other financial ratios and performance indicators to gain a comprehensive understanding of a company's financial health and debt-servicing capability.

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Profitability Ratios

Profitability ratios are financial metrics that assess a company's ability to generate profits and earnings relative to its revenue, assets, equity, and other factors. These ratios provide insights into the company's overall financial performance and its efficiency in generating profits from its operations. Some common profitability ratios include:

1. Gross Profit Margin: The Gross Profit Margin measures the percentage of revenue that exceeds the cost of goods sold. It indicates how efficiently a company produces goods or services. The formula is:

   Gross Profit Margin = (Gross Profit / Revenue) x 100

   A higher gross profit margin is generally desirable as it shows the company is effectively managing its production costs.

2. Operating Profit Margin: The Operating Profit Margin (or Operating Margin) shows the percentage of revenue that remains after deducting operating expenses but before interest and taxes. The formula is:

   Operating Profit Margin = (Operating Profit / Revenue) x 100

   A higher operating profit margin indicates that the company is efficiently managing its operating expenses.

3. Net Profit Margin: The Net Profit Margin measures the percentage of revenue that remains as net profit after all expenses, including taxes and interest. The formula is:

Net Profit Margin = (Net Profit / Revenue) x 100

A higher net profit margin indicates that the company is generating more profit from its revenue.

4. Return on Assets (ROA): Return on Assets calculates how efficiently a company utilizes its assets to generate profit. The formula is:

ROA = (Net Profit / Average Total Assets) x 100

A higher ROA suggests better utilization of assets to generate profit.

5. Return on Equity (ROE): Return on Equity measures how effectively a company generates profits relative to shareholders' equity. The formula is:

ROE = (Net Profit / Average Shareholders' Equity) x 100

A higher ROE indicates better returns for shareholders' investments.

6. Return on Investment (ROI): Return on Investment assesses the return generated on an investment, considering the cost of that investment. The formula is:

ROI = (Net Profit / Investment Cost) x 100

A higher ROI indicates a more favourable return relative to the investment made.

Profitability ratios provide valuable insights into a company's financial performance and can help investors and stakeholders evaluate its profitability and efficiency. It's essential to analyze profitability ratios over time and in comparison to industry benchmarks to gain a comprehensive understanding of a company's financial health and performance.

However, it's important to note that different industries may have different profit margins and return expectations, so it's crucial to consider the context of the company's specific industry and competitive landscape when interpreting these ratios.

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Gross Profit Margin

Gross Profit Margin is a financial ratio that measures a company's profitability by expressing the percentage of revenue that exceeds the cost of goods sold (COGS). It provides insight into how efficiently a company is managing its production process and pricing its products or services.

The formula for calculating the Gross Profit Margin is as follows:

Gross Profit Margin = (Gross Profit / Revenue) x 100

Where:

- Gross Profit is the difference between total revenue and the cost of goods sold. It represents the profit generated from core operations before deducting operating expenses, interest, and taxes.
- Revenue refers to the total sales or revenue generated from the sale of goods or services.

The Gross Profit Margin indicates the proportion of each dollar of revenue that remains after accounting for the cost of producing the goods or services. A higher Gross Profit Margin indicates that the company is effectively managing its production costs and generating a higher profit for each dollar of revenue.

For example:

- If a company's gross profit is $200,000, and its revenue is $500,000, the Gross Profit Margin would be (200,000 / 500,000) x 100 = 40%. This means that the company retains 40 cents of gross profit for every dollar of revenue it generates.

The Gross Profit Margin is a crucial indicator of a company's operational efficiency and pricing strategy. It helps businesses and investors understand how well the company can control its production costs and whether it can maintain a competitive advantage in the market.

However, it's essential to consider the Gross Profit Margin in conjunction with other financial ratios and metrics to gain a comprehensive understanding of a company's overall profitability and financial performance.

Different industries may have varying levels of acceptable gross profit margins, so it's essential to compare a company's ratio to industry benchmarks and competitors for a more meaningful analysis.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Operating Profit Margin

Operating Profit Margin, also known as Operating Margin, is a financial ratio that measures a company's profitability from its core operations. It represents the percentage of revenue that remains as operating profit after deducting all operating expenses but before considering interest and taxes.

The formula for calculating the Operating Profit Margin is as follows:

Operating Profit Margin = (Operating Profit / Revenue) x 100

Where:

- Operating Profit (also known as Operating Income or Earnings Before Interest and Taxes - EBIT) refers to the profit generated from the company's core operations before deducting interest and taxes.
- Revenue represents the total sales or revenue generated from the sale of goods or services.

The Operating Profit Margin indicates the company's efficiency in managing its operating expenses and generating profits from its main business activities. A higher Operating Profit Margin implies that the company is effectively controlling its operating costs and generating a larger proportion of profit for each dollar of revenue.

For example:

- If a company's operating profit is $100,000, and its revenue is $500,000, the Operating Profit Margin would be (100,000 / 500,000) x 100 = 20%. This means that the company retains 20 cents of operating profit for every dollar of revenue it generates.

The Operating Profit Margin is a key indicator of a company's operational efficiency and financial health. It helps investors and analysts understand how well the company's core business is performing and how much profit it can generate from its day-to-day operations.

It's important to note that the Operating Profit Margin may vary significantly across industries. Some industries with higher operating costs, such as manufacturing or retail, may typically have lower operating profit margins compared to industries with lower operating costs, such as technology or software.

As with any financial ratio, it's essential to consider the Operating Profit Margin in conjunction with other financial metrics and industry benchmarks to gain a comprehensive view of a company's financial performance and profitability.

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Net Profit Margin

Net Profit Margin, also known as Net Margin, is a financial ratio that measures a company's profitability by expressing the percentage of net income (profit) generated from each dollar of revenue. It provides insights into how efficiently a company manages its operating expenses, interest expenses, taxes, and other costs to generate profit.

The formula for calculating the Net Profit Margin is as follows:

Net Profit Margin = (Net Profit / Revenue) x 100

Where:

- Net Profit (also known as Net Income or Net Earnings) refers to the profit remaining after deducting all expenses, including operating expenses, interest expenses, taxes, and other costs, from the total revenue.
- Revenue represents the total sales or revenue generated from the sale of goods or services.

The Net Profit Margin measures the company's overall profitability after all expenses have been accounted for. A higher Net Profit Margin indicates that the company is efficiently managing its costs and generating a larger proportion of profit from each dollar of revenue.

For example:

- If a company's net profit is $50,000, and its revenue is $500,000, the Net Profit Margin would be (50,000 / 500,000) x 100 = 10%. This means that the company retains 10 cents of net profit for every dollar of revenue it generates.

The Net Profit Margin is a critical indicator of a company's financial performance and efficiency in managing its expenses. It provides valuable insights into the company's ability to control costs, maintain profitability, and generate returns for its shareholders.

As with other financial ratios, it's essential to consider the Net Profit Margin in conjunction with other financial metrics and industry benchmarks to gain a comprehensive view of a company's financial health and profitability.

Comparing the Net Profit Margin to industry peers and historical performance can help assess the company's competitiveness and long-term sustainability. Additionally, changes in the Net Profit Margin over time can indicate trends in the company's profitability and performance.

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Return on Assets (ROA)

Return on Assets (ROA) is a financial ratio that measures a company's profitability in relation to its total assets. It provides insight into how effectively a company is utilizing its assets to generate profit.

The formula for calculating the Return on Assets (ROA) is as follows:

ROA = (Net Income / Average Total Assets) x 100

Where:

- Net Income (also known as Net Profit or Net Earnings) represents the company's profit after deducting all expenses, including operating expenses, interest expenses, taxes, and other costs, from the total revenue.
- Average Total Assets is the average value of the company's total assets over a specific period. It is calculated by adding the total assets at the beginning and end of the period and dividing by 2.

The ROA measures the company's ability to generate earnings from its assets. A higher ROA indicates that the company is effectively utilizing its assets to generate profit. Conversely, a lower ROA suggests that the company is not generating as much profit relative to its asset base.

For example:

- If a company's net income is $50,000, and its average total assets are $500,000, the ROA would be (50,000 / 500,000) x 100 = 10%. This means that the company generates a 10% return on its total assets.

ROA is a crucial financial performance metric for investors, creditors, and management. It helps assess a company's efficiency in generating profit and provides a basis for comparison with industry peers and historical performance. A high ROA is generally desirable, as it indicates that the company is utilizing its assets effectively to generate earnings.

It's essential to interpret ROA in the context of the company's industry and business model. Industries with high capital intensity, such as manufacturing, may have lower ROAs due to significant asset investments. On the other hand, industries with asset-light business models, such as technology companies, may have higher ROAs.

As with any financial ratio, it's essential to consider the ROA in conjunction with other financial metrics and industry benchmarks to gain a comprehensive understanding of a company's financial performance and profitability. Additionally, analyzing trends in ROA over time can provide insights into a company's performance and efficiency improvements.

Created with the Standard Edition of HelpNDoc: Make Documentation Review a Breeze with HelpNDoc's Advanced Project Analyzer

Return on Equity (ROE)

Return on Equity (ROE) is a financial ratio that measures a company's profitability in relation to its shareholders' equity. It provides insight into how effectively a company is generating returns for its

shareholders' investment.

The formula for calculating the Return on Equity (ROE) is as follows:

ROE = (Net Income / Average Shareholders' Equity) x 100

Where:

- Net Income (also known as Net Profit or Net Earnings) represents the company's profit after deducting all expenses, including operating expenses, interest expenses, taxes, and other costs, from the total revenue.
- Average Shareholders' Equity is the average value of the company's shareholders' equity over a specific period. It is calculated by adding the shareholders' equity at the beginning and end of the period and dividing by 2.

The ROE measures the company's ability to generate profit relative to the shareholders' investment in the company. A higher ROE indicates that the company is generating higher returns for its shareholders' equity, which is generally considered favorable.

For example:

- If a company's net income is $50,000, and its average shareholders' equity is $500,000, the ROE would be (50,000 / 500,000) x 100 = 10%. This means that the company generates a 10% return on shareholders' equity.

ROE is a critical financial performance metric for investors, as it helps assess the company's profitability and its ability to generate returns on investment for shareholders. A high ROE is generally considered a positive sign, indicating that the company is effectively utilizing its equity to generate earnings.

It's essential to interpret ROE in the context of the company's industry and business model. Industries with higher capital requirements or lower-profit margins may have lower ROEs, while industries with asset-light business models or higher-profit margins may have higher ROEs.

As with any financial ratio, it's essential to consider the ROE in conjunction with other financial metrics and industry benchmarks to gain a comprehensive understanding of a company's financial performance and profitability. Additionally, analyzing trends in ROE over time can provide insights into a company's performance and efficiency improvements.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Return on Investment (ROI)

Return on Investment (ROI) is a financial metric used to evaluate the profitability or efficiency of an investment or a business venture. It measures the return or gain on an investment relative to its cost.

The formula for calculating Return on Investment (ROI) is as follows:

ROI = (Net Profit from Investment / Cost of Investment) x 100

Where:

- Net Profit from Investment refers to the gain or profit generated from the investment. It is calculated by subtracting the initial cost of the investment from the final value or returns.
- Cost of Investment represents the initial investment amount or the total cost incurred to acquire the investment.

The ROI is expressed as a percentage, representing the return on the investment relative to the initial cost. A positive ROI indicates that the investment has generated a profit, while a negative ROI suggests a loss.

For example:

- If an investment costs $10,000, and it generates a net profit of $2,000, the ROI would be (2,000 / 10,000) x 100 = 20%. This means that the investment has a 20% return on investment.

ROI is a fundamental metric used by investors, businesses, and financial analysts to assess the success and profitability of an investment. It helps compare the returns from different investment opportunities and make informed decisions on allocating capital.

However, it's essential to consider the time frame and risks associated with the investment when interpreting ROI. A high ROI may not necessarily be the best indicator of the investment's long-term success. Some investments may have a higher ROI but come with higher risk, while others may have a lower ROI but provide stable and consistent returns.

ROI is a versatile metric used in various contexts, including assessing the performance of stocks, real estate investments, marketing campaigns, capital projects, and business expansions. As with any financial metric, ROI should be used alongside other performance indicators and financial ratios to gain a comprehensive understanding of the investment's overall performance and potential.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Efficiency Ratios

Efficiency Ratios, also known as activity ratios, are financial metrics used to assess how effectively a

company manages its assets, liabilities, and other resources to generate sales and revenue. These ratios provide insights into the company's operational efficiency, asset utilization, and overall effectiveness in managing its resources. Some common efficiency ratios include:

1. Inventory Turnover Ratio: The Inventory Turnover Ratio measures how many times a company sells and replaces its inventory within a specific period. The formula is:

Inventory Turnover Ratio = Cost of Goods Sold / Average Inventory

   A higher inventory turnover ratio indicates that the company is efficiently managing its inventory and selling products quickly.

2. Accounts Receivable Turnover Ratio: The Accounts Receivable Turnover Ratio assesses how quickly a company collects its accounts receivable from customers. The formula is:

Accounts Receivable Turnover Ratio = Net Credit Sales / Average Accounts Receivable

   A higher accounts receivable turnover ratio suggests that the company is efficient in collecting payments from customers.

3. Accounts Payable Turnover Ratio: The Accounts Payable Turnover Ratio measures how quickly a company pays off its suppliers. The formula is:

Accounts Payable Turnover Ratio = Purchases / Average Accounts Payable

   A higher accounts payable turnover ratio indicates that the company is managing its payables efficiently.

4. Asset Turnover Ratio: The Asset Turnover Ratio evaluates how efficiently a company utilizes its assets to generate sales. The formula is:

Asset Turnover Ratio = Revenue / Average Total Assets

   A higher asset turnover ratio suggests better utilization of assets to generate revenue.

5. Fixed Asset Turnover Ratio: The Fixed Asset Turnover Ratio measures how efficiently a company uses its fixed assets (such as property, plant, and equipment) to generate sales. The formula is:

Fixed Asset Turnover Ratio = Revenue / Average Fixed Assets

   A higher fixed asset turnover ratio indicates that the company is efficiently using its fixed assets.

6. Total Asset Turnover Ratio: The Total Asset Turnover Ratio combines both the fixed and current asset utilization to measure how effectively all assets generate revenue. The formula is:

Total Asset Turnover Ratio = Revenue / Average Total Assets

A higher total asset turnover ratio implies better overall asset efficiency in generating revenue.

Efficiency ratios help investors and stakeholders assess a company's operational performance and resource management. By comparing these ratios with industry benchmarks and historical performance, one can identify areas where the company is performing well or where improvements might be needed.

However, it's essential to consider efficiency ratios in conjunction with other financial metrics to get a comprehensive view of a company's financial health and performance.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Inventory Turnover Ratio

Inventory Turnover Ratio is a financial ratio that measures the efficiency with which a company manages its inventory. It evaluates how quickly a company sells and replaces its inventory over a specific period, typically a year.

The formula for calculating the Inventory Turnover Ratio is as follows:

Inventory Turnover Ratio = Cost of Goods Sold (COGS) / Average Inventory

Where:

- Cost of Goods Sold (COGS) represents the direct costs associated with producing or purchasing the goods that a company sells during a specific period.
- Average Inventory is the average value of the company's inventory over the same period. It is calculated by adding the beginning inventory value and the ending inventory value and then dividing by 2.

The Inventory Turnover Ratio indicates the number of times a company sells its entire inventory during a specific period. A higher Inventory Turnover Ratio implies that the company is efficiently managing its inventory and selling products quickly, which can be beneficial for cash flow and profitability.

For example:

- If a company's Cost of Goods Sold (COGS) is $500,000, and its Average Inventory is $100,000, the Inventory Turnover Ratio would be 500,000 / 100,000 = 5. This means that the company sold and replaced its entire inventory five times during the period.

A low Inventory Turnover Ratio may indicate that the company has excess inventory or is facing challenges in selling its products. Conversely, a very high Inventory Turnover Ratio might suggest that the company is running out of stock frequently, potentially leading to lost sales.

The ideal Inventory Turnover Ratio varies among industries. Some industries, such as fashion or technology, may have faster inventory turnover due to rapidly changing trends, while industries with perishable goods may also have higher turnover rates.

Businesses can use the Inventory Turnover Ratio to assess their inventory management practices and identify areas for improvement. An increase in the ratio may suggest that the company is becoming more efficient in managing its inventory, while a decrease might signal inefficiencies or excess stock.

It's essential to analyze the Inventory Turnover Ratio in conjunction with industry benchmarks and other financial metrics to gain a comprehensive understanding of a company's inventory management performance.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

Accounts Receivable Turnover Ratio

The Accounts Receivable Turnover Ratio is a financial metric that measures how effectively a company is managing its accounts receivable (or credit sales) and collecting payments from customers. It assesses how quickly the company is converting its credit sales into cash.

The formula for calculating the Accounts Receivable Turnover Ratio is as follows:

Accounts Receivable Turnover Ratio = Net Credit Sales / Average Accounts Receivable

Where:

- Net Credit Sales represents the total sales made on credit during a specific period, excluding cash sales.
- Average Accounts Receivable is the average value of accounts receivable over the same period. It is calculated by adding the beginning accounts receivable balance and the ending accounts receivable balance and then dividing by 2.

The Accounts Receivable Turnover Ratio indicates the number of times a company collects its average accounts receivable balance during a specific period. A higher turnover ratio implies that the company is efficiently collecting payments from customers, converting credit sales to cash quickly, and managing its accounts receivable effectively.

For example:

- If a company's Net Credit Sales for the year were $500,000, and its Average Accounts Receivable was $50,000, the Accounts Receivable Turnover Ratio would be 500,000 / 50,000 = 10. This means that the

company collected its average accounts receivable balance 10 times during the year.

A high Accounts Receivable Turnover Ratio is generally favorable, as it indicates effective credit management and timely collections. Conversely, a low ratio may suggest that the company is facing challenges in collecting payments promptly or has lenient credit terms for customers.

Companies can use the Accounts Receivable Turnover Ratio to evaluate their credit policies and collection procedures. A declining ratio over time might indicate worsening credit practices or potential issues with customers' creditworthiness.

It's important to analyze the Accounts Receivable Turnover Ratio in conjunction with industry benchmarks and other financial metrics. Industries with different credit policies and sales cycles may have varying levels of acceptable turnover ratios.

Overall, a healthy and consistent Accounts Receivable Turnover Ratio can positively impact a company's cash flow, liquidity, and working capital management. By improving collection practices, companies can enhance their financial stability and reduce the risk of bad debts.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Accounts Payable Turnover Ratio

The Accounts Payable Turnover Ratio is a financial metric that measures how efficiently a company manages its accounts payable and pays its suppliers. It evaluates how quickly a company is settling its outstanding obligations to suppliers or creditors.

The formula for calculating the Accounts Payable Turnover Ratio is as follows:

Accounts Payable Turnover Ratio = Total Purchases / Average Accounts Payable

Where:

- Total Purchases represents the total value of goods or services purchased on credit during a specific period. It is calculated by adding the beginning accounts payable balance to the total credit purchases made during the period and then subtracting the ending accounts payable balance.
- Average Accounts Payable is the average value of accounts payable over the same period. It is calculated by adding the beginning accounts payable balance and the ending accounts payable balance and then dividing by 2.

The Accounts Payable Turnover Ratio indicates the number of times a company pays its average accounts payable balance during a specific period. A higher turnover ratio suggests that the company is efficiently

managing its payments to suppliers and settling obligations promptly.

For example:

- If a company's Total Purchases during the year were $500,000, and its Average Accounts Payable was $50,000, the Accounts Payable Turnover Ratio would be 500,000 / 50,000 = 10. This means that the company paid its average accounts payable balance 10 times during the year.

A high Accounts Payable Turnover Ratio generally indicates favourable payment practices, which may lead to better supplier relationships and potentially discounts or better terms on future purchases. However, an excessively high ratio might also indicate that the company is paying suppliers too quickly and might be missing out on the benefits of delayed payment terms.

On the other hand, a low ratio might suggest that the company is facing challenges in making timely payments to suppliers, which could affect supplier relationships and might even lead to credit issues.

Analyzing the Accounts Payable Turnover Ratio can help companies evaluate their cash flow management and supplier payment strategies. It's crucial to consider the industry norms and the company's specific business model when interpreting the ratio, as different industries may have different payment practices and supplier relationships.

Overall, a balanced and consistent Accounts Payable Turnover Ratio is desirable, indicating that the company is managing its cash flow effectively and maintaining good relationships with its suppliers.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Asset Turnover Ratio

Asset Turnover Ratio is a financial metric that measures a company's efficiency in utilizing its assets to generate revenue. It evaluates how effectively a company generates sales from its total assets.

The formula for calculating the Asset Turnover Ratio is as follows:

Asset Turnover Ratio = Revenue (or Sales) / Average Total Assets

Where:

- Revenue (or Sales) represents the total sales or revenue generated by the company during a specific period.
- Average Total Assets is the average value of the company's total assets over the same period. It is calculated by adding the total assets at the beginning and end of the period and then dividing by 2.

The Asset Turnover Ratio indicates the amount of revenue generated for each dollar of assets invested. A higher Asset Turnover Ratio suggests that the company is efficiently utilizing its assets to generate sales, while a lower ratio may indicate that the company is not using its assets effectively.

For example:

- If a company's revenue is $1,000,000, and its average total assets are $500,000, the Asset Turnover Ratio would be 1,000,000 / 500,000 = 2. This means that the company generates $2 of revenue for every dollar of assets invested.

The interpretation of the Asset Turnover Ratio depends on the industry and business model. Some industries, such as retail or hospitality, may have higher asset turnover due to their fast-moving nature and lower asset requirements. In contrast, capital-intensive industries, such as manufacturing or utilities, may have lower asset turnover due to higher investments in fixed assets.

A declining Asset Turnover Ratio over time may indicate that the company's sales are not growing proportionately to its asset base, and further analysis might be required to identify the underlying reasons.

Comparing the Asset Turnover Ratio to industry peers and historical performance can provide insights into a company's competitive position and operational efficiency.

Overall, a healthy Asset Turnover Ratio reflects a company's ability to generate revenue efficiently from its assets, which is crucial for maintaining profitability and optimizing the use of resources.

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Fixed Asset Turnover Ratio

Fixed Asset Turnover Ratio is a financial metric that measures a company's efficiency in utilizing its fixed assets to generate revenue. It specifically focuses on how effectively a company generates sales from its fixed or long-term assets, such as property, plant, and equipment.

The formula for calculating the Fixed Asset Turnover Ratio is as follows:

Fixed Asset Turnover Ratio = Revenue (or Sales) / Average Net Fixed Assets

Where:

- Revenue (or Sales) represents the total sales or revenue generated by the company during a specific period.
- Average Net Fixed Assets is the average value of the company's net fixed assets over the

same period. It is calculated by adding the net fixed assets at the beginning and end of the period and then dividing by 2.

Net Fixed Assets is calculated as follows:

Net Fixed Assets = Total Fixed Assets - Accumulated Depreciation

The Fixed Asset Turnover Ratio indicates the amount of revenue generated for each dollar of net fixed assets invested. A higher Fixed Asset Turnover Ratio suggests that the company is efficiently using its fixed assets to generate sales, while a lower ratio may indicate that the company is not utilizing its fixed assets effectively.

For example:

- If a company's revenue is $2,000,000, and its average net fixed assets are $1,000,000, the Fixed Asset Turnover Ratio would be 2,000,000 / 1,000,000 = 2. This means that the company generates $2 of revenue for every dollar of net fixed assets invested.

Similar to the Asset Turnover Ratio, the interpretation of the Fixed Asset Turnover Ratio depends on the industry and business model. Capital-intensive industries with substantial fixed asset investments, such as manufacturing or transportation, may have lower fixed asset turnover ratios compared to asset-light industries like technology or service-oriented businesses.

A declining Fixed Asset Turnover Ratio over time may suggest that the company's sales are not growing in proportion to its fixed asset base, which could indicate inefficiencies in asset utilization.

It's essential to compare the Fixed Asset Turnover Ratio to industry peers and historical performance to gain insights into the company's operational efficiency and asset management practices.

A healthy and consistent Fixed Asset Turnover Ratio indicates that the company is effectively leveraging its fixed assets to generate revenue, contributing to overall profitability and return on investment.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Market Ratios

Market ratios, also known as valuation ratios or market multiples, are financial metrics that help investors and analysts assess a company's valuation and its attractiveness as an investment. These ratios use the company's stock market price and other market data to evaluate its performance and potential. Some common market ratios include:

1. Price-to-Earnings Ratio (P/E Ratio): The Price-to-Earnings Ratio compares a company's stock price

with its earnings per share (EPS). The formula is:

P/E Ratio = Stock Price / Earnings per Share

A higher P/E ratio typically indicates that investors are willing to pay more for each dollar of earnings, suggesting a higher expectation for future growth or performance.

2. Price-to-Book Ratio (P/B Ratio): The Price-to-Book Ratio compares a company's stock price with its book value per share, which represents the net asset value of the company. The formula is:

P/B Ratio = Stock Price / Book Value per Share

A higher P/B ratio suggests that the stock is trading at a premium relative to its book value, indicating positive investor sentiment.

3. Dividend Yield: The Dividend Yield measures the percentage of dividends paid per share relative to the stock's current market price. The formula is:

Dividend Yield = Annual Dividend per Share / Stock Price

A higher dividend yield indicates a higher return on investment from dividends.

4. Earnings per Share (EPS): Earnings per Share represents the company's net earnings available to common shareholders divided by the average number of outstanding shares. It is often used as a component in other market ratios.

EPS = Net Earnings / Average Number of Outstanding Shares

Higher EPS typically indicates better profitability on a per-share basis.

5. Price-to-Sales Ratio (P/S Ratio): The Price-to-Sales Ratio compares a company's stock price with its revenue per share. The formula is:

P/S Ratio = Stock Price / Revenue per Share

A higher P/S ratio suggests that investors are willing to pay more for each dollar of revenue, indicating positive market sentiment.

6. Market Capitalization: Market Capitalization represents the total value of a company's outstanding shares of stock. It is calculated by multiplying the stock price by the number of outstanding shares.

Market Capitalization = Stock Price × Number of Outstanding Shares

Market capitalization provides an indication of the company's size in the market.

These market ratios provide valuable information to investors, helping them assess a company's relative value, growth potential, and risk. However, it's essential to use these ratios in conjunction with other

financial metrics and industry analysis to make well-informed investment decisions.

Additionally, market ratios may vary significantly among companies and industries, so it's essential to compare them against industry peers and historical data for a more accurate assessment.

Created with the Standard Edition of HelpNDoc: Effortlessly bring your documentation online with HelpNDoc

Price-to-Earnings Ratio (P/E Ratio)

The Price-to-Earnings Ratio, commonly known as the P/E ratio, is a financial metric used to evaluate the relative valuation of a company's stock. It compares the market price of a company's shares to its earnings per share (EPS).

The formula for calculating the Price-to-Earnings Ratio is as follows:

P/E Ratio = Market Price per Share / Earnings per Share (EPS)

Where:

- Market Price per Share is the current market price of one share of the company's stock.
- Earnings per Share (EPS) is the company's net income (profit) divided by the number of outstanding shares.

The P/E ratio reflects how much investors are willing to pay for each dollar of the company's earnings. It is a measure of investor sentiment and provides insights into market expectations and the perceived growth prospects of the company.

Interpretation of P/E Ratio:

- A high P/E ratio typically suggests that investors have high expectations for the company's future earnings growth. It may indicate that the stock is considered overvalued or that investors are optimistic about the company's prospects.
- A low P/E ratio may imply that investors have lower expectations for future earnings growth or that the stock is undervalued relative to its earnings potential.

The P/E ratio is often used for comparing the valuation of different companies within the same industry or sector. Companies with similar business models and growth prospects are often compared based on their P/E ratios to assess relative attractiveness as investments.

It's important to note that the P/E ratio should not be analyzed in isolation. Investors should consider other financial metrics, the company's growth prospects, industry trends, and market conditions when making

investment decisions.

A high P/E ratio may be justified if the company has strong growth potential, innovative products or services, and a competitive advantage. Conversely, a low P/E ratio may indicate an opportunity to invest in a company with solid fundamentals and undervalued stock.

However, it's essential to exercise caution when using the P/E ratio, as it can be influenced by various factors, including market sentiment, earnings volatility, and accounting practices. As with any financial metric, it is recommended to conduct comprehensive research and analysis before making investment decisions based on the P/E ratio.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Price-to-Book Ratio (P/B Ratio)

The Price-to-Book Ratio, commonly known as the P/B ratio, is a financial metric used to evaluate the relative valuation of a company's stock. It compares the market price of a company's shares to its book value per share.

The formula for calculating the Price-to-Book Ratio is as follows:

P/B Ratio = Market Price per Share / Book Value per Share

Where:

- Market Price per Share is the current market price of one share of the company's stock.
- Book Value per Share is the company's total book value (total assets minus total liabilities) divided by the number of outstanding shares.

The P/B ratio provides insights into how the market values a company relative to its net asset value as reported in its financial statements. It indicates whether a stock is trading at a premium (P/B > 1) or a discount (P/B < 1) to its book value.

Interpretation of P/B Ratio:

- A P/B ratio greater than 1 indicates that the market is valuing the company at a premium to its book value. It may suggest that investors have high expectations for the company's future growth and profitability.
- A P/B ratio less than 1 indicates that the market is valuing the company at a discount to its book value. It may suggest that investors have lower expectations for the company's future performance.

Like the P/E ratio, the P/B ratio is often used for comparing the valuation of different companies within the same industry or sector. However, while the P/E ratio focuses on earnings, the P/B ratio focuses on the underlying asset value of the company.

Investors often use the P/B ratio to identify potential value stocks. A low P/B ratio may suggest that the company's stock is undervalued relative to its book value, making it an attractive investment opportunity. However, a low P/B ratio could also indicate underlying issues with the company or industry.

It's important to consider other financial metrics, such as the company's earnings, growth prospects, and debt levels, when using the P/B ratio for investment decisions. Additionally, the P/B ratio may not be as relevant for companies with significant intangible assets, such as technology companies, where a significant portion of the value may not be reflected in the book value.

As with any financial metric, the P/B ratio should be used in conjunction with comprehensive research and analysis to make informed investment decisions.

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Dividend Yield

Dividend Yield is a financial ratio that measures the percentage return an investor receives from owning a company's stock in the form of dividends. It is calculated by dividing the annual dividend per share by the current market price per share and then multiplying the result by 100 to express it as a percentage.

The formula for calculating Dividend Yield is as follows:

Dividend Yield = (Annual Dividend per Share / Current Market Price per Share) x 100

Where:

- Annual Dividend per Share represents the total dividends paid by the company to shareholders per share over the course of a year.
- Current Market Price per Share is the current trading price of one share of the company's stock in the stock market.

The Dividend Yield provides insights into the income generated by a stock relative to its current market price. It is especially relevant for income-oriented investors who seek regular dividend payments as a source of income from their investments.

Interpretation of Dividend Yield:

- A higher Dividend Yield indicates that the company is paying a larger proportion of its earnings as

dividends, making it attractive for income-focused investors.

- A lower Dividend Yield suggests that the company is retaining a larger portion of its earnings for reinvestment or other purposes and may not be as appealing to income-focused investors.

It's important to note that Dividend Yield is not the same as the total return on an investment. It only considers the dividend income component and does not take into account the potential price appreciation or depreciation of the stock.

Investors should consider other factors such as the company's dividend policy, financial health, growth prospects, and stability when evaluating the attractiveness of a stock based on its dividend yield. Additionally, companies with higher dividend yields might not always be the best long-term investments if they are sacrificing growth opportunities by distributing too much of their earnings as dividends.

Dividend Yield is a useful metric for comparing the income-generating potential of different stocks, especially within the same industry or sector. However, it should be used in conjunction with other financial metrics and thorough research to make well-informed investment decisions.

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Earnings per Share (EPS)

Earnings per Share (EPS) is a fundamental financial metric that represents the portion of a company's profit or earnings attributable to each outstanding share of its common stock. It is a key indicator of a company's profitability on a per-share basis and is widely used by investors and analysts to assess a company's financial performance.

The formula for calculating Earnings per Share (EPS) is as follows:

EPS = (Net Income - Preferred Dividends) / Weighted Average Number of Common Shares Outstanding

Where:

- Net Income represents the company's total earnings after deducting all expenses, taxes, and interest.
- Preferred Dividends represent dividends paid to preferred shareholders (if applicable) and are subtracted from net income to arrive at earnings available to common shareholders.
- Weighted Average Number of Common Shares Outstanding is the average number of

common shares outstanding during a specific period. It considers changes in the number of shares over time, such as stock issuances or repurchases.

EPS is a crucial metric for investors because it allows them to evaluate a company's earnings performance on a per-share basis, regardless of the company's size or capital structure. It helps investors understand how much profit they can expect to earn for each share they own.

Interpretation of Earnings per Share (EPS):

- A higher EPS indicates that the company is generating more earnings per share, which is generally considered positive and may lead to higher stock prices.
- A lower EPS suggests that the company's profitability is lower on a per-share basis, which may result in a lower stock price.

EPS is commonly used to compare the earnings performance of different companies within the same industry or sector. It is also a key component of valuation metrics such as the price-to-earnings (P/E) ratio, where the market price of a company's stock is divided by its EPS to assess its relative valuation.

However, investors should be aware that EPS alone may not provide a complete picture of a company's financial health. Factors such as revenue growth, profit margins, debt levels, and cash flow are also essential in evaluating a company's overall financial performance and investment potential.

Additionally, EPS can be influenced by various accounting practices and non-recurring items, so it's crucial to analyze EPS in conjunction with other financial metrics and consider the company's overall business strategy and outlook.

Created with the Standard Edition of HelpNDoc: Make Documentation Review a Breeze with HelpNDoc's Advanced Project Analyzer

Price-to-Sales Ratio (P/S Ratio)

The Price-to-Sales Ratio, commonly known as the P/S ratio, is a financial metric used to assess the relative valuation of a company's stock in relation to its revenue or sales. It compares the market price per share to the company's revenue per share.

The formula for calculating the Price-to-Sales Ratio is as follows:

P/S Ratio = Market Price per Share / Revenue per Share

Where:

- Market Price per Share is the current trading price of one share of the company's stock in the

stock market.

- Revenue per Share represents the company's total revenue divided by the number of outstanding shares.

The P/S ratio is similar to the Price-to-Earnings (P/E) ratio but focuses on revenue rather than earnings. It is particularly useful for valuing companies that are not yet profitable or have volatile earnings. Since revenue is less subject to accounting manipulations, the P/S ratio can provide a more stable valuation metric.

Interpretation of P/S Ratio:

- A higher P/S ratio suggests that investors are willing to pay a premium for each dollar of the company's revenue, possibly indicating high growth expectations or investor optimism about the company's future prospects.
- A lower P/S ratio may indicate that the market is valuing the company at a discount to its revenue, which could suggest undervaluation or lower growth expectations.

As with any financial metric, it's essential to compare the P/S ratio of a company to industry peers and historical data to gain insights into its relative valuation and growth potential.

The P/S ratio should not be used in isolation to make investment decisions but rather as part of a comprehensive analysis. Other financial metrics, such as profitability, earnings growth, cash flow, and competitive positioning, should also be considered.

The P/S ratio is commonly used in conjunction with other valuation metrics like the P/E ratio or the Price-to-Book (P/B) ratio to gain a more comprehensive understanding of a company's valuation and investment attractiveness.

Overall, the P/S ratio provides valuable information about how the market values a company's revenue relative to its stock price, making it a useful tool for investors seeking to assess the attractiveness of a stock based on its revenue generation.

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Total Asset Turnover Ratio

Total Asset Turnover Ratio is a financial metric that measures a company's efficiency in generating revenue from its total assets, including both current and fixed assets. It evaluates how effectively a company utilizes all of its assets to generate sales.

The formula for calculating the Total Asset Turnover Ratio is as follows:

Total Asset Turnover Ratio = Revenue (or Sales) / Average Total Assets

Where:

- Revenue (or Sales) represents the total sales or revenue generated by the company during a specific period.
- Average Total Assets is the average value of the company's total assets over the same period. It is calculated by adding the total assets at the beginning and end of the period and then dividing by 2.

The Total Asset Turnover Ratio indicates the amount of revenue generated for each dollar of assets invested. A higher Total Asset Turnover Ratio suggests that the company is efficiently using its assets to generate sales, while a lower ratio may indicate that the company is not utilizing its assets effectively.

For example:

- If a company's revenue is $2,000,000, and its average total assets are $1,000,000, the Total Asset Turnover Ratio would be 2,000,000 / 1,000,000 = 2. This means that the company generates $2 of revenue for every dollar of assets invested.

The interpretation of the Total Asset Turnover Ratio depends on the industry and business model. Different industries may have varying levels of acceptable turnover ratios based on their capital intensity and business practices.

A declining Total Asset Turnover Ratio over time may indicate that the company's sales are not growing in proportion to its asset base, and further analysis might be required to identify the underlying reasons.

Comparing the Total Asset Turnover Ratio to industry peers and historical performance can provide insights into a company's operational efficiency and its ability to optimize the use of its assets.

Overall, a healthy and consistent Total Asset Turnover Ratio indicates that the company is effectively leveraging its assets to generate revenue, which contributes to overall profitability and efficiency.

However, it's essential to analyze this ratio in conjunction with other financial metrics and consider the company's specific industry and business circumstances for a comprehensive evaluation.

Created with the Standard Edition of HelpNDoc: Effortlessly optimize your documentation website for search engines

Market Capitalization

Market Capitalization, often referred to as "market cap," is a financial metric used to measure the total value of a publicly traded company. It represents the market value of a company's outstanding shares of stock and is calculated by multiplying the current market price per share by the total number of outstanding shares.

The formula for calculating Market Capitalization is as follows:

Market Capitalization = Current Market Price per Share x Total Number of Outstanding Shares

Where:

- Current Market Price per Share is the current trading price of one share of the company's stock in the stock market.
- Total Number of Outstanding Shares represents the total number of shares of the company's stock that are currently held by shareholders, including both institutional and individual investors.

Market Capitalization is a significant indicator of a company's size and overall value as perceived by the market. It provides insights into the company's relative standing compared to other companies in the market.

Based on Market Capitalization, companies are often categorized into different groups:

1. Large-Cap: Companies with a market capitalization of over several billion dollars are considered large-cap companies. They are typically well-established and have a significant market presence.
2. Mid-Cap: Companies with a market capitalization between a few hundred million dollars to several billion dollars fall into the mid-cap category. They are often in a growth phase and may have more room for expansion.
3. Small-Cap: Companies with a market capitalization of a few million to a few hundred million dollars are classified as small-cap companies. They are generally smaller, less established, and may have higher growth potential but also higher risk.

Market Capitalization is a crucial factor for investors as it influences the investment decisions of various stakeholders, including institutional investors, mutual funds, and index funds. It also plays a role in determining a company's weighting in stock market indices, such as the S&P 500 or the Dow Jones

Industrial Average.

Investors often use Market Capitalization as part of their investment analysis to identify companies of different sizes and risk profiles that align with their investment goals and strategies.

However, it's important to note that Market Capitalization alone does not provide a complete picture of a company's financial health or investment potential, and other financial metrics and qualitative factors should be considered for a comprehensive analysis.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Time Value of Money (TVM)

What is the Time Value of Money?

The Time Value of Money (TVM) is a fundamental financial concept that recognizes the idea that money's value changes over time due to the potential to earn interest or generate returns on investments. In essence, it suggests that a specific amount of money today is worth more than the same amount of money in the future or that receiving money in the future is less valuable than receiving it today.

The concept is based on the principle that money can be invested or put to productive use, earning interest, dividends, or capital gains. Therefore, a sum of money available today has the potential to grow and increase in value over time.

The Time Value of Money is crucial in various financial calculations, including:

1. Present Value (PV): Calculating the current worth of future cash flows or investments. It involves discounting future cash flows to determine their equivalent value today.
2. Future Value (FV): Determining the value of an investment or cash flow at a specific point in the future, considering the impact of interest or investment returns.
3. Net Present Value (NPV): Evaluating the profitability of an investment or project by comparing the present value of its expected future cash flows with the initial investment cost.
4. Internal Rate of Return (IRR): Calculating the rate at which an investment breaks even or generates a specific return over time.
5. Annuities and Loans: Assessing the periodic payments or instalments needed to repay a loan or the value of a series of future cash flows.

By considering the Time Value of Money, individuals and businesses can make better financial decisions, evaluate investment opportunities, and understand the real cost and potential benefits of financial

transactions over time. It is an essential concept in various fields, including finance, accounting, investing, and personal financial planning.

Is there any examples or formulas for Time Value of Money?

The Time Value of Money is best understood through examples and formulas. Let's look at a few common scenarios and the formulas used to calculate the present value, future value, and other related concepts.

1. Future Value of a Lump Sum: The future value (FV) of a lump sum investment can be calculated using the following formula:

   ```
   FV = PV * (1 + r)^n
   ```

   Where: FV = Future Value PV = Present Value (initial investment) r = Interest rate per period (expressed as a decimal) n = Number of periods (time in years or fractions of a year)

2. Present Value of a Lump Sum: The present value (PV) of a lump sum to be received in the future can be calculated using the following formula:

   ```
   PV = FV / (1 + r)^n
   ```

3. Future Value of an Annuity: An annuity is a series of equal payments made or received at regular intervals. The future value of an ordinary annuity can be calculated using the following formula:

   ```
   FV = Pmt * [(1 + r)^n - 1] / r
   ```

   Where: FV = Future Value of the annuity Pmt = Payment amount (equal periodic payment) r = Interest rate per period (expressed as a decimal) n = Number of periods (number of payments)

4. Present Value of an Annuity: The present value of an ordinary annuity can be calculated using the following formula:

   ```
   PV = Pmt * [(1 - (1 + r)^(-n)) / r]
   ```

5. Net Present Value (NPV): The net present value (NPV) is used to determine the profitability of an investment or project. It is the sum of the present values of all cash inflows and outflows associated with the investment. The formula is:

   ```
   NPV = Σ [CFt / (1 + r)^t]
   ```

   Where: NPV = Net Present Value CFt = Cash flow at time t r = Discount rate (opportunity cost of capital) t = Time period

6. Internal Rate of Return (IRR): The internal rate of return (IRR) is the discount rate that makes the NPV of an investment or project equal to zero. It is the rate at which the present value of cash inflows

equals the present value of cash outflows. The IRR is typically calculated using trial and error or using financial calculators/software.

These formulas demonstrate how the Time Value of Money concept is applied in various financial calculations. By using these formulas, individuals and businesses can assess the value of money over time, make informed investment decisions, and evaluate the profitability of projects and investments.

Created with the Standard Edition of HelpNDoc: Elevate your documentation to new heights with HelpNDoc's built-in SEO

Branches in Accounting

What is the Branches in Accounting?

In the field of accounting, there are several branches or specialized areas that cater to different aspects of financial reporting, analysis, and management. Each branch serves a unique purpose and contributes to the overall understanding of an organization's financial health. Here are some of the main branches in accounting:

1. Financial Accounting: Financial accounting is concerned with the preparation and presentation of financial statements for external users, such as investors, creditors, and regulatory authorities. The main financial statements include the income statement, balance sheet, cash flow statement, and statement of changes in equity. Financial accounting follows generally accepted accounting principles (GAAP) or international financial reporting standards (IFRS) to ensure consistency and comparability.
2. Management Accounting: Also known as managerial accounting, this branch focuses on providing internal management with the necessary financial information for decision-making, planning, and controlling business activities. Management accountants analyse data, create budgets, perform cost analysis, and generate reports that help managers make informed decisions to achieve organizational goals.
3. Cost Accounting: As mentioned earlier, cost accounting deals with the recording, analysis, and control of costs related to the production of goods and services. It involves methods such as job costing, process costing, and activity-based costing to ascertain the cost of products or services and helps in cost control and decision-making.
4. Tax Accounting: Tax accounting involves the preparation and filing of tax returns in compliance with tax laws and regulations. Tax accountants assist individuals and businesses in minimizing tax liabilities while ensuring compliance with tax laws.

5. Auditing: Auditing is the examination and verification of an organization's financial records, statements, and internal controls by independent auditors. The primary purpose of auditing is to provide an objective assessment of the financial position and performance of an entity, adding credibility to the financial statements.
6. Forensic Accounting: Forensic accounting combines accounting, investigative skills, and legal knowledge to detect and investigate financial fraud and financial crimes. Forensic accountants may be involved in litigation support, dispute resolution, and conducting fraud examinations.
7. Government and Public Sector Accounting: This branch focuses on accounting principles and practices specific to government entities and the public sector. It includes budgeting, fund accounting, and compliance with governmental accounting standards.
8. Non-profit Accounting: Non-profit accounting involves the unique financial reporting and regulatory requirements for non-profit organizations. It emphasizes transparency and accountability in the use of funds received from donations, grants, and contributions.
9. International Accounting: International accounting deals with accounting practices across different countries and regions. It considers variations in accounting principles and financial reporting standards worldwide.

These branches of accounting demonstrate the diverse roles that accountants play in various sectors and industries. Accountants may specialize in one or more of these areas based on their interests and career goals.

How Accounting software, such as osFinancials5/TurboCASH5 be applied to the branches of accounting?

Accounting software, such as osFinancials5/TurboCASH5, can be applied to various branches of accounting to streamline processes, improve efficiency, and enhance the accuracy of financial data. Here's how accounting software can be used in different branches of accounting:

1. Financial Accounting: Accounting software like osFinancials5/TurboCASH5 is designed to handle the core aspects of financial accounting, such as recording transactions, preparing financial statements (income statement, balance sheet, cash flow statement), and managing general ledger accounts. It automates the process of journal entries, posting, and trial balance preparation, making financial reporting faster and more accurate.
2. Management Accounting: Accounting software can generate detailed reports and financial analysis to support management decision-making. It allows for budgeting, variance analysis, cost allocation, and forecasting, helping management accountants analyse financial data and provide insights for strategic planning.

3. Cost Accounting: Accounting software can assist in tracking and allocating costs to different products, projects, or activities using cost allocation methods like activity-based costing. This helps businesses understand the true cost of their products or services, supporting cost control and pricing decisions.
4. Tax Accounting: Accounting software often includes tax modules that help calculate and prepare tax returns, ensuring compliance with tax laws and regulations. It can handle various tax codes, deductions, and credits, simplifying tax reporting processes.
5. Auditing: Accounting software facilitates the auditing process by providing auditors with easy access to financial data and transaction histories. Auditors can review financial records, conduct tests, and verify transactions efficiently using the software.
6. Government and Public Sector Accounting: Accounting software with fund accounting capabilities is particularly useful for government and public sector entities. It allows for separate tracking of funds and grants, ensuring compliance with budgetary and regulatory requirements.
7. Non-profit Accounting: Accounting software can accommodate the specific needs of non-profit organizations, such as fund accounting, donor tracking, and grant management. It helps non-profits report on restricted and unrestricted funds and demonstrate financial transparency to stakeholders.
8. International Accounting: Accounting software with multi-currency and multi-language capabilities can be beneficial for companies operating in multiple countries, enabling them to manage financial transactions in different currencies and comply with international accounting standards.
9. Forensic Accounting: Accounting software aids forensic accountants in conducting data analysis and identifying anomalies or patterns that may indicate financial fraud or irregularities.
10. Small Business Accounting: Accounting software is commonly used by small businesses to manage their financial transactions, generate invoices, track expenses, and reconcile bank accounts.

In summary, accounting software like osFinancials5/TurboCASH5 is versatile and can be adapted to meet the specific needs of different branches of accounting. It streamlines processes, improves data accuracy, and provides valuable financial information to support decision-making and compliance.

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Financial Accounting

What is Financial Accounting?

Financial accounting is a branch of accounting that focuses on the preparation, presentation, and reporting of financial information about an organization's economic activities to external stakeholders. Its primary purpose is to provide a clear and accurate overview of a company's financial performance and position, enabling investors, creditors, regulators, and other interested parties to make informed decisions.

Key features of financial accounting include:

1. Financial Statements: The core output of financial accounting is the preparation of financial statements. These statements summarize the financial position (balance sheet), financial performance (income statement or profit and loss statement), and cash flows (cash flow statement) of the organization over a specific period. The financial statements are prepared in accordance with generally accepted accounting principles (GAAP) or international financial reporting standards (IFRS) to ensure consistency and comparability.
2. External Reporting: The financial statements are primarily intended for external users, such as shareholders, potential investors, creditors, suppliers, government agencies, and the general public. These stakeholders use the information to assess the financial health and performance of the company.
3. Accrual Basis of Accounting: Financial accounting follows the accrual basis of accounting, where transactions are recorded when they occur, not necessarily when the cash is exchanged. This method recognizes revenues and expenses in the period in which they are earned or incurred, regardless of when the actual cash flows take place.
4. Historical Perspective: Financial accounting provides a historical perspective of a company's financial performance and position. It reports on past events and transactions rather than predicting future outcomes.
5. Objective and Neutral: Financial accounting aims to be objective and neutral in presenting financial information. It should provide a fair and unbiased representation of the company's financial affairs.
6. External Audit: Many companies engage external auditors to conduct an independent audit of their financial statements. The auditors review the financial records, internal controls, and financial reporting processes to provide assurance on the accuracy and reliability of the financial statements.
7. Key Users: The primary users of financial accounting information include investors (shareholders and potential investors), creditors (such as banks and suppliers), regulatory authorities (e.g., tax authorities and securities commissions), and analysts (financial analysts and credit rating agencies).

Overall, financial accounting plays a critical role in facilitating transparency and accountability in a company's financial dealings. It ensures that relevant and reliable financial information is available to

external stakeholders, enabling them to assess the company's performance and make informed decisions about their investments, credit offerings, and other interactions with the organization.

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Cost Accounting

What is Cost Accounting?

Cost accounting is a branch of accounting that focuses on the recording, analysis, and control of costs incurred in the production of goods or services. It involves the process of collecting, classifying, summarizing, and interpreting various costs to aid management in decision-making, cost control, and performance evaluation.

Objectives of Cost Accounting

The main objectives of cost accounting are as follows:

1. Cost Ascertainment: Determining the total cost involved in the production of goods or the provision of services. This includes direct costs (materials, labor) and indirect costs (overheads).
2. Cost Control: Identifying areas where costs can be controlled or reduced to improve efficiency and profitability.
3. Cost Planning and Budgeting: Preparing cost budgets and forecasts to set targets and allocate resources effectively.
4. Product Pricing: Assisting in determining the selling price of products or services by considering their production costs and desired profit margins.
5. Decision Making: Providing relevant cost information to aid management in making informed decisions about product lines, production methods, pricing strategies, etc.
6. Performance Evaluation: Evaluating the performance of different departments or products based on their costs and revenues.
7. Inventory Valuation: Valuing the closing inventory and its impact on the cost of goods sold in the income statement.

Methods and Techniques in Cost Accounting

Methods and Techniques in Cost Accounting:

1. Job Costing: Assigning costs to specific jobs or projects. This method is used in industries where each job is unique and requires individual costing, such as construction or custom manufacturing.
2. Process Costing: Allocating costs to a continuous production process, where large quantities of identical products are produced, such as in the chemical or food manufacturing industries.
3. Standard Costing: Establishing predetermined cost standards for products and comparing them to actual costs to identify variations and take corrective actions.
4. Activity-Based Costing (ABC): Allocating costs based on the activities that drive them, providing a more accurate understanding of the cost behavior and resource consumption.
5. Marginal Costing: Analysing the impact of changes in production volume on total costs, revenue, and profitability.
6. Absorption Costing: Allocating both variable and fixed manufacturing costs to units of output, which is required for external financial reporting under generally accepted accounting principles (GAAP).

Cost accounting plays a crucial role in helping organisations make sound financial decisions and optimize their operations by identifying cost-effective measures and controlling expenses. It is an essential tool for management in understanding the cost structure of their business and maintaining competitiveness in the market.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Management Accounting

What is Management Accounting?

Management accounting, also known as managerial accounting, is a branch of accounting that focuses on providing financial information and analysis to aid internal decision-making and help management plan, control, and make strategic decisions within an organization. Unlike financial accounting, which is primarily concerned with reporting financial information to external stakeholders, management accounting is geared towards providing relevant, timely, and detailed information to managers within the organization.

Key features and characteristics of management accounting include:

1. Internal Focus: Management accounting is primarily used for internal purposes within the

organization. It provides financial and non-financial information to assist managers in making informed decisions.

2. Forward-looking: While financial accounting primarily deals with historical financial data, management accounting emphasizes forecasting and projecting future financial and operational outcomes.
3. Decision Support: The primary goal of management accounting is to support decision-making processes by providing relevant data, performance metrics, and analysis to aid in evaluating alternatives and selecting the best course of action.
4. Costing and Cost Analysis: Management accounting is often involved in costing products or services, analyzing cost behavior, and understanding cost structures to optimize pricing and resource allocation.
5. Budgeting and Planning: Management accountants are heavily involved in the budgeting process, helping managers set financial goals, create budgets, and compare actual performance against budgeted targets.
6. Performance Evaluation: Management accounting provides performance measurement and variance analysis to assess how well the organization and its units are performing relative to established goals and standards.
7. Strategic Decision Making: It assists in strategic planning and analysis, such as assessing potential investments, evaluating business opportunities, and conducting feasibility studies.
8. Customization: Management accounting reports are tailored to the needs of different levels of management, allowing each level to access information relevant to their specific roles and responsibilities.
9. Flexibility: Unlike financial accounting, which follows strict accounting standards, management accounting systems can be adapted to suit the unique needs and requirements of the organization.

Overall, management accounting is a valuable tool for internal decision-makers to optimize resource allocation, improve operational efficiency, and achieve the organization's objectives effectively. It plays a vital role in helping managers navigate complex business environments and make data-driven decisions to stay competitive and successful.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Tax Accounting

What is Tax Accounting?

Tax accounting is a specialized area of accounting that deals with the preparation, calculation, and reporting of taxes for individuals, businesses, and other entities. The main focus of tax accounting is to ensure compliance with tax laws and regulations while optimizing tax efficiency within the legal framework. Tax accountants or tax professionals help individuals and businesses navigate the complex tax landscape and fulfil their tax obligations accurately.

Key aspects of tax accounting include:

1. Tax Preparation: Tax accountants assist individuals and businesses in preparing and filing their tax returns. This involves gathering financial information, analyzing transactions, applying relevant tax laws and deductions, and calculating the amount of tax owed or refund due.
2. Tax Planning: Tax accountants engage in tax planning strategies to legally minimize tax liabilities. They analyze financial situations and advise clients on the most tax-efficient ways to structure transactions, investments, and operations. This may involve timing income and expenses, utilizing tax credits and deductions, and considering the tax implications of various financial decisions.
3. Compliance: Tax accounting focuses on ensuring that taxpayers comply with the applicable tax laws and regulations. This involves staying up-to-date with changes in tax legislation and making sure that tax returns are filed accurately and on time.
4. Representation: Tax accountants may represent individuals or businesses in their dealings with tax authorities. They can handle communications, audits, and appeals on behalf of their clients to resolve tax-related issues.
5. Tax Research: Tax accountants conduct tax research to interpret complex tax laws and regulations, particularly in cases where there may be ambiguity or specific tax planning needs.
6. Cross-border Taxation: For multinational companies and individuals with international financial activities, tax accounting deals with the complexities of cross-border taxation, including issues related to double taxation agreements and transfer pricing.
7. Compliance with Tax Reporting: Tax accounting also covers compliance with various tax reporting requirements, such as the filing of informational returns, providing documentation for tax credits or deductions claimed, and ensuring adherence to tax-related disclosure rules.
8. Tax Strategy for Businesses: For businesses, tax accounting may involve strategic planning for structuring the business entity, considering tax implications related to mergers and acquisitions, and optimizing the allocation of resources to maximize tax efficiency.

Tax accounting is essential for individuals and businesses alike to ensure accurate tax reporting and to

avoid potential penalties or legal issues related to non-compliance with tax laws. It requires a strong understanding of tax regulations, attention to detail, and staying current with changes in tax legislation to provide the best advice and support to clients.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Forensic Accounting

What is Forensic Accounting?

Forensic accounting is a specialized area of accounting that combines accounting, auditing, and investigative skills to examine financial records and transactions for legal purposes. The primary objective of forensic accountants is to uncover and analyze financial evidence to support or refute claims in legal disputes, investigations, or fraud cases. They play a crucial role in detecting and preventing financial fraud, embezzlement, and other financial crimes.

Key aspects of forensic accounting include:

1. Fraud Investigation: Forensic accountants are often engaged to investigate suspected financial fraud within organizations or in cases involving white-collar crimes. They examine financial records, transactions, and accounting systems to identify irregularities and potential instances of fraud.
2. Litigation Support: Forensic accountants provide support in litigation and legal proceedings by quantifying damages, preparing expert reports, and serving as expert witnesses to explain complex financial matters to judges and juries.
3. Dispute Resolution: In cases of business disputes, such as partnership disagreements or contract disputes, forensic accountants may be called upon to analyze financial data and provide an objective assessment of the financial impact of the dispute.
4. Asset Tracing: Forensic accountants may assist in tracing and identifying hidden or misappropriated assets in cases involving divorce, bankruptcy, or recovery of stolen funds.
5. Business Valuation: Valuation of businesses or assets is another area where forensic accountants apply their expertise, especially when disputes arise over the value of a company or its assets.
6. Anti-Money Laundering (AML) and Compliance: Forensic accountants work with regulatory bodies and financial institutions to identify suspicious financial activities and ensure compliance with anti-money laundering regulations.
7. Due Diligence: In mergers and acquisitions, forensic accountants may conduct financial due diligence

to assess the accuracy and completeness of financial information provided by the target company.

8. Cyber Forensics: With the rise of cybercrime, forensic accountants may also be involved in investigating financial data breaches and digital financial fraud.

Forensic accountants must possess strong analytical and investigative skills, a deep understanding of accounting principles, and knowledge of legal and regulatory frameworks. They work closely with law enforcement agencies, lawyers, and other professionals to uncover financial evidence and support legal cases.

It's important to note that forensic accountants maintain independence and objectivity while conducting their investigations, and their findings are typically presented in a clear and impartial manner to support legal proceedings or dispute resolutions. Their work is vital in maintaining financial integrity, promoting transparency, and bringing financial wrongdoers to justice.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

---

What is Auditing?

Auditing is a systematic examination and verification of an organization's financial records, transactions, processes, and internal controls to assess their accuracy, reliability, and compliance with applicable laws, regulations, and accounting principles. The primary objective of an audit is to provide independent assurance to stakeholders that the financial statements and other information presented by the organization are free from material misstatements and fairly represent the true financial position and performance of the entity.

Key aspects of auditing include:

1. Independence: Auditors must be independent and unbiased. They should not have any financial or personal interest in the organization being audited to maintain objectivity and integrity.

2. Assurance: The audit process aims to provide reasonable assurance, not absolute certainty. Auditors gather sufficient and appropriate evidence to form an opinion on the fairness and reliability of the financial statements.

3. Financial Statement Audit: The most common type of audit is the financial statement audit, where auditors examine the financial statements, including the balance sheet, income statement, cash flow statement, and statement of changes in equity.

4. Compliance Audit: Compliance audits assess whether the organization is adhering to specific laws, regulations, or internal policies.
5. Internal Control Evaluation: Auditors review the organization's internal controls, which are procedures and policies designed to safeguard assets, prevent fraud, and ensure accurate financial reporting.
6. External Audit: External audits are conducted by independent auditors from outside the organization. They are typically required for public companies and may also be performed voluntarily by private companies for additional credibility and assurance.
7. Internal Audit: Internal audits are conducted by internal auditors employed by the organization. They focus on evaluating and improving internal controls, risk management, and operational efficiency.
8. Audit Reports: After completing the audit, auditors issue audit reports summarizing their findings and conclusions. The reports include an opinion on the fairness of the financial statements and, if applicable, recommendations for improvement.
9. Materiality: Auditors consider materiality, which refers to the significance of potential misstatements. Material misstatements are those that could influence the economic decisions of users of the financial statements.
10. Professional Standards: Auditors follow professional standards and guidelines established by auditing standard-setting bodies, such as the International Auditing and Assurance Standards Board (IAASB) and the Public Company Accounting Oversight Board (PCAOB).

Auditing plays a critical role in promoting financial transparency, accountability, and trust in the business world. It provides stakeholders, including investors, creditors, regulators, and the public, with confidence in the accuracy of financial information presented by organizations. The audit process helps detect errors, irregularities, or fraud and encourages organizations to maintain strong internal controls and financial reporting practices.

Created with the Standard Edition of HelpNDoc: Easily Add Encryption and Password Protection to Your PDFs

---

What is Non-profit Accounting?

Non-profit accounting is a specialized area of accounting that focuses on the financial management and reporting for nonprofit organizations. Unlike for-profit businesses, non-profit organizations have a different set of financial objectives and face unique accounting challenges due to their mission-driven

nature. The primary goal of nonprofit accounting is to accurately track and report financial information while ensuring transparency and accountability in the use of funds for achieving the organization's charitable or social objectives.

Key features of non-profit accounting include:

1. Fund Accounting: Non-profits typically use fund accounting to track financial resources separately based on their specific purposes or restrictions. Funds are often categorized into unrestricted, temporarily restricted, and permanently restricted funds. This method allows donors and stakeholders to understand how funds are allocated and used for different programs or projects.
2. Revenue Recognition: Non-profits receive funding from various sources, including donations, grants, program service fees, and investment income. Proper revenue recognition is essential to align the revenue with the timing of the related expenses and activities.
3. Donor Reporting: Non-profits must report to their donors and funding sources on how their contributions are utilized. Donor reporting often requires detailed information about the organization's programs, expenses, and outcomes.
4. Compliance with Regulations: Non-profit organizations must comply with specific accounting and reporting regulations, which may vary based on their size, activities, and funding sources. Compliance with tax-exempt status requirements is also crucial for maintaining their tax-exempt status.
5. Transparency and Accountability: Non-profit accounting places a strong emphasis on transparency and accountability to donors, beneficiaries, and the public. Clear financial reporting helps demonstrate how resources are used to fulfil the organization's mission.
6. Cost Allocation: Non-profits may engage in cost allocation to distribute shared expenses among different programs or administrative functions fairly.
7. Budgeting and Resource Management: Budgeting is essential in non-profit accounting to plan and manage resources effectively. Nonprofits need to allocate resources efficiently to ensure sustainability and to fulfil their mission.
8. Tax Reporting: Non-profits must comply with tax regulations applicable to their tax-exempt status, which may include filing Form 990 with the Internal Revenue Service (IRS) in the United States.

Examples of non-profit organizations include charities, foundations, religious organizations, educational institutions, healthcare organizations, and social service agencies. The financial statements for non-profits typically include the statement of financial position (balance sheet), statement of activities (income statement), and statement of cash flows.

Non-profit accounting plays a critical role in maintaining the trust of donors and stakeholders by ensuring that financial resources are utilized effectively to achieve the organization's charitable or social objectives.

It also helps non-profit leaders make informed decisions to optimize their impact and fulfil their missions.

Created with the Standard Edition of HelpNDoc: Don't Let Unauthorized Users View Your PDFs: Learn How to Set Passwords

International Accounting

What is International Accounting?

International accounting is a branch of accounting that deals with the accounting and financial reporting practices across different countries and jurisdictions. It addresses the challenges and complexities arising from the variations in accounting principles, financial reporting standards, and regulations worldwide.

Key aspects of international accounting include:

1. Harmonization and Convergence: With the increasing globalization of business and investment, there is a growing need for harmonization and convergence of accounting standards. International accounting efforts aim to promote consistency and comparability in financial reporting by encouraging countries to adopt or converge with internationally recognized accounting standards, such as the International Financial Reporting Standards (IFRS) issued by the International Accounting Standards Board (IASB).
2. Comparative Financial Reporting: International accounting enables users to compare financial statements of companies from different countries. It involves analyzing financial statements prepared under different accounting frameworks and converting financial results from one currency to another using appropriate exchange rates.
3. Foreign Currency Translation: International accounting deals with the translation of financial statements of multinational companies from their functional currency (the currency of the primary economic environment in which they operate) to the presentation currency used for consolidated financial reporting.
4. Cross-Border Transactions: International accounting considers the accounting treatment of cross-border transactions, including foreign investments, exports, and imports, and the implications of foreign currency exchange fluctuations on financial results.
5. Cultural and Legal Differences: Accounting practices are influenced by cultural norms and legal requirements in each country. International accounting recognizes the need to adapt financial reporting practices to comply with local laws and regulations while maintaining transparency and comparability.

6. Taxation and Transfer Pricing: International accounting also takes into account the impact of different tax systems and transfer pricing regulations on multinational companies' financial reporting and profitability.
7. Multinational Companies: International accounting is particularly relevant for multinational companies that operate in multiple countries and must prepare consolidated financial statements that comply with various accounting standards and regulations.
8. International Financial Reporting Standards (IFRS) : IFRS is a set of accounting standards used or adopted by more than 140 countries, with some countries requiring its use for all or certain types of companies. IFRS aims to provide a common language for financial reporting globally.

International accounting is essential for facilitating cross-border investments, mergers, and acquisitions, as well as enabling global investors and stakeholders to make informed decisions based on comparable and reliable financial information. It helps organizations understand and navigate the accounting complexities of operating in multiple jurisdictions and supports the goal of global financial transparency and consistency.

Created with the Standard Edition of HelpNDoc: Free help authoring environment

Government and Public Sector Accounting

What is Government and Public Sector Accounting?

Government and public sector accounting is a specialized area of accounting that deals with the financial management and reporting of government entities and public sector organizations. It focuses on the unique accounting principles, rules, and regulations applicable to governmental and not-for-profit entities, including federal, state, and local governments, as well as public agencies, educational institutions, and non-governmental organizations (NGOs) operating for public purposes.

Key features of government and public sector accounting include:

1. Fund Accounting: Similar to non-profit accounting, government accounting often uses fund accounting to segregate financial resources based on their sources and purposes. Funds are established to track revenues and expenses related to specific activities, programs, or restrictions.
2. Budgeting and Appropriations: Government accounting emphasizes budgeting as a critical component of financial management. Governments must adhere to budgetary regulations and report on how funds are appropriated and spent in alignment with the approved budgets.
3. Modified Accrual Accounting: Many government entities use modified accrual accounting, a hybrid of

cash and accrual accounting. Under this method, revenues are recognized when measurable and available, while expenses are recognized when incurred.

4. Compliance and Transparency: Governments are subject to stringent regulations and are required to demonstrate transparency in their financial reporting. Accountability to taxpayers and citizens is a significant aspect of government accounting.
5. Government Financial Statements: Government entities prepare comprehensive annual financial reports (CAFRs) that include not only the traditional financial statements but also additional sections such as management's discussion and analysis (MD&A) and notes to the financial statements.
6. Fund Types: Governments have various fund types, including governmental funds (general fund, special revenue funds, capital projects funds, debt service funds), proprietary funds (enterprise funds, internal service funds), and fiduciary funds.
7. Governmental Accounting Standards Board (GASB): The GASB is responsible for establishing accounting and financial reporting standards for governmental entities in the United States. Similarly, other countries may have their own standard-setting bodies for government accounting.
8. Performance Reporting: In addition to financial reporting, government accounting may include performance reporting, which assesses the effectiveness and efficiency of government programs and services.
9. Cost Allocation: Government and public sector accounting may involve allocating costs across various programs and services to assess their true cost and impact on society.
10. Compliance with Legal and Regulatory Requirements: Government entities must comply with specific legal and regulatory requirements related to financial reporting, taxation, and transparency.

Government and public sector accounting is vital for responsible financial management, fiscal planning, and accountability in the use of public funds. It ensures that government organizations operate with financial integrity, fulfil their public service missions, and provide transparent financial information to citizens and stakeholders.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Fund Accounting

What is Fund Accounting?

Fund accounting is a specialized accounting method used by organizations that manage funds or have multiple sources of restricted funding. It is commonly employed by non-profits, government agencies, educational institutions, and investment companies to track and report financial activities related to specific funds, projects, or grants.

The key features of fund accounting include:

1. Segregation of Funds: Each fund is treated as a separate accounting entity, meaning its financial transactions are distinct and do not commingle with other funds.
2. Tracking Restricted Funding: Fund accounting allows organizations to track funds with specific purposes or restrictions, such as donations for a particular project, grant money, or endowment funds.
3. Compliance and Reporting: Fund accounting ensures compliance with legal, regulatory, and donor requirements by accurately recording and reporting financial activities for each fund.
4. Accrual Basis: It typically follows the accrual basis of accounting, where revenues and expenses are recognized when earned or incurred, regardless of cash flow.
5. Inter-fund Transactions: Fund accounting facilitates interfund transactions, which occur when money is transferred between different funds within the same organization.
6. Budgeting: It aids in budget preparation and monitoring, enabling organizations to compare actual financial results against the budget for each fund.
7. Auditing: The separation of funds makes it easier for auditors to verify financial records and ensure the appropriate use of funds.

Fund accounting is essential for transparency and accountability when dealing with diverse funding sources and when there's a need to demonstrate how each fund's resources are utilized. It allows stakeholders to understand how funds are managed and spent, which is particularly crucial for organizations operating with public money or charitable donations.

Who uses Fund Accounting?

Fund accounting is commonly used by various types of organizations that manage funds with specific purposes or restrictions. Some of the key entities that utilize fund accounting include:

1. Non-profit Organizations: Non-profits, including charitable organizations, foundations, religious institutions, and educational institutions, often use fund accounting to manage donations, grants, endowments, and other funding sources dedicated to specific programs or projects.

2. Government Agencies: Government entities, such as municipalities, states, and federal agencies, use fund accounting to manage public funds allocated to specific programs, departments, or projects. This helps ensure accountability and transparency in the use of public funds.
3. Educational Institutions: Schools, colleges, and universities employ fund accounting to manage diverse sources of funding, such as tuition fees, grants, endowments, and donations for various departments, scholarships, or research projects.
4. Investment Companies: Investment firms and mutual funds use fund accounting to track and manage the assets and liabilities of specific funds or portfolios, enabling investors to understand the performance and composition of their investments.
5. Healthcare Organizations: Hospitals, healthcare foundations, and other medical institutions use fund accounting to handle donations, grants, and funds earmarked for medical research, specific healthcare programs, or community health initiatives.
6. Community and Housing Organizations: Community development organizations and housing authorities often use fund accounting to manage funds allocated for affordable housing projects, community development initiatives, or other specific programs.
7. Associations and Clubs: Membership-based organizations, clubs, and professional associations may use fund accounting to track and manage funds received from membership fees, events, sponsorships, or donations for specific purposes.
8. Philanthropic Foundations: Philanthropic foundations and trusts use fund accounting to manage endowments, grants, and donations, ensuring that funds are allocated to projects aligned with their charitable missions.
9. Religious Organizations: Churches, mosques, synagogues, and other religious institutions use fund accounting to manage donations and contributions designated for specific ministries, programs, or community outreach activities.

Fund accounting is essential for these organizations as it allows them to demonstrate responsible stewardship of funds, comply with legal and regulatory requirements, and provide transparency to donors, stakeholders, and beneficiaries about how funds are allocated and used. The segregation of funds and tracking of restricted funding sources help ensure that resources are directed appropriately and in line with the intended purposes.

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

Trust Accounting

What is Trust Accounting?

Trust accounting is a specific type of financial management used primarily by lawyers, law firms, and financial institutions that handle funds on behalf of their clients or beneficiaries. It involves the administration and proper handling of funds held in trust, where one party (the trustee) holds assets or funds on behalf of another party (the beneficiary) for a specific purpose or under specific conditions.

Key elements of trust accounting include:

1. Fiduciary Duty: The trustee has a legal obligation to act in the best interests of the beneficiary and manage the trust's assets prudently and responsibly.
2. Segregation of Funds: Trust accounting requires the clear separation of trust funds from the trustee's personal funds and other business accounts.
3. Accurate Record-Keeping: Trustees must maintain detailed and accurate records of all financial transactions related to the trust, including deposits, withdrawals, investments, and expenses.
4. Reporting and Communication: Trustees are responsible for providing regular reports to the beneficiaries, keeping them informed about the status of the trust and its assets.
5. Compliance and Regulations: Trust accounting must adhere to specific legal and regulatory requirements, which can vary depending on the jurisdiction and the nature of the trust.
6. Interest and Income Allocation: In cases where the trust generates income (e.g., interest from investments), trust accountants must properly allocate this income among the beneficiaries according to the trust's terms.
7. Distribution of Assets: Trust accounting oversees the proper distribution of trust assets according to the terms and conditions specified in the trust agreement.
8. Audit and Accountability: In many cases, trust accounts are subject to audits to ensure compliance with legal and accounting standards and to verify the accuracy of financial records.

Trust accounting is highly important because it involves managing and protecting assets that belong to others, often with significant legal and financial consequences if mismanaged. Proper trust accounting ensures that the trust's purpose is fulfilled, the beneficiaries' rights are respected, and the trustee's actions align with their fiduciary duty. Failure to adhere to trust accounting principles can lead to legal consequences and damage to the reputation of the trustee and the institution involved.

Who uses Trust Accounting?

Trust accounting is used primarily by professionals and organizations that handle funds on behalf of others, often with a fiduciary duty to act in the best interests of the beneficiaries. Some of the key users of

trust accounting include:

1. Lawyers and Law Firms: Lawyers often hold funds in trust for their clients, such as settlement funds, advance payments, or funds related to real estate transactions. Trust accounting ensures that these funds are managed separately from the lawyer's own funds and are appropriately disbursed to the clients when needed.
2. Financial Institutions: Banks and other financial institutions may act as trustees for various types of trusts, including revocable and irrevocable trusts, and manage the assets and funds held in trust for the beneficiaries.
3. Estate Administrators: Executors or administrators of estates often use trust accounting to manage the assets and funds of the deceased person's estate and distribute them to the rightful heirs and beneficiaries.
4. Investment Firms: Investment companies or asset management firms may manage trusts on behalf of individuals or entities, ensuring proper investment of trust funds according to the terms of the trust.
5. Retirement Plan Administrators: Companies or financial institutions responsible for administering retirement plans, such as 401(k) plans, may use trust accounting to handle the plan's assets on behalf of plan participants and beneficiaries.
6. Non-profit Organizations: Non-profits may manage trust funds donated by individuals or organizations, with specific purposes or conditions attached to their use. Trust accounting ensures that these funds are used in accordance with the donors' intentions.
7. Court-Appointed Guardians: Guardianships often involve managing funds for minors or incapacitated individuals. Trust accounting is used to oversee and account for the financial transactions related to the protected person's assets.
8. Charitable Foundations: Philanthropic foundations may utilize trust accounting to manage endowments and charitable trusts, ensuring that the funds are prudently invested and distributed for charitable purposes.
9. Family Trusts: Families may establish trusts to manage their assets and wealth, provide for future generations, or support charitable causes. Trust accounting helps in administering and distributing these assets according to the trust's provisions.

Trust accounting is crucial in all these cases to maintain accurate records, ensure proper handling of funds, and fulfil fiduciary responsibilities. It provides transparency to beneficiaries and other stakeholders, giving them confidence that their interests are being protected and that the trust's assets are being managed appropriately.

What is the common accounts used for Trusts in a Chart of Accounts?

The accounts used for trusts in a Chart of Accounts can vary depending on the specific nature and purpose of the trust, as well as the reporting requirements and preferences of the organization or individual managing the trust. However, here are some common accounts that are typically used in the Chart of Accounts for trusts:

1. Trust Assets:
    - Cash - This account represents the cash held in the trust.
    - Investments - This account includes various types of investments held by the trust, such as stocks, bonds, mutual funds, real estate, etc.
    - Receivables - Any amounts due to the trust, such as interest, dividends, or loan repayments.
2. Trust Liabilities:
    - Payables - Any amounts owed by the trust, such as expenses or fees.
    - Trust Beneficiaries' Accounts - Individual accounts for each beneficiary, showing their entitlements or distributions from the trust.
3. Income and Expenses:
    - Income - This account records all income earned by the trust, such as interest, dividends, rental income, etc.
    - Expenses - This account includes all expenses related to managing the trust, such as trustee fees, legal fees, administrative costs, etc.
4. Gains and Losses:
    - Capital Gains/Losses - This account tracks gains and losses realized from the sale of investments or assets.
    - Unrealized Gains/Losses - For investments that have not been sold, this account records changes in their market value.
5. Distribution Accounts:
    - Principal Distribution - This account represents distributions made from the principal of the trust.
    - Income Distribution - This account represents distributions made from the income earned by

the trust.

6. Reserves and Designations:
    - Accumulated Income - This account shows the cumulative income earned but not distributed to beneficiaries.
    - Reserve for Contingencies - An account used to set aside funds for unforeseen circumstances or future needs of the trust.
7. Trustee's Fees:
    - Trustee's Compensation - This account records fees or compensation paid to the trustee for managing the trust.

It's important to note that the Chart of Accounts for trusts can be more extensive and may include additional accounts based on the complexity and unique features of the trust. Moreover, the Chart of Accounts should be customized to adhere to accounting principles and any specific legal or regulatory requirements applicable to trusts in the respective jurisdiction.

Is there any specific information that is required to include in documents such as invoices, etc. for Trusts?

Yes, when preparing documents such as invoices for trusts, there are specific pieces of information that should be included to ensure accuracy, compliance, and transparency. The required information may vary depending on the jurisdiction, the type of trust, and the specific circumstances, but some common details to include in invoices for trusts are:

1. Trust Name and Identification: Clearly state the name of the trust and any unique identification number or reference assigned to the trust.
2. Trustee Information: Include the name and contact details of the trustee or trustees responsible for managing the trust.
3. Beneficiary Information: If applicable, mention the names of the beneficiaries entitled to receive distributions from the trust.
4. Invoice Date: Clearly indicate the date the invoice was issued.
5. Invoice Number: Assign a unique invoice number to each invoice for proper tracking and reference.
6. Description of Goods or Services: Provide a detailed description of the goods sold or services rendered to the trust.
7. Quantity and Unit Price: Include the quantity of goods or services provided and the unit price per

item or service.

8. Total Amount: Calculate and display the total amount due for the goods or services provided.
9. Payment Terms: Outline the payment terms, including the due date for payment and any applicable discounts or penalties for early or late payment.
10. Payment Instructions: Provide information on how payments should be made, such as accepted payment methods and the designated bank account for transfers.
11. Tax Information: If applicable, include any taxes or duties that apply to the invoice, along with the relevant tax identification numbers.
12. Legal and Compliance Information: Depending on the jurisdiction, there may be specific legal or regulatory requirements for invoices issued to trusts. Ensure compliance with any relevant regulations or legal obligations.
13. Trust Accounting Details: If the invoice pertains to specific trust expenses or distributions, clearly indicate the trust account numbers or designations related to the transaction.
14. Itemization of Expenses: If the invoice includes various expenses, provide an itemized breakdown to show how the total amount is derived.

It's essential to maintain clear and accurate records of all financial transactions related to the trust, including invoices and payments received. These records help provide transparency and accountability in trust management, which is critical for fulfilling the trustee's fiduciary duty and ensuring compliance with legal and regulatory requirements. Always consult with a legal or financial professional to ensure that the invoices issued for trusts meet all necessary requirements and adhere to applicable laws and guidelines.

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Accounting frameworks

What is an accounting framework?

An accounting framework refers to a set of rules, principles, and guidelines that govern the preparation and presentation of financial statements. Accounting frameworks provide a standardized framework for financial reporting, ensuring consistency and comparability in financial statements across different companies and jurisdictions. Examples of accounting frameworks include Generally Accepted Accounting Principles (GAAP) and International Financial Reporting Standards (IFRS).

Is IFRS for SMEs also an accounting framework?

The IFRS for SMEs (International Financial Reporting Standards for Small and Medium-sized Entities) is considered an accounting framework. It is a simplified set of accounting standards specifically designed for small and medium-sized entities (SMEs) that do not have public accountability.

IFRS for SMEs provides a comprehensive set of accounting principles, rules, and guidelines that govern the preparation and presentation of financial statements for SMEs. It covers topics such as recognition, measurement, presentation, and disclosure of various financial elements including assets, liabilities, equity, income, expenses, and cash flows. The aim of IFRS for SMEs is to provide a less complex and more cost-effective financial reporting framework for SMEs compared to the full International Financial Reporting Standards (IFRS) framework.

The adoption of IFRS for SMEs enables SMEs to prepare their financial statements in a consistent and transparent manner, facilitating comparability and understanding of their financial performance and position. It helps SMEs meet the needs of various stakeholders, such as investors, lenders, and regulatory authorities, by providing relevant and reliable financial information.

It's important to note that the application of IFRS for SMEs is subject to local regulations and requirements in each jurisdiction. Some jurisdictions may have made modifications or amendments to the standard to suit their specific legal and regulatory frameworks.

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

Accounting standards - GAAP vs IFRS

What is the collective name for GAAP and IFRS?

The collective name for Generally Accepted Accounting Principles (GAAP) and International Financial Reporting Standards (IFRS) is "*Accounting Standards*." These are the guidelines and rules that companies and organizations follow when preparing financial statements and reports.

Is GAAP and IFRS applicable to Small businesses?

GAAP (Generally Accepted Accounting Principles) and IFRS (International Financial Reporting Standards) are typically used by larger, publicly traded companies that are required to follow certain accounting standards for financial reporting purposes. However, small businesses may also benefit from using these

accounting standards, particularly if they plan to seek financing or investments from outside sources.

While there are no legal requirements for small businesses to use GAAP or IFRS, using these standards can provide several benefits. First, they provide a consistent framework for financial reporting, which can be useful for comparing financial performance across different companies or industries. Second, using GAAP or IFRS can help small businesses attract investors or lenders who may prefer to work with companies that use recognized accounting standards. Finally, using these standards can help small businesses identify and address financial issues, which can be important for long-term success.

That being said, small businesses may find that using GAAP or IFRS can be costly and time-consuming, particularly if they do not have dedicated accounting staff. In these cases, it may be more practical for small businesses to use simplified accounting methods or standards that are tailored to their specific needs. Ultimately, the decision to use GAAP or IFRS will depend on the specific circumstances of each small business, including their industry, size, and financial reporting needs.

Can accounting software be configured to accommodate both GAAP and IFRS in different databases?

Yes, many accounting software systems can be configured to accommodate both GAAP and IFRS in different databases. This allows companies to maintain separate financial records for each standard, ensuring that they are in compliance with the appropriate accounting rules and regulations. However, it is important to note that while some accounting software may be able to support multiple accounting standards, it may not be able to do so with equal functionality or accuracy. Companies should carefully evaluate their accounting software options and work with their software providers to ensure that their chosen system can accommodate both GAAP and IFRS accounting needs.

What is the main options to consider whether to use GAAP or IFRS?

When considering whether to use GAAP (Generally Accepted Accounting Principles) or IFRS (International Financial Reporting Standards), companies should consider several factors:

1. Geographic location: Companies that operate primarily in the United States may find it more advantageous to use GAAP, while companies that operate globally or have international investors may find it more advantageous to use IFRS.
2. Regulatory requirements: Companies should consider the regulatory requirements of their industry and the countries in which they operate. Some industries may require the use of a specific accounting standard, and certain countries may have specific rules and regulations regarding financial reporting.

3. Investor preferences: Companies should consider the preferences of their investors when choosing an accounting standard. Some investors may prefer GAAP, while others may prefer IFRS.
4. Complexity of transactions: Companies with complex transactions may find it easier to use IFRS, as it is designed to handle more complex accounting issues. However, for simpler transactions, GAAP may be more appropriate.
5. Access to talent: Companies should consider the availability of accounting talent that is trained in either GAAP or IFRS. Depending on the location and industry, one standard may be more prevalent than the other, making it easier to find qualified accounting professionals.

Ultimately, the decision to use GAAP or IFRS will depend on the specific needs and requirements of each company. It is important to carefully evaluate the options and consult with accounting professionals to determine the best course of action.

Which countries use GAAP and which countries use IFRS?

The United States uses Generally Accepted Accounting Principles (GAAP), while many other countries around the world, including most of Europe, Australia, and Canada, use International Financial Reporting Standards (IFRS).
However, some countries may allow companies to choose between using GAAP or IFRS, while others may adopt a modified version of one or both of these standards. It's important to note that accounting standards may also vary based on the industry or sector in which a company operates.

GAAP and IFRS and Tax?

GAAP (Generally Accepted Accounting Principles) and IFRS (International Financial Reporting Standards) are accounting standards used by companies and organizations to prepare financial statements and reports. These standards are focused on financial reporting and disclosure and do not necessarily directly affect tax calculations.

Tax laws, on the other hand, are regulations and rules that govern the assessment and collection of taxes. Tax laws vary by country and can differ from accounting standards. Companies and organizations must comply with both tax laws and accounting standards separately.

While there may be some overlap between accounting standards and tax laws, it is important to understand that they are distinct areas of regulation with different purposes and requirements.

Does the USA use IFRS or GAAP?

In the United States, the generally accepted accounting principles (GAAP) are used for accounting and financial reporting. While the International Financial Reporting Standards (IFRS) are widely used around the

world, including in many developed economies, they are not used in the United States as the primary accounting standard.

However, the Securities and Exchange Commission (SEC) has allowed foreign companies that are listed in the U.S. to prepare their financial statements using IFRS since 2007. In addition, some U.S. companies that have operations in other countries may also prepare their financial statements using IFRS to better align with the reporting standards of their foreign operations.

Overall, while IFRS is not used as the primary accounting standard in the United States, it may be used by some foreign companies listed on U.S. exchanges or by U.S. companies with significant foreign operations.

Does Canada use IFRS or GAAP?

In Canada, both IFRS and GAAP are used in accounting and financial reporting.

Publicly accountable enterprises, such as publicly traded companies and some financial institutions, are required to use IFRS for their financial statements. This requirement was phased in between 2011 and 2014.

Private enterprises, which are typically smaller businesses that are not publicly traded, have the option to use either IFRS or Accounting Standards for Private Enterprises (ASPE), which is a Canadian GAAP standard.

Not-for-profit organizations also have the option to use either IFRS or the Accounting Standards for Not-for-Profit Organizations (ASNFPO), which is a Canadian GAAP standard specifically designed for the not-for-profit sector.

Overall, while both IFRS and GAAP are used in Canada, the specific standard used will depend on the type of organization and its reporting requirements.

Does the United Kingdom use IFRS or GAAP?

In the United Kingdom, both IFRS and UK GAAP (Generally Accepted Accounting Practice) are used in accounting and financial reporting, although there have been recent changes to this.

Historically, UK GAAP has been the standard used by most UK companies for financial reporting, but this has changed in recent years. In 2015, the Financial Reporting Council (FRC) introduced a new standard called FRS 102, which is based on the IFRS framework but tailored specifically for UK companies. FRS 102 replaced most of the previous UK GAAP standards.

In addition, some UK companies are required to use IFRS. Publicly traded companies listed on the London Stock Exchange (LSE) are required to use IFRS for their consolidated financial statements, and some other companies may choose to use IFRS voluntarily.

Overall, while both UK GAAP and IFRS are used in the UK, the specific standard used will depend on the

type of company and its reporting requirements.

Does South Africa use IFRS or GAAP?

In South Africa, both IFRS (International Financial Reporting Standards) and SA GAAP (South African Generally Accepted Accounting Practice) are used in accounting and financial reporting.

For companies that are listed on the Johannesburg Stock Exchange (JSE), IFRS is required for their financial statements. In addition, companies that are subsidiaries of foreign entities or have significant foreign operations may also be required to use IFRS.

For other companies, SA GAAP is the most commonly used standard for financial reporting. SA GAAP is similar to IFRS in many respects, but there are some differences between the two standards. The Companies Act of South Africa requires that all companies must prepare financial statements that are compliant with either IFRS or SA GAAP.

Overall, while both IFRS and SA GAAP are used in South Africa, the specific standard used will depend on the type of company and its reporting requirements.

What is the structure of GAAP Chart of accounts?

The structure of the GAAP (Generally Accepted Accounting Principles) chart of accounts is a standardized system that categorizes and organizes financial transactions for reporting purposes. The chart of accounts is typically broken down into five main categories:

1. Assets: This category includes all items that a company owns and has value, such as cash, accounts receivable, inventory, and property.
2. Liabilities: This category includes all debts and obligations that a company owes, such as accounts payable, loans, and taxes.
3. Equity: This category represents the residual interest in the assets of the company after all liabilities have been paid off. It includes items such as capital stock, retained earnings, and dividends.
4. Revenues: This category includes all income earned by the company, such as sales revenue, service revenue, and interest income.
5. Expenses: This category includes all costs incurred by the company in the process of generating revenue, such as salaries and wages, rent, and utilities.

Within each category, accounts are further organized by subcategories and sub-accounts to provide more detail and specificity. This allows for accurate tracking and reporting of financial transactions and enables companies to make informed decisions based on their financial performance.

What is the structure of IFRS Chart of accounts?

IFRS (International Financial Reporting Standards) does not prescribe a specific chart of accounts structure. Instead, it provides general guidelines and principles that companies can use to develop their own chart of accounts that is relevant and useful for their specific industry and business operations.

However, there are some general principles that are commonly used in developing an IFRS-compliant chart of accounts. These principles include:

1. Classification by type of account: Similar to GAAP, accounts are typically categorized by asset, liability, equity, revenue, and expense.
2. Grouping by business function: Accounts are grouped according to their function within the business, such as sales, marketing, production, and finance.
3. Hierarchical structure: Accounts are arranged in a hierarchical structure, with the most general accounts at the top and more specific accounts at the bottom.
4. Standardization: Accounts are standardized across the organization, with consistent naming conventions and numbering schemes used to avoid confusion and facilitate reporting.

Overall, the structure of an IFRS chart of accounts will vary depending on the needs and requirements of the individual company, but it will generally adhere to these general principles to ensure accurate and effective financial reporting.

Is there an example of IFRS Chart of accounts?

There is no standardized example of an IFRS (International Financial Reporting Standards) chart of accounts as it is up to each individual company to design their own chart of accounts that best fits their business operations and industry. However, an example of a possible IFRS chart of accounts structure could be:

- Assets
    - Non-current assets
        - Property, plant, and equipment
        - Intangible assets
        - Investment properties
        - Other non-current assets
    - Current assets

        - Inventories
        - Trade and other receivables
        - Cash and cash equivalents
        - Other current assets
- Liabilities
    - Non-current liabilities
        - Borrowings
        - Provisions
        - Deferred tax liabilities
        - Other non-current liabilities
    - Current liabilities
        - Trade and other payables
        - Borrowings
        - Provisions
        - Current tax liabilities
        - Other current liabilities
- Equity
    - Share capital
    - Retained earnings
    - Other reserves
- Income
    - Revenue
    - Gains
- Expenses
    - Cost of sales
    - Employee benefits

- Depreciation and amortization
- Impairment losses
- Finance costs
- Other expenses

This is just an example and the specific accounts and subcategories used will vary depending on the needs and operations of each company.

Is there an example of GAAP Chart of accounts?

Yes, there is an example of a GAAP (Generally Accepted Accounting Principles) chart of accounts. While the specific accounts and categories may vary depending on the business and industry, a typical GAAP chart of accounts may include:

- Assets
  - Current assets
    - Cash and cash equivalents
    - Accounts receivable
    - Inventory
    - Prepaid expenses
  - Non-current assets
    - Property, plant, and equipment
    - Intangible assets
    - Investments
    - Other non-current assets
- Liabilities
  - Current liabilities
    - Accounts payable
    - Short-term loans
    - Accrued expenses
    - Unearned revenue

    - Non-current liabilities
        - Long-term debt
        - Pension obligations
        - Deferred tax liabilities
- Equity
    - Common stock
    - Additional paid-in capital
    - Retained earnings
- Revenue
    - Sales revenue
    - Other revenue
- Expenses
    - Cost of goods sold
    - Selling, general, and administrative expenses
    - Research and development expenses
    - Interest expenses
    - Income tax expenses

This is just an example and the specific accounts and subcategories used will vary depending on the needs and operations of each company.

Is there a common example for a chart of accounts of a small businesses?

Yes, there is a common example of a chart of accounts for a small business, which typically includes the following accounts:

- Assets
    - 1000 - Cash on hand
    - 1010 - Cash in bank

- 1020 - Accounts receivable
- 1030 - Inventory
- 1050 - Prepaid expenses

- Liabilities
  - 2000 - Accounts payable
  - 2010 - Accrued expenses
  - 2050 - Customer deposits
- Equity
  - 3000 - Owner's equity
  - 3100 - Retained earnings
- Income
  - 4000 - Sales revenue
  - 4050 - Interest income
- Expenses
  - 5000 - Cost of goods sold
  - 5050 - Rent expense
  - 5100 - Salaries and wages
  - 5150 - Supplies expense
  - 5200 - Telephone and internet
  - 5250 - Advertising and promotion
  - 5300 - Professional fees
  - 5350 - Utilities expense
  - 5400 - Insurance expense
  - 5450 - Depreciation expense
  - 5500 - Taxes and licences

This is just an example, and a small business can customize their chart of accounts to best fit their business

needs and operations.

Are there any recommendations when to use sub-accounts in the chart of accounts?

There are several recommendations for when to use sub-accounts in a chart of accounts:

1. To provide more detail: Sub-accounts can be used to provide more detailed information about a specific account. For example, a company might use a sub-account to track expenses for a specific department or project within a larger expense account.
2. To track multiple locations or divisions: If a company has multiple locations or divisions, sub-accounts can be used to track financial information separately for each location or division. This can help management make more informed decisions about allocating resources and identifying areas for improvement.
3. To comply with regulatory requirements: In some industries, regulatory bodies may require companies to track financial information in a specific way. Sub-accounts can be used to ensure that financial data is recorded and reported in accordance with these requirements.
4. To facilitate financial analysis: Sub-accounts can make it easier to analyze financial data by providing more granular information. For example, a company might use sub-accounts to track sales by product line, making it easier to identify which products are driving revenue growth.
5. To simplify financial reporting: Sub-accounts can be used to simplify financial reporting by grouping related accounts together. For example, a company might use sub-accounts to group all travel-related expenses together, making it easier to prepare financial statements and tax returns.

Overall, the decision to use sub-accounts in a chart of accounts should be based on the specific needs of the organization. While sub-accounts can provide more detail and facilitate financial analysis, they can also add complexity to the chart of accounts and make it more difficult to maintain.

What is the correct spelling for subaccounts (sub-accounts or sub accounts)?

Both "sub-accounts" and "sub accounts" are considered correct spellings, and which one to use may depend on the style guide being followed or personal preference.

Some style guides, such as The Chicago Manual of Style, recommend using a hyphen to join two words that function as a single adjective, such as "sub-" and "accounts". In this case, "sub-accounts" would be the preferred spelling.

Other style guides, such as the Associated Press Stylebook, generally recommend not using a hyphen for compound words that are frequently used together and easily understood, such as "sub accounts". In this case, "sub accounts" would be the preferred spelling.

Ultimately, it is important to be consistent within a document or organization when using spelling and punctuation for compound words like "sub-accounts" or "sub accounts".

What is the difference between Stock and Inventory in general and in specific countries?

In general, "*stock*" and "*inventory*" are often used interchangeably to refer to the goods or materials a company has on hand for sale or production. However, in some specific countries, there may be legal or accounting distinctions between the two terms.

In the United States, for example, "inventory" generally refers to the raw materials, work-in-progress goods, and finished goods a company has on hand for sale. "Stock" is a broader term that can also refer to ownership shares in a company or securities traded on a stock exchange.

In the United Kingdom, the term "*stock*" is commonly used to refer to the goods a company has on hand for sale, while "*inventory*" is a more general term that can include equipment, property, and other assets.

In some other countries, such as Canada and Australia, the terms "*inventory*" and "*stock*" are often used interchangeably.

It's important to note that the specific definitions of "*stock*" and "*inventory*" can vary depending on the context and industry. In general, however, both terms refer to the goods or materials a company has on hand, with "*inventory*" typically used in accounting contexts and "*stock*" used more broadly.

Where does VAT/GST/Sales tax fit in the GAAP Chart of accounts and Financial categories?

Value Added Tax (VAT), Goods and Services Tax (GST), and Sales Tax are types of taxes that are applied to goods and services at different stages of production and distribution.

In the GAAP (Generally Accepted Accounting Principles) Chart of Accounts, VAT, GST, and Sales Tax are typically recorded as part of the "*Taxes Payable*" account, which falls under the "*Liabilities*" category in the financial statements.

When a company makes a sale and collects VAT, GST, or Sales Tax from its customers, it is essentially acting as an agent for the government and holding the tax on behalf of the tax authority. The amount collected is recorded as a liability in the "*Taxes Payable*" account.

When the company remits the collected tax to the tax authority, the " *Taxes Payable*" account is reduced, and the "*Cash*" account is increased by the same amount.

It's worth noting that the specific account names and categories in a Chart of Accounts may vary between companies and industries, but the general principles for recording taxes in financial statements are the same.

Where does VAT/GST/Sales tax fit in the IFRS Chart of accounts and Financial categories?

Under International Financial Reporting Standards (IFRS), VAT/GST/Sales tax would be classified as indirect taxes and recorded as part of the "*Current Liabilities*" category in the financial statements.

Similar to GAAP, when a company makes a sale and collects VAT/GST/Sales tax, it is recorded as a liability in the "*Taxes Payable*" account. When the tax is remitted to the tax authority, the liability is reduced and the "*Cash*" account is increased by the same amount.

However, it's important to note that the IFRS Chart of Accounts may have some differences compared to the GAAP Chart of Accounts, such as in account naming and categorization. Nevertheless, the basic accounting principles and financial reporting requirements for recording taxes under IFRS are similar to those under GAAP.

Which accounts is structured in the Capital or Equity section of the Financial categories?

The Capital or Equity section of the financial categories typically includes accounts that represent the ownership interests in a company. These accounts may include:

1. Common stock: This account represents the portion of the company that is owned by its shareholders.
2. Preferred stock: This account represents a type of stock that typically pays a fixed dividend and has priority over common stock in the event of liquidation.
3. Retained earnings: This account represents the accumulated profits of the company that have not been distributed to shareholders as dividends.
4. Additional paid-in capital: This account represents the amount of money that shareholders have invested in the company in excess of the par value of the stock.
5. Treasury stock: This account represents shares of the company's own stock that have been repurchased and are held by the company.

Accumulated other comprehensive income: This account represents gains and losses that have not yet been recognized in the income statement, such as unrealized gains or losses on investments.

Which accounts is structured in the Capital or Equity section of the Financial categories of a sole proprietorship or partnership?

The Capital or Equity section of the financial categories for a sole proprietorship or partnership typically includes accounts that represent the ownership interests of the owner(s) or partner(s). These accounts may include:

1. Owner's capital account: This account represents the owner's investment in the business, including initial capital contributions and any additional investments made over time.
2. Drawing account: This account represents any withdrawals made by the owner or partners for personal use, which reduces the amount of capital in the business.
3. Partner's capital account: This account represents the investment made by each partner in the business, including initial capital contributions and any additional investments made over time.
4. Partner's drawing account: This account represents any withdrawals made by each partner for personal use, which reduces the amount of capital in the business.
5. Profit and loss sharing accounts: These accounts represent the distribution of profits or losses among the partners, based on their ownership percentage or agreement.
6. Retained earnings: This account represents the accumulated profits of the business that have not been distributed to the owner(s) or partner(s) as withdrawals.

Where does VAT/GST/Sales tax fit in the GAAP Chart of accounts and Financial categories?

Value Added Tax (VAT), Goods and Services Tax (GST), and Sales Tax are types of taxes that are applied to goods and services at different stages of production and distribution.

In the GAAP (Generally Accepted Accounting Principles) Chart of Accounts, VAT, GST, and Sales Tax are typically recorded as part of the "Taxes Payable" account, which falls under the "Liabilities" category in the financial statements.

When a company makes a sale and collects VAT, GST, or Sales Tax from its customers, it is essentially acting as an agent for the government and holding the tax on behalf of the tax authority. The amount collected is recorded as a liability in the "Taxes Payable" account.

When the company remits the collected tax to the tax authority, the "Taxes Payable" account is reduced,

and the "Cash" account is increased by the same amount.

It's worth noting that the specific account names and categories in a Chart of Accounts may vary between companies and industries, but the general principles for recording taxes in financial statements are the same.

Where does VAT/GST/Sales tax fit in the IFRS Chart of accounts and Financial categories?

Under International Financial Reporting Standards (IFRS), VAT/GST/Sales tax would be classified as indirect taxes and recorded as part of the "Current Liabilities" category in the financial statements.

Similar to GAAP, when a company makes a sale and collects VAT/GST/Sales tax, it is recorded as a liability in the "Taxes Payable" account. When the tax is remitted to the tax authority, the liability is reduced and the "Cash" account is increased by the same amount.

However, it's important to note that the IFRS Chart of Accounts may have some differences compared to the GAAP Chart of Accounts, such as in account naming and categorization. Nevertheless, the basic accounting principles and financial reporting requirements for recording taxes under IFRS are similar to those under GAAP.

For Fixed assets and depreciation what is the suggested structure in the Chart of Accounts for GAAP?

For fixed assets and depreciation, the suggested structure in the Chart of Accounts for GAAP includes the following accounts:

1. Fixed Assets: This account is used to record the initial cost of acquiring a fixed asset, such as a building, equipment, or vehicle. The balance of this account represents the net book value of fixed assets that have not yet been depreciated.
2. Accumulated Depreciation: This account is used to record the total amount of depreciation expense that has been recognized for fixed assets. The balance of this account represents the cumulative amount of depreciation that has been charged against fixed assets over time.
3. Depreciation Expense: This account is used to record the periodic depreciation expense for fixed assets. The balance of this account represents the amount of depreciation expense that has been recognized during a specific period, such as a month or year.
4. Gain/Loss on Disposal of Fixed Assets: This account is used to record any gains or losses that result from the sale or disposal of fixed assets. The balance of this account represents the difference between the net book value of the fixed asset at the time of disposal and the amount of cash received

from the sale.

It's important to note that the specific accounts used in the Chart of Accounts for fixed assets and depreciation may vary depending on the industry and the organization's specific needs. However, the above accounts are generally recommended as a starting point for recording and tracking fixed assets and depreciation under GAAP.

Fixed assets book value and Fixed assets at cost and Accumulated depreciation in GAAP?

Fixed assets book value, fixed assets at cost, and accumulated depreciation are all important concepts in GAAP accounting for fixed assets.

- Fixed assets at cost refers to the total amount of money spent to acquire a fixed asset, including any costs associated with acquiring or installing the asset. This includes the purchase price, delivery charges, installation fees, and any other costs directly related to acquiring the asset.
- Accumulated depreciation, on the other hand, is the total amount of depreciation expense that has been recognized for the fixed asset over its useful life. Depreciation is the method used to spread the cost of a fixed asset over its useful life, and is recognized as an expense on the income statement.
- Fixed assets book value is calculated by subtracting accumulated depreciation from the fixed assets at cost. This represents the net book value of the fixed asset, or the amount that the asset is currently worth on the company's balance sheet.

For example, suppose a company purchased a machine for $50,000 and expected it to last for 10 years, with no residual value at the end of its useful life. Using straight-line depreciation, the company would recognize $5,000 in depreciation expense each year, until the accumulated depreciation reached $50,000 after 10 years.

At the end of year 5, the accumulated depreciation would be $25,000 ($5,000 x 5 years). The fixed asset book value would be $25,000 ($50,000 - $25,000), representing the current value of the asset on the company's balance sheet.

Overall, fixed assets book value, fixed assets at cost, and accumulated depreciation are important components of GAAP accounting for fixed assets, and are used to accurately record and report the value and depreciation of fixed assets over time.

Is there a difference in Depreciation and Amortization?

Yes, there is a difference between depreciation and amortization.

Depreciation is the method used to allocate the cost of tangible assets, such as buildings, machinery, and vehicles, over their useful lives. This means that the cost of the asset is spread out over a number of years, with a portion of the cost being recognized as an expense each year.

Amortization, on the other hand, is the method used to allocate the cost of intangible assets, such as patents, trademarks, and copyrights, over their useful lives. Like depreciation, the cost of the intangible asset is spread out over a number of years, with a portion of the cost being recognized as an expense each year.

Both depreciation and amortization are recognized as expenses on the income statement, and reduce the value of the asset on the balance sheet over time. The main difference between the two is that depreciation applies to tangible assets, while amortization applies to intangible assets.

It's important to note that the useful life of an asset and the method of depreciation or amortization used can vary depending on the asset and the organization's accounting policies. In general, straight-line depreciation and straight-line amortization are the most commonly used methods for calculating the annual depreciation or amortization expense for an asset.

Is depreciation the correct term to use for Land and Buildings, or should amortization be used?

Depreciation is the correct term to use for buildings, while land is not depreciated. This is because land is considered to have an indefinite useful life and, therefore, does not decrease in value over time.

On the other hand, buildings are subject to wear and tear and become less valuable over time. Depreciation is a method of allocating the cost of a building over its useful life, reflecting the decrease in value due to factors such as age, wear and tear, and obsolescence.

Amortization, on the other hand, is used for intangible assets such as patents, copyrights, and trademarks. It is a similar concept to depreciation but relates specifically to the allocation of the cost of intangible assets over their useful life.

In summary, while depreciation is the correct term to use for buildings, amortization is used for intangible assets such as patents and copyrights.

Do we use sub-accounts to record fixed assets in GAAP?

Yes, sub-accounts can be used to record fixed assets in GAAP. Using sub-accounts can provide more detail and allow for better tracking of fixed assets.

For example, a company might use sub-accounts to record fixed assets by category or location. This would allow the company to track the value and depreciation of each asset separately, and would make it

easier to identify any issues or discrepancies.

In addition to sub-accounts for fixed assets, other sub-accounts may also be used in the chart of accounts for related expenses, such as maintenance and repair costs, property taxes, and insurance premiums.

Overall, the decision to use sub-accounts for fixed assets in GAAP should be based on the specific needs of the organization and the level of detail required for financial reporting and analysis.

Is there any examples of long-term adjustments in GAAP and IFRS?

Yes, there are several examples of long-term adjustments that may be required under both GAAP and IFRS. Here are a few examples:

1. Long-term investments: If a company has investments in securities or other assets that are expected to be held for more than one year, they may need to be revalued periodically to reflect changes in their fair value. This is required under both GAAP and IFRS.
2. Pension and post-retirement benefits: Companies with defined benefit pension plans or other post-retirement benefit plans may need to make long-term adjustments to account for changes in the plan's assumptions, such as changes in interest rates or life expectancy. This is required under both GAAP and IFRS.
3. Goodwill impairment: If a company acquires another company and pays more than the fair value of its identifiable assets and liabilities, the excess is recorded as goodwill. Under both GAAP and IFRS, the company must periodically test for impairment of the goodwill, which may result in a long-term adjustment.
4. Asset impairments: If the value of a company's assets has declined and it is no longer recoverable, the company may need to recognize an impairment loss. This may include long-lived assets, such as property, plant, and equipment, as well as intangible assets. This is required under both GAAP and IFRS.
5. Restructuring charges: If a company incurs costs associated with a restructuring, such as severance payments or asset write-downs, these costs may need to be recognized as a long-term adjustment under both GAAP and IFRS.

Overall, long-term adjustments are an important part of GAAP and IFRS accounting, and are necessary to ensure that financial statements accurately reflect a company's financial position and performance over time.

Is there any examples of short-term adjustments in GAAP and IFRS?

Yes, there are several examples of short-term adjustments that may be required under both GAAP and IFRS. Here are a few examples:

1. Accruals: If a company has incurred expenses but has not yet paid them, it may need to record an accrual. This is a short-term adjustment that ensures that expenses are recognized in the period in which they are incurred, even if the actual payment is made later.
2. Prepayments: If a company has paid for goods or services in advance, it may need to record a prepayment. This is a short-term adjustment that ensures that the expenses are recognized in the period in which the goods or services are actually received.
3. Provision for bad debts: If a company expects that it will not be able to collect all of the amounts owed to it by customers, it may need to record a provision for bad debts. This is a short-term adjustment that reflects the estimated amount of uncollectible accounts receivable.
4. Inventory valuation: If the value of a company's inventory has declined, the company may need to record an adjustment to reflect the lower value. This is a short-term adjustment that ensures that the value of the inventory is reported accurately on the balance sheet.
5. Deferred revenue: If a company has received payment for goods or services that it has not yet delivered, it may need to record a deferred revenue liability. This is a short-term adjustment that ensures that the revenue is recognized in the period in which the goods or services are actually delivered.

Overall, short-term adjustments are an important part of GAAP and IFRS accounting, and are necessary to ensure that financial statements accurately reflect a company's financial position and performance in the current period.

Where do these examples of short-term adjustments fit in the Chart of accounts for GAAP and IFRS?

The examples of short-term adjustments can fit into various accounts in the Chart of Accounts for both GAAP and IFRS, depending on the nature of the adjustment. Here are some examples:

1. Accruals: These adjustments would typically be recorded in a liability account, such as "*Accrued Expenses*" or "*Accrued Liabilities*".
2. Prepayments: These adjustments would typically be recorded in an asset account, such as "*Prepaid Expenses*" or "*Deferred Charges*".

3. Provision for bad debts: These adjustments would typically be recorded as an expense, such as "Bad Debt Expense," and a contra-asset account, such as "*Allowance for Doubtful Accounts*".
4. Inventory valuation: These adjustments would typically be recorded in an inventory account, such as "*Raw Materials Inventory*" or "*Finished Goods Inventory*."
5. Deferred revenue: These adjustments would typically be recorded as a liability, such as "*Deferred Revenue*" or "*Unearned Revenue*."

Overall, the specific accounts used in the Chart of Accounts for these short-term adjustments will depend on the nature of the adjustment and the specific accounting policies of the company. It is important to have a well-designed Chart of Accounts that accurately reflects the company's financial transactions and makes it easy to prepare financial statements in accordance with GAAP or IFRS.

Which word is the best for salespersons selected on sales documents such as invoices, quotes and credit notes and purchase documents such as purchases, supplier returns and orders?

The word that is commonly used for salespersons on sales documents such as invoices, quotes, and credit notes, as well as purchase documents such as purchases, supplier returns, and orders, is "*Salesperson*" or "*Sales Representative*." This term is widely recognized and commonly used in the business world to identify the person responsible for the sale or purchase transaction. Other possible terms could include "*Sales Agent*," "*Account Executive*," or "*Business Development Manager*," depending on the specific role and responsibilities of the individual.

Is there a recommended Chart of accounts example for countries in South Africa?

There is no one-size-fits-all Chart of Accounts that is recommended for all countries, as each company's accounting needs may vary depending on factors such as their industry, size, and legal requirements. However, there are general guidelines that can be followed when creating a Chart of Accounts for a South African company.

The Chart of Accounts for South African companies typically follows the International Financial Reporting Standards (IFRS) and generally includes the following categories:

1. Assets
2. Liabilities
3. Equity

4. Income
5. Cost of sales
6. Expenses

Each of these categories may have subcategories that are more specific to the company's operations. For example, under "*Assets*," there may be subcategories for *"Cash and cash equivalents*," "*Accounts receivable*," and "*Fixed assets*." Similarly, under "*Expenses*," there may be subcategories for "*Salaries and wages*," "*Rent and utilities*," and "*Marketing and advertising expenses*."

It is also important to consider any industry-specific requirements or regulations that may apply to the company when designing the Chart of Accounts.

Overall, the Chart of Accounts should be designed in a way that accurately reflects the company's financial transactions and makes it easy to prepare financial statements in accordance with the applicable accounting standards. It is recommended to consult with a qualified accountant or accounting firm to help create a Chart of Accounts that meets the company's specific needs and complies with local accounting standards.

Is there a recommended Chart of accounts example for countries in South Africa that is GAAP compliant?

South Africa uses International Financial Reporting Standards (IFRS) as the generally accepted accounting principles (GAAP) for financial reporting. Therefore, the recommended Chart of Accounts example for South African companies that is GAAP compliant is based on IFRS guidelines.

The Chart of Accounts for South African companies typically includes the following categories:

1. Assets
2. Liabilities
3. Equity
4. Income
5. Cost of sales
6. Expenses

Each of these categories may have subcategories that are more specific to the company's operations. For example, under "*Assets*," there may be subcategories for "*Cash and cash equivalents*," "Accounts receivable," and "*Property, plant, and equipment*". Similarly, under "Expenses," there may be subcategories for "*Salaries and wages*," "*Rent and utilities*," and "*Advertising and marketing expenses*."

The Chart of Accounts should be designed to comply with IFRS guidelines and should accurately reflect the company's financial transactions. It is important to work with a qualified accountant or accounting firm to ensure that the Chart of Accounts is tailored to the company's specific needs and complies with local accounting standards.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Differences between GAAP and IFRS

What is the difference of Accounting terminology used in GAAP and IFRS?

GAAP (Generally Accepted Accounting Principles) and IFRS (International Financial Reporting Standards) are two sets of accounting standards used by companies to prepare financial statements. While there are many similarities between GAAP and IFRS, there are also some key differences in the accounting terminology used by the two standards:

1. Revenue recognition: GAAP and IFRS have different rules for when revenue can be recognized. Under GAAP, revenue can be recognized when it is earned, while under IFRS, revenue can be recognized only when it is probable that economic benefits will flow to the company.
2. Inventory valuation: GAAP allows for the use of LIFO (last-in, first-out) inventory accounting, while IFRS does not. Instead, IFRS requires companies to use the FIFO (first-in, first-out) or weighted average cost methods.
3. Financial statement presentation: GAAP and IFRS have different requirements for the presentation of financial statements. For example, GAAP requires a separate statement of comprehensive income, while IFRS allows for comprehensive income to be included in the statement of profit and loss or in a separate statement.
4. Goodwill impairment: GAAP and IFRS have different rules for testing for goodwill impairment. Under GAAP, goodwill is tested for impairment at least annually, while under IFRS, it is tested only when there is an indication of impairment.
5. Lease accounting: GAAP and IFRS have different rules for accounting for leases. Under GAAP, leases are classified as either operating or finance leases, while under IFRS, leases are classified as either finance leases or operating leases.

These are just a few examples of the differences in accounting terminology used by GAAP and IFRS. It is important for companies to be aware of these differences and to ensure that they are using the appropriate accounting standards for their specific needs and requirements.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's Efficient User Interface

Differences of between in IFRS (full) and IFRS for SMEs

What is the difference of Accounting terminology used in IFRS (full) and IFRS for SMEs?

The accounting terminology used in IFRS (full) and IFRS for SMEs (International Financial Reporting Standards for Small and Medium-sized Entities) is generally similar, but there are some differences in terminology and terminology usage. The main objective of IFRS for SMEs is to simplify the accounting requirements for SMEs and make them more accessible and cost-effective compared to the full IFRS framework.

Here are some key differences in accounting terminology between IFRS (full) and IFRS for SMEs:

1. Terminology Adaptation: IFRS for SMEs may use simplified or adapted terminology to make it more understandable and applicable to the needs of SMEs. This can include the use of simpler terms or specific terms commonly used in SME contexts.
2. Presentation and Disclosure: IFRS for SMEs may have reduced disclosure requirements compared to full IFRS. This means that certain terminology related to disclosure items in full IFRS may not be present or may be simplified in IFRS for SMEs.
3. Measurement and Recognition: IFRS for SMEs provides simplified measurement and recognition principles compared to full IFRS. This may result in the use of different terms or terminology specific to the simplified requirements of SMEs.
4. Specific Industry Considerations: IFRS for SMEs may provide industry-specific guidance or exemptions for certain industries or activities. This can result in the use of industry-specific terminology or terminology tailored to the needs of specific sectors.

It's important to note that while there may be differences in terminology, the underlying accounting principles and concepts remain consistent across both IFRS (full) and IFRS for SMEs. The aim is to provide a clear and transparent framework for financial reporting, irrespective of the size or complexity of the reporting entity.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Accounting principles - GAAP

osFinancials5/TurboCASH5 is an accounting system used by businesses to keep track of their financial transactions. The main purpose of accounting is to provide financial information in an understandable format to investors, bank managers, creditors, consultants, and others.

There are several basic accounting principles that are followed by most accounting systems, including osFinancials5/TurboCASH5.

By following basic accounting principles, businesses can ensure that their financial information is accurate and reliable. While accounting may seem like a complex language at first, there are tools and resources available, such as osFinancials5/TurboCASH5, that can help simplify the process and minimise the need for extensive accounting knowledge.

What is a definition of accounting principles?

Accounting principles, also known as generally accepted accounting principles (GAAP), refer to a set of guidelines, standards, and concepts that govern the preparation, presentation, and reporting of financial statements. These principles provide a framework for how financial transactions should be recorded, measured, and communicated to users of financial information.

Accounting principles ensure consistency, comparability, and transparency in financial reporting across different organizations and industries. They serve as a common language that enables stakeholders, such as investors, creditors, regulators, and management, to understand and interpret financial information accurately.

These principles are established by accounting standard-setting bodies, regulatory authorities, and professional accounting organizations. They evolve over time to adapt to changing business environments and reflect the needs of financial statement users.

By following accounting principles, businesses can ensure that their financial information is reliable, relevant, and comparable. It helps promote trust, facilitate decision-making, and provide a standardized basis for assessing a company's financial performance and position.

Does the Accounting principles only apply to GAAP; or is it also applicable to IFRS full and IFRS for SMEs?

The term "*accounting principles*" is commonly associated with generally accepted accounting principles (GAAP), which are widely used in the United States. However, the concept of accounting principles extends beyond GAAP and applies to other accounting frameworks as well, including International Financial

Reporting Standards (IFRS).

IFRS is a globally recognized set of accounting standards developed by the International Accounting Standards Board (IASB). Like GAAP, IFRS also encompasses a set of principles, guidelines, and concepts that govern financial reporting. These principles serve a similar purpose as GAAP in providing guidance on how financial transactions should be recorded, measured, and reported.

While there may be some differences between specific accounting principles under GAAP and IFRS, both frameworks share the common objective of ensuring the accuracy, comparability, and transparency of financial statements. Both GAAP and IFRS aim to provide reliable and relevant financial information to users, regardless of their geographical location.

Additionally, IFRS has a specific standard called IFRS for Small and Medium-sized Entities (IFRS for SMEs), which provides simplified accounting principles tailored to the needs of smaller businesses. This standard recognizes that smaller entities may have different reporting requirements and resources compared to larger organizations.

In summary, accounting principles apply to various accounting frameworks, including GAAP and IFRS, and they provide a foundation for the preparation, presentation, and reporting of financial statements in a consistent and reliable manner.

What is accounting principles?

Accounting principles, also known as generally accepted accounting principles (GAAP), refer to a set of guidelines, standards, and concepts that govern the preparation, presentation, and reporting of financial statements. These principles provide a framework for how financial transactions should be recorded, measured, and communicated to users of financial information.

Accounting principles ensure consistency, comparability, and transparency in financial reporting across different organizations and industries. They serve as a common language that enables stakeholders, such as investors, creditors, regulators, and management, to understand and interpret financial information accurately.

These principles are established by accounting standard-setting bodies, regulatory authorities, and professional accounting organizations. They evolve over time to adapt to changing business environments and reflect the needs of financial statement users.

By following accounting principles, businesses can ensure that their financial information is reliable, relevant, and comparable. It helps promote trust, facilitate decision-making, and provide a standardized basis for assessing a company's financial performance and position.

Objectives of Accounting principles

- Provide financial information: The main objective of accounting principles is to provide accurate and reliable financial information about a business's transactions and financial position. This information is essential for decision-making by various stakeholders.
- Ensure transparency: Accounting principles aim to promote transparency by requiring businesses to disclose all relevant financial information and provide a clear picture of their financial activities.
- Facilitate comparability: By following consistent accounting methods and procedures, accounting principles enable stakeholders to compare financial information across different periods and entities.
- Enhance reliability: Accounting principles emphasize the use of objective evidence and reliable measurement methods to ensure that the financial information is trustworthy and free from bias.
- Assist in decision-making: The information generated through accounting principles helps investors, creditors, and other users in making informed decisions regarding their involvement with the business.

Brief explanation of the accounting principles

1. Business entity principle: This principle states that the business's financial transactions should be kept separate from the personal transactions of its owners or stakeholders. The business is treated as a separate legal entity.
2. Going concern principle: This principle assumes that a business will continue to operate in the foreseeable future, allowing it to meet its financial obligations and commitments. It implies that the financial statements are prepared under the assumption that the business will not be liquidated.
3. Monetary unit principle: This principle states that financial transactions should be recorded and reported in a common monetary unit, such as the local currency. It helps in measuring and comparing the financial information accurately.
4. Time period principle: This principle divides the business's activities into specific time periods, such as months, quarters, or years. Financial statements are prepared for these periods to provide useful information for decision-making and analysis.
5. Historical cost principle: This principle requires that assets be recorded at their original cost when they are acquired, regardless of their current market value. It ensures objective and verifiable accounting information.
6. Revenue recognition: This principle outlines when and how revenue should be recognized in the financial statements. Revenue is typically recognized when it is earned, regardless of when the payment is received.

7. Matching principle: This principle states that expenses should be recognized in the same accounting period as the revenue they helped generate. It ensures that the expenses are matched with the revenue they are associated with.
8. Full disclosure principle: This principle requires businesses to provide all necessary information in the financial statements and accompanying notes to ensure transparency and help users make informed decisions.
9. Materiality principle: This principle suggests that insignificant or immaterial amounts can be recorded in a simplified manner, while significant or material amounts should be disclosed and given detailed treatment.
10. Conservatism principle: This principle advises accountants to exercise caution and conservatism when recording uncertain events or transactions. It suggests that potential losses should be recognized earlier than potential gains to avoid overstating financial position or performance.
11. Accrual principle: This principle states that revenue and expenses should be recognized when they are earned or incurred, regardless of when the cash payment is received or made. It focuses on matching revenues and expenses with the accounting period.
12. Consistency principle: This principle requires businesses to use consistent accounting methods and procedures from one period to another. It ensures comparability and reliability of financial information over time.
13. Objectivity principle: This principle emphasizes that financial transactions should be supported by objective evidence, such as receipts, invoices, or bank statements. It ensures reliability and verifiability of the recorded transactions.

Adhering to accounting principles is crucial for businesses to maintain accurate financial records, present reliable financial statements, and meet regulatory requirements. These principles ensure that financial information is prepared consistently, transparently, and objectively.

Additionally, accounting software like osFinancials5/TurboCASH5 can further simplify the process and support businesses in implementing these principles effectively, even without extensive accounting knowledge. By following these principles, businesses can gain a better understanding of their financial performance, improve decision-making, and build trust with stakeholders.

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

Accounting principles that apply to IFRS full and IFRS for SMEs

---

Is there specific accounting principles that apply to IFRS full and IFRS for SMEs?

There are specific accounting principles that apply to both IFRS (International Financial Reporting Standards) and IFRS for SMEs (International Financial Reporting Standards for Small and Medium-sized Entities). While there is significant overlap between the two frameworks, IFRS for SMEs includes simplified accounting principles specifically designed for smaller entities.

Some of the specific accounting principles that apply to IFRS and IFRS for SMEs include:

1. Accrual basis of accounting: Both frameworks require the recognition of transactions and events when they occur, rather than when cash is received or paid.
2. Substance over form: Transactions are accounted for based on their underlying economic substance rather than merely their legal form.
3. Fair presentation and Compliance with standards: Financial statements should present a true and fair view of the entity's financial position, performance, and cash flows in accordance with the specific requirements of the applicable framework.
4. Going concern: Financial statements are prepared on the assumption that the entity will continue its operations for the foreseeable future, unless there is evidence to the contrary.
5. Prudence: This principle encourages the exercise of caution in uncertain circumstances and the exercise of professional judgment in making estimates and provisions.
6. Materiality: Financial information should be presented and disclosed based on its relevance and importance to the decision-making needs of the users of the financial statements.
7. Cost principle: Assets are initially recognized and measured at their historical cost, although certain exceptions exist for specific types of assets.
8. Substance of Non-exchange transactions: Non-exchange transactions, such as government grants or donations, are accounted for based on their substance and the related conditions.

These are just a few examples of the accounting principles that apply to IFRS and IFRS for SMEs. The specific set of principles and requirements within each framework are more comprehensive and detailed, providing guidance on various aspects of accounting and financial reporting.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's Efficient User Interface

Accounting principles that apply to IFRS for SMEs

Is there specific accounting principles that apply to IFRS for SMEs?

The International Financial Reporting Standards for Small and Medium-sized Entities (IFRS for SMEs) is a simplified set of accounting principles specifically designed for small and medium-sized entities. It provides a streamlined framework for financial reporting that takes into account the unique characteristics and needs of SMEs, while still maintaining a high level of transparency and reliability.

The IFRS for SMEs includes specific accounting principles and requirements that SMEs should follow when preparing their financial statements. Some key principles and topics covered in the IFRS for SMEs include:

1. Recognition and measurement of assets, liabilities, equity, income, and expenses: The IFRS for SMEs provides guidance on how to recognize and measure various elements of financial statements, including the initial recognition, subsequent measurement, and derecognition of assets, liabilities, equity, income, and expenses.
2. Presentation and disclosure: The standard outlines the presentation and disclosure requirements for financial statements, including the minimum set of financial statements that should be prepared (such as statement of financial position, statement of comprehensive income, statement of changes in equity, and statement of cash flows) and the information that should be disclosed in the notes to the financial statements.
3. Specific accounting topics: The IFRS for SMEs covers various specific accounting topics, including revenue recognition, leasing, financial instruments, impairment of assets, inventory valuation, employee benefits, income taxes, and others. It provides guidance on how to account for these specific items in a manner suitable for SMEs.
4. Simplifications and exemptions: The IFRS for SMEs includes simplifications and exemptions compared to the full IFRS standards to reduce the reporting burden for SMEs. These simplifications include reduced disclosure requirements and simplified measurement and recognition criteria for certain items.

It's important for SMEs to familiarize themselves with the specific accounting principles and requirements outlined in the IFRS for SMEs and ensure compliance when preparing their financial statements.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

IFRS for SME's - Countries - Optional / Mandatory

In which countries is the IFRS for SME's optional and in which countries is it compulsory?

See - IFRS for SMEs around the world -

The International Financial Reporting Standards for Small and Medium-sized Entities (IFRS for SMEs) is not universally adopted and varies by country.

As in 2021, some countries have made the IFRS for SMEs mandatory for SMEs, while others have made it optional. Here are some examples:

Optional:

- Australia
- Canada
- India
- New Zealand
- South Africa

Mandatory:

- European Union member states (including the United Kingdom)
- China
- Hong Kong
- Malaysia
- Pakistan
- Singapore

Please note that this list may not be complete and that the adoption of IFRS for SMEs may change over time. It is recommended to consult with a professional accountant or regulatory body for up-to-date information on the adoption of IFRS for SMEs in a specific country.

Created with the Standard Edition of HelpNDoc: Free EPub producer

Differences in accounting terminology in countries

Does accounting terms and terminology differ from country to country and tax regimes?

Yes, accounting terms and terminology can differ from country to country and tax regimes due to variations in accounting principles, tax laws, and regulations. For example, the Generally Accepted Accounting Principles (GAAP) used in the United States may differ from the International Financial Reporting Standards (IFRS) used in other countries.

Similarly, tax laws and regulations can vary significantly from one country to another, which can impact the way accounting terms and concepts are used and interpreted. It is important for businesses and accountants to be aware of these differences and to ensure that they are using the appropriate accounting terms and principles for their specific location and tax regime.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Accounting in China

Is the IFRS for UK applicable to China?

No, the IFRS for the UK is not applicable to China.

China has its own set of accounting standards known as the Chinese Accounting Standards (CAS).

China - China is included in the IFAD GAAP Convergence Studies. - Accounting standard setter: China Accounting Standards Committee (CASC) ...

While there is some convergence between CAS and IFRS, CAS is the primary set of standards used by Chinese companies.

www.ptl-group.com

Chinese Accounting Standards (CAS)

See - https://www.ptl-group.com/guides/accounting-in-china/ -

See - https://www.ptl-group.com/guides/taxes-paid-by-employers/ -

IFRS Resources

See - https://www.ifrs.org/use-around-the-world/use-of-ifrs-standards-by-jurisdiction/ -

See - IFRS Jurisdiction Profile : China

https://www.ifrs.org/content/dam/ifrs/publications/jurisdictions/pdf-profiles/china-ifrs-profile.pdf

Does China apply IFRS for all companies?

No, China does not apply IFRS for all companies, but some Chinese companies do use IFRS for financial reporting to investors outside of China.

Explanation

- *Chinese Accounting Standards (ASBEs)*

China's national accounting standards, which are substantially similar to IFRS. All companies listed in China must use ASBEs to prepare financial statements.

IFRS

The International Financial Reporting Standards, which are issued by the IASB.
Hong Kong Financial Reporting Standards (HKFRS)
The financial reporting standards used in Hong Kong.
Dual listings
Chinese companies that are listed in both China and other international markets may produce IFRS-compliant financial statements.
Why the difference?

- China's accounting rules are different from IFRS in terms of practical implementation and interpretation.
- IFRS is modelled on developed economies, and it's not clear how it will affect large transitional economies like China.

  See - IFRS adoption in China and foreign institutional investments -

What accounting standards are adopted in China?

China has its own accounting rules referred to as the Chinese Accounting Standards (CAS). Despite substantial convergence between CAS and the International Financial Reporting Standards (IFRS) that most Western investors are used to, practical implementation and interpretation differences remain.

The CAS framework is based on two standards:

- Accounting Standards for Business Enterprises (ASBEs); and
- Accounting Standards for Small Business Enterprises (ASSBEs).

The ASBE standards are significantly converged with the International Financial Reporting Standards (IFRS) and all listed companies in China must comply with the ASBEs for the preparation of their financial statements. Most foreign-invested entities also generally follow the ASBEs.

The ASSBEs are a counterpart of the ASBEs, providing unified standards for small-size enterprises. The ASSBEs use the ASBEs as a reference but are more similar to tax laws in terms of their tax calculation methods, which simplify the process of making adjustments between accounting standards and tax rules. Small-scale enterprises can choose to adopt either the ASBEs or ASSBEs.

Language and currency for reporting

RMB is the base currency for ledgers and financial reports. For enterprises using currencies other than RMB in their business transactions, foreign currencies can be used as the functional currency; however, financial reports are required to be presented in RMB. Furthermore, accounting records must be maintained in Chinese. FIEs can choose to use only Chinese or a combination of Chinese and a foreign language.

Chart of Accounts

Is there sample chart of accounts for Accounting Standards for Small Business Enterprises (ASSBEs)?

While there isn't a single, universal sample chart of accounts specifically tailored to ASSBEs, here's a basic framework you can adapt based on your business's specific needs and the applicable ASSBE requirements:

Assets:

- Cash: Bank accounts, petty cash
- Accounts Receivable: Money owed by customers
- Inventory: Goods held for sale
- Prepaid Expenses: Expenses paid in advance (e.g., insurance, rent)
- Fixed Assets: Property, plant, and equipment (less accumulated depreciation)

Liabilities:

- Accounts Payable: Money owed to suppliers
- Short-Term Loans Payable: Loans due within a year
- Long-Term Loans Payable: Loans due beyond a year
- Accrued Expenses: Expenses incurred but not yet paid

Equity:

- Owner's Capital: Initial investment and additional contributions
- Retained Earnings: Accumulated profits less dividends

Revenue:

- Sales Revenue: Income from sales of goods or services
- Other Income: Interest, rental income, etc.

Expenses:

- Cost of Goods Sold: Direct costs of producing goods sold
- Selling Expenses: Costs related to marketing and sales
- General and Administrative Expenses: Overhead costs (e.g., rent, utilities, salaries)

Remember:

- Tailor to Your Business: Adjust the chart to match your specific operations and industry.
- Consider ASSBE Requirements: Ensure your chart aligns with the specific requirements and disclosures outlined in the ASSBEs.
- Use a Chart of Accounts Software: Consider using accounting software to automate the process and ensure accuracy.

Where to Find More Information:

- Accounting Software Providers: Many accounting software programs come with pre-built chart of accounts templates that you can customize.
- Consult with an Accountant: An accountant can provide tailored advice and help you create a chart of accounts that meets your specific needs and complies with ASSBEs.

By carefully considering these factors, you can create a comprehensive and effective chart of accounts for your small business under the ASSBEs framework.

Is there sample chart of accounts for Accounting Standards for Business Enterprises (ASBEs)?

While there isn't a single, universal sample chart of accounts specifically tailored to ASBEs, here's a basic framework you can adapt based on your business's specific needs and the applicable ASBE requirements:

Assets:

- Cash: Bank accounts, petty cash
- Accounts Receivable: Money owed by customers
- Inventory: Goods held for sale
- Prepaid Expenses: Expenses paid in advance (e.g., insurance, rent)
- Fixed Assets: Property, plant, and equipment (less accumulated depreciation)

Liabilities:

- Accounts Payable: Money owed to suppliers
- Short-Term Loans Payable: Loans due within a year
- Long-Term Loans Payable: Loans due beyond a year
- Accrued Expenses: Expenses incurred but not yet paid

Equity:

- Owner's Capital: Initial investment and additional contributions
- Retained Earnings: Accumulated profits less dividends

Revenue:

- Sales Revenue: Income from sales of goods or services
- Other Income: Interest, rental income, etc.

Expenses:

- Cost of Goods Sold: Direct costs of producing goods sold
- Selling Expenses: Costs related to marketing and sales
- General and Administrative Expenses: Overhead costs (e.g., rent, utilities, salaries)

Remember:

- Tailor to Your Business: Adjust the chart to match your specific operations and industry.
- Consider ASBE Requirements: Ensure your chart aligns with the specific requirements and disclosures outlined in the ASBEs.
- Use a Chart of Accounts Software: Consider using accounting software to automate the process and ensure accuracy.

Where to Find More Information:

- Accounting Software Providers: Many accounting software programs come with pre-built chart of accounts templates that you can customize.
- Consult with an Accountant: An accountant can provide tailored advice and help you create a chart of accounts that meets your specific needs and complies with ASBEs.

By carefully considering these factors, you can create a comprehensive and effective chart of accounts for your business under the ASBEs framework.

Chinese 4-CAS-GENERIC Set of Books Debug

Good job - Need to look at the following:

Inno Install script for Chinese

Currently we have the following languages to install TurboCASH5

Folders that contain the tcash.ini files:

chs- Chinese simplified

cht - Chinese traditional

Innoscript language files:

ChineseSimp.isl

ChineseTrad.isl

Important to select the correct language folder and innoScript language files which is inline with the Chinese.dfm language file. Should it be Chinese simplified or Chinese traditional.

Language : Chinese.dfm - Codepage setting

Language : Chinese.dfm - Codepage - Tools -> Customize Language

The default codepage is 1253



What is codepage 1253 and is it applicable to the China?

Codepage 1253 is specifically designed for the Greek language. [1] It's a character encoding standard used to represent text in the modern Greek alphabet, including accented letters, punctuation marks, and special symbols.[2]

It is not applicable to the Chinese language. Chinese languages (Simplified and Traditional) require different code pages, such as GB2312, GBK, GB18030 (for Simplified Chinese) and Big5, CNS 11643 (for Traditional Chinese).

Key Points:

- Codepage 1253: For modern Greek.[3]
- Chinese Languages: Use different code pages like GB2312, GBK, GB18030, Big5, and CNS 11643.
- Unicode: The preferred standard for modern systems, supporting all languages, including Chinese and Greek.

I hope this clarifies the distinction!

- https://learn.microsoft.com/en-us/windows/win32/intl/code-page-identifiers -

What is the Codepages for Chinese languages?

The most common code pages for Chinese languages are:

- Simplified Chinese:
  - GB2312: A national standard for mainland China, covering a subset of simplified Chinese characters.
  - GBK: An extension of GB2312, supporting a larger set of characters.
  - GB18030: A more recent standard that includes a wider range of characters, including those used in minority languages in China.
- Traditional Chinese:
  - Big5: A widely used encoding for traditional Chinese, primarily in Taiwan and Hong Kong.
  - CNS 11643: A national standard for Taiwan, supporting a comprehensive set of traditional Chinese characters.

It's important to note that:

- Unicode: The preferred encoding for modern systems is Unicode (specifically UTF-8), which supports all languages and scripts.
- Code pages are often legacy encodings. While they may still be used in some older systems, Unicode is generally the recommended standard for new applications and data exchange.

Display of Chinese characters on screens, forms / reports

Print Setup -> Groups and Ledger analyser 1/2

Print button in Print Setup -> Groups seems to print correctChinese characters, but in the Ledger analyser 1/2 it prints the characters with question marks ????



On the Accounts, Groups, etc. forms seems to display in the Chinese characters correctly.

Setup menu

Setup -> Company Info

Name of Set of Books refers to "4-EN-UK GENERIC BOOKS - Standard VAT Scheme"

Setup -> Reporting dates

Reporting dates refer to January - to December - may need to be translated.

Chart of accounts

VAT GST/Sales tax in China

Currently the VAT in the Chart of Accounts is based on the UK VAT - Standards= cgeme reflecting tax percentages of 20%, etc.

The correct term for the sales tax in China is Value Added Tax (VAT).[1]

See - https://taxsummaries.pwc.com/quick-charts/value-added-tax-vat-rates -

China has a multi-tiered VAT system with different rates:[2]

See - https://wise.com/gb/vat/china -

- Standard Rate: 13% (applies to most goods and services)[3]
  See - https://wise.com/gb/vat/china -
- Reduced Rates: 9% and 6% (for specific goods and services like certain agricultural products, transportation, and some services)

Note: The specific VAT rates and their applicability can change, so it's essential to refer to the latest official information from the Chinese tax authorities for the most accurate and up-to-date details.

Organizing payroll accounts in China

Here's a possible structure for organizing payroll accounts in China, keeping in mind that specific requirements might vary:

I. Expense Accounts

- 501000 Salaries Expense
  - 501010 Basic Salary
  - 501020 Overtime Pay
  - 501030 Bonuses
  - 501040 Allowances (e.g., housing, transportation)
- 502000 Payroll Taxes Expense
  - 502010 Pension Insurance - Employer Portion
  - 502020 Medical Insurance - Employer Portion
  - 502030 Unemployment Insurance - Employer Portion
  - 502040 Work Injury Insurance - Employer Portion
  - 502050 Maternity Insurance - Employer Portion
  - 502060 Housing Fund - Employer Portion
- 503000 Employee Benefits Expense
  - 503010 Medical Insurance - Employee Portion
  - 503020 Housing Fund - Employee Portion
  - 503030 Other Employee Benefits (e.g., life insurance, meal subsidies)

II. Balance Sheet Accounts

- 211000 Accrued Salaries Payable
- 212000 Payroll Taxes Payable
    - 212010 Pension Insurance Payable
    - 212020 Medical Insurance Payable
    - 212030 Unemployment Insurance Payable
    - 212040 Work Injury Insurance Payable
    - 212050 Maternity Insurance Payable
    - 212060 Housing Fund Payable
- 213000 Withholding Taxes Payable

Key Considerations:

- Chart of Accounts Design: This structure provides a basic framework. You should adapt it to your specific needs and the level of detail required for your accounting system.
- Coding System: Implement a consistent coding system (e.g., alphanumeric) for easy identification and reporting.
- Internal Controls: Establish strong internal controls to ensure accuracy and prevent fraud in payroll processing.[1] See - https://www.unit21.ai/fraud-aml-dictionary/payroll-fraud#:~:text=Strong%20internal%20controls%20that%20restrict,used%20to%20manage%20threats%20more -
- Regular Reviews: Regularly review and update your payroll account structure to reflect changes in regulations and business requirements.

Disclaimer: This information is for general guidance only and should not be considered professional accounting advice.

It is strongly recommended consulting with a qualified accounting professional or tax advisor in China for specific guidance on payroll accounting and tax requirements. They can help you design a Chart of Accounts that meets your specific needs and complies with all applicable regulations.

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Designing a Chart of Accounts

Steps when Designing a chart of accounts from scratch

Designing a chart of accounts from scratch is a crucial step in setting up a robust and efficient accounting system for your business. The chart of accounts organizes and categorises your financial transactions, making it easier to track and analyse your company's financial performance. Here are some steps to consider when designing a Chart of Accounts in osFinancials:

1. Understand Accounting Standards and Framework and Legislation : Begin by familiarizing yourself with the accounting standards and frameworks, Legal Requirements and Tax Regulations, Legislation Regarding Business Ownership and Structure, Labour Laws and Employment Regulations and any applicable matters regarding the nature of your business and the industry and jurisdiction in which it operates. Let's delve into the significance of each aspect:
    - Accounting Standards and Frameworks: Different countries may follow specific accounting principles and frameworks, such as Generally Accepted Accounting Principles (GAAP) or International Financial Reporting Standards (IFRS). Complying with these standards ensures that your financial statements are prepared in a consistent and transparent manner, making it easier for stakeholders to understand your company's financial performance. Adhering to recognized accounting standards also facilitates comparisons with other companies and builds credibility with investors, creditors, and regulatory authorities.
    - Legal Requirements and Tax Regulations : Each country has its own set of legal requirements and tax regulations that businesses must follow. Understanding these regulations is crucial for ensuring compliance and avoiding potential legal and financial risks. Specific attention should be given to areas such as Value Added Tax (VAT), Goods and Services Tax (GST), Sales Tax, Income Tax, and other taxes applicable to your business activities. Non-compliance with tax regulations can lead to penalties and other consequences, so it's essential to be well-informed and stay up-to-date with changes in tax laws.
    - Legislation Regarding Business Ownership and Structure: Depending on the type of business ownership and legal structure (e.g., sole proprietorship, partnership, corporation), there may be specific legal requirements and obligations to consider. The Companies Act or other relevant legislation governs the formation, management, and dissolution of companies. Similarly, for non-profit organizations (NGOs/NPOs), there may be additional regulatory requirements specific to their operations and funding sources.

- Labour Laws and Employment Regulations: Compliance with labour laws and employment regulations is essential for businesses with employees. These laws cover areas such as wages, working hours, benefits, health and safety, and employment contracts. Failure to comply with labour laws can result in legal liabilities and damage to the company's reputation.

Incorporating these considerations into your accounting and financial management processes ensures that your business operates ethically and within the legal framework of the country and industry. It also helps you maintain accurate financial records, prepare reliable financial statements, and comply with tax obligations, providing a solid foundation for sustainable growth and success. Seeking professional advice from accountants or legal experts familiar with your country's regulations can be beneficial in ensuring compliance and proper financial management.

2. Creating a Chart of Accounts from scratch: When creating a Set of Books from (Using the "*Customise your own Set of Books (Advanced)?*" option in osFinancials5/TurboCASH5. The basic Chart of Accounts will only include three basic control accounts (i.e. Debtors control account, Creditors control account and Retained earnings). You need to add an Inventory Control account into the Chart of Accounts when setting up osFinancials5/TurboCASH5. These are essential control accounts that help track and manage specific financial activities within your business. Let's take a closer look at each of these control accounts:

   - Debtors Control Account: The Debtors Control Account is used to track the amounts owed to your business by customers who have purchased goods or services on credit. It serves as a summary of all outstanding accounts receivable balances. Each individual customer's outstanding balance is recorded in a subsidiary ledger, while the total of all outstanding balances is reflected in the Debtors Control Account in the general ledger. This control account helps monitor and manage your company's accounts receivable effectively.
   - Creditors Control Account: The Creditors Control Account is used to track the amounts your business owes to suppliers or vendors for goods or services purchased on credit. Similar to the Debtors Control Account, individual supplier balances are recorded in a subsidiary ledger, while the total of all outstanding balances is maintained in the Creditors Control Account in the general ledger. This control account enables you to manage and keep track of your company's accounts payable.
   - Retained Earnings Account: The Retained Earnings Account is used to track the accumulated profits or losses earned by the company since its inception, minus any dividends or distributions paid to shareholders. It represents the portion of the company's profits that have been retained within the business rather than distributed to shareholders. The Retained Earnings Account is an essential component of the equity section in the balance sheet.
   - Inventory Control Account: The Inventory Control Account is used to monitor the value of

your company's inventory or stock items. It represents the total value of all inventory items held by the company and is a critical account for managing inventory levels and cost of goods sold (COGS). Like the other control accounts, individual item details are maintained in a subsidiary ledger, while the summarized total is reflected in the Inventory Control Account in the general ledger.

Incorporating these control accounts in osFinancials5/TurboCASH5 ensures that your financial data is well-organized, easy to track, and provides valuable insights into your business's financial health. Subsidiary ledgers help provide more detailed information for each account, while control accounts in the general ledger provide a summarised view, allowing for better financial management and reporting.

3. Add Accounts to the Chart of Accounts

   - Identify Account Groups and Classifications: Create account groups based on your accounting standards and framework. Common account groups include assets, liabilities, equity, income, and expenses. Within each group, establish relevant classifications to further organize the accounts. For example, under assets, you may have subgroups like current assets, fixed assets, and intangible assets. These groups are added in the Setup → Groups menu on the Setup ribbon).
   - Align with Your Business Plan and Products: Ensure that your Chart of Accounts aligns with your business plan and reflects the nature of your business operations. Consider the products or services you offer and the revenue and expense categories associated with them. For instance, if you sell multiple product lines, you may want separate income accounts for each product to track their individual performance.
   - Add Accounts and Link to Account Groups: Once you have defined your account groups and classifications, start adding specific accounts. Include accounts for cash, accounts receivable, accounts payable, inventory, sales, salaries, rent, etc. Assign each account to its appropriate group and classification. These Accounts are added in the Setup → Accounts menu on the Setup ribbon).
   - Map Accounts to Financial Categories: Map your accounts to the five main financial categories: assets, liabilities, equity, income, and expenses. This step ensures that transactions are correctly classified in financial statements generated by osFinancials5/TurboCASH5. These groups is can be linked to the financial categories in the Setup → Financial categories menu on the Setup ribbon).

   After you have created the accounts and linked them to account groups, and linked accounting groups to financial categories, you can print the structure of your ledger accounts according to Reporting group 1 or Reporting group 2 in a list of accounts or trial balance, income statement

and balance sheet. If any adjustments are needed, you can do them at this stage.

4. Customise language: osFinancials5/TurboCASH5 offers the flexibility to customise the language used within your Set of Books to cater to specific industries and regional requirements. This customisation allows businesses to tailor the terminologies and labels used in osFinancials to match their industry jargon, corporate preferences, and local language requirements. By setting your preferred language or customizing the language settings through the Setup → Access control menu on the Setup ribbon, osFinancials5/TurboCASH5 will display all labels, terminologies, and interface elements in the selected language whenever you access your Set of Books and print reports or documents. This makes it more convenient and user-friendly, especially when you have customised the language to suit your industry or regional requirements.
5. Review and Refine: Periodically review and refine your chart of accounts as your business grows or undergoes changes. Ensure that it remains relevant and useful for financial reporting and analysis.
6. Test and Implement: Before fully implementing the Chart of Accounts, test it with some sample transactions to ensure it works as intended and captures the necessary information accurately.

By following these steps, you can create a well-structured chart of accounts in osFinancials5/TurboCASH5 supports your business's financial management needs and facilitates accurate reporting and decision-making.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Chart of Accounts - Definition and objectives

What is the chart of accounts?

A Chart of Accounts is a structured list of all the individual accounts used by a company to record its financial transactions. It serves as a systematic classification or organizational tool for categorizing and tracking financial information. The chart of accounts provides a framework for organizing and summarizing financial data, financial activities and resources enabling businesses to track income, expenses, assets, liabilities, and equity.

Each account in the Chart of Accounts represents a specific financial category, such as assets, liabilities, equity, revenue, and expenses. These accounts are assigned unique identifiers or codes, known as account numbers, to facilitate their identification and classification.

The Chart of Accounts typically includes a hierarchical structure, where accounts are organized into different levels and sub-levels based on their nature and relationship. The top level often consists of broad

categories such as assets, liabilities, equity, revenue, and expenses. These categories are further broken down into subcategories and individual accounts for more specific classification.

The purpose of the Chart of Accounts is to provide a standardized framework for recording financial transactions and generating financial reports. It helps in capturing and organising financial data accurately, enabling businesses to track their financial activities, analyse performance, and prepare financial statements like the balance sheet, income statement, and cash flow statement.

Designing a well-structured and tailored Chart of Accounts is crucial for effective financial management, reporting, and analysis. It allows businesses to have a clear overview of their financial position, understand the sources and uses of funds, and make informed decisions based on reliable financial information.

What are the objectives of a chart of accounts?

The objectives of a chart of accounts are as follows:

1. Organize financial information: The primary objective of a Chart of Accounts is to organize financial information in a structured manner. It establishes a standardized system for classifying and recording transactions, allowing for easy retrieval and analysis of financial data. It helps in categorizing transactions into different account types, such as assets, liabilities, equity, revenue, and expenses, allowing for better organization and management of financial data.
2. Facilitate accurate recording: A well-designed Chart of Accounts ensures that financial transactions are recorded accurately and consistently. Each account represents a specific financial element, which helps in correctly classifying and posting transactions to the appropriate account. It provides a standardized system for capturing financial information, which simplifies the process of recording transactions and generating financial reports.
3. Support financial reporting: A well-designed Chart of Accounts supports the preparation of financial statements and other financial reports. It provides the foundation for generating meaningful reports by grouping similar accounts together and allowing for efficient summarisation and analysis of financial data. These reports help in making informed decisions, identifying trends, and evaluating the financial health of the organization.
4. Enable financial analysis: The structure of a Chart of Accounts allows for effective and meaningful financial analysis. It allows businesses to generate reports that provide insights into their financial performance, profitability, liquidity, and other key metrics. These reports help in making informed decisions, identifying trends, and evaluating the financial health of the organisation. The Chart of Accounts enhances communication and collaboration within an organisation and with external stakeholders. It provides a common language for discussing financial matters and facilitates the sharing of financial information among departments, management, investors, auditors, and other stakeholders.

5. Facilitate regulatory compliance and tax reporting: The Chart of Accounts helps businesses meet regulatory and legal requirements by providing a framework for recording and reporting financial information. It ensures that financial statements are prepared in accordance with applicable accounting standards and regulations. This supports transparency, accuracy, and compliance in financial reporting. It facilitates the accurate reporting of financial information for statutory filings, tax purposes, and external audits.
6. Support management decision-making: The Chart of Accounts plays a crucial role in providing financial information for managerial decision-making. It allows management to track and analyse key financial metrics, monitor expenses, evaluate profitability, and make informed business decisions based on reliable and relevant data.
7. Adaptability and scalability: The Chart of Accounts should be designed to accommodate the evolving needs of the organisation. It should be flexible enough to adapt to changes in the business structure, operations, and reporting requirements. The Chart of Accounts should also support scalability, allowing for the addition of new accounts or modification of existing accounts as the organization grows or undergoes changes.

Overall, the objectives of a Chart of Accounts revolve around providing a systematic and standardized framework for organizing, recording, reporting, analysing, and communicating financial information within an organization in a consistent and meaningful manner.

While there is no universally standardized chart of accounts that applies to all businesses, including specific recommended account numbers, the accounts and account codes provide you with a general structure and some commonly used accounts in the chart of accounts. You can adapt this structure to fit your specific business needs,, accounting procedures and accounting practices, industry specific requirements, jurisdiction, country specific legislation and terminology industries, etc.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

---

Chart of Accounts - Number of digits

Is a 3-digit number Chart of accounts good for both Small businesses?

A 3-digit number Chart of Accounts may be suitable for small businesses, depending on the complexity of their operations and financial reporting needs.

Small businesses may have simpler financial transactions and reporting requirements compared to larger organisations. Therefore, a 3-digit Chart of Accounts may be sufficient to accurately categorise financial transactions and produce meaningful financial reports.

However, it is important for small businesses to consider their specific financial reporting needs and regulatory requirements. If the business operates in an industry with specific reporting requirements or regulations, a more detailed Chart of Accounts may be necessary to meet those requirements.

Ultimately, the number of digits used in the Chart of Accounts should be based on the specific needs of the business. It is important to ensure that the Chart of Accounts is organized in a logical and consistent manner to facilitate accurate financial reporting and analysis, regardless of the number of digits used.

Is a 3-digit number Chart of accounts good for both GAAP and IRFS?

The use of a 3-digit number Chart of Accounts may not be sufficient for both GAAP and IFRS, as it may not provide enough detail for accurate financial reporting and analysis.

While there is no specific requirement for the number of digits in the Chart of Accounts for either GAAP or IFRS, it is common for the Chart of Accounts to have at least four digits. This allows for greater detail and specificity in categorizing financial transactions, which can be important for accurate financial reporting and analysis.

A 3-digit Chart of Accounts may be suitable for smaller or less complex organizations, but larger and more complex organizations may require a more detailed Chart of Accounts to accurately capture and categorise financial transactions.

Ultimately, the number of digits used in the Chart of Accounts will depend on the specific needs and requirements of the organisation, as well as any regulatory requirements for financial reporting. It is important to ensure that the Chart of Accounts is organized in a logical and consistent manner to facilitate accurate financial reporting and analysis.

What number of digits should be in Chart of accounts for GAAP and IRFS?

There is no specific number of digits that is required for the Chart of Accounts in either GAAP or IFRS. The number of digits used can vary depending on the needs and complexity of the organization. However, it is common for the Chart of Accounts to have at least four digits, with each digit representing a different level of detail or classification.

For example, the first digit may represent the category of account (such as assets, liabilities, equity, revenue, or expenses), the second digit may represent the subcategory within that category, the third digit may represent the specific account within that subcategory, and the fourth digit may represent a further breakdown of the specific account.

Ultimately, the number of digits used in the Chart of Accounts will depend on the organization's specific needs and the level of detail required for financial reporting and analysis. It is important to ensure that the Chart of Accounts is organized in a logical and consistent manner to facilitate accurate financial reporting and analysis.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

---

Chart of Accounts structure - Numbering - Sub-accounts - Grouping

The ideal account structure for a chart of accounts isn't fixed and should align with your business's size, nature, and complexity. However, some general guidelines can be followed:

1. Numbering System: Employ a numbering system for easy transaction identification. Small businesses often use three-digit numbers for primary accounts, while larger businesses opt for four-digit numbers to accommodate future account expansion.
2. Grouping Accounts: Organize accounts into ranges based on their type and function. For instance, Assets can start with numbers in the 1 range, Liabilities with numbers in the 2 range, Equity accounts in the 3 range, revenue accounts for Operating revenue in the 4 range, and expenses for Operating expenses in the 5-7 range. Additionally, assign the 8 range for Non-Operating revenue and the 9 range for Non-Operating expenses.
3. Sub-Accounts: Utilize sub-accounts to further categorize main accounts into specific subcategories. For example, employ a three-digit sub-account to indicate the department or division associated with the primary account. Sub-accounts can also help track various projects, locations, or activities within a primary account.

Some recommendations and tips to plan your Chart of Accounts according to your selection on the number of main account digits

In addition to the standard 3-Digit General Ledger Chart of Accounts in most Sets of Books (which is available as a download on the option "*Let osFinancials help you to create a Set of Books?*" option / "*Let TurboCASH help you to create a Set of Books?*" option), you have the flexibility to craft your own custom Sets of Books using the "*Customise your own Set of Books (Advanced)?*" option. This feature is available for both the Firebird and MSSQL database types. These custom Sets of Books will include only three essential

control accounts: Debtors control, Creditors control, and Retained Earnings.

These advanced options empower you to tailor your main account and sub-account structures to meet your specific requirements, regardless of your industry or unique needs. Here are the available options:

- 4-Digit main accounts and 3-Digit sub-accounts: This template allows for more detailed main accounts with four digits, coupled with three-digit sub-accounts for further subcategorization.
- 5-Digit main accounts and 3-Digit sub-accounts: For even finer granularity, this template provides five-digit main accounts and three-digit sub-accounts.
- 6-Digit main accounts and 3-Digit sub-accounts: If you require highly detailed accounting, this template offers six-digit main accounts with three-digit sub-accounts.
- 7-Digit main accounts and 3-Digit sub-accounts: Taking detail to the next level, this template features seven-digit main accounts alongside three-digit sub-accounts.
- 8-Digit main accounts and 3-Digit sub-accounts: For the utmost level of detail, this template includes eight-digit main accounts in conjunction with three-digit sub-accounts.

These options grant you the flexibility to select the level of granularity that aligns best with your specific accounting needs when creating Sets of Books in either the Firebird or MSSQL database types.

A 4-Digit main accounts and 3 Digit sub-accounts in a Chart of Accounts, Is there any recommendations for an account structure?

A 4-digit main accounts and 3-digit sub-accounts structure in a chart of accounts provides limited granularity and detail. Here are some recommendations for structuring your accounts:

1. Identify your main account categories: Start by identifying the main categories of accounts that you want to track. For example, you may have categories for assets, liabilities, equity, revenue, and expenses.
2. Assign the first digit to the main account categories: Use the first digit of the account number to identify the main account category. For example, all asset accounts could start with the number 1, all liability accounts could start with the number 2, and so on.
3. Assign the next three digits to the individual accounts: Use the next three digits of the account number to identify individual accounts within each category. For example, an individual accounts receivable account could be numbered 110, and an individual accounts payable account could be numbered 210.
4. Assign the next three digits to subcategories: Use the next three digits of the account number to identify the subcategory of the individual account. For example, all accounts receivable sub-accounts

could start with the number 110100, and all accounts payable sub-accounts could start with the number 210100.

5. Consider adding a leading digit for multiple entities: If you have multiple entities, you may want to consider adding a leading digit to differentiate the account numbers for each entity. For example, all account numbers for entity A could start with the number 1, and all account numbers for entity B could start with the number 2.

By following these recommendations, you can create a basic and straightforward chart of accounts that provides a limited level of detail for financial reporting and analysis. However, keep in mind that with this structure, you may not have enough detail for complex financial analysis and reporting.

A 5-Digit main accounts and 3 Digit sub-accounts in a Chart of accounts, Is there any recommendations for an account structure?

A 5-digit main accounts and 3-digit sub-accounts structure in a chart of accounts provides moderate granularity and detail. Here are some recommendations for structuring your accounts:

1. Identify your main account categories: Start by identifying the main categories of accounts that you want to track. For example, you may have categories for assets, liabilities, equity, revenue, and expenses.
2. Assign the first two digits to the main account categories: Use the first two digits of the account number to identify the main account category. For example, all asset accounts could start with the number 10, all liability accounts could start with the number 20, and so on.
3. Assign the next three digits to the individual accounts: Use the next three digits of the account number to identify individual accounts within each category. For example, an individual accounts receivable account could be numbered 10010, and an individual accounts payable account could be numbered 20010.
4. Assign the next three digits to subcategories: Use the next three digits of the account number to identify the subcategory of the individual account. For example, all accounts receivable sub-accounts could start with the number 100110, and all accounts payable sub-accounts could start with the number 200110.
5. Consider adding a leading digit for multiple entities: If you have multiple entities, you may want to consider adding a leading digit to differentiate the account numbers for each entity. For example, all account numbers for entity A could start with the number 1, and all account numbers for entity B could start with the number 2.

By following these recommendations, you can create a structured and organized chart of accounts that provides a moderate level of detail for financial reporting and analysis.

A 6-Digit main accounts and 3 Digit sub-accounts in a Chart of accounts, Is there any recommendations for an account structure?

A 6-digit main accounts and 3-digit sub-accounts structure in a chart of accounts can still provide a high level of granularity and detail in your financial reporting. Here are some recommendations for structuring your accounts:

1. Identify your main account categories: Start by identifying the main categories of accounts that you want to track. For example, you may have categories for assets, liabilities, equity, revenue, and expenses.
2. Assign the first two digits to the main account categories: Use the first two digits of the account number to identify the main account category. For example, all asset accounts could start with the number 10, all liability accounts could start with the number 20, and so on.
3. Assign the next four digits to the individual accounts: Use the next four digits of the account number to identify individual accounts within each category. For example, an individual accounts receivable account could be numbered 101000, and an individual accounts payable account could be numbered 201000.
4. Assign the next three digits to subcategories: Use the next three digits of the account number to identify the subcategory of the individual account. For example, all accounts receivable sub-accounts could start with the number 101100, and all accounts payable sub-accounts could start with the number 201100.
5. Consider adding a leading digit for multiple entities: If you have multiple entities, you may want to consider adding a leading digit to differentiate the account numbers for each entity. For example, all account numbers for entity A could start with the number 1, and all account numbers for entity B could start with the number 2.

By following these recommendations, you can create a structured and organized chart of accounts that provides detailed information for financial reporting and analysis.

A 7-Digit main accounts and 3 Digit sub-accounts in a Chart of accounts, Is there any recommendations for an account structure?

A 7-digit main accounts and 3-digit sub-accounts structure in a chart of accounts provides even more granularity and detail than a 6-digit main accounts structure. Here are some recommendations for structuring your accounts:

1. Identify your main account categories: Start by identifying the main categories of accounts that you want to track. For example, you may have categories for assets, liabilities, equity, revenue, and

expenses.

2. Assign the first three digits to the main account categories: Use the first three digits of the account number to identify the main account category. For example, all asset accounts could start with the number 100, all liability accounts could start with the number 200, and so on.
3. Assign the next four digits to the individual accounts: Use the next four digits of the account number to identify individual accounts within each category. For example, an individual accounts receivable account could be numbered 1001000, and an individual accounts payable account could be numbered 2001000.
4. Assign the next three digits to subcategories: Use the next three digits of the account number to identify the subcategory of the individual account. For example, all accounts receivable sub-accounts could start with the number 1001100, and all accounts payable sub-accounts could start with the number 2001100.
5. Consider adding a leading digit for multiple entities: If you have multiple entities, you may want to consider adding a leading digit to differentiate the account numbers for each entity. For example, all account numbers for entity A could start with the number 1, and all account numbers for entity B could start with the number 2.

By following these recommendations, you can create a highly detailed and organized chart of accounts that provides extensive information for financial reporting and analysis.

An 8-Digit main accounts and 3 Digit sub-accounts in a Chart of accounts, Is there any recommendations for an account structure?

An 8-digit main accounts and 3-digit sub-accounts structure in a chart of accounts can provide a high level of granularity and detail in your financial reporting. Here are some recommendations for structuring your accounts:

1. Identify your main account categories : Start by identifying the main categories of accounts that you want to track. For example, you may have categories for assets, liabilities, equity, revenue, and expenses.
2. Assign the first two digits to the main account categories: Use the first two digits of the account number to identify the main account category. For example, all asset accounts could start with the number 10, all liability accounts could start with the number 20, and so on.
3. Assign the next two digits to subcategories: Use the next two digits of the account number to identify the subcategory of the main account. For example, all accounts receivable sub-accounts could start with the number 1100, and all accounts payable sub-accounts could start with the number 2100.

4. Assign the last three digits to the individual accounts: Use the last three digits of the account number to identify individual accounts within each subcategory. For example, an individual accounts receivable account could be numbered 110001, and an individual accounts payable account could be numbered 210001.

5. Consider adding a leading digit for multiple entities: If you have multiple entities, you may want to consider adding a leading digit to differentiate the account numbers for each entity. For example, all account numbers for entity A could start with the number 1, and all account numbers for entity B could start with the number 2.

By following these recommendations, you can create a structured and organized chart of accounts that provides detailed information for financial reporting and analysis.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's User-Friendly UI

Chart of Accounts - Sub-accounts

What is Sub-accounts in a Chart of Accounts?

A Chart of Accounts is a structured list that includes the names and unique codes for all accounts. It's used to categorize and record financial transactions within an organization. This chart is a fundamental component of a company's financial accounting system, facilitating the organization and tracking of financial data.

In osFinancials5/TurboCASH5, sub-accounts can be created and used for any account, with the exception of three control accounts: Debtors control (Accounts receivable), Creditors control (Accounts payable), and Retained earnings account. Sub-accounts help further categorize and provide detailed information about specific accounts to meet specific organizational needs.

Sub-accounts are hierarchical, linked to parent accounts or main accounts, and provide a more detailed and organized structure within the Chart of Accounts. They allow for specific components of a main account. For instance, the main account "*Vehicle Expenses*" can be subdivided using sub-accounts to record specific costs related to motor vehicles, including Fuel, Licence Fees, Insurance, Maintenance, Repairs, and more. This breakdown helps with budgeting and facilitates the management of the main account's total within the sub-accounts' details.

Are there any recommendations when to use sub-accounts in the chart of accounts?

In osFinancials5/TurboCASH5, you can use Main accounts with a range of 3 to 8 digits in the Chart of Accounts. Additionally, osFinancials5/TurboCASH5 allows you to include 3-digit Sub-accounts, as needed, for each Main account based on your specific requirements.

There are several recommendations for when to use sub-accounts in a chart of accounts:

1. To provide more detail: Sub-accounts can be used to provide more detailed information about a specific account. For example, a company might use a sub-account to track expenses for a specific department or project within a larger expense account.
2. To track multiple locations or divisions: If a company has multiple locations or divisions, sub-accounts can be used to track financial information separately for each location or division. This can help management make more informed decisions about allocating resources and identifying areas for improvement.
3. To comply with regulatory requirements: In some industries, regulatory bodies may require companies to track financial information in a specific way. Sub-accounts can be used to ensure that financial data is recorded and reported in accordance with these requirements.
4. To facilitate financial analysis: Sub-accounts can make it easier to analyze financial data by providing more granular information. For example, a company might use sub-accounts to track sales by product line, making it easier to identify which products are driving revenue growth.
5. To simplify financial reporting: Sub-accounts can be used to simplify financial reporting by grouping related accounts together. For example, a company might use sub-accounts to group all travel-related expenses together, making it easier to prepare financial statements and tax returns.

Overall, the decision to use sub-accounts in a chart of accounts should be based on the specific needs of the organization. While sub-accounts can provide more detail and facilitate financial analysis, they can also add complexity to the chart of accounts and make it more difficult to maintain.

Example : Sub-accounts for a Main account Expense

The exact structure and naming conventions for sub-accounts in a Chart of Accounts can vary between organizations, depending on their specific needs and accounting practices.

Here's an example to illustrate how sub-accounts work within a Chart of Accounts:

Account	*Account name /*	*Amount*

code	Description		
G6800-000	Motor Vehicle Expenses	Main account (Total of the balances of all Sub accounts)	$ 4.000
G6800-010	Fuel and oil	Sub-account - Tracks expenses related to Fuel and oil	$ 1,000
G6800-020	Vehicle - Insurance	Sub-account - Tracks expenses related to insurance premiums paid for motor vehicles.	$ 1,200
G6800-030	Vehicle - Maintenance and repairs	Sub-account - Tracks expenses related to maintenance and repairs paid for motor vehicles.	$ 800
G6800-040	Vehicle - Registration and Licence fees	Sub-account - Tracks expenses related to registration and licence fees paid for motor vehicles.	$ 700
G6800-050	Vehicle - Tolls and parking fees	Sub-account - Tracks expenses related to toll fees and parking fees paid for motor vehicles.	$ 300
G6800-060	Vehicle - Traffic fines / Vehicle violation expenses	Sub-account - Tracks expenses related to traffic fines and traffic violations paid for motor vehicles.	$0

In this example, "*Motor Vehicle Expenses*" is a parent account or main account in the Chart of Accounts, and it has several sub-accounts that provide more detail about different expense categories.

Sub-accounts help organizations track their financial transactions with greater precision and facilitate the preparation of financial statements, such as the income statement and balance sheet, by breaking down income and expenses into specific categories. This hierarchical structure also makes it easier to monitor and analyse financial performance at various levels of detail.

This example of sub-accounts in a Chart of Accounts offers a clear illustration of how sub-accounts are used to provide detailed information and structure within the Chart of Accounts.

Example : Sub-accounts for a Main account Assets

Another example of sub-accounts within a Chart of Accounts, particularly related to tracking assets. This

example highlights the use of sub-accounts to break down and track the value and details of assets over time. In this case, it's specifically related to motor vehicles as an asset.

The hierarchical structure helps in providing a comprehensive view of the assets on the financial statements. To summarize:

Account code	*Account name / Description*		*Amount*
G1540000	*Vehicles - Book value*	*Main account (This account tracks the Book value of Motor vehicles)*	*$50,000*
G1540010	*Vehicles at cost*	*Sub-account - Tracks the cost of purchase transactions of the assets.*	*$100,000*
G1540020	*Accumulated depreciation - Vehicles*	*Sub-account - Tracks the depreciation accumulated over the lifespan of the motor vehicle.*	*$50,000*

The total value of the main account, "*Vehicles - Book value of Motor vehicles*" would be $50,000, which can be reported on financial statements such as the balance sheet. Sub-accounts, in this case, provide the necessary breakdown to understand how the book value is derived from the cost of purchase and the accumulated depreciation.

The total value of the main account, "*Motor Vehicles - Net Value*" represents the book value or holding value of the asset (in this example $50,000) and is derived by subtracting the accumulated depreciation (in this example $50,000) from the asset's cost (in this example $100,000). It provides a clear reflection of the net value of the motor vehicles on the balance sheet.

Sub-accounts, in this case, provide the necessary breakdown to understand how the book value is derived from the cost of purchase and the accumulated depreciation.

This structure allows organizations to effectively manage and report the value and condition of their assets in a clear and detailed manner, which is essential for financial management and compliance with accounting standards.

Example : Sub-Accounts for a Main Account - Tax VAT/GST/Sales Tax

In the Chart of Accounts, the Tax (VAT/GST/Sales tax) accounts are typically maintained under the "VAT - Control" main account, categorized under "*Current Liabilities*" on the Balance Sheet. Individual tax accounts within the "VAT - Control" account are created as sub-accounts to represent different tax types. These sub-accounts detail Output tax and Input tax percentages and calculate these taxes as either exclusive or inclusive percentages of transaction amounts.

Structure within the Chart of Accounts:

Account code / Tax code	Account name / Description		Tax percentage	Account type	Amount
G850-000	VAT - Control - 15%	Main account - This main account, indicated with a "G" prefix. This main account summarizes VAT payable to the tax authority.	Not applicable	General ledger Balance sheet	70
T860-010	Output VAT - 15%	Sub-account for Output tax. Contains transactions and Output VAT charged on sales at a rate of 15%.	15%	Tax type	
T860-020	Input VAT - Standard rate -15%	Sub-account for Input VAT on standard goods. Contains transactions and Input VAT levied on purchases at a rate of 15%.	15%	Tax type	
T860-030	Input VAT - Capital goods -15%	Sub-account for Input VAT on capital goods. Contains transactions and Input VAT levied on purchases at a rate of 15%.	15%	Tax type	
T860-040	Zero-rated VAT - 0%	Sub-account for Zero-rated VAT. Contains transactions and Input VAT levied on purchases for goods with a rate of 0%.	0%	Tax type	
G850-100	VAT - Payment - 15%	This sub-account, indicated with a "G" prefix, is a sub-account under "VAT CONTROL ACCOUNT - 15%". This sub-account records all payments to be remitted to the tax authority if Output VAT exceeds Input VAT, as well as refunds received from the tax authority if Input VAT exceeds Output VAT.	Not applicable	General ledger Balance sheet	

- Prefixes for Tax Codes: VAT codes or sub-accounts, indicated with a "*T*" prefix, specifying the applicable VAT code's percentage (e.g., 15% or 0%).
- General Ledger Accounts:
    - VAT - Control Account- 15%: This main account, indicated with a "G" prefix, is a General ledger -Balance sheet sub-account. Under this "VAT - Control - 15%" account, sub-accounts is

created as a "*Tax*" type account which the percentages for VAT is specified.

- VAT Payment Account - 15%: This sub-account, indicated with a "G" prefix, is a General ledger -Balance sheet sub-account under "VAT - Control - 15%" main account. It records payments to be remitted to the tax authority and refunds received, depending on the VAT balance.

Note that this example is a simplified version, specific to the South African Revenue Services (SARS), and may not cover all aspects. It illustrates the fundamental structure of VAT accounts in the Chart of Accounts within osFinancials5/TurboCASH5. It's essential to tailor the structure of VAT sub-accounts to align with VAT returns based on your specific circumstances and requirements.

Tax regulations and VAT schemes can vary significantly from one country to another. Even within a single country, different VAT schemes and regulations may apply to specific businesses and circumstances.

In the United Kingdom (UK), for instance, there are various VAT schemes, including the Standard VAT Scheme, the Flat Rate VAT Scheme, the Cash Accounting Scheme, and more. Each of these schemes has its own rules and requirements, and businesses may choose the one that best suits their needs.

When setting up a Chart of Accounts and sub-accounts for VAT in osFinancials5/TurboCASH5 it's essential to consider the specific VAT schemes, rules, and reporting requirements relevant to your country and your business type. This might involve customizing the Chart of Accounts and sub-accounts to align with your unique circumstances, ensuring that you can accurately track, calculate, and report VAT in compliance with local regulations.

The following examples of the "Full Structure of VAT accounts and VAT-codes in the Chart of Accounts" and the alignment to the relevant fields or boxes on VAT Returns"or VAT-declarations is available in this documentation:

- *Value Added Tax (VAT) - South Africa - The "Full Structure of VAT accounts in the Chart of Accounts and the VAT Return" The stricture South African VAT-accounts and VAT-codes of the Chart of Accounts is aligned with the VAT201-return.*
- *Value Added Tax (VAT) - United Kingdom - Various schemes for VAT may be applicable for various scenarios. The most commonly used VAT Standard rate scheme is documented as an example of the VAT-account and VAT-codes structure in Chart of Accounts for the United Kingdom (UK) to match the various Boxes on the UK VAT return.. "VAT Standard Rate Scheme - Structure of VAT Accounts in the Chart of Accounts"*

Working with a knowledgeable accountant or tax advisor who is familiar with the tax laws in your country can be extremely helpful in setting up your Chart of Accounts to meet your VAT reporting and compliance needs.

Control Accounts and Sub-Accounts

Debtors Control (Accounts Receivable)

The Debtor Control Account represents the total accounts receivable owed by all debtors (customers/clients) and is typically displayed in the General Ledger. Individual debtor accounts are housed in a subsidiary ledger, commonly referred to as the "*Debtors Ledger*" or "*Accounts Receivable Ledger*".

In the General Ledger:

- The Debtor Control Account serves as a summary account, displaying the total accounts receivable owed by all debtors (customers/clients). This account is reported in the "*Current Assets*" section of the Balance Sheet.

In the Debtors Ledger:

- The individual debtor accounts are maintained in the subsidiary ledger, often referred to as the "*Debtors Ledger*" or "*Accounts Receivable Ledger*".
- The total amount in the "*Debtors Ledger*" must always balance with the outstanding amount in the "*Debtors Control*" or "*Accounts Receivable*" account in the General Ledger.

Each debtor's account within the Debtors Ledger functions as a sub-account of the Debtor Control Account, providing detailed information about the specific amounts owed by each customer. This includes transactions, balances, and relevant details.

Each individual debtor account contains specific information, such as contact details, postal and delivery addresses, accounting terms (e.g., settings for open item accounts, discount and interest percentages, charge amounts, fixed amounts, and more).

Using sub-accounts for individual debtors in the Debtors Ledger facilitates the tracking of amounts owed by different customers and allows for specific and detailed management of accounts receivable. This breakdown is essential for effective management and collection of outstanding debts.

A range of reports is available to manage debtor accounts in the Debtors Ledger, such as listings, transactions, credit control, ageing reports, and statements.

This structure ensures a clear separation between the summary account (Debtor Control Account) in the General Ledger and the detailed individual debtor accounts in the subsidiary ledger, enhancing the management and tracking of accounts receivable.

Creditors Control (Accounts Payable)

The Creditors Control Account represents the total accounts payable owed to all creditors (suppliers) and

is typically displayed in the General Ledger. Individual creditor accounts are maintained in a subsidiary ledger, commonly referred to as the "*Creditors Ledger*" or "*Accounts Payable Ledger*".

In the General Ledger:

- The Creditors Control Account functions as a summary account, displaying the total accounts payable owed to all creditors (suppliers). This account is reported in the "*Current liabilities*" section of the Balance Sheet.

In the Creditors Ledger:

- The individual creditor accounts are housed in the subsidiary ledger, often referred to as the "*Creditors Ledger*" or "*Accounts Payable Ledger*".
- The total amount in the "*Creditors Ledger*" must always balance with the outstanding amount in the "*Creditors Control*" or "*Accounts Payable*" account in the General Ledger.

Each creditor's account within the Creditors Ledger serves as a sub-account of the Creditor Control Account, offering detailed information about the specific amounts owed to each supplier. This includes transactions, balances, and relevant details.

Each individual creditor account contains specific information, such as contact details, postal and delivery addresses, accounting terms (e.g., settings for open item accounts, charge amounts, and more).

Using sub-accounts for individual creditors in the Creditors Ledger aids in tracking amounts owed to different suppliers and allows for specific and detailed management of accounts payable. This breakdown is vital for effectively managing and making payments for outstanding debts to suppliers.

A range of reports is available to manage creditor accounts in the Creditors Ledger, such as listings, transactions, credit control, ageing reports, and remittance advises.

This structure ensures a clear separation between the summary account (Creditors Control Account) in the General Ledger and the detailed individual creditor accounts in the subsidiary ledger, enhancing the management and tracking of accounts payable.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's CHM Help File Creation Features

Chart of Accounts - Recommendations to configure - GAAP and IFRS

What recommendations is suggested to configure a chart of accounts, accounting groups and financial categories to accommodate GAAP or IFRS?

When setting up a database chart of accounts, accounting groups, and financial categories to accommodate Generally Accepted Accounting Principles (GAAP) or International Financial Reporting Standards (IFRS), the following recommendations may be considered:

1. Start with a standardized chart of accounts: Both GAAP and IFRS have standard chart of accounts that can be used as a starting point. A standardized chart of accounts will ensure consistency in reporting and facilitate financial analysis.
2. Use a hierarchical structure: Organize accounts in a hierarchical structure that reflects the company's organizational structure. This will provide a logical and easy-to-understand framework for financial reporting.
3. Group accounts by type: Categorize accounts based on their type, such as assets, liabilities, equity, revenue, and expenses. This will ensure that financial statements are organized in accordance with GAAP or IFRS.
4. Use standard accounting codes: Assign standardized accounting codes to each account to facilitate data entry and analysis. Standard codes will also make it easier to compare financial data across different organizations and industries.
5. Consider local regulations: Depending on the country or region where the company operates, there may be local regulations that affect the chart of accounts and financial reporting. Consider these regulations when setting up the database.
6. Allow for flexibility: Allow for some flexibility in the chart of accounts to accommodate changes in the company's organizational structure or accounting needs. This will help ensure that the chart of accounts remains relevant and useful over time.

By following these recommendations, companies can set up a database chart of accounts, accounting groups, and financial categories that is compliant with GAAP or IFRS and provides a solid foundation for financial reporting and analysis.

What recommendations is suggested to configure a chart of accounts, accounting groups and financial categories to accommodate IFRS for SMEs?

When configuring a chart of accounts, accounting groups, and financial categories to accommodate IFRS for SMEs, the following recommendations can be considered:

1. Understand the IFRS for SMEs: Familiarize yourself with the requirements and principles outlined in the IFRS for SMEs. Gain a clear understanding of the specific accounting treatments and disclosures required for various transactions and events.
2. Follow the framework: Structure your chart of accounts, accounting groups, and financial categories in accordance with the framework provided by the IFRS for SMEs. This ensures consistency and compliance with the standard.
3. Use standard account codes: Adopt standard account codes and numbering conventions that align with the IFRS for SMEs. This facilitates easier identification and categorization of accounts.
4. Reflect reporting requirements: Consider the reporting requirements of the IFRS for SMEs when designing your chart of accounts. Ensure that the accounts and categories capture the necessary information to prepare the required financial statements, such as the statement of financial position, statement of comprehensive income, statement of changes in equity, and statement of cash flows.
5. Consider industry-specific needs: Take into account any industry-specific considerations when configuring your chart of accounts. Some industries may have unique requirements or specific reporting needs that should be accommodated in the chart of accounts structure.
6. Maintain flexibility: Design your chart of accounts in a way that allows for future changes or updates. As your business evolves or new accounting standards are introduced, having a flexible chart of accounts can facilitate adjustments without significant disruptions.
7. Seek professional advice: If you're unsure about specific requirements or need assistance in configuring your chart of accounts, consider consulting with an accounting professional or an expert knowledgeable in IFRS for SMEs. They can provide guidance tailored to your specific business and help ensure compliance with the standard.

Remember, the configuration of the chart of accounts should be aligned with the specific needs of your business, while still adhering to the principles and requirements of IFRS for SMEs.

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-

Step Guide

Chart of Accounts - Recommendations to configure - IFRS for SMEs

What recommendations is suggested to configure a chart of accounts, accounting groups and financial categories to accommodate IFRS for SMEs?

When configuring a chart of accounts, accounting groups, and financial categories to accommodate IFRS for SMEs, the following recommendations can be considered:

1. Understand the IFRS for SMEs: Familiarize yourself with the requirements and principles outlined in the IFRS for SMEs. Gain a clear understanding of the specific accounting treatments and disclosures required for various transactions and events.
2. Follow the framework: Structure your chart of accounts, accounting groups, and financial categories in accordance with the framework provided by the IFRS for SMEs. This ensures consistency and compliance with the standard.
3. Use standard account codes: Adopt standard account codes and numbering conventions that align with the IFRS for SMEs. This facilitates easier identification and categorization of accounts.
4. Reflect reporting requirements: Consider the reporting requirements of the IFRS for SMEs when designing your chart of accounts. Ensure that the accounts and categories capture the necessary information to prepare the required financial statements, such as the statement of financial position, statement of comprehensive income, statement of changes in equity, and statement of cash flows.
5. Consider industry-specific needs: Take into account any industry-specific considerations when configuring your chart of accounts. Some industries may have unique requirements or specific reporting needs that should be accommodated in the chart of accounts structure.
6. Maintain flexibility: Design your chart of accounts in a way that allows for future changes or updates. As your business evolves or new accounting standards are introduced, having a flexible chart of accounts can facilitate adjustments without significant disruptions.
7. Seek professional advice: If you're unsure about specific requirements or need assistance in configuring your chart of accounts, consider consulting with an accounting professional or an expert knowledgeable in IFRS for SMEs. They can provide guidance tailored to your specific business and help ensure compliance with the standard.

Remember, the configuration of the chart of accounts should be aligned with the specific needs of your

business, while still adhering to the principles and requirements of IFRS for SMEs.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Chart of Accounts - Legislation ownership

What legislation for ownership types a accounting database (Chart of Accounts) should be considered?

The legislation for ownership types and their impact on accounting databases, including the Chart of Accounts, can also vary depending on the country and jurisdiction in which the business is located.

For example, in some countries, there may be different legal structures for businesses, such as sole proprietorships, partnerships, limited liability companies, and corporations. Each of these structures has different rules and regulations regarding financial reporting and accounting practices, which can impact the chart of accounts.

In addition, the ownership type can also impact the chart of accounts in terms of the level of detail required for financial reporting. For example, a sole proprietorship may have a simpler chart of accounts compared to a corporation with multiple subsidiaries and complex financial transactions.

Overall, businesses should consult with their local accounting and legal professionals to ensure they are following the applicable laws and regulations related to their ownership type and accounting practices, including the chart of accounts.

The legislation for setting up an accounting database, including a Chart of Accounts, can vary depending on the country and jurisdiction in which the business is located. Generally, there are laws and regulations that businesses need to follow when it comes to financial reporting, including the way they organize and present financial information.

In many countries, there are accounting standards and regulations that specify the minimum requirements for the Chart of Accounts. For example, in the United States, the Generally Accepted Accounting Principles (GAAP) provide guidance on how to structure the chart of accounts.

In addition to accounting standards, businesses may also need to comply with tax laws and regulations that impact the chart of accounts. For example, in some countries, there are specific tax codes that businesses must use when categorizing their financial transactions in the chart of accounts.

Overall, when setting up a chart of accounts, businesses should consult with their local accounting and tax

professionals to ensure they are following the applicable laws and regulations.

What legislation for ownership types a accounting database (Chart of Accounts) should be considered?

The legislation for ownership types and their impact on accounting databases, including the chart of accounts, can also vary depending on the country and jurisdiction in which the business is located.

For example, in some countries, there may be different legal structures for businesses, such as sole proprietorships, partnerships, limited liability companies, and corporations. Each of these structures has different rules and regulations regarding financial reporting and accounting practices, which can impact the chart of accounts.

In addition, the ownership type can also impact the chart of accounts in terms of the level of detail required for financial reporting. For example, a sole proprietorship may have a simpler chart of accounts compared to a corporation with multiple subsidiaries and complex financial transactions.

Overall, businesses should consult with their local accounting and legal professionals to ensure they are following the applicable laws and regulations related to their ownership type and accounting practices, including the chart of accounts.

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Chart of Accounts - Business ownership

What is the types of ownership of a business?

There are several types of ownership structures for a business, including:

1. Sole proprietorship: A business owned and operated by one individual. The owner has full control over the business and is personally responsible for all debts and liabilities.
2. Partnership: A business owned and operated by two or more individuals. Partners share profits and losses, and each partner is personally responsible for the debts and liabilities of the partnership.
3. Limited Liability Company (LLC): A business structure that provides limited liability protection for its owners (called members). This means that the members are not personally responsible for the debts and liabilities of the business.
4. Corporation: A legal entity that is separate from its owners (called shareholders). The corporation is responsible for its own debts and liabilities, and shareholders' liability is limited to the amount of their

investment in the corporation.

5. Cooperative: A business owned and operated by its members, who share in the profits and decision-making of the business. Cooperatives can take many forms, including agricultural cooperatives, credit unions, and housing cooperatives.
6. Franchise: A business model where an individual (the franchisee) is granted the right to operate a business using the trademark, products, and services of another company (the franchisor) in exchange for fees and royalties.

The type of ownership structure chosen for a business can have legal and financial implications, and it's important to consider the benefits and drawbacks of each option before making a decision.

Is there specific legislation required for the ownership structures of a business?

Yes, there are often specific laws and regulations that govern the ownership structures of businesses.

For example, in the United States, the formation of corporations is governed by state laws, and each state has its own statutes that outline the requirements for incorporating a business. Similarly, the creation and operation of LLCs are regulated by state law, and each state has its own LLC statutes that specify the requirements for forming and running an LLC.

Partnerships are generally governed by state law as well, and some states require partnerships to register with the state or file certain documents with the state to operate legally.

Additionally, there are federal laws and regulations that apply to certain types of businesses, such as franchises, that must be followed.

Overall, it's important for business owners to understand the legal requirements and regulations that apply to their chosen ownership structure in order to operate their business legally and effectively.

Business ownership types how do these types of ownership reflect in the Chat of accounts?

There are several types of business ownership, including sole proprietorship, partnership, limited liability company (LLC), and corporation. The type of ownership will affect the way that the company's financial transactions are recorded in the chart of accounts.

1. Sole Proprietorship: In a sole proprietorship, the business is owned by a single person. The chart of accounts for a sole proprietorship will typically include accounts for revenue, expenses, assets, liabilities, and owner's equity.

2. Partnership: In a partnership, the business is owned by two or more people. The chart of accounts for a partnership will typically include accounts for revenue, expenses, assets, liabilities, and partner's equity.
3. Limited Liability Company (LLC): An LLC is a type of business ownership that combines the liability protection of a corporation with the tax benefits of a partnership. The chart of accounts for an LLC will typically include accounts for revenue, expenses, assets, liabilities, and members' equity.
4. Corporation: A corporation is a separate legal entity from its owners, and it can be owned by shareholders. The chart of accounts for a corporation will typically include accounts for revenue, expenses, assets, liabilities, and shareholders' equity.

In general, the chart of accounts for each type of ownership will be similar in terms of the accounts included, but the names and details of the accounts may differ slightly. It's important to tailor the chart of accounts to the specific needs of the business, regardless of the type of ownership.

What are the common legal requirements for businesses or organisations?

The specific legal requirements for businesses or organizations can vary depending on the country, industry, and type of business. However, there are some common legal requirements that most businesses or organizations need to comply with. These may include:

1. Business registration: Most businesses are required to register with the government and obtain a business licence or permit to operate legally.
2. Taxation: Businesses are typically required to register with the tax authorities and pay taxes on their income, as well as collect and remit taxes on behalf of employees or customers.
3. Employment laws: Businesses must comply with labor laws and regulations, including minimum wage requirements, overtime rules, and anti-discrimination laws.
4. Health and safety regulations: Businesses may be subject to health and safety regulations that govern workplace conditions and employee safety.
5. Data protection and privacy laws: Businesses that collect or process personal data may be subject to data protection and privacy laws that govern how they handle this information.
6. Environmental regulations: Businesses may be required to comply with environmental regulations that govern how they manage waste, emissions, and other environmental impacts.
7. Intellectual property laws: Businesses may need to protect their intellectual property rights through patents, trademarks, or copyrights, and may be subject to laws governing these rights.

These are just a few examples of the common legal requirements that businesses or organizations may need to comply with. It's important for business owners to understand the specific legal requirements that apply to their industry aBusiness ownership types how do these types of ownership reflect in the Chat of accounts?

Chart of accounts and business ownership

There are several types of business ownership, including sole proprietorship, partnership, limited liability company (LLC), and corporation. The type of ownership will affect the way that the company's financial transactions are recorded in the chart of accounts.

1. Sole Proprietorship: In a sole proprietorship, the business is owned by a single person. The chart of accounts for a sole proprietorship will typically include accounts for revenue, expenses, assets, liabilities, and owner's equity.
2. Partnership: In a partnership, the business is owned by two or more people. The chart of accounts for a partnership will typically include accounts for revenue, expenses, assets, liabilities, and partner's equity.
3. Limited Liability Company (LLC): An LLC is a type of business ownership that combines the liability protection of a corporation with the tax benefits of a partnership. The chart of accounts for an LLC will typically include accounts for revenue, expenses, assets, liabilities, and members' equity.
4. Corporation: A corporation is a separate legal entity from its owners, and it can be owned by shareholders. The chart of accounts for a corporation will typically include accounts for revenue, expenses, assets, liabilities, and shareholders' equity.

In general, the chart of accounts for each type of ownership will be similar in terms of the accounts included, but the names and details of the accounts may differ slightly. It's important to tailor the chart of accounts to the specific needs of the business, regardless of the type of ownership.

What information should a business display on its reports and invoices?

A business report and invoice should include certain key information to ensure that it is clear and informative for the recipient. The specific information that should be included may vary depending on the type of business and the nature of the transaction, but here are some common elements that are typically included:

1. Business name and logo: The report or invoice should clearly display the name and logo of the business to identify the sender.

2. Contact information: The report or invoice should include the business's contact information, including a phone number, email address, and physical address.
3. Date: The date of the report or invoice should be clearly displayed to identify when the transaction occurred.
4. Invoice or report number: A unique invoice or report number should be assigned and displayed on the document to track and reference the transaction.
5. Itemized list: For an invoice, an itemized list of products or services provided should be included, along with their prices and quantities. For a report, relevant data and information should be presented in an organized and logical manner.
6. Payment terms: The invoice should include the payment terms, including the due date, acceptable forms of payment, and any applicable discounts or late fees.
7. Tax information: If applicable, the invoice should include the amount of taxes charged and any tax identification numbers associated with the business.
8. Terms and conditions: The report or invoice may include additional terms and conditions related to the transaction, such as warranties or return policies.

By including these key elements, a business report or invoice can effectively communicate important information and facilitate efficient and accurate transactions.nd location in order to operate their business legally and avoid potential penalties or legal issues.

In addition to this, what specific information regarding the business ownership should be printed on reports?

The specific information regarding the business ownership that should be printed on reports may vary depending on the type of report and the jurisdiction in which the business operates. However, here are some common pieces of information that may be relevant:

1. Legal business name: The legal business name should be included on all reports, as it identifies the entity responsible for the transaction.
2. Business structure: The type of business structure, such as sole proprietorship, partnership, limited liability company (LLC), or corporation, should be clearly indicated on the report.
3. Business address: The business address should be included on the report, as it identifies the location of the business.
4. Business registration number: The business registration number, such as a tax ID number or employer identification number (EIN), should be included on the report as required by law.

5. Ownership information: For a partnership or corporation, the names of the owners or shareholders should be included on the report, along with the percentage of ownership for each.
6. Board of directors: For a corporation, the names of the board of directors should be included on the report.
7. Licences and permits: If the business is required to hold any licences or permits to operate in a particular jurisdiction, these should be listed on the report.

Including this information on business reports can help to establish the identity and ownership of the business, which is important for legal and regulatory compliance purposes.

What are the legal requirements and structure of a chart of accounts for a Non-Profit-Organisation?

The legal requirements and structure of a chart of accounts for a non-profit organization may vary depending on the country or region in which the organization operates. In general, a chart of accounts is a listing of all the accounts used in an organization's financial accounting system, and it provides a framework for organizing financial transactions and preparing financial reports.

Here are some general considerations for creating a chart of accounts for a non-profit organization:

1. Legal Requirements: It is important to check with the relevant regulatory bodies in your country or region to determine any legal requirements for a chart of accounts for a non-profit organization. For example, in the United States, non-profit organizations are required to follow the Financial Accounting Standards Board (FASB) guidelines for non-profit accounting.
2. Structure: The structure of a non-profit organization's chart of accounts should reflect the specific activities and financial transactions of the organization. It should be designed to track revenues and expenses by program or activity, and to differentiate between restricted and unrestricted funds.
3. Accounts: The chart of accounts should include accounts for all financial transactions related to the organization's operations, including revenue, expenses, assets, liabilities, and equity. Accounts should be grouped together in a logical manner and assigned a unique account number for easy reference and tracking.
4. Fund Accounting: Non-profit organizations typically use fund accounting, which means that the organization's finances are divided into different funds based on the source of the funds or the purpose of the funds. The chart of accounts should reflect these different funds and provide a way to track financial transactions within each fund.
5. Reporting: The chart of accounts should be designed to facilitate the preparation of financial reports, including the statement of financial position (balance sheet), statement of activities (income statement),

and statement of cash flows. The accounts should be organized in a way that makes it easy to generate these reports and to provide detailed information about the organization's financial position and activities.

Overall, the chart of accounts for a non-profit organization should be designed to provide a clear and accurate picture of the organization's financial position and activities, and to meet any legal requirements for financial reporting. It should be regularly reviewed and updated to ensure that it remains relevant and useful for the organization's financial management and reporting needs.

What types of companies, for example Limited Liability Company (LLC), is there in various countries?

There are many different types of companies that exist in various countries, each with its own unique legal structure, governance rules, and tax implications. Here are some examples of common types of companies in different countries:

1. United States:
    - Limited Liability Company (LLC): A popular type of company that offers limited liability protection to its owners (known as members) while being treated as a pass-through entity for tax purposes.
    - Corporation: A company that is treated as a separate legal entity from its owners (known as shareholders) and offers limited liability protection. It can be taxed as a separate entity or as a pass-through entity if it elects to be taxed as an S-Corporation.
    - Partnership: A company owned by two or more individuals who share profits and losses. Partnerships can be general partnerships, limited partnerships, or limited liability partnerships.
2. United Kingdom:
    - Private Limited Company (Ltd): A company that is privately owned and offers limited liability protection to its owners (known as shareholders).
    - Public Limited Company (PLC): A company that is publicly traded and offers limited liability protection to its owners.
    - Limited Liability Partnership (LLP): A company structure that offers limited liability protection to its owners while being taxed as a partnership.
3. Canada:
    - Corporation: A company that is treated as a separate legal entity from its owners (known as shareholders) and offers limited liability protection. It can be taxed as a separate entity or as a

pass-through entity if it elects to be taxed as a Canadian Controlled Private Corporation (CCPC).

- Cooperative: A company owned and controlled by its members, who share profits and decision-making.
- Sole Proprietorship: A company owned by a single individual who is responsible for all of its debts and liabilities.

4. Australia:
    - Proprietary Limited Company (Pty Ltd): A company that is privately owned and offers limited liability protection to its owners (known as shareholders).
    - Public Company (Limited) (Ltd): A company that is publicly traded and offers limited liability protection to its owners.
    - Partnership: A company owned by two or more individuals who share profits and losses. Partnerships can be general partnerships, limited partnerships, or limited liability partnerships.

These are just a few examples of the many different types of companies that exist in different countries. The legal structure and governance rules for each type of company can vary widely depending on the country and the industry in which the company operates.

What types of companies, for example Limited Liability Company (LLC), is there in South Africa?

In South Africa, there are several types of companies that can be registered under the Companies Act of 2008. Here are some examples of common types of companies in South Africa:

1. Private Company (Pty) Ltd: This is the most common type of company in South Africa. A private company can have between one and 50 shareholders and is not allowed to offer its shares to the public. The shareholders have limited liability for the company's debts, and the company's shares cannot be freely traded on the stock exchange.
2. Public Company (Ltd): A public company can offer its shares to the public and is listed on the stock exchange. It can have an unlimited number of shareholders, and its shares can be freely traded on the stock exchange. The shareholders have limited liability for the company's debts.
3. Personal Liability Company (Inc): A personal liability company is similar to a private company, but the shareholders have personal liability for the company's debts. This type of company is often used by professional service providers, such as doctors or lawyers.
4. Non-Profit Company (NPC): A non-profit company is a company that is not-for-profit and is

established to promote a public benefit. It can be registered as either a public or private company, but it cannot distribute its profits to its members or shareholders.

5. State-Owned Company (SOC): A state-owned company is a company that is wholly or partially owned by the South African government. These companies are established to provide public services or to undertake commercial activities on behalf of the government.

These are some of the most common types of companies in South Africa. The legal requirements, governance rules, and tax implications for each type of company can vary, so it's important to consult with a qualified professional when deciding which type of company is best for your business.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

United Kingdom (UK) - Chart of Accounts - GAAP

Is there a sample chart of accounts for the United Kingdom?

Yes, there are sample charts of accounts available for businesses in the United Kingdom. The specific accounts used may vary depending on the nature of the business, the size of the company, and the industry in which it operates.

Here is a sample Chart of Accounts based on the UK's Generally Accepted Accounting Principles (GAAP):

1. Fixed assets
    - 1000 Buildings
    - 1100 Equipment
    - 1200 Vehicles
    - 1300 Furniture and fittings
    - 1400 Land and buildings
    - 1500 Computer software
    - 1600 Investments in subsidiaries
2. Current assets
    - 2000 Bank and cash
    - 2100 Accounts receivable

- 2200 Inventory
- 2300 Prepaid expenses
- 2400 Investments in shares

3. Liabilities
    - 3000 Bank loans
    - 3100 Trade creditors
    - 3200 Taxation payable
    - 3300 Other creditors
    - 3400 Loans from directors
4. Shareholder's equity
    - 4000 Ordinary shares
    - 4100 Share premium
    - 4200 Retained earnings
5. Revenue
    - 5000 Sales revenue
    - 5100 Other revenue
6. Cost of sales
    - 6000 Direct materials
    - 6100 Direct labour
    - 6200 Factory overheads
7. Operating expenses
    - 7000 Selling and distribution expenses
    - 7100 Administrative expenses
8. Other income and expenses
    - 8000 Gain or loss on sale of assets
    - 8100 Interest income or expense

- 8200 Foreign exchange gain or loss

9. Taxation
    - 9000 Corporation tax
    - 9100 Deferred tax

This is just a sample Chart of Accounts, and businesses can customize it based on their individual requirements. It is recommended that businesses seek the advice of a professional accountant or bookkeeper when setting up their Chart of Accounts to ensure it is accurate and compliant with UK GAAP.

What is the recommended financial categories and account groups for accounts in the United Kingdom Chart of Accounts?

The recommended financial categories and account groups for the United Kingdom Chart of Accounts may vary depending on the specific needs of the organization. However, there are some general categories and groups that are commonly used in UK accounting practices.

1. Assets: This includes all the resources owned by the organization, such as cash, investments, property, plant, and equipment.
2. Liabilities: This includes all the obligations owed by the organization, such as loans, accounts payable, and accrued expenses.
3. Equity: This represents the residual interest in the assets of the organization after deducting liabilities.
4. Revenue: This includes all the income earned by the organization, such as sales revenue, interest income, and other operating income.
5. Expenses: This includes all the costs incurred by the organization, such as wages, rent, utilities, and supplies.

Some account groups that may be used within these categories include:

1. Cash and bank accounts: This includes all the accounts used to manage the organization's cash and bank transactions.
2. Accounts receivable and payable: This includes all the accounts used to manage the organization's sales and purchases.
3. Fixed assets: This includes all the accounts used to manage the organization's property, plant, and equipment.
4. Revenue accounts: This includes all the accounts used to record the organization's income from various sources.

5. Expense accounts: This includes all the accounts used to record the organization's costs associated with its operations.
6. Tax accounts: This includes all the accounts used to manage the organization's tax obligations.
7. Equity accounts: This includes all the accounts used to record the organization's equity transactions, such as share capital, retained earnings, and dividends.

Overall, the recommended financial categories and account groups for the United Kingdom Chart of Accounts should be tailored to meet the specific needs of the organization and should comply with UK accounting standards and regulations.

What is a full list of accounts suggested in the chart of accounts for UK?

The Chart of Accounts for the UK may vary depending on the industry and specific needs of the business, but here is a general list of accounts that may be included:

1. Assets:
    - Current assets:
        - Cash
        - Bank accounts
        - Accounts receivable
        - Inventory
        - Prepaid expenses
    - Non-current assets:
        - Property, plant, and equipment
        - Investments
        - Goodwill
2. Liabilities:
    - Current liabilities:
        - Accounts payable
        - Short-term loans
        - Accrued expenses

- Non-current liabilities:
  - Long-term loans
  - Deferred tax liabilities
  - Pension liabilities

3. Equity:
   - Share capital
   - Retained earnings
4. Revenue:
   - Sales revenue
   - Interest income
   - Other revenue
5. Expenses:
   - Cost of goods sold
   - Salaries and wages
   - Rent and utilities
   - Depreciation and amortization
   - Marketing and advertising
   - Taxes and licences
   - Interest expense
   - Other expenses

Again, this is a general list and may vary depending on the specific needs of the business. It's always a good idea to consult with an accountant or financial advisor to determine the best Chart of Accounts for your business.

What is examples of operating expenses and administrative expenses?

Operating expenses are expenses directly related to the production and sale of goods or services, while administrative expenses are costs associated with the general management and administration of the

business. Here are some examples of operating expenses and administrative expenses:

1. Operating expenses:
    - Cost of goods sold (COGS)
    - Raw materials
    - Manufacturing labor
    - Freight and shipping
    - Sales commissions
    - Marketing and advertising expenses
    - Rent and utilities for production facilities
    - Repairs and maintenance for production equipment
    - Packaging materials
    - Supplies used in production
2. Administrative expenses:
    - Salaries and wages of administrative staff
    - Rent and utilities for administrative offices
    - Office supplies and equipment
    - Accounting and legal fees
    - Insurance premiums
    - Travel and entertainment expenses for management
    - Depreciation and amortization of non-production assets
    - Information technology expenses such as software and hardware for office use
    - Property taxes and other government fees

It's important to note that some expenses may be classified as both operating and administrative, depending on the nature of the expense and the industry in which the business operates.

What is Selling and distribution expenses?

Selling and distribution expenses are costs associated with marketing, selling, and distributing products or

services. These expenses are typically considered as operating expenses and include:

1. Sales commissions: Commissions paid to sales representatives who generate revenue for the company.
2. Advertising and promotion: Costs associated with promoting and advertising products or services to potential customers, such as print and online ads, billboards, and sponsorship.
3. Freight and shipping: Expenses incurred to transport products from the production facility to the customer, including freight charges, packing materials, and handling fees.
4. Distribution expenses: Costs associated with distributing products to customers, such as warehouse rent, employee salaries, and other related costs.
5. Sales salaries and benefits: Salaries, bonuses, and other benefits paid to sales staff and other personnel involved in the sales and distribution process.
6. Travel expenses: Costs associated with traveling to meet with customers or attend sales conferences, trade shows, or other sales-related events.
7. Customer service expenses: Costs associated with providing customer service, such as call centre expenses, warranty claims, and product returns.
8. Bad debts: Expenses associated with customers who fail to pay their invoices.

Selling and distribution expenses are important to track as they can significantly impact a company's profitability and overall financial health.

What accounts is suggested for payroll in the UK?

For payroll accounting in the UK, some of the key accounts that may be used include:

1. Wages and salaries: This account is used to record the gross amount of wages and salaries paid to employees, including any overtime, bonuses, or other compensation.
2. Employer National Insurance Contributions: This account is used to record the amount of employer national insurance contributions payable to HM Revenue and Customs (HMRC), which is calculated based on the gross salaries and wages paid to employees.
3. Employee National Insurance Contributions: This account is used to record the amount of employee national insurance contributions withheld from employee salaries and wages, which must be paid to HMRC on a monthly basis.
4. PAYE (Pay-as-you-earn) payable: This account is used to record the amount of PAYE tax withheld from employee salaries and wages, which must be paid to HMRC on a monthly basis.

5. Pension contributions: This account is used to record any employer contributions to employee pension schemes, as well as any employee contributions made through salary sacrifice arrangements.
6. Student loan repayments: This account is used to record any student loan repayments made by employees, which are withheld from employee salaries and wages and paid to HMRC on a monthly basis.
7. Other deductions and benefits: This account is used to record any other deductions or benefits provided to employees, such as childcare vouchers, cycle-to-work schemes, or health insurance.

These accounts may be used in conjunction with other accounts in the company's chart of accounts to provide a comprehensive record of payroll transactions and related expenses. It is important to consult with a qualified accountant or payroll specialist to ensure that payroll accounts are set up and managed correctly in accordance with UK regulations and requirements.

Which accounts is Income statement and balance sheet accounts in the Chart of Accounts for payroll transactions in the UK?

In the Chart of Accounts for payroll transactions in the UK, the Income Statement accounts are typically used to record revenues, expenses, gains, and losses related to payroll transactions. The Balance Sheet accounts are used to track the assets, liabilities, and equity related to payroll transactions.

Here's an example of the Income Statement and Balance Sheet accounts that could be used in the Chart of Accounts for payroll transactions in the UK:

Income Statement accounts:

4000 - Gross Pay

4010 - Employee National Insurance Contributions

4020 - Employer National Insurance Contributions

4030 - PAYE Income Tax

4040 - Pension Contributions

4050 - Other Payroll Deductions

4060 - Payroll Processing Fees

4070 - Payroll Software Costs

4080 - Payroll Training Costs

4090 - Other Payroll Expenses

Balance Sheet accounts:

1000 - Cash and Bank

1010 - Accounts Receivable

1020 - Employee Loans and Advances

1500 - Employee PAYE Tax and National Insurance Payable

1510 - Pension Contributions Payable

1520 - Other Payroll Deductions Payable

2000 - Employee Salaries Payable

2010 - Employer National Insurance Contributions Payable

2020 - Other Payroll Expenses Payable

2500 - Employee Loans and Advances Payable

These accounts can be customized based on the specific needs of the business, but they provide a basic framework for recording and tracking payroll transactions in the UK.

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

United Kingdom (UK) - Standard Chart of Accounts (SCOA)

Is there a sample of a chart of accounts for the UK?

Yes, there are several samples of chart of accounts available for businesses operating in the United Kingdom. However, the specific chart of accounts that a business uses will depend on factors such as the nature of the business, its industry, and its accounting practices.

In the UK, the most commonly used chart of accounts is the Standard Chart of Accounts (SCOA), which is used by many businesses, including those in the public sector. The SCOA is a comprehensive framework that provides a standardised structure for financial reporting.

The SCOA includes several categories, such as assets, liabilities, equity, income, and expenses. Within each category, there are subcategories that provide additional detail for financial reporting purposes. For example, under the expenses category, there may be subcategories for salaries and wages, rent, utilities, and advertising expenses.

In addition to the SCOA, businesses may also use other industry-specific charts of accounts or customize

their own based on their specific needs and accounting practices.

It's important to note that the chart of accounts should be regularly reviewed and updated to ensure it accurately reflects the business's financial transactions and complies with applicable laws and regulations.

Is there an example of a Standard Chart of Accounts (SCOA) for the UK?

Yes, there is an example of a Standard Chart of Accounts (SCOA) for the UK. The SCOA provides a standardized framework for financial reporting and includes several categories and subcategories to organize financial transactions.

Here is an example of the SCOA for the UK:

Assets:

1000 - Current assets

1100 - Property, plant, and equipment

1200 - Investment property

1300 - Intangible assets

1400 - Other assets

Liabilities:

2000 - Current liabilities

2100 - Trade and other payables

2200 - Borrowings

2300 - Provisions

2400 - Other current liabilities

2500 - Taxation

Equity:

3000 - Share capital and reserves

3100 - Share capital

3200 - Other reserves

3300 - Retained earnings

Income:

4000 - Income

4100 - Sales

4200 - Interest received

4300 - Dividends received

4400 - Other income

Expenses:

5000 - Cost of sales

5100 - Direct costs

5200 - Depreciation and amortization

5300 - Overheads

5400 - Interest paid

5500 - Taxation

5600 - Other expenses

This is just one example of the SCOA for the UK, and it's important to note that businesses may customize their own chart of accounts based on their specific needs and accounting practices.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

South Africa - Chart of Accounts - SA GAAP and SA GAAP for SMEs

---

SA GAAP for SMEs

South African Generally Accepted Accounting Practice for Small and Medium-sized Entities (SA GAAP for SMEs) is a set of accounting principles and standards specifically tailored for small and medium-sized businesses in South Africa.

SA GAAP for SMEs provides simplified accounting and reporting requirements compared to the full version of SA GAAP, which is based on International Financial Reporting Standards (IFRS).

SA GAAP for SMEs aims to meet the financial reporting needs of smaller entities while considering their resource constraints and the specific characteristics of their operations. It provides a more cost-effective

and less complex framework for financial reporting, enabling SMEs to prepare meaningful financial statements that accurately reflect their financial performance and position.

The key features of SA GAAP for SMEs include:

1. Simplified recognition and measurement: The standard provides simplified criteria for recognizing and measuring assets, liabilities, income, and expenses. It allows for a more straightforward approach compared to the detailed requirements of full SA GAAP/IFRS.
2. Reduced disclosure requirements: SA GAAP for SMEs has streamlined disclosure requirements compared to the full version of SA GAAP/IFRS. This reduces the reporting burden on SMEs while still providing relevant and essential information to users of financial statements.
3. Flexibility in presentation: The standard allows for flexibility in the presentation of financial statements, enabling SMEs to present information in a format that best suits their business and user needs.
4. Exemptions and simplifications: SA GAAP for SMEs provides certain exemptions and simplifications in areas such as goodwill, business combinations, deferred taxes, and complex financial instruments. These exemptions and simplifications help ease the reporting requirements for SMEs.

SA GAAP for SMEs is designed to strike a balance between providing useful financial information and reducing the reporting burden on small and medium-sized entities. It enables SMEs to comply with the local accounting and reporting requirements in South Africa while considering their unique circumstances. However, it's important to note that SA GAAP for SMEs may not be suitable for all entities, and some SMEs may choose to adopt full SA GAAP/IFRS depending on their specific needs and circumstances.

What is the differences between SA GAAP and SA GAAP for SMEs?

The differences between SA GAAP (South African Generally Accepted Accounting Practice) and SA GAAP for SMEs (South African Generally Accepted Accounting Practice for Small and Medium-sized Entities) lie primarily in the complexity, reporting requirements, and applicable accounting standards. Here are the key distinctions:

1. Applicability:
    - SA GAAP: SA GAAP is designed for larger entities, including publicly traded companies, financial institutions, and organizations with complex operations. It follows the full set of International Financial Reporting Standards (IFRS) as adopted by South Africa.
    - SA GAAP for SMEs: SA GAAP for SMEs is specifically tailored for small and medium-sized entities, which generally have fewer reporting resources and less complex operations. It provides a simplified framework based on IFRS, with certain modifications and simplifications

to suit the needs of SMEs.

2. Reporting Requirements:
    - SA GAAP: SA GAAP requires entities to adhere to comprehensive reporting requirements, including detailed disclosure notes, comprehensive financial statement presentation, and various complex accounting standards and principles.
    - SA GAAP for SMEs: SA GAAP for SMEs offers reduced reporting requirements compared to SA GAAP. It provides simplified recognition and measurement criteria, streamlined disclosure requirements, and flexibility in financial statement presentation. It aims to strike a balance between providing meaningful financial information and reducing the reporting burden for SMEs.
3. Complexity:
    - SA GAAP: SA GAAP encompasses the full set of IFRS, which can be complex and extensive. It includes detailed guidance on various accounting topics, such as revenue recognition, financial instruments, leases, and employee benefits.
    - SA GAAP for SMEs: SA GAAP for SMEs simplifies the accounting and reporting requirements, making it less complex compared to SA GAAP. It provides exemptions, simplifications, and reduced disclosure requirements in areas such as goodwill, business combinations, deferred taxes, and complex financial instruments.
4. Chart of Accounts:
    - SA GAAP: SA GAAP follows a standardized chart of accounts framework, which provides specific guidance and codes for different account categories and sub-categories.
    - SA GAAP for SMEs: SA GAAP for SMEs does not provide a specific standard or example chart of accounts. SMEs have more flexibility to design their own chart of accounts based on their specific industry, nature of operations, and reporting needs.

It's important to note that while SA GAAP for SMEs provides simplifications and reduced requirements, SMEs may still choose to adopt SA GAAP (full IFRS) if it better suits their needs or if they have specific reporting obligations, such as being a subsidiary of a larger company or seeking international investors.

What is the differences between SA GAAP for SMEs and IFRS for SMEs in South Africa?

In South Africa, there is a distinction between SA GAAP for SMEs (South African Generally Accepted Accounting Practice for Small and Medium-sized Entities) and IFRS for SMEs (International Financial

Reporting Standards for Small and Medium-sized Entities). Here are the key differences between the two:

1. Applicability:
    - SA GAAP for SMEs: SA GAAP for SMEs is specifically designed for small and medium-sized entities operating in South Africa. It takes into account the local legal and regulatory requirements, as well as the specific characteristics and reporting needs of SMEs in the South African context.
    - IFRS for SMEs: IFRS for SMEs is an international accounting standard developed by the International Accounting Standards Board (IASB) specifically for small and medium-sized entities worldwide. It aims to provide a simplified set of accounting and reporting requirements that are suitable for SMEs globally.
2. Basis and Framework:
    - SA GAAP for SMEs: SA GAAP for SMEs is based on the full version of SA GAAP, which in turn is closely aligned with the International Financial Reporting Standards (IFRS) framework. SA GAAP for SMEs incorporates modifications and simplifications to align with the reporting needs and resource constraints of SMEs in South Africa.
    - IFRS for SMEs: IFRS for SMEs is a separate stand-alone standard developed by the IASB. It is a simplified version of full IFRS, specifically tailored to the needs and capabilities of SMEs globally. It provides a streamlined framework with reduced complexity compared to full IFRS.
3. Reporting Requirements:
    - SA GAAP for SMEs: SA GAAP for SMEs offers simplified reporting requirements compared to the full version of SA GAAP. It includes exemptions, simplifications, and reduced disclosure requirements in various accounting areas to reduce the reporting burden on SMEs while still providing relevant and meaningful financial information.
    - IFRS for SMEs: IFRS for SMEs provides a streamlined set of accounting and reporting requirements specifically designed for SMEs. It eliminates many of the detailed and complex requirements of full IFRS. It focuses on key principles and areas relevant to SMEs while providing a more cost-effective reporting framework.
4. Recognition and Measurement:
    - SA GAAP for SMEs: SA GAAP for SMEs follows the recognition and measurement principles of the full version of SA GAAP, which are closely aligned with IFRS. However, it may incorporate modifications and simplifications specific to SMEs in South Africa.
    - IFRS for SMEs: IFRS for SMEs provides simplified recognition and measurement criteria compared to full IFRS. It allows for more straightforward approaches in areas such as revenue

recognition, property, plant and equipment, financial instruments, and leases.

It's important to note that while SA GAAP for SMEs is specifically tailored for SMEs in South Africa, SMEs also have the option to adopt IFRS for SMEs if it better suits their needs, particularly if they have international operations or reporting obligations outside of South Africa. The choice between the two depends on factors such as the entity's size, industry, international operations, and reporting requirements.

Is there a standard or example chart of accounts for SA GAAP for SMEs?

In South Africa, there isn't a specific standard or example chart of accounts provided by the South African Institute of Chartered Accountants (SAICA) or any other regulatory body for SA GAAP for SMEs. Unlike the full version of SA GAAP or IFRS, which provides a detailed chart of accounts framework, SA GAAP for SMEs offers more flexibility for SMEs to design their own chart of accounts based on their specific industry, nature of operations, and reporting needs.

However, there are general guidelines and best practices that can be followed when creating a chart of accounts for SMEs under SA GAAP. Here are some key considerations:

1. Relevant account categories: Identify the main categories of accounts needed for your business, such as assets, liabilities, equity, revenue, and expenses. Within these categories, further sub-categories can be created as required.
2. Industry-specific accounts: Consider any specific accounts or categories relevant to your industry. Different industries may have unique reporting requirements, such as inventory accounts for manufacturing businesses or client trust accounts for legal firms. Tailor your chart of accounts to capture these industry-specific transactions.
3. Numbering system: Develop a logical numbering system for your accounts to make it easier to navigate and locate specific accounts. This can include using a hierarchical numbering system where the first digit represents the main category and subsequent digits represent sub-categories or specific accounts.
4. Consistency and comparability: Ensure consistency in account names and numbering across different periods and financial statements. This allows for easier comparability and analysis of financial information over time.
5. Scalability: Design a chart of accounts that can accommodate the future growth and expansion of your business. Consider including accounts that may be required as your business evolves, such as new product lines, additional locations, or expanded operations.

While there isn't a prescribed standard chart of accounts for SA GAAP for SMEs, it's advisable to consult

with an experienced accountant or financial professional who can provide guidance and assist in designing a chart of accounts that aligns with your business's specific needs and reporting requirements.

Is there a GAAP compliant Chart of Accounts structure for South Africa

Yes, there is a GAAP compliant Chart of Accounts structure for South Africa. The Generally Accepted Accounting Practice (GAAP) in South Africa is based on the International Financial Reporting Standards (IFRS). The South African Institute of Chartered Accountants (SAICA) provides guidance on the structure and content of a Chart of Accounts that is compliant with GAAP.

The SAICA recommends that a Chart of Accounts in South Africa should have the following sections:

1. Assets
2. Liabilities
3. Equity
4. Income
5. Cost of Sales
6. Expenses
7. Other Income and Expenses
8. Taxation

Each section should be further broken down into specific accounts, such as cash, accounts receivable, accounts payable, revenue, salaries, and so on. The specific accounts used may vary depending on the nature of the business.

It's important to note that while there is a recommended structure for a Chart of Accounts in South Africa, the actual accounts used may differ from one business to another based on their individual requirements and industry-specific reporting requirements.

Is there a sample Chart of Accounts in South Africa?

Yes, there are sample charts of accounts available that businesses in South Africa can use as a reference. However, the specific accounts used may vary depending on the nature of the business, the size of the company, and the industry in which it operates.

Here is a sample Chart of Accounts based on the SAICA's recommended structure:

1. Assets

- 1000 Cash and cash equivalents
- 1100 Accounts receivable
- 1200 Inventory
- 1300 Prepaid expenses
- 1400 Property, plant, and equipment
- 1500 Investments
- 1600 Other assets

2. Liabilities
    - 2000 Accounts payable
    - 2100 Accrued expenses
    - 2200 Short-term debt
    - 2300 Long-term debt
    - 2400 Other liabilities
3. Equity
    - 3000 Share capital
    - 3100 Retained earnings
4. Income
    - 4000 Sales revenue
    - 4100 Other revenue
5. Cost of Sales
    - 5000 Cost of goods sold
6. Expenses
    - 6000 Salaries and wages
    - 6100 Rent and utilities
    - 6200 Advertising and marketing
    - 6300 Insurance

- 6400 Repairs and maintenance
- 6500 Supplies and materials
- 6600 Depreciation
- 6700 Interest expense

7. Other Income and Expenses
    - 7000 Gain or loss on sale of assets
    - 7100 Foreign exchange gain or loss
    - 7200 Miscellaneous income and expenses
8. Taxation
    - 8000 Current income tax
    - 8100 Deferred income tax

This is just a sample Chart of Accounts, and businesses can customize it based on their individual requirements. It is recommended that businesses seek the advice of a professional accountant or bookkeeper when setting up their Chart of Accounts to ensure it is accurate and compliant with GAAP.

What is the recommended financial categories and account groups for accounts in the South African Chart of Accounts?

The South African Chart of Accounts is a standardized list of financial accounts that businesses in South Africa can use to organize their financial transactions. Here are some recommended financial categories and account groups that can be used in the South African Chart of Accounts:

1. Assets: This category includes all the resources that a business owns and controls. It includes subcategories such as:
    - Current assets (e.g. cash, accounts receivable, inventory)
    - Fixed assets (e.g. property, plant, and equipment)
    - Intangible assets (e.g. patents, trademarks, goodwill)
2. Liabilities: This category includes all the financial obligations that a business owes to others. It includes subcategories such as:
    - Current liabilities (e.g. accounts payable, taxes payable, short-term loans)
    - Long-term liabilities (e.g. long-term loans, bonds, mortgages)

3. Equity: This category includes the owners' investment in the business. It includes subcategories such as:
    - Share capital (e.g. common shares, preferred shares)
    - Retained earnings (e.g. accumulated profits or losses)
4. Income: This category includes all the revenue earned by the business. It includes subcategories such as:
    - Sales revenue (e.g. revenue from the sale of goods or services)
    - Other income (e.g. interest income, rental income)
5. Expenses: This category includes all the costs incurred by the business. It includes subcategories such as:
    - Cost of sales (e.g. the cost of producing or acquiring the goods sold)
    - Operating expenses (e.g. rent, salaries, utilities)
    - Depreciation and amortization (e.g. the cost of using up fixed assets and intangible assets over time)

These financial categories and account groups can be further customized and refined to suit the specific needs of each business. It is important to consult with a professional accountant or bookkeeper to ensure that the chart of accounts is set up correctly and accurately reflects the business's financial transactions.

What is the recommended financial categories and account groups for accounts in the South African Chart of Accounts?

The recommended financial categories and account groups for the South African Chart of Accounts may vary depending on the specific needs of the organization. However, there are some general categories and groups that are commonly used in South African accounting practices.

1. Assets: This includes all the resources owned by the organization, such as cash, investments, property, plant, and equipment.
2. Liabilities: This includes all the obligations owed by the organization, such as loans, accounts payable, and accrued expenses.
3. Equity: This represents the residual interest in the assets of the organization after deducting liabilities.
4. Revenue: This includes all the income earned by the organization, such as sales revenue, interest income, and other operating income.

5. Expenses: This includes all the costs incurred by the organization, such as wages, rent, utilities, and supplies.

Some account groups that may be used within these categories include:

1. Cash and bank accounts: This includes all the accounts used to manage the organization's cash and bank transactions.
2. Accounts receivable and payable: This includes all the accounts used to manage the organization's sales and purchases.
3. Fixed assets: This includes all the accounts used to manage the organization's property, plant, and equipment.
4. Revenue accounts: This includes all the accounts used to record the organization's income from various sources.
5. Expense accounts: This includes all the accounts used to record the organization's costs associated with its operations.
6. Tax accounts: This includes all the accounts used to manage the organization's tax obligations.
7. Equity accounts: This includes all the accounts used to record the organization's equity transactions, such as share capital, retained earnings, and dividends.

Overall, the recommended financial categories and account groups for the South African Chart of Accounts should be tailored to meet the specific needs of the organization and should comply with South African accounting standards and regulations.

Payroll in South Africa

What accounts is suggested for payroll in South Africa?

For payroll accounting in South Africa, some of the key accounts that may be used include:

1. Salaries and wages: This account is used to record the gross amount of salaries and wages paid to employees, including any overtime, bonuses, or other compensation.
2. Employee benefits: This account is used to record any employer contributions to employee benefits, such as pension funds, medical aid, or other fringe benefits.
3. PAYE (Pay-as-you-earn) payable: This account is used to record the amount of PAYE tax withheld from employee salaries and wages, which must be paid to the South African Revenue Service (SARS) on a monthly basis.
4. UIF (Unemployment Insurance Fund) payable: This account is used to record the amount of UIF

contributions withheld from employee salaries and wages, which must be paid to the Department of Labour on a monthly basis.

5. SDL (Skills Development Levy) payable: This account is used to record the amount of SDL contributions payable by employers, which are used to fund training and skills development programs.
6. Employee loans and advances: This account is used to record any loans or advances made to employees, such as salary advances or loans for education or housing.
7. Employee payroll taxes and levies: This account is used to record any other payroll taxes or levies payable by employers, such as COIDA (Compensation for Occupational Injuries and Diseases Act) contributions or UIF COVID-19 TERS (Temporary Employer/Employee Relief Scheme) payments.

These accounts may be used in conjunction with other accounts in the company's chart of accounts to provide a comprehensive record of payroll transactions and related expenses. It is important to consult with a qualified accountant or payroll specialist to ensure that payroll accounts are set up and managed correctly in accordance with South African regulations and requirements.

Payroll Employers Contributions an Employees contributions

In general, the employer's contributions to employee benefits, such as pension contributions or health insurance premiums, are recorded as expense accounts. These contributions are considered part of the overall compensation package provided by the employer. On the other hand, employees' contributions to benefits programs are typically treated as deductions from their gross salaries and are not recorded as separate expense accounts.

Regarding Pay-As-You-Earn (PAYE), it is a system for withholding and remitting income tax from employees' salaries on behalf of the tax authority. The amount withheld represents the employees' income tax liability. In the chart of accounts, PAYE is recorded as a current liability, reflecting the obligation to remit the withheld taxes to the tax authority.

To summarize:

- Employer contributions to employee benefits: Recorded as expense accounts.
- Employees' contributions to benefits: Generally not recorded as separate expense accounts.
- Pay-As-You-Earn (PAYE) taxes: Recorded as a current liability.

It's important to note that specific accounting practices may vary based on the jurisdiction and accounting standards followed. It is advisable to consult with an accounting professional or refer to the applicable regulations for accurate guidance in your specific context.

Created with the Standard Edition of HelpNDoc: Free help authoring tool

South Africa - Chart of Accounts - Small business

Sample outline of a Chart of Accounts for a South African Small business?

For a South African small business, the Chart of Accounts (COA) should be straightforward, yet comprehensive enough to manage the financial transactions and reporting needs of the business. Here's a sample outline of a Chart of Accounts for a South African small business:

1. Assets
    - 1.1 Current Assets
        - 1.1.1 Cash on Hand
        - 1.1.2 Cash in Bank
        - 1.1.3 Petty Cash
        - 1.1.4 Accounts Receivable (Outstanding customer invoices)
        - 1.1.5 Inventory (if applicable)
        - 1.1.6 Prepaid Expenses
        - 1.1.7 Other Current Assets
    - 1.2 Non-Current Assets
        - 1.2.1 Property and Buildings (if owned by the business)
        - 1.2.2 Furniture and Fixtures
        - 1.2.3 Equipment (computers, machinery, etc.)
        - 1.2.4 Vehicles (if used for business purposes)
        - 2.5 Other Non-Current Assets
        - 2.5.1 Long-Term Investments
        - 2.5.2 Long-Term Notes Receivable
        - 2.5.3 Deferred Tax Assets
        - 2.5.4 Security Deposits

- § 2.5.5 Long-Term Prepaid Expenses
- § 2.5.6 Mineral Rights
- § 2.5.7 Leasehold Improvements
- § 2.5.8 Deferred Charges
- § 2.5.9 Long-Term Deposits
- § 2.5.10 Deferred Financing Costs

- o 1.3 Intangible Assets
  - § 1.3.1 Patents
  - § 1.3.2 Licences
  - § 1.3.3 Trademarks
  - § 1.3.4 Copyrights
  - § 1.3.5 Goodwill (if applicable)
  - § 1.3.6 Other Intangible Assets

2. Liabilities

- o 2.1 Current Liabilities
  - § 2.1.1 Accounts Payable (Outstanding bills and expenses)
  - § 2.1.2 Accrued Liabilities (e.g., Salaries payable, utilities)
  - § 2.1.3 Short-Term Loans and Borrowings (if applicable)
  - § 2.1.4 Credit Card Payables
  - § 2.1.5 Value Added Tax (VAT) Payable (if applicable)
    - · 2.1.5.1 Output VAT (VAT on Sales)
    - · 2.1.5.2 Input VAT (VAT on Purchases)
    - · 2.1.5.3 Input VAT (VAT on Capital goods)
    - · 2.1.5.4 Zero Rated VAT (Sales with 0% VAT)
    - · 2.1.5.5 VAT Bad Debts (Uncollectible VAT on Sales)
  - § 2.1.6 Payroll or Salaries and Wages Payable

- 2.1.6.1 Pay-As-You-Earn (PAYE) Tax
- 2.1.6.2 Pension Fund Contributions Payable
- 2.1.6.3 Medical Aid Contributions Payable
- 2.1.6.4 Other Payroll Deductions

§ 2.1.7 Other Current Liabilities

o 2.2 Non-Current Liabilities

§ 2.2.1 Long-Term Loans and Borrowings (if applicable)

§ 2.2.2 Lease Liabilities (if applicable)

§ 2.2.3 Other Non-Current Liabilities

3. Equity
   - o 3.1 Owner's Capital
   - o 3.2 Retained Earnings
   - o 3.3 Drawings or Dividends (if applicable)
   - o 3.4 Other Equity Items
4. Income
   - o 4.1 Sales Revenue (Income from products or services sold)
   - o 4.2 Interest Income (e.g., from bank accounts)
   - o 4.3 Other Income
5. Cost of Goods Sold (COGS)
   - o 5.1 Beginning Inventory (if applicable)
   - o 5.2 Purchases (Cost of goods acquired for resale or materials used)
   - o 5.3 Ending Inventory (if applicable)
   - o 5.4 Cost of Services (Direct costs related to service delivery, if applicable)
   - o 5.5 Gross Profit
6. Expenses
   - o 6.1 Salaries and Wages

- 6.2 Rent and Lease Expenses
- 6.3 Utilities (Electricity, Water, etc.)
- 6.4 Office Supplies
- 6.5 Advertising and Promotion
- 6.6 Bank Fees and Interest Expenses
- 6.7 Repairs and Maintenance
- 6.8 Travel and Transportation Expenses
- 6.9 Professional Fees (e.g., accounting, legal)
- 6.10 Insurance
- 6.11 Depreciation and Amortization
- 6.12 Other Operating Expenses

7. Taxes
    - 7.1 Value Added Tax (VAT) Payable (if applicable)
    - 7.2 Pay-As-You-Earn (PAYE) Tax (if applicable)
    - 7.3 Other Taxes
8. Other Comprehensive Income
    - 8.1 Foreign Currency Translation Gains/Losses (if applicable)
    - 8.2 Other Items
9. Gains and Losses
    - 9.1 Gain on Sale of Assets (if applicable)
    - 9.2 Loss on Impairment of Assets (if applicable)
10. Inter-Account Transactions
    - 10.1 Transfers between Bank Accounts (if applicable)
11. Project or Job Income and Expenses
    - 11.1 Project A
        - 11.1.1 Income

- § 11.1.2 Expenses
- o 11.2 Project B
  - § 11.2.1 Income
  - § 11.2.2 Expenses
- o 11.3 Other Projects or Jobs

Please note that the above COA is a general outline and can be customized to suit the specific operations and financial reporting needs of the South African small business. It is essential to consult with a qualified accountant or financial expert to ensure compliance with South African accounting standards and regulations for small businesses.

Value Added Tax (VAT)

For the VAT-related accounts:

- Output VAT (VAT on Sales): This account tracks the VAT amount charged to customers on sales of goods and services. The percentage for Output VAT is the standard VAT rate, which is prescribed by the South African Revenue Service (SARS). As of my knowledge cutoff in September 2021, the standard VAT rate in South Africa is 15%.
- Input VAT (VAT on Purchases): This account records the VAT paid on purchases of goods and services from suppliers. Businesses can claim Input VAT as a credit against their Output VAT liability. The percentage for Input VAT is also the standard VAT rate, which is 15%.
- Input VAT (VAT on Purchases - Capital goods): In South Africa, when a business purchases capital goods (such as machinery, equipment, vehicles, etc.) that are used in the business for an extended period, they are entitled to claim Input VAT on these purchases as part of their Input Tax Credit. Therefore, Input VAT should encompass both VAT on regular purchases (goods and services used in day-to-day operations) and VAT on capital goods.

  It's important to accurately track and account for Input VAT on capital goods to ensure compliance with VAT regulations and to maximize VAT recoveries for the business. As always, businesses should consult with a qualified tax professional to ensure proper accounting treatment and adherence to the latest VAT rules and regulations.
- Zero Rated VAT (Sales with 0% VAT): Some goods and services are considered zero-rated for VAT purposes. This means that VAT is still applicable, but the rate is 0%. Examples of zero-rated goods may include basic food items, certain medical supplies, and exports of goods. The percentage for Zero Rated VAT is 0%.

- VAT Bad Debts (Uncollectible VAT on Sales): If a customer fails to pay an invoice, and the debt is considered bad (uncollectible), businesses can claim relief on the VAT previously accounted for on that invoice. This is known as VAT Bad Debts. The percentage for VAT Bad Debts is the standard VAT rate, which is 15%.

Please note that tax regulations can change, so it's important to verify the current VAT rates and regulations with the South African Revenue Service (SARS) or a qualified tax professional. Additionally, businesses should adjust their Chart of Accounts as needed to comply with any updates in tax laws or accounting standards.

Created with the Standard Edition of HelpNDoc: Maximize Your PDF Protection with These Simple Steps

South Africa - Chart of Accounts - Retail business

Sample outline of a Chart of Accounts for a South African Retail business?

For a South African retail business, the Chart of Accounts (COA) should be tailored to reflect the specific financial transactions and reporting needs of the retail industry. Here's a sample outline of a Chart of Accounts for a South African retail business:

1. Assets
    - 1.1 Current Assets
        - 1.1.1 Cash on Hand
        - 1.1.2 Cash in Bank
        - 1.1.3 Petty Cash
        - 1.1.4 Accounts Receivable (Trade Debtors)
        - 1.1.5 Inventory (Merchandise for resale)
        - 1.1.6 Prepaid Expenses
        - 1.1.7 Other Current Assets
    - 1.2 Non-Current Assets
        - 1.2.1 Property and Buildings (Store locations, warehouses, etc.)
        - 1.2.2 Land

        - § 1.2.3 Furniture and Fixtures
        - § 1.2.4 Equipment (Cash registers, shelving, etc.)
        - § 1.2.5 Vehicles (if used for delivery or business purposes)
        - § 1.2.6 Intangible Assets (Trademarks, licences, etc.)
        - § 1.2.7 Other Non-Current Assets

2. Liabilities
    - o 2.1 Current Liabilities
        - § 2.1.1 Accounts Payable (Trade Creditors)
        - § 2.1.2 Accrued Liabilities (e.g., Salaries payable, utilities)
        - § 2.1.3 Short-Term Loans and Borrowings (if applicable)
        - § 2.1.4 Credit Card Payables
        - § 2.1.5 Other Current Liabilities
    - o 2.2 Non-Current Liabilities
        - § 2.2.1 Long-Term Loans and Borrowings (if applicable)
        - § 2.2.2 Lease Liabilities
        - § 2.2.3 Other Non-Current Liabilities
3. Equity
    - o 3.1 Share Capital
        - § 3.1.1 Ordinary Shares
        - § 3.1.2 Preference Shares
    - o 3.2 Retained Earnings
    - o 3.3 Other Equity Items
4. Income
    - o 4.1 Sales Revenue (Income from merchandise sales)
    - o 4.2 Discounts and Allowances (Sales discounts, returns)
    - o 4.3 Interest Income (e.g., from bank accounts)
    - o 4.4 Rental Income (if renting out store space)

- 4.5 Other Income

5. Cost of Goods Sold (COGS)
    - 5.1 Beginning Inventory
    - 5.2 Purchases (Cost of merchandise acquired)
    - 5.3 Direct Labor Costs (if applicable)
    - 5.4 Freight and Shipping Costs
    - 5.5 Ending Inventory
    - 5.6 Gross Profit
6. Expenses
    - 6.1 Salaries and Wages
    - 6.2 Rent and Lease Expenses
    - 6.3 Utilities (Electricity, Water, etc.)
    - 6.4 Insurance
    - 6.5 Advertising and Promotion
    - 6.6 Store Supplies (Shopping bags, price tags, etc.)
    - 6.7 Repairs and Maintenance
    - 6.8 Depreciation and Amortization
    - 6.9 Bank Fees and Interest Expenses
    - 6.10 Security and Surveillance
    - 6.11 Other Operating Expenses
7. Taxes
    - 7.1 Value Added Tax (VAT) Payable
    - 7.2 Pay-As-You-Earn (PAYE) Tax (if applicable)
    - 7.3 Other Taxes
8. Other Comprehensive Income
    - 8.1 Foreign Currency Translation Gains/Losses (if applicable)

- 8.2 Other Items

9. Gains and Losses
    - 9.1 Gain on Sale of Assets (if applicable)
    - 9.2 Loss on Impairment of Assets (if applicable)
10. Inter-store Transactions
    - 10.1 Transfers between Store Locations
11. Supplier Credits
    - 11.1 Supplier Credits and Rebates
12. Customer Loyalty Programs
    - 12.1 Loyalty Points and Rewards

Please note that the above COA is a general outline and may need to be adjusted based on the specific operations and financial reporting requirements of the South African retail business. It is essential to consult with a qualified accountant or financial expert to ensure compliance with South African accounting standards and regulations for the retail industry.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

South Africa - Chart of Accounts - Service business

Sample outline of a Chart of Accounts for a South African Service business?

For a South African service business, the Chart of Accounts (COA) should be designed to suit the specific financial transactions and reporting needs of the service industry. Here's a sample outline of a Chart of Accounts for a South African service business:

1. Assets
    - 1.1 Current Assets
        - 1.1.1 Cash on Hand
        - 1.1.2 Cash in Bank

        - § 1.1.3 Petty Cash
        - § 1.1.4 Accounts Receivable (Outstanding client invoices)
        - § 1.1.5 Prepaid Expenses
        - § 1.1.6 Other Current Assets
    - o 1.2 Non-Current Assets
        - § 1.2.1 Property and Buildings (Office space, facilities, etc.)
        - § 1.2.2 Land
        - § 1.2.3 Furniture and Equipment
        - § 1.2.4 Vehicles (if used for service delivery)
        - § 1.2.5 Intangible Assets (Software, licences, etc.)
        - § 1.2.6 Other Non-Current Assets
2. Liabilities
    - o 2.1 Current Liabilities
        - § 2.1.1 Accounts Payable (Outstanding expenses, bills, etc.)
        - § 2.1.2 Accrued Liabilities (e.g., Salaries payable, utilities)
        - § 2.1.3 Short-Term Loans and Borrowings (if applicable)
        - § 2.1.4 Credit Card Payables
        - § 2.1.5 Other Current Liabilities
    - o 2.2 Non-Current Liabilities
        - § 2.2.1 Long-Term Loans and Borrowings (if applicable)
        - § 2.2.2 Lease Liabilities
        - § 2.2.3 Other Non-Current Liabilities
3. Equity
    - o 3.1 Share Capital
        - § 3.1.1 Ordinary Shares
        - § 3.1.2 Preference Shares
    - o 3.2 Retained Earnings

- 3.3 Other Equity Items

4. Income
    - 4.1 Service Revenue (Income from providing services)
    - 4.2 Project Revenue (if applicable, for project-based services)
    - 4.3 Retainer Fees (if applicable)
    - 4.4 Interest Income (e.g., from bank accounts)
    - 4.5 Other Income
5. Expenses
    - 5.1 Salaries and Wages
    - 5.2 Rent and Lease Expenses
    - 5.3 Utilities (Electricity, Water, etc.)
    - 5.4 Insurance
    - 5.5 Advertising and Promotion
    - 5.6 Office Supplies
    - 5.7 Professional Fees (e.g., legal, consulting)
    - 5.8 Travel and Transportation Expenses
    - 5.9 Training and Professional Development
    - 5.10 Depreciation and Amortization
    - 5.11 Bank Fees and Interest Expenses
    - 5.12 Other Operating Expenses
6. Taxes
    - 6.1 Value Added Tax (VAT) Payable
    - 6.2 Pay-As-You-Earn (PAYE) Tax (if applicable)
    - 6.3 Other Taxes
7. Other Comprehensive Income
    - 7.1 Foreign Currency Translation Gains/Losses (if applicable)

- 7.2 Other Items

8. Gains and Losses
    - 8.1 Gain on Sale of Assets (if applicable)
    - 8.2 Loss on Impairment of Assets (if applicable)
9. Inter-project Transactions
    - 9.1 Transfers between Projects or Divisions (if applicable)
10. Service Categories
    - 10.1 Service Category A
        - 10.1.1 Income
        - 10.1.2 Expenses
    - 10.2 Service Category B
        - 10.2.1 Income
        - 10.2.2 Expenses
    - 10.3 Other Service Categories
11. Customer Contracts
    - 11.1 Contract A
        - 11.1.1 Income
        - 11.1.2 Expenses
    - 11.2 Contract B
        - 11.2.1 Income
        - 11.2.2 Expenses
    - 11.3 Other Customer Contracts

Please note that the above COA is a general outline and can be customized to match the specific services offered and financial reporting requirements of the South African service business. It is essential to consult with a qualified accountant or financial expert to ensure compliance with South African accounting standards and regulations for service-based industries.

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

South Africa - Chart of Accounts - Mixed Retail and Service business

Sample outline of a Chart of Accounts for a South African mixed Retail and Service business?

For a South African mixed retail and service business, the Chart of Accounts (COA) needs to reflect the unique financial transactions and reporting requirements of both retail and service operations. Here's a sample outline of a Chart of Accounts for such a business:

1. Assets
    - 1.1 Current Assets
        - 1.1.1 Cash on Hand
        - 1.1.2 Cash in Bank
        - 1.1.3 Petty Cash
        - 1.1.4 Accounts Receivable (Trade Debtors for retail sales and service invoices)
        - 1.1.5 Inventory (Retail merchandise for resale)
        - 1.1.6 Prepaid Expenses
        - 1.1.7 Other Current Assets
    - 1.2 Non-Current Assets
        - 1.2.1 Property and Buildings (Store locations, office space, etc.)
        - 1.2.2 Land
        - 1.2.3 Furniture and Fixtures
        - 1.2.4 Equipment (Cash registers, service tools, etc.)
        - 1.2.5 Vehicles (if used for delivery or service)
        - 1.2.6 Intangible Assets (Software, licences, etc.)
        - 1.2.7 Other Non-Current Assets
2. Liabilities
    - 2.1 Current Liabilities
        - 2.1.1 Accounts Payable (Outstanding expenses, bills, etc.)

        - § 2.1.2 Accrued Liabilities (e.g., Salaries payable, utilities)
        - § 2.1.3 Short-Term Loans and Borrowings (if applicable)
        - § 2.1.4 Credit Card Payables 2.1.5 Other Current Liabilities
    - o 2.2 Non-Current Liabilities
        - § 2.2.1 Long-Term Loans and Borrowings (if applicable)
        - § 2.2.2 Lease Liabilities
        - § 2.2.3 Other Non-Current Liabilities

3. Equity
    - o 3.1 Share Capital
        - § 3.1.1 Ordinary Shares
        - § 3.1.2 Preference Shares
    - o 3.2 Retained Earnings
    - o 3.3 Other Equity Items

4. Income
    - o 4.1 Retail Sales Revenue (Income from merchandise sales)
    - o 4.2 Service Revenue (Income from providing services)
    - o 4.3 Project Revenue (if applicable, for project-based services)
    - o 4.4 Discounts and Allowances (Sales discounts, returns)
    - o 4.5 Interest Income (e.g., from bank accounts) 4.6 Rental Income (if renting out store space)
    - o 4.7 Other Income

5. Cost of Goods Sold (COGS)
    - o 5.1 Beginning Inventory (for retail merchandise)
    - o 5.2 Purchases (Cost of merchandise acquired for retail)
    - o 5.3 Direct Labor Costs (for service operations)
    - o 5.4 Freight and Shipping Costs (for retail merchandise)
    - o 5.5 Ending Inventory (for retail merchandise)
    - o 5.6 Cost of Services (Direct costs related to service delivery)

- 5.7 Gross Profit

6. Expenses
    - 6.1 Salaries and Wages
    - 6.2 Rent and Lease Expenses
    - 6.3 Utilities (Electricity, Water, etc.)
    - 6.4 Insurance
    - 6.5 Advertising and Promotion
    - 6.6 Office Supplies
    - 6.7 Professional Fees (e.g., legal, consulting)
    - 6.8 Travel and Transportation Expenses
    - 6.9 Training and Professional Development
    - 6.10 Depreciation and Amortization
    - 6.11 Bank Fees and Interest Expenses
    - 6.12 Other Operating Expenses
7. Taxes
    - 7.1 Value Added Tax (VAT) Payable
    - 7.2 Pay-As-You-Earn (PAYE) Tax (if applicable)
    - 7.3 Other Taxes
8. Other Comprehensive Income
    - 8.1 Foreign Currency Translation Gains/Losses (if applicable)
    - 8.2 Other Items
9. Gains and Losses
    - 9.1 Gain on Sale of Assets (if applicable)
    - 9.2 Loss on Impairment of Assets (if applicable)
10. Inter-store Transactions
    - 10.1 Transfers between Store Locations

11. Supplier Credits
    - 11.1 Supplier Credits and Rebates
12. Service Categories
    - 12.1 Service Category A
        - 12.1.1 Income
        - 12.1.2 Expenses
    - 12.2 Service Category B
        - 12.2.1 Income
        - 12.2.2 Expenses
    - 12.3 Other Service Categories
13. Customer Contracts
    - 13.1 Contract A
        - 13.1.1 Income
        - 13.1.2 Expenses
    - 13.2 Contract B
        - 13.2.1 Income
        - 13.2.2 Expenses
    - 13.3 Other Customer Contracts

Please note that the above COA is a general outline and can be customized based on the specific retail and service operations, as well as the financial reporting requirements of the South African mixed business. It is essential to consult with a qualified accountant or financial expert to ensure compliance with South African accounting standards and regulations for such a diverse business.

Created with the Standard Edition of HelpNDoc: Upgrade your help files and your workflow with HelpNDoc's WinHelp HLP to CHM conversion

South Africa - Chart of Accounts - Manufacturing

Sample outline of a Chart of Accounts for a South African Manufacturing business?

A Chart of Accounts (COA) is a structured list of all the accounts and categories used to organize a company's financial transactions. For a South African manufacturing business, the COA needs to reflect the specific needs and requirements of the industry and the country's accounting practices. Here's a sample outline of a Chart of Accounts for a South African manufacturing business:

1. Assets
    - 1.1 Current Assets
        - 1.1.1 Cash and Cash Equivalents
        - 1.1.2 Accounts Receivable
        - 1.1.3 Inventory (Raw materials, work in progress, finished goods)
        - 1.1.4 Prepaid Expenses
        - 1.1.5 Other Current Assets
    - 1.2 Non-Current Assets
        - 1.2.1 Property, Plant, and Equipment (Land, Buildings, Machinery, etc.)
        - 1.2.2 Intangible Assets (Patents, Trademarks, Software, etc.)
        - 1.2.3 Long-Term Investments
        - 1.2.4 Other Non-Current Assets
2. Liabilities
    - 2.1 Current Liabilities
        - 2.1.1 Accounts Payable
        - 2.1.2 Short-Term Loans and Borrowings
        - 2.1.3 Accrued Liabilities
        - 2.1.4 Taxes Payable
        - 2.1.5 Other Current Liabilities
    - 2.2 Non-Current Liabilities
        - 2.2.1 Long-Term Loans and Borrowings

        - § 2.2.2 Deferred Tax Liabilities
        - § 2.2.3 Other Non-Current Liabilities

3. Equity
    - o 3.1 Share Capital
        - § 3.1.1 Ordinary Shares
        - § 3.1.2 Preference Shares
    - o 3.2 Retained Earnings
    - o 3.3 Other Equity Items
4. Income
    - o 4.1 Sales Revenue
    - o 4.2 Cost of Goods Sold (COGS)
    - o 4.3 Gross Profit
    - o 4.4 Operating Revenue (if applicable)
    - o 4.5 Operating Expenses
        - § 4.5.1 Selling and Marketing Expenses
        - § 4.5.2 General and Administrative Expenses
        - § 4.5.3 Research and Development Expenses
    - o 4.6 Operating Profit
    - o 4.7 Other Income (e.g., interest income, rental income)
5. Expenses
    - o 5.1 Cost of Goods Sold (COGS)
        - § 5.1.1 Direct Materials
        - § 5.1.2 Direct Labor
        - § 5.1.3 Factory Overhead
    - o 5.2 Selling and Marketing Expenses
        - § 5.2.1 Advertising and Promotion
        - § 5.2.2 Sales Commissions

- 5.3 General and Administrative Expenses
  - 5.3.1 Salaries and Wages
  - 5.3.2 Rent and Utilities
  - 5.3.3 Office Supplies
- 5.4 Research and Development Expenses
- 5.5 Other Operating Expenses

6. Cost of Sales
7. Taxation
   - 7.1 Current Tax
   - 7.2 Deferred Tax
8. Other Comprehensive Income
   - 8.1 Foreign Currency Translation Gains/Losses
   - 8.2 Unrealized Gains/Losses on Investments
   - 8.3 Other Items
9. Gains and Losses
   - 9.1 Gain on Sale of Assets
   - 9.2 Loss on Impairment of Assets
10. Intercompany Transactions
    - 10.1 Intercompany Revenue
    - 10.2 Intercompany Expenses
11. Dividends
12. Subsidiary and Associate Companies

Please note that the above COA is a general outline and can be tailored to meet the specific needs and reporting requirements of the manufacturing business. Additionally, it's essential to consult with a qualified accountant or financial expert to ensure compliance with South African accounting standards and regulations.

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

South Africa - Chart of Accounts - Church

Sample outline of a Chart of Accounts for a South African Church?

For a South African church, the Chart of Accounts (COA) will differ from that of a manufacturing business due to the unique financial transactions and reporting needs in a religious organization. Here's a sample outline of a Chart of Accounts for a South African church:

1. Assets
    - 1.1 Current Assets
        - 1.1.1 Cash on Hand
        - 1.1.2 Cash in Bank
        - 1.1.3 Petty Cash
        - 1.1.4 Accounts Receivable (Offerings and Donations)
        - 1.1.5 Prepaid Expenses
        - 1.1.6 Other Current Assets
    - 1.2 Non-Current Assets
        - 1.2.1 Property (Church Building)
        - 1.2.2 Land
        - 1.2.3 Furniture and Fixtures
        - 1.2.4 Equipment (Sound system, musical instruments, etc.)
        - 1.2.5 Vehicles (if owned by the church)
        - 1.2.6 Investments (if any)
        - 1.2.7 Other Non-Current Assets
2. Liabilities
    - 2.1 Current Liabilities
        - 2.1.1 Accounts Payable (Outstanding expenses, bills, etc.)
        - 2.1.2 Accrued Liabilities (e.g., Salaries payable, utility bills)
        - 2.1.3 Short-Term Loans and Borrowings (if applicable)

        - § 2.1.4 Other Current Liabilities
    - 2.2 Non-Current Liabilities
        - § 2.2.1 Long-Term Loans and Borrowings (if applicable)
        - § 2.2.2 Other Non-Current Liabilities
3. Fund Balances
    - 3.1 General Fund
    - 3.2 Building Fund
    - 3.3 Mission Fund
    - 3.4 Other Designated Funds
4. Income
    - 4.1 Offerings
    - 4.2 Tithes
    - 4.3 Donations
    - 4.4 Fundraising Income
    - 4.5 Rental Income (if the church rents out its facilities)
    - 4.6 Interest Income
    - 4.7 Other Income
5. Expenses
    - 5.1 Salaries and Benefits (for church staff)
    - 5.2 Rent and Utilities
    - 5.3 Office Supplies
    - 5.4 Maintenance and Repairs
    - 5.5 Outreach and Mission Expenses
    - 5.6 Worship and Music Expenses
    - 5.7 Educational and Training Expenses
    - 5.8 Charitable Contributions

- 5.9 Other Operating Expenses

6. Taxes and Levies
    - 6.1 Value Added Tax (VAT)
    - 6.2 Pay-As-You-Earn (PAYE) Tax (if applicable)
    - 6.3 Other Taxes and Levies
7. Other Comprehensive Income
    - 7.1 Foreign Currency Translation Gains/Losses (if applicable)
    - 7.2 Other Items
8. Gains and Losses
    - 8.1 Gain on Sale of Assets (if applicable)
    - 8.2 Loss on Impairment of Assets (if applicable)
9. Interchurch Transactions
    - 9.1 Interchurch Transfers
10. Ministries and Projects
    - 10.1 Youth Ministry
    - 10.2 Women's Ministry
    - 10.3 Outreach Projects
    - 10.4 Other Ministries and Projects
11. Memberships and Subscriptions
    - 11.1 Church Memberships
    - 11.2 Subscriptions to Religious Publications
12. Donor-Restricted Funds
    - 12.1 Donations with Specific Restrictions

Please note that the above COA is a general outline and can be adapted based on the specific activities, ministries, and financial reporting needs of the South African church. Additionally, it's crucial to seek guidance from a qualified accountant or financial expert to ensure compliance with South African accounting standards and regulations for non-profit and religious organizations.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

South Africa - Chart of Accounts - NPO or NGO

Sample outline of a Chart of Accounts for a South African NPO or NGO?

For a South African Non-Profit Organization (NPO) or Non-Governmental Organization (NGO), the Chart of Accounts (COA) will be designed to suit the specific financial transactions and reporting requirements of the organization. Here's a sample outline of a Chart of Accounts for a South African NPO or NGO:

1. Assets
    - 1.1 Current Assets
        - 1.1.1 Cash on Hand
        - 1.1.2 Cash in Bank
        - 1.1.3 Petty Cash
        - 1.1.4 Accounts Receivable (Donations, Grants, etc.)
        - 1.1.5 Prepaid Expenses
        - 1.1.6 Inventory (if applicable)
        - 1.1.7 Other Current Assets
    - 1.2 Non-Current Assets
        - 1.2.1 Property and Buildings
        - 1.2.2 Land
        - 1.2.3 Furniture and Fixtures
        - 1.2.4 Equipment (computers, office equipment, etc.)
        - 1.2.5 Vehicles (if owned by the organization)
        - 1.2.6 Investments (if any)
        - 1.2.7 Other Non-Current Assets
2. Liabilities

- 2.1 Current Liabilities
    - 2.1.1 Accounts Payable (Outstanding expenses, bills, etc.)
    - 2.1.2 Accrued Liabilities (e.g., Salaries payable, utility bills)
    - 2.1.3 Short-Term Loans and Borrowings (if applicable)
    - 2.1.4 Grants Payable
    - 2.1.5 Other Current Liabilities
- 2.2 Non-Current Liabilities
    - 2.2.1 Long-Term Loans and Borrowings (if applicable)
    - 2.2.2 Other Non-Current Liabilities

3. Net Assets
    - 3.1 Unrestricted Net Assets
    - 3.2 Temporarily Restricted Net Assets
    - 3.3 Permanently Restricted Net Assets
4. Income
    - 4.1 Donations and Contributions
    - 4.2 Grants and Funding (Government grants, foundation grants, etc.)
    - 4.3 Membership Fees
    - 4.4 Fundraising Income
    - 4.5 Interest Income
    - 4.6 Program Service Revenue (if applicable)
    - 4.7 Other Income
5. Expenses
    - 5.1 Salaries and Benefits
    - 5.2 Rent and Utilities
    - 5.3 Office Supplies
    - 5.4 Program Expenses (Direct costs related to the organization's mission)
    - 5.5 Administrative Expenses

- 5.6 Fundraising Expenses
- 5.7 Outreach and Community Development Expenses
- 5.8 Advocacy and Awareness Expenses
- 5.9 Training and Capacity Building Expenses
- 5.10 Research and Evaluation Expenses
- 5.11 Other Operating Expenses

6. Taxes and Levies
   - 6.1 Value Added Tax (VAT)
   - 6.2 Pay-As-You-Earn (PAYE) Tax (if applicable)
   - 6.3 Other Taxes and Levies
7. Other Comprehensive Income
   - 7.1 Foreign Currency Translation Gains/Losses (if applicable)
   - 7.2 Other Items
8. Gains and Losses
   - 8.1 Gain on Sale of Assets (if applicable)
   - 8.2 Loss on Impairment of Assets (if applicable)
9. Inter-Project Transactions
   - 9.1 Transfers between Projects or Programs
10. Projects and Programs
    - 10.1 Project A
      - 10.1.1 Income
      - 10.1.2 Expenses
    - 10.2 Project B
      - 10.2.1 Income
      - 10.2.2 Expenses
    - 10.3 Program
      - C 10.3.1 Income

        - § 10.3.2 Expenses
    - o 10.4 Other Projects and Programs
11. Memberships and Subscriptions
    - o 11.1 Membership Fees (if applicable)
    - o 11.2 Subscriptions to Publications (if applicable)
12. Donor-Restricted Funds
    - o 12.1 Donations with Specific Restrictions

Please note that the above COA is a general outline and can be customized to match the specific activities, projects, and financial reporting needs of the South African NPO or NGO. It is essential to consult with a qualified accountant or financial expert to ensure compliance with South African accounting standards and regulations for non-profit organizations.

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

New Zealand - Chart of Accounts - NZ IFRS

What is a suggested Chart of Accounts according to the New Zealand Chart of Accounts, based on the New Zealand International Financial Reporting Standards (NZ IFRS)?

The suggested Chart of Accounts for a business in New Zealand based on the New Zealand International Financial Reporting Standards (NZ IFRS) typically includes the following main categories:

1. Assets: This category includes accounts related to the resources that a business owns or controls, such as cash, accounts receivable, inventory, and property, plant, and equipment.
2. Liabilities: This category includes accounts related to the obligations that a business owes to others, such as accounts payable, loans, and other forms of debt.
3. Equity: This category includes accounts related to the ownership interest in a business, such as share capital and retained earnings.
4. Income: This category includes accounts related to the revenue earned by a business, such as sales revenue, interest income, and rental income.

5. Expenses: This category includes accounts related to the costs incurred by a business in generating revenue, such as cost of goods sold, operating expenses, and interest expenses.

Within each of these main categories, the accounts are usually identified by a three-digit code, with the first digit indicating the category and the last two digits indicating the specific account within the category.

The specific accounts included in the Chart of Accounts can vary depending on the nature of the business and its financial reporting requirements. It is important to consult with an accountant or bookkeeper to determine the most appropriate Chart of Accounts for your business.

Is there a sample chart of accounts for New Zealand?

Yes, there are sample charts of accounts available for businesses in New Zealand. The specific accounts used may vary depending on the nature of the business, the size of the company, and the industry in which it operates.

Here is a sample Chart of Accounts based on the New Zealand Generally Accepted Accounting Principles (GAAP):

1. Assets
    - 1000 Cash and bank accounts
    - 1100 Accounts receivable
    - 1200 Inventory
    - 1300 Prepaid expenses
    - 1400 Property, plant and equipment
    - 1500 Investments
    - 1600 Other assets
2. Liabilities
    - 2000 Accounts payable
    - 2100 Accrued expenses
    - 2200 Short-term debt
    - 2300 Long-term debt
    - 2400 Other liabilities
3. Shareholder's equity

- 3000 Share capital
- 3100 Retained earnings

4. Revenue
    - 4000 Sales revenue
    - 4100 Other revenue
5. Cost of sales
    - 5000 Cost of goods sold
6. Expenses
    - 6000 Salaries and wages
    - 6100 Rent and utilities
    - 6200 Advertising and marketing
    - 6300 Insurance
    - 6400 Repairs and maintenance
    - 6500 Supplies and materials
    - 6600 Depreciation
    - 6700 Interest expense
7. Other income and expenses
    - 7000 Gain or loss on sale of assets
    - 7100 Foreign exchange gain or loss
    - 7200 Miscellaneous income and expenses
8. Taxation
    - 8000 Current income tax
    - 8100 Deferred income tax

This is just a sample Chart of Accounts, and businesses can customize it based on their individual requirements. It is recommended that businesses seek the advice of a professional accountant or bookkeeper when setting up their Chart of Accounts to ensure it is accurate and compliant with New Zealand GAAP.

What is the recommended financial categories and account groups for these accounts in the New Zealand Chart of Accounts?

The New Zealand Chart of Accounts is a standardized list of financial accounts that businesses in New Zealand can use to organize their financial transactions. Here are some recommended financial categories and account groups that can be used in the New Zealand Chart of Accounts:

1. Assets: This category includes all the resources that a business owns and controls. It includes subcategories such as:
    - Current assets (e.g. cash, accounts receivable, inventory)
    - Fixed assets (e.g. property, plant, and equipment)
    - Intangible assets (e.g. patents, trademarks, goodwill)
2. Liabilities: This category includes all the financial obligations that a business owes to others. It includes subcategories such as:
    - Current liabilities (e.g. accounts payable, taxes payable, short-term loans)
    - Long-term liabilities (e.g. long-term loans, bonds, mortgages)
3. Equity: This category includes the owners' investment in the business. It includes subcategories such as:
    - Share capital (e.g. common shares, preferred shares)
    - Retained earnings (e.g. accumulated profits or losses)
4. Income: This category includes all the revenue earned by the business. It includes subcategories such as:
    - Sales revenue (e.g. revenue from the sale of goods or services)
    - Other income (e.g. interest income, rental income)
5. Expenses: This category includes all the costs incurred by the business. It includes subcategories such as:
    - Cost of goods sold (e.g. the cost of producing or acquiring the goods sold)
    - Operating expenses (e.g. rent, salaries, utilities)
    - Depreciation and amortization (e.g. the cost of using up fixed assets and intangible assets

over time)

These financial categories and account groups can be further customized and refined to suit the specific needs of each business. It is important to consult with a professional accountant or bookkeeper to ensure that the chart of accounts is set up correctly and accurately reflects the business's financial transactions.

What accounts is suggested for payroll in New Zealand?

In New Zealand, the following accounts are commonly used to record payroll transactions in the chart of accounts:

1. Salaries and wages: This account is used to record the gross wages and salaries paid to employees.
2. PAYE payable: This account is used to record the amount of tax withheld from employee wages, which must be paid to the Inland Revenue Department (IRD) on behalf of the employee.
3. KiwiSaver payable: This account is used to record the employer's contributions to the employee's KiwiSaver account, which is a government-approved retirement savings plan.
4. Employee loan payable: This account is used to record any loans or advances made to employees.
5. Employee deduction payable: This account is used to record deductions from employee wages such as union dues, charitable donations, or voluntary insurance contributions.
6. Holiday pay payable: This account is used to record the amount of holiday pay owed to employees, which must be paid out when the employee takes a holiday or at the end of their employment.
7. Accrued payroll: This account is used to record any payroll expenses that have been incurred but not yet paid, such as salaries and wages for the current pay period that will be paid in the following pay period.
8. Bank account: This account is used to record the transactions related to the company's payroll bank account, including deposits and withdrawals for payroll-related expenses.

It is important to tailor the chart of accounts to the specific needs of the business and to ensure compliance with local regulations. Consulting with a professional accountant or payroll provider can be helpful in setting up an effective payroll system and chart of accounts for New Zealand businesses.

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

Australia - Chart of Accounts - Australian Accounting Standards

---

What is a suggested Australian Chart of Accounts is based on the Australian Accounting Standards and is used by businesses in Australia?

The suggested Chart of Accounts for a business in Australia based on the Australian Accounting Standards typically includes the following main categories:

1. Assets: This category includes accounts related to the resources that a business owns or controls, such as cash, accounts receivable, inventory, and property, plant, and equipment.
2. Liabilities: This category includes accounts related to the obligations that a business owes to others, such as accounts payable, loans, and other forms of debt.
3. Equity: This category includes accounts related to the ownership interest in a business, such as share capital and retained earnings.
4. Revenue: This category includes accounts related to the income earned by a business, such as sales revenue, interest income, and rental income.
5. Expenses: This category includes accounts related to the costs incurred by a business in generating revenue, such as cost of goods sold, operating expenses, and interest expenses.

Within each of these main categories, the accounts are usually identified by a four-digit code, with the first two digits indicating the category and the last two digits indicating the specific account within the category.

The specific accounts included in the Chart of Accounts can vary depending on the nature of the business and its financial reporting requirements. It is important to consult with an accountant or bookkeeper to determine the most appropriate Chart of Accounts for your business.

Is there a sample chart of accounts for Australia?

Yes, there are sample charts of accounts available for businesses in Australia. The specific accounts used may vary depending on the nature of the business, the size of the company, and the industry in which it operates.

Here is a sample Chart of Accounts based on the Australian Accounting Standards:

1. Assets
    - 1000 Cash at bank
    - 1100 Accounts receivable
    - 1200 Inventory

- 1300 Prepaid expenses
- 1400 Property, plant, and equipment
- 1500 Investments
- 1600 Other assets

2. Liabilities
    - 2000 Accounts payable
    - 2100 Accrued expenses
    - 2200 Short-term debt
    - 2300 Long-term debt
    - 2400 Other liabilities
3. Equity
    - 3000 Share capital
    - 3100 Retained earnings
4. Revenue
    - 4000 Sales revenue
    - 4100 Other revenue
5. Cost of sales
    - 5000 Cost of goods sold
6. Expenses
    - 6000 Salaries and wages
    - 6100 Rent and utilities
    - 6200 Advertising and marketing
    - 6300 Insurance
    - 6400 Repairs and maintenance
    - 6500 Supplies and materials
    - 6600 Depreciation

- 6700 Interest expense

7. Other income and expenses
    - 7000 Gain or loss on sale of assets
    - 7100 Foreign exchange gain or loss
    - 7200 Miscellaneous income and expenses
8. Taxation
    - 8000 Current income tax
    - 8100 Deferred income tax

This is just a sample Chart of Accounts, and businesses can customize it based on their individual requirements. It is recommended that businesses seek the advice of a professional accountant or bookkeeper when setting up their Chart of Accounts to ensure it is accurate and compliant with Australian Accounting Standards.

NOTE: The accounts "Taxation - 8000 Current income tax" and "Taxation - 8100 Deferred income tax" are applicable to various types of business ownership, including corporations and certain partnerships. They are typically used to record tax-related transactions and obligations.

In the case of sole proprietorships, the taxation accounts mentioned above may not be relevant or commonly used. Sole proprietorships are typically treated as pass-through entities for tax purposes, meaning the business owner reports and pays taxes on their personal income tax return rather than having separate business tax accounts.

However, it's important to note that tax requirements and regulations can vary by jurisdiction. In some countries, even sole proprietorships may have specific tax reporting obligations or may need to account for certain tax-related transactions. Therefore, it's always advisable to consult with a tax professional or accountant familiar with the specific tax laws in the relevant jurisdiction to determine the appropriate accounts to be included in the Chart of Accounts for a sole proprietorship or any other type of business ownership.

What is the recommended financial categories and account groups for accounts in the Australia Chart of Accounts?

The Australian Chart of Accounts is a standardized list of financial accounts that businesses in Australia can use to organize their financial transactions. Here are some recommended financial categories and account groups that can be used in the Australian Chart of Accounts:

1. Assets: This category includes all the resources that a business owns and controls. It includes subcategories such as:
    - Current assets (e.g. cash, accounts receivable, inventory)
    - Non-current assets (e.g. property, plant, and equipment)
    - Intangible assets (e.g. patents, trademarks, goodwill)
2. Liabilities: This category includes all the financial obligations that a business owes to others. It includes subcategories such as:
    - Current liabilities (e.g. accounts payable, taxes payable, short-term loans)
    - Non-current liabilities (e.g. long-term loans, bonds, mortgages)
3. Equity: This category includes the owners' investment in the business. It includes subcategories such as:
    - Share capital (e.g. common shares, preferred shares)
    - Retained earnings (e.g. accumulated profits or losses)
4. Income: This category includes all the revenue earned by the business. It includes subcategories such as:
    - Sales revenue (e.g. revenue from the sale of goods or services)
    - Other income (e.g. interest income, rental income)
5. Expenses: This category includes all the costs incurred by the business. It includes subcategories such as:
    - Cost of sales (e.g. the cost of producing or acquiring the goods sold)
    - Operating expenses (e.g. rent, salaries, utilities)
    - Depreciation and amortization (e.g. the cost of using up fixed assets and intangible assets over time)

These financial categories and account groups can be further customized and refined to suit the specific needs of each business. It is important to consult with a professional accountant or bookkeeper to ensure that the chart of accounts is set up correctly and accurately reflects the business's financial transactions.

What is VAT / GST rates in Australia?

As in September 2021, the Goods and Services Tax (GST) rate in Australia is 10%. The GST is a value-added tax applied to most goods and services consumed in Australia.

It's important to note that tax rates and regulations can change over time, so it's advisable to consult official sources or the Australian Taxation Office (ATO) for the most up-to-date information on VAT/GST rates in Australia.

What is business activity statements (BAS) ?

Business Activity Statements (BAS) are a reporting requirement for businesses in Australia. They are used to report and pay various tax obligations to the Australian Taxation Office (ATO). BAS statements are typically lodged on a monthly, quarterly, or annual basis, depending on the business's turnover and reporting obligations.

The BAS includes information about the business's income, expenses, and GST (Goods and Services Tax) collected and paid. It covers various taxes and obligations, including:

1. Goods and Services Tax (GST): Businesses registered for GST must report the GST they have collected from sales and claim GST credits on eligible business expenses.
2. Pay as You Go (PAYG) Withholding: This involves reporting and remitting the amounts withheld from employees' wages for income tax purposes.
3. Pay as You Go (PAYG) Instalments: Businesses making regular payments towards their expected income tax liability may need to report and pay PAYG instalments.
4. Fringe Benefits Tax (FBT): If a business provides fringe benefits to employees or associates, they may need to report and pay FBT.
5. Wine Equalization Tax (WET): Applicable to businesses involved in the production or wholesale of wine.
6. Luxury Car Tax (LCT): This applies to businesses that sell or import luxury cars.

By lodging a BAS, businesses ensure compliance with their tax obligations and provide the ATO with accurate financial information. The frequency of BAS lodgement depends on the business's turnover, with larger businesses typically required to lodge on a monthly basis.

Is there a chart of accounts based on Business Activity Statements (BAS) ?

The Business Activity Statement (BAS) is a reporting requirement in Australia that encompasses various tax obligations. While the BAS provides a structure for reporting and paying taxes, it doesn't prescribe a specific chart of accounts.

The chart of accounts is a financial organizational tool that helps categorize and record transactions within a business. It provides a systematic framework for classifying and tracking financial activities. The specific accounts included in a chart of accounts can vary depending on the nature of the business, its industry, and reporting requirements.

However, when preparing the financial statements for BAS reporting, businesses typically utilize a chart of accounts that aligns with the relevant accounting standards and regulations. This includes accounts for income, expenses, assets, liabilities, and equity, which are necessary for generating accurate financial information for BAS reporting purposes.

While there isn't a specific chart of accounts prescribed by the BAS, businesses can customize their chart of accounts to ensure compliance with the reporting requirements and capture the necessary information for the BAS lodgement. It's essential to consult with accounting professionals or refer to accounting standards and regulations specific to your jurisdiction to design a suitable chart of accounts that meets the BAS reporting needs.

What accounts is suggested for payroll in Australia?

In Australia, the following accounts are commonly used to record payroll transactions in the chart of accounts:

1. Salaries and wages: This account is used to record the gross wages and salaries paid to employees.
2. Employee benefits expense: This account is used to record the cost of employee benefits such as superannuation contributions, sick leave, annual leave, and long service leave.
3. Payroll tax expense: This account is used to record the employer's share of payroll taxes, which include taxes such as the Payroll Tax, the Superannuation Guarantee Charge (SGC), and the Medicare Levy Surcharge.
4. PAYG withholding payable: This account is used to record the amount of tax withheld from employee wages, which must be paid to the Australian Taxation Office (ATO) on behalf of the employee.
5. Superannuation payable: This account is used to record the employer's contributions to employee superannuation funds.
6. Employee loan payable: This account is used to record any loans or advances made to employees.
7. Employee deduction payable: This account is used to record deductions from employee wages such as union dues, charitable donations, or voluntary insurance contributions.
8. Accrued payroll: This account is used to record any payroll expenses that have been incurred but not yet paid, such as salaries and wages for the current pay period that will be paid in the following pay period.

9. Bank account: This account is used to record the transactions related to the company's payroll bank account, including deposits and withdrawals for payroll-related expenses.

It is important to tailor the chart of accounts to the specific needs of the business and to ensure compliance with local regulations. Consulting with a professional accountant or payroll provider can be helpful in setting up an effective payroll system and chart of accounts for Australian businesses.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Canada - Chart of Accounts

Sets of Books: Canada

osFinancials and TurboCASH users may download these Sets of Books (templates) free in a matter of a few seconds (using the option, Let osFinancials help you to create a Set of Books). It takes only 3 clicks to download a Set of Books.

After downloading a Set of Books, the Set of Books (template) will automatically open in the language associated with the country and language (*"en-Canada"*).

	Books with 4-digit main account and 3 -digit-sub-accounts
	EN-CANADA-CORPORATION
	EN-CANADA-OTHER

Which accounting standards is applicable to businesses in Canada?

As of ChatGPT's last update in September 2021, the accounting standards applicable to businesses in Canada are primarily governed by the Accounting Standards for Private Enterprises (ASPE) and the Accounting Standards for Not-for-Profit Organizations (ASNPO). These standards are issued by the Accounting Standards Board (AcSB) of the Canadian Institute of Chartered Accountants (CICA).

1. Accounting Standards for Private Enterprises (ASPE): ASPE applies to private companies, which are typically smaller and privately held businesses. ASPE provides specific accounting principles and guidelines for preparing financial statements in accordance with Canadian Generally Accepted Accounting Principles (GAAP) for private enterprises.
2. Accounting Standards for Not-for-Profit Organizations (ASNPO): ASNPO sets out the accounting

principles for not-for-profit organizations, including charities and other non-profit entities. It provides guidance on how to report financial transactions and activities for these types of organizations.

In addition to ASPE and ASNPO, publicly accountable enterprises in Canada, such as publicly traded companies and certain financial institutions, are required to follow the International Financial Reporting Standards (IFRS) as issued by the International Accounting Standards Board (IASB). IFRS is also used in many other countries worldwide.

It's important to note that accounting standards and regulations can change over time, so I recommend checking with the Canadian Accounting Standards Board or consulting with a qualified accounting professional for the most up-to-date information on accounting standards applicable to businesses in Canada.

Example Chart of Accounts Structure - Canada

Below is a sample outline of a Chart of Accounts for a Canadian company. Please note that the specific accounts may vary based on the company's industry, size, and reporting requirements. Additionally, account numbering conventions may differ between companies, so the numbering used here is just one example.

1. Assets
    - 1.1 Current Assets
        - 1.1.01 Cash and Cash Equivalents
        - 1.1.02 Accounts Receivable
        - 1.1.03 Inventory
        - 1.1.04 Prepaid Expenses
    - 1.2 Non-Current Assets
        - 1.2.01 Property, Plant, and Equipment
        - 1.2.02 Intangible Assets
        - 1.2.03 Investments
        - 1.2.04 Long-term Receivables
        - 1.2.05 Deferred Tax Assets
2. Liabilities
    - 2.1 Current Liabilities

        - § 2.1.01 Accounts Payable
        - § 2.1.02 Short-term Loans
        - § 2.1.03 Accrued Liabilities
        - § 2.1.04 Current Portion of Long-term Debt
    - o 2.2 Non-Current Liabilities
        - § 2.2.01 Long-term Loans
        - § 2.2.02 Deferred Tax Liabilities
        - § 2.2.03 Other Non-Current Liabilities
        - § 2.2.04 Long-term Debt

3. Equity
    - o 3.1 Share Capital
        - § 3.1.01 Common Shares
        - § 3.1.02 Preferred Shares
    - o 3.2 Retained Earnings
    - o 3.3 Additional Paid-In Capital
    - o 3.4 Other Comprehensive Income
4. Revenue
    - o 4.1 Sales Revenue
    - o 4.2 Service Revenue
    - o 4.3 Interest Income
    - o 4.4 Other Operating Revenue
5. Cost of Sales (Cost of Goods Sold)
    - o 5.1 Direct Labor
    - o 5.2 Raw Materials
    - o 5.3 Manufacturing Overheads
6. Expenses
    - o 6.1 Salaries and Wages

- 6.2 Rent and Utilities
- 6.3 Advertising and Marketing
- 6.4 Insurance
- 6.5 Repairs and Maintenance
- 6.6 Supplies and Materials
- 6.7 Depreciation and Amortization
- 6.8 Interest Expense
- 6.9 Taxes and Licences
- 6.10 Bad Debts
- 6.11 Other Operating Expenses

7. Other Income and Expenses
    - 7.1 Gain/Loss on Sale of Assets
    - 7.2 Foreign Exchange Gains/Losses
    - 7.3 Investment Income
    - 7.4 Non-operating Income/Expense
8. Equity Reserve (Optional)
    - 8.1 Capital Reserve
    - 8.2 Revaluation Reserve
    - 8.3 Treasury Stock

Please keep in mind that this is a simplified example, and the actual Chart of Accounts used by a Canadian company may have additional accounts or different sub-categories based on their specific requirements. As always, consulting with an accountant or financial professional familiar with Canadian accounting standards and tax regulations is recommended for tailoring the Chart of Accounts to your company's needs.

What accounts is suggested for payroll in Canada?

There are several accounts that businesses in Canada may use to properly track and manage payroll-related transactions. Some suggested accounts include:

1. Salaries and Wages Expense: This account is used to record the gross wages and salaries paid to employees during a specific period.
2. CPP Payable: This account is used to track the employer and employee portions of the Canada Pension Plan contributions withheld from employees' paychecks.
3. EI Payable: This account is used to track the employer and employee portions of Employment Insurance premiums withheld from employees' paychecks.
4. Income Tax Payable: This account is used to track the amounts of federal and provincial income tax withheld from employees' paychecks.
5. XPP Payable: This account is used to track any extra payroll expenses incurred by a business, such as overtime pay or bonuses, that have not yet been paid to employees.
6. Employee Benefits Payable: This account is used to track any employee benefits owed to employees, such as vacation pay, sick pay, or health insurance premiums.

Properly tracking payroll-related transactions in these accounts is important for accurately reporting payroll expenses, remitting payroll taxes to the government, and ensuring timely payment of employee wages and benefits. It is important to consult with an accountant or bookkeeper to determine the most appropriate accounts for your business's specific payroll needs.

Is there any sub accounts suggested to control Payroll expenses in the balance sheet?

Yes, there are several sub-accounts that businesses in Canada may use to control payroll expenses in the balance sheet. Some suggested sub-accounts include:

1. Gross Payroll: This account is used to track the total amount of salaries and wages paid to employees during a specific period, before any deductions are made for payroll taxes, benefits, or other expenses.
2. Payroll Taxes Payable: This account is used to track the amounts of CPP, EI, and income tax withheld from employees' paychecks and owed to the government.
3. Employee Benefits Payable: This account is used to track the amounts owed to employees for benefits such as vacation pay, sick pay, or health insurance premiums.
4. XPP Payable: This account is used to track any extra payroll expenses incurred by a business, such as overtime pay or bonuses, that have not yet been paid to employees.
5. Net Payroll: This account is used to track the amount of salaries and wages paid to employees after all deductions have been made for payroll taxes, benefits, and other expenses.
6. Wages Payable: This account is used to track the amounts owed to employees for regular wages or

salaries.

Properly tracking payroll expenses in these sub-accounts can help businesses to better control their payroll costs, manage their cash flow, and ensure compliance with payroll regulations. It is important to consult with an accountant or bookkeeper to determine the most appropriate sub-accounts for your business's specific payroll needs.

XPP Payable and CPP Payable is there a difference?

Yes, there is a difference between XPP Payable and CPP Payable.

XPP Payable refers to the extra payroll expenses that have been incurred by a business but have not yet been paid to its employees, such as overtime pay, bonuses, or other forms of additional compensation.

On the other hand, CPP Payable refers to the amounts of Canada Pension Plan contributions that have been withheld from employees' paychecks but have not yet been remitted to the government. Both employers and employees are required to contribute to the CPP program through CPP premiums.

While XPP Payable and CPP Payable are both payroll-related liabilities that businesses must track and remit on time, they represent different types of expenses. XPP Payable is an additional expense incurred by the business, while CPP Payable represents the employer and employee contributions to a mandatory government program.

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

---

USA - Chart of Accounts

Sets of Books: United States of America (USA)

osFinancials and TurboCASH users may download these Sets of Books (templates) free in a matter of a few seconds (using the option, Let osFinancials help you to create a Set of Books). It takes only 3 clicks to download a Set of Books.

After downloading a Set of Books, the Set of Books (template) will automatically open in the language associated with the country and language (*"english-usa"*).

Books with 3-digit main account and 3 -digit-	*Books with 5-digit main account and*



What accounts is suggested for payroll in USA?

In the USA, common accounts used for payroll include:

1. Salaries and Wages Payable: This account is used to record the amount of salaries and wages owed to employees for work performed but not yet paid.
2. Payroll Taxes Payable: This account is used to record the amounts of federal, state, and local payroll taxes that are withheld from employees' paychecks and are owed to the appropriate tax authorities.
3. Employee Benefits Payable: This account is used to record the amounts owed to employees for benefits such as health insurance, retirement plans, and other employee benefits.
4. Accrued Vacation and Sick Pay: This account is used to record the amount of paid time off that employees have earned but not yet taken.
5. Advances from Employees: This account is used to record any amounts advanced to employees and will be deducted from future paychecks.
6. Payroll Clearing: This account is used to reconcile the amounts paid to employees with the amounts recorded in the various payroll accounts.

It is important to note that the specific accounts used may vary depending on the company's accounting practices and chart of accounts. Companies should consult with their accountants or financial advisors to determine the appropriate accounts for their specific circumstances.

Which of these accounts is expense accounts and which accounts is current liabilities?

Of the accounts listed in the previous answer, the following are expense accounts:

1. Salaries and Wages Expense: This account is used to record the amount of salaries and wages earned by employees during a specific period.
2. Payroll Taxes Expense: This account is used to record the amounts of federal, state, and local payroll taxes that are incurred by the employer based on employee wages.
3. Employee Benefits Expense: This account is used to record the cost of providing employee benefits

such as health insurance, retirement plans, and other benefits.

4. Accrued Vacation and Sick Pay Expense: This account is used to record the expense associated with paid time off that employees have earned but not yet taken.

The following account is a current liability:

Salaries and Wages Payable: This account is used to record the amount of salaries and wages owed to employees for work performed but not yet paid. It represents a current liability because it is a debt that is expected to be paid within one year.

The following accounts could be either an expense account or a current liability depending on their balance:

- Payroll Taxes Payable: This account is used to record the amounts of federal, state, and local payroll taxes that are withheld from employees' paychecks and are owed to the appropriate tax authorities. It represents a current liability because it is a debt that is expected to be paid within one year, but it could also be considered an expense account if the employer is required to pay these taxes on its own.
- Advances from Employees: This account is used to record any amounts advanced to employees and will be deducted from future paychecks. It could represent a current liability if the amount advanced is expected to be repaid within one year, but it could also be considered an expense account if the amount advanced is not expected to be repaid.

What s FUTA Payable?

FUTA stands for the Federal Unemployment Tax Act, which is a federal law that requires employers to pay a tax to fund unemployment benefits for eligible workers. FUTA Payable refers to the amount of federal unemployment tax that an employer owes to the government but has not yet paid. The FUTA tax rate is a percentage of the first $7,000 of each employee's wages, and the rate may vary depending on the state where the employer operates. Employers are required to report their FUTA liability on their quarterly federal tax return, and any unpaid FUTA liability may result in penalties and interest charges.

What is SUTA?

SUTA stands for State Unemployment Tax Act, which is a state-level tax that employers must pay to fund unemployment benefits for eligible workers in their state. Each state has its own SUTA tax rate and wage base, which may vary depending on the size of the employer and the industry in which they operate. Employers are typically required to register with their state's workforce agency and pay SUTA taxes on a quarterly basis. The SUTA tax is based on a percentage of the wages paid to employees during a certain period, and the funds collected are used to provide unemployment benefits to eligible workers who have

lost their jobs through no fault of their own. Employers who fail to pay their SUTA taxes or who do not comply with state reporting requirements may be subject to penalties and interest charges.

1030 Payroll Checking Account - Which transactions is processed in this account?

The Payroll Checking Account (1030) is typically used to process transactions related to payroll. This account is used to record the deposits of funds from the employer's bank account to cover payroll expenses, as well as the payments made to employees via direct deposit or checks. The following transactions are typically processed in this account:

1. Deposit of funds to cover payroll expenses: This includes the deposit of funds from the employer's bank account to cover the total payroll expense for a specific period.
2. Payment of wages to employees: This includes the payment of wages and salaries to employees via direct deposit or checks.
3. Payment of payroll taxes: This includes the payment of federal, state, and local payroll taxes that are withheld from employees' paychecks and are owed to the appropriate tax authorities.
4. Payment of employee benefits: This includes the payment of employee benefits such as health insurance premiums, retirement plan contributions, and other benefits.
5. Reconciliation of account balances: This includes the reconciliation of the Payroll Checking Account balance with the total payroll expense for the period, as well as the verification of the accuracy of individual employee paychecks and the payroll tax calculations.

It is important to note that the specific transactions processed in this account may vary depending on the company's payroll processes and accounting practices. Companies should consult with their accountants or financial advisors to determine the appropriate transactions to process in this account.

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Example and notes for a 4-digit Chart of Accounts

Control accounts when creating a Set of Books from scratch

In osFinancials5/TurboCASH5, when creating a Set of Books from scratch using the "*Customize your own Set of Books (Advanced)?*" option in the "*Creation wizard*", you have the flexibility to define your chart of accounts according to your specific needs and requirements.

As part of this customization process, you will have the opportunity to set the number of main digits for your accounts, ranging from 3 to 8 digits. Additionally, you will specify the account numbers for three main control accounts: the Creditors control account, Debtors control account, and Retained earnings account.

1. The Creditors control account is a general ledger account that represents the total amount owed to the company by its creditors or suppliers. It serves as a summary account for all individual creditor accounts and helps track the company's outstanding payables.
2. The Debtors control account, on the other hand, is a general ledger account that represents the total amount owed to the company by its debtors or customers. It acts as a summary account for all individual debtor accounts and aids in monitoring the company's receivables.
3. The Retained earnings account, reflects the cumulative net earnings or profits of the company that have been retained and reinvested in the business. It represents the portion of equity that is derived from the company's profitability and serves as a financial record of the accumulated profits over time.

By defining these main control accounts during the Set of Books creation process, you can structure your chart of accounts and design the account numbering system that aligns with your specific accounting practices and reporting requirements.

Account number	*Description*	*Notes*
G2000-000	*Creditor's control*	*The Creditor's control account, also known as the Accounts payable control account or Creditor's control ledger account, is a general ledger account used to track and summarize the total amount owed to creditors or suppliers by a business.* *It represents the outstanding balances of individual creditor accounts in the accounts payable subsidiary ledger. The subsidiary ledger contains detailed information about each specific creditor, such as their name, contact details, and transaction history.* *The purpose of the Creditor's control account is to provide a summary of all the amounts owed to creditors at any given time. It helps businesses monitor their payable balances, track payment due dates, and ensure accurate financial reporting.* *Transactions related to purchases on credit from suppliers, invoice payments, and adjustments are recorded in both the subsidiary ledger (creditor accounts) and the Creditor's control account in the general ledger. The balances of individual creditor accounts are periodically reconciled with the balance in the Creditor's control account to ensure accuracy.*

		The Creditor's control account is an important component of a business's financial records, enabling effective management of accounts payable and ensuring timely payment to creditors.
G1100-000	*Debtor's control*	*The Debtor's control account, also known as the Accounts receivable control account or Debtor's control ledger, is a general ledger account used to track and summarize the total amount owed by debtors or customers to a business.* *Similar to the Creditor's control account, the Debtor's control account represents the outstanding balances of individual debtor accounts in the accounts receivable subsidiary ledger. The subsidiary ledger contains detailed information about each specific debtor, including their name, contact details, and transaction history.* *The primary purpose of the Debtor's control account is to provide a summary of all the amounts owed by customers at any given time. It helps businesses monitor their receivable balances, track payment due dates, and ensure accurate financial reporting.* *Transactions related to sales on credit to customers, receipt of customer payments, and adjustments are recorded in both the subsidiary ledger (debtor accounts) and the Debtor's Control Account in the general ledger. The balances of individual debtor accounts are periodically reconciled with the balance in the Debtor's Control Account to ensure accuracy.* *The Debtor's Control Account plays a crucial role in managing a business's accounts receivable, allowing for effective tracking of customer balances and timely collection of payments. It provides valuable information for cash flow management, credit control, and financial analysis.*
G3900-000	*Retained earnings*	*The Retained earnings account, also known as the Accumulated earnings account or Earnings surplus, is a general ledger account that represents the cumulative net earnings or profits of a company that have been retained and reinvested in the business rather than distributed to shareholders as dividends.* *Retained earnings are generated from the company's net income, which is calculated by deducting expenses from revenues. Instead of distributing all of the net income to shareholders, a portion of it is retained within the company. This retained portion is added to the Retained earnings account.* *The Retained earnings account serves as a financial record of the company's accumulated profits over time. It reflects the cumulative value of the company's retained earnings from its inception until the present. The*

account is adjusted at the end of each accounting period to reflect changes in net income and any dividends declared.

The Retained earnings account is an important component of the company's equity section on the balance sheet. It represents the portion of equity that is derived from the company's profitability and retained within the business. Retained earnings can be used for various purposes, such as reinvesting in the business, funding expansion projects, reducing debt, or distributing dividends in the future.

The balance in the Retained earnings account is carried forward from one accounting period to the next. It serves as a source of funding for future growth and helps to enhance the company's financial stability and flexibility. The account also provides insights into the historical profitability and financial performance of the company.

Basic outline for a 4-digit main accounts chart of accounts

The outline for the chart of accounts is a general framework that can be applicable to various accounting systems, including IFRS for SMEs. It covers different categories of accounts that are commonly found in financial reporting. While the account ranges and specific names may vary depending on the company and reporting requirements, the general structure remains similar.

The suggested outline includes:

1. Asset accounts (1000 - 1999): Accounts representing various types of assets owned or controlled by the business, such as cash, receivables, inventory, and fixed assets. They include cash, short-term investments, accounts receivable, inventory, prepaid expenses, property, plant, and equipment, intangible assets, investments, and other assets.
2. Liability accounts (2000 - 2999): Accounts representing the financial obligations or debts of the business to external parties, including payables, borrowings, and accrued liabilities. They include accounts payable, accrued expenses, short-term borrowings, long-term borrowings, deferred revenue, and other current and long-term liabilities.
3. Equity accounts (3000 - 3999): Accounts representing the equity portion of the company's capital structure, depending on the type of business ownership (sole proprietorship, partnership, corporation, LLC). For a sole proprietorship, they typically include owner's capital, owner's drawings, and retained earnings. In a partnership, they include partner's capital accounts, partner's drawings, partner's profit and loss allocation, and retained earnings. In a corporation, they include common stock, preferred stock, additional paid-in capital, retained earnings, and treasury stock. In a limited liability company (LLC), they include member's capital accounts, member's drawings, member's profit and loss

allocation, and retained earnings.

4. Revenue accounts (4000 - 4999): Accounts representing the income or revenue generated by the company's primary business activities. They include operating revenue, which is directly related to the core operations, and other revenue, which includes income from sources incidental or peripheral to the main operations.
5. Cost of Goods Sold (COGS) accounts (5000 - 5999): Accounts reflecting the direct costs associated with producing or acquiring the goods or services sold by the company. The specific account names may vary, such as Cost of Sales (COS) or Cost of Services Rendered (SOSR), depending on the nature of the business.
6. Expense accounts (6000 - 7999): Accounts representing the operating expenses incurred by the business in its day-to-day operations. They include wages, rent, utilities, materials, and other expenses directly related to the revenue-generating activities.
7. Non-operating revenue accounts (8000 - 8999): Accounts recording income or revenue generated by the business that is not directly related to its core operations. It includes sources of income that are incidental, peripheral, or non-recurring in nature.
8. Non-operating expenses accounts (9000 - 9999): Accounts reflecting expenses incurred by the business that are not directly related to its core operations. They typically arise from activities outside the normal operations and are separate from operating expenses.

This summary is a general outline of the typical accounts found within each range.

It's important to customize and adjust this chart of accounts and reporting framework to suit your business's specific requirements and comply with the relevant reporting standards, tax regulations, and accounting frameworks in your jurisdiction and country. Factors such as your business ownership type, industry, and other specific needs should be considered when adapting the chart of accounts and reporting framework to ensure accurate and relevant financial reporting for your business.

Expanded outline for a 4-digit main accounts chart of accounts

The following expanded summary serves as a general guide outlining the common accounts within each range. It includes account groups or classifications linked to financial categories like assets, liabilities, equity, income, and expenses. This summary provides a recommended numbering template to follow when designing and numbering your accounts.

The chart of accounts is based on a four-digit numbering system, which helps organize all your accounts. Here’s the most common numbering template to follow when designing and numbering your accounts:

- Asset accounts (1000 - 1999): Assets are economic resources that are owned or controlled by a

business or individual and are expected to provide future benefits. In accounting, assets are recorded on a balance sheet and represent the value of what an entity owns. Assets can take various forms, including cash, inventory, property, equipment, investments, and intellectual property.

Asset accounts in the range of 1000-1999 typically represent various types of assets on a company's balance sheet. Here's a concise summary of these asset accounts:

1. Cash and Cash Equivalents (1000-1099): This account includes cash on hand, demand deposits, and highly liquid short-term investments that can be readily converted into cash.
2. Short-term Investments (1100-1199): These accounts cover investments in securities and other financial instruments that are expected to be converted into cash within a relatively short period, typically one year or less.
3. Accounts Receivable (1200-1299): This account represents amounts owed to the company by its customers or clients for goods sold or services rendered on credit.
4. Inventory (1300-1399): This account includes the cost of raw materials, work-in-progress, and finished goods held by the company for sale or production.
5. Prepaid Expenses (1400-1499): This account represents expenses that have been paid in advance but have not yet been incurred or used. Examples include prepaid insurance, prepaid rent, or prepaid subscriptions.
6. Property, Plant, and Equipment (1500-1599): This account encompasses the tangible assets used in the business, such as land, buildings, machinery, vehicles, and furniture.
7. Intangible Assets (1600-1699): These accounts capture non-physical assets, such as patents, copyrights, trademarks, goodwill, and intellectual property, which provide long-term value to the business.
8. Investments (1700-1799): This account includes long-term investments in equity securities, bonds, and other financial instruments that are not expected to be converted into cash within the next year.
9. Other Assets (1800-1999): This account serves as a catch-all category for any additional assets that don't fit into the above classifications. It may include items like deferred tax assets, advances to suppliers, or miscellaneous assets.

It's important to note that the specific account numbers and classifications may vary depending on the company's chart of accounts and reporting framework. The above summary provides a general overview of common asset accounts within the given range.

- Liability accounts (2000 - 2999): Liabilities are obligations or debts that a business or individual owes to external parties. They represent the claims or obligations that others have on the assets of the

entity. In accounting, liabilities are recorded on the balance sheet and reflect the financial obligations that need to be fulfilled in the future.

The range of accounts from 2000 to 2999 typically represents liability accounts in the chart of accounts. These accounts capture the various types of financial obligations or debts that a business owes to external parties. Here is a concise summary of common liability accounts within this range:

1. Accounts Payable (2000-2099): This account represents the amount owed to suppliers or vendors for goods or services received on credit. It includes unpaid invoices and bills that are due to be paid.
2. Accrued Expenses (2100-2199): These are expenses that have been incurred but not yet paid or recorded in the accounting system. They include accrued wages, accrued interest, and accrued utilities.
3. Short-term Borrowings (2200-2299): This account captures short-term loans or borrowings that are due within one year or the normal operating cycle of the business. It includes bank loans, lines of credit, and short-term notes payable.
4. Long-term Borrowings (2300-2399): This account represents long-term loans or borrowings that extend beyond the next year. It includes long-term bank loans, bonds payable, and other long-term debt obligations.
5. Deferred Revenue (2400-2499): Also known as unearned revenue, this account records the amount received in advance from customers for goods or services that are yet to be delivered. It represents an obligation to provide the products or services in the future.
6. Other Current Liabilities (2500-2599): This category includes various short-term financial obligations that do not fit into specific accounts mentioned above. It may include items such as accrued taxes, customer deposits, and other short-term liabilities.
7. Other Long-term Liabilities (2600-2699): Similar to other current liabilities, this category captures long-term financial obligations that are not classified under specific accounts. It may include items such as deferred tax liabilities, long-term customer deposits, and other long-term liabilities.

These are just a few examples of common liability accounts within the 2000-2999 range. The specific accounts and their numbering may vary depending on the organization's chart of accounts and industry-specific requirements.

- Equity accounts (3000 - 3999): The complexity of required accounts for the equity financial category in the chart of accounts can vary depending on the type of business ownership. Here is a brief summary of the accounts typically used for equity in different types of business ownership:

1. Sole Proprietorship:
    - § Owner's Capital: Represents the owner's investment in the business.
    - § Owner's Drawings: Records withdrawals made by the owner for personal use.
    - § Retained Earnings: Accumulated profits or losses that have been retained in the business.
2. Partnership:
    - § Partner's Capital Accounts: Each partner has a separate capital account to track their investment in the partnership.
    - § Partner's Drawings: Records withdrawals made by partners for personal use.
    - § Partner's Profit and Loss Allocation: Tracks the allocation of profits or losses among partners based on their agreed-upon sharing ratios.
    - § Retained Earnings: Accumulated profits or losses that have been retained in the partnership.
3. Corporation:
    - § Common Stock: Represents the ownership interest of common shareholders.
    - § Preferred Stock: Represents the ownership interest of preferred shareholders, if applicable.
    - § Additional Paid-in Capital: Records the amount received from shareholders in excess of the par value of the shares.
    - § Retained Earnings: Accumulated profits or losses that have not been distributed to shareholders as dividends.
    - § Treasury Stock: Represents shares of the corporation's own stock that have been repurchased and are held by the corporation.
4. Limited Liability Company (LLC):
    - § Member's Capital Accounts: Each member has a separate capital account to track their investment in the LLC.
    - § Member's Drawings: Records withdrawals made by members for personal use.
    - § Member's Profit and Loss Allocation: Tracks the allocation of profits or losses among members based on their agreed-upon sharing ratios.
    - § Retained Earnings: Accumulated profits or losses that have been retained in the LLC.

The complexity of these accounts may vary depending on the specific requirements of the business and any additional factors applicable to the industry or jurisdiction. It is important to consult with an accountant or financial professional to ensure the chart of accounts accurately reflects the equity structure and financial reporting needs of the specific business ownership type.

- Revenue accounts (4000 - 4999):
    - Operating revenue are the revenue generated through the primary business activities or core operations by a business. It represents the income earned from the sale of goods, provision of services, or other activities directly related to the main operations of the business.
    - Other revenue refers to income or revenue generated by a company from sources other than its primary business activities or core operations. It includes income that is incidental or peripheral to the main operations of the company. It is often considered as supplementary or ancillary revenue. Examples of accounts that can be categorized as "Other Revenue" and are not necessarily non-operating revenue. These accounts represent income or revenue generated from sources that are not directly related to the company's primary business activities. Here are some examples:
        1. Dividend Income: Income received from owning shares of other companies, typically in the form of dividends.
        2. Donations or Gifts: Any non-business-related contributions or gifts received.
        3. Gain on Sale of Assets: Profits realized from the sale of non-inventory assets like property, equipment, or investments. When a company sells its assets, such as property, equipment, or investments, at a price higher than their carrying value, the difference between the sale proceeds and the book value is recognized as a gain and recorded as Other Revenue.
        4. Insurance Proceeds / Insurance Reimbursements: Amounts received from insurance claims due to unexpected events or losses. If a company receives insurance reimbursements for claims related to damages, losses, or liabilities, the amount received would be classified as Other Revenue.
        5. Interest Income: Interest earned on bank deposits, loans to others, or any interest-bearing securities.
        6. Foreign Exchange Gains: Gains resulting from favourable currency exchange rate fluctuations. Companies that engage in international transactions may have foreign currency exchange gains when converting foreign currencies back to the reporting currency.

7. Recovery of Bad Debts: Income obtained from previously written-off bad debts that have now been recovered.
8. Rental Income: Revenue generated from leasing out property, equipment, or other assets. If a company owns properties or assets that are rented out to third parties, the rental income generated from those assets would be considered as Other Revenue.
9. Royalties and Licensing Fees: Income earned from granting the use of intellectual property, trademarks, or patents.If a company licences its intellectual property, such as patents, trademarks, or copyrights, to other entities in exchange for royalties, the income received from those royalties would fall under Other Revenue.
10. Miscellaneous Income: Any other sources of income that do not fit into the primary revenue categories.

Other Income" is a general accounting term used to classify revenue or income that does not arise from a company's primary business operations or core activities. It includes various non-operating or incidental sources of income that are not directly related to the sale of goods or services.

Other Income is typically recorded in a separate section of the income statement or profit and loss statement, apart from the main revenue from operations. It is essential to segregate Other Income to provide a clear picture of the business's primary revenue-generating activities and any additional income streams.

It's important to note that the specific items included under Other Income will depend on the nature of the business and its operations. Some companies may have more diverse sources of other income than others. Accurate recording and proper classification of Other Income are crucial for transparent financial reporting and analysis.

As with any accounting terminology, it's always best to refer to the organization's accounting policies and consult with a qualified accountant or financial professional for clarity and accuracy in financial reporting.

These examples demonstrate that Other Revenue accounts can encompass a variety of income sources that are not directly related to the company's core operations. It's important to note that the specific accounts and classifications may vary depending on the industry and the company's individual circumstances.

- Cost of Goods Sold (COGS) (5000 - 5999): Gross profit is calculated by subtracting the COS, COGS, or SOSR from the revenue generated from the sale of goods or services. It represents the profit generated from the core operations of the business before considering other operating expenses. Gross profit provides insight into the efficiency and profitability of a company's primary revenue-

generating activities.

- Cost of Sales (COS): Cost of Sales is a broader term that encompasses the cost associated with both goods and services sold by a company. It includes the direct costs incurred in producing or providing the products or services, such as raw materials, labour, and overhead costs. COS is typically used in service-oriented businesses where goods are not the primary focus.
- Cost of Goods Sold (COGS): COGS specifically refers to the direct costs incurred in producing or acquiring the goods that are sold by a company. It includes the cost of raw materials, direct labour, and manufacturing overhead directly associated with the production of goods. COGS is primarily used in manufacturing, retail, and distribution businesses.
- Cost of Services Rendered (SOSR): SOSR is similar to COGS but applies specifically to service-based businesses. It represents the direct costs associated with providing services to customers, such as labour, subcontractor fees, and any other expenses directly related to delivering the services.

- Expense accounts (6000 - 7999): Operating expenses are expenses incurred by a business in the ordinary course of its operations, such as wages, rent, utilities, and materials. These expenses are directly related to the revenue-generating activities of the business and are subtracted from revenue to arrive at operating income.
- Non-operating revenue (8000 - 8999): Non-operating revenue refers to income or revenue generated by a business that is not directly related to its core operations or primary business activities. It includes sources of income that are incidental, peripheral, or non-recurring in nature. Non-operating revenue typically arises from activities that are outside the day-to-day operations of the business.
- Non-operating expenses (9000 - 9999): Non-operating expenses refer to expenses incurred by a business that are not directly related to its core operations or primary business activities. These expenses are typically incidental, peripheral, or non-recurring in nature. Non-operating expenses arise from activities that are outside the day-to-day operations of the business. They are usually separate from the expenses directly associated with producing or delivering goods or services. Non-operating expenses are expenses that are not directly related to the core revenue-generating activities of the business. They typically arise from activities outside of the normal operations, such as interest expense, foreign exchange losses, or one-time charges. Non-operating expenses are reported separately from operating expenses and are taken into account when calculating net income.

The sample chart of account numbers serves as a guideline and helps you understand the different accounts that should be established and the procedure for adding new account numbers.

Balance sheet

In osFinancials5/TurboCASH5, the Balance sheet accounts represent the Assets, Liabilities, and Equity items of a company. These accounts can be further organised and classified by utilising up to two account groups, namely Account group 1 and Account group 2. You can configure these account groups in the Setup → Groups menu on the Setup ribbon. It is important to link these account groups to the corresponding financial categories in the Setup → Financial categories menu on the Setup ribbon.

G2000-000	*Creditor's control*	*The Creditor's control account, also known as the Accounts payable control account or Creditor's control ledger account, is a general ledger account used to track and summarize the total amount owed to creditors or suppliers by a business.* *It represents the outstanding balances of individual creditor accounts in the accounts payable subsidiary ledger. The subsidiary ledger contains detailed information about each specific creditor, such as their name, contact details, and transaction history.* *The purpose of the Creditor's control account is to provide a summary of all the amounts owed to creditors at any given time. It helps businesses monitor their payable balances, track payment due dates, and ensure accurate financial reporting.* *Transactions related to purchases on credit from suppliers, invoice payments, and adjustments are recorded in both the subsidiary ledger (creditor accounts) and the Creditor's control account in the general ledger. The balances of individual creditor accounts are periodically reconciled with the balance in the Creditor's control account to ensure accuracy.* *The Creditor's control account is an important component of a business's financial records, enabling effective management of accounts payable and ensuring timely payment to creditors.*
G1100-000	*Debtor's control*	*The Debtor's control account, also known as the Accounts receivable control account or Debtor's control ledger, is a general ledger account used to track and summarize the total amount owed by debtors or customers to a business.* *Similar to the Creditor's control account, the Debtor's control account represents the outstanding balances of individual*

		debtor accounts in the accounts receivable subsidiary ledger. The subsidiary ledger contains detailed information about each specific debtor, including their name, contact details, and transaction history. *The primary purpose of the Debtor's control account is to provide a summary of all the amounts owed by customers at any given time. It helps businesses monitor their receivable balances, track payment due dates, and ensure accurate financial reporting.* *Transactions related to sales on credit to customers, receipt of customer payments, and adjustments are recorded in both the subsidiary ledger (debtor accounts) and the Debtor's Control Account in the general ledger. The balances of individual debtor accounts are periodically reconciled with the balance in the Debtor's Control Account to ensure accuracy.* *The Debtor's Control Account plays a crucial role in managing a business's accounts receivable, allowing for effective tracking of customer balances and timely collection of payments. It provides valuable information for cash flow management, credit control, and financial analysis.*
G3900-000	*Retained earnings*	*The Retained earnings account, also known as the Accumulated earnings account or Earnings surplus, is a general ledger account that represents the cumulative net earnings or profits of a company that have been retained and reinvested in the business rather than distributed to shareholders as dividends.* *Retained earnings are generated from the company's net income, which is calculated by deducting expenses from revenues. Instead of distributing all of the net income to shareholders, a portion of it is retained within the company. This retained portion is added to the Retained earnings account.* *The Retained earnings account serves as a financial record of the company's accumulated profits over time. It reflects the cumulative value of the company's retained earnings from its inception until the present. The account is adjusted at the end of each accounting period to reflect changes in net income and any dividends declared.*

The Retained earnings account is an important component of the company's equity section on the balance sheet. It represents the portion of equity that is derived from the company's profitability and retained within the business. Retained earnings can be used for various purposes, such as reinvesting in the business, funding expansion projects, reducing debt, or distributing dividends in the future.

The balance in the Retained earnings account is carried forward from one accounting period to the next. It serves as a source of funding for future growth and helps to enhance the company's financial stability and flexibility. The account also provides insights into the historical profitability and financial performance of the company.

ASSET ACCOUNTS - 1000 - 1999

CASH AND CASH EQUIVALENTS (1000 - 1099) - These accounts represents the actual cash on hand, as well as cash equivalents that can be quickly converted into cash, such as cash on hand, bank accounts or short-term investments.

G1000-000 Petty cash

B1010-000 Current bank account

CURRENT ASSETS (1100 - 1499) - These are the assets of a business that are expected to be converted into cash or used up within one year or within the normal operating cycle of the business, whichever is longer. They are resources that can be readily converted into cash or used to support the ongoing operations of the business. These current assets are typically used by the company in its day-to-day operations or are expected to be converted into cash within a relatively short period.

G1100-000 Debtor's control

Debtor's control represents the total outstanding receivables owed to a company by its customers. When a company extends credit to its customers, it creates accounts receivable, which are recorded as assets on the balance sheet. The debtor's control account is a summary or aggregate account that captures the total amount of accounts receivable owed to the company.

The debtor's control account is typically used in conjunction with individual customer accounts or subsidiary ledgers. Each customer's outstanding balance is recorded separately in their respective customer accounts, while the debtor's control account provides a summarized view of all the outstanding

		receivables. *As payments are received from customers, the debtor's control account is updated to reflect the reduced balances of accounts receivable. The account is debited when new sales are made on credit and credited when payments are received.* *The debtor's control account helps the company monitor and manage its receivables effectively. It provides a centralized view of the overall receivables position, enabling management to assess the creditworthiness of customers, track payment trends, and take appropriate actions for collection.* *It's important to regularly reconcile the debtor's control account with the individual customer accounts to ensure accuracy and identify any discrepancies. Reconciliation helps identify any errors, unrecorded payments, or disputes that need resolution.* *The debtor's control account is a key component of the company's financial statements, particularly the balance sheet, where it is reported as a current asset. It provides important information about the company's liquidity, credit risk, and the value of outstanding receivables.* *It's recommended to consult with an accountant or financial professional to determine the specific treatment and accounts to be used for the debtor's control account in your business's chart of accounts. They can provide guidance based on your company's specific needs and accounting practices.*
G1110-000	*Provision for doubtful debts*	*Provision for doubtful debts is an estimate made by a company to account for potential losses from customers who may default on their payment obligations. When a company extends credit to customers or sells goods or services on credit, there is a risk that some customers may not fulfil their payment obligations, leading to bad debts.* *To account for this risk, companies create a provision for doubtful debts on their balance sheet. The provision is based on historical data, past payment patterns, creditworthiness of customers, and other relevant factors. It represents the amount that the company expects to write off as bad debts or be unable to collect from customers.* *The provision for doubtful debts is typically calculated as a percentage of accounts receivable or based on specific*

		customer balances. The purpose of this provision is to anticipate and account for the potential losses in the financial statements, providing a more accurate representation of the company's financial position. *The provision for doubtful debts is reported as a contra-asset account on the balance sheet, reducing the value of accounts receivable. It is a conservative accounting approach that recognizes the risk of bad debts and ensures that the financial statements reflect the estimated collectability of receivables.* *When actual bad debts occur, the company writes off the specific amounts from the provision for doubtful debts and reduces the accounts receivable balance accordingly. This adjustment reflects the actual losses incurred by the company.* *It's important for businesses to regularly review and update the provision for doubtful debts to ensure it remains appropriate and reflective of the company's credit risk. Factors such as changes in customer payment behaviour, economic conditions, and specific customer circumstances may require adjustments to the provision.* *It's recommended to consult with an accountant or financial professional to determine the specific treatment and accounts to be used for the provision for doubtful debts in your business's chart of accounts.*
G1200-000	*Stock / Inventory*	*Stock or inventory includes the raw materials, work-in-progress (partially completed goods), and finished goods that a company holds. It represents the goods that are available for sale to customers or are used in the production process.* *Inventory is an essential component of various businesses, such as retailers, manufacturers, wholesalers, and distributors. It enables these businesses to meet customer demand, fulfil orders, and generate revenue.* *The stock/inventory account is used to track the quantity and value of the goods held by the company. It includes the cost of acquiring or producing the inventory, which consists of direct costs (such as materials and labour) and indirect costs (such as overhead expenses).* *Inventory is typically classified into different categories based on its nature or stage of completion. Common inventory*

		categories include raw materials, work-in-progress, and finished goods. Each category may have its specific accounts or sub-accounts to track the related inventory items. *The stock/inventory account is updated regularly to reflect the changes in quantity and value of the inventory. This includes recording purchases, sales, returns, adjustments for damaged or obsolete goods, and any other inventory-related transactions.* *Accurate inventory management is crucial for businesses to ensure sufficient stock levels, minimize holding costs, prevent stock-outs or overstocking, and optimize cash flow. It involves inventory valuation methods, such as First-In-First-Out (FIFO), Last-In-First-Out (LIFO), or weighted average cost, to determine the cost of goods sold and the value of remaining inventory.* *The stock/inventory account is reported as a current asset on the balance sheet, representing the value of inventory held at a specific point in time. It's important to conduct regular physical inventory counts or use inventory management systems to reconcile the recorded inventory balances with the actual stock on hand.* *The specific accounts and classifications for stock/inventory may vary depending on the company's industry, size, and accounting practices. It's recommended to consult with an accountant or financial professional to determine the appropriate structure and accounts for tracking inventory in your business's chart of accounts.*
G1300-000	*Accrued revenue / Outstanding revenue*	*Accrued revenue is revenue that has been earned but not yet received or recorded. It occurs when a company provides goods or services to a customer, but the payment or recognition of the revenue is delayed beyond the normal billing cycle. The company recognizes the revenue in its financial statements even though the cash has not been received.* *Examples of accrued revenue include:* • *Services rendered: A service-based company may provide services to a client but bill them at the end of the month or project.*

- *Rent income: If a company owns rental properties, it may accrue rent revenue when it's earned, even if the tenant pays at a later date.*
- *Interest income: Financial institutions may accrue interest income on loans or investments that have not yet been paid or received.*
- *Commission income: Sales representatives or agents may earn commissions based on sales made, but the actual payment may be delayed.*

Accrued revenue is recorded as an asset on the balance sheet and recognized as revenue on the income statement. The company creates an adjusting entry to increase the accounts receivable or accrued revenue account and recognizes the corresponding revenue.

Accrued revenue is important for accurate financial reporting as it reflects the company's true financial performance, even if the cash is not yet received. It allows businesses to properly recognize revenue in the period it was earned, matching revenue with the expenses incurred to generate that revenue.

G1350-000	*Prepaid expenses / Expenses paid in advance*	*Prepaid expenses are costs that have been paid in advance but have not yet been consumed or used. They represent future expenses that have been prepaid to ensure the availability of goods, services, or benefits over a specific period of time. Prepaid expenses are recorded as assets on the balance sheet until they are gradually recognized as expenses over the periods to which they relate.*

Examples of prepaid expenses include:

- *Prepaid Rent: Payment made in advance for rent on a property or facility.*
- *Prepaid Insurance: Premiums paid upfront for insurance coverage extending beyond the current accounting period.*
- *Prepaid Subscriptions: Payments made in advance for magazine subscriptions, software licences, or other subscription-based services.*
- *Prepaid Maintenance: Costs paid in advance for*

maintenance services or contracts.

- *Prepaid Advertising: Amounts paid upfront for advertising campaigns or marketing services.*
- *Prepaid Supplies: Costs of supplies or inventory items purchased in advance and used gradually over time.*

Prepaid expenses are gradually recognized as expenses through an adjusting entry process. As time passes or the benefits are consumed, the prepaid expenses are expensed, reducing the asset account and increasing the corresponding expense account.

Properly tracking and managing prepaid expenses is essential for accurate financial reporting and budgeting. It ensures that expenses are recognized in the appropriate accounting periods and helps in determining the true profitability of a business. Consulting with an accountant or financial professional can provide further guidance on the specific treatment and accounts to be used for prepaid expenses in your business's chart of accounts.

G1400-000 Short-term - Deposits

PP&E - PROPERTY, PLANT, AND EQUIPMENT (1500 - 1699) - This account represents tangible assets such as land, buildings, machinery, equipment, and vehicles that are used in the business operations to generate revenue. These assets are expected to be used for more than one accounting period and are not intended for resale.

PP&E includes various types of assets, such as land, buildings, machinery, vehicles, furniture, and equipment. These assets are essential for the company's day-to-day operations and are typically necessary to produce goods, provide services, or support the business activities.

PP&E is recorded on the balance sheet at its original cost, which includes the purchase price, transportation costs, installation costs, and any other costs directly attributable to acquiring and preparing the asset for use. Over time, the value of PP&E is systematically reduced through depreciation, reflecting the wear and tear, obsolescence, or decline in value of the assets.

The purpose of recording PP&E is to track the company's investment in long-term productive assets and to provide information about their value, usage, and depreciation over time. The value of PP&E is typically disclosed on the balance sheet, and any changes in the value or disposal of these assets are recorded in the income statement or statement of cash flows.

Proper management and maintenance of PP&E is crucial for businesses to ensure the continued efficiency and productivity of their operations. Regular assessments, maintenance, and periodic revaluations are performed

to ensure that the carrying value of these assets is appropriate and reflects their true economic value.

G1510-000	*Furniture & Fittings*
G1510-010	*Furniture & Fittings at cost*
G1510-020	*Accumulated depreciation - Furniture & Fittings*
G1520-000	*Equipment*
G1520-010	*Equipment at cost*
G1520-020	*Accumulated depreciation - Equipment*
G1530-000	*Computer equipment*
G1530-010	*Computer equipment at cost*
G1530-020	*Accumulated depreciation - Computer equipment*
G1540-000	*Vehicles*
G1540-010	*Vehicles at cost*
G1540-020	*Accumulated depreciation - Vehicles*
G1600-000	*Land and Buildings*
G1600-010	*Land and Buildings at cost*
G1600-020	*Land and Buildings - Improvements*
G1600-030	*Amortisation - Land and Buildings*

OTHER NON-CURRENT ASSETS (1700-1799) - Other Non-Current Assets is a category in the Chart of Accounts that includes a wide range of items that are important for a company's operations, growth, and

revenue generation. These assets are expected to provide economic benefits to the company over an extended period of time, typically beyond one year.

This category is designed to capture any non-current assets that don't fit into the standard asset classifications like property, buildings, equipment, vehicles, and intangible assets. It allows businesses to account for specific long-term assets that are unique or industry-specific and may not be adequately represented in the standard asset categories.

Some examples of assets that could be included in "Other Non-Current Assets" are:

G1700-000	*Long-term - investments*	*These accounts tracks investments in other companies, bonds, or long-term securities that are not readily convertible into cash within one year.*
G1710-000	*Long-term - Notes receivable*	*Loans made to other parties, which will be repaid over an extended period, beyond one year.*
G1720-000	*Deferred Tax assets*	*Tax benefits that the business expects to realize in the future due to temporary differences between accounting and tax treatment.*
G1730-000	*Security deposits*	*Deposits made to landlords or service providers that will be refundable at a later date, typically when a lease or contract ends.*
G1740-000	*Long-term - Prepaid expenses*	*Prepaid expenses that will be utilized over more than one year, such as long-term insurance premiums.*
G1750-000	*Mineral rights*	*Rights to extract minerals or resources from land owned by the business.*
G1760-000	*Leasehold improvements*	*Improvements made to leased premises, which are amortized over the lease term.*
G1770-000	*Deferred charges*	*Costs incurred that will be expensed over time, such as organization costs or startup expenses.*
G1780-000	*Long-term - Deposits*	*Deposits held with suppliers or vendors that will be used over an extended period.*
G1790-000	*Deferred Financing costs*	*Costs related to obtaining long-term financing, which are amortized over the loan term.*

The inclusion of "Other Non-Current Assets" in the Chart of Accounts allows businesses to provide more

comprehensive financial reporting and accurately represent the composition of their long-term assets. If the business has unique or industry-specific assets that don't fit into the standard asset categories, they can be appropriately grouped under "Other Non-Current Assets" for better accounting and reporting.

It's important to note that the specific assets included under "Other Non-Current Assets" will depend on the nature of the business and its operations.

It's important to note that the specific assets included under "Other Non-Current Assets" will depend on the nature of the business and its operations. If the business has unique or industry-specific assets that don't fit into the standard asset categories, they can be appropriately grouped under "Other Non-Current Assets" for better accounting and reporting.

As always, it's advisable to consult with a qualified accountant to ensure the Chart of Accounts accurately represents the business's financial position and meets reporting requirements.

INTANGIBLE ASSETS (1800-1999)- Intangible assets are non-physical assets that lack a physical substance but have value and provide economic benefits to a business. Unlike tangible assets, which can be seen or touched, intangible assets are more conceptual or intellectual in nature. They represent legal or contractual rights, intellectual property, brand recognition, or other intangible qualities that contribute to a company's value and competitive advantage.

Intangible assets are typically recorded on the balance sheet at their acquisition cost or fair value if acquired through a business combination. They are amortized over their estimated useful lives, reflecting the gradual consumption or expiration of their economic benefits. However, certain intangible assets with indefinite useful lives, such as goodwill, are not amortized but are subject to periodic impairment assessments.

Managing and protecting intangible assets is important for businesses to safeguard their competitive advantages, maintain brand value, and ensure legal compliance. Proper valuation, strategic utilization, and adequate legal protection of these assets are essential for maximizing their value and contributing to the overall success of a business.

Examples of intangible assets include:

	Brand names	*This account records the names or labels by which a business is recognized and distinguished in the market. It represents the reputation, image, and goodwill associated with a particular brand. Brand names can be highly valuable assets as they contribute to customer recognition, loyalty, and the ability to differentiate products or services from competitors.*
G1900-000	*Copyrights*	*This account records the cost or value of copyrights held by the business, which protect original literary, artistic, or musical works.*
	Customer lists	*Customer lists are databases or records of existing or potential*

		customers, including their contact information, purchasing history, preferences, and other relevant data. They are valuable assets that help businesses maintain and grow their customer base.
	Franchise rights	*This account represents the value of franchise rights obtained by the business, allowing it to operate under a recognized brand and business model.*
G1910000	*Goodwill*	*Goodwill represents the value of a company's reputation, customer relationships, and brand recognition. It is typically recorded when a company acquires another business for a price higher than the fair value of its identifiable tangible and intangible assets.* *This account represents the excess of the purchase price of a business over the fair value of its identifiable net assets.*
	Intellectual property	*This includes patents, trademarks, copyrights, and trade secrets. These assets protect a company's innovations, inventions, brand names, logos, creative works, and proprietary information.*
G1920000	*Patents*	*This account captures the cost or value of patents held by the business, which provide exclusive rights to a specific invention or innovation.*
	Software and Licences	*Software programs, computer codes, and licences are intangible assets used in technology-driven businesses. They enable companies to operate their systems, provide services, or develop products.*
G1930000	*Trademarks & Brands*	*Brand names or trademarks are distinctive names, logos, symbols, or designs associated with a company's products or services. They help differentiate a company's offerings from competitors and build customer loyalty.*

LIABILITIES ACCOUNTS - (2000 - 2999)

CURRENT LIABILITIES (2000 - 2499) - Current Liabilities refer to the obligations or debts of a company that are expected to be settled within a short-term period, typically within one year or the normal operating cycle of

the business, whichever is longer. Current Liabilities represent the company's short-term financial obligations that are due in the near future.

These obligations arise as a result of the company's day-to-day operations and can include accounts payable (amounts owed to suppliers for goods or services), short-term loans, accrued expenses (such as wages or taxes payable), current portion of long-term debt (the portion of long-term debt due within the next year), and any other short-term liabilities.

Current Liabilities are important for assessing a company's liquidity and its ability to meet its short-term financial obligations. They are typically settled using current assets or by generating additional revenue from ongoing operations. Monitoring and managing current liabilities is crucial for maintaining the financial health and stability of a business.

G2000-000	*Creditor's control*	*Creditor's control is a liability account that records the amounts owed by a company to its creditors. It reflects the company's unpaid invoices or bills for purchases made on credit. These could include purchases of inventory, raw materials, equipment, or services used in the business operations.* *When a company receives goods or services from a creditor without making an immediate payment, an accounts payable entry is recorded. The amount owed is added to the creditor's control account, which serves as a central record of all outstanding payables. As payments are made to creditors, the accounts payable balance is reduced accordingly.* *The creditor's control account provides a summary of the company's total outstanding liabilities to creditors at a given point in time. It helps the company monitor and manage its payment obligations, ensuring timely payments and maintaining good relationships with suppliers.* *In the chart of accounts, the creditor's control account is typically classified under current liabilities, as it represents obligations that are expected to be settled within one year. It is usually grouped with other accounts payable or trade payable accounts.* *It's important for businesses to effectively manage their creditor's control account to ensure accurate tracking of their outstanding payables and to avoid late payment penalties or strained relationships with suppliers.* *Please note that the specific accounts and classifications related to creditor's control may vary depending on the company's accounting practices and industry. It's advisable to*

		consult with an accountant or financial professional to determine the appropriate structure and accounts for tracking creditor's control in your business's chart of accounts.
G2100-000	*Accrued expenses / Outstanding expenses*	*These are expenses that have been incurred but not yet paid or recorded in the accounting records. They represent expenses that are owed by the business at the end of an accounting period, even though the actual payment has not been made.*
G2150-000	*Deferred revenue / Unearned revenue*	*This account represents the amount of revenue that has been received in advance but has not yet been recognized as earned. It arises when a company receives payment from a customer before delivering goods or providing services. The unearned revenue is initially recorded as a liability since the company still owes the customer the corresponding goods or services. As the goods are delivered or services are provided, the revenue is gradually recognized and transferred from the unearned revenue account to the appropriate revenue account.*
G2200-000	*Credit cards payable*	*G2200-000 - Credit cards payable as a current liability - Can you give a brief summary for the following accounts and its purpose* *Here is a brief summary of the accounts related to Credit Cards Payable as a current liability:* • *G2200-000: Credit Cards Payable (Control Account) - This is the control account that represents the total outstanding balances owed to credit card companies by the business. It serves as an overall summary of the credit card liabilities.* • *T2200-010: Credit Card 1 Payable - This account represents the outstanding balance owed to a specific credit card company or issuer, such as Visa or Mastercard. It captures the amount owed and tracks the liability associated with that particular credit card.* • *T2200-020: Credit Card 2 Payable - Similar to the previous account, this account represents the outstanding balance owed to another credit card company or issuer. It is used to*

		track the liability associated with the specific credit card. • *T2200-XXX: Additional Credit Card Payable Accounts - Depending on the number of credit cards used by the business, additional accounts may be created to represent the outstanding balances for each credit card. The account numbers would follow a similar pattern, such as T2200-030, T2200-040, and so on.* *The purpose of these accounts is to accurately record and track the amounts owed to credit card companies. As the business makes purchases or incurs expenses using credit cards, the corresponding amounts are recorded as liabilities in the appropriate credit card payable accounts. When payments are made to credit card companies, the balances are reduced accordingly.* *It's important to reconcile these accounts regularly with credit card statements to ensure accuracy and to make timely payments to avoid any additional charges or interest.*
G225-000	*Short-term loans*	
G2300-000	*SALARIES AND WAGES CONTROL (PAYROLL CONTROL)*	*These accounts are typically used to record and track the various payroll-related liabilities that arise from employee compensation and deductions. They help maintain accurate records of amounts owed and ensure proper disbursement of salaries, taxes, insurance premiums, contributions, loans, and other payroll-related obligations. It's important to consult with a payroll specialist or accountant to ensure compliance with relevant payroll regulations and reporting requirements.* *Purpose: The Payroll Control account serves as a control account to track the overall payroll liabilities and payments. It acts as a summary account for the individual payroll-related accounts.*
G2300-010	*Employee Salaries Payable*	*Purpose: This account represents the amount of salaries and wages owed to employees but not yet paid. It reflects the current liability for the salaries and wages that have been*

		earned by employees but not yet disbursed.
G2300-020	*PAYE Income Tax Payable*	*Purpose: This account tracks the amount of income tax that has been withheld from employees' salaries and wages but not yet remitted to the tax authorities. It represents the current liability for the income tax withheld from employees' earnings.*
G2300-030	*Health Insurance Premiums*	*Purpose: This account represents the current liability for health insurance premiums that are deducted from employees' salaries and wages but not yet paid to the insurance provider. It reflects the amount owed for health insurance coverage for employees.*
G2300-040	*National Insurance Contributions Payable*	*Purpose: This account tracks the current liability for National Insurance contributions (social security contributions) that are deducted from employees' salaries and wages (as well as the employers contribution) but not yet remitted to the relevant government agency. It represents the amount owed for social security benefits for employees.*
G2300-050	*Pension Contributions Payable*	*Purpose: This account represents the current liability for pension contributions that are deducted from employees' salaries and wages but not yet contributed to the pension scheme or fund. It reflects the amount owed for employees' retirement savings.*
G2300-060	*Employee Loans and Advances*	*Purpose: This account tracks the current liability for loans or advances provided to employees by the company. It represents the amount owed by employees for loans or advances received and is payable to the company.*
G2300-070	*Other Payroll Deductions Payable (Unions / garnishee orders)*	*Purpose: This account captures other payroll deductions that are withheld from employees' salaries and wages for purposes such as union dues or garnishee orders. It represents the current liability for these deductions that are owed to the respective parties.*
G2400-000	*VAT-CONTROL ACCOUNT*	*Purpose: The VAT-Control Account serves as a control account that tracks the overall VAT liabilities and payments. It acts as a summary account for the individual VAT accounts related to output VAT and input VAT.*

		These accounts are commonly used in VAT accounting systems to accurately track VAT liabilities and payments. The specific VAT rates may vary depending on the applicable tax regulations in your country or region. It's important to consult with a tax professional or accountant to ensure proper compliance with VAT reporting and recording requirements.
T2400-010	*Output VAT (Sales) - 20%*	*Purpose: This account tracks the output VAT charged on sales transactions at a 20% rate. It represents the VAT amount collected from customers on taxable sales.*
T2400-020	*Output VAT (Sales) - 5%*	*Purpose: Similar to the previous account, this account tracks the output VAT charged on sales transactions at a 5% rate. It represents the VAT amount collected from customers on taxable sales subject to a lower VAT rate.*
T2400-030	*Output VAT (Sales) - 0%*	*Purpose: This account tracks the output VAT charged on sales transactions that are zero-rated for VAT purposes. It represents the VAT amount collected from customers on sales transactions that have a 0% VAT rate.*
T2400-110	*Input VAT (Purchases) - 20%*	*Purpose: The Input VAT (Purchases) - 20% account tracks the VAT incurred on purchases at a 20% rate. It represents the VAT amount paid to suppliers on taxable purchases.*
T2400-120	*Input VAT (Purchases) - 5%*	*Purpose: Similar to the previous account, this account tracks the input VAT incurred on purchases at a 5% rate. It represents the VAT amount paid to suppliers on taxable purchases subject to a lower VAT rate.*
T2400-130	*Input VAT (Purchases) - 0%*	*Purpose: This account tracks the input VAT incurred on purchases that are zero-rated for VAT purposes. It represents the VAT amount paid to suppliers on purchases that have a 0% VAT rate.*
G2400-300	*VAT PAYABLE*	*Purpose: The VAT Payable account represents the net VAT liability of the business. It reflects the difference between the output VAT collected from customers and the input VAT paid to suppliers. It is usually settled periodically with the tax authorities.*

G2450-000	*Suspense account*	

NON-CURRENT LIABILITIES (2500 - 2999) - Non-current liabilities, also known as Long-term liabilities, refer to the obligations or debts of a company that are not expected to be settled within a short-term period, typically longer than one year or the normal operating cycle of the business. Non-current liabilities represent the company's long-term financial obligations that are due over an extended period of time.

Non-current Liabilities are important for assessing the long-term financial obligations and solvency of a company. They represent the portion of a company's debt or obligations that are not due for repayment in the immediate future. Monitoring and managing non-current liabilities are essential for ensuring the company's long-term financial stability and ability to meet its long-term obligations.

Some common examples of Non-Current Liabilities are:

G2500-000	*Long-term loans and borrowings*	*This includes loans and debts with a maturity date beyond one year, such as bank loans or bonds.*
	Lease Liabilities	*Obligations arising from long-term leases, such as operating leases or finance leases (capital leases).*
	Deferred Tax Liabilities	*Tax obligations that will be payable in future periods due to temporary differences between accounting and tax treatment.*
	Pension Liabilities	*Long-term obligations to pay pensions and other retirement benefits to employees.*
	Long-Term Debts to Suppliers	*Long-term payables to suppliers for deferred payment arrangements.*
	Deferred Revenue	*Advance payments or deposits received from customers for goods or services to be delivered in the future.*
	Other Non-Current Liabilities	*Any other long-term liabilities that don't fit into the standard categories but are expected to be paid off beyond one year.* *Other Non-Current Liabilities" is a category in the Chart of Accounts where businesses can include any long-term liabilities that do not fit into the more common classifications. These are specific obligations that are expected to be paid off over an extended period, typically beyond one year, but may not fall under the standard Non-Current Liability categories. Here are some examples of what could be included under*

"Other Non-Current Liabilities":

1. *Deferred Charges: Costs incurred that will be amortized or expensed over time, such as organization costs or startup expenses.*
2. *Long-Term Deposits Received: Deposits received from customers or other parties that will be refundable after an extended period, often for large projects or contracts.*
3. *Deferred Credits: Liabilities created when the company receives payments in advance for services or goods that will be delivered or fulfilled later.*
4. *Long-Term Warranty Obligations: Obligations to provide warranty services or repairs beyond the standard warranty period.*
5. *Deferred Compensation: Liabilities for deferred compensation plans or employee benefits that will be paid out over time.*
6. *Long-Term Bonus or Incentive Payments: Liabilities for bonuses or incentives that will be paid out to employees or management over an extended period.*
7. *Long-Term Lease Obligations: Lease liabilities for long-term operating leases or finance leases (capital leases).*
8. *Long-Term Deferred Revenue: Advance payments received for goods or services to be delivered over an extended period.*
9. *Long-Term Environmental Liabilities: Obligations for environmental cleanup or remediation efforts that extend beyond the current year.*
10. *Long-Term Contingent Liabilities: Obligations that may arise from legal disputes or other potential liabilities, with settlement expected beyond one year.*

It's important to note that the specific liabilities included under "Other Non-Current Liabilities" will depend on the nature of the business and its operations. This category provides flexibility for businesses to account for unique or less common long-term liabilities that don't fit into the standard classifications.

As always, businesses should consult with a qualified accountant or financial expert to ensure accurate recording and reporting of "Other Non-Current Liabilities" in accordance with accounting standards and regulations.

EQUITY ACCOUNTS - (3000 - 3999)

EQUITY - Equity, also known as Shareholders' Equity or Owner's Equity, represents the residual interest in the assets of a company after deducting its liabilities. It represents the ownership interest of the company's shareholders or owners.

Equity is a financial category in the chart of accounts that captures the contributions made by the owners (such as investments or capital contributions) and the accumulated profits or losses of the company over time. It reflects the net worth of the company and represents the claim on the company's assets by its owners.

Equity can be further divided into various components, such as share capital, retained earnings, and other comprehensive income. Share capital represents the amount of capital contributed by the shareholders, while retained earnings reflect the accumulated profits or losses that have been retained in the business.

Equity is an important indicator of a company's financial health and stability. It provides a measure of the company's net worth and the owners' stake in the company's assets. It also serves as a source of funding for the company's operations and growth, as retained earnings can be reinvested back into the business.

Changes in equity can occur through various transactions, such as the issuance or repurchase of shares, the distribution of dividends, net income or loss from operations, and other comprehensive income or loss. Monitoring and analyzing equity is crucial for assessing the financial position and performance of a company.

This example, the accounts, is listed For a Sole proprietor.

It's important to note that retained earnings for a sole proprietorship may not have the same level of complexity as those for a corporation, as there are no separate shareholders or dividend distributions involved. Instead, any profits or losses generated by the business directly impact the sole proprietor's equity in the business, including the retained earnings.

For a sole proprietorship. te accounts, is as follows:

G3000-000	*Capital*	*This account represents the initial investment made by the sole proprietor in the business. It reflects the owner's equity stake in the business and serves as a source of funding for the company's operations. Any subsequent capital contributions made by the owner can also be recorded in this account.*

G3100-000	*Additional capital*	*This account is used to record any additional capital contributions made by the sole proprietor during the course of business. It represents the additional investments made by the owner to increase their equity stake in the business.*
G3200-000	*Drawings*	*This account is used to record the withdrawals or distributions made by the sole proprietor from the business for personal use. It represents the amounts taken out of the business by the owner for personal expenses or other purposes unrelated to the business operations.*
G3900-000	*Retained Earnings*	*This account captures the accumulated profits or losses that have been retained in the business. It represents the portion of the company's earnings that have not been distributed to the owner as dividends or drawings. Retained earnings increase when the business generates net income and decrease when there are net losses or when dividends are paid.*

Income statement

In osFinancials5/TurboCASH5, the Income statement accounts represent the Income and Expense items of a company. These accounts can be further organised and classified by utilising up to two account groups, namely Account group 1 and Account group 2. You can configure these account groups in the Setup → Groups menu on the Setup ribbon. It is important to link these account groups to the corresponding financial categories in the Setup → Financial categories menu on the Setup ribbon.

REVENUE (4000 - 4399)

OPERATING REVENUE (4000 - 4999) - Operating revenue are the revenue generated through the primary business activities or core operations by a business. It represents the income earned from the sale of goods, provision of services, or other activities directly related to the main operations of the business.

G4000-000 Sales revenue

OTHER REVENUE (4500 - 4999) - Other revenue refers to income or revenue generated by a company from sources other than its primary business activities or core operations. It includes income that is incidental or

peripheral to the main operations of the company.

Unlike operating revenue, which is derived from the company's primary activities, other revenue represents additional sources of income that may arise from non-operating activities, one-time events, or secondary business ventures. It is often considered as supplementary or ancillary revenue.

G4400-000	*Interest earned*	*Interest earned is a component of other revenue and refers to the income a business earns from interest-bearing financial instruments, such as bank deposits, loans made to others, bonds, or other interest-bearing investments. It represents the return or compensation received by the business for lending money or having funds deposited with a financial institution.* *Interest earned is typically recorded as revenue in the financial statements of a business. It is categorized as other revenue because it is not directly related to the primary operations or core activities of the business. Instead, it represents income generated from the surplus funds or financial assets of the business.* *Examples of interest earned include the interest received on savings accounts, interest earned on loans made to customers or suppliers, or interest earned on investments in interest-bearing securities. The amount of interest earned depends on the interest rate applied to the financial instrument and the principal amount involved.* *Interest earned is typically recognized over time as it accrues or as it becomes due. It is reported on the income statement of the business, contributing to the overall revenue generated by the business.*
G4500-000	*Sales discounts*	*Sales discounts are a component of other revenue and refer to the reductions in the selling price offered to customers as an incentive to encourage prompt payment or to promote sales. They represent a reduction or deduction from the original sales amount and are provided to customers as a reward for paying their invoices early or within a specified time period.* *Sales discounts are typically expressed as a percentage of the total invoice amount or as a specific amount. The purpose of offering sales discounts is to motivate customers to pay their invoices quickly, which helps*

improve the cash flow of the business and reduces the risk of bad debts.

When a customer takes advantage of a sales discount and makes payment within the discount period, the discount amount is recorded as a reduction in revenue and is classified as other revenue. It is considered a reduction in the selling price and is reflected in the financial statements as a contra-revenue account.

Sales discounts are a type of deduction or reduction in the selling price of goods or services offered by a business. They are often used as an incentive to encourage prompt payment or to attract customers. Sales discounts represent a decrease in revenue for the business, but they are recorded as part of other revenue in the financial statements.

Sales discounts are typically offered to customers who pay their invoices or bills within a specified period of time, known as the discount period. The discount is a percentage or a fixed amount that is subtracted from the total sales price. By providing a discount, the business aims to motivate customers to settle their payments earlier, improving cash flow and reducing the risk of bad debts.

For example, a business may offer a 2% discount to customers who pay their invoices within 10 days of the invoice date. If the total invoice amount is $1,000, the customer would be eligible for a $20 discount if they pay within the discount period.

When a customer takes advantage of a sales discount, the discounted amount is recorded as a reduction in revenue on the income statement. This reduction is included as part of other revenue to reflect the impact of discounts on the overall financial performance of the business.

Sales discounts are important for businesses to manage their accounts receivable effectively and encourage timely payments. They can help improve customer relationships and provide an incentive for repeat business. However, it's essential for businesses to carefully monitor and analyse

		the impact of sales discounts on their profitability and financial performance.
G4300-000	*Finance charge income*	*Finance charge income refers to the revenue earned by a business from charging interest or fees on outstanding customer balances or overdue payments. When customers or clients fail to make timely payments on their credit accounts, loans, or other financial obligations, the business may apply finance charges as a penalty or compensation for the delay in payment.* *The finance charges typically include interest charges, late payment fees, or other penalties assessed on the outstanding balances. These charges serve as a way for the business to earn additional income for the extended credit period or the inconvenience caused by the late payment.* *The finance charge income is recognized as revenue in the financial statements of the business and is typically recorded separately from the sales or service revenue. It represents the earnings derived from the financial services provided by the business, such as extending credit or offering financing options.* *The specific treatment and account classification for finance charge income may vary depending on the accounting policies and chart of accounts used by the business. It's important to follow the relevant accounting standards and guidelines to accurately record and report finance charge income.*

COS (Cost of Sales), COGS (Cost of Goods Sold), and SOSR (Cost of Services Rendered) are all related to the calculation of gross profit. Here's a brief explanation of each:

- *Cost of Sales (COS): Cost of Sales is a broader term that encompasses the cost associated with both goods and services sold by a company. It includes the direct costs incurred in producing or providing the products or services, such as raw materials, labor, and overhead costs. COS is typically used in service-oriented businesses where goods are not the primary focus.*
- *Cost of Goods Sold (COGS): COGS specifically refers to the direct costs incurred in producing or acquiring the goods that are sold by a company. It includes the cost of raw materials, direct labor, and*

manufacturing overhead directly associated with the production of goods. COGS is primarily used in manufacturing, retail, and distribution businesses.

- *Cost of Services Rendered (SOSR): SOSR is similar to COGS but applies specifically to service-based businesses. It represents the direct costs associated with providing services to customers, such as labour, subcontractor fees, and any other expenses directly related to delivering the services.*

Gross profit is calculated by subtracting the COS, COGS, or SOSR from the revenue generated from the sale of goods or services. It represents the profit generated from the core operations of the business before considering other operating expenses. Gross profit provides insight into the efficiency and profitability of a company's primary revenue-generating activities.

====

COST OF GOODS SOLD - Cost of Goods Sold (COGS) is an expense category in the income statement that calculates the direct costs associated with the production or acquisition of the goods or services sold by a company. It includes the costs directly attributed to the production process, such as raw materials, direct labour, and manufacturing overhead.

COGS is calculated by subtracting the ending inventory from the sum of the beginning inventory and purchases or production costs during a specific accounting period. The resulting figure represents the cost of the goods that have been sold during that period.

The concept of COGS is primarily applicable to businesses that deal with physical goods, such as retailers, manufacturers, and wholesalers. For service-based companies, the equivalent concept is often referred to as the Cost of Services Rendered (COSR).

COGS is a crucial metric in determining a company's gross profit, which is calculated by subtracting COGS from the revenue generated by the sale of goods or services. It represents the profit made by the company before considering other operating expenses.

In the chart of accounts, Cost of Goods Sold is typically classified as an expense account and categorized under the operating expenses section. It is commonly grouped with other expense accounts related to the cost of sales or production.

Accurately tracking and managing COGS is essential for businesses to determine their profitability, assess pricing strategies, and make informed decisions about inventory management and production processes.

It's important to note that the specific accounts and classifications related to COGS may vary depending on the company's accounting practices and industry. It's advisable to consult with an accountant or financial professional to determine the appropriate structure and accounts for tracking COGS in your business's chart of accounts.

COST OF SALES - Cost of Sales (COS), also known as Cost of Revenue, is an expense category in the income statement that captures the direct costs directly associated with the sales of goods or services by a company. It includes the costs related to the production, acquisition, or delivery of the products or services that were sold.

COS encompasses the costs directly attributed to the production or acquisition process, such as raw materials, direct labour, and manufacturing overhead. Additionally, it may include other costs incurred in the sales process, such as shipping or packaging expenses, direct sales commissions, or certain marketing expenses.

The calculation of COS typically involves determining the direct costs associated with the production or acquisition of the goods or services sold during a specific accounting period. This may involve taking into account the beginning inventory, purchases or production costs, and adjusting for the ending inventory to arrive at the total cost of sales.

COS is an essential component in calculating a company's gross profit. Gross profit is obtained by subtracting the COS from the revenue generated by the sale of goods or services. It reflects the profitability of a company's core operations before considering other operating expenses.

In the chart of accounts, Cost of Sales is typically classified as an expense account and categorized under the operating expenses section. It is often grouped with other accounts related to the cost of production, acquisition, or delivery of goods or services.

It's important to note that the specific accounts and classifications related to Cost of Sales may vary depending on the company's accounting practices and industry. It's advisable to consult with an accountant or financial professional to determine the appropriate structure and accounts for tracking Cost of Sales in your business's chart of accounts.

COST OF SERVICES RENDERED (COSR) - Cost of Services Rendered (COSR) refers to the expenses directly associated with providing services to customers or clients. It represents the costs incurred by a business in delivering its services and is analogous to the concept of Cost of Goods Sold (COGS) for a product-based business.

COSR includes various expenses related to the production or delivery of services, such as labour costs, direct materials or supplies used in providing the services, subcontractor fees, overhead costs, and any other direct costs specifically attributable to the services rendered. These expenses are incurred during the process of providing services to generate revenue.

By subtracting the COSR from the revenue generated by services, a business can calculate its gross profit or gross margin. This figure represents the profitability of the services provided before accounting for other operating expenses.

It's important to note that the specific accounts and classifications within COSR can vary depending on the nature of the services and the accounting practices of the business. It's recommended to consult with an accountant or financial professional to determine the appropriate accounts and structure for recording COSR in your specific accounting system.

G5000-000	*Cost of Sales*
G5200-000	*Stock (Inventory) shortages / surplus*

G5300-000 *Freight charges*

G5400-000 *Packaging*

EXPENSES (6000 - 7399)

OPERATING EXPENSES (6000 - 7999) - Operating expenses are expenses incurred by a business in the ordinary course of its operations, such as wages, rent, utilities, and materials. These expenses are directly related to the revenue-generating activities of the business and are subtracted from revenue to arrive at operating income.

G6000-000 *Accounting fees*

G6050-000 *Audit fees*

G6100-000 *Bad debts*

G6150-000 *Bank charges*

G6200-000 *Cleaning services*

G6250-000 *Commissions paid*

G6300-000 *Depreciation*

G6350-000 *Entertainment*

G6400-000 *Finance charges*

G6450-000 *Gifts and donations*

G6500-000 *Insurance premiums*

G6550-000 *Interest paid*

G6600-000 *Legal fees*

G6650-000 *Licence fees*

G6700-000 *Maintenance*

G6750-000 *Marketing and advertising expenses*

G6800-000	*Vehicle expenses*	
G6800-010	*Fuel and oil*	
G6800-020	*Vehicle - Insurance*	
G6800-030	*Vehicle - Maintenance and repairs*	
G6800-040	*Vehicle - Registration and licence fees*	
G6800-050	*Vehicle - Tolls and parking fees*	
G6800-060	*Vehicle - Traffic fines / Vehicle violation expenses*	
G6850-000	*Office expenses*	
G6900-000	*Printing*	
G6950-000	*Professional fees*	
G7000-000	*Repairs*	
G7050-000	*Rent paid*	
G7100-000	*Salaries and wages expenses*	*This account represents the expenses related to salaries and wages within an organisation. This includes the costs associated with compensating employees for their work, such as regular salaries, hourly wages, bonuses, commissions, benefits, and any other expenses, such as employers contributions, related to employee compensation.* *The specific regulations and requirements governing salaries and wages, including tax legislation, labour legislation, and other applicable regulations, may vary depending on the country and jurisdiction in which the organisation operates. It is important to adhere to the relevant laws and regulations when determining and recording expenses related to salaries and wages.* *Using sub-accounts for each expense item related to*

salaries and wages (payroll expenses) can provide a more detailed breakdown of the various components involved.

G7100-010	*Gross Salaries*
G7100-020	*Employer National Insurance contributions*
G7100-030	*Employer Pension contributions*
G7100-040	*Bonuses and commissions*
G7100-050	*Disability pay*
G7100-060	*Health Insurance premiums*
G7100-070	*Holiday pay*
G7100-080	*Maternity / Paternity pay*
G7100-090	*Overtime pay*
G7100-100	*Severance pay*
G7100-110	*Sick pay*
G7100-200	*Payroll processing fees*
G7100-210	*Payroll software costs*
G7100-220	*Payroll training costs*
G7100-230	*Other payroll expenses*
G7150-000	*Stationery*
G7200-000	*Subscriptions*
G7250-000	*Travel & Subsistence*
G7300-000	*Utilities*

NON-OPERATING REVENUE (8000 - 8999) - Non-operating revenue refers to income or revenue generated by a business that is not directly related to its core operations or primary business activities. It

includes sources of income that are incidental, peripheral, or non-recurring in nature.

Non-operating revenue typically arises from activities that are outside the day-to-day operations of the business.

G8000-000 Gain on sale of assets

G8010-000 Investment income

G8020-000 Royalties received

G8030-000 Rent income

G8040-000 Foreign exchange gain

G8050-000 Insurance proceeds

G8060-000 Legal settlements

G8070-000 Other non-operating revenue

NON-OPERATING EXPENSES - (9000 - 9999) - Non-operating expenses refer to expenses incurred by a business that are not directly related to its core operations or primary business activities. These expenses are typically incidental, peripheral, or non-recurring in nature.

Non-operating expenses arise from activities that are outside the day-to-day operations of the business. They are usually separate from the expenses directly associated with producing or delivering goods or services.

G9000-000 Loss on disposal of assets

G9010-000 Donations & contributions

G9020-000 Foreign exchange loss

G9030-000 Insurance expenses

G9040-000 Interest expenses

G9050-000 Litigation expenses

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Notes on specific accounts and financial categories

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Short-term assets (Current assets) and Long-term assets (Non-current assets)

What is Current assets and Non-current assets?

Current assets and non-current assets are two major categories of assets found on a company's balance sheet or statement of financial position. These categories help to classify assets based on their liquidity and expected holding period. Here's an overview of each:

1. Current Assets: Current assets are assets that are expected to be converted into cash or used up within the company's operating cycle or one year, whichever is longer. The operating cycle refers to the time it takes for a company to convert its inventory into cash through its normal business operations. Current assets are typically used for day-to-day operations and represent the company's short-term resources. Examples of current assets include:
    - Cash and Cash Equivalents: Physical cash, bank balances, and highly liquid investments with maturities of three months or less.
    - Accounts Receivable: Amounts owed to the company by its customers for goods sold or services rendered on credit.
    - Inventory: The value of goods or raw materials held for resale or production.
    - Prepaid Expenses: Amounts paid in advance for goods or services that will be received or consumed in the future.
2. Non-current Assets (Long-term Assets): Non-current assets, also known as long-term assets, are assets that are not expected to be converted into cash or used up within the company's operating cycle or one year. These assets are held for the long term and are essential for the company's ongoing operations and future growth. Examples of non-current assets include:
    - Property, Plant, and Equipment: Tangible assets such as buildings, machinery, equipment, and land used in the company's operations.
    - Investments: Long-term investments in other companies' stocks, bonds, or equity instruments.

- Intangible Assets: Non-physical assets, such as patents, trademarks, copyrights, and goodwill.
- Long-term Investments in Bonds: Bonds or debt securities that the company intends to hold for an extended period.
- Deferred Tax Assets: Tax benefits that the company will realize in future periods due to temporary differences between accounting and tax rules.

Classifying assets into current and non-current categories provides valuable information about a company's short-term liquidity and its ability to meet current obligations (current assets) and its long-term financial position and capacity for growth (non-current assets). Investors, creditors, and stakeholders use this information to evaluate a company's financial health and assess its ability to manage its assets effectively.

Current assets

There are several other accrual accounts that can be classified under current assets on a company's balance sheet. Current assets are those that are expected to be converted into cash or used up within one year or the operating cycle of the business, whichever is longer. Accrual accounts represent expenses or revenues that have been incurred or earned but have not yet been paid or received, respectively. Here are some common accrual accounts that fall under current assets:

1. Accounts Receivable: This represents the amount of money owed to the company by its customers for goods sold or services rendered on credit. It is a claim that the company has on its customers for payment.
2. Inventory: This includes the value of goods or raw materials held by the company for the purpose of resale or production. It comprises finished goods, work-in-progress, and raw materials.
3. Short-term Investments: These are investments made by the company in securities that are expected to be converted into cash within a short period, usually less than one year.
4. Prepaid Expenses: As you mentioned, prepaid expenses are amounts paid in advance for goods or services that will be received or consumed in the future. These are considered assets because they represent economic benefits to be received later.
5. Notes Receivable: Similar to accounts receivable, notes receivable represent written promises of payment from customers or other parties. However, they are formal, written agreements that include specific terms such as interest rates and maturity dates.
6. Accrued Revenues: These are revenues that have been earned but not yet billed to customers or received in cash. For example, a company may have completed a service or delivered goods but has

not yet issued an invoice to the customer.

7. Other Current Assets: This category may include various other short-term assets that do not fit into the above categories. It can encompass items like prepaid taxes, prepaid insurance (if not already included in prepaid expenses), and other prepaid items.

It's important to note that the specific accounts and their names may vary depending on the accounting practices and reporting standards used by the company. The classification of accounts under current assets provides valuable information to stakeholders about a company's short-term liquidity and its ability to meet its current obligations.

What is Short-term investments (Current Asset) and Long-term investment (Non-Current Asset)?

The account "*Investments*" is not inherently classified as a long-term asset or a short-term asset solely based on its name. The classification of this account depends on the company's specific accounting policies and the nature of the investments held.

In accounting, investments can be classified into two main categories: current investments and non-current (or long-term) investments.

1. Current Investments: Current investments are short-term investments that are readily convertible to cash and are intended to be held for a short period, typically less than one year. These investments are actively managed, and their purpose is often to earn a return on excess cash or funds that are not immediately needed for operational purposes. Examples of current investments include marketable securities, Treasury bills, and short-term government or corporate bonds.

2. Non-current (Long-term) Investments: Non-current investments are long-term investments that are intended to be held for a more extended period, usually more than one year. These investments are not readily convertible to cash and are generally held for strategic purposes, to gain significant influence or control over another company, or to earn a return on investment over an extended period. Non-current investments are often accounted for using the equity method or the cost method, depending on the level of influence or ownership. Examples of non-current investments include equity investments in other companies, long-term bonds, and real estate held for investment purposes.

To determine whether the account "*1500 Investments*" is classified as a long-term asset or a short-term asset, you need to refer to the company's financial statements and notes to the financial statements. There, you will find details about the nature of the investments held in this account and how the company has classified them based on their intended holding period and purpose. The balance sheet or statement of financial position will provide information on whether the investments are classified as current assets or non-current assets.

Notes receivable - Is this a Current Asset or a Non-Current Asset?

Notes receivable can be classified as either a current asset or a non-current asset, depending on the maturity or due date of the notes.

1. Current Asset: If the notes receivable are expected to be collected or converted into cash within the company's operating cycle or one year, whichever is longer, then they are classified as a current asset. The operating cycle is the time it takes for a company to convert its inventory into cash through the normal course of business. For example, if a company issues short-term notes receivable that are due for repayment within the next year, those notes would be considered a current asset.
2. Non-current Asset: If the notes receivable have a maturity date or due date beyond the company's operating cycle or one year, then they are classified as a non-current asset. These are notes receivable that will not be collected or converted into cash within the next year. Instead, they represent the long-term portion of the receivables that the company expects to realize over an extended period.

It's important for the company to differentiate between current and non-current assets in its financial statements to provide relevant information about its liquidity and the timing of cash flows. Investors, creditors, and stakeholders use this information to assess the company's financial health, its ability to meet short-term obligations, and its long-term financial stability.

Is there examples of Notes receivable as a Current asset or a Non-current asset?

Let's look at examples of "*Notes Receivable*" classified as both a current asset and a non-current asset:

1. Current Asset - Example: Short-term Promissory Note: Let's say a company lends money to a customer and receives a promissory note in return, which states that the customer will repay the loan in six months. Since the maturity date of the promissory note is within one year, it is considered a current asset. The company expects to receive the payment within its operating cycle or one year, making it part of its current assets on the balance sheet.
2. Non-current Asset - Example: Long-term Loan Agreement: In this scenario, a company extends a long-term loan to a business partner, and the repayment period specified in the loan agreement is five years from the date of the loan disbursement. Since the maturity date of the loan is beyond the company's operating cycle or one year, the loan is classified as a non-current asset. The company expects to receive the repayment over an extended period, making it part of its non-current assets on the balance sheet.

So, whether "*Notes Receivable*" is considered a current asset or a non-current asset depends on the specific terms and maturity dates of the promissory notes or loans held by the company. If the notes will

be collected or converted into cash within one year or the operating cycle, they are classified as current assets. If the maturity date extends beyond one year, they are classified as non-current assets.

Prepaid Expenses and Accrued Revenue - Is usually a Current asset - Can this be a long-term asset?

Prepaid expenses and accrued revenue are typically classified as current assets on a company's balance sheet because they are related to future economic benefits expected to be realized within the next operating cycle or one year. However, there are specific scenarios where they can be classified as long-term assets, depending on their nature and timing.

1. Prepaid Expenses (Current Asset): Prepaid expenses represent payments made in advance for goods or services that will be received or consumed over time in the future. Since these expenses will provide economic benefits within the next operating cycle or one year, they are considered current assets. Examples of prepaid expenses include prepaid rent, prepaid insurance, and prepaid subscriptions.
2. Accrued Revenue (Current Asset): Accrued revenue refers to revenue that has been earned but not yet billed or received in cash. It arises when a company provides goods or services to a customer but has not yet issued an invoice for the transaction. Since the revenue is earned and will be converted into cash within the next operating cycle or one year, it is classified as a current asset.

However, in some unique circumstances, prepaid expenses and accrued revenue can be classified as long-term assets. Here are a few examples:

1. Long-Term Prepaid Expenses: If a company makes payments for goods or services that will provide economic benefits for more than one year, the prepaid expenses may be considered long-term assets. For instance, if a company pays for a long-term software licence that covers a period of three years, the prepaid expense for the entire license period would be classified as a long-term asset.
2. Long-Term Contractual Accrued Revenue: In some cases, accrued revenue may be recognized based on long-term contractual agreements that extend beyond one year. For example, a company may provide ongoing maintenance services to a customer under a multi-year service contract. The accrued revenue for the full service period may be recognized as a long-term asset.

It's essential for companies to carefully assess the timing and nature of prepaid expenses and accrued revenue to determine their appropriate classification as either current assets or long-term assets. The classification should be in line with the company's accounting policies and consistent with accounting principles and reporting standards.

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Short-term liabilities (Current liabilities) / Long-term liabilities (Non-current liabilities)

What is Short-term debt (Current Liability) and Short-term debt (Non-Current Liability)?

Current liabilities and non-current liabilities are two categories of obligations or debts that a company owes to external parties. These liabilities are reported on the balance sheet or statement of financial position and represent the company's financial obligations as of a specific date.

1. Current Liabilities: Current liabilities are obligations that are expected to be settled within the company's operating cycle or one year, whichever is longer. Operating cycle refers to the time it takes for a company to convert its inventory into cash through the normal course of business. Current liabilities typically include:
    - Accounts Payable: Money owed by the company to its suppliers or vendors for goods or services purchased on credit.
    - Short-term Loans and Borrowings: Any loans or borrowings due for repayment within the next year.
    - Accrued Liabilities: Expenses that have been incurred but not yet paid, such as wages payable, taxes payable, and utility bills.
    - Short-term Provisions: Amounts set aside to cover expected liabilities or expenses that are likely to be settled within the next year.
    - Dividends Payable: Amounts owed to shareholders for declared dividends that have not yet been paid.
2. Non-current Liabilities: Non-current liabilities, also known as long-term liabilities, are obligations that are not expected to be settled within the company's operating cycle or one year. Non-current liabilities typically include:
    - Long-term Loans and Borrowings: Loans or borrowings due for repayment beyond the next year.
    - Bonds Payable: Long-term debt securities issued by the company.
    - Deferred Tax Liabilities: Taxes that will become payable in the future due to temporary differences between accounting and tax rules.
    - Long-term Provisions: Amounts set aside to cover long-term liabilities or expenses expected

to be settled beyond one year.

It's essential for investors, creditors, and stakeholders to pay attention to a company's current and non-current liabilities to assess its financial health and liquidity. A company with a large proportion of short-term liabilities compared to its current assets may face challenges in meeting its obligations in the short term. On the other hand, non-current liabilities provide insight into the company's long-term financial obligations and its ability to manage debt over an extended period.

Example - Short-term debt (Current Liability) and Short-term debt (Non-Current Liability)

Short-term debt (Current Liability): Short-term debt refers to borrowings or financial obligations that are due for repayment within the next operating cycle or one year, whichever is longer. This category typically includes debts that a company must settle in the short term. Here's an example:

Example: Bank Revolving Credit Line A company obtains a revolving credit line from a bank with a limit of $50,000. They use $30,000 of the credit line to cover temporary cash flow needs. Since the company expects to repay this amount within the next year, it will be classified as "2200 Short-term debt" in the company's financial statements.

Long-term debt (Non-Current Liability): Long-term debt represents borrowings or financial obligations that are not due for repayment within the next operating cycle or one year. These debts have longer repayment terms, usually extending beyond one year. Here's an example:

Example: Corporate Bonds A company issues corporate bonds to raise funds for expansion. The bonds have a maturity period of five years, meaning the company will make periodic interest payments and repay the principal amount at the end of five years. Since the repayment period is beyond one year, these bonds will be classified as "2300 Long-term debt" on the company's balance sheet.

It's important to note that the specific examples and amounts will vary for each company. The classification of short-term debt and long-term debt depends on the maturity dates of the liabilities and the company's accounting practices. Companies need to ensure accurate and transparent reporting of their debt obligations in their financial statements to provide stakeholders with a clear understanding of their financial position.

Created with the Standard Edition of HelpNDoc: Effortlessly optimize your documentation website for search engines

Operating expenses and Non-operating expenses

What is a definition of Operating expenses and Non-operating expenses?

Operating expenses are expenses incurred by a business in the ordinary course of its operations, such as wages, rent, utilities, and materials. These expenses are directly related to the revenue-generating activities of the business and are subtracted from revenue to arrive at operating income.

Non-operating expenses, on the other hand, are expenses that are not directly related to the primary business activities of the company, such as interest expense, foreign exchange losses, and one-time charges. These expenses do not affect the company's operating income and are typically reported separately from operating expenses on the income statement.

Is Non-Operating Revenue and Non-Operating Expense accounts in the Income statement section in the chart of accounts?

Yes, Non-Operating Revenue and Non-Operating Expense accounts are typically included in the Income Statement section of the chart of accounts. These accounts capture revenues and expenses that are not directly related to the core operating activities of the business.

Non-Operating Revenue accounts record any revenue generated from sources outside of the primary operations of the business, such as rental income, interest income, or gains from the sale of assets.

Non-Operating Expense accounts, on the other hand, capture expenses that are not directly related to the core operations of the business, such as interest expense, foreign exchange losses, or one-time charges.

By including these accounts in the chart of accounts, businesses can track and analyze the financial impact of non-operating activities separately from their operating activities, providing a clearer picture of the overall financial performance of the company.

Can donations and contributions be an operating expense and when is it a non-operating expense?

Donations and contributions can be classified as both operating and non-operating expenses, depending on the nature of the donation or contribution.

If the donation or contribution is directly related to the normal course of business operations, such as a donation to a charity that aligns with the company's mission or a contribution to an employee retirement plan, then it may be considered an operating expense and recorded as such.

On the other hand, if the donation or contribution is not directly related to the normal course of business operations, such as a one-time donation to a disaster relief fund or a contribution to a political campaign,

then it may be considered a non-operating expense and recorded as such.

It is important to carefully consider the nature of each donation or contribution to determine how it should be classified in the company's financial statements.

Can litigation expenses be an operating expense and when is it a non-operating expense?

Litigation expenses can be either an operating or non-operating expense, depending on the nature of the expense.

If the litigation expenses are incurred in the ordinary course of business operations, such as legal fees associated with contract disputes or employment issues, they would be considered operating expenses and would be included in the income statement as such.

However, if the litigation expenses are incurred as a result of a one-time event or unusual circumstance, such as a settlement payment related to a lawsuit or legal fees associated with a merger or acquisition, they would be considered non-operating expenses and would be reported separately on the income statement as such.

It is important to note that the classification of litigation expenses as operating or non-operating is based on the specific circumstances surrounding the expense and can vary from company to company.

Can Bad Debt expenses be an operating expense and when is it a non-operating expense?

Bad debt expenses can be considered an operating expense if they are related to the company's primary business activities, such as the sale of goods or services on credit. However, if the bad debt expense is related to an investment or other non-primary business activity, it may be classified as a non-operating expense. Ultimately, the classification will depend on the specific circumstances of the expense and the company's accounting policies.

Can bank charges and depreciation as a Non-Operating Expense accounts in the chart of accounts the same as Operating Expense?

Bank charges and depreciation can be recorded as either Operating Expenses or Non-Operating Expenses in the chart of accounts, depending on how they are classified.

Bank charges can be considered as an Operating Expense if they are directly related to the company's day-to-day operations, such as fees for processing payments or maintaining accounts. However, if the bank charges are associated with financing activities, such as interest expense on loans, they may be classified as Non-Operating Expenses.

Depreciation, on the other hand, is typically recorded as an Operating Expense since it represents the decline in value of assets used in the company's operations. However, if the depreciation relates to non-operating assets, such as idle equipment or investment properties, it may be classified as a Non-Operating Expense.

Amortization

Amortization could that be an expense account?

Yes, amortization is typically recorded as an expense account in the chart of accounts. Amortization refers to the systematic allocation of the cost of intangible assets over their useful life. Examples of intangible assets that may be subject to amortization include patents, copyrights, trademarks, and software.

When an intangible asset is acquired, its cost is spread out over its estimated useful life through periodic amortization expense. This expense is recorded in the income statement and reduces the reported net income. The amortization expense is calculated based on the asset's cost, estimated useful life, and any residual value.

It's important to note that amortization is distinct from depreciation, which is the allocation of the cost of tangible assets over their useful life. Depreciation is typically associated with property, plant, and equipment (PP&E), while amortization is specifically related to intangible assets.

The specific account number for amortization may vary depending on the chart of accounts used by the organization, but it is commonly found in the range of operating expenses or non-operating expenses.

Could Amortization be a operating expense or a non operating expense?

Amortization can be classified as either an operating expense or a non-operating expense, depending on the nature of the intangible asset being amortized and its relevance to the core operations of the business.

If the amortization expense is directly associated with the production or sale of goods or services, it is generally considered an operating expense. For example, if a company develops and sells software, the amortization of the software development costs would be classified as an operating expense.

On the other hand, if the amortization expense is related to non-core activities or non-recurring items, it may be considered a non-operating expense. For instance, if a company incurs amortization expenses for the acquisition of a trademark or a patent that is not directly tied to its main business operations, it would typically be categorized as a non-operating expense.

The classification of amortization as an operating or non-operating expense ultimately depends on the specific circumstances and accounting policies of the company. It is important to consult relevant accounting standards and guidelines, as well as seek professional advice, to determine the appropriate classification for amortization in a particular context.

Profit loss on sale of assets

Gain on Sale of Assets can that be reported on Non-operating revenue as well as Other operating revenue on the income statement?

Yes, the gain on the sale of assets can be reported under both non-operating revenue and other operating revenue on the income statement, depending on the nature of the gain and the company's accounting policies.

If the gain on the sale of assets is considered to be incidental or non-recurring in nature and is not directly related to the core operations of the business, it is typically classified as non-operating revenue. Non-operating revenue represents income generated from activities that are not considered the primary source of revenue for the company.

However, if the gain on the sale of assets is related to the regular course of business operations or is considered part of the company's core activities, it can be reported as other operating revenue. Other operating revenue includes income earned from activities that are integral to the company's primary operations but are not directly related to the sale of goods or services.

The specific classification of the gain on the sale of assets as non-operating revenue or other operating revenue depends on the company's accounting policies, industry norms, and the materiality and frequency of such gains. It is important for companies to disclose their accounting policies and provide clear explanations in their financial statements to ensure transparency and consistency in reporting.

Loss on Sale of Assets can that be reported on Non-operating expense as well as Other operating expenses on the income statement?

Yes, the loss on the sale of assets can be reported under both non-operating expenses and other operating expenses on the income statement, depending on the circumstances surrounding the loss and the company's accounting policies.

If the loss on the sale of assets is considered to be incidental or non-recurring in nature and is not directly related to the core operations of the business, it is typically classified as a non-operating expense. Non-operating expenses represent costs or losses incurred from activities that are not considered the primary source of expenses for the company.

However, if the loss on the sale of assets is related to the regular course of business operations or is considered part of the company's core activities, it can be reported as other operating expenses. Other operating expenses include costs or losses incurred from activities that are integral to the company's primary operations but are not directly related to the production of goods or services.

The specific classification of the loss on the sale of assets as non-operating expenses or other operating expenses depends on the company's accounting policies, industry norms, and the materiality and frequency of such losses. It is important for companies to disclose their accounting policies and provide clear explanations in their financial statements to ensure transparency and consistency in reporting.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Expense classifications

What is Selling and Distribution Expenses?

"*Selling and Distribution Expenses*" is a category of expenses in a company's financial statements that encompasses costs associated with the selling, marketing, and distribution of its products or services. These expenses are incurred to promote and deliver the company's offerings to customers and are essential for generating sales and revenue. In the Chart of Accounts, "*Selling and Distribution Expenses*" is typically classified as a part of operating expenses.

The components included in "*Selling and Distribution Expenses*" may vary depending on the nature of the business and its industry. Some common items that fall under this category include:

1. Sales and Marketing Expenses: These expenses cover costs related to advertising, promotions, sales commissions, sales salaries, sales incentives, trade shows, and other marketing activities aimed at attracting customers and increasing sales.
2. Distribution Costs: This includes expenses associated with the transportation, warehousing, and delivery of products to customers or retailers. It also involves the costs of setting up and maintaining a distribution network, including logistics expenses.
3. Customer Support and Service: Costs related to customer support, technical assistance, warranties, and after-sales service are also part of "Selling and Distribution Expenses."
4. Packaging and Branding: Expenses incurred for packaging materials, design, and branding activities that enhance the presentation and appeal of the products to customers.
5. Bad Debts: In some cases, bad debts resulting from uncollectible sales may be included in this category.
6. Sales and Distribution Software and Systems: Expenses related to sales and distribution software, customer relationship management (CRM) systems, and sales-related technologies.
7. Samples and Demonstrations: Costs associated with providing product samples, demonstrations, or trial offers to potential customers.
8. Sales Allowances and Returns: Provision for potential product returns or allowances to customers.

These expenses are crucial for companies aiming to promote their products effectively, reach their target market, and ensure timely delivery of goods or services to customers. Proper management of selling and distribution expenses is essential for optimizing sales performance, customer satisfaction, and overall profitability.

It's important to note that the specific breakdown of "Selling and Distribution Expenses" may differ between companies based on their unique business models, industry practices, and accounting policies. As such, the Chart of Accounts can be tailored to capture the distinct expenses relevant to each organization's operations.

What is "General and Administrative Expenses"?

"General and Administrative Expenses" is a category of expenses in a company's financial statements that encompasses various costs associated with running the day-to-day operations and management of the business. These expenses are essential for supporting the overall functioning of the organization but are not directly linked to the production of goods or the delivery of services. In the Chart of Accounts, "*General*

and Administrative Expenses" is typically classified as a part of operating expenses.

The components included in "*General and Administrative Expenses*" may vary depending on the size, nature, and industry of the business. Some common items that fall under this category include:

1. Salaries and Wages: Compensation paid to administrative staff, management, and other non-production employees who contribute to the general operations of the company.
2. Rent and Utilities: Costs related to office space, utilities (electricity, water, etc.), property taxes, and building maintenance.
3. Office Supplies: Expenses for stationery, printing materials, and other office supplies required for day-to-day administrative tasks.
4. Professional Fees: Payments to external consultants, legal advisors, auditors, and other professionals hired to provide expert services to the company.
5. Insurance: Premiums for various types of insurance coverage, such as general liability insurance, property insurance, and worker's compensation insurance.
6. Communication Costs: Expenses for telephone services, internet connectivity, and postal/courier services.
7. Travel and Entertainment: Costs related to business travel, meals, and entertainment expenses incurred by employees during company-related activities.
8. Depreciation of Administrative Assets: The allocation of the cost of administrative assets (e.g., office equipment, computers) over their useful life.
9. Office Maintenance and Repairs: Costs for repairs and maintenance of office equipment, facilities, and other administrative assets.
10. Training and Development: Expenses related to employee training, workshops, and professional development programs.
11. Office Equipment Leasing: Costs associated with leasing office equipment instead of purchasing it outright.
12. Office Security: Expenditures on security services, surveillance systems, and access control to protect office premises and assets.

These expenses are necessary for the overall management and support functions of the company, ensuring that administrative tasks are efficiently handled and the organization can operate smoothly. Proper management and control of general and administrative expenses are crucial for optimizing cost structures, maintaining financial stability, and improving the company's profitability.

Again, it's important to note that the specific breakdown of "*General and Administrative Expenses*" may differ

between companies based on their unique business models, industry practices, and accounting policies. The Chart of Accounts can be customized to accurately capture the distinct expenses relevant to each organization's administrative operations.

What is "Finance Costs"?

"*Finance Costs*" refer to the expenses incurred by a company in connection with its borrowing or financing activities. These costs are associated with obtaining and servicing various forms of debt, such as loans, bonds, and other forms of financing used to fund the company's operations and investments. In the financial statements, "*Finance Costs*" are typically classified as part of the company's operating expenses or as interest expenses in the income statement.

The components included in "*Finance Costs*" may vary depending on the company's financing arrangements and the types of debt it utilizes. Some common items that fall under this category include:

1. Interest Expense: The primary component of finance costs is the interest paid on outstanding loans or bonds. This includes both short-term and long-term interest payments.
2. Bank Charges and Fees: Fees charged by financial institutions for various services, such as loan processing fees, commitment fees, and other banking-related charges.
3. Amortization of Financing Costs: For certain financing arrangements, companies may incur costs related to setting up loans or bonds. These costs are spread over the term of the debt through amortization.
4. Foreign Exchange Losses: Finance costs may include foreign exchange losses incurred on foreign-denominated loans or financing instruments due to fluctuations in exchange rates.
5. Fair Value Changes: For certain financial instruments, such as derivatives, changes in their fair value may result in finance costs.
6. Penalty Charges: Penalties imposed for late or missed payments on debt obligations.

Finance costs are an essential aspect of a company's financial management as they impact its overall cost of capital and can significantly affect profitability and cash flow. It's crucial for businesses to carefully manage their debt levels and financing terms to minimize the impact of finance costs on their financial performance.

In contrast to "*Finance Costs*," "*Operating Expenses*" represent the day-to-day expenses of running the business that are not directly related to financing activities. Examples of operating expenses include salaries, rent, utilities, marketing expenses, and other costs necessary for the company's regular operations.

As with other financial metrics, the specific breakdown of finance costs may differ between companies

based on their financing arrangements and accounting policies. It's essential to accurately classify and disclose finance costs in financial statements to provide a clear and transparent view of a company's financial performance and obligations.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with a Help Authoring Tool

Insurance proceeds

Insurance Proceeds is a Non-operating expense - Can this also be an operating expense?

Insurance proceeds are typically not classified as expenses, but rather as income or revenue. Insurance proceeds represent funds received by a company as a result of an insurance claim or settlement, and they are generally recorded as a separate line item on the income statement.

In the context of non-operating expenses, insurance proceeds would not be classified as such. Non-operating expenses are typically associated with costs or losses incurred from activities that are not considered the primary source of expenses for the company. Insurance proceeds, on the other hand, represent a recovery or reimbursement of costs or losses, rather than an actual expense.

However, it's worth noting that insurance expenses, such as insurance premiums paid by the company, can be considered operating expenses. Insurance premiums are regular payments made by the company to an insurance provider to maintain insurance coverage for various risks. These premiums are classified as operating expenses since they are directly related to the ongoing operations of the business.

In summary, insurance proceeds are not classified as operating expenses, but rather as income or revenue when received. Insurance expenses, in the form of insurance premiums, can be classified as operating expenses.

Insurance Proceeds is a Non-operating revenue - Can this also be an operating revenue ?

Insurance proceeds are typically classified as non-operating revenue rather than operating revenue. Non-operating revenue represents income generated from sources that are not directly related to the core operations of a business. Insurance proceeds, in this context, refer to the funds received by a company as

a result of an insurance claim or settlement.

Operating revenue, on the other hand, pertains to the income generated from the primary activities of a business, such as sales of goods or services. It represents the revenue directly linked to the core operations and primary sources of income for the company.

While it is possible for a company's operations to involve insurance-related activities as part of its core business, such as an insurance company or brokerage, in most cases, insurance proceeds would be considered non-operating revenue. They represent funds received as a result of unforeseen events or incidents, such as insurance claims for property damage, loss, or liability, which are not directly related to the day-to-day operations of the business.

Therefore, in the majority of cases, insurance proceeds would be classified as non-operating revenue rather than operating revenue.

Insurance proceeds should that be recorded to determine gain or loss on the disposal of fixed assets?

No, insurance proceeds should not be recorded to determine gain or loss on the disposal of fixed assets.

When a fixed asset is disposed of, the gain or loss on the disposal is typically calculated by comparing the proceeds from the disposal (e.g., the selling price) with the carrying value of the asset (e.g., the original cost minus accumulated depreciation). Insurance proceeds, on the other hand, represent the funds received from an insurance claim or settlement due to an insured event such as damage or loss of an asset.

Insurance proceeds are not directly related to the disposal of fixed assets but rather serve to compensate for the loss or damage incurred. They are meant to restore the company's financial position to what it would have been if the insured event had not occurred.

Therefore, when determining the gain or loss on the disposal of fixed assets, insurance proceeds should not be included in the calculation. The gain or loss should be based solely on the selling price and the carrying value of the asset. Insurance proceeds should be recorded separately as non-operating revenue in the financial statements.

Created with the Standard Edition of HelpNDoc: Elevate Your Documentation with HelpNDoc's Project Analyzer Features

Suspense accounts

What is a suspense account and what is it used for?

A suspense account is a temporary account used to hold transactions or balances temporarily until they can be properly classified or allocated to their appropriate accounts. It is a tool used in accounting to temporarily accommodate transactions that cannot be immediately identified or allocated to specific accounts.

Here are some key points about suspense accounts:

1. Temporary holding: Suspense accounts are used as temporary placeholders for transactions or balances that require further investigation or clarification before they can be properly recorded or allocated.
2. Unidentified or misallocated transactions: Suspense accounts are typically used when there is uncertainty or ambiguity regarding the proper classification or allocation of a transaction. For example, if a payment is received without sufficient information to determine the specific account it should be credited to, it may be temporarily recorded in a suspense account until the correct account can be identified.
3. Resolution and adjustment: Suspense accounts should not be left unresolved indefinitely. It is important to investigate and reconcile the transactions or balances in suspense accounts promptly. Once the appropriate information or allocation is determined, the transactions should be properly recorded or allocated to their respective accounts, and the balances in the suspense account should be cleared.
4. Balancing purposes: In some cases, suspense accounts may be used to temporarily balance financial statements or trial balances when there are discrepancies or errors that need to be resolved.
5. Transparency and accuracy: While suspense accounts serve as a temporary solution, it is essential to identify and rectify the underlying issues causing the need for a suspense account. Timely resolution ensures the accuracy and transparency of financial records.

Suspense accounts should be regularly monitored and cleared to ensure that all transactions are properly recorded and allocated. It is important to investigate and resolve any issues that lead to the use of suspense accounts to maintain accurate financial reporting.

What is Suspense accounts and clearing accounts - Is this a current liability?

Suspense Accounts: A suspense account is a temporary account used to record transactions or entries when there is uncertainty or a lack of information about the appropriate account to which the entry should be posted. It acts as a holding or clearing account until the correct information is obtained and the transaction can be properly allocated to the relevant account. Suspense accounts are typically used as a temporary solution to avoid delays in the accounting process.

For example, if a company receives a payment from a customer but is unsure which specific account the payment belongs to, it may initially post the transaction to a suspense account. Later, when the appropriate details are clarified, the transaction can be moved from the suspense account to the correct account, such as accounts receivable or revenue.

Clearing Accounts: A clearing account is a temporary account used to process and reconcile transactions between two other accounts. It acts as an intermediary account to facilitate the transfer of funds or transactions from one account to another. Clearing accounts are commonly used in situations where multiple transactions need to be grouped together for efficient processing.

For example, if a company has several payments from customers that are received through different payment methods (e.g., cash, credit card, bank transfer), it may use a clearing account to temporarily pool these payments before allocating them to the appropriate individual customer accounts. Once the payments are grouped together in the clearing account, they can be easily reconciled and distributed to the respective customer accounts.

Current Liability Classification: Both suspense accounts and clearing accounts are not considered current liabilities. They are temporary accounts used for administrative and reconciliation purposes within the accounting system. As such, they do not represent obligations or liabilities of the company to external parties.

Instead, suspense accounts and clearing accounts are part of the company's internal accounting processes. They are used to facilitate accurate and organized financial record-keeping and do not directly impact the company's financial position or obligations to external stakeholders.

Is there a specific category to link these accounts?

Suspense accounts and clearing accounts are both considered temporary or intermediary accounts used to facilitate accounting processes, but they serve different purposes. They may be linked or associated with specific categories or types of transactions within a company's accounting system. Here's how they are typically linked or categorized:

Suspense Accounts: Suspense accounts are usually linked to transactions or entries that are temporarily recorded when there is uncertainty about the appropriate account to which the entry should be posted. These accounts are often used in the following situations:

1. Unidentified or Misallocated Transactions: When a transaction lacks complete or accurate information, such as a missing invoice number or customer name, it may be initially recorded in a suspense account until the correct details are obtained.
2. Timing Differences: Sometimes, transactions occur near the end of an accounting period, and there might not be enough time to allocate them properly to the correct accounts. In such cases, the transactions might be temporarily recorded in a suspense account and later reallocated in the next accounting period.
3. Accounting Errors: When errors are discovered in the accounting process, the corrective entry may be posted to a suspense account until the error is rectified.
4. System or Data Migration: During system upgrades or data migrations, transactions may be temporarily recorded in suspense accounts until they can be correctly integrated into the new system.

Clearing Accounts: Clearing accounts are generally used for grouping and reconciling multiple transactions before transferring them to their final destination. They are commonly employed in the following scenarios:

1. Multiple Payments or Receipts: When a company receives multiple payments or receipts that need to be distributed to individual customer accounts, a clearing account is used to temporarily hold these transactions until they are matched and allocated.
2. Bank Reconciliations: Clearing accounts can be used to reconcile bank transactions, especially when there are timing differences between the company's records and the bank statement.
3. Inter-company Transactions: In large organizations with multiple subsidiaries, a clearing account may be used to process intercompany transactions before they are eliminated in the consolidation process.

The specific categories or names of suspense accounts and clearing accounts may vary from one company to another, depending on their accounting systems and practices. Properly managing suspense and clearing accounts is crucial for maintaining accurate financial records and ensuring that all transactions are correctly allocated to their respective accounts.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

Commissions paid

Commissions paid can this account be used for commissions paid not to employees and the Bonusses and commissions payroll expense account be used to pay commissions on the payroll?

Yes, the "Commissions Paid" account can be used to record commissions paid to individuals or entities who are not employees of the company. This account is typically used to track and report the expenses related to commissions paid to non-employees, such as independent sales agents, brokers, or contractors.

On the other hand, the "Bonuses and Commissions" payroll expense account is generally used to record commissions that are paid to employees as part of their regular payroll. This account is specifically designated for recording the compensation-related expenses associated with bonuses and commissions paid to employees.

By using separate accounts, one for commissions paid to non-employees and another for employee bonuses and commissions, you can differentiate between the two types of expenses in your financial records. This separation allows for better tracking, analysis, and reporting of the company's commission-related expenditures.

It's important to maintain clear and accurate documentation of commission payments, whether to employees or non-employees, to ensure proper recording and reporting in accordance with accounting standards and regulations.

I see the employee commissions may need to be included in their tax certificates?

Yes, if employees receive commissions as part of their compensation, those commissions may need to be included in their tax certificates or other tax-related documents. The specific requirements for reporting commissions on tax certificates can vary depending on the tax regulations of the country or jurisdiction in which the employees are located.

Typically, commissions paid to employees are considered taxable income and should be reported as such for income tax purposes. The employer is responsible for accurately calculating and reporting the commission amounts on the employees' tax certificates or payroll documentation.

It is recommended to consult with a tax professional or accounting advisor familiar with the tax laws and regulations in your specific jurisdiction to ensure compliance with the reporting requirements related to employee commissions and to accurately reflect them in the employees' tax documentation.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Subsistence and travel allowances and advances

What methods are commonly used for subsistence and travel allowances and advances and recording of the transactions?

Subsistence and travel allowances are common forms of employee reimbursements for expenses incurred during business travel or other work-related activities. Advances may also be provided to employees to cover anticipated expenses prior to travel. Here are some methods that are commonly used for subsistence and travel allowances and advances, as well as the recording of these transactions:

1. Per diem rates: One common method for calculating subsistence allowances is to use per diem rates. These rates are set by the company or government agency and represent a fixed amount that employees can claim for meals, lodging, and incidental expenses while on business travel. Per diem rates are often set based on the location of the travel and can vary depending on the time of year.
2. Receipt-based reimbursement: Another common method is to reimburse employees for actual expenses incurred during business travel. In this method, employees must provide receipts or other documentation for expenses such as meals, lodging, transportation, and other expenses incurred during travel. The company then reimburses the employee for the actual expenses, up to a pre-determined limit.
3. Advances: Companies may also provide advances to employees to cover anticipated expenses during business travel. These advances are typically reconciled against actual expenses incurred by the employee, with any excess returned to the company and any shortfall repaid by the employee.
4. Recording transactions: The recording of subsistence and travel allowances and advances typically involves creating a separate account for each type of expense in the company's chart of accounts. These accounts may include categories such as travel, lodging, meals, and incidentals. Transactions related to subsistence and travel allowances and advances are recorded in these accounts, with appropriate documentation attached to support each transaction.

In addition to these methods, many companies use expense management software to automate the process of tracking and reimbursing employee expenses. These software systems can help reduce errors and streamline the reimbursement process, saving time and improving accuracy.

Is Travel & Subsistence an expense account and which tariffs apply in different countries?

Yes, "*Travel & Subsistence*" is typically recorded as an expense account in the chart of accounts. It represents the costs incurred by employees for business-related travel, including transportation, accommodation, meals, and other related expenses.

Regarding tariffs or rates applicable to travel and subsistence expenses, it varies depending on the country and its specific regulations. Each country may have its own tax laws, guidelines, and reimbursement rates for travel and subsistence expenses.

For example, in the United States, the Internal Revenue Service (IRS) provides guidelines and reimbursement rates known as the "*per diem rates*" for various locations. These rates specify the maximum amount that can be reimbursed for lodging, meals, and incidental expenses without the need for detailed receipts.

Similarly, other countries may have their own tax authorities or government agencies that set guidelines and rates for travel and subsistence expenses. These rates may vary based on factors such as location, duration of travel, and the purpose of the trip.

It is essential to consult the tax laws and regulations of the specific country in question or seek guidance from a qualified tax professional to determine the applicable tariffs or rates for travel and subsistence expenses.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Discounts allowed

What types of discounts are there?

There are several types of discounts that businesses may offer to customers, including:

1. Cash discount: A discount offered to customers who pay for their purchases in cash, rather than using credit or another form of payment.
2. Trade discount: A discount offered to customers who are part of a particular trade or industry. Trade discounts are often used to encourage bulk purchases or to incentivize repeat business.
3. Quantity discount: A discount offered to customers who purchase a large quantity of goods or services. Quantity discounts are often used to incentivize bulk purchases or to clear inventory.

4. Seasonal discount: A discount offered during a particular season or time of year, often to clear out inventory or to encourage sales during a slow period.
5. Promotional discount: A discount offered as part of a marketing or promotional campaign, often to introduce a new product or to encourage customers to try a product or service.
6. Early payment discount: A discount offered to customers who pay their bills early or before the due date. Early payment discounts are often used to incentivize prompt payment and improve cash flow.
7. Loyalty discount: A discount offered to customers who have been loyal to a business or who have made repeat purchases over a certain period of time. Loyalty discounts are often used to incentivize customer retention and build brand loyalty.

The specific types of discounts offered by a business may vary depending on the industry, the target customer base, and the overall business strategy.

Where would discounts allowed be processed in the Chart of accounts and what is the basic transactions?

Discounts allowed would typically be processed in the chart of accounts under a separate account code, such as "*Discounts Allowed*" or "*Sales Discounts.*" This account would be classified as a contra revenue account, which means that it reduces the amount of revenue reported on the income statement.

The basic transaction for discounts allowed involves reducing the revenue earned from a sale by the amount of the discount. For example, if a customer purchases goods with a list price of $1,000 and is offered a 10% discount, the total revenue earned from the sale would be $900 ($1,000 - $100 discount).

The journal entry to record this transaction would be:

- Debit: Cash or Accounts Receivable (depending on the payment method)
- Credit: Revenue Credit: Discounts Allowed

In this entry, the revenue account is credited for the net amount earned from the sale, while the Discounts Allowed account is credited for the amount of the discount given to the customer. The cash or accounts receivable account is debited for the amount received from the customer.

By recording discounts allowed in a separate account, businesses can track the amount of discounts given to customers and analyze their impact on revenue and profitability.

Discounts Allowed account would that be a balance sheet account or a income statement account?

The Discounts Allowed account is typically an income statement account.

It is a contra revenue account, meaning it is used to reduce the amount of revenue reported on the income statement. This account is used to record the discounts that a business offers to its customers, which are deducted from the total revenue earned from sales.

The Discounts Allowed account is an expense that reduces the gross revenue, which results in the net revenue reported on the income statement. This net revenue reflects the total revenue earned from sales, minus the cost of goods sold and any other expenses associated with generating revenue, including discounts allowed.

It is important to note that the balance in the Discounts Allowed account is a debit balance, as it represents a reduction in revenue. At the end of the accounting period, this balance is transferred to the income statement to be subtracted from the gross revenue earned during that period.

Where would discounts received be processed in the Chart of accounts and what is the basic transactions?

Discounts received would typically be processed in the chart of accounts under a separate account code, such as "Discounts Received" or "Purchase Discounts." This account would be classified as a revenue account.

The basic transaction for discounts received involves reducing the cost of goods purchased by the amount of the discount. For example, if a business purchases goods with a list price of $1,000 and is offered a 5% discount for prompt payment, the total cost of goods purchased would be $950 ($1,000 - $50 discount).

The journal entry to record this transaction would be:

- Debit: Purchases Credit: Cash or Accounts Payable (depending on the payment method)
- Credit: Discounts Received

In this entry, the purchases account is debited for the gross amount of the purchase, while the Discounts Received account is credited for the amount of the discount received from the supplier. The cash or accounts payable account is credited for the net amount paid to the supplier.

By recording discounts received in a separate account, businesses can track the amount of discounts received from suppliers and analyze their impact on expenses and profitability.

Trade discounts - does this type of discount need to be recorded?

Trade discounts are a type of discount that is offered by a supplier to a customer, based on the quantity or volume of goods purchased. These discounts are usually offered as a percentage off the list price of the goods and are often used to incentivize customers to buy in larger quantities.

In accounting, trade discounts are not typically recorded as a separate transaction. Instead, the net price of the goods, after the trade discount has been applied, is recorded as the purchase price or the sales price, depending on the transaction.

For example, if a supplier offers a customer a trade discount of 10% off the list price of goods with a list price of $1,000, the net price of the goods would be $900 ($1,000 - $100 discount). The customer would then record the purchase of the goods at the net price of $900, rather than recording a separate transaction for the trade discount.

Similarly, if a business offers a trade discount to a customer, the net price of the goods, after the discount has been applied, would be recorded as the sales price. The customer would then record the purchase of the goods at the net price, rather than recording a separate transaction for the trade discount.

It is important to note that trade discounts are different from cash discounts, which are offered for prompt payment and are typically recorded as separate transactions in accounting.

What is the difference between trade discounts and cash discounts?

Trade discounts and cash discounts are two different types of discounts that businesses may offer or receive.

Trade discounts are discounts that are offered by a supplier to a customer based on the quantity or volume of goods purchased. These discounts are usually a percentage off the list price of the goods and are designed to incentivize customers to purchase larger quantities. Trade discounts are not typically recorded as a separate transaction in accounting. Instead, the net price of the goods after the trade discount has been applied is recorded as the purchase price or sales price, depending on the transaction.

Cash discounts, on the other hand, are discounts that are offered to customers for prompt payment. For example, a business may offer a customer a 2% discount if they pay their invoice within 10 days of the invoice date. Cash discounts are recorded as a separate transaction in accounting and are deducted from the gross amount of the sale to arrive at the net amount received by the business.

The main difference between trade discounts and cash discounts is that trade discounts are used to incentivize customers to purchase larger quantities of goods, while cash discounts are used to encourage

prompt payment by customers. Additionally, trade discounts are not typically recorded as separate transactions, while cash discounts are recorded as a deduction from the gross sale amount.

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Discounts received

What types of discount received is there?

There are various types of discounts that a business can receive, depending on the nature of the transaction and the terms negotiated with the supplier. Here are some common types of discounts received:

1. Trade discounts: Trade discounts are reductions in the listed or catalog price of goods or services offered by suppliers to businesses. These discounts are usually based on the volume or quantity of purchases made or on established trade agreements. Trade discounts are not recorded as income or revenue but are rather treated as a reduction in the cost of purchases.
2. Cash discounts: Cash discounts, also known as prompt payment discounts or early payment discounts, are incentives offered to customers for paying their invoices early or within a specified time period. For example, a supplier may offer a discount of 2% if payment is made within 10 days of the invoice date. Cash discounts are recorded as a reduction in the expense or accounts payable when the payment is made.
3. Quantity discounts: Quantity discounts are discounts provided based on the quantity of goods or services purchased. These discounts encourage customers to buy larger quantities, often resulting in lower per-unit costs. Quantity discounts can be negotiated with suppliers based on the volume of purchases or predetermined quantity thresholds.
4. Seasonal or Promotional discounts: Seasonal or promotional discounts are temporary price reductions offered by suppliers to promote sales during specific periods or for specific products or services. These discounts are often associated with holidays, special events, or product launches. They can be a percentage reduction or a specific amount off the regular price.
5. Rebates: Rebates are discounts provided by suppliers after the completion of a specific condition or action. For example, a supplier may offer a rebate to a customer who achieves a certain sales target or purchases a specific quantity of goods within a specified period. Rebates are typically claimed by the customer and are recorded as a reduction in expenses or accounts payable.

It's important for businesses to carefully track and record the different types of discounts received, as they

can impact the cost of goods sold, expense recognition, and overall financial performance. Proper documentation and accounting treatment are necessary to accurately reflect the discounts received in the financial statements.

What is discount received?

Discount received refers to a reduction in the purchase price of goods or services granted by a supplier to a customer as an incentive or reward for prompt payment or other favourable terms. It is a form of trade discount offered to encourage early settlement of an invoice or to promote customer loyalty.

When a business receives a discount from a supplier, it means that the supplier is reducing the amount payable by the business for the goods or services provided. The discount received is typically expressed as a percentage or a specific amount deducted from the original invoice amount.

For accounting purposes, the discount received is recorded as a reduction in the cost of the purchases or expenses incurred by the business. It is treated as a reduction in the expense rather than as income. The discount received is usually recognized as a separate line item in the financial statements or recorded as a deduction on the purchase invoice.

The accounting entry to record a discount received is typically as follows:

1. When the purchase is initially recorded:
    - Debit: Purchases or Expense Account
    - Credit: Accounts Payable or Cash (depending on the payment method)
2. When the discount is received and applied:
    - Debit: Accounts Payable (for the discounted amount)
    - Debit: Discount Received (for the amount of the discount)
    - Credit: Cash (if the payment is made in cash) or Accounts Payable (if the payment is made through credit)

By recording the discount received separately, businesses can track and analyse the impact of discounts on their financial performance and evaluate the effectiveness of their discount policies or supplier relationships.

Is trade discounts received from a supplier recorded?

Yes, trade discounts received from a supplier are typically recorded in the accounting records of a business. However, it's important to note that trade discounts are not recognized as income or revenue. Instead, they are treated as a reduction in the cost of purchases or expenses.

When a trade discount is received, the business will record the transaction in its accounting system. The specific recording method can vary depending on the accounting framework and practices followed by the business. Here is a common approach:

1. Initial Purchase Recording:
    - Debit: Purchases or Expense Account (for the gross amount before the trade discount)
    - Credit: Accounts Payable or Cash (depending on the payment method)
2. Recognition of Trade Discount:
    - Debit: Accounts Payable (for the reduced amount after the trade discount)
    - Credit: Trade Discounts Received (for the amount of the trade discount)

In this entry, the accounts payable is reduced by the amount of the trade discount, reflecting the lower amount payable to the supplier. The trade discounts received account is credited to capture the value of the trade discount received. The trade discounts received account is usually presented as a separate line item in the financial statements or as a deduction on the purchase invoice.

Recording trade discounts received separately allows businesses to track and analyse the impact of trade discounts on their financial performance and assess the effectiveness of their discount arrangements with suppliers. It provides transparency and helps in evaluating the overall cost structure and profitability of the business.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Delivery charges

What is Delivery charges?

Delivery charges refer to the fees or costs incurred by a company or individual to transport goods or services from one location to another. These charges are associated with the logistics and transportation of goods to their intended destinations, whether it's delivering products to customers, moving inventory between warehouses, or distributing goods to retailers.

Delivery charges can vary depending on various factors, including the distance of transportation, the weight and volume of the goods, the mode of transportation (e.g., courier, truck, air freight), and the urgency of delivery (e.g., standard shipping, express delivery).

For businesses engaged in selling products, delivery charges are often an essential aspect of the supply

chain and can impact customer satisfaction and the overall cost of goods sold. Companies may choose to absorb the delivery charges into the product's selling price or pass them on to customers as separate charges.

Types of Delivery Charges:

1. Shipping Charges: These charges apply to the transportation of goods from the seller's location to the customer's delivery address. Shipping charges can be calculated based on factors like distance, package weight, and shipping method selected by the customer.
2. Freight Charges: Freight charges are associated with the transportation of larger shipments or bulk goods. They are commonly used in the context of commercial shipments that require specialized freight carriers.
3. Handling Fees: Handling fees may be added to cover the cost of packaging, processing, and preparing goods for shipment. These fees may apply to both individual customers and business-to-business transactions.
4. Delivery Surcharge: A delivery surcharge may be imposed for deliveries to remote or difficult-to-access locations, which require additional effort or specialized transportation arrangements.
5. Express Delivery Charges: For expedited or express shipping services that guarantee quicker delivery times, additional charges may apply.

Delivery charges are an integral part of businesses' shipping and logistics operations and need to be managed effectively to ensure timely and cost-efficient deliveries. For customers, understanding delivery charges is crucial when making purchasing decisions, as it can impact the total cost of the goods they are buying.

Can delivery charges part of "Other income" or Operating expenses?

The classification of delivery charges as "*Other Income*" or "*Operating Expenses*" depends on the nature and purpose of these charges within a company's business activities. Let's examine how delivery charges may be treated in each category:

1. Other Income: Delivery charges can be classified as "Other Income" if they represent revenue generated by the company from providing delivery services to customers or other businesses. In this case, the delivery charges are considered an ancillary or secondary source of income for the company.

   For example, if a company operates an online store and charges customers for delivery services when they purchase products, the delivery charges would be considered as "Other Income." The amount received from customers for delivery services would be added to the company's revenue under this

category.

2. Operating Expenses: On the other hand, delivery charges may be treated as "*Operating Expenses*" if they represent costs incurred by the company to deliver goods to customers. In this case, the delivery charges are considered a part of the company's operating costs directly related to its main business activities.

   For instance, if a company incurs expenses for shipping and delivering products to customers, these expenses are classified as "Operating Expenses." These costs are subtracted from the company's revenue to calculate its operating profit or loss.

3. Determining the Appropriate Classification: To determine the appropriate classification for delivery charges, consider the role of delivery services in the company's overall business model. If delivery charges are an essential component of the company's revenue-generating activities, they should be included as "*Other Income*." Conversely, if delivery charges represent costs incurred in the process of providing goods to customers, they should be categorized as "*Operating Expenses*."

It's crucial for companies to maintain accurate financial records and adhere to proper accounting principles when classifying various items in their financial statements. The classification of delivery charges has implications for financial analysis, tax reporting, and decision-making, so it's essential to ensure consistency and transparency in accounting practices. If there is uncertainty about how to classify specific charges, consulting with an accountant or financial professional can provide guidance and ensure compliance with accounting standards.

Delivery charge expenses - could that also be as Cost of Goods Sold (COGS)?

Yes, delivery charge expenses can be considered as part of the Cost of Goods Sold (COGS) under certain circumstances. The treatment of delivery charges as COGS depends on whether these expenses are directly associated with the production or purchase of goods that the company sells.

COGS represents the direct costs incurred in producing or acquiring the goods that a company sells to its customers. It typically includes the cost of raw materials, direct labour, and other directly attributable production costs. If delivery charges are directly tied to the production or purchase of goods and are necessary to get the products to the company's premises or customers, they can be included as part of the COGS.

Here are a few scenarios where delivery charges could be considered as part of COGS:

1. Delivery of Raw Materials: If the company incurs delivery charges for transporting raw materials to its manufacturing facility, and these raw materials are used to produce the goods that the company sells, then the delivery charges can be treated as part of COGS.

2. Shipping of Finished Goods: If the company pays for shipping and delivery of the finished goods to customers as part of the sales process, and these delivery charges are directly linked to the sale of the goods, they can be included as part of COGS.
3. Direct Purchase Costs: If the company purchases goods for resale and pays delivery charges as part of the purchase transaction, these charges can be added to the cost of the goods and included in COGS.

It's important to note that not all delivery charges are classified as COGS. If delivery charges are related to general administrative expenses, such as delivering documents or office supplies, they are not part of COGS but are treated as regular operating expenses.

Properly categorising expenses, including delivery charges, is crucial for accurate financial reporting and understanding the true cost of goods sold. If there is uncertainty about how to classify specific delivery charges, consulting with an accountant or financial professional can provide guidance and ensure compliance with accounting principles.

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Directors' remuneration

What is Directors' remuneration?

Directors' remuneration refers to the compensation, fees, and benefits paid to the directors of a company for their services and responsibilities as members of the board of directors. Directors are individuals elected or appointed by shareholders to oversee the management and strategic decision-making of the company. They play a crucial role in setting the company's direction, ensuring its compliance with laws and regulations, and safeguarding the interests of shareholders.

Directors' remuneration can take various forms, and the specific components may vary depending on the company's size, industry, and corporate governance practices. Some common elements of directors' remuneration include:

1. Director's Salaries: This is the fixed regular payment or annual salary paid to executive directors for their day-to-day involvement in managing the company's operations.
2. Director's Fees: Non-executive directors, who are not involved in the daily management of the company, may receive fees for attending board meetings, committee meetings, and other company-related activities.

3. Bonuses: Some companies offer performance-based bonuses to directors, linked to the achievement of specific financial or strategic targets.
4. Share-Based Payments: Directors may receive stock options, restricted stock units, or other equity-based compensation as part of their remuneration package.
5. Benefits: Directors may receive various benefits, such as health insurance, retirement contributions, car allowances, and other fringe benefits.
6. Pension Contributions: Companies may contribute to pension funds or retirement plans on behalf of their directors.
7. Perquisites (Perks): Certain non-cash benefits or perquisites, such as club memberships or travel allowances, may be provided to directors.

Directors' remuneration is a significant aspect of corporate governance and is subject to scrutiny by shareholders, regulators, and other stakeholders. Companies are required to disclose the details of directors' remuneration in their financial statements and annual reports to ensure transparency and accountability.

In some jurisdictions, there are specific regulations or guidelines governing directors' remuneration, particularly for publicly listed companies. These regulations aim to ensure that director remuneration is fair, reasonable, and aligned with the company's performance and long-term interests.

The level of directors' remuneration can vary widely based on factors such as the company's financial performance, industry norms, corporate governance practices, and the directors' responsibilities and qualifications. It is ultimately the responsibility of the company's board of directors or remuneration committee to determine appropriate remuneration packages for directors, taking into account these various factors and the interests of shareholders.

For a company, directors remuneration would be recorded as a separate item under Operating expenses - What would the structure and accounts for Directors remuneration be?

The structure and accounts for recording directors' remuneration would typically be categorized under the operating expenses section of a company's income statement. Directors' remuneration refers to the compensation and benefits paid to the company's directors for their services as board members. It includes various forms of payments, such as salaries, fees, bonuses, and other benefits. Below are the key accounts that might be used to record directors' remuneration:

1. Director's Salaries: This account records the fixed monthly or annual salaries paid to the company's directors for their services as executives or non-executive directors.

2. Director's Fees: If directors receive fees for attending board meetings or serving on committees, this account is used to record those payments.
3. Director's Bonuses: If directors are entitled to receive bonuses based on company performance or specific targets, this account is used to track those bonus payments.
4. Director's Benefits: This account includes non-cash benefits or perquisites provided to directors, such as health insurance, car allowances, housing allowances, and other fringe benefits.
5. Retirement Contributions: If the company contributes to retirement funds or pension plans on behalf of directors, this account is used to record those contributions.
6. Director's Share-Based Payments: If directors receive share options or equity-based compensation as part of their remuneration, this account is used to track the value of those share-based payments.
7. Social Security Contributions: The company may be required to contribute to social security schemes on behalf of its directors. This account records those contributions.
8. Payroll Taxes: This account includes any payroll taxes, such as income tax withheld at source, related to directors' remuneration.

These accounts are typically combined to calculate the total remuneration expense for directors, which is then included in the overall operating expenses of the company. Directors' remuneration is an important component of corporate governance and is subject to disclosure and transparency requirements in financial statements and annual reports.

It's important to note that the specific account names and structure may vary from one company to another based on their accounting practices and reporting requirements. Companies should adhere to relevant accounting standards and regulations when recording and disclosing directors' remuneration. Additionally, for publicly listed companies, there may be additional disclosure requirements regarding directors' remuneration in the notes to the financial statements.

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Financial Intelligence Centre Act (FICA)

What is FICA?

FICA stands for the Financial Intelligence Centre Act, which is a piece of legislation in South Africa that aims to combat money laundering, terrorist financing, and other financial crimes. The act was enacted in 2001 and has since been amended to strengthen the country's anti-money laundering and counter-terrorism

financing (AML/CFT) framework.

The main objectives of the FICA are to:

1. Identify and Verify Customers: FICA requires financial institutions and accountable institutions to identify and verify the identity of their customers or clients when establishing business relationships or conducting occasional transactions.
2. Report Suspicious Transactions: FICA mandates financial institutions and accountable institutions to report any transactions that they suspect to be related to money laundering, terrorist financing, or other criminal activities to the Financial Intelligence Centre (FIC).
3. Record Keeping: FICA requires institutions to maintain records of customer identification and transaction information for a specified period to enable effective monitoring and compliance with the law.
4. Customer Due Diligence (CDD): Financial institutions are required to perform risk-based customer due diligence to understand their customers' activities and ensure that they are not involved in illegal or suspicious transactions.
5. Reporting of Cash Transactions: FICA requires financial institutions to report cash transactions exceeding certain thresholds to the FIC. This helps in monitoring large cash movements and detecting potential money laundering activities.

FICA places obligations on a wide range of entities, including banks, financial services providers, attorneys, accountants, estate agents, and casinos, among others. These entities are referred to as "accountable institutions" under the FICA. They play a critical role in the fight against financial crime by identifying and reporting suspicious activities to the FIC.

The Financial Intelligence Centre (FIC) is the regulatory body responsible for overseeing and enforcing compliance with the FICA in South Africa. The FIC receives, analyzes, and disseminates financial intelligence to law enforcement agencies to support their efforts in combating financial crimes.

FICA is an essential component of South Africa's efforts to maintain a robust financial system and prevent illicit financial activities. By imposing strict measures to identify customers, report suspicious transactions, and maintain proper records, FICA aims to protect the integrity of the country's financial sector and deter criminals from exploiting financial institutions for illegal purposes.

Is there any specific accounts in the Chart of Accounts related to FICA?

In the Chart of Accounts of a company or organization, there are generally no specific accounts directly related to FICA (Financial Intelligence Centre Act) compliance. FICA is a regulatory framework in South Africa

that imposes obligations on financial institutions and accountable institutions to combat money laundering and terrorist financing. It focuses on customer identification, verification, reporting of suspicious transactions, and record-keeping requirements.

While there might not be specific accounts in the Chart of Accounts dedicated to FICA, the accounting processes and records play a crucial role in ensuring compliance with the FICA regulations. Some aspects of FICA compliance are reflected indirectly in various accounts and transactions. Here are some examples:

1. Suspicious Transaction Reporting: If the company is an accountable institution under FICA and identifies a suspicious transaction, the process of reporting it to the Financial Intelligence Centre may involve documenting the details of the transaction and any related customer accounts.
2. Customer Due Diligence: The customer identification and verification process required by FICA might involve recording customer details, identification documents, and other relevant information in the accounting system.
3. Record-Keeping: FICA mandates the retention of records related to customer identification, transactions, and suspicious activities. These records might be stored in the company's accounting system or other databases.
4. Compliance Costs: The expenses incurred by the company to ensure compliance with FICA requirements, such as implementing systems for customer due diligence, staff training, and enhanced monitoring, would be recorded in appropriate expense accounts.

While FICA compliance is not directly reflected in specific accounts within the Chart of Accounts, it does have a significant impact on the company's overall accounting and reporting processes. Companies that are subject to FICA regulations need to maintain proper records and documentation to demonstrate their compliance with the law. Additionally, they may need to engage with auditors and regulatory authorities to ensure adherence to FICA requirements.

It's essential for companies to have well-designed internal controls and accounting procedures to comply with FICA and other relevant anti-money laundering and counter-terrorism financing regulations. Professional advice from accountants, auditors, or legal experts can be sought to ensure appropriate FICA compliance measures are in place.

In which countries does FICA or related legislation apply?

The term "FICA" specifically refers to the Financial Intelligence Centre Act, which is a piece of legislation in South Africa. FICA is designed to combat money laundering, terrorist financing, and other financial crimes in South Africa. It establishes measures for customer identification, verification, and reporting of suspicious transactions for various accountable institutions, including financial institutions, attorneys, accountants, estate agents, and casinos.

It's important to note that FICA is specific to South Africa and may not apply to other countries. Different countries have their own anti-money laundering (AML) and counter-terrorism financing (CTF) laws and regulations that are tailored to their specific legal and financial systems.

In other countries, similar legislation and regulations exist to address AML and CTF concerns, but they have different names and legal frameworks. Some examples of AML/CTF legislation in other countries include:

1. USA: The United States has the Bank Secrecy Act (BSA) and the USA PATRIOT Act, which impose AML and CTF obligations on financial institutions.
2. Canada: Canada has the Proceeds of Crime (Money Laundering) and Terrorist Financing Act (PCMLTFA) to combat money laundering and terrorist financing.
3. United Kingdom: The UK has the Money Laundering Regulations, which outline the AML and CTF requirements for various businesses and professions.
4. Australia: Australia has the Anti-Money Laundering and Counter-Terrorism Financing Act (AML/CTF Act) to address money laundering and terrorist financing risks.
5. European Union: The EU has various directives and regulations, such as the Fourth Anti-Money Laundering Directive (AMLD4) and the Fifth Anti-Money Laundering Directive (AMLD5), which are implemented by member states.
6. Singapore: Singapore has the Corruption, Drug Trafficking and Other Serious Crimes (Confiscation of Benefits) Act and the Terrorism (Suppression of Financing) Act to address AML and CTF concerns.

These are just a few examples of AML/CTF legislation in different countries. Each country's laws and regulations aim to ensure that financial systems are not misused for illegal purposes and to promote transparency and integrity in financial transactions. Companies and institutions operating in multiple jurisdictions must comply with the relevant AML/CTF regulations in each country where they conduct business.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Federal Insurance Contributions Act (FICA)

FICA (Federal Insurance Contributions Act) - Which countries uses this legislation - Is there similar legislation?

The term "*FICA*" specifically refers to the Federal Insurance Contributions Act, and it is a United States federal law. FICA is the legislation that governs the collection of Social Security and Medicare taxes in the

United States. Therefore, FICA is not used in other countries.

However, other countries have their own social security and healthcare contribution systems, which may be similar in concept but operate under different names and legal frameworks. These systems are designed to provide social insurance and healthcare benefits to citizens and residents. Here are some examples of similar legislation in other countries:

1. Canada: In Canada, the social security program is known as the Canada Pension Plan (CPP) and the Employment Insurance (EI) program. The contributions made by employees and employers are used to fund retirement, disability, and survivor benefits, as well as employment insurance for those who lose their jobs.
2. United Kingdom: In the UK, the social security system includes National Insurance contributions, which fund various benefits such as the State Pension, Jobseeker's Allowance, and Maternity Allowance.
3. Australia: In Australia, the social security system includes contributions to the Superannuation Guarantee, which is used to provide retirement benefits to eligible employees.
4. Germany: In Germany, social security contributions are made to various funds, including those for pension insurance, health insurance, unemployment insurance, and long-term care insurance.
5. Japan: In Japan, social security contributions fund various benefits, including the National Pension and Health Insurance systems.

Each country's social security and healthcare contribution systems are unique and tailored to the specific needs and priorities of that nation. They typically aim to provide financial security and support to individuals in various life situations, such as retirement, disability, unemployment, and medical needs.

It's important for individuals and businesses to be aware of the social security and healthcare contribution requirements in their respective countries to ensure compliance with the law and to avail themselves of the benefits provided by these systems.

Accrued – FICA

The account "*Accrued – FICA*" likely refers to an accounting entry used to record the accrual of FICA (Federal Insurance Contributions Act) taxes that are owed by a company but not yet paid. FICA taxes are a combination of Social Security tax and Medicare tax imposed on employees and employers in the United States to fund the Social Security and Medicare programs.

The term "*Accrued*" indicates that the taxes have been incurred or earned but not yet paid or remitted to the relevant tax authorities. Accrual accounting recognizes income and expenses when they are earned or incurred, regardless of when the actual cash transaction takes place.

In the context of payroll accounting, a company is responsible for withholding FICA taxes from its

employees' wages and also contributes an employer portion of the tax. The company must remit both the employee and employer portions of FICA taxes to the Internal Revenue Service (IRS) on a regular basis.

When accounting for FICA taxes, a company may use an accrual entry to recognize the portion of FICA taxes owed to the employees and the government for the current accounting period but not yet paid. This allows the company to accurately reflect its financial obligations and liabilities related to payroll taxes.

The entry to record the accrual of FICA taxes might look like this:

Debit: Payroll Expense

Credit: Accrued – FICA

In this entry, "*Payroll Expense*" represents the total FICA taxes (both the employee and employer portions) incurred during the accounting period. The credit to "*Accrued – FICA*" signifies the amount of FICA taxes accrued but not yet paid.

The accrued FICA taxes will later be reversed and settled when the company actually pays the payroll taxes to the tax authorities, typically during the next payroll tax reporting period. Accrued FICA taxes are typically reported as a current liability on the company's balance sheet until they are paid.

It's important to note that the specific account numbers and names in the Chart of Accounts can vary between companies and accounting systems. The example provided above is a general illustration of how accrued FICA taxes might be recorded in the company's accounting records.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Risk management

What is risk management?

Risk management is the process of identifying, assessing, and mitigating or managing potential risks that could affect an individual, organization, project, or any other endeavour. Risks are uncertainties or events that have the potential to impact objectives, goals, or outcomes in a negative way. The goal of risk management is to minimize the negative impact of these uncertainties while maximizing the opportunities for positive outcomes.

Key steps in the risk management process include:

1. Risk Identification: This involves identifying potential risks that could affect the project, organization, or goal. Risks can come from various sources, including financial, operational, legal, technological, environmental, and more.

2. Risk Assessment: Once risks are identified, they are assessed in terms of their likelihood of occurring and the potential impact they could have. This assessment helps prioritize which risks need the most attention.
3. Risk Analysis: Risk analysis involves diving deeper into the identified risks to understand their root causes, potential consequences, and potential interdependencies. This helps in developing effective strategies for risk mitigation.
4. Risk Mitigation Planning: In this step, strategies and plans are developed to either prevent risks from occurring or to minimize their impact if they do occur. Mitigation strategies can include preventive measures, contingency plans, risk transfer (such as insurance), and risk avoidance.
5. Implementation: The risk mitigation strategies are put into action. This might involve making operational changes, investing in technology, developing backup plans, or any other necessary actions.
6. Monitoring and Review: Risks and risk management strategies need to be continuously monitored to ensure they remain relevant and effective. New risks might emerge, or the impact of existing risks could change, requiring adjustments to the risk management plan.
7. Communication: Clear communication of risks and risk management plans is crucial to ensure that all stakeholders are aware of potential issues and understand how they will be addressed.

Risk management is not just about avoiding negative outcomes but also about capitalizing on opportunities. By identifying and managing risks effectively, organizations and individuals can improve decision-making, allocate resources wisely, and enhance their ability to achieve their objectives in an uncertain environment.

Various industries, including finance, project management, healthcare, and information technology, employ risk management to safeguard their operations and investments. Different frameworks and methodologies are used to implement risk management, such as ISO 31000, COSO ERM, and PMI's Project Risk Management framework. The approach taken depends on the specific context and goals of the entity or project involved.

What is the components of risk management in accounting?

In the context of accounting, risk management involves identifying and addressing financial risks that could impact an organization's financial statements, operations, and overall financial health. The components of risk management in accounting typically include:

1. Risk Identification: This is the process of identifying potential financial risks that an organization may face. These risks could include credit risk (default by customers or counterparties), liquidity risk (inability to meet short-term financial obligations), market risk (fluctuations in interest rates, exchange rates, and commodity prices), operational risk (internal processes and systems failures), and

regulatory compliance risk (failure to adhere to financial reporting and legal requirements).

2. Risk Assessment and Analysis: Once risks are identified, they need to be assessed and analyzed to determine their potential impact on the organization's financial performance, financial position, and cash flow. This involves estimating the likelihood of the risk occurring and the potential magnitude of its impact.
3. Risk Mitigation Strategies: After assessing risks, organizations develop strategies to mitigate or manage these risks. For example, they might implement credit policies to minimize the risk of default by customers, establish cash reserves to address liquidity risk, use hedging strategies to manage market risk, and improve internal controls to mitigate operational risk.
4. Internal Controls: Internal controls are mechanisms put in place to ensure accurate financial reporting, safeguard assets, and prevent fraud. They play a crucial role in managing financial risks. Examples of internal controls include segregation of duties, authorization and approval procedures, and regular reconciliations.
5. Financial Reporting: Clear and accurate financial reporting is essential for risk management. Transparent financial statements provide stakeholders with information about the organization's financial position, performance, and any potential risks that might impact its future prospects.
6. Contingency Planning: Contingency planning involves preparing for potential adverse events. Organizations develop contingency plans that outline steps to take if a risk materializes. For instance, a company might have a contingency plan for a sudden economic downturn or a significant disruption in its supply chain.
7. Risk Monitoring and Review: Regular monitoring of financial risks is essential to ensure that mitigation strategies are effective and up-to-date. Organizations need to adapt their risk management efforts as the business environment evolves and new risks emerge.
8. Stakeholder Communication: Effective communication with stakeholders, including investors, lenders, regulators, and employees, is vital. Transparent communication about the organization's risk exposure and risk management strategies helps build trust and confidence.
9. Compliance and Regulatory Risk: Adhering to accounting standards and regulatory requirements is a critical aspect of risk management in accounting. Non-compliance can lead to financial penalties, legal issues, and reputational damage.
10. Technology and Cybersecurity Risk: With the increasing reliance on technology, organizations need to address risks related to data security, cybersecurity, and potential disruptions to digital systems.
11. Ethical Considerations: Managing ethical risks is also important in accounting, as unethical behaviour can lead to financial misstatements, legal consequences, and reputational damage.

It's important to note that the components of risk management in accounting can vary depending on the size of the organization, the industry it operates in, and the specific risks it faces. Effective risk management requires collaboration among various departments, including finance, operations, legal, and compliance, to ensure a holistic approach to identifying, assessing, and mitigating risks.

Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Internal control

What is internal control?

Internal control refers to the set of policies, procedures, and practices implemented within an organization to safeguard assets, ensure the accuracy and reliability of financial information, promote operational efficiency, and achieve the organization's objectives. It is a crucial aspect of corporate governance and risk management, designed to provide reasonable assurance that the organization's resources are used effectively and that operations are conducted in compliance with relevant laws and regulations.

Key elements of internal control include:

1. Risk Assessment: Identifying and analyzing potential risks that could affect the achievement of organizational goals and objectives.
2. Control Environment: Establishing a positive tone at the top of the organization that emphasizes the importance of internal control and ethical behavior.
3. Control Activities: Implementing specific policies, procedures, and practices to mitigate identified risks and ensure the integrity of financial and operational processes.
4. Information and Communication: Ensuring that relevant and timely information is communicated both vertically and horizontally throughout the organization.
5. Monitoring: Regularly assessing the effectiveness of internal control measures and making necessary adjustments to address changing circumstances and risks.

Internal control can encompass a wide range of activities and mechanisms, including segregation of duties, authorization and approval procedures, physical safeguards, access controls, reconciliations, reviews and approvals, and internal audits.

The objectives of internal control are threefold:

1. Efficiency and Effectiveness: Ensuring that operations and processes are carried out efficiently, promoting optimal resource utilization and maximizing productivity.

2. Reliability of Financial Reporting: Providing reasonable assurance that financial statements and other financial information are accurate, complete, and free from material misstatements.
3. Compliance: Ensuring that the organization complies with applicable laws, regulations, and internal policies, reducing the risk of legal and regulatory violations.

Internal control is not a one-time activity but an ongoing process that requires continuous monitoring, evaluation, and improvement. It involves collaboration between different levels of management and employees to establish a strong control environment that fosters ethical behaviour and accountability. Effective internal control contributes to the overall success and sustainability of the organization by minimizing risks and providing stakeholders with confidence in the organization's operations and financial reporting.

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Credit notes and Debit notes

What is Credit notes and Debit notes?

Credit notes and debit notes are both financial documents used in accounting to record adjustments in transactions and correct errors in invoices or billing. They are commonly used in business-to-business (B2B) transactions and can be issued by both sellers and buyers.

1. Credit Note: A credit note is a document issued by a seller to a buyer when there is an overcharge or an error in the original invoice. It serves to decrease the amount owed by the buyer to the seller. The reasons for issuing a credit note can vary, such as goods returned by the buyer, incorrect pricing, quantity discrepancies, or any other adjustments needed to the original invoice.

   For example, if a company sells goods to a customer for $1,000 but later realizes that they overcharged by $100, they would issue a credit note to the customer for $100. The customer can then deduct this amount from their outstanding balance.

2. Debit Note: A debit note, on the other hand, is a document issued by a buyer to a seller when there is an undercharge or an error in the original invoice. It serves to increase the amount owed by the buyer to the seller. Like credit notes, the reasons for issuing debit notes can vary, such as the seller undercharging for goods or services, billing mistakes, or any other adjustments required.

   For example, if a company receives goods from a supplier and the supplier undercharges them by $50, the buyer will issue a debit note to the supplier for $50. This additional amount will be added to the outstanding balance that the buyer owes to the supplier.

In both cases, credit notes and debit notes help in maintaining accurate and transparent accounting records, ensuring that financial transactions are correctly documented and any discrepancies are appropriately addressed. They serve as supporting documents and are often used during the process of reconciling accounts between buyers and sellers.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

---

Purchase Returns and Purchase Discounts

Purchase Returns and Purchase Discounts list of account codes or account categories used in accounting or financial management systems. These codes are typically part of a chart of accounts, which is a standardized list of accounts that a business uses to categorize its financial transactions. Each account code corresponds to a specific type of financial transaction or activity. Here's what each of these accounts represents:

1. G5900-000 - Purchase Returns: This account is used to track returns of goods or products that a business has purchased from its suppliers. When a business returns a purchase, it records the transaction in this account to reflect a reduction in the cost of goods purchased. Depending on your company's accounting policies and jurisdiction, you may need to configure the default contra account if you wish to allocate supplier returns to an account different from the default purchase account in most Sets of Books templates available in osFinancials5/TurboCASH5.
2. G5950-000 - Purchase Discounts: This account is used to track discounts received by a business for early payment of its bills or invoices from suppliers. When a business takes advantage of purchase discounts by paying its bills early, it records the discount amount in this account to reflect the savings achieved.

These account codes are part of a structured accounting system and help businesses accurately record and categorize their financial transactions for reporting and analysis purposes. The specific codes and account names may vary between businesses and accounting systems, but they generally serve similar purposes across different organizations.

Sales Allowances and Sales Discounts

Sales Allowances and Sales Discounts are part of a chart of accounts used in accounting and financial management systems. Here's what each of these accounts represents:

1. G4800-000 - Sales Allowances: This account is used to track allowances granted to customers for issues such as damaged goods, defects, or other reasons that lead to a reduction in the sale price. Sales allowances are essentially deductions from the total sales revenue due to concessions made to customers after a sale has been completed. Depending on your company's accounting policies and jurisdiction, you may need to configure the default contra account if you wish to allocate credit notes to an account different from the default sales account in most Sets of Books templates available in osFinancials5/TurboCASH5.
2. G4900-000 - Sales Discounts: This account is used to record discounts offered to customers as an incentive for early payment. When a customer takes advantage of a sales discount by paying their invoice early, the discount amount is recorded in this account. Sales discounts are often expressed as a percentage of the invoice total and are intended to encourage prompt payment.

These account codes help businesses keep track of various adjustments to their sales revenue, whether it's due to allowances made to customers or discounts offered to encourage timely payment. Properly categorizing these transactions is essential for accurate financial reporting and analysis.

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Customer Returns and Credit notes - Default Contra account

Customer Returns and Credit notes

When a customer returns goods and a credit note is issued, the accounting treatment typically depends on the reason for the return and the specific accounting policies of the company. Credit notes can be offset against different accounts, and the choice often depends on the nature of the return and the impact on the company's financial statements. Two common approaches are:

1. Offset Against Sales Revenue (Sales Account): If the returned goods are being credited back to the customer, and the company is reducing its reported sales revenue, the credit note can be offset against the sales account. This is often the case when the returned goods are being deducted from the total sales revenue because they were sold in error, were damaged, or for some other reason that requires a reduction in sales.

   For example, if a customer returns $100 worth of goods, the company could reduce its sales revenue by $100 by offsetting it against the sales account.
2. Offset Against Sales Allowances: If the credit note represents a concession or allowance given to the customer (e.g., for damaged goods or a pricing dispute), it is commonly offset against the "Sales Allowances" account. This reduces the net sales revenue reported in the financial statements.

For example, if a customer is granted a $20 allowance for damaged goods, the $20 credit note would be offset against the "Sales Allowances" account to reflect the reduction in sales revenue.

The choice between these two options depends on the company's accounting policies, the specific circumstances of the return, and how the company wants to present its financial statements. Both approaches are acceptable and can be used depending on what makes the most sense for accurate financial reporting.

It's important for a company to have clear and consistent accounting policies in place for handling returns and credit notes to ensure accurate and transparent financial reporting. These policies should be in line with generally accepted accounting principles (GAAP) or International Financial Reporting Standards (IFRS) if applicable in the company's jurisdiction.

Set default contra account for Credit notes

In osFinancials5/TurboCASH5, the default configuration for handling invoices and credit notes involves utilizing the Sales Journal. Consequently, by default, credit notes are set to offset against the Sales Account.

However, should you wish to utilize a different account, like the Sales Allowances account, to offset credit notes instead of the Sales Account, you will need to follow these steps within osFinancials:

1. Navigate to the Setup menu and select Batch types from the options provided on the Setup ribbon. Here, you can create a specific journal, such as the Sales Returns journal.
2. Within the "*Options for this batch*," you can specify the contra account as "Sales Allowances" or any other specific account distinct from the Sales Account.
3. Access the Setup menu again, this time selecting Document setup from the options on the Setup ribbon. On the Credit notes tab, you can designate the Sales Returns journal as the desired journal for credit note transactions.

This approach aligns with established accounting practices where businesses often employ separate journals or accounts to meticulously track returns, allowances, and discounts, ensuring the precision of financial reporting and facilitating thorough analysis.

It remains essential to tailor osFinancials5/TurboCASH5 to conform to your company's unique accounting policies and reporting criteria. This flexibility to configure contra accounts for various transaction types, such as sales returns and allowances, empowers businesses to uphold the accuracy and transparency of their financial records.

Created with the Standard Edition of HelpNDoc: Protect Your Confidential PDFs with These Simple Security

Purchase Returns and Credit Notes issued by Suppliers

If a supplier returns goods sold a credit note is issued - could the supplier be offset against the purchase account - or would it commonly be offset against "Purchase Allowances:"

When a supplier returns goods, and a credit note is issued by the supplier, the accounting treatment typically depends on the nature of the return and the specific accounting policies of the company. Credit notes issued by suppliers can be offset against different accounts, and the choice often depends on the circumstances surrounding the return:

1. Offset Against the Purchase Account : If the credit note from the supplier represents a reduction in the cost of goods purchased or a refund for goods returned due to defects or other reasons, it can be offset against the relevant purchase account. This approach effectively reduces the cost of the goods initially recorded in the purchase account.

   For example, if a company originally recorded a purchase of $1,000 worth of goods from a supplier and later received a credit note for $200 due to returned goods or a pricing adjustment, the credit note could be offset against the purchase account, reducing the recorded purchase cost to $800.

2. Offset Against Purchase Allowances (or Purchase Returns): If the credit note represents a concession or allowance given by the supplier, such as a discount or rebate for early payment or for accepting goods with minor defects, it is commonly offset against an account like "Purchase Allowances" or "Purchase Returns." This approach reduces the net cost of purchases.

   For example, if a supplier offers a $50 allowance for goods with minor defects, the $50 credit note would be offset against the "Purchase Allowances" or "Purchase Returns" account.

The choice between these two options depends on the company's accounting policies, the specific circumstances of the return, and how the company wants to present its financial statements. Just like with customer returns, it's important for a company to have clear and consistent accounting policies for handling supplier returns and credit notes to ensure accurate financial reporting. These policies should align with relevant accounting standards and guidelines in the company's jurisdiction.

Set default contra account for Supplier returns

In osFinancials5/TurboCASH5, the default configuration for handling purchases and supplier returns involves utilizing the Purchase Journal. Consequently, by default, supplier returns (credit notes issued by

suppliers) are set to offset against the Purchase Account.

However, should you wish to utilize a different account, like the Purchase Allowances account, to offset supplier returns instead of the Purchase Account, you will need to follow these steps within osFinancials:

1. Navigate to the Setup menu and select Batch types from the options provided on the Setup ribbon. Here, you can create a specific journal, such as the Purchase Returns journal.
2. Within the "*Options for this batch*," you can specify the contra account as "Purchase Allowances" or any other specific account distinct from the Purchase Account.
3. Access the Setup menu again, this time selecting Document setup from the options on the Setup ribbon. On the Supplier returns tab, you can designate the Purchase Returns journal as the desired journal for supplier return transactions.

This approach aligns with established accounting practices where businesses often employ separate journals or accounts to meticulously track returns, allowances, and discounts, ensuring the precision of financial reporting and facilitating thorough analysis.

It remains essential to tailor osFinancials5/TurboCASH5 to conform to your company's unique accounting policies and reporting criteria. This flexibility to configure contra accounts for various transaction types, such as supplier returns and allowances, empowers businesses to uphold the accuracy and transparency of their financial records.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

List of Accounts - Classification

Basic outline for a 4-digit main accounts chart of accounts

The outline for the chart of accounts is a general framework that can be applicable to various accounting systems, including IFRS for SMEs. It covers different categories of accounts that are commonly found in financial reporting. While the account ranges and specific names may vary depending on the company and reporting requirements, the general structure remains similar.

The suggested outline includes:

1. Asset accounts (1000 - 1999): Accounts representing various types of assets owned or controlled by the business, such as cash, receivables, inventory, and fixed assets. They include cash, short-term investments, accounts receivable, inventory, prepaid expenses, property, plant, and equipment, intangible assets, investments, and other assets.

2. Liability accounts (2000 - 2999): Accounts representing the financial obligations or debts of the business to external parties, including payables, borrowings, and accrued liabilities. They include accounts payable, accrued expenses, short-term borrowings, long-term borrowings, deferred revenue, and other current and long-term liabilities.
3. Equity accounts (3000 - 3999): Accounts representing the equity portion of the company's capital structure, depending on the type of business ownership (sole proprietorship, partnership, corporation, LLC). For a sole proprietorship, they typically include owner's capital, owner's drawings, and retained earnings. In a partnership, they include partner's capital accounts, partner's drawings, partner's profit and loss allocation, and retained earnings. In a corporation, they include common stock, preferred stock, additional paid-in capital, retained earnings, and treasury stock. In a limited liability company (LLC), they include member's capital accounts, member's drawings, member's profit and loss allocation, and retained earnings.
4. Revenue accounts (4000 - 4999): Accounts representing the income or revenue generated by the company's primary business activities. They include operating revenue, which is directly related to the core operations, and other revenue, which includes income from sources incidental or peripheral to the main operations.
5. Cost of Goods Sold (COGS) accounts (5000 - 5999): Accounts reflecting the direct costs associated with producing or acquiring the goods or services sold by the company. The specific account names may vary, such as Cost of Sales (COS) or Cost of Services Rendered (SOSR), depending on the nature of the business.
6. Expense accounts (6000 - 7999): Accounts representing the operating expenses incurred by the business in its day-to-day operations. They include wages, rent, utilities, materials, and other expenses directly related to the revenue-generating activities.
7. Non-operating revenue accounts (8000 - 8999): Accounts recording income or revenue generated by the business that is not directly related to its core operations. It includes sources of income that are incidental, peripheral, or non-recurring in nature.
8. Non-operating expenses accounts (9000 - 9999): Accounts reflecting expenses incurred by the business that are not directly related to its core operations. They typically arise from activities outside the normal operations and are separate from operating expenses.

This summary is a general outline of the typical accounts found within each range.

Structure - Sequences of Accounts

It's important to customize and adjust this chart of accounts and reporting framework to suit your business's specific requirements and comply with the relevant reporting standards, tax regulations, and

accounting frameworks in your jurisdiction and country. Factors such as your business ownership type, industry, and other specific needs should be considered when adapting the chart of accounts and reporting framework to ensure accurate and relevant financial reporting for your business.

The organization of accounts, including expense accounts, in a financial chart of accounts can vary widely from one organization to another. While there is no universal rule that dictates the order of account names in an alphabetical sequence, it's essential to structure the chart of accounts in a way that makes sense for the specific needs of your organization and facilitates financial reporting.

Common approaches to organizing expense accounts in a chart of accounts include:

1. Numerical Sequence: Some organizations prefer to assign account codes or numbers sequentially, making it easier to manage and reference accounts systematically. This approach doesn't necessarily require alphabetical order.
2. Alphabetical Order: You can choose to list account names in alphabetical order. This can be helpful for quickly locating specific accounts and may align well with the alphabetical arrangement of income statement categories like "Salaries and Wages," "Amortization," "Depreciation," and "Professional Fees."
3. Functional or Grouping Approach: Many organizations group accounts based on their function or type. For example, you might have a group for all personnel-related expenses, a group for depreciation and amortization, a group for professional fees, and so on. Within each group, you can choose to order accounts alphabetically or based on their importance or frequency of use.
4. Customized for Specific Needs: Some organizations customize their chart of accounts to align with their unique business operations or industry requirements. This may result in a hybrid approach that combines numerical sequencing, alphabetical ordering, and functional grouping.

Ultimately, the goal of structuring a chart of accounts is to make financial reporting, analysis, and decision-making more efficient and meaningful for your organization. You should choose an approach that suits your organization's specific needs, accounting practices, and reporting requirements. The key is to maintain consistency and clarity so that financial information can be easily understood and utilized.

Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

List of Accounts - Assets

What is a brief description of Assets and how is it classified?

Assets are economic resources owned or controlled by an individual, organization, or entity that have the

potential to provide future economic benefits. They represent items of value that can be used to generate revenue, reduce liabilities, or contribute to the organization's overall financial well-being. Assets play a crucial role in the financial health and performance of any entity, as they form the basis for its operations and growth.

Assets can be classified into two main categories based on their nature and expected holding period:

1. Current Assets: Current assets are short-term assets that are expected to be converted into cash or used up within one operating cycle, typically one year. These assets are crucial for the day-to-day operations of the business and include:
    - Cash and Cash Equivalents: Physical currency, cash in bank accounts, and highly liquid investments with maturities of three months or less.
    - Accounts Receivable: Amounts owed to the organization by customers or clients for goods or services provided on credit.
    - Inventory: Represents the value of goods held for resale or raw materials used in production.
    - Prepaid Expenses: Represents advance payments made for goods or services that will be received in the future.
    - Short-Term Investments: Investments with maturities beyond three months but less than one year.
2. Non-Current (or Long-Term) Assets: Non-current assets are long-term assets that are expected to provide economic benefits for more than one operating cycle, usually beyond one year. These assets are essential for the organization's strategic growth and include:
    - Property, Plant, and Equipment (PP&E): Tangible assets like land, buildings, machinery, and vehicles used in the organization's operations.
    - Intangible Assets: Non-physical assets with long-term value, such as patents, copyrights, trademarks, and goodwill.
    - Investments: Long-term investments in other companies, subsidiaries, or joint ventures.
    - Long-Term Receivables: Amounts owed to the organization with a longer-term repayment schedule.
    - Deferred Tax Assets: Tax benefits expected to be realized in future tax periods.

Asset classification is vital for financial reporting and analysis, as it provides insights into the organization's liquidity, solvency, and overall financial position. Properly managing and utilizing assets is essential for achieving financial goals and sustaining long-term success.

List of accounts in charts of accounts for assets?

Here's an alphabetical list of common asset accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Accounts Receivable: Amounts owed to the organization by customers or clients for goods or services provided on credit.
2. Cash: Represents the physical cash held by the organization, including cash in hand and cash in bank accounts.
3. Marketable Securities: Investments in financial instruments that can be easily bought, sold, or traded in the financial markets.
4. Inventory: Represents the value of goods held for resale or raw materials used in production.
5. Prepaid Expenses: Represents advance payments made for goods or services that will be received in the future.
6. Fixed Assets: Tangible assets with a long-term useful life, such as land, buildings, machinery, and equipment.
7. Accumulated Depreciation: Represents the cumulative depreciation of fixed assets over their useful life.
8. Intangible Assets: Non-physical assets with long-term value, such as patents, trademarks, copyrights, and goodwill.
9. Investments: Long-term investments in other companies or entities.
10. Loans Receivable: Amounts lent to other parties, typically with a longer-term repayment schedule.
11. Notes Receivable: Promissory notes or written promises to pay a specific amount on a specified date.
12. Petty Cash: Represents a small amount of cash set aside for minor expenses.
13. Prepaid Rent: Represents rent payments made in advance for future periods.
14. Supplies: Represents the value of office or operational supplies held by the organization.
15. Work in Progress: Represents the value of partially completed projects or production processes.
16. Land: The cost of land owned by the organization for operational or investment purposes.
17. Buildings: The cost of buildings owned by the organization for operational or investment purposes.
18. Equipment: The cost of equipment, such as machinery and tools, used in the organization's operations.

19. Vehicles: The cost of vehicles owned by the organization for business purposes.
20. Goodwill: Represents the excess of the purchase price of an acquired business over the fair value of its net assets.

Please note that this list is not exhaustive, and the specific accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. Additionally, some organizations may have more specific asset accounts tailored to their unique needs and operations. The chart of accounts should be structured to provide clear and accurate information for financial reporting and decision-making.

B1000000	*Petty cash*	*CURRENT ASSETS@CASH AND CASH EQUIVALENTS*	*CASH AND CASH EQUIVALENTS*
G1110000	*Provision for doubtful debts*	*CURRENT ASSETS@CURRENT RECEIVABLES*	*CURRENT ASSETS*
G1200000	*Stock / Inventory*	*CURRENT ASSETS@INVENTORIES*	*CURRENT ASSETS*
G1300000	*Accrued revenue / Outstanding revenue*	*CURRENT ASSETS@ACCRUED ASSETS*	*CURRENT ASSETS*
G1510000	*Furniture & Fittings*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1510010	*Furniture & Fittings at cost*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1510020	*Accumulated depreciation - Furniture &*	*NON-CURRENT ASSETS@PP&E -*	*PP&E -*

	Fittings	*PROPERTY, PLANT, AND EQUIPMENT*	*PROPERTY, PLANT, AND EQUIPMENT*
G1520000	*Equipment*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1520010	*Equipment at cost*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1520020	*Accumulated depreciation - Equipment*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1530000	*Computer equipment*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1530010	*Computer equipment at cost*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY,*

			PLANT, AND EQUIPMENT
G1530020	Accumulated depreciation - Computer equipment	NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT	PP&E - PROPERTY, PLANT, AND EQUIPMENT
G1540000	Vehicles	NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT	PP&E - PROPERTY, PLANT, AND EQUIPMENT
G1540010	Vehicles at cost	NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT	PP&E - PROPERTY, PLANT, AND EQUIPMENT
G1540020	Accumulated depreciation - Vehicles	NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT	PP&E - PROPERTY, PLANT, AND EQUIPMENT
G1600000	Land and Buildings	NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT	PP&E - PROPERTY, PLANT, AND

			EQUIPMENT
G1600010	*Land and Buildings at cost*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1600020	*Land and Buildings - Improvements*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1600030	*Amortisation - Land and Buildings*	*NON-CURRENT ASSETS@PP&E - PROPERTY, PLANT, AND EQUIPMENT*	*PP&E - PROPERTY, PLANT, AND EQUIPMENT*
G1700000	*Long-term - Deposits*	*NON-CURRENT ASSETS@LONG-TERM INVESTMENTS*	*NON-CURRENT ASSETS*
G1900000	*Copyrights*	*NON-CURRENT ASSETS@INTANGIBLE ASSETS*	*INTANGIBLE ASSETS*
G1910000	*Goodwill*	*NON-CURRENT ASSETS@INTANGIBLE ASSETS*	*INTANGIBLE ASSETS*
G1920000	*Patents*	*NON-CURRENT ASSETS@INTANGIBLE ASSETS*	*INTANGIBLE ASSETS*

G1930000	*Trademarks & Brands*	*NON-CURRENT ASSETS@INTANGIBLE ASSETS*	*INTANGIBLE ASSETS*

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

What is a brief description of Fixed Assets and how is it classified?

Fixed assets, also known as long-term assets or non-current assets, are tangible or intangible assets that a company holds for long-term use in its business operations rather than for sale. These assets are not intended for conversion into cash or consumption within one operating cycle, and their useful life typically extends beyond one year.

Brief Description of Fixed Assets:

Fixed assets can take various forms and play a crucial role in a company's operations. Some common types of fixed assets include:

1. Tangible Fixed Assets: These are physical assets that have a tangible form. Examples include:
    - Property, Plant, and Equipment (PP&E): Includes land, buildings, machinery, vehicles, and equipment used in the production and delivery of goods and services.
    - Furniture and Fixtures: Includes office furniture, fixtures, and fittings used in the workplace.
    - Computer Hardware: Includes desktops, laptops, servers, and other computer equipment used in the company's operations.
2. Intangible Fixed Assets: These are non-physical assets that lack a physical form but have long-term value to the company. Examples include:
    - Intellectual Property: Includes patents, copyrights, trademarks, and trade secrets that grant the company exclusive rights to its creations or innovations.
    - Goodwill: Represents the excess of the purchase price over the fair value of net assets acquired in a business combination.

Classification of Fixed Assets:

Fixed assets are classified based on their nature and use. They are typically grouped into the following categories:

1. Tangible Fixed Assets: This category includes all physical assets, such as property, plant, equipment, and vehicles.
2. Intangible Fixed Assets: This category includes non-physical assets, such as intellectual property, goodwill, and software.

Fixed assets are recorded on the company's balance sheet under the non-current assets section. They are reported at historical cost less accumulated depreciation (for tangible assets) or amortization (for intangible assets). Depreciation and amortization are used to allocate the cost of fixed assets over their estimated useful lives to reflect their gradual consumption or obsolescence.

Properly managing fixed assets is crucial for companies to ensure they can effectively conduct their business operations, maintain competitiveness, and generate future revenue. Additionally, keeping accurate records of fixed assets helps in financial reporting, taxation, and decision-making processes.

List of accounts in charts of accounts for plant, property and equipment

Here's an alphabetical list of common plant, property, and equipment (PP&E) accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Accumulated Depreciation - Buildings: Represents the cumulative depreciation of buildings over their useful life.
2. Accumulated Depreciation - Equipment: Represents the cumulative depreciation of equipment over its useful life.
3. Accumulated Depreciation - Vehicles: Represents the cumulative depreciation of vehicles over their useful life.
4. Buildings: Represents the cost of buildings owned by the organization for operational or investment purposes.
5. Equipment: Represents the cost of equipment, such as machinery and tools, used in the organization's operations.
6. Land: The cost of land owned by the organization for operational or investment purposes.
7. Leasehold Improvements: Represents the cost of improvements made to leased property.

8. Vehicles: The cost of vehicles owned by the organization for business purposes.

Please note that the specific PP&E accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. Additionally, the chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis. Proper accounting of PP&E is essential for assessing an organization's capital investments and determining the depreciation expense, which impacts the income statement and overall financial health.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

List of Accounts - Current Assets

What is a brief description of Current Assets and how is it classified?

Current assets are a category of assets on a company's balance sheet that are expected to be converted into cash or used up within one operating cycle or one year, whichever is longer. These assets are vital for the day-to-day operations of the business and provide liquidity and flexibility in meeting short-term obligations and expenses.

Brief Description of Current Assets:

Current assets typically include the following types of assets:

1. Cash and Cash Equivalents: This includes physical cash, balances in bank accounts, and highly liquid investments with a maturity of three months or less.
2. Accounts Receivable: Represents amounts owed to the company by customers or clients for goods or services provided on credit.
3. Inventory: Represents the value of goods held for resale or raw materials used in the production process.
4. Prepaid Expenses: Represents payments made in advance for goods or services that will be received in the future.
5. Short-Term Investments: Includes investments with maturities beyond three months but less than one year.

Classification of Current Assets:

Current assets are typically classified in the order of their liquidity, with the most liquid assets listed first. The specific order may vary between companies and accounting practices, but a common classification is as follows:

1. Cash and Cash Equivalents: This is the most liquid asset and is always listed first.
2. Short-Term Investments: These are investments that are relatively liquid and close to their maturity date.
3. Accounts Receivable: Represents the amounts to be collected from customers, arranged in order of their expected collection.
4. Inventory: Represents the value of goods held for sale, categorized based on the stage of completion or saleability.
5. Prepaid Expenses: Represents payments made in advance for goods or services, which will be consumed within one year.

Current assets provide insights into a company's short-term liquidity, its ability to meet short-term obligations, and its operational efficiency. They are essential for the smooth functioning of the business and play a crucial role in managing cash flow and working capital. Analysing the composition and trends of current assets helps investors, creditors, and management assess the company's financial health and short-term financial strength.

List of accounts in charts of accounts for current assets?

Here's an alphabetical list of common current asset accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Accounts Receivable: Amounts owed to the organization by customers or clients for goods or services provided on credit.
2. Cash and Cash Equivalents: Represents the physical cash held by the organization and highly liquid investments with maturities of three months or less.
3. Inventory: Represents the value of goods held for resale or raw materials used in production.
4. Marketable Securities: Investments in financial instruments that can be easily bought, sold, or traded in the financial markets.
5. Notes Receivable: Represents promissory notes or written promises to pay a specific amount on a specified date.

6. Prepaid Expenses: Represents advance payments made for goods or services that will be received in the future.
7. Short-Term Investments: Represents investments with maturities beyond three months but less than one year.
8. Supplies: Represents the value of office or operational supplies held by the organization.

Please note that the specific current asset accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. Additionally, the chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis. Current assets are important indicators of an organization's liquidity and operational efficiency and are crucial for short-term financial decision-making.

Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-Use Tool

List of Accounts - Intangible Assets

What is a brief description of Intangible Assets and how is it classified?

Intangible assets are assets that lack physical substance but have identifiable value and long-term utility to a company. These assets represent non-physical resources or rights that provide future economic benefits to the business. Unlike tangible assets, intangible assets cannot be seen or touched, but they contribute to the company's competitive advantage, revenue generation, and overall value.

Brief Description of Intangible Assets:

Intangible assets can take various forms and play a crucial role in a company's operations and success. Some common types of intangible assets include:

1. Intellectual Property (IP): This includes patents, copyrights, trademarks, and trade secrets that grant the company exclusive rights to its inventions, creations, brands, or proprietary knowledge.
2. Goodwill: Represents the excess of the purchase price of a business acquisition over the fair value of its identifiable net assets. It arises from factors such as customer loyalty, brand reputation, and the company's overall reputation.
3. Software: Represents the value of purchased or internally developed software applications and

computer programs.

4. Licenses and Franchises: Represents the rights to use certain intellectual property or business methods granted by a licensor or franchisor.
5. Customer Lists and Relationships: Represents the value derived from established customer relationships, client lists, or customer databases.

Classification of Intangible Assets:

Intangible assets are typically classified into two main categories based on their nature and how they are acquired:

1. Purchased Intangible Assets: These are intangible assets acquired through a purchase or acquisition. They are recorded at their historical cost, including any acquisition costs, and are subject to amortization over their estimated useful life.
2. Internally-Generated Intangible Assets: These are intangible assets developed or created by the company internally. Generally, internally-generated intangible assets are expensed as incurred and not capitalized, except in certain specific circumstances where specific accounting criteria are met.

Intangible assets are reported on the company's balance sheet under the non-current assets section. They are listed after tangible assets, such as property, plant, and equipment. Like tangible assets, intangible assets are subject to periodic impairment assessments to ensure their carrying value is not overstated and to adjust their value based on their actual performance and economic benefits.

Properly identifying, valuing, and managing intangible assets are crucial for companies to protect their intellectual property, build brand value, and maintain a competitive edge in the market. Intangible assets can significantly contribute to a company's long-term success and financial performance.

List of accounts in charts of accounts for intangible assets?

Here's an alphabetical list of common intangible asset accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Copyrights: Represents exclusive rights granted to authors or creators of original works.
2. Franchise Rights: Represents the rights granted to franchisees to operate under a franchisor's brand and business model.
3. Goodwill: Represents the excess of the purchase price of an acquired business over the fair value of its net assets.
4. Intellectual Property: Represents the collective value of patents, copyrights, trademarks, and trade secrets owned by the organization.

5. Licenses: Represents permissions granted by an authority to carry out specific activities or use specific resources.
6. Patents: Represents exclusive rights granted to inventors for their inventions.
7. Software: Represents the cost of acquiring or developing computer software for internal use.
8. Trademarks and Trade Names: Represents distinctive symbols, names, or logos associated with the organization's brand.

Please note that the specific intangible asset accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. Additionally, the chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis. Intangible assets can play a significant role in an organization's value, and proper accounting and reporting of these assets are essential for financial decision-making.

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

List of Accounts - Liabilities

What is a brief description of Liabilities and how is it classified?

Liabilities are financial obligations or debts that a business or organization owes to external parties. They represent the claims on the organization's assets by creditors and other stakeholders. Liabilities arise from past transactions or events, and the organization has an obligation to settle these debts in the future, either by providing goods or services or by making cash payments.

Brief Description of Liabilities:

Liabilities can take various forms and represent different types of obligations. Some common types of liabilities include:

1. Accounts Payable: Amounts owed to suppliers or vendors for goods or services purchased on credit.
2. Notes Payable: Formal written promises to repay borrowed funds on specified terms.
3. Loans and Borrowings: Represents amounts borrowed from financial institutions or lenders.
4. Accrued Liabilities: Expenses incurred but not yet paid, such as salaries, taxes, or utilities.
5. Deferred Revenue: Represents cash received from customers for goods or services not yet delivered or rendered.

6. Long-Term Debt: Debts or obligations that are due beyond one year.
7. Contingent Liabilities: Potential liabilities that may arise from uncertain events, such as pending lawsuits or warranties.

Classification of Liabilities:

Liabilities are classified based on their maturity and the timeline for settlement. They are typically grouped into two main categories:

1. Current Liabilities: These are obligations that are expected to be settled within one operating cycle or one year, whichever is longer. Current liabilities represent short-term debts that the organization will pay off in the near future. Common examples include accounts payable, accrued liabilities, and short-term loans.
2. Non-Current (or Long-Term) Liabilities: These are obligations that are due beyond one year or the operating cycle. Non-current liabilities represent long-term debts that the organization will settle over an extended period. Common examples include long-term loans, bonds, and deferred tax liabilities.

Proper classification of liabilities is essential for financial reporting and analysis, as it helps stakeholders understand the organization's debt obligations, liquidity, and financial health. By monitoring and managing liabilities effectively, organizations can ensure they meet their financial commitments and maintain a stable financial position.

List of accounts in charts of accounts for liabilities?

Here's an alphabetical list of common liability accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Accounts Payable: Amounts owed to vendors or suppliers for goods or services received but not yet paid.
2. Accrued Liabilities: Represents expenses incurred but not yet paid or recorded, such as accrued salaries or accrued interest.
3. Bank Loans Payable: Represents long-term loans from financial institutions or banks.
4. Bonds Payable: Represents long-term debt securities issued by the organization.
5. Customer Deposits: Represents advance payments received from customers for goods or services to be delivered in the future.
6. Deferred Revenue: Represents payments received in advance for goods or services not yet provided.
7. Income Tax Payable: Represents taxes owed to tax authorities based on taxable income.

8. Interest Payable: Represents interest owed on outstanding loans or debt.
9. Long-Term Debt: Represents long-term loans or debt obligations with maturities beyond one year.
10. Notes Payable: Represents promissory notes or written promises to pay a specific amount on a specified date.
11. Payroll Liabilities: Represents amounts withheld from employee salaries for taxes, benefits, and other deductions.
12. Sales Tax Payable: Represents taxes collected from customers on behalf of taxing authorities.
13. Short-Term Debt: Represents short-term loans or debt obligations with maturities within one year.
14. Unearned Revenue: Represents payments received in advance for goods or services not yet provided.
15. Warranty Liabilities: Represents the estimated future cost of fulfilling warranty obligations for products sold.

Please note that this list is not exhaustive, and the specific liability accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. Additionally, some organizations may have more specific liability accounts tailored to their unique needs and operations. The chart of accounts should be structured to provide clear and accurate information for financial reporting and decision-making.

G2100000	*Accrued expenses / Outstanding expenses*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2200000	*Accued Salaries and Wages*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2300000	*SALARIES AND WAGES CONTROL*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300010	*Employee Salaries Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300020	*PAYE Income Tax Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300030	*Health Insurance Premiums*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*

G2300040	National Insurance Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300050	Pension Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300060	Employee Loans and Advances	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300070	Other Payroll Deductions Payable (Unions / garnishee orders)	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400000	VAT-CONTROL ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400500	VAT PAYMENTS ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G8010000	Investment income	No group	NON-OPERATING REVENUE
G2500000	Long-term loans	NON-CURRENT LIABILITIES	NON-CURRENT LIABILITIES

G2150000	Deferred revenue / Unearned revenue	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2450000	Suspense account	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES

- Liability accounts (2000 - 2999): Liabilities are obligations or debts that a business or individual owes to external parties. They represent the claims or obligations that others have on the assets of the entity. In accounting, liabilities are recorded on the balance sheet and reflect the financial obligations that need to be fulfilled in the future.

  The range of accounts from 2000 to 2999 typically represents liability accounts in the chart of accounts.

These accounts capture the various types of financial obligations or debts that a business owes to external parties. Here is a concise summary of common liability accounts within this range:

1. Accounts Payable (2000-2099): This account represents the amount owed to suppliers or vendors for goods or services received on credit. It includes unpaid invoices and bills that are due to be paid.
2. Accrued Expenses (2100-2199): These are expenses that have been incurred but not yet paid or recorded in the accounting system. They include accrued wages, accrued interest, and accrued utilities.
3. Short-term Borrowings (2200-2299): This account captures short-term loans or borrowings that are due within one year or the normal operating cycle of the business. It includes bank loans, lines of credit, and short-term notes payable.
4. Long-term Borrowings (2300-2399): This account represents long-term loans or borrowings that extend beyond the next year. It includes long-term bank loans, bonds payable, and other long-term debt obligations.
5. Deferred Revenue (2400-2499): Also known as unearned revenue, this account records the amount received in advance from customers for goods or services that are yet to be delivered. It represents an obligation to provide the products or services in the future.
6. Other Current Liabilities (2500-2599): This category includes various short-term financial obligations that do not fit into specific accounts mentioned above. It may include items such as accrued taxes, customer deposits, and other short-term liabilities.
7. Other Long-term Liabilities (2600-2699): Similar to other current liabilities, this category captures long-term financial obligations that are not classified under specific accounts. It may include items such as deferred tax liabilities, long-term customer deposits, and other long-term liabilities.

These are just a few examples of common liability accounts within the 2000-2999 range. The specific accounts and their numbering may vary depending on the organization's chart of accounts and industry-specific requirements.

G2100000	*Accrued expenses / Outstanding expenses*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2200000	*Accued Salaries and Wages*	*CURRENT LIABILITIES@ACCRUED*	*CURRENT LIABILITIES*

		LIABILITIES	
G2300000	*SALARIES AND WAGES CONTROL*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300010	*Employee Salaries Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300020	*PAYE Income Tax Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300030	*Health Insurance Premiums*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300040	*National Insurance Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300050	*Pension Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300060	*Employee Loans and Advances*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300070	*Other Payroll Deductions Payable (Unions / garnishee orders)*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2400000	*VAT-CONTROL ACCOUNT*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2400500	*VAT PAYMENTS ACCOUNT*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G8010000	*Investment income*	*No group*	*NON-OPERATING REVENUE*
G2500000	*Long-term loans*	*NON-CURRENT LIABILITIES*	*NON-CURRENT LIABILITIES*

G2100000	*Accrued expenses / Outstanding expenses*	*CURRENT*	*CURRENT*

		LIABILITIES@ACCRUED LIABILITIES	LIABILITIES
G2200000	Accued Salaries and Wages	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2300000	SALARIES AND WAGES CONTROL	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300010	Employee Salaries Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300020	PAYE Income Tax Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300030	Health Insurance Premiums	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300040	National Insurance Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300050	Pension Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300060	Employee Loans and Advances	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300070	Other Payroll Deductions Payable (Unions / garnishee orders)	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400000	VAT-CONTROL ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400500	VAT PAYMENTS ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G8010000	Investment income	No group	NON-OPERATING REVENUE
G2500000	Long-term loans	NON-CURRENT LIABILITIES	NON-CURRENT

			LIABILITIES

G2100000	*Accrued expenses / Outstanding expenses*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2200000	*Accued Salaries and Wages*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2300000	*SALARIES AND WAGES CONTROL*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300010	*Employee Salaries Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300020	*PAYE Income Tax Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300030	*Health Insurance Premiums*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300040	*National Insurance Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300050	*Pension Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300060	*Employee Loans and Advances*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300070	*Other Payroll Deductions Payable (Unions / garnishee orders)*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2400000	*VAT-CONTROL ACCOUNT*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2400500	*VAT PAYMENTS ACCOUNT*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G8010000	*Investment income*	*No group*	*NON-*

			OPERATING REVENUE
G2500000	*Long-term loans*	*NON-CURRENT LIABILITIES*	*NON-CURRENT LIABILITIES*

G2100000	*Accrued expenses / Outstanding expenses*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2200000	*Accued Salaries and Wages*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2300000	*SALARIES AND WAGES CONTROL*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300010	*Employee Salaries Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300020	*PAYE Income Tax Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300030	*Health Insurance Premiums*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300040	*National Insurance Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300050	*Pension Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300060	*Employee Loans and Advances*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300070	*Other Payroll Deductions Payable (Unions / garnishee orders)*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2400000	*VAT-CONTROL ACCOUNT*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*

G2400500	VAT PAYMENTS ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G8010000	Investment income	No group	NON-OPERATING REVENUE
G2500000	Long-term loans	NON-CURRENT LIABILITIES	NON-CURRENT LIABILITIES

G2100000	Accrued expenses / Outstanding expenses	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2200000	Accued Salaries and Wages	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2300000	SALARIES AND WAGES CONTROL	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300010	Employee Salaries Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300020	PAYE Income Tax Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300030	Health Insurance Premiums	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300040	National Insurance Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300050	Pension Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300060	Employee Loans and Advances	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300070	Other Payroll Deductions Payable (Unions /	CURRENT LIABILITIES@OTHER	CURRENT

	garnishee orders)	*CURRENT LIABILITIES*	*LIABILITIES*
G2400000	*VAT-CONTROL ACCOUNT*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2400500	*VAT PAYMENTS ACCOUNT*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G8010000	*Investment income*	*No group*	*NON-OPERATING REVENUE*
G2500000	*Long-term loans*	*NON-CURRENT LIABILITIES*	*NON-CURRENT LIABILITIES*

G2100000	*Accrued expenses / Outstanding expenses*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2200000	*Accued Salaries and Wages*	*CURRENT LIABILITIES@ACCRUED LIABILITIES*	*CURRENT LIABILITIES*
G2300000	*SALARIES AND WAGES CONTROL*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300010	*Employee Salaries Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300020	*PAYE Income Tax Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300030	*Health Insurance Premiums*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300040	*National Insurance Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G2300050	*Pension Contributions Payable*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*

G2300060	Employee Loans and Advances	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300070	Other Payroll Deductions Payable (Unions / garnishee orders)	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400000	VAT-CONTROL ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400500	VAT PAYMENTS ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G8010000	Investment income	No group	NON-OPERATING REVENUE
G2500000	Long-term loans	NON-CURRENT LIABILITIES	NON-CURRENT LIABILITIES

G2100000	Accrued expenses / Outstanding expenses	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2200000	Accrued Salaries and Wages	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2300000	SALARIES AND WAGES CONTROL	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300010	Employee Salaries Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300020	PAYE Income Tax Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300030	Health Insurance Premiums	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300040	National Insurance Contributions Payable	CURRENT LIABILITIES@OTHER	CURRENT

		CURRENT LIABILITIES	LIABILITIES
G2300050	Pension Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300060	Employee Loans and Advances	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300070	Other Payroll Deductions Payable (Unions / garnishee orders)	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400000	VAT-CONTROL ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400500	VAT PAYMENTS ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G8010000	Investment income	No group	NON-OPERATING REVENUE
G2500000	Long-term loans	NON-CURRENT LIABILITIES	NON-CURRENT LIABILITIES

G2100000	Accrued expenses / Outstanding expenses	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2200000	Accued Salaries and Wages	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2300000	SALARIES AND WAGES CONTROL	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300010	Employee Salaries Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300020	PAYE Income Tax Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES

G2300030	Health Insurance Premiums	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300040	National Insurance Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300050	Pension Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300060	Employee Loans and Advances	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300070	Other Payroll Deductions Payable (Unions / garnishee orders)	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400000	VAT-CONTROL ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400500	VAT PAYMENTS ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G8010000	Investment income	No group	NON-OPERATING REVENUE
G2500000	Long-term loans	NON-CURRENT LIABILITIES	NON-CURRENT LIABILITIES

G2100000	Accrued expenses / Outstanding expenses	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2200000	Accued Salaries and Wages	CURRENT LIABILITIES@ACCRUED LIABILITIES	CURRENT LIABILITIES
G2300000	SALARIES AND WAGES CONTROL	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300010	Employee Salaries Payable	CURRENT LIABILITIES@OTHER	CURRENT

		CURRENT LIABILITIES	LIABILITIES
G2300020	PAYE Income Tax Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300030	Health Insurance Premiums	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300040	National Insurance Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300050	Pension Contributions Payable	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300060	Employee Loans and Advances	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2300070	Other Payroll Deductions Payable (Unions / garnishee orders)	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400000	VAT-CONTROL ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G2400500	VAT PAYMENTS ACCOUNT	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G8010000	Investment income	No group	NON-OPERATING REVENUE
G2500000	Long-term loans	NON-CURRENT LIABILITIES	NON-CURRENT LIABILITIES

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's Project Analyzer

List of Accounts - Equity / Capital

What is equity or capital?

Equity, also referred to as capital or owner's equity, represents the residual interest in an organization's assets after deducting its liabilities. In simple terms, it is the portion of the organization's value that belongs to its owners or shareholders. Equity reflects the ownership stake of the shareholders in the company and represents the total value of assets that are financed by the owners' contributions and retained earnings.

Equity can be calculated using the following formula:

```
Equity = Total Assets - Total Liabilities
```

The components of equity include:

1. Paid-In Capital: Also known as contributed capital, it represents the amount of capital contributed by shareholders through the issuance of common and preferred shares.
2. Retained Earnings: This portion of equity comprises the accumulated profits or losses retained in the company over time after deducting dividends paid to shareholders.
3. Treasury Stock: Represents shares of the company's own stock that have been repurchased and are held by the company itself.
4. Other Comprehensive Income: Includes gains and losses from certain financial instruments that are not recognized in the income statement but are included in equity.

Equity is a crucial element in the balance sheet of an organization and provides insight into the owners' claims on the company's assets. It serves as a measure of the company's financial health and solvency, indicating how much of its assets are funded by investors rather than borrowed funds. Additionally, equity serves as a source of funding for future business activities and investments. As the company grows and generates profits, retained earnings increase, contributing to the growth of equity and shareholder value.

In which countries is Equity used and in which countries is Capital used?

The terms "*equity*" and "*capital*" are used interchangeably in many countries to refer to the ownership interest or ownership stake in a company. Both terms essentially represent the same concept of the residual interest in the assets of an entity after deducting liabilities. They signify the total value that belongs to the owners or shareholders.

The usage of "*equity*" and "*capital*" can vary based on regional language, business practices, and legal terminology. However, in the context of business and finance, both terms are widely recognized and used

across various countries.

1. Equity: The term "*equity*" is commonly used in the United States, Canada, the United Kingdom, and many other countries around the world. It is widely used in accounting, finance, and corporate governance to refer to the ownership interest of shareholders in a company.
2. Capital: The term "*capital*" is also widely used across the world to refer to the funds contributed by shareholders to start or operate a business. It can be used interchangeably with "*equity*" to represent the financial interest of the owners in a company.

In summary, both "*equity*" and "*capital*" are widely used and recognized terms to describe ownership interests in companies, and they are used interchangeably in many countries. The specific usage of these terms may vary based on regional language and business practices, but their underlying meaning remains the same.

In which countries does Stock apply and in which countries does Shares apply?

The terms "*stock*" and "*shares*" are used interchangeably in many countries to refer to ownership interests in a company. However, there are some regional differences in how these terms are commonly used. It's important to note that the usage of these terms may vary, and the legal and accounting definitions can differ from colloquial usage.

In general, "*stock*" is a term more commonly used in the United States and Canada, while "*shares*" is a term more commonly used in the United Kingdom and other Commonwealth countries.

1. Stock (United States and Canada): In the United States and Canada, the term "stock" is often used to refer to ownership interests in a corporation. For example, a company's ownership may be divided into common stock and preferred stock. Common stock represents ownership with voting rights, while preferred stock typically represents ownership with preferential treatment in terms of dividends and other benefits. The total value of a company's outstanding stock is often referred to as its "market capitalization."
2. Shares (United Kingdom and Commonwealth Countries) : In the United Kingdom and other Commonwealth countries, the term "shares" is commonly used to refer to ownership interests in a company. For example, a company may issue ordinary shares or preference shares. Ordinary shares typically carry voting rights and are the most common type of shares issued. Preference shares, similar to preferred stock in the United States, may have preferential rights to dividends and assets in case of liquidation.

Despite these regional differences in common usage, both terms essentially refer to the same concept of ownership in a company. The legal definitions and regulations related to ownership interests in

corporations are generally similar across countries, but the specific terminology may vary. Companies and investors should be aware of the local legal and regulatory requirements related to the issuance and ownership of stock or shares in their respective jurisdictions.

List of accounts in charts of accounts for equity?

Here's an alphabetical list of common equity accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Common Stock: Represents the par value or stated value of shares issued to shareholders.
2. Preferred Stock: Represents shares with preferential rights, such as priority dividends or liquidation preference.
3. Additional Paid-in Capital: Represents the amount received from shareholders in excess of the par value of shares issued.
4. Retained Earnings: Represents accumulated profits or losses retained in the company after dividends and distributions.
5. Treasury Stock: Represents shares of the company's own stock that have been repurchased and held by the company.
6. Stock Dividends Distributable: Represents dividends declared in the form of additional shares to be distributed to shareholders.
7. Accumulated Other Comprehensive Income: Represents unrealized gains and losses from certain financial instruments.
8. Contributed Capital: Represents capital contributions made by shareholders, owners, or partners.
9. Capital Surplus: Represents additional amounts received from shareholders for specific purposes.
10. Deficit: Represents a negative balance in retained earnings due to cumulative net losses.
11. Common Stock Subscribed: Represents shares of common stock that have been promised to be purchased by investors.
12. Donated Capital: Represents contributions of capital from donors or benefactors for specific purposes.
13. Equity Compensation: Represents the value of stock options or other equity-based compensation plans.
14. Opening Balances Equity: Represents the equity balance carried forward from the previous accounting period.

Please note that the specific equity accounts used in a chart of accounts can vary based on the organization's legal structure, reporting requirements, and accounting practices. Additionally, some organizations may have more detailed equity accounts based on their unique equity transactions and ownership arrangements. The chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis.

Stock / Shares - Terminology - Depending on Jurisdictions

The specific accounts used to represent equity can vary depending on the jurisdiction, accounting framework, and accounting standards followed by an organization. Different countries have different legal requirements and reporting standards that may influence the naming and classification of equity accounts in the financial statements.

While the concepts of equity, such as common stock, preferred stock, retained earnings, and treasury stock, are widely recognized and used in accounting, the actual account names and classifications may differ based on regional or legal requirements.

For example, in some jurisdictions, the term "*share capital*" may be used instead of "*common stock*" or "*equity capital*." Similarly, the accounting standards may have specific requirements for the presentation and disclosure of equity-related accounts.

Some other examples of equity-related accounts that may be applicable in certain jurisdictions or accounting frameworks include:

- Share Premium: Represents the amount received by a company from the issuance of shares above their nominal or par value.
- Capital Reserves: Represents funds set aside for specific purposes, such as legal reserves or specific business investments.
- Retained Earnings Appropriated for Legal Reserve: Represents retained earnings allocated for legal reserve requirements.
- Dividends Payable: Represents dividends declared by the company but not yet paid to shareholders.
- Dividends Payable to Non-Controlling Interests: Represents dividends owed to minority shareholders or non-controlling interests in subsidiaries.
- Other Comprehensive Income: Represents items of income and expense that bypass the income statement and are directly recorded in equity.

The specific accounts and their names may also vary depending on the organizational structure, industry, and accounting practices followed by the company.

It's essential for organizations to comply with the applicable accounting standards and legal requirements in their jurisdiction while preparing their financial statements and reporting equity-related transactions accurately.

In the equity section of the balance sheet, the business ownership type will determine the structure of the accounts in the Equity section?

Yes, the business ownership type can influence the structure of accounts in the equity section of the balance sheet. The structure of the equity section may vary depending on whether the business is a sole proprietorship, partnership, or corporation.

1. Sole Proprietorship: In a sole proprietorship, the business is owned and operated by a single individual. The equity section typically includes the following accounts:
    - Owner's Capital: Represents the owner's initial investment in the business and any additional capital contributions made over time.
    - Owner's Drawings: Represents withdrawals or distributions taken by the owner for personal use.

    In a sole proprietorship, the equity section may be relatively straightforward, consisting mainly of the owner's capital and drawings accounts.
2. Partnership: In a partnership, the business is owned and operated by two or more individuals or entities. The equity section may include the following accounts:
    - Partner's Capital Accounts: Separate capital accounts are maintained for each partner, reflecting their initial investments and share of profits or losses.
    - Partner's Drawings: Represents withdrawals or distributions taken by each partner for personal use.

    Partnership equity sections are more complex than sole proprietorships as they need to account for the capital contributions and profit-sharing among multiple partners.
3. Corporation: In a corporation, the business is a separate legal entity owned by shareholders. The equity section of a corporation's balance sheet may include the following accounts:
    - Common Stock: Represents the par value or stated value of the common shares issued to shareholders.
    - Preferred Stock: Represents the par value or stated value of preferred shares issued to

shareholders, if applicable.

- Additional Paid-In Capital: Represents the amount received above the par value when issuing stock.
- Retained Earnings: Represents accumulated profits or losses retained in the company over time.
- Treasury Stock: Represents shares of the company's own stock repurchased and held by the company.

Corporations have more complex equity sections due to the various classes of shares, additional paid-in capital, and the ability to buy back and hold their own stock as treasury stock.

In summary, the ownership structure of the business, whether sole proprietorship, partnership, or corporation, will influence the accounts included in the equity section of the balance sheet to reflect the respective ownership interests and capital contributions of the owners or shareholders.

Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

---

List of accounts in charts of accounts for other revenue?

Here's an alphabetical list of common other revenue accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Gain on Foreign Exchange: Represents gains realized from favourable exchange rate fluctuations when dealing with foreign currencies.
2. Gain on Sale of Assets: Represents gains realized from selling assets, such as property, equipment, or investments.
3. Gain on Sale of Investments: Represents gains realized from selling investments, such as stocks or bonds.
4. Gain on Sale of Subsidiaries: Represents gains realized from selling subsidiary companies.
5. Interest Income: Revenue earned from interest on loans, investments, or bank deposits.
6. Miscellaneous Other Revenue: Revenue from various sources that do not fit into other specific categories.

7. Other Operating Income: Revenue generated from sources other than primary business activities.

Please note that the specific other revenue accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. The chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis.

List of accounts in charts of accounts for operating revenue?

You can group or classify the Operating Revenue accounts into several categories based on their nature and purpose.

You can group or classify operating revenue accounts, closely tied to your core business operations, it's operating income; into several categories based on their nature and purpose. Here are some common categories for operating revenue accounts:

1. Product Sales Revenue: Sales revenue from the sale of physical products your company manufactures or sells.
2. Service Revenue: Revenue generated from providing services to clients or customers.
3. Subscription Revenue: Revenue from subscription-based services or products.
4. Licensing and Royalty Revenue: Income from licensing your intellectual property or collecting royalties.
5. Rental and Leasing Revenue: Income from renting or leasing out assets, such as property or equipment.
6. Advertising Revenue: Revenue generated from advertising services or partnerships.
7. Commission Revenue: Income earned from acting as an intermediary or broker in transactions.
8. Interest and Dividend Income: Revenue from investments in interest-bearing securities or dividends from stock holdings.
    1. Interest from operating bank accounts is typically included in the "Interest and Dividend Income" category if it represents income earned from investments in interest-bearing securities. However, it's important to distinguish between interest income from regular business operations and interest income earned from surplus cash or investments. interest from Operating Bank Accounts (Regular Business Operations): If the interest income is earned as part of your company's regular business operations, such as interest earned on a checking or savings account used for daily cash management, it's considered operating revenue. In this case, it would not be classified as non-operating income.
    2. Interest from Investments (Non-Operating Income) : If the interest income is earned from

investments made with surplus cash or excess funds that are not directly tied to your core business operations, it would be classified as non-operating income. This typically includes interest from investments in certificates of deposit (CDs), bonds, or other interest-bearing securities.

In summary, whether interest income is categorized as operating or non-operating depends on the source and purpose of the funds generating the interest. If the funds are closely tied to your core business operations, it's operating income; if they represent investments or excess cash, it's non-operating income. Always consult with your accounting and finance professionals to ensure proper classification in your financial reporting.

9. Consulting and Professional Services Revenue: Revenue from consulting or professional services provided to clients.
10. Franchise Fees: Income from franchise fees paid by franchisees.
11. Donations and Grants: Revenue received from charitable donations or grants.
12. Royalty Income: Income earned from licensing intellectual property or copyrighted material.
13. Online Sales and E-commerce Revenue: Revenue generated from online sales and e-commerce activities.
14. Government Grants and Contracts: Income received from government grants, contracts, or subsidies.
15. Other Operating Revenue: Miscellaneous operating revenue not covered by the above categories.

These categories should provide a framework for organizing your operating revenue accounts. Depending on your specific business and industry, you may need to create additional categories or subcategories to accurately represent the sources of your operating revenue.

===

Here's an alphabetical list of common operating revenue accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Consulting Revenue: Revenue generated from providing consulting services to clients or customers.
2. Interest Income: Revenue earned from interest on loans, investments, or bank deposits.
3. Membership Dues: Revenue received from individuals or organizations as membership fees.
4. Rental Income: Revenue earned from renting out property, equipment, or assets.
5. Sales Revenue: Revenue generated from the sale of goods or services.
6. Service Revenue: Revenue earned from providing services to clients or customers.

7. Subscriptions Revenue: Revenue received from subscription-based products or services.
8. Royalty Income: Revenue earned from royalties on intellectual property, such as books, music, or patents.
9. Commission Income: Revenue earned as a commission for facilitating sales or transactions.
10. Licensing Fees: Revenue received for granting others the right to use the organization's intellectual property or brand.
11. Advertising Revenue: Revenue earned from advertising services or space.
12. Sponsorship Revenue: Revenue received from sponsors for promoting their products or brands.
13. Freight and Shipping Revenue: Revenue earned from charging customers for shipping or freight services.
14. Gain on Sale of Assets: Represents gains realized from selling assets, such as property, equipment, or investments.
15. Miscellaneous Income: Revenue from various sources that do not fit into other specific categories.

Please note that this list is not exhaustive, and the specific operating revenue accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. Additionally, some organizations may have more detailed revenue accounts based on their specific revenue streams and business activities. The chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis.

===

Non-Operating Revenue Accounts Categories

Can you can group or classify the Non-Operating Revenue accounts into several categories based on their nature and purpose?

Certainly, you can group or classify non-operating revenue accounts into several categories based on their nature and purpose. Non-operating revenue typically includes income or gains that are not directly related to a company's core business activities. Here are some common categories for non-operating revenue accounts:

1. Investment Income:
    - Interest income from investments in bonds, certificates of deposit (CDs), or other interest-bearing securities.
    - Dividend income from investments in stocks and equity securities.

2. Rental Income: Income from renting out properties, equipment, or other assets not used in the company's primary operations.
3. Gain on Sale of Assets: Gains realized from selling non-core assets, such as real estate, equipment, or investments.
4. Insurance Proceeds: Proceeds received from insurance claims, including property damage, liability claims, or business interruption insurance.
5. Settlements and Legal Awards: Income received as a result of legal settlements, judgments, or awards.
6. Foreign Exchange Gains: Gains resulting from favourable foreign exchange rate movements.
7. Other Non-Operating Income: Miscellaneous non-operating income that doesn't fit into the above categories.
8. Discontinued Operations: Revenue generated from operations that have been discontinued or sold.
9. Government Grants (Non-Operating): Grants received from government entities that are not related to the company's core operations.
10. Donations and Gifts (Non-Operating): Non-operating revenue received in the form of charitable donations or gifts.
11. Extraordinary Gains: One-time or extraordinary gains that are unusual and infrequent in nature.
12. Other Income from Non-Operating Activities: Income from non-operating activities or sources not covered by the above categories.

These categories should help you organize your non-operating revenue accounts. Keep in mind that the specific accounts you use may vary depending on your company's unique financial activities and reporting requirements.

List of accounts in charts of accounts for non-operating revenue?

Here's an alphabetical list of common non-operating revenue accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Dividend Income: Revenue earned from dividends received on investments in other companies.
2. Interest Income: Revenue earned from interest on loans, investments, or bank deposits.
3. Gain on Sale of Investments: Represents gains realized from selling investments, such as stocks or bonds.
4. Gain on Sale of Assets: Represents gains realized from selling assets, such as property, equipment,

or investments.

5. Rental Income: Revenue earned from renting out property, equipment, or assets.
6. Royalty Income: Revenue earned from royalties on intellectual property, such as books, music, or patents.
7. Miscellaneous Non-Operating Income: Revenue from various non-operating sources that do not fit into other specific categories.

Please note that the non-operating revenue accounts may not be as extensive as the operating revenue accounts since non-operating revenue typically includes income from occasional or non-core activities. Additionally, the specific non-operating revenue accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. The chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis.

G4000000	*Sales revenue*	*OPERATING REVENUE*	*OPERATING REVENUE*
G4400000	*Interest earned*	*No group*	*OTHER REVENUE*
G4500000	*Sales discounts*	*No group*	*OTHER REVENUE*
G4300000	*Finance charge income*	*No group*	*OTHER REVENUE*

NON-OPERATING REVENUE

G8010000	*Investment income*	*No group*	*NON-OPERATING REVENUE*

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

List of Accounts - Expenses

What is a brief description of Expenses and how is it classified?

Expenses are the costs incurred by a business or organization in its day-to-day operations to generate revenue and maintain its activities. In accounting, expenses are recorded on the income statement and

represent the outflow or consumption of assets (such as cash or goods) to support the production of goods or services.

Brief Description of Expenses:

Expenses include various items that reduce the organization's income and profitability. They can be classified into several categories based on their nature and function. Some common types of expenses include:

1. Cost of Goods Sold (COGS): Represents the direct costs associated with producing goods or services sold by the organization. It includes expenses like raw materials, labour, and manufacturing overhead.
2. Operating Expenses: These are the day-to-day expenses incurred to run the business and include items like salaries, rent, utilities, office supplies, marketing, and administrative expenses.
3. Depreciation and Amortization: These represent the allocation of the cost of long-term assets (tangible and intangible) over their useful life to reflect their gradual consumption or obsolescence.
4. Interest Expense: Represents the cost of borrowing money or interest paid on loans and outstanding debt.
5. Taxes: Includes income taxes and other taxes paid by the organization.
6. Other Expenses: May include one-time or infrequent expenses not categorized under the above headings.

Classification of Expenses:

Expenses are classified based on their relationship to the organization's core operations and their accounting treatment. They are typically grouped in the income statement into the following categories:

- Cost of Goods Sold (COGS): This category includes expenses directly associated with the production of goods or services. It is subtracted from the total revenue to calculate the gross profit.
- Operating Expenses: These expenses are related to the general operations of the business and are further categorized into selling, general, and administrative expenses (SG&A).
- Non-Operating Expenses: These are expenses not directly related to the primary business activities, such as interest expense and income taxes.

The classification of expenses helps in understanding the cost structure of the organization, assessing its profitability, and identifying areas where cost control and efficiency improvements can be made. Proper classification of expenses is essential for accurate financial reporting and analysis.

List of accounts in charts of accounts for operating expenses?

Here's an alphabetical list of common operating expense accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Advertising and Marketing Expenses: Costs incurred for advertising campaigns, marketing materials, and promotional activities.
2. Bad Debt Expense: Represents the estimated portion of accounts receivable that is unlikely to be collected.
3. Cost of Goods Sold (COGS): The direct cost of producing goods or services sold by the organization.
4. Depreciation Expense: Represents the allocation of the cost of tangible assets over their useful life.
5. Employee Benefits Expense: Costs related to employee benefits, such as health insurance, retirement plans, and paid time off.
6. Insurance Expense: Costs incurred for various insurance coverages, such as property insurance, liability insurance, etc.
7. Office Supplies Expense: Costs for office consumables like pens, paper, and other supplies.
8. Payroll Expenses: Includes wages, salaries, and associated costs, such as payroll taxes and benefits.
9. Rent Expense: Costs incurred for renting office space or facilities.
10. Repairs and Maintenance Expenses: Costs for maintaining and repairing equipment, machinery, and facilities.
11. Research and Development (R&D) Expenses: Costs incurred for research and development activities to create new products or improve existing ones.
12. Salaries and Wages: Represents the payroll costs associated with employees' regular working hours.
13. Selling and Distribution Expenses: Costs incurred for selling and distributing goods or services, such as sales commissions and shipping expenses.
14. Travel and Entertainment Expenses: Costs for business travel, meals, and entertainment.
15. Utilities Expense: Costs incurred for electricity, water, gas, and other utilities.
16. Website and Software Expenses: Costs related to website development, hosting, and software licenses.

Please note that this list is not exhaustive, and the specific operating expense accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. Additionally, some organizations may have more detailed expense accounts based on their specific cost structures and

business activities. The chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis.

List of accounts in charts of accounts for non-operating expenses?

Here's an alphabetical list of common non-operating expense accounts that you might find in a chart of accounts, along with brief descriptions of each account:

1. Interest Expense: Expenses incurred from interest on loans, credit lines, or other borrowed funds.
2. Loss on Sale of Investments: Represents losses realized from selling investments, such as stocks or bonds.
3. Loss on Sale of Assets: Represents losses realized from selling assets, such as property, equipment, or investments.
4. Impairment Charges: Expenses recorded when the value of an asset declines significantly and is deemed impaired.
5. Foreign Exchange Losses: Expenses resulting from unfavourable exchange rate fluctuations when dealing with foreign currencies.
6. Legal and Settlement Costs: Expenses related to legal disputes, settlements, or legal advice.
7. Miscellaneous Non-Operating Expenses: Expenses from various non-operating activities that do not fit into other specific categories.

Please note that the non-operating expense accounts may not be as extensive as the operating expense accounts since non-operating expenses typically arise from occasional or one-time events. Additionally, the specific non-operating expense accounts used in a chart of accounts can vary based on the organization's industry, size, and accounting practices. The chart of accounts should be tailored to provide accurate and relevant information for financial reporting and analysis.

How could these accounts for operating expenses be grouped of classified ? =

G6000000 Accounting fees

G6050000 Audit fees

G6100000 Bad debts

G6150000 Bank charges

G6200000 Cleaning services

G6250000 Commissions paid

G6300000 Depreciation

G6350000 Entertainment

G6400000 Finance charges

G6450000 Gifts and donations

G6500000 Insurance premiums

G6550000 Interest paid

G6600000 Legal fees

G6650000 License fees

G6700000 Maintenance G6750000

Marketing and advertising expenses

G6800000 Motor vehicle expenses

G6800010 Fuel and oil

G6800020 Vehicle - Insurance

G6800030 Vehicle - Maintenance and repairs

G6800040 Vehicle - Registration and Licence fees

G6800050 Vehicle - Tolls and parking fees

G6800060 Vehicle - Traffic fines / Vehicle violation expenses

G6850000 Office expenses

G6900000 Printing

G6950000 Professional fees

G7000000 Repairs

G7050000 Rent paid

G7100000 Salaries and wages expenses

G7100010 Basic salaries

G7100020 Basic wages

G7100030 Overtime pay

G7100040 Incentives - Bonuses

G7100050 Incentives - Commissions

G7100100 Allowance - Cellphone

G7100110 Allowance - Housing

G7100120 Allowance - Meals

G7100130 Allowance - Transport

G7100140 Allowance - Uniforms

G7100200 Leave - Annual leave

G7100210 Leave - Sick leave G7100220 Leave - Parental leave

G7100300 Retrenchment Packages

G7100310 Severance Packages

G7100400 Employers contributions - UIF (Unemployment Insurance Fund)

G7100410 Employers contributions - SDL (Skills Development Levy)

G7100420 Employers contributions - Workman's Compensation Fund

G7100430 Employers contributions - Medical Aid

G7100440 Employers contributions - Pension / Retirement Fund

G7100800 Payroll processing fees

G7100810 Payroll software costs

G7100820 Payroll training costs

G7100830 Other payroll expenses

G7150000 Stationery

G7200000 Subscriptions

G7250000 Travel and subsistence

G7300000 Utilities

SACCOUNTCODE	*SDESCRIPTION*	*SGROUP1*	*SGROUP2*
G5000000	*Cost of Sales*	*COST OF GOODS SOLD*	*COST OF GOODS SOLD*

G5200000	Stock (Inventory) shortages / surplus	COST OF GOODS SOLD	COST OF GOODS SOLD
G5400000	Packaging	COST OF GOODS SOLD	COST OF GOODS SOLD
G7100010	Gross Salaries	No group	OPERATING EXPENSES
G6000000	Accounting fees	COST OF GOODS SOLD	OPERATING EXPENSES
G6051000	Audit fees	No group	OPERATING EXPENSES
G6100000	Bad debts	No group	OPERATING EXPENSES
G6150000	Bank charges	No group	OPERATING EXPENSES
G6200000	Cleaning services	No group	OPERATING EXPENSES
G6250000	Commissions paid	No group	OPERATING EXPENSES

G6300000	Depreciation	No group	OPERATING EXPENSES
G6350000	Entertainment	No group	OPERATING EXPENSES
G6400000	Finance charges	No group	OPERATING EXPENSES
G6450000	Gifts and donations	No group	OPERATING EXPENSES
G6500000	Insurance premiums	No group	OPERATING EXPENSES
G6550000	Interest paid	No group	OPERATING EXPENSES
G6600000	Legal fees	No group	OPERATING EXPENSES
G7100020	Employer National Insurance contributions	No group	OPERATING EXPENSES
G7100030	Employer Pension contributions	No group	OPERATING EXPENSE

			S
G6650000	License fees	No group	OPERATING EXPENSES
G6700000	Maintenance	No group	OPERATING EXPENSES
G6750000	Marketing and advertising expenses	No group	OPERATING EXPENSES
T2400040	Output VAT - Zero Rated EU Goods - 0%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G6850000	Office expenses	No group	OPERATING EXPENSES
G6900000	Printing	No group	OPERATING EXPENSES
G6950000	Professional fees	No group	OPERATING EXPENSES
G7000000	Repairs	No group	OPERATING EXPENSES
G7050000	Rent paid	No group	OPERATI

			NG EXPENSES
G7100000	Salaries and wages expenses	No group	OPERATING EXPENSES
G7200000	Stationery	No group	OPERATING EXPENSES
G7250000	Subscriptions	No group	OPERATING EXPENSES
G7300000	Travel and subsistence	No group	OPERATING EXPENSES
G7350000	Utilities	No group	OPERATING EXPENSES
G6050000	Amortization	No group	No group
G1350000	Prepaid expenses / Expenses paid in advance	CURRENT ASSETS@ACCRUED ASSETS	CURRENT ASSETS
T2400015	Output VAT - Reduced rate (Sales) - 5%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES

G7100040	Bonuses and commissions	No group	OPERATING EXPENSES
G7100050	Disability pay	No group	OPERATING EXPENSES
G2250000	Short-term loans	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G7100060	Health Insurance premiums	No group	OPERATING EXPENSES
G7100070	Holiday pay	No group	OPERATING EXPENSES
G7100080	Maternity / Paternity pay	No group	OPERATING EXPENSES
G7100090	Overtime pay	No group	OPERATING EXPENSES
G3100000	Additional capital	EQUITY	EQUITY
G3200000	Drawings	EQUITY	EQUITY
B1010000	Current bank account	CURRENT ASSETS@CASH AND CASH EQUIVALENTS	CASH AND CASH EQUIVAL

			ENTS
G7150000	*Salaries and wages expenses*	*No group*	*No group*
G7150010	*Gross Salaries*	*No group*	*No group*
G8000000	*Gain on sale of assets*	*No group*	*NON-OPERATING REVENUE*
G9000000	*Loss on disposal of assets*	*No group*	*NON-OPERATING EXPENSES*
G7150020	*Employer National Insurance contributions*	*No group*	*No group*
G8020000	*Royalties received*	*No group*	*NON-OPERATING REVENUE*
T2400020	*Output VAT - Exempt Income (Sales) - 0%*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
T2400030	*Output VAT - Zero-rated (Sales) - 0%*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G7150030	*Employer Pension contributions*	*No group*	*No group*
T2400120	*Input VAT - EU Acquisitions - 20% -*	*CURRENT LIABILITIES@OTHER CURRENT*	*CURREN*

	Reverse charged	*LIABILITIES*	*T LIABILITIES*
T2400130	*Input VAT - EU Acquisitions (Zero Rated) - 0%*	*CURRENT LIABILITIES@OTHER CURRENT LIABILITIES*	*CURRENT LIABILITIES*
G8030000	*Rent income*	*No group*	*NON-OPERATING REVENUE*
G8040000	*Foreign exchange gain*	*No group*	*NON-OPERATING REVENUE*
G8050000	*Insurance proceeds*	*No group*	*NON-OPERATING REVENUE*
G8060000	*Legal settlements*	*No group*	*NON-OPERATING REVENUE*
G8070000	*Other non-operating revenue*	*No group*	*NON-OPERATING REVENUE*
G9010000	*Donations & Contributions*	*No group*	*NON-OPERATING*

			EXPENSES
G7100100	Severance pay	No group	OPERATING EXPENSES
G9020000	Foreign exchange loss	No group	NON-OPERATING EXPENSES
G9030000	Insurance expenses	No group	NON-OPERATING EXPENSES
G9040000	Interest expenses	No group	NON-OPERATING EXPENSES
G9050000	Litigation expenses	No group	NON-OPERATING EXPENSES
G7100110	Sick pay	No group	OPERATING EXPENSES
G7100200	Payroll processing fees	No group	OPERATING EXPENSES
G7100210	Payroll software costs	No group	OPERATI

			NG EXPENSES
G7100220	Payroll training costs	No group	OPERATING EXPENSES
G7100230	Other payroll expenses	No group	OPERATING EXPENSES
G5300000	Freight charges	COST OF GOODS SOLD	COST OF GOODS SOLD
G6800000	Motor vehicle expenses	No group	OPERATING EXPENSES
T2400050	Output VAT - Zero Rated EU Services - 0%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
T2400100	Input VAT - Standard rate (Purchases) - 20%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
T2400115	Input VAT - Reduced rate (Purchases) - 5%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
T2400140	Input VAT - Exempt Expenses - 0%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES

G1400000	Short-term - Deposits / Investments	CURRENT ASSETS@SHORT-TERM DEPOSITS	CURRENT ASSETS
T2400150	Input VAT - Reverse Charge Expenses - 20%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
T2400160	Input VAT - VAT on Imports - 100%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
T2400170	Input VAT - Zero Rated EU Expenses - 0%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
T2400180	Input VAT - Zero Rated Expenses - 0%	CURRENT LIABILITIES@OTHER CURRENT LIABILITIES	CURRENT LIABILITIES
G6800010	Fuel and oil	No group	OPERATING EXPENSES
G6800020	Vehicle - Insurance	No group	OPERATING EXPENSES
G6800030	Vehicle - Maintenance and repairs	No group	OPERATING EXPENSES
G6800040	Vehicle - Registration and Licence fees	No group	OPERATING EXPENSES

G6800050	*Vehicle - Tolls and parking fees*	*No group*	*OPERATING EXPENSES*
G6800060	*Vehicle - Traffic fines / Vehicle violation expenses*	*No group*	*OPERATING EXPENSES*

Classification of operating expenses according to groups

You can group or classify these operating expenses into several categories based on their nature and purpose. Here's a suggested grouping:

1. Professional Services Expenses:
    - G6000000 Accounting fees
    - G6050000 Audit fees
    - G6600000 Legal fees
    - G6650000 License fees
    - G6950000 Professional fees
    - G7100800 Payroll processing fees
    - G7100810 Payroll software costs
    - G7100820 Payroll training costs
    - G7100830 Other payroll expenses
2. Financial Expenses:
    - G6100000 Bad debts
    - G6300000 Depreciation
    - G6400000 Finance charges
    - G6550000 Interest paid
3. Employee-related Expenses:

- G7100000 Salaries and wages expenses (break down further if necessary)
  - G7100010 Basic salaries
  - G7100020 Basic wages
  - G7100030 Overtime pay
  - G7100040 Incentives - Bonuses
  - G7100050 Incentives - Commissions
  - G7100100 Allowance - Cellphone
  - G7100110 Allowance - Housing
  - G7100120 Allowance - Meals
  - G7100130 Allowance - Transport
  - G7100140 Allowance - Uniforms
  - G7100200 Leave - Annual leave
  - G7100210 Leave - Sick leave
  - G7100220 Leave - Parental leave
  - G7100300 Retrenchment Packages
  - G7100310 Severance Packages
  - G7100400 Employers contributions (UIF, SDL, Workman's Compensation Fund, Medical Aid, Pension / Retirement Fund)

4. Office and Administrative Expenses:
   - G6150000 Bank charges
   - G6200000 Cleaning services
   - G6850000 Office expenses
   - G7150000 Stationery
5. Marketing and Promotion Expenses:
   - G6750000 Marketing and advertising expenses
6. Transportation Expenses:
   - G6800000 Motor vehicle expenses (break down further if necessary)

- G6800010 Fuel and oil
- G6800020 Vehicle - Insurance
- G6800030 Vehicle - Maintenance and repairs
- G6800040 Vehicle - Registration and Licence fees
- G6800050 Vehicle - Tolls and parking fees
- G6800060 Vehicle - Traffic fines / Vehicle violation expenses

7. Facility and Property Expenses:
    - G6700000 Maintenance
    - G7000000 Repairs
    - G7050000 Rent paid
    - G7300000 Utilities (including electricity, water, gas, etc.)
8. General Expenses:
    - G7250000 Travel and subsistence
    - G7300000 Utilities
    - G7200000 Subscriptions
    - G6250000 Commissions paid (depending on the nature of commissions, this might also fall under another category)
9. Miscellaneous Expenses:
    - G6350000 Entertainment
    - G6450000 Gifts and donations
    - G6900000 Printing

This grouping should help provide a clearer overview of your operating expenses, making it easier for financial reporting and analysis. Depending on your specific accounting and reporting needs, you may further refine these categories.

Administrative expenses - would this fit in with the list of te response?

ChatGPT

Yes, administrative expenses would fit within the list provided in the response. Administrative expenses

typically include costs associated with running the administrative functions of a business. You can group various expenses related to administration under the "Office and Administrative Expenses" category:

Office and Administrative Expenses:

- G6150000 Bank charges
- G6200000 Cleaning services
- G6850000 Office expenses
- G7150000 Stationery
- Administrative salaries and wages (if applicable)

If you have specific administrative expenses that are not covered by the categories listed, you can create subcategories or add them under "Office and Administrative Expenses" for reporting purposes.

Office and Administrative expense

Office and Administrative Expenses would typically include salaries and wages related to administrative staff, while Salaries and wages could also include employees in other departments, including Sales and Marketing.

To clarify:

Office and Administrative Expenses:

- G6150000 Bank charges
- G6200000 Cleaning services
- G6850000 Office expenses
- G7150000 Stationery
- Administrative salaries and wages (related to administrative staff)

Salaries and Wages Expenses (Sales and Marketing):

- G7100000 Salaries and wages expenses (sales and marketing staff)

This way, you can allocate salaries and wages to specific departments or functions within your business for more accurate financial reporting and analysis.

MARKETING AND PROMOTIONS as Operating expenses - Sample of accounts

Certainly, here are some sample accounts that can be classified under "Marketing and Promotions" as part of your operating expenses:

1. Advertising Expenses:
    - G6750010 Advertising campaigns
    - G6750020 Online advertising (e.g., Google Ads, Facebook Ads)
    - G6750030 Print advertising (e.g., newspaper, magazine ads)
    - G6750040 Outdoor advertising (e.g., billboards, signage)
2. Promotional Expenses:
    - G6750050 Promotional materials (e.g., flyers, brochures, pamphlets)
    - G6750060 Promotional events and sponsorships
    - G6750070 Product samples and giveaways
    - G6750080 Merchandising expenses (e.g., point-of-sale displays) *
3. Marketing Research and Analysis:
    - G6750090 Market research expenses
    - G6750100 Customer surveys and feedback
    - G6750110 Marketing analytics tools and software
4. Public Relations Expenses:
    - G6750120 PR campaigns and activities
    - G6750130 Media relations
    - G6750140 Press releases
5. Digital Marketing Expenses:
    - G6750150 Website maintenance and updates
    - G6750160 Email marketing expenses
    - G6750170 Social media advertising and management
6. Event Marketing Expenses:

- G6750180 Event planning and execution
- G6750190 Trade show expenses
- G6750200 Conferences and seminars

7. Creative and Design Costs:
    - G6750210 Graphic design services
    - G6750220 Video production
    - G6750230 Copywriting and content creation
8. Marketing Agency Fees:
    - G6750240 Marketing agency fees (if outsourcing marketing services)

These accounts represent various expenses related to marketing and promotional activities. Depending on the specific needs and structure of your business, you can further customize these accounts to align with your financial reporting and analysis requirements.

* G6750080 Merchandising expenses (e.g., point-of-sale displays) - Here's why merchandising expenses are typically classified as operating expenses:

1. Consumable Nature: Expenses related to point-of-sale displays, marketing materials, and promotional items are typically considered consumable and have a short-term benefit. They are used up or consumed in the process of promoting products or services, which is why they are treated as current period expenses.
2. Matching Principle: Accounting follows the matching principle, which dictates that expenses should be recognized in the same period as the revenues they help generate. In the case of promotional expenses like point-of-sale displays, the costs are incurred to drive immediate sales or brand visibility, and therefore, they are recognized as expenses in the period when they are incurred.
3. Conservatism: From an accounting perspective, it's generally conservative to recognize expenses as they are incurred rather than capitalizing them as assets. Capitalizing such expenses as assets would mean spreading the costs over multiple accounting periods, which may not accurately reflect the costs associated with the revenue generated in the current period.

However, there can be exceptions, especially if certain promotional materials have a more enduring benefit or if they meet specific criteria to be considered as capitalizable assets. This determination should be made in accordance with accounting standards and the specific circumstances of your business. If you believe that certain promotional expenses should be treated as assets, it's important to consult with your accountant or financial advisor and ensure that you are in compliance with applicable accounting regulations.

In most cases, though, merchandising expenses, including point-of-sale displays, are considered operating expenses because they are incurred for the primary purpose of promoting products and generating immediate sales.

TRAINING as Operating expenses - Sample of accounts

Some sample accounts that can be classified under "*Training*" as part of your operating expenses:

1. Employee Training:
    - GXXX0010 Employee orientation and onboarding
    - GXXX0020 Employee skill development programs
    - GXXX0030 Training workshops and seminars for staff
    - GXXX0040 Leadership and management training
    - GXXX0050 Diversity and inclusion training
    - GXXX0060 Health and safety training
    - GXXX0070 Compliance and regulatory training
    - GXXX0080 Software and technology training for employees
2. Sales and Marketing Training:
    - GXXX0100 Sales team training
    - GXXX0110 Marketing team training
    - GXXX0120 Product knowledge training for sales and marketing
    - GXXX0130 Customer service training
3. Customer Training:
    - GXXX0200 Customer training and support
    - GXXX0210 Training materials for customers
    - GXXX0220 Online customer training platforms
4. Supplier and Vendor Training:
    - GXXX0300 Supplier/vendor training and development
5. Technical and IT Training:
    - GXXX0400 IT staff training

- GXXX0410 Software and system training
- GXXX0420 Cybersecurity training

6. Compliance and Safety Training:
    - GXXX0500 Ongoing compliance training
    - GXXX0510 Workplace safety training
    - GXXX0520 Environmental compliance training
7. Professional Development:
    - GXXX0600 Professional certifications and licenses
    - GXXX0610 Industry-specific training
8. Training Materials and Resources:
    - GXXX0700 Training materials and supplies
    - GXXX0710 Training software and platforms
    - GXXX0720 Training books and resources
9. Training Facilities and Equipment:
    - GXXX0800 Training room rental
    - GXXX0810 Training equipment purchase or rental
10. External Training Services:
    - GXXX0900 External training providers and consultants
    - GXXX0910 Training service contracts

These accounts cover a wide range of training-related expenses that businesses may incur. Depending on your specific needs and the complexity of your training programs, you can customize and further detail these accounts to align with your financial reporting and analysis requirements.

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Stock / Inventory

In which countries is Stock used and in which countries is Inventory used?

The terms "*stock*" and "*inventory*" are used differently in various countries, and the usage can depend on regional language and business practices. It's important to note that these terms may have different meanings in different contexts, and the specific terminology used can vary based on the local customs and conventions.

1. Stock: In some countries, particularly in the United Kingdom and other Commonwealth nations, the term "*stock*" is often used to refer to inventory or goods held for sale by a business. For example, a retailer might use the term "*stock*" to describe the goods available for purchase in their store. In this context, "*stock*" is synonymous with "*inventory*" and represents the physical items a business holds to meet customer demand.
2. Inventory: In many other countries, including the United States, Canada, and other parts of the world, the term "*inventory*" is more commonly used to refer to goods held for sale. Businesses use the term "*inventory*" to represent the raw materials, work-in-progress, and finished goods that are part of their production and sales process.

In both cases, "*stock*" and "*inventory*" essentially refer to the same concept of goods held by a business for sale or production purposes. However, the terminology used can vary depending on the region and local business practices.

It's important for businesses and individuals to be aware of the terminology used in their respective countries or regions and understand the context in which these terms are used to avoid any confusion.

Is Inventory or Stock used in South Africa?

In South Africa, the term "*inventory*" is commonly used to refer to goods held by a business for sale or production purposes. The term "*stock*" is not as commonly used in the business context in South Africa to refer to inventory.

South African businesses and accounting practices generally follow international accounting standards and terminology, where "*inventory*" is the standard term used to describe the physical items held by a business, including raw materials, work-in-progress, and finished goods.

Therefore, if you are referring to goods held by a business in South Africa, it is more appropriate to use the term "*inventory*" rather than "*stock*." This terminology is consistent with global accounting practices and ensures clarity and understanding in financial reporting and business communication.

Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Inventory systems

What types of inventory systems are there?

There are several types of inventory systems that businesses use to manage their inventory levels and keep track of their stock. The choice of inventory system depends on the nature of the business, the size of the inventory, and the level of complexity required for inventory management. Some common types of inventory systems include:

1. Periodic Inventory System: In this system, businesses physically count their inventory at regular intervals, such as weekly, monthly, or annually. The cost of goods sold (COGS) and inventory levels are updated periodically based on these physical counts. This method is simple and suitable for small businesses with relatively low inventory levels.
2. Perpetual Inventory System: In a perpetual inventory system, inventory levels are continuously updated in real-time as sales and purchases are made. This is typically done using software and barcoding systems. The system automatically adjusts the inventory and COGS whenever a sale or purchase is recorded. It provides a more accurate and up-to-date view of inventory levels.
3. Just-In-Time (JIT) Inventory System: The JIT inventory system aims to minimize inventory carrying costs by ordering and receiving inventory only when it is needed for production or sale. Businesses maintain very low inventory levels and rely on a tightly coordinated supply chain to receive new inventory as needed.
4. ABC Inventory System: The ABC inventory system categorizes inventory items based on their value and importance. "A" items are high-value and high-importance items, "B" items are moderately important, and "C" items are low-value and low-importance. This system helps businesses prioritize their inventory management efforts and allocate resources efficiently.
5. EOQ (Economic Order Quantity) Model: The EOQ model calculates the optimal order quantity to minimize total inventory costs, including holding costs and ordering costs. The goal is to find the right balance between ordering in large quantities to reduce unit costs and ordering only what is necessary to avoid excessive inventory holding costs.
6. Stock Keeping Units (SKU) System: SKUs are unique codes assigned to each different item in inventory. The SKU system helps businesses track and identify individual products, variations, or different packaging sizes accurately.

7. Backorder System: In a backorder system, businesses accept customer orders even when the item is not currently in stock. The item is then backordered, and the customer is notified of the delay. This system helps businesses avoid losing sales due to temporary stockouts.
8. Dropshipping: In a dropshipping system, businesses don't hold physical inventory but instead transfer customer orders and shipment details to a manufacturer, wholesaler, or another retailer who then ships the products directly to the customer. This system reduces the need for businesses to maintain their inventory.

Each inventory system has its advantages and disadvantages, and businesses choose the one that best aligns with their specific needs, size, and operations. Effective inventory management is crucial for optimizing costs, meeting customer demand, and maximizing profitability.

Created with the Standard Edition of HelpNDoc: Easily Add Encryption and Password Protection to Your PDFs

---

What is inventory valuation?

Inventory valuation is the process of determining the monetary value of a company's inventory (i.e., the goods held for sale or used in the production of goods for sale) at a specific point in time. It is a crucial aspect of financial reporting and is essential for calculating the cost of goods sold (COGS) and the value of ending inventory on the balance sheet.

There are several methods used to value inventory, and the choice of method can have significant effects on a company's financial statements and profitability. The most common inventory valuation methods include:

1. First-In, First-Out (FIFO): This method assumes that the oldest inventory items are sold first. The cost of goods sold is based on the cost of the earliest purchases, and the ending inventory is valued at the cost of the most recent purchases.
2. Last-In, First-Out (LIFO): This method assumes that the most recent inventory items are sold first. The cost of goods sold is based on the cost of the most recent purchases, and the ending inventory is valued at the cost of the earliest purchases. LIFO is not allowed in all accounting standards and is less commonly used in some countries due to tax implications.
3. Weighted Average Cost: This method calculates the average cost of all inventory items available for sale during a specific period and applies that average cost to the cost of goods sold and ending inventory.

4. Specific Identification: This method values each individual item of inventory separately based on its actual cost.

The choice of inventory valuation method can have significant impacts on a company's financial statements, tax liabilities, and profitability. It is essential for businesses to consistently apply the chosen method and disclose the method used in their financial statements to ensure transparency and comparability of financial information.

Inventory valuation is especially important in industries where inventory represents a significant portion of the assets, such as retail, manufacturing, and wholesale businesses. Properly valuing inventory allows businesses to determine the true cost of goods sold, track inventory turnover, and make informed decisions about pricing, production, and inventory management.

Created with the Standard Edition of HelpNDoc: Save time and frustration with HelpNDoc's WinHelp HLP to CHM conversion feature

---

What is LIFO and FIFO?

LIFO (Last-In, First-Out) and FIFO (First-In, First-Out) are two commonly used inventory valuation methods that businesses use to determine the cost of goods sold (COGS) and the value of ending inventory. These methods are used to account for the flow of inventory items in and out of a business.

1. LIFO (Last-In, First-Out): In the LIFO method, the assumption is that the last items added to the inventory are the first ones sold. In other words, the most recently acquired inventory is considered to be sold first. As a result, the cost of goods sold (COGS) is calculated using the cost of the most recent purchases, while the ending inventory is valued at the cost of the earliest purchases. LIFO is often used in periods of rising prices because it results in a higher cost of goods sold, which can lead to lower taxable income.
2. FIFO (First-In, First-Out): In the FIFO method, the assumption is that the first items added to the inventory are the first ones sold. In other words, the oldest inventory is considered to be sold first. As a result, the cost of goods sold (COGS) is calculated using the cost of the oldest purchases, while the ending inventory is valued at the cost of the most recent purchases. FIFO is often used in periods of rising prices because it results in a lower cost of goods sold, which can lead to higher taxable income.

To better understand LIFO and FIFO, let's consider an example:

Example: Suppose a company purchases 100 units of a product at different prices:

- January 1: 50 units at $10 each
- March 1: 30 units at $12 each
- June 1: 20 units at $15 each

At the end of the year, the company has sold 80 units of the product. Using LIFO and FIFO, we calculate the cost of goods sold and the value of ending inventory:

- LIFO Calculation: COGS = (20 units x $15) + (30 units x $12) + (30 units x $10) = $600 Ending Inventory = 20 units x $10 = $200
- FIFO Calculation: COGS = (50 units x $10) + (30 units x $12) = $900 Ending Inventory = 20 units x $15 = $300

As you can see, the LIFO method results in a lower ending inventory value but a higher cost of goods sold compared to the FIFO method. The choice between LIFO and FIFO can have significant effects on a company's financial statements and tax liabilities, and the method selected must be consistently applied over time. Different countries may have specific regulations on which inventory valuation method businesses are allowed to use for tax reporting purposes.

Inventory valuation - which is followed by various accounting standards?

Various accounting standards allow businesses to use different inventory valuation methods, but the most commonly followed methods are:

1. International Financial Reporting Standards (IFRS): IFRS allows businesses to use either the FIFO or weighted average cost methods for inventory valuation. Under IFRS, LIFO is not allowed.
2. Generally Accepted Accounting Principles (GAAP) - United States: In the United States, businesses following US GAAP have the option to use any of the following inventory valuation methods: FIFO, LIFO, and weighted average cost. LIFO is a popular choice among US companies for tax purposes.
3. ASPE (Accounting Standards for Private Enterprises) - Canada: In Canada, businesses following ASPE can use the FIFO, LIFO, or weighted average cost methods for inventory valuation. However, LIFO is less common in Canada due to its impact on tax calculations.
4. UK GAAP (Generally Accepted Accounting Practice) - United Kingdom: UK GAAP allows businesses to use either the FIFO or weighted average cost methods for inventory valuation. LIFO is not commonly used in the UK.
5. Indian Accounting Standards (Ind AS): Ind AS allows businesses to use any of the following inventory

valuation methods: FIFO, weighted average cost, and specific identification.

6. Chinese Accounting Standards (CAS): In China, businesses are required to use the FIFO method for inventory valuation.

It's important to note that while these accounting standards provide guidance on inventory valuation methods, businesses must consistently apply the chosen method and disclose the method used in their financial statements. Additionally, some countries or industries may have specific regulations or restrictions on the inventory valuation method used for tax reporting purposes. As a result, businesses should consult with accounting professionals or tax advisors to ensure compliance with applicable regulations and accounting standards.

Inventory valuation - LIFO and FIFO -which is followed in South Africa?

As of ChatGPT's last update in September 2021, South Africa follows the First-In, First-Out (FIFO) method for inventory valuation. The use of Last-In, First-Out (LIFO) for inventory valuation is not permitted in South Africa.

The International Financial Reporting Standards (IFRS) are adopted in South Africa for financial reporting by companies listed on the Johannesburg Stock Exchange (JSE). Under IFRS, FIFO is one of the accepted methods for inventory valuation. LIFO is not allowed under IFRS and is not commonly used in South Africa for financial reporting purposes.

It's important to note that accounting regulations and standards can change over time, so it's always best to consult with accounting professionals or refer to the latest accounting guidelines issued by relevant authorities in South Africa to ensure compliance with the current inventory valuation methods.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

COS, COGS and COSR

What is cost of sales?

Cost of sales, also known as cost of goods sold (COGS), is the direct cost incurred by a company to produce or purchase the goods or services that it sells to customers. It represents the expenses directly associated with the production or acquisition of the products that are subsequently sold.

The cost of sales includes various expenses related to the production process or the purchase of

inventory, such as:

1. Cost of Raw Materials: This includes the cost of the materials and components used in the manufacturing process.
2. Direct Labour Costs: This includes the wages and benefits paid to employees directly involved in the production or assembly of goods.
3. Manufacturing Overhead: These are indirect costs associated with production, such as utilities, factory rent, and depreciation of manufacturing equipment.
4. Purchase Cost: For companies that don't manufacture their own products, the cost of sales includes the purchase price of goods from suppliers.
5. Shipping and Freight Costs: These are the expenses incurred to transport goods from the manufacturer or supplier to the company's warehouse or directly to customers.

Cost of sales is an essential component of the income statement (profit and loss statement) and is deducted from the company's total revenue to calculate gross profit. Gross profit represents the difference between revenue and the cost of sales and reflects the profitability of a company's core operations before considering other operating expenses.

The formula to calculate gross profit is:

```
Gross Profit = Total Revenue - Cost of Sales
```

The accuracy and management of cost of sales are critical for businesses to ensure proper pricing of products, effective inventory management, and overall financial performance analysis. It also plays a significant role in determining a company's gross margin, which is the percentage of revenue remaining after deducting the cost of sales.

What is COS, COGS and COSR?

COS, COGS, and COSR are abbreviations used in accounting and business to refer to different concepts related to the cost of sales or cost of goods sold. While they are related, they have specific meanings and contexts in which they are used:

1. COS (Cost of Sales):
    - COS is a general term that refers to the total cost incurred by a business to produce or acquire the goods or services that it sells to customers. It includes all the direct and indirect costs associated with the production or purchase of goods or services, such as raw materials, direct labour, manufacturing overhead, shipping costs, and any other expenses directly related to the production process.

2. COGS (Cost of Goods Sold):
    - COGS is a specific line item on the income statement (profit and loss statement) that represents the direct costs associated with the production or purchase of goods that were sold during a specific accounting period. It includes the costs of raw materials, direct labour, and manufacturing overhead. COGS is used to calculate gross profit, which is the difference between total revenue and COGS. Gross profit reflects the profitability of a company's core operations before considering other operating expenses.
3. COSR (Cost of Services Rendered):
    - COSR is a specific line item on the income statement (profit and loss statement) that represents the direct costs incurred by a service-based business to provide services to its customers. Similar to COGS (Cost of Goods Sold) for businesses that sell physical products, COSR is the equivalent for service-based businesses.

In summary, COS is a general term referring to the total cost of producing or acquiring goods or services for sale, COGS is a specific line item on the income statement representing the direct costs of goods sold during a specific period, and COSR is the equivalent for service-based businesses These concepts are important for businesses to assess their profitability, cost management, and overall financial performance.

COSR as in Cost of Services Rendered?

COSR can also stand for "Cost of Services Rendered" in some contexts.

The Cost of Services Rendered typically includes expenses such as:

1. Direct Labour Costs: The wages and benefits paid to employees who directly provide the services to customers.
2. Materials and Supplies: The cost of any materials or supplies used in delivering the services.
3. Subcontractor Costs: If the business hires subcontractors or freelancers to provide certain services, their costs may be included in the COSR.
4. Other Direct Costs: Any other direct costs specifically related to rendering the services to customers.

Just like COGS, the COSR is an important factor in calculating the profitability of a service-based business. It is deducted from the total revenue generated from services to determine the gross profit from services rendered. Gross profit from services indicates the efficiency of the business's operations and provides insights into the overall financial performance of the service-based company.

COSR (Cost of Sales Ratio)

COSR is a financial ratio that measures the percentage of sales revenue that is consumed by the cost of sales (COGS). It is calculated by dividing COGS by total sales revenue and multiplying by 100 to express the result as a percentage. The COSR is used to assess the efficiency of a company's cost management and production processes. A lower COSR indicates that a company is able to generate more profit from its sales revenue, while a higher COSR may indicate higher production or purchasing costs relative to revenue.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Work in Progress (WIP)

What is Work in Progress?

"*Work in Progress*" (WIP) refers to partially completed projects or goods that are still in the process of production or construction but have not yet been finished or delivered to the customer. It is an important concept in accounting and business management, particularly in industries that involve long-term projects or the manufacturing of goods.

In the context of accounting, Work in Progress represents the value of costs incurred on unfinished projects or goods at a specific point in time. These costs include direct materials, direct labour, and manufacturing or production overheads that have been allocated to the incomplete items. Work in Progress is considered an asset on the company's balance sheet because it represents the value of work that has been done but not yet converted into finished products or delivered to customers.

Here are some examples of how Work in Progress can apply in different industries:

1. Construction Industry: In construction, Work in Progress represents the value of buildings or infrastructure projects that are still under construction. It includes the cost of materials, labour, and overheads incurred in the construction process.
2. Manufacturing Industry: In manufacturing, Work in Progress refers to the value of partially finished goods that are still on the production line and have not been completed or moved to the finished goods inventory.
3. Service Industry: In the service industry, Work in Progress may refer to ongoing projects or services that are in progress but not yet completed or billed to the customer.

Recording Work in Progress is essential for accurate financial reporting. Companies need to account for the costs incurred on partially completed projects to properly assess the value of work done and the

associated revenue and expenses. As the projects or goods are completed, the costs are transferred to the finished goods inventory or recognized as revenue when delivered to customers.

Work in Progress is also a key indicator of a company's operational efficiency and productivity. Monitoring the value of Work in Progress helps management track the progress of ongoing projects, identify potential bottlenecks, and manage resources effectively to meet project timelines and customer demands.

It's important to note that the specific accounting treatment of Work in Progress may vary depending on the accounting standards used by the company and the nature of the industry in which it operates.

How would Work in Progress (WIP) reflect in the Chart of Accounts?

"*Work in Progress*" (WIP) is typically represented as an asset in the Chart of Accounts of a company. It is categorized under current assets or non-current assets, depending on the time it takes to complete the projects or convert the WIP into finished goods. The specific account number and name in the Chart of Accounts may vary between companies, but here are some common examples:

1. 1130 Work in Progress (WIP) - Current Assets: This account is used to track the value of work in progress that is expected to be completed and converted into finished goods or delivered to customers within the next accounting period. It represents the costs incurred on partially completed projects or goods that are in the production process.
2. 1135 Work in Progress (WIP) - Non-Current Assets: This account is used to track the value of work in progress that will take longer than the next accounting period to complete. It represents long-term projects or production activities that are expected to span multiple accounting periods.

The Work in Progress accounts mentioned above can be further subdivided based on specific projects or types of WIP if the company deals with multiple ongoing projects or has different WIP categories.

As the projects or production processes are completed, the costs associated with the Work in Progress are transferred to the appropriate accounts. For example:

- For manufacturing companies, completed WIP is transferred to the Finished Goods Inventory account when the goods are fully produced and ready for sale.
- For construction companies, completed WIP is transferred to the Fixed Assets or Property, Plant, and Equipment accounts when the construction projects are completed.

It's important to note that the Chart of Accounts is customizable and can vary between companies based on their specific business activities and accounting requirements. The examples provided here are general illustrations of how WIP might be represented in the Chart of Accounts. Companies may choose to use different account numbers, names, or subcategories based on their internal reporting needs and

accounting practices.

Would Work in Progress (WIP) reflect Cost of Sales in the Chart of Accounts?

No, "*Work in Progress*" (WIP) does not reflect in the Cost of Sales (also known as Cost of Goods Sold or COGS) in the Chart of Accounts. WIP and COGS are two separate and distinct concepts in accounting, and they serve different purposes in financial reporting.

1. Work in Progress (WIP): As mentioned earlier, WIP is the value of partially completed projects or goods that are still in the process of production or construction but have not yet been finished or delivered to the customer. WIP is considered an asset on the company's balance sheet because it represents the value of work that has been done but not yet converted into finished products or delivered to customers. WIP is part of the company's inventory and is usually categorized as a current asset or a non-current asset, depending on the expected completion time of the projects or goods.
2. Cost of Sales (COGS): COGS represents the direct costs incurred by a company to produce or acquire the goods or services sold to customers during a specific accounting period. COGS includes the costs of raw materials, direct labour, and manufacturing or production overhead directly related to the production of goods or provision of services. COGS is an expense on the income statement and is subtracted from the company's revenue to calculate its gross profit.

The key difference between WIP and COGS is that WIP represents the value of unfinished projects or goods, which have not yet been sold, while COGS represents the costs associated with the goods that have been sold during a specific period.

When the WIP is completed and converted into finished goods, the costs associated with it will be included in the COGS when those finished goods are sold to customers. Until the completion of WIP, the costs incurred are considered assets, and they only become expenses (COGS) when the goods are sold.

To summarize, WIP and COGS are separate elements in the Chart of Accounts, with WIP being an asset representing partially completed projects or goods, and COGS being an expense representing the direct costs associated with the goods sold during a specific accounting period.

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Amortization

What is Amortization?

Amortization is a financial term that refers to the process of spreading the cost of an intangible asset over its useful life. It is a systematic allocation of the asset's cost, similar to depreciation for tangible assets. Intangible assets are assets that lack physical substance but have value due to their contractual or legal rights, intellectual property, or other factors.

The purpose of amortization is to match the cost of acquiring or creating an intangible asset with the benefits it provides over time. As the asset generates benefits, its cost is gradually recorded as an expense on the income statement. This helps in accurately reflecting the asset's consumption or decline in value over time.

Common examples of intangible assets subject to amortization include:

1. Patents: Exclusive rights granted to inventors to protect their inventions from being used, made, or sold by others without permission.
2. Copyrights: Exclusive rights granted to authors, artists, or creators to protect their original works (e.g., books, music, software).
3. Trademarks: Distinctive symbols, names, or logos that identify and distinguish products or services from those of competitors.
4. Franchise Rights: Rights granted by a franchisor to a franchisee to operate under their brand and business model.
5. Licenses: Permissions granted by an authority to carry out specific activities or use specific resources.

The process of amortization involves dividing the cost of the intangible asset (minus any estimated residual value) over its estimated useful life. The result is the annual amortization expense, which is recognized in the financial statements over the asset's useful life.

It's essential to note that amortization is different from depreciation, which is the systematic allocation of the cost of tangible assets (such as buildings, machinery, and equipment) over their useful life. Both amortization and depreciation are crucial accounting practices that help organizations accurately represent the consumption of assets and their impact on financial performance.

What is the transactions for amortization?

The transactions for amortization involve recording the periodic allocation of the cost of an intangible asset as an expense over its useful life. Let's take an example of a patent to understand the transactions for amortization:

Assuming a company purchased a patent for $60,000 with an estimated useful life of 5 years and no

estimated residual value. The company would record the following transactions for amortization:

1. Initial Purchase of Patent:

Patent Account (Intangible Asset)	Cash/Bank Account (Payment)
Debit: $60,000	Credit: $60,000

2. Annual Amortization Expense (Straight-line method):

   The straight-line method evenly distributes the cost of the patent over its useful life. So, the annual amortization expense would be $60,000 / 5 = $12,000.

Amortization Expense Account (Operating Expense)	Accumulated Amortization Account (Contra-Asset)
Debit: $12,000	Credit: $12,000

At the end of Year 1, the company's financial statements would show the following balances:

Balance Sheet

- Intangible Assets:
  - Patent: $48,000 ($60,000 - $12,000)

Income Statement

- Operating Expenses:
  - Amortization Expense: $12,000

The process of amortization will continue each year until the end of the asset's useful life or until the asset is fully amortized.

Please note that the above example uses the straight-line method of amortization, which allocates an equal amount of the asset's cost each year. Other methods like the declining balance method or units-of-production method can also be used depending on the organization's accounting policies and the asset's pattern of usage or consumption.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

RICA and related laws

RICA

RICA stands for "*Regulation of Interception of Communications and Provision of Communication-Related Information Act*." It is a South African law that was enacted to regulate the interception of communications and the handling of communication-related information to protect the privacy and security of communications in the country.

The main objectives of RICA are to:

1. Protect Privacy: RICA aims to protect the privacy and confidentiality of communications by regulating how and when interceptions of communications can be conducted.
2. Combat Crime and Security Threats: The law facilitates the lawful interception of communications by law enforcement agencies in cases of serious crimes and security threats, subject to appropriate judicial oversight.
3. Prevent Unauthorized Access: RICA seeks to prevent unauthorized access to communication-related information, including call records and subscriber information.

Key provisions of RICA include:

1. Registration of SIM Cards: RICA requires all users of mobile phones and other communication devices to register their SIM cards with their personal information. This helps law enforcement trace and identify users when necessary.
2. Interception of Communications: The law provides procedures and requirements for law enforcement agencies to lawfully intercept communications, such as phone calls or messages, during investigations related to serious crimes.
3. Handling of Communication-Related Information: RICA sets out guidelines for the lawful access and handling of communication-related information by law enforcement and other authorized entities.
4. Judicial Oversight: RICA emphasizes the importance of judicial oversight to ensure that interception orders are only granted when justified and necessary for the investigation of serious crimes or national security concerns.
5. Data Retention: RICA requires communication service providers to retain certain communication-related information for a specified period, which can be accessed by authorized entities as part of investigations.

It's important to note that RICA is specific to South Africa and does not apply in other countries. Similar legislation may exist in other jurisdictions to regulate communication interception and protect privacy. The goal of RICA is to strike a balance between the need for law enforcement and security agencies to access communication-related information for legitimate reasons and the protection of individual privacy rights.

How can RICA help to secure a business or organizations resources?

RICA (Regulation of Interception of Communications and Provision of Communication-Related Information Act) can help secure a business or organization's resources in several ways:

1. Verification of Customer Identities: RICA requires telecommunications service providers to verify the identities of their customers before providing telecommunication services. This verification process helps ensure that the services are used by legitimate individuals or entities and not by malicious actors seeking to engage in illegal activities.
2. Prevention of Unauthorized Access: RICA places an emphasis on data protection and privacy. Telecommunications service providers are required to implement security measures to safeguard customer information from unauthorized access or use. This helps prevent unauthorized individuals from gaining access to sensitive data or using telecommunication services for fraudulent purposes.
3. Monitoring Suspicious Activities: RICA allows law enforcement and authorized agencies to intercept communications in specific circumstances, such as during investigations related to serious crimes or national security threats. This monitoring capability can help identify and prevent criminal activities, thereby enhancing the security of businesses and organizations.
4. Legal Enforcement Against Wrongdoers: RICA enables law enforcement agencies to gather evidence through lawful interception of communications, which can be crucial in prosecuting criminals and wrongdoers. This legal enforcement can act as a deterrent to potential threats and enhance the overall security environment.
5. Assistance in Incident Response: In case of security incidents or emergencies, RICA-compliant telecommunication service providers may cooperate with law enforcement authorities to provide critical information and aid in incident response efforts. This collaboration can help mitigate the impact of security breaches and expedite the resolution of issues.
6. Reduction of Fraudulent Activities: By verifying customer identities and monitoring suspicious activities, RICA can help reduce fraudulent activities conducted through telecommunication channels. This can protect businesses and organizations from financial losses and reputational damage caused by fraudulent schemes.
7. Protection against Terrorism and Cybersecurity Threats: RICA's provisions on lawful interception and information sharing can contribute to national security efforts by detecting and preventing terrorist activities and cybersecurity threats that may use telecommunication networks.
8. Safeguarding Intellectual Property: In some cases, RICA may assist businesses in investigating and addressing issues related to intellectual property infringement conducted through telecommunication

channels.

It's important to note that while RICA can play a role in securing businesses and organizations, security measures should not solely rely on telecommunication-related regulations. Comprehensive security strategies should encompass various aspects, such as cybersecurity measures, physical security, access controls, employee training, and incident response protocols.

Businesses and organizations can enhance their overall security posture by implementing a multi-layered security approach that considers RICA compliance as one of the components to protect their valuable resources, data, and operations.

RICA - Is there similar regulations and legislation in other countries or jurisdictions?

Yes, there are similar regulations and legislation in other countries and jurisdictions that govern the interception of communications and the handling of communication-related information. These laws are often referred to as "*Interception of Communications*" or "*Telecommunications Surveillance*" laws and are designed to protect privacy rights while allowing lawful access to communications for specific purposes, such as criminal investigations and national security.

The specific names and details of these laws may vary from country to country, but their underlying objectives are often similar to those of RICA in South Africa. Some examples of similar legislation in other countries include:

1. United States: In the United States, the main legislation governing electronic surveillance and communications interception is the "*Electronic Communications Privacy Act*" (ECPA). The ECPA includes provisions on the interception of wire, oral, or electronic communications, and it sets forth guidelines for the use of electronic surveillance by law enforcement agencies.
2. United Kingdom: In the United Kingdom, the relevant legislation is the "*Regulation of Investigatory Powers Act*" (RIPA), which provides the legal framework for the interception of communications, the acquisition of communications data, and the conduct of covert surveillance.
3. European Union: Within the European Union, data protection and privacy laws, such as the General Data Protection Regulation (GDPR), apply to the processing of personal data, including communications data. Additionally, individual EU member states may have specific laws on telecommunications surveillance.
4. Canada: In Canada, the "*Personal Information Protection and Electronic Documents Act*" (PIPEDA) includes provisions related to the interception of communications and the protection of personal information.
5. Australia: In Australia, the "*Telecommunications (Interception and Access) Act*" governs the interception

of communications and the access to telecommunications data by law enforcement and intelligence agencies.

6. India: India has the "*Telegraph Act*" and the "*Information Technology Act*" (IT Act) that address interception of communications and the use of electronic evidence.

These are just a few examples, and many other countries have their own specific legislation concerning communications interception and data privacy. The exact provisions and scope of these laws can differ significantly depending on each country's legal system, cultural norms, and approach to balancing privacy rights with legitimate law enforcement and national security interests.

Businesses operating in multiple jurisdictions or providing telecommunication services across borders must ensure compliance with the relevant laws and regulations in each country where they operate or offer services. It's essential for businesses to be aware of the legal requirements and obligations related to communications interception and data privacy to avoid potential legal and reputational risks.

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Taxes - Types

Important - Tax compliance

Ignorance of the law is not a valid defense for non-compliance. It's essential for individuals and businesses to ensure they understand and adhere to the accounting standards, frameworks, and tax regulations applicable in their country or jurisdiction. Consulting with relevant authorities, tax professionals, accountants, and legal experts is a prudent approach to avoid legal and financial consequences related to non-compliance. Staying informed and proactive in meeting legal obligations is crucial for maintaining the integrity and sustainability of any business or financial endeavor.

What is taxes and what types of taxes are used in the various countries?

Taxes are compulsory financial contributions imposed by governments on individuals, businesses, and other entities to fund public services and government activities. Taxes are a primary source of revenue for governments and play a crucial role in funding infrastructure, education, healthcare, defense, and other essential services that benefit society.

Types of taxes can vary significantly from one country to another, but some common types of taxes found

in various countries include:

1. Income Tax: Income tax is levied on individuals and businesses based on their earnings or profits. It may be progressive, meaning the tax rate increases with income levels.
2. Corporate Tax: Corporate tax is imposed on the profits of businesses and corporations. The tax rate may vary depending on the country's tax laws and the size of the company.
3. Value Added Tax (VAT)/Goods and Services Tax (GST): VAT or GST is a consumption tax levied on the value added at each stage of production or distribution of goods and services. It is typically borne by the end consumer.
4. Sales Tax: Similar to VAT/GST, sales tax is applied to the sale of goods and services. It may be levied at the federal, state, or local level.
5. Property Tax: Property tax is based on the value of real estate owned by individuals or businesses. It is commonly used to fund local government services.
6. Capital Gains Tax: Capital gains tax is imposed on the profit realized from the sale of assets, such as stocks, bonds, real estate, or businesses.
7. Inheritance/Estate Tax: Inheritance or estate tax is applied to the transfer of assets from a deceased person's estate to their beneficiaries.
8. Social Security Contributions: Social security contributions are payroll taxes paid by employees and employers to fund social security programs, such as retirement benefits and healthcare.
9. Import/Export Duties: Import duties (customs duties) are taxes imposed on goods imported into a country, while export duties are taxes levied on goods leaving a country.
10. Excise Tax: Excise tax is imposed on specific goods or services, such as alcohol, tobacco, gasoline, and luxury items.
11. Environmental Taxes: Some countries impose environmental taxes to discourage activities harmful to the environment, such as carbon taxes on greenhouse gas emissions.

It's important to note that tax systems can be complex and vary widely from country to country. Each country's government determines its tax policies and rates, and they can change over time due to economic conditions and political decisions. Taxpayers are generally required to comply with their country's tax laws and regulations and fulfill their tax obligations by paying the appropriate taxes in a timely manner.

Is State Income Tax (SIT), Federal Income Tax (FIT) and Income Tax the same?

State Income Tax (SIT), Federal Income Tax (FIT), and Income Tax refer to different types of taxes, but they are all related to the taxation of individuals' income. Let's clarify the differences:

1. State Income Tax (SIT): State Income Tax, as the name suggests, is a tax levied by individual states within a country. Not all countries have state-level income taxes; this concept is particularly applicable to federal systems like the United States, Canada, Australia, and others.

   In the United States, each state can impose its own income tax on residents and sometimes on non-residents earning income within the state's jurisdiction. State income tax rates and rules vary widely among different states. Individuals in states with income tax need to file separate state tax returns in addition to their federal tax return.

2. Federal Income Tax (FIT): Federal Income Tax, on the other hand, is the tax levied by the central or federal government of a country on individuals' income. It is a nationwide tax system that applies to residents and non-residents throughout the entire country.

   In the United States, the Internal Revenue Service (IRS) is responsible for collecting federal income taxes. The federal tax rates and rules are set by the federal government and apply uniformly across all states.

3. Income Tax (Generic Term): "*Income Tax*" is a general term used to refer to taxes imposed on individuals based on their income. It is a broader term that encompasses both state income tax and federal income tax, as well as other similar taxes imposed by different countries.

So, in summary:

- State Income Tax (SIT) is specific to individual states within a country and can vary from state to state.
- Federal Income Tax (FIT) is imposed by the central or federal government and applies nationwide.
- Income Tax, as a generic term, includes both state income tax and federal income tax and is used to describe taxes on individuals' income in general.

The tax systems and terminology may vary from country to country, but the concepts of state income tax, federal income tax, and income tax are designed to generate revenue for governments and are based on individuals' income levels.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's

SIT - Is that State Income Tax?

Yes, "*SIT*" stands for "*State Income Tax*." It refers to the income tax imposed by individual U.S. states on the taxable income of residents and businesses within their jurisdiction. State income taxes are separate from federal income taxes, which are imposed by the U.S. federal government.

Each state in the United States has the authority to impose its own income tax laws and rates, subject to the limits of the U.S. Constitution. State income tax rates can vary significantly from state to state, and some states may not levy an income tax at all.

Individuals and businesses must file state income tax returns to report their income earned within the state and calculate the amount of state income tax owed. State income tax returns are typically due around the same time as federal income tax returns, on or around April 15th of each year.

It's important for individuals and businesses to be aware of their state's specific income tax laws, rates, and filing requirements to ensure compliance with state tax regulations and avoid penalties for late or incorrect filings. Additionally, some states may offer various deductions, credits, and exemptions that can help reduce the overall state income tax liability. Consulting a tax professional can be helpful in navigating state income tax regulations and optimizing tax planning strategies.

In which countries does SIT apply?

The acronym "*SIT*" can have different meanings depending on the context and the country in question. However, as mentioned earlier, in the context of taxes, "*SIT*" commonly stands for "*State Income Tax*" in the United States. State income tax is imposed by individual U.S. states on the taxable income of residents and businesses within their jurisdiction.

Outside of the United States, the acronym "*SIT*" may have different meanings and applications depending on the country's tax system or other contexts. For instance:

1. In some other countries, "*SIT*" might stand for "*Social Insurance Tax*," which is a tax levied to fund social insurance programs, such as health care, unemployment benefits, and pensions.
2. In other cases, "*SIT*" could refer to "*Sales and Income Tax*" when a country combines a consumption tax (e.g., Value Added Tax - VAT or Goods and Services Tax - GST) with an income tax system.
3. "*SIT*" might also be used as an abbreviation for specific taxes related to specific regions or local jurisdictions.

To provide accurate information about the countries where "*SIT*" applies, it would be necessary to clarify the specific meaning or context of the acronym. Tax systems vary widely between countries, and different countries may use different acronyms or tax names for similar types of taxes.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Federal Income Tax (FIT)

What is FIT?

"*FIT*" stands for "*Federal Income Tax.*" It is a type of income tax that is imposed by the central or national government of a country on individuals and businesses based on their taxable income. The term "*FIT*" is often used in countries that have a federal system of government, where income tax is collected at the federal level, as opposed to state or local levels.

Federal income tax is a significant source of revenue for the government and is used to fund various public services, infrastructure projects, and social programs. The rates and rules for calculating federal income tax can vary between countries and are subject to the tax laws and regulations of each specific jurisdiction.

In countries with a federal income tax system, individuals and businesses are required to report their income and deductions to the tax authorities on an annual basis. The tax authorities then assess the tax liability based on the applicable tax rates and deductions allowed under the tax laws.

Federal income tax is one component of the overall tax burden that individuals and businesses may face. In addition to federal income tax, there may be other types of taxes, such as state or provincial income tax, local taxes, social security contributions, and other levies.

It's important to note that the specific term "FIT" might not be used in all countries. The concept of federal income tax, however, is applicable in countries that have a federal system of government and collect income tax at the federal level. The terminology for income tax may vary between countries, and the specific rules and rates are subject to the tax laws of each jurisdiction.

In which countries does FIT apply?

The term "*FIT*" (Federal Income Tax) specifically applies to countries that have a federal system of government, where the central or national government imposes income tax on individuals and businesses operating within the country. The tax is commonly known as federal income tax because it is collected at the federal level, as opposed to state or local levels.

Countries with federal systems that impose federal income tax include:

1. United States: The United States has a federal income tax system, where the federal government collects income tax from individuals and businesses based on their taxable income.
2. Canada: Canada has a federal income tax system, where the federal government levies income tax on individuals and corporations.
3. Australia: Australia operates under a federal income tax system, with the federal government collecting income tax from individuals and businesses.
4. Germany: Germany is an example of a federal country that has a federal income tax system imposed by the national government.
5. Switzerland: Switzerland has a federal system of government and collects federal income tax from individuals and businesses.
6. India: India operates a federal income tax system, where the federal government levies income tax on individuals and companies.

It's important to note that not all countries have a federal system of government, and thus, the concept of "FIT" may not apply everywhere. In some countries, income tax may be collected at the national level without a formal federal system. Additionally, the specific income tax rates, rules, and regulations can vary significantly between countries, and they are subject to change based on each country's tax laws and economic policies.

If you are considering the application of federal income tax in a specific country, it's essential to refer to that country's tax authorities or consult with a tax professional who is familiar with the tax laws of that particular jurisdiction.

What is Taxes – FIT Expense?

In the Chart of Accounts, "*7400 Taxes – FIT Expense*" refers to the account used to record the income tax expense related to the company's federal income tax (FIT) liability. FIT stands for Federal Income Tax, which is the tax imposed by the national or federal government on a company's taxable income.

The account "7400 Taxes – FIT Expense" is part of the company's operating expenses and falls under the broader category of income tax expenses. It is used to record the estimated or actual income tax liability that the company owes to the federal government based on its taxable income.

When a company prepares its financial statements, it calculates its income tax expense using the applicable tax rates and regulations. This calculation considers deductions, credits, and other factors that impact the company's taxable income. The resulting income tax expense is recorded in the "*7400 Taxes – FIT Expense*" account.

It's important to note that the specific account numbers and names in a Chart of Accounts can vary from

one organization to another, depending on the company's accounting system and practices. However, the use of a dedicated account to record income tax expense related to federal income tax is a common practice to ensure proper accounting and tax reporting.

In the context of financial reporting, income tax expense is typically disclosed in the income statement as part of the company's operating expenses. It reflects the company's tax obligation to the federal government and is an essential element in calculating the company's net income for the period.

What would be a structure and accounts in the Chart of Accounts for FIT?

The Chart of Accounts for Federal Income Tax (FIT) will vary depending on the accounting system and practices of each specific company or organization. However, I can provide a general structure and example accounts commonly used to record FIT-related transactions. The accounts are typically categorized under operating expenses and income tax expense. Here's an example of a Chart of Accounts for FIT:

Income Tax Expense Accounts:

1. 7400 Taxes – FIT Expense: This account is used to record the current year's income tax expense related to federal income tax liability.
2. 7410 Taxes – Deferred FIT Expense: This account is used to record the deferred income tax expense related to temporary differences between accounting income and taxable income.

Income Tax Liability Accounts:

3. 2110 Current Income Tax Payable: This account represents the current year's federal income tax liability that is due and payable to the tax authorities.
4. 2120 Deferred Income Tax Liability: This account represents the portion of income tax that is deferred to future periods due to temporary differences between accounting and tax rules.

Income Tax Asset Accounts:

5. 1130 Income Tax Receivable: This account represents the current year's income tax refund receivable from the tax authorities, if applicable.
6. 1140 Deferred Income Tax Asset: This account represents the portion of income tax overpaid or prepaid that is deferred to future periods due to temporary differences.

Adjustments and Provisions:

7. 7300 Income Tax Provision Adjustment: This account is used to record adjustments to the income tax provision during the year, such as changes in tax rates or adjustments to deferred tax balances.

Miscellaneous Tax Accounts:

8. 7800 Taxes – Other: This account is used to record other taxes that may be payable or receivable, such as state or local taxes, in addition to FIT.

It's important to note that the account numbers and names in the Chart of Accounts can be customized based on the company's accounting system and preferences. Additionally, the structure and accounts might differ based on the company's specific tax situation, industry, and accounting requirements. It's essential to consult with a qualified accountant or financial professional to design a Chart of Accounts that best suits the company's needs and ensures accurate recording and reporting of FIT-related transactions.

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Capital gains tax

What is Capital gains tax?

Capital gains tax is a tax levied on the profit or "capital gain" realized from the sale or disposal of certain types of assets, such as stocks, real estate, precious metals, and other investments. The tax is applied to the difference between the purchase price (cost basis) of the asset and its selling price. If the selling price is higher than the purchase price, a capital gain is generated, and if the selling price is lower, a capital loss is incurred.

Key points about capital gains tax:

1. Taxable Assets: Capital gains tax is typically applied to the sale of assets held for investment purposes or for personal use, but it does not usually apply to assets used in a trade or business. The specific assets subject to capital gains tax may vary depending on the tax laws of each country.
2. Short-term vs. Long-term: In many countries, including the United States, the tax rates for capital gains depend on the holding period of the asset. Assets held for a short period (usually one year or less) are considered short-term capital gains and are generally taxed at a higher rate than assets held for a more extended period, which are considered long-term capital gains.
3. Tax Rates: The tax rates for capital gains vary by country and can also depend on the taxpayer's income level and other factors. In some countries, capital gains may be subject to lower tax rates compared to ordinary income tax rates, incentivizing long-term investments.
4. Tax Deductions and Credits: In certain tax systems, capital losses from the sale of assets can be used to offset capital gains, reducing the overall tax liability. Additionally, some countries may provide tax credits or deductions for specific types of capital gains, such as gains from the sale of a primary

residence.

5. Exemptions: Some jurisdictions offer exemptions or reduced tax rates on capital gains for certain types of assets or in specific circumstances. For example, the sale of certain small assets or assets held within tax-advantaged accounts like Individual Retirement Accounts (IRAs) may be exempt from capital gains tax.

Capital gains tax is an important source of revenue for governments and plays a role in shaping investment behavior and economic decisions. It's essential for individuals and investors to understand the capital gains tax rules in their country and consider tax implications when making investment decisions or selling assets. Tax laws regarding capital gains can be complex and subject to change, so seeking advice from tax professionals is recommended for specific guidance.

Capital gains tax - where would it Fit in the Chart of Accounts under IFRS and GAAP?

Under both IFRS and GAAP, capital gains tax would typically be recorded as an income tax expense in the income statement and as a liability in the balance sheet until it is paid.

In the chart of accounts, the account for income tax expense would typically be listed under the category of operating expenses or general and administrative expenses. The account for the liability of unpaid income taxes would typically be listed under the category of current liabilities.

For example, under IFRS, the account for income tax expense might be listed as "*Income tax expense - current*" and the liability account for unpaid income taxes might be listed as "*Income tax payable*". Under GAAP, similar accounts might be listed as "*Income tax provision*" and "*Income tax payable*", respectively.

It's worth noting that the exact placement of the capital gains tax account in the chart of accounts may vary depending on the specific organization's accounting policies and practices. However, the general principle is that capital gains tax would be recorded as an income tax expense and a liability in the financial statements.

What accounts and transactions is used to record capital gains?

Capital gains are generally recorded in the accounting system through journal entries. The accounts and transactions used to record capital gains depend on the type of asset sold and the accounting method used by the organization.

Under a typical scenario where a company sells an asset for more than its cost, resulting in a capital gain, the following accounts and transactions would be involved:

1. Sale of the asset: The sale of the asset would be recorded as a debit to Cash or Accounts Receivable

(depending on how the buyer paid) and a credit to the asset account being sold (e.g. Property, Plant, and Equipment).

2. Calculation of the capital gain: The capital gain is the difference between the sale price and the asset's book value (i.e. its original cost minus accumulated depreciation). This amount would be calculated and recorded as a debit to the capital gains account and a credit to the asset account being sold.
3. Recognition of the tax liability: If the organization is subject to capital gains tax, a tax liability would be recognized in the income statement and as a liability in the balance sheet. The amount of the liability would be calculated based on the tax rate and the amount of the capital gain.
4. Recording of any related expenses: If there were any expenses related to the sale of the asset (such as brokerage fees or legal fees), those expenses would also be recorded in the income statement as operating expenses.

It's worth noting that the exact accounts and transactions used to record capital gains may vary depending on the specific organization's accounting policies and practices. However, the general principle is that a capital gain represents a profit on the sale of an asset and would be recorded in the financial statements as a debit to the capital gains account and a credit to the relevant asset account.

In which countries do Capital gains tax apply for businesses?

Capital gains tax (CGT) for businesses, also known as corporate capital gains tax, is applicable in various countries around the world.

Capital gains tax (CGT) is a tax imposed on the profit or gain realized from the sale or disposal of certain assets, known as capital assets. The specific rules and rates regarding capital gains tax vary from country to country. This information is based on some countries where capital gains tax typically applies. Here are a few examples:

Here are some examples of countries where capital gains tax typically applies to businesses:

1. United States: In the United States, businesses are subject to corporate capital gains tax on the profit or gain realized from the sale or disposal of capital assets. The tax rate for corporate capital gains varies based on the type of asset and the holding period.
2. United Kingdom: Businesses in the United Kingdom are subject to capital gains tax on the sale or disposal of capital assets. The tax rate for capital gains depends on the type of asset and the business's tax status.
3. Canada: Canadian businesses are subject to capital gains tax on the sale or disposition of capital assets. Corporations are required to report and pay tax on their net capital gains, with specific rules

and rates applicable to different types of assets.

4. Australia: Businesses in Australia are subject to capital gains tax on the sale or disposal of capital assets. The tax is payable by companies on their net capital gains, with various exemptions, concessions, and discounts available based on factors like the type of asset and the length of ownership.
5. Germany: In Germany, businesses are subject to capital gains tax, known as Körperschaftsteuer, on the sale or disposal of capital assets. The tax rates and rules depend on the type of asset and the business's tax status.
6. South Africa: South African businesses are subject to capital gains tax on the disposal of capital assets. The tax is payable by companies on their net capital gains, with different rates and exemptions applicable depending on the asset and the business's tax status.
7. France: French businesses are subject to corporate capital gains tax, called Impôt sur les plus-values des entreprises, on the sale or disposal of capital assets. The tax rates and exemptions depend on various factors, including the type of asset and the business's tax status.

It's important to note that the specific rules, exemptions, thresholds, and rates regarding corporate capital gains tax can vary within each country, and tax laws are subject to change. It is advisable to consult with a tax professional or refer to the relevant tax authority in the specific country to obtain the most up-to-date and accurate information regarding capital gains tax for businesses.

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Customs Duties / Excise tax

What is the difference between Customs Duties and Excise tax?

"*Customs Duties*" and "*Excise Tax*" are both forms of taxes imposed by governments, but they are levied on different types of goods and at different points in the supply chain. Let's explore the differences between the two:

Customs Duties:

- Customs duties, also known as import duties or tariffs, are taxes imposed by a government on goods that are imported into a country from abroad. They are collected by customs authorities at the point of entry (such as ports or border crossings) before the goods are allowed to enter the country.

- Customs duties are typically levied as a percentage of the value of the imported goods, but they can also be imposed based on the weight or quantity of the items.
- The primary purpose of customs duties is to protect domestic industries, regulate trade, and generate revenue for the government. By imposing tariffs on certain imported goods, the government can make them more expensive for consumers, which may encourage the purchase of domestically produced alternatives.
- Customs duties are generally applied to a wide range of goods, including raw materials, finished products, and consumer goods.

Excise Tax:

- Excise tax, on the other hand, is a tax levied on specific goods that are produced domestically or imported into a country. It is often referred to as a "*sin tax*" because it is commonly applied to goods that are considered harmful or non-essential, such as alcoholic beverages, tobacco products, sugary beverages, and certain luxury items.
- Unlike customs duties, which are imposed at the point of entry, excise taxes are levied at the production or manufacturing stage of the goods. The taxes are included in the cost of production, and manufacturers or importers are responsible for paying the tax to the government.
- The main objectives of excise taxes are to discourage the consumption of harmful or non-essential goods, promote public health, and raise revenue for the government.
- Excise tax rates can vary based on the type of goods and may be imposed as a specific amount per unit (e.g., per liter of alcohol) or as a percentage of the product's value.

In summary, the key differences between customs duties and excise tax lie in the types of goods they are applied to, the point at which the tax is levied (importation or production stage), and their objectives. Customs duties are imposed on imported goods at the border, while excise taxes are applied to specific goods produced domestically or imported at the manufacturing stage.

In which countries does Customs and excise duties apply?

Customs and excise duties are taxes levied on goods and certain activities at the border or upon importation or exportation of goods. These duties are typically imposed by national governments and can vary significantly from country to country. Customs duties are specifically applied to goods imported into a country, while excise duties are imposed on specific goods produced domestically or imported.

Customs and excise duties apply in most countries around the world, but the specific rates, regulations, and items subject to these duties can differ widely. Here are some examples of countries where customs and excise duties are commonly levied:

1. United States: The U.S. imposes customs duties on imported goods, and excise duties on specific items like alcohol, tobacco, and firearms.
2. European Union (EU) Countries: Customs duties are applied to goods imported into the EU, while excise duties are imposed on items like alcoholic beverages, tobacco, and energy products.
3. China: China levies customs duties on imports, and excise duties on items like tobacco, alcohol, and luxury goods.
4. India: India imposes customs duties on imported goods, and excise duties on various items including petroleum products, alcohol, and tobacco.
5. Brazil: Brazil applies customs duties on imports, and excise duties on items like alcoholic beverages, tobacco, and petroleum products.
6. United Kingdom: The UK imposes customs duties on imports, and excise duties on items such as alcohol, tobacco, and fuel.
7. Canada: Canada imposes customs duties on imports, and excise duties on items like alcohol, tobacco, and certain petroleum products.
8. Australia: Australia applies customs duties on imported goods, and excise duties on items like alcohol, tobacco, and petroleum products.
9. Japan: Japan levies customs duties on imports, and excise duties on specific items like alcohol and tobacco.

These are just a few examples, and customs and excise duties are prevalent in numerous other countries as well. It's important to note that the specific rates, exemptions, and regulations for customs and excise duties can change, so businesses engaged in international trade or dealing with goods subject to excise duties should always be aware of the current requirements and seek professional advice to ensure compliance with the respective country's customs and excise regulations.

If Excise Tax is applicable to a business, should there be a separate account under current liabilities?

If excise tax is applicable to a business, there should be a separate account under current liabilities to record the excise tax payable. This account is used to track the amount of excise tax that the business owes to the government for the specific goods subject to the tax.

The excise tax payable account is a short-term liability because the tax is generally due for payment shortly after the production or importation of the goods. As a current liability, it reflects the company's obligation to settle the excise tax in the near future.

The excise tax payable account is typically classified under the current liabilities section on the company's balance sheet, alongside other short-term obligations like accounts payable, accrued expenses, and short-term borrowings. Properly categorizing excise tax as a current liability provides a clear representation of the company's short-term financial obligations, which is important for assessing its liquidity and financial health.

When the excise tax is paid to the government, the excise tax payable account is debited to reduce the liability, and the cash or bank account is credited to reflect the payment. Regular and accurate accounting for excise tax ensures compliance with tax regulations and helps the business manage its financial responsibilities effectively.

Customs and excise duties - What would the typical transactions and accounts be?

Customs and excise duties involve various financial transactions and accounts that businesses need to manage for importation, exportation, and the production or sale of specific goods subject to these duties. Here are some typical transactions and accounts related to customs and excise duties:

1. Customs Duties on Imports:
    - Transaction: When goods are imported into a country, the importer is required to pay customs duties at the border or upon entry.
    - Account: An account should be created to track customs duties payable on imports. This account records the amount of customs duties incurred on imported goods until they are paid.
2. Customs Duties on Exports:
    - Transaction: In some countries, customs duties may apply to certain goods exported. Exporters are responsible for paying these duties before shipping the goods.
    - Account: An account should be created to track customs duties payable on exports. This account records the amount of customs duties incurred on exported goods until they are paid.
3. Excise Duties on Production or Manufacture:
    - Transaction: Excise duties are imposed on the production or manufacture of specific goods domestically.
    - Account: An account should be established to track excise duties payable on goods produced or manufactured. This account records the amount of excise duties incurred on the production

or manufacturing process.

4. Excise Duties on Imports:
    - Transaction: Excise duties may also apply to certain imported goods. Importers are required to pay these duties upon entry.
    - Account: An account should be created to track excise duties payable on imported goods. This account records the amount of excise duties incurred on imported goods until they are paid.
5. Duty Refunds or Drawbacks:
    - Transaction: In some cases, businesses may be eligible for duty refunds or drawbacks when exporting goods or re-exporting previously imported goods.
    - Account: An account should be set up to track duty refunds or drawbacks owed to the business. This account records the amount of duty refunds or drawbacks received.
6. Customs Brokerage Fees:
    - Transaction: Businesses often engage customs brokers to handle import/export documentation and compliance. Customs brokerage fees are charged for these services.
    - Account: An account should be created to track customs brokerage fees payable. This account records the amount of fees incurred for customs brokerage services.
7. Excise Duty Exemptions or Waivers:
    - Transaction: Some goods may be exempt from excise duties based on specific criteria or government policies.
    - Account: An account should be established to track any excise duty exemptions or waivers granted to the business.

By maintaining accurate records and setting up the appropriate accounts, businesses can effectively manage customs and excise duties, comply with regulations, and accurately report these transactions in their financial statements and tax returns. It's crucial to seek guidance from accounting professionals or customs experts to ensure proper handling of customs and excise duties, as the rules and requirements can vary depending on the country and the nature of the goods involved.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

Business tax

What is business taxes?

Business taxes refer to the taxes that businesses are required to pay to the government on their income, profits, and other financial activities. These taxes are essential for funding various public services and government functions. The specific types and rates of business taxes vary depending on the country and its tax laws.

Here are some common types of business taxes:

1. Income Tax: Just like individuals, businesses are subject to income tax on their profits. The tax rate is typically based on the net income of the business, which is calculated by subtracting allowable deductions and expenses from the total revenue.
2. Corporate Tax: Many countries impose a specific tax on corporations or companies. This tax is applied to the profits earned by the company during a financial year.
3. Value Added Tax (VAT) or Goods and Services Tax (GST): These are indirect taxes that are levied on the sale of goods and services at each stage of production or distribution. Businesses collect these taxes from their customers and then remit the amount to the government.
4. Payroll Taxes: These taxes are withheld from employees' wages by the employer and are paid to the government. They include taxes like Social Security and Medicare in the United States or similar social security contributions in other countries.
5. Property Tax: Businesses that own real property, such as land, buildings, or machinery, may be required to pay property taxes based on the value of those assets.
6. Excise Tax: This tax is levied on specific goods, such as alcohol, tobacco, gasoline, or luxury items.
7. Import and Export Taxes: Businesses involved in international trade may be subject to taxes on imports and exports, known as customs duties or tariffs.

It's important for businesses to comply with their tax obligations and keep accurate financial records. Failing to do so can lead to penalties, fines, and legal consequences. Many businesses seek the assistance of accountants or tax professionals to ensure they meet their tax responsibilities and take advantage of available deductions and credits.

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Corporate tax

What is Corporate Tax?

Corporate tax, also known as company tax or corporate income tax, is a direct tax imposed on the profits earned by corporations or businesses. It is one of the primary forms of business taxes and is levied by governments to generate revenue for funding public services and government functions. Corporate tax rates and regulations vary from country to country and can be influenced by factors such as the company's size, industry, and location.

Key points about corporate tax:

1. Taxable Income: Corporate tax is usually calculated based on the company's net income or profits, which is the total revenue earned by the business minus allowable deductions and expenses. These deductions can include operating expenses, employee salaries, depreciation of assets, interest on loans, and other legitimate business expenses.
2. Separate Legal Entity: Corporations are considered separate legal entities from their owners (shareholders). As a result, they are subject to corporate tax on their earnings, distinct from the personal income taxes of shareholders.
3. Corporate Tax Rate: The corporate tax rate is the percentage of a company's taxable income that it must pay as tax to the government. The tax rate can vary significantly between countries and can also depend on the company's size and level of income.
4. Double Taxation: In some jurisdictions, corporate tax can lead to double taxation, where both the company's profits are taxed, and then shareholders may also be subject to personal income tax when they receive dividends or capital gains from their shares.
5. Tax Incentives and Deductions: Many countries offer tax incentives, credits, or deductions to businesses to encourage investments, research and development, job creation, and other activities that promote economic growth.
6. Tax Planning: Companies may engage in tax planning strategies to legally minimize their tax liabilities, such as optimizing deductions, utilizing tax credits, and structuring their operations in a tax-efficient manner.
7. Global Corporate Taxation: Multinational corporations face complex tax considerations because they operate in multiple countries, each with its own corporate tax laws and regulations. This can lead to international tax planning and the use of tax havens to reduce overall tax burdens.

Overall, corporate tax is a critical source of government revenue and plays a significant role in shaping

business decisions and economic activities within a country.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Franchise tax

What is franchise tax?

Franchise tax is a type of tax imposed on certain business entities by some states in the United States. It is not related to the franchise fees paid by businesses to use a company's brand name or business model. Instead, franchise tax is a state-level tax that applies to specific types of corporations and limited liability companies (LLCs) that are registered or doing business in the state.

The franchise tax is often based on the company's net worth or capital, the number of shares issued, or a combination of these factors. Each state that imposes a franchise tax may have its own rules and methods for calculating the tax liability. Some states use the term "*franchise tax*," while others may refer to it as a "*privilege tax*" or a "*business entity tax*."

The purpose of the franchise tax is to generate revenue for the state's government, and it is typically separate from the income tax that businesses may also be required to pay. The franchise tax may apply regardless of whether the business is profitable or not.

It's important to note that not all states impose a franchise tax, and the requirements and rates can vary significantly from one state to another. Some states may have minimum taxes for small businesses, while others may have different tax rates based on the size and type of business entity.

As tax laws and regulations can change over time, businesses should check with the specific state's tax authorities or consult with a tax professional to understand the franchise tax requirements and obligations in the state where they operate or are registered.

In which states of the US is franchise tax imposed?

In which States is this applicable in the United States?

As of ChatGPT's last update in September 2021, franchise taxes are imposed in the following states in the United States:

1. Alabama - Alabama imposes a franchise tax on corporations doing business in the state. The franchise tax rates vary depending on the corporation's net worth or capital value.

2. Arkansas - Arkansas imposes a franchise tax on corporations and limited liability companies (LLCs) doing business in the state. The tax is based on the entity's capital or net worth and is calculated using a prescribed formula.
3. California - California imposes a franchise tax on corporations and LLCs registered in the state. The tax is based on the company's net income or a minimum franchise tax, whichever is greater. The minimum franchise tax applies even if the company has no net income.
4. Delaware - Delaware imposes an annual franchise tax on corporations incorporated in the state. The franchise tax amount is based on the corporation's authorized shares or the number of issued shares and their par value.
5. Georgia - Georgia imposes an annual corporate net worth tax, also known as a franchise tax, on corporations registered in the state. The tax is calculated based on the company's net worth and is subject to a minimum tax amount.
6. Illinois - Illinois imposes a corporate franchise tax on corporations doing business in the state. The tax is based on the company's paid-in capital and is calculated using specified rates. Certain corporations, such as financial institutions, are subject to different franchise tax rules.
7. Louisiana - Louisiana imposes a corporate franchise tax on corporations registered in the state. The tax is based on the company's capital or net worth and is calculated using a prescribed formula.
8. Mississippi - Mississippi imposes a franchise tax on corporations doing business in the state. The tax is based on the company's capital or net worth and is calculated using a specified rate.
9. Missouri - Missouri imposes a corporate franchise tax on corporations and LLCs doing business in the state. The tax is based on the company's net worth or book value and is calculated using a prescribed formula.
10. New York - New York imposes a corporate franchise tax on corporations doing business in the state. The tax is based on the company's entire net income and capital base and is calculated using specified rates.
11. North Carolina - North Carolina imposes a franchise tax on corporations and LLCs registered in the state. The tax is based on the company's net worth or book value and is calculated using specified rates.
12. Oklahoma - Oklahoma imposes a corporate franchise tax on corporations doing business in the state. The tax is based on the company's net worth or book value and is calculated using specified rates.
13. Tennessee - Tennessee imposes a franchise tax on corporations and LLCs registered in the state. The tax is based on the company's net worth or book value and is calculated using specified rates.
14. Texas - Texas imposes a franchise tax, also known as the "margin tax," on corporations and LLCs doing

business in the state. The tax is based on the company's margin or apportioned revenue, and the calculation varies based on the entity's classification and business activities.

Please note that franchise tax laws and rates may change, and it's recommended to consult the respective state's Department of Revenue or a tax professional for the most up-to-date and specific information related to franchise taxes in each state. Additionally, some states may have different types of franchise taxes, so the specific details and rates may vary from state to state.

In which other countries around the world other than the US is franchise tax imposed?

As of ChatGTP's last update in September 2021, franchise taxes, similar to those in the United States, are not common in other countries. The concept of a "*franchise tax*" as it exists in the US, which is a tax on businesses for the privilege of operating as a corporation or limited liability company, is not widely adopted in other countries.

However, different countries may have various forms of business taxes, including corporate income taxes, value-added taxes (VAT), payroll taxes, and other specific industry-related taxes. These taxes vary from country to country, and their structure and rates may be quite different from the franchise tax in the US.

If you are interested in a specific country's tax system, it's best to consult official tax authorities or seek advice from local tax professionals for the most up-to-date and accurate information. Tax laws and regulations can change over time, so it's essential to have the latest information when dealing with tax matters in any country.

In the Chart of accounts, what is the basic accounts for franchise tax transactions?

In the chart of accounts for a business, the specific accounts for franchise tax transactions may vary depending on the accounting system and the company's individual needs. However, I can provide you with some general account categories that are commonly used for recording franchise tax-related transactions:

1. Franchise Tax Payable (Liability Account): This account is used to record the amount of franchise tax that the company owes to the relevant tax authorities but has not yet paid. It is a liability account since the tax is an obligation of the company until it is remitted.
2. Franchise Tax Expense (Expense Account): This account is used to record the expense incurred by the company for paying franchise taxes. It reflects the amount of tax paid during a specific accounting period.
3. Franchise Tax Refund (Asset Account): If the company overpays the franchise tax and is entitled to a

refund, this account is used to track the refund amount due from the tax authorities.

4. Franchise Tax Receivable (Asset Account): In some cases, the company may have overpaid franchise taxes and is eligible to receive a credit or offset against future tax payments. This account tracks the amount of credit receivable.
5. Deferred Franchise Tax (Asset or Liability Account): Depending on the accounting method used, some companies may need to recognize franchise tax as an asset or a liability if the tax payment spans multiple accounting periods. This account is used to record the deferred portion of the tax.

It's important to note that the chart of accounts can be customized to fit the specific needs and requirements of the business. Additionally, businesses often consult with accountants or financial experts to set up their chart of accounts accurately and efficiently. The accounts mentioned above are just general examples, and the actual accounts used may differ from company to company based on their unique circumstances and accounting practices.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Withholding tax

What is withholding tax?

Withholding tax is a tax that is deducted or withheld at the source of income before it is paid to the recipient. It is a method used by governments to collect taxes on various types of income, such as wages, interest, dividends, royalties, and certain other payments. The entity responsible for making the payment is required to withhold a portion of the payment and remit it directly to the government on behalf of the recipient.

The purpose of withholding tax is to ensure that individuals and businesses pay their income taxes in a timely manner. By deducting the tax at the source of income, governments can ensure a steady flow of revenue and reduce the risk of tax evasion. Withholding tax is particularly common when dealing with cross-border transactions, where the tax jurisdiction of the payer and the recipient may be different.

The withholding tax rate varies depending on the type of income, the tax laws of the jurisdiction, and any applicable tax treaties between countries. In some cases, the withheld tax can be used as a credit against the recipient's total tax liability when they file their tax return.

It's important to note that withholding tax regulations and rates can differ significantly from one country to another, so it's advisable to consult the tax authorities or a tax professional in the relevant jurisdiction to understand the specific rules and requirements related to withholding tax.

In which countries is withholding tax applicable?

Withholding tax is applicable in many countries around the world. The specific rules, rates, and types of income subject to withholding tax can vary widely from one country to another. Here are a few examples of countries where withholding tax is commonly applied:

1. United States: The U.S. applies withholding tax to various types of income, including wages, dividends, interest, and certain other payments. Non-residents who earn income in the U.S. may be subject to withholding tax.
2. United Kingdom: The UK imposes withholding tax on interest income, royalties, and certain other payments made to non-residents.
3. Canada: Canada has withholding tax on payments such as dividends, interest, and royalties made to non-residents.
4. Germany: Germany applies withholding tax to dividends, interest, and royalties paid to non-residents.
5. France: France has withholding tax on dividends, interest, and royalties paid to non-residents.
6. Australia: Australia imposes withholding tax on various types of income paid to non-residents, including interest, dividends, and royalties.
7. India: India applies withholding tax on various types of payments made to non-residents, including interest, royalties, and certain technical service fees.
8. Japan: Japan has withholding tax on dividends, interest, royalties, and certain other payments made to non-residents.
9. China: China applies withholding tax to various types of income paid to non-residents, including dividends, interest, royalties, and service fees.
10. Singapore: Singapore has withholding tax on certain types of payments made to non-residents, such as interest, royalties, and technical service fees.

These are just a few examples, and the list is not exhaustive. The applicability of withholding tax depends on the specific tax laws and regulations of each country. Additionally, many countries have tax treaties in place with other nations to mitigate double taxation and adjust withholding tax rates for certain types of income.

If you are involved in cross-border transactions or have income from foreign sources, it's recommended to consult with a tax professional or the tax authorities in the relevant countries to understand the specific withholding tax requirements that apply to your situation.

Is withholding tax applicable to South Africa?

Yes, withholding tax is applicable in South Africa. South Africa has a withholding tax system that requires certain payments to have tax withheld at the source before being paid to the recipient. The purpose of withholding tax in South Africa is to ensure the collection of taxes and to regulate compliance with tax laws, particularly for payments made to non-residents.

As of ChatGPT's last knowledge update in September 2021, here are some common types of withholding taxes applicable in South Africa:

1. Dividends Tax: Dividends paid by South African companies to shareholders are subject to dividends tax. The tax is withheld by the company distributing the dividends before they are paid to shareholders.
2. Interest Withholding Tax: Interest payments made by South African entities to non-residents are subject to interest withholding tax. The tax is withheld by the payer before the interest is remitted to the non-resident recipient.
3. Royalties Withholding Tax: Royalty payments made by South African entities to non-residents for the use of intellectual property rights are subject to royalties withholding tax. The tax is withheld by the payer before the royalty payment is made to the non-resident.
4. Service Fees Withholding Tax: Payments made to non-residents for certain services rendered are subject to service fees withholding tax. The tax is withheld by the payer before the service fee payment is remitted to the non-resident.

It's important to note that tax laws and regulations can change over time, and new developments might have occurred since my last update. If you're dealing with payments to or from South Africa, or if you have any specific questions about withholding taxes in South Africa, I recommend consulting the South African Revenue Service (SARS) website or seeking advice from a tax professional who is up to date with the latest regulations.

To which business types of ownership is withholding tax applicable?

Withholding tax can be applicable to various types of business ownership structures, depending on the jurisdiction and the type of income being generated. Here are some common business ownership types to which withholding tax may apply:

1. Corporations: Both domestic and foreign corporations may be subject to withholding tax on certain types of income, such as dividends, interest, royalties, and certain service fees. The withholding tax rate

and rules can vary based on the specific country's tax laws and any applicable tax treaties.

2. Partnerships: Partnerships, including limited partnerships and limited liability partnerships, may be subject to withholding tax on income distributions to partners. The tax treatment can differ depending on whether the partners are residents or non-residents.
3. Sole Proprietorships: Withholding tax is less commonly applied to sole proprietorships, as the business income is often reported directly on the owner's personal tax return. However, if a sole proprietorship makes payments to non-residents for services, interest, or other income types, withholding tax might apply.
4. Limited Liability Companies (LLCs): In jurisdictions where LLCs are recognized, they might be subject to withholding tax on distributions made to non-resident members. The tax treatment can vary based on the specific tax laws of the country.
5. Branches of Foreign Companies: A foreign company operating a branch in a different country might be subject to withholding tax on certain income generated in the host country. This could include payments such as dividends, interest, and royalties.
6. Joint Ventures: Joint ventures involving both domestic and foreign partners can also be subject to withholding tax on their income distributions, depending on the tax laws of the relevant jurisdiction.
7. Trusts: Trusts might be subject to withholding tax on distributions made to beneficiaries, particularly if those beneficiaries are non-residents.

It's important to note that the applicability of withholding tax to different business ownership types can vary significantly from one country to another. Additionally, the types of income that are subject to withholding tax and the rates applied can differ based on the specific tax laws of each jurisdiction. If you are operating a business or have ownership interests in different countries, it's advisable to seek guidance from tax professionals who are familiar with the relevant local tax regulations to ensure compliance.

What is the common transactions for withholding tax?

Common transactions involving withholding tax typically occur when a business or individual makes payments to vendors, contractors, or other parties and is required to withhold a portion of the payment for tax purposes. The withheld amount is then remitted to the tax authorities on behalf of the payee. Here are some common transactions that involve withholding tax:

1. Payment to Vendors/Suppliers:
    - A business pays an invoice to a vendor for goods or services rendered.
    - As part of the payment process, the business calculates and withholds the applicable withholding tax percentage from the payment.

2. Payment to Contractors/Freelancers:
    - A company pays a contractor or freelancer for services provided.
    - The company calculates and withholds the required withholding tax amount from the payment before remitting the remaining amount to the contractor.
3. Dividend Payments:
    - A corporation makes dividend payments to its shareholders.
    - The corporation deducts withholding tax from the dividend payment based on the tax rate applicable to the recipient.
4. Interest Payments:
    - A borrower makes interest payments to a lender or bondholder.
    - The borrower withholds and remits the applicable withholding tax on the interest payment to the tax authorities.
5. Royalty Payments:
    - A company pays royalties to another entity for the use of intellectual property.
    - The company deducts and remits the appropriate withholding tax on the royalty payment.
6. Rental Income Payments:
    - A landlord pays rental income to a non-resident property owner.
    - The landlord withholds and pays the required withholding tax on the rental income.
7. Cross-Border Transactions:
    - Businesses engaged in international trade and services may need to withhold tax on payments made to non-resident suppliers, contractors, or service providers.

In each of these transactions, the withholding tax amount is calculated based on the applicable tax rate, which can vary depending on the type of income, the jurisdiction, and any relevant tax treaties. The withheld amount is then reported to the tax authorities and remitted according to the specified schedule and regulations.

Proper documentation and reporting are essential for these transactions to ensure compliance with tax laws and regulations. It's recommended to work closely with accounting professionals and tax advisors to accurately calculate, withhold, report, and remit withholding taxes in accordance with the applicable laws in your jurisdiction.

How would withholding tax be reflected in the chart of accounts?

Withholding tax can be reflected in the chart of accounts as a separate account to track the amount of tax withheld before making payments to vendors, contractors, or other payees. The specific account structure can vary based on the accounting system you're using and the level of detail you want to maintain. Here's a general example of how you might include withholding tax in your chart of accounts:

Account Type: Liability (Current Liability) Account Name:

Withholding Tax Payable Account Number: 2100 (Example) Description: This account is used to track withholding taxes that have been deducted from payments to vendors, contractors, or other payees but have not yet been remitted to the tax authorities.

When you make a payment to a vendor or contractor that requires withholding tax, you would record the transaction in your accounting system as follows:

Debit: Expense Account Credit: Accounts Payable Credit: Withholding Tax Payable

In this entry, the expense account represents the amount you owe to the vendor or contractor for their services or goods. The credit to the accounts payable account reflects the liability you owe to the vendor or contractor. The credit to the withholding tax payable account shows the amount of withholding tax that you've deducted from the payment.

As you remit the withholding tax to the tax authorities, you would reduce the balance in the "Withholding Tax Payable" account by recording a journal entry like this:

Debit: Withholding Tax Payable Credit: Cash/Bank Account

This entry shows that you're reducing the liability in the withholding tax payable account by paying the withheld tax amount to the tax authorities.

Keep in mind that the specific account names, numbers, and structures can vary based on your organization's preferences and the accounting software you're using. It's important to consult with your accounting professional to ensure that your chart of accounts accurately reflects your business's financial transactions and meets any legal or regulatory requirements related to withholding tax reporting.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Provisional tax

What is provisional tax?

Provisional tax is a system used in many countries to collect income tax from individuals and businesses in a timely manner, rather than waiting until the end of the financial year. It is a method for taxpayers to make payments towards their income tax liability in advance, usually in multiple installments throughout the year.

The purpose of provisional tax is to ensure that taxpayers make timely payments towards their eventual income tax liability, thus preventing a large tax burden from accumulating at the end of the tax year. This is particularly important for individuals and businesses with fluctuating or irregular incomes, as well as for self-employed individuals and freelancers who do not have taxes withheld from their earnings like traditional employees do.

The system generally works as follows:

1. Estimation: Taxpayers are required to estimate their total income for the current tax year and calculate their expected tax liability. This can include income from various sources such as business profits, investments, rental income, etc.
2. Installments: Based on this estimated tax liability, taxpayers are required to make regular payments, often in the form of installments, throughout the tax year. These installments are usually due on specific dates during the year.
3. Adjustments: At the end of the tax year, when the actual income and deductions are known, taxpayers reconcile their estimated tax payments with their actual tax liability. If they have overpaid, they may receive a refund. If they have underpaid, they may need to pay the remaining tax balance.

It's important to note that the rules and procedures for provisional tax can vary significantly from one country to another. Some countries have complex systems with different payment schedules and methods for calculating the estimated tax, while others have simpler systems. Taxpayers are usually required to keep accurate records of their income, expenses, and estimated tax payments to ensure compliance with the provisional tax requirements.

If you need specific information about provisional tax in a particular country, it's advisable to consult the tax authority or a tax professional in that jurisdiction.

In which countries is provisional tax applicable?

Provisional tax systems are used in various countries around the world to collect income tax payments in advance. However, the specific rules, regulations, and terminology may differ from one country to another. Here are some countries where provisional tax or similar concepts are applicable:

1. New Zealand: New Zealand has a well-known provisional tax system. Individuals and businesses with a

certain level of income are required to make regular payments towards their income tax liability based on their estimated tax for the year.

2. Australia: Australia has a Pay As You Go (PAYG) system that functions similarly to provisional tax. Under PAYG, individuals and businesses make regular tax payments throughout the year to cover their expected tax liability.
3. South Africa: In South Africa, provisional tax is paid by individuals and businesses that earn income that is not subject to employees' tax (PAYE). Taxpayers make two or three installment payments based on their estimated tax liability.
4. Canada: Canada has a system called "*installment payments*", where individuals with substantial tax liabilities are required to make regular payments throughout the year to cover their income tax liability.
5. *United States*: While the United States doesn't have a formal provisional tax system, the estimated tax payment requirement serves a similar purpose. Individuals who expect to owe a certain amount of tax that isn't covered by withholding need to make quarterly estimated tax payments.
6. United Kingdom: The United Kingdom has a system called "*Payments on Account*" for self-employed individuals and certain other taxpayers. This requires making advance payments toward the upcoming year's tax liability.
7. India: India has a system of Advance Tax, where taxpayers are required to pay their tax liability in installments if their tax liability exceeds a certain threshold. This applies to individuals, companies, and firms.
8. Ireland: Ireland's Pay As You Earn (PAYE) system for income tax includes a "*Preliminary End of Year Statement*" (PEOYS) process, which allows taxpayers to make payments towards their expected tax liability before the end of the tax year.
9. Singapore: In Singapore, individuals who have non-salary income are required to make regular payments called "*Estimated Chargeable Income*" (ECI) to cover their potential tax liability.

These are just a few examples, and the specific details of each country's provisional tax system can vary widely. It's important to refer to the tax authority or consult with a tax professional in the specific country to understand the exact rules and requirements related to provisional tax or similar concepts.

How is Provisional tax recorded in the Chart of Accounts?

The way provisional tax is recorded in the Chart of Accounts can vary based on the accounting practices and regulations of the specific country in which you're operating. However, ChatGPT can provide you with a general idea of how provisional tax might be recorded in the Chart of Accounts:

1. Create a Liability Account: Provisional tax payments are essentially prepayments of income tax that

you'll owe in the future. In your Chart of Accounts, you would typically create a liability account to track the amount of provisional tax that you owe. This account might be named something like "Provisional Tax Payable" or "Income Tax Prepayments."

2. Subdivide by Year: If you make provisional tax payments for multiple tax years, you might want to further subdivide the liability account by creating sub-accounts for each year. For example, you could have "Provisional Tax Payable - Year 2023," "Provisional Tax Payable - Year 2024," and so on.
3. Record Payments: When you make a provisional tax payment, you would credit (reduce) the cash or bank account that you used to make the payment, and you would debit (increase) the corresponding provisional tax liability account. This reflects that you've paid money in advance for your future tax liability.
4. Adjustments: At the end of the tax year when your actual tax liability is calculated, you would adjust the provisional tax liability account. If you overpaid, you would debit the provisional tax liability account to reduce the balance, and if you underpaid, you would credit the account to increase the balance.
5. Reclassification: Once the provisional tax liability is reconciled with the actual tax liability, any remaining balance might be reclassified to a regular income tax liability account in your Chart of Accounts.

Remember, the exact account names, numbers, and organization in the Chart of Accounts can vary based on your accounting software, your industry, and the specific requirements of your country's tax regulations. It's always a good idea to work with a qualified accountant or financial professional to set up your Chart of Accounts correctly and ensure compliance with tax laws.

The information provided here is a general guideline and not a substitute for personalized financial or accounting advice. Always consult with professionals familiar with your specific situation and jurisdiction.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Turnover tax

What is Turnover tax?

Turnover tax, also known as gross receipts tax or sales tax, is a type of tax that is assessed on the total revenue or sales generated by a business during a specific period, typically a fiscal quarter or year. Unlike traditional income taxes, which are based on a company's profits, turnover tax is based on the total value of goods sold or services provided, regardless of whether the business is making a profit or not.

Here's how turnover tax generally works:

1. Calculation: The tax authority calculates the tax liability by applying a predetermined tax rate to the total turnover or gross receipts of the business. This rate can vary depending on the jurisdiction, the type of business, and the nature of the goods or services being sold.
2. Reporting: Businesses are also responsible for reporting their total turnover to the tax authority at regular intervals, such as monthly, quarterly, or annually. They must accurately document their sales and transactions for tax purposes.
3. Payment: After calculating the tax liability based on the reported turnover, the business must pay the taxes owed to the tax authority within the specified timeframe.
4. Compliance: Failure to accurately report turnover or pay the required turnover tax can result in penalties and legal consequences.

The main advantage of turnover tax is its simplicity, as it does not require businesses to consider deductions or expenses when calculating their tax liability. However, it can be regressive, meaning that it may disproportionately affect smaller businesses or those with lower profit margins.

It's important to note that the specific rules and rates for turnover tax can vary widely from one jurisdiction to another, and some regions may not have turnover tax systems at all. Businesses should consult with their local tax authorities or seek professional advice to understand how turnover tax applies to their specific situation.

In which countries is Turnover tax applicable?

Turnover tax, or similar taxes based on sales or gross receipts, may be applicable in various countries around the world. However, the specific name, rules, and rates of such taxes can vary significantly from one country to another. Here are a few examples of countries where turnover taxes or similar taxes are used:

1. South Africa: South Africa has a Turnover tax It is based on a business's total turnover or sales, and is submitted using the TT03 Return, where businesses report their total turnover, and the tax liability is calculated based on this turnover.
2. Russia: Russia has a turnover-based tax known as the "Unified Tax on Imputed Income." This tax is applied to certain types of businesses and is calculated based on the estimated income or turnover of the business.
3. Kenya: Kenya has a turnover tax that is applied to small businesses with annual turnovers below a certain threshold. This tax is designed to simplify the tax system for small businesses.
4. Slovenia: Slovenia has a turnover tax called the "Simplified Business Tax." It is applicable to certain

small businesses and is based on their turnover.

5. Taiwan: Taiwan has a turnover tax called the "Business Tax," which is applied to the turnover generated by businesses engaged in various industries.

It's important to note that turnover taxes can take various forms and names in different countries, and they may apply to specific types of businesses or under certain conditions. Additionally, the rates and thresholds for turnover taxes can vary widely. Businesses operating in a particular country should consult with local tax authorities or seek professional advice to understand the specific turnover tax regulations that apply to their situation.

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

---

What is the considerations for taxes in the Chart of Accounts and financial reporting?

General guidance on how businesses should consider taxes and other charges in their chart of accounts and financial statements.

1. Chart of Accounts: When creating a chart of accounts, businesses should include accounts to capture the various taxes, levies, and charges that apply to their specific jurisdiction and industry. This may include accounts for income tax, sales tax/VAT, payroll taxes, property taxes, customs duties, and other relevant taxes and charges.

2. Accrual Accounting: Businesses that use accrual accounting will need to make adjustments to their financial statements to recognize taxes and charges in the period they are incurred, regardless of when they are paid. For example, if income tax is payable for the current financial year but will be paid in the next year, an adjusting entry should be made to recognize the tax expense in the current year's financial statements.

3. Specific Industry Considerations: Some industries may have specific taxes or levies that apply to them. For example, certain environmental taxes or industry-specific levies may need to be accounted for separately in the chart of accounts.

4. Different Levels of Government: Businesses operating in certain countries may need to account for taxes and charges imposed by the central government, provincial or state governments, and local municipalities. Each level of government may have its own tax rates and regulations.

5. Accounting Standards: The chart of accounts and financial statements should comply with the relevant accounting standards applicable in the jurisdiction. International Financial Reporting Standards (IFRS) or Generally Accepted Accounting Principles (GAAP) may be followed, depending on the country and industry.
6. Compliance and Reporting: Businesses should ensure they are compliant with all tax and charge regulations, including timely payment and accurate reporting to the relevant government authorities.
7. Consultation with Professionals: Given the complexity of taxes and charges, businesses should seek guidance from tax professionals, accountants, or financial advisors to ensure their chart of accounts and financial statements accurately reflect the applicable taxes and charges.

It's important for businesses to stay informed about the specific taxes and charges that apply to their jurisdiction and industry and to tailor their chart of accounts and financial reporting accordingly. This will ensure accurate financial statements and compliance with relevant tax and regulatory requirements.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's HTML5 template

Taxes in South Africa

South Africa (ZA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in South Africa (ZA):

1. Value-Added Tax (VAT):
    - VAT is a consumption tax applied to the supply of goods and services in South Africa.
    - The standard VAT rate is 15%, and it applies to most goods and services, with some exceptions.
    - Certain essential items, such as basic foodstuffs and healthcare services, may be zero-rated or exempt from VAT.
    - Registered businesses are required to collect VAT on behalf of the government and submit regular VAT returns.
2. Income Tax:
    - South Africa has a progressive income tax system, with higher income earners paying higher

tax rates.

- Individual taxpayers are subject to personal income tax, while businesses are subject to corporate income tax.
- There are various tax deductions, rebates, and credits available to individuals and businesses.
- Tax rates and brackets may change from year to year, so it's important to stay updated on the latest changes.

3. Capital Gains Tax (CGT):
   - Capital gains tax is applied to the profit made from the sale of assets, such as property, shares, and investments.
   - Individuals and businesses are required to pay CGT on the disposal of assets.
   - Different rates and exemptions may apply depending on the type of asset and the taxpayer's status.
4. Dividends Tax:
   - Dividends tax is applied to dividends paid to shareholders.
   - The tax rate is currently 20%, but lower rates or exemptions may apply in certain cases, such as for qualifying companies.
5. Secondary Tax on Companies (STC):
   - The Secondary Tax on Companies (STC), also known as the "*dividend tax*," was a tax levied on dividends declared and paid by South African companies to shareholders.
   - As of April 1, 2012, STC was replaced by the Dividends Tax, which is a tax on dividends declared and paid by companies to shareholders.
6. Estate Duty and Donations Tax:
   - Estate duty is a tax levied on the estate of a deceased person, with rates varying based on the value of the estate.
   - Donations tax is applied to certain gifts and donations made during a person's lifetime.
   - Both taxes are aimed at transferring wealth between generations and discouraging tax avoidance through gifting.
7. Customs and Excise:
   - Customs and excise duties are applied to imported and locally produced goods, as well as

specific goods like alcohol, tobacco, and petroleum products.

- These taxes are collected by the South African Revenue Service (SARS) at the border or point of production.

8. Payroll Taxes:
    - Employers are required to deduct Pay-As-You-Earn (PAYE) tax from employees' salaries and remit it to SARS.
    - Employers also contribute to the Unemployment Insurance Fund (UIF) and the Skills Development Levy (SDL).
9. COID Contributions:
    - COID (Compensation for Occupational Injuries and Diseases) contributions are payments made by employers to provide compensation to employees who are injured, contract diseases, or die in the course of their employment.
    - Employers are required to register with the Compensation Fund and make these contributions to cover potential workplace-related injuries or illnesses.
10. Tax Filing and Compliance:
    - Individuals and businesses are required to register for tax with SARS and comply with the relevant tax obligations.
    - Tax returns are typically filed annually, and payment due dates may vary depending on the type of tax.

Please note that tax laws and regulations can change over time, so it's essential to consult the South African Revenue Service (SARS) or a tax professional for the most up-to-date and specific information related to the tax system in South Africa.

Local and provincial taxes and charges

In addition to the national taxes mentioned earlier, South Africa has various local and provincial taxes and charges levied by municipalities and provincial governments. These taxes and charges are used to fund local and regional services and infrastructure development. Here are some common examples:

Local Municipality Taxes and Charges:

1. Property Rates: Property rates are local taxes levied on property owners by municipalities based on the assessed value of their properties. The rates vary depending on the location and type of property.
2. Sewerage and Sanitation Charges: Municipalities may charge property owners for the provision of

sewerage and sanitation services.

3. Refuse Removal Charges: Property owners may be charged for the collection and disposal of refuse and waste.
4. Water and Electricity Charges: Municipalities provide water and electricity services and charge consumers based on their usage.
5. Special Levies: In certain situations, municipalities may impose special levies on property owners to fund specific projects or improvements within a specific area.
6. Business Licenses and Permits: Businesses operating within a municipality may be required to obtain licenses or permits, for which fees are charged.

Provincial Taxes and Charges:

1. Transfer Duty: In addition to the national transfer duty, some provinces may impose their own transfer duty on the purchase of immovable property.
2. Vehicle License and Registration Fees: Vehicle owners pay registration fees to the relevant provincial authorities for licensing their vehicles.
3. Gambling Taxes: Provinces may impose taxes on gambling activities within their jurisdictions.
4. Environmental Taxes and Levies: Some provinces may introduce environmental taxes and levies to fund environmental conservation and sustainability initiatives.

It's important to note that the specific local and provincial taxes and charges may vary depending on the region and local regulations. Each municipality and province may have its own set of taxes, charges, and fees, which are used to provide essential services and maintain local infrastructure.

As these taxes and charges may change over time, individuals and businesses should consult with their local municipality and provincial authorities or seek advice from tax professionals to stay informed about the current local and provincial tax obligations in South Africa.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

---

United Kingdom (UK) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in the United Kingdom (UK):

1. Value Added Tax (VAT):
    - VAT is a consumption tax applied to the supply of goods and services.
    - The standard VAT rate is 20%, but there are reduced rates (5% and 0%) for certain goods and services.
    - Some goods and services, such as essential food items, are exempt from VAT.
2. Income Tax:
    - The UK has a progressive income tax system, where higher income earners pay higher tax rates.
    - Individual taxpayers are subject to income tax on their earnings from various sources, including employment, self-employment, and investments.
    - The tax rates and thresholds for income tax can change annually in the UK's budget.
3. National Insurance Contributions (NICs):
    - NICs are contributions paid by employees, employers, and self-employed individuals to fund state benefits and pensions.
    - NICs are separate from income tax and are based on the individual's earnings.
4. Capital Gains Tax (CGT):
    - CGT is applied to the profit made from selling assets, such as property, investments, and valuable possessions.
    - Individuals and businesses are subject to CGT, with different rates and exemptions based on factors like the type of asset and the taxpayer's status.
5. Corporation Tax:
    - Businesses are subject to corporation tax on their profits.
    - The corporation tax rate can change and may vary depending on the size of the company and the level of profits.
6. Inheritance Tax:
    - Inheritance tax is applied to the estate of a deceased person.
    - The tax rate is currently 40% on the value of the estate above a certain threshold.
    - There are exemptions and reliefs available for certain transfers and gifts.
7. Stamp Duty and Stamp Duty Land Tax:

- Stamp duty is applied to certain transactions, such as buying shares or land.
- Stamp Duty Land Tax (SDLT) is a tax on property transactions.
- Different rates and thresholds apply depending on the nature of the transaction.

8. Customs and Excise:
    - Customs duties and excise duties are applied to imported and locally produced goods, as well as specific products like alcohol, tobacco, and petroleum.
9. Council Tax:
    - Council tax is a local tax levied by local authorities to fund local services.
    - The amount of council tax depends on the valuation band of the property and the local authority's rate.
10. Vehicle Excise Duty (VED):
    - Vehicle Excise Duty, commonly known as road tax or car tax, is a tax payable on most vehicles used or parked on public roads in the UK.
    - The amount of VED is determined by factors such as the vehicle's emissions, fuel type, and date of registration.
11. Climate Change Levy (CCL):
    - The Climate Change Levy is an environmental tax applied to energy use in businesses and industrial processes.
    - It is designed to encourage energy efficiency and reduce greenhouse gas emissions.
12. Tax Filing and Compliance:
    - Individuals and businesses are required to register for tax with HM Revenue & Customs (HMRC) and comply with their tax obligations.
    - Tax returns are typically filed annually, and payment due dates may vary depending on the type of tax.

Please note that tax laws and regulations can change over time, so it's important to consult HM Revenue & Customs (HMRC) or a tax professional for the most up-to-date and specific information related to the tax system in the United Kingdom.

In addition to taxes in United Kingdom - what is local taxes and charges?

In the United Kingdom, local taxes and charges are levied by local authorities and are separate from the national taxes imposed by the central government. These local taxes and charges are used to fund local services and infrastructure development. The specific taxes and charges can vary depending on the region, as different local authorities may have their own funding needs and priorities. Here are some common examples of local and provincial taxes and charges in the UK:

Local Council Taxes:

- Council Tax: Council tax is a local property tax levied by local authorities in England, Scotland, and Wales. It is based on the value of residential properties and the number of occupants. Each property is placed in a specific council tax band, and the tax rates vary by band and local authority.

Business Taxes and Charges:

- Business Rates: Business rates, also known as non-domestic rates, are a tax on non-residential properties used for business purposes, such as offices, shops, and factories. The rates are based on the rateable value of the property and are set by the local authority.

Other Local Charges:

- Parking Charges: Local authorities may charge for parking in certain areas, such as city centers or designated parking zones.
- Planning Fees: Local authorities charge fees for planning applications and other planning-related services.
- Licensing Fees: Businesses may be required to obtain various licenses from local authorities, and fees are charged for these licenses.
- Garden Waste Collection: Some local authorities charge a fee for the collection of garden waste.
- Resident Parking Permits: Local residents may be required to pay for parking permits in residential areas with controlled parking zones.

It's important to note that the specific local taxes and charges can vary by region and may be subject to change. Different local authorities have the flexibility to set their own rates and fees to meet their local funding needs. Businesses and individuals should check with their local authority to understand the local taxes and charges that apply in their specific area.

In addition to the local taxes and charges, the UK also has devolved administrations in Scotland, Wales,

and Northern Ireland, each with its own tax-raising powers and responsibilities for certain areas of taxation and public services. These devolved administrations may have additional taxes and charges specific to their regions.

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Taxes in Australia

Australia (AU) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Australia (AU):

1. Goods and Services Tax (GST):
    1. GST is a broad-based consumption tax applied to most goods and services in Australia.
    2. The standard GST rate is 10% on the value of goods and services consumed.
    3. Certain goods and services, such as basic food items, medical services, and education, may be GST-free or input-taxed.
2. Goods and Services Tax (GST) on Imported Goods :
    - Since July 1, 2018, Australia applies the Goods and Services Tax (GST) to imported goods with a value of AUD 1,000 or less.
    - Overseas businesses that meet certain registration requirements are required to collect and remit GST on these imported goods.
3. Income Tax:
    - Australia has a progressive income tax system, with higher income earners paying higher tax rates.
    - Individual taxpayers are subject to income tax on their earnings from various sources, including employment, business, and investments.
    - The tax rates and income thresholds for income tax can change annually in the federal budget.
4. Capital Gains Tax (CGT):
    - CGT is applied to the profit made from selling assets, such as property, investments, and

valuable possessions.

- Individuals and businesses are subject to CGT, with different rates and exemptions based on factors like the type of asset and the taxpayer's status.

5. Fringe Benefits Tax (FBT):
   - FBT is applied to non-cash benefits provided by employers to employees as part of their remuneration package.
   - Employers are responsible for paying FBT on these benefits at a rate equivalent to the top marginal tax rate.
6. Superannuation Contributions Tax:
   - Superannuation is the Australian retirement savings system, and contributions to super funds are subject to tax concessions.
   - Contributions made to super funds are generally taxed at a concessional rate, and withdrawals in retirement may be tax-free or subject to concessional rates.
7. Customs and Excise:
   - Customs duties and excise duties are applied to imported and locally produced goods, as well as specific products like alcohol, tobacco, and petroleum.
8. Medicare Levy:
   - The Medicare Levy is a 2% tax applied to most taxpayers to help fund Australia's public healthcare system (Medicare).
   - Some taxpayers may be exempt or receive a reduction based on their income and circumstances.
9. Medicare Levy Surcharge (MLS):
   - The Medicare Levy Surcharge is an additional tax applied to high-income earners who do not have private hospital insurance.
   - The surcharge aims to encourage individuals to take out private health insurance and relieve pressure on the public health system.
10. Payroll Tax:
    - Payroll tax is a state and territory tax applied to the wages paid by employers.
    - It is imposed when the total wages paid by an employer exceed a certain threshold.
    - The payroll tax rates and thresholds can vary by state and territory.

11. Pay As You Go (PAYG) Withholding:
    1. PAYG withholding is a system where employers deduct income tax from employees' salaries and remit it to the Australian Taxation Office (ATO).
    2. Employers are also required to withhold the Medicare Levy and the Temporary Budget Repair Levy, if applicable.
12. Stamp Duty:
    1. Stamp duty is applied to certain transactions, such as buying shares, property, or certain agreements.
    2. Stamp duty rates and thresholds can vary based on the type of transaction and the state or territory.
13. Land Tax:
    1. Land tax is a state and territory tax applied to the value of land holdings.
    2. It is typically payable by owners of land, and the rates and thresholds can vary by state or territory.
14. Tax Filing and Compliance:
    - Individuals and businesses are required to register for tax with the Australian Taxation Office (ATO) and comply with their tax obligations.
    - Tax returns are typically filed annually, and payment due dates may vary depending on the type of tax.

Please note that tax laws and regulations can change over time, so it's important to consult the Australian Taxation Office (ATO) or a tax professional for the most up-to-date and specific information related to the tax system in Australia.

In addition to taxes in Australia - what is council taxes and charges?

In Australia, local and provincial taxes and charges are levied by local councils and state governments, respectively. These taxes and charges are separate from the federal taxes imposed by the central government. Local councils and state governments use these revenues to fund various services and projects at the local and state levels. The specific taxes and charges can vary depending on the state and local government area. Here are some common examples of local and state taxes and charges in Australia:

Local Council Taxes and Charges:

1. Council Rates: Council rates, also known as property rates, are a type of property tax levied by local councils on residential and commercial properties. The rates are based on the assessed value of the property and are used to fund local services and infrastructure, such as rubbish collection, parks, libraries, and community facilities.
2. Garbage and Recycling Charges: Some local councils charge fees for rubbish and recycling collection services.
3. Parking Fees: Local councils may charge fees for parking in certain areas, such as central business districts or metered parking zones.
4. Development Application Fees: Local councils charge fees for processing development applications for construction or renovation projects.

State Government Taxes and Charges:

1. Payroll Tax: Payroll tax is a state-based tax on the wages paid by businesses when their total payroll exceeds a certain threshold. Each state sets its own payroll tax rates and thresholds.
2. Stamp Duty: Stamp duty is a state tax on various transactions, such as property transfers, motor vehicle registrations, and certain financial transactions.
3. Land Tax: Land tax is a state-based tax on the value of land owned by individuals or entities above a certain threshold. The rates and thresholds vary by state.
4. Motor Vehicle Registration Fees: States collect fees for motor vehicle registration, driver's licenses, and other motor vehicle-related services.
5. Fines and Penalties: State governments may impose fines and penalties for various offences, such as traffic violations and non-compliance with regulations.
6. Gambling Taxes: Some states impose taxes on gambling activities within their jurisdictions.
7. Taxes on Specific Industries: Some states may impose specific taxes or levies on certain industries, such as mining or gambling.

It's important to note that the specific local and state taxes and charges can vary significantly depending on the state and local government area. Each state and local council has its own tax laws and regulations. Businesses and individuals should check with their local council and state revenue departments to understand the local and state taxes and charges that apply in their specific area.

Additionally, tax laws and charges may change over time, so it's essential to stay informed about any updates or changes in the local and state tax landscape. Consulting with local authorities and tax professionals can help ensure compliance with local and state tax obligations in Australia.

Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Taxes in New Zealand

New Zealand (NZ) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in New Zealand (NZ):

1. Goods and Services Tax (GST):
    - GST is a broad-based consumption tax applied to most goods and services in New Zealand.
    - The standard GST rate is 15% on the value of goods and services consumed.
    - Certain goods and services, such as financial services and residential rent, are exempt from GST.
2. Income Tax:
    - New Zealand has a progressive income tax system, with higher income earners paying higher tax rates.
    - Individual taxpayers are subject to income tax on their earnings from various sources, including employment, business, and investments.
    - The tax rates and income thresholds for income tax can change annually in the government's budget.
3. Capital Gains Tax (CGT):
    - As of my last update, New Zealand did not have a comprehensive capital gains tax on all assets.
    - However, gains on certain types of property, such as residential rental properties, may be subject to income tax.
4. Accident Compensation Levy (ACC):
    - The ACC levy is applied to fund New Zealand's no-fault accident compensation scheme.
    - It is applied to most income and collected alongside income tax.
5. Customs and Excise:

- Customs duties and excise duties are applied to imported and locally produced goods, as well as specific products like alcohol, tobacco, and petroleum.

6. Pay As You Earn (PAYE):
    - PAYE is the system by which employers deduct income tax from employees' salaries and remit it to the Inland Revenue Department (IRD).
7. KiwiSaver:
    - KiwiSaver is a voluntary retirement savings scheme that includes tax incentives for contributing to a KiwiSaver account.
    - Contributions to KiwiSaver may be deducted from an individual's taxable income.
8. Fringe Benefit Tax (FBT):
    - FBT is applied to non-cash benefits provided by employers to employees as part of their remuneration package.
    - Employers are responsible for paying FBT on these benefits at a rate equivalent to the top marginal tax rate.
9. Stamp Duty:
    - As of my last update, New Zealand does not have a comprehensive stamp duty on documents or transactions. However, there may be specific duties or levies in certain circumstances.
10. Land Transfer Tax:
    - In New Zealand, land transfer tax is known as "Land Transfer Tax" or "LTT."
    - LTT is applied to the transfer of land ownership and is payable by the purchaser.
    - The LTT rates and thresholds can vary based on factors such as the value of the property and the type of transaction.
11. Provisional Tax:
    - Provisional tax is a system for paying income tax in instalments throughout the year.
    - Individuals and businesses estimate their income for the year and make payments based on these estimates.
    - The actual tax liability is reconciled when the annual tax return is filed.
12. Gift Duty:
    - As of ChatGPT's last update, New Zealand abolished gift duty in 2011.

- Previously, gift duty was applied to certain gifts or transfers of property made during a person's lifetime.

13. Tax Filing and Compliance:
    - Individuals and businesses are required to register for tax with the Inland Revenue Department (IRD) and comply with their tax obligations.
    - Tax returns are typically filed annually, and payment due dates may vary depending on the type of tax.

Please note that tax laws and regulations can change over time, so it's important to consult the Inland Revenue Department (IRD) or a tax professional for the most up-to-date and specific information related to the tax system in New Zealand.

In addition to taxes in New Zealand - what is local and provincial taxes and charges?

In New Zealand, local and provincial taxes and charges are levied by local authorities and regional councils, respectively. These taxes and charges are separate from the national taxes imposed by the central government. Local and regional governments use these revenues to fund various services and projects at the local and regional levels. The specific taxes and charges can vary depending on the region. Here are some common examples of local and provincial taxes and charges in New Zealand:

Local Government Taxes and Charges:

- Property Rates: Property rates, also known as property taxes, are levied by local authorities (city or district councils) on real estate properties. The rates are based on the value of the property and are used to fund local services and infrastructure.
- Water Rates: Local councils may charge water rates to cover the cost of providing water supply and wastewater services to properties.
- Sewerage Rates: Local councils may charge sewerage rates to cover the cost of providing sewerage and wastewater services.
- Rubbish and Recycling Collection Fees: Some local authorities charge fees for rubbish and recycling collection services.
- Licensing Fees: Businesses may be required to obtain licenses from local authorities, and fees are charged for these licenses.
- Building Consent Fees: Local councils charge fees for processing building consent applications for

construction or renovation projects.

Provincial (Regional Council) Taxes and Charges:

- Regional Fuel Tax: Some regional councils have the authority to impose a regional fuel tax on petrol and diesel to fund transportation projects in their regions.
- Regional Rates: Regional councils may levy rates on properties within their regions to fund regional services and projects.
- Consent Fees: Regional councils may charge fees for resource consents related to activities that have environmental impacts.
- Water Quality and Resource Management Charges: Some regional councils may charge levies or fees related to water quality monitoring and resource management.

It's important to note that the specific local and provincial taxes and charges can vary depending on the region and local government policies. Each local authority and regional council has its own tax and charge structure. Businesses and individuals should check with their local council and regional council to understand the local and provincial taxes and charges that apply in their specific area.

Additionally, tax laws and charges may change over time, so it's essential to stay informed about any updates or changes in the local and regional tax landscape. Consulting with local authorities and professionals can help ensure compliance with local and provincial tax obligations in New Zealand.

Created with the Standard Edition of HelpNDoc: Free Qt Help documentation generator

Taxes in Canada

Canada (CA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Canada (CA):

1. Goods and Services Tax (GST) / Harmonized Sales Tax (HST):
    - GST is a federal consumption tax applied to most goods and services in Canada.
    - HST is a combined tax that includes both the federal GST and provincial/territorial sales tax, applied in provinces that have harmonized their sales tax with the GST.
2. Sales Taxes:

- In addition to the GST and HST, some provinces have their own sales taxes, such as the PST in British Columbia and Manitoba.

3. Federal Income Tax:
    - Federal income tax is imposed by the Canadian government on individuals and businesses.
    - The tax rates are progressive, meaning higher income levels are subject to higher tax rates.
4. Provincial Income Tax:
    - Provinces and territories in Canada also levy their own income taxes in addition to the federal tax.
    - Provincial tax rates vary, and some provinces have separate brackets and deductions.
5. Provincial and Territorial Taxes:
    - Provinces and territories have their own income tax systems, including their own tax rates and brackets.
    - Some provinces also have their own sales taxes, such as the Provincial Sales Tax (PST) or the Quebec Sales Tax (QST).
6. Income Tax:
    - Canada has a progressive income tax system, with tax rates increasing as income levels rise.
    - Individuals are subject to federal and provincial/territorial income taxes on their earnings from various sources, including employment, self-employment, and investments.
7. Payroll Taxes:
    - Payroll taxes include contributions to the Canada Pension Plan (CPP) and Employment Insurance (EI) by employees and employers.
    - Employers also deduct federal and provincial income taxes from employees' salaries and remit them to the government.
8. Employment Insurance (EI) and Canada Pension Plan (CPP):
    - Employees and employers contribute to the Employment Insurance (EI) program, which provides temporary financial assistance to workers who lose their jobs.
    - Contributions are also made to the Canada Pension Plan (CPP), which provides retirement, disability, and survivor benefits.
9. Property Tax:

- Property tax is levied by municipalities on the value of real property, including homes and commercial properties.
- Rates and assessment methods vary by municipality.

10. Estate Tax and Probate Fees:
    - As of ChatGPT's last update, Canada does not have a federal estate tax, but some provinces may have estate administration taxes (often referred to as probate fees) on the value of an estate's assets.
11. Corporate Tax:
    - Corporations operating in Canada are subject to federal and provincial/territorial corporate income taxes.
    - The corporate tax rates can vary depending on the type of income and the jurisdiction.
12. Capital Gains Tax:
    - Capital gains are generally subject to taxation in Canada, with some exemptions for gains on the sale of a primary residence.
    - Fifty percent of capital gains are included in a taxpayer's income for tax purposes.
13. Excise and Customs Duties:
    - Excise duties are applied to certain goods, such as alcohol, tobacco, and gasoline.
    - Customs duties are levied on imported goods based on their value and classification.
14. Foreign Account Reporting:
    - Canadian residents are required to report their foreign financial accounts and certain foreign property holdings if they meet specific thresholds.
    - Non-compliance with reporting requirements can result in penalties.
15. Tax Filing and Compliance:
    - Individuals and businesses are required to file tax returns annually.
    - The due dates for filing tax returns and making tax payments vary depending on the type of tax and the taxpayer's circumstances.

Please note that tax laws and regulations can change over time, so it's important to consult the Canada Revenue Agency (CRA) or a tax professional for the most up-to-date and specific information related to the tax system in Canada.

In addition to taxes in Canada - what is municipalities and provincial governments taxes and charges?

In Canada, local and provincial taxes and charges are levied by municipalities and provincial governments, respectively. These taxes and charges are separate from the federal taxes imposed by the central government. Local and provincial governments use these revenues to fund various services and projects at the local and provincial levels. The specific taxes and charges can vary depending on the province and municipality. Here are some common examples of local and provincial taxes and charges in Canada:

Local Government Taxes and Charges:

- Property Taxes: Property taxes are levied by municipalities on real estate properties, including residential and commercial properties. The tax rates are based on the assessed value of the property and are used to fund local services such as schools, police, fire departments, and infrastructure projects.
- Business Taxes and Licensing Fees: Municipalities may impose taxes or require businesses to obtain licenses to operate within their boundaries. The fees and taxes vary by municipality.
- Local Improvement Levies: In some cases, municipalities may levy additional taxes or fees on properties in specific areas to fund local improvement projects, such as road construction or utility upgrades.
- Parking Fees: Municipalities may charge fees for parking in certain areas, such as downtown areas or public parking lots.
- Recreation Fees: Municipalities may charge fees for the use of recreational facilities, parks, and community centers.
- Waste Collection Fees: Some municipalities charge fees for waste collection and disposal services.

Provincial Government Taxes and Charges:

- Provincial Income Tax: Most provinces in Canada impose their own income tax on individuals and corporations, in addition to the federal income tax.
- Provincial Sales Tax (PST): Some provinces have a provincial sales tax that is levied on the sale of goods and services within their jurisdiction, in addition to the federal Goods and Services Tax (GST).
- Fuel Taxes: Provinces may levy taxes on gasoline, diesel, and other fuels to fund transportation and infrastructure projects.
- Vehicle Registration and Licensing Fees: Provinces collect fees for vehicle registration, driver's

licenses, and other motor vehicle-related services.

- Health and Education Levies: Some provinces have specific levies or fees dedicated to funding healthcare and education services.
- Environment Fees: Provinces may impose environmental levies or fees to fund environmental protection and conservation initiatives.

It's important to note that the specific local and provincial taxes and charges can vary significantly depending on the province and municipality. Each province and municipality has its own tax laws and regulations. Businesses and individuals should check with their local government and provincial revenue departments to understand the local and provincial taxes and charges that apply in their specific area.

Additionally, tax laws and charges may change over time, so it's essential to stay informed about any updates or changes in the local and provincial tax landscape. Consulting with local authorities and tax professionals can help ensure compliance with local and provincial tax obligations in Canada.

Created with the Standard Edition of HelpNDoc: Easily convert your WinHelp HLP help files to CHM with HelpNDoc's step-by-step guide

Taxes in United States of America (USA)

United States (US) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in the United States (US):

1. Federal Income Tax:
    - The United States has a progressive federal income tax system, meaning higher income levels are subject to higher tax rates.
    - Income tax rates vary based on filing status and income level.
2. State Income Tax:
    - Many states impose their own income taxes, with rates and regulations varying by state.
    - Some states have a flat tax rate, while others have graduated rates.
3. Sales and Use Tax:
    - Sales tax is levied by state and local governments on the sale of goods and services at the

point of sale.

- Use tax is applicable when taxable goods are purchased from out-of-state sellers and used within the state.

4. Payroll Taxes:
    - Employees and employers contribute to Social Security and Medicare programs through payroll taxes.
    - Social Security taxes are subject to an annual wage base limit.
5. Capital Gains Tax:
    - Capital gains tax is applied to profits from the sale of assets such as stocks, real estate, and investments.
    - Long-term capital gains receive preferential tax rates.
6. Estate and Gift Tax:
    - The federal government imposes estate and gift taxes on certain large transfers of wealth.
    - Exemptions and tax rates can change over time.
7. Corporate Tax:
    - Corporations are subject to federal corporate income tax on their profits.
    - Corporate tax rates and deductions can vary based on factors such as income and industry.
8. Property Tax:
    - Property tax is levied by local governments on real property, such as land and buildings.
    - Rates vary by jurisdiction and property value.
9. Excise Taxes:
    - Excise taxes are levied on specific goods, such as alcohol, tobacco, fuel, and certain luxury items.
10. Foreign Account Reporting:
    - US citizens and residents with foreign financial accounts are required to report them to the Internal Revenue Service (IRS).
    - Non-compliance can result in penalties.
11. Alternative Minimum Tax (AMT):

- The AMT is an additional tax calculation that aims to ensure taxpayers with certain deductions still pay a minimum amount of tax.

12. Online Sales Tax:

    - The US Supreme Court's "*Wayfair*" decision allows states to impose sales tax on online sales even if the seller has no physical presence in the state.

Please note that tax laws and regulations can change over time, so it's important to consult the Internal Revenue Service (IRS) or a tax professional for the most up-to-date and specific information related to the tax system in the United States.

In addition to taxes in United State of America - what is local and state taxes and charges?

In the United States, local and provincial taxes and charges are levied by local governments and state governments, respectively. These taxes and charges are separate from the federal taxes imposed by the central government. Local and state governments use these revenues to fund various services and projects at the local and state levels. The specific taxes and charges can vary significantly depending on the state and locality. Here are some common examples of local and state taxes and charges in the USA:

Local Taxes and Charges:

- Property Taxes: Property taxes are levied by local governments on real estate properties, including residential and commercial properties. The tax rates are based on the assessed value of the property and are used to fund local services like schools, police, and fire departments.
- Sales Taxes: Sales taxes are imposed by many cities, counties, and other local jurisdictions on the sale of goods and services within their boundaries. The rates can vary widely from one locality to another.
- Occupancy Taxes: Occupancy taxes, also known as hotel or lodging taxes, are charged by local governments on hotel room rentals and short-term accommodations.
- Local Business Taxes: Some local jurisdictions may impose taxes or license fees on businesses operating within their boundaries.
- Motor Vehicle Taxes: Local governments may collect taxes or registration fees on motor vehicles, including cars, trucks, and motorcycles.
- Local Service Fees: Local governments may charge fees for specific services, such as waste collection, parking, and recreation facilities.

State Taxes and Charges:

- State Income Tax: Most states impose a state income tax on individuals and businesses, with rates and brackets varying by state.
- State Sales Tax: State governments typically levy a sales tax on the sale of goods and services within their borders. The state sales tax rates can differ from one state to another.
- State Business Taxes: States may have corporate income taxes or other business taxes that apply to businesses operating within their jurisdictions.
- State Motor Vehicle Taxes and Fees: States collect taxes and fees on motor vehicle registrations, titles, and driver's licenses.
- State Fuel Taxes: States impose taxes on gasoline and diesel fuel to fund transportation infrastructure projects.
- State Excise Taxes: Some states levy excise taxes on specific goods, such as alcohol, tobacco, and fuel.

It's important to note that the specific local and state taxes and charges can vary significantly depending on the state and locality. Each state and local jurisdiction has its own tax laws and regulations. Businesses and individuals should check with their local government and state revenue departments to understand the local and state taxes and charges that apply in their specific area. Additionally, tax laws and rates may change over time, so it's essential to stay informed about any updates or changes in the tax landscape.

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

---

What is Sales Tax?

Sales tax is a type of consumption tax imposed by governments on the sale of goods and services. It is typically collected by businesses on behalf of the government and is added to the purchase price of taxable items or services. When a customer buys a taxable product or service, they pay the sales tax in addition to the actual cost of the item.

The rate of sales tax can vary depending on the jurisdiction, such as country, state, county, or city. Different regions may have different sales tax rates, and some areas may have no sales tax at all. Sales tax rates are usually represented as a percentage of the total purchase price.

Businesses are responsible for collecting the sales tax from customers and then remitting it to the appropriate government authority. This revenue is an essential source of income for governments and is

used to fund public services and infrastructure, such as schools, roads, healthcare, and other government programs.

It is essential for businesses and consumers to be aware of the applicable sales tax rates in their area to ensure compliance with tax laws and to avoid any penalties for non-compliance. Sales tax is one of the primary methods governments use to generate revenue and is a crucial component of a country's or region's tax system.

In which countries is Sales Tax applicable?

Sales tax or a similar form of consumption tax is applicable in many countries around the world. However, it's important to note that the specific name, structure, and regulations of such taxes may vary from country to country. Here are some common forms of sales tax and their equivalent names in different countries:

1. Value Added Tax (VAT): VAT is a widely used form of sales tax applied in many countries, including most of Europe, Asia, and Africa. Some of the countries with VAT systems include:
    - United Kingdom
    - Germany
    - France
    - Spain
    - Italy
    - China
    - India
    - South Africa
2. Goods and Services Tax (GST): Similar to VAT, GST is another common form of sales tax applied in some countries, including:
    - Canada
    - Australia
    - New Zealand
    - Singapore
3. Sales and Use Tax: In the United States, sales tax is levied at the state level, and in some cases, at the local level. Each state determines its sales tax rates and regulations. There is no national sales tax in

the U.S., but the tax is applied on the sale of goods and some services at the state and local levels.

4. Consumption Tax: Some countries use a generic term like "*consumption tax*" to describe their sales tax system. For example:
    - Japan applies a Consumption Tax.
    - South Korea has a Value Added Tax, but it is commonly referred to as a Consumption Tax.

It's important to remember that tax systems and regulations can change, so it's best to consult official government sources or tax professionals for the most up-to-date information on sales tax in specific countries. Additionally, some countries may have exemptions or reduced rates for certain goods and services, making their sales tax systems more complex.

What is Use Tax?

"*Use tax*" is a companion tax to sales tax and is applicable in some regions or countries. It is designed to complement the sales tax by ensuring that the government can collect taxes on purchases made outside the jurisdiction that would have been subject to sales tax if purchased within that jurisdiction. The use tax is typically levied on the use, storage, consumption, or other enjoyment of taxable goods and services that were acquired from outside the taxing jurisdiction.

The need for a use tax arises when a resident or business in a specific jurisdiction purchases taxable goods or services from an out-of-state or foreign seller where no sales tax was collected at the time of purchase. If the same goods or services were purchased within the taxing jurisdiction, they would have been subject to sales tax.

For example, let's say a person living in a state with a sales tax rate of 6% purchases a high-value item from an online retailer located in a different state that does not charge sales tax. In this case, the purchaser may be required to pay a use tax on that item to their home state's tax authorities, equivalent to the sales tax rate, to make up for the tax revenue that would have been collected if the item were purchased locally.

Use tax laws are often enforced to ensure that local businesses and retailers are not at a disadvantage compared to out-of-state or online sellers who may not charge sales tax. It helps maintain a level playing field for businesses and ensures that the appropriate tax revenue is collected regardless of where the purchase is made.

It's important for individuals and businesses to be aware of use tax requirements in their jurisdiction and report and remit the use tax when applicable. Similar to sales tax, use tax rates and regulations can vary depending on the jurisdiction, so it's best to consult official government sources or tax professionals for specific guidance.

In which countries does VAT/GST/Sales Tax thresholds exist?

Value Added Tax (VAT), Goods and Services Tax (GST), and Sales Tax thresholds exist in various countries around the world. These thresholds are the minimum sales or turnover amounts at which businesses are required to register for and charge VAT, GST, or Sales Tax. Below are some examples of countries where such thresholds are implemented:

1. South Africa: South Africa has a Value Added Tax (VAT) system, and the VAT registration threshold was ZAR 1 million in annual taxable supplies as of ChatGPT's last update.
2. United Kingdom: In the UK, businesses must register for VAT if their taxable turnover exceeds the VAT registration threshold. As of ChatGPT's last update in September 2021, this threshold was £85,000 in a 12-month period. However, tax thresholds and regulations may change, so it's important to check for the most current information.
3. United States: The United States does not have a federal VAT or GST system. Instead, it relies on sales taxes, which are administered at the state level. Each state sets its own sales tax rules, including any thresholds for registration and collection. Thresholds may vary significantly from state to state.
4. Canada: Canada has a federal Goods and Services Tax (GST) and Harmonized Sales Tax (HST) system. As of ChatGPT's last update, the threshold for GST registration was CAD 30,000 in annual worldwide taxable supplies for most businesses, but this may vary based on the type of business and location.
5. Australia: Australia has a Goods and Services Tax (GST) system, and businesses with annual turnover of AUD 75,000 or more must register for GST.
6. European Union (EU): In the EU, each member country has its own VAT thresholds and rules. For intra-EU trade, businesses may need to register for VAT in each country where they surpass the threshold for distance selling (EUR 35,000 or EUR 100,000, depending on the country).
7. India: India has a Goods and Services Tax (GST) system, and the threshold for GST registration varies by state. As of ChatGPT's last update, the threshold was INR 40 lakhs (INR 20 lakhs for special category states) in annual turnover for most businesses.

It's important to note that tax laws and thresholds may change over time, and they can vary by industry, type of business, and location. Additionally, some countries may have multiple tax rates and exemptions based on the type of goods or services being provided. Therefore, businesses should regularly monitor and comply with the tax regulations of the countries in which they operate to ensure proper VAT, GST, or Sales Tax registration and collection.

In which countries does not use VAT/GST/Sales Tax?

As of ChatGPT's last update in September 2021, several countries do not have a Value Added Tax (VAT), Goods and Services Tax (GST), or Sales Tax system. Instead, they may use alternative tax structures to generate revenue for the government. Some of these countries include:

1. Bahrain: Bahrain does not have a VAT or GST system. However, it implemented a 5% VAT system in January 2019, becoming the last Gulf Cooperation Council (GCC) country to introduce VAT.
2. Oman: As of ChatGPT's last update, Oman did not have a VAT or GST system. However, like Bahrain, it was planning to introduce a 5% VAT system in the future.
3. Saudi Arabia: Saudi Arabia introduced a 5% VAT system in January 2018, becoming one of the GCC countries to implement VAT.
4. United Arab Emirates: The UAE implemented a 5% VAT system in January 2018.
5. Qatar: As of ChatGPT's last update, Qatar did not have a VAT or GST system. However, it was also planning to introduce a 5% VAT system in the future.
6. Brunei: Brunei does not have a VAT or GST system.
7. Cayman Islands: The Cayman Islands does not have a VAT or GST system.
8. Monaco: Monaco does not have a VAT or GST system.
9. Panama: Panama does not have a VAT or GST system.
10. United States (Sales Tax): The United States does not have a national VAT or GST system. Instead, it relies on sales taxes, which are administered at the state level. There is no federal sales tax, and each state has its own rules and rates for sales tax.

It's important to note that tax systems can change over time, and some countries may introduce VAT, GST, or Sales Tax systems in the future to generate revenue and fund public services. Therefore, it is always best to check for the most current tax regulations and updates in each country where business operations are conducted.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

VAT/GST/Sales tax schemes

What is VAT/GST/Sales tax schemes?

VAT/GST/Sales tax schemes, also known as alternative or special tax schemes, are specific methods of calculating and reporting value-added tax (VAT), goods and services tax (GST), or sales tax that differ from the standard tax system. These schemes are designed to simplify tax compliance for certain types of businesses or transactions.

The primary objective of these schemes is to provide businesses with alternative ways of accounting for taxes, making it easier for them to calculate and report their tax liability. Some common types of VAT/GST/Sales tax schemes include:

1. Flat Rate Scheme: Under this scheme, businesses pay a fixed percentage of their turnover as tax instead of calculating tax on each individual transaction. This simplifies the tax accounting process, especially for small businesses.
2. Cash Accounting Scheme: This scheme allows businesses to account for tax based on cash receipts and payments rather than invoiced amounts. It can help with cash flow management, particularly for businesses that deal with delayed payments.
3. Annual Accounting Scheme: With this scheme, businesses submit tax returns and make payments on an annual basis, rather than quarterly or monthly. It reduces the frequency of tax reporting for eligible businesses.
4. Margin Scheme: This scheme is commonly used for the sale of second-hand goods, works of art, antiques, or collectibles. Tax is calculated based on the margin between the purchase price and the selling price, rather than the full selling price.
5. Tour Operators Margin Scheme (TOMS): TOMS is applicable to businesses that buy and sell travel services, such as package holidays. Tax is calculated on the margin of the services provided rather than the full selling price.
6. Simplified Tax Accounting Methods: Some countries offer simplified methods of calculating tax for specific types of businesses, such as retailers, hotels, or restaurants.
7. Exemption Schemes: Certain industries or activities may be exempt from tax or have a reduced tax rate under specific circumstances.

Each country may have its own set of VAT/GST/Sales tax schemes with specific eligibility criteria and rules. The availability of these schemes and their conditions may also change over time based on government policies and tax regulations.

Businesses should carefully consider their eligibility and the potential benefits of using a VAT/GST/Sales tax scheme. They are advised to seek guidance from accounting professionals or tax advisors to determine

the most suitable scheme for their specific circumstances and to ensure compliance with tax laws and regulations.

Which countries use VAT schemes?

Value Added Tax (VAT) schemes, also known as alternative or special VAT schemes, are used in several countries around the world to simplify VAT reporting and compliance for certain types of businesses or transactions. These schemes may differ from the standard VAT system and may be optional or mandatory depending on the country. Here are some examples of countries that use specific VAT schemes:

1. United Kingdom: The UK has various VAT schemes, including the Flat Rate Scheme, Cash Accounting Scheme, and Annual Accounting Scheme, which provide alternative methods of calculating and reporting VAT for eligible businesses.
2. Australia: Australia offers the Cash Accounting Scheme, which allows small businesses with an annual turnover below a certain threshold to report GST on a cash basis rather than an accrual basis.
3. New Zealand: New Zealand has several GST schemes, including the Payments Basis Scheme and the Hybrid Basis Scheme, which provide alternative methods of accounting for GST for certain businesses.
4. European Union (EU) Member States: Within the EU, each member state may have specific VAT schemes for certain industries or activities, such as the Margin Scheme for second-hand goods, works of art, and antiques.
5. India: India has a composition scheme under its Goods and Services Tax (GST) regime, allowing small businesses to pay a fixed percentage of turnover as tax and file simplified returns.
6. Canada: Canada has the Quick Method, a simplified accounting method for calculating GST/HST (Goods and Services Tax/Harmonized Sales Tax) for small businesses.
7. Singapore: Singapore offers the GST Flat Rate Scheme for certain businesses to simplify their GST reporting and claim input tax credits.

It's important to note that the availability and conditions of VAT schemes may vary from country to country, and they may be subject to change based on government policies and tax regulations. Businesses should consult with local tax authorities or seek advice from tax professionals to determine if they are eligible to use any specific VAT schemes in their respective countries.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Invoice - Requirements

Requirements for Invoices

What is the basic requirements of an invoice for NON Registered VAT/GST/Sales tax vendors?

The basic requirements for an invoice for non-registered VAT/GST/Sales tax vendors may vary depending on the jurisdiction and specific regulations. However, in general, here are some common elements that are often required on an invoice for non-registered vendors:

1. Header Information:
    - Date of the invoice.
    - A unique invoice number or reference.
    - Your business name and contact information.
    - The recipient's name and contact information (if applicable).
2. Description of Goods or Services:
    - A clear and accurate description of the goods or services provided.
    - The quantity of the goods or the duration of the service.
    - The price per unit or service rate.
3. Total Amount:
    - The total amount payable for the goods or services.
    - Any applicable discounts or deductions.
4. Terms of Payment:
    - Payment terms and due date.
    - Accepted forms of payment (e.g., cash, check, bank transfer).
5. Currency:
    - The currency in which the transaction is conducted (if applicable).
6. Additional Charges:
    - Any additional charges such as shipping, handling, or taxes (if applicable).
7. Business Information:

- Your business's legal status (sole proprietorship, partnership, etc.).
- Your business registration number (if applicable).

8. Customer Information:
    - The customer's name and address (if applicable).
9. Transaction Details:
    - The date the goods or services were delivered or completed (if applicable).
    - Any relevant terms or conditions related to the transaction.
10. Contact Information:
    - Contact details for customer inquiries or disputes.

It's important to note that the specific requirements for invoices may vary from one jurisdiction to another, and they can change over time. Additionally, some jurisdictions may have different requirements for registered and non-registered vendors. Therefore, it's recommended to consult the relevant tax authorities or a professional accountant in your jurisdiction to ensure that your invoices comply with the applicable regulations.

What is the basic requirements of a Tax invoice?

A tax invoice is a formal document issued by a seller to a buyer that provides details of a taxable transaction, including the amount of tax charged. The basic requirements of a tax invoice can vary by jurisdiction, but they generally include the following information:

1. Seller's Information: The name, address, and contact information of the seller (supplier) must be clearly stated on the tax invoice.
2. Buyer's Information: The name, address, and contact information of the buyer (recipient) should be included on the invoice.
3. Invoice Number: A unique identification number for the invoice, which helps both parties keep track of transactions.
4. Invoice Date: The date when the invoice is issued.
5. Description of Goods or Services: A clear description of the goods sold or services provided, including quantity, unit price, and any applicable codes or identifiers.
6. Quantity: The quantity of goods or services being supplied.
7. Unit Price: The price per unit of the goods or services.

8. Total Amount: The total amount payable for the goods or services before taxes.
9. Tax Amount: The amount of tax charged, broken down by type (e.g., VAT, GST, sales tax).
10. Tax Identification Number: The seller's tax identification number (e.g., VAT number, GST number) that is used for tax reporting purposes.
11. Tax Rate: The rate at which the tax is charged.
12. Currency: The currency in which the transaction is conducted.
13. Payment Terms: The terms of payment, including due date and accepted payment methods.
14. Additional Charges: Any additional charges, such as shipping fees or handling charges, should be clearly indicated.
15. Total Amount Payable: The total amount payable by the buyer, including the tax and any additional charges.
16. Terms and Conditions: Any specific terms and conditions related to the transaction, such as return policy or warranty information.
17. Date of Supply: The date on which the goods were supplied or services were rendered.
18. Signature: Depending on the jurisdiction, a signature or electronic verification from the seller may be required.

It's important to note that the specific requirements for a tax invoice can vary by country and jurisdiction. Businesses should ensure that their tax invoices comply with the regulations and guidelines set by the relevant tax authorities. Failure to issue proper tax invoices may result in penalties or legal consequences. If you have questions about the requirements for tax invoices in your jurisdiction, it's recommended to consult with a tax professional or the relevant tax authority.

Currency: Is this applicable to international transactions only?

The inclusion of the currency in a tax invoice is not necessarily limited to international transactions. While it's especially important for international transactions to specify the currency to avoid any confusion, including the currency in the tax invoice can also be relevant for domestic transactions under certain circumstances. Here's why:

1. Cross-Border Transactions: In international transactions, specifying the currency is essential to avoid any misunderstandings or mistakes related to exchange rates and currency conversions.
2. Multi-Currency Transactions: In some cases, businesses may operate in regions where multiple currencies are accepted. Even within a single country, certain areas or industries might commonly use a different currency. Specifying the currency ensures clarity and accuracy.

3. Accounting and Reporting: For businesses that handle transactions in multiple currencies, including the currency in the tax invoice can help with accurate accounting and financial reporting. It helps businesses keep track of different currency transactions and conversions.
4. Transparency: Even in domestic transactions, some businesses may prefer to specify the currency to provide transparency to their customers and stakeholders.
5. Legal and Regulatory Compliance: In certain jurisdictions, tax laws might require the currency to be specified on invoices, regardless of whether the transaction is domestic or international.

Ultimately, the decision to include the currency on a tax invoice depends on the specific context and the practices within a particular business and jurisdiction. If you have any doubts about whether to include the currency on your tax invoices, it's advisable to consult with a tax professional or legal expert who is familiar with the regulations in your area.

The name of an Invoice in South Africa?

In osFinancials5/TurboCASH5, the name of the Invoice is "Invoice" in most of the template Set of Books. This may not required to amend the name "*Invoice*" to "*Tax Invoice*", "*VAT Invoice*".

In South Africa as the name of a invoice "*Contains the words "Tax Invoice", "VAT Invoice" or "Invoice*" according to the South African Revenue Services (SARS) .

This is optional to change the Name of the "*Invoice*" to "*Tax Invoice*", "*VAT Invoice*", etc. This may apply to other Tax jurisdictions.

If your the Tax requirements for your jurisdiction prescribes a specific name for Invoice, you may change the name of the document type. The following options is available in osFinancials:

- Change the name on translatable document layout files: However, If you need to change the description of Invoice, for Invoice on translatable document layout files, you need to do this on the Types tab of "Customise Languages:" (Tools → Customise Language menu on the Setup ribbon).
- Designing customised layout files: The name of the document may need to include specific terms like "*Tax Invoice*" or "*VAT Invoice*", based on the requirements of your tax jurisdiction. Ensure that the document name aligns with the regulations.

Keep in mind that specific formatting and content requirements may vary based on the regulations in your jurisdiction, so it's always a good idea to consult with a tax professional or authority to ensure that your documents meet the necessary standards.

What is the difference between an Invoice or an abridged tax invoice?

An "*Invoice*" and an "*Abridged Tax Invoice*" are terms often used in the context of taxation and accounting, particularly when dealing with value-added tax (VAT) or goods and services tax (GST) systems. These terms have specific meanings and implications based on the regulations of the jurisdiction in which they are used.

- Invoice: An invoice is a detailed document that provides a record of a transaction between a seller and a buyer. It typically includes information such as the names and contact information of both parties, a description of the goods or services sold, the quantity, the price per unit, the total amount payable, and any applicable taxes. In the context of taxation, an invoice serves as proof of the transaction and is used for various purposes, including record-keeping, accounting, and compliance with tax laws. An invoice issued in a VAT or GST system usually includes the tax amount charged separately from the net amount.
- Abridged Tax Invoice: An abridged tax invoice is a simplified version of a regular invoice that may be used for specific situations, often in business-to-business (B2B) transactions. In some tax systems, an abridged tax invoice may be used when the total value of the transaction falls below a certain threshold, or when specific conditions are met. This type of invoice typically includes key information such as the seller's name, the buyer's name, a description of the goods or services, the total amount payable, and the tax amount. Unlike a full invoice, an abridged tax invoice may not include all the detailed information that a regular invoice provides.

The purpose of an abridged tax invoice is to simplify the documentation process for smaller transactions or transactions where the buyer is registered for VAT or GST and is eligible to claim input tax credit. It's important to note that the rules and requirements for using abridged tax invoices vary by jurisdiction, so it's essential to consult the specific tax regulations in your country or region to understand when and how abridged tax invoices can be used.

As always, when dealing with invoicing and tax matters, it's recommended to consult with a tax professional or authority to ensure compliance with local regulations and requirements.

Does thresholds apply for an Invoice or an abridged tax invoice?

Thresholds can apply to both regular invoices and abridged tax invoices, but the specific thresholds and their applicability can vary depending on the tax regulations of the jurisdiction in question. Here's how thresholds might apply to each type of invoice:

- Regular Invoice Thresholds: In some tax systems, there might be thresholds that determine when businesses are required to issue regular invoices that include detailed information about the

transaction, including the tax amount. Below a certain transaction value, businesses may not be required to issue detailed invoices. Instead, they might be allowed to use simplified documents or receipts. These thresholds are often intended to reduce administrative burdens for smaller transactions.

- Abridged Tax Invoice Thresholds: Abridged tax invoices are often used in specific cases, such as business-to-business transactions where the buyer is eligible to claim input tax credits. These simplified invoices may be allowed for transactions below a certain threshold value. This threshold can vary by jurisdiction and is typically designed to streamline documentation for smaller transactions while still ensuring adequate tax reporting.

It's important to note that the thresholds and requirements for both regular invoices and abridged tax invoices can differ widely from one jurisdiction to another. Some jurisdictions might not use abridged tax invoices at all, while others might have specific rules about when they can be used and what information they must contain.

If you're dealing with invoices and tax matters, it's advisable to consult the tax authorities or a tax professional in your specific jurisdiction to understand the rules, thresholds, and requirements that apply to your situation.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

VAT/GST/Sales Tax - Configure Chart of Accounts

What is Registering / Cancellation of Registration for VAT/GST/Sales Tax?

Registering for VAT/GST/Sales Tax: Registering for VAT/GST/Sales Tax involves the formal process of enrolling as a tax vendor with the relevant tax authority in your jurisdiction. When your business reaches a specified sales threshold, you are required to collect and remit taxes on behalf of the government. The registration process typically includes providing essential business details, obtaining a unique tax identification number, and understanding the tax rates and regulations applicable to your industry. Registering ensures compliance with tax laws, allows you to collect tax from customers, and entitles you to claim input tax credits.

Cancellation of Registration for VAT/GST/Sales Tax: Cancellation of registration for VAT/GST/Sales Tax entails formally informing the tax authority that you will no longer be conducting taxable activities. This could be due to various reasons, such as ceasing business operations or falling below the minimum sales

threshold. Upon cancellation, you are no longer required to collect tax from customers or remit it to the government. The process may involve settling any outstanding tax liabilities, updating your accounting records, and adjusting your system settings to reflect the change in your tax status. It's important to follow the proper procedures to avoid any penalties or complications related to tax compliance.

Options to Register / Cancel Registration for VAT/GST/Sales Tax

VAT/GST/Sales Tax Registration / Cancellation of Registration options:

1. New Registered Vendor in osFinancials5/TurboCASH5: If you're new to osFinancials5/TurboCASH5 and are a registered VAT/GST/Sales Tax vendor, this option is for you. You'll follow the steps to set up your VAT/GST/Sales Tax accounts, configure tax codes and percentages, and customize document layouts to meet your tax jurisdiction's requirements. This ensures accurate tax calculations and proper tax invoicing in your transactions.
2. New User in osFinancials5/TurboCASH5 without Tax Registration: If you're new to osFinancials5/TurboCASH5 and not a registered VAT/GST/Sales Tax vendor, this choice is appropriate. You'll need to adjust the system's default settings for tax accounts to reflect your non-registered status. This includes disabling or removing VAT/GST/Sales Tax accounts, configuring layouts to reflect non-taxable transactions, and updating document names if necessary. This option ensures accurate transaction documentation without tax-related elements.
3. Existing User Opting for Tax Deregistration: If you're an existing osFinancials5/TurboCASH5 user who has decided to cancel your VAT/GST/Sales Tax registration, or if you have been served a notice of cancellation of registration from your tax authority. Following this route involves steps to update your tax accounts' status to *'Disabled*,' and possibly remove them if unposted transactions are absent. Additionally, you need to process all tax-related transactions until the date of cancellation of registration, ensuring accurate records. After the date of deregistration, it's crucial to adjust your system to process transactions without Tax (VAT/GST/Sales tax) to reflect the updated tax-related changes accurately. Managing this process diligently will help maintain the integrity of your financial records.

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

VAT/GST/Sales Tax - New Registered Vendor in osFinancials

If you are already Registered as a VAT/GST/Sales Tax Vendor and you are New to osFinancials5/TurboCASH5

If you're new to osFinancials5/TurboCASH5 and are a registered VAT/GST/Sales Tax vendor, this option is for you. You'll follow the steps to set up your VAT/GST/Sales Tax accounts, configure tax codes and percentages, and customize document layouts to meet your tax jurisdiction's requirements. This ensures accurate tax calculations and proper tax invoicing in your transactions.

VAT/GST/Sales tax codes - Template (Set of Books)

Most template Set of Books, downloaded from the "*Let osFinancials help you to create a Set of Books?*" option, already includes basic VAT/GST/Sales tax accounts in the "*Current liabilities*" section in the Chart of Accounts.

> *Before you start to process any transactions and documents or link your Stock items / Inventory items / Products to the Output and Input tax accounts, you need to check your tax codes and percentages (If you are registered as a VAT/GST/Sales Tax vendor).*

Steps to configure the template Set of Books for VAT/GST/Sales Tax

> *As a new user to osFinancials5/TurboCASH5, before you start processing any transactions in journals batches (journals) or to process and transactions in documents it is advisable to review and edit the Chart of Accounts.*

In cases where you have met the compulsory threshold for VAT/GST/Sales tax registration or have chosen to opt for voluntary registration as a VAT/GST/Sales tax vendor, there are steps to follow when dealing with VAT/GST/Sales tax codes in a template Set of Books:

1. VAT/GST/Sales Tax accounts: If you are registered as a VAT/GST/Sales Tax vendor, you need to review the basic VAT/GST/Sales Tax accounts included in the "*Current liabilities*" section in the Chart of Accounts of your selected template Set of Books, downloaded from the "*Let osFinancials help you to create a Set of Books?*" option. You need to add additional Tax codes and edit the existing tax percentages for your Tax regime and jurisdiction. To do this, navigate to the Setup → Accounts menu on the Setup ribbon.

   > *You may print a "Tax code - Tax rates" report on the User reports → Tax menu on the Reports ribbon to print a list of Tax codes and their respective percentages and the status whether the Tax code is enabled or disabled).*

2. VAT/GST/Sales Tax Registration number: Enter the VAT/GST/Sales Tax registration number in the "*Tax reg. no.*" field on the Setup → Company Info (Address tab).

3. VAT/GST/Sales Tax - Document Headings: The decision to modify the document name should be guided by the legal requirements and guidelines of your tax jurisdiction to ensure compliance with invoicing regulations. By default, the document type "*Invoice*" will print on document layout files for the following documents will print on document layout files as follows:

    - Change Document Headings: Change the "*Invoice*" to "*Tax Invoice*" for your specific country or jurisdiction and/or industry (Setup → Documents setup menu on the Setup ribbon). Check the headings for the other document types (Credit notes, Quotes, Purchases, Supplier returns and Orders), and change the headings, if necessary.

    - Change the Names of Document Types: You may need to change the appropriate document type names such as *"Invoice," "Credit note", "Quote", "Purchase", "Supplier return"*, or *"Order"* for your specific country or jurisdiction and/or industry. These document type names will display in the osFinancials5/TurboCASH5 interface and will print on " *Translatable Document Layout Files with Dynamic Document Types*" such as "*Layout file*", "*Document layout*" and "*Document layout (15 code)*" document layout files.

    - POS Tax Invoice: "*POS Tax Invoice*" will be printed on the "POS-SP100", POS 1 and POS 2 document layout files. To Change the "*POS Tax Invoice*" label, you need to go to Tools → Customise language on the Setup ribbon and change the description of "*LabelID - 906014*".

4. Select Document Layout Files: By default, "*Layout file*" is pre-selected in Set of Books templates. The default "*Layout file*" supports Tax (VAT/GST/Sales Tax) related expressions and label descriptions. If you are registered as a Tax (VAT/GST/Sales Tax) vendor, you may select other *Translatable Document Layout Files with Dynamic Document Types*, such as "*Document layout*" and "*Document layout (15 code)*" document layout files, which includes tax related expressions and labels.

5. Stock items/Inventory items Tax classes: When planning, designing and adding your stock/inventory system, you may create Tax classes to link your stock items (goods/services/products) to a Output tax and Input tax codes (including your Sales, Cost of Sales and Stock control accounts). You may need to add tax classes for each of your stock items and link them to the appropriate tax codes (including zero-rated and exempt tax codes).

You may print a "Tax classes report" report on the Reports → Stock item listing - Tax classes menu (Reports ribbon) to print a list of Tax classes for Output tax, Input tax and their respective sales, cost of sales and stock control accounts.

Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

VAT/GST/Sales Tax - New to osFinancials without Tax Registration

If you are New to osFinancials5/TurboCASH5 without VAT/GST/Sales Tax Registration

If you're new to osFinancials5/TurboCASH5 and not a registered VAT/GST/Sales Tax vendor, this choice is appropriate. You'll need to adjust the system's default settings for tax accounts to reflect your non-registered status. This includes disabling or removing VAT/GST/Sales Tax accounts, configuring layouts to reflect non-taxable transactions, and updating document names if necessary. This option ensures accurate transaction documentation without tax-related elements.

VAT/GST/Sales tax codes - Template (Set of Books)

Most template Set of Books, downloaded from the "*Let osFinancials help you to create a Set of Books?*" option, already includes basic VAT/GST/Sales tax accounts in the "*Current liabilities*" section in the Chart of Accounts.

Before you start to process any transactions and documents or link your Stock items / Inventory items / Products to the Output and Input tax accounts, you need to select the "No tax" code.

Steps to configure the template Set of Books for VAT/GST/Sales Tax

As a new user to osFinancials5/TurboCASH5, before you start processing any transactions in journals batches (journals) or to process and transactions in documents it is advisable to review and edit the Chat of Accounts.

In cases where you have not met the compulsory threshold for VAT/GST/Sales tax registration or have chosen not to opt for voluntary registration as a VAT/GST/Sales tax vendor, there are steps to follow when dealing with VAT/GST/Sales tax codes in a template Set of Books:

1. VAT/GST/Sales Tax accounts: If you are not registered as a VAT/GST/Sales Tax vendor, you need to review the basic VAT/GST/Sales Tax accounts included in the "*Current liabilities*" section in the Chart of Accounts of your selected template Set of Books, downloaded from the "*Let osFinancials help you to create a Set of Books?*" option. You need to set the "*Status*" of the VAT/GST/Sales Tax accounts to "*Disabled*" (Setup → Accounts menu on the Setup ribbon).

Delete or set VAT/GST/Sales Tax accounts as disabled:

If you have not processed any transactions in Batches (Journals or Documents), you may choose to delete these VAT/GST/Sales Tax accounts. The option to keep these VAT/GST/Sales Tax accounts, but to disable them, allows you to review enable and edit the VAT/GST/Sales Tax accounts when you need to registered as a VAT/GST/Sales Tax vendor.

You may print a "Tax code - Tax rates" report on the User reports → Tax menu on the Reports ribbon to print a list of Tax codes and their respective percentages and the status whether the Tax code is enabled or disabled).

2. VAT/GST/Sales Tax Registration number: Do not enter the VAT/GST/Sales Tax registration number in the "*Tax reg. no.*" field on the Setup → Company Info (Address tab) should be left blank, as you are not registered as a vendor for these taxes. If you have a different registration number or certificate related to tax exemptions, you should enter that information. It's important to accurately reflect your tax status and provide any relevant registration numbers or certificates to ensure compliance with tax regulations.

3. VAT/GST/Sales Tax - Document Headings: The decision to modify the document name should be guided by the legal requirements and guidelines of your tax jurisdiction to ensure compliance with invoicing regulations. By default, the document type "*Invoice*" will print on document layout files for the following documents will print on document layout files as follows:

    - Change Document Headings: Change the "*Invoice*" to "*Tax Invoice*" for your specific country or jurisdiction and/or industry (Setup → Documents setup menu on the Setup ribbon). Check the headings for the other document types (Credit notes, Quotes, Purchases, Supplier returns and Orders), and change the headings, if necessary.

    - Change the Names of Document Types: You may need to change the appropriate document type names such as *"Invoice," "Credit note", "Quote", "Purchase", "Supplier return",* or *"Order"* for your specific country or jurisdiction and/or industry. These document type names will display in the osFinancials5/TurboCASH5 interface and will print on " *Translatable NOTAX Document Layout Files with Dynamic Document Types*" such as "*Layout file*", "*Document layout*" and "*Document layout (15 code)*" document layout files.

    - POS Tax Invoice: "*POS Tax Invoice*" will be printed on the "*POS-STARTSP100, POS 1*" and "*POS 2*" document layout files. If you need to change the "*POS Tax Invoice*" label, you need to go to Tools → Customise language on the Setup ribbon and change the description of "*LabelID - 906014*".

4. Select Document Layout Files: By default, "*Layout file*" is pre-selected in Set of Books templates. The

default "*Layout file*" supports Tax (VAT/GST/Sales Tax) related expressions and label descriptions. If you are not registered as a Tax (VAT/GST/Sales Tax) vendor, you may select the *Translatable NO-TAX Document Layout Files with Dynamic Document Types*, such as "*NO-TAX Layout file*", "*NO-TAX Document layout*" and "*NO-TAX Document layout (15 code)*" document layout files, which excludes tax related expressions and labels.

5. Stock items/Inventory items Tax classes: When planning, designing and adding your stock/inventory system, you may create Tax classes to link your stock items (goods/services/products) to your Sales, Cost of Sales and Stock control accounts). Since the Output tax and Input tax codes, is not applicable in these cases, you may need to select the "*Empty*" option for Output tax and Input tax codes. (Setup → Stock information menu (Tax classes tab) on the Setup ribbon).

> *You may print a "Tax classes report" report on the Reports → Stock item listing - Tax classes menu (Reports ribbon) to print a list of Tax classes for Output tax, Input tax and their respective sales, cost of sales and stock control accounts. The Output tax and Input Tax code should be empty.*

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

VAT/GST/Sales Tax - Existing User Opting for Tax Deregistration

---

Deregister for VAT/GST/Sales Tax - Steps in osFinancials

If you're an existing osFinancials5/TurboCASH5 user who has decided to cancel your VAT/GST/Sales Tax registration, this is your selection. Following this route involves steps to update your tax accounts' status to *'Disabled*,' and possibly remove them if unposted transactions are absent. Additionally, you need to process all tax-related transactions until the date of cancellation of registration, ensuring accurate records. After the date of deregistration, it's crucial to adjust your system to process transactions without Tax (VAT/GST/Sales tax) to reflect the updated tax-related changes accurately. Managing this process diligently will help maintain the integrity of your financial records.

If you do not comply with the requirements for Voluntary Registration or if you apply for de-registration, or for some other reason your registration is cancelled, the Tax Authority will send you a notice of your actual cancellation date.

After this date, you may not use the VAT/GST/Sales Tax number again and all VAT/GST/Sales (Output Tax less the Input Tax) (on transactions before or on the date of cancellation of VAT/GST/Sales Tax must be submitted on a return and a final payment must be done to the Tax Authority. If you continue to process

transactions after the cancellation date, you will need to select "*No Tax*" code for all transactions.

If your business ceases or you stop trading you need to consult with your tax authority or accountant, since there may be some specific requirements with regard to the keeping or disposing of assets, etc. and your final VAT returns /GST returns /Sales Tax returns and payments.

To Cancel VAT/GST/Sales Tax Registration in osFinancials5/TurboCASH5:

The following procedure needs to be followed in the case of Cancellation of Registration (if you do not stop trading):

1. VAT/GST/Sales Tax Configuration: Once you have received a notification of the cancellation or deregistration of VAT/GST/Sales Tax from your Tax Authority, note the date of cancellation or deregistration of VAT?GST/Sales Tax.
2. Capture and process transactions until date of cancellation of VAT/GST/Sales Tax Registration:
    - Batch (journal) processing: You need to capture an process all transactions in batches (journals) and post (update) the batches (journals) containing transactions up to the date of deregeistration (Batch entry / Journal entry on the Default ribbon).
    - Repeating Batch (journal) Transactions: Import repeating batch transactions into normal batches and process (if necessary) batches. (Edit → Repeating transactions menu on the Default ribbon).
    - Document processing You need to process any documents (post) Documents (Invoices, Credit notes, Purchases, Supplier returns documents for this date. In some cases you need to check and finalize the Quotes and convert them to Invoices and Orders and convert them them to Purchase documents. (Documents on the Default ribbon).
    - Repeating Invoices: Process any repeating invoices up to the date of deregeistration (Edit → Repeating invoices menu on the Default ribbon).
3. Configure Tax accounts after date of cancellation of VAT Registration:
    - Tax Accounts Status: Set the "*Status*" of Tax codes or Tax accounts to "*Disabled*" to prevent further selecting the transactions on the Tax lookup when processing the transactions. (Setup → Accounts menu on the Setup ribbon). In Batches (journals) you may select the "No tax" option on the Options for this batch (F:10) to hide the Tax column and Tax lookup in batches (journals).

You will not be allowed to delete these Tax accounts if transactions was already processed for the VAT accounts. You still need to print reports from the historical data.

- Stock items / Inventory items / Products: Your Stock items Inventory items Products will still display the Output tax / Input Tax codes with the respective percentages., including Zero-rated and Exempt tax codes with a 0%. Create a Tax class with a "*No Tax*" code (Setup → Stock information menu - Tax classes tab on the Setup ribbon).
- Link Stock items / Inventory items / Products to the "No Tax" tax class: Stock items on the Default ribbon. You may edit individual stock items, or more conveniently, use the Stock item grid to filter and link multiple Stock items / Inventory items / Products.

Note: If you use different accounts or sub accounts for Sales, Cost of Sales and Stock control you need to create a Tax class for each of your accounts with the "No Tax" code.

4. Edit unposted transactions in batches after the date of cancellation of VAT Registration:
   - Unposted Batches (journals): If you have processed unposted transactions in bathes (journals) and documents after the deregistration date you need to edit these transactions to change these transactions to the "*No Tax*" code.
   - Unposted Documents: In the case of documents, after the deregistration date, you may need to reselect the Stock items / Inventory items / Products to the "*No Tax*" (if necessary).
5. VAT / GST Reference number / Tax Invoice:
   - Remove VAT/GST Registration number: Remove your VAT/GST/Sales Tax Registration Number in the Tax Reg. No. field on the Setup → Company Info (Address tab) menu. Make sure that you have printed or stored all unprinted documents in a PDF format for future reference) before and on deregistration date.
   - Change Document Headings: Change the "*Tax Invoice*" to "*Invoice*" (Setup → Documents setup menu on the Setup ribbon). Check the headings for the other document types (Credit notes, Quotes/Estimates, Purchases, Supplier returns and Orders), and change the headings, if necessary.
   - Layout files: Select a Layout file for "*No Tax*" in the following options:
     - § Global setting in Setup → Documents setup menu on the Setup ribbon. If you have any specific layout files selected for specific debtor accounts or creditor accounts, select the "*No Tax*" layout files. (Delivery address tab of Debtors / Delivery address tab of Creditors on the Default ribbon).
     - § Debtors - Delivery address tab: If you have any specific layout files selected for specific debtor (customer/client) accounts for Layout file 1 (Invoices), Layout file 2 (Credit notes) and/or Layout file 3 (Quotes/Estimates), select the "*No Tax*" layout files.

- § Creditors - Delivery address tab: If you have any specific layout files selected for specific creditor (supplier/vendor) accounts for Layout file 1 (Purchases), Layout file 2 (Supplier returns) and/or Layout file 3 (Orders), select the "*No Tax*" layout files.
- § Documents - If Layout file 1, Layout file 2, Layout file 3 and/or Layout file 4 is selected, you need to select the "*No Tax*" layout files.

6. VAT/GST/Sales Tax Reconciliation / Returns / Accounts:

- o VAT/GST/Sales Tax Returns: The final VAT return should include all transactions until the data of deregistration.
- o VAT reconciliation: Perform a final VAT reconciliation to ensure that all VAT transactions are accounted for correctly before deregistration.
- o VAT/GST/Sales Tax Control Account: The VAT / GST Control Account should display a zero balance after the amount matching with your VAT return is paid to the tax authority. If an refund is due by the Tax authority, the amount should be matching your VAT/GST return. Once the refund is received from the Tax authority, the VAT/GST/Sales Tax control account will reflect a zero balance. as there are no outstanding VAT liability or receivable after deregistration.
- o VAT/GST/Sales Tax Payment Account Set the VAT/GST/Sales Tax Payment account's "*Status*" to "*Disabled*". (Setup → Accounts menu on the Setup ribbon).

> *You may print a "Tax code - Tax rates" report on the User reports → Tax menu on the Reports ribbon to print a list of Tax codes and their respective percentages and the status whether the Tax code is enabled or disabled).*

It's advisable to consult with your local tax authority or an accountant to ensure proper compliance with tax regulations during the cancellation process.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

---

VAT/GST/Sales tax codes - Template (Set of Books)

Most template Set of Books, downloaded from the "*Let osFinancials help you to create a Set of Books?*" option, already includes basic VAT/GST/Sales tax accounts in the Current Liabilities section in the Chart of Accounts.

Before you start to process any transactions and documents or link your Stock items / Inventory items / Products to the Output and Input tax accounts, you need to check your tax codes and percentages (If you are registered as a VAT/GST/Sales Tax vendor).

If you are registered as a VAT/GST/Sales Tax vendor, you need to check that the all the relevant Tax codes and percentages applicable to your country and jurisdiction is correct and reflect the correct percentages and aligns with your VAT/GT/Sales tax return. You may need to add or delete any tax codes, where necessary. Note if Zero-rated tax or exempt tax is applicable to your country or jurisdiction needs to be included with a 0%. (Setup → Accounts menu on the Setup ribbon).

Tip: You may print a "*Tax code - Tax rates*" report on the User reports → Tax menu on the Reports ribbon to print a list of Tax codes and their respective percentages and the status whether the Tax code is enabled or disabled).

Register for VAT

What is requirements and changes in osFinancials5/TurboCASH5 when a business register for VAT?

When a business registers for Value Added Tax (VAT), there are several requirements and changes that may need to be implemented in osFinancials5/TurboCASH5 to ensure compliance with VAT regulations. Here are some key considerations:

1. VAT Configuration: The accounting software should have a VAT configuration option where you can set the applicable VAT rates and any specific VAT rules based on your business activities. You'll need to enter the standard VAT rate, zero-rated VAT rate, exempt VAT rate, and any other applicable rates.
2. VAT Accounts: Ensure that the Chart of Accounts in osFinancials5/TurboCASH5 includes all the necessary VAT accounts, such as Output VAT, Input VAT, VAT on Imports, VAT Adjustments, VAT Bad Debt Relief, VAT on Assets and Disposals, etc. These accounts will be used to accurately record VAT-related transactions.
3. VAT Invoices and Reports: The accounting software should be able to generate VAT invoices and reports required for VAT compliance. Ensure that the VAT amount is correctly calculated and displayed on invoices and reports.
4. VAT Calculation: The accounting software should be capable of automatically calculating the VAT amount on sales and purchases based on the applicable VAT rates. This calculation should be accurate and in compliance with VAT regulations.
5. Reverse Charge Mechanism: If your business deals with reverse charge transactions, where the

recipient accounts for VAT instead of the supplier, the accounting software should support this mechanism and correctly account for the VAT.

6. VAT Returns: osFinancials5/TurboCASH5 should have the functionality to generate VAT returns, including the VAT amounts collected and paid, and assist in completing the required VAT forms accurately.
7. VAT Payment and Refund: The software should help track VAT payments to be made to the tax authorities or refunds to be claimed, ensuring proper cash flow management.
8. VAT Compliance Reporting: The accounting software should provide reports that assist with VAT compliance, such as VAT control reports, VAT audit trails, and VAT reconciliation reports.
9. VAT Documentation: Make sure you have access to the necessary documentation and guides provided by osFinancials5/TurboCASH5 or third-party resources to understand the VAT functionality and how to correctly set it up in the software.

When implementing VAT in accounting software, it's crucial to thoroughly review the software's VAT features, consult with accounting professionals or tax advisors, and perform thorough testing to ensure accurate VAT calculations and compliance with VAT regulations specific to your country or jurisdiction. Keep in mind that tax laws and requirements may change, so it's essential to keep the software updated and be aware of any updates or changes related to VAT.

What is requirements and changes in osFinancials5/TurboCASH5 when a business deregister for VAT?

When a business deregisters for Value Added Tax (VAT), there are several requirements and changes that may need to be implemented in osFinancials5/TurboCASH5 to reflect the new VAT status accurately. Here are some key considerations:

1. VAT Configuration: Update the VAT configuration in osFinancials5/TurboCASH5 to indicate that the business is no longer registered for VAT. This may involve changing VAT rates to zero and updating any VAT-related settings.
2. VAT Accounts: Depending on the country's tax regulations, you may need to close or modify specific VAT accounts that are no longer applicable after deregistration. For example, you may need to close the Output VAT and Input VAT accounts.
3. VAT Invoices and Reports: Modify the layout of invoices and reports to indicate that the business is no longer VAT-registered. Remove or update any VAT-related information, such as the VAT number, from invoices and reports.
4. VAT Returns: Ensure that osFinancials is configured to stop generating VAT returns since the business

is no longer required to submit them after deregistration.

5. VAT Control Account: Adjust the VAT Control Account to zero out the balance, as there should be no outstanding VAT liability or receivable after deregistration.
6. VAT Reconciliation: Perform a final VAT reconciliation to ensure that all VAT transactions are accounted for correctly before deregistration.
7. VAT Payment and Refund: If there are any pending VAT payments or refunds, ensure that they are accounted for and settled appropriately before deregistration.
8. Reverse Charge Mechanism: If your business was dealing with the Reverse Charge Mechanism, update osFinancials5/TurboCASH5 to reflect that this mechanism is no longer applicable.
9. Accounting Treatment: Review the accounting treatment of sales and purchases to ensure that VAT is no longer considered in financial transactions.
10. Compliance Reporting: Remove any VAT compliance reporting functionalities from osFinancials5/TurboCASH5, as the business is no longer required to report VAT.
11. Record Keeping: Retain all necessary VAT records for the required period as per the tax regulations.

It's crucial to follow the deregistration process as specified by the local tax authorities and comply with any reporting requirements related to the deregistration. Before making any changes in osFinancials5/TurboCASH5, businesses should consult with accounting professionals or tax advisors to ensure that the correct adjustments are made and that the business remains compliant with tax laws.

Additionally, businesses should retain records of their VAT deregistration for future reference and potential tax audits.

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

VAT/GST/Sales - Compulsory registration / Voluntary registration

---

Compulsory registration for VAT/GST/Sales Tax?

What is Compulsory registration for VAT/GST/Sales Tax?

Compulsory registration for VAT/GST/Sales Tax refers to the legal requirement imposed by tax authorities on businesses to enrol as tax vendors and collect sales tax or value-added tax (VAT) from their customers. This requirement is triggered when a business's taxable turnover exceeds a specified threshold

determined by the tax jurisdiction. Once the threshold is crossed, the business becomes obligated to register for VAT/GST/Sales Tax, regardless of whether it is engaged in the provision of goods or services.

Compulsory registration aims to ensure that businesses generating a certain level of revenue contribute their share of taxes to the government. This helps fund public services, infrastructure, and other government initiatives. Once registered, the business is responsible for charging the appropriate tax rate on eligible transactions, maintaining accurate records, and remitting the collected tax to the tax authority within specified timelines.

Businesses that fail to comply with the compulsory registration requirement may face penalties, fines, or legal action. It's important for businesses to monitor their turnover and be aware of the thresholds set by their jurisdiction to avoid any potential non-compliance issues.

In which countries is Compulsory registration for VAT/GST/Sales Tax applicable?

Compulsory registration for VAT/GST/Sales Tax is applicable in many countries around the world. The specific rules and thresholds for compulsory registration can vary significantly from one country to another. Here are some countries where compulsory registration for VAT/GST/Sales Tax is commonly applicable:

1. European Union (EU) Member States: Most EU countries have VAT systems that include compulsory registration thresholds.
2. United Kingdom: The UK has its own VAT system with compulsory registration thresholds.
3. Australia: The Australian Goods and Services Tax (GST) system includes compulsory registration thresholds.
4. Canada: Canada has a federal Goods and Services Tax (GST) and Provincial Sales Tax (PST) systems with thresholds for registration.
5. India: India has a Goods and Services Tax (GST) system with compulsory registration thresholds.
6. South Africa: South Africa has a Value Added Tax (VAT) system with thresholds for compulsory registration.
7. New Zealand: New Zealand has a Goods and Services Tax (GST) system with compulsory registration thresholds.
8. Singapore: Singapore's Goods and Services Tax (GST) system includes compulsory registration thresholds.
9. Malaysia: Malaysia has a Goods and Services Tax (GST) system with thresholds for compulsory registration.

10. Brazil: Brazil has a Value Added Tax (VAT) system known as ICMS, which includes compulsory registration thresholds.
11. China: China has a Value Added Tax (VAT) system with thresholds for compulsory registration.
12. Japan: Japan has a Consumption Tax system with thresholds for compulsory registration.

These are just a few examples, and there are many other countries around the world where compulsory registration for VAT/GST/Sales Tax applies. It's important to note that the rules and thresholds can vary widely, so businesses should consult their local tax authorities for specific information related to their jurisdiction.

Voluntary registration for VAT/GST/Sales Tax

What is Voluntary registration for VAT/GST/Sales Tax?

Voluntary registration for Value Added Tax (VAT), Goods and Services Tax (GST), or Sales Tax refers to the option available to businesses to register for these taxes even if their turnover or sales do not exceed the threshold for compulsory registration. In many countries, there is a specific threshold limit above which businesses are required to register for VAT/GST/Sales Tax, and below which registration is optional or voluntary.

Voluntary registration allows businesses to proactively opt into the VAT/GST/Sales Tax system, even if they are not legally obligated to do so. This can have several benefits and implications:

Benefits:

- Input Tax Credit: Once registered, businesses can claim input tax credits for the VAT/GST/Sales Tax they pay on their purchases. This reduces the overall tax burden on the business.
- Credibility: Voluntarily registering for VAT/GST/Sales Tax can enhance a business's credibility, especially when dealing with other registered businesses or government entities.
- Competitive Advantage: Being registered for VAT/GST/Sales Tax can provide a competitive advantage over non-registered competitors, as customers may prefer to deal with registered businesses.
- Business Expansion: Voluntary registration may be beneficial for businesses that anticipate exceeding the threshold in the near future or plan to expand their operations.

Implications:

- Tax Collection: Once registered, the business becomes responsible for collecting VAT/GST/Sales Tax from its customers and remitting it to the tax authorities.

- Compliance Obligations: Voluntary registration comes with compliance responsibilities, including issuing tax invoices, maintaining records, and filing periodic tax returns.
- Costs and Administrative Burden: There may be additional administrative costs associated with VAT/GST/Sales Tax compliance, such as record-keeping and reporting requirements.
- Liability: Registered businesses must ensure they charge the correct amount of tax and remit it on time. Any errors or late payments can result in penalties.

The decision to voluntarily register for VAT/GST/Sales Tax should be carefully considered, taking into account the specific business circumstances, industry, and future plans. Some businesses may choose voluntary registration to take advantage of input tax credits and enhance their market position, while others may prefer to delay registration until they reach the compulsory threshold to avoid the associated compliance obligations and costs.

As tax laws and regulations can vary significantly between countries, businesses should consult with local tax authorities or seek advice from accounting professionals or tax advisors to understand the implications and requirements of voluntary registration in their specific jurisdiction.

In which countries have the option to register voluntarily for VAT/GST/Sales Tax?

The option for voluntary registration for Value Added Tax (VAT), Goods and Services Tax (GST), or Sales Tax is available in various countries around the world. In these countries, businesses have the choice to register for VAT/GST/Sales Tax even if their turnover or sales do not exceed the threshold for compulsory registration. This allows businesses to voluntarily become part of the VAT/GST/Sales Tax system, which can have certain benefits and implications. Here are some examples of countries where voluntary registration is commonly allowed:

1. United Kingdom: In the UK, businesses with taxable turnover below the VAT registration threshold can choose to register voluntarily for VAT. As of ChatGPT's last update in September 2021, the registration threshold was £85,000.
2. Australia: Australia also offers voluntary GST registration for businesses with annual turnover below the GST registration threshold. As of ChatGPT's last update, the GST registration threshold was AUD $75,000.
3. New Zealand: In New Zealand, businesses with turnover below the GST registration threshold can voluntarily register for GST. As of ChatGPT's last update, the GST registration threshold was NZD $60,000.
4. Canada: Canada allows businesses with sales below the GST/HST registration threshold to voluntarily register for GST/HST.

5. Singapore: Singapore offers voluntary GST registration for businesses with annual turnover below the compulsory registration threshold. As of ChatGPT's last update, the GST registration threshold was SGD $1 million.
6. India: In India, businesses with turnover below the compulsory GST registration threshold can voluntarily register for GST.
7. South Africa: South Africa allows voluntary VAT registration for businesses with turnover below the compulsory VAT registration threshold. As of ChatGPT's last update, the VAT registration threshold was ZAR R1 million.

It's essential for businesses to carefully consider the implications of voluntary registration, as it means they will be required to charge VAT/GST/Sales Tax on their sales and may also be eligible to claim input tax credits on their purchases. Voluntary registration can have both advantages and disadvantages, and businesses should weigh the benefits against the administrative burden and costs associated with compliance.

As tax regulations may change over time, it is advisable to consult with local tax authorities or seek advice from accounting professionals or tax advisors to understand the current requirements and implications of voluntary registration in each specific country.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with a Help Authoring Tool

---

Key points when adding tax codes and the format of your VAT return

Absolutely, when setting up tax codes in your Chart of Accounts, it's important to consider the format and requirements of your VAT return. The tax codes you use in osFinancials5/TurboCASH5 should align with the boxes (fields) and codes used in your VAT return to ensure accurate reporting and compliance with tax regulations. Here are some key points to consider:

1. Box Alignment / Field Alignment: Each box on your VAT return corresponds to specific types of transactions. The tax codes you use should match the box numbers on your VAT return. This alignment helps ensure that the amounts recorded in your accounts can be easily transferred to the correct boxes on the return.
2. VAT Rates: The tax codes should accurately represent the VAT rates that apply to different types of transactions. Ensure that the tax rates in your tax codes match the rates specified by tax authorities.

3. Specific Transactions: Some boxes on the VAT return might relate to specific types of transactions, such as Reverse Charge or Goods and Services subject to different rates. Make sure your tax codes cover these specific scenarios.
4. Additional Information: Some VAT returns may require additional information or notes for certain transactions. Consider adding relevant notes or references in your Chart of Accounts to help with reporting.
5. Changes in Regulations: VAT regulations can change, and tax authorities may update the format of VAT returns. Stay informed about any changes and update your Chart of Accounts and tax codes accordingly.
6. Consultation: If you're uncertain about how to structure your tax codes to align with your VAT return, consider consulting with accounting professionals or tax advisors. They can provide guidance based on their expertise and knowledge of current regulations.
7. Regular Reconciliation: Regularly reconcile the amounts in your tax codes with the totals reported on your VAT return. This helps catch any discrepancies and ensures accurate reporting.

By considering the format of your VAT return when setting up tax codes, you can streamline your reporting process, reduce the risk of errors, and ensure that your financial records accurately reflect your tax obligations. Keep in mind that accurate VAT reporting is crucial for compliance and maintaining the financial health of your business.

Tax Code Numbering Structure: Flexibility

Adding flexibility to your tax code numbering structure by leaving spaces for additional tax codes is a smart approach. This ensures that your Chart of Accounts remains adaptable to changes in legislation, new VAT classifications, or unforeseen requirements. Here's how you could incorporate this idea into your tax code numbering structure:

1. Structured Tax Code Numbers: Establish a structured numbering system for your tax codes. For example, as you mentioned, use numbers like "*T2400-010*" and "*T2400-020*" for Output Tax categories.
2. Reserved Spaces: Leave reserved or unused numbers within your structured sequence to allow for the addition of new tax codes without disrupting the existing structure. For instance, you could leave gaps like "*T2400-030*" and "*T2400-040*" to accommodate future tax codes.
3. Flexibility for Changes: If tax regulations change or new VAT classifications are introduced, you can easily insert new tax codes within the reserved spaces without renumbering existing codes.
4. Documentation and Consistency: Keep documentation that explains the purpose of each reserved space and any potential scenarios for future tax code additions.

5. Review and Update: Periodically review your tax code structure to assess whether new codes are needed due to changes in legislation or business requirements.

6. Professional Guidance: If you're unsure about the best approach for structuring your tax code numbers, consider seeking advice from accounting professionals or tax advisors who are familiar with VAT regulations and requirements.

By leaving reserved spaces for additional tax codes, you're proactively planning for potential changes and ensuring that your Chart of Accounts remains adaptable and compliant with evolving VAT regulations. This flexibility can save you time and effort in the long run while allowing your accounting system to accommodate new tax-related scenarios seamlessly.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

VAT/GST/Sales Tax - Selecting the No Tax Code

Selecting the Empty option as No Tax Code

Transactions that do not involve Tax (VAT/GST/Sales tax) should typically be recorded using the "*Empty*" option as the "*No Tax*" code, depending on how your Set of Books in osFinancials5/TurboCASH5 labels it. These transactions are not included in the Tax (VAT/GST/Sales tax) return because they don't have a Tax (VAT/GST/Sales tax) component. Here are some examples of transactions that usually do not have VAT and should be recorded using an "*Empty*" option as the "*No Tax*" code:

1. Opening Balances: Transactions related to opening balances, such as the transfer of account balances from a previous accounting period or accounting system, generally do not have Tax (VAT/GST/Sales tax) implications.

2. Payments Received from Debtors: When you receive payments from your customers (debtors), the payment amount usually corresponds to the invoice amount without any additional Tax (VAT/GST/Sales tax).

3. Payments Made to Creditors: Payments made to your suppliers (creditors) for goods or services usually do not include Tax (VAT/GST/Sales tax) because Tax (VAT/GST/Sales tax) is usually accounted for when the purchase invoice is recorded.

4. Adjustments: Certain accounting adjustments, like correcting entries, may not involve Tax (VAT/GST/Sales tax). For example, adjusting entries to correct errors in accounts might not have Tax (VAT/GST/Sales tax) implications.

5. Accruals: Accruals represent expenses or revenues that have been incurred but not yet recorded. These transactions are usually recorded without Tax (VAT/GST/Sales tax).
6. Internal Transfers: Transfers of funds or assets within your organization, such as between different bank accounts or departments, generally do not involve Tax (VAT/GST/Sales tax).
7. General Journal Entries: Journal entries for internal bookkeeping purposes, such as reclassifications or allocations, may not have Tax (VAT/GST/Sales tax) implications.
8. Depreciation: Entries related to depreciation of assets do not involve Tax (VAT/GST/Sales tax).
9. Dividend Payments: When paying dividends to shareholders, the payment amount is typically not subject to Tax (VAT/GST/Sales tax).
10. Loan Transactions: Transactions related to loans, interest payments, and repayments usually do not involve Tax (VAT/GST/Sales tax).
11. Employee Salaries: Payments made to employees as salaries usually do not include Tax (VAT/GST/Sales tax).
12. Interest Income: Income earned from interest on savings or investments may not include Tax (VAT/GST/Sales tax).

Remember that specific circumstances and regulations may vary, so it's essential to review each transaction type in the context of your business and the applicable Tax (VAT/GST/Sales tax) rules. If you're unsure about the Tax (VAT/GST/Sales tax) treatment of certain transactions, it's a good idea to consult with an accounting professional or tax advisor to ensure accurate and compliant recording.

Selecting the "*No Tax*" code in osFinancials5/TurboCASH5 when processing transactions

Transactions that do not involve Tax (VAT/GST/Sales tax) should typically be recorded using an "*Empty*" or "*No Tax*" code, depending on how your Set of Books in osFinancials5/TurboCASH5 labels it. In osFinancials when processing transactions in batches (journals) and documents (sales documents such as invoices, credit notes, quotes, point-of-sales invoices, and purchase documents such as purchases, supplier returns and orders) you need to select the "*Empty*" option as the "*No Tax*" code.

Selecting the "No Tax" code in osFinancials5/TurboCASH5 in Batch processing

In osFinancials5/TurboCASH5, you may configure specific batches (journals) to hide the Tax lookup and Tax column to process transactions that are not Tax (VAT/GST/Sales tax)-related. This is particularly useful when all transactions within a batch do not involve VAT.

However, if "Exempt" or "Zero-rated" tax is applicable to certain transactions, you need to select the appropriate tax codes from the Tax lookup.

You can hide the Tax (VAT/GST/Sales tax) lookup and Tax (VAT/GST/Sales tax) column in all batches (journals) in the following scenarios:

1. New User in osFinancials5/TurboCASH5 without Tax Registration: If you're new to osFinancials5/TurboCASH5 and not a registered VAT/GST/Sales Tax vendor.
2. Existing User Opting for Tax Deregistration: If you're an existing osFinancials5/TurboCASH5 user who has decided to cancel your VAT/GST/Sales Tax registration, or if you have been served a notice of cancellation of registration from your tax authority.

Using Tax classes to link specific items to the "No Tax" code

In osFinancials5/TurboCASH5, when configuring your inventory (stock items / products), you may use the Tax classes to link (pre-configure) such items on which "*No Tax*" code is applicable to specific items.

Using Tax classes to link specific items to the "*Empty*" option as the "*No Tax*" code in osFinancials5/TurboCASH5 is a useful approach for configuring your inventory, especially when dealing with products or items that are not subject to Tax (VAT/GST/Sales tax). This allows you to pre-configure items that consistently fall under the "*No Tax*" category, ensuring that the correct tax treatment is applied automatically during transactions.

By associating items with the appropriate Tax classes, you streamline the process of recording transactions for those items, as the system will automatically apply the "*Empty*" option as the "*No Tax*" code when those items are included in documents such as sales invoices, credit notes, and purchase orders. This helps to reduce manual errors and ensures consistent and accurate Tax (VAT/GST/Sales tax) treatment across your inventory.

Using Tax classes in this manner also provides an efficient way to manage items that have consistent tax treatment, freeing up time for your financial team to focus on more complex transactions and tasks.

Zero-rated and Exempt VAT classifications

For transactions that are subject to either zero-rated or exempt Tax (VAT/GST/Sales tax) classifications, it's essential to select the appropriate tax code that aligns with your tax authority's regulations and guidelines. These transactions may not involve the standard rate of VAT, but they still require accurate recording and reporting in accordance with the specific Tax (VAT/GST/Sales tax) classification they fall under.

The distinction between "*Zero-rated*" and "*Exempt*" Tax (VAT/GST/Sales tax) classifications is important because they have different implications for Tax (VAT/GST/Sales tax) recovery on related expenses. Zero-

rated supplies allow for the recovery of Input Tax (VAT/GST/Sales tax), while exempt supplies generally do not.

When processing transactions, always choose the correct tax code that corresponds to the Tax (VAT/GST/Sales tax) classification applicable to the transaction. This ensures that your Tax (VAT/GST/Sales tax) records accurately reflect the nature of the transaction and comply with your tax authority's requirements. If you're uncertain about which tax code to use for a particular transaction, consulting with tax professionals or referring to your tax authority's guidelines is recommended.

Created with the Standard Edition of HelpNDoc: Transform Your Word Document into a Professional eBook with HelpNDoc

Reverse Charge Mechanism - Reverse Charge Mechanism

What is the Reverse Charge Mechanism for VAT/GST?

The Reverse Charge Mechanism (RCM) is a tax rule used in some countries' value-added tax (VAT) or goods and services tax (GST) systems. Under the Reverse Charge Mechanism, the responsibility for accounting and reporting the tax shifts from the supplier of goods or services to the recipient (buyer) of those goods or services. This means that the recipient becomes liable for paying the VAT/GST directly to the tax authorities, instead of the supplier charging and remitting the tax.

The Reverse Charge Mechanism is typically applied in the following scenarios:

1. Imports: When a business imports goods from another country, the Reverse Charge Mechanism requires the importer (recipient) to account for and pay the VAT/GST on the imported goods directly to the tax authorities. This ensures that the tax is collected by the country where the goods are consumed, rather than the country of origin.
2. Services from Overseas Suppliers: When a business receives services from a supplier located in another country, the recipient of the services is often required to account for and pay the VAT/GST on those services under the Reverse Charge Mechanism.
3. Certain Domestic Transactions: In some countries, the Reverse Charge Mechanism may also be applied to specific domestic transactions, such as construction services, where the recipient of the services becomes responsible for reporting and paying the VAT/GST.

The Reverse Charge Mechanism is designed to prevent tax evasion and ensure that VAT/GST is collected on cross-border transactions and certain domestic transactions where the supplier is not located in the same country as the recipient. It places the responsibility for tax compliance on the recipient, who will

include the VAT/GST amount in their own VAT/GST return and remit the tax to the tax authorities.

It's important for businesses to be aware of the Reverse Charge Mechanism rules in their respective countries and properly account for and report the VAT/GST when it applies to their transactions. Compliance with the Reverse Charge Mechanism is essential to avoid penalties and ensure accurate tax reporting.

In which countries is the Reverse Charge Mechanism for VAT/GST applied?

The Reverse Charge Mechanism for VAT/GST is commonly used in various countries around the world. It's important to note that the application and specific rules of the mechanism can vary from country to country. As of ChatGPT's last update in September 2021, here are some countries where the Reverse Charge Mechanism for VAT/GST is commonly applied:

1. European Union (EU) Member States: The Reverse Charge Mechanism is commonly used within the EU for intra-community transactions to prevent double taxation and simplify cross-border trade.
2. United Kingdom (UK): The Reverse Charge Mechanism is used in the UK for certain supplies of goods and services, including construction services.
3. Australia: Australia applies the Reverse Charge Mechanism for imported services and digital products purchased by Australian businesses from non-resident suppliers.
4. Canada: Canada applies the Recipient-Driven VAT system, which is a type of reverse charge mechanism, for certain imported services.
5. Singapore: The Reverse Charge Mechanism applies to certain imported services and goods in Singapore.
6. India: The Reverse Charge Mechanism is used in India for specific goods and services, where the recipient is responsible for paying the tax to the government.
7. New Zealand: New Zealand applies the Reverse Charge Mechanism for imported services and other specified transactions.
8. Malaysia: The Reverse Charge Mechanism is applied in Malaysia for certain imported services.
9. South Africa: South Africa applies the Reverse Charge Mechanism for certain imported services.
10. Norway: Norway applies the Reverse Charge Mechanism for certain imported services.
11. Switzerland: The Reverse Charge Mechanism is used in Switzerland for specific transactions, including cross-border services.

12. Turkey: Turkey applies the Reverse Charge Mechanism for certain goods and services.
13. Ukraine: Ukraine applies the Reverse Charge Mechanism for imported services and certain transactions.

Please note that tax laws and regulations can change, and the applicability of the Reverse Charge Mechanism may vary based on the specific circumstances and transactions. It's advisable to consult the tax authorities of each country or a tax professional for the most up-to-date and accurate information regarding the Reverse Charge Mechanism for VAT/GST.

Is the Reverse Charge Mechanism applicable to Sales Tax and Use Tax?

The Reverse Charge Mechanism is typically associated with Value Added Tax (VAT) and Goods and Services Tax (GST) systems, rather than with Sales Tax and Use Tax systems. While both Sales Tax and Use Tax systems and VAT/GST systems are consumption-based taxes, they operate differently and have distinct mechanisms.

In Sales Tax and Use Tax systems (common in the United States), the tax is generally collected at the point of sale by the seller and remitted to the tax authorities. There is usually no direct concept of the Reverse Charge Mechanism in these systems. Instead, the responsibility for collecting and remitting the tax falls on the seller, not the buyer.

In VAT/GST systems, including the Reverse Charge Mechanism, the tax liability can be shifted from the seller to the buyer in certain circumstances. This can occur when the buyer is liable to account for the tax instead of the seller, typically for cross-border transactions or specific goods and services.

It's important to note that tax terminology and mechanisms can vary between countries, and the Reverse Charge Mechanism may have different names or concepts in different jurisdictions. If you're looking for information specific to a certain jurisdiction or tax system, it's recommended to consult the local tax authority or a tax professional for accurate guidance.

Reverse Charge Mechanism for the VAT - Is this applicable to South Africa?

Yes, the Reverse Charge Mechanism is applicable in South Africa, and businesses that engage in reverse charge transactions must account for VAT under this mechanism. The Reverse Charge Mechanism in South Africa is commonly referred to as the "*Imported Services VAT*" system.

Under the Imported Services VAT system, if a South African VAT-registered business acquires services from a foreign supplier that is not registered for VAT in South Africa, the recipient (buyer) of the services is

responsible for accounting for the VAT on those imported services. In other words, the recipient must self-assess the VAT and include it in their VAT return as both the output tax and the input tax.

This means that the recipient of the services must calculate the VAT on the imported services and account for it as follows:

1. Include the VAT amount as both output tax (VAT payable) on their VAT return's output tax section.
2. Simultaneously, claim the same VAT amount as input tax (VAT refundable) on their VAT return's input tax section.

By doing so, the business accounts for the VAT on the imported services without the foreign supplier having to register for VAT in South Africa.

For example, if a South African business acquires services from a foreign supplier for R10,000, and the VAT rate is 15%, the business must calculate and account for the VAT as follows:

- Output VAT (VAT Payable) = R10,000 * 15% = R1,500
- Input VAT (VAT Refundable) = R10,000 * 15% = R1,500

The business will then report both the R1,500 as output tax (VAT Payable) and the R1,500 as input tax (VAT Refundable) on their VAT return, resulting in a neutral VAT impact.

To comply with the Imported Services VAT system, businesses in South Africa should ensure that their accounting software supports the Reverse Charge Mechanism and allows for the proper recording and reporting of VAT on imported services. This feature enables businesses to accurately account for the VAT on such transactions and remain compliant with South African VAT regulations.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

---

Value Added Tax (VAT) in South Africa

South Africa currently applies a Value Added Tax (VAT) system. VAT is a consumption tax that is levied on the supply of goods and services within the country.

Here are some key points about VAT in South Africa:

1. VAT Rate: The standard VAT rate in South Africa is 15%. This means that when consumers purchase goods or services, they pay an additional 15% of the purchase price as VAT.
2. Registration Threshold: Businesses that provide taxable goods and services must register for VAT

with the South African Revenue Service (SARS) if their total taxable supplies exceed a certain threshold. As of ChatGPT's last update, the threshold for VAT registration was ZAR 1 million in a 12-month period. This means that businesses whose annual taxable turnover exceeds ZAR 1 million are required to register for VAT.

3. Input Tax Credit: Registered businesses can claim input tax credits for the VAT they have paid on their business expenses. This allows businesses to offset the VAT they pay on purchases against the VAT they collect on sales, resulting in a net VAT liability or refund.

4. VAT Exemptions and Zero-Rating: Some goods and services are exempt from VAT, while others are subject to a 0% VAT rate. Exempt supplies do not attract VAT, and businesses making exempt supplies cannot claim input tax credits. Zero-rated supplies, on the other hand, are still subject to VAT, but at a 0% rate. This means that businesses can claim input tax credits for zero-rated supplies.

5. VAT Returns: Registered businesses are required to submit regular VAT returns to SARS, usually on a bi-monthly basis. The VAT returns detail the VAT collected on sales and the VAT paid on purchases.

It's essential for businesses operating in South Africa to comply with the VAT regulations, including registration, record-keeping, and timely filing of VAT returns. Non-compliance can result in penalties and interest charges.

Please note that tax laws and regulations can change, so it is recommended to check the official website of the South African Revenue Service (SARS) or consulting with a tax professional for the most up-to-date information regarding VAT in South Africa.

What is registration/cancellation of registration for VAT?

Registration for Value Added Tax (VAT): Registration for VAT involves the formal process of registering as a VAT entrepreneur with the South African Revenue Service - Please consult - " *Value Added Tax*" section of the South African Revenue Service (SARS)'s website. There are basically two options to register for VAT:

1. Compulsory Registration: When your business reaches a certain turnover threshold or taxable supplies (which is currently R1 million), you are obliged to register for VAT within 21 working days from the date on which the R1 million is or will be exceeded.

2. Voluntary Registration: A person can also choose to voluntarily register for VAT if the value of taxable supplies made or to be made is less than R1 million, but under certain circumstances has exceeded R50 000 in the past 12-month period. The registration process usually includes providing essential business details, obtaining a unique VAT identification number and understanding the VAT rates and regulations applicable to your industry.

   Registration ensures compliance with VAT laws, enables you to collect tax from customers, and gives you the right to claim input tax credits.

3. Cancellation of registration for Value Added Tax (VAT) : Cancellation of VAT registration may happen in the following circumstances:
    - A VAT-vendor can apply in writing for cancellation of a VAT registration where the value of taxable supplies will be less than the mandatory registration threshold of R1 million in any consecutive 12-month period.
    - The Commissioner can cancel a VAT registration under certain circumstances.

Sets of Books Templates - Simplified Structure of VAT Accounts in the Chart of Accounts and the VAT-Return

osFinancials5/TurboCASH5 supports 79 different languages and tax regimes languages such as 87 Sets of Books (databases) that can be downloaded and customized to meet your requirements.

If you are a new user of osFinancials5/TurboCASH5, you can download the "*EN-SOUTHAFRICA*" Set of Books or of the industry-specific Set of Books (namely, *"FARMING, SERVICE, CHURCH, MEDICAL, MANUFACTURING, RETAIL*" or "*WORKSHOP*") from select the available Firebird database Sets of Books and linked languages available as a free download, the basic Chart of Accounts which already includes basic Output and Input VAT accounts and VAT codes is already pre-configured. There are also Manual Sets of Books namely HANDYMAN, HANDYMAN-A and HANDYMAN-B available for English which illustrate the basic transactions where VAT is involved.

These English-language versions of the Sets of Books, can be downloaded free of charge from the available Firebird database Sets of Books and linked languages that are available. While the Afrikaans-language Set of Books will contain "*Belasting op Toegevoegde Waarde (BTW)*", the English-language Set of Books will contain "*Value Added Tax (VAT)*". osFinancials5/TurboCASH5 has already included for your basic Output VAT and Input VAT account as sub-accounts of the VAT control account as an "*Current liabilities*" in the master "*templates*".

The following basic simplified VAT accounts have already been created for the purposes of this documentation:

Tutorial Sets of Books HANDYMAN, HANDYMAN-A and HANDYMAN-B and *Documentation in in this Help file*			*EN-SOUTH-AFRICA Sets of Books template*		
Account code/ *Tax-code*	*Description*	*Tax-rate*	*Account code/* *Tax-code*	*Account code*	*VAT-Rate*

G850-000	*VAT - Control - 15%*	*Not applicable*	*G950-000*	*VAT CONTROL ACCOUNT - 15%*	*NVT*
T860-010	*Output VAT - 15%*	*15%*	*T950-005*	*Output VAT - 15%*	*15%*
T860-020	*Input VAT - Standard rate -15%*	*15%*	*T950-010*	*Input VAT - Standard rate -15%*	*15%*
T860-030	*Input VAT - Capital goods -15%*	*15%*	*T950-020*	*Input VAT - Capital goods -15%*	*15%*
T860-040	*Zero-rated VAT - 0%*	*0%*	*T950-030*	*Zero-rated VAT - 0%*	*0%*
G850-100	*VAT - Payment - 15%*	*Not applicable*	*G950-100*	*VAT PAYMENT ACCOUNT - 15%*	*NVT*

The Output VAT codes and Input VAT codes were created as sub-accounts under the "*VAT CONTROL ACCOUNT - 15%*" and included in the "*Current liabilities*" account group in the Chart of Accounts in the Set of Books. VAT codes or rather sub-accounts are indicated with a "*T*" prefix on which the applicable VAT code's percentage must be specified whether it is at 15% or 0% percent, for example in the case of zero rate VAT.

Finally, a General Ledger account "*VAT PAYMENT ACCOUNT - 15%*" (indicated with a "*G*" prefix) was also created as a sub-account under the "*VAT CONTROL ACCOUNT - 15%*" (indicated with a "*G*" prefix).

The "*VAT PAYMENT ACCOUNT - 15%*" is the account in which all payments that must be remitted to the South African Revenue Service (SARS) (if the Output VAT is more than the Input VAT) as well as refunds received from the South African Revenue Service (SARS) is received (if the Input VAT is more than the Output VAT), is recorded.

The balances of the "*VAT CONTROL ACCOUNT - 15%*" are as follows:

- A credit balance on the "*VAT CONTROL ACCOUNT - 15%*" means that the Output VAT is more than the Input VAT, which consequently normally shows that VAT is owed to the South African Revenue Service (SARS).
- A debit balance on the "VAT CONTROL ACCOUNT - 15%" means that the Input VAT is more than the Output VAT and that there is VAT from the South African Revenue Service (SARS) recoverable or refundable.

The transactions of the "VAT PAYMENT ACCOUNT - 15%" are as follows:

- Debit transactions - Payments owed to the South African Revenue Service (SARS) are debited against this account when the payment is made from the payment journal linked to the Bank Account. This amount should be indicated on the VAT return (VAT-201), for the period of the VAT return, as the amount you must pay to SARS.
- Credit transactions - Refunds received from the South African Revenue Service (SARS) are credited to this account and credited when the payment is received from the receipt journal linked to the Bank account. This amount should be shown on the VAT return (VAT-201), for the period of the VAT return, as owed to you by SARS.

In addition to these basic Tax codes or Tax accounts, within the "*VAT CONTROL ACCOUNT - 15%*" main account, you can create further sub-accounts to accommodate the respective classifications and/or tax percentages in respect of Output VAT and Input VAT to help you complete the VAT returns and make the correct payments to the tax authority.

Full Structure of VAT Accounts in the Chart of Accounts and the VAT-Return

In the Chart of Accounts, Value Added Tax (VAT) payable is typically included in the "*Current liabilities*" section of the Balance sheet. This account represents the VAT that the business has collected on sales but has not yet remitted to the tax authorities.

To simplify matters, in this example, the Output VAT and Input VAT, the sub-accounts or tax codes are organized in a way that matches the VAT codes and account numbers with the corresponding sections of the VAT201 return.

To ensure proper accounting and alignment with the VAT return, it's important to structure VAT sub-accounts (VAT codes) for the various rates that apply, within the VAT Control account. The VAT Control account, G2400-000, reflects the net balance due to SARS. A credit balance implies that the VAT is payable to SARS.

The breakdown of the VAT payable account includes the following sub-accounts (T-codes) (T is the prefix for Tax account type) to provide more detailed information about different types of VAT:

Output VAT (supplied by you):

1. T2400-010 - Output VAT- Standard rate - 15% (VAT on Sales): Field 1 on the VAT return. Standard rate (excluding capital goods and/or services and accommodation). This sub-account records the VAT that the business has charged on its sales transactions. It represents the VAT collected from customers.
2. T2400-015 - Output VAT- Capital goods - 15% (VAT on Sales): Field 1A on the VAT return. Standard

rate (only capital goods and/or services). This sub-account records the VAT that the business has charged on its sales transactions only for capital goods and/or services supplied by you at the standard rate, . This field must reflect the consideration received in respect of:

- Sale of capital goods and/or services (e.g. Sale of land and buildings, plant and machinery, intellectual property).
- VAT on assets upon termination of registration.

3. T2400-020 - Output VAT- Zero rate - 0% (VAT on Sales): Field 2 on the VAT return. Zero rate (excluding goods exported). - This sub-account is used to record sales that are subject to a 0% VAT rate. Even though no VAT is charged on these sales, they still need to be accounted for separately.
4. T2400-025 - Output VAT- Zero rate - 0% - Exported goods (VAT on Sales): Field 2A on the VAT return. - Zero rate (only exported goods). Zero Rated VAT (Sales with 0% VAT): This sub-account is used to record sales only exported goods that are subject to a 0% VAT rate. Even though no VAT is charged on these sales, they still need to be accounted for separately.
5. T2400-030 - VAT- Exempt and Non supplies - 0% (VAT on Sales): Field 3 on the VAT return. - Exempt and non-supplies The amount of exempt supplies or non-supplies supplied by you must be completed in Field 3. This sub-account is used to record sales of exempt supplies or non-supplies.
   - Exempt supplies are transactions on which no output tax is levied, and no input tax relating to the expenditure on these supplies may be deducted.
   - Examples of exempt supplies include financial services, donated goods or services by an association not for gain, residential accommodation, the letting of leasehold land, and other specified items.

   In a tax code or VAT sub-account, the tax rate for exempt supplies and non-supplies should be set at 0%. This indicates that although these supplies are subject to VAT reporting, they are taxed at a 0% rate, meaning that no actual VAT amount is charged to the customer on these transactions.

   By using a 0% tax rate for exempt supplies and non-supplies, businesses can distinguish them from standard-rated supplies (which have a positive VAT rate) and zero-rated supplies (which have a 0% VAT rate but still allow for VAT recovery on input purchases). This differentiation is crucial for accurate VAT reporting, as well as for proper treatment of input VAT claims related to taxable supplies.

   Remember that even though no VAT is charged on exempt supplies and non-supplies, they still need to be accounted for separately in the VAT return. Additionally, businesses should ensure that they don't claim any input VAT deductions related to these supplies, as no VAT is recoverable on them.
6. T2400-050 - Accommodation (VAT on Sales): Field 5 on the VAT return. Supply of accommodation. Commercial accommodation provided for a full period of more than 28 days. The VAT exclusive

amount of accommodation supplied not exceeding 28 days must be completed in Field 7. The total value (VAT excluded) in respect of accommodation supplied for a period equal to or less than 28 days (full period) must be reported in Field 7. This sub-account is used to record the supply of commercial accommodation provided for a full period of more than 28 days.

Please note that the VAT treatment of commercial accommodation services can be intricate, and it's crucial for businesses to correctly record and report these transactions to comply with VAT regulations.

7. T2400-100 - VAT- Adjustments - Change in use and export of second-hand goods: Field 10 on the VAT return. Change in use and export of second-hand goods.
8. T2400-120 - VAT- Adjustments - Field 12 on the VAT return. – Other and imported services

Input VAT (supplied to you): This sub-account records the VAT that the business has paid on its purchases of goods and services. It represents the VAT that the business can potentially recover or offset against the output VAT.

9. T2400-140 - Input VAT- Capital goods - 15%: Field 14 on the VAT return. Capital goods and/or services supplied to you
10. T2400-145 - Input VAT- Capital goods - Imported - 15% Field 14A on the VAT return. Capital goods imported by you. This sub-account records the VAT that the business has paid on its purchases of capital goods. It represents the VAT that the business can potentially recover or offset against the Output VAT.
11. T2400-150 - Input VAT - Standard rate - 15% (VAT on Purchases) Field 15 on the VAT return. Other goods and/or services supplied to you (not capital goods). This sub-account records the VAT that the business has paid on its purchases of goods and services. It represents the VAT that the business can potentially recover or offset against the output VAT.
12. T2400-155 - Input VAT - Standard rate - Imported (VAT on Purchases): Field 15A on the VAT return. Other goods imported by you (not capital goods)
13. T2400-160 - VAT - Adjustments - Change in use - Imported (VAT on Purchases): Field 16 on the VAT return. Change in use The VAT amount in respect of the change in use must be completed in Field 16. Only the VAT amount in respect of:
    - Goods and services previously applied for non-taxable purposes and now wholly or partially applied for taxable purposes.
    - An increase in the extent of application of use of goods and / or services for taxable purposes.
14. T2400-170 - VAT Adjustments Bad Debts (Uncollectible VAT on Sales): Field 17 on the VAT return.

This sub-account is used to record the VAT that becomes uncollectible due to bad debts. When a customer does not pay their invoice, the VAT that was previously charged on the sale may need to be reversed or adjusted to reflect the uncollectible status. NOTE: "The VAT amount in respect of bad debts must be completed in Field 17. Fill in only the VAT amount in respect of irrecoverable debts on which VAT was levied during the sale. Only applies if registered under the invoice basis of VAT" according to SARS.

15. T2400-180 - VAT Adjustments - Other. Field 18 on the VAT return - This sub-account is used to record various VAT adjustments on credit notes, debit notes, and changes in accounting basis.
    - The VAT amount in respect of credit notes issued by the business should be reported in Field 18 on the VAT return. Credit notes are issued when a supplier refunds money to a customer or reduces the value of a previous sale, and the VAT amount associated with the credit note needs to be adjusted on the VAT return.
    - The VAT amount in respect of debit notes received by the business should also be reported in Field 18 on the VAT return. Debit notes are received from suppliers when they reduce the value of a previous purchase, and the VAT amount associated with the debit note requires adjustment on the VAT return.
    - Additionally, this sub-account includes any other VAT adjustments related to a change in accounting basis that may impact the VAT calculations and reporting. These adjustments may arise due to changes in the business's VAT accounting methods or other relevant factors that affect the VAT amount.

    Properly accounting for credit notes, debit notes, and changes in accounting basis is crucial to ensure accurate VAT reporting. By using this sub-account and corresponding Field 18 on the VAT return, businesses can accurately reflect any necessary adjustments to the VAT amounts associated with these transactions. As always, it's essential to adhere to the tax regulations and guidelines of the relevant jurisdiction to maintain compliance with VAT reporting requirements.

Totals on the VAT201 return:

- TOTAL A - Field 13 - Total Output Tax: Total Output Tax must be equal to the sum of Fields (4+4A+9+11+12). This amount is automatically calculated on the VAT201 Declaration.
- TOTAL B - Field 19 - Total Input Tax: Total Input Tax must be equal to the sum of Fields (14+14A+15+15A+16+17+18). This amount is automatically calculated on the VAT201 Declaration.
- Field 20 – VAT Payable /Refundable (Total A - Total B) must be equal to the difference between Fields 13 and 19. This amount is automatically calculated on the VAT201 Declaration. If the difference between Field 13 and 19 is less than zero, then the minus (-) sign must be added in the first block before the amount entered in the field. The minus sign (-) will indicate that a refund is due. If Field 20

has no minus sign (-) before the amount, then the amount indicates that payment is due.

Diesel refunds

In the Sample Chart of Accounts in this documentation, (Sets of Books templates) only includes the following on the VAT201 return:

- *Output VAT accounts and Tax codes for Total A - Output Tax of field 13 Field - This amount is automatically calculated on the VAT201 Declaration. based on the declarations submitted in Fields 4+4A+9+11+12.*
- *Input VAT accounts and Tax codes for Total B - Input Tax of field 20 Field - This amount is automatically calculated on the VAT201 Declaration. based on the declarations submitted in Fields 14+14A+15+15A+16+17+18.*

On the VAT201 return Fields 21 to Field 38 "CALCULATION OF DIESEL REFUND IN TERMS OF THE CUSTOMS AND EXCISE ACT" is excluded form the Sample Chart of Accounts in this documentation (Sets of Books templates) on the VAT201 return

If Diesel refunds is applicable to your business or industry, you need to create additional accounts for the relevant sections or categories (i.e. "Land," "Offshore," "Rail & Harbour services," and "Peak Power Plant") to assist you to complete the correct details on the Diesel refunds section of the VAT-return.

It is once again important when dealing with complex tax matters like VAT refunds and specific sections of tax returns, it's wise to rely on the expertise of professionals who are well-versed in tax regulations and can provide tailored guidance for your unique business circumstances.

Additionally, there is the VAT Payment Account, G2400-200, which is used to record payments in cases where the Output VAT exceeds the Input tax. This represents the VAT payable as submitted on the VAT return, and any payments to SARS would be recorded to this account.

Conversely, if the Input VAT exceeds the Output VAT, resulting in a tax refund due from SARS, the refund received would be recorded to the VAT Payment Account, G2400-200.

In addition to this example and text, it is important to note that this is a basic structure of the VAT Accounts. Depending on the complexities for the nature of your business, such as exporting of taxable supplies, importing of taxable supplies, second-hand goods, accommodation, adjustments, etc., you may need to add additional tax codes applicable to your business.

This well-organized structure ensures that VAT liabilities are accurately accounted for and helps businesses in complying with tax regulations while maintaining clear records for reporting and analysis.

Overall, the explanation provides a comprehensive understanding of how VAT is accounted for in the Chart of Accounts for South Africa, and the breakdown of sub-accounts offers valuable insights into the different

components of VAT transactions.

It's important for businesses to maintain accurate records and ensure that VAT liabilities are correctly calculated and reported in compliance with the tax regulations in South Africa. As always, consulting with accounting professionals or tax experts can provide further guidance and ensure proper adherence to the tax laws and regulations related to VAT.

Is there any VAT Schemes in South Africa?

As of ChatGPT's last update in September 2021, South Africa does not have specific VAT schemes like some other countries have, such as the UK's Flat Rate Scheme or Australia's Cash Accounting Scheme. In South Africa, the Value Added Tax (VAT) system follows a standard method, and all VAT-registered businesses charge VAT on their taxable supplies and claim input tax credits on their eligible business purchases.

The standard VAT rate in South Africa is a flat rate that applies to most goods and services. There are certain supplies that may be exempt from VAT, such as certain financial services, residential property rentals, and some basic food items. Additionally, there are specific zero-rated supplies that are subject to a 0% VAT rate, such as certain basic food items, export of goods, and certain services provided to non-residents.

Businesses in South Africa are required to register for VAT if their annual taxable turnover exceeds the threshold set by the South African Revenue Service (SARS). Once registered, businesses charge VAT on their taxable supplies, keep appropriate records, and submit regular VAT returns to SARS.

It's essential for businesses to accurately account for VAT in their Chart of Accounts, ensuring that VAT collected from customers is correctly recorded under Output VAT and that VAT paid on purchases is correctly recorded under Input VAT.

Please note that tax laws and regulations are subject to change, so it's always best to consult with a tax professional or visit the South African Revenue Service (SARS) website for the most up-to-date information regarding VAT in South Africa.

VAT on Bad debts?

VAT on bad debts refers to the treatment of Value Added Tax (VAT) when a business is unable to recover the VAT it has previously charged on sales to customers who subsequently fail to pay their debts, resulting in the debts becoming "bad" or uncollectible. In many tax systems, including the VAT system in various countries, there are specific provisions that address the treatment of bad debts for VAT purposes.

The treatment of VAT on bad debts can vary depending on the specific rules of each country's VAT system, but some common approaches include:

1. Bad Debt Relief: Many VAT systems allow businesses to claim a deduction or refund for the VAT previously charged and remitted to the tax authorities on sales that have turned into bad debts. This is often referred to as "*bad debt relief*" or "*VAT bad debt relief*." The relief essentially reduces the VAT liability of the business, helping to avoid double taxation on the unpaid amounts.
2. Conditions for Bad Debt Relief: The conditions for claiming bad debt relief may vary by country, but they generally include requirements such as:
    - The debt must have been written off as uncollectible by the business.
    - The debt must be overdue for a specific period (e.g., six months) from the due date of payment.
    - The business must have taken reasonable steps to recover the debt.
    - The VAT on the bad debt must have been previously accounted for and paid to the tax authorities.
3. Adjustment Period: Some countries have specific rules regarding the timing of bad debt relief. There may be a waiting period after which a business can claim the relief, ensuring that the debt is genuinely uncollectible before the VAT is adjusted.
4. Partial Bad Debts: In certain cases, where only a portion of the debt is deemed uncollectible, businesses may be able to claim relief only for the VAT applicable to the uncollectible portion.

It's important to note that the rules and procedures for VAT on bad debts can be complex and may vary from country to country. Businesses should follow the specific guidelines provided by their country's tax authority and maintain proper records and documentation to support any claims for bad debt relief.

As tax laws are subject to change, businesses should consult with tax professionals or tax authorities in their jurisdiction for the most up-to-date and accurate information on VAT treatment of bad debts.

Special Notes: Import of General Ledger Accounts and VAT Accounts

When you import a Chart of Accounts into your own or new Set of Books, it is important to pay particular attention to the following:

1. Text file - Import - General ledger accounts - The following require special attention:
    - First sub-account - The Tax tab on the first VAT code (e.g. Output VAT - 15% (T850010) is missing after import. You will need to delete the first VAT sub-account and recreate it as a VAT account type and the VAT percentage must be entered.

- Zero rate - VAT codes - Zero rate VAT with a VAT percentage of "*0%*" can be blank. You will need to reconfirm the "*0%*" as the VAT percentage.
- Inactive VAT Codes - The inactive VAT codes in your source Import text file may be imported as "*Active*". If there are any VAT accounts or VAT codes that you do not use, you can their status as "Inactive" or delete them.

2. Spreadsheet - Import - General ledger accounts - When you import accounts from the spreadsheet option, all sub-accounts can be imported as main accounts. You will need to delete the VAT codes (as main accounts) and recreate your VAT sub-accounts or VAT codes and key in the correct VAT percentages on the VAT tab. Above and beyond the VAT related accounts, will you must also check the other accounts in your ledger that contain sub-accounts and perform the necessary actions.

You can print a "Tax codes - Tax rates" report on the User Reports → Tax menu on the Reports ribbon to print a list of VAT codes and their respective percentages. The status of whether the VAT code is "Active" or "Inactive" will also be indicated on this report. Tax percentages with a zero-rate will be Imported as a blank percentage.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Goods and Services Tax (GST) - Australia

Goods and Services Tax (GST) in Australia

As of ChatGPT's last update in September 2021, Australia applies a Goods and Services Tax (GST) instead of Value Added Tax (VAT). The GST is a broad-based consumption tax levied on the supply of most goods, services, and other items in Australia.

Here are some key points about the GST in Australia:

1. GST Rate: The standard GST rate in Australia is 10%. This means that when consumers purchase most goods and services, they pay an additional 10% of the purchase price as GST.
2. Taxable Supplies: The GST applies to most goods and services provided by businesses, including sales of goods, services, imports, and certain intangible supplies. However, some supplies may be GST-free or input-taxed, meaning GST is not charged on them or the GST paid on related expenses cannot be claimed as an input tax credit.
3. GST Registration: Businesses with an annual turnover of AUD 75,000 or more (AUD 150,000 or more

for non-profit organizations) are required to register for GST with the Australian Taxation Office (ATO). Once registered, businesses must charge GST on their taxable supplies and can claim input tax credits for the GST paid on their business expenses.

4. Business Activity Statement (BAS): Registered businesses must lodge regular Business Activity Statements with the ATO, typically on a monthly or quarterly basis, to report their GST transactions. The BAS includes information on GST collected (output tax) and GST paid on expenses (input tax), and the net amount is remitted to the ATO.

5. Input Tax Credits: Registered businesses can claim input tax credits for the GST they have paid on their business expenses. This allows businesses to offset the GST they pay on purchases against the GST they collect on sales, resulting in a net GST liability or refund.

6. GST Exemptions: Some goods and services are exempt from GST, meaning they are not subject to the tax. Common exemptions include basic food items, some medical and health services, and certain educational services.

7. GST on Imported Goods: As of July 1, 2018, Australia introduced the "*GST on Low-Value Imported Goods*" (also known as "low-value imported goods GST"), which applies GST to certain low-value goods imported by consumers into Australia.

It's essential for businesses operating in Australia to understand and comply with the GST regulations, including registration, reporting, and remittance requirements. As tax laws can change, businesses should consult with the Australian Taxation Office or tax professionals for the most up-to-date information regarding the GST in Australia.

Is there any GST Schemes in Australia?

Yes, there are several Goods and Services Tax (GST) schemes in Australia. These schemes are designed to simplify GST reporting for specific types of businesses and transactions. The main GST schemes in Australia include:

1. Standard GST Scheme: This is the standard GST scheme that applies to most businesses in Australia. Under this scheme, businesses charge GST on their taxable sales (output GST) and claim GST credits for the GST included in the price of goods and services they acquire for their business (input GST). GST returns are usually filed on a regular basis, either monthly, quarterly, or annually, depending on the business's turnover.

2. Cash Accounting Scheme: Businesses with an annual turnover of less than AUD $10 million can choose to use the cash accounting scheme. Under this scheme, businesses account for GST when they receive payment for their sales or when they make payments for their purchases. This can help with cash flow management for small businesses.

3. Accruals Accounting Scheme: This is the default scheme for businesses with an annual turnover of AUD $10 million or more. Under this scheme, GST is accounted for when an invoice is issued or received, regardless of whether payment has been made. Most larger businesses in Australia use this scheme.
4. Simplified GST Accounting Methods: There are several simplified accounting methods available for specific types of businesses, such as the cash basis, annual apportionment, and the 1/11th basis. These methods simplify the calculation and reporting of GST for certain business activities.
5. Margin Scheme: The margin scheme is applicable to certain transactions involving real property (e.g., property development or sales). Under this scheme, GST is calculated based on the margin (the difference between the selling price and the purchase price) rather than the full selling price.
6. Tourist Refund Scheme (TRS): The TRS allows overseas visitors to claim a refund of the GST paid on goods purchased in Australia, subject to certain conditions.

It's important for businesses to select the most appropriate GST scheme based on their turnover, the nature of their transactions, and their reporting preferences. Businesses are advised to seek guidance from accounting professionals or tax advisors to determine the best GST scheme for their specific circumstances.

Structure of GST Accounts in the Chart of Accounts for the Australia

In the Chart of Accounts for businesses in Australia, Goods and Services Tax (GST) accounts are structured to accurately record and report GST-related transactions.

Standard GST Scheme

The structure of GST accounts for the Standard GST Scheme may vary depending on the size and complexity of the business, but here is a common framework:

1. GST Control Account (Current Liabilities):
    - 2000 - GST Control: This is the main GST Control account that tracks the GST amounts payable or refundable to the Australian Taxation Office (ATO). It represents the net balance due to or from the ATO. A credit balance implies that the GST is recoverable from the ATO, while a debit balance indicates GST is payable to the ATO.
2. GST on Sales (Output Tax):
    - 2001 - GST on Sales: This account records the GST charged on sales made by the business. It represents the GST collected from customers and is payable to the ATO.

3. GST on Purchases (Input Tax Credit):
    - 2002 - GST on Purchases: This account records the GST paid on purchases made by the business. It represents the GST that can be claimed as input tax credits (ITC) from the ATO.
4. GST on Imports:
    - 2003 - GST on Imports: This account records the GST paid on goods imported into Australia from overseas. The GST on imports is usually paid directly to the Australian Customs and Border Protection Service (ACBPS).
5. GST Adjustments:
    - 2004 - GST Adjustments: This account is used to record any adjustments or corrections to previously reported GST amounts, such as bad debts, errors, or changes in taxable supplies.
6. GST on Acquisitions from Overseas Suppliers:
    - 2005 - GST on Acquisitions: This account records the GST on goods and services acquired from overseas suppliers. The GST on acquisitions is self-assessed by the business and included in the GST return.
7. GST on Capital Assets:
    - 2006 - GST on Capital Assets: This account is used to record GST on the acquisition of capital assets, such as machinery, equipment, or property.
8. GST on Disposals of Capital Assets:
    - 2007 - GST on Disposals: This account records GST on the disposal of capital assets.
9. GST Bad Debt Relief:
    - 2008 - GST Bad Debt Relief: This account records the GST amounts that are claimed as bad debt relief when customers fail to pay their invoices.

It's important to note that the above structure is a general framework, and businesses may have additional sub-accounts or variations based on their specific needs and the complexity of their GST transactions. Properly organizing and maintaining GST accounts in the Chart of Accounts ensures accurate GST reporting and compliance with ATO regulations in Australia. Businesses are encouraged to consult with accounting professionals or tax advisors to set up their Chart of Accounts effectively and ensure compliance with GST requirements.

Cash Accounting Scheme

In Australia, the Cash Accounting Scheme for Goods and Services Tax (GST) allows eligible businesses to

account for GST on a cash basis, which means GST is accounted for and paid only when the business receives payment from customers. Here is a common structure of VAT accounts in the Chart of Accounts for businesses in Australia that use the Cash Accounting Scheme:

1. GST Collected (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record the GST collected from customers. It represents the GST amount that the business has charged on sales but has not yet remitted to the Australian Taxation Office (ATO). The balance of this account reflects the net GST payable to the ATO.
2. GST Paid (Current Asset):
    - Account Code: 1XXX
    - Description: This account is used to record the GST paid on purchases made by the business. It represents the GST that the business can claim as input tax credits. The balance of this account reflects the net GST refundable from the ATO.
3. GST Adjustment:
    - Account Code: 3XXX
    - Description: This account is used to record any adjustments or corrections to previously reported GST amounts. It may include adjustments for bad debts, errors, or changes in the business's GST status.
4. GST Refund Due:
    - Account Code: 1XXX.X
    - Description: This sub-account is used to track any GST refund due to the business. It reflects the amount of GST that the business has paid on purchases and is eligible for a refund from the ATO.
5. GST Payable:
    - Account Code: 2XXX.X
    - Description: This sub-account is used to track any GST payable by the business. It reflects the amount of GST that the business has collected from customers and needs to remit to the ATO.
6. GST Paid on Imports:

- Account Code: 1XXX.XX
- Description: This sub-account is used to record the GST paid on imports of goods into Australia. It represents the GST that the business needs to remit to the ATO on imported goods.

7. GST Adjustments - Imports:
   - Account Code: 3XXX.XX
   - Description: This sub-account is used to record any adjustments or corrections related to GST on imports.
8. GST Suspense:
   - Account Code: 4XXX
   - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of VAT accounts may vary depending on the specific needs and preferences of the business. Businesses using the Cash Accounting Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with Australian tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Cash Accounting Scheme for GST.

Accruals Accounting Scheme

In Australia, the Accruals Accounting Scheme for Goods and Services Tax (GST) is the standard method of accounting for GST. Under this scheme, businesses account for GST based on the date of invoice issuance or receipt, regardless of when the payment is made. Here is a common structure of VAT accounts in the Chart of Accounts for businesses in Australia that use the Accruals Accounting Scheme:

1. GST Collected (Current Liability):
   - Account Code: 2XXX
   - Description: This account is used to record the GST collected from customers. It represents the GST amount that the business has charged on sales and needs to remit to the Australian Taxation Office (ATO). The balance of this account reflects the net GST payable to the ATO.
2. GST Paid (Current Asset):

- Account Code: 1XXX
- Description: This account is used to record the GST paid on purchases made by the business. It represents the GST that the business can claim as input tax credits. The balance of this account reflects the net GST refundable from the ATO.

3. GST Adjustment:
   - Account Code: 3XXX
   - Description: This account is used to record any adjustments or corrections to previously reported GST amounts. It may include adjustments for bad debts, errors, or changes in the business's GST status.
4. GST Refund Due:
   - Account Code: 1XXX.X
   - Description: This sub-account is used to track any GST refund due to the business. It reflects the amount of GST that the business has paid on purchases and is eligible for a refund from the ATO.
5. GST Payable:
   - Account Code: 2XXX.X
   - Description: This sub-account is used to track any GST payable by the business. It reflects the amount of GST that the business has collected from customers and needs to remit to the ATO.
6. GST Paid on Imports:
   - Account Code: 1XXX.XX
   - Description: This sub-account is used to record the GST paid on imports of goods into Australia. It represents the GST that the business needs to remit to the ATO on imported goods.
7. GST Adjustments - Imports:
   - Account Code: 3XXX.XX
   - Description: This sub-account is used to record any adjustments or corrections related to GST on imports.
8. GST Suspense:

- Account Code: 4XXX
- Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of VAT accounts may vary depending on the specific needs and preferences of the business. Businesses using the Accruals Accounting Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with Australian tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Accruals Accounting Scheme for GST.

Simplified GST Accounting Methods

In Australia, businesses that have an annual turnover of less than AUD $10 million may be eligible to use the Simplified GST Accounting Methods. These methods simplify the way GST is accounted for, making it easier for smaller businesses to manage their GST obligations. Here is a common structure of GST accounts in the Chart of Accounts for businesses in Australia that use the Simplified GST Accounting Methods:

1. GST Collected (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record the GST collected from customers. It represents the GST amount that the business has charged on sales and needs to remit to the Australian Taxation Office (ATO). The balance of this account reflects the net GST payable to the ATO.
2. GST Paid (Current Asset):
    - Account Code: 1XXX
    - Description: This account is used to record the GST paid on purchases made by the business. It represents the GST that the business can claim as input tax credits. The balance of this account reflects the net GST refundable from the ATO.
3. GST Adjustment:
    - Account Code: 3XXX
    - Description: This account is used to record any adjustments or corrections to previously reported GST amounts. It may include adjustments for bad debts, errors, or changes in the business's GST status.

4. GST Refund Due:
    - Account Code: 1XXX.X
    - Description: This sub-account is used to track any GST refund due to the business. It reflects the amount of GST that the business has paid on purchases and is eligible for a refund from the ATO.
5. GST Payable:
    - Account Code: 2XXX.X
    - Description: This sub-account is used to track any GST payable by the business. It reflects the amount of GST that the business has collected from customers and needs to remit to the ATO.
6. GST Paid on Imports:
    - Account Code: 1XXX.XX
    - Description: This sub-account is used to record the GST paid on imports of goods into Australia. It represents the GST that the business needs to remit to the ATO on imported goods.
7. GST Adjustments - Imports:
    - Account Code: 3XXX.XX
    - Description: This sub-account is used to record any adjustments or corrections related to GST on imports.
8. GST Suspense:
    - Account Code: 4XXX
    - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of GST accounts may vary depending on the specific needs and preferences of the business. Businesses using the Simplified GST Accounting Methods should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with Australian tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Simplified GST Accounting Methods.

Margin Scheme

In Australia, the Margin Scheme is a special method of calculating Goods and Services Tax (GST) on the sale of certain types of property, such as second-hand goods, real property, or other specified items. When using the Margin Scheme, GST is calculated based on the difference between the selling price and the original purchase price, rather than the full selling price. Here is a common structure of GST accounts in the Chart of Accounts for businesses in Australia that use the Margin Scheme:

1. Margin Scheme Sales (Current Revenue):
    - Account Code: 4XXX
    - Description: This account is used to record the sales made under the Margin Scheme. It represents the revenue generated from the sale of items eligible for the Margin Scheme.
2. Margin Scheme GST Payable (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record the GST payable on Margin Scheme sales. It represents the GST amount that the business needs to remit to the Australian Taxation Office (ATO) based on the margin between the selling price and the original purchase price.
3. Margin Scheme GST Adjustment:
    - Account Code: 3XXX
    - Description: This account is used to record any adjustments or corrections related to the Margin Scheme GST. It may include adjustments for errors or changes in the business's Margin Scheme calculations.
4. Margin Scheme GST Refund Due (Current Asset):
    - Account Code: 1XXX.X
    - Description: This sub-account is used to track any GST refund due to the business under the Margin Scheme. It reflects the amount of GST that the business has paid on eligible purchases and is eligible for a refund from the ATO.
5. Margin Scheme GST Payable (Current Liability):
    - Account Code: 2XXX.X
    - Description: This sub-account is used to track any GST payable by the business on Margin Scheme sales. It reflects the amount of GST that the business needs to remit to the ATO based on the margin.

6. Margin Scheme GST Suspense:
    - Account Code: 5XXX
    - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts under the Margin Scheme.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of GST accounts may vary depending on the specific needs and preferences of the business. Businesses using the Margin Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with Australian tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Margin Scheme for GST.

Tourist Refund Scheme (TRS)

The Tourist Refund Scheme (TRS) allows eligible tourists to claim a refund of the Goods and Services Tax (GST) and Wine Equalisation Tax (WET) paid on certain goods purchased in Australia. Businesses that sell goods to tourists eligible for the TRS may need to account for the GST and WET on these sales differently in their Chart of Accounts. Here is a common structure of GST accounts in the Chart of Accounts for businesses in Australia that deal with the Tourist Refund Scheme:

1. TRS Sales (Current Revenue):
    - Account Code: 4XXX
    - Description: This account is used to record the sales made to tourists eligible for the TRS. It represents the revenue generated from the sales of goods that qualify for the TRS.
2. TRS GST Payable (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record the GST payable on TRS sales. It represents the GST amount that the business needs to remit to the Australian Taxation Office (ATO) based on the sales to TRS-eligible tourists.
3. TRS WET Payable (Current Liability):
    - Account Code: 2XXX.X
    - Description: This sub-account is used to track the WET payable on sales of wine to TRS-eligible tourists. It represents the WET amount that the business needs to remit to the ATO.
4. TRS GST Adjustment:

- Account Code: 3XXX
- Description: This account is used to record any adjustments or corrections related to the GST on TRS sales. It may include adjustments for errors or changes in the business's TRS calculations.

5. TRS GST Refund Due (Current Asset):
   - Account Code: 1XXX.X
   - Description: This sub-account is used to track any GST refund due to the business from the ATO for TRS sales. It reflects the amount of GST that the business has paid on eligible purchases related to TRS sales and is eligible for a refund from the ATO.
6. TRS GST Payable (Current Liability):
   - Account Code: 2XXX.X
   - Description: This sub-account is used to track any GST payable by the business on TRS sales. It reflects the amount of GST that the business needs to remit to the ATO based on the sales to TRS-eligible tourists.
7. TRS GST Suspense:
   - Account Code: 5XXX
   - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts related to TRS sales.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of GST accounts may vary depending on the specific needs and preferences of the business. Businesses that participate in the Tourist Refund Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST and WET transactions in compliance with Australian tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of dealing with the Tourist Refund Scheme.

GST Return in Australia

What blocks or fields appears on the GST return in Australia?

As of ChatGPT's last update in September 2021, the Goods and Services Tax (GST) return in Australia includes the following blocks or fields:

1. Business and Contact Information: This section requires the business's name, ABN (Australian

Business Number), GST registration status, and contact details.

2. GST Turnover: The total value of sales, other supplies, and taxable importations for the tax period. This is used to determine the applicable GST rate.
3. GST on Sales: This section includes the GST amount collected on sales and other supplies made during the tax period.
4. GST on Purchases: This field includes the GST amount paid on purchases and other expenses during the tax period.
5. Capital Purchases: Any capital purchases made during the tax period that are eligible for GST credit.
6. Non-capital Purchases: This section includes non-capital purchases on which you can claim a GST credit.
7. Export Sales: The value of GST-free sales or other supplies made for export purposes.
8. Other GST-Free Sales: The value of other GST-free sales or supplies made during the tax period.
9. Input Taxed Sales: The value of sales or supplies that are input taxed (not subject to GST).
10. Total GST Payable: This is the net GST amount calculated as GST on Sales minus GST on Purchases, considering any adjustments.
11. Luxury Car Tax (LCT): If applicable, the LCT payable on luxury cars.
12. Wine Equalisation Tax (WET): If applicable, the WET payable on wine sales.
13. Fuel Tax Credits: If eligible, this section includes the credits for fuel tax that can be claimed.
14. Other Taxes: Any other taxes or adjustments that need to be reported.
15. Total Amount Payable or Refundable: The final amount to be paid to the ATO (Australian Taxation Office) or refunded, considering all GST amounts and credits.

Please note that tax regulations may change over time, so it's essential to refer to the latest guidelines and forms provided by the Australian Taxation Office (ATO) for the most up-to-date information. If you are preparing a GST return, it's always a good idea to seek professional advice or use official resources to ensure compliance with current tax laws.

Full Reporting - GST Returns

The GST return full reporting requirements for businesses in Australia with a GST turnover of $10 million or more, reporting and paying GST quarterly. Below are the specific fields (labels) that need to be reported on the activity statement each quarter:

- G1: Total sales - The total value of all sales made during the tax quarter.

- G2: Export sales - The value of GST-free sales or other supplies made for export purposes.
- G3: Other GST-free sales - The value of other GST-free sales or supplies made during the tax quarter.
- G10: Capital purchases - The total value of capital purchases made during the tax quarter that are eligible for GST credit.
- G11: Non-capital purchases - The total value of non-capital purchases on which you can claim a GST credit during the tax quarter.
- 1A: GST on sales - The total amount of GST collected on sales and other supplies made during the tax quarter.
- 1B: GST on purchases - The total amount of GST paid on purchases and other expenses during the tax quarter.

Additionally, if the business has obligations or entitlements related to Wine Equalisation Tax (WET), Luxury Car Tax (LCT), or Fuel Tax Credits (FTC), the following labels must also be reported each quarter:

- 1C: Wine Equalisation Tax (WET) - If applicable, the WET payable on wine sales.
- 1D: Luxury Car Tax (LCT) - If applicable, the LCT payable on luxury cars.
- 1E: Fuel Tax Credits (FTC) - If eligible, this label includes the credits for fuel tax that can be claimed.
- 1F: FTC adjustments - Any adjustments to Fuel Tax Credits.
- 7C: WET payable - If applicable, the WET payable for the tax quarter.
- 7D: LCT payable - If applicable, the LCT payable for the tax quarter.

It's important for businesses to accurately report and calculate their GST and related taxes on their activity statements to comply with Australian tax regulations. For specific details and instructions on reporting methods, businesses should refer to official resources provided by the Australian Taxation Office (ATO) or consult with a qualified tax professional.

Simpler BAS reporting method GST Returns

Under the Simpler BAS reporting method in Australia, businesses with a GST turnover of less than $10 million are required to report less information on their quarterly Business Activity Statement (BAS) but still calculate and pay their GST amounts quarterly. The reporting requirements for the Simpler BAS are as follows:

- G1: Total sales - The total value of all sales made during the tax quarter.
- 1A: GST on sales - The total amount of GST collected on sales and other supplies made during the tax

quarter.

- 1B: GST on purchases - The total amount of GST paid on purchases and other expenses during the tax quarter.

The following information does not need to be reported under the Simpler BAS method:

- G2: Export sales - The value of GST-free sales or other supplies made for export purposes.
- G3: Other GST-free sales - The value of other GST-free sales or supplies made during the tax quarter.
- G10: Capital purchases - The total value of capital purchases made during the tax quarter that are eligible for GST credit.
- G11: Non-capital purchases - The total value of non-capital purchases on which you can claim a GST credit during the tax quarter.

If a business has obligations or entitlements related to Wine Equalisation Tax (WET), Luxury Car Tax (LCT), or Fuel Tax Credits (FTC), the following labels must also be reported each quarter:

- 1C: Wine Equalisation Tax (WET) - If applicable, the WET payable on wine sales.
- 1D: Luxury Car Tax (LCT) - If applicable, the LCT payable on luxury cars.
- 1E: Fuel Tax Credits (FTC) - If eligible, this label includes the credits for fuel tax that can be claimed.
- 1F: FTC adjustments - Any adjustments to Fuel Tax Credits.
- 7C: WET payable - If applicable, the WET payable for the tax quarter.
- 7D: LCT payable - If applicable, the LCT payable for the tax quarter.

For businesses that qualify for the GST instalments method, they can choose to pay quarterly GST instalments that are calculated by the Australian Taxation Office (ATO) and report their actual GST information annually on an annual GST return. This method is available to businesses with an aggregated turnover of less than $10 million or non-business entities with a GST turnover of $2 million or less.

As tax regulations can change, it's essential to refer to the latest guidelines and resources provided by the ATO for the most up-to-date information and compliance. Businesses are encouraged to seek professional advice or use official resources to ensure accurate reporting and compliance with current tax laws.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Goods and Services Tax (GST) - New Zealand

Goods and Services Tax (GST) in New Zealand

As of ChatGPT's last update in September 2021, New Zealand applies a Goods and Services Tax (GST). The GST is a broad-based consumption tax levied on the supply of most goods, services, and other items in New Zealand.

Here are some key points about the GST in New Zealand:

1. GST Rate: The standard GST rate in New Zealand is 15%. This means that when consumers purchase most goods and services, they pay an additional 15% of the purchase price as GST.
2. Taxable Supplies: The GST applies to most goods and services supplied by businesses, including sales of goods, services, imports, and certain intangible supplies. Some supplies may be GST-exempt, meaning GST is not charged on them, or they may be zero-rated, in which case they are subject to GST at a 0% rate.
3. GST Registration: Businesses with an annual turnover of NZD 60,000 or more are required to register for GST with the Inland Revenue Department (IRD). Once registered, businesses must charge GST on their taxable supplies and can claim input tax credits for the GST paid on their business expenses.
4. GST Returns: Registered businesses must file regular GST returns with the IRD, typically on a bi-monthly, six-monthly, or annual basis, depending on their GST turnover. The GST returns report the GST collected (output tax) and GST paid on expenses (input tax). The net amount is either remitted to the IRD or refunded.
5. Input Tax Credits: Registered businesses can claim input tax credits for the GST they have paid on their business expenses. This allows businesses to offset the GST they pay on purchases against the GST they collect on sales, resulting in a net GST liability or refund.
6. GST on Imported Goods and Services: Goods and services imported into New Zealand are generally subject to GST. For low-value imported goods (valued up to NZD 1,000), offshore suppliers may be required to register for and collect GST on behalf of the New Zealand Customs Service.
7. GST on Digital Services: As of October 1, 2016, non-resident suppliers of digital services (e.g., streaming services, software downloads) to New Zealand consumers are required to register for and charge GST on these services.

It's important for businesses operating in New Zealand to understand and comply with the GST regulations, including registration, reporting, and remittance requirements. As tax laws can change, businesses should consult with the Inland Revenue Department or tax professionals for the most up-to-date information regarding the GST in New Zealand.

Is there any GST Schemes in New Zealand?

Yes, there are several Goods and Services Tax (GST) schemes in New Zealand. These schemes are designed to simplify GST reporting for specific types of businesses and transactions. The main GST schemes in New Zealand include:

1. Standard GST Scheme: This is the standard GST scheme that applies to most businesses in New Zealand. Under this scheme, businesses charge GST on their sales (output GST) and claim GST on their purchases (input GST). GST returns are usually filed on a regular basis, either monthly, two-monthly, or six-monthly, depending on the business's turnover.
2. Payments Basis Scheme: Businesses with an annual turnover of less than NZD $2 million can opt for the payments basis scheme. Under this scheme, businesses only account for GST when they receive payment for their sales or when they make payments for their purchases. This can help with cash flow management for small businesses.
3. Invoice Basis Scheme: This is the default scheme for businesses with an annual turnover of NZD $24 million or more. Under this scheme, GST is accounted for when an invoice is issued or received, regardless of whether payment has been made. Most larger businesses in New Zealand use this scheme.
4. Hybrid Basis Scheme: Some businesses may use a hybrid of the payments basis and invoice basis schemes. This means they account for GST on a payments basis for some transactions and on an invoice basis for others.
5. Non-Residents GST Scheme: This scheme applies to non-resident businesses that make taxable supplies in New Zealand. Non-resident businesses are required to register for GST under this scheme if they exceed the registration threshold for non-residents.
6. Margin Scheme: The margin scheme is applicable to certain transactions involving land or other specified assets. Under this scheme, GST is calculated based on the margin (the difference between the selling price and the purchase price) rather than the full selling price.
7. Tourist Refund Scheme (TRS): The TRS allows tourists and visitors to New Zealand to claim a refund of GST paid on goods purchased in New Zealand, subject to certain conditions.

It's important for businesses to select the most appropriate GST scheme based on their turnover, the nature of their transactions, and their cash flow requirements. Businesses are advised to seek guidance from accounting professionals or tax advisors to determine the best GST scheme for their specific circumstances.

Structure of GST Accounts in the Chart of Accounts for New Zealand

In the Chart of Accounts for businesses in New Zealand, Goods and Services Tax (GST) accounts are structured to accurately record and report GST-related transactions.

Standard GST Scheme

The structure of GST accounts for the Standard GST Scheme may vary depending on the size and complexity of the business, but here is a common framework:

1. GST Control Account (Current Liabilities):
    - 251 - GST Control: This is the main GST Control account that tracks the GST amounts payable or refundable to the New Zealand Inland Revenue Department (IRD). It represents the net balance due to or from the IRD. A credit balance implies that the GST is recoverable from the IRD, while a debit balance indicates GST is payable to the IRD.
2. GST on Sales (Output Tax):
    - 252 - GST on Sales: This account records the GST charged on sales made by the business. It represents the GST collected from customers and is payable to the IRD.
3. GST on Purchases (Input Tax Credit):
    - 253 - GST on Purchases: This account records the GST paid on purchases made by the business. It represents the GST that can be claimed as input tax credits (ITC) from the IRD.
4. GST on Imports:
    - 254 - GST on Imports: This account records the GST paid on goods imported into New Zealand from overseas. The GST on imports is usually paid to the New Zealand Customs Service.
5. GST Adjustments:
    - 255 - GST Adjustments: This account is used to record any adjustments or corrections to previously reported GST amounts, such as bad debts, errors, or changes in taxable supplies.
6. GST on Capital Assets:
    - 256 - GST on Capital Assets: This account is used to record GST on the acquisition of capital assets, such as machinery, equipment, or property.
7. GST on Disposals of Capital Assets:

- 257 - GST on Disposals: This account records GST on the disposal of capital assets.

8. GST on Acquisitions from Overseas Suppliers:
    - 258 - GST on Acquisitions: This account records the GST on goods and services acquired from overseas suppliers. The GST on acquisitions is self-assessed by the business and included in the GST return.
9. GST Bad Debt Relief:
    - 259 - GST Bad Debt Relief: This account records the GST amounts that are claimed as bad debt relief when customers fail to pay their invoices.

It's important to note that the above structure is a general framework, and businesses may have additional sub-accounts or variations based on their specific needs and the complexity of their GST transactions. Properly organizing and maintaining GST accounts in the Chart of Accounts ensures accurate GST reporting and compliance with IRD regulations in New Zealand. Businesses are encouraged to consult with accounting professionals or tax advisors to set up their Chart of Accounts effectively and ensure compliance with GST requirements.

Payments Basis Scheme

In New Zealand, the Payments Basis Scheme is an alternative method of accounting for Goods and Services Tax (GST). Under this scheme, businesses account for GST based on the date they receive payment for goods and services, rather than the date of the invoice. Here is a common structure of GST accounts in the Chart of Accounts for businesses in New Zealand that use the Payments Basis Scheme:

1. GST Collected (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record the GST collected from customers. It represents the GST amount that the business has charged on sales and needs to remit to the New Zealand Inland Revenue (IRD). The balance of this account reflects the net GST payable to the IRD.
2. GST Paid (Current Asset):
    - Account Code: 1XXX
    - Description: This account is used to record the GST paid on purchases made by the business. It represents the GST that the business can claim as input tax credits. The balance of this account reflects the net GST refundable from the IRD.
3. GST Adjustment:

- Account Code: 3XXX
- Description: This account is used to record any adjustments or corrections related to previously reported GST amounts. It may include adjustments for bad debts, errors, or changes in the business's GST status.

4. GST Refund Due (Current Asset):
    - Account Code: 1XXX.X
    - Description: This sub-account is used to track any GST refund due to the business. It reflects the amount of GST that the business has paid on purchases and is eligible for a refund from the IRD.
5. GST Payable (Current Liability):
    - Account Code: 2XXX.X
    - Description: This sub-account is used to track any GST payable by the business. It reflects the amount of GST that the business has collected from customers and needs to remit to the IRD.
6. GST Suspense:
    - Account Code: 4XXX
    - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of GST accounts may vary depending on the specific needs and preferences of the business. Businesses using the Payments Basis Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with New Zealand tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Payments Basis Scheme for GST.

Invoice Basis Scheme

In New Zealand, the Invoice Basis Scheme is the default method of accounting for Goods and Services Tax (GST). Under this scheme, businesses account for GST based on the date of the invoice issued for goods and services, regardless of when the payment is received. Here is a common structure of GST accounts in the Chart of Accounts for businesses in New Zealand that use the Invoice Basis Scheme:

1. GST Collected (Current Liability):

- Account Code: 2XXX
- Description: This account is used to record the GST collected from customers. It represents the GST amount that the business has charged on sales and needs to remit to the New Zealand Inland Revenue (IRD). The balance of this account reflects the net GST payable to the IRD.

2. GST Paid (Current Asset):
   - Account Code: 1XXX
   - Description: This account is used to record the GST paid on purchases made by the business. It represents the GST that the business can claim as input tax credits. The balance of this account reflects the net GST refundable from the IRD.
3. GST Adjustment:
   - Account Code: 3XXX
   - Description: This account is used to record any adjustments or corrections related to previously reported GST amounts. It may include adjustments for bad debts, errors, or changes in the business's GST status.
4. GST Refund Due (Current Asset):
   - Account Code: 1XXX.X
   - Description: This sub-account is used to track any GST refund due to the business. It reflects the amount of GST that the business has paid on purchases and is eligible for a refund from the IRD.
5. GST Payable (Current Liability):
   - Account Code: 2XXX.X
   - Description: This sub-account is used to track any GST payable by the business. It reflects the amount of GST that the business has collected from customers and needs to remit to the IRD.
6. GST Suspense:
   - Account Code: 4XXX
   - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

It's important to note that the account codes and descriptions mentioned above are examples, and the

actual structure of GST accounts may vary depending on the specific needs and preferences of the business. Businesses using the Invoice Basis Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with New Zealand tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Invoice Basis Scheme for GST.

Hybrid Basis Scheme

In New Zealand, the Hybrid Basis Scheme is an option for some businesses to account for Goods and Services Tax (GST) using a combination of the Payments Basis and Invoice Basis methods. Under the Hybrid Basis Scheme, businesses account for GST on different transactions using either the Payments Basis or the Invoice Basis, depending on the nature of the transaction. Here is a common structure of GST accounts in the Chart of Accounts for businesses in New Zealand that use the Hybrid Basis Scheme:

1. GST Collected (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record the GST collected from customers on transactions subject to the Invoice Basis. It represents the GST amount that the business has charged on sales and needs to remit to the New Zealand Inland Revenue (IRD) for these transactions. The balance of this account reflects the net GST payable to the IRD for Invoice Basis transactions.
2. GST Paid (Current Asset):
    - Account Code: 1XXX
    - Description: This account is used to record the GST paid on purchases made by the business on transactions subject to the Invoice Basis. It represents the GST that the business can claim as input tax credits for these transactions. The balance of this account reflects the net GST refundable from the IRD for Invoice Basis transactions.
3. GST Collected (Payments Basis) (Current Liability):
    - Account Code: 2XXX.X
    - Description: This sub-account is used to record the GST collected from customers on transactions subject to the Payments Basis. It represents the GST amount that the business has charged on sales and needs to remit to the IRD for these transactions. The balance of this sub-account reflects the net GST payable to the IRD for Payments Basis transactions.
4. GST Paid (Payments Basis) (Current Asset):

- Account Code: 1XXX.X
- Description: This sub-account is used to record the GST paid on purchases made by the business on transactions subject to the Payments Basis. It represents the GST that the business can claim as input tax credits for these transactions. The balance of this sub-account reflects the net GST refundable from the IRD for Payments Basis transactions.

5. GST Adjustment:
    - Account Code: 3XXX
    - Description: This account is used to record any adjustments or corrections related to previously reported GST amounts for both Invoice Basis and Payments Basis transactions. It may include adjustments for bad debts, errors, or changes in the business's GST status.
6. GST Suspense:
    - Account Code: 4XXX
    - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of GST accounts may vary depending on the specific needs and preferences of the business. Businesses using the Hybrid Basis Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with New Zealand tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Hybrid Basis Scheme for GST.

Non-Residents GST Scheme

In New Zealand, the Non-Residents GST Scheme is designed for non-resident businesses that make supplies of goods and services in New Zealand and are required to register for Goods and Services Tax (GST) under certain circumstances. Non-resident businesses can choose to use the Non-Residents GST Scheme to simplify their GST compliance. Here is a common structure of GST accounts in the Chart of Accounts for non-resident businesses using the Non-Residents GST Scheme in New Zealand:

1. GST Collected (Non-Residents Scheme) (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record the GST collected from customers in New Zealand under the Non-Residents GST Scheme. It represents the GST amount that the non-resident

business has charged on sales and needs to remit to the New Zealand Inland Revenue (IRD) under this scheme. The balance of this account reflects the net GST payable to the IRD.

2. GST Paid (Non-Residents Scheme) (Current Asset):
    - Account Code: 1XXX
    - Description: This account is used to record the GST paid on purchases made by the non-resident business in New Zealand under the Non-Residents GST Scheme. It represents the GST that the non-resident business can claim as input tax credits under this scheme. The balance of this account reflects the net GST refundable from the IRD.
3. GST Adjustment:
    - Account Code: 3XXX
    - Description: This account is used to record any adjustments or corrections related to previously reported GST amounts under the Non-Residents GST Scheme. It may include adjustments for bad debts, errors, or changes in the non-resident business's GST status.
4. GST Refund Due (Current Asset):
    - Account Code: 1XXX.X
    - Description: This sub-account is used to track any GST refund due to the non-resident business under the Non-Residents GST Scheme. It reflects the amount of GST that the non-resident business has paid on purchases and is eligible for a refund from the IRD.
5. GST Payable (Current Liability):
    - Account Code: 2XXX.X
    - Description: This sub-account is used to track any GST payable by the non-resident business under the Non-Residents GST Scheme. It reflects the amount of GST that the non-resident business has collected from customers and needs to remit to the IRD.
6. GST Suspense:
    - Account Code: 4XXX
    - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of GST accounts may vary depending on the specific needs and preferences of the non-resident business. Businesses using the Non-Residents GST Scheme should configure their Chart of

Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with New Zealand tax regulations. Additionally, non-resident businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Non-Residents GST Scheme for GST.

Margin Scheme

In New Zealand, the Margin Scheme is a special scheme that allows registered businesses to calculate Goods and Services Tax (GST) on the profit margin made on certain second-hand goods, land transactions, and other specified supplies. Here is a common structure of GST accounts in the Chart of Accounts for businesses in New Zealand that use the Margin Scheme:

1. Margin Scheme Sales (Current Liability):
    - Account Code: 2XXX
    - Description: This account is used to record sales made under the Margin Scheme. It represents the total value of supplies subject to the Margin Scheme, and the GST is calculated based on the profit margin instead of the full sale value. The balance of this account reflects the net GST payable to the New Zealand Inland Revenue (IRD) for Margin Scheme sales.
2. Margin Scheme GST (Current Liability):
    - Account Code: 2XXX.X
    - Description: This sub-account is used to calculate and record the GST amount payable under the Margin Scheme. The GST is calculated based on the margin, which is the difference between the purchase price and the selling price of the second-hand goods or specified supplies subject to the Margin Scheme.
3. Margin Scheme Purchases (Current Asset):
    - Account Code: 1XXX
    - Description: This account is used to record purchases made under the Margin Scheme. It represents the total value of second-hand goods or specified supplies acquired for resale under the Margin Scheme. The balance of this account reflects the net GST refundable from the IRD for Margin Scheme purchases.
4. Margin Scheme GST Refund (Current Asset):
    - Account Code: 1XXX.X
    - Description: This sub-account is used to track any GST refund due to the business for Margin

Scheme purchases. The GST refund is calculated based on the margin and represents the GST paid on the difference between the purchase price and the selling price of the second-hand goods or specified supplies.

5. GST Adjustment:
    - Account Code: 3XXX
    - Description: This account is used to record any adjustments or corrections related to previously reported GST amounts under the Margin Scheme. It may include adjustments for bad debts, errors, or changes in the business's GST status for Margin Scheme transactions.
6. GST Suspense:
    - Account Code: 4XXX
    - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts, including those related to the Margin Scheme.

It's important to note that the account codes and descriptions mentioned above are examples, and the actual structure of GST accounts may vary depending on the specific needs and preferences of the business. Businesses using the Margin Scheme should configure their Chart of Accounts in their accounting software accordingly to accurately record and report GST transactions in compliance with New Zealand tax regulations. Additionally, businesses should consult with accounting professionals or tax advisors to ensure that they understand the requirements and implications of using the Margin Scheme for GST.

Tourist Refund Scheme (TRS)

In New Zealand, the Tourist Refund Scheme (TRS) allows eligible overseas tourists to claim a refund of the Goods and Services Tax (GST) paid on goods purchased in New Zealand, which they intend to take out of the country with them. However, the TRS process is managed by New Zealand Customs, and businesses are not directly involved in the refund process. Therefore, there are typically no specific GST accounts in the Chart of Accounts for businesses related to the TRS.

For businesses that make sales to tourists eligible for the TRS, the GST treatment remains the same as for any other sale. Businesses will charge GST on the goods sold to eligible tourists, and these GST amounts will be recorded in the regular GST accounts as part of their normal GST reporting.

Here is a common structure of GST accounts in the Chart of Accounts for businesses in New Zealand that may interact with the TRS:

1. GST Collected (Current Liability):
    - Account Code: 2XXX

- Description: This account is used to record the GST collected from all sales made by the business, including sales to eligible tourists under the TRS. It represents the total GST charged on all taxable supplies made by the business, and the balance of this account reflects the net GST payable to the New Zealand Inland Revenue (IRD) for all sales.

2. GST Paid (Current Asset):
    - Account Code: 1XXX
    - Description: This account is used to record the GST paid on all purchases made by the business, including purchases related to goods sold to eligible tourists. It represents the total GST that the business can claim as input tax credits for all purchases, and the balance of this account reflects the net GST refundable from the IRD.
3. GST Adjustment:
    - Account Code: 3XXX
    - Description: This account is used to record any adjustments or corrections related to previously reported GST amounts. It may include adjustments for bad debts, errors, or changes in the business's GST status for all transactions.
4. GST Suspense:
    - Account Code: 4XXX
    - Description: This account is used to temporarily record GST amounts that are not yet allocated to specific transactions or accounts.

Remember that businesses should configure their Chart of Accounts in their accounting software according to their specific needs and compliance requirements. Additionally, businesses should consult with accounting professionals or tax advisors to ensure accurate GST reporting and compliance with New Zealand tax regulations, especially when dealing with international transactions and eligible tourists under the Tourist Refund Scheme.

GST return in New Zealand

What blocks or fields appears on the GST return in New Zealand?

As of ChatGPT's last update in September 2021, the GST (Goods and Services Tax) return in New Zealand typically includes the following blocks or fields:

1. Business Information: This includes the business name, IRD (Inland Revenue Department) number, and the GST registration status.

2. Income: This section requires you to report the total value of taxable supplies (sales) made during the period.

3. Expenses: Here, you declare the total value of GST-exclusive expenses incurred for business purposes during the period.

4. Output Tax: This field is calculated automatically based on the sales made (Income) and the applicable GST rate.

5. Input Tax: This field is calculated automatically based on the expenses claimed (Expenses) and the applicable GST rate.

6. GST Payable (or Refundable): The difference between Output Tax and Input Tax will determine whether you owe GST to the IRD (GST Payable) or are eligible for a GST refund (GST Refundable).

7. Payments or Refunds: In this section, you will enter any additional tax payments made or GST refunds received during the return period.

8. Other GST adjustments: Any adjustments to GST that need to be made, such as corrections for previous periods, should be included here.

9. Final Amount Payable (or Refundable): This is the net amount of GST that you will need to pay to the IRD or that will be refunded to you.

It's important to note that tax regulations can change over time, and there might have been updates or changes to the GST return in New Zealand since my last update. I recommend checking with the New Zealand Inland Revenue or a tax professional to get the most up-to-date and accurate information.

Created with the Standard Edition of HelpNDoc: Transform your help documentation into a stunning website

---

Value Added Tax (VAT) in United Kingdom

As of ChatGPT's last update in September 2021, the United Kingdom (UK) applies a Value Added Tax (VAT). The VAT is a consumption tax levied on the supply of goods and services in the UK.

Here are some key points about the VAT in the United Kingdom:

1. VAT Rates: The UK has different VAT rates for different types of goods and services. The standard VAT rate is 20%, which applies to most goods and services. However, there are reduced rates, such as 5% for certain items like home energy, children's car seats, and women's sanitary products, and a zero rate, which applies to certain essential items like most food, books, and public transport.

2. VAT Registration: Businesses with a taxable turnover that exceeds the VAT registration threshold must register for VAT with Her Majesty's Revenue and Customs (HMRC). As of ChatGPT's last update, the VAT registration threshold was £85,000, but this threshold may change, so it's essential to check the current threshold with HMRC.
3. VAT Returns: Registered businesses are required to file regular VAT returns with HMRC. The frequency of VAT returns depends on the size of the business. Typically, VAT returns are filed quarterly, but some businesses may be eligible to file annually or on a monthly basis.
4. Input Tax and Output Tax: Businesses can claim input tax credit for the VAT they have paid on their business expenses. At the same time, they must charge output tax on the VAT they collect from their customers. The difference between output tax and input tax is the net VAT liability, which is either remitted to or refunded by HMRC.
5. VAT on Imports and Exports: VAT is also applicable to imports and exports of goods and services. Imports are subject to import VAT, while exports are usually zero-rated, meaning VAT is not charged on them.
6. Making Tax Digital (MTD): The UK has implemented Making Tax Digital, a digital system for VAT reporting. It requires VAT-registered businesses with a taxable turnover above the VAT threshold to keep digital records and submit VAT returns using MTD-compatible software.
7. VAT MOSS: For businesses selling digital services to consumers in other EU countries, the VAT Mini One Stop Shop (VAT MOSS) scheme allows them to account for VAT on these cross-border sales in one EU member state rather than registering for VAT in each country separately.

It's essential for businesses operating in the UK to understand and comply with the VAT regulations, including registration, record-keeping, and reporting requirements. As tax laws can change, businesses should consult with HMRC or tax professionals for the most up-to-date information regarding VAT in the United Kingdom.

What is the Tax Schemes for VAT in the United Kingdom?

As of ChatGPT's last update in September 2021, the United Kingdom (UK) follows the Value Added Tax (VAT) system for taxation. The VAT system in the UK includes several schemes designed to simplify VAT reporting and compliance for businesses. Some of the main VAT schemes in the UK are:

1. Standard VAT Scheme: This is the default VAT scheme for most businesses in the UK. Under this scheme, businesses charge VAT on their sales (output VAT) and reclaim VAT on their purchases (input VAT). VAT returns are usually submitted quarterly, and the difference between output VAT and input VAT is paid to or refunded by HM Revenue & Customs (HMRC).
2. Flat Rate Scheme (FRS): The Flat Rate Scheme is designed to simplify VAT reporting for small

businesses. Instead of accounting for the difference between output VAT and input VAT, businesses pay a fixed percentage of their gross turnover to HMRC as VAT. The percentage varies depending on the business's industry, and it allows the business to keep the difference between the fixed rate and the actual VAT charged to customers.

3. Cash Accounting Scheme: The Cash Accounting Scheme allows eligible businesses to account for VAT on the basis of cash received and paid, rather than on invoice dates. This can help businesses with their cash flow as they only pay VAT on customer payments actually received, and they can only reclaim VAT on supplier payments actually made.
4. Annual Accounting Scheme: The Annual Accounting Scheme is designed to simplify VAT administration for small businesses. Instead of submitting quarterly VAT returns, businesses only need to submit one annual return. During the year, they make interim payments based on an estimated VAT liability, and at the end of the year, they reconcile the payments with the actual liability.
5. VAT Margin Scheme: The VAT Margin Scheme is used for businesses that sell second-hand goods, works of art, antiques, or collectibles. Instead of accounting for VAT on the full selling price, businesses only pay VAT on the difference between the selling price and the purchase price (the margin).
6. Tour Operators Margin Scheme (TOMS): TOMS is used by tour operators when calculating VAT on certain travel services. It is applied to businesses that buy and sell travel services, such as package holidays, and it allows them to account for VAT on the margin of the services provided.

It's important for businesses to choose the most appropriate VAT scheme based on their specific circumstances. The VAT schemes aim to simplify the VAT reporting process and help businesses manage their VAT obligations more efficiently. However, businesses should be aware of the eligibility criteria and specific rules for each scheme, as they may vary depending on the size and nature of the business. Businesses are encouraged to seek advice from tax professionals to ensure they comply with the correct VAT scheme and meet all VAT reporting requirements in the UK.

Structure of VAT Accounts in the Chart of Accounts for the United Kingdom

In the Chart of Accounts for businesses in the United Kingdom, Value Added Tax (VAT) accounts are typically structured to accurately record and report VAT-related transactions.

Standard VAT Scheme

The structure of VAT accounts is commonly used for businesses following the Standard VAT Scheme in the United Kingdom. The Standard VAT Scheme is the default and most common VAT scheme used by businesses, especially those with larger turnovers.

Under the Standard VAT Scheme, businesses charge VAT on their sales (output VAT) and reclaim VAT on their purchases (input VAT). The VAT accounts mentioned in the structure reflect this process, with separate accounts for output VAT on sales, input VAT on purchases, and additional accounts for specific VAT-related transactions, such as VAT on imports, VAT on EU acquisitions, reverse charge VAT, VAT adjustments, VAT bad debt relief, and VAT on assets and disposals.

While the structure of VAT accounts is generally applicable to businesses using the Standard VAT Scheme, it's important to note that the Chart of Accounts may vary depending on the specific needs and nature of each business. Smaller businesses or businesses with simpler operations may have a more streamlined Chart of Accounts, while larger or more complex businesses may have a more detailed and comprehensive Chart of Accounts to accurately record their financial transactions and VAT-related activities.

As always, businesses are advised to seek guidance from accounting professionals or tax advisors to ensure their Chart of Accounts and VAT accounting practices comply with the applicable VAT regulations and reporting requirements in the United Kingdom.

The structure of VAT accounts may vary depending on the size and complexity of the business, but here is a common framework based on the Standard VAT Scheme:

1. VAT Control Account (Current Liabilities) : 2200 - VAT Control: This is the main VAT Control account that tracks the VAT amounts payable or refundable to HM Revenue & Customs (HMRC). It represents the net balance due to or from HMRC. A credit balance implies that the VAT is recoverable from HMRC, while a debit balance indicates VAT is payable to HMRC.
2. VAT on Sales (Output VAT): 2201 - Output VAT: This account records the VAT charged on sales made by the business. It represents the VAT collected from customers and is payable to HMRC.
3. VAT on Purchases (Input VAT): 2202 - Input VAT: This account records the VAT paid on purchases made by the business. It represents the VAT that can be reclaimed from HMRC.
4. VAT on Imports: 2203 - VAT on Imports: This account records the VAT paid on goods imported from countries outside the European Union (EU). The VAT on imports is usually paid directly to HMRC.
5. VAT on Acquisitions from EU Suppliers : 2204 - VAT on EU Acquisitions: This account records the VAT on goods acquired from suppliers in EU member states. The VAT on acquisitions is self-accounted for by the business and is included in the VAT return.
6. VAT on Reverse Charge Supplies: 2205 - Reverse Charge VAT: This account records the VAT on reverse charge supplies, where the recipient of the goods or services accounts for the VAT instead of the supplier.
7. VAT Adjustments: 2206 - VAT Adjustments: This account is used to record any adjustments or corrections to previously reported VAT amounts, such as bad debts, errors, or changes in accounting methods.

8. VAT Bad Debt Relief: 2207 - VAT Bad Debt Relief: This account records the VAT amounts that are claimed as bad debt relief when customers fail to pay their invoices.
9. VAT on Assets and Disposals: 2208 - VAT on Assets and Disposals: This account is used to record VAT on capital assets and disposals of assets.

It's important to note that the above structure is a general framework, and businesses may have additional sub-accounts or variations based on their specific needs and the complexity of their VAT transactions. Properly organizing and maintaining VAT accounts in the Chart of Accounts ensures accurate VAT reporting and compliance with HMRC regulations in the United Kingdom. Businesses are encouraged to consult with accounting professionals or tax advisors to set up their Chart of Accounts effectively and ensure compliance with VAT requirements.

Flat Rate Scheme (FRS)

When a business in the United Kingdom opts to use the Flat Rate Scheme (FRS) for VAT, the structure of VAT accounts in the Chart of Accounts may differ from the Standard VAT Scheme. The Flat Rate Scheme is designed to simplify VAT reporting for small businesses by applying a fixed percentage to the gross turnover as the VAT liability to be paid to HM Revenue & Customs (HMRC). Under the FRS, businesses are not required to record the input VAT on purchases and cannot reclaim input VAT, except for certain capital assets.

The typical structure of VAT accounts for businesses using the Flat Rate Scheme may include the following:

1. VAT Control Account (Current Liabilities): This is the main VAT Control account that tracks the VAT amounts payable or recoverable from HMRC. The VAT liability or refund is based on the fixed percentage of the gross turnover.
2. Flat Rate VAT Payable: This account records the VAT payable to HMRC under the Flat Rate Scheme. It is calculated based on the fixed percentage of the gross turnover, and it represents the difference between the output VAT charged to customers and the fixed rate VAT to be paid.
3. VAT on Sales (Output VAT): This account records the VAT charged on sales made by the business, similar to the Standard VAT Scheme. However, under the FRS, the output VAT is not linked to the VAT payable.
4. VAT Adjustments: This account is used to record any adjustments or corrections to previously reported VAT amounts, such as bad debts, errors, or changes in accounting methods. Adjustments may still be necessary, even under the Flat Rate Scheme.
5. Capital Goods Scheme (CGS) Adjustment: Under the FRS, businesses are allowed to reclaim input VAT on capital assets exceeding £2,000, including VAT-inclusive costs, if the standard rules for capital goods scheme apply. This account records any adjustments related to capital goods scheme input VAT

reclaim.

It's important to note that businesses using the Flat Rate Scheme do not typically maintain separate accounts for input VAT on purchases since they are not allowed to reclaim input VAT, except for the specific circumstances related to capital assets. Additionally, the Flat Rate Scheme may have different fixed percentages based on the business's industry, so the specific rates applied will vary.

As with any accounting practices, businesses are advised to seek guidance from accounting professionals or tax advisors to ensure their Chart of Accounts and VAT accounting comply with the regulations and requirements of the Flat Rate Scheme in the United Kingdom.

VAT - Cash Accounting Scheme

When a business in the United Kingdom chooses to use the Cash Accounting Scheme for VAT, the structure of VAT accounts in the Chart of Accounts will be adjusted to accommodate this method of accounting. The Cash Accounting Scheme allows eligible businesses to account for VAT on the basis of cash received and paid, rather than on invoice dates. This can help businesses with their cash flow, as they only pay VAT on customer payments actually received, and they can only reclaim VAT on supplier payments actually made.

The typical structure of VAT accounts for businesses using the Cash Accounting Scheme may include the following:

1. VAT Control Account (Current Liabilities): This is the main VAT Control account that tracks the VAT amounts payable or recoverable from HM Revenue & Customs (HMRC). The VAT liability or refund is based on the cash received and paid, rather than on invoice dates.
2. Output VAT on Cash Sales: This account records the VAT on cash sales made by the business. Under the Cash Accounting Scheme, VAT is accounted for when the payment is received from the customer, not when the invoice is issued.
3. Input VAT on Cash Purchases: This account records the VAT on cash purchases made by the business. VAT is accounted for when the payment is made to the supplier, not when the invoice is received.
4. VAT Adjustments: This account is used to record any adjustments or corrections to previously reported VAT amounts under the Cash Accounting Scheme, such as bad debts or changes in accounting methods.
5. VAT on Sales (Output VAT): Similar to the Standard VAT Scheme, this account records the VAT charged on credit sales made by the business. However, under the Cash Accounting Scheme, the output VAT is not linked to the VAT payable until the cash is received from the customer.
6. VAT on Purchases (Input VAT): Similar to the Standard VAT Scheme, this account records the VAT paid on credit purchases made by the business. However, under the Cash Accounting Scheme, the input VAT is not linked to the VAT reclaimable until the cash is paid to the supplier.

The Cash Accounting Scheme may not be suitable for all businesses, and there are specific eligibility criteria and turnover thresholds that must be met to use this scheme. As always, businesses are advised to seek guidance from accounting professionals or tax advisors to ensure their Chart of Accounts and VAT accounting practices comply with the regulations and requirements of the Cash Accounting Scheme in the United Kingdom.

VAT - Annual Accounting Scheme

When a business in the United Kingdom chooses to use the Annual Accounting Scheme for VAT, the structure of VAT accounts in the Chart of Accounts will be tailored to accommodate this scheme. The Annual Accounting Scheme is designed to simplify VAT reporting for businesses by submitting only one annual VAT return instead of quarterly returns. Businesses make interim payments based on an estimated VAT liability throughout the year, and then reconcile the payments with the actual liability at the end of the year.

The typical structure of VAT accounts for businesses using the Annual Accounting Scheme may include the following:

1. VAT Control Account (Current Liabilities): This is the main VAT Control account that tracks the VAT amounts payable or recoverable from HM Revenue & Customs (HMRC). The VAT liability or refund is based on the interim payments made during the year and the actual liability calculated at the end of the year.
2. VAT Due on Sales: This account records the VAT due on sales made by the business throughout the year. The business makes interim payments based on this account.
3. VAT Reclaimed on Purchases: This account records the VAT reclaimed on purchases made by the business throughout the year. The business makes interim payments based on this account.
4. VAT Adjustments: This account is used to record any adjustments or corrections to previously reported VAT amounts under the Annual Accounting Scheme, such as adjustments for errors or changes in accounting methods.
5. VAT on Sales (Output VAT): This account records the VAT charged on credit sales made by the business throughout the year. The business includes this in the VAT due on sales account for interim payments.
6. VAT on Purchases (Input VAT): This account records the VAT paid on credit purchases made by the business throughout the year. The business includes this in the VAT reclaimed on purchases account for interim payments.
7. Annual VAT Liability or Refund: This account represents the final VAT liability or refund at the end of the year after reconciling the interim payments with the actual liability.

The Annual Accounting Scheme may be beneficial for businesses with a predictable or steady turnover, as it helps with cash flow management by spreading VAT payments throughout the year. However, businesses should carefully consider their eligibility and turnover threshold before choosing this scheme.

As always, businesses are advised to seek guidance from accounting professionals or tax advisors to ensure their Chart of Accounts and VAT accounting practices comply with the regulations and requirements of the Annual Accounting Scheme in the United Kingdom.

VAT Margin Scheme

When a business in the United Kingdom uses the VAT Margin Scheme, the structure of VAT accounts in the Chart of Accounts will be tailored to accommodate this scheme. The VAT Margin Scheme is designed for businesses that sell second-hand goods, works of art, antiques, or collectibles. Under this scheme, businesses calculate VAT based on the difference between the selling price and the purchase price (the margin) rather than the full selling price.

The typical structure of VAT accounts for businesses using the VAT Margin Scheme may include the following:

1. VAT Control Account (Current Liabilities): This is the main VAT Control account that tracks the VAT amounts payable or recoverable from HM Revenue & Customs (HMRC) based on the VAT Margin Scheme calculations.
2. VAT on Margin Sales: This account records the VAT on sales made under the VAT Margin Scheme. The VAT is calculated based on the margin between the selling price and the purchase price.
3. VAT Adjustments: This account is used to record any adjustments or corrections to previously reported VAT amounts under the VAT Margin Scheme, such as adjustments for errors or changes in accounting methods.
4. Margin Sales: This account records the sales made under the VAT Margin Scheme. It includes the selling prices and the corresponding margins.
5. Margin Purchases: This account records the purchase costs of the goods sold under the VAT Margin Scheme. It includes the cost prices and the corresponding margins.
6. VAT Margin Liability: This account represents the final VAT liability calculated based on the margins of the sales and purchases under the scheme.

Businesses using the VAT Margin Scheme should keep detailed records of the goods bought and sold under the scheme, including the purchase cost and the selling price, as this information is crucial for calculating the VAT liability correctly.

As always, businesses are advised to seek guidance from accounting professionals or tax advisors to

ensure their Chart of Accounts and VAT accounting practices comply with the regulations and requirements of the VAT Margin Scheme in the United Kingdom.

VAT - Tour Operators Margin Scheme (TOMS)

When a business in the United Kingdom operates under the Tour Operators Margin Scheme (TOMS), the structure of VAT accounts in the Chart of Accounts will be adjusted to accommodate this specific scheme. The TOMS is designed for businesses that buy and sell travel services, such as package holidays, and it allows them to calculate VAT on the margin of the services provided, rather than on the full selling price.

The typical structure of VAT accounts for businesses using the Tour Operators Margin Scheme (TOMS) may include the following:

1. VAT Control Account (Current Liabilities): This is the main VAT Control account that tracks the VAT amounts payable or recoverable from HM Revenue & Customs (HMRC) based on the TOMS calculations.
2. VAT on TOMS Sales: This account records the VAT on sales made under the Tour Operators Margin Scheme. The VAT is calculated based on the margin between the selling price and the cost of the travel services.
3. VAT Adjustments: This account is used to record any adjustments or corrections to previously reported VAT amounts under the TOMS, such as adjustments for errors or changes in accounting methods.
4. TOMS Sales: This account records the sales made under the Tour Operators Margin Scheme. It includes the selling prices and the corresponding margins.
5. TOMS Purchase Costs: This account records the cost of the travel services purchased by the business for resale under the TOMS. It includes the cost prices and the corresponding margins.
6. TOMS Margin Liability: This account represents the final VAT liability calculated based on the margins of the TOMS sales and purchase costs.

Businesses using the Tour Operators Margin Scheme must keep detailed records of the travel services bought and sold under the scheme, including the purchase costs and the selling prices, as this information is essential for calculating the VAT liability correctly.

As always, businesses are advised to seek guidance from accounting professionals or tax advisors to ensure their Chart of Accounts and VAT accounting practices comply with the regulations and requirements of the Tour Operators Margin Scheme (TOMS) in the United Kingdom.

How would the Tax accounts as mentioned tie up to the Boxes 1 to Box 9 in the UK VAT Return on the Standard VAT Rate?

In the UK VAT Return, the tax accounts mentioned in the Chart of Accounts would tie up to the different boxes on the VAT Return as follows:

1. Box 1: Output VAT - Standard rate (T2400-010) This box represents the total VAT charged on sales made by the business at the standard rate of 20%. The value in this box would be the sum of all transactions recorded under the tax account T2400-010 (Output VAT - Standard rate - 20%).
2. Box 2: Output VAT - Reduced rate (T2400-015) This box represents the total VAT charged on sales made by the business at the reduced rate of 5%. The value in this box would be the sum of all transactions recorded under the tax account T2400-015 (Output VAT - Reduced rate - 5%).
3. Box 3: Output VAT - Zero rated - This box represents the total VAT charged on sales made by the business at a 0% VAT rate. The value in this box would be the sum of all transactions recorded under the tax accounts T2400-030 (Output VAT - Zero Rated Income - 0%), T2400-040 (Output VAT - Zero Rated EU Goods - 0%), and T2400-050 (Output VAT - Zero Rated EU Services - 0%).
4. Box 4: VAT on purchases - This box represents the total VAT paid on purchases made by the business. The value in this box would be the sum of all transactions recorded under the tax accounts T2400-100 (Input VAT - Standard rate - 20%), T2400-115 (Input VAT - Reduced rate - 5%), T2400-120 (Input VAT - EU Acquisitions - 20% - Reverse charged), T2400-130 (Input VAT - EU Acquisitions (Zero Rated) - 0%), T2400-140 (Input VAT - Exempt Expenses - 0%), T2400-150 (Input VAT - Reverse Charge Expenses - 20%), T2400-160 (Input VAT - VAT on Imports - 100%), T2400-170 (Input VAT - Zero Rated EU Expenses - 0%), and T2400-180 (Input VAT - Zero Rated Expenses - 0%).
5. Box 5: Net VAT due (or reclaimed) (calculated) This box represents the difference between Box 3 (Total VAT on sales) and Box 4 (Total VAT on purchases). If Box 3 is greater than Box 4, the difference is the VAT due to HMRC. If Box 4 is greater than Box 3, the difference is the VAT reclaimable from HMRC.
6. Box 6: Total value of sales (excluding VAT) This box represents the total value of all sales made by the business, excluding VAT. It is not directly related to any specific tax account.
7. Box 7: Total value of purchases (excluding VAT) This box represents the total value of all purchases made by the business, excluding VAT. It is not directly related to any specific tax account.
8. Box 8: Total value of supplies of goods to other EU countries (excluding VAT) This box represents the total value of goods supplied by the business to other EU countries, excluding VAT. It is not directly related to any specific tax account.
9. Box 9: Total value of acquisitions of goods from other EU countries (excluding VAT) This box

represents the total value of goods acquired by the business from other EU countries, excluding VAT. It is not directly related to any specific tax account.

The tax accounts mentioned in the Chart of Accounts are used to record and track the VAT amounts related to different types of transactions, which are then reported in the appropriate boxes on the VAT Return. Properly categorizing and recording these transactions is essential to ensure accurate VAT reporting and compliance with the UK tax regulations.

VAT Standard Rate Scheme - Structure of VAT Accounts in the Chart of Accounts

In the Chart of Accounts, Value Added Tax (VAT) payable is typically included in the Current Liabilities section of the Balance Sheet. This account represents the VAT that the business has collected on sales but has not yet remitted to the tax authorities.

To ensure proper accounting and alignment with the VAT return, it's important to structure VAT sub-accounts (VAT codes) for the various rates that apply, within the VAT Control account. The VAT Control account, G2400-000, reflects the net balance due to HM Revenue & Customs (HMRC). A credit balance implies that the VAT is payable to HM Revenue & Customs (HMRC).

The breakdown of the VAT payable account includes the following sub-accounts (T-codes) (T is the prefix for Tax account type) to provide more detailed information about different types of VAT.

The standard structure of the VAT accounts (Tax code sub-accounts) consists of four sections in the Chart of Accounts: Output VAT Codes and Input VAT Codes sections.

1. Output VAT Codes:
    - T2400-010 - Output VAT - Standard rate - 20% (VAT on Sales) This account records the VAT charged on standard-rated sales made by the business. Standard-rated supplies typically attract a VAT rate of 20%.
    - T2400-015 - Output VAT - Reduced rate - 5% (VAT on Sales) This account records the VAT charged on reduced-rated sales made by the business. Reduced-rated supplies typically attract a lower VAT rate of 5%.
    - T2400-020 - Output VAT - Exempt Income - 0%: This account is used to record sales that are exempt from VAT. No VAT is charged on exempt supplies, and the input tax on related expenses is not recoverable.
    - T2400-030 - Output VAT - Zero Rated Income - 0% This account is used to record sales that are subject to a 0% VAT rate. Although no VAT is charged on zero-rated supplies, businesses can recover input VAT on related expenses.

- T2400-040 - Output VAT - Zero Rated EU Goods - 0% This account is specific to transactions involving the supply of goods to other European Union (EU) countries at a 0% VAT rate.
- T2400-050 - Output VAT - Zero Rated EU Services - 0%: This account is specific to transactions involving the supply of services to other European Union (EU) countries at a 0% VAT rate.
- T2400-070 - Adjustment - Bad Debt Relief - 20%: This account is used to record the VAT amount that becomes uncollectible due to bad debts. It is an adjustment to reduce the Output VAT liability on the VAT return.
- T2400-075 - Adjustment - Bad Debt Relief - 5%: This account is used to record the VAT amount that becomes uncollectible due to bad debts. It is an adjustment to reduce the Output VAT liability on the VAT return.

  Please note that specific rules and procedures may apply to claiming Bad Debt Relief, and businesses need to meet certain conditions to be eligible for the relief. It's crucial to follow the regulations and maintain proper documentation to support the claim for bad debt relief. As always, consulting with accounting professionals familiar with the UK VAT rules and requirements can help businesses correctly apply Bad Debt Relief in their VAT reporting and align it with the UK VAT returns.

2. Input VAT Codes:
   - 2400-100 - Input VAT - Standard rate - 20%: This account records the VAT paid on purchases of goods and services subject to the standard VAT rate of 20%.
   - 2400-115 - Input VAT - Reduced rate - 5%: This account records the VAT paid on purchases of goods and services subject to the reduced VAT rate of 5%.
   - 2400-120 - Input VAT - EU Acquisitions (20%) - Reverse charge This account is used for VAT on goods acquired from other EU countries, where the recipient accounts for the VAT using the reverse charge mechanism.
   - 2400-130 - Input VAT - EU Acquisitions (Zero Rated) - 0%: This account is used for VAT on goods acquired from other EU countries at a 0% VAT rate.
   - 2400-140 - Input VAT - Exempt Expenses - 0%: This account is used to record expenses that are exempt from VAT. No input VAT can be recovered on exempt expenses.
   - 2400-150 - Input VAT - Reverse Charge Expenses (20%) This account is used for VAT on services received where the recipient accounts for the VAT using the reverse charge mechanism.

- 2400-160 - Input VAT - VAT on Imports - 100%: This account records the VAT paid on goods imported from countries outside the EU.
- 2400-170 - Input VAT - Zero Rated EU Expenses - 0% This account is specific to VAT on services received from other EU countries at a 0% VAT rate.
- 2400-180 - Input VAT - Zero Rated Expenses - 0% This account is specific to VAT on services received at a 0% VAT rate (outside the EU).

Additionally, there is the VAT Payment Account, G2400-500, which is used to record payments in cases where the Output VAT exceeds the Input tax. This represents the VAT payable as submitted on the VAT return, and any payments to HM Revenue & Customs (HMRC) would be recorded to this account.

Conversely, if the Input VAT exceeds the Output VAT, resulting in a tax refund due from HM Revenue & Customs (HMRC), the refund received would be recorded to the VAT Payment Account, G2400-500.

In addition to this example and text, it is important to note that this is a basic structure of the VAT Accounts. Depending on the complexities for the nature of your business, such as exporting of taxable supplies, importing of taxable supplies, vat schemes, adjustments, etc., you may need to add additional tax codes applicable to your business.

This well-organized structure ensures that VAT liabilities are accurately accounted for and helps businesses in complying with tax regulations while maintaining clear records for reporting and analysis.

Overall, the explanation provides a comprehensive understanding of how VAT is accounted for in the Chart of Accounts for the United Kingdom, and the breakdown of sub-accounts offers valuable insights into the different components of VAT transactions.

It's important for businesses to maintain accurate records and ensure that VAT liabilities are correctly calculated and reported in compliance with the tax regulations in the United Kingdom. As always, consulting with accounting professionals or tax experts can provide further guidance and ensure proper adherence to the tax laws and regulations related to VAT.

The specific structure of the Chart of Accounts may vary depending on the business's needs, industry, and the complexity of its VAT transactions. It's important to organize the accounts in a way that makes sense for the business's financial reporting and compliance requirements. Additionally, regular updates and adjustments may be necessary to accommodate changes in VAT regulations and the business's operations.

Additional Tax Codes and Tax Rates

Additional tax rates and specific VAT scenarios applicable to businesses using the VAT Flat rate scheme

Additional Tax Codes - Flat rate scheme: (additional accounts based on specific VAT schemes and regulations)

- 2400-200 - Flat rate @ 15% VAT on Capital Sales: This tax rate of 15% is applied to record VAT on the sales of fixed assets when a business is using the VAT flat rate scheme.
- 2400-210 - Flat rate @ 20% VAT on Capital Sales: This tax rate of 20% is also applied to record VAT on the sales of fixed assets under the VAT flat rate scheme.
- 2400-220 - Flat rate @ 20% VAT on Capital Purchases: This tax rate of 20% is used to record VAT on the purchases of fixed assets when a business is using the VAT flat rate scheme.

NOTE: 2400-200 - Flat rate @ 15% VAT on Capital Sales is the percentage correct for the Flat Tate scheme in a UK Chart of Accounts?

The percentage of 15% for "*VAT on Capital Sales*" as part of the additional tax codes in a Chart of Accounts seems to be incorrect for the VAT flat rate scheme in the United Kingdom. In the UK's VAT flat rate scheme, businesses charge VAT to their customers at a fixed rate based on their industry sector. However, the percentage rate is typically higher than the standard VAT rate to simplify accounting for small businesses.

The VAT flat rate scheme rates vary depending on the business's industry, and they are generally higher than the standard VAT rate to account for both the VAT on sales and the VAT on expenses in a single flat rate. For example, a business might apply a flat rate of 12% or 14.5% (as an example) for its sector, and this rate would be used for both output VAT (sales) and input VAT (purchases).

The actual flat rate percentage applicable to a business would depend on the specific industry sector it falls under as defined by HM Revenue & Customs (HMRC). Therefore, it's important for businesses to check the correct VAT flat rate applicable to their industry and ensure that they apply the correct rate to their sales and purchases when using the VAT flat rate scheme.

As VAT regulations and rates can change over time, it's essential for businesses to keep updated with the latest information from HMRC or consult with a qualified tax professional to ensure accurate and compliant reporting in their Chart of Accounts and VAT returns.

Additional tax rates and specific VAT scenarios applicable to businesses using the VAT Domestic Reverse Charge mechanism

Additional tax rate for the Domestic Reverse Charge (DRC): (Use the VAT domestic reverse charge for building and construction services).

- 2400-300 - Domestic Reverse Charge @ 20% (VAT on Income): This tax rate of 20% is used to record the VAT on income when the domestic reverse charge mechanism applies for specific types of transactions.
- 2400-310 - Domestic Reverse Charge @ 20% (VAT on Expenses): This tax rate of 20% is used to record the VAT on expenses when the domestic reverse charge mechanism applies. Under the reverse charge, the recipient of the services accounts for the VAT instead of the supplier.
- 2400-320 - Domestic Reverse Charge @ 5% (VAT on Income): This tax rate of 5% is used to record the VAT on income when the domestic reverse charge mechanism applies to certain transactions with a reduced rate.
- 2400-330 - Domestic Reverse Charge @ 5% (VAT on Expenses): This tax rate of 5% is used to record the VAT on expenses when the domestic reverse charge mechanism applies to certain transactions with a reduced rate.

The domestic reverse charge regulation is a mechanism used in some countries where the responsibility for reporting and paying VAT shifts from the supplier to the recipient for certain types of supplies. This often applies to business-to-business transactions to combat VAT fraud and ensure that VAT is correctly accounted for.

It's important for businesses to accurately apply these additional tax rates in their accounting systems and VAT returns as per the regulations and guidelines set by the relevant tax authority. Additionally, it's recommended to consult with a qualified tax professional to ensure compliance with the specific VAT rules and requirements applicable to the business's circumstances.

Capital Goods Scheme (CGS)

VAT in UK is there a difference between standard and capital goods?

Yes, in the United Kingdom's Value Added Tax (VAT) system, there is a distinction between standard-rated VAT and capital goods scheme (CGS) when it comes to certain types of purchases. Here's an overview of the difference between these two concepts:

1. Standard-Rated VAT: Standard-rated VAT is the regular rate of VAT applied to most goods and services in the UK. As of ChatGPT's knowledge cutoff date in September 2021, the standard rate of VAT in the UK is usually 20%. This rate is applied to most consumer goods and services, with a few exceptions like zero-rated items (such as most food and children's clothing) and reduced-rated items (such as domestic fuel and power at 5% VAT).
2. Capital Goods Scheme (CGS): The Capital Goods Scheme is a mechanism within the UK VAT system that is specifically designed to address the input tax recovery on certain capital assets. These assets are expected to have a long-lasting benefit to a business. When a business acquires or constructs a capital asset, such as real estate or machinery, the input VAT (VAT paid on purchases) can usually be recovered over time. The CGS helps to ensure that the recovery of input tax is aligned with the actual use of the asset for business purposes over its useful life.

Under the CGS, businesses need to make adjustments to their input VAT claims over time based on changes in the use of the capital asset. If the business's use of the asset changes, adjustments are made to the input tax claim to reflect the actual proportion of the asset's use for business purposes. This prevents overrecovery or underrecovery of input VAT on assets that have both business and non-business use.

It's important to note that VAT regulations and rates can change, and specific rules and procedures related to standard-rated VAT and the Capital Goods Scheme may have evolved since my last update in September 2021. If you're seeking the most up-to-date and accurate information on VAT in the UK, I recommend consulting the official HM Revenue & Customs (HMRC) website or seeking advice from a tax professional.

Where would the "Capital Goods Scheme (CGS)" fit in the chart of accounts and the UK VAT return?

In the context of the Chart of Accounts and the UK VAT return, the "*Capital Goods Scheme (CGS)*" would typically involve specific accounting entries and adjustments to accurately reflect the recovery of input VAT on capital assets over their useful life. Here's how the CGS might fit into these components:

1. Chart of Accounts: Within the Chart of Accounts, you might create specific accounts to track the input VAT related to capital assets subject to the Capital Goods Scheme. These accounts would help you monitor the recovery of input VAT as adjustments are made over time. For example:
    - Input VAT on Capital Assets (a liability account): This account would be used to initially record the input VAT paid on the acquisition or construction of capital assets.
    - CGS Adjustment - Increase (an expense account): This account would be used to record adjustments that increase the input VAT recovery due to changes in the business's use of the capital asset.

- CGS Adjustment - Decrease (a revenue account): This account would be used to record adjustments that decrease the input VAT recovery due to changes in the business's use of the capital asset.

2. UK VAT Return: On the UK VAT return, the Capital Goods Scheme adjustments would be reported in the appropriate boxes to ensure accurate VAT recovery and compliance. The specific boxes where CGS adjustments are reported can vary based on the current VAT return format. However, as of ChatGPT's last update in September 2021, these adjustments are generally reported in boxes 4 and 7 of the VAT return:
    - Box 4 (Input tax): This box is used to report the total input tax recoverable on purchases and expenses. CGS adjustments that increase the input VAT recovery would be added to this box.
    - Box 7 (Total value of purchases): This box is used to report the total value of purchases before VAT. CGS adjustments that decrease the input VAT recovery would be subtracted from this box.

It's important to note that the VAT return and reporting requirements can change, and specific adjustments related to the Capital Goods Scheme may have evolved since my last update.

Keep in mind that accurate and compliant reporting of the Capital Goods Scheme requires a solid understanding of VAT regulations and proper accounting practices. It's advisable to work with a qualified accountant or financial professional who is knowledgeable about VAT and can assist you in setting up your Chart of Accounts and reporting accurately on your VAT return.

Is "Capital Goods Scheme (CGS)" part of the Standard VAT Scheme?

Yes, the "*Capital Goods Scheme (CGS)*" is a part of the standard VAT scheme in the United Kingdom. The CGS is a specific mechanism within the standard VAT scheme that addresses the recovery of input VAT (VAT paid on purchases) on capital assets over their useful life.

Under the standard VAT scheme, businesses account for VAT on their sales and purchases according to the standard VAT rates, record their transactions in the VAT return, and make payments or claims for VAT based on the net difference between their output tax (VAT collected from customers) and input tax (VAT paid to suppliers).

The Capital Goods Scheme is designed to ensure that the recovery of input tax on capital assets accurately reflects their business use over time. As capital assets like real estate or machinery may be used for both business and non-business purposes, the CGS involves making adjustments to input VAT claims to align with the actual use of these assets for business purposes.

The CGS requires businesses to periodically review the use of capital assets and make adjustments to the input VAT recovery if the business use changes. These adjustments are then reported on the VAT return as

part of the standard VAT reporting process.

In summary, while the Capital Goods Scheme is a specific aspect of the standard VAT scheme in the UK, it introduces additional considerations and adjustments to the VAT reporting process for businesses that acquire or construct capital assets.

Capital Goods Scheme (CGS) and the Flat Rate Scheme

The "*Capital Goods Scheme (CGS)*" and the "Additional Tax Codes - Flat rate scheme" you mentioned are separate concepts within the UK VAT system. Let's clarify the relationship between these two:

1. Capital Goods Scheme (CGS):
    - The CGS is a mechanism designed to adjust the recovery of input VAT on capital assets over their useful life.
    - It applies to businesses that acquire or construct capital assets like real estate or machinery, and ensures that the input VAT recovery accurately reflects the business use of these assets.
    - Adjustments under the CGS are made to input VAT claims over time based on changes in the use of the capital asset.
    - CGS adjustments are typically reported on the standard VAT return.
2. Additional Tax Codes - Flat Rate Scheme:
    - The VAT Flat Rate Scheme is an alternative way for small businesses to calculate and pay VAT.
    - Under the Flat Rate Scheme, businesses apply a fixed VAT rate to their gross turnover and pay the calculated amount to HMRC.
    - The "*Additional Tax Codes*" you mentioned (e.g., 2400-200, 2400-210, 2400-220) appear to represent different tax codes for recording VAT on capital sales and purchases under the VAT Flat Rate Scheme.
    - These tax codes are used to account for VAT on the sales and purchases of fixed assets when a business is using the Flat Rate Scheme.
    - The VAT rates associated with these tax codes (15% and 20%) correspond to the fixed VAT rates used in the Flat Rate Scheme.

In summary, while both the Capital Goods Scheme and the VAT Flat Rate Scheme are part of the UK VAT system, they address different aspects of VAT calculation and reporting. The Capital Goods Scheme focuses on adjusting input VAT recovery on capital assets over time, while the VAT Flat Rate Scheme provides an alternative method for calculating and paying VAT for eligible businesses.

What is EC Acquisitions (20%) EC Acquisitions (Zero Rated)?

EC Acquisitions (20%) and EC Acquisitions (Zero Rated) refer to specific types of purchases made by a business in the context of the European Union (EU) value-added tax (VAT) system. These terms are applicable when a business in one EU member state purchases goods or services from a supplier in another EU member state.

1. EU Acquisitions (20%): This term refers to purchases of goods or services from another EU member state where the supplier charges VAT at the standard rate of 20%. The purchasing business will account for the VAT on these acquisitions in their own country at the applicable standard rate. The VAT amount paid on these acquisitions is generally recoverable as input tax in the VAT return of the purchasing business.
2. EU Acquisitions (Zero Rated): This term refers to purchases of goods or services from another EU member state where the supplier charges VAT at a rate of 0%. The purchasing business will account for the VAT on these acquisitions in their own country at a zero rate. While the supplier does charge VAT at 0%, the VAT amount is effectively neutral, and no actual VAT is paid to the supplier. The purchasing business may still need to report these acquisitions in their VAT return but at the zero rate.

It's important to note that the rules and terminology may vary slightly between different EU member states, and businesses should ensure they understand the specific requirements and obligations for EU Acquisitions in their country. Additionally, businesses engaged in cross-border transactions within the EU should keep proper documentation and records to comply with VAT regulations and claim any eligible VAT refunds or input tax credits appropriately. Consulting with tax advisors or professionals familiar with the VAT rules in the specific EU member state is advisable to ensure accurate VAT reporting and compliance.

"EC Acquisitions (20%) EC Acquisitions (Zero Rated)" Is there any other VAT such as Reduced rate (5%) or Exempt VAT applicable?

Yes, in addition to the standard rate, there are other VAT rates and exemptions that may be applicable in the European Union (EU) and other countries with VAT systems. The most common ones include:

1. Reduced Rate (e.g., 5%, 7%, 10%): Some goods and services may be subject to a reduced rate of VAT, which is lower than the standard rate. Reduced rates are often applied to essential goods and services to make them more affordable and to promote certain economic activities. The specific items eligible for reduced rates vary between countries and are subject to each country's VAT regulations.
2. Zero-Rated VAT: Zero-rated VAT means that goods or services are subject to VAT at a rate of 0%. While the supplier still accounts for VAT on these transactions, the actual VAT amount charged is zero. Zero-rated VAT is often applied to certain goods and services that are considered essential or to

support specific sectors such as food, medicine, or exports.

3. Exempt VAT: Some goods and services may be exempt from VAT altogether. Unlike zero-rated items, exempt items do not attract any VAT, and the supplier does not charge VAT on these transactions. However, businesses making exempt supplies may not be entitled to reclaim the input VAT paid on related purchases.
4. Mixed Supplies: Some businesses may provide a combination of goods and services, some of which are subject to standard VAT, reduced VAT, or zero-rated VAT, while others may be exempt. Handling the VAT treatment for mixed supplies can be more complex and may require careful consideration of the specific rules and regulations.

It's essential for businesses to correctly identify the VAT rates applicable to their supplies and purchases to ensure accurate VAT reporting and compliance. The VAT rates and exemptions may vary between countries, so businesses operating in multiple jurisdictions need to be aware of the rules in each location where they trade. Additionally, maintaining proper documentation and accurate records is crucial for VAT compliance and to support any claims for input tax credits or VAT refunds. Businesses should consult with tax advisors or professionals familiar with the VAT regulations in their country to ensure they are adhering to the correct VAT rates and requirements.

What is the MTD VAT Return?

MTD VAT Return refers to the Making Tax Digital (MTD) for VAT initiative introduced by HM Revenue & Customs (HMRC) in the United Kingdom. It is part of the UK government's efforts to modernize and digitize the tax system, making it easier for businesses and individuals to manage their taxes online.

Under the MTD for VAT, businesses with a taxable turnover above the VAT threshold (currently £85,000) are required to keep digital records of their VAT transactions and submit their VAT returns electronically using compatible accounting software. This means that businesses must use MTD-compatible software to maintain their VAT records and report their VAT information directly to HMRC through the digital platform.

The key features of MTD VAT Return include:

1. Digital Record-Keeping: Businesses must use MTD-compatible accounting software to maintain digital records of all their VAT transactions, including sales, purchases, and expenses.
2. Quarterly Reporting: Businesses submit their VAT returns on a quarterly basis through the MTD digital platform. The submission process is done electronically, and manual submission through the HMRC website is no longer allowed for businesses mandated to use MTD.
3. VAT Account: Businesses must also keep a digital VAT account that summarizes their VAT liability and payments for each VAT period.

4. VAT Payment: VAT payments are still made as before, but the reporting and record-keeping processes are digital under MTD.

MTD for VAT aims to improve the accuracy and efficiency of VAT reporting, reduce errors, and provide businesses with a clearer view of their VAT position. It also streamlines the interaction between businesses and HMRC, making the tax compliance process more streamlined and less prone to errors.

It's essential for affected businesses to ensure they are compliant with MTD for VAT requirements by using MTD-compatible accounting software and maintaining digital records of their VAT transactions. Businesses can check with HMRC or their accounting software providers to confirm that they are using the appropriate software for MTD compliance.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of a Help Authoring Tool

European Union (EU) value-added tax (VAT) system

What is the European Union (EU) value-added tax (VAT) system?

The European Union (EU) value-added tax (VAT) system is a harmonized tax framework that governs the collection and administration of VAT within the member states of the European Union. VAT is a consumption tax levied on the value added to goods and services at each stage of production or distribution. It is ultimately borne by the final consumer, but businesses act as intermediaries in collecting and remitting the tax to the government.

The EU VAT system aims to create a single market for goods and services within the EU by providing a uniform set of rules for VAT across all member states. This helps facilitate trade and cross-border transactions between EU countries and reduces administrative barriers for businesses operating within the EU.

Key features of the EU VAT system include:

1. Harmonized VAT Rates: Each EU member state sets its own standard and reduced VAT rates, but there is a minimum standard rate (usually 15% or higher) that all member states must apply. Additionally, certain goods and services may be subject to reduced or zero rates across the EU.
2. Intra-EU Transactions: VAT is applied to goods and services traded between EU member states. Businesses that supply goods or services to other VAT-registered businesses in different EU countries can often zero-rate the sale (intra-community supply) and the buyer accounts for the VAT using the reverse charge mechanism.

3. VAT Registration Thresholds: Each member state may set its own VAT registration thresholds, below which businesses are not required to register for VAT. However, once a business's turnover exceeds the threshold, it must register and comply with the relevant VAT rules.
4. VAT Returns and Reporting: VAT-registered businesses must regularly submit VAT returns to their national tax authorities, reporting the VAT collected on sales (output VAT) and the VAT paid on purchases (input VAT). The difference between output VAT and input VAT is the net amount payable to or refundable from the tax authority.
5. One-Stop Shop (OSS): To simplify VAT compliance for cross-border e-commerce transactions, the EU has introduced the One-Stop Shop (OSS) mechanism. This allows businesses to register for VAT in one EU member state and submit a single VAT return for all their cross-border sales to EU consumers.

The EU VAT system is governed by the EU VAT Directive, which provides the legal framework for VAT across the EU. However, each member state may have its own specific rules and regulations to implement the EU VAT system within their jurisdiction. Businesses operating within the EU must adhere to the relevant VAT rules and keep accurate records to comply with the VAT requirements in their country and for cross-border transactions with other EU member states.

What is EC and EU for in EC Acquisitions?

In the context of VAT (Value Added Tax) within the European Union (EU), "*EC*" stands for *"European Community*." However, since January 1, 2021, the term "*EC*" has been replaced by "*EU*" in the VAT rules due to the UK's departure from the EU and the end of the Brexit transition period. Therefore, the correct term for cross-border transactions within the EU is now "*EU Acquisitions*" instead of "EC Acquisitions."

Prior to Brexit, "*EC Acquisitions*" referred to the purchase of goods or services by a VAT-registered business in one EU member state from a supplier in another EU member state. The supplier would charge VAT at their country's VAT rate (either standard, reduced, or zero-rated), and the purchaser would account for the VAT using the reverse charge mechanism. This mechanism allowed the VAT-registered buyer to self-assess the VAT due on the acquisition and report it in their own VAT return.

Now, after Brexit, the term "*EU Acquisitions*" is used to describe similar cross-border transactions involving VAT-registered businesses within the EU, excluding the UK. The VAT treatment for these transactions remains largely the same, with the reverse charge mechanism still applying.

It's essential for businesses to use the correct terminology and comply with the VAT rules applicable in their country and when dealing with cross-border transactions within the EU. The specific VAT rates, rules, and terminology may vary between EU member states, so businesses should seek guidance from tax advisors or professionals familiar with the VAT regulations in the relevant jurisdictions.

What is Harmonized VAT Rates?

Harmonized VAT rates refer to a uniform or standardized system of Value Added Tax (VAT) rates applied across different countries or regions. The goal of harmonization is to create consistency in VAT rates, making it easier for businesses and consumers to understand and comply with tax obligations when trading across borders.

In the context of international trade and the European Union (EU), harmonized VAT rates are particularly relevant. The EU has a harmonized VAT system that sets rules and guidelines for VAT rates applied by its member states. While individual member states have some flexibility in setting their VAT rates, certain goods and services must adhere to minimum standard rates, and others may be eligible for reduced rates or exemptions.

The harmonized VAT rates in the EU as of ChatGPT's last update in September 2021 were as follows:

1. Standard Rate: This rate applies to most goods and services. It varies slightly among member states but cannot be lower than 15%.
2. Reduced Rates: Member states can apply reduced rates, which must be higher than 5%, to specific goods and services, such as essential food, books, medical equipment, and more.
3. Zero Rate: Some goods and services can be zero-rated, meaning no VAT is charged. Examples include certain food items, medical supplies, and exports to non-EU countries.
4. Exempt: Certain goods and services may be exempt from VAT altogether, such as healthcare, education, and insurance.

The harmonized VAT rates in the EU aim to facilitate cross-border trade and create a level playing field for businesses. Businesses can have a better understanding of their tax obligations when operating within the EU, as the VAT rates are relatively consistent across member states.

Outside the EU, some other regions or economic blocs may also implement harmonized VAT rates or similar tax harmonization efforts to simplify tax compliance and foster economic integration. The specific VAT rates and rules will vary from one country or region to another, depending on their tax policies and agreements in place.

What is Intra-EU Transactions?

Intra-EU transactions refer to the movement of goods and services between countries that are members of the European Union (EU). These transactions involve trade or commercial activities taking place within the borders of the EU, involving businesses located in different EU member states.

Intra-EU transactions are an essential aspect of the EU's single market, which aims to create a unified and

integrated economic area with the free movement of goods, services, capital, and people among member states. The single market eliminates barriers to trade, such as tariffs and customs duties, and seeks to promote economic growth, efficiency, and competition within the EU.

Key characteristics of intra-EU transactions include:

1. No Customs Duties: Since the EU is a customs union, customs duties are not levied on goods traded between member states. This means that goods can move freely across EU borders without facing customs charges.
2. VAT Treatment: Intra-EU transactions are subject to the EU's harmonized rules for Value Added Tax (VAT). VAT is charged by the supplier in the member state where the goods are dispatched or where services are provided. The VAT is then usually accounted for and paid by the recipient in the member state where the goods are received or the services are consumed. This is known as the "reverse charge mechanism."
3. Intrastat Reporting: For statistical purposes, businesses engaged in intra-EU trade are required to submit Intrastat declarations. Intrastat is a system for collecting information on the movement of goods between EU member states.
4. Services and Digital Transactions: Intra-EU transactions also cover the supply of services and digital services (e.g., telecommunications, broadcasting, electronically supplied services) between businesses in different member states. Special VAT rules, such as the VAT Mini One Stop Shop (VAT MOSS), apply to certain digital services provided to non-business customers (consumers) in other EU countries.

It's important for businesses engaged in intra-EU transactions to be familiar with the specific VAT rules and regulations governing such trade. Compliance with VAT obligations, including proper invoicing, reporting, and VAT registration in relevant member states, is essential to avoid penalties and ensure smooth cross-border operations within the EU. Businesses should seek advice from tax professionals or local tax authorities to understand their VAT obligations for intra-EU transactions.

What is One-Stop Shop (OSS)?

One-Stop Shop (OSS) is a simplified VAT registration and compliance scheme introduced by the European Union (EU) to simplify the VAT obligations for businesses that supply digital services to consumers in multiple EU member states. The scheme aims to streamline the VAT reporting process for cross-border digital services, making it easier and more efficient for businesses to comply with their VAT obligations.

Before the introduction of OSS, businesses that supplied digital services to consumers in other EU member states were required to register for VAT in each individual member state where they had customers. This could be administratively burdensome and time-consuming, especially for small and medium-sized businesses operating in multiple countries.

With OSS, businesses have the option to register for VAT in a single EU member state and use that registration to account for the VAT on their cross-border digital service supplies to consumers in other EU countries. The main features of the One-Stop Shop scheme are as follows:

1. VAT Registration: Businesses that wish to use the OSS must register for VAT in an EU member state of their choice. This state is known as the "Member State of Identification."
2. Quarterly Returns: Under OSS, businesses submit quarterly VAT returns to the Member State of Identification. The returns cover all the VAT due on the cross-border digital service supplies made to consumers in other EU member states.
3. Payment of VAT: The VAT collected through OSS is paid to the tax authorities of the Member State of Identification, which then distributes the appropriate amounts to the tax authorities of the other EU member states.
4. Uniform VAT Rules: The OSS scheme applies uniform VAT rules to cross-border digital services, regardless of the EU member state where the consumers are located. This simplifies the VAT treatment for businesses and ensures consistency in reporting.
5. VAT MOSS for Non-EU Suppliers: Non-EU businesses that supply digital services to EU consumers can also use a similar scheme known as the VAT Mini One Stop Shop (VAT MOSS) to comply with their VAT obligations.

The One-Stop Shop scheme is designed to ease the compliance burden for businesses engaged in cross-border digital services, promoting the growth of the digital economy within the EU. It allows businesses to use a single VAT registration and reporting system, reducing administrative costs and complexity associated with multiple VAT registrations in different member states.

Created with the Standard Edition of HelpNDoc: Experience a User-Friendly Interface with HelpNDoc's Documentation Tool

VAT MOSS

What is VAT MOSS?

VAT MOSS stands for "*VAT Mini One Stop Shop*." It is a scheme introduced by the European Union (EU) to simplify the process of VAT (Value Added Tax) compliance for businesses that supply certain digital services to customers in multiple EU member states.

Prior to the introduction of VAT MOSS, businesses that provided digital services (e.g., telecommunications, broadcasting, and electronically supplied services) to customers in different EU countries had to register

for VAT in each member state where their customers were located. This resulted in significant administrative burdens and compliance complexities for such businesses.

With VAT MOSS, eligible businesses can register for the scheme in their home EU member state and submit a single quarterly VAT return that covers all their sales to customers in other EU countries. The tax authorities in the home member state will then distribute the VAT collected to the relevant member states where the customers are located.

Key points about VAT MOSS:

1. Applicability: VAT MOSS is applicable to businesses established within the EU that supply digital services to consumers (non-business customers) in other EU member states.
2. Digital Services: The scheme covers a range of digital services, such as streaming or downloading of videos, music, e-books, online courses, software, mobile applications, and other electronically supplied services.
3. Single VAT Return: Instead of registering for VAT in multiple member states, businesses registered for VAT MOSS can submit a single quarterly VAT return and payment to their home member state.
4. VAT Rates: The VAT rates used under VAT MOSS are those of the member states where the services are consumed by customers.
5. Thresholds: Businesses using VAT MOSS must comply with the distance selling thresholds of the EU member states they are supplying to. Once the threshold in a specific member state is exceeded, the business must charge the VAT rate of that member state on subsequent sales to customers in that country.

VAT MOSS is intended to simplify the VAT compliance process for digital service providers, reduce administrative burdens, and improve cross-border trade within the EU. It allows businesses to deal with their VAT obligations in a more efficient manner, without the need to register for VAT in multiple countries where they have customers.

VAT MOSS - Structure of VAT Accounts in the Chart of Accounts

The structure of VAT accounts in the Chart of Accounts for businesses using the VAT MOSS scheme will typically include specific accounts to track the VAT on digital services provided to consumers in different EU member states. Here is a possible structure of VAT accounts in the Chart of Accounts for businesses using VAT MOSS:

1. VAT MOSS Control Account: This is the main VAT MOSS control account that tracks the net VAT payable or refundable under the scheme. It represents the total VAT collected on digital services provided to customers in other EU member states and the total VAT owed to the respective tax

authorities of those member states.

2. VAT MOSS Sales - Standard Rate: This account records the VAT charged on digital services provided to consumers in other EU member states at the standard rate. It represents the VAT collected on such sales and is payable to the respective tax authorities.
3. VAT MOSS Sales - Reduced Rate: If applicable, this account records the VAT charged on digital services provided at a reduced rate to consumers in specific EU member states that have reduced VAT rates for certain services.
4. VAT MOSS Sales - Zero Rate: This account records the VAT charged on digital services that are subject to a zero rate in certain EU member states.
5. VAT MOSS Input Tax: This account tracks the VAT incurred on expenses directly related to the supply of digital services under the VAT MOSS scheme. It includes input tax on costs such as software licenses, digital content, and other services purchased for the provision of the digital services.
6. VAT MOSS Adjustments: This account is used to record any adjustments or corrections to previously reported VAT amounts under the VAT MOSS scheme. It may include adjustments for bad debts, errors, or changes in accounting methods.
7. VAT MOSS Refunds: If applicable, this account records any VAT refunds received from other EU member states under the VAT MOSS scheme.

It's important to note that the specific structure of VAT accounts may vary depending on the individual business's needs and the requirements of the tax authorities in the relevant EU member states. Businesses using VAT MOSS should maintain accurate and detailed records of their digital services sales and purchases to ensure compliance with the scheme's reporting and record-keeping requirements. Consulting with a tax professional or advisor familiar with VAT MOSS and EU VAT regulations can help businesses set up the appropriate Chart of Accounts and ensure proper VAT compliance.

Created with the Standard Edition of HelpNDoc: Elevate Your Documentation with HelpNDoc's Project Analyzer Features

Destination-Based Taxes

What is Destination-Based Taxes?

Destination-based taxes refer to a taxation system in which the applicable tax rate is determined based on the location where goods or services are ultimately consumed or delivered, rather than the location of the seller or business. This approach ensures that the appropriate local or regional tax rate is applied to the

transaction, aligning with the principle that taxes should be paid in the jurisdiction where the economic activity occurs.

In a destination-based tax system, the tax amount is calculated based on the consumer's location, ensuring that the revenue generated from the tax benefits the local jurisdiction where the consumption takes place. This concept is particularly relevant in the context of cross-border or e-commerce transactions, where goods and services may be purchased from sellers located in different regions or countries.

Destination-based taxes are commonly associated with Value-Added Tax (VAT) and Goods and Services Tax (GST) systems, but similar principles can also be applied to other consumption-based taxes, such as sales tax, use tax, and excise tax. The goal is to ensure that tax revenue is collected and allocated fairly, reflecting the principle that the tax burden should be placed on the final consumer or user of the goods or services.

What is Destination-Based Sales Tax?

Destination-based sales tax refers to a type of sales tax system in which the tax rate is determined based on the location of the buyer or consumer rather than the location of the seller or business. In destination-based sales tax, the tax rate is determined by the location where the purchased goods or services are ultimately delivered or consumed.

This type of sales tax system is often used in jurisdictions with multiple local tax rates or where there are variations in tax rates based on different regions or localities. Destination-based sales tax helps ensure that the appropriate local tax rate is applied to the transaction, taking into account the specific jurisdiction where the consumer is located.

Here's how destination-based sales tax works:

1. Location Determination: The tax rate is determined based on the destination or delivery address provided by the buyer. This ensures that the correct local tax rate is applied.
2. Variable Tax Rates: Since different localities or regions may have varying sales tax rates, destination-based sales tax allows for the accurate calculation of the appropriate tax amount based on the buyer's location.
3. Complexity: Implementing destination-based sales tax can be complex, especially for businesses that sell goods or services across multiple jurisdictions with different tax rates. Businesses need to accurately calculate and apply the correct tax rate for each transaction.
4. E-commerce and Online Sales: Destination-based sales tax is particularly relevant for e-commerce and online sales, where businesses may have customers in various jurisdictions. It ensures that the appropriate sales tax is collected based on the buyer's location.

5. Local Jurisdiction Funding: Destination-based sales tax helps ensure that the revenue generated from the sales tax benefits the local jurisdictions where the goods are consumed, supporting local infrastructure and services.

It's important to note that the specifics of destination-based sales tax can vary depending on the jurisdiction and its tax laws. Some regions may use a destination-based system for certain types of transactions, while others may use an origin-based system (where the tax rate is based on the seller's location). As tax laws can change and vary, it's recommended to consult the relevant tax authorities or a tax professional for accurate and up-to-date information.

In which states in the US does Destination-based sales tax apply?

As of ChatGPT's last update in September 2021, destination-based sales tax applies in various states in the United States. However, it's important to note that tax laws and regulations can change over time, so it is recommended to verify the current tax policies with the respective state's tax authorities or to consulting a tax professional for the most up-to-date information. Here are some states where destination-based sales tax is commonly used:

1. Alabama
2. Colorado
3. Louisiana
4. Maine
5. Mississippi
6. New York
7. Ohio
8. Oklahoma
9. Pennsylvania
10. Tennessee

In these states, the sales tax rate is determined based on the location of the buyer or consumer, ensuring that the appropriate local tax rate is applied to the transaction. This is especially relevant for online and remote sales, as it helps allocate tax revenue to the jurisdictions where the goods are ultimately consumed.

Please keep in mind that this list may not be exhaustive, and there might be other states or jurisdictions that have also implemented destination-based sales tax systems. Always refer to official state tax authorities or consult with tax professionals for the most accurate and up-to-date information.

Is Destination-Based Sales Tax also applicable to other countries / jurisdictions?

The concept of destination-based sales tax or destination-based taxation is not limited to the United States; it can also apply to other countries and jurisdictions. The idea behind destination-based taxation is to ensure that the appropriate tax rate is applied based on where the goods or services are ultimately consumed or delivered, regardless of the location of the seller.

In many countries, especially those with decentralized tax systems or varying tax rates across regions, destination-based taxation helps allocate tax revenue to the local jurisdictions where consumption occurs. This approach is often used to address the challenges posed by e-commerce and online transactions, where goods and services can be sold to consumers in different regions or countries.

For example, some countries within the European Union (EU) have adopted destination-based taxation for value-added tax (VAT) on cross-border transactions among member states. Similarly, various countries around the world may implement destination-based taxation to ensure that tax revenue is collected by the jurisdiction where the end consumer resides.

The specific implementation of destination-based taxation can vary from one country to another, as each jurisdiction has its own tax laws, regulations, and administrative procedures. Businesses engaged in cross-border transactions should be aware of these variations and consult with local tax authorities or tax professionals to ensure compliance with destination-based tax requirements in the relevant jurisdictions.

In which countries is Destination-based taxation applicable?

Destination-based taxation, similar to destination-based sales tax, is implemented in various countries for value-added tax (VAT) and other indirect tax systems. Here are a few examples of countries where destination-based taxation principles are applied:

1. European Union (EU): Many EU countries use destination-based taxation for cross-border transactions among member states. VAT is collected at the rate of the destination country where the goods or services are consumed. This ensures that tax revenue is allocated to the jurisdiction where the final consumption occurs.
2. Australia: Australia applies the Goods and Services Tax (GST) with a destination-based approach. GST is collected on transactions based on the location of the consumer, ensuring that the appropriate tax rate is applied depending on where the goods or services are delivered.
3. Canada: Canada's federal Goods and Services Tax (GST) and Harmonized Sales Tax (HST) system also operate on a destination-based principle. The tax rate is determined based on the province or territory where the goods or services are received by the consumer.

4. New Zealand: New Zealand's Goods and Services Tax (GST) is destination-based. It is applied based on the location of the recipient, ensuring that tax is collected at the appropriate rate for the destination jurisdiction.
5. Japan: Japan applies consumption tax (similar to VAT) on a destination-based principle. The tax rate is determined based on the location of the consumer, ensuring that tax is collected at the rate applicable in the destination region.
6. South Korea: South Korea's value-added tax system is also destination-based. The tax rate is determined based on the location of the consumer, ensuring that tax revenue is allocated to the relevant jurisdiction.
7. India: India's Goods and Services Tax (GST) is a destination-based tax system. The tax is collected based on the location of the recipient, ensuring that tax revenue is allocated to the state where the consumption occurs.

These are just a few examples of countries that implement destination-based taxation principles in their VAT or GST systems. The specific details, rates, and regulations can vary widely among different countries, so it's essential to consult with local tax authorities or tax professionals in each jurisdiction to understand the applicable rules and requirements.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

---

What is Online Sales Tax and Online Purchase Tax?

"*Online Sales Tax*" and "*Online Purchase Tax*" are terms used to refer to the taxation of transactions involving goods or services conducted over the internet. Here's what each term typically means:

1. Online Sales Tax:
    - Online sales tax refers to the requirement for online retailers and e-commerce businesses to collect and remit sales tax on transactions conducted over the internet.
    - Prior to the "*Wayfair*" decision by the US Supreme Court in 2018, many online retailers were not required to collect sales tax from customers if they did not have a physical presence (such as a brick-and-mortar store) in the customer's state.
    - The "*Wayfair*" decision allowed states to impose sales tax obligations on remote sellers

(online retailers) based on their economic activity in the state, even if they lack a physical presence.

- As a result, online retailers may need to collect and remit sales tax on transactions made by customers located in states where the retailer exceeds certain sales or transaction thresholds.

2. Online Purchase Tax:

   - Online purchase tax can refer to the tax that customers are required to pay on their online purchases if the seller does not collect sales tax at the time of purchase.
   - Some online retailers may not automatically calculate and charge sales tax on transactions. In such cases, customers are often still legally obligated to pay the equivalent use tax directly to their state's tax authority.
   - Online purchase tax is essentially the same as use tax. It's the tax that a customer owes on a taxable purchase when the seller didn't charge them sales tax, typically because the seller doesn't have a tax obligation in the customer's state.

Both online sales tax and online purchase tax aim to ensure that online transactions are subject to the same taxation principles as traditional in-person transactions. It's important for individuals and businesses to be aware of their obligations regarding these taxes, as tax laws can vary by jurisdiction and are subject to change. If you have questions about your specific situation, consulting a tax professional or the relevant tax authority is recommended.

In which States in the US is this applicable?

As of ChatGPT's last update in September 2021, the application of online sales tax and online purchase tax (also known as use tax) varies by state in the US due to the "*Wayfair*" decision and individual state laws. The "*Wayfair*" decision allowed states to require online retailers to collect sales tax even if they don't have a physical presence in the state. Here are some key points:

Online Sales Tax Collection:

- Many states have enacted laws to require online retailers to collect sales tax if they meet certain economic thresholds in the state, such as a certain level of sales or transactions.
- The specifics of the thresholds and requirements vary by state.

Online Purchase Tax (Use Tax):

- Use tax is owed by consumers in many states if sales tax was not collected at the time of purchase, such as when buying from an out-of-state online retailer.
- Consumers are generally required to self-report and remit use tax on their state income tax returns.

Since tax laws can change, and the applicability of online sales tax and use tax can vary based on evolving state regulations, it's important to check with the relevant state's Department of Revenue or a tax professional for the most up-to-date information on which states have implemented these taxes and how they are enforced.

In which other countries (jurisdictions) is this applicable outside of the United States?

Outside of the United States, similar concepts to online sales tax and use tax exist in various forms in different countries. These concepts may have different names and structures depending on the jurisdiction. Here are a few examples:

European Union (EU): The EU has implemented Value Added Tax (VAT) regulations that apply to digital goods and services sold to consumers within the EU, regardless of the seller's location. This is often referred to as the "VAT on e-services" or "VAT MOSS" (Mini One Stop Shop) system.

Canada: Canada imposes the Goods and Services Tax (GST) and the Harmonized Sales Tax (HST) on digital products and services sold to Canadian consumers, regardless of the seller's location.

Australia: Australia has a Goods and Services Tax (GST) that applies to digital products and services imported by Australian consumers.

United Kingdom: The UK has implemented rules similar to the EU's VAT MOSS system for digital services provided to UK consumers.

South Africa: South Africa has implemented Value Added Tax (VAT) on electronic services provided to South African consumers, regardless of the supplier's location.

New Zealand: New Zealand has a Goods and Services Tax (GST) on remote services and digital products imported by New Zealand consumers.

These examples showcase that many countries have adapted their tax systems to address the taxation of digital products and online services. The specifics of the regulations, thresholds, and requirements can vary significantly from one jurisdiction to another. If you're doing business internationally or purchasing goods and services from abroad, it's important to understand the relevant tax laws and consult with tax professionals or local tax authorities to ensure compliance.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Sales tax and use tax in the USA

What is the difference between a sales tax and use tax in the USA?

In the USA, the main difference between a sales tax and a use tax lies in who is responsible for paying the tax and when it is collected. Although they both pertain to the taxation of goods and services, they are applied in different scenarios:

1. Sales Tax:
    - Sales tax is a tax imposed on the sale of tangible personal property and certain services.
    - The responsibility for collecting and remitting the sales tax lies with the seller.
    - The seller adds the sales tax to the total purchase price and collects it from the buyer at the time of the transaction.
    - The sales tax rate is based on the location of the seller and the buyer (destination-based or origin-based, depending on the state).
    - Sales tax is applicable to purchases made within the state where the seller has a physical presence or nexus.
    - The funds collected by the seller are remitted to the state's tax authority to fund public services and operations.
2. Use Tax:
    - Use tax is a tax imposed on the use, consumption, or storage of tangible personal property and certain services purchased from an out-of-state seller or from a seller who does not collect sales tax.
    - The responsibility for reporting and paying the use tax lies with the buyer or the consumer.
    - If the seller does not collect the sales tax at the time of the transaction, the buyer is required to self-assess and pay the use tax to their state's tax authority.
    - Use tax is applicable to purchases made from out-of-state sellers, online retailers without a physical presence in the buyer's state, or when purchases are made in a state with a lower sales tax rate and brought back to the buyer's home state.
    - The use tax rate is typically the same as the sales tax rate in the buyer's location.
    - The purpose of the use tax is to ensure that consumers and businesses pay the appropriate amount of tax on purchases, even if the seller is not required to collect the sales tax.

In summary, the key distinction between sales tax and use tax is based on who collects and remits the tax. Sales tax is collected and remitted by the seller at the time of the transaction, while use tax is reported and

paid by the buyer or consumer when sales tax is not collected by the seller. Both taxes aim to generate revenue for states and local jurisdictions and ensure the fair taxation of goods and services. It's essential for businesses and consumers to understand and comply with the relevant sales and use tax regulations in their respective states to avoid potential tax liabilities.

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Sales tax in the US

What is sales tax in the US?

Sales tax in the United States is a consumption tax imposed on the sale of tangible personal property and certain services. It is a tax collected by businesses from consumers at the point of purchase. The tax is then remitted to the appropriate state or local tax authority to fund public services and government operations.

Key points about sales tax in the US:

1. Collection Responsibility: Businesses that sell goods or taxable services are responsible for collecting sales tax from their customers. The seller adds the sales tax amount to the total purchase price, and the customer pays the combined total at the time of the transaction.
2. Rates and Jurisdiction: Sales tax rates can vary significantly depending on the state and local jurisdiction. Each state sets its own sales tax rate, and local governments such as cities, counties, and special districts may impose additional sales taxes, resulting in different combined tax rates.
3. Destination or Origin-Based: Sales tax can be destination-based or origin-based, depending on the state's rules. In destination-based states, the sales tax rate is based on the location where the buyer receives the goods or services. In origin-based states, the tax rate is based on the location of the seller.
4. Exemptions and Exclusions: Certain items may be exempt from sales tax, such as groceries, prescription drugs, and certain medical services. Additionally, some states exempt certain types of transactions, like sales to tax-exempt organizations.
5. Filing and Remittance: Businesses are required to file regular sales tax returns (monthly, quarterly, or annually) with the relevant tax authority, reporting the total sales made and the corresponding sales tax collected. The collected sales tax is then remitted to the state or local tax authority.
6. Use Tax: In situations where the seller does not collect sales tax (e.g., purchases from out-of-state online retailers), the buyer may be required to self-assess and pay a complementary tax called use tax,

ensuring that the appropriate tax is paid regardless of where the seller is located.

Sales tax is a crucial source of revenue for state and local governments and plays a significant role in funding public services like education, infrastructure, and public safety. Due to variations in sales tax rates and rules across states and localities, businesses often use automated sales tax software or consult with tax professionals to ensure compliance with the correct rates and regulations.

What is the Sales tax rates in the USA?

Sales tax rates in the USA vary significantly as they are imposed at the state and local levels, and there is no federal sales tax. Each state has the authority to set its own sales tax rate, and within a state, local jurisdictions like cities, counties, and municipalities can add their own additional sales taxes. As a result, the total sales tax rate can vary from one location to another.

As of ChatGPT's last update in September 2021, here are some general guidelines:

1. State Sales Tax Rates: State-level sales tax rates typically range from 2% to 7%, with some states having no sales tax at all. For example, states like Alaska, Delaware, Montana, New Hampshire, and Oregon do not have a statewide sales tax.
2. Local Sales Tax Rates: Local sales taxes can be imposed in addition to the state rate. These rates vary widely and can add an additional 0.1% to 5% or more to the total sales tax rate.
3. Special District Taxes: In certain areas, there may be additional special district taxes for specific purposes like transportation, tourism, or education. These rates are added on top of state and local sales taxes.

Since sales tax rates can change, it is essential to check with the state's Department of Revenue or the local tax authorities for the most up-to-date and accurate sales tax rates for a specific location.

Keep in mind that some states have destination-based sales tax, while others have origin-based sales tax. In destination-based states, the sales tax is based on the location where the buyer receives the goods or services, while in origin-based states, the tax is based on the location of the seller. This can affect the total sales tax a business must collect and remit.

Given the complexities and variations in sales tax rates, businesses often use automated sales tax calculation software or consult with tax professionals to ensure compliance with the correct rates for each transaction.

Is there a national Sales tax in the US?

As of ChatGPT's last update in September 2021, there is no national sales tax in the United States. The United States does not have a federal-level sales tax that applies uniformly across the entire country.

Instead, sales tax is imposed at the state and local levels.

Each state has the authority to set its own sales tax rate and rules, and the rates can vary significantly from one state to another. Additionally, some local jurisdictions within states may also impose their own sales tax, further adding to the complexity of sales tax regulations in the U.S.

Because of this decentralized system, the sales tax structure can be quite intricate, with different rates and rules for each state and even within different localities. Businesses that operate in multiple states need to be aware of the specific sales tax requirements in each jurisdiction where they conduct sales.

It's essential for businesses to consult with tax professionals or use automated tax software to ensure they are compliant with the varying sales tax rates and regulations across different states and localities in the U.S.

What is the Tax rates in the various States in the US?

As of ChatGPT's last update in September 2021, sales tax rates in the United States can vary significantly from state to state. Additionally, local jurisdictions within each state may impose additional sales taxes, further affecting the total tax rate. Please note that sales tax rates can change over time, and it's essential to check with the respective state's Department of Revenue or tax authority for the most up-to-date rates. Below are the general ranges of state-level sales tax rates as of 2021:

Lowest State Sales Tax Rates:

- Alaska: 0% (Alaska has no statewide sales tax, but some local jurisdictions may impose a local sales tax.)
- Delaware: 0% (Delaware does not have a state sales tax.)

States with Moderate State Sales Tax Rates:

- Hawaii: 4.00%
- Wyoming: 4.00%
- Wisconsin: 5.00%
- Maine: 5.50%
- Virginia: 5.30%
- Vermont: 6.00%
- Utah: 4.85%
- South Dakota: 4.50%

- North Dakota: 5.00%
- Connecticut (CT): 6.35%

States with Higher State Sales Tax Rates:

- Tennessee: 7.00%
- Arkansas: 6.50%
- Louisiana (LA): 4.45%
- Arizona: 5.60%
- Alabama (AL): 4.00% -
- Mississippi (MS): 7.00%
- Oklahoma: 4.50%
- Washington: 6.50%
- California: 7.25%
- New York: 4.00%
- Illinois: 6.25%
- Maryland: 6.00%
- Pennsylvania: 6.00%
- Massachusetts: 6.25%

Please remember that the list above is not exhaustive, and sales tax rates in each state can vary based on the specific local jurisdictions and the types of goods and services subject to sales tax. Additionally, there are some variations in how states administer and apply sales tax, such as destination-based or origin-based sourcing, which can affect the total tax rate. Always refer to official sources or consult with a tax professional for the most current and accurate sales tax rates in a particular state.

BOOKS CATEGORIZED BY STATES SALES TAX

STATES WITH 0% SALES TAX AND IN COUNTIES AND CITIES

No Sales Taxes with 0,00% are collected by the Counties for the following states.

No Tax Accounts are set for the following Sets of Books:

	State	Sales Tax	County Tax	City Tax	Set of Books
	Delaware (DE)	0.00%	0.00%	0.00%	
	Montana (MT)	0.00%	0.00%	0.00%	
	New Hampshire (NH)	0.00%	0.00%	0.00%	
	Oregon (OR)	0.00%	0.00%	0.00%	

STATES WITH SALES TAX - NO SALES TAX IN COUNTIES AND CITIES

	State	Sales Tax	County Tax	City Tax	*Set of Books - (Not yet updated)
	Indiana (IN)	7.00%	0.00%	0.00%	
	Kentucky (KY)	6.00%	0.00%	0.00%	
	Massachusetts (MA)	6,25%	0.00%	0.00%	
	Michigan (MI)	6.00%	0.00%	0.00%	
	Maine (ME)	5.50%	0.00%	0.00%	
	Maryland (MD)	6.00%	0.00%	0.00%	

	Rhode Island (RI)	7.00%	0.00%	0.00%

In these states, the sales tax rate specified is the total combined rate that applies to retail sales throughout the entire state. This means that there are no additional local sales taxes imposed by counties or cities within these states. The statewide sales tax rate is the only rate that applies uniformly across all jurisdictions within the state.

It's important to note that while these states do not have additional local sales taxes, some specific products or services might be exempt from sales tax or subject to a reduced rate. Additionally, sales tax rates and regulations can change over time, so it's always best to verify the current rates with the respective state's tax authority for the most up-to-date information.

STATES WITH NO SALES TAX - ONLY IN COUNTIES AND CITIES

	State	Sales Tax	County Tax	City Tax	Set of Books - (Not yet updated)
	Alaska (AK)	0.00%	3.00%	4,50%	

STATES WITH SALES TAX - IN COUNTIES AND CITIES

	State	Sales Tax	County Tax	City Tax	Set of Books - (Not yet updated)
	Alabama (AL)	4.00%	4.000 - 11.000%		
	Arizona (AZ)	5.60%	5.850 - 11.200%		
	Arkansas (AR)	6.50%	6.500 - 11.625%		
	California (CA)	7.25%	7.250 - 10.250%		

	Colorado (CO)	*2.90%*	*2.900 - 11.200%*	
	Connecticut (CT)	*6.35%*	*6.350 - 6.990%*	
	Florida (FL)	*6.00%*	*6.000 - 8.500%*	
	Georgia (GA)	*4.00%*	*4.000 - 8.000%*	
	Hawaii (HI)	*4.00%*	*4.000 - 4.500%*	*General Excise Tax (GET) is a similar system to Sales tax in Hawaii*
	Idaho (ID)	*6.00%*	*6.000 - 8.500%*	
	Illinois (IL)	*6.25%*	*6.250 - 11.000%*	
	Iowa (IA)	*6.00%*	*6.000 - 7.000%*	
	Kansas (KS)	*6.50%*	*6.500 - 10.500%*	
	Louisiana (LA)	*4.45%*	*5.000 - 11.450%*	
	Mississippi (MS)	*7.00%*	*7.000 - 8.000%*	
	Missouri (MO)	*4.225%*	*4.225 - 5.763%*	

	Nebraska (NE)	5.50%	5.500 - 7.500%
	New York (NY)	4.00%	4.000% - 8.875%
	North Carolina (NC)	4.75%	6.750 - 7.500%
	North Dakota (ND)	5.00%	5.000 - 8.500%
	Ohio (OH)	5.75%	6.500 - 8.000%
	Oklahoma (OK)	4.50%	4.500-11.500%
	Pennsylvania (PA)	6.00%	6.000 - 8.000%
	South Carolina (SC)	6.00%	6.000 - 9.000%
	South Dakota (SD)	4.50%	4.500 - 6.500%
	Tennessee (TN)	7.00%	8.500 - 9.750%
	Texas (TX)	6.25%	6.250 - 8.250%
	Utah (UT)	4.85%	5.950 - 8.600%
	Vermont (VT)	6.00%	6.000 - 7.000%

	Virginia (VA)	*5.30%*	*5.300 - 6.000%*
	Washington (WA)	*6.50%*	*7.000 - 10.400%*
	West Virginia (WV)	*6.00%*	*6.000 - 7.000%*
	Wisconsin (WI)	*5.00%*	*5.000 - 5.600%*
	Wyoming (WY)	*4.00%*	*4.000 - 6.000%*

What blocks or fields appears on the Sales tax return in USA?

In the United States, the specific blocks or fields that appear on a Sales Tax return can vary depending on the state in which the business operates. Each state has its own rules and regulations regarding sales tax, and the format of the Sales Tax return can differ from one state to another.

However, in general, a typical Sales Tax return in the USA might include the following blocks or fields:

1. Business Information: This section requires details about the business, such as its legal name, address, Employer Identification Number (EIN), or Taxpayer Identification Number (TIN).
2. Sales Information: Here, you will report the total amount of sales made during the reporting period, broken down by taxable and non-taxable sales.
3. Tax Collected: This field will ask you to report the total amount of sales tax collected from customers during the reporting period.
4. Exemptions: If your business made sales that were exempt from sales tax (e.g., certain types of products or sales to tax-exempt organizations), you would report those here.
5. Credits and Deductions: This section allows businesses to claim any credits or deductions that are applicable to their sales tax liability. These could include timely filing discounts, bad debt deductions, or other eligible credits.
6. Local Taxes: In some states, there may be additional local sales taxes imposed by cities or counties. Businesses may need to report these separately.
7. Payment Information: This section requires you to specify the payment method and any

accompanying payment details.

8. Signature and Certification: The return is typically required to be signed and certified by an authorized representative of the business.

It's important to note that the above information is a general outline, and the actual Sales Tax return for a specific state may have additional fields or may be structured differently. As sales tax regulations can change, businesses should always consult the specific state's Department of Revenue or tax authority for the most up-to-date and accurate information.

How does the blocks or fields on the Sales Tax return tie up with the Chart of Accounts in USA?

The blocks or fields on the Sales Tax return in the USA should align with the corresponding accounts in the Chart of Accounts of the business. The purpose of the Sales Tax return is to report the sales and sales tax collected during a specific reporting period accurately. This data needs to be reflected in the company's financial records, and the Chart of Accounts is where these transactions are recorded.

Let's see how the blocks or fields on the Sales Tax return tie up with the Chart of Accounts:

1. Sales Information (Sales Revenue): The total amount of taxable sales reported in the Sales Information section of the Sales Tax return should be reflected in the "Sales *Revenue*" account in the Chart of Accounts.

2. Tax Collected (Sales Tax Payable): The total amount of sales tax collected from customers, as reported in the Tax Collected section of the Sales Tax return, should be recorded in the "*Sales Tax Payable*" account in the Chart of Accounts. This account represents the liability the business owes to the taxing authority for the collected sales tax.

3. Exemptions and Exclusions: If any sales were exempt from sales tax or excluded from the taxable amount, these transactions should be adjusted in the Chart of Accounts accordingly. For example, if sales to tax-exempt organizations were excluded, you might create a separate account for "*Exempt Sales*" in the Chart of Accounts.

4. Credits and Deductions: Any credits or deductions applicable to the sales tax liability should be considered in the Chart of Accounts. For example, if there are timely filing discounts or other deductions, specific accounts can be created to track these adjustments.

5. Local Taxes: If there are additional local sales taxes imposed by cities or counties, these should be separately recorded in the Chart of Accounts. You may create accounts for "Local Sales Tax Payable" to differentiate these amounts from state-level sales tax.

It's crucial to maintain consistency between the Sales Tax return and the Chart of Accounts to ensure

accurate financial reporting and compliance. Regular reconciliations should be performed to verify that the sales tax collected aligns with the Sales Tax return filed and the corresponding entries in the Chart of Accounts. This will help identify any discrepancies or errors that need to be addressed promptly. A well-maintained Chart of Accounts ensures that financial data, including sales tax information, is accurately recorded, organized, and easily accessible for reporting and decision-making purposes.

Does each state have its own Sales Tax return?

Yes, each state in the United States has its own Sales Tax return. Sales tax is a state-level tax, and each state has its own set of rules, regulations, and procedures for collecting and remitting sales tax.

When a business makes sales within a state that imposes a sales tax, it is generally required to collect the appropriate sales tax from the customers and then remit it to the state's tax authority. To facilitate this process, businesses must file a Sales Tax return with the state's Department of Revenue or the equivalent tax authority. The Sales Tax return is typically filed on a regular basis, such as monthly, quarterly, or annually, depending on the state's requirements and the volume of sales.

The Sales Tax return contains information about the total sales made by the business during the reporting period, the sales tax collected from customers, any exemptions or deductions claimed, and other relevant details. It serves as a formal record of the business's sales tax liability and allows the state to reconcile the tax collected by the business.

Since sales tax rules can vary significantly from one state to another, it's essential for businesses to understand and comply with the specific requirements of each state where they have sales or operate. This may include registering for a sales tax permit in each state, charging the correct sales tax rate based on the location of the buyer, and filing the corresponding Sales Tax returns accurately and on time. It is advisable for businesses to seek professional tax advice or use automated tax software to ensure compliance with the diverse and evolving sales tax regulations across states.

In the US a State may have Sales tax and local Sales tax may also be applicable to some local authorities?

Yes, that's correct. In the United States, a state may impose a statewide sales tax, and in addition to that, local sales taxes may also be applicable in certain local jurisdictions. This results in a combined sales tax rate, which includes both the state sales tax rate and any applicable local sales tax rates.

Here's how it works:

1. State Sales Tax: Each state has the authority to levy its own sales tax rate, which is applicable throughout the entire state. State sales tax rates typically range from 2% to 7% but can vary widely depending on the state. As mentioned earlier, some states do not impose a state-level sales tax at all.

2. Local Sales Tax: In many areas, local jurisdictions such as cities, counties, municipalities, and special districts have the option to impose additional sales taxes on top of the state sales tax. These local sales taxes are usually used to fund specific local projects, services, or initiatives.

3. Combined Sales Tax Rate: The combined sales tax rate is the total tax rate that consumers pay when making a purchase in a specific location. It is the sum of the state sales tax rate and any applicable local sales tax rates.

For example, if a state has a 5% sales tax rate and a city within that state imposes an additional 2% local sales tax rate, then the combined sales tax rate in that city would be 7%. This means that for every dollar of taxable purchase, the consumer would pay an additional 7 cents in sales tax.

The presence of local sales taxes adds complexity to sales tax compliance for businesses, as the total tax rate can vary from one location to another even within the same state. Businesses that operate in multiple jurisdictions need to be aware of the specific sales tax rates in each location where they make sales, collect the correct amount of sales tax from customers, and file accurate Sales Tax returns with the appropriate state and local tax authorities. Automated sales tax software or tax professionals can be helpful in managing these complexities and ensuring compliance with the various tax rates.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

---

Delaware (DE) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Delaware:

1. No Sales Tax: Delaware does not have a statewide sales tax. This means there is no sales tax imposed on goods or services sold within the state. As a result, retail purchases in Delaware are generally tax-free at the state level.

2. No Use Tax: Similarly, Delaware does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In Delaware, there is no use tax applicable to such transactions.

3. Corporate Income Tax: Delaware is known for its favorable business climate and attracts many corporations due to its corporate-friendly tax laws. The state imposes a corporate income tax on corporations doing business in Delaware.

4. Franchise Tax: Delaware imposes an annual franchise tax on corporations incorporated in the state.

The franchise tax amount is based on the corporation's authorized shares or the number of issued shares and their par value.

5. Personal Income Tax: Delaware levies a personal income tax on individuals residing in the state. The income tax rates are graduated, meaning that higher income levels are subject to higher tax rates.
6. Property Taxes: Delaware imposes property taxes on real property, such as land and buildings. Property tax rates vary by county and are levied by the local governments.
7. Limited Business Taxation: Besides the corporate income tax, Delaware does not impose a state-level sales tax, gross receipts tax, or inventory tax, making it attractive to businesses.
8. Estate Tax: Delaware does not have its own estate tax. However, it does have a "pick-up" tax, which means that it can collect a portion of the federal estate tax paid by the estate.
9. Tax-Friendly Trust Laws: Delaware is known for its trust-friendly laws, making it a popular state for establishing trusts.
10. No Vehicle Sales Tax: Delaware does not impose a sales tax on vehicle purchases, making it a tax-free state for buying cars.

It's important to note that tax laws are subject to change, and it's recommended to consult the Delaware Division of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Delaware.

Delaware (DE) - Sales Tax

As of ChatGPT's last update in September 2021, Delaware (DE) is one of the few states in the United States that does not have a statewide sales tax or use tax.

Delaware is known for its business-friendly environment, and one of the factors contributing to this reputation is its lack of a sales tax. This means that there is no sales tax imposed on the retail sale of goods or services within the state, making it an attractive destination for shopping and conducting business.

Additionally, Delaware does not have a use tax, which means there is no tax imposed on items purchased from out-of-state retailers for use, storage, or consumption within the state.

While Delaware does not have a statewide sales or use tax, it's important to note that other taxes, such as income taxes, property taxes, and gross receipts taxes, may still apply to businesses and individuals in the state.

As tax laws can change over time, I recommend checking with the Delaware Division of Revenue or consulting with a tax professional for the most current and accurate information on Delaware's tax policies and obligations.

Delaware (DE) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Delaware does not impose a statewide sales tax or use tax. This makes Delaware one of the few states in the United States that does not have a sales tax at the state level.

Sales Tax: Delaware has no statewide sales tax on goods or services sold within the state. Therefore, there is no state sales tax rate to be applied to retail purchases. This tax-free status is often promoted by the state, and it makes Delaware a popular destination for shoppers seeking tax-free purchases.

Use Tax: Similarly, Delaware does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In Delaware, since there is no state sales tax, there is no use tax applicable to such transactions.

Local Taxes: While Delaware does not have a state-level sales or use tax, it's important to note that some local jurisdictions in Delaware may impose certain local taxes, such as property taxes. However, these local taxes are distinct from sales and use taxes and are not applicable to retail transactions.

Overall, the absence of a state sales tax and use tax in Delaware simplifies the tax structure for businesses and consumers within the state. It's essential to be aware of any local taxes that may apply to specific business activities or property ownership in certain areas of the state.

Please note that tax laws are subject to change, and it's essential to consult the Delaware Division of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Delaware.

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

Sales tax / Use tax - Montana (MT)

Montana (MT) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Montana:

1. No Sales Tax: Montana does not have a statewide sales tax. This means there is no sales tax imposed on goods or services sold within the state. As a result, retail purchases in Montana are generally tax-free at the state level.
2. No Use Tax: Similarly, Montana does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's

sales tax. In Montana, there is no use tax applicable to such transactions.

3. Individual Income Tax: Montana imposes an individual income tax on residents and non-residents who earn income in the state. The state has multiple tax brackets with varying tax rates based on income levels.
4. Corporate Income Tax: Montana levies a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
5. Property Taxes: Montana imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and vary by county.
6. Gasoline Tax: Montana imposes a gasoline tax on fuel purchases, which contributes to funding road and transportation infrastructure.
7. Lodging Facility Use Tax: Montana imposes a lodging facility use tax on accommodations provided by hotels, motels, and other lodging establishments.
8. Estate Tax: Montana does not have its own estate tax. However, it does have a "pick-up" tax, which means that it can collect a portion of the federal estate tax paid by the estate.
9. No Vehicle Sales Tax: Montana does not impose a sales tax on vehicle purchases, making it a tax-free state for buying cars.
10. Local Option Taxes: While Montana does not have a statewide sales tax, some local jurisdictions in the state may impose certain local taxes, such as resort taxes or local option taxes. These local taxes are distinct from sales and use taxes and are limited in scope.

It's important to note that tax laws are subject to change, and it's recommended to consult the Montana Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Montana.

Montana (MT) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Montana (MT) is another state in the United States that does not have a statewide sales tax or use tax. This means that there is no sales tax imposed on the retail sale of goods or services, and there is no use tax on items purchased for use, storage, or consumption in the state.

Montana's lack of a statewide sales tax is notable and contributes to the state's reputation for being tax-friendly for consumers and businesses. As a result, there is no need for businesses to collect sales tax from customers or for residents to pay sales tax on their purchases within the state.

It's important to note that while Montana does not have a statewide sales tax, it does have other taxes and fees, such as property taxes and income taxes. Additionally, some local jurisdictions within the state may

impose certain local taxes or fees on specific items or services, but there is no statewide sales or use tax.

As tax laws and regulations can change over time, I recommend checking with the Montana Department of Revenue or consulting with a tax professional for the most current and accurate information on Montana's tax policies.

Montana (MT) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Montana does not impose a statewide sales tax or use tax. This makes Montana one of the states in the United States that does not have a general sales tax at the state level.

Sales Tax: Montana has no statewide sales tax on goods or services sold within the state. Therefore, there is no state sales tax rate to be applied to retail purchases. This tax-free status is often promoted by the state, and it makes Montana a popular destination for shoppers seeking tax-free purchases.

Use Tax: Similarly, Montana does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In Montana, since there is no state sales tax, there is no use tax applicable to such transactions.

Local Taxes: While Montana does not have a state-level sales or use tax, it's important to note that some local jurisdictions in Montana may impose certain local taxes, such as resort taxes or local option taxes. However, these local taxes are distinct from sales and use taxes and are typically limited in scope.

Overall, the absence of a state sales tax and use tax in Montana simplifies the tax structure for businesses and consumers within the state. It's essential to be aware of any local taxes that may apply to specific business activities or property ownership in certain areas of the state.

Please note that tax laws are subject to change, and it's essential to consult the Montana Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Montana.

Montana - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Montana does not have a statewide sales tax or any special sales tax rates. The state of Montana does not impose a general sales tax on goods or services sold within its borders. Therefore, there are no special sales tax rates in addition to the standard state sales tax rate because there is no state sales tax applied to retail purchases.

Montana is known for being one of the states in the United States with no general sales tax, making it a popular destination for shoppers seeking tax-free purchases. There are no variations in the sales tax rate based on the type of goods or services purchased, the location of the transaction, or any other factors.

Additionally, Montana does not have a use tax, which is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. Since there is no sales tax in Montana, there is no corresponding use tax applicable to such transactions.

It's important to note that while Montana does not have a sales tax, the state may still have other types of taxes, such as property taxes and business taxes, which are unrelated to sales tax.

For the most current and accurate information regarding taxes in Montana, including any potential local taxes or other tax obligations, it's recommended to consult the Montana Department of Revenue or a tax professional. They can provide the latest information on tax regulations and requirements in Montana.

Montana Taxes - Key points

As of March 23, 2023, the information on Montana taxes indicates that Montana does not have a general-use sales tax. This means there is no statewide sales tax on goods or services sold within the state.

Here are some key points regarding Montana taxes:

Montana Businesses Purchasing Goods for Resale:

- If you are a Montana business purchasing goods for resale, you can use the Montana Business Registry Resale Certificate when making purchases from out-of-state vendors.
- The completed resale certificate can be given to the vendor, and they may accept it as a substitute "resale certificate," exempting the transaction from the state's sales, use, or transaction tax. However, the vendor is not required to accept it.
- Some states, including Washington, may have their state-specific form or additional requirements for resale certificates.

Montana Residents Shopping in Another State:

- Montana residents working or shopping in a state with a sales tax should contact that state's Department of Revenue to learn about their rules for exempting non-residents from the tax.
- Montana residents cannot claim another state's sales tax on their Montana income tax return.

The Wayfair Decision and Online Sales Tax:

- The US Supreme Court's Wayfair decision allows states to collect sales tax from taxpayers located outside the state if there is a sufficient connection between the taxpayer and the state.
- The Wayfair decision does not affect Montana's purchasing goods or services online because Montana does not have a general sales tax.

- Montana's do not generally owe sales tax to another state, but exceptions may exist for other taxes (e.g., federal taxes on airline tickets, state and local taxes on hotel or rental car bookings).
- Montana businesses selling products online to buyers in states with sales tax requirements, such as South Dakota, may need to collect and remit sales taxes for those states.

Overall, Montana's tax system is unique in that it does not impose a general sales tax. It's essential for Montana businesses and residents to be aware of their tax obligations when dealing with other states that have sales tax requirements, especially when making online sales to customers in those states. For specific tax advice and compliance information, it's recommended to consult a tax professional.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Sales tax / Use tax - New Hampshire (NH)

New Hampshire (NH) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in New Hampshire:

1. No Sales Tax: New Hampshire does not have a statewide sales tax. This means there is no sales tax imposed on goods or services sold within the state. As a result, retail purchases in New Hampshire are generally tax-free at the state level.
2. No Use Tax: Similarly, New Hampshire does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In New Hampshire, there is no use tax applicable to such transactions.
3. No Individual Income Tax: New Hampshire is one of the few states that do not impose an individual income tax on wages and salaries. However, it does tax interest and dividends earned by residents at a flat rate.
4. No General Corporate Income Tax: New Hampshire does not have a general corporate income tax on profits earned by corporations. However, it does impose a Business Profits Tax (BPT) and a Business Enterprise Tax (BET) on certain businesses.
5. Property Taxes: New Hampshire imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and vary by municipality.
6. Meals and Rooms Tax: New Hampshire imposes a Meals and Rooms Tax on prepared meals,

beverages, and accommodations provided by hotels, restaurants, and other establishments.

7. No Estate Tax: New Hampshire does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
8. No Vehicle Sales Tax: New Hampshire does not impose a sales tax on vehicle purchases, making it a tax-free state for buying cars.
9. Keno Tax: New Hampshire has a tax on Keno, a type of lottery game.
10. Local Taxes: While New Hampshire does not have a broad-based state sales tax, some local jurisdictions in the state may impose certain local taxes or fees.

It's important to note that tax laws are subject to change, and it's recommended to consult the New Hampshire Department of Revenue Administration or a tax professional for the most up-to-date and specific information related to taxes in New Hampshire.

New Hampshire (NH) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, New Hampshire (NH) is another state in the United States that does not have a statewide sales tax or use tax. This means that there is no sales tax imposed on the retail sale of goods or services, and there is no use tax on items purchased for use, storage, or consumption in the state.

Like Oregon, New Hampshire's lack of a statewide sales tax is notable and contributes to the state's reputation for being tax-friendly for consumers and businesses. This can be advantageous for both residents and visitors, as they are not required to pay additional sales tax on most purchases made within the state.

It's important to note that while New Hampshire does not have a statewide sales tax, it does have other taxes and fees, such as property taxes and business taxes. Additionally, some local jurisdictions within the state may impose local taxes on specific items or services, such as meals and rooms taxes in certain areas.

As tax laws and regulations can change over time, I recommend checking with the New Hampshire Department of Revenue Administration or consulting with a tax professional for the most current and accurate information on New Hampshire's tax policies.

New Hampshire (NH) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, New Hampshire does not impose a statewide sales tax or use tax. This makes New Hampshire one of the states in the United States that does not have a sales tax at the state level.

Sales Tax: New Hampshire has no statewide sales tax on goods or services sold within the state.

Therefore, there is no state sales tax rate to be applied to retail purchases. This tax-free status is often promoted by the state, and it makes New Hampshire a popular destination for shoppers seeking tax-free purchases.

Use Tax: Similarly, New Hampshire does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In New Hampshire, since there is no state sales tax, there is no use tax applicable to such transactions.

Local Taxes: While New Hampshire does not have a state-level sales or use tax, it's important to note that some local jurisdictions in New Hampshire may impose certain local taxes, such as property taxes. However, these local taxes are distinct from sales and use taxes and are not applicable to retail transactions.

Overall, the absence of a state sales tax and use tax in New Hampshire simplifies the tax structure for businesses and consumers within the state. It's essential to be aware of any local taxes that may apply to specific business activities or property ownership in certain areas of the state.

Please note that tax laws are subject to change, and it's essential to consult the New Hampshire Department of Revenue Administration or a tax professional for the most up-to-date and specific information related to taxes in New Hampshire.

New Hampshire - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, New Hampshire does not have a statewide sales tax or any special sales tax rates. The state of New Hampshire does not impose a sales tax on goods or services sold within its borders. As a result, there is no state sales tax rate to be applied to retail purchases.

New Hampshire is known for being one of the states in the United States with no general sales tax, making it a popular destination for shoppers seeking tax-free purchases. There are no variations in the sales tax rate based on the type of goods or services purchased, the location of the transaction, or any other factors.

Additionally, New Hampshire does not have a use tax, which is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. Since there is no sales tax in New Hampshire, there is no corresponding use tax applicable to such transactions.

It's important to note that while New Hampshire does not have a sales tax, the state may still have other types of taxes, such as property taxes and business taxes, which are unrelated to sales tax.

For the most current and accurate information regarding taxes in New Hampshire, including any potential local taxes or other tax obligations, it's recommended to consult the New Hampshire Department of Revenue Administration or a tax professional. They can provide the latest information on tax regulations

and requirements in New Hampshire.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Sales tax / Use tax - Oregon (OR)

Oregon (OR) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Oregon:

1. No Sales Tax: Oregon does not have a statewide sales tax. This means there is no sales tax imposed on goods or services sold within the state. As a result, retail purchases in Oregon are generally tax-free at the state level.
2. No Use Tax: Similarly, Oregon does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In Oregon, there is no use tax applicable to such transactions.
3. Individual Income Tax: Oregon levies an individual income tax on residents and non-residents who earn income in the state. The state has multiple tax brackets with varying tax rates based on income levels.
4. Corporate Income Tax: Oregon imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
5. Property Taxes: Oregon imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and vary by county.
6. Excise Taxes: Oregon imposes excise taxes on certain products, such as alcohol, tobacco, and gasoline.
7. Estate Tax: Oregon has an estate tax that applies to estates with a value above a certain threshold. The tax rates are progressive, and the estate tax is separate from the federal estate tax.
8. No Vehicle Sales Tax: Oregon does not impose a sales tax on vehicle purchases, making it a tax-free state for buying cars.
9. Marijuana Tax: Oregon imposes a tax on the sale of recreational marijuana products.
10. No Local Option Taxes: Oregon does not have local option sales taxes, allowing for a uniform tax structure throughout the state.

It's important to note that tax laws are subject to change, and it's recommended to consult the Oregon

Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Oregon.

Oregon (OR) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Oregon (OR) is one of the few states in the United States that does not have a statewide sales tax or use tax. This means that there is no sales tax imposed on the retail sale of goods or services, and there is no use tax on items purchased for use, storage, or consumption in the state.

The absence of a sales tax in Oregon is a unique aspect of its tax system compared to most other states. This is often highlighted as one of the reasons why Oregon has a reputation for being a tax-friendly state, particularly for consumers and businesses who are not required to factor in sales tax when making purchases or sales.

However, it's important to note that there may be other taxes and fees applicable in Oregon, such as income taxes, property taxes, and certain local taxes. It's advisable to check with the Oregon Department of Revenue or consult with a tax professional for the most up-to-date information on Oregon's tax laws and regulations.

Oregon (OR) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Oregon does not impose a statewide sales tax or use tax. This makes Oregon one of the few states in the United States that does not have a sales tax at the state level.

Sales Tax: Oregon has no statewide sales tax on goods or services sold within the state. As a result, there is no state sales tax rate to be applied to retail purchases, making Oregon a popular destination for shoppers seeking tax-free purchases.

Use Tax: Similarly, Oregon does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In Oregon, since there is no state sales tax, there is no use tax applicable to such transactions.

Local Taxes: While Oregon does not have a state-level sales or use tax, it's important to note that some local jurisdictions in Oregon may impose certain local taxes, such as business taxes or property taxes. However, these local taxes are distinct from sales and use taxes and are not applicable to retail transactions.

Overall, the absence of a state sales tax and use tax in Oregon simplifies the tax structure for businesses and consumers within the state. However, it's important to be aware of any local taxes that may apply to specific business activities or property ownership in certain areas of the state.

Please note that tax laws are subject to change, and it's essential to consult the Oregon Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Oregon.

Oregon - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Oregon does not have a statewide sales tax, and therefore, there are no special sales tax rates in addition to the standard state sales tax rate because there is no state sales tax applied to goods or services sold within Oregon.

Oregon is one of the few states in the United States that does not impose a sales tax at the state level. As a result, there are no variations in the sales tax rate based on the type of goods or services purchased, the location of the transaction, or any other factors. Retail purchases in Oregon are generally tax-free at the state level.

However, it's important to note that some local jurisdictions in Oregon may impose certain local taxes, such as business taxes or property taxes. These local taxes are distinct from sales taxes and are not applicable to retail transactions.

Since there is no state sales tax in Oregon, there are no state sales tax exemptions or special sales tax rates to consider. Retailers and consumers in Oregon do not need to calculate or collect sales tax on their transactions.

It's essential to be aware of the specific tax regulations and requirements in Oregon, particularly related to local taxes, business taxes, and property taxes. For the most current and accurate information regarding taxes in Oregon, it's recommended to consult the Oregon Department of Revenue or a tax professional. They can provide the latest information on local taxes and any specific regulations that may be applicable in Oregon.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Output with HelpNDoc's Advanced Project Analyzer

Sales tax / Use tax - Alabama (AL)

Alabama (AL) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Alabama:

1. Sales Tax: Alabama imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4%, but some local jurisdictions may also impose

additional sales taxes, which can result in varying total sales tax rates in different areas of the state.

2. Use Tax: Alabama also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Alabama for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Alabama imposes an individual income tax on residents and non-residents who earn income in the state. The state has multiple tax brackets with varying tax rates based on income levels.
4. Corporate Income Tax: Alabama imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
5. Franchise Tax: Alabama imposes a franchise tax on corporations doing business in the state. The franchise tax rates vary depending on the corporation's net worth or capital value.
6. Property Taxes: Alabama imposes property taxes on real and tangible personal property, such as land, buildings, and vehicles. Property tax rates are determined at the local level and can vary by county.
7. Motor Vehicle Taxes and Fees: Alabama imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, annual registration fees, and "*ad valorem*" taxes based on the vehicle's value.
8. Excise Taxes: Alabama imposes excise taxes on certain products, such as alcohol, tobacco, and gasoline.
9. Simplified Sellers Use Tax (SSUT): Alabama offers a program called Simplified Sellers Use Tax for qualifying remote sellers. It allows certain out-of-state sellers to collect and remit a flat 8% sales tax on their Alabama sales in lieu of the varying local sales tax rates.
10. Local Taxes: In addition to the state-level taxes, some local jurisdictions in Alabama may impose additional taxes, such as local option sales taxes and occupational taxes.
11. Estate Tax: Alabama does not have its own estate tax, but it conforms to the federal estate tax laws.

It's important to note that tax laws are subject to change, and it's recommended to consult the Alabama Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Alabama.

Alabama (AL) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Alabama imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Alabama Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Alabama is 4%. Additionally, some counties and municipalities may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 4% to 11% or higher, depending on the location.
2. Exemptions: Some items and services may be exempt from Alabama's sales tax. Common exemptions include prescription drugs, groceries, medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Alabama's sales tax are required to register with the Alabama Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Alabama has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Alabama is the same as the sales tax rate, which is 4%. The use tax is applicable when residents or businesses in Alabama purchase taxable items from out-of-state sellers who do not collect Alabama sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Alabama are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Alabama is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Alabama Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Alabama.

Alabama- Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Alabama does not have any special sales tax rates in

addition to the standard state sales tax rate. The state sales tax rate in Alabama is 4%, and this rate applies uniformly to most taxable transactions throughout the state.

However, Alabama does allow counties and municipalities to impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. These local sales taxes are known as county and city sales taxes, and they are in addition to the state sales tax.

The combined state and local sales tax rates can vary from 4% to 11% or higher, depending on the specific county and city where the taxable transaction occurs. Each county and city in Alabama has the authority to set its own local sales tax rate, and the rate may differ even within the same county.

Local sales tax revenues are used to fund various local government initiatives, such as infrastructure projects, public services, and community development. It's essential to be aware of the specific tax rates applicable in your area and for the goods or services you are buying or selling.

For the most current and accurate information regarding Alabama's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Alabama Department of Revenue or a tax professional. They can provide the latest information on local sales tax rates and any specific local taxes or exemptions that may be applicable in Alabama.

Alabama - Sales Tax and Use Tax in local jurisdictions

As of ChatGPT's last update in September 2021, Alabama imposes both a state sales tax and allows local jurisdictions to levy additional sales taxes. This means that the combined sales tax rate can vary depending on the specific county and municipality where the taxable transaction occurs.

State Sales Tax: The state sales tax rate in Alabama is 4%. The state sales tax is applicable to most taxable transactions throughout the state on goods and certain services, subject to exemptions.

Local Sales Tax: In addition to the state sales tax, local jurisdictions in Alabama have the authority to impose their own local sales taxes. These local sales taxes are often referred to as city and county sales taxes. The rates and applicability of local sales taxes can vary depending on the specific county and city or town where the transaction takes place.

Local sales tax rates can range from 0% to 7.5% or higher, depending on the location. Each county and municipality has the discretion to set its own local sales tax rate or choose not to impose one at all.

Use Tax: As for use tax, Alabama applies the same rate as the sales tax rate, which is 4%. The use tax is applicable when residents or businesses in Alabama purchase taxable items from out-of-state sellers who do not collect Alabama sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.

It's essential to be aware of the specific sales tax rates applicable in your area and for the goods or

services you are buying or selling. For the most current and accurate information regarding Alabama's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Alabama Department of Revenue or a tax professional. They can provide the latest information on state and local sales tax rates, use tax requirements, and any specific local taxes or exemptions that may be applicable in Alabama.

Alabama - Sales Tax - Notes

As of ChatGPT's last update in September 2021, Alabama imposes a sales and use tax on various goods and services. Here are some key points about the Alabama Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Alabama is 4%. However, local jurisdictions (cities and counties) may also impose additional sales taxes, which means the total sales tax rate can be higher in some areas. The combined state and local sales tax rates can range from 4% to 11%.
2. Use Tax: Alabama also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Alabama sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Certain items and services may be exempt from Alabama's sales and use tax. Common exemptions include prescription drugs, groceries, agricultural equipment, and manufacturing machinery used directly in production.
4. Filing and Payment: Businesses that make sales subject to Alabama's sales tax are required to obtain a sales tax license from the Alabama Department of Revenue (ADOR) and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Simplified Seller Use Tax Program (SSUT): Alabama offers a simplified program for remote sellers (out-of-state sellers without a physical presence in Alabama) to voluntarily collect and remit sales tax. This program allows eligible remote sellers to collect a flat 8% use tax on their sales to Alabama customers, rather than dealing with varying local tax rates.
6. Online Sales: Alabama has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Please note that tax laws are subject to change, and it's essential to consult the Alabama Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Alabama.

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Sales tax / Use tax - Alaska (AK)

Alaska (AK) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Alaska:

1. No Statewide Sales Tax or Individual Income Tax: Alaska does not have a statewide sales tax or individual income tax. This makes it one of the few states in the United States with no state-level sales or income taxes.
2. Local Sales Taxes: While Alaska does not have a statewide sales tax, some local jurisdictions within the state may impose local sales taxes. These local taxes are limited in scope and vary by location.
3. No Statewide Use Tax: Alaska does not have a statewide use tax. Use tax is typically applied when residents or businesses purchase taxable items from out-of-state sellers who do not collect the state's sales tax. In Alaska, there is no use tax applicable to such transactions.
4. Property Taxes: Alaska does have property taxes imposed at the local level. However, the state has unique provisions related to property tax, and the property tax rates and assessments vary significantly depending on the municipality.
5. No Statewide Personal Property Tax: Alaska does not impose a statewide personal property tax on assets such as vehicles, boats, or personal belongings.
6. No Vehicle Sales Tax: Alaska does not have a statewide sales tax on vehicle purchases, making it a tax-free state for buying cars.
7. Oil and Gas Revenue: Alaska derives a significant portion of its revenue from oil and gas taxes and royalties due to its rich natural resources.
8. Permanent Fund Dividend: Alaska residents are eligible to receive an annual payment known as the Permanent Fund Dividend, which is funded from the state's oil revenues.
9. Excise Taxes: Alaska imposes excise taxes on certain products, such as alcohol, tobacco, and motor fuel.
10. No Estate Tax: Alaska does not have its own estate tax. Additionally, it does not have a "*pick-up*" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.

It's important to note that tax laws are subject to change, and it's recommended to consult the Alaska Department of Revenue or a tax professional for the most up-to-date and specific information related to

taxes in Alaska.

Alaska (AK) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Alaska does not have a statewide sales tax. This means there is no state-level sales tax applied to goods or services sold within Alaska.

However, it's essential to note that some local jurisdictions in Alaska do have the authority to impose local sales taxes. These local sales taxes are determined by individual municipalities (cities and boroughs) within the state. As a result, the presence and rates of sales taxes can vary depending on the specific location.

Since Alaska does not have a statewide sales tax, the sales tax rates, if applicable, are entirely determined by the local governments. It's crucial to check with the local municipality where a taxable transaction occurs to determine if a local sales tax applies and at what rate.

As for use tax, Alaska also does not have a statewide use tax. Use tax is typically applied to taxable items purchased outside of the state and used within the state when no sales tax was collected at the time of purchase. Since there is no statewide sales tax in Alaska, there is generally no statewide use tax either.

However, some local jurisdictions may have specific use tax requirements or regulations related to certain transactions. As with sales tax, it's essential to check with the local municipality where a taxable transaction occurs to determine if any use tax applies.

Keep in mind that tax laws can change, and it's essential to consult the Alaska Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Alaska, particularly at the local level.

Alaska - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Alaska does not have a statewide sales tax, and therefore, there are no special sales tax rates in addition to the standard state sales tax rate because there is no state sales tax applied to goods or services sold within Alaska.

However, it's important to note that some local jurisdictions in Alaska do have the authority to impose local sales taxes. These local sales taxes are determined by individual municipalities (cities and boroughs) within the state. As a result, the presence and rates of sales taxes can vary depending on the specific location.

If a local sales tax is applicable, it will be specific to the particular municipality where the taxable transaction occurs. Each city or borough that imposes a local sales tax sets its own rate, rules, and regulations related to sales tax.

Since Alaska does not have a statewide sales tax, the sales tax rates, if applicable, are entirely determined by the local governments. It's crucial to check with the local municipality where a taxable transaction occurs

to determine if a local sales tax applies and at what rate.

For the most current and accurate information regarding sales tax rates, exemptions, and any other relevant tax regulations in Alaska, especially at the local level, it's recommended to consult the Alaska Department of Revenue or a tax professional. They can provide the latest information on local sales tax rates and any specific local taxes or exemptions that may be applicable in Alaska.

Alaska - Sales Tax - Notes

Alaska (AK) does not have a state-wide sales tax, and the total sales tax rate varies depending on the local jurisdictions within the state.

Municipal governments in Alaska have the authority to impose local sales taxes, which results in different sales tax rates in different cities, counties, and special districts. The sales tax rates can range from 0.00% in some cities like Anchorage and Fairbanks to as high as 9.5% in places like Seldovia.

For example, in Seldovia, the total sales tax rate is 9.5%, which is a combination of the 3% Kenai Peninsula Borough sales tax and the 6.5% Seldovia city tax.

Since sales tax rates can vary significantly within Alaska, it's essential for businesses and consumers to be aware of the specific sales tax rate in their respective locations to ensure accurate tax collection and reporting.

It's also crucial to note that tax rates can change over time due to local tax rate adjustments or changes in tax laws. Therefore, it's always best to verify the current rates with the Alaska Department of Revenue or consult respective local tax authorities for the most up-to-date and accurate sales tax rates and regulations in specific areas within Alaska.

Alaska - Sales Tax and Use Tax in local jurisdictions

Alaska - Sales Tax and Use Tax in local jurisdictions

As of ChatGPT's last update in September 2021, Alaska does not have a statewide sales tax. However, some local jurisdictions within the state do have the authority to impose local sales taxes. These local sales taxes are determined by individual municipalities (cities and boroughs) and are not applicable across the entire state.

Local Sales Tax: The presence and rates of sales taxes can vary depending on the specific location within Alaska. Each city or borough that imposes a local sales tax sets its own rate, rules, and regulations related to sales tax. Some localities may have a sales tax, while others may not have one at all.

It's crucial to check with the local municipality where a taxable transaction occurs to determine if a local sales tax applies and at what rate. The local government's official website or the Alaska Department of

Revenue can be helpful resources for finding information about local sales taxes.

Use Tax: As for use tax, Alaska also does not have a statewide use tax. Use tax is typically applied to taxable items purchased outside of the state and used within the state when no sales tax was collected at the time of purchase. Since there is no statewide sales tax in Alaska, there is generally no statewide use tax either.

However, some local jurisdictions may have specific use tax requirements or regulations related to certain transactions. As with sales tax, it's essential to check with the local municipality where a taxable transaction occurs to determine if any use tax applies.

Please note that tax laws are subject to change, and it's essential to consult the Alaska Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Alaska, particularly at the local level. Local jurisdictions may update their tax regulations, so it's essential to verify the latest information from the appropriate authorities.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's Efficient User Interface

Sales tax / Use tax - Arizona (AZ)

Arizona (AZ) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Arizona:

1. Sales Tax: Arizona imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 5.6%. In addition to the state sales tax, some local jurisdictions may impose additional sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Arizona also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Arizona for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Arizona levies an individual income tax on residents and non-residents who earn income in the state. The state has multiple tax brackets with varying tax rates based on income levels.
4. Corporate Income Tax: Arizona imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.

5. Franchise Tax: Arkansas imposes a franchise tax on corporations and limited liability companies (LLCs) doing business in the state. The tax is based on the entity's capital or net worth and is calculated using a prescribed formula.
6. Property Taxes: Arizona imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary by county.
7. Vehicle Taxes and Fees: Arizona imposes various taxes and fees on motor vehicles, including transaction privilege tax (TPT) on vehicle sales, registration fees, and vehicle license taxes based on the vehicle's value.
8. Excise Taxes: Arizona imposes excise taxes on certain products, such as tobacco and alcohol.
9. Transaction Privilege Tax (TPT): Arizona has a unique tax called the Transaction Privilege Tax, which is a type of gross receipts tax that applies to businesses for the privilege of conducting business in the state. It is similar to a sales tax but is imposed on the seller rather than the buyer.
10. No Estate Tax: Arizona does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
11. No Local Income Tax: Arizona does not allow local jurisdictions to impose their own income taxes.

It's important to note that tax laws are subject to change, and it's recommended to consult the Arizona Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Arizona.

Arizona (AZ) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Arizona imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Arizona Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Arizona is 5.6%. Additionally, some cities and counties may impose an additional local sales tax, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 5.6% to 11.2% or higher, depending on the location.
2. Exemptions: Some items and services may be exempt from Arizona's sales tax. Common exemptions include prescription drugs, groceries, medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Arizona's sales tax are required to register with the Arizona Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.

4. Online Sales: Arizona has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Arizona is the same as the sales tax rate, which is 5.6%. The use tax is applicable when residents or businesses in Arizona purchase taxable items from out-of-state sellers who do not collect Arizona sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Arizona are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Arizona is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Arizona Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Arizona.

Arizona - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Arizona does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Arizona is 5.6%, and this rate applies uniformly to most taxable transactions throughout the state.

Arizona does have local sales taxes that are imposed by cities and counties. These local sales taxes are in addition to the state sales tax and can vary depending on the location. The combined state and local sales tax rates can range from 5.6% to 11.2% or higher, depending on the city or county where the taxable transaction occurs.

Each city and county in Arizona has the authority to set its own local sales tax rate, and the rate may differ even within the same county. Local sales tax revenues are used to fund various local government initiatives, such as infrastructure projects, public services, and community development.

It's important to be aware of the specific tax rates applicable in your area and for the goods or services you are buying or selling. For the most current and accurate information regarding Arizona's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Arizona Department of Revenue or a tax professional. They can provide the latest information on sales tax rates

and any specific local taxes or exemptions that may be applicable in Arizona.

Arizona - Sales Tax - Notes

As of ChatGPT's last update in September 2021, Arizona imposes a sales and use tax on various goods and services. Here are some key points about the Arizona Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Arizona is 5.6%. However, cities and counties may impose additional sales taxes, so the total sales tax rate can vary depending on the location. The combined state and local sales tax rate can range from 5.6% to 11.2%.
2. Use Tax: Arizona also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Arizona sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Transaction Privilege Tax: In Arizona, the sales tax is often referred to as the Transaction Privilege Tax (TPT). This is because Arizona imposes a tax on the privilege of doing business in the state, rather than just taxing the final retail sale. The TPT applies to the gross receipts of businesses, which means it affects various business activities beyond traditional retail sales.
4. Exemptions: Some items and services are exempt from Arizona's Transaction Privilege Tax. Common exemptions include prescription drugs, groceries, certain types of machinery and equipment used in manufacturing, and sales to the U.S. government.
5. Filing and Payment: Businesses that make sales subject to Arizona's Transaction Privilege Tax are required to obtain a TPT license from the Arizona Department of Revenue (ADOR) and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file TPT returns, reporting the gross receipts and the corresponding tax due.
6. Online Sales: Arizona, like many other states, has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit the Transaction Privilege Tax.

Please note that tax laws are subject to change, and it's essential to consult the Arizona Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Arizona.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Sales tax / Use tax - Arkansas (AR)

Arkansas (AR) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Arkansas:

1. Sales Tax: Arkansas imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.5%. In addition to the state sales tax, some local jurisdictions may impose additional sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Arkansas also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Arkansas for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Arkansas levies an individual income tax on residents and non-residents who earn income in the state. The state has multiple tax brackets with varying tax rates based on income levels.
4. Corporate Income Tax: Arkansas imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
5. Property Taxes: Arkansas imposes property taxes on real and personal property, such as land, buildings, and vehicles. Property tax rates are determined at the local level and can vary by county.
6. Motor Vehicle Taxes and Fees: Arkansas imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, annual registration fees, and excise taxes based on the vehicle's value.
7. Excise Taxes: Arkansas imposes excise taxes on certain products, such as alcohol, tobacco, and gasoline.
8. Severance Taxes: Arkansas imposes severance taxes on natural resources, such as oil, gas, and minerals, extracted from the state.
9. No Estate Tax: Arkansas does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
10. No Vehicle Sales Tax: Arkansas does not impose a separate sales tax on vehicle purchases, but the purchase of a motor vehicle is subject to the state sales tax.

It's important to note that tax laws are subject to change, and it's recommended to consult the Arkansas Department of Finance and Administration or a tax professional for the most up-to-date and specific

information related to taxes in Arkansas.

Arkansas (AR) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Arkansas imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Arkansas Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Arkansas is 6.5%. Additionally, some cities and counties may impose an additional local sales tax, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6.5% to 11.5% or higher, depending on the location.
2. Exemptions: Some items and services may be exempt from Arkansas's sales tax. Common exemptions include prescription drugs, groceries, medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Arkansas's sales tax are required to register with the Arkansas Department of Finance and Administration and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Arkansas has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Arkansas is the same as the sales tax rate, which is 6.5%. The use tax is applicable when residents or businesses in Arkansas purchase taxable items from out-of-state sellers who do not collect Arkansas sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Arkansas are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Arkansas is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Arkansas Department of

Finance and Administration or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Arkansas.

Arkansas - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Arkansas does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Arkansas is 6.5%, and this rate applies uniformly to most taxable transactions throughout the state.

However, it's important to note that Arkansas does allow local jurisdictions, such as cities and counties, to impose local sales taxes on top of the state sales tax rate. These local sales taxes are known as local option sales taxes and are used to fund various local government initiatives, such as infrastructure projects, public services, and community development.

The combined state and local sales tax rates in Arkansas can range from 6.5% to 11.5% or higher, depending on the city or county where the taxable transaction occurs. Each city and county has the authority to set its own local sales tax rate, and the rate may differ even within the same county.

It's essential to be aware of the specific tax rates applicable in your area and for the goods or services you are buying or selling. For the most current and accurate information regarding Arkansas's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Arkansas Department of Finance and Administration or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Arkansas.

Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Sales tax / Use tax - California (CA)

California (CA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in California:

1. Sales Tax: California imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The statewide base sales tax rate is 7.25%. In addition to the state sales tax, some local jurisdictions may impose additional sales taxes, resulting in varying total sales tax rates in different areas of the state. The total sales tax rate can be higher than 7.25% in certain cities and counties.

2. Use Tax: California also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into California for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: California levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with multiple tax brackets and rates based on income levels.
4. Corporate Income Tax: California imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
5. Franchise Tax: California imposes a franchise tax on corporations and LLCs registered in the state. The tax is based on the company's net income or a minimum franchise tax, whichever is greater. The minimum franchise tax applies even if the company has no net income.
6. Property Taxes: California imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and are based on the assessed value of the property.
7. Vehicle Taxes and Fees: California imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, annual registration fees, and vehicle license fees based on the vehicle's value.
8. Excise Taxes: California imposes excise taxes on certain products, such as gasoline, alcohol, and tobacco.
9. Estate Tax: California does not have its own estate tax. However, it conforms to the federal estate tax laws.
10. Local Taxes: In addition to the state-level taxes, some local jurisdictions in California may impose additional taxes, such as local sales taxes or local income taxes.
11. Special District Taxes: Certain areas in California may impose special district taxes to fund specific projects or services, such as public safety, transportation, or education.

It's important to note that tax laws are subject to change, and it's recommended to consult the California Department of Tax and Fee Administration (CDTFA) or a tax professional for the most up-to-date and specific information related to taxes in California.

California (CA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, California imposes a sales tax and use tax on various goods and services. Here are some key points about the California Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in California is 7.25%. Additionally, some local jurisdictions (cities and counties) may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 7.25% to 10.25%.
2. Exemptions: Some items and services may be exempt from California's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to California's sales tax are required to register with the California Department of Tax and Fee Administration (CDTFA) and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: California has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in California is also 7.25%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect California sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in California are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in California is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the California Department of Tax and Fee Administration (CDTFA) or a tax professional for the most up-to-date and specific information related to sales tax and use tax in California.

Sales and Use Tax - Components

In California, retailers engaged in business are required to register with the California Department of Tax and Fee Administration (CDTFA) and collect and remit the state's sales tax. The sales tax applies to all retail sales of goods and merchandise unless specifically exempted by law.

In addition to the state sales tax, California also imposes a use tax. The use tax is generally applied to the storage, use, or other consumption of goods purchased from retailers in transactions not subject to the sales tax. It also applies to purchases made by California consumers from out-of-state retailers, including purchases made by mail order, telephone, or internet.

The sales and use tax rate in a specific location in California comprises three components:

1. State tax rate: The statewide base sales tax rate set by the state government.
2. Local tax rate: Some cities and counties impose additional local sales taxes, which are added to the state tax rate.
3. District tax rate: Certain local jurisdictions may also impose additional district taxes, resulting in varying total tax rates across different locations.

The revenue from state sales and use taxes contributes to the state's General Fund, which funds various government programs and services. Additionally, specific allocations of the sales and use tax revenue are provided to cities, counties, and other local jurisdictions within the state to support their respective budgets and services.

What is the Tax rates in the State of California?

As of ChatGPT's last update in September 2021, the sales tax rate in the state of California can vary depending on the location due to the addition of local sales taxes. California has a statewide base sales tax rate, and local jurisdictions, such as cities and counties, may impose additional sales taxes. The combined sales tax rate is the total rate that consumers pay, including both the state and local taxes.

As of 2021, the statewide base sales tax rate in California is 7.25%. However, the combined sales tax rate can range from 7.25% to 10.25% or even higher in some special districts.

It's important to note that sales tax rates can change over time, and specific local jurisdictions may have their own adjustments to the rate. Additionally, some products or services may be subject to special tax rates or exemptions. For the most up-to-date and accurate information on California's current sales tax rates, I recommend checking the California Department of Tax and Fee Administration (CDTFA) website or consulting with a tax professional.

In the State of California - what is the additional sales tax rates and taxes imposed by local jurisdictions, such as cities and counties?

As of ChatGPT's last update in September 2021, the state of California has a statewide base sales tax rate of 7.25%. However, additional sales taxes can be imposed by local jurisdictions, such as cities and

counties, on top of the state rate. These additional local taxes are known as district taxes.

The combined sales tax rate in California includes both the state rate and any applicable district taxes. The total sales tax rate can vary depending on the specific location of the transaction, as different cities and counties may have different district tax rates.

The additional district taxes in California can range from 0.10% to 3.00% or more, depending on the local jurisdiction's requirements. Some areas may have multiple district taxes imposed by different local agencies.

For example, if you were to make a purchase in a city or county with a 2.00% district tax rate, the combined sales tax rate would be 7.25% (state) + 2.00% (district) = 9.25%.

To find the exact sales tax rate for a specific location within California, you can use the California Department of Tax and Fee Administration (CDTFA) website or contact the local tax authority for the city or county where the purchase is made. Local tax rates can change over time, so it's essential to verify the current rates to ensure accurate tax collection and reporting. Additionally, businesses that operate in multiple locations within California may need to collect and remit different sales tax rates depending on the customer's location.

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Sales tax / Use tax - Colorado (CO)

Colorado (CO) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Colorado:

1. Sales Tax: Colorado imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The state sales tax rate is 2.9%. In addition to the state sales tax, some local jurisdictions may impose additional sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Colorado also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Colorado for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Colorado levies an individual income tax on residents and non-residents who earn income in the state. The state has a flat income tax rate of 4.55% for all income levels.

4. Corporate Income Tax: Colorado imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
5. Property Taxes: Colorado imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and are based on the assessed value of the property.
6. Vehicle Taxes and Fees: Colorado imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and specific ownership tax based on the vehicle's age and taxable value.
7. Excise Taxes: Colorado imposes excise taxes on certain products, such as gasoline, tobacco, and marijuana.
8. Estate Tax: Colorado does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
9. No Local Income Tax: Colorado prohibits local jurisdictions from imposing their own income taxes.
10. Special District Taxes: Certain areas in Colorado may impose special district taxes to fund specific projects or services, such as transportation improvements or public safety initiatives.

It's important to note that tax laws are subject to change, and it's recommended to consult the Colorado Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Colorado.

Colorado (CO) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Colorado imposes a sales tax and use tax on various goods and services. Here are some key points about the Colorado Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Colorado is 2.9%. Additionally, local jurisdictions (cities, counties, and special districts) may impose additional sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 2.9% to 11.2%, depending on the specific location.
2. Exemptions: Some items and services may be exempt from Colorado's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Colorado's sales tax are required to obtain a sales tax license from the Colorado Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales

volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.

4. Online Sales: Colorado has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Colorado is the same as the sales tax rate, which is 2.9%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Colorado sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Colorado are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Colorado is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Colorado Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Colorado.

Colorado - Sales and Use tax - Notes

As of ChatGPT's last update in September 2021, Colorado imposes a sales and use tax on various goods and services. Here are some key points about the Colorado Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Colorado is 2.9%. Additionally, local jurisdictions (cities, counties, and special districts) may impose their own sales taxes, which vary by location. The total sales tax rate, including state and local taxes, can range from 2.9% to 11.2% depending on the specific location.
2. Home Rule Cities: Colorado has both home rule cities and state-collected cities. Home rule cities have the authority to administer and collect their own sales taxes independently of the state. This means that the sales tax rate and regulations may differ between different cities within the state.
3. Use Tax: Colorado also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Colorado sales tax. The purchaser

is then responsible for paying the corresponding use tax directly to the state.

4. Exemptions: Some items and services are exempt from Colorado's sales and use tax. Common exemptions include prescription drugs, groceries, and certain agricultural items.

5. Filing and Payment: Businesses that make sales subject to Colorado's sales tax are required to obtain a sales tax license from the Colorado Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.

6. Online Sales: Colorado has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

7. Special District Taxes: In addition to state and local sales taxes, some areas in Colorado may have special district taxes that apply to specific goods or services. These district taxes are separate from the state and local taxes and may vary by location.

Please note that tax laws are subject to change, and it's essential to consult the Colorado Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Colorado.

Colorado Sales and Use Tax - Components

As of ChatGPT's last update in September 2021, the Colorado sales and use tax consists of several components that contribute to the total tax rate. Here are the main components:

1. State Sales and Use Tax: The state of Colorado imposes a base sales and use tax rate of 2.9%. This is the primary tax rate that applies to most taxable transactions in the state.

2. Local Sales and Use Tax: In addition to the state tax, local jurisdictions (cities, counties, and special districts) in Colorado have the authority to impose their own sales and use taxes. These local taxes vary depending on the specific location and can range from 0% to several percentage points. The total local tax rate varies depending on the sum of the local sales and use taxes applicable in a particular area.

3. Regional Transportation District (RTD) Tax : In areas that are part of the Regional Transportation District (RTD), an additional sales and use tax is imposed to fund public transportation services. As of ChatGPT's last update, the RTD tax rate is 1%. This tax is only applicable in specific areas within the state.

4. Scientific and Cultural Facilities District (SCFD) Tax: In counties that are part of the Scientific and

Cultural Facilities District, an additional sales and use tax is imposed to support scientific and cultural organizations. As of ChatGPT's last update, the SCFD tax rate is 0.1%.

5. Special District Taxes: Some special districts in Colorado may levy additional sales and use taxes for specific purposes, such as fire protection, public safety, or recreational facilities. These taxes are only applicable in the specific districts that impose them.

When making a purchase in Colorado, the total sales tax rate you pay is the combination of the state sales tax rate, any applicable local sales tax rates, and any other district-specific taxes that apply to your location.

Please note that tax rates are subject to change, and it's essential to verify the current rates with the Colorado Department of Revenue or a tax professional for the most up-to-date information on sales and use tax components in Colorado.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Sales tax / Use tax - Connecticut (CT)

Connecticut (CT) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Connecticut (CT):

1. Sales Tax: Connecticut imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.35%. However, certain items, such as groceries, prescription drugs, and medical devices, may be exempt from the sales tax.
2. Use Tax: Connecticut also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Connecticut for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Connecticut levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 3% to 6.99% based on income levels.
4. Corporate Income Tax: Connecticut imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 7.5% to 10.0% based on taxable income.

5. Property Taxes: Connecticut imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by municipality.
6. Vehicle Taxes and Fees: Connecticut imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a property tax based on the value of the vehicle.
7. Estate Tax: Connecticut has its own estate tax, separate from the federal estate tax. The Connecticut estate tax applies to estates with a value above a certain threshold, and the tax rates range from 10% to 12%.
8. Local Income Tax: Connecticut allows municipalities to impose a local income tax on residents' earned and unearned income. However, as of my last update, no municipality has implemented a local income tax.
9. Tax Credits and Incentives: Connecticut offers various tax credits and incentives to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and tax incentives for businesses investing in certain areas or creating jobs.

It's important to note that tax laws are subject to change, and it's recommended to consult the Connecticut Department of Revenue Services or a tax professional for the most up-to-date and specific information related to taxes in Connecticut.

Connecticut (CT) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Connecticut imposes a sales tax and use tax on various goods and services. Here are some key points about the Connecticut Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Connecticut is 6.35%. Additionally, some local jurisdictions (cities and towns) may impose an additional local sales tax, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6.35% to 6.99%.
2. Exemptions: Some items and services may be exempt from Connecticut's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Connecticut's sales tax are required to register with the Connecticut Department of Revenue Services and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Connecticut has adopted economic nexus laws for online sales. This means that

businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Connecticut is also 6.35%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Connecticut sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Connecticut are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Connecticut is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Connecticut Department of Revenue Services or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Connecticut.

Connecticut Department of Revenue Services about Sales Tax and Use Tax in Connecticut

Here's a summary of the key points:

Sales Tax in Connecticut:

- The state sales tax rate in Connecticut is 6.35%.
- It applies to the retail sale, lease, or rental of most goods and taxable services.
- Retailers are required to register for a Sales and Use Tax Permit with the Department of Revenue Services (DRS) if they engage in selling tangible personal property, taxable services, or operating hotels, motels, lodging houses, or bed and breakfast establishments.
- The permit must be displayed conspicuously for customers to see.
- Vendors selling at flea markets, craft shows, trade shows, or similar events in Connecticut, even for one day, must also obtain a permit and display it at their booth or table.
- Manufacturers, wholesalers, and retailers must obtain a permit for selling in the state.

- Building contractors, including subcontractors, must obtain a Sales and Use Tax Permit before providing any services, even if the services provided are not taxable or if the contract is with a tax-exempt entity.
- Failure to obtain a tax permit may result in fines or penalties.

Use Tax in Connecticut:

- The Use Tax is imposed on taxable purchases made by businesses or individuals for use in Connecticut when sales tax was not collected at the time of purchase.
- The use tax rate is the same as the sales tax rate, which is 6.35%.
- Businesses not required to register for sales tax should still register to pay business use tax.

Special Sales Tax Rates:

Some specific transactions have different sales tax rates, such as:

- 1% for certain computer and data processing services and canned software electronically accessed or transferred for business use.
- 2.99% for sales of vessels, motors for vessels, trailers used for transporting a vessel, and dyed diesel fuel sold by a marine dock exclusively for marine purposes.
- 4.5% for sales of motor vehicles to nonresident members of the armed forces stationed on full-time active duty in Connecticut.
- 7.35% for sales of meals and certain beverages.
- 7.75% for certain high-value motor vehicles, jewelry, clothing, footwear, handbags, luggage, umbrellas, wallets, and watches.
- 9.35% for short-term rental or leasing of passenger motor vehicles (30 consecutive calendar days or less).

Please note that tax laws and rates can change, and it's essential to verify the current rates and regulations with the Connecticut Department of Revenue Services or consult with a tax professional for accurate and up-to-date information.

Connecticut - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Connecticut does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Connecticut is 6.35%, and this rate applies uniformly to most taxable transactions throughout the state.

Connecticut does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6.35% state sales tax rate is the only sales tax rate that applies to most taxable sales in Connecticut.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Connecticut's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Connecticut Department of Revenue Services or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Connecticut.

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Sales tax / Use tax - Florida (FL)

Florida (FL) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Florida:

1. Sales Tax: Florida imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. However, there are some exceptions to the general rate, such as a reduced rate of 3% for sales of new mobile homes, 4% for amusement machine receipts, 5.5% for the rental, lease, or license of commercial real property, and 6.95% for electricity.
2. Use Tax: Florida also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Florida for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. No Individual Income Tax: Florida is one of the few states that do not impose an individual income tax on wages and salaries.
4. No Corporate Income Tax on Regular C Corporations: Florida does not impose a corporate income tax on regular C corporations. However, there is a corporate income tax on certain financial institutions and utility companies.
5. No Estate Tax: Florida does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
6. Property Taxes: Florida imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary by county.

7. Communication Services Tax (CST): Florida imposes a Communication Services Tax on services such as telecommunications, cable, satellite, and VoIP services.
8. Documentary Stamp Tax: Florida imposes a documentary stamp tax on various documents, such as deeds, promissory notes, and mortgages.
9. Gross Receipts Tax: Florida has a gross receipts tax on certain businesses, including rental car companies, commercial rentals, and certain tobacco products.
10. No Local Income Tax: Florida prohibits local jurisdictions from imposing their own income taxes.

It's important to note that tax laws are subject to change, and it's recommended to consult the Florida Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Florida.

Florida (FL) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Florida imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Florida Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Florida is 6%. Additionally, some counties may impose an additional discretionary sales surtax, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6% to 8.5% or higher, depending on the county.
2. Exemptions: Some items and services may be exempt from Florida's sales tax. Common exemptions include prescription drugs, certain groceries, medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Florida's sales tax are required to register with the Florida Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Florida has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Florida is the same as the sales tax rate, which is 6%. The use tax is applicable when residents or businesses in Florida purchase taxable items from out-of-state sellers who do not collect Florida sales tax. The purchaser is then responsible for paying the corresponding

use tax directly to the state.

2. Filing and Payment: Individuals and businesses in Florida are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.

3. Online Purchases: As mentioned above, use tax in Florida is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Florida Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Florida.

Florida - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Florida does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Florida is 6%, and this rate applies uniformly to most taxable transactions throughout the state.

Florida does have a discretionary sales surtax, also known as the local option sales tax, which is imposed by many counties. This surtax is in addition to the state sales tax and varies by county. The discretionary sales surtax is used to fund various county and local government initiatives, such as infrastructure projects, public services, and education.

The combined state sales tax and discretionary sales surtax rates can range from 6.5% to 8.5% or higher, depending on the county where the taxable transaction occurs. Each county has the authority to set its own discretionary sales surtax rate, and the rate may differ even within the same region.

It's important to be aware of the specific tax rates applicable in your area and for the goods or services you are buying or selling. For the most current and accurate information regarding Florida's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Florida Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Florida.

Florida - Sales Tax - Notes

As of ChatGPT's last update in September 2021, Florida imposes a sales and use tax on various goods and services. Here are some key points about the Florida Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Florida is 6%. Additionally, local jurisdictions (counties) may

impose their own discretionary sales surtax, which can add up to an additional 2.5%. The total sales tax rate, including state and local taxes, can range from 6% to 8.5% depending on the specific location.

2. Use Tax: Florida also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Florida sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services are exempt from Florida's sales and use tax. Common exemptions include prescription drugs, groceries, medical equipment, and agricultural products.
4. Filing and Payment: Businesses that make sales subject to Florida's sales tax are required to register with the Florida Department of Revenue (DOR) and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Online Sales: Florida has not adopted an economic nexus law for online sales. However, it does require out-of-state sellers with a substantial number of sales in the state to collect and remit sales tax, provided they have sufficient nexus under other provisions of the law.
6. Resale Certificates: Businesses that purchase goods for resale are eligible for a resale certificate. This certificate allows them to buy goods without paying sales tax on those items. Instead, they will collect sales tax when they sell the goods to the end consumer.

Please note that tax laws are subject to change, and it's essential to consult the Florida Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Florida.

Florida Sales and Use Tax - Additional information

Here are some more key points:

1. Sales Tax Exceptions: The general state sales tax rate in Florida is 6%, but there are exceptions with different rates for specific items or services. For example:
    - Retail sales of new mobile homes have a reduced tax rate of 3%.
    - Amusement machine receipts are taxed at a rate of 4%.
    - The rental, lease, or license of commercial real property is taxed at a rate of 5.5%.
    - Electricity is subject to a higher tax rate of 6.95%.
2. Discretionary Sales Surtax: Many Florida counties impose a discretionary sales surtax, also known as

a county tax, in addition to the state sales tax. The county surtax rate is added to the state sales tax rate and applies to most transactions subject to sales or use tax. The surtax rate varies by county and is applied to taxable items or services delivered into the county. Different rates may apply to motor vehicles and mobile homes based on the purchaser's home address.

3. Use Tax: Florida's use tax is due when sales tax was not paid at the time of purchase. This tax applies to the use or consumption of taxable goods or services in situations such as buying a taxable item in Florida without paying sales tax, using a tax-exempt item for personal use or business purposes, or bringing a taxable item from outside Florida without paying sales tax on it.
4. Transient Rental Taxes: In addition to the state sales and use tax and discretionary sales surtax, some Florida counties may impose local option transient rental taxes on short-term rentals or leases of accommodations. These taxes apply to hotels, motels, apartments, rooming houses, mobile home parks, RV parks, condominiums, and timeshare resorts for rental terms of six months or less. The local transient rental taxes are often reported and remitted directly to the local government, while sales tax and discretionary sales surtax on transient rentals are reported and remitted to the Florida Department of Revenue.

It's important to keep in mind that tax laws can change, and it's advisable to verify the most current information with the Florida Department of Revenue or a tax professional for any updates or specific questions regarding sales and use tax in Florida.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Georgia (GA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Georgia:

1. Sales Tax: Georgia imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4%. In addition to the state sales tax, some local jurisdictions may impose additional sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Georgia also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Georgia for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.

3. Individual Income Tax: Georgia levies an individual income tax on residents and non-residents who earn income in the state. The state has a graduated income tax system with six tax brackets and rates ranging from 1% to 5.75% based on income levels.
4. Corporate Income Tax: Georgia imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
5. Franchise Tax: Georgia imposes an annual corporate net worth tax, also known as a franchise tax, on corporations registered in the state. The tax is calculated based on the company's net worth and is subject to a minimum tax amount.
6. Property Taxes: Georgia imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary by county.
7. Vehicle Taxes and Fees: Georgia imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, ad valorem taxes based on the vehicle's value, and annual registration fees.
8. Excise Taxes: Georgia imposes excise taxes on certain products, such as alcohol, tobacco, and motor fuel.
9. Estate Tax: Georgia does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
10. Local Option Sales Tax: Some counties in Georgia may impose a Local Option Sales Tax (LOST) or Special Purpose Local Option Sales Tax (SPLOST) for specific projects or local funding needs.
11. No Local Income Tax: Georgia does not allow local jurisdictions to impose their own income taxes.

It's important to note that tax laws are subject to change, and it's recommended to consult the Georgia Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Georgia.

Georgia (GA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Georgia imposes a sales tax and use tax on various goods and services. Here are some key points about the Georgia Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Georgia is 4%. However, some local jurisdictions (counties and cities) may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 4% to 8%.
2. Exemptions: Some items and services may be exempt from Georgia's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt

organizations.

3. Filing and Payment: Businesses that make sales subject to Georgia's sales tax are required to register with the Georgia Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Georgia has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Georgia is also 4%. The use tax is applicable when residents or businesses in Georgia purchase taxable items from out-of-state sellers who do not collect Georgia sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Georgia are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Georgia is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Georgia Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Georgia.

Georgia - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Georgia has special sales tax rates for certain types of transactions. These special rates apply in addition to the standard state sales tax rate of 4% and any applicable local sales taxes. Here are some of the special sales tax rates in Georgia:

1. Local Option Sales Tax: Some counties and cities in Georgia impose a local option sales tax on top of the state sales tax rate. The local option sales tax rates vary by location and can range from 1% to 4%.
2. Special Purpose Local Option Sales Tax (SPLOST): Certain counties in Georgia have implemented a SPLOST, which is an additional 1% sales tax to fund specific local projects, such as infrastructure improvements or capital projects.
3. Special District Taxes: In some areas, additional sales taxes may apply to support specific districts or

projects. These special district taxes can vary based on the location and purpose of the tax.

4. Hotel-Motel Excise Tax: Georgia imposes an excise tax on hotel and motel accommodations. The tax rate can vary by location and may apply in addition to the regular sales tax rate.
5. Motor Fuel Tax: Georgia imposes specific taxes on motor fuel sales. These taxes are generally included in the fuel's retail price and are not collected at the point of sale separately.
6. Telecommunications Tax: There is a state tax on telecommunications services in Georgia, which applies to charges for telephone and other communication services.
7. Admissions and Amusement Tax: Certain entertainment and amusement activities, such as admission to sporting events, concerts, or amusement parks, may be subject to an additional tax.

It's important to note that the application of special sales tax rates can vary depending on the specific location and type of transaction. For businesses and consumers, it's essential to be aware of the specific tax rates applicable in their area and for the goods or services they are buying or selling.

Please keep in mind that tax laws are subject to change, and it's crucial to verify the most up-to-date information with the Georgia Department of Revenue or a tax professional to ensure compliance with current tax rates and regulations.

Georgia - Sales Tax - Notes

As of ChatGPT's last update in September 2021, Georgia imposes a sales and use tax on various goods and services. Here are some key points about the Georgia Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Georgia is 4%. Additionally, local jurisdictions (counties and municipalities) may impose their own local option sales taxes, which can add up to an additional 4%. The total sales tax rate, including state and local taxes, can range from 4% to 8% depending on the specific location.
2. Use Tax: Georgia also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Georgia sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services are exempt from Georgia's sales and use tax. Common exemptions include prescription drugs, certain medical equipment, groceries, and sales to the U.S. government.
4. Filing and Payment: Businesses that make sales subject to Georgia's sales tax are required to register for a sales tax permit with the Georgia Department of Revenue (DOR) and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the

corresponding tax collected.

5. Online Sales: Georgia has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

6. Special Sales Tax Rates: Certain products and services may have special sales tax rates in Georgia. For example, motor fuel is subject to a separate excise tax and is not included in the general sales tax rate.

Please note that tax laws are subject to change, and it's essential to consult the Georgia Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Georgia.

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Sales tax / Use tax - Idaho (ID)

Idaho (ID) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Idaho:

1. Sales Tax: Idaho imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. In addition to the state sales tax, some local jurisdictions may impose additional sales taxes, resulting in varying total sales tax rates in different areas of the state.

2. Use Tax: Idaho also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Idaho for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.

3. Individual Income Tax: Idaho levies an individual income tax on residents and non-residents who earn income in the state. The state has several tax brackets with rates ranging from 1.125% to 6.925% based on income levels.

4. Corporate Income Tax: Idaho imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.

5. Property Taxes: Idaho imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary by county.

6. Vehicle Taxes and Fees: Idaho imposes various taxes and fees on motor vehicles, including sales tax

on vehicle purchases, registration fees, and a motor vehicle excise tax based on the vehicle's value.

7. Excise Taxes: Idaho imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. Estate Tax: Idaho does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
9. No Local Income Tax: Idaho does not allow local jurisdictions to impose their own income taxes.
10. Grocery Tax Credit: Idaho provides a grocery tax credit to offset the impact of the state sales tax on food purchased for home consumption. Eligible individuals and families can claim this credit on their income tax returns.

It's important to note that tax laws are subject to change, and it's recommended to consult the Idaho State Tax Commission or a tax professional for the most up-to-date and specific information related to taxes in Idaho.

Idaho (ID) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Idaho imposes a sales tax and use tax on various goods and services. Here are some key points about the Idaho Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Idaho is 6%. This is the primary tax rate that applies to most taxable transactions in the state.
2. Exemptions: Some items and services may be exempt from Idaho's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Idaho's sales tax are required to register with the Idaho State Tax Commission and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Idaho has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Idaho is also 6%. The use tax is applicable when residents or businesses in Idaho purchase taxable items from out-of-state sellers who do not collect Idaho sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.

2. Filing and Payment: Individuals and businesses in Idaho are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Idaho is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Idaho State Tax Commission or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Idaho.

Idaho - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Idaho does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Idaho is 6%, and this rate applies uniformly to most taxable transactions throughout the state.

Unlike some other states, Idaho does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6% state sales tax rate is the only sales tax rate that applies to most taxable sales in Idaho.

However, it's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Idaho's sales tax rates, it's recommended to consult the Idaho State Tax Commission or a tax professional. They can provide the latest information on sales tax rates, exemptions, and any other relevant tax regulations in the state of Idaho.

Idaho - Sales and Use tax - Notes

As of ChatGPT's last update in September 2021, Idaho imposes a sales and use tax on various goods and services. Here are some key points about the Idaho Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Idaho is 6%. Additionally, there may be local option taxes imposed by counties or cities, which can vary the total sales tax rate in specific areas.
2. Use Tax: Idaho also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Idaho sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services may be exempt from Idaho's sales and use tax. Common

exemptions include prescription drugs, groceries, and certain agricultural products.

4. Filing and Payment: Businesses that make sales subject to Idaho's sales tax are required to register for a seller's permit with the Idaho State Tax Commission and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Online Sales: Idaho has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.
6. Destination-Based Sales Tax: In Idaho, the sales tax rate is generally based on the destination of the sale. This means that the applicable tax rate is determined by the location where the goods are delivered or services are performed.
7. Special Sales Tax Rates: Some specific items and services may have special sales tax rates in Idaho. For example, there are specific tax rates for lodging and alcoholic beverages.

Please note that tax laws are subject to change, and it's essential to consult the Idaho State Tax Commission or a tax professional for the most up-to-date and specific information related to sales and use tax in Idaho.

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Sales tax / Use tax - Illinois (IL)

Illinois (IL) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Illinois:

1. Sales Tax: Illinois imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.25%. In addition to the state sales tax, there may be additional local sales taxes imposed by counties and municipalities, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Illinois also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Illinois for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.

3. Individual Income Tax: Illinois levies an individual income tax on residents and non-residents who earn income in the state. As of my last update, the individual income tax rates are 4.95% for individuals and 7% for corporations.
4. Corporate Income Tax: Illinois imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 7% for regular corporations and 1.5% for S corporations.
5. Franchise Tax: Illinois imposes a corporate franchise tax on corporations doing business in the state. The tax is based on the company's paid-in capital and is calculated using specified rates. Certain corporations, such as financial institutions, are subject to different franchise tax rules.
6. Property Taxes: Illinois imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
7. Vehicle Taxes and Fees: Illinois imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a vehicle use tax based on the purchase price.
8. Excise Taxes: Illinois imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
9. Estate Tax: Illinois had its own estate tax, commonly known as the "Illinois death tax." As of my last update, the estate tax applied to estates with a value over $4 million, with rates ranging from 0.8% to 16%.
10. No Local Income Tax: Illinois does not allow local jurisdictions to impose their own income taxes.
11. No Tax on Retirement Income: Illinois does not tax retirement income, such as Social Security benefits, pensions, and retirement account distributions.

It's important to note that tax laws are subject to change, and it's recommended to consult the Illinois Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Illinois.

Illinois (IL) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Illinois imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Illinois Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Illinois is 6.25%. Additionally, some local jurisdictions (counties and municipalities) impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6.25% to 11%.

2. Exemptions: Some items and services may be exempt from Illinois' sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations. It's essential to review the Illinois Department of Revenue's guidelines for a comprehensive list of exemptions.
3. Filing and Payment: Businesses that make sales subject to Illinois' sales tax are required to register with the Illinois Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Illinois has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Illinois is the same as the sales tax rate, which is 6.25%. The use tax is applicable when residents or businesses in Illinois purchase taxable items from out-of-state sellers who do not collect Illinois sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Illinois are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Illinois is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Illinois Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Illinois.

Illinois- Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Illinois has several special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Illinois is 6.25%, but certain areas and specific transactions may have additional local or regional sales taxes. Here are some of the special sales tax rates in Illinois:

1. Local Option Sales Tax: Many counties and municipalities in Illinois impose a local option sales tax on top of the state sales tax rate. The local option sales tax rates can vary by location and can range from

0.25% to 2.75% or higher.

2. Regional Transportation Authority (RTA) Tax: In the metropolitan Chicago area, which includes Cook, DuPage, Kane, Lake, McHenry, and Will counties, an additional 1% RTA sales tax is imposed to support the Regional Transportation Authority's operations.
3. Home Rule Sales Tax: Some municipalities in Illinois have been granted home rule authority, which allows them to impose additional sales taxes beyond the state and local option rates. The home rule sales tax rates can vary depending on the municipality.
4. Special District Taxes: In certain areas, additional sales taxes may be imposed to fund specific districts or projects, such as public safety, education, or infrastructure improvements.
5. Retailers' Occupation Tax (ROT) and Service Occupation Tax (SOT): In addition to the state sales tax, Illinois imposes retailers' occupation tax and service occupation tax on certain sales and services. These taxes are collected by the retailer and vary based on the type of product or service being sold.
6. Prepared Food and Beverage Tax: Some localities in Illinois impose an additional tax on prepared food and beverages sold in restaurants or other dining establishments.

It's important to note that the application of special sales tax rates can vary depending on the specific location and type of transaction. For businesses and consumers, it's essential to be aware of the specific tax rates applicable in their area and for the goods or services they are buying or selling.

Please keep in mind that tax laws are subject to change, and it's crucial to verify the most up-to-date information with the Illinois Department of Revenue or a tax professional to ensure compliance with current tax rates and regulations.

Illinois - Sales and Use tax - Notes

As of ChatGPT's last update in September 2021, Illinois imposes a sales and use tax on various goods and services. Here are some key points about the Illinois Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Illinois is 6.25%. Additionally, local jurisdictions (municipalities and counties) may impose additional sales taxes, which means the total sales tax rate can be higher in some areas. The combined state and local sales tax rates can range from 6.25% to 11% depending on the specific location.
2. Use Tax: Illinois also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Illinois sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services may be exempt from Illinois' sales and use tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt

organizations.

4. Filing and Payment: Businesses that make sales subject to Illinois' sales tax are required to register for a Retailer's Occupation Tax (ROT) certificate with the Illinois Department of Revenue (IDOR) and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Online Sales: Illinois has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.
6. Destination-Based Sales Tax: In Illinois, the sales tax rate is generally based on the destination of the sale. This means that the applicable tax rate is determined by the location where the goods are delivered or services are performed.
7. Service Occupation Tax: In addition to the Retailers' Occupation Tax (ROT), Illinois also has a Service Occupation Tax (SOT) that applies to certain services, such as dry cleaning, repair services, landscaping, and others.

Please note that tax laws are subject to change, and it's essential to consult the Illinois Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Illinois.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Sales tax / Use tax - Indiana (IN)

Indiana (IN) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Indiana (IN):

1. Sales Tax: Indiana imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 7%. However, there may be additional local sales taxes imposed by counties and municipalities, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Indiana also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Indiana for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.

3. Individual Income Tax: Indiana levies an individual income tax on residents and non-residents who earn income in the state. The state has a flat income tax rate of 3.23% as of my last update.
4. Corporate Income Tax: Indiana imposes a corporate income tax on corporations conducting business in the state. The corporate tax rate is also a flat rate of 5.25% as of ChatGPT's last update.
5. Property Taxes: Indiana imposes property taxes on real and personal property, such as land, buildings, and vehicles. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: Indiana imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and an excise tax based on the vehicle's value.
7. Excise Taxes: Indiana imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. Inheritance Tax: Indiana repealed its inheritance tax, and as of ChatGPT's last update, there is no inheritance tax imposed by the state.
9. No Local Income Tax: Indiana does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Indiana offers various tax credits and incentives to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and tax incentives for businesses investing in certain areas or creating jobs.

It's important to note that tax laws are subject to change, and it's recommended to consult the Indiana Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Indiana.

Indiana (IN) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Indiana imposes a sales tax and use tax on various goods and services. Here are some key points about the Indiana Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Indiana is 7%. Additionally, some local jurisdictions (counties and municipalities) may impose additional local option sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 7% to 9%.
2. Exemptions: Some items and services may be exempt from Indiana's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Indiana's sales tax are required to register

for a Retail Merchant Certificate with the Indiana Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.

4. Online Sales: Indiana has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Indiana is also 7%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Indiana sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Indiana are required to report and remit use tax on their Indiana income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Indiana is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Indiana Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Indiana.

Indiana's county tax rates

The state sales tax rate for Indiana is 7%. However, counties and municipalities within Indiana may impose additional taxes on specific transactions. Here are some types of taxes that may be levied at the county level:

1. County Innkeeper's Tax (CIT): This tax is imposed on lodging services, typically hotels, motels, and other accommodations. The tax rate for CIT varies by county and may not be applicable in all counties.
2. Food and Beverage Tax (FAB): This tax is imposed on the sale of prepared food and beverages in certain areas. The FAB tax rate varies by county and may also be applicable in some municipalities within the counties.
3. Local Income Tax (LIT): All counties in Indiana have a Local Income Tax (LIT) rate. LIT is a tax imposed on the income of individuals and businesses within the county. The LIT rate may differ from one county

to another.

Please note that county tax rates may change over time, and it's essential to refer to the Indiana Department of Revenue (DOR) or the specific county's official website for the most up-to-date and accurate tax rate information for County Innkeeper's Tax (CIT), Food and Beverage Tax (FAB), and Local Income Tax (LIT) in Indiana.

Indiana - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Indiana does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Indiana is 7%, and this rate applies uniformly to most taxable transactions throughout the state.

Indiana does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 7% state sales tax rate is the only sales tax rate that applies to most taxable sales in Indiana.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Indiana's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Indiana Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Indiana.

Created with the Standard Edition of HelpNDoc: Transform Your Word Document into a Professional eBook with HelpNDoc

Sales tax / Use tax - Iowa (IA)

Iowa (IA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Iowa:

1. Sales Tax: Iowa imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. In addition to the state sales tax, there may be additional local option sales taxes imposed by counties and municipalities, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Iowa also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Iowa for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.

3. Individual Income Tax: Iowa levies an individual income tax on residents and non-residents who earn income in the state. The state has nine income tax brackets, with rates ranging from 0.33% to 8.53% based on income levels.
4. Corporate Income Tax: Iowa imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 5.5% to 12% based on taxable income.
5. Property Taxes: Iowa imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: Iowa imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and annual vehicle fees.
7. Excise Taxes: Iowa imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. Inheritance Tax: Iowa has an inheritance tax that applies to certain transfers of property after a person's death. The tax rates depend on the relationship between the decedent and the beneficiary.
9. No Local Income Tax: Iowa does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Deductions: Iowa offers various tax credits and deductions to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and the Research Activities Credit for eligible research and development expenses.

It's important to note that tax laws are subject to change, and it's recommended to consult the Iowa Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Iowa.

Iowa (IA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Iowa imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Iowa Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Iowa is 6%. Additionally, some local jurisdictions (cities and counties) may impose an additional local option sales tax, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6% to 7%.
2. Exemptions: Some items and services may be exempt from Iowa's sales tax. Common exemptions include prescription drugs, certain food items, medical equipment, and sales to tax-exempt organizations. Iowa also provides exemptions for manufacturing machinery and equipment.
3. Filing and Payment: Businesses that make sales subject to Iowa's sales tax are required to register with the Iowa Department of Revenue and collect the appropriate tax from their customers. The filing

frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.

4. Online Sales: Iowa has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Iowa is the same as the sales tax rate, which is 6%. The use tax is applicable when residents or businesses in Iowa purchase taxable items from out-of-state sellers who do not collect Iowa sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Iowa are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Iowa is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Iowa Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Iowa.

Iowa - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Iowa does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Iowa is 6%, and this rate applies uniformly to most taxable transactions throughout the state.

Iowa does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6% state sales tax rate is the only sales tax rate that applies to most taxable sales in Iowa.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Iowa's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Iowa Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Iowa.

Iowa - Sales Tax - Notes

As of ChatGPT's last update in September 2021, Iowa imposes a sales and use tax on various goods and services. Here are some key points about the Iowa Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Iowa is 6%. Additionally, some local jurisdictions (cities and counties) may impose an additional local option sales tax, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6% to 7%.
2. Use Tax: Iowa also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Iowa sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services may be exempt from Iowa's sales and use tax. Common exemptions include prescription drugs, certain medical equipment, groceries, and purchases made by tax-exempt organizations.
4. Filing and Payment: Businesses that make sales subject to Iowa's sales tax are required to obtain a sales tax permit from the Iowa Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Online Sales: Iowa has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.
6. Destination-Based Sales Tax: In Iowa, the sales tax rate is generally based on the destination of the sale. This means that the applicable tax rate is determined by the location where the goods are delivered or services are performed.
7. Special Sales Tax Rates: Some specific items and services may have special sales tax rates in Iowa. For example, there are specific tax rates for hotel accommodations and the rental of vehicles.

Please note that tax laws are subject to change, and it's essential to consult the Iowa Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Iowa.

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Sales tax / Use tax - Kansas (KS)

Kansas (KS) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Kansas:

1. Sales Tax: Kansas imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.5%. In addition to the state sales tax, there may be additional local sales taxes imposed by counties and municipalities, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Kansas also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Kansas for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Kansas levies an individual income tax on residents and non-residents who earn income in the state. The state has three income tax brackets, with rates ranging from 3.1% to 5.7% based on income levels.
4. Corporate Income Tax: Kansas imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates range from 4% to 7% based on taxable income.
5. Property Taxes: Kansas imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: Kansas imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and motor vehicle excise tax.
7. Excise Taxes: Kansas imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. No Estate Tax: Kansas does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
9. No Local Income Tax: Kansas does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Kansas offers various tax credits and incentives to individuals and businesses, such as the Child and Dependent Care Credit, the Low-Income Student Scholarship Program, and tax incentives for businesses investing in certain areas or creating jobs.

It's important to note that tax laws are subject to change, and it's recommended to consult the Kansas Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Kansas.

Kansas (KS) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Kansas imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Kansas Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Kansas is 6.5%. Additionally, some local jurisdictions (counties and cities) may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6.5% to 10.5% or higher, depending on the location.
2. Exemptions: Some items and services may be exempt from Kansas' sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations. Additionally, Kansas provides various exemptions for manufacturing machinery and equipment.
3. Filing and Payment: Businesses that make sales subject to Kansas' sales tax are required to register with the Kansas Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Kansas has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Kansas is the same as the sales tax rate, which is 6.5%. The use tax is applicable when residents or businesses in Kansas purchase taxable items from out-of-state sellers who do not collect Kansas sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Kansas are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Kansas is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Kansas Department of

Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Kansas.

Kansas - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Kansas does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Kansas is 6.5%, and this rate applies uniformly to most taxable transactions throughout the state.

Kansas does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6.5% state sales tax rate is the only sales tax rate that applies to most taxable sales in Kansas.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Kansas's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Kansas Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Kansas.

Kansas - Sales and Use tax - Notes

As of ChatGPT's last update in September 2021, Kansas imposes a sales and use tax on various goods and services. Here are some key points about the Kansas Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Kansas is 6.5%. Additionally, local jurisdictions (cities, counties, and special taxing districts) may impose additional sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6.5% to 11.5% depending on the specific location.
2. Use Tax: Kansas also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Kansas sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services may be exempt from Kansas' sales and use tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
4. Filing and Payment: Businesses that make sales subject to Kansas' sales tax are required to register with the Kansas Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.

5. Online Sales: Kansas has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.
6. Food Sales Tax: In Kansas, food sales tax is lower than the general sales tax rate. As of my last update, food sales tax is 6.5%, while the general sales tax rate is also 6.5%. However, some localities may have additional taxes on food sales.
7. Compensating Use Tax: Kansas imposes a compensating use tax on goods and services purchased outside of the state when the seller does not collect Kansas sales tax.

Please note that tax laws are subject to change, and it's essential to consult the Kansas Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Kansas.

Kansas - Tax system - key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Kansas:

1. Sales Tax: Kansas imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.5%. In addition to the state sales tax, there may be additional local sales taxes imposed by counties and municipalities, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Kansas also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Kansas for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Kansas levies an individual income tax on residents and non-residents who earn income in the state. The state has three income tax brackets, with rates ranging from 3.1% to 5.7% based on income levels.
4. Corporate Income Tax: Kansas imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates range from 4% to 7% based on taxable income.
5. Property Taxes: Kansas imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: Kansas imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and motor vehicle excise tax.
7. Excise Taxes: Kansas imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. No Estate Tax: Kansas does not have its own estate tax. Additionally, it does not have a "pick-up" tax,

meaning it does not collect a portion of the federal estate tax paid by the estate.

9. No Local Income Tax: Kansas does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Kansas offers various tax credits and incentives to individuals and businesses, such as the Child and Dependent Care Credit, the Low-Income Student Scholarship Program, and tax incentives for businesses investing in certain areas or creating jobs.

It's important to note that tax laws are subject to change, and it's recommended to consult the Kansas Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Kansas.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Sales tax / Use tax - Kentucky (KY)

Kentucky (KY) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Kentucky (KY):

1. Sales Tax: Kentucky imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. In addition to the state sales tax, there may be additional local sales taxes imposed by cities and counties, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Kentucky also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Kentucky for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Kentucky levies an individual income tax on residents and non-residents who earn income in the state. The state has six income tax brackets, with rates ranging from 2% to 5%. Additionally, there is a limited deduction for certain retirement income.
4. Corporate Income Tax: Kentucky imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 4% to 6.25% based on taxable income.
5. Property Taxes: Kentucky imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.

6. Vehicle Taxes and Fees: Kentucky imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a motor vehicle usage tax based on the vehicle's value.
7. Excise Taxes: Kentucky imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. No Estate Tax: Kentucky does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
9. No Local Income Tax: Kentucky does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Kentucky offers various tax credits and incentives to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and tax incentives for businesses creating jobs and investing in certain areas.

It's important to note that tax laws are subject to change, and it's recommended to consult the Kentucky Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Kentucky.

Kentucky (KY) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Kentucky imposes a sales tax and use tax on various goods and services. Here are some key points about the Kentucky Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Kentucky is 6%. Additionally, some local jurisdictions (cities and counties) may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6% to 7%.
2. Exemptions: Some items and services may be exempt from Kentucky's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Kentucky's sales tax are required to register with the Kentucky Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Kentucky has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Kentucky is also 6%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Kentucky sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Kentucky are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Kentucky is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Kentucky Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Kentucky.

Kentucky - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Kentucky does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Kentucky is 6%, and this rate applies uniformly to most taxable transactions throughout the state.

Kentucky does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6% state sales tax rate is the only sales tax rate that applies to most taxable sales in Kentucky.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Kentucky's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Kentucky Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Kentucky.

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Sales tax / Use tax - Louisiana (LA)

Louisiana (LA)- Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in

Louisiana:

1. Sales Tax: Louisiana imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4.45%. However, when combined with local sales taxes imposed by parishes (counties) and municipalities, the total sales tax rate can vary and may be higher than the state rate.
2. Use Tax: Louisiana also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Louisiana for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Louisiana levies an individual income tax on residents and non-residents who earn income in the state. The state has three income tax brackets, with rates ranging from 2% to 6% based on income levels.
4. Corporate Income Tax: Louisiana imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 4% to 8% based on taxable income.
5. Franchise Tax: Louisiana imposes a corporate franchise tax on corporations registered in the state. The tax is based on the company's capital or net worth and is calculated using a prescribed formula.
6. Property Taxes: Louisiana imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by parish.
7. Vehicle Taxes and Fees: Louisiana imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and ad valorem taxes based on the vehicle's value.
8. Excise Taxes: Louisiana imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
9. No Estate Tax: Louisiana does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
10. No Local Income Tax: Louisiana does not allow local jurisdictions to impose their own income taxes.
11. Tax Credits and Incentives: Louisiana offers various tax credits and incentives to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and tax incentives for businesses investing in certain areas or creating jobs.

It's important to note that tax laws are subject to change, and it's recommended to consult the Louisiana Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Louisiana.

Louisiana (LA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Louisiana imposes both a sales tax and a use tax on various goods and services. Here are some key points about the Louisiana Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Louisiana is 4.45%. Additionally, some local jurisdictions (parishes) may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 4.45% to 11.45% or higher, depending on the location.
2. Exemptions: Some items and services may be exempt from Louisiana's sales tax. Common exemptions include groceries, prescription drugs, certain medical equipment, and sales to tax-exempt organizations. Additionally, Louisiana provides various exemptions for manufacturing machinery and equipment.
3. Filing and Payment: Businesses that make sales subject to Louisiana's sales tax are required to register with the Louisiana Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Louisiana has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Louisiana is the same as the sales tax rate, which is 4.45%. The use tax is applicable when residents or businesses in Louisiana purchase taxable items from out-of-state sellers who do not collect Louisiana sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Louisiana are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Louisiana is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Louisiana Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Louisiana.

Louisiana - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Louisiana does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Louisiana is 4.45%, and this rate applies uniformly to most taxable transactions throughout the state.

Louisiana does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 4.45% state sales tax rate is the only sales tax rate that applies to most taxable sales in Louisiana.

However, it's important to note that local jurisdictions in Louisiana may have additional taxes on certain items or services. For example, some parishes (counties) in Louisiana impose a parish sales tax on top of the state sales tax rate. The combined state and local sales tax rates can vary depending on the location.

It's essential to be aware of the specific tax rates applicable in your area and for the goods or services you are buying or selling. For the most current and accurate information regarding Louisiana's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Louisiana Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Louisiana.

Louisiana - Sales and Use tax - Notes

As of ChatGPT's last update in September 2021, Louisiana imposes a sales and use tax on various goods and services. Here are some key points about the Louisiana Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Louisiana is 4.45%. Additionally, local jurisdictions (parishes) may impose additional sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 4.45% to 11.45% depending on the specific location.
2. Use Tax: Louisiana also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Louisiana sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services may be exempt from Louisiana's sales and use tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.

4. Filing and Payment: Businesses that make sales subject to Louisiana's sales tax are required to register with the Louisiana Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Online Sales: Louisiana has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.
6. Destination-Based Sales Tax: In Louisiana, the sales tax rate is generally based on the destination of the sale. This means that the applicable tax rate is determined by the location where the goods are delivered or services are performed.
7. Special Sales Tax Rates: Some specific items and services may have special sales tax rates in Louisiana. For example, there are specific tax rates for hotel accommodations, car rentals, and certain luxury items.

Please note that tax laws are subject to change, and it's essential to consult the Louisiana Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Louisiana.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

---

Maine (ME) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Maine (ME):

1. Sales Tax: Maine imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 5.5%. However, certain items, such as groceries, prescription drugs, and some agricultural products, may be exempt from the sales tax.
2. Use Tax: Maine also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Maine for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Maine levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from

5.8% to 7.15% based on income levels.

4. Corporate Income Tax: Maine imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 8.93% on net income up to $3 million, and 3.5% on net income over $3 million.
5. Property Taxes: Maine imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by municipality.
6. Vehicle Taxes and Fees: Maine imposes various taxes and fees on motor vehicles, including excise tax based on the vehicle's value, registration fees, and title fees.
7. Estate Tax: Maine has its own estate tax, separate from the federal estate tax. The Maine estate tax applies to estates with a value above a certain threshold, and the tax rates range from 8% to 12%.
8. No Local Income Tax: Maine does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: Maine offers various tax credits and incentives to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and tax credits for certain industries and job creation.
10. Property Tax Relief Programs: Maine offers property tax relief programs for certain individuals, such as the Homestead Exemption and the Property Tax Fairness Credit, which provide assistance to eligible homeowners and renters.

It's important to note that tax laws are subject to change, and it's recommended to consult the Maine Revenue Services or a tax professional for the most up-to-date and specific information related to taxes in Maine.

Maine (ME) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Maine imposes a sales tax and use tax on various goods and services. Here are some key points about the Maine Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Maine is 5.5%. Additionally, some local jurisdictions (municipalities) may impose additional local option sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 5.5% to 8%.
2. Exemptions: Some items and services may be exempt from Maine's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.

3. Filing and Payment: Businesses that make sales subject to Maine's sales tax are required to register with the Maine Revenue Services and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Maine has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Maine is also 5.5%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Maine sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Maine are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Maine is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Maine Revenue Services (MRS). or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Maine.

Maine- Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Maine does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Maine is 5.5%, and this rate applies uniformly to most taxable transactions throughout the state.

Maine does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 5.5% state sales tax rate is the only sales tax rate that applies to most taxable sales in Maine.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Maine's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Maine Revenue Services (MRS) or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Maine.

What is the difference between sales tax and use tax and service provider tax in Maine?

Sales Tax, Use Tax, and Service Provider Tax are different types of taxes applied in Maine based on specific transactions and activities. Here's a brief explanation of each:

1. Sales Tax: Sales tax is a tax levied on the sale of tangible personal property and, in some cases, certain services within the state of Maine. When a business sells taxable goods or services to a customer, the business is required to collect the sales tax from the customer at the time of the sale. The collected sales tax is then remitted to the state's tax authorities. The sales tax rate in Maine is 5.5%, with the potential for additional local option taxes in certain areas.
2. Use Tax: Use tax is a complementary tax to sales tax and is applicable when taxable goods or services are purchased outside of Maine and brought into the state for use, storage, or consumption. If the seller did not collect Maine sales tax at the time of purchase, the buyer is responsible for paying the equivalent use tax directly to the state. Use tax ensures that out-of-state purchases are subject to a tax similar to the sales tax on in-state purchases, preventing tax avoidance through cross-border transactions.
3. Service Provider Tax: The service provider tax is a specific tax applicable to certain services provided by businesses in Maine. It is not a tax on the sale of tangible personal property but rather on services rendered. The service provider tax rate in Maine is 5.5%. It applies to specific services, such as lodging and accommodation services, rental of living quarters or sleeping accommodations, certain prepared food and drink services, certain rental and leasing of tangible personal property, and various personal and professional services.

In summary:

- Sales tax is a tax on the sale of taxable goods and services within the state of Maine, collected by the seller from the customer at the time of the transaction.
- Use tax is a tax on the use, storage, or consumption of taxable goods or services purchased outside Maine, paid directly by the buyer to the state if sales tax was not collected at the time of purchase.
- Service Provider Tax is a tax on specific services provided within Maine, applied by businesses that offer the specified taxable services.

Each of these taxes serves a different purpose and applies to different transactions, ensuring that both in-state and out-of-state purchases are appropriately taxed. Please note that tax laws can change, and it's crucial to verify the latest information with the Maine Revenue Services (MRS) or a tax professional.

Maine - Sales Tax, Use Tax and Service Provider Tax - Notes

Maine's sales tax and service provider tax.

Sales Tax in Maine: Maine imposes a sales tax on the retail sale of tangible personal property and certain services. The sales tax is collected by retailers from customers and is considered a "*trust fund*" tax. This means that retailers collect the tax on behalf of the state and hold it in trust until it is remitted to the Maine Revenue Services (MRS).

The exact sales tax rate may vary depending on the location and type of sale, as some municipalities may impose additional local taxes. Retailers are required to timely file their sales tax returns and remit the collected sales tax to the state.

Use Tax in Maine: Maine also has a use tax, which is imposed on the use, storage, or consumption of tangible personal property in the state when sales tax has not been paid on the purchase. The use tax is generally applicable to purchases made from out-of-state sellers who do not collect Maine sales tax.

Service Provider Tax: In addition to the sales tax, Maine imposes a service provider tax on certain services. The service provider tax applies to specific services provided in Maine, and the tax rate may vary depending on the type of service.

Filing and Payment Deadlines: The deadline for filing and remitting Maine sales tax is generally unchanged, even in times of economic strain. Retailers are encouraged to file their sales tax returns on time, and an extension to file does not extend the deadline for remitting the collected sales tax to the state.

If retailers cannot compute the actual sales tax amount to remit, they may still timely file their return and remit an estimated sales tax based on their filing history. They can later file an amended return to reconcile the correct tax owed.

For specific questions or assistance with Maine's sales tax, service provider tax, or use tax, retailers and taxpayers can contact the Maine Revenue Services (MRS) Sales Tax Division or Compliance Division using the provided contact information.

As with any tax matters, it is essential for businesses and individuals in Maine to comply with the relevant tax laws and regulations, and when in doubt, seek advice from a tax professional to ensure proper compliance.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Sales tax / Use tax - Maryland (MD)

Maryland (MD) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Maryland (MD):

1. Sales Tax: Maryland imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. However, certain items, such as groceries, prescription drugs, and residential energy, may be exempt from the sales tax.
2. Use Tax: Maryland also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Maryland for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Maryland levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 2% to 5.75% based on income levels.
4. Corporate Income Tax: Maryland imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 8.25% to 8.75% based on taxable income.
5. Property Taxes: Maryland imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: Maryland imposes various taxes and fees on motor vehicles, including excise tax based on the vehicle's value, registration fees, and title fees.
7. Estate Tax: Maryland has its own estate tax, separate from the federal estate tax. The Maryland estate tax applies to estates with a value above a certain threshold, and the tax rates range from 0.8% to 16%.
8. No Local Income Tax: Maryland does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: Maryland offers various tax credits and incentives to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and tax credits for certain industries and job creation.
10. Sales Tax Holidays: Maryland occasionally offers sales tax holidays during which certain qualifying items, such as back-to-school supplies, are exempt from the sales tax for a limited time.

It's important to note that tax laws are subject to change, and it's recommended to consult the Maryland Comptroller's Office or a tax professional for the most up-to-date and specific information related to taxes in Maryland.

Maryland (MD) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Maryland imposes a sales tax and use tax on various goods and services. Here are some key points about the Maryland Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Maryland is 6%. This is the primary tax rate that applies to most taxable transactions in the state.
2. Exemptions: Some items and services may be exempt from Maryland's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Maryland's sales tax are required to register with the Maryland Comptroller's Office and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Maryland has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Maryland is also 6%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Maryland sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Maryland are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Maryland is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Maryland Comptroller's Office or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Maryland.

Maryland - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Maryland does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Maryland is 6%, and this rate applies uniformly to most taxable transactions throughout the state.

Maryland does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6% state sales tax rate is the only sales tax rate that applies to most taxable sales in Maryland.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Maryland's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Maryland Comptroller's Office or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Maryland.

Maryland - Sales and Use tax - Notes

The sales tax rate in the state of Maryland is 6.00%. Businesses in Maryland are required to collect this 6% sales tax from customers whenever a taxable purchase is made. The sale of tangible personal property is generally taxable, while the sale of services is generally not taxable, except for certain taxable services provided by law.

It's important to note that while the state of Maryland imposes a statewide sales tax rate of 6.00%, the total sales tax rate that customers pay may be higher in some locations due to additional local taxes. Each city in each county collects the sales tax on behalf of the state of Maryland, which means that there may be local sales taxes imposed on top of the state rate, depending on the specific location of the transaction.

Local sales tax rates can vary, and the total combined sales tax rate may be higher than 6% in certain areas of Maryland. Businesses should verify the exact sales tax rate for each location where they make sales to ensure accurate tax collection and reporting. It's always recommended to consult with the Maryland Comptroller's Office or the local tax authority for the most up-to-date and accurate sales tax rates and regulations in the state.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Sales tax / Use tax - Massachusetts (MA)

Massachusetts (MA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Massachusetts:

1. Sales Tax: Massachusetts imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.25%. Some items, such as groceries and prescription drugs, may be exempt from the sales tax.
2. Use Tax: Massachusetts also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Massachusetts for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Massachusetts levies an individual income tax on residents and non-residents who earn income in the state. The state has a flat income tax rate of 5.00% as of my last update.
4. Corporate Income Tax: Massachusetts imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is also a flat rate of 8.00% as of my last update.
5. Property Taxes: Massachusetts imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by city and town.
6. Vehicle Taxes and Fees: Massachusetts imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and an annual excise tax based on the value of the vehicle.
7. Excise Taxes: Massachusetts imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. Estate Tax: Massachusetts has its own estate tax, separate from the federal estate tax. The Massachusetts estate tax applies to estates with a value above a certain threshold, and the tax rates range from 0.8% to 16%.
9. No Local Income Tax: Massachusetts does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Deductions: Massachusetts offers various tax credits and deductions to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and various credits for renewable energy and job creation.

It's important to note that tax laws are subject to change, and it's recommended to consult the Massachusetts Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Massachusetts.

Massachusetts (MA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Massachusetts imposes a sales tax and use tax on various goods and services. Here are some key points about the Massachusetts Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Massachusetts is 6.25%. This is the primary tax rate that applies to most taxable transactions in the state.
2. Exemptions: Some items and services may be exempt from Massachusetts' sales tax. Common exemptions include prescription drugs, groceries, clothing, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Massachusetts' sales tax are required to register with the Massachusetts Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Massachusetts has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Massachusetts is also 6.25%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Massachusetts sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Massachusetts are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Massachusetts is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

In summary, Massachusetts does not have additional local or district-specific components for the sales tax and use tax. The tax rates are consistent statewide, and there are no separate local or regional taxes levied on top of the state rates.

Please note that tax laws are subject to change, and it's essential to consult the Massachusetts Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Massachusetts.

Massachusetts - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Massachusetts does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Massachusetts is 6.25%, and this rate applies uniformly to most taxable transactions throughout the state.

Massachusetts does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6.25% state sales tax rate is the only sales tax rate that applies to most taxable sales in Massachusetts.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Massachusetts's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Massachusetts Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Massachusetts.

Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Sales tax / Use tax - Michigan (MI)

Michigan (MI) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Michigan (MI):

1. Sales Tax: Michigan imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. However, there are exemptions for certain items, such as groceries and prescription drugs.
2. Use Tax: Michigan also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Michigan for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Michigan levies an individual income tax on residents and non-residents who earn income in the state. The state has a flat income tax rate of 4.25%.

4. Corporate Income Tax: Michigan imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 6.25% of taxable income.
5. Property Taxes: Michigan imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by municipality.
6. Vehicle Taxes and Fees: Michigan imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a vehicle-specific tax known as the Vehicle Registration Tax.
7. Excise Taxes: Michigan imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
8. Estate Tax: Michigan does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
9. No Local Income Tax: Michigan does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Michigan offers various tax credits and incentives to individuals and businesses, such as the Homestead Property Tax Credit for eligible homeowners and tax incentives for businesses investing in certain areas or creating jobs.

It's important to note that tax laws are subject to change, and it's recommended to consult the Michigan Department of Treasury or a tax professional for the most up-to-date and specific information related to taxes in Michigan.

Michigan (MI) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Michigan imposes a sales tax and use tax on various goods and services. Here are some key points about the Michigan Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Michigan is 6%. Additionally, some local jurisdictions (cities, townships, and counties) may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 6% to 7.75%.
2. Exemptions: Some items and services may be exempt from Michigan's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Michigan's sales tax are required to register with the Michigan Department of Treasury and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales

volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.

4. Online Sales: Michigan has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Michigan is also 6%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Michigan sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Michigan are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Michigan is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Michigan Department of Treasury or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Michigan.

Michigan- Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Michigan does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Michigan is 6%, and this rate applies uniformly to most taxable transactions throughout the state.

Michigan does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 6% state sales tax rate is the only sales tax rate that applies to most taxable sales in Michigan.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Michigan's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Michigan Department of Treasury or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Michigan.

Created with the Standard Edition of HelpNDoc: Effortlessly Create Professional Documentation with HelpNDoc's Clean UI

Mississippi (MS) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Mississippi:

1. Sales Tax: Mississippi imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 7%. Some items, such as groceries and prescription drugs, may be subject to a reduced sales tax rate of 3%.
2. Use Tax: Mississippi also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Mississippi for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Mississippi levies an individual income tax on residents and non-residents who earn income in the state. The state has three income tax brackets, with rates ranging from 3% to 5%.
4. Corporate Income Tax: Mississippi imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 5.0% on the first $5,000 of taxable income and 3.0% on taxable income over $5,000.
5. Franchise Tax: Mississippi imposes a franchise tax on corporations doing business in the state. The tax is based on the company's capital or net worth and is calculated using a specified rate.
6. Property Taxes: Mississippi imposes property taxes on real and personal property, such as land, buildings, and vehicles. Property tax rates are determined at the local level and can vary significantly by county and municipality.
7. Vehicle Taxes and Fees: Mississippi imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and an ad valorem tax based on the vehicle's value.
8. Excise Taxes: Mississippi imposes excise taxes on certain products, such as gasoline, tobacco, and alcohol.
9. Estate Tax: Mississippi does not have its own estate tax. Additionally, it does not have a "pick-up" tax, meaning it does not collect a portion of the federal estate tax paid by the estate.
10. No Local Income Tax: Mississippi does not allow local jurisdictions to impose their own income taxes.

11. Tax Credits and Incentives: Mississippi offers various tax credits and incentives to individuals and businesses, such as the Earned Income Tax Credit (EITC) for low-income individuals and tax incentives for businesses creating jobs and investing in certain areas.

It's important to note that tax laws are subject to change, and it's recommended to consult the Mississippi Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Mississippi.

Mississippi (MS) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Mississippi imposes a sales tax and use tax on various goods and services. Here are some key points about the Mississippi Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Mississippi is 7%. Additionally, some local jurisdictions (cities and counties) may impose additional local sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 7% to 9%.
2. Exemptions: Some items and services may be exempt from Mississippi's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Mississippi's sales tax are required to register with the Mississippi Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Mississippi has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Mississippi is also 7%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Mississippi sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Mississippi are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.

3. Online Purchases: As mentioned above, use tax in Mississippi is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Mississippi Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Mississippi.

Mississippi - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Mississippi does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Mississippi is 7%, and this rate applies uniformly to most taxable transactions throughout the state.

Mississippi does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 7% state sales tax rate is the only sales tax rate that applies to most taxable sales in Mississippi.

It's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Mississippi's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Mississippi Department of Revenue or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Mississippi.

Mississippi - Sales and Use tax - Notes

As of ChatGPT's last update in September 2021, Mississippi imposes a sales and use tax on various goods and services. Here are some key points about the Mississippi Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in Mississippi is 7%. Additionally, some local jurisdictions (cities and counties) may impose additional sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 7% to 9%.

2. Use Tax: Mississippi also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect Mississippi sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.

3. Exemptions: Some items and services may be exempt from Mississippi's sales and use tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.

4. Filing and Payment: Businesses that make sales subject to Mississippi's sales tax are required to register with the Mississippi Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Online Sales: Mississippi has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.
6. Destination-Based Sales Tax: In Mississippi, the sales tax rate is generally based on the destination of the sale. This means that the applicable tax rate is determined by the location where the goods are delivered or services are performed.
7. Special Sales Tax Rates: Some specific items and services may have special sales tax rates in Mississippi. For example, there are specific tax rates for hotel accommodations, car rentals, and certain luxury items.

Please note that tax laws are subject to change, and it's essential to consult the Mississippi Department of Revenue or a tax professional for the most up-to-date and specific information related to sales and use tax in Mississippi.

Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

Sales tax / Use tax - Missouri (MO)

Missouri (MO) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Missouri (MO):

1. Sales Tax: Missouri imposes a state sales tax on the sale of tangible personal property and certain services. The state sales tax rate is 4.225%. However, local jurisdictions (counties and cities) may impose additional sales taxes, resulting in varying total sales tax rates.
2. Use Tax: Use tax is due when tangible personal property is purchased from out-of-state retailers and brought into Missouri for use or consumption. Individuals and businesses are responsible for reporting and remitting use tax on their state income tax return.
3. Income Tax: Missouri levies a state income tax on individuals and corporations. The individual income tax rates are progressive and range from 1.5% to 5.4% depending on income levels.

4. Property Tax: Missouri assesses property taxes on real property (land and buildings) and personal property (vehicles, boats, etc.). Property tax rates and assessment practices can vary by county and local jurisdiction.
5. Corporate Income Tax: Missouri imposes a corporate income tax on corporations doing business in the state. Corporate income tax rates range from 4.0% to 6.25% depending on income levels.
6. Franchise Tax: Missouri imposes a corporate franchise tax on corporations and LLCs doing business in the state. The tax is based on the company's net worth or book value and is calculated using a prescribed formula.
7. Local Taxes: Local governments in Missouri may impose additional taxes, such as local sales taxes and property taxes.
8. Vehicle Taxes: Missouri has a personal property tax on vehicles, based on their value.
9. Online Sales Tax: Missouri has adopted economic nexus laws following the "*Wayfair*" decision, requiring out-of-state sellers to collect and remit sales tax if they meet certain sales or transaction thresholds.
10. Other Taxes: Missouri may have other taxes and fees, such as motor fuel tax, tobacco tax, and more.

Please note that tax laws and regulations can change, and it's important to consult the Missouri Department of Revenue or a tax professional for the most up-to-date and specific information related to the tax system in Missouri.

Missouri (MO) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, here are some key points about the sales tax and use tax in Missouri (MO):

Sales Tax:

- Missouri imposes a state sales tax on the sale of tangible personal property and certain services.
- The state sales tax rate is 4.225%.
- However, local jurisdictions (counties, cities, and special taxing districts) may impose additional sales taxes, resulting in varying total sales tax rates.
- Sales tax is collected from the purchaser at the time of sale, and the seller is responsible for remitting the collected tax to the Missouri Department of Revenue.

Use Tax:

- Use tax is due when tangible personal property is purchased from out-of-state retailers and brought

into Missouri for use or consumption.

- This tax is intended to ensure that items purchased outside the state and used in Missouri are subject to the same taxation as items purchased within the state.
- Individuals and businesses are responsible for reporting and remitting use tax on their state income tax return.
- Use tax rates are the same as the state sales tax rate of 4.225%.

Online Sales Tax (*Wayfair* Decision):

- Following the "*Wayfair*" decision, Missouri has adopted economic nexus laws that require out-of-state sellers to collect and remit sales tax if they meet certain economic thresholds in terms of sales or transactions in the state.
- Remote sellers that exceed these thresholds are required to register with the Missouri Department of Revenue and collect and remit sales tax on their sales to Missouri customers.

Exemptions and Special Rules:

- Missouri provides certain exemptions from sales tax for specific items, such as groceries, prescription medications, and manufacturing equipment.
- Some counties and cities may impose additional taxes on specific goods or services, so it's important to be aware of local regulations.

Please note that tax laws and regulations can change, and it's important to consult the Missouri Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Missouri.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Sales tax / Use tax - Nebraska (NE)

Nebraska (NE) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Nebraska (NE):

1. Sales Tax: Nebraska imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 5.5%. Additionally, local jurisdictions such as

cities and counties can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.

2. Use Tax: Nebraska also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Nebraska for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Nebraska levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 2.46% to 6.84%.
4. Corporate Income Tax: Nebraska imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 5.58% to 7.81% based on taxable income.
5. Property Taxes: Nebraska imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: Nebraska imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a motor vehicle excise tax based on the vehicle's value.
7. Inheritance Tax and Estate Tax: Nebraska has an inheritance tax on certain transfers of property upon a person's death. The tax rates vary based on the relationship between the deceased and the heir. Nebraska does not have an estate tax.
8. No Local Income Tax: Nebraska does not impose a statewide local income tax.
9. Tax Credits and Incentives: Nebraska offers various tax credits and incentives to individuals and businesses, including credits related to renewable energy, job creation, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Nebraska Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Nebraska.

Nebraska (NE) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Nebraska imposes a sales tax and use tax on various goods and services. Here are some key points about the Nebraska Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Nebraska is 5.5%. However, the total sales tax rate can vary due to additional local sales taxes imposed by cities and counties. These local sales taxes can range from 0.5% to 2%, resulting in a combined state and local sales tax rate that can be higher than the

general state rate.

2. Exemptions: Certain items and services may be exempt from Nebraska's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Nebraska's sales tax are required to register with the Nebraska Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Nebraska has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Nebraska is also 5.5%. The use tax is applicable when residents or businesses in Nebraska purchase taxable items from out-of-state sellers who do not collect Nebraska sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Nebraska are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: Use tax in Nebraska is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Nebraska Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Nebraska.

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Sales tax / Use tax - New York (NY)

New York (NY) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in New

York (NY):

1. Sales Tax: New York imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4%. However, when combined with local sales taxes imposed by counties and municipalities, the total sales tax rate can vary and may be higher than the state rate. In some areas, the total sales tax rate can reach up to 8.875%.
2. Use Tax: New York also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into New York for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: New York levies an individual income tax on residents and non-residents who earn income in the state. The state has several income tax brackets with rates ranging from 4% to 8.82% based on income levels.
4. Corporate Income Tax: New York imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates range from 6.5% to 10.9% based on taxable income.
5. Franchise Tax: New York imposes a corporate franchise tax on corporations doing business in the state. The tax is based on the company's entire net income and capital base and is calculated using specified rates.
6. Property Taxes: New York imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
7. Vehicle Taxes and Fees: New York imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a motor vehicle use tax based on the vehicle's value.
8. Estate Tax: New York has its own estate tax, separate from the federal estate tax. The New York estate tax applies to estates with a value above a certain threshold, and the tax rates range from 3.06% to 16%.
9. No Local Income Tax: New York does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Deductions: New York offers various tax credits and deductions to individuals and businesses, such as the Child and Dependent Care Credit, the Earned Income Tax Credit (EITC), and tax incentives for certain industries and job creation.
11. Metropolitan Commuter Transportation Mobility Tax (MCTMT): New York City and some surrounding counties impose an additional payroll tax on certain employers known as the MCTMT. This tax is used to fund mass transit services in the region.

It's important to note that tax laws are subject to change, and it's recommended to consult the New York State Department of Taxation and Finance or a tax professional for the most up-to-date and specific

information related to taxes in New York.

New York (NY) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, New York imposes a sales tax and use tax on various goods and services. Here are some key points about the New York Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in New York is 4%. However, local jurisdictions (counties and cities) can impose additional sales taxes, which means the total sales tax rate can be higher in certain areas. The combined state and local sales tax rates can range from 4% to 8.875%, depending on the specific location.
2. Exemptions: Some items and services may be exempt from New York's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to New York's sales tax are required to register with the New York State Department of Taxation and Finance and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: New York has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in New York is also 4%. The use tax is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect New York sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in New York are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in New York is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the New York State Department

of Taxation and Finance or a tax professional for the most up-to-date and specific information related to sales tax and use tax in New York.

New York - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, New York does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in New York is 4%, and this rate applies uniformly to most taxable transactions throughout the state.

New York does have local sales tax rates, which vary by county and city. Local jurisdictions in New York are allowed to impose additional sales taxes on top of the state rate. The combined state and local sales tax rates can range from 4% to 8.875% or higher, depending on the location.

In addition to the state and local sales taxes, some localities in New York may impose special district taxes or additional taxes on specific items or services. These special district taxes can vary by location and purpose.

For example, in New York City, there is an additional 0.375% Metropolitan Commuter Transportation District (MCTD) tax that applies to sales of certain items and services. This tax is used to fund public transportation services in the metropolitan region.

It's essential to be aware of the specific tax rates applicable in your area and for the goods or services you are buying or selling. For the most current and accurate information regarding New York's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the New York State Department of Taxation and Finance or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in New York.

New York - Sales and Use tax - Notes

As of ChatGPT's last update in September 2021, New York imposes a sales and use tax on various goods and services. Here are some key points about the New York Sales and Use Tax:

1. Sales Tax Rate: The state sales tax rate in New York is 4%. However, local jurisdictions (counties and cities) may impose additional sales taxes, which means the total sales tax rate can be higher in some areas. The combined state and local sales tax rates can range from 4% to 8.875% depending on the specific location.
2. Use Tax: New York also has a use tax, which is applicable when residents or businesses in the state purchase taxable items from out-of-state sellers who do not collect New York sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
3. Exemptions: Some items and services may be exempt from New York's sales and use tax. Common

exemptions include prescription drugs, most groceries, certain medical equipment, and sales to tax-exempt organizations.

4. Filing and Payment: Businesses that make sales subject to New York's sales tax are required to register for a Certificate of Authority from the New York State Department of Taxation and Finance and collect the appropriate tax from their customers. The filing frequency (quarterly or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
5. Online Sales: New York has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.
6. Special Sales Tax Rates: New York has different tax rates for various types of transactions. For instance, there are special rates for hotel occupancy, car rentals, and certain luxury items.
7. Sales Tax Exemption Certificates: Businesses purchasing items for resale or for tax-exempt purposes can use sales tax exemption certificates to avoid paying sales tax on those purchases.

Please note that tax laws are subject to change, and it's essential to consult the New York State Department of Taxation and Finance or a tax professional for the most up-to-date and specific information related to sales and use tax in New York.

New York - State Rate - County/City Rates

New York has a statewide sales tax rate of 4%. However, each county in the state has the option to impose additional local sales tax, which results in varying total sales tax rates across different counties. Here are the details:

Sales Tax in New York Counties

County	*State Rate*	*County/City Rate*	*Total Sales Tax*
Albany	*4%*	*4%*	*8%*
Allegany	*4%*	*4.5%*	*8.5%*
Bronx	*4%*	*4.875%*	*8.875%*
Broome	*4%*	*4%*	*8%*

Cattaraugus	*4%*	*4%*	*8%*
Cayuga	*4%*	*4%*	*8%*
Chautauqua	*4%*	*4%*	*8%*
Chemung	*4%*	*4%*	*8%*
Chenango	*4%*	*4%*	*8%*
Clinton	*4%*	*4%*	*8%*
Columbia	*4%*	*4%*	*8%*
Cortland	*4%*	*4%*	*8%*
Delaware	*4%*	*4%*	*8%*
Dutchess	*4%*	*4.125%*	*8.125%*
Erie	*4%*	*4.75%*	*8.75%*
Essex	*4%*	*4%*	*8%*
Franklin	*4%*	*4%*	*8%*
Fulton	*4%*	*4%*	*8%*
Genesee	*4%*	*4%*	*8%*
Greene	*4%*	*4%*	*8%*
Hamilton	*4%*	*4%*	*8%*
Herkimer	*4%*	*4.25%*	*8.25%*
Jefferson	*4%*	*4%*	*8%*
Kings (Brooklyn)	*4%*	*4.875%*	*8.875%*
Lewis	*4%*	*4%*	*8%*

Livingston	*4%*	*4%*	*8%*
Madison	*4%*	*4%*	*8%*
Monroe	*4%*	*4%*	*8%*
Montgomery	*4%*	*4%*	*8%*
Nassau	*4%*	*4.625%*	*8.625%*
New York (Manhattan)	*4%*	*4.875%*	*8.875%*
Niagara	*4%*	*4%*	*8%*
Oneida	*4%*	*4.75%*	*8.75%*
Onondaga	*4%*	*4%*	*8%*
Ontario	*4%*	*3.5%*	*7.5%*
Orange	*4%*	*4.125%*	*8.125%*
Orleans	*4%*	*4%*	*8%*
Oswego	*4%*	*4%*	*8%*
Otsego	*4%*	*4%*	*8%*
Putnam	*4%*	*4.375%*	*8.375%*
Queens	*4%*	*4.875%*	*8.875%*
Rensselaer	*4%*	*4%*	*8%*
Richmond (Staten Island)	*4%*	*4.875%*	*8.875%*
Rockland	*4%*	*4.375%*	*8.375%*
Saratoga	*4%*	*3%*	*7%*
Schenectady	*4%*	*4%*	*8%*

Schoharie	*4%*	*4%*	*8%*
Schuyler	*4%*	*4%*	*8%*
Seneca	*4%*	*4%*	*8%*
Steuben	*4%*	*4%*	*8%*
Suffolk	*4%*	*4.625%*	*8.625%*
Sullivan	*4%*	*4%*	*8%*
Tioga	*4%*	*4%*	*8%*
Tompkins	*4%*	*4%*	*8%*
Ulster	*4%*	*4%*	*8%*
Warren	*4%*	*3%*	*7%*
Washington	*4%*	*3%*	*7%*
Wayne	*4%*	*4%*	*8%*
Westchester	*4%*	*4.375%*	*8.375%*
Wyoming	*4%*	*4%*	*8%*
Yates	*4%*	*4%*	*8%*

The state sales tax rate in New York is 4.000%. With local taxes, the total sales tax rate is between 4.000% and 8.875%.

Created with the Standard Edition of HelpNDoc: Easily convert your WinHelp HLP help files to CHM with HelpNDoc's step-by-step guide

Sales tax / Use tax - North Carolina (NC)

North Carolina (NC) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in North Carolina (NC):

1. Sales Tax: North Carolina imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4.75%. Additionally, local jurisdictions such as counties and municipalities can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: North Carolina also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into North Carolina for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: North Carolina levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 5.25% to 5.499%.
4. Corporate Income Tax: North Carolina imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 2.5% for the 2021 tax year and will decrease to 2.0% for the 2022 tax year.
5. Franchise Tax: North Carolina imposes a franchise tax on corporations and LLCs registered in the state. The tax is based on the company's net worth or book value and is calculated using specified rates.
6. Property Taxes: North Carolina imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
7. Vehicle Taxes and Fees: North Carolina imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a highway use tax based on the vehicle's value.
8. Excise Taxes: North Carolina imposes excise taxes on various items such as tobacco products, alcoholic beverages, gasoline, and motor fuels. The rates for these taxes can vary.
9. Inheritance Tax and Estate Tax: North Carolina phased out its estate tax, and it does not have an inheritance tax.
10. Local Income Tax: North Carolina does not impose a statewide local income tax.
11. Local Taxes: In addition to state taxes, local governments in North Carolina can impose additional taxes or fees, such as local sales taxes, property taxes, and other local assessments.
12. Tax Credits and Incentives: North Carolina offers various tax credits and incentives to individuals and

businesses, including credits related to job creation, research and development, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the North Carolina Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in North Carolina.

North Carolina (NC) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, North Carolina imposes a sales tax and use tax on various goods and services. Here are some key points about the North Carolina Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in North Carolina is 4.75%. Additionally, there are local sales taxes imposed by counties and municipalities, which can result in varying total sales tax rates across the state.
- Exemptions: Some items and services may be exempt from North Carolina's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to North Carolina's sales tax are required to register with the North Carolina Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: North Carolina has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in North Carolina is also 4.75%. The use tax is applicable when residents or businesses in North Carolina purchase taxable items from out-of-state sellers who do not collect North Carolina sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in North Carolina are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in North Carolina is relevant to out-of-state purchases and online

purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the North Carolina Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in North Carolina.

North Carolina (NC) - Sales Tax and Use Tax - Notes

As of ChatGPT's last update in September 2021, here's information about North Carolina's sales tax and use tax:

- Sales Tax: North Carolina imposes a general sales tax on most retail sales of tangible personal property and certain services. The state's base sales tax rate is 4.75%. However, the actual total sales tax rate can be higher due to additional local sales taxes imposed by counties and municipalities. Local sales tax rates can vary across different areas of the state.

  It's important to note that North Carolina has a few exemptions from the sales tax. Common exemptions include prescription medications, most groceries, and some types of medical equipment. However, the specifics of exemptions can vary, and it's advised to check with the North Carolina Department of Revenue or a tax professional for accurate and up-to-date information.

- Use Tax: Use tax is a companion to the sales tax and is designed to ensure that individuals and businesses don't avoid paying sales tax by making purchases from out-of-state vendors that do not collect North Carolina sales tax. If you buy taxable items for use in North Carolina from an out-of-state vendor and the vendor doesn't collect North Carolina sales tax, you are generally required to report and pay use tax on those purchases. Use tax is usually at the same rate as the state sales tax.

In practical terms, use tax is often applicable to online purchases, catalog purchases, or purchases made out of state. Individuals and businesses are expected to self-report and remit the use tax when applicable.

It's important to keep in mind that tax laws and rates can change, so for the most current and accurate information about North Carolina's sales tax and use tax, you should consult the North Carolina Department of Revenue or seek advice from a tax professional.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Sales tax / Use tax - North Dakota (ND)

North Dakota (ND) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in North Dakota (ND):

1. Sales Tax: North Dakota imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 5%. Additionally, local jurisdictions such as cities and counties can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: North Dakota also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into North Dakota for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: North Dakota levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 1.1% to 2.9%.
4. Corporate Income Tax: North Dakota imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 4.31%.
5. Property Taxes: North Dakota imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: North Dakota imposes various taxes and fees on motor vehicles, including excise taxes based on the vehicle's value, registration fees, and a motor vehicle excise tax.
7. Excise Taxes: The state imposes excise taxes on various items, including cigarettes, tobacco products, and alcoholic beverages.
8. Inheritance Tax and Estate Tax: North Dakota does not have an inheritance tax or an estate tax.
9. Local Income Tax: North Dakota does not impose a statewide local income tax.
10. Tax Credits and Incentives: North Dakota offers various tax credits and incentives to individuals and businesses, including credits related to research and development, job creation, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the North Dakota Office of State Tax Commissioner or a tax professional for the most up-to-date and specific information related to taxes in North Dakota.

North Dakota (ND) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, North Dakota imposes a sales tax and use tax on various goods and services. Here are some key points about the North Dakota Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in North Dakota is 5%. Additionally, there are local sales taxes imposed by cities and counties, which can result in varying total sales tax rates across the state.
- Exemptions: Some items and services may be exempt from North Dakota's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to North Dakota's sales tax are required to register with the North Dakota Office of State Tax Commissioner and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: North Dakota has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in North Dakota is also 5%. The use tax is applicable when residents or businesses in North Dakota purchase taxable items from out-of-state sellers who do not collect North Dakota sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in North Dakota are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in North Dakota is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the North Dakota Office of State Tax Commissioner or a tax professional for the most up-to-date and specific information related to sales tax and use tax in North Dakota.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Sales tax / Use tax - Ohio (OH)

Ohio (OH) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Ohio (OH):

1. Sales Tax: Ohio imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 5.75%. Additionally, local jurisdictions such as counties and municipalities can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Ohio also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Ohio for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Ohio levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 0.5% to 4.797%.
4. Corporate Income Tax: Ohio does impose a corporate income tax on corporations doing business in the state. The corporate income tax rate is a flat rate of 10%. This tax is calculated based on the net income of corporations.
5. Commercial Activity Tax (CAT): Ohio also imposes a commercial activity tax (CAT) on businesses conducting business in the state. The CAT is based on the gross receipts of the business, rather than its net income. The CAT has a minimum tax threshold, which means that businesses with gross receipts below a certain level may be exempt from paying the tax.
6. Property Taxes: Ohio imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and school district.
7. Vehicle Taxes and Fees: Ohio imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a vehicle excise tax based on the vehicle's value.
8. Excise Taxes: The state imposes excise taxes on items such as cigarettes, tobacco products, and motor fuels.
9. Inheritance Tax and Estate Tax: Ohio phased out its estate tax in 2013, and it does not have an

inheritance tax.

10. Local Income Tax: Some local jurisdictions in Ohio impose local income taxes on earned income. The rates and rules vary by locality.
11. Municipal Income Tax: Many cities in Ohio levy their own municipal income tax on individuals who live or work within their city limits. The rates and rules can vary widely from one municipality to another.
12. School District Income Tax: Some school districts in Ohio have their own income tax rates, which are collected alongside the state and municipal income taxes.
13. Tax Credits and Incentives: Ohio offers various tax credits and incentives to individuals and businesses, including credits related to job creation, research and development, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Ohio Department of Taxation or a tax professional for the most up-to-date and specific information related to taxes in Ohio.

Ohio (OH) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Ohio imposes a sales tax and use tax on various goods and services. Here are some key points about the Ohio Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Ohio is 5.75%. Additionally, there are county and transit authority sales taxes that can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Ohio's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Ohio's sales tax are required to register with the Ohio Department of Taxation and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Ohio has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Ohio is also 5.75%. The use tax is applicable when residents or businesses in Ohio purchase taxable items from out-of-state sellers who do not collect Ohio sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.

- Filing and Payment: Individuals and businesses in Ohio are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Ohio is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Ohio Department of Taxation or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Ohio.

Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Sales tax / Use tax - Oklahoma (OK)

Oklahoma (OK) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Oklahoma (OK):

1. Sales Tax: Oklahoma imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4.5%. Additionally, local jurisdictions such as cities and counties can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Oklahoma also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Oklahoma for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Oklahoma levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 0.5% to 5%.
4. Corporate Income Tax: Oklahoma imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 6%.
5. Franchise Tax: Oklahoma imposes a corporate franchise tax on corporations doing business in the state. The tax is based on the company's net worth or book value and is calculated using specified rates.

6. Property Taxes: Oklahoma imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and school district.
7. Vehicle Taxes and Fees: Oklahoma imposes various taxes and fees on motor vehicles, including excise taxes based on the vehicle's value, registration fees, and a 3.25% excise tax on the purchase price of vehicles.
8. Excise Taxes: The state imposes excise taxes on items such as gasoline, tobacco products, and alcoholic beverages.
9. Inheritance Tax and Estate Tax: Oklahoma does not have an inheritance tax or an estate tax.
10. No Local Income Tax: Oklahoma does not allow local jurisdictions to impose their own income taxes.
11. Tax Credits and Incentives: Oklahoma offers various tax credits and incentives to individuals and businesses, including credits related to job creation, research and development, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Oklahoma Tax Commission or a tax professional for the most up-to-date and specific information related to taxes in Oklahoma.

Oklahoma (OK) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Oklahoma imposes a sales tax and use tax on various goods and services. Here are some key points about the Oklahoma Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Oklahoma is 4.5%. Additionally, local sales taxes imposed by cities and counties can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Oklahoma's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Oklahoma's sales tax are required to register with the Oklahoma Tax Commission and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Oklahoma has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Oklahoma is also 4.5%. The use tax is applicable when residents or businesses in Oklahoma purchase taxable items from out-of-state sellers who do not collect Oklahoma sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Oklahoma are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Oklahoma is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Oklahoma Tax Commission or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Oklahoma.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

Sales tax / Use tax - Rhode Island (RI)

Rhode Island (RI) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Rhode Island (RI):

1. Sales Tax: Rhode Island imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 7%. However, there are exemptions for certain items, such as groceries and prescription drugs.
2. Use Tax: Rhode Island also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Rhode Island for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Rhode Island levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 3.75% to 5.99% based on income levels.
4. Corporate Income Tax: Rhode Island imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 3.5% to 9.0% based on taxable

income.

5. Property Taxes: Rhode Island imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by municipality.
6. Vehicle Taxes and Fees: Rhode Island imposes various taxes and fees on motor vehicles, including excise tax based on the vehicle's value, registration fees, and a vehicle-specific tax known as the Vehicle Value Commission (VVC) tax.
7. Estate Tax: Rhode Island has its own estate tax, separate from the federal estate tax. The Rhode Island estate tax applies to estates with a value above a certain threshold, and the tax rates range from 0.8% to 16%.
8. No Local Income Tax: Rhode Island does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: Rhode Island offers various tax credits and incentives to individuals and businesses, such as the Rhode Island Earned Income Tax Credit (RI EITC) for low-income individuals and tax incentives for businesses investing in certain areas or creating jobs.

It's important to note that tax laws are subject to change, and it's recommended to consult the Rhode Island Division of Taxation or a tax professional for the most up-to-date and specific information related to taxes in Rhode Island.

Rhode Island (RI) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Rhode Island imposes a sales tax and use tax on various goods and services. Here are some key points about the Rhode Island Sales Tax and Use Tax:

Sales Tax:

1. Sales Tax Rate: The state sales tax rate in Rhode Island is 7%. This is the primary tax rate that applies to most taxable transactions in the state.
2. Exemptions: Some items and services may be exempt from Rhode Island's sales tax. Common exemptions include prescription drugs, groceries, certain medical equipment, and sales to tax-exempt organizations.
3. Filing and Payment: Businesses that make sales subject to Rhode Island's sales tax are required to register with the Rhode Island Division of Taxation and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
4. Online Sales: Rhode Island has adopted economic nexus laws for online sales. This means that

businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

1. Use Tax Rate: The use tax rate in Rhode Island is also 7%. The use tax is applicable when residents or businesses in Rhode Island purchase taxable items from out-of-state sellers who do not collect Rhode Island sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
2. Filing and Payment: Individuals and businesses in Rhode Island are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
3. Online Purchases: As mentioned above, use tax in Rhode Island is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Rhode Island Division of Taxation or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Rhode Island.

Rhode Island - Special Sales Tax Rates

As of ChatGPT's last update in September 2021, Rhode Island does not have any special sales tax rates in addition to the standard state sales tax rate. The state sales tax rate in Rhode Island is 7%, and this rate applies uniformly to most taxable transactions throughout the state.

Unlike some other states, Rhode Island does not have local option sales taxes or special district taxes that impose additional sales taxes on specific goods, services, or locations. Therefore, the 7% state sales tax rate is the only sales tax rate that applies to most taxable sales in Rhode Island.

However, it's important to note that tax laws can change, and it's possible that new legislation or updates may have been implemented since my last update. For the most current and accurate information regarding Rhode Island's sales tax rates, exemptions, and any other relevant tax regulations, it's recommended to consult the Rhode Island Division of Taxation or a tax professional. They can provide the latest information on sales tax rates and any specific local taxes or exemptions that may be applicable in Rhode Island.

Rhode Island - Sales and Use tax - Notes

Information about Rhode Island's sales tax and use tax.

1. Sales Tax in Rhode Island: Rhode Island imposes a 7% sales tax on the retail sale, rental, or lease of many goods and services. Retail sales refer to sales where the property or service sold will be used and not resold in the regular course of business. Retailers are responsible for collecting the sales tax from their customers and remitting it directly to the state.

   In addition to the sales tax, there is also a 6% hotel tax on the rental of rooms in hotels, motels, or lodging houses.

2. Use Tax in Rhode Island: Rhode Island also has a use tax, which is imposed at 7% on the storage, use, or consumption of tangible personal property in the state. The use tax applies when property is purchased from a retailer who is not authorized to collect the sales tax or when the tax has not been paid on the property.

For example, if a person purchases a taxable item from an out-of-state retailer that does not collect Rhode Island sales tax, they are required to pay the use tax directly to the state. The use tax is also applicable in cases of casual sales, such as when a motor vehicle is purchased from a non-licensed dealer.

It's important to note that the use tax rate is the same as the sales tax rate (7%), and it is intended to ensure that individuals and businesses pay the appropriate amount of tax on purchases, regardless of where the seller is located.

Exemptions may apply to certain casual sales, such as those made between members of the immediate family.

As with any tax matters, individuals, businesses, and retailers in Rhode Island should comply with the relevant tax laws and regulations, and when in doubt, seek advice from a tax professional to ensure proper compliance.

Created with the Standard Edition of HelpNDoc: Transform Your Word Document into a Professional eBook with HelpNDoc

Sales tax / Use tax - Pennsylvania (PA)

Pennsylvania (PA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Pennsylvania (PA):

1. Sales Tax: Pennsylvania imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. However, certain items such as food, clothing, prescription drugs, and some services may be exempt from the sales tax.
2. Use Tax: Pennsylvania also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Pennsylvania for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Pennsylvania levies an individual income tax on residents and non-residents who earn income in the state. The state has a flat income tax rate of 3.07%.
4. Corporate Income Tax: Pennsylvania imposes a corporate net income tax on corporations conducting business in the state. The corporate net income tax rate is 9.99% of net income.
5. Property Taxes: Pennsylvania imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by school district and municipality.
6. Vehicle Taxes and Fees: Pennsylvania imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a motor vehicle excise tax.
7. Inheritance Tax and Estate Tax: Pennsylvania imposes an inheritance tax on the transfer of property upon a person's death. The tax rates vary based on the relationship between the deceased and the heir. Pennsylvania does not have an estate tax.
8. No Local Income Tax: Pennsylvania allows local jurisdictions to impose their own local income taxes on earned income, but not all areas have local income taxes.
9. Tax Credits and Incentives: Pennsylvania offers various tax credits and incentives to individuals and businesses, including credits related to education, historic preservation, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Pennsylvania Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Pennsylvania.

Pennsylvania (PA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Pennsylvania imposes a sales tax and use tax on various goods and services. Here are some key points about the Pennsylvania Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Pennsylvania is 6%. Additionally, there may be local sales taxes imposed by certain counties and municipalities, which can result in varying total sales tax rates in

different areas of the state.

- Exemptions: Some items and services may be exempt from Pennsylvania's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Pennsylvania's sales tax are required to register with the Pennsylvania Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Pennsylvania has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Pennsylvania is also 6%. The use tax is applicable when residents or businesses in Pennsylvania purchase taxable items from out-of-state sellers who do not collect Pennsylvania sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Pennsylvania are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Pennsylvania is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Pennsylvania Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Pennsylvania.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Sales tax / Use tax - South Carolina (SC)

South Carolina (SC) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in South Carolina (SC):

1. Sales Tax: South Carolina imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. Additionally, local jurisdictions such as counties and municipalities can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: South Carolina also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into South Carolina for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: South Carolina levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 0% to 7%.
4. Corporate Income Tax: South Carolina imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 5%.
5. Property Taxes: South Carolina imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
6. Vehicle Taxes and Fees: South Carolina imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a property tax on vehicles.
7. Excise Taxes: The state imposes excise taxes on items such as gasoline, cigarettes, and alcohol.
8. Inheritance Tax and Estate Tax: South Carolina does not have an inheritance tax or an estate tax.
9. Local Income Tax: South Carolina does not impose a statewide local income tax.
10. Tax Credits and Incentives: South Carolina offers various tax credits and incentives to individuals and businesses, including credits related to job creation, research and development, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the South Carolina Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in South Carolina.

South Carolina (SC) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, South Carolina imposes a sales tax and use tax on various

goods and services. Here are some key points about the South Carolina Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in South Carolina is 6%. Additionally, local jurisdictions such as counties and municipalities can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from South Carolina's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to South Carolina's sales tax are required to register with the South Carolina Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: South Carolina has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in South Carolina is also 6%. The use tax is applicable when residents or businesses in South Carolina purchase taxable items from out-of-state sellers who do not collect South Carolina sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in South Carolina are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in South Carolina is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the South Carolina Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in South Carolina.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Sales tax / Use tax - South Dakota (SD)

South Dakota (SD) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in South Dakota (SD):

1. Sales Tax: South Dakota imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4.5%. However, certain local jurisdictions can add their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: South Dakota also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into South Dakota for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. No Individual Income Tax: South Dakota does not impose a state-level individual income tax on earned income. This absence of an income tax is one of the key features of South Dakota's tax system.
4. No Corporate Income Tax: South Dakota does not impose a corporate income tax on corporations conducting business in the state.
5. Property Taxes: South Dakota imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county.
6. Vehicle Taxes and Fees: South Dakota imposes various taxes and fees on motor vehicles, including motor vehicle excise taxes, registration fees, and a 4% motor vehicle excise tax on the purchase price of vehicles.
7. Inheritance Tax and Estate Tax: South Dakota does not have an inheritance tax or an estate tax.
8. No Local Income Tax: South Dakota does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: South Dakota offers various tax incentives to businesses, including credits related to job creation, research and development, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the South Dakota Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in South Dakota.

South Dakota (SD) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, South Dakota imposes a sales tax and use tax on various

goods and services. Here are some key points about the South Dakota Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in South Dakota is 4.5%. Additionally, there may be local sales taxes imposed by municipalities, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from South Dakota's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to South Dakota's sales tax are required to register with the South Dakota Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: South Dakota has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in South Dakota is also 4.5%. The use tax is applicable when residents or businesses in South Dakota purchase taxable items from out-of-state sellers who do not collect South Dakota sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in South Dakota are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in South Dakota is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the South Dakota Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in South Dakota.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Sales tax / Use tax - Tennessee (TN)

Tennessee (TN) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Tennessee (TN):

1. Sales Tax: Tennessee imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 7%. Additionally, local jurisdictions such as counties and municipalities can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Tennessee also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Tennessee for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Tennessee does not impose a state-level individual income tax on earned income. However, it does impose a tax on certain types of income, such as interest and dividends. This tax is known as the "Hall Income Tax," and the rate is 1%.
4. Corporate Income Tax: Tennessee imposes a franchise and excise tax on corporations conducting business in the state. The tax is calculated based on a business's net earnings and tangible property.
5. Franchise Tax: Tennessee imposes a franchise tax on corporations and LLCs registered in the state. The tax is based on the company's net worth or book value and is calculated using specified rates.
6. Property Taxes: Tennessee imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and municipality.
7. Vehicle Taxes and Fees: Tennessee imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a motor vehicle privilege tax.
8. Inheritance Tax and Estate Tax: Tennessee does not have an inheritance tax or an estate tax.
9. No Local Income Tax: Tennessee does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Tennessee offers various tax credits and incentives to businesses, including credits related to job creation, research and development, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Tennessee Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Tennessee.

Tennessee (TN) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Tennessee imposes a sales tax and use tax on various goods and services. Here are some key points about the Tennessee Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Tennessee is 7%. Additionally, there may be local sales taxes imposed by municipalities and counties, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Tennessee's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Tennessee's sales tax are required to register with the Tennessee Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Tennessee has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Tennessee is also 7%. The use tax is applicable when residents or businesses in Tennessee purchase taxable items from out-of-state sellers who do not collect Tennessee sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Tennessee are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Tennessee is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Tennessee Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Tennessee.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Sales tax / Use tax - Texas (TX)

Texas (TX) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Texas (TX):

1. Sales Tax: Texas imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.25%. Additionally, local jurisdictions such as cities, counties, and special purpose districts can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state. The total sales tax rate can vary widely across the state.
2. Use Tax: Texas also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Texas for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Texas does not impose a state-level individual income tax on residents' earned income. This absence of an income tax is one of the key features of Texas' tax system.
4. Corporate Income Tax: Texas imposes a franchise tax on corporations conducting business in the state. The franchise tax is calculated based on a business's margin, with different rates for different types of businesses.
5. Franchise Tax: Texas imposes a franchise tax, also known as the "margin tax," on corporations and LLCs doing business in the state. The tax is based on the company's margin or apportioned revenue, and the calculation varies based on the entity's classification and business activities.
6. Property Taxes: Texas imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county and school district.
7. Vehicle Taxes and Fees: Texas imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and a motor vehicle sales and use tax.
8. Inheritance Tax and Estate Tax: Texas does not have an inheritance tax or an estate tax.
9. No Local Income Tax: Texas does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Texas offers various tax incentives to businesses, including credits related to research and development, job creation, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Texas Comptroller of Public Accounts or a tax professional for the most up-to-date and specific information related to taxes in Texas.

Texas (TX) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Texas imposes a sales tax and use tax on various goods and services. Here are some key points about the Texas Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Texas is 6.25%. Additionally, there may be local sales taxes imposed by cities, counties, and special purpose districts, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Texas's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Texas's sales tax are required to register with the Texas Comptroller of Public Accounts and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Texas has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Texas is also 6.25%. The use tax is applicable when residents or businesses in Texas purchase taxable items from out-of-state sellers who do not collect Texas sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Texas are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Texas is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Texas Comptroller of Public Accounts or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Texas.

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Sales tax / Use tax - Utah (UT)

Utah (UT) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Utah (UT):

1. Sales Tax: Utah imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 4.85%. Additionally, local jurisdictions such as counties and municipalities can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: Utah also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Utah for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Utah levies an individual income tax on residents and non-residents who earn income in the state. The state has a flat income tax rate of 4.95%.
4. Corporate Income Tax: Utah imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is also 4.95%.
5. Property Taxes: Utah imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county.
6. Vehicle Taxes and Fees: Utah imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and property taxes on vehicles.
7. Inheritance Tax and Estate Tax: Utah does not have an inheritance tax or an estate tax.
8. No Local Income Tax: Utah does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: Utah offers various tax credits and incentives to individuals and businesses, including credits related to education, renewable energy, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Utah State Tax Commission or a tax professional for the most up-to-date and specific information related to taxes in

Utah.

Utah (UT) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Utah imposes a sales tax and use tax on various goods and services. Here are some key points about the Utah Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Utah is 4.85%. Additionally, there may be local sales taxes imposed by counties and municipalities, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Utah's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Utah's sales tax are required to register with the Utah State Tax Commission and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Utah has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Utah is also 4.85%. The use tax is applicable when residents or businesses in Utah purchase taxable items from out-of-state sellers who do not collect Utah sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Utah are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Utah is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Utah State Tax Commission or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Utah.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Sales tax / Use tax - Vermont (VT)

Vermont (VT) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Vermont (VT):

1. Sales Tax: Vermont does not impose a state-level sales tax. As a result, there is no general sales tax imposed on the retail sale of tangible personal property or services at the state level.
2. Use Tax: Since Vermont does not have a state sales tax, there is no corresponding use tax imposed on the purchase of goods brought into the state.
3. Individual Income Tax: Vermont levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 3.35% to 8.75% based on income levels.
4. Corporate Income Tax: Vermont imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 6.0% to 8.5% based on taxable income.
5. Property Taxes: Vermont imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by municipality.
6. Vehicle Taxes and Fees: Vermont imposes various taxes and fees on motor vehicles, including a purchase and use tax based on the vehicle's purchase price, registration fees, and a local option tax.
7. Inheritance Tax and Estate Tax: Vermont has an estate tax that applies to estates with a value exceeding a certain threshold. The tax rates range from 0.8% to 16%. Vermont does not have an inheritance tax.
8. No Local Income Tax: Vermont does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: Vermont offers various tax credits and incentives to individuals and businesses, including credits related to child care, energy efficiency, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Vermont Department of Taxes or a tax professional for the most up-to-date and specific information related to taxes in Vermont.

Vermont (VT) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Vermont imposes a sales tax and use tax on various goods and services. Here are some key points about the Vermont Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Vermont is 6%. Additionally, there may be local option taxes imposed by municipalities, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Vermont's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Vermont's sales tax are required to register with the Vermont Department of Taxes and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Vermont has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Vermont is also 6%. The use tax is applicable when residents or businesses in Vermont purchase taxable items from out-of-state sellers who do not collect Vermont sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Vermont are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Vermont is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Vermont Department of Taxes or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Vermont.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Virginia (VA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Virginia:

1. Sales Tax:
    - Virginia imposes a state sales tax on most retail sales, leases, and rentals of goods, as well as some services.
    - The general state sales tax rate is 4.3%, and additional local sales taxes may apply in certain localities.
2. Use Tax:
    - Use tax is applicable when sales tax was not paid at the time of purchase, such as for online purchases from out-of-state sellers.
    - It is the responsibility of individuals and businesses to report and remit use tax.
3. Income Tax:
    - Virginia has a progressive income tax system with tax rates ranging from 2% to 5.75%.
    - Income tax is levied on both individuals and corporations.
4. Property Tax:
    - Local governments in Virginia assess property taxes on real property (land and buildings) and personal property (vehicles, boats, etc.).
    - Property tax rates and assessments vary by locality.
5. Corporate Income Tax:
    - Virginia levies a corporate income tax on corporations doing business in the state.
    - Corporate income tax rates vary based on income levels and can range from 2.0% to 6.75%.
6. Estate Tax:
    - Virginia had an estate tax, but it was phased out, and it's no longer applicable as of January 1, 2008.

7. Local Taxes:
    - Localities may impose additional taxes, such as local sales taxes, local business taxes, and more.
8. Business License Tax:
    - Virginia localities may impose business license taxes on businesses operating within their jurisdictions.
9. Vehicle Taxes:
    - Virginia has a personal property tax on vehicles, which is assessed by local governments based on the value of the vehicle.
10. Online Sales Tax:
    - Virginia has adopted economic nexus laws for online sales, requiring out-of-state sellers to collect and remit sales tax if they meet certain sales thresholds.
    - Virginia follows the US Supreme Court's "Wayfair" decision and may require remote sellers to collect and remit sales tax on online transactions.

Please keep in mind that tax laws and regulations can change, so it's important to consult the Virginia Department of Taxation or a tax professional for the most up-to-date and specific information related to the tax system in Virginia.

Virginia (VA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, here are some key points about the sales tax and use tax in Virginia:

Sales Tax:

- Virginia imposes a state sales tax on retail sales, leases, and rentals of most goods and some services.
- The general state sales tax rate is 4.3%. However, certain localities may impose additional local sales taxes, which can vary.
- Sales tax is collected at the point of sale, and businesses are required to collect and remit the appropriate amount to the Virginia Department of Taxation.
- Some items are exempt from sales tax, such as prescription drugs, groceries, and certain medical equipment.

Use Tax:

- Use tax is due when Virginia sales tax was not paid at the time of purchase, such as when purchasing items online from out-of-state sellers.
- If you buy a taxable item from another state and use it in Virginia, you may owe use tax on that purchase.
- Individuals are responsible for reporting and paying use tax on their individual income tax returns.
- Businesses are also required to remit use tax on their sales and purchases.

Please note that tax laws can change, and it's important to consult the Virginia Department of Taxation or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Virginia.

Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

Sales tax / Use tax - Washington (WA)

Washington (WA) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Washington (WA):

1. Sales Tax: Washington imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6.5%. Additionally, local jurisdictions such as cities and counties can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state. The total sales tax rate can vary widely across the state.
2. Use Tax: Washington also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Washington for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Business and Occupation (B&O) Tax: Washington has a unique tax structure for businesses known as the Business and Occupation (B&O) tax. It is levied on the gross receipts of businesses and varies depending on the type of business activity. Different rates apply to different industries.
4. Property Taxes: Washington imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county. The property tax system also includes measures to limit annual increases in assessed values.

5. Vehicle Taxes and Fees: Washington imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, excise taxes based on the vehicle's value, and registration fees.
6. No Individual Income Tax: Washington does not impose a state-level individual income tax on residents' earned income. This absence of an income tax is one of the key features of Washington's tax system.
7. No Corporate Income Tax: Washington does not impose a corporate income tax on corporations conducting business in the state.
8. Inheritance Tax and Estate Tax: Washington does not have an inheritance tax or an estate tax.
9. No Local Income Tax: Washington does not allow local jurisdictions to impose their own income taxes.
10. Tax Credits and Incentives: Washington offers various tax incentives to businesses, including credits related to research and development, job creation, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Washington Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Washington.

Washington (WA) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Washington imposes a sales tax and use tax on various goods and services. Here are some key points about the Washington Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Washington is 6.5%. Additionally, there may be local sales taxes imposed by cities, counties, and other local jurisdictions, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Washington's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to Washington's sales tax are required to register with the Washington Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Washington has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical

presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Washington is also 6.5%. The use tax is applicable when residents or businesses in Washington purchase taxable items from out-of-state sellers who do not collect Washington sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Washington are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Washington is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Washington Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Washington.

Created with the Standard Edition of HelpNDoc: Free EPub producer

Sales tax / Use tax - West Virginia (WV)

West Virginia (WV) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in West Virginia (WV):

1. Sales Tax: West Virginia imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 6%. Additionally, local jurisdictions such as municipalities and counties can impose their own local sales taxes, resulting in varying total sales tax rates in different areas of the state.
2. Use Tax: West Virginia also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into West Virginia for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: West Virginia levies an individual income tax on residents and non-residents

who earn income in the state. The state has a progressive income tax system with tax rates ranging from 3% to 6.5% based on income levels.

4. Corporate Income Tax: West Virginia imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rate is 6.5% of net income.
5. Property Taxes: West Virginia imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by county.
6. Vehicle Taxes and Fees: West Virginia imposes various taxes and fees on motor vehicles, including sales tax on vehicle purchases, registration fees, and property tax on vehicles.
7. Inheritance Tax and Estate Tax: West Virginia does not impose an inheritance tax, but it does have an estate tax. The state's estate tax is separate from the federal estate tax and applies to estates with a value exceeding a certain threshold.
8. No Local Income Tax: West Virginia does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: West Virginia offers various tax credits and incentives to individuals and businesses, including credits related to child care, education, and economic development.

It's important to note that tax laws are subject to change, and it's recommended to consult the West Virginia State Tax Department or a tax professional for the most up-to-date and specific information related to taxes in West Virginia.

West Virginia (WV) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, West Virginia imposes a sales tax and use tax on various goods and services. Here are some key points about the West Virginia Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in West Virginia is 6%. Additionally, there may be local sales taxes imposed by municipalities and counties, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from West Virginia's sales tax. Common exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.
- Filing and Payment: Businesses that make sales subject to West Virginia's sales tax are required to register with the West Virginia State Tax Department and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding

tax collected.

- Online Sales: West Virginia has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in West Virginia is also 6%. The use tax is applicable when residents or businesses in West Virginia purchase taxable items from out-of-state sellers who do not collect West Virginia sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in West Virginia are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in West Virginia is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the West Virginia State Tax Department or a tax professional for the most up-to-date and specific information related to sales tax and use tax in West Virginia.

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

Sales tax / Use tax - Wisconsin (WI)

Wisconsin (WI) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Wisconsin (WI):

1. Sales Tax: Wisconsin imposes a state-level sales tax on the retail sale of tangible personal property and certain services. The general state sales tax rate is 5%. However, there may be additional local sales taxes imposed by counties and municipalities, resulting in varying total sales tax rates in different areas of the state.

2. Use Tax: Wisconsin also has a use tax, which is applied when tangible personal property is purchased out-of-state and brought into Wisconsin for use, storage, or consumption. If sales tax was not paid at the time of purchase, the purchaser owes use tax on the value of the property.
3. Individual Income Tax: Wisconsin levies an individual income tax on residents and non-residents who earn income in the state. The state has a progressive income tax system with tax rates ranging from 3.54% to 7.65% based on income levels.
4. Corporate Income Tax: Wisconsin imposes a corporate income tax on corporations conducting business in the state. The corporate income tax rates range from 4.0% to 7.9% based on taxable income.
5. Property Taxes: Wisconsin imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level and can vary significantly by municipality.
6. Vehicle Taxes and Fees: Wisconsin imposes various taxes and fees on motor vehicles, including registration fees, license plate fees, and a vehicle-specific tax known as the Title and Registration (T&R) fee.
7. Inheritance Tax and Estate Tax: Wisconsin does not impose an inheritance tax or an estate tax. As of my last update, both the inheritance tax and the estate tax have been eliminated.
8. No Local Income Tax: Wisconsin does not allow local jurisdictions to impose their own income taxes.
9. Tax Credits and Incentives: Wisconsin offers various tax credits and incentives to individuals and businesses, including the Homestead Credit for eligible homeowners and credits related to child care, education, and more.

It's important to note that tax laws are subject to change, and it's recommended to consult the Wisconsin Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Wisconsin.

Wisconsin (WI) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Wisconsin imposes a sales tax and use tax on various goods and services. Here are some key points about the Wisconsin Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Wisconsin is 5%. Additionally, there may be county sales taxes and stadium district taxes imposed by certain counties and municipalities, which can result in varying total sales tax rates in different areas of the state.
- Exemptions: Some items and services may be exempt from Wisconsin's sales tax. Common

exemptions include prescription drugs, groceries, and sales to tax-exempt organizations.

- Filing and Payment: Businesses that make sales subject to Wisconsin's sales tax are required to register with the Wisconsin Department of Revenue and collect the appropriate tax from their customers. The filing frequency (monthly, quarterly, or annually) depends on the business's sales volume. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Wisconsin has adopted economic nexus laws for online sales. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to collect and remit sales tax.

Use Tax:

- Use Tax Rate: The use tax rate in Wisconsin is also 5%. The use tax is applicable when residents or businesses in Wisconsin purchase taxable items from out-of-state sellers who do not collect Wisconsin sales tax. The purchaser is then responsible for paying the corresponding use tax directly to the state.
- Filing and Payment: Individuals and businesses in Wisconsin are required to report and remit use tax on their state income tax return if they made purchases without paying sales tax. This typically applies to out-of-state purchases, internet purchases, and other transactions where sales tax was not collected at the time of purchase.
- Online Purchases: Use tax in Wisconsin is relevant to out-of-state purchases and online purchases where sales tax was not collected. Individuals and businesses are required to report and remit the use tax on these transactions when filing their state income tax return.

Please note that tax laws are subject to change, and it's essential to consult the Wisconsin Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Wisconsin.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

Sales tax / Use tax - Wyoming (WY)

Wyoming (WY) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Wyoming (WY):

1. Sales Tax: Wyoming does not have a state-level sales tax. As a result, there is no general sales tax imposed on the retail sale of tangible personal property or services at the state level.
2. Use Tax: Since Wyoming does not have a state sales tax, there is no corresponding use tax imposed on the purchase of goods brought into the state.
3. Individual Income Tax: Wyoming does not impose an individual income tax on residents' or non-residents' earned income. This absence of an income tax is one of the key features of Wyoming's tax system.
4. Corporate Income Tax: Similar to individual income tax, Wyoming does not impose a corporate income tax on corporations conducting business in the state.
5. Property Taxes: Wyoming imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the local level, and the state has relatively low property tax rates compared to other states.
6. Vehicle Taxes and Fees: Wyoming imposes various taxes and fees on motor vehicles, including registration fees, license plate fees, and certain excise taxes.
7. Inheritance Tax and Estate Tax: Wyoming does not impose an inheritance tax or an estate tax. This means there are no state-level taxes on the transfer of property upon death.
8. No Local Income Tax: Wyoming does not allow local jurisdictions to impose their own income taxes.
9. Severance Taxes: Wyoming relies significantly on revenue from severance taxes, which are levied on the extraction of natural resources such as oil, gas, coal, and minerals.
10. Tax Credits and Incentives: Wyoming offers various tax credits and incentives to individuals and businesses, including incentives related to agriculture, manufacturing, and energy production.

It's important to note that tax laws are subject to change, and it's recommended to consult the Wyoming Department of Revenue or a tax professional for the most up-to-date and specific information related to taxes in Wyoming.

Wyoming (WY) - Sales Tax and Use Tax

As of ChatGPT's last update in September 2021, Wyoming imposes a sales tax and use tax on various goods and services. Here are some key points about the Wyoming Sales Tax and Use Tax:

Sales Tax:

- Sales Tax Rate: The state sales tax rate in Wyoming is 4%. However, Wyoming is one of the few states that does not impose a statewide sales tax on most goods and services. Instead, local jurisdictions have the option to impose a local sales and use tax, which can result in varying total

sales tax rates in different areas of the state.

- Exemptions: Wyoming does not impose a statewide sales tax on most goods and services, but local jurisdictions that have opted for a local sales tax may have exemptions for certain items.
- Filing and Payment: Businesses in areas with a local sales tax in Wyoming are required to register with the Wyoming Department of Revenue and collect the appropriate tax from their customers. The filing frequency and process depend on the local jurisdiction's rules. Businesses must file sales tax returns, reporting the total sales made and the corresponding tax collected.
- Online Sales: Wyoming does not have statewide economic nexus laws for online sales due to the absence of a statewide sales tax. However, local jurisdictions with local sales taxes may have their own rules for taxing online sales.

Use Tax:

- Wyoming does not have a statewide use tax. The concept of a use tax is closely tied to the presence of a sales tax, which Wyoming does not have at the state level. However, individuals and businesses may still be subject to local use taxes in areas with local sales taxes.
- Online Purchases: The absence of a statewide sales tax means that Wyoming residents are not generally required to pay sales or use tax on purchases made within the state. However, they may still be subject to any local sales taxes imposed by their jurisdiction.

Please note that tax laws are subject to change, and it's essential to consult the Wyoming Department of Revenue or a tax professional for the most up-to-date and specific information related to sales tax and use tax in Wyoming.

Created with the Standard Edition of HelpNDoc: Transform your help documentation into a stunning website

General Excise Tax / Use tax - Hawaii (HI)

Hawaii (HI) - Tax system key points

As of ChatGPT's last update in September 2021, here are some key points about the tax system in Hawaii:

1. General Excise Tax (GET): Hawaii has a unique tax called the General Excise Tax (GET). It is a broad-based tax imposed on business activities rather than on sales to consumers. The GET is applied to almost all business transactions, including sales of goods and services, and is levied at different rates depending on the type of business activity. The statewide general excise tax rate is 4%.

2. Transient Accommodations Tax (TAT): Hawaii imposes a Transient Accommodations Tax (TAT) on hotel and other transient accommodations, such as vacation rentals. The TAT rate is 10.25% as of my last update.
3. Sales Tax: Hawaii does not have a traditional state-level sales tax as most other states do. Instead, it relies on the General Excise Tax, which is applied to business activities at different rates.
4. Individual Income Tax: Hawaii levies an individual income tax on residents and non-residents who earn income in the state. The state has multiple tax brackets with rates ranging from 1.4% to 11% based on income levels.
5. Corporate Income Tax: Hawaii imposes a corporate income tax on corporations conducting business in the state. The corporate tax rates vary depending on the company's taxable income.
6. Property Taxes: Hawaii imposes property taxes on real property, such as land and buildings. Property tax rates are determined at the county level and can vary by location.
7. Vehicle Taxes and Fees: Hawaii imposes various taxes and fees on motor vehicles, including a registration fee based on the vehicle's weight, an annual vehicle weight tax, and a county surcharge.
8. Estate Tax: Hawaii has its own estate tax, which is separate from the federal estate tax. The Hawaii estate tax applies to estates with a value above a certain threshold, and the tax rates range from 10% to 20%.
9. No Local Income Tax: Hawaii does not allow local jurisdictions to impose their own income taxes.
10. No Use Tax: Hawaii does not have a separate use tax. The General Excise Tax applies to both sales and use of goods and services.

It's important to note that tax laws are subject to change, and it's recommended to consult the Hawaii Department of Taxation or a tax professional for the most up-to-date and specific information related to taxes in Hawaii.

Hawaii (HI) - General Excise Tax and Use Tax

As of ChatGPT's last update in September 2021, Hawaii imposes a general excise tax (GET) instead of a traditional sales tax. The Hawaii General Excise Tax is a broad-based tax that applies to various business activities, including the sale of goods and services. Here are some key points about the Hawaii General Excise Tax:

1. General Excise Tax Rate: The Hawaii General Excise Tax rate is not a fixed percentage like a traditional sales tax. Instead, there are different rates depending on the type of business activity. As of my last update, the standard tax rates are as follows:
    - 4% on the retail sale of tangible personal property and certain services.

- 0.5% on wholesale transactions.
- 0.15% on insurance commissions.
- 4.5% on businesses engaged in certain activities, such as the sale of alcohol for consumption on the premises or selling rental motor vehicles.

2. Island Districts: Hawaii's excise tax rates may vary within different island districts. For example, the county of Honolulu has an additional surcharge on the general excise tax, making the total rate higher in that district.
3. Exemptions: Some items and transactions may be exempt from the Hawaii General Excise Tax. However, the GET is generally broader in scope than traditional sales taxes, so many business activities are subject to taxation.
4. Filing and Payment: Businesses are required to register for a GET license with the Hawaii Department of Taxation and report their gross receipts regularly. The filing frequency (monthly, quarterly, or semi-annually) is based on the amount of gross receipts generated by the business.
5. Use Tax: Unlike many other states, Hawaii does not have a separate use tax. Instead, the GET applies to both sales and the use of tangible personal property and services.
6. Online Sales: Hawaii has adopted economic nexus laws for remote sellers. This means that businesses with a certain level of sales or transactions in the state, even if they have no physical presence there, may be required to register for a GET license and collect and remit the tax.

Please note that tax laws are subject to change, and it's essential to consult the Hawaii Department of Taxation or a tax professional for the most up-to-date and specific information related to the General Excise Tax in Hawaii.

Created with the Standard Edition of HelpNDoc: Experience a User-Friendly Interface with HelpNDoc's Documentation Tool

Use tax in the US

What is use tax in the US?

In the United States, use tax is a tax imposed on the use, consumption, or storage of tangible personal property or certain services when the seller does not collect sales tax at the time of the transaction. Use tax is often referred to as the counterpart of sales tax and is designed to ensure that consumers and businesses pay the appropriate amount of tax on purchases, even if the seller is located outside the

buyer's state or jurisdiction.

The key points to understand about use tax are as follows:

1. Out-of-State Purchases: Use tax applies when a buyer makes a purchase from a seller located outside their state, and the seller is not required to collect sales tax in the buyer's state due to a lack of physical presence or nexus.
2. Online Purchases: One common scenario where use tax comes into play is when consumers make purchases from out-of-state online retailers that do not have a physical presence in their state.
3. Mail-Order Purchases: Use tax also applies to purchases made from out-of-state mail-order catalogs or retailers.
4. Cross-Border Shopping: Use tax is relevant when consumers travel to a different state with a lower sales tax rate, make purchases there, and bring the items back to their home state.
5. Business Purchases: Businesses may also be subject to use tax when they purchase taxable items from sellers outside their state's jurisdiction.

The use tax rate is typically the same as the sales tax rate in the buyer's location, and it is based on the value of the purchased goods or services. The use tax rate may include the state tax rate and any applicable local taxes, depending on the buyer's location.

To ensure compliance, individuals and businesses are required to self-assess and pay the use tax owed to their state's tax authority. This is typically done by filing a use tax return, and the frequency of filing may vary by state. The use tax return allows the taxpayer to report the purchases subject to use tax and calculate the amount owed based on the applicable tax rates.

The goal of use tax is to prevent the avoidance of sales tax by making purchases from out-of-state sellers and to level the playing field between local businesses and remote sellers. Since tax laws can be complex and vary by state, it is advisable for individuals and businesses to seek advice from a tax professional to ensure proper compliance with use tax regulations.

Use tax return in the US

In the United States, a use tax return is a tax form that individuals and businesses are required to file to report and remit the use tax owed on purchases made from out-of-state sellers or for items used in a way that is subject to use tax. Use tax is a complementary tax to the sales tax and is designed to ensure that consumers pay the appropriate amount of tax on purchases, regardless of whether the seller collects the sales tax at the time of the transaction.

Use tax applies in situations where a seller does not have a physical presence (nexus) in the buyer's state and, therefore, is not required to collect sales tax. Instead, the responsibility falls on the buyer to self-

assess and pay the use tax on these purchases.

Common scenarios where use tax may be applicable include:

1. Online Purchases: When consumers make purchases from out-of-state online retailers that do not collect sales tax.
2. Mail-Order Purchases: When consumers buy goods from out-of-state mail-order catalogs.
3. Cross-Border Shopping: When consumers make purchases in a state with a lower sales tax rate and bring the items back to their home state.
4. Business Purchases: When businesses buy taxable items from sellers outside their state's jurisdiction.

The use tax rate is usually the same as the sales tax rate in the buyer's location, but it applies to out-of-state purchases that are subject to sales tax if the sale occurred within the buyer's state. If the local sales tax rate varies based on the buyer's location, the use tax rate will reflect the specific local rate applicable to the buyer.

To report and pay the use tax owed, individuals and businesses typically file a use tax return with their state's tax authority. The frequency of filing may vary by state, but it is often done annually with the state income tax return or through a separate use tax return form.

It's essential for individuals and businesses to understand their state's use tax laws and requirements to ensure compliance with the appropriate tax obligations. As tax laws can be complex and subject to change, seeking advice from a tax professional is recommended for accurate reporting and remittance of use tax.

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Trade and Investment Incentives and Regulations

What is Trade and Investment Incentives and Regulations?

Trade and Investment Incentives and Regulations refer to a set of government policies, measures, and regulations aimed at promoting international trade, attracting foreign direct investment (FDI), and stimulating economic growth. These incentives and regulations are designed to create a favourable business environment, support specific industries or regions, and encourage businesses to engage in cross-border trade and investment activities.

Here's a breakdown of what Trade and Investment Incentives and Regulations may entail:

1. Trade Incentives:

- Customs Duties Reduction or Elimination: Governments may offer tariff reductions or exemptions on certain imported goods to lower the cost of imports and encourage international trade.
- Free Trade Agreements (FTAs): Bilateral or multilateral agreements between countries that reduce or eliminate tariffs and other trade barriers, promoting free flow of goods and services.
- Export Promotion Schemes: Incentives such as export subsidies, export tax refunds, or export credit facilities provided to boost exports and enhance competitiveness in the global market.
- Trade Finance Support: Governments may offer financial support, guarantees, or insurance to facilitate trade transactions and reduce risks for exporters and importers.

2. Investment Incentives:
   - Tax Incentives: Governments may provide tax holidays, reduced corporate income tax rates, or tax credits to attract foreign investment and encourage domestic capital expenditure.
   - Foreign Direct Investment (FDI) Policies: Regulations to streamline foreign investment procedures, protect investor rights, and offer incentives for specific industries or regions.
   - Investment Promotion Agencies: Entities set up to attract and facilitate foreign investment by providing information, support, and guidance to potential investors.
3. Special Economic Zones (SEZs) and Development Zones:
   - Industrial Development Zones (IDZs): Specific geographic areas with special economic regulations and incentives to promote industrial growth, attract FDI, and create jobs.
   - Economic Development Zones (EDZs): Similar to IDZs, these zones offer various incentives to encourage economic activities and development.
4. Diesel Rebates and Excise Tax Refunds:
   - Diesel Rebates: Refunds or reductions on excise duties or taxes on diesel fuel used for specific purposes, such as farming, mining, or off-road activities.
   - Excise Tax Refunds: Reimbursements or credits provided for excise taxes paid on certain goods produced domestically or imported.
5. Regulatory Reforms:
   - Trade Facilitation Measures: Simplifying customs procedures, reducing paperwork, and implementing efficient logistics systems to expedite cross-border trade.

- Business Registration and Licensing Reforms: Streamlining business registration and licensing processes to encourage entrepreneurship and investment.

Trade and Investment Incentives and Regulations play a crucial role in attracting foreign investment, promoting exports, creating jobs, and boosting economic development. Governments use these measures to enhance their country's competitiveness, integrate into the global economy, and foster sustainable economic growth. The specific incentives and regulations vary from country to country, and businesses looking to benefit from these measures should thoroughly research and understand the relevant policies and requirements in the countries they operate or plan to invest in.

Accounts for Trade and Investment Incentives and Regulations in the Chart of Accounts

The relevant accounts for Trade and Investment Incentives and Regulations in the Chart of Accounts is essential for several reasons:

1. Accurate Documentation: Creating specific accounts for trade and investment incentives allows businesses to accurately document the financial transactions related to these incentives. Proper documentation is crucial for compliance, audit purposes, and providing transparent financial reports.
2. Regulatory Compliance: By setting up dedicated accounts, businesses can ensure that they comply with the specific regulations and reporting requirements associated with each type of incentive. It helps them keep track of the incentives claimed or availed and maintain a clear audit trail.
3. Transparency and Accountability: Separate accounts for trade and investment incentives facilitate transparency in financial reporting. It enables stakeholders, including investors, regulators, and tax authorities, to easily identify and understand the impact of these incentives on the business's financial performance.
4. Internal Control and Monitoring: Having designated accounts helps businesses monitor the utilization of incentives and ensures that they are used for the intended purposes. This strengthens internal control and minimizes the risk of non-compliance or misuse of incentives.
5. Tax and Financial Reporting: Maintaining proper accounts allows businesses to accurately calculate tax liabilities, claim tax benefits, and prepare financial statements in accordance with accounting standards and regulations.
6. Incentive Optimization: By tracking the utilization of incentives through dedicated accounts, businesses can analyze the effectiveness of various incentives and make informed decisions on how to optimize their benefits.
7. Ease of Auditing: During external audits, having segregated accounts for incentives simplifies the

process for auditors to review and verify the accuracy of incentive-related transactions.

8. Cross-Border Transactions: For businesses engaged in international trade and investment, separate accounts for customs duties, tax refunds, and other trade-related transactions help manage the complexities of cross-border activities.
9. Financial Planning: Having dedicated accounts allows businesses to monitor the financial impact of incentives, helping them plan and forecast their future financial positions more effectively.

Including the relevant accounts for Trade and Investment Incentives and Regulations in the Chart of Accounts demonstrates the business's commitment to proper financial management and compliance. It also ensures that the business can take full advantage of the incentives offered by the government while adhering to the specific regulations and accounting standards in their jurisdiction. As accounting practices and regulations can evolve, businesses should continuously review and update their Chart of Accounts to align with any changes in the incentive schemes or reporting requirements.

Consulting with accounting professionals who are familiar with the Trade and Investment Incentives and Regulations

Consulting with accounting professionals who are familiar with the Trade and Investment Incentives and Regulations specific to a business's jurisdiction is crucial for effectively managing financial operations within designated areas and availing the available incentives. These professionals can provide valuable guidance and ensure that the business complies with all relevant regulations and accounting standards related to these incentives.

The complexity of trade and investment incentives, customs and excise duties, tax rebates, and various regulations in different countries necessitates expert advice to navigate the intricacies of these incentive schemes. Accounting professionals well-versed in these areas can help businesses with the following:

1. Incentive Eligibility: Determine which incentives apply to the business based on its activities, industry, and location.
2. Record-keeping: Set up and maintain appropriate accounts in the Chart of Accounts to accurately record transactions related to incentives, ensuring proper documentation for compliance and audits.
3. Claiming Incentives: Assist in the proper claiming and utilization of incentives, ensuring businesses receive the maximum benefits available to them.
4. Reporting and Compliance: Ensure that the business's financial statements and tax returns are prepared in accordance with relevant regulations and accounting standards, taking into account the impact of incentives.
5. Regulatory Updates: Keep the business informed about changes in incentive schemes, customs

regulations, and tax laws, helping them adapt their financial operations accordingly.

6. Risk Mitigation: Identify and address potential risks associated with incentive utilization and compliance, helping the business avoid penalties or adverse consequences.
7. Strategic Planning: Provide financial planning advice, considering the impact of incentives on the business's short-term and long-term financial goals.
8. Cross-Border Transactions: For businesses engaged in international trade and investment, accounting professionals can assist in navigating the complexities of cross-border transactions, including customs duties and tax implications.

By collaborating with accounting professionals who possess expertise in Trade and Investment Incentives and Regulations, businesses can optimize their financial operations, benefit from available incentives, and ensure adherence to the specific requirements of their jurisdiction. This partnership helps to build a strong financial foundation and supports the business's growth and success within designated areas and special economic zones.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Diesel refunds

What is a diesel refund, diesel tax refund or diesel fuel tax rebate?

A diesel refund, also known as a diesel tax refund or diesel fuel tax rebate, is a mechanism by which certain businesses or industries can claim a reimbursement or credit for the excise tax paid on diesel fuel used for specific purposes. The refund is typically provided by the government as an incentive to support certain sectors, encourage economic activities, and reduce the overall cost burden on businesses that heavily rely on diesel fuel.

The eligibility and regulations for diesel refunds vary from country to country, and the types of industries or activities that may qualify can differ significantly. Generally, industries that consume large amounts of diesel for specific purposes, such as farming, mining, fishing, forestry, construction, and certain off-road machinery, are more likely to be eligible for diesel refunds.

To claim a diesel refund, businesses are usually required to maintain detailed records of their diesel purchases and usage, as well as meet specific criteria defined by the tax authorities. The refund amount is often calculated based on the volume of diesel used for eligible activities, and it may be provided as a reimbursement, credit against future tax liabilities, or other forms of incentives.

By providing diesel refunds, governments aim to support key industries, stimulate economic growth, and offset some of the costs associated with using diesel fuel for essential purposes. It can also help businesses in eligible sectors remain competitive and contribute to job creation and development.

As diesel refund schemes are subject to specific regulations and requirements, businesses seeking to claim a diesel refund should carefully review the relevant tax laws and consult with tax professionals to ensure compliance and maximize the benefits available to them.

Calculation of diesel refund, diesel tax refund or diesel fuel tax rebate

The tax codes and accounts mentioned earlier primarily focused on Value Added Tax (VAT) and its related transactions. However, for some businesses engaged in specific activities, such as those involving the use of diesel in certain industries, additional records and accounts may be required to calculate and claim refunds in terms of the Customs and Excise Act.

In the case of businesses that are eligible for a diesel refund, additional documentation and accounting processes may be necessary to accurately calculate and report the refund amount. These processes can vary depending on the nature of the business activities and the specific regulations governing diesel refunds in the respective country.

Here's a general outline of what might be involved for the calculation of a diesel refund:

1. Records and Invoices: Businesses may need to maintain detailed records of diesel purchases, including invoices and receipts, to substantiate the fuel expenses and determine the eligible refund amount.
2. Fuel Usage Tracking: The business may need to track and record the usage of diesel for eligible activities, as not all diesel usage may qualify for a refund.
3. Calculation of Refund: Based on the eligible fuel usage, the business would calculate the refund amount according to the prescribed rates and rules under the Customs and Excise Act.
4. Specific Accounts: Depending on the complexity of the calculations and the size of the business, specific accounts may be created to track the diesel refund-related transactions separately.
5. Submission of Refund Claims: The business would submit the refund claims to the relevant tax authorities following the prescribed procedures and deadlines.
6. Reconciliation and Compliance: Regular reconciliation of diesel purchases, usage, and refund claims with the records in the books of accounts would be necessary to ensure compliance and accuracy.

It's important to note that the specific requirements for diesel refunds can vary significantly depending on

the country's tax laws, the industry, and the type of diesel usage involved. Therefore, businesses should seek guidance from tax professionals or relevant authorities to ensure compliance with the Customs and Excise Act and to set up the appropriate accounting procedures to manage diesel refund-related transactions effectively.

As this example is specific to diesel refunds, businesses in other industries or with different types of activities may have other specific tax-related requirements that must be addressed separately.

The "CALCULATION OF DIESEL REFUND IN TERMS OF THE CUSTOMS AND EXCISE ACT" items is included below the VAT section of the VAT201 Return / Declaration that needs to be calculated.

If the "*CALCULATION OF DIESEL REFUND IN TERMS OF THE CUSTOMS AND EXCISE ACT*" items are included below the VAT section of the VAT201 Return/Declaration, it means that businesses are required to calculate and report diesel refunds as a separate section of the VAT return.

In this case, the VAT201 Return would include both the VAT-related information as described in the earlier responses (i.e., the VAT sub-accounts and corresponding fields for output VAT, input VAT, adjustments, etc.) and a separate section dedicated to the calculation of diesel refunds in accordance with the Customs and Excise Act.

The specific details and requirements for calculating the diesel refund would be outlined in this additional section, and businesses would need to provide the necessary records, data, and calculations to support their refund claims.

Since diesel refunds involve complex calculations and are subject to specific regulations, it's essential for businesses to carefully follow the instructions provided by the tax authorities and maintain accurate records to support their refund claims.

To ensure compliance and accuracy in reporting both the VAT-related information and the diesel refund calculation, businesses should seek professional advice from tax experts or accountants familiar with the Customs and Excise Act and the specific requirements for diesel refunds in their country. This will help ensure that the VAT201 Return is completed correctly, and the diesel refund claim is accurately calculated and reported.

It is probably more related to farming and mining sectors

Diesel refunds are indeed commonly associated with the farming and mining sectors, as well as other industries that use diesel for specific purposes, such as construction, transportation, and certain off-road

machinery.

In these sectors, diesel is often used for agricultural machinery, mining vehicles, generators, and other equipment. Due to the significant diesel consumption in these operations, some countries may have provisions that allow businesses in these sectors to claim partial or full refunds on the excise duties paid on diesel used for qualifying activities.

As mentioned earlier, the specific regulations, eligibility criteria, and refund calculation methodologies can vary from country to country. The process for claiming diesel refunds may involve additional documentation, record-keeping, and calculations to demonstrate eligible usage and ensure compliance with the applicable tax laws.

To properly handle diesel refunds, businesses operating in the farming, mining, or related sectors should:

1. Understand Eligibility: Familiarize themselves with the specific eligibility criteria for claiming diesel refunds in their country and industry.
2. Track Diesel Usage: Maintain accurate records of diesel purchases and track the usage of diesel for eligible activities.
3. Apply Correct Rates: Use the correct refund rates or percentages as specified in the relevant tax regulations.
4. Maintain Supporting Documentation: Keep all invoices, receipts, and relevant documentation as evidence to support refund claims.
5. Comply with Filing Requirements: Adhere to the prescribed filing procedures and deadlines for submitting diesel refund claims.
6. Seek Professional Advice: Consult with tax advisors or experts who are knowledgeable about diesel refunds in the respective country to ensure compliance and optimize the refund process.

Given the complexity of diesel refund calculations and the potential impact on business costs, it's essential for companies in the farming and mining sectors, or any industry eligible for diesel refunds, to handle these claims accurately and efficiently. Working closely with tax professionals can help ensure that businesses maximize their eligible refunds while meeting all regulatory requirements.

In which counties may this apply?

The eligibility for diesel refunds and the specific regulations governing them can vary significantly from country to country. While diesel refunds are common in some regions, they may not be applicable or may have different conditions in others. Here are some examples of countries where diesel refunds or similar schemes are known to be implemented or have been considered:

1. South Africa: The Diesel Refund Scheme is available for certain sectors like mining, farming, forestry,

and off-road activities.

2. Australia: The Fuel Tax Credit (FTC) scheme allows businesses to claim credits for the fuel tax (which includes diesel) used in eligible activities, including agriculture, mining, and forestry.
3. Canada: Some provinces offer tax exemptions or rebates on diesel used for certain off-road purposes or primary production activities.
4. United States: Certain states may provide exemptions or refunds on diesel taxes for agricultural or off-road use.
5. United Kingdom: Red Diesel (rebated gas oil) is used in certain sectors, such as agriculture, fishing, and non-road mobile machinery, and is subject to a reduced tax rate.
6. European Union: Some EU member states may offer reduced tax rates or exemptions for diesel used in agriculture and certain off-road activities.
7. India: Diesel is subject to various tax rates depending on its usage, with certain sectors like agriculture and fishing often enjoying lower rates.

It's important to note that this list is not exhaustive, and the regulations and eligibility criteria for diesel refunds may change over time. Additionally, each country's scheme may have different requirements, rates, and qualifying activities. Therefore, businesses operating in the farming, mining, or related sectors should refer to their country's specific tax laws, customs, and excise regulations, or seek guidance from tax professionals to understand the eligibility and process for claiming diesel refunds in their respective jurisdictions.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Industrial Development Zones and Economic Development Zones

What is Industrial Development Zones and Economic Development Zones?

Industrial Development Zones (IDZs) and Economic Development Zones (EDZs) are special geographic areas that governments create to promote economic growth, attract investments, and facilitate industrial and commercial activities. These zones are designed to provide various incentives and benefits to businesses and investors, encouraging them to establish operations within the designated areas. The specific terms and regulations associated with IDZs and EDZs can vary depending on the country or

region.

1. Industrial Development Zones (IDZs):
    - IDZs are geographical areas typically located near ports, airports, or major transportation hubs, making them strategically positioned for trade and export activities.
    - The main objective of IDZs is to attract foreign direct investment (FDI) and boost the domestic industrial and manufacturing sectors.
    - Incentives in IDZs often include tax breaks, customs duty exemptions or reductions, streamlined regulatory processes, access to infrastructure, and other financial and non-financial benefits to attract businesses.
    - Companies that set up operations in IDZs can take advantage of these incentives to enhance their competitiveness and profitability in the global market.
2. Economic Development Zones (EDZs):
    - EDZs are broader economic development areas that encompass various zones, including industrial zones, technology parks, free trade zones, and more.
    - The goal of EDZs is to promote economic growth and development in specific regions or across the entire country by attracting investments and stimulating business activities.
    - Like IDZs, EDZs also offer a range of incentives and benefits to businesses and investors. These may include tax incentives, duty exemptions, simplified regulations, access to infrastructure and utilities, and enhanced support services.
    - In some cases, EDZs may have a more diversified focus, aiming to encourage not only industrial and manufacturing activities but also services, trade, technology, research, and development.

Both IDZs and EDZs play a crucial role in attracting investments, creating employment opportunities, and fostering economic development in regions where these zones are established. By providing a favorable business environment and incentives, governments seek to stimulate economic growth, increase export potential, and enhance competitiveness on the global stage. The specific terms, regulations, and benefits offered in IDZs and EDZs can vary significantly depending on the country's economic policies and development goals.

In which countries may IDZs, EDZs apply?

Industrial Development Zones (IDZs) and Economic Development Zones (EDZs) are established in various countries around the world to promote economic growth and attract investments. The availability and

characteristics of these zones can vary from one country to another. Here are some examples of countries where IDZs and EDZs are commonly found or have been established:

1. South Africa: South Africa has several Industrial Development Zones (IDZs) strategically located in different provinces to encourage industrial development, job creation, and export-oriented manufacturing.
2. China: China has numerous Special Economic Zones (SEZs) that offer various incentives and benefits to businesses, including tax breaks, streamlined customs procedures, and access to infrastructure.
3. United Arab Emirates: The UAE has numerous Free Zones, which are similar to Economic Development Zones, offering tax exemptions, full foreign ownership, and other advantages to businesses.
4. India: India has Special Economic Zones (SEZs) that provide tax benefits, simplified regulatory procedures, and infrastructure support to promote exports and industrial development.
5. Singapore: Singapore has several Free Trade Zones (FTZs) and Free Trade Areas (FTAs) that offer tax incentives and customs duty exemptions to facilitate international trade and logistics.
6. United States: The U.S. has Foreign Trade Zones (FTZs) that provide various cost-saving benefits for companies engaged in international trade and manufacturing.
7. Turkey: Turkey has Organized Industrial Zones (OIZs) that offer benefits like tax incentives and customs duty exemptions to promote industrial development.
8. Brazil: Brazil has Industrial Districts and Economic Development Areas that provide tax incentives and support for industrial activities.
9. Malaysia: Malaysia has Free Industrial Zones (FIZs) that offer tax exemptions and other advantages for export-oriented industries.
10. Mexico: Mexico has Maquiladora Zones that provide tax benefits to manufacturing companies producing goods for export.

It's important to note that this list is not exhaustive, and many other countries have established similar zones to promote economic development and attract investments. The specific names, characteristics, and incentives offered in these zones can differ widely depending on the economic policies and development goals of each country.

If businesses are interested in exploring opportunities within IDZs, EDZs, or other similar zones, they should research the specific regulations and benefits offered by the relevant countries and consult with legal and financial advisors to understand the implications and requirements for setting up operations in these zones.

Accounts for IDZs and EDZs in the Chart of Accounts

Absolutely, including accounts in the Chart of Accounts to track transactions related to Industrial Development Zones (IDZs), Economic Development Zones (EDZs), or any other special economic zones is essential for proper reporting and compliance. By creating specific accounts for these zones, businesses can accurately record and monitor the financial transactions associated with their activities within these designated areas.

Here are some key points to consider when incorporating IDZs and EDZs in the Chart of Accounts:

1. Clear Identification: Assign unique codes or names to the accounts that represent transactions specific to IDZs, EDZs, or any other special economic zones. This will make it easier to distinguish them from regular accounts and enable accurate reporting.
2. Differentiation of Incentives: If the IDZs or EDZs offer tax incentives, customs duty exemptions, or other benefits, ensure that separate accounts are created to track these incentives. This will help in accurately calculating tax savings and benefits.
3. Tracking Eligible Expenses: If businesses can claim tax credits or deductions on specific expenses within the zones, create accounts to track those expenses separately. This will facilitate easy identification and calculation of eligible deductions.
4. Reporting and Compliance: Ensure that all transactions related to the IDZs or EDZs are correctly recorded in the designated accounts. This will help businesses in meeting reporting requirements and tax compliance obligations.
5. Supporting Documentation: Maintain proper supporting documentation for transactions within the zones. This may include invoices, receipts, permits, and any other documents necessary to substantiate the claims for benefits or incentives.
6. Regular Reconciliation: Regularly reconcile the transactions recorded in the accounts related to the special economic zones with the overall financial records to ensure accuracy and consistency.

By incorporating these specific accounts in the Chart of Accounts, businesses can ensure that they accurately report and track financial activities within IDZs, EDZs, or other special economic zones. This will help in maximizing the benefits and incentives offered by the zones while staying compliant with the relevant tax regulations and reporting requirements. It is essential to seek advice from accounting and tax professionals to set up the Chart of Accounts correctly and meet all regulatory obligations related to these zones.

IDZs and EDZs - What would the typical transactions and accounts be?

In the context of Industrial Development Zones (IDZs) and Economic Development Zones (EDZs), businesses engaged in activities within these designated areas may have specific transactions and accounts related to their operations. These zones typically offer various incentives, benefits, and streamlined processes to attract investments and promote economic growth. Here are some typical transactions and accounts that businesses may encounter within IDZs and EDZs:

1. Lease or Rental Agreements:
    - Transaction: Businesses operating within IDZs or EDZs may enter into lease or rental agreements with the zone authorities or landlords to secure space for their operations.
    - Account: An account should be created to track lease or rental expenses for the facilities or land used within the zone.
2. Infrastructure Charges or Contributions:
    - Transaction: Some IDZs or EDZs may impose infrastructure charges or require businesses to make financial contributions towards the development and maintenance of shared infrastructure within the zone.
    - Account: An account should be established to track infrastructure charges or contributions payable by the business.
3. Customs and Excise Duties:
    - Transaction: Businesses importing or exporting goods within IDZs or EDZs may still be subject to customs and excise duties, depending on the country's regulations.
    - Account: Separate accounts should be maintained to track customs duties payable on imports, customs duties receivable on exports, and excise duties payable on specific goods produced or imported within the zone.
4. Tax Incentives and Benefits:
    - Transaction: Businesses within IDZs or EDZs may be eligible for tax incentives, including reduced corporate income tax rates, exemptions, or tax holidays.
    - Account: An account should be created to track tax benefits and incentives availed by the business, including deferred tax liabilities resulting from these incentives.
5. Sales and Purchases within the Zone:

- Transaction: Businesses operating within IDZs or EDZs may engage in sales and purchases of goods and services with other companies within the same zone.
- Account: Separate accounts should be maintained to track sales revenue and purchases made within the zone.

6. Investment Subsidies or Grants:
   - Transaction: In some cases, businesses may receive investment subsidies or grants from the zone authorities or the government to support their operations within IDZs or EDZs.
   - Account: An account should be established to track investment subsidies or grants received by the business.
7. Zone Administrative Fees:
   - Transaction: Businesses operating within IDZs or EDZs may be required to pay administrative fees to the zone authorities for various services or compliance purposes.
   - Account: An account should be created to track administrative fees payable to the zone authorities.
8. Job Creation or Training Incentives:
   - Transaction: Some IDZs or EDZs may offer incentives to businesses for job creation, training programs, or skills development initiatives.
   - Account: An account should be set up to track expenses related to job creation or training activities, as well as any incentives received for these efforts.

It's essential for businesses operating within IDZs or EDZs to have a clear accounting system that reflects the unique transactions and incentives offered within these zones. Properly tracking these transactions and maintaining accurate records will ensure compliance with zone regulations, optimize the benefits available, and facilitate transparent financial reporting. As always, consulting with accounting professionals familiar with the regulations and requirements of IDZs and EDZs can help businesses effectively manage their financial operations within these designated areas.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Incentives for generation and use of green energy

Incentives for generation and use of green energy

Many countries and governments offer various incentives to encourage the generation and use of green energy as part of their efforts to promote energy security, reduce carbon emissions, and transition to more sustainable energy sources. These incentives are designed to make green energy technologies more accessible and financially viable, ultimately supporting the growth of renewable energy infrastructure. Some common incentives for generating green energy include:

1. Feed-in Tariffs (FiTs): FiTs guarantee a fixed payment or premium rate for renewable energy producers (such as solar, wind, or biomass) for each kilowatt-hour (kWh) of electricity they generate. This provides long-term price certainty and revenue stability for renewable energy projects, making them attractive to investors and developers.
2. Renewable Energy Certificates (RECs): RECs, also known as green certificates or tradable green certificates, represent the environmental attributes of one megawatt-hour (MWh) of electricity generated from renewable sources. Renewable energy producers can sell these certificates to electricity retailers or consumers to demonstrate their commitment to supporting renewable energy.
3. Tax Credits and Incentives: Governments often offer tax credits or deductions for businesses or individuals investing in renewable energy projects. These tax incentives can significantly reduce the upfront costs and improve the financial viability of green energy installations.
4. Grants and Subsidies: Governments may provide grants or subsidies to support the development and deployment of renewable energy technologies. These funds can be used to cover a portion of the project costs or provide financial support for research and development in the renewable energy sector.
5. Net Metering: Net metering allows renewable energy system owners to receive credits for the excess electricity they generate and feed back into the grid. These credits can be used to offset electricity purchases during periods when renewable energy generation is insufficient.
6. Green Bonds and Financing: Green bonds are a form of financing used to fund environmentally friendly projects, including renewable energy developments. Investors purchase green bonds, and the proceeds are used to support green energy initiatives.
7. Priority Grid Access: Some jurisdictions grant renewable energy projects priority access to the electricity grid, ensuring that green energy is given preference in feeding electricity into the system over traditional fossil fuel sources.
8. Low-interest Loans: Governments or financial institutions may offer low-interest loans or favorable financing terms for renewable energy projects to help reduce the overall project costs.
9. Green Energy Targets and Mandates: Some countries implement renewable energy targets or

mandates that require a certain percentage of electricity to come from renewable sources. Meeting these targets may make green energy generation more economically attractive for energy producers.

These incentives vary from country to country and may be subject to specific eligibility criteria and time-frames. Businesses and individuals interested in green energy projects should consult with local energy authorities, renewable energy associations, or financial experts to understand the available incentives and how to make the most of them while contributing to a sustainable energy future.

In which countries and governments does the incentives to encourage the generation and use of green energy apply?

Incentives to encourage the generation and use of green energy apply in various countries and governments around the world. The specific incentives and their availability can differ significantly from one country to another, as each nation designs its policies and programs based on its energy goals, environmental commitments, and economic considerations. Here are some examples of countries and regions where green energy incentives are commonly offered:

1. Germany: Germany has been a global leader in promoting renewable energy. It offers feed-in tariffs (FiTs) for solar, wind, and biomass projects, providing stable and attractive returns to renewable energy producers.
2. United States: In the United States, incentives for green energy vary at the federal, state, and local levels. The federal government offers tax credits and grants for renewable energy projects, and several states have their own incentive programs.
3. China: China is a major player in renewable energy deployment. The country provides various incentives, including subsidies, feed-in tariffs, and favourable financing options, to support the growth of solar and wind power.
4. India: India has ambitious renewable energy targets and offers incentives such as Viability Gap Funding (VGF), Generation-Based Incentive (GBI), and capital subsidies to promote green energy adoption.
5. Japan: Japan offers feed-in tariffs for solar, wind, and other renewable energy sources to encourage the development of clean energy projects.
6. United Kingdom: The UK provides financial support through Contracts for Difference (CfD) and Renewables Obligation Certificates (ROCs) to incentivize renewable energy generation.
7. Canada: Canada offers various federal and provincial incentives, including tax credits, grants, and low-interest loans, to promote renewable energy projects.
8. Australia: Australia offers incentives such as the Small-scale Renewable Energy Scheme (SRES) for

solar systems and large-scale renewable energy targets to encourage green energy generation.

9. Brazil: Brazil provides feed-in tariffs and tax incentives for renewable energy projects, particularly in the areas of hydropower and bioenergy.
10. South Africa: South Africa offers tax incentives, feed-in tariffs, and competitive bidding programs to support the growth of renewable energy, particularly in the solar and wind sectors.
11. European Union: The EU member states collectively implement various green energy incentives and targets, including feed-in tariffs and renewable energy certificates.

It's important to note that the availability and nature of green energy incentives can change over time, depending on the policy priorities of each country. Additionally, some countries may offer specific incentives or grants targeted at certain types of renewable energy technologies or specific regions with energy development goals.

For businesses or individuals interested in green energy projects, it is crucial to research and stay up-to-date on the latest incentives and programs available in their respective countries. Consulting with local energy authorities or renewable energy associations can provide valuable insights into the specific incentives and how to leverage them effectively.

Accounts for green energy incentives in the Chart of Accounts

Yes, including the relevant accounts related to green energy incentives in the Chart of Accounts is crucial for proper reporting and documentation of the financial transactions associated with these incentives. Properly tracking and reporting these incentives in the accounting system ensures transparency, compliance, and accurate financial statements. Here's why it's important to include these accounts in the Chart of Accounts:

1. Compliance and Transparency: Designated accounts for green energy incentives enable businesses to segregate and accurately report the financial impact of these incentives. This ensures compliance with relevant regulations and enhances the transparency of financial reporting.
2. Record-keeping and Audit Trail: By maintaining specific accounts, businesses can keep detailed records of transactions related to green energy incentives. This creates a clear audit trail, facilitating verification during internal or external audits.
3. Accurate Financial Reporting: Including these accounts in the Chart of Accounts ensures that the financial statements accurately reflect the benefits derived from green energy incentives. This supports better decision-making and financial planning.
4. Incentive Utilization Tracking: Separate accounts help businesses monitor the utilization of green energy incentives, ensuring they are properly applied and contribute to the business's financial

performance.

5. Tax and Regulatory Compliance: Having designated accounts makes it easier to calculate tax benefits and comply with reporting requirements related to green energy incentives, reducing the risk of errors or omissions.
6. Internal Management and Analysis: By isolating the financial impact of green energy incentives, businesses can assess the effectiveness of these incentives in achieving their environmental and financial goals.
7. Budgeting and Forecasting: Specific accounts allow businesses to budget and forecast their financials more accurately, considering the impact of green energy incentives on their cash flows and profitability.
8. Cross-Reference with Incentive Programs: Linking these accounts to specific incentive programs or policies simplifies the cross-referencing process, aiding in tracking the benefits derived from each program.
9. Comprehensive Financial Picture: Including green energy incentive accounts provides a comprehensive view of the business's environmental and financial performance, demonstrating its commitment to sustainable practices.

When implementing green energy projects and availing relevant incentives, businesses should work closely with accounting professionals to ensure the Chart of Accounts aligns with the specific requirements of the incentive programs and the country's regulations. Properly documenting and reporting green energy incentives not only ensures compliance but also enhances the business's reputation as a responsible and environmentally conscious entity.

Green energy incentives - What would the typical transactions and accounts be?

Typical transactions and accounts related to green energy incentives will vary based on the specific incentive programs, regulations, and accounting practices of each country or region. However, here are some common transactions and accounts that businesses may encounter when availing green energy incentives:

1. Feed-in Tariff (FiT) Incentives:
    - Transaction: Receiving payments for the electricity generated from renewable energy sources at a fixed tariff rate.
    - Account: "*FiT Revenue*" or "*Renewable Energy Income*" (Income account) to record the revenue generated from selling electricity at the feed-in tariff rate.

2. Renewable Energy Certificates (RECs):
    - Transaction: Generating Renewable Energy Certificates for each megawatt-hour (MWh) of renewable energy produced.
    - Account: "*Renewable Energy Certificate (REC) Asset*" (Asset account) to track the number of certificates earned and "REC Revenue" (Income account) when the certificates are sold.
3. Tax Incentives:
    - Transaction: Claiming tax credits or deductions for investments in renewable energy projects.
    - Account: "*Green Energy Tax Credit*" or "*Renewable Energy Tax Deduction*" (Expense account) to track the tax benefits received.
4. Grants and Subsidies:
    - Transaction: Receiving financial support through grants or subsidies for renewable energy initiatives.
    - Account: "*Green Energy Grant*" or "*Renewable Energy Subsidy*" (Income account) to record the funds received.
5. Net Metering:
    - Transaction: Offset of electricity consumption with excess energy generated and fed back into the grid.
    - Account: "*Net Metering Credit*" or "*Renewable Energy Offset*" (Income account) to track the credits received for excess energy supplied.
6. Green Bonds and Financing:
    - Transaction: Raising funds through the issuance of green bonds for renewable energy projects.
    - Account: "*Green Bond Proceeds*" or "*Renewable Energy Financing*" (Liability account) to record the funds raised.
7. Infrastructure Investment Incentives:
    - Transaction: Claiming tax incentives or grants for investing in renewable energy infrastructure development.
    - Account: "*Green Infrastructure Investment Credit*" (Expense account) to track the benefits received.
8. Renewable Energy Project Costs:

- Transaction: Capitalizing expenses related to the development and construction of renewable energy projects.
- Account: "*Renewable Energy Project Assets*" (Asset account) to track the capitalization of project costs.

9. Research and Development (R&D) Incentives:
    - Transaction: Claiming R&D tax credits for renewable energy technology innovation.
    - Account: "*Green Energy R&D Tax Credit*" (Expense account) to record the benefits received.

It's important to note that the naming and categorization of accounts may vary depending on the business's accounting system and practices. The specific accounts may also be adjusted to comply with the financial reporting standards of the country or region.

Businesses should work closely with accounting professionals to identify the most appropriate accounts for tracking green energy incentives and ensure accurate and compliant financial reporting.

Created with the Standard Edition of HelpNDoc: How to Protect Your PDFs with Encryption and Passwords

---

Government assistance and support for crises

Governments often provide various forms of assistance and support to help businesses and organizations get back on their feet after facing challenges such as economic downturns, natural disasters, or other crises. These support measures aim to promote economic recovery, preserve jobs, and revitalize industries. Some common examples of how governments help businesses and organizations include:

1. Financial Support and Grants: Governments may offer financial assistance in the form of grants, loans, or subsidies to help businesses cover operational costs, invest in new equipment or technology, and maintain their workforce during difficult times.
2. Tax Relief and Incentives: Tax relief measures, such as temporary reductions or deferrals of taxes, can provide businesses with much-needed breathing space. Governments may also introduce tax incentives to encourage specific investments or business activities that support economic recovery.
3. Employment Support Programs: Governments may implement programs to support employee retention and job creation. These programs may include wage subsidy schemes or training initiatives to help businesses retain and upskill their workforce.

4. Access to Credit and Financing: Governments may collaborate with financial institutions to offer special credit facilities or loan guarantees to businesses, making it easier for them to access capital and credit during challenging times.
5. Industry-Specific Support: In some cases, governments may offer targeted support to specific industries that have been severely impacted by a crisis. This could include tailored assistance packages, regulatory changes, or sector-specific grants.
6. Business Advisory Services: Governments may provide advisory services to help businesses navigate challenges, access resources, and develop recovery strategies. These services may include training, mentorship, and counselling.
7. Infrastructure Investment: Governments may initiate public infrastructure projects to stimulate economic activity and create new opportunities for businesses.
8. Easing Regulatory Burdens: During times of crisis, governments may streamline or temporarily suspend certain regulations and bureaucratic processes to help businesses operate more efficiently and with greater flexibility.
9. Export Promotion and Market Access: Governments may offer support to businesses seeking to expand their markets through export promotion initiatives, trade missions, or market access facilitation.
10. Public-Private Partnerships: Collaboration between the public and private sectors can lead to joint initiatives that support business recovery and foster economic growth.

It's important to note that the specific assistance measures and their availability can vary significantly from one country to another and depend on the nature of the crisis being faced. Government support may be short-term or longer-term, depending on the severity of the situation and the government's overall economic policy objectives.

During periods of crisis, it is essential for businesses and organizations to stay informed about the support programs and resources available to them and actively engage with government agencies and business associations to take advantage of available assistance.

Chart of Accounts - government assistance and support

When businesses receive government assistance and support to navigate through economic downturns, natural disasters, or other crises, they need to ensure strict adherence to the regulations and guidelines set by the government or relevant authorities. Adhering to these regulations is crucial for maintaining transparency, accountability, and compliance with the terms and conditions of the support programs. One essential aspect of ensuring compliance is aligning the Chart of Accounts accordingly to accurately record and track the financial transactions related to the government assistance. Here are some considerations

for aligning the Chart of Accounts:

1. Separate Accounts for Government Assistance: Create specific accounts in the Chart of Accounts to track the government assistance received. These accounts should clearly differentiate between grants, subsidies, loans, or other forms of support and should be labeled appropriately.
2. Detailed Reporting: Ensure that the Chart of Accounts allows for detailed reporting on how the government assistance is utilized. This may involve creating sub-accounts or cost centers to categorize expenses related to the support received.
3. Tax Implications: Consider the tax implications of the government assistance and set up accounts to accurately record any tax reliefs, deferrals, or adjustments that may result from the support.
4. Regulatory Compliance: Be aware of any specific regulatory requirements related to government assistance, such as reporting deadlines or eligibility criteria. Ensure that the Chart of Accounts enables proper tracking and reporting in line with these requirements.
5. Segregation of Funds: If the government assistance involves the allocation of specific funds for particular purposes, segregate these funds in the Chart of Accounts to prevent commingling with regular operational funds.
6. Audit and Accountability: Design the Chart of Accounts in a way that facilitates easy auditing and provides a clear trail of how the government support is utilized. This level of accountability is essential to maintain transparency and build trust with relevant authorities.
7. Updates and Changes: Keep the Chart of Accounts flexible to accommodate any updates or changes to the government support programs. As regulations or assistance terms evolve, businesses may need to modify their Chart of Accounts accordingly.
8. Data Integrity: Ensure data integrity and accuracy in the Chart of Accounts by implementing proper controls and reconciliation processes. This will help maintain the reliability of financial information related to government assistance.

By aligning the Chart of Accounts with the regulations and requirements related to government assistance, businesses can effectively track and manage the funds received, demonstrate compliance, and fulfill their reporting obligations. This level of financial diligence not only helps businesses benefit from the support offered but also ensures responsible and accountable use of public resources during times of crisis or economic challenges.

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Pandemics such as Covid

Are there any examples of how governments help businesses and organizations to get on their feet with a pandemic such as Covid-19?

Yes, governments around the world have implemented various measures to help businesses and organizations get back on their feet during the Covid-19 pandemic. The pandemic had a profound impact on economies, leading to widespread disruptions and financial challenges for businesses. Some examples of how governments provided assistance and support to businesses during the Covid-19 pandemic include:

1. Financial Relief Packages: Many governments introduced financial relief packages that included grants, loans, and subsidies to help businesses cover operational costs and maintain their workforce. These packages aimed to provide immediate financial support and bridge the gap during periods of economic uncertainty.
2. Wage Subsidies and Job Retention Schemes: Several countries implemented wage subsidy programs to encourage employers to retain their employees during the pandemic. These subsidies helped businesses keep their workforce employed, even if their operations were temporarily affected.
3. Tax Deferrals and Payment Extensions: Governments offered tax deferrals and extensions on tax payments to ease the immediate financial burden on businesses. This provided businesses with more time to manage their cash flow during challenging periods.
4. Industry-Specific Support: Some governments provided targeted support to industries that were particularly hard-hit by the pandemic. For example, sectors like hospitality, tourism, and entertainment received specific assistance measures tailored to their needs.
5. Access to Credit and Financing: Governments collaborated with financial institutions to offer credit facilities, loan guarantees, or low-interest loans to businesses that needed capital to continue their operations.
6. Rent Relief and Commercial Eviction Bans: To ease the burden on businesses facing rent obligations, some governments implemented rent relief programs or banned commercial evictions during specific periods of the pandemic.
7. Health and Safety Guidelines: Governments issued health and safety guidelines for businesses to follow to protect their employees and customers from the spread of Covid-19. Compliance with these guidelines was often essential for businesses to continue operating during the pandemic.
8. Digital Transformation Support: Governments encouraged businesses to adopt digital technologies to adapt to the new normal. Some provided grants or training programs to help businesses transition

to online operations and e-commerce.

9. Support for Small and Medium Enterprises (SMEs) : Many governments recognized the importance of SMEs and provided special support programs tailored to their unique needs, as they often faced more significant challenges during the pandemic.
10. Recovery and Revitalization Initiatives: As the pandemic situation improved in some regions, governments launched recovery and revitalization initiatives to stimulate economic activity and help businesses rebound.

It's important to note that the specific measures and extent of government support varied across countries and regions, depending on the severity of the pandemic and each government's fiscal capacity and policy priorities. Governments continuously adapted their assistance programs based on the evolving nature of the pandemic and its economic impact.

Overall, the aim of these support measures was to provide businesses with the necessary resources and stability to weather the crisis, protect jobs, and contribute to economic recovery in the aftermath of the Covid-19 pandemic.

Pandemics such as Covid-19 had a global impact - In which countries was affected

As of ChatGPT's last update in September 2021, the Covid-19 pandemic had a significant global impact, affecting nearly every country in the world. It spread rapidly and led to widespread health, social, and economic disruptions. The impact of the pandemic varied from country to country based on factors such as population density, healthcare infrastructure, government response measures, and adherence to public health guidelines.

It is essential to note that the situation regarding the Covid-19 pandemic is dynamic, and the impact may have evolved since ChatGPT's last update. However, as of September 2021, some of the countries that were particularly affected by the Covid-19 pandemic included:

1. United States: The United States experienced a high number of Covid-19 cases and fatalities, making it one of the most affected countries in terms of both infections and deaths.
2. Brazil: Brazil also experienced a significant impact, with a high number of Covid-19 cases and fatalities.
3. India: India faced a severe surge in Covid-19 cases during the second wave of the pandemic, which strained its healthcare system and led to numerous deaths.
4. United Kingdom: The United Kingdom faced several waves of the pandemic, leading to substantial disruptions in healthcare, social life, and the economy.

5. Italy: Italy was one of the early epicenters of the pandemic in Europe and faced a high number of Covid-19 cases and deaths.
6. Spain: Spain also experienced a significant impact during the early stages of the pandemic, with high infection rates and fatalities.
7. France: France faced multiple waves of Covid-19, leading to healthcare challenges and economic disruptions.
8. Russia: Russia experienced a high number of Covid-19 cases and implemented various measures to contain the spread of the virus.
9. China: China, where the pandemic originated, was one of the first countries to be affected and implemented strict measures to control the spread of the virus.

It's important to recognize that Covid-19's impact was not limited to these countries alone. The pandemic had a global reach, affecting economies, healthcare systems, and daily life in nearly every nation around the world. Governments and international organizations worked together to address the challenges posed by the pandemic, develop vaccines, and implement public health measures to mitigate its effects.

For the most current information on the global impact of Covid-19, it is recommended to refer to updated sources such as the World Health Organization (WHO), the Centers for Disease Control and Prevention (CDC), and other reputable health agencies.

Chart of Accounts - Pandemics such as Covid

Pandemics, such as the Covid-19 pandemic, can have significant financial implications for businesses, governments, and individuals. In the context of the Chart of Accounts, various accounts may be relevant to track the financial effects of pandemics:

1. Revenue Accounts:
    - Sales - Pandemic Impact: This account can be used to track the revenue generated during the pandemic period. It may include specific products or services that saw increased or decreased demand due to the pandemic.
2. Expense Accounts:
    - Staff Wages - Pandemic Relief: This account can be used to track any additional wages or benefits provided to staff during the pandemic, such as hazard pay or special relief packages.
    - Healthcare Expenses: This account can be used to track expenses related to providing healthcare benefits or medical supplies to employees and customers during the pandemic.
    - Remote Work Expenses: This account can be used to track additional expenses incurred to

facilitate remote work arrangements, such as purchasing equipment or software.

- Cleaning and Sanitization: This account can be used to track expenses related to increased cleaning and sanitization efforts in workplaces and public spaces.
- Insurance Claims - Business Interruption: This account can be used to track insurance claims made for business interruption or other losses caused by the pandemic.
- Contingency Fund Utilization: If the organization maintains a contingency fund, this account can be used to record the utilization of funds to address pandemic-related expenses.

3. Liabilities:
   - Provisions for Pandemic Costs: This account can be used to record estimated costs and liabilities associated with the pandemic, such as potential legal claims or refunds to customers.
4. Assets:
   - Inventory - Perishable Goods: If the business deals with perishable goods, this account can be used to track the value of inventory that may be at risk of spoilage due to disruptions caused by the pandemic.
   - Remote Work Equipment: This account can be used to track the value of equipment purchased for remote work arrangements.
   - Accounts Receivable - Pandemic Impact: This account can be used to track outstanding receivables that may have been affected by the pandemic, such as delayed payments from customers.
5. Equity:
   - Reserves - Pandemic Relief: This account can be used to track any specific equity reserves set aside to address pandemic-related financial challenges.

It's important to note that the Chart of Accounts should be adapted to the specific needs and circumstances of each organization. Additionally, financial reporting and accounting for pandemics may require compliance with specific accounting standards and regulations that address the unique circumstances presented by such events. Properly accounting for the financial effects of a pandemic can help businesses and organizations make informed decisions, manage resources effectively, and demonstrate transparency in financial reporting.

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Disaster Management and Acts of God

Disaster management and Acts of God are related to how individuals, organizations, and governments respond to and mitigate the impacts of natural or human-induced disasters. Let's explore each of these concepts:

1. Disaster Management: Disaster management refers to the coordinated efforts and strategies put in place to prepare for, respond to, and recover from disasters. Disasters can include natural disasters like earthquakes, floods, hurricanes, wildfires, and tsunamis, as well as human-induced disasters like industrial accidents, terrorist attacks, and pandemics. The key components of disaster management include:
    - Preparedness: Planning and organizing resources, infrastructure, and personnel in advance to effectively respond to disasters. This includes creating emergency response plans, conducting drills and exercises, and establishing communication systems.
    - Response: Immediate actions taken to address the emergency when a disaster occurs. This involves search and rescue operations, providing medical aid, and coordinating emergency services.
    - Recovery: The process of restoring and rebuilding communities after a disaster. This includes rehabilitation, reconstruction, and support for affected individuals and businesses.
    - Mitigation: Strategies to reduce the impact of future disasters. This can involve implementing building codes, constructing flood barriers, promoting sustainable land use, and raising awareness about disaster risk reduction.
2. Acts of God: The term "*Acts of God*" is often used in insurance and legal contexts to describe events that are beyond human control and are not caused by human actions. Acts of God are typically considered natural disasters or catastrophic events caused by forces of nature. These events are unforeseen, unexpected, and cannot be prevented or avoided. Examples of Acts of God include earthquakes, lightning strikes, volcanic eruptions, hurricanes, and tornadoes.

In insurance contracts, "*Acts of God*" are usually specified as events for which coverage may be provided, depending on the type of insurance policy. It is essential for individuals and businesses to understand their insurance coverage and whether it includes protection against Acts of God.

It's worth noting that disaster management is focused on preparing for and responding to disasters, whether they are natural or human-induced. Acts of God, on the other hand, specifically refer to

uncontrollable and unforeseen natural events. Both concepts are essential in understanding how societies and organizations cope with and recover from adverse events that can significantly impact communities, economies, and the environment.

Are there any examples of how governments help businesses and organizations to get on their feet?

Yes, governments often play a crucial role in providing support and assistance to businesses and organizations to help them get back on their feet after facing challenges such as economic downturns, natural disasters, or other adverse events. Here are some examples of how governments can help businesses during difficult times:

1. Financial Assistance and Grants: Governments may offer financial assistance in the form of grants, low-interest loans, or subsidies to help businesses cover immediate expenses or invest in recovery efforts. These funds can be directed towards rebuilding infrastructure, restocking inventory, or supporting employee wages.
2. Tax Relief and Incentives: Governments may provide tax relief measures, such as tax breaks, deferred tax payments, or tax credits, to ease the financial burden on businesses during challenging periods. These incentives can improve cash flow and make it easier for businesses to recover.
3. Business Recovery Funds: Governments may establish dedicated funds to support businesses affected by specific events, like natural disasters or economic crises. These funds can be used to provide targeted assistance and ensure a more rapid recovery for impacted businesses.
4. Employment Support: To prevent lay-offs and maintain employment levels, governments may implement wage subsidy programs that help businesses retain their workforce during chllenging times.
5. Access to Credit and Financing: Governments can collaborate with financial institutions to provide businesses with easier access to credit and financing options. This helps businesses secure the necessary capital to restart operations and invest in growth.
6. Support for Innovation and Diversification: In times of crisis, governments may encourage businesses to innovate and diversify their operations to adapt to changing market conditions. Funding programs or initiatives may be put in place to support research and development, technology adoption, and market expansion.
7. Streamlined Regulatory Processes: Governments can expedite permitting and licensing processes to help businesses resume operations more quickly after a disruption. Reducing bureaucratic hurdles can speed up recovery efforts.
8. Industry-Specific Assistance: In sectors heavily impacted by adverse events, governments may

provide tailored support to address unique challenges faced by those industries. This could include support for tourism, agriculture, healthcare, or other sectors directly affected by disasters or crises.

9. Training and Skills Development: To help businesses rebuild and thrive, governments may offer training programs and skill development initiatives to equip workers with new competencies aligned with emerging opportunities.
10. Public-Private Partnerships (PPPs): Governments can partner with private businesses and organizations to pool resources, expertise, and knowledge to jointly address recovery challenges.

It's essential to note that the type and extent of government assistance may vary depending on the severity and nature of the crisis and the country's financial capacity. Governments often work in collaboration with local authorities, non-governmental organizations, and international partners to implement these support measures effectively. Businesses should proactively seek information about available government assistance programs and engage with relevant agencies to access the support they need during challenging times.

Disaster Management and Acts of God - Accounts for governments support and assistance in the Chart of Accounts

In a Chart of Accounts for a government entity or a business that receives government support and assistance for disaster management and acts of God, the accounts related to such support and assistance would typically be categorized under specific revenue and expense accounts. Here are some typical accounts that may be included:

1. Revenue Accounts:
    - Grants - Disaster Relief: This account is used to record the revenue received from the government as grants specifically designated for disaster relief efforts and assistance in the aftermath of acts of God.
    - Subsidies - Disaster Management: This account is used to record any subsidies received from the government to support ongoing disaster management activities or to cover costs associated with preparedness and prevention measures.
    - Emergency Funding: This account is used to record any emergency funding received from the government during times of crises caused by natural disasters or acts of God.
2. Expense Accounts:
    - Disaster Relief Expenditures: This account is used to track all expenses related to providing relief and assistance to individuals, communities, or businesses affected by disasters and acts of God.

- Disaster Recovery Costs: This account is used to record expenses incurred during the recovery and reconstruction phase following a disaster or act of God.
- Preparedness and Prevention Costs: This account is used to track expenses related to measures taken to prepare for potential disasters and mitigate their impact on communities and infrastructure.
- Emergency Response Expenses: This account is used to record expenses incurred during immediate emergency response efforts when disaster strikes.

3. Other Accounts:

- Contingency Reserve: This account is used to set aside funds as a contingency reserve to be utilized for disaster management and acts of God if needed.
- Catastrophe Fund: Some governments or businesses may maintain a separate fund specifically designated to cover expenses related to catastrophic events, including acts of God.

It's important to note that the specific accounts and their names may vary depending on the organization's structure, accounting practices, and the nature of government support and assistance received. Additionally, the Chart of Accounts should align with any applicable accounting standards and reporting requirements.

Having these specific accounts in the Chart of Accounts helps the organization track and report on the financial impact of disaster management efforts and acts of God, ensuring transparency and accountability in the use of government support and assistance. It also allows for effective financial planning and budgeting for future disaster-related events.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

SASRIA - South African Special Risks Insurance Association

What is SASRIA?

SASRIA, also known as the South African Special Risks Insurance Association, is a state-owned, non-profit insurance company based in South Africa. It was established in 1979 by the South African government to provide insurance coverage for special risks that are not typically covered by standard insurance policies offered by private insurers.

The primary function of SASRIA is to offer insurance coverage against certain politically motivated or politically motivated-related risks, as well as acts of terrorism, riots, strikes, civil commotion, public

disorder, and malicious damage. These risks are often excluded from standard insurance policies, making it essential for businesses and individuals to seek coverage from a specialized insurer like SASRIA.

Key features of SASRIA and its coverage include:

1. Non-Profit Nature: SASRIA operates on a non-profit basis, and any excess premiums collected are used to strengthen the association's reserves and enhance its ability to meet claims.
2. Mandatory Coverage: Certain types of insurance, such as motor insurance and property insurance for commercial properties, may require compulsory SASRIA coverage in South Africa.
3. Affordable Premiums: SASRIA's premiums are generally considered affordable, and its coverage provides an extra layer of protection against politically motivated risks and acts of terrorism.
4. Special Risks Coverage: SASRIA provides coverage for a wide range of special risks, including damage to property and assets resulting from riots, strikes, and civil unrest.
5. Catastrophic Events: SASRIA plays a critical role in offering insurance coverage against catastrophic events that can have significant financial implications for businesses and individuals.
6. Public Liability Coverage: SASRIA's coverage extends to public liability, protecting insured parties against third-party claims arising from the covered risks.
7. Commercial and Personal Policies: SASRIA coverage is available for both commercial and personal policies, providing protection for various types of assets and risks.

It's important to note that SASRIA is specific to South Africa and serves as an important mechanism to protect businesses, properties, and assets against politically motivated risks and civil unrest. As a state-owned entity, SASRIA operates under the regulations and guidelines set by the South African government and fulfils a critical role in the country's insurance landscape.

Is is SASRIA compulsory for businesses in South Adrica?

Yes, SASRIA (South African Special Risks Insurance Association) is compulsory for businesses in South Africa. SASRIA provides insurance coverage for special risks, such as damage caused by riots, strikes, civil commotion, terrorism, and malicious damage. While many standard insurance policies in South Africa cover common risks like fire, theft, and natural disasters, they do not typically include coverage for damage caused by civil unrest, riots, and acts of terrorism.

To address this gap in insurance coverage, the South African government made SASRIA coverage mandatory for businesses and other entities in the country. This requirement ensures that businesses are protected against specific risks related to civil unrest and acts of terrorism, which are unique to certain regions and periods of time.

The compulsory nature of SASRIA coverage means that businesses operating in South Africa must include

SASRIA insurance in their risk management and insurance portfolios. Businesses are required to pay a premium based on their specific risk profile, which allows them to access SASRIA coverage for the designated special risks.

Compliance with SASRIA requirements is essential for businesses to avoid potential financial liabilities and losses resulting from events covered by SASRIA. By obtaining this coverage, businesses can better protect their assets, operations, and stakeholders from the potential impact of civil unrest and other special risks specified in the SASRIA policy.

Is similar insurance compulsory in other countries?

The requirement for similar insurance coverage, similar to SASRIA in South Africa, is not universal across all countries. The need for specialized insurance coverage for risks like civil unrest, riots, terrorism, and malicious damage can vary depending on the specific risk landscape and the prevalence of such events in each country. As a result, not all countries have a compulsory insurance scheme like SASRIA.

However, some countries do have specific insurance arrangements or government-backed insurance programs that address unique risks or provide coverage for events that are not typically covered by standard insurance policies. These programs are often designed to address risks that may be more prevalent in certain regions or industries.

Examples of similar insurance programs in other countries include:

1. Terrorism Risk Insurance Programs: Some countries, especially those at higher risk of terrorism, have established government-backed or public-private partnership terrorism insurance programs. These programs provide coverage for losses resulting from acts of terrorism.
2. Natural Disaster Insurance Pools: Countries located in regions prone to natural disasters, such as earthquakes, hurricanes, or floods, may have established insurance pools or government-backed programs to provide coverage for damages resulting from these events.
3. Riots and Civil Unrest Coverage: In regions with a history of civil unrest or political instability, insurers may offer specialized insurance policies that cover damage resulting from riots, strikes, and civil commotion.
4. War Risk Insurance: In some cases, businesses operating in areas with heightened geopolitical risks or conflicts may seek war risk insurance coverage to protect against losses related to war, armed conflict, or political violence.

The availability and compulsory nature of such insurance programs depend on the country's legal and regulatory framework, its assessment of risk exposures, and the specific needs of the economy and society. Some countries may rely on private insurance markets to address these risks, while others may implement government-supported initiatives to ensure adequate coverage.

If businesses operate in countries other than South Africa, they should investigate the specific insurance requirements and risk landscape of those regions to determine the need for any specialized or compulsory insurance coverage related to civil unrest, terrorism, or other unique risks. Local insurance providers and regulatory authorities can provide valuable information and guidance on insurance options available in each respective country.

How do SASRIA fit in a Chart of Accounts - What would the typical transactions and accounts be?

In a Chart of Accounts, SASRIA would typically be categorized as an insurance expense account. Since SASRIA provides insurance coverage for special risks, the premiums paid to SASRIA would be recorded as an expense to the business or organization.

Here's how SASRIA would fit into a Chart of Accounts, along with some typical transactions and accounts:

1. Chart of Accounts Category:
    - Insurance Expense: This is the category under which the SASRIA premium expenses would be recorded.
2. Typical Account for SASRIA Premiums:
    - Insurance Expense - SASRIA: This account would be used to record the premium expenses paid to SASRIA for coverage against special risks, such as riots, strikes, civil commotion, public disorder, terrorism, and malicious damage.
3. Typical Transactions:
    - Payment of SASRIA Premium: When the business makes the premium payment to SASRIA for the insurance coverage, the transaction would be recorded as a debit to the "Insurance Expense - SASRIA" account and a credit to the bank or cash account.
    - Monthly/Quarterly/Annual Adjustment: Depending on the frequency of premium payments, the "Insurance Expense - SASRIA" account would be adjusted accordingly to reflect the expense for the specific period.
4. Additional Accounts:
    - It's important to note that in addition to the SASRIA premium expense, the business may have other insurance expenses related to standard insurance coverage for assets, liability, motor vehicles, etc. Each type of insurance coverage would have a separate expense account in the Chart of Accounts.
    - For example:

- Insurance Expense - Property Insurance
- Insurance Expense - General Liability Insurance
- Insurance Expense - Motor Vehicle Insurance

It's essential to tailor the Chart of Accounts to the specific needs and complexities of the business or organization. The accounts mentioned above are general examples, and the actual structure may vary depending on the industry, size, and unique insurance requirements of the entity.

By allocating the SASRIA premium expenses to a specific account, businesses can accurately track their insurance costs and understand the financial impact of this special risk coverage. Properly categorizing the insurance expenses ensures transparent financial reporting and facilitates the management's ability to make informed decisions about risk management and insurance coverage.

SASRIA Premiums - Accrual basis

When recording SASRIA premiums on an accrual basis in the Chart of Accounts, you would follow the principles of accrual accounting, which recognizes revenue and expenses when they are earned or incurred, regardless of when the cash transactions occur. Here's how SASRIA premiums would be recorded on an accrual basis:

1. Accrual Accounting Principle:
    - Under accrual accounting, SASRIA premiums would be recognized as an expense in the accounting period when the insurance coverage is effective and the business incurs the liability for the premium. This is the period during which the risk coverage is provided, regardless of whether the actual payment has been made.
2. Typical Account for SASRIA Premiums on Accrual Basis:
    - Insurance Expense - SASRIA: This account is used to record the accrued SASRIA premium expense for the accounting period.
3. Recording the Accrual:
    - At the end of each accounting period (month, quarter, or year), the business will accrue the SASRIA premium expense for the coverage provided during that period.
    - To record the accrual, the business will make the following adjusting entry:

        Debit: Insurance Expense - SASRIA (Income Statement Account)
        Credit: Accrued Liabilities - SASRIA Premium (Balance Sheet Account)

    The debit to the "*Insurance Expense - SASRIA*" account recognizes the expense in the income statement, and the credit to the "Accrued Liabilities - SASRIA Premium" account establishes the liability for the

unpaid premium.

4. Payment of Accrued SASRIA Premium:

   When the business makes the actual payment of the accrued SASRIA premium, a separate journal entry is made to reflect the payment:

   Debit: Accrued Liabilities - SASRIA Premium (Balance Sheet Account)
   Credit: Bank or Cash Account (Balance Sheet Account)

   This entry reduces the liability for the accrued premium and reflects the cash outflow for the payment.

5. Reversal of Accrual (If Applicable):

   If the business makes the premium payment before the end of the accounting period to which the accrual applies, a reversal entry may be required to avoid double counting the expense.

   Debit: Accrued Liabilities - SASRIA Premium (Balance Sheet Account)
   Credit: Insurance Expense - SASRIA (Income Statement Account)

   This entry eliminates the accrual for the portion of the premium already paid.

By using the accrual basis to record SASRIA premiums, the financial statements will accurately reflect the expenses incurred during each accounting period, providing a more accurate picture of the business's financial performance and obligations related to insurance coverage. Accrual accounting helps in matching revenues and expenses in the appropriate accounting periods, improving the overall financial reporting accuracy.

SASRIA - Is there similar regulations and legislation in other countries or jurisdictions?

SASRIA (South African Special Risks Insurance Association) is a unique state-owned insurance association in South Africa that provides coverage for special risks, such as damage caused by riots, strikes, civil commotion, terrorism, and malicious damage. While SASRIA is specific to South Africa, there are similar entities and insurance coverage options available in some other countries, particularly in regions prone to certain types of risks. These entities are often established to provide insurance coverage for risks that are not typically covered by standard insurance policies.

Although the specific names and structures of such insurance entities may vary, they serve similar functions in providing coverage for special risks. Some examples of similar entities in other countries include:

1. Terrorism Risk Insurance Programs: In some countries, governments have established terrorism risk insurance programs to provide coverage against losses resulting from acts of terrorism. These programs are often designed to complement private insurance coverage for terrorism-related risks.

2. Riots and Civil Commotion Coverage: Some insurers in regions with a history of civil unrest or political instability may offer specialized insurance policies that cover damage resulting from riots, strikes, and civil commotion.
3. Natural Disaster Insurance Pools: In areas prone to natural disasters such as earthquakes, hurricanes, or floods, some countries have established insurance pools or government-backed programs to provide coverage for damages resulting from these events.
4. Specialized Insurance Programs: Certain regions or industries may have unique risks that are not adequately covered by standard insurance policies. As a result, specialized insurance programs or associations may be established to address these specific risks.

It's important to note that the availability of such specialized insurance coverage varies from country to country and depends on the prevalent risks and the government's approach to managing these risks. Additionally, the legal and regulatory frameworks that govern insurance entities differ in each jurisdiction.

For businesses operating in regions with unique risks that may not be fully covered by standard insurance, it is crucial to conduct thorough risk assessments and explore available insurance options to adequately protect their assets and operations. Consulting with insurance professionals familiar with the local market and regulatory environment can help businesses make informed decisions about their insurance needs.

Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

osFinancials5/TurboCASH5 Program

The osFinancials5/TurboCASH5 program is easy to use with a user-friendly graphical interface. When launching osFinancials5/TurboCASH5 for the first time, the osFinancials5/TurboCASH5 program will be displayed in the language linked to a Set of Books, when a Set of Books is opened in osFinancials5/TurboCASH5 is launched for the first time.

For the purposes of this documentation, the images (screenshots) are displayed in the default English language.

By default, osFinancials5 will be displayed in the "Classic" theme. You may select another theme (i.e. "Blue, Glass, Material, Silver, Soft-blue" or "VS2010") on Theme (Setup ribbon) to change the appearance of osFinancials5/TurboCASH5.

The Material-navy theme (black icons) is used for screen captures in the rest of this documentation.

The Blue, Glass, Silver, Soft-blue theme includes a similar set of icons as in the Material theme (navy-blue

icons).

The "Classic" theme (default theme) and "VS2010" theme displays the same set of icons (located in the "... \bin\themes\Classic" folder.

Most of the program options can be easily accessed by one or more mouse-clicks or by pressing a few buttons on the keyboard.

osFinancials5/TurboCASH5 offers many features and options. To enhance your effectiveness and efficiency to perform your tasks in the program, it is important that you can access the required options as quickly and effortlessly as possible. The osFinancials5/TurboCASH5 program screen will be briefly discussed:



The design of the osFinancials5 user-interface (UI) offers you different options, which displays information and/or allows you to access the different features and options:

1. Title bar – Displays the Company name of the opened (active) Set of Books and the name and the version of osFinancials5/TurboCASH5 program.

2. Ribbon bar - Displays the ribbon tabs (i.e. Start, Default, Reports, Setup and User tab).

You may press the F1 key on most screens, fields and tabs to launch the associated (context-sensitive help) topic.

3. Ribbons – The functions and features and utilities are grouped in five Ribbon tabs. These are:

    a) Start - Open, Register (will be displayed until yourosFinancials5/TurboCASH5 is registered), Backup / Restore, Delete Set of Books, Create Set of Books, Save as (Set of Books), Close Set of Books, Switch language and Help (menu list).

    b) Default – Documents, Debtors, Creditors, Stock items, Batch entry, Reconciliation, Open item link, Contacts, Calendar, Update ledger, Edit (menu list), Input (menu list), Search.

    c) Reports – Reports (menu list), User reports (menu list), Spreadsheet reports (menu list), Ledger analyser 1, Ledger analyser 2, T-Account viewer, Printer.

    d) Setup – Company info, Documents, Groups, Stock information, Reporting dates, Access control, Batch types, Salesperson, Printer, Workflow setup, Setup (menu list), Report designer, Import, Export and Tools (menu list).

    e) User tab – This tab is by default not activated. The user tab is a quick menu to manage (customise) the menus, most frequently used. It can be grouped into up to six (6) groups. If users are added in Setup → Access control, it will store the custom menus for each user. There are two (2) options to activate this tab, i.e.:

        i) Auto learn – Tick this option to add the last accessed options to the User tab.

        ii) Edit – Add / Remove the options to be displayed in the User tab.

Show / Hide Ribbon options

You may also hide or show the ribbon options using the Collapse and Pin icons on the bottom of the right-hand corner of the ribbon options strip:



"Collapse the Ribbon" - this will hide the ribbon options strip.

"Pin the Ribbon" - this will show the ribbon options strip.

4. Status bar – The following is displayed in the Statusbar:

    a) User Name – Universal Administrator will be displayed when a Set of Books with no users and passwords. If users and passwords were set in Setup → Access control, it will display User and the user's name.

b) Name of Books - The Name of the opened (active) Set of Books is displayed in the fourth section.

c) Path of the Set of Books - The full path of the opened Set of Books is displayed in the last section.

Most of these program options are only accessible if a valid Set of Books are opened. If no Set of Books are opened, only the Start ribbon tab will be displayed. The Default, Reports, Setup and User tab ribbons will be inactive.

On the Start ribbon, the Open, Backup / Restore, Delete Set of Books, Create Set of Books, Switch language and Exit osFinancials5 options will be accessible.

You need to have a Set of Books opened to access the Register and Save as options.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Ribbons

The functions and features and utilities are grouped in five Ribbon tabs.



Show / Hide Ribbon options

You may need some extra space when working with, Documents, Stock, Debtors, Creditors, Ledger analyser, etc.

To Auto hide the ribbons options, double-click on any of the ribbon tabs. This will hide the options on the ribbon and only display the ribbon tabs and auto-resize (larger) the screens in osFinancials5/TurboCASH5. You may then click on a ribbon tab to select and access the options. Once you have selected an option, the ribbon options will auto hide and only display the ribbon tabs.

To Show the ribbon options and resize the screens (smaller), you may double-click on a ribbon tab .

Show / Hide Ribbon options

You may also hide or show the ribbon options using the "Collapse the ribbon" and "Pin the ribbon" icons on the bottom of the right-hand corner of the ribbon options strip:



"Collapse the Ribbon" - this will hide the ribbon options strip.

"Pin the Ribbon" - this will show the ribbon options strip.

These ribbon tabs are:

1. Start - This ribbon tab is used to manage your sets of books, backups, registration and language.
2. Default -
    a) Records - Debtors, creditors, contacts, stock items, appointments, tasks, etc.
    b) Processing of transactions in sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders), batches (journals), managing open item accounts (adjust payment dates and/or process receipts / remittance advice for payments and/or refunds, etc.
    c) Periodic processing – Open item, Reconciliation, Repeating transactions Repeating invoices.
    d) Search – Search for data in the central search and print transactions and documents, etc.
3. Reports - Print reports, User reports, Spreadsheet reports, Ledger analyser, T-account viewer, Age analysis, Printer setup, etc.
4. Setup - This ribbon tab is used to access the Setup, Tools, Global processes, Themes and Plugins.
5. User tab - This ribbon tab is a custom (quick menu). It is used to manage user navigation in a Set of Books. You may select (tick) the "*Auto-learn*" feature to add the last accessed options in up to six (6) groups.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Start ribbon

The Start is used to manage your sets of books, backups, registration and language.



The following nine options are available:

1. Open - This option allows you to open an existing Set of Books, which is essentially a collection of financial data and records that you have previously created / saved.

2. Backup / Restore - With this option, you can create a backup file of your current Set of Books, which is useful for data recovery in case of loss or corruption. You can also restore a Set of Books from a valid backup file.

3. Close Set of Books - This option allows you to close the currently opened Set of Books. Once the Set of Books is closed, you will not be able to access any of its data or records until you reopen it.

4. Create Set of Books - You may use the different options available when creating a new Set of Books in osFinancials:

    a) Copy an existing Set of Books - With this option, you can create a new Set of Books by making an exact copy of an existing one. This includes all of the data contained within the Set of Books. You simply select the Set of Books you want to copy and the system will create a new one in a directory of your choosing.

    b) Let osFinancials help you to create a Set of Books - This option allows you to create a new Set of Books by selecting a selected Set of Books as a template. The program will then guide you through the process of setting up your new Set of Books. You can also download pre-existing Sets of Books for your specific country or industry as templates to use as a starting point. See a list of the Sets of Books available for a download.

    c) Create a Set of Books (Advanced) - This option is intended for more advanced users who want to create a new Set of Books from scratch. In addition to the Firebird database type, you can also select to create a Set of Books using the MSSQL database type. This option provides more flexibility and control over the structure and content of your new Set of Books.

5. Delete Set of Books - If you no longer need a particular Set of Books, you can use this option to permanently delete it.

6. Save as - This option is used to save a copy of the currently opened Set of Books with a different name.

7. Switch language - With this option, you can change the language used in the osFinancials5/TurboCASH5 program.

8. Online registration - This option will take you to the "*Register your osFinancials / Register your TurboCASH*" screen where you can register your copy of osFinancials5/TurboCASH5 online.

9. Help -

    a) Help - This option will launch the context-sensitive Help file and display support information respectively. You can use the Help file to get more information on any particular feature or option in osFinancials5/TurboCASH5. You may press F1 to launch the help file from most screens and fields to launch the topic relating to that screen or field. This help system is designed to assist users in understanding and navigating the osFinancials accounting software, as well as to provide guidance on accounting principles and practices.

    b) Support - This option will provide you with contact information for technical assistance.

    c) Show welcome - This option will display the latest news and updates related to osFinancials5/TurboCASH5.

    d) Updates - Once you install osFinancials5/TurboCASH5 on your system, updates will be released from time to time, containing bug fixes, new features, and other improvements. You may use the "*Updates*" option to install an updated version of osFinancials5/TurboCASH5.

    e) Forum - With this option, you can access the osFinancials forum where you can ask questions or search for solutions to issues that other users have faced.

    f) Webshop - This option will take you to the osFinancials webshop where you can purchase additional features or support services.

    g) Bug report - This will land on the osFinancials Forum page where you can report any bugs or issues you encounter while using the program.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with a Help Authoring Tool

Default ribbon

The Default ribbon in osFinancials5/TurboCASH5 is used to manage various aspects of your business operations.

- Master files – It includes tools for managing master files such as debtors, creditors, contacts, stock items, appointments, and more.
- Transactions - You can also use this ribbon to process transactions, including sales documents (invoices, credit notes, quotes) and purchase documents (purchases, supplier returns, orders), as well as batches (journals).
- Periodic processing – Additionally, the Default ribbon provides tools for periodic processing, such as open item management, cash-book transactions, and repeating transactions or invoices.
- Search – The search function allows you to search for data in a central search and print transactions and documents as needed.



The Default ribbon offers fourteen (14) options to process and manage various aspects of the Set of Books:

1. Documents - The Documents feature allows you to process and manage sales documents like invoices, credit notes, and quotes for your debtor (customer / client) accounts Similarly, you can process and manage purchase documents like purchases, supplier returns and orders for your creditor (supplier / vendor) accounts. The Documents option allows you to manage all these documents, and it automatically generates the required transactions and source documents. Additionally, you can print, reprint, and choose from various layout files for these documents.
2. Debtors - The Debtors feature allows you to manage debtor (customer/ client) accounts. You can create new accounts, edit existing ones, delete or disable accounts as needed. This feature also provides filtering and search options to locate specific debtor (customer/ client) accounts. Within a debtor (customer/ client) account, you can make changes to the name, contact details, addresses,

messages, accounting information, and payment terms. You can also manage various activities, such as Contacts, Appointments or tracking transactions, on the Documents, Transactions, Bank accounts, Backorders and Stock items tabs. Overall, the Debtors feature is designed to help you efficiently manage and track customer or client accounts, allowing you to provide better service and ensure accurate financial records.

3. Creditors - The Creditors feature allows you to manage creditor (supplier / vendor) accounts. You can create new accounts, edit existing ones, delete or disable accounts as needed. This feature also provides filtering and search options to locate specific creditor (supplier / vendor) accounts. Within a creditor (supplier / vendor) account, you can make changes to the name, contact details, addresses, messages, accounting information, and payment terms. You can also manage various activities, such as Contacts, Appointments or tracking transactions, on the Documents, Transactions, Bank accounts and Stock items tabs. The overall purpose of the Creditors feature is to enable you to efficiently manage and track creditor (supplier / vendor) accounts, which in turn allows you to provide better service and ensure accurate financial records.

4. Stock items - The Stock items feature allows you to manage your inventory items or products. You have the ability to create new stock items or products, edit existing ones, delete or disable items as needed. The feature provides filtering and search options to help you locate specific items. Within each item, you can make changes to the stock code, description, extra description, quantities, reorder levels and more. You can also manage various settings on the Ledger tab and various activities on the Document groups, Transactions, Image, Multi-group, and Backorders tabs. By using the Stock Items feature, you can efficiently manage and track your inventory, providing better service and ensuring accurate financial records.

5. Batch entry - Batch entry is a process of entering multiple transactions into batches or journals, and then processing those transactions in the selected batch or journal. This feature enables you to import multiple transactions at once from a spreadsheet or an exported file, instead of manually entering and processing each transaction. This helps to streamline financial and accounting processes, especially for businesses or organizations with high volumes of transactions. Additionally, you can print a posted batch type report for selected batches (journals).

6. Cash / Bank entry - Reconcile transactions is processed (entered form bank statements) in separate payment batches and receipt batches (linked to a bank account). (If the "*Default bank reconciliation*" option is selected).

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin licence is included in the 7. osFinancials5/TurboCASH5 Business class subscription.

The Bank import plugin is a tool that can be added to the software to import bank transactions and save users time on data entry. Bank statements can be imported into a single cash-book journal (combined payments journal and receipts journal). The imported transactions can be easily linked to debtor, creditor, or other accounts, and payments can be linked to specific invoices with just a few clicks. To activate this feature, go to Setup ribbon, select Setup → System Parameters..

7. Open item link - Process and edit links for open item accounts, adjust payment dates, and process receipts or payments.

8. Contacts - Create and edit contact persons and print a contact list.

9. Calendar - The calendar / planner allows you to manage (schedule, add, edit, delete) events (appointments, debtor appointments, creditor appointments, repeating invoices and to generate quotes / invoices for events). It also allows you to (add / edit / delete) contacts and tasks.

10. Spreadsheet sales - Process sales in a spreadsheet

11. Update ledger - Update (post) sales documents (i.e. invoices and credit notes) and purchase documents (i.e. purchases and supplier returns) and batches to the ledger.

12. Edit - Access the following four (4) options:

    a) Backorders - Add, edit and delete backorders for stock items.

    b) Repeating transactions - Enter / edit transactions in batches of a recurring nature.

    c) Repeating invoices - Generate and process invoices of an recurring nature.

    d) Documents (delete) - Delete sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders).

13. Input - Access the following ten (10) options:

    a) Confirm - Confirm and convert quotes to invoices and orders to purchases.

    b) Adjust stock - Access the Edit Stock screen. You may edit stock items, adjust quantities, prices, etc.

    c) Invoices - Invoices are created for debtors (customers / clients). This will generate a source document which can be printed. The Invoice, can be edited before it is posted (updated) to the ledger.

    When an Invoice is posted (updated) to the ledger, the transactions in the Sales journal will automatically be generated.

d) Quotes - You may need to produce a quote for your debtors (customers / clients). When the quote is accepted, you may confirm the quote (convert the Quote to an Invoice).

e) Credit notes - Credit notes are created for debtors (customers / clients) to correct a transaction or an exiting Invoice or to cancel the Invoice. This will generate a source document which can be printed. The Credit notes, can be edited before it is posted (updated) to the ledger.

When a Credit note is posted (updated) to the ledger, the transactions in the Sales journal (or Sales returns journal) will automatically be generated.

f) Purchases - Purchase documents are created creditors (suppliers). This will generate a source document which can be printed. The Purchase document, can be edited before it is posted (updated) to the ledger.

When a purchase document is posted (updated) to the ledger, the transactions in the Purchase journal will automatically be generated.

g) Supplier returns - Supplier returns are created creditors (suppliers) to correct a transaction or an exiting Purchase or to cancel the Purchase. This will generate a source document which can be printed. The Supplier returns, can be edited before it is posted (updated) to the ledger.

When a Supplier return is posted (updated) to the ledger, the transactions in the Purchase journal (or Purchase returns journal) will automatically be generated.

h) Orders - You may need to place an order with any of your creditors (suppliers). When the goods are received or services are provided, you may confirm the order against the actual goods received and the original order. You will do this by converting the Order to a Purchase document.

i) POS Invoice - If the standard Point-of-Sales is configured, for the Set of Books, you may run and manage a point-of-sales shift and process point-of-sale invoices.

j) Checking for unposted items - This will list any batches and documents with transactions that have not yet been posted (updated) to the ledger.

14. Search - Launch the central search (Investigator) to search and filter for data in the Set of Books.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Reports ribbon

The Reports ribbon is used to access all Reports, User reports, Spreadsheet reports and reports in the Ledger analyser 1 / Ledger analyser 2 and T-Accounts can be accessed and printed and even exported and opened in a Spreadsheet. It is also used to process and analyse Budgets access to the Printer setup.



Buttons 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

In addition to the Printer and Budgets options, the reports is grouped into the seven (7) options:

1. Reports - List the reports in the following groups:

    a) Ledger - You may print the Budget vs actual (3 periods) report, List the General ledger accounts (Chart of accounts) and Transaction reports.

    b) Debtors - You may print various age analysis reports, various listing reports, address labels, transaction reports, debtor statements and ageing analysis reports.

    c) Creditors - You may print various age analysis reports, various listing reports, address labels, transaction reports and creditor remittance advises and ageing analysis reports.

    d) Stock - Reorder reports, listing reports, stock movements, backorder reports. You may also print labels (barcodes).

e) Contacts - Lists the details of all your contacts.

f) Calendar - Print the appointments (events) (i.e. Appointment, Debtor appointment, Creditor appointment and Hours) that was scheduled in the Calendar / Planner.

g) Batch entry - Print the transactions of posted invoices, credit notes purchase and supplier return documents as well as posted batch transactions (i.e. sales journal, purchase journal, payments journals, receipts journals, general journals, etc.).

h) Documents - Lists your documents, such as invoices, credit notes, purchases, supplier returns documents, orders and quotes or a selection of documents or for a selected period.

i) Tax - If you are registered as a Tax (VAT/GST/Sales tax) vendor, you need to print and view reports for a specific period for all your Tax (VAT/GST/Sales tax) or for a specific tax code such as Input Tax (VAT/GST/Sales tax), Output Tax (VAT/GST/Sales tax), Zero-rated Tax (VAT/GST/Sales tax), etc.

j) Sales - Various reports are available to analyse your sales documents. Print Graphs, Debtors, Sales and Items reports for Invoices, Credit notes and Quotes.

k) Sales analysis - You may print reports for five (5) reporting groups (i.e. Debtor group 1, Debtor group 2, Document group 1, Document group 2 and Salespersons) for each sales documents (i.e. quotes, invoices and credit notes). You may also print sales per product for stock group 1 or stock group 2 reports for sales documents.

l) Purchases - Various reports are available to analyse your purchase documents. Print Graphs, Creditors, Purchases and Items reports for Purchase and Supplier return documents as well as Orders.

m) Purchase analysis - You may print reports for five (5) reporting groups (i.e. Creditor group 1, Creditor group 2, Document group 1, Document group 2 and Salespersons) for each purchase documents (i.e. orders, purchases and supplier returns). You may also print purchases per product for stock group 1 or stock group 2 reports for purchase documents.

n) Company info - You may print the details of the bank accounts or the company information, messages and cost of sales settings.

o) Currencies - If you process Multi-currency documents (i.e. Invoices, Credit notes and Quotes for debtors (customers / clients) or Purchases, Supplier returns and Orders for creditors (suppliers / vendors). you may print a list of the "*Currencies*" (added / edited in the Setup → Currencies menu on the Setup ribbon.

p) Plugins - Price agreement report for the Price agreement plugin.

q) Point-of-sale - Sales and Receipt reports for the plugin point-of-sale systems (if you

purchased and use the HorecaPOS or RetailPOS point-of-sale systems).

2. User reports - Any other reports that are under construction. Users may add their own reports in the …\plug_ins\reports\userreports folder.

> *You may use Report designer on the Setup ribbon to create, add or edit document layout files and reports. You may add your own reports to be accessible from the User reports menu.*
>
> - *User reports is stored in the …\plug_ins\reports\userreports filder.*
> - *Document layout files is stored in the …\plug_ins\reports\DOCUMENTS\DOCUMENTS folder.*

3. Spreadsheet reports - The following reports will be opened in the powerful spreadsheet feature in osFinancials5/TurboCASH5:

   a) Creditors - The Creditors → Listing - List postal addresses report will be imported into the spreadsheet.

   b) Debtors - The Debtors → Listing - List postal addresses report will be imported into the spreadsheet.

   c) Transactions per period - List the transactions in posted batches and documents (i.e. sales documents (Invoices and Credit notes) and Purchase documents (Purchases and Supplier returns)) for a selected period in a spreadsheet.

   d) General ledger - Budget

      i) Column balances this year - Reporting group 1

      ii) Column balances this year - This year

   e) General ledger (Transaction totals)

      i) Column balances this year - Reporting group 1

      ii) Column balances this year - This year Column balances

   f) Sales analysis

      i) Stock movement

      ii) Sales per period

4. Ledger analyser 1 - Trial balance, Income statement, Balance sheet, Standard column balances (column view of the Trial balance, Income statement and Balance sheet in one report), Budget vs actual, This year vs last year as well as Column balances.

Export button for all Report types on Ledger analyser 1 / Ledger analyser 2 -

You may save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

5. Ledger analyser 2 - The same reports are available as for the Ledger analyser 1, but it gives you another option to generate. print or export different views and reports.
6. Age analysis - View and choose options for the Age analysis report on screen and print it on the Reports ribbon and on the Open item link - Due tab (Default ribbon).
7. T-Account viewer - Analyse, print and export transactions for specific accounts, etc. You may also export the transactions in the T-Account viewer to spreadsheets.

Column balances - Report types on Ledger analyser 1 / Ledger analyser 2 - The column balances report types will list the transactions of a selected account for each period of Last year and This year in a spreadsheet format.

You may select an account and double-click on any period. This will launch the T-Account viewer with a list of all the transactions for the selected period. You may be print and/or export the transactions.

The following six (6) column balances report types is available:

1. *Column balances - Lists all ledger account balances in a spreadsheet view. These are the ledger accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*
2. *Column balances debtors - Lists the balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
3. *Column balances creditors - Lists the balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts*

are reported in the Creditor's control account on the Trial balance and the Balance sheet.

4. *Column balances D/C - Lists all debit and credit ledger account balances in a spreadsheet view. These are the accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*
5. *Column balances debtors D/C - Lists the debit and credit account balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
6. *Column balances creditors D/C - Lists all debit and credit balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*

8. Printer - Setup and configure the printers on your system.
9. Budgets - You may process your budget figures, copy "*Budget figures from the previous year*" or from "*Actual figures from the previous year*". You may view, filter and analyse the budget figures in the Pivot feature.

This is in addition to the standard option to process budgets in Setup → Accounts (Setup ribbon).

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Setup ribbon

In osFinancials5/TurboCASH5, the Setup ribbon tab provides access to several key features, including the Setup, Tools, Global processes, Themes, and Plugins. These features are designed to enable you to customize your Set of Books and streamline your financial processes.

By accessing the Setup option, you can configure your Set of Books to meet the unique requirements of your business, including setting up your company information, document settings, reporting groups, accounts, and taxes. The Tools option allows you to access various tools that can help you manage your data, including backup and restore options, data import and export features, and more. The Global processes option provides access to batch processing functions, such as posting documents, running reports, and updating stock levels. The Themes option enables you to customize the appearance of your accounting system, while the Plugins option allows you to add additional features and functionality to your system. With the Setup ribbon tab, you can easily manage all aspects of your accounting system and

ensure that your financial data is accurate, up-to-date, and organized.

The Setup ribbon tab is used to access the Setup, Tools, Global processes, Themes and Plugins.



The following nine options (9) options are available:

1. Do year end - This option allows you to close off all nominal accounts (income and expense accounts) and transfer their balances for the current financial year to the Retained Income/Earnings account. The start date and the reporting dates for the financial year will also be created for the new financial year.

2. Import - Import accounts, debtors, creditors, documents and stock from specific file formats.

3. Export - Export accounts, debtors, creditors, documents, stock and posted batches to specific file formats.

4. Tools - Access the following five (5) options:

    a) Blockchain - By default not activated.

    > See *video on osFinancials and Blockchain*.

    b) Data integrity check - This option allows you to run a check on the integrity of your data and generate a corresponding report. By selecting this option, you can verify that your data is accurate and free of errors that could cause issues in your Set of Books. Once the check is complete, you can print the "*Data integrity check report*" to review the results and take any necessary corrective action.

    c) Customise language - Customise (edit, change and translate) language files. This option allows you to edit, change, and translate language files. By selecting this option, you can customise the language used in osFinancials5/TurboCASH5 to better suit your needs or preferences. This might involve making changes to existing language files, translating the osFinancials5/TurboCASH5 into a different language, or creating entirely new language files.

    d) Close active forms - This option allows you to close any open forms or screens within the Set of Books, such as the Documents, Debtors, Creditors, or Stock items screens. By selecting this option, you can quickly close all active forms.

e) Activate plugins - By default, no plugins is activated when osFinancials5/TurboCASH5 is installed. This option allows you to activate / deactivate all plugins, registered plugins or specific plugins. The activated plugins will be available from the Plugins menu (on the Setup ribbon).

5. Global processes - The following four (4) options are available:

   i) Clear / Reset - This option allows you to clear all transactions and balances in a Set of Books. By selecting this option, you will effectively reset the Set of Books, deleting all transactions and balances. However, you also have the option to retain all documents and set them to unposted status.

   ii) Copy from a Set of Books - This option allows allows you to copy data from a chosen Set of Books into the currently active (open) Set of Books. By selecting this option, all the existing data in the active Set of Books will be replaced with the data from the selected Set of Books.

   iii) Reverse posted batch / document - This feature enables you to reverse or cancel transactions in posted batches (journals) and documents.

      - Reverse posted batch (Journal) - This feature allows you to cancel transactions that were processed in batches (journals) which have already been updated (posted) to the ledger. By selecting this option, all the transactions that were previously updated (posted) to the ledger will be cancelled and removed from the transaction file.

        The cancelled transactions will be automatically imported to the selected batch (journal). At this point, you have the option to either erase or delete the entire batch (journal). If you wish to keep the cancelled (reversed) batch, you can edit and correct the transactions, balance the batch, print the batch list, and post it to the ledger.

      - Reverse posted document - This feature cancels the documents as well as any transactions that were generated by the documents (such as invoices and credit notes, purchases, and supplier returns) after they were updated (posted) to the ledger. The cancelled (reversed) document can then be accessed as an unposted document, which you can edit in the Documents section of the Default ribbon and then post (update) to the ledger. If you do not need to update (post) the document to the ledger, you may also choose to delete it using the Edit → Delete - Documents. option on the Default ribbon.

6. Setup -

a) Company info - Enter the company information (name, address telephone, fax numbers e-mail address) and registration numbers for the Company and VAT/GST/Sales Tax, if applicable.

i) You also need to set the default tax method and output method for reports (to screen, printer, file, e-mail or fax).

ii) Load your logo or picture, which you wish to be displayed on the documents.

iii) Set the default currency format and date format in your Windows Operating System.

b) Reporting dates - This option allows you to set the start date of your financial year and define the periods within it. By selecting this option, you can specify when your financial year begins and ends, as well as how it is divided into reporting periods. Additionally, you can close a specific period or year for posting transactions to the ledger, effectively preventing any further changes or updates to that time period. This can be useful for ensuring the accuracy and integrity of your financial records.

c) Documents setup - Settings for sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders). Set the defaults for documents, such as the numbers, batch types, headings and messages and document layout files.

On the Statements setup tab, you may enter a global message to be printed on Debtor statements (Reports → Debtors → Outstanding (Reports ribbon).

d) Accounts - Edit, Add or Delete General ledger accounts, Bank accounts and Tax accounts. Budget figures are also entered, edited or deleted for accounts.

Budget figures may also be processed in the Budgets option on the Reports ribbon. You may also view and analyse budget figures using the Pivot feature.

e) Groups - Set up to 2 Groups for ledger Accounts, Debtors, Creditors, Stock items and Documents for generating reports.

f) Stock information - The following settings are available:

i) Selling prices - Enter (edit) the descriptions for up to 3 selling prices. You may set the default selling price 1 / 2 / 3 which will be used globally when processing documents.

ii) Cost of sales - Set the parameters for Cost of sales (account, batch type, whether you will be using average or latest cost).

iii) Documents setup - This also contains various settings when processing documents and/or working with stock.

iv) Unit size - Specify the unit descriptions and sizes to be displayed in stock item screens and on layout files.

v) Tax classes - Create add, edit Tax classes (Account classes) to which you may select Input Tax codes, Output Tax codes, Sales, Cost of sales and Stock control accounts.

g) Batch types - Create or delete batch types or journals in which you wish to enter transactions. Batch types also need to be linked to sales documents (i.e. invoices and credit notes) and purchase documents (i.e. purchases and supplier returns) on Setup Documents.

h) Access control - Set the passwords, users and access to certain menus for each of your users.

i) Salesperson - Add or remove any salespersons, which will be processing sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders) or cashiers operating Point-of-Sale.

j) Financial categories - Link your Ledger Account groups to Assets, Capital, Expenses, Income or Liabilities.

k) System parameters - Select the indicators for debit and credit, number of decimals to be displayed on reports and documents as well as the number of decimals to be stored. You may also select to display the default system currency symbol.

l) Internet - This option enables you to configure your Internet settings so that you can send reports, statements, and lists to any person or organization via email. To do this, you will need to specify your email's outgoing mail server as set up by your Internet Service Provider on your computer system.

m) Countries - Add and manage the ISO CODE2 and ISO CODE3 as well as ICL CODES for each country. See Country codes.

n) Currencies - You may add / edit currencies and the exchange rates. When processing documents, you may select the currency. This will automatically calculate the prices for that currency.

o) Point-of-Sale - Set the Point-of-Sale parameters, configure printers, peripherals, etc.

p) Workflow Setup -

Workflow plugin - Manual - Shop - Licence : Once-off -

The workflow plugin allows you to record the steps or processes of a task.

The different screens osFinancials5/TurboCASH5 can be created such as the stock screen or debtors / creditors and documents. This allows you to record almost every conceivable process (steps) in a task, visualize and gain instant insight wherever you are in the process and what steps have been taken before.

A step can be assigned to a user and an administrator can see all workflow steps not done (outstanding steps) and possibly assign a task to a user. Outstanding transitions that are possible after showing the step.

Workflow is a knowledge system that can gain your knowledge or just to share it with others. This allows you to formalize your business and capture the steps in an automated system.

Another advantage is that you retain a better overview of your running processes and you have historical data at hand.

q) Printer - Select the default settings for printing reports and documents.

7. Report designer - Edit existing reports and layout files for documents. You may also create and edit your own reports and layout files.

8. Themes - This option enables you to customize the appearance of your accounting system, By default, osFinancials5 is installed in the "*Classic*" theme (default theme), while TurboCASH5 is installed by default in the "*Material-navy*" theme. You may select the "*Material Blue, Glass, Silver, Soft-blue*" or "*VS2010*" theme to be displayed in the program. You may also add your own favourite background pictures.

If you choose to use the "Classic" or "VS2010" theme, the icons that will be displayed will be those from the Classic theme icon set.

However, if you choose to use one of the following themes: "Blue, Glass, Silver", or "Soft-blue", a different set of icons in SVG file format will be displayed in Navy blue colour. On the other hand, if you select the "Material" theme, the same set of icons will be displayed but in the colour Black.

The screenshots in this documentation are captured using the "Material" theme.

9. Plugins - By default, no plugins are listed on this menu. Only activated plugins will be listed.

Most of these plugins are licenced under commercial licences. You need to purchase a licence on which a registration code and instructions will be mailed to you to unlock the full features of these plugins. Multi-User and Plugins need to be registered in Plugins → Tools → Register Plugins on the Setup ribbon.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

---

Spreadsheet Export / Import

Spreadsheet Export / Import -

See video on Improved Export/Import -

The Spreadsheet Export / Import spreadsheet feature allows to easily export data into spreadsheets, edit the data and import it.

Excel Export / Import is available in the following options:

Setup ribbon:

W *Setup → Accounts*

W *Setup → Groups*

W *Import Accounts, Import Debtors/Creditors, Import Stock*

Default ribbon

W *Batch entry (all batches)*

W *Edit → Repeating transactions*

W *Stock (Import / Export tab)*

W *Documents - Context menu - Documents → Spreadsheet import*

Export / Import - Setup ribbon

Export / Import	
Export	*Import*
Accounts	*Accounts*
Debtors	*Debtors*
Creditors	*Creditors*
Stock	*Stock*
Documents	*Documents*
Posted Batches	*Posted batches import* *(Batch entry - F9:Process on the* *Default* *ribbon)*

Export - Reports ribbon

Ledger analyser - Financials

There are six (6) report types, which may be selected (i.e. Trial balance, Income statement, Balance sheet, Standard column balances, Budget vs actual and This year vs last year) which may be printed and exported to spreadsheets.

Column balances

In addition to this, there are 6 report types which may be exported to spreadsheets (i.e. Column balances, Column balances Debit/Credit, Column balances debtors, Column balances creditors, Column balances debtors Debit/Credit, and Column balances creditors Debit/Credit.)

Budgets

Budget figures as entered or processed in the Budgets option on the Reports ribbon; or in Setup → Accounts (Setup ribbon). may be printed and exported. This option, if selected, will list only the budget figures (Budget listing) You may select the "*Budget*" option on the Trial balance, Income statement, Balance

sheet and Standard column balances report types. These budget figures may be printed or exported.

The Budget vs actual is the budget performance report. It will list and compare the budget figures versus the actual posted (updated) transactions. The Budget vs actual report may also be printed or exported.

Transactions

T-Account viewer - You may select a specific account, group, etc. to view the transactions in the T-Account viewer.

On the report types in the Ledger analyser, you may right-click on a selected account, and select the "*Show details*" option on the context menu. You may print these transactions and exported these transactions to spreadsheets.

Open item link

The lists on the Open item link - Totals tab, Transactions tab and selected accounts may be exported and opened in spreadsheets.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Setup menu

In osFinancials5/TurboCASH5, the Setup menu provides access to a range of options that enable you to configure your Set of Books according to your specific business needs.

To access the Setup menu:

1. On the Setup ribbon, select Setup. A list of the menu options will be displayed.



2. Select one of the available options:

   a) Company info - Enter the company information (name, address telephone, fax numbers e-mail address) and registration numbers for the Company and VAT/GST/Sales Tax, if applicable.

      i) You also need to set the default tax method and output method for reports (to screen, printer, file, e-mail or fax).

      ii) Load your logo or picture, which you wish to be displayed on the documents.

      iii) Set the default currency format and date format in your Windows Operating System.

   b) Reporting dates - Set the start date of your financial year and the periods in a financial year. You may also close a specific period or year for posting transactions to the ledger.

   c) Documents setup - Settings for sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders). Set the defaults for documents, such as the numbers, batch types, headings and messages and document layout files.

On the Statements setup tab, you may enter a global message to be printed on Debtor statements.

d) Accounts - Edit, Add or Delete General ledger accounts, Bank accounts and Tax accounts. Budget figures are also entered, edited or deleted for accounts.

> *Budget figures may also be processed in the Budgets option on the Reports ribbon. You may also view and analyse budget figures using the Pivot feature.*

e) Groups - Set up to 2 Groups for ledger Accounts, Debtors, Creditors, Stock items and Documents for generating reports.

f) Stock information - The following settings are available:

i) Selling prices - Enter (edit) the descriptions for up to 3 selling prices. You may set the default selling price 1 / 2 / 3 which will be used globally when processing documents.

ii) Cost of sales - Set the parameters for Cost of sales (account, batch type, whether you will be using average or latest cost).

iii) Documents setup - This also contains various settings when processing documents and/or working with stock.

iv) Unit size - Specify the unit descriptions and sizes to be displayed in stock item screens and on layout files.

v) Tax classes - Create add, edit Tax classes (Account classes) to which you may select Input Tax codes, Output Tax codes, Sales, Cost of sales and Stock control accounts.

g) Batch types - Create or delete batch types or journals in which you wish to enter transactions. Batch types also need to be linked to sales documents (i.e. invoices and credit notes) and purchase documents (i.e. purchases and supplier returns) on Setup Documents.

h) Access control - Set the passwords, users and access to certain menus for each of your users.

i) Salesperson - Add or remove any salespersons, which will be processing sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders) or cashiers operating Point-of-Sale.

j) Financial categories - Link your Ledger Account groups to Assets, Capital, Expenses, Income or Liabilities.

k) System parameters - Select the indicators for debit and credit, number of decimals to be

displayed on reports and documents as well as the number of decimals to be stored. You may also select to display the default system currency symbol.

l) Internet - This option enables you to configure your Internet settings so that you can send reports, statements, and lists to any person or organization via email. To do this, you will need to specify your email's outgoing mail server as set up by your Internet Service Provider on your computer system.

m) Countries - Add and manage the ISO CODE2 and ISO CODE3 as well as ICL CODES for each country. See Country codes.

n) Currencies - You may add / edit currencies and the exchange rates. When processing documents, you may select the currency. This will automatically calculate the prices for that currency.

o) Point-of-Sale - Set the Point-of-Sale parameters, configure printers, peripherals, etc.

p) Workflow Setup -

Workflow plugin - Manual - Shop - Licence : Once-off -

The workflow plugin allows you to record the steps or processes of a task.

The different screens osFinancials5/TurboCASH5 can be created such as the stock screen or debtors / creditors and documents. This allows you to record almost every conceivable process (steps) in a task, visualize and gain instant insight wherever you are in the process and what steps have been taken before.

A step can be assigned to a user and an administrator can see all workflow steps not done (outstanding steps) and possibly assign a task to a user. Outstanding transitions that are possible after showing the step.

Workflow is a knowledge system that can gain your knowledge or just to share it with others. This allows you to formalize your business and capture the steps in an automated system.

Another advantage is that you retain a better overview of your running processes and you have historical data at hand.

q) Printer - Select the default settings for printing reports and documents.

Created with the Standard Edition of HelpNDoc: Converting Word Documents to eBooks: A Step-by-Step Guide with HelpNDoc

Company info

In osFinancials5/TurboCASH5, the Company Information option is available for entering all the necessary details related to your business, such as the address, email address, contact numbers, company registration number, and tax registration number. These details will be displayed on all reports, statements, and lists, ensuring that your business information is readily available to anyone who needs it.

Additionally, it is important to set the Windows default date and currency formats to ensure that your data is displayed correctly.

Furthermore, you have the option to load a logo picture, which can be displayed on your documents and statements. This feature enables you to personalize your documents with your company logo, which can help to increase brand recognition and create a more professional appearance for your business. By using these features, you can ensure that your company information is accurate and up-to-date, and that your documents are customised to reflect your business branding.

To enter and set the Company info and defaults:

1. On the Setup ribbon, select Setup → Company info (Ctrl+F5).



2. Check the details of the company.

Company Reg. No.

If you are registered as a company, a close corporation or a non-profit organisation, the relevant registration number must be entered.

Tax Reg. No.

If you are registered as a VAT/GST/Sales Tax vendor, the VAT/GST/Sales Tax registration number must be entered.

Bank name 1 / 2, Holder's name (Branch code) 1 / 2, Bank account no. 1 / 2, SWIFT 1 / 2 and/or IBAN 1 / 2. may be entered if available.

Your banking information can be used on the BankInvoice layout file or you may add these on your layout files, in the Report designer (accessed from the Reports ribbon or Setup ribbon).

3. Banking Details (Optional). You may enter up to two (2) fields for the following:

   a) Bank name - Enter the name of the bank, if available.

   b) Holder's name - Enter the branch code, if available.

   c) Bank account number - Enter the bank account number, if available.

   d) SWIFT - (Society for Worldwide Interbank Financial Telecommunication). Enter, if available.

SWIFT - See http://en.wikipedia.org/wiki/SWIFT / http://www.theswiftcodes.com/

SEPA - (Single Euro Payments Area) - See - http://en.wikipedia.org/wiki/Single_Euro_Payments_Area

   e) IBAN - (International Bank Account Number). Enter, if available.

See http://en.wikipedia.org/wiki/International_Bank_Account_Number

   f) BIC - (Bank Identifier Code). Enter, if available.

This banking information is added and available to print on the Document layout file (15 codes) and Statements for debtor (customer / client) accounts. You may add these banking details to your own layout files, in the Report designer (accessed from the Setup ribbon).

3. Additional Data (Optional). Enter a contact name, mobile telephone number and or your company's

website.

This information can be added to reports and layout files, in the Report designer (accessed from Setup ribbon).

These fields were created (added) using the FreeFields Plugin. This Plugin is available as a commercial plugin.

4. Click on the Options button. The "*Company info - Options"* screen is displayed:



5. The Tax method is by default set to Invoice based. For the purposes of this documentation, the Invoice based Tax method is used.

6. Select your Default output options for screen, printer, file, fax or e-mail. For the purposes of this tutorial, select "*Screen*".

7. Company Logo leave blank for the purposes of this documentation.

If you have a company logo or picture, which includes the address, you may right-click on the Company logo to load the logo from a valid file format on your system.

This logo can be selected to display on documents (invoices, etc.) and statements.

8. Click on the Set Windows date format/style button to set the date format of your operating system.

> *This option does not work on Linux or Apple operating systems. The settings for this, should be done via the specifics of that operating systems.*

> *If the Set Windows date format/style button does not launch your operating system's (version of Windows™), Regional Settings, you need to open the Regional and Language Settings in the Control Panel to set the format of the Short Date and the correct Currency Symbol.*

> *It is important to check your Windows Date Format, since this format will determine the format in which you will enter your dates for your transactions.*
>
> *It will also determine the format in which your dates will be displayed in the lookup facilities, screens, reports, debtor statements, etc.*
>
> *The date for 1 March 2021 may be displayed in one of the following formats:*
>
> W *YY/MM/DD - 24/03/01*
>
> W *DD/MM/YY - 01/03/24*
>
> W *YYYY/MM/DD - 2024/03/01*
>
> W *DD/MM/YYYY - 01/03/2024*
>
> *The YYYY/MM/DD (2021/03/01) is the format, which is used in this help file.*

9. OpenAI token / OpenAI company key: At the moment, OpenAI and ETL is implemented in the Bank import plugin. In the Bank import plugin, an OpenAI import tab with the System prompt and a user prompt to convert raw bank statement data to a JSON file type. You can enter a user prompt to convert the data.

> *The transformation is guided by system prompts and user prompts are updated and stored in the root directory of your osFinancials5.1 or TurboCASH5-3 installation folder:*
>
> - *oaccounting_banksystemprompt.txt*
> - *oaccounting_bankuserprompt.txt*

If you need to use the OpenAI and ETL (Extract, Transform, Load) functionality in osFinancials5.1 or TurboCASH5-3, you need to enter your valid OpenAI credentials. OpenAI Credentials:

- OpenAI token: Enter your valid OpenAI API token. This token is provided when you subscribe to OpenAI's services.

- OpenAI company key: Enter your OpenAI company key, which is also provided as part of your OpenAI subscription.
- Save the Settings: Click Save to store your OpenAI token and OpenAI company key. Then, click OK to close the window.
- Credentials Storage: Your OpenAI token and company key will be securely stored in the Registry of your local machine under the osFinancials5 folder. This allows the credentials to be used across any Set of Books in both osFinancials5.1 and TurboCASH5-3.
- Verification: Once the credentials are saved, the OpenAI and ETL functionalities should be activated and ready for use within the osFinancials5.1 or TurboCASH5-3.

Important Notes:

- *Ensure that your OpenAI token and company key are valid and active. If you encounter any issues, double-check the credentials and your OpenAI subscription status.*
- *The credentials are stored locally on your machine, so if you move to a different computer, you will need to re-enter the credentials on osFinancials5.1 or TurboCASH5-3 in that machine.*

By following these steps, you should be able to successfully activate OpenAI and ETL functionalities in osFinancials5.1 or TurboCASH5-3.

10. Click on the OK button to save your changes.

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Reporting dates

This option allows you to set the start date of your financial year and define the periods within it. By selecting this option, you can specify when your financial year begins and ends, as well as how it is divided into reporting periods.

Additionally, you can close a specific period or year for posting transactions to the ledger, effectively preventing any further changes or updates to that time period. This can be useful for ensuring the accuracy and integrity of your financial records.

It is important to set up the reporting dates or accounting periods for your financial year. You can select specific reporting periods to print financial statements and other reports, or to filter and export the data in spreadsheets. Typically, this is done on an annual basis, but you can also choose reporting periods that

cover 6 months, 4 months, 3 months, 2 months, or 1 month, depending on your needs.

You can choose to have anywhere from 1 to 13 reporting dates in a year, depending on your needs. These dates help you organize your financial data and generate reports on your entity's financial activities, performance, and position.

If you want to prevent any further posting to a previous reporting period, you can restrict posting for that period or for the entire previous year. However, you'll still be able to view the transactions and details for these "*Closed*" periods.

To set Reporting dates:

1. On the Setup ribbon, select Setup → Reporting dates.



2. To set up your reporting dates in osFinancials5/TurboCASH5, you'll need to select the following options:

    a) Number - This is the number of reporting dates, or financial periods, for which you can enter transactions and view reports. Usually, businesses use 12 periods to cover each calendar month in a financial year (i.e. 1 year).

However, small businesses with minimal transactions may choose to use 6-month periods.

b) Start date - This is the starting date of your financial year. You'll need to enter the date from which you want your reporting periods to begin.

c) Post to other years - By default, this option is ticked, allowing you to process transactions, budgets, and other entries to any of the financial years preceding the financial year in the "*Start date*" field. If you uncheck this box, you won't be able to post anything to the previous financial years.

d) Previous year - By default, this option is ticked, allowing you to process transactions, budgets, and other entries to the previous financial year preceding the this year's reporting periods. If you uncheck this option, you can prevent posting to the previous financial year preceding the this year's reporting periods. This is a helpful feature if you want to avoid inadvertent modifications to data from the previous financial year by users.

e) Open for posting - These options allows you to select specific period(s) in the Post to other years and Previous year columns. last By default, this option is ticked, allowing you to process transactions, budgets, and other entries to the financial periods that ends on the periods specified in the "*Ends on*" field. If you uncheck this box for specific period(s), you won't be able to post anything to that financial period(s) for Post to other years and/or Previous year .

3. If you click on the OK button.

If you choose a number of reporting periods that is different from the default of 12, the "Reporting dates" screen will adjust to show only the number of periods you have entered. You can then customize the descriptions of these periods (for example, using calendar months like "January" to "December") to match your specific needs. These descriptions will appear in the Periods lookup facility for both the current year and the previous year, as well as on reports.

In this documentation, we use the yyyy/MM/dd format (such as 2024/03/01) for short dates. However, you can change the date style or format in your system to display short dates in the way that best suits your needs on screens, reports, and documents in osFinancials5/TurboCASH5.

If the date in your system is beyond the date of the last period indicated on the "Reporting dates" screen, you will receive a prompt to perform a year-end process (Do year end on the Setup ribbon).

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

Groups

Reporting groups refer to a collection of items or entities that are grouped together for reporting or analysis purposes.

These groups are typically defined based on some common characteristics, such as geographical location, product line, department, or business unit.

In finance and accounting, reporting groups are used to aggregate financial data and create reports that provide insights into the financial performance of an organization.

The osFinancials5/TurboCASH5 supports up to two (2) reporting groups for accounts, debtors, creditors, stock, documents. and cost centres. The reporting groups feature in osFinancials5/TurboCASH5 offers a powerful and user-friendly system for filtering and sorting data. This system is much quicker and more efficient than other methods, and allows users to group, sort, and filter data on most screens in a Set of Books with just a few mouse clicks. This feature is particularly useful for managing and analysing data, and makes it easy to print and group data on reports, pivot tables, spreadsheets, and other types of documents. Overall, the reporting groups feature in osFinancials5/TurboCASH5 helps users to work more efficiently and effectively with their data, saving time and improving accuracy.

You may set up to two (2) reporting groups for the following features:

1. Accounts - You have the option to create two (2) reporting groups (Account group 1 and/or Account group 2) that can be used to categorise the various types of accounts in your chart of accounts, including ledger, bank and tax accounts. Each account must be linked to one of these reporting groups in order to be properly classified.

   These reporting groups can be linked to a financial category that will help structure your options for viewing, analysing, and printing financial reports such as the trial balance, income statement and balance sheet.

2. Debtors - You may set up to two (2) reporting groups for your debtors (customers / clients). These groups allows you to group or categorise the debtor (customer / client) accounts on which you would like to report. These groups can be linked to each debtor (customer / client) account for better reporting.

3. Creditors - You may set up to two (2) reporting groups for your creditors (suppliers / vendors). These groups allows you to group or categorise the creditor (supplier / vendor) accounts on which you would like to report. These groups can be linked to each creditor (supplier / vendor) account for better reporting.

4. Stock items - You may set up to two (2) reporting groups for your stock items (products). Stock groups allows you to group or categorise the stock items (products) on which you would like to report. These stock groups can be linked to each stock item (product) for better reporting. analysing and managing of your inventory (products).

5. Documents - You can set up to two (2) reporting groups for your documents, which can categorize them based on their types, such as invoices, credit notes, quotes, purchases, supplier returns, and orders. These document groups can be linked to each document for further reporting and analysis.

6. Cost centres - You can create up to two (2) reporting groups for cost centres, which can be activated in batches (journals) and/or documents. If you create only one (1) reporting group for cost centres, then only one cost centre group will be available in batches (journals) and/or documents.

   Once the batches and/or documents are posted (updated to the ledger), you can select to print reports for each cost centre from the Reports ribbon. By categorizing your cost centres, you can easily track your assets, liabilities, expenses and allocate costs to specific departments or centres.

Groups may also be set for following features:

1. Salespersons - You can add salespersons in Setup → Salesperson (Setup ribbon), and they will automatically be listed in the Salespersons groups. You can also edit the salespersons in the groups as needed. When processing sales documents, such as invoices, credit notes, and quotes, as well as purchase documents, such as purchases, supplier returns, and orders, you can select the relevant salesperson. When printing various reports, you can view salespersons.

2. Projects - You can create reporting groups to manage and track your projects. These project groups can be activated in batches (journals) and/or documents, and once the batches (journals) and/or documents are posted (updated to the ledger), you can generate reports for each project.

3. Languages - You may add different languages to your Set of Books. These languages can be selected in the "*Language*" field on Setup → Access control (Standard security tab) (Setup ribbon), and it will add a Languages tab on the stock items.

Multi-Language accounts - Manual - Shop - Licence : Once-off -

This plugin enables users to translate ledger and group names into multiple languages, allowing for accounting to be done in different languages. Users can select their preferred language, and the osFinancials5/TurboCASH5 user-interface as well as the data in the Set of Books can be viewed in different languages.

This feature is especially useful for businesses with employees who speak different languages or for international businesses. Employees can enter information in their preferred language (for

example English), while bookkeepers or auditors can view the set of books in a different language, for example, Afrikaans, Dutch, etc.

By using this plugin, businesses can improve communication and efficiency, and ensure that all users have access to information in their preferred language.

4. Payment types - To be advised.

To add and set reporting groups:

On the Setup ribbon, select Setup → Groups.



Created with the Standard Edition of HelpNDoc: Elevate Your Documentation Process with HelpNDoc's Advanced Features

Salespersons

When processing sales documents, such as invoices, credit notes, and quotes, as well as purchase documents, such as purchases, supplier returns, and orders, you can select the relevant salesperson. When printing various reports, you can view salespersons.

Examples of reporting groups for salespersons

Some examples of groups that can be used for salespersons:

1. Sales territories: You can create reporting groups based on sales territories or geographical regions. For example, you can have reporting groups for North America, Europe, Asia-Pacific, etc. This allows you to track and compare the sales performance of different territories.
2. Product lines: Another option is to group salespersons based on the product lines they handle. You can create reporting groups for specific product categories or types, such as electronics, clothing, or furniture. This helps in analysing the sales performance of each product line and identifying top-performing salespersons for each category.
3. Customer segments: You can assign salespersons to reporting groups based on the customer segments they focus on. For instance, you can have reporting groups for retail customers, corporate clients, or specific industries like healthcare or technology. This allows you to evaluate the sales performance and effectiveness of salespersons in different customer segments.
4. Sales teams: If you have multiple sales teams within your organization, you can create reporting groups to represent each team. This helps in tracking the performance of individual sales teams and comparing their results. It also allows for effective team management and resource allocation.
5. Sales channels: If your salespersons operate through different channels, such as direct sales, online sales, or distribution partners, you can assign them to reporting groups based on these channels. This enables you to analyse the sales performance across different channels and assess the effectiveness of each salesperson in their respective channel.

These examples illustrate how reporting groups for salespersons in osFinancials5/TurboCASH5 can be used to organize and analyse sales data. By assigning salespersons to appropriate groups, you can evaluate their performance, identify sales trends, and make data-driven decisions to drive business growth.

You can add salespersons in Setup → Salesperson (Setup ribbon), and they will automatically be listed in the Salespersons groups. You can also edit the salespersons in the groups as needed.

Define reporting groups for salespersons

To add / edit /delete salespersons:

1. On the Setup ribbon, select Setup → Groups. The "*Groups (Account group 1)"* default screen will be displayed.

2. Select "*Salespersons*".



If you want to organize your salespersons based on different criteria such as sales territories, product lines, customer segments, sales teams, sales channels, or any other relevant factors, you can create groups to categorise them accordingly. By assigning salespersons to specific groups, you can achieve better organisation, management, and analysis of sales activities and performance. This segmentation enables you to easily track and evaluate the performance of salespersons within each group, helping you optimise sales strategies and make informed business decisions.

You may set different sequences for each reporting group in which the groups and salespersons are listed on reports, etc. This is done by selecting the groups on the list and use the Move up or Move down buttons.

3. If you wish to rename the Reporting group name - Salespersons, over-type the description with your new description. This will change the description of the button for Salespersons.

4. To add a new Group to the root directory or list, select the "*REPORTING GROUP ROOT*" on the list and click on the New button.

5. Enter the name of your next salesperson and click on "*REPORTING GROUP ROOT*" on the list.

6. Repeat the process until you have entered all the Salespersons, etc.

7. Click on the OK button to save your changes and close (exit) this screen.

You may click on the Print button to print a list of your salespersons.

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Payment types

Payment types - To be advised.

Some examples of reporting groups for payment types:

1. Cash payments: This group can include all payment types that involve cash transactions, such as cash payments made to suppliers or cash refunds issued to customers.
2. Bank payments: This group can include payment types that involve transactions made through bank accounts, such as electronic fund transfers, checks, or online payments.
3. Credit card payments: This group can include payment types that involve credit card transactions, including payments received from customers via credit card or payments made to suppliers using a company credit card.
4. Online payment services: This group can include payment types that involve online payment platforms or services, such as PayPal, Stripe, or other similar payment gateways.
5. Direct debit payments: This group can include payment types where funds are debited directly from a customer's bank account, such as recurring automatic payments or instalment plans.
6. Wire transfers: This group can include payment types that involve wire transfers, typically used for international transactions or large-value payments.
7. Voucher payments: This group can include payment types that involve the use of vouchers or gift cards, such as redeeming customer vouchers or making supplier payments using prepaid vouchers.
8. Payment plan instalments: This group can include payment types that involve instalment payment plans, allowing customers to pay for products or services in multiple instalments over a specified period.

These are just a few examples, and the actual reporting groups for payment types can be customized and tailored to fit the specific needs and requirements of a business.



Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Languages

The Language groups allows you to add Languages. These languages can be selected in the Language field on Access control (Standard security tab) on the Setup ribbon.

It will add a Languages tab on the Stock items (Default ribbon).

Multi-Language accounts - Manual - Shop - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

To add / edit /delete Language groups:

1. On the Setup ribbon, select Setup → Groups. The "*Groups (Account group 1)*" default screen will be displayed.

2. Select "*Languages*".



If you have created a Set of Books from scratch (using the "Create Set of Books (Advanced)" option for Firebird database types or the "Create Set of Books (Advanced)" option for MSSQL database types), the Languages group will not be available.

You need to manually add the Project group to the TYPES table

See topics in this Help file : -

- *Steps after creating the Set of Books (Advanced) - Add missing Groups and Paper types in the Types table.*
- *Reportman - References - Groups.*

You may set different sequences for each reporting group in which the languages are listed on reports, etc. This is done by selecting the groups on the list and use the Move up or Move down buttons.

3. If you wish to rename the Reporting group name - Languages, over-type the description with your new description. This will change the description of the button for Languages.
4. To add a new Group to the root directory or list, select the "*REPORTING GROUP ROOT*" on the list and click on the New button.
5. Enter the name of your next Language and click on "*REPORTING GROUP ROOT*" on the list.
6. Repeat the process until you have entered all the Languages, etc.
7. Click on the OK button to save your changes and close (exit) this screen.

You may click on the Print button to print a list of your languages.

Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

System parameters

This option allows you to set the options and parameters in which osFinancials5/TurboCASH5 should store and display amounts and numbers to be displayed on screens, reports and documents and special settings.

The following error may occur, when printing "Budget vs actual" and/or "This year vs last year "reports:

"Type conversion error 'Val':Expression TRpExpression46"

You need to set the "Number Format" of your operating system to resolve this issue.

To access the System parameters settings:

1. On the Setup ribbon, select Setup → System parameters.



2. If necessary, change the following options:

    a) Report amounts with - This setting is not applicable to osFinancials5/TurboCASH5.

    b) Data storage - Select Fix decimals and specify the number decimals in which numbers and amounts should be rounded off. If you select Real numbers, the numbers and amounts will be stored in osFinancials5/TurboCASH5 with an "*unlimited*" number of decimals. In cases where percentages are calculated on amounts, e.g. VAT/GST/Sales Tax, you may select to fix the number of decimals to limit any rounding differences.

    c) Reporting decimals -

        i) Number - Specify the number of decimals to be displayed on reports. It is recommended that this be set to 2.

        ii) Document row - Specify the number of decimals to be displayed on documents. It is recommended that this be set to 2.

iii) Document quantity - Specify the number of decimals to be displayed on document quantities. It is recommended that this be set to 2.

iv) Document show Quantity - It is recommended that this be set to 2.

v) Date / Time Settings - This will launch the Regional and language options in which you may configure or set the formats of your operating system. (See – Setup → Company info - Options).

vi) Use currency sign - Select to use the currency symbol as set in the Regional Settings of your Operating System to be displayed on screens, reports and documents.

vii) Dutch text numbering - All other countries should leave this blank. This should only be selected if the amounts in words are written in different rules to that of the English language, as is the case in the Netherlands language. The amount in figures and words is used by osFinancials5/TurboCASH5 in the Create receipts option of Receipt journals.

d) Speed - Do not calculate batches - By default, the totals of batches are calculated each time you access the Batch type selection screen to select a Batch type. Selecting this option will turn this automatic calculation off.

e) Special settings -

i) Show calendar - By default, the calendar will not be displayed when opening a Set of Books. You need to manually launch it on the Calendar (Default ribbon). If you select this field (tick), the Calendar will then be automatically displayed each time you Open the Set of Books.

ii) No warning unposted - This option is not applicable to osFinancials5/TurboCASH5.

iii) Contra ref. as account ref. - By default, this option (Contra reference as account reference) is not selected. This is the global settings for batches.

iv) Strict tax on account - By default, this option is not selected. This is the global settings for batches.

v) Projects - By default the Projects feature is not enabled. If this option is selected, it will activate the Projects on Projects (Default ribbon).

vi) Default bank reconciliation method - This option is selected, by default, to do bank reconciliation in the default method in separate payments and receipt batches linked to a bank account. If you wish to import transactions from bank statements in Bank

reconciliation, you need to de-select (remove the tick) in this field.

The Bank import plugin allows you to import the transactions from your bank statement and allocate these transactions to the accounts.

vii) Block chain - Activate block chain.

See video on osFinancials and Blockchain.

vii) Enable auto set inactive debtor after x days unpaid - To be advised.

viii) General ledger differences - You may create a general ledger account (Setup → Accounts) and select that account in this field. If there any rounding differences, it will be posted to this account.

ix) Log level – "*Off*" is the default setting. It may be set up to level 7. You may print the Log report in Setup → Access control.

3. Click OK.

Created with the Standard Edition of HelpNDoc: Free Kindle producer

Internet

This option enables you to configure your Internet settings so that you can send reports, statements, and lists to any person or organization via email. To do this, you will need to specify your email's outgoing mail server as set up by your Internet Service Provider on your computer system.

You can also test your email server and view the test log file from this option. It is necessary to perform internet setup in order to send document layout files. If the Internet setup is not completed, an information message will be displayed.

"Internet setup information is incorrect! Run Setup -> Setup -> Internet."

If you wish to:

- Send document layout files form the Documents tab on Debtors form the Documents tab on Creditors (Default ribbon) via email to any person or institution.
- If you have set up any other users on the system, that user's User ID (that is logged on in this Set of Books) and their e-mail address will be displayed on this screen.

Note this option will only be available to the users that have been granted access privileges for "System Setup" in Setup → Access control (Setup ribbon) but all users, with a valid e-mail address will be able to send reports, lists and documents on the Internet.

This option allows you to set up your Internet connection in order to send reports, lists and documents to any person or institution by e-mail. You need to specify your e-mail's outgoing mail server, as setup in your e-mail account on your computer system by your Internet Service Provider (ISP).

You need to then test your E-mail server, and view the test log file from this option, before you can send any reports, lists and documents via e-mail. The test to your e-mail server must be successful before this option will work.

To configure the Internet:

1. On the Setup ribbon, select Setup → Internet.



2. Enter your E-mail account's outgoing mail server's identification as provided by your Internet Service Provider (with whom you already have an account).

3. Enter your User ID and a valid Password as provided by your Internet Service Provider (with whom you already have an account).

4. Default Text is displayed in the "*Subject*" field on the "*Sending E-mail and Fax Report*" screen. This *Sending E-mail and Fax Report*" screen, is launched if you click on the Print button when the Send report to E-mail or Fax option is selected. You may over type this with your own text (subject), if necessary.

5. Click on the Test Mail Server button. This will test your e-mail connection. If successful, a similar result would be displayed:

   "Verifying osfinancials1@gmail.com on server smtp.saix.net
   Connected.
   Disconnected..."

6. View the results of your settings for the e-mail server. If your e-mail server is set correctly, a similar result should be displayed:

   "Test Finished. Success ."

7. Once the test is finished, a confirmation e-mail is sent to the Inbox of your system's default e-mail program.

8. Click on the Apply button.

9. Click on the Close button to close this screen.

- *Server Name - You may enter a name for your outgoing mail server, which can be up to 30 characters long and can include both letters and special characters.*
- *User ID - You may enter a user ID for your email account, which can be up to 20 characters long and can include both letters and special characters. If you have previously entered user IDs in the "Setup → Access control" section, the user ID of the currently logged-in user will be displayed here. You cannot change user IDs in this field and can only modify them in the " Setup → Access Control" section.*
- *E-Mail Address - This field displays your registered email address, which can be up to 30 characters long and can include both letters and special characters. If your email address is not displayed, you need to create a user and enter the email address in the "Setup → Access control" section. You can also enter your email address in the "Setup → Company Info" section on the Address tab.*

Created with the Standard Edition of HelpNDoc: Converting Word Docs to eBooks Made Easy with HelpNDoc

Countries

ISO CODE2 and ISO CODE3 are codes used to represent countries and regions. ISO CODE2 is a two-letter code, and ISO CODE3 is a three-letter code.

Add and manage the ISO CODE2 and ISO CODE3 as well as ICL CODES for each country. See Country codes.



ISO CODE2 and ISO CODE3 are standardized codes used to represent countries and regions, created by the International Organization for Standardization (ISO). Here's a brief overview of their uses:

-

- ISO CODE2: This is a two-letter code (e.g., "US" for the United States, "JP" for Japan) used in various international contexts, such as internet domains (.us, .jp), vehicle registration plates, and international shipping.
- ISO CODE3: This is a three-letter code (e.g., "USA" for the United States, "JPN" for Japan) used in more specific contexts like international data exchange, customs declarations, and financial services.
- ICL CODE This is likely industry-specific codes that complement the ISO codes for more detailed categorization and management.

These codes ensure consistency and clarity in global communication. Managing these codes in software like osFinancials5 and TurboCASH5 helps standardize country and region identifiers across various modules and reports.

Created with the Standard Edition of HelpNDoc: Why Microsoft Word Isn't Cut Out for Documentation: The Benefits of a Help Authoring Tool

Currencies

In osFinancials5/TurboCASH5, users have the capability to engage in international transactions, purchasing goods from foreign suppliers and selling goods to customers in foreign countries. osFinancials5/TurboCASH5 allows users to process and print documents in foreign currencies. However, before they can do so, it is necessary to add and/or update the currencies in the Set of Books.

The Currencies feature in osFinancials5/TurboCASH5 is particularly beneficial for businesses dealing with international transactions, streamlining financial processes for processing and printing sales documents and purchase documents in various currencies.

Currencies functionality overview

Here's a breakdown of the functionalities:

1. Add / Edit / Delete Currencies: osFinancials5/TurboCASH5 allows users to manage a list of currencies. You may add new currencies, edit existing ones (e.g., update exchange rates), and also remove currencies that are no longer needed.
2. Processing Multi-currency Documents: Once the currencies is added and or updated, users can select the currency applicable to their debtors (customers/clients) when processing sales documents such as invoices, credit notes, and quotes. When processing purchase documents such as purchases, supplier returns, and orders, users can select or specify the currency applicable to their for creditors (suppliers / vendors).
3. Printing Currency in Document Layouts: Once a currency is selected for a specific document, osFinancials5/TurboCASH5 incorporates this information into the document layout files. This means that the selected currency will be visibly printed on the documents, ensuring clarity and transparency in financial transactions.
4. Printing a List of Currencies in Reports: You may print a "*Currencies - Listing*" report in the Reports → Currencies menu.

Overall, this currency management and multi-currency document handling feature set are valuable for

businesses and organizations that deal with international transactions and need to manage financial records in different currencies. It streamlines the process, ensures accuracy, and facilitates transparency in financial dealings.

To add currencies:

1. On the Setup ribbon, select Setup → Currencies.



2. Click on the add icon to create a new record.

3. Enter the description, currency symbol and currency rate.

> *Alt Code Shortcuts for Currency Symbols - Example Works if the Alt+0165 for the Japanese Yen, etc.*

4. Click on the save icon.

Created with the Standard Edition of HelpNDoc: Make Documentation Review a Breeze with HelpNDoc's Advanced Project Analyzer

Point-of-Sale

Point-of-Sale can be set up only if you are selling stock items. Improved security and access control has been added for users to access or start a Point-of-Sale session or shift.

You may now link the salespersons (cashiers) added in Setup → Salesperson to users on the Others tab - Setup → Access control. This feature will add more security when users access or start a Point-of-Sale invoicing session.

Webshop

The following Point-of-Sales products are available at out webshop:

W *HorecaPOS*

W *RetailPOS*

W *POSDisplay*

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's Efficient User Interface

Printer

This option allows you to select the default printer (from any available printers set up / configured on your system).

To select the printer:

1. On the Reports ribbon or the Setup ribbon, select Printer.

This "Dialog"-screen may also be launched from the following options:

- *Print setup tab - click on the Configure printers button.*
- *Page setup button op Setup → Setup documents (Setup ribbon).*

2. The "*Dialog*" screen is automatically displayed:



Configuration file options - Location:

- *User configuration - e.g. - "C:\Users\danva\AppData\Roaming\reportman.ini"*
- *System configuration - e.g. - "C:\ProgramData\reportman.ini"*

On the "*Dialog*" window, you may: -

1. Select one of the following printers; Default printer, Reporting printer, Reporting printer 2, Ticket printer, Ticket printer 2, Graphics printer, Character based printer, User printer 1 - 9, Plain text printer or Full plain text printer.
2. Printer Fonts (Windows GDI Only) - The Microsoft Windows graphics device interface (GDI).
3. Text driver only - You may select a print driver from the list (i.e. "*PLAIN, EPSON, EPSON-MASTER, EPSON-ESCP, EPSON-ESCPQ, IBMPROPRINTER, EPSONTMU210, EPSONTMU210CUT, EPSONTM88II, EPSONTM88IICUT, HP-PCL, VT100*" of "*PLAINFULL*".

Oem (Original Equipment Manufacturers) tick to use the drivers from the hardware manufacturers.

4. Position adjustment - Optional - You may enter a value for the left and top of the page.

5. Operations after print -

    - Cut paper -

    - Open drawer -

6. Configuration file - Printer configuration file - Report Manager Designer will use a Printer configuration file, only used in printer selection.

Configuration file options - Location:

- *User configuration - e.g. - "C:\Users\danva\AppData\Roaming\reportman.ini"*
- *System configuration - e.g. - "C:\ProgramData\reportman.ini"*

This configuration file will be searched as Documents & Settings\Local Config\All Users\reporman.ini, if not found it will create or use Documents & Settings\Local Config\YourUserName\reporman.ini

---

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Tools

This menu allows you to perform a Data integrity check, customise a language for your specific needs or industry. You may close any active screens, etc. in the Set of Books. You may also activate various utilities and plugins / extensions.

To access the Tools menu:

1. On the Setup ribbon, select Tools. A list of the menu options will be displayed.



2. Select one of the available options:

   a) Blockchain - By default, Blockchain is not activated. Blockchain needs to be activated in the Setup → System parameters on the Setup ribbon.

   > *See video on osFinancials and Blockchain.*

   b) Data integrity check - Run a Data integrity check and print a Data integrity check report.

   c) Customise language - Customise (edit, change and translate) language files.

   d) Close active forms - Close any open forms (e.g. Documents, Debtors, Creditors, Stock items screens, etc.)

   e) Activate plugins - By default, no plugins is activated when osFinancials5/TurboCASH5 is installed. This option allows you to activate / deactivate all plugins, registered plugins or specific plugins. The activated plugins will be available from the Plugins menu (on the Setup ribbon).

> *Most of these plugins are licenced under commercial licences. You need to purchase a licence on which a registration code and instructions will be mailed to you to unlock the full features of these plugins. Multi-User and Plugins need to be registered in Plugins → Tools → Register plugins menu (Setup ribbon).*

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Calculator

The Calculator is not available on the Setup ribbon (*Tools*) in osFinancials5/TurboCASH5. The calculator is integrated on specific amount fields, on which you may perform certain calculations and transfer the results into the amount fields.

To access the Calculator:

1. The Calculator's buttons may also be launched from the Credit limit and Charge amount fields of the Accounting information tab of the Debtor / Creditor accounts.



> *When focus on certain amount fields, you may press the Ctrl + F4) keys to launch the Calculator.*

2. You may do your calculations. Once a calculation has been completed, the result is transferred to the input field.

Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

Close active forms

If any of the Debtor, Creditor, Stock item edit screens or Document entry screens are open, you may click on the Tools → Close active forms (Setup ribbon), to close all or any of these screens.

Created with the Standard Edition of HelpNDoc: Create cross-platform Qt Help files

Global processes menu

This menu allows you to perform global processes in a Set of Books, such as to Clear / Reset a Set of Books, Copy from a Set of Books and reverse transactions in posted batches (journals) and/or documents.

It is advisable to create a backup of your current Set of Books before accessing any options on the Global processes menu.

Additionally, it is crucial to be absolutely certain before performing any of these functions. Once these options are executed, they cannot be easily reversed or cancelled. The only way to undo any changes made is to restore the Set of Books from the backup.

To access the Global processes menu:

1. On the Setup ribbon, select Global processes. A list of the three (3) menu options will be displayed.



2. Select one of the three (3) available options:

   a) Clear / Reset - This option allows you to clear all transactions and balances in a Set of Books. By selecting this option, you will effectively reset the Set of Books, deleting all transactions and balances. However, you also have the option to retain all documents and set them to unposted status.

   b) Copy from a Set of Books - This option allows allows you to copy data from a chosen Set of Books into the currently active (open) Set of Books. By selecting this option, all the existing data in the active Set of Books will be replaced with the data from the selected Set of Books.

   c) Reverse posted batch / document - Reverse posted batch / document - This feature enables you to reverse or cancel transactions in posted batches (journals) and documents.

      - Reverse posted batch (Journal) - This feature allows you to cancel transactions that were processed in batches (journals) which have already been updated (posted) to the ledger. By selecting this option, all the transactions that were previously updated (posted) to the ledger will be cancelled and removed from the transaction file.

        The cancelled transactions will be automatically imported to the selected batch (journal). At this point, you have the option to either erase or delete the

entire batch (journal). If you wish to keep the cancelled (reversed) batch, you can edit and correct the transactions, balance the batch, print the batch list, and post it to the ledger.

- Reverse posted document - This feature cancels the documents as well as any transactions that were generated by the documents (such as invoices and credit notes, purchases, and supplier returns) after they were updated (posted) to the ledger. The cancelled (reversed) document can then be accessed as an unposted document, which you can edit in the Documents section of the Default ribbon and then post (update) to the ledger. If you do not need to update (post) the document to the ledger, you may also choose to delete it using the Edit → Delete - Documents. option on the Default ribbon.

Created with the Standard Edition of HelpNDoc: Free Kindle producer

Clear/Reset

This option allows you to clear all transactions and balances in a Set of Books. By selecting this option, you will effectively reset the Set of Books, deleting all transactions and balances. However, you also have the option to retain all documents and set them to unposted status.

This process is similar to the Delete Set of Books option from the Start ribbon, as all data related to transactions and batch entries will be permanently removed from the system.

The only difference is that if you use the Global processes → Clear/Reset option from the Setup ribbon, you will still be able to access the Set of Books from the Open Set of Books option on the Start ribbon. All the original setup data for your Set of Books, such as accounts, stock and selling prices, debtor and creditor accounts, contacts, reporting groups, etc., will still be available.

It is highly recommended to create sufficient backups of your data before using this option. In case you accidentally use the Global processes → Clear / Reset option on the Setup ribbon, you will need to restore your Set of Books from the backup disks. Additionally, you may need to manually enter any transactions that were not included in your last backup until you have used the Clear / Reset option, unless you have not processed any transactions since your last backup.

Before clearing or resetting a Set of Books from your system, it is crucial to ensure that all necessary reports have been printed and retained, along with supporting documents such as slips, cheques, invoices, etc. This

is essential to substantiate your profit from the business and ensure compliance with tax return requirements.

As a small business owner, you must keep all necessary records for five (5) years, starting from the date of receipt of the last applicable tax return for audit and record purposes. Additionally, there may be other legislative and/or statutory requirements that apply to your specific business type and/or industry.

It is essential to be absolutely certain before using the Clear / Reset option on a Set of Books, as this action will permanently delete all transactions, balances, stock quantities, and cost prices.

There are two options to clear or reset a Set of Books:

1. Clear / Reset all transactions and balances in a Set of Books. No transactions, documents or any balances will be available in the Set of Books.
2. To Clear / Reset all the transactions and and retain all sales documents (i.e. invoices, credit notes, quotes) and all purchase documents (purchases, supplier returns and orders).

To Clear / Reset all transactions and balances:

1. On the Setup ribbon, select Global processes → Clear / Reset menu. The following confirmation screen is displayed:



2. If you are absolutely sure, tick the "*I have read this instruction and understand the action!*" field. The Yes and No buttons will be available on this screen.



If you click on the No button, the process will be cancelled.

3. Click on the Yes button only if you are absolutely sure. Another confirmation screen is displayed:



On this screen you have the last chance to cancel the clearing process. If you click on the Yes button, the process will be terminated.

4. Click on the No button to clear / reset the Set of Books. The following confirmation screen is displayed:



5. If you do not want to reset clear the quantities, etc. of stock items, click on the No button.

If you click on the Yes button, all stock values will permanently be lost.

6. The following confirmation screen is displayed:



7. If you click on the Yes button, all transactions, documents and balances in a Set of Books will be deleted. No transactions, documents or any balances will be available in the Set of Books.

If you click on the No button, all the transactions and balances will be cleared reset to zero. All sales documents (i.e. invoices, credit notes, quotes) and all purchase documents (purchases, supplier returns and orders) will be retained and be available in Documents (Default ribbon).

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Reverse posted batch/document

This feature allows you to reverse or cancel the transactions entered or imported into batches (journals), and or a selected document, which have already been updated (posted) to the ledger.

W Reverse posted batch (Journal) - This feature allows you to cancel transactions that were processed in batches (journals) which have already been updated (posted) to the ledger. By selecting this option, all the transactions that were previously updated (posted) to the ledger will be cancelled and removed from the transaction file.

The cancelled transactions will be automatically imported to the selected batch (journal). At this point, you have the option to either erase or delete the entire batch (journal). If you wish to keep the cancelled (reversed) batch, you can edit and correct the transactions, balance the batch, print the batch list, and post it to the ledger.

- Reverse posted document - This feature cancels the documents as well as any transactions that were generated by the documents (such as invoices and credit notes, purchases, and supplier returns) after they were updated (posted) to the ledger. The cancelled (reversed) document can then be accessed as an unposted document, which you can edit in the Documents section of the Default ribbon and then post (update) to the ledger. If you do not need to update (post) the document to the ledger, you may also choose to delete it using the Edit → Delete - Documents. option on the Default ribbon.

Created with the Standard Edition of HelpNDoc: Easy EBook and documentation generator

Copy from Set of Books

This option allows you to copy all the data from one Set of Books to another. By selecting this option, you replace all the existing data in the active Set of Books (opened Set of Books) with the data from the selected Set of Books.

The copying process includes copying settings, master files (such as accounts, debtors, creditors, and stock items), transactions in batches/journals (both posted and unposted), documents (both updated and not updated), budgets, repeating transactions, and more. Essentially, it duplicates the entire content of one Set of Books into another.

It's important to note that this feature overwrites any existing data in the target Set of Books. Therefore, you should exercise caution when using this option, as it can result in the loss of any data that was previously present in the target Set of Books.

If you try to copy a Set of Books into the same destination source (selected) set of Books, an error message will be displayed:

```
Dest and source are the same!C:\TCASH5\BIN\TUTORIALS\ENGLISH\HANDYMAN-B\
```

By using the "*Copy from a Set of Books?*" option, you can create two identical Sets of Books on your system with the same data, reports, and other information. It can be useful when you want to create a backup or have multiple copies of a Set of Books for different purposes.

Remember to carefully review and verify your actions before proceeding with the copying process to ensure that you don't unintentionally overwrite or lose any important data.

If you want to create a new Set of Books, you can use the following options on the Start ribbon tab:

1. *Create Set of Books ("Copy an existing Set of Books?" option): This option enables you to create a new Set of Books by making a copy of an existing one. When you select this option, you will be prompted to*

choose an existing Set of Books as the source. osFinancials5/TurboCASH5 will create a duplicate of the selected Set of Books, including its settings, master files, transactions, documents, budgets, and other data. You can then modify the newly created Set of Books as needed.

2. *Save as: This option allows you to save a copy of an existing Set of Books with a different name and/or location. This option is useful if you want to create a backup or create a copy of an existing Set of Books without modifying the original. When you choose this option, you need to specify the name and/or location for the copied Set of Books.*

Both options provide ways to create new Sets of Books based on existing ones, either by making a direct copy or by saving a copy with a different name and/or location. These options help streamline the process of creating new Sets of Books and provide flexibility in managing your financial data.

It's crucial to exercise caution and follow important precautions before using the "Copy from a Set of Books" feature in osFinancials5/TurboCASH5. There are some potential risks involved in the copying process. Here are the precautions you should take:

1. *Ensure that the correct Set of Books is opened: Before initiating the copy process, verify that you have the correct Set of Books opened in osFinancials5/TurboCASH5. Double-checking ensures that you don't accidentally copy data into the wrong Set of Books.*
2. *Create backups of the Set of Books: It's highly recommended to create backups of your active Set of Books before performing any irreversible operations. Backups serve as a safety net in case any issues or data loss occur during the copying process. Having a backup allows you to restore the previous state of your Set of Books if needed.*
3. *Perform a Data integrity check: Before copying data from another Set of Books, it's essential to ensure that the Set of Books you wish to copy from is in a good state and not corrupted. You can run a Data integrity check on the source Set of Books to verify its integrity and resolve any potential issues beforehand.*

By following these precautions, you can minimize the risks associated with the copying process and ensure the integrity and safety of your data. It's always wise to proceed with caution when performing any irreversible actions that can potentially overwrite or replace existing data.

To copy data from another Set of Books:

1. On the Setup ribbon, select Global processes → Copy from Set of Books. The following confirmation screen is displayed:



2. If you are absolutely sure, tick the "*I have read this instruction and understand the action!*" field. The Yes and No buttons will be available on this screen.



3. Click on the Yes button only if you are absolutely sure.

> *On this screen you have the last chance to cancel the clearing process. If you click on the No button, the process will be terminated.*

4. Click on the Yes button to replace all the data in the open (active) Set of Books. The *Set of Books* screen (the same screen as the one to Open a Set of Books) is displayed:



You may click on the Browse button to locate and Open a Set of Books, stored elsewhere on your system.

If a Set of Books is not located in the .../books or other directory where osFinancials5/TurboCASH5 is installed, (elsewhere on your system) the name of the Set of Books is displayed in a blue colour.

5. Select the Set of Books which you would like to copy the data from.

If the Set of Books you need to copy from, is not listed on the Set of Books screen, click on the Browse icon to select from any other Directory.

You may click on the Properties icon to view the holding Directory for the Set of Books selected on the list. If you click on the Properties icon, the following screen is displayed:



Once done, click on the Cancel button to close (exit) this screen.

6. Click on the Open button. All the data in the selected Set of Books will be imported (replace all existing data) into the Set of Books you are working in.

Once this process is finished, it is recommended that: -

W *Do a Data integrity check on the Set of Books you wish to copy from, to check that the Set of Books is not corrupted.*

W *Generate some reports to check that the data is correct. You may, for example, print a trial balance on both Sets of Books to compare the figures.*

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

User tab ribbon

The User tab ribbon in osFinancials5/TurboCASH5 is a customisable quick menu that allows you to manage user navigation in up to six groups within a Set of Books. This makes it convenient for users to access their frequently used features.



Activating the Auto-learn feature: The "Auto-learn" feature, when selected (ticked), automatically adds the last accessed options to the User tab ribbon in up to six (6) groups. This makes it convenient for users to access their frequently used features.

Deactivating Auto-learn feature: Once you have populated the User tab ribbon with the desired shortcuts, you can deactivate the "*Auto-learn*" feature by removing the tick from the "*Auto-learn*" field. This ensures that the User tab ribbon retains the manually selected options and doesn't automatically update based on the last accessed features.

Default ribbon: By default, when opening the Set of Books, the Default ribbon is displayed. However, if the User tab ribbon is activated and configured, it will automatically display the User tab ribbon instead of the Default ribbon upon opening the Set of Books.



Manually configure the User tab ribbon: The User tab ribbon may be changed or set manually in the Usertabs tab on the Setup → Access control (Setup ribbon).

Filter options: The User tab ribbon also provides filter options, allowing you to create filter files, save them, and load them as needed. This helps in managing and organising data based on specific criteria.



Removing Control icons: If any of the Control icons are added, you may remove it from the "User tab". For example, "Do year-end" is only performed once a year, you may select a different feature to replace it, or simply delete it from the list.

By customizing the User tab ribbon, you can streamline user navigation, enhance efficiency, and tailor the interface to match the specific needs and preferences of each user in a Set of Books.

Created with the Standard Edition of HelpNDoc: Don't Let Unauthorized Users View Your PDFs: Learn How to Set Passwords

Show / Hide ribbon options

To hide the Ribbon options

Select any of the ribbon tabs.

Right-click and select "*Minimize the ribbon*" (a tick will be added before this option).



To show the Ribbon options

Select any of the ribbon tabs.

Right-click and select "*Minimize the ribbon*" (the tick before this option will be removed).

Show / Hide Ribbon - Double click

You may also double-click on any of the Ribbon tabs to show or hide the ribbon options

Show / Hide Ribbon options

Collapse the ribbons

You may also hide or show the ribbon options using the "Collapse the ribbon" and "Pin the ribbon" icons on the bottom of the r

"Collapse the Ribbon" - this will hide the ribbon options strip.



Collapsed ribbon



Pin the ribbons - this will show (add) the ribbon options strip.



If the screens of debtors, creditors, stock items or documents is not displayed correctly, you may need to go to Tools → Close active forms (Setup ribbon) and relaunch the screens when the ribbon is collapsed.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Resizing screens

By default, all sections of screens are docked (maximised). If you see the following button on a screen, you may click to undock (maximise) resize a screen or to dock (minimise) the screen.

To maximise the Transactions tab and/or Debit / Credit transactions section of the screen, click on the *button to maximise the Transactions tab. You may also click and drag any part of the screen up / or down.* 

Show / Hide Ribbon options

You may need some extra space when working with, Documents, Stock, Debtors, Creditors, Ledger analyser, etc.

To Auto hide the ribbons options, double-click on any of the ribbon tabs. This will hide the options on the ribbon and only display the ribbon tabs and auto-resize (larger) the screens in osFinancials5/TurboCASH5. You may then click on a ribbon tab to select and access the options. Once you have selected an option, the ribbon options will auto hide and only display the ribbon tabs.

To Show the ribbon options and resize the screens (smaller), you may double-click on a ribbon tab.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Keyboard navigation

Keyboard Shortcuts - Program			
Function Keys		*Other Combination Keys*	
F1	*Help → Help (Start ribbon)*	*Alt+F2*	*Cash / Bank (Reconciliation) (Default ribbon)*
F2	*Batch entry (Default ribbon)*	*Alt+O*	*Open Set of Books (Start ribbon)*
F3	*Update ledger (Default ribbon)*	*Alt+Q*	*Exit osFinancials5/TurboCASH5 - (Top-right corner on the titlebar of the osFinancials5/TurboCASH5 program.*
F4	*Debtors (Default ribbon)*	*Ctrl+F6*	*Input → POS Invoice (Default ribbon)*
F5	*Creditors (Default ribbon)*	*Ctrl+F5*	*Setup → Company info (Setup ribbon)*
F6	*Documents (Invoices) (Default ribbon)*	*Ctrl+L*	*Open item link (Default ribbon)*
F10	*Create Set of Books (Start ribbon)*		
F12	*Stock items (Edit) (Default ribbon)*		

Keyboard Shortcuts - Batch and Document Processing			
Batch Processing		*Document Processing*	
Ctrl+D *Delete*	*Delete (transaction(s))*	*Ctrl+D* *Delete*	*Delete document lines (transaction and/or comment line(s))*
Ctrl+I *Insert*	*Insert an empty line into the batch entry screen*	*Ctrl+I* *Insert*	*Insert an empty line into the document entry screen*
F5	*Balance*	*F7*	*Exclusive / Inclusive - Tax (VAT/GST/Sales Tax)*

Keyboard Shortcuts - Batch and Document Processing			
Batch Processing		Document Processing	
F6	Post	F8	Discount
F7	Exclusive / Inclusive - Tax (VAT/GST/Sales Tax)	F9	Comment
F8	List	F10	Delete all
F9	Process	F11	Copy
F10	Setup	Alt+F3	Focus on Quantity ship field.
		Ctrl+F3	Focus on Fast add item (code/barcode/serial) field. Then press scan.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Keyboard navigation - Changes from osfinancials4

Changed Keyboard Shortcuts from osFinancials4 to osFinancials5/TurboCASH5			
osFinancials4 Short Cut Keys		osFinancials5/TurboCASH5 Short Cut Keys	
F5	Creditors	F4	Debtors
F4	Debtors	F5	Creditors
Alt+X	Exit osFinancials5	Alt+Q	Exit osFinancials5
Ctrl+F7	POS Invoice	Ctrl+F6	POS Invoice
Ctrl+R	Reconciliation	Alt+F2	Cash / Bank

Changed Keyboard Shortcuts from osFinancials4 to osFinancials5/TurboCASH5			
osFinancials4 Short Cut Keys		*osFinancials5/TurboCASH5 Short Cut Keys*	
Shift+F3	*Confirm*	*Alt+F3*	*Confirm*

Discontinued Keyboard Shortcuts			
Function Keys		*Other Combination Keys*	
F11	*Close Set of Books*	*Alt+F5*	*Credit notes*
Ctrl+F3	*Search (Investigator)*	*Alt+F7*	*Orders*
Ctrl+F10	*Delete Set of Books*	*Alt+F8*	*Purchases*
Ctrl+S	*Save as (Save a Set of Books as)*	*Alt+F9*	*Quotes*
Ctrl+W	*Repeating invoices*	*Alt+F10*	*Supplier returns*
Shift+Ctrl+A	*Adjust stock*		

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Record buttons

There are ten (10) record buttons are used to manage records some of the following screens:

- Setup → Accounts (Setup ribbon)
- Stock items (Multi-group) tab (Default ribbon)
- Setup → Stock information - (Tax classes) tab (Setup ribbon)
- Setup → Currencies (Setup ribbon)

These are:

1. First record - Go to the first record.
2. Prior record - Go to the previous record.
3. Next record - Go to the next record.
4. Last record - Go to the last record.
5. Insert record (add) a new record.
6. Delete record - (permanently remove) a record. Once you click on this button, a confirmation message will be displayed:

   "Delete record?"

   Make absolutely sure that the correct record before you click on the OK button. If it is not the correct record, click on the Cancel button and select the correct record.

7. Edit record - Edit a selected record. This will activate the Post edit or Cancel edit buttons.
8. Post edit - Saves (accept) the changes to a record.
9. Cancel edit - Cancels the changes to a record.
10. Refresh data - This will refresh the latest changes.

Created with the Standard Edition of HelpNDoc: Experience the power of a responsive website for your documentation

Filters

Filter Options in Column Headings

The grid is very powerful because of its sophisticated easy to use filter and sort features does this quicker than any other way. It has the ability to group, sort and filter any data column(s) on most screens in a Set of Books with only a view mouse clicks.

If you need to view or find specific data, there are carious option available to locate and find your data. Some of the options are:



- Sort - Click on a column heading to sort and list the data ascending or descending sequence. All the data is by default displayed ascending; from the smallest to the highest value (e.g. a-z or 0-9) according to the record number (e.g. line number in a batch, etc.) To change the sort order from ascending (e.g. a-z or 0-9) to descending (e.g. z-a or 9-0) select a column and click on it. If you click on it again it will change back to ascending sequence.
- Drag and Drop Columns - You may click on a column and drag it to the left or to the right to change the sequence your data is displayed on screens.
- Filter - Click in the arrow to list the data in a specific column. A list displaying the data, as well as an All option and a Custom... option in the selected column will be displayed. For example, if amounts are entered in a batch entry screen, all the amounts will be listed. By adding a tick next to a specific amount, only transactions, matching that amount will be listed.
- Custom - You can easily build customised filters according to your needs. These filter files can be saved and opened for future use.

Custom Filters

Once you have selected an option on a list, the your selection will be displayed at the bottom section of the Batch entry screen as follows:



You may click on the Customise option on a column list or click on the Customise button to:

1. Make a filter (add or delete conditions and groups).
2. Save a filter.
3. Open a filter.

Make a Custom Filter

To make a filter:

1. Click on the Customise option on a column list or click on the Customise button.
2. Select an operator (i.e. and, or, and not, or not).
3. Click on the Filter button (or on the ... button) and select one of the following options on the context menu:
    a) New condition
    b) New group
    c) Delete row (If you click on the Filter button, you may delete all rows (conditions and groups)).

4. Select a column from the list of available data applicable to the screen. In this example, the Date is selected.
5. Select a filter condition. In this example, the Between is selected. Another field is opened to select another date.
6. Once you have created your conditions or groups, click on the Apply button.
7. Click on the OK button to close and exit this Make filter screen.

Conditions

1. Equal to - list or display all values which is the same as the specified value.
2. Not equal to - list or display all values which is not the same as the specified value.
3. Less than - list or display all values smaller than the specified value.
4. Less than or equal to - list or display all values smaller or equal to the specified value.
5. Greater than - list or display all values greater than the specified value.
6. Greater than or equal to - list or display all values greater or equal to the specified value.
7. Like - list all values similar to the specified value.
8. Not like - list all values not similar to the specified value.
9. Contains - list all values which contains (includes) the specified value.



10. Does not contain - list all values which does not contain (excludes) the specified value.
11. Begins with - list all values which starts with the specified value.
12. Ends with - list all values which ends with the specified value.
13. Is null - excludes any value entered, will not be listed or displayed.
14. Is not null - is not zero - any value which is not equal to zero will be listed or displayed.
15. Between - Specify specific values, etc. to include only matching values. (For example, between

reference numbers 105 and 111 will exclude any lower numbers than 105 and higher numbers than 111).

16. Not between - Specify specific values, etc. to exclude values. (For example, Not between reference numbers 105 and 111 will exclude these numbers and will list any lower numbers than 105 and higher numbers than 111).

17. In - In a specified value.

18. Not in - Not in a specified value.

If a Date for a column condition is selected, additional conditions will be available (i.e. is this month, is this year, is next 7 days, is next week, is next 14 days, is next two weeks, is next 30 days, is next month, is future, is this week, is yesterday, is today, is last 7 days, is last week, is last 14 days, is last two weeks, is last 30 days, is last month, is last year, is past, is this week, etc.

Save Custom Filter Files

To Save a Custom Filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Save as... button. The "*Save active filter as*" screen will be displayed.

2. Select a Directory in which you wish to save the custom filter file.

3. Enter a file name.

4. Click on the Save button to save the Filter in a (*.*flt*) Filter file format. You may then at any later stage open the saved *.flt file.

Open Custom Filter Files

To Open a Saved a Custom Filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Open... button. The "*Open saved filter as*" screen will be displayed.

2. Select a Directory in which you have saved the custom filter file.

3. Select a valid filter file.

4. Click on the Open button. The selected filter file's name will be displayed in the titlebar of the make filter screen.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Help and Support

The Help on the Start ribbon, lists access to help and support information and options to access the osFinancials5/TurboCASH5 community.



The Help on the Start ribbon, lists the following seven menu items:

1. Help - Launches the context-sensitive Help file. You may press F1 to launch the help file from most screens and fields to launch the topic relating to that screen or field. This help system is designed to assist users in understanding and navigating the osFinancials5/TurboCASH5 accounting software, as well as to provide guidance on accounting principles and practices.

English Online help -

Afrikaans Online help -

- osFinancials - Videos -

- TurboCASH - Videos - All videos -

2. Support - This option will display the support information.

3. Show welcome - The "*Welcome to osFinancials*" screen will by default be displayed. It will list the latest News from osFinancials5/TurboCASH5.

> *You may set the Calendar as the default to launch in stead of the "Welcome to osFinancials" screen, when you open a Set of Books.*

4. Updates - This option will list all the installation files available for download. By default, the Update will be launched when starting osFinancials5/TurboCASH5. To disable the check for update at start, select this field and remove the tick.

5. Forum - You may access and view the latest and older Forum posts as well as various categories. Should you have a query or an issue, you may search and will probably find a solution to your query or issue. If not, you may post your query or issue. Registered osFinancials5/TurboCASH5 users will soon help by posting answers or solutions to your query or issue.

6. Webshop - Access to the osFinancials webshop.

7. Bug report - Access to the osFinancials Forum page. Should you have a bug or an issue, you may search and will probably find a solution to your bug or issue in the Questions and Answers page. If not, you may post your bug or issue.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

TurboCASH - Releases

TurboCASH Releases

TurboCASH Series	*Updates*	*Latest releases*	*Publications*
TurboCASH4	*No*	*2021-04-06-TurboCASH4-838-setup.exe* *Download at Sourceforge*	*Accounting Made Easy* *2021-*

			04-06-TC4-838-AME-Revision4.pdf Download at Sourceforge
	No	2021-03-28-TC5-400969-setup.exe Download at Sourceforge	Accounting Made Easy 2021-03-29-TC5-400969-AME-Revision6.pdf - Rekening kunde Met Gemak 2021-03-29-TC5-

			400969-AME-AFRIKAANS-Revision5.pdf
	No	TurboCASH5/2021-03-28-TC5-400969-US-setup.exe Download at Sourceforge	
	Yes (Official and Beta versions) Help → Updates menu	Purchase - Contact mail : philip@pinksoft.co.za	Updated versions available with upgrades: TurboCASH5.2 Accounting Made Easy - File - 2021-03-12-TC5-2-398-AME-

			Revision22.pdf TurboCASH5.2 - Accounting Made Easy with Bank Import - File - 2021-03-12-TC5-2-398-AME-BANK-IMPORT - Revision22.pdf TurboCASH5.2 - Rekening kunde Met Gem

			ak - File - 2021-03-12-TC5-2-398-AME-AFRIKAANS-Revision3.pdf TurboCASH5.2 - Projects - File - 2021-03-12-TC5-2-398-Projects-Revision-9.pdf TurboCASH5.2 - Cost centres -

			File - 2021-03-12-TC5-2-398-Cost Centres-Revision-6.pdf

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Help

Launches the context-sensitive Help file. You may press F1 to launch the help file from most screens and fields to launch the topic relating to that screen or field. This help system is designed to assist users in understanding and navigating the osFinancials5/TurboCASH5 accounting software, as well as to provide guidance on accounting principles and practices.

English Online help -

Afrikaans Online help -

- osFinancials - Videos -

- TurboCASH - Videos - All videos -

books

The Set of Books in this directory, is installed when installing osFinancials5/TurboCASH5, is HANDYMAN which will open in the English language.

Tutorials

Tutorial Sets of Books, will be installed in the "*bin / Tutorials*" directory. To follow these tutorials, you need to click on the Browse icon (of the Open Set of Books screen) and select the Sets of Books tutorials.

ENGLISH

English tutorials (using the default payments and receipt batches for banking / cash transactions):

The following Set of Books based on this tutorial, is installed in the "... \bin\Tutorials\ENGLISH\" folder:

- HANDYMAN (No transactions)
- HANDYMAN-A (Unposted)
- HANDYMAN-B (Posted)



The following folders contains files which may be imported into batches:

- *EXPORTED-BATCH-Delimited-File – Exported batch transactions using the "Write delimited file" option and may be imported into a batch using the "Delimited file import" option (F9:Process icon) on batches.*
- *EXPORTED-BATCH-Spreadsheets – Exported batch transactions in the *.xlsx (Excel 2007-365) file format. These transaction files may be opened in the Spreadsheet import icon*

on batches, and imported into a selected batch.

BANK-IMPORT Plugin - English tutorials

English tutorials (using the BankImport plugin for banking / cash transactions):

The following Set of Books based on this tutorial, is installed in the "...\bin\Tutorials\BANK-IMPORT\" folder:

- HANDY-BANK (No transactions).
- HANDY-BANK-A (Unposted transactions in batches and documents, except the Payments and Receipt batches, which is cleared for the Bank account and the Petty cash).
- HANDY-BANK-B (Posted transactions in batches and documents, including the imported bank statement and processed Petty cash transactions).
- HANDY-BANK-UNPOSTED-BANK-STATEMENT – All transactions in batches and documents have been posted. The sample Bank statement in the "*...\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS*" folder needs to be imported and Petty cash transactions needs to be processed).

AFRIKAANS

The following Set of Books based on the Afrikaans tutorial, is installed in the "*...\bin\Tutorials\AFRIKAANS*\" folder.

- NUTSMAN (No transactions).
- NUTSMAN-A (Unposted)
- NUTSMAN-B (Posted).

COST-CENTRES

Tutorials / examples to explore the activation, processing and reporting of Cost centres in osFinancials5/TurboCASH5. See - Cost centres in this Help file.

The following Set of Books based on this tutorial, is installed in the "*...\bin\Tutorials\COST-CENTRES*\" folder:

- COST-CENTRES-A (transactions and documents not posted to the ledger)
- COST-CENTRES-B (transactions and documents posted to the ledger).

PROJECTS

Tutorials / examples to explore the activation, processing and reporting of Projects in osFinancials5/TurboCASH5. See - Projects in this Help file.

The following Set of Books based on this tutorial, is installed in the "...\bin\Tutorials\PROJECTS\" folder:

- PROJECTS-A (transactions and documents not posted to the ledger)
- PROJECTS-B (transactions and documents posted to the ledger).

Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

Support

Support information

This option will provide you with contact information for technical assistance.

To display osFinancials5 Support information:

1. On the Start ribbon, select Help → Support.

2. Check the necessary details.
3. Click on the OK button, or press the Enter key on your keyboard, if you do not wish to link to the Website. You may also press the Esc key on your keyboard to exit this screen.

You may, from this screen, connect to the osFinancials Website directly by clicking on the Internet address (blue link) osFinancials support page.

Access to osFinancials website

- https://www.osfinancials.org/nl/ - Netherlands

- https://www.osfinancials.org/en/ - English

Support Contract and Extra Tickets

Support Contract and Extra Tickets - Shop -

Support Contract:

The support contract grants you direct access to our team for issue resolution, subject to a "*fair use*" policy. Support is provided via telephone and/or email. Additionally, you'll receive interim updates of osFinancials5/TurboCASH5 where bugs are fixed and new features introduced.

Extra Tickets:

Additional support tickets beyond the "*fair use*" allocation can be purchased at a discounted rate for contract holders.

Please note that development or modification of osFiosFinancials5/TurboCASH5 document layouts are not included in the support contract.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Show welcome

The "*Welcome to osFinancials*" screen will by default be displayed. It will list the latest News from osFinancials.

To close or exit the "*Welcome to osFinancials*" screen, click on X (close).

To display the "*Welcome to osFinancials*" screen again, select Help → Show welcome on the Start ribbon.

You may set the Calendar as the default to launch in stead of the "Welcome to osFinancials" screen, when you open a Set of Books.

Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Forum

You may access and view the latest and older Forum posts as well as various categories. Should you have a query or an issue, you may search and will probably find a solution to your query or issue.

If not, you may post your query or issue. Registered osFinancials users will soon help by posting answers or solutions to your query or issue.

To access the forum:

On the Start ribbon, select Help → Forum.

An information message will be displayed for unregistered users.

> "You are not yet registered to post on our forum! You will need to register osFinancials to use that username password to login to our forum or shop."

The Forum webpage is launched.

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Webshop

osFinancials Webshop

Please visit our osFinancials webshop.to support the osFinancials5/TurboCASH5 development.

You will our most popular commercial products and services: to extend, configure, and support osFinancials5/TurboCASH5. If you have questions about any product or service, please contact us. Please note that some products are available for 14-day trial periods.

To access our the osFinancials webshop:

On the Start ribbon, select Help → Webshop.

TurboCASH Webshop

TurboCASH Business Class offers a Monthly Subscription or an Annual subscription.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Bug report

This will land on the osFinancials Forum page where you can search and will probably find a solution to your bug or issue. If not available, you may report any bugs or issues you encounter while using the program.

To access the Bug reporting system in osFinancials5/TurboCASH5:

On the Start ribbon, select Help → Bug report.

This will land on the Forum page.

Some or most bugs are resolved with a later release or an update.

The Updates option may manually be launched from Help → Updates (Start ribbon). You may install later updates or beta updates.



Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Manage Sets of Books

Options to manage Sets of Books in osFinancials5/TurboCASH5

There are several options on the Start ribbon to manage Sets of Books (databases) in osFinancials5 / TurboCASH5, including:

1. Open Set of Books: Clicking on the Open icon on the Start ribbon allows you to select and access a specific Set of Books from the list of valid Sets of Books. The list includes Sets of Books located in the "books" folder of the osFinancials5/TurboCASH5 installation directory and any Sets of Books stored in other locations that have been added to the list.
2. Close Set of Books: The Close Set of Books option on the Start ribbon allows you to close the currently active/opened Set of Books.
3. Create Set of Books: The "*Creation wizard*" provides three options to copy and create a Set of Books:
    - Copy an existing Set of Books?: This option enables you to create a new Set of Books by making an exact copy of an existing one, including all the data it contains. You can select the Set of Books you want to copy and specify the directory for the new Set of Books.
    - Let osFinancials help you to create a Set of Books?: / Let TurboCASH help you to create a Set of Books?: This option guides you through the process of setting up a new Set of Books using an existing Set of Books as a template. You can also download pre-existing Sets of Books as templates for your country or industry.

      After downloading a Set of Books (template) using the "Let osFinancials help you to create a Set of Books?" option, the "Save as" screen will be launched, allowing you to save the template in a directory of your choosing.

      You can also view a list of available Sets of Books available for a download to use as templates for your new Set of Books.

      After downloading a Set of Books, the Set of Books (template) will automatically open in the language associated with the country and language of the Set of Books.
    - Create a Set of Books (Advanced)?: This option is for advanced users who want to create a new Set of Books from scratch. It allows you to choose the database type (Firebird or MSSQL) and set a maximum of 8-digit account codes, providing more flexibility in creating the Set of Books structure.

      When creating, or copying a Set of Books, the default number of characters for the account codes is pre-determined by the selected Set of Books. Most Sets of Books currently use 3-digit account codes as their default setting.

> *However, if you choose the "Create a Set of Books (Advanced)?" option, you can select a maximum of 8-digit account codes, providing more flexibility in creating a Set of Books that suits your needs.*

4. Save as: This option allows you to save a Set of Books to a different directory or folder on your system. It creates a copy of the Set of Books with a new name and location, without affecting the original data.
5. Delete Set of Books: Deleting a Set of Books permanently removes all data within it. It is important to have backups, print necessary reports, and retain supporting documents before deleting a Set of Books, as the information may be required for tax returns or other legal purposes.

These options provide flexibility in managing Sets of Books in osFinancials5/TurboCASH5, including creating new ones, copying existing ones, saving copies, and deleting Sets of Books.

Options to Backup or Copy a Set of Books in osFinancials5/TurboCASH5

In addition to the Backup/Restore feature, you can create exact copies of existing Sets of Books or templates that are installed in your osFinancials5/TurboCASH5 …/books directory.

The following options are available in osFinancials5/TurboCASH5 for backing up or copying a Set of Books:

1. Backup / Restore: This option is available on the Start ribbon. It allows you to create backups of your Set of Books and restore them when needed. You can select the backup option to create a backup file and choose the restore option to restore a previously created backup.
2. Save as: This option is also available on the Start ribbon. It enables you to create a copy of an existing Set of Books with a new name and/or a new location. This is useful when you want to create a duplicate or backup of a Set of Books.
3. Create Set of Books: This option is found in the "*Copy an existing Set of Books?*" option of the "*Creation wizard*" on the Start ribbon. It allows you to create a new Set of Books based on an existing one. You can select an existing Set of Books and provide a new name and/or location for the copied Set of Books.
4. Tools → Global processes → Copy from a Set of Books: This menu-option is available on the Setup ribbon. It provides a feature for copying a Set of Books from an existing one. You can select the source Set of Books and specify the name and/or location for the copied Set of Books.

These options allow you to create backups or copies of Sets of Books in osFinancials5/TurboCASH5, either by directly saving them as new files or by using existing Sets of Books as templates. Each option provides

flexibility in terms of naming, location, and source for the copied Set of Books.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Open Set of Books

Every time an unregistered version of osFinancials5/TurboCASH5 is started, the following confirmation message will be displayed:

> This software is limited to 500 transactions or 500 documents. Please register and buy a licence for osFinancials5!
> This copy of osFinancials5 is not registered! Do you wish to register it now?

Unregistered versions will allow you to process up to 500 transactions and /or documents. Once this limit is reached, osFinancials5/TurboCASH5 will not allow any processing of transactions, in batches and/or documents.

Once you have registered osFinancials5/TurboCASH5, you will receive an unlocking code and will be able to process further transactions and or documents.

Open a Set of Books in which 500 transactions and or documents have been processed:

osFinancials5/TurboCASH5 the limit of 500 transactions or 500 document is reached! Please register and buy a licence.

Once you have registered osFinancials5, you will receive an unlocking code and will be able to process further transactions and or documents.

Accessing Budgets (Reports ribbon) in a Set of Books in which 500 transactions and or documents have been processed:

> This software is limited to 500 transactions or 500 documents! Please register and buy a licence for osFinancials5.

Once you have registered osFinancials5/TurboCASH5, you will receive an unlocking code and will be able to process further budgets.

To access the Set of Books option in osFinancials5/TurboCASH5, you need to click on the Open icon on the Start ribbon. This option will display a list of all valid Sets of Books (databases) that are located in the "*books*" folder of the osFinancials5 installation folder. Additionally, it will also show any Sets of Books that are stored in other locations, such as on a different part of the hard disk or on a mapped drive on the

network, which have been added to the list. The path or directory of these Sets of Books can be set in the Properties of the Set of Books.

Open Set of Books screen

To open a Set of Books:

1. On the Start ribbon, select Open Set of Books (Alt + O). The "*Set of Books*" screen is displayed:



Blue - Font colour

This indicates indicates that a Set of Books is not located in the same directory (books folder) where osFinancials5/TurboCASH5 is installed. Instead, it is located elsewhere on your system.

Red - Font colour

When a Set of Books (which is located elsewhere on your system) is deleted or its folder is moved to a different location, the font color of the Set of Books name turns red.

This also happens when the drive or network where the Set of Books is stored becomes unavailable or unmounted.

You may right-click on the Cancel button remove invalid Set of Books in the Open Set of Books screen.



2. Select the Set of Books which you would like to open.

3. Click on the Open button.

If you click on the Cancel button, no Sets of Books will be opened.

Year-end confirmation

Should you open the Set of Books, and the date of the end of the year, is in the past, a confirmation message will be displayed, for example;

> This year Ends on 2022/02/28
> Today 2022/04/04
> Warning, this date does not fall into any of this or last year's reporting dates!
> Do year end?

You need to adjust the Start of the financial year in one of the following options on the Setup ribbon:

- *Setup → Reporting dates (if no transactions were processed for the Set of Books).*
- *Do year end.*

Icons on Open Set of Books screen

Browse

The Browse icon will allow you to add a Set of Books to the list.

If the Set of Books you want to open is stored in a location other than the "*books*" folder in the

osFinancials5/TurboCASH5 installation folder, you can use the Browse icon to locate and select it. Clicking on the Browse icon will allow you to navigate to the directory or folder where the Set of Books is stored and select it from there.

To browse and add a valid osFinancials5/TurboCASH5 Set of Books to the Set of Books list:

1. If you click on the Browse button, you may select from any other directory. The '*Browse for Folder*' screen is displayed.
2. You must pick a valid osFinancials5/TurboCASH5 Set of Books. If the directory does not contain a valid Set of Books, it will not be added to the list.



The Books are by default installed in the following directories:

1. books directory - The Sets of Books in the "books" directory are installed during the

osFinancials5/TurboCASH5 installation. The specific sets of books depend on the country and language you have chosen during the installation process.

> If the set of books for your language and or country, is not available in the books directory, you may select any of the available Firebird Sets of Books and linked languages available as a free download.
> osFinancials5/TurboCAH5 supports 79 different languages and counties / tax regimes languages liked to 87 Sets of Books (databases) which may be downloaded and customised to meet your requirements.

2. bin directory - The bin directory consists of the following three folders:
    - 4-DIGIT-BOOKS - These Sets of Books consists of a 4-Digit main accounts with 3-Digit sub-accounts with a Chart of accounts supporting larger descriptions and fields. These Sets of Books is based on the Firebird database type. The following Sets of Books, based on the "CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS.zip" (with a 4-digit main accounts and 3 digit sub-accounts) were created:
        - 4-EN-SOUTH-AFRICA-GENERIC: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes, aligned with the VAT201-return.
        - 4-AF-SUID-AFRIKA-GENERIES.: This generic Set of Books includes 4-digit main account and 3-digit sub-account codes, based on the South African Chart of Accounts in Afrikaans. It incorporates specific South African terminology and includes the structure of South African VAT-accounts and VAT-codes (Belasting op Toegevoegde Waarde (BTW) Suid-Afrika (Afrikaans), aligned with the VAT201-return.
        - 4-EN-UK-GENERIC: This generic Set of Books includes 4-digit main account and 3-digit sub-accounts, based on the United Kingdom (UK) Chart of Accounts. It incorporates specific UK terminology and includes Value Added Tax (VAT) - United Kingdom accounts based on the VAT Standard rate scheme. The VAT-account and VAT-codes structure in the Chart of Accounts is designed to match the various boxes on the UK VAT return. NOTE: Various schemes for VAT may be applicable for various scenarios.
    - CUSTOMISE-EMPTY-BOOKS - (Pre-configured Firebird databases) - Only includes 3 control accounts (Retained earnings / Debtors control and Creditors control). The field length for Account descriptions and Groups description length is set to 128 characters. The "TYPES" table with Paper types and may need to add the Groups for Cost centre 1 / Cost centre 2 / Projects and Languages. The basic journals (such as Sales journal, Purchase journal and General

journal) have been added and the basic settings for documents (such as Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders) is already set.

The basic Sets of Books created using this option will include the essential three main accounts: Debtor's Control, Creditor's Control, and Retained Earnings. The remaining Chart of Accounts can be fully customised according to your specific requirements. This flexibility enables you to tailor the Sets of Books to suit your unique accounting needs. You may select the templates consisting 3- to 8-digits number of digits for main accounts to customise for your specific requirements.

- Tutorials
  - ENGLISH - The …bin/Tutorials/ ENGLISH folder contains some tutorials / examples to explore osFinancials5/TurboCASH5 in the English language. The English tutorials (i.e. HANDYMAN (no transactions), HANDYMAN-A (transactions and documents not posted to the ledger) and HANDYMAN-B (transactions and documents posted to the ledger).
  - AFRIKAANS - The …bin/Tutorials/ AFRIKAANS folder contains some tutorials / examples to explore osFinancials5/TurboCASH5 in the Afrikaans language. The Afrikaans tutorials (i.e. NUTSMAN (no transactions), NUTSMAN-A (transactions and documents not posted to the ledger) and NUTSMAN-B (transactions and documents posted to the ledger).
  - BANK-IMPORT - The …bin/Tutorials/ BANK-IMPORT folder contains some tutorials / examples to explore the BANK-IMPORT plugin to import and process Bank statements into your cashbook in osFinancials5/TurboCASH5 using the English language. The English tutorials (i.e. HANDY-BANK (no transactions), HANDY-BANK-A (transactions and documents not posted to the ledger) and HANDY-BANK-B (transactions and documents posted to the ledger). The HANDY-BANK-UNPOSTED-BANK-STATEMENT (all transactions and documents posted to the ledger, except the bank transactions).
  - COST-CENTRES - The …bin/Tutorials/ COST-CENTRES folder contains some tutorials / examples to explore the activation, processing and reporting of Cost centres in osFinancials5/TurboCASH5. The Cost centre tutorials (i.e. COST-CENTRES-A (transactions and documents not posted to the ledger) and COST-CENTRES-B (transactions and documents posted to the ledger). See - Cost centres in this Help file.
  - PROJECTS - The …bin/Tutorials/ PROJECTS folder contains some tutorials / examples to explore the activation, processing and reporting of Projects in osFinancials5/TurboCASH5. The Projects tutorials (i.e. PROJECTS-A (transactions and documents not posted to the ledger) and PROJECTS-B (transactions and documents

posted to the ledger). See - Projects in this Help file Projects

Purge list

The Purge list icon is used to remove a selected Set of Books from the list, but it does not delete the Set of Books from the directory. It's important to note that you cannot purge a Set of Books located in the osFinancials5/TurboCASH5 directory (books folder). To remove a Set of Books from the books folder, you need to use the Delete Set of Books option located on the Start ribbon. If you want to remove a Set of Books from the list but keep the Set of Books, you will need to move the entire Set of Books folder out of the osFinancials5/TurboCASH5 directory using File Explorer or any other file/folder management program.

When you click on the Purge icon, the following confirmation message will be displayed:

> "This will seriously affect your Set of Books! Are you sure you want to clear this Set of Books?"

Properties

The Properties icon displays the name of the Set of Books (e.g. "*MYBOOKS*") and its holding directory in the list.

> e.g. C:\osFinancials5\books\MYBOOKS\books.fdb.

1. If you select a Set of Books and click on the Properties icon, the following screen is displayed:



2. If you need to change any of the properties for the Set of Books, follow these steps:

    a) Enter the name of the Set of Books - Enter a valid name for the Set of Books.

b) Server - If osFinancials5 is configured as a Multi-user product, enter the server details.

c) Enter the path where the Set of Books are stored - Enter the path or directory where the Set of Books is stored on your system..

d) Username - Enter a valid username for the Set of Books

e) Password - Enter a valid password for the Set of Books.

f) Databasetype - Select the appropriate database type from the following options:

a) Firebird - This is the default database type for all Sets of Books included in the osFinancials5 installation in the "books" and the "...bin/Tutorials" folder. Sets of Books (Firebird database type) may also be downloaded when you create a Set of Books using the "*Let osFinancials help you to create a Set of Books?*" / "*Let TurboCASH help you to create a Set of Books?*" option.

b) SharedDisk (Firebird) - For sharing in multi user setup for multi-user environment for Firebird databases.

c) MSSQL - Microsoft SQL server -

d) Mysql - Not fully supported.

e) Postgress - Not fully supported.

Database type - Firebird is the default for all Sets of Books included in the install. You may create MySQL databases (see - My SQL database online manual) and Postgress databases (see - Postgress database online manual).

3. Once done, click on the Change button to save the changes and to exit or close this screen.

Add

If you click on the Add icon, the following two (2) options is displayed:



1. Select Set of Books directory - On this screen, you need to enter the name of the Set of Books, Server name, path, user name and password.

2. Creating Set of Books - Launch the Creation wizard (Start → Create Set of Books (F10)) on which you may create a set of books, copy a set of books, etc.

To change the Set of Books properties:

1. If you click on the Add icon, and select the "*Select Set of Books directory*" option, the "*Open*" screen is displayed:



2. Select a valid database (*.fdb - Firebird database) on your system and click on the Open button. The "*Change Set of Books properties*" screen is displayed:



3. If you need to change any of the properties for the Set of Books, enter the following:

    a) Enter the name of the Set of Books - Enter a valid name for the Set of Books.

    b) Server - This works, if osFinancials5 is configured as a Multi-user product.

    c) Enter the path where the books are stored - Enter the path (i.e. directory (folder)) where the Set of Books is stored on your system.

    d) Username - Enter a valid username for the Set of Books

    e) Password - Enter a valid password for the Set of Books.

> *Database type - Firebird is the default for all Sets of Books included in the install. You may create MySQL databases (see - My SQL database online manual) and Postgress databases (see - Postgress database online manual).*

4. Once done, click on the Change button to save the changes and to exit or close this screen.

Cancel button (right-click context menu)

The Cancel button on the Set of Books screen has a right-click context menu that provides four options:



1. Purge invalid - This option deletes Sets of Books that are listed in Red - Font colour on the "*Set of Books*" open screen, indicating that they are either deleted, moved to another location, or stored on an unavailable or unmounted drive or network.

2. Purge not in this folder - This option does not delete the files from the directory. Sets of Books located in the "*books*" folder of the osFinancials5/TurboCASH5 directory cannot be purged using this option. To remove them, use the Delete Set of Books option in the Start ribbon.

3. Delete not local (Books this PC can not find) - This option removes Sets of Books that are not available on the current device.

4. Reinit version - This option updates the database of the selected Set of Books. Once finished, a confirmation message will be displayed.

   Database version updated.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's User-Friendly UI

Sets of Books - Download

Sets of Books - Installed in osFinancials5/TurboCASH5

The sets of books in the "*books*" directory are installed during the osFinancials5/TurboCASH5 installation. The specific sets of books depend on the country and language you have chosen during the installation process.

Sets of Books (Templates) available for download

osFinancials and TurboCASH users may download these Sets of Books (templates) free in a matter of a few seconds (using the option, Let osFinancials / TurboCASH help you to create a Set of Books). It takes only 3 clicks to download a Set of Books.

After downloading a Set of Books, the Set of Books (template) will automatically open in the language

associated with the country and language.

The Sets of Books are linked to languages. These languages are pre-set for each Set of Books in the "System language" field on Setup → Access control.

All Sets of Books (templates) is consists of a 3-digit main account and 3-digit sub accounts, except for the following Sets of Books (templates):

	Books with 4-digit main account and 3 -digit-sub-accounts			*Books with 5-digit main account and 3 -digit-sub-accounts*	
		Language			*Language*
	EN-CANADA-CORPORATION	*en-Canada*		*EN-USA*	*english-usa*
	EN-CANADA-OTHER	*en-Canada*		*EN-USA CALIFORNIA*	*english-usa*
	BE_Books (Belgium)	*Nederlands*			
	BTW21VOORBEELD_A_20XX (installed)	*Nederlands*			
	BTW09VOORBEELD_A_2019PLUS	*Nederlands*			
	6-digit main account and 3-digit sub-accounts				
	BTW_VOORBEELD_BELGIE	*Nederlands*			

Tutorials - English

	English	*Linked language file*	*Comments*
	HANDYMAN	*English*	*Set of Books with no transactions or documents*

	HANDYMAN-A	English	Unposted batches and documents
	HANDYMAN-B	English	Posted batches and documents

South African users may set the language to en-SouthAfrica to display the correct terminology, e.g. VAT, instead of Tax, etc.

Tutorials - Afrikaans

	Books name	Linked language file	Comments
	NUTSMAN	Afrikaans	Set of Books with no transactions or documents
	NUTSMAN-A	Afrikaans	Unposted batches and documents
	NUTSMAN-B	Afrikaans	Posted batches and documents

Afrikaans - Books

	Country (official name)	Books name	Linked language file
	The Republic of South Africa	AF-SUID-AFRIKA	Afrikaans
		BOERDERY	
		DIENS	
		KERK	
		MEDIES	

VERVAARDIGING	
WERKSWINKEL	

English

English - Europe

	Country (official name)	*Books name*	*Linked language file*
	Ireland	*EN-IRELAND*	*en-Ireland*
	The Isle of Man	*EN-ISLEOFMAN*	*en-Isle-of-Man*
	The Republic of Malta	*EN-MALTA*	*en-Malta*
	The United Kingdom of Great Britain and Northern Ireland	*EN-UK*	*en-UK*
	Iceland	*ICELAND-BASIS*	*en-UK*

English - Africa

	Country (official name)	*Books name*	*Linked language file*
	The Republic of Botswana	*EN-BOTSWANA*	*en-Botswana*
	The Republic of Cameroon	*EN-CAMEROON*	*en-Cameroon*
	The Kingdom of Lesotho	*EN-LESOTHO*	*en-Lesotho*

	The Republic of Malawi	EN-MALAWI	en-Malawi
	The Republic of Malta	EN-MALTA	en-Malta
	The Republic of Mauritius	EN-MAURITIUS	en-Mauritius
	The Republic of Namibia	EN-NAMIBIA	en-Namibia
	The Republic of Rwanda	EN-RWANDA	en-Rwanda
	The Republic of South Africa	EN-SOUTHAFRICA	en-South-Africa
	The United Republic of Tanzania	EN-TANZANIA	en-Tanzania
	The Kingdom of Tonga	EN-TONGA	en-Tonga
	The Republic of Trinidad and Tobago	EN-TRINIDADTOBAGO	en-Trinidad
	The Republic of Uganda	EN-UGANDA	en-Uganda
	The Republic of Zambia	EN-ZAMBIA	en-Zambia
	The Republic of Zimbabwe	EN-ZIMBABWE	en-Zimbabwe

English - USA

Country (official	Books name	Linked language file

	name)		
	The United States of America	*EN-US-CALIFORNIA*	*english-usa*
	The United States of America	*EN-US-GENERIC*	*english-usa*
	The United States of America	*EN-USA*	*english-usa*

English - Canada

	Country (official name)	*Books name*	*Linked language file*
	Canada	*EN-CANADA-CORPORATION*	*en-Canada*
	Canada	*EN-CANADA-OTHER*	*en-Canada*

English - Oceania

	Country (official name)	*Books name*	*Language file*
	The Commonwealth of Australia	*EN-AUSTRALIA*	*Australia*
	New Zealand	*EN-NEWZEALAND*	*en-New-Zealand*
	The Kingdom of Tonga	*EN-TONGA*	*en-Tonga*

English - Other

	Books name	Linked language file
	EN-INDUSTRIES	English
	CHURCH	
	FARMING	
	MANUFACTURING	
	MEDICAL	
	PERSONAL	
	RESTAURANT	
	RETAIL	
	SCHOOL	
	SERVICE	
	WORKSHOP	

Spanish (Español)- South America

	Country (official name)	Books name	Linked language file
	The Argentine Republic	ES-ARGENTINA	es-Argentina
	The Republic of Chile	ES-CHILE	es-Chile
	The Republic of Ecuador	ES-ECUADOR	es-Ecuador
	The Republic of El Salvador	ES-ELSALVADOR	es-ElSalvador
	The Republic of Honduras	ES-HONDURAS	es-Honduras

	The United Mexican States	ES-MEXICO	es-Mexico
	The Republic of Panamá	ES-PANAMA	es-Panama
	The Republic of Paraguay	ES-PARAGUAY	es-Paraguay
	The Republic of Perú	ES-PERU	es-Peru
	The Oriental Republic of Uruguay	ES-URUGUAY	es-Uruguay
	The Bolivarian Republic of Venezuela	ES-VENEZUELA	es-Venezuela

French - (Français)

Flag	Country (official name)	Books name	Linked language file
	The French Republic	FR-BOOKS	Français
	The French Republic	FR-FRANCE	Français
	The Republic of Benin	FR-BENIN	fr-Benin
	Burkina Faso	FR-BURKINAFASO	fr-Burkina
	The Republic of Cameroon	FR-CAMEROUN	fr-Cameroun
	The Central African Republic	FR-CENTRAFRICAINEREPUBLIQUE	fr-C-African-Rep

	The Union of the Comoros	FR-COMORES	fr-Comores
	The Gabonese Republic	FR-GABON	fr-Gabon
	The Republic of Guinea	FR-GUINEE	fr-Guinee
	The Republic of Haiti	FR-HAITI	fr-Haiti
	The Republic of Mali	FR-MALI	fr-Mali
	The Republic of Mauritius	FR-MAURICE	fr-Maurice
	The Republic of the Niger	FR-NIGER	fr-Niger
	The Democratic Republic of the Congo	FR-REPCONGO	fr-Rep-Congo
	The Republic of Rwanda	FR-RWANDA	fr-Rwanda
	The Republic of Senegal	FR-SENEGAL	fr-Senegal
	The Republic of Chad	FR-TCHAD	fr-Tchad
	The Republic of Vanuatu	FR-VANUATU	fr-Vanuatu

Other Languages

Croatia

	Country (official name)	Books name	Language name
	The Republic of Croatia	HR-CROATIAN-CONTOH_INA	Croatia
	The Republic of Croatia	HR-CROATIAN-PERSONID	Croatia
	Montenegro	HR-MONTENEGRO	Croatia

Estonia

	Country (official name)	Books name	Language file	
	The Republic of Estonia	ET-ESTONIAN-2X	Est	Eesti and Estonian languages available but not linked to a Set of Books
	The Republic of Estonia	ET-ESTONIAN-3X	Est	

Greek

	Country (official name)	Books name	Language file
	The Republic of Cyprus	EL-CYPRUS	Greek

	The Hellenic Republic	EL-GREECE	Greek

Indonesia

	Country (official name)	Books name	Language name
	The Republic of Indonesia	ID-INDONESIA-PRIBADI	Indonesia

Lithuania

	Country (official name)	Books name	Language name
	The Republic of Lithuania	LT-LITHUANIA	Lithuanian

Thai

	Country (official name)	Books name	Language name
	The Kingdom of Thailand	TH-THAILAND	Thai

Turkish

	Country (official name)	Books name	Language name

	The Republic of Turkey	*TR-TURKEY*	*Turkish*

Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Sets of Books - Turorials

books directory

The sets of books in the "*books*" directory are installed during the osFinancials5/TurboCASH5 installation. The specific sets of books depend on the country and language you have chosen during the installation process.



Tutorials

To open the tutorial sets of books installed in the "*bin/Tutorials*" directory, click the Open icon on the Start ribbon. On the "*Set of Books*" screen, click the Browse icon and select the desired tutorial set of books to follow.

ENGLISH

English tutorials (using the default payments and receipt batches for banking / cash transactions):

The following Set of Books based on this tutorial, is installed in the "...\bin\Tutorials\ENGLISH\" folder:

- HANDYMAN (No transactions)
- HANDYMAN-A (Unposted)
- HANDYMAN-B (Posted)

The following folders contains files which may be imported into batches:

- *EXPORTED-BATCH-Delimited-File – Exported batch transactions using the "Write delimited file" option and may be imported into a batch using the "Delimited file import" option (F9:Process icon) on batches.*
- *EXPORTED-BATCH-Spreadsheets – Exported batch transactions in the *.xlsx (Excel 2007-365) file format. These transaction files may be opened in the Spreadsheet import icon on batches, and imported into a selected batch.*

BANK-IMPORT Plugin - English tutorials

English tutorials (using the BankImport plugin for banking / cash transactions):

The following Set of Books based on this tutorial, is installed in the "...\bin\Tutorials\BANK-IMPORT\" folder:

- HANDY-BANK (No transactions).
- HANDY-BANK-A (Unposted transactions in batches and documents, except the Payments and Receipt batches, which is cleared for the Bank account and the Petty cash).
- HANDY-BANK-B (Posted transactions in batches and documents, including the imported bank statement and processed Petty cash transactions).
- HANDY-BANK-UNPOSTED-BANK-STATEMENT – All transactions in batches and documents have been posted. The sample Bank statement in the "*...\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS*" folder needs to be imported and Petty cash transactions needs to be processed).

AFRIKAANS

The following Set of Books based on the Afrikaans tutorial, is installed in the "*...\bin\Tutorials\AFRIKAANS*" folder.

- NUTSMAN (No transactions).
- NUTSMAN-A (Unposted)
- NUTSMAN-B (Posted).

COST-CENTRES

Tutorials / examples to explore the activation, processing and reporting of Cost centres in osFinancials5/TurboCASH5. See - Cost centres in this Help file.

The following Set of Books based on this tutorial, is installed in the "*...\bin\Tutorials\COST-CENTRES*" folder:

- COST-CENTRES-A (transactions and documents not posted to the ledger).
- COST-CENTRES-B (transactions and documents posted to the ledger).

PROJECTS

Tutorials / examples to explore the activation, processing and reporting of Projects in osFinancials5/TurboCASH5. See - Projects in this Help file.

The following Set of Books based on this tutorial, is installed in the "*...\bin\Tutorials\PROJECTS*" folder:

- PROJECTS-A (transactions and documents not posted to the ledger).
- PROJECTS-B (transactions and documents posted to the ledger).

Created with the Standard Edition of HelpNDoc: Make Your PDFs More Secure with Encryption and Password Protection

Close Set of Books

This option allows you to close the currently open Set of Books.

To close a Set of Books:

1. On the Start ribbon, select Close Set of Books.

It's important to regularly backup your Set of Books to prevent data loss.

Created with the Standard Edition of HelpNDoc: Free Kindle producer

Delete Set of Books

If you want to remove a Set of Books permanently from your osFinancials5/TurboCASH5 system, you should be absolutely certain that you want to do so, as all data contained within the Set of Books will be permanently lost. Before deleting a Set of Books from your system, it is important to ensure that you have printed all necessary reports and retained any supporting documents, such as slips, invoices, etc., which will help substantiate your profit (or loss) from the business. This information may be required for your tax returns or other legal purposes. Therefore, it is crucial to make sure that you have all the necessary documentation before deleting a Set of Books.

This operation can not be reversed! If you have deleted a Set of Books by mistake, you need to restore it from a backup file!

It is important to remember that even if you are a small business, you are required to keep the necessary records for at least five years starting from the date you received the last applicable tax return. This is to comply with audit and record-keeping requirements.

Additionally, if there are other statutory prescriptions that apply to your business, you should also comply with them. Therefore, it is crucial to maintain accurate and complete records and ensure that you retain them for the required period of time to meet legal obligations.

After you have taken all necessary steps and are absolutely certain that you want to proceed with the deletion of a Set of Books, you may then delete it from your system.

To delete a Set of Books:

1. On the Start ribbon, select Delete Set of Books. The following "*Set of Books*" screen, reflecting the list of all Set of Books, is displayed:





The location or full path of the selected Set of Books is displayed. Before you click the Delete button, make absolutely sure that the correct Set of Books is selected.

Red - Font colour

This indicates that a Set of Books (elsewhere on your system) is deleted or the Set of Books folder is moved somewhere else on your system. It may also indicate that the drive or network on which the Set of Books is stored, is not available or mounted.

Blue - Font colour

This indicates that a Set of Books is not located in the directory where osFinancials5/TurboCASH5 is installed, but elsewhere on your system.

2. Select the Set of Books, and click on the Delete button. The following confirmation message is

displayed:

> Are you sure you want to delete the MY-BOOKS set of accounts?"

3. If you are sure, click on the Yes button. Another confirmation message is displayed:

> The Set of Books MY-BOOKS will permanently be removed from disk!
> Do you want to cancel the deletion?

4. On this screen you have the option to cancel the deletion process. If you click on the Yes button, the process will be terminated. If you click on the No button, the Set of Books will be permanently deleted.

5. Wait for the deletion process to finish. The following information message is displayed:

> "Set of Books C:\osFinancials5\books\MY-BOOKS\books.fdb deleted!" or
> "Set of Books C:\TurboCASH5\books\MY-BOOKS\books.fdb deleted!" or

6. Click on the OK button.

Once the Set of Books is deleted, the contents of the folder with the name of the Set of Books maybe emptied and the files of the
your Operating System.



You may need to: -

W *The Set of Books should by default be deleted. You may check in the books folder (e.g."C:\osfinancials5\books\MY-BOOKS delete the folder, if not deleted. (If this action is not done, you will not be able to create or save a Set of Books with exactly t*

W *Empty the Recycle Bin of your Operating System.*

If the Set of Books is not too large for your Recycle Bin, all the files for the deleted Set of Books will be transferred to your Recycle Bin. You then need to click on the Recycle Bin icon on your desktop and empty the Recycle Bin to make more space available on your hard disk.

Should you have any Set of Books open on the system whilst deleting a Set of Books, osFinancials5 will automatically close any Set of Books on your system at this stage.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of a Help Authoring Tool

Exit osFinancials5

It is recommended that you create regular backups of your data before exiting osFinancials5/TurboCASH5. The decision of whether or not to make a backup depends on the amount of data that you have entered.

To exit (close) osFinancials5/TurboCASH5:

1. Click on the 

button on the top right-hand corner of the osFinancials5/TurboCASH5 title bar.

   You may also press the Alt and Q keys.

   If no Set of Books are opened, the osFinancials5/TurboCASH5 program will be closed.

2. osFinancials5 will automatically close any Set of Books that is open. The following information message will be displayed:

   osFinancials5 would like to remind you that:
   It is good practice to make regular backups and archive copies of your Sets of Books to prevent loss of data.
   Do you wish to close osFinancials5?

3. Take note of this information, and click on the Yes button, only if you are absolutely sure that you wish to exit (close) osFinancials5/TurboCASH5.

   It is recommended that you Backup the Set of Books and store it in a safe place.

   If you click on the No button, osFinancials5 will not close. You may then perform the necessary backups e.g. to a different location before exiting (closing) the program. You may then close the Set of Books and exit osFinancials5/TurboCASH5.

Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-

Use Tool

Create Set of Books

You may create exact copies from existing sets of books, templates on your system. The following options are available:

- Save as (Start ribbon).
- Create Set of Books (Copy an existing Set of Books? option on the "*Creation wizard*") (Start ribbon).
- Tools → Global processes → Copy from a Set of Books (Setup ribbon).

On the Start ribbon, you can select the Create Set of Books option or simply press the F10 key on your keyboard to use any of the following options on the "*Creation wizard*":



You may use the different options available when creating a new Set of Books in osFinancials:

1. Copy an existing Set of Books? - This option allows you to create a new Set of Books by making an exact copy of an existing one, including all the data it contains. You can select the Set of Books you want to copy, and the system will create a new one in a directory of your choice.

2. Let TurboCASH5 help you to create a Set of Books? - This option lets you create a new Set of Books by selecting an existing Set of Books as a template. osFinancials5/TurboCASH5 will then guide you through the process of setting up your new Set of Books. You can also download pre-existing Sets of Books for your specific country or industry as templates to use as a starting point.

After downloading a Set of Books (template) using the "Let TurboCASH5 help you to create a Set of Books?" option, the "Save as" screen will be launched, allowing you to save the template in a directory of your choosing.

You can also view a list of available Sets of Books available for a download to use as templates for your new Set of Books.

After downloading a Set of Books, the Set of Books (template) will automatically open in the language associated with the country and language of the Set of Books.

3. Create a Set of Books (Advanced)? - This option is intended for more advanced users who want to create a new Set of Books from scratch. You can select either the Firebird or MSSQL database type, providing more flexibility and control over the structure and content of your new Set of Books. You can also choose to set a maximum of 8-digit account codes, giving you more flexibility in creating a Set of Books that best suits your needs.

When creating, converting, or copying a Set of Books, the default number of characters for the account codes is determined by the selected Set of Books. Most Sets of Books currently use 3-digit account codes as their default setting.

However, if you choose the "Create a Set of Books (Advanced)?" option , you can select a maximum of 8-digit account codes, providing more flexibility in creating a Set of Books that suits your needs.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Copy an existing Set of Books

This option allows you to create a new Set of Books by making an exact copy of an existing one, including all the data it contains. You can select the Set of Books you want to copy, and the system will create a new one in a directory of your choice.

This new Set of Books can be accessed within the osFinancials5/TurboCASH5 program, even if it is not created in the osFinancials5/TurboCASH5 directory. You may keep your Set of Books in any mapped directory, i.e. on a local or network drive.

To create a copy of a Set of Books:

1. On the Start ribbon, you can select the Create Set of Books option or simply press the F10 key on your keyboard.



2. osFinancials5/TurboCASH5 automatically defaults to the option "*Let osFinancials help you to create a Set of Books?*", as this is the recommended option for most users. Select the "*Copy an existing Set of Books?*" option.

3. Click on the Next button.



4. Select any of the available Set of Books on your system. If you do not find the Set of Books on the list, you may click on the Browse button to find a Set of Books from the "*Pick a directory*" screen.

5. Click on the Next button.



6. Enter the name for your new Set of Books.

> *The name must not already exist and may not be longer than 50 characters. This name will help you to identify your Set of Books on your system and you will need to select this name, whenever you need to open the Set of Books or perform some other functions on the Set of Books.*

> *The Directory in which you create the Set of Books is displayed underneath the Location Browse button. It will usually be the default directory in which osFinancials5/TurboCASH5 is installed, or the directory which you have specified when you installed* osFinancials5/TurboCASH5. *If you wish to create your Set of Books in any other directory or location on your system, you may click on the Browse button to select any folder or drive on the "Pick a directory" screen.*

7. Click on the Finish button. A confirmation message is displayed:

> Are you sure you want to create the MY-BOOKS Set of Books?

8. To confirm that you want to create the Set of Books, click on the Yes button. An information message

> MY-BOOKS Set of Books created!

9. Click OK. The new Set of Books, which is a copy of another Set of Books, is automatically opened and ready to work in.

Year-end confirmation

Should you open the Set of Books, and the date of the end of the year, is in the past, a confirmation message will be displayed, for example;

> This year Ends on 2022/02/28
> Today 2022/04/04
> Warning, this date does not fall into any of this or last year's reporting dates!
> Do year end?

You need to adjust the Start of the financial year in one of the following options on the Setup ribbon:

- *Setup → Reporting dates (if no transactions were processed for the Set of Books).*
- *Do year end.*

If you have created a copy of an existing Set of Books, which already has transactions and balances:

If you do wish to have a clean Set of Books with no transactions and balances, you may need to clear / reset the transactions and balances in the Set of Books. (See Global processes → Clear / Reset on the Setup ribbon). All the master files (accounts, etc.) will be available and you may then enter your own transactions and balances in the new Set of Books.

This is similar to Save as option on the Start ribbon), where you may save an exact copy of an existing Set of Books with a new name.

You may also copy all the settings and data of an existing Set of Books into a new Set of Books using Global processes → Copy from a Set of Books on the Setup ribbon.

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

Let osFinancials5/TurboCASH5 help you to create a Set of Books

---

osFinancials5/TurboCASH5 will guide you through the steps to create a new Set of Books with the "*Creation wizard*" in a matter of minutes.

It is a good idea to check that you have all the necessary information regarding your business at hand

before starting to create your Set of Books.

Once you have the necessary information available, you may proceed to create your Set of Books. Should you not have all the information available at this stage, you may go back and enter or change some of the information at a later stage.

The following options to create a Set of Books using the "*Let osFinancials help you to create a Set of Books?" / "Let TurboCASH help you to create a Set of Books?" wizard*, is available:

- To create a Set of Books using a template on your system.
- To create a Set of Books downloading a template from osFinancials5.

To create a Set of Books using a template:

1. On the Start ribbon, you can select the Create Set of Books option or simply press the F10 key on your keyboard.



2. osFinancials5.1 automatically defaults to the option "*Let osFinancials help you to create a Set of Books?"* or in TurboCASH5-3 "*Let TurboCASH5-3 help you to create a Set of Books?"* as this is the recommended option for most users. You only need to check that it is selected.

3. Click on the Next button. The Download books - "*Which Chart of Accounts do you want to use?*" screen will automatically be launched, if you have an Internet connection:



osFinancials5/TurboCASH5 supports 79 different languages and counties / tax regimes languages liked to 87 Sets of Books (databases) which may be downloaded and customised to meet your requirements.

If the set of books for your language and or country, is not available in the books directory, you may select any of the available Firebird Sets of Books and linked languages available as a free download.

If you do not wish to use this online option, exit the "Which Chart of Accounts you wish to use?" Download screen.

You may click the Browse button, to select another Set of Books on your system.

The Directory in which you will create the Set of Books is displayed underneath the Location

Browse button. It will usually be the default directory in which osFinancials5.1/TurboCASH5-3 is installed or other directory, which you have specified when you have installed osFinancials5.1/TurboCASH5-3.

If you wish to create your Set of Books in any other directory or location on your system, you may click on the Browse button to select any folder or drive on the Pick a directory screen.



4. Select a Set of Books (template).

5. Click on the Next button.



6. Enter the name for your new Set of Books.

The name must not already exist and may not be longer than 50 characters. This name will help you to identify your Set of Books on your system and you will need to select this name, whenever you need to open the Set of Books or perform some other functions on the Set of Books.

The Directory in which you will create the Set of Books is displayed underneath the Location Browse button. It will usually be the default directory in whichosFinancials5/TurboCASH5 is installed or other directory, which you have specified when you have installed osFinancials5. If you wish to create your Set of Books in any other directory or location on your system, you may click on the Browse button to select any folder or drive on the "Pick a directory" screen.

Database type - Firebird is the default for all Sets of Books included in the install and Sets of Books available for download.

Microsoft SQL Server (MSSQL) Database types is also introduced in osFinancials5 (518). Also implemented in TurboCASH5-3.

You may create MySQL databases (see - My SQL database online manual) and Postgress databases (see - Postgress database online manual).

> *NOTE: In addition to the Firebird database types, only the Microsoft SQL Server (MSSQL) Database types is supported.*

7. Click on the Next button.



8. By default, all options is selected. It is recommended that you keep all setup options selected to confirm or change the basic settings. The screens, based on this selection, will launch when you click on the Finish button. The confirmation message will be displayed.

> "Are you sure you want to create the MY-BOOKS Set of Books?" (where "MY-BOOKS" is the name of the Set of Books entered)

9. Click on the Yes button. The following screens from the Setup ribbon will automatically be displayed as selected on the last screen of the Creation wizard.

10. Enter and select the necessary information and settings for the following screens:

    a) Company info - Enter all your business' details such as the address, e-mail address, contact numbers and Company and Tax Registration numbers, which you need to display on all documents, reports, and lists. You may also select whether your default output option for

documents, reports and lists are on: screen, printer, file, e-mail or fax. You may also load a logo picture to be displayed on your reports or documents, and set your Windows operating system's default date and currency formats.

b) Reporting dates - Set up the number of reporting dates required, and the start date of your financial year period. The periods or dates will be displayed in the format in which you have set your Windows Operating System's default date on the previous screen.

c) Batch types - Check the default batch types, add (create) new batch types, delete an existing batch type, or change the name of existing batch types in which you wish to enter and update or post your transactions to the ledger.

d) Groups - Set up to two Reporting groups for your General ledger, Debtors, Creditors accounts, Stock and Document groups.

e) Documents setup - This option allows you to set up your documents Invoices, Credit notes, Quotes, Orders, Purchases and Supplier return documents, you wish to hand to customers (debtors) or suppliers (creditors) when you sell, or quote, or order and purchase, stock items and services.

f) Stock information - Set the selling price descriptions, default selling price, cost of sales, options for documents, unit sizes, tax classes, etc. This option should be used if you use stock and/or wish to generate documents (Invoices, Credit notes, Quotes, Orders, Purchases and Supplier returns).

g) Salesperson - This option allows you to enter or add the salespersons who will be processing documents.

11. After the last setup screen (i.e. Salesperson) is closed, the new Set of Books, is automatically opened and ready to work in.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Let osFinancials5/TurboCASH5 help you to create a Set of Books - Download

---

osFinancials5/TurboCASH5 will guide you through the steps to create a new Set of Books with the "*Creation wizard*" in a matter of minutes.

It is a good idea to check that you have all the necessary information regarding your business at hand before starting to create your Set of Books.

Once you have the necessary information available, you may proceed to create your Set of Books. Should you not have all the information available at this stage, you may go back and enter or change some of the information at a later stage.

The following options to create a Set of Books using the "*Let osFinancials5-1 help you to create a Set of Books?" / "Let TurboCASH5-3 help you to create a Set of Books?" wizard*, is available:

- To create a Set of Books using a template on your system.
- To create a Set of Books downloading a template from osFinancials5.

To create a Set of Books downloading a template:

1. On the Start ribbon, you can select the Create Set of Books option or simply press the F10 key on your keyboard.



2. osFinancials5.1 automatically defaults to the option "*Let osFinancials help you to create a Set of Books?"* or in TurboCASH5-3 "*Let TurboCASH5-3 help you to create a Set of Books?"* as this is the recommended option for most users. You only need to check that it is selected.

3. Click on the Next button. The "*Which Chart of Accounts do you want to use?*" screen on which you may

select a Set of Books (template) for your country, language. country or industry to download will automatically be launched, if you have an internet connection.

4. If you do not wish to download a Set of Books from the osFinancials website, you may close this online screen on the titlebar.

If you do not have an Internet connection, clicking on the Online button will automatically close. You may click on the button to elect a Set of Books in your osFinancials5.1/TurboCASH5-3 installation folder.



5. If you have an Internet connection, "*Which Chart of Accounts do you want to use?*" download screen will automatically be launched.



File date	Country	Type	Name of Set of Books	URL
2021/03/04	BARBADOS	General	EN-BARBADOS	http://www.osfinancials.org/books/EN/EN-BARBADOS.zip
2021/03/04	BELIZE	General	EN-BELIZE	http://www.osfinancials.org/books/EN/EN-BELIZE.zip
2021/03/04	BOTSWANA	General	EN-BOTSWANA	http://www.osfinancials.org/books/EN/EN-BOTSWANA.zip
2021/03/04	CAMEROON	General	EN-CAMEROON	http://www.osfinancials.org/books/EN/EN-CAMEROON.zip
2021/03/04	CANADA	General	EN-CANADA-CORPORATION	http://www.osfinancials.org/books/EN/EN-CANADA-CORPORATION.zi
2021/03/04	CANADA	General	EN-CANADA-OTHER	http://www.osfinancials.org/books/EN/EN-CANADA-OTHER.zip
2021/03/04	IRELAND	General	EN-IRELAND	http://www.osfinancials.org/books/EN/EN-IRELAND.zip
2021/03/04	ISLEOFMAN	General	EN-ISLEOFMAN	http://www.osfinancials.org/books/EN/EN-ISLEOFMAN.zip
2021/03/04	LESOTHO	general	EN-LESOTHO	http://www.osfinancials.org/books/EN/EN-LESOTHO.zip
2021/03/04	MALAWI	General	EN-MALAWI	http://www.osfinancials.org/books/EN/EN-MALAWI.zip
2021/03/04	MALTA	General	EN-MALTA	http://www.osfinancials.org/books/EN/EN-MALTA.zip
2021/03/04	MAURITIUS	General	EN-MAURITIUS	http://www.osfinancials.org/books/EN/EN-MAURITIUS.zip
2021/03/04	NAMIBIA	General	EN-NAMIBIA	http://www.osfinancials.org/books/EN/EN-NAMIBIA.zip
2021/03/04	NEWZEALAND	general	EN-NEWZEALAND	http://www.osfinancials.org/books/EN/EN-NEWZEALAND.zip
2021/03/04	RWANDA	General	EN-RWANDA	http://www.osfinancials.org/books/EN/EN-RWANDA.zip
2021/03/04	SOUTH-AFRICA	General	EN-SOUTHAFRICA	http://www.osfinancials.org/books/EN/EN-SOUTHAFRICA.zip
2021/03/04	TANZANIA	General	EN-TANZANIA	http://www.osfinancials.org/books/EN/EN-TANZANIA.zip
2021/03/04	TONGA	General	EN-TONGA	http://www.osfinancials.org/books/EN/EN-TONGA.zip
2021/03/04	TRINIDADTOBAGO	General	EN-TRINIDADTOBAGO	http://www.osfinancials.org/books/EN/EN-TRINIDADTOBAGO.zip
2021/03/04	UGANDA	General	EN-UGANDA	http://www.osfinancials.org/books/EN/EN-UGANDA.zip
2021/03/04	UK	General	EN-UK	http://www.osfinancials.org/books/EN/EN-UK.zip
2021/03/04	USA	General	EN-US-CALIFORNIA	http://www.osfinancials.org/books/EN/EN-US-CALIFORNIA.zip
2021/03/04	USA	General	EN-US-GENERIC	http://www.osfinancials.org/books/EN/EN-US-GENERIC.zip
2021/03/04	USA	General	EN-USA	http://www.osfinancials.org/books/EN/EN-USA.zip
2021/03/04	ZAMBIA	General	EN-ZAMBIA	http://www.osfinancials.org/books/EN/EN-ZAMBIA.zip
2021/03/04	ZIMBABWE	General	EN-ZIMBABWE	http://www.osfinancials.org/books/EN/EN-ZIMBABWE.zip
2021/03/04	SOUTH-AFRICA	General	CHURCH	http://www.osfinancials.org/books/EN/CHURCH.zip
2021/03/04	SOUTH-AFRICA	General	FARMING	http://www.osfinancials.org/books/EN/FARMING.zip
2021/03/04	SOUTH-AFRICA	General	MANUFACTURING	http://www.osfinancials.org/books/EN/MANUFACTURING.zip
2021/03/04	SOUTH-AFRICA	General	MEDICAL	http://www.osfinancials.org/books/EN/MEDICAL.zip
2021/03/04	SOUTH-AFRICA	General	RESTAURANT	http://www.osfinancials.org/books/EN/RESTAURANT.zip
2021/03/04	SOUTH-AFRICA	General	RETAIL	http://www.osfinancials.org/books/EN/RETAIL.zip
2021/03/04	SOUTH-AFRICA	General	SCHOOL	http://www.osfinancials.org/books/EN/SCHOOL.zip
2021/03/04	SOUTH-AFRICA	General	SERVICE	http://www.osfinancials.org/books/EN/SERVICE.zip
2021/03/04	SOUTH-AFRICA	General	WORKSHOP	http://www.osfinancials.org/books/EN/WORKSHOP.zip
Language : EL				
2021/03/04	CYPRUS	general	EL-CYPRUS	http://www.osfinancials.org/books/EL/EL-CYPRUS.zip
2021/03/04	GREECE	general	EL-GREECE	http://www.osfinancials.org/books/EL/EL-GREECE.zip
Language : AF				
2021/03/04	SUID-AFRIKA	Algemeen	AF-SUID-AFRIKA	http://www.osfinancials.org/books/AF/AF-SUID-AFRIKA.zip
2021/03/04	SUID-AFRIKA	Handleiding	NUTSMAN-A	http://www.osfinancials.org/books/AF-HANDLEIDINGS/NUTSMAN-A.zi

osFinancials5/TurboCASH5 supports 79 different languages and counties / tax regimes languages liked to 87 Sets of Books (databases) which may be downloaded and customised to meet your requirements.

If the set of books for your language and or country, is not available in the books directory, you may select any of the available Firebird Sets of Books and linked languages available as a free download.

6. Select the Chart of Accounts (Set of Books) and click on the Download button. Once the download, is completed, the "*Save as*" screen will display the Name of the selected downloaded Set of Books.



7. Enter a unique name for the Set of Books.

> *If the name for the new Set of Books already exists, an information message is displayed:*
>
> That Set of Books already exists! Please re-enter!
>
> *Enter a new name for the Set of Books.*

8. Click Save. The following information message is displayed:

Set of Books created!

9. Click OK. The Set of Books will automatically be opened.

> *Year-end confirmation*
>
> *Should you open the Set of Books, and the date of the end of the year, is in the past, a confirmation message will be displayed, for example;*
>
> This year Ends on 2022/02/28
> Today 2022/04/04
> Warning, this date does not fall into any of this or last year's reporting dates!
> Do year end?
>
> *You need to adjust the Start of the financial year in one of the following options on the Setup ribbon:*
>
> - *Setup → Reporting dates (if no transactions were processed for the Set of Books).*
> - *Do year end.*

10. To complete and configure the downloaded Set of Books for your needs, it is recommended that you first check enter, add and select the necessary information and settings:

    a) Accounts - Check the Chart of Accounts. Add any accounts required. You may also Disable or Delete any accounts that you do not require. Specific attention is required with the following

account types:

i) Tax accounts - Check that the correct tax codes and tax percentages are applicable to your country. You may need to change the descriptions, add tax codes, change the tax percentages, etc.

ii) Bank accounts - Rename an existing bank account, check your Payments and Receipt batches linked to the bank account. Add any additional bank accounts or delete unnecessary bank accounts.

b) Company info - Enter all your business' details such as the address, e-mail address, contact numbers and Company and Tax Registration numbers, which you need to display on all documents, reports, and lists. You may also select whether your default output option for documents, reports and lists are on: screen, printer, file, e-mail or fax. You may also load a logo picture to be displayed on your reports or documents, and set your Windows operating system's default date and currency formats.

c) Reporting dates - This option allows you to set up the number of reporting dates required, and the start date of your financial year period. The periods or dates will be displayed in the format in which you have set your Windows Operating System's default date on the previous screen.

d) Batch types - This option allows you to create, delete an existing batch type, or change the name of an existing batch type in which you wish to enter and update or post your transactions to the ledger.

e) Groups - This option allows you to set up to two Reporting groups for your General ledger, Debtors, Creditors accounts, Stock and Document groups.

f) Documents setup - This option allows you to set up your documents Invoices, Credit notes, Quotes, Orders, Purchases and Supplier return documents, you wish to hand to customers (debtors) or suppliers (creditors) when you sell, or quote, or order and purchase, stock items and services.

g) Salesperson - This option allows you to enter or add the salespersons who will be processing documents.

h) Stock items - Add your stock items (inventory items / products).

i) Debtors - Add your debtor (customer / client) accounts.

j) Creditors - Add your creditor (supplier / vendor) accounts.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Customise your own Set of Books (Advanced)

In osFinancials5/TurboCASH5, when creating a Set of Books from scratch using the "*Customise your own Set of Books (Advanced)?*" option in the "*Creation wizard*", you have the flexibility to define your chart of accounts according to your specific needs and requirements. It is important to consider some steps when designing you own Chart of Accounts.

Basic Sets of Books for the Firebird database is included in the bin/CUSTOMIE-EMPTY-BOOKS folder of your osFinancials5.1/TurboCASH-3 installation. The following Sets of Books (templates) with longer field lengths and only the three basic control accounts is available in the bin/CUSTOMIE-EMPTY-BOOKS folder:

1. *CUSTOMISE-EMPTY-BOOKS-3X3-DIGITS*
2. *CUSTOMISE-EMPTY-BOOKS-4X3-DIGITS*
3. *CUSTOMISE-EMPTY-BOOKS-5X3-DIGITS*
4. *CUSTOMISE-EMPTY-BOOKS-6X3-DIGITS*
5. *CUSTOMISE-EMPTY-BOOKS-7X3-DIGITS*
6. *CUSTOMISE-EMPTY-BOOKS-8X3-DIGITS*

Select a CUSTOMIE-EMPTY-BOOKS template:

- *Copy an existing Set of Booksc Use this option and use the Browse button to navigate to the bin/CUSTOMIE-EMPTY-BOOKS folder. Enter the name of your Set of Books.*
- *Save as: Open a Set of Books and use the Browse button to navigate to the bin/CUSTOMIE-EMPTY-BOOKS folder. Once the CUSTOMISE SET OF BOOKS template of your choice is opened, go the Save as option on the Start ribbon and save your Set of Books with your own name in the books directory.*

Key features:

- *Description length increased and Added missing entries in the Types table.*
- *Changed the number of characters in the Descriptions (Account description and Groups description) to 128 characters.*

Should you need any further field length adjustments for osFinancials and TurboCASH, please visit the osFinancials webshop.

Accounts:

These Sets of Books only include the 3 control accounts (i.e. Debtors control + Creditors control + Retained

earnings) accounts in the Chart of Accounts.

You may change these three control account numbers and descriptions to meet your specific requirements. It is recommended that you do it before you add or import your ledger. accounts.

See - Designing a Chart of Accounts in this documentation.

Updated Types table:

- *Added: Groups for Projects -1000, Cost centre 1 -1002, Cost centre 2 - 1003 and Languages -1004.*
- *Added: Paper types - 55 - Till slip and 56 New plain paper types.*

When creating a Set of Books using the "*Customise your own Set of Books (Advanced)?*" option, you begin with a clean slate and have to build your chart of accounts from scratch. The initial setup process will only include three main control accounts: the Debtor's control account, Creditor's control account, and Retained earnings account.

As part of this customisation process, you will have the opportunity to set the number of main digits for your accounts, ranging from 3 to 8 digits. Additionally, you will specify the account numbers for three main control accounts: the Creditors control account, Debtors control account, and Retained earnings account.

1. *The Creditors control account is a general ledger account that represents the total amount owed to the company by its creditors or suppliers. It serves as a summary account for all individual creditor accounts and helps track the company's outstanding payables.*
2. *The Debtors control account, on the other hand, is a general ledger account that represents the total amount owed to the company by its debtors or customers. It acts as a summary account for all individual debtor accounts and aids in monitoring the company's receivables.*
3. *The Retained earnings account, reflects the cumulative net earnings or profits of the company that have been retained and reinvested in the business. It represents the portion of equity that is derived from the company's profitability and serves as a financial record of the accumulated profits over time.*

By defining these main control accounts during the Set of Books creation process, you can structure your chart of accounts and design the account numbering system that aligns with your specific accounting practices and reporting requirements.

To complete the setup and create a comprehensive chart of accounts, you will need to define and link all the necessary accounts in your organisation. This includes creating and setting up Ledger accounts, Bank accounts, Creditor accounts, Debtor accounts, and Tax accounts. You have the flexibility to customize the account structure and naming conventions based on your specific requirements.

Additionally, you will also need to create and configure other elements such as Batch types, Groups, and

any other accounts or settings that are relevant to your business operations. This allows you to tailor the Set of Books to suit your organisation's needs and ensure accurate financial management and reporting.

By going through the setup process and defining the necessary accounts, you establish the foundation for recording and managing financial transactions within osFinancials5/TurboCASH5, enabling you to effectively track and analyse your company's financial activities.

Choosing the number of digits for main accounts

See - Chart of Accounts - Optimising 4-,5-,6-,7- and 8-digit main accounts - Some recommendations and tips to plan your Chart of Accounts according to your selection on the number of Main account digits -

Choosing the appropriate number of digits for main accounts is an important consideration when setting up your Chart of Accounts in osFinancials5/TurboCASH5. The number of digits determines the level of detail and granularity in your account numbering system.

When creating your Set of Books, you will be prompted to select the number of main account digits. For example, if you choose a 4-digit main accounts Chart of Accounts, the and you have initially assigned the following account numbers: 1100 for the Debtor's control account, 2100 for the Creditor's control account, and 3100 for the Retained earnings account. These are default account codes that can be modified later if needed.

The selection of main account digits impacts the structure and organization of your Chart of Accounts. Here are some recommendations and tips to consider:

- 4-digit main accounts: This option provides a concise and compact Chart of Accounts, it can be suitable for small and medium enterprises as well as larger organizations that need to comply with various accounting frameworks and standards such as GAAP US, GAAP UK, SA GAAP, NZ GAAP, IFRS (full), IFRS for SMEs, and others based on their jurisdiction and accounting needs. However, it's important to note that this option may have limitations in accommodating detailed account classifications or sub-categories.
- 5 to 8-digit main accounts: These options offer greater offer greater flexibility and granularity in your Chart of Accounts. These options allow for more detailed account classifications and sub-categories, making them beneficial for larger organizations or those with complex accounting requirements. With these options, you can design a Chart of Accounts that aligns precisely with your financial reporting needs and internal management requirements.

It's crucial to consider your organization's size, complexity, and reporting needs when choosing the number of main account digits. By selecting the appropriate option, you can ensure that your Chart of Accounts supports accurate financial reporting, compliance with accounting standards, and effective management of your organization's financial data.

When creating a Set of Books with the option to choose the number of digits for main accounts, you have the flexibility to select a structure that suits your needs. Here are the available options and the corresponding number of digits for the general ledger main accounts:

4-Digit General ledger main accounts: Enter a 4-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100, 1100, and 3100). This option includes 3-digit sub-accounts as well as 7-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger.

5-Digit General ledger main accounts: Enter a 5-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000, 11000, and 31000). This option includes 3-digit sub-accounts as well as 8-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

6-Digit General ledger main accounts: Enter a 6-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 210000, 110000, and 310000). This option includes 3-digit sub-accounts as well as 9-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

7-Digit General ledger main accounts: Enter a 7-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100000, 1100000, and 3100000). This option includes 3-digit sub-accounts as well as 10-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

8-Digit General ledger main accounts: Enter an 8-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000000, 11000000, and 31000000). This option includes 3-digit sub-accounts as well as 11-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

When planning your Chart of Accounts, it's important to carefully consider and define the codes or numbers for these accounts based on the structure you have chosen. This will help ensure consistency and organization in your financial reporting and analysis.

After creating your Set of Books, you still have the flexibility to change the account codes or numbers in the Chart of Accounts. In the Setup → Accounts menu on the Setup ribbon, you can modify the account codes to align with your specific requirements, including the codes for the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100, 1100, and 3100 in the example of the 4-Digit General ledger main accounts). This initial stage allows you to plan and design your chart of accounts according to your needs.

However, it's important to note that once you start processing functions such as entering transactions or budgets, you may not be allowed to change the account codes or numbers. Therefore, careful consideration and planning during the initial setup stage is crucial to ensure accurate financial structure and reporting.

By carefully selecting the number of main account digits and customizing the account codes in the Chart of Accounts, you can optimize the organization and usability of your financial data within osFinancials5/TurboCASH5.

Defining Account groups and Financial categories

Before creating and setting up Ledger accounts, Bank accounts, Creditor accounts, Debtor accounts, and Tax accounts in osFinancials5/TurboCASH5, it is recommended to define the basic classification of accounts using Account Group 1 or Account Group 2. This helps organize and categorize your accounts based on their nature or function.

In the Setup → Groups menu on the Setup ribbon, you can add Account Group 1 or Account Group 2 and assign them meaningful names that represent different account classifications. For example, you can create groups for fixed assets, cash and receivables, current assets, current liabilities, equity, operating expenses, operating revenue, non-operating expenses, non-operating revenue, etc. These groups provide a structured framework for organising your accounts.

After creating the account groups, you can map or link them to the five financial categories: Assets, Liabilities, Equity, Income, and Expenses in the Setup → Financial categories menu on the Setup ribbon. This mapping ensures that the accounts are correctly classified within the financial framework of your organisation.

When you proceed to create and set up Ledger accounts, Bank accounts, and Tax accounts in the Setup → Accounts menu, you will have the option to select the appropriate Account Group 1 and/or Account Group 2 for each account. By associating the accounts with their respective account groups, you establish a hierarchical structure that allows for easier navigation and analysis of financial information.

By properly defining and linking account groups, you lay the foundation for accurate financial reporting and analysis within osFinancials5/TurboCASH5, enabling you to effectively track and manage your organisation's financial data.

Process to create a Set of Books using the Customize your own Set of Books (Advanced) option

To create a Set of Books using the Advanced option:

1. On the Start ribbon, you can select the Create Set of Books option or simply press the F10 key on your keyboard.



2. osFinancials5 / TurboCASH automatically defaults to the option "*Let osFinancials help you to create a Set of Books?*"/ "*Let TurboCASH help you to create a Set of Books?*" , as this is the recommended option for most users. Select the "*Create a Set of Books (Advanced)?*" option.

3. Click on the Next button.



4. Enter the name for your Set of Books.

> *The name must not already exist and may not be longer than 50 characters. This name will help you to identify the Set of Books on your system. You will need to select this name whenever you need to open the Set of Books or perform some other functions on the Set of Books.*

> *The Directory in which you create the Set of Books is displayed underneath the Location Browse button. It will usually be the default directory (e.g. "C: \ osfinancials5 \ books" folder in which osFinancials5/TurboCASH5 is installed or directory, which you have specified when you installed osFinancials5/TurboCASH5. If you wish to create your Set of Books in any other directory or location on your system, you may click on the Browse button, if desired, to select any folder or drive on the "Pick a directory" screen.*

5. Check the location where you wish to create the Set of Books is correct, and click on the Next button.



6. Account digits: The default number of account Digits is 3. Select the desired number of digits for your general ledger main accounts. This will determine the structure and length of the account codes for the Creditor's control, Debtor's control, and Retained income/earnings accounts.

7. Account codes: Enter the numeric code for each of these accounts based on the chosen number of digits. For example, in a 4-digit structure, you would enter codes like 2100, 1100, and 3100.

When creating a Set of Books with the option to choose the number of digits for main accounts, you have the flexibility to select a structure that suits your needs. Here are the available options and the corresponding number of digits for the general ledger main accounts:

4-Digit General ledger main accounts: Enter a 4-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100, 1100, and 3100). This option includes 3-digit sub-accounts as well as 7-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger.

5-Digit General ledger main accounts: Enter a 5-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000, 11000, and 31000). This option includes 3-digit sub-accounts as well as 8-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

6-Digit General ledger main accounts: Enter a 6-digit numeric code for each of the Creditor's

control, Debtor's control, and Retained income/earnings accounts (e.g., 210000, 110000, and 310000). This option includes 3-digit sub-accounts as well as 9-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

7-Digit General ledger main accounts: Enter a 7-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100000, 1100000, and 3100000). This option includes 3-digit sub-accounts as well as 10-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

8-Digit General ledger main accounts: Enter an 8-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000000, 11000000, and 31000000). This option includes 3-digit sub-accounts as well as 11-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

When planning your Chart of Accounts, it's important to carefully consider and define the codes or numbers for these accounts based on the structure you have chosen. This will help ensure consistency and organization in your financial reporting and analysis.

However, it's important to note that once you start processing functions such as entering transactions or budgets, you may not be allowed to change the account codes or numbers. Therefore, careful consideration and planning during the initial setup stage is crucial to ensure accurate financial structure and reporting.

8. Click on the Next button to initiate each of the set up options listed on the right-hand side of the "Creation wizard" screen. Enter and select the necessary information and settings for the following screens:

    a) Company info - Enter all your business' details such as the address, e-mail address, contact numbers and Company and Tax Registration numbers, which you need to display on all documents, reports, and lists. You may also select the Tax method applicable to your VAT/GST/Sales Tax registration, whether your default output option for documents, reports and lists are on: screen, printer, file, e-mail or fax. You may also load a logo picture to be displayed on your reports or documents, and set your Windows operating system's default date and currency formats.

    b) Reporting dates - This option allows you to set up the number of reporting dates required, and the start date of your financial year period. The periods or dates will be displayed in the format in which you have set your Windows Operating System's default date on the previous screen.

The start date of the financial year is the first day of the calendar month in which the Set

of Books (Advanced option) is created.

For example, it it is created on 20 August 2021, the Start date is 1 August 2021, etc.

Before the "Reporting dates" screen is launched, a message will be displayed.

Periods are not there

Click on OK to launch the "Reporting dates" screen.

c) Batch types - This option allows you to create, delete an existing batch type, or change the name of an existing batch type in which you wish to enter and update or post your transactions to the ledger.

d) Groups - This option allows you to set two Reporting groups for your General ledger accounts, Debtors, Creditors, Stock and Document groups.

e) Salesperson - This option allows you to enter the salespersons names who will be selling your stock items, or selling services.

f) Documents setup - This option allows you to set up your documents Invoices, Credit notes, Quotes, Orders, Purchases and Supplier return documents, you wish to hand to customers (debtors) or suppliers (creditors) when you sell, or quote, or order and purchase, physical stock items and services set up in your stock item code file.

g) Stock information - The option allows you to define the units of stock you sell and the selling price descriptions and to set the Cost of sales parameters. This option should only be used if you use stock and/or wish to generate documents (Invoices, Credit notes, Quotes, Orders, Purchases and Supplier returns).

9. After the last setup screen (i.e. Stock information) is closed, the Next button will change to the Finish button.



10. Click on the Finish button. The new Set of Books will automatically be opened automatically and now ready to work in.

Before you begin processing transactions, make sure to create your general ledger accounts, bank accounts, tax accounts, debtor accounts, creditor accounts, and review or modify your settings and parameters to ensure accuracy and efficiency.

Steps after creating the Set of Books (Advanced)

Deactivate / Activate the Bank import plugin

By default, the Bank import plugin setting activated.

The "*Default bank reconciliation*" option (Setup → System parameters on Setup ribbon) is not selected.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bankimport plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the

payments to the right invoices.

Needs to be activated on the Setup ribbon, select Setup → System Parameters.

If you do not intend to wish to use the Bank import plugin at this stage, you need to turn the Bank import plugin off (Tick (select) the "*Default bank reconciliation*" field in Setup → System parameters (Setup ribbon).

The Bank import plugin can be activated as it is included in the osFinancials5/TurboCASH5 subscription.

If the Bank import plugin is not activated, separate Payments and Receipt batches will be created on the Bank tab when you create (add) Bank accounts in Setup → Accounts (Setup ribbon).

Customise labels for Document types

You may need to customise labels and fix records.

Change the descriptions on the Types tab on Tools → Customise languages (Setup ribbon). If you have a different language than English, you need to translate the descriptions for your language or specific requirements.

Document types5





"*Goods Returned*" - change to Supplier return to be consistent with the other labels in the language file.



The Document type (i.e. Invoice, Credit note, Quote, Purchase, Supplier return or Order) is stored and edited 1n the Tools → Customize language (Setup ribbon).

It should print the Document type (i.e. Invoice, Credit note, Quote, Purchase, Supplier return or Order) as this is more correct for the recipient of these documents.

If you need to print documents using the document layout files supporting one (1) Layout file for all document types), it is recommended that the Document types are edited and/or translated to the singular

in the Types tab Tools → Customize language menu (Setup ribbon).

Change Edit Groups

Change the reporting group names (descriptions) of the Groups (Setup ribbon).

You may also add groups for reporting groups, if necessary.



The name must not already exist and may not be longer than 50 characters. This name will help you to identify the Set of Books on your system. You will need to select this name whenever you need to open the Set of Books or perform some other functions on the Set of Books.

The following groups are not included if the Set of Books was created using Create Set of Books (Advanced) option:

- Projects - You may create groups for Projects. These Projects may be activated in batches and documents. Once the batches and/or documents are posted (updated to the ledger), you may generate various reports for each Projects on the Sidebar of the Default menu.
- Cost centre 1 and/or Cost centre 2 -
- Languages - *Multi-Language accounts*

Multi-Language accounts - Manual - Shop - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

Add missing Groups and Paper types in the Types table

To add missing groups:

If you intend to use Projects, Cost centres and/or Multi-language Set of Books, you need to add these Groups manually:

1. Activate the SQLBrowser plugin in Tools → Activate plugins (Setup ribbon)
2. Launch the SQLBrowser plug-in Plugins → Tools → SQLBrowser (Setup ribbon).
3. Select the "*TYPES*" table.
4. Right-click and select "*Open*" on the context menu.



5. Select the last record WTYPEID - 93 in the TYPES table. Insert or Add a new record (you may also use the down arrow on your keyboard).

6. Add Groups - Optional - If you are planning to use any of the following features in osFinancials5/TurboCASH5, you may add the groups, as required. To do this, type the following records and type 2 in the WTYPEPARENT column:

    § 1000 - Projects

    § 1002 - Cost centre 1

    § 1003 - Cost centre 2

    § 1004 - Languages

7. Add Paper types - Type the following records and type 5 in the WTYPEPARENT column:

    § 55 - Till slip

    § 56 - New plain

The number of records in the "TYPES" table is 55 records. After adding the 4 records for the groups and the 2 records for the paper types, the number of records in the "TYPES" table should be 61 records.

8. Close the SQLBrowser

SQLBrowser - Manual - Shop - Licence : Once-off -

Activate the SQLBrowser plug-in Tools → Activate Plugins (select Tools → SQLBrowser and click Activate plugin) on the Setup ribbon.

The groups will be added on Setup → Groups



Before you can start any processing, you need to set up your general ledger accounts, bank account, tax accounts, accounts receivable (debtor accounts), accounts payable (creditor accounts), etc. create and check or change your settings and parameters. This should not take much time, but can save you a lot of extra work and frustration, as the key to success in your processing and reports is in setting up the osFinancials5/TurboCASH5 program.

Customise your own Set of Books (Advanced)? - Set Books - Properties

Length of description fields and the basic control accounts

The basic features of your customized Set of Books with the "*Customise your own Set of Books (Advanced)?*" -option should be as follows:

1. Length of description fields - The default length of description fields for accounts is 64 characters and groups are up to 30 characters for group names. The group descriptions are more than 50 characters.
2. Account codes - Character length and the default control accounts. Depending on your choice of the number of digits for account codes, during the creation of your own Set of Books, the number of characters for the control accounts and the debtor accounts as well as the creditor accounts will be as follows:

Number of digits *Account code*	*Retained earnings*	*Debtors control*	*Creditors control*	*Number of account code digits - Debtor accounts*	*Number of account code digits - Creditor accounts*
3X3-DIGITS	*G510-000*	*G700-000*	*G900-000*	*D + 5-characters D00001*	*C + 5-characters C00000*
4X3-DIGITS	*G3100-000*	*G1100-000*	*G2000-000*	*D + 6-characters D000001*	*C + 6-characters C000000*
5X3-DIGITS	*G31000-000*	*G11000-000*	*G20000-000*	*D + 7-characters D0000001*	*C+ 7-characters C0000000*
6X3-DIGITS	*G310000-000*	*G110000-000*	*G200000-000*	*D + 8-characters D00000001*	*C + 8-characters C00000000*
7X3-DIGITS	*G3100000-000*	*G1100000-000*	*G2000000-000*	*D + 9-characters D000000001*	*C + 9-characters - C000000000*
8X3-DIGITS	*G31000000-000*	*G11000000-000*	*G20000000-000*	*D + 10-characters - D0000000001*	*C + 10-characters - C0000000000*

Customise your own Set of Books - Configure Set of Books

Language settings

If you have created your custom Set of Books in "*English*" as the default language, the osFinancials5/TurboCASH5 interface will be displayed in "*English*". If the osFinancials5/TurboCASH5 interface is displayed in the language of your choice, you can select a different available language in the "*Switch language*" (Start ribbon).

Set the default language for your Set Books - You can choose your language and country in Setup → Access control. When you reopen your Set of Books, the language in the osFinancials interface, reports, etc. will be displayed in your selected language.

Customise your own language

If you want to customise your own language, you can select your language in Tools → Customise language (Setup ribbon).

It is strongly recommended that the label, which is edited or entered, is not longer than the default "English" labels' length. If your label is too long, it may cause some options in the program not to function or display properly. Do not use the Delete button to remove any of the existing edited labels.

Care must be taken to ensure that existing labels or descriptions in the main language, i.e. "English" not be modified. You must create a copy of the "English" or other selected language and rename it with a new name. You may use your own language file to edit.

If you decide to adapt a selected language file for your own specific industry or specific needs and want to modify these labels accordingly, it is important that you use a copy of the language file. This will prevent your language file from being overwritten when you reinstall osFinancials5/TurboCASH5, or install osFinancials update download files, or install osFinancials updates through the Help menu.

Customise the "TYPES"-tab

The entries on the "*Types*"-tab in Tools → Customise language (Setup ribbon) is database specific and will update the "*TYPES*" table in your Set of Books. You may edit, translate or change the descriptions as necessary.

- Reporting groups - The default descriptions for the reporting groups is available in English as "*Account Reporting Group1 Name*", etc, , After adding the 4 reporting groups for Projects, Cost centre 1, Cost centre 2 and Languages, these 16 reporting groups, you may change, edit, translate these descriptions on the "*Types*"-tab in Tools → Customise language (Setup

ribbon). These reporting group names may also be reviewed, changes, edited, translated in Setup → Groups according to your specific requirements for your country language or industry. The common reporting group names in most databases, is "Account group 1, Account group 2, Debtor group 1, Debtor group 2, Creditor group 1, Creditor group 2, Stock group 1, Stock group 2, Document group 1, Document group 2, Payment types, Salespersons, Projects, Cost centre 1, Cost centre 2 and Languages".

- Document types - The default descriptions for the standard 6 document types is "*Invoice", "Credit note", "Purchase", "Goods Returned*", "*Quote",* and "*Order*" . You may change, edit, translate the descriptions for the standard 6 document types for sales documents (Invoices, Credit notes and Quotes and for purchase documents (Purchases, Supplier returns and Orders) to match your specific requirements for your country language, tax regime or industry in the Types tab.

  In your language file, you may search and edit / translate the language labels for each of these document types. These matching descriptions are also displayed in the "*English*" language file. If you want to change or edit the labels according to your personal needs, you can make a copy of the "*English*" language file and feel free to translate the language labels for the document types according to your specific requirements, preferences and industry. You then also search for and modify and adapt the language labels for each of these document types in your own language file.

- Tax terminology - Tax account is the default description for VAT/GST/Sales tax/Consumption tax in the Types tab. You may change this description for your country language, tax regime or industry. In your language file, you may search and edit / translate the language labels for the for the tax terminology.

Customise the "Rest"-tab

The Customize language - Rest tab entries on this tab is database specific.

Change descriptions of the "*Description of Zero account*" and "*Group empty account*". The 2 change buttons only saves 1 description. Work around change both to "*Empty*".

General ledger accounts

Accounts Setup → Accounts - Only the 3 control accounts (i.e. Debtors control + Creditors control + Retained earnings) accounts in the Chart of Accounts is included in the Chart of Accounts.

You cannot delete these 3 control accounts. An error message will be displayed:

"You cannot delete a control account!"

You can edit the account code and description for each of these 3 control accounts, if necessary.

Depending on your choice of the number of digits for account codes, during the creation of your own Set of Books, the number of characters for the control accounts will be as follows:

Number of digits Account code	*Retained earnings*	*Debtors control*	*Creditors control*
3X3-DIGITS	*G510-000*	*G700-000*	*G900-000*
4X3-DIGITS	*G3100-000*	*G1100-000*	*G2000-000*
5X3-DIGITS	*G31000-000*	*G11000-000*	*G20000-000*
6X3-DIGITS	*G310000-000*	*G110000-000*	*G200000-000*
7X3-DIGITS	*G3100000-000*	*G1100000-000*	*G2000000-000*
8X3-DIGITS	*G31000000-000*	*G11000000-000*	*G20000000-000*

Control accounts - You can edit the account code and account description for each of these 3 control accounts.

It is important to note that you need to keep in mind that these control accounts need to be linked to account groups and financial categories:

Control account name	*Financial category*	*Account groups*
Retained earnings	*Capital*	*Equity / Capital*
Debtors control	*Assets*	*Current assets*
Creditors control	*Liabilities*	*Current liabilities*

If you import general ledger accounts from a Tab delimited file, you may:

- Change the account codes and descriptions to meet your specific requirements and needs. In the case of accounts, which contains sub-accounts, you cannot change the sub-accounts account codes. You first need to delete the sub-accounts and rename the account codes and account descriptions and recreate sub-accounts where necessary.

- Review your imported ledger accounts descriptions. You may use longer account descriptions (longer than the default 35-characters or 64-characters) , where necessary.
- Disabled (inactive) accounts imported - review and decide to keep these disabled (inactive) accounts or delete them if not required.
- Tax (VAT/GST/Sales tax) accounts - The first sub-account (tax code) may not include the Tax tab and Tax percentage - You need to delete and recreate the tax account (tax code) as a Tax account. Zero-rated Tax codes. You need to confirm the percentage.
- If Account groups 1 and / or Account group 2 is imported, these account groups may not be linked to the 5 financial categories. You may need to link these account groups to the 5 financial categories.

Imported or copied text in osFinancials screens from external files - Account / Group descriptions in Accounts description lines in batches

When importing or copying text for account. group descriptions or any other screens, or forms, the fields from external programs such as spreadsheet, word documents, etc. the hyphenation character "–" may be displayed as a pipe character " | " in lookups and some screens or as " " in some screens and in reports, document layout files, etc.

For example, Motor vehicles Net value if copied or imported into Setup - Accounts as Motor vehicles – Net value (with the hyphenation format) it will be displayed as Motor vehicles Net value on some screens and in reports and as Motor vehicles | Net value on lookup screens.

You need to use the dash sign "-" to be displayed correctly.

Solution:

To ensure hyphens display correctly in osFinancials5 / TurboCASH, use the standard dash character ("-") instead of the hyphenation character when copying or importing text from external files.

Debtor / Creditor accounts

Depending on your choice of the number of digits for account codes, during the creation of your own Set of Books, the number of digits for the account codes of debtor accounts and creditor accounts will be as follows:

Number of digits Account code	*Number of account code digits - Debtor accounts*	*Number of account code digits - Creditor accounts*
3X3-DIGITS	*D + 5-characters D00001*	*C + 5-characters C00000*
4X3-DIGITS	*D + 6-characters D000001*	*C + 6-characters C000000*

5X3-DIGITS	*D + 7-characters D0000001*	*C+ 7-characters C0000000*
6X3-DIGITS	*D + 8-characters D00000001*	*C + 8-characters C00000000*
7X3-DIGITS	*D + 9-characters D000000001*	*C + 9-characters - C000000000*
8X3-DIGITS	*D + 10-characters - D0000000001*	*C + 10-characters - C0000000000*

When creating or adding Debtor accounts and Creditor accounts, it is important that you use a different prefix for the account codes:

The first Debtor code (e.g. D00001, etc.), will automatically be generated. It is important to prefix Debtor codes with a unique prefix. In this documentation, the accounts is prefixed as follows:

- *Debtor code = 1*
- *Creditor code = 2*

The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens on "Batch entry" screens.

Company information

Only "*osFinancials5.1.0.127*" / TurboCASH5.1.0.227 (osFinancials5/TurboCASH5 and the version number) will be displayed in the title bar, unless you have already entered your company name in the Company info screen during the creation of the Set of Books. Review and enter the name and contact details as well as the relevant registration numbers of your business in the Setup → Company info (Setup ribbon).

Financial year and accounting periods

The default start of the financial year is on the first day of the month in which you created your set of books. For example, if you created your Set of Books on 20 March 2024, the start of the financial year will automatically be set as "*1 March 2024*". You can change this in Setup → Reporting dates for the beginning of your financial year and set the accounting periods.
If you selected a different language than the English languages, for example, "*Afrikaans*" as the language to create your Set of Books in, the months of the year should already be displayed in "*Afrikaans*". You may need to review and edit or translate the months of your financial year, if necessary.

Batches (Journals)

No batch types (journal types) are included in your customised Set Books. You will need to add your own

batch types (journal types) in Setup → Batch types (Setup ribbon) to meet your specific needs and requirements. The basic journals, are the "*Sales journal*", "*Purchase journal*" and the "*General journal*".

Receipts journals and Payments journals for Bank accounts and Petty cash accounts

When you add or create a Bank account and Petty cash account, the Receipts journals and Payments journals will be created and added and linked to each Bank account and Petty cash account.

The "*Sales journal*", should be linked to the Invoices and Credit notes document types in Documents setup. This will update the transactions generated with the Invoices and Credit notes in the Sales journal to the ledger.

The "*Purchase journal*", should be linked to the Purchases and Supplier returns document types in the Documents setup. This will update the transactions generated with the Purchases and Supplier returns in the Purchase journal to the general ledger.

You can use any number of journal types as you deem necessary to group and process your transactions. In addition to the general journal, you may add specific journals for; cost of sales, adjustments, depreciation, payroll, etc. to accommodate your specific needs and requirements.

Documents setup

The defaults settings in the Setup → Documents setup is as follows:

1. Global settings - Documents setup
    - Layout file point-of-sale : "*DefaultA4*" is the default setting and is not available in the " ... *\plug_ins\reports\DOCUMENTS\DOCUMENTS*" folder. You may change the default layout file to "*POS - STARTSP100*".
    - Append notes below item: By default this option is selected. The default sequence in which the document lines will be displayed on document entry forms and printed in document layout files, is Item/Remark/Comment. If you deselect this option, the sequence in which the document lines will be displayed on document entry forms and printed in document layout files, will be Comment, Item, Remark.
    - Auto-post documents on print: By default this option is not selected. This means that you need to manually launch the Update ledger option to post or update documents to the ledger.
2. Settings for specific document types. The basic configuration for each document type, is as follows:

Field	*Sales documents*			*Purchase documents*		
Document	*Invoice*	*Credit note*	*Quote*	*Purchase*	*Purchase*	*Orders*

type					*returns*	
Next Document number	*I0N000001*	*C0000001*	*Q0000001*	*P0000001*	*R0000001*	*OR000001*
Batch type						
Layout file						
Layout file 2	-	-	-	-	-	-
Heading	*Tax Invoice no.*	*Credit note no.*	*Quote No*	*GRV No*	*Goods Returned No*	*Order No*
Message 1/2/3	-	-	-	-	-	-

Customise / translate notes:

You may need to customise, change and translate the following to suit your specific preferences and needs:

- Next Document number - This is an 8-character alphanumeric field. You may use prefixes for each document type. Prefixes will make it easier to identify the document type in searches and filters, on reports and on exported data in spreadsheets. The character prefixes for each document number are in English. You can change the document numbers for each type of document to suit your specific preferences and needs.
- Batch types - No batch types or journals are available at this stage. You will need to select the default journals in which the documents will be posted (updated) to the ledger. If you have already created journals earlier during the creation of your advanced Set of Books, you can select the "*Sales journal*" for Invoices and Credit notes and the "*Purchase journal*" for Purchases and Supplier returns. If not, you will first need to create the journal types in Setup → Batch types (Setup ribbon) such as "*Sales journal*" and "*Purchase journal*". Journals do not apply to Quotes and Orders.
- Layout file - You can select "*Layout file*" at this stage for all document types. The "Layout file" is one standard generic layout file that applies to all document types (Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders) and is translated via the language files. The layout file selected is a global setting. You may also select custom or other layout files as defaults for specific debtor or creditor accounts.
- Layout file 2 - This option is not selected. You may select other layout files or the delivery note to

print after the Layout file.

- Headings - You may change the headings of each document headings to match your country language, tax regime or industry.
- Messages - No messages is available at this stage. You may enter up to 3 lines as a global message (for each document type) that will be displayed on the "*Message*" fields of the document entry screens and printed on document layout files for each document type. Custom messages may be set as default for specific debtor or creditor accounts.
- Statement message - You can enter up to 3 lines of statement messages in the Statement setup tab. This is a global standard message that will appear on all debtor account statements.

Additional settings for documents

Post / Confirm and Delete buttons on Documents grid - By default, only the New, Edit and Print buttons are available on the Documents grid screen's sidebar. You may add the Posting and Delete buttons underneath the Print button. To add the Posting and Delete buttons to the Document grid screen, select (tick) the "*Document posting*" field on the Documents tab in Setup → Access control.

Stock items / Inventory items

Before you add or import your stock items / inventory items / products you may need to configure some important basic settings such as Cost of sales, Create tax classes / account classes and Selling prices.

At this point, your chart of accounts (general ledger accounts) should have already been finalised.

Activate Cost of Sales

By default cost of sales is not activated. You need to configure cost of sales as follows:

1. Cost of Sales journal - Create a cost of sales batch (journal) type (Setup → Batch types) to update the transactions for cost of sales to the ledger when you post documents.
2. Cost of sales settings (Setup → Stock information) - Select the following:
    - Create cost of sales - To activate cost of sales, select (tick) the "*Create cost of sales*" tick box.
    - Cost of sales batch - Select the Cost of sales batch (journal) in which the cost of sales transactions will be posted.
    - Use "*Average cost*" or "*Latest cost*" option.

> *The method you use to calculate the value of your stock is crucial for determining its impact on your profit and loss figures. It is important to consider whether to use the "average cost" or the "latest cost" method.*

If you are unsure which method to use, it is recommended that you seek guidance from your accountant.

Create tax classes / account classes

At this point, your chart of accounts (general ledger accounts) should have already been finalised.

You need to link each stock item / inventory item / product to the applicable ledger accounts (i.e. Input tax, Output tax, Sales account, Cost of sales account and Stock control account).

Tax classes may be set and linked to each category of tax and various tax rates such as Output tax, Input tax - Standard rate, Input tax - Capital goods, Zero rated goods, Exempt supplies applicable to the stock items / inventory items / products in your country and tax jurisdiction, etc.

Tax classes is defined and managed in the Tax classes tab in Setup → Stock information. When you create add or import your stock items / inventory items / products you may select a pre-configured Tax class to automatically link the 5 accounts (i.e. Input tax, Output tax, Sales account, Cost of sales account and Stock control account) applicable to the stock item / inventory item / product.

Selling prices

osFinancials5/TurboCASH5 supports up to 3 selling prices (i.e. Selling price 1, Selling price 2 and Selling price 3). You may change the descriptions of these selling prices on the "Selling price descriptions" section of the Default tab of Setup → Stock information to suit your specific requirements and set one of these Selling prices as the default Selling price (global setting) for your Set of Books.

In addition to this, you may set one of these Selling prices as the default Selling price on the Accounting information tab for specific debtor (customer / client) accounts.

Price agreement plugin - Manual - Shop - Licence : Once-off -

In addition to the standard 3 selling prices in odFinancials, Price agreement plugin, allows you to set up to five (5) levels of quantity discounts that can be applied to specific debtors or groups of debtors. Additionally, you can set a special price for individual debtors per product. These prices will overrule the default Selling price 1 / 2 / 3 and can be set per debtor (customer / client). The price agreement may also be activated for creditor (supplier / vendor) accounts.

Units of stock

Add and define the units such as each, hours, etc. for your stock items / inventory / products. You may add these descriptions on the Units tab in Setup → Stock information.

Reporting groups - Stock group 1 / Stock group 2

In osFinancials5/TurboCASH5, you have the option to set up to 2 reporting groups for your stock items / inventory items / products, allowing you to categorise search, filter and report on your products more effectively. These reporting groups provide a way to organize and analyse your inventory based on specific criteria.

You may add these Stock groups in Setup → Groups can be linked to each stock item (inventory item / product).

Set the Calendar as default

You have the option to activate the Calendar to be launched instead of the Welcome screen whenever you open a Set of Books, This means that the Calendar will be automatically displayed as the default screen.

Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with a Help Authoring Tool

Converting Sets of Books

Add Sets of Books

Already have Set of Books

TurboCASH4, TurboCASH5 (4.0.0.969), osFinancials4 (4.0.0.1093) Sets of Books do not need to be converted to osFinancials5/TurboCASH5.

You may copy the Sets of Books using File Explorer to the "*books*" directory of your osFinancials5/TurboCASH5 installation.

You may also Restore a Set of Books from a valid Backup file in osFinancials5/TurboCASH5.

New Set of Books

If you are new to osFinancials5/TurboCASH5, you may download an existing template for your country and language from the Let osFinancials help you to create a Set of Books - Download option. See a list of available Firebird Sets of Books and linked languages available as a free download.

New to Accounting and osFinancials

Download Tutorials - Basic Tutorials is available from the Let osFinancials help you to create a Set of Books - Download option.

Conversion

If you need to convert your data from other accounting packages, the following options is available on the osFinancials Webshop:

- *Basic conversion* -

- *Extensive conversion* -

- *Convert Sets of Books to Microsoft SQL Server database.*

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Save as

The "*Save as*" option in osFinancials5/TurboCASH5 allows you to save a Set of Books to any directory or folder on your system. To use this option, you must have a Set of Books open and select the option to save the entire Set of Books with a different name in the directory of your choice. This allows you to create a copy of the Set of Books with a new name in a different location without affecting the original data.

The "Save as" screen will also be launched if you download one of the free Sets of Books (templates) (using the option, Let osFinancials help you to create a Set of Books / Let TurboCASH5 help you to create a Set of Books)

After downloading a Set of Books, the Set of Books (template) will automatically open in the language associated with the country and language.

See a list of the Sets of Books available for a download.

To save a Set of Books as:

1. On the Start ribbon, Open the Set of Books which you need to save under a new name.

If you already have an open Set of Books, please make sure that it is the actual Set of Books you wish to save. If not, close the Set of Books and open the Set of Books you wish to save.

2. On the Start ribbon, select Save as (Ctrl + S). The "*Save as*" screen is displayed:



3. The default or installation Directory, in which osFinancials5/TurboCASH5 is installed, will be displayed.

If you wish to Save the Set of Books in another Directory or location on your system, you may click on the Folder icon on the right hand side of the Directory field. The "Browse for Folder" screen will be displayed on which you may then select a valid directory or folder on your system in which you wish to Save the Set of Books.

4. Enter a name in which you wish to save your Set of Books. The name for the Set of Books must not already exist.

5. Click on the Save button. The full Set of Books will be saved into the specific directory with the specified name. When this process is finished, an information message will be displayed.

"Set of Books copied"

6. Click on the OK button to close (exit) the "*Save as*" screen.

7. The source Set of Books will be opened.

To open the Saved Set of Books, click on Open (Start ribbon) and select the new saved (copied) Set of Books can then be selected from the list.

Created with the Standard Edition of HelpNDoc: Free help authoring environment

Data integrity check

This option allows you to run a check on the integrity of your data and generate a corresponding report. By selecting this option, you can verify that your data is accurate and free of errors that could cause issues in your Set of Books. Once the check is complete, you can print the "*Data integrity check report*" to review the results and take any necessary corrective action.

The Data integrity check should be performed on a regular basis. It is recommended that you perform this check at regular intervals and after performing major changes to your Set of Books. It is good practice to perform a Data integrity check on your Set of Books before you make a Backup and after you have restored from a Set of Books.

Performing a Data integrity check on a regular basis is essential for maintaining the accuracy and reliability of your financial records. It is recommended that you perform this check at regular intervals and after making any major changes to your Set of Books.

It is also good practice to perform a Data integrity check on your Set of Books before making a Backup, as well as after restoring from a Set of Books.

By regularly checking your data for integrity issues, you can help ensure that your financial records remain accurate and up-to-date.

If you are operating in a multi-user environment (i.e. in a networked environment and other users are using the same Set of Books as you are) then ALL users need to exit the Set of Books before the Data integrity check is started.

Run the data integrity check

To perform a data integrity check:

1. On the Setup ribbon, select Tools → Data integrity check.



2. Select one of the available options:

    a) Select a Set of Books by clicking on the From List down arrow (drop-down list) and select an available Set of Books.

> *If the Set of Books on which you wish to perform the data integrity check is open on the system, the Data integrity check will be performed for that Set of Books.*
>
> *If no Set of Books is open on the system, the Data integrity check will be performed for the Set of Books that was open before the Data integrity check was initiated, unless another Set of Books is selected.*
>
> *The full path or directory and name of the selected Set of Books on which the Data integrity check is to be performed, if the Check button is clicked on, will be displayed directly under the Data integrity check title bar.*

b) Select the type of function, the data integrity check has to perform. It is recommended that in most cases, all of these functions should be selected (with a tick).

3. Click on the Check button and the process will be performed. The word *Finished* will be displayed next to each function when the process for that function is completed. When the whole process is completed, you may click on the Print button to print the Data integrity check report.

4. Click on the Close button.

5. Study the report to determine if there is any data corruption or errors.

Check for any errors on the report. If there are any errors, see if you can fix these errors. If these errors cannot be fixed, the Set of Books may have to be restored from your last backup disks. You may have to re-enter some data from the last backup to the last transaction entered before the problem/s arose.

View data integrity check reports

The Data integrity check report consists of the following five (5) basic sections:

1. Files check - List all the tables in the database (Set of Books).

2. Accounts check - This specifies the number of Account master files created for each Account type (General ledger, Debtors, Creditors, Bank and Tax accounts) in Setup → Accounts (Setup ribbon). The number of Accounts for Debtors indicates the number of Debtor accounts in the Debtors ledger and the number of Accounts for Creditors indicates the number of Creditor accounts in the Creditors ledger. The total of all account types (ledger, bank, tax, debtor and creditor) in the Set of Books will be displayed.

3. Trial balance check - This will list the Accounting Periods and the Debit Totals and Credit Totals and Balances for each period. If there are any balances (i.e. the Debit and Credit Totals for an Accounting period do not balance), it indicates that the data may be corrupt for the specific accounting period in which the Balance is displayed.

4. Debtors / Creditor check (Control accounts check) - This will indicate the balances for the Full Amount, Control account and the Outstanding Amount for the Debtors and Creditors. These three amounts must be in balance and must balance with the Debtor's control account or the Creditor's control account in the Balance sheet or Trial balance.

5. Unposted batches check - This will only be displayed if there are any documents and batches or journals which have not yet been posted to the ledger. If you have set any users (Setup → Access control on the Setup ribbon), the name of the user will also be displayed.

If the differences or corruption is not fixed, you may need to Restore the Set of Books from a previous backup. It is advisable not to continue entering transactions until the current Set of Books is repaired.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Backup / Restore Sets of Books

What is a Backup file in osFinancials?

A backup file is a copy of data in a Set of Books in osFinancials5/TurboCASH5 that is stored separately in case the original data is lost or becomes inaccessible. The backup file is essentially a snapshot of the original data at a particular point in time, and it can be used to restore the data in a Set of Books in case of data loss, corruption, or system failure.

They are typically stored on an external device or in a remote location to protect against disasters like fire, theft, or hardware failure that could damage or destroy the original data.

Backup files can be created manually or automatically on a scheduled basis. Manual backups require the user to initiate the backup process, while automatic backups are configured to run automatically at regular intervals.

In summary, backup files are essential for ensuring data integrity and availability in case of data loss or system failure. They provide a way to recover data and restore system functionality quickly and efficiently.

Options to store backup files

Backup files can be stored in a variety of locations, depending on your needs and preferences. Here are some common options:

1. External hard drive: You can store backup files on an external hard drive that is connected to your computer or server. This provides a physical backup that is easily accessible and can be quickly restored if needed.

2. Cloud storage: You can store backup files in cloud storage services such as Google Drive, Dropbox, or OneDrive. This provides an off-site backup that is accessible from anywhere with an internet connection and can protect against physical disasters like fire or theft.

3. Network-attached storage (NAS): You can store backup files on a NAS device that is connected to your network. This provides a centralized backup solution that can be easily accessed by multiple devices.

4. Tape backup: You can store backup files on magnetic tapes that are stored in a secure location. This is a traditional backup method that is still used in some organizations because of its durability and reliability.

5. USB drive: You can store backup files on a USB drive that is stored in a secure location. This is a portable backup solution that can be easily transported and used to restore data on different devices.

6. Optical media: Optical media such as CDs, DVDs, and Blu-ray discs can be used to store backup files.

Overall, the choice of storage location for backup files depends on your needs for accessibility, security, and reliability. It is recommended to store backup files in at least two separate locations to ensure redundancy and protect against data loss.

Options to Backup or Copy a Set of Books in osFinancials

In addition to the Backup/Restore feature, you can create exact copies of existing Sets of Books or templates that are installed in yourosFinancials5/TurboCASH5 …/books directory.

The following options are available in osFinancials5/TurboCASH5 for backing up or copying a Set of Books:

1. Backup / Restore: This option is available on the Start ribbon. It allows you to create backups of your Set of Books and restore them when needed. You can select the backup option to create a backup file and choose the restore option to restore a previously created backup.

2. Save as: This option is also available on the Start ribbon. It enables you to create a copy of an existing Set of Books with a new name and/or a new location. This is useful when you want to create a duplicate or backup of a Set of Books.

3. Create Set of Books: This option is found in the "*Copy an existing Set of Books?*" section of the "*Creation wizard*" on the Start ribbon. It allows you to create a new Set of Books based on an existing one. You can select an existing Set of Books and provide a new name and/or location for the copied Set of Books.

4. Tools → Global processes → Copy from a Set of Books: This menu-option is available on the Setup ribbon. It provides a feature for copying a Set of Books from an existing one. You can select the source Set of Books and specify the name and/or location for the copied Set of Books.

These options allow you to create backups or copies of Sets of Books in osFinancials5/TurboCASH5, either by directly saving them as new files or by using existing Sets of Books as templates. Each option provides

flexibility in terms of naming, location, and source for the copied Set of Books.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Backup a Set of Books

The Backup / Restore feature allows you to create a backup of your data in a Set of Books onto a disk or hard drive, or other selected location, in a compressed tcBackup.zip file. There are two (2) options for creating a backup file:

1. Normal backup, which includes all files in the Set of Books folder (including images and PDFs),
2. Small backup (books), which only includes the database file (e.g. books.fdb) and excludes all other files.

Backup files are created to restore a Set of Books to the exact state it was in when the backup file was created. Backups are essentially copies of your data that you create on a regular basis to ensure that you have a recent version of your data in case of any issues or errors.

As a general rule, it's a good practice to back up your data often, preferably upon closing the program. While backing up to your hard disk is also a good practice, it's best to store your backups on a different device than your computer to protect against data loss in case of a hard drive failure or a system failure.

You will need backups:

- *In case of file corruption, hardware failures and other errors.*
- *Send backup files via e-mail*

It's also a good practice to complete a backup in the following instances:

- Prior to performing any major processes, such as Delete Set of Books on the Start ribbon or performing global processes like (Clear/Reset or Do year end., Reverse posted batches / documents) on the Setup ribbon.
- Old data on your previous version of osFinancials5/TurboCASH5 or other accounting package prior to conversion to osFinancials5/TurboCASH5.
- Import data from exported files - If errors or inconsistencies occur after importing data from an exported file, you may need to restore the Set of Books.

W Depending on your volume of work, it's recommended to create backups. The following is recommended:

- § 2 - 3 sets daily re-used weekly or every 3rd to 4th day.
- § 2 weekly sets - re-used every 3rd week.
- § 12 Monthly sets - done at the end of each month, and re-used each year.
- § 1 set prior to and after year-end that is kept permanently.

To restore your data, you'll need the same backup disks or backup files on your hard drive. Without regular backups, you may have to re-enter thousands of transactions and other important information.

To create a Backup file:

1. On the Start ribbon, select Backup / Restore. If a Set of Books is open on your system, osFinancials5/TurboCASH5 will automatically close the Set of Books and the "*Backup Set of Books*" screen is displayed:



2. Select the Backup option, if not already selected.

If no Set of Books are opened, the Restore button is automatically selected.

If a Set of Books are opened, the Backup button is automatically selected.

3. Select the Name of the Set of Books you wish to Backup.

4. You may over type the Backup file name with a name of your own.

The date and time of your operating system is automatically inserted in the file name (e.g. MY-BOOKS202204050538) after the default file name.

(In this example, the date and time format is YYYYMMDD followed by the Hour and Minutes). The format may differ if your operating system's short date style or format is set different).

5. Select the folder (drive, etc.) to Backup to.

6. If you need to create a small backup, tick the "*Small backup (books)*" option.

If you wish to e-mail the backup, you may select the "Small backup (books)" option to create a backup of your Set of Books database in a single file only (e.g. books.fdb - for the firebird database).

If this option is selected, no images or other files linked to your Set of Books will not be included in your backup. This will reduce the size of your backup file.

7. Click on the Backup button to start the backup process. While the Backup process is running, the files are backed up from and added on your backup disk or location on your hard drive or network drive will be displayed. When the backup process is completed, an information screen will be displayed.

```
The Backup process is completed!
```

The information in the *Backup* process will be displayed, for example:

```
Starting backup...
  100%
12 Files compressed
Backup completed...
```

8. Click on the OK button and click on the Close button on the "*Backup Set of Books*" screen. You may also press the Esc key on your keyboard.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Backup a Set of Books to E-mail

To use the "*E-mail backup*" option to send a Set of Books to email, you need to ensure that your computer system is properly set up and that you have an active Internet account with your Internet Service Provider.

If you select the "*E-mail backup*" option on the "*Backup Set of Books*" screen in osFinancials5/TurboCASH5, a backup file of your Set of Books will be created automatically and attached to your system's default email application.

From there, you can compose an email message, add recipients, and send the email with the backup file attached.

It's important to ensure that the backup file is securely transmitted and that the recipients are authorized to access the data. You may also want to consider encrypting the backup file or using a secure email service to protect the data during transmission.

If your system is not configured for Microsoft Outlook, the following message will be displayed:

> "You need to create a Microsoft Outlook profile. In Microsoft Windows, go to the Control Panel and open Mail. Click Show Profiles, and then click Add."

Click OK and configure Microsoft Outlook.

If your system is not configured for Microsoft Outlook, you may create the backup file and attach it to your e-mail message. If you do not have Microsoft Outlook configured on your system, you can still create a backup file and attach it manually to your preferred email application.

To send a backup file via e-mail:

1. Select the "*E-mail backup*" option on the Backup Set of Books screen.

   You can choose the "Small backup (books)" option to create a backup of your Set of Books database as a single file, such as "books.fdb" for the Firebird database type. However, if you select this option, any images or other files that are linked to your Set of Books will not be included in the backup. This will help to reduce the size of your backup file.

2. When the backup process is finished, your e-mail program will automatically be launched.

3. The e-mail address of osFinancials5/TurboCASH5 will automatically be entered in this field. Should you wish to change it to a different e-mail address, (e.g. that of your auditor or consultant), you may enter

a valid e-mail address to that field. The email address of osFinancials5/TurboCASH5 will be automatically added to this field.

However, if you want to use a different email address, such as that of your auditor or consultant, you can replace the osFinancials5/TurboCASH5 email address with the desired email address in the "To" field provided. Just make sure to enter a valid, trusted and correct recipient's email address.



4. Add a description to the subject if you wish (e.g. your company name).

5. The file is automatically attached to the e-mail message.

You can attach additional documents to the email message. However, please note that your Internet Service Provider may have a limit on the size of your email message, including attachments, typically around 1.2MB. If your message exceeds this limit, it may not be delivered to the recipient and instead may be returned to you.

6. Enter your message.

7. Click on the Send button.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Restore a Set of Books

option allows you to restore data for a specific Set of Books from a valid backup file located on your hard drive or in a valid folder on your system. This option also decompresses or unzips the files contained in the backup file.

To restore a Set of Books from a backup, a valid backup file (tcBackup.zip) must exist. If your data becomes corrupt for any reason, restoring from backup can fix the issue. However, you will need to re-enter all the data that was entered after the date of the last backup.

Regularly backing up your data is important as it can save a lot of work in the event of data corruption or loss. If you don't make regular backups, you may have to re-enter thousands of transactions and information related to the general ledger, debtor, creditor, and stock.

It's also important to keep a record of your backup files and label them to prevent restoring a Set of Books from an incorrect backup file. Keeping a record of which data is backed up and which is not can also prevent you from re-entering data that's already on your backup files.

To Restore a Set of Books:

1. On the Start ribbon, select Backup / Restore. If a Set of Books is open on your system, the Set of Books will automatically be closed and the Backup Set of Books screen is displayed:



2. Select the Restore option. The "*Backup Set of Books*" screen will change to the "*Restore Set of Books*" screen.

3. Select the Name of the Set of Books you wish to restore.

4. Select the folder (drive, etc.) to Restore from.

> *You can also select the folder on your hard drive or network drive where your backup data is stored by browsing for a folder. To do this, click on the icon located on the right-hand side of the "Restore to" field.*
>
> *This will open the "Browse For Folder - Select backup target" screen. From here, select a valid folder and click on the OK button.*

5. Click on the Restore button. The following confirmation message is displayed:

> Restore from backup
> New No
> WARNING this will overwrite your current Set of Books! Are you sure you want to continue?

6. If you click Yes, another confirmation message will be displayed.

> This will seriously affect your Set of Books! Are you sure you want to clear this Set of Books?

7. Select (tick) the "*I have read this instruction and I understand the action!*" The Yes and No buttons will be activated. If you click on the No button, the process will be cancelled. Click on the Yes button, if you are absolutely sure. The following information message will be displayed.

> Your Set of Books will be restored in:
> C:\TurboCASH5-2025\books\MY-BOOKS\
> Do you wish to continue?

8. If you click on the No button, the process will be cancelled. Click on the Yes button, the restore process will be started. When the restore process is completed, an information message will be displayed.

> The Restore process is completed!

If the "Small backup (books)" option was not selected on the "Backup Set of Books" screen, any images that are linked to Groups and Stock items will also be included in the backup file and will be restored when the backup is restored.

9. Click on the OK button and click on the Close button on the "*Backup Set of Books*" screen.

You may also press the Esc key on your keyboard to exit the Backup Set of Books screen.

Should a backup file not exist in the selected directory, an error message will be displayed:

> Backup file not found in
> C:\TurboCASH5-2025\Backups\MY-BOOKS202204050538.zip

Click OK and select the correct backup file in zip format.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Accounts (Ledger)

What is the chart of accounts?

The chart of accounts is a systematic arrangement of all the accounts that a business uses to record its

financial transactions. It encompasses a comprehensive list of accounts tailored to fit the specific needs of each business. These accounts are linked to account groups, which classify them according to their nature, such as fixed assets, non-current assets, current assets, current liabilities, long-term liabilities, revenue, equity or capital, operating revenue, non-operating revenue, operating expenses, non-operating expenses, cost of sales, and more.

The chart of accounts is structured to align accounts with five financial categories: assets, liabilities, equity (capital), revenue (income), and expenses. By linking or mapping accounts to these financial categories, businesses ensure consistency and accuracy in financial records. The chart of accounts serves as a standardized structure for organizing financial information, facilitating the management and analysis of a business's financial data. It is a systematic arrangement of all the accounts that a business needs to prepare its financial statements, including the such as the trial balance, income statement and balance sheet.

The specific account groups and their links to financial categories may vary depending on the applicable accounting standards, such as Generally Accepted Accounting Principles (GAAP), International Financial Reporting Standards (IFRS), IFRS for SMEs (International Financial Reporting Standards for Small and Medium-sized Entities). or other jurisdiction-specific frameworks. Adhering to these accounting standards ensures compliance and facilitates consistent financial reporting across entities.

In summary, the chart of accounts is an essential tool for financial reporting and analysis. It provides a standardized structure for organizing financial information, ensures consistency and accuracy in financial records, and can be customized to meet the specific needs of a business based on its size, industry, and accounting requirements.

The accounting framework aligned with the chart of accounts, when processing transactions the accounting standards prescribes the treatment of transactions?

The accounting framework aligned with the chart of accounts provides the guidelines and principles for how transactions should be recorded and treated in financial statements. Accounting standards, such as GAAP or IFRS, prescribe the specific rules and principles that determine how transactions should be recognized, measured, and presented in financial statements.

When processing transactions, businesses follow the accounting standards to ensure that the financial information accurately reflects the financial position, performance, and cash flows of the company. The accounting standards dictate the appropriate accounting treatment for various types of transactions, such as revenue recognition, expense recognition, asset valuation, and liability measurement.

By adhering to the accounting standards, businesses maintain consistency and comparability in their

financial reporting. This allows stakeholders, including investors, creditors, and regulatory bodies, to understand and analyse the financial information in a standardized and meaningful way.

The alignment of the chart of accounts with the accounting framework ensures that transactions are recorded and classified correctly, following the prescribed rules and principles of the applicable accounting standards. This helps ensure the accuracy and reliability of the financial statements and promotes transparency and trust in the financial reporting process.

Existing users of osFinancias/TurboCASH

You may add your Set of Books (database) in the books directory of your osFinancials5/TurboCASH5 installation directory.

Where to get osFinancials5/TurboCASH5 Sets of Books (templates)?

If you're new to osFinancials5/TurboCASH5, the initial step would be to choose a suitable Set of Books that matches your country, language, industry and requirements. If you opt to use one of the pre-made Sets of Books in osFinancials5/TurboCASH5, most of the settings and defaults will already be configured.

You can easily download a template for your country and language by selecting the "*Let osFinancials help you to create a Set of Books?* / "*Let TurboCASH5 help you to create a Set of Books?*" - *Download*" option, which takes only a few clicks. You can view a list of available Firebird Sets of Books and linked languages available as a free download. You can then customise the Set of Books to meet your specific requirements.

In TurboCASH5, you may click on the Browse button of the Open Set of Books option and select similar Sets of Books from the "...\bin\Repository" folder.

To get started, you need to provide a few basic details and select some basic options. This process is simple and straightforward.

Steps to Customise a Set of Books (template)

Once you have downloaded a Set of Books (template), the first steps is to view and analyse the existing chart of accounts, groups and financial categories and change it to suit your specific requirements.

View analyse and print the chart of accounts

After opening a Set of Books, you may print a list of the chart of accounts from the following options:

- Reports → Ledger → Listing menu. You may select to print the chart of accounts in various sequences: account code, account description, account type, reporting group 1 or reporting group 2. ,

- Ledger analyser 1 / Ledger analyser 2 - Trial balance - "Ignore zero balances" option not selected. The default "Groups" is none. This will list all the Ledger accounts (Chart of accounts) according to the account code. To preview how the Chart of accounts is structured and linked to Financial categories, Account group 1 and Account group 2, select Reporting groups 1 or Reporting group 2.

Customise the chart of accounts

The next step is to customise the Chart of accounts for your specific requirements

It is important to plan the Chart of accounts and to link accounts to account reporting groups and financial categories, since this is the core of managing your budgets, business activities and managing your business on the financial reports, such as the trial balance, income statement and balance sheet.

The chart of accounts is further structured by linking each account to a reporting groups (Account group 1 and/or Account group 2). Each of these Account groups needs to be linked to a financial category.

In osFinancials5/TurboCASH5, the chart of accounts lists all the accounts (ledger, bank and tax account types) in the general ledger which is either reported in the Trial balance, Income statement and Balance sheet.

The first step, after installing osFinancials5/TurboCASH5, is to find a Set of Books (template) that matches your requirements.

Once you have selected your Set of Books, go to Save as on the Start ribbon, to edit your Chart of accounts.

The accounts structure in all of the Set of Books templates, available as a free download, when you create a Set of Books using the / "*Let TurboCASH5 help you to create a Set of Books?*" on the Creation wizard, consists of 3-digit main accounts and 3-digit sub-accounts, except for the following Sets of Books:

	Books with 4-digit main account and 3 - digit-sub-accounts		*Books with 5-digit main account and 3 - digit-sub-accounts*
	EN-CANADA-CORPORATION		*EN-USA*
	EN-CANADA-OTHER		*EN-USA CALIFORNIA*

After opening a Set of Books, you may print a list of the Chart of accounts from the following options:

- *Reports → Ledger → Listing menu.*
- *Ledger analyser 1 / Ledger analyser 2 - Trial balance - "Ignore zero balances" option not selected. The default "Groups" is none. This will list all the Ledger accounts (Chart of accounts) according to the account code. To preview how the Chart of accounts is structured and linked to Financial categories, Account group 1 and Account group 2, select Reporting groups 1 or Reporting group 2.*

All ledger accounts, including budgets is maintained in the Budgets on the Reports ribbon or in the Setup → Accounts on the Setup ribbon. Once your chart of accounts is set and linked, you may edit your chart of accounts:

1. Ledger accounts - Income and Expense and Balance sheet account types; which include the following account types:
2. Bank accounts - Bank accounts, including Petty cash accounts
3. Tax accounts - Correct tax rates and terminology for your country. If Tax rates changes, you need to change the tax rates.
4. Budgets - Enter and edit budget figures. Budgets may also be entered and edited in the Setup → Accounts on the Setup ribbon.

If you have added a Financial entry stock item type, you may select a general ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account from the Accounts lookup when processing documents.



It is important to note the types of accounts, which will be reflecting in your List of Accounts (Chart of accounts) as you will create, edit and delete accounts in Setup → Accounts (Setup ribbon):

Account type	*Brief description of the Account type*
Bank accounts	*Bank accounts should be linked to a Receipts and Payment Journal batch.*
General ledger accounts	*Accounts are aligned to either an Income / Expense or Balance sheet account type.* *The Balance sheet account type, needs to include the following 3 control accounts;* W *Retained income / earnings.* W *Creditor's control account.* W *Debtor's control account.*
Tax accounts	*Accounts containing the Tax percentages and dates for which those tax percentages are effective. These are the Output Tax and Input Tax codes.*

These are country specific and should contain the VAT / GST / Sales Tax terminology and codes as prescribed by the tax authority of your specific country.

Creditor (supplier / vendor) and Debtor (customer / client) accounts, are created, edited or deleted in Default ribbon.

Menu option	*Brief description of the account type*
Creditors	*Creditor (supplier) accounts containing the details of the creditors, remittance advice messages, contacts, land terms. It also contains detail of processed transactions and a list of purchase documents (i.e. Purchases, Supplier returns and Orders).* *The total of all individual accounts in the Creditor's ledger will be displayed as the Creditor's control account in the General ledger.*
Debtors	*Debtor (customer / client) accounts containing the details of the debtors, statement messages and terms. It also contains detail of processed transactions and a list of sales documents (i.e. Invoices, Credit notes, Quotes and Point-of-Sale Invoices).* *The total of all individual accounts in the Debtor's ledger will be displayed as the Debtor's control account in the General ledger.*

Created with the Standard Edition of HelpNDoc: Elevate Your Help Documentation with a Help Authoring Tool

Planning your Chart of Accounts

When planning the Chart of accounts in osFinancials5/TurboCASH5, you should follow the following guidelines:

- Increment each account number by either 5 or 10 to allow for future additions.
- Try to list accounts in alphabetical order.
- Group similar accounts in similar predefined ranges, such as 600-699 for Fixed assets.
- List accounts in the order you want them to appear in reports.

osFinancials5/TurboCASH5 allows for 999 main accounts in a 3-digit Set of Books. Each account can have up to 999 sub-accounts, which should be sufficient for most businesses.

Some Sets of Books may have 4-digit main, and 5-digit main accounts. The option to "Customise your own Set of Books (Advanced)?" on the Creation wizard (Create Set of Books on the Start ribbon)), allows you to create your own Set of Books from scratch. This will then ask you to specify the number of digits for accounts (from 3 to 8-digits). You need to enter the following 3 control accounts;

W *Retained income / earnings.*

W *Creditor's control account.*

W *Debtor's control account.*

The following ranges (based on the 3-digit main account codes) are an example that you can follow to group accounts:

Description	*Range*	*Group*
Total Chart	*001-999*	
Income	*001-099*	*Income*
Expenses	*200-499*	*Expenses*
Capital	*500-599*	*Capital*
Retained earnings / income	*500-599*	*Capital*
Fixed assets	*600-699*	*Fixed assets*
Current assets	*700-899*	*Current assets*
Current liabilities	*900-999*	*Current liabilities*
Tax codes for Tax main account	*850-860*	*Current liabilities*

Bank account + Positive balance	*810*	*Current assets*
Bank account – Negative balance (O/D)	*910*	*Current liabilities*

In the Setup → Accounts section, you can create, edit, and delete general ledger, bank, and tax accounts, as well as enter and edit budget figures for accounts. You must link accounts to Account groups 1 and/or Account group 2, which must be linked to Financial categories.

You can create Reporting groups in Setup → Accounts and link them to Financial categories for the Balance sheet (i.e., Assets, Capital, Liabilities) and Financial categories for the Income statement (i.e., Income and Expenses).

In addition to this, you may create Account group 1 and/or Account group 2 in Setup → Groups and link them to Financial categories. These Account groups may also be linked to Financial categories in Setup → Financial categories.

Created with the Standard Edition of HelpNDoc: Effortlessly bring your documentation online with HelpNDoc

Considerations when designing a chart of accounts

Considerations when designing a chart of accounts

Designing a chart of accounts is an important step in setting up an accounting system for a business. The chart of accounts provides a framework for organizing and categorizing financial transactions and helps in generating accurate financial reports. When designing a chart of accounts, there are several factors to consider:

1. Legal and regulatory requirements: Take into account the tax legislation, accounting standards, and frameworks mandated by the regulatory authorities in your country. Ensure that your chart of accounts aligns with these requirements to facilitate accurate reporting and compliance.
2. Business type: Consider the legal structure of your business (sole proprietorship, partnership, corporation, etc.) and any specific reporting requirements applicable to your business type. This may include separate categories for equity accounts, distributions, dividends, or partner capital accounts, depending on the structure.
3. Organizational structure: Take into account the structure of your organization, including any

subsidiaries or departments that require separate reporting. Determine whether you need separate accounts for each entity or if a consolidated approach is sufficient.

4. Reporting requirements: Identify the financial reports you need to generate for internal and external stakeholders. Ensure that your chart of accounts aligns with the reporting requirements of regulatory authorities, tax agencies, and other relevant parties.
5. Industry-specific needs: Different industries have unique financial requirements and operational activities. Tailor your chart of accounts to reflect the specific needs of your industry. For example, a manufacturing business may have separate accounts for raw materials, work-in-progress, and finished goods, while a service-based business may focus more on revenue accounts and service-related expenses.
6. Operational activities: Consider the nature of your business operations and the key financial activities involved. Identify the essential accounts that reflect your revenue streams, expenses, assets, liabilities, and equity. Determine the level of detail required to track and analyze your financial transactions effectively.
7. Future scalability: Anticipate the growth and expansion of your business. Design your chart of accounts with scalability in mind, allowing for the addition of new accounts or reporting categories as your business evolves.
8. Consistency and standardization: Maintain consistency and standardization in your chart of accounts to ensure accurate and meaningful financial analysis and reporting. Use clear and concise account names and numbering systems that are easy to understand and navigate.
9. Integration with accounting software: If you're using accounting software, ensure that your chart of accounts aligns with the software's capabilities and structure. This will facilitate seamless data entry, reporting, and analysis.
10. Collaboration with accounting professionals: Consult with accounting professionals, such as certified public accountants (CPAs) or financial advisors, who can provide guidance based on their expertise and industry knowledge. They can help ensure that your chart of accounts meets regulatory requirements and best practices.

It's important to strike a balance between having a comprehensive chart of accounts that captures all necessary information and keeping it manageable and user-friendly. Regular review and adjustment of the chart of accounts may be necessary as the business evolves and financial reporting needs change.

Regularly review and update your chart of accounts as your business evolves and financial reporting needs change. It's important to strike a balance between capturing necessary financial information and maintaining a manageable and user-friendly structure for day-to-day accounting operations.

Is there any legal requirements for SMEs?

Legal requirements for SMEs (Small and Medium Enterprises) can vary depending on the country and the specific industry. However, there are some common legal considerations that SMEs generally need to address. Here are a few examples:

1. Business registration: SMEs are typically required to register their business with the appropriate government authorities. This may involve obtaining a business license, tax identification number, or other permits based on the jurisdiction.
2. Tax compliance: SMEs must comply with tax regulations and fulfil their tax obligations. This includes filing tax returns, remitting taxes (such as income tax, sales tax, or value-added tax), and maintaining proper tax records.
3. Employment laws: SMEs need to comply with labour laws and regulations related to hiring, employing, and managing their workforce. This includes adhering to minimum wage requirements, providing employee benefits, following workplace safety standards, and respecting labour rights.
4. Financial reporting: SMEs are typically required to maintain accurate financial records and prepare financial statements in accordance with applicable accounting standards or regulations. These financial statements may need to be submitted to regulatory authorities or made available to stakeholders such as tax authorities, investors, or lenders.
5. Intellectual property protection: SMEs should be aware of intellectual property laws and consider protecting their intellectual property assets, such as trademarks, copyrights, or patents, to safeguard their unique products, services, or brand identity.
6. Consumer protection: Depending on the nature of the SME's business, there may be consumer protection laws and regulations in place. These laws aim to ensure fair business practices, protect consumer rights, and regulate product safety, labeling, warranties, or refund policies.
7. Data protection and privacy: SMEs that handle personal data or operate online may need to comply with data protection and privacy laws. This includes safeguarding customer information, obtaining necessary consent for data collection and processing, and following data breach notification requirements.

It's important for SMEs to consult with legal professionals or business advisors who have expertise in local laws and regulations. They can provide specific guidance tailored to the SME's jurisdiction and industry, helping ensure compliance with legal requirements and minimizing legal risks.

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Account groups

In osFinancials5/TurboCASH5, you can create multiple groups to meet your specific requirements. These account groups are linked to financial categories and play a crucial role in structuring the layout of the Trial balance, Income statement and Balance sheet. By organizing and categorizing your financial data effectively, these account reporting groups and their links to financial categories provide a structured framework for generating accurate financial reports.

What is Account groups and Financial categories in the Chart of Accounts?

Account groups and Financial categories play a significant role in aligning the Chart of Accounts with accounting standards such as GAAP (Generally Accepted Accounting Principles), IFRS (International Financial Reporting Standards), and IFRS for SMEs (International Financial Reporting Standards for Small and Medium-sized Entities). While the specific terminology and requirements may vary across jurisdictions, the general principles remain consistent. Here's a general definition of these terms in relation to accounting standards:

1. Account groups: Account groups represent logical classifications or categories of related accounts within the Chart of Accounts. They provide a structured framework for organizing and grouping accounts based on their characteristics, functions, or purpose. The account groups assist in generating accurate financial statements and facilitate analysis, reporting, and compliance with accounting standards. The specific account groups within the Chart of Accounts may vary depending on the nature of the business, industry practices, and specific accounting standards applicable in the jurisdiction.
2. Financial categories: Financial categories refer to the classification of accounts based on their nature or financial statement presentation requirements. These categories typically include Assets, Liabilities, Equity, Revenue, Expenses relevant classifications specified by accounting standards. Financial categories ensure the appropriate grouping and presentation of accounts in the financial statements to comply with accounting standards. They provide consistency and comparability of financial information across different entities, enabling stakeholders to analyse and interpret financial data in a standardised manner.

Account groups and financial categories are designed to align the Chart of Accounts with the prescribed accounting standards in various jurisdictions. The specific requirements and terminology may differ based on the applicable accounting framework. Therefore, it is important to consult the relevant accounting standards (such as GAAP, IFRS, IFRS for SMEs, etc.) specific to the jurisdiction in order to understand the detailed guidelines for defining and implementing account groups and financial categories within the Chart of Accounts.

In osFinancials5/TurboCASH5, you have the flexibility to create multiple groups to meet your specific requirements. These account groups are linked to the financial categories. These account reporting groups and their link to financial categories play a crucial role in structuring the layout of the Trial balance, Income statement and Balance sheet. They help organize and categorize your financial data effectively.

Defining Account groups and Financial categories

Before creating and setting up or or when editing Ledger accounts, Bank accounts, and Tax accounts in osFinancials5/TurboCASH5, it is recommended to define the basic classification of accounts using Account group 1 or Account group 2. This helps organize and categorize your accounts based on their nature or function.

In the Setup → Groups menu on the Setup ribbon, you can add Account group 1 or Account group 2 and assign them meaningful names that represent different account classifications. For example, you can create groups for fixed assets, cash and receivables, current assets, current liabilities, equity, operating expenses, operating revenue, non-operating expenses, non-operating revenue, etc. These groups provide a structured framework for organising your accounts.

After creating the account groups, you can map or link them to the five financial categories: Assets, Liabilities, Equity, Income, and Expenses in the Setup → Financial categories menu on the Setup ribbon. This mapping ensures that the accounts are correctly classified within the financial framework of your organisation.

When you proceed to create and set up Ledger accounts, Bank accounts, and Tax accounts in the Setup → Accounts menu, you will have the option to select the appropriate Account group 1 and/or Account group 2 for each account. By associating the accounts with their respective account groups, you establish a hierarchical structure that allows for easier navigation and analysis of financial information on the Trial balance, Income statement and Balance sheet, etc.

By properly defining and linking account groups, you lay the foundation for accurate financial reporting and analysis within osFinancials5/TurboCASH5, enabling you to effectively track and manage your organisation's financial data.

Options to define Account groups and Financial categories

In osFinancials5/TurboCASH5, you have the option to set up two (2) Reporting groups for your General ledger accounts, including Bank accounts and Tax accounts. To configure these groups, you can utilize the following menu options on the Setup ribbon:

1. Setup → Groups: This menu option allows you to define and configure Reporting groups. Reporting groups are used to categorize and classify accounts based on specific criteria or classifications. You

can assign accounts to different Reporting groups to facilitate reporting and analysis. By organizing accounts into groups, you can easily generate financial reports and statements based on these groupings.

2. Setup → Accounts: Under this menu option, you can create and manage your accounts within the Chart of Accounts. This includes setting up General ledger accounts, Bank accounts, Tax accounts, Creditor accounts, Debtor accounts, and more. Here, you can define the account codes, descriptions, account types, and other relevant details for each account.

It is recommended to set up Reporting groups in order to enhance the organization and analysis of your financial data. By utilising the Accounts and Groups options on the Setup ribbon, you can effectively manage and structure your Chart of Accounts to meet your reporting and analysis requirements.

Financial categories and Account groups - Outline

The Account groups in osFinancials5/TurboCASH5 serve as a means to further classify and categorize your accounts based on the main financial categories of Income, Expenses, Capital, Assets, and Liabilities, which are part of the accounting equation.

Each of the main financial categories can be divided into specific Account groups that align with the nature of the transactions and activities within your business. Here are some examples of how the main financial categories can be further divided:

1. Assets: (Balance sheet accounts)
    - Fixed assets (Immovable assets): These are long-term assets that have a physical form and provide value to the business over an extended period, such as buildings, land, vehicles, and machinery.
    - Current assets (Movable assets): These are short-term assets that can be easily converted into cash within a year, including cash on hand, inventory, accounts receivable, and short-term investments.

        > *The Debtors control account (Accounts receivable account) should be lined or mapped to the Current assets account group.*

    - Intangible assets These are valuable resources that lack physical substance but possess long-term value and contribute to the business's financial performance. They represent non-physical assets that provide economic benefits over an extended period. such as intellectual property, goodwill, licenses and permits, customer relationships, client brands.
2. Liabilities: (Balance sheet accounts)

- Long-term liabilities: These are obligations that extend beyond one year, such as loans, mortgages, or bonds.
- Current liabilities: These are short-term obligations that need to be settled within a year, such as accounts payable, credit card debt, or accrued expenses.

> *The Creditors control account (Accounts payable account) should be lined or mapped to the Current liabilities account group.*

3. Capital: (Balance sheet accounts)
   - The contribution or investment from the owner(s): This represents the funds or assets contributed by the business owner(s) to establish or operate the business. The specific groups within Capital will depend on the type of ownership structure, such as Company, Close Corporation, Partnership, or Sole Proprietorship.

> *The Retained earnings account (Retained income account) should be lined or mapped to the Capital or Equity financial category.*

4. Income: (Income statement accounts)
   - Income from normal business activities: This includes revenue generated from sales, consulting services, or any other core business operations.
   - Other income: This includes income received from sources other than the normal business activities, such as interest earned.

5. Expenses: (Income statement accounts)
   - Expenses incurred during normal business activities: This includes costs related to rent, utilities, salaries, advertising, and other day-to-day operational expenses.
   - Expenses of a Capital nature: These are expenses related to the acquisition or improvement of long-term assets, such as property, equipment, or software.

In osFinancials5/TurboCASH5, you have the flexibility to create any number of Account groups that align with your specific requirements. These Account Reporting groups play a crucial role in structuring the layout of the Trial balance, and financial statements, including the Income statement and Balance sheet. Additionally, you can choose to generate General ledger transaction reports for specific Account groups, allowing you to focus on relevant accounts for reporting and analysis purposes.

Options to link account groups to financial categories

When setting up your account groups and linking them to financial categories, you have two options available on the Setup ribbon. Here's a breakdown of each option:

1. Option 1: Setup → Accounts: This option allows you to link account groups to financial categories.
2. Option 2: Setup → Financial categories: The second option involves linking account groups to financial categories.

Both options provide flexibility in managing and organizing your financial data. The choice between them depends on your preference and the level of granularity you require for categorizing your accounts and account groups.

Options to preview the structure of your Chart of Accounts

To preview or print a list of your general ledger accounts, including bank accounts and tax accounts, which you ave lined to account groups and financial categories, you may print a list of accounts linked to account groups from the following options on the Reports ribbon:

1. Reports → Ledger → Listing menu: Print or view the report in "*Account code, Account description Account type*" (Ledger, Bank and Tax accounts) or "*Account group 1*" or "*Account group 2*" sequence.
2. Ledger analyser 1 or Ledger analyser 2: You may select the Trial balance to view all accounts, Income statement to view only the insome and expense accounts or Balance sheet to view only the balance sheet accounts. You may select to print may select the Groups as "*None*" to print accounts according to the account code or "*Reporting group 1*" or "*Reporting group 2*" options.

This will provide a preview of how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Options to change the structure of your Chart of Accounts

If you need to change the layout and structure on which the Trial balance, Income statement and Balance sheet groups and financial categories are printed on financial reports, you may change the sequence in the following options on the Setup ribbon:

1. Setup → Accounts: On the Accounts screen select the Reporting group 1 or Reporting group 2 sort option and then use the Move up or Move down options.
2. Setup → Groups: On the Groups screen select the Account group 1 or Account group 2 sort option and then use the Move up or Move down buttons.

These options will change the sequence and structure of accounts linked or mapped to account groups and financial categories.

By adjusting the sequence of account groups using these options, you can modify the layout and structure of financial reports such as the Trial balance, Income statement and Balance sheet. These changes will affect how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Created with the Standard Edition of HelpNDoc: Converting Word Docs to eBooks Made Easy with HelpNDoc

Account groups (Setup - Groups)

You have the option to create two (2) reporting groups (Account group 1 and/or Account group 2) that can be used to categorise the various types of accounts in your chart of accounts, including ledger, bank and tax accounts. Each account must be linked to one of these reporting groups in order to be properly classified.

These reporting groups can be linked to a financial category that will help structure your options for viewing, analysing, and printing financial reports such as the Trial balance, Income statement and Balance sheet,

To set reporting groups for General ledger accounts:

1. On the Setup ribbon, select Setup → Groups. The "*Groups (Account group 1)*" default screen is displayed:



You may set different sequences for each reporting group in which the groups and accounts are listed on reports, etc. This is done by selecting the groups on the list and use the Move up or Move down buttons.

You may also change the sequence of the groups to structure of your Chart of Accounts in Setup → Accounts by selecting the Reporting group 1 or Reporting group 2 sort option and then use the Move up or Move down options.

By adjusting the sequence of account groups using these options, you can modify the layout and structure of financial reports such as the Trial balance, Income statement and Balance sheet, These changes will affect how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Account group 1	*Account group 2*
	

2. If you wish to rename the Reporting group name - Account group 1, over-type the description with your new description. This will change the description of the button for Account group 1.

3. To add a new Group to the root directory or list, select the "*REPORTING GROUP ROOT*" on the list and click on the New button.

4. Enter the name of your Account group and click on "*REPORTING GROUP ROOT*" on the list.

5. Repeat the process until you have entered all the Account groups, etc.

6. If you need to add Reporting group 2 for Account groups, click on the Account group 2 button and repeat the process as for Account group 1.

7. Click on the OK button to save your changes and close (exit) this screen.

You may click on the Print button to print a list of your general ledger account groups.

You may set colours to display on the T-Account viewer. To do this, click on the Back colour button to set the rows background colour and the Font colour button to set the Font colour.

To retain and save the selected colors, you also need to set both the "Back color" and the "Font color".

Options to preview the structure of your Chart of Accounts:

To preview or print a list of your general ledger accounts, including bank accounts and tax accounts, which you ave lined to account groups and financial categories, you may print a list of accounts linked to account groups from the following options on the Reports ribbon:

1. *Reports → Ledger → Listing menu: Print or view the report in "Account code, Account description Account type" (Ledger, Bank and Tax accounts) or "Account group 1" or "Account group 2" sequence.*
2. *Ledger analyser 1 or Ledger analyser 2: You may select the Trial balance to view all accounts, Income statement to view only the insome and expense accounts or Balance sheet to view only the balance sheet accounts. You may select to print may select the Groups as "None" to print accounts according to the account code or "Reporting group 1" or "Reporting group 2" options.*

This will provide a preview of how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Account groups (Setup - Accounts)

The process for creating and managing reporting groups for Account Group 1 and Account Group 2 in the Setup → Accounts menu and linking account groups to financial categories:

1. Creating or Deleting Reporting Groups in Setup - Accounts Menu:
    - Access the Setup → Accounts menu.
    - Within this menu, you have the ability to create or delete reporting groups for Account Group 1 and Account Group 2.
    - By creating reporting groups, you can further categorize and organize your accounts within these account groups based on your specific requirements.
    - Similarly, if needed, you can delete existing reporting groups that are no longer necessary.
2. Linking Account Groups to Financial Categories in Setup → Accounts Menu:
    - While in the Setup - Accounts menu, you can also link account groups to financial categories such as Assets, Capital, Expenses, Income, or Liabilities.

- This step allows you to associate each account group with its corresponding financial category to ensure accurate reporting and categorization of accounts.
- By linking account groups to financial categories, you establish a relationship between the groups and the broader financial classification framework.

To summarize, in the Setup - Accounts menu, you have the ability to create, delete, and manage reporting groups for Account Group 1 and Account Group 2. Additionally, you can link these account groups to the appropriate financial categories to ensure accurate categorization of your accounts within the chosen accounting framework.

You may set up to two Reporting groups for your Accounts. Account groups allows you to group or categorise the accounts on which you would like to report. Each Account group need to linked to a Financial category to structure the options to view, analyse and print the financial reports (i.e. the Trial balance, Income statement and Balance sheet, etc.).

To set reporting groups for General ledger accounts:

1. On the Setup ribbon, select Setup → Accounts.
2. Select "*Financial categories*, *Reporting group 1*" or "*Reporting group2*" in the "*Sort*" field.



3. To add a new group, click on the Add:Group icon. Enter the name for the Group.
4. Select a Group and select a Financial category (i.e. Assets, Capital, Expenses, Income or Liabilities) from the list.
5. Click on the Save button.
6. Repeat the process for all the Account groups.

7. Once finished with Reporting group 1, select Reporting group 2 and repeat the link process.

The Save button will only be displayed (next to the Name) field, once any any changes are made.

You need to click on the Save button. If you do not do this, your changes will be lost.

Account group 1	Account group 2
	

Options to preview the structure of your Chart of Accounts:

To preview or print a list of your general ledger accounts, including bank accounts and tax accounts, which you ave lined to account groups and financial categories, you may print a list of accounts linked to account groups from the following options on the Reports ribbon:

1. *Reports → Ledger → Listing menu: Print or view the report in "Account code, Account description Account type" (Ledger, Bank and Tax accounts) or "Account group 1" or "Account group 2" sequence.*
2. *Ledger analyser 1 or Ledger analyser 2: You may select the Trial balance to view all accounts, Income statement to view only the insome and expense accounts or Balance sheet to view only the balance sheet accounts. You may select to print may select the Groups as "None" to print accounts according to the account code or "Reporting group 1" or "Reporting group 2" options.*

This will provide a preview of how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Options to change the structure of your Chart of Accounts:

If you need to change the layout and structure on which the Trial balance, Income statement and Balance sheet groups and financial categories are printed on financial reports, you may change the sequence in the following options on the Setup ribbon:

1. *Setup → Accounts: On the Accounts screen select the Reporting group 1 or Reporting group 2 sort option and then use the Move up or Move down options.*
2. *Setup → Groups: On the Groups screen select the Account group 1 or Account group 2 sort option and then use the Move up or Move down buttons.*

These options will change the sequence and structure of accounts linked or mapped to account groups and financial categories.

By adjusting the sequence of account groups using these options, you can modify the layout and structure of financial reports such as the Trial balance, Income statement and Balance sheet. These changes will affect how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Financial categories

Options to link account groups to financial categories

Financial categories are a way to group accounts into categories that are relevant for financial reporting. In osFinancials5/TurboCASH5, financial categories are used to generate reports for the balance sheet and income statement. Financial categories include assets, liabilities, capital, income, and expenses.

When setting up accounts in osFinancials5/TurboCASH5, they can be linked to financial categories so that they can structure the financial reports. By properly categorizing accounts into financial categories, businesses can get a clear picture of their financial position and performance.

Once your Reporting groups for Account group 1 and/or Account group 2 is added, you need to link these to one of the Assets, Capital, Expenses, Income or Liabilities financial categories.

The following two (2) options, on the Setup ribbon, are available to link the financial categories:

1. Setup → Financial categories.
2. Setup → Accounts.

The basic account groups should already be pre-set for a Set of Books, and you may add, edit or delete any of these groups in Setup → Groups on the Account group 1 and/or Account group 2, before linking them to financial categories.

- Assets, Capital and Liabilities are Balance sheet financial categories, and
- Income and Expenses are Income statement financial categories.

It is important to base this linkage, to the respective categories, on the accounting equation.

Account groups - Reporting group 1 and 2 – The sequence in which the groups and accounts are listed, may be changed by selecting the groups on the list and use the Move up or Move down buttons.

In this example, two (2) Reporting groups 1 and 2 is set to different sequences:

Reporting group 1	*Reporting group 2*
	

This will enable you to print general ledger reports (i.e. Trial balance, Income statement, Balance sheet, Chart of Accounts), to list accounts and balances to be listed according to Reporting group 1 or according to Reporting group 2 sequences.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Output with HelpNDoc's Advanced Project Analyzer

Financial categories (Setup - Accounts)

In osFinancials5/TurboCASH5, you can create up to two (2) reporting groups for your accounts. Account groups allow you to categorize and group your accounts based on how you want to report on them. Each account group needs to be linked to a financial category in order to structure the financial reports such as the trial balance, income statement, and balance sheet. By properly categorizing and grouping your accounts, you can more easily analyse and understand your financial data.

Account reporting groups may also be linked to financial categories on the Setup → Financial categories (Setup ribbon).

To link Groups to Financial categories using the Accounts screen:

1. On the Setup ribbon, select Setup → Accounts. The Groups as created on Account groups - Reporting group 1 will be listed in the "*Accounts*" screen.

2. Select "*Financial categories*" in the "*Sort*" field.



3. Select a Group and select a Financial category (i.e. Assets, Capital, Expenses, Income or Liabilities) from the list.

4. Click on the Save button.

5. Repeat the process for all the Account groups.

6. Once finished with Reporting group 1, select Reporting group 2 and repeat the link process.

The Save button will only be displayed (next to the Financial category name) field, once any any changes are made.

You need to click on the Save button. If you do not do this, your changes will be lost.

Account groups - Reporting group 1 and 2 – The sequence in which the groups and accounts are listed, may be changed by selecting the groups on the list and use the Move up or Move down icons.

Account group 1	*Account group 2*
REPORTING GROUP ROOT Income Expenses Capital Longterm liabilities Current liabilities Fixed assets Current assets	REPORTING GROUP ROOT Capital2 Longterm liabilities2 Current liabilities2 Fixed assets2 Current assets2 Income2 Expenses2

Options to preview the structure of your Chart of Accounts:

To preview or print a list of your general ledger accounts, including bank accounts and tax accounts, which you ave lined to account groups and financial categories, you may print a list of accounts linked to account groups from the following options on the Reports ribbon:

1. *Reports → Ledger → Listing menu: Print or view the report in "Account code, Account description Account type" (Ledger, Bank and Tax accounts) or "Account group 1" or "Account group 2" sequence.*
2. *Ledger analyser 1 or Ledger analyser 2: You may select the Trial balance to view all accounts, Income statement to view only the insome and expense accounts or Balance sheet to view only the balance sheet accounts. You may select to print may select the Groups as "None" to print accounts according to the account code or "Reporting group 1" or "Reporting group 2" options.*

This will provide a preview of how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Options to change the structure of your Chart of Accounts:

If you need to change the layout and structure on which the Trial balance, Income statement and Balance sheet groups and financial categories are printed on financial reports, you may change the sequence in the following options on the Setup ribbon:

1. *Setup → Accounts: On the Accounts screen select the Reporting group 1 or Reporting group 2 sort option and then use the Move up or Move down options.*
2. *Setup → Groups: On the Groups screen select the Account group 1 or Account group 2 sort option and then use the Move up or Move down buttons.*

These options will change the sequence and structure of accounts linked or mapped to account groups and financial categories.

By adjusting the sequence of account groups using these options, you can modify the layout and structure of financial reports such as the Trial balance, Income statement and Balance sheet. These changes will affect how the account groups and financial categories are printed on the reports, providing a preview of your Chart of Accounts based on your desired accounting framework.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Financial categories (Setup)

You may set up to two (2) Reporting groups for your Accounts. Account groups allows you to group or categorise the accounts on which you would like to report. Each Account group need to linked to a Financial category to structure the options to view, analyse and print the financial reports (i.e. Trial balance, Income statement, Balance sheet, etc.).

Account reporting groups may also be linked to financial categories on the Setup → Accounts (Setup ribbon).

To link Reporting groups to Financial categories:

1. On the Setup ribbon, select Setup → Financial categories.



All your available account reporting groups will be listed. If you notice that not all account groups are available, you have to exit this screen and do the necessary amendments in Setup → Groups.

2. Select a category (Assets, Capital, Expenses, Income or Liabilities).

3. Select a group from the group list, and click on the Add button.

You may select more than one group. To do this, press the Ctrl or Shift key and while keeping it sown, use the mouse to select another group.

4. Repeat the process until you have no more items in the group list.

The following is a basic guideline of how groups should be linked to the Financial categories:

W *- Assets - Fixed assets, Current assets*

W *- Capital - Capital (for Sole Proprietorships and Partnerships), Share Capital (for Companies), Members Contributions (for Close Corporations)*

W *- Expenses - Expenses*

W *- Income - Income, Other income*

W *- Liabilities - Long-term liabilities, Current liabilities.*

For example, in the category Assets, select Fixed assets and click on the Add button, select Current assets and click on the Add button. The groups will be moved from the group list and be listed in the right hand side of the screen.

These selected groups are no longer available to be added to any other category. Click on each of these categories (Capital, Expenses, Income or Liabilities) and repeat the process for each of these categories, if necessary. At the end of this process you should not have any Groups available on the left-hand side of the screen.

5. Once you have completed the process, click on the Cancel button.

6. Click on the Yes button, and start again linking the groups to their respective category.

If you have added incorrect groups to a specific financial category, simply select the incorrect group from the list on the right hand side of your screen, and click on the Remove button. The option will now be available to link to another financial category.

To clear or reset all the linked groups to the Financial categories (Assets, Capital, Expenses, Income and Liabilities), click on the Reset button. An information message will be displayed:

> "This will radically alter your data! We recommend that you stop and make a backup! Do you wish to continue?"

You then need to start all over again to link a group.

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Edit - Accounts

Spreadsheet export



Accounts may be exported to the Excel Export / Import spreadsheet feature.

This option is used to add, edit or delete general ledger accounts. Should you no longer need an account, but cannot or do not wish to delete it, you may disable the ledger account.

To access Accounts:

1. On the Setup ribbon, select Setup → Accounts. The "*Accounts*" screen; listing your available accounts, is displayed:



2. You may filter and search for Accounts and Account groups as follows:

Search / Filter Option	*Description*
Sort:	*The default is None. - This will list all accounts according to the Account number (Code).*

	You may select to sort / list accounts according to Reporting group 1 or Reporting group 2 or Financial categories.
Account starts with:	*Filter your accounts by entering the first digit of the account number (code). For example, entering 2 will list only those account numbers starting with 2 (e.g. 200 to 299). To filter the list further, you may, for example, enter 21 to list only those accounts from 210 to 219.*
Description:	*Enter any character in the Account name (description). Only those accounts containing that character will be listed (e.g. B will list all accounts containing the character b. By typing BANK in this field, only the Accounts containing bank in the account name (description) field will be listed.*
Expand after refresh:	*If this field is selected, the expanded list of accounts will be displayed (when clicking on the Refresh icon (or clicking on the Refresh item on the context menu).*

The icons indicates the following:

Account groups	*Financial categories*
	

Account groups - Reporting group 1 and 2 – The sequence in which the groups and accounts are listed, may be changed in Setup → Groups. This is done by selecting the groups on the list and use the Move up or Move down buttons.

Account group 1	*Account group 2*
	

Icons for accounts:

Icon	Account type	Reported on	Description
	Income	*Income statement*	*Income – Expenses = Net Profit / Loss*
	Expense		
	Assets	*Balance sheet*	*What you own = Assets*
	Liability	*Balance sheet*	*What you owe to others = Liabilities*
	Bank	*Balance sheet*	*Current assets*
	Tax	*Balance sheet*	*Current liabilities (Output Tax – Input Tax)*
	Retained income / earnings	*Balance sheet*	*Capital (Profit / Loss – Previous Years)*
	Debtor's control account	*Balance sheet*	*Debtor's control = Current assets*
	Creditor's control account	*Balance sheet*	*Creditor's control = Current liabilities*

Processing Icons and Context menus:

Account groups	Accounts



W *Add Group.*

W *Save - Save changes.*

W *Delete a selected Group Account / Sub-account.*

W *Move selected Group up 1 entry.*

W *Move selected Group down 1 entry.*

W *Move selected Group to the left.*



W *Add Account / Add Sub-account.*

W *Delete a selected Account / Sub-account.*

W *Refresh the items on the Groups / Accounts list.*

W *Collapse the expanded Groups / Accounts list.*

W *Expand the short list of Accounts and Groups.*

W *Add new Account / Add new Sub-account.*

W *Refresh the Groups / Accounts list.*

W *Collapse the expanded Groups / Accounts list.*

W *Expand the short list of Accounts and Groups.*

The Delete icon (option) will not be available for the following accounts:

W *Accounts which has any transactions processed (posted). The Posted field display a value of more than 0.*

W *The Retained income / earnings account.*

W *The Delete icon (option) is available for Debtor's control account and Creditor's control account. Trying to delete these control accounts, will produce an Error message:*

"You cannot delete a control account!"

Field	*Description*
Account type:	*Select the following options:* 1. *Ledger Income / Expense , Asset / Liability / Capital accounts and Retained income / earnings and Debtor's control and Creditor's control accounts.*

2. *Bank account will allow you to link a Payments and Receipts batch on the Bank tab.*

3. *Tax account will allow you to set the tax percentage for (VAT/GST/Sales Tax) and specific tax settings.*

This field may only be selected for a new account. For existing accounts; this field will be disabled.

Account number: *This consists of 2 parts. The first block is for the main account; and the second block for the sub-account.*

Description: *The description for the account which will be used to lookup (select) accounts. This is also the description which will be displayed on reports.*

Group1: *This is used to group and classify the accounts on reports.*

Group2: *This is used to group and classify the accounts on reports.*

Type: *Balance sheet - (i.e Capital, Liabilities and Assets) or Income statement accounts (i.e. Income or Expense).*

Balance sheet accounts retains the balances of the previous financial year (opening balances).

Income statement – these accounts are closed off during the Year-end process and the balance (Net Profit / Loss) is transferred to the Retained income / earnings account.

Sub-accounts: *Select this option to create a main account. Once this option is selected, you first need to click on the Save button before you are allowed to create sub-accounts for that main account. You may then create sub-accounts for this main account.*

You will not be allowed to process (post) any transactions; or enter / edit any budget figures to the main account. All transactions and budget figures are entered on sub-accounts. The total of these individual sub-accounts will add up to the main account.

To delete a main account, you first need to delete all sub-accounts.

Status: *By default, all accounts are enabled (active). Once you have any transactions processed (posted) on a main account, you may not delete the main account.*

You may then select the disabled option to block a selected account or sub-account. This will disable; or set the selected account's status to inactive). This will produce error messages to remind you that the account or sub-account is disabled, when trying to process (post) transactions to the disabled account or sub-account.

Open item *By default all accounts are set to "No". If you select the "Yes" option, you may select to link (match) a*

account:	*receipt transaction to a debit transaction; or a payment transaction to a credit transaction, etc.* *This facility is useful when, for example, you need to control specific payments to specific transactions and specific receipts to specific transactions.*
Posted:	*This field indicates the number of transactions processed (posted) for the selected account. Once any transactions have been processed (posted) (the value is more than 0), you will not be allowed to delete the account.*
Use link tax:	*Link a Tax account to a ledger account. This will then be the default tax account when selecting the ledger account when processing transactions in the payments journal, receipts journal or other journals (batches).*

Only the Account type, Account number, Description, Group 1 and Group 2 fields will be displayed for control accounts; i.e. (Retained income / earnings) and Debtor's control and Creditor's control accounts).

The Save button will only be displayed (next to the Description (Account name) field), once any account is created or any field of an existing selected account is changed.

You need to click on the Save button. If you do not do this, your changes will be lost.

Created with the Standard Edition of HelpNDoc: Simplify Your Help Documentation Process with a Help Authoring Tool

Edit Bank accounts

You may have more than one Bank account and wish to add this to your Chart of accounts. osFinancials5/TurboCASH5 will have set up a Bank account for you in your selected template. (In this example, account number "*810-000 - Current Bank account*" is used).

Examples of cash books (bank accounts) in osFinancials5/TurboCASH5 could include:

- Checking account - This cash book represents a primary bank account used for daily transactions and general banking activities.
- Savings account - This cash book represents a bank account specifically designated for savings and accumulation of funds.
- Petty cash - This cash book is used to track and manage small cash transactions and expenses within

an organization.

- Credit card account - This cash book represents a bank account associated with a credit card, used for tracking credit card transactions and payments.
- Loan account - This cash book represents a bank account associated with a loan, used for tracking loan payments and balances.
- Investment account - This cash book represents a bank account used for managing investments, such as stocks, bonds, or mutual funds.
- Foreign currency account - This cash book represents a bank account denominated in a foreign currency, used for managing transactions and balances in that currency.
- Escrow account - This cash book represents a bank account used for holding funds in trust for specific purposes, such as real estate transactions or legal settlements.
- Trust account - This cash book represents a bank account used for holding funds in trust on behalf of clients or beneficiaries.
- Expense reimbursement account - This cash book represents a bank account used for tracking and reimbursing employee expenses.

These are just a few examples, and the specific cash books will depend on the needs and requirements of your organisation.

If you wish to change the Bank account description and batches name you my edit the account and batch types.

Bank accounts must be linked to a unique Payments and Receipts batch. You may create a new Payments and Receipts batch can create on the Bank tab when creating a new Bank account. You may edit the Batch type descriptions in Setup → Batch types.

To change a Bank account:

1. On the Setup ribbon, select Setup → Accounts. The *Accounts* screen; listing your available accounts will be displayed.
2. Select the "*810-000 - Current Bank account*" ("*Current assets" – Reporting group*).



2. In the "*Description*" field, replace "*Current bank account*" with the new Bank account description e.g. "*ABC-Bank*".

3. Click on the Bank tab.

4. Enter the unique name for the Payments and Receipts batches, e.g. "*ABC-Payments*" and the "*ABC-Receipts*". This will automatically add (create) the batch types which may be edited in Setup → Batch types.

> *Bank import plugin - Is included in the osFinancials5/TurboCASH5 Subscription - Bank Reconciliations Plugin Manual - BankImport Plugin Manual -*
>
> *If the "Default bank reconciliation method" option is not selected (tick removed) on the Setup → System parameters (Setup ribbon); the Payments and Receipts batch fields will be combined. You may then select either the Payments journal or the Receipts journal.*
>
>
>

5. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Create Bank accounts

On Accounts, you may create a new bank account, change the descriptions of an existing account, or to delete an existing account.

You may have more than one Bank account and wish to add this to your Chart of Accounts. osFinancials5/TurboCASH5 will have set up a Bank account for you in your selected template. (In this example, account number "*810-000 - Current Bank account*" is used).

If you wish to add another Bank account remember that in planning your Chart of Accounts you would like accounts of a similar nature to be grouped together.

Bank accounts must be linked to a unique Payments and Receipts batch. You may create a new Payments and Receipts batch can create on the Bank tab when creating a new Bank account. You may edit the Batch type descriptions in Setup → Batch types.

To create a new Bank account:

1. On the Setup ribbon, select Setup → Accounts. The *Accounts* screen; listing your available accounts will be displayed.

2. Select the last Bank account (e.g. "*B820000 - Petty cash*") (*Current assets – Reporting group*).



3. Click on the (Add:Account) icon (or select the Add on the context menu). An entry for the new bank account is displayed as "*G821 Account name*" on the Account list (the next Bank account code (incremented by 1), for example "*820000*" is selected, the next Bank account code will be "*821000*").

4. Enter or select the following:

    a) Account type - Select "*Bank Account*".

    b) Account no. - The main account "*821*" is displayed and cannot be edited. Type "*830*" in the account field.

    c) Description - Replace "*Account name*" with the new Bank account description e.g. "*XYZ-Bank*".

d) Account group 1 - Select the "*Current assets*" Account group.

e) Account group 2 - Select Account group 2, if not selected.

f) Account type - Select "*Balance sheet*", since the Bank account needs to be reported on the Balance sheet.

g) Sub-accounts - This field should not be selected, since bank accounts may not have sub-accounts.

> *If you select (tick) this field, the Bank tab will not be displayed. You will not be allowed to link the bank account to its own receipts and payments batch.*

h) Status - "*Enabled*" (default) should be selected.

i) Open item account - "*No*" (default) should be selected.

5. Click on the Bank tab.



6. Enter the unique name for the Payments and Receipts batches, e.g. "*XYZ Payments*" and the "*XYZ Receipts*". This will automatically add (create) the batch types which may be edited in Setup → Batch types.

> *If you select any existing payments and/or receipts batch, an error message will be displayed.*
>
> "Batch is linked to another bank. Please enter a unique name."
>
> *Click on the OK button and enter a new name for the Payments and Receipt batches.*

> *Bank import plugin - Is included in the osFinancials5/TurboCASH5 Subscription - Bank Reconciliations Plugin Manual - BankImport Plugin Manual -*
>
> *If the "Default bank reconciliation method" option is not selected (tick removed) on the Setup → System parameters (Setup ribbon); the Payments and Receipts batch fields will be combined. You may then select either the Payments journal or the Receipts journal.*



Once any transactions is posted (updated to the ledger) for a selected bank account; you cannot change the Payments or Receipts batches.

7. Click on the Save button.

The icon will change from *(Assets / Liabilities) to* *(Bank account).*

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Create / Edit Tax accounts

Sets of Books and Tax (VAT/GST/Sales Tax) terminology

You need to use this option whenever you wish to create a new Tax account or Tax code for VAT/GST/Sales Tax (Output Tax as well as Input Tax).

You may also change the descriptions of an existing account, change the percentages on your various tax types and percentages whenever the legislation is amended, or to delete an existing account.

The Tax codes and percentages, which apply for VAT/GST/Sales Tax, are prescribed by VAT/GST/Sales Tax or Tax Legislation and may be amended from time to time by the Tax Authorities.

Being registered for VAT/GST/Sales Tax, you will have two basic accounts, i.e. Output Tax that is charged when selling services or goods, and Input Tax when you purchase from another registered VAT/GST/Sales Tax vendor.

osFinancials5/TurboCASH5 will have setup an Output VAT/GST/Sales Tax and an Input VAT/GST/Sales Tax account as sub-accounts of the VAT/GST/Sales Tax Control account as Current liabilities for you in the templates.

The Tax codes and percentages differ from country to country and you may be required to change the percentages and create new codes whenever the legislation changes.

English (Default language file) refers to Tax. If you select the following English languages, it will refer to the following tax terminology:

English VAT	English GST	English Sales Tax / Consumption Tax
en-Bangladesh	en-Australia	en-American (Sales Tax)
en-Barbados	en-Belize	en-Tonga (Consumption Tax)
en-Botswana	en-New-Zealand	
en-Cameroon		
en-Ireland		
en-Isle-of-Man		
en-Lesotho		
en-Malawi		
en-Malta		
en-Mauritius		
en-Namibia		
en-Rwanda		
en-South-Africa		
en-Tanzania		
en-Trinadad		

en-Uganda

en-UK

en-Zambia

en-Zimbabwe

It is of utmost importance that you create these codes and percentages correctly to suit your needs and the requirements of legislation applicable to your country. You have to create, or add the Tax accounts (Tax codes), which you will need to fill in your VAT/GST/Sales Tax return. will print the necessary Tax or VAT/GST/Sales Tax reports for your Tax codes.

These Tax codes, or Tax accounts, should be created as sub-accounts. Before you can create the Tax codes you need the following two General ledger accounts created in Setup → Accounts (Setup ribbon):

1. *VAT/GST/Sales Tax Control account - the main account which will be used as a totalling account for the Tax codes.*
2. *VAT/GST/Sales Tax Payments account - the sub-account which you need to allocate your Tax payable (as submitted on your VAT/GST/Sales Tax returns) when you make payments in the payments journal to the Tax Authorities.*

In cases where the Input Tax is more than the Output Tax, you need to allocate the refunds received from the Tax Authorities in the receipts journal.

Sets of Books Templates - Simplified Structure of VAT Accounts in the Chart of Accounts and the VAT-Return

osFinancials5 / TurboCASH supports 79 different languages and tax regimes languages such as 87 Sets of Books (databases) that can be downloaded and customized to meet your requirements.

If you are a new user of osFinancials5/TurboCASH5, you can download the "*EN-SOUTHAFRICA*" Set of Books or of the industry-specific Set of Books (namely, *"FARMING, SERVICE, CHURCH, MEDICAL, MANUFACTURING, RETAIL*" or "*WORKSHOP*") from select the available Firebird database Sets of Books and linked languages available as a free download, the basic Chart of Accounts which already includes basic Output and Input VAT accounts and VAT codes is already pre-configured. There are also Manual Sets of Books namely HANDYMAN, HANDYMAN-A and HANDYMAN-B available for English which illustrate the

basic transactions where VAT is involved.

These English-language versions of the Sets of Books, can be downloaded free of charge from the available Firebird database Sets of Books and linked languages that are available. While the Afrikaans-language Set of Books will contain "*Belasting op Toegevoegde Waarde (BTW)*", the English-language Set of Books will contain "*Value Added Tax (VAT)*". osFinancials5/TurboCASH5 has already included for your basic Output VAT and Input VAT account as sub-accounts of the VAT control account as an "*Current liabilities*" in the master "*templates*".

The following basic simplified VAT accounts have already been created for the purposes of this documentation:

Tutorial Sets of Books HANDYMAN, HANDYMAN-A and HANDYMAN-B and *Documentation in in this Help file*			*EN-SOUTH-AFRICA Sets of Books template*		
Account code/ *Tax-code*	*Description*	*Tax-rate*	*Account code/* *Tax-code*	*Account code*	*VAT-Rate*
G850-000	*VAT - Control - 15%*	*Not applicable*	*G950-000*	*VAT CONTROL ACCOUNT - 15%*	*NVT*
T860-010	*Output VAT - 15%*	*15%*	*T950-005*	*Output VAT - 15%*	*15%*
T860-020	*Input VAT - Standard rate -15%*	*15%*	*T950-010*	*Input VAT - Standard rate -15%*	*15%*
T860-030	*Input VAT - Capital goods -15%*	*15%*	*T950-020*	*Input VAT - Capital goods -15%*	*15%*
T860-040	*Zero-rated VAT - 0%*	*0%*	*T950-030*	*Zero-rated VAT - 0%*	*0%*
G850-100	*VAT - Payment - 15%*	*Not applicable*	*G950-100*	*VAT PAYMENT ACCOUNT - 15%*	*NVT*

The Output VAT codes and Input VAT codes were created as sub-accounts under the "*VAT CONTROL ACCOUNT - 15%*" and included in the "*Current liabilities*" account group in the Chart of Accounts in the Set of Books. VAT codes or rather sub-accounts are indicated with a "*T*" prefix on which the applicable VAT code's percentage must be specified whether it is at 15% or 0% percent, for example in the case of zero rate VAT.

Finally, a General Ledger account "*VAT PAYMENT ACCOUNT - 15%*" (indicated with a "*G*" prefix) was also created as a sub-account under the "*VAT CONTROL ACCOUNT - 15%*" (indicated with a "*G*" prefix).

The "*VAT PAYMENT ACCOUNT - 15%*" is the account in which all payments that must be remitted to the South African Revenue Service (SARS) (if the Output VAT is more than the Input VAT) as well as refunds received from the South African Revenue Service (SARS) is received (if the Input VAT is more than the Output VAT), is recorded.

The balances of the "*VAT CONTROL ACCOUNT - 15%*" are as follows:

- A credit balance on the "*VAT CONTROL ACCOUNT - 15%*" means that the Output VAT is more than the Input VAT, which consequently normally shows that VAT is owed to the South African Revenue Service (SARS).
- A debit balance on the "VAT CONTROL ACCOUNT - 15%" means that the Input VAT is more than the Output VAT and that there is VAT from the South African Revenue Service (SARS) recoverable or refundable.

The transactions of the "VAT PAYMENT ACCOUNT - 15%" are as follows:

- Debit transactions - Payments owed to the South African Revenue Service (SARS) are debited against this account when the payment is made from the payment journal linked to the Bank Account. This amount should be indicated on the VAT return (VAT-201), for the period of the VAT return, as the amount you must pay to SARS.
- Credit transactions - Refunds received from the South African Revenue Service (SARS) are credited to this account and credited when the payment is received from the receipt journal linked to the Bank account. This amount should be shown on the VAT return (VAT-201), for the period of the VAT return, as owed to you by SARS.

In addition to these basic Tax codes or Tax accounts, within the "*VAT CONTROL ACCOUNT - 15%*" main account, you can create further sub-accounts to accommodate the respective classifications and/or tax percentages in respect of Output VAT and Input VAT to help you complete the VAT returns and make the correct payments to the tax authority.

The following examples of the "Full Structure of VAT accounts and VAT-codes in the Chart of Accounts" and the alignment to the relevant fields or boxes on VAT Returns"or VAT-declarations is available in this documentation:

- *Value Added Tax (VAT) - South Africa - The "Full Structure of VAT accounts in the Chart of Accounts and the VAT Return" The stricture South African VAT-accounts and VAT-codes of the Chart of Accounts is aligned with the VAT201-return.*

- *Value Added Tax (VAT) - United Kingdom - Various schemes for VAT may be applicable for various scenarios. The most commonly used VAT Standard rate scheme is documented as an example of the VAT-account and VAT-codes structure in Chart of Accounts for the United Kingdom (UK) to match the various Boxes on the UK VAT return.. "VAT Standard Rate Scheme - Structure of VAT Accounts in the Chart of Accounts"*

Create Tax accounts (Tax Codes)

To create a new Tax account (Tax Code):

1. On the Setup ribbon, select Setup → Accounts. The *Accounts* screen; listing your available accounts will be displayed.

2. Select the Tax Control account (as in this case, "*G860-000 VAT Control account*").



2. Click on the (Add:Account) icon (or select the Add on the context menu). An entry for the new Ledger account is displayed (e.g. "*G850 000 Account name*" on the Account list. The Tax code is a Sub-account for the Tax main account (i.e. " *VAT Control account*").

3. Enter or select the following:

   a) Account type - Select "*Tax account*".

   b) Account no. - The Main account "*860*" is displayed and cannot be edited. Type "*040*" in the sub-account field.

   c) Description - Replace *Account name* with the new Tax code description e.g. "*Zero-rated VAT –*

0%".

d) Account group 1 - "*Current liabilities*" should be displayed. This is the Account group which is linked to the Main account.

e) Account group 2 - Select Account group 2, if not selected.

f) Account type - "*Balance sheet*" should be displayed. This field cannot be selected, since the Main account is a Balance sheet account type.

g) Sub-accounts - This field cannot be selected, since this is a sub-account.

h) Status - "*Enabled*" (default) should be selected.

i) Open item account - "*No*" (default) should be selected.

4. Click on the Tax tab.

   a) Enter the Percentage "*0*" for the purposes of this example.

   b) Use Link Tax - To be advised.

   c) Show tax in documents - To be advised.

5. Click on the Save button. The account will automatically be placed in the correct structure of the Account list.

The icon will change from *(Assets / Liabilities) to* *(Tax account).*

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Delete accounts

You may delete a ledger (income/expense, bank or tax) account if the account has no transactions and/or balances.

You may disable a ledger (income/expense, bank or tax) account to block (prevent) posting of any documents or batch transactions for the ledger (income/expense, bank or tax) account.

Delete accounts

The *Delete icon (option) will not be available for the following accounts:*

- *Accounts which has any transactions processed (posted). The Posted field display a value of more than 0.*
- *The* *Retained income / earnings account.*
- *The* *Delete icon (option) is available for* *Debtor's control account and* *Creditor's control account. Trying to delete these control accounts, will produce an Error message:*

"You cannot delete a control account!".

To delete a Ledger (Income/Expense, Bank or Tax) account:

1. On the Setup ribbon, select Setup → Accounts.
2. Select the account, and click on the Delete icon. A confirmation message will be displayed.

"Do you want to delete?"

3. Once again, make sure it is absolutely the correct ledger (income/expense, bank or tax) account.
4. Click on the Yes button. This will permanently remove the ledger (income/expense, bank or tax) account.

Delete Main accounts:

If an account has sub-accounts, you first need to delete the sub-accounts, before you can delete the main account.

Delete Bank accounts:

If a Bank account is deleted, you may need to delete the Payments and Receipt batches (Setup → Batch types (Setup ribbon).

Disable accounts

To disable a Ledger (Income/Expense, Bank or Tax) account:

If a ledger (income/expense, bank or tax) account has transactions and/or balances, you cannot delete it. In the "*Posted*" field, the number of transactions processed (posted) for the selected account will be displayed. Once any transactions have been processed (posted) (the value is more than 0), you will not be allowed to delete the account.

1. On the Setup ribbon, select Setup → Accounts.
2. Select the account.
3. Select Disabled in the "*Status*" field and click on the Save button. This will block posting of any documents or batch transactions for the ledger (income / expense, bank or tax) account.
4. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Effortlessly Create Encrypted, Password-Protected PDFs

Export / Import - General ledger accounts

You may export and import general ledger accounts (chart of accounts).

This feature may be used to import ledger accounts (chart of accounts) into:

- Into the same Set of Books.
- Into a different Set of Books.
- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types.
- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

Before you may import ledger accounts in a new Set of Books, you need to do the necessary setup and configuration.

Once this is done, you may start to import ledger accounts from a saved "Excel Workbook (.xlsx) file type or from a saved the "Tab delimited" (*.txt) file.*

These accounts (Chart of Accounts) are maintained in Setup → Accounts (Setup ribbon).

Reports for the accounts (Chart of Accounts) are printed in Reports → Ledger → Listing - Chart of Accounts (Reports ribbon).

Before using this feature, it is recommended to print the report.

Export / Import options on Setup ribbon

To be able to import the data for Account records, you need to created a "*Tab delimited*" export file in the Export (Setup ribbon).

It is recommended that the accounts (chart of accounts) is exported in the "*Tab delimited*" (*.txt) file format. This file format may be used to import the "*Tab delimited*" (*.txt) file format in the Import (Setup ribbon).

Spreadsheet export / import

osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx)* file type Spreadsheet import and export feature.

- Spreadsheet export - You may export ledger accounts and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import ledger accounts from a saved "*Excel Workbook (*.xlsx) file type.*

Created with the Standard Edition of HelpNDoc: Maximize Your PDF Protection with These Simple Steps

Export General ledger accounts (Setup ribbon)

All the information of each account, as entered in Setup → Accounts (Setup ribbon) (includes specific data for general ledger, bank and tax accounts), will be exported in the selected file format.

It is recommended that the accounts (chart of accounts) is exported in the "*Tab delimited*" (*.txt) file format. This file format may be used to import the "*Tab delimited*" (*.txt) file format in the Import (Setup ribbon).

It is recommended to print the report from the source Set of Books (Reports → Ledger → Listing - Chart of Accounts (Reports ribbon).

Disabled accounts (Status set as Disabled) will be included in the export file.

After importing the general ledger accounts, all inactive ("Disabled") accounts will be imported as active ("Enabled"). After Import you need to decide whether to keep them as active accounts or do the following in Setup → Accounts (Setup ribbon):

- *Set the status as inactive ("Disabled").*

- *Delete the Accounts*

To export accounts from a Set of Books:

1. On the Setup ribbon, select Export.

2. Click on the Accounts button.



3. Select and/or enter the following:

   a) Export to - The installation directory in which osFinancials5/TurboCASH5 is installed, will be displayed. You may click on the Browse icon to select a folder on the "*Browse for Folder*" screen. You may then select any available folder, or drive, on your system into which you wish to export the data.

   b) File type - Select to export the file in the XML Database (*XML), Comma Separated Variable (*CSV), Lotus Spreadsheet file (*WK1), MS Excel Spreadsheet (*XLS), or any other format available on your system from the list.

> *It is recommended that the "(*.txt) Tab delimited" file type is selected to Import general ledger accounts.*

It will create the following export file types for the export file name:

**.txt - Tab delimited text file - Recommended for Import on the Setup ribbon.*

**.slk - Can be opened in spreadsheets of LibreOffice, OpenOffice or UltraOffice). You may save it as a a Microsoft Excel file.*

**.xml - Can be opened in your system's default web browser or Notepad.*

c) Export files name - Enter the File name. You need to select this file at a later stage when you wish to import the file, or analyse the data in a spreadsheet.

d) Log file - Enter the Log file name.

e) Range - From / To - The Accounts lookup will be automatically initiated. Select any range of accounts to include in the export file.

f) Increment Export - Leave this option blank.

4. Click on the Export button to create the export file, and save it in the specified directory.

The information for the General ledger accounts, which will be exported, is:

- *Account ID (Ledger account, Bank or Tax account).*
- *Description or name of account.*
- *Account code.*
- *Income / Expense or Balance sheet indicator.*
- *Sub-Accounts Indicator.*
- *Account Reporting groups 1 and 2.*
- *Start and End Dates (only applicable to Tax (VAT/GST/Sales Tax) accounts).*
- *Rate - percentage (only applicable to Tax (VAT/GST/Sales Tax) accounts).*
- *Receipts and payments batch (only applicable to Bank accounts).*

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Import General ledger accounts (Setup ribbon)

This option will allow you to import data for Account records from a valid file format into an existing Set of Books.

To be able to import the data for Account records, you need to have created a "*Tab delimited*" (*.txt) export file in the Export (Setup ribbon).

To import accounts into a Set of Books:

1. On the Setup ribbon, select Import.



2. Select Accounts as the "*Data type to import*".

3. Select the "*Tab delimited*" (recommended) file type to import.

> *Other file types created with the export as "Tab delimited" file type, is SLK, XML Database File (*.XML), which is stored in your exported folder.*

> *Other available file types, is:" (*.TXF) TurboCASH Exchange File , (*.WK1) Lotus Spreadsheet File, (*.Xml) Xml Database, Comma separated values" and "Windows list separator values".*

4. Click on the >> button to locate the data file.



5. Click on the button to locate the data file.

Optional - You may click on the View file button to view the file in your system's default app (program) associated with th

An example of the exported Tab Delimited text file is as follows:



Export-Accounts-Tab-delimited.txt - Notepad

File Edit View

```
WACCOUNTTYPEID    SDESCRIPTION       SACCOUNTCODE       BINCOMEEXPENSE     BSUBACCOUNTS       BOPENITEM BINACTIVE SGroup1
0       "Sales"   "G010000" 1       0                            "Income"  "Income2"                              ""
0       "Cost of sales"     "G100000" 1       0                            "Income"  "Income2"
0       "Bank charges"      "G200000" 1       0                            "Expenses"         "Expenses2"
0       "Depreciation"      "G205000" 1       0                            "Expenses"         "Expenses2"
0       "Motor vehicle expenses"    "G210000" 1       1                            "Expenses"         "Expenses2"
0       "Fuel and oil"      "G210010" 1       0                            "Expenses"         "Expenses2"
0       "Maintenance"       "G210020" 1       0                            "Expenses"         "Expenses2"
0       "Repairs" "G210030" 1       0                            "Expenses"         "Expenses2"
0       "Maintenance of tools"      "G215000" 1       0                            "Expenses"         "Expenses2"
0       "Rent"    "G220000" 1       0                            "Expenses"         "Expenses2"
0       "Salaries and wages"        "G225000" 1       0                            "Expenses"         "Expenses2"
0       "Stationery"        "G230000" 1       0                            "Expenses"         "Expenses2"
0       "Sundry expenses"   "G235000" 1       0                            "Expenses"         "Expenses2"
0       "Capital" "G505000" 0       0                            "Capital" "Capital2"
0       "Retained income"   "G510000" 0       0                            "Capital" "Capital2"
0       "Installment agreements"    "G520000" 0       0                            "Longterm liabilities"       "Longterm
0       "Furniture & fittings - Net value"    "G600000" 0       1                            "Fixed assets"     "Fixed ass
0       "Furniture  fittings @ cost"  "G600010" 0       0                            "Fixed assets"     "Fixed assets2"
0       "Furniture  fittings -Acc. deprec."   "G600020" 0       0                            "Fixed assets"     "Fixed ass
0       "Motor vehicles - Net value"  "G610000" 0       1                            "Fixed assets"     "Fixed assets2"
0       "Motor vehicles @ cost"     "G610010" 0       0                            "Fixed assets"     "Fixed assets2"
0       "Motor vehicles -Accum. depreciation"  "G610020" 0       0                            "Fixed assets"     "Fixed ass
0       "Debtors control"   "G700000" 0       1                            "Current assets"   "Current assets2"
0       "POS - Transfer"    "G735000" 0       0                            "Current assets"   "Current assets2"
0       "POS - Till"        "G740000" 0       0                            "Current assets"   "Current assets2"
0       "POS - Payment"     "G745000" 0       0                            "Current assets"   "Current assets2"
0       "Stock control"     "G750000" 0       0                            "Current assets"   "Current assets2"
3       "ABC - Bank"        "B810000" 0       0                            "Current assets"   "Current assets2"
3       "Petty cash"        "B820000" 0       0                            "Current assets"   "Current assets2"
3       "XYZ-Bank"          "B830000" 0       0                            "Current assets"   "Current assets2"
0       "VAT - Control - 14%"       "G850000" 0       1                            "Current liabilities"       "Current
4       "Output VAT - 14%"  "T850010" 0       0                            "Current liabilities"       "Current liabilitie
4       "Input VAT - Standard rate - 14%"     "T850020" 0       0                            "Current liabilities"
4       "Input VAT - Capital goods - 14%"     "T850030" 0       0                            "Current liabilities"
4       "Zero-rated VAT - 0%"       "T850040" 0       0                            "Current liabilities"       "Current
0       "VAT - Payment - 14%"       "G850100" 0       0                            "Current liabilities"       "Current
0       "VAT - Control - 15%"       "G860000" 0       1                            "Current liabilities"       "Current
4       "Output VAT - 15%"  "T860010" 0       0                            "Current liabilities"       "Current liabilitie
4       "Input VAT - Standard rate -15%"      "T860020" 0       0                            "Current liabilities"
4       "Input VAT - Capital goods -15%"      "T860030" 0       0                            "Current liabilities"
4       "Zero-rated VAT - 0%"       "T860040" 0       0                            "Current liabilities"       "Current
0       "VAT - Payment - 15%"       "G860100" 0       0                            "Current liabilities"       "Current
0       "Creditors control" "G900000" 0       1                            "Current liabilities"       "Current liabilitie
0       "Suspense"          "G999000" 0       0                            "Current liabilities"       "Current liabilitie
```

Ln 46, Col 1

6. Click on the button.



7. Click on the Import button. The "*ImportCheck*" screen is displayed:



WACCOUNTTYPE	SDESCRIPTION	SACCOUI	BINCOMEE	BSUBACCO	BOPENITEM	BINACTIVE	SGroup1
3	ABC - Bank	B810000	0	0			Current assets
3	Petty cash	B820000	0	0			Current assets
3	XYZ-Bank	B830000	0	0			Current assets
0	Sales	G010000	1	0			Income
0	Cost of sales	G100000	1	0			Income
0	Bank charges	G200000	1	0			Expenses
0	Depreciation	G205000	1	0			Expenses
0	Motor vehicle expenses	G210000	1	1			Expenses
0	Fuel and oil	G210010	1	0			Expenses
0	Maintenance	G210020	1	0			Expenses
0	Repairs	G210030	1	0			Expenses
0	Maintenance of tools	G215000	1	0			Expenses
0	Rent	G220000	1	0			Expenses
0	Salaries and wages	G225000	1	0			Expenses
0	Stationery	G230000	1	0			Expenses
0	Sundry expenses	G235000	1	0			Expenses

You may use the record buttons to add, delete or change the accounts on the "ImportCheck" screen. You may then click on the All or OK buttons to import the accounts.

The values of the data in the "ImportCheck" screen, listing the general ledger accounts, is as follows:

- *ACCOUNTTYPEID - Account type - 0=General ledger, 3=Bank accounts and 4=Tax accounts.*
- *SDESCRIPTION - Account description (Name).*
- *SACCOUNTCODE - Account number (Code).*

W *BINCOMEEXPENSE - 1=Income / Expenses, 2=General ledger (Tax and Bank accounts is by default a Balance sheet Account).*

W *BSUBACCOUNTS - 1=Sub-accounts, 0=No Sub-accounts.*

W *BOPENITEM - Column values is blank.*

W *BINACTIVE - Column values is blank.*

W *SGroup1 - Account group 1 Description*

W *SGroup2 - Account group 2 Description*

W *DSTARTDATE - Start Date - (only applicable to Account type 4 only (i.e. Tax accounts)).*

W *DENDDATE - End Date - (only applicable to Account type 4 only (i.e. Tax accounts)).*

W *FRATE - Tax Rate (Percentage) - (only applicable to Account type 4 only (i.e. Tax accounts)).*

W *SReceipt - Receipts journal - (only applicable to Account type 3 only (i.e. Bank accounts)).*

W *SPayment - Payments journal - (only applicable to Account type 3 only (i.e. Bank accounts)).*

W *SCurrency - Currency (Not used).*

BOPENITEM column is blank. All accounts for which the "Open item account" was set as "Yes" is set to "No" is blank. This will import any Open accounts as normal accounts.

You may need to identify and set these accounts as a "Open item account".

BINACTIVE column is blank. All accounts for which the "Status" is set to "Disabled" is blank. This will import any "Disabled (inactive) accounts as "Enabled" (active) accounts.

You need to Delete these accounts; or set them as "Disabled" (inactive) after importing these accounts.

Bank accounts - WACCOUNTTYPEID column is "3". If Bank accounts is imported, it will create Payments bathes and/or Receipt batches for each bank account depending on the Default bank reconciliation method setting (Setup - System parameters on the Setup ribbon).

You may select to delete the Bank accounts on the "ImportCheck" screen.

If these Bank accounts is not deleted on the "ImportCheck" screen, it will import the Bank accounts, as well as the Payments bathes and/or Receipt batches associated with each of the Bank accounts.

You may then need to delete these Bank accounts, as well as its associated Payments bathes and/or Receipt batches associated with each of the Bank accounts and create (add) your own Bank accounts and associated Payments bathes and/or Receipt batches.

8. Once the import process is finished an information message will be displayed.

   "Data file import completed!"

9. Click on the OK button.

10. Go to the Reports ribbon and select Reports → Ledger → Listing menu to check that the ledger accounts are correct.

Blocked accounts - If accounts status is set to disabled, these accounts will be imported. Note the status of disabled accounts is set to enabled. For example, if you have changed the Tax rates, and do not wish to use these old accounts, you may delete these accounts or disable them.

The Reporting groups for Account groups 1 and Account group 2, will also be imported in the Setup → Groups.

11. If you need to edit the ledger accounts, go to the Setup ribbon and select Accounts.

After Import

Link Account group 1 / Account group 2 to Financial categories

If Account group 1 and or Account group 2 is imported into your Set of Books, these Account groups should be linked to the imported general ledger accounts in Setup → Accounts (Setup ribbon).

These Account groups may not be linked to the 5 Financial categories (i.e. Assets, Liabilities, Capital, Income and Expenses).

You may need to link the Account groups to the Financial categories (on the Setup ribbon) in the following two (2) options:

1. Setup → Financial categories.
2. Setup → Accounts.

The basic account groups should already be included in your imported Set of Books, and you may add, edit or delete any of these groups in Setup → Groups on the Account group 1 and/or Account group 2, before linking them to financial categories.

The sequence in which the groups and accounts are listed, may be changed by selecting the groups on the list and use the Move up or Move down buttons.

This will enable you to structure your general ledger reports (i.e. Trial balance, Income statement, Balance sheet, Chart of Accounts), according to your specific reporting needs.

Disabled (Inactive) Accounts

If the status of Accounts were set as Disabled in the source Set of Books from which the Export file was exported, the Disabled accounts will be imported as "Enabled". You may need to:

- Delete the "*Disabled*" accounts, if you do not wish to keep these accounts; or
- Keep the Status of these Accounts as "Enabled" (active); or set the Status of these Accounts as "*Disabled*" (inactive).

Tax (VAT/GST/Sales tax) Accounts / Codes

It is important to check the Tax (VAT/GST/Sales tax accounts and Tax percentages, before you process any transactions in batches and/or documents.

Recreate Tax (VAT/GST/Sales tax) codes with missing Tax tab

The Tax tab on the first Tax code (e.g. Output VAT - 14% (T850010) and Output VAT - 15% (T850010) is missing after Import.



Select the Tax code (e.g. T860010) and Copy the Description (e.g. Output VAT - 15%) to your clipboard.

Click on the Delete icon.

Select the Tax control account (e.g. VAT - Control - Output VAT - 15%) (main account).

Click on the Add icon.



A new Ledger account will be added. Select the following:

- Account type - Select Tax.
- Account number - Change the "000" in the Sub-account section with "010". You may use the same sub account code as the deleted Tax account.
- Description - Enter the name of your Output tax account (or paste from your clipboard).
- Account group 2 - If Account group 2 is used in the in the other accounts, you need to reselect Account group 2.
- On the Tax tab, enter the Tax percentage (e.g. 15) and click on the Save button.

The Account name will change to "*Output VAT - 15%*" (as in this example) and the Ledger icon will change to the Tax icon.

Zero -rated Tax (VAT/GST/Sales tax) accounts - Confirm Zero percentage

Zero- rated Tax (VAT/GST/Sales tax) with a Tax percentage of "*0%*" may be blank.

On the Tax codes - Tax rates report (User reports → Tax on the Reports ribbon), Tax percentages with a

zero-rate will be Imported as a blank percentage.

This may cause the Zero rated Tax (VAT/GST/Sales tax) selected in processing transactions in Batches and/or Documents not to display correctly on Tax reports.



To fix this; select the Zero-rated Tax (VAT/GST/Sales tax) account.

Overtype the Tax percentage with "*0*" and click Save.



After confirming Zero-rated "0" tax percentages (tax rates) the Tax rates should be correctly listed as "*0*" percentage.



Delete / Add Bank Accounts

If Bank accounts is imported, it will create a Payments batch/ Receipts batch for each Bank account / Petty Cash account.

It is recommended that the Bank Accounts, as well as the Imported batch types be deleted and recreated.

If a blank Set of Books was created; using the "*Customise your own Set of Books (Advanved)?*" option on the "Creation wizard", the setting for the Bank import plugin, will be activated. This means, that by default, the "*Default bank reconciliation method*" option is not selected (Setup → System parameters) and the Bank account will be linked to a combined Payments and Receipt batch.



If you do not wish to use the Bank import plugin, to import bank statements, (and manually process bank transactions is a separate Payments batch and Receipts batch), the "*Default bank reconciliation method*" option is need to be selected (Setup → System parameters).



Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Open exported text file - Spreadsheet

To illustrate the exported fields and data, the exported text file is opened in a spreadsheet.

Once the text file is saved, you need to launch your spreadsheet application i.e Excel, OpenOffice, LibreOffice, Ultra Office, etc.

If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.

*If the exported Text (*txt) file is opened (active), and you are trying to open the export file with the same name, a similar error message as the following will be displayed:*

> Cannot create file "D:\Export\Export.txt"

The process cannot access the file because it is being used by another process.

On your spreadsheet application, open the accounts saved text (*.txt) file and confirm your tab delimited settings ("*Separator Options*") on the "*Text Import*" screen.



This will open your exported text file of the accounts in a spreadsheet. An example of the exported file opened in "*LibreOffice Calc*" spreadsheet, is as follows:



WACCOUNTTYPEID	SDESCRIPTION	SACCOUNTCODE	BINCOMEEXPENSE	BSUBACCOUNTS	BOPENITEM	BINACTIVE	SGroup1	SGroup2	DSTARTDATE	DENDDATE	FRATE	SReceipt	SPayment	SCurrency
0	Sales	G010000	1	0			Income	Income2						
0	Cost of sales	G100000	1	0			Income	Income2						
0	Bank charges	G200000	1	0			Expenses	Expenses2						
0	Depreciation	G205000	1	0			Expenses	Expenses2						
0	Motor vehicle expenses	G210000	1	1			Expenses	Expenses2						
0	Fuel and oil	G210010	1	0			Expenses	Expenses2						
0	Maintenance	G210020	1	0			Expenses	Expenses2						
0	Repairs	G210030	1	0			Expenses	Expenses2						
0	Maintenance of tools	G215000	1	0			Expenses	Expenses2						
0	Rent	G220000	1	0			Expenses	Expenses2						
0	Salaries and wages	G225000	1	0			Expenses	Expenses2						
0	Stationery	G230000	1	0			Expenses	Expenses2						
0	Sundry expenses	G235000	1	0			Expenses	Expenses2						
0	Capital	G505000	0	0			Capital	Capital2						
0	Retained income	G510000	0	0			Capital	Capital2						
0	Installment agreements	G520000	0	0			Longterm liabilities	Longterm liabilities2						
0	Furniture & fittings - Net value	G600000	0	1			Fixed assets	Fixed assets2						
0	Furniture fittings @ cost	G600010	0	0			Fixed assets	Fixed assets2						
0	Furniture fittings -Acc. deprec	G600020	0	0			Fixed assets	Fixed assets2						
0	Motor vehicles - Net value	G610000	0	1			Fixed assets	Fixed assets2						
0	Motor vehicles @ cost	G610010	0	0			Fixed assets	Fixed assets2						
0	Motor vehicles -Accum. depreciatio	G610020	0	0			Fixed assets	Fixed assets2						
0	Debtors control	G700000	0	1			Current assets	Current assets2						
0	POS - Transfer	G735000	0	0			Current assets	Current assets2						
0	POS - Till	G740000	0	0			Current assets	Current assets2						
0	POS - Payment	G745000	0	0			Current assets	Current assets2						
0	Stock control	G750000	0	0			Current assets	Current assets2						
3	ABC - Bank	B810000	0	0			Current assets	Current assets2				ABC-Receipts	ABC-Payments	
3	Petty cash	B820000	0	0			Current assets	Current assets2				Petty cash Rec	Petty cash Pay	
3	XYZ-Bank	B830000	0	0			Current assets	Current assets2				XYZ-Receipts	XYZ-Payments	
0	VAT - Control - 14%	G850000	0	1			Current liabilities	Current liabilities2						
4	Output VAT - 14%	T850010	0	0			Current liabilities	Current liabilities2	30/12/1899	30/12/1899	14			
4	Input VAT - Standard rate - 14%	T850020	0	0			Current liabilities	Current liabilities2	30/12/1899	30/12/1899	14			
4	Input VAT - Capital goods - 14%	T850030	0	0			Current liabilities	Current liabilities2	30/12/1899	30/12/1899	14			
4	Zero-rated VAT - 0%	T850040	0	0			Current liabilities	Current liabilities2			0			
0	VAT - Payment - 14%	G850100	0	0			Current liabilities	Current liabilities2						
0	VAT - Control - 15%	G860000	0	1			Current liabilities	Current liabilities2						
4	Output VAT - 15%	T860010	0	0			Current liabilities	Current liabilities2			15			
4	Input VAT - Standard rate -15%	T860020	0	0			Current liabilities				15			
4	Input VAT - Capital goods -15%	T860030	0	0			Current liabilities				15			
4	Zero-rated VAT - 0%	T860040	0	0			Current liabilities	Current liabilities2			0			
0	VAT - Payment - 15%	G860100	0	0			Current liabilities	Current liabilities2						
0	Creditors control	G900000	0	1			Current liabilities	Current liabilities2						
0	Suspense	G999000	0	0			Current liabilities	Current liabilities2						

The exported data will be exported in 15 columns:

Column	*Column heading*	*Source / fields*	*Remarks*	
A	*WACCOUNTTYPE*	*Account type*	*Ledger / Bank / Tax*	*Integer* *0 = Ledger* *3 = Bank* *4 = Tax*
B	*SDESCRIPTION*	*Description*	*Name (Account description)*	*String (35)*
C	*SACCOUNTCODE*	*Account no.*	*Account code*	*String (6) Prefixed by account type* *G = Ledger* *B = Bank* *T = Tax*
D	*BINCOMEEXP*	*Account type*	*Income statement /*	*List*

	ENSE		*Balance sheet* *(Tax and Bank accounts is by default a Balance sheet Account)*	*1 = Income statement account type* *0 = Balance sheet account type*
E	*BSUBACCOUNTS*	*Sub-accounts*		*B=CheckBox* *1 = Sub accounts (True - checked)* *0 = No sub-accounts (False - not checked)*
F	*BOPENITEM*	*Open item account*	*No / Yes*	*List* *1 = Open item account (Yes - checked)* *0 = Not an Open item account (No - not checked)*
G	*BINACTIVE*	*Status*	*Enabled / Disabled*	*List* *1 = Account disabled (inactive) - (Enabled - selected)* *0 = Account enabled (active) - (Disabled - not selected)*
H	*SGroup1*	*Account group 1*		*String (30)*
I	*SGroup2*	*Account group 2*		*String (30)*
J	*DSTARTDATE*		*Not available to select (only applicable to Tax accounts)*	*Date*
K	*DENDDATE*			*Date*
L	*FRATE*	*Percentage (Tax tab)*	*Only applicable to Tax accounts*	*Float(numeric)*
M	*SReceipt*	*Receipts (Bank tab)*	*Receipts batch (only applicable to Bank accounts)*	

N	*SPayment*	*Payments (Bank tab)*	*Payments batch (only applicable to Bank accounts)*
O	*SCurrency*	*Currency*	

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Import Accounts - Spreadsheet Export / Import

osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx)* file type Spreadsheet import and export feature.

- Spreadsheet export - You may export ledger accounts and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import ledger accounts from a saved "*Excel Workbook (*.xlsx) file type.*

This feature may be used to import ledger accounts into:

- Into the same Set of Books.
- Into a different Set of Books.
- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types.
- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

Before you may import ledger accounts in a new Set of Books, you need to do the necessary setup and configuration.

Once this is done, you may start to import ledger accounts from a saved "Excel Workbook (.xlsx) file type.*

You may access the "*Data Import Export*" feature from the following options:

- Setup → Accounts (Setup ribbon).

- Import option on the Setup ribbon.



Select Accounts as the "*Data type to import*". Click on the Excel import export button. The "*Data Import Export*" spreadsheet will displayed column headings for the Accounts (without any data).

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Markdown Content with HelpNDoc

Spreadsheet - Export - General ledger accounts

This option will allow you to import your Accounts (Chart of accounts) file from a valid an Excel spreadsheet in the Excel Workbook (xlsx) file format. You may then add new accounts, edit existing accounts and import it back into another Set of Books.

Reports for the accounts (Chart of Accounts) are printed in Reports → Ledger → Listing - Chart of Accounts (Reports ribbon).

Before using this feature, it is recommended to print the report.

If you make any changes in the Excel spreadsheet, and Import it, these changes will be reflected.

To import Accounts from a Excel Workbook (xlsx) file:

Select the Set of Books which contains the Accounts (Chart of accounts) you need to export.

To export accounts to a spreadsheet:

1. In the source Set of Books from which you wish to export the Accounts to a spreadsheet file, go to Setup → Accounts (Setup ribbon).

2. Click on the Spreadsheet icon. A blank "*Data Import Export*" spreadsheet will be displayed with the column headings of the "*Accounts*" table.



3. Click on the Export icon on the "*Data Import Export*" screen. All the "*accounts*" (chart of accounts) is exported (populated) in the spreadsheet.



	A	B	C	D	E	F	G	H	I	J	K	L	M	N
1	SACCOUNTC(	SDESCRIPTIC	BINCOMEEXF	BSUBACCOU	BOPENITEM	BINACTIVE	SGROUP1	SGROUP2	DSTARTDATI	DENDDATE	FRATE	SRECEIPT	SPAYMENT	SCURRENCY
2	T	Empty	0	0	0	0	Empty	Empty						
3	G010000	Sales	1	0	0	0	Income	Income2						
4	G100000	Cost of sale	1	0	0	0	Income	Income2						
5	G200000	Bank charge	1	0	0	0	Expenses	Expenses2						
6	G205000	Depreciatio	1	0	0	0	Expenses	Expenses2						
7	G210000	Motor vehic	1	1	0	0	Expenses	Expenses2						
8	G210010	Fuel and oil	1	0	0	0	Expenses	Expenses2						
9	G210020	Maintenanc	1	0	0	0	Expenses	Expenses2						
10	G220000	Rent	1	0	0	0	Expenses	Expenses2						
11	G225000	Salaries an	1	0	0	0	Expenses	Expenses2						
12	G230000	Stationery	1	0	0	0	Expenses	Expenses2						
13	G235000	Sundry expe	1	0	0	0	Expenses	Expenses2						
14	G505000	Capital	0	0	0	0	Capital	Capital2						
15	G510000	Retained in	0	0	0	0	Capital	Capital2						
16	G520000	Installment	0	0	0	0	Longterm lia	Longterm liabilities2						
17	G600000	Furniture &	0	1	0	0	Fixed asset:	Fixed assets2						
18	G700000	Debtors con	0	1	0	0	Current asse	Current assets2						
19	G750000	Stock contro	0	0	0	0	Current asse	Current assets2						
20	B810000	ABC - Bank	0	0	0	0	Current asse	Current assets2				ABC-Receipt	ABC-Payments	
21	G850000	VAT - Contro	0	1	0	1	Current liab	Current liabilities2						
22	T850010	Output VAT	0	0	0	1	Current liab	Current liabilities2			14.00			
23	T850020	Input VAT -	0	0	0	1	Current liab	Current liabilities2			14.00			
24	G850100	VAT - Payme	0	0	0	1	Current liab	Current liabilities2						
25	G900000	Creditors co	0	1	0	0	Current liab	Current liabilities2						
26	G600010	Furniture &	0	0	0	0	Fixed asset:	Fixed assets2						
27	G600020	Furniture &	0	0	0	0	Fixed asset:	Fixed assets2						
28	G610000	Motor vehic	0	1	0	0	Fixed asset:	Fixed assets2						
29	G610010	Motor vehic	0	0	0	0	Fixed asset:	Fixed assets2						
30	G610020	Motor vehic	0	0	0	0	Fixed asset:	Fixed assets2						
31	G215000	Maintenanc	1	0	0	0	Expenses	Expenses2						
32	T850030	Input VAT -	0	0	0	1	Current liab	Current liabilities2			14.00			
33	G999000	Suspense	0	0	0	0	Current liab	Current liabilities2						
34	G735000	POS - Transf	0	0	0	0	Current asse	Current assets2						

4. To save the Spreadsheet export as a file, click on the Save as... icon.



5. The recommended file type is Excel Workbook (*.xlsx).

6. Select the location where you wish to save the spreadsheet file.

7. Enter a name Click the Save button.

8. Close the "*Data Import Export*" spreadsheet screen.

Spreadsheet columns

The data of the exported accounts into the spreadsheet, consists of fourteen (14) columns, and is as follows:

Column		*Field name*	*Values*	*Comments*
	A	*SACCOUNTCODE*	*Account code prefixed by account type:* *G - General ledger* *B = Bank account* *T = Tax account*	*3-Digits for main account and 3-Digits for sub-accounts.*

	B	SDESCRIPTION	Description or name of account	
	C	BINCOMEEXPENSE	0 = Income / Expense account 1 = Balance sheet account	
	D	BSUBACCOUNTS	0 = No Sub-accounts 1 = Has sub accounts	
	E	BOPENITEM	0 = Not set as open item 1 = Open item account	
	F	BINACTIVE	0 = Active 1 = Disabled (inactive)	
	G	SGROUP1	Account Reporting group 1	Description
	H	SGROUP2	Account Reporting group 2	Description
	I	DSTARTDATE	Not applicable	Not imported
	J	DENDDATE	Not applicable	Not imported
	K	FRATE	Tax rate (percentage)	Tax rate - Account code prefix = T
	L	SRECEIPT	Name of Receipts batch linked to the bank account	Account code prefix = B
	M	SPAYMENT	Name of Payments batch linked to the bank account	Account code prefix = B
	N	SCURRENCY		Not imported

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Spreadsheet - Import - General ledger accounts

Select the Set of Books which contains the Accounts (Chart of accounts) you need to export.

This option will allows you to import data for Account records from a valid Excel Workbook (*.xlsx) file format into an existing Set of Books.

To be able to import the data for Account records, you need to create a valid spreadsheet export file in the Excel Workbook (*.xlsx) file format from a Set of Books, you wish to import your system in the Export or Setup → Accounts menu (Setup ribbon).

To import accounts to a spreadsheet:

1. In the Set of Books in which which you wish to import the Accounts to a spreadsheet file, go to Setup → Accounts (Setup ribbon).

2. Click on the Spreadsheet icon. A blank "*Data Import Export*" spreadsheet will be displayed with the column headings of the "*Accounts*" table.



3. Click on the Open icon on the "*Data Import Export*" screen.



4. Locate a valid Excel Workbook (*.xlsx) saved file and click on the Open button. All the "*accounts*" (chart of accounts) included in the exported file is populated in the spreadsheet.



5. To do a import check of the imported file, select (tick) the "*Show data before import*" option and click on the Import check icon.



	A	B	C	D	E	F	G	H	I	J	K	L	M	N
1	SACCOUNTCODE	SDESCRIPTION	BINCOMEEXPE	BSUBACCOU	BOPENITEM	BINACTIVE	SGROUP1	SGROUP2	DSTARTDATE	DENDDATE	FRATE	SRECEIPT	SPAYMENT	SCURRENCY
2	T	Empty	0	0	0	0	Empty	Empty						
16	G520000	Installment agreements	0	0	0	0	Longterm lia	Longterm liabilities2						
17	G600000	Furniture & fittings - Net value	0	1	0	0	Fixed asset	Fixed assets2						
18	G700000	Debtors control	0	1	0	0	Current ass	Current assets2						
19	G750000	Stock control	0	0	0	0	Current ass	Current assets2						
20	B810000	ABC - Bank	0	0	0	0	Current ass	Current assets2				ABC-Rece	ABC-Paym	
21	G850000	VAT - Control - 14%	0	1	0	1	Current liab	Current liabilities2						
22	T850010	Output VAT - 14%	0	0	0	1	Current liab	Current liabilities2			14.00			
23	T850020	Input VAT - Standard rate - 14%	0	0	0	1	Current liab	Current liabilities2			14.00			
24	G850100	VAT - Payment - 14%	0	0	0	1	Current liab	Current liabilities2						
25	G900000	Creditors control	0	1	0	0	Current liab	Current liabilities2						
26	G600010	Furniture fittings @ cost	0	0	0	0	Fixed asset	Fixed assets2						
27	G600020	Furniture fittings -Acc. deprec.	0	0	0	0	Fixed asset	Fixed assets2						
28	G610000	Motor vehicles - Net value	0	1	0	0	Fixed asset	Fixed assets2						
29	G610010	Motor vehicles @ cost	0	0	0	0	Fixed asset	Fixed assets2						
30	G610020	Motor vehicles -Accum. depreciat	0	0	0	0	Fixed asset	Fixed assets2						
31	G215000	Maintenance of tools	1	0	0	0	Expenses	Expenses2						
32	T850030	Input VAT - Capital goods - 14%	0	0	0	1	Current liab	Current liabilities2			14.00			
33	G999000	Suspense	0	0	0	0	Current liab	Current liabilities2						
34	G735000	POS - Transfer	0	0	0	0	Current ass	Current assets2						
35	G740000	POS - Till	0	0	0	0	Current ass	Current assets2						
36	G745000	POS - Payment	0	0	0	0	Current ass	Current assets2						
37	B820000	Petty cash	0	0	0	0	Current ass	Current assets2				Petty cash	Petty cash	
38	G210030	Repairs	1	0	0	0	Expenses	Expenses2						
39	T850040	Zero-rated VAT - 0%	0	0	0	1	Current liab	Current liabilities2			0.00			
40	B830000	XYZ-Bank	0	0	0	0	Current ass	Current assets2				XYZ-Rece	XYZ-Payme	
41	G860000	VAT - Control - 15%	0	1	0	0	Current liab	Current liabilities2						
42	G860100	VAT - Payment - 15%	0	0	0	0	Current liab	Current liabilities2						
43	T860010	Output VAT - 15%	0	0	0	0	Current liab	Current liabilities2			15.00			
44	T860020	Input VAT - Standard rate -15%	0	0	0	0	Current liab	Empty			15.00			
45	T860030	Input VAT - Capital goods -15%	0	0	0	0	Current liab	Empty			15.00			
46	T860040	Zero-rated VAT - 0%	0	0	0	0	Current liab	Current liabilities2			0.00			
47														

Column L - "SRECEIPT" and column N - "SPAYMENT" background is in a Yellow colour. This indicates that special attention is needed with the Receipt batches and Payments batches linked to Bank accounts.

You may proceed with the Import, but need to pay special attention to add and link payments and receipt batches to bank accounts, after the import.

6. Click on the Settings tab.



7. Click on the Import icon.

Optional - Show data before import setting

The "ImportCheck" screen (if the Import the "Show data before import" option was selected (ticked) on the "Data Import Exp
screen) is displayed:



Click on the All or OK buttons to start the import process.



	A	B	C	D	E	F	G	H	I	J	K	L	M	N
1	SACCOUNTCODE	SDESCRIPTION	BINCOMEEXPENSE	BSUBACCOUNTS	BOPENITEM	BINACTIVE	SGROUP1	SGROUP2	DSTARTDATE	DENDDATE	FRATE	SRECEIPT	SPAYMENT	SCURRENCY
2	T	Empty	0	0	0	0	Empty	Empty						
21	G850000	VAT - Control - 14%	0	1	0	1	Current liab	Current liabilities2						
22	T850010	Output VAT - 14%	0	0	0	1	Current liab	Current liabilities2			14.00			
23	T850020	Input VAT - Standard rate - 14%	0	0	0	1	Current liab	Current liabilities2			14.00			
24	G850100	VAT - Payment - 14%	0	0	0	1	Current liab	Current liabilities2						
25	G900000	Creditors control	0	1	0	0	Current liab	Current liabilities2						
26	G600010	Furniture fittings @ cost	0	0	0	0	Fixed asset	Fixed assets2						
27	G600020	Furniture fittings -Acc. deprec.	0	0	0	0	Fixed asset	Fixed assets2						
28	G610000	Motor vehicles - Net value	0	1	0	0	Fixed asset	Fixed assets2						
29	G610010	Motor vehicles @ cost	0	0	0	0	Fixed asset	Fixed assets2						
30	G610020	Motor vehicles -Accum. depreci	0	0	0	0	Fixed asset	Fixed assets2						
31	G215000	Maintenance of tools	1	0	0	0	Expenses	Expenses2						
32	T850030	Input VAT - Capital goods - 14%	0	0	0	1	Current liab	Current liabilities2			14.00			
33	G999000	Suspense	0	0	0	0	Current liab	Current liabilities2						
34	G735000	POS - Transfer	0	0	0	0	Current asse	Current assets2						
35	G740000	POS - Till	0	0	0	0	Current asse	Current assets2						
36	G745000	POS - Payment	0	0	0	0	Current asse	Current assets2						
37	B820000	Petty cash	0	0	0	0	Current asse	Current assets2				Petty cash	Petty cash	
38	G210030	Repairs	1	0	0	0	Expenses	Expenses2						
39	T850040	Zero-rated VAT - 0%	0	0	0	1	Current liab	Current liabilities2			0.00			
40	B830000	XYZ-Bank	0	0	0	0	Current asse	Current assets2				XYZ-Rece	XYZ-Payme	
41	G860000	VAT - Control - 15%	0	1	0	0	Current liab	Current liabilities2						
42	G860100	VAT - Payment - 15%	0	0	0	0	Current liab	Current liabilities2						
43	T860010	Output VAT - 15%	0	0	0	0	Current liab	Current liabilities2			15.00			
44	T860020	Input VAT - Standard rate -15%	0	0	0	0	Current liab	Empty			15.00			
45	T860030	Input VAT - Capital goods -15%	0	0	0	0	Current liab	Empty			15.00			
46	T860040	Zero-rated VAT - 0%	0	0	0	0	Current liab	Current liabilities2			0.00			

8. Once the import process is finalised, Column A will be displayed in a green background colour.

9. Close the "*Data Import Export*" spreadsheet screen. The "*Accounts*" screen will list the imported chart of accounts.

After import

Imports accounts but no Sub accounts, etc. Sub-accounts greyed out but ticked for Main accounts

Imports tax accounts with Tax tabs but no tax percentages.





Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Change Tax rates

This topic is listed to illustrate the process for changes in Tax percentages. Some of the screens, themes and periods are not in line with the rest of the documentation.

Change Tax rates

The Tax authorities may impose changes in the VAT (GST/Sales tax) rates. For example, in South Africa, the South African Revenue Services (SARS), changed the VAT rate from 14% to 15% on 1 April 2018.

References / Resources

SARS - *FAQs: Increase in the VAT rate from 1 April 2018*.

SARS – *Pocket Guide on the VAT rate increase on 1 April 2018*. The following is a list of topics explained in detail:

- RATE CHANGE
- TRANSACTION DATE
- PRICES QUOTED OR ADVERTISED
- AGREEMENTS
- SALES AND BILLING SYSTEMS, ISSUING OF CASH REGISTER SLIPS, TAX INVOICES, DEBIT AND CREDIT NOTES
- RECEIPT OF QUOTES, TAX INVOICES, CASH REGISTER SLIPS DEBIT OR CREDIT NOTES
- IMPORTATION OF GOODS
- ACCOUNTING SYSTEMS
- VAT201 RETURNS
- RATE SPECIFIC RULES

SARS – *VAT201 – Return Example*.

GOLEGAL - *VAT rate increase: What you need to consider*.

Moneyweb - *VAT increase: Practical issues for companies to consider*.

In osFinancials5/TurboCASH5, the VAT accounts need to accommodate two VAT rates.

An invoice may even reflect a rate of 14% and 15% depending if the goods were supplied or services rendered before 31 March 2018 or after 1 April 2018. An example would be where a service provider charges subscriptions in advance April 2018, but usage (e.g. calls) are charged in arrears March 2018.

Configure TurboCASH5 / osFinancials

Tax Accounts

In this example, the VAT rate is based on 14% in March 2018 and increased to 15% in 1 April 2018.

For the transition period and thereafter; it is recommended that a total new structure of Tax accounts (including the 2 Tax ledger accounts (i.e. VAT – Control and VAT – Payment accounts), similar to the14% structure is replicated.

An example of the 14% Tax accounts and the 15% Tax accounts.



This method makes it easier for reporting, managing and processing tax transactions.

Another method is where Tax accounts are added within the existing VAT structure.

See TurboCASH VAT Changeover video

An example to incorporate the Tax (VAT) accounts into the existing structure of the Chart of accounts:

- *T850050 – Output VAT – 15%*
- *T850060 – Input VAT – Standard rate - 15%*
- *T850070 – Input VAT – Capital goods – 15%*

Change the Descriptions of existing Tax Accounts to 14%

Add or Change the Descriptions of the Tax Accounts (i.e. Output - VAT Control, the VAT Payment account, as well as all Tax accounts to 14%) to reflect the existing percentage applicable (until 31 March 2018).

To change the Descriptions of Output and Input tax accounts to 14%:

1. On the Setup ribbon, select Setup → Accounts.

2. Select a Tax account.



3. In the "*Description*" field, add "- *14%*" to "*Output VAT - 14%*".

4. Click the Save button to save the changes. After all the account descriptions is changed, the 14% accounts should display as follows:



Add new VAT - Control and VAT - Payments - 15% accounts

This is only applicable if a new Structure is set for the Tax accounts (i.e. VAT - Control, the VAT - Payment account (as Ledger accounts), as well as all Tax accounts to 15%) to reflect the 15% percentage applicable (as from 1 April 2018).

Add new VAT - Control account at 15% as a Ledger Main account

The VAT – Control – 15% account is the Main account under which the VAT – Payment – 15% as a Ledger

account type as well as Tax account type for each Tax codes (VAT codes) at 15% as well as the Zero-rated Tax codes (VAT codes) will be processed, managed and reported on. Transactions on which the 15% VAT rate is applicable from 1 April 2018, are selected and posted (updated to the ledger).

To Add a new VAT Control as a Ledger Main account for 15%:

1. On the Setup ribbon, select Setup → Accounts.

2. Select the "*REPORTING GROUP ROOT*" and click on the (Add:Account) icon (or select the Add on the Context menu). An entry for the new ledger account is displayed as "*G000 000 Account name*" on the Account list.



3. Enter or select the following:

   a) Account type - Select "*Ledger*".

   b) Account no. - Change "*100*" in the sub accounts field of the "Account no." field to "*860*".

   c) Description - Replace "*Account name*" with "*VAT Control – 15%*".

   d) Account group 1 - If you have set up "*Account group 1*", select your account group e.g.

"*Current liabilities*".

e) Account group 2 - If you have set up "*Account group 2*", select your account group e.g. "*Current liabilities2*".

f) Type - "*Balance sheet*" should be displayed.

g) Sub accounts - Select (tick) this option. This is the new main account under which a Ledger sub account for the Tax payments and Tax accounts for each of VAT accounts will be added for the 15%.

h) Status -"*Enabled*" (default) should be selected.

i) Open item account - "*No*" (default) should be selected.

j) Link tax - "*Empty*" (default) should be selected.

4. Click on the Save button. When you save the "*VAT - Control - 15%*" account, if will automatically be listed after the 14% Tax accounts.

Add new VAT Payment account at 15% as a Ledger Sub account

The VAT – Payment – 15% as a Ledger account type on which the payment to SARS is recorded. All payments to SARS for transactions, on which the 15% VAT rate is applicable from 1 April 2018, should be paid and recorded in the from this VAT – Payment – 15% account.

All payments to SARS for transactions, on which the 14% VAT rate is applicable on or before 31 March 2018, should be paid and recorded in the VAT – Payment – 14% account.

To Add a new VAT Payment - Ledger Sub account for 15%:

1. On the Setup ribbon, select Setup → Accounts.

2. Select the "*G860000" VAT Control – 15%*" account and click on the (Add:Account) icon (or select the Add on the Context menu). An entry for the new ledger account is displayed as "*G860 000 Account name*" on the Account list.



3. Enter or select the following:

    a) Account type - Select "*Ledger*".

    b) Account no. - The main account "*860*" in the of the "*Account no.*" field cannot be changed. Change the "*Sub accounts*" field from "*000*" to "*100*".

    c) Description - Replace "*Account name*" with "*VAT - Payment – 15%*".

    d) Account group 1 - If you have set up "*Account group 1*", select your account group, e.g. "*Current liabilities*".

    e) Account group 2 - If you have set up "*Account group 2*", select your account group, e.g. "*Current liabilities2*".

    f) Type - "*Balance sheet*" should be displayed.

    g) Sub accounts - This option cannot be selected, since this is a sub account of the VAT - Control - 15% main account.

    h) Status -"*Enabled*" (default) should be selected.

    i) Open item account - "No" (default) should be selected.

    j) Link tax - "*Empty*" (default) should be selected.

4. Click on the Save button.

Add new Tax codes (Tax accounts) for Each Tax type at 15%.

Your Set of Books in TurboCASH need to be configured to is able to accommodate the different rates. Transactions need to be processed at the new VAT rate of 15% as from 1 April 2018, and at VAT rate of 14% as up to 31 March 2018.

All "*Enabled*" Tax / VAT codes are listed in the Tax lookup in the "*Tax*" column. Transactions are taxable at the VAT rate of 14% up to 31 March 2018, and transactions as from 1 April 2018 are taxable at the VAT rate of 15%.



To Add a VAT accounts – Tax Sub account for 15%:

1. On the Setup ribbon, select Setup → Accounts.

2. Select the Tax Control Account (as in this case, "*G860-000 VAT Control Account*") and click on the (Add:Account) icon (or select the Add option on the Context menu).

3. An entry for the new ledger account is displayed as "*G860 000 Account name*" on the Account list. The reason for this is that we need to create a Tax code, which is a Sub-account for the Tax main account (i.e. "*VAT Control – 15% account*").



4. Enter or select the following:

   a) Account type - Select “Tax (VAT/GST/Sales tax)”.

   b) Account no. - The Main account “*860*” is displayed and the sub accounts number field enter “*010*”.

   c) Description - Replace “*Account name*” with “*Output VAT – 15%*”.

   d) Account group 1 - If you have set up “*Account group 1*”, select your account group, e.g. “*Current liabilities*”. This is the Account group which is linked to the main account.

   e) Account group 2 - If you have set up “*Account group 2*”, select your account group, e.g. “*Current liabilities2*”. This is the Account group which is linked to the main account.

   f) Type - “*Balance sheet*” should be displayed. This field cannot be selected, since the main account is a Balance sheet type account.

   g) Sub-accounts - This field cannot be selected, since this is a sub-account.

   h) Status - “*Enabled*” (default) should be selected.

   i) Open item account - “No” (default) should be selected.

j) Link tax - “Empty” (default) should be selected.

5. Click on the Tax tab.

a) Percentage - Enter the percentage as “*15*”.

b) Use link tax - Do not select this option.

c) Show tax in documents – Leave the option as “*All*” for the purpose of this tutorial.

6. Click on the Save button.

Add new Tax type accounts at 15% similar to the 14% tax type accounts, including the Zero-rated tax type accounts

An example of the Tax accounts - 14% as well as the Tax accounts - 15%, in the Chart of accounts, is as follows:



Stock items

Each Stock item is linked to up to 5 accounts, i.e. the Input tax, Output tax, Sales, Cost of sales and Stock control accounts. The Output and Input Tax at the 15% Vat rate needs to be linked to each Stock item.

Tax classes in Stock - create a new Tax class

To save time to select up to 5 accounts, for each stock type, use Tax classes in Stock to link the Input tax, Output tax, Sales, Cost of sales and Stock control accounts.

To create a new Tax class:

1. On the Setup ribbon, select Stock information.

2. Click on the Tax classes tab.

If “English” as the default language is used, Tax classes will be displayed.

If you have selected, "en-South-Africa" the Tax classes description, will reflect VAT classes.



3. Select the existing Tax class and add 14% to the Name field, if not displayed as 14%.
4. Click to save the changes.
5. Click to add a new Tax class.
6. Enter the Name (description) e.g. "*Standard rate 15%*" for the tax class.
7. Select the following accounts:
    a) Input Tax - Select the Input tax account, i.e. Input VAT – Standard rate – 15% (*860-020*).
    b) Output Tax - Select the Output tax account, i.e. Output VAT – 15% (*860-010*).
    c) Sales account - Select the Sales account (*010-000*).
    d) Cost of sales - Select the Cost of sales account (*100-000*).
    e) Stock control - Select the Stock control account (*750-000*).
8. Click to save the changes.
9. Click on the OK button to close the "*Stock information*" screen.

Print a list of the Tax classes

When a stock item is linked to a tax class, it will disable the Lookup button on the Ledger tab of the Stock

items screen (Default ribbon) for a selected stock item. It will automatically set the Input tax and Output tax, Sales, Cost of sales and Stock control account fields without having to select them for each stock item.

To print Stock item listing - Tax classes reports:

1. On the Reports ribbon, select Reports → Stock → Stock item listing.
2. Select "*Tax classes*" report.



3. Select the Sequence (i.e. ID (record Id) or description) for the sequence to list the tax classes.
4. Click on the OK button.

An example of the Stock item listing - "*Tax class - Listing*" report, is as follows:





The next step is to link the accounts to the stock items.

Link Tax classes to Stock items

To change Input and Output tax accounts from 14% to 15%:

1. On the Default ribbon, select Stock items.
2. Select a Stock item.
3. Click on the Ledger tab.



4. Tax class, select "*Standard rate 15%*".
5. Click on the Save button. The inclusive amount will automatically be updated with the new tax rate.



6. Repeat the process for all the stock items.

You may also change the tax classes on the grid view. In this example, the Tax class column was dragged from the Right to the



Select the Stock item and Tax class Standard rate 15% and click on the Save button.

Repeat the process for all the stock items.

Disable / Block posting transactions at the 14% VAT rate

Once all the 14% taxable transactions is processed and finalised, you may:

- Disable the tax accounts to prevent any transactions being posted (updated) to the ledger, to the 14% tax accounts, or available for selection on lookup screens and lists, while entering transactions in Batches and Documents, and/or;
- Block the Period March 2018 in which the 14% tax rate is applicable. This will not allow you to post (update) any transactions to the ledger at at the 14% Tax rate.

Disable Tax accounts at 14%

If the "*Status*" field of a ledger account is set to "*Disabled*" for a ledger account (Setup ribbon, select Setup → Accounts), it will not allow you to post (update) the batch or document to the ledger.

Before you disable old tax accounts at 14%, make absolutely sure that the taxable transactions at 14%, is correct and posted (updated) to the ledger. All purchase documents (i.e. Purchases and Supplier returns), as well as sales documents (i.e. Invoices and Credit notes) is correct and posted (updated) to the ledger at the Tax rate of 14%.

To disable Input and Output tax accounts from 14%:

1. On the Setup ribbon, select Setup → Accounts.
2. Select a Tax account.



3. In the “*Status*” field, select “*Disabled*”.

4. Click the Save button to save the changes.

Print or view Disabled accounts

On the Reports ribbon, select Reports → Ledger → Chart of accounts. The Disabled accounts is displayed as "*Yes*" in the "*Disabled*" column.



From account: G010000 To: G999000

Sequence: Account

Code	Description	Reporting group 1	Reporting group 2	Type	Open item	Disabled
*G010000	Sales	Income	Income2	Inc / Exp	No	No
*G100000	Cost of sales	Income	Income2	Inc / Exp	No	No
*G200000	Bank charges	Expenses	Expenses2	Inc / Exp	No	No
*G205000	Depreciation	Expenses	Expenses2	Inc / Exp	No	No
*G210000	Motor vehicle expenses	Expenses	Expenses2	Inc / Exp	No	No
*G210010	Fuel and oil	Expenses	Expenses2	Inc / Exp	No	No
*G210020	Maintenance	Expenses	Expenses2	Inc / Exp	No	No
*G210030	Repairs	Expenses	Expenses2	Inc / Exp	No	No
*G215000	Maintenance of tools	Expenses	Expenses2	Inc / Exp	No	No
*G220000	Rent	Expenses	Expenses2	Inc / Exp	No	No
*G225000	Salaries and wages	Expenses	Expenses2	Inc / Exp	No	No
*G230000	Stationery	Expenses	Expenses2	Inc / Exp	No	No
*G235000	Sundry expenses	Expenses	Expenses2	Inc / Exp	No	No
G505000	Capital	Capital	Capital2		No	No
G510000	Retained income	Capital	Capital2		No	No
G520000	Installment agreements	Longterm liabilities	Longterm liabilities2		No	No
G600000	Furniture & fittings - Net value	Fixed assets	Fixed assets2		No	No
G600010	Furniture fittings @ cost	Fixed assets	Fixed assets2		No	No
G600020	Furniture fittings -Acc. deprec.	Fixed assets	Fixed assets2		No	No
G610000	Motor vehicles - Net value	Fixed assets	Fixed assets2		No	No
G610010	Motor vehicles @ cost	Fixed assets	Fixed assets2		No	No
G610020	Motor vehicles -Accum depreciation	Fixed assets	Fixed assets2		No	No
G700000	Debtors control	Current assets	Current assets2		No	No
G735000	POS - Transfer	Current assets	Current assets2		No	No
G740000	POS - Till	Current assets	Current assets2		No	No
G745000	POS - Payment	Current assets	Current assets2		No	No
G750000	Stock control	Current assets	Current assets2		No	No
B810000	ABC - Bank	Current assets	Current assets2	Bank account	No	No
B820000	Petty cash	Current assets	Current assets2	Bank account	No	No
B830000	XYZ Bank	Current assets	Current assets2	Bank account	No	No
G850000	VAT - Control - 14%	Current liabilities	Current liabilities2		No	Yes
T850010	Output VAT - 14%	Current liabilities	Current liabilities2	Tax account	No	Yes
T850020	Input VAT - Standard rate - 14%	Current liabilities	Current liabilities2	Tax account	No	Yes
T850030	Input VAT - Capital goods - 14%	Current liabilities	Current liabilities2	Tax account	No	Yes
T850040	Zero-rated VAT - 0%	Current liabilities	Current liabilities2	Tax account	No	Yes
G850100	VAT - Payment - 14%	Current liabilities	Current liabilities2		No	Yes
G860000	VAT Control - 15%	Current liabilities	Current liabilities2		No	No
T860010	Output VAT - 15%	Current liabilities	Current liabilities2	Tax account	No	No
T860020	Input VAT - Standard rate - 15%	Current liabilities	Current liabilities2	Tax account	No	No

Disabled Tax accounts will not be listed on the Tax account lookup in Batches



Disabled Tax accounts will not be listed on the Tax account lookup in Documents



Disable posting to period March 2018

Block the Period March 2018 in which the 14% tax rate is applicable. This will not allow you to post (update) any transactions to the ledger at at the 14% Tax rate.

All purchase documents (i.e. Purchases and Supplier returns), as well as sales documents (i.e. Invoices and Credit notes) is correct and posted (updated) to the ledger at the Tax rate of 14%.

Disable posting to period March 2018:

1. On the Setup ribbon, select Reporting dates.



2. Select "*March 2018*" period "*Ends on"* and remove the tick in the "*Open for Posting*" fields.

3. Click on the OK button to save the changes.

Processing Transactions

During the transition period, you may need to use both the tax rates, i.e. 14% or 15%, depending on whether the transaction(s) is taxable on or before 31 March 2018 at 14%; or from 1 April 2018 at 15%.

In TurboCASH, the VAT accounts need to accommodate two VAT rates. An invoice may even reflect a rate of 14% and 15% depending if the goods were supplied or services rendered on or before 31 March 2018 or from 1 April 2018.

An example would be where a service provider charges subscriptions in advance April 2018 at 15%, but usage (e.g. calls) are charged in arrears March 2018 at 14%.

Processing transactions in Batches

When processing transactions in Batch entry on the Default tab, you need to make absolutely sure that the correct Tax / VAT code is selected.

By default, all accounts is "*Enabled*". All Tax / VAT codes are listed in the Tax lookup in the "*Tax*" column. Once the transitional period where all the transactions up to 31 March 2018 at 14% is posted (updated) to the ledger, you may disable the 14% Tax / VAT accounts (Setup ribbon, Setup → Accounts). The 14% rate Tax / VAT accounts will not be listed on the Tax lookup screens.

If you have a Zero-rated VAT – 0% Tax account, in the 14% structure (e.g. "850040 Zero-rated VAT – 0%"), you also need to disable Zero-rated VAT – 0% Tax account.

The 14% VAT rate (e.g. "*850000*" account range) are normally applicable to transactions up to 31 March 2018, in the "*Date*" column.



The 15% VAT rate (e.g. "*860000*" account range) is normally applicable to transactions as from 1 April 2018, in the "*Date*" column.

Processing transactions in Documents

When processing transactions in Documents on the Default tab in purchase documents (i.e. Purchases

and Supplier returns), as well as sales documents (i.e. Invoices and Credit notes), you need to make absolutely sure that the correct Tax / VAT code is selected.

By default, all accounts is "*Enabled*". All Tax / VAT codes are listed in the Tax lookup in the "*Tax*" column. Once the transitional period where all the transactions up to 31 March 2018 at 14% is posted (updated) to the ledger, you may disable the 14% Tax / VAT accounts (Setup ribbon, Setup → Accounts). The 14% rate Tax / VAT accounts will not be listed on the Tax lookup screens.

If you have a Zero-rated VAT – 0% Tax account, in the 14% structure (e.g. "850040 Zero-rated VAT – 0%"), you also need to disable Zero-rated VAT – 0% Tax account.

The 14% VAT rate (e.g. "*850000*" account range) are normally applicable to transactions up to 31 March 2018, in the "*Date*" column.



The 15% VAT rate (e.g. "*860000*" account range) is normally applicable to transactions as from 1 April 2018, in the "*Date*" column.

Tax reports

Before you print tax reports to submit your Tax (VAT/GST/Sales tax) returns, you need to post (update) all batch transactions and documents (i.e. invoices, credit notes, purchase and supplier return documents) for the tax period.

The following tax reports are available:

1. Tax per period report – This report is used to complete the Tax (VAT/GST/Sales tax) returns. It will list

a summary of the Output tax less the Input tax and the total tax payable / refundable.

2. Tax report - Reference / Document no. - This report will list the details of accounts and transactions of all posted (updated) batch and document transactions, on which Tax (VAT/GST/Sales tax is applicable. It will display the Tax code and description as well as the contra accounts for each transaction.

3. Tax list debtor with tax id - This report will list a total exclusive of tax, tax amount and inclusive amount of tax) for the Invoices *less* Credit notes for debtor (customer / client) accounts for selected period(s) or date(s). It will also display the Company and Tax registration numbers for each for debtor (customer / client) accounts.

4. Tax list creditor with tax id - This report will list a total exclusive of tax, tax amount and inclusive amount of tax) for the Purchase documents *less* Supplier returns for creditor (supplier / vendor) accounts for selected period(s) or date(s). It will also display the Company and Tax registration numbers for each for creditor (supplier / vendor) accounts.

The Tax excluded and Tax amount in the Report total of the Tax report - Reference / Document no. report, should balance with the Total - Output tax – Input tax of the Tax per period report, if the same periods are selected.

It is recommended that these tax reports are printed and archived (PDF) for record and audit purposes.

Tax per period report

This report is used to complete the Tax (VAT/GST/Sales tax) returns. It will list a summary of the Output tax less the Input tax and the total tax payable / refundable.

An option is available to list all transactions and documents including the account code, account description, country and tax reference of the debtor (customer / client) or creditor (supplier / vendor) account (if applicable).

To print tax per period reports:

1. On the Reports ribbon, select Reports → Tax.

2. Select the Tax per period report. The *"Tax list debtor with tax id" report* is the default report.

3. Select the "*Tax per period*" report.



4. Select the following:

    a) Per period - Tick on "*2 Months*" and select "*2018/03/01 / 2018/04/30*".

    b) Show details - Leave blank. By default, this option is not selected. It will only list the totals exclusive of Tax (VAT/GST/Sales Tax) for each tax code.

    If this option is selected, it will list all transactions and documents including the account code, account description, country and tax reference of the debtor or creditor account (if applicable).

    c) Show tax separately - Leave blank. By default, this option is not selected. If this option is selected, each tax code will print on a new page. It is recommended, that this option should only be selected, when the "*Show details*" option is selected.

5. Click on the OK button.

An example of the "*Tax per period*" (no details) report, is as follows:



It is recommended that the details should also be printed and saved for record purposes.

It is important to print the details to check the details of your transactions.

The detailed tax report ("*Show details*" and "*Show tax separately*" options selected) for the same period, is as follows:

Page 1 – Output tax - 14%



Page 2 – Input tax – Standard rate -14%



Page 3 – Input tax – Capital goods - 14%



Page 4 – Output tax – 15%



Page 5 – Input tax – Standard rate -15%



The Tax excluded and Tax amount in the Report total of the Tax report - Reference / Document no. report, should balance with the Total - Output tax – Input tax of the Tax per period report, if the same periods are selected.

Tax report - Reference / Document no.

This report will list the details of accounts and transactions of all posted (updated) batch and document transactions, on which Tax (VAT/GST/Sales tax is applicable. It will display the Tax code and description as well as the contra accounts for each transaction. If the same periods is selected as on the Tax per period report, the Exclusive and Tax amount totals should balance.

To print tax reference /document no. reports:

1. On the Reports ribbon, select Reports → Tax.
2. Select the Tax per period report. The *"Tax list debtor with tax id" report* is the default report.

3. Select the "*Tax report – Reference / Document no.*" report.



4. Select the following on "*2 Months*" and select "*2018/03/01 / 2018/04/30*".

5. Click on the OK button.

An example of the "*Tax report – Reference / Document no.*" report, is as follows:

Page 1 -



Page 5 – (Last page) Totals



Once again, the Tax excluded and Tax amount in the Report total of the Tax report - Reference /

Document no. report, should balance with the Total - Output tax – Input tax of the Tax per period report, if the same periods are selected.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with a Help Authoring Tool

Debtor (customer / client) accounts

The Debtors feature in osFinancials5/TurboCASH5, is specifically designed to manage and maintain debtor (customer / client) accounts. This feature provides a range of functionalities to effectively manage these accounts and ensure smooth customer relationship management. Here are some key aspects of the Debtors feature:

1. Account Management: You can create new debtor accounts, modify existing ones, delete or disable accounts based on your requirements. This gives you control over the debtor database and allows you to keep it up to date.
2. Account Details: Within each debtor account, you have the flexibility to make changes to various aspects, such as the debtor's name, contact details, addresses, and messages on the debtor form. You can also manage the delivery address and select specific document layout files on the Delivery address tab. Additionally, you can set accounting and payment terms, including discounts and interest percentage charges, on the Accounting information tab. This ensures that you maintain accurate and up-to-date information for each debtor.
3. Activities Tracking: The Debtors feature allows you to efficiently manage various activities related to debtor accounts. It provides dedicated tabs for tracking Contacts, Appointments, and transactions on the Documents, Transactions, Bank accounts, Backorders and Stock items tabs. These capabilities enable you to gain a comprehensive view of interactions and transactions with each debtor, enhancing your ability to manage and maintain fruitful relationships.
4. Filtering and Search: osFinancials5/TurboCASH5 provides filtering and search options within the Debtors feature, enabling you to easily locate specific debtor accounts based on various criteria such as name, contact details, or other relevant information.
5. Reporting Groups: You can create up to two custom reporting groups for debtor accounts, categorizing them by attributes like geographic regions, customer types, or sales channels. This enables you to generate insightful views of your debtor data. It allows you to slice and dice the information based on multiple dimensions and conduct detailed analysis, providing a comprehensive view of your debtor data and supporting better decision-making and strategic planning.

By leveraging the Debtors feature in osFinancials5/TurboCASH5, you can efficiently manage customer accounts, streamline communication, track transactions, and maintain precise financial records. This enhances customer service, boosts efficiency, and strengthens financial management within your organization.

To access the Debtors selection screen:

1. On the Default ribbon, select Debtors (F4). The "*Debtor accounts*" screen is displayed:



2. Once a debtor (customer / client) account is selected, you may view and manage the activities in the following tabs:

   a) Contacts - Add / edit / delete contactpersons.

   b) Appointments - View a list of events or appointments scheduled in the Calendar.

   c) Documents - View a list of the posted as well as the unposted sales documents (Quotes, Invoices, Point-of-Sales Invoices and Credit notes). You may select a document and print it. You may also print a Posted batches report for the posted sales documents (Invoices, Point-of-Sales Invoices and Credit notes).

   d) Transactions - View a list of the transactions posted in batches as well as sales documents (Invoices, Point-of-Sales Invoices and Credit notes). You may select a transaction and print a Posted batches report and print the transactions in the T-Account viewer.

   e) Bank accounts - Manage references for the Bank import plugin.

   f) Backorders - View a list all backorders for the selected debtor (customer / client) account.

You may add / edit or delete backorders.

g) Stock items - View a list of the products (stock items) in posted as well as unposted sales documents (i.e. Invoices, Credit notes and Quotes) for the selected debtor (customer / client) account.

3. Buttons –

a) New – Create a new debtor (customer / client) account.

b) Delete – Delete remove a selected debtor (customer / client) account.

c) Edit – Add or change the details of a selected debtor (customer / client) account.



d) Save – Save any changes to a selected debtor (customer / client) account.

e) Cancel – Cancel will revert to the previous values. Any changes will not be saved.

f) Export - Export the view of your debtor data as displayed in the list of debtors (customer / client) accounts. Only those records matching your sort, search and filter options will be exported.

3. Search Filter –

a) Filter Column - None is the default. You may select any of the available items (columns), (e.g. Debtor code, Name, Contact Person, Debtor group 1, Debtor group 2, Address 1, Address 2, Address 3, Postal code, Telephone 1, Telephone 2, Fax, E-mail, Bank account type, Bank account no., Last invoice, Reference, Due days, Debtor group 1 Sort, Debtor group 2 Sort, Delivery address, Delivery address2, Delivery address 3, Delivery address postal code, Delivery address country, X, etc.).

b) Like – Default operator. Others that may be selected is <, >, <=, >=, <>.

c) Value – Enter the text e.g. city, telephone numbers, postal code etc.

d) Filter button – Click to filter / search for your criteria.

e) Clear button – Click to clear / reset the filter / search for your criteria.

f) Show Disabled - By default, this option is not selected (not ticked). Only those active (enabled) debtor (customer / client) accounts will be listed. Select (tick) this option to include those

inactive (disabled) (Account disabled field selected (ticked) on the Accounting information tab) debtor (customer / client) accounts.

4. Line count – This will display the number of records (debtor (customer / client) accounts) that is available on the list. This will display the number of records (rows / debtor (customer / client) accounts) that matches your filter / search criteria.

5. Context menu – The following options are available:

    a) Create Invoice – A new Invoice (Document entry screen) will be launched for the selected debtor (customer / client) account.

    b) Create Credit note – A new Credit note (Document entry screen) will be launched for the selected debtor (customer / client) account.

    c) Create Quote – A new Quote (Document entry screen) will be launched for the selected debtor (customer / client) account.

    d) Reports – You may print postal or delivery address labels for selected debtor(s) (customer(s) / client(s)). You may also print these labels from the Reports → Debtors → Print labels (Reports ribbon).

    e) Debtor group 1 / 2 - Change the reporting group 1 or 2.

    f) Copy account - Create a new account from a selected account.

Created with the Standard Edition of HelpNDoc: Don't Let Unauthorized Users View Your PDFs: Learn How to Set Passwords

Debtor groups

This option allows you to set up to two Reporting groups for your Debtors (customers / clients). Debtor groups allows you to group or categorise the Debtors accounts on which you would like to report. Reporting groups for debtors can vary depending on the specific needs and requirements of your business.

These Debtor groups can be linked to each debtor (customer/ client) account.

- *You may use the context menu option on the debtors grid to set or change the reporting groups for Debtor group 1 and/or Debtor group 2 for selected debtor account(s).*

- *You may use the debtors grid to filter, search or group debtor accounts.*
- *You may print Debtor listing reports and Print labels for postal addresses and delivery addresses for all or only for debtor accounts linked to a selected debtor group or groups.*
- *You may print Sales analysis reports for Debtor group 1 or Debtor group 2.*

Examples of reporting groups for debtors (customers / clients)

Here are a few examples of reporting groups that you can use for debtor accounts:

1. Customer type: You can create reporting groups based on the type of customers or clients you have. For example, you may have reporting groups such as "*Retail customers*," "*Wholesale customers*," or "*Corporate clients*."
2. Geographic region: If you serve customers from different geographic regions, you can create reporting groups based on their locations. This can be helpful for analysing regional sales or managing relationships with customers in specific areas.
3. Sales channel: If you sell your products or services through different channels, you can create reporting groups to track and analyse sales performance for each channel. This could include groups like "*Online sales*," "*Retail store sales*," or "*Direct sales*."
4. Payment terms: You can create reporting groups based on the payment terms agreed upon with your debtors. This allows you to track and analyse the payment behaviour of different groups. For example, you might have reporting groups for "*Cash sales*," "*Credit sales*," or "*Instalment payments*."
5. Sales representative: If you have a sales team responsible for different territories or customer segments, you can create reporting groups based on the sales representatives. This can help in assessing individual performance and analysing sales by representative.
6. Customer rating: If you have a rating system to evaluate the creditworthiness or loyalty of your customers, you can create reporting groups based on their ratings. This allows you to identify high-value or high-risk customers. For example, you might have reporting groups for "*Gold customers*," "*Silver customers*," or "*Preferred customers*."

These are just a few examples, and you can customize reporting groups based on the unique characteristics and needs of your business. The goal is to create groups that allow you to analyse and report on debtor data in a meaningful way, enabling you to make informed decisions and effectively manage your customer relationships.

Define reporting groups for debtors (customers / clients)

To set reporting groups for Debtor accounts:

1. On the Setup ribbon, select Setup → Groups. The "*Groups (Account group 1)"* default screen will be displayed.

2. Click on the Debtor group 1 button.



3. If you wish to rename the Reporting group name - Debtor group 1, over-type the description with your new description. This will change the description of the button for Debtor group 1.

4. To add a new Group to the root directory or list, select the *REPORTING GROUP ROOT* on the list and click on the New button.

5. Enter the name of your Debtor group 1 and click on "*REPORTING GROUP ROOT*" on the list.

6. Repeat the process until you have entered all the Debtor groups, etc.

> *Adding sub groups for debtor groups*
>
> *Select a Debtor group, for example; "Debtor group 1A" and click on the New button. Enter the name of your sub group.*

7. If you need to add Reporting group 2 for Debtors, click on the Debtor group 2 button and repeat the process as for Debtor group 1.

8. Click on the OK button to save your changes and close (exit) this screen.

Changing the sequence of groups for debtors

Select a Debtor group, for example; "Debtor group 1B" and click on the Move up or Move down button. This will list the debtor group according to your preferred sequence.

You may click on the Print button to print a list of your debtor groups.

You may set colours to display on the Debtor accounts List screen. To do this, click on the Back colour button to set the rows background colour and the Font colour button to set the Font colour.

To retain and save the selected colors, you also need to set both the "Back color" and the "Font color".

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Debtors filter and search options

The osFinancials5/TurboCASH5 grid has a powerful and user-friendly filtering and sorting system that makes it quicker and easier than other methods. With just a few mouse clicks, you can group, sort, and filter any column(s) of data on most screens in a Set of Books. This feature is very useful and efficient for managing and analysing data.

Account disabled

By default, only active debtor (customer / client) accounts will be listed when launching the Debtors on the Debtor list screen.

To list the debtor (customer / client) accounts which have been set to "*Disabled*" on the Accounting information tab, you need to tick the "*Show disabled*" tick box and click on the Filter button.



Debtor code	Name	Address	Address 2	Address 3	Postal code	Telephone 1	Telephone 2
1CASHC	CASH CUSTOMERS						
1DOPEN	Opening Balances - Debtor						
1MDAVI	Mr. Mike Davies	P O Box 333	Halfway House		1685	(011) 315-1225	083 286-8763
1ROGSM	Mr. Roger Smith	Plot 539 Boxer Road	Glen Austin Ext 3	Midrand	1685	(011) 310-1677	
1ABGRE	Mr. AB Green	PO Box 1111	Lakeside	Johannesburg	2122	(011)314-9997	(011)314-9998
1MACDS	MAC Shop Decor Specialists	PO Box 5555	Morningside	Johannesburg	2222	(011)314-5557	(011)314-5558

The "Debtor listing - Credit control listing (Credit limit vs Current balance) as at..." report will display if a debtor (customer / client) account is disabled, or enabled.

If the "Show disabled" option is selected, and if you Close active forms or when you reopen the Set of Books, it will by default list only the active (enabled) debtor (customer / client) accounts.

Search by options

You may use the filter options to find a specific debtor (customer / client) account, or all accounts with the same values, in any of the twenty-eight (28) columns:

Default



Sorted (selected) - Alphabetical list



To search for specific debtor (customer / client) accounts:

1. The filter options will display only those debtor (customer / client) accounts in your search or filter criteria. To do this, you may:



   a) Search by - The default option is none. It will list all the column headings. You may select any of these as an option.

   b) Like - Operator to find all debtor (customer / client) accounts with the same value, values greater than, smaller than, greater than or equal to, smaller than or equal to the values you have selected, or wish to enter.

   c) Value - Enter the value for the field type you have selected, for example, Postal code (if you

have selected "*Postal code*" as the "*Search by*" option).



2. Once you have selected or specified the search criteria, click on the Filter button. Only those debtor (customer / client) accounts as in your search or filter criteria or options will be listed.

3. If you need to clear your filter options and values, click on the Clear button. You may also click on any of the column headings to change the sorting sequence of the debtor (customer / client) accounts listed.

You may also search for debtor (customer / client) accounts in the "Investigator" screen (Search (Default ribbon)).

Column headings

All the data for each of your debtor (customer / client) accounts are listed in twenty-eight (28) columns. To view change the sequence in which the data is displayed, you may use the following options:

- Scroll bars - Scroll to the right or to the left on the horizontal scroll bar to view the information.
- Sequence of rows - Click on any of the column headings to change the sorting sequence of the debtor (customer / client) accounts listed in the descending or ascending sequence.
- Sequence of columns - Click on a column heading and drag it to the right or to the left to change the sequence in which the columns need to be displayed.



You may drag and drop any of the columns on the data band to the left band and the columns from the left band to the data band, to customise the grid for your requirements.

The sequence of the columns as set will be retained if you close active forms or when you reopen the Set of Books.

Show / hide bands

All the data for each of your debtor (customer / client) accounts are listed in twenty-eight (28) columns. It is listed in two (2) bands:

Left band - Contains the Debtor code and Name.

Data band - Contains the rest of the data columns.



You may drag and drop any of the columns on the data band to the left band and the columns from the left band to the data band, to customise the grid for your requirements.

To hide the columns on the Left band, remove the tick in the first block.

To hide the columns on the Data band, remove the tick in the second block.

Show / hide columns

Click on the second block - Column headings - All the columns will be listed.

Remove the ticks for the columns to hide or select the columns you need to display.

You may use the Up arrows and/or the Down arrows Right or Left arrows keys to navigate the fields. You may use the Space bar to deselect (remove the tick) or to reselect (tick a field again).



Group columns

You may drag any column heading to the column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns will be grouped.

Select a column and click on it. While holding the mouse button down, drag it to the "*Use your mouse to pull a column here to group on that column*" bar. Select any other column to drag and drop it on the the "*Use your mouse to pull a column here to group on that column*" bar. You may select as many columns, as necessary, to group your data.

You may also drag and drop these columns to the right or left to change the grouping of these columns.



To remove a column from the "*Use your mouse to pull a column here to group on that column*" bar, you may use the following two (2) options:

1. Select the column heading (e.g., "*Postal code*") on the "*Use your mouse to pull a column here to group on that column*" bar, and drag it to the first line (above the column headings). When the mouse pointer change to a big X, drop it. The column will automatically be placed in the correct default sequence (or the place of the previous saved grid layout).
2. If you wish to change the column to a specific place, select the column heading (e.g., "*Postal code*") on the "*Use your mouse to pull a column here to group on that column*" bar, and drag it to the second line (column headings). When you drop it, the column will be added to the selected position or sequence of the columns.



Filter options : Column headings

If you need to view or find specific data, there are various options available to locate and find your data. Some of the options are:



- Sort - Click on a column heading to sort and list the data ascending or descending sequence. All the data is by default displayed ascending; from the smallest to the highest value (e.g. a-z or 0-9)

according to the record number (e.g. line number in a batch, etc.) To change the sort order from ascending (e.g. a-z or 0-9) to descending (e.g. z-a or 9-0) select a column and click on it. If you click on it again it will change back to ascending sequence.

- Drag and drop columns - You may click on a column and drag it to the left or to the right to change the sequence your data is displayed on screens.
- Filter - Click in the arrow to list the data in a specific column. A list displaying the data, as well as an All option and a Custom... option in the selected column will be displayed. By adding a tick next to a specific data, only the data, matching that amount will be listed.
- Custom - You can easily build customised filters according to your needs. These filter files can be saved and opened for future use.

Custom filters

Once you have selected data from the list in a column, the your selection will be displayed at the bottom section of the Debtors list screen as follows:



- To temporarily clear the filter (show all records, remove the tick. To show the filtered records, add the tick again.

- To delete the filter, click on the close icon.

You may click on the (Custom...) option on a column list; or click on the Customise... button to:

1. Make a filter (add or delete conditions and groups).

2. Save a filter.

3. Open a filter.

Make a custom filter

To make a filter:

1. Click on the (Custom...) option on a column list; or click on the Customise button.

2. Select an operator (i.e. and, or, and not, or not).

3. Click on the Filter button (or on the ... button) and select one of the following options on the context menu:

    a) New Condition

    b) New Group

    c) Delete row (If you click on the Filter button, you may delete all rows (conditions and groups)).

4. Select a column from the list of available data applicable to the screen.

5. Select a filter condition. In this example, the Between is selected. Another field is opened to select another date.

6. Once you have created your conditions or groups, click on the Apply button.

7. Click on the OK button to close and exit this "*Make filter*" screen.

Conditions



1. Equal to - list or display all values which is the same as the specified value.
2. Not equal to - list or display all values which is not the same as the specified value.
3. Less than - list or display all values smaller than the specified value.
4. Less than or equal to - list or display all values smaller or equal to the specified value.
5. Greater than - list or display all values greater than the specified value.
6. Greater than or equal to - list or display all values greater or equal to the specified value.
7. Like - list all values in the table similar to the specified value.
8. Not like - list all values in the table not similar to the specified value.
9. Contains - list all values in the table, which contains specified value.
10. Does not contain - list all values in the table, which does not contain specified value.
11. Begins with - starts with the specified value in the table.
12. Ends with - ends with the specified value in the table.
13. Is null - excludes any value entered, will not be listed or displayed.
14. Is not null - is not zero - any value which is not equal to zero will be listed or displayed.
15. Between - Specify specific values, etc. to include only matching values.
16. Not between - Specify specific values, etc. to exclude values.
17. In - In a specified value.
18. Not in - Not in a specified value.

Save custom filter files

To save a custom filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Save as... button. The "*Save active filter*" screen will be displayed.
2. Select a Directory in which you wish to save the custom filter file.
3. Enter a file name.
4. Click on the Save button to save the Filter in a (*.flt) Filter file format. You may then at any later stage open the saved *.flt file.

Open custom filter files

To open a saved a custom filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Open... button. The "*Open a saved filter*" screen will be displayed.
2. Select a Directory in which you have saved the custom filter file.
3. Select a valid filter file.
4. Click on the Open button. The selected filter file's name will be displayed in the titlebar of the "*Make filter*" screen.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Debtor - Context menu

Right-click to display the following context menu:



The following options are available:

1. Create Invoice – A new Invoice (Document entry) will be launched for the selected debtor (customer / client) account.
2. Create Credit note – A new Credit note (Document entry) will be launched for the selected debtor (customer / client) account.
3. Create Quote – A new Quote (Document entry) will be launched for the selected debtor (customer / client) account.
4. Reports – You may print postal or delivery address labels for selected debtor(s) (customer(s) / client(s)). You may also print these labels from the Reports → Debtor → Print labels (Reports ribbon).
5. Debtor group 1 / 2 - Change the reporting group 1 or 2.
6. Copy account - Create a new account from a selected account.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Debtor Context menu - Set Debtor group 1/2

You may change the Debtor group 1 and/or Debtor group 2 for selected debtor (customer / client) account(s).

To change the Debtor group 1 or 2:

1. On the Debtors (Debtors list screen) (Default ribbon), select the debtor (customer / client) account(s).

> *If you need to select multiple debtor (customer / client) account(s), press the Ctrl or Shift key and click on each debtor (customer / client) account, for which you need to change the debtor reporting group.*

2. Right-click and select "*Debtor group 1*" or "*Debtor group 2*" on the context menu.

3. Select "*Empty*" or the available debtor group from the sub-menu. The "*Debtor group 1*" or "*Debtor group 2*" will change on reports.



Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Debtor - Context menu - Reports

The "*Reports*" context menu option allows you to print postal or delivery address labels for a selected debtor (customer / client) account.

To print labels for a selected debtor (customer / client) account:

1. On the "*Debtors*" list screen, select a debtor (customer / client) account.

2. Right-click and select "*Reports → Selected debtor label*" option or the select "*Reports → Selected debtor delivery label*" option on the context menu. This will print the postal address label or the delivery address label of the selected debtor (customer / client) account.



You will only be allowed to print the postal address label or delivery address label for one selected debtor (customer / client) account at a time.

An example of a printed postal address labels, is as follows:



An example of a printed delivery address labels, is as follows:



You may also print the Postal address labels or Delivery address labels for debtor (customer / client) accounts from the Reports → Debtors → Print labels (Reports ribbon).

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Markdown Content with HelpNDoc

Debtor - Context menu - Copy account

The "*Copy account*" context menu option allows you to create a copy of a selected debtor (customer / client) account.

To copy a selected debtor (customer / client) account:

1. On the "*Debtors*" list screen, select a debtor (customer / client) account.

2. Right-click and select the "*Copy account*" option on the context menu.



3. This will create a copy of the of the selected debtor (customer / client) account.



4. Enter the Debtor code.

> *The next Debtor code (e.g. D00008, etc.), will automatically be generated. It is important to prefix Debtor codes with a unique prefix. In this documentation, the accounts is prefixed as follows:*
>
> *Debtor code = 1*
>
> *Creditor code = 2*
>
> *The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens.*

5. Edit the copied fields, where necessary.

> *Note the following:*
>
> - *The contact person is not copied on the new account.*
> - *On the Accounting information tab, all the terms and conditions (e.g. Due days, Credit limit, Charge amount, Customer discount percentage, Monthly interest of overdue amounts percentage, etc.) is copied.*
> - *No information is copied on the Contacts, Appointment, Documents, Transactions, Bank accounts, Backorders and Stock items tabs.*

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files

to CHM with HelpNDoc

Debtor accounts edit form

To create add / edit a Debtor (customer / client) account:

1. If you do not find a debtor (customer / client) account, you may add it by clicking on the New button. You only need to replace the Debtor code, enter the Name and save it. The rest of the fields are optional, but it is recommended that you fill in as much details as possible.

The next Debtor code (e.g. D00006, etc.), will automatically be generated. It is important to prefix Debtor codes with a unique prefix. In this documentation, the accounts is prefixed as follows:

- *Debtor code = 1*
- *Creditor code = 2*

The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens on "Batch entry" screens.



The following nine (9) tabs are used to enter and/or edit settings and check additional useful information to manage debtor (customer / client) accounts:

- *Delivery address - Delivery address, Address 2, Address 3, Postal code, Country, Message, Message 1, Message 2 and Message 3 and Layout files for Invoices, Credit notes and Quotes.*
- *Accounting information - Account disabled, Open item account, Due days (Payment date), Credit limit, Charge amount, Customer discount (percentage), Monthly interest on overdue amounts (percentage), Selling prices, Bank account (i.e. Bank account type, Bank account no., Bank name and Branch code), Use default account and Use default tax.*

- *Contacts - Any contacts linked to the debtor (customer / client) account will be listed. You may also add, edit, delete and search for contacts. An auto-copy feature allows you to copy the searched contacts details, which may be edited if required.Any contacts linked to the debtor (customer / client) account will be listed. Contacts may also be maintained (managed) in the in the Contacts and Calendar on the Default ribbon.*
- *Appointments - Any events or appointments have been scheduled in the Calendar (Default ribbon) for that debtor (customer / client) account will be listed.*
- *Documents - Any sales documents (Quotes, Invoices and Credit notes) that have been processed for that debtor (customer / client) account will be listed.*
- *Transactions - Any Debit and Credit transactions have been processed for that debtor (customer / client) account will be listed.*
- *Bank accounts – This is used for the Bank import plugin.*
- *Backorders – This tab will list all backorders for the debtor (customer / client) account.*
- *Stock items – This tab will list all the posted as well as unposted documents (i.e. invoices, credit notes and quotes) for the selected debtor (customer / client) account.*

Plugins (e.g. Price agreements and Subscriptions), which may be purchased separately will be added as tabs on debtor (customer / client) accounts. These will be dealt with in separate documentation.

2. Enter and/or select the following options:

a) Debtor code - It is automatically generated.

The Debtor code is automatically generated when you click on the New button. It is prefixed with a D, followed by 5 numeric characters. You may overtype this with your own to suit your specific requirements.

If you have created a Set of Books (Advanced option), and have set the Account code to:

- *4-digits, you may enter a 7-digit Account code (a prefix followed by 6 characters).*
- *5-digits, you may enter a 8-digit Account code (a prefix followed by 7 characters).*
- *6-digits, you may enter a 9-digit Account code (a prefix followed by 8 characters).*
- *7-digits, you may enter a 10-digit Account code (a prefix followed by 9 characters).*

- *8-digits, you may enter a 11-digit Account code (a prefix followed by 10 characters).*

b) Name - Enter the name (description) for the debtor (customer / client).

c) Address - Enter up to 3 address lines.

d) Postal code - Enter the postal code or zip code.

e) Country - You may select the Country from the list, if necessary.

f) Phone 1 - Enter the phone number.

g) Phone 2 - Enter the phone number, if available.

h) Fax - Enter the fax number, if available.

i) Website - Enter the website address, if available.

You may double-click on this field to access the website of the debtor (customer / client) in your system's default web browser.

j) E-mail - Enter the e-mail address, if available.

You may double-click on this field to launch the a new message to the debtor (client / customer) in your system's default mail app / program.

k) Tax Reference - If debtor (customer / client) are exempt from tax, or registered for VAT/GST/Sales Tax, that tax reference should be entered in this field.

l) Company Reg. No. - Enter, if available.

m) Contact Person - Select a Contact Person from the list.

If no Contact Person is available, you need create it on the Contacts tab.

n) Salesperson - Select the salesperson for the debtor (customer / client) account. All salespersons, if created on the Setup ribbon Setup → Salesperson (or Setup → Groups (Salespersons) , will be listed.

If you are not generating sales documents (Quotes, Invoices, Credit notes or Point-of-Sales Invoices), you may leave this blank.

o) Debtor group 1 / 2 - The Reporting group to which you wish this debtor (customer / client) to be allocated.

> *The description of Debtor group 1 and/or Debtor group 2 you have entered on the "Reporting group name" field on the Debtor groups tab - Setup → Groups may be reflected on this screen.*

p) Language - The list of language files in Switch language (Start ribbon) as maintained in Tools → Customise language (Setup ribbon) will be listed. You may select a preferred language for the debtor (customer / client). If the standard translatable document layout files are selected, the documents (i.e. invoices, credit notes and quotes) will be printed in the selected language for debtor (customer / client) account.

3. Click on the Delivery address tab and/or Accounting information tab to enter additional information, select settings and accounting terms.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Debtor accounts - Delivery address tab

Delivery address tab - Enter delivery address, and messages and settings for layout files.

1. The Delivery address tab is the default when accessing the Debtors on the Default ribbon.



2. Enter and/or select the following on the "*Delivery address*" tab, if necessary:

a) Delivery address, Address 2, Address 3 - Enter up to 3 address lines.

b) Postal code - Enter the postal code or zip code.

c) Country - Default is *Empty*. You may select the Country.

d) Message, Message 1, Message 2 and Message 3 - Enter the message for the debtor (customer / client) account. This message will be displayed on Statements printed in Reports → Reports → Debtors → Statements.

> *This statement message is only applicable for the selected debtor (customer / client) account. You may also enter a global statement message to be displayed on statements for all debtor (customer / client) accounts in Setup → Documents setup - Statementstab.*

e) Layout files

> *If no layout files have been selected for the debtor (customer / client) on this tab, the default settings as set for Invoices, Credit notes and Quotes (Setup → Documents setup) will be used.*

(i) Layout file 1 - Invoice - Layout file - If you have a specific Invoice layout file for the this debtor (customer / client), you may select it.

(ii) Layout file 2 -Credit note - Layout file - If you have a specific Credit note layout file for the this debtor (customer / client), you may select it.

(iii) Layout file 3 - Quote - Layout file - If you have a specific Quote layout file for the this debtor (customer / client), you may select it.

f) Send document type - This is only applicable to the E-mailPro plugin. Print document is the default. Other options are; Print document and send email or Email. To use this feature, you need to activate and purchase the E-mailPro plugin and need to set it to print to a printer.

3. Click on the Accounting information tab to enter and select settings and accounting terms.

4. Once finished, click on the Save button.

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Debtor accounts - Accounting information tab

Accounting information tab contains settings for a specific debtor.

1. Click on the Accounting information tab.



2. Enter and/or select the following, if necessary:

   a) Account disabled - This field should not be selected (ticked) if you wish to enter and post transactions to the debtor (customer / client) account. Select (tick) this field if you wish to disable the debtor (customer / client) account (e.g. if you no longer do business with this debtor (customer / client)). osFinancials5/TurboCASH5 will allow you to enter transactions for the debtor (customer / client), but it will not allow you to post transactions to the debtor (customer / client) account. However, you will still be able to view reports for the debtor (customer / client).

   b) Open item account - Select (tick) this field if you wish to allocate or link receipts or credit notes (credit transactions) to a particular invoice or debit transaction. If this field is left blank, the Balance B/F (brought forward) posting method will be used, where payments received or credit notes issued are allocated against the oldest outstanding amount.

   c) Due days - Enter the number of days for the credit facility granted to the debtor (customer / client).

> *This date will be used to calculate the date when payments are to be received from debtor (customer / client) on sales documents (i.e. invoices, credit notes or quotes) and via the electronic payment system in the Automatic receipts batch processing option. It will also print on sales documents (i.e. invoices, credit notes or quotes).*

   d) Credit limit - Enter the credit limit which you have agreed and granted to your debtor (customer / client). When you are processing transactions, osFinancials5/TurboCASH5 will warn you if the debtor is exceeding this credit limit.

> *It will also display the Available balance (i.e. Current balance minus the Credit limit) on sales document entry screens (i.e. Invoices, Credit notes or Quotes).*

The Calculator's buttons may also be launched from the Credit limit field.

e) Charge amount - Enter an amount as agreed upon when you have granted the credit facility to your debtor (customer / client).

You may generate Multiple Transactions - Debtors with charge amount option in any Batch type or Journal (except the Receipts and Payments batch types). When you post this Batch,osFinancials5/TurboCASH5 will debit (increase the debtor (customer / client) account) for each of the debtor (customer / client) accounts with the amount specified in this field and credit a specified account (e.g. Income account).

The Calculator's buttons may be launched from the Charge amount field.

f) Customer discount - You may enter a percentage for the debtor (customer / client) discount which you wish to allow to the specific debtor (customer / client).

The discount will automatically be calculated on the selected selling price of a selected stock item (if the "Allow invoice discount field is selected on the Stock items (Default ribbon)) when sales documents (i.e. invoices, credit notes or quotes) are created or edited for the selected debtor (customer / client).

g) Monthly interest on overdue amounts (percentage) - The percentage of the monthly interest on overdue accounts that will be charged to the debtor (customer / client).

If the annual interest is 18%, you would enter 1.5% (18 / 12 months) for the monthly interest. Another example, if the annual interest rate you wish to charge is 24% (24 / 12 months), you would enter 2 %).

You may generate Multiple Entries - Interest on overdue debtors option - in any Batch type or Journal (except the Receipts and Payments batch types). osFinancials5/TurboCASH5 will calculate the interest for the number of overdue days for each debtor (customer / client) account for which you have entered an amount in this field.

When you post this Batch,osFinancials5/TurboCASH5 will debit (increase the debtor (customer / client) account) for each of the debtor (customer / client) accounts with the amount specified in this field and credit a specified account (e.g. Interest Income account).

h) Selling prices - You may select any one of the three (3) available selling prices as the default selling price for this debtor (customer / client).

If you have changed the descriptions of your selling prices 1 / 2 / 3 in Setup → Stock information, your own descriptions will be displayed on the list.

i) Bank account type - Select *Arbitrair* or *11 Proof*. This is for electronic payments received from debtor (customer / client) accounts via the electronic banking system.

11-Proof - See - http://nl.wikipedia.org/wiki/Elfproef

Arbitrair - Random - not controlled

j) Bank account no. - Enter the bank account number, if available.

k) Bank name - Enter the bank account name, if available.

l) BIC - (Bank Identifier Code). Enter, if available.

m) IBAN - (International Bank Account Number). Enter, if available.

See - http://en.wikipedia.org/wiki/International_Bank_Account_Number

n) Signature - Enter, if available.

SWIFT - (Society for Worldwide Interbank Financial Telecommunication) - See - http://en.wikipedia.org/wiki/SWIFT / http://www.theswiftcodes.com/

SEPA - (Single Euro Payments Area) - See - http://en.wikipedia.org/wiki/Single_Euro_Payments_Area

o) Signature date - Enter, if available.

p) Stock file override - By default, the Stock file override settings is not activated. If necessary, select the following:

i) Use default account - By default, the "*Use default account* " option is not selected. The Sales account, as selected on the on Stock items (Default ribbon), will be used when invoices or credit notes for the debtor (customer / client) is updated (posted) to the ledger.

If you activate the Use default account settings, you need to select a different account on the Accounts lookup facility.

When invoices or credit notes for the debtor (customer / client) is updated (posted) to the ledger, the selected Sales account for this Stock item will be ignored and the sales transaction will be updated (posted) to the specified

account for the debtor (customer / client).

ii) Use default tax - By default, the "*Use default tax*" option is not selected. The Output Account, as selected on the on Stock items (Default ribbon), will be used when invoices or credit notes for the debtor (customer / client) is updated (posted) to the ledger.

If you activate the Use default tax settings, you need to select a different VAT/GST/Sales Tax account or code on the Tax Lookup.

When invoices or credit notes for the debtor (customer / client) is updated (posted) to the ledger, the selected Tax account or code for this Stock item will be ignored and the Output VAT/GST/Sales Tax transaction will be updated (posted) to the specified VAT/GST/Sales Tax account or code for the debtor (customer / client).

Do not select this option, if you are not registered for VAT/GST/Sales Tax, or if multiple Tax codes (accounts) is applicable to the transactions with the debtor (customer / client).

If you do not generate sales documents (Invoices, Credit notes and Quotes), the selling prices and customer discount fields are not applicable.

3. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Debtor accounts - Contacts tab

You may add, delete or enter contact persons for the debtor (customer / client). A list of all contact persons linked to the selected debtor (customer / client) account, you have created, edited or deleted, in the following options on the Default ribbon:

- Calendar
- Contacts



This will display the First name, Name, Address, Address 2, Address 3, Phone 1, Phone 2, Fax and E-mail address.

The options are as follows:

New - This will open a blank contactperson screen.

Edit - This will open the selected contact's details screens.

Delete - Delete a selected contact.

Search - This will initiate a similar screen as in the Contacts (Default ribbon) listing all contacts. You can then select a specific contact. You can also use the "*Auto-copy info*" option to copy the details of a selected contact.

Deleted contact persons will be removed from this list.

Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Debtor accounts - Appointments tab

In osFinancials5/TurboCASH5, the "*Debtor accounts - Appointments*" tab allows you to view and manage appointments specifically related to a selected debtor (customer/client) account. This tab provides a centralised view of all scheduled debtor appointments that have been added in the Calendar (Default ribbon).

By accessing the "*Debtor accounts - Appointments*" tab, you will be able to see a comprehensive list of all debtor appointments/events that have been scheduled in the Calendar. This includes appointments for meetings, discussions, notes, or any other relevant activities associated with your debtor account.

If any Bulk time entries were processed for a selected debtor (customer/client) account these entries will only be listed on the "*Debtor accounts - Appointments*" tab, once you generated quotes on the "Create invoices for hours" button.

All scheduled Debtor appointments (events) added in the Calendar (Default ribbon) for the selected

debtor (customer / client) account will be listed here.



If you double click on a selected appointment, the Bulk time entry screen will be launched. You may select the dates edit reschedule, add notes, etc. and set reminders, etc.

When you use the Bulk time entry feature to add time entries for a selected debtor account, those entries are initially recorded but not directly listed on the "Debtor accounts - Appointments" tab. However, once you proceed to generate quotes for the hours using the "Create invoices for hours" button on the Calendar, the bulk time entries will be transformed into quotes.

Therefore, to see the bulk time entries reflected on the "Debtor accounts - Appointments" tab, it is necessary to generate quotes for those hours using the "Create invoices for hours" button in osFinancials5/TurboCASH5.

At this point, the quotes created from the bulk time entries will be listed on the "Debtor accounts - Appointments" tab.

The Repeating invoices event will not be listed in the "Debtor accounts - Appointments" tab. The Repeating invoices event will not be listed in the Reports → Calendar report.

You may click on the column headings (i.e. Description or Notes) to change the sort sequence from the ascending to the descending sequence.

You may click on any of the column headings (i.e. Start time, End time, Description or Notes) and drag it to the left or right to change the sequence in which to display the columns.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Debtor accounts - Documents tab

All sales documents (i.e. Invoices, Credit notes, Quotes and/or POS Invoices) which have been processed for the selected debtor (customer / client) account will be listed here.

To maximise the Documents tab and/or Debit / Credit transactions section of the screen, click on the

button to maximise the Documents tab. You may also click and drag any part of the screen

up / or down.



The options are as follows:

1. Print button - This will print the selected document to the default or selected output method.

   You may also double-click on a selected document to print it.

2. Layout file - This is by default blank. The selected document will be printed using the layout file as selected for each document type (i.e. Invoices, Credit notes and Quotes) in Documents setup (Setup → Documents setup).

   If specific layout files is selected on the Delivery address tab of a debtor (customer / client) account, te layout files will be used to print the selected documents.

   You may change the layout file by selecting a layout file from the list.

   These layout files are stored in the ...\plug_ins\reports\DOCUMENTS\DOCUMENTS directory of your system.

3. Send report to - The default option as set in the "*Output Method*" field on Setup → Company info (Options) or Setup → Access control (Reports access tab). You any change this to any other option (i.e. "*Screen, Printer, File, E-mail*" or "*Fax*"), if required.

   You may click on the column headings (i.e. Document number, Date, Description or Reference) to

change the sort sequence from the ascending to the descending sequence.

You may also click and drag any of the column headings to the left or right to change the sequence in which the columns are to be displayed.

View Transactions - Show transact context menu

The Documents tab lists all posted and unposted documents (i.e. Invoices, Credit notes and Quotes. The Show transactions context menu option will not do anything, if an order or an unposted document is selected.

1. Select a document (Invoices or Credit notes) and right-click, select Show transactions. The posted batch transactions will be displayed in the "*Transactions*" screen.



2. Click on the Print button to print the posted batch transactions, if required.



Created with the Standard Edition of HelpNDoc: Transform your help documentation into a stunning website

Debtor accounts - Transactions tab

Any transactions which have been processed (posted documents and posted batches) for that debtor (customer / client) account will be listed:

- Batch (Journal) Transactions which have been updated (posted) to the ledger.
- Document Transactions (i.e. Invoices and Credit notes) which have been updated (posted) to the ledger.

To maximise the Transactions tab and/or Debit / Credit transactions section of the screen, click on the *button to maximise the Transactions tab. You may also click and drag any part of the screen up / or down.*

All selected - All transactions listed. Those transactions, which are fully linked or settled, will display an 0.00 amount in the Outstanding column:



All not selected - This is the default option. Only those with outstanding amounts will be listed:



Before sending statements to your debtors (customers / clients), it is recommended that any amounts in the credit section be linked to any outstanding invoices or debit transactions.

If the debtor (customer / client) account is not set as an open item, account, all transactions will be listed.

It will list transactions as follows:

1. Debit - Documents (i.e. Invoices and POS Invoices), Sales journal, Generate multiple transactions (Interest on overdue debtors, Debtors with charge amount, Fixed amount to all debtors), Opening Balances take-on, etc. It will list any transactions, for which amounts are entered in the Debit column of batches.

2. Credit - Documents (i.e. Credit notes), Sales returns journal, Receipts journal, Generate multiple transactions (Balance debtors with amount), etc. It will list any transactions, for which amounts are entered in the Credit column of batches.

You may click on the column headings (i.e. Reference, Description, Date, Amount or Outstanding) to change the sort sequence from the ascending to the descending sequence.

You may also click and drag any of the column headings to the left or right to change the sequence in which the columns are to be displayed.

Before sending debtor statements, it is recommended that any amounts in the credit section be linked to any outstanding invoices or debit transactions.

View Transactions - Show transactions context menu

1. Select a transaction and click on the Show transactions context menu.
2. On the "*Transactions*" screen, click on the Print button.



Line	Reference	Date	Description	Account	Default account	Tax	Debit	Credit	Amount entry	Amount exclusive
1	IN000020	2021/06/30	Compressor	G010000 Sales	-	860-010	0.00	3,000.00	3,000.00-	
2	IN000020	2021/06/30	Drill press	G010000 Sales	-	860-010	0.00	2,000.00	2,000.00-	
3	IN000020	2021/06/30	Invoice /C-103	D1ABGRE Mr. AB Green	-	860-010	5,750.00	0.00	5,750.00	
4	IN000020	2021/06/30	Invoice /C-103	T860010 Output VAT - 15%	-	-	0.00	750.00	750.00-	
5	IN000020	2021/06/30	COST OF SALES/C-103	G100000 Cost of sales	-	-	3,000.00	0.00	3,000.00	
118	IN000020	2021/06/30	COST OF SALES/C-103	G750000 Stock control	-	-	0.00	3,000.00	3,000.00-	
6							8750.00	8750.00	0.00	

The Amount exclusive values are as follows:

- 0 = Amount exclusive
- 1 = Amount inclusive



Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2021/06/30	IN000020	*Compressor	G010-000 Sales	860-010	-450.00	0.00	3,000.00
2021/06/30	IN000020	*Drill press	-	860-010	-300.00	0.00	2,000.00
2021/06/30	IN000020	Invoice /C-103	- D1AB-GRE Mr. AB Green	860-010	750.00	5,750.00	0.00
2021/06/30	IN000020	*Invoice /C-103	- T860-010 Output VAT - 15%	-	0.00	0.00	750.00
			-	Total		5,750.00	5,750.00

View Transactions - Show Transactions button

T-Account viewer

1. Click on the Show transactions button.
2. Enter or select a start date and an end date, if necessary. Click on the Print button to print the transactions, if required.



You may double-click on a selected batch number to view only the transactions for the selected document. For example, if you need to view and print the transactions for Invoice "IN000020" only, double-click on the batch number "10077"

Show contra - By default, this option is not selected. The contra accounts will not be printed in the "ledgerdetail" report when you click on the Print button.

Show contra option selected you may view the Contra accounts in the T-Account-viewer. If you click on the Export button, the contra accounts will be included in Column A of a Spreadsheet.

The Contra accounts consists of the following, separated by a comma:

"G010000 Sales,T860010 Output VAT - 15%"

Documents

- *Ledger account and account description set as the contra account of the batch type linked to the document type. (i.e. Contra account of the Sales jnl linked to Invoice and Credit note document types in Setup documents).*
- *Tax account (tax code) and description as linked to the Output tax (VAT/GST/Sales tax) on the Ledger tab of the Stock item selected on the Document lines.*

Batches

- *Ledger account and account description of the contra account selected in Batch setup generated as balancing entries; or selected in the "Account" column for Batch transactions.*
- *Tax account (tax code) and description as selected in the "Tax" column for Batch transactions and/or generated as balancing entries.*

Lookup document

You may right-click on a selected document and select "*Lookup document*" on the context menu of the "*T-Account viewer*".

The posted document will be displayed in a stand alone "*Document entry*" screen.



You will not be allowed to edit or change the posted document.

T-Account viewer - Print transactions

To print the transactions, in the "*T-Account viewer*", click on the Print button.



View a specific selected batch transaction (e.g. Invoice "*IN000020*" (batch number "*10077).*



T-Account viewer - Export transactions

To export the transactions, in the "*T-Account viewer"*, click on the Export button. This will export the transactions, as selected displayed in the T-Account viewer, as a comma separated text file as a "*Export.txt*" file. The Exported file will automatically be opened in your in your system's app (program) associated with the CSV (Comma Separated Values) file types.

Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Debtor accounts - Bank accounts tab

This allows you to use references for the Bank import plugin.



Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System Parameters.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Debtor accounts - Backorders tab

This tab will list all backorders for the debtor (customer / client) account. Backorders will automatically be listed here when processing documents or added / edited from the following options:

- When processing invoices in Input → Documents (Default ribbon), and the debtor (customer / client) orders more than is actually invoiced, it will be recorded in the backorder facility.
- An example where the quantity entered in the "*Order*" field is more than the quantity entered in the "*Ship*" field, is as follows:



You may also click on the Backorder icon to edit backorders when processing invoices and quotes.

The insufficient quantities (e.g. 10 – 2 = 8, as per this example) will be added to the backorder

feature.

The Backorders may be accessed from the following options on the (Default ribbon).

- Stock items – List of backorders for the selected stock item.
- Input → Backorders – List of backorders for all stock items.



Sorting and Rearranging Columns:

- *You can click on the column headings (such as Stock item, Description, Unit, Items, Discount, Stock, Referral source, Selling price, Price, and Exp. Selected) to change the sort sequence from ascending to descending order.*
- *To rearrange the sequence in which the columns are displayed, you can click and drag any of the column headings to the left or right.*

You may also add a new backorder, edit an existing backorder or delete a backorder.



If the Backorders screen is launched from Input → Documents → Backorders, both the Debtor as well as the Stock item will be displayed. You may select them, if necessary.

Click on the New button to add a new backorder item or on the Edit button to edit a selected backorder. The fields are as follows:

- Stock item – The stock item code and description will be displayed for existing backorders. For new backorders, select the stock item.

- Items – The quantity is automatically displayed as the difference of the quantity entered in the "*Order*" field and the quantity entered in the "*Ship*" field of documents. For new backorders, enter the quantity.

- Recalculate selling price – This button will clear the Discount percentage and recalculate the Selling price to the original selling price (Price).

- Selling price and Price – This is the prices per item. The Selling price is the amount after the discount percentage and the Price is the price excluding any discount.

The Selling price and Price displayed is the prices for a single item.

- Discount – The Discount will be displayed if the percentage is entered on the "*Customer discount*" field on the Accounting information tab of the debtor (customer / client) account and the "*Apply invoice discount*" field is selected (ticked) on Stock items (Default ribbon).

- Stock – (Exp.Selected column on the Backorders tab – List view). This is the quantity of stock items on hand. The quantities in this field will be updated if:

    - Documents are posted (updated) to the ledger (e.g. credit notes, purchases and supplier returns).

    - Stock item adjustments – If the quantities "*On Hand*" field is updated / changed on the Stock items (Default ribbon).

- Referral Source – This will automatically be updated with the Invoice number in which the quantity entered in the "*Order*" field is more than the quantity entered in the "*Ship*" field.

When processing a new Invoice for a debtor (customer / client) account (with outstanding Backorders), the "*Backorders*" screen is automatically displayed:



If you select an item (tick the Selected field), the following is updated:

- Transferred to the Document line.
- Removed from the backorder records and reports.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's CHM Help File Creation Features

Debtor accounts - Stock items tab

This tab will list all the posted as well as unposted documents (i.e. invoices, credit notes and quotes) for the selected debtor (customer / client) account.

To maximise the Stock items tab and/or Debit / Credit transactions section of the screen, click on the  *button to maximise the Stock items tab. You may also click and drag any part of the screen up / or down.*



Date	Items	Document no.	Description	Price	Discount	Exclusive	Inclusive	Units	Description	Document type	Posted	Stock code	Description
2021/06/24	2	QU000005	Compressor	1,500.00	0	3,000.00	3,450.00	1	Each	Quotes	0	3COMP	Compressor
2021/06/24	2	QU000005	Drill press	1,000.00	0	2,000.00	2,300.00	1	Each	Quotes	0	3DRILL	Drill press
2021/05/07	2	QU000003	07-05-2021 Russell	500.00	0	1,000.00	1,150.00			Quotes	-1	4L-PAINT-E	Paint - Exterior
2021/03/01	2	QU000001	Paint - Exterior	500.00	0	1,000.00	1,150.00	1	Each	Quotes	-1	4L-PAINT-E	Paint - Exterior
2021/06/30	2	IN000022	Compressor	1,500.00	0	3,000.00	3,450.00	1	Each	Invoice	0	3COMP	Compressor
2021/06/30	2	IN000022	Drill press	1,000.00	0	2,000.00	2,300.00	1	Each	Invoice	0	3DRILL	Drill press
2021/06/30	2	IN000021	Compressor	1,500.00	0	3,000.00	3,450.00	1	Each	Invoice	0	3COMP	Compressor
2021/06/30	2	IN000021	Drill press	1,000.00	0	2,000.00	2,300.00	1	Each	Invoice	0	3DRILL	Drill press
2021/06/30	2	IN000020	Compressor	1,500.00	0	3,000.00	3,450.00	1	Each	Invoice	1	3COMP	Compressor
2021/06/30	2	IN000020	Drill press	1,000.00	0	2,000.00	2,300.00	1	Each	Invoice	1	3DRILL	Drill press
2021/06/30	2	IN000019	Compressor	1,500.00	0	3,000.00	3,450.00	1	Each	Invoice	1	3COMP	Compressor
2021/06/30	2	IN000019	Drill press	1,000.00	0	2,000.00	2,300.00	1	Each	Invoice	1	3DRILL	Drill press
2021/06/05	1	IN000011	Drill press	1,000.00	0	1,000.00	1,150.00	1	Each	Invoice	1	3DRILL	Drill press
2021/05/07	2	IN000009	Paint - Exterior	500.00	0	1,000.00	1,150.00	1	Each	Invoice	1	4L-PAINT-E	Paint - Exterior
2021/03/15	2	IN000003	Paint - Exterior	500.00	0	1,000.00	1,150.00	1	Each	Invoice	1	4L-PAINT-E	Paint - Exterior
2021/03/13	2	IN000001	Paint - Exterior	500.00	0	1,000.00	1,150.00	1	Each	Invoice	1	4L-PAINT-E	Paint - Exterior
2021/06/30	1	CR000003	Compressor	1,500.00	0	1,500.00	1,725.00	1	Each	Credit notes	1	3COMP	Compressor
2021/06/30	1	CR000003	Drill press	1,000.00	0	1,000.00	1,150.00	1	Each	Credit notes	1	3DRILL	Drill press
2021/06/30	2	CR000001	Compressor	1,500.00	0	3,000.00	3,450.00	1	Each	Credit notes	1	3COMP	Compressor
2021/06/30	2	CR000001	Drill press	1,000.00	0	2,000.00	2,300.00	1	Each	Credit notes	1	3DRILL	Drill press
20	25					23,500.00							

You may click on the column headings (i.e. Date, Items, Document no., Description, Price, Discount, Unit Price, Exclusive amount, Inclusive amount, Unit size, Description (Unit), Document type, Posted, Stock code and Stock description) to change the sort sequence from the ascending to the descending sequence.

You may also click and drag any of the column headings to the left or right to change the sequence in which the columns are to be displayed.

Posted

- 0 – Invoices and Credit notes are not yet posted (updated) to the ledger.
- 0 – Quotes are not yet confirmed (Converted to an Invoice).
- 1 – Invoices and Credit notes are posted (updated) to the ledger.
- 1 – Quotes are confirmed (Converted to an Invoice).
- -1 - Quotes which are still open.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Intuitive Interface

Delete Debtor accounts

You may delete a debtor (customer / client) account if the account has no transactions and/or balances.

You may disable a debtor (customer / client) account to block (prevent) posting of any documents or batch transactions for the debtor (customer / client). You may need to do this, if you are no longer doing business with the debtor (customer / client), or if the account is overdue, etc.

Delete accounts

To delete a Debtor (customer / client) account:

1. On the "*Debtor accounts*" list screen, select the account.

If you wish to delete more than one (1) debtor (customer / client) account at a time, press the Ctrl key and keep it down while selecting the other debtor (customer / client) accounts to delete with a mouse click.

2. Click on the Delete button. A confirmation message is displayed.

"Are you sure you want to delete this account?"

Make sure absolutely sure that the correct debtor (customer / client) account is selected.

3. Click on the Yes button. A confirmation message is displayed:

   "Account deleted!"

4. Click on the OK button. This will permanently remove the debtor (customer / client) account.

Disable accounts

To disable a Debtor (customer / client) account:

1. If the debtor (customer / client) account has transactions and/or balances, you cannot delete it. A similar error message, is displayed:

   "1MDAVI Mr. Mike Davies
   This account has balances, cannot be deleted!"

2. Click on the OK button. To block posting of any documents or batch transactions for the debtor (customer / client), click on the Edit button and Accounting information tab.



3. Select (tick) the "*Account disabled*" field.

4. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with HelpNDoc's Clean and Efficient User Interface

Export / Import Debtor accounts

You may export and import debtor (customer / client) accounts and creditor (supplier / vendor).

This feature may be used to import debtor (customer / client) accounts and creditor (supplier / vendor) into:

- Into the same Set of Books.
- Into a different Set of Books.
- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for

Firebird database types.

- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

Before you may import debtor (customer / client) accounts and creditor (supplier / vendor) accounts in a new Set of Books, you need to do the necessary setup and configuration.

Once this is done, you may start to import ledger accounts from a valid saved file type.

The debtor (customer / client) accounts (Chart of Accounts) are maintained in Debtors (Default ribbon).

The creditor (supplier / vendor) accounts (Chart of Accounts) are maintained in Creditors (Default ribbon).

Reports for the accounts (Chart of Accounts) are printed in Reports → Ledger → Listing - Chart of Accounts (Reports ribbon).

Before using this feature, it is recommended to print the report.

Export / Import options on Setup ribbon

To be able to import the data for debtor (customer / client) accounts and creditor (supplier / vendor) accounts, you need to created a "*Tab delimited*" (*.txt) export file in the Export (Setup ribbon).

It is recommended that the debtor (customer / client) accounts and creditor (supplier / vendor) accounts is exported in the "*Tab delimited*" (*.txt) file format. This file format may be used to import the "*Tab delimited*" (*.txt) file format in the Import (Setup ribbon).

Spreadsheet export / import

osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx)* file type Spreadsheet import and export feature.

- Spreadsheet export - You may export debtor (customer / client) accounts and creditor (supplier / vendor) accounts and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import debtor (customer / client) accounts and creditor (supplier / vendor) accounts from a saved "*Excel Workbook (*.xlsx) file type.*

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Export Debtor accounts

All the information for each account as entered in Debtors (Default ribbon) (includes specific data for debtor accounts), will be exported in the selected file format.

Disabled debtor (customer / client) accounts ("Account disabled" field selected (ticked) on the Accounting information tab) will be excluded from the export file.

To export Debtor (customer / client) accounts:

1. On the Setup ribbon, select Export.
2. Click on the Debtors button.



3. Select and/or enter the following:

    a) Export to - The installation directory in which osFinancials5/TurboCASH5 is installed, will be displayed. You may click on the Browse icon to select a folder on the *Browse for Folder* screen. You may then select any available folder, or drive, on your system into which you wish to export the data.

b) File type - Select to export the file in the XML Database (*XML), Comma Separated Variable (*CSV), Lotus Spreadsheet File (*WK1), MS Excel Spreadsheet (*XLS), or any other format available on your system from the list.

> *It is recommended that the "(*.txt) Tab delimited" file type is selected to Import debtor (customer / client) accounts.*
>
> *It will create the following export file types for the export file name:*
>
> **.txt - Tab delimited text file - Recommended for Import on the Setup ribbon.*
>
> **.slk - Can be opened in spreadsheets of LibreOffice, OpenOffice or UltraOffice). You may save it as a a Microsoft excel file.*
>
> **.xml - Can be opened in your system's default web browser or Notepad.*

c) Export files name - Enter the File name. You need to select this file at a later stage when you wish to import the file, or analyse the data in a spreadsheet.

d) Log file - Enter the Log file name.

e) Range - From / To - The Debtors lookup will be automatically initiated. Select any range of accounts to include in the export file.

f) Increment Export - Leave this option blank.

4. Click on the Export button to create the export file, and save it in the specified directory.

> *The information for the Debtors, which will be exported, is:*
>
> - *Account code.*
> - *Description or name.*
> - *Contact persons.*
> - *Account code.*
> - *Postal and Delivery addresses.*
> - *Two Telephone numbers and Fax number.*
> - *E-mail addresses.*
> - *Credit limits.*
> - *Charge amounts.*
> - *Discount.*

- *Monthly interest percentage.*
- *Discount.*
- *Disabled account indicator.*
- *Open item debtor indicator.*
- *Statement messages.*
- *Reporting groups 1 and 2.*
- *Salespersons.*
- *The last date a transaction was entered for the debtor accounts, will also be included into the selected export file.*

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

Import Debtor accounts

This option will allow you to import data for debtor (customer / client) records from a valid file format into an existing Set of Books. To be able to import the data for debtor (customer / client) records, you need to have created a valid "*Tab delimited*" file on your system in Export (Setup ribbon).

To import Debtor (customer / client) accounts:

1. On the Setup ribbon, select Import. The "*Import Data into osFinancials*" screen is displayed:



2. Select Debtors/Creditors as the "*Data type to import*".

3. Select the "*Tab delimited*" (recommended) option.

4. Click on the >> button to locate the data file. The following screen is displayed:



5. Click on the button to locate the data file.

Optional - You may click on the View file button to view the file in your system's default app (program) associated with th

An example of the exported Tab Delimited text file is as follows:



6. Click on the >> button. The following screen is displayed:



7. Click on the Import button. The "*ImportCheck*" screen is displayed



8. You may use the record buttons to add, delete or change the debtor (customer / client) accounts on the "*ImportCheck*" screen. You may then click on the All or OK buttons to import the debtor (customer / client) accounts.

9. Once the import process is finished an information message is displayed:

   "Data file import completed!"

10. Click on the OK button.

11. Go to the Reports ribbon and select Reports → Debtors → Listing menu to check that the debtor (customer / client) accounts are correct.

12. If you need to edit the debtor (customer / client) accounts, go to the Default ribbon and select Debtors.

Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Export Debtor accounts - Open text file in spreadsheet

To illustrate the exported fields and data, the exported text file (created on the Export option of the Setup ribbon) is opened in a spreadsheet.

If the exported text file does not open in Microsoft Excel; or if you do not have Microsoft Excel installed on your system, you may open the file with OpenOffice, LibreOffice, Ultra Office, etc.

On your spreadsheet application, open the debtor (customer / client) accounts saved text (*.txt) file and confirm your tab delimited settings on the "*Text Import*" screen.



This will open your exported text file of the selected debtor (customer / client) accounts in a spreadsheet.

An example of the exported file opened in "*LibreOffice Calc*" spreadsheet, is as follows:



The exported data will be exported in forty-six (46) columns:

Column	Column heading	Source / fields	Field location (main form / tab)	
A	SACCOUNTCODE	Debtor code	Main form	String (6)
B	SDescription	Name (Account description)	Main form	String (35)
C	SContactName	Contactperson	Main form	String (35)
D	SPostCountry	Postal address country	Main form	String (35)
E	SDelCountry	Delivery address country	Delivery address tab	String (64)
F	SPOSTAL1	Address	Main form	String (30)
G	SPOSTAL2	Address 2	Main form	String (30)
H	SPOSTAL3	Address 3	Main form	String (30)
I	SPOSTALCODE	Postal code	Main form	String (8)
J	SDELIVERY1	Delivery address	Delivery address tab	String (30)
K	SDELIVERY2	Address 2	Delivery address tab	String (30)
L	SDELIVERY3	Address 3	Delivery address tab	String (30)
M	SDeliveryCode	Delivery code	Delivery address tab	String (8)
N	STELEPHONE	Telephone	Main form	String (20)

	1	*1*		
O	*STELEPHONE 2*	*Telephone 2*	*Main form*	*String (20)*
P	*SEMAIL*	*E-Mail*	*Main form*	*String (50)*
Q	*SFAX*	*Fax*	*Main form*	*String (20)*
R	*FCREDITLIMIT*	*Credit limit*	*Accounting information tab*	*Float(numeric)*
S	*FCHARGEAMOUNT*	*Charge amount*	*Accounting information tab*	*Float(numeric)*
T	*FDISCOUNT*	*Discount*	*Accounting information tab.*	*Float(numeric)*
U	*FInterest*	*Interest*	*Accounting information tab*	*Float(numeric)*
V	*BOPENITEM*	*Open item*	*Accounting information tab*	*B=CheckBox* *1 = Open item account (True - checked)* *0 = Not an Open item account (False - not checked)*
W	*BINACTIVE*	*Inactive*	*Accounting information tab*	*B=CheckBox* *1 = Account disabled (inactive) - (True - checked)* *0 = Account enabled (active) - (False - not checked)*
X	*SMESSAGE*	*Message*	*Delivery address tab*	*String (50)*
Y	*WDEFAULTPRICETYPEID*	*Default selling price*	*Accounting information tab*	*Integer*
Z	*DLASTACTIVITY*	*Last invoice*		*Date*
AA	*SREFERENCE*	*Tax reference*	*Main form*	*String (20)*

AB	*SBANKNAME*	*Bank name*	*Accounting information tab*	*String (20)*
AC	*SBRANCHCODE*	*Bank account type*	*Accounting information tab*	*String (10)*
AD	*SBANKACCOUNTNUMBER*	*Bank account no.*	*Accounting information tab*	*String (45)*
AE	*SBANKACCOUNTNAME*	*Bank account name*	*Accounting information tab*	*String (30)*
AF	*SCREDITCARDNUMBER*	*Credit card number*		*String (35)*
AG	*SCREDITCARDTYPE*	*Credit card type*		
AH	*SCREDITCARDHOLDER*	*Credit card holder*		*String (20)*
AI	*WDUEDAYS*	*Due days*	*Accounting information tab*	*Integer*
AJ	*SCOMPANYREGNO*	*Company reg. no.*	*Main form*	*String (35)*
AK	*SFREEFIELD1*	*Statement message 1*	*Delivery address tab*	*String (35)*
AL	*SFREEFIELD2*	*Statement message 2*	*Delivery address tab*	*String (35)*
AM	*SFREEFIELD3*	*Statement message 3*	*Delivery address tab*	*String (35)*
AN	*SGroup1*	*Debtor group 1*	*Main form*	*String (30)*

AO	*SGroup2*	*Debtor group 2*	*Main form*	*String (30)*
AP	*SSalesperson*	*Salesperson*	*Main form*	
AQ	*SCurrency*	*Currency*		*String (35)*
AR	*SForeExAccount*			
AS	*SDEFAULTACCOUNT*	*Use default account*	*Accounting information tab*	
AT	*SDEFAULTTAX*	*Use default tax*	*Accounting information tab*	

Created with the Standard Edition of HelpNDoc: Make your documentation accessible on any device with HelpNDoc

Export Debtor accounts - Export grid

The Export button of the sidebar of the "*Debtor accounts*" list screen, will create a text file (tab delimited), which will open in your system's default Microsoft Excel (if installed on your system).

Export options

To export debtor (customer / client) accounts:

On Debtors (Default ribbon).

Select the Filter and search options in the Filter column and click on the Filter button to include only those filter criteria to be included in the Export file.

By default, the export file will include all the debtor (customer / client) accounts (excluding disabled accounts).

To include disabled debtor (customer / client) accounts in the export file, you need to select the "Show

disabled" option, and click on the Filter button.

Click on the Export button.



The "*Save As*" screen is displayed:



Enter a name to save the file.

"Save as type :" options will be empty. A text (.txt) file type will automatically be created with your file name.*

If you do not enter a unique name in the selected folder, and save the export.txt file name, you may replace existing (previously exported) files.

If an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "F:\exports\your-file-name.txt". The process cannot access the file because it is being used by another process.

Click on the Save button.

Example : Exported text file - Microsoft Excel

In this example, the exported file is automatically opened in "*Microsoft Excel*":



Only those accounts matching your filter and search criteria in the Filter column options, will be included in the export file.

For example, if the postal code (zip code), is specified, only those accounts for the specific postal code will be included in the export file.

All the columns will be exported in the default sequence.



Example : Exported text file - Notepad

An example, of the exported text file file opened in your systems default program associated with *.txt files (e.g. "*Notepad*") is as follows:



Example : Exported text file - LibreOffice Calc

If the exported text file does not open in Microsoft Excel; or if you do not have Microsoft Excel installed on

your system, you may open the file with OpenOffice, LibreOffice, Ultra Office, etc.

Locate the exported text file in your System's File Explorer.

In this example, Open with > LibreOffice Calc is selected. The "*Text Import*" screen is selected.



If LibreOffice and not LibreOffice Calc is selected, the exported text file will open in LibreOffice Writer as a text file.



Separator options - Separated by

Tab is the only option which should be selected for this exported text file. This may differ for some other report types.



Created with the Standard Edition of HelpNDoc: Elevate Your Documentation Process with HelpNDoc's Advanced Features

Spreadsheet Export / Import - Debtor / Creditor accounts

osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet export and import feature.

- Spreadsheet export - You may export debtor (customer / client) accounts and creditor (supplier / vendor) accounts and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import debtor (customer / client) accounts and creditor (supplier / vendor) accounts from a saved "*Excel Workbook (*.xlsx) file type.*

This feature may be used to import debtor (customer / client) accounts and creditor (supplier / vendor) accounts into:

- Into the same Set of Books.
- Into a different Set of Books.
    - Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types
    - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

> *Before you may import debtor (customer / client) accounts and creditor (supplier / vendor) accounts in a new Set of Books, you need to do the necessary setup and configuration.*
>
> *Once this is done, you may start to import debtor (customer / client) accounts and creditor (supplier / vendor) accounts from a saved "Excel Workbook (*.xlsx) file type.*

After import

> *To check the imported account details, you may print the necessary listing reports for debtor (customer / client) accounts and listing reports for creditor (supplier / vendor) accounts from the Set of Books in which you created the export file.*

You may go to Debtors (Default ribbon) to view and/or edit the imported debtor (customer / client) accounts.

You may go to Creditors (Default ribbon) to view and/or edit the imported creditor (supplier / vendor) accounts.

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Spreadsheet - Export - Debtors / Creditor accounts

This option will allow you to Export your debtor (customer / client) accounts and creditor (supplier / vendor) accounts into an Excel spreadsheet. You may then add new debtor (customer / client) accounts, edit existing debtor (customer / client) accounts and import it back into your stock code file.

The debtor (customer / client) accounts are maintained in Debtors (Default ribbon).

The creditor (supplier / vendor) accounts are maintained in Creditors (Default ribbon).

To export debtor (customer / client) and creditor (supplier / vendor) accounts to a Excel Workbook (xlsx) file:

1. On the Setup ribbon, select Import.
2. Select "*Debtors/Creditors*".



3. Click on the Excel import export button. The Excel spreadsheet will be displayed with the column headings (database table) for the debtor (customer / client) accounts and creditor (supplier / vendor) accounts (without any data).



4. Click on the Export icon. The data from your debtor (customer / client) accounts and creditor (supplier / vendor) accounts will be imported (populated) into the spreadsheet.



5. You may add new accounts, edit the accounts, change the addresses, credit limits, charge amounts, etc., whatever field, is necessary.

6. Click on the Save as... icon (View ribbon) to save the data in the "*Data Import Export*" spreadsheet as an "*Excel Workbook (*.xlsx)*" file.



7. Select the folder and enter a name for the file.

8. Click on the Save button.

9. Click on the Close icon in the titlebar of the "*Data Import Export*" screen.

Spreadsheet columns

The data of the debtor (customer / client) accounts and creditor (supplier / vendor) accounts are imported (populated) in forty-six (46) columns in the spreadsheet, and is as follows:

		Field name	*Values*	*Comments*
	A	*SACCOUNTCODE*	*Account code prefixed by account type:* *C = Creditors* *D = Debtors*	*When creating creditor or debtor accounts, the code should start (prefixed). Another example is :* *1 = Debtors* *2 = Creditors*
	B	*SDESCRIPTION*	*Alpha-numeric*	*Name or description of debtor / creditor account*
	C	*SCONTACTNAME*	*Alpha-numeric*	*Name or description of contact*
	D	*SPOSTAL1*	*Alpha-numeric*	*Postal address 1*
	E	*SPOSTAL2*	*Alpha-numeric*	*Postal address 2*

	F	SPOSTAL3	Alpha-numeric	Postal address 3
	G	SPOSTALCODE	Alpha-numeric	Postal code / Zip code
	H	SPOSTCOUNTRY	Alpha-numeric	Country
	I	SDELIVERY1	Alpha-numeric	Delivery address 1
	J	SDELIVERY2	Alpha-numeric	Delivery address 2
	K	SDELIVERY3	Alpha-numeric	Delivery address 3
	L	SDELIVERYCODE	Alpha-numeric	Delivery code / zip code
	M	SDELCOUNTRY	Alpha-numeric	Country
	N	STELEPHONE1	Alpha-numeric	Telephone 1
	O	STELEPHONE2	Alpha-numeric	Telephone 2
	P	SEMAIL	Alpha-numeric	E-mail address
	Q	SFAX	Alpha-numeric	Fax number
	R	FCREDITLIMIT	Numeric	Credit limit
	S	FCHARGEAMOUNT	Numeric	Charge amount (Generate multiple transactions) in Batches.
	T	FDISCOUNT	Numeric	Discount percentage - Only applicable to Debtor accounts
	U	FINTEREST	Numeric	Percentage - Only applicable to Debtor accounts
	V	BOPENITEM	0 = Not set as open item 1 = Open item account	
	W	BINACTIVE	0 = Active 1 = Disabled (inactive)	

	X	SMESSAGE	Alpha-numeric	Statement message for debtors Remittance message for creditors
	Y	WDEFAULTPRICETYPEID	Numeric	ID of Selling price 1 / 2 / 3 selected for debtor accounts
	Z	DLASTACTIVITY	Date	
	AA	SREFERENCE	Alpha-numeric	
	AB	SBANKNAME	Alpha-numeric	
	AC	SBRANCHCODE	Alpha-numeric	
	AD	SBANKACCOUNTNUMBER	Alpha-numeric	
	AE	SBANKACCOUNTNAME	Alpha-numeric	
	AF	SCREDITCARDNUMBER	Alpha-numeric	
	AG	SCREDITCARDTYPE	Alpha-numeric	
	AH	SCREDITCARDHOLDER	Alpha-numeric	
	AI	WDUEDAYS	Numeric	Number of days used for ageing and due date
	AJ	SCOMPANYREGNO	Alpha-numeric	
	AK	SFREEFIELD1	Alpha-numeric	Statement message for debtors line 1

	AL	SFREEFIELD2	Alpha-numeric	
	AM	SFREEFIELD3	Alpha-numeric	
	AN	SGROUP1	Alpha-numeric	Debtor / Creditor Reporting group 1
	AO	SGROUP2	Alpha-numeric	Debtor / Creditor Reporting group 2
	AP	SSALESPERSON	Alpha-numeric	Name of Salesperson (only applicable to debtor accounts)
	AQ	SCURRENCY		
	AR	SFOREEXACCOUNT		
	AS	SDEFAULTACCOUNT		Ledger account code (selected)
	AT	SDEFAULTTAX		Tax account code (selected)

Created with the Standard Edition of HelpNDoc: Elevate Your Documentation Process with HelpNDoc's Advanced Features

Spreadsheet - Import - Debtors / Creditor accounts

This option will allow you to import creditor (supplier / vendor) accounts from a valid an Excel spreadsheet in the Excel Workbook (xlsx) file format. You may then add new creditor (supplier / vendor) accounts, edit existing creditor (supplier / vendor) accounts and import it back into your Set of Books.

To export debtor (customer / client) and/or creditor (supplier / vendor) accounts to a Excel Workbook (xlsx) file:

1. Open the Set of Books in which, you wish to import debtor (customer / client) accounts and creditor

(supplier / vendor) accounts from a valid a spreadsheet export file.

2. On the Setup ribbon, select Import.

3. Select Debtors/Creditors as the "*Data type to import*".



4. Click on the Excel import export button. The Excel spreadsheet will be displayed with the column headings (database table) for the debtor (customer / client) accounts and creditor (supplier / vendor) accounts (without any data).



5. On the "*Data Import Export*" screen, click on the Open icon to select a valid Excel Workbook (*.xlsx) file.



You may click on the "Show preview pane" icon on the "Open" screen to display a preview of the selected file to open (import) in the "Data Import Export" screen..

7. The data of the debtor (customer / client) accounts and creditor (supplier / vendor) accounts included in the valid Excel Workbook (xlsx) file, will be imported (populated) into the spreadsheet ("*Data Import Export*" screen).



7. Click on the Import icon.

Optional - Show data before import setting

The "ImportCheck" screen (if the Import the "Show data before import" option was selected (ticked) on the "Data Import Exp screen) is displayed:



Click on the All or OK buttons to start the import process.



8. Once the import process is finalised, Column A will be in a green background colour.

9. Close the "*Data Import Export*" spreadsheet screen.

10. You may go to Debtors (Default ribbon) to view and/or edit the imported debtor (customer / client) accounts. You may go to Creditors (Default ribbon) to view and/or edit the imported creditor (supplier / vendor) accounts.

Created with the Standard Edition of HelpNDoc: Effortlessly Publish Your Word Document as an eBook

Creditor (supplier / vendor) accounts

The Creditors feature in osFinancials5/TurboCASH5 is specifically designed to manage and maintain creditor (supplier/vendor) accounts. This feature provides a range of functionalities to effectively manage these accounts and ensure smooth supplier/vendor relationship management. Here are some key aspects of the Creditors feature:

1. Account Management: You can create new creditor accounts, modify existing ones, delete or disable accounts based on your requirements. This gives you control over the creditor database and allows you to keep it up to date.
2. Account Details: Within each creditor account, you have the flexibility to make changes to various aspects, such as the creditor's name, contact details, addresses, and messages on the creditor form. You can also manage the delivery address and select specific document layout files on the Delivery address tab. Additionally, you can set accounting and payment terms, including discounts and charges, on the Accounting information tab. This ensures that you maintain accurate and up-to-date information for each creditor.
3. Activities Tracking: The Creditors feature allows you to efficiently manage various activities related to creditor accounts. It provides dedicated tabs for tracking Contacts, Appointments, and transactions on the Documents, Transactions, Bank accounts and Stock items tabs. These capabilities enable you to gain a comprehensive view of interactions and transactions with each creditor, enhancing your ability to manage and maintain fruitful relationships.
4. Filtering and Search: osFinancials5/TurboCASH5 provides filtering and search options within the Creditors feature, enabling you to easily locate specific creditor accounts based on various criteria such as name, contact details, or other relevant information.
5. Reporting Groups: You can create up to two custom reporting groups for creditor accounts, categorizing them by attributes like geographic regions, supplier types, or purchase channels. This enables you to generate insightful views of your creditor data. It allows you to slice and dice the information based on multiple dimensions and conduct detailed analysis, providing a comprehensive view of your creditor data and supporting better decision-making and strategic planning.

By leveraging the Creditors feature in osFinancials5/TurboCASH5, you can efficiently manage supplier/vendor accounts, streamline communication, track transactions, and maintain precise financial records. This enhances supplier/vendor relationships, boosts efficiency, and strengthens financial management within your organization.

To access the Creditor selection screen:

1. On the Default ribbon, select Creditors (F5). The "*Creditor accounts*" screen is displayed:



2. Once a creditor (supplier / vendor) account is selected, you may view and manage the activities in the following tabs:

   a) Contacts - Add / edit / delete contactpersons.

   b) Appointments - View a list of events or appointments scheduled in the Calendar.

   c) Documents - View a list of the posted as well as the unposted purchase documents (i.e. Purchases, Supplier returns and Orders). You may select a document and print it. You may also print a Posted batches report for the posted purchase documents (i.e. Purchases, Supplier returns and Orders).

   d) Transactions - View a list of the transactions posted in batches as well as purchase documents (i.e. Purchases, Supplier returns and Orders). You may select a transaction and print a Posted batches report and print the transactions in the T-Account viewer.

   e) Bank accounts - Manage references for the Bank import plugin.

   f) Stock items - View a list of the products (stock items) in posted as well as unposted purchase

documents (i.e. Purchases, Supplier returns and Orders) for the selected creditor (supplier / vendor) account.

3. Buttons –

   a) New – Create a new creditor (supplier / vendor) account.

   b) Delete – Delete remove a selected creditor (supplier / vendor) account.

   c) Edit – Add or change the details of a selected creditor (supplier / vendor) account.

   You may also double click on a selected creditor (supplier / vendor) account.

   d) Save – Save any changes to a selected creditor (supplier / vendor) account.

   e) Cancel – Cancel will revert to the previous values. Any changes will not be saved.

   f) Export - Export the view of your debtor data as displayed in the list of creditors (supplier) accounts. Only those records matching your sort, search and filter options will be exported.

4. Search Filter –

   a) Filter Column - None is the default. You may select any of the available items (columns), (e.g. Creditor code, Name, Contact Person, Creditor group 1, Creditor group 2, Address 1, Address 2, Address 3, Postal code, Telephone 1, Telephone 2, Fax, E-mail, Bank account type, Bank account no., Last invoice, Reference, Due days, Creditor group 1 Sort, Creditor group 2 Sort, Delivery address, Delivery address2, Delivery address 3, Delivery address postal code, Delivery address country, X, etc.).

   b) Like – Default operator. Others that may be selected is <, >, <=, >=, <>.

   c) Value – Enter the text e.g. city, telephone numbers, postal code etc.

   d) Filter button – Click to filter / search for your criteria.

   e) Clear button – Click to clear / reset the filter / search for your criteria.

   f) Show disabled - By default, this option is not selected (not ticked). Only those active (enabled) creditor (supplier / vendor) accounts will be listed. Select (tick) this option to include those inactive (disabled) (Account disabled field selected (ticked) on the Accounting information tab) creditor (supplier / vendor) accounts.

5. Line count – This will display the number of records (creditor (supplier / vendor) accounts) that is

available on the list. This will display the number of records (rows / creditor (supplier / vendor) accounts) that matches your filter / search criteria.

6. Context menu – The following options are available:

   a) Reports – You may print postal or delivery address labels for selected creditor(s) (supplier(s)). You may also print these labels from the Reports → Creditor → Print labels (Reports ribbon).

   b) Creditor group 1 / 2 - Change the reporting group 1 or 2.

   c) Copy account - Create a new account from a selected account.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

Creditor groups

This option allows you to set up to two Reporting groups for your Creditors (suppliers / vendors). Creditor groups allows you to group or categorise the Creditor accounts on which you would like to report. Reporting groups for creditors can vary depending on the specific needs and requirements of your business.

These Creditor groups can be linked to each creditor (supplier / vendor) account.

- *You may use the context menu option on the creditors grid to set or change the reporting groups for Creditor group 1 and/or Creditor group 2 for selected creditor account(s).*
- *You may use the creditors grid to filter, search or group creditor accounts.*
- *You may print Creditor listing reports and Print labels for postal addresses and delivery addresses for all or only for creditor accounts linked to a selected creditor group or groups.*
- *You may print Purchase analysis reports for Creditor group 1 or Creditor group 2.*

Examples of reporting groups for creditors (suppliers / vendors)

Here are a few examples of reporting groups that you can use for creditor accounts:

1. Industry: You can create reporting groups based on the industries or sectors your creditors belong to. For example, you may have reporting groups such as "IT Suppliers," "Marketing Services," or "Office Supplies."

2. Geographic region: If you work with creditors from different geographic regions, you can create reporting groups based on their locations. This can be helpful for analysing regional expenses or managing relationships with regional suppliers.

3. Payment terms: You can create reporting groups based on the payment terms agreed upon with your creditors. For instance, you might have reporting groups such as "*Net 30 Days*," "*Net 60 Days*," or "*Early Payment Discount*."

4. Vendor type: If you deal with different types of vendors or suppliers, you can categorize them using reporting groups. This could include groups like "*Manufacturers*," "*Wholesalers*," or "*Service providers*."

5. Contractual agreements: If you have specific contracts or agreements in place with certain creditors, you can create reporting groups to track and manage those relationships. For example, you might have reporting groups for "*Preferred suppliers*" or "*Exclusive suppliers*."

Remember, these are just examples, and you can customize reporting groups based on the unique characteristics and needs of your business. The goal is to create groups that allow you to analyse and report on creditor data in a meaningful way that supports your financial management and decision-making processes.

Define reporting groups for creditors (suppliers / vendors)

To set reporting groups for Creditor accounts:

1. On the Setup ribbon, select Setup → Groups. The "*Groups (Account group 1)"* default screen will be displayed..

2. Click on the Creditor group 1 button.



3. If you wish to rename the Reporting group name - Creditor group 1, over-type the description with your new description. This will change the description of the button for Creditor group 1.

4. To add a new Group to the root directory or list, select the "*REPORTING GROUP ROOT*" on the list and click on the New button.

5. Enter the name of your Creditor group 1 and click on "*REPORTING GROUP ROOT*" on the list.

6. Repeat the process until you have entered all the Creditor groups, etc.

> *Adding sub groups for creditor groups:*
>
> *Select a Creditor group, for example; "Creditor group 1A" and click on the New button. Enter the name of your sub group.*

7. If you need to add Reporting group 2 for Creditors, click on the Creditor group 2 button and repeat the process as for Creditor group 1.

8. Click on the OK button to save your changes and close (exit) this screen.

> *Changing the sequence of groups for creditors:*
>
> *Select a Creditor group, for example; "Creditor group 1B" and click on the Move up or Move down button. This will list the creditor group according to your preferred sequence.*

> *You may click on the Print button to print a list of your creditor groups.*

> *You may set colours to display on the Creditor accounts grid screen. To do this, click on the Back colour button to set the rows background colour and the Font colour button to set the Font colour.*
>
> *To retain and save the selected colors, you also need to set both the "Back color" and the "Font color".*

Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

Creditors filter and search options

The osFinancials5/TurboCASH5 grid has a powerful and user-friendly filtering and sorting system that makes it quicker and easier than other methods. With just a few mouse clicks, you can group, sort, and

filter any column(s) of data on most screens in a Set of Books. This feature is very useful and efficient for managing and analysing data.

Account disabled

By default, only active creditor (supplier / vendor) accounts will be listed when launching the Creditors on the Creditor list screen.

To list the creditor (supplier / vendor) accounts which have been set to "*Disabled*" on the Accounting information tab, you need to tick the "*Show disabled*" tick box and click on the Filter button.



The "Creditor - Credit control listing (Credit limit vs Current balance) as at..." report will display if a creditor (supplier / vendor) account is disabled, or enabled.

If the "Show disabled" option is selected, and if you close active forms or when you reopen the Set of Books, it will by default list only the active (enabled) creditor (supplier / vendor) accounts.

Search by options

You may use the filter options to find a specific document, or all documents with the same values, in any of the twenty-eight (28) columns:

Default	*Sorted (selected) - Alphabetical list*



To search for specific creditor (supplier / vendor) accounts:

1. The filter options will display only those creditor (supplier / vendor) accounts in your search or filter criteria. To do this, you may:



   a) Search by - The default option is none. It will list all the column headings. You may select any of these as an option.

   b) Like - Operator to find all documents with the same value, values greater than, smaller than, greater than or equal to, smaller than or equal to the values you have selected, or wish to enter.

   c) Value - Enter the value for the field type you have selected, for example, Postal code (if you have selected "*Postal code*" as the "*Search by*" option).



2. Once you have selected or specified the search criteria, click on the Filter button. Only those creditor

(supplier / vendor) accounts as in your search or filter criteria or options will be listed.

3. If you need to clear your filter options and values, click on the Clear button. You may also click on any of the column headings to change the sorting sequence of the creditor (supplier / vendor) accounts listed.

The "Line count" will show the number of records (creditor (supplier / vendor) accounts) that matches your search or filter criteria.

You may also search for creditor (supplier / vendor) accounts in the "Investigator" screen (Search (Setup ribbon)).

Column headings

All the data for each of your creditor (supplier / vendor) accounts are listed in twenty-eight (28) columns. To view change the sequence in which the data is displayed, you may use the following options:

- Scroll bars - Scroll to the right or to the left on the horizontal scroll bar to view the information.
- Sequence of rows - Click on any of the column headings to change the sorting sequence of the creditor (supplier / vendor) accounts listed in the descending or ascending sequence.
- Sequence of columns - Click on a column heading and drag it to the right or to the left to change the sequence in which the columns need to be displayed.



You may drag and drop any of the columns on the data band to the left band and the columns from the left band to the data band, to customise the grid for your requirements.

The sequence of the columns as set will be retained if you close active forms or when you reopen the Set of Books.

Show / hide bands

All the data for each of your creditor (supplier / vendor) accounts are listed in twenty-eight (28) columns. It is listed in two (2) bands:

Left band - Contains the Creditor code and Name.

Data band - Contains the rest of the data columns.



You may drag and drop any of the columns on the data band to the left band and the columns from the left band to the data band, to customise the grid for your requirements.

To hide the columns on the Left band, remove the tick in the first block.

To hide the columns on the Data band, remove the tick in the second block.

Show / hide columns

Click on the second block - Column headings - All the columns will be listed.

Remove the ticks for the columns to hide or select the columns you need to display.

You may use the Up arrows and/or the Down arrows Right or Left arrows keys to navigate the fields. You may use the Space bar to deselect (remove the tick) or to reselect (tick a field again).



Group columns

You may drag any column heading to the column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns will be grouped.

Select a column and click on it. While holding the mouse button down, drag it to the "*Use your mouse to pull a column here to group on that column*" bar. Select any other column to drag and drop it on the the "*Use your mouse to pull a column here to group on that column*" bar. You may select as many columns, as necessary, to group your data.

You may also drag and drop these columns to the right or left to change the grouping of these columns.



To remove a column from the "*Use your mouse to pull a column here to group on that column*" bar, you may use the following two (2) options:

1. Select the column heading (e.g., "*Postal code*") on the "*Use your mouse to pull a column here to group on that column*" bar, and drag it to the first line (above the column headings). When the mouse pointer change to a big X, drop it. The column will automatically be placed in the correct default sequence (or the place of the previous saved grid layout).
2. If you wish to change the column to a specific place, select the column heading (e.g., "*Postal code*") on the "*Use your mouse to pull a column here to group on that column*" bar, and drag it to the second line (column headings). When you drop it, the column will be added to the selected position or sequence of the columns.



Filter options : Column headings

If you need to view or find specific data, there are various options available to locate and find your data. Some of the options are:



- Sort - Click on a column heading to sort and list the data ascending or descending sequence. All the data is by default displayed ascending; from the smallest to the highest value (e.g. a-z or 0-9) according to the record number (e.g. line number in a batch, etc.) To change the sort order from

ascending (e.g. a-z or 0-9) to descending (e.g. z-a or 9-0) select a column and click on it. If you click on it again it will change back to ascending sequence.

- Drag and drop columns - You may click on a column and drag it to the left or to the right to change the sequence your data is displayed on screens.
- Filter - Click in the arrow to list the data in a specific column. A list displaying the data, as well as an All option and a Custom... option in the selected column will be displayed. By adding a tick next to a specific data, only the data, matching that amount will be listed.
- Custom - You can easily build customised filters according to your needs. These filter files can be saved and opened for future use.

Custom filters

Once you have selected data from the list in a column, the your selection will be displayed at the bottom section of the "*Creditors list*" screen as follows:



To temporarily clear the filter (show all records, remove the tick. To show the filtered records, add the tick again.

- To delete the filter, click on the close icon.

You may click on the (Custom...) option on a column list; or click on the Customise... button to:

1. Make a filter (add or delete conditions and groups).

2. Save a filter.

3. Open a filter.

Make a custom filter

To make a filter:

1. Click on the (Custom...) option on a column list; or click on the Customise button.

2. Select an operator (i.e. and, or, and not, or not).

3. Click on the Filter button (or on the ... button) and select one of the following options on the context menu:

    a) New Condition

    b) New Group

    c) Delete row (If you click on the Filter button, you may delete all rows (conditions and groups)).

4. Select a column from the list of available data applicable to the screen.

5. Select a filter condition. In this example, the Between is selected. Another field is opened to select another date.

6. Once you have created your conditions or groups, click on the Apply button.

7. Click on the OK button to close and exit this "*Make filter*" screen.

Conditions



1. Equal to - list or display all values which is the same as the specified value.
2. Not equal to - list or display all values which is not the same as the specified value.
3. Less than - list or display all values smaller than the specified value.
4. Less than or equal to - list or display all values smaller or equal to the specified value.
5. Greater than - list or display all values greater than the specified value.
6. Greater than or equal to - list or display all values greater or equal to the specified value.
7. Like - list all values in the table similar to the specified value.
8. Not like - list all values in the table not similar to the specified value.
9. Contains - list all values in the table, which contains specified value.
10. Does not contain - list all values in the table, which does not contain specified value.
11. Begins with - starts with the specified value in the table.
12. Ends with - ends with the specified value in the table.
13. Is null - excludes any value entered, will not be listed or displayed.
14. Is not null - is not zero - any value which is not equal to zero will be listed or displayed.
15. Between - Specify specific values, etc. to include only matching values.
16. Not between - Specify specific values, etc. to exclude values.
17. In - In a specified value.
18. Not in - Not in a specified value.

Save custom filter files

To save a custom filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Save as... button. The "*Save active filter*" screen will be displayed.
2. Select a Directory in which you wish to save the custom filter file.
3. Enter a file name.
4. Click on the Save button to save the Filter in a (*.flt) Filter file format. You may then at any later stage open the saved *.flt file.

Open custom filter files

To open a saved a custom filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Open... button. The "*Open a saved filter*" screen will be displayed.
2. Select a Directory in which you have saved the custom filter file.
3. Select a valid filter file.

---

4. Click on the Open button. The selected filter file's name will be displayed in the titlebar of the "*Make filter*" screen.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Creditor - Context menu

Right-click to display the following context menu:



The following options are available:

1. Reports – You may print postal or delivery address labels for selected creditor(s) (supplier(s)). You may also print these labels from the Reports → Creditor → Print labels (Reports ribbon).

2. Creditor group 1 / 2 - Change the reporting group 1 or 2.

3. Copy account - Create a new account from a selected account.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Creditor - Context menu - Set Creditor Group 1/2

You may change the Creditor group 1 and/or Creditor 2 for selected creditor (supplier / vendor) account(s).

To change the Creditor group 1 or 2:

1. On the Creditors (Creditors list screen) (Default ribbon), select the creditor (supplier / vendor) account(s).

> *If you need to select multiple* creditor (supplier / vendor) account(s), *press the Ctrl or Shift key and click on each* creditor (supplier / vendor) account, *for which you need to change the*

	creditor reporting group.

2. Right-click and select "*Creditor group 1*" or "*Creditor group 2*" on the context menu.

3. Select "*Empty*" or the available creditor group from the sub-menu. The "*Creditor group 1*" or "*Creditor group 2*" will change on reports.



Created with the Standard Edition of HelpNDoc: Easily create EBooks

Creditor - Context menu - Reports

The "*Reports*" context menu option allows you to print postal or delivery address labels for a selected creditor (supplier / vendor) account.

To print labels for a selected creditor (supplier / vendor) account:

1. On the "*Creditors*" list screen, select a creditor (supplier / vendor) account.

2. Right-click and select "*Reports → Selected creditor label*" option or the select "*Reports → Selected creditor delivery label*" option on the context menu. This will print the postal address label or the delivery address label of the selected creditor (supplier / vendor) account.



You will only be allowed to print the postal address label or delivery address label for one selected creditor (supplier / vendor) account at a time.

An example of a printed postal address labels, is as follows:



An example of a printed delivery address labels, is as follows:



You may also print the Postal address labels or Delivery address labels for creditor (supplier / vendor) accounts from the Reports → Creditors → Print labels (Reports ribbon).

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

Creditor - Context menu - Copy account

The "*Copy account*" context menu option allows you to create a copy of a selected creditor (supplier / vendor) account.

To copy a selected creditor (supplier / vendor) account:

1. On the "*Creditors*" list screen, select a creditor (supplier / vendor) account.

2. Right-click and select the "*Copy account*" option on the context menu.



3. This will create a copy of the of the selected creditor (supplier / vendor) account.



4. Enter the Creditor code.

The next Creditor code (e.g. D00008, etc.), will automatically be generated. It is important to prefix Creditor codes with a unique prefix. In this documentation, the accounts is prefixed as follows:

Debtor code = 1

Creditor code = 2

The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens.

If you have created a Set of Books (Advanced option), and have set the Account code to:

W *4-digits, you may enter a 7-digit Account code (a prefix followed by 6 characters).*

W *5-digits, you may enter a 8-digit Account code (a prefix followed by 7 characters).*

W *6-digits, you may enter a 9-digit Account code (a prefix followed by 8 characters).*

W *7-digits, you may enter a 10-digit Account code (a prefix followed by 9 characters).*

W *8-digits, you may enter a 11-digit Account code (a prefix followed by 10 characters).*

5. Edit the copied fields, where necessary.

Note the following:

- *The contact person is not copied on the new account.*
- *On the Accounting information tab, all the terms and conditions (e.g. Due days, Credit limit, Charge amount, etc.) is copied.*
- *No information is copied on the Contacts, Appointment, Documents, Transactions, Bank accounts, and Stock items tabs.*

Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

Creditor accounts edit form

To create add / edit a creditor (supplier / vendor) account:

1. If you do not find a creditor (supplier / vendor) account, you may add it by clicking on the New button.

It will launch the blank creditor (supplier / vendor) account with the next account number (i.e. C000001, etc.). You only need to replace the Creditor code, enter the Name and save it. The rest of the fields are optional, but it is recommended that you fill in as much details as possible.

The next Creditor code (e.g. C00006, etc.), will automatically be generated. It is important to prefix Creditor codes with a unique prefix. In this documentation, the accounts is prefixed as follows:

Debtor code = 1

Creditor code = 2

The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens.



The following eight (8) tabs are used to enter and/or edit settings and check additional useful information to manage creditor (supplier / vendor) accounts:

- *Delivery address - Delivery address, Address 2, Address 3, Postal code, Country, Message, Message 1, Message 2 and Message 3 and Layout files for Orders, Purchases and Supplier return documents.*
- *Accounting information - Account disabled, Open item account, Due days (Payment date), Credit limit, Charge amount, Bank account (i.e. Bank account type, Bank account no., Bank name and Branch code), Use default account, Use default tax and Debtor code.*
- *Appointments - Any events or appointments have been scheduled in Calendar (Default ribbon) for that creditor (supplier / vendor) account will be listed.*
- *Documents - Any purchase documents (Orders, Purchases and Supplier return documents) have been processed for that creditor (supplier / vendor) account will be listed.*
- *Transactions - Any Debit and Credit transactions have been processed for that creditor (supplier / vendor) account will be listed.*

- *Bank accounts – This is used for the Bank import plugin.*
- *Stock items – This tab will list all the posted as well as unposted documents (i.e. purchase documents, supplier returns and orders) for the selected creditor (supplier / vendor) account.*

Plugins (e.g. Price agreements and Subscriptions), which may be purchased separately will be added as tabs on creditor (supplier / vendor) accounts. These will be dealt with in separate documentation.

2. Enter and/or select the following options:

a) Creditor code - It is automatically generated.

The *Creditor code* is automatically generated when you click on the New button. It is prefixed with a C, followed by 5 numeric characters. You may overtype this with your own to suit your specific requirements.

If you have created a Set of Books (Advanced option), and have set the Account code to:

- *4-digits, you may enter a 7-digit Account code (a prefix followed by 6 characters).*
- *5-digits, you may enter a 8-digit Account code (a prefix followed by 7 characters).*
- *6-digits, you may enter a 9-digit Account code (a prefix followed by 8 characters).*
- *7-digits, you may enter a 10-digit Account code (a prefix followed by 9 characters).*
- *8-digits, you may enter a 11-digit Account code (a prefix followed by 10 characters).*

b) Name - Enter the name (description) for the creditor (supplier / vendor).

c) Address - Enter up to 3 address lines.

d) Postal code - Enter the postal code or zip code.

e) Country - You may select the Country from the list, if necessary.

f) Phone 1 - Enter the phone number.

g) Phone 2 - Enter the phone number, if available.

h) Fax - Enter the fax number, if available.

i) Website - Enter the website address, if available.

You may double-click on this field to access the website of the creditor (supplier / vendor) in your system's default web browser.

j) E-mail - Enter the e-mail address, if available.

You may double-click on this field to launch the a new message to the creditor (supplier / vendor) in your system's default mail app / program.

k) Tax Reference - If creditors (suppliers) are exempt from tax, or registered for VAT/GST/Sales Tax, that tax reference should be entered in this field.

l) Company Reg. No. - Enter, if available.

m) Contact Person - Select a Contact Person from the list.

If no Contact Person is available, you need create it on the Contacts tab.

n) Creditor group 1 / 2 - The Reporting group to which you wish this creditor (supplier / vendor) to be allocated.

The description of Creditor group 1 and/or Creditor 2 you have entered on the "Reporting group name" field on the Creditor groups tab - Setup → Groups may be reflected on this screen.

o) Language - The list of language files in Switch language (Start ribbon) as maintained in Tools → Customise language (Setup ribbon) will be listed. You may select a preferred language for the creditor (supplier / vendor). If the standard translatable document layout files are selected, the documents (i.e. purchases, supplier returns and orders) will be printed in the selected language for creditor (supplier / vendor) account.

3. Click on the Delivery address tab and/or Accounting information tab to enter additional information, select settings and accounting terms.

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Creditor accounts - Delivery address tab

Delivery address tab - Enter delivery address, and messages and settings for layout files.

1. The Delivery address tab is the default when accessing the Creditors (Default ribbon).



2. Enter and/or select the following on the *Delivery address* tab, if necessary:

   a) Delivery address, Address 2, Address 3 - Enter up to 3 address lines.

   b) Postal code - Enter the postal code or zip code.

   c) Country - Default is *Empty*. You may select the Country.

   d) Message, Message 1, Message 2 and Message 3 - Enter the message for the creditor (supplier / vendor) account. This message will be displayed on remittance advises printed in Reports → Creditors → Remittance advises (Reports ribbon).

   e) Layout files

      If no layout files have been selected for the creditor (supplier / vendor) on this tab, the default settings as set for Purchases, Supplier returns and Orders (Setup → Documents setup) will be used.

      i) Layout file 1 – Purchases - Layout file - If you have a specific purchase layout file for the this creditor (supplier / vendor), you may select it.

      ii) Layout file 2 – Supplier returns - Layout file - If you have a specific Supplier returns layout file for the this creditor (supplier / vendor), you may select it.

      iii) Layout file 3 – Orders - Layout file - If you have a specific Order layout file for the this creditor (supplier / vendor), you may select it.

   f) Send document type - This is only applicable to the E-mailPro plugin. Print document is the default. Other options are; Print document and send email or Email. To use this feature, you need to activate and purchase the E-mailPro plugin and need to set it to print to a printer.

3. Click on the Accounting information tab to enter and select settings and accounting terms.

4. Once finished, click on the Save button.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Creditor accounts - Accounting information tab

Accounting information tab contains settings for a specific creditor.

1. Click on the Accounting information tab.



2. Enter and/or select the following, if necessary:

   a) Account disabled - This field should not be selected (ticked) if you wish to enter and post transactions to the creditor (supplier / vendor) account. Select (tick) this field if you wish to disable the creditor (supplier / vendor) account (e.g. if you no longer do business with this creditor (supplier / vendor)). osFinancials5/TurboCASH5 will allow you to enter transactions for the creditor (supplier / vendor), but it will not allow you to post transactions to the creditor (supplier / vendor) account. However, you will still be able to view reports for the creditor (supplier / vendor).

   b) Open item account - Select (tick) this field if you wish to allocate or link payments or supplier returns (debit transactions) to a particular purchase or credit transaction. If this field is left blank, the Balance B/F (brought forward) posting method will be used, where payments made or supplier returns made are allocated against the oldest outstanding amount.

   c) Due days - Enter the number of days for the credit facility granted by the creditor (supplier / vendor).

> *This date will be used to calculate the date when payments are to be made to creditors*

(suppliers) on purchase documents (i.e. purchases or supplier returns) and via the electronic payment system in the Automatic payments batch processing option. It will also print on purchase documents (i.e. (i.e. purchases, supplier returns or orders).

d) Credit limit - Enter the credit limit granted by the creditor (supplier / vendor). When you are processing transactions, osFinancials5/TurboCASH5 will warn you if you are exceeding the credit limit for the creditor (supplier / vendor).

It will also display the Available balance (i.e. Current balance minus the Credit limit) on purchase document entry screens (i.e. purchases, supplier returns and orders).

The Calculator's buttons may also be launched from the Credit limit field.

e) Charge amount - Enter an amount as agreed upon with your creditor (supplier / vendor).

You may generate Multiple Transactions - Creditors with charge amount option in any Batch type or Journal (except the Receipts and Payments batch types). When you post this Batch, osFinancials5/TurboCASH5 will credit (increase the creditor (supplier / vendor) account) for each of the creditor (supplier / vendor) accounts with the amount specified in this field and debit a specified account (e.g. Expense account).

The Calculator's buttons may be launched from the Charge amount field.

f) Bank account type - Select *Arbitrair* or *11 Proof*. This is for electronic payments made to creditor (supplier / vendor) accounts via the electronic banking system.

11-Proof - See - http://nl.wikipedia.org/wiki/Elfproef

Arbitrair - Random - not controlled

g) Bank account no. - Enter the bank account number, if available.

h) Bank name - Enter the bank account name, if available.

i) BIC - (Bank Identifier Code). Enter, if available.

See - http://en.wikipedia.org/wiki/International_Bank_Account_Number

j) IBAN - (International Bank Account Number)

See - http://en.wikipedia.org/wiki/International_Bank_Account_Number

k) Signature - Enter, if available.

SWIFT - (Society for Worldwide Interbank Financial Telecommunication) - See - http://en.wikipedia.org/wiki/SWIFT / http://www.theswiftcodes.com/

SEPA - (Single Euro Payments Area) - See - http://en.wikipedia.org/wiki/Single_Euro_Payments_Area

l) Signature date - Enter, if available.

m) Debtor code - Enter the debtor (customer / client) code for the creditor (supplier / vendor), if available.

n) Stock file override - By default, the Stock file override settings is not activated. If necessary, select the following:

i) Use default account - By default, the "*Use default account*" option is not selected. The Purchase account, as selected on Stock items (Default ribbon), will be used when purchase documents or orders for the creditor (supplier / vendor) is updated (posted) to the ledger.

If you activate the Use default account settings, you need to select a different account on the Accounts lookup facility.

When purchases or supplier returns for the creditor (supplier / vendor) is updated (posted) to the ledger, the selected Purchase account for this Stock item will be ignored and the purchase transaction will be updated (posted) to the specified account for the creditor (supplier / vendor)).

ii) Use default tax - By default, the "*Use default tax*" option is not selected. The Input Tax account, as selected on Stock items (Default ribbon), will be used when purchases or supplier returns for the creditor (supplier / vendor) is updated (posted) to the ledger.

If you activate the Use default tax settings, you need to select a different VAT/GST/Sales Tax account or code on the Tax Lookup.

When purchases or supplier returns for the creditor (supplier / vendor) is updated (posted) to the ledger, the selected Tax account or code for this Stock item will be ignored and the Input VAT/GST/Sales Tax transaction will be updated (posted) to the specified VAT/GST/Sales Tax account or code for the creditor (supplier /

vendor).

Do not select this option, if you are not registered for VAT/GST/Sales Tax, or if multiple Tax codes (accounts) is applicable to the transactions with the creditor (supplier / vendor).

3. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Converting Word Documents to eBooks: A Step-by-Step Guide with HelpNDoc

Creditor accounts - Contacts tab

You may add, delete or enter contact persons for the creditor (supplier / vendor). A list of all contact persons linked to the selected creditor (supplier / vendor) account, you have created, edited or deleted, in the following options on the Default ribbon:

- Calendar
- Contacts



This will display the First name, Name, Address, Address 2, Address 3, Phone 1, Phone 2, Fax and E-mail address.

The options are as follows:

New - This will open a blank contactperson screen.

Edit - This will open the selected contact's details screens.

Delete - Delete a selected contact.

Search - This will initiate a similar screen as in the Contacts (Default ribbon) listing all contacts. You can then select a specific contact. You can also use the "*Auto-copy info*" option to copy the details of a selected contact.

Deleted contact persons will be removed from this list.

Created with the Standard Edition of HelpNDoc: Make Your PDFs More Secure with Encryption and Password Protection

Creditor accounts - Appointments tab

In osFinancials5/TurboCASH5, the "*Creditor accounts - Appointments*" tab allows you to view and manage appointments specifically related to a selected creditor (supplier/vendor) account. This tab provides a centralised view of all scheduled creditor appointments that have been added in the Calendar (Default ribbon).

By accessing the "*Creditor accounts - Appointments*" tab, you will be able to see a comprehensive list of all creditor appointments/events that have been scheduled in the Calendar. This includes appointments for meetings, discussions, notes, or any other relevant activities associated with your creditor account.

You may click on the column headings (i.e. Description or Notes) to change the sort sequence from the ascending to the descending sequence.

You may click on any of the column headings (i.e. Start time, End time, Description or Notes) and drag it to the left or right to change the sequence in which to display the columns.

Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

Creditor accounts - Documents tab

All purchase documents (i.e. Purchases, Supplier returns and/or Orders) which have been processed for the selected creditor (supplier / vendor) account will be listed here. These documents need not to be updated (posted) to the ledger.

To maximise the Documents tab and/or Debit / Credit transactions section of the screen, click on the *button to maximise the Documents tab. You may also click and drag any part of the screen up / or down.* 



The options are as follows:

1. Print button - This will print the selected document to the default or selected output method.

   You may also double-click on a selected document to print it.

2. Layout file - This is by default blank. The selected document will be printed using the layout file as set in Setup → Documents setup for Purchases, Supplier returns and Orders.

   You may change the layout file by selecting your own layout file from the list. These layout files are stored in the

   ...\plug_ins\reports\DOCUMENTS\DOCUMENTS directory of your system.

3. Send report to - The default option as set in the "*Output method*" field on Setup → Company info (Options) or Setup → Access control (Reports access). You any change this to any other option (i.e. Screen, Printer, File, E-mail or Fax), if required.

   You may click on the column headings (i.e. Document number, Date, Description or Reference) to change the sort sequence from the ascending to the descending sequence.

   You may also click and drag any of the column headings to the left or right to change the sequence in which the columns are to be displayed.

View Transactions - Show transact context menu

1. Select a transaction and click on the Show transactions context menu.
2. On the "*Transactions*" screen, click on the Print button.

> *The Documents tab lists all posted and unposted documents and orders. The Show transactions context menu option will not do anything, if an order or an unposted document is selected.*



The Amount Exclusive values are as follows:

- 0 = Amount Exclusive
- 1 = Amount Inclusive



Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Creditor accounts - Transactions tab

Any transactions which have been processed for that creditor (supplier / vendor) account will be listed:

- Batch (Journal) transactions which have been updated (posted) to the ledger.
- Document transactions (i.e. Purchases and Supplier returns) which have been updated (posted) to the ledger.

To maximise the Transactions tab and/or Debit / Credit transactions section of the screen, click on the  *button to maximise the Transactions tab. You may also click and drag any part of the screen up / or down.*

All selected - All transactions listed. Those transactions which are fully linked or settled, will display an 0.00 amount in the Outstanding column:



All -

By default, this option is not selected. If a creditor account is set to Open item account (Accounting information tab) only the transactions which are not linked (matched) in the Open item feature (i.e. amounts in the Outstanding column smaller or larger than 0.00), will be listed.

All - If you select this option, all the transactions which are linked (matched) in the Open item feature (i.e. amounts in the Outstanding column = 0.00), will be listed.

All not selected - This is the default option. Only those with outstanding amounts will be listed:



Before sending remittance advises to your creditors (suppliers) , it is recommended that any amounts in the debit section be linked to any outstanding invoices or credit transactions.

If the creditor (supplier / vendor) account is not set as an open item, account, all transactions will be listed.

It will list transactions as follows:

1. Debit - Documents (i.e. Supplier returns), Purchase returns journal, Payments journal, Opening Balances take-on, etc. It will list any transactions, for which amounts are entered in the Debit column of batches.
2. Credit - Documents (i.e. Purchases), Purchase journal, Generate multiple transactions (Creditors with charge amount), Opening Balances take-on, etc. It will list any transactions, for which amounts are entered in the Credit column of batches.

You may click on the column headings (i.e. Reference, Description, Date, Amount or Outstanding) to change the sort sequence from the ascending to the descending sequence.

You may also click and drag any of the column headings to the left or right to change the sequence in which the columns are to be displayed.

View Transactions - Show transactions context menu

1. Select a transaction and click on the Show transactions context menu.
2. On the "*Transactions*" screen, click on the Print button.

> *The Documents tab lists all posted and unposted documents and orders. The Show transactions context menu option will not do anything, if an order or an unposted document is selected.*



The Amount exclusive values are as follows:

- 0 = Amount exclusive
- 1 = Amount inclusive



View Transactions - Show Transactions button

T-Account viewer

1. Click on the Show transactions button.
2. Enter or select a start date and an end date, if necessary. Click on the Print button to print the transactions, if required.



You may double-click on a selected batch number to view only the transactions for the selected document. For example, if you need to view and print the transactions for Supplier return "PU000005" only, double-click on the batch number "10081"

Show contra - By default, this option is not selected. The contra accounts will not be printed in the "ledgerdetail" report when you click on the Print button.

Show contra option selected you may view the Contra accounts in the T-Account-viewer. If you click on the Export button, the contra accounts will be included in Column A of a Spreadsheet.

The Contra accounts consists of the following, separated by a comma:

"G750000 Stock control,T860020 Input VAT - Standard rate -15%"

Documents

- *Ledger account and account description set as the contra account of the batch type linked to the document type. (i.e. Contra account of the Purchase jnl linked to Purchase and Supplier return document types in Setup documents).*
- *Tax account (tax code) and description as linked to the Input tax (VAT/GST/Sales tax) on the Ledger tab of the Stock item selected on the Document lines.*

Batches

- *Ledger account and account description of the contra account selected in Batch setup generated as balancing entries; or selected in the "Account" column for Batch transactions.*
- *Tax account (tax code) and description as selected in the "Tax" column for Batch transactions and/or generated as balancing entries.*

Lookup document

You may right-click on a selected document and select "*Lookup document*" on the context menu of the "*T-Account viewer*".

The posted document will be displayed in a stand alone "*Document entry*" screen.



You will not be allowed to edit or change the posted document.

T-Account viewer - Print transactions

To print the transactions, in the "*T-Account viewer*", click on the Print button.



View a specific selected batch transaction (e.g. Supplier return "*PU000005*" (batch number "*10081)*



T-Account viewer - Export transactions

To export the transactions, in the "*T-Account viewer*", click on the Export button. This will export the transactions, as selected displayed in the T-Account viewer, as a comma separated text file as a "*Export.txt*" file. The Exported file will automatically be opened in your in your system's app (program) associated with the CSV (Comma Separated Values) file types.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

Creditor accounts - Bank accounts tab

This allows you to use references for the Bank import plugin.



Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System Parameters.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Creditor accounts - Stock items tab

This tab will list all the posted as well as unposted documents (i.e. purchase documents, supplier returns and orders) for the selected creditor (supplier / vendor) account.

To maximise the Stock items tab and/or Debit / Credit transactions section of the screen, click on the *button to maximise the Stock items tab. You may also click and drag any part of the screen up / or down.*



Date	Items	Document no.	Description	Price	Discount	Exclusive	Inclusive	Units	Description	Document type	Posted	Stock code	Description
2021/06/19	3	SR000003	Drill press	500.00	0	1,500.00	1,725.00	1	Each	Purchases	1	3DRILL	Drill press
2021/06/17	3	SR000002	Drill press	500.00	0	1,500.00	1,725.00	1	Each	Purchases	1	3DRILL	Drill press
2021/06/09	2	PU000006	Compressor	1,000.00	0	2,000.00	2,300.00	1	Each	Purchases	1	3COMP	Compressor
2021/06/26	3	PU000005	Drill press	500.00	0	1,500.00	1,725.00	1	Each	Purchases	1	3DRILL	Drill press
2021/04/05	3	PU000003	Drill press	500.00	0	1,500.00	1,725.00	1	Each	Purchases	1	3DRILL	Drill press
2021/05/30	3	OR000004	Drill press	500.00	0	1,500.00	1,725.00	1	Each	Orders	1	3DRILL	Drill press
2021/04/01	3	OR000002	Drill press	500.00	0	1,500.00	1,725.00	1	Each	Orders	-1	3DRILL	Drill press
	7				-8	-5,000.00							

You may click on the column headings (i.e. Date, Items, Document no., Description, Price, Discount, Unit Price, Exclusive amount, Inclusive amount, Unit size, Description (Unit), Document type, Posted, Stock code and Stock description) to change the sort sequence from the ascending to the descending sequence.

You may also click and drag any of the column headings to the left or right to change the sequence in which the columns are to be displayed.

Posted

W 0 – Purchase and Supplier return documents are not yet posted (updated) to the ledger.

W 0 – Orders are not yet confirmed (Converted to a Purchase Document).

W 1 – Purchase and Supplier return documents are posted (updated) to the ledger.

W 1 – Orders are confirmed (Converted to a Purchase Document).

W -1 - Orders which are still open.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Delete Creditor accounts

You may delete a creditor (supplier / vendor) account if the account has no transactions and/or balances.

You may disable a creditor (supplier / vendor) account to block (prevent) posting of any documents or batch transactions for the creditor (supplier / vendor). You may need to do this, if you are no longer doing business with the creditor (supplier / vendor), etc.

Delete accounts

To delete a Creditor (supplier / vendor) account:

1. On the Creditor (supplier / vendor) accounts, select the account.

   If you wish to delete more than one (1) creditor (supplier / vendor) account at a time, press the Ctrl key and keep it down while selecting the other creditor (supplier / vendor) accounts to delete with a mouse click.

2. Click on the Delete button. A confirmation message is displayed:

   "Are you sure you want to delete this account?"

   Make sure absolutely sure that the correct creditor (supplier / vendor) account is selected.

3. Click on the Yes button. A confirmation message is displayed:

   "Account deleted!"

4. Click on the OK button. This will permanently remove the creditor (supplier / vendor) account.

Disable accounts

To disable a Creditor (supplier / vendor) account:

1. If the creditor (supplier / vendor) account has transactions and/or balances, you cannot delete it. A similar error message is displayed:

"2AONES A-ONE Suppliers
This account has balances, cannot be deleted!"

2. Click on the OK button. To block posting of any documents or batch transactions for the creditor (supplier / vendor), click on the Edit button and Accounting information tab.



3. Select (tick) the "*Account disabled*" field.

4. Click on the Save button. You may delete a creditor (supplier / vendor) account if the account has no transactions and/or balances.

Created with the Standard Edition of HelpNDoc: How to Protect Your PDFs with Encryption and Passwords

Export / Import Creditor accounts

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Export Creditor accounts

Using this facility, you may also export certain data for the creditor (supplier / vendor) accounts in an open Set of Books to XML Database format, or any available format on your system.

All the information regarding each account as entered in the Creditors (Default ribbon) menu (includes specific data for creditor accounts), will be exported in the selected file format.

To export Creditors (supplier / vendor) accounts:

1. On the Setup ribbon, select Export.

2. Click on the Creditors button.



3. Select and/or enter the following:

   a) Export to - The installation directory in which osFinancials5/TurboCASH5 is installed, will be displayed. You may click on the Browse icon to select a folder on the "*Browse for Folder*" screen. You may then select any available folder, or drive, on your system into which you wish to export the data.

   b) File type - Select to export the file in the XML Database (*XML), Comma Separated Variable (*CSV), Lotus Spreadsheet File (*WK1), MS Excel Spreadsheet (*XLS), or any other format available on your system from the list.

> *It is recommended that the "(*.txt) Tab delimited" file type is selected to Import general ledger accounts.*
>
> *It will create the following export file types for the export file name:*
>
> **.txt - Tab delimited text file - Recommended for Import on the Setup ribbon.*
>
> **.slk - Can be opened in spreadsheets of LibreOffice, OpenOffice or UltraOffice). You may save it as a a Microsoft excel file.*
>
> **.xml - Can be opened in your system's default web browser or Notepad.*

c) Export files name - Enter the File name. You need to select this file at a later stage when you wish to import the file, or analyse the data in a spreadsheet.

d) Log file - Enter the Log file name.

e) Range - From / To - The Creditors lookup will be automatically initiated. Select any range of accounts to include in the export file.

f) Increment Export - Leave this option blank.

4. Click on the Export button to create the export file, and save it in the specified directory.

The information for the Creditors, which will be exported, is:

- *Account code.*
- *Description or name.*
- *Contact persons.*
- *Postal and Delivery addresses.*
- *Two Telephone numbers and Fax number.*
- *E-mail addresses.*
- *Credit limits.*
- *Charge amounts.*
- *Discount.*
- *Disabled account indicator.*
- *Remittance advise messages.*
- *Open item creditor indicator.*
- *Reporting groups 1 and 2.*
- *The last date a transaction was entered for the creditor accounts, will also be included into the selected export file.*

Created with the Standard Edition of HelpNDoc: Create cross-platform Qt Help files

Import Creditor accounts

This option will allow you to import data for creditor (supplier / vendor) records from a valid file format into an existing Set of Books. To be able to import the data for creditor (supplier / vendor) records, you need to have created a valid "*Tab delimited*" file on your system in Export (Setup ribbon)

To import Creditor (supplier / vendor) accounts:

1. On the Setup ribbon, select Import. The "*Import Data into osFinancials*" screen is displayed:



2. Select Debtors/Creditors as the "*Data type to import*".

3. Select the "*Tab delimited*" (recommended) option.

4. Click on the >> button to locate the data file. The following screen is displayed:



5. Click on the button to locate the data file.

Optional - You may click on the View file button to view the file in your system's default app (program) associated with th

An example of the exported Tab Delimited text file is as follows:



6. Click on the >> button. The following screen is displayed:



7. Click on the Import button. The following message is displayed:

Field SSalesPerson not found in import!

8. Click on the OK button. The "*ImportCheck*" screen is displayed:



9. You may use the record buttons to add, delete or change the creditor (supplier / vendor) accounts records on the "*ImportCheck*" screen. You may then click on the All or OK buttons to import the creditor (supplier / vendor) accounts.

10. Once the import process is finished an information message is displayed:

"Data file import completed!"

11. Click on the OK button.

12. Go to the Reports ribbon and select Reports → Creditors → Listing menu to check that the creditor (supplier / vendor) accounts are correct.

13. If you need to edit the creditor (supplier / vendor) accounts, go to the Default ribbon and select Creditors.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Export Creditor accounts - Open text file in spreadsheet

To illustrate the exported fields and data, the exported text file (created on the Export option of the Setup ribbon) is opened in a spreadsheet.

If the exported text file does not open in Microsoft Excel; or if you do not have Microsoft Excel installed on your system, you may open the file with OpenOffice, LibreOffice, Ultra Office, etc.

On your spreadsheet application, open the creditor (supplier / vendor) accounts saved text (*.txt) file and

confirm your tab delimited settings on the "*Text Import*" screen.



This will open your exported text file of the selected creditor (supplier / vendor) accounts in a spreadsheet.

An example of the exported file opened in "*LibreOffice Calc*" spreadsheet, is as follows:



The exported data will be exported in forty-five (45) columns:

Column	*Column heading*	*Source / fields*	*Field location (main form / tab)*	
A	*SACCOUNTCODE*	*Creditor code*	*Main form*	*String (6)*
B	*SDescription*	*Name (Account description)*	*Main form*	*String (35)*
C	*SContactName*	*Contactperson*	*Main form*	*String (35)*
D	*SPostCountry*	*Postal address country*	*Main form*	*String (35)*
E	*SDelCountry*	*Delivery address country*	*Delivery address tab*	*String (64)*
F	*SPOSTAL1*	*Address*	*Main form*	*String (30)*
G	*SPOSTAL2*	*Address 2*	*Main form*	*String (30)*
H	*SPOSTAL3*	*Address 3*	*Main form*	*String (30)*
I	*SPOSTALCODE*	*Postal code*	*Main form*	*String (8)*
J	*SDELIVERY1*	*Delivery address*	*Delivery address tab*	*String (30)*
K	*SDELIVERY2*	*Address 2*	*Delivery address tab*	*String (30)*
L	*SDELIVERY3*	*Address 3*	*Delivery address tab*	*String (30)*
M	*STELEPHONE1*	*Telephone 1*	*Main form*	*String (20)*
N	*STELEPHONE2*	*Telephone 2*	*Main form*	*String (20)*

O	SEMAIL	E-Mail	Main form	String (50)
P	SFAX	Fax	Main form	String (20)
Q	FCREDITLIMIT	Credit limit	Accounting information tab	Float(numeric)
R	FCHARGEAMOUNT	Charge amount	Accounting information tab	Float(numeric)
S	FDISCOUNT	Discount	Accounting information tab (only applicable to debtor (customer / client) accounts.	Float(numeric)
T	SDeliveryCode	Delivery code	Delivery address tab	String (8)
U	FInterest	Interest	Accounting information tab (only applicable to debtor (customer / client) accounts.	Float(numeric)
V	SCREDITCARDNUMBER	Credit card number		String (35)
W	SCREDITCARDTYPE	Credit card type		
X	SCREDITCARDHOLDER	Credit card holder		String (20)
Y	BOPENITEM	Open item	Accounting information tab	B=CheckBox 1 = Open item account (True - checked) 0 = Not an Open item account (False - not checked)
Z	BINACTIVE	Inactive	Accounting information tab	B=CheckBox 1 = Account disabled (inactive) - (True - checked) 0 = Account enabled (active) - (False - not checked)

AA	*SMESSAGE*	*Message*	*Delivery address tab (only applicable to debtor (customer / client) accounts.*	*String (50)*
AB	*WDEFAULTPRICETYPEID*	*Default selling price*	*Accounting information tab (only applicable to debtor (customer / client) accounts.*	*Integer*
AC	*DLASTACTIVITY*	*Last invoice*		*Date*
AD	*SREFERENCE*	*Tax reference*	*Main form*	*String (20)*
AE	*SBANKNAME*	*Bank name*	*Accounting information tab*	*String (20)*
AF	*SBRANCHCODE*	*Bank account type*	*Accounting information tab*	*String (10)*
AG	*SBANKACCOUNTNUMBER*	*Bank account no.*	*Accounting information tab*	*String (45)*
AH	*SBANKACCOUNTNAME*	*Bank account name*	*Accounting information tab*	*String (30)*
AI	*WDUEDAYS*	*Due days*	*Accounting information tab*	*Integer*
AJ	*SCOMPANYREGNO*	*Company reg. no.*	*Main form*	*String (35)*
AK	*SFREEFIELD1*	*Statement message 1*	*Delivery address tab*	*String (35)*
AL	*SFREEFIELD2*	*Statement message 2*	*Delivery address tab*	*String (35)*
AM	*SFREEFIELD3*	*Statement message 3*	*Delivery address tab*	*String (35)*
AN	*SGroup1*	*Creditor group 1*	*Main form*	*String (30)*
AO	*SGroup2*	*Creditor group 2*	*Main form*	*String (30)*

AP	*SCurrency*	*Currency*		*String (35)*
AQ	*SForeExAccount*			
AR	*SDEFAULTACCOUNT*	*Use default account*	*Accounting information tab*	
AS	*SDEFAULTTAX*	*Use default tax*	*Accounting information tab*	

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Export Creditor accounts - Export grid

The Export button of the sidebar of the "*Creditor accounts*" list screen, will create a text file (tab delimited), which will open in your system's default Microsoft Excel (if installed on your system).

Export options

To export creditor (supplier / vendor) accounts:

On Creditors (Default ribbon).

Select the Filter and search options in the Filter column and click on the Filter button to include only those filter criteria to be included in the Export file.

By default, the export file will include all the creditor (supplier / vendor) (excluding disabled accounts).

To include disabled creditor (supplier / vendor) accounts in the export file, you need to select the "Show disabled" option, and click on the Filter button.

Click on the Export button.



The "*Save As*" screen is displayed:



Enter a name to save the file.

"Save as type :" options will be empty. A text (.txt) file type will automatically be created with your file name.*

If you do not enter a unique name in the selected folder, and save the export.txt file name, you may replace existing (previously exported) files.

If an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "F:\exports\your-file-name.txt". The process cannot access the file because it is being used by another process.

Click on the Save button.

Example : Exported text file - Microsoft Excel

In this example, the exported file is automatically opened in "*Microsoft Excel*":



	Name	Creditor code	Address	Address 2	Address 3	Postal code	Telephone 1	Telephone 2	Fax	E-mail	Bank accour	Bank accc	Last invoi	Reference	Due days
2	Opening balances - Creditor	2COPEN									Arbitrair				30
3	SUNDRY SUPPLIERS	2SUNSU									Arbitrair				30
4	A-ONE Suppliers	2AONES	P O Box 3	Marshallto	Johannesburg	2000	(011) 838-922	(011) 838-922	(011) 83	aones@h	Arbitrair			906012345	30
5	BEST Suppliers	2BESTS	P O Box 4	Halfway House		1685	(011) 310-3110		(011) 31	best@his	Arbitrair			1234567892	30
6	ABC-Office-Supplies	2ABCOS	PO Box 8	Lakeview	Johannesburg	2012	(011)312-9997	(011)312-999	(011)31	abcoff@h	Arbitrair			4444444444	30
7	ABC-Service-Centre	2ABCSC	PO Box 9	Lakeside	Johannesburg	2122	(011)313-9997	(011)313-999	(011)31	abc@hisr	Arbitrair			3333333333	30

Only those accounts matching your filter and search criteria in the Filter column options, will be included in the export file.

For example, if the postal code (zip code), is specified, only those accounts for the specific postal code will be included in the export file.

All the columns will be exported in the default sequence.



Example : Exported text file - Notepad

An example, of the exported text file file opened in your systems default program associated with *.txt files (e.g. "*Notepad*") is as follows:

```
Name   Creditor code Address      Address 2    Address 3    Postal code  Telephone 1  Telephone 2  Fax    E-mail Bank account type
       Bank account no.    Last invoice  Reference    Due days     AccountID    Contactperson Creditor group 1    Creditor group 1
Sort   Creditor group 2    Creditor group 2 Sort      Delivery address Address   Delivery address Address 2 Delivery address Address
3      Delivery address Postal code      Delivery address Country   Delivery address    First name
Opening balances - Creditor 2COPEN                                                Arbitrair
       30     49           Creditor group 1A                26     Unallocated                        40

SUNDRY SUPPLIERS     2SUNSU                                                       Arbitrair
       30     51           Creditor group 1A                26     Unallocated                        40

A-ONE Suppliers      2AONES P O Box 31318 Marshalltown  Johannesburg  2000   (011) 838-9221      (011) 838-9222      (011) 838-9223
       aones@hismail.com    Arbitrair                                906012345           30     29     Austin Creditor group 1B
       27     Unallocated                      40     Austin Street Marshalltown  Johannesburg  2001   South Africa  South Africa  Andy
BEST Suppliers       2BESTS P O Box 45532 Halfway House       1685   (011) 310-3110            (011) 310-3111      best@hismail.com
       Arbitrair                                1234567892          30     30     Best   Creditor group 1B                27
       Unallocated                      40     Best Street   Halfway House       1686   South Africa  South Africa  Ben
ABC-Office-Supplies  2ABCOS PO Box 8888   Lakeview      Johannesburg  2012   (011)312-9997 (011)312-9998 (011)312-9999
       abcoff@hismail.com   Arbitrair                                4444444444    30     53     Penny  Creditor group 1C
       41     Unallocated                      40     Lake Street 444      Lakeview      Johannesburg  2013                Walters
ABC-Service-Centre   2ABCSC PO Box 9999   Lakeside      Johannesburg  2122   (011)313-9997 (011)313-9998 (011)313-9999 abc@hismail.com
       Arbitrair                                3333333333    30     55     Brown  Creditor group 1C                41     Unallocated
       40     Metro Building       Lake Street   Lakeside      2123                Xavier
```

Example : Exported text file - LibreOffice Calc

If the exported text file does not open in Microsoft Excel; or if you do not have Microsoft Excel installed on

your system, you may open the file with OpenOffice, LibreOffice, Ultra Office, etc.

Locate the exported text file in your System's File Explorer.

In this example, Open with > LibreOffice Calc is selected. The "*Text Import*" screen is selected.



If LibreOffice and not LibreOffice Calc is selected, the exported text file will open in LibreOffice Writer as a text file.



Separator options - Separated by

Tab is the only option which should be selected for this exported text file. This may differ for some other report types.



Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Spreadsheet Export / Import - Debtor / Creditor accounts

osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet export and import feature.

- Spreadsheet export - You may export debtor (customer / client) accounts and creditor (supplier / vendor) accounts and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import debtor (customer / client) accounts and creditor (supplier / vendor) accounts from a saved "*Excel Workbook (*.xlsx) file type.*

This feature may be used to import debtor (customer / client) accounts and creditor (supplier / vendor) accounts into:

- Into the same Set of Books.
- Into a different Set of Books.
  - Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types
  - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

> *Before you may import debtor (customer / client) accounts and creditor (supplier / vendor) accounts in a new Set of Books, you need to do the necessary setup and configuration.*
>
> *Once this is done, you may start to import debtor (customer / client) accounts and creditor (supplier / vendor) accounts from a saved "Excel Workbook (*.xlsx) file type.*

After import

To check the imported account details, you may print the necessary listing reports for debtor (customer / client) accounts and listing reports for creditor (supplier / vendor) accounts from the Set of Books in which you created the export file.

You may go to Debtors (Default ribbon) to view and/or edit the imported debtor (customer / client) accounts.

You may go to Creditors (Default ribbon) to view and/or edit the imported creditor (supplier / vendor) accounts.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Contacts

The Contacts feature in osFinancials5/TurboCASH5 refer to individuals or entities associated with debtor (customer/client) and creditor (supplier/vendor) accounts. The Contacts feature allows you to maintain a list and details of contacts linked to these accounts for easy reference and communication.

Contacts play a crucial role in processing sales and purchase documents within osFinancials5/TurboCASH5. They help specify the relevant contact person or entity associated with a particular transaction. Here's how contacts are utilised in the process:

1. Sales documents: When creating sales documents such as quotes, invoices, and credit notes, the default contact linked to the debtor (customer/client) account will be automatically selected. This ensures that the appropriate contact is associated with the transaction. The contact specified in the sales document represents the person responsible for the transaction or serves as the primary point of contact for the customer.
2. Purchase documents: Similarly, when generating purchase documents like orders, purchases and supplier returns, the default contact linked to the creditor (supplier/vendor) account will be automatically selected. This ensures that the relevant contact information is associated with the transaction. The contact specified in the purchase document represents the person responsible for the transaction or serves as the primary point of contact for the supplier.

By assigning the correct contacts to the respective accounts, osFinancials5/TurboCASH5 ensures that the appropriate contact information is readily available when processing sales and purchase transactions. This helps maintain accurate and effective communication with customers, clients, suppliers, and vendors

throughout the transactional process.

Contacts will also be printed on document layout files for sales documents such as quotes, invoices, and credit notes as well as purchase documents such as orders, purchases and supplier returns providing additional information for the recipient or reference.

Including contact information on document layout files for sales and purchase documents is a valuable feature in osFinancials5/TurboCASH5. By printing contacts on these documents, you provide additional information for the recipient or reference, enhancing the clarity and professionalism of the transaction. This ensures that the necessary contact details, such as the name, phone number, email address, or any other relevant information, are readily available for easy communication or reference purposes. It allows recipients to quickly reach out to the relevant contact person or entity in case of any queries, clarifications, or further discussions related to the transaction.

In osFinancials5/TurboCASH5, the Contacts: feature will list all the contacts, where you can manage and maintain contact information for debtors (customers/clients) and creditors (suppliers/vendors). You may add new contacts, update contact details, delete contacts and print a list of all the contacts in your Set of Books.

Additionally, you may maintain and manage contacts on the following options on the Default ribbon.

1. Debtors - Contacts tab: This tab specifically focuses on managing contacts associated with debtor accounts. You can add, edit, or delete contacts linked to debtor accounts, ensuring that the contact details are up to date.
2. Creditors - Contacts tab: Similar to the Debtors - Contacts tab, this tab is dedicated to managing contacts associated with creditor accounts. You can modify the contact information for your suppliers/vendors to maintain accurate records.
3. Calendar - Contacts feature: provides the ability to manage contacts, ensuring that any changes made to contact information are reflected across the system. The following options on the Default ribbon allow you to create, edit, or delete contacts, with all updates being synchronized with the Contacts in the Calendar.

By utilising these options, you can conveniently manage contacts within osFinancials5/TurboCASH5, ensuring that all contact information remains consistent and accessible across different sections in a Set of Books.

To create / add / edit / delete / print contacts:

1. On the Default ribbon, select Contacts.



Click the Print button to print a list of all Contacts. This report may also be printed in Reports → Contacts (Reports ribbon). This report will list all contacts for debtors (customers/clients) as well as contacts for creditors (suppliers/vendors). It offers a consolidated view of all contacts in your Set of Books.

To list only the contacts for debtor (customer / client) accounts, you need to print it in Reports → Debtors → Listing - Contacts menu (Reports ribbon). This report specifically focuses on contacts related to debtors (customers/clients). It provides a listing of contacts associated with your debtor accounts.

To list only the contacts for creditor (supplier / vendor) accounts, you need to print it in Reports → Creditors → Listing - Contacts menu (Reports ribbon). This report specifically lists contacts related to creditors (suppliers/vendors). It presents a comprehensive view of contacts associated with your creditor accounts.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Stock (Inventory / Products)

The Stock items / Inventory items / products) in osFinancials5/TurboCASH5 features a comprehensive inventory system designed to manage and track stock items, inventory items or products. It supports an unlimited number of stock items and allows for detailed item-specific information. The inventory system also offers up to two reporting groups, enabling efficient data organisation and analysis.

With eleven different stock item types available, osFinancials5/TurboCASH5 provides flexibility in managing

various types of products. When processing documents for debtors or creditors, or generating reports, the stock item lookup function helps in selecting the appropriate products. The system utilizes the chosen stock item's details to calculate selling and cost prices based on specified quantities, ensuring accurate pricing information on documents and reports.

In addition to the Financial entry stock item type, which allows for processing both sales and purchase documents by selecting ledger accounts, you can choose from various other stock item types when working with sales documents (such as Quotes, Invoices and Credit notes). These options include "Default, Sales, Sales (No stock), Option item, Option item (No stock), BOM (Bill of Materials), BOM (Bill of Materials) - Production" or "Linked item" stock item types.

Similarly, when processing purchase documents (like Orders, Purchases, and Supplier returns), you have the flexibility to select from stock item types, including " Default, Purchases, Purchases (No stock), Option item, Option item (No stock), BOM (Bill of Materials), BOM (Bill of Materials) - Production" or "Linked item" stock item types.

The Stock items feature in osFinancials5/TurboCASH5 allows for easy management of inventory items or products. You can create, edit, delete, or disable items as needed, and the feature provides filtering and search options for efficient item location. Within each item, you can make changes to important details such as stock code, description, quantities, reorder levels, and more.

Additionally, the inventory system offers various settings on the Ledger tab and allows for managing activities on the Document groups, Transactions, Image, Multi-group, and Backorders tabs. This comprehensive set of features ensures efficient inventory tracking, accurate pricing, and streamlined document and report generation, making osFinancials5/TurboCASH5 a reliable solution for managing and optimizing your inventory management processes.

Overall, osFinancials5's inventory system offers a comprehensive solution for managing and tracking stock items (inventory items) or products, allowing for efficient inventory tracking, accurate cost and selling price calculation, and streamlined document and report generation.

Serials-Batches-Location plugin : Licence :- Manual - Shop - Licence : Once-off - Added the Serials and Batches to document layout files and 2 reports (i.e. On hand and Stock movement report).

The "Serials-Batches-Location" plugin in osFinancials5/TurboCASH5 appears to be a tool designed to manage and track inventory, specifically serial numbers, batches, and locations.

Features:

1. *Serial : Allows for tracking individual serial numbers, suitable for items like phones or computers. You can track manufacturing dates or production dates and sell by dates or expiry dates.*
2. *Batch/Location : Enter batch numbers and quantities and have the possibility to move between locations. You can track manufacturing dates or production dates and sell by dates or expiry dates.*

3. *Location : Just location management. Focuses on managing item locations in your shop, store, or warehouse. You can add locations (e.g., bin, aisle number, row) where you store stock items if needed.*

To access Stock items:

1. On the Default ribbon, select Stock items (F12).



2. Buttons – The following buttons are available:

   a) New – Create a new stock item.

   b) Delete – Delete remove a selected stock item.

   c) Edit – Edit / change a selected stock item.

> *You may also double click on a selected stock item.*

   d) Save – Save any changes to a stock item.

   e) Cancel – Cancel will revert to the previous values. Any changes will not be saved.

   f) Copy from item – This will create an exact copy of a selected stock item. You only need to enter the Stock code and change / edit the necessary fields.

> *You may also select the stock item type. The fields that are not applicable to a selected stock item type, will be disabled / enabled.*

   g) Default / Advanced mode – This will display the Export / Import, Adjust stock and Settings

tabs. Clicking on the Default button, the button's caption will change to display Advanced mode. This will hide the Export / Import, Adjust stock and Settings tabs. In the Advanced mode, you may enter / edit data (values) of stock items (like you would in a spreadsheet).

3. Limit rows - The default is "*200*" records to be listed displayed on this screen. If necessary, you may change that.

4. Reports – Prints the selected report type for the selected stock item(s) only. If you need to include all items, click on the Report button.

> *These barcodes or the Yagoda barcodes may also be printed from the Reports → Stock → Print labels (Reports ribbon).*

> *These reports are designed using the Reportman. These reports are located in the "... \plug_ins\reports\REPORTS\STOCK" directory.*

> *There are two (2) options to print these reports, i.e.:*
>
> - *Click on the Report button – to include all stock items in the reports.*
> - *Right-click on a selected item, and select Print single item option from the context menu.*

5. Use barcode printer – Select this option if you have a barcode printer configured and setup on your system; and you need to print the Barcodes (i.e. Barcode or Yagoda barcode) report type from the list.

6. Single line mode - This option has three (3) basic settings:

   a) If this field is selected (ticked) and the Advanced mode (Export / Import, Adjust stock and Settings tabs displayed), each stock item record will be listed in a single row.

   b) If this field is not selected (not ticked) and the Advanced mode (Export / Import, Adjust stock and Settings tabs displayed), a fixed right pane column (similar to the left pane on which the stock code and date last action columns are by default displayed) will be added. You may drag any column between the left and right panes to be added.

   c) If this field is selected (ticked) and the Default mode (Export / Import, Adjust stock and Settings tabs not displayed), each stock item record will be listed in a single row.

   d) If this field is not selected (not ticked) and the Advanced mode (Export / Import, Adjust stock and Settings tabs displayed), the fields for stock item records will be grouped in some columns (e.g. Units, Stock group1 / 2, Stock item type, Cost centres, etc.).

7. Update type - The following options are available to change (group) the columns:



8. Search filter / options – Filter by entering the Item Code, Description or Extra description and/or by selecting (ticking) the Reporting group 1 / 2. If you click on the Search button, the only those stock items that matches your search / filter criteria will be listed. If you click on the Type button, you may select Item Code, Description, Extra description, Reporting group 1, Reporting group 2 or Creditor.



If the "Creditor" option is selected in the "Type" field, you may select the Creditor account on the Lookup. This will list those stock items which are linked to the creditor (supplier / vendor) account in the "Preferred supplier 1" (Default Supplier 1) field of a Stock item.

9. Context menu – The following options are available:

   - Print single item – Prints the selected report type for the selected stock item(s) only. If you need to include all items, click on the Report button.
   - Copy – The following options to process Supplier 1 and Purchase Sales Stock Tax are available:
     - Copy from / init and Paste to / perform on selected rows:



§ Stock item - Similar than the Copy from item button. – This will create an exact copy of a selected stock item. You only need to enter the Stock code and change / edit the necessary fields.

- Reporting group 1 - Change the reporting group of a stock item, if Reporting group 1 was set for Stock items (as added in Setup → Groups - Stock group 1 on the Setup ribbon).

> *The colours of the rows (list of stock items) will be changed, if set in Reporting group 1.*

- Reporting group 2 – Change the reporting group of a document, if Reporting group 2 was set for Stock items (as added in Setup → Groups - Stock group 2 on the Setup ribbon).
- Mass check - This option will run a check on all stock items. The stock item form will be automatically opened and closed for each stock item.

10. Grid totals - This will display the line count (number of records in rows / stock items) that is available on the list. The number of records will indicate the number of records that matches your filter / search criteria.

Created with the Standard Edition of HelpNDoc: Effortlessly Publish Your Word Document as an eBook

Planning stock codes

Stock items are essential for managing goods, services, and products. They are used when processing sales documents such as invoices, credit notes and quotes as well as purchase documents such as purchases, supplier returns and orders.

Planning the structure of stock codes is important for efficient stock control. A well-organised structure based on the layout of stores and business needs will simplify the management of stock items.

Careful planning of stock codes can simplify the processing of documents, such as selecting stock items for stock lookups, and for point-of-sale invoices by selecting stock items on the POS lookup. Additionally, having a structured stock code system can aid in organizing and generating reports, such as sales analysis and purchase analysis reports, when the stock code sequence is selected.

In osFinancials5/TurboCASH5, there are several options available to optimize the control and management of stock items; i.e.:

- Stock item type – You may create up to eleven (11) stock types, with "*Default*" being the standard type used for trading stock.
- Stock code – Use up to 15 alpha-numerical characters. You may also change the Stock code when you edit existing Stock items.
- Reporting groups - You may set up to two (2) reporting groups for your stock items (products). Stock groups allows you to group or categorise the stock items (products) on which you would like to report. These stock groups can be linked to each stock item (product) for better reporting, analysing and managing of your inventory (products).
- Sub-accounts - Sub-accounts can also be created for sales, cost of sales, and stock control accounts and linked to each stock item.

> *Stock can be categorised into different groups by using a prefix in the stock code. This allows for the sales, cost of sales, and stock control accounts to be divided into sub-accounts for each category of stock. Each stock item can then be associated with the appropriate sub-account for its specific category.*
>
> *In addition, each stock item can be linked to different tax types to account for varying VAT/GST/Sales Tax rates.*

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Stock item types

---

osFinancials5/TurboCASH5 provides for eleven different stock item types, each with its own set of required data and settings to be entered or selected when creating a new stock item. The type of stock item you select when creating it will determine what data needs to be entered or selected.

For example, the Purchase (no stock) stock item type requires the selection of a default Input Tax account and a Purchase account, but does not allow for the selection of the Output Tax and Sales account.

Additionally, this type of stock item will not appear on the Item lookup when processing sales documents such as invoices, point-of-sale invoices, credit notes, and quotes.

For example, if you select the Purchases (no stock) stock item type, it will allow you to set the default Input Tax account and a Purchase account. It will not allow you to select the Output Tax and Sales account. When processing sales documents, (i.e. Invoices, Point-of-Sale Invoices, Credit notes and Quotes), the Purchases (no stock) type stock items will not be listed on the Item lookup.

The eleven (11) stock item types are:

1. Default – Used for trading stock and requires the selection of the Sales, Cost of sales, and Stock control accounts. It can also be linked to the Input and Output Tax accounts. In this documentation, two (2) trading stock items, namely a Compressor and a Drill Press, is used as examples.
2. Sales – Used for non-trading stock and requires the selection of a Sales account only. It can only be linked to the Output Tax account.
3. Sales (no stock) – Used for non-trading stock and requires the selection of a Sales account only. It can only be linked to the Output Tax account.
4. Purchases – Used for non-trading stock and requires the selection of the Cost of sales and the Stock control or Purchase account. It can only be linked to the Input Tax account, and no selling prices can be entered.
5. Purchases (no stock) – Used for non-trading stock and requires the selection of the Cost of sales and the Stock control or Purchase account. It can only be linked to the Input Tax account, and no selling prices can be entered.
6. Financial entry – Cannot select the Sales, Cost of sales and Stock control accounts. Once you select this stock item type when processing documents, the Accounts lookup will be displayed. You may then select any general ledger account on the Accounts lookup. You need to select the Input as well as Output Tax accounts for this stock item type. Selling prices can also be entered.
7. Option item – Used for items with options such as colour and size. The available options are defined in the Setup options on Stock information (Setup ribbon) and linked to the Options stock item type (Stock items - Options tab on the Default ribbon). When processing documents, the available options list will be launched from which you can specify quantities and select the options.
8. Option item (no stock) – Similar to the Option item with stock, but does not allow every entry to have a sales price, cost price, quantity, and minimum stock level. This will also be used in generating purchases on supplier 1. The Setup options on Stock information (Setup ribbon) need to be defined.
9. BOM – Bills of Materials – Allows the addition of other stock items or products consisting of various other stock items (components) and/or services, etc. to the BOM list. The BOM stock item is the

finished product. For trading stock, the cost of sales and stock control accounts are controlled via the default stock items linked to the BOM item. An example would be the components of a computer system which are used to make the complete system, which is then sold as a finished product.

10. BOM (Production) – Similar to the BOM stock item type, with a feature that allows for the assembly (specify the quantities) of finished items or disassemble a specified quantity of finished items.
11. Linked Sale - To be advised.

Each stock item type serves a unique function, ensuring precise data entry and configuration to meet specific business needs. Choose the appropriate type based on the nature of the product or service to streamline inventory management and financial tracking in osFinancials5/TurboCASH5.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Stock groups

In osFinancials5/TurboCASH5, you have the option to set up to two (2) reporting groups for your stock items or inventory items, allowing you to categorise and report on your products more effectively. These reporting groups provide a way to organize and analyse your inventory based on specific criteria.

These Stock groups can be linked to each stock item (inventory item / product).

- *You may use the context menu option on the stock grid to set or change the reporting groups for Stock group 1 and/or Stock group 2 for selected stock item(s).*
- *You may use the stock grid to filter, search or group stock items.*
- *You may print Stock reports and Print barcodes for all or only for stock items linked to a selected Stock group or groups.*
- *You may print Sales analysis reports for Stock group 1 or Stock group 2.*

Examples of reporting groups for stock items / inventory items / products

Here are some examples of reporting groups that you can use for stock items:

1. Product category: You can create reporting groups based on the category or type of products you offer. For instance, if you sell electronics, you might have reporting groups like *"Computers," "Mobile*

Devices," "Audio Equipment," etc.

2. Brand or Manufacturer: Another option is to create reporting groups based on the brand or manufacturer of your products. This can be useful for tracking sales and performance by brand. For example, you could have reporting groups like *"Samsung," "Apple," "Sony,"* etc.

3. Product line: If you offer multiple product lines, you can create reporting groups to differentiate them. For instance, if you sell clothing, you might have reporting groups like "*Men's Apparel," "Women's Apparel," "Children's Apparel*," etc.

4. Location: Reporting groups based on the location of your products can be helpful for inventory management and sales analysis. This is particularly useful if you have multiple warehouses or stores. Examples of reporting groups could be *"Warehouse A," "Store Branch 1," "Online Store,"* etc.

5. Sales channel: If you sell your products through various channels, you can set up reporting groups to track sales performance across those channels. This could include groups like *"Retail Stores," "E-commerce," "Wholesale,"* etc.

These are just a few examples, and you can customise the reporting groups in osFinancials to fit your specific business needs. By assigning stock items to the appropriate reporting groups, you can generate reports that provide insights into your inventory, sales, and performance based on the defined categorisation.

Define groups for stock items / inventory items / products

To set reporting groups for stock items:

1. On the Setup ribbon, select Setup → Groups. The "*Groups* (*Account group 1)"* default screen will be displayed.

2. Click on the Stock group 1 button.



3. If you wish to rename the Reporting group name - Stock group 1, over-type the description with your new description. This will change the description of the button for Stock group 1.

4. To add a new Group to the root directory or list, select the "*REPORTING GROUP ROOT*" on the list and click on the New button.

5. Enter the name of your Stock group 1 and click on "*REPORTING GROUP ROOT*" on the list.

6. Repeat the process until you have entered all the Stock groups, etc.

> *Adding sub groups for stock items:*
>
> *Select a Stock group, for example; "Power tools" and click on the New button. Enter the name of your sub group.*

7. If you need to add Reporting group 2 for Stock, click on the Stock group 2 button and repeat the process as for Stock group 1.

8. Click on the OK button to save your changes and close (exit) this screen.

> *Changing the sequence of groups for stock items:*
>
> *Select a Stock group, for example; "Power tools" and click on the Move up or Move down button. This will list the stock group according to your preferred sequence.*

> *You may click on the Print button to print a list of your stock groups.*

You may set colours to display on the Stock item list screen. To do this, click on theBack colour button to set the rows background colour and the Font colour button to set the Font colour.

To retain and save the selected colors, you also need to set both the "Back color" and the "Font color".

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Stock information

You should use this option if you need to create sales documents such as quotes, invoices, and credit notes, as well as purchase documents such as purchases, supplier returns, and orders.

The "*Stock information*" screen is divided into three tabs: Default, Units, and Tax classes.

The Default tab has three groups: Selling price descriptions, Cost of sales, and Documents setup.

1. Selling price descriptions group allows you to change the name for up to three (3) selling prices and select the default selling price for stock items.
2. Cost of sales group lets you activate cost of sales and select the method such as average cost or latest cost and the batch (journal) to which the cost of sales will be posted.
3. Documents setup group allows you to configure settings related to document processing and stock items.

To set the Stock information and Cost of sales parameters:

1. On the Setup ribbon, select Setup → Stock information.



2. Selling price descriptions –

    a) Selling price descriptions – The Default (Selling price 1, Selling price 2, Selling price 3) is displayed. You may over-type these with your own.

    b) Default – The default selling price as the global setting. You may select any of the 3 Selling prices.

> *You may set a different selling price for specific debtor (customer / client) accounts on the Accounting information tab - Debtors (Default ribbon).*

3. Cost of sales settings – This is applicable to the "*Default*" (trading stock) and some other stock item types only. Select the following:

    a) Create cost of sales – To activate cost of sales, select (tick) the "*Create cost of sales*" tick box.

b) Cost of sales batch – Select the Cost of sales batch (journal) in which the cost of sales transactions will be posted.

c) Use "*Average cost*" or "*Latest cost*" option.

> *The method you use to calculate the value of your stock is crucial for determining its impact on your profit and loss figures. It is important to consider whether to use the "average cost" or the"latest cost" method.*
>
> *If you are unsure which method to use, it is recommended that you seek guidance from your accountant.*

4. Production contra account - If you use Bill of Materials (BOM Production) stock item type, you need to select a contra account.

5. Documents setup – The rest of the options (tick boxes) are used to set and configure document processing. Select (tick) these options; if necessary.

> *The Options setup button only need to be used to create options for the Option item and Option item (no stock) stock types.*

6. Click on the Units tab - to add or edit the unit descriptions for stock items. These are selected when you create or edit stock items and will display on reports and layout files.

   a) Add – Enter these and click on the Add button.

   b) Delete - Select a description from the list and click on the Delete button.

7. Click on the Tax classes tab to set the default Tax accounts and ledger accounts. You may then select a Tax class when you create or edit stock items.

8. Click on the OK button to save your changes and close or exit this screen.

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Units

What is units relating to stock items / inventory items and products?

In the context of stock items or inventory items, "units" refers to the quantity or measurement used to quantify and track the physical count of those items. It represents the individual items or the smallest discrete units in which the stock is measured, purchased, and sold.

The term "*units*" can vary depending on the nature of the stock items or products. It could refer to items like pieces, boxes, cartons, bottles, kilograms, litres, meters, or any other appropriate unit of measurement based on the characteristics of the items being tracked. The choice of units depends on the specific industry, product type, and standard practices within that particular business or market.

For example, in a retail store, units could represent individual items such as a single shirt, a pack of batteries, or a case of soft drinks. In a manufacturing setting, units might refer to components or sub-assemblies used in the production process. The choice of units allows for accurate inventory management, pricing, and tracking of stock levels.

Examples of Units

What is common examples of Units for stock items in which stock items are purchased and sold?

Common examples of units or unit sizes for stock items in which stock items are purchased and sold can include:

1. Pieces or Units: This is the most basic unit of measurement and refers to individual items or products.
2. Boxes or Cartons: Stock items may be packaged in boxes or cartons containing a specific quantity of units.
3. Pallets: In the case of bulk products or larger items, stock items may be measured and sold by the pallet.
4. Gallons or Litres: For liquids or fluids, units of measurement can include gallons or litres.
5. Pounds or Kilograms: Weight-based units such as pounds or kilograms are commonly used for items sold by weight.
6. Yards or Meters: Length-based units like yards or meters are relevant for products sold by length or size.
7. Cases: Some items are sold in cases, which typically contain a predetermined number of units.

These are just a few examples, and the units or unit sizes used for stock items can vary depending on the nature of the products and the industry in which they are being bought and sold.

What is common examples of Units for non-physical items in which stock items are purchased and sold?

When it comes to non-physical items or intangible goods that are purchased and sold, there are various units or unit sizes that can be used to measure them. Here are some common examples:

1. Licenses: Units of measurement for software licenses or intellectual property rights can include "User Licenses," "Seat Licenses," "Site Licenses," or "Enterprise Licenses." These units represent the number of users or locations covered by the license.
2. Subscriptions: For subscription-based services or digital content, units such as "Monthly Subscriptions," "Annual Subscriptions," or "Tiered Subscriptions" are often used. These units indicate the duration or level of access to the service or content.
3. Data Usage: In the telecommunications or internet service provider industry, units like "Data Volume" or "Data Units" are used to measure the amount of data consumed or allocated.
4. Consulting Services: Units can be used to measure consulting services, such as "Consulting Hours," "Consulting Sessions," or "Project Engagements." These units represent the time or sessions dedicated to providing consulting expertise.
5. Digital Downloads: For digital products like e-books, music tracks, or video files, units such as "Downloads," "Songs," or "Video Views" can be used to quantify the number of times the item is accessed or downloaded.
6. Virtual Currency: In virtual economies or online gaming, units like "*Virtual Coins," "Points*," or "*Credits*" are used to represent the currency used within the system.

These examples illustrate how units or unit sizes can be applied to non-physical items to facilitate their purchase and sale, taking into account the specific nature and characteristics of each product or service.

Labour - Is hours also used as a unit of measurement?

Hours can be used as a unit of measurement or unit size when it comes to labour. In certain industries or businesses where labour is billed or tracked based on time, hours can be used to quantify the amount of work or effort put into a particular task or project. For example, in consulting firms, freelance work, or service-based businesses, the unit of measurement for labour may be hours. It allows for accurate tracking, billing, and estimation of labour costs and efforts.

Each and Hours is that also used for products?

Units such as "*Each*" and "*Hours*" are typically not used as units of measurement for physical products themselves, but they can be associated with certain aspects related to the products.

- "*Each*" is often used as a generic unit when the quantity or unit of measurement is not specified or when dealing with individual items. For example, when selling miscellaneous or unique items where each item is different, the unit may be labelled as "*Each*" to indicate that it refers to one item without specifying a specific measurement.
- "*Hours*" is commonly used to measure the duration or time spent on a service or labour-related task rather than a physical product. For example, in industries such as consulting, maintenance, or professional services, the unit of measurement for billing purposes may be "*Hours*" to reflect the time spent providing the service.

So, while "*Each*" and "*Hours*" are not typically used to measure physical products directly, they can have relevance in certain contexts related to products, such as specifying quantities or measuring service-related aspects.

Add unit descriptions

In osFinancials5/TurboCASH5 you can add unit descriptions to manage the stock items / inventory items or products you purchase and sell. When creating or editing stock items (Stock items on the Default ribbon) you can assign these units to specific stock items / inventory items or products. These unit descriptions will be printed in some reports as well as in document layout files for sales documents (i.e. quotes, invoices, credit notes and delivery notes) for purchase documents (i.e. orders, purchases and supplier returns).

To add unit descriptions:

1. On the Setup ribbon, select Setup → Stock information. Navigate to the Units tab.



2. Enter the Units of stock / product description.

3. Click on the Add button. The Description will be added to the list.

4. Click on the OK button to exit the "*Stock information*" screen.

By managing unit descriptions in osFinancials5/TurboCASH5, you can ensure accurate representation of stock units in reports and documents, facilitating effective inventory management and sales transactions.

Delete unit descriptions

If you want to delete a unit description, you can click on the Delete button. A confirmation message will be displayed:

> "Are you sure ?"

If you are not sure, click on the No button.

If you click on the Yes button, the unit description will permanently be removed from the list.

This will affect all reports and printing or reprinting of layout files supporting unit size descriptions. This deletion will impact reports and the printing or reprinting of layout files that use the unit descriptions.

If you accidentally delete a unit description and want to restore it, you need to follow these steps:

1. *Go to the Setup → Stock information menu on the Setup ribbon.*
2. *Add the unit description.*
3. *Go to Stock items on the Default ribbon and re-link the stock items to the new unit description.*
4. *This re-linking will apply to all printing or reprinting of layout files that support unit size descriptions.*

Note that already posted documents will not include the unit size descriptions. To print the unit size on

unposted documents, you need to edit the documents and reselect the stock item.

Units on document layout files

The Unit size will be displayed on the Default → Stock items, Reports → Stock items and on the following layout files:

Added the Unit Description to the following Layout files:

- Tutorial-Invoice
- Layout file - (TRN_1910)
- Document layout (15 codes) - (TRN_906277)
- Delivery note - (TRN_1313)

You may add the unit description to your own layout files. See - Reportman - Add Unit Descriptions to Layout files.

Created with the Standard Edition of HelpNDoc: Free EPub producer

Add Account / Tax classes

The Tax Classes tab in the Stock information section enables you to create and manage account classes/tax classes. Tax classes consist of five (5) accounts that are associated with the Ledger tab of stock items on the Default ribbon.

You may add Account classes or Tax Classes stock item type for each of the Tax (VAT/GST/Sales tax) items for example, standard rate, capital goods, zero rated, exempt goods, etc.) which is prescribed by your tax authority.

You may also use Account classes or Tax Classes to assign various stock items to various Sales accounts, Cost of Sales accounts and Stock control accounts.

When you link a stock item to a tax class, it automatically populates the Input Tax, Output Tax, Sales, Cost of Sales, and Stock control account fields on the Ledger tab for that specific stock item. This eliminates the need to manually select these accounts for each individual stock item.

By utilising tax classes, the Lookup button on the Ledger tab of stock items is disabled, as the tax class already defines the appropriate accounts for taxation and accounting purposes. This simplifies the process of assigning accounts to stock items, ensuring consistency and accuracy in tax calculations and financial reporting.

To set Stock Tax classes:

1. On the Setup ribbon, select Setup → Stock information. The "*Stock information*" screen will be displayed.

2. Click on the Tax classes tab.



3. Click (Add) to add a new tax class.

4. Enter the Name (description) for the tax class.

5. Select the following accounts:

    a) Input Tax - Select the Input Tax account.

> *If you are not registered for VAT/GST/Sales Tax, you may leave the Input Tax accounts blank.*

> *You may activate the Use default tax - Stock file override settings on the Creditors (Accounting information tab (Default ribbon)) for a creditor (supplier / vendor) account, and select a different VAT/GST/Sales Tax account or code on the Tax lookup for*

that creditor (supplier / vendor).

When purchase documents or supplier returns documents for the creditor (supplier / vendor) is updated (posted) to the ledger, the selected Input Tax account for this Stock item will be ignored and the purchase transaction will be updated (posted) to the specified Input Tax account for the creditor (supplier / vendor).

b) Output Tax - Select the Output Tax account.

If you are not registered for VAT/GST/Sales Tax, you may leave the Output Tax accounts blank.

You may activate the Use default tax - Stock file override settings on the Debtors (Accounting information tab (Default ribbon)) for a debtor (customer / client) account, and select a different VAT/GST/Sales Tax account or code on the Tax lookup for that debtor (customer / client).

When invoices or credit notes for the debtor (customer / client) is updated (posted) to the ledger, the selected Output Tax account for this Stock item will be ignored and the purchase transaction will be updated (posted) to the specified Output Tax account for the debtor (customer / client).

c) Sales - Select the Sales account.

If you have more than one Sales account, or use Sub-accounts, you may select the applicable Account or Sub-account for each of your Stock items.

d) Cost of sales - Select the Cost of sales account.

If you have more than one Cost of sales account, or use Sub-accounts, you may select the applicable Account or Sub-account for each of your Stock items.

e) Stock control - Select the Stock control account.

If you have more than one Stock control account, or use Sub-accounts, you may select the applicable Account or Sub-account for each of your Stock items.

6. Click (Save) to save the new tax class.

7. Click on the OK button on the "*Stock information*" screen.

8. Go to the Stock items and select a stock item from the list.

9. Click on the Ledger tab of the selected stock item and select the Tax class from the list.

10. All the accounts linked to the Tax classes tab - Setup → Stock information will be linked to the applicable account fields on the Ledger tab of the selected stock item.

Once you have created Tax classes, and selected a Tax class from the list on the Ledger tab of stock items, you may change them and click on the Apply to All button. This will update all stock items with the new accounts selected (changed) for the each stock item linked to the Tax class.

Tax class report

You may print a list of your Tax classes in the Reports → Stock → Stock item listing menu and select the Tax classes report.

Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with HelpNDoc's easy CHM conversion

Create Cost of sales

Before initiating any document processing in osFinancials5/TurboCASH5, it is crucial to ensure that all settings pertaining to Stock items, Cost of sales, and Documents are accurately configured.

During the initial setup of your Set of Books, it is essential to either input a purchase transaction or conduct a stock take-on for each stock item before entering any invoices. This step allows osFinancials5/TurboCASH5 to capture the cost price of each stock item.

The cost price plays a vital role in updating the Cost of sales and Stock accounts when an invoice is generated.

Failing to provide a cost price will result in the Cost of sales account being updated with a zero amount, which can lead to an inflated gross profit figure.

It is imperative that the required accounts and settings are properly configured before engaging in purchasing and selling activities involving trading stock items within your Set of Books.

Neglecting this step may yield inaccurate results in osFinancials5/TurboCASH5, such as missing Cost of sales transactions upon posting to the ledger or incorrect calculation of the cost of sales using average cost instead of the latest cost.

Use “average cost” or “latest cost” setting:

The selection between "using average cost" or "latest cost" is a critical setting that significantly impacts the valuation of your stockand could impact your profit and loss figures.. If you are uncertain about which method to choose, it is advisable to consult with your accountant, as the value assigned to your stock can have implications on your profit and loss figures.

Average cost” or Latest cost” setting and accounting frameworks and standards:

The choice between using "average cost" or "latest cost" for calculating the Cost of sales is an important decision that should align with the applicable accounting framework and standards, such as GAAP (Generally Accepted Accounting Principles), IFRS (International Financial Reporting Standards) full, or IFRS for SMEs (Small and Medium-sized Enterprises), depending on the jurisdiction.

Different accounting frameworks may have specific guidelines regarding the valuation of inventory and determining the cost to be allocated to the Cost of sales. These guidelines aim to ensure consistency, accuracy, and comparability in financial reporting.

To adhere to the appropriate accounting framework and standard, it is advisable to consult with your accountant or financial advisor. They can provide guidance on selecting the most suitable cost calculation method (average cost or latest cost) based on the specific requirements of your jurisdiction and the nature of your business operations.

Average cost” or Latest cost” setting and accounting frameworks and standards - Examples:

Both average cost and latest cost can be used as cost calculation methods for inventory valuation and Cost of sales in various accounting standards. The choice between these methods depends on the specific requirements and principles outlined in each accounting standard. Here are some examples:

1. *Generally Accepted Accounting Principles (GAAP): Under GAAP, both average cost and latest cost methods can be used. The specific application may vary depending on the country and the relevant accounting principles adopted within that jurisdiction.*
2. *International Financial Reporting Standards (IFRS): IFRS provides guidelines for inventory valuation but does not prescribe a specific cost calculation method. Entities following IFRS have the flexibility to choose between average cost and latest cost based on their specific circumstances and the requirements of the standard.*

It's important to note that the choice of cost calculation method should be consistent and applied in a manner that faithfully represents the financial position and performance of the company. It is recommended to consult with a qualified accountant or financial professional to determine the appropriate cost method based on the applicable accounting standards and the specific requirements of your business.

The transactions for the Default (trading stock) stock item type is as follows:

Trading stock items (Default stock item type)	
Purchases (Purchase journal)	*Invoices (Sales journal)*
DR - Stock item (net cost price - Input Tax Excluded) *DR - Input Tax (% of purchase price)* *CR - Creditor (full amount - Input Tax Included)*	*DR - Debtor (full amount - Output Tax Included)* *CR - Sales (selling price - Output Tax Excluded)* *CR - Output Tax (% of selling price)*
	Cost of sales journal
	DR - Cost of sales (cost price) *CR - Stock (cost price)*

The transactions for Supplier returns (Credit notes received from creditors (suppliers)) are exactly the opposite than those of purchase documents (Invoices received from creditors (suppliers)).

The transactions for Credit notes (issued to debtors (customers / clients)) are exactly the opposite than those of Invoices.

Trading stock items (Default stock item type)	
Supplier returns (Purchase journal)	*Credit notes (Sales journal)*
DR - Creditor (full amount - Input Tax Included) *CR - Stock item (cost price - Input Tax Excluded)* *CR - Input Tax (% of purchase price)*	*DR - Sales (selling price - Output Tax Excluded)* *DR - Output Tax (% of selling price)* *CR - Debtor (full amount - Output Tax Included)*
	Cost of sales journal
	DR - Stock (cost price) *CR - Cost of sales (cost price)*

All other stock types (excluding the Bills of Materials (BOM) stock item type), have no cost of sales transactions.

The Bills of Materials (BOM) and the Bills of Materials (Production) (BOM (Production)) stock types, are usually linked to trading stock items (components).

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Cost of Sales and FIFO / LIFO

Before initiating any document processing in osFinancials5/TurboCASH5, it is crucial to ensure that all settings pertaining to Stock items, Cost of sales, and Documents are accurately configured.

Cost price setting and calculation of Cost of Sales

During the initial setup of your Set of Books, it is essential to either input a purchase transaction or conduct a stock take-on for each stock item before entering any invoices. This step allows osFinancials5/TurboCASH5 to capture the cost price of each stock item. The cost price plays a vital role in updating the Cost of sales and Stock accounts when an invoice is generated. Failing to provide a cost price will result in the Cost of sales account being updated with a zero amount, which can lead to an inflated gross profit figure.

It is imperative that the required accounts and settings are properly configured before engaging in purchasing and selling activities involving trading stock items within your Set of Books. Neglecting this step may yield inaccurate results in osFinancials5/TurboCASH5, such as missing Cost of sales transactions upon posting to the ledger or incorrect calculation of the cost of sales using average cost instead of the latest cost.

The selection between using "*average cost*" or "*latest cost*" is a critical setting that significantly impacts the valuation of your stock. If you are uncertain about which method to choose, it is advisable to consult with your accountant, as the value assigned to your stock can have implications on your profit and loss figures.

Cost of sales - Using "average cost" or "latest cost" setting

Cost of sales - Using "*average cost*" or "*latest cost*" is a critical setting that you may take note of when following the accounting framework and standard e.g. GAAP, IFRS full, IFRS for SMEs depending on the jurisdiction

Indeed, the choice between using "*average cost*" or "*latest cost*" for calculating the Cost of sales is an important decision that should align with the applicable accounting framework and standards, such as GAAP (Generally Accepted Accounting Principles), IFRS (International Financial Reporting Standards) full, or IFRS for SMEs (Small and Medium-sized Enterprises), depending on the jurisdiction.

Different accounting frameworks may have specific guidelines regarding the valuation of inventory and determining the cost to be allocated to the Cost of sales. These guidelines aim to ensure consistency,

accuracy, and comparability in financial reporting.

To adhere to the appropriate accounting framework and standard, it is advisable to consult with your accountant or financial advisor. They can provide guidance on selecting the most suitable cost calculation method (average cost or latest cost) based on the specific requirements of your jurisdiction and the nature of your business operations.

In which accounting standard is average cost or latest cost followed?

Both average cost and latest cost can be used as cost calculation methods for inventory valuation and Cost of sales in various accounting standards. The choice between these methods depends on the specific requirements and principles outlined in each accounting standard. Here are some examples:

1. Generally Accepted Accounting Principles (GAAP): Under GAAP, both average cost and latest cost methods can be used. The specific application may vary depending on the country and the relevant accounting principles adopted within that jurisdiction.
2. International Financial Reporting Standards (IFRS): IFRS provides guidelines for inventory valuation but does not prescribe a specific cost calculation method. Entities following IFRS have the flexibility to choose between average cost and latest cost based on their specific circumstances and the requirements of the standard.

It's important to note that the choice of cost calculation method should be consistent and applied in a manner that faithfully represents the financial position and performance of the company. It is recommended to consult with a qualified accountant or financial professional to determine the appropriate cost method based on the applicable accounting standards and the specific requirements of your business.

Is the use of average cost and latest cost related to FIFO and LIFO?

Yes, the use of average cost and latest cost can be related to the inventory valuation methods of FIFO (First-In, First-Out) and LIFO (Last-In, First-Out).

FIFO assumes that the first items purchased or produced are the first ones sold. Under FIFO, the cost of inventory sold is based on the oldest or earliest purchases, while the ending inventory is valued at the most recent purchases. This generally results in the Cost of sales being calculated using the oldest cost prices, which may be considered similar to the average cost method.

LIFO, on the other hand, assumes that the last items purchased or produced are the first ones sold. Under LIFO, the cost of inventory sold is based on the most recent purchases, while the ending inventory is valued

at the oldest or earliest purchases. This generally results in the Cost of sales being calculated using the most recent cost prices, which may be considered similar to the latest cost method.

While average cost and latest cost methods are not strictly defined by the FIFO or LIFO principles, they can align with the cost flow assumptions used in these methods. Average cost represents an average of all costs incurred, while latest cost represents the most recent cost incurred.

It's important to note that the use of FIFO and LIFO, as well as the choice between average cost and latest cost, may be subject to specific accounting regulations and requirements in different jurisdictions. It's advisable to consult with a qualified accountant or financial professional to determine the appropriate inventory valuation method based on the applicable accounting standards and regulations in your specific region.

Is the use of average cost related to FIFO or LIFO?

The use of average cost is not directly related to either FIFO (First-In, First-Out) or LIFO (Last-In, First-Out). Average cost is a separate inventory valuation method that calculates the cost of inventory as an average of the costs of all items in stock.

Under the average cost method, the cost of inventory is determined by dividing the total cost of goods available for sale by the total number of units available for sale. This average cost per unit is then used to value both the Cost of sales and the ending inventory.

In contrast, FIFO assumes that the first items purchased or produced are the first ones sold, while LIFO assumes that the last items purchased or produced are the first ones sold. Both FIFO and LIFO methods assign specific costs to the inventory based on the order of acquisition or production.

While average cost can provide a smoothed and consistent valuation for inventory, it is not tied to the specific flow assumptions of FIFO or LIFO. The choice between average cost, FIFO, or LIFO depends on factors such as the nature of the business, industry practices, applicable accounting standards, and regulatory requirements.

Is the use of latest cost related to FIFO or LIFO?

The use of the latest cost method is more closely related to the LIFO (Last-In, First-Out) inventory valuation method.

Under the LIFO method, the assumption is that the most recently acquired or produced items are the first ones sold. Therefore, when calculating the cost of goods sold, the cost assigned to each unit is based on the most recent cost of acquiring or producing inventory. This approach can result in a better reflection of current market prices and cost changes.

In the context of the latest cost method, the cost assigned to inventory is based on the most recent or latest cost incurred to acquire or produce the items. This method allows for greater responsiveness to changes in the cost of inventory, as it values the inventory based on the most up-to-date costs. This can be particularly useful in industries where the cost of inventory fluctuates frequently.

While there is a relationship between the use of the latest cost method and the LIFO inventory valuation method, it's important to note that they are not interchangeable. The LIFO method involves specific assumptions and requirements for inventory accounting, including the need to maintain detailed records of the order of acquisition or production. The use of the latest cost method, on the other hand, focuses on valuing inventory based on the most recent costs incurred without necessarily adhering to the strict LIFO requirements.

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Selling prices

Selling price descriptions in osFinancials5/TurboCASH5

Price agreement plugin - Manual - Shop - Licence : Once-off -

In addition to the standard 3 selling prices in osFinancials5/TurboCASH5, Price agreement plugin, allows you to set up to five (5) levels of quantity discounts that can be applied to specific debtors or groups of debtors. Additionally, you can set a special price for individual debtors per product. These prices will overrule the default Selling price 1 / 2 / 3 and can be set per debtor (customer / client). The price agreement may also be activated for creditors (suppliers / vendors).

Global selling prices

osFinancials5/TurboCASH5 supports up to 3 selling prices (i.e. Selling price 1, Selling price 2 and Selling price 3). You may change the descriptions of these selling prices on the "Selling price descriptions" section of the Default tab of Setup → Stock information to suit your specific requirements and set one of these Selling prices as the default Selling price (global setting) for your Set of Books.



These selling price descriptions will be displayed in the osFinancials5/TurboCASH5 interface, stock items and reports in the following options:

- Stock item grid and stock item form
- Documents - when processing sales documents (i.e. invoices, credit notes and quotes), these selling price descriptions may be used to select a different selling price than the default selling price.



Default selling price for debtors

In addition to this, you may set one of these Selling prices as the default Selling price on the Accounting information tab for specific debtor (customer / client) accounts.



Examples of Selling price descriptions

Selling price descriptions in osFinancials5/TurboCASH5 can vary based on the specific needs and industry of the user. These descriptions are typically used to differentiate between different pricing tiers, discounts, or special offers. Here are some examples of selling price descriptions:

1. Standard Price: Regular selling price without any discounts or promotions.
2. Wholesale Price: The price offered to wholesale buyers or bulk purchasers.
3. Retail Price: The price at which the product is sold to end consumers through retail channels.

Here are some more examples of selling price descriptions:

1. Promotional Price: A temporarily reduced price for a specific period or promotion.
2. Member Price: Exclusive pricing for members or subscribers to a loyalty program.
3. Contract Price: Agreed-upon price for products or services under a contractual agreement.
4. Volume Discount Price: Price reduction based on the quantity purchased, encouraging bulk buying.
5. Seasonal Price: Pricing that varies according to seasons or specific times of the year.
6. Bundle Price: Combined pricing for a package or bundle of related products.
7. Clearance Price: Heavily discounted price to clear out excess or outdated inventory.
8. Special Event Price: Pricing for special events or occasions, often with limited-time offers.
9. Preferred Customer Price: Discounted price for preferred or loyal customers.
10. Tiered Pricing: Differentiated prices based on customer tiers, such as bronze, silver, and gold levels.

These descriptions are just examples, and users can customize them according to their business requirements. It's important to choose descriptions that make it easy for users to understand and select the appropriate selling price for each inventory item.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Options setup

If you wish to create the Option item and Option item (no stock) stock types, you may select items that are a combination of options (like colour and size) options.

These options are then linked to the Options stock item type (Stock items on the Default ribbon). When

processing documents, the available options (options list) will be launched from the quantity fields when selecting documents.

The Options with stock allows every entry to have a sales price, cost price, quantity and minimum stock level. This will also be used in generating purchases on supplier 1.

To create / add Options for option items:

1. On the Setup ribbon, select Setup → Stock information. The "*Stock information*" screen will be displayed.

2. Click on the Setup options button. The "*Setup options*" screen is displayed:



3. Click on the (Add) button. A record number will automatically be assigned. Enter the name for the Option, e.g. Colour, Size, etc.

4. Click on the (Save) icon.

5. Double-click on the item to add the list of options and the extra prices. This may be the size, colours, etc. The selling price of the first option (default option) should be zero, as this is the default selling price of the stock item to which this is linked. The extra prices for the other options (on the options list) are the extra prices to be added to the stock items default selling price.

6. Once finished with the options list, click on the OK button to save the list.



7. Close the "*Setup options*" screen (click Close button on the title bar).
8. Close the "*Stock information*" screen and return to the Stock items screen (Default ribbon). You may then link this option on the Options tab of the Stock item.

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Stock item list screen

---

osFinancials5/TurboCASH5 features a robust inventory system that allows users to store an unlimited number of stock items (inventory items) or products in the stock ledger. Each stock item has specific details associated with it. The inventory system allows for the structuring of stock items into up to two (2) reporting groups, which aids in data organisation and analysis.

osFinancials5/TurboCASH5 also offers eleven different stock item types to choose from, providing flexibility in managing various types of products.

When processing documents for debtors or creditors or selecting stock items for reports, the stock item lookup function is utilised to choose the appropriate products. The selected stock item's details are then used to calculate the selling and cost prices based on the specified quantity, and this information is displayed on the respective documents and reports.

Overall, osFinancials5's inventory system offers a comprehensive solution for managing and tracking stock items (inventory items) or products, allowing for efficient inventory tracking, accurate cost and selling price calculation, and streamlined document and report generation.

The Stock items feature allows you to manage your inventory items or products. You have the ability to create new stock items or products, edit existing ones, delete or disable items as needed. The feature provides filtering and search options to help you locate specific items.

Within each item, you can make changes to the stock code, description, extra description, quantities, reorder levels and more. You can also manage various settings on the Ledger tab and various activities on the Document groups, Transactions, Image, Multi-group, and Backorders tabs.

To access Stock items:

1. On the Default ribbon, select Stock items (F12).



2. Buttons – The following buttons are available:

   a) New – Create a new stock item.

   b) Delete – Delete remove a selected stock item.

   c) Edit – Edit / change a selected stock item.

   > *You may also double click on a selected stock item.*

   d) Save – Save any changes to a stock item.

   e) Cancel – Cancel will revert to the previous values. Any changes will not be saved.

   f) Copy from item – This will create an exact copy of a selected stock item. You only need to enter the Stock code and change / edit the necessary fields.

   > *You may also select the stock item type. The fields that are not applicable to a selected stock item type, will be disabled / enabled.*

   g) Default / Advanced mode – This will display the Export / Import, Adjust stock and Settings tabs. Clicking on the Default button, the button's caption will change to display Advanced mode. This will hide the Export / Import, Adjust stock and Settings tabs. In the Advanced mode, you may enter / edit data (values) of stock items (like you would in a spreadsheet).

3. Limit rows - The default is "*200*" records to be listed displayed on this screen. If necessary, you may change that.

4. Reports – Prints the selected report type for the selected stock item(s) only. If you need to include all items, click on the Report button.

> *These barcodes or the Yagoda barcodes may also be printed from the Reports → Stock → Print labels (Reports ribbon).*

> *These reports are designed using the Reportman. These reports are located in the "... \plug_ins\reports\REPORTS\STOCK" directory.*

> *There are two (2) options to print these reports, i.e.:*
>
> - *Click on the Report button – to include all stock items in the reports.*
> - *Right-click on a selected item, and select Print single item option from the context menu.*

5. Use barcode printer – Select this option if you have a barcode printer configured and setup on your system; and you need to print the Barcodes (i.e. Barcode or Yagoda barcode) report type from the list.

6. Single line mode - This option has three (3) basic settings:

   a) If this field is selected (ticked) and the Advanced mode (Export / Import, Adjust stock and Settings tabs displayed), each stock item record will be listed in a single row.

   b) If this field is not selected (not ticked) and the Advanced mode (Export / Import, Adjust stock and Settings tabs displayed), a fixed right pane column (similar to the left pane on which the stock code and date last action columns are by default displayed) will be added. You may drag any column between the left and right panes to be added.

   c) If this field is selected (ticked) and the Default mode (Export / Import, Adjust stock and Settings tabs not displayed), each stock item record will be listed in a single row.

   d) If this field is not selected (not ticked) and the Advanced mode (Export / Import, Adjust stock and Settings tabs displayed), the fields for stock item records will be grouped in some columns (e.g. Units, Stock group1 / 2, Stock item type, Cost centres, etc.).

7. Update type - The following options are available to change (group) the columns:



8. Search filter / options – Filter by entering the Item Code, Description or Extra description and/or by selecting (ticking) the Reporting group 1 / 2. If you click on the Search button, the only those stock items that matches your search / filter criteria will be listed. If you click on the Type button, you may select Item Code, Description, Extra description, Reporting group 1, Reporting group 2 or Creditor.



If the "Creditor" option is selected in the "Type" field, you may select the Creditor account on the Lookup. This will list those stock items which are linked to the creditor (supplier / vendor) account in the "Preferred supplier 1" (Default Supplier 1) field of a Stock item.

9. Context menu – The following options are available:

   - Print single item – Prints the selected report type for the selected stock item(s) only. If you need to include all items, click on the Report button.

   - Copy – The following options to process Supplier 1 and Purchase Sales Stock Tax are available:

     - Copy from / init and Paste to / perform on selected rows:



§ Stock item - Similar than the Copy from item button. – This will create an exact copy of a selected stock item. You only need to enter the Stock code and change / edit the necessary fields.

- Reporting group 1 - Change the reporting group of a stock item, if Reporting group 1 was set for Stock items (as added in Setup → Groups - Stock group 1 on the Setup ribbon).

> *The colours of the rows (list of stock items) will be changed, if set in Reporting group 1.*

- Reporting group 2 – Change the reporting group of a document, if Reporting group 2 was set for Stock items (as added in Setup → Groups - Stock group 2 on the Setup ribbon).

- Mass check - This option will run a check on all stock items. The stock item form will be automatically opened and closed for each stock item.

> *If the BOM (Production) stock item type is selected, the following context menu options, is available:*
>
> · *Disassemble*
>
> · *Assemble*

10. Grid totals - This will display the line count (number of records in rows / stock items) that is available on the list. The number of records will indicate the number of records that matches your filter / search criteria.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Filter options (Stock)

The osFinancials5/TurboCASH5 grid has a powerful and user-friendly filtering and sorting system that makes it quicker and easier than other methods. With just a few mouse clicks, you can group, sort, and filter any column(s) of data on most screens in a Set of Books. This feature is very useful and efficient for managing and analysing data.

Type



You may enter or search for a stock item using the following options:

- Item code - enter a valid item code.
- Description - Enter a description or part of the description.
- Extra description - Enter a extra description or part of the extra description.
- Reporting group 1 / 2 - All stock item groups as set in Groups (Setup ribbon) will be listed. Select (tick) to list only those stock items linked to a selected stock reporting group.
- Creditor - If preferred suppliers is selected on stock items, you may lookup a creditor to view only those stock items linked to a supplier.

If you click on the Type button, you may select Item code, Descriptions, Extra description, Reporting group 1, Reporting group 2 or Creditors.



Column headings

All the data for each of your stock items are listed in columns. To view change the sequence in which the data is displayed, you may:

- Scroll bars - Scroll to the right or to the left on the horizontal scroll bar to view the information.
- Sequence of rows - Click on any of the column headings to change the sorting sequence of the stock items listed in the descending or ascending sequence.
- Sequence of columns - Click on a column heading and drag it to the right or to the left to change the sequence in which the columns need to be displayed.

The "Line count" will show the number of records (stock items) that matches your search or filter criteria.

You may also search for stock items in the "Investigator" (Search on the Default ribbon).

The column headings are grouped into three (3) bands:

- *Left - Click on a column and drag the column to the desired position.*
- *Data - You may also drag it to the right band or to the left band.*
- *Right - By default this band is empty. Any number of columns can be dragged to that band.*

Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

Stock list screen - Default mode

The stock item list screen has two (2) mode options available:

- Default mode option - This is a plain list view of the stock items on which the data in the columns is not editable.
- Advanced mode option - This mode will enable the following options:
    - The data in the columns on the stock item grid can be edited (like you would in a spreadsheet).
    - Add the Export / Import, Adjust stock and Settings tabs.

By default, the "*Single line mode*" option is selected (ticked). The details for each of the stock items in the list will display in a single line.

If this option is selected, a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns can be grouped.

Default mode : Single line mode - Selected

The details for each of the stock items in the list will display in a single line.



Default mode : Single line mode - Not selected

If the "*Single line mode*" option is not selected a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns can be grouped.



The column headings are grouped into three (3) bands:

- *Left - Click on a column and drag the column to the desired position.*
- *Data - You may also drag it to the right band or to the left band.*
- *Right - By default this band is empty. Any number of columns can be dragged to that band.*

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Stock list screen - Advanced mode

The stock item list screen has two (2) mode options available:

- Default mode option - This is a plain list view of the stock items on which the data in the columns is not editable.
- Advanced mode option - This mode will enable the following options:
    - The data in the columns on the stock item grid can be edited (like you would in a spreadsheet).

- Add the Export / Import, Adjust stock and Settings tabs.

By default, the "*Single line mode*" option is selected (ticked). The details for each of the stock items in the list will display in a single line.

If this option is selected, a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns can be grouped.

Advanced mode : Single line mode - Selected

If the "*Advanced mode*" option is selected, the Advanced mode button's caption, will change to Default. It will enable the following options:

- The data in the columns on the stock item grid can be edited.
- Add the Export / Import, Adjust stock and Settings tabs.



Advanced mode : Single line mode - Not selected

The data for each of the stock items in the list can not be edited. You need to select a stock item and edit the details in the Stock item form.



The column headings are grouped into three (3) bands:

- *Left - Click on a column and drag the column to the desired position.*
- *Data - You may also drag it to the right band or to the left band.*
- *Right - By default this band is empty. Any number of columns can be dragged to that band.*

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's CHM Help File Creation Features

Import / Export tab

The Import / Export tab on the on the Stock item list screen will only be available when the mode in set to Default. In the Advanced mode is not selected, the Import / Export tab will not be displayed.

The stock item screen may also be launched as a floating screen from the Input → Adjust stock menu on the Default ribbon.



The options, is as follows:

1. Spreadsheet import -
    - Spreadsheet export - You may export stock items and save it as a "*Excel Workbook (*.xlsx) file type.*
    - Spreadsheet import - You may import stock items from a saved "*Excel Workbook (*.xlsx) file type.*
2. Export - Create an Export file in the "*Tab delimited (*.txt)*" (default - recommended).

    Stock items may also be exported in Export - Stock items (Setup ribbon).

3. Import - Import a valid file exported via the Import option.

    Stock items may also be imported from Import - Stock items (Setup ribbon).

4. Enter is next record - To be advised.
5. Auto detail on one record - To be advised.
6. Match on creditor code - To be advised.

Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

Adjust stock tab

The Adjust stock tab on the on the Stock item list screen will only be available when the mode in set to Default. In the Advanced mode is not selected, the Adjust stock tab will not be displayed.

The stock item screen may also be launched as a floating screen from the Input → Adjust stock menu on the Default ribbon.



To adjust selling prices for all stock items:

1. Select the first stock item from the list.
2. The percentage in the "*Use percentage*" field, is inactive.
3. Use transactions - To be advised.
4. Enter or select the date ("*Date*" field).
5. Click on the OK button. All selling prices will automatically be adjusted by the specified percentage.

To adjust specified selling prices for stock items:

1. Select the stock item from the list.
2. Enter the selling prices 1 / 2 and 3 in the "*Exclusive*" field.
3. Enter or select the date ("*Date*" field).
4. Click on the <-Set selected to this price button. A confirmation message will be displayed.

   "Edit price?"

5. Click on the Yes button, if you need to change the selling prices.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Settings tab

The Settings tab on the on the Stock item list screen will only be available when the mode in set to Default mode. If the Advanced mode is not selected, the Settings tab will not be displayed.

The stock item screen may also be launched as a floating screen from the Input → Adjust stock menu on the Default ribbon.



The Settings tab allows quick access to the following options:

1. Setup stock – This will launch the Stock information screen. On this screen, you may set the units of stock, change the selling price descriptions, set the default selling price. Cost of sales parameters may also be set for the Default (Trading stock) stock item type. You may also configure document processing options.

2. Setup group – This will launch the "*Groups*" screen (Groups on the Setup ribbon). On this screen, you may add Reporting groups (i.e. Stock group 1 and/or Stock group 2). These may be used to search and filter your stock items and to print reports.

3. NoCalcFields - No calculation of fields. This option is by default selected (ticked). It this option is not selected (tick removed), it will change the values of certain fields.

4. Save layout - This button will save the "*Stock items*" list screen grid layout.

To save your column preferences, you may click on the Save layout on the Settings tab in the Advanced mode. Your view and grid layout preferences will be available when you close active forms or close and reopen the Set of Books and access Stock items again.

Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

Show / Hide columns

To save your column preferences, you may click on the Save layout on the Settings tab in the Advanced mode. Your view and grid layout preferences will be available when you close active forms or close and reopen the Set of Books and access Stock items again.

By default, all thirty-nine (39) columns will be displayed and listed in the Stock item list screen for each stock item type.

The data in columns is grouped in to three (3) bands:

1. Left - Lists the id (stock record id), Stock code, Description, Date last action, Total stock value, Total Expected sales on price 2, and delivery delay.

2. Data - Barcode, Stock group 1, Stock group 2, On hand, Reorder, Avg. cost, Unit cost, Discount, Selling price 1, Selling price 2, Selling price 3, Units, Tax class, Type, Disabled, Extra description, Input (tax account code), Output (tax account code), Cost (Cost of sales account code), Sales (account code), Stock (account code), Net weight, Gross weight, Reorder at, Manufacturer, Minimum Salesperson, Supplier stock code 1, Supplier stock code 2, Preferred supplier 1, Preferred supplier 2 and Cost centre.

Default



Sorted (selected) - Alphabetical list



3. Right - This band is by default blank. You may drag any column or columns from the Left band or the Data band to the Right band.

You may drag and drop any of the columns on the left band to the right band and the columns from the right band to the left band, to customise the grid for your requirements.

Hide / Show bands

Left band - Remove the tick in the first tick box. This will hide the id (stock record id), Stock code, Description, Date last action, Total stock value, Total Expected sales on price 2, and delivery delay columns.

Data band - Remove the tick in the second tick box. This will hide all columns in the data band.

Right band - Remove the tick in the third tick box. This will hide all columns in the right band (if any columns were dragged to the right band).



The column headings are grouped into three (3) bands:

- *Left - Click on a column and drag the column to the desired position.*
- *Data - You may also drag it to the right band or to the left band.*
- *Right - By default this band is empty. Any number of columns can be dragged to that band.*

Hide / Show columns

Click on the second block - Column headings - A list of the fields will be listed.

Remove the ticks for the columns to hide or select the columns you need to display.

You may use the Up arrows and/or the Down arrows Right or Left arrows keys to navigate the fields. You may use the Space bar to deselect (remove the tick) or to reselect (tick a field again).



You may change sequence in which the data in the columns is displayed by selecting one of the following options on the Update type:



Drag columns

Click on a column heading and drag it to the right or to the left to change the sequence in which the columns need to be displayed.



Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Group columns

If the “*Single line mode*” option is not selected (tick removed), a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns can be grouped.

Group columns

Select a column and click on it. While holding the mouse button down, drag it to the column header bar "*Use your mouse to pull a column here to group on that column*". Select any other column to drag and drop it on column header bar. You may select as many columns, as necessary, to group your data.

You may also drag and drop these columns to the right or left to change the grouping of these columns.



Remove grouped columns

To remove a column from column header bar "*Use your mouse to pull a column here to group on that column*", you may use the following two (2) options:



1. Select the column heading (e.g., “*Stock group 1*”) on column header bar "*Use your mouse to pull a column here to group on that column*", and drag it to the first line (above the column headings). When the mouse pointer change to a big X, drop it. The column will automatically be placed in the correct default sequence (or the place of the previous grid layout).
2. If you wish to change the column to a specific place, select the column heading (e.g., “*Stock group 1*”) on column header bar "*Use your mouse to pull a column here to group on that column*", and drag it to the second line (column headings). When you drop it, the column will be added to the selected position or sequence of the columns.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Stock items - Context menu

Stock item context menu options:

- Print single item - You may select reports from the Stock items (Default ribbon) to print all stock items or selected stock item(s):
- Copy / Pate - You may copy the specific data of a selected stock item and paste (replace) the data of selected stock item(s).
- Reporting Stock group 1 / 2 - You may change the Stock group 1 and/or 2 for selected stock item(s).
- Mass check - This option will run a check on all stock items.

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Context menu - Print single item

You may select the following reports from the Stock items (Default ribbon) to print all stock items or selected stock item(s):

Report name	*Description*
Production list	*The "Production list" report lists the transactions of all items (other stock item types) linked to the BOM and BOM (Production) stock item type on the BOM tab.*
Stock item list - Active stock	*The "Stock item listing - Active stock" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. Only active (enabled) Stock items will be listed. Inactive (disabled) Stock items not will be listed.*
Stock item listing	*The "Stock item listing" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. All active (enabled) Stock items as well as inactive (disabled) Stock items will be listed.*
Barcode	*The "Barcode" report prints barcodes for all stock items or a selected stock item.*
Yagoda barcode	*The "Yagoda barcode" report prints Yagoda barcodes for all stock items or a selected stock item.*
Reporting group 1	*The Reporting group 1 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.*
Reporting group 2	*The Reporting group 2 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.*
Historical value	*The "Historical value" report for stock items, will list the Stock code, Stock description, Quantities and Total value for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.*
Stock movement	*The "Stock movement" report will list the Stock code, Stock description, Quantities and Average cost for a selected stock item.*
Outstanding orders	*The "Outstanding orders" report will list all outstanding orders, which is not yet confirmed (converted to a purchase document). This report will list all unconfirmed orders for each creditor*

	(supplier / vendor) account by order number, order date stock quantities, stock item code, stock item description and document reporting group 1.
Outstanding quotes	*The "Outstanding quotes" report will list all outstanding quotes, which is not yet confirmed (converted to invoices). This report will list all unconfirmed quotes for each debtor (customer / client) account by quote number, quote date stock quantities, stock item code, stock item description and document reporting group 1.*
Reorder quantities	*The "Reorder quantities" report will list the Stock code, Stock description, Quantity on hand, Unposted Invoices/Purchases, Reorder level and quantity to order for each stock item.*
Transaction details	*The "Transaction details" report list the document date (and time, if available) document number, document type, quantities, salesperson and document reference for each stock item.*
Value stock account	*The "Value stock account" report lists the total value of the stock control account. If the "Show details" option is selected, it will list the the value of each stock item.*
Price list - Large retail - Sales	*The "Price list - Large retail - Sales" report will list quantity discount up to five (5) price levels of a selected stock item for a selected debtor (customer / client) account.*
Price list - Large retail - Purchases	*The "Price list - Large retail - Purchases" report will list quantity discount up to five (5) price levels of a selected stock item for a selected creditors (suppliers / vendors) account.*

Created with the Standard Edition of HelpNDoc: Experience the power of a responsive website for your documentation

Print single item - Barcode

Barcode - Stock grid reports

The "*Barcode*" report prints barcodes for all stock items or a selected stock item.

You may select the Barcode report on the Reports → Stock → Print labels menu (Reports ribbon) to print barcodes. You may select a specific stock item or a range of stock items; or all stock items linked to a specific Stock reporting group 1.

Barcode options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

Prints directly to printer - Control (bytes =0)



Report button

Prints barcode for all stock items.



Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Print single item - Yagoda barcode

Yagoda barcode - Stock grid reports

The "*Yagoda barcode*" report prints Yagoda barcodes for all stock items or a selected stock item.

You may select the Yagoda barcode report on the Reports → Stock → Print labels menu (Reports ribbon) to print Yagoda barcodes. You may select a specific stock item or a range of stock items; or all stock items linked to a specific Stock reporting group 1.

Yagoda barcode options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.

Report button

Prints barcode for all stock items.



Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Print single item - Historical value

Historical value - Stock grid reports

The "*Historical value*" report for stock items, will list the Stock code, Stock description, Quantities and Total value for a selected stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.

Historical value options



Print single item (context menu)

Parameter - Select the Until date.



Prints directly to the Reportman preview screen.



Report button

Parameter - Select the Until date.



Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

Print single item - Outstanding orders

Outstanding orders - Stock grid reports

The "*Outstanding orders*" report will list all outstanding orders, which is not yet confirmed (converted to a purchase document). This report will list all unconfirmed orders for each creditor (supplier / vendor) account by order number, order date stock quantities, stock item code, stock item description and document reporting group 1.

You may print a list of the unconfirmed orders in the Reports → Documents → Document listing per account → Purchase documents - Orders (Reports ribbon). The "Confirmed" option on the report parameters needs to be blank (not ticked).

Outstanding orders (Unconfirmed) orders options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Print single item - Outstanding quotes

Outstanding quotes - Stock grid reports

The "*Outstanding quotes*" report will list all outstanding quotes, which is not yet confirmed (converted to invoices). This report will list all unconfirmed quotes for each debtor (customer / client) account by quote number, quote date stock quantities, stock item code, stock item description and document reporting group 1.

You may print a list of the unconfirmed quotes in the Reports → Documents → Document listing per account → Sales documents - Quotes (Reports ribbon). The "Confirmed" option on the report parameters needs to be blank (not ticked).

Outstanding quotes (Unconfirmed) quotes options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Print single item - Production list

Production list - Stock grid reports

Production list report lists the transactions of all items (other stock item types) linked to the BOM and BOM (Production) stock item type on the BOM tab.

This report will only list the active stock items. Disabled (inactive) stock items will be excluded from this report.

Production list options



Print singe item (context menu)

The Print singe item (context menu option) will only print the selected Stock item, if the Stock item type is BOM and BOM (Production).



Report button

The report will print all active Stock items for the BOM and BOM (Production) stock item types.



Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Print single item - Reorder quantities

Reorder quantities - Stock grid reports

The "*Reorder quantities*" report will list the Stock code, Stock description, Quantity on hand, Unposted Invoices/Purchases, Reorder level and quantity to order for each stock item.

You may select the "Reorder report" or the "Current stock levels" report on the Reports → Stock → Reorder menu (Reports ribbon). You may select a specific stock item or a range of stock items; or all stock items linked to a specific Stock reporting group 1.

Reorder quantities options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Print single item - Reporting group 1

Reporting group 1 - Stock grid reports

The Reporting group 1 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock reporting group 1 and the Unit description.

You may select the "All Selling prices" or the "Stock item listing" report on the Reports → Stock → Stock item listing menu (Reports ribbon) to print all three (3) selling prices. You may select a specific stock item or a range of stock items; or all stock items linked to a specific Stock reporting group 1.

Reporting group 1 options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Output with HelpNDoc's Advanced Project Analyzer

Print single item - Reporting group 2

Reporting group 2 - Stock grid reports

The Reporting group 2 for stock items, will list the Stock code, Stock description, Quantity on hand as well as Selling price 2 for each stock item. These stock items will be grouped and listed for each Stock

reporting group 1 and the Unit description.

You may select the "All Selling prices" or the "Stock item listing" report on the Reports → Stock → Stock item listing menu (Reports ribbon) to print all three (3) selling prices. You may select a specific stock item or a range of stock items.

Reporting group 2 options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Print single item - Stock movement

Stock movement - Stock grid reports

The "*Stock movement*" report will list the Stock code, Stock description, Quantities and Average cost for a selected stock item.

Stock movement options



Stock movement (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Irrespective of the stock item selected on the stock grid, it always prints the first available stock item on the list.

In this example, the first item on the stock grid (i.e. "*Compressor*" is printed while the "*Drill press*" is selected.



Created with the Standard Edition of HelpNDoc: Easily create EBooks

Print single item - Stock item listing

Stock item listing - Stock grid reports

The "*Stock item* listing" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. All active (enabled) Stock items as well as inactive (disabled) Stock items will be listed.

You may select the "Stock item listing" report on the Reports → Stock → Stock item listing menu (Reports ribbon). You can choose to print a report for a specific stock item or a range of stock items. You can also filter the report to include only stock items that are linked to selected stock groups for stock group 1.

Stock item listing options



Stock item listing (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: Easily create EBooks

Print single item - Stock item listing - Active items

Stock item list - Active stock - Stock grid reports

The "*Stock item listing - Active stock*" report, will list the Stock code, Stock description, Quantity on hand, the Unit description and the total value for each stock item. Only active (enabled) Stock items will be listed. Inactive (disabled) Stock items not will be listed.

You may select the "Stock item listing" report on the Reports → Stock → Stock item listing menu (Reports ribbon). You can choose to print a report for a specific stock item or a range of stock items. You can also filter the report to include only stock items that are linked to selected stock groups for stock group 1.

Stock item list - Active stock options



Stock item listing - Active stock (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Report button

Prints the report for all stock items.



Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Print single item - Transaction details

Transaction details - Stock grid reports

The "*Transaction details*" report list the document date (and time, if available) document number, document type, quantities, salesperson and document reference for each stock item.

You may select the "Documents" and the "Stock In / Out" reports on the Reports → Stock → Stock In / Out menu (Reports ribbon) to print stock transactions. You may select a specific stock item or a range of stock items; or all stock items linked to a specific Stock reporting group 1.

Transaction details options



Print single item (context menu)

Prints directly to default printer and not to the Reportman preview screen.

In this example, the system's default printer is set to "*Microsoft print to PDF*" where you need to enter a file name to save the file print as "*PDF Document (*pdf)*" file type on the " *Save Print Output As*" screen.



Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com

Stock - Transaction details - Grid

Code	Description	Quantities	Disabled
3DRILL	Drill press	10	No

Date	*Document no.*	*Type*	*Quantity*	*Salesperson*	*Document reference*
2021/04/05	PU000003	12	3	Russell	4562
2021/04/07	IN000005	10	-1	Tracy	D-101
2021/04/11	IN000008	10	-2	Tracy	D-102
2021/05/08	IN000010	10	-1	Russell	
2021/06/05	IN000011	10	-1	Tracy	D-101
2021/06/12	IN000014	10	-2	Tracy	D-102
2021/06/15	IN000015	10	-1	Tracy	D-101
2021/06/20	IN000017	10	-1	Russell	C-103
2021/06/24	IN000018	10	-2	Tracy	D-102
2021/06/30	IN000019	10	-2	Tracy	D-101
2021/06/30	IN000020	10	-2	Russell	A-103-2
2021/06/26	PU000005	12	3	Russell	4562
2021/06/17	SR000002	13	-3	Russell	4562
2021/06/19	SR000003	13	-3	Russell	4562
2021/06/30	CR000001	11	2	Tracy	D-101
2021/06/22	CR000002	11	2	Tracy	D-102
2021/06/30	CR000003	11	1	Russell	C-103
2021/05/07	ST00001	16	15	Empty	Surplus
2021/05/07	ST00002	16	-5	Empty	Shortage
2021/06/25	PU000007	12	3	Russell	4562
2022/02/28	ST00004	16	5	Empty	Auto correction
2021/06/26	SR000004	13	-3	Russell	4562-A
2022/02/28	ST00006	16	1	Empty	Surplus
2022/02/28	ST00007	16	-1	Empty	Shortage
2022/02/28	SA00003	19	-2	Empty	Assemble BOM (P
2022/02/28	SA00004	18	2	Empty	Disassemble BOM

The Types column on the report, is as follows:

Type	*Description*	*+ Increase Quantities* *- Decrease Quantities*
10	*Invoice*	-
11	*Credit note*	+
12	*Purchase*	+

13	*Supplier return*	*-*	
14	*Quote*		*Not applicable to this report*
15	*Order*		*Not applicable to this report*
16	*Stock adjustments*	*+ Surplus* *- Shortage* *+ / - Auto correction*	*ST00001, etc. - Document numbers - Auto prefixed with ST followed by seven (7) numerical digits.* *Stock adjustments - Remarks entered in the "Change remarks" screen (e.g. Surplus / Shortage or Auto correction).*
17	*Stock in / Stock+*	*Stock+*	*SI00001, etc. - Document numbers - Auto prefixed with SI followed by seven (7) numerical digits.*
18	*Disassemble - BOM (Production)*	*+*	*BOM (Production) stock item type - Disassemble option on context menu.* *SA00001, etc. - Document numbers - Auto prefixed with SA followed by seven (7) numerical digits.*
19	*Assemble - BOM (Production)*	*-*	*BOM (Production) stock item type - Assemble option on context menu.* *SA00001, etc. - Document numbers - Auto prefixed with SA followed by seven (7) numerical digits.*

Report button

Prints the report for all stock items.



Transaction details

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com

Stock - Transaction details - Grid

Code	Description				Quantities	Disabled
3COMP	Compressor				5	No
Date	*Document no.*	*Type*	*Quantity*	*Salesperson*	*Document reference*	
2021/04/06	PU000004	12	2	Russell	3532	
2021/04/09	IN000006	10	-2	Tracy	C-102	
2021/04/10	IN000007	10	-1	Russell	C-103	
2021/06/07	IN000012	10	-2	Tracy	C-102	
2021/06/10	IN000013	10	-1	Russell	C-103	
2021/06/17	IN000016	10	-2	Tracy	C-102	
2021/06/20	IN000017	10	-1	Russell	C-103	
2021/06/30	IN000019	10	-2	Tracy	D-101	
2021/06/30	IN000020	10	-2	Russell	A-103-2	
2021/06/09	PU000006	12	2	Russell	3532	
2021/06/24	SR000001	13	-2	Russell	3532	
2021/06/30	CR000001	11	2	Tracy	D-101	
2021/06/30	CR000003	11	1	Russell	C-103	
2021/06/03	ST00003	16	9	Empty	Surplus	
2022/02/28	SA00003	19	-2	Empty	Assemble BOM (P	
2022/02/28	SA00004	18	2	Empty	Disassemble BOM	
2022/02/28	ST00008	16	1	Empty	Surplus	
2022/02/28	ST00009	16	-1	Empty	Shortage	
3DRILL	Drill press				10	No
Date	*Document no.*	*Type*	*Quantity*	*Salesperson*	*Document reference*	
2021/04/05	PU000003	12	3	Russell	4562	
2021/04/07	IN000005	10	-1	Tracy	D-101	
2021/04/11	IN000008	10	-2	Tracy	D-102	
2021/05/08	IN000010	10	-1	Russell		
2021/06/05	IN000011	10	-1	Tracy	D-101	
2021/06/12	IN000014	10	-2	Tracy	D-102	
2021/06/15	IN000015	10	-1	Tracy	D-101	
2021/06/20	IN000017	10	-1	Russell	C-103	
2021/06/24	IN000018	10	-2	Tracy	D-102	
2021/06/30	IN000019	10	-2	Tracy	D-101	
2021/06/30	IN000020	10	-2	Russell	A-103-2	

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Print single item - Value stock account

Value stock account - Stock grid reports

The "*Value stock account*" report lists the total value of the stock control account. If the "*Show details*" option is selected, it will list the the value of the selected stock item.

Value stock account options



Print single item (context menu)

Parameter - "*Show detail*" leave blank to print the only the total of the selected stock item.

Parameter - "*Show detail*" select to print the stock item code, item description, quantities and the total value of the selected stock item.



Prints directly to the Reportman preview screen.

Print single item (no detail)



Print single item (show detail)



Report button

Parameter - "*Show detail*" leave blank to print the only the total of all stock items.

Parameter - "*Show detail*" select to print the stock item code, item description, quantities and the total value of all stock items.



Report button (no detail)



Report button (show detail)



Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Print single item - Price list - Large retail - Sales

Price agreement - Stock grid reports

Price agreement plugin - *Manual* - *Shop* - *Licence : Once-off -*

Price list - Large retail - Sales

The "*Price list - Large retail - Sales*" report will list quantity discount up to five (5) price levels of a selected stock item for a selected debtor (customer / client) account.

Price list - Large retail - Sales options



Report button on Sidebar



Select the debtor (customer / client) account.

Enter the quantities (up to 5 levels).



Code	Description	Price1	Price5	Price10	Price15	Price20	Disabled
3COMP	Compressor	1500,00	1450,00	1400,00	1350,00	1300,00	No
3DRILL	Drill press	1000,00	950,00	900,00	850,00	800,00	No
4L-INSTCUP	Install - Built-in cupboards	500,00	500,00	500,00	500,00	500,00	No
4L-PAINT-E	Paint - Exterior	500,00	500,00	500,00	500,00	500,00	No
BOM	BOM	0,00	0,00	0,00	0,00	0,00	No
BOMPRODUCTION	BOM (Production)	0,00	0,00	0,00	0,00	0,00	No
GL-CODE	General ledger	0,00	0,00	0,00	0,00	0,00	No
OPTIONITEM	Option item	0,00	0,00	0,00	0,00	0,00	No
OPTIONITEM-NS	Option item (no stock)	0,00	0,00	0,00	0,00	0,00	No
PURCHASES	Purchases	0,00	0,00	0,00	0,00	0,00	No
PURCHASES-NS	Purchases (no stock)	0,00	0,00	0,00	0,00	0,00	No
SALES	Sales	0,00	0,00	0,00	0,00	0,00	No
SALES-NS	Sales (no stock)	0,00	0,00	0,00	0,00	0,00	No

Print single item on context menu

Right-click on a selected stock item (product).

Select the debtor (customer / client) account.

Enter the quantities (up to 5 levels).



Prints directly to the Reportman preview screen.

Price agreement reports (Reports menu)

You may print lists of the price agreements.

Print Price agreements for Debtors (Customers / Clients)

To print Price agreement reports for debtors (customers / clients):

1. On the Reports ribbon, select Reports → Plugins → Price agreement.
2. Select the "*Debtor - Price agreement*" report (default option).



3. Select the debtor (customer / client) account or creditor (supplier / vendor) account.

4. Enter up to 5 quantities.

5. Click on the OK button.

An example of the "*Debtor Price agreement*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Print single item - Price list - Large retail - Purchases

Price agreement - Stock grid reports

Price agreement plugin - *Manual* - *Shop* - *Licence : Once-off* -

Price list - Large retail - Purchases

The "*Price list - Large retail - Purchases*" report will list quantity discount up to five (5) price levels of a selected stock item for a selected creditor (supplier / vendor) account.

Price list - Large retail - Purchases options



Report button on Sidebar



Select the creditor (supplier / vendor) account.

Enter the quantities (up to 5 levels).



Code	Description	Price1	Price5	Price10	Price15	Price20	Disabled
3COMP	Compressor	1000,00	1000,00	1000,00	1000,00	1000,00	No
3DRILL	Drill press	1000,00	1000,00	950,00	900,00	850,00	No
4L-INSTCUP	Install - Built-in cupboards	0,00	0,00	0,00	0,00	0,00	No
4L-PAINT-E	Paint - Exterior	0,00	0,00	0,00	0,00	0,00	No
BOM	BOM	0,00	0,00	0,00	0,00	0,00	No
BOMPRODUCTION	BOM (Production)	0,00	0,00	0,00	0,00	0,00	No
GL-CODE	General ledger	0,00	0,00	0,00	0,00	0,00	No
OPTIONITEM	Option item	0,00	0,00	0,00	0,00	0,00	No
OPTIONITEM-NS	Option item (no stock)	0,00	0,00	0,00	0,00	0,00	No
PURCHASES	Purchases	0,00	0,00	0,00	0,00	0,00	No
PURCHASES-NS	Purchases (no stock)	0,00	0,00	0,00	0,00	0,00	No
SALES	Sales	0,00	0,00	0,00	0,00	0,00	No
SALES-NS	Sales (no stock)	0,00	0,00	0,00	0,00	0,00	No

Print single item on context menu

Right-click on a selected stock item (product).

Select the creditor (supplier / vendor) account.

Enter the quantities (up to 5 levels).



Prints directly to the Reportman preview screen.



Price agreement reports (Reports menu)

You may print lists of the price agreements.

Print Price agreements for Creditors (Suppliers / Vendors)

To print Price agreement reports for creditors (suppliers / vendors):

1. On the Reports ribbon, select Reports → Plugins → Price agreement.
2. The "*Debtor - Price agreement*" is the default option. Select the "*Creditor - Price agreement*" report.



3. Select the creditor (supplier / vendor) account.
4. Enter up to 5 quantities.

5. Click on the OK button.

An example of the "*Creditor Price agreement*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

Set Stock reporting group 1/2

You may change the Stock group 1 and/or Stock group 2 for selected stock item(s).

To change the Stock group 1 or Stock group 2:

1. On the Default ribbon, select Stock items. Select the stock item(s), right-click on Stock group 1 or Stock group 2 context menu.

2. Select empty or the available Stock group from the sub-menu. The Stock group 1 or 2 will change on the reports.

Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Copy / Paste

You may copy the specific data of a selected stock item and paste (replace) the data of selected stock item(s).

To copy and paste data from a stock item to other stock item(s):

1. On the Default ribbon, select Stock items.
2. Select the stock item, from which you need to copy data.
3. Right-click and select the "*Copy from / init*" (initiate) option on the context menu.
4. Select the stock item(s) to which you wish to paste the data.

> *If you need to select multiple stock items, press the Ctrl or Shift key and click on each stock item, for which you need to paste (replace) the selected data.*

5. Right-click and select the "*Paste to / init*" (initiate) option on the context menu.



> *Stock item - This option is another option to the Copy from item button. This will launch a new Stock item edit form with the data of the selected source stock item. You need to enter a stock code and edit the copied stock item, where necessary.*

Copy / Paste Supplier 1

The preferred supplier 1 account as selected on the selected source stock item will be copied to (replace) the "*Preferred supplier 1*" field of the selected stock item(s).



When the "*Paste to / init*" (initiate) option on the context menu, is selected, A confirmation message will be displayed:

> Replace old data for &Supplier 1?



The Supplier stock code for preferred supplier 1 will not be copied (replaced).

Copy / Paste Ledger and Tax

The Tax class, Tax (Input tax and Output tax) and Ledger (Sales account, Cost of sales and Stock control) accounts as set on the Ledger tab of the selected source stock item will be copied to (replace) the Tax class and Input tax Output tax and Ledger accounts of the selected stock item(s).

When the "*Paste to / init*" (initiate) option on the context menu, is selected, a confirmation message is displayed:

> Replace old data for &Ledger and tax?



Copy / Paste Multi-group

The reporting groups as set on the Multi-group tab of the selected source stock item will be copied to (replace) the groups of the selected stock item(s).

When the "*Paste to / init*" (initiate) option on the context menu, is selected, a confirmation message is displayed:

> Replace old data for M&ulti-group copy?



Copy / Paste Active stock

To be advised.

When the "*Paste to / init*" (initiate) option on the context menu, is selected, a confirmation message is displayed:

> Replace old data for &Active stock?

Extra convert to languages

To be advised.

For this option, the Languages needs to be added in Groups (Setup ribbon). These languages can be selected in the "*Language*" field on Access control (Standard security tab) on the Setup ribbon. It will add a Languages tab on the Stock items (Default ribbon).

When the "*Paste to / init*" (initiate) option on the context menu, is selected, a confirmation message is displayed:

```
Replace old data for &Extra convert to languages?
```

Dummy price

Copy Dummy price produce the following SQL error:

```
Dynamic SQL Error
SQL error code = -204
Table unknown
STOCK_EXTRADATA
At line 1, column 39
Select FDUMMYQTY from STOCK_EXTRADATA where WStockid = 4
```

Mark copy

Copy Mark copy produce the following SQL error:

```
Dynamic SQL Error
SQL error code = -204
Table unknown
STOCK_EXTRADATA
At line 1, column 37
Select WMERKID from STOCK_EXTRADATA where WStockid = 4
```

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Mass check

This option will run a check on all stock items.

This process may take some time.

To do a mass check on stock items:

1. On the Default ribbon, select Stock items.
2. Select "*Mass check*" option on the context menu.
3. The stock item form will be automatically opened and closed for each stock item.
4. When the mass check process is finished, a confirmation message is displayed:

   "Check finished:"

5. Click OK.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Copy from a Stock item

This option will open a Stock screen with the necessary data from a selected Stock item. Before you can create the new Stock item with the copied data, you need to at least enter a Stock code and Save it. You may enter and/or select the options for the blank fields, as necessary. If necessary you may also edit or change any of the copied data.

The data that will be copied from a selected Stock item, may depend on the on the Stock item type.

To create a new stock item - Copy from item:

1. On the Default ribbon, select Stock items (F12).
2. Select the Stock item from the list.
3. Make absolutely sure that it is the correct Stock item to be copied.

To view more details of the selected Stock item, you may:

- *Click on the Edit button - or double-click on the selected stock item.*

- *Use the horizontal scroll bar to view the data of the selected stock items in columns.*

4. Click on the Copy from item button.

You may right-click and select the Copy → Stock item from the context menu.

The Stock item screen with basically all the data from the selected Stock item screen will be displayed as follows:



5. Enter the new Stock code.

6. Enter the necessary details in the fields, as required. You may also edit the copied data, where necessary.

7. Click on the Save button to save this stock item.

It copy the following fields :

- *Stock description*
- *Barcode*
- *Manufacturer*

- *Extra description*
- *Expected quantity (values will be set to 0 (zero)*
- *Type (You need to select the stock item type)*
- *Units*
- *Apply invoice discount (tick)*
- *Stock group 1*
- *Stock group 2*
- *Preferred supplier 1 account and stock code.*
- *Preferred supplier 2 account and stock code.*
- *Ledger*
    - *Tax classes (Sales account / Cost of sales account / Stock control account)*
    - *Weight (Net and Gross)*
    - *Selling prices 1/2/3*
    - *Latest cost*
    - *Reorder level*
    - *Reorder at*
    - *Minimum*

What it does not copy:

- *Stock code*
- *Ledger*
    - *Average cost*
    - *Total cost*
    - *Quantity on hand*
    - *Last invoice*
- *Document groups*

- *Transactions*
- *Image (does not copy the correct image but the default image)*
- *Multigroup*
- *Descriptions (Language) (copies the groups but not the Descriptions and the text).*

Created with the Standard Edition of HelpNDoc: Maximize Your PDF Protection with These Simple Steps

Adjust stock menu

The stock item screen may also be launched from Stock items on the Default ribbon.

To access the Stock item - Adjustments:

1. On the Default ribbon, select Input → Adjust stock. The "*Stock item*" floating screen is displayed:



Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

Stock items edit form

The stock entry form is basically similar for all stock items (inventory items) for all stock item types. Depending on the selected stock item type, some fields on the Ledger tab, may be disabled and some fields may be hidden.

For some stock item types, additional tabs may be added, e.g. Option items, BOM and Linked items.

When you process documents, you need to select a stock item.

The document type for Sales documents (Quotes, Invoices and Credit notes) and for Purchase documents (Orders, Purchases and Supplier returns) will list only specific stock item types in the stock item lookup.

To edit stock items:

1. On the Default ribbon, select Stock items (F12).

2. Select a stock item and click on the Edit button.

> *You may also double click on a selected stock item to open the stock item form.*



3. Enter and select the following:

   a) Stock code - Enter any code for your purchase stock item. You may enter a stock code of up to 15 characters.

   > *You need to plan the Stock item codes to optimise this facility in .*

   b) Description - Enter a description for the purchase stock item.

c) Barcode - Enter the barcode, if applicable.

> *The EAN13 Barcode validates for 13 numbers (the last number is a checksum number). If the Barcode is incorrect, the labels will not be printed.*

d) Manufacturer - You may enter any additional information or description of the manufacturer (e.g. the name of the manufacturer). This is optional.

e) Type - Default is the default stock item type.

> *The default stock item type is recommended for trading stock. If it is not trading stock, you may select one of the following stock types:*
>
> - *Financial entry*
> - *Sales*
> - *Sales (no stock)*
> - *Purchases*
> - *Purchases (no stock)*
>
> *In addition to the above-mentioned stock types, you may also select the following stock types:*
>
> - *Options*
> - *Option item*
> - *Option item (no stock)*
> - *Bill of Materials (BOM)*
> - *BOM*
> - *BOM (Production)*
> - *Linked Sale*

> *Once a transaction has been processed for a stock item, this field will be disabled.*

f) Unit size - Leave blank or select any unit e.g. each, hours, boxes, etc., which you wish to be displayed on your purchase documents. These Units of your Stock items such as: each, hours, boxes, etc., are setup in Setup →Stock information.

g) Disabled - By default, all Stock items are active (enabled) when Stock items are created or edited. Select this field if you (or any of your salespersons) do not want to process any documents for a Service Stock item. Select this field to hide the Stock item from the Stock item lookup when processing new documents. This will speed up document processing.

You will still be able to update (post) any unposted documents, which include transactions for the disabled Stock item, to the ledger.

You may select the disabled Stock items on the Stock item lookup when generating Stock, Sales analysis and Purchase analysis reports and view the transactions of disabled Stock items.

You may de-select this field at any stage, when necessary to continue processing documents for the Stock item.

h) Apply invoice discount - Do not select. This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab - Default → Debtors.

i) Extra description - You may enter any additional information or description (up to 255 characters) for the stock item, as necessary. This is optional.

j) Reports - Groups 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

The description of Stock group 1 or 2 you have entered on the "Reporting group name" field on the Stock groups tab on Setup → Groups may be reflected in this list.

k) Preferred supplier 1 - The main creditor (supplier / vendor) you purchase stock items from, may be selected. You may enter the supplier's stock code, if applicable.

l) Preferred supplier 2 - If you have a backup or alternative supplier, you may select the creditor (supplier / vendor) and enter the supplier's stock code, if applicable.

4. Click on the Ledger tab, if not already displayed.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Stock items - Ledger tab

The Ledger tab is used to link the stock item (inventory item) to accounts, specify sales prices and values (costs and number of items).

The Ledger tab, is the default tab when selecting a stock item (inventory item).

Click on the Ledger tab, if not already displayed.



The options, is as follows:

1. Tax

    a) Output Tax - Select the Output VAT/GST/Sales Tax account which you will use for your Sales.

    b) Input Tax - Select the Input VAT/GST/Sales Tax account which you will use for your Purchases. If this is a Zero-rated Stock item which is exempted from VAT/GST/Sales Tax, select the Input Zero Rated Tax Code.

> *If you are not registered for VAT/GST/Sales Tax, or if VAT/GST/Sales Tax is not applicable to this purchase item, select the "Empty" option as the "No Tax" code and this field will be blank.*

> *You may activate the Use default tax - Stock file override settings on the Creditors (Accounting information tab (Default ribbon)) for a Creditor (supplier / vendor) account, and select a different VAT/GST/Sales Tax account or code on the Tax lookup facility for that creditor (supplier / vendor).*
>
> *When purchase documents or supplier returns documents for the creditor (supplier / vendor) is updated (posted) to the ledger, the selected Input Tax account for this Stock item will be ignored and the purchase transaction will be updated (posted) to the specified Input Tax account for the creditor (supplier / vendor).*

2. Weight

    c) Gross weight -

    d) Net weight -

3. Ledger

    a) Sales - Select the applicable Purchase account from the lookup.

    If you have more than one Sales account, or use Sub-accounts, you may select the applicable Account or Sub-account for each of your Stock items.

    b) Cost of sales - Select the applicable Purchase account from the lookup.

    If you have more than one Cost of sales account, or use Sub-accounts, you may select the applicable Account or Sub-account for each of your Stock items.

    c) Stock control - Select the Stock control account from the lookup. This may be an Expense account, for example, stationery, if stationery is purchased.

    If you have more than one Purchase account, or use Sub-accounts, you need to select the applicable Account or Sub-account for the Purchase Item.

    You may activate the Use default account - Stock file override settings on the Creditors (Accounting information tab (Default ribbon)) for a Creditor (supplier / vendor) account, and select a different account on the Tax lookup facility for that creditor (supplier / vendor).

    When purchase documents or supplier returns documents for the creditor (supplier / vendor) is updated (posted) to the ledger, the selected Stock control and Cost of sales account for this Stock item will be ignored and the purchase transaction will be updated (posted) to the specified Input Tax account for the creditor (supplier / vendor).

    d) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

4. Values

e) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage. When you process purchases, the Average cost Price will be automatically updated.

f) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage. When you process purchases, the Total cost price will be automatically updated.

g) Latest cost - The latest cost price of your Stock item can now be entered. When you process purchases, the Latest cost Price will be automatically updated.

> *Once you have created your new Stock items, you may enter the cost prices and quantities in the Stock take-on option of Stock items (Default ribbon) (or the Adjust stock tab of the Stock item selection screen), if you have any Stock item records on a previous accounting system.*

h) Quantity on hand - The quantity, or number of Stock items on hand, can be entered at this stage. When do the stock take-on (for trading stock - default stock item type), or process purchases, the quantities will be automatically updated.

i) Reorder level - Enter the reorder quantity level.

j) Reorder at - Enter the quantity level when you need to reorder.

k) Minimum - Enter the minimum quantity of stock items on hand before reordering.

l) Delivery delay - To be advised.

5. Click on the Save button to save this stock item.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Stock items - Document groups tab

This will list all sales documents (i.e. Invoices, Point-of-Sale Invoices, Credit notes and Quotes) as well as any purchase documents (Purchases, Supplier returns and Orders) on which the stock item was selected.

These will only include documents, which have been updated (posted) to the ledger. Only Quotes which have been converted to Invoices and Orders which have been converted to Purchase documents, will be listed.



Date	Items	Document no.	Description	Price	Discount	Exclusive	Inclusive	Unit price	Units	Description	Number	Name	Document type	Posted
2021/06/30	2	IN000021	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ABGRE	Mr. AB Green	Invoice	0
2021/06/30	2	IN000022	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ABGRE	Mr. AB Green	Invoice	0
2021/06/30	2	IN000020	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ABGRE	Mr. AB Green	Invoice	1
2021/06/30	2	IN000019	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ABGRE	Mr. AB Green	Invoice	1
2021/06/30	1	CR000003	Compressor	1500.00	0	1500.00	1725.00	1500.00	1	Each	1ABGRE	Mr. AB Green	Credit notes	1
2021/06/30	2	CR000001	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ABGRE	Mr. AB Green	Credit notes	1
2021/06/24	2	QU000005	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ABGRE	Mr. AB Green	Quotes	0
2021/06/24	2	SR000001	Compressor	1000.00	0	2000.00	2300.00	1000.00	1	Each	2BESTS	BEST Suppliers	Purchases	1
2021/06/20	1	IN000017	Compressor	1500.00	0	1500.00	1725.00	1500.00	1	Each	1MDAVI	Mr. Mike Davies	Invoice	1
2021/06/17	2	IN000016	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ROGSM	Mr. Roger Smith	Invoice	1
2021/06/10	1	IN000013	Compressor	1500.00	0	1500.00	1725.00	1500.00	1	Each	1MDAVI	Mr. Mike Davies	Invoice	1
2021/06/09	2	PU000006	Compressor	1000.00	0	2000.00	2300.00	1000.00	1	Each	2AONES	A-ONE Suppliers	Purchases	1
2021/06/07	2	IN000012	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ROGSM	Mr. Roger Smith	Invoice	1
2021/06/03	-9	ST00003	Surplus	0.00				0.00				Empty	Stock-	1
2021/04/10	1	IN000007	Compressor	1500.00	0	1500.00	1725.00	1500.00	1	Each	1MDAVI	Mr. Mike Davies	Invoice	1
2021/04/09	2	IN000006	Compressor	1500.00	0	3000.00	3450.00	1500.00	1	Each	1ROGSM	Mr. Roger Smith	Invoice	1
2021/04/06	2	PU000004	Compressor	1000.00	0	2000.00	2300.00	1000.00	1	Each	2BESTS	BEST Suppliers	Purchases	1
17	19.00					39,000.00	44,850.00							

The document numbers for Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders, as prefixed in the Documents setup (Setup ribbon), makes it easy to identify the document type.

In addition to these standard document numbers, the following documents may be included:

- *Stock adjustments - Document numbers prefixed with "ST" is a 7-digit document number. These are automatically generated when doing stock adjustments (changes in the quantities on hand). These stock adjustments does not show any transactions and it prints a blank Posted batch type reports.*
- *BOM (Production) stock type - Assemble / Disassemble context menu options - Document numbers prefixed with"SA" will be a 7-digit number.*
- *Project Quote - Document numbers prefixed with"D" will be a 7-digit number.*

You may double-click on a selected document to print the selected document.

You may use the context menu (right-click) to open selected document(s).



Unposted document = 0. This will open the unposted document form, which may be viewed and may be edited.

Posted documents = 1. This will open the posted document form, which may be viewed but cannot be edited.

You may click on the column headings to change the sort sequence from the ascending to the descending sequence.

You may also click and drag any of the column headings to the left or right to change the sequence in which

the columns are to be displayed.

The columns are as follows:

1. Date – The date on which the documents are generated and updated (posted) to the ledger.
2. Items – This displays the number of items quantities as specified in the Quantity Ship field of document lines.
3. Document no. - The document number as automatically generated.

If document numbers were not prefixed for each document type, with IN, CR, QU, PU, SR and OR, it would virtually be impossible to identify the correct document type.

4. Description – The description (name) of the Stock item.
5. Price – The price is as follows:
    a) Cost price of each item (Exclusive of Input Tax) for purchase documents (i.e. Purchases, Supplier returns and Orders).
    b) Selling price of each item (Exclusive of Output Tax) for sales documents (i.e. Invoices, Point-of-Sale Invoices and Credit notes).
6. Discount – The discount percentage as entered in the discount column for the stock item.
7. Unit Price – The price is as follows:
    a) Cost price of each item (Exclusive of Input Tax) for purchase documents (i.e. Purchases, Supplier returns and Orders).
    b) Selling price of each item (Exclusive of Output Tax) for sales documents (i.e. Invoices, Point-of-Sale Invoices and Credit notes).The cost price of each item (Exclusive of Input Tax).
8. Exclusive – The selling price (for sales documents) exclusive of Output Tax or the purchase price (for purchase documents) exclusive of Input Tax for the number of items (unit price x quantity) minus the discount amount.
9. Inclusive - The selling price (for sales documents) inclusive of Output Tax or the purchase price (for purchase documents) inclusive of Input Tax for the number of items (unit price x quantity) minus the discount amount.
10. Posted - 1 = Posted and Unposted = 0.

You may use the context menu (right-click) to open selected document(s).

You may use the context menu (right-click) to open selected document(s).



Unposted document = 0. This will open the unposted document form, which may be viewed and may be edited.

Posted documents = 1. This will open the posted document form, which may be viewed but cannot be edited.

If document numbers were not prefixed for each document type, with IN, CR, PU and SR it would virtually be impossible to identify the correct document type.

Selling prices 1 / 2 / 3 as selected on sales documents. If not selected on sales documents, these will automatically be used from the following settings:

- *Global Setting – The Default selling price as selected in Setup → Stock information.*
- *The Selling price as selected on the Accounting information tab of a selected Debtor account.*

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Stock items - Transactions tab

This will list all posted sales documents (i.e. Invoices, Point-of-Sale Invoices and Credit notes) as well as any posted purchase documents (Purchases and Supplier returns) on which the stock item was selected.

These will only include documents, which have been updated (posted) to the ledger. Quotes and Orders will not be listed.



Date	Items	Cost price	Selling price	Document row	Document no.	Reference	User	Cum	id	Posted	Document type
2021/04/06	2	1,000.00	1,000.00	0	PU000004	3532		6	12	1	Purchases
2021/04/09	-2	1,000.00	1,500.00	0	IN000006	C-102		4	14	1	Invoice
2021/04/10	-1	1,000.00	1,500.00	0	IN000007	C-103		3	15	1	Invoice
2021/06/03	9	0.00	1,000.00	1	ST00003	Surplus		12	45	1	Stock-
2021/06/07	-2	1,000.00	1,500.00	0	IN000012	C-102		10	19	1	Invoice
2021/06/09	2	1,000.00	1,000.00	0	PU000006	3532		12	34	1	Purchases
2021/06/10	-1	1,000.00	1,500.00	0	IN000013	C-103		11	20	1	Invoice
2021/06/17	-2	1,000.00	1,500.00	0	IN000016	C-102		9	23	1	Invoice
2021/06/20	-1	1,000.00	1,500.00	0	IN000017	C-103		8	24	1	Invoice
2021/06/24	-2	1,000.00	1,000.00	0	SR000001	3532		6	35	1	Purchases
2021/06/29	2	1,000.00	1,500.00	1	CR000001	D-101		8	39	1	Credit notes
2021/06/30	1	1,000.00	1,500.00	0	CR000003	C-103		9	41	1	Credit notes
2021/06/30	-2	1,000.00	1,500.00	1	IN000019	D-101		7	28	1	Invoice
2021/06/30	-2	1,000.00	1,500.00	0	IN000020	A-103-2		5	29	1	Invoice

14 1

The document numbers for Invoices, Credit notes, Purchases and Supplier returns, as prefixed in the Documents setup (Setup ribbon), makes it easy to identify the document type.

In addition to these standard document numbers, the following documents may be included:

- *Stock adjustments - Document numbers prefixed with "ST" is a 7-digit document number. These are automatically generated when doing stock adjustments (changes in the quantities on hand). These stock adjustments does not show any transactions and it prints a blank Posted batch type reports.*
- *BOM (Production) stock type - Assemble / Disassemble context menu options - Document numbers prefixed with"SA" will be a 7-digit number.*
- *Project Quote - Document numbers prefixed with"D" will be a 7-digit number.*

You may use the context menu (right-click) to open selected document(s).



Posted documents = 1. This will open the posted document form, which may be viewed but cannot be edited.

You may click on the column headings to change the sort sequence from the ascending to the descending sequence.

You may also click and drag any of the column headings to the left or right to change the sequence in which the columns are to be displayed.

The columns are as follows:

1. Date – The date on which the documents are generated and updated (posted) to the ledger.
2. Items – This displays the number of items quantities as specified in the Quantity Ship field of document lines.
    a) Positive Quantities - Purchases and Credit notes – (Stock In).
    b) Negative Quantities – Invoices and Supplier returns (Stock Out).
3. Cost price – The cost price of each item (Exclusive of Input Tax).

In the case of Purchases and Supplier returns, the cost price and selling price will be the same.

4. Selling price – The selling price of each item (Exclusive of Output Tax).

In the case of Purchases and Supplier returns, the cost price and selling price will be the same.

5. Document row - To be advised.
6. Document no. - The document number as automatically generated.

If document numbers were not prefixed for each document type, with IN, CR, PU and SR it would virtually be impossible to identify the correct document type.

Selling prices 1 / 2 / 3 as selected on sales documents. If not selected on sales documents, these will automatically be used from the following settings:

- *Global Setting – The Default selling price as selected in Setup → Stock information.*
- *The Selling price as selected on the Accounting information tab of a selected Debtor account (Debtors (Default ribbon)).*

7. Reference - The reference number as added in the "*Your reference*" field of the document.
8. User - The name of the User if added in Setup → Access control (Setup ribbon).
9. Cumulative - The cumulative quantities
10. Posted - Value = 1 - The document is posted (updated) to the ledger.
11. Document type - Invoices, Credit notes, Purchases and Supplier returns.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Stock items - Image tab

You may add or delete an image for the stock item. This image will be available to display on the Button lookup mode, when processing sales documents (i.e. Invoices, Credit notes, Quotes and Point-of-Sales Invoices) as well as purchase documents (i.e. Purchases, Supplier returns and Orders).

You may add or delete an image for the stock item. This image will display on the following screens:

- Lookup Stock items - *Button lookup* mode, when processing sales documents (i.e. Invoices, Credit notes, Quotes and Point-of-Sales Invoices) as well as purchase documents (i.e. Purchases, Supplier returns and Orders).
- Stock item List screen - When selecting or scrolling on the list of stock items, it will display at the bottom left of the Side bar.

Add images

To select an image for a Stock item:

1. Go to Stock items and select a Stock item from the list.
2. Click on the Images tab.



3. Click on the Select Image button. The "*Open"* screen is displayed:



4. Select an image and click on the Open button.

5. Click Save.

*Images need to be in the *.jpg, *.jpeg, *.bmp or *.png file formats.*

After loading the Images, you need to Save the Stock item before the image will be displayed on the sidebar of the Stock item.

Delete images

To delete an image:

1. Click on the Delete button.

2. A confirmation message is displayed:

   "Do you wish to delete this image?"

3. Click OK.

Button lookup

To enable (activate) the Button lookup:

1. On the Setup ribbon, select Stock information menu.
2. Select (tick) the "*Button lookup*" field.
3. Click on the OK button. The Button lookup screen is displayed when selecting stock items while processing documents.

The default size of images is 120px width x 40px height. You may change the size of the buttons in Plugins → Point-of-Sale → HorecaPOS (Setup ribbon).

Groups - Images and colours

The Button lookup may be configured by adding images of your product groups and setting colours (background and font) in Setup → Groups (Stock group 1).

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Stock items - Multi-group tab

This option allows you to set multiple groups to the selected stock item. The main Reporting group 1 (Stock group 1) is selected on the Reports Reporting group 1 section of the Edit Stock screen. The same list of the available Reporting group 1 (Setup → Groups (Stock group 1)) will be listed and may also be linked to the stock item.



Created with the Standard Edition of HelpNDoc: Elevate Your Help Documentation with a Help Authoring Tool

Stock items - Backorders tab

When processing invoices in Documents (Default ribbon), and the debtor (customer / client) orders more than is actually invoiced, it will be recorded in the backorder facility.

Backorder records and reports will only be updated when the Invoices are posted (updated) to the ledger.

An example where the quantity entered in the "*Qty Order*" field is more than the quantity entered in the "*Qty Ship*" field, is as follows:

You may also click on the Backorder icon to edit backorders when processing invoices and quotes.

The insufficient quantities (e.g. 10 – 2 = 8, as per this example) will be added to the backorder feature. The following options, on the Default ribbon, are available to manage (view / add / edit / delete) backorders:

1. Stock items (Backorders tab) – List of backorders for the selected stock item.
2. Debtors (Backorders tab) – List of backorders for the selected debtor (customer / client) account.
3. Input → Backorders Outstanding – List of backorders for all stock items.

The Backorder report may be printed in Reports → Stock → Backorder (Reports ribbon). This will launch the Backorders options screen on which you may select the range of Stock items to include / exclude from the report.



Sorting and Rearranging Columns:

- *You can click on the column headings (such as Stock item, Description, Unit, Items, Discount, Stock, Referral source, Selling price, Price, and Exp. Selected) to change the sort sequence from ascending to*

descending order.

- *To rearrange the sequence in which the columns are displayed, you can click and drag any of the column headings to the left or right.*

Add / Edit Backorders



When processing Invoices and you select the Stock item on backorder, the invoicing screen, the Backorders Outstanding screen is displayed:



If you select this item, the entry will be removed from the backorder records and reports.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Use tabs for stock

By default, the Stock item screen for a selected stock item, will display the Ledger, Document groups, Image, Multi Groups and Backorders tabs below the Stock information section.



To change the interface of the Stock item screen:

1. On the Setup ribbon, select Stock information.

2. On the "*Stock information*" screen, deselect (remove the tick) in the "*Use tabs in stock*" field.



3. Click on the OK button. The Stock item screen for a selected Stock item will display a Data tab on which you may click + to expand (or - to collapse) the Stock information (Stock main form), Accounting (Ledger tab) and the Multigroup tabs. change as follows:



You may need to go to the Tools → Close active forms (Setup ribbon), to close the Stock item screen before the changes will take effect.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's HTML5 template

Create / Edit Stock item types

Default (Trading stock) stock type:

The entries for the Default (trading stock) stock item type is as follows:

Trading stock items (Default stock item type)			
Purchases (Purchase journal)		*Invoices (Sales journal)*	
DR	*Stock item (net cost price - Input Tax Excluded)*	*DR*	*Debtor (full amount - Output Tax Included)*

Trading stock items (Default stock item type)					
Purchases (Purchase journal)			*Invoices (Sales journal)*		
DR	*Input Tax (% of purchase price)*			*CR*	*Sales (selling price - Output Tax Excluded)*
	CR	*Creditor (full amount - Input Tax Included)*		*CR*	*Output Tax (% of selling price)*
			Cost of sales journal		
			DR		*Cost of sales (cost price)*
				CR	*Stock (cost price)*

The transactions for Supplier returns (Credit notes received from creditors (suppliers)) are exactly the opposite than those of purchase documents (Invoices received from creditors (suppliers)).

The transactions for Credit notes (issued to debtors (customers / clients)) are exactly the opposite than those of Invoices.

Trading stock items (Default stock item type)					
Supplier returns (Purchase journal)			*Credit notes (Sales journal)*		
DR	*Creditor (full amount - Input Tax Included)*		*DR*	*Sales (selling price - Output Tax Excluded)*	
	CR	*Stock item (net cost price - Input Tax Excluded)*	*DR*	*Output Tax (% of selling price)*	
	CR	*Input Tax (% of purchase price)*		*CR*	*Debtor (full amount - Output Tax Included)*
			Cost of sales journal		
			DR	*Stock (cost price)*	
				CR	*Cost of sales (cost price)*

All other stock types (excluding the Bills of Materials (BOM) stock item type), have no cost of sales transactions.

Other stock item types:

The transactions are similar to those as entered in the various batches. It is as follows:

Other stock item types					
Purchases (Purchase journal)			Invoices (Sales journal)		
DR	*Pre-set / selected purchase (expense or asset) account. (purchase price - Input Tax Excluded)*		*DR*	*Debtor (full amount - Output Tax Included)*	
DR	*Input Tax (% of purchase price)*		*CR*	*Sales / selected income account (selling price - Output Tax Excluded)*	
	CR	*Creditor (full amount - Input Tax Included)*	*CR*	*Output Tax (% of selling price)*	

The transactions for Supplier returns (Credit notes received from creditors (suppliers)) are exactly the opposite than those of purchase documents (Invoices received from creditors (suppliers)).

The transactions for Credit notes (issued to debtors (customers / clients)) are exactly the opposite than those of Invoices.

Other stock item types					
Supplier returns (Purchase journal)			*Credit notes (Sales journal)*		
DR	*Creditor (full amount - Input Tax Included)*		*DR*	*Sales / selected income account (selling price - Output Tax Excluded)*	
	CR	*Pre-set / selected purchase (expense or asset) account. (purchase price - Input Tax Excluded)*	*DR*	*Output Tax (% of selling price)*	
	CR	*Input Tax (% of purchase price)*	*CR*	*Debtor (full amount - Output Tax Included)*	

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Create / Edit Stock items - Trading stock - Default

The Default Stock item type is used for Trading stock items. The Cost of sales settings for these are important as these may have an impact on your gross profit.

To create a Default stock item:

1. On the Default ribbon, select Stock items (F12).

2. Click on the New button. A blank Stock form, "*Default*" stock item type is displayed:



3. Enter and select the following:

   a) Stock code - Enter any code for your purchase stock item. You may enter a stock code of up to 15 characters.

   > *You need to plan the Stock item codes to optimise this feature in osFinancials5/TurboCASH5.*

   b) Description - Enter a description for the purchase stock item.

   c) Barcode - Enter the barcode, if applicable.

   > *The EAN13 Barcode validates for 13 numbers (the last number is a checksum number). If the Barcode is incorrect, the labels will not be printed.*

   d) Manufacturer - You may enter any additional information or description of the manufacturer (e.g. the name of the manufacturer). This is optional.

   e) Type - Default is the default stock item type.

   > *The default stock item type is recommended for trading stock. If it is not trading stock, you may select one of the following stock types:*
   >
   > - *Financial entry*

- *Sales*
- *Sales (no stock)*
- *Purchases*
- *Purchases (no stock)*

In addition to the above-mentioned stock types, you may also select the following stock types:

- *Options*
  - *Option item*
  - *Option item (no stock)*
- *Bill of Materials (BOM)*
  - *BOM*
  - *BOM (Production)*
- *Linked Sale*

Once a transaction has been processed for a stock item, this field will be disabled.

f) Unit size - Leave blank or select any unit e.g. each, hours, boxes, etc. which you wish to be displayed on your purchase documents. These Units of your Stock items such as: each, hours, boxes, etc. are setup in Setup → Stock information.

g) Disabled - By default, all Stock items are active (enabled) when Stock items are created or edited. Select this field if you (or any of your salespersons) do not want to process any documents for a Service Stock item. Select this field to hide the Stock item from the Stock item lookup when processing new documents. This will speed up document processing.

You will still be able to update (post) any unposted documents, which include transactions for the disabled Stock item, to the ledger.

You may select the disabled Stock items on the Stock item lookup when generating Stock, Sales analysis and Purchase analysis reports and view the transactions of disabled Stock items.

You may de-select this field at any stage, when necessary to continue processing documents for the Stock item.

h) Apply invoice discount - Do not select. This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab.

i) Extra description - You may enter any additional information or description (up to 255 characters) for the stock item, as necessary. This is optional.

j) Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

The description of Stock group 1 or 2 you have entered on the "Reporting group name" field on the Stock groups tab - Setup → Groups may be reflected in this list.

k) Preferred supplier 1 - The main creditor (supplier / vendor) you purchase stock items from, may be selected. You may enter the supplier's stock code, if applicable.

l) Preferred supplier 2 - If you have a backup or alternative supplier, you may select the creditor (supplier / vendor) and enter the supplier's stock code, if applicable.

4. Click on the Ledger tab, if not already displayed.



5. Enter or select the following options:

a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

b) Last invoice - Field inactive. The date of the last purchase or other document generated on

which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

d) Weight

i) Gross weight - Enter, if applicable.

ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

This description should reflect your selling price descriptions as you have entered in Setup → Stock information.

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage. When you process purchases, the Average cost Price will be automatically updated.

ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage. When you process purchases, the Total cost price will be automatically updated.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage. When you process purchases, the quantities will be automatically updated.

iv) Latest cost - The latest cost price of your Stock item can now be entered. When you

process purchases, the Latest cost Price will be automatically updated.

Once you have created your new Stock items, you may enter the cost prices and quantities in the Stock take-on option in Stock items, if you have any Stock item records on a previous accounting system.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item. In the case of Stock item codes for the purchase of services, this field should be left blank.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

6. Click on the Save button to save this stock item. The "*Stock item"* grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Create / Edit Stock items - Sales

The disabled and inactive options for the Sales and the Sales (no stock) stock item type are the same. If you select this Sales or the Sales (no stock) stock item type on an invoice or a credit note, no Cost of sales transactions would be generated. You will also not be allowed to specify the re-order level and select the Cost of sales, Stock control and Input Tax accounts.

Should you need to generate invoices and credit notes to customers (debtors) for services, fees, charges or other sales which is not trading stock, you may create a Sales or Sales (no stock) stock item type. You may generate invoices and credit notes for these non trading stock items only or add these item codes to an invoice or credit note containing physical Stock items.

Some examples where you would create a Sales or Sales stock item type, is the following:

- Invoicing services such as labour, consulting fees, etc.
- Invoicing carting fees, delivery fees, other charges, etc.

To create a Stock item - Sales:

1. On the Default ribbon, select Stock items (F12).

2. Click on the New button. A blank Stock form will be displayed.

3. Select the "*Sales*" stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.

5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab.

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

8. Click on the Ledger tab, if not already displayed.



9. Enter or select the following options:

    a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

The Input Tax account field is disabled. The Cost of sales and Stock control account fields are disabled.

b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

d) Weight

i) Gross weight - Enter, if applicable.

ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

This description should reflect your selling price descriptions as you have entered in Setup →Stock Information.

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage. When you process purchases, the Average cost Price will be automatically updated.

ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage. When you process purchases, the Total cost price will be automatically updated.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage. When you process purchases, the quantities will be automatically updated.

iv) Latest cost - The latest cost price of your Stock item can now be entered. When you process purchases, the Latest cost Price will be automatically updated.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item. In the case of Stock item codes for the purchase of services, this field should be left blank.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

10. Click on the Save button to save this stock item. The "*Stock item*" grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Create / Edit Stock items - Sales (no stock)

The disabled and inactive options for the Sales and the Sales (no stock) stock item type is the same. If you select this Sales or the Sales (no stock) stock item type on an invoice or a credit note, no Cost of sales transactions would be generated. You will also not be allowed to specify the re-order level and select the Cost of sales, Stock control and Input Tax accounts.

Should you need to generate invoices and credit notes to customers (debtors) for services, fees, charges or other sales which is not trading stock, you may create a Sales or Sales (no stock) stock item type. You may generate invoices and credit notes for these non trading Stock items only or add these item codes to an invoice or credit note containing physical Stock items.

Some examples where you would create a Sales or Sales (no stock) stock item type, is the following:

- Invoicing services such as labour, consulting fees, etc.
- Invoicing carting fees, delivery fees, other charges, etc.

To create a stock item - Sales (no stock):

1. On the Default ribbon, select Stock items (F12).

2. Click on the New button. A blank Stock form will be displayed.

3. Select the "*Sales (no stock)*" stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.

5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab - Debtors (Default ribbon).

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

8. Click on the Ledger tab, if not already displayed.



9. Enter or select the following options:

    a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

The Input Tax account field is disabled. The Cost of sales and Stock control account fields are disabled.

b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

d) Weight

i) Gross weight - Enter, if applicable.

ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

This description should reflect your selling price descriptions as you have entered in Setup →Stock information.

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage.

ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage.

iv) Latest cost - The latest cost price of your Stock item can now be entered.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

10. Click on the Save button to save this stock item. The "*Stock item"* grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Create / Edit Stock items - Purchases

The disabled and inactive options for the Purchase and the Purchase (no stock) stock item type are the same. If you select this Purchase or the Purchase (no stock) stock item type on a purchase document or a supplier return document, no Cost of sales transactions would be generated. You will also not be allowed to select the Sales and Output Tax accounts.

Should you need to generate purchase documents or supplier returns documents to suppliers (creditors) for services, fees, charges or other purchases which is not trading stock, you may create a Purchase or the Purchase (no stock) stock item type. You may generate purchase documents or supplier returns documents for these non trading Stock items only or add these item codes to an purchase document or a supplier return document containing physical Stock items.

Some examples where you would create a Purchase or the Purchase (no stock) stock item type, is the following:

- Purchasing services such as labour, consulting fees, etc.
- Purchasing goods on which delivery charges (fees), other charges, etc. is applicable.
- Purchasing goods (not for resale) such as stationery, etc.

To create a stock item - Purchases:

1. On the Default ribbon, select Stock items (F12).

2. Click on the New button. A blank Stock form will be displayed.

3. Select the "*Purchases*" stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.

5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab of the debtor (customer / client) account.

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

8. Preferred supplier 1 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

9. Preferred supplier 2 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

10. Click on the Ledger tab, if not already displayed.



11. Enter or select the following options:

    a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

    The Output Tax account field is disabled. The Sales account field is disabled.

    b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

    c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

    d) Weight

        i) Gross weight - Enter, if applicable.

        ii) Net weight - Enter, if applicable.

    e) Values

        i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage.

        ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage.

        iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage.

        iv) Latest cost - The latest cost price of your Stock item can now be entered.

        v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item.

        vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

        vii) Minimum - Specify the minimum quantity of stock to be on hand.

        i) Delivery delay - To be advised.

12. Click on the Save button to save this stock item. The "*Stock item"* grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Free Qt Help documentation generator

Create / Edit Stock items - Purchases (no stock)

The disabled and inactive options for the Purchase and the Purchase (no stock) stock item type are the same. If you select this Purchase or the Purchase (no stock) stock item type on a purchase document or a supplier return document, no Cost of sales transactions would be generated. You will also not be allowed to select the Sales and Output Tax accounts.

Should you need to generate purchase documents or supplier returns documents to suppliers (creditors) for services, fees, charges or other purchases which is not trading stock, you may create a Purchase or the Purchase (no stock) stock item type. You may generate purchase documents or supplier returns documents for these non trading Stock items only or add these item codes to an purchase document or a supplier return document containing physical Stock items.

Some examples where you would create a Purchase or the Purchase (no stock) stock item type, is the following:

- Purchasing services such as labour, consulting fees, etc.
- Purchasing goods on which delivery charges (fees), other charges, etc. is applicable.
- Purchasing goods (not for resale) such as stationery, etc.

To create a stock item - Purchases (no stock):

1. On the Default ribbon, select Stock items (F12).
2. Click on the New button. A blank Stock form will be displayed.
3. Select the "*Purchases (no stock)"* stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.

5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab - Debtors (Default ribbon).

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

8. Preferred supplier 1 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

9. Preferred supplier 2 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

10. Click on the Ledger tab, if not already displayed.



11. Enter or select the following options:

    a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of

sales and Stock control accounts in the Ledger section.

The Output Tax account field is disabled. The Sales account field is disabled.

b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

d) Weight

   i) Gross weight - Enter, if applicable.

   ii) Net weight - Enter, if applicable.

e) Values

   i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage.

   ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage.

   iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage.

   iv) Latest cost - The latest cost price of your Stock item can now be entered.

   v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item.

   vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

   vii) Minimum - Specify the minimum quantity of stock to be on hand.

   i) Delivery delay - To be advised.

12. Click on the Save button to save this stock item. The "*Stock item"* grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Effortlessly optimize your documentation website for search engines

Create / Edit Stock items - Financial entry

The Financial entry Stock item type allows you to select a ledger account on the Accounts lookup when processing documents. Once you select a Financial entry stock item type when processing documents, the Accounts lookup will be displayed. You may then select any general ledger account on the accounts lookup. Examples of accounts that may be selected on documents, are:

- Sales documents (i.e. Invoices, Credit notes and Quotes)
  - Income Accounts - Selling miscellaneous services and goods not trading stock.
- Purchase documents (i.e. Purchases, Supplier returns and Orders)
  - Expense Accounts - e.g. Purchasing of Stationery (Consumables)
  - Asset Accounts - Purchasing fixed assets

To create a Financial entry stock item:

1. On the Default ribbon, select Stock items (F12).
2. Click on the New button. A blank Stock form will be displayed
3. Select the "*Financial entry*" stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.

5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab Debtors (Default ribbon).

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

8. Click on the Ledger tab, if not already displayed.



9. Enter or select the following options:

   a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

   > *The Output Tax account field is disabled. The Sales account field is disabled.*

   > *When selecting the Financial entry stock item type on the Document entry screen, the correct accounts may be selected on the Accounts lookup.*

   b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

   c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

   d) Weight

      i) Gross weight - Enter, if applicable.

ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

This description should reflect your selling price descriptions as you have entered in Setup →Stock information.

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage.

ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage.

iv) Latest cost - The latest cost price of your Stock item can now be entered.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

10. Click on the Save button to save this stock item. The "*Stock item"* grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Create / Edit Stock items - Option item

Option Items allows items that are a combination of options (like colour and size) options can be defined in Setup → Stock information - (Default tab). The Setup options button will launch the screens where the options can be added.

These options are then linked to the Options stock item type (Stock items on the Default ribbon). When processing documents, the available options (options list) will be launched from the quantity fields when selecting documents.

The Options with stock allows every entry to have a sales price, cost price, quantity and minimum stock level. This will also be used in generating purchases on supplier 1.

See - Option item (no stock)

To create an Option stock item:

1. On the Default ribbon, select Stock items (F12).
2. Click on the New button. A blank Stock form will be displayed.
3. Select the "*Option item*" stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.
5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab Debtors (Default ribbon).

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

8. Preferred supplier 1 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

9. Preferred supplier 2 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

10. Click on the Ledger tab, if not already displayed.



11. Enter or select the following options:

    a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

    b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

    c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

    d) Weight

        i) Gross weight - Enter, if applicable.

        ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

This description should reflect your selling price descriptions as you have entered in Setup → Stock information.

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage. When you process purchases, the Average cost Price will be automatically updated.

ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage. When you process purchases, the Total cost price will be automatically updated.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage. When you process purchases, the quantities will be automatically updated.

iv) Latest cost - The latest cost price of your Stock item can now be entered. When you process purchases, the Latest cost Price will be automatically updated.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item. In the case of Stock item codes for the purchase of services, this field should be left blank.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

12. Click on the Options tab, if not already displayed.



13. Select the Options as added in the Setup options (Setup → Stock information).

14. Click on the Generate button to generate a list from the options list. It will generate the Combination Name and the Extra Price.

15. Click on the Save button to save this stock item. The "*Stock item*" grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Simplify Your Help Documentation Process with a Help Authoring Tool

Create / Edit Stock items - Option item (no stock)

Options Item allows items that are a combination of options (like colour and size) options can be defined in Setup → Stock information - (Default tab). The Setup Options button will launch the screens where the options can be added.

These options are then linked to the Options (no stock) stock item type (Stock items on the Default ribbon). When processing documents, the available options (options list) will be launched from the quantity fields when selecting documents.

It induces a Option item (no stock) that you can use to select options with 1 item without having lots of sub items.

See - Option item

To create an Option (no stock) stock item:

1. On the Default ribbon, select Stock items (F12).

2. Click on the New button. A blank Stock form will be displayed.

3. Select the "*Option item (no stock)"* stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.

5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab Debtors (Default ribbon).

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

7. Preferred supplier 1 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

8. Preferred supplier 2 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

9. Click on the Ledger tab, if not already displayed.



10. Enter or select the following options:

a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

d) Weight

   i) Gross weight - Enter, if applicable.

   ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

This description should reflect your selling price descriptions as you have entered in Setup → Stock information.

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

   i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage. When you process purchases, the Average cost Price will be automatically updated.

   ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage. When you process purchases, the Total cost price will be automatically updated.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage. When you process purchases, the quantities will be automatically updated.

iv) Latest cost - The latest cost price of your Stock item can now be entered. When you process purchases, the Latest cost Price will be automatically updated.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item. In the case of Stock item codes for the purchase of services, this field should be left blank.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

11. Click on the Options tab, if not already displayed.



12. Select the Options as added in the Setup options (Setup → Stock information).

13. Click on the Save button to save this stock item. The "*Stock item*" grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Create / Edit Stock items - BOM

You need to select the BOM (Bills of Materials) option if you are selling Stock items or products consisting

of various other Stock items (components) and some services, etc. This option allows you to link existing Stock items and non-physical Stock items to the finished product.

For example, if you wish to sell a complete spraying kit (consisting of a compressor, 2 high pressure pipes and a spray gun), you may select and add these components (existing Stock items) to your finished product.

You will also not be allowed to specify the re-order level and select thae Cost of sales, Stock control and Input Tax accounts.

To create a stock item for Bills of Materials (BOM):

1. On the Default ribbon, select Stock items (F12).
2. Click on the New button. A blank Stock form will be displayed.
3. Select the "*BOM*" stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.
5. Select the Unit size.
6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab Debtors (Default ribbon).
7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.
8. Preferred supplier 1 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.
9. Preferred supplier 2 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.
10. Click on the Ledger tab, if not already displayed.



11. Enter or select the following options:

a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

> *The Input Tax account field is disabled. The Cost of sales and Stock control account fields are disabled.*

b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

d) Weight

i) Gross weight - Enter, if applicable.

ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

> *This description should reflect your selling price descriptions as you have entered in Setup → Stock information.*

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage. When you process purchases, the Average cost Price will be automatically updated.

ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage. When you process purchases, the Total cost price will be automatically updated.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage. When you process purchases, the quantities will be automatically updated.

iv) Latest cost - The latest cost price of your Stock item can now be entered. When you process purchases, the Latest cost Price will be automatically updated.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item. In the case of Stock item codes for the purchase of services, this field should be left blank.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

12. Click on the BOM tab, if not already displayed.



13. Click on the Add button to select an item on the Stock item lookup. Repeat this process until all the items (components) have been added to the list.

> *If more than 1 Stock item is included in the finished product, you need to enter the quantities to be included in the finished product.*

> *To delete (remove) an item from the BOM List, select the item on the list and click on the Delete button.*

14. Once you have added the BOM items to the list, enter the quantities of the components for each item. The values in the *Average cost, Latest cost* and *Quantities on Hand* fields will automatically be displayed for each stock item. The total Cost price value will also be automatically calculated (sum of the number of items x cost price for each item).

15. Select Cost price or Selling price option in the *Calculate Base* field. Click on the Recalculate Sales % button. This will calculate the Percentage of Sales for each item on the BOM List.

16. Click on the Save button to save this stock item. The "*Stock item"* grid (default) screen will be displayed.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Create / Edit Stock items - BOM (Production)

BOM (Production) stock item type

The BOM (Production) stock item type is used when you are selling stock items or products that consist of various other stock items (components) and services. This allows you to link existing physical and non-

physical stock items to create a finished product.

Manufacturing and BOM (Production) Stock Item Type

The Manufacturing process would specifically apply to the BOM (Production) stock item type. This is because BOM (Production) includes features that are essential for manufacturing processes, such as the ability to assemble and disassemble products. Here's a detailed explanation:

BOM (Production) Stock Item Type and Manufacturing:

- Manufacturing Focus: BOM (Production) is designed to handle the manufacturing process where components and services are combined to create finished products.
- Assembly: Allows for specifying and combining quantities of various components to form a finished product. This reflects the manufacturing process of creating new products from raw materials or parts.
- Disassembly: Enables breaking down finished products back into their individual components, which can be necessary for various manufacturing and inventory management scenarios.
- Inventory Management: Tracks the usage and adjustments of components and finished products, ensuring accurate inventory control during manufacturing operations.

Conclusion:

- BOM (Bills of Materials): Generally used for tracking and managing items that consist of various components and services.
- BOM (Production): Specifically tailored for manufacturing processes, providing features to assemble and disassemble items, crucial for creating and managing finished products from various components.

Therefore, the Manufacturing process applies specifically to the BOM (Production) stock item type due to its specialized features for handling the complexities of production.

Instructions for BOM (Production) Stock Item Type: Assemble / Disassemble

Before you proceed with the assembly or disassembly of BOM (Production) stock items, you need to perform the following preliminary steps:

Add Stock items as BOM (Production) stock item type

Add Stock items as BOM (Production) stock item type : On the BOM tab of the BOM (Production) stock item type, add or the link existing physical and non-physical stock items to create a finished product on the BOM list. On the BOM tab, you need to configure to recalculate the base (on cost price or selling price). You may also recalculate the sales percentage.

Select a BOM (Production) Contra Account

The BOM (Production) stock item type, will add the Assembly and Disassembly features as context menu options which include the ability to:

- Assemble: Specify and combine quantities of components to create finished items.
- Disassemble: Specify and break down quantities of finished items back into components.

The Assemble and Disassemble context menu options will process transactions to the "*BOM (Production) Contra account*" will record the transactions when the you:

- Assemble: Specify and combine quantities of components to create finished items from the BOM. This will debit the "*BOM (Production) Contra account*" and credit the "*Stock control account*" .
- Disassemble: Specify and break down quantities of finished items from the BOM list back into components. This will debit the "*Stock control account*" and credit the "*BOM (Production) Contra account*".

If the BOM (Production) contra account is not selected, the system will display an information message:

"Please setup production contra account in Stock setup."

To select the BOM (Production) contra account, navigate to Setup → Stock information and select the ledger account.

You will not be allowed to specify the re-order level and select the Cost of sales, Stock control and Input Tax accounts.

Create (Add) stock items for Bills of Materials - Production (BOM (Production)

To create a stock item for Bills of Materials - Production (BOM (Production):

1. On the Default ribbon, select Stock items (F12).

2. Click on the New button. A blank Stock form will be displayed.

3. Select the "*BOM (Production)*" stock item type. The Stock entry form is displayed as follows:



4. Enter the Stock code, Description, Barcode, Manufacturer and Extra description as required.

5. Select the Unit size.

6. Apply invoice discount - This is applicable to debtor (customer / client) accounts, as the percentage customer discount is specified on the Accounting information tab - Debtors (Default ribbon).

7. Reports - Stock group 1 / 2 - The reporting group to which you wish this Stock item to be allocated.

8. Preferred supplier 1 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

9. Preferred supplier 2 - Optional - Select a creditor (supplier / vendor) account and enter a supplier stock code if applicable.

10. Click on the Ledger tab, if not already displayed.



11. Enter or select the following options:

a) Tax class - If you have created tax classes, select the tax class. The Tax class will automatically add the Input Tax and Output Tax accounts in the Tax section, the Sales account, Cost of sales and Stock control accounts in the Ledger section.

b) Last invoice - Field inactive. The date of the last purchase or other document generated on which the Stock item was selected. This field will not display any date if it is a new item, or if no Stock items have been selected on any documents.

c) Default cost group - This is by default inactive. If you have created and activated cost centres, these may be selected.

d) Weight

   i) Gross weight - Enter, if applicable.

   ii) Net weight - Enter, if applicable.

e) Selling prices - Enter the Selling price 1/2/3 exclusive or inclusive of Tax. The inclusive of VAT/GST/Sales Tax will be calculated based on the percentage entered in your Output Tax account. (if you selected that account in advance).

This description should reflect your selling price descriptions as you have entered in Setup → Stock information.

If you have for example entered: "Retail", "Wholesale" and "Cash" for these Selling prices, the Selling price 1 / 2 / 3 will be respectively displayed as such.

The amounts as entered in these fields will be displayed on Invoices, Credit notes and Quotes. When the cursor is displayed on the Amount fields, you may select any of the available selling prices you wish to charge your debtors (customers / clients).

f) Values

   i) Average cost - Field inactive. The average cost price of your Stock item cannot be entered at this stage. When you process purchases, the Average cost Price will be automatically updated.

   ii) Total cost - Field inactive. The total cost price of your Stock item cannot be entered at this stage. When you process purchases, the Total cost price will be automatically updated.

iii) Quantity on hand - Field inactive. The quantity, or number of Stock items on hand, cannot be entered at this stage. When you process purchases, the quantities will be automatically updated.

iv) Latest cost - The latest cost price of your Stock item can now be entered. When you process purchases, the Latest cost Price will be automatically updated.

v) Reorder level - The minimum level of stock that you wish to keep on hand for this Stock item. In the case of Stock item codes for the purchase of services, this field should be left blank.

vi) Reorder at - Specify the quantity of stock to be available when you need to reorder stock.

vii) Minimum - Specify the minimum quantity of stock to be on hand.

i) Delivery delay - To be advised.

12. Click on the BOM tab, if not already displayed.



13. Click on the Add button to select an item on the Stock item lookup. Repeat this process until all the items (components) have been added to the list.

If more than 1 Stock item is included in the finished product, you need to enter the quantities to be included in the finished product.

To delete (remove) an item from the BOM List, select the item on the list and click on the Delete button.

14. Once you have added the BOM items to the list, enter the quantities of the components for each item. The values in the *Average cost, Latest cost* and *Quantities on Hand* fields will automatically be displayed for each stock item. The total Cost price value will also be automatically calculated (sum of the number

of items x cost price for each item).

15. Select Cost price or Selling price option in the *Calculate Base* field. Click on the Recalculate Sales % button. This will calculate the Percentage of Sales for each item on the BOM List.

16. Click on the Save button to save this stock item. The "*Stock item - List view*" (default) screen will be displayed.

BOM (Production) Assemble / Disassemble

Before you may process the assemble / disassemble options for the "*BOM (Production)*" stock item, you need to add the stock items and do some basic settings.

Select a BOM (Production) contra account

If the BOM (Production) contra account is not selected, an information message is displayed:

"Please setup production contra account in Stock setup."

Add a BOM (Production) contra account in Setup → Stock information.



Add the stock items



Assemble and Disassemble BOM (Production) stock item type

Once this you have finished adding and configuring your items (products) pm the BOM tab, you may select the "*Assemble*" or "*Disassemble*" on the context menu for the "*BOM (Production)*" stock item type.

IMPORTANT : This will automatically generate a document and post (update the ledger) the transactions based on your configuration, for the items (products) on your BOM list.



Assemble BOM (Production) item

To assemble BOM (Production) item:

1. Select the "*BOM (Production)*" item on the "*Stock item"* grid.

2. Right-click on a selected stock item (BOM (Production) stock item type) and select the " *Assemble"* option on the context menu. The "*Quantity"* screen is displayed:



3. Enter the quantity and click on the OK button. The confirmation screen will list the details of the assembly:

```
Processing lvl 0  BOMPRODUCTION BOM (Production)
Processing lvl 1  3COMP Compressor
Processing trans qty:5  3COMP Compressor
Processing lvl 1  3DRILL Drill press
Processing trans qty:5  3DRILL Drill press
Processing trans qty:-5  BOMPRODUCTION BOM (Production)
Processing costofsale:5  BOMPRODUCTION BOM (Production)
Processing costofsale:5  BOMPRODUCTION BOM (Production)
Processing costofsale:5  3COMP Compressor
Processing costofsale:5  BOMPRODUCTION BOM (Production)
Processing costofsale:5  3DRILL Drill press
```

4. Click OK to update quantities to BOM (Production) stock item and post transactions. A posted document with prefix *'SA'* (e.g., *'SA00001'*) will be generated for "*Assemble*".

Disassemble BOM (Production) item

Once you have assembled items, you may disassemble quantities.

To disassemble BOM (Production) item:

1. Select the"*BOM (Production)*" item on the "*Stock item - List view*" (default) screen.

2. Right-click and select the "*Assemble*" option on the context menu. The "*Quantity*" screen is displayed:

3. Enter the quantity and click on the OK button. The confirmation screen will list the details of the disassembly:

```
Processing lvl 0  BOMPRODUCTION BOM (Production)
Processing lvl 1  3COMP Compressor
Processing trans qty:1  3COMP Compressor
Processing lvl 1  3DRILL Drill press
Processing trans qty:1  3DRILL Drill press
Processing trans qty:-1  BOMPRODUCTION BOM (Production)
Processing costofsale:1  BOMPRODUCTION BOM (Production)
Processing costofsale:1  BOMPRODUCTION BOM (Production)
Processing costofsale:1  3COMP Compressor
```

```
Processing costofsale:1  BOMPRODUCTION BOM (Production)
Processing costofsale:1  3DRILL Drill press
```

4. Click OK to update quantities to BOM (Production) stock item and post transactions. A posted document with prefix *'SA'* (e.g., *'SA00001'*) will be generated for "*Disassemble*".

BOM (Production) Document groups / Transactions tabs

The "*Assemble*" and "*Disassemble*" functions for BOM (Production) items create posted documents. These transactions will be listed under the Document groups tab and the Transactions tab.

Documents generated by these functions will have a document prefix "*SA*" (e.g., "*SA00001*"), using a similar 7-digit format.

BOM (Production) Document Groups Tab

The Document Groups tab for BOM (Production) stock items shows documents related to assembly and disassembly. These documents are automatically posted when you perform the Assemble and Disassemble actions.



On the Document groups tab, you can:

- Print a document: Double-click on the document to print it.
- Open a posted document: Right-click on the document and select "*Open document*" from the context menu.

BOM (Production) Transactions Tab

The Transactions tab includes posted documents generated by the assembly and disassembly of BOM (Production) items.



On the Transactions tab, you can:

- Open a posted document: Right-click on the document and select "Open document" from the context menu.

By following these instructions, you can efficiently manage and review the documents and transactions related to the assembly and disassembly of BOM (Production) items.

Viewing Posted Documents for BOM (Production) Items

Opening a Posted document

On the BOM (Production) Document groups and Transactions tabs, you can open posted documents generated by the "*Assemble*" and "*Disassemble*" functions as follows:

1. Right-click on the desired document.
2. Select "Open document" from the context menu.



Identifying the Document type

- The "*Your reference*" field and the "*Description*" column in the posted document will indicate whether the document was generated using the "*Assemble*" or "*Disassemble*" options for BOM (Production) items.
- Documents generated by these functions will have a document prefix "SA" (e.g., "SA00001"), using a similar 7-digit format.

By using these steps, you can easily access and identify the specific documents related to the assembly and disassembly of BOM (Production) items.

Print a Posted document

You may print selected posted document generated by the "*Assemble*" and "*Disassemble*" of BOM (Production) items from the following options:

- BOM (Production) - Document groups tab : (Double-click to print).
- Search (central search) : Locate these posted document generated by the "*Assemble*" and "*Disassemble*" of BOM (Production) items. (Double-click to print).



The "*POS Tax Invoice*" will print the correct document number, but will print the system date and time

stamp of your operating system and not the actual transaction date.

The default document layout file which will be used to print documents generated by the "Assemble" and "Disassemble" of BO is the "Layout file point-of-sale" selected in Setup → Documents setup.

WARNING: Point-of-sale document layouts might not be ideal for printing "Assemble" and "Disassemble" documents for BOM types due to:

- *Date: POS invoices show your system's date, not the actual processing date.*
- *Document Name: Might say "POS Tax Invoice" instead of something relevant.*
- *Footer: Contains data like cashup amounts, not relevant for BOM operations.*

Recommendation: Select a different document layout file for BOM (Production) transactions (Setup → Documents setup).



NOTE: Selecting the document layout files, which supports the "TYPES.SDESCRIPTION" document name from the "TYPES" table, document name as "Delivery note" for "Assemble" option and "Remittance" for "Disassemble" option. Selecting the following do will replicate the document names:

- *Layout file - (TRN_1910)*
- *Document layout - (TRN_3174)*

- *Document layout (15codes) - (TRN_906277)*
- *NO-TAX Layout file - (TRN_906589)*
- *NO-TAX Document layout - (TRN_906590)*
- *NO-TAX Document layout (15codes) - (TRN_906591)*

Recommendation: You may select the BOM (Production) Layout file (TRN_3266) for the Stock item type to print layout file "Assembly" or "Disassembly".

Document prefix: "SA" (e.g., "SA00001"), with a similar 7-digit format.

Example : Assemble



Delivery note accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```


BOM (Production)

BOM (Production) Page no.: 1 / 1

Empty account

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195
Company reg. no.: 336012345
Tax reg. no.: 446010111
Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Delivery address

Document no.: SA00001 **Date: 2024/05/21** **Account no.: T**

Code / Description	Units	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inc
BOMPRODUCTION Assemble BOM (Production)		5	1 500,00		7 500,00			

Total

Due date:
Your reference: Assemble BOM (Production)
Tax reference:
Message:

Salesperson: No group

BOM (Production) accepted:

Name: _____

Date: _____

Signature: _____

Printed/Reprinted *2024/09/04 04:47:14*

Example : Disassemble



Remittance accepted: in SubReport-1(TAX) - Changed label TRpExpression85 to print BOM (Production accepted :)

```
CUSTOM('GETTEXTLANG',3266,'BOM(Production',CLIENTORDEFLANG.SLANGUAGE,0,0)+'
'+(CUSTOM('GETTEXTLANG',906275,'Accepted',CLIENTORDEFLANG.SLANGUAGE,0,0)+(':  '))
```



Viewing BOM (Production) Transactions

The transactions generated by assembling and disassembling BOM (Production) items are posted to the "BOM (Production) Contra account" as configured in Setup → Stock Information.

These transactions are recorded in the ledger and can be viewed through various reports and tools. Here's how you can view, print, and export these transactions:

1.

1. Reports Menu: To view these transactions, navigate to the Reports menu and select Reports → Ledger → Transactions. You can choose from the following reports:
    - Transactions
    - Transactions - Standard

- Transactions - Extra details

2. Batch entry: Cost of Sales journal: Open the Batch entry (F2) and select Cost of Sales journal. In the Cost of Sales journal, click on the posted batches tab and select the batch. You can print the transactions in the "*Batch type report - Posted batch*".

3. T-Account Viewer: Access the T-Account viewer and select the "*BOM (Production) Contra account*". This allows you to view, print, and export the transactions.

4. Ledger Analyser: Alternatively, you can print a Trial Balance in Ledger Analyser 1 or Ledger Analyser 2. Double-click on the desired account or use the "*Show details*" option from the context menu to view detailed transactions.

5. Central Search: To locate specific assemble or disassemble transactions or document numbers. In the search results, double-click on the Batch type to display the transactions in the T-Account viewer.

Example : Ledger transactions - BOM (Production) Contra account



BOM (Production) - Assemble and Disassemble options will automatically generate transactions, which is posted to the ledger.

The Document no. for a BOM (Production) - Assemble and Disassemble options is automatically generated as a seven-digit number (consisting of a prefix SA followed by 5 numerical digits).

The Document type is "Assemble" or "Disassemble"

Example : Batch type report - Posted batch - BOM (Production) Batch transactions

Open the Batch entry (F2) and select Cost of Sales journal. In the Cost of Sales journal, click on the posted batches tab and select the batch.



Click the Print button to print the transactions in the "*Batch type report - Posted batch*".



Example : Batch type report - Posted batch report - Assemble transactions



Example : Batch type report - Posted batch report - Disassemble transactions



T-Account viewer

In addition to the transaction reports on the Reports menu; you may view, print and export transactions in the T-Account viewer from the following options.

- T- Account viewer : On the reports menu, select the T-Account viewer icon and select the "*BOM (Production) Contra account*".
- Alternatively, you may print a Trial balance in the Ledger analyser 1 / Ledger analyser 2 and double-click or use the "*Show details*" option on the context menu.



You may filter the transactions by batch number, e,g, "*34*" or "*35*".

Click on the Print button to print a T-account view of the transactions.



Should you wish to export these transactions to a spreadsheet click Export. If you need to include Contra accounts, in your spreadsheet, select the "*Show contra*" option

Search (Central search)

To locate specific assemble or disassemble transactions or document numbers:

- Search for keywords such as "*assemble*", "*disassemble*", or document numbers starting with "*SA*".
- In the search results, double-click on the "*Batch*" type to display the transactions in the T-Account viewer.
- To print a document, double-click on a document for the "*Document*" type.



NOTE: On the Search (central search), the "*Description*" column for the "*Document*" type, is indicated as follows:

- Dissable Details - Should be "*Production Details*" since the document e.g. "*SA00001*" is created using the "*Assemble*" option. The document type is listed as "*Assemble*" on the Document groups and Transactions tabs of the stock item for the BOM (Production) stock item type.
- Production Details - Should be "*Disassemble Details*" since the document e.g. "*SA00002*" is created using the "*Disassemble*" option. The document type is listed as "*Disassemble*" on the Document groups and Transactions tabs of the stock item for the BOM (Production) stock item type.

Search Description Inaccuracy:

- Central Search shows "*Dissable Details*" for "Assemble" documents (e.g., "SA00001"). This should be *"Production Details*".
- Conversely, "*Production Details*" are shown for "*Disassemble*" documents (e.g., "SA00002"). This should be "*Disassemble Details*".

Correct Descriptions:

- "*Assemble*" documents: Use "*Production Details*".
- "*Disassemble*" documents: Use "*Disassemble Details*".

These descriptions are consistent with the document types listed on the stock item's "Document groups" and "Transactions" tabs (BOM (Production) stock item type).

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Create / Edit Stock items - Linked sale

Stock item - Linked Sale (580) - To be advised.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Delete stock items

You may delete a stock item, if it has no transactions and/or balances.

You may disable a stock item to hide the stock item from the stock lookup when processing documents. Disabled stock items will still be included on the stock lookup when printing reports.

You may need to do this, if you are no longer use the stock item, the stock item is discontinued, etc.

Delete items

To delete a stock item:

1. On the Stock items, select the stock item, and click on the Delete button. A confirmation message is displayed:

   "Are you sure you want to delete this stock item?"

   Make sure absolutely sure that the correct stock item is selected.

2. Click on the Yes button. The stock item will be permanently removed (deleted).

Disable items

If you cannot delete a stock item, if it has no transactions and/or balances you may disable or set the stock item as inactive.

Advantages of Disabling or Setting a Stock Item to Inactive:

1. Organization: Disabling stock items that are no longer in use such as discontinued items, helps keep your inventory database organized and decluttered.
2. Accuracy: By removing inactive items from the selection options, you reduce the chances of users mistakenly selecting them for new transactions.
3. Focus: Keeping only active items visible can streamline the selection process for users, allowing them to focus on items that are relevant to current operations.
4. Compliance: In some cases, regulatory or internal compliance requirements may necessitate the removal of certain items from active circulation. Disabling them ensures adherence to these requirements.

Ultimately, the decision to disable or set a stock item to inactive should be made based on factors such as current usage, future plans, and organizational policies, while considering the balance between organization and operational efficiency.
When processing sales and purchase documents,

To disable a stock item:

1. If the stock item has transactions and/or balances, you cannot delete it. An information message is displayed:

"3COMP You cannot delete this stock item! It has transactions! 12 PU000004"
(3COMP is the stock code and PU000004 is the last processed document number as per this example).

2. To hide the stock item from the stock item lookup when processing documents, select the stock item and click on the Edit button.
3. Tick the Disabled field.
4. Click on the Save button.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Export / Import - Stock items

Created with the Standard Edition of HelpNDoc: Free help authoring environment

Export - Stock items (Setup ribbon)

This feature is additional to the powerful Report Export facility in which all reports for Stock items in osFinancials5/TurboCASH5 may be exported, and saved in any available format on your system, such as Word Processing (Text), Spreadsheets, etc. Using this facility, you may also export the data of your Stock items in an open Set of Books to XML Database format, or any available format on your system.

You may then open the other applications to which the exported data is saved, and work in the applications, such as OpenOffice.org Calc, Lotus 123, Microsoft Excel, etc. You may edit the data for your Stock items in a Lotus123 (*WK1) file format and import it in Stock items (Default ribbon).

All the information regarding each stock item as entered in the Stock items (Default ribbon) (Stock code, Barcode, Description, Re-order levels, Apply invoice discount, Selling prices, Unit Description, Cost of sales account, Sales account, Input Tax and Output Tax accounts) will be displayed. In the same export file, the latest updated information regarding any adjustments and transactions (Quantity on hand and Average cost) would also be included into the selected export file format.

You may edit the data for your Stock items in a Lotus123 (*WK1) file format and import it in the Stock items (Default ribbon).

To export Stock items:

1. On the Setup ribbon, select Export.

2. Click on the Stock button, if not selected.



3. Select and/or enter the following:

a) Export to - The installation directory in which osFinancials5/TurboCASH5 is installed, will be displayed. You may click on the Browse icon to select a folder on the "*Browse for Folder*" screen. You may then select any available folder, or drive, on your system into which you wish to export the data.

b) File type - Select to export the file as "*Tab delimited*" (*.txt) file format (recommended).

"Import file format not implemented!" information message is displayed for the following file types:

- *TXF TurboCASH Exchange File*
- *SXC OpenOffice Spreadsheet*

*The XML Database (*XML) file format export can only be imported in Import (Setup ribbon). It cannot be imported in Stock items (Default ribbon).*

c) Export files name - Enter the File name. You need to select this file at a later stage when you wish to import the file, or analyse the data in a spreadsheet.

d) Log file - Enter the Log file name.

e) Range - From / To - Select the stock items to include in the export file.

f) Increment Export - Leave this option blank.

4. Click on the Export button to create the export file, and save it in the specified directory.

The information for the Stock items, which will be exported, is:

- *Stock code*
- *Stock item type*
- *Barcode*
- *Description*
- *Quantity on hand*
- *Reorder quantity*
- *Apply invoice discount*
- *Selling price 1 amount*
- *Selling price 2 amount*
- *Selling price 3 amount*
- *Unit average cost amount*
- *Unit cost amount*
- *Unit description*
- *Stock group 1*
- *Stock group 2*
- *Cost of sales account*
- *Sales account code*
- *Stock account*

- *Input Tax account*
- *Output Tax account*

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Import - Stock items (Setup ribbon)

This option will allow you to import data for Stock items from a valid file format into an existing Set of Books. To be able to import the data for Stock items, you need to have created a valid XML Database File format or a valid Lotus Spreadsheet file format on your system in Export (Setup ribbon).

To import Stock items:

1. On the Setup ribbon, select Import. The "*Import Data into osFinancials"* screen is displayed:



2. Select Stock as the "*Data type to import*".
3. Select one of the following file types in which the data to import, is saved on your system:
    a) Tab delimited (recommended)
    b) Comma Separated Values (*.CSV)
    c) Tab Delimited (*.TXT)
    d) XML Database File (*.XML)
    e) Lotus Spreadsheet File (*.WK1)

4. Click on the >> button to locate the data file. The following screen is displayed:



5. Click on the button to locate the data file.

Optional - You may click on the View file button to view the file in your system's default app (program) associated with th

An example of the exported Tab Delimited text file is as follows:



Export-Stock-Tab-delimited.txt - Notepad

File Edit View

```
SSTOCKCODE    WSTOCKTYPEID  SBARCODENUMBER       SDESCRIPTION  SMANUFACTURER FQTYONHAND
       BAPPLYINVOICEDISCOUNT       FSELLINGPRICE1       FSELLINGPRICE2       FSELLINGPRICE3
       FGROSSWEIGHT  SEXTRADESC    SEXTERNALID   BDISABLED     SSTOCKCODESUP1       SSTOCKC
       SCostAccount  SSaleSACCOUNT SStockAccount SInputTax     STaxclass     SOutputTax
"3DRILL"      0      "1234567890"  "Drill press" "Bosch"       10     10     5      4
       "850 Watts + 6 drill bits"  ""     0      "A-12345"     "B-12345"     "Each" "Power
       "T860020"     "Standard rate 15%"  "T860010"     "C2AONES"     "C2BESTS"     ""
"3COMP"       0      "3456789123"  "Compressor"  "CMP"  5      10     4      0      1
       0      "A1-12345"    "B-12345"     "Each" "Power tools" "Unallocated" "G100000"
15%"   "T860010"     "C2AONES"     "C2BESTS"     ""
"SALES"       2      ""     "Sales"       ""     0      0      0      0      1      0
       ""     ""     ""     "Sales"       "Unallocated" "G100000"     "G010000"     "G75000
       "T"    ""
"PURCHASES"   3      ""     "Purchases"   ""     0      0      0      0      1      0
       ""     ""     ""     "Purchases"   "Unallocated" "G100000"     "G010000"     "G75000
       "T"    ""
"SALES-NS"    4      ""     "Sales (no stock)"   ""     0      0      0      0      1
       0      ""     ""     ""     "Sales"       "Unallocated" "G100000"     "G010000"
       "T"    "T"    ""
"4L-PAINT-E"  4      ""     "Paint - Exterior"   ""     0      0      0      0      1
       0      ""     ""     "Hours"       "Labour"      "Unallocated" "G100000"     "G01000
       "T860010"     "T"    "T"    ""
"4L-INSTCUP"  4      ""     "Install - Built-in cupboards"     ""     0      0      0
       ""     ""     0      ""     ""     "Hours"       "Labour"      "Unallocated" "G10000
rate 15%"     "T860010"     "T"    "T"    ""
"GL-CODE"     6      ""     "General ledger"     ""     0      0      0      0      1
       0      ""     ""     ""     "Labour"      "Unallocated" "G100000"     "G010000"
       "T"    "T"    ""
"OPTIONITEM"  7      ""     "Option item" ""     0      0      0      0      1      0
       ""     ""     ""     "Option"      "Unallocated" "G100000"     "G010000"     "G75000
       "T"    ""
"OPTIONITEM-NS"      8      ""     "Option item (no stock)"    ""     0      0      0
       ""     ""     0      ""     ""     ""     "Option"      "Unallocated" "G100000"
15%"   "T860010"     "T"    "T"    ""
"PURCHASES-NS"       5      ""     "Purchases (no stock)"      ""     0      0      0
       ""     ""     0      ""     ""     ""     "Purchases"   "Unallocated" "G100000"
15%"   "T860010"     "C2AONES"     "C2BESTS"     ""
"BOM"  1      ""     "BOM"  ""     0      0      0      0      1      0      0      0
       "@"    "Bom"  "Unallocated" "G100000"     "G010000"     "G750000"     "T860020"
"BOMPRODUCTION"      9      ""     "BOM (Production)"   ""     0      0      0      0
       ""     0      ""     ""     "@"    "Bom"  "Unallocated" "G100000"     "G010000"
       "T"    "T"    ""
```

Ln 9, Col 65

6. Click on the >> button. The following screen is displayed:



7. Click on the Import button. The "*ImportCheck*" screen is displayed:



8. You may use the record buttons to add, delete or change the stock records on the "*ImportCheck*" screen. You may then click on the All or OK buttons to import the stock file.

9. Once the import process is finished an information message is displayed:

   "Data file import completed!"

10. Click on the OK button.

11. Go to the Reports ribbon and select Reports → Stock items → Stock item listing to check the stock items.

12. Go to the Default ribbon and select Stock items to edit the stock items, if necessary.

Important notes - After import

Stock colours

If stock items were linked to Stock group 1 and or Stock group 2 and it is included in the exported file, the stock items will be linked to reporting groups for Stock group 1 and / or Stock group 2.

The colours will not be imported in the Stock grid. You need to set the reporting group colours for Stock group 1 and or Stock group 2 in Setup → Groups - Stock group 1 and / or Stock group 2.

Cost of sales settings

If cost of sales is not activated before you import stock items, the Cost of Sales account will be inactive when you edit stock items.



This reason for this is that Cost of sales is not activated in your Set of Books.

To activate Cost of sales:

1. Create a batch type (journal type) for Cost of sales in Setup → Batch types and set the contra account to the "*Cost of Sales*" account.
2. Activate Cost of sales in Setup → Stock information - Default tab

This is applicable to the "Default" (trading stock) and some other stock item types only.

3. Select the following:
   - Create cost of sales – To activate cost of sales, select (tick) the "*Create cost of sales*" tick box.
   - Cost of sales batch – Select the "*Cost of sales*" batch (journal) in which the cost of sales transactions will be posted.
   - Use "*Average cost*" or "*Latest cost*" option.

The method you use to calculate the value of your stock is crucial for determining its impact on your profit and loss figures. It is important to consider whether to use the "average cost" or the"latest cost" method.

If you are unsure which method to use, it is recommended that you seek guidance from your accountant.

4. Click OK.
5. For these settings to take effect, you may need to go to Tools → Close active forms (Setup ribbon) or reopen the Set of Books. The Cost of sales lookup field will be active (for the "*Default*" stock item type or other stock item types which supports Cost of sales) on the Ledger tab of Stock items.

Tax classes

After Stock items is imported the Tax Classes will be empty.

The Tax Classes tab in the Stock information section enables you to create and manage account classes/tax classes. Tax classes consist of five (5) accounts that are associated with the Ledger tab of stock items on the Default ribbon.

You may add Tax Classes stock item type for each of the Tax (VAT/GST/Sales tax) items for example, standard rate, capital goods, zero rated, exempt goods, etc.) which is prescribed by your tax authority.

You may also use Tax Classes to assign various stock items to various Sales accounts, Cost of Sales accounts and Stock control accounts.

When you link a stock item to a tax class, it automatically populates the Input Tax, Output Tax, Sales, Cost of Sales, and Stock control account fields on the Ledger tab for that specific stock item. This eliminates the

need to manually select these accounts for each individual stock item.

By utilising tax classes, the Lookup button on the Ledger tab of stock items is disabled, as the tax class already defines the appropriate accounts for taxation and accounting purposes. This simplifies the process of assigning accounts to stock items, ensuring consistency and accuracy in tax calculations and financial reporting.

Created with the Standard Edition of HelpNDoc: Elevate Your Documentation with HelpNDoc's Project Analyzer Features

Exported stock items - Open text file in spreadsheet

If you need to import stock items it is recommended that you first create an export file of the data for your stock items in the Export option on the Setup ribbon.

You may then import the data of your stock items in the Import option on the Setup ribbon.

You may also export or import stock items as a tab delimited text file from the following options:

Once the text file is saved, you need to launch your spreadsheet application i.e Excel, OpenOffice, LibreOffice, Ultra Office, etc.

To open the exported stock items text file in a spreadsheet:

On your spreadsheet application, open the saved stock items text (*.txt) file and confirm your tab delimited settings.



This will open your stock items in a spreadsheet. An example of the exported file opened in "*LibreOffice Calc*" spreadsheet, is as follows:



The exported data will be exported in 38 columns:

Column	*Column heading*	*Source / fields*	
A	*SSTOCKCODE*	*Stock item code*	*String (15)*
B	*WSTOCKTYPEID*	*Stock type ID*	*Integer* *0 = Default stock item* *1 = BOM* *2 = Sales* *3 = Purchases* *4 = Sales (no stock)* *5 = Purchases (no stock)* *6 = Financial entry (General ledger)* *7 = Option item* *8 = Option item (no stock)* *9 = BOM (Production)* *10 = Linked sale (Linked items)*
C	*SBARCODENUMBER*	*Bar code number*	*String (30)*
D	*SDESCRIPTION*	*Stock item description*	*String (35)*
E	*SMANUFACTURER*	*Manufacturer*	*String (35)*
F	*FQTYONHAND*	*Quantity on hand*	*Float(numeric)*
G	*FREORDERQTY*	*Reorder quantity*	*Float(numeric)*
H	*FREORDERQTYTRIG*	*Reorder at quantity*	*Float(numeric)*
I	*FMINIMUMQTY*	*Minimum quantity*	*Float(numeric)*

J	BAPPLYINVOICEDISCOUNT	Apply Invoice discount	B = CheckBox 0 = No 1 = Yes
K	FSELLINGPRICE1	Selling price 1	Float(numeric)
L	FSELLINGPRICE2	Selling price 2	Float(numeric)
M	FSELLINGPRICE3	Selling price 3	Float(numeric)
			Line ID used for sorting items on document lines
N	FUNITAVECOST	Unit average cost	Float(numeric)
O	FUNITCOST	Unit cost	Float(numeric)
P	FNETTOWEIGHT	Net weight	Float(numeric)
Q	FGROSSWEIGHT	Gross weight	Float(numeric)
R	SEXTRADESC	Extra description	String (255)
S	SEXTERNALID	External ID	
T	BDISABLED	Disabled	B=CheckBox 0 = Stock item enabled (active) - (False - not checked) 1 = Stock item disabled (inactive) - (True - checked)
U	SSTOCKCODESUP1	Preferred supplier 1 Stock code	String (30)
V	SSTOCKCODESUP2	Preferred supplier 2 Stock code	String (30)
W	SUnit	Unit description	String (8)
X	SGroup1	Stock group 1	String (30)
Y	SGroup2	Stock group 2	String (30)

Z	*SCostAccount*	*Cost of sales account code*	*String (6) + G prefix*
AA	*SSaleSACCOUNT*	*Sales account code*	*String (6) + G prefix*
AB	*SStockAccount*	*Stock control account code*	*String (6) + G prefix*
AC	*SInputTax*	*Input Tax account code*	*String (6) + T prefix*
AD	*STaxclass*	*Tax class description*	
AE	*SOutputTax*	*Output Tax account code*	*String (6) + T prefix*
AF	*SSupplier1*	*Preferred supplier 1 Account code*	*String (6)*
AG	*SSupplier2*	*Preferred supplier 2 Account code*	*String (6)*
AH	*OPTION*	*Option item*	
AI	*DESCLANG50*	*Description language*	
AJ	*MEMOLANG50*	*Memo language*	
AK	*DESCLANG51*	*Description language*	
AL	*MEMOLANG51*	*Memo language*	*String (15)*

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Spreadsheet Export / Import - Stock items

osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export

feature.

- Spreadsheet export - You may export stock items and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import stock items from a saved "*Excel Workbook (*.xlsx) file type.*

This feature may be used to import stock items into:

- Into the same Set of Books.
- Into a different Set of Books.
- Into a new Set of Books -Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types.
- Into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

> *Before you may import stock items in a new Set of Books, you need to do the necessary setup and configuration for stock.*
>
> *Once this is done, you may start to import stock items from a saved "Excel Workbook (*.xlsx) file type.*

This option will allow you to Export your stock item file into an Excel spreadsheet. You may then add new stock items, edit existing stock items and import it back into your stock code file.

You may access the "*Data Import Export*" feature from the following options:

- Import / Export tab of the Stock items (Advanced mode) on the Default ribbon.



- Import option on the Setup ribbon.



Select Stock as the "*Data type to import*". Click on the Excel import export button. The "*Data Import Export*" spreadsheet will displayed column headings for the Stock items (without any data).

Created with the Standard Edition of HelpNDoc: Make Documentation Review a Breeze with HelpNDoc's Advanced Project Analyzer

Spreadsheet - Export - Stock items

This option will allow you to Export your stock code file into an Excel spreadsheet. You may then add new stock items, edit existing stock items and import it back into your stock code file.

To export and stock items to a Excel Workbook (xlsx) file:

1. Open the Set of Books from which, you wish to create a spreadsheet export file.

2. On the Setup ribbon, select Import. The "*Import Data into osFinanacials*" screen is displayed:



3. Select Stock as the "*Data type to import*".

4. Click on the Excel import export button. The Excel spreadsheet will be displayed with the column headings for the Stock items (without any data).

5. Click on the Export icon. The data from your stock code file will be imported (populated) into the spreadsheet.



	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R
1	SSTOCKCODI	WSTOCKTYP	SBARCODEN	SDESCRIPTIC	SMANUFACT	FQTYONHAN	FREORDERQ	FREORDERQ	FMINIMUMC	BAPPLYINVC	FSELLINGPRI	FSELLINGPRI	FSELLINGPRI	FUNITAVECO	FUNITCOST	FNETTOWEIC	FGROSSWEIC	SEXTRADES
2	3DRILL	0	123456789	Drill press	Bosch	5.00	10.00	5.00	4.00	1	1,000.00	1,100.00	1,200.00	500.00	500.00	0.00	0.00	850 Watts
3	3COMP	0	345678912	Compressor	CMP	3.00	10.00	4.00	0.00	1	1,500.00	1,600.00	1,700.00	1,000.00	1,000.00	0.00	0.00	
4	SALES	2		Sales		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5	PURCHASES	3		Purchases		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
6	SALES-NS	4		Sales (no stock)		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
7	4L-PAINT-E	4		Paint - Exterior		0.00	0.00	0.00	0.00	1	500.00	550.00	600.00	0.00	0.00	0.00	0.00	
8	4L-INSTCUP	4		Install - Built-in cupboarc		0.00	0.00	0.00	0.00	1	500.00	550.00	600.00	0.00	0.00	0.00	0.00	
9	GL-CODE	6		General ledger		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
10	OPTIONITEM	7		Option item		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
11	OPTIONITEM	8		Option item (no stock)		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
12	PURCHASES-	5		Purchases (no stock)		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
13	BOM	1		BOM		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	1,500.00	0.00	0.00	0.00	
14	BOMPRODU	9		BOM (Production)		0.00	0.00	0.00	0.00	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
15																		

6. You may add new stock items, edit the stock items, change the quantities, selling prices, whatever field, is necessary.

7. Once you are done, check the following options:

    a) Import check

    b) Profile

8. Click on the Save as... icon (View ribbon) to save the data in the "*Data Import Export*" spreadsheet as an "*Excel Workbook (*.xlsx)*" file.



9. Select the folder and enter a name for the file.

10. Click on the Save button.

11. Click on the Close icon in the titlebar of the "*Data Import Export*" screen.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Spreadsheet - Import - Stock items

This option will allow you to import your stock code file from a valid an Excel spreadsheet in the Excel Workbook (xlsx) file format. You may then add new stock items, edit existing stock items and import it back into your stock code file.

To import stock items from a Excel Workbook (xlsx) file:

1. Open the Set of Books in which, you wish to import stock items from a valid a spreadsheet export file.

2. On the Setup ribbon, select Import. The "*Import Data into osFinanacials*" screen is displayed:



3. Select Stock as the "*Data type to import*".

4. Click on the Excel import export button. The "*Data Import Export*" screen will be displayed with the column headings for the Stock items (without any data).



5. On the "*Data Import Export*" screen, click on the Open icon to select a valid Excel Workbook (*.xlsx) file.



You may click on the "Show preview pane" icon on the "Open" screen to display a preview of the selected file to open (import) in the "Data Import Export" screen..

6. The data of the Stock items included in the valid Excel Workbook (xlsx) file, will be imported (populated) into the spreadsheet ("*Data Import Export*" screen).



7. Click on the Import icon.



8. You may add new stock items, edit the stock items, change the quantities, selling prices, whatever field, is necessary.

9. Once you are done, check the following options:

    a) Import check

    b) Profile

    c) Import type -

7. Click on the Import icon.

Optional - Show data before import setting

The "ImportCheck" screen (if the Import the "Show data before import" option was selected (ticked) on the "Data Import Exp spreadsheet screen) is displayed:



Click on the All or OK buttons to start the import process.



	A	B	C	D	E	F	G	H	I	J	K	L	M
1	SSTOCKCODE	WSTOCKTYPEID	SBARCODEN	SDESCRIPTIC	SMANUFACT	FQTYONHAND	FREORDERQ	FREORDERQ	FMINIMUMQTY	BAPPLYINVO	FSELLINGPRICE1	FSELLINGPRI	FSELLIN
2	3DRILL	0	1234567890	Drill press	Bosch	10.00	10.00	8.00	6.00	1	1,000.00	1,100.00	1,2
3	3COMP	0	3456789123	Compressor	CMP	5.00	10.00	4.00	5.00	1	1,500.00	1,600.00	1,7
4	SALES	2		Sales		0.00	0.00	0.00	0.00	1	0.00	0.00	
5	PURCHASES	3		Purchases		0.00	0.00	0.00	0.00	1	0.00	0.00	
6	SALES-NS	4		Sales (no st		0.00	0.00	0.00	0.00	1	0.00	0.00	
7	4L-PAINT-E	4		Paint - Exter		0.00	0.00	0.00	0.00	1	500.00	550.00	€
8	4L-INSTCUP	4		Install - Bui		0.00	0.00	0.00	0.00	1	500.00	550.00	€
9	GL-CODE	6		General led		0.00	0.00	0.00	0.00	1	0.00	0.00	
10	OPTIONITEM	7		Option item		0.00	0.00	0.00	0.00	1	0.00	0.00	
11	OPTIONITEM-NS	8		Option item		0.00	0.00	0.00	0.00	1	0.00	0.00	
12	PURCHASES-NS	5		Purchases (i		0.00	0.00	0.00	0.00	1	0.00	0.00	
13	BOM	1		BOM		0.00	0.00	0.00	0.00	1	0.00	0.00	
14	BOMPRODUCTION	9		BOM (Produ		0.00	0.00	0.00	0.00	1	0.00	0.00	
15													

8. Once the import process is finalised, Column A will be in a green background colour.

9. Close the "*Data Import Export*" spreadsheet screen.

10. You may to the Default ribbon and select Stock items to edit the stock items, if necessary.

11. Go to the Reports ribbon and select Reports → Stock items → Stock item listing to check the stock items.

The data of the stock items is imported (populated) in thirty-four (34) columns in the spreadsheet, and is as follows:

		Field name	*Values*	*Comments*
	A	*SSTOCKCODE*	*Alpha-numeric (15-digits)*	*Stock item code*
	B	*WSTOCKTYPEID*	*Numeric*	*11 - Stock item types* *0 = Default (trading stock)* *1 = BOM* *2 = Sales* *3 = Purchases* *4 = Sales (no stock)*

				5 = Purchases (no stock) *6 = Financial entry* *7 = Option item* *8 = Option item (no stock)* *9 = BOM (Production)* *10 = Linked item (linked sale)*
	C	*SBARCODENUMBER*	*Alpha-numeric*	*Barcode number*
	D	*SDESCRIPTION*	*Alpha-numeric*	*Name or description of stock item*
	E	*SMANUFACTURER*	*Alpha-numeric*	*Name or description of manufacturer*
	F	*FQTYONHAND*	*Numeric*	*Name or description of contact*
	G	*FREORDERQTY*	*Numeric*	*Quantity re-order*
	H	*FREORDERQTYTRIG*	*Alpha-numeric*	*Quantity re-order warning*
	I	*FMINIMUMQTY*	*Alpha-numeric*	*Quantity re-order minimum*
	J	*BAPPLYINVOICEDISCOUNT*	*Alpha-numeric*	*Apply invoice discount:* *0 = No* *1= Yes*
	K	*FSELLINGPRICE1*	*Numeric (amount)*	*Selling price 1 amount*
	L	*FSELLINGPRICE2*	*Numeric (amount)*	*Selling price 2 amount*
	M	*FSELLINGPRICE3*	*Numeric (amount)*	*Selling price 3 amount*
	N	*FUNITAVECOST*	*Numeric (amount)*	*Average unit cost*
	O	*FUNITCOST*	*Numeric (amount)*	*Unit cost*
	P	*FNETTOWEIGHT*	*Numeric (number)*	*Nett weight*

	Q	*FGROSSWEIGHT*	*Alpha-numeric*	*Gross weight*
	R	*SEXTRADESC*	*Alpha-numeric*	*Extra description for stock item*
	S	*SEXTERNALID*	*Alpha-numeric*	*External id*
	T	*BDISABLED*	*Alpha-numeric*	*Stock item Disabled:* *0 = No* *1= Yes*
	U	*SSTOCKCODESUP1*	*Numeric*	*Supplier 1 Stock code*
	V	*SSTOCKCODESUP2*	*Numeric*	*Supplier 2 Stock code*
	W	*SUNIT*	*Numeric*	*Unit description*
	X	*SGROUP1*	*Alpha-numeric*	*Stock item group 1*
	Y	*SGROUP2*	*Alpha-numeric*	*Stock item group 2*
	Z	*SCOSTACCOUNT*	*Alpha-numeric*	*Cost of sales account code*
	AA	*SSALESACCOUNT*	*Alpha-numeric*	*Sales account code*
	AB	*SSTOCKACCOUNT*	*Numeric*	*Stock control account code*
	AC	*SINPUTTAX*	*Date*	*Input tax code T-*
	AD	*STAXCLASS*	*Alpha-numeric*	*Tax class description*
	AE	*SOUTPUTTAX*	*Alpha-numeric*	*Output tax code T-*
	AF	*SSUPPLIER1*	*Alpha-numeric*	
	AG	*SSUPPLIER2*	*Alpha-numeric*	
	AH	*OPTION*	*Alpha-numeric*	

The information for the Stock items, which will be exported, is:

- *Stock code*
- *Stock item type*
- *Barcode*
- *Description*
- *Quantity on hand*
- *Reorder quantity*
- *Apply invoice discount*
- *Selling price 1 amount*
- *Selling price 2 amount*
- *Selling price 3 amount*
- *Unit average cost amount*
- *Unit cost amount*
- *Unit description*
- *Stock group 1*
- *Stock group 2*
- *Cost of sales account*
- *Sales account code*
- *Stock account*
- *Input Tax account*
- *Output Tax account*

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's CHM Help File

Creation Features

Change stock code

To change the stock code:

1. Click on the Change stock code button (next to the "*Stock code*" field).
2. A confirmation message will be displayed.

> "Changing the stock code will result in all reports to use this code! Are you sure you want to change the code?"

> *Make absolutely sure that the correct stock item is selected.*

3. If you click Yes, the following screen is displayed:



4. Enter a new code for the Stock item.
5. Click OK.

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Change stock quantites

Quantities on hand may be changed on the Stock edit form; or on the Stock item list screen. You will be prompted to enter a remark (reason / note) for changing the stock quantity on hand.

Change Quantity on hand - Stock edit form

Select the stock item and click on the Ledger tab.



If you change the "Quantity on hand" field on the Ledger tab, and you click on the Save button, a confirmation message is displayed:

> "Stock quantity has been changed! Do you want to retain the current database data?"

If you click on the Yes button, the Stock quantity on hand value will not be changed. It will revert to the old values.

To change the value with the new one entered in the "*Quantity on hand*" field, you need to click on the No button. The "*Change remark*" screen is displayed:

Enter a remark (comment) and click on the OK button.

Change quantity on hand - Stock item grid

To be able to edit the values of the number of inventory items "On hand" column, you must select the Advanced mode, so that you can edit the data as in a spreadsheet.

If you change the values of the stock quantity on hand in the quantity on hand column of the "*Stock item list*" screen, the confirmation message will not be displayed:

"Stock quantity has been changed! Do you want to retain the current database data?"



Once you have entered (changed) the quantity in the "*Quantity on hand*" column , the "*Change remark"* screen is displayed:

Enter a remark (comment) and click on the OK button.

View - Change remarks on Stock item tabs

The remark as entered on the "*Change remark*" screen will be displayed in the Document groups and Transactions tabs of the stock item.

The Document no. for a remark is automatically generated as a seven-digit number (consisting of a prefix ST followed by 5 numerical digits).

The Document type is "Stock-"

Document groups tab



Date	Items	Document no.	Description	Price	Discount	Exclusive	Inclusive	Unit price	Units	Descriptio	Number	Name	Document ty	Posted
2022/06/01	-1	ST00005	Stock surplus	0.00				0.00				Empty	Stock-	1
2022/06/01	1	ST00006	Stock shortage	0.00				0.00				Empty	Stock-	1
2022/04/16	-5	ST00004	Auto correction	0.00				0.00				Empty	Stock-	1
2021/06/30	2	IN000021	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ABGRE	Mr. AB Green	Invoice	0
2021/06/30	2	IN000022	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ABGRE	Mr. AB Green	Invoice	0
2021/06/30	2	IN000020	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ABGRE	Mr. AB Green	Invoice	1
2021/06/30	2	IN000019	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ABGRE	Mr. AB Green	Invoice	1
2021/06/30	2	CR000001	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ABGRE	Mr. AB Green	Credit notes	1
2021/06/30	1	CR000003	Drill press	1000.00	0	1000.00	1150.00	1000.00	1	Each	1ABGRE	Mr. AB Green	Credit notes	1
2021/06/26	3	PU000005	Drill press	500.00	0	1500.00	1725.00	500.00	1	Each	2AONES	A-ONE Suppliers	Purchases	1
2021/06/26	3	SR000004	Drill press	500.00	0	1500.00	1725.00	500.00	1	Each	2ABCOS	ABC-Office-Supplies	Purchases	1
2021/06/25	3	PU000007	Drill press	500.00	0	1500.00	1725.00	500.00	1	Each	2ABCOS	ABC-Office-Supplies	Purchases	1
2021/06/24	2	QU000005	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ABGRE	Mr. AB Green	Quotes	0
2021/06/24	2	IN000018	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ROGSM	Mr. Roger Smith	Invoice	1
2021/06/22	2	CR000002	Drill press	1000.00	0	2000.00	2300.00	1000.00	1	Each	1ROGSM	Mr. Roger Smith	Credit notes	1
2021/06/20	1	QU000004	Drill press	1000.00	0	1000.00	1150.00	1000.00	1	Each	1ROGSM	Mr. Roger Smith	Quotes	0
2021/06/20	1	IN000017	Drill press	1000.00	0	1000.00	1150.00	1000.00	1	Each	1MDAVI	Mr. Mike Davies	Invoice	1
31	37.00					40,000.00	46,000.00							

Transactions tab



Date	Items	Cost price	Selling price	Document row	Document no.	Reference	User	Cum	id	Posted	Document type
2022/06/01	1	0.00	500.00	1	ST00005	Stock surplus		11	56	1	Stock-
2022/06/01	-1	0.00	500.00	1	ST00006	Stock shortage		10	57	1	Stock-
2022/04/16	5	0.00	500.00	1	ST00004	Auto correction		10	54	1	Stock-
2021/06/30	1	500.00	1,000.00	2	CR000003	C-103		9	42	1	Credit notes
2021/06/30	-2	500.00	1,000.00	0	IN000019	D-101		7	27	1	Invoice
2021/06/30	-2	500.00	1,000.00	2	IN000020	A-103-2		5	30	1	Invoice
2021/06/29	2	500.00	1,000.00	0	CR000001	D-101		8	38	1	Credit notes
2021/06/26	3	500.00	500.00	0	PU000005	4562		9	33	1	Purchases
2021/06/26	-3	500.00	500.00	0	SR000004	4562-A		6	55	1	Purchases
2021/06/25	3	520.00	500.00	0	PU000007	4562		6	52	1	Purchases
2021/06/24	-2	500.00	1,000.00	0	IN000018	D-102		3	26	1	Invoice
2021/06/22	2	500.00	1,000.00	0	CR000002	D-102		5	40	1	Credit notes
2021/06/20	-1	500.00	1,000.00	2	IN000017	C-103		3	25	1	Invoice
2021/06/19	-3	500.00	500.00	0	SR000003	4562		4	37	1	Purchases
2021/06/17	-3	500.00	500.00	0	SR000002	4562		7	36	1	Purchases
2021/06/15	-1	500.00	1,000.00	0	IN000015	D-101		10	22	1	Invoice
2021/06/12	-2	500.00	1,000.00	0	IN000014	D-102		11	21	1	Invoice
24	5										

Open a Posted document

On the Document groups and Transactions tabs, for stock items of which stock quantities is changed; you may right-click and select the "*Open document*" option on the context menu to open a selected posted document.



The remark entered for the changed quantity on hand will be added in the "*Your reference*" field of the Document header.

Print a Posted document

On the Document groups tab, for stock items of which stock quantities is changed; you may may double-click to print a selected posted document.



The default document layout file which will be used to print documents generated by the changed quantities of stock items, is of-sale" selected in Setup → Documents setup.



Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Backorders

What is backorders?

Backorders refer to customer orders that cannot be fulfilled immediately due to a lack of available inventory or stock. When a customer places an order for a product or service that is currently out of stock or unavailable, the business may choose to accept the order and create a backorder. This allows the customer to secure their place in line and receive the product or service once it becomes available again.

Here are some key points about backorders:

1. Customer order fulfilment: Backorders are used as a mechanism to manage customer orders when the requested products or services are temporarily unavailable.
2. Reservation of Stock: When a backorder is created, the business reserves the requested quantity of items for the customer. This ensures that the stock is set aside for that specific order, and the

customer will receive it once it becomes available again.

3. Communication with customers: It is crucial for businesses to communicate with customers regarding their backorders. Customers should be informed about the estimated availability date, any potential delays, and alternative options if applicable.

4. Inventory management: Backorders provide valuable insights into demand for products or services. They help businesses track and anticipate customer needs, allowing for better inventory management and planning.

5. Order prioritization: Backorders are typically fulfilled on a first-come, first-served basis. However, businesses may have internal policies or priority systems to determine the order in which backorders are fulfilled, especially if there are limited quantities available.

6. Impact on financials: Backorders may have implications for revenue recognition and financial reporting. Depending on the accounting principles or standards applied, revenue from backordered items may be recognized at the time of shipment or when the customer is invoiced.

By managing backorders effectively, businesses can maintain customer satisfaction, optimize inventory management, and meet customer demands even when immediate fulfilment is not possible.

Backorders when processing invoices and quotes

If there are insufficient quantities of an item in stock to fulfil an order, the system will automatically calculate the shortage quantity (e.g., 10 - 2 = 8, as per this example) and add it to the backorder feature.



When processing invoices and quotes in osFinancials5/TurboCASH5, you have the option to click on the Backorder icon.

This allows you to edit backorders associated with the transaction being processed.

When processing a new invoice for a debtor (customer/client) account that has outstanding backorders, the "*Backorders*" screen will be automatically displayed. In this screen, you can review and manage the backordered items associated with the customer.



If you select an item by ticking the "*Selected*" field, the system will update the transferred document line accordingly. The selected item will be removed from the backorder records and reports, indicating that it has been successfully transferred to the document line for invoicing or quoting purposes.

This functionality allows for efficient management of backorders during the invoice and quote processing workflow in osFinancials5/TurboCASH5. By selecting and transferring items from the backorder records to the relevant document lines, you can ensure accurate and up-to-date tracking of inventory and timely fulfilment of customer orders.

Option to manage backorders

In osFinancials5/TurboCASH5, the management of backorders is facilitated through various options and screens. Here is a breakdown of how backorders can be added, edited, and accessed from the Default ribbon within osFinancials:

1. Edit → Backorders menu - You can edit, or delete backorders associated with specific stock items and debtor (customer/client) accounts. When adding new backorders, you may select the stock items and debtor (customer/client) accounts.

2. Stock items (Backorders tab) - This tab allows you to manage backorders for individual stock items. You can edit, or delete backorders associated with specific stock items and debtor (customer/client) accounts. When adding new backorders, you may select the debtor (customer/client) accounts.

3. Debtors (Backorders tab - This tab enables you to manage and track backorders for specific debtor accounts. You can edit, or delete backorders associated with specific stock items and debtor (customer/client) accounts. When adding new backorders, you may select the stock items.

These functionalities within osFinancials5/TurboCASH5 provide tools for managing backorders, allowing you to track, modify, and remove backorder items as needed. The backorder records and reports assist in monitoring outstanding orders and ensuring proper fulfilment when stock becomes available.

Backorder reports

Backorder reports may be printed on the Reports → Stock→ Backorder menu on the Reports ribbon. This Backorder report provides a detailed overview of the items on backorder, their associated customer accounts, quantities, pricing information, and any applicable discounts. It allows businesses to track and manage their backorder items effectively, aiding in inventory management and order fulfilment.

By utilising the Backorder report in osFinancials5/TurboCASH5, businesses can stay informed about the status of backorder items, make informed decisions, and take necessary actions to fulfil customer orders promptly.

Edit → Backorders menu (Default ribbon)

This Backorders option on the Edit menu enables you to manage manage and track backorders for specific debtor accounts. You can edit, or delete backorders associated with specific stock items and debtor (customer/client) accounts. When adding new backorders, you may select the stock items and debtor (customer/client) accounts.



Debtors - Backorders tab (Default ribbon)

This tab enables you to manage manage and track backorders for specific debtor accounts. You can edit, or delete backorders associated with specific stock items and debtor (customer/client) accounts. When adding new backorders, you may select the stock items.

You can add, edit, and delete backorders, as well as adjust quantities, prices, and discounts as necessary. This helps ensure accurate tracking and fulfilment of customer orders.



Sorting and Rearranging Columns:

- *You can click on the column headings (such as Stock item, Description, Unit, Items, Discount, Stock, Referral source, Selling price, Price, and Exp. Selected) to change the sort sequence from ascending to descending order.*
- *To rearrange the sequence in which the columns are displayed, you can click and drag any of the column headings to the left or right.*

Adding, Editing, and Deleting Backorders:

- Within the Debtors - Backorders tab, you have the ability to add new backorders, edit existing backorders, or delete backorders as needed.
- Clicking the New button allows you to add a new backorder item, while the Edit button enables you to modify a selected backorder.



If the Backorders screen is launched from Input → Documents → Backorders, both the Debtor as well as the Stock item will be displayed. You may select them, if necessary.

Click on the New button to add a new backorder item or on the Edit button to edit a selected backorder. The fields are as follows:

- Stock item – For existing backorders, the stock item code and description will be displayed. For new backorders, you can select the stock item.
- Items – The quantity field is automatically populated as the difference between the quantity entered in the "*Order*" field and the quantity entered in the "*Ship*" field of documents. For new backorders, you can enter the quantity.
- Recalculate selling price – Clicking this button will clear the discount percentage and recalculate the selling price to the original selling price (Price).

- Selling price and Price – These fields represent the price per item. The Selling price reflects the amount after the discount percentage, while the Price excludes any discount.

> *The Selling price and Price displayed is the prices for a single item.*

- Discount – The discount will be displayed if a percentage is entered in the "*Customer discount*" field on the Accounting information tab of the debtor account and the "*Apply invoice discount*" field is selected on the Stock Items (Default ribbon).

- Stock – This field displays the quantity of stock items on hand. This is the quantity of the "*Exp. Selected*" column on the Backorders tab - List view) displays the quantity of stock items on hand. The quantities in this field are updated when documents are posted to the ledger (e.g., credit notes, purchases, and supplier returns) or when stock item adjustments are made.

- Unit - The Unit description of the stock item.

- Description - To be advised.

- Referral Source – The Referral Source field will automatically be updated with the invoice number if the quantity entered in the "*Order*" field exceeds the quantity entered in the "*Ship*" field.

Stock items - Backorders tab (Default ribbon)

This tab allows you to manage backorders for individual stock items. You can edit, or delete backorders associated with specific stock items and debtor (customer/client) accounts. When adding new backorders, you may select the debtor (customer/client) accounts.



Adding, Editing, and Deleting Backorders:



Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

Batches (Journals)

What are Journals (Batches) and the Role of Source Documents?

Journals, also known as batches, are a fundamental concept in accounting. They refer to a chronological record of financial transactions that are systematically recorded in the accounting system. Journals serve as the initial entry point for capturing and documenting the details of each transaction before they are posted to the general ledger.

One crucial aspect of maintaining accurate journals is the use of source documents. Source documents are original records or paperwork that provide concrete evidence of a financial transaction. These documents play a pivotal role in the accounting process, as they support and validate the entries made in journals. Here's how source documents fit into the journaling process:

1. Source Documents: Whenever a financial transaction occurs, it generates a source document. These documents can take various forms, such as invoices, receipts, purchase orders, contracts, bank statements, and more. Source documents contain essential information about the transaction, including the parties involved, the date, the nature of the transaction, and the monetary amount.

2. Recording in Journals: Accountants use these source documents as the basis for creating journal entries. Each transaction is meticulously recorded in the appropriate journal, ensuring that all relevant details from the source document are accurately transcribed. The columns in the journal capture key information, such as the date of the transaction, the accounts involved (debit and credit), a description of the transaction, and the monetary amount.

Types of Journals:

> *Various types of journals exist, each designed for specific transaction types. Common examples include the Sales Journal, Purchases Journal, Cash Receipts Journal, Cash Payments Journal, and General Journal. Specialised journals may also be used for specific transactions, such as the Payroll journal or Inventory journal.*

3. Batch Processing: Entries within a journal are often processed and posted collectively as a batch. This batch processing approach helps streamline the accounting process and ensures that transactions are recorded accurately and efficiently. Batch processing is especially useful when dealing with a high volume of transactions.
4. Posting to the General Ledger: After recording transactions in the appropriate journals, the entries, along with their supporting source documents, are transferred or posted to the general ledger. This step summarizes the journal entries and updates the account balances in the general ledger accounts.
5. Audit Trail: Source documents, along with the journal entries they support, provide an essential audit trail. This audit trail allows accountants and auditors to trace and verify the accuracy and completeness of transactions recorded in the accounting system. It serves as supporting documentation for financial statements and facilitates reconciliation and analysis.

By incorporating source documents into the accounting process and maintaining organized and accurate journals, businesses can effectively track and analyse their financial transactions, ensure compliance with accounting principles, and generate reliable financial statements.

What is the purpose of source documents and journals?

The purpose of source documents and journals in accounting is to maintain an accurate and systematic record of financial transactions and events in a business. Here is a more detailed explanation of the purpose of these elements in the accounting process:

1. Origin of Transactions: Source documents, such as invoices, receipts, bank statements and contracts, serve as the original information indicating when a financial transaction took place. These documents help to maintain a transparent trail of all financial activities.
2. Proof of Transactions: Source documents serve as proof of the actual transactions that have taken place in a business. This is important for proving income, expenses and other financial events, especially for tax purposes and financial reporting.
3. Ledger Entries: Journals are where financial information from source documents is entered into the ledger of a business. These entries are essential to maintaining an organized and structured accounting system, such as osFinancials5/TurboCASH5.
4. Preparation of Financial Statements: Source documents and journals serve as the basis for the

preparation of financial statements, such as the balance sheet, income statement and cash flow statement. These financial statements provide an overview of the financial health and performance of a business.

5. Tax compliance: Source documents are essential to comply with tax obligations. This includes the proof of income, expenses, and deductions required by the tax authorities to process tax applications.
6. Decision Making and Analysis: Financial information provided by source documents and journals helps managers make decisions about the financial strategy of an enterprise. This enables them to evaluate the financial performance and determine future goals.

In a nutshell, the purpose of source documents and journals is to maintain an orderly and faithful record of financial activities, which is essential for management, financial reporting and compliance with legal requirements. These elements form the backbone of an efficient accounting process and contribute to the transparency and credibility of a company's financial information.

What is the importance of source documents and journals?

Source documents and journals play a critical role in the field of accounting, and their importance cannot be underestimated. Here are some reasons why source documents and journals are so important in accounting:

1. Compliance with Financial Rules and Regulations: Accounting source documents, such as invoices, receipts and bank statements, serve as proof of financial transactions. These documents are essential to ensure that a business complies with the financial rules and regulations.
2. Accurate Financial Reports: Source documents are the basis on which financial reports, such as a balance sheet and an income statement, are drawn up. Journals are used to record the information from these documents in the ledger of the business. This ensures an accurate registration of financial events.
3. Tax returns: Income tax returns, Tax (VAT/GST/Sales tax) returns and other tax obligations require a careful record of income, expenses and deductions. Source documents are essential to substantiate the fidelity of this information.
4. Financial Analysis: Financial analysts and managers use source documents and journals to evaluate the financial health of a business. These documents provide a clear picture of the company's performance and financial position.
5. Decision Making: Managers use financial information provided by source documents and journals to make decisions about the future of a business. This information can help determine strategies and set financial goals.

6. Forensic Investigation: In cases of financial malpractice, fraud or corruption, source documents can play a critical role in forensic investigations. These documents serve as evidence to prove irregularities.

In short, source documents and journals are indispensable in the world of accounting to maintain an accurate and reliable record of financial transactions. These documents not only ensure that a business meets legal requirements, but also play a central role in the management and analysis of accurate financial information.

Journal (Batch) Feature in osFinancials

The Batch Entry / Journal Entry feature in osFinancials5/TurboCASH5 provides versatile functionality for creating customized batch or journal types tailored to your specific requirements. These batch types enable structured transaction organization, ensuring precise allocation to the appropriate ledger and debtor accounts. Here's an overview of this feature:

1. Batch Types Customization: In osFinancials5/TurboCASH5, you can define various batch types to match your unique needs. While many Sets of Books and templates include standard basic batches like sales journal, purchase journal, payments journal, receipts journal, and general journals (accessible through the "*Let osFinancials help you to create a Set of Books?*" option), osFinancials5/TurboCASH5 allows unlimited specific batch types. Examples of specialise journals, include Payroll journals, Depreciation journals, Fixed assets journals, Accrual journals, or any custom type necessary. Each batch type is designed for specific transaction categories or sets of related transactions, granting precise control over your accounting processes.
2. Batch / Journal Configuration: The Batch Entry / Journal Entry feature offers options to configure settings, reducing errors during batch transaction entry and processing: Journal configuration: The Standard tab and Advanced tab in the "*Options for this batch*" offer several options to configure default settings such as the default Contra account, Tax (VAT/GST/Sales tax) settings and other parameters for each type of journal. Configuring these settings, which reduce errors when processing transactions in journals:
    - Contra Account: Assign each batch (journal) to a specific contra account for easy identification and assignment of transactions to the corresponding contra account. This account will be the balancing account. When you balance the batch, the contra transactions will be generated to this contra account in the journal.
    - Lookup Accounts Configuration: You can set a journal so that you can select all accounts for the general ledger, debtors, creditors or only accounts for the general ledger or only debtors or only creditors in the journal. So for example, in the Sales journal you can choose to list only the debtor accounts in the Lookup and can choose when you enter invoices in the Sales

journal. This speeds up the allocation of transactions so that only the relevant account type can be listed and selected.

3. Open Item Transactions: This is particularly useful for matching receipts or payments transactions with outstanding amounts. When you allocate transactions against open item accounts, you can choose to link the transactions against outstanding transactions. Link specific transactions to open item accounts for extra accuracy. This is especially useful for linking receipts or payment transactions with outstanding amounts. For example, when a payment is received from a debtor, you can assign the payment to a specific outstanding invoice.

4. Repeating Transactions: The Repeating transactions feature allows you to enter transactions occurring on a periodic basis (weekly, monthly, quarterly, annually, etc.). Enter transactions once in the Edit → Repeating transactions menu and, when due, process them into the standard batch, edit (if amounts have changed), delete, or add an entry. This time-saving feature simplifies recurring transaction handling.

5. Export and Import Feature: Export posted or unposted batches using delimited file options. osFinancials5/TurboCASH5 also supports Spreadsheet export and Spreadsheet Import options for batch transactions:

    - Posted Batches: Use the "Import a posted batch" option (F9:Process) of the "*Batch entry*" screen to select a posted batch on the Posted batches tab for import.

    - Spreadsheet Import/Export: osFinancials5/TurboCASH5 supports Excel Workbook (*.xlsx) file type Spreadsheet import and export features. You can export unposted batch transactions and save them as Excel Workbook files, or import batch transactions from saved Excel Workbook files.

    - Unposted Batches: Export batch transactions using the "Write delimited file" option (F9:Process) to create a Comma Separated Value (.csv) file. Import batch transactions via the "Delimited file import" option (F9:Process) by selecting the Comma Separated file (.csv) file.

6. Ledger Updates: You don't need to post or update transactions in batches every time. Close a batch and reopen it as needed to add or edit transactions. When finalizing batch processing and posting to the ledger, osFinancials5/TurboCASH5 automatically updates ledger accounts, including debtor and creditor accounts where applicable. This ensures financial statements, such as the trial balance, balance sheet and the income statement including relevant reports accurately include and reflect these transactions.

By utilizing the Batch Entry / Journal Entry feature in osFinancials5/TurboCASH5, you can efficiently manage and allocate transactions across various batch types, maintaining accurate and up-to-date accounting records with precision.

Which journals (batches) is included in osFinancials5/TurboCASH5 template Sets of Books?

In osFinancials5/TurboCASH5, the template Sets of Books include various subsidiary journals or books of prime entry (also known as batches) to facilitate the recording and summarization of transaction details. These journals help ensure accurate and organized financial data. Here are the subsidiary journals typically included in osFinancials5/TurboCASH5 template Sets of Books:

1. Sales Journal: Used for recording and processing of sales invoices and credit notes generated internally within the business. The Sales Journal is typically used to record and process invoices and credit notes for customers.
2. Purchases Journal: Used for recording supplier invoices and credit notes received from external suppliers.
3. General Journal: Used for recording miscellaneous non-routine or unusual transactions that do not fit into the other subsidiary journals. This journal provides flexibility for recording various types of transactions, including corrections of errors. If there is no specific journal available for a particular type of transaction, using the general journal is a suitable option.
4. Bank accounts:- By default if the "*Default bank reconciliation*" option is selected (on the Setup → System parameters menu on the Setup ribbon), osFinancials5/TurboCASH5 will create two journals for each Bank account.
    - Receipts Journal: Used for recording deposit slips, receipts, or copies of incoming payments received internally.
    - Payments Journal: Used for recording cheque counterfoils or copies of outgoing payments made internally.
5. Petty Cash Journal: Used for recording petty cash vouchers and associated expenses incurred internally.

In many Sets of Books available as a free download, the following batch types or journal types is also included:

By default if the "Default bank reconciliation" option is selected (on the Setup → System parameters menu on the Setup ribbon), osFinancials5/TurboCASH5 will create two journals for each Bank account.

- *Receipts Journal: Used for recording deposit slips, receipts, or copies of incoming payments received internally.*
- *Payments Journal: Used for recording cheque counterfoils or copies of outgoing payments*

made internally.

However, whenever there is a specialized journal available for a specific type of transaction, it is recommended to use that journal to ensure accuracy and efficiency in record-keeping. This helps maintain consistency and allows for easier analysis and reporting of transactions within their relevant categories.

In many Sets of Books available as a free download, the following batch types or journal types is also included:

- *Cost of Sales journal: Used for recording the costs directly associated with the production or acquisition of goods sold by a business. It is an important journal in the accounting process, specifically for businesses that deal with stock items or inventory or the sale of physical products.*
- *POS journal: Used in osFinancials5/TurboCASH5 to integrate with the point-of-sale (POS) systems. It is designed to record sales transactions that occur directly at the point of sale, typically in retail or hospitality businesses where goods or services are sold to customers in-person.*

Each subsidiary journal is designed for specific transaction types, and they are utilised to record the relevant source document information accurately. By debiting specific accounts and crediting specific accounts applicable to each subsidiary journal, errors can be minimized or eliminated during the recording and summarisation of transactions before they are posted to the ledger.

These subsidiary journals in osFinancials5/TurboCASH5 assist in organising and categorizing transaction data, providing an efficient workflow for entering and summarising transactions before they are integrated into the general ledger and further financial reporting processes.

Adding specialized customized journals

In osFinancials5/TurboCASH5, you have the option to add specialized customized journals to record and process transactions that are distinct from the general journal. This provides flexibility and allows for better organization and visibility of specific types of transactions. Here is how you can utilize customized journals in osFinancials5/TurboCASH5:

1. Default journals: osFinancials5/TurboCASH5 comes with a range of default journal types, including the sales journal, purchase journal, general journal, payments journals, and receipt journals. These default journals are, making it convenient to record and process transactions related to sales, purchases, and general entries. Each Payments journal, and Receipt journal is automatically linked to bank accounts or petty cash accounts.
2. Custom journal types: In addition to the default journals, osFinancials provides you with the flexibility to add custom journal types that align with your specific requirements. By accessing the Setup → Batch types menu on the Setup ribbon, you can define and configure custom journal types to create

dedicated journals for various specialized transactions or categories relevant to your business. Here are some examples of additional custom journal types you can create:

- Payroll journal: This journal type can be used specifically for recording payroll entries, including salary expenses, tax withholdings, benefits, and other related transactions. It allows for accurate tracking and reporting of payroll-related costs.
- Fixed assets journal: By creating a custom journal type for fixed assets, you can record transactions related to asset acquisition, depreciation, disposals, and any other changes in the fixed asset register. This ensures proper tracking of asset values and facilitates compliance with accounting standards and regulatory requirements.
- Accruals journal: An accruals journal can be used to record accrual-based adjustments, such as recognizing revenue or expenses that have been incurred but not yet recorded in the general ledger. This journal type helps ensure accurate matching of revenues and expenses in the appropriate accounting periods.
- Inventory adjustment journal: This journal type allows for the recording of inventory adjustments, such as write-offs, write-downs, and any changes in the quantity or value of inventory items. It helps maintain accurate inventory records and supports proper valuation of inventory on the financial statements.
- Inter-company transactions journal: If your business has multiple entities or subsidiaries, you can create a custom journal type for inter-company transactions. This journal would be dedicated to recording transactions between different entities within your organization, ensuring proper consolidation and elimination of inter-company balances.

These are just a few examples, and you can create custom journal types for any other specialized transactions that are specific to your business needs. By utilizing custom journal types, you can accurately record and track various transactions, maintain better control and organization, and generate meaningful financial reports for decision-making and compliance purposes.

3. Configuration Options: Each custom journal type can be customized with various configuration options. This includes defining contra accounts, specifying account and tax lookup settings, and utilising the standard and advanced options. These configurations ensure accuracy in recording specific transactions and provide consistency in the accounting treatment across your Set of Books.
4. Access Control: If you have multiple users working in a Set of Books on osFinancials5/TurboCASH5, you can control their access to process transactions in specific journals. The Setup → Access control menu, specifically the Batches access tab, allows you to grant or restrict access to users for processing transactions in specific journals. This helps enforce segregation of duties and maintain data integrity within your accounting system.

By leveraging customized journals, you can tailor your journaling process to match your specific business needs. This level of customization enhances accuracy in recording transactions, improves organization, and provides better visibility of different transaction types. It allows for a more efficient and controlled accounting system, ensuring compliance and facilitating effective financial management.

===

Before you can enter your transactions in a batch (journal), you need to sort your source documents according to the type or nature of the transactions. You then need to select the correct batch or journal to capture the transactions of a similar nature. You may select a batch type from the available batch types (journals) in which you enter your transactions from source documents.

Any business issues source documents and hands the original documents to its customers or debtors or other parties with whom a transaction is concluded. These source documents are generated internally and the copies of such source documents are used to enter the transactions in the journals or batch types.

On the other hand a business receives original source documents from its suppliers or creditors or any other party with whom a transaction is concluded. These source documents are generated externally and the business would usually receive the original source documents, which are then used to enter the transactions in the journals or batches.

Batch types (journals) are used to enter the details of the transactions and to summarise the details into.

===

In any business the transaction data on source documents are entered in the following subsidiary journals or books of first entry:

In accounting, a journal is a record of financial transactions that have been entered in chronological order. It is used as a book of original entry, meaning it is the first place transactions are recorded before being posted to the general ledger.

Journals are important because they provide a complete record of all financial transactions and help ensure accuracy in financial reporting. They can also be used for auditing purposes and for generating financial statements.

There are many different types of journals, including the general journal, sales journal, purchase journal, and cash receipts journal. Each journal is used to record specific types of transactions, and the information recorded in each journal is then posted (updated) to the appropriate accounts in the general ledger.

Before you can record your transactions in a batch, you'll need to organise your source documents by transaction type. Once you've done that, you can select the appropriate batch type or journal to enter transactions of a similar nature. You can only choose from the batch types available to you when entering your transactions from source documents.

Every business generates internal source documents and provides the original documents to customers, debtors, or other parties involved in the transaction. Copies of these source documents are used to record transactions in the journals or batch types.

Likewise, a business receives external source documents from suppliers, creditors, or other parties involved in the transaction. The original source documents are typically received by the business and used to record transactions in the journals or batch types.

Batch types (journals) are used to enter transaction details and summarise them. In any business, the transaction data on source documents is entered in subsidiary journals or books of first entry or original entry any business the transaction data on source documents are entered in the following subsidiary journals:

Source document	*Internal / External*	*Subsidiary Journal / Books of first entry*
Sales invoices (copies)	*Internal*	*Sales journal*
Credit notes (copies)	*Internal*	*Sales journal or Sales returns journal*
Supplier invoices (originals)	*External*	*Purchases journal*
Credit notes (originals)	*External*	*Purchases journal or Purchase returns journal*
Deposit slips or Receipts (copies)	*Internal*	*Receipts Journal*
Cheque counterfoils /	*Internal*	*Payments Journal*
Petty cash vouchers	*Internal*	*Petty Cash Journal*
Miscellaneous	*Internal*	*General Journal*

For each of these subsidiary journals or books of prime entry, you would debit specific accounts and credit specific accounts applicable to the specific subsidiary journal. This will definitely help to eliminate or significantly reduce the errors that may occur when recording and summarising the transactions or when transactions are posted to the ledger.

The entries for each of these subsidiary journals or books of prime entry are as follows:

Subsidiary journal	*Account(s) Debited*	*Account(s) Credited*
Sales journal	*Debtor's control*	*Sales*

Sales returns journal	*Sales*	*Debtor's control*
Purchase journal	*Stock control or sundry account.*	*Creditor's control*
Purchase returns journal	*Creditor's control*	*Stock control or selected account.*
Receipts journal	*Bank*	*Receipts journal*
Payments journal	*Creditor's control or sundry account.*	*Bank*
Petty cash journal	*Expense account*	*Petty cash payments journal*
General journal	*Selected accounts*	*Selected accounts*

The General Journal is used for other transactions which cannot be classified into any of the transactions that are entered into the subsidiary journals listed above.

===

What is the general journal used for?

The general journal is a book or computer program used in accounting to record all transactions in chronological order. It is also known as the "journal" or "journal entry book".

Each transaction recorded in the general journal includes a date, a brief description of the transaction, the accounts involved, and the amounts debited or credited. These transactions are then later transferred to the appropriate ledgers for posting and summarization.

The general journal is used to record a wide range of transactions, such as sales, purchases, expenses, and other financial transactions. It is also used to record adjusting entries and closing entries at the end of an accounting period.

By recording all transactions in the general journal, a business can keep a complete and accurate record of its financial activities. This information is then used to prepare financial statements and to analyze the financial performance of the business. The general journal is an essential tool for any business that wants to maintain accurate financial records and make informed decisions about its financial activities.

The document types is already linked to the batch types in Setup → Document setup (Setup ribbon). The batch types linked to the documents, is as follows:

Invoices - Sales journal

Credit notes - Sales journal

Purchases - Purchase journal

Supplier returns - Purchase journal

When should a general journal not be used?

A general journal should not be used in certain situations where there are specific journals designed for recording transactions. For example:

- Sales: For recording sales, specialised journals like the sales journal should be used. To record sales transactions in osFinancials5/TurboCASH5, you can use the sales journal available in the Batch entry section of the Default ribbon. The sales journal allows you to enter and manage sales-related transactions effectively.

  In addition to the sales journal, you can process invoices and credit notes using the Documents section on the Default ribbon. Invoices and credit notes can be linked to the sales journal in Setup → Documents setup (Setup ribbon). When you process invoices and credit notes, the source documents will be automatically generated, allowing you to have physical or digital copies of these documents for record-keeping purposes. These documents can be printed and reprinted as needed, enabling you to send them to your debtors (customers/clients) as required.

  Once the invoices and credit notes are updated and posted to the ledger, the corresponding transactions will be automatically processed in the sales journal. Each item included in the invoice or credit note will be recorded in the sales journal, ensuring accurate tracking of your sales transactions.

  By utilising the sales journal and linking invoices and credit notes, you can efficiently manage and maintain a comprehensive record of your sales activities in osFinancials5/TurboCASH5.

- Purchases: For recording purchases, specialised journals like the purchase journal should be used. To record purchase transactions in osFinancials5/TurboCASH5, you can use the purchase journal available in the Batch entry section of the Default ribbon. The purchase journal allows you to enter and manage purchase-related transactions effectively.

  In addition to the purchase journal, you can process purchase and supplier return documents using the Documents section on the Default ribbon. Purchases and supplier return documents can be linked to the purchase journal in Setup → Documents setup (Setup ribbon). When you process purchase and supplier return documents, the source documents will be automatically generated, allowing you to have physical or digital copies of these documents for record-keeping purposes. These documents can be printed and reprinted as needed, enabling you to send them to your creditors (suppliers/vendors) as required.

  Once the purchase and supplier return documents are updated and posted to the ledger, the corresponding transactions will be automatically processed in the purchase journal. Each item included in the purchase and supplier return documents will be recorded in the purchase journal, ensuring

accurate tracking of your purchase transactions.

By utilising the purchase journal and linking purchase and supplier return documents, you can efficiently manage and maintain a comprehensive record of your purchase activities in osFinancials5/TurboCASH5.

- Cash transactions: To record cash transactions in osFinancials5/TurboCASH5, specialised journals such as the cash receipts journal and cash disbursements journal are used. In osFinancials5/TurboCASH5, when setting up bank accounts and petty cash accounts in the Setup → Accounts menu of the Setup ribbon, each account will be associated with its own unique payments journal and receipts journal.

  If the Bank import plugin is not activated in osFinancials, you can manually process cash transactions in the respective payments journal and receipts journal associated with the bank account or petty cash account. To access these journals, you can go to the Batch entry option on the Default ribbon.

  If the Bank import plugin is activated, you have the option to process and import transactions directly into the payments journal and receipts journal associated with the bank account or petty cash account. This can be done through the Cash/Bank entry option on the Default ribbon.

  By using the appropriate journals for cash transactions, you can effectively record and manage your cash receipts and disbursements. The journals allow for accurate tracking of cash flows, providing a clear overview of your financial activities.

  Please note that the availability and functionality of specific features may depend on the configuration and settings of your Set of Books in osFinancials5/TurboCASH5.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin is included with the osFinancials5/TurboCASH5 Business Class license, meaning you have access to it without any additional cost or separate license requirement.

With the plugin, you can download bank statement files from your online banking app or portal provided by your bank or financial institution. These files can be imported into the appropriate bank accounts (cash books) in osFinancials5/TurboCASH5.

You can download statements for multiple bank accounts and credit cards, as long as you have them linked to your online banking. Each bank account or credit card should have its corresponding Payments and Receipts journals set up in osFinancials5/TurboCASH5.

Importing the bank statements automatically populates the transactions into the Payments and Receipts columns, saving you time and reducing the risk of errors associated with manual entry.

The plugin offers a user-friendly interface with context menus that make it easy to locate, select, and

search for specific transactions, debtors, creditors, or general ledger accounts. This simplifies the navigation and management of your bank transactions.

You can link debit transactions to credit transactions and vice versa, allowing for accurate tracking of outstanding balances and efficient management of payments and receipts. You can also link a portion of a payment or receipt to multiple outstanding transactions if needed.

Additionally, the plugin allows you to link accounts to specific debtors, creditors, or general ledger accounts. This ensures that subsequent bank statement imports automatically allocate transactions correctly based on the predefined account linkages, improving accuracy and saving time.

The plugin utilizes bank references to automatically allocate or link various transactions to the correct accounts in your Set of Books. It supports automatic receipts for debit orders from your debtors and automatic payments for managing supplier payments.

In summary, the Bank import plugin in osFinancials5/TurboCASH5 simplifies the import of bank statements, automates transaction allocation, and efficiently manages and reconciles your bank accounts. It reduces manual data entry, improves accuracy, and streamlines your financial management processes.

- Payroll: To record payroll transactions in osFinancials5/TurboCASH5, a specialised journal such as the payroll journal can be used. If you need to add the payroll journal, you can do so in the Setup → Batch types menu on the Setup ribbon.

  By processing payroll transactions in the payroll journal, you can effectively track your salary and wage expenses and payments. This allows you to have a dedicated journal specifically for recording payroll-related transactions, providing specific configuration of the payroll journal and better organisation and analysis of your payroll data.

  In addition to the payroll journal, osFinancials also provides the option to process repeating transactions. Repeating transactions can be accessed in the Edit → Repeating transactions menu on the Default ribbon. This feature allows you to set up and manage transactions that occur on a regular basis, such as recurring payroll entries. You can edit the repeating transactions as needed and import them into the normal payroll journal, ensuring consistency and efficiency in recording your payroll transactions.

  Using a payroll journal and taking advantage of the repeating transactions feature in osFinancials can streamline your payroll processing and help maintain accurate records of your payroll expenses and payments.

- Fixed assets: To record fixed asset transactions in osFinancials5/TurboCASH5, a specialized journal such as the fixed asset journal can be used. If the fixed asset journal is not already added, you can do so in the Setup → Batch types menu on the Setup ribbon.

By processing transactions for fixed assets in the fixed asset journal, you can effectively track your fixed asset-related transactions. This includes recording acquisitions, disposals, multi-year depreciation, and any transactions related to losses or profits on the disposal of fixed assets. Having a dedicated journal specifically for fixed asset transactions allows for better organization and analysis of your fixed asset data.

In addition to the fixed asset journal, osFinancials also provides the option to process repeating transactions. The repeating transactions feature can be accessed in the Edit → Repeating transactions menu on the Default ribbon. This feature is useful for setting up and managing transactions that occur on a regular basis, such as recurring depreciation entries for fixed assets. You can edit the repeating transactions as needed and import them into the normal fixed asset journal, ensuring consistency and efficiency in recording your fixed asset transactions.

Using the fixed asset journal and leveraging the repeating transactions feature in osFinancials5/TurboCASH5 streamline your fixed asset processing and help maintain accurate records of your fixed asset-related transactions. This allows for better tracking and management of your fixed assets throughout their life-cycle.

It's important to note that the availability and functionality of specific features may vary depending on the configuration and settings of your Set of Books in osFinancials5/TurboCASH5.

Activa plugin - Manual - Shop - Licence : Once-off -

The Activa plugin automates the management and processes of fixed assets and the depreciation of fixed assets in your accounts over the lifespan of the fixed assets. Periodically you will receive a notification screen, which the depreciation shown. From this screen, the depreciation(s) can directly take place.

The Activa plugin in osFinancials5/TurboCASH5 allows you to register fixed assets that need to be written off. The write-off process occurs over the lifespan of the asset and can be spread across multiple financial years.

By adding the Activa Fixed asset accounts in the plugin setup, you will receive reminders when new transactions are posted to the ledger or when Activa transactions require processing. This automation streamlines the management of depreciation allowances for fixed assets (tangible assets) in your Set of Books over the asset's lifespan.

As you record the depreciation expenses for each financial year, they will be reported in the income statement and reduce your net profit. Additionally, the plugin will provide you with the net value of your fixed assets, which is calculated as the fixed assets' cost minus the accumulated depreciation, and this information will be reflected in the balance sheet.

In summary, the Activa plugin helps automate the depreciation management process, ensures accurate reporting of depreciation expenses, and provides visibility into the net value of fixed assets over their lifespan in both the income statement and the balance sheet.

When a fixed asset reached the end of life end process that will clear of the total write-off from the balance write-off account and the initial asset account. This will display only the remaining total on the asset account and the contra account the will be cleared of this total.

By allowing the write-off process to occur over the lifespan of the asset and providing reminders for transaction processing, the plugin further streamlines the management of depreciation allowances for fixed assets.

The accurate reporting of depreciation expenses in the income statement and the reflection of the net value of fixed assets (cost minus accumulated depreciation) in the balance sheet remain essential features of the plugin.

Furthermore, the ability to clear the total write-off from the balance write-off account and the initial asset account when a fixed asset reaches the end of its life adds to the efficiency of the process.

The Activa plugin's powerful grid, custom filtering options, and integrated pivot tables enhance the search and analysis capabilities for active fixed assets, assets requiring processing, and transaction details. The Ledger analyser allows for the printing and exporting of the trial balance, income statement, and balance sheet, while the T-Account viewer facilitates the export of transactions to spreadsheets.

The Central search feature in osFinancials5/TurboCASH5 further aids in searching for transactions related to fixed assets, providing comprehensive functionality for managing and analysing fixed asset data.

- Accrual-based adjustments: To record transactions for accrual-based accounting adjustments, you can add an "*Adjustments*" journal type in the Setup → Batch types menu on the Setup ribbon. By creating an adjustments journal, you can specifically configure the options for recording month-end or year-end adjustments and easily track these adjustments within your Set of Books.

  Using a dedicated adjustments journal allows you to separate these specific transactions from other routine transactions and provides better organization and visibility for accrual-based adjustments. This ensures that these adjustments are properly captured and reflected in your financial statements.

Steps when entering and processing transactions in journals

When entering and processing transactions in journals or batches, there are typically seven steps involved. These steps ensure accurate data entry, balancing, and posting to the ledger. Here is a breakdown of each step:

1. Set the options or defaults for the batch: Before entering transactions, you may need to configure certain options or defaults for the batch. This could include setting the default currency, account codes, or any other relevant parameters. This step is typically done once, unless there are changes in your requirements.

2. Enter the alias (name for the batch): Assign a name or alias to the batch to help identify it later when generating reports or exporting/importing data. This allows for easy reference and organisation of your batches.
3. Select VAT/GST/Sales Tax treatment: If your transactions are subject to VAT/GST/Sales Tax, specify whether they are inclusive or exclusive of these taxes. This ensures accurate tax calculations and reporting. If no tax is applicable to the transactions, this option can be skipped.
4. Enter the transactions in the batch: Input the transaction details into the batch. This involves capturing the relevant information from source documents, such as invoices or receipts, and entering it into the appropriate fields in the batch. Ensure accuracy and completeness during data entry.
5. Balance the batch: Once all transactions are entered, ensure that the batch is balanced. This means the total debits and credits in the batch should match. Balancing the batch is crucial to maintaining accurate financial records and identifying any data entry errors.
6. List the batch and retain the batch listing: Generate a listing of the transactions within the batch and retain it along with the source documents. This serves as a record of the transactions entered and aids in reconciling the data at a later stage.
7. Post the batch to the ledger: The final step is to post the batch to the appropriate ledger accounts. This action updates the accounts with the transaction data and ensures the financial records are accurate and up to date. Posting transfers the information from the batch to the general ledger for proper accounting.

In osFinancials5/TurboCASH5*, you have the flexibility to enter and capture transactions without immediately posting the batch to the ledger. This allows you to capture transactions on a daily basis and exit the batch screen, proceeding to steps 5 and 7 at a later time. The data will be saved within the batch, ensuring it is not lost and can be balanced and posted at a more convenient time.*

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Batch types (setup)

This option allows you to create a batch (journal) to capture and enter your transactions. The Sales, Purchases, Receipts, Payments and General journal are standard defaults.

You can create any additional batches by adding them to this list. If you have more than one Bank account, you need to create a payments and receipts batch for each one. If you were initially short of batch types, you may enter additional batch types to accommodate your reporting requirements. These will not be

retroactive, so *thorough setting up* is preferable.

BATCH TYPES	*Lookup Type*	*Contra account lookup type*	*DEBIT / CREDIT*
Sales journal	*Debtors*	*General ledger*	*Debit*
Sales returns	*General ledger*	*Debtors*	*Credit*
Purchases	*General ledger*	*Creditors*	*Credit*
Purchase returns	*Creditors*	*General ledger*	*Debit*
Payments	*All*	*All*	*Debit*
Receipts	*All*	*All*	*Credit*
General journal	*All*	*All*	*Allow both (Debit / Credit)*

In the Sets of Books available as a free download, includes a Sales journal, Purchases journal, General journal, Bank account (linked to a Receipts and a Payments batch) and a Petty cash account (linked to a Receipts and a Payments batch).

When documents is updated to the ledger it will generate the transactions in the batches.

The document types is already linked to the batch types in Setup → Document setup (Setup ribbon). The batch types linked to the documents, is as follows:

- *Invoices - Sales journal*
- *Credit notes - Sales journal*
- *Purchases - Purchase journal*
- *Supplier returns - Purchase journal*

You can also set the batch defaults to reduce incorrect capturing of transactions. For example, in a Sales journal, only debit entries may be entered. Batch defaults such as “*contra accounts*”, “*contra account per*

line", "*inclusive*" (of VAT/GST/Sales Tax) or "*exclusive*" capture and increment reference numbers, and can only be set from within the batch.

The setting of the defaults will be discussed in later topics. The new features, which have been added to configure batches or journals, may be taken into account when you need to create or add your batch or journal types. This will enable faster and more accurate processing of transactions.

Some of these features are:

- No Tax - You may now hide the tax column and the Tax Code lookup facility if you are not registered for VAT/GST/Sales Tax or if VAT/GST/Sales Tax is not applicable to all transactions in the batch or journal.
- Lookup filters - You may now select to show all Accounts or only General ledger, Debtor or Creditor accounts.
- Contra account per line - easier processing of transactions with this setting. Contra accounts are now visible in the Contra account column.

Batch types are the journals in which you will enter (capture) the source documents of your transactions. You may enter all your invoices in the sales journal, deposits or receipts in the receipts journal, cheques or payments in the payments journal, etc. After you have entered, your transactions from the source documents, you need to check them and post or update these batches to the ledger.

To add a Batch type:

1. On the Setup ribbon, select Setup → Batch types.



2. Select a Batch type on the Description list. A blank line will be inserted above the selected Batch type.

3. Enter the name for the new batch type.

4. Click on the Close button.

You may select any batch and click on the Edit button to do the Batch setup; or press F10 or click on the F10:Setup icon on the Batch entry screen.

Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Sales journal / Sales returns journal

Sales Journal: Used for recording invoices and credit notes issued yo customers.

Sales journal for Credit notes

When processing credit notes for customers in the Sales Journal, the opposite entry is required to offset the original transaction. In 3. osFinancials5/TurboCASH5, specifically in the Batch entry mode, you would enter the amount preceded by a negative sign (minus sign) to transfer the amount to the credit column of the sales journal.

By using a negative sign before the amount, the credit note amount is treated as a deduction or reduction from the customer's account receivable. This helps offset the original sale or invoice and reflects the appropriate adjustment in the financial records.

Entering the credit note amount in the credit column of the sales journal ensures accurate recording and reporting of the transaction. It helps maintain proper documentation and provides a clear audit trail of the credit note issued to the customer.

Remember to apply the necessary adjustments in the sales journal to accurately reflect the credit note transaction and its impact on the customer's account and overall financial records.

In the Document entry mode, when you select the Sales journal, for the Credit notes document type, it will automatically debit the sales account and credit the customer account opposite of when you process and post Invoices.

When documents is updated to the ledger it will generate the transactions in the batches (journals).

The document types is already linked to the batch types in Setup → Document setup (Setup ribbon). The batch types linked to the documents, is as follows:

- *Invoices - Sales journal*
- *Credit notes - Sales journal*

- *Purchases - Purchase journal*
- *Supplier returns - Purchase journal*

In osFinancials5/TurboCASH5 you may add or create a batch type or journal type for credit notes such as sales returns journal to accurately handle credit notes for customers, you may add an additional journal type or utilize an existing journal type specifically designed for credit notes. This allows for proper segregation and categorization of credit note transactions, ensuring accurate recording and reporting. Depending on the accounting software or system being used, you may have the flexibility to customize and configure journal types to suit your specific requirements.

By incorporating a separate journal type for credit notes, you can maintain proper documentation, track customer returns or adjustments, and ensure that financial records accurately reflect the impact of these credit note transactions. This enhances the accuracy and integrity of financial reporting and facilitates proper analysis and reconciliation of customer accounts.

The opposite entry, with the amount entered in the credit column, helps offset the original transaction.

Additionally, in osFinancials5/TurboCASH5, you have the flexibility to add or create a batch type or journal type specifically for credit notes, such as a Sales Returns Journal. This allows for proper segregation and categorization of credit note transactions, ensuring accurate recording and reporting. You may configure the Sales Returns Journal to process credit notes to suit your specific requirements.

By incorporating a separate journal type for credit notes, you can maintain proper documentation, track customer returns or adjustments, and ensure that financial records accurately reflect the impact of these credit note transactions. This enhances the accuracy and integrity of financial reporting and facilitates proper analysis and reconciliation of customer accounts.

Customer Returns and Credit notes

When a customer returns goods and a credit note is issued, the accounting treatment typically depends on the reason for the return and the specific accounting policies of the company. Credit notes can be offset against different accounts, and the choice often depends on the nature of the return and the impact on the company's financial statements. Two common approaches are:

1. Offset Against Sales Revenue (Sales Account): If the returned goods are being credited back to the customer, and the company is reducing its reported sales revenue, the credit note can be offset against the sales account. This is often the case when the returned goods are being deducted from the total sales revenue because they were sold in error, were damaged, or for some other reason that requires a reduction in sales.

   For example, if a customer returns $100 worth of goods, the company could reduce its sales revenue

by $100 by offsetting it against the sales account.

2. Offset Against Sales Allowances: If the credit note represents a concession or allowance given to the customer (e.g., for damaged goods or a pricing dispute), it is commonly offset against the "Sales Allowances" account. This reduces the net sales revenue reported in the financial statements.

   For example, if a customer is granted a $20 allowance for damaged goods, the $20 credit note would be offset against the "Sales Allowances" account to reflect the reduction in sales revenue.

The choice between these two options depends on the company's accounting policies, the specific circumstances of the return, and how the company wants to present its financial statements. Both approaches are acceptable and can be used depending on what makes the most sense for accurate financial reporting.

It's important for a company to have clear and consistent accounting policies in place for handling returns and credit notes to ensure accurate and transparent financial reporting. These policies should be in line with generally accepted accounting principles (GAAP) or International Financial Reporting Standards (IFRS) if applicable in the company's jurisdiction.

Set default contra account for Credit notes

In osFinancials5/TurboCASH5, the default configuration for handling invoices and credit notes involves utilizing the Sales Journal. Consequently, by default, credit notes are set to offset against the Sales Account.

However, should you wish to utilize a different account, like the Sales Allowances account, to offset credit notes instead of the Sales Account, you will need to follow these steps within osFinancials:

1. Navigate to the Setup menu and select Batch types from the options provided on the Setup ribbon. Here, you can create a specific journal, such as the Sales Returns journal.
2. Within the "*Options for this batch*," you can specify the contra account as "Sales Allowances" or any other specific account distinct from the Sales Account.
3. Access the Setup menu again, this time selecting Document setup from the options on the Setup ribbon. On the Credit notes tab, you can designate the Sales Returns journal as the desired journal for credit note transactions.

This approach aligns with established accounting practices where businesses often employ separate journals or accounts to meticulously track returns, allowances, and discounts, ensuring the precision of financial reporting and facilitating thorough analysis.

It remains essential to tailor osFinancials5/TurboCASH5 to conform to your company's unique accounting policies and reporting criteria. This flexibility to configure contra accounts for various transaction types,

such as sales returns and allowances, empowers businesses to uphold the accuracy and transparency of their financial records.

Created with the Standard Edition of HelpNDoc: Free EPub producer

Purchase journal / Purchase returns journal

Purchases Journal: Used for recording supplier invoices and credit notes received from external suppliers.

Purchase journal for Credit notes received from external suppliers

When processing credit notes received from external suppliers in the Purchase Journal, the opposite entry is required to offset the original transaction. In osFinancials5/TurboCASH5, specifically in the Batch entry mode, you would enter the amount preceded by a negative sign (minus sign) to transfer the amount to the debit column of the purchase journal.

By using a negative sign before the amount, the credit note received from external suppliers is treated as a deduction or reduction from the creditor or supplier's account payable. This helps offset the original purchase or invoice and reflects the appropriate adjustment in the financial records.

Entering the credit note amount in the debit column of the purchase journal ensures accurate recording and reporting of the transaction. It helps maintain proper documentation and provides a clear audit trail of the credit note received from external suppliers.

Remember to apply the necessary adjustments in the purchase journal to accurately reflect the credit note transaction and its impact on the creditor or supplier's account and overall financial records. This ensures consistency and accuracy in financial reporting and facilitates proper analysis and reconciliation of supplier accounts.

When documents is updated to the ledger it will generate the transactions in the batches.

The document types is already linked to the batch types in Setup → Document setup (Setup ribbon). The batch types linked to the documents, is as follows:

- *Invoices - Sales journal*
- *Credit notes - Sales journal*
- *Purchases - Purchase journal*
- *Supplier returns - Purchase journal*

Purchase Returns Journal: Used for recording returns of purchased goods or services and associated credit notes received from external suppliers.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Receipts / Payments journals

Payments and Receipt Journals

Payments and Receipt batches (journals) in accounting are indeed linked to bank accounts and petty cash accounts, and they play a crucial role in recording the physical inflow and outflow of cash in a business. Here's a more detailed explanation:

1. Payments Journal (Cash Disbursements Journal): This journal is used to record all outgoing payments or disbursements made by the business. It includes payments made by check, electronic transfer, or in cash. These payments could be for various purposes, such as paying suppliers, employees, utilities, rent, or any other expenses incurred by the business. The Payments journal helps in tracking cash outflows and ensures that all expenditures are properly documented.
2. Receipts Journal (Cash Receipts Journal): The Receipts Journal, on the other hand, is used to record all incoming cash receipts. This includes payments received from customers, clients, or any other sources of income. Like the Payments journal, it helps in tracking cash inflows and ensures that all revenue is accurately recorded.

Both of these journals are linked to bank accounts and petty cash accounts in the following ways:

- Bank Accounts: Transactions recorded in the Payments and Receipts Journals are closely related to the business's bank accounts. When a payment is made (recorded in the Payments Journal), it usually results in a decrease in the bank balance, and when a receipt is recorded (in the Receipts Journal), it leads to an increase in the bank balance. These journals serve as a bridge between the physical cash transactions and the entries made in the bank statement, ensuring that the bank accounts are accurately reconciled.
- Petty Cash Accounts: Petty cash is a small amount of cash that a business keeps on hand for minor expenses. Transactions involving petty cash, such as replenishing the petty cash fund or recording expenses paid using petty cash, are also recorded in these journals. This helps in maintaining a clear record of petty cash transactions and ensures that the petty cash account is balanced.

While the Payments and Receipts Journals focus on cash transactions, other journals like the Sales Journal

and Purchase journal primarily deal with credit transactions. Sales Journal records credit sales to customers, while the Purchase journal records credit purchases from suppliers. These journals help in tracking accounts receivable (amounts owed to the business by customers) and accounts payable (amounts owed by the business to suppliers) but do not directly involve physical cash flow in and out of the business.

In summary, Payments and Receipts Journals are essential tools for accurately tracking and managing the physical flow of cash in a business, while other journals like the Sales and Purchase journals are more concerned with credit transactions and accounts receivable/payable. Properly maintaining these journals is crucial for effective cash flow management and financial record-keeping.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Cost of Sales journal

What is the Cost of Sales journal?

The Cost of Sales journal, also known as the Cost of Goods Sold (COGS) journal, is used to record the costs directly associated with the production or acquisition of goods sold by a business. It is an important journal in the accounting process, specifically for businesses that deal with inventory or the sale of physical products.

Here are some key points about the Cost of Sales journal:

1. Purpose: The Cost of Sales journal is used to track and record the costs directly attributable to the production or acquisition of goods that are subsequently sold to customers.
2. Cost Components: The journal captures various cost components, including the cost of raw materials, direct labor, manufacturing overhead, freight or shipping costs, and any other direct costs associated with the production or acquisition of inventory.
3. Calculation of Cost of Sales: The Cost of Sales journal helps calculate the Cost of Goods Sold (COGS), which represents the cost incurred by a business to produce or acquire the goods that are sold during a particular accounting period.
4. Inventory Valuation: The Cost of Sales journal plays a crucial role in the valuation of inventory. By recording the cost of inventory sold, it helps determine the value of the remaining inventory on hand, following the principles of inventory valuation methods such as First-In, First-Out (FIFO), Last-In, First-Out (LIFO), or Weighted Average Cost.
5. Impact on Financial Statements: The entries in the Cost of Sales journal affect the income statement

by reducing the revenue with the corresponding cost of goods sold, ultimately determining the gross profit or gross margin of the business.

6. Integration with Other Journals: The Cost of Sales journal is closely linked with other journals, such as the Sales Journal and the Purchases Journal. It incorporates the relevant information from these journals to calculate the cost of goods sold accurately.
7. Periodic or Perpetual Inventory Systems: The recording and calculation of cost of sales can vary depending on the inventory system employed by the business, such as periodic or perpetual inventory systems.

By maintaining a Cost of Sales journal, businesses can track and analyse the direct costs associated with the production or acquisition of goods sold, enabling them to determine profitability, evaluate pricing strategies, and make informed decisions regarding inventory management and cost control.

Inventory Adjustments Journal

Inventory journal can indeed be used to record adjustments to the purchase cost of stock items, such as correcting errors or adding additional costs like freight or import duties. Using an Inventory journal can provide more specificity and transparency in your accounting records, particularly when these adjustments are related to inventory values. Here's how it might work:

Adjustments to Inventory Cost: Inventory Journal: If you need to make adjustments to the cost of specific items within your inventory, an Inventory journal is a suitable choice. This journal allows you to specify the inventory item, the quantity, and the cost adjustment for each item. For example, if you discover an error in the initial cost recorded or need to add additional costs to specific items (e.g., freight charges), you can use the Inventory journal entries to adjust the cost of those specific items. Each entry in the Inventory journal would involve debiting or crediting the appropriate inventory item and reflecting the cost adjustment.

Using an Inventory journal for these adjustments provides a clear audit trail and ensures that changes to inventory costs are accurately recorded for each item. It allows for more precise tracking of inventory-related expenses and helps maintain the integrity of your inventory valuation.

In summary, while the General Journal can be used for various adjustments, including those related to inventory, using an Inventory journal for specific adjustments to the cost of stock items is a good practice. It offers better visibility and control over inventory-related transactions and helps ensure accurate inventory valuation on your financial statements.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's HTML5 template

General journal

General journal - Key points

The General journal is a fundamental component of the accounting system used for recording miscellaneous transactions that do not fit into the other specialized subsidiary journals. It provides flexibility for recording various types of transactions that are not covered by the specific journals, such as the Sales journal, Purchase journal, or Payments and Receipts journals (linked to specific bank accounts).

Here are some key points about the General journal:

1. Miscellaneous Transactions: The General Journal is used to record transactions that are unique or do not have a designated journal for their specific type. It includes transactions such as corrections of errors, adjusting entries, accruals, deferrals, depreciation entries, and other non-routine transactions.
2. Flexibility: The General Journal allows for the recording of diverse transactions, making it a versatile tool in the accounting process. It accommodates transactions that do not fit into predefined categories or require special treatment.
3. Manual Entries: Unlike other subsidiary journals that may have automated or system-generated entries, the General Journal typically involves manual entries made by accountants or bookkeepers. These entries require careful consideration and proper documentation.
4. Debits and Credits: The General journal follows the fundamental principles of double-entry bookkeeping, where each transaction is recorded with equal debits and credits to maintain the balance of the accounting equation.
5. Ledger posting: After entries are recorded in the General Journal, they are posted to the respective accounts in the General ledger. This ensures that the impact of the transactions is reflected accurately in the overall accounting records.
6. Financial reporting: The transactions recorded in the General Journal are ultimately reflected in the financial statements. They contribute to the preparation of the trial balance, income statement, balance sheet, and other financial reports.
7. Audit trail: The General Journal provides an audit trail for miscellaneous transactions, allowing for proper documentation and tracking of entries. This helps in ensuring transparency, accountability, and accuracy in financial reporting.
8. Internal controls: The General Journal, like other accounting journals, plays a role in maintaining internal controls within an organization. It allows for proper authorization, review, and approval processes for miscellaneous transactions, minimizing the risk of errors or fraudulent activities.

Overall, the General journal serves as a crucial tool in accounting, providing flexibility for recording various types of transactions that do not fit into other specialized journals. It ensures that all transactions are properly documented, recorded, and reported, maintaining the integrity of the financial records and supporting accurate financial analysis and decision-making.

When should a general journal be used?

The general journal, on the other hand, is typically used for recording non-routine or unusual transactions that do not fit into other specialized journals. It is a versatile journal that can be used for various purposes, including corrections of errors. If there is no specific journal available for a particular type of transaction, using the general journal is a suitable option.

However, whenever there is a specialized journal available for a specific type of transaction, it is recommended to use that journal to ensure accuracy and efficiency in record-keeping. This helps maintain consistency and allows for easier analysis and reporting of transactions within their relevant categories.

In general, a general journal is used to record non-routine or unusual transactions that do not fit into the other specialized journals. However, if there is a specific journal available for a particular type of transaction, it is best to use that journal to ensure accuracy and efficiency in record-keeping

When should a general journal NOT be used?

A general journal should not be used in certain situations where there are specific journals designed for recording transactions. For example:

- Sales: For recording sales, specialised journals like the sales journal should be used. To record sales transactions in osFinancials5/TurboCASH5, you can use the sales journal available in the Batch entry section of the Default ribbon. The sales journal allows you to enter and manage sales-related transactions effectively.

  In addition to the sales journal, you can process invoices and credit notes using the Documents section on the Default ribbon. Invoices and credit notes can be linked to the sales journal in Setup → Documents setup (Setup ribbon). When you process invoices and credit notes, the source documents will be automatically generated, allowing you to have physical or digital copies of these documents for record-keeping purposes. These documents can be printed and reprinted as needed, enabling you to send them to your debtors (customers/clients) as required.

  Once the invoices and credit notes are updated and posted to the ledger, the corresponding transactions will be automatically processed in the sales journal. Each item included in the invoice or credit note will be recorded in the sales journal, ensuring accurate tracking of your sales transactions.

  By utilising the sales journal and linking invoices and credit notes, you can efficiently manage and

maintain a comprehensive record of your sales activities in osFinancials5/TurboCASH5.

- Purchases: For recording purchases, specialised journals like the purchase journal should be used. To record purchase transactions in osFinancials5/TurboCASH5, you can use the purchase journal available in the Batch entry section of the Default ribbon. The purchase journal allows you to enter and manage purchase-related transactions effectively.

  In addition to the purchase journal, you can process purchase and supplier return documents using the Documents section on the Default ribbon. Purchases and supplier return documents can be linked to the purchase journal in Setup → Documents setup (Setup ribbon). When you process purchase and supplier return documents, the source documents will be automatically generated, allowing you to have physical or digital copies of these documents for record-keeping purposes. These documents can be printed and reprinted as needed, enabling you to send them to your creditors (suppliers/vendors) as required.

  Once the purchase and supplier return documents are updated and posted to the ledger, the corresponding transactions will be automatically processed in the purchase journal. Each item included in the purchase and supplier return documents will be recorded in the purchase journal, ensuring accurate tracking of your purchase transactions.

  By utilising the purchase journal and linking purchase and supplier return documents, you can efficiently manage and maintain a comprehensive record of your purchase activities in osFinancials5/TurboCASH5.

- Cash transactions: To record cash transactions in osFinancials5/TurboCASH5, specialised journals such as the cash receipts journal and cash disbursements journal are used. In osFinancials5/TurboCASH5, when setting up bank accounts and petty cash accounts in the Setup → Accounts menu of the Setup ribbon, each account will be associated with its own unique payments journal and receipts journal.

  If the Bank import plugin is not activated in osFinancials5/TurboCASH5, you can manually process cash transactions in the respective payments journal and receipts journal associated with the bank account or petty cash account. To access these journals, you can go to the Batch entry option on the Default ribbon.

  If the Bank import plugin is activated, you have the option to process and import transactions directly into the payments journal and receipts journal associated with the bank account or petty cash account. This can be done through the Cash/Bank entry option on the Default ribbon.

  By using the appropriate journals for cash transactions, you can effectively record and manage your cash receipts and disbursements. The journals allow for accurate tracking of cash flows, providing a clear overview of your financial activities.

  Please note that the availability and functionality of specific features may depend on the configuration

and settings of your Set of Books in osFinancials5/TurboCASH5.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin is included with the osFinancials5/TurboCASH5 Business Class license, meaning you have access to it without any additional cost or separate license requirement.

With the plugin, you can download bank statement files from your online banking app or portal provided by your bank or financial institution. These files can be imported into the appropriate bank accounts (cash books) in osFinancials5/TurboCASH5.

You can download statements for multiple bank accounts and credit cards, as long as you have them linked to your online banking. Each bank account or credit card should have its corresponding Payments and Receipts journals set up in osFinancials5/TurboCASH5.

Importing the bank statements automatically populates the transactions into the Payments and Receipts columns, saving you time and reducing the risk of errors associated with manual entry.

The plugin offers a user-friendly interface with context menus that make it easy to locate, select, and search for specific transactions, debtors, creditors, or general ledger accounts. This simplifies the navigation and management of your bank transactions.

You can link debit transactions to credit transactions and vice versa, allowing for accurate tracking of outstanding balances and efficient management of payments and receipts. You can also link a portion of a payment or receipt to multiple outstanding transactions if needed.

Additionally, the plugin allows you to link accounts to specific debtors, creditors, or general ledger accounts. This ensures that subsequent bank statement imports automatically allocate transactions correctly based on the predefined account linkages, improving accuracy and saving time.

The plugin utilizes bank references to automatically allocate or link various transactions to the correct accounts in your Set of Books. It supports automatic receipts for debit orders from your debtors and automatic payments for managing supplier payments.

In summary, the Bank import plugin in osFinancials5/TurboCASH5 simplifies the import of bank statements, automates transaction allocation, and efficiently manages and reconciles your bank accounts. It reduces manual data entry, improves accuracy, and streamlines your financial management processes.

- Payroll: To record payroll transactions in osFinancials5/TurboCASH5, a specialised journal such as the payroll journal can be used. If you need to add the payroll journal, you can do so in the Setup → Batch types menu on the Setup ribbon.

  By processing payroll transactions in the payroll journal, you can effectively track your salary and wage

expenses and payments. This allows you to have a dedicated journal specifically for recording payroll-related transactions, providing specific configuration of the payroll journal and better organisation and analysis of your payroll data.

In addition to the payroll journal, osFinancials5/TurboCASH5 also provides the option to process repeating transactions. Repeating transactions can be accessed in the Edit → Repeating transactions menu on the Default ribbon. This feature allows you to set up and manage transactions that occur on a regular basis, such as recurring payroll entries. You can edit the repeating transactions as needed and import them into the normal payroll journal, ensuring consistency and efficiency in recording your payroll transactions.

Using a payroll journal and taking advantage of the repeating transactions feature in osFinancials5/TurboCASH5 can streamline your payroll processing and help maintain accurate records of your payroll expenses and payments.

- Depreciation: To record fixed asset transactions in osFinancials5/TurboCASH5, a specialized journal such as the fixed asset journal can be used. If the fixed asset journal is not already added, you can do so in the Setup → Batch types menu on the Setup ribbon.

  By processing transactions for fixed assets in the fixed asset journal, you can effectively track your fixed asset-related transactions. This includes recording acquisitions, disposals, multi-year depreciation, and any transactions related to losses or profits on the disposal of fixed assets. Having a dedicated journal specifically for fixed asset transactions allows for better organization and analysis of your fixed asset data.

  In addition to the fixed asset journal, osFinancials5/TurboCASH5 also provides the option to process repeating transactions. The repeating transactions feature can be accessed in the Edit → Repeating transactions menu on the Default ribbon. This feature is useful for setting up and managing transactions that occur on a regular basis, such as recurring depreciation entries for fixed assets. You can edit the repeating transactions as needed and import them into the normal fixed asset journal, ensuring consistency and efficiency in recording your fixed asset transactions.

  Using the fixed asset journal and leveraging the repeating transactions feature in osFinancials5/TurboCASH5 can streamline your fixed asset processing and help maintain accurate records of your fixed asset-related transactions. This allows for better tracking and management of your fixed assets throughout their life-cycle.

  It's important to note that the availability and functionality of specific features may vary depending on the configuration and settings of your Set of Books in osFinancials5/TurboCASH5.

Activa plugin - *Manual* - *Shop* - *Licence : Once-off* -

The Activa plugin automates the management and processes of fixed assets and the depreciation of fixed assets in your accounts over the lifespan of the fixed assets. Periodically you will receive a notification screen, which the depreciation shown. From this screen, the depreciation(s) can directly take place.

The Activa plugin in osFinancials5/TurboCASH5 allows you to register fixed assets that need to be written off. The write-off process occurs over the lifespan of the asset and can be spread across multiple financial years.

By adding the Activa Fixed asset accounts in the plugin setup, you will receive reminders when new transactions are posted to the ledger or when Activa transactions require processing. This automation streamlines the management of depreciation allowances for fixed assets (tangible assets) in your Set of Books over the asset's lifespan.

As you record the depreciation expenses for each financial year, they will be reported in the income statement and reduce your net profit. Additionally, the plugin will provide you with the net value of your fixed assets, which is calculated as the fixed assets' cost minus the accumulated depreciation, and this information will be reflected in the balance sheet.

In summary, the Activa plugin helps automate the depreciation management process, ensures accurate reporting of depreciation expenses, and provides visibility into the net value of fixed assets over their lifespan in both the income statement and the balance sheet.

When a fixed asset reached the end of life end process that will clear of the total write-off from the balance write-off account and the initial asset account. This will display only the remaining total on the asset account and the contra account the will be cleared of this total.

By allowing the write-off process to occur over the lifespan of the asset and providing reminders for transaction processing, the plugin further streamlines the management of depreciation allowances for fixed assets.

The accurate reporting of depreciation expenses in the income statement and the reflection of the net value of fixed assets (cost minus accumulated depreciation) in the balance sheet remain essential features of the plugin.

Furthermore, the ability to clear the total write-off from the balance write-off account and the initial asset account when a fixed asset reaches the end of its life adds to the efficiency of the process.

The Activa plugin's powerful grid, custom filtering options, and integrated pivot tables enhance the search and analysis capabilities for active fixed assets, assets requiring processing, and transaction details. The Ledger analyser allows for the printing and exporting of the trial balance, income statement, and balance sheet, while the T-Account viewer facilitates the export of transactions to spreadsheets.

The Central search feature in osFinancials5/TurboCASH5 further aids in searching for transactions related to fixed assets, providing comprehensive functionality for managing and analysing fixed asset data.

- Accrual-based adjustments: To record transactions for accrual-based accounting adjustments, you can add an "*Adjustments*" journal type in the Setup → Batch types menu on the Setup ribbon. By creating an adjustments journal, you can specifically configure the options for recording month-end or year-end adjustments and easily track these adjustments within your Set of Books.

Using a dedicated adjustments journal allows you to separate these specific transactions from other routine transactions and provides better organization and visibility for accrual-based adjustments. This ensures that these adjustments are properly captured and reflected in your financial statements.

Created with the Standard Edition of HelpNDoc: Protect Your Confidential PDFs with These Simple Security Measures

Specialised journals

Payroll journal: This journal type can be used specifically for recording payroll entries, including salary expenses, tax withholdings, benefits, and other related transactions. It allows for accurate tracking and reporting of payroll-related costs.

Fixed assets journal: By creating a custom journal type for fixed assets, you can record transactions related to asset acquisition, depreciation, disposals, and any other changes in the fixed asset register. This ensures proper tracking of asset values and facilitates compliance with accounting standards and regulatory requirements.

Accruals journal: An accruals journal can be used to record accrual-based adjustments, such as recognizing revenue or expenses that have been incurred but not yet recorded in the general ledger. This journal type helps ensure accurate matching of revenues and expenses in the appropriate accounting periods.

Inventory adjustment journal: This journal type allows for the recording of inventory adjustments, such as write-offs, write-downs, and any changes in the quantity or value of inventory items. It helps maintain accurate inventory records and supports proper valuation of inventory on the financial statements.

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Depreciation journal / Amortization journal

Depreciation journal or Amortization journal - is there examples of transactions to be recorded in this journal?

There are examples of transactions that can be recorded in a Depreciation Journal or Amortization Journal. These journals are used to record the periodic depreciation or amortization expense of fixed assets or intangible assets. Here are some examples:

Depreciation journal:

1. Straight-Line Depreciation: This is the most common method of depreciation, where the asset's cost is evenly allocated over its estimated useful life. Each period, a portion of the asset's value is recorded as depreciation expense in the Depreciation Journal.
2. Accelerated Depreciation: In some cases, businesses may use accelerated depreciation methods, such as the declining balance method or the sum-of-the-years'-digits method. These methods allocate higher depreciation expense in the early years and lower expense in the later years.
3. Depreciation Expense Adjustment: If there are any changes to the estimated useful life or residual value of an asset, an adjustment entry would be made in the Depreciation Journal to reflect the updated depreciation expense.

Amortization journal:

1. Intangible Asset Amortization: Intangible assets, such as patents, trademarks, copyrights, and software, are typically amortized over their estimated useful life. The periodic amortization expense is recorded in the Amortization Journal.
2. Loan Amortization: If your business has loans or borrowings, the periodic repayment of principal and interest can be recorded in the Amortization Journal. This allows for accurate tracking of the principal reduction and interest expense over time.
3. Prepaid Expense Amortization: If your business has prepaid expenses, such as insurance premiums or rent paid in advance, the gradual allocation of these expenses over the applicable period can be recorded in the Amortization Journal.

These examples highlight the types of transactions that can be recorded in a Depreciation Journal or Amortization Journal. The specific entries will depend on the depreciation or amortization methods used, the assets or liabilities being accounted for, and any adjustments or changes made over time. By maintaining a dedicated journal for depreciation or amortization, you can accurately record and track these expenses, ensuring compliance with accounting principles and providing a clear view of your asset or liability values.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Accruals journal

The Accruals journal is used to record accrual entries, which are adjustments made to recognize revenues or expenses that have been earned or incurred but not yet recorded in the financial statements. Here are some examples of transactions that could be recorded in an Accruals journal:

1. Accrued Revenues: If your business has provided goods or services to customers, but the payment or invoice has not been received or issued by the end of the accounting period, you can record an accrued revenue entry. This recognizes the revenue earned in the current period, even though the payment or invoice is not yet received.
2. Accrued Expenses: Similarly, if your business has received goods or services from suppliers, but the payment or invoice has not been processed or received by the end of the accounting period, you can record an accrued expense entry. This recognizes the expense incurred in the current period, even though the payment or invoice is not yet paid.
3. Interest Accruals: If your business has borrowed funds and the interest expense for a certain period has not been paid or invoiced, you can record an accrual entry to recognize the interest expense incurred during that period.
4. Salary and Wage Accruals: If your business has employees and the payroll period ends before the actual payment is made, you can record an accrual entry to recognize the salary or wage expense incurred during that period.
5. Rent Accruals: If your business is renting premises or equipment and the rental period ends before the actual payment is made, you can record an accrual entry to recognize the rent expense incurred during that period.
6. Utilities Accruals: If your business has utility expenses, such as electricity or water, and the billing period ends before the actual payment is made, you can record an accrual entry to recognize the utility expense incurred during that period.

These are just a few examples of transactions that could be recorded in an Accruals Journal. The specific entries will depend on the nature of your business and the timing of revenue and expense recognition. By recording these accrual entries in a dedicated journal, you can ensure that your financial statements reflect the appropriate revenue and expense recognition, providing a more accurate representation of your business's financial position.

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Inventory adjustment journal

Inventory adjustment journal - Is there examples of transactions to be recorded in this journal?

The Inventory Adjustment Journal is used to record various transactions related to inventory adjustments. These adjustments help to maintain accurate inventory records and reflect changes in the quantity or value of inventory items. Here are some examples of transactions that can be recorded in an Inventory Adjustment Journal:

1. Physical Inventory Count: When conducting a physical inventory count, any discrepancies found between the actual physical count and the recorded inventory quantities are recorded in the Inventory Adjustment Journal. This includes adjustments for overstock or understock situations.
2. Damaged or Spoiled Goods: If inventory items become damaged, spoiled, or unsellable, the reduction in their value is recorded as an inventory adjustment. This adjustment is typically recorded as a decrease in quantity and value in the Inventory Adjustment Journal.
3. Write-Off of Obsolete Inventory: When inventory items become obsolete or are no longer usable or sellable, they are typically written off from the inventory records. The write-off is recorded as a decrease in quantity and value in the Inventory Adjustment Journal.
4. Returns or Exchanges: If there are customer returns or exchanges that result in changes to inventory quantities, the adjustments are recorded in the Inventory Adjustment Journal. This includes both increases and decreases in quantity and value.
5. Price Adjustments: If there are changes in the cost or selling price of inventory items, adjustments may be made in the Inventory Adjustment Journal to reflect the updated values. This helps to ensure accurate valuation of inventory.
6. Shrinkage or Losses: Inventory shrinkage or losses can occur due to theft, damage, or other reasons. Any adjustments made to account for these losses are recorded in the Inventory Adjustment Journal as decreases in quantity and value.

These examples highlight the types of transactions that can be recorded in an Inventory Adjustment Journal. The specific entries will depend on the nature of your business, the inventory management practices you follow, and any specific events or circumstances that impact your inventory. By maintaining a dedicated journal for inventory adjustments, you can keep track of changes in inventory quantities and values, maintain accurate records, and ensure your financial statements reflect the true state of your inventory.

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Inter-company transactions journal - Is there examples of transactions to be recorded in this journal?

Inter-company transactions involve transactions between different entities or subsidiaries within the same organization. Here are some examples of transactions that could be recorded in an Inter-company transactions journal:

1. Inter-company sales: When one entity within the organization sells goods or services to another entity, the transaction should be recorded in the Inter-company transactions journal. This ensures that the sales revenue is properly recognized in the selling entity's financial records and the purchasing entity's accounts payable is appropriately recorded.
2. Inter-company purchases: Similarly, when one entity purchases goods or services from another entity within the organization, the transaction should be recorded in the Inter-Company Transactions Journal. This ensures that the purchasing entity's accounts payable is accurately reflected, and the selling entity's sales revenue is appropriately recorded.
3. Inter-company loans: If one entity lends funds to another entity within the organization, the loan transaction should be recorded in the Inter-company transactions journal. This helps track the borrowing entity's liability for the loan and the lending entity's receivable for the loan.
4. Inter-company service charges: If one entity provides services to another entity within the organization and charges a fee for those services, the service charge transaction should be recorded in the Inter-company transactions journal. This ensures that the service revenue is appropriately recognized and the purchasing entity's accounts payable is properly recorded.
5. Inter-company asset transfers: When assets are transferred between entities within the organization, such as equipment, machinery, or inventory, the transfer should be recorded in the Inter-company transactions journal. This helps track the movement of assets between entities and ensures proper accounting for the value of the transferred assets.

These are just a few examples of transactions that could be recorded in an Inter-Company Transactions Journal. The specific transactions will depend on the nature of the inter-company activities and the policies of your organization. By recording these transactions in a dedicated journal, you can accurately track inter-company balances, eliminate inter-company transactions during consolidation, and ensure proper financial reporting within your organization.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Point-of-Sales journal

What is the POS journal (Point-of-Sales journal)?

The POS journal, also known as the Point-of-Sales journal, is a specific type of journal used in osFinancials5/TurboCASH5 that integrate with point-of-sale (POS) systems. It is designed to record sales transactions that occur directly at the point of sale, typically in retail or hospitality businesses where goods or services are sold to customers in-person.

Here are some key points about the POS journal:

1. Purpose: The POS journal is used to record and track sales transactions that take place at the point of sale, where customers make purchases in real-time. It captures details such as the items sold, quantities, prices, discounts, and payment methods.
2. Integration with POS Systems: The POS journal is closely linked with the business's POS system or software. It receives data directly from the POS system, which automatically captures and transfers sales transaction information to the journal.
3. Real-Time Recording: As sales occur, the POS system records the transaction details, and the information is immediately transferred to the POS journal. This enables real-time tracking of sales and ensures accurate and up-to-date financial information.
4. Sales Information: The POS journal includes essential details about each sale, such as the date and time of the transaction, customer information, items purchased, sales prices, discounts applied, and the total amount of the sale.
5. Integration with Other Journals: The data from the POS journal is typically integrated into other relevant journals, such as the Sales Journal, Cash Receipts Journal, or General Journal. This integration ensures that the sales transactions are properly recorded and reflected in the appropriate accounts.
6. Reporting and Analysis: The POS journal provides valuable data for reporting and analysis purposes. It allows businesses to track sales trends, monitor inventory levels, evaluate product performance, calculate sales commissions, and analyze customer buying patterns.
7. Cash Management: The POS journal also plays a role in cash management, as it records cash sales and tracks the amount of cash collected during each transaction. This information can be used for cash reconciliation and to ensure that cash on hand matches the recorded sales.

The POS journal is an essential component of accounting systems in retail and hospitality businesses. It

enables accurate and efficient recording of sales transactions, provides real-time information for decision-making, and facilitates proper financial management and reporting.

Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Batch entry selection screen

These are so named because all transactions of the same type are grouped together as a “batch” (for example, all the receipts or, all the purchases).

Batch types are added / renamed and/or edited in Setup → Batch types. (Setup ribbon).

The following are the most commonly used batch types are included in the Sets of Books:

- Sales journal - This journal or book is used to record your sales for the day. You would record the invoice number, date of invoice, invoice details, the debtor (who you sold to), Output VAT/GST/Sales Tax (if you are registered for VAT/GST/Sales Tax) and the amount you charged the customer - including or excluding VAT/GST/Sales Tax, depending on your requirements.
- Purchase journal - This journal is used to record all the purchases, which were made in the normal operation of your business. Details which would be recorded include the supplier invoice or other number (as a reference), the date of the purchase, purchase details, from whom you purchased, Input VAT/GST/Sales Tax (if you are VAT/GST/Sales Tax registered and if applicable) and the amount you were charged, including or excluding VAT/GST/Sales Tax, depending on your requirements.
- Cashbook - This is made up of both the Receipts and Payments Journals. The Receipts and Payments Journals of the Cashbook are reconciled with a bank statement.
    - Receipts journal - All deposits, along with the date of the deposit, the name of the depositor and the amount are recorded in this book. For debtors it would have the effect of debiting the bank account and crediting the debtor, after the debtor has been debited through the Sales journal.
    - Payments journal - All payments made, along with the date, detail and amount are recorded here. Payments would have the effect of debiting the creditor or the expense, and crediting the bank.
- General journal - This book is used to enter all your opening balances, correct any errors you have made and process items like depreciation of assets and the payroll. Depending on the need, the payroll (or any other journal) for example, can be set up as separate batch type and it will then be possible to print a separate report for that function will then be generated. Other journals that may be

required are the sales returns or debtor allowances journal, petty cash journal, depreciation journal or payroll journal.

To select and open a batch:

1. On the Default ribbon, select Batch entry (F2).

2. Select the batch from the list and click on the Open button. The "*Batch entry*" screen for the selected Batch type will be displayed.

Once the options for a batch or journal has been set up, the Contra account code and name or description, will be displayed. If the options for a batch or journal, which have not yet been setup, it will display no Contra account.

If you access a batch type and the contra account is for example, displayed as the Sales account (010-000), you may change the contra account when you set the options for a batch.

If any transactions have been entered into a batch (journal), the total amount of the transactions entered in the debit column and/or the total amount of the transactions entered in the credit column will be displayed as unposted.

If the batch is in balance (amounts of equal value is entered in the debit and credit columns or if the batch has been balanced), the debit and credit amounts will reflect the same value.

The alias (batch name) will display at the bottom (left to the Open and Cancel buttons.

Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Batch entry selection screen - Context menu

To access the context menu options, right-click on the "*Batch type*" selection screen for easy access to perform various batch processing tasks in osFinancials5/TurboCASH5. Here is a summary of the available options:



1. Print - Allows you to print a list of transactions in a selected batch (journal) that has not been posted (updated) to the ledger. This provides a printed record of the transactions for reference or auditing purposes. it is recommended to review the batch list and edit or correct any transactions before proceeding to post the batch (journal). This ensures that the transactions are accurate and complete before being updated to the ledger. Printing the list of transactions allows you to have a physical record that can be used for reference, auditing, or reconciliation purposes.

2. Edit - Opens the selected Batch entry screen, where you can enter or add new transactions, edit existing transactions, delete or insert transactions, reverse transactions, change the alias (batch name), write transactions to a delimited file, or import transactions from a delimited file. This option gives you flexibility in managing and modifying batch transactions.

3. Balance batch - Balances the transactions entered into a selected batch by generating balancing entries (transactions) to ensure that the debits and credits in the batch match. Balancing the batch is crucial for accurate financial records and proper posting to the ledger.

4. Post batch - Updates the transactions entered into a selected batch to the ledger, effectively posting them and updating the accounts with the transaction data. This step finalises the batch processing and ensures the transactions are reflected in the financial records.

5. Erase batch - Deletes the selected batch (journal) along with all the transactions contained within it. This option is useful when you need to remove an entire batch and its associated transactions from the system.

6. Change alias - Allows you to modify the alias (batch name) for a selected batch type. The alias provides a unique identifier for the batch and helps in distinguishing between different batches. You

can assign a specific name or use an auto-generated alias based on system date or other criteria.

Auto-alias - Setting may also be activated on the F10:Setup - Advanced tab - "Options for this batch". This will automatically generate the system date as the alias (batch name) (e.g., "20210331") for the batch.

Auto generated - Alias in Receipts batches - TR00001, TR00002,etc. These aliases prefixed with "TR" (consisting of seven (7) digits) will automatically be generated in receipt batches when the "Receive payment" option is used in Open item link context menu.

See -

- *Receive payment for a selected debtor (customer / client) account.*
- *Receive payment for a selected creditor (supplier / vendor) account.*

7. Delimited file import - Imports transactions from a valid delimited file into the selected batch (journal). This feature enables you to efficiently import a large number of transactions from external sources into osFinancials5/TurboCASH5.

8. Write delimited file - Writes or exports the transactions entered or imported into a batch to a delimited file. This option allows you to generate a file containing the batch transactions that can be used for various purposes such as data backup or to re-import the transactions a batch or journal at a later stage.

9. Reverse batch (D<-->C) - Reverses the amounts of transactions in a selected batch (journal) from the debit column to the credit column or vice versa. This option is helpful when you need to correct or adjust the direction of the transaction entries.

10. Posted batches import - Imports transactions from a valid file format if the transactions from a batch (journal) that have already been posted (updated) to the ledger were exported using the "*Export - Posted Batches*" option. This feature allows you to re-import posted transactions if necessary.

11. Delete balance - Deletes the balancing entries (transactions) if the selected batch (journal) is already balanced. This option is useful when you want to remove or modify the balancing entries associated with a batch.

12. Trial balance - Generates a trial balance for the unposted transactions entered or imported into batches that have not been posted (updated) to the ledger. You can choose to include unposted transactions, posted transactions, or only posted transactions in the trial balance report. This helps in reviewing the financial impact of unposted transactions.

13. Sort by date - Sorts the transactions in the selected batch (journal) in ascending date sequence (from the oldest date to the latest date) if they have not been entered or imported in that order. This option ensures proper sequencing of transactions based on their transaction dates.

If any invoices and credit notes have been updated to the ledger, these transactions will be included in the batch type report for the sales journal (or other batch (journal)) selected in Setup → Documents setup.

If any Purchase documents and Supplier return documents have been updated to the ledger, these transactions will be included in the batch type report for the Purchase journal (or other batch (journal)) selected in Setup → Documents setup.

Created with the Standard Edition of HelpNDoc: Simplify Your Help Documentation Process with a Help Authoring Tool

Batch entry form

The batch entry screen can accommodate various types of transactions depending on your business needs. It allows you to enter the necessary details, allocate amounts to specific accounts, and accurately record your financial transactions.

Remember to adhere to proper accounting principles and guidelines when entering transactions and ensure that the information entered is accurate and supported by appropriate documentation.

The basic layout and principles of the "*Batch entry*" screen, is as follows:



Handyman Hardware Store
VAT Reg. No. 446010111

To: Mr. AB Green
PO Box 1111
Lakeside
Johannesburg
2012
VAT No. 111111111

Tax Invoice: INV001
Date: 7 March 2022
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Paint - Exterior	1 000.00	-	1 000.00
			Sub-total	1 000.00
			VAT @ 15%	150.00
			Invoice Total	1 150.00

E.&O.E

When selecting a debtor (customer/client) account or a creditor (supplier/vendor) account in the batch entry screen, their details such as account code, name, and address will be displayed. This allows you to verify the accuracy of the account details before entering the transaction.

If you notice any discrepancies in the displayed information for a debtor or creditor account, such as an incorrect address, you can update the account with the correct details. In osFinancials5/TurboCASH5, you can do this by following these steps:

1. *In the Batch entry screen, right-click on the debtor or creditor account for which you want to edit the details.*
2. *From the context menu that appears, select the "Edit account" option and select the "Debtors" or "Creditors" account type.*
3. *Select the debtor or creditor account. This will open the account details screen for the selected debtor or creditor account.*
4. *Make the necessary changes to the address or other contact information in the account details.*
5. *Save the updated information to apply the changes to the debtor or creditor account.*

Alternatively, you can access the debtor or creditor accounts directly from the Default ribbon. In osFinancials5/TurboCASH5, you will find the "Debtors" and "Creditors" options on the Default ribbon. Clicking on these options will allow you to view and edit the debtor or creditor accounts and make the necessary changes to the contact details.

By keeping the debtor and creditor account information up to date, you can ensure accurate communication and maintain reliable records of your business transactions.



For each transaction, you need a source document from which you will enter the basic information in a Batch entry screen. We would enter the cheque number, date, to whom the payment is made, for what, and the amount of the transaction.

Title bar

Displays the name of the selected batch accessed from the batch type screen. The name of the selected batch [between square brackets in the title bar], may be entered in the Change alias field to reflect the batch name for the specific transactions entered into the selected batch. Once the batch is posted or updated to the ledger, the batch name will make it easier if you need to identify the specific batch to print a batch type report, export the posted transactions in the posted to a file or to reverse the posted batch.

Speed buttons or icons

These speed buttons or icons are conveniently placed below the title bar on the Batch entry screen to allow you to access the most frequently used options with ease. Each of the speed buttons has a shortcut key to access the required option from your keyboard.

^D:Delete - Delete selected transaction(s).

^N:Insert - Select the line or row in which you wish to insert a blank line or row above the selected transaction.. You may then enter a transaction.

F5:Balance - Generate balancing transactions to the contra accounts.

F6:Post - Post (update) transactions to the ledger.

F7:Exclusive - Enter amounts of transactions exclusive of Tax (VAT/GST/Sales tax).

F7:Inclusive - Enter amounts of transactions inclusive of Tax (VAT/GST/Sales tax).

F8:List - After entering all your transactions in a batch, and before updating or posting the transactions to the ledger, you need to print a list of the transactions entered in the batch.

F9:Process - Launches the Batch processing options to select various options to process transactions in unposted batches, export and import functions. Various functionalities to generate and process transactions is also available.

F10:Setup - Set and configure the "*Batch entry*" screen for each batch or journal to meet your own specific requirements. The following two (2) options is available:

- Standard tab - In addition to selecting the contra account, various settings and configuration options, you may set the amount entry columns to "*Debit, Credit*" or "*Allow both*" to enter amounts faster and more accurately.
- Advanced tab - In addition to various settings and configuration options, the "*Account code lookup type*" and "*Contra account lookup type*" may be set to list only those accounts to select from in the Accounts lookup when processing transactions.

Spreadsheet import - osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export feature.

- Spreadsheet export - You may export unposted batch transactions and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import batch transactions from a saved "*Excel Workbook (*.xlsx) file type.*

Column headings and rows

Column headings

Show where to enter the basic information:

Column heading	*Description*
Reference:	*The number of the document, which contains the details of the transaction. It may be an invoice*

	number for a sales transaction, a supplier invoice number for a purchase transaction, cheque number for a payment mad, deposit or receipt for a payment received, etc., depending on the batch type.
Date:	*The date of the transaction. This date must be a valid date within any accounting period within a financial year.*
Description:	*A brief description of the details of the transaction.*
Account:	*The account which must be debited or credited with the transaction.*
Tax:	*The tax account - the correct tax code must be selected if you are registered as a VAT/GST/Sales Tax Vendor and/or if VAT/GST/Sales Tax is applicable to an entry or transaction. The Tax amount will be calculated automatically based on the percentage of the selected tax code.* *If you are not registered as a VAT/GST/Sales Tax Vendor, and/or if VAT/GST/Sales Tax is not applicable to all the transactions in the batch or journal, you may select to hide the Tax column for the specific batch or journal.*
Amount:	*The amount of the transaction. if VAT/GST/Sales Tax is applicable, it may be inclusive or exclusive of Tax (VAT/GST/Sales Tax),*

Rows

For each source document or transaction you need to enter the basic information in a row on the Batch entry screen.

Should you, for example, make one payment or issue a cheque for petrol and repairs and wish to allocate the petrol to one account and the repairs to another account, you need to enter each of these items (parts of a transaction) in 2 separate rows.

You will still need to use one reference number (same cheque number) for both transactions. You will then have one source document (cheque) with 2 entries representing 2 transactions with the same party.

The descriptions entered in the description fields should be entered sensibly; they should enable anybody to determine the origin and nature of the transaction.

Some general recommendations for transaction descriptions entered in journals. Here are a few tips:

1. *Be concise: Transaction descriptions should be brief and to the point. Avoid including unnecessary details that do not add to the understanding of the transaction.*
2. *Be specific: The description should clearly identify the nature of the transaction and the accounts*

affected. For example, instead of simply saying "payment," include the name of the vendor and the invoice number.

3. *Use consistent terminology: Use the same terminology consistently throughout the journal to ensure clarity and avoid confusion.*
4. *Include reference numbers: Whenever possible, include reference numbers such as invoice numbers, purchase order numbers, or account numbers in the description. This can make it easier to track transactions and reconcile accounts.*
5. *Avoid abbreviations: Unless they are widely understood and accepted in your industry, avoid using abbreviations in transaction descriptions. This can help to avoid confusion and ensure that the descriptions are clear to everyone who reads them.*
6. *Include any relevant details: If there are any special circumstances or details related to the transaction, include them in the description. This can help to provide context and ensure that the transaction is properly understood.*

By following these general recommendations, you can help to ensure that your transaction descriptions are clear, concise, and easy to understand. This can be helpful for accounting and record-keeping purposes, as well as for communication with others who may need to understand the transactions.

You may define any abbreviations, which you wish to enter in the description fields for each description, which is of a repetitive nature. You only need to enter the key or keys to transfer the full description when the cursor is in the description field of the batch entry screen.

Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Batch entry screen - Context menu

In addition to the standard account lookup in the "*Account*" column, you may use the right-click context menu and select options to select accounts in batches, to edit an account, etc.

You may also copy and paste the "*Contra account*, *Date*, *Reference*" and "*Description*" from one line to another.



The options are as follows:

1. Lookup document - In addition to the lookup function in the "*Accounts / Debtors / Creditors*" column in the ""*Batch entry*" screen you can choose to search for a specific document. You can use the advanced search and filter options in the "Document entry" screen to select a specific document.
    - Once you have selected a document (invoice or credit note), the debtor's (customer/ client) account associated with the document (invoice or credit note) will appear in the "*Accounts / Debtors / Creditors*" column of the "*Batch entry*" screen, be selected.
    - Once you have selected a document (purchase or supplier return), the creditor (supplier / vendor) account associated with the document (purchase or supplier return) will be selected in the "*Accounts / Debtors / Creditors*" column of the "*Batch entry*" screen .
2. Lookup document with amount - The option is similar to the Lookup document context menu option.
3. Lookup debtor - In addition to the lookup function in the "*Account*" column in the "*Batch entry*" screen, you can choose to lookup a debtor (customer / client) account from the "*Debtor accounts*" screen. On the "*Debtor accounts*" screen, you can use the filter and search options to select a specific debtor (customer / client) account.
4. Lookup creditor - In addition to the lookup function in the "*Account*" column in the "*Batch entry*" screen you may choose to lookup a creditor (supplier / vendor) account from the "*Creditor accounts*"

screen. On the "*Creditor accounts*" screen, you can use the filter and search options to select a specific creditor (supplier / vendor) account.

5. Copy - Copy the "*Contra account, Date, Reference*" or "*Description*" from one transaction in a batch to another transaction.

6. Select from account open item list - You may select a debtor (customer / client) or creditor (supplier / vendor) account on the "*Batch entry*" screen (right-click on selected transaction) and select the "*Select from account open item list*" option. The "*Open item selection*" screen will list the unlinked transactions as well as transactions with outstanding amounts for the relevant debtor (customer / client) or creditor (supplier / vendor) account. You then choose to link this transaction to a specific outstanding transaction on this open item list.

7. Edit accounts - If you have selected a debtor (customer / client) or a creditor (supplier / vendor) account, the details (ie Account Code, Name and Address) will be displayed on the top left of the "*Batch entry*" screen. If it does not match the source document, or something has changed, you can choose to edit the account.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Batch entry - Context menu - Lookup document

In addition to the lookup function in the "*Accounts / Debtors / Creditors*" column in the ""*Batch entry*" screen you can choose to search for a specific document. You can use the advanced search and filter options in the "Document entry" screen to select a specific document.

- Once you have selected a document (invoice or credit note), the debtor's (customer/ client) account associated with the document (invoice or credit note) will appear in the "*Accounts / Debtors / Creditors*" column of the "*Batch entry*" screen, be selected.

- Once you have selected a document (purchase or supplier return), the creditor (supplier / vendor) account associated with the document (purchase or supplier return) will be selected in the "*Accounts / Debtors / Creditors*" column of the "*Batch entry*" screen.

To select an account from documents in a batch:

1. Select a transaction in the batch.

2. Right-click and select the Lookup document option on the context menu. The Document entry list screen for Invoices will by default be displayed. You may select any other document type (i.e. credit

notes, quotes, purchases, supplier returns or orders).



3. Select the document from the list. (You may use the sort and filter options to locate a specific document).

4. Click on the OK button. The transaction with the system date will automatically be inserted in the batch. The document number as well as the Your reference (if entered in documents) will be displayed in the Description column of the Batch entry screen.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Batch entry - Context menu - Lookup document with amount

The option is similar to the Lookup document context menu option.

To select an account from documents in a batch:

1. Select a transaction in the batch.

2. Right-click and select the Lookup document with amount option on the context menu. The "*Document entry*" list screen for *Invoices* will by default be displayed. You may select any other document type (i.e. credit notes, quotes, purchases, supplier returns or orders).



3. Select the document from the list. (You may use the sort and filter options to locate a specific document).

4. Click on the OK button. The transaction with the system date will automatically be inserted in the batch. The document number as well as the Your reference (if entered in documents) will be displayed in the Description column of the Batch entry screen.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Batch entry - Context menu - Lookup debtor

In addition to the lookup function in the "*Account*" column in the "*Batch entry*" screen, you can choose to lookup a debtor (customer / client) account from the "*Debtor accounts*" screen. On the "*Debtor accounts*" screen, you can use the filter and search options to select a specific debtor (customer / client) account.

To select a debtor account in a batch:

1. Select a transaction in the batch.

2. Right-click and select the Lookup debtor option on the context menu. The "*Debtor accounts*" list screen is displayed:



3. Select the debtor (customer / client) account. (You may use the sort and filter options to locate a debtor (customer / client) account).

4. Click on the OK or Open button. The selected account will be transferred to the account column.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Batch entry - Context menu - Lookup creditor

In addition to the lookup function in the "*Account*" column in the "*Batch entry*" screen you may choose to lookup a creditor (supplier / vendor) account from the "*Creditor accounts*" screen. On the "*Creditor accounts*" screen, you can use the filter and search options to select a specific creditor (supplier / vendor) account.

To select a creditor account in a batch:

1. Select a transaction in the batch.

2. Right-click and select the Lookup creditor option on the context menu. The "*Creditor accounts*" list screen is displayed:



3. Select the creditor (supplier / vendor) account. (You may use the sort and filter options to locate a creditor (supplier / vendor) account).

4. Click on the OK or Open button. The selected account will be transferred to the account column.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Batch entry - Context menu - Copy

Copy the "*Contra account, Date, Reference*" or "*Description*" from one transaction in a batch to another transaction.

To copy and paste Contra account, Date, Reference or Description from a transaction in a batch to another transaction:

1. Select a transaction to copy from.

2. Right-click and select the Copy → Copy from / init → Contra account, Date, Reference or Description options on the context menu.

3. Select the transaction to paste the copied field to.

4. Right-click and select the Copy → Paste to / perform → Contra account, Date, Reference or Description options on the context menu. The selected field's content will be pasted or replaced in the

selected transaction.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with a Help Authoring Tool

Batch entry - Context menu - Select from account open item list

---

You may select a debtor (customer / client) or creditor (supplier / vendor) account on the "*Batch entry*" screen (right-click on selected transaction) and select the "*Select from account open item list*" option. The "*Open item selection*" screen will list the unlinked transactions as well as transactions with outstanding amounts for the relevant debtor (customer / client) or creditor (supplier / vendor) account. You then choose to link this transaction to a specific outstanding transaction on this open item list.

To copy and paste Contra account, Date, Reference or Description from a transaction in a batch to another transaction:

To select a creditor account in a batch:

1. Select a transaction in the batch.
2. Right-click and select the Select from account open item list option on the context menu. The "*Open item selection"* screen is displayed:



3. Select the transaction(s) on the "*Open item selection*" screen.
4. Add a tick in the "*X*" column to link.
5. Click OK to link the transaction in the Batch to the selected transaction(s) in the " *Open item selection*" screen.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Edit accounts from the Batch entry screen

If you have selected a debtor (customer / client) or a creditor (supplier / vendor) account in a batch, the details (i.e. Name, address will be displayed on the top of Batch entry screen which does not match the details on the source document, you may need to edit the account.

1. Select the debtor (customer / client) or a creditor (supplier / vendor) account and click on the Edit button of the "*Debtor accounts"* list screen or *Creditor accounts* list screen.
2. Edit the account, as necessary and click on the OK or Save button of the Debtor account edit form or Creditor account edit form.
3. Click on the Close button of the *accounts* screen.
4. Reselect the account and the updated information will be displayed on the top of Batch entry screen.

Create new accounts from the Batch entry screen

If you enter an invalid account code or account description in the standard filter options for the account lookup in the "*Accounts*" column for a transaction, a confirmation message will be displayed.

"w Account does not exist, do you wish to create it?" (where "w" does not exist in the chart of accounts, debtor accounts or creditor accounts)



If you click on the Yes button, the "*Account type*" screen is displayed:



Select the account type for which you need to create a new account. The account types are as follows:

1. Debtors - The "*Debtor accounts*" list screen, will be displayed on which you may use the search and filter options to locate a debtor (customer / client) account. If the account does not exist, you may click on the New button and create a new debtor (customer / client) account.

2. Creditors - The "*Creditor accounts*" list screen, will be displayed on which you may use the search and filter options to locate a creditor (supplier / vendor) account. If the account does not exist, you may click on the New button and create a new creditor (supplier / vendor) account.

3. Bank account, Tax account and General ledger account - The Accounts screen will be displayed. You may filter for that account and create the new account, if necessary.

You may configure the Account types to be included in the lookup Account lookup. On the F10:Setup Advanced tab, you may set the Account lookup type to:

- *All (default) all account types,*
- *General ledger – All account types, except Debtors, Creditors.*
- *Debtors (only Debtor accounts),*
- *Creditors (only Creditor accounts).*
- *Open item – Only those General ledger, Debtor and Creditor accounts for which Open item is activated.*

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Accounts lookup - Batches

When the cursor is in various fields on a screen, osFinancials5/TurboCASH5 will display the lookup screen for that specific field. A lookup screen is basically a list of all the valid master records in a Set of Books from which you need to select one item from the list.

Some lookup screens contains all accounts. Other lookup screens lists only ledger accounts / only debtor accounts and / only creditor accounts.

Disabled or blocked accounts will be excluded from some lookups.

Debtor / Creditor accounts - "Account disabled" field selected (ticked) on Accounting information tab (Default ribbon).

Accounts - "Status" field set to "Disabled". (Setup → Accounts on the Setup ribbon). For example;

W *if a ledger account is disabled, it will not be listed on the Accounts lookup when processing transactions.*

W *if a Tax type account (Tax code) is disabled, the disabled accounts will not be available on the Tax lookup in batches.*

Account lookup for Contra account in batch setup

The last selected contra account for a batch will be displayed in the Batch entry selection screen.

If no contra account is displayed in the Contra account, you need to select a contra account.

If a contra account is displayed in the Contra account column, and you wish to select a different contra account for a selected batch, you may change it.

The options to select a contra account is as follows:

1. Access the batch.
2. Click on the F10:Setup - *Options for this batch* - Standard tab.
3. Select the contra account on the "*Accounts*" lookup.



Bank accounts - Payments and receipt batches - Select contra accounts disabled.

When creating Bank accounts, a Payments and Receipt batch is linked to the bank account. The Bank account will be by default set as the contra account of the Payments and Receipt batches. The select Contra account option, will for this reason be disabled for Payments and Receipt batches linked to Bank accounts.

You may also go to the Setup ribbon and select Setup → Batch types. *Then click on the Edit button to launch the F10:Setup - Options for this batch - Standard tab.*

Account lookup for ledger reports



Account lookup for selecting accounts when entering transactions

The lookup in the batch entry screen automatically filter the code or the description. When the Account or Tax columns are focused, you may type the code or description. In this example, the description is typed as “*fu*” and it lists only those accounts with the starting with the typed characters, e.g. *Fuel and Oil* and *Furniture...*



The number of records matching your search characters will be displayed.

Your search characters entered will be displayed at the bottom of the lookup as well as above the column descriptions.

You may configure the Account types to be included in the lookup Account lookup. On the F10:Setup Advanced tab, you may set the Account lookup type to:

- *All (default) all account types,*
- *General ledger – All account types, except Debtors, Creditors.*
- *Debtors (only Debtor accounts),*
- *Creditors (only Creditor accounts).*
- *Open item – Only those General ledger, Debtor and Creditor accounts for which Open item is activated.*

Context menu (right-click) lookup on Batch entry screen:



You may right-click on a selected transaction to allocate a transaction to a debtor (customer / client) or creditor (supplier) account, or to copy and paste a contra account, reference or date from one transaction to other transaction(s)

Configure the account lookup list for batches

To display only the accounts for the specific transactions you need to enter in the batch, you may configure the accounts to be listed in the lookup.

To do this, you may select the Account lookup type option and the Contra account lookup type option on the F10:Setup - *Options for this batch* - Advanced tab as follows:

1. All - select to display all accounts (i.e. General ledger, Debtors, Creditors and Special ledgers).
2. General ledger - select to display all General ledger accounts (excluding Debtors, Creditor and Special ledgers). Examples would be if only need to enter and process transactions which does not apply to Debtors or Creditor accounts, e.g. Depreciation or adjustments to General ledger accounts in the General journal. Other examples would be cash purchases in the Payments journal or Petty cash payments journal which need to be allocated to the Expense and Asset accounts).
3. Debtors - select to display only Debtor accounts (excluding General ledger, Creditors and Special ledgers). An example would be if only sales invoices are batched and entered into the Sales journal for which you only need to select the Debtor accounts. Another example would be if you only batch or group deposits (receipts) for payments received from Debtors.
4. Creditors - select to display all Creditor accounts (excluding General ledger, Debtors, and Special ledgers). An example would be if only purchase invoices (received from creditors) are batched and entered into the Purchase journal for which you only need to select the Creditor accounts. Another example would be if you only batch or group a payments (cheque counterfoils or payment remittance advises) for payments made to Creditors.

Tax column - Tax lookup

If the No tax option on the F10:Setup - *Options for this batch* - Standard tab is not ticked (default option), the Tax lookup list will also be displayed.



The number of records matching your search characters will be displayed.

Your search characters entered will be displayed at the bottom of the lookup as well as above the column descriptions.

If the No tax option on the F10:Setup - Options for this batch - Standard tab is ticked, the Tax column and Tax lookup list will not be displayed.

Create accounts if the account does not exist

If you enter an invalid account code or account description in the standard filter options for the account lookup in the Accounts column for a transaction, a confirmation message will be displayed.

> "w Account does not exist, do you wish to create it?" (where "w" does not exist in the chart of accounts, debtor accounts or creditor accounts)

If you click on the No button, you will be returned to the batch entry screen, on which you may select a different account.

If you click on the Yes button, you may select the "*Account type*" screen is displayed:



Select the account type for which you need to create a new account. The account types will launch the screens as follows:

1. Debtors - The "*Debtor accounts"* list screen, will be displayed on which you may use the search and filter options to locate a debtor (customer / client) account. If the account does not exist, you may click on the New button and create a new debtor (customer / client) account.
2. Creditors - The "*Creditor accounts"* list screen, will be displayed on which you may use the search and filter options to locate a creditor (supplier / vendor) account. If the account does not exist, you may click on the New button and create a new creditor (supplier / vendor) account.
3. Bank account, Tax account and General ledger account - The Accounts screen will be displayed. You may filter for that account and create the new account, if necessary.

Created with the Standard Edition of HelpNDoc: Transform Your Word Document into a Professional eBook with HelpNDoc

Batch entry screen - Posted batches tab

All transactions are entered into batches and documents and when these batches and documents are updated or posted to the Ledger transactions are generated. All transactions are stored in osFinancials5/TurboCASH5 for up to two years. The format in which transactions are stored in osFinancials5/TurboCASH5 is the same as the way they are entered in the batch entry screens. The quality of your reports depends on the care you have taken to enter your data or transactions correctly and to optimise the various fields in the batch entry screens.

You may enter thousands of transactions of a different nature.osFinancials5/TurboCASH5 have provided you with a powerful facility to retrieve reports on each of these Batch types. You may print batch type reports for specific periods, or by Batch numbers, or batch names. You are then able to view and analyse

these transactions for each of the specific Batch types (Journal types), in which they were entered into the system.

- Sales - Sales journal
- Purchases - Purchase journal
- Payments - Payments journal
- Receipts - Receipts journal
- Petty cash - Petty cash payments journal
- General - Adjustments, correction of errors, Depreciation, Payroll transactions, etc. - General journal

You may also create additional batch types to enter and update or post specific transactions to the Ledger. These additional Batch types would then be reflected in the Batch type report.

If you generate documents in Documents (Default ribbon), the documents will be updated and posted to the Ledger and be included in the Batch type reports for the following Journals:

- *Sales journal - Invoices and Credit notes*
- *Purchase journal - Purchase documents and Supplier return documents.*

In addition to the Batch type Reports Options on the Reports → Batch entry menu, you may print a batch type report for a specific posted batch.

To print a batch type report for a specific batch:

1. On the Default ribbon, select Batch entry (F2).

   You may also print the same batch type reports in Tools → Global processes → Reverse posted batch/document (Setup ribbon).

2. Select the specific Batch type.
3. Click on the Posted batches tab. The Batch entry tab listing all batches and documents posted to the ledger is displayed:



4. The context menu (right-click) are as follows:

    a) Details - Select to open the Details tab for a selected batch.

    b) Report - This will launch the old standard batch type report for a specific batch.

5. The columns of the Batch entry tab is as follows:

    a) ID - Batch ID as automatically generated for each batch created.

    b) Alias (batch name) - This is the name entered in the "*Change alias*" field before you post the batch.

    > *In the case of documents, the document number will be listed. Document numbers are generated automatically generated.*

    c) Date - The date and time on which the batch was posted to the ledger.

    d) Line count - The number of transactions (including balancing transactions) in batches. In the case of documents,the line count is the debtor / creditor account, the contra account and the tax (VAT/GST/Sales tax) account as set in the Ledger tab of the selected stock item.

    e) Document id - This is the record id automatically generated when a new document is created.

    > *In the case of Batches the "Document id" will always be "0".*

    f) Min date - The date of the first transaction entered in the batch.

g) Max date - The date of the last transaction entered in the batch.

6. Select a specific batch and double-click it. The Details tab is displayed:



Line	Reference	Date	Description	Account	Cost centre 1	Cost centre 2	Default account	Tax	Debit	Credit	Amount entry	Amount exclusive
1	INV001	2022/03/07	Paint - Exterior	D1ABGRE Mr. AB Green	Empty	Empty	010-000	860-010	1,150.00	0.00	1,150.00	☑
2	INV002	2022/03/09	Install - Built-in cupboard	D1MACDS MAC Shop Decor Specialists	Empty	Empty	010-000	860-010	1,725.00	0.00	1,725.00	☑
3	INV003	2022/03/10	Paint - Exterior	D1ABGRE Mr. AB Green	Empty	Empty	010-000	860-010	1,150.00	0.00	1,150.00	☑
4	INV004	2022/03/12	Install - Built-in cupboard	D1MDAVI Mr. Mike Davies	Empty	Empty	010-000	860-010	1,725.00	0.00	1,725.00	☑
5	********	2022/03/07	Paint - Exterior	T860010 Output VAT - 15%	Empty	Empty	-	-	0.00	150.00	150.00-	☑
6	********	2022/03/07	Paint - Exterior	G010000 Sales	Empty	Empty	-	860-010	0.00	1,000.00	1,000.00-	☑
7	********	2022/03/09	Install - Built-in cupboard	T860010 Output VAT - 15%	Empty	Empty	-	-	0.00	225.00	225.00-	☑
8	********	2022/03/09	Install - Built-in cupboard	G010000 Sales	Empty	Empty	-	860-010	0.00	1,500.00	1,500.00-	☑
9	********	2022/03/10	Paint - Exterior	T860010 Output VAT - 15%	Empty	Empty	-	-	0.00	150.00	150.00-	☑
10	********	2022/03/10	Paint - Exterior	G010000 Sales	Empty	Empty	-	860-010	0.00	1,000.00	1,000.00-	☑
11	********	2022/03/12	Install - Built-in cupboard	T860010 Output VAT - 15%	Empty	Empty	-	-	0.00	225.00	225.00-	☑
12	********	2022/03/12	Install - Built-in cupboard	G010000 Sales	Empty	Empty	-	860-010	0.00	1,500.00	1,500.00-	☑
12									5750.00	5750.00	0.00	

The columns are similar to the Batch entry screen. Note the following columns:

- *Default account - The Contra account field of the batch setup (Options for this batch - Standard tab).*
- *Amount entry - Amount entered Exclusive / Inclusive of tax in the Debit / Credit columns.*
- *Amount Exclusive - 0 = True (Exclusive) and 1 = False (Inclusive).*

7. Click on the Print button. The Batch type transactions will be printed. An example is as follows:

Page 1 -


C:\osfinancials5\plug_ins\reports\GENERAL\documents\postedbatch.rep

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no. 336012345
Tax reg. no. 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000
E-mail: myrnail@myisp.net
Website:

Batch type report - Posted batch
Batch type : Salesjnl.
Alias (batch name) : Sales2203

Batch id : 10028
Batch type id : 1
Batch no. : 00000113
File name : bat0t1

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2022/03/07	INV001	Paint - Exterior Empty, Empty	D1AB-GRE Mr. AB Green G010-000	860-010	150.00	1,150.00	0.00
				Total		**1,150.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**Tax**	**Tax amount**	**Debit**	**Credit**
2022/03/09	INV002	Install - Built-in cupboard Empty, Empty	D1MA-CDS MAC Shop Decor Specialists G010-000	860-010	225.00	1,725.00	0.00
				Total		**1,725.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**Tax**	**Tax amount**	**Debit**	**Credit**
2022/03/10	INV003	Paint - Exterior Empty, Empty	D1AB-GRE Mr. AB Green G010-000	860-010	150.00	1,150.00	0.00
				Total		**1,150.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**Tax**	**Tax amount**	**Debit**	**Credit**
2022/03/12	INV004	Install - Built-in cupboard Empty, Empty	D1MD-AVI Mr. Mike Davies G010-000	860-010	225.00	1,725.00	0.00
				Total		**1,725.00**	**0.00**
Date	**Reference**	**Description**	**Account / Contra account**	**Tax**	**Tax amount**	**Debit**	**Credit**
2022/03/07	*******	*Paint - Exterior Empty, Empty	T860-010 Output VAT - 15% -	-	0.00	0.00	150.00
2022/03/07	*******	*Paint - Exterior Empty, Empty	G010-000 Sales -	860-010	-150.00	0.00	1,000.00
				Total		**0.00**	**1,150.00**
Date	**Reference**	**Description**	**Account / Contra account**	**Tax**	**Tax amount**	**Debit**	**Credit**
2022/03/09	*******	*Install - Built-in cupboard Empty, Empty	T860-010 Output VAT - 15% -	-	0.00	0.00	225.00
2022/03/09	*******	*Install - Built-in cupboard Empty, Empty	G010-000 Sales -	860-010	-225.00	0.00	1,500.00

Page 2 -



Some additional information for consultants and advanced users (using the SQL Browser Plugin or FlameRobin) are displayed in the right-hand block. The details are as follows:

- *ID - Batch ID as automatically generated for each batch created.*
- *Batch type ID - This is the ID generated when a batch type is created in Setup → Batch types.*
- *Batch No. - Internal number for each batch automatically generated.*
- *File Name - The File name as automatically generated.*

8. After printing the batch - click on the Close button.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Batch setup

---

osFinancials5/TurboCASH5 also allows you to set and configure the "*Batch entry*" screen for each batch or journal to meet your own specific requirements. The following two (2) options is available:

- Standard tab - In addition to selecting the contra account, various settings and configuration options, you may set the amount entry columns to "*Debit, Credit*" or "*Allow both*" to enter amounts faster and more accurately.

- Advanced tab - In addition to various settings and configuration options, the "*Account code lookup type*" and "*Contra account lookup type*" may be set to list only those accounts to select from in the Accounts lookup when processing transactions.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

F10:Batch setup - Standard tab

---

osFinancials5/TurboCASH5 allows you to set the Standard options for each batch or journal to make the entering and processing of transactions easier, faster and more accurate.



The options are as follows:

1. Contra account - Select the default balancing account contra account for the batch. When you balance the batch, osFinancials5/TurboCASH5 will generate the balancing transaction to the contra account for the total amount of all the transactions for each date.

> *For example in the SALES JOURNAL you would set up the contra account to be the SALES account and enter all the DEBIT transactions for the various debtors. When you balance the batch, generates CREDIT transactions to the SALES account.*

> *In the case of the Payments and Receipts journal, the contra account is always the Bank account*

and cannot be changed.



Post in period 0 - This option is not available for the Payments and Receipts journal. since you will not be allowed to post transactions for opening balances. If you need to take-on the opening balances for bank accounts, you need to process the opening balances in a normal batch type, e.g. "General journal".

2. No Tax - Hide the Tax column in the batch or journal entry screen as well as the Tax account lookup (Search). This option should only be used if no VAT/GST/Sales Tax is applicable to all transactions entered in the batch or journal or if the user is not registered as a VAT/GST/Sales Tax Vendor. However, there may be certain transactions, such as opening balances, depreciation transactions, or other non-taxable transactions, where VAT/GST/Sales Tax is not applicable. In such cases, you have the option to disable the Tax feature in the batch.

   By disabling the Tax in the batch, the tax account lookup will be hidden, indicating that no tax is applicable to any of the transactions within the batch. This eliminates the need to specify tax treatment for each individual transaction and streamlines the data entry process for non-taxable transactions.

Some examples of transactions where VAT/GST/Sales Tax may not be applicable:

- *Opening balances: When setting up your accounting system, you may need to enter opening balances for your accounts. These balances represent the financial position of your business at the beginning of a specific accounting period. Since opening balances are not actual transactions involving the sale or purchase of goods or services, VAT/GST/Sales Tax is not applicable.*

- *Depreciation entries: Depreciation is an accounting entry that reflects the decrease in value of an asset over time. It is a non-cash expense and does not involve any actual transaction or the application of VAT/GST/Sales Tax.*
- *Journal entries for adjustments: Journal entries made for adjustments, corrections, or reclassifications within your accounting system are not transactions that trigger VAT/GST/Sales Tax. These entries are made to ensure accurate financial reporting and may involve reclassifying expenses or revenues, correcting errors, or adjusting account balances.*
- *Internal transfers: If your business has multiple locations or departments and you need to transfer assets, inventory, or funds between them, these internal transfers are not subject to VAT/GST/Sales Tax. Internal transfers are internal movements within your organization and do not involve the sale or purchase of goods or services to external parties.*
- *Inter-company transactions: If your business has multiple entities or subsidiaries and you need to record transactions between them, these inter-company transactions may not involve VAT/GST/Sales Tax. Instead, these transactions may be recorded as eliminations or internal accounting entries to consolidate financial statements.*

These are just a few examples where VAT/GST/Sales Tax may not be applicable. The key is to identify transactions that are not related to the sale or purchase of goods or services to external parties. By selecting the appropriate tax treatment, or disabling the tax feature altogether, you can ensure accurate tax calculations and reporting for the transactions where VAT/GST/Sales Tax is applicable and streamline the data entry process for non-taxable transactions.

3. Increment reference - If the Reference number of most of the transactions are the same, you may leave the setting for this option blank. When proceeding to the next line, the previous line's reference number will be blank. You may over type these, if necessary.

   If the Reference number of most of the transactions are following in a sequence (e.g. payment numbers, invoice numbers, etc.), you may select (tick) this option. When proceeding to the next line, the previous line's reference number will be repeated. You may over type the next reference number, if necessary (for example if more than 1 item is purchases on the same cheque or payment number and need to be allocated to different accounts).

4. Consolidate balancing - If you select (tick) this option, the balancing entries generated (when you click on the F5:Balance icon), will be grouped to the balancing entry by date.

The Tax report (Reports → Tax) does not include the Sales journal. It only includes Sales documents (i.e. Invoices an Credit notes). Transactions on other Batch types may cause similar errors.

The reason for this, is the Consolidate balancing option on the Standard tab - F10:Setup on the

Options for this batch screen. When setting up the batch, an information message will be displayed.

"Consolidating lines and using tax will mess up your tax report! Please make sure you do not use tax or do not consolidate lines!"

Click on the OK button and click on the F10:Setup icon and deselect (remove the tick) from the Consolidate balancing field on the Standard tab of the "Options for this batch" screen.

Balance the batch again.

5. Contra account per line - If you select (tick) this option, each time you select an account, you to also need to select a contra account. In this way you can select a different contra account for each transaction. When you balance the batch, will generate all the transactions to each of these contra accounts.

6. Inclusive mode - Select (tick) to enter amounts in the inclusive mode. If not selected (not) ticked, the default for entering amounts, is exclusive.

7. Repeat details - If the descriptions of most of the transactions are of a repeating nature, you may select (tick) this option. When proceeding to the next line, the previous line's descriptions will be repeated. You may over type these, if necessary.

If *Abbreviation definitions* are set, you may type a character or a few characters to auto-complete the descriptions.

8. Amount entry - This setting allows you to enable or block amount entry in the debit and/or credit columns of batches. You may select Allow Both (enter amounts in both the debit and credit column), Debit (enter amounts in the debit column only) or Credit (enter amounts in the credit column only). The recommended amount entry and lookup type settings for batch types, is as follows:

BATCH TYPES	*Lookup Type*	*Contra account lookup type*	*DEBIT /CREDIT*
Sales journal	*Debtors*	*General ledger*	*Debit*
Sales returns	*General ledger*	*Debtors*	*Credit*
Purchases	*General ledger*	*Creditors*	*Credit*
Purchase returns	*Creditors*	*General ledger*	*Debit*
Payments	*All*	*All*	*Debit*

Receipts	*All*	*All*	*Credit*
General journal	*All*	*All*	*Allow both (Debit / Credit)*

9. Post in period 0 - If you need to enter opening balances in the current year (not in last year) select (tick) this option.

In the case of the Payments and Receipts batches, the Post in period 0 setting is not available.

10. Minimum chars before search - The default value is 0. If you enter one (1) invalid account code or description on the lookup, an message will be displayed, e.g.

"z Account does not exist, do you wish to create it?"

You can set the number of characters before receiving this confirmation message.

You have the option to click No and select another account. If you click Yes, you have the options to create a new account for a selected account type (i.e. ledger, bank, tax, debtor or creditor.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's User-Friendly UI

F10:Batch setup - Advanced tab

---

osFinancials5/TurboCASH5 also allows you to set the advanced options for each batch or journal to make the entering and processing of transactions easier, faster and more accurate.



The options are as follows:

1. Always balance - Automatically balance the transactions in the batch or journal
2. Not open item batch - Disables the Open item selection screens and Open item confirmation messages
3. Remember inclusive - Save the settings for tax on the Contra account.
4. Auto-alias - Select to automatically generate aliases for this batch.
5. Only look in account for search - To be advised.
6. Remember tax on contra account - Save the settings for tax on the Contra account.
7. Remember contra on account - Save the settings for the Contra account (Balancing Entry) on the selected Account.
8. Projects - Activate projects for this batch.
9. Cost centres - Activate cost centres for this batch.
10. Cost centre - Select the default cost centre for this batch. Cost centres will only be available if cost groups are added in Setup → Groups.
11. Account code lookup type - Select to filter list of accounts to be displayed in the lookup facility:
    a) All - select to display all accounts (i.e. General ledger, Debtors, Creditors and Special ledgers).
    b) General ledger - select to display all General ledger accounts (excluding Debtors, Creditor and Special ledgers). Examples would be if only need to enter and process transactions which does not apply to Debtors or Creditor accounts, e.g. Depreciation or adjustments to General

ledger accounts in the General journal. Other examples would be cash purchases in the Payments journal or Petty cash payments journal which need to be allocated to the Expense and Asset Accounts).

c) Debtors - select to display only Debtor accounts (excluding General ledger, Creditors and Special ledgers). An example would be if only sales invoices are batched and entered into the Sales journal for which you only need to select the Debtor accounts. Another example would be if you only batch or group deposits (receipts) for payments received from Debtors.

d) Creditors - select to display all Creditor accounts (excluding General ledger, Debtors, and Special ledgers). An example would be if only purchase invoices (received from creditors) are batched and entered into the Purchase journal for which you only need to select the Creditor accounts. Another example would be if you only batch or group a payments (cheque counterfoils or payment remittance advises) for payments made to Creditors.

e) Special ledgers - select to display all Special ledger accounts (i.e. General ledger, Debtors and Creditors).

f) Open item – Only those General ledger, Debtor and Creditor accounts for which Open item is activated.

12. Contra account code lookup type - Select to filter list of accounts to be displayed in the lookup facility for Contra accounts or Balancing transaction accounts:

a) All - select to display all accounts (i.e. General ledger, Debtors, Creditors and Special ledgers).

b) General ledger - select to display all General ledger accounts (excluding Debtors, Creditor and Special ledgers).

c) Debtors - select to display only Debtor accounts (excluding General ledger, Creditors and Special ledgers).

d) Creditors - select to display all Creditor accounts (excluding General ledger, Debtors, and Special ledgers).

e) Special ledgers - select to display all Special ledger accounts (i.e. General ledger, Debtors and Creditors).

Created with the Standard Edition of HelpNDoc: Easily create Help documents

F9:Batch processing options

Batch processing options contains various options to process transactions in unposted batches, export and import functions. Various functionalities to generate and process transactions is also available.

Process the batch options - Normal batch entry

Batch processing options:

1. Click Launch the correct batch type.

2. Click on the F9: Process icon. The Process the batch options screen is displayed:



3. Select one of the following options:

    a) Abbreviation definition - You may define any abbreviations, which you wish to enter in the description fields for each description, which is of a repetitive nature. You only need to select the key to transfer the full description when the cursor is in the description field of the batch entry screen. Abbreviation definitions may also be used in the description column of lines in documents (invoices, credit notes, quotes, purchases, supplier returns and orders).

    b) Balance batch - Before you may proceed to post a batch, you need to balance the batch. This will not be necessary when your batch is in balance (i.e. where you have entered debit transactions and credit transactions of equal value) in a batch.

    c) Delimited file import - Select and open a valid comma separated value file format to import the transactions in a an unposted batch. This feature will import batch transactions exported using the Write delimited file option.

    d) Erase batch - You may delete an entire batch, including all the entries, which you may have entered or which was imported into the batch.

e) Generate multiple transactions - This option allows you to process transactions for all debtor (customer / client) accounts that matches specific criteria. You may also process transactions for creditor's with charge amounts.

> *Generate multiple transactions - will be replaced with the following in:*
>
> - *Receipts batches - Create receipts - You may create a receipt from a receipt batch, print it out and hand it to a customer or the party from which you have received payment. A receipt will automatically be generated and the transaction for the receipt will automatically be entered in the selected Receipts journal.*
> - *Payment batches - Creditor balances to date - The "Creditor balances at date" batch processing option allows you to add payment transactions for all your creditors (suppliers) into the payments batch at a specified date. You may then edit the batch (for example, decide which creditors (suppliers) to pay, change the amounts, delete creditors (suppliers), etc.).*

f) List Batch - After entering all your transactions in a batch, and before updating or posting the transactions to the ledger, it is recommended to print a list of the transactions entered in the batch. You may need to check the transactions and edit the batch, if necessary, before you post the batch.

g) Post batch - Posting a batch is the final step in batch processing. To Post the transactions in a batch, will automatically update the ledger accounts, general ledger (with its control accounts) and the subsidiary ledgers (individual ledger accounts for the Debtors and Creditors) simultaneously.

h) Repeating transactions - The Repeating transactions feature allows you to enter transactions, which occur on a periodic basis. They may be weekly, monthly, quarterly or annually, etc. You may enter the transactions once and, when due, copy them into the normal batch, edit (if amounts have changed), delete or add an entry.

i) Change alias (batch name) - The alias provides the opportunity for you to add an unique name for the batch type. For example, you may use a specific batch type (e.g. general journal) for many different transactions and may post many general journal transactions in a month or even in a year. You need to enter these in the Batch header.

Auto-alias - Setting may also be activated on the F10:Setup - Advanced tab - "Options for this batch". This will automatically generate the system date as the alias (batch name) (e.g., “20210331”) for the batch.

Auto generated - Alias in Receipts batches - TR00001, TR00002,etc. These aliases prefixed with "TR" (consisting of seven (7) digits) will automatically be generated in receipt batches when the "Receive payment" option is used in Open item link context menu.

See -

- *Receive payment for a selected debtor (customer / client) account.*
- *Receive payment for a selected creditor (supplier / vendor) account.*

j) Totals for each period - Once you have entered transactions for more than one accounting period in any batch (journal), you may view the totals for each accounting period of the transactions in the batch (journal). This will display the total amount for the debit transactions, as well as the total amount for the credit transactions in each respective accounting period.

k) Write delimited file - Export and save the transactions in a an unposted batch to a file in a comma separated value file format.

l) Reverse batch (D<-->C) - If transactions were entered incorrectly in the debit column in stead of entering the transactions in the credit column, and *vice versa,* you may transfer (switch) the transaction amounts as entered into the credit columns to the debit columns and *vice versa* for any unposted batch.

m) Posted batches import - This feature is not supported in this version of osFinancials5/TurboCASH5. It is recommended to use the Write delimited file option to export and save the transactions in a an unposted batch to a file in a comma separated value file format. You may then use the Delimited file import option to select and open a valid comma separated value file format to import the transactions in a an unposted batch.

osFinancials5 supports the "Excel Workbook (.xlsx) file type Spreadsheet import and export feature.*

- *Spreadsheet export - You may export unposted batch transactions and save it as a "Excel Workbook (*.xlsx) file type.*
- *Spreadsheet import - You may import batch transactions from a saved "Excel Workbook (*.xlsx) file type.*

n) Automatic payments - You may pay your creditor (supplier / vendor) accounts, as well as refunds to debtor (customer / client) accounts (with credit balances, which need to be refunded) via the electronic banking system. The transactions for accounts with outstanding transactions and balances will be transferred into the "*Automatic payments*" screen, where you may select the accounts and outstanding amounts you need to pay.

o) Automatic receipts - You may receive payments from debtor (customer / client) accounts for their accounts via the electronic banking system. The transactions for debtor (customer / client) accounts with outstanding transactions and balances will be transferred into the "*Automatic receipts*" screen, where you may select the debtor (customer / client) accounts and outstanding amounts you need to receive from the debtor 's Bank accounts.

p) Import a posted batch - This option allows you to import the transactions from a posted batch in the same Set of Books.

q) Payroll import - This is a plugin - *Shop* - Licence : Once-off - Supported applications: Logisal, RoosRoos and Unit 4.

4. Click on the OK button.

Process the batch options - Repeating batch entry

In Repeating transactions batch entry screens (Edit - Repeating transactions) the F9:Process lists six (6) "*Process the batch*" options:



1. Erase batch - You may delete an entire batch, including all the entries, which you may have entered or which was imported into the batch.
2. List Batch - After entering all your transactions in a batch, and before updating or posting the transactions to the ledger, it is recommended to print a list of the transactions entered in the batch. You may need to check the transactions and edit the batch, if necessary, before you post the batch.
3. Write delimited file - Export and save the transactions in a an unposted batch to a file in a comma separated value file format.
4. Delimited file import - Select and open a valid comma separated value file format to import the transactions in a an unposted batch. This feature will import

batch transactions exported using the Write delimited file option.

5. Import a posted batch - This option allows you to import the transactions from a posted batch in the same Set of Books.

6. Payroll import - This is a plugin - *Shop* - Licence : Once-off - Supported applications: Logisal, RoosRoos and Unit 4.

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Abbreviation definition

You may define any abbreviations, which you wish to enter in the description fields for each description, which is of a repetitive nature. You only need to enter the key or keys to transfer the full description when the cursor is in the description field of the batch entry screen.

You may now assign more than 1 key for abbreviation definitions.

Abbreviation definitions may also be used in the description column of lines in documents (invoices, credit notes, quotes, purchases, supplier returns and orders) .

To set an abbreviation definitions:

1. When the cursor is in the description field (of any Batch entry screen) when entering a transaction, click on the F9:Process icon. The Process the batch options screen will be displayed.

2. Select the Abbreviation definition option and click on the OK button.



3. Enter any alphabetical and/or numeric key(s) on your keyboard you wish to assign to an abbreviation.

> *Use the record buttons add, edit, delete, save the abbreviations.*
>
> *You may click on the column headings to sort and filter the abbreviations on the list.*

4. Enter the description for the abbreviation.

> *The description should be useful to debtors or creditors if the abbreviation key is selected when entering descriptions for transactions for debtors (customers / clients) or creditors (suppliers), since this abbreviation will be displayed on debtor statements and creditor remittance advises.*

5. Click on the X button on the titlebar.

To print a list of abbreviations:

If you click on the Print list button on the first screen of the Set an abbreviations screen, a list of your abbreviations will be printed.



If you press any of your abbreviation keys the descriptions will be transferred to the description field for a transaction. In this example, the descriptions for the p and r keys will be transferred to the description fields of the batch entry screen. If you have assigned numerical characters (0 to 9) they will be listed before the alphabetical keys are listed.

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Change alias (Batch name)

The alias provides the opportunity for you to add an unique name for the batch type. For example, you may use a specific batch type (e.g. general journal) for many different transactions and may post many general journal transactions in a month or even in a year.

Auto-alias - Setting may also be activated on the F10:Setup - Advanced tab - "Options for this batch". This will automatically generate the system date as the alias (batch name) (e.g., “20210331”) for the batch.

Auto generated - Alias in Receipts batches - TR00001, TR00002,etc. These aliases prefixed with "TR" (consisting of seven (7) digits) will automatically be generated when the "Receive payment" option is used in Open item link context menu.

See -

- *Receive payment for a selected debtor (customer / client) account.*
- *Receive payment for a selected creditor (supplier / vendor) account.*

The alias enables you to easily identify and select specific batches (journals). The alias (batch name) will be displayed on the bottom section next to the Open and Cancel buttons of the Batch type selection screen.

You may need to identify and select a specific batch type from the following options:

- Tools → Export posted batches option - Batches List Lookup screen to export specific posted batches.
- Posted Batches tab of the Batch entry screen - View the details and/or print the batch type report for a specific batch.
- Import a posted batch (F9:Process) - To Import all the transactions of a specific batch which have already been posted / updated to the ledger.
- Tools → Global processes → Reverse posted batch/document . This will cancel (unpost) the posted batch and import it to the Batch entry screen for the selected batch.

If you do not utilise this feature to change the alias, you may not find it easy to identify the correct batch.

The alias is displayed directly after the batch type name in square [ ] brackets on the title bar of a selected batch type. For example, if you access the "*General jnl.*", "*General jnl. - [General jnl.]*" will be displayed on the title bar.



After changing the alias for a batch type, the alias will be displayed in the square brackets [ ] on the title bar. For example, if we use the General journal to record the Opening balance transactions, you may change the alias to display the "*General jnl. -[OpenBalances]*" description.

You will then be able to identify the Batch number by the alias on various options.

When selecting a batch on the Batch entry selection screen, the Alias will be displayed on the left side of the Open and Cancel buttons.

If the alias was not changed, the name of the selected batch type will be displayed.



Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Balance batch

Before you may proceed to post a batch, you need to balance the batch.

This will not be necessary when your batch is in balance (i.e. where you have entered debit transactions and credit transactions of equal value) in a batch.

An example for this is when you take-on opening balances from a trial balance, obtained from the accounting records of your previous accounting system.

The Tax report (Reports → Tax) does not include the Sales journal. It only includes Sales documents (i.e. Invoices an Credit notes). Transactions on other Batch types may cause similar errors. The reason for this, is the Consolidate balancing option on the Standard tab - F10:Setup on the Options for this batch screen. When setting up the batch, an information message will be displayed.

> "Consolidating lines and using tax will mess up your tax report! Please make sure you do not use tax or do not consolidate lines!" .

Click on the OK button and click on the F10:Setup icon and deselect (remove the tick) from the Consolidate balancing field on the Standard tab of the "Options for this batch" screen. Balance the batch again.

To balance a Batch:

1. Click on the F5:Balance icon.

Right-click on the selected batch (journal) on the Batch type selection screen, and select the Balance batch option on the context menu.

You may click on the F9:Process icon. You then need to select the Balance batch from the list of batch processing options.

2. When this process is finished, the balancing entries will automatically be inserted directly below your last transaction entry. An example of the transactions entered in the Sales journal, is as follows:



a) Reference - Balancing entries are indicated by 8 asterisks (********) in the Reference Field.

b) Date - The Date of the balancing entries will be the date of the last transaction, which you have entered.

> *If you have entered transactions with dates in more than one accounting period, balancing entries will be generated for each accounting period.*

c) Description - Balancing entries for the description of the transactions, as entered in the batch, will be generated for each entry, excluding Tax (VAT/GST/Sales Tax) and also for the Tax (VAT/GST/Sales Tax) amounts.

> *In cases where the Consolidate balancing option on the Standard tab of the F10:Setup on the Batch entry screen is selected (ticked), the BALANCING ENTRY followed by the Batch name and the alias name are displayed in the Description field.*
>
> *Once again, make sure that No Tax (VAT/GST/Sales Tax) is applicable to all transactions in the batch.*
>
> *You may then over type these descriptions, as it is not very meaningful to an outside auditor or accountant. If you over type these, it will definitely make it easier to trace and reconcile transactions.*

Steps after balancing the batch

After the batch balances, you still need to do the following to finalise the batch:

1. Click on the F8:List icon to print a list of the transactions in the batch.

> *It is a good idea to list the batch, and check the entries on the batch thoroughly. If there are any errors, you may edit the batch, before posting the batch.*

2. Click on the F6:Post icon to post the batch. The transactions will automatically be posted (updated) to the ledger.

> *In this example, it would debit the individual accounts (i.e. Debtor accounts), credit the total to the contra account (i.e. sales account) and credit the VAT amount to the Output VAT account.*

> *You may also post batches in Update ledger (Batches tab) (*Default ribbon*), or from the Post batch option on the Batch type selection screen's context menu.*

Created with the Standard Edition of HelpNDoc: Save time and frustration with HelpNDoc's WinHelp HLP to CHM conversion feature

List batch

After entering all your transactions in a batch, and before updating or posting the transactions to the ledger, you need to print a list of the transactions entered in the batch.

> *It is recommended to review the batch list and edit or correct any transactions before proceeding to post the batch (journal). This ensures that the transactions are accurate and complete before being updated to the ledger.*
>
> *Printing the list of transactions allows you to have a physical record that can be used for reference, auditing, or reconciliation purposes.*

> *Once a batch is posted, any errors or corrections would need to be addressed through additional journal transactions or by reversing the posted batch and making the necessary corrections before reposting it.*
>
> *It's important to ensure accuracy in the initial batch entry and review process to minimize the need for subsequent corrections.*

> *Using the printed batch list as an index or cover for the supporting source documents is a good practice. It provides a clear connection between the batch list and the underlying transactions, serving as evidence or proof of the recorded transactions.*

This can be helpful during audits or when reviewing the accuracy and completeness of the batch. Keeping the supporting documents organized and easily accessible alongside the printed batch list helps maintain proper documentation and facilitates efficient reference and verification processes.

Tax authorities and legislation in various jurisdictions often prescribe specific retention periods for financial documents and records. These retention periods determine how long businesses are required to keep their documents as proof of profits, deductions, and other financial transactions. The purpose of these regulations is to ensure that businesses maintain proper records for auditing, compliance, and legal purposes.

The retention periods can vary depending on the jurisdiction and the specific type of document. It's important for businesses to familiarize themselves with the applicable regulations in their jurisdiction and ensure that they comply with the required retention periods. This may involve retaining documents such as invoices, receipts, bank statements, financial statements, and other supporting documentation for a certain number of years.

By adhering to the prescribed retention periods, businesses can meet their legal obligations, facilitate audits or inspections, and maintain a reliable and accurate record-keeping system. It's always recommended to consult with tax professionals or legal advisors to ensure compliance with the specific requirements of your jurisdiction.

You may list the entries at any time when transactions have been entered in a batch, even if the batch has been balanced or not. Before printing a list of your batch transactions, you need to decide if you wish to include the balancing entries. Should you wish to include the balancing entries on your batch list, you need to first balance the batch.

To list transactions entered in a batch:

1. Once the transactions are entered in a batch, you may print a list of transactions entered in the batch to check the transactions.



2. Click on the F8:List icon to print a list of the transactions in the batch.

> *You may also right-click on the selected batch (journal) on the "Batch type" selection screen, and select the Print option on the context menu.*

> *You may click on the F9:Process icon. You then need to select the List batch option from the list of batch processing options.*

3. An example of the transactions in the "*List batch - - Unposted batch*" report, is as follows:


C:\osfinancials5\plug_ins\reports\GENERAL\documents\batch.rep

List batch - Unposted batch

Batch name Sales jnl.
Alias (batch name) Sales2203

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2022/03/07	INV001	Paint - Exterior Empty, Empty	D1AB-GRE G010-000	T860-010	150.00	1,150.00	
2022/03/07	********	*Paint - Exterior Empty, Empty	T860-010 860-010		0.00		150.00
2022/03/07	********	*Paint - Exterior Empty, Empty	G010-000 010-000	T860-010	-150.00		1,000.00
				Total		1,150.00	1,150.00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2022/03/09	INV002	Install - Built-in cupboard Empty, Empty	D1MA-CDS G010-000	T860-010	225.00	1,725.00	
2022/03/09	********	*Install - Built-in cupboard Empty, Empty	T860-010 860-010		0.00		225.00
2022/03/09	********	*Install - Built-in cupboard Empty, Empty	G010-000 010-000	T860-010	-225.00		1,500.00
				Total		1,725.00	1,725.00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2022/03/10	INV003	Paint - Exterior Empty, Empty	D1AB-GRE G010-000	T860-010	150.00	1,150.00	
2022/03/10	********	*Paint - Exterior Empty, Empty	T860-010 860-010		0.00		150.00
2022/03/10	********	*Paint - Exterior Empty, Empty	G010-000 010-000	T860-010	-150.00		1,000.00
				Total		1,150.00	1,150.00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2022/03/12	INV004	Install - Built-in cupboard Empty, Empty	D1MD-AVI G010-000	T860-010	225.00	1,725.00	
2022/03/12	********	*Install - Built-in cupboard Empty, Empty	T860-010 860-010		0.00		225.00
2022/03/12	********	*Install - Built-in cupboard Empty, Empty	G010-000 010-000	T860-010	-225.00		1,500.00
				Total		1,725.00	1,725.00

Check that the "Alias (batch name)" is displayed on correctly on the report.

4. The details of the transactions, displayed in nine (9) columns, are as follows:

   a) Date - This is the transaction date as entered in the date field.

   b) Reference number - This is usually refers to the source document from which the transaction is entered (e.g. the cheque number, deposit number, invoice number, supplier invoice number, etc. as entered in the "*Reference*" field.

If a batch is balanced, the reference number will be indicated by eight asterisks (********).

This refers to the contra account and cannot not, under any circumstances, be over typed or changed before you post the batch.

c) Description - This is the description of the transaction as entered in the description field.

> *This detail should be entered sensibly so as to enable any person or independent auditor to determine the nature of the transaction (what was paid, purchased, sold, etc.*

> *When a Creditor account or a Debtor account was selected, the descriptions should also make sense for the creditor or debtor if Creditor Remittance advises or Debtor statements are sent.*

d) Account - The account code for the selected General ledger, Creditor or Debtor account will be displayed.

> *If a batch is balanced (if the Consolidate balancing is selected in the Options for this batch), the selected Contra account (balancing account) will be displayed.*

> *If any VAT/GST/Sales Tax was applicable to transactions and a Tax account or Code was selected, the Tax code would also be displayed as a balancing entry.*

e) Contra account - This is the default the selected Contra account (balancing account) selected in the Options for this batch Standard tab.

f) Tax - The tax code will be displayed (if tax was selected for a transaction).

g) Tax - The tax amount will be displayed (if tax was selected for a transaction).

h) Debit - The amount of each transaction as entered in the debit column.

i) Credit - The amount of each transaction as entered in the credit column.

5. After printing the report, click on the Close button.

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

Post batch

Posting a batch is the final step in batch processing. To Post the transactions in a batch, will automatically update the ledger accounts, general ledger (with its control accounts) and the subsidiary ledgers (individual ledger accounts for the Debtors and Creditors) simultaneously.

Once the batches have been posted to the ledger, you need to create another transaction in another batch to correct any errors.

Since your reports will be as accurate as the transactions entered into a batch type, when the batch type is posted (updated) to the ledger, it is recommended that you print a batch list and to check your transactions before posting the batches.

Once transactions have been posted to the ledger, a trial balance can then be generated giving you a list of the accounts and the value of the transactions, as well as a profit / loss analysis. You may also print a wide range of reports for the posted transactions.

Before you start to post the batch, you need to balance the batch and check the descriptions of your balancing entries, You also need to change the alias for the batch, list the batch and check the entries if they are correct.

The transaction data in unposted batches are not included in any ledger reports. You may check for any unposted batches and/or documents in the Input → Checking for unposted items menu on the Default ribbon. You may then decide to post the batches if you wish to include these transactions in your reports.

osFinancials5/TurboCASH5 displays the posted transactions in the 3-column ledger account format. You may also view the posted transactions in general ledger and the subsidiary ledgers (debtors and creditors ledger) in the traditional T-Account format using the T-Account viewer.

To post a batch to the ledger:

1. Click on the F6:Post icon, to post (update) the batch to the ledger.

   You may also right-click on the selected batch (journal) on the Batch type selection screen, and select the Post batch option on the context menu.

   Before you start to post the batch, you need to balance the batch and check the descriptions of your balancing entries, You also need to change the alias for the batch, list the batch and check the entries if they are correct.

   You may click on the F9:Process icon. You then need to select the Post batch from the list of batch processing options.

2. The transactions in the Batch entry Transaction screen will be posted (updated) to the selected accounts in the batch.

3. Once the transactions are posted (updated) to the ledger, the Batch entry Transaction screen will automatically be closed and the Batch type selection screen will be displayed.

4. Click on the Cancel button, or press the Esc key on your keyboard, to exit this screen.

Post to last year

1. Transactions may however be posted to the previous financial year, after the year-end procedure is performed. Should the batch contain transactions with a date relating to the previous financial year, (for example, if the current financial year is from 01/03/2022 to 28/02/2023, and the date of the transaction is 10/02/2022), a confirmation message will be displayed.

   "Do you want to continue posting? Batch contains transactions posting to last year!"

2. Check that the date is correct - Last year's date.

3. Click on the Yes button. osFinancials5/TurboCASH5 will post the transaction to the previous (last) financial year.

If the date(s) of the transactions is incorrect:

1. Click on the No button.

2. Correct the date(s) of the transaction in the batch to this year.

3. Balance the batch once again.

4. Post the Batch.

Error message : Batch does not balance

Should the batch not be in balance or if the batch is not balanced, an error message will be displayed.

"Batch is not in balance!"

To fix this:

1. Click on the OK button.

2. Balance the batch.

3. Post the batch again.

Error message : Account disabled

You will not be allowed to post (update) the batch or document, if a selected the "*Account disabled*" field

on the Accounting information tab for a debtor (customer / client) (Debtors on the Default ribbon) or a creditor (supplier / vendor) (Creditors on the Default ribbon) account is selected.

If the "*Status*" field of a ledger account is set to "*Disabled*" for a ledger account (Setup → Accounts) it will also not allow you to post (update) the batch or document to the ledger.

An error message will be displayed.

> "This batch does not validate! Account disabled 000005 Mr. AB Green" (000005 Mr. AB Green is the account code and name of the debtor (customer / client) as per this example - creditor (supplier / vendor) accounts or ledger account)

This error may be caused by one of two reasons, i.e.

1. The incorrect debtor (customer / client), creditor (supplier / vendor) or ledger account was selected.
2. The "*Account disabled*" field is selected (ticked) on the Accounting information tab of the debtor (customer / client) or creditor (supplier / vendor) account. In the case of a ledger account, the "*Status*" field of a ledger account is set to "*Disabled*".

If you have selected an account in a Batch, and the account is disabled, osFinancials5/TurboCASH5 will display an error message when you post (update) the batch to the ledger:

1. Take note of the account code and name. You may also check that you have not selected the incorrect account.
2. Click on the OK button.
3. If the incorrect account has been selected, select the correct account in the batch and continue to post the batch.

If the selected account was correct, you need to follow the following process:

1. If it is a correct debtor (customer / client) or creditor (supplier / vendor) account, remove the tick in the "*Account disabled*" field on the Accounting information tab of the debtor (customer / client) or creditor (supplier / vendor) account. In the case of a ledger account, set the "*Status*" field to "*Enabled*".
2. Access the Batch type, from which this error message was generated, and post the batch again.

It is also a good idea to make a backup before posting, in case there is any incorrect allocations in the batch. If there are, it is easy to restore your data from your backup and correct the allocations before updating the transactions to the ledger again.

allows you to set the options or defaults for a batch to enable you to minimise errors and/or to maximise your productivity when you capture or enter transactions in a batch. The batch options or defaults only needs to be set once when you start to enter transactions for the first time, unless your requirements change.

You need to post (update) Payments and Receipt batches before you can do the Bank reconciliation (Cash / Bank entry on the Default ribbon) (reconcile your Payments and Receipts journals with your Bank Statement).

Post (update) transactions from the Update ledger (F3) option

This option is used to post (update) your batches to the ledger, which you have entered in Batch entry (Default ribbon) in the various batches. When these batches are updated to the ledger they will automatically pass the journals and post the transactions to the applicable accounts in the Ledger.

You may also post (update) these batches to the ledger from the following options:

- *F6:Post icon or Post batch batch processing option on the Batch entry screens.*
- *Post option on the context menu (right-click) on the Bach Type Selection screen.*

Steps before updating / posting

1. Balance the batch - If the debit and credit totals for the batch is not the same as displayed on the Batch type selection screen, you need to balance the batch. This will generate the balancing entries or transactions.
2. List the batch - Generate or Print a list of the transactions in the Batch.

You need to check the transactions to see that they are correct. This is your last chance to correct any incorrect transactions.

You may also need to attach the source documents to the Batch List for record and audit purposes.

To post (update) batches to the ledger:

1. On the Default ribbon, select Update ledger (F3). The "*Update invoices*" screen will be displayed.
2. Click on the Batches tab. The "*Update batches*" screen will be displayed. Any of the available batches, for which you have entered transactions, will be listed:



Batch numbers is automatically generated.

3. Select the following options:

   a) Select type - This is only active for documents if you click on the Documents tab.

   b) Suppress open item - By default, the following Open item selection screens will be displayed on which you need to link the debit and credit transactions when updating batches:

      i) Open item selection screen for debtor (customer / client) accounts if the Use Open item field on the Accounting information tab is selected.

      ii) Open item selection screen for creditor (supplier / vendor) accounts if the Use Open item field on the Accounting information tab is selected.

      Select the Suppress open item field, if you do not wish to use the Open item link selection facilities when updating or posting batches. You may then later use the Open item link facility to link the transactions.

   c) From ... to - This will display the Batch numbers "*From ... to*". This option allows you to select the starting Batch number on a drop-down list, and a last Batch number which you need to post (update) to the ledger. All batches (journals) within the selected range of Batch numbers will be posted (updated) to the ledger.

If you only need to post (update) one batch (journal) to the ledger, the Batch number in the From... and To... fields must be the same.

d) Selected - If you select this option, the "*From ... to*" fields and the drop-down lists for Batch numbers will be de-activated. An arrow will indicate the selected document. You may also use the down arrow or Up arrow keys on your keyboard, to select a document from the list.

4. Click on the Update button. osFinancials5/TurboCASH5 will automatically post (update) the transactions in the selected batches (journals) to the respective accounts in the General ledger, Debtor's ledger and/or Creditor's ledger.

Finding or locating specific batches

You may also use the following options to find or locate a specific batch or batches:

1. Search by Batch entry number -

2. Enter the Batch number - The Batch number will automatically be selected. If not, click on the Search button.

Sort sequences - Double-click on Column headings to sort the list of batches ascending or descending:

1. Batch entry number - By default, all Batch numbers are displayed ascending (smallest Batch number to the latest Batch number).

   If you double-click on this heading, it will list the Batch numbers in the descending sequence (from the latest Batch number to the smallest or first Batch number).

2. Batch type - By default, the batches are listed by Batch numbers. The batch descriptions or names (as created or edited in Setup → Batch types) may not be displayed in the ascending sequence.

   To display the batch descriptions or names in the descending sequence (9-0 / Z-A), double-click on this heading. To display the batch descriptions or names in the ascending sequence (0-9 / A-Z), double-click on this heading again.

3. User - By default, the batches are listed by Batch numbers. The Users (as created in Setup → Access control and which were logged on to the system and which have processed any transactions in Batches / Journals) may not be displayed in the ascending sequence.

   To display the Users in the descending sequence (9-0 / Z-A), double-click on this heading. To display the users in the ascending sequence (0-9 / A-Z), double-click on this heading again.

4. Online - By default, the batches are listed by Batch numbers. The Online column will display TRUE or

FALSE and may not be displayed in the ascending sequence.

To display the Online in the descending sequence (TRUE then FALSE), double-click on this heading. To display the users in the ascending sequence (FALSE then TRUE), double-click on this heading again.

Context menu options

If you select a batch on the list, you may right-click to launch the following context menu:



1. Update - will post (update) the transactions in the selected batch (journal) to the ledger.
2. Edit batch - will launch or open the selected batch entry screen. You may then edit the transactions in the batch, balance the batch, list the batch and change the alias, etc. before posting it to the ledger.
3. Delete batch - When a batch (journal) is posted (updated) to the ledger, it is automatically removed from the list of batches.

It is recommended that this option not be used to delete a batch (journal), but that batches rather be deleted in the Erase batch batch processing option.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Totals for each period

Once you have entered transactions for more than one accounting period in any batch (journal), you may view the totals for each accounting period of the transactions in the batch (journal). This will display the total amount for the debit transactions, as well as the total amount for the credit transactions in each respective accounting period.

To view the totals for each period:

For example, transactions have been entered for more than one accounting period (e.g. December, January and February), in a General journal, it would be displayed as follows:

1. Click on the F9: Process icon. The *Process the batch options* screen will be displayed.
2. Select the Totals for each period option, and click on the OK button. The *Totals for each Period* screen

is displayed:



3. Check that the totals for the debit transactions are equal to the credit transactions and that the *To Balance* column is reflecting a zero amount for each Accounting period.

4. Once finished checking the totals, click on the Close button on the title bar of the *Totals for each Period* screen or press the Esc key on your keyboard, to exit or close this screen.

Differences in the Amount to Balance column could implicate that the -

- *Batch is not balanced.*
- *Amounts in the Debit Amount column or the Credit Amount column are entered incorrectly (e.g. 54 as 45, etc.) This option is usually the case if the Amount entry is set to enter both Debit and Credit amounts in the Batch setup Options.*

You need to either balance the batch or find and enter the correct amount if an amount was entered incorrectly in the batch.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Edit unposted batch transactions

In addition to the Insert transactions to, and Delete transactions in, an unposted batch, you may use the following "*Options for this batch*" to edit or change transactions in an unposted batch:

1. Erase batch - You may delete an entire batch, including all the entries, which you may have entered or which was imported into the batch.

2. Reverse batch (D<-->C) - If transactions were entered incorrectly in the debit column in stead of entering the transactions in the credit column, and *vice versa*, you may transfer (switch) the transaction amounts as entered into the credit columns to the debit columns and *vice versa* for any unposted batch.

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

Erase batch

You may delete an entire batch, including all the entries, which you may have entered or which was imported into the batch.

Should you have deleted a batch by mistake, you cannot undo the delete. You need to re-enter or import all the transactions into the batch.

To erase a batch:

1. Click on the F9: Process icon. The Process the batch options screen will be displayed.
2. Select the Erase batch option, and click on the OK button.

   You may also right-click on the selected batch (journal) on the Batch type selection screen, and select the Erase batch option on the context menu.

   A Warning message will be displayed.

   "Are you sure you want to erase this entire batch?"

3. Click on the Yes button to permanently remove the transactions in the batch and close the batch entry screen.

   If you have selected the incorrect batch (journal), click on the No button to cancel this operation.

4. Click on the Close button on the title bar or press the Esc key on your keyboard, to close or exit the Batch entry transaction screen and/or the Batch type selection screens.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Insert transactions in a batch

Sometimes you may have entered a number of transactions in a batch. You may wish to insert a transaction in a specific place in the batch.

To insert a transaction in a batch:

1. Select the line or row in which you wish to insert a blank line or row above the selected transaction.
2. Click on the ^N:Insert icon (Ctrl + N) / (Insert).
3. A new blank row above a selected transaction will be inserted.
4. Enter the transaction in the inserted row or line.

Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with a Help Authoring Tool

Delete transactions in a batch

If an incorrect transaction have been entered in a batch, you may select the transaction and delete it from a row in a batch.

Should you have deleted a transaction by mistake, you cannot undo the delete. You need to re-enter the transaction, which is incorrectly deleted.

Should you wish to delete all the transactions in a batch, you may select the Erase batch option from the Process the batch options screen.

To delete transactions in a batch:

1. Select the transaction in the batch, which you wish to delete.

   Multi-select feature allows you to delete more than one (1) transaction at a time. To select the more than one (1) transaction, press the Ctrl key and keep it down while selecting the other lines to delete with a mouse click.

2. Click on the ^D:Delete icon (Ctrl + D). A confirmation message will be displayed:

   "Are you sure you wish to delete this transaction? (3)"
   ((3) is the number of selected transactions to be deleted) .

3. Click on the Yes button to delete the selected transaction.

If you have selected the incorrect transaction or row, click on the No button to cancel this action.

All the Balancing Entries may be deleted on the Delete Balance context menu of the selected batch type on the Batch type selection screen, if the selected batch (journal) is already balanced.

To delete a selected transaction, you need to select an account and/or enter the amount. If the reference number, date and description fields, contains data, but the account and/or amount fields are blank, you will not be allowed to delete the selected transaction.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Reverse batch (D<-->C)

Once a batch has been posted (updated) to the ledger with the amounts in the incorrect column (e.g. in the debit column instead of the credit column), this error will not be revealed by the trial balance. This is called errors of reverse posting.

You may check and edit the entries in a batch before posting or updating the transactions to the ledger. It is good practice to list the transactions in the batch and check your data thoroughly before posting a batch.

You may transfer the transaction amounts as entered into the debit columns to the credit columns and *vice versa* for any unposted batch.

This option should be used with utmost care and only if you have entered amounts in the incorrect side debit instead of credit and vice versa.

To reverse transactions in an unposted batch:

1. In the following example, the amounts for the transactions in the Sales journal (Batch type), were incorrectly entered in the credit column (instead of the debit column). The Batch entry screen for the Sales journal will display the incorrect transactions as follows:



> *Should this batch be posted (updated) to the ledger, the individual debtor accounts (and the Debtor's control account) will incorrectly be credited and the Sales account (income) incorrectly debited. This feature allows you to correct this with a few mouse clicks.*

2. Click on the F9:Process icon. The Process the batch options screen will be displayed.

3. Select the Reverse batch (D<-->C) option, and click on the OK button.

> *You may also right-click on the selected batch (journal) on the Batch type selection screen, and select the Reverse batch (D<-->C) option on the context menu.*

4. All amounts entered in the credit columns will be transferred to the debit column. If the batch was balanced, the Balancing amounts will also be transferred to the correct column (e.g. credit column).



Should the processing icons on the "Batch entry" screen is inactive during this process, you may need to close and reopen the batch.

Should this corrected batch be posted (updated) to the ledger, the individual debtor accounts (and the Debtor's control account) will correctly be debited and the Sales account (income) incorrectly credited.

If you have selected a Tax code, in the Cashbook (Receipts journal and Payments journal), the amount EXCLUSIVE of VAT/GST/Sales Tax (NOT the INCLUSIVE of VAT/GST/Sales Tax) is reflected in the amount column, when the cursor is not on the amount field of a transaction.

The following list indicates whether amounts of transactions for a specific batch type should be entered in the debit or credit columns in a batch entry screen:

Batch	*Debit / Credit (Amount entry)*
Sales	*Debit*
Sales returns	*Credit*
Purchase journal	*Credit*

Purchase returns journal	*Debit*
Receipts journal	*Credit*
Payments journal	*Debit*
Petty cash journal	*Credit*
General journal	*Both Debit and Credit*

Once a batch is posted of which the transactions have been entered in the incorrect amount columns (debits as credits and vice versa), you need to:

1. *Enter the transactions in another batch (journal) to cancel the transactions, which were incorrectly posted (updated) to the ledger.*
2. *Enter the transactions again to record the original transactions and post (update) it to the ledger.*

Another option is to make a backup and use the Cancel / Reverse posted batch in Tools → Global processes (Setup ribbon). This will cancel the batch and import it to the batch entry screen on which you may use the "Reverse batch (D<-->C)" option before posting the batch again.

Created with the Standard Edition of HelpNDoc: Why Microsoft Word Isn't Cut Out for Documentation: The Benefits of a Help Authoring Tool

F9:Batch processing options - Transactions

The following "*Options for this batch*" may be used to generate transactions.

1. Generate multiple transactions - This option allows you to process transactions for all debtor (customer / client) accounts that matches specific criteria. You may also process transactions for creditor's with charge amounts.

Generate multiple transactions - will be replaced with the following in:

- *Receipts batches - Create receipts - You may create a receipt from a receipt batch, print it out and hand it to a customer or the party from which you have received payment. A receipt will automatically be generated and the transaction for the receipt will automatically be*

entered in the selected Receipts journal.

- *Payment batches - Creditor balances to date - The "Creditor balances at date" batch processing option allows you to add payment transactions for all your creditors (suppliers) into the payments batch at a specified date. You may then edit the batch (for example, decide which creditors (suppliers) to pay, change the amounts, delete creditors (suppliers), etc.).*

2. Repeating transactions - The Repeating transactions feature allows you to enter transactions, which occur on a periodic basis. They may be weekly, monthly, quarterly or annually, etc. You may enter the transactions once and, when due, copy them into the normal batch, edit (if amounts have changed), delete or add an entry.

3. Automatic payments - You may pay your creditor (supplier / vendor) accounts, as well as refunds to debtor (customer / client) accounts (with credit balances, which need to be refunded) via the electronic banking system. The transactions for accounts with outstanding transactions and balances will be transferred into the "*Automatic payments*" screen, where you may select the accounts and outstanding amounts you need to pay.

4. Automatic receipts - You may receive payments from debtor (customer / client) accounts for their accounts via the electronic banking system. The transactions for debtor (customer / client) accounts with outstanding transactions and balances will be transferred into the "*Automatic receipts*" screen, where you may select the debtor (customer / client) accounts and outstanding amounts you need to receive from the debtor 's Bank accounts.

Created with the Standard Edition of HelpNDoc: Free help authoring environment

Generate multiple transactions

This option allows you to process transactions for all debtor (customer / client) accounts that matches specific criteria. You may also process transactions for creditor's with charge amounts.

To generate multiple transactions:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Batch type (except Payment and Receipt Journals, which is linked to Bank accounts) and click on the Open button.
3. Enter the Alias (batch name) in the "*Change alias*" field.

4. Click on the F10:Setup icon and select the Contra account.

5. Click on the F9: Process icon. The "*Process the batch*" screen will be displayed.

6. Select the "*Generate multiple transactions*" option.



7. The following five (5) options are available:

   a) Balance debtors with amount < x.xx - Generate transactions for those Debtor accounts, which have an outstanding balance of less than the amount you specify.

   b) Debtors with charge amount - Generate transactions for those Debtor accounts, which have a charge amount entered in the Debtor (Accounting information tab).

   c) Creditors with charge amount - Generate transactions for those Creditor accounts, which have a charge amount entered in the Creditor (Accounting information tab).

   d) Fixed amount to all debtors - Generate transactions for all Debtor accounts, to charge a fixed specified amount.

   e) Interest on overdue debtors - Generate transactions for those Debtor accounts, which are overdue and have a percentage monthly interest entered in the (Accounting information tab).

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

Balance debtors with amount < x.xx

You may generate transactions for those Debtor accounts, which have an outstanding balance of less than the amount you specify.

This feature may be used if you decide, for example, to write-off all debts of all the debtors who owe less than a specified amount, which are considered uneconomical to recover.

To generate multiple transactions for debtors with an outstanding amount less than a specified amount:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Batch type (except Payment and Receipt Journals, which is linked to Bank accounts) and click on the Open button.
3. Enter the Alias (batch name) in the *Change alias* field.
4. Click on the F10:Setup icon and select the Contra account.
5. Click on the F9: Process icon. The "*Process the batch*" screen will be displayed.
6. Select the "*Generate multiple transactions*" option.



7. Select and enter the following:
    a) Date for transactions - Enter or select the date for which the transactions should be generated.
    b) Contra account - Do not select.

The selected contra account is not stored. The contra account needs to be selected in the F10:Setup batch before balancing the batch.

c) To debtors with a balance less than (amount) - Specify an amount for which debtors owing less than this amount should be listed in the batch.

5. Click on the OK button. The Generate multiple transactions screen will automatically be closed, and the transactions for the Debtors will be imported into the selected batch.

6. Check the transactions and, if necessary, change the descriptions, etc.

Once you have finished entering / editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*
4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

Fixed amount to all debtors

You may generate transactions for all or selected Debtor accounts, to charge a fixed specified amount.

When this fixed amount transactions is generated, and once the batch has been posted, the Debtor accounts will be increased (debited) and the selected contra account (e.g. income account) will also be increased (credited).

To generate multiple transactions for fixed amount to debtors:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Batch type (except Payment and Receipt Journals, which is linked to Bank accounts) and click on the Open button.
3. Enter the Alias (batch name) in the "*Change alias"* field.
4. Click on the F10:Setup icon and select the Contra account. This is the account to be credited with the generated transactions. This account may be an Income or Sales account, or any other account you specify.
5. Click on the F9: Process icon. The "*Process the batch*" screen will be displayed.
6. Select the Generate multiple transactions option. The "*Generate multiple transactions"* screen will be displayed.
7. Select the Fixed amount to all debtors option. The screen will change to reflect the options for this option:



8. Select and enter the following:

    a) Date for transactions - Enter or select the date for which the transactions should be generated.

    b) Contra account - Do not select.

> *The selected contra account is not stored. The contra account needs to be selected in the F10:Setup batch before balancing the batch.*

    c) Description - Change "Description" with any description to suit your requirements.

> *The description must be useful to your debtors, since it will be displayed on Debtor statements.*

    d) To debtors for (amount) - Enter the amount, which should be charged to all Debtor accounts or a selected Debtor account.

    e) From debtor ... To - Select a specific Debtor account or a range of Debtor accounts from the Debtors lookup facility.

9. Click on the OK button. The Generate multiple transactions screen will automatically be closed, and the transactions for the selected Debtor accounts with the specified amounts, will be imported into the selected batch.

10. Check the transactions and, if necessary, change the descriptions, etc.

11. Click F10:Setup and select the contra account.

12. Click F5:Balance to generate balancing entries to the contra account.

> *Once you have finished entering / editing the transactions in the batch you need to: -*
>
> 1. *Change the Alias (Batch name).*
> 2. *Balance the batch.*
> 3. *List the batch.*
> 4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Easily convert your WinHelp HLP help files to CHM with HelpNDoc's step-by-step guide

Debtors with charge amount

osFinancials5/TurboCASH5 provides this useful feature to generate transactions for those Debtor accounts, which have a charge amount entered in the Debtors (Accounting information tab).

When this charge amount is generated and once the batch has been posted, the Debtor accounts will be increased (debited) and the selected contra account (e.g. income account) will also be increased (credited).

To generate multiple transactions for debtors with charge amount:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Batch type (except Payment and Receipt Journals, which is linked to Bank accounts) and click on the Open button.
3. Enter the Alias (batch name) in the "*Change alias*" field.
4. Click on the F10:Setup icon and select the Contra account.
5. Press or click on the F9: Process icon. The "*Process the batch*" screen will be displayed.
6. Select the "*Generate multiple transactions*" option.
7. Select the Debtors with charge amount option.



8. Select and enter the following:
    a) Date for transactions - Enter or select the date for which the transactions should be generated.
    b) Contra account - Do not select.

The selected contra account is not stored. The contra account needs to be selected in the F10:Setup batch before balancing the batch.

c) Description - Change "*My Description*" with any description to suit your requirements.

The description must be useful to your debtors, since it will be displayed on Debtor statements.

9. Click on the OK button. The *Generate multiple transactions* screen will automatically be closed, and the transactions for the Debtors which have charge amounts entered in the Accounting information tab of the Debtor account, will be imported into the selected batch.

10. Click F10:Setup and select the contra account.

11. Click F5:Balance to generate balancing entries to the contra account.

12. Check the transactions and, if necessary, change the descriptions, etc.

Once you have finished entering / editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*
4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Creditors with charge amount

This feature allows you to generate transactions for those Creditor accounts, which have a charge amount entered in the Creditor (Accounting information tab).

When this charge amount is generated and once the batch has been posted, the Creditor accounts will be increased (credited) and the selected contra account (e.g. expense or cost account) will also be increased (debited).

To generate multiple transactions for creditors with charge amount:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Batch type (except Payment and Receipt Journals, which is linked to Bank accounts) and click on the Open button.
3. Enter the Alias (batch name) in the *Change alias* field.
4. Click on the F10:Setup icon and select the Contra account. This is the account to be debited with the generated transactions. This account may be an Expense account, or any other account you specify.
5. Click on the F9: Process icon. The "*Process the batch*" screen will be displayed.
6. Select the Generate multiple transactions option. The "*Generate multiple transactions"* screen will be displayed.
7. Select the Creditors with charge amount option. The screen will change to reflect the options for this option:



8. Select and enter the following:

a) Date for transactions - Enter or select the date for which the transactions should be generated.

b) Contra account - Do not select.

> *The selected contra account is not stored. The contra account needs to be selected in the F10:Setup batch before balancing the batch.*

c) Description - Change "*My Description*" with any description to suit your requirements.

> *This description must be useful to your creditors, since it will be displayed on Creditor Remittance advises.*

9. Click on the OK button. The *Generate multiple transactions* screen will automatically be closed, and the transactions for the Creditors which have charge amounts entered in the Accounting information tab of the Creditor account, will be imported into the selected batch.

10. Check the transactions and, if necessary, change the descriptions, etc.

11. Click F10:Setup and select the contra account.

12. Click F5:Balance to generate balancing entries to the contra account.

> *Once you have finished entering / editing the transactions in the batch you need to: -*
>
> 1. *Change the Alias (Batch name).*
> 2. *Balance the batch.*
> 3. *List the batch.*
> 4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Interest on overdue debtors

You may generate transactions for those Debtor accounts, which are overdue and have a percentage monthly interest entered in Debtors (Accounting information tab).

If this option is initiated, osFinancials5/TurboCASH5 will calculate the Interest and generate the transactions. Once the batch has been posted, the Debtor accounts will be increased (debited) and the selected contra account (e.g. interest received - income account) will also be increased (credited).

To generate multiple transactions for interest on overdue debtor accounts:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Batch type (except Payment and Receipt Journals, which is linked to Bank accounts) and click on the Open button.
3. Enter the Alias (batch name) in the *Change alias* field.
4. Click on the F10:Setup icon and select the Contra account. This is the account to be credited with the generated transactions. This account should be an Income or Interest Received account.
5. Press or click on the F9: Process icon. The "*Process the batch*" screen will be displayed.
6. Select the "*Generate multiple transactions*" option.
7. Select the Interest on overdue debtors option. The screen will change to reflect the options for this option:



8. Select and enter the following:

a) Date for transactions - Enter or select the date for which the transactions should be generated.

b) Contra account - Do not select.

> *The selected contra account is not stored. The contra account needs to be selected in the F10:Setup batch before balancing the batch.*

c) Number of days overdue - Enter the number of days the account is overdue. Note it is important that the correct number of days be entered here. osFinancials5/TurboCASH5 will use this to calculate the Interest amount.

9. Click on the OK button. The Generate multiple transactions screen will automatically be closed and osFinancials5/TurboCASH5 will calculate the Interest and transfer the calculated interest transactions for the Debtors which have a monthly interest percentage entered in the Debtor account (Accounting information tab). The transactions will be imported into the selected batch.
10. Check the transactions and, if necessary, change the descriptions, etc.
11. Click F10:Setup and select the contra account.
12. Click F5:Balance to generate balancing entries to the contra account.

> *Once you have finished entering / editing the transactions in the batch you need to: -*
>
> 1. *Change the Alias (Batch name).*
> 2. *Balance the batch.*
> 3. *List the batch.*
> 4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Create receipts (Receipt batches)

Normally you would write out a receipt in a receipt book, and then enter the details of the hand-written receipt in the receipt batch.

You may create a receipt from a receipt batch, print it out and hand it to a customer or the party from which you have received payment. A receipt will automatically be generated and the transaction for the

receipt will automatically be entered in the selected Receipts journal.

To create a receipt:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Receipts journal.

> *Should you have more than one Bank account, you need to make sure that you select the correct Receipts journal for the Bank account into which you are going to deposit the payment received.*

3. Click on the Open button. The Batch entry screen for the selected Receipts journal will be displayed.
4. Enter the Alias (batch name) and press the Enter key, if necessary.
5. Click on the F9: Process icon. The Process the batch options screen will be displayed.
6. Select the Create receipts option, and click on the OK button. The "*Edit receipts options*" screen is displayed:



7. Enter and select the following options:

   a) Account - Select the Account to which you wish to allocate the moneys received from the Accounts lookup facility. Usually it would be a Debtor account for which the money is received. In some cases, it may also be a ledger account to be credited with the moneys received for cash (e.g. Sale of a Fixed Asset for cash).

   b) Date - The system date of your operating system will automatically be displayed in the date field. Enter the date or select the date, if necessary.

c) Description - Enter the description, which you wish to be displayed on the receipt, as well as on the details of reports and on the debtor statements if applicable.

d) Amount - Enter the amount in figures. You may enter up to Nine billion, nine hundred and ninety nine million, nine hundred and ninety nine thousand nine hundred and ninety nine (Rands, Euros, Pounds or Dollars) and ninety nine cents in this field (9,999,999,999.99).

> *If your system's digit separator id set to a comma and your system's Decimal symbol is set to a period, do not enter a comma as the decimal separator.*
>
> *If a comma is used as a digit separator, It will print and generate the transaction amount as 115,000.00 instead of 1,150.00.*

e) Payment method - Select the payment method Cash, Cheque, Credit Card or Other.

f) Print out - Select to print out or not to print the receipt in the print out field. If this field is left blank, no receipt will be printed, but the details of the receipt will generate a transaction in the batch entry screen.

g) Send report to - Select Screen, Printer, File, E-mail or Fax to generate the receipt.

h) Copies - Not implemented.

8. Click on the OK button. The receipt will be sent to the medium you have selected in the Send report to field, provided that the "*Print out*" field is selected. Click OK on the "*Report parameter*" screen.



9. An example of the printed "*Receipt*", is as follows:



To display the amount in words correctly on receipts, where the rules are different than in English or other languages, you need to select the Dutch text numbering option on Setup → System parameters (Setup ribbon).

10. The transaction for the receipt will automatically be inserted into the Receipts journal from which this option was initiated.

11. Click on F5:Balance. An example, of the balanced batch, is as follows:



You may change the receipt number in the reference field to the deposit number on which the receipt is deposited. It is important to use the deposit number as reference number. If this is not done, you may find difficulties when matching the bank statement with the transactions in the Receipts journal when you finalise the bank reconciliation.

Should the processing icons on the "Batch entry" screen is inactive during this process, you may need to close and reopen the batch.

Open item debtor (customer / client) accounts

If a debtor (customer / client) account were set as an Open item account, and when you edit or select a transaction. the "Open i be displayed. You may confirm or select a transaction to which you wish to apply the receipt.



Once you have finished entering / editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*

4. *Post the batch*.

Created with the Standard Edition of HelpNDoc: Effortlessly Spot and Fix Problems in Your Documentation with HelpNDoc's Project Analyzer

Creditor balances to date (Payments batches)

The "*Creditor balances at date*" batch processing option allows you to add payment transactions for all your creditors (suppliers) into the payments batch at a specified date.

You may then edit the batch (for example, decide which creditors (suppliers) to pay, change the amounts, delete creditors (suppliers), etc.).

To create outstanding transactions for creditors (suppliers) at a specified dates:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Payments journal.

> *Should you have more than one Bank account, you need to make sure that you select the correct Payments journal for the Bank account out of which you are going to pay the creditors (suppliers).*

3. Click on the Open button. The Batch entry screen for the selected Payments journal will be displayed.
4. Enter the "*Alias (batch name)*" and press the Enter key, if necessary.
5. Click on the F9: Process icon. The "*Process the batch*" options screen will be displayed.
6. Select the Creditor balances at date option, and click on the OK button. The "*Get date report value*" screen is displayed:



7. Select the date on which the creditor (supplier / vendor) accounts with outstanding balances to be added as transactions in the payments batch.
8. Click OK. The transactions for the creditor (supplier / vendor) balances as at the specified date will be

imported into the payments batch as follows:



N	Reference	Date	Description	Account	Tax	Debit	Credit	Open item
4	Bal0107	2021/07/01	BALANCE AT 2021/07/01	C2AONES A-ONE Suppliers	T Empty	1,725.00		
8	Bal0107	2021/07/01	BALANCE AT 2021/07/01	C2BESTS BEST Suppliers	T Empty	2,300.00		
10	Bal0107	2021/07/01	BALANCE AT 2021/07/01	C2ABCOS ABC-Office-Supplies	T Empty	975.00		
11	Bal0107	2021/07/01	BALANCE AT 2021/07/01	C2ABCOS ABC-Office-Supplies	T Empty	1,725.00		
12	Bal0107	2021/07/01	BALANCE AT 2021/07/01	C2ABCOS ABC-Office-Supplies	T Empty	1,725.00		
13	Bal0107	2021/07/01	BALANCE AT 2021/07/01	C2ABCSC ABC-Service-Centre	T Empty	1,150.00		
14	Bal0107	2021/07/01	BALANCE AT 2021/07/01	C2ABCSC ABC-Service-Centre	T Empty	1,150.00		
15	********	2021/07/01	BALANCE AT 2021/07/01	B810000 ABC - Bank	Bal		**1,725.00**	
16	********	2021/07/01	BALANCE AT 2021/07/01	B810000 ABC - Bank	Bal		**2,300.00**	
17	********	2021/07/01	BALANCE AT 2021/07/01	B810000 ABC - Bank	Bal		**975.00**	
18	********	2021/07/01	BALANCE AT 2021/07/01	B810000 ABC - Bank	Bal		**1,725.00**	
19	********	2021/07/01	BALANCE AT 2021/07/01	B810000 ABC - Bank	Bal		**1,725.00**	
20	********	2021/07/01	BALANCE AT 2021/07/01	B810000 ABC - Bank	Bal		**1,150.00**	
21	********	2021/07/01	BALANCE AT 2021/07/01	B810000 ABC - Bank	Bal		**1,150.00**	
14						10,750.00	10,750.00	

9. Edit the batch as necessary. In this example, transactions numbers 1 to 3 and 5 to 7 were deleted, since transactions of those creditor (supplier / vendor) accounts were excluded from this payment.

Should the processing icons on the "Batch entry" screen is inactive during this process, you may need to close and reopen the batch.

Open item creditor (supplier / vendor) accounts

If a creditor (supplier / vendor) account were set as an Open item account, and when you edit or select a transaction. the "Open
be displayed. You may confirm or select a transaction to which you wish to apply the payment.

In this example, a purchase transaction (i.e. PU002) has an outstanding balance which is imported.



Once you have finished entering / editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*
4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Free EPub producer

Automatic payments

You may use the "Creditor balances at date" batch processing option to generate all Creditor accounts with outstanding balances as at the specified date. The transactions will automatically be imported into the Payments journal.

You may pay your creditor (supplier / vendor) accounts, as well as refunds to debtor (customer / client)

accounts (with credit balances, which need to be refunded) via the electronic banking system. The transactions for accounts with outstanding transactions and balances will be transferred into the "*Automatic payments*" screen, where you may select the accounts and outstanding amounts you need to pay.

The accounts which have open or outstanding amounts will be listed. The (outstanding amount) balances are transferred to an intermediate account or clearing account on the date of the transactions.

Once the payment is cleared at the bank (on the due date) payment is deducted from the Bank account and will appear on the bank statement. When you allocate the transaction on the bank statement, the intermediate account or clearing (account contra account) will be debited.

> *Before using this feature, bank accounts need to be entered the Accounting information tab of Creditor (supplier / vendor) accounts (Default ribbon).*

To pay accounts using the automatic payments feature:

1. On the Default ribbon, select Batch entry (F2).
2. Select the General journal or any other batch type.
3. Click on the Open button. The "*Batch entry*" screen for the selected batch will be displayed.
4. Enter the Alias (batch name) and press the Enter key.
5. Click on the F9: Process icon. The "*Process the batch*" options screen will be displayed.
6. Select the "*Automatic payments*" option, and click on the OK button. The "*Automatic payments*" screen is displayed:



Debtor (customer / client) accounts, with a credit balance, which need to be refunded, may also be included in this "Automatic payments" feature.

See -

- *https://www.paiementor.com/keys-to-understand-the-sepa-messages-names/*
- *https://wiki.xmldation.com/General_Information/ISO_20022/pain.001*

7. All the creditors (supplier / vendor) accounts with transactions will be imported.

8. Select and enter the following:

   a) Contra Account - Select the intermediate account. This is basically a clearing account for the payments to creditor (supplier / vendor) accounts.

      It is recommended that a General ledger account, which is linked to the Current liabilities Account group be selected.

   b) Payment Date - Enter or select the date for which you need to process payments for creditor (supplier / vendor) accounts.

      The transactions on this date to the intermediate account or clearing account (Contra account), and calculate the due days as specified in the Due days field on the Accounting information tab of the selected creditor (supplier / vendor) account.

   c) Create Clieop File - If you select this option, you need to specify the name for the Clieop file.

      The Clieop file is a general accepted file format that can be read into a bank program for payments.

   d) Payment Bank Account - Enter the payment Bank account.

   e) Clieop comment - By default, this will be the system date in the format "*DD-MM-YYYY*". Enter a comment for the transaction.

   f) Export Type - "*None*" is the default option. This will transfer the selected transactions into the "*Batch entry*" screen. If you select the following export types you need to save a export file before the selected transactions is transferred into the "*Batch entry*" screen:

      i) Create a clieop file - Create an export file.

      ii) pain.001.001.03 - Create an export file in the XML Document type.

See -

- *https://www.paiementor.com/keys-to-understand-the-sepa-messages-names/*
- *https://wiki.xmldation.com/General_Information/ISO_20022/pain.001*

g) Do not close - By default, this option is not selected. If this option is selected, the Process ok button will be available.

h) Search and filter options -





9. Check that the payment information and outstanding amounts for each account is correct.

If you do not wish to pay an account at this stage, deselect (remove the tick) the "Pay transaction" field next to the selected creditor. If the "Pay transaction" field is not selected, no transactions will be generated for the account and the account will be excluded from the "Automatic payments report".

10. Click on the Print button to print a "*Automatic payments report*" for all accounts with outstanding amounts (balances) for which the "*Pay transaction*" field was selected. An example of the "*Automatic payments report*", is as follows:



11. Click on the Process button. All accounts with outstanding amounts (balances), for which the "*Pay transaction*" field was selected will be imported into the selected batch (journal).

> *If "Create a clieop file" or pain.001.001.03" is selected as the "ExportType" option, a "Save As" screen will be launched, in which the export file needs to be saved. Thereafter, all selected creditor (supplier / vendor) accounts, as well as debtor (customer / client) accounts, if any, with outstanding amounts (balances) for which the receive transaction field was selected, will be imported into the selected batch (journal).*



> *Debtor (customer / client) accounts, with a credit balance, which need to be refunded, may also be included in this "Automatic payments" feature.*

> *Once you have finished entering / editing the transactions in the batch you need to: -*
>
> 1. *Change the Alias (Batch name).*
> 2. *Balance the batch.*
> 3. *List the batch.*
> 4. *Post the batch.*

Export type : Clieop file

If the "*Create Clieop file*" option was selected as the "*ExportType*" field, the "*Save As*" screen will be displayed, if you click on the Update button of the "*Automatic payments*" screen.



Select the directory in which you need to store the file and specify the name for the file.

If the bank accounts is not entered for a creditor (supplier / vendor) account (on the Accounting information tab, a message similar to this will be displayed.

"No bank account for C2ABCOS ABC-Office-Supplies
Skiping record!"

Click on the Save button to save and generate the "*clieop*" export file. An example of the exported "*clieop*" file, is as follows:



Export type : pain.001.001.03

If the "*pain.001.001.03*" option was selected as the "*ExportType*" field, the "*Save As*" screen will be displayed, (after the "*Automatic receipts report*" is printed) if you click on the Update button of the "*Automatic receipts*" screen.



Click on the Save button. This will create an XML Document file type for the "*pain.001.001.03*" "*ExportType*".

The export file name will be generated as "pain_002", etc. These numbers indicate the version number of the file export.

An example of the "*pain.001.001.03*" export file, is as follows:



Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Automatic receipts

You may receive payments from debtor (customer / client) accounts for their accounts via the electronic banking system. The transactions for debtor (customer / client) accounts with outstanding transactions and balances will be transferred into the "*Automatic receipts*" screen, where you may select the debtor (customer / client) accounts and outstanding amounts you need to receive from the debtor 's Bank accounts.

The debtor (customer / client) accounts which have open or outstanding amounts will be listed. The (outstanding amount) balances are transferred to an intermediate account or clearing account on the date of the transactions.

Once the payment is cleared at the bank (on the due date) payment is received into the Bank account it will

appear on the bank statement. When you allocate the transaction on the bank statement, the intermediate account or clearing (account contra account) will be credited.

Before using this feature, bank account details need to be entered in:

- *Setup → Company information (Setup ribbon)*
- *Accounting information tab of Debtor (customer / client) accounts (Default ribbon).*

To process automatic receipts for debtor (customer / clients):

1. On the Default ribbon, select Batch entry (F2).
2. Select the General journal or any other batch type.
3. Click on the Open button. The "*Batch entry*" screen for the selected batch will be displayed.
4. Enter the Alias (batch name) and press the Enter key.
5. Click on the F9: Process icon. The "*Process the batch*" options screen will be displayed.
6. Select the "*Automatic receipts*" option, and click on the OK button. The "*Automatic receipts*" screen is displayed:



7. The bank account of the Set of Books as entered in Setup → Company information is automatically

displayed on this screen.

8. Select and enter the following:

    a) Use reference - Select to use the Invoice reference as entered in the "Your reference" field of the Document entry form.

    b) Contra account - This is basically a clearing account for the payments received from debtors.

    > *The contra account needs to be set in the F10:Setup.*
    >
    > *It is recommended that a general ledger account, which is linked to the Current assets Account group be selected.*

    c) From - Enter or select the date from which you need to process payments for debtor (customer / client) accounts.

    d) To - Enter or select the date until which you need to process payments for debtor (customer / client) accounts.

    > *The transactions for the debtor (customer / client) accounts created on and until the selected dates. After selecting (or reselecting) the dates, click on the Refresh button to update the listed transactions with the date selection.*

    e) SLEV - To be advised.

    f) B2B - To be advised.

    g) Refresh button - This will refresh the data in the "*Automatic receipts*" screen.

    h) Export Type - "*None*" is the default option. This will transfer the selected transactions into the "*Batch entry*" screen. If you select the following export types you need to save a export file before the selected transactions is transferred into the "*Batch entry*" screen:

        i) Create a clieop file - Create an export file.

        ii) pain.001.001.03 - Create an export file in the XML Document type.

        iii) pain.001.001.08 - Create an export file in the XML Document type. To use this export file type, you need to specify a valid "*Incassant* id" (Collector ID).

    These export files contains specific validation and parameters etc. for specific payment systems. These export files will instruct the banks or financial institutions to clear the payments to your debtors (customers / clients).

See -

- *https://www.paiementor.com/keys-to-understand-the-sepa-messages-names/*
- *https://wiki.xmldation.com/General_Information/ISO_20022/pain.001*

i) Account no. - The Bank account of the IBAN number (as entered in Setup → Company information).

j) IBAN - (International Bank Account Number) (as entered in Setup → Company information).

See - http://en.wikipedia.org/wiki/International_Bank_Account_Number

SWIFT - (Society for Worldwide Interbank Financial Telecommunication) - See - http://en.wikipedia.org/wiki/SWIFT / http://www.theswiftcodes.com/

SEPA - (Single Euro Payments Area) - See - http://en.wikipedia.org/wiki/Single_Euro_Payments_Area

k) BIC - (Bank identifier code) (as entered in Setup → Company information).

l) Payment date - Enter or select the date for which you need to process payments for debtor (customer / client) accounts.

The transactions will be generated on this date to the intermediate account or clearing account (Contra Account), and calculate the due days as specified in the "Due days" field on the Accounting information tab of the debtor (customer / client) account.

m) Extra line description - You may enter an extra description to be included in the export file, if required.

n) Credit note message 1 - You may enter message to be included in the export file, if required.

o) Credit note message 2 - You may enter message to be included in the export file, if required.

p) Credit note message 3 - You may enter message to be included in the export file, if required.

q) "*Incassant* id" (Collector ID) - Enter a valid "*Incassant* id" (Collector ID) in this field. This is required for the "*pain.001.001.08*" export file type.

r) Do not close - By default, this option is not selected. If this option is selected, the Process ok button will be available.

s) Search and filter options -





9. Check that the payment information and outstanding amounts for each account is correct.

> *If you do not wish to include a payment from a debtor at this stage, deselect (remove the tick) the Export field next to the selected debtor. If the "ExportType" field is not selected, no transactions will be generated for the debtor and the debtor will be excluded from the Automatic receipts report".*

10. Click on the Print button to generate a "*Automatic receipts report*" for all accounts with outstanding amounts (balances) for which the receive transaction field was selected.

> *If the bank accounts is not entered for a debtor (customer / client) account (on the Accounting information tab, a message similar to this will be displayed.*
>
> "No bank account for D1ROGSM Mr. Roger Smith
> Skiping record!"

An example of the printed "*Automatic receipts report*", is as follows:



11. Click on the Update button. If "*None*" is selected as the "*ExportType*" option, all debtor (customer / client) accounts with outstanding amounts (balances) for which the receive transaction field was selected, will be imported into the selected batch (journal).

If "Create a clieop file, pain.001.001.03" or "pain.001.001.08" is selected as the "ExportType" option, a "Save As" screen will be launched, in which the export file needs to be saved. Thereafter, all debtor (customer / client) accounts with outstanding amounts (balances) for which the receive transaction field was selected, will be imported into the selected batch (journal).



Once you have finished entering / editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*

4. *Post the batch*.

Export type : Clieop file

If the "*Create Clieop file*" option was selected as the "*ExportType*" field, the "*Save As*" screen will be displayed, if you click on the Update button of the "*Automatic receipts*" screen.



Select the directory in which you need to store the file and specify the name for the file.

Click on the Save button to save and generate the "*clieop*" export file. An example of the "*clieop*" export file, is as follows:



Export type : pain.001.001.03

If the "*pain.001.001.03*" option was selected as the "*ExportType*" field, the "*Save As*" screen will be displayed, (after the "*Automatic receipts report*" is printed) if you click on the Update button of the "*Automatic receipts*" screen.



Click on the Save button. This will create an XML Document file type for the "*pain.001.001.03*" "*ExportType*".

The export file name will be generated as "pain_002", etc. These numbers indicate the version number of the file export.

An example of the "*pain.001.001.03*" export file, is as follows:



Export type : pain.001.001.08

To use the "pain.001.001.08" "ExportType" option, you need to specify a valid "Incassant id" (Collector ID) on the "Automatic receipts" screen.

If no valid id, is specified, an error message, similar to the following; will be displayed.

"U heeft geen incassant id opgegeven!"

If the "*pain.001.001.08*" option was selected as the "*ExportType*" field, the "*Save As*" screen will be displayed (after the "*Automatic receipts report*" is printed), if you click on the Update button of the "*Automatic receipts*" screen.



Click on the Save button. This will create an XML Document file type for the "*pain.001.001.08*" "*ExportType*".

The export file name will be generated as "pain_009", "pain_011, etc. These numbers indicate the version number of the file export.

An example of the "*pain.001.001.08*" export file, is as follows:



Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Payroll import

Payroll plugin

Payroll - Manual - Shop - Licence : Once-off -

Supported applications: Logisal, RoosRoos and Unit 4.

Seamlessly import payroll data from supported applications like Logisal, RoosRoos, and Unit 4 directly into osFinancials5/TurboCASH5, simplifying payroll-related transactions.

Is the program you use not listed? No problem! With our commitment to customer satisfaction, simply

send us an export, and we will explore the possibility of adding that import. In most cases, the addition is free of charge.

Say goodbye to manual data entry and hello to efficiency as you effortlessly generate batches or journals for payroll processing within osFinancials5/TurboCASH5.

Payroll Plugin Access - Batch entry - F9:Process - Payroll import option.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Repeating transactions

The Repeating transactions feature allows you to enter transactions, which occur on a periodic basis. They may be weekly, monthly, quarterly or annually, etc.

You may enter the transactions once and, when due, copy them into the normal batch, edit (if amounts have changed), delete or add an entry. This facility will save you lots of time. You may identify those transactions in your business and enter them in this facility. A few examples of these entries are:

1. For entry in the General journal or alternative batch type.
    - Depreciation of fixed assets
    - Payroll journals or integration
2. For entry in the Payments journal
    - Debit orders to third parties
3. For entry in the Receipts journal
    - Debit orders from third parties, etc.

Repeating transactions may be processed via the following options:

- Edit → Repeating transactions – Enter the transactions once in the Repeating batch entry screen. You may then Import the transactions into the normal Batch entry screen using the Repeating transactions option on the F9:Process options.
- Import a posted batch option on the F9:Process options. Once you have entered and posted a normal batch, you may import the batch, edit it as required and then post it.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Enter / Edit - Repeating transactions

To enter Repeating transactions:

1. On the Default ribbon, select Edit → Repeating transactions.



The alias (batch name) is not entered on the Repeating transactions batch.

The alias (batch name) of the last Repeating transactions batch imported (F9:Process) will be displayed before the Open and Cancel buttons

The Debit and Credit totals will not be displayed. These totals are only displayed if the Batch type selection screen is launched from the Default → Batch entry (F2) on the Default ribbon.

2. Select the General Jnl batch type and click on the Open button.

To indicate that you have selected a Repeating Batch or Journal, note the following:

- ****Repeating transactions*** is displayed after the name of the batch type.*
- *No alias for the batch will be displayed in the screen heading (title bar).*

3. Click on the F10:Setup icon to set your batch up.

4. Set up the Repeating transactions General journal for depreciation transactions as follows:
    a) Contra account - Select the contra (balancing) account (e.g. Depreciation expense account).
    b) Amount entry - Select Credit.
5. Click on the Advanced tab.
6. Select the "*General ledger*" option for the Account lookup type, since you do not need to select Debtor or Creditor accounts when you enter transactions for depreciation.
7. Once setup; click on the OK button.

> *Tax*
>
> *Since No Tax (VAT/GST/Sales Tax) is applicable, to the depreciation transactions in this topic, we have selected to hide the Tax column in the Setup Options.*

8. You are now ready to capture your first repeating entry transaction.
    a) Reference: DE2203
    b) Date: 2022/03/31
    c) Description: Depreciation-Furniture and Fittings.
    d) Account: 600/020 Furniture and Fittings - Accumulated Depreciation
    e) Amount: 50.00 CR
9. Once finished, capture your second entry.
    a) Reference: DE2203
    b) Date: 2022/03/31
    c) Description: Depreciation-Motor Vehicles-Merc
    d) Account: 610/020 Motor Vehicles - Accumulated Depreciation
    e) Amount: 75.00 CR
10. Once finished, capture your third transaction.
    a) Reference: DE2203
    b) Date: 2022/03/31

c) Description: Depreciation-Motor Vehicles-Delivery Van

d) Account: 610/020 Motor Vehicles - Accumulated Depreciation

e) Amount: 25.00 CR

11. The Repeating transactions for General journal screen should now reflect as follows:



A Repeating Batch differs from a normal batch as follows:

*Title bar - displays *** Repeating transactions ****

F6:Post - Disabled since you cannot post repeating transactions.

Lines - Background colour.

12. Click on the F5:Balance icon to balance the batch. osFinancials5/TurboCASH5 will generate a balancing entry to the selected Contra account (e.g. "*Depreciation*").

If the description is displayed as "BALANCING ENTRY General Jnl", and you have entered transactions with Tax, the Tax reports may not include these transactions correctly.

You need to deselect (remove the tick) of the Consolidate balancing field on the Standard tab of the F10:Setup (Options for this batch screen) and rebalance the batch.

13. Click on the F8:List icon to print a list of the transactions in the batch.



It is recommended that the source documents (e.g. working papers, calculations, etc.) be attached to this List of the transactions and that it be retained for record and audit purposes.

14. Press the Esc key to exit this repeating batch.

Created with the Standard Edition of HelpNDoc: Easily Add Encryption and Password Protection to Your PDFs

Repeating transactions import

Once transactions is added and or edited, in the Repeating transactions batch entry screen, you may then import the transactions into the normal Batch entry screen using the Repeating transactions option on the F9:Process options.

To post (update) the Repeating transactions batch:

1. On the Default ribbon, select Batch entry (F2).
2. Select the General Jnl and click on the Open button. The *General journal* screen will be displayed. Note that there will be no alias displayed on the screen title bar as this is a normal batch.
3. Click on the F9:Process icon. The *Process the batch* screen will be displayed.
4. Select the "*Repeating transactions*" option and click on the OK button. osFinancials5/TurboCASH5 will display the following screen on the *Batch entry* screen:



If you enter a reference number into the New Reference number field, the reference numbers will not be incremented.

The reference number entered, will apply to all repeating transactions which will be imported or generated into the batch (journal).

5. Enter or select the following:

    a) Select "*This Year*" in the Year field.

    b) Select the period (month, i.e. "*March 2022*") in which to repeat or copy the transactions.

    c) Enter *"2203"* in the "*Add this to descriptions*" field. You may enter your own, if necessary. This will add it after the description entered in the Repeating Batch which was imported.

    d) Enter *"DE2203"* in the "*New Reference*" field. This will replace the Reference entered in the Repeating batch which was imported.

The Reference "DE2203", as in this example, indicates that it is Depreciation for March 2023.

6. Click on the OK button. All the transactions you have entered in the repeating Batch entry for the General journal will be imported (copied) into the normal batch.

7. Enter the Alias (batch name) in the *Change alias* field on the Topbar of the Batch entry screen. In this example we enter *"Depreciate2203"* to indicate that the Depreciation transactions for March 2023 was entered in this General journal batch.

The alias option allows you to identify a batch by a unique name. You will be able to select the batch by alias or batch name if you need to reverse the posted batch or import a posted batch.

8. The imported repeating batch, as in this example, should reflect as follows:



9. The first line should be imported will be blank, consisting only of the reference number and date. Click on the ^D: Delete icon to delete this row.

> *Always check that the amounts are the same before posting this batch. For instance if you have sold your Mercedes-Benz, you may need to delete the entry for the next months. If you have purchased new assets you may change the amount or add a new entry.*
>
> *You may do it on this screen, but it is recommended that you edit your repeating transactions in Edit → Repeating transactions (Default ribbon) to avoid having to change the same issues every time you wish to update a repeating batch.*

10. If the batch is not balanced or in balance, you need to click on the F5:Balance icon to balance the batch.

11. Click on the F8:List icon to print a list of the transactions in the batch.



It is recommended that the source documents (e.g. working papers, calculations, etc.) be attached to this List of the transactions and that it be retained for record and audit purposes.

12. Once you are satisfied that all the entries are correct, click on the F6:Post icon to post (update) the batch to the ledger. osFinancials5/TurboCASH5 will update and post the transactions to the ledger accounts.

Created with the Standard Edition of HelpNDoc: Easily Add Encryption and Password Protection to Your PDFs

Batch transactions / Journal transactions

---

osFinancials5/TurboCASH5 installation provides tutorial Sets of Books in both English and Afrikaans. These tutorial books allow users to explore different settings, transactions, and reports within the software. Here are the available tutorial sets:

Accounting Made Easy	***Accounting Made Easy - Bank Import***	***Rekeningkunde Met Gemak (Afrikaans)***
English tutorials (using separate receipt and payments journals for banking / cash transactions)	*English tutorials (using the BankImport plugin for banking / cash transactions)*	*Afrikaanse handleidings (gebruik aparte ontvangste- en betalingsjoernale vir bank- / kontanttransaksies)*
		
The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\ENGLISH\" folder:	*The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\BANK-IMPORT\" folder:*	*Die volgende Stel Boeke gebaseer op die Afrikaanse handleidings, is in die "…\bin\Tutorials\AFRIKAANS\"-lêergids geïnstalleer:*

- *HANDYMAN (No transactions)*
- *HANDYMAN-A (Unposted transactions)*
- *HANDYMAN-B (Posted transactions)*
- *HANDY-BANK (No transactions).*
- *HANDY-BANK-A (Unposted transactions)*
- *HANDY-BANK-B (Posted transactions).*
- *HANDY-BANK-UNPOSTED-BANK-STATEMENT – Posted transactions, excluding bank / cash transactions. Bank statement needs to be imported from the "…\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS" folder.*
- *NUTSMAN (Geen transaksies).*
- *NUTSMAN-A (Ongeposteerde transaksies)*
- *NUTSMAN-B (Geposteerde transaksies).*

To open the tutorial Sets of Books, installed in the "*bin / Tutorials*" directory, you need to click on the Open icon on the Start ribbon. On the "*Set of Books*" screen, click on the Browse icon and select the desired tutorial Set of Books that you wish to follow.

Additionally, there are other tutorial folders available with relevant files for import into batches. The following folders contains files which may be imported into batches:

- *EXPORTED-BATCH-Delimited-File – Exported batch transactions using the "Write delimited file" option and may be imported into a batch using the "Delimited file import" option (F9:Process icon) on batches.*
- *EXPORTED-BATCH-Spreadsheets – Exported batch transactions in the *.xlsx (Excel 2007-365) file format. These transaction files may be opened in the Spreadsheet import icon on batches, and imported into a selected batch.*

These tutorials are designed to guide users, regardless of their accounting experience, through the basics of accounting and demonstrate how to effectively use osFinancials5/TurboCASH5 for managing business finances. The tutorials cover various aspects, including software features, chart of accounts setup, transaction creation, processing sales and purchase documents, and report generation. They also serve as a reference guide to osFinancials5/TurboCASH5.

By the end of these tutorials, users will have gained a solid understanding of the accounting process and will be able to confidently utilise osFinancials5/TurboCASH5 for managing their business finances.

OTHER TUTORIALS

Additionally, there are other tutorials for exploring the activation, processing, and reporting of Cost centres and Projects within osFinancials5/TurboCASH5.

COST-CENTRES

Tutorials / examples to explore the activation, processing and reporting of Cost centres in osFinancials5/TurboCASH5. See - Cost centres in this Help file.

The following Set of Books based on this tutorial, is installed in the "*...\bin\Tutorials\COST-CENTRES*" folder:

- COST-CENTRES-A (transactions and documents not posted to the ledger)
- COST-CENTRES-B (transactions and documents posted to the ledger).

PROJECTS

Tutorials / examples to explore the activation, processing and reporting of Projects in osFinancials5/TurboCASH5. See - Projects in this Help file.

The following Set of Books based on this tutorial, is installed in the "*...\bin\Tutorials\PROJECTS*" folder:

- PROJECTS-A (transactions and documents not posted to the ledger)
- PROJECTS-B (transactions and documents posted to the ledger).

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Take-on Opening Balances

Commencing the use of osFinancials5/TurboCASH5 need not coincide with the commencement of business operations. osFinancials5/TurboCASH5 may be implemented at a later time. Nonetheless, it is likely that the closing balances of your existing ledger accounts, obtained from your Set of Books either from a manual or computer system, must be recorded in osFinancials5/TurboCASH5. These balances are referred to as opening balances. To ensure the efficiency of the system, it is advisable to enter these balances at the time of system setup.

The latest trial balance from your previous accounting system, will provide the necessary information for

opening balances. In cases where the business has been running for an extended period, it is recommended that the trial balance figures from the preceding year be entered into the osFinancials5/TurboCASH5. Suppose your financial year commences on 2024/03/01, in that case, it is ideal to record your opening balances using the date 2024/02/29, providing an opportunity for a comparison between the prior year and the current year.

Should the trial balance figures of the previous financial year be entered, osFinancials will perform a net profit/loss calculation and allocate the result to the Retained Income account. However, it will not transfer the expense figures to the current year.

The completeness of your set of accounts depends on the entry of opening balances. Should you fail to enter these balances, your accounts will remain incomplete. However, if you are commencing a new business venture, it would be unnecessary to enter any opening balances since none are in existence.

If you do not enter any opening balances, your set of accounts will not be complete. However, if it is a brand new business you are starting, it will obviously not be necessary to enter any opening balances, as you will not have any.

The opening balances are captured in the General journal.

Opening Balance - Configuration of osFinancials

Transitioning to a new accounting system like osFinancials5/TurboCASH5 requires careful preparation and data migration. Here are the essential steps to take when setting up your new system and adding opening balances:

1. Prepare Your Data:
    a) On your old accounting system, prepare and finalise all outstanding transactions, adjustments to prepare financial statements like, the trial balance, income statement and balance sheet. This step is necessary to eliminate any duplicates or errors.
    b) Back up your data from the old accounting system to ensure you have a safe copy of your financial records.
    c) Gather the necessary data to configure osFinancials5/TurboCASH5 and process opening balances.
2. Configure Chart of Accounts:
    a) Set up your Chart of Accounts in osFinancials5/TurboCASH5 to match your business's financial structure. You may need to refer to your previous system's Chart of Accounts and trial balance

for guidance.

b) Create or add the necessary accounting groups to classify your accounts and link the account groups to the financial categories such as income, expense, asset, liability, and equity. This will ensure that your accounts are properly structured, categorized and labelled.

3. Add Debtor Accounts:

a) Setup a default debtor account to capture the total opening balance of the debtors ledger of your customers and clients. This account will be necessary to take on the total opening balance of the debtors control account of the debtors' ledger in the general ledger. Once this is done, you need to Take on the individual balances of your once your individual debtor (customer / client) accounts is added in osFinancials5/TurboCASH5.

b) Set up your debtor accounts for your customers and clients into osFinancials5/TurboCASH5. This includes accurate details such as customer names, contact information such as contactpersons, postal and delivery address information, payment terms, and credit limits, interest rates, discounts, etc.

c) Use your old system's debtor records as a reference to maintain consistency.

4. Add Creditor Accounts:

a) Set up creditor accounts for your suppliers and vendors.

b) Enter supplier information, contact details, payment terms, and any outstanding amounts.

c) Verify the accuracy of this information against your previous system's creditor records.

5. Import Stock/Inventory Data:

a) Transfer your stock or inventory data into osFinancials5/TurboCASH5. This includes product names, descriptions, quantities, costs, and selling prices.

b) Ensure that your stock data aligns with your existing inventory levels.

6. Take On Opening Balances:

a) Once your master files (Chart of Accounts, debtor accounts, creditor accounts, and stock) are correctly configured and populated, you can proceed to enter opening balances.

b) Record the opening balances for your debtor accounts, creditor accounts, and inventory.

c) These balances should reflect the outstanding amounts owed to you by customers, the amounts you owe to creditors, and the value of your existing inventory at the start of your osFinancials5/TurboCASH5 accounting.

7. Verification and Reconciliation:

a) Verify that the opening balances you've entered match the figures from your old accounting system.

b) Reconcile your accounts to ensure accuracy and to identify any discrepancies that need correction.

8. Test Transactions:

a) Conduct test transactions to make sure your new accounting system is functioning correctly.

b) Verify that your opening balances are correctly carried forward in your financial reports.

9. Training and Familiarization:

a) Ensure that your team is familiar with osFinancials5/TurboCASH5 and its features. Provide training as necessary to ensure efficient operation.

10. Documentation:

a) Maintain documentation of the entire setup process, including the configuration, data migration, and opening balances.

b) Keep records of any issues encountered and how they were resolved.

By following these steps, you can successfully set up osFinancials5/TurboCASH5, add your master files, and take on opening balances from your previous accounting system, ensuring a smooth transition to your new financial software.

Which records is required from your previous accounting system to take on opening balances in osFinancials5/TurboCASH5?

When transitioning to a new accounting system like osFinancials and taking on opening balances, you will need certain records and information from your previous accounting system. Here are the essential records and data you should have:

1. Trial Balance: Obtain a copy of the trial balance from your previous accounting system. This trial balance should include the closing balances of all your accounts at the end of the previous accounting period. It will serve as a starting point for entering opening balances in osFinancials5/TurboCASH5.

2. Chart of Accounts: Ensure you have a detailed list of your chart of accounts from the previous system. This list should include the account names, account numbers, and account types (e.g., assets, liabilities, equity, revenue, expenses).

3. Debtor (Accounts Receivable) Reports: These reports show the outstanding amounts that your customers owe you. It's important to have records of outstanding customer invoices, sales orders, and

customer statements as of the transition date. This information is necessary for accurately setting up your accounts receivable balances and creating accurate opening balances for your debtor accounts in osFinancials5/TurboCASH5.

4. Creditor (Accounts Payable) Reports: These reports show the outstanding balances you owe to your suppliers or creditors. You should obtain records of outstanding invoices, bills, and supplier statements as of the transition date. This information is necessary for accurately setting up your accounts payable balances and creating accurate opening balances for your creditor accounts in osFinancials5/TurboCASH5.
5. General Ledger Transactions: Depending on the complexity of your accounting, you might need access to detailed general ledger transactions for the accounts you're transferring. This is especially important if you have complex transactions, accruals, or prepayments that need to be accurately carried forward.
6. Debtor (Customer/Client) Information: Information about your debtors (customers/clients), including contact details, credit terms, and outstanding balances, can be helpful for setting up accounts receivable and accounts payable in osFinancials5/TurboCASH5.
7. Creditor (Supplier/Vendor) Information: Information about your creditors (suppliers/vendors), including contact details, credit terms, and outstanding balances, can be helpful for setting up accounts receivable and accounts payable in osFinancials5/TurboCASH5.
8. Customer Invoices and Statements: It can be helpful to have copies of customer invoices and statements, particularly if there are any discrepancies or disputes that need to be resolved during the transition.
9. Supplier Invoices and Statements: It can be helpful to have copies of supplier invoices and statements, particularly if there are any discrepancies or disputes that need to be resolved during the transition.
10. Aged Receivables Report: An aged receivables report shows how long each receivable has been outstanding. It can be useful for accurately ageing your outstanding debtor balances in osFinancials5/TurboCASH5, especially if you plan to use the ageing facility in osFinancials5/TurboCASH5.
11. Aged Payables Report: An aged payables report shows how long each payable has been outstanding. It can be useful for accurately ageing your outstanding creditor balances in osFinancials5/TurboCASH5, especially if you plan to use the ageing facility in the osFinancials5/TurboCASH5.
12. Tax Records: Ensure you have records of any outstanding sales tax or value-added tax (VAT) liabilities to accurately reflect your tax obligations in osFinancials5/TurboCASH5.
13. Asset and Liability Information: If you have assets or liabilities with specific details (e.g., depreciation

schedules for assets, loan details for liabilities), gather this information to accurately carry it forward in your new accounting system.

14. Bank Statements: If your bank account balances are part of your opening balances, obtain copies of your bank statements to reconcile and verify the balances.
15. Opening Inventory Balances: If you manage inventory, you'll need records of your opening inventory balances to accurately reflect your inventory assets.
16. Employee Records: If you handle payroll in your accounting system, ensure you have employee records, payroll tax information, and year-to-date payroll figures to transfer into osFinancials5/TurboCASH5.

Having these records and data readily available will make the process of taking on opening balances inosFinancials5/TurboCASH5 smoother and more accurate. It's essential to maintain accuracy during the transition to ensure the continuity of your financial records and reporting.

Converting a Set of Books from other accounting systems

When converting a Set of Books from other accounting systems, to osFinancials5/TurboCASH5, all balances and transactions are automatically included. Nevertheless, if the decision is made to use osFinancials5/TurboCASH5 while possessing balances in a manual system or a different computerised accounting system, the balances from the prior accounting system must be entered.

Conversion Options on the osFinancials Shop

If you need to convert your data from other accounting packages, please visit the osFinancials Webshop for options; such as Basic conversion, Extensive conversion, Conversion to Microsoft SQL Server database.

Example: Take on Opening Balances

A simplified example of the transactions to take-on opening balances for Debtors (customers/clients) can be followed in the HANDYMAN, HANDYMAN-A and HANDYMAN-B tutorials which may be downloaded fro free using the option "*Let osFinancials help you to create a Set of Books?*" option.

To illustrate the entry of opening balances, this documentation will utilize the following examples:

General ledger : The Trial balance:

Handyman Hardware Store
Closing Trial Balance as at 29 February 2024

Description	Account No.	Debit	Credit
Capital	505		11 500.00
Retained Income	510		4 200.00
Furniture & Fittings - @ Cost	600-010	1 007.00	
Furniture & Fittings - Accumulated Depreciation	600-020		300.00
Motor Vehicles - @ Cost	610-010	5 000.00	
Motor Vehicles - Accumulated Depreciation	610-020		500.00
Debtor's Control	700	1 800.00	
Creditor's Control	900		1 000.00
Stock Control	750	6 500.00	
Bank	810	3 193.00	
Petty Cash	820	100.00	
Output VAT	860-010		100.00
Total		17 600.00	17 600.00

Control accounts:

Individual balances needs to be taken on separately for the following Control accounts:

- *Debtor's control (G700).*
- *Creditor's control (G900).*
- *Stock control (G750)*

Control accounts in the General ledger must always be in balance with the total of the sub-ledgers.

Debtor's ledger : The Balances of the individual Debtor accounts:

Handyman Hardware Store
Debtor's Age analysis as at 29 February 2024

Debtor	Account no.	Outstanding amount	Outstanding as at		
			29/02/2024	31/01/2024	31/12/2023
Mr. Mike Davies	D1MD-AVI	800.00	500.00	200.00	100.00
Mr. Roger Smith	D1RO-GSM	1 000.00	600.00	200.00	200.00
Total		1 800.00	1 100.00	400.00	300.00

Debtor's ledger:

Individual balances may be taken on for the following:

- *Outstanding amount.*
- *Each period separately. Each period separately will allow you to use the Debtor's age analysis reports.*

Creditor's ledger : The Balances of the individual Creditor accounts:

Handyman Hardware Store
Creditor's Age Analysis as at 29 February 2024

Creditor	Account No.	Outstanding Amount	Outstanding as at		
			29/02/2024	31/01/2024	31/12/2023
A-One Suppliers	2AO-NES	600.00	300.00	200.00	100.00
BEST Suppliers	2BE-STS	400.00	200.00	100.00	100.00
Total		1 000.00	500.00	300.00	200.00

Creditor's ledger:

Individual balances may be taken on for the following:

- *Outstanding amount.*
- *Each period separately. Each period separately will allow you to use the Creditor's*

age analysis reports.

Stock Ledger: The Balances (Quantities and Cost prices) of the Individual Stock items:



Handyman Hardware Store
List of Stock Items as at 29 February 2024

Stock Item	Stock Code	Quantity on Hand	Unit Cost Price	Value of Stock on Hand
Compressor	3Comp	4	1 000.00	4 000.00
Drill Press	3Drill	5	500.00	2 500.00
Total				6 500.00

Stock Ledger / Inventory Ledger: Only the total value (cost price of inventory) is entered as the opening balance of your inventory items.

The number of units and value of the individual inventory items (cost of inventory) is entered when you record your opening inventory.

The total quantities and the total value of the inventory at cost must match the total amount of the Stock control account as the opening balance of your inventory.

The opening balances for your stock items must be entered for each individual stock item - you cannot simply enter the total from the trial balance. You need to specify the quantities on hand and the cost prices for each stock item.

osFinancials5/TurboCASH5 will calculate the value of each stock item by multiplying the quantities on hand by the cost price. After all the quantities and cost prices of your stock items are entered, the total value of all stock items should be equal to the control figure (stock control account), as per your financial statements.

Created with the Standard Edition of HelpNDoc: Maximize Your PDF Protection with These Simple Steps

Take-on General Ledger Opening Balances

Entering opening balances for general ledger accounts

To enter opening balances for general ledger accounts, you will need to have the account balances as of

the start of your accounting period. This could be the beginning of a new financial year or the start of a new accounting cycle.

It is important to ensure that your opening balances are entered accurately, as they will form the foundation for all future transactions in your accounts. You should also ensure that you have supporting documentation for your opening balances, such as, bank statements and previous trial balance and other financial statements.

Once you have entered your opening balances, you can begin recording transactions for the current period. You should also regularly review and reconcile your accounts to ensure that they are accurate and up-to-date.

Guidelines to process opening balances for general ledger accounts

When setting up a new accounting system, it is important to set up the chart of accounts correctly to ensure that your financial information is accurate and organized. Here are some steps you can follow to set up your chart of accounts:

1. Review your existing chart of accounts: If your new Set of Books already includes a chart of accounts, review it to ensure that it meets the needs of your business. Compare it to your previous accounting system's chart of accounts to identify any differences.
2. Make necessary changes: If your new Set of Books chart of accounts is missing any accounts that you need, or includes accounts that you don't require, make the necessary changes. This may involve adding new accounts, deleting accounts, or modifying account names or numbers.
3. Determine account structure: Determine the structure of your accounts, including the number of digits in your account numbers, the grouping of accounts, the linking of account groups to financial categories, and the use of sub-accounts. This will help ensure that your accounts are organized in a way that makes sense for your business.
4. Create a standard naming convention : Establish a standard naming convention for your accounts to ensure consistency and clarity. This may involve using abbreviations, codes, or other conventions to make it easier to identify accounts.
5. Enter your opening balances: Once you've set up your chart of accounts, enter the opening balances for each account to ensure that your financial statements are accurate from the beginning.
6. Review and adjust: After setting up your chart of accounts and entering opening balances, review your work to ensure that everything is correct. Make any necessary adjustments to ensure that your accounts are accurate and organized.

By following these steps, you can ensure that your chart of accounts is set up correctly and that your financial information is accurate and well-organized.

Steps to Process General Ledger Opening Balances

Once you have set up your chart of accounts and entered the opening balances correctly, you can begin recording transactions in your new accounting database. It is important to maintain accurate records of all transactions to ensure that your financial statements are accurate.

To maintain accurate records, you should:

1. Record transactions timely: Record all transactions as soon as possible to avoid any delay and ensure that the records are up-to-date.
2. Enter all transactions correctly: Ensure that you enter all transactions accurately, with the correct account and amount.
3. Categorize transactions correctly: Categorize transactions correctly based on the chart of accounts you have set up, to ensure that your financial reports reflect the correct information.
4. Reconcile accounts regularly: Regularly reconcile your accounts to ensure that your records match your bank and other statements. This will help you identify and correct any errors or discrepancies.
5. Generate financial reports: Regularly generate financial reports, such as balance sheets and income statements, to help you analyse the financial health of your business.

By following these practices, you can maintain accurate records in your new accounting database, which will help you make informed business decisions and ensure that your financial statements are accurate.

Example: Source document



Handyman Hardware Store
Closing Trial Balance as at 29 February 2024

Description	Account No.	Debit	Credit
Capital	505		11 500.00
Retained Income	510		4 200.00
Furniture & Fittings - @ Cost	600-010	1 007.00	
Furniture & Fittings - Accumulated Depreciation	600-020		300.00
Motor Vehicles - @ Cost	610-010	5 000.00	
Motor Vehicles - Accumulated Depreciation	610-020		500.00
Debtor's Control	700	1 800.00	
Creditor's Control	900		1 000.00
Stock Control	750	6 500.00	
Bank	810	3 193.00	
Petty Cash	820	100.00	
Output VAT	860-010		100.00
Total		17 600.00	17 600.00

Process opening Balances in General journal

These transactions can be replicated in HANDYMAN, HANDYMAN-A en HANDYMAN-B Tutorials Sets of Books.

Since you cannot enter transactions to the Debtors control account and Creditors control account you need to:

- Add an "*Opening balances - Debtors*" account in the Debtors ledger in Debtors (Default ribbon).
- Add an "*Opening balances - Creditors*" account in the Creditors ledger in Creditors (Default ribbon).

To enter opening balances from your trial balance:

1. On the Default ribbon, select Batch entry (F2).

> *If no contra account, or a different contra account than the contra account you wish to use, is displayed on the Batch type selection screen, you need to set up the options for the batch. If you have not yet set up the General journal, or if your requirements should change,click on the F10:Setup icon.*

2. Select the General Jnl and click on the Open button.
3. Enter the Alias (batch name) in the '*Change alias'* field on the "*Batch entry*" screen.



Batch Settings

Before you can process transactions for opening balances, you first need to setup or configure the batch (journal). The setup "*Options for this batch*", consists of two tabs, i.e. Standard tab and Advanced tab.

To set the Options for this batch:

1. Click on the F10:Setup icon to set your batch up. On the Standard tab, the options is as follows:



> *The first time you enter transactions in a General journal, you should set it up according to your requirements. This should be done for each journal, but only need to be done once, unless your requirements change.*

2. The recommended settings (Standard tab) for entering opening balances in the General journal, is as follows:

    a) Contra account - The relevant contra account for the batch (i.e. the account to which

osFinancials5/TurboCASH5 will create a balancing entry). Select the suspense account, i.e. "*999 - Suspense Account*".

b) No Tax - Select this option, as no VAT/GST/Sales Tax (Output VAT/GST/Sales Tax and Input VAT/GST/Sales Tax) is applicable to the opening balance transactions.

c) Consolidate balancing - If you tick this field, osFinancials5/TurboCASH5 will consolidate all balancing entries into 1 entry, if you have used an account more than once. As for the take-on of opening balances, it is NOT necessary to tick this option, since you will be entering both debits and credits from your Trial balance and will not be asking osFinancials5/TurboCASH5 to balance the batch.

d) Repeat details - If you tick this field, the detail entered in the "*Description*" column will be repeated (duplicated) on each subsequent line. Tick this option to repeat the details for the next transactions.

e) Amount entry - Set to "*Allow both*", since you will enter amounts in both the debit and credit column.

The rest of the tick-boxes may be left blank.

f) Post in period 0 - Need to tick this field for opening balances, if you need to post retained income transactions to the previous year.

If the "Post in period 0" field is not selected (ticked), you will not be allowed to post the transactions to the Retained earnings / income account.

An error message (similar to this error message, will be produced:

"This batch does not validate!
Line JNL1 Opening balance - Take-on retained income must be adjusted in opening balance batch! See F10 in batch for setup."

3. Click on the Advanced tab. On the Advanced tab, the options is as follows:



4. Leave all fields blank, and make sure that the default option, "*Account lookup type*" and "*Contra account lookup type*" both, is set to "*All*" for opening balances.

> *You need to enter the total opening balance for all debtor accounts in the Debtors control account on the source Trial balance to the "Opening balances - Debtors" account. There after you need to clear this Opening balances - Debtors" account and debit the individual debtor accounts with their own opening balances.*
>
> *Similarly, you need to enter the total opening balance for all creditor accounts in the Creditors control account on the source Trial balance to the to the "Opening balances - Creditors" account. There after you need to clear this Opening balances - Creditors" account and credit the individual creditor accounts with their own opening balances.*

5. Click on the OK button.

Capturing opening balances in the General ledger

Capture the transactions, from your source document (Trial balance) from your previous accounting system.

Handyman Hardware Store
Closing Trial Balance as at 29 February 2024

Description	Account No.	Debit	Credit
Capital	505		11 500.00
Retained Income	510		4 200.00
Furniture & Fittings - @ Cost	600-010	1 007.00	
Furniture & Fittings - Accumulated Depreciation	600-020		300.00
Motor Vehicles - @ Cost	610-010	5 000.00	
Motor Vehicles - Accumulated Depreciation	610-020		500.00
Debtor's Control	700	1 800.00	
Creditor's Control	900		1 000.00
Stock Control	750	6 500.00	
Bank	810	3 193.00	
Petty Cash	820	100.00	
Output VAT	860-010		100.00
Total		17 600.00	17 600.00

1. Capture the first transaction as follows:

    a) Reference: JNL1

    b) Date: 2024/02/29

    c) Description: Opening Balance Take-on

    d) Account: 505 (for Capital)

    e) Amount: 11500.00 CR

> *Use the same reference number, date and details for all the entries.*

> *Tax*
>
> *Since No Tax (VAT/GST/Sales Tax) is applicable, to the opening balance transactions in this tutorial, we have selected to hide the Tax column in the Setup Options.*

2. Repeat as above for capturing the rest of the Trial balance. After capturing the Trial balance, the transactions should reflect as follows:



When entering the opening balance for the Debtor's control account (Account number G700-000), will not allow you to select the Debtor's control account.

The same applies to the Creditor's control account (Account number G900-000).

The reason for this is that you cannot post any transactions to the Debtor's control account in the General ledger. You need to select the individual Debtor accounts in the Debtor's ledger, to take on each individual Debtor's opening balance. When posting the transactions for the opening balances in the General journal, the Debtor's control account in the General ledger will automatically be updated with the total of all the individual transactions posted to the Debtor's ledger.

It is not necessary to "balance" your batch, as your Trial balance should already be in balance.

You will note that there is an amount indicating the difference between the debit and credit entries at the end of the Debit Amount column.

This amount (and the Reference Total at the bottom of the screen) should reflect a zero after entering all your transactions.

Checking your transactions before posting the transactions

Once your transactions is entered in the General ledger journal, you need to make absolutely sure that you have captured the transactions correctly. This is crucial to post the transactions on the correct date, correct references, descriptions debit and credit amounts to the correct accounts.

To print a list of transactions in the unposted batch:

1. Click on the F8:List icon to print a list of the transactions in the batch (journal). The batch list is

displayed as follows:



F:\TCASH5\plug_ins\reports\GENERAL\documents\batch.rep

List batch - Unposted batch

Batch name General jnl.
Alias (batch name) OpenBalances

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/02/29	JNL1	Opening balance - Take-on Empty,	G505-000 G999-000	T		0.00	11,500.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	G510-000 G999-000	T		0.00	4,200.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	G600-010 G999-000	T		1,007.00	0.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	G600-020 G999-000	T		0.00	300.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	G610-010 G999-000	T		5,000.00	0.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	G610-020 G999-000	T		0.00	500.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	D1DO-PEN G999-000	T		1,800.00	0.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	C2CO-PEN G999-000	T		0.00	1,000.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	G750-000 G999-000	T		6,500.00	0.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	B810-000 G999-000	T		3,193.00	0.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	B820-000 G999-000	T		100.00	0.00
2024/02/29	JNL1	Opening balance - Take-on Empty,	T860-010 G999-000	T		0.00	100.00
					Total	17,600.00	17,600.00

It is recommended that the source document (e.g. trial balance or balance sheet and income statement, etc.) be attached to this List of the transactions (take-on of opening balances) and that it be retained for record and audit purposes.

You may also click on the *icon (Save the report as a metafile report), and save it as a PDF - compressed file for archiving purposes.*

2. If there are any errors, you may fix this before you update (post) the transactions to the ledger.

Print a Trial balance for unposted batches

You may print a Trial balance of unposted batches journals. To do this, press the F2-key and right-click on the Batch e balance" from the context menu. A confirmation screen will be displayed:

"Unposted only?"

Click Yes and the Trial balance for unposted batches (journals) will be launched:



NOTE: Initially, the Print button will not be displayed. To display the Print button, go to the "Report type" and re-sel

You may print the Trial balance for unposted batches.

An example of the Trial balance for the opening balances (not updated (posted) to the ledger should display as follo


detail

Trial balance Period + Opening balances 2023/03/01 / 2024/02/29

	Debit	Totals Credit	Debi
REPORTING GROUP ROOT		800.00	
505000 Capital			
510000 Retained income			
600000 Furniture & fittings - Net value	707.00		
600010 Furniture & fittings @ cost			1,007.0
600020 Furniture & fittings - Accumulated depreciation			
610000 Motor vehicles - Net value	4,500.00		
610010 Motor vehicles @ cost			5,000.0
610020 Motor vehicles - Accumulated depreciation			
700000 Debtors control			
1DOPEN Opening Balances - Debtor			1,800.0
750000 Stock control			6,500.0
810000 ABC-Bank			3,193.0
820000 Petty cash			100.0
860000 VAT - Control - 15%		100.00	
860010 Output VAT - 15%			
900000 Creditors control			
Creditor group 1A		1,000.00	
2COPEN Opening balances - Creditor			
		Totals	17,600.0
		Net loss	

Update (post) transactions to the ledger

Once you have entered your transactions an you are absolutely sure that it is correct, you may proceed with the final step in processing jour opening balances in the journal (batch).

To Update (post) transactions to the ledger:

1. Click on the F6:Post icon, to post (update) the batch to the ledger. A confirmation message will be displayed.

   "Do you want to continue posting? Batch contains transactions posting to last year!"

2. Click on the Yes button, or press the Enter key to continue. A confirmation message will be displayed.

"Do you wish to post on the retained earnings account?"

If you click on the No button, the transactions will not be posted.

3. osFinancials5/TurboCASH5 will now post all the transactions to the general ledger.

Opening Balances - Transactions

Once the transactions is updated (posted) to the ledger, you may print a Trial balance of your opening balances.



Click on the Print button to print your opening balances.



	Totals Debit	Credit	Debit	Credit
REPORTING GROUP ROOT				
505000 Capital				11,500.00
510000 Retained income				4,200.00
600000 Furniture & fittings - Net value	**707.00**			
600010 Furniture & fittings @ cost			1,007.00	
600020 Furniture & fittings - Accumulated depreciation				300.00
610000 Motor vehicles - Net value	**4,500.00**			
610010 Motor vehicles @ cost			5,000.00	
610020 Motor vehicles - Accumulated depreciation				500.00
700000 Debtors control	**1,800.00**			
1MDAVI Mr. Mike Davies			800.00	
1ROGSM Mr. Roger Smith			1,000.00	
750000 Stock control			6,500.00	
810000 ABC-Bank			3,193.00	
820000 Petty cash			100.00	
860000 VAT - Control - 15%		**100.00**		
860010 Output VAT - 15%				100.00
900000 Creditors control		**1,000.00**		
Creditor group 1B		**1,000.00**		
2AONES A-ONE Suppliers				600.00
2BESTS BEST Suppliers				400.00
	Totals		**17,600.00**	**17,600.00**
	Net loss			



Handyman Hardware Store
Closing Trial Balance as at 29 February 2024

Description	Account No.	Debit	Credit
Capital	505		11 500.00
Retained Income	510		4 200.00
Furniture & Fittings - @ Cost	600-010	1 007.00	
Furniture & Fittings - Accumulated Depreciation	600-020		300.00
Motor Vehicles - @ Cost	610-010	5 000.00	
Motor Vehicles - Accumulated Depreciation	610-020		500.00
Debtor's Control	700	1 800.00	
Creditor's Control	900		1 000.00
Stock Control	750	6 500.00	
Bank	810	3 193.00	
Petty Cash	820	100.00	
Output VAT	860-010		100.00
Total		17 600.00	17 600.00

Ledger analyser - View transactions

In the Ledger analyser you may export your transactions and open it in a spreadsheet. In addition to this, you have two options to view your transactions.

- T-Account viewer - View and filter and export your transactions.

- Pivot - View and analyse your transactions in pivot tables.

T-Account viewer

Once you have printed the Trial balance, you may print and view and analyse your transactions in the T-Account account viewer.



Handyman Hardware Store
Closing Trial Balance as at 29 February 2024

Description	Account No.	Debit	Credit
Capital	505		11 500.00
Retained Income	510		4 200.00
Furniture & Fittings - @ Cost	600-010	1 007.00	
Furniture & Fittings - Accumulated Depreciation	600-020		300.00
Motor Vehicles - @ Cost	610-010	5 000.00	
Motor Vehicles - Accumulated Depreciation	610-020		500.00
Debtor's Control	700	1 800.00	
Creditor's Control	900		1 000.00
Stock Control	750	6 500.00	
Bank	810	3 193.00	
Petty Cash	820	100.00	
Output VAT	860-010		100.00
Total		17 600.00	17 600.00

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of a Help Authoring Tool

Take-on Debtor Opening Balances

Which records is required from your previous accounting system to take on opening balances for debtors (customers/clients) in osFinancials5/TurboCASH5?

When transitioning to a new accounting system like osFinancials5/TurboCASH5 and taking on opening balances, you will need certain records and information from your previous accounting system. Here are the essential records and data you should have for debtors (customers/clients):

1. Trial Balance: Obtain a copy of the trial balance from your previous accounting system. This trial balance should include the closing balances of all your accounts at the end of the previous accounting period. It will serve as a starting point for entering opening balances in osFinancials5/TurboCASH5. The total balances of Debtor's control account (Accounts receivable account) should be entered.
2. Debtor (Accounts Receivable) Reports: These reports show the outstanding balances owed to you by your suppliers or debtors. You should obtain records of outstanding invoices, bills, and debtor statements as of the transition date. This information is necessary for accurately setting up your accounts receivable balances and creating accurate opening balances for your debtor accounts in osFinancials5/TurboCASH5.
3. Debtor (customer/client) Information: Information about your debtors (customers/clients), including contact details, credit terms, and outstanding balances, can be helpful for setting up accounts receivable in osFinancials5/TurboCASH5.
4. Customer Invoices and Statements: It can be helpful to have copies of supplier invoices and statements, particularly if there are any discrepancies or disputes that need to be resolved during the transition.
5. Aged Receivables Report: An aged receivables report shows how long each payable has been outstanding. It can be useful for accurately ageing your outstanding creditor balances in osFinancials5/TurboCASH5, especially if you plan to use the ageing facility in osFinancials5/TurboCASH5.

Having these records and data readily available will make the process of taking on opening balances in osFinancials5/TurboCASH5 smoother and more accurate. It's essential to maintain accuracy during the transition to ensure the continuity of your financial records and reporting.

Steps to take-on opening balances for debtors

Taking on opening balances for debtor accounts is an essential step in the accounting process, especially when transitioning to a new accounting system, like osFinancials5/TurboCASH5. Here's a step-by-step

guide on how to do this using osFinancials5/TurboCASH5:

1. Add Debtor (Customer/Client) accounts: Create or add each individual debtor (customer/client) account. Each individual debtor (customer/client) account should contain specific information about your debtors (customers/clients), including postal and delivery addresses, contact details, credit terms (including credit limits) tax and registration numbers, and more. You could use the Filter and search options to verify the details and or using Debtor listing reports to verify the correct details.

2. Set Up an "*Opening Balances - Debtors*" Account: In osFinancials, create a new account called "*Opening Balances - Debtors*." This account will be used to record the total opening balances for all your debtor accounts. This Opening balance should match the total amount in the Debtors control account (Accounts payable account) and would be processed when Taking on the Trial Balance of the General ledger accounts.

3. Process Journal Entries: Create journal entries to allocate the outstanding amounts to individual debtor accounts. The journal entries should credit the "*Opening Balances - Debtors*" account and credit the respective debtor accounts.

   Example Journal Entry:

   - Debit: Customer A (Individual Debtor Account)
   - Credit: Opening Balances - Debtors

   Repeat this process for each debtor account until all opening balances have been allocated.

   If you wish to utilize the ageing feature in osFinanacials, when entering the opening balances in individual debtor accounts, you need to capture the outstanding balances at the end of each accounting period as per ageing reports or lists from your previous accounting system. A breakdown of each individual to track and manage the ageing of outstanding receivables. This will help you monitor how long each receivable has been outstanding, which is essential for managing cash flow and debtor relationships.

4. Import or Enter Opening Balances: Import or manually enter the opening balances for your debtor accounts into the "*Opening Balances - Debtors*" account. These balances should represent the amounts you owe to your suppliers at the beginning of the accounting period.

5. Verify the Totals: Double-check that the total outstanding amount in the "*Opening Balances - Debtors*" account matches the total opening balances in your trial balance. It's essential to ensure accuracy at this stage.

6. Utilise the Ageing Facility: When entering the opening balances are correctly recorded in individual debtor accounts, you can utilise the ageing facility within osFinancials5/TurboCASH5 to track and manage the ageing of outstanding receivables. This will help you monitor how long each receivable

has been outstanding, which is essential for managing cash flow and debtor relationships.

7. Reconcile and Review: After processing the journal entries, reconcile the individual debtor accounts to make sure they match the opening balances from your trial balance. This step ensures that all amounts have been correctly transferred.

8. Regularly Update Debtor Accounts: Going forward, continue to update your debtor accounts with new transactions, sales, and payments received as they occur. Regularly reconcile these accounts to ensure accuracy.

Remember that accurate recording of debtor balances is crucial for financial reporting and maintaining good relationships with your customers. Always consult yourosFinancials's documentation and guidelines for the most accurate and up-to-date instructions on handling opening balances and debtor accounts.

By following these steps, you can accurately capture outstanding balances at the end of each accounting period for individual debtor accounts in osFinancials5/TurboCASH5 and utilise the ageing feature to track the ageing of receivables effectively. This approach ensures that your financial records reflect the true state of your accounts receivable and helps with financial reporting and cash flow management.

Example: Source document - Debtor Age Analysis

Handyman Hardware Store
Debtor's Age analysis as at 29 February 2024

Debtor	Account no.	Outstanding amount	Outstanding as at		
			29/02/2024	31/01/2024	31/12/2023
Mr. Mike Davies	D1MD-AVI	800.00	500.00	200.00	100.00
Mr. Roger Smith	D1RO-GSM	1 000.00	600.00	200.00	200.00
Total		1 800.00	1 100.00	400.00	300.00

Opening Balances - Debtors

These transactions can be replicated in HANDYMAN, HANDYMAN-A en HANDYMAN-B Tutorials Sets of Books.

The transactions for opening balances in the ledger should already include the total outstanding balances in an "*Opening balances - Debtors*" account. This total outstanding balances need to be allocated and processed for each individual debtor (customer/client) account.

To enter Opening Balances for your Debtor accounts:

1. On the Default ribbon, select Batch entry (F2).

If no contra account, or a different contra account than the contra account you wish to use, is displayed on the Batch type selection screen, you need to set up the options for the batch. If you have not yet set up the General journal, or if your requirements should change,click on the F10:Setup icon.

2. Select the General Jnl and click on the Open button.

3. Enter the Alias (batch name) in the *Change alias* field on the Batch entry screen. (In this example, "*D-OpenBalances*" is used for Debtor Opening Balances).



Batch settings

Before you can process transactions for opening balances, you first need to setup or configure the batch (journal). The setup "*Options for this batch*", consists of two tabs, i.e. Standard tab and Advanced tab.

To set the Options for this batch:

1. Click on the F10:Setup icon to set your batch up. The '*Options for this batch'* screen will be displayed. The settings are basically the same as for the Opening balances of the General ledger account. Change the options for this batch, as follows:

a) Standard tab – Select the Contra account for Opening Balances – Debtors (1DO-PEN) and Set Amount entry to Debit.



The tick in the "Post in period 0" field must not be selected (not ticked) for opening balances for debtors (customers / clients).

b) Advanced tab – Set the "*Account lookup type*" and "*Contra account lookup type*" both to Debtor.



5. Once setup, click on the OK button.

Process Opening balance transactions : Debtors

1. Find your source document.

2. Enter the following transactions:

Handyman Hardware Store
Debtor's Age analysis as at 29 February 2024

Debtor	Account no.	Outstanding amount	Outstanding as at 29/02/2024	31/01/2024	31/12/2023
Mr. Mike Davies	D1MD-AVI	800.00	500.00	200.00	100.00
Mr. Roger Smith	D1RO-GSM	1 000.00	600.00	200.00	200.00
Total		1 800.00	1 100.00	400.00	300.00

The Opening Balances – Debtor account should reflect the total of all Debtor accounts (in the Debtor's control account). You only need to list (select) the individual debtor accounts and enter their balances.

You may enter only the total outstanding balance (i.e. 1800.00 as per this example) as at 29 February 2024 for each debtor account (2 entries).

If you wish to optimise the ageing facility in , you may enter the balances for each debtor account as at the end of each period, e.g. 29 February 2024 – 1100.00, 31 January 2024 – 400.00 and 31 December 2023 – 300.00.



3. Click on the F5: Balance icon. osFinancials will generate balancing entries for each period. After entering the individual balances for each period, and balancing the batch, the transactions should be

displayed as follows:



You may click on the F9: Process icon and select the "Totals per period" option. This will list the totals of all the Debit entries and all the Credit entries for each period. The difference should be zero.



4. Click on the F8:List icon to print a list of the transactions in the batch.



5. Click on the F6:Post icon, to post (update) the batch to the ledger. A confirmation message will be displayed.

> "Do you want to continue posting? Batch contains transactions posting to last year!"

6. Click on the Yes button, or press the Enter key to continue.

> *If you click on the No button, the transactions will not be posted.*

7. osFinancials5/TurboCASH5 will post the entries for each period to the ledger.

T-Account view : Debtor - Opening balances

The Opening Balances - Debtor account should have a zero balance after balances were debited to the individual Debtor accounts.



The Batch for Opening Balances (e.g. BatchID 11) should have a zero balance (credit transactions in Opening Balances - Debtor account = debit transactions individual Debtor accounts).



Age analysis view : Debtor - Opening balances

The Debtor age analysis report for 30 March 2024 (Reports → Debtors → Age analysis - Balances detail) will display the totals for each period as follows:



Balances detail

Debtor age analysis - Balances detail

From account: D1ABGRE To: D1ROGSM

Period 1 : 2024/03/30
Period 2 : 2024/02/29
Period 3 : 2024/01/30

Sequence: Description
Show transactions: No
Show contact details: No
New page per account: No

Debtor group: Debtor group 1B

D1MDAVI Mr. Mike Davies — Open item: Yes

Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
800.00	500.00	200.00	100.00

D1ROGSM Mr. Roger Smith — Open item: No

Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
1,000.00	600.00	200.00	200.00

Total - Debtor group: Debtor group 1B

Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
1,800.00	1,100.00	400.00	300.00

Report total:

Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
1,800.00	1,100.00	400.00	300.00

Handyman Hardware Store
Debtor's Age analysis as at 29 February 2024

Debtor	Account no.	Outstanding amount	Outstanding as at 29/02/2024	31/01/2024	31/12/2023
Mr. Mike Davies	D1MD-AVI	800.00	500.00	200.00	100.00
Mr. Roger Smith	D1RO-GSM	1 000.00	600.00	200.00	200.00
Total		1 800.00	1 100.00	400.00	300.00

Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

Take-on Creditor Opening Balances

Which records is required from your previous accounting system to take on opening balances for creditors (suppliers/vendors) in osFinancials5/TurboCASH5?

When transitioning to a new accounting system like osFinancials5/TurboCASH5 and taking on opening balances, you will need certain records and information from your previous accounting system. Here are the essential records and data you should have for creditors (suppliers/vendors):

1. Trial Balance: Obtain a copy of the trial balance from your previous accounting system. This trial balance should include the closing balances of all your accounts at the end of the previous accounting period. It will serve as a starting point for entering opening balances in osFinancials5/TurboCASH5. The total balances of Creditor's control account (Accounts payable account) should be entered.
2. Creditor (Accounts Payable) Reports: These reports show the outstanding balances you owe to your suppliers or creditors. You should obtain records of outstanding invoices, bills, and supplier statements as of the transition date. This information is necessary for accurately setting up your accounts payable balances and creating accurate opening balances for your creditor accounts in osFinancials5/TurboCASH5.
3. Creditor (Supplier/Vendor) Information: Information about your creditors (suppliers/vendors), including contact details, credit terms, and outstanding balances, can be helpful for setting up accounts receivable and accounts payable in osFinancials5/TurboCASH5.
4. Supplier Invoices and Statements: It can be helpful to have copies of supplier invoices and statements, particularly if there are any discrepancies or disputes that need to be resolved during the transition.
5. Aged Payables Report: An aged payables report shows how long each payable has been outstanding. It can be useful for accurately ageing your outstanding creditor balances in osFinancials5/TurboCASH5, especially if you plan to use the ageing facility in the osFinancials5/TurboCASH5.

Having these records and data readily available will make the process of taking on opening balances in osFinancials5/TurboCASH5 smoother and more accurate. It's essential to maintain accuracy during the transition to ensure the continuity of your financial records and reporting.

Steps to take-on opening balances for creditors

Taking on opening balances for creditor accounts is an essential step in the accounting process, especially when transitioning to a new accounting system, like osFinancials. Here's a step-by-step guide on how to do this using osFinancials5/TurboCASH5:

1. Add Creditor (Supplier/Vendor) accounts: Create or add each individual creditor (supplier/vendor) account. Each individual creditor (supplier/vendor) account should contain specific information about your creditors (suppliers/vendors), including postal and delivery addresses, contact details, credit terms (including credit limits) tax and registration numbers, and more. You could use the Filter and search options to verify the details and or using Creditor listing reports to verify the correct details.
2. Set Up an "*Opening Balances - Creditors*" Account: In osFinancials5/TurboCASH5, create a new account called "*Opening Balances - Creditors*." This account will be used to record the total opening balances for all your creditor accounts. This Opening balance should match the total amount in the Creditors control account (Accounts payable account) and would be processed when Taking on the Trial Balance of the General ledger accounts.
3. Process Journal Entries: Create journal entries to allocate the outstanding amounts to individual creditor accounts. The journal entries should debit the "*Opening Balances - Creditors*" account and credit the respective creditor accounts.

   Example Journal Entry:

   - Debit: Opening Balances - Creditors
   - Credit: Supplier A (Individual Creditor Account)

   Repeat this process for each creditor account until all opening balances have been allocated.

   If you wish to utilise the ageing feature in osFinanacials, when entering the opening balances in individual creditor accounts, you need to capture the outstanding balances at the end of each accounting period as per aging reports or lists from your previous accounting system. a breakdown of each individual to track and manage the ageing of outstanding accounts payable. This will help you monitor how long each payable has been outstanding, which is essential for managing cash flow and supplier relationships.
4. Import or Enter Opening Balances: Import or manually enter the opening balances for your creditor accounts into the "*Opening Balances - Creditors*" account. These balances should represent the amounts you owe to your suppliers at the beginning of the accounting period.
5. Verify the Totals: Double-check that the total outstanding amount in the "*Opening Balances - Creditors*" account matches the total opening balances in your trial balance. It's essential to ensure accuracy at this stage.
6. Utilize the Ageing Facility: When entering the opening balances are correctly recorded in individual creditor accounts, you can utilize the ageing facility within your accounting software to track and manage the ageing of outstanding accounts payable. This will help you monitor how long each payable has been outstanding, which is essential for managing cash flow and supplier relationships.

7. Reconcile and Review: After processing the journal entries, reconcile the individual creditor accounts to make sure they match the opening balances from your trial balance. This step ensures that all amounts have been correctly transferred.
8. Regularly Update Creditor Accounts: Going forward, continue to update your creditor accounts with new transactions, purchases, and payments as they occur. Regularly reconcile these accounts to ensure accuracy.

Remember that accurate recording of creditor balances is crucial for financial reporting and maintaining good relationships with your suppliers. Always consult your specific accounting software's documentation and guidelines for the most accurate and up-to-date instructions on handling opening balances and creditor accounts.

By following these steps, you can accurately capture outstanding balances at the end of each accounting period for individual creditor accounts in osFinancials5/TurboCASH5 and utilise the ageing feature to track the ageing of accounts payable effectively. This approach ensures that your financial records reflect the true state of your accounts payable and helps with financial reporting and cash flow management.

Example: Source document - Creditor Age Analysis

Handyman Hardware Store
Creditor's Age Analysis as at 29 February 2024

Creditor	Account No.	Outstanding Amount	Outstanding as at		
			29/02/2024	31/01/2024	31/12/2023
A-One Suppliers	2AO-NES	600.00	300.00	200.00	100.00
BEST Suppliers	2BE-STS	400.00	200.00	100.00	100.00
Total		1 000.00	500.00	300.00	200.00

Opening Balances - Creditors

These transactions can be replicated in HANDYMAN, HANDYMAN-A en HANDYMAN-B Tutorials Sets of Books.

The transactions for opening balances in the ledger should already include the total outstanding balances in an "*Opening balances - Creditors*" account. This total outstanding balances need to be allocated and processed for each individual creditor (supplier/vendor) account.

To enter Opening Balances for your Creditor accounts:

1. On the Default ribbon, select Batch entry (F2).

If no contra account, or a different contra account than the contra account you wish to use, is displayed on the Batch type selection screen, you need to set up the options for the batch. If you have not yet set up the General journal, or if your requirements should change,click on the F10:Setup icon.

2. Select the General Jnl and click on the Open button.

3. Enter the Alias (batch name) in the *Change alias* field on the Batch entry screen. (In this example, "*C-OpenBalances*" is used for Creditor Opening Balances).



Batch settings

Before you can process transactions for opening balances, you first need to setup or configure the batch (journal). The setup "*Options for this batch*", consists of two tabs, i.e. Standard tab and Advanced tab.

1. Click on the F10:Setup icon to set your batch up. The "*Options for this batch*" screen will be displayed. The settings are basically the same as for the Opening Balances of the General ledger account. Change the Batch Settings as follows:

    a) Standard tab – Select the Contra account for "*Opening Balances – Creditors (2CO-PEN)*" and set

Amount entry to Credit.



b) Advanced tab – Set the "*Account lookup type*" and the "*Contra account lookup type*" both to Creditors.



2. Once setup, click on the OK button.

Process Opening balance transactions : Debtors

1. Find your source document.

2. Enter the following transactions:

Handyman Hardware Store
Creditor's Age Analysis as at 29 February 2024

Creditor	Account No.	Outstanding Amount	Outstanding as at 29/02/2024	31/01/2024	31/12/2023
A-One Suppliers	2AO-NES	600.00	300.00	200.00	100.00
BEST Suppliers	2BE-STS	400.00	200.00	100.00	100.00
Total		1 000.00	500.00	300.00	200.00

The Opening Balances – Creditor account should reflect the total of all Creditor accounts (in the Creditor's control account). You only need to list (select) the individual creditor accounts and enter their balances.

You may enter only the total outstanding balance (i.e. 1000.00 as per this example) as at 29 February 2024 for each creditor account (2 entries).

If you wish to optimise the ageing facility in osFinancials5/TurboCASH5, you may enter the balances for each creditor account as at the end of each period, e.g. 29 February 2024 – 500.00, 31 January 2024 – 300.00 and 31 December 2023 – 200.00.

3. Click on the F5: Balance icon. osFinancials will generate balancing entries for each period. After entering the individual balances for each period, and balancing the batch, the transactions should be displayed as follows:



4. Click on the F5:Balance icon to generate balancing transactions.



You may click on the F9: Process icon and select the Totals per Period option. This will list the totals of all the Debit entries and all the Credit entries for each period. The difference should be zero.



5. Click on the F8:List icon to print a list of the transactions in the batch.



6. Click on the F6:Post icon, to post (update) the batch to the ledger. A confirmation message will be displayed.

> "Do you want to continue posting? Batch contains transactions posting to last year!"

7. Click on the Yes button, or press the Enter key to continue.

> *If you click on the No button, the transactions will not be posted.*

8. osFinancials5/TurboCASH5 will post the entries for each period to the ledger.

T-Account view : Creditor - Opening balances

The Opening Balances – Creditor account should have a zero balance after balances were credited to the individual Creditor accounts.



The Batch for Opening Balances (e.g. BatchID 12) should have a zero balance (debit transactions in Opening Balances – Creditor account = credit transactions individual Creditor accounts).



Age analysis view : Creditor - Opening balances

The Creditor age analysis report for 30 March 2024 (Reports → Creditors → Age analysis - Balances detail) will display the totals for each period as follows:



Handyman Hardware Store
Creditor's Age Analysis as at 29 February 2024

Creditor	Account No.	Outstanding Amount	Outstanding as at 29/02/2024	31/01/2024	31/12/2023
A-One Suppliers	2AO-NES	600.00	300.00	200.00	100.00
BEST Suppliers	2BE-STS	400.00	200.00	100.00	100.00
Total		1 000.00	500.00	300.00	200.00

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Intuitive Interface

Print a Trial Balance for Opening Balances

Print a Trial Balance for Opening Balances

It is good practice to print a Trial balance in osFinancials5/TurboCASH5 at this point and check it with the

Trail balance of your previous accounting records from which you have entered your transactions.

> *It is recommended that this printed Trial balance be retained with your working papers and the previous trial balance for record and audit purposes.*

To print a trial balance from the Ledger analyser:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.



> *If you need to check the individual balances of the Debtor's accounts in the Debtor's control account (G700), you need to generate Debtor's age analysis report.*
>
> *If you need to check the individual balances of the Creditor's accounts in the Creditor's control account (G900), you need to generate Creditor's age analysis report.*
>
> *If you need to check the opening balances of the individual stock items in the Stock control account, you need to generate a Stock item listing report.*

2. Select the following:

a) Periods - On the default "*Per period*" tab, select "*Year*" and Period "*2024/03/01-2025/02/28*".

b) Report type -Select "*Trial balance*".

c) Reporting group - The following options are available:

   i) None - Select this option. This will list the accounts according to the Account code (account number).

   ii) Reporting group 1 - This will list the accounts according to the Account Group 1 (Groups - Account group1) (Setup ribbon).

   iii) Reporting group 2 - This will list the accounts according to the Account Group 2 (Groups (Account group2) (Setup ribbon).

d) Ignore zero balances - Tick will list only those accounts for which opening balances was entered.

e) Viewer Debtors / Creditors - If this option is not ticked, it will list only the balances of the Debtor's control account and the Creditor's control account.

Tick this option to show the break down of the Debtor accounts in the Debtor's control account and the break down of the C account.



f) Include opening balances – Tick this option to include the opening balances.

g) Opening balances only – Tick this option to include only the opening balances.

> *If any transactions is posted for the selected period, you need to tick this option to list only the accounts for which opening balances have been entered.*
>
> *You may leave this option blank, if no other transactions are entered and posted for the selected period.*

3. Click on the Report button. You may change the sequences, and click on the Print button to print the trial balance.

An example of the "*Trial balance*" (account code sequence), is as follows:



detail

Trial balance Period + Opening balances 2023/03/01 / 2024/02/29

	Totals Debit	Credit	Debit	Credit
REPORTING GROUP ROOT		**800.00**		
505000 Capital				11,500.00
510000 Retained income				4,200.00
600000 Furniture & fittings - Net value	**707.00**			
600010 Furniture & fittings @ cost			1,007.00	
600020 Furniture & fittings - Accumulated depreciation				300.00
610000 Motor vehicles - Net value	**4,500.00**			
610010 Motor vehicles @ cost			5,000.00	
610020 Motor vehicles - Accumulated depreciation				500.00
700000 Debtors control				
1DOPEN Opening Balances - Debtor			1,800.00	
750000 Stock control			6,500.00	
810000 ABC-Bank			3,193.00	
820000 Petty cash			100.00	
860000 VAT - Control - 15%		**100.00**		
860010 Output VAT - 15%				100.00
900000 Creditors control				
Creditor group 1A		**1,000.00**		
2COPEN Opening balances - Creditor				1,000.00
	Totals		**17,600.00**	**17,600.00**
	Net loss			

> *The totals should balance with the previous financial year. Check that the totals are in balance and that the correct balances correspond with the balances on your source trial balance.*

Handyman Hardware Store
Closing Trial Balance as at 29 February 2024

Description	Account No.	Debit	Credit
Capital	505		11 500.00
Retained Income	510		4 200.00
Furniture & Fittings - @ Cost	600-010	1 007.00	
Furniture & Fittings - Accumulated Depreciation	600-020		300.00
Motor Vehicles - @ Cost	610-010	5 000.00	
Motor Vehicles - Accumulated Depreciation	610-020		500.00
Debtor's Control	700	1 800.00	
Creditor's Control	900		1 000.00
Stock Control	750	6 500.00	
Bank	810	3 193.00	
Petty Cash	820	100.00	
Output VAT	860-010		100.00
Total		17 600.00	17 600.00

At this point you have completed your setup, charted your accounts, captured your debtors and creditors; and entered your opening balances into osfinancials5.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with a Help Authoring Tool

Sales transactions

What is sales transactions?

Sales transactions are any type of financial transaction that involves the sale of goods and/oror services by a business to a customer or client. These transactions can be conducted in a variety of ways, including in-person, online, or over the phone, and can involve different payment methods, such as cash, credit card, or invoice.

Sales transactions typically involve the exchange of goods or services for some form of payment or consideration. They may also involve additional terms or conditions, such as warranties, returns policies, or delivery timelines. Sales transactions are an important part of a business's revenue stream and are recorded in the sales journal or ledger as part of the accounting process. By tracking sales transactions, a business can monitor its sales performance, identify trends or patterns in customer behaviour, and make informed decisions about its marketing and sales strategies.

How to correct incorrect sales transactions?

If a sales transaction is incorrect, there are several steps that can be taken to correct it, depending on the

nature and extent of the error. Here are some common methods:

1. Refund or return: If a customer received the wrong product or if the product is defective, the business may need to issue a refund or accept a return.
2. Adjustment: If the price charged was incorrect, the business may need to adjust the transaction to reflect the correct amount. This can be done by issuing a credit or debit memo, which adjusts the amount owed or paid by the customer.
3. Cancellation: If a transaction was recorded in error, it may need to be cancelled or reversed. This can be done by issuing a credit note or cancellation invoice, which cancels the original transaction and corrects the accounting records.
4. Credit or debit note: If there was an overcharge or undercharge, a credit or debit note can be issued to correct the transaction amount.

It's important to note that correcting sales transactions should be done in a timely and accurate manner to maintain good relationships with customers and ensure the accuracy of financial records. It may also be helpful to review and improve internal processes to minimize errors and prevent similar mistakes from happening in the future.

How to prevent incorrect sales transactions?

There are several steps that businesses can take to prevent incorrect sales transactions, including:

1. Implementing proper controls: Businesses should establish proper controls for all sales activities, including proper authorisation procedures, separation of duties, and regular reconciliations.
2. Providing training: Employees should receive proper training on sales procedures, policies, and best practices to ensure they understand their roles and responsibilities.
3. Ensuring accuracy of sales orders: Sales orders should be accurately prepared, including correct quantities, prices, and delivery dates.
4. Verifying deliveries: When goods are shipped or services are provided, they should be thoroughly verified to ensure they match the details of the sales order.
5. Reviewing invoices: Invoices should be carefully reviewed to ensure they match the sales order and delivery details. Any discrepancies should be resolved promptly.
6. Regularly reviewing and updating processes: Businesses should regularly review and update their sales processes to ensure they are efficient, effective, and minimize the risk of errors.

By implementing these steps, businesses can prevent incorrect sales transactions and minimize the risk of financial discrepancies, inventory issues, and other related problems. Additionally, businesses should invest

in robust accounting and inventory management systems to ensure the accuracy and timeliness of sales transactions.

What is a sales order and what is a quote?

A sales order is a document that records the details of a transaction between a buyer and a seller. It includes information such as the names and addresses of both parties, the items being purchased, the quantity of each item, the price per item, and the total cost of the order. A sales order is typically generated by the seller after the buyer has agreed to purchase the items.

A quote, on the other hand, is a document that provides an estimated price for goods or services. It is often requested by a potential buyer before a purchase is made, as it allows them to compare prices and make an informed decision. A quote may include details such as the item or service being offered, the quantity, the price per item or service, and any applicable discounts or taxes. Unlike a sales order, a quote does not represent a binding agreement and does not require the buyer to make a purchase.

Sales Journal in osFinancials5/TurboCASH5

In addition to sales transactions, you can process sales documents (such as invoices, credit notes, and quotes) in the Journal entries (Journals on the Default ribbon). The following stock item types can be used to process these sales documents:

- Financial Entry: Allows you to select a general ledger account.
- Sales (No Inventory): Suitable for service-based inventory items (e.g., consulting fees, labour). Sales documents (Invoices and Credit Notes) can be linked to the Sales Journal.

In the Setup → Documents menu for Invoices and Credit notes on the Setup ribbon, you can link these documents to the Sales journal. When you process sales documents (Invoices and Credit Notes) in Documents (Default ribbon), source documents will be generated. Once these documents are updated (posted) to the general ledger, the transactions will appear similarly to those in the Sales journal under the Journals option on the Default ribbon.

In addition to sales documents, you can create, print, edit, and convert quotes to invoices by confirming quotes. For documentation purposes, transactions processed in the Sales journal under the Journals option on the Default ribbon are similar. The Journals option is illustrative for this documentation.

The Journals option on the Default ribbon is not designed to handle your trading inventory where cost of sales applies. To take full control of your inventory items (products), you must process the transactions in Documents (Default ribbon).

Processing Invoices and Credit Notes in the Documents option on the Default ribbon, rather than the Journals option, offers the following benefits:

- Quotes: The origin of sales transactions that can later be confirmed and converted to invoices.
- Layout Files: Several document layout files are available. osFinancials allows you to print and reprint quotes as needed. Universal document layout files can print and reprint one layout for all sales documents (quotes, invoices, and credit notes) and purchasing documents (orders, purchases, and supplier returns) in your preferred language. You can also create and edit your own document layout files using the Report designer.
- References: You can enter a reference.
- Messages: In the Setup → Documents for sales documents, you can enter up to three message lines that will be used as standard messages for each sales document (e.g., Quotes, Invoices, and Credit Notes). These standard messages will be included in the document when processed and can be edited as needed.
- Notes, Comments, and Remarks: In addition to the product's item code and description, you can enter additional information that will be printed on the sales documents.
- Discount: You can specify the discount on documents. The discount on documents will automatically be adjusted.

Sales Journal Options in osFinancials5/TurboCASH5

Hand-written invoices can be used when immediate invoicing is required or when electronic invoicing is not available. These invoices can be captured in the Sales journal using the Batch entry mode in osFinancials5/TurboCASH5.

The sales journal is not used to keep track of inventory or stock. The sales journal is a record of all credit sales made by a business, including information about the customer, date of sale, invoice number, and amount of the sale. It is used to keep track of the revenue generated by the business.

Processing Sales Documents in osFinancials:

1. Batch Entry Mode:
    - This mode is used to capture invoices from debtors (customers/clients).
    - It does not support stock items (inventory items/products).
2. Document Entry Mode:

- This mode allows you to create Quotes, Invoices and Credit notes linked to the Sales journal in Setup → Documents (Setup ribbon).
- It supports stock item types (inventory items/products).
- This method creates the necessary source documents (Quotes, Invoices and Credit notes), which can be printed and reprinted as needed.
- When documents (Invoices and Credit notes are posted to the ledger, the transactions are processed in the Sales journal.
- Features of Invoices and Credit Notes:
  - Quotes: You can use quotes and convert (confirm) the quotes to invoices .
  - Comments and Remarks: Add comments and remarks to items on a quote, invoice and credit note.
  - Standard Messages: Include standard messages on the quote, invoice and credit note and add additional messages and references.
  - Credit Limit Monitoring: You will be warned if a debtor exceeds their credit limit and can track their available balance.
- Support for Additional Stock Item Types:
  - This option allows you to create quotes, invoices and credit notes using various stock item types, such as:
    - Financial entry: Use the Accounts lookup to select general ledger accounts.
    - Sales (no stock): For items that do not involve stock.
    - Invoices and credit notes created in this way are automatically linked to the Sales journal in Setup → Documents (Setup ribbon).
    - When posted to the ledger, these invoices automatically process transactions in the Sales journal.
- Available Stock Item Types for Sales Documents:
  - Default
  - Sales
  - Option item
  - Option item (No stock)

- BOM (Bill of Materials)
- BOM (Bill of Materials) - Production
- Linked item

Recommended Approach:

The Document entry mode is recommended for creating invoices and credit notes whenever possible, as it provides a more efficient and accurate way of managing sales transactions in osFinancials5/TurboCASH5.

When to use a general journal or a credit note for sales transactions?

The decision to use a general journal or a credit note for sales transactions depends on the specific circumstances of the transaction.

A general journal entry is typically used to record adjusting entries, corrections, or other non-routine transactions. For example, if a sale was recorded in the wrong account or in the wrong period, a general journal entry may be used to correct the error. General journal entries are also used for transactions that do not involve a customer, such as depreciation or inventory adjustments.

On the other hand, a credit note is typically used for routine transactions related to returns, discounts, or allowances given to a customer. If a customer returns goods or receives a discount or allowance, a credit note is issued to adjust the amount owed by the customer. Credit notes are also used to correct errors related to sales transactions, such as incorrect pricing or quantity.

In general, if the transaction involves a customer and is related to returns, discounts, or allowances, a credit note is typically used. If the transaction is a non-routine transaction or does not involve a customer, a general journal entry may be more appropriate. However, it is important to follow the specific accounting policies and procedures of the business to ensure that transactions are properly recorded and documented.

What is the recommended process and journal to correct errors in the sales journal?

If an error is made in the sales journal, the recommended process to correct it depends on the nature and severity of the error.

If the error is a simple mistake, such as a transposition error in the amount of a sale, it can typically be corrected by making an adjusting entry in the sales journal. The adjustment should be made in the same month as the original entry, and the correction should be clearly noted in the sales journal.

If the error is more complex or if it affects multiple periods, it may be necessary to create a reversing entry in the general journal to cancel out the original entry and then create a new entry to correct the error. This process ensures that the original entry is properly reversed and that the correction is properly recorded.

For example, if a sale was recorded in the wrong period or with the wrong customer, the correcting entry would be recorded in the sales journal with the correct date and customer information. Then, a reversing entry would be made in the general journal to cancel out the original entry. Finally, a new entry would be made in the sales journal to correctly record the sale.

It is important to maintain proper documentation of all corrections made in the sales journal. The sales journal should clearly indicate the reason for the correction and the date of the correction. This ensures that the corrected information is accurately reflected in the business's financial records and that the business's financial statements are accurate.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's HTML5 template

---

Process Sales journal in Batch Entry Mode

However, if there is a need for handwritten invoices, they can be captured in the Sales journal using the Batch entry mode.

For the purposes of the sales journal this topic, assume that you will be writing out your invoices manually for sales to your debtors (customers / clients). You simply need to capture the details such as the invoice number, date of the invoice, details of the services or goods sold, the amount and Tax (VAT/GST/Sales Tax) (if you are registered as a Tax (VAT/GST/Sales Tax) vendor) in the Sales journal.

The hand written invoices in this topic are only applicable to the selling of services and items, which does not constitute your trading stock items to debtors (customers / clients) on credit. In this case, you need to manually produce hand-written invoices, which are captured in the Sales journal.

Example : Source documents - Invoices

Capture the following hand-written invoices:



Handyman Hardware Store

VAT Reg. No. 446010111

To: Mr. AB Green
PO Box 1111
Lakeside
Johannesburg
2012
VAT No. 111111111

Tax Invoice: INV001
Date: 7 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Paint - Exterior	1 000.00	-	1 000.00

Sub-total	1 000.00
VAT @ 15%	150.00
Invoice Total	1 150.00

E.&O.E



Handyman Hardware Store

VAT Reg. No. 446010111

To: MAC Shop Decor
Specialists
PO Box 5555
Morningside
Johannesburg
2222
VAT No. 66666666

Tax Invoice: INV002
Date: 9 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Install Built-in Cupboards	1 500.00	-	1 500.00

Sub-total	1 500.00
VAT @ 15%	225.00
Invoice Total	1 725.00

E.&O.E



Handyman Hardware Store

VAT Reg. No. 446010111

To: Mr. AB Green
PO Box 1111
Lakeside
Johannesburg
2122
VAT No. 111111111

Tax Invoice: INV003
Date: 10 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Paint -Exterior	1 000.00	-	1 000.00

Sub-total	1 000.00
VAT @ 15%	150.00
Invoice Total	1 150.00

E.&O.E

Handyman Hardware Store
VAT Reg. No. 446010111

To: Mike Davies
PO Box 333
Halfway House
1685
VAT No. 336012345

Tax Invoice: INV004
Date: 12 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Install Built-in Cupboards	1 500.00	-	1 500.00
			Sub-total	1 500.00
			VAT @ 15%	225.00
			Invoice Total	1 725.00

E.&O.E

Using the Document entry, Invoices may be printed by osFinancials5/TurboCASH5, which will generate similar transactions as the Batch entry in the Sales journal. Using the documents feature to record sales transactions in the Sales journal, you do not have to write out hand written invoices as in this example.

Capture your Invoices in the Sales journal

To enter your Sales transactions in the sales journal:

1. On the Default ribbon, select Batch entry (F2).



If no contra account is displayed on the "Batch type" selection screen, you need to set up the options for the batch. If you have not yet set the Sales journal, or if your requirements should change, click on the F10:Setup icon.

2. Select the “Sales jnl” and click on the Open button.

3. Enter the Alias (batch name) and press the Enter key.



The Alias (Batch name) will help you if you need to identify a specific batch, to print a batch type report, if you wish to export posted batches to a file, etc. The alias (batch name) will also make it easier to identify the specific transactions in reports and various screens, and exported data.

4. Click F10:Setup to set the "*Options for this batch*". On the Standard tab, check the settings, and change, as required.



Note that for Invoices, the "Amount entry" field should be set to Debit.

If you have a few credit notes, you may enter a negative (minus sign), followed by the amount in the credit column. These amounts will be transferred to the debit column.

On the Advanced tab and check and take note of the settings.

If you have many credit notes to capture, you need to set the amount entry to debit in the setup options for the Sales journal, before entering credit notes in the Sales journal. Alternatively, you may enter the credit notes in the Sales returns journal.



Select the "Debtor" option for the Account lookup type, since you only need to select "Debtor" option when you enter transactions for sales on credit to Debtors only.

If you wish to allocate different transactions to different sales accounts, setup one contra account per line.

The Tax report (Reports → Tax) does not include the Sales journal. It only includes Sales documents (i.e. Invoices an Credit notes). Transactions on other Batch types may cause similar errors.

The reason for this, is the Consolidate balancing option on the Standard tab - F10:Setup on the Options for this batch screen. When setting up the batch, an information message will be displayed.

> "Consolidating lines and using tax will mess up your tax report! Please make sure you do not use tax or do not consolidate lines!"

Click on the OK button and click on the F10:Setup icon and deselect (remove the tick) from the

	Consolidate balancing field on the Standard tab of the "Options for this batch" screen. *Balance the batch again.*

5. Once set up; click on the OK button.

6. Capture the following hand-written invoices:



Handyman Hardware Store
VAT Reg. No. 446010111

To: Mr. AB Green
PO Box 1111
Lakeside
Johannesburg
2012
VAT No. 111111111

Tax Invoice: INV001
Date: 7 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Paint - Exterior	1 000.00	-	1 000.00
			Sub-total	1 000.00
			VAT @ 15%	150.00
			Invoice Total	1 150.00

E.&O.E



Handyman Hardware Store
VAT Reg. No. 446010111

To: MAC Shop Decor Specialists
PO Box 5555
Morningside
Johannesburg
2222
VAT No. 66666666

Tax Invoice: INV002
Date: 9 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Install Built-in Cupboards	1 500.00	-	1 500.00
			Sub-total	1 500.00
			VAT @ 15%	225.00
			Invoice Total	1 725.00

E.&O.E

Handyman Hardware Store
VAT Reg. No. 446010111

To: Mr. AB Green
PO Box 1111
Lakeside
Johannesburg
2122
VAT No. 111111111

Tax Invoice: INV003
Date: 10 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Paint -Exterior	1 000.00	-	1 000.00
			Sub-total	1 000.00
			VAT @ 15%	150.00
			Invoice Total	1 150.00

E.&O.E

Handyman Hardware Store
VAT Reg. No. 446010111

To: Mike Davies
PO Box 333
Halfway House
1685
VAT No. 336012345

Tax Invoice: INV004
Date: 12 March 2024
27 Olifants Road
Emmarentia
Johannesburg
2195
Tel : (011) 310-1390

Qty	Description	Price Excl.	Discount	Amount Excl.
	Install Built-in Cupboards	1 500.00	-	1 500.00
			Sub-total	1 500.00
			VAT @ 15%	225.00
			Invoice Total	1 725.00

E.&O.E

7. After capturing all your invoices, the Batch entry screen for the Sales journal should reflect as follows:



"F7: Inclusive" icon - Amounts in the bold font indicate that it is entered Inclusive of VAT/GST/Sales Tax.

If the "F7: Exclusive" icon is displayed, the amounts are entered as Exclusive if VAT/GST/Sales Tax and will be displayed in the normal or regular font.

You have now captured all your sales invoices for the month and may proceed with posting.

Finalising the Sales journal

Once you have completed entering these invoices, and you are sure they are correct, you may proceed to finalise the batch. The recommended process, consists of the following steps:

1. Balance the transactions entered in the sales journal.
2. Print a list the transactions in the sales journal (after the journal is balanced).
3. Post the transactions in the sales journal to the ledger.

Balance the sales journal

Balancing the transactions entered in a sales journal before posting to the ledger is an important step in maintaining accurate financial records for a business. Here are some reasons why:

1. Accuracy: Balancing the transactions in the sales journal helps to ensure that the total debits and total credits are equal, which is the basic principle of double-entry accounting. This helps to minimize the risk of errors or discrepancies in the financial records.
2. Efficiency: Balancing the sales journal before posting to the ledger can help to streamline the posting process by ensuring that all necessary information is complete and accurate. This can help to reduce the time and effort required to correct any errors or discrepancies that may arise later.
3. Compliance: Balancing the transactions in the sales journal is a standard accounting practice and is often required by accounting regulations and standards. This can help to ensure compliance with legal and regulatory requirements.
4. Verification: Balancing the transactions in the sales journal provides an opportunity to review and verify the accuracy of the recorded transactions. This can help to catch any errors or discrepancies that may have been made during the recording process.

Overall, balancing the transactions in a sales journal before posting to the ledger is an essential step in maintaining accurate financial records and ensuring compliance with accounting regulations and standards.

To balance the transactions entered in the sales journal:

Click on the F5:Balance icon. osFinancials5/TurboCASH5 will generate balancing entries. The balancing entries should reflect as follows:



No.	Reference	Date	Description	Debtors	Tax	Debit	Credit	Open item
1	INV001	2024/03/07	Paint - Exterior	D1ABGRE Mr. AB Green	T860010 Output VAT - 15%	1,150.00		
2	INV002	2024/03/09	Install - Built-in cupboard	D1MACDS MAC Shop Decor Specialists	T860010 Output VAT - 15%	1,725.00		
3	INV003	2024/03/10	Paint - Exterior	D1ABGRE Mr. AB Green	T860010 Output VAT - 15%	1,150.00		
4	INV004	2024/03/11	Install - Built-in cupboard	D1MDAVI Mr. Mike Davies	T860010 Output VAT - 15%	1,725.00		
5	********	2024/03/07	Paint - Exterior	T860010 Output VAT - 15%	Bal		150.00	
6	********	2024/03/07	Paint - Exterior	G010000 Sales	Bal		1,000.00	
7	********	2024/03/09	Install - Built-in cupboard	T860010 Output VAT - 15%	Bal		225.00	
8	********	2024/03/09	Install - Built-in cupboard	G010000 Sales	Bal		1,500.00	
9	********	2024/03/10	Paint - Exterior	T860010 Output VAT - 15%	Bal		150.00	
10	********	2024/03/10	Paint - Exterior	G010000 Sales	Bal		1,000.00	
11	********	2024/03/11	Install - Built-in cupboard	T860010 Output VAT - 15%	Bal		225.00	
12	********	2024/03/11	Install - Built-in cupboard	G010000 Sales	Bal		1,500.00	
12						5,750.00	5,750.00	

List the transactions in the Sales journal

Printing a list of transactions in a sales journal before posting to the ledger can be an important step in ensuring accurate financial records for a business. Here are some reasons why:

1. Verification: Printing a list of transactions in the sales journal provides an opportunity to review and verify the accuracy of the recorded transactions before they are posted to the ledger. This helps to catch any errors or discrepancies that may have been made during the recording process. If you find any errors or discrepancies, you can make the necessary corrections in the sales journal before posting the transactions to the ledger. This can help ensure that the financial records are accurate and up-to-date, which is important for making informed business decisions.
2. Organisation: Printing a list of transactions in the sales journal can help to organize and keep track of all the transactions that have been recorded. This can be useful in case there are any questions or disputes that arise regarding specific transactions.
3. Audit trail: Printing a list of transactions in the sales journal can help to create an audit trail that can be used to track the flow of transactions from the source documents (such as sales invoices) to the ledger. This can be important for both internal and external audits.
4. Reference: Printing a list of transactions in the sales journal can serve as a reference for future use. For

example, if a customer calls with a question about a transaction, the sales journal can be used to quickly locate and review the relevant information.

Overall, printing a list of transactions in a sales journal before posting to the ledger can help to ensure accurate and organized financial records, which is important for the success and stability of any business.

To print a list of the transactions in the sales journal:

Click on the F8:List icon to print a list of the transactions in the sales journal.



It is recommended that the source documents (e.g. sales invoices, etc.) be attached to this List of the transactions and that it be retained for record and audit purposes.

You may also click on the *icon (Save the report as a metafile report), and save it as a PDF - compressed file for archiving purposes.*

Post the Sales journal to the Ledger

Click on the F6:Post icon, to post (update) the batch to the ledger.

Posting transactions from a sales journal to the ledger is an important accounting process that helps to ensure accurate financial reporting for a company. When these transactions are posted to the ledger, several things happen:

1. The accounts affected by the transactions are updated: Each transaction in the sales journal represents a sale made by the company. When these transactions are posted to the ledger, the accounts affected by the sale, such as revenue or accounts receivable, are updated with the appropriate amounts.
2. The ledger provides a complete record of transactions: By posting the transactions from the sales journal to the ledger, the ledger provides a complete record of all sales made by the company during the period. This information can be used to prepare financial statements and to analyze the company's financial performance.
3. The accuracy of financial information is improved: Posting transactions to the ledger helps to ensure the accuracy of financial information. By keeping a complete and accurate record of all sales, the company can track its revenue and make informed business decisions based on the financial information.
4. Adjusting entries can be made: Sometimes, errors are made in the sales journal that need to be corrected. When transactions are posted to the ledger, adjusting entries can be made to correct these errors and ensure the accuracy of the financial information.

In summary, posting transactions from a sales journal to the ledger is a crucial step in the accounting process. It helps to ensure the accuracy of financial information, provides a complete record of transactions, and allows for the preparation of financial statements that can be used to analyze the company's financial performance.

T-Account view

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, exported and analysed.

To access the T-Account view of the transactions, do the following:

1. On the Reports ribbon, select Ledger analyser1 or Ledger analyser 2.
2. Select "*Trial balance*" report type and click on the Report button.
3. On the "*Trial balance*", select the "*Sales*" account.

4. Double-click on the selected account; or right-click and select Show details on the context menu.

5. Click on the following to get specific views of transactions:

    - Batch number (e.g. 4 generated by osFinancials). This will list only the transactions for a specific batch (journal).

    - Account code (e.g. G100-000 Sales, T850-010 Output VAT/GST/Sales Tax, D1MD-AVI Mr. Mike Davies, D1AB-GRE Mr. AB Green, DMA-SDS MAC Shop Decor Specialists). This will list the transactions for a selected account.

    - Date – This will list the transactions for a specific date. If you double-click on a date, the *'From date'* and *'To date'* will be changed to the selected date.

After posting the transactions in the Sales journal, the transactions should display as follows in the T-Account viewer:

Batch View



Account view

Accounts in the Debtor's ledger:

Mr. AB Green

D1ABGRE Mr. AB Green				Debit	Credit
4 Sales2403	2024/03/07	INV001	Paint - Exterior Empty,	1,150.00	
4 Sales2403	2024/03/10	INV003	Paint - Exterior Empty,	1,150.00	
			Totals	2,300.00	

MAC Shop Decor Specialist

D1MACDS MAC Shop Decor Specialists				Debit	Credit
4 Sales2403	2024/03/09	INV002	Install - Built-in cupboard Empty,	1,725.00	
			Totals	1,725.00	

Mr. Mike Davies

D1MDAVI Mr. Mike Davies				Debit	Credit
4 Sales2403	2024/03/11	INV004	Install - Built-in cupboard Empty,	1,725.00	
			Totals	1,725.00	

Accounts in the General ledger:

Sales

G010000* Sales				Debit	Credit
4 Sales2403	2024/03/07	*******	Paint - Exterior Empty,		1,000.00
4 Sales2403	2024/03/09	*******	Install - Built-in cupboard Empty,		1,500.00
4 Sales2403	2024/03/10	*******	Paint - Exterior Empty,		1,000.00
4 Sales2403	2024/03/11	*******	Install - Built-in cupboard Empty,		1,500.00
			Totals		5,000.00

Output Tax - 15%

T860010 Output VAT - 15%				Debit	Credit
4 Sales2403	2024/03/07	*******	Paint - Exterior Empty,		150.00
4 Sales2403	2024/03/09	*******	Install - Built-in cupboard Empty,		225.00
4 Sales2403	2024/03/10	*******	Paint - Exterior Empty,		150.00
4 Sales2403	2024/03/11	*******	Install - Built-in cupboard Empty,		225.00
			Totals		750.00

Accounting equation

Debits = *Credits*

Debit Debtor's ledger (i.e. individual *Debtor accounts)*

=

Credit General ledger (i.e. *Sales account +* *Output Tax).*

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Purchase transactions

What is purchase transactions?

Purchase transactions are financial transactions that involve the acquisition of goods or services by a business from a supplier or vendor. These transactions can take various forms, such as placing an order, receiving goods, and making payments.

In a typical purchase transaction, a business will create a purchase order, which specifies the details of the items or services being purchased, such as quantity, price, delivery date, and any special terms or conditions. The purchase order is sent to the supplier or vendor, who will then send the goods or provide the services. The business will then record the transaction in its accounting system, typically in a purchase journal or ledger.

Purchase transactions are an essential part of a business's operations, as they allow the business to acquire the materials, supplies, and services it needs to operate and grow. By tracking purchase transactions, a business can monitor its spending, manage its cash flow, and make informed decisions about its purchasing strategies. It is also important for a business to maintain accurate records of purchase transactions for tax and accounting purposes.

How to incorrect purchase transactions?

If a purchase transaction is incorrect, there are several steps that can be taken to correct it, depending on the nature and extent of the error. Here are some common methods:

1. Return or exchange: If the wrong goods were received or the goods are defective, the business may need to return or exchange them with the supplier or vendor.
2. Adjustment: If the price charged was incorrect, the business may need to adjust the transaction to reflect the correct amount. This can be done by issuing a credit or debit memo, which adjusts the amount owed or paid by the business.

3. Cancellation: If a transaction was recorded in error or if the goods or services are no longer required, it may need to be cancelled or reversed. This can be done by issuing a credit note or cancellation invoice, which cancels the original transaction and corrects the accounting records.
4. Credit or debit note: If there was an overcharge or undercharge, a credit or debit note can be issued to correct the transaction amount.

It is important to maintain accurate records of purchase transactions and correct any errors promptly to avoid overpayment, incorrect inventory balances, and other financial discrepancies. By establishing and maintaining effective internal controls and reviewing and improving processes regularly, a business can minimize errors and prevent similar mistakes from happening in the future.

How to prevent incorrect purchase transactions?

There are several steps that businesses can take to prevent incorrect purchase transactions, including:

1. Implementing proper controls: Businesses should establish proper controls for all purchasing activities, including proper authorization procedures, separation of duties, and regular reconciliations.
2. Conducting thorough vendor research: Before engaging with a vendor or supplier, businesses should conduct thorough research to ensure they are reputable and have a good track record.
3. Ensuring accuracy of purchase orders: Purchase orders should be accurately prepared, including correct quantities, prices, and delivery dates.
4. Verifying deliveries: When goods are received, they should be thoroughly inspected to ensure they match the details of the purchase order.
5. Reviewing invoices: Invoices should be carefully reviewed to ensure they match the purchase order and delivery details. Any discrepancies should be resolved promptly.
6. Regularly reviewing and updating processes: Businesses should regularly review and update their purchasing processes to ensure they are efficient, effective, and minimize the risk of errors.

By implementing these steps, businesses can prevent incorrect purchase transactions and minimize the risk of financial discrepancies, inventory issues, and other related problems.

When to use a general journal or a credit note for purchase transactions?

The decision to use a general journal or a supplier return for purchase transactions depends on the specific circumstances of the transaction.

A general journal entry is typically used to record adjusting entries, corrections, or other non-routine

transactions. For example, if a purchase was recorded in the wrong account or in the wrong period, a general journal entry may be used to correct the error. General journal entries are also used for transactions that do not involve a debtor, such as depreciation or inventory adjustments.

On the other hand, a supplier return is typically used for routine transactions related to returns, discounts, or allowances given to a creditor. If a creditor returns goods or receives a discount or allowance, a supplier return is issued to adjust the amount owed to the creditor. Supplier returns are also used to correct errors related to purchase transactions, such as incorrect pricing or quantity.

In general, if the transaction involves a creditor and is related to returns, discounts, or allowances, a supplier return is typically used. If the transaction is a non-routine transaction or does not involve a creditor, a general journal entry may be more appropriate. However, it is important to follow the specific accounting policies and procedures of the business to ensure that transactions are properly recorded and documented.

What is the recommended process and journal to correct errors in the purchase journal?

If an error is made in the purchase journal, the recommended process to correct it depends on the nature and severity of the error.

If the error is a simple mistake, such as a transposition error in the amount of a purchase, it can typically be corrected by making an adjusting entry in the purchase journal. The adjustment should be made in the same month as the original entry, and the correction should be clearly noted in the purchase journal.

If the error is more complex or if it affects multiple periods, it may be necessary to create a reversing entry in the general journal to cancel out the original entry and then create a new entry to correct the error. This process ensures that the original entry is properly reversed and that the correction is properly recorded.

For example, if a purchase was recorded in the wrong period or with the wrong creditor, the correcting entry would be recorded in the purchase journal with the correct date and creditor information. Then, a reversing entry would be made in the general journal to cancel out the original entry. Finally, a new entry would be made in the purchase journal to correctly record the sale.

It is important to maintain proper documentation of all corrections made in the purchase journal. The purchase journal should clearly indicate the reason for the correction and the date of the correction. This ensures that the corrected information is accurately reflected in the business's financial records and that the business's financial statements are accurate.

Purchase Journal Options in osFinancials5/TurboCASH5

Hand-written invoices received from creditors (suppliers/vendors) can be used when immediate purchase is required or when electronic purchase invoices is not available. These purchase invoices can be captured in the Purchase journal using the Batch entry mode in osFinancials5/TurboCASH5.

The purchase journal is not used to keep track of inventory or stock. The purchase journal is a record of all credit purchases made by a business, including information about the creditor, date of purchase, purchase invoice number, and amount of the purchase. It is used to keep track of the expenses / payments incurred by the business.

Processing Purchase Documents in osFinancials:

1. Batch Entry Mode:
    - This mode is used to capture invoices received from creditors (suppliers/vendors).
    - It does not support stock items (inventory items/products).
2. Document Entry Mode:
    - This mode allows you to create Purchases and Supplier returns linked to the Purchase journal in Setup → Documents (Setup ribbon).
    - It supports stock item types (inventory items/products).
    - This method creates the necessary source documents (Purchases and Supplier returns), which can be printed and reprinted as needed.
    - When documents (Purchases and Supplier returns) are posted to the ledger, the transactions are processed in the Purchase journal.
    - Features of Purchases and Supplier returns:
        - Orders: You can use orders and convert (confirm) the orders to purchases.
        - Comments and Remarks: Add comments and remarks to items on a Order, Purchase and Supplier return document.
        - Standard Messages: Include standard messages on the Order, Purchase and Supplier return document and add additional messages and references.
        - Credit Limit Monitoring: You will be warned if a creditor's credit limit is exceeded it can track their available balance.
    - Support for Additional Stock Item Types:

- This option allows you to create orders, purchases and supplier returns using various stock item types, such as:
  - Financial entry: Use the Accounts lookup to select general ledger accounts.
  - Purchases (no stock): For items that do not involve stock.
  - Purchases and Supplier returns created in this way are automatically linked to the Purchase journal in Setup → Documents (Setup ribbon).
  - When posted to the ledger, these purchases and supplier returns automatically process transactions in the Purchase journal.

- Available Stock Item Types for Purchase Documents:
  - Default
  - Purchases
  - Purchases (no stock)
  - Financial entry
  - Option item
  - Option item (No stock)
  - BOM (Bill of Materials)
  - BOM (Bill of Materials) - Production
  - Linked item

Recommended Approach:

The Document entry mode is recommended for creating purchases whenever possible, as it provides a more efficient and accurate way of managing purchase transactions in osFinancials5.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with a Help Authoring Tool

Purchase journal

Process Purchase journal in Batch Entry Mode

If there is a need for handwritten invoices, they can be captured in the Sales journal using the Batch entry mode.

To record your credit purchases from your creditors (suppliers / vendors), you would need to use the Purchase journal. In this journal, you would enter details such as the supplier invoice number, date of the supplier invoice, creditor information, Input VAT/GST/Sales Tax (if applicable), and the amount (including or excluding VAT/GST/Sales Tax).

The purchase journal is not used to keep track of inventory or stock. The purchase journal is a record of all credit purchases made by a business, including information about the supplier, date of purchase, supplier invoice number, and amount of the purchase. It is used to keep track of the purchases made by the business.

Overall, it is important to accurately record all supplier invoices received for credit purchases. You can choose to use either the Batch entry mode or the Document entry option to do this, depending on your preference and specific needs.

Example : Source documents - Supplier invoices

Capture the following supplier invoices in the Purchase journal:



ABC-Service-Centre
VAT Reg. No. 3333333333

To: Handyman
Hardware Store
27 Olifants Road
Emmarentia
Johannesburg 2195
VAT No. 446010111

Tax Invoice: IN0107
Date: 5 March 2024
PO Box 9999
Lakeside
Johannesburg
2012
Tel : (011) 313-9997

Qty	Description	Price Excl.	Discount	Amount Excl.
	Service Delivery Van	400.00	-	400.00
	5 x New Tyres Fitting and Balancing	600.00		600.00
			Sub-total	1 000.00
			VAT @ 15%	150.00
			Invoice Total	1 150.00

E.&O.E



ABC-Office-Supplies
VAT Reg. No. 4444444444

To: Handyman
Hardware Store
27 Olifants Road
Emmarentia
Johannesburg 2195
VAT No. 446010111

Tax Invoice: IN0014
Date: 6 March 2024
PO Box 8888
Lakeview
Johannesburg
2012
Tel : (011) 312-9997

Qty	Description	Price Excl.	Discount	Amount Excl.
	Supply and Install Built-in Cupboards	1 500.00	-	1 500.00
			Sub-total	1 500.00
			VAT @ 15%	225.00
			Invoice Total	1 725.00

E.&O.E

Using the Document entry, Purchases may be printed by osFinancials5/TurboCASH5, which will generate similar transactions as the Batch entry in the Purchase journal.

Capture your Supplier invoices in the Purchases journal

To enter your purchase transactions in the purchase journal:

1. On the Default ribbon, select Batch entry (F2).

If no contra account is displayed on the "Batch type" selection screen, you need to set up the options for the batch. If you have not yet set the Purchase journal, or if your requirements should change, click on the F10:Setup icon.

2. Select the “Purchase jnl” and click on the Open button.

3. Enter the Alias (batch name) and press the Enter key.



> *The Alias (Batch name) will help you if you need to identify a specific batch, to print a batch type report, if you wish to export posted batches to a file, etc. The alias (batch name) will also make it easier to identify the specific transactions in reports and various screens, and exported data.*

4. Click F10:Setup to set the "*Options for this batch*". On the Standard tab, check the settings, and change, as required.



> *Contra account per line -Select (tick) this option, each time you select a creditor account, you to also need to select a ledger account for each purchase. In this way you can select a different contra account for each transaction. When you balance the batch, osFinancials5/TurboCASH5 will generate all the transactions to each of these contra accounts.*

> *Note that for Purchase or Supplier Invoices, the "Amount entry" field should be set to Credit.*

If you have a few supplier credit notes, you may enter a negative (minus sign), followed by the amount in the credit column. These amounts will be transferred to the debit column.

If you have many supplier credit notes to capture, you need to set the amount entry to debit in the setup options for the Purchase journal, before entering supplier credit notes in the Purchase journal. Alternatively, you may enter the supplier credit notes in the Purchase returns journal.

On the Advanced tab and check and take note of the settings.



Select the “Creditor” option for the "Account lookup type", since you only need to select “Creditor” accounts when you enter transactions for purchases on credit to creditors (suppliers / vendors) only.

Set the “Contra account lookup type” to “General ledger”, since you need to select the ledger account for each purchase. When you balance the batch, osFinancials5/TurboCASH5 will generate balancing transactions for each of these contra accounts to the general ledger accounts

5. Once set up; click on the OK button.

6. Capture the following supplier invoices in the Purchase journal:



ABC-Service-Centre
VAT Reg. No. 3333333333

To: Handyman
Hardware Store
27 Olifants Road
Emmarentia
Johannesburg 2195
VAT No. 446010111

Tax Invoice: IN0107
Date: 5 March 2024
PO Box 9999
Lakeside
Johannesburg
2012
Tel : (011) 313-9997

Qty	Description	Price Excl.	Discount	Amount Excl.
	Service Delivery Van	400.00	-	400.00
	5 x New Tyres Fitting and Balancing	600.00		600.00
			Sub-total	1 000.00
			VAT @ 15%	150.00
			Invoice Total	1 150.00

E.&O.E

ABC-Office-Supplies
VAT Reg. No. 4444444444

To: Handyman
Hardware Store
27 Olifants Road
Emmarentia
Johannesburg 2195
VAT No. 446010111

Tax Invoice: IN0014
Date: 6 March 2024
PO Box 8888
Lakeview
Johannesburg
2012
Tel : (011) 312-9997

Qty	Description	Price Excl.	Discount	Amount Excl.
	Supply and Install Built-in Cupboards	1 500.00	-	1 500.00
			Sub-total	1 500.00
			VAT @ 15%	225.00
			Invoice Total	1 725.00

E.&O.E

7. Enter and/or select the following:

   a) Reference - Enter the purchase or other applicable number you allocate to the supplier invoice.

   b) Date - Enter or select the date of the transaction.

   c) Description - Enter a description for the transaction.

   d) Account - Select the Creditor account.

   e) Contra account - Select the account to be debited with the credit purchase (expense or asset).

   f) Tax - Select the applicable Input Tax account for the expense or purchase.

> *This is only applicable if Input VAT/GST/Sales Tax is allowed on a transaction, and if you are registered as a VAT/GST/Sales Tax Vendor. If no VAT/GST/Sales Tax is applicable to the transaction, select the "Empty" option as the "No Tax" code.*

> *You may also select to hide the Tax column, and lookup facility in the Setup Options for the Purchase journal, if no VAT/GST/Sales Tax is applicable to all transactions in this batch; or if you are not registered as a VAT/GST/Sales Tax Vendor.*

g) Amount - Enter the amount of the transaction (Inclusive or Exclusive of VAT/GST/Sales Tax) in the Credit amount column.

8. After entering the supplier invoices in the Purchase journal, the transactions will be displayed as follows:



Finalising the Purchase journal

Once you have completed entering these invoices, and you are sure they are correct, you may proceed to finalise the batch. The recommended process, consists of the following steps:

1. Balance the transactions entered in the purchase journal.
2. Print a list the transactions in the purchase journal (after the journal is balanced).
3. Post the transactions in the purchase journal to the ledger.

Balance the Purchase journal

Balancing the transactions entered in the purchase journal before posting to the ledger is an important step in maintaining accurate financial records for a business. Here are some reasons why:

1. Accuracy: Balancing the transactions in the sales journal helps to ensure that the total debits and total credits are equal, which is the basic principle of double-entry accounting. This helps to minimize the

risk of errors or discrepancies in the financial records.

2. Efficiency: Balancing the purchase journal before posting to the ledger can help to streamline the posting process by ensuring that all necessary information is complete and accurate. This can help to reduce the time and effort required to correct any errors or discrepancies that may arise later.

3. Compliance: Balancing the transactions in the purchase journal is a standard accounting practice and is often required by accounting regulations and standards. This can help to ensure compliance with legal and regulatory requirements.

4. Verification: Balancing the transactions in the purchase journal provides an opportunity to review and verify the accuracy of the recorded transactions. This can help to catch any errors or discrepancies that may have been made during the recording process.

Overall, balancing the transactions in a purchase journal before posting to the ledger is an essential step in maintaining accurate financial records and ensuring compliance with accounting regulations and standards.

To balance the transactions entered in the purchase journal:

Click on the F5:Balance icon. osFinancials5/TurboCASH5 will generate balancing entries. The balancing entries should reflect as follows:



List the transactions in the Purchase journal

Printing a list of transactions in a purchase journal before posting to the ledger can be an important step in ensuring accurate financial records for a business. Here are some reasons why:

1. Verification: Printing a list of transactions in the purchase journal provides an opportunity to review

and verify the accuracy of the recorded transactions before they are posted to the ledger. This helps to catch any errors or discrepancies that may have been made during the recording process. If you find any errors or discrepancies, you can make the necessary corrections in the sales journal before posting the transactions to the ledger. This can help ensure that the financial records are accurate and up-to-date, which is important for making informed business decisions.

2. Organisation: Printing a list of transactions in the purchase journal can help to organize and keep track of all the transactions that have been recorded. This can be useful in case there are any questions or disputes that arise regarding specific transactions.
3. Audit trail: Printing a list of transactions in the purchase journal can help to create an audit trail that can be used to track the flow of transactions from the source documents (such as sales invoices) to the ledger. This can be important for both internal and external audits.
4. Reference: Printing a list of transactions in the purchase journal can serve as a reference for future use. For example, if a customer calls with a question about a transaction, the purchase journal can be used to quickly locate and review the relevant information.

Overall, printing a list of transactions in a purchase journal before posting to the ledger can help to ensure accurate and organized financial records, which is important for the success and stability of any business.

To print a list of the transactions in the purchase journal:

Click on the F8:List icon to print a list of the transactions in the purchase journal.



It is a good idea to list the batch, and check the entries on the batch thoroughly. If there are any errors, you may edit the batch, before posting the batch.

Post the Purchase journal to the Ledger

Click on the F6:Post icon, to post (update) the purchase journal to the ledger.

Posting transactions from a sales journal to the ledger is an important accounting process that helps to ensure accurate financial reporting for a company. When these transactions are posted to the ledger, several things happen:

1. The accounts affected by the transactions are updated: Each transaction in the purchase journal represents a sale made by the company. When these transactions are posted to the ledger, the accounts affected by the sale, such as revenue or accounts receivable, are updated with the appropriate amounts.
2. The ledger provides a complete record of transactions: By posting the transactions from the purchase journal to the ledger, the ledger provides a complete record of all sales made by the company during the period. This information can be used to prepare financial statements and to analyze the company's financial performance.
3. The accuracy of financial information is improved: Posting transactions to the ledger helps to ensure the accuracy of financial information. By keeping a complete and accurate record of all sales, the company can track its revenue and make informed business decisions based on the financial information.
4. Adjusting entries can be made: Sometimes, errors are made in the sales journal that need to be corrected. When transactions are posted to the ledger, adjusting entries can be made to correct these errors and ensure the accuracy of the financial information.

In summary, posting transactions from a sales journal to the ledger is a crucial step in the accounting process. It helps to ensure the accuracy of financial information, provides a complete record of transactions, and allows for the preparation of financial statements that can be used to analyze the company's financial performance.

Click on the F6:Post icon, to post (update) the batch to the ledger.

It is not necessary to post (update) the transactions at the end of each day. You may add and/or post the transactions on a daily, or weekly basis, or at the end of a month. When you have entered a few transactions, you may close or exit the batch. The data will not be lost.

T-Account view

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, exported and analysed.

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, printed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select Ledger analyser1 or Ledger analyser 2.
2. Select "*Trial balance*" report type and click on the Report button.
3. On the "*Trial balance*", select the "*Creditors control*" account.
4. Click on the following to get specific views of transactions:
    - Batch number (e.g. 3 automatically generated). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. G210-020 Maintenance, G210-030 Repairs, G610-010 Furniture & fittings, T850-020 Input VAT/GST/Sales Tax-Standard rate, C2ABCOS ABC-Office Supplies, C2ABCSC ABC-Service Centre). This will list the transactions for a specific account.
    - Date – This will list the transactions for a specific date. If you double-click on a date, the '*From date'* and '*To date'* will be changed to the selected date.

After posting the transactions in the Purchase journal, the transactions should display as follows in the T-Account viewer:

Batch View



Account view

Accounts in the Creditor's ledger:

ABC-Service-Centre

C2ABCSC ABC-Service-Centre					Debit	Credit
3 Purchases2403	2024/03/05	PU001	Service - Delivery van Empty,			460.00
3 Purchases2403	2024/03/05	PU001	5xNew tyres - Fitting and balancing Empty,			690.00
				Totals		1,150.00

ABC-Office-Supplies

C2ABCOS ABC-Office-Supplies					Debit	Credit
3 Purchases2403	2024/03/06	PU002	Install - Built-in cupboards Empty,			1,725.00
				Totals		1,725.00

Accounts in the General ledger:

Motor vehicles - Maintenance

G210020* Motor vehicles - Maintenance					Debit	Credit
3 Purchases2403	2024/03/05	******	Service - Delivery van Empty,		400.00	
				Totals	400.00	

Motor vehicles - Repairs

G210030* Motor vehicles - Repairs					Debit	Credit
3 Purchases2403	2024/03/05	******	5xNew tyres - Fitting and balancing Empty,		600.00	
				Totals	600.00	

Furniture & fittings @ cost

G600010 Furniture & fittings @ cost					Debit	Credit
3 Purchases2403	2024/03/06	******	Install - Built-in cupboards Empty,		1,500.00	
				Totals	1,500.00	

Input Tax – Standard rate – 15 %

T860020 Input VAT - Standard rate -15%				Debit	Credit
3 Purchases 2403	2024/03/05	*******	Service - Delivery van Empty.	60.00	
3 Purchases 2403	2024/03/05	*******	5xNew tyres - Fitting and balancing Empty.	90.00	
3 Purchases 2403	2024/03/06	*******	Install - Built-in cupboards Empty.	225.00	
			Totals	375.00	

Accounting equation

Debits = *Credits*

Debit General ledger (i.e. *Purchases (Assets) +* *Expenses +* *Input Tax accounts)*

=

Credit Creditor's ledger (i.e. individual *Creditor accounts).*

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Cash transactions

Options to process cash / bank transactions

osFinancials5/TurboCASH5 provides two options for processing transactions for Bank accounts:

1. Manual Transaction Capture:
    - Navigate to Setup → System parameters (Setup ribbon).
    - Ensure the "*Default bank reconciliation*" option is selected.
    - This setting links each bank account to its own separate payment and receipt journal.
    - Enter and process payment transactions separately in the payment journal, and similarly for receipt transactions in the receipts journal.
    - Perform bank reconciliation to reconcile processed transactions with bank statements.
2. Bank Import Plugin:

- Ensure the "*Default bank reconciliation*" option is not selected in Setup → System parameters (Setup ribbon).
- This setting links each bank account to a combined payment and receipt journal in a single batch entry screen.
- Utilise the Bank Import batch entry screen to manage imported banking transactions from valid downloaded bank statements.

Payments and Receipt Journals

Payments and Receipt batches (journals) in accounting are indeed linked to bank accounts and petty cash accounts, and they play a crucial role in recording the physical inflow and outflow of cash in a business. Here's a more detailed explanation:

1. Payments Journal (Cash Disbursements Journal): This journal is used to record all outgoing payments or disbursements made by the business. It includes payments made by check, electronic transfer, or in cash. These payments could be for various purposes, such as paying suppliers, employees, utilities, rent, or any other expenses incurred by the business. The Payments journal helps in tracking cash outflows and ensures that all expenditures are properly documented.
2. Receipts Journal (Cash Receipts Journal): The Receipts Journal, on the other hand, is used to record all incoming cash receipts. This includes payments received from customers, clients, or any other sources of income. Like the Payments journal, it helps in tracking cash inflows and ensures that all revenue is accurately recorded.

Both of these journals are linked to bank accounts and petty cash accounts in the following ways:

- Bank Accounts: Transactions recorded in the Payments and Receipts Journals are closely related to the business's bank accounts. When a payment is made (recorded in the Payments Journal), it usually results in a decrease in the bank balance, and when a receipt is recorded (in the Receipts Journal), it leads to an increase in the bank balance. These journals serve as a bridge between the physical cash transactions and the entries made in the bank statement, ensuring that the bank accounts are accurately reconciled.
- Petty Cash Accounts: Petty cash is a small amount of cash that a business keeps on hand for minor expenses. Transactions involving petty cash, such as replenishing the petty cash fund or recording expenses paid using petty cash, are also recorded in these journals. This helps in maintaining a clear record of petty cash transactions and ensures that the petty cash account is balanced.

While the Payments and Receipts Journals focus on cash transactions, other journals like the Sales Journal and Purchase journal primarily deal with credit transactions. Sales Journal records credit sales to customers, while the Purchase journal records credit purchases from suppliers. These journals help in

tracking accounts receivable (amounts owed to the business by customers) and accounts payable (amounts owed by the business to suppliers) but do not directly involve physical cash flow in and out of the business.

In summary, Payments and Receipts Journals are essential tools for accurately tracking and managing the physical flow of cash in a business, while other journals like the Sales and Purchase journals are more concerned with credit transactions and accounts receivable/payable. Properly maintaining these journals is crucial for effective cash flow management and financial record-keeping.

This procedure describes the process to record transactions in the Receipts journal and the Payments journal, if the Bank import plugin is not activated. If the Bank import plugin, is activated, please read the following:

- *Bank import plugin -*
- *Bank import plugin - Petty cash transactions (Manual entry) -*

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop -The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bankimport plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System parameters.

The bank accounts and the petty cash accounts, are the only source where money can physically flow into and out of the business. The bank account should be strictly monitored to ensure that all the monies that are received are deposited, and that all the payments and/or cheques have been honoured.

Options to Process Cashbook Transactions

Bank transactions are recorded the cashbook. The cashbook consists of a Bank account created in Accounts (Setup ribbon) and linked to its own Payments and Receipts batch. The transactions are manually entered and processed in the following batches:

- Receipts batches - receipts and deposit slips and credits on the bank statements such as interest received, monies paid directly into your bank account.

Create receipts:

- *F9:Process - Create receipts - You may print a receipt and generate a transaction into the receipts batch.*

- *Receive payment option on Open item link - Allows you to print a receipt / payment advise and directly update (post) the receipts batch with the transaction.*
- *F9:Process - Automatic receipts option.*

- Payments batches - cheques or other payment source documents, debits on the bank statements such as bank charges, withdrawals, etc.

Automatic payments:

- *F9:Process - Creditors at date - You may import the creditor accounts with balances as at a selected date. Once these transactions are imported into the payments batch, you may edit the amounts and delete those you do not wish to pay at that stage, if necessary.*
- *F9:Process - Automatic payments option.*

You need to reconcile the bank account / cashbook (Receipts- and Payments batches) with the bank statement in Cash / Bank (Default-ribbon) .

Handyman Hardware Store
27 Olifants Raod
Emmarentia
Johannesburg
2195
Bank Statement No. 5

ABC Bank - Registered Bank
PO Box 111
Johannesburg
2000
Date of Statement: 1 April 2024
Page 1 of 1

Bank Statement for the period 1 March 2024 to 31 March 2024

Date	Transaction Description	Reference	Debit	Credit	Balance
01 March 2024	Balance brought down				3 193.00
01 March 2024	Deposit	D5000		5 000.00	8 193.00
16 March 2024	Deposit	D5001		3 000.00	11 193.00
30 March 2024	Cheque	106	345.00		10 848.00
30 March 2024	Cheque	107	575.00		10273.00
30 March 2024	Cheque	108	750.00		9 523.00
30 March 2024	Cheque	109	150.00		9 373.00
30 March 2024	Cheque	110	230.00		9 143.00
30 March 2024	Cheque	111	100.00		9 043.00
31 March 2024	Service Fee	SF	45.00		8 998.00

Definition of Codes	Deposits	Interest Received	Cheques	Unpaid Cheques	Other Debits	Bank Charges
CO - Commission DO - Debit Order INT- Interest SF - Service Fee UC - Unpaid Cheque	8 000.00	0.00	2 150.00	0.00	0.00	45.00

Important Notice
Statements are accepted as correct unless queried within 30 days. Any cheques reflected on this statement, which are not attached, will be included with your next statement.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System Parameters.

Created with the Standard Edition of HelpNDoc: Quickly and Easily Convert Your Word Document to an ePub or Kindle eBook

Cashbook transactions

Bank transactions are recorded the cashbook. The cashbook consists of a Bank account created in Setup → Accounts menu on the Setup ribbon) and linked to its own Payments and Receipts batch. The transactions are manually entered and processed in the following batches:

- Receipts batches - receipts and deposit slips and credits on the bank statements such as interest received, monies paid directly into your bank account.

> *Create receipts:*
>
> - *F9:Process - Create receipts - You may print a receipt and generate a transaction into the receipts batch.*
> - *Receive payment option on Open item link - Allows you to print a receipt / payment advise and directly update (post) the receipts batch with the transaction.*
> - *F9:Process - Automatic receipts option.*

- Payments batches - cheques or other payment source documents, debits on the bank statements such as bank charges, withdrawals, etc.

> *Automatic payments:*
>
> - *F9:Process - Automatic payments option.*

Once this is done you need to reconcile the bank account in Reconciliation (Default ribbon)with the bank statement.

Handyman Hardware Store
27 Olifants Raod
Emmarentia
Johannesburg
2195

Bank Statement No. 5

ABC Bank - Registered Bank
PO Box 111
Johannesburg
2000

Date of Statement: 1 April 2024
Page 1 of 1

Bank Statement for the period 1 March 2024 to 31 March 2024

Date	Transaction Description	Reference	Debit	Credit	Balance
01 March 2024	Balance brought down				3 193.00
01 March 2024	Deposit	D5000		5 000.00	8 193.00
16 March 2024	Deposit	D5001		3 000.00	11 193.00
30 March 2024	Cheque	106	345.00		10 848.00
30 March 2024	Cheque	107	575.00		10273.00
30 March 2024	Cheque	108	750.00		9 523.00
30 March 2024	Cheque	109	150.00		9 373.00
30 March 2024	Cheque	110	230.00		9 143.00
30 March 2024	Cheque	111	100.00		9 043.00
31 March 2024	Service Fee	SF	45.00		8 998.00

Definition of Codes	Deposits	Interest Received	Cheques	Unpaid Cheques	Other Debits	Bank Charges
CO - Commission DO - Debit Order INT- Interest SF - Service Fee UC - Unpaid Cheque	8 000.00	0.00	2 150.00	0.00	0.00	45.00

Important Notice

Statements are accepted as correct unless queried within 30 days. Any cheques reflected on this statement, which are not attached, will be included with your next statement.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The BankImport plugin allows you to import the transactions from your bank statement and allocate these transactions to the accounts.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Receipts journal

All the receipts (deposits, debit orders into your Bank account, interest received, etc), which are deposited into a specific Bank account are entered in the Receipts journal for the Bank account in which the money is deposited.

The source documents used to enter transactions in a receipt batch are receipts and deposit slips and entries on the bank statement (e.g. bank interest received, etc.).

All receipts and moneys deposited will be displayed on the bank statement, and must be reconciled (usually on a monthly basis) with the Receipts journal. You may find other transactions, such as monies deposited directly into your Bank account, interest, etc. on your bank statement, which are usually dealt with when the bank reconciliation are done.

A copy of a receipt issued to a customer, debtor or other party from whom the money is received, is retained for record purposes, and should be included with the deposit slip. The original receipt is handed

to the party from whom the money is received.

All the moneys received are deposited in the Bank account. A receipt should always be issued when cash is received. In some cases, cheques may be received instead. In these cases, receipts are not always issued, as cheques are listed on the deposit slip when the money is deposited into the Bank account.

Transactions in the Receipts journal can also be generated by the following options:

- Automatic receipts - Batch Processing option.
- Open item link - Debtor - select a transaction and right-click select the *Receive Payment* option on the context menu.
- Create receipts - Batch Processing option. When using this option, you may print the receipt, and the transaction for the receipt will automatically be inserted in the Receipts journal, in which case you do not have to write a hand-written receipt.

Process Transactions in the Receipts journal

To enter transactions in Receipt journals:

1. On the Default ribbon, select Batch entry (F2).

2. Select the Receipts Journal (linked to the correct Bank account) and click on the Open button.



3. Enter the Alias (batch name) in the "*Change alias*" field on the Batch entry screen. In this example we enter *"ABCReceipts2403"* to indicate that the receipts in the ABC Bank account for March 2024 was entered in this Petty cash payments journal.

> *If you have more than one Bank account, select the correct Receipts journal for the Bank account into which the moneys is deposited.*

> *If you have not yet set up the Receipts journal, or if your requirements should change, click on the F10: Setup icon.*

4. Click F10:Setup to set the "*Options for this batch*". On the Standard tab, check the settings, and change, as required.



> *The contra account of the Bank account to which the Receipts journal is linked, will be displayed on the Batch type selection screen. You cannot change the contra account in the batch setup options*

for the Receipts journal.

By default, the “Amount entry” is set to “Allow both”. You cannot set the “Amount entry” to “Credit”.

On the Advanced tab and check and take note of the settings.



3. Enter the Alias (batch name) and press the Enter key.

4. Capture the Deposit slips or Receipts. The following is an example of deposit slips obtained from a bank:











You may have pre-printed deposit slips, which may be pre-numbered and of a different appearance, but the information on the deposit slips is basically the same.

5. Enter and/or select the following:

   a) Reference - Enter the deposit number.

All the receipts on the same deposit slip must have the same reference number. If this is not done, bank reconciliation will be difficult, if not impossible. On the 16th of March, we have two receipts deposited on the last deposit slip. In this case, we use the same reference number (e.g. D5001) to enter both the deposit transactions on the same deposit slip.

b) Date - Enter or select the date of the deposit.

c) Description - Enter a brief description for the transaction.

You need to enter a sensible description (e.g. "Payment Received - Thank you" in the description column, as this will appear on the debtor's statement and it must be useful information for the debtor.

If you have many transactions with descriptions of a repetitive nature, you may assign a key on your keyboard as an abbreviation. For example, if you assign the R key on your keyboard for the description "Payment received - Thank you", you only need to press the R key and press the Enter key in the description field. The full description (e.g. "Payment received - Thank you") will be transferred to the description field.

d) Account - Select the Debtor or other applicable account to which you need to allocate the receipt.

e) Tax - Select the applicable Output Tax account for the receipt, if applicable.

This is only applicable if Output VAT/GST/Sales Tax is allowed on a transaction, and if you are registered as a VAT/GST/Sales Tax Vendor. If no VAT/GST/Sales Tax is applicable to the transaction, select the "Empty" option as the "No Tax" code.

You may also select to hide the Tax column, and lookup facility in the Setup Options for the Receipts journal, if no VAT/GST/Sales Tax is applicable to all transactions in this batch (e.g. only capturing Receipts from Debtors; or if you are not registered as a VAT/GST/Sales Tax Vendor.

f) Amount - Enter the amount of the transaction (Inclusive or Exclusive of VAT/GST/Sales Tax, if applicable).

Should you have any Open item Debtors, an Open item selection screen will appear, listing all debit transactions, as well a you have selected in the account field, if this Debtor account is created as an Open item Debtor. You need to select the spec

payment.



If you need to enter a debit transaction (i.e. early settlement discount allowed), you may enter a negative (minus sign), followed by the amount in the credit column. These amounts will be transferred to the debit column.

You may select (tick) the "Not open item batch" field (F10:Setup - "Options for this batch" - Advanced tab) to de-activate the open item feature in batches.

6. After entering the Deposits in the Receipts journal, the transactions will be displayed as follows:



> *If you have selected a Tax code, in the Cashbook (Receipts journal), the amount EXCLUSIVE of VAT/GST/Sales Tax (NOT the INCLUSIVE of VAT/GST/Sales Tax) is reflected in the amount column, when the cursor is not on the amount field of a transaction.*

> *If a transaction for a debtor in the receipts journal is linked to an transaction on the Open item selection screen, the transaction will be displayed in a peach background colour.*

Finalising the Receipts batch

Once you have completed entering these receipts, and you are sure they are correct, you may proceed to finalise the batch. The recommended process, is as follows:

1. Click on the F5:Balance icon.osFinancials5/TurboCASH5 will generate balancing entries to the Bank account (contra account) and to the Output VAT/GST/Sales Tax account, if a Tax code was selected for a transaction.



2. Click on the F8:List icon to print a list of the transactions in the batch.



> *It is a good idea to list the batch, and check the entries on the batch thoroughly. If there are any errors, you may edit the batch, before posting the batch.*

3. Press or click on the F6:Post icon, to post (update) the batch to the ledger.

> *It is not necessary to post (update) the transactions at the end of each day. You may add and/or post the transactions on a daily, or weekly basis, or at the end of a month. When you have entered a few transactions, you may close or exit the batch. The data will not be lost.*

T-Account view of transactions

After posting the transactions in the Receipts journal, the transactions should display as follows in the T-Account viewer:

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, printed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select T-Account analyser 1.
2. Select an account (e.g. B810-000 ABC - Bank) and double-click on it.
3. Click on the following to get specific views of transactions:
    - Batch number (e.g. 9 automatically generated). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. G505-000 Capital account, B810-000 ABC - Bank, D1AB-GRE Mr. AB Green, D1MA-CDS MAC Shop Decor Specialists). This will list the transactions for a specific account.
    - Date – This will list the transactions for a specific date. If you double-click on a date, the "*From date"* and "*To date*" will be changed to the selected date.

After posting the transactions in the Receipts journal, the transactions should display as follows in the T-Account viewer:

Batch view



Account view

Accounts in the Debtor's ledger:

Mr. AB Green

D1ABGRE Mr. AB Green

				Debit	Credit
9 ABCReceipts2403	2024/03/16	D5001	Payment received - Thank you Empty,		2,000.00
			Totals		2,000.00
					2,000.00

MAC Shop Decor Specialists

D1MACDS MAC Shop Decor Specialists

				Debit	Credit
9 ABCReceipts2403	2024/03/16	D5001	Payment received - Thank you Empty,		1,000.00
			Totals		1,000.00

Accounts in the General ledger:

Capital

G505000 Capital

				Debit	Credit
9 ABCReceipts2403	2024/03/01	D5000	Cash received from owner Empty,		5,000.00
			Totals		5,000.00

ABC - Bank

B810000 ABC-Bank

				Debit	Credit
9 ABCReceipts2403	2024/03/01	*******	Cash received from owner Empty,	5,000.00	
9 ABCReceipts2403	2024/03/16	*******	Payment received - Thank you Empty,	1,000.00	
9 ABCReceipts2403	2024/03/16	*******	Payment received - Thank you Empty,	2,000.00	
			Totals	8,000.00	

Debits = *Credits*

Debit transactions in the General ledger (i.e. Bank account).

=

Credit transactions in the General ledger (i.e. Capital account) + Debtor's ledger (i.e. individual Debtor accounts).

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help

Payments journal

Process Transactions in the Payment journal

To enter your Payments Transactions:

1. On the Default ribbon, select Batch entry (F2).

2. Select the Payments Journal (linked to the correct Bank account) and click on the Open button.



3. Enter the Alias (batch name) in the "*Change alias"* field on the Batch entry screen. In this example we enter *''ABCPayments2403''* to indicate that the payments from the ABC Bank account for March 2024 was entered in this Petty cash payments journal.



The contra account of the Bank account to which the Payments journal is linked, will be displayed on the Batch type selection screen. You cannot change the contra account in the batch setup options for the Payments journal.

By default, the "Amount entry" is set to "Allow both". You cannot set the "Amount entry" to "Debit".

On the Advanced tab and check and take note of the settings.



4. Capture the following payments (cheques) issued on 1 March 2024 in the Payments journal:



5. After capturing the transactions, it should display as follows:



6. Capture the following payments (cheques) issued on 30 March 2016 in the Payments journal:



7. An "*Open item selection"* screen will appear listing all purchase documents for Mr. AB Green. You need to select the purchase document which, is paid, i.e. PU000002. Select the correct amount and press the Enter key. This links this payment to that purchase document.



> *If a transaction for a debtor in the receipts journal is linked to an transaction on the Open item selection screen, the transaction will be displayed in a peach background colour.*

> *You may select (tick) the “Not open item batch” field (F10:Setup - “Options for this batch” - Advanced tab) to de-activate the open item feature in batches.*

8. After entering all your payments (cheques), the screen should reflect your transactions as follows:



"F7: Inclusive" icon - Amounts in the normal or regular font indicate that it is entered Inclusive of VAT/GST/Sales Tax.

If the "F7: Exclusive" icon is selected, the amounts are entered as Exclusive if VAT/GST/Sales Tax and will be displayed in the bold font.

Finalising the Payments batch

Once you have completed entering these payments (cheques), and you are sure they are correct, you may proceed to finalise the batch. The recommended process, is as follows:

1. Click on the F5:Balance icon. osFinancials5/TurboCASH5 will generate balancing entries. The balancing entries should reflect as follows:



2. Click on the F8:List icon to print a list of the transactions in the batch.



F:\TCASH5\plug_ins\reports\GENERAL\documents\batch.rep

List batch - Unposted batch

Batch name ABC-Payments
Alias (batch name) ABCPayments2403

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/01	105	1 x Desk Empty,	G600-010 B810-000	T860-030	-75.00	500.00	
2024/03/01	*******	*1 x Desk Empty,	T860-030 860-030		0.00	75.00	
2024/03/01	*******	*1 x Desk Empty,	B810-000 810-000		0.00		575.00
2024/03/01	106	2 x Chairs Empty,	G600-010 B810-000	T860-030	-45.00	300.00	
2024/03/01	*******	*2 x Chairs Empty,	T860-030 860-030		0.00	45.00	
2024/03/01	*******	*2 x Chairs Empty,	B810-000 810-000		0.00		345.00
				Total		920.00	920.00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/30	107	Rent - April Empty,	G220-000 B810-000	T860-020	-75.00	500.00	
2024/03/30	*******	*Rent - April Empty,	T860-020 860-020		0.00	75.00	
2024/03/30	*******	*Rent - April Empty,	B810-000 810-000		0.00		575.00
2024/03/30	108	Payment on account Empty,	C2AB-COS B810-000		0.00	750.00	
2024/03/30	*******	*Payment on account Empty,	B810-000 810-000		0.00		750.00
2024/03/30	109	Petrol - Mercedez Benz Empty,	G210-010 B810-000		0.00	150.00	
2024/03/30	*******	*Petrol - Mercedez Benz Empty,	B810-000 810-000		0.00		150.00
2024/03/30	110	Waltons - Paper and pens Empty,	G230-000 B810-000	T860-020	-30.00	200.00	
2024/03/30	*******	*Waltons - Paper and pens Empty,	T860-020 860-020		0.00	30.00	
2024/03/30	*******	*Waltons - Paper and pens Empty,	B810-000 810-000		0.00		230.00
2024/03/30	111	Petty cash - Increase float Empty,	B820-000 B810-000		0.00	100.00	
2024/03/30	*******	*Petty cash - Increase float Empty,	B810-000 810-000		0.00		100.00
				Total		1,805.00	1,805.00

An asterisk (*) is automatically displayed before the description of the Balancing Entry, as replaced with your own.

It is recommended that the source documents (e.g. payment requisitions and/or invoices, slips, etc. received from suppliers, etc.) be attached to this List of the transactions and that it be retained for record and audit purposes.

You may also click on the *icon (Save the report as a metafile report), and save it as a PDF - compressed file for archiving purposes.*

3. Click on the F6:Post icon, to post (update) the batch to the ledger.

T-Account view of transactions

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, printed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select T-Account analyser 1.
2. Select an account (e.g. B810-000 ABC - Bank) and double-click on it.
3. Click on the following to get specific views of transactions:
    - Batch number (e.g. 8 automatically generated). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. B810-000 Current Bank account, G610-010 Furniture & fittings @ cost, G210-010 Fuel & Oil, B820-000 Petty cash, G220-000 Rent, C2AB-COS ABC-Office-Supplies, T850-020 Input Tax - Standard rate or T850-030 Input Tax - Capital goods). This will list the transactions for a specific account.
    - Date – This will list the transactions for a specific date. If you double-click on a date, the "*From date"* and "*To date*" will be changed to the selected date.

After posting the transactions in the Payments journal, the transactions should display as follows in the T-Account viewer:

Batch view



Account view

Debit transactions in the Creditor's ledger:

ABC-Office-Supplies

C2ABCOS ABC-Office-Supplies

					Debit	Credit
8	2024/03/30	108	Payment on account		750.00	
ABCPayments 2403			Empty,			
				Totals	750.00	

Debit transactions in the General ledger:

Furniture & fittings @ cost

G600010 Furniture & fittings @ cost

					Debit	Credit
8	2024/03/01	105	1 x Desk		500.00	
ABCPayments 2403			Empty,			
8	2024/03/01	106	2 x Chairs		300.00	
ABCPayments 2403			Empty,			
				Totals	800.00	

Rent

G220000* Rent

					Debit	Credit
8	2024/03/30	107	Rent - April		500.00	
ABCPayments 2403			Empty,			
				Totals	500.00	

Motor vehicles - Fuel & oil

G210010* Motor vehicles - Fuel & oil

					Debit	Credit
8	2024/03/30	109	Petrol - Mercedez Benz		150.00	
ABCPayments 2403			Empty,			
				Totals	150.00	

Stationery

G230000* Stationery

					Debit	Credit
8	2024/03/30	110	Waltons - Paper and pens		200.00	
ABCPayments 2403			Empty,			
				Totals	200.00	

Petty cash

B820000 Petty cash				Debit	Credit
8 ABCPayments 2403	2024/03/30	111	Petty cash - Increase float Empty,	100.00	
			Totals	100.00	

Input Tax – Standard rate - 14%

T860020 Input VAT - Standard rate -15%				Debit	Credit
8 ABCPayments 2403	2024/03/30	*******	Rent - April Empty,	75.00	
8 ABCPayments 2403	2024/03/30	*******	Waltons - Paper and pens Empty,	30.00	
			Totals	105.00	

Input Tax – Capital goods - 14%

T860030 Input VAT - Capital goods -15%				Debit	Credit
8 ABCPayments 2403	2024/03/01	*******	1 x Desk Empty,	75.00	
8 ABCPayments 2403	2024/03/01	*******	2 x Chairs Empty,	45.00	
			Totals	120.00	

Credit transactions in the General ledger:

ABC - Bank

B810000 ABC-Bank				Debit	Credit
8 ABCPayments 2403	2024/03/01	*******	1 x Desk Empty,		575.00
8 ABCPayments 2403	2024/03/01	*******	2 x Chairs Empty,		345.00
8 ABCPayments 2403	2024/03/30	*******	Rent - April Empty,		575.00
8 ABCPayments 2403	2024/03/30	*******	Payment on account Empty,		750.00
8 ABCPayments 2403	2024/03/30	*******	Petrol - Mercedez Benz Empty,		150.00
8 ABCPayments 2403	2024/03/30	*******	Waltons - Paper and pens Empty,		230.00
8 ABCPayments 2403	2024/03/30	*******	Petty cash - Increase float Empty,		100.00
			Totals		2,725.00

Debits = *Credits*

Debit transactions in the General ledger (i.e. *Petty cash* + *Furniture & fittings* + Expenses + Tax (Input VAT/GST/Sales Tax)) and Creditor's ledger (i.e. individual Creditor accounts).

=

Credit transactions (i.e. payment transactions from the *Bank account).*

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Petty cash transactions

What is petty cash?

Petty cash is a small amount of cash that is kept on hand by a business or organization to cover small, incidental expenses.

This fund is typically used for expenses such as office supplies, postage, taxi fares, or other small purchases that do not warrant the use of a company credit card or a check.

The amount of petty cash maintained by a business may vary depending on the size and nature of the organization. Typically, petty cash is held in a secure location and is managed by a designated employee, such as an administrative assistant or office manager.

To ensure that the petty cash fund remains balanced and that all transactions are properly accounted for, a petty cash book or ledger is maintained. This book is used to record all transactions made from the petty cash fund, including the date, amount, purpose, and recipient of each expenditure.

At regular intervals, such as at the end of each month or quarter, the petty cash fund is reconciled to ensure that the balance of the fund matches the total of the transactions recorded in the petty cash book.

Source documents

The source documents used to enter transactions in petty cash are typically receipts, invoices, and other documents that provide evidence of the transaction.

For example, if a small amount of cash is used to purchase office supplies, a receipt would be obtained and used as the source document to record the transaction in the petty cash book.

Other types of transactions that may be recorded in a petty cash book could include reimbursements for

small expenses such as transportation costs, office snacks or coffee, and other incidental expenses.

In order to maintain accurate records of petty cash transactions, it's important to ensure that all source documents are properly dated and contain the necessary details, such as the amount spent, the purpose of the expenditure, and the names of any individuals involved in the transaction. This will help to ensure that all transactions are properly accounted for and can be easily reconciled with the petty cash book.

Petty cash vouchers

A petty cash voucher is a small form or document that is used to record transactions for small, incidental expenses paid from a petty cash fund.

The voucher typically contains information such as the date of the transaction, the amount of the expense, the purpose of the expenditure, the name of the payee or recipient, and the signature of the person authorizing the expense.

Petty cash vouchers are important because they provide a record of all transactions made from the petty cash fund, which helps to ensure that all expenditures are properly accounted for and that the fund remains balanced.

The voucher is usually submitted along with the original receipt or other source document as evidence of the transaction. It is then used to record the transaction in the petty cash book or ledger, which is used to track all transactions made from the petty cash fund.

Petty cash payments should be used as a bank account. If it is used as a normal General ledger – Balance sheet Account, it could cause problems on the Tax Reports (Input VAT/GST/Sales Tax).

You may also reconcile your Petty cash payments and Receipt batches.

For the purposes of this tutorial, we assume that you have paid the following expenses from your petty cash:


Handyman Hardware Store
Petty Cash Voucher No. PCV001
Date: 31 March 2024
Waltons - Paper (VAT Incl.) ------46.00
Total: ------46.00
Account: Stationery - Acc 230
Petty Cashier: Authorised:


Handyman Hardware Store
Petty Cash Voucher No. PCV002
Date: 31 March 2024
ABC Service Station - Fix Puncture ------10.00
Total: ------10.00
Account: Motor Vehicle Repairs - Acc 210-020
Petty Cashier: Authorised:

Petty cash transactions

This procedure describes the process to record Petty cash transactions if the Bank import plugin is not activated. If the Bank import plugin, is activated, please read the following:

- *Bank import plugin -*
- *Bank import plugin - Petty cash transactions (Manual entry) -*

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop -The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bankimport plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System parameters.

In addition to bank accounts, petty cash accounts, is the only source where money can physically flow into and out of the business. The bank account should be strictly monitored to ensure that all the monies that are received are deposited, and that all the payments and/or cheques have been honoured.

Select and Open the Petty cash journal

To enter your Petty cash payment transactions:

1. On the Default ribbon, select Batch entry (F2).

2. Select the Petty cash Pay Jnl and click on the Open button. The *Petty cash journal* screen will be displayed.



3. Enter the Alias (batch name) in the "*Change alias*" field on the Batch entry screen. In this example we enter *''PettyCash2403''* to indicate that the Petty cash payments for March 2024 was entered in this Petty cash payments journal.

> *The alias option allows you to identify a batch by a unique name. You will be able to select the batch by alias or batch name if you need to reverse the posted batch or import a posted batch.*

4. Click on the F10:Setup icon to set the Options for the batch, if necessary.



> *The contra account of the Bank account to which the Petty cash payments journal is linked, will be displayed on the Batch type selection screen. You cannot change the contra account in the batch setup options for the Payments journal.*

> *By default, the "Amount entry" is set to "Allow both". You cannot set the "Amount entry" to "Debit".*

On the Advanced tab and check and take note of the settings.



If you need to enter transactions with Tax accounts, you need to check that the Consolidate balancing field is not selected (not ticked) on the Standard tab of the F10:Setup (Options for this batch screen).

5. Select the General ledger option for the Account lookup type, since you do not need to select Debtor or Creditor accounts when you enter transactions for petty cash payments.

6. Once set up; click on the OK button. You are now ready to capture your first petty cash voucher.

Ref. No.	*Date*	*Description*	*Account*	*Tax*	*Amount*
PCV001	*2024/03/31*	*Paper - Waltons*	*Stationery*	*Input VAT/GST/ Sales Tax*	*46.00*
PCV002	*2024/03/31*	*Fix Puncture ABC Service Station*	*Maintenance*	*No Tax*	*10.00*

7. Capture your petty cash vouchers from your petty cash voucher book or from your requisitions. Use your petty cash voucher number as the reference number.

    a) Reference: PCV001

    b) Date: 2024/03/31

c) Description: Waltons Paper

d) Account: Type 720 or Petty cash and select the correct Petty cash account.

e) Contra account: Type 230 or Stationery to select the correct account, for this payment.

f) Tax: Input VAT/GST/Sales Tax - Standard Goods.

g) Amount: 46.00 CR Ensure that the F7:Inclusive icon is reflecting "*inclusive*". This should be so as we set the batch to the inclusive mode.

8. You are now ready to enter your next petty cash voucher no. PCV002.

a) Reference: PCV002

b) Date: 2024/03/31

c) Description: ABC Service Centre - Fix Puncture

d) Account: Type 720 or Petty cash and select the correct Petty cash account.

e) Contra account: Type 210020 or Maintenance to select the correct account, for this payment.

f) Tax: No Tax

g) Amount: 10.00 CR

9. After capturing all your petty cash vouchers, the Petty cash journal is displayed as follows:



"F7: Inclusive" icon - Amounts in the bold font indicate that it is entered Inclusive of VAT/GST/Sales Tax.

If the "F7: Exclusive" icon is displayed, the amounts are entered as Exclusive if VAT/GST/Sales Tax and will be displayed in the normal or regular font.

When you enter a transaction and the cursor is in the -

- *Account field, you need to select the correct contra account to be credited with the petty cash payment. This should at all times be the Petty cash account.*
- *Contra account field, you need to select the correct account to be debited with the petty cash payment.*

Posting the Petty cash batch

Once you have completed entering these petty cash payments, and you are sure they are correct, you may proceed to finalise the batch. The recommended process, is as follows:

1. Click on the F5:Balance icon. osFinancials5/TurboCASH5 will generate balancing entries to the selected contra accounts and the "*Input VAT/GST/Sales Tax - Standard Rate*" and the "*Petty cash*" accounts.



The Balancing Entries will automatically be generated for each transaction to the Contra account (e.g. Petty cash account) and the Input Tax (VAT/GST/Sales Tax) accounts.

If the description is displayed as "BALANCING ENTRY Pay.PettyCash", the Tax reports may not include these transactions correctly. This implies that the Consolidate balancing field is ticked on the Standard tab of the F10:Setup (Options for this batch screen).

You need to deselect (remove the tick) of the Consolidate balancing field on the Standard tab of the F10:Setup (Options for this batch screen) and rebalance the batch.

2. Click on the F8:List icon to print a list of the transactions in the batch.



It is recommended that the source documents (e.g. petty cash vouchers and/or invoices, slips, etc. received from suppliers, etc.) be attached to this List of the transactions and that it be retained for record and audit purposes.

3. Click on the F6:Post icon, to post (update) the batch to the ledger.

T-Account view of transactions

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, exported and analysed.

To access the T-Account view of the Transactions, do the following:

1. Click on the T-Account Analyser (on the Sidebar (Quick menu); or on the Tools menu).
2. Select an Account (e.g. B820-000 Petty cash) and double-click on it.
3. Click on the following to get specific views of transactions:
    - Batch number (e.g. 10 generated by osFinancials). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. B820-000 Petty cash, G210-020 Maintenance G230-000 Stationery, 860-020 Input VAT – Standard rate - 15%). This will list the transactions for a specific account.
    - Date – This will list the transactions for a specific date. If you double-click on a date, the From date and To date will be changed to the selected date.

After posting the transactions in the Petty cash payments journal, the transactions should display as follows in the T-Account viewer:

Batch View



Account View

Petty cash

B820000 Petty cash

				Debit	Credit
10 PCPayments 2403	2024/03/31	*******	Waltons - Paper Empty,		46.00
10 PCPayments 2403	2024/03/31	*******	ABC - Service Station -Fix puncture Empty,		10.00
			Totals		56.00

Motor vehicles - Maintenance

G210020* Motor vehicles - Maintenance

				Debit	Credit
10 PCPayments 2403	2024/03/31	PCV002	ABC - Service Station -Fix puncture Empty,	10.00	
			Totals	10.00	

Stationery

G230000* Stationery

				Debit	Credit
10 PCPayments 2403	2024/03/31	PCV001	Waltons - Paper Empty,	40.00	
			Totals	40.00	

Input VAT – Standard rate - 15%

T860020 Input VAT - Standard rate -15%

				Debit	Credit
10 PCPayments 2403	2024/03/31	*******	Waltons - Paper Empty,	6.00	
			Totals	6.00	

Accounting equation

Debits = Credits

Debit General ledger (i.e. Expenses + Input Tax)

=

Credit General ledger (i.e. payment transactions from the Petty cash (Bank account)) - (Inclusive of Input VAT/GST/Sales Tax).

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

General journal

What is the general journal used for?

The general journal is a book or computer program used in accounting to record all transactions in chronological order. It is also known as the "*journal*" or "*journal entry book*".

Each transaction recorded in the general journal includes a date, a brief description of the transaction, the accounts involved, and the amounts debited or credited. These transactions are then later transferred to the appropriate ledgers for posting and summarization.

The general journal is used to record a wide range of transactions, such as sales, purchases, expenses, and other financial transactions. It is also used to record adjusting entries and closing entries at the end of an accounting period.

By recording all transactions in the general journal, a business can keep a complete and accurate record of its financial activities. This information is then used to prepare financial statements and to analyze the financial performance of the business. The general journal is an essential tool for any business that wants to maintain accurate financial records and make informed decisions about its financial activities.

When should a general journal not be used?

A general journal should NOT be used in certain situations where there are specific journals designed for recording transactions. For example:

1. Sales and purchases: For recording sales and purchases, specialized journals like sales journal and purchase journal should be used.
2. Cash transactions: For recording cash transactions, specialized journals like cash receipts journal and cash disbursements journal should be used.
3. Payroll: For recording payroll transactions, a specialized journal like payroll journal should be used.
4. Fixed assets: For recording fixed asset transactions, a specialized journal like fixed asset journal should be used.

In general, a general journal is used to record non-routine or unusual transactions that do not fit into the other specialized journals. However, if there is a specific journal available for a particular type of transaction, it is best to use that journal to ensure accuracy and efficiency in record-keeping.

The General journal is used to enter the general transactions and corrections, or adjustments, you would not normally enter in the Sales journal, Purchase journal, Receipts journal, Payments journal.

When to use the general journal?

The general journal is used to enter and post (update) non-regular transactions to the General journal, such as:

- To Take-on your Opening Balances for General ledger accounts, Debtor accounts and Creditor accounts.
- To correct errors in posting (accounts have been debited or credited incorrectly or with incorrect amounts, etc.)
- To enter transactions for depreciation of fixed assets.
- To write-off bad debts and make provision for doubtful debts.
- To do year-end adjustments for the accrual-based accounting.

You may create or add any other Batch types or Journal types in Setup → Batch types to suit your specific requirements.

Examples of journals that you could use for specific other transactions:

- *Payroll journal: For recording payroll transactions*
- *Adjustments journal: - Accrual journal:*

- *Fixed assets journal: Depreciation journal:*

To process transactions in the General journal:

1. On the Default ribbon, select Batch entry (F2).

2. Select the General journal.

> *If no contra account, or a different contra account than the contra account you wish to use, is displayed on the Batch type selection screen, you need to set up the options for the batch. If you have not yet set up the General journal, or if your requirements should change, click on the F10:Setup icon.*

3. Click on the Open button.

> *Note that for General journal, the Amount entry field could be set to debit, credit or allow both, depending on your requirements.*

4. Enter the Alias (batch name) in the *Change alias* field on the Topbar of the Batch entry screen.

> *The alias option allows you to identify a batch by a unique name. You will be able to select the batch by alias or batch name if you need to reverse the posted batch or import a posted batch.*

5. Enter and/or select the following:

a) Reference number - Enter the applicable reference number.

b) Date - Enter or select the date of the transaction.

c) Description - Enter a brief description for the transaction.

> *You need to enter a sensible description to describe the nature of the transaction.*

d) Account - Select the applicable account to which you need to allocate the debit or the credit transaction.

e) Tax - Select the applicable Input Tax or Output Account for the transaction, if applicable.

> *This is only applicable if Input VAT/GST/Sales Tax is allowed on a transaction, and if you are registered as a VAT/GST/Sales Tax Vendor. If no VAT/GST/Sales Tax is applicable to the transaction, select the "Empty" option as the "No Tax" code.*

> *Since no Tax is applicable to these transactions, you may select to hide the tax column, F7:Exclusive and F7:Inclusive icons, as well as the lookup facility in the Setup options for the General journal, as in this example.*

f) Amount - Enter the amount of the transaction (Inclusive or Exclusive of VAT/GST/Sales Tax, if applicable).

6. After entering the transactions in the General journal, the transactions will be displayed as follows:



You may enter transactions in a batch daily, and only post at the end of the month. Exiting or closing the batch, or even osFinancials5/TurboCASH5, will not cause these transactions to be lost. You may also choose to post after every entry.

7. Click on the F5:Balance icon, to create balancing transactions for the transactions entered in the batch, if the batch is not in balance.

It is not necessary to balance the batch if you have entered debit transactions for the same amount as for credit transactions, the net total of all transactions (debits minus credits) and the reference total for the entire batch (journal) should be zero.

will generate balancing entries to the selected contra accounts and the Input VAT/GST/Sales Tax or Output VAT/GST/Sales Tax accounts (if a Tax code was selected for a transaction).

8. Click on the F8:List icon to print a list of the transactions in the batch.

It is a good idea to list the batch, and check the entries on the batch thoroughly. If there are any errors, you may edit the batch, before posting the batch.

9. Click on the F6:Post icon, to post (update) the batch to the ledger.

It is not necessary to post (update) the transactions at the end of each day. You may add and/or post the transactions on a daily, or weekly basis, or at the end of a month. When you have entered a few transactions, you may close or exit the batch. The data will not be lost.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Export / Import batch transactions

The following options is available to export and import batch transactions:

- Posted batches - Import a posted batch option (F9:Process) of the "*Batch entry*" screen. You may select a posted batch on the Posted batches tab of the "*Batch entry*" screen to import.
- Spreadsheet Import Export - osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export feature.

- Spreadsheet export - You may export unposted batch transactions and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import batch transactions from a saved "*Excel Workbook (*.xlsx) file type.*

- Unposted batches
  - Export batch transactions - Write delimited file option (F9:Process) of the "*Batch entry*" screen. This will create a Comma Separated Value (*.csv) file.
  - Import batch transactions - Delimited file import option (F9:Process) of the "*Batch entry*" screen. Select the Comma Separated file (*.csv) file.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Export posted batches

All files exported in the Posted batches option in the Export (Setup ribbon) cannot be imported as the TXF or XML file formats.

All other file types in the (Posted batches) option in the Export (Setup ribbon) cannot be imported as well using the Posted batches import option (F9:Process) option of the Batch entry screen.

The following options is available to export and import batch transactions:

- Posted batches - Import a posted batch option (F9:Process) of the "*Batch entry*" screen. You may select a posted batch on the Posted batches tab of the "*Batch entry*" screen to import.
- Spreadsheet Import Export - osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export feature.
  - Spreadsheet export - You may export unposted batch transactions and save it as a "*Excel Workbook (*.xlsx) file type.*
  - Spreadsheet import - You may import batch transactions from a saved "*Excel Workbook (*.xlsx) file type.*
- Unposted batches
  - Export batch transactions - Write delimited file option (F9:Process) of the "*Batch entry*"

screen. This will create a Comma Separated Value (*.csv) file.

- Import batch transactions - Delimited file import option (F9:Process) of the "*Batch entry*" screen. Select the Comma Separated file (*.csv) file.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Import a posted batch

This option allows you to import the transactions from a posted batch in the same Set of Books.

If you need to import posted batches from TurboCASH4 or a different Set of Books in osFinancials, osFinancials5/TurboCASH5, you need to:

1. *On the Setup ribbon, go to Export (Posted batches tab) and create a valid export file in the Set of Books containing that batch.*
2. *On the Default ribbon, go to Batch entry - F9:Process and select the "Posted batches import" option in the Set of Books you need to import the batch.*

To import a posted batch:

1. On the Default ribbon, select Batch entry (F2).
2. Select a Batch type and click on the Open button.
3. Click on the F9:Process icon. The "*Process the batch*" options screen is displayed:



4. Select the Import a posted batch option, and click on the OK button. The "*Reverse posted batch/document*" screen is displayed:



5. All posted batches associated with the selected batch type, will be listed. Select a batch to import. The Alias (batch name) makes it easier to identify the correct batch to import. View the details of the batch to make absolutely sure that it is the correct batch (journal).

> *To view the details of the transactions in the selected batch (journal), you may:-*
>
> - *Double-click on the selected batch (journal).*
> - *On the Details tab, the transactions for the selected batch will be listed. (If you wish to print a list of the transactions in the posted batch, you may click on the Print button to print a "Batch type - Posted batch" report).*

6. If you double-click, or select the Details option on the context menu, the following screen is

displayed:



Line	Date	Description	Cost centre 1	Cost centre 2	Default account	Tax	Debit	Credit	Amount entry	Amount exclusive
1	2022/03/07	Paint - Exterior	Empty	Empty	010-000	860-010	1,150.00	0.00	1,150.00	☑
2	2022/03/09	Install - Built-in cupboard	Empty	Empty	010-000	860-010	1,725.00	0.00	1,725.00	☑
3	2022/03/10	Paint - Exterior	Empty	Empty	010-000	860-010	1,150.00	0.00	1,150.00	☑
4	2022/03/12	Install - Built-in cupboard	Empty	Empty	010-000	860-010	1,725.00	0.00	1,725.00	☑
5	2022/03/07	Paint - Exterior	Empty	Empty	-	-	0.00	150.00	150.00-	☑
6	2022/03/07	Paint - Exterior	Empty	Empty	-	860-010	0.00	1,000.00	1,000.00-	☑
7	2022/03/09	Install - Built-in cupboard	Empty	Empty	-	-	0.00	225.00	225.00-	☑
8	2022/03/09	Install - Built-in cupboard	Empty	Empty	-	860-010	0.00	1,500.00	1,500.00-	☑
9	2022/03/10	Paint - Exterior	Empty	Empty	-	-	0.00	150.00	150.00-	☑
10	2022/03/10	Paint - Exterior	Empty	Empty	-	860-010	0.00	1,000.00	1,000.00-	☑
11	2022/03/12	Install - Built-in cupboard	Empty	Empty	-	-	0.00	225.00	225.00-	☑
12	2022/03/12	Install - Built-in cupboard	Empty	Empty	-	860-010	0.00	1,500.00	1,500.00-	☑
12							5750.00	5750.00	0.00	

7. All the details of the transactions entered or imported and posted (updated) to the ledger for the selected batch, will be displayed. Check that the selected batch (journal) contains the transactions which needs to be imported, and click on the Batch entry tab.

You may click on the Print button to print the transactions in the posted batch. An example of the "Batch type - Poste



Only those batches for the selected batch type will be listed.

8. Select a batch and click on the OK button. All the transactions in the selected, posted batch will be imported into the selected batch. An example, is as follows:



Should the processing icons on the "Batch entry" screen is inactive during this process, you may need to close and reopen the batch.

Once you have finished entering / editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*
4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Keep Your Sensitive PDFs Safe with These Easy Security Measures

Write delimited file

The Write delimited file batch processing option allows you to export transactions in an unposted batch to a valid Comma Separated Batch (*.csv) file format.

To import delimited files in a batch, you need to select a valid file format using the Delimited file import batch processing option.

To write a delimited file:

1. On the Default ribbon, select Batch entry (F2).

2. Select a Batch type and click on the Open button.

> *You may right-click on the selected batch (journal) on the Batch type selection screen, and select the Write delimited file option on the context menu.*

3. Click on the F9:Process icon. The "*Process the batch options*" screen will be displayed.



4. Select the Write delimited file option, and click on the OK button. The "*Save as*" screen will be displayed.



5. Enter a File name for the "*Comma Delimited Batches*" file. You may select any valid folder on your system, in which you wish to save the file. You may create a new folder, if you click on the New folder icon on the *"Save as"* screen.

6. Click on the Save button. All the transactions in the selected batch will be saved (exported) into the selected folder.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Delimited file import

The Delimited file import batch processing option allows you to import transactions in a batch from valid Comma Separated Batch (*.csv) file format.

To import delimited files in a batch, you need to select a valid file format (created with the Write delimited file option).

To import a delimited file into a batch:

1. On the Default ribbon, select Batch entry (F2).

> *You may right-click on the selected batch (journal) on the Batch type selection screen, and select the Delimited file import option on the context menu.*

2. Select a Batch type and click on the Open button. The Batch entry transaction screen for the selected Batch type will be displayed.

3. Click on the F9:Process icon. The "*Process the batch*" options screen is displayed:



4. Select the Delimited file import option, and click on the OK button.

5. The "*Open*" screen is displayed:



6. Select valid "*Comma Delimited Batches*" (default) file from the folders on your system

7. Click on the Open button. All the transactions in the selected, posted batch will be imported into the selected batch.



Should the processing icons on the "Batch entry" screen is inactive during this process, you may need to close and reopen the batch.

Imported or copied text in osFinancials5/TurboCASH5 screens from external files - Description lines in batches

When importing or copying text for account. group descriptions or any other screens, or forms, the fields from external programs such as spreadsheet, word documents, etc. the hyphenation character "–" may be displayed as a pipe character " | " in lookups and some screens or as " " in some screens and in reports, document layout files, etc.

For example, Motor vehicles Net value if copied or imported into Setup - Accounts as Motor vehicles – Net value (with the hyphenation format) it will be displayed as Motor vehicles Net value on some screens and in reports and as Motor vehicles | Net value on lookup screens.

You need to use the dash sign "-" to be displayed correctly.

Solution:

To ensure hyphens display correctly in osFinancials5/TurboCASH5, use the standard dash character ("-") instead of the hyphenation character when copying or importing text from external files.

8. All the transactions included in the Exported file saved using the "*Write delimited file*" option, will be imported into the batch.

*If Balancing entries (transactions indicated with ******** (8 asterisks) in the "Reference" column) were included in the must be deleted.*



9. Edit the transactions as necessary. In this example the Debtors account is "*T-Empty*". You may need to select the account,, or delete the transaction, if you do not wish to import that transaction.

It is important to check and edit the transactions imported in the batch, before you proceed to balance and post the batch.



10. Press F5: Balance to generate balancing entries for the batch. The balancing entries, as per this example, should be as follows:



Once you have finished entering / editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*
4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Batch transactions - Spreadsheet Export / Import

osFinancials5/TurboCASH5 supports the "*Excel Workbook (*.xlsx) file type* Spreadsheet import and export feature.

- Spreadsheet export - You may export unposted batch transactions and save it as a "*Excel Workbook (*.xlsx) file type.*
- Spreadsheet import - You may import batch transactions from a saved "*Excel Workbook (*.xlsx) file type.*

This feature may be used to import transactions into:

- Batches into the same Set of Books - Also handy to handle Repeating transactions.
- Batches into a different Set of Books with a similar accounts.
- Batches into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Firebird database types.
- Batches into a new Set of Books - Created from scratch - Create your own Set of Books (Advanced)? option for Microsoft SQL sever (MSSQL) database types.

Before you may import batch transactions in a new Set of Books, you need to do the necessary setup and add batch types.

You also need to create or import:

- *Accounts*
- *Debtor (customer / client) accounts*
- *Creditor (supplier / supplier) accounts*

Once this is done, you may start to import batch transactions from a saved "Excel Workbook (.xlsx) file type.*

Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Batch transactions - Spreadsheet Export

You may export unposted batch transactions in a selected batch and save it in a spreadsheet "*Excel Workbook (*.xlsx) file type.*

You may then import it into a batch, when required.

To export batch transactions from a Excel Workbook (xlsx) file:

1. On the Default ribbon, select Batch entry (F2).
2. Select an unposted batch, and click Open.



3. Click on the Spreadsheet import icon.
4. The "*Data Import Export*" be launched without any data.



5. On the "*Data Import Export*" screen, click Export. All the transactions (excluding the balancing transactions, if the batch is already balanced) in the unposted batch will be imported the "*Data Import Export*" screen.



SREFERENCE	SACCOUNT	SDESCRIPTION	FAMOUNT	STAX	DDATE	SCONTRAACCOUNT	BEXCLUSIVE	SJOBCODE	SCOSTGROUP1	SCOSTGROUP2
INV001	D1ABGRE	Paint - Exterior	1,000.00	T860010	2022/03/07	G010000	1		Empty	Empty
INV002	D1MACDS	Install - Built-in cupboard	1,500.00	T860010	2022/03/09	G010000	1		Empty	Empty
INV003	D1ABGRE	Paint - Exterior	1,000.00	T860010	2022/03/10	G010000	1		Empty	Empty
INV004	D1MDAVI	Install - Built-in cupboard	1,500.00	T860010	2022/03/12	G010000	1		Empty	Empty

If the Batch includes balancing transactions, these will not be included in the "Data Import Export" screen.

Imported or copied text in osFinancials5/TurboCASH5 screens from external files - Description lines in batches

When importing or copying text for account. group descriptions or any other screens, or forms, the fields from external programs such as spreadsheet, word documents, etc. the hyphenation character "–" may be displayed as a pipe character " | " in lookups and some screens or as " " in some screens and in reports, document layout files, etc.

For example, Motor vehicles Net value if copied or imported into Setup - Accounts as Motor vehicles – Net value (with the hyphenation format) it will be displayed as Motor vehicles Net value on some screens and in reports and as Motor vehicles | Net value on lookup screens.

You need to use the dash sign "-" to be displayed correctly.

Solution:

To ensure hyphens display correctly in osFinancials5/TurboCASH5, use the standard dash character ("-") instead of the hyphenation character when copying or importing text from external files.

6. Click on Save as... to save the imported transactions to an Excel Workbook.



7. Select the folder and enter a name for the file.
8. Click on the Save button.
9. Click on the Close icon in the titlebar of the "*Data Import Export*" screen.

The data of the imported accounts is imported (populated) in the following eleven (11) columns in the spreadsheet and is as follows:

		Field name	*Values*	*Comments*
	A	*SREFERENCE*	*Alpha-numeric*	*Reference entered*
	B	*SACCOUNT*	*Account code - Prefixed by:* *G = Ledger account* *D = Debtor account* *C = Creditor account* *B = Bank account*	*Selected account - Account lookup*
	C	*SDESCRIPTION*	*Description*	*Description entered for the transaction*
	D	*FAMOUNT*	*Amount*	*Amount entered - Exclusive of Tax*
	E	*STAX*	*Tax account code (should be pre-fixed by T)*	*Selected tax account - Tax lookup*

	F	DDATE	Date	Date of the transaction
	G	SCONTRAACCOUNT	Account code - Prefixed by: G = Ledger account D = Debtor account C = Creditor account B = Bank account	Account code selected / set in F10:Setup (for balancing entries)
	H	BEXCLUSIVE	0 = Inclusive 1 = Exclusive	Tax Amount entered Inclusive of Tax or Exclusive of Tax
	I	SJOBCODE	Project code	Projects (if activated and selected)
	J	SCOSTGROUP1	Cost centre 1 name	Cost centre 1 group (if activated and selected)
	K	SCOSTGROUP2	Cost centre 2 name	Cost centre 2 group (if activated and selected)

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Batch transactions - Spreadsheet Import

You may import batch transactions from a valid spreadsheet saved as a "*Excel Workbook (*.xlsx) file type* into a batch.

You may then add new transactions, edit existing transactions, etc.

To import batch transactions from a Excel Workbook (xlsx) file:

1. On the Default ribbon, select Batch entry (F2).
2. Select a blank Batch, and click Open.



3. Click on the Spreadsheet import icon.

4. The "*Data Import Export*" be launched without any data.



5. On the "*Data Import Export*" screen, click Open to select a valid saved exported file.



You may click on the "Show the preview pane" icon on the "Open" screen to display a preview of the selected file to open (import) in the "Data Import Export" screen..

6. Select the folder and file. Click on the Open button. The batch transactions included in the selected "Excel Workbook (*.xlsx) file opened will be imported and listed in the "*Data Import / Export*" screen.



Should you need to change an account (in column B - "SACCOUNT" or column E - "STAX" or column G - "SCONTRAAC option.



	A	B	C	D	E	F	G
1	SREFERENCE	SACCOUNT	SDESCRIPTION	FAMOUNT	STAX	DDATE	SCONTRAA
2	INV001	D1ABGRE	Paint - Exterior	1,000.00	T860010	2022/03/07	G010000
3	INV002	D1MACDS	Install - Built-in cupboard	1,500.00	T860010	2022/03/09	G010000
4	INV003	D1ABGRE	Paint - Exterior	1,000.00	T860010	2022/03/10	G010000
5	INV004	D1MDAVI	Install - Built-in cupboard	1,500.00	T860010	2022/03/12	G010000
6							
7							
8							
9							
10							
11							
12							

This will launch the "Select account" lookup screen.



7. You may select the following options:

   a) Show data before import - If this option is selected, the *"ImportCheck"* screen will be launched, before the import process is initialised.

   b) Import check - Click on this option to populate the values of the various columns on the Settings tab to be imported.



See - Spreadsheet export - The data of the imported accounts is imported (populated) in the following eleven (11) columns in the spreadsheet on the "Data Import Export" screen..

8. Click on the Import tab and on the Import icon. If the "*Show data before import" option is selected, the "ImportCheck" screen will be launched*:



9. The transactions that will be imported into the batch will be listed. You may edit these transactions, if necessary. Click on the All or OK button to start the import process.



	A	B	C	D	E	F	G	H	I	J	K	L
1	SREFERENCE	SACCOUNT	SDESCRIPTION	FAMOUNT	STAX	DDATE	SCONTRAACCOUNT	BEXCLUSIVE	SJOBCODE	SCOSTGROUP1	SCOSTGROUP2	
2	INV001	D1ABGRE	Paint - Exterior	1,000.00	T860010	2022/03/07	G010000	1		Empty	Empty	
3	INV002	D1MACDS	Install - Built-in cupboard	1,500.00	T860010	2022/03/09	G010000	1		Empty	Empty	
4	INV003	D1ABGRE	Paint - Exterior	1,000.00	T860010	2022/03/10	G010000	1		Empty	Empty	
5	INV004	D1MDAVI	Install - Built-in cupboard	1,500.00	T860010	2022/03/12	G010000	1		Empty	Empty	
6												
7												

10. Click on the Import icon. The colour of the cells in the rows for the transactions in the "*SREFERENCE*" column should be green. This means that the import process is finalised.

11. Click on the Close icon in the titlebar of the "*Data Import Export*" screen. The imported transactions will be listed in the "*Batch entry*" screen.



No	Reference	Date	Description	Debtors	Tax	Debit	Credit	Open item
1	INV001	2022/03/07	Paint - Exterior	D1ABGRE Mr. AB Green	T860010 Output VAT - 15%	1,150.00	0.00	
2	INV002	2022/03/09	Install - Built-in cupboard	D1MACDS MAC Shop Decor Specialists	T860010 Output VAT - 15%	1,725.00	0.00	
3	INV003	2022/03/10	Paint - Exterior	D1ABGRE Mr. AB Green	T860010 Output VAT - 15%	1,150.00	0.00	
4	INV004	2022/03/12	Install - Built-in cupboard	D1MDAVI Mr. Mike Davies	T860010 Output VAT - 15%	1,725.00	0.00	
4						5,750.00	0.00	

12. You may edit the transactions if necessary.

Once you have finished importing and/or editing the transactions in the batch you need to: -

1. *Change the Alias (Batch name).*
2. *Balance the batch.*
3. *List the batch.*
4. *Post the batch.*

Created with the Standard Edition of HelpNDoc: Free Web Help generator

Reverse posted batches

This feature allows you to cancel transactions that were processed in batches (journals) which have already been updated (posted) to the ledger. By selecting this option, all the transactions that were previously updated (posted) to the ledger will be cancelled and removed from the transaction file.

The cancelled transactions will be automatically imported to the selected batch (journal). At this point, you have the option to either erase or delete the entire batch (journal). If you wish to keep the cancelled (reversed) batch, you can edit and correct the transactions, balance the batch, print the batch list, and post it to the ledger.

The Log-report in Setup → Access control (Setup ribbon) will list the date and time, as well as which user and on which device, the batch were cancelled as REVBATC - Reverse batch! and the Batch ID.

If any transactions are already entered or imported in a batch (journal), which is not yet posted (updated) to the ledger, and all or some of the transactions are incorrect, you may use the following options to edit the transactions in the batch (journal):

- *Delete Batch - delete the entire journal as well as all the transactions entered or imported.*
- *Delete Transaction - delete only the selected transaction in the batch (journal).*
- *Reverse batch (D<-->C) - all amounts entered or imported in the debit column of the journal, will be transferred to the credit column, and all amounts entered or imported in the credit column of the journal will be transferred to the debit column.*

This option should only be used to correct critical errors. Errors encountered in the normal accounting process, (for example, errors of omission, errors of principle, posting to incorrect accounts, errors of principle, etc.) should be corrected in the general journal or specific batches (journals).

It is recommended that you make a backup of the Set of Books, before you start to use this facility to cancel or reverse a posted batch. In the event of making a mistake or if some problems are experienced, you may then easily restore the Set of Books from the backup file.

To reverse or cancel all the transactions in a posted batch (journal):

1. On the Setup ribbon, select Global processes → Reverse posted batch/document .



No document posted

- *If this field is selected, it will only list the batches processed in the Batch entry (F2) option.*
- *If this field is not selected, it will list all the batches processed in the Batch entry (F2) options well as any documents (i.e Invoices, Credit notes, Purchases and Supplier returns.*

2. Select the posted batch from the list to be reversed or cancelled.

You may identify the posted batch (journal) by Batch number as displayed on the Batch list lookup facility, alias or date and time. If you changed the alias of the batch, it will be easier to identify the batch (journal) to be reversed, or cancelled, by the alias (batch name).

3. View the details of the batch to make absolutely sure that it is the correct batch (journal).

To view the details of the transactions in the selected batch (journal), you may:-

- *Double-click on the selected batch (journal).*
- *On the Details tab, the transactions for the selected batch will be listed. (If you wish to print a list of the transactions in the posted batch, you may click on the Print button to print a Batch type - Posted batch report).*

4. If you double-click, or select the Details option on the context menu, the following screen is displayed:



Line	Reference	Date	Description	Account	Cost centre 1	Cost centre 2	Default account	Tax	Debit	Credit	Amount entry	Amount exclusive
1	INV001	2024/03/07	Paint - Exterior	D1ABGRE Mr. AB Green	Empty	No group	010-000	860-010	1,150.00	0.00	1,150.00	☑
2	INV002	2024/03/09	Install - Built-in cupboard	D1MACDS MAC Shop Decor Speci	Empty	No group	010-000	860-010	1,725.00	0.00	1,725.00	☑
3	INV003	2024/03/10	Paint - Exterior	D1ABGRE Mr. AB Green	Empty	No group	010-000	860-010	1,150.00	0.00	1,150.00	☑
4	INV004	2024/03/11	Install - Built-in cupboard	D1MDAVI Mr. Mike Davies	Empty	No group	010-000	860-010	1,725.00	0.00	1,725.00	☑
5	********	2024/03/07	Paint - Exterior	T860010 Output VAT - 15%	Empty	No group	-	-	0.00	150.00	150.00-	☑
6	********	2024/03/07	Paint - Exterior	G010000 Sales	Empty	No group	-	860-010	0.00	1,000.00	1,000.00-	☑
7	********	2024/03/09	Install - Built-in cupboard	T860010 Output VAT - 15%	Empty	No group	-	-	0.00	225.00	225.00-	☑
8	********	2024/03/09	Install - Built-in cupboard	G010000 Sales	Empty	No group	-	860-010	0.00	1,500.00	1,500.00-	☑
9	********	2024/03/10	Paint - Exterior	T860010 Output VAT - 15%	Empty	No group	-	-	0.00	150.00	150.00-	☑
10	********	2024/03/10	Paint - Exterior	G010000 Sales	Empty	No group	-	860-010	0.00	1,000.00	1,000.00-	☑
11	********	2024/03/11	Install - Built-in cupboard	T860010 Output VAT - 15%	Empty	No group	-	-	0.00	225.00	225.00-	☑
12	********	2024/03/11	Install - Built-in cupboard	G010000 Sales	Empty	No group	-	860-010	0.00	1,500.00	1,500.00-	☑
12									5750.00	5750.00	0.00	

5. All the details of the transactions entered or imported and posted (updated) to the ledger for the selected batch, will be displayed. Check that the selected batch (journal) contains the transactions which needs to be reversed or cancelled, and click on the Batch entry tab.

Fix unique id - If the batch cannot be reversed / cancelled and some error message is produced, you need to click on the Fix unique id button. It is recommended that you make a backup of the Set of Books, before you click on the Fix unique id button

You may click on the Print button to print the transactions in the batch. The batch will be removed and the "Batch ty cannot be printed for the selected batch.

Page 1 -


C:\TCASH5\plug_ins\reports\GENERAL\documents\postedbatch.rep
Batch type report - Posted batch
Batch type : Sales jnl.
Alias (batch name) : Sales2403
Batch id : 4
Batch type id : 2
Batch no. : B0000003
File name : bat0t2
2024/03/09 ******* *Install - Built-in cupboard Empty, T860-010 Output VAT - 15% - 0.00
2024/03/09 ******* *Install - Built-in cupboard Empty, G010-000 Sales 860-010 -225.00
Total
Date Reference Description Account / Contra account Tax Tax amount
2024/03/10 ******* *Paint - Exterior Empty, T860-010 Output VAT - 15% - 0.00
2024/03/10 ******* *Paint - Exterior Empty, G010-000 Sales 860-010 -150.00
Total
Date Reference Description Account / Contra account Tax Tax amount
2024/03/11 ******* *Install - Built-in cupboard Empty, T860-010 Output VAT - 15% - 0.00
2024/03/11 ******* *Install - Built-in cupboard Empty, G010-000 Sales 860-010 -225.00
Total

Page 2 -



6. Click on the Reverse posted batch button to start the process. The following information message will be displayed:

This will radically alter your data! We recommend that you stop and make a backup! Do you wish to continue?

7. Click on the Yes button, only if you are absolutely sure that the selected batch is correct, and that you need to continue with this process.

> *If you have not made a backup of the Set of Books, before starting this process, it is recommended that you click on the No button, and first make a backup of the Set of Books.*

8. Wait until the process is finalised.

> *It is advisable not to use your system for other tasks while this process is running.*

> *Once this process is finalised, the selected batch will not be listed on the Reverse posted batch screen.*

9. Click on the Close button in the title bar of the Reverse posted batch/document screen to exit (close) this facility.

10. Click on the Batch entry icon, and select the batch type, to see the transactions of the posted batch which was reversed. You may then edit these transactions, delete the transactions, etc. Once your transactions is corrected, you need to balance the batch (journal), and post (update) the transactions to the ledger.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Documents (Sales and Purchases)

In osFinancials5/TurboCASH5, the Documents feature provides a comprehensive solution for processing and managing sales documents and purchase documents related to debtor (customer/client) and creditor (supplier/vendor) accounts. It offers a range of functionalities to streamline document management and automate source document and transaction generation. Additionally, osFinancials5/TurboCASH5 supports the usage of up to two reporting groups for documents. This feature allows you to categorize and classify your documents based on different criteria or attributes that are relevant to you. This categorization and classification feature enhances your document organization capabilities, making it easier to manage and retrieve specific documents when needed. Here's an overview of the key aspects of the Documents feature:

1. Sales documents: This includes (invoices, credit notes, quotes), associated with debtor accounts. You can create, process, and manage these sales documents (invoices, credit notes, quotes) within

osFinancials5/TurboCASH5. The Documents option provides a centralized interface to handle all sales documents efficiently. Additionally, the Documents option provides a centralized interface to process sales documents (invoices, credit notes, quotes) for debtors (customers/clients).

2. Purchase documents: This comprises purchases, supplier returns, orders relevant to creditor accounts. Similarly, you can create, process, and manage these purchase documents using the Documents option. It allows for seamless handling of purchase transactions and associated records. Furthermore, the Documents option provides centralized management for purchase documents (purchases, supplier returns, orders) for creditors (suppliers/vendors).

3. Transaction generation: When you create sales documents or purchase documents, osFinancials5/TurboCASH5 automatically generates the required transactions and source documents based on the document details. This ensures accurate and consistent recording of financial transactions in your accounting system. Moreover, in addition to the normal processing options, the context menus provide quick access to process various options for easy copying, converting documents, and more to process documents.

4. Layout files: The Documents feature allows you to choose from various layout files for printing or reprinting your sales and purchase documents. You can use the Report designer to customize the appearance and format of these documents to align with your business branding or specific requirements.

5. Print and Reprint: With osFinancials5/TurboCASH5, you have the ability to print or reprint your sales and purchase documents as needed. This allows for easy distribution of invoices, credit notes, quotes, purchases, supplier returns, orders, and delivery notes relevant to your customers, suppliers, or internal stakeholders. Additionally, the powerful grid for documents contains the data for each document, allowing you to filter and search for specific documents according to the criteria you specify.

Overall, the Documents feature in osFinancials5/TurboCASH5 simplifies the management of sales documents and purchase documents. It automates transaction generation, provides options for selecting layout files, and enables printing or reprinting of these documents. By leveraging this functionality, you can streamline your document workflows, ensure accurate financial records, and effectively communicate with your customers and suppliers.

To access the Document selection screen:

On the Default ribbon, select Documents (F6).

This is the first screen displayed when you access the Documents in your Set of Books. At first, when you start a new Set of Books, and have not processed any documents, this list will be empty.



The six (6) document types are grouped as follows:

1. Sales documents -



a) Quotes - You may need to produce a Quote for your debtors (customers / clients). When the Quote is accepted, you may confirm the quote (convert the Quote to an Invoice).

b) Invoices - Invoices are created for debtors (customers / clients). This will generate a source document which can be printed. The Invoice, can be edited before it is posted (updated) to the ledger. When an Invoice is posted (updated) to the ledger, the transactions in the Sales journal will automatically be generated.

c) Credit notes - Credit notes are created for debtors (customers / clients) to correct a transaction or an exiting posted Invoice or to cancel the Invoice. This will generate a source document which can be printed. The Credit notes, can be edited before it is posted (updated) to the ledger. When a Credit note is posted (updated) to the ledger, the transactions in the

Sales journal (or Sales returns journal) will automatically be generated.

2. Purchase documents -

   a) Orders - You may need to place an Order with any of your creditors (suppliers / vendors). When the goods are received or services are provided, you may confirm the Order against the actual goods received and the original Order. You will do this by converting the Order to a Purchase document.

   b) Purchases - Purchase documents are created for creditors (suppliers / vendors). This will generate a source document which can be printed. The Purchase document, can be edited before it is posted (updated) to the ledger. When a Purchase document is posted (updated) to the ledger, the transactions in the Purchase journal will automatically be generated.

   c) Supplier returns - Supplier returns are created creditors (suppliers / vendors) to correct a transaction or an exiting posted Purchase or to cancel the Purchase. This will generate a source document which can be printed. The Supplier returns, can be edited before it is posted (updated) to the ledger. When a Supplier return is posted (updated) to the ledger, the transactions in the Purchase journal (or Purchase returns journal) will automatically be generated.

Access document types - Stand alone screens

By default, the "*Document list*" screen and the "*Document entry*" screens will be launched as a Integral part of the program. If you select a document type on the Input menu on the Default ribbon, the "*Document list*" screen and the "*Document entry*" screens, will launch the selected document type in a separate stand alone screens.



Other options to create documents

In addition to process Documents from this option, documents may be also be created from the following options on the Default ribbon:

- Documents - Various context menu options.
- Edit → Repeating invoices
- Calendar (Repeating invoices)
- Calendar (Invoices for hours)
- Calendar (Create invoice - context menu)
- Calendar (Bulk time entry)
- Input → Confirm (Quotes and Orders)

Context menu options to create documents

In addition to this, documents may also be created on quickly from the following context menus:

- Copy document - Create a copy of a selected document.
- Create purchase on default supplier 1 - Create order/s for selected invoice/s). Preferred supplier 1 must be selected for a stock item.
- Convert invoice to order - Create order/s for selected invoice/s).
- Convert to credit note / supplier return (invoice/s will be converted to credit note/s and purchase/s to supplier return/s).
- Copy to - Copy selected document/s - to invoice/s, credit note/s, quote/s, purchase/s, supplier return/s or order/s.

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Documents setup

The "*Documents setup*" option in osFinancials5/TurboCASH5 allows you to set up sales documents such as invoices, credit notes and quotes for debtors (customers / clients) as well as purchase documents such as purchases, supplier returns and orders for creditors (suppliers / vendors).

You can also enter global statement messages on the Statement setup tab to be displayed on statements for debtors (customers / clients).

Before you can start generating documents in osFinancials5/TurboCASH5, you need to set up the documents. If you have created a new Set of Books in osFinancials5/TurboCASH5, the basic settings in the documents setup will already be set up for you. However, it's recommended to review and customize each document type according to your specific needs and requirements.

By default, osFinancials5/TurboCASH5 assigns document numbers that begin with 000001 and are prefixed by 2 alphabetical characters - IN for invoices, CR for credit notes, PU for purchase documents, SR for supplier return documents, OR for orders, and QU for quotes.

However, you can change this to fit your requirements. Afterwards, osFinancials5/TurboCASH5 will automatically allocate document numbers in the numerical sequence they were generated.

If you have created multiple users in Setup → Access control (Setup ribbon), you can choose to use general numbers for users and select a default user. This will enable document numbers to be generated by each user.

If your business or organization is registered as a company, close corporation, non-profit organisation, non-governmental organisation, or any other type of organisation that requires your registration number to be displayed on all documentation in accordance with legislation, you must enter that registration number in the "Company reg. no." field of the Setup → Company info (Setup ribbon).

This should be done before processing any documents.

If you are registered as a VAT/GST/Sales Tax vendor, you must enter your Tax (VAT/GST/Sales Tax) registration number in the "Tax reg. no." field of the Setup → Company info (Setup ribbon). This should be done before processing any documents.

Before you start processing any documents in osFinancials5/TurboCASH5, it is important to check and set the document numbers, batches (journals), headings, and messages. You should also ensure that your document headings are displayed correctly in accordance with your country's tax legislation, especially if you are registered for VAT/GST/Sales Tax.

To set documents:

1. On the Setup ribbon, select Setup → Documents setup. The "*Documents setup*" screen is displayed:



2. The global settings to configure for document processing, is as follows:

   a) Layout file point-of-sale - This is the default layout file ("*POS-STARTSP100*" layout file for a till-slip printer) used in the standard point-of-sale feature (Setup → Point-of-Sale (Setup ribbon) and POS Invoice (Input → POS Invoice (Default ribbon).

   b) Print standard logo - The logo field is included in the document layout files, debtor statements and creditor remittance advices. To display the logo, you need to load the logo in the "*Company info - Options*" screen.

   c) Auto-post documents on print - By default, documents in osFinancials5/TurboCASH5 require manual updating (posting) to the ledger. However, if you choose to select the option for automatic updating (posting), the system will automatically update (post) the documents to the ledger when they are printed.

   d) Save / load layout in localfiles - This settings is optional for a network environment when the settings of the documents (layout column visible, etc.) needs to be stored at a central location.

   e) Append notes after item - By default, this option is selected. When processing documents, and a comment F9: Comment is inserted in a document, the comment is added one line below the selected stock item in the document lines.

> *By default, comments is inserted below a selected item. The option "Append notes below*

item" (Setup → Documents setup (Setup ribbon)) is added to set the preference if comments should be added before, or below (default option), a selected item when processing documents and printing comments on layout files.

The default "Append notes below item" setting is selected (ticked). It will display on document lines and document layout files as follows:

1. *Item*
2. *Remark*
3. *Comment*

If the "Append notes below item" setting is not selected. It will display on document lines and document layout files as follows:

1. *Comment*
2. *Item*
3. *Remark*

f) Next batch number - The batch numbers are are automatically generated starting from the number in this field. These batch numbers are generated for batch transactions as well as the transactions in documents posted to the ledger.

3. To check or amend the document numbers, batch types (except in the case of Orders and Quotes), select the paper type, change the headings, if necessary, and to enter the messages you wish to be displayed on the documents, you can select each of the following documents:

a) Debtor (customer / client) documents:

i) Invoices: record the sales transactions with your debtors (customers / clients) from your stock code file. Once updated (posted) to the ledger, this document will record the sales, cost of sales transactions in the general ledger and update the debtor's ledger.

ii) Credit notes: record the sales returns received from your debtors (customers / clients) from your stock code file. Once updated (posted) to the ledger, this document will reverse the entries or part of the transactions issued and posted on the Invoice.

iii) Quotes: record the promise to sell specified goods or stock items at certain prices and quantities, if the debtor (customer / client) accepts the quote within a specified period. Once a quote is accepted, it can be confirmed and converted to an Invoice. Quotes cannot be updated (posted) to the ledger.

b) Creditor (supplier / vendor) documents:

i) Purchases (Goods received notes): record all the purchase transactions with your creditors (suppliers / vendors) from your stock code file. Once updated (posted) to the ledger, this document will record the purchases in the stock ledger, the stock control account in the general ledger and the creditors account in the creditor's ledger.

ii) Supplier returns: record the purchase returns returned to your creditors (suppliers / vendors) from your stock code file. Once updated (posted) to the ledger, this document will reverse the entries or part of the transactions issued and posted on the Purchase document (Goods received note).

iii) Orders: record the stock items or goods, which are ordered from a creditor (supplier / vendor). Once an order is fulfilled, i.e. the stock items or goods are received, the order can be confirmed and converted to a Purchase document (Goods received note). Orders cannot be updated (posted) to the ledger.

4. To add or edit a global statement message that will be displayed on all debtor statements, go to the Statement setup tab. Here, you can enter up to three (3) lines of text that will appear on every debtor statement you print using the Reports → Debtors → Debtor statement feature. This is a useful way to communicate important information to your debtors, such as payment terms, contact information, or other relevant details. Once you have entered your statement messages, they will be automatically included on all debtor statements you generate going forward.

5. Click on the OK button to save your changes and close or exit this screen.

If you click on the Page setup button, the following screen will be launched:



Created with the Standard Edition of HelpNDoc: Free Kindle producer

Documents setup - Invoices

To set documents - Invoices:

1. On the Setup ribbon, select Setup → Documents setup.

2. Click on the Invoices tab.



3. Enter or select the following options:

   a) Next invoice no. - It is recommended that the Invoice number be prefixed (e.g. IN000001) to identify the document type.

   b) Invoice batch - Select the Sales Jnl.

   c) Layout file - If you have a customised layout file, you may select the layout file.

> *The universal Layout file (one file to print all document types) is by default set for all Sets of Books.*
>
> *See - Document layout files to assist you in selecting a layout files.*

> *The Layout files set in the Documents setup, is a global setting. If you need to set a different layout file for a specific debtor (customer / client), you may select it on the Delivery address tab of Debtors (Default-ribbon).*
>
> *You may also change the layout file when printing documents.*

   d) Layout file 2 - This field is optional. If a layout file is selected, the document will print twice using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files listed above.

   e) Invoice heading - This field is not used on the document layout files, but it is recommended

that Invoice or Tax Invoice should be displayed or entered.

f) Invoice message - Enter a global message to be printed on all Invoices.

4. Click on the other tabs, if necessary. Once finished, click on the OK button to save your changes.

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Documents setup - Credit notes

To set documents - Credit notes:

1. On the Setup ribbon, select Setup → Documents setup.

2. Click on the Credit notes tab.



3. Enter or select the following options:

a) Next credit note no. - It is recommended that the Credit note number be prefixed (e.g. CR000001) to identify the document type.

b) Credit note batch - Select the Sales jnl. or Sales returns jnl., if you have created such a batch type.

c) Layout file - If you have a customised layout file, you may select the layout file.

The universal Layout file (one file to print all document types) is by default set for all Sets of Books.

See - Document layout files to assist you in selecting a layout files.

The Layout files set in the Documents setup, is a global setting. If you need to set a different layout file for a specific debtor (customer / client), you may select it on the Delivery address tab of Debtors (Default-ribbon).

You may also change the layout file when printing documents.

d) Layout file 2 - This field is optional. If a layout file is selected, the document will print twice using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files listed above.

e) Credit note heading - This field is not used on the document layout files, but it is recommended that Credit note should be displayed or entered.

f) Credit note message - Enter a global message to be printed on all Credit notes.

4. Click on the other tabs, if necessary. Once finished, click on the OK button to save your changes.

Created with the Standard Edition of HelpNDoc: Transform your help documentation into a stunning website

Documents setup - Quotes

To set documents - Quotes:

1. On the Setup ribbon, select Setup → Documents setup.

2. Click on the Quotes tab.



3. Enter or select the following options:

   a) Next quote no. - It is recommended that the Quote number be prefixed (e.g. QU000001) to identify the document type.

   b) Layout file - If you have a customised layout file, you may select the layout file.

> *The universal Layout file (one file to print all document types) is by default set for all Sets of Books.*
>
> *See - Document layout files to assist you in selecting a layout files.*

> *The Layout files set in the Documents setup, is a global setting. If you need to set a different layout file for a specific debtor (customer / client), you may select it on the Delivery address tab of Debtors (Default-ribbon).*
>
> *You may also change the layout file when printing documents.*

   c) Layout file 2 - This field is optional. If a layout file is selected, the document will print twice using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files listed above.

   d) Quote heading - This field is not used on the document layout files, but it is recommended that Quote should be displayed or entered.

e) Quote message - Enter a global message to be printed on all Quotes.

4. Click on the other tabs, if necessary. Once finished, click on the OK button to save your changes.

Created with the Standard Edition of HelpNDoc: Keep Your PDFs Safe from Unauthorized Access with These Security Measures

Documents setup - Purchases

To set documents - Purchases:

1. On the Setup ribbon, select Setup → Documents setup.

2. Click on the Purchases tab.



3. Enter or select the following options:

a) Next purchase no. - It is recommended that the Purchase number be prefixed (e.g. PU000001) to identify the document type.

b) Purchase batch - Select the Purchase Jnl.

c) Layout file - If you have a customised layout file, you may select the layout file.

The universal Layout file (one file to print all document types) is by default set for all Sets of Books.

See - Document layout files to assist you in selecting a layout files.

The Layout files set in the Documents setup, is a global setting. If you need to set a different layout file for a specific creditor (supplier / vendor), you may select it on the Delivery address tab of Creditors (Default-ribbon).

You may also change the layout file when printing documents.

d) Layout file 2 - This field is optional. If a layout file is selected, the document will print twice using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files listed above.

e) Purchase heading - This field is not used on the document layout files, but it is recommended that Purchase should be displayed or entered.

f) Purchase message - Enter a global message to be printed on all Purchases.

4. Click on the other tabs, if necessary. Once finished, click on the OK button to save your changes.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Documents setup - Supplier returns

To set documents - Supplier returns:

1. On the Setup ribbon, select Setup → Documents setup.

2. Click on the Supplier returns tab.



3. Enter or select the following options:

   a) Next return no. - It is recommended that the Supplier return number be prefixed (e.g. SR000001) to identify the document type.

   b) Supplier return batch - Select the Purchase jnl or the Purchase returns jnl, if you have created such a batch type.

   c) Layout file - If you have a customised layout file, you may select the layout file.

> *The universal Layout file (one file to print all document types) is by default set for all Sets of Books.*
>
> *See - Document layout files to assist you in selecting a layout files.*

> *The Layout files set in the Documents setup, is a global setting. If you need to set a different layout file for a specific creditor (supplier / vendor), you may select it on the Delivery address tab of Creditors (Default-ribbon).*
>
> *You may also change the layout file when printing documents.*

   d) Layout file 2 - This field is optional. If a layout file is selected, the document will print twice using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files listed above.

e) Supplier return heading - This field is not used on the document layout files, but it is recommended that Supplier return should be displayed or entered.

f) Supplier return message - Enter a global message to be printed on all Supplier returns.

4. Click on the other tabs, if necessary. Once finished, click on the OK button to save your changes.

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Documents setup - Orders

To set documents - Orders:

1. On the Setup ribbon, select Setup → Documents setup.

2. Click on the Orders tab.



3. Enter or select the following options:

a) Next order no. - It is recommended that the Order number be prefixed (e.g. OR000001) to identify the document type.

b) Layout file - If you have a customised layout file, you may select the layout file.

The universal Layout file (one file to print all document types) is by default set for all Sets of Books.

See - Document layout files to assist you in selecting a layout files.

The Layout files set in the Documents setup, is a global setting. If you need to set a different layout file for a specific creditor (supplier / vendor), you may select it on the Delivery address tab of Creditors (Default-ribbon).

You may also change the layout file when printing documents.

c) Layout file 2 - This field is optional. If a layout file is selected, the document will print twice using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files listed above.

d) Order heading - This field is not used on the document layout files, but it is recommended that Order should be displayed or entered.

e) Order message - Enter a global message to be printed on all Orders.

4. Click on the other tabs, if necessary. Once finished, click on the OK button to save your changes.

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Documents setup - Change document numbers

Each transaction should have a unique document number, which helps to identify the source document for that transaction. Document numbers are important as they are displayed in reports and screens in osFinancials5/TurboCASH5. The default document numbers are eight character alphanumeric numbers, but these can be changed to suit your own numbering system.

The default document numbers in most Sets of Books (templates) are set to start with:-

- Invoices - IN000001
- Credit notes - CR00001
- Quotes - QU00001
- Purchases - PU00001

- Supplier returns - SR00001
- Orders - OR00001

It is important to note that document numbers should only be changed before processing any documents, and each source document containing details of a transaction should be numbered with a unique alphanumeric identifier consisting of eight characters.

To change document numbers:

1. Go to the Setup ribbon and select Setup → Documents setup.
2. Select the Document type (Invoices, Credit notes, Purchases, Supplier returns, Orders and/or Quotes) and over type the displayed number with your own number. A confirmation message will be displayed.

   "Are you sure you want to change the next document number?Invoice no." (Where Invoice no. is the selected Document tab (document type) description).

3. Click on the Yes button, and the Next document number for the selected document will be changed. Should you click on the No button, the document number will not be changed.
4. Repeat this process for all your document numbers. Once you have changed all your other document numbers and/or settings, click on the Close button, or press the Esc key on your keyboard, to exit this screen.

You may use any combination of letters and/or numbers for your document numbers. As osFinancials5/TurboCASH5 will increment the document number from the last character (letter or number), it is recommended that the following format for your document numbers be used:

- *Use all eight characters of the document number. If you only use for example 3 or 4 numerical characters for your documents you may find that the document numbers may be repeated in an accounting period or financial year.*
- *Assign unique two or three unique alphabetical-character prefixes to each document. For example, Invoices could be ''IN'', Credit notes ''CN'', Quotes "QU", Purchase "PU", Supplier returns "SR" and Orders "OR".*
- *Enter numeric characters for the rest of the document number. For example, if your last invoice number on your previous accounting system was 56 enter the last invoice number as IN000056. osFinancials5/TurboCASH5 will automatically generate the next invoice number as IN000057 when you generate your first Invoice.*

By prefixing document numbers with specific codes, it helps to avoid any overlap of numbers and confusion with other transactions in the Set of Books. This practice also aids in easy identification of the document type and tracing, tracking and grouping them through reports, screens, pivot tables, spreadsheets, and more. Additionally, using prefixes for document numbers, can assist in identifying the transaction type, for example if it is a sales or a purchase transaction.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's Project Analyzer

Documents setup - Statement setup

The Statement setup tab allows you to add or edit a global statement message that will be displayed on all debtor statements. Here, you can enter up to three (3) lines of text that will appear on every debtor statement you print using the Reports → Debtors → Debtor statement feature. This is a useful way to communicate important information to your debtors, such as payment terms, contact information, or other relevant details. Once you have entered your statement messages, they will be automatically included on all debtor statements you generate going forward.

Enter global messages to display on all debtor statements:

1. On the Setup ribbon, select Setup → Documents setup.
2. Select the Statement setup tab.



3. Enter the message in up to 3 lines to display on the Debtor statements.

4. Click on the OK button.

Enter statement messages for specific debtor accounts:

1. On the Default ribbon, select Debtors (F4).

2. Select the debtor (customer / client) account.

3. On the Delivery address tab, enter a message of up to 3 lines.

4. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Documents setup - General numbers

The "*General numbers*" option will only be available and displayed in a multi-user environment. Once users have been set up, in Setup → Access control (Setup ribbon). the "*General numbers*" option can be assigned specific users.

To set the General numbers:

1. Once users are add in Setup → Access control (Setup ribbon), select Setup → Documents setup on the Setup ribbon.



2. Select (tick) the "*General numbers*" option. A list of the users will be displayed. Select the user from the drop-down list; which osFinancials5/TurboCASH5 will use to generate document numbers.

3. Click OK.

If the "General numbers" field is not selected (ticked), osFinancials5/TurboCASH5 will generate the document numbers numerically.

You may also select the user from the "Doc no" field on the Documents tab in Setup → Access control (Setup ribbon).



Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Documents setup - Change document type names

Internal Translatable Language Labels for Document Layout Files

These language labels serve as a reference point within the osFinancials5/TurboCASH5 language files, so that you can easily identify and work with the different document layout files. Using these language labels, you can customize or modify the names or descriptions of document layout files for your specific language

file. These names or descriptions of the translatable document layout files will be displayed when you need to select a document layout file to print your documents.

Feel free to use a copy of the documents in the Report designer to serve as a base template when creating your own custom translatable document layout file that aligns with your branding and communication needs.

For your convenience the internal translatable language labels for the document layout files is as follows:

TAX (VAT/GST/Sales tax)		*NO TAX - If not registered for TAX (VAT/GST/Sales tax)*	
Language LabelID	*Layout file name*	*Language LabelID*	*Layout file name*
TRN_1910	*Layout file*	*TRN_906589*	*NO-TAX Layout file*
TRN_3174	*Document layout*	*TRN_906590*	*NO-TAX Document layout*
TRN_906277	*Document layout (15-code)*	*TRN_906591*	*NO-TAX Document layout (15-code)*

These document layout files prints the document type " *Invoice*," "*Credit note*," "*Quote*," "*Purchase*," "*Supplier return*," or "*Order*", based on the specific type of document being processed and printed.

Customised Tax Terminology in Document Layout File Names:

The filenames assigned to these document layout files are initially based on the "*English*" language file and prominently include the term "*Tax*". However, the beauty of osFinancials5/TurboCASH5 lies in its adaptability to various regions and jurisdictions, accommodating diverse tax naming conventions.

Depending on your chosen language setting or the language associated with your Set of Books, the tax terminology within these filenames can be tailored to accurately reflect the tax applicable in your specific country or jurisdiction. For instance:

- South Africa and the UK: In Sets of Books for these regions, the tax-related expressions and translatable labels will seamlessly incorporate "*VAT*" as the tax term.
- Australia and New Zealand: For Sets of Books operating in these countries, the tax-related expressions and translatable labels will use "*GST*" to align with the prevailing tax structure.
- United States: In the context of the US, the tax-related expressions and translatable labels will appropriately adopt "*Sales tax*" terminology.

By embracing this customization, osFinancials5/TurboCASH5 ensures that your document layout files not

only conform to the legal and linguistic nuances of your region but also facilitate a smoother user experience. This adaptability underscores the global applicability of osFinancials5/TurboCASH5 in serving businesses across different geographies and tax frameworks.

Changing Document Type Names for Universal Translatable Document Layout Files

In osFinancials5/TurboCASH5, translatable document layout files offer a dynamic way to seamlessly adapt document type names such as "*Invoice*," "*Credit note*," "*Quote*," "*Purchase*," "*Supplier return*," or "*Order*", based based on the specific document being printed. This dynamic capability is driven by expressions sourced from the *"TYPES.SDESCRIPTION"* field within the document layout.

To customize and modify these document type names, follow the outlined steps below:

1. Leveraging Translatable Expressions in Layout Files: The *"Layout file", "Document layout",* and "*Document layout (15 code)" document* layout files harness the power of translatable expressions, facilitated by language files and settings within osFinancials5/TurboCASH5. These layout files adeptly pull data from various fields entered during document processing, establishing connections to database tables and expressions for precise data presentation.
2. NO-TAX Layout Files and Tax Exclusions: Similarly, the *"NO-TAX Layout file," "NO-TAX Document layout," and "NO-TAX Document layout (15 code)"* layout files also make use of translatable expressions, leveraging language files and settings within osFinancials5/TurboCASH5. These files mirror the functionality of their tax-inclusive counterparts but are tailored for scenarios where Tax (VAT/GST/Sales Tax) is not applicable. Notably, these "NO-TAX" layout files exclude any Tax (VAT/GST/Sales Tax) expressions in their translatable components, catering to Set of Books instances where tax provisions do not apply.

To begin the process of modifying document type names for Translatable Document layout files, navigate to the Types tab within the "*Customize Languages*" screen. This screen is accessible through the Tools → Customise language menu on the Setup ribbon. Follow the steps outlined in the subsequent sections to tailor the document type names according to your specific business requirements.

Procedure to Modify Document Type Names

To tailor document type names according to your business requirements, follow these steps:

1. On the Setup ribbon, select the Tools → Customise language menu.
2. On the "*Customize Languages*" screen click on the Types tab.
3. On the Types tab. locate the document names you wish to modify, such as "*Invoice*," "*Credit note*,"

"*Quote*," "*Purchase*," "*Supplier return*," or "*Order*". These will be listed among other entries on the Types tab. For each document type, click on the name and replace it with your desired modification.

For example, you could change "*Invoice*" to "*Tax Invoice*" (or if "*Tax Invoice*" is listed, you could change this to "*Invoice*". Similarly you could change the document type names of the other document names, to suit your specific requirements.



4. Click on any other item on the Types tab to focus out of the edited item. and click on the Close button on the "*Customize Languages*" screen.

5. To see the updated document type names in effect, either go to the Tools → Close active forms (Setup ribbon) or close and reopen the Set of Books.

6. Impact of Modified Document Type Names: The modified document type names will have a cascading impact:

    - Dynamic Printing: When using translatable document layout files, the modified document type names will dynamically display the appropriate name on invoices, credit notes, quotes, purchases, supplier returns, or orders based on the specific document type being printed.
    - User Interface Update: The altered document type names will also reflect in the osFinancials5/TurboCASH5interface of your Set of Books. This is noticeable when selecting document types for processing or copying documents.

By customizing the document type names, you tailor osFinancials to better match your business terminology and preferences, improving clarity and consistency throughout your financial processes.

Tax Invoice or Invoice document layout files for Point-of-Sales invoices

For translatable Point-of-Sales invoices, osFinancials5/TurboCASH5 offers the following document layout files are available for Point-of-Sales invoices:

1. POS-STARTSP100 - (TRN_906183) - This layout file is designed for Till slip printers.
2. POS 1 - (TRN_906184)
3. POS 2 - (TRN_906185)

To further customize the Point-of-Sales invoice experience, you have the flexibility to modify the names associated with POS Invoices. By using the Tools → Customise language menu accessible from the Setup ribbon, you can alter the following translation labels:

1. 1270 - POS Invoice
2. 906104 - POS Tax Invoice

Other Document-name expressions that support Debtors / Creditors language preferences

The names of the document types are included as a translatable expression in the document layout files.

- Delivery note: CUSTOM('GETTEXTLANG',1313,'DeliveryNote',ACCOUNTINFO.SLANGUAGE,0,0)
- POS 2: CUSTOM('GETTEXTLANG',906014,'POSTaxInvoice',DEBTORINFO.SLANGUAGE,0,0)+': '
- POS - STARTSP100: CUSTOM('GETTEXTLANG',906014,'POSInvoice',ACCOUNTINFO.SLANGUAGE,0,0)

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Documents setup - POS layout

Changing the Layout File for Point-of-Sale (POS) Documents

The default setting in the "*Point-of-sale layout file*" field on the "*Documents setup*" screen is "*POS - STARTSP100*," a till slip document layout file. To select a different layout file from the default document layout files included in the osFinancials5/TurboCASH5 installation or your own if you have created one, the

document layout will be printed in that format.

When you alter the default Point-of-Sale (POS) layout file (or any other selected layout file), the changes will also impact documents generated with specific prefixes in various scenarios:

- *D - Project Quotes: These documents are automatically created with a 7-digit format, starting with "D" followed by 6 numeric digits.*
- *ST - Stock adjustments: Generated when stock quantities are modified within the Input → Adjust stock menu on the Default ribbon, these documents are prefixed with "ST," for example, "ST00001." Notably, the document number consists of 7 digits, including 4 zeros instead of 5.*
- *SA - BOM (Production) stock item type: Document numbers with the "SA" prefix, such as "SA00001," are generated for BOM (Production) stock items when they are Assembled or Disassembled. Similar to stock adjustments, the document number follows a 7-digit format with 4 zeros.*

Available document layout files for Point-of-Sales invoices

The following document layout files are available for Point-of-Sales invoices:

1. POS-STARTSP100 - (TRN_906183) - Prints on Till slip printers.
2. POS 1 - (TRN_906184)
3. POS 2 - (TRN_906185)

Options to select a point-of-sale document layout file

To configure the layout files for point-of-sale documents, you can choose from the following options:

1. Documents setup - Setup menu on the Setup ribbon.



2. Point-of-Sale - Printer tab - Setup menu on the Setup ribbon.



On whichever option you choose, the layout file will be updated in both screens

---

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

Documents settings - Check list

The setup of documents in osFinancials5/TurboCASH5 is a one-time process that involves several steps:

1. Check the document numbers, messages, and set layout files on the Setup → Documents setup menu of the Setup ribbon.
2. Select the "*Append notes below item*" option (default setting) or choose to add comments before a selected item on documents and layout files.

By default, comments is inserted below a selected item. The option "Append notes below item" (Setup → Documents setup (Setup ribbon)) is added to set the preference if comments should be added before, or below (default option), a selected item when processing documents and printing comments on layout files.

The default "Append notes below item" setting is selected (ticked). It will display on document lines and document layout files as follows:

1. *Item*
2. *Remark*
3. *Comment*

If the "Append notes below item" setting is not selected. It will display on document lines and document layout files as follows:

1. *Comment*
2. *Item*
3. *Remark*

3. Add the Cost of sales reporting group under Account group 1 (Reporting group 1) on the Setup → Groups menu of the Setup ribbon. Also, add reporting groups 1 and 2 for Document groups and reporting groups 1 and 2 for Stock groups, where applicable.
4. Add Salespersons on the Setup → Salesperson menu of the Setup ribbon.
5. Add a Cost of sales batch (journal) on the Setup → Batch types menu of the Setup ribbon (only to be used with Cost of sales settings for the "*Default*" stock item type).
6. Set up unit prices, selling price descriptions, and default selling price on the Setup → Stock information menu of the Setup ribbon.
7. Create a Cost of sales account for Trading stock on the Setup → Accounts menu of the Setup ribbon.
8. Create a Sundry Supplier account under the Creditors section on the Default ribbon.
9. Create a Cash Customer and linking debtors to a Salesperson under the Debtors section on the Default ribbon.

By completing these steps, you will have all the necessary settings in place to efficiently manage and process documents in osFinancials5/TurboCASH5.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Steps - Document processing

Once documents are set up and configured in osFinancials5/TurboCASH5, creating new documents is a simple process that involves the following steps:

1. Access Documents from the Default ribbon and the document type (e.g. invoices, credit notes, quotes, purchases, supplier returns or orders) .
2. Click on the New button.
3. Select the appropriate debtor or creditor account.
4. The document entry screen for the selected document type and debtor/creditor will be displayed, showing all relevant details that were entered and set up in the debtor/creditor account and any messages or document setup.
5. Select the stock code for the stock items (products) being added to the document. The default selling price or purchase price will be displayed, and you can enter the quantity (if the default quantity of 1 is not applicable).

   You may add Comments and remarks to selected items (products).
6. Click on the OK button to finalise the document and print it (e.g. as an invoice).
7. Post the document to the ledger to complete the process.

Overall, this process is designed to be easy and intuitive, allowing for quick creation of documents and efficient management of financial transactions.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Salespersons

This option allows you to add / delete the salespersons, who sell your stock items or services. Salespersons may be selected on sales documents (quotes, invoices point-of-sales access and credit notes).

The Salespersons are also added to the purchase documents (orders, purchases and supplier returns). This feature is useful to manage a user / salesperson / cashier who have processed a specific purchase document.

You may select the default salesperson for each debtor (customer / client) account. When sales documents are generated and the debtor (customer / client) account is selected, the default salesperson will be displayed for the document or you may select any available salesperson.

This feature makes it easy to see who made the most sales or did not make target. It is also a useful tool if it is necessary to pay commission on those sales.

Salespersons may also be selected for purchase documents (i.e. Purchases, Supplier returns and Orders). This allows you to see who handled the purchase document.

You may also link the salespersons (cashiers) to users on the Setup → Access control - Others tab (Setup ribbon) for improved Point-of-Sale access and security.

To add Salespersons:

Salespersons may also be added or deleted in Setup → Groups - Salespersons) (Setup ribbon).

1. On the Setup ribbon, select Setup → Salesperson. The "*Salesperson*" screen is displayed:



2. Click on the Add button. A new record will be inserted "*Change name*"

3. Overtype this with the name of your salesperson. Repeat this process for all your salespersons.

4. Click on the Close button.

To delete Salespersons:

1. On the Setup ribbon, select Setup → Salesperson.

2. Select the Salesperson and click on the Delete button. A confirmation message is displayed.

Do you want to delete the salesperson?: Name

3. Make absolutely sure that the correct salesperson is selected.
4. Click on the Yes button to delete the salesperson.
5. Click on the Close button.

To print a list of the salespersons:

1. *Go to Setup → Groups (Setup ribbon).*
2. *On the Salespersons group, click on the Print button.*

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Document groups

You can set up to two (2) reporting groups for your documents, which can categorise them based on their types, such as invoices, credit notes, quotes, purchases, supplier returns, and orders. These document groups can be linked to each document for further reporting and analysis.

These Document groups can be linked to each document.

- *You may use the context menu option on the documents grid to set or change the reporting groups for Document group 1 and/or Document group 2 for selected document(s).*
- *You may use the documents grid to filter, search or group documents.*
- *You may print Sales analysis reports for Document group 1 or Document group 2.*

Examples of reporting groups for sales documents

Some examples of reporting groups for sales documents (quotes, invoices and credit notes:

1. Sales regions: You can use reporting groups to categorize sales documents based on different sales regions. For example, you can create reporting groups for regions such as North America, Europe, Asia-Pacific, etc. This allows you to analyse and compare sales performance across different regions.
2. Sales representatives: Reporting groups can also be used to track sales documents by sales representatives or sales teams. Each sales representative can be assigned to a specific reporting

group, enabling you to evaluate individual sales performance or team performance.

3. Product categories: Another way to utilize reporting groups is by grouping sales documents based on product categories. You can create reporting groups for categories like electronics, apparel, furniture, etc. This helps in analysing sales patterns and identifying the performance of different product categories.

4. Customer types: Reporting groups can be used to differentiate sales documents based on customer types. For instance, you can create reporting groups for retail customers, wholesale customers, corporate clients, etc. This allows you to assess sales trends and profitability based on customer segments.

5. Sales channels: If your business operates through multiple sales channels, reporting groups can help classify sales documents accordingly. You can create reporting groups for channels like online sales, retail stores, distribution partners, etc. This enables you to monitor and compare sales performance across different channels.

These are just a few examples of how you can utilize reporting groups for sales documents in osFinancials5/TurboCASH5. By assigning documents to appropriate reporting groups, you can gain insights into various aspects of your sales operations and make informed business decisions.

Examples of reporting groups for purchase documents

Some examples of reporting groups for purchase documents (orders, purchases, and supplier returns):

1. Supplier categories: You can create reporting groups based on the categories or types of suppliers. For example, you can have reporting groups for raw material suppliers, equipment suppliers, or service providers. This helps in analysing and comparing the purchasing activities and performance for different supplier categories.

2. Product categories: Another option is to group purchase documents based on the product categories or types. You can create reporting groups for specific product lines or categories, such as electronics, office supplies, or machinery. This allows you to track the purchasing patterns and expenses associated with each product category.

3. Approval levels: If your organization follows an approval hierarchy for purchase documents, you can create reporting groups based on different approval levels. For example, you can have reporting groups for purchases approved by managers, directors, or executives. This helps in monitoring the approval process and identifying bottlenecks or delays in purchasing activities.

4. Purchase regions: If your organization operates in multiple regions or countries, you can assign purchase documents to reporting groups based on the regions or countries of the suppliers. This allows you to analyse and compare the purchasing activities and expenses across different regions.

These examples demonstrate how reporting groups for purchase documents in osFinancials5/TurboCASH5 can be used to categorize and analyse purchasing data. By assigning purchase documents to appropriate groups, you can track expenses, monitor supplier performance, and make informed decisions regarding purchasing strategies and cost management.

Define reporting groups

To set reporting groups for Documents:

1. On the Setup ribbon, select Setup → Groups. The "*Groups (Account group 1)"* default screen will be displayed.

2. Click on the Document group 1 button.



3. If you wish to rename the Reporting group name - Document group 1, over-type the description with your new description. This will change the description of the button for Document group 1.

4. To add a new Group to the root directory or list, select the "*REPORTING GROUP ROOT*" on the list and click on the New button.

5. Enter the name of your Document group 1 and click on "*REPORTING GROUP ROOT*" on the list.

> *Adding sub groups for document groups*
>
> *Select a Document group, for example; "Document group 1B" and click on the New button. Enter the name of your sub group.*

6. Repeat the process until you have entered all the Document groups, etc.

7. If you need to add Reporting group 2 for Documents, click on the Document group 2 button and repeat the process as for Document group 1.

8. Click on the OK button to save your changes and close (exit) this screen.

Changing the sequence of groups for document groups

Select a Document group, for example; "Document group 1B" and click on the Move up or Move down button. This will list the stock group according to your preferred sequence.

You may click on the Print button to print a list of your document groups.

You may set colours to display on the Documents grid screen. To do this, click on the Back colour button to set the rows background colour and the Font colour button to set the Font colour.

To retain and save the selected colors, you also need to set both the "Back color" and the "Font color".

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Documents list screen

This is the first screen displayed when you access the Documents in your Set of Books. At first, when you start a new Set of Books, and have not processed any documents, this list will be empty.

To access the Document selection screen:

1. On the Default ribbon, select Documents (F6).

You may also click on the Input menu (Default ribbon) to select a specific sales document (Invoices, Credit notes or Quotes) or Purchase documents (Purchases or Orders) or the Point-of-Sale Invoice option.



> *The Background colour and the Font colour may be set for each Document group 1 (in Setup → Groups).*

2. Document type - Select one of the six (6) document types (i.e. Invoices (default), Credit notes, Quotes, Purchases, Supplier returns or Orders) if the correct one is not displayed.

3. Search and filter options - Search by – Once you have selected a document type, you may filter and search by columns and/or document status (posted, unposted and/or all). You may also filter documents by Document group 1. In addition to this, you may configure the grid to show / hide columns or to group columns, etc.

> *If you click on the Show All Items list, it will list all Document group 1 items (inSetup → Groups (Document groups 1)). You may select any of the available groups from the list and click on the Filter button. Only those documents matching the selected Document group 1, will be listed.*

4. Buttons - By default the following buttons are available:

   a) New - create a new document for the selected document type.

   b) Edit - Edit or change a selected document from the list.

c) Print - Print a selected document.

> *If you activate (tick) the Document Posting option on the Setup → Access control (Documents tab), it will add the following two (2) buttons underneath the Print button:*
>
> - *Posting - This will allow you to launch the Update ledger screen to post Invoices to the ledger. If Quotes or Orders is selected, the button's caption will change to Confirmation.*
> - *Delete - This will allow you to delete an unposted document.*

5. Layout file – Default is displayed. The global settings for layout files are done by selecting a Layout file for each document type on Setup → Documents setup (Setup ribbon).

> *Specific Layout files may also be selected for:*
>
> - *Each debtor (customer / client) account by selecting a different layout file in the Layout file 1 (Invoices), Layout file 2 (Credit notes), Layout file 3 (Quotes) in Debtors (Default ribbon).*
> - *Each creditor (supplier / vendor) account by selecting a different layout file in the Layout file 1 (Purchases), Layout file 2 (Supplier return), Layout file 3 (Orders) in Creditors (Default ribbon).*
>
> *The global settings for the document layout files as selected in Setup → Documents setup (Setup ribbon) will be over-ruled.*

6. Layout file 2 – This field is optional. If a layout file is selected, the document will print twice using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files as selected for Layout file (1).

> *If you need to print Delivery notes, you may you may select the Delivery note layout file.*

7. Layout file 3 – This field is optional. If a layout file is selected, the document will print a third time using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files as selected for Layout file (1).

8. Layout file 4 – This field is optional. If a layout file is selected, the document will print a fourth time using this layout file. If you have a customised layout file, you may select the layout file. Otherwise, you may select one of the layout files as selected for Layout file (1).

9. Send report to – Select - Screen, Printer, File, E-mail or Fax.

10. Printer setup – The printer settings may be set in Printer on Reports or Setup ribbons. You may click on the Page button to set the page and printer options.

> *If you have selected (ticked) the "Use Multiple Printers" field, you may click on the Page button of the "Printer settings" screen to select the any available printer (properly configured on your system) for the First printer, Second printer, Barcode printer and/or Label printer. You may also set the page and printer options for each of these, if necessary.*

11. Export - Export the view of your document data as displayed in the list of list of documents for the selected document type. Only those records matching your sort, search and filter options will be exported.

12. Single line mode - By default, this option is selected (ticked). The details for each of the documents in the list will display in a single line. If you do not select this option (remove the tick), a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns will be grouped.

13. Save grid layout - Once you have used the filter and sort options (column sequences, etc.), you need to click on this button to save the grid layout. If you Exit osFinancials5/TurboCASH5, and reopen the Set of Books, the grid layout may return to its old values id you do not save the grid layout.

> *To display this button, you may need to hide the ribbons (double-click on any of the ribbon tabs (i.e. Start, Default, Reports, Setup or User tab).*

14. Graph - Displays the documents in a graph.

> *You may use the filter options to display a graph that matches your filter criteria only.*

15. Grid totals - This will display the line count (number of records in rows / documents) that is available on the list. The number of records will indicate the number of records that matches your filter / search criteria. It will also display the totals of the amount columns.

Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

Document types

By default, the Document list screen and the Document entry screens will be launched as a Integral part of

the program. If you access the document types from the following options, it will be launched as separate screens:

1. Documents icon on the Default ribbon and select the document type.
2. Input menu on the Default ribbon. This will launch the selected document type as a separate screens.

Other options to create documents

In addition to process Documents from this option, documents may be also be created from the following options on the Default ribbon:

- Documents - Various context menu options.
- Edit → Repeating invoices
- Calendar (Repeating invoices)
- Calendar (Invoices for hours)
- Calendar (Create invoice - context menu)
- Calendar (Bulk time entry)
- Input → Confirm (Quotes and Orders)

Context menu options to create documents

In addition to this, documents may also be created on quickly from the following context menus:

- Copy document - Create a copy of a selected document.
- Create purchase on default supplier 1 - Create order/s for selected invoice/s). Preferred supplier 1 must be selected for a stock item.
- Convert invoice to order - Create order/s for selected invoice/s).
- Convert to credit note / supplier return (invoice/s will be converted to credit note/s and purchase/s to supplier return/s).
- Copy to - Copy selected document/s - to invoice/s, credit note/s, quote/s, purchase/s, supplier return/s or order/s.

Access document types

The six (6) document types are grouped as follows:

1. Sales documents -



   a) Quotes - You may need to produce a Quote for your debtors (customers / clients). When the Quote is accepted, you may confirm the quote (convert the Quote to an Invoice).

   b) Invoices - Invoices are created for debtors (customers / clients). This will generate a source document which can be printed. The Invoice, can be edited before it is posted (updated) to the ledger. When an Invoice is posted (updated) to the ledger, the transactions in the Sales journal will automatically be generated.

   c) Credit notes - Credit notes are created for debtors (customers / clients) to correct a transaction or an exiting posted Invoice or to cancel the Invoice. This will generate a source document which can be printed. The Credit notes, can be edited before it is posted (updated) to the ledger. When a Credit note is posted (updated) to the ledger, the transactions in the Sales journal (or Sales returns journal) will automatically be generated.

2. Purchase documents -

   a) Orders - You may need to place an Order with any of your creditors (suppliers / vendors). When the goods are received or services are provided, you may confirm the Order against the actual goods received and the original Order. You will do this by converting the Order to a Purchase document.

   b) Purchases - Purchase documents are created for creditors (suppliers / vendors). This will generate a source document which can be printed. The Purchase document, can be edited before it is posted (updated) to the ledger. When a Purchase document is posted (updated) to the ledger, the transactions in the Purchase journal will automatically be generated.

   c) Supplier returns - Supplier returns are created creditors (suppliers / vendors) to correct a transaction or an exiting posted Purchase or to cancel the Purchase. This will generate a source document which can be printed. The Supplier returns, can be edited before it is posted (updated) to the ledger. When a Supplier return is posted (updated) to the ledger, the transactions in the Purchase journal (or Purchase returns journal) will automatically be

generated.

Access document types - Stand alone screens

You may select a document type on the Input menu on the Default ribbon. This will launch the selected document type in a separate stand alone screens.



The "*Document entry*" screen, listing the Invoices, is displayed if the Input → Invoices menu is selected, from the Default ribbon.



Unposted document

If an unposted document (Invoice) is selected, the "*Document entry*" form for the selected unposted document (Invoice) will be displayed as a separate screen:



Posted document

If an posted document (Invoice) is selected, the "*Document entry*" form for the selected posted document (Invoice) will be displayed as a separate screen:



Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Document status

The Document list screen can be filtered by the document status for existing Invoices, Credit notes, Purchases or Supplier returns, Orders and Quotes, as follows:



1. Unposted documents - This is the default option on the Document list screen. Any document (Invoice, Credit note, Quote, Purchase, Supplier returns or Orders) may be edited, if it is not yet updated or posted to the ledger.
2. Posted documents - If you select this option on the Document list screen, you may view the documents as they were originally processed in the Document entry screen before these documents were updated (posted) to the ledger. You will not be allowed to edited posted documents.

> *The reason for this is, that quotes and orders cannot be posted (updated) to the ledger. Quotes need to be converted to Invoices and Orders need to be converted to a Purchase documents. Once a*

Quote or Order is confirmed, the Status will change to "Posted".

3. Confirmed - The status for Quotes and Orders will may be filtered as Confirmed, Posted or Open, Document list screen. In the Document entry header of Quotes and Orders, the "*Status*" may also be changed.



When a Quote or Order is created, the Status is set as "*Open*". Once a Quote or Order is confirmed, the Status will change to "*Posted*". You may change it to "*Confirmed*" when editing the Quote or Order.

You may set the status of unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns) from "Open (Unposted)" to "Confirmed".

To do this, select the document(s), right-click and select Documents → Confirm on the context menu.

Once unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns) is posted (updated to the ledger), these "Confirmed" documents will change to "Posted".

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Filter options (Documents)

The osFinancials5/TurboCASH5 grid has a powerful and user-friendly filtering and sorting system that makes it quicker and easier than other methods. With just a few mouse clicks, you can group, sort, and filter any column(s) of data on most screens in a Set of Books. This feature is very useful and efficient for managing and analysing data.

Column headings

All the data for each of your sales documents and purchase documents are listed in thirty-six (36) columns. To view change the sequence in which the data is displayed, you may:

- Scroll bars - Scroll to the right or to the left on the horizontal scroll bar to view the information.
- Sequence of rows - Click on any of the column headings to change the sorting sequence of the

documents listed in the descending or ascending sequence.

- Sequence of columns - Click on a column heading and drag it to the right or to the left to change the sequence in which the columns need to be displayed.



id	Document no.	Date	Description	Due date	Period	Printed	Amount incl.	Tax amount	Reference	Document group 1	Document group 2	Salesperson	Account no.	Amount excl.
72	IN000022		Mr. AB Green		54	2	5,750.00	750.00	C-103					5,000.00
67	IN000021	2021/06/30	Mr. AB Green	2021/07/30	54	1	5,750.00	750.00	C-103	Document group 1B		Russell	D1ABGRE	5,000.00
56	IN000020		Mr. AB Green		54	2	5,750.00	750.00	A-103-2					5,000.00
55	IN000019		Mr. AB Green		54		5,750.00	750.00	D-101	Document group 1A		Tracy		5,000.00
54	IN000018	2021/06/24	Mr. Roger Smith	2021/07/24	28		2,300.00	300.00	D-102				D1RGGSM	2,000.00
53	IN000017	2021/06/20	Mr. Mike Davies	2021/07/20	27		2,875.00	375.00	C-103			Russell	D1MDAVI	2,500.00
52	IN000016	2021/06/17	Mr. Roger Smith	2021/07/17	28		3,450.00	450.00	C-102				D1RGGSM	3,000.00
51	IN000015	2021/06/15	Mr. Mike Davies	2021/07/15	27	0	1,150.00	150.00	D-101	Document group 1B		Tracy	D1MDAVI	1,000.00

You may drag and drop any of the columns on the left band to the right band and the columns from the right band to the left band, to customise the grid for your requirements.

If you wish to retain your layout, click on the Save grid layout button.

Search by options

You may use the filter options to find a specific document, or all documents with the same values, in any of the thirty-six (36) columns. These columns are as follows:

Default	*Sorted (selected) - Alphabetical list*



To search for specific documents:

1. The filter options will display only those documents in your search or filter criteria. To do this, you may:



   a) Search by - The default option is none. It will list all the column headings. You may select any of these as an option.

   b) Like - Operator to find all documents with the same value, values greater than, smaller than, greater than or equal to, smaller than or equal to the values you have selected, or wish to enter.

   c) Value - Enter the value for the field type you have selected, for example, Postal code (if you have selected "*Postal code*" as the "*Search by*" option).



2. Once you have selected or specified the search criteria, click on the Filter button. Only those documents as in your search or filter criteria or options will be listed.

3. If you need to clear your filter options and values, click on the Clear button. You may also click on any of the column headings to change the sorting sequence of the debtor (customer / client) accounts listed.

The "Line count" will show the number of records (documents) that matches your search or filter criteria.

You may also search for documents in the "Investigator" screen (Search (Setup ribbon)).

Filter by Document group

When processing documents, you may select up two (2) reporting groups for documents, if document groups are added in the Groups - Documents (Setup menu on the Setup ribbon).

You may select any available Document reporting group 1 to list only those documents linked to selected Document group 1.

To filter for specific documents for a document group:

1. The default is "*Empty*". Select a document group 1 (e.g. Document group 1B, as in this example). Click

on the Filter button. Only those documents linked to the selected document group will be listed.



2. To clear your selection, Select "*Show all items*" and click on the Filter button.

You may change the Document groups - Reporting group1 on the context menu of the Document list screen.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Output with HelpNDoc's Advanced Project Analyzer

Single line mode

By default, the "*Single line mode*" option is selected (ticked). The details for each of the documents in the list will display in a single line.

If you do not select this option (remove the tick), a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns will be grouped.

Single line mode selected

The details for each of the documents in the list will display in a single line.



Single line mode not selected

If the "*Single line mode*" option is not selected a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns will be grouped.



All similar data in columns will be displayed once, e.g. Dates, Document groups, Salespersons, etc.

If you wish to retain your layout, click on the Save grid layout button.

Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-Use Tool

Show / Hide columns

By default, all thirty-four (36) columns will be displayed and listed in the Document entry list screen for each document type.

The columns is grouped in to two (2) bands:

You may use the filter options to find a specific document, or all documents with the same values, in any of the thirty-six (36) columns. These columns are as follows:

1. Left band - Lists the first four (4) columns, i.e., id (document id), Document number, Date of document, and Account description.
2. Data band - List the rest of the columns Due date, Accid (Account id), Printed, Amount inclusive, Tax amount, Reference, Document group 1, Document group 2, Account no., Salesperson, Amount exclusive, Status, Message line 1, Message line 2, Message line 3, Delivery address 1, Delivery address 2, Delivery address 3, Delivery address country, Postal address 1, Postal address 2, Postal address 3, Postal code, Country, Invoice address Company, Invoice address Contact, Delivery address Company, Delivery address Contact, E-mail address, Project, and Due (due / outstanding amount).

Default	*Sorted (selected) - Alphabetical list*



You may drag and drop any of the columns on the left band to the right band and the columns from the right band to the left band, to customise the grid for your requirements.

Hide / Show bands

Hide left band - Remove the tick in the first tick box. This will hide the id, Document no. Date and Description, columns.

Show left band - Tick the first block. This will add the hidden columns on the left band.

Hide data band - Remove the tick in the second tick box. This will hide all columns in the data band.

Show data band - Tick the second block. This will add all the hidden columns on the left band.



Hide / Show columns

By default, all thirty-six (36) columns will be displayed and listed in the Document entry list screen for each document type.

You may select to hide or show any column, as required.

To hide or show columns:

Click on the second block - Column headings - A list of the fields will be listed.

Remove the ticks for the columns to hide or select the columns you need to display.

You may use the Up arrows and/or the Down arrows Right or Left arrows keys to navigate the fields. You may use the Space bar to deselect (remove the tick) or to reselect (tick a field again).



If you wish to retain your layout, click on the Save grid layout button.

Created with the Standard Edition of HelpNDoc: Easily share your documentation with the world through a beautiful website

Group columns

If the "*Single line mode*" option is not selected (tick removed), a column header "*Use your mouse to pull a column here to group on that column*" will be displayed and the similar data in columns will be grouped.

Select a column and click on it. While holding the mouse button down, drag it to the "*Use your mouse to pull a column here to group on that column*" bar. Select any other column to drag and drop it on the the "*Use your mouse to pull a column here to group on that column*" bar. You may select as many columns, as necessary, to group your data.

You may also drag and drop these columns to the right or left to change the grouping of these columns.



If you wish to retain your layout, click on the Save grid layout button.

To remove a column from the "*Use your mouse to pull a column here to group on that column*" bar, you may use the following two (2) options:



1. Select the column heading (e.g., “*Document group*”) on the "*Use your mouse to pull a column here to group on that column*" bar, and drag it to the first line (above the column headings). When the mouse pointer change to a big X, drop it. The column will automatically be placed in the correct default sequence (or the place of the previous saved grid layout).
2. If you wish to change the column to a specific place, select the column heading (e.g., “*Document group*”) on the "*Use your mouse to pull a column here to group on that column*" bar, and drag it to the second line (column headings). When you drop it, the column will be added to the selected position or sequence of the columns.

If you wish to retain your layout, click on the Save grid layout button.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

Documents - Graphs

In addition to the Graph feature for each document type, in Documents on the Default ribbon, you may also print Graphs per week or Graphs per month for posted document types on the User reports menu:

1. Graphs → Graphs per week → Sales menu:
    a) Sales (Invoices - Credit notes) per week
    b) Invoices per week
    c) Credit notes per week
    d) Quotes per week
2. Graphs → Graphs per week → Purchases menu:
    a) Purchases (Purchases - Supplier returns) per week
    b) Purchases per week
    c) Supplier returns per week
    d) Orders per week
3. Graphs → Graphs per month → Sales menu:
    a) Sales (Invoices - Credit notes) per month
    b) Invoices per month
    c) Credit notes per month
    d) Quotes per month
4. Graphs → Graphs per month → Purchases menu:
    a) Purchases (Purchase - Supplier returns) per month
    b) Purchases per month
    c) Supplier returns per month
    d) Orders per month

View graphs

You may filter and view the documents in a graph.

To view the documents in graph, you may use the following options for the data to be included in the graph:

- Document types - Select the document type (i.e. invoices, credit notes, quotes purchases, supplier returns or orders).
- Document status - Select All, Posted or Unposted and Confirmed (Quotes and Orders).

- Filter options to select the documents to include or exclude from the graph , etc.

To view the documents in a graph, click on the Graph button.

To close the graph, click on the Graph button again.

In this example, the amount due is lower than the amount inclusive. This implies that the invoice is partially settled with payments or credit notes, linked to that invoice in the Open item link.

Example : Filtered by Address 3



Customize Chart

Customize Chart : Types

The default chart diagram is the "*Column diagram*". You may select the one of the following diagrams to view the graph.



Customize Chart : Series

By default, only the Amount inclusive and Due amount and Tax amount is displayed.

You may remove the tick of the series or add a tick to a series. For example, if you wish to see the amount exclusive, tick that option and if you do not wish to view the tax amount, remove the tick.



Sort by: select the options in the series to change the sequence of the documents in the graph is displayed.

Customize Chart : Data Groups

The Data Groups will list all the columns headings (field names) of the Document selection screen.

Customize Chart : Options

You may change the default values for the "*Legend, Title, Toolbox*" and "*Other (Value Hints)*" according to your requirements.



Customize Chart : Data groups

The data groups list all the available columns on the Documents grid, which is not already set as "*Data Levels*". You may add or remove any of the available Data Groups on the "*Data Levels*".

To add a "*Data Group*" to the "*Data Levels*":

1. Click on the Customize Chart button.
2. On the "*Customisation*" screen, click on the Data Groups tab.
3. Select the available data group form the list you wish to add to the "*Data Levels*".
4. Drag and drop the data group to the required place on the "*Data Levels*".

To remove a "*Data Group*" from the "*Data Levels*":

1. Click on the Customize Chart button.
2. On the "*Customisation*" screen, click on the Data Groups tab.
3. Select the available data group on the "*Data Levels*".
4. Drag the data group to any place below the "*Data Levels*". When the mouse pointer change to a big X, drop it. The data field will be added to its original place on the list in the "*Data Groups*" tab of the "*Customisation*" screen.



Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Export - Documents grid

The Export button on the Document entry list screen allows you to export the detail of a selected document type to a CSV (Comma Separated Value) file type. The saved exported file will automatically open the "*Export.txt*" file in a default spreadsheet app (program) (associated with the CSV (Comma Separated Values) file type.

You may use the following options to filter the data which you need to include in the spreadsheet:

1. Document type - Select one of the six (6) document types (i.e. Invoices (default), Credit notes, Quotes, Purchases, Supplier returns or Orders) you need to export.
2. Document status - Select "*All, Posted, Unposted*" or "*Confirmed*" for selected document types (i.e. Invoices (default), Credit notes, Quotes, Purchases, Supplier returns or Orders) you need to export.
3. Search and filter options - Search by – Once you have selected a document type, you may filter and search by columns. For example, if you wish to export documents for a specific Salesperson, you may filter for that Salesperson.
4. Document groups - You may select any specific document groups for Document group 1 you need to export.

Once you have made your choices, click on the Export button.

On the "*Save As*" screen, select the folder to store the file and enter name.

Click on the Save button.



Once the file is saved, it will automatically be opened in your system's default spreadsheet program, e.g. Microsoft Excel.



Open saved Export.txt files in another app (program) for CSV (Comma Separated Values) file type

If you wish to open saved Export.txt files in another app (program) for CSV (Comma Separated Values) file type, than Microsoft Excel, you may use the spreadsheet components of other apps (programs) e.g. LibreOffice, OpenOffice or UltraOffice installed on your system.

To do this, select the saved Export.txt file and right click on LibreOffice Calc.

Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Documents - Context menu

Right-click to display the following context menu:



The options are as follows:

1. Salesperson – Change the Salesperson (as added in Setup → Setup → Salesperson or Setup → Groups (Salespersons)).

2. Set reporting group 1 – Change the reporting group of a document, if Reporting group 1 was set for Documents (as added in the Setup → Groups (Document groups 1)).

The colours of the rows (list of documents) will be changed, if set in Reporting group 1.

3. Set reporting group 2 – Change the reporting group of a document, if Reporting group 2 was set for Documents (as added in Setup → Groups (Document group 2)).

4. Documents - The "*Documents*" context menu option on the Document list screen changes for the document type selected. Depending on whether a posted document; or an unposted document is selected; some context menu options may not be available, or additional specific context menu options may be added. Some examples are:

    - Change account - is not available for posted documents.
    - Adjustment - is not available for unposted documents. Adjustments not implemented in osFinancials5/TurboCASH5.

5. Print

    a) Print barcodes – This will print only the barcodes of stock item codes included on selected document(s).

    b) Print labels – This will only print the name (account description) of a debtor customer / client on a selected sales document. In the case of a purchase document, it will print the name (account description) of the creditor (supplier / vendor).

6. Others

    a) Import – This option allows you to import an exported document from a valid existing export.txf file. "*TurboCASH Data Exchange files*" are exported (created) in Tools → Export (Documents).

    b) Totals – This will list a summary of the Exclusive, Inclusive, Open amounts and the records on an Information screen.

The results may be selected and copied to any other text editor or other external program.

    c) Show details – This will display a mouse-over screen displaying the details (i.e. account description, document number, stock description, quantity and amount (inclusive of tax) of the selected document.

    d) Open item link – This will launch the Open item link screen displaying the transactions of the debtor (customer / client) or creditor (supplier / vendor) account on a selected document.

Only available for Invoices / Purchases document type.

This option is not available for other document types (Quotes, Credit notes, Orders and Supplier return documents).

7. Plugin action - To be advised.
8. Plugin mass action - Launch the mass actions (multiple actions), if plugins are activated and supported. To be advised.

The Plugins will be discussed in separate documentation.

9. Document links - To be advised.

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

Context menu - Salesperson

You may change the Salesperson for a selected document or documents. Salespersons can be changed for posted as well as unposted documents.

To change the salesperson on documents:

1. On Documents (Documents list screen) (Default ribbon), select the Document type, if the correct document type is not selected.
2. Select the Document(s), right-click on "*Salesperson*" context menu and select "*Empty*" or the salesperson from the sub-menu. The Salesperson will change on documents and the reports.

If you need to select multiple documents, press the Ctrl or Shift key and click on each document, for which you need to change the salesperson.



Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Context menu - Set reporting group 1/2

You may change the Document group 1 and/or Document group 2 for a selected document or documents. These Groups can be changed for posted as well as unposted documents.

To change the Document group 1 or 2 on documents:

1. On Documents (Documents list screen) (Default ribbon), select the Document type, if the correct document type is not selected.

2. Select the Document(s), right-click on "*Document group 1*" or "*Document group 2*" context menu.

> *If you need to select multiple documents, press the Ctrl or Shift key and click on each document, for which you need to change the document reporting group.*

3. Select "*Empty*" or the available document group from the sub-menu. The "*Document group 1*" or "*Document group 2*" will change on documents and the reports.



Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Context menu - Documents

The "*Documents*" context menu option on the "*Document list*" screen changes for the document type selected.

Depending on whether a posted document; or an unposted document is selected; some context menu options may not be available, or additional specific context menu options may be added.

Some examples are:

Change account - is not available for posted documents.

Adjustment - is not available for unposted documents and is not implemented in osFinancials5/TurboCASH5.

Sales documents

Invoices - Documents context menu



The options is as follows:

1. Copy document - Create an exact copy of a selected document and add it as a new document to the list for the same document type.

2. Create purchase on default supplier 1 – This option allows you to create an order for a default preferred supplier 1 (as selected for a specific stock item (Stock items on the Default ribbon)).

3. Convert invoice to order - Create an Order from a selected Invoice or Quote. The "*Creditor accounts*" screen will be displayed on which you need to select a creditor (supplier / vendor) account. This will add the converted Invoice or Quote as a new document to the list of Orders. You may edit the Order and then confirm (convert) the Order to a Purchase document.

4. Copy to - In addition to the Documents → Copy document option on the context menu of the "*Document list*" screen, to create exact copies of the selected document(s) of a specific document type, you may also copy any of the documents to another document type.

5. Convert to credit note / supplier return - Convert selected Invoice(s) to Credit note(s).
6. Redo discount on document - This will refresh the discount on a selected document.
7. Change account - Select another debtor (customer / client) account for a selected unposted Invoice.
8. Edit account - Edit the debtor (customer / client) account for a selected document.
9. Create backorders to deliver - If an outstanding backorder exists for a debtor (customer / client), you may use this option to create a new Invoice for the outstanding backorders to deliver.
10. Adjustment - This option is only available for posted documents. This option to edit the document header of a posted document is not implemented in osFinancials5/TurboCASH5.
11. Create account from document details - This document context menu allows you to create a new debtor (customer / client) account for unposted Invoices, using the document details.
12. Confirm - By default, the "*Status*" of an unposted document (i.e. Invoice, Credit note, Purchase or Supplier return), is set as "*Unposted*". Unposted documents can be edited. You may change the "*Status*" of unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), from "*Open*" to "*Confirmed*". Once document status, is set to "*Confirmed*" you may filter the document status for a Confirmed documents. Posting "*Confirmed*" unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), will change the document's "*Status*" from "*Confirmed*" to "*Posted*".
13. Spreadsheet import -

Credit notes - Documents context menu



The options is as follows:

1. Copy document - Create an exact copy of a selected document and add it as a new document to the list for the same document type.

2. Copy to - In addition to the Documents → Copy document option on the context menu of the "*Document list*" screen, to create exact copies of the selected document(s) of a specific document type, you may also copy any of the documents to another document type.

3. Change account - Select another debtor (customer / client) account for a selected unposted Credit note.

4. Edit account - Edit the debtor (customer / client) account for a selected document.

5. Adjustment - This option is only available for posted documents. This option to edit the document header of a posted document is not implemented in osFinancials5/TurboCASH5.

6. Create account from document details - This document context menu allows you to create a new debtor (customer / client) account for unposted Credit notes, using the document details.

7. Confirm - By default, the "*Status*" of an unposted document (i.e. Invoice, Credit note, Purchase or Supplier return), is set as "*Unposted*". Unposted documents can be edited. You may change the "*Status*" of unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), from "*Open*" to "*Confirmed*". Once document status, is set to "*Confirmed*" you may filter the document status for a Confirmed documents. Posting "*Confirmed*" unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), will change the document's "*Status*" from "*Confirmed*" to "*Posted*".

8. Spreadsheet import -

Quotes - Documents context menu



The options is as follows:

1. Copy document - Create an exact copy of a selected document and add it as a new document to the list for the same document type.

2. Confirm quotes and orders - Once the debtor (customer / client) accepts the Quote, it can then be confirmed and converted to an Invoice. Once a Quote is confirmed and converted to an Invoice, you may need to edit the Invoice, before you update (post) the Invoice to the ledger.

3. Create purchase on default supplier 1 - This option allows you to create an order for a default supplier 1 (as selected for a specific stock item (Stock items on the Default ribbon)).

4. Convert invoice to order - Create an Order from a selected Invoice or Quote. *The "Creditor accounts*" screen will be displayed on which you need to select a creditor (supplier / vendor) account. This will add the converted Invoice or Quote as a new document to the list of Orders. You may edit the Order and then confirm (convert) the Order to a Purchase document.

5. Convert quote to one unprocessed invoice per client -

6. Convert documents to single document - This will convert selected unposted Quotes to a single document.

WARNING - CONVERT POSTED DOCUMENTS TO A SINGLE DOCUMENT

In the case of Purchases and Supplier returns, DO NOT SELECT THE POSTED documents.

7. Copy to - In addition to the Documents → Copy document option on the context menu of the "*Document list*" screen, to create exact copies of the selected document(s) of a specific document type, you may also copy any of the documents to another document type.

8. Redo discount on document - This will refresh the discount on a selected document.

9. Change account - Select another debtor (customer / client) account for a selected unconfirmed Quote.

10. Edit account - Edit the debtor (customer / client) account for a selected document.

11. Create backorders to deliver - If an outstanding backorder exists for a debtor (customer / client), you may use this option to create a new Invoice for the outstanding backorders to deliver.

12. Create account from document details - This document context menu allows you to create a new debtor (customer / client) account for unconfirmed Quotes, using the document details.

13. Confirm - This option is not applicable to Quotes.

14. Spreadsheet import -

Purchase documents

Purchases - Documents context menu



The options is as follows:

1. Copy document - Create an exact copy of a selected document and add it as a new document to the list for the same document type.

2. Convert documents to single document - This will convert selected unposted Purchase documents to a single document.

> *WARNING - CONVERT POSTED DOCUMENTS TO A SINGLE DOCUMENT*
>
> *In the case of Purchases and Supplier returns, DO NOT SELECT THE POSTED documents.*

3. Copy to - In addition to the Documents → Copy document option on the context menu of the "*Document list*" screen, to create exact copies of the selected document(s) of a specific document type, you may also copy any of the documents to another document type.

4. Convert to credit note / supplier return - Convert selected Purchase(s) to Supplier return(s).

5. Change account - Select another creditor (supplier / vendor) account for a selected unposted

Purchase.

6. Edit account - Edit the creditor (supplier / vendor) account for a selected document.

7. Adjustment - This option is only available for posted documents. This option to edit the document header of a posted document is not implemented in osFinancials5/TurboCASH5.

8. Create account from document details - This documents context menu allows you to create a new creditor (supplier / vendor) account for unposted Purchases, using the document details.

9. Confirm - By default, the "*Status*" of an unposted document (i.e. Invoice, Credit note, Purchase or Supplier return), is set as "*Unposted*". Unposted documents can be edited. You may change the "*Status*" of unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), from "*Open*" to "*Confirmed*". Once document status, is set to "*Confirmed*" you may filter the document status for a Confirmed documents. Posting "*Confirmed*" unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), will change the document's "*Status*" from "*Confirmed*" to "*Posted*".

10. Spreadsheet import -

Supplier returns - Documents context menu



The options is as follows:

1. Copy document - Create an exact copy of a selected document and add it as a new document to the list for the same document type.

2. Convert documents to single document - This will convert selected unposted Supplier return documents to a single document.

WARNING - CONVERT POSTED DOCUMENTS TO A SINGLE DOCUMENT

In the case of Purchases and Supplier returns, DO NOT SELECT THE POSTED documents.

3. Copy to - In addition to the Documents → Copy document option on the context menu of the "*Document list*" screen, to create exact copies of the selected document(s) of a specific document type, you may also copy any of the documents to another document type.

4. Change account - Select another creditor (supplier / vendor) account for a selected unposted Supplier return.

5. Edit account - Edit the creditor (supplier / vendor) account for a selected document.

6. Adjustment - This option is only available for posted documents. This option to edit the document header of a posted document is not implemented in osFinancials5/TurboCASH5.

7. Create account from document details - This document context menu allows you to create a newcreditor (supplier / vendor) account for unposted Supplier returns, using the document details.

8. Confirm - By default, the "*Status*" of an unposted document (i.e. Invoice, Credit note, Purchase or Supplier return), is set as "*Unposted*". Unposted documents can be edited. You may change the "*Status*" of unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), from "*Open*" to "*Confirmed*". Once document status, is set to "*Confirmed*" you may filter the document status for a Confirmed documents. Posting "*Confirmed*" unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), will change the document's "*Status*" from "*Confirmed*" to "*Posted*".

9. Spreadsheet import -

Orders - Documents context menu



The options is as follows:

1. Copy document - Create an exact copy of a selected document and add it as a new document to the list for the same document type.

2. Confirm quotes and orders - Once the creditor (supplier / vendor) delivers the Order, it can then be confirmed and converted to a Purchase. Once a Order is confirmed and converted to a Purchase document, you may need to edit the Purchase, before you update (post) the Purchase to the ledger.

3. Convert documents to single document - This will convert selected Orders to a single document.

> *WARNING - CONVERT POSTED DOCUMENTS TO A SINGLE DOCUMENT*
>
> *In the case of Purchases and Supplier returns, DO NOT SELECT THE POSTED documents.*

4. Copy to - In addition to the Documents → Copy document option on the context menu of the "*Document list*" screen, to create exact copies of the selected document(s) of a specific document type, you may also copy any of the documents to another document type.

5. Change account - Select another creditor (supplier / vendor) account for a selected unconfirmed

Order.

6. Edit account - Edit the creditor (supplier / vendor) account for a selected document.
7. Create purchase on default supplier 1 – This option allows you to create an order for a default preferred supplier 1 (as selected for a specific stock item (Stock items on the Default ribbon)).
8. Create account from document details - This document context menu allows you to create a new creditor (supplier / vendor) account for unconfirmed Orders, using the document details.
9. Confirm - This option is not applicable to Orders.
10. Spreadsheet import - This option allows you to export and import documents in a Spreadsheet.

Created with the Standard Edition of HelpNDoc: Create cross-platform Qt Help files

Context menu - Copy document

You may create exact copies of the selected document(s) of a specific document type.

To create copies of selected documents:

1. On Documents (Documents list screen) (Default ribbon), select the Document type, if the correct document type for sales documents (i.e. Invoices, Credit notes or Quotes) or purchase documents (i.e. Purchases, Supplier returns or Orders).
2. Select the Document(s), right-click on Documents → Copy document on the context menu. Exact unposted copies of the selected documents will be created for the same document type.

If you need to select multiple documents, press the Ctrl or Shift key and click on each document, which you need to copy.

Once this is done, you may edit / post these documents.



Once a document is copied, the selected source document from which it is copied, will be added to the third message line.

You need to edit the first and second message line, if required.

Note the following:

- *Date - The system date will be used. You may edit the date, if required.*
- *Message lines 1 and 2 - Document message (set in the Setup → Documents setup on the Setup ribbon) will also be adde*
- *Message line 3 - Up to 2 References for Document numbers (e.g. IN000022 (the latest document reference from which the existing document numbers on the source document (from which this document is copied). Only 5 digits of the 3 document*



Comments and remarks

The comments and remarks, if added in the source document will be included in the copied document. You may need to check and edit these, if necessary.

This is important if specific information for the stock item (such as, for example, series or serial numbers, etc.) may not be applicable in the copied document.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Context menu - Copy to

In addition to the Documents → Copy document option on the context menu of the "*Document list*" screen, to create exact copies of the selected document(s) of a specific document type, you may also copy any of the documents to another document type.

If you need to select multiple documents, press the Ctrl or Shift key and click on each document, which you need to copy.

Right-click and select Documents → Copy to → Invoices, Credit notes, Quotes, Purchases, Supplier returns or Orders option on the context menu.



A confirmation message will be displayed:

"Continue action Copy to Invoice ?" (where Invoice is the selected document type to copy to).

Click Yes to copy the document to the selected document type. New documents for the selected document type will be created.

Once this is done, you may edit / post these documents.

Copy from Invoice to Invoice / Credit note / Quote

Remarks and Comments will also be copied from the source document. You may need to edit these, if your

requirements changes.

Once a document is copied, the selected source document from which it is copied, will be added to the third message line.

You need to edit the first and second message line, if required.

Note the following:

- *Date - The system date will be used. You may edit the date, if required.*
- *Message lines 1 and 2 - Document message (set in the Setup → Documents setup on the Setup ribbon) will also be adde*
- *Message line 3 - Up to 2 References for Document numbers (e.g. IN000022 (the latest document reference from which the existing document numbers on the source document (from which this document is copied). Only 5 digits of the 3 document*



Comments and remarks

The comments and remarks, if added in the source document will be included in the copied document. You may need to check and edit these, if necessary.

This is important if specific information for the stock item (such as, for example, series or serial numbers, etc.) may not be applicable in the copied document.

Copy from Invoice to Purchase / Supplier return / Order

Should you copy an Invoice / Credit note / Quote to a Purchase / Supplier return or Order document, you may need to consider the following and edit, where necessary:



Comments and remarks

The comments and remarks, if added in the source document will be included in the copied document. You may need to check and edit these, if necessary.

This is important if specific information for the stock item (such as, for example, series or serial numbers, etc.) may not be applicable in the copied document.

Copy Sales documents to Purchase documents - Notes

Should you copy an Invoice / Credit note / Quote to a Purchase / Supplier return or Order document, you may need to consider the following and edit, where necessary:

- Change account - Change the debtor (customer / client) account to a creditor (supplier / vendor) account in the Documents → Change account option on the context menu of the "*Document entry*" list screen.
- Messages - Once a document is copied, the selected source document from which it is copied, will be added to the third message line. You need to edit the first and second message line, if required. Note the following:
    - Message lines 1 and 2 - Document message (set in the Setup → Documents setup on the Setup ribbon) will also be added to the copied message of the selected source document.
    - Message line 3 - Up to 2 References for Document numbers (e.g. IN000022 (the latest document reference from which the document is copied will automatically be inserted before any existing document numbers on the source document (from which this document is copied). Only 5 digits of the 3 document number will be available..
- Tax - Output tax (VAT/GST/Sales tax) - will be copied - You may need to change this to Input tax (VAT/GST/Sales tax).
- Selling prices - will be copied - You may need to change this to purchase prices.
- Date - The system date will be used. You may edit the date, if required.

Copy Purchase documents to Sales documents - Notes

Should you copy an Purchase / Supplier return / Order to a Invoice / Credit note / Quote, you may need to consider the following and edit, where necessary:

- Change account - Change the creditor (supplier / vendor) account to a debtor (customer / client) account in the Documents → Change account option on the context menu of the "*Document entry*" list screen.
- Messages - Once a document is copied, the selected source document from which it is copied, will be added to the third message line. You need to edit the first and second message line, if required. Note the following:
    - Message lines 1 and 2 - Document message (set in the Setup → Documents setup on the Setup ribbon) will also be added to the copied message of the selected source document.

- Message line 3 - Up to 2 References for Document numbers (e.g. IN000022 (the latest document reference from which the document is copied will automatically be inserted before any existing document numbers on the source document (from which this document is copied). Only 5 digits of the 3 document number will be available..

- Tax - Input tax (VAT/GST/Sales tax) - will be copied - You may need to change this to Output tax (VAT/GST/Sales tax).
- Purchase prices - will be copied - You may need to change this to Selling prices.
- Date - The system date will be used. You may edit the date, if required.

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Context menu - Convert invoice to an order

The context menu option will only be available for the Invoices document type.

To convert invoice(s) to order(s):

1. Select the Invoices document type.
2. Select the document(s) to convert.
3. Right-click and select Documents → Convert invoice to order option on the context menu. A confirmation message is displayed:

   Do you wish to continue?

4. Click on the Yes button to continue. The "*Creditor accounts*" screen is displayed:



5. Select the creditor (supplier / vendor) account and click on the Open or OK button.

6. The Order(s) will be available as "*Unposted*" if the "*Orders*" document type is selected.



Edit orders converted from invoices

You need to check and edit the following, if needed:

- *Date - The system date will by default be displayed. You may edit it, if necessary.*
- *Delivery address - The delivery address of the debtor (customer / client) account will be copied. The delivery address of the debtor (customer / client) account will print on document layout files and delivery notes..*
- *Contact person - The contactperson will be available on the list for the selected creditor (supplier / vendor) account.In the postal address field the contact person of the creditor (supplier / vendor) will be displayed and in the Delivery address the contact person of the debtor (customer / client) will be displayed.*
- *Message - The Invoice message line 1 field content will automatically be inserted after the Order message line 1 field.*
- *Amounts - The purchase (cost) prices will replace the selling prices. You may need to edit the purchase (cost) prices, if necessary.*
- *Tax - The output tax (VAT/GST/Sales tax) on the Invoice is converted to input tax (VAT/GST/Sales tax) on the order.*

Comments and remarks

The comments and remarks, if added in the source invoice will be included in the converted order. You may need to check and edit these, if necessary.

This is important if specific information for the stock item (such as, for example, series or serial numbers, etc.) may not be applicable in the converted order.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's Efficient User Interface

Context menu - Create purchase on default supplier1

This option allows you to create an order for a default supplier 1 of specific stock items (products) account (as selected for a specific stock item (Stock items on the Default ribbon)) from the Invoices, Quotes and Orders document types.

If you have selected Documents → Create purchases on default supplier1 on the context menu of the Documents list screen; and no default supplier 1 have been added in the "Preferred supplier 1" field for the

Stock item included in the document(s) selected stock item, an error message will be displayed.

"3DRILL Drill press No default supplier 1 for these stock items! Please correct first!" (where "3DRILL Drill press" is the stock code and stock description, as per this example).

Click on the OK button and correct it in the Stock items (Default ribbon) for the stock item, if necessary.

Preferred supplier setting



Create Orders for preferred supplier 1

To create orders for preferred supplier 1:

1. Select the "*Invoice*" or "*Quote*"or "*Order*" document type.

2. Right-click and select Documents → Create purchase on default supplier 1 option on the context menu. A new Order for the default (preferred) supplier account will be created.



Note the Supplier stock code will be displayed in the "Item no." field of Document entry form, if entered in the "Supplier stock code" field.

The original Stock code will still print on document layout files.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Context menu - Convert invoice to credit note / supplier return

---

Convert Invoices to Credit notes

Once you have posted an Invoice to the ledger, you cannot edit the Invoice.

Adjustments - not implemented in osFinancials5/TurboCASH5

For example; it may happen sometimes that a debtor (customer / client), relocates and still have outstanding invoices with the incorrect (old) address after the Invoice is posted to the ledger.

You may use the Documents → Adjustment - option on the context menu (Documents list screen), to change / edit specific fields, such as the reference in the "Your reference" field, "Postal address", Contactperson, "Delivery address" and "Messages" in the Document header. The Tax reference field may also be edited.

You may change the Salesperson or Document groups (Reporting group1 and/or Reporting group) on the

context menu.

These changes will be reflected on the document layout files, when you print or reprint the document.

If an Invoice is incorrectly processed and posted; or if the all the items; or some of the items on an Invoice is returned, you may use this option to create a Credit note for the Invoice to cancel the Invoice or a part of the Invoice.

To convert invoice to credit note / return note:

1. Select the "*Invoices*" document type.

2. Select the document(s) to convert.

   If you need to select multiple documents, press the Ctrl or Shift key and click on each Invoice, which you need to convert to a Credit note.

3. Right-click and select Documents → Convert to credit note / supplier return option on the context menu. A confirmation screen will be displayed.

   "Do you wish to continue?"

4. Click on the Yes button to continue. The Credit note(s) will be available as a new unposted Credit note(s).



Once a Credit note is converted from an Invoice, the selected source Invoice from which it is converted, will be added to the third message line.

You need to edit the first and second message line, if required.

Note the following:

- *Date - The system date will be used. You may edit the date, if required.*
- *Message lines 1 and 2 - Document message (set in the Setup → Documents setup on the Setup ribbon) will also be added to the copied message of the selected source document.*
- *Message line 3 - Up to 2 References for Document numbers (e.g. IN000022 (the latest document reference from the Purchase is converted will automatically be inserted before any existing document numbers on the Supplier return. Only 5 digits of the 3 document number will be available..*

You may need to edit the quantities. For example, if 2 stock items were included on the selected source Credit note, and only 1 stock item was returned, you need to change the Quantities to 1.

Comments and remarks

The comments and remarks, if added in the source invoice will be included in the converted credit note. You may need to check and edit these, if necessary.

This is important if specific information for the stock item (such as, for example, series or serial numbers, etc.) may not be applicable in the converted credit note.

Convert Purchases to Supplier returns

Once you have posted a Purchase document to the ledger, you cannot edit the Purchase document.

Adjustments - not implemented in osFinancials5/TurboCASH5

For example; it may happen sometimes that a creditor (supplier / vendor), relocates and still have outstanding purchases with the incorrect (old) address after the Purchase document is posted to the ledger.

You may use the Documents → Adjustment - option on the context menu (Documents list screen), to change / edit specific fields, such as the reference in the "Your reference" field, "Postal address", Contactperson, "Delivery address" and "Messages" in the Document header. The Tax reference field may also be edited.

You may change the Salesperson or Document groups (Reporting group1 and/or Reporting group 2) on the context menu.

These changes will be reflected on the document layout files, when you print or reprint the document.

If a Purchase document is incorrectly processed and posted; or if the all the items; or some of the items on

a Purchase document is returned, you may use this option to create a Supplier return for the Purchase to cancel the Purchase or a part of the Purchase.

To convert a purchase to Supplier return:

1. Select the "*Purchases*" document type.

2. Select the document(s) to convert.

> *If you need to select multiple documents, press the Ctrl or Shift key and click on each Purchase, which you need to convert to a Supplier return.*

3. Right-click and select Documents → Convert to credit note / supplier return option on the context menu. A confirmation screen will be displayed.

> "Do you wish to continue?"

4. Click on the Yes button to continue. The Supplier return(s) will be available as a new unposted Supplier return document.



> *Once a Supplier return is converted from a Purchase, the selected source Purchase from which it is converted, will be added to the third message line.*
>
> *You need to edit the first and second message line, if required.*
>
> *Note the following:*

- *Date - The system date will be used. You may edit the date, if required.*
- *Message lines 1 and 2 - Document message (set in the Setup → Documents setup on the Setup ribbon) will also be added to the copied message of the selected source document.*
- *Message line 3 - Up to 2 References for Document numbers (e.g. PU000006 (the latest document reference from which the document is converted will automatically be inserted before any existing document numbers on the Supplier return. Only 5 digits of the 3 document number will be available..*

You may need to edit the quantities. For example, if 2 stock items were included on the selected source Supplier return, and only 1 stock item was returned, you need to change the Quantities to 1.

Comments and remarks

The comments and remarks, if added in the source purchae will be included in the converted supplier return. You may need to check and edit these, if necessary.

This is important if specific information for the stock item (such as, for example, series or serial numbers, etc.) may not be applicable in the converted supplier return.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Context menu - Confirm quotes and orders - Quotes

Once the debtor (customer / client) accepts the Quote, it can then be confirmed and converted to an Invoice. Once a Quote is confirmed and converted to an Invoice, you may need to edit the Invoice, before you update (post) the Invoice to the ledger.

Quotes may also be confirmed in Input → Confirm menu on the Default ribbon. (Shift+F3).

If the Document posting option is selected (ticked) on the Documents tab of Access control (Setup ribbon), the caption of the Posting button, will change to Confirmation button if Quotes and Orders are selected as the document type.

The Documents → Confirm quotes and orders option on the context menu, is only available, if the Quotes or Orders document type is selected.

To confirm Quotes(s):

1. Select the "*Quote*" document type.

2. Select the Quote(s) to confirm.

> *If you need to select multiple documents, press the Ctrl or Shift key and click on each Quote, you need to confirm.*



3. Right-click and select Documents → Confirm quotes and orders option on the context menu. A confirmation message is displayed:

> "Do you wish to: (2) Quotes Confirmation" (where (2) is the number of documents selected).

4. Click on the Yes button to continue. A confirmation message will be displayed.

> "Do you wish to delete this Quotes?"

> *If you click on the No button, the selected Quotes will still be confirmed and converted to Invoices. These Quotes will still be available to edit.*
>
> *You may delete the Quotes manually in Edit → Documents menu on the Default ribbon.*

5. Click on the Yes button to continue. Once the process is finished, an information message is displayed:

"Document(s) created." (This message will list the new Invoice number, reference, account code and account description of the debtor (customer / client) account)).

6. Click on the OK button. Note - If the Orders document type was selected, this confirmation message will not be displayed.

7. The converted Quotes will be available will be available as unposted Invoices.

You need to check and edit the Messages in the Document header, if necessary.

The source document, Quote number (e.g. "Ref:QU000004") will be added to the third Message line in the Document header of the Invoice.

Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with a Help Authoring Tool

Context menu - Confirm quotes and orders - Orders

Once the creditor (supplier / vendor) delivers the Order, it can then be confirmed and converted to a Purchase. Once a Order is confirmed and converted to a Purchase document, you may need to edit the Purchase, before you update (post) the Purchase to the ledger.

Quotes and Orders may also be confirmed in Input → Confirm menu on the Default ribbon.

(Shift+F3).

If the Document posting option is selected (ticked) on the Documents tab of Access control (Setup ribbon), the caption of the Posting button, will change to Confirmation button if Quotes and Orders are selected as the document type.

The Documents → Confirm quotes and orders option on the context menu, is only available, if the Quotes or Orders document type is selected.

To confirm Order(s):

1. Select the "*Order*" document type.

2. Select the Order(s) to confirm.

If you need to select multiple Orders, press the Ctrl or Shift key and click on each Order, you need to confirm.



3. Right-click and select Documents → Confirm quotes and orders option on the context menu. A confirmation message is displayed:

"Do you wish to: (2) Orders Confirmation" (where (2) is the number of documents selected).

4. Click on the Yes button to continue. A confirmation message is displayed:

"Do you wish to delete this Orders?"

If you click on the No button, the selected Orders will still be confirmed and converted to Purchases. These Orders will still be available to edit.

You may delete the Orders manually in Edit → Documents menu on the Default ribbon.

5. Click on the Yes button to continue.

6. The converted Orders will be available will be available as unposted Purchases.

You need to check and edit the Messages in the Document header, if necessary.

The source document, Order number (e.g. "Ref:OR000002") will be added to the third Message line in the Document header of the Purchase.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Context menu - Convert quote to one unprocessed invoice per client

Convert quote to one unprocessed invoice per client.

The Quote number and date of the selected quote which is converted will be added as a comment.

Each time this option is selected for a selected Quote a new line with the Stock item and Quote number and date will be added.

To convert quote to one unprocessed invoice per client:

1. Select the "*Quotes*" document type.
2. Select the Quote to convert quote to one unprocessed invoice per client.
3. Right-click and select Documents → Convert quote to one unprocessed invoice per client option on the context menu.



4. A new Invoice for the selected debtor (client) will be generated.

5. Select the "*Invoices*" document type and select the Invoice.



The Quote number and date of the selected quote which is converted will be added as a comment.

Each time this option is selected for a selected Quote a new line with the Stock item and Quote number and date will be added.

Created with the Standard Edition of HelpNDoc: Easily convert your WinHelp HLP help files to CHM with HelpNDoc's step-by-step guide

Context menu - Convert documents to a single document

To convert documents to a single document:

1. Select the sales documents (i.e. Credit notes or Quotes) or for purchase documents (i.e. Purchases, Supplier returns or Orders) document type.

2. Select the documents to convert into one document.

3. Right-click and select Documents → Convert documents to a single document option on the context

menu. A confirmation message "*Do you wish to delete this Purchases?*" (Purchases, as per this example, will be replaced by Credit notes, Quotes, Supplier returns or Orders depending from which document type this option is launched) will be displayed.

4. If you need to retain the selected documents and create a new document, click on the No button or Yes button to continue.

> *If you wish to retain the original documents, click on the No button. These documents will still be available to process.*
>
> *If you click on the Yes button, these documents will permanently be deleted. If you have selected the incorrect documents, and you have clicked on the Yes button, you may need to create these document(s) again.*

   The *"Debtor accounts"* screen will be displayed (for Credit notes or Quotes document type) or *Creditor account* (Purchases, Supplier returns or Orders document type).

5. Select the Debtor account (Credit notes or Quotes document type) or Creditor account (Purchases, Supplier returns or Orders document type) and click on the Open / OK button. Once the process is finished, the new document will be available will be available as Unposted for the selected document type.

6. You may edit the new document, if necessary.

This option allows you to select more than one sales documents (i.e. Credit notes or Quotes) or for purchase documents (i.e. Purchases, Supplier returns or Orders) and convert them as a single document of the same document type.

> *WARNING - CONVERT POSTED DOCUMENTS TO A SINGLE DOCUMENT*
>
> *In the case of Purchases and Supplier returns, DO NOT SELECT THE POSTED documents. This option allows you to select posted Purchase documents and Posted Supplier return documents and to confirm to delete the posted Documents.*
>
> *Deleted documents will not be available on the Tools → Global processes → Reverse posted batch/document menu on the Documents tab (Setup ribbon).*
>
> *Credit notes will not be listed in the Documents tab and the Transactions tab of the debtor (customer / client) account, but will still be listed in the T-Account viewer as transactions.*
>
> *Purchases and Supplier returns will not be listed in the Documents tab and the Transactions tab of the creditor (supplier / vendor) account, but will still be listed in the T-Account viewer as transactions.*
>
> *You will not be allowed to Delete posted documents in the Edit → Delete - Documents menu option*

(Default ribbon).

Convert Quotes to a single document

The process to convert Orders to a single document, is similar than to convert Quotes to a single document.

To convert quotes to a single document:

1. Select the "*Quotes*" document type.

> *WARNING - CONVERT POSTED DOCUMENTS TO A SINGLE DOCUMENT*
>
> *In the case of Purchases and Supplier returns, DO NOT SELECT THE POSTED documents.*

2. Select the unposted documents to convert into one document.

> *If you need to select multiple documents, press the Ctrl or Shift key and click on each document, which you need to convert to a single document.*



3. Right-click and select Documents → Convert documents to a single document option on the context menu. A confirmation message will be displayed.

"Do you wish to delete this Quotes?"

4. If you need to retain the selected documents and create a new document, click on the No button to continue.

If you wish to retain the original Quotes, click on the No button. These Quotes will still be available to process.

If you click on the Yes button, these Quotes will permanently be deleted. If you have selected the incorrect documents, and you have clicked on the Yes button, you may need to create these Quote(s) again.

The *"Debtor accounts" list* screen is displayed:



5. Select the Debtor (customer / client) account and click on the Open / OK button. Once the process is finished, the new document will be available will be available as "Unposted" (unconfirmed) for the selected document type.

6. You may edit the new document, if necessary. An example of 2 Quotes that is converted to a single Quote, is as follows:



You may need to edit the quote with specific attention to the following:

- Message lines 1 and 2 - The message fields need to be edited, as the messages of both the source quotes are added in the first 2 message lines.
- Message line 3 - The reference of the last selected source Quote,
- Comments - The Quote number and Reference number (as in the "*Your reference*" field of the document header) will be added as a Comment after the items.

In this example, the selected source Quotes selected is as follows:

- *QU000005 C103 - It contains two items. This inserted after the last item's comment line.*
- *QU000004 D-102 - This inserted after the item's comment line.*

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Context menu - Change account

You may change the account for unposted documents.

Sales documents - Select a different debtor (customer / client) account for unposted sales documents (i.e. Invoices, Credit notes or Quotes).

Purchase documents - Select a different creditor (supplier / vendor) account for unposted purchase documents (i.e. Purchases, Supplier returns or Orders).

Change a debtor (customer / client) account

To change a debtor (customer / client) account for a unposted document:

1. Select the Invoices, Credit notes or Quotes document type.
2. Select the document to change the account for.
3. Right-click and select Documents → Change account option on the context menu. The "*Debtor accounts*" list screen will list only the active debtor (customer / client) accounts:



4. Select a different account.
5. Click on the Open or OK button.

Change the creditor (creditor / vendor) account

To change the creditor (creditor / vendor) account for a unposted purchase document:

1. Select the Purchases, Supplier returns or Orders document type.

2. Select the document to change the account for.

3. Right-click and select Documents → Change account option on the context menu. The "*Creditor accounts*" list screen will list only the active creditor (supplier / vendor) accounts:



4. Select a different account.

5. Click on the Open or OK button.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Context menu - Edit account

You may edit a debtor (customer / client) account for sales documents (i.e. Invoices, Credit notes or Quotes) or edit a creditor (supplier / vendor) account for purchase documents (i.e. Purchases, Supplier returns or Orders) using the document details.

Once the changes on an account is saved, it will be reflected in the document header of unposted documents.

If a document is posted and the account is edited, the changes will not be reflected in the document header.

Edit a debtor (customer / client) account

To edit a debtor (customer / client) account from the documents list screen:

1. Select the Invoices, Credit notes or Quotes document type.
2. Select the document to edit the account.
3. Right-click and select Documents → Edit account option on the context menu. The "*Debtor accounts*" edit form with the details of the debtor (customer / client) account for sales documents (i.e. Invoices, Credit notes or Quotes) is displayed:



4. Enter and/or edit the fields, as necessary.
5. Click on the OK or Save button.

Edit a creditor (supplier / vendor) account

To edit a creditor (supplier / vendor) account from the documents list screen:

1. Select the Purchases, Supplier returns or Orders document type.
2. Select the document to edit the account.

3. Right-click and select Documents → Edit account option on the context menu. The "*Creditor accounts*" edit form with the details of the creditor (supplier / vendor) account for purchase documents (i.e. Purchases, Supplier returns or Orders) is displayed:



4. Enter and/or edit the fields, as necessary.

5. Click on the OK or Save button.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Context menu - Create account from document details

This documents context menu option allows you to create a new debtor (customer / client) account for unposted sales documents (i.e. Invoices, Credit notes or Quotes) or an new creditor (supplier / vendor) account for unposted purchase documents (i.e. Purchases, Supplier returns or Orders) using the document details.

This may be necessary if a Document is imported and the account does not exist.

Create a new debtor (customer / client) account using the document details

To create a new debtor (customer / client) account using the document details:

1. Select the Invoices, Credit notes or Quotes document type.

2. Select the document to create an account for.

3. Right-click and select Documents → Create account from document details option on the context menu. The "*Debtor accounts*" edit form with the details on the document header is displayed:



4. Enter a "*Debtor code*" and enter or edit the fields, as necessary.

> *Debtor code - Enter a prefix followed by 5-digits. In this example, the Debtor code is prefixed with "1". Creditor codes are prefixed with "2" in this documentation.*
>
> *This is important to distinguish accounts for debtors (customers / clients) from accounts for creditors (suppliers / vendors). In some features and on some screens and reports this makes it easier to identify the account type.*

5. Click on the OK or Save button. A confirmation message will be displayed.

Create this account?"

6. Click on the Yes button to continue.

Once the New account is saved the document will be listed in the Documents tab of the new debtor (customer / client) account.

Create a new creditor (supplier / vendor) account using the document details

To create a new creditor (supplier / vendor) account using the document details:

1. Select the Purchases, Supplier returns or Orders document type.
2. Select the document to create an account for.
3. Right-click and select Documents → Create account from document details option on the context menu. The "*Creditor accounts"* edit form with the details on the document header is displayed:



4. Enter a "*Creditor code*" and enter or edit the fields, as necessary.

Creditor code - Enter a prefix followed by 5-digits. In this example, the Creditor code is prefixed

with "2". Debtor codes are prefixed with "1" in this documentation.

This is important to distinguish accounts for creditors (suppliers / vendors) from accounts for debtors (customers / clients). In some features and on some screens and reports this makes it easier to identify the account type.

5. Click on the OK or Save button. A confirmation message " will be displayed.

Create this account?

6. Click on the Yes button to continue.

Once the New account is saved the document will be listed in the Documents tab of the new creditor (supplier / vendor) account.

Created with the Standard Edition of HelpNDoc: How to Protect Your PDFs with Encryption and Passwords

Context menu - Redo discount on document

If discount is processed on unposted Invoices or Quotes, you may need to reset or clear the discount. The "*Redo discount on document*" option is also available for posted Invoices, but cannot be cleared as you may not edit a posted Invoice.

To redo discount on document:

1. Select the Invoices or Quotes document type.
2. Select the document(s) to reset the discount.

If you need to select multiple documents, press the Ctrl or Shift key and click on each document, which you reset the discount.

3. Right-click and select Documents → Redo discount on document option on the context menu.
4. Once the process is finished, you may need to edit the document.

Discount changes

The discount that will be cleared and reset, is added as follows:

1. F8:Discount icon - Percentage added which applies to all items included in the document lines.

2. Any Discount percentage added manually in the "*Discount percentage*" column of the document lines for a Stock item.

3. Enter Invoice total - If a new Invoice total is added "*Enter new inclusive total*"

The discount will not be cleared for Customer discount

If a different percentage (lower or higher percentage) is entered, it will reset back to the percentage as added on the Accounting information tab of the debtor (customer / client) account.

Customer discount automatically added if the "Customer discount" percentage is added on the Accounting information tab of the debtor (customer / client) account and the "Apply invoice discount" setting is selected, will not clear or reset. If you wish to change the percentage to 0%, you need to edit the Invoice and change the discount percentage.

Example of Customer discount percentage

To allow item discount for a debtor (customer / client):

To allow a specific percentage of discount to a debtor (customer / client) on sales documents (Invoices, Credit notes and Quotes) for a specific stock item (item discount), you need to do the following basic settings:

- The Customer discount percentage (which you will allow for a specific debtor (customer / client) account) must be specified on the Accounting information tab of Debtors (Default ribbon).



- The "*Apply invoice discount*" field for the stock item on which you will allow discount, must be selected on Stock items (Default ribbon).

  Apply invoice discount - selected



Apply invoice discount - not selected



Selecting Stock items



In this example the "Apply invoice discount" field is selected for the Drill press and the "Customer discount" percentage is set to 10% for the debtor (customer / client) account. The 10% discount will be applied for the Drill press.

In this example the "Apply invoice discount" field is not selected for the Compressor and the "Customer discount" percentage is set to 10% for the debtor (customer / client) account. No discount will be applied for the Compressor.

You may overtype the percentages if you wish to, you may overtype a percentage or enter a percentage, if no discount is applicable to an item.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Context menu - Adjustment

The "*Adjustment*" option (on the Documents context menu) to edit the document header of a posted document is not implemented in osFinancials5/TurboCASH5.

Unposted documents may be edited before a document is posted to the ledger.

Once a document is posted (updated) to the ledger, the document cannot be edited. You may access a

posted document by double clicking on it (Documents selection screen).

For example; it may happen sometimes that a debtor (customer / client), relocates and still have outstanding invoices with the incorrect (old) address.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Create backorders to deliver

When processing documents, and there are any Backorders outstanding, a list of Backorders will be displayed.



You may select the item on the list and the quantities (in the Items) will be added to the document lines and will be removed from this list.

Backorders to deliver - Invoices

If an outstanding backorder exists for a debtor (customer / supplier account), you may use this option to create a new Invoice for the outstanding backorders to deliver.

To create backorders to deliver:

1. Select the "*Invoices*" document type.
2. Select the document to create backorders to deliver.
3. Right-click and select Documents → Backorders to deliver option on the context menu. A new Invoice will be created.
4. You may need to edit the Invoice.



WARNING - Input Tax / Output tax

In the case of Invoices, the Input tax is used instead of the Output tax. You need to check this, and change it to the Output Tax.

The Invoice will reflect the Selling prices and the quantities as it was on the Backorders. The stock item will be removed from the Backorders screen as well as on the Backorders tabs for the Stock item and the Backorders tab of the Debtor (customer / client) account.

You may click on the Backorder icon and select another stock item to add to the Invoice.

Backorders to deliver - Quotes

WARNING - INVOICE under Quotes document type

This process is not recommended, as it will create an Invoice on the Quotes document type.



To create an Invoice from the Quotes document type for Backorders to deliver:

To create backorders to deliver:

1. Select the "*Quotes*" document type.
2. Select the document to create backorders to deliver.
3. Right-click and select Documents → Backorders to deliver option on the context menu. A new Invoice will be created in the Quotes document type.
4. You may need to edit the Invoice / Quote.



WARNING - Input Tax / Output tax

In the case of Invoices, the Input tax is used instead of the Output tax. You need to check this, and change it to the Output Tax.

The Add to backorder icon is added (after the Backorder icon).



This will list the Outstanding items on Backorder. You may click on the list tab to view a list of the debtor (customer / client) accounts.



Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Context menu - Confirm

Document listing → Documents per account

Unprinted document listing only included posted documents - Confirmed unposted documents is excluded.

Posted document status

By default, the "*Status*" of a posted (updated to the ledger) document (i.e. Invoice, Credit note, Purchase or Supplier return), is set as "*Posted*". Posted documents cannot be edited.

Unposted document status

By default, the "*Status*" of an unposted document (i.e. Invoice, Credit note, Purchase or Supplier return), is set as "*Unposted*". Unposted documents can be edited.



Note the "*Status*" is set to "*Open*" for an unposted document, and cannot be changed. You may edit the Unposted document.

After posting an unposted document (i.e. Invoice, Credit note, Purchase or Supplier return), the "*Status*" will be displayed as "*Posted*".

Confirmed unposted document status

To change an unposted document status from "*Open (Unposted)*" to "*Confirmed*":

Choose the unposted document (i.e. Invoice, Credit note, Purchase or Supplier return), right-click and select Documents → Confirm on the context menu.

The "*Status*" of the unposted document will change from "*Open*" to "*Confirmed*".

Once document status, is set to "*Confirmed*" you may filter the document status for a Confirmed documents.



Confirmed posted document status

Posting a "*Confirmed*" unposted documents (i.e. Invoices, Credit notes, Purchases or Supplier returns), it will change the document's "*Status*" from "*Confirmed*" to "*Posted*".

Created with the Standard Edition of HelpNDoc: Free Qt Help documentation generator

Context menu - Spreadsheet import

This option allows you to export and import documents in a Spreadsheet.

To import documents:

1. On Input → Documents (Documents list), select the Document type.

2. Right-click and select the Documents → Spreadsheet import option on the context-menu.



3. The "*Data Import Export*" screen is displayed:



4. Select

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Context menu - Print

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Context menu - Print barcodes

This option allows you to print barcodes for the stock items included on sales documents (i.e. Invoices, Credit notes or Quotes) or purchase documents (i.e. Purchases, Supplier returns or Orders).

You may also print the Barcode or the Yagoda barcode from the Reports → Stock → Print labels menu on the Reports ribbon.

To print barcodes for selected stock items:

1. On Documents (Documents list screen) Default ribbon), select the Document type, if the correct document type is not selected.
2. Select the Document(s), right-click and select Print → Barcodes on the context menu. This will print the labels of all the stock items included on a selected document.

If you need to select multiple documents, press the Ctrl or the Shift key and click on each document, for which you need to print barcodes.

An example of a printed barcodes for a selected document, is as follows:



Barcodes will be printed for each stock item included in a selected document.

It will display / print the following for each stock item included in a document:

1. Stock code
2. Stock item description
3. Barcode
4. Selling price (exclusive of Tax (VAT/GST/Sales tax).

Labels will be printed for each stock item on a selected document.

If more than one document is selected, labels will be printed for each of the selected documents.

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Context menu - Print labels

This option allows you to print the postal address labels of the selected debtor (customer / client) account(s) for which sales documents (i.e. Invoices, Credit notes or Quotes) were processed.

If purchase documents (i.e. Purchases, Supplier returns or Orders) were selected, it will print the postal address labels for creditor (supplier / vendor) account(s).

You may also print the Postal address labels or Delivery address labels for debtor (customer / client) accounts from the Reports → Debtors → Print labels menu on the Reports ribbon.

You may also print the Postal address labels or Delivery address labels for creditor (supplier / vendor) accounts from the Reports → Creditors → Print labels menu on the Reports ribbon.

To print labels for selected stock items:

1. On Documents (Documents list screen) (Default ribbon), select the Document type, if the correct document type is not selected.
2. Select the Document(s), right-click and select Print → Labels on the context menu. This will print the postal address labels of the selected debtor (customer / client) or creditor (supplier / vendor)

account(s).

An example of a printed postal address labels, is as follows:



Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Context menu - Others

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Context menu - Others - Import

This option allows you to import documents from a valid exported txf file (exported in the Export - Documents option on the Setup ribbon).

Document Export / Import plugin - Manual - Shop - Licence: Once-off

The Document Export / Import plugin allows you to export sales documents (invoices, credit notes and quotes) and purchase documents (purchases, supplier returns and orders) to a TurboCASH Exchange (.txf) or a Comma Separated Value (*.csv) file format. You may then select an exported documents file (context menu Others → Export) and import the exported file in the (context menu Others → Import) options in the documents grid.*

To import documents from a valid txf file:

1. On the Default ribbon, select Documents (Documents list screen), select the Document type.

2. Right-click and select the Others → Import option on the context-menu.



3. The "*Open*" screen is displayed:



4. Select a valid "*TurboCASH Exchange file (*.txf)*" file and click Open.

The valid "TurboCASH Exchange file (.txf)" file is generated in the Export - Documents option on*

the Setup ribbon. This will only include the documents on the dates selected to include in the export file.

5. On the "*Debtor accounts*" list screen, click on any of the OK, Close or Open buttons. The Documents will be imported.

If an invalid account code is included in the "TurboCASH Exchange file (.txf)" file (generated in the Export - Documents option on the Setup ribbon), a message will be displayed:*



The document (listed on the message screen) will not be imported.



id	Document no.	Date	Description	Due date	Accid	Printed	Amount incl.	Tax amount	Reference	Document group 1	Document group	Account no.	Salesperson	Amount excl.	Due	Status
107	IN000050	19/06/2021	A-ONE Suppliers	19/06/2	29		3,450.00	450.00	SR000003 4562					3,000.00	3,450.00	
106	IN000049	17/06/2021	A-ONE Suppliers	17/06/2021	29		3,450.00	450.00	SR000002 4562			C2AONES		3,000.00	3,450.00	
105	IN000048	24/06/2021	BEST Suppliers	24/06/2021	30		3,450.00	450.00	SR000001 3532			C2BESTS		3,000.00	3,450.00	
104	IN000047	09/06/2021	A-ONE Suppliers	09/06/2021	29		3,450.00	450.00	PU000006 3532			C2AONES		3,000.00	3,450.00	
103	IN000046	26/06/2021	A-ONE Suppliers	26/06/2021	29		3,450.00	450.00	PU000005 4562					3,000.00	3,450.00	
102	IN000045	30/06/2021	Mr. AB Green	30/06/2021	54		2,875.00	375.00	CR000003 C-103			D1ABGRE		2,500.00	2,875.00	
101	IN000044	24/06/2021	Mr. AB Green	24/06/2021	54		5,750.00	750.00	QU000005 C-103					5,000.00	5,750.00	
100	IN000043	20/06/2021	Mr. Roger Smith	20/06/2021	28		1,150.00	150.00	QU000004 D-102			D1ROGSM		1,000.00	1,150.00	
99	IN000042	22/06/2021	Mr. Roger Smith	22/06/2021	28		2,300.00	300.00	CR000002 D-102					2,000.00	2,300.00	
98	IN000041	30/06/2021	Mr. AB Green	30/06/2021	54		5,750.00	750.00	CR000001 D-101			D1ABGRE		5,000.00	5,750.00	
97	IN000040		Mr. AB Green		54		5,750.00	750.00	IN000020 A-103-					5,000.00	5,750.00	
96	IN000039	23/10/2021	ABC-Office-Supplies	23/10/2021	53		3,450.00	450.00	SR000005 4562-A					3,000.00	3,450.00	
95	IN000038	26/06/2021	ABC-Office-Supplies	26/06/2021	53		3,450.00	450.00	SR000004 4562-A			C2ABCOS		3,000.00	3,450.00	
94	IN000037	23/10/2021	ABC-Office-Supplies	23/10/2021	53	0	3,450.00	450.00	PU000008 4562	Empty			Empty	3,000.00	3,450.00	
93	IN000036		Mr. AB Green		54		2,875.00	375.00	CR000004 C-103		Empty	D1ABGRE		2,500.00	2,875.00	Unposted
92	IN000035	25/06/2021	ABC-Office-Supplies	25/06/2021	53		3,450.00	450.00	PU000007 4562			C2ABCOS		3,000.00	3,450.00	
91	IN000034	30/06/2021	Mr. AB Green	30/06/2021	54		5,750.00	750.00	IN000019 D-101			D1ABGRE		5,000.00	5,750.00	
90	IN000032		Mr. AB Green		54		5,750.00	750.00	IN000022 C-103					5,000.00	5,750.00	
89	IN000031	24/06/2021	Mr. Roger Smith	24/06/2021	28		2,300.00	300.00	IN000018 D-102			D1ROGSM		2,000.00	2,300.00	
88	IN000030	30/06/2021	Mr. AB Green	30/06/2021	54		5,750.00	750.00	IN000021 C-103			D1ABGRE		5,000.00	5,750.00	
87	IN000029	20/06/2021	Mr. Mike Davies	20/06/2021	27		2,875.00	375.00	IN000017 C-103			D1MDAVI		2,500.00	2,875.00	
86	IN000028	17/06/2021	Mr. Roger Smith	17/06/2021	28		3,450.00	450.00	IN000016 C-102			D1ROGSM		3,000.00	3,450.00	
85	IN000027	15/06/2021	Mr. Mike Davies	15/06/2021	27		1,150.00	150.00	IN000015 D-101			D1MDAVI		1,000.00	1,150.00	
84	IN000026	12/06/2021	Mr. Roger Smith	12/06/2021	28		2,300.00	300.00	IN000014 D-102			D1ROGSM		2,000.00	2,300.00	
83	IN000025	10/06/2021	Mr. Mike Davies	10/06/2021	27		1,725.00	225.00	IN000013 C-103			D1MDAVI		1,500.00	1,725.00	
82	IN000024	07/06/2021	Mr. Roger Smith	07/06/2021	28		3,450.00	450.00	IN000012 C-102			D1ROGSM		3,000.00	3,450.00	
81	IN000023	05/06/2021	CASH CUSTOMER	05/06/2021	42		1,150.00	150.00	IN000011 D-101			D1CASHC		1,000.00	1,150.00	
72	IN000022	30/06/2021	Mr. AB Green	30/07/2021	54	45	5,750.00	750.00	C-103	Document group 1f		D1ABGRE	Russell	5,000.00	5,750.00	
67	IN000021		Mr. AB Green		54	1	5,750.00	750.00	C-103					5,000.00	5,750.00	
	29						104,650.00	13,650.00						91,000.00	104,650.00	

"Reference" column, the source of the exported document Document number and the "Your reference" field of the original source document will be listed.

The new document numbers will be generated numerically from the last document in the Set of Books. In this example, the last existing document number ends with IN000022 and the first document imported starts with IN000023.

Comments of the original source document will also be imported.

Document group 1 and Document group 2 - will not be imported.

Salesperson - will not be imported.

Status - All documents will be imported as unposted documents.

Printed - All imported documents will be imported as unprinted.

If there are any imported documents, that you do not wish to keep, go to the Default ribbon, and select Edit → Delete - Documents to delete the documents, if necessary.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Output with HelpNDoc's Advanced Project Analyzer

Context menu - Others - Totals

On the Document list screen, select the document type for sales documents (i.e. Invoices, Credit notes or Quotes) or purchase documents (i.e. Purchases, Supplier returns or Orders).

To select multiple documents, press the Ctrl key and keep it down while selecting the other documents to include in the Totals.

Right-click and select Others → Totals option on the context menu. This will list an information screen with the calculated totals of selected document(s).



This will display the following on an information message:

- Total inc - Total amount of the selected documents inclusive of Tax (VAT/GST/Sales tax).
- Total excl - Total amount of the selected documents exclusive of Tax (VAT/GST/Sales tax).
- Total open - Total of selected documents; with outstanding amounts.
- Total records - The total number of documents selected.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Context menu - Others - Show details

By default, the details of each document is listed on the Documents list screen in columns. You may select to show the basic details of the items, quantities, remarks and comments added to documents. When a document is selected or the scrolled on the list, the details will be displayed.

The detail will be displayed regardless of whether you select other document types.

The "Show detail" will only be disabled when you:

- *Select the Other → Hide option context menu option on the Document entry list screen.*
- *Select the Tools → Close active forms (Setup ribbon) option.*
- *Close and reopen the Set of Books.*

To show or hide the details on a selected document:

1. On the Default ribbon, select Documents (Documents list screen), select the Document type, if the correct document type is not selected.
2. Right-click anywhere on the Documents list screen or on a selected document. On the context menu, select the Others → Show details option.



3. When a document is selected, it will display the details of the document.



The details will display the following:

- Name of debtor (customer / client) or creditor (supplier / vendor)
- Document number
- Stock item description
- Quantity
- Price (Inclusive of tax)
- Remarks (if entered)
- Comments (if entered)

To turn the Show details off:

Right-click and select the Others → Hide option on the context menu.

Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Context menu - Others - Open item link

The Open item link option will launch the "*Open item link*" form for the debtor (customer / client) account associated with the selected document, if Invoices, Credit notes or Quotes document type is selected.

If purchase documents, (Purchases, Supplier returns or Orders document type is selected, the "*Open item*

link" form for the creditor (supplier / vendor) account associated with the selected document will be launched.

You may view all the transactions and process open item links for the selected account. See - Open item link.

To launch the Open item link for a selected document:

1. On Default ribbon, select Documents (Documents list screen), select the Document type, if the correct document type is not selected.

2. Right-click on a selected document. On the context menu, select the Others → Open item link option.

This will launch the "*Open item link*" form for the debtor (customer / client) account; or the creditor (supplier / vendor) account; associated with the selected document.



Only the unlinked (outstanding) transactions will be listed.

You may link the transactions to the documents.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Context menu - Document links

To be advised.

Created with the Standard Edition of HelpNDoc: Simplify Your Help Documentation Process with a Help Authoring Tool

Document entry

Once you have selected a specific Document type and the Debtor account or Creditor account or an existing Document (to edit), the Document type entry (Invoice, Credit note, Quote, Purchase, Supplier returns or Orders) screen will be initiated.

This Document entry screen displays similar information as found in a source document (e.g. Invoice, etc.) such as the details of the selected Debtor or Creditor account, etc. You only need to select the stock items, enter quantities, discounts, comments, etc. or to edit the transactions, discounts, comments, etc.

Once a document (Invoices, Credit notes, Purchases or Supplier returns) have been updated (posted) to the ledger, you cannot edit or change these documents.

The Document entry screen can be accessed for existing Invoices, Credit notes, Purchases or Supplier returns as follows:

1. Unposted documents - This is the default option on the Document list screen. Any document (Invoice, Credit note, Quote, Purchase, Supplier returns or Orders) may be edited, if it is not yet updated or posted to the ledger.
2. Posted documents - If you deselect (remove the tick) in the Unposted option on the Document list screen, you may view the documents as they were originally processed in the Document entry screen before these documents were updated (posted) to the ledger.

Quotes and Orders will not be listed, if the Unposted field is not selected on the Document list screen. The reason for this is, that quotes and orders cannot be posted (updated) to the ledger. Quotes need to be converted to Invoices and Orders need to be converted to a Purchase documents.

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Document entry form - Unposted documents

The Document entry screen is as follows:



The layout of the Document entry screen displays all active fields, which may be edited (options to select and entering or editing of data) first, and all other fields (which cannot be changed) is displayed in the bottom section of this screen.

The Document entry screen consists of the following sections:

1. Title bar: - Displays the following:

    a) Telephone number - The telephone number as entered in the Phone 1 field of the debtor (customer / client) or creditor (supplier / vendor) account.

    b) Account number or code of the selected Debtor account or Creditor account for which you need to create a document will be displayed.

    c) Document type - Invoice, Credit note, Quote for sales documents or in the case of creditor (supplier / vendor) or documents it will display Purchase, Supplier returns or Orders.

    d) Document number - If you create a new document; the next document number will be displayed (as generated). If you have selected a specific document to edit, the number of the selected document will be displayed.

It is recommended that you check your document numbers and change the document

numbers, if necessary in Setup → Documents setup before starting to process your first document.

If you have created more than one user in Setup → Access control, you may set to Use General Numbers and select the Default User in Setup → Documents setup.

e) Quantities on hand - The Quantities on hand of the selected trading stock item.

The Quantity on hand is only displayed for the following stock item types:

- *Default*
- *Option item*
- *BOM Production*

For all other stock item types it will not be displayed.

2. Header section: - You may enter or select the following where necessary:

a) Your reference - Enter the reference number if received from the debtors (customers / clients) or creditors (suppliers). When printing the documents, the reference number will be displayed and make it easier for the debtors (customers / clients) or creditors (suppliers) to link and trace the transaction in their records.

b) Salesperson – Select from the list for Invoices, Credit notes or Quotes only.

You may select the default salesperson for each debtor account. When sales documents are generated and the debtor (customer / client) account is selected, the default salesperson will be displayed for the document or you may select any available salesperson.

Salespersons may also be selected for purchase documents (i.e. purchases, supplier returns and orders). This allows you to see who handled the purchase document.

c) Document group 1 and/or Document group 2 - Select, if you have created any document groups in Setup → Groups.

d) Date - The system date should automatically be displayed. You may enter or select the date

using the date picker (if not correct).

If your system date is incorrect, please set your operating system's date. If it is a document which you are editing, the date when the document was created will be displayed.

e) Due date - The due date will automatically be calculated as the number of days entered in the Due days field of the Debtors (Default ribbon) (Accounting information tab). If this field is left blank for the Debtor account, or a value of (zero) 0 is entered, this due date will be the same as the date of the document. The same principles apply to Creditor accounts.

f) Postal address - The postal address, as entered on the Debtors (Default ribbon), and in the case of creditors in the Creditors (Default ribbon), will be displayed. You may over type this address for a specific document, but need to change the address details on the Debtors / Creditors (Default ribbon), if the address for a debtor or a creditor has permanently changed.

g) Delivery address - The delivery address, if entered on the Debtors (Default ribbon) (Delivery address tab), and in the case of creditors in the Creditors (Default ribbon) (Delivery address tab), will be displayed. You may enter or over type this address for a specific document, but need to change the address details on the Debtors / Creditors (Default ribbon), if the address for a debtor or a creditor has permanently changed.

h) Message – Message (up to 3 lines will be printed on the selected layout files for documents. By default, the message, if entered for the specific document type on Setup → Documents setup (Setup ribbon) will be displayed.

Messages entered in the Message fields of the following screens, will be displayed on the Message fields in the Document entry screen's Header section:

- *Edit → Repeating invoices – The message as entered (and if it is selected to replace message by) will be displayed.*
- *Calendar – Repeating invoices - Event. The message as entered will be displayed.*

Data may also be inserted into the message fields from the following options:

- *Order number – Convert Orders to Purchase documents.*
- *Quote number – Convert Quotes to Purchase documents.*
- *Document number – Copy Document – the number of the copied document.*

3. Transaction / Remarks / Comments section: - Select and enter or edit the following:

   a) Transactions - Select the stock item and specify the quantities and discount percentages for sales to debtors (customers / clients) or purchases from creditors (suppliers / vendors).

   > *The Purchase and Purchase (no stock) stock item types will not be listed on the lookup screen when sales documents (Quotes, Invoices and Credit notes) are processed.*

   > *The Sales and Sales (no stock) stock item types will not be listed on the lookup screen when purchase documents (Orders, Purchases and Supplier returns) are processed.*

   b) Comments (optional) - You may add comments, or additional information, for transactions or stock items.

   > *Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.*
   >
   > *You may select Expand to show remarks or Collapse to hide remarks on the context menu.*

   c) Speed buttons (icons) - The following eight (8) icons (speed buttons) are conveniently placed on top of the rows to edit and process documents:

      i) +Open fast add / -Close fast add - Open or Close the Item lookup as a part of the "*Document entry*" form.

      ii) ^D:Delete - Delete a selected transaction. (F12 or Ctrl+D).

      iii) F12:^N:Insert - Insert a row directly above the selected transaction. (Ctrl+N).

      iv) F7:Exclusive - Switch to the exclusive mode.

      v) F7:Inclusive - Switch to the inclusive mode.

      vi) F8:Discount - This will allow you to enter a percentage for discount.

      vii) F9:Comment - This will change a line to a comment line to insert a comment or additional information for the transaction.

      viii) F10:Delete all - This will delete or clear all the transactions and/or comments entered in this document.

      ix) F11:Copy - This will display a list of documents of which you may select to copy the content (transactions and comments). All the transactions and comments for the

selected document will be copied after the last line.

New keyboard shortcuts:

- *Alt+F3 - Focus on Quantity ship field.*
- *Ctrl+F3 - Focus on Fast add item (code/barcode/serial) field. Then press scan.*

d) Context menu - You may right-click and use the following options:

i) Sequence - Move up, Move down and Sort on stock code options on the context menu to change the sequence of the document lines. This will change the sequence of transactions and/or comments on document layout files when printing or reprinting documents.

ii) Enter total - You may also enter an amount to round the document (e.g. Invoice total).

This will automatically recalculate and adjust the inclusive totals and tax amounts proportionally for all items included in the document.

4. Footer section: - These fields cannot be edited and displays the following information:

a) Debtor / Creditor - The Account code, or Number, of the selected Debtor / Creditor account.

b) Document number - The Document number for the selected document type.

c) Credit facilities - It is good practice to train your eye to view the available balance quickly to see if sufficient credit facilities are available. This area of the screen displays the following:

i) Current balance - osFinancials5/TurboCASH5 will reflect the current account balance for the selected Debtor or Creditor account.

ii) Credit limit - The credit limit, if entered on the Debtors (Default ribbon) (Accounting information tab), and in the case of creditors in the Creditors (Default ribbon) (Accounting information tab) menus.

iii) Available balance - osFinancials5/TurboCASH5 will calculate and display the amount available on the credit facility Credit limit minus the Available balance). If the current balance exceeds the credit facility when you enter transactions,

osFinancials5/TurboCASH5 will inform you accordingly.

d) Totals - The totals of the transactions on the document (excluding tax (VAT/GST/Sales Tax)) Discount amount and the Document total (payable / due).

5. Status bar: - The statusbar of the Document entry screen is only displayed if the document is not launched from the sidebar. It displays the similar information as in the titlebar. It also displays the following applicable to debtor (customer / client) or sales documents (i.e, Invoices, Credit notes, Quotes).

a) Selling price - The selected selling price (Selling price 1 / 2 / 3) or the default selling price as set in the Debtors (Default ribbon) (Accounting information tab) for the debtor (customer / client) account.

b) Customer discount - If you have entered any percentage for Customer discount on the Debtors (Default ribbon) (Accounting information tab), and the "*Apply invoice discount*" field is selected on Default → Stock items for the selected stock item, the customer discount percentage for the selected Debtor account will be displayed.

You may over type the discount with a zero (0) percentage, if you do not wish to allow discount for this transaction in the Discount Column of the Transaction section of this screen. If you wish to grant a lower percentage or higher percentage of discount, you may over type the percentage with the percentage of discount you wish to allow.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Delete transactions / comments in documents

Sometimes you may have entered a number of transactions and/or comments in a document, and you wish to delete a transaction or a comment in the Document entry screen.

To delete a transaction or a comment in a document:

1. Select the row or line for the transaction or comment which you wish to delete.

Once again, make sure absolutely sure that the correct stock item, transaction, or comment is selected.

2. Click on the ^D:Delete icon; or (Ctrl + D). A confirmation message is displayed:

   "Do you wish to delete this Line?"

3. Click on the Yes button. The selected transaction, or comment, will be deleted or removed.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Insert transactions / comments in documents

Sometimes you may have entered a number of transactions in a document, and you wish to insert a transaction or a line in a specific place in the document. You may need to do this to insert another transaction, or to insert a comment for a selected transaction.

To insert a line for a transaction or a comment in a document:

1. Select the row or line into which you wish to insert a transaction or enter a comment.
2. Click on the ^N:Insert icon (Ctrl + N). A new blank line or row above a selected transaction or comment line will be inserted.
3. Enter the transaction in the inserted row, or change the inserted row to a Comment.

Created with the Standard Edition of HelpNDoc: Save time and frustration with HelpNDoc's WinHelp HLP to CHM conversion feature

Tax Inclusive / Exclusive - Documents

You may select to change the amounts to be displayed as exclusive or exclusive of Output VAT/GST/Sales Tax on all sales documents for debtors (customers / clients) (i.e. Invoices, Credit notes and Quotes) and exclusive or exclusive of Input VAT/GST/Sales Tax on all purchase documents for creditors (suppliers) (i.e. Purchase, Supplier returns and Orders).

The selling price amounts for debtor (customer / client) documents are automatically inserted in the documents when a stock item is selected.

Please take note of whether these selling prices are entered or adjusted Inclusive or Exclusive of

VAT/GST/Sales Tax on Stock items (Default ribbon), or if you adjust the selling prices in the Input → Adjust stock menu (Selling prices tab) on the Default ribbon.

The purchase (cost) price amounts for creditor (supplier / vendor) documents are automatically inserted in the documents when a stock item is selected.

By default, the amounts are inserted or entered (if manually over-typed) Exclusive of VAT/GST/Sales Tax on the amount column the document lines. To enter and view amounts Inclusive of VAT/GST/Sales Tax, you may select (tick) the "Default inclusive for documents" field option on Setup → Stock information menu (Setup ribbon).



Tax Exclusive mode

To set the Exclusive of Tax (VAT/GST/Sales tax) mode:

1. Click on the F7:Exclusive icon.



2. The amount will change to the selected mode, and will be displayed in the transaction section, as well as at the bottom of the Document entry screen.

You may press the F7 key or click on the F7:Exclusive / F7:Inclusive icons on the "Document entry" screen for unposted documents to toggle between the Inclusive or Exclusive modes.

Tax Inclusive mode

To set the Inclusive of Tax (VAT/GST/Sales tax) mode:

1. Click on the F7:Inclusive icon.



2. The amount will change to the selected mode, and will be displayed in the transaction section, as well as at the bottom of the Document entry screen.

Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Discount - Documents

There are two basic methods to allow a percentage of discount to your debtors, or to enter the discount received from your creditors (suppliers / vendors) at the time of the sale or purchase transaction. These discounts are often referred to as trade discounts.

- Item discount - This option allows you to specify the percentage of discount in the Discount percentage column on the Document entry screen.
- Invoice discount - This option allows you to specify a percentage of discount, which is applicable to all the transactions in the document.

If you have already specified a percentage in the discount percentage column, this percentage will be calculated as well for the item.

It is recommended that you use only one of these methods (either the item discount or the Invoice discount), unless you wish to allow overall discount on all the transactions including those transactions that already has a discount specified. Both of these methods can be applied to debtors (customers / clients) and creditors (suppliers / vendors).

- Change invoice total - You may allow or process discount on the document total, e.g. Rounding discount or discontinued cents, etc.).

If discount is processed on unposted Invoices or Quotes, you may need to reset or clear the discount. The "Redo discount on document" option is also available for posted Invoices, but cannot be cleared as you may not edit a posted Invoice.

Discount received

On the other hand, you may use price list received form your creditors (suppliers / vendors), which is the normal selling price. Your creditors (suppliers / vendors) may give you a trade discount at the time of the purchase. This discount is reflected on Purchase documents, Supplier return documents and Orders). When these Purchase documents are updated (posted) to the ledger, the net cost price (the purchase price less discount) at the time of the purchase will be recorded as a transaction. This will reduce the cost prices of your purchases, and will consequently affect the gross profit.

Discount allowed

Line discount

This feature is used to calculate and record the trade discounts or other discounts which you may allow to your debtors at the time of the sale transaction. This discount is reflected on the sales source document (Quote, Invoice or Credit note) and will reduce the selling price on the sales document. When these sales source documents are updated (posted) to the ledger, the net selling price (selling price less discounts) will be recorded as a transaction. This discount will reduce the selling price of the sales, and consequently your gross profit will be affected.

Overall discount

You may allow discount to all items selected in the document lines.

To allow overall discount to a debtor (customer / client):

1. Click on the F8:Discount icon. The "*Enter overall discount*" screen is displayed:



2. Enter the percentage for the overall discount you wish to allow to your debtor (customer / client), and press the Enter key on your keyboard. This discount percentage will be applied to each item.

You may overtype the discount percentage, if required. Please do not enter any negative percentages.

If you print the Invoice, the Item discount and the Invoice discount will be displayed in the % Discount column.

- *If you confirm and convert a Quote to an Invoice, and you have entered any item and/or Invoice discounts, these discounts will reflect on the converted Invoice.*
- *If you have generated repeating invoices, which include any discounts, these discounts will also be copied to the new Invoice.*
- *If you have copied transactions from Invoices, which include any discounts, these discounts will also be copied to the new Invoice.*

Discounts should be entered or specified on Credit notes exactly as they were entered or specified on the original Invoice for which the Credit note is issued.

Customer discount on items

If discount is processed on unposted Invoices or Quotes, you may need to reset or clear the discount. The "Redo discount on document" option is also available for posted Invoices, but cannot be cleared as you may not edit a posted Invoice.

To allow item discount for a debtor (customer / client):

To allow a specific percentage of discount to a debtor (customer / client) on sales documents (Invoices, Credit notes and Quotes) for a specific stock item (item discount), you need to do the following basic settings:

- The Customer discount percentage (which you will allow for a specific debtor (customer / client) account) must be specified on the Debtors - Accounting information tab (Default ribbon).



- The "*Apply invoice discount*" field for the stock item on which you will allow discount, must be selected on Stock items (Default ribbon).

  Apply invoice discount - selected



Apply invoice discount - not selected



Selecting Stock items



In this example the "Apply invoice discount" field is selected for the Drill press and the "Customer discount" percentage is set to 10% for the debtor (customer / client) account. The 10% discount will be applied for the Drill press.

In this example the "Apply invoice discount" field is not selected for the Compressor and the "Customer discount" percentage is set to 10% for the debtor (customer / client) account. No discount will be applied for the Compressor.

You may overtype the percentages if you wish to, you may overtype a percentage or enter a percentage, if no discount is applicable to an item.

Negative / Positive discount percentages

Negative percentage

Adds to selling price

Invoice: IN000035			Date:	2022/05/01		Account no.:		D1MDAVI
Description	**Unit**	**Qty**	**Price**	**Disc%**	**Exclusive**	**Tax%**	**Tax**	**Inclusive**
Drill press	Each	1	1,000.00	-10.00%	1,100.00	15.00%	165.00	1,265.00
	Total				1,100.00		165.00	1,265.00

Positive percentage (Normal)

Subtracts from selling price

Invoice: IN000035			Date:	2022/05/01		Account no.:		D1MDAVI
Description	**Unit**	**Qty**	**Price**	**Disc%**	**Exclusive**	**Tax%**	**Tax**	**Inclusive**
Drill press	Each	1	1,150.00	10.00%	900.00	15.00%	135.00	1,035.00
	Total				900.00		135.00	1,035.00

An example of a printed layout file, which includes the customer discount for a specific stock item, is as follows:



Rounding discount

You may allow a total discount on the Invoice, for example rounding of the Invoice for discontinued coins, etc.

To change the Invoice total:

Right-click anywhere in the Document lines or on the Document footer section of the " *Document entry*" screen, and select the "*Enter total*" option on the context menu.



Enter a new total (inclusive of Tax (VAT/GST/Sales tax) for the Invoice on the " *Enter new inclusive total*" screen and press the Enter key.



The new Invoice total will be displayed. The Inclusive and Exclusive amounts (as well as the Tax) for each item will automatically be recalculated accordingly and adjusted.



Types of discount

There are basically two types of discount:

- Trade discount - This discount is allowed to your debtors (customers / clients) for cash sales or to a special classification or group of debtors (customers / clients), e.g. trade customers, retailers, etc. is allowed at the time when you sell items or services to your debtors (customers / clients).

> *This discount is usually deducted from the selling price at the time of sale. Only the net selling price is reflected, and no discounts are physically recorded as a transaction. This discount will reduce the selling price of the sales and consequently your gross profit will be affected.*

- Discount allowed for the early settlement of accounts - This discount is allowed to your debtors (customers / clients) at the time of the settlement of their account. You may agree with your customers to allow a certain percentage of discount allowed, e.g. 2½ %, if they settle the full amount on an Invoice within 30 days.

> *This discount is recorded when a debtor (customer / client) settles the full Invoice within the specified time. This discount needs to be entered as an expense in a Discount Allowed account, will reduce the net profit, and will have no effect on the gross profit.*

Created with the Standard Edition of HelpNDoc: Powerful and User-Friendly Help Authoring Tool for Markdown Documents

Insert comments - Documents

Comments

Comments are additional information which can be entered when processing documents. This additional information will be printed on layout files for sales documents (e.g. Invoices, Credit note and Quote) and purchase documents (e.g. Purchases, Supplier returns and Orders).

Information entered in comments can be used to find and track specific invoices, etc.

By default, comments is inserted below a selected item. The option "Append notes below item" (Setup → Documents setup (Setup ribbon)) is added to set the preference if comments should be added before, or below (default option), a selected item when processing documents and printing comments on layout files.

The default "Append notes below item" setting is selected (ticked). It will display on document lines and document layout files as follows:

1. *Item*
2. *Remark*
3. *Comment*

If the "Append notes below item" setting is not selected. It will display on document lines and document layout files as follows:

1. *Comment*
2. *Item*
3. *Remark*

To insert a comment in a document:

1. Select the row or line directly underneath the transaction for which you wish to insert a comment.

   If you have any other transactions below the selected line or row, which you wish to keep, it is recommended that you click on the ^N:Insert icon, or press the Ctrl + N keys to insert a line or row before you change the selected line to a comment.

   You should note that if any information or a transaction is displayed in a selected line, that information would be lost for the selected line or row.

2. Click on the F9:Comment icon.



3. Enter the comment for the stock item, or transaction, and click on the OK button. The comment will be transferred into the selected line or row and will display as follows on the Document entry form:



You may double-click on a selected comment to edit an existing comment.

You may also click on the + (before stock item code) to add a remark (additional information) for a stock item.

This remark will also be printed before the comment (if added) on document layout files.

[*Search (Investigator)*]

- *Comments entered in document lines are searchable.*
- *Remarks is not searchable.*

4. Press the Enter key on your keyboard to proceed to the next line or row.

Although the full comment is not displayed on the comment line or row, it will be displayed as entered on the printed d
(transaction section). For example;



Invoice: IN000022		Date:	2021/06/30		Account no.:		D1A
Description	Unit	Qty	Price	Disc%	Exclusive	Tax%	Tax	In
Compressor	Each	2	1,500.00		3,000.00	15.00%	450.00	3,
Compressor remark								
30 Days money back guarantee. Please use high pressure sprayguns and pipes with compressor! Serial number: XEF-0018-00								
Drill press	Each	2	1,000.00		2,000.00	15.00%	300.00	2,
Drill remark								
Serial number:DXP-200-01501 Serial number:DXP-200-01502								
	Total				5,000.00		750.00	5,

5. You may proceed to enter any further transactions for the debtor (customer / client) or creditor (supplier / vendor). If you are finished, click on the Esc key on your keyboard to exit (close) the Stock item lookup screen, and to return to the Document list screen.

Serial number tracking

Should you for example, enter a serial number in the comment of a document, you may locate it on the Search - Investigator. To do this:

1. On the Default ribbon, select Search (Ctrl + F3). The "*Investigator*" screen will be displayed.
2. Enter the serial number.
3. Click on the Search now button.
4. The sales document (e.g. Invoices, Credit note or Quote) and purchase documents (e.g. Purchases, Supplier returns or Orders) containing that serial number will be listed. To display the selected document, simply double-click on it.

Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

Delete all transactions and comments - Documents

If you have entered transactions and/or comments in a Document entry screen, you may wish to delete all

the transactions and comments, if any, in the document.

To delete all the transactions and comments:

1. Click on the F10:Delete all icon. A confirmation message is displayed:

   Are you sure you want to clear all the entries in this Invoice?

2. Click on the Yes button, if you are absolutely sure. All the transactions and comments will be removed and deleted from this document.

If you have clicked on the F10:Delete all icon by accident; or if you want to delete only a few transactions and/or comments, click on the No button. You may then click on the F12:^D:Delete icon, or press the F12 key or the Ctrl + D keys, to delete only the selected lines or rows.

If you have entered any overall discount for this Invoice, you need to click on the F8:Discount icon, to set the discount to a zero percentage. The Enter overall discount screen is displayed:

Enter the zero percentage, and press the Enter key on your keyboard. You may start to enter any transactions and comments for the same document.

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Copy transactions / comments - Documents

This feature allows you to copy the transactions and the comments, if any, entered in another document into the current document.

In addition to this option, you may also copy selected documents from the following context menu options on the Document entry grid screen:

- *Documents → Copy document*
- *Documents → Copy to - Order, Purchase, Supplier return, Quote, Invoice or Credit note.*

To copy transactions and comments from a selected document to another document:

1. Create a new document or edit a selected document.

2. Click on the F11:Copy icon.

3. The options to select an existing document to copy from, is as follows:



4. Select the document number and the account code of the debtor (customer / client) (if it is Invoices, Credit notes or Quotes), or the document number and the account code of your creditor (supplier / vendor) (Purchase, Supplier return documents or Orders).

By default, the "Only this account" option will be selected (ticked). This means that only those documents generated for the selected debtor (customer / client) or the creditor (supplier / vendor) in the Document header will be listed. You may filter and search for documents using the following values:

- *Document number - Enter a valid document number and click on the Filter button.*
- *Only this account - Deselect (remove the tick) this option and click on the Filter button to list all posted as well as unposted documents of debtor (customer / client) or creditor (supplier / vendor) accounts.*
- *All documents - Select (tick) this option and click on the Filter button to list all sales documents and purchase documents.*

If the "All documents" option is selected (ticked), take note of the document numbers:

The document numbers for Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders as prefixed in the Documents setup (Setup ribbon), makes it easy to identify the document type.

In addition to these standard document numbers, the following documents may be included:

- *Stock adjustments - Document numbers prefixed with "ST" is a 7-digit document number. These are automatically generated when doing stock adjustments (changes in the quantities on hand). These stock adjustments does not show any transactions and it prints a blank Posted batch type reports.*
- *BOM (Production) stock type - Assemble / Disassemble context menu options - Document numbers prefixed with"SA" will be a 7-digit number.*
- *Project Quote - Document numbers prefixed with"D" will be a 7-digit number.*

It is recommended that you do not select these documents.

5. Select a document on the list.

6. Click on the OK button. All the transactions as well as any comments and remarks, if any, will be copied into the current document.



You may need to:

- *Edit remarks and comments.*
- *Edit the transactions (change quantities, delete items or add items, etc.).*
- *You may need to use the Move up or Move down options on the context menu (document lines section)*

to set the sequence of transactions and/or comments.

This feature can only be used to copy from sales documents for debtors (customers /clients) (i.e. Invoices, Credit notes and Quotes) and purchase documents for creditors (suppliers) (i.e. Purchase, Supplier returns and Orders).

- *If any transactions in purchase documents (i.e. Purchase, Supplier returns and Orders) are copied to sales documents (i.e. Invoices, Credit notes and Quotes) the purchase prices will be indicated. You may then select any of the selling prices for the sales documents.*
- *If any transactions in sales documents (i.e. Invoices, Credit notes and Quotes) are copied to purchase documents (i.e. Purchase, Supplier returns and Orders) the selling prices will be indicated. You may then select any of the purchase prices for the purchase documents.*

Created with the Standard Edition of HelpNDoc: Maximize Your Reach: Convert Your Word Document to an ePub or Kindle eBook

Item lookup

When processing documents, you're required to choose the stock item within the document lines section. By default, only the active stock items are displayed. If a stock item is marked as inactive (disabled) on the Stock form, it won't appear in the Stock lookup. This ensures that only active or enabled items are available for selection in the documents.

If you need to select disabled items in documents, simply check the "*Inactive*" box and click the Search button. This action will include inactive or disabled stock items in the lookup results.

There are basically three (3) options to select stock items in any open / unposted document:

1. Lookup - Click on the "*Item no.*" column of document line or when proceeding to a new line, the Lookup will automatically be launched. To edit / select an existing Item, you need to double-click on the selected item in the document line.
2. Open fast add - The icon will launch the lookup as a part of the "*Document entry*" screen (replace the header section of the document). Once finished selecting stock items, you may click on the Close fast add icon.

You may enter a valid stock code, barcode or serial number and press the Enter key in the "Fast add item (stockcode / barcode/ serial)" field in the footer section of the "Document entry" screen. This will insert the stock transaction in the document line.

Keyboard shortcuts:

- *Alt+F3 - Focus on Quantity ship field.*
- *Ctrl+F3 - Focus on Fast add item (code/barcode/serial) field. Then press scan.*

3. Button lookup - This will launch a graphical image view of images added for Stock group 1 (Setup → Groups - Stock group 1 (Setup ribbon) and the images for stock items added in the Image tab of Stock items (Default-ribbon).
4. Accounts lookup - If you have added a Financial entry stock item type, you may select a general ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account from the Accounts lookup when processing documents.

Stock item types en Document types

The selected document type will list only the stock item types:

Sales documents (Quotes, Invoices and Credit notes)	*Purchase documents (Orders, Purchases and Supplier returns)*
The following stock item types may be selected to process Sales documents:	*The following stock item types may be selected to process Purchase documents:*
Default	*Default*
Sales	*Purchases*
Sales (No stock)	*Purchases (No stock)*
Financial entry	*Financial entry*
Option item	*Option item*
Option item (No stock)	*Option item (No stock)*
BOM (Bill of Materials)	*BOM (Bill of Materials)*
BOM (Bill of Materials) - Production	*BOM (Bill of Materials) - Production*
Linked item	*Linked item*

Created with the Standard Edition of HelpNDoc: Quickly and Easily Convert Your Word Document to an ePub

or Kindle eBook

Item lookup - Default

When processing documents, you're required to choose the stock item within the document lines section. By default, only the active stock items are displayed. If a stock item is marked as inactive (disabled) on the Stock form, it won't appear in the Stock lookup. This ensures that only active or enabled items are available for selection in the documents.

If you need to select disabled items in documents, simply check the "*Inactive*" box and click the Search button. This action will include inactive or disabled stock items in the lookup results.

The standard "*Lookup*" screen is as follows:



The values and fields are as follows:

1. Code - Code is the default option. You may select the Description, Barcode, Description and extra description or Code, Description and extra description option. This will allow you to enter any valid values for a stock item. If you click on the Search button, it will list only those stock items matching the value entered.

2. Operator - None is the default. You may select an operator (i.e. "*and*" / "*or*"). These operators will add another field where you may enter values to filter the stock items. If you click on the Search button, it

will list only those stock items matching the values entered in the first search values field and/or the values entered in the second search values field.

3. Stock group 1 - You may select a stock group 1 (created / added in Groups (Stock group 1) (Setup ribbon) and linked to the stock item). This will only list those stock items linked to Stock group 1.

4. Stock group 2 - You may select a stock group 2 (created / added in Groups (Stock group 2) (Setup ribbon) and linked to the stock item). This will only list those stock items linked to Stock group 2.

5. Search by: Code, Description and Barcodes is the default options. If any of these are selected (ticked), it will change the sort sequence in which the stock items are listed.

The Auto-select tick box will only be displayed when the

(right-click) is selected (ticked). The "Auto-select" option allows you to enter any keys to filter by stock code, description, barcode, etc.

6. Status bar - This bar is located right at the bottom of the lookup screen. It will display the following details for the selected stock item:

    a) Cur: This displays the current actual quantities on hand for the selected stock item. This is the totals of the "*Quantity on hand*" field of the Values section on the Ledger tab of Stock items (Default ribbon) (as updated by posted documents) plus any unposted purchase documents.

    b) Quote: This displays the quantities of any open / unconfirmed quotes which have not yet been converted to invoices.

    c) Order: This displays the quantities of any open / unconfirmed orders which have not yet been converted to purchase documents.

    d) Exp: This displays the expected quantities on hand for the selected stock item. This is the current quantities on hand for the selected stock item. This is the totals of the "*Quantity on hand*" field of the Values section on the Ledger tab of Stock items (Default ribbon) MINUS the quantities of any open / unconfirmed quotes which have not yet been converted to invoices PLUS the quantities of any open / unconfirmed orders which have not yet been converted to purchase documents.

    e) P1: This displays the "*Selling price 1*" field of the Selling prices section on the Ledger tab of Stock items (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

    f) P2: This displays the "*Selling price 2*" field of the Selling prices section on the Ledger tab of

Stock items (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

g) P3: This displays the "*Selling price 3*" field of the Selling prices section on the Ledger tab of Stock items (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

h) LP: This displays the "*Latest cost*" (last cost price) field of the Values section on the Ledger tab of Stock items (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

The following options is not available on the Stock lookup in when selecting stock items on Reports:

- *Stock group 2 - Created / added in Groups - Stock group 2 on the Setup ribbon and linked to the stock item.*
- *Multilang - Multi-language stock item descriptions.*

Created with the Standard Edition of HelpNDoc: Protect Your Confidential PDFs with These Simple Security Measures

Item lookup - Fast add

When processing documents, you're required to choose the stock item within the document lines section. By default, only the active stock items are displayed. If a stock item is marked as inactive (disabled) on the Stock form, it won't appear in the Stock lookup. This ensures that only active or enabled items are available for selection in the documents.

If you need to select disabled items in documents, simply check the "*Inactive*" box and click the Search button. This action will include inactive or disabled stock items in the lookup results.

The +Open fast add - The icon will launch the lookup as a part of the "*Document entry*" screen (replace the header section of the document). Once finished selecting stock items, you may click on the -Close fast add icon.

The "+*Open fast add - Stock lookup*" screen is as follows:



You may enter a valid stock code, barcode or serial number and press the Enter key in the "Fast add item (stockcode / barcode/ serial)" field in the footer section of the "Document entry" screen. This will insert the stock transaction in the document line.

Keyboard shortcuts:

- *Alt+F3 - Focus on Quantity ship field.*
- *Ctrl+F3 - Focus on Fast add item (code/barcode/serial) field. Then press scan.*

The values and fields are as follows:

1. Code - Code is the default option. You may select the Description, Barcode, Description and extra description or Code, Description and extra description option. This will allow you to enter any valid values for a stock item. If you click on the Search button, it will list only those stock items matching the value entered.

2. Operator - None is the default. You may select an operator (i.e. "*and*" / "*or*"). These operators will add another field where you may enter values to filter the stock items. If you click on the Search button, it will list only those stock items matching the values entered in the first search values field and/or the values entered in the second search values field.

3. Stock group 1 - You may select a stock group 1 (created / added in Groups (Stock group 1) (Setup ribbon) and linked to the stock item). This will only list those stock items linked to Stock group 1.

4. Stock group 2 - You may select a stock group 2 (created / added in Groups (Stock group 2) (Setup ribbon) and linked to the stock item). This will only list those stock items linked to Stock group 2.

5. Search by: Code, Description and Barcodes is the default options. If any of these are selected (ticked), it will change the sort sequence in which the stock items are listed.

> *The Auto-select tick box will only be displayed when the*
>
> *(right-click) is selected (ticked). The "Auto-select" option allows you to enter any keys to filter by stock code, description, barcode, etc.*

6. Status bar - This bar is located right at the bottom of the "*Lookup*" screen. It will display the following details for the selected stock item:

    a) Cur: This displays the current actual quantities on hand for the selected stock item. This is the totals of the "*Quantity on hand*" field of the Values section on the Ledger tab of Stock items (Default ribbon) (as updated by posted documents) plus any unposted purchase documents.

    b) Quote: This displays the quantities of any open / unconfirmed quotes which have not yet been converted to invoices.

    c) Order: This displays the quantities of any open / unconfirmed orders which have not yet been converted to purchase documents.

    d) Exp: This displays the expected quantities on hand for the selected stock item. This is the current quantities on hand for the selected stock item. This is the totals of the "*Quantity on hand*" field of the Values section on the Ledger tab of the Ledger tab of Stock items (Default ribbon) MINUS the quantities of any open / unconfirmed quotes which have not yet been converted to invoices PLUS the quantities of any open / unconfirmed orders which have not yet been converted to purchase documents.

    e) P1: This displays the "*Selling price 1*" field of the Selling prices section on the Ledger tab of Stock items (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

    f) P2: This displays the "*Selling price 2*" field of the Selling prices section on the Ledger tab of Stock items screen (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

g) P3: This displays the "*Selling price 3*" field of the Selling prices section on the Ledger tab of Stock items (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

h) LP: This displays the "*Latest cost*" (last cost price) field of the Values section on the Ledger tab of Stock items (Default ribbon). The price is displayed as exclusive of tax (VAT/GST/Sales tax) and the price is displayed as inclusive of tax (VAT/GST/Sales tax) between brackets.

The following options is not available on the Stock lookup in when selecting stock items on Reports:

- *Stock group 2 - Created / added in Groups - Stock group 2 on the Setup ribbon and linked to the stock item.*
- *Multilang - Multi-language stock item descriptions.*

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Item lookup - Financial entry

If you have added a Financial entry stock item type, you may select a general ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account from the Accounts lookup when processing documents.

To select the Financial entry item in documents:

1. On the "*Document entry*" screen, select the "*Financial entry*" stock type code.



2. On the "*Accounts*" lookup, select a general ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account.



Disabled (blocked) accounts will not be available in the "Accounts" lookup.

- *Ledger accounts - Status set to disabled.*
- *Account disabled selected (ticked) - Accounting information tab of debtor (customer / client) accounts.*
- *Account disabled selected (ticked) - Accounting information tab of creditor (supplier / vendor) accounts.*

Do not select Main accounts. For example, an error message will be displayed if an account is selected which contains sub-accounts and the document is posted:

```
You cant post a account With subaccounts!
IN000023      Motor vehicle expenses          210-000
```

You need to select a valid sub-account, for example:

- *G210010 - Fuel and oil*
- *G210020 - Maintenance*
- *G210030 - Repairs*

3. Once an account is selected, it will display on the Document lines as follows:



4. The selected account code will be displayed in the "*Item no.*" column and the account description will be added in the "*Description*" column.

You may enter comments (F9: Comment) and/or remarks for additional information regarding this item.

If comments were added, these will also be available in the Search - Investigator.

Remarks will not be searchable in the Search - Investigator.

5. Once a document containing a financial entry stock item type, is posted to the ledger, you may search for the stock item description in the Search - Investigator.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Document entry form - Posted documents

Once a document (Invoices, Credit notes, Purchases or Supplier returns) have been updated (posted) to the ledger, you cannot edit or change these documents.

However, you may still view the documents as they were originally processed in the Document entry screen before these documents were updated (posted) to the ledger.

To view the posted documents in the Document entry screen:

1. Select the document type (Invoices, Credit notes, Purchases, or Supplier returns).

2. Select "Posted" on the Document grid screen. Only the posted documents will be listed.

3. Select the Posted document on the list.

4. Click on the Edit button.

> *You may double-click on a selected document.*

The document is displayed in the Document entry screen:



> *To view the full comment, you need to print the document.*
>
> *You may select a comment and double-click on it to view the full comment on screen. You will not be allowed to edit (change) the comment.*

> *Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.*
>
> *You may select Expand to show remarks or Collapse to hide remarks on the context menu.*

> *The Move up, Move down and Sort on stock code options on the context menu to change the sequence of the document lines. This will not change the sequence of transactions and/or comments when you cancel the posted Document entry form.*

5. To close this screen, click on the Cancel button.

The layout Document entry screen displays all fields as on the original Document entry screen before it was updated (posted) to the ledger.

The transaction section lists all the stock item codes and/or comments. It does not display the processing icons since posted documents cannot be edited.

The Enter total option on the context menu will also be disabled, since posted documents cannot be edited.

To print the document, click on the Cancel button and click on the Print button on the Document list screen.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Document entry form - Context menu

Context menu options on Document lines

In the document entry form, you may right-click on the document lines area to access the options on the context menu:



Move up, Move down and Sort on stock code

Change the sequence of transactions and/or comments - in unposted documents. Once you have entered transactions and/or comments, you may need to change the sequence of the document lines. You may have entered a comment in the incorrect document line, or need to sort the document lines by moving an

item and/or comment down or up, and or sort the items by stock code, etc. This will change the sequence of transactions and/or comments on document layout files when printing or reprinting documents.

Sort on suppliercode

If the "*Preferred supplier 1*" was selected and a "*Supplier stock code*" is entered for a stock item on a Stock form, the Supplier (vendor) item codes will be added in the "*Item no.*" column in the document lines when you use the "*Create purchase on default supplier 1*" context menu option of the "*Document entry*" list screen.



You may use the "*Sort on suppliercode*" to change the sequence in which the items are listed.

You may also use the "Move up, Move down" and "Sort on stock code" options to move individual items, according to your requirements.

Enter total

Enter a new inclusive total for an unposted document. The "*Enter total*" option is mostly used to allow rounding discount.

Right-click anywhere in the Document lines or on the Document footer section of the " *Document entry*" screen, and select the "*Enter total*" option on the context menu.



Enter a new total (inclusive of Tax (VAT/GST/Sales tax) for the Invoice on the " *Enter new inclusive total*" screen and press the Enter key.



The new Invoice total will be displayed. The Inclusive and Exclusive amounts (as well as the Tax) for each item will automatically be recalculated accordingly and adjusted.



This will automatically recalculate and adjust the inclusive totals and tax amounts proportionally for all items included in the document.

Collapse / Expand

If Remarks is added to a Stock item (additional to Comments) in the document lines is displayed when opening a selected Document entry form.

On the context menu, you may select "*Collapse*" to hide the remarks or "*Expand*" to show the remarks in the document lines.

Document lines - Collapsed (hide remarks)



Document lines - Expanded (show remarks)



Context menu options on Document footers

In the document entry form, you may right-click on the document footer area to access the options on the context menu:



If you click on the "*Cancel Next*" or "*Cancel Prev*" options on the context menu, an error message is displayed:

> Please save or cancel your document first!

Click OK on to close the error message.

You need to close the Document entry form by clicking on the OK or Cancel buttons in the document footer:

- OK button will save any changes to the unposted Document entry form and close it. The OK button will not be available on posted Document entry forms.
- Cancel button will discard any changes to the unposted Document entry form and close it. If a posted Document entry form is active the Cancel button will close the Document entry form.

Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with HelpNDoc's easy CHM conversion

Document processing options

Setup Stock information

Document processing may be globally configured on Setup → Stock information.



The options in the Documents setup section is as follows:

1. SQL only for stock lookup - To be advised.
2. Merge invoice to orders - To be advised.
3. Merge items per tax on ledger - To be advised.
4. Calculate BOM stock – This setting is for the Bills of Materials - BOM (Production) stock item type.
5. Warning Backorders -
6. Limit stock purchase only for default supplier or non - To be advised.
7. Force stock type check - To be advised.
8. No calc for backorders to deliver - To be advised.
9. No calc for qty unposted - To be advised.

10. Default inclusive for documents - By default, the amounts are entered (if manually over-typed) Exclusive of VAT/GST/Sales Tax on the amount column of the document lines. To enter amounts Inclusive of VAT/GST/Sales Tax, select (tick) this option.
11. Cannot edit price - By default, the prices may be entered or manually over-typed in the amount column of the document lines. To disable the editing of prices, select (tick) this option. When processing documents, cursor will bypass the Price field.
12. Cannot edit description - By default, the descriptions may be entered or manually over-typed in the Description column of the document lines. To disable the editing of descriptions, select (tick) this option.
13. Go to quantity – By default, the cursor will go directly to the description field. To set the cursor on document lines (after selecting the stock item) to go directly to the quantity column, select (tick) this option.
14. No backorder – Select this option to disable the backorder feature when processing documents.
15. Cannot sell out of stock – By default, you are allowed to sell trading stock items that is out of stock. This will indicate negative stock quantities. To block the selling of stock items that is out of stock (insufficient quantities on hand), select this option.
16. Use tabs in stock - By default, this option is selected (ticked). If you deselect (remove the tick) for this option, the selected stock item (Stock items on the Default ribbon) screen's layout (interface) will change.
17. No print confirmation - By default, the print confirmation message will be displayed, when you click on the OK button to finish creating or editing a document. If you click on the Yes button, the document will be printed. To turn this feature off, select (tick) this option.
18. Check reference used - By default, the Check reference used field on Setup → Stock information (Default tab) is not selected (not ticked). This will not check if any matching references exists in the Your reference field of the document entry screen for any open / unposted documents for the same document type. If you activate (tick) this option, a warning message "*The reference has been used in a other document! Please check your input for duplicates!*" will be displayed. Click OK twice to save and exit the document entry screen.
19. Cannot create items - By default, if an invalid stock code, description, etc. is typed, an confirmation screen to create a new stock item will be displayed. If you click on the Yes button, you may first create the item and then return to continue with your document. To turn this feature off, select (tick) this option.
20. Button lookup - By default the Stock lookup are the default. To change this to be replaced by the Button lookup, select (tick) this option. This should support Touchscreen technology.

Groups - Images and colours

The Button lookup may be configured by adding images of your product groups and setting colours (background and font) in Setup → Groups (Stock group 1).

Product - Images

The Button lookup may be configured by adding images of your products on the Images tab of Stock items (Default → Stock items on the Default ribbon).

21. No out of stock message – By default, an information message for the trading stock items (Default stock item type) is displayed when the stock item is out of stock (insufficient quantities) or when a quantity is entered in the "*Qty Shipped*" field of the Document entry screen. To hide this message, select (tick) this option.
22. Use colours for out of stock - If this option is selected (ticked), the "*Qty Shipped*" field of the Document entry screen, will be displayed in a Red background and a White font colour.

Access control setup

The following settings may be globally configured on Setup → Access control - Documents tab:

- Set Tax Lookup On/Off - By default the Tax accounts lookup will be displayed - when the cursor is in the Tax field of the Document line on the Document entry screen. To deactivate this, select (tick) the "*Tax Read-only*" option.

  Only when you re-open the Set of Books, and process documents, the Tax account lookup will not be displayed.

- Document posting – By default only the New, Edit and Print buttons are available on the Document list screen. To add the Posting and Delete buttons, select (tick) the "*Document Posting*" option. It will add the following two (2) buttons underneath the Print button:
  - Posting - This will allow you to launch the Update ledger screen to update (post) documents (Invoices, Credit notes, Purchases and Supplier returns) to the ledger.
  - Delete - This will allow you to delete unposted documents.

  Only when you re-open the Set of Books, these buttons will be added.

Setup Documents

Auto-post on document printing

By default Documents are updated manually in Update ledger (F3) (Default ribbon). You may configure it to be updated automatically once a document is printed. To do this select (tick) the "*Auto-post on document printing*" field in Setup → Documents setup (Setup ribbon).

Only when the document is printed it will be updated – unprinted documents will not be posted (updated) to the ledger.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Append notes below item

The F9:Comments is, by default, inserted after a selected stock item.

The "*Append notes below item*" (Setup → Documents setup (Setup ribbon)) option is added to set the preference if comments should be added before, or after, a selected stock item when processing documents and printing comments on layout files.

If you change this "Append notes below item" setting when a Document entry form is open or active, you may need to go to Tools → Close active forms (Setup ribbon)*, before this setting will be activated.*

Insert comments below a selected item

"Append notes below item" = TICKED (selected). This is the default setting.



Document lines



Document layout file

It will display on document lines and document layout files as follows:

1. Item
2. Remark
3. Comment

Insert comments before a selected item

"*Append notes below item*" = NOT TICKED.



If you change this setting when a Document entry form is open or active, you may need to go to Tools → Close active forms (Setup ribbon), before this setting will be activated.

It will display on document lines and document layout files as follows:

1. Comment

2. Item

3. Remark

Document lines



Document layout file

Description	Unit	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inclusive
Comment compressor								
Compressor	Each	1	1,500.00		1,500.00	15.00%	225.00	1,725.00
Comment drill press								
Drill press	Each	1	1,000.00		1,000.00	15.00%	150.00	1,150.00

Change the sequence of document lines in unposted documents:

You may select an item, or a comment and right-click to change the sequence (order) on the document lines. On the context me

options are available:



Should you select a comment only the selected comment will be moved up or down to the previous or next line.

Should you select a item, the item and its remarks, if entered, will be moved up or down.

Sort on stockcode - This will sort the items according to the items stock code in an alphabetical sequence. Note that comments w alphabetically and will not be sorted with the stock item code.

Sort on Suppliercode - This will sort the document lines to the supplier code, if available.

Created with the Standard Edition of HelpNDoc: Make your documentation accessible on any device with HelpNDoc

Add Posting and Delete buttons

By default, only the New, Edit and Print buttons are available on the Documents grid's sidebar. You may add the Posting and Delete buttons underneath the Print button for a selected user:

- Posting - This will allow you to launch the Update ledger screen to update (post) documents (Invoices, Credit notes, Purchases and Supplier returns) to the ledger.

  If Quotes and Orders is selected as the document type, the caption of the Posting button, will change to Confirmation. If you click on the Confirmation button, it will launch the Confirm quotes and orders process option on the Documents list screen's context menu.

- Delete - This will allow you to delete an unposted document.



If the Posting and Delete buttons are not available, you may:

1. To post documents, click on the Update ledger (Default ribbon) or press the F3 key.

2. To delete documents, click on the Edit → Delete → Documents (Default ribbon).



To Add the Posting and Delete buttons to the Document list screen:

1. Click on the Setup → Access control.

2. Select the Documents tab.

3. Select (tick) the Document posting field.



4. Click on the Apply button.

5. Click on the Close button.

6. You need to click on Tools → Close active forms (Setup ribbon) or reopen the Set of Books. The Posting and Delete buttons will then be available on the Documents list screen.



Created with the Standard Edition of HelpNDoc: Transform Your Word Document into a Professional eBook with HelpNDoc

Default inclusive for documents

By default, the amounts are entered (if manually over-typed) Exclusive of Tax (VAT/GST/Sales Tax) on the amount column of the document lines. To enter and view amounts Inclusive of Tax (VAT/GST/Sales Tax), select (tick) this option.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

Cannot edit price

By default, the prices may be entered or manually over-typed in the amount column of the document lines. To disable the editing of prices, select (tick) the "*Cannot edit price*" option. When processing documents,

cursor will bypass the "*Price*" field.

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Cannot edit description

By default, the descriptions may be entered or manually over-typed in the Description column of the document lines. To disable the editing of descriptions, select (tick) this "*Cannot edit description*" option.

Created with the Standard Edition of HelpNDoc: Upgrade your help files and your workflow with HelpNDoc's WinHelp HLP to CHM conversion

Go to quantity

By default, the cursor will go directly to the description field. To set the cursor on document lines (after selecting the stock item) to go directly to the quantity column, select (tick) this "*Go to quantity*" option.

Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-Use Tool

No backorder

Select this "*No backorder*" option to disable the backorder feature when processing documents.

Created with the Standard Edition of HelpNDoc: Make Your PDFs More Secure with Encryption and Password Protection

Cannot sell out of stock

By default, you are allowed to sell trading stock items that is out of stock. This will indicate negative stock quantities. To block the selling of stock items that is out of stock (insufficient quantities on hand), select this "*Cannot sell out of stock*" option.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Check reference used

By default, the "*Check reference used*" field on Setup → Stock information (Default tab) is not selected (not ticked). This will not check if any matching references exists in the " *Your reference*" field of the document entry screen for any open / unposted documents for the same document type.

If you activate (tick) this option, a warning message is displayed:

> "The reference has been used in a other document! Please check your input for duplicates!"

Click OK twice to save and exit the document entry screen.

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Cannot create items

By default, if an invalid stock code, description, etc. is typed, when selecting a stock item on the Stock lookup, an confirmation screen to create a new stock item will be displayed.

If you click on the Yes button, you may first create the item and then return to continue with processing the document. To turn this feature off, select (tick) this "*Cannot create items*" option.

Created with the Standard Edition of HelpNDoc: Effortlessly bring your documentation online with HelpNDoc

Button lookup

By default, the Stock lookup are the default. To change this to be replaced by the Button lookup, select (tick) this option. This should support Touchscreen technology.

Groups - Images and Colours

The Button lookup may be configured by adding images of your product groups and setting colours (background and font) in Setup → Groups (Stock group 1).

Product - Images

The Button lookup may be configured by adding images of your products on the Images tab of Stock items in the Stock items (Default ribbon).

The button lookup will display images added in the following options:

- Setup → Groups (Stock group 1 tab) (Setup ribbon). These images will display as Stock groups on the Button lookup.
- Stock items (Images tab) (Default ribbon). These images will display as Product images on the Button lookup

These images may be used on a touch screen.

To enable (activate) the Button lookup:

1. Go to the Setup → Stock information.
2. Select (tick) the “Button lookup” field.

---

3. Click on the OK button. The Button lookup screen is displayed when selecting stock items while processing documents.

Examples of the Button lookup:

Stock lookup



Fast Add - Document Entry



Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

No out of stock message

By default, an information message for the trading stock items (Default stock item type) is displayed when the stock item is out of stock (insufficient quantities) or when a quantity is entered in the " *Qty Shipped*" field of the Document entry screen. To hide this message, select (tick) this "*No out of stock message*" option.

Created with the Standard Edition of HelpNDoc: Keep Your PDFs Safe from Unauthorized Access with These Security Measures

Use colours for out of stock

If this "*Use colours for out of stock*" option is selected (ticked), the "*Qty shipped*" field of the Document entry screen, will be displayed in a Red background and a White font colour.

Created with the Standard Edition of HelpNDoc: Free Qt Help documentation generator

SQL only for stock lookup

SQL only for stock lookup (565)

To be advised.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Merge invoice to orders

Merge invoice to orders (566)

To be advised.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Merge items per tax on ledger

Merge items per tax on ledger (567)

To be advised.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Calculate BOM stock

Calculate BOM Stock - This setting is for the BOM (Production) stock item type.

To be advised.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Warning backorders

Warning backorders (569)

To be advised.

Created with the Standard Edition of HelpNDoc: Converting Word Documents to eBooks: A Step-by-Step Guide with HelpNDoc

Limit stock purchase only for default supplier or non

Limit stock purchase only for default supplier or non (665)

To be advised.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Force stock type check

Force stock item type (666)

To be advised.

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Auto-post documents on print

By default all documents need to be manually posted on the following options:

- Update ledger (Default ribbon)
- Documents - Posting button (if added) (Default ribbon)
- Setup → Documents setup menu (Setup ribbon)- Auto-post documents on print field not selected.

To set the documents to post (update) to the ledger when printed:

1. Click on the Setup → Documents.
2. Select (tick) the Auto-post documents on print option.
3. Click on the OK button to save your changes. Documents will automatically be updated (posted) to the ledger, when documents are printed.

If you use this feature, and do not print a document once it is generated, you need to:

- *Update (post) the unprinted documents manually; or*
- *Print unposted documents to update the documents. You may print a list of unprinted documents in Reports → Documents → Unprinted documents listing.*

You may disable this mode of document printing by selecting (placing a tick) in the " No print confirmation" field on Setup → Stock information. This will not print any documents when processing documents.

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Set tax lookup On/Off

Set tax lookup On/Off - By default the Tax accounts lookup will be displayed - when the cursor is in the Tax field of the Document line on the Document entry screen. To deactivate this, select (tick) the " *Tax Read-only*" option.

To change the setting, you need to tick the "*Readonly tax*" option in the Documents tab (Setup → Access control on the Setup ribbon).

Only when you re-open the Set of Books, and process documents, the Tax account lookup will not be displayed when processing documents.

Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with HelpNDoc's easy CHM conversion

Document printing options

Where are Document layout files stored?

Documents can be printed/reprinted at any stage. To be able to print documents, you can select the document layout files stored in the " … \ *plug_ins* \ *reports* \ *DOCUMENTS* \ *DOCUMENTS* \ " directory or file folder of your osFinancials5/TurboCASH5 installation on your system.

When you want to customize document layout files according to your requirements, it is recommended to make a copy of the existing document layout file, and save it under your unique name. To be able to select your own document layout files to print, print it must be " … \ *plug_ins* \ *reports* \ *DOCUMENTS* \ *DOCUMENTS* \" directory or file folder of your osFinancials5/TurboCASH5 installation stored on your system.

Options to print Document layout files

Documents may be printed / reprinted at any stage using the following options on the Default ribbon:

1. Documents - Selection screen (Print button). This will print the documents for the selected document for a specific document type.

2. Debtors (Documents tab) - Select a list on a document and print it. Allows you to search and filter for and locate specific document.
3. Creditors (Documents tab) - Select a list on a document and print it. Allows you to search and filter for and locate specific document.
4. Stock items (Document groups tab of a selected stock item) - Select a document and double-click to print it.
5. Search (Investigator) – Search and double click on a document.

To determine which documents have not yet been printed, you can use the following options:

- *The filter and search options in the Document grid will allow you to search and filter for unprinted documents and select the documents which has not been printed (Printed column with value of 0). You can export the unprinted documents to a spreadsheet, for example "Excel".*
- *Reports*
  - *Reports → Documents → Unprinted document listing → Sales documents - Choose to list only the unprinted Invoices, Credit notes or Quotes.*
  - *Reports → Documents → Unprinted document listing → Purchase documents - Choose to list only the unprinted Purchases, Supplier returns or Orders.*

Select layout files

The layout files selected for each document type on the Setup → Documents setup menu (Setup ribbon) are the global default layout files that will be used to print documents. You may select up to two (2) Layout files for each document type (i.e. Quotes, Invoices, Credit notes, Orders, Purchases and Supplier returns).

Layout file 2 is optional. If layout file 2 is selected, it will print Layout file 2 document after the first layout file.

The first Layout file is required (global setting) and will serve as the default option for printing document layout files (for example, if "Default" is selected in the Layout file" field for Documents.

Specific layout files may also be selected on the Default ribbon for:

1. Debtors - Delivery address tab - Each debtor (customer / client) account by selecting a different layout file in the Layout file 1 (Invoices), Layout file 2 (Credit notes), Layout file 3 (Quotes).
2. Creditors - Delivery address tab - Each creditor (supplier / vendor) account by selecting a different

layout file in the Layout file 1 (Purchases), Layout file 2 (Supplier return), Layout file 3 (Orders).

The global settings will be over-ruled.

In addition to these settings, you may also select a different layout file when printing documents on the "*Layout file*" fields of the following options (Default ribbon):



- Documents - Selection screen (Print button) - You may select up to four (4) layout files. If you have selected a layout file for Layout file 2, Layout file 3 and/or Layout file 4, and you no longer want to print these layout files, you can select the blank option.
- Debtors (Documents tab)
- Creditors (Documents tab)

Layout files are stored in the "...\plug_ins\reports\DOCUMENTS\DOCUMENTS" directory. These may be edited using the Reportman (Report designer accessed from Setup ribbon).

Layout files have been designed to be displayed in the Language file (Switch language on the Start ribbon). If you change the language, the layout file will be displayed in the selected language.

Should the correct tax terminology (e.g. Sales Tax, VAT, GST) not be displayed on layout files, you need to select the correct language / country file.

Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Document print confirmation

By default, when a document is created or edited, it's automatically set to be printed. Upon saving the document (by clicking the OK button in the Document entry screen), a print confirmation message will appear. By default, documents will be printed when a document is created or edited (when clicking on the OK button of the Document entry screen). A print confirmation message will be displayed:

"Do you wish to print this Invoice now?"

For instance, if the document type is an "Invoice," the message might read: "Do you wish to print this Invoice now?" The same applies to other document types like credit notes, quotes, purchases, supplier returns, or orders.

If you click on the Yes button, the document will be printed immediately. If you click on the No button, you have the option to print the document at a later stage.

No print confirmation setting

You may disable this mode of document printing by selecting (placing a tick) in the "No print confirmation" field on Setup → Stock information. This will not print any documents when processing documents.

To disable the print confirmation mode, select (place a tick) in the "No print confirmation" field. This can be done through the Setup → Stock information menu under the Setup ribbon.

This means that documents will not be automatically printed when created or edited. There won't be any print confirmation message displayed.

Auto-post documents on print setting

You may also set the "Auto-post documents on print" option on the Setup Setup → Documents setup (Default ribbon) to post the documents automatically when printing the documents.

You can further streamline your document processing by setting the "Auto-post documents on print" option. This can be done through the Setup → Documents setup menu under the Setup ribbon. Enabling this option will automatically post the documents when you print them, eliminating the need for a separate posting step.

By utilizing these settings, you can customize your document creation and printing process to match your preferred workflow, ensuring efficiency and accuracy in your business operations.

Created with the Standard Edition of HelpNDoc: Effortlessly Publish Your Word Document as an eBook

Printing logo on documents

Company Logo in Layout Files

You can easily include your company logo on various documents in osFinancials5/TurboCASH5, enhancing your branding and ensuring a professional look for your financial documentation.

If any of the existing layout files that come with osFinancials5/TurboCASH5 installations or updates are

customized, there's a risk of losing your changes. When working with layout files other than your own, it's crucial to create a copy of the layout file or report and rename it before making any modifications.

osFinancials offers two options to add logos to document layout files:

1. Load Company logo: Logo Expressions included in the document layout files installed with osFinancials5/TurboCASH5 i.e. Layout file, Document layout, Document layout (15 code), and their NO-TAX equivalents (NO-TAX Layout file, NO-TAX Document layout, NO-TAX Document layout (15 code) layout files, Delivery note layout files as well as the Tutorial-Invoice and NO-TAX Invoice-English layout files and on Debtor statements as well as on Creditor remittance advises . When you load the Company logo the logo will by default be displayed and printed in the place of the Company name, Address, Telephone, Fax, E-mail address and Website.
2. Insert a logo image in to your custom layout files: When you design or customise your own layout file, you can insert or add the Image object into the place of your layout file.

Options for Including Company Logo in Layout Files

Options for Including Company Logo in Layout Files:

1. Load Company Logo Option:
    1. Description: osFinancials5/TurboCASH5 provides a straightforward way to include logos in document layout files.
    2. Usage: This option applies to document layout files that come pre-installed with osFinancials5/TurboCASH5, including standard layouts and their NO-TAX equivalents, as well as delivery note layout files, Tutorial-Invoice, and NO-TAX Invoice-English layouts. It also extends to Debtor statements and Creditor remittance advises.
    3. Functionality: By loading the Company logo, it will automatically replace designated elements like Company name, Address, Telephone, Fax, E-mail address, and Website. The logo is displayed and printed in these locations.
    4. Implementation: Access the "Company info" options in the Setup menu to load the logo. This logo expression is integrated within the layout files.
2. Insert Logo Image in Custom Layout Files:
    1. Description: For enhanced customization, osFinancials5/TurboCASH5 offers the flexibility of inserting a logo image directly into custom-designed or modified layout files.
    2. Usage: This option is ideal when you're creating your own layout or making changes to existing ones.

3. Functionality: Design your layout to include an Image object in the desired location. This object will hold the logo image.
4. Implementation: Access the Report designer (Reportman) tool within the Setup menu. Drag and drop the Image object into your layout and configure its settings as needed.

Example : Company logo as Image



In this example a company logo may also be added as an image in the layout file. In this example, you do not nee

Company info (Setup ribbon).

By understanding and utilizing these two options, you can seamlessly incorporate your company logo into various layout files within osFinancials5/TurboCASH5. Whether you're using pre-installed layouts or creating your own, these choices ensure that your branding is effectively represented on your documents.

Load Company Logo

To display and print the logo, you need to load the logo in the "*Company info - Options*" screen.

To load the Company logo:

1. On the Setup ribbon, select Company info.
2. Click on the Options tab.



3. Click on the Load from file button (or right-click in the Logo area and select the Load from file option).

4. On the "osFinancials5/TurboCASH5 - *Load Picture*" screen, select a valid file format (i.e. jpg, png, gif, bmp).

5. Click OK to save.

6. The selected Company logo will print on Document layout files and Debtor statements as well as on Creditor remittance advises.



If you do not wish to print the logo, repeat the process but select the Clear option.

See Reportman - Company logo. You add your own document layout files and add resize and move the image on your layout file and change the settings (i.e. crop, stretch, display full size, tile or proportional tile) on the Image tab - Draw Style field to display the image or logo (in the Report designer (accessed from the Setup ribbon).

Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

Document layout files

Preview of available document layout file samples

To assist in choosing a layout file for your needs, you may preview some screenshots of document layout files:

1. Translatable Document Layout Files with Dynamic Document Types:
    - *"Layout File"*
    - *"Document Layout"*
    - *"Document Layout (15 Code)"*

    These layout files utilize translatable expressions facilitated by language files and osFinancials5/TurboCASH5 settings. They dynamically display the appropriate document type names such as "*Invoice," "Credit note," "Quote," "Purchase," "Supplier return,*" or "*Order*" based on the specific document being printed. The document types are sourced from the *"TYPES.SDESCRIPTION*" expressions within the layout.

2. Translatable Document Layout Files with Dynamic Document Types without VAT/GST/Sales Tax:
    - *"NO-TAX Layout File"*
    - *"NO-TAX Document Layout"*
    - *"NO-TAX Document Layout (15 code)"*

    If you are not registered for VAT/GST/Sales tax or have chosen not to opt for voluntary registration, these layout files exclude VAT/GST/Sales tax information. They also dynamically display the appropriate document type names based on the specific type of document being printed.

    These layout files utilize translatable expressions facilitated by language files and osFinancials5/TurboCASH5 settings. They dynamically display the appropriate document type names such as "*Invoice," "Credit note," "Quote," "Purchase," "Supplier return,"* or *"Order"* based on the specific document being printed. The document types are sourced from the "*TYPES.SDESCRIPTION*" expressions within the layout.

3. Document Layout Files in English with Static Text:
    - *"TAX Invoice - English"*
    - *"NO-TAX Invoice - English"*

    These layout files offer a simple design featuring fixed text labels in the English language. Unlike translatable expressions, these layouts utilize static text labels. They are well-suited for customization to suit a range of document types, including *"Invoice", "Credit note", "Quote", "Purchase", "Supplier*

return", or *"Order"*. You have the flexibility to personalize these files according to your specific layout requirements and English translations. Additionally, you can leverage the Invoice layout as a foundation for creating other document types.

4. Translatable Delivery Note Document Layout File: The delivery note document layout file includes a versatile and dynamic option that caters to a wide range of language preferences and customisation needs. This translatable delivery note layout is powered by our language files feature, ensuring seamless translation of content across various languages. Not only does it adapt to the default language of your Set of Books, but it also accommodates debtor and creditor language preferences when they differ from the default.
5. Translatable Document Layout Files for Point-of-Sale (POS): These layout files are designed specifically for point-of-sale systems, catering to the needs of retail transactions at the point of sale.
6. Document Layout Files in Dutch Language: These layout files are previewed in the Dutch language, providing options for document layout customization for users in the Netherlands.

By offering these different layout file samples, osFinancials5/TurboCASH5 provides users with a range of choices to accommodate their needs, whether it's for different document types, languages, VAT/GST considerations, or point-of-sale transactions. This variety allows users to select the most suitable document layout template for their specific requirements.

You may use the Report designer to design your own layout files or copy any existing layout file and customise it for your own specific requirements.

Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Document layout files (English) - (static text)

English Layout Files With Static Text - English

The "*TAX Invoice - English*" and "*NO-TAX Invoice - English*" Invoice document layout files is designed as a straightforward layout file featuring fixed text labels in the English language. Unlike translatable expressions enabled by language files and settings in osFinancials5/TurboCASH5, this layout utilizes static text labels. The document pulls data from various fields entered during the document processing phase, and it establishes connections to tables and expressions within the Database fields to present the data accurately.

- *"TAX Invoice - English"* - This document layout file includes the Tax (VAT/GST/Sales tax) expressions

and static tax-related labels. This layout file is designed for those businesses which needs to be registered for Tax (VAT/GST/Sales tax).

- *"NO-TAX Invoice - English"* - This document layout file excludes the Tax (VAT/GST/Sales tax) expressions and static tax-related labels. This layout file is designed for those businesses which is not required to be registered for Tax (VAT/GST/Sales tax).

These layout files offer a simple design featuring fixed text labels in the English language. Unlike translatable expressions, these layouts utilize static text labels. They are well-suited for customization to suit a range of document types, including *"Invoice", "Credit note", "Quote", "Purchase", "Supplier return",* or *"Order".* You have the flexibility to personalize these files according to your specific layout requirements and English translations. Additionally, you can leverage the Invoice layout as a foundation for creating other document types.

Example: TAX Invoice - English

The "*TAX Invoice - English*" document layout files is designed as a straightforward layout file featuring fixed text labels in the English language. Unlike translatable expressions enabled by language files and settings in osFinancials5/TurboCASH5, this layout utilizes static text labels. The document pulls data from various fields entered during the document processing phase, and it establishes connections to tables and expressions within the Database fields to present the data accurately.

TAX Invoice - English - VAT/GST/Sales Tax expressions For scenarios where VAT/GST/Sales Tax is not relevant to your business, you can refer to a similar layout file called "*NO-TAX Invoice - English*". This layout excludes the VAT/GST/Sales Tax provisions, if needed. This layout file accommodates those businesses that does not meet the compulsory threshold for registration of Tax (VAT/GST/ Sales Tax) or those businesses which did not opt for the voluntarily registration of Tax (VAT/GST/ Sales Tax).



This layout file includes the details of your business bank accounts (for bank account 1) as entered in Setup → Company info menu on the Setup ribbon. You may print the "*Company info – Bank accounts*" report from the Reports → Company info menu on the Reports ribbon to verify that your banking details are correct. This ensures that accurate and up-to-date banking information is presented on your documents, fostering transparency and professionalism in your financial transactions.

Customising the TAX Invoice - English layout file

The "*TAX Invoice - English*" layout file is designed as a straightforward template, featuring fixed text labels in the English language. Unlike translatable expressions enabled by language files and settings in osFinancials5/TurboCASH5, this layout utilizes static text labels. The document draws data from various fields entered during the document processing phase and establishes connections to tables and expressions within the database fields to ensure accurate presentation of the data.

You have the creative freedom to customize the "*TAX Invoice - English*" according to your preferences. Adjust not only the placement of static text and labels but also integrate logos and image objects to craft a unique design that resonates with your brand identity and document needs.

Furthermore, The "*TAX Invoice - English*" layout file includes English tax components to accommodate VAT/GST/Sales Tax requirements.

Utilizing the "*TAX Invoice - English*" Layout:

1. Customization Basis: This layout provides a strong foundation for customization. The "*TAX Invoice - English*" layout file includes English tax components to accommodate VAT/GST/Sales Tax requirements. You can duplicate the "*TAX Invoice - English*" layout and utilize it as a template for creating personalized document layout files for invoices. You may also create other document types such as credit notes, quotes, purchases supplier returns and orders.
2. Edit Labels: Modify, edit, or translate the static text labels within the layout to align with your specific language and terminology preferences.
3. Design Flexibility: Adjust the placement of static text, labels, and even database fields (expressions) to create a layout that suits other document types as well. This flexibility extends to sales documents such as invoices, credit notes, and quotes, as well as purchase documents like purchases, supplier returns, and orders.
4. Including Logos and Image Objects:
    - Logos: Infuse your company's logo for a distinctive and professional touch. Logos contribute to branding and reinforce your business identity across documents.
    - Image Objects: Elevate your design by incorporating image objects. These can include product images, service visuals, or any other relevant graphics that enhance the visual appeal of your documents.
5. Tailoring Layouts for Your Needs: With the ability to seamlessly integrate logos, image objects, and finely tune the placement of text and labels, you can create layout files that reflect your business's style and meet specific requirements. Whether you're designing invoices, credit notes, quotes, purchases, supplier returns, or orders, this adaptability empowers you to produce documents that stand out and convey information effectively.

   By harnessing design flexibility, you ensure that your documents not only convey information accurately but also exude a professional and consistent visual representation, strengthening your brand's identity and leaving a lasting impression.
6. Tax Relevance and Customization Options:
    - For Tax-Applicable Scenarios: The "*TAX Invoice - English*" layout is designed to include English

Tax to accommodate VAT/GST/Sales Tax. This ensures accurate tax calculations and inclusion in your invoice documents.

- For Non-Tax Scenarios: If your business operates in scenarios where VAT/GST/Sales Tax is not applicable, you have the option to refer to a similar layout file called "*NO-TAX Invoice -English*." This layout is designed to accommodate scenarios where tax provisions are excluded. It provides the flexibility to tailor your document layout based on your business needs.

By understanding and utilizing the features and customization options of the "*Tutorial-Invoice - English*" layout file, you can create professional, accurate, and tailored invoice documents that suit your business's specific requirements and scenarios.

By harnessing design flexibility, you ensure that your documents not only convey information accurately but also exude a professional and consistent visual representation, strengthening your brand's identity and leaving a lasting impression.

NO-TAX Invoice - English

The "*NO-TAX Invoice - English*" document layout files is designed as a straightforward layout file featuring fixed text labels in the English language. Unlike translatable expressions enabled by language files and settings in osFinancials5/TurboCASH5, this layout utilizes static text labels. The document pulls data from various fields entered during the document processing phase, and it establishes connections to tables and expressions within the Database fields to present the data accurately.

TAX Invoice - English - VAT/GST/Sales Tax expressions For scenarios where VAT/GST/Sales Tax becomes relevant to your business, you can refer to a similar layout file called "*TAX Invoice - English*". This layout accommodates the inclusion of VAT/GST/Sales Tax provisions, if needed, offering flexibility as your business needs evolve.



Here's what you can do with this "*NO-TAX Invoice - English*" layout:

1. Customization Basis: You can create a duplicate of this NO-TAX Invoice layout and use it as a foundational template to personalize your document layout files for invoices.
2. Edit Labels: Modify, edit, or translate the static text labels within the document layout to align with your specific language and terminology requirements.
3. Design Flexibility: Adjust the placement of static text, labels, and even database fields (expressions) to create a layout that suits other document types as well. This extends to sales documents such as invoices, credit notes, and quotes, as well as purchase documents like purchases, supplier returns, and orders.

For scenarios where VAT/GST/Sales Tax becomes relevant to your business, you can refer to a similar layout file called "*TAX Invoice - English*". This layout accommodates the inclusion of VAT/GST/Sales Tax provisions, if needed, offering flexibility as your business needs evolve.

Customising the NO-TAX Invoice - English layout file

The "*NO-TAX Invoice - English*" layout file is designed as a straightforward template, featuring fixed text labels in the English language. Unlike translatable expressions enabled by language files and settings in osFinancials5/TurboCASH5, this layout utilizes static text labels. The document draws data from various fields entered during the document processing phase and establishes connections to tables and expressions within the database fields to ensure accurate presentation of the data.

You have the creative freedom to customize the "*NO-TAX Invoice - English*" according to your preferences. Adjust not only the placement of static text and labels but also integrate logos and image objects to craft a unique design that resonates with your brand identity and document needs.

The "*NO-TAX Invoice - English*" layout file includes English tax components to accommodate VAT/GST/Sales Tax requirements.

Utilizing the "*NO-TAX Invoice - English*" Layout:

1. Customization Basis: This layout provides a strong foundation for customization. The "*NO-TAX Invoice - English*" layout file excludes English tax components to accommodate VAT/GST/Sales Tax requirements. You can duplicate the "*NO-TAX Invoice - English*" layout and utilize it as a template for creating personalized document layout files for invoices. You may also create other document types such as credit notes, quotes, purchases supplier returns and orders.
2. Edit Labels: Modify, edit, or translate the static text labels within the layout to align with your specific language and terminology preferences.
3. Design Flexibility: Adjust the placement of static text, labels, and even database fields (expressions) to create a layout that suits other document types as well. This flexibility extends to sales documents such as invoices, credit notes, and quotes, as well as purchase documents like purchases, supplier returns, and orders.
4. Including Logos and Image Objects:
    - Logos: Infuse your company's logo for a distinctive and professional touch. Logos contribute to branding and reinforce your business identity across documents.
    - Image Objects: Elevate your design by incorporating image objects. These can include product images, service visuals, or any other relevant graphics that enhance the visual appeal of your documents.
5. Tailoring Layouts for Your Needs: With the ability to seamlessly integrate logos, image objects, and finely tune the placement of text and labels, you can create layout files that reflect your business's style and meet specific requirements. Whether you're designing invoices, credit notes, quotes, purchases,

supplier returns, or orders, this adaptability empowers you to produce documents that stand out and convey information effectively.

By harnessing design flexibility, you ensure that your documents not only convey information accurately but also exude a professional and consistent visual representation, strengthening your brand's identity and leaving a lasting impression.

6. Tax Relevance and Customization Options:
    - For Tax-Applicable Scenarios: The "*TAX Invoice - English*" layout is designed to include English Tax to accommodate VAT/GST/Sales Tax. This ensures accurate tax calculations and inclusion in your invoice documents.
    - For Non-Tax Scenarios: If your business operates in scenarios where VAT/GST/Sales Tax is not applicable, you have the option to refer to a similar layout file called "*NO-TAX Invoice -English*." This layout is designed to accommodate scenarios where tax provisions are excluded. It provides the flexibility to tailor your document layout based on your business needs.

By understanding and utilizing the features and customization options of the "*Tax-Invoice - English*" layout file, you can create professional, accurate, and tailored invoice documents that suit your business's specific requirements and scenarios.

By harnessing design flexibility, you ensure that your documents not only convey information accurately but also exude a professional and consistent visual representation, strengthening your brand's identity and leaving a lasting impression.

Additional Note for Customization of Static English Document Files:

These static document layout files serve as fundamental templates, primarily supporting translations in a single language. However, if your business operations involve multiple languages or require the inclusion of alternative language options for debtors and creditors, there are advanced options available.

Consideration for Enhanced Customization:

For comprehensive language options and the ability to adapt to diverse language preferences, you might want to explore the following options as a foundation for customization:

1. Dynamic Language Features:
    - Opt for the "*Document layout files - Translatable*" or the "*NO-TAX Document layout files - Translatable*" as your base templates.
    - These options offer powerful dynamic language capabilities within osFinancials5/TurboCASH5,

allowing you to create layouts that adapt to various languages seamlessly.

2. Accommodating Multilingual Scenarios:
    - If your business engages with international clientele or operates in regions with multiple languages, these dynamic language features become essential.
    - You can cater to the language preferences of both debtors and creditors, ensuring clear communication and professional documentation.

By embracing the "*Document layout files - Translatable*" or the "*NO-TAX Document layout files - Translatable*", you harness the potential of osFinancials' language versatility. This empowers you to create customized layouts that not only adhere to diverse language requirements but also enhance the clarity, accuracy, and professionalism of your financial documents.

Report designer help

To customize or create your own document layout files and reports using the Report designer within the Setup ribbon, you can follow these steps:

1. Refer to Documentation: To get started, you can refer to the "*Report designer*" section within the osFinancials5/TurboCASH5 help file. Additionally, you can access online documentation related to the Report designer on the osFinancials website.
2. Utilize Offline Documentation: Apart from the topics covered in this documentation, there is a comprehensive offline set of resources available in the "*.../plug_ins/reportman/doc*" folder of your osFinancials5/TurboCASH5 installation directory. You can access this offline documentation by opening the "*index.html*" file located at "*.../plug_ins/reportman/doc/index.html*" in your web browser.
3. Visit Online Resources: For further insights, the official online documentation for the "*Report Manager*" can be found at https://reportman.sourceforge.io/. This online documentation offers additional resources and information specifically about the Report Manager, providing valuable guidance as you work on your customization and design endeavours.

By following these steps and utilizing the available resources, you can effectively navigate the Report designer in osFinancials5/TurboCASH5 and create customized document layout files and reports to meet your specific requirements.

Afrikaans Layout Files (Static labels)

Similar versions than the "*TAX Invoice - English*" and "*NO-TAX Invoice - English*" document layout files is also available in the Afrikaans Language:

- "*BTW-Faktuur - Afrikaans*"
- "*GEEN-BTW Faktuur - Afrikaans*" is also available.

These documents contain static text labels that can be translated to Afrikaans in just a few minutes.

BTW-Faktuur - Afrikaans



C:\osfinancials5\plug_ins\reports\DOCUMENTS\documents\BTW Faktuur - Afrikaans.rep

BTW-Faktuur *Bladsynr.: 1 / 1*

Mnr. AB Green
Posbus 1111
Lakeside
Johannesburg
2122

Afleweringsadres
Greenstraat 23
Lakeside
Johannesburg
2123

Nutsman Hardeware
Olifantsweg 27
Emmarentia
Johannesburg
2195

Tellefoon: (011) 310-1390
Faks: (011) 310-2000
E-posadres: osfinancials1@gmail.com
Webtuiste: osfinancials.org/en/

Registrasienr.: 336012345
BTW-Registrasienr.: 446010111

BTW-Faktuur: FA000022 **Datum: 2022/06/30** **Rekeningnr.: D100005**

Beskrywing	Eenheid	Aantal	Prys	Korting.%	Eksklusief	BTW %	BTW	Inklusief
Boorpers	Elk	2	1,000.00		2,000.00	15.00%	300.00	2,300.00
Boorpers kommentaar								
Serie nommer : BP-12345-6787								
Serie nommer : BP-12345-6786								
Kompressor	Elk	2	1,500.00		3,000.00	15.00%	450.00	3,450.00
Kompressor opmerking								
Serie nommer : KO-9876-54324								
Serie nommer : KO-9876-54325								
		Totaal:			**5,000.00**		**750.00**	**5,750.00**

Banknaam: ABC - Lopende Bankrekening
Takkode: 999-999
Bankrekeningnr.: 1234567890123
IBAN:
SWIFT:
BIC:

Datum verskuldig: 2022/07/30
Jou verwysing: RS-12345
BTW-verwysing 111111111

Boodskap: Betaal asseblief binne 30 dae!

Ref:FA000021 Ref:KW000004

Verkoopspersoon Russell

Faktuur aanvaar:
Naam: _____
Datum: _____
Handtekening: _____

Gedruk/herdruk: 2023/08/20 22:13:45

GEEN-BTW Faktuur - Afrikaans


C:\osfinancials5\plug_ins\reports\DOCUMENTS\documents\GEEN-BTW Faktuur - Afrikaans.rep

Faktuur

Bladsynr..: 1 / 1

Mnr. AB Green
Posbus 1111
Lakeside
Johannesburg
2122

Afleweringsadres:
Greenstraat 23
Lakeside
Johannesburg
2123

Nutsman Hardeware
Olifantsweg 27
Emmarentia
Johannesburg
2195

Telefoon: (011) 310-1390
Faks: (011) 310-2000
E-posadres: osfinancials1@gmail.com
Webtuiste: osfinancials.org/en/
Registrasienr.: 336012345

Faktuur: FA000023 **Faktuurdatum:** 2022/07/01 **Rekeningnr.:** D100005

Beskrywing	Eenheid	Aantal	Prys	Korting %	Bedrag
Boorpers Boorpers kommentaar Serie nommer : BP-12345-6787 Serie nommer : BP-12345-6786	Elk	2	1,000.00		2,000.00
Kompressor Komressor opmerking Serie nommer : KO-9876-54324 Serie nommer : KO-9876-54325	Elk	2	1,500.00		3,000.00
	Totaal:		**5,000.00**		**5,000.00**

Naam van Bank: ABC - Lopende Bankrekening
Takkode: 999-999
Bankrekeningnr: 1234567890123
IBAN:
SWIFT:
BIC:

Datum betaalbaar: 2022/07/31
Jou verwysing: RS-12345

Boodskap: Betaal asseblief binne 30 daeBetaa

Ref:FA000022 Ref:FA000021 Ref:KW000

Verkoopspersoon: Russell

Faktuur aanvaar:
Naam: _____
Datum: _____
Handtekening: _____

Gedruk/Herdruk: 2023/08/20 22:11:47

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Document layout files - Translatable

The layout files selected for each document type on the Setup → Documents setup menu (Setup ribbon) are the global default layout files that will be used to print documents.

Specific layout files may also be selected on the Default ribbon for:

1. Each debtor (customer / client) account by selecting a different layout file in the Layout file 1 (Invoices), Layout file 2 (Credit notes), Layout file 3 (Quotes) in the Debtors.

2. Each creditor (supplier / vendor) account by selecting a different layout file in the Layout file 1 (Purchases), Layout file 2 (Supplier return), Layout file 3 (Orders) in the Creditors.

The global settings will be over-ruled.

In addition to these settings, you may also select a different layout file when printing documents on the "*Layout file*" fields of the following options (Default ribbon):

- Documents - Selection screen (Print button)
- Debtors (Documents tab)
- Creditors (Documents tab)

Layout files are stored in the *"...\plug_ins\reports\DOCUMENTS\DOCUMENTS"* directory. These may be edited using the Reportman (Report designer accessed from the Reports or Setup ribbons).

Layout files have been designed to be displayed in the Language file (Switch language on the Start ribbon). If you change the language, the layout file will be displayed in the selected language.

Should the correct tax terminology (e.g. Sales Tax, VAT, GST) not be displayed on layout files, you need to select the correct language / country file.

Document layout files supports all document types

These translatable document layout files includes a versatile and dynamic option that caters to a wide range of language preferences and customisation needs. These translatable document layout files is powered by our language files feature, ensuring seamless translation of content across various languages. Not only does it adapt to the default language of your Set of Books, but it also accommodates debtor and creditor language preferences when they differ from the default.

Changing the Document type name

To change the Document type name for Document layout files which supports all document types. you need to modify the document type names, you can navigate to the Types tab within the "*Customize Languages*" screen (accessible through the Tools → Customise Language menu on the Setup ribbon).

Labels for Tax terminology will be printed in the selected language or the language associated with the Set of Books or the selected language in the Switch language option on the Start ribbon.

If you need to customise the Tax terminology labels in your selected language, you may change these in the may be modified in the Tools → Customise Language menu on the Setup ribbon).

Examples: Document layout files (Translatable)

The "*Layout file*", *Document layout*" and "*Document layout (15 code)*" document layout files make use of translatable expressions facilitated by language files and settings within osFinancials5/TurboCASH5. These files extract data from various fields input during the document processing stage, establishing connections to tables and expressions in the Database fields to ensure accurate data presentation.

These Document layout files dynamically display the appropriate document type name, whether it's an "*Invoice*," "*Credit note*," "*Quote*," "*Purchase*," "*Supplier return*," or "*Order*", based on the specific type of document being printed. This information is sourced from the "*TYPES.SDESCRIPTION*" expressions within the document layout.

To modify the document type names, you can navigate to the Types tab within the "*Customize Languages*" screen (accessible through the Tools → Customise Language menu on the Setup ribbon).

Layout file

The "*Layout file*" does not print stock codes, but only stock descriptions.



Document layout (15-code) file

The "*Document layout file*" prints stock codes (of up to 15-digits – Maximum allowed creating stock items) and stock descriptions.



This layout file includes the details of your business bank accounts (for bank account 1) as entered in Setup → Company info menu on the Setup ribbon. You may print the "*Company info – Bank accounts*" report from the Reports → Company info menu on the Reports ribbon to verify that your banking details are correct. This ensures that accurate and up-to-date banking information is presented on your documents, fostering transparency and professionalism in your financial transactions.

Document layout file



The "*Document layout"* file does not print stock codes, but only stock descriptions.

Document layout files supports additional languages for Debtors / Creditors

These translatable document layout files are a feature designed to accommodate multiple languages within osFinancials5/TurboCASH5. These files facilitate printing documents in either the chosen language or the default language associated with the Set of Books. Additionally, these translatable document layout files take into account language preferences specified for debtor (customer/client) or creditor (supplier/vendor) accounts, including international ones.

In osFinancials5/TurboCASH5, users have the flexibility to designate a particular language for debtor or creditor accounts:

- Debtors: When a specific language is assigned to a debtor account, osFinancials5/TurboCASH5 will print document layout files for sales-related documents (such as invoices, credit notes, quotes, and point-of-sale invoices) in the debtor's preferred language.
- Creditors: If a specific language is set for a creditor account, osFinancials5/TurboCASH5 will print document layout files for purchase-related documents (including purchase orders, supplier returns,

and orders) in the preferred language of the creditor, whether they are domestic or international.



This feature ensures that financial documents align with the language preferences of both customers and suppliers, enhancing communication and clarity for a diverse range of business interactions and in regions with multiple languages. For instance, in a country like South Africa, documents can be generated in languages like Afrikaans or English..

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Intuitive Interface

NO-TAX Document layout files - Translatable

If You Are Not Registered as a VAT/GST/Sales Tax Vendor

In cases where you have not met the compulsory threshold for VAT/GST/Sales tax registration or have chosen not to opt for voluntary registration as a VAT/GST/Sales tax vendor, you may select the following document layout files that does not include VAT/GST/Sales Tax.:

- NO-TAX Layout file
- NO-TAX Document layout
- NO-TAX Document layout (15 code)

These document layout files is designed as one layout file which is translatable to print all document types for sales documents (invoices, credit notes and quotes) and purchase documents (purchases, supplier returns and orders).

These NO-TAX layout files are characterized by the following features:

- They do not display Exclusive, Inclusive, or Tax amounts on the documents.
- They are meant for scenarios where VAT/GST/Sales Tax is not applicable or relevant.

Need to Register VAT/GST/Sales tax vendor at al later stage

Once you reached your VAT/GST/Sales tax threshold or opt for voluntary registration for VAT/GST/Sales tax, you need to select and use the following translatable document layout files:

- Layout file
- Document layout
- Document layout (15 code)

These document layout files are characterized by the following features:

- They display Exclusive, Inclusive, or Tax amounts on the documents.
- They are meant for scenarios where VAT/GST/Sales Tax is applicable or relevant.

Examples: NO-TAX layout files (Translatable)

The "*NO-TAX Layout file*", "*NO-TAX Document layout*" and "*NO-TAX Document layout (15 code)*" document layout files make use of translatable expressions facilitated by language files and settings within osFinancials5/TurboCASH5. These files extract data from various fields input during the document processing stage, establishing connections to tables and expressions in the Database fields to ensure accurate data presentation.

These Document layout files dynamically display the appropriate document type name, whether it's an "*Invoice*," "*Credit note*," "*Quote*," "*Purchase*," "*Supplier return*," or "*Order*", based on the specific type of document being printed. This information is sourced from the "*TYPES.SDESCRIPTION*" expressions within the document layout.

To modify the document type names, you can navigate to the Types tab within the "*Customize Languages*" screen (accessible through the Tools → Customize language menu on the *Setup* ribbon).

NO-TAX Layout File



This layout file includes the details of your business bank accounts (for bank account 1) as entered in Setup → Company info menu on the Setup ribbon. You may print the "*Company info – Bank accounts*" report from the Reports → Company info menu on the Setup ribbon to verify that your banking details is correct.

NO-TAX Document layout (15 code)

The "*NO-TAX Document layout file*" prints stock codes (of up to 15-digits – Maximum allowed creating stock items) and stock descriptions.



This layout file includes the details of your business bank accounts (for bank account 1) as entered in Setup → Company info menu on the Setup ribbon. You may print the "*Company info – Bank accounts*" report from the Reports → Company info menu on the Setup ribbon to verify that your banking details is correct.

NO-TAX Document layout



Document layout files supports additional languages for Debtors / Creditors

These translatable document layout files are a feature designed to accommodate multiple languages within osFinancials5/TurboCASH5. These files facilitate printing documents in either the chosen language or the default language associated with the Set of Books. Additionally, these translatable document layout files take into account language preferences specified for debtor (customer/client) or creditor (supplier/vendor) accounts, including international ones.

In osFinancials5/TurboCASH5, users have the flexibility to designate a particular language for debtor or creditor accounts:

- Debtors: When a specific language is assigned to a debtor account, osFinancials5/TurboCASH5 will print document layout files for sales-related documents (such as invoices, credit notes, quotes, and point-of-sale invoices) in the debtor's preferred language.
- Creditors: If a specific language is set for a creditor account, osFinancials5/TurboCASH5 will print document layout files for purchase-related documents (including purchase orders, supplier returns, and orders) in the preferred language of the creditor, whether they are domestic or international.



This feature ensures that financial documents align with the language preferences of both customers and suppliers, enhancing communication and clarity for a diverse range of business interactions and in regions with multiple languages. For instance, in a country like South Africa, documents can be generated in languages like Afrikaans or English..

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Document layout file - Delivery notes (Translatable)

What is a delivery note?

A delivery note, also known as a delivery receipt or packing slip, is a document used in the shipping and logistics industry to confirm the delivery of goods from a seller or supplier to a buyer or customer. It serves as a record of the items that have been delivered, their quantities, and their condition at the time of delivery. Here are some key points about a delivery note:

1. Contents: A delivery note typically includes information such as the names and addresses of the sender (supplier) and the recipient (buyer), a list of the items being delivered along with their descriptions and quantities, any special handling instructions, and any additional notes relevant to the delivery.

2. Purpose: The primary purpose of a delivery note is to provide both the sender and the recipient with

a record of the goods that have been shipped and received. It acts as proof of delivery and can be used to resolve any disputes or discrepancies that might arise regarding the delivered items.

3. Reference: Often, a delivery note will include a reference number or code that can be used to cross-reference the delivery with corresponding sales orders, purchase orders, invoices, and other related documents.

4. Internal and External Use: Delivery notes are used internally within the shipping and receiving departments of a company to ensure that the correct items are dispatched and received. They are also provided to the recipient to assist with inventory management and quality control.

5. Legal and Financial Implications: Delivery notes may have legal and financial implications. For instance, they can be used as evidence in cases where disputes arise over the condition, quantity, or timeliness of a delivery. They can also be used by the recipient to check against their purchase orders and invoices to ensure accurate billing.

6. Variations: The specific format and information included in a delivery note can vary based on the industry, company policies, and local regulations. Some businesses may choose to include additional details such as batch numbers, serial numbers, barcodes, and more.

In summary, a delivery note is an essential document that helps ensure the smooth flow of goods between suppliers and customers. It provides a clear record of what has been delivered, aiding in accuracy, accountability, and transparency in business transactions.

Exclude / Include prices in a delivery note

It is a common practice to exclude prices from a delivery note, particularly for security and confidentiality reasons. Including prices on a delivery note can have several potential drawbacks:

1. Confidentiality: Prices can be sensitive information, and sharing them on a delivery note could potentially expose sensitive financial details to unintended recipients, such as third-party logistics providers, warehouse staff, or even competitors.

2. Customer Relations: If a delivery note with prices falls into the hands of the recipient's customers or clients, it might cause confusion, privacy concerns, or even harm the business relationship by revealing pricing agreements.

3. Theft and Fraud Prevention: Excluding prices from delivery notes can help reduce the risk of theft and fraud. If unauthorized individuals gain access to delivery notes with prices, they might exploit the information for illicit purposes.

4. Data Protection: Many countries have data protection regulations that require businesses to handle personal and sensitive data with care. Exposing pricing information unnecessarily could potentially

violate these regulations.

5. Focus on Delivery: Delivery notes are primarily used to confirm the receipt of goods and their condition. Excluding prices allows both the sender and the recipient to focus on verifying the accuracy of the items received rather than getting distracted by financial details.

While excluding prices is a common practice, it's essential to ensure that the delivery note contains enough information for the recipient to accurately verify the delivered items. Including details such as references, item codes, descriptions, quantities, unit measurements, and any relevant comments is crucial for efficient inventory management and reconciliation.

Ultimately, the decision to include or exclude prices on a delivery note should be based on your business's specific policies, industry norms, and the need to balance security and transparency in your business operations.

Delivery notes is usually sent to customers and to creditors for returns

Sending delivery notes to both customers and creditors for returns is a common practice in business transactions. Here's how the process typically works:

1. Debtors (Customers/Clients):
    - Outgoing Deliveries: When you send products to customers, you provide them with a delivery note along with the shipment. The delivery note contains details about the items being delivered, their quantities, descriptions, and any other relevant information.
    - Returns: If a customer wants to return items to you, they would typically include a copy of the delivery note that was sent with the original shipment. This helps you verify the returned items against the original delivery and ensures accuracy in the return process.
2. Creditors (Suppliers/Vendors):
    - Incoming Deliveries: When you receive goods from your suppliers or vendors, they might send a delivery note along with the shipment. This note provides you with information about the items you've received, quantities, descriptions, and potentially other details like batch numbers.
    - Returns to Suppliers: If you need to return items to your suppliers due to defects, errors, or other reasons, you can include a copy of the original delivery note (if available) to indicate the items being returned and their quantities. This helps the supplier process the return efficiently.

In both cases, the primary purpose of the delivery note is to ensure transparency and accuracy in the

movement of goods. Including essential details like references, item codes, descriptions, quantities, and any relevant comments ensures that both parties have clear records of the transactions.

While it's common to exclude prices from delivery notes to maintain security and confidentiality, the exact content and format of the delivery notes can vary based on your business's practices and industry norms. The key is to provide enough information for easy verification and processing of shipments and returns while protecting sensitive information.

Features: Delivery note

This Delivery note document layout file is a document template used to create delivery notes that can be adapted to various languages. This layout file would allow you to generate delivery notes in different languages while maintaining a consistent structure and design. Here's a breakdown of what this might entail:

1. Purpose: The purpose of a translatable delivery note document layout file is to provide a template for creating delivery notes that can be easily customized to display information in different languages. This is particularly useful when dealing with international clients, suppliers, or partners who prefer to receive documents in their native language.
2. Translatable Elements: The layout file would incorporate translatable elements, such as placeholders or expressions, which dynamically populate with the appropriate content based on the language settings or preferences.
3. Dynamic Language Switching: The layout file might be designed to switch between different languages based on the language settings associated with the recipient's account or the specific transaction. For example, if you're sending a delivery note to a customer with a preference for French, the layout file could render the content in French.
4. Customizable Fields: The layout would include fields for essential information such as item codes, descriptions, quantities, and any other relevant details specific to delivery notes.
5. Consistent Layout: While the content within the delivery note might change based on the language, the overall layout and design would remain consistent. This ensures professionalism and brand coherence.
6. Adaptability for Different Document Types: The same translatable delivery note document layout file might be used as a foundation to create other similar documents, such as return notes or order acknowledgements.
7. User-Friendly Customization: Users could easily customize the translatable elements, language expressions, and placeholders to adapt the layout for their specific needs.

In summary, a translatable delivery note document layout file simplifies the process of generating delivery notes in different languages, ensuring effective communication with recipients from various linguistic backgrounds while maintaining a unified visual identity.

Preview of Available Translatable Delivery Note Document Layout Files

This delivery note document layout files includes a versatile and dynamic option that caters to a wide range of language preferences and customisation needs. This translatable delivery note layout is powered by our language files feature, ensuring seamless translation of content across various languages. Not only does it adapt to the default language of your Set of Books, but it also accommodates debtor and creditor language preferences when they differ from the default.

By selecting this translatable delivery note layout, you benefit from:

- Multi-Language Support: Your delivery notes can be generated in different languages, ensuring effective communication with recipients around the world.
- Debtor and Creditor Language Adaptation: When the language preferences of your debtors or creditors vary from the default, the layout dynamically adjusts to present the information in the preferred language.
- Consistent and Professional Layout: While the content changes with translation, the layout maintains a consistent and professional appearance.
- Customization Flexibility: Customize the layout to include essential details such as item codes, quantities, descriptions, and more, ensuring accuracy in every delivery.

This translatable delivery note document layout offers an advanced level of flexibility and adaptability, enhancing your communication efficiency with customers, suppliers, and partners across different linguistic backgrounds.

Feel free to adapt and adjust the description to match the specific features and benefits of your translatable delivery note document layout in osFinancials5/TurboCASH5.



The "*Delivery note*" prints stock codes (of up to 15-digits – Maximum allowed creating stock items) and stock descriptions.

The name of this "Delivery note" document type is translatable in the "LabelID 1313" in the Language file as expression "CUSTOM('GETTEXTLANG',1313,'DeliveryNote',CLIENTORDEFLANG.SLANGUAGE,0,0)".

Document layout files supports additional languages for Debtors / Creditors

The translatable "*Delivery note*" document layout file is a feature designed to accommodate multiple languages within osFinancials5/TurboCASH5. These files facilitate printing documents in either the chosen language or the default language associated with the Set of Books. Additionally, these translatable document layout files take into account language preferences specified for debtor (customer/client) or

creditor (supplier/vendor) accounts, including international ones.

In osFinancials5/TurboCASH5, users have the flexibility to designate a particular language for debtor or creditor accounts:

- Debtors: When a specific language is assigned to a debtor account, osFinancials5/TurboCASH5 will print document layout files for sales-related documents (such as invoices, credit notes, quotes, and point-of-sale invoices) in the debtor's preferred language.
- Creditors: If a specific language is set for a creditor account, osFinancials5/TurboCASH5 will print document layout files for purchase-related documents (including purchase orders, supplier returns, and orders) in the preferred language of the creditor, whether they are domestic or international.



This feature ensures that financial documents align with the language preferences of both customers and suppliers, enhancing communication and clarity for a diverse range of business interactions and in regions with multiple languages. For instance, in a country like South Africa, documents can be generated in languages like Afrikaans or English.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Document layout files - POS - Translatable

Point-of-Sales (POS)

The point-of-sales (POS) document layout file includes a versatile and dynamic option that caters to a wide range of language preferences and customisation needs. This translatable delivery note layout is powered by our language files feature, ensuring seamless translation of content across various languages. Not only does it adapt to the default language of your Set of Books, but it also accommodates debtor and creditor language preferences when they differ from the default.

POS - START -SP100 - layout file

This specific layout file may be used for documents generated by point-of-sale printers with model SP100 (or a similar designation).



The "*POS - START -SP100*" layout file does prints stock codes and stock descriptions.

The Cashup in the footer sections will only display actual values when POS payments are processed.

The name of this "POS Tax Invoice" document type is translatable in the "LabelID 906014" in the Language files.

POS 1



The Cashup in the footer sections will only display actual values when POS payments are processed.

The name of this "POS Tax Invoice" document type is translatable in the "LabelID 906014" in the Language files.

POS 2



The "*POS 2*" layout file prints stock codes and stock descriptions.

The Cashup in the footer sections will only display actual values when POS payments are processed.

The name of this "POS Tax Invoice" document type is translatable in the "LabelID 906014" in the Language files.

Document layout files supports additional languages for Debtors / Creditors

The translatable "*POS - STARTSP100*", "*POS 1*" and "*POS 2*" document layout file is a feature designed to accommodate multiple languages within osFinancials5/TurboCASH5. These files facilitate printing documents in either the chosen language or the default language associated with the Set of Books.

Additionally, these translatable document layout files take into account language preferences specified for debtor (customer/client) or creditor (supplier/vendor) accounts, including international ones.

In osFinancials5/TurboCASH5, users have the flexibility to designate a particular language for debtor or creditor accounts:

- Debtors: When a specific language is assigned to a debtor account, osFinancials5/TurboCASH5 will print document layout files for sales-related documents (such as invoices, credit notes, quotes, and point-of-sale invoices) in the debtor's preferred language.
- Creditors: If a specific language is set for a creditor account, osFinancials5/TurboCASH5 will print document layout files for purchase-related documents (including purchase orders, supplier returns, and orders) in the preferred language of the creditor, whether they are domestic or international.



This feature ensures that financial documents align with the language preferences of both customers and suppliers, enhancing communication and clarity for a diverse range of business interactions and in regions with multiple languages. For instance, in a country like South Africa, documents can be generated in languages like Afrikaans or English.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Document layout files (Netherlands)

These layout files is designed as a straightforward layout file featuring fixed text labels in the "*Nederlands*" language. Unlike translatable expressions enabled by language files and settings in osFinancials5/TurboCASH5, this layout utilizes static text labels. The document pulls data from various fields entered during the document processing phase, and it establishes connections to tables and expressions within the Database fields to present the data accurately.

Sales documents

RMPakbon (Delivery note)



RMFactuur


C:\osfinancials5\plug_ins\reports\DOCUMENTS\documents\RMFactuur.rep
Handyman Hardware Store
Straat 27 Olifants Road
Postcode Plaats 2195 Emmarentia
Land Johannesburg
Telefoon (011) 310-1390
KVKNr 336012345
BTWNr 446010111
FACTUUR
Mr. AB Green
PO Box 1111
2122 Lakeside
Johannesburg
Factuurnummer: IN000022 Factuurdatum: 2021/06/30 Debiteurnummer: 1ABGRE
Omschrijving Aantal Prijs/stuk % prijs exc BTW
Compressor 2 1500.00 3000.00 15% 450.00
Compressor remark
30 Days money back guarantee.
Please use high pressure sprayguns and pipes with compressor!
Serial number: XEF-0018-0019-0021.
Serial number: XEF-0018-0019-0022.
Drill press 2 1000.00 2000.00 15% 300.00
Drill remark
Serial number:DXP-200-01501
Serial number:DXP-200-01502
Subtotaal: 5000.00
Totaal BTW 15%: 750.00
Totaal inc btw: 5750.00

RMfactuur BE



RMFactuurbtwAanEinde



RMCreditnota



RMOfferte



Purchase documents

RMInkoop



RMRetourzending



RMBestelling



POS

RMSTARTSP100



RMPOS


C:\osfinancials5\plug_ins\reports\DOCUMENTS\documents\RMPOS.rep
Handyman Hardware Store
Straat 27 Olifants Road
Postcode Plaats 2195 Emmarentia
Land Johannesburg
Telefoon (011) 310-1390
KVKNr 336012345
BTWNr 446010111
KASSABON
Mr. AB Green
PO Box 1111
2122 Lakeside
Johannesburg
Factuurnummer: IN000022 Factuurdatum: 2021/06/30 Debiteurnummer: 1ABGRE
Omschrijving Aantal Prijs/stuk % prijs exc BTW
Compressor 2 1500.00 3000.00 15% 450.00
Compressor remark
30 Days money back guarantee.
Please use high pressure sprayguns and pipes with compressor!
Serial number: XEF-0018-0019-0021.
Serial number: XEF-0018-0019-0022.
Drill press 2 1000.00 2000.00 15% 300.00
Drill remark
Serial number:DXP-200-01501
Serial number:DXP-200-01502
Subtotaal: 5000.00
Totaal BTW 15%: 750.00
Totaal inc btw: 5750.00
Contant: 1
Creditcard: 3
Cheque: 2
Op rekening: 3
Bon: 4
Totaal betaald: 34
Wissel geld: 5

POS


C:\osfinancials5\plug_ins\reports\DOCUMENTS\documents\POS.rep
FACTUUR
Mr. AB Green
PO Box 1111
2122 Lakeside
Johannesburg
27 Olifants Road
2195 Emmarentia
Johannesburg
Tel. (011) 310-1390
Fax. (011) 310-2000
osfinancials1@gmail.com
Factuumummer: IN000022 Factuurdatum: 2021/06/30 Debiteurnummer: 1ABGRE
Artikel Aantal Prijs/stuk % prijs exc BTW
Compressor 2 1,500.00 0 3,450.00 450.00
Compressor remark
30 Days money back guarantee. 0
Please use high pressure sprayguns and pipes with compressor!
Serial number: XEF-0018-0019-0021.
Serial number: XEF-0018-0019-0022.
Drill press 2 1,000.00 0 2,300.00 300.00
Drill remark
Serial number:DXP-200-01501 0
Serial number:DXP-200-01502

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Document layout files - Plugins

Kassabon VM

To print this layout file, the HORECAPOS plugin need to be activated and installed.

HORECAPOS - Shop - Annual subscription -

With this plugin you can create a checkout system specifically for catering.
The use of hand-held computers can speed up the serving of customers and gives you a control of the ordered products.
After recording an order at a table, the ticket printer in the kitchen and/or bar and/or POS pc will be used for the specific printout of the products.
You can specify a product to be a "kitchen" or "bar" product, and thus the printer specified is used to print the order.
You can even use product options such as butter, mustard, bread, etc. if the customer chooses that.
Products can be selected through a quick search function based on the starting letter of the product.
Or through icon based images of the product group and ultimately the product.

See Video of the latest version(Dutch) Video of an older version(Dutch) .

If not activated and configured, the following error message is displayed:

```
C:\osfinancials5\plug_ins\reports\DOCUMENTS\documents\Kassabon  VM.rep
has errors TABLENO:Dynamic SQL Error
SQL error code = -204
Table unknown
HORECAPOS_SEATS
At line 1, column 31
```

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of a Help Authoring Tool

Quotes

You may need to produce a quote for your debtors (customers / clients). When the quote is accepted, you may confirm the quote (convert the Quote to an Invoice).

Quotes cannot be updated (posted) to the ledger and it generates no transactions. But, once the Quote has been converted to an Invoice, the Invoice can be edited (if necessary) and updated (posted) to the ledger.

The following options is available to convert Quotes to Invoices:

- *Confirm quotes and orders context menu option on the "Document entry" list screen for the Quote document type.*
- *Input → Confirm menu.*

Options to create / edit Quotes:

1. *New - On the "Quotes" screen, click the New button. Select a debtor (customer / client) account on the "Debtor accounts" list screen.*
2. *Edit - On the "Quotes" screen, click the Edit button.*
3. *Copy - "Documents → Copy document" or "Documents → Copy to → Quotes" option on context menu (right-click).*

Unposted Quote entry form

The sections and fields of the Quote form, is as follows:



1. Document header:

   a) Your reference - You may enter a reference. This will allow you to track down the reference in the Search (Investigator) on the Default ribbon. All documents matching the reference will be listed.

   b) Salesperson - Select a Salesperson. This field is to show who handled the Quote. The salespersons are used for reports and to filter and search documents.

   c) Document group 1/2 - Select Document group 1 / 2 - These groups are used for reports and to filter and search documents.

   d) Date - By default, the system date will be displayed. You may enter or select any other date.

   e) Due date - This date will be automatically be calculated. It is the "*Date*" plus the number of days set in the Accounting information tab of the selected debtor (customer / client) account.

   f) Postal address - The postal address as entered for the debtor (customer / client).

   g) Delivery address - The delivery address as entered for the debtor (customer / client) on the Delivery address tab.

   h) Message - The message, as entered in Setup → Documents setup - Quotes tab (Setup ribbon) will be displayed. You may edit / enter messages to be printed on the document layout file.

> *Message line 3 - Reference document numbers converted or copied document(s).*

i) Tax reference - The Tax (VAT/GST/Sales tax) registration number as entered for the debtor (customer / client).

j) Contra account:Standard - This is the default setting. If you click on this button, you may select a different account. The account code will then be displayed.

k) Status - Open, Confirmed and Posted.

2. Document lines:

a) Item no. - Select a stock item.

Options to select stock items:

- *Stock item lookup - Use the down arrow key to launch the Stock lookup.*
- *+ Open Fast add*
- *Enter the stock code, bar code or serial number in the document footer.*

The following stock item types may be selected to process Sales documents (Quotes, Invoices and Credit notes):

- *Default (trading stock items)*
- *Sales*
- *Sales (No stock)*
- *Financial entry*
- *Option item*
- *Option item (No stock)*
- *BOM (Bill of Materials)*
- *BOM (Bill of Materials) - Production*
- *Linked item*

If the Financial entry stock item type is selected, the Accounts lookup screen will be displayed. The description of the selected account will be displayed. You may overtype this.

If Abbreviation definitions were set in the Batch entry menu (F9:Process), you may enter a character (or more) to auto-complete a description in the document line.

b) Remark - You may also click on the + (before stock item code) to add a remark (additional information) for a stock item. This remark will be printed before the comment (if added) on document layout files.

Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.

You may select Expand to show remarks or Collapse to hide remarks on the context menu.

c) Comment - You may click on the F9:Comment icon or press the F9 key to add additional information. This comment will be printed on document layout files.

Search (Investigator)

- *Comments entered in document lines are searchable.*
- *Remarks is not searchable.*

d) Order - The default quantity is 1. You may overtype the quantities.

e) Ship - The default quantity is 1. You may overtype the quantities.

f) Unit price - If up to three (3) selling prices have been entered in in the Selling price field for the selected stock item, the selling prices will be listed. The default selling price will be selected for the Set of Books or the selling price set as default for the selected debtor (customer / client) account. You may select any of the three (3) selling prices for the item. Selling prices Exclusive of VAT/GST/Sales Tax, if the F7:Exclusive icon is active - or Inclusive of VAT/GST/Sales, Tax if the F7:Inclusive icon is active.

Selling prices

If you have entered up to three (3) sales prices for a stock item (inventory / product), the selling prices will be listed when you focus in the "Unit" (amount) column.

You can set the global default selling prices 1 / 2 / 3 in the Setup → Stock information (Setup ribbon) which will apply to all debtors (customers / clients).

You can also set the default selling price 1 / 2 / 3 in the Debtors - Accounting information tab (Default ribbon) which will apply to a specific debtor (customer / client).

g) Discount - You may enter the discount percentage for the item.

h) Amount exclusive - This will is the quantities in the Ship field x Unit price. If any discount percentage is entered, the discount will be deducted from the unit price.

You may use the F11: Copy feature to copy the document transactions / comments from

an existing document.

3. Document footer:
    a) Fast add item (code / barcode / serial) - Enter the stock code, barcode or serial number. Press enter to add the item to the document lines.
    b) Current balance - The balance of all posted and unposted documents for the debtor (customer / client).
    c) Available - The available balance is calculated as the Credit limit minus the Current balance. When processing documents, and the credit limit is exceeded, a warning message will be displayed.
    d) Credit limit - The credit limit as entered for the debtor (customer / client) on the Accounting information tab.
    e) Std disc% - Standard discount percentage is only applicable to debtor (customer / client) accounts. The discount percentage as entered for the debtor (customer / client) in the Customer discount field on the Accounting information tab.
4. Click on the OK button.

By default, a confirmation message will be displayed.

"Do you wish to print this quote?"

You may turn this feature off by selecting the "No print confirmation" option on Stock information (Setup ribbon).

5. Click on the Yes button to print the Quote.

Printed : Quote

An example of the printed "*Quote*", is as follows:



This example is based on the "Layout file". You may select other available layout files.

Created with the Standard Edition of HelpNDoc: Free EPub producer

Invoices

Invoices are created for debtors (customers / clients). This will generate a source document which can be printed. The Invoice, can be edited before it is posted (updated) to the ledger.

When an Invoice is posted (updated) to the ledger, the transactions in the Sales journal (or the batch selected in the Setup → Documents setup - Invoices tab on the Setup ribbon) will automatically be generated.

Posted (updated) Invoices cannot be edited.

You may right-click and use the Move up, Move down and Sort on stock code options on the context menu to change the sequence of the document lines.

This will change the sequence of transactions and/or comments on document layout files when printing or reprinting documents.

If you need to cancel or correct a posted (updated) Invoice, you need to process a Credit note.

You may use the Reverse posted batch / document option on Global processes menu (Setup ribbon).

The reversed document may then be selected and edited. It can then be posted (updated) to the ledger.

Quotes cannot be updated (posted) to the ledger and it generates no transactions. But, once the Quote has been converted to an Invoice, the Invoice can be edited (if necessary) and updated (posted) to the ledger.

Options to create / edit Invoices:

1. *New - On the "Invoices" screen, click the New button. Select a debtor (customer / client) account on the "Debtor accounts" screen.*
2. *Edit - On the "Invoices" screen, click the Edit button.*
3. *Copy - "Documents → Copy document" or "Documents → Copy to → Invoice" option on context menu (right-click).*
4. *Confirm quotes - On "Quotes" document type, select "Documents → Confirm quotes and orders" option on context menu (right-click). (You may also confirm Orders on the Input → Confirm menu (Default ribbon)).*

1. *Edit → Repeating invoices*
2. *Calendar (Repeating invoices)*
3. *Calendar (Invoices for hours)*
4. *Calendar (Create invoice - context menu option).*
5. *Calendar (Bulk time entry)*

Convert invoice to order

If you have already created invoices (whether they are updated to the ledger (posted) or not), you may convert the Invoice to an Order. To do this, select the Invoice on the documents list and right-click and select the Documents → Convert invoice to an order option from the context menu.

You may then edit the order and convert it to a purchase document.

Unposted Invoice entry form

The sections and fields of the Invoice screen, is as follows:



The Backorder icon will only be displayed if a backorder is activated for stock items on invoices or quotes.

1. Document header:

    a) Your reference - You may enter a reference. This will allow you to track down the reference in the Search (Investigator) on the Default ribbon. All documents matching the reference will be listed.

    b) Salesperson - Select a Salesperson. This field is to show who handled the Invoice. The salespersons are used for reports and to filter and search documents.

    c) Document group 1/2 - Select Document group 1 / 2 - These groups are used for reports and to filter and search documents.

    d) Date - By default, the system date will be displayed. You may enter or select any other date.

    e) Due date - This date will be automatically be calculated. It is the "*Date*" plus the number of days set in the Accounting information tab of the selected debtor (customer / client) account.

    f) Postal address - The postal address as entered for the debtor (customer / client).

g) Delivery address - The delivery address as entered for the debtor (customer / client) on the Delivery address tab.

h) Message - The message, as entered in Setup → Documents setup - Invoices tab (Setup ribbon) will be displayed. You may edit / enter messages to be printed on the document layout file.

If a Quote is confirmed and converted to an Invoice, the message as entered in the Documents setup - Quotes tab (Setup ribbon) will be displayed. You may remove or edit the Quote message.

Message line 3 - Reference document numbers

- *Quote number for confirmed and converted Quote will be displayed.*
- *Document number of the copied document.*

i) Tax reference - The Tax (VAT/GST/Sales tax) registration number as entered for the debtor (customer / client).

j) Contra account:Standard - This is the default setting. If you click on this button, you may select a different account. The account code will then be displayed.

k) Status - Open, Confirmed and Posted.

2. Document lines:

a) Item no. - Select a stock item.

Options to select stock items:

- *Stock item lookup - Use the down arrow key to launch the Stock lookup.*
- *+ Open Fast add*
- *Enter the stock code, bar code or serial number in the document footer.*

Keyboard shortcuts:

- *Alt+F3 - Focus on Quantity ship field.*
- *Ctrl+F3 - Focus on Fast add item (code/barcode/serial) field. Then press scan.*

The following stock item types may be selected to process Sales documents (Quotes, Invoices and Credit notes):

- *Default (trading stock items)*
- *Sales*
- *Sales (No stock)*
- *Financial entry*
- *Option item*
- *Option item (No stock)*
- *BOM (Bill of Materials)*
- *BOM (Bill of Materials) - Production*
- *Linked item*

If the Financial entry stock item type is selected, the Accounts lookup screen will be displayed. The description of the selected account will be displayed. You may overtype this.

If Abbreviation definitions were set in the Batch entry menu (F9:Process), you may enter a character (or more) to auto-complete a description in the document line.

b) Remark - You may also click on the + (before stock item code) to add a remark (additional information) for a stock item. This remark will be printed before the comment (if added) on document layout files.

Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.

You may select Expand to show remarks or Collapse to hide remarks on the context menu.

c) Comment - You may click on the F9:Comment icon or press the F9 key to add additional information. This comment will be printed on document layout files.

Search (Investigator)

- *Comments entered in document lines are searchable.*
- *Remarks is not searchable.*

d) Order / Ship - The default quantity is 1. You may overtype the quantities.

e) Unit price - If up to three (3) selling prices have been entered in in the Selling price field for

the selected stock item, the selling prices will be listed. The default selling price will be selected for the Set of Books or the selling price set as default for the selected debtor (customer / client) account. You may select any of the three (3) selling prices for the item. Selling prices Exclusive of VAT/GST/Sales Tax, if the F7:Exclusive icon is active - or Inclusive of VAT/GST/Sales, Tax if the F7:Inclusive icon is active.

> *Selling prices*
>
> *If you have entered up to three (3) sales prices for a stock item (inventory / product), the selling prices will be listed when you focus in the "Unit" (amount) column.*
>
> *You can set the global default selling prices 1 / 2 / 3 in the Setup → Stock information (Setup ribbon) which will apply to all debtors (customers / clients).*
>
> *You can also set the default selling price 1 / 2 / 3 in the Debtors - Accounting information tab (Default ribbon) which will apply to a specific debtor (customer / client).*

f) Discount - You may enter the discount percentage for the item.

g) Amount exclusive - This will is the quantities in the Order and Ship field x Unit price. If any discount percentage is entered, the discount will be deducted from the unit price.

> *You may use the F11: Copy feature to copy the document transactions / comments from an existing document.*

3. Document footer:

   a) Fast add item (code / barcode / serial) - Enter the stock code, barcode or serial number. Press enter to add the item to the document lines.

   b) Current balance - The balance of all posted and unposted documents for the debtor (customer / client).

   c) Available - The available balance is calculated as the Credit limit minus the Current balance. When processing documents, and the credit limit is exceeded, a warning message will be displayed.

   d) Credit limit - The credit limit as entered for the debtor (customer / client) on the Accounting information tab.

   e) Std disc% - Standard discount percentage is only applicable to debtor (customer / client) accounts. The discount percentage as entered for the debtor (customer / client) in the Customer discount field on the Accounting information tab.

4. Click on the OK button.

By default, a confirmation message will be displayed.

"Do you wish to print this invoice?"

You may turn this feature off by selecting the "No print confirmation" option on Stock information (Setup ribbon).

5. Click on the Yes button to print the Invoice.

Printed : Invoice

An example of the printed "*Invoice*", is as follows:



Remarks are similar to comments.

This example is based on the "Layout file". You may select other available [layout files](#).

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Credit notes

Credit notes are created for debtors (customers / clients) to correct a transaction or an exiting Invoice or to cancel the Invoice. This will generate a source document which can be printed. The Credit notes, can be edited before it is posted (updated) to the ledger.

When a Credit note is posted (updated) to the ledger, the transactions in the Sales journal (or the batch selected in the Setup → Documents setup - Credit notes tab on the Setup ribbon) will automatically be generated.

Posted (updated) Credit notes cannot be edited.

You may right-click and use the Move up, Move down and Sort on stock code options on the context menu to change the sequence of the document lines.

This will change the sequence of transactions and/or comments on document layout files when printing or reprinting documents.

You may use the Reverse posted batch / document option on Tools → Global processes menu (Setup ribbon).

The reversed document may then be selected and edited. It can then be posted (updated) to the ledger.

Options to create / edit Credit notes:

1. *New - On the "Credit notes" screen, click the New button. Select a debtor (customer / client) account on the "Debtor accounts" list screen.*
2. *Edit - On the "Credit notes" screen, click the Edit button.*
3. *Copy - "Documents → Copy document" or "Documents → Copy to → Credit note" option on context menu (right-click).*
4. *On "Invoices" screen, select "Documents → Convert to credit note / supplier return" option on context menu (right-click).*

Unposted Credit note entry form

The sections and fields of the Credit note screen, is as follows:



1. Document header:

   a) Your reference - You may enter a reference. This will allow you to track down the reference in the Search (Investigator) on the Default ribbon. All documents matching the reference will be listed.

   b) Salesperson - Select a Salesperson. This field is to show who handled the Credit note. The salespersons are used for reports and to filter and search documents.

   c) Document group 1/2 - Select Document group 1 / 2 - These groups are used for reports and to filter and search documents.

   d) Date - By default, the system date will be displayed. You may enter or select any other date.

   e) Due date - This date will be automatically be calculated. It is the "*Date*" plus the number of days set in the Accounting information tab of the selected creditor account.

   f) Postal address - The postal address as entered for the creditor (supplier / vendor).

   g) Delivery address - The delivery address as entered for the debtor (customer / client) on the Delivery address tab.

   h) Message - You may enter messages to be printed on the document layout file.

   i) The message, as entered in Setup → Documents setup - Credit notes tab (Setup ribbon) will be displayed. You may edit / enter messages to be printed on the document layout file.

> *Message line 3 - Reference document number(s) of the copied document(s).*

j) Tax reference - The Tax (VAT/GST/Sales tax) registration number as entered for the debtor (customer / client).

k) Contra account:Standard - This is the default setting. If you click on this button, you may select a different account. The account code will then be displayed.

l) Status - Open or Posted.

2. Document lines:

a) Item no. - Select a stock item.

Options to select stock items:

- *Stock item lookup - Use the down arrow key to launch the Stock lookup.*
- *+ Open Fast add*
- *Enter the stock code, bar code or serial number in the document footer.*

The following stock item types may be selected to process Sales documents (Quotes, Invoices and Credit notes):

- *Default (trading stock items)*
- *Sales*
- *Sales (No stock)*
- *Financial entry*
- *Option item*
- *Option item (No stock)*
- *BOM (Bill of Materials)*
- *BOM (Bill of Materials) - Production*
- *Linked item*

If the Financial entry stock item type is selected, the Accounts lookup screen will be displayed. The description of the selected account will be displayed. You may overtype this.

If Abbreviation definitions were set in the Batch entry menu (F9:Process), you may enter a character (or more) to auto-complete a description in the document line.

b) Remark - You may also click on the + (before stock item code) to add a remark (additional information) for a stock item. This remark will be printed before the comment (if added) on document layout files.

> *Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.*
>
> *You may select Expand to show remarks or Collapse to hide remarks on the context menu.*

c) Comment - You may click on the F9:Comment icon or press the F9 key to add additional information. This comment will be printed on document layout files.

> *Search (Investigator)*
>
> - *Comments entered in document lines are searchable.*
> - *Remarks is not searchable.*

d) Order / Ship - The default quantity is 1. You may overtype the quantities.

e) Unit price - If up to three (3) selling prices have been entered in in the Selling price field for the selected stock item, the selling prices will be listed. The default selling price will be selected for the Set of Books or the selling price set as default for the selected debtor (customer / client) account. You may select any of the three (3) selling prices for the item. Selling prices Exclusive of VAT/GST/Sales Tax, if the F7:Exclusive icon is active - or Inclusive of VAT/GST/Sales, Tax if the F7:Inclusive icon is active.

> *Selling prices*
>
> *If you have entered up to three (3) sales prices for a stock item (inventory / product), the selling prices will be listed when you focus in the "Unit" (amount) column.*
>
> *You can set the global default selling prices 1 / 2 / 3 in the Setup → Stock information (Setup ribbon) which will apply to all debtors (customers / clients).*
>
> *You can also set the default selling price 1 / 2 / 3 in the Debtors - Accounting information tab (Default ribbon) which will apply to a specific debtor (customer / client).*

f) Discount - You may enter the discount percentage for the item.

g) Amount exclusive - This will is the quantities in the Order and Ship field x Unit price. If any discount percentage is entered, the discount will be deducted from the unit price.

> *You may use the F11: Copy feature to copy the document transactions / comments from an existing document.*

3. Document footer:
    a) Fast add item (code / barcode / serial) - Enter the stock code, barcode or serial number. Press enter to add the item to the document lines.
    b) Current balance - The balance of all posted and unposted documents for the debtor (customer / client).
    c) Available - The available balance is calculated as the Credit limit minus the Current balance. When processing documents, and the credit limit is exceeded, a warning message will be displayed.
    d) Credit limit - The credit limit as entered for the debtor (customer / client) on the Accounting information tab.
    e) Std disc% - Standard discount percentage is only applicable to debtor (customer / client) accounts. The discount percentage as entered for the debtor (customer / client) in the Customer discount field on the Accounting information tab.
4. Click on the OK button.

By default, a confirmation message will be displayed.

"Do you wish to print this quote?"

You may turn this feature off by selecting the "No print confirmation" option on Stock information (Setup ribbon).

5. Click on the Yes button to print the Credit note.

Printed : Credit note

An example of the printed "*Credit note*", is as follows:



This example is based on the "Layout file". You may select other available layout files.

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Orders

You may need to place an order with any of your creditors (suppliers). When the goods are received or services are provided, you may confirm the order against the actual goods received and the original order. You will do this by converting the Order to a Purchase document.

Orders cannot be updated (posted) to the ledger and it generates no transactions. But, once the Order has been converted to a Purchase document, the Purchase document can be edited (if necessary) and updated (posted) to the ledger.

The following options is available to convert Orders to Purchases:

- *Confirm quotes and orders context menu option on the "Document entry" list screen for the Orders document type.*
- *Input → Confirm menu.*

Options to create / edit orders:

1. *New - On the “Orders” screen, click the New button. Select a creditor (supplier / vendor) account on the "Creditor accounts" screen.*
2. *Edit - On the “Orders” screen, click the Edit button.*
3. *Copy - "Documents → Copy document" or "Documents → Copy to → Orders" option on context menu (right-click).*
4. *On "Invoices" screen, select "Documents → Create purchase on default supplier 1" option on context menu (right-click).*

Convert invoice to order

If you have already created invoices (whether they are updated to the ledger (posted) or not), you may convert the Invoice to an Order. To do this, select the Invoice on the documents list and right-click and select the Documents → Convert invoice to an order option from the context menu.

You may then edit the order and convert it to a purchase document.

Unposted Order entry form

The sections and fields of the Order screen, is as follows:



1. Document header:

   a) Your reference - You may enter a reference. This will allow you to track down the reference in the Search (Investigator) on the Default ribbon. All documents matching the reference will be listed.

   b) Salesperson - Select a Salesperson. Salespersons are optional for orders. This field is to show who handled the order. The salespersons are used for reports and to filter and search documents.

   c) Document group 1/2 - Select Document group 1 / 2 - These groups are used for reports and to filter and search documents.

   d) Date - By default, the system date will be displayed. You may enter or select any other date.

   e) Due date - This date will be automatically be calculated. It is the "*Date*" plus the number of days set in the Accounting information tab of the selected creditor account.

   f) Postal address - The postal address as entered for the creditor (supplier / vendor).

   g) Delivery address - The delivery address as entered for the creditor (supplier / vendor) on the Delivery address tab.

   h) Message - The message, as entered in Setup → Documents setup - Orders tab (Setup ribbon) will be displayed. You may edit / enter messages to be printed on the document layout file.

> *Message line 3 - Reference document number(s) of the copied document(s).*

i) Tax reference - The Tax (VAT/GST/Sales tax) registration number as entered for the creditor (supplier / vendor).

j) Contra account:Standard - This is the default setting. If you click on this button, you may select a different account. The account code will then be displayed.

k) Status - Open, Confirmed and Posted.

2. Document lines:

a) Item no. - Select a stock item.

If you have selected a default supplier in the "Preferred supplier 1" and entered a "Supplier stock code" for a specific stock item, the supplier stock code will be displayed in the "Item no." field followed by the Stock item code in brackets.

Only the original Stock code will still print on document layout files.

Options to select stock items:

- *Stock item lookup - Use the down arrow key to launch the Stock lookup.*
- *+ Open Fast add*
- *Enter the stock code, bar code or serial number in the document footer.*

The following stock item types may be selected to process Purchase documents (Orders, Purchases and Supplier returns):

- *Default*
- *Purchases*
- *Purchases (No stock)*
- *Financial entry*
- *Option item*
- *Option item (No stock)*
- *BOM (Bill of Materials)*
- *BOM (Bill of Materials) - Production*
- *Linked item*

If the Financial entry stock item type is selected, the Accounts lookup screen will be displayed. The description of the selected account will be displayed. You may overtype this.

If Abbreviation definitions were set in the Batch entry menu (F9:Process), you may enter a character (or more) to auto-complete a description in the document line.

b) Remark - You may also click on the + (before stock item code) to add a remark (additional information) for a stock item. This remark will be printed before the comment (if added) on document layout files.

Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.

You may select Expand to show remarks or Collapse to hide remarks on the context menu.

c) Comment - You may click on the F9:Comment icon or press the F9 key to add additional information. This comment will be printed on document layout files.

Search (Investigator)

- *Comments entered in document lines are searchable.*
- *Remarks is not searchable.*

d) Order / Ship - The default quantity is 1. You may overtype the quantities.

e) Unit price - If cost prices have been entered in in the Cost price field for the selected stock item, the cost price will be displayed. Cost prices Exclusive of VAT/GST/Sales Tax, if the F7:Exclusive icon is active - or Inclusive of VAT/GST/Sales, Tax if the F7:Inclusive icon is active.

f) Discount - You may enter the discount percentage for the item.

g) Amount exclusive - This will is the quantities in the Order and Ship field x Unit price. If any discount percentage is entered, the discount will be deducted from the unit price.

You may use the F11: Copy feature to copy the document transactions / comments from an existing document.

3. Document footer:

a) Fast add item (code / barcode / serial) - Enter the stock code, barcode or serial number. Press enter to add the item to the document lines.

b) Current balance - The balance of all posted and unposted documents for the creditor

(supplier / vendor).

c) Available - The available balance is calculated as the Credit limit minus the Current balance. When processing documents, and the credit limit is exceeded, a warning message will be displayed.

d) Credit limit - The credit limit as entered for the creditor (supplier / vendor) on the Accounting information tab.

e) Std disc% - Standard discount percentage is only applicable to debtor (customer / client) accounts.

4. Click on the OK button.

By default, a confirmation message will be displayed.

"Do you wish to print this order?"

You may turn this feature off by selecting the "No print confirmation" option on Stock information (Setup ribbon).

5. Click on the Yes button to print the order.

Printed : Order

An example of the printed "*Order*", is as follows:



This example is based on the "Layout file". You may select other available layout files.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Purchases

Purchase documents are created creditors (suppliers). This will generate a source document which can be printed. The Purchase document, can be edited before it is posted (updated) to the ledger.

When a purchase document is posted (updated) to the ledger, the transactions in the Purchase journal (or the batch selected in the Setup → Documents setup - Purchases tab on the Setup ribbon) will automatically be generated.

Posted (updated) purchase documents cannot be edited.

You may right-click and use the Move up, Move down and Sort on stock code options on the context menu to change the sequence of the document lines.

This will change the sequence of transactions and/or comments on document layout files when printing or reprinting documents.

If you need to cancel or correct a posted (updated) purchase document, you need to process a Supplier return.

You may use the Reverse posted batch / document option on the Tools → Global processes menu on Setup ribbon.

The reversed document may then be selected and edited. It can then be posted (updated) to the ledger.

Orders cannot be updated (posted) to the ledger and it generates no transactions. But, once the Order has been converted to a Purchase document, the Purchase document can be updated (posted) to the ledger.

Options to create / edit Purchases:

1. *New - On the "Purchases" screen, click the New button. Select a creditor (supplier / vendor) account on the "Creditor accounts" screen.*
2. *Edit - On the "Purchases" screen, click the Edit button.*
3. *Copy - Copy a selected purchase. "Documents → Copy document" or "Documents → Copy to → Purchases" option on context menu (right-click).*
4. *Confirm orders - On "Orders" document type, select "Documents → Confirm quotes and orders" option on context menu (right-click). (You may also confirm Orders on the Input → Confirm menu (Default ribbon)).*

Unposted Purchase entry form

The sections and fields of the Order screen, is as follows:



1. Document header:

   a) Your reference - You may enter a reference. This will allow you to track down the reference in the Search (Investigator) on the Default ribbon. All documents matching the reference will be listed.

   b) Salesperson - Select a Salesperson. Salespersons are optional for purchases. This field is to show who handled the purchase. The salespersons are used for reports and to filter and search documents.

   c) Document group 1/2 - Select Document group 1 / 2 - These groups are used for reports and to filter and search documents.

   d) Date - By default, the system date will be displayed. You may enter or select any other date.

   e) Due date - This date will be automatically be calculated. It is the "*Date*" plus the number of days set in the Accounting information tab of the selected creditor account.

   f) Postal address - The postal address as entered for the creditor (supplier / vendor).

   g) Delivery address - The delivery address as entered for the creditor (supplier / vendor) on the Delivery address tab.

   h) Message - The message, as entered in Setup → Documents setup - Purchases tab (Setup ribbon) will be displayed. You may edit / enter messages to be printed on the document layout file.

> *If an Order is confirmed and converted to an Invoice, the message as entered in the Documents setup - Orders tab (Setup ribbon) will be displayed. You may remove or edit the Order message.*

Message line 3 - Reference document numbers

- *Order number for confirmed and converted Order will be displayed.*
- *Document number of the copied document.*

i) Tax reference - The Tax (VAT/GST/Sales tax) registration number as entered for the creditor (supplier / vendor).

j) Contra account:Standard - This is the default setting. If you click on this button, you may select a different account. The account code will then be displayed.

k) Status - Open, or Posted.

2. Document lines:

a) Item no. - Select a stock item.

Options to select stock items:

- *Stock item lookup - Use the down arrow key to launch the Stock lookup.*
- *+ Open Fast add*
- *Enter the stock code, bar code or serial number in the document footer.*

If you have selected a default supplier in the "Preferred supplier 1" and entered a "Supplier stock code" for a specific stock item, the supplier stock code will be displayed in the "Item no." field followed by the Stock item code in brackets.

Only the original Stock code will still print on document layout files.

The following stock item types may be selected to process Purchase documents (Orders, Purchases and Supplier returns):

- *Default*
- *Purchases*
- *Purchases (No stock)*
- *Financial entry*
- *Option item*
- *Option item (No stock)*
- *BOM (Bill of Materials)*

- *BOM (Bill of Materials) - Production*
- *Linked item*

If the Financial entry stock item type is selected, the Accounts lookup screen will be displayed. The description of the selected account will be displayed. You may overtype this.

If Abbreviation definitions were set in the Batch entry menu (F9:Process), you may enter a character (or more) to auto-complete a description in the document line.

b) Remark - You may also click on the + (before stock item code) to add a remark (additional information) for a stock item. This remark will be printed before the comment (if added) on document layout files.

Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.

You may select Expand to show remarks or Collapse to hide remarks on the context menu.

c) Comment - You may click on the F9:Comment icon or press the F9 key to add additional information. This comment will be printed on document layout files.

Search (Investigator)

- *Comments entered in document lines are searchable.*
- *Remarks is not searchable.*

d) Order / Ship - The default quantity is 1. You may overtype the quantities.

e) Unit price - If cost prices have been entered in in the Cost price field for the selected stock item, the cost price will be displayed. Cost prices Exclusive of VAT/GST/Sales Tax, if the F7:Exclusive icon is active - or Inclusive of VAT/GST/Sales, Tax if the F7:Inclusive icon is active.

f) Discount - You may enter the discount percentage for the item.

g) Amount exclusive - This will is the quantities in the Order and Ship field x Unit price. If any discount percentage is entered, the discount will be deducted from the unit price.

You may use the F11: Copy feature to copy the document transactions / comments from an existing document.

3. Document footer:
    a) Fast add item (code / barcode / serial) - Enter the stock code, barcode or serial number. Press enter to add the item to the document lines.
    b) Current balance - The balance of all posted and unposted documents for the creditor (supplier / vendor).
    c) Available - The available balance is calculated as the Credit limit minus the Current balance. When processing documents, and the credit limit is exceeded, a warning message will be displayed.
    d) Credit limit - The credit limit as entered for the creditor (supplier / vendor) on the Accounting information tab.
    e) Std disc% - Standard discount percentage is only applicable to debtor (customer / client) accounts.
4. Click on the OK button.

By default, a confirmation message will be displayed.

"Do you wish to print this order?"

You may turn this feature off by selecting the "No print confirmation" option on Stock information (Setup ribbon).

5. Click on the Yes button to print the Purchase.

Printed : Purchase

An example of the printed "*Purchase*" document, is as follows:



This example is based on the "Layout file". You may also select other available layout files.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Supplier returns

Supplier returns are created creditors (suppliers) to correct a transaction or an exiting Purchase or to cancel the Purchase. This will generate a source document which can be printed. The Supplier returns, can be edited before it is posted (updated) to the ledger.

When a Supplier return is posted (updated) to the ledger, the transactions in the Purchase journal (or the batch selected in the Setup → Documents setup - Supplier returns tab on the Setup ribbon) will automatically be generated.

Posted (updated) Supplier returns cannot be edited.

You may right-click and use the Move up, Move down and Sort on stock code options on the context menu to change the sequence of the document lines.

This will change the sequence of transactions and/or comments on document layout files when printing or reprinting documents.

You may use the Reverse posted batch / document option on Tools → Global processes menu on Setup ribbon.

The reversed document may then be selected and edited. It can then be posted (updated) to the ledger.

Options to create / edit Supplier returns:

1. *New - On the "Supplier returns" screen, click the New button. Select a creditor (supplier / vendor) account on the "Creditor accounts" screen.*
2. *Edit - On the "Supplier returns" screen, click the Edit button.*
3. *Copy - Copy a selected purchase. "Documents → Copy document" or "Documents → Copy to → Supplier return" option on context menu (right-click).*
4. *On "Puechases" screen, select "Documents → Convert to credit note / supplier return" option on context menu (right-click).*

Unposted Supplier return entry form

The sections and fields of the Supplier return screen, is as follows:



1. Document header:

    a) Your reference - You may enter a reference. This will allow you to track down the reference in the Search (Investigator) on the Default ribbon. All documents matching the reference will be listed.

    b) Salesperson - Select a Salesperson. Salespersons are optional for supplier returns. This field is to show who handled the supplier return. The salespersons are used for reports and to filter and search documents.

    c) Document group 1/2 - Select Document group 1 / 2 - These groups are used for reports and to filter and search documents.

    d) Date - By default, the system date will be displayed. You may enter or select any other date.

    e) Due date - This date will be automatically be calculated. It is the "*Date*" plus the number of days set in the Accounting information tab of the selected creditor account.

    f) Postal address - The postal address as entered for the creditor (supplier / vendor).

    g) Delivery address - The delivery address as entered for the creditor (supplier / vendor) on the Delivery address tab.

    h) Message - You may enter messages to be printed on the document layout file. The message, as entered in Setup → Documents setup - Supplier returns tab (Setup ribbon) will be displayed. You may edit / enter messages to be printed on the document layout file.

    > *Message line 3 - Reference document number(s) of the copied document(s).*

    i) Tax reference - The Tax (VAT/GST/Sales tax) registration number as entered for the creditor (supplier / vendor).

    j) Contra account:Standard - This is the default setting. If you click on this button, you may select a different account. The account code will then be displayed.

    k) Status - Open or Posted.

2. Document lines:

    a) Item no. - Select a stock item.

    > *Options to select stock items:*
    >
    > - *Stock item lookup - Use the down arrow key to launch the Stock lookup.*
    > - *+ Open Fast add*
    > - *Enter the stock code, bar code or serial number in the document footer.*

If you have selected a default supplier in the "Preferred supplier 1" and entered a "Supplier stock code" for a specific stock item, the supplier stock code will be displayed in the "Item no." field followed by the Stock item code in brackets.

Only the original Stock code will still print on document layout files.

The following stock item types may be selected to process Purchase documents (Orders, Purchases and Supplier returns):

- *Default*
- *Purchases*
- *Purchases (No stock)*
- *Financial entry*
- *Option item*
- *Option item (No stock)*
- *BOM (Bill of Materials)*
- *BOM (Bill of Materials) - Production*
- *Linked item*

If the Financial entry stock item type is selected, the Accounts lookup screen will be displayed. The description of the selected account will be displayed. You may overtype this.

If Abbreviation definitions were set in the Batch entry menu (F9:Process), you may enter a character (or more) to auto-complete a description in the document line.

b) Remark - You may also click on the + (before stock item code) to add a remark (additional information) for a stock item. This remark will be printed before the comment (if added) on document layout files.

Remarks are similar than comments. You may click on the + icon (before the stock code) to add a remark for the stock item.

You may select Expand to show remarks or Collapse to hide remarks on the context menu.

c) Comment - You may click on the F9:Comment icon or press the F9 key to add additional information. This comment will be printed on document layout files.

Search (Investigator)

- *Comments entered in document lines are searchable.*
- *Remarks is not searchable.*

d) Order / Ship - The default quantity is 1. You may overtype the quantities.

e) Unit price - If cost prices have been entered in in the Cost price field for the selected stock item, the cost price will be displayed. Cost prices Exclusive of VAT/GST/Sales Tax, if the F7:Exclusive icon is active - or Inclusive of VAT/GST/Sales, Tax if the F7:Inclusive icon is active.

f) Discount - You may enter the discount percentage for the item.

g) Amount exclusive - This will is the quantities in the Order and Ship field x Unit price. If any discount percentage is entered, the discount will be deducted from the unit price.

You may use the F11: Copy feature to copy the document transactions / comments from an existing document.

3. Document footer:

a) Fast add item (code / barcode / serial) - Enter the stock code, barcode or serial number. Press enter to add the item to the document lines.

b) Current balance - The balance of all posted and unposted documents for the creditor (supplier / vendor).

c) Available - The available balance is calculated as the Credit limit minus the Current balance. When processing documents, and the credit limit is exceeded, a warning message will be displayed.

d) Credit limit - The credit limit as entered for the creditor (supplier / vendor) on the Accounting information tab.

e) Std disc% - Standard discount percentage is only applicable to debtor (customer / client) accounts.

4. Click on the OK button.

By default, a confirmation message will be displayed.

"Do you wish to print this order?"

You may turn this feature off by selecting the "No print confirmation" option on Stock information (Setup ribbon).

5. Click on the Yes button to print the Supplier return.

Printed : Supplier return

An example of the printed "*Supplier return*", is as follows:



Supplier return Page 1

A-ONE Suppliers
P O Box 31318
Marshalltown
Johannesburg
2000

Handyman Hardware Store
27 Olifants Road
Emmarentia
Johannesburg
2195
Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail osfinancials1@gmail.com
Company reg. no.: 336012345
Tax reg. no.: 446010111

Delivery address
Austin Street
Marshalltown
Johannesburg
2001

Supplier return: SR000005 Date: 2022/05/01 Account no.: C2AONES

Description	Unit	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inclusive
Drill press Drill press remark Serial number:DXP-200-01502 Serial number:DXP-200-01503	Each	2	500.00		1,000.00	15.00%	150.00	1,150.00
	Total				1,000.00		150.00	1,150.00

Due date: 2022/05/31
Your reference: 4562
Tax reference: 906012345
Message: Early settlement discount of 2.5% if paid within 30 days. Ref:PU000007 Ref:OR000002
Salesperson: Russell

Supplier return accepted:
Name: _____
Date: _____
Signature: _____
Printed/Reprinted 2022/05/01 05:51:21

This example is based on the "Layout file". You may select other available layout files.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Confirm Quotes and Orders

Confirm and convert Quotes to Invoices

Once the debtor (customer / client) accepts the Quote, it can then be confirmed and converted to an Invoice. Once a quote is confirmed and converted to an invoice, you may need to edit the Invoice, before

you update (post) the invoice to the ledger.

The following options is available to confirm and convert Quotes to Invoices:

- Input → Confirm menu on the Default ribbon.
- Documents → Confirm quotes and orders option on the context menu, (on the Document entry selection screen), if the Quotes document type is selected.

Confirm and convert Orders to Purchases

Once the creditor (supplier / vendor) delivers the Order, it can then be confirmed and converted to a Purchase. Once a Order is confirmed and converted to a Purchase document, you may need to edit the Purchase, before you update (post) the Purchase to the ledger.

The following options is available to confirm and convert Orders to Purchases:

- Input → Confirm menu on the Default ribbon.
- Documents → Confirm quotes and orders option on the context menu, (on the Document entry selection screen), if the Orders document type is selected.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Confirm Quotes

Once the debtor (customer / client) accepts the Quote, it can then be confirmed and converted to an Invoice. Once a Quote is confirmed and converted to an Invoice, you may need to edit the Invoice, before you update (post) the Invoice to the ledger.

The debtor (customer / client) may, when accepting the Quote, not accept all the items on the Quote, or may add some more items on the Quote. In this case, you may edit the Quote (Documents) (Default ribbon), before you confirm the Quote and convert it to an Invoice.

If you have already confirmed a Quote and converted it to an Invoice, and there are still any discrepancies in the Quote, for example the correct quantities of goods accepted, you may edit the Invoice (Documents) (Default ribbon), before you update (post) the Invoice to the ledger.

If you did not edit the Invoice (converted Quote), you will then need to process a Credit note to correct the updated (posted) Invoice with the incorrect amounts and quantities.

Quotes may also be converted to Invoices on the Confirm quotes and orders context menu option on the "Document entry" list screen for the Quotes document type.

To confirm and convert a Quote to an Invoice:

1. On the Default ribbon, select Input → Confirm (Shift + F3).



2. Select Quotes in the "*Document type*" field. The screen will change to reflect Quotes, Invoices and Debtors, and a list of the Quotes.

By default, only the open and unconfirmed Quotes will be listed. To list the confirmed (Quotes already confirmed and converted to Invoices) select (tick) the "Show posted" field.

3. Select the Quotes to be confirmed and converted to Invoices. Click on the Add selected button. The selected Quotes will be transferred to the "*Quotes to convert to invoice*" section of the screen.

4. Enter or select the Date on which the Quotes was accepted, if necessary.

By default, the system date is displayed. You may select (tick) the "Use document date" option. The Quotes will be converted to Invoices using the original document date.

5. Click on the Convert button. A confirmation message is displayed:

"Do you wish to delete all Quotes?"

6. Click on the Yes button to convert the Quotes to Invoices and to delete the Quotes.

If you click on the No button, the selected Quotes will still be confirmed and converted to Invoices. These Quotes will still be available to edit.

You may delete the Quotes manually in Edit → Delete → Documents menu on the Default ribbon.

7. The Quotes will be removed from the "*Quote to convert to invoice*" list, and will be ready to be edited in the Invoices document type on the Document list screen.

8. Click on the Cancel button, or press the Esc key on your keyboard, to close or exit this screen.

You may also search for a specific Quote by entering the Quote number, and click on the Search button.

You may also select a specific Debtor (customer / client) account by clicking on the Select debtor button. The screen w

Quotes to the lookup for Debtor (customer / client) accounts. (It also includes Creditor (supplier / vendor) accounts).



Select the Debtor (customer / client) account and click on the OK button. The screen will change to the normal screen displayed.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Confirm Orders

Once the creditor (supplier / vendor) delivers the Order, it can then be confirmed and converted to a Purchase. Once a Order is confirmed and converted to a Purchase document, you may need to edit the Purchase, before you update (post) the Purchase to the ledger.

When the creditor (supplier / vendor) delivers the stock items or products, you may discover that some items are damaged or not included in the order, you may remove or add some more items on the Order. In this

case, you may edit the Order (Documents) (Default ribbon), before you confirm the Order and convert it to an Purchase.

If you have already confirmed an Order and converted it to a Purchase, and there are still any discrepancies in the Order, for example the correct quantities of goods accepted, you may edit the Purchase (Documents) (Default ribbon), before you update (post) the Purchase to the ledger.

If you did not edit the Purchase (converted Order), you will then need to process a Supplier return to correct the updated (posted) Purchase with the incorrect amounts and quantities.

Orders may also be converted to Purchases on the Confirm quotes and orders context menu option on the "Document entry" list screen for the Orders document type.

To confirm and convert an Order to a Purchase:

1. On the Default ribbon, select Input → Confirm (Shift + F3).



2. Select Orders in the "*Document type*" field. The screen will change to reflect Orders, Purchases and Creditors, and a list of the Orders.

By default, only the open and unconfirmed Orders will be listed. To list the confirmed (Orders already confirmed and converted to Purchases) select (tick) the "Show posted" field.

3. Select the Orders to be confirmed and converted to to Invoices. Click on the Add selected button. The selected Orders will be transferred to the "*Order to convert to purchase*" section of the screen.

4. Enter or select the Date on which the Order was accepted, if necessary.

By default, the system date is displayed. You may select (tick) the "Use document date" option. The Orders will be converted to invoices using the original document date.

5. Click on the Convert button. A confirmation message is displayed:

"Do you wish to delete all Orders?"

6. Click on the Yes button to convert the selected Orders to Purchases and to delete the Orders.

If you click on the No button, the selected Orders will still be confirmed and converted to Purchases. These Orders will still be available to edit.

You may delete the Orders manually in Edit → Delete → Documents menu on the Default ribbon.

7. The Orders will be removed from the "*Order to convert to purchase*" list, and will be ready to be edited in the Purchases document type on the Document list screen.

8. Click on the Cancel button, or press the Esc key on your keyboard, to close or exit this screen.

You may also search for a specific Order by entering the Order number, and click on the Search button.

You may also select a specific Creditor account by clicking on the Select creditor button. The screen will change from lookup for Creditor (supplier / vendor) accounts. (It also includes Debtor (customer / client) accounts).



Select the Creditor account and click on the OK button. The screen will change to the normal screen and the available

---

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of a Help Authoring Tool

Repeating invoices

You may select Invoices from the Invoice history which occur frequently or on a regular basis (e.g. every month) and to set them as repeating invoices.

In addition to this feature, you may schedule Repeating invoices as events in Calendar (Default ribbon). You may select to generate Invoices for selected Invoices or Quotes from the Invoice History List to one or many Debtor accounts.

Once selected Invoices are generated, osFinancials5/TurboCASH5 will generate Invoice numbers and the transactions will be copied into normal Invoice documents for the selected debtor or debtors.

To check and /or edit these Invoices you need to access the Invoices (Documents on the Default ribbon) and select the Debtor account for which you have copied a repeating Invoice.

Finally, you need to update (post) the Invoices to the ledger for the selected debtor or debtors. This feature saves you the extra work of entering these Invoices each month.

To generate repeating invoices:

1. On the Default ribbon, select Edit → Repeating invoices. The *Invoice History* screen will be displayed. The "*Invoice History*" screen will list all the posted and unposted Invoices associated for your debtors (customers / clients). These Invoices will be listed according to the Invoice Number:



2. Select the Invoices to repeat. You have two (2) basic options to select and copy the Invoices to the "*Invoice history*" field.

    a) Select and highlight an Invoice and click on the Add sel. (Add Selected) button to transfer only the selected Invoice to the "*Invoice history*" field.

    b) Select the Invoices to repeat, and mark them as Repeating and click on the Add all button to transfer all the selected marked Invoices to the "*Invoice history*" field.

> *If you have incorrectly selected and transferred an Invoice to the Invoices to Repeat List,*

you may select the Invoice to activate the Remove button. You may then click on the Remove button. This Invoice will remove the selected Invoices from the Invoices to Repeat field.

3. Select the Invoice from the list of Invoices in the Invoices to Repeat field and click on the Options button. (The Options button will only be activated once an Invoice is selected on the Invoices to Repeat (right hand side of the screen)). The Invoice history screen will change as follows:



4. Select one or a range of Debtor accounts from the list of available Debtor accounts for which you wish to copy the repeating invoice.

5. Apply to all - The following options will apply to all repeating invoices when you click on the Generate button:

    a) Select date - Enter the date or select the date (using the date picker) on which you wish to generate the repeating invoices. This date will be displayed as the Invoice date on the Invoices, and it will also be the transaction date when the Invoice(s) is updated (posted) to the ledger.

    b) Set new invoice as repeating - You may select to set the New invoice as repeating to add this new Invoice to the Invoices to repeat list. If selected, you may use the selected Invoice to generate the new Invoices in the future.

    c) Replace message with - You may also replace any existing messages (which are currently displayed as the standard Invoice message as entered in Setup → Documents setup - Invoices tab) with a message which you may enter in the "*Replace message with*" field. There

are three (3) lines to enter a message.

> *If you enter the message, you should not exceed the viewable area of each line. If too many characters are entered in a line, the characters exceeding the line, will not be displayed on the Document entry screen and on the printed Invoice.*

d) Add this comment line - You may also enter a standard comment line, if you wish to add a comment to the transactions on the invoice. This comment will be displayed on the new generated repeating invoices.

6. Click on the OK button to close the "*Options*" screen. The screen will display the list of Invoices.

7. Click on the Generate button to generate repeating invoices for the selected debtor (customer / client) accounts. It will generate the next Invoice number.

> *Should you by accident have generated a repeating Invoice incorrectly to a debtor (customer / client) account, you need to delete the Invoice in Edit → Documents (Default ribbon).*

> *The generated repeating invoices can be selected when you click in Documents (Default ribbon). You need to select the Debtor account and the Invoice number to check, edit (if necessary) and print the Invoices. Finally, you need to update (post) the Invoices to the ledger to update the transactions to the general ledger, debtors ledger, and the stock ledger.*

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Delete documents

This option is used to delete the selected sales document types (Invoices, Credit notes or Quotes) for your debtors (customers / clients) and purchase document types (Purchases, Supplier returns or Orders) for your creditors (suppliers / vendors) which you have created or edited in Documents (Default ribbon).

> *An option to delete Quotes for debtors (customers / clients) and Orders for creditors (suppliers) is available when:*
>
> - *Quotes are confirmed and converted to Invoices.*
> - *Orders are confirmed and converted to Purchase documents.*
>
> *If you did not delete Quotes and Orders when these are confirmed or converted, these documents may be*

deleted with this option.

You may only delete documents which have not yet been updated (posted) to the ledger.

You will not be allowed to delete documents (i.e. Invoices, Credit notes, Purchases or Supplier returns) which have been updated (posted) to the ledger.

Confirmed, posted or unposted Quotes and Orders may be deleted.

If the Document posting option is selected on the Documents tab of Setup → Access control, the Delete button will be added to the sidebar of then Document list screen. Clicking on this button will delete a selected document.

Once a document has been deleted you will no longer be able to reprint deleted documents. These deleted document numbers will also not be available to be selected on the Reports → Documents (Document listing, Document listing per account or Unprinted document listing).

Any deleted documents will no longer be available to be printed or re-printed from the Documents tab of the Debtor (customer / client) accounts or from the Documents tab of the Creditor (supplier/ vendor) accounts.

Before you decide to delete a document, it is advisable to make sure that you don't need to:

- *Copy the transactions and comments to an active document.*
- *Use it as a repeating Invoice or schedule it as an repeating Invoice event.*

Delete Documents

To delete documents:

1. On the Default ribbon, select Edit → Delete → Documents.



2. The "*Delete Invoices*" screen will be displayed.

3. Select type - Select Invoices, Credit notes, Quotes, Purchases, Supplier returns or Orders. If you select the "*All*" option, all these document types will be listed.



> *If the row in which a document is listed is shaded (light cream colour) (in this example CR000003, IN000021, IN000022 and IN000025), it indicates that the document is printed. The other colour shades in the rows, indicates that a document is not yet printed. You may wish to print these documents before deleting them.*

3. Select the following options:

   a) Posted - By default, only the unposted documents will be listed. The posted option (tick box) will be inactive (cannot be ticked) for Invoices, Credit notes, Purchases or Supplier returns. These document types can only be deleted if these are not yet posted or updated to the ledger.

> *The posted field can only be selected for Quotes and Orders.*
>
> - *Posted - Not selected (default), will list Quotes or Orders which status is "Open" and "Confirmed".*
> - *Posted - Selected (ticked), will list Quotes or Orders which status is "Posted".*

   b) From / To - This will display "*From ... to*" and the name of the Document type. This option

allows you to select a starting document number on a drop-down list and a last document number which you need to delete. All documents within the selected range of document numbers will be deleted.

> *If you need to delete only one document, the document number in the "From ... to" fields must be the same.*

c) Selected - If you select this option, the "*From ... to*" fields and the drop-down lists of document numbers will be de-activated. An arrow will indicate the selected document.

> *You may also use the Down arrow or Up arrow keys on your keyboard to select a document from the list.*

> *You may also right-click to access the context menu.*
>
> 
>
>
> *Update (Ctrl + U) will display a confirmation message to delete the selected document(s).*

4. Click on the Delete button. The information message is displayed:

   "Do you want to delete?"

5. Click on the Yes button.

Finding or locating specific documents

You may also use the following options to find or locate a specific document (documents):

1. Search by Invoice no. - (or document number for the selected document type) will reflect the Search by the selected Document type no.
2. Enter the Document number - The document number will automatically be selected. If not, click on the Search button.

Sort sequences

Double-click on the column headings to sort the list of documents ascending or descending:

1. Invoice no. - (or document number for the selected document type) - By default, all document numbers are displayed ascending (smallest document number to the latest document number). If you double-click on this heading, it will list the Invoice no. or document number for the selected document type descending (from the latest document number to the smallest or first document number).

2. Date - By default, the document dates are listed by document numbers. The dates may not necessarily be in the ascending sequence. To display the dates in the descending sequence (from the latest date to the newest date), double-click on this heading. To display the dates in the ascending sequence (oldest date to the latest date), double-click on this heading again.

3. Account - By default, the Debtor accounts (Invoices, Credit notes and Quotes) and Creditor accounts (Purchases and Supplier return documents and Orders) are listed by document numbers. The Debtor / Creditor account codes may not be displayed in the ascending sequence. To display the Debtor / Creditor account codes in the descending sequence (9-0 / Z-A), double-click on this heading. To display the Debtor / Creditor account codes in the ascending sequence (0-9 / A-Z), double-click on this heading again.

4. Description - By default, the Debtor accounts (Invoices, Credit notes and Quotes) and Creditor accounts (Purchases and Supplier return documents and Orders) are listed by document numbers. The Debtor / Creditor account descriptions or names may not be displayed in the ascending sequence. To display the Debtor / Creditor account descriptions or names in the descending sequence (9-0 / Z-A), double-click on this heading. To display the Debtor / Creditor account descriptions or names in the ascending sequence (0-9 / A-Z), double-click on this heading again.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Update / Post documents

This option is used to update (post) your documents created or generated in Documents (Default ribbon) to the ledger. The debtor (customer / client) documents which can be updated (posted) to the ledger are Invoices and Credit notes. The creditor (supplier / vendor) documents are Purchase documents and Supplier return documents.

You may set the "Auto-post documents on print" option in Setup → Documents setup (Setup ribbon) to update (post) documents automatically, once a document is generated and printed. If you use this feature, and do not print a document once it is generated, you need to update (post) the unprinted documents in Update ledger (Default ribbon) .

Quotes for debtors (customers / clients) and Orders for creditors (suppliers) cannot be updated (posted) to the ledger.

- *Quotes - only when a Quote is confirmed and converted to an Invoice, can the Invoice be edited and updated (posted) to the ledger.*
- *Orders - only when an Order is confirmed and converted to a Purchase document, can the Purchase document be edited and updated (posted) to the ledger.*

When these documents are updated to the ledger they will automatically write up your journals and post the transactions to the applicable accounts in the ledger (the General ledger as well as the Debtor's ledger, Creditors ledger and Stock ledger).

If you have purchased stock items from a creditor (supplier / vendor), you need to update the Purchase documents before you update (post) your Invoices for sales of stock items to your debtors (customers / clients). This will ensure that your Stock item file will be updated with the purchases before you actually sell the stock items and that you will have sufficient stock items on hand when you update (post) the Invoices.

Update ledger - Documents

To update the documents to the ledger:

1. On the Default ribbon, select Update ledger (F3). The "*Update Invoices"* screen is ("*Invoices*" - default document type) will be displayed.

   If the Document Posting option is selected on the Documents tab - Setup → Access control, the Posting button will be added to the sidebar of the Document list screen. Clicking on this button will launch the Update ledger - Documents screen.

2. Select type - Select "*Invoices, Credit notes, Purchases*" or "*Supplier returns*". If you select the "*All"* option, all these document types will be listed.



The document numbers for Invoices, Credit notes, Purchases and Supplier returns, as prefixed in the Documents setup (Setup ribbon), makes it easy to identify the document type.

If the "All" option is selected, the following documents may be included:

- *Stock adjustments - Document numbers prefixed with "ST" is a 7-digit document number. These are automatically generated when doing stock adjustments (changes in the quantities on hand). These stock adjustments does not show any transactions and it prints a blank Posted batch type reports.*
- *BOM (Production) stock type - Assemble / Disassemble context menu options - Document numbers prefixed with"SA" will be a 7-digit number.*
- *Project Quote - Document numbers prefixed with"D" will be a 7-digit number.*

These documents will not be listed. if Invoices, Credit notes, Purchases and Supplier returns in the "Select type" list.

If the row in which a document is listed is shaded (light cream colour) (in this example CR000003, IN000021, IN000022 and IN000025), it indicates that the document is printed. The other colour shades in the rows, indicates that a document is not yet printed. You may wish to print these documents before updating them.

3. Select the following options:

   a) Suppress open item - By default, the following Open item selection screens will be displayed

on which you need to link the debit and credit transactions when updating (posting) documents:

- § Open item selection screen for Debtor (customer / client) accounts if the "*Use Open item*" field on the Accounting information tab is selected.
- § Open item selection screen for Creditor (supplier / vendor) accounts if the "*Use Open item*" field on the Accounting information tab is selected.

b) Select the Suppress Open item field, if you do not wish to use the Open item link selection feature to be launched when updating or posting documents. You may then later use the Open item link feature to link the transactions.

c) From / To - This will display "*From ... to*" and the name of the Document type. This option allows you to select a starting document number on a drop-down list and a last document number which you need to update (post) to the ledger. All documents within the selected range of document numbers will be updated (posted) to the ledger.

If you need to update (post) only one document to the ledger, the document number in the "From ... to" fields must be the same.

d) Selected - If you select this option, the "*From ... to*" fields and the drop-down lists of document numbers will be de-activated. An arrow will indicate the selected document.

You may also use the Down arrow or Up arrow keys on your keyboard to select a document from the list.

4. Click on the Update button. osFinancials5/TurboCASH5 will automatically write up the transactions in the respective batches (journals), as selected in Setup → Documents setup (Setup ribbon).

Finding or locating specific documents

You may also use the following options to find or locate a specific document (documents):

1. Search by Invoice no. - (or document number for the selected document type) will reflect the Search by the selected Document type no.
2. Enter the Document number - The document number will automatically be selected. If not, click on the Search button.

Sort sequences

Double-click on the column headings to sort the list of documents ascending or descending:

1. Invoice no. - (or document number for the selected document type) - By default, all document numbers are displayed ascending (smallest document number to the latest document number). If you double-click on this heading, it will list the Invoice no. (or document number for the selected document type) descending (from the latest document number to the smallest or first document number).

2. Date - By default, the document dates are listed by document numbers. The dates may not necessarily be in the ascending sequence. To display the dates in the descending sequence (from the latest date to the newest date), double-click on this heading. To display the dates in the ascending sequence (oldest date to the latest date), double-click on this heading again.

3. Account - By default, the Debtor accounts (Invoices and Credit notes) and Creditor accounts (Purchases and Supplier return documents) are listed by document numbers. The Debtor / Creditor account codes may not be displayed in the ascending sequence. To display the Debtor / Creditor account codes in the descending sequence (9-0 / Z-A), double-click on this heading. To display the Debtor / Creditor account codes in the ascending sequence (0-9 / A-Z), double-click on this heading again.

4. Description - By default, the Debtor accounts (Invoices and Credit notes) and Creditor accounts (Purchases and Supplier return documents) are listed by document numbers. The Debtor / Creditor account descriptions or names may not be displayed in the ascending sequence. To display the Debtor / Creditor account descriptions or names in the descending sequence (9-0 / Z-A), double-click on this heading. To display the Debtor / Creditor account descriptions or names in the ascending sequence (0-9 / A-Z), double-click on this heading again.

Context menu options

If you select a document on the list, you may right-click to launch the following context menu:



The options are as follows:

1. Set as From Option - This will set and display the selected document number as the starting document number in the range options From ... field.

2. Set as To Option - This will set and display the selected document number as the end document number in the range options To... field.

3. Update - This will update (post) the document to the ledger.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Reverse posted documents

This facility allows you to cancel or reverse all the transactions and balances of a selected document which have been updated (posted) to the ledger. This process will automatically:

- Export (remove) the transactions from the transaction file (TransAct.DB) file, reset the totals and account balances of all the accounts (which is linked to the selected stock items on Stock items (Default ribbon), debtor or creditor accounts, stock quantities, etc.

- The reversed document may then be selected for the debtor or creditor, edited and posted to the ledger. If you do not need to update (post) the document to the ledger, you may delete the document in Edit → Documents (Default ribbon).

The balances of the accounts and stock item records will be corrected automatically for the following documents:

- Documents for Debtors (customers / clients) (Invoices or Credit notes) - debtor account, sales account, cost of sales and stock control account as well as any Output VAT/GST/Sales Tax accounts and the quantities and cost prices of any stock items.

- Documents for Creditors (suppliers) (Purchase or Supplier return documents) - creditor account, cost of sales and stock control account, as well as any Input VAT/GST/Sales Tax accounts, and the quantities and cost prices of any stock items returned to creditors (suppliers).

The Log-report in Setup → Access control (Setup ribbon) will list the date and time, as well as which user and on which device, the documents were cancelled as REVDOC - Reverse doc! and the Batch ID.

If a document for a debtor (customer / client) (Invoice is generated or a Quote which is confirmed and converted to an Invoice), or if a document for a creditor (supplier / vendor) (purchase document is generated an order is confirmed and converted to a purchase document), and these documents are not yet updated

(posted) to the ledger, the following options are available to edit the transactions and/or comments:

- *Delete Document - delete the entire document, including all transactions and comments in the document.*
- *Delete transactions and/or comments in a document - only the selected transaction(s), or comment(s), will be deleted from the document.*

It is recommended that you make a backup of the Set of Books, before you start to use this facility to cancel or reverse a posted batch. In the event of making a mistake or if some problems are experienced, you may then easily restore the Set of books from the backup file.

It is strongly recommended that you take the utmost precautions, before you use this facility. The following is a few guidelines to be taken into account, before using this facility:

- *Invoices - Once an invoice is already handed to, or sent to a debtor (customer / client), you need to generate a credit note to reverse or cancel the invoice.*
- *Purchase documents - Once a purchase document is already handed to or sent to a creditor (supplier / vendor), you need to generate a supplier return document to reverse or cancel the purchase document.*

This is of importance as the debtor (customer / client) or creditor (supplier / vendor) will receive the documents (invoice or purchase document), and record it in their books. They will then receive no source document to cancel or correct the source document received earlier in their records. If you and your debtors (customers / clients) or creditors (suppliers) are registered as VAT/GST/Sales Tax-vendors, it may have implications for VAT/GST/Sales Tax.

To reverse or cancel all the transactions in a posted document:

1. On the Setup ribbon, select Global processes → Reverse posted batch/document . The "*Reverse posted batch/document"* screen is displayed, listing only the posted batches on the Batches tab:



By default, only the posted batches will be listed. If you select (tick) the "No document po" (No documents posting) option, it will add the posted documents to the posted batches on the list.

2. To list the posted documents, click on the Documents tab. The "*Reverse posted batch/document"* screen will change to list all the documents which are already updated (posted) to the ledger.



Doc. no.	Date	Reference	docid
CR000002	2021/06/22	D-102	58
CR000003	2021/06/30	C-103	61
IN000001	2021/03/13	AB-IN110	32
IN000002	2021/03/14	IB-101	33
IN000003	2021/03/15	PH-101	34
IN000004	2021/03/16	IB-102	35
IN000005	2021/04/07	D-101	40
IN000006	2021/04/09	C-102	41
IN000007	2021/04/10	C-103	42
IN000008	2021/04/11	D-102	43
IN000009	2021/05/07	PH-101	44
IN000010	2021/05/08		46
IN000011	2021/06/05	D-101	47
IN000012	2021/06/07	C-102	48
IN000013	2021/06/10	C-103	49
IN000014	2021/06/12	D-102	50
IN000015	2021/06/15	D-101	51
IN000016	2021/06/17	C-102	52
IN000017	2021/06/20	C-103	53
IN000018	2021/06/24	D-102	54
IN000019	2021/06/30	D-101	55
IN000020	2021/06/30	A-103-2	56
IN000021	2021/06/30	C-103	67
PU000001	2021/03/14	AAB234GP	29
PU000002	2021/03/15	IN0014	30
PU000003	2021/04/05	4562	37
PU000004	2021/04/06	3532	38
PU000005	2021/06/26	4562	62
PU000006	2021/06/09	3532	63
PU000007	2021/06/25	4562	76
SR000001	2021/06/24	3532	64
SR000002	2021/06/17	4562	65
SR000003	2021/06/19	4562	66
SR000004	2021/06/26	4562-A	77
ST00002	2021/05/07	Shortage	71
ST00003	2021/06/03	Surplus	73

38

The document numbers for Invoices, Credit notes, Purchases and Supplier returns, as prefixed in the Documents setup (Setup ribbon), makes it easy to identify the document type.

The following documents may be included:

- *Stock adjustments - Document numbers prefixed with "ST" is a 7-digit document number. These are automatically generated when doing stock adjustments (changes in the quantities on hand). These stock adjustments does not show any transactions and it prints a blank Posted batch type reports.*

- *BOM (Production) stock type - Assemble / Disassemble context menu options - Document numbers prefixed with"SA" will be a 7-digit number.*
- *Project Quote - Document numbers prefixed with"D" will be a 7-digit number.*

3. Select the posted document you need to reverse or cancel from the list.

If you have more than one updated (posted) document to cancel (reverse), you may press the Ctrl key and click on each document you wish to reverse / cancel.

If you have more than one updated (posted) document to cancel (reverse), you may click on the Select from delimited list button.

For example, if you wish to cancel (reverse) Invoices IN000003 and IN000004 as well as Credit note CR000001 simultaneously, enter each of the document numbers separated by a comma (without a space) e.g. IN000003,IN000004,CR000001. If you click on the Reverse posted document button, all the selected documents will be cancelled (reversed) during the same process.

4. View the details of the document(s) to make absolutely sure that it is the correct document(s).

To view the details of the transactions in the selected document(s), you may:-

- *Double-click on the selected document(s).*
- *On the Details tab, the transactions for the selected document(s) will be listed.*



If you wish to print a list of the transactions in the posted batch (posted batches), you may click on the Print button to



*The Cost of Sales "*COST OF SALES entries for each stock item will not be printed.*

5. Click on the Reverse posted document button to start the process. The following information message will be displayed:

> This will radically alter your data! We recommend that you stop and make a backup!
> Do you wish to continue?

6. Click on the Yes button, only if you are absolutely sure that the selected document(s) is correct, and that you need to continue with this process.

> *If you have not made a backup of the Set of Books before starting this process it is recommended that you click on the No button and first make a backup of the Set of Books.*

7. If you click on the Yes button, the process will be started.

8. Wait until the process is finalised.

> *A log displaying the new quantities for each stock item on the reversed documents will be displayed, for example:*



You may copy this information to Notepad or your favourite text editor.

It is advisable not to use your system for other tasks while this process is running.

Once this process is finalised, the selected document will not be listed on the Reverse posted document screen.

9. Click on the Close button in the title bar of the Reverse posted batch/document screen.

10. Click on the Invoice icon, and select the document type. If you select the debtor or creditor, for which the document was reversed, or cancelled, you may select the reversed document number. You may then edit these documents, delete the transactions, etc. Once the document is corrected, you may update (post) the document to the ledger.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Export Documents - Export grid

The Export button of the sidebar of the "*Documents*" list screen, will create a text file (tab delimited), which will open in your system's default Microsoft Excel (if installed on your system).

Export options

To export documents:

On Documents (Default ribbon), select the document type.

Select the document status; i.e. "*All, Posted, Unposted*" or "*Confirmed*".

> *Select the Filter and search options in the Filter column and click on the Filter button to include only those filter criteria to be included in the Export file.*



Click on the Export button. The "*Save As*" screen is displayed:



Enter a name to save the file.

"Save as type :" options will be "CSV". A text (.txt) file type will automatically be created with your file name.*

If you do not enter a unique name in the selected folder, and save the export.csv or export.txt file name, you may replace existing (previously exported) files.

If an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "F:\exports\your-file-name.txt". The process cannot access the file because it is being used by another process.

Click on the Save button.

Example : Exported text file - Microsoft Excel

In this example, the exported file is automatically opened in "*Microsoft Excel*":



id	Document no.	Date	Due date	Accid	Printed	Amount excl.	Amount incl.	Due	Tax amo	Reference	Document group 1	Documer	Account no.	Description	Salesper	Status
72	IN000022	2021/06/30	2021/07/30	54	2	5,000.00	5,750.00	5,750.00	750	C-103	Document group 1	Empty	D1ABGRE	Mr. AB Green	Russell	0
67	IN000021	2021/06/30	2021/07/30	54	1	5,000.00	5,750.00	5,750.00	750	C-103	Document group 1	Empty	D1ABGRE	Mr. AB Green	Russell	0
56	IN000020	2021/06/30	2021/07/30	54	2	5,000.00	5,750.00	2,875.00	750	A-103-2	Document group 1	Empty	D1ABGRE	Mr. AB Green	Russell	1
55	IN000019	2021/06/30	2021/07/30	54	0	5,000.00	5,750.00	0	750	D-101	Document group 1	Empty	D1ABGRE	Mr. AB Green	Tracy	1
54	IN000018	2021/06/24	2021/07/24	28	0	2,000.00	2,300.00	2,300.00	300	D-102	Document group 1	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1
53	IN000017	2021/06/20	2021/07/20	27	0	2,500.00	2,875.00	2,875.00	375	C-103	Document group 1	Empty	D1MDAVI	Mr. Mike Davies	Russell	1
52	IN000016	2021/06/17	2021/07/17	28	0	3,000.00	3,450.00	3,450.00	450	C-102	Document group 1	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1
51	IN000015	2021/06/15	2021/07/15	27	0	1,000.00	1,150.00	1,150.00	150	D-101	Document group 1	Empty	D1MDAVI	Mr. Mike Davies	Tracy	1
50	IN000014	2021/06/12	2021/07/12	28	0	2,000.00	2,300.00	2,300.00	300	D-102	Document group 1	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1
49	IN000013	2021/06/10	2021/07/10	27	0	1,500.00	1,725.00	1,725.00	225	C-103	Document group 1	Empty	D1MDAVI	Mr. Mike Davies	Russell	1
48	IN000012	2021/06/07	2021/07/07	28	0	3,000.00	3,450.00	3,450.00	450	C-102	Document group 1	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1
47	IN000011	2021/06/05	2021/07/05	54	0	1,000.00	1,150.00	1,150.00	150	D-101	Document group 1	Empty	D1ABGRE	Mr. AB Green	Tracy	1
46	IN000010	2021/05/08	2021/06/07	27	0	1,000.00	1,150.00	1,150.00	150		Document group 1	Empty	D1MDAVI	Mr. Mike Davies	Russell	1
44	IN000009	2021/05/07	2021/06/06	54	3	1,000.00	1,150.00	1,150.00	150	PH-101	Document group 1	Empty	D1ABGRE	Mr. AB Green	Russell	1
43	IN000008	2021/04/11	2021/05/11	28	2	2,000.00	2,300.00	2,300.00	300	D-102	Document group 1	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1
42	IN000007	2021/04/10	2021/05/10	27	0	1,500.00	1,725.00	1,725.00	225	C-103	Document group 1	Empty	D1MDAVI	Mr. Mike Davies	Russell	1
41	IN000006	2021/04/09	2021/05/09	28	2	3,000.00	3,450.00	3,450.00	450	C-102	Document group 1	Empty	D1ROGSM	Mr. Roger Smith	Tracy	1
40	IN000005	2021/04/07	2021/05/07	27	0	1,000.00	1,150.00	0	150	D-101	Document group 1	Empty	D1MDAVI	Mr. Mike Davies	Tracy	1
35	IN000004	2021/03/16	2021/04/15	27	0	1,500.00	1,725.00	1,725.00	225	IB-102	Document group 1	Empty	D1MDAVI	Mr. Mike Davies	Tracy	1
34	IN000003	2021/03/15	2021/04/14	54	0	1,000.00	1,150.00	1,150.00	150	PH-101	Document group 1	Empty	D1ABGRE	Mr. AB Green	Russell	1
33	IN000002	2021/03/14	2021/04/13	56	0	1,500.00	1,725.00	1,725.00	225	IB-101	Document group 1	Empty	D1MACDS	MAC Shop Decor Sp	Tracy	1
32	IN000001	2021/03/13	2021/04/12	54	0	1,000.00	1,150.00	1,150.00	150	AB-IN110	Document group 1	Empty	D1ABGRE	Mr. AB Green	Russell	1

Only those documents matching your filter and search criteria in the Filter column options, will be included in the export file.

For example, if the Document status is selected as "Unposted", only those unposted documents will be included in the export file. Posted documents will be excluded from the export file.

All of the thirty-six (36) columns will be exported in the default sequence.



Example : Exported text file - Notepad

An example, of the exported text file file opened in your systems default program associated with *.txt files (e.g. "*Notepad*") is as follows:



Example : Exported text file - LibreOffice Calc

If the exported text file does not open in Microsoft Excel; or if you do not have Microsoft Excel installed on your system, you may open the file with OpenOffice, LibreOffice, Ultra Office, etc.

Locate the exported text file in your System's File Explorer.

In this example, Open with > LibreOffice Calc is selected. The "*Text Import*" screen is selected.



If LibreOffice and not LibreOffice Calc is selected, the exported text file will open in LibreOffice Writer as a text file.



Separator options - Separated by

Tab is the only option which should be selected for this exported text file. This may differ for some other report types.



Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Export / Import documents

Using this export feature, you may also export the data for sales documents (Invoices, Credit notes and Quotes) as well as purchase documents (Purchases, Supplier returns and Orders) in an open Set of Books to the available file formats.

All the information for each account as entered in Documents (Default ribbon), will be exported in the selected file format for the selected dates.

To import documents, it is recommended that a valid "TurboCASH Exchange file (.txf)" file is generated in the Export - Documents option on the Setup ribbon. This will only include the documents on the dates selected to include in the export file. These exported documents may then be imported from the Others → Import context menu option on the "Documents list" screen.*

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Export documents

Document Export / Import plugin - Manual - Shop - Licence: Once-off

The Document Export / Import plugin allows you to export sales documents (invoices, credit notes and

quotes) and purchase documents (purchases, supplier returns and orders) to a TurboCASH Exchange (.txf) or a Comma Separated Value (*.csv) file format. You may then select an exported documents file (context menu Others → Export) and import the exported file in the (context menu Others → Import) options in the documents grid.*

Using this facility, you may also export the data for sales documents (invoices, credit notes and quotes) as well as purchase documents (purchases, supplier returns and orders) in an open Set of Books to the available file formats.

All the information for each document, as entered in Documents (Default ribbon), will be exported in the selected file format.

To be able to import the data for sales documents (invoices, credit notes and quotes) as well as purchase documents (purchases, supplier returns and orders) in Import (Setup ribbon), you need to create a valid XML Database File format on your system in Export (Setup ribbon).

To export Documents:

1. On the Setup ribbon, select Export.
2. Click on the Documents button.



3. Select and/or enter the following:

    a) Export to - The installation directory in which osFinancials5/TurboCASH5 is installed, will be displayed. You may click on the Browse icon to select a folder on the *Browse for Folder* screen. You may then select any available folder, or drive, on your system into which you wish to export the data.

    b) File type - Select to export the file in the XML Database (*XML), Comma Separated Variable (*CSV), Lotus Spreadsheet File (*WK1), MS Excel Spreadsheet (*XLS), or any other format available on your system from the list.

    c) Export files name - Enter the File name. You need to select this file at a later stage when you wish to import the file, or analyse the data in a spreadsheet.

    d) Log file - Enter the Log file name.

    e) Range - From / To - Select the date from and to. All documents in the selected period(s) should be included in the export file.

4. Click on the Export button to create the export file, and save it in the specified directory.

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Import documents

Document Export / Import plugin - Manual - Shop - Licence: Once-off

The Document Export / Import plugin allows you to export sales documents (invoices, credit notes and quotes) and purchase documents (purchases, supplier returns and orders) to a TurboCASH Exchange (.txf) or a Comma Separated Value (*.csv) file format. You may then select an exported documents file (context menu Others → Export) and import the exported file in the (context menu Others → Import) options in the documents grid.*

This option will allow you to import data for sales documents (invoices, credit notes and quotes) as well as purchase documents (purchases, supplier returns and orders) from a valid file format into an existing Set of Books.

To be able to import the data for sales documents (invoices, credit notes and quotes) as well as purchase documents (purchases, supplier returns and orders), you need to have created a valid XML Database File format on your system in Export (Setup ribbon).

To import documents:

1. On the Setup ribbon, select Import. The "*Import Data into osFinancials*" screen is displayed:



2. Select Documents as the "*Data type to import*".

3. Select a valid exported in which the data to import, is saved on your system.

4. Click on the button to locate the data file. The following screen is displayed:



5. Click on the button to locate the data file.

6. Click on the button. The following screen is displayed:



7. Click on the Import button. The "*ImportCheck*" screen is displayed:



8. You may use the record buttons to add, delete or change the stock records on the "*ImportCheck*" screen. You may then click on the All or OK buttons to import the stock file.

9. Once the import process is finished an information message is displayed:

   "Data file import completed!"

10. Click on the OK button.

11. Go to the Default ribbon and select Documents to edit the stock items, if necessary.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Exported documents in Spreadsheets

Using this export feature, you may also export the data for sales documents (Invoices, Credit notes and Quotes) as well as purchase documents (Purchases, Supplier returns and Orders) in an open Set of Books to the available file formats.

All the information for each document as entered in Documents (Default ribbon), will be exported in the selected file format for the selected dates.

To illustrate the exported fields and data, the exported text file is opened in a spreadsheet.

Once the exported documents is saved in the "(*.XLS) MS Excel SpreadSheet" file format, it will create 2 files:

1. Headers file
2. Lines file

You may open these files with your spreadsheet application i.e Excel, LibreOffice, OpenOffice, Ultra Office, etc.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Exported documents - Headers files in Spreadsheets

If you have saved the documents for the selected periods as a "MS Excel SpreadSheet (*.XLS)" file type, you can open this export file for the document header ("*Header*") in a spreadsheet.

An example of the exported file opened in "*LibreOffice Calc*" spreadsheet, is as follows:



WDOCID	WTYPEID	DDATE	DALLOCATE	SDOCNO	SREFERENC	BPRINTED	BPOSTED	BEXCLUSIVE	FINVOICEDI	FDOCAMOU	FTAXAMOU	WACCOUNT	WPAYMENT	WPAYMENTI	BREPEATI
47	10	2021/06/05	2021/06/05	IN000011	D-101	0	1	1	0	1150	150	54	0	0	
48	10	2021/06/07	2021/06/07	IN000012	C-102	0	1	1	0	3450	450	28	0	0	
49	10	2021/06/10	2021/06/10	IN000013	C-103	0	1	1	0	1725	225	27	0	0	
50	10	2021/06/12	2021/06/12	IN000014	D-102	0	1	1	0	2300	300	28	0	0	
51	10	2021/06/15	2021/06/15	IN000015	D-101	0	1	1	0	1150	150	27	0	0	
52	10	2021/06/17	2021/06/17	IN000016	C-102	0	1	1	0	3450	450	28	0	0	
53	10	2021/06/20	2021/06/20	IN000017	C-103	0	1	1	0	2875	375	27	0	0	
67	10	2021/06/30	2021/06/30	IN000021	C-103	1	0	1	0	5750	750	54	0	0	
54	10	2021/06/24	2021/06/24	IN000018	D-102	0	1	1	0	2300	300	28	0	0	
72	10	2021/06/30	2021/06/30	IN000022	C-103	13	0	1	0	5750	750	54	0	0	
73	16	2021/06/03		ST00003	Surplus	1	1	0	0	0	0	0	0	0	
55	10	2021/06/30	2021/06/30	IN000019	D-101	0	1	1	0	5750	750	54	0	0	
56	10	2021/06/30	2021/06/30	IN000020	C-103	6	1	1	0	5750	750	54	0	0	
57	11	2021/06/29	2021/06/29	CR000001	D-101	0	1	1	0	5750	750	54	0	0	
58	11	2021/06/22	2021/06/22	CR000002	D-102	0	1	1	0	2300	300	28	0	0	
59	14	2021/06/20	2021/06/20	QU000004	D-102	0	-1	1	0	1150	150	28	0	0	
60	14	2021/06/24	2021/06/24	QU000005	C-103	1	-1	1	0	5750	750	54	0	0	
61	11	2021/06/30	2021/06/30	CR000003	C-103	0	1	1	0	2875	375	54	0	0	
62	12	2021/06/26	2021/06/26	PU000005	4562	1	1	1	0	1725	225	29	0	0	
63	12	2021/06/09	2021/06/09	PU000006	3532	2	1	1	0	2300	300	29	0	0	
64	13	2021/06/24	2021/06/24	SR000001	3532	0	1	1	0	2300	300	30	0	0	
65	13	2021/06/17	2021/06/17	SR000002	4562	0	1	1	0	1725	225	29	0	0	
66	13	2021/06/19	2021/06/19	SR000003	4562	0	1	1	0	1725	225	29	0	0	

The exported document header data will be exported in forty-two (42) columns:

Column	*Column heading*	*Source / fields*	*Notes*
A	*WDOCID*	*Document ID*	*Integer (Auto generated for each new document created or imported).*
B	*WTYPEID*	*Document type ID*	*Integer* *10 = Invoice* *11 = Credit note* *12 = Purchase* *13 = Supplier return* *14 = Quote* *15 = Order* *16 = Stock adjustment*
C	*DDATE*	*Date of document*	*Date*
D	*DALLOCATE DDATE*	*Date*	*Date*

E	*SDOCNO*	*Document no.*	*String (8) Prefixes added in templates followed by 6 numeric digits.* *IN = Invoice* *CR = Credit note* *PU = Purchase* *SR = Supplier return* *QU = Quote* *OR = Order* *ST = Stock adjustments (Hard coded)*
F	*SREFERENCE*	*Your reference*	*String (15)*
G	*BPRINTED*	*Printed*	*0 = Document never been printed* *1 or more = Document have been printed or reprinted*
H	*BPOSTED*	*Posted*	*0 = Document is unposted* *1 = Document is posted (updated to the ledger)*
I	*BEXCLUSIVE*	*Exclusive of tax*	*0 = Document is inclusive of tax* *1 = Document is exclusive of tax*
J	*FINVOICEDISCOUNT*	*Invoice discount*	*Float(numeric)*
K	*FDOCAMOUNT*	*Document amount (inclusive of tax)*	*Float(numeric)*
L	*FTAXAMOUNT*	*Tax amount*	*Float(numeric)*
M	*WACCOUNTID*	*Account ID*	*Integer*
N	*WPAYMENTTYPEID*	*Payment type ID*	*Integer*
O	*WPAYMENTG*	*Payment group ID*	*Integer*

	ROUPID		
P	*BREPEATING*	*Repeating invoice*	*0 = Document is not set as repeating* *1 = Document is set as repeating*
Q	*DSYSDATE*	*System date*	*Date*
R	*SACCOUNTCODE*	*Account code*	*String (6) Need to have this prefixed when creating accounts followed by 5 characters. In this example it is prefixed as follows:* *1 = Debtors* *2 = Creditors*
S	*WACCOUNTTYPEID*	*Account type ID*	*Integer* *1 = Debtors* *2 = Creditors* *4 = Stock adjustment*
T	*SPostCompany*	*Name (description) of Debtor / Creditor account*	*String (35)*
U	*SPostContact*	*Name of the contactperson*	*String (35)*
V	*SDelCompany*	*Name (description) of Debtor / Creditor account*	*String (35)*
W	*SDelContact*	*Delivery contactperson*	*String (35)*
X	*STAXREF*	*Tax reference*	*String (35)*
Y	*SPost1*	*Postal address 1*	*String (35)*
Z	*SPost2*	*Postal address 2*	*String (35)*
AA	*SPost3*	*Postal address 3*	*String (35)*

AB	*SPostCode*	*Postal code*	*String (20)*
AC	*SMsg1*	*Message 1*	*String (35)*
AD	*SMsg2*	*Message 2*	*String (35)*
AE	*SMsg3*	*Message 3*	*String (35)*
AF	*SSalesperson*	*Salesperson*	*String (30)*
AG	*SDel1*	*Delivery address 1*	*String (35)*
AH	*SDel2*	*Delivery address 2*	*String (35)*
AI	*SDel3*	*Delivery address 3*	*String (35)*
AJ	*SDelCode*	*Delivery code*	*String (35)*
AK	*SGroup1*	*Document group 1*	*String (35)*
AL	*SGroup2*	*Document group 2*	*String (35)*
AM	*SCurrency*	*Currency*	*String*
AN	*SUserName*	*User name*	*String (30)*
AO	*SPostCountry*	*Postal address country*	*String (64)*
AP	*SDelCountry*	*Delivery address country*	*String (64)*

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Exported documents - Lines files in Spreadsheets

If you have saved the documents for the selected periods as a "MS Excel SpreadSheet (*.XLS)" file type, you can open this export file for the document lines ("*Lines*") in a spreadsheet.

An example of the exported file opened in "*LibreOffice Calc*" spreadsheet, is as follows:



WDOCID	WLINETYPEI	WDOCLINEI	WSTOCKID	FQTYORDE	FQTYSHIPP	FSELLINGPP	FITEMDISCO	WTAXID	FINCLUSIVE	FEXCLUSIVE	FTAXAMOUI	WSORTNO	SDescription	SACCOUNT	SBARCODEI
47	90	0	3	1	1	1000	0	68	1150	1000	150	1	Drill press	860010	
48	90	0	4	2	2	1500	0	68	3450	3000	450	1	Compressor	860010	
49	90	0	4	1	1	1500	0	68	1725	1500	225	1	Compressor	860010	
50	90	0	3	2	2	1000	0	68	2300	2000	300	1	Drill press	860010	
51	90	0	3	1	1	1000	0	68	1150	1000	150	1	Drill press	860010	
52	90	0	4	2	2	1500	0	68	3450	3000	450	1	Compressor	860010	
53	90	0	4	1	1	1500	0	68	1725	1500	225	1	Compressor	860010	
53	91	1	0	0	0	0	0	0	0	0	0	2	30 Days money back guarantee. Plase use high pressure spravguns and p Serial number: XEF-0018-0019-0020.		
53	90	2	3	1	1	1000	0	68	1150	1000	150	3	Drill press	860010	
53	91	3	0	0	0	0	0	0	0	0	0	4	Serial number: DXP-200-01500		
67	90	0	4	2	2	1500	0	68	3450	3000	450	1	Compressor	860010	
67	91	1	0	0	0	0	0	0	0	0	0	2	30 Days money back guarantee. Plase use high pressure spravguns and p Serial number: XEF-0018-0019-0021. Serial number: XEF-0018-0019-0022.		
67	90	2	3	2	2	1000	0	68	2300	2000	300	3	Drill press	860010	
67	91	3	0	0	0	0	0	0	0	0	0	4	Serial number: DXP-200-01501 Serial number: DXP-200-01502		
54	90	0	3	2	2	1000	0	68	2300	2000	300	1	Drill press	860010	
72	90	0	4	2	2	1500	0	68	3450	3000	450	1	Compressor	860010	
72	91	1	0	0	0	0	0	0	0	0	0	2	30 Days money back guarantee. Please use high pressure spravguns and Serial number: XEF-0018-0019-0021. Serial number: XEF-0018-0019-0022.		

The exported data will be exported in seventeen (17) columns:

Column	*Column heading*	*Source / fields*	
A	*WDOCID*	*Document ID*	*Integer (Auto generated for each new document created or imported).*
B	*WLINETYPEID*	*Document line type ID*	*Integer* *90 = Line item (stock item)* *91 = Comment*
C	*WDOCLINEID*	*Document line ID*	*Integer* *0 = Line 1* *1 = Line 2* *2 = Line 3, etc.*
D	*WSTOCKID*	*Stock item ID*	*Integer (ID for each stock item)*
E	*FQTYORDERED*	*Quantity ordered*	*Float(numeric)*
F	*FQTYSHIPPED*	*Quantity shipped*	*Float(numeric)*

G	*FSELLINGPRICE*	*Selling price*	*Float(numeric)*
H	*FITEMDISCOUNT*	*Item discount*	*Float(numeric)*
I	*WTAXID*	*Tax account ID*	*Integer*
J	*FINCLUSIVEAMT*	*Amount inclusive of Tax*	*Float(numeric)*
K	*FEXCLUSIVEAMT*	*Amount exclusive of Tax*	*Float(numeric)*
L	*FTAXAMOUNT*	*Tax amount*	*Float(numeric)*
M	*WSORTNO*	*Sort number*	*Integer* *Line ID used for sorting items on document lines*
N	*SDescription*	*Description on lines*	*String (290)* *Line type 90 = Stock item description* *Line type 91 = Comment*
O	*SACCOUNTCODE*	*Account code*	*String (6)*
P	*SBARCODENUMBER*	*Barcode number*	*String*
Q	*SSTOCKCODE*	*Stock item code*	*String (15)*

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Calendar / Planner

In osFinancials5/TurboCASH5, the Calendar feature provides a comprehensive tool for managing your agenda, tasks, appointments, contacts, and more within a Set of Books. It offers a range of functionalities to help you stay organised and efficiently handle your events and tasks in a Set of Books.

One of the key features of the Calendar is its ability to schedule events with various recurrence options. You can set events to repeat on a daily, weekly, monthly (by day or date), yearly (by day or date), or custom interval. This allows you to automate the scheduling of repetitive events, such as meetings, reminders, or recurring invoices.

The Calendar supports different event types, including general appointments, repeating invoices for managing regular billing processes, debtor appointments for scheduling interactions with customers or clients (with the option to create quotes and invoices directly from these appointments), and creditor appointments for scheduling interactions with suppliers. Additionally, you can schedule hours to invoice debtors based on time spent and generate quotes for those hours, which can later be edited and converted into invoices.

To make it easier to distinguish between different event categories, the Calendar uses colour coding, which helps visually identify the type of event when displayed in the Calendar view.

In addition to event management, the Calendar also provides functionalities to handle tasks. You can add, edit, and delete tasks, allowing you to maintain a to-do list and set completion dates for each task. Furthermore, the Calendar allows you to manage contacts, enabling you to search, add, edit, or delete contacts within your Set of Books.

Another notable feature is the bulk time entry option, which facilitates the efficient processing of quotes and invoices for specific salespersons, debtor accounts, and stock items. You can allocate time slots for each entry, streamlining the invoicing process for time-based services or activities.

Overall, the Calendar in osFinancials5/TurboCASH5 serves as a powerful tool for managing your agenda, tasks, appointments, contacts, and bulk time entries. It offers a comprehensive set of features to enhance your organisation, productivity, and invoicing processes within the software.

The Calendar is a powerful tool, which integrates your agenda (tasks, appointments, contacts, etc.) in a Set of Books. You may manage all your events in this Calendar with options to set the recurrence of an event (i.e. daily, weekly, monthly by day, monthly by date, yearly by day, yearly by date or custom, where you may specify the interval in days).

In addition to scheduling all your events, the Calendar has a powerful reminder system which may be set to remind you of a scheduled event, or task, well in advance (from any number of minutes, hours and even days).

Event categories

The Calendar feature offers the flexibility to schedule and create various types of events or appointments.

You can schedule or add events in the following categories:

1. Appointment (General): This category allows you to schedule general appointments, such as meetings with a bank manager or lunches with clients or colleagues.
2. Repeating invoices: If you have recurring invoices that need to be processed or copied regularly, you can schedule them as repeating invoices. This feature simplifies the task of generating invoices for repetitive transactions.
3. Hours: This category allows you to schedule services rendered on an hourly basis. Once the hours are scheduled, you have the option to generate Quotes based on the scheduled hours. These Quotes can be edited if necessary to ensure accuracy. After finalizing the Quotes, you can convert them into Invoices.
4. Debtors appointment: You have the ability to schedule up to six different categories of appointments with debtors (customers/clients). These categories can be customized based on your specific needs and can include appointments for specials, accounts, or any other relevant category. Moreover, you can create quotes and invoices directly from these debtor appointments, streamlining your quotations and invoicing processes.
5. Creditors appointment: This category allows you to schedule appointments with creditors (suppliers/vendors). You can use this feature to keep track of important meetings or discussions with your suppliers regarding orders, accounts, or any other related matters.

By leveraging these features in the Calendar, you can effectively manage and track various types of appointments, schedule repeating invoices, and create invoices for debtor appointments, all within osFinancials5/TurboCASH5.

The Calendar feature utilises colour coding to visually distinguish between different categories of events. This makes it easier to identify and differentiate the types of events when they are displayed on the Calendar. The colour-coded system helps you quickly recognise and navigate through your scheduled events, improving efficiency and organisation.

Additional features of the Calendar

In osFinancials5/TurboCASH5, the Calendar feature offers additional functionality to manage tasks, contacts, and bulk time entries.

1. Tasks: You can use the Calendar to manage your tasks effectively. This includes adding, editing, and deleting tasks such as bank reconciliation, printing debtor statements, printing creditor remittance

advises, and more. By keeping track of your tasks in the Calendar, you can easily monitor and complete your to-do list.

2. Contacts: The Calendar provides a convenient way to manage your contacts. You can find contacts by clicking on the alphabetical keys and perform various actions like adding, editing, or deleting contacts. This allows you to keep your contact information organized and easily accessible within the Calendar.

3. Bulk time entry: The Calendar feature also allows for bulk time entry. This functionality enables you to select a salesperson, debtor (customer/client) account, and stock item. You can then add time in specific slots to process invoices for the designated times and days. Bulk time entry simplifies the process of invoicing for multiple time entries, making it more efficient and less time-consuming.

By incorporating tasks, contacts, and bulk time entry into the Calendar, osFinancials5/TurboCASH5 provides a comprehensive platform for managing various aspects of your business operations in one centralized location.

Access and views of the Calendar

The Calendar is (by default) not displayed when you open a Set of Books. You may set the "Show calendar" option in Setup → System parameters to launch the Calendar as default view when you Open a Set of Books.

To access the Calendar:

1. On the Default ribbon, select Calendar.



2. The *Display* listing four (4) icons will be displayed. You may click on the following icons to change or display the view of the Calendar:

    a) Agenda - This is the default view of the Planner (Calendar). It displays the following three sections:

        i) Day view - This displays the selected day in time intervals of one hour each. If any events, or appointments, have been scheduled for the selected date, they will be displayed.

        You can also use the slider to view up to a week (seven days) at a time.

        ii) Calendar by month - displays the dates for the selected month. The selected day will be displayed in a red font colour.

        If any events, or appointments, have been scheduled for any dates within the selected month, the day will be underlined and displayed in a bold font style.

    b) Tasks - Lists all tasks, if any. Displays the tasks in the full viewable area.

    c) Contacts - Lists all the contacts created in the Set of Books alphabetically. You may find and filter contacts by clicking on alphabetical character buttons.

    *You may also manage (add, edit or delete) contacts in addition to Contacts on the (*Default ribbon*).*

    d) Bulk entry time entry - Select the salesperson, debtor (customer / client) account and the stock item. Add time in slots to process invoices for the times and days.

Multi-User calendar (agenda) - Manual - Shop - Licence : Once-off -

This plugin adds the multi-user agenda (multiple agendas) to the Calendar (Planner). You can add agendas and link them as default to the current user. For every agenda a tab will appear in the agenda Calendar so you can see what the appointments, etc. are on other agendas. You can have a agenda for each employee, salesperson, user, etc. and create invoices directly from his / her agenda with a simple click. Each agenda has it's own calendar and task list.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Calendar- Resource name

The Resource name links the events, tasks, etc. to a specific name in the Calendar. It will also print on the Calendar report.

Multi-User calendar (agenda) - Manual - Shop - Licence : Once-off -

This plugin adds the multi-user agenda (multiple agendas) to the Calendar (Planner). You can add agendas and link them as default to the current user. For every agenda a tab will appear in the agenda Calendar so you can see what the appointments, etc. are on other agendas. You can have a agenda for each employee, salesperson, user, etc. and create invoices directly from his / her agenda with a simple click. Each agenda has it's own calendar and task list.

By default a Resource is already defined as osFinancials or osFinancials5/TurboCASH5 in each of the Firebird database templates you may download from the Downloads screen launched from the Creation wizard - Let osFinancials help you to create a Set of Books? option.

After creating a Blank database on the Creation wizard - Customise your own Set of Books (Advanced)? option, no resource is available for the blank database.



When you start to add an Event to the Calendar for the first time, the following confirmation message is displayed:

> No resources have been defined! Would you like to add one now?

Click Yes to add a Resource name.

The resource name or description field can accommodate up to 255 characters in the "RESOURCES" table.

The Task form can only display up to 12 characters.



Click OK to save the resource.

Created with the Standard Edition of HelpNDoc: Make your documentation accessible on any device with HelpNDoc

Set the Calendar as default

In osFinancials5/TurboCASH5, the default behaviour is for the Welcome screen to be launched when opening a Set of Books. However, you have the option to activate the Calendar to be launched instead. This means that whenever you open a Set of Books, the Calendar will be automatically displayed as the default screen.

Activating the Calendar as the default screen can be useful if you frequently rely on the Calendar feature and want quick access to it whenever you open your Set of Books. It allows you to directly view and manage your scheduled events, appointments, and other calendar-related tasks without having to navigate through the Welcome screen first.

To set the Calendar as the default when opening the Set of Books:

1. On the Setup ribbon, select Setup → System parameters.



2. Select (tick) the "*Show calendar*" field.

3. Click on the OK button.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Create / Add events (Appointments)

In osFinancials5/TurboCASH5, the Calendar feature offers the flexibility to schedule and create various types of events or appointments. You can schedule or add events in the following The Calendar feature offers the flexibility to schedule and create various types of events or appointments. You can schedule or

add events in the following categories:



1. Appointment (General): This category allows you to schedule general appointments, such as meetings with a bank manager or lunches with clients or colleagues.
2. Repeating invoices: If you have recurring invoices that need to be processed or copied regularly, you can schedule them as repeating invoices. This feature simplifies the task of generating invoices for repetitive transactions.
3. Hours: This category allows you to schedule services rendered on an hourly basis. Once the hours are scheduled, you have the option to generate Quotes based on the scheduled hours. These Quotes can be edited if necessary to ensure accuracy. After finalizing the Quotes, you can convert them into Invoices.
4. Debtors appointment: You have the ability to schedule up to six different categories of appointments with debtors (customers/clients). These categories can be customized based on your specific needs and can include appointments for specials, accounts, or any other relevant category. Moreover, you can create quotes and invoices directly from these debtor appointments, streamlining your quotations and invoicing processes.
5. Creditors appointment: This category allows you to schedule appointments with creditors (suppliers/vendors). You can use this feature to keep track of important meetings or discussions with your suppliers regarding orders, accounts, or any other related matters.

By leveraging these features in the Calendar, you can effectively manage and track various types of appointments, schedule repeating invoices, and create invoices for debtor appointments, all within osFinancials5/TurboCASH5.

The Calendar feature utilises colour coding to visually distinguish between different categories of events. This makes it easier to identify and differentiate the types of events when they are displayed on the Calendar. The colour-coded system helps you quickly recognise and navigate through your scheduled events, improving efficiency and organisation.

To add (create) events or appointments:

1. Select a suitable time on the day-time view of the agenda and right-click. The following context menu is

displayed:



a) Add event - Select this option to create a new event. You can choose the category of the event, select the salesperson associated with the event, and provide all the necessary details such as description, start and end time, reminders, appointment recurrence, location, select a default stock item or product for the event, add notes, and any other relevant information.

b) Edit event - If you have already created an event, you can select it and choose the "*Edit event*" option to modify its details. This allows you to make changes such as updating the title, salesperson, adjusting the time, rescheduling the event, change the appointment recurrence, setting or removing reminders, selecting a default stock item or product, adding notes, or updating any other information associated with the event.

c) Delete event - This option allows you to delete a selected event. If you want to remove a previously created event, select it and choose the "*Delete event*" option from the context menu. You will be prompted to confirm the deletion before the event is permanently removed.

d) Create invoice - By selecting this option, you can generate an invoice for a selected debtor (customer/client) account directly from the event. This simplifies the invoicing process by automatically populating the invoice with the relevant details from the event.

e) Create quote - If you need to create a quote for a selected debtor (customer/client) account, you can select this option. It enables you to generate a quote based on the information provided in the event. The quote can be further customized, finalized, and sent to the customer for review.

Change to Agenda - option may be available on the context menu.

Multi-User calendar (agenda) - Manual - Shop - Licence : Once-off -

This plugin adds the multi-user agenda (multiple agendas) to the Calendar (Planner). You can add agendas and link them as default to the current user. For every agenda a tab will appear in the agenda Calendar so you can see what the appointments, etc. are on other agendas. You can have a agenda for each employee, salesperson, user, etc. and create invoices directly from his / her agenda with a simple click. Each agenda has it's own calendar and task list.

These options in the context menu of the Calendar provide convenient ways to add, edit, delete events or appointments, as well as create invoices or quotes directly from the agenda in

osFinancials5/TurboCASH5.

2. To create a new event, select the "*Add event*" option. The "*Untitled - Event*" screen is displayed:



3. Enter the subject (topic) of the appointment.

4. Select the category (i.e. Appointment, Repeating invoices, Debtors appointment (up to six (6) categories) or Creditors appointment).

5. Set the "*Start time*" and "*End time*" for the appointment. The selected time, when the "*Add event*" option was launched, will be displayed.

> *If you wish to mark this event as an all day event, select the "All day event" option. You are then not able to set the start and the end date.*

6. Select the appointment recurrence (i.e. "*None*" (default), "*Daily, Weekly, Monthly by day, Monthly by date, Yearly by day, Yearly by date*" or "*Custom*").

> *If "Custom" is selected, you may set the interval in the number of days.*

> *If the Recurrence is set to any other value than "None", the Repeat until date will be displayed for one calendar year, e.g. 07/05/2022 if the start date is 07/05/2023.*

You may then select a date until, which the event or appointment is to be repeated.

7. Select the Reminder option if you need to be reminded of the event or appointment.

This will remind you of a scheduled event or task well in advance (from any number of minutes, hours and even days) until the event or appointment is deleted.

8. Enter any additional information or notes about the appointment. This will also be displayed when you edit the event or when the Reminder is displayed.

9. Click on the OK button to save the event or appointment.

Created with the Standard Edition of HelpNDoc: Free Qt Help documentation generator

Create documents - Events (Appointments)

Event categories

The Calendar feature offers the flexibility to schedule and create various types of events or appointments. You can schedule or add events in the following categories:

1. Appointment (General): This category allows you to schedule general appointments, such as meetings with a bank manager or lunches with clients or colleagues.

2. Repeating invoices: If you have recurring invoices that need to be processed or copied regularly, you can schedule them as repeating invoices. This feature simplifies the task of generating invoices for repetitive transactions.

3. Hours: This category allows you to schedule services rendered on an hourly basis. Once the hours are scheduled, you have the option to generate Quotes based on the scheduled hours. These Quotes can be edited if necessary to ensure accuracy. After finalizing the Quotes, you can convert them into Invoices.

4. Debtors appointment: You have the ability to schedule up to six different categories of appointments with debtors (customers/clients). These categories can be customized based on your specific needs and can include appointments for specials, accounts, or any other relevant category. Moreover, you can create quotes and invoices directly from these debtor appointments, streamlining your quotations

and invoicing processes.

5. Creditors appointment: This category allows you to schedule appointments with creditors (suppliers/vendors). You can use this feature to keep track of important meetings or discussions with your suppliers regarding orders, accounts, or any other related matters.

By leveraging these features in the Calendar, you can effectively manage and track various types of appointments, schedule repeating invoices, and create invoices for debtor appointments, all within osFinancials5/TurboCASH5..

The Calendar feature utilises colour coding to visually distinguish between different categories of events. This makes it easier to identify and differentiate the types of events when they are displayed on the Calendar. The colour-coded system helps you quickly recognise and navigate through your scheduled events, improving efficiency and organisation.

Additional features of the Calendar

In osFinancials5/TurboCASH5, the Calendar feature offers additional functionality to manage tasks, contacts, and bulk time entries.

1. Tasks: You can use the Calendar to manage your tasks effectively. This includes adding, editing, and deleting tasks such as bank reconciliation, printing debtor statements, printing creditor remittance advises, and more. By keeping track of your tasks in the Calendar, you can easily monitor and complete your to-do list.

2. Contacts: The Calendar provides a convenient way to manage your contacts. You can find contacts by clicking on the alphabetical keys and perform various actions like adding, editing, or deleting contacts. This allows you to keep your contact information organized and easily accessible within the Calendar.

3. Bulk time entry: The Calendar feature also allows for bulk time entry. This functionality enables you to select a salesperson, debtor (customer/client) account, and stock item. You can then add time in specific slots to process invoices for the designated times and days. Bulk time entry simplifies the process of invoicing for multiple time entries, making it more efficient and less time-consuming.

By incorporating tasks, contacts, and bulk time entry into the Calendar, osFinancials5/TurboCASH5 provides a comprehensive platform for managing various aspects of your business operations in one centralized location.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Repeating invoices - Calendar

The "*Repeating invoices*" appointment category in the Calendar feature of osFinancials5/TurboCASH5 provides a convenient way to schedule and generate recurring invoices for your debtors (customers/clients). This feature is especially useful for invoices that occur frequently or on a regular basis, such as monthly service fees or subscription payments.

With the "*Repeating invoices*" category, you have the flexibility to select invoices for selected debtors or debtors linked to a selected group that need to be generated repeatedly. These can be invoices for specific services or products that are billed to multiple debtors or a single debtor.

Once you have selected the invoices to be generated, osFinancials5/TurboCASH5 will automatically generate invoice numbers and copy the document details into the normal invoice document for the selected debtor or debtors. This eliminates the need for manual entry of invoice information, saving you time and reducing the chances of errors.

To review and make any necessary edits to the generated invoices, you can access the Invoices section of osFinancials5/TurboCASH5. Here, you can check the details, adjust any amounts or descriptions if needed, and ensure the accuracy of the invoices before they are sent to the debtors.

After reviewing and editing the invoices, the next step is to update (post) them to the ledger. This final step ensures that the generated invoices are properly recorded in the accounting system and reflected in the relevant debtor accounts.

By utilizing the "*Repeating invoices*" category in the Calendar, you can streamline the invoicing process for recurring transactions. It eliminates the need to manually enter the same invoices each month and reduces the risk of overlooking or forgetting to bill for recurring services. This feature in osFinancials5/TurboCASH5 saves you time and effort by automating the generation of repeating invoices, allowing you to focus on other aspects of your business.

Schedule Repeating invoice events

To schedule a Repeating Invoice Event:

1. On the Default ribbon, select Calendar. The Planner (Display - Agenda - the default screen) will be displayed.

2. Select a suitable time and right-click on the Day View. On the context menu, select the Add Event option. The *Untitled - Event* screen is displayed:



3. Enter and select the following:

   a) Subject - Enter the subject for the repeating invoices event. This subject needs to be a sensible one to allow you to easily identify and manage the scheduled event on the Calendar.

   b) Category - Select the category as Repeating invoices. This will be indicated with red in the Calendar. (Other options are Appointments, Debtors Appointments or Creditors Appointments).

   c) Start time ... End time - The selected time when the Add Event option was launched, will be displayed. You may set or adjust the Start time, if necessary.

> *You may need to:*
>
> - *If it will take longer than the default 30 minutes (from the Starting time), you may adjust the end time.*
> - *If you wish to mark this event as an all day event, select the "All day event" option. You will then not be able to set the start and the end date.*

   d) Recurrence - This is the frequency and times you may schedule the repeating invoices. For example, if you need to process the Invoices on a monthly basis, you may select the "*Monthly by day*" or the "*Monthly by date*" options.

Select the appointment recurrence (i.e. "None" (default), "Daily, Weekly, Monthly by day, Monthly by date, Yearly by day, Yearly by date" or "Custom"). If "Custom" is selected, you may set the interval in the number of days.

Interval (days) - If "Custom" is selected you may set the interval in the number of days, for example, 30 days if you need to process the repeating invoices every 30 days.

Repeat until - If the Recurrence is set to any other value than "None", the "Repeat until date" will be displayed for one calendar year, e.g. 07/05/2022 if the end date is 07/05/2023.

e) Reminder - Select this option, if you need to be reminded of the event or appointment. This will remind you of a scheduled event or task well in advance (from any number of minutes, hours and even days). This will also remind you until the Event or appointment is deleted.

f) Notes / Information - Enter any notes or additional information about the appointment. This will also be displayed when you edit the event, or when the "*Reminder*" is displayed.

4. Click on the OK button.

Copy scheduled Repeating invoice

To copy scheduled Repeating invoices:

1. You may also open the event - Repeating invoices using the following two options:

   a) Click on the Open item button of the Reminder screen to edit the event - Repeating invoices.

   b) Right-click on the event - "*Repeating invoices*" on the Calendar. Select the Add event option. This will launch the Repeating invoices - Event screen.

2. On the Event tab you may edit any of the fields you need to edit. You may also add any additional information or edit any notes or information already added when the event or appointment was created or previously edited.

3. Click on the Repeating invoice tab. The following Process list screen is displayed:



4. The first time the Process list screen is displayed, no Invoices will be listed. Click on the New button to copy or set the Invoices as recurring invoices. The following screen is displayed:



5. Enter and select the following:

    a) Type - Select one of the following:

        i) Copy Invoice (default option) - to copy a selected Debtor account.

        ii) Copy Invoice to group 1 - this will copy a selected document (Invoice or Quote) to all Debtor accounts linked to a specific debtor group 1.

This option is only available if you have created Debtor groups 1 in Setup → Groups (Debtors).

b) Debtor - Select one of the following:

i) If the Copy Invoice has been selected, select the Debtor account for which you need to set or copy a selected Invoice as a Repeating Invoice.

ii) If the Copy Invoice to group 1 has been selected, you need to select an available debtor group from the drop-down list.

c) Documents - Select a specific document (Invoice or Quote) from the drop-down list. This Invoice will be set or copied to a selected Debtor account, or to all Debtor accounts within the selected Debtor group 1.

6. Select the date on which these repeating invoices are to be processed / generated, if necessary.

7. Enter a message which you would like to be displayed on the repeating Invoice, or all repeating invoices for the selected Debtor group 1.

8. Click on the OK button. All Repeating invoices will be listed on the Process list.

Edit scheduled Repeating invoices

Once a document (Invoice or Quote) has been copied or added to the Process list, you may edit the Process List, if necessary. The process list will display a list of the copied documents. The following information for each document will be displayed on each row:

- Account number - Account number or account code of the Debtor account.
- Description - Account description or name of the Debtor account.
- Debtor group 1 - The debtor group 1 if the selected Debtor account have been linked to a Debtor group 1 and the Copy Invoice to group 1 option was selected will be displayed.
- Document number - The selected document number from which the repeating Invoice will be copied to create / generate a new Invoice.
- Reference - The reference, if entered on the Document entry screen for the document.

The following options are available:

- Edit button - click to edit the selected Repeating Invoice's selection (Type, Debtor / Debtor

group 1 or Documents).

- Delete button - click to remove the selected Repeating invoice from the Process list.

Process scheduled Repeating invoices

Once a document (Invoice or Quote) has been copied or added to the Process list, you may process or create the Repeating documents. Before you do this, you need to check that the date is correct and enter or edit the message, if necessary.

To Process Scheduled Repeating invoices:

When you are ready you may click on one of the following buttons:

1. Process selected - click to process or create a document for selected Debtor accounts, or all Debtor accounts linked to the selected debtor group 1, from the selected document on the process list.
2. Process All - click to process or create documents for selected Debtor accounts or all Debtor accounts linked to the selected debtor group 1 from the selected document on the process list. Once the process is finished, a confirmation message will be displayed.

   "Document(s) created!"

3. Click on the OK button to close or exit the Repeating invoices - Process list screen, or Repeating invoices - Event screen.

Edit / Process copied / created invoices

When the Invoices are created with this feature, osFinancials5/TurboCASH5 will automatically generate document numbers for each Invoice. The created / generated Invoices will be listed on the Document list screen for Invoices.

To do this, go to Invoices. You need to select the Debtor account and the Invoice number to check, edit (if necessary) and print the Invoices.

Finally you need to update (post) the Invoices to the ledger. This will update the transactions to the general ledger, debtors ledger, and the stock ledger. You may select the Invoice and edit the Invoices before posting or updating it to the ledger.

Should you by accident have generated a Repeating invoice incorrectly to a Debtor account, you need to delete the Invoice.

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Invoices - Hours - Calendar

The "*Hours*" appointment category in the Calendar feature of osFinancials5/TurboCASH5 is designed for scheduling services rendered on an hourly basis. This category is particularly useful for professions that charge their clients based on the amount of time spent, such as consultants, contractors, or other service providers.

When you schedule hours appointments in the Calendar, you can specify the duration and details of the services provided. This allows you to track and manage your time effectively and ensure accurate billing for your clients.

Once the hours are scheduled, you have the option to generate Quotes based on the scheduled hours. Quotes serve as a preliminary document outlining the services and associated costs for your debtors. These Quotes can be edited if necessary to ensure accuracy.

After finalizing the Quotes, you can convert them into Invoices. The Quotes serve as a basis for creating the actual invoices that you send to your debtors for payment. This conversion process helps streamline the invoicing workflow and ensures that the services provided are accurately reflected in the invoices. The integration of the Calendar with the billing functionality in osFinancials5/TurboCASH5 streamlines the invoicing process and eliminates the need for manual data entry.

By using the "*Hours*" category in the Calendar, you can keep track of your time spent on different tasks or projects, allocate it to the corresponding debtors (customers/clients), and seamlessly generate quotes for invoicing. This integration between time tracking and billing ensures accurate and efficient billing processes for services provided on an hourly basis.

Overall, the "*Hours*" appointment category in the Calendar feature of osFinancials5/TurboCASH5 serves as an electronic diary and time sheet, allowing you to schedule, track, and invoice your hours-based services to your debtors (customers/clients) with ease and accuracy.

This option generates Quotes and not Invoices. The reason for this, is:

- *Quotes are used to schedule the hourly services in the future.*
- *Once the service is rendered, the Quotes are edited and confirmed (converted to invoices).*
- *You may also view and print the Invoice on the Documents tab of the Debtor account (Default ribbon). Once the Invoice is posted (updated to the ledger), it will be listed as a debit transaction on the Transactions tab of the Debtor account.*

- *You may also select a specific person (salesperson) which will render these services.*

To create Invoices for Hours:

1. On the Default ribbon, select Calendar.
2. Select the day and a time slot to schedule the hours.
3. Select a date and right-click on a time slot. On the context menu, select the Add event... option. The "*Untitled – Event*" screen will be displayed.



4. On the *Untitled Event* screen, enter and/or select the following:

   a) Subject - Leave blank. This will automatically be filled in with the debtor (customer / client) account code, description and Salesperson when selecting it. If you have entered any text in the "*Subject*" field (fourth Empty) field, this text would also be included in the subject (for example "*Paint exterior*".

   b) Category - Select *Hours* (Magenta colour).

   c) Hours - Click on the *Hours* field. Select a debtor customer account.

   d) Projects - *Empty* is the default project. Select a Project from the list.

e) Salesperson - Select a salesperson. If the consultant or the salesperson is not added you need to exit this screen and first add a salesperson in Setup → Salesperson or in Setup → Groups (Salesperson).

f) Quote - Leave blank.

g) All day event - Leave blank.

h) Start time - Select *2024/05/03*. This is the date and time as selected on the Calendar from where the *Untitled - Event* screen was launched. If this date is not correct, you may select the correct date. Enter or select the time slot, if not correct.

i) End time - Enter the time expected to finish the project.

j) Appointment recurrence - The default is "*None*".

k) Repeat until - Field disabled.

l) Reminder - Leave blank. You may activate it and set the Minutes, Hours or Days to remind you in advance to process invoices for hours.

m) Stock item - You may select a default stock item (product) for this Appointment.

5. After scheduling the invoices for hours, the screen should display as follows:



The Subject and the Titlebar will display the Debtor (customer / client) account code and name as well as the name of the salesperson (consultant). If Projects are activated, you may select the project. The selected Project code and description will be displayed.

6. Click on the OK button.

7. On the Agenda (top of the screen), click on the Create invoices for hours button.



The "*Hours between date*" options screen is displayed:



8. Select the date from and date to in which the hourly fee is to be charged (e.g. *2024/05/03*).

9. Click on the Lookup icon and select the stock item for services (or the correct Stock item if you have created one).

10. Click on the OK button to create the quote. An information message will be displayed.

"Quote(s) generated!"

11. Click on the OK button.

This Quote may be viewed on the following options:

- *Document entry screen - Quotes document type - as Unposted (i.e. Not converted to an Invoice).*
- *Projects on the list of a selected Project.*
- *Documents tab of the Debtor (customer / client) account. Once the Quote is confirmed (converted to an invoice and the Invoice is posted (updated to the ledger), it will be listed as a debit transaction on the Transactions tab of the Debtor account.*

You may need to edit the quote, e.g. add comments, change the hours, etc. change the Project code (if projects are activated), before converting it to an Invoice.

The Hours – Event will be displayed in Purple (Magenta) colour on the time slot of the scheduled day. The Day in the calendar will also be underlined and displayed in a Purple (Magenta) font.

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Create invoices - Debtor appointments

You may also create invoices for any of the six (6) categories of appointments scheduled with debtors (customers / clients).

To create invoices for debtor (customer / client) appointments:

1. On the Calendar, select any of the six (6) categories of debtor appointments and right-click.



2. On the context menu, select the "*Create Invoice*" option. A new invoice entry screen, displaying all the information and details for the debtor (customer / client) account will be displayed.



3. Enter and/or select the necessary fields and select a stock item.

4. Click on the OK button.

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

Create quotes - Debtor appointments

You may also create quotes for any of the six (6) categories of appointments scheduled with debtors (customers / clients).

To create quotes for debtor (customer / client) appointments:

1. On the Calendar, select any of the six (6) categories of debtor appointments and right-click.



2. On the context menu, select the "*Quote*" option. A new Quote entry screen, displaying all the information and details for the debtor (customer / client) account will be displayed.



3. Enter and/or select the necessary fields and select a stock item.

4. Click on the OK button.

This Quote may be viewed on the following options:

- *Document entry screen - Quotes document type - as Unposted (i.e. Not converted to an Invoice).*
- *Projects on the list of a selected Project.*
- *Documents tab of the Debtor (customer / client) account. Once the Quote is confirmed (converted to an invoice and the Invoice is posted (updated to the ledger), it will be listed as a debit transaction on the Transactions tab of the Debtor account.*

You may need to edit the quote, e.g. add comments, change the quantities, etc. change the Project code (if projects are activated), before converting it to an Invoice.

Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

Bulk time entry

The bulk time entry feature in the Calendar of osFinancials5/TurboCASH5 allows you to efficiently add multiple time entries for a salespersons and a specific debtor (customer/client) account. This feature is particularly useful when scheduling recurring appointments or events.

To use bulk time entry, you can select the desired dates and set the time for a salesperson's hours event on the Calendar. For example, if a debtor (customer/client) has booked a training course or workshop for a week, you can easily schedule appointments for each day of that week. These bulk time entries will create multiple appointments on the calendar as hours-type events for the selected dates and time slots.

Once the bulk time entries are created, you have the option to generate quotes for these events. Quotes can be customised and edited as needed before sending them to the debtor (customer/client). This allows for clear communication and documentation of the scheduled appointments or services.

After the appointments are completed, you have the flexibility to convert the quotes to invoices. This streamlined process eliminates the need for manual data entry and ensures accuracy in billing and invoicing. By converting the quotes to invoices, you can efficiently generate invoices based on the scheduled appointments and bill the debtor (customer/client) for the services provided.

Overall, the bulk time entry feature in osFinancials' Calendar provides a convenient way to schedule and manage multiple appointments for salespersons and debtors (customers/clients). It enables the creation of quotes, smooth transition to invoices, and simplifies the workflow for tracking and billing services.

See video on Bulk time entries

To process bulk entries:

1. On the Default ribbon, select Calendar.
2. Click on the Bulk time entry button.
3. Select the dates / days and a time slot to schedule the hours.
4. "*Week*" is the default option - it displays Monday to Sunday. If the "*Week*" option is not selected it will list only the selected date.
5. Select the Salesperson and enter the start dates and number of hours.
6. Select a stock item (usually sales no stock type)
7. Select the debtor (customer / client) account.



8. Click on the Create entries button. A confirmation message will be displayed.

"Entries created!"



9. Once the entries are created, these entries will be listed in the calendar.



10. You may edit these events, set reminders and add notes.

11. On the top of the screen, click on the Create invoices for hours button.



The "*Hours between date*" options screen is displayed:



12. Select the dates (from date and to date) and a Stock item.

13. Click OK. An information message will be displayed.

    "Quote(s) generated!"

    A quote is generated for the entries on the Bulk time entries for the selected dates and number of hours.

14. You may edit the quote



15. Check and edit the quote, if necessary. You may wish to:

    a) Enter a reference.

b) Enter a message.

c) Add comments and remarks, as needed.

d) Change the number of hours and selling prices.

e) Add discount, etc.

16. Click OK to save the quote.

17. Once these appointments bookings are done, you may print the quote and forward it to the debtor (customer / client). The quote needs to be converted to an invoice.

The bulk time entries will be printed in the "Calendar - Hours" report (Reports → Calendar (Reports ribbon).



These bulk time entries will be listed in the Appointment tab of the selected debtor (customer / client) account.



If you double-click on a selected appointment, the Bulk time entry screen will be launched. You may select the dates edit resch

---

Created with the Standard Edition of HelpNDoc: Free Qt Help documentation generator

Tasks - Calendar

In osFinancials5/TurboCASH5, the Calendar feature includes the ability to manage tasks or a to-do list. You can add, edit, or delete tasks according to your requirements. When creating a task, you can specify a completion date to indicate when the task should be completed.

Additionally, you have the option to include notes or additional details for each task. These notes can serve as reminders for additional steps, procedures, contact information such as phone numbers, or any other relevant information related to the task.

By utilising the task management functionality in the osFinancials5/TurboCASH5 Calendar, you can stay organized and keep track of your to-do list efficiently. This feature helps you manage and prioritize your tasks effectively, ensuring that important activities are completed within the desired time-frame.

You may add, edit, or delete tasks (to do list), and set a completion date when the tasks should be completed. You may also add some notes to each task to remind you of additional steps, procedures,

phone numbers, etc.

All tasks (excluding the deleted tasks, will display as follows:



- Future tasks - If tasks have not yet reached its completion date, these tasks will be displayed in a grey font.
- **Expired tasks** - Will display in a **red** font colour.
- Tasks marked as completed - The field is ticked and the task displays a stripe through it. The task will also be displayed in a grey font.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Add / Create task - Calendar

To add (create) a task:

1. To create a new task, simply right-click on any area of the Task list section of the Agenda screen.
2. On the context menu, select the Add task... option. The Untitled - Task screen will be displayed.
3. Enter the subject (topic) of the task.
4. Select the Due date when the task should be completed.
5. Enter any additional information or notes for the task.
6. Click on the OK button to save the task.



Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Edit task - Calendar

Once a task has been added, you may then edit it, if necessary.

To edit a task:

1. Select a task on the Task list section of the Agenda screen, and right-click to select the Edit task... option.

> *The subject (topic) of the task will be displayed in the title bar of the Task screen. If you create a new task it will be displayed as Untitled - Task.*

2. Edit any of the fields you need to edit. You may also add any additional information, or edit any notes or information already added when the task was created, or previously edited.
3. If the task is completed, select the Complete field (tick in box). When a Task is set as completed, the Task will be ticked and striped through on the Task list.

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with a Help Authoring Tool

Delete task - Calendar

Once a task has been added, you may then edit it or reschedule it, if necessary. If you wish to permanently remove an existing task, you need to delete the task.

To delete a task:

1. To delete a task, simply select the task, and right-click on the selected task. On the context menu, select the Delete task... option. A confirmation message will be displayed.

   "Delete Cash flow from your task list? This operation cannot be undone!" (Cash flow is the name of the task, as per this example).

   Make absolutely sure that the correct task is selected. If you click on the Yes button by accident, you need to create and add / enter all the details.

2. Click on the Yes button. The task will be removed from the list.

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Contacts - Calendar

In osFinancials5/TurboCASH5, the Calendar feature provides the ability to manage contacts, ensuring that any changes made to contact information are reflected across the system. The following options on the Default ribbon allow you to create, edit, or delete contacts, with all updates being synchronized with the Contacts in the Calendar:

1. Contacts: This option allows you to access the general Contacts section, where you can manage and maintain contact information for debtors (customers/clients) and creditors (suppliers/vendors).
2. Debtors - Contacts tab: This tab specifically focuses on managing contacts associated with debtor accounts. You can add, edit, or delete contacts linked to debtor accounts, ensuring that the contact details are up to date.
3. Creditors - Contacts tab: Similar to the Debtors - Contacts tab, this tab is dedicated to managing contacts associated with creditor accounts. You can modify the contact information for your suppliers/vendors to maintain accurate records.

By utilizing these options, you can conveniently manage contacts within osFinancials5/TurboCASH5,

ensuring that all contact information remains consistent and accessible across different sections in a Set of Books.



You may print a "*Contact listing*" report for all debtors (customers/clients) as well as contacts for creditors (suppliers / vendors) from Contacts option on the Default ribbon. Additionally "*Contact listing*" reports may be printed in the following options on the Reports ribbon:

- Contact listing - This report will list all contacts for debtors (customers/clients) as well as contacts for creditors (suppliers/vendors). It offers a consolidated view of all contacts in your Set of Books.
- Reports → Debtors → Listing - Contacts - This report specifically focuses on contacts related to debtors (customers/clients). It provides a listing of contacts associated with your debtor accounts.
- Reports → Creditors → Listing - Contacts - This report specifically lists contacts related to creditors (suppliers/vendors). It presents a comprehensive view of contacts associated with your creditor accounts.

Created with the Standard Edition of HelpNDoc: Protect Your Confidential PDFs with These Simple Security Measures

Add / Create contacts - Calendar

To add (create) a contact:

1. Click on the Contacts icon (if the Contacts screen is not displayed).

2. To create a new contact, simply right-click on any area of the Contacts screen. On the context menu, select the Add contact... option. The Untitled - Contact screen is displayed:



3. Enter a Name for the contact. This Name will be displayed in the title bar, and on the Contact screen once this contact is saved.

4. Enter the title, address, city, state zip / postal code, country, company, position, and select the category of the contact (business, clients, family, other or personal).

5. Click on the Telephone tab. The following screen is displayed:



6. Enter up to two telephone numbers, a fax number and an e-mail address, if available / applicable. You may also enter two additional fields for the following:

    a) Number for - select one of the following: Mobile, Other, (phone), Other Fax, Pager, Primary, Radio, Telex, TTY/TDD, Work or Work Fax, then enter the number for the selected option.

    b) Number for - select one of the following: Assistant (default), Call-back, Car, Company, Home, Home Fax, IDSN or Mobile, then enter the number for the selected option.

7. Once finished entering the necessary details, click on the Notes tab, if you need to enter additional information for the contact.

8. Click on the OK button.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with

HelpNDoc

Edit contacts - Calendar

Once a contact has been added, you may then edit it, if necessary.

To edit a contact:

1. To edit an existing contact, simply select the contact, and right-click on the selected contact. On the context menu select the Edit contact... option.

   *The Name of the Contact - *Contact will be displayed in the title bar.*

2. Edit any of the fields you need to edit on the Main tab, Telephone tab or the Notes tab.

3. Click on the OK button.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Delete contacts - Calendar

If you wish to permanently remove an existing contact, you need to delete the contact.

To delete a contact:

1. To delete a contact, simply select the contact, and right-click on the selected contact. On the context menu, select the Delete contact... option. A confirmation message will be displayed.

   "Delete Mike Davies from your list of contacts? This operation cannot be undone!" (Mike Davies is the name and surname of the contact, as per this example).

   Make absolutely sure that the correct contact is selected. If you click on the Yes button by accident, you need to create and add / enter all the details.

2. Click on the Yes button. The contact will be removed from the list.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

Reminders

In osFinancials5/TurboCASH5, the Calendar feature includes a Reminder functionality that helps you stay organised and on top of your scheduled events and appointments. Here are the key options available for managing reminders:

1. Dismiss: By clicking on the Dismiss option, you can turn off the reminder for a specific event or appointment. If you no longer wish to receive reminders for that particular item, this option allows you to deactivate the reminder. If needed, you can always edit the event later to enable the reminder again.



2. Snooze: If you're not ready to address the reminder at that moment but would like to be reminded later, you can click on the Snooze option. This will postpone the reminder and provide you with options to set a customised time interval for the reminder to reappear. You can choose intervals such as 5, 10, 15, 30, or 45 minutes, as well as 1 to 8 hours, 1 to 6 days, or 1 week.

3. Open item: Clicking on the Open item option allows you to directly access and edit the event or appointment associated with the reminder. You can make any necessary changes, finalise or reschedule the appointment, and even activate or deactivate the reminder based on your preferences.

By utilising these reminder management options, you can efficiently handle your scheduled events and appointments, ensuring that you stay informed and can take appropriate actions when needed.

Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Open item link

What is the open item processing?

Open item processing is indeed a method of managing financial transactions, and it is commonly used in accounts receivable (debtors ledger) and accounts payable (creditors ledger) to track outstanding invoices, payments, and balances in a detailed and organized manner.

In addition to its primary application in accounts receivable and accounts payable, open item processing can also be extended to manage financial transactions for selected accounts in the general ledger. This approach allows organizations to maintain detailed records of specific general ledger accounts, monitor balances, reconcile transactions, and generate comprehensive financial reports for those accounts.

Open item processing in the general ledger can be particularly useful for accounts that require a high level of scrutiny or where tracking individual transactions is important. This method helps ensure transparency and accuracy in financial management across various accounts within an organization's financial system.

Open Item Basics

In open item processing, each individual transaction, such as an invoice or payment, is tracked separately as an "*open item*" until it is paid or resolved. This means that the transaction is not considered fully completed until the balance has been paid in full. The open item remains on the debtor or creditor account as a record of the transaction until it is fully paid, and any remaining balance is kept open until the next payment is received.

The advantage of open item processing is that it provides a detailed and accurate record of all transactions, making it easier to identify and resolve payment issues. It allows for more precise tracking of payments and outstanding debts, and helps to ensure that all transactions are accounted for. However, it can require more administrative work to manage and track individual transactions.

Open item processing is commonly used in industries such as retail, where there are multiple transactions for each customer, and in business-to-business transactions, where there are ongoing relationships between the debtor and creditor.

What is balance forward and open item processing?

Balance forward and open item processing are two different methods used to manage financial transactions, particularly in accounts receivable (debtors control account) and accounts payable (creditors control account). These methods differ in how they handle outstanding balances and invoices.

1. Balance Forward Processing:
    - In balance forward processing, customer or supplier accounts typically carry forward a running balance from one period to the next, rather than tracking individual transactions. The

outstanding balance is updated based on the net effect of transactions within a given period.

- Balance forward processing is a more simplified approach. It is often used for low-volume transactions or in situations where tracking individual invoices is less critical. This method is commonly used for utilities, subscriptions, or regular service fees.
- Customers or suppliers receive statements that show their beginning balance, transactions during the period, and ending balance. The statement may not provide a detailed breakdown of individual invoices or payments.

2. Open Item Processing:

- Open item processing, on the other hand, meticulously tracks individual transactions, such as invoices and payments, without carrying forward balances from one period to the next. It maintains a list of "open" or outstanding items until they are fully cleared.
- With open item processing, each invoice and payment is tracked separately, and the system maintains a record of which invoices are paid and which ones are still outstanding. It provides a more detailed and transaction-specific view of the accounts.
- Open item processing is typically used in situations where detailed tracking of transactions is essential, such as in accounts receivable and accounts payable for businesses with a high volume of transactions.

In summary, the key distinction between balance forward processing and open item processing lies in how they manage outstanding balances and transactions. Balance forward processing carries forward balances, while open item processing maintains a detailed record of individual transactions until they are reconciled. The choice between these methods depends on the specific needs and complexity of an organization's financial processes and the level of detail required for effective management and reporting.

Open Item Account Basics in osFinancials

Open item processing allows you to allocate (match / link) each debit transaction to a credit transaction and each credit transaction to a debit transaction; which are posted to the same account.

Basically most or all receipts or payments transactions, should be matched when processing transactions in batches. When allocating transactions to an account, which is set as an Open item account, an "*Open item selection*" screen will list all the transactions with outstanding amounts. You may then select a specific outstanding transaction on a list to link the transaction to.

By default, Open item is not activated when an account is created. You need to activate or set an account as an Open item account.

Debtor (customer / client) accounts / Creditor (supplier / vendor) accounts

The basics for debtor (customer / client) accounts and creditor (supplier / vendor) accounts, which is set as an "*Open item account*", is as follows:

- Debtor (customer / client) accounts - By default, the " *Open item selection*" screen will be launched when allocating credit transactions (e.g. payments received or credit notes, etc.) to debit transactions (e.g. Invoices, Credit notes, and other debit transactions such as interest on overdue accounts, etc.)
- Creditor (supplier / vendor) accounts - By default, the "*Open item selection*" screen will be launched when allocating debit transactions (e.g. payments on account or supplier returns, etc.) to credit transactions (e.g. Purchases, and other credit transactions such as charge amounts, etc.).

There are various options to filter and manage the details, totals and transactions of open item accounts.

General ledger accounts

The "*Open item link*" for a specific ledger account may be opened with a double-click from the Totals tab or the Transactions tab on Open item link.

Some examples of such ledger accounts may be;

- Advance accounts - You may wish to keep track and manage advances paid to an employee or salesperson for subsistence and travel. After the employee or salesperson returns from his trip, he return the expenses source documents and refund any unused monies. When processing these source documents in batches, etc., these transactions may be linked (matched) to the original advance.
- Suspense / Clearing accounts - When an transactions needs to be managed, matched or reconciled, etc.

Open item link access in osFinancials

To access the Open item link feature, click on the Open item link icon (Default ribbon).

There are four (4) tabs, i.e. Totals, Transactions, Unposted batches and Due tabs to manage open item accounts.



You may also edit or unlink the existing links, or even convert a specific account to the "*Balance brought forward*" method, where any payment or receipt will be set off against the oldest outstanding amount.

Created with the Standard Edition of HelpNDoc: How to Protect Your PDFs with Encryption and Passwords

Open item link - Settings

---

osFinancials5/TurboCASH5 allows two basic methods of age processing Ledger, Debtor and Creditor transactions. These age type processing methods are:

- Balance brought forward -
  - Debtor (customer) accounts - The credit transactions (payments received, debtor allowances, credit notes or any other credit transaction) are allocated to the oldest outstanding debit transaction (opening balances, invoices, etc.) amount.
  - Creditor (supplier / vendor) accounts - The debit transactions (payments made to creditors, creditor allowances or supplier returns documents or any other debit transaction) are allocated to the oldest outstanding credit transaction (opening balances, purchases, etc.) amount.
- Open item -
  - Debtor (customer) accounts - Open item is by default not activated. To activate Open item processing for a debtor (customer / client) account, select (tick) the "*Open item*" field on the Accounting information tab of a selected debtor (customer / client) account.



The credit transactions (payments received, debtor allowances, credit notes or any other credit transaction) may be linked to any selected outstanding debit transaction (opening balances, invoices, etc.) amount.

- Creditor (supplier / vendor) accounts - Open item is by default not activated. To activate Open item processing for a creditor (supplier / vendor) account, select (tick) the "*Open item*" field on the Accounting information tab of a selected creditor (supplier / vendor) account.

  The debit transactions (payments made to creditors, creditor allowances or supplier return documents or any other debit transaction) may be linked to any selected outstanding credit transaction (opening balances, purchases, etc.) amount.

- General ledger accounts - Accounts (Setup ribbon) Open item account field – Default is No. You may set it to Yes.



The Open item account option is not available for the Retained earnings / income, Debtor's control and Creditor's control accounts.

Open item processing of ledger accounts, may be useful for suspense accounts, clearing accounts, advance accounts for subsistence and travel, etc.

You may link debit transactions to credit transactions or credit transactions to debit transactions.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Open item link - Disable / Enable in batches

By default, the "*Open item selection*" feature is enabled in batches. The last column, i.e. "*Open item*", will be available in "*Batch entry*" screens.

If the "*Open item*" column is displayed, and you wish to disable open item processing, you may disable this feature.

To disable open item in batches:

1. On the "*Batch entry*" screen, click F10: Setup.



2. On the Advanced tab, add a tick in the "*Not open item batch*" field.



3. Click OK. The "*Open item*" column will be removed from the "*Batch entry*" screen.



Created with the Standard Edition of HelpNDoc: Effortlessly Publish Your Word Document as an eBook

Open item link - Totals tab

The Totals tab will list the transaction total and total outstanding total for open item accounts.

Show colours - Option selected where no transactions have incorrect or outstanding links.



Show colours - If this field is, selected, This will show red or orange colours for those accounts and transactions which have incorrect or outstanding links.



Account type:

- *1 - Debtor accounts (Open item account field selected (ticked) on the Accounting information tab in Debtors (Default ribbon).*
- *2 - Creditor accounts (Open item account field selected (ticked) on the Accounting information tab in Creditors (Default ribbon).*
- *0 - General ledger (Open item account field set to Yes in Setup → Accounts).*
- *3 - Bank accounts (Open item account field set to Yes in the Setup → Accounts).*
- *4 - Tax accounts (Open item account field set to Yes in the Setup → Accounts).*

Filter options

Filter options:

1. Search by - Select any of the column headings and an operator (e.g. Like (default), =, <, >, <=, =>, or <>) and enter a value. Click on the Filter button. Only those transactions matching your specified values will be listed. To clear the values, click on the Clear button.
2. Account type - Select (tick) or deselect (remove the tick) to list the accounts for the selected account type(s) (Ledger, Debtors or Creditors).
3. Show colours - If this field is, selected, This will show red or orange colours for those accounts and transactions which have incorrect links.
4. Find invalid - Select (tick) and click on the Filter button to list those accounts and transactions which have incorrect links.
5. limitrows - Limit rows - 200 rows is the default number of rows or transactions to be listed. The number of rows may be specified (decreased or increased).
6. Export - This button will create an Export.txt (Text files), which you may change the name and folder and save it. A Comma separated (CSV) file format is also available. This will export the list, as selected and/or filtered and displayed in the Totals tab, as a comma separated text file as a "*Export.txt*" file. The Exported file will automatically be opened in your in your system's app (program) associated with the CSV (Comma Separated Values) file types.

Column headings

The columns is as follows:

1. Account - Account code.
2. Description - Account name or account description.
3. Account type - Ledger (General ledger accounts, Bank accounts and Tax accounts), Debtors or Creditors. The account type values is as follows:

> *Account type:*
>
> - *1 - Debtor accounts (Open item account field selected (ticked) on the Accounting information tab in Debtors (Default ribbon).*
> - *2 - Creditor accounts (Open item account field selected (ticked) on the Accounting information tab in Creditors (Default ribbon).*
> - *0 - General ledger (Open item account field set to Yes in Setup → Accounts).*
> - *3 - Bank accounts (Open item account field set to Yes in the Setup → Accounts).*
> - *4 - Tax accounts (Open item account field set to Yes in the Setup → Accounts).*

4. Transaction total - The total of the actual transactions in posted batches and documents.
5. Total outstanding - The outstanding total of outstanding transactions, which is not matched linked. If the totals in the "*Transaction total*" and "*Total outstanding*" columns matches; or is displayed in the default system font, it means that all transactions are linked (matched). In this example, the font colour of "*ABC-Office-Supplies*", is in an orange font colour or row background colour. This indicates that there may be some transactions which is not linked (matched).

> *You may also drag columns to the "Use your mouse to pull a column here to group on that column" row.*

Context menu

Right-click on a selected account on the list, to launch the context menu for the following processing options.



Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Open item link - Transactions tab

The Transactions tab will list the transactions for open item accounts.

Open item link - Transactions tab - All transactions

Open transactions only - By default, this option is not selected and will list all transactions, including those with a 0.00 balance.



Account	Description	Reference	Batch entry	Transaction tot	Due	Due date	Date	Account type
		CR000003	Credit note /C-103	2,875.00-	2,875.00-	2021/07/30		
1ABGRE	Mr. AB Green	CR000001	Credit note /D-101	5,750.00-	0.00	2021/07/29	2021/06/30	1
		IN000020	Invoice /C-103	5,750.00	5,750.00	2021/07/30		
		IN000019	Invoice /D-101	5,750.00	0.00			
		IN000011	Invoice /D-101	1,150.00	1,150.00	2021/07/05	2021/06/05	
		IN000009	Invoice /PH-101	1,150.00	1,150.00	2021/06/06	2021/05/07	
		D5001	Payment received - Thank you	2,000.00-	0.00	2021/04/15	2021/03/16	
		IN000003	Invoice /PH-101	1,150.00	1,150.00	2021/04/14	2021/03/15	
		IN000001	Invoice /AB-IN110	1,150.00	1,150.00	2021/04/12	2021/03/13	
		INV003	Paint - Exterior	1,150.00	300.00	2021/04/09	2021/03/10	
		INV001	Paint - Exterior	1,150.00	0.00	2021/04/06	2021/03/07	
1MDAVI	Mr. Mike Davies	IN000017	Invoice /C-103	2,875.00	2,875.00	2021/07/20	2021/06/20	
		IN000015	Invoice /D-101	1,150.00	1,150.00	2021/07/15	2021/06/15	
		IN000013	Invoice /C-103	1,725.00	1,725.00	2021/07/10	2021/06/10	
		IN000010	Invoice /IN000010	1,150.00	1,150.00	2021/06/07	2021/05/08	
		IN000007	Invoice /C-103	1,725.00	1,725.00	2021/05/10	2021/04/10	
		IN000005	Invoice /D-101	1,150.00	1,150.00	2021/05/07	2021/04/07	
		IN000004	Invoice /IB-102	1,725.00	1,725.00	2021/04/15	2021/03/16	
		INV004	Install - Built-in cupboard	1,725.00	1,725.00	2021/04/10	2021/03/11	
		JNL2	Debtor opening balances - Feb 2(	500.00	500.00	2021/03/30	2021/02/28	
		JNL2	Debtor opening balances - Jan 2(	200.00	200.00	2021/03/02	2021/01/31	
		JNL2	Debtor opening balances - Dec 2	100.00	100.00	2021/01/30	2020/12/31	
2ABCOS	ABC-Office-Supplies	SR000004	Supplier returns /4562-A	1,725.00	1,725.00	2021/07/26	2021/06/26	
		PU000007	Purchases /4562	1,725.00-	1,725.00-	2021/07/25	2021/06/25	
		108	Payment on account	750.00	0.00	2021/04/29	2021/03/30	
		PU000002	Purchases /IN0014	1,725.00-	1,725.00-	2021/04/14	2021/03/15	
		PU002	Install - Built-in cupboards	1,725.00-	975.00-	2021/04/05	2021/03/06	
2AONES	A-ONE Suppliers	PU000005	Purchases /4562	1,725.00-	1,725.00-	2021/07/26	2021/06/26	
		120	Payment on account	2,300.00	0.00	2021/07/25	2021/06/25	2
		SR000003	Supplier returns /4562	1,725.00	1,725.00	2021/07/19	2021/06/19	
		SR000002	Supplier returns /4562	1,725.00	0.00	2021/07/17	2021/06/17	
		PU000006	Purchases /3532	2,300.00-	0.00	2021/07/09	2021/06/09	
		PU000003	Purchases /4562	1,725.00-	0.00	2021/05/05	2021/04/05	
		JNL3	Creditor opening balances -Feb 2	300.00-	300.00-	2021/03/30	2021/02/28	
		JNL3	Creditor opening balances -Jan 2(	200.00-	200.00-	2021/03/02	2021/01/31	
36				18,500.00	18,500.00			

Open item link - Transactions tab - Open transactions only

Open transactions only - If this field is ticked, it will list only those transactions with a value of more than 0.00 in the "*Due*" column.



Open item link - Transactions tab - Context menu

Select an account and a transaction. Right-click to select the following options from the context menu:



- Adjust payment date - This will change the due date to a selected date.

- Receive payment - This feature, will automatically generate the transactions to the receipts batch for a selected transaction and print a combined receipt / payment advise (if selected). The transaction will automatically be posted (updated) to the ledger.

Open item link - Transactions tab - Filter options

Filter options:

1. Search by - Select any of the column headings and an operator (e.g. Like (default), =, <, >, <=, =>, or <>) and enter a value. Click on the Filter button. Only those transactions matching your specified values will be listed. To clear the values, click on the Clear button.

2. Account type - Select (tick) or deselect (remove the tick) to list the accounts for the selected account type(s) (Ledger, Debtors or Creditors).

3. Open transactions only - By default, this option is not selected and will list all transactions, including those with a 0.00 balance. If this field is ticked, it will list only those transactions with a value of more than 0.00 in the "*Due*" column.

> *The Transactions tab of a selected debtor (customer / client) account, will by default, only list the transactions with outstanding amounts. You may select the "All" option to view all the transactions, including those linked (matched) transactions.*
>
> *The Transactions tab of a selected creditor (supplier / vendor) account, will by default, only list the transactions with outstanding amounts. You may select the "All" option to view all the transactions, including those linked (matched) transactions.*

4. group - Click on the group button to group the transactions on the list by "*Month, From today, By date*" and "*By year*".

> *You may also drag columns to the "Use your mouse to pull a column here to group on that column" row.*

5. limitrows - Limit rows - 200 rows is the default number of rows or transactions to be listed. The number of rows may be specified (decreased or increased).

6. Export - This button will create an Export.txt (Text files), which you may change the name and folder and save it. A Comma separated (CSV) file format is also available. This will export the list, as selected and/or filtered and displayed in the Transactions tab, as a comma separated text file as a "*Export.txt*" file. The Exported file will automatically be opened in your in your system's app (program) associated with the CSV (Comma Separated Values) file types.

Open item link - Transactions tab - Columns

The columns is as follows:

1. Account - Account code.

2. Description - Account name or account description.

3. Reference - The reference as entered in the "*Reference*" column for each transaction in "*Batch entry*" screens. In the case of Documents, the document number will be listed.

4. Batch entry - The description as entered in the "*Description*" column for each transaction in *"Batch entry*" screens. In the case of Documents, the document type and reference as entered in the "*Your*

reference" field of the document header section of the "*Document entry*" screen will be listed.

5. Transaction total - The total of the actual transactions in posted batches and documents.
6. Due - The due amount lists the total of outstanding for transactions, which is not matched linked. If the totals in the "*Transaction total*" and "*Due*" columns matches; or is displayed in the default system font, it means that all transactions are linked (matched).
7. Due date - The Due date is the number of days added to the actual date of the transaction. The number of days is on the Accounting information tab of debtor (customer / client) accounts and on the Accounting information tab of creditor (supplier / vendor) accounts.
8. Date - The actual date of the transaction in documents and batches.
9. Account type - Ledger (General ledger accounts, Bank accounts and Tax accounts), Debtors or Creditors.

Account type:

- *1 - Debtor accounts (Open item account field selected (ticked) on the Accounting information tab in Debtors (Default ribbon).*
- *2 - Creditor accounts (Open item account field selected (ticked) on the Accounting information tab in Creditors (Default ribbon).*
- *0 - General ledger (Open item account field set to Yes in Setup → Accounts).*
- *3 - Bank accounts (Open item account field set to Yes in the Setup → Accounts).*
- *4 - Tax accounts (Open item account field set to Yes in the Setup → Accounts).*

Created with the Standard Edition of HelpNDoc: Revolutionize your documentation process with HelpNDoc's online capabilities

Adjust payment date

The Payment date (due date) is automatically calculated by adding the number of days (entered in the "*Due date*" field on the Accounting information tab of Debtor/ Creditor accounts) to the date of the document (i.e. invoices, credit notes, purchase and supplier return documents) and the transaction dates entered in batches.

To adjust payment date:

1. On the Default ribbon, select Open item link. The Totals tab of the "*Open item link*" screen will be displayed.

2. Click on the Transactions tab.

3. Select an account and right-click to select the Adjust payment date option from the context menu. The "*Adjust payment date*" will display the current payment dates in the From (disabled) and To fields. Select or enter the new payment date in the To field.



4. Click on the OK button. The new payment date will be displayed in the "*Due date*" column.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Receive payment

The Receive payment feature, will automatically generate the transactions to the receipts batch for a selected transaction and print a combined receipt / payment advise (if selected). The transaction will automatically be posted updated to the ledger.

The "Receive payment" feature may also be launched on the context menu of selected transactions on the "Open item link" screen of a selected debtor (customer / client) account or on the "Open item link" screen of a selected creditor (supplier / vendor) account.

It will generate the transactions as follows:

Create receipts - Debtor (customer / client) accounts

- Invoices - Positive amount - Debit : Bank account and Credit : Debtor (customer / client) account.

- Credit notes - Negative amount - Debit : Debtor (customer / client) account and Credit : Bank account.

Create receipts - Creditor (supplier / vendor) accounts

- Purchases - Negative amount - Debit : Creditor (supplier / vendor) account and Credit : Bank account.
- Supplier returns - Positive amount - Debit : Bank account and Credit : Creditor (supplier / vendor) account.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Open item processing - Selected accounts

The "*Open item link*" for a specific ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account may be opened with a double-click from the Totals tab or Transactions tab on "*Open item link*".

Accounts which contains unlinked (unmatched) transactions, will be listed in an orange font or row colour on the Totals tab (if the "Show colours" option is selected).

Icon options

The icons on the "*Open item link*" screen for a selected account:



Contactperson, Address 1, Address 2, Phone 1 and Phone 2 is only displayed for a selected debtor (customer / client) account or a selected creditor (supplier / vendor) account. This is not applicable to a selected ledger account,

Clear links

This option will clear links according to the options you select.

If you click on the Clear links icon, a confirmation message is displayed:

> "Warning, if you click yes you will lose all your current links for this account!"

If you click on the Yes button of the confirmation message, the "*Clear links options*" screen is displayed:



Generate BBF

This option will clear all the open item links, and generate the ageing as balance brought forward account for a selected ledger, debtor or creditor account, according to the options you select.

If you click on the Generate BB/F icon, a confirmation message is displayed:

> "Warning, if you click yes you will lose all your current links for this account!"

If you click on the Yes button of the confirmation message, the "*Generate Balance BF options*" screen is displayed:



Unlink

This option allows you to unlink a selected linked debit and credit transactions.

The Unlink icon will change to Unlinked items and the Process icon will change to Delete icon. This will list all transactions as linked. If any transaction is not fully linked, it will list the outstanding amount for the transaction.



You may select a debit transaction(s) to unlink to a credit transaction(s) (tick the "*Link*" column) and click on the Delete icon to remove the link of selected transactions.

Process

Any linked transaction(s) will be removed from the debit or credit sections of the "*Open item link*" screen.

Select a debit transaction(s) to link to a credit transaction(s) (tick the "*Link*" column) and click on the Process icon. The "*Enter amount to link*" screen will display, by the default, the amount of the selected transaction to enter.



You need to confirm or over-type the amount, if necessary and click OK.

If the amounts of the selected transactions is the same, the debit and credit transactions will be removed from the "*Open item link*" screen.

If the amounts of the selected transactions differs (is not the same), the debit or credit transaction will be removed from the "*Open item link*" screen and the amount of a transaction which is not fully linked, will be adjusted in the "*Outstanding*" column.

Statement

Click to view the selected account in a statement layout with the ageing labels (e.g. Current, 30 days, 60 days, etc.). You may select the dates from which and until which date to include items.

Close

Close the "*Open item link*" screen for the selected account and return to Totals tab or Transactions tab of the "*Open item link*" main screen.

Export

The Export icon will create an Export.txt (Text files), which you may change the name and folder and save it. A Comma separated (CSV) file format is also available.

This will export the list, as selected and/or filtered and displayed in the "*Open item link*" screen for a selected account, as a comma separated text file as a "*Export.txt*" file. The Exported file will automatically be opened in your in your system's app (program) associated with the CSV (Comma Separated Values) file types.

Context menu processing options

In the "Debit" (top half) or "Credit" (bottom half) section of the selected account, right-click on a selected transaction on the list, to launch the context menu for the following processing options:



When the Statement option is selected for a selected account, only the "Unlink" option will be available for a selected transaction.

Filter options

You may apply the following options to filter transactions:



You may double-click on a selected account on the Totals tab or Transactions tab to process open item links.

Document entry context menu - Right-click on a selected document. On the context menu, select the Others → Open item link option.

The Invoice, Credit note or Quote document type will list the "Open item link" screen associated with the debtor (customer / client) account.

The Purchase, Supplier return or Orders document type will list the "Open item link" screen associated with the creditor (supplier / vendor) account.

Batch entry context menu - Right-click on a selected transaction. On the context menu, select the "Select from account open item list" option. The "Open item selection" screen will list the unlinked transactions as well as transactions with outstanding amounts for the selected debtor (customer / client) or creditor (supplier / vendor) account.

Transactions tab of a selected debtor (customer / client) account - This list the posted transactions similar to the "Open item link" screen.

- *All not selected - This is the default option. Only those with outstanding amounts will be listed.*
- *All option selected - All transactions will be listed. Those transactions, which are fully linked or settled,*

will display an 0.00 amount in the "Outstanding" column.

Transactions tab of a selected creditor (supplier / vendor) account - This list the posted transactions similar to the "Open item link" screen.

- *All not selected - This is the default option. Only those with outstanding amounts will be listed.*
- *All option selected - All transactions will be listed. Those transactions, which are fully linked or settled, will display an 0.00 amount in the "Outstanding" column.*

Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Open item processing - Ledger accounts

How does Open item processing help to manage general ledger accounts?

Open item processing can also be applied to general ledger accounts, particularly in organizations that require detailed tracking and reconciliation of individual transactions within their financial records. Here's how open item processing helps manage general ledger accounts:

1. Detailed Transaction Tracking: Open item processing allows for the detailed recording of individual financial transactions within various general ledger accounts. This means that every transaction, whether it's an expense, revenue, asset acquisition, liability, or equity movement, is tracked and recorded with specific details.
2. Accurate Account Balances: By meticulously tracking each transaction, open item processing ensures that the account balances for general ledger accounts are accurate and up-to-date. This accuracy is crucial for financial reporting, decision-making, and compliance with accounting standards.
3. Transaction Reconciliation: Regular reconciliation processes are employed to match recorded transactions against account balances. This reconciliation helps identify and rectify discrepancies or errors in the general ledger, ensuring the financial data's integrity.
4. Audit Trail: Open item processing maintains a comprehensive audit trail, which can be invaluable for internal and external audits. This trail provides a transparent record of all financial transactions, making it easier to verify and ensure the accuracy of financial records.
5. Reporting and Analysis: The detailed transaction data recorded through open item processing allows for the generation of various financial reports and analyses. These reports can provide insights into

the organization's financial performance, including profit and loss, balance sheets, and cash flow statements.

6. Compliance and Accountability: Open item processing helps organizations ensure compliance with financial regulations and accounting standards. It also promotes accountability and transparency in financial management practices.
7. Historical Reference: Over time, open item processing creates a historical record of all transactions. This historical reference is valuable for trend analysis, budgeting, forecasting, and other financial planning activities.
8. Efficient Error Correction: If errors are identified in the general ledger, open item processing makes it easier to pinpoint the exact transaction or entry that needs correction, streamlining the error resolution process.

In summary, open item processing in general ledger accounts provides a structured and detailed method for recording, reconciling, and maintaining financial transactions. It supports accurate financial reporting, ensures compliance, and facilitates a more efficient and transparent financial management process for organizations of varying sizes and complexities.

Can open item processing be used in other ledger accounts in the chart of accounts, for example suspense or ledger accounts?

Open item processing can potentially be used in any ledger account where there are multiple transactions or outstanding balances to be tracked. However, whether or not it is appropriate to use open item processing in a particular ledger account will depend on the specific nature of the account and the transactions involved.

For example, a suspense account is typically used to temporarily hold transactions that cannot be immediately classified to a specific account. In this case, open item processing may not be appropriate, as the purpose of the account is to temporarily hold transactions that will eventually be classified elsewhere.

Similarly, a general ledger account may not be well-suited to open item processing, as it is typically used to record a summary of all transactions for a particular account or category. In this case, it may be more appropriate to use a subsidiary ledger account, such as an accounts receivable or accounts payable ledger, to track individual transactions using open item processing.

That being said, there may be situations where open item processing could be used in conjunction with other ledger accounts in the chart of accounts. For example, if a particular general ledger account has multiple transactions that need to be tracked separately, it may be possible to use open item processing to track those transactions within the account.

Ultimately, the decision of whether or not to use open item processing in a particular ledger account will depend on a variety of factors, including the nature of the account, the specific transactions involved, and the desired level of detail and accuracy in tracking those transactions.

Open item link - Ledger accounts

Open item link feature may be activated for selected accounts in the Chart of accounts. This allows you to match credit transactions to specific debit transactions and vice versa. The Open item feature is used to manage and reconcile transactions in ledger accounts.

The "Open item account" setting is not available for the following accounts:

- *Retained earnings / Retained income - This account reflect the Net profit/Net loss.*
- *Debtors control - This account reflect the total of the individual debtor (customer / client) accounts in the general ledger. You may set selected debtor (customer / client) accounts as an "Open item account" on the Accounting information tab.*
- *Creditors control - This account reflect the total of the individual creditor (supplier / vendor) accounts in the general ledger. You may set selected creditor (supplier / vendor) accounts as an "Open item account" on the Accounting information tab.*

The "*Open item link*" for a specific ledger account may be opened with a double-click from the Totals tab or the Transactions tab on Open item link.

Some examples of such ledger accounts may be;

- Advance accounts - You may wish to keep track and manage advances paid to an employee or salesperson for subsistence and travel. After the employee or salesperson returns from his trip, he return the expenses source documents and refund any unused monies. When processing these source documents in batches, etc., these transactions may be linked (matched) to the original advance.
- Suspense / Clearing accounts - When an transactions needs to be managed, matched or reconciled, etc.

Age analysis reports for "Open item" ledger accounts is available on the Reports ribbon, or the Due tab of Open item link option on the Default ribbon.

Bank accounts should not be set to open item accounts. The allocation of transactions in the Receipts and Payments (batches) journals may be linked matched to specific transactions in the "Open item" ledger accounts, debtor (customer / client) accounts or creditor (supplier / vendor) accounts.

Bank account transactions is reconciled to Bank statements in the Cash/Bank entry option on the Default ribbon.

When processing transactions in batches and documents, the Open item link for a ledger account, may be launched to link and allocate or match transactions specific transactions for open item ledger accounts. Some of these options, is as follows:

1. Batch entry - Select transactions on the "*Open item selection*" screen when processing credit transactions for a specific ledger accounts and match them to debit transactions and visa versa.

   By default, the "Open item selection" feature is enabled in batches. The last column, i.e. "Open item", will be available in "Batch entry" screens. The "Open item selection" feature may be deactivated or activated in "Batch entry" screens.

2. Batch entry - Once a ledger account is selected for a transaction on the "*Batch entry*" screen, you may right-click and choose the Select from account open item list option on the context menu. The "*Open item selection*" screen will list all the transactions with outstanding balances. You may select a specific outstanding transaction to link the transaction to.

Open item link - Unlinked Ledger transactions

A simple example of the "*Sales*" account, where no (or not all) credit transactions (e.g. Credit notes) were linked to specific debit transactions (e.g. Invoices), is as follows:



In this example, the debit section (top half) lists all the Credit notes not matched to Invoices.

If an Invoice or Credit note includes more than one stock item, e.g. Drill press and Compressor (as in this example), you may link (match) the item on the Credit note to a specific item on the Invoice.

Open item link - Linked Ledger transactions

An example of the "Sales" account where all credit transactions (e.g. Credit notes) were linked to specific debit transactions (e.g. Invoices), is as follows:



In this example, the debit section (top half) does not list any transactions. All Credit notes is linked to Invoices.

Open item link - Ledger context menu

Right-click on a selected transaction on the list, to launch the context menu for the following processing options:



Open item link - Ledger - Filter options

You may apply the following options to filter transactions:

Open item link - Ledger - Statement

The Statement option list all the transactions from a selected date up to the current date (or selected date. If the transactions on Credit notes and Invoices is matched for the full amount, a 0.00 (zero amount) will be displayed in the in the "*Outstanding column*".

If transactions is partially matched on an Invoice, the Outstanding amount will differ from the Invoice amount.



Context menu

Right-click on a selected transaction on the list to "Unlink" selected transactions from the context menu.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Open item - Debtors

How does Open item processing help to manage debtor accounts in the debtors ledger?

Open item processing plays a crucial role in managing debtor accounts within the debtors ledger (accounts receivable) by providing a systematic and detailed method to track, reconcile, and manage

outstanding invoices and payments from customers. Here's how open item processing helps manage debtor accounts:

1. Detailed Transaction Tracking: Open item processing allows for the detailed recording of individual transactions in debtor accounts. This means that each invoice and payment is tracked with specific information, such as the invoice date, due date, amount, and payment date.
2. Accurate Account Balances: By recording every transaction individually, open item processing ensures that debtor account balances are accurate and up-to-date. This accuracy is crucial for understanding the financial position of the company.
3. Transaction Reconciliation: Regular reconciliation processes are employed to match recorded transactions against debtor account balances. This reconciliation helps identify any discrepancies or errors in the debtor ledger and ensures the integrity of the financial data.
4. Ageing Analysis: Open item processing facilitates the generation of aging reports, which categorize outstanding invoices by their due dates. This helps the company prioritize collections efforts and determine which invoices are overdue and require attention.
5. Clearing Outstanding Items: When a payment is received and matched with specific invoices, those invoices are considered "cleared" or "closed." This reduces the outstanding balance of the debtor account and allows for accurate tracking of which invoices are paid and which are still open.
6. Customer Statements: The system can generate detailed customer account statements that provide customers with a transparent view of their outstanding balances and transaction history. These statements can include a breakdown of open items.
7. Improved Collections Management: Open item processing helps organizations efficiently manage their collections process by providing a clear view of outstanding invoices and prioritizing collections activities. This can help improve cash flow and reduce bad debt.
8. Historical Reference: Over time, open item processing creates a historical record of all debtor transactions. This historical reference is valuable for understanding customer payment patterns, making financial forecasts, and resolving any disputes or discrepancies.
9. Transparency and Customer Relations: Customers appreciate transparency in their accounts. Open item processing ensures that customers have a clear view of their financial obligations and payment history, which can enhance customer relations.

In summary, open item processing in debtor accounts within the debtors ledger provides an organized and transparent method for managing accounts receivable. It helps companies maintain accurate records, improve cash flow, streamline collections efforts, and enhance customer relations by ensuring clarity and accuracy in the management of outstanding invoices and payments.

Open item debtor (customer / client) accounts in osFinancials

In the case of debtor (customer / client) accounts, debit transactions are processed in the sales batch or invoices (document entry).

Once these debit transactions is updated (posted) to the ledger, and credit transactions are processed in the receipts batch, or credit notes in document entry) these credit transactions may be linked to the debit transactions.

Once these debit transactions is linked to a credit transaction, only the outstanding transactions (unlinked) outstanding transactions should be listed.

If all the transactions are not linked, it will be indicated on the Totals tab in a red or orange colour. This will help you to identify those accounts which may need open item processing.

1. *Show colours - If this field is selected, this will show red or orange colours for those accounts and transactions, which have unlinked transactions.*
2. *Find invalid - Select (tick) and click on the Filter button to list those accounts and transactions, which have unlinked transactions.*

It is important to check that all batches and documents are updated to the ledger and that all transactions are linked, before sending out debtor statements. The Unposted batches tab of Open item link will only display the linked transactions which is already linked but not yet posted (updated) to the ledger.

There may also be unposted documents and batches, which need to be linked, once these transactions and documents are posted (updated) to the ledger. To view these, select in Input → Checking for unposted items on the Default ribbon).

Open item / Ageing reports for debtor (customer / client) accounts

In addition to the Age analysis icon on the Reports ribbon; or the Due tab of Open item link icon on the Default ribbon; the following reports is available to manage open item debtor (customer / client) accounts:

Reports menu

Transaction reports -

- Transaction list - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. It will list only those transactions with outstanding amounts. Any debit amounts, which are not linked to credit transactions, should be processed in Open

item link (Default ribbon).

- Transaction list - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.

Debtor statements -

- Debtor statements - The statement will print all transactions. It does not use the "*Open item*" feature.
- Debtor statements - Outstanding The statement will print only the transactions with outstanding amounts.

Age analysis reports -

- Age analysis - Balances detail - Displays the reference, date, amount and description for each transaction. The Total outstanding as at the Date of ageing is split to the number of days specified in up to 3 periods.
- Age analysis - Balances detail history (open item) - This is similar to the "*Balances detail*" report, but it displays the outstanding amount and TransactionID.
- Age analysis - Balances - This is a similar report as the "*Balances detail*" report. It will only list the balances for each ageing period.

Accessing the Open item link screen for a debtor (customer / client) account

To launch the Open item link screen for a debtor account:

Documents list screen - context menu - Others → Open item link option.

On Default ribbon, select Documents (Documents list screen), select the Document type, e.g. Invoices, Credit notes or Quotes.

Right-click on a selected document. On the context menu, select the Others → Open item link option.

This will launch the "Open item link" form for the debtor (customer / client) account;; associated with the selected document.

1. Go to Open item link (Default ribbon).
2. On the list of accounts in the Totals or the Transactions tab, select the debtor (customer / client) account and double-click.
3. The "*Open item link*" screen for a selected debtor (customer / client) account is launched.



If the transaction for Credit note CR000003 is not linked to Invoice IN000020, both Credit note CR000003 and Invoice IN000020, "Transaction list - Open item" report as well as the "Debtor statement - Outstanding".



You may need to process the links on the Open item link (Default ribbon).

4. All the outstanding transactions which are not linked (matched), while processing transactions in batches and documents, will be listed. Once all transactions for an open item debtor account, is correctly linked and processed, there should be no transactions in the "*Credit*" section of the screen:



Transactions tab - This list the posted transactions similar to the "Open item link" screen.

- *All not selected - This is the default option. Only those with outstanding amounts will be listed.*
- *All option selected - All transactions will be listed. Those transactions, which are fully linked or settled, will display an 0.00 amount in the "Outstanding" column.*

Open item - processing options and filter options

See - Open item processing - Selected accounts.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Open item - Debtor - Statements

The Open item link - Statement - This is a statement view of the transactions with outstanding amounts included between selected dates for a selected debtor (customer / client) account.



You may click on the ⊞ icon to expand show the links to for a selected transactions. To hide the links, click on the ⊟ icon.

Debtor statements -

- *Debtor statements - The statement will print all transactions. It does not use the "Open item" feature.*
- *Debtor statements - Outstanding The statement will print only the transactions with outstanding amounts.*

The credit transactions which are linked to specific debit transactions of the same value, will not be displayed. If a transaction c

specific transaction, only the outstanding amount (difference) will be listed.

An example of transactions in a receipts batch link to outstanding transactions on the "Open item selection" screen.



For example, an payment of 2,000.00 is received from the debtor (customer / client) on 2021/03/16. The payment is linked as fo

- *INV001 - 2021/03/07 - 1,150.00 is fully settled (linked to the payment of 2000.00) -*
- *The remaining balance of 850.00 is linked to INV003 as a partial settlement of INV003. An outstanding amount of 300.00 v amount is calculated as 1,150.00 minus the partial settlement of 850.00 = 300.00 as the outstanding amount.*

As per this example -

- *Invoice INV001 will not be printed on some reports and in other reports it will print 0.00 as the outstanding amount.*
- *INV003 will print on some reports as 300.00 as the outstanding amount.*

All the credit transactions which are linked to specific debit transactions of the same value, will be displayed. If a transaction of a different amount is linked to a specific transaction, the full amount of the transaction will be listed.

Debtors - Transaction list reports

View the "*Debtors - Transaction list*" report.



Transaction list

Debtors - Transaction list

From account: D1ABGRE To: D1ROGSM

Period: 2021/03/01 - 2022/02/28
Sequence: Description
New page per account: Yes

Cost centre 1:
Cost centre 2:

D1ABGRE Mr. AB Green — **Open item: Yes**

Date	Period	Batch id	Alias	Reference	Description	Debit	Credit	Cum
2021/03/07	March	10028	Sales 2103	INV001	Paint - Exterior	1,150.00		1,150.00
2021/03/10	March	10028	Sales 2103	INV003	Paint - Exterior	1,150.00		2,300.00
2021/03/13	March	10039	IN000001	IN000001	Invoice /AB-IN110	1,150.00		3,450.00
2021/03/15	March	10041	IN000003	IN000003	Invoice /FH-101	1,150.00		4,600.00
2021/03/16	March	10032	ABCReceipts 2103	D5001	Payment received - Thank you		2,000.00	2,600.00
2021/05/07	May	10056	IN000009	IN000009	Invoice /FH-101	1,150.00		3,750.00
2021/06/05	June	10059	IN000011	IN000011	Invoice /D-101	1,150.00		4,900.00
2021/06/30	June	10075	IN000019	IN000019	Invoice /D-101	5,750.00		10,650.00
2021/06/30	June	10077	IN000020	IN000020	Invoice /C-103	5,750.00		16,400.00
2021/06/30	June	10086	CR000001	CR000001	Credit note /D-101		5,750.00	10,650.00
2021/06/30	June	10090	CR000003	CR000003	Credit note /C-103		2,875.00	7,775.00
					Total: D1ABGRE Mr. AB Green	**7,775.00**		

View the "*Debtor transaction list - Open item*" report.



If the transaction for Credit note CR000003 is not linked to Invoice IN000020, both Credit note CR000003 and Invoice IN000020, "Transaction list - Open item" report as well as the "Debtor statement - Outstanding".



You may need to process the links on the Open item link (Default ribbon).

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Open item - Debtor - Receive payments

The Receive payment feature, will automatically generate the transactions to the receipts batch for a selected transaction and print a combined receipt / payment advise (if selected). The transaction will automatically be posted updated to the ledger.

The "Receive payment" feature may also be launched on the context menu of selected transactions on the "Open item link" screen of a selected debtor (customer / client) account or on the "Open item link" screen of a selected creditor (supplier / vendor) account.

It will generate the transactions as follows:

- Invoices - Positive amount - Debit : Bank account and Credit : Debtor (customer / client) account.
- Credit notes - Negative amount - Debit : Debtor (customer / client) account and Credit : Bank account.

Receive payments - Debtor (customer / client) accounts

To receive a payment:

1. Go to Open item link (Default ribbon). The Totals tab of the "*Open item link"* screen will be displayed.
2. Click on the Transactions tab and click on the Filter button.
3. Select the debtor (customer / client) account and select a transaction. Right-click to select the Receive payment option from the context menu. The "*Receive payment"* screen is displayed:



4. Enter and select the following options:

   a) Date - The Operating System (e.g. Windows) date will automatically be displayed in the date field. Enter the date or select the date, if necessary.

   b) Bank account - Please make sure that the correct bank account is selected.

   c) Receiving from - The account code is disabled. The name of the debtor (customer / client) is displayed. Check that the correct account is selected.

   d) Reference - The Document number or reference number in batches.

   e) Description - The default description is Payment follows by the Document number.

   f) Amount - The default outstanding amount of the selected transaction is displayed. You may overtype this, if necessary.

   g) Alias - The alias is automatically generated. It is prefixed by TR and five (5) numeric characters.

   h) Payment method - Select the payment method Cash, Cheque, Credit Card or Other.

   i) Print receipt - Select to print out or not to print the receipt / payment advise. If this field is left blank, no receipt payment advise will be printed, but the details of the receipt will generate a transaction in the receipts batch linked to the bank account. The transaction will automatically be posted (updated to the ledger).

5. Click on the OK button.



6. Click on the OK button of the parameters screen. The transaction for the receipt will automatically be inserted into the Receipts journal from which this option was initiated. An example of the printed "*Receipt / Payment*" (if the "*Print receipt*" option was selected), is as follows:


payments

Receipt / Payment

Issued by: **Handyman Hardware Store** 27 Olifants Road Emmarentia Johannesburg 2195	**Received from / Paid to:** D1ABGRE **Mr. AB Green**
Phone: (011) 310-1390 Fax: (011) 310-2000 E-mail: osfinancials1@gmail.com Website: osfinancials.org/en/	
Company reg. no. 336012345 Tax reg. no. 446010111	

Receipt number / Payment number: TR00002 **Date: 2021/05/17 19:55:47**

The sum of: **300.00**
(Three hundred)

Payment reference: INV003
Payment method: Cash
Description: Payment INV003
Receipts batch entry: ABC-Receipts

Received for

Original transaction amount: **1,150.00** **Date:** **2021/03/10**

Reference: INV003
Description: Paint - Exterior
Amount outstanding: 0.00

_____ Issued by (Signature)
System user: danva osFinancials user:

_____ Received from (Signature)
Printed : 2022/05/17 19:58:09

7. Click the Cancel button of the parameters screen.

The Receive payment feature, will automatically generate the transactions to the receipts batch for a selected transaction and payment advise (if selected). The transaction will automatically be posted (updated) to the ledger. The updated posted transac

Receipts batch.

The outstanding amount of a debtor (customer / client) account is usually a debit amount and the debtor (customer / client) acc

bank account will be debited.

To view the Receipt transaction:

1. *Select and open the Bank account receipt batch.*
2. *Click on Posted batches tab.*



3. *On the Batch entry tab, select the batch and double-click. The transaction is on the Details tab.*



4. *Click on the Print button to print the transactions in the Posted batch report.*



Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Open item - Debtors - Link / allocate transactions in batches

Allocate and link transactions in batches

By default, the "*Open item selection*" screen will be launched when allocating credit transactions (e.g. payments received or credit notes, etc.) to debit transactions (e.g. Invoices, Credit notes, and other debit transactions such as interest on overdue accounts, charge amounts, fixed amounts, etc.).

It will list all the transactions with outstanding amounts. You need to select the specific invoice or transaction for which, you are receiving the payment.

Should you have any Open item debtors, an "*Open item selection*" screen will appear, listing all debit transactions, as well as the outstanding balances of transactions for the debtor you have selected in the account field, if this debtor (customer / client) account is created as an Open item debtor.



You may select (tick) the "Not open item batch" field (F10:Setup - "Options for this batch" - Advanced tab) to de-activate the open item feature in batches.

After entering the receipts (deposits) in the Receipts journal, the transactions will be displayed as follows:



If a transaction for a debtor in the receipts journal is linked to an transaction on the "Open item selection" screen, the transaction will be displayed in a peach background colour.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Open item - Creditors

How does Open item processing help to manage creditor accounts in the creditors ledger?

Open item processing is instrumental in efficiently managing creditor accounts within the creditors ledger (accounts payable). It provides a structured and detailed approach to tracking and reconciling transactions with suppliers or creditors, helping organizations maintain accurate financial records and effective financial management. Here's how open item processing helps manage creditor accounts:

1. Detailed Transaction Tracking: Open item processing enables organizations to track and record individual transactions with suppliers. Each invoice and payment is recorded with specific information, such as the invoice date, due date, amount, and payment date.
2. Accurate Account Balances: By meticulously recording each transaction, open item processing ensures that creditor account balances are accurate and up-to-date. This accuracy is essential for managing the company's financial liabilities.
3. Transaction Reconciliation: Regular reconciliation processes are carried out to match recorded transactions against creditor account balances. This reconciliation helps identify discrepancies or errors in the creditor ledger, ensuring the financial data's integrity.
4. Ageing Analysis: Open item processing facilitates the generation of aging reports, which classify outstanding invoices by their due dates. These reports help the company monitor which invoices are overdue and prioritize payments to suppliers.
5. Clearing Outstanding Items: When a payment is made and matched with specific invoices, those invoices are considered "cleared" or "closed." This reduces the outstanding balance of the creditor account and allows for accurate tracking of paid and outstanding invoices.
6. Supplier Statements: The system can generate detailed supplier account statements, providing suppliers with a transparent view of their outstanding balances and transaction history. These statements may include a breakdown of open items.

7. Improved Cash Flow Management: Open item processing helps organizations effectively manage their cash flow by providing a clear view of outstanding invoices and payment priorities. This can aid in optimizing working capital and ensuring timely payments to suppliers.
8. Historical Reference: Over time, open item processing creates a historical record of all creditor transactions. This historical reference is valuable for understanding payment patterns, making financial forecasts, and resolving any disputes or discrepancies with suppliers.
9. Compliance and Transparency: Open item processing promotes compliance with financial regulations and accounting standards by maintaining transparent and accurate records of financial transactions.

In summary, open item processing in creditor accounts within the creditors ledger offers an organized and transparent method for managing accounts payable. It helps organizations maintain accurate records, effectively manage their cash flow, prioritize payments to suppliers, and ensure clarity and accuracy in the management of outstanding invoices and payments to creditors. This approach fosters healthy supplier relationships and financial management practices.

Open item creditor (supplier / vendor) accounts in osFinancials

In the case of creditor (supplier / vendor) accounts, credit transactions are processed in the purchase batch or purchase documents (document entry).

Once these credit transactions is updated (posted) to the ledger, and debit transactions are processed in the payments batch, or supplier returns in document entry) these debit transactions may be linked to the credit transactions.

Once these credit transactions is linked to a debit transaction, only the outstanding transactions (unlinked) outstanding transactions should be listed.

If all the transactions are not linked, it will be indicated on the Totals tab in a red or orange colour. This will help you to identify those accounts which may need open item processing.

1. *Show colours - If this field is selected, this will show red or orange colours for those accounts and transactions, which have unlinked transactions.*
2. *Find invalid - Select (tick) and click on the Filter button to list those accounts and transactions, which have unlinked transactions.*

It is important to check that all batches and documents are updated to the ledger and that all transactions are linked, before sending out creditor remittance advises. The Unposted batches tab of Open item link will only display the linked transactions which is already linked but not yet posted (updated) to the ledger.

There may also be unposted documents and batches, which need to be linked, once these transactions and

documents are posted (updated) to the ledger. To view these, select in Input → Checking for unposted items on the Default ribbon).

Open item / Ageing reports for creditor (supplier / vendor) accounts

In addition to the Age analysis icon on the Reports ribbon; or the Due tab of Open item link icon on the Default ribbon; the following reports is available to manage open item creditor (supplier / vendor) accounts:

Reports menu

Transaction reports -

- Transaction list - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. It will list only those transactions with outstanding amounts. Any debit amounts, which are not linked to credit transactions, should be processed in Open item link (Default ribbon).
- Transaction list - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.

Remittance advices -

- Creditor remittance advises - The remittance advice will print all transactions. It does not use the "*Open item*" feature.
- Creditor remittance advises - Outstanding - The remittance advice will print only the transactions with outstanding amounts.

Age analysis reports -

- Age analysis - Balances detail - Displays the reference, date, amount and description for each transaction. The Total outstanding as at the Date of ageing is split to the number of days specified in up to 3 periods.
- Age analysis - Balances detail history (open item) - This is similar to the "*Balances detail*" report, but it displays the outstanding amount and TransactionID.
- Age analysis - Balances - This is a similar report as the "*Balances detail*" report. It will only list the balances for each ageing period.

Accessing the Open item link screen for a creditor (supplier / vendor) account

Documents list screen - context menu - Others → Open item link option.

On Default ribbon, select Documents (Documents list screen), select the Document type, e.g. Purchase, Supplier return or Orders.

Right-click on a selected document. On the context menu, select the Others → Open item link option.

This will launch the "Open item link" form for the creditor (supplier / vendor) account; associated with the selected document.

To launch the Open item link screen for a creditor (supplier / vendor) account:

1. Go to Open item link (Default ribbon).
2. On the list of accounts in the Totals or the Transactions tab, select the creditor (supplier / vendor) account and double-click.
3. The "*Open item link*" screen for a selected creditor (supplier / vendor) account is launched.



4. All the outstanding transactions, which are not linked (matched), while processing transactions in batches and documents, will be listed. Once all transactions for an open item creditor (supplier / vendor) account, is correctly linked and processed, there should be no transactions in the "*Debit*" section of the screen:



Transactions tab - This list the posted transactions similar to the "Open item link" screen.

- *All not selected - This is the default option. Only those with outstanding amounts will be listed.*
- *All option selected - All transactions will be listed. Those transactions, which are fully linked or settled, will display an 0.00 amount in the "Outstanding" column.*

Open item - processing options and filter options

See - Open item processing - Selected accounts.

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Open item - Creditor - Remittance advises

The Open item link - Statement option displays the transactions of the selected creditor (supplier / vendor) account.



You may click on the ⊞ icon to expand show the links to for a selected transactions. To hide the links, click on the ⊟ icon.

Remittance advices -

- *Creditor remittance advises - The remittance advice will print all transactions. It does not use the "Open item" feature.*
- *Creditor remittance advises - Outstanding - The remittance advice will print only the transactions with outstanding amounts.*

The debit transactions which are linked to specific credit transactions of the same value, will not be displayed. If a transaction c
outstanding amount (difference) will be listed.

An example of transactions in a payments batch link to outstanding transactions on the "Open item selection" screen.



For example, an payment of 750.00 is made to the creditor (supplier / vendor) on 2021/03/30. The payment is linked as follows:

- *PU002 - 2021/03/06 - 1,725.00 is partially settled (linked to the payment of 750.00) - The outstanding amount is calculate outstanding amount.*

As per this example -

- *The payment for "Payment reference - 108" will not be printed on some reports and in other reports it will print 0.00 as the*
- *PU002 will print on some reports as 975.00 as the outstanding amount.*

The debit transactions which are linked to specific credit transactions of the same value, will not be displayed. If a transaction is linked to a specific transaction, only the outstanding amount (difference) will be listed.

For example:

- *Payment - 108 - 2021/03/30 - 750.00 - Debit transaction in the Payments journal is linked to the supplier invoice PU002 - 2*

The outstanding amount for this transaction is 850.00 still due to the creditor (supplier / vendor). (1725.00 minus 750.00). Only

- *Supplier return SR000004 - 2021/06/26 - 1725.00 is linked to Purchase PU000007 - 2021/06/25 - 1725.00.*

Supplier return SR000004 and Purchase PU000007 will not be listed on the "Transaction list - Open item" report as well as the "C advise - Outstanding".



If the transaction for Supplier return SR000004 is not linked to Purchase PU000007, both Supplier return SR000004 and Purchas listed on the "Transaction list - Open item" report as well as the "Creditor remittance advise - Outstanding".



You may need to process the links on the Open item link (Default ribbon).

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with a Help Authoring Tool

Open item - Creditor - Receive payments

The Receive payment feature, will automatically generate the transactions to the receipts batch for a selected transaction and print a combined receipt / payment advise (if selected). The transaction will automatically be posted updated to the ledger.

The "Receive payment" feature may also be launched on the context menu of selected transactions on the "Open item link" screen of a selected debtor (customer / client) account or on the "Open item link" screen of a selected creditor (supplier / vendor) account.

It will generate the transactions as follows:

- Purchases - Negative amount - Debit : Creditor (supplier / vendor) account and Credit : Bank account.
- Supplier returns - Positive amount - Debit : Bank account and Credit : Creditor (supplier / vendor) account.

Receive payments - Creditor (supplier / vendor) accounts

To make a payment:

1. Go to Open item link (Default ribbon). The Totals tab of the "*Open item link*" screen will be displayed.

2. Click on the Transactions tab and click on the Filter button.

3. Select the creditor (supplier / vendor) account and select a transaction. Right-click to select the Receive payment option from the context menu. The "*Receive payment*" screen is displayed:



4. Enter and select the following options:

    a) Date - The Operating System (e.g. Windows) date will automatically be displayed in the date field. Enter the date or select the date, if necessary.

    b) Bank account - Please make sure that the correct bank account is selected.

    c) Receiving from - The account code is disabled. The name of the creditor (supplier / vendor) is displayed. Check that the correct account is selected.

    d) Reference - The Document number or reference number in batches.

    e) Description - The default description is Payment follows by the Document number.

    f) Amount - The default outstanding amount of the selected transaction is displayed. You may

overtype this, if necessary.

g) Alias - The alias is automatically generated. It is prefixed by TR and five (5) numeric characters.

h) Payment method - Select the payment method Cash, Cheque, Credit Card or Other.

i) Print receipt - Select to print out or not to print the receipt / payment advise. If this field is left blank, no receipt payment advise will be printed, but the details of the receipt will generate a transaction in the receipts batch linked to the bank account. The transaction will automatically be posted (updated to the ledger).

5. Click on the OK button.



6. Click on the OK button of the parameters screen. The transaction for the receipt will automatically be inserted into the Receipts journal from which this option was initiated. An example of the printed "*Receipt / Payment*" (if the "*Print receipt*" option was selected), is as follows:



7. Click the Cancel button of the parameters screen.

The Receive payment feature, will automatically generate the transactions to the receipts batch for a selected transaction and selected). The transaction will automatically be posted (updated) to the ledger. The updated posted transaction will be availab

The outstanding amount of a creditor (supplier / vendor) account is usually a credit amount, and the creditor (supplier / vendo account will be credited.

To view the Receipt transaction:

1. *Select and open the Bank account receipt batch.*
2. *Click on Posted batches tab.*



3. *On the Batch entry tab, select the batch and double-click. The transaction is on the Details tab.*



4. *Click on the Print button to print the transactions in the Posted batch report.*



Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-Use Tool

Open item - Creditors - Link / allocate transactions in batches

Allocate and link transactions in batches

By default, the "*Open item selection*" screen will be launched when allocating debit transactions (e.g. payments made on account or supplier returns, etc.) to credit transactions (e.g. Purchases, Supplier returns, and other debit transactions such as, charge amounts, etc.).

It will list all the transactions with outstanding amounts. You need to select the specific purchase transaction or or other transaction for which, you are making the payment.

Should you have any Open item creditors, an "*Open item selection*" screen will appear, listing all credit transactions, as well as the outstanding balances of transactions for the creditor you have selected in the account field, if this creditor (supplier / vendor) account is created as an Open item creditor.



You may select (tick) the "Not open item batch" field (F10:Setup - "Options for this batch" - Advanced tab) to de-activate the open item feature in batches.

After entering the payments in the Payments journal, the transactions will be displayed as follows:



If a transaction for a creditor in the payments journal is linked to an transaction on the "Open item selection" screen, the transaction will be displayed in a peach background colour.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Open item link - Unposted batches tab

The Unposted batches tab will list all transactions linked to open item accounts (i.e. ledger, debtors and creditors) in batches, which have not yet been posted (updated) to the ledger. The transactions in unposted batches for open item accounts need to be linked to transactions in posted batches.



If any transactions in unposted batches are not linked to transactions in posted batches, these transactions will not be listed on the Unposted batches tab.

You may remove linked transactions (right-click on selected transaction(s) and select Remove on the context menu. A confirmation message is displayed:

"Continue action Unlink transaction?"

Click Yes to remove the link. This will clear the links in the "Batch entry" screen.

When processing transactions in batches and an open item account is selected, the "*Open item selection*" screen list all the outstanding transaction. For example, if a payment is received, you may select to link the receipt to outstanding amount(s) in batches as well as documents.



If a transaction in unposted batches is linked to outstanding amounts in the Open item selection screen the transaction line will be displayed in a peach background.

You may also select an account on the "Batch entry" screen (right-click on selected transaction) and select the "Select from account open item list" option. The "Open item selection" screen will list the unlinked transactions as well as transactions with outstanding amounts.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Open item link - Due tab

The Due tab will list all transactions for all open item accounts (i.e. ledger, debtors and creditors), which is set as open item accounts.

The transaction or outstanding transaction amounts are added in columns based on the number of days (0-29 days, 30-59 days, 60-89 days and +90 days).

You may to view and generate the report for a selected date options:

- Date of ageing - Select the date or due date option. The default is "*Date of ageing*" is the "*Current date*" (which is the date of your operating system). This report will include all outstanding transactions of only the open item accounts, for selected account types.
- Date of ageing - Select a specific date of the ageing to include in the report. This report will include all outstanding transactions of all accounts, including those non-open item accounts, for selected account types.

You may click on Age analysis icon on the Reports ribbon to access this Due tab.

Date of ageing - Current date

To generate and print ageing report for the current date:

1. Select Open item link (Default ribbon).
2. Click on Due tab.



Account type	Account	Name	Description	Reference	Date	Due date	Org amount	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+	Comments
C	2AONES	A-ONE Suppliers	Creditor opening balances -Dec 2020	JNL3	2020/12/31	2021/01/30		100.00-				100.00-	
D	1MDAVI	Mr. Mike Davies	Debtor opening balances - Dec 2020	JNL2	2020/12/31	2021/01/30		100.00				100.00	
C	2AONES	A-ONE Suppliers	Creditor opening balances -Jan 2021	JNL3	2021/01/31	2021/03/02		200.00-			200.00-		
D	1MDAVI	Mr. Mike Davies	Debtor opening balances - Jan 2021	JNL2	2021/01/31	2021/03/02		200.00			200.00		
C	2AONES	A-ONE Suppliers	Creditor opening balances -Feb 2021	JNL3	2021/02/28	2021/03/30		300.00-			300.00-		
D	1MDAVI	Mr. Mike Davies	Debtor opening balances - Feb 2021	JNL2	2021/02/28	2021/03/30		500.00			500.00		
C	2ABCOS	ABC-Office-Supplies	Install - Built-in cupboards	PU002	2021/03/06	2021/04/05		975.00-		975.00-			
D	1ABGRE	Mr. AB Green	Paint - Exterior	INV003	2021/03/10	2021/04/09		300.00		300.00			
D	1MDAVI	Mr. Mike Davies	Install - Built-in cupboard	INV004	2021/03/11	2021/04/10		1,725.00		1,725.00			
D	1ABGRE	Mr. AB Green	Invoice /AB-IN110	IN000001	2021/03/13	2021/04/12		1,150.00		1,150.00			
C	2ABCOS	ABC-Office-Supplies	Purchases /IN0014	PU000002	2021/03/15	2021/04/14		1,725.00-		1,725.00-			
D	1ABGRE	Mr. AB Green	Invoice /PH-101	IN000003	2021/03/15	2021/04/14		1,150.00		1,150.00			
D	1MDAVI	Mr. Mike Davies	Invoice /IB-102	IN000004	2021/03/16	2021/04/15		1,725.00		1,725.00			
D	1MDAVI	Mr. Mike Davies	Invoice /D-101	IN000005	2021/04/07	2021/05/07		1,150.00	1,150.00				
D	1MDAVI	Mr. Mike Davies	Invoice /C-103	IN000007	2021/04/10	2021/05/10		1,725.00	1,725.00				
D	1ABGRE	Mr. AB Green	Invoice /PH-101	IN000009	2021/05/07	2021/06/06		1,150.00	1,150.00				
D	1MDAVI	Mr. Mike Davies	Invoice /IN000010	IN000010	2021/05/08	2021/06/07		1,150.00	1,150.00				
D	1ABGRE	Mr. AB Green	Invoice /D-101	IN000011	2021/06/05	2021/07/05		1,150.00	1,150.00				
D	1MDAVI	Mr. Mike Davies	Invoice /C-103	IN000013	2021/06/10	2021/07/10		1,725.00	1,725.00				
D	1MDAVI	Mr. Mike Davies	Invoice /D-101	IN000015	2021/06/15	2021/07/15		1,150.00	1,150.00				
D	1MDAVI	Mr. Mike Davies	Invoice /C-103	IN000017	2021/06/20	2021/07/20		2,875.00	2,875.00				
D	1ABGRE	Mr. AB Green	Invoice /C-103	IN000020	2021/06/30	2021/07/30		2,875.00	2,875.00				
	22							18500.00	14950.00	3350.00	200.00	0.00	

3. Select the account type (i.e. ledger, debtors and creditors) to generate the Age analysis report for a specific account type.

4. Date of ageing - Select the date or due date option. The default is "*Date of ageing*" is the "*Current date*" (which is the date of your operating system).

5. Click on the Print button to print the "*opendays*" report.



D1ABGRE Mr. AB Green	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
INV003 Paint - Exterior	2021/03/10	2021/04/09	300.00	0.00	300.00	0.00	0.00
IN000001 Invoice /AB-IN110	2021/03/13	2021/04/12	1,150.00	0.00	1,150.00	0.00	0.00
IN000003 Invoice /FH-101	2021/03/15	2021/04/14	1,150.00	0.00	1,150.00	0.00	0.00
IN000009 Invoice /FH-101	2021/05/07	2021/06/06	1,150.00	1,150.00	0.00	0.00	0.00
IN000011 Invoice /D-101	2021/06/05	2021/07/05	1,150.00	1,150.00	0.00	0.00	0.00
IN000020 Invoice /C-103	2021/06/30	2021/07/30	2,875.00	2,875.00	0.00	0.00	0.00
	Total		7,775.00	5,175.00	2,600.00	0.00	0.00
D1MDAVI Mr. Mike Davies	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
JNL2 Debtor opening balances - Dec 2020	2020/12/31	2021/01/30	100.00	0.00	0.00	0.00	100.00
JNL2 Debtor opening balances - Jan 2021	2021/01/31	2021/03/02	200.00	0.00	0.00	200.00	0.00
JNL2 Debtor opening balances - Feb 2021	2021/02/28	2021/03/30	500.00	0.00	0.00	500.00	0.00
INV004 Install - Built-in cupboard	2021/03/11	2021/04/10	1,725.00	0.00	1,725.00	0.00	0.00
IN000004 Invoice /IB-102	2021/03/16	2021/04/15	1,725.00	0.00	1,725.00	0.00	0.00
IN000005 Invoice /D-101	2021/04/07	2021/05/07	1,150.00	1,150.00	0.00	0.00	0.00
IN000007 Invoice /C-103	2021/04/10	2021/05/10	1,725.00	1,725.00	0.00	0.00	0.00
IN000010 Invoice /IN000010	2021/05/08	2021/06/07	1,150.00	1,150.00	0.00	0.00	0.00
IN000013 Invoice /C-103	2021/06/10	2021/07/10	1,725.00	1,725.00	0.00	0.00	0.00
IN000015 Invoice /D-101	2021/06/15	2021/07/15	1,150.00	1,150.00	0.00	0.00	0.00
IN000017 Invoice /C-103	2021/06/20	2021/07/20	2,875.00	2,875.00	0.00	0.00	0.00
	Total		14,025.00	9,775.00	3,450.00	700.00	100.00
C2ABCOS ABC-Office-Supplies	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
PU002 Install - Built-in cupboards	2021/03/06	2021/04/05	-975.00	0.00	-975.00	0.00	0.00
PU000002 Purchases /IN0014	2021/03/15	2021/04/14	-1,725.00	0.00	-1,725.00	0.00	0.00
	Total		-2,700.00	0.00	-2,700.00	0.00	0.00
C2AONES A-ONE Suppliers	Date	Due date	Amount	Amount 0-29	Amount 30-59	Amount 60-89	Amount 90+
JNL3 Creditor opening balances - Dec 2020	2020/12/31	2021/01/30	-100.00	0.00	0.00	0.00	-100.00
JNL3 Creditor opening balances - Jan 2021	2021/01/31	2021/03/02	-200.00	0.00	0.00	-200.00	0.00
JNL3 Creditor opening balances - Feb 2021	2021/02/28	2021/03/30	-300.00	0.00	0.00	-300.00	0.00
	Total		-600.00	0.00	0.00	-500.00	-100.00
	Total		**18,500.00**	**14,950.00**	**3,350.00**	**200.00**	**0.00**

Only the transactions of accounts set as open item accounts will be included in this report.

Date of ageing - Selected date

To generate and print ageing report for a selected date:

1. Select Open item link (Default ribbon).

2. Click on Due tab.



3. Select the account type (i.e. ledger, debtors and creditors) to generate the Age analysis report for a specific account type.

4. Date of ageing - The default is "*Date of ageing*" is the "*Current date*" (which is the date of your operating system). Select a specific date of the ageing.

> *In this example, the date of ageing is set to 30 April 2021.*
>
> *"Correction transaction ageing COR" will automatically be generated to include the outstanding transactions of all accounts for selected account types.*
>
> *The "Correction transaction ageing COR" message, is only displayed for transactions of non-open item accounts.*

5. Click on the Print button to print the "*opendays*" report.

In this example, the date of ageing is set to 30 April 2021.


openitemdays
Age analysis - Due report
Date of report: 2021/04/30
Date of ageing: 2021/04/30
D1ABGRE Mr. AB Green
Date
Due date
Amount
Amount 0-29
Amount 30-59
Amount 60-89
Amount 90+
INV003 Paint - Exterior 2021/03/10 2021/04/09 300.00 0.00 300.00 0.00 0.00
IN000001 Invoice/AB-IN110 2021/03/13 2021/04/12 1,150.00 0.00 1,150.00 0.00 0.00
IN000003 Invoice/PH-101 2021/03/15 2021/04/14 1,150.00 0.00 1,150.00 0.00 0.00
Total 2,600.00 0.00 2,600.00 0.00 0.00
D1MACDS MAC Shop Decor Specialists
Correction transaction ageing COR 2021/04/30 2021/04/30 2,450.00 2,450.00 0.00 0.00 0.00
Total 2,450.00 2,450.00 0.00 0.00 0.00
D1MDAVI Mr. Mike Davies
JNL2 Debtor opening balances - Dec 2020 2020/12/31 2021/01/30 100.00 0.00 0.00 0.00 100.00
JNL2 Debtor opening balances - Jan 2021 2021/01/31 2021/03/02 200.00 0.00 0.00 200.00 0.00
JNL2 Debtor opening balances - Feb 2021 2021/02/28 2021/03/30 500.00 0.00 0.00 500.00 0.00
INV004 Install - Built-in cupboard 2021/03/11 2021/04/10 1,725.00 0.00 1,725.00 0.00 0.00
IN000004 Invoice/IB-102 2021/03/16 2021/04/15 1,725.00 0.00 1,725.00 0.00 0.00
IN000005 Invoice/D-101 2021/04/07 2021/05/07 1,150.00 1,150.00 0.00 0.00 0.00
IN000007 Invoice/C-103 2021/04/10 2021/05/10 1,725.00 1,725.00 0.00 0.00 0.00
Total 7,125.00 2,875.00 3,450.00 700.00 100.00
D1ROGSM Mr. Roger Smith
Correction transaction ageing COR 2021/04/30 2021/04/30 6,750.00 6,750.00 0.00 0.00 0.00
Total 6,750.00 6,750.00 0.00 0.00 0.00
C2ABCOS ABC-Office-Supplies
PU002 Install - Built-in cupboards 2021/03/06 2021/04/05 -975.00 0.00 -975.00 0.00 0.00
PU000002 Purchases /IN0014 2021/03/15 2021/04/14 -1,725.00 0.00 -1,725.00 0.00 0.00
Total -2,700.00 0.00 -2,700.00 0.00 0.00
C2ABCSC ABC-Service-Centre
Correction transaction ageing COR 2021/04/30 2021/04/30 -2,300.00 -2,300.00 0.00 0.00 0.00
Total -2,300.00 -2,300.00 0.00 0.00 0.00

Page 2 -



Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Open item link - Export to spreadsheets

The Open item link, matching your filter and search criteria, may be exported and opened in spreadsheets:

- The Totals tab will list the transaction total and total outstanding total for each open item account.
- The Transactions tab will list all transactions for each open item account. It will also list the outstanding amount (due amount) for each transaction.
- Selected accounts - The Export icon will export the transaction totals and outstanding amounts for a specific ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Open item link - Totals tab - Spreadsheet

The Totals tab will list the transaction total and total outstanding total for each open item account.

Export options

To export Open item - Totals to a spreadsheet:

1. Op die Default ribbon, select Open item link. The Totals tab (default) is displayed.



2. Select the account type ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account, which you need to include in the export file.

> *You may:*
>
> - *Use the search and filter and options to export only the criteria that matches your search and filter options.*
> - *Drag the columns in the sequence you wish to export the data.*

3. Click on the Filter button to list all accounts that have been set as open item accounts, and against which transactions have been posted in journals and/or documents for the selected account type(s).

4. Click the Export button. This will launch the "*Save As*" screen:



5. Select the folder in which you wish to save the file and enter a file name.

> *If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.*
>
> *If an existing exported file is opened, and you are trying to open a export file with the same name, a similar error message as the following will be displayed:*
>
> Cannot create file "D:\Export\Export.txt". The process cannot access the file because it is being used by another process.

6. Select the file type. Text files (*.txt) is the default; or select CSV files (*.csv) (Comma Separated Values).

> - *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
> - *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, Apache OpenOffice, LibreOffice, Ultra Office, etc.). You may need to set the "Separator Options" on the "Text Import" screen to "Tab".*

7. Click on the Save button. This will automatically open (launch) the exported file in the program associated with the selected file type.

Export file opened in Microsoft Excel

In this example, the exported "*Export.txt*" file is automatically opened in "*Microsoft Excel*":



	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
1	Created on	2021/07/20 21:58													
2	Ledger	TRUE													
3	Debtors	TRUE													
4	Creditors	TRUE													
5															
6	Account	Description	Account type	Transaction	Total outstanding		Contactperson	Address	Address 2	Phone 1	Phone 2				
7	G010000	Sales	0	-36000	-36000										
8	D1ABGRE	Mr. AB Green	1	7775	7775		Andrew	PO Box 1111	Lakeside	(011)314-9997	(011)314-9998				
9	D1MDAVI	Mr. Mike Davies	1	14025	14025		Mike	P O Box 333	Halfway House	(011) 315-1225	083 286-8763				
10	C2ABCOS	ABC-Office-Supplies	2	-2700	-2700		Walters	PO Box 8888	Lakeview	(011)312-9997	(011)312-9998				
11	C2AONES	A-ONE Suppliers	2	-600	-600		Andy	P O Box 31318	Marshalltown	(011) 838-9221	(011) 838-9222				
12															

Open item link - Totals tab - Spreadsheet columns

This will open your exported text file of the accounts in a spreadsheet. An example of the exported file opened in "*Microsoft Excel*" spreadsheet, is as follows:

The first 6 rows will display the following:

- Row 1 - Date and timestamp on which the export file is created.
- Row 2 - Ledger - TRUE - Included in the Export file, if account is set as "*Open item account*". If FALSE - Ledger accounts was not selected in the Filter options.
- Row 3 - Debtors - TRUE - Included in the Export file, if account is set as "Open item account" If FALSE - Debtors accounts was not selected in the Filter options.
- Row 4 - Creditors - TRUE - Included in the Export file, if account is set as "Open item account" If FALSE - Creditors accounts was not selected in the Filter options.
- Row 5 - Blank.
- Row 6 - Column headings

The exported data will be exported in 11 columns:

Column	*Column heading*	*Source / fields*	*Remarks*
A	*Account*	*Account code / Account no.*	*Ledger is prefixed by account type* *G = Ledger* *B = Bank* *T = Tax*
B	*Description*		*Name (Account description)*
C	*Account type*		*1 = Debtors* *2 = Creditors* *0 = Ledger* *3 = Bank* *4 = Tax*

D	*Transaction total*	
E	*Total outstanding*	
F		*Not used*
G	*Contactperson*	*Only the first name of the contactperson.*
H	*Address*	*Postal address 1*
I	*Address 2*	*Postal address 2*
J	*Phone 1*	*Telephone 1*
K	*Phone 2*	*Telephone 2*

Columns G to K - The contact details (Contact person, Address, Address2, Phone1 and Phone2) is only applicable to debtor (customer / supplier) accounts (Account type 1) and creditor (supplier / vendor) accounts (Account type 2)

Columns G to K - will be blank for the following account types:

G	General ledger (Account type 0)
B	Bank (Account type 3)
T	Tax (Account type 4)

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Open item link - Transactions tab - Spreadsheet

Open item link - Transactions tab - Export to spreadsheet

The Transactions tab will list all transactions for each open item account. It will also list the outstanding amount (due amount) for each transaction.

Export options

Select the account type ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account, which you need to include in the export file.

You may:

- *Select Open transactions only to include only the transactions with outstanding amounts or to include all transactions in the export file.*
- *Use the search and filter and options to export only the criteria that matches your search and filter options.*
- *Drag the columns in the sequence you wish to export the data.*

To export Open item - Transactions to a spreadsheet:

1. Op die Default ribbon, select Open item link. The Totals tab (default) is displayed.
2. Click on the Transactions tab.



Account	Description	Reference	Batch entry	Transaction tot	Due	Due date	Date	Account type
		CR000003	Credit note /C-103	2,875.00-	2,875.00-	2021/07/30		
1ABGRE	Mr. AB Green	CR000001	Credit note /D-101	5,750.00-	0.00	2021/07/29	2021/06/30	1
		IN000020	Invoice /C-103	5,750.00	5,750.00	2021/07/30		
		IN000019	Invoice /D-101	5,750.00	0.00			
		IN000011	Invoice /D-101	1,150.00	1,150.00	2021/07/05	2021/06/05	
		IN000009	Invoice /PH-101	1,150.00	1,150.00	2021/06/06	2021/05/07	
		D5001	Payment received - Thank you	2,000.00-	0.00	2021/04/15	2021/03/16	
		IN000003	Invoice /PH-101	1,150.00	1,150.00	2021/04/14	2021/03/15	
		IN000001	Invoice /AB-IN110	1,150.00	1,150.00	2021/04/12	2021/03/13	
		INV003	Paint - Exterior	1,150.00	300.00	2021/04/09	2021/03/10	
		INV001	Paint - Exterior	1,150.00	0.00	2021/04/06	2021/03/07	
1MDAVI	Mr. Mike Davies	IN000017	Invoice /C-103	2,875.00	2,875.00	2021/07/20	2021/06/20	
		IN000015	Invoice /D-101	1,150.00	1,150.00	2021/07/15	2021/06/15	
		IN000013	Invoice /C-103	1,725.00	1,725.00	2021/07/10	2021/06/10	
		IN000010	Invoice /IN000010	1,150.00	1,150.00	2021/06/07	2021/05/08	
		IN000007	Invoice /C-103	1,725.00	1,725.00	2021/05/10	2021/04/10	
		IN000005	Invoice /D-101	1,150.00	1,150.00	2021/05/07	2021/04/07	
		IN000004	Invoice /IB-102	1,725.00	1,725.00	2021/04/15	2021/03/16	
		INV004	Install - Built-in cupboard	1,725.00	1,725.00	2021/04/10	2021/03/11	
		JNL2	Debtor opening balances - Feb 2(	500.00	500.00	2021/03/30	2021/02/28	
		JNL2	Debtor opening balances - Jan 2(	200.00	200.00	2021/03/02	2021/01/31	
		JNL2	Debtor opening balances - Dec 2	100.00	100.00	2021/01/30	2020/12/31	
2ABCOS	ABC-Office-Supplies	SR000004	Supplier returns /4562-A	1,725.00	1,725.00	2021/07/26	2021/06/26	
		PU000007	Purchases /4562	1,725.00-	1,725.00-	2021/07/25	2021/06/25	
		108	Payment on account	750.00	0.00	2021/04/29	2021/03/30	
		PU000002	Purchases /IN0014	1,725.00-	1,725.00-	2021/04/14	2021/03/15	
		PU002	Install - Built-in cupboards	1,725.00-	975.00-	2021/04/05	2021/03/06	
2AONES	A-ONE Suppliers	PU000005	Purchases /4562	1,725.00-	1,725.00-	2021/07/26	2021/06/26	
		120	Payment on account	2,300.00	0.00	2021/07/25	2021/06/25	2
		SR000003	Supplier returns /4562	1,725.00	1,725.00	2021/07/19	2021/06/19	
		SR000002	Supplier returns /4562	1,725.00	0.00	2021/07/17	2021/06/17	
		PU000006	Purchases /3532	2,300.00-	0.00	2021/07/09	2021/06/09	
		PU000003	Purchases /4562	1,725.00-	0.00	2021/05/05	2021/04/05	
		JNL3	Creditor opening balances -Feb 2	300.00-	300.00-	2021/03/30	2021/02/28	
		JNL3	Creditor opening balances -Jan 2(	200.00-	200.00-	2021/03/02	2021/01/31	
36				18,500.00	18,500.00			

3. Select the account type ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account, which you need to include in the export file.

> *You may:*
>
> - *Select Open transactions only to include only the transactions with outstanding amounts or to include all transactions in the export file.*
> - *Use the search and filter and options to export only the criteria that matches your search and filter options.*
> - *Drag the columns in the sequence you wish to export the data.*

4. Click on the Filter button to list all accounts that have been set as open item accounts, and against which transactions have been posted in journals and/or documents for the selected account type(s).

5. Click the Export button. This will launch the "*Save As*" screen:



6. Select the folder in which you wish to save the file and enter a file name.

> *If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.*
>
> *If an existing exported file is opened, and you are trying to open a export file with the same name, a similar error message as the following will be displayed:*
>
> Cannot create file "D:\Export\Export.txt". The process cannot access the file because it is being used by another process.

7. Select the file type. Text files (*.txt) is the default; or select CSV files (*.csv) (Comma Separated Values).

> - *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
> - *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, Apache OpenOffice, LibreOffice, Ultra Office, etc.). You may need to set the "Separator Options" on the "Text Import" screen to "Tab".*

8. Click on the Save button. This will automatically open (launch) the exported file in the program

associated with the selected file type.

Export file opened in Microsoft Excel

In this example, the exported "*Export.txt*" file is automatically opened in "*Microsoft Excel*":



	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
1	Created on	2021/07/20 22:22															
2	Ledger	FALSE															
3	Debtors	TRUE															
4	Creditors	TRUE															
5																	
6	Account	Description	Reference	Batch entry	Transaction total	Due	Due date	Date	Account type		Contactpe	Address	Address 2	Phone 1	Phone 2		
7	D1ABGRE	Mr. AB Green	IN000020	Invoice /C-103	5750	2875	2021/07/30	2021/06/30	1	54	475	Andrew	PO Box 11	Lakeside	(011)314-	(011)314-9998	
8	D1MDAVI	Mr. Mike Davies	IN000017	Invoice /C-103	2875	2875	2021/07/20	2021/06/20	1	27	458	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
9	D1MDAVI	Mr. Mike Davies	IN000015	Invoice /D-101	1150	1150	2021/07/15	2021/06/15	1	27	447	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
10	D1MDAVI	Mr. Mike Davies	IN000013	Invoice /C-103	1725	1725	2021/07/10	2021/06/10	1	27	437	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
11	D1ABGRE	Mr. AB Green	IN000011	Invoice /D-101	1150	1150	2021/07/05	2021/06/05	1	54	427	Andrew	PO Box 11	Lakeside	(011)314-	(011)314-9998	
12	D1MDAVI	Mr. Mike Davies	IN000010	Invoice /IN000010	1150	1150	2021/06/07	2021/05/08	1	27	422	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
13	D1ABGRE	Mr. AB Green	IN000009	Invoice /PH-101	1150	1150	2021/06/06	2021/05/07	1	54	419	Andrew	PO Box 11	Lakeside	(011)314-	(011)314-9998	
14	D1MDAVI	Mr. Mike Davies	IN000007	Invoice /C-103	1725	1725	2021/05/10	2021/04/10	1	27	407	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
15	D1MDAVI	Mr. Mike Davies	IN000005	Invoice /D-101	1150	1150	2021/05/07	2021/04/07	1	27	397	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
16	D1MDAVI	Mr. Mike Davies	IN000004	Invoice /IB-102	1725	1725	2021/04/15	2021/03/16	1	27	388	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
17	C2ABCOS	ABC-Office-Supplies	PU000002	Purchases /IN0014	-1725	-1725	2021/04/14	2021/03/15	2	53	375	Walters	PO Box 88	Lakeview	(011)312-	(011)312-9998	
18	D1ABGRE	Mr. AB Green	IN000003	Invoice /PH-101	1150	1150	2021/04/14	2021/03/15	1	54	385	Andrew	PO Box 11	Lakeside	(011)314-	(011)314-9998	
19	D1ABGRE	Mr. AB Green	IN000001	Invoice /AB-IN110	1150	1150	2021/04/12	2021/03/13	1	54	379	Andrew	PO Box 11	Lakeside	(011)314-	(011)314-9998	
20	D1MDAVI	Mr. Mike Davies	INV004	Install - Built-in cupboard	1725	1725	2021/04/10	2021/03/11	1	27	327	Mike	P O Box 3	Halfway H	(011) 315-	083 286-8763	
21	D1ABGRE	Mr. AB Green	INV003	Paint - Exterior	1150	300	2021/04/09	2021/03/10	1	54	326	Andrew	PO Box 11	Lakeside	(011)314-	(011)314-9998	
22	C2ABCOS	ABC-Office-Supplies	PU002	Install - Built-in cupboards	-1725	-975	2021/04/05	2021/03/06	2	53	317	Walters	PO Box 88	Lakeview	(011)312-	(011)312-9998	

The first 6 rows will display the following:

- Row 1 - Date and timestamp on which the export file is created.
- Row 2 - Ledger - TRUE - Included in the Export file, if account is set as "*Open item account*". If FALSE - Ledger accounts was not selected in the Filter options.
- Row 3 - Debtors - TRUE - Included in the Export file, if account is set as "*Open item account*" If FALSE - Debtors accounts was not selected in the Filter options.
- Row 4 - Creditors - TRUE - Included in the Export file, if account is set as "*Open item account*" If FALSE - Creditors accounts was not selected in the Filter options.
- Row 5 - Blank row.
- Row 6 - Column headings

The exported data will be exported in 16 columns:

Colu	*Column heading*	*Source / fields*	*Remarks*

mn

A	*Account*	*Account code / Account no.*	*Ledger is prefixed by account type* *G = Ledger* *B = Bank* *T = Tax*
B	*Description*	*Name (Account description)*	
C	*Reference*	*Batches = Reference entered in Reference columns of Batch entry screens* *Documents = Document number*	
D	*Batch entry*	*Batches = Description entered in Description columns of Batch entry screens* *Documents = Document number / Your reference (on document headers)*	
E	*Transaction total*	*Total transactions*	
F	*Due*	*Total outstanding*	
G	*Due date*	*Due date*	*(Usually 30 days after the document date)*
H	*Date*	*Date of transaction / Date of document*	
I	*Account type*	*1 = Debtors* *2 = Creditors* *0 = Ledger* *3 = Bank* *4 = Tax*	
J	** -*	*Account ID*	
K	** Contactperson*	*Transaction ID*	

L	** Address*	*First name of the contactperson*
M	** Address 2*	*Postal address 1*
N	** Phone 1*	*Postal address 2*
O	** Phone 2*	*Telephone 1*
P	** -*	*Telephone 2*

* Column headings out of line in spreadsheet export, as column J does not include a column heading.

Columns L to P - The contact details (Contact person, Address, Address2, Phone1 and Phone2) is only applicable to debtor (customer / supplier) accounts (Account type 1) and creditor (supplier / vendor) accounts (Account type 2).

Columns L to P - will be blank for the following account types:

G	General ledger (Account type 0)
B	Bank (Account type 3)
T	Tax (Account type 4)

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Open item link - Selected account - Spreadsheet

The Transactions tab will list all transactions for each open item account. It will also list the outstanding amount (due amount) for each transaction.

Export options

To export a selected account to a spreadsheet:

1. Op die Default ribbon, select Open item link. The Totals tab (default) is displayed.
2. On the Totals tab or on the Transactions tab, select the specific account type(s) ledger account, debtor (customer / client) account or a creditor (supplier / vendor) account.

3. Click on the Filter button to list all accounts that have been set as open item accounts, and against which transactions have been posted in journals and/or documents for the selected account type(s).

4. Select the account and double-click on it.



> *Only outstanding items will be included in the export file.*
>
> *The export file in the Statement option will be similar to the default Open item link option for a selected account.*

5. Click the Export button. This will launch the "*Save As*" screen:



6. Select the folder in which you wish to save the file.folder in which you wish to save the file and enter a file name.

> *If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.*
>
> *If an existing exported file is opened, and you are trying to open a export file with the same name, a similar error message as the following will be displayed:*
>
> Cannot create file "D:\Export\Export.txt". The process cannot access the file because it is being used by another process.

7. Select the file type. Text files (*.txt) is the default; or select CSV files (*.csv) (Comma Separated Values).

> - *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
> - *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, Apache OpenOffice, LibreOffice, Ultra Office, etc.). You may need to set the "Separator Options" on the "Text Import" screen to "Tab".*

8. Click on the Save button. This will automatically open (launch) the exported file in the program associated with the selected file type.

Export file opened in Microsoft Excel

In this example, the exported "*Export.txt*" file (for a selected debtor (customer / client) account) is automatically opened in "*Microsoft Excel*":



The first 8 rows will display the following:

- Row 1 - Company name.
- Row 2 - Company address 1.
- Row 3 - Company address 2.
- Row 4 - Company address 3.
- Row 5 - Company postal code.
- Row 6 - Company phone number 1.
- Row 7 - Date and timestamp on which the export file is created.
- Row 8 -Blank row.
- Row 9 - Account type - Debtors, Creditors or Ledger (Account code also included in the export).

- Row 10 - Contact person - Only applicable if Debtors or the Creditors account type is exported.
- Row 11 - Address - Only applicable if Debtors or the Creditors account type is exported.
- Row 12 - Address 2 - Only applicable if Debtors or the Creditors account type is exported.
- Row 13 - Phone 1 - Only applicable if Debtors or the Creditors account type is exported.
- Row 14 - Phone 2 - Only applicable if Debtors or the Creditors account type is exported
- Row 15 - Column headings

The exported data will be exported in 8 columns:

Column	*Column heading*	*Source / fields*
A	*trn*	*Transaction ID*
B	*Reference*	*Batches = Reference entered in Reference columns of Batch entry screens* *Documents = Document number*
C	*Date*	*Date of transaction / Date of document*
D	*Amount*	*Transaction total*
E	*Outstanding*	*Total outstanding*
F	*Description*	*Batches = Description entered in Description columns of Batch entry screens* *Documents = Document number / Your reference (on document headers)*
G	*Link*	

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Bank reconciliation

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System parameters.

In addition to the petty cash account, the bank account is the only source where money can physically flow into and out of the business. The bank account should be strictly monitored to ensure that all the monies that are received are deposited, and that all the payments and/or cheques have been honoured.

The Bank reconciliation feature allows you to match, or reconcile, your Cashbook with the bank statement you receive from the bank. The bank reconciliation is a process of checking and comparing the transactions in your cashbook with the transactions on the bank statement.

All the transactions on the bank statement should be reflected in the cashbook and those transactions appearing in the cashbook, but not on the bank statement, should be reflected on the bank reconciliation statement.

When the bank statement is received, you will find that any bank costs (and interest if you have an overdrawn cheque account) is debited, and any interest that you have received on a positive bank balance is credited to your bank account. These transactions will appear on your bank statement, but will not appear in your cashbook. The same applies for debit orders and electronic payments as well as monies paid directly into your bank account by your customers or other parties.

The bank reconciliation helps you to identify these transactions and enter them into your cashbook. Another reason is the time factor. If you send a cheque to another supplier by post, this can take some time and the other party (beneficiary) to whom the cheque is issued, may bank the cheque too late for the bank to clear the cheque and reflect it on your bank statement. You may also have made a deposit up, after banking hours, and the deposit will only be reflected on the bank statement on the next day.

The bank reconciliation is carried out for a number of reasons. These are:

1. Determining of outstanding cheques and deposits and reporting it in the Cashbook Reconciliation report:
    - Outstanding deposits – Monies may have been received after banking hours and deposited into your bank account on the next day of the month or the day after the bank statement was printed.
    - Outstanding cheques – All cheques that were issued may not yet have been presented to the bank by the recipient or beneficiary of the cheque. The cheque may have been presented at a different bank or may not yet have reached the beneficiary of the cheque.

allows you to match your Cash-book with your bank statement. You will always find that the bank costs and interest paid/received does not appear in your Cash-book. The same applies for debit orders and electronic payments as well as moneys paid directly into your bank account by your customers or other parties. This bank reconciliation helps you to identify these transactions and enter them into your general ledger.

2. Recording of transactions on the bank statement which do not appear in the cashbook:
    - Electronic payments – Some electronic payments by debit orders may not reflect in the cashbook, but do appear on the bank statement.
    - Bank charges and interest – The amount of these bank charges will only be known when the bank statement is received. Interest may also be received on a favourable bank balance and can only be recorded when the amount is known.
    - Dishonoured cheques – Sometimes cheques deposited may have been returned to the drawer as there are no funds in the drawers account, or the cheque has not been signed, or many other reasons.

The transactions on the deposits (credit) side of the bank statement which are not yet recorded in the cashbook, should be entered in the receipts journal. The transactions on the payments (debit) side of the bank statement which are not yet recorded in the cashbook, should be entered in the payments journal.

3. Tracing and correction of errors:
    - Errors of entered transactions – This may occur when receipts were recorded in the receipts journal and/or when payments were recorded in the payments journals. Amounts may have been entered incorrectly (e.g. 45 instead of 54).
    - Errors of omission – Transactions have not been entered in the receipts or payments batches.
    - Errors that may occur at the bank – This is usually when the teller at the bank has recorded the amount of a cheque or a deposit incorrectly. This is very rare and is sometimes rectified automatically by the bank. (This is also referred to as "error in cast" on bank statements).
        - In the case where banks use the Automated Clearing Bureau (ACB) to read and record the cashed cheques electronically on your bank statement, you should take care that the cheques are written out clearly and correctly.
        - Deposit slips should also be filled in correctly and the entries (cash and cheques, etc.)

should add up correctly.

> *There are various reasons which may cause differences between the bank balance, as per bank statement, and the reconciled balance according to .*

4. Fraudulent cheques - The amounts on the bank statement should match the amount in the cashbook. If it does not, the cashed cheque should be scrutinised to determine that there was no tampering with the cheque.

You may receive a bank statement by fetching it from the bank or by post. An example of a bank statement is as follows:

Handyman Hardware Store
27 Olifants Raod
Emmarentia
Johannesburg
2195
Bank Statement No. 5

ABC Bank - Registered Bank
PO Box 111
Johannesburg
2000
Date of Statement: 1 April 2024
Page 1 of 1

Bank Statement for the period 1 March 2024 to 31 March 2024

Date	Transaction Description	Reference	Debit	Credit	Balance
01 March 2024	Balance brought down				3 193.00
01 March 2024	Deposit	D5000		5 000.00	8 193.00
16 March 2024	Deposit	D5001		3 000.00	11 193.00
30 March 2024	Cheque	106	345.00		10 848.00
30 March 2024	Cheque	107	575.00		10273.00
30 March 2024	Cheque	108	750.00		9 523.00
30 March 2024	Cheque	109	150.00		9 373.00
30 March 2024	Cheque	110	230.00		9 143.00
30 March 2024	Cheque	111	100.00		9 043.00
31 March 2024	Service Fee	SF	45.00		8 998.00

Definition of Codes	Deposits	Interest Received	Cheques	Unpaid Cheques	Other Debits	Bank Charges
CO - Commission DO - Debit Order INT- Interest SF - Service Fee UC - Unpaid Cheque	8 000.00	0.00	2 150.00	0.00	0.00	45.00

Important Notice
Statements are accepted as correct unless queried within 30 days. Any cheques reflected on this statement, which are not attached, will be included with your next statement.

The bank reconciliation is carried out for a number of reasons, such as:

- It checks to see that the transactions, which you have entered into osFinancials5/TurboCASH5, are the same as the transactions, which went through your bank.
- It checks to see that these transactions which went through the bank are the same as those going through your osFinancials5/TurboCASH5 program.
- It checks to see whether you or the bank is, in fact, correct.
- It will list all your outstanding cheques and receipts, thus giving you a reconciled bank balance, which would be the actual amount you would have in the bank, had all your transactions gone through the bank.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Hints when doing the bank reconciliation

Hints when doing the Bank reconciliation:

1. Check that you have all the bank statement pages and that they run sequentially.
2. Use the last day of the month and amount as per the bank statement - this will be your closing date (include items until) and bank balance.
3. Start at the beginning of the bank statement and not in the middle.
4. Use a ruler to make it easier to do the reconciliation line by line and "tick" every reconciled item on your statement.
5. If you find an error, go back to your Cashbook and try to correct it immediately. Do not simply carry on doing the reconciliation.

You may to do your bank reconciliation, even if all your batches have not been posted. You may post or update your batches after your reconciliation is completed, unless you are working on a “Client Machine” in a network environment.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Reconciling your cashbook with bank statements

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System parameters.

Once your receipt transactions have been entered in the Receipts journal and the payment transactions have been entered in the Payments journal, for a specific month or period, you may reconcile your cashbook (payments and receipts batches) with the bank statement. Before you start to reconcile, ensure the bank statement is received by post, or fetched from your bank or financial institution.

If you are registered for online banking, you may download a bank statement from your bank or financial institution, and import a bank statement which is saved in a valid file format on your system.

If you have any repeating transactions set up for your receipts batch and payments batch in Edit → Repeating transactions (Default ribbon), you need to copy them to the normal batch as they will not reflect in the cashbook for a specific period when doing the Bank reconciliation. Examples of such entries in the receipts batch would be amounts (debit orders) paid into your bank account on a monthly basis. Examples for the payments batch would be amounts (debit orders) paid out of your bank account on a monthly basis.

osFinancials5 allows you to reconcile your Bank accounts, before you update or post your Payments and Receipts Journals to the ledger.

This will allow you to easily correct any errors found (edit transactions, insert transactions which are omitted, delete transactions which are entered twice, reverse all the transactions if entered on the incorrect side, etc.), when doing the bank reconciliation.

You may also enter any transactions (such as bank charges and interest), which are listed in your bank statement, but do not appear in your cashbook.

You may post or update your batches after your reconciliation is completed, unless you are working on a "Client Machine" in a network environment.

To do a Bank reconciliation using a printed bank statement:

1. Obtain the Bank statement for the bank account you need to reconcile. The following is an example of a printed bank statement:

Handyman Hardware Store
27 Olifants Raod
Emmarentia
Johannesburg
2195

Bank Statement No. 5

ABC Bank - Registered Bank
PO Box 111
Johannesburg
2000

Date of Statement: 1 April 2024
Page 1 of 1

Bank Statement for the period 1 March 2024 to 31 March 2024

Date	Transaction Description	Reference	Debit	Credit	Balance
01 March 2024	Balance brought down				3 193.00
01 March 2024	Deposit	D5000		5 000.00	8 193.00
16 March 2024	Deposit	D5001		3 000.00	11 193.00
30 March 2024	Cheque	106	345.00		10 848.00
30 March 2024	Cheque	107	575.00		10273.00
30 March 2024	Cheque	108	750.00		9 523.00
30 March 2024	Cheque	109	150.00		9 373.00
30 March 2024	Cheque	110	230.00		9 143.00
30 March 2024	Cheque	111	100.00		9 043.00
31 March 2024	Service Fee	SF	45.00		8 998.00

Definition of Codes	Deposits	Interest Received	Cheques	Unpaid Cheques	Other Debits	Bank Charges
CO - Commission DO - Debit Order INT- Interest SF - Service Fee UC - Unpaid Cheque	8 000.00	0.00	2 150.00	0.00	0.00	45.00

Important Notice

Statements are accepted as correct unless queried within 30 days. Any cheques reflected on this statement, which are not attached, will be included with your next statement.

2. On the Default ribbon, select Cash / Bank (Alt + F2). The "*Bank statement options*" screen will list all transactions to the selected bank account up to the date specified:



3. Select and enter the following:

    a) Bank account - Select the cashbook you wish to reconcile.

    b) Include Items Until - Enter or select the date until which you would like to include cashbook transactions to be reconciled with your Bank Statement.

    c) Last total - The last total of the bank account will be displayed.

    d) Bank Balance - Enter the closing balance of your bank statement.

4. Click on the Open button and the *"Reconcile bank account"* screen displaying the name of your selected account is displayed:



This screen will list all the transactions Receipts and Payments Journals (batches) for the selected cashbook for the selected period. These entries represent your unreconciled items.

5. If you have more than one transaction with the same reference number (deposit or cheque number), you may click on the Consolidate icon.

This will group the transactions with the same reference number together, and it will display one amount which can then be matched with the bank statement.

6. You need to mark the item appearing on your bank statement as reconciled in the last column of this screen. To do this, you need to select the item and click on the reconciled field.

You may also use the Up arrow or Down arrow and the Spacebar on your keyboard to mark an item as reconciled or not.

The items displayed on your bank statement also need to be manually ticked off on the printed bank statement.

You will find that not all the transactions would be selected or marked on the Reconcile Bank

account screen and the bank statement. These unmarked transactions or items are as follows:

a) *Bank Statement - These unmarked transactions are not yet entered in your cashbook (receipts or payments journal (batch)). You need to exit this screen and enter the unmarked items or bank statement transactions in the cashbook as follows:*

- *Debits - enter these transactions in the payments journal (batch).*
- *Credits - enter the transactions in the receipts journal (batch).*

Once all these transactions are entered, or if any errors are found at this stage, and are corrected, you need to access the Reconcile Bank account screen again and mark the corresponding transactions.

No difference should be displayed on the bottom right-hand corner of the Reconcile Bank account screen. If any differences are displayed, you need to find these differences and correct them.

b) *Reconcile Bank account screen - These unmarked items or transaction which are not selected, represent outstanding deposits (receipts) and outstanding cheques (payments). These transactions will be reported in the bank reconciliation statement and should be displayed on the next bank statement.*

7. Once this is done and there is no difference displayed on the bottom left-hand corner of the Reconcile Bank account screen, click on the Process icon.

This will group the transactions with the same reference number together, and it will display one amount which can then be matched with the bank statement.

8. Click on the Reconciliation icon to print a bank reconciliation report. This report will reflect the outstanding deposits and payments (cheques), and will also display any differences.

9. Click on the Close button on the title bar to close or exit the Bank reconciliation screen.

If this report does not reflect any differences between the cashbook and the Bank balance, it is said to be "in balance" as at a specified date. This report will also enable you to determine whether bank charges and other debits or credits appearing on your bank statement, are recorded in your cashbook for the selected period.

If you access or return to the receipts and payments journal, to add or to edit any transactions, the transactions (which are marked or selected as reconciled items or transactions) will be displayed in a blue font colour.

Speed buttons - Bank reconciliations

The following speed buttons (icons) are available to help you to reconcile or unreconcile your cashbook with the bank statement:

1. Consolidate - Click to consolidate all entries in the selected cashbook with the same reference number.

   If an entry is selected, for which other entries with the same reference number exists, all these entries will be displayed in a different colour (blue).

   The total amount of all these entries with the same reference number will be displayed as a Posted Payments item, or Unposted Payments item, or Posted Receipts item, or an Unposted Receipts item.

   If you click on this icon again to turn it off, all entries will be listed as individual entries with the same reference number and will not be consolidated.

2. Show statement - Click to split the screen in two sections. The top section will display the details of the Receipts and Payments batches while the bottom half of this screen will display the details of the transactions displaying on the bank statement.

   Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

   The BankOnline Plugin - Not implemented at this stage. You may use the BankImport Plugin to import bank statements (if the "Default bank reconciliation method" field is not selected on Setup → Setup → System parameters).

   If you click on this icon again, the "*Bank statement transactions*" section will not be displayed.

3. Reconcile - Click to automatically reconcile all payments and receipts for a specified period.



If you select the "Reconcile by reference" field, you will not be able to select the date from and to. This will allow you to automatically reconcile payments and receipts for a specified reference number.

4. UnReconcile - Click to automatically unreconcile all payments and receipts for a specified period.



If you select the "UnReconcile by reference" field, you will not be able to select the date from and to. This will allow you to automatically unreconcile reconciled payments and receipts for a specified reference number.

5. Search - Click to launch a screen (displayed on the bottom of the reconciliation screen) where you may enter any of the following to search for an item:



a) Search by reference - You need to enter a valid reference number. The date and amount for the specific transaction will be displayed.

b) Search by amount - You need to enter the amount and the entry will be selected. The reference and date for the specific transaction will be displayed.

c) Search by date - You need to enter a valid date within the periods and the entry will be selected. The reference and amount for the specific transaction will be displayed.

6. Report – Click to launch the "*Bank account recon options*" screen on which you may print a bank reconciliation report.

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Bank charges and items on the bank statement

You would only know what your bank charges are when you actually receive your bank statement from the bank. Any bank charges that have to be paid must be entered into your "*Payments journal*", and only interest received must be entered into your "*Receipts journal*".

It is always a good idea to use a reference number; such as your Bank Statement number; so as have a reference to the specific bank statement.

You now need to go back to your Payments journal and enter your bank charges. Press the Esc key to exit the reconciliation.

Before exiting the batch, make sure that you have clicked on the Apply reconciled option on the Process button to save the "ticks" and reconcile the ticked items).

To enter bank charges and finalise the bank reconciliation:

1. Click on the Batch entry icon. (You may also press the F2 key). The "*Batch type*" screen will be displayed.
2. Select the Payments Jnl and click on the Open button. The "*Payments journal*" screen will be displayed.
3. Enter the Alias (BatchName) as "*ABC-Payments-BS5*".
4. Enter the following transaction:
    a) Reference: BS5
    b) Date: 2024/03/31
    c) Description: Bank charges- Bank statement no.5
    d) Account: Bank Charges
    e) Tax: Select No Tax for the purposes of this documentation.

        Tax (VAT/GST/Sales tax) may be applicable to some charges on your bank statement, if you are registered as a VAT/GST/Sales Tax vendor.

    f) Amount: 45.00 DR

        In practice, it is easier to enter any bank charges, debit orders, interest, etc. into your Payments or Receipts Journals before starting the reconciliation.
5. Balance the batch. After entering the transactions and balancing the batch, the Payments Jnl is as follows:



6. List the unposted transactions in the batch.
7. Post the batch.
8. Press the Esc key to exit the batch or journal.
9. Go back to your bank reconciliation and reconcile your bank charges. (To do this, tick the Unreconciled item and click the Process icon and select the Apply reconciled option) on the The Difference in the bottom right-hand corner of the "*Reconcile bank account*" screen should now reflect a nil balance.

> *Once you have completed your bank reconciliation, you must check that your Cashbook is, in fact, in balance.*

10. Click on the Report icon.

> *Any unreconciled payments will be subtracted from a positive bank balance and any unreconciled receipts will be added to a positive bank balance according to the bank statement, thus giving a reconciled balance.*

11. Click on the Close button of the *Reconcile Bank account Options* screen; or press the Esc key to exit (close) these screens.

Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-Use Tool

Bank reconciliation reports

A bank reconciliation report typically includes the following information:

1. Bank statement balance: The balance of the bank account as shown on the bank statement.

2. Company statement balance: The balance of the bank account as shown in the company's records.
3. Adjustments: Any adjustments made to the company's records to reconcile them with the bank statement, such as outstanding checks or deposits in transit.
4. Reconciled balance: The final balance of the bank account after all adjustments have been made.
5. Date range: The period covered by the bank statement and the company's records.
6. Explanation of differences: Any differences between the bank statement and the company's records should be explained, including any discrepancies that could not be resolved.

The bank reconciliation report provides a clear picture of the company's cash position and ensures that the company's records are accurate and up-to-date. It is an important tool for financial management and helps to identify any errors or discrepancies in the financial records.

To print a bank reconciliation report:

1. Click on the Report icon on the *"Bank statement options"* screen.



All the data of the Bank account, Date, Bank balance, etc. should still be the same as per your your previous selection criteria.

2. Click on the Open or Reconcile button. The "*recon.rep*" report parameters screen will be displayed:



If you wish to print the bank reconciliation report in the PDF file format, you may tick the "Open in PDF" option.

3. The "*Bank reconciliation report as at*" is displayed:



After the bank reconciliation is finalised, the Difference should be 0.00. If there is an amount in the Difference section of the report, you may need to find the differences and fix them. - See Troubleshooting differences.

Created with the Standard Edition of HelpNDoc: Free Kindle producer

Troubleshooting differences

If there is a difference between the reconciled balance and the balance according to osFinancials5/TurboCASH5, there is an error, in the “Payments” or the “Receipts” journals. Search for the error and correct it.

Steps to resolve differences in the Bank reconciliation

If there are differences between the bank statement and the company's records during the bank reconciliation process, the following steps can be taken to resolve them:

- Verify the accuracy of both sets of records: Check the company's records and the bank statement to make sure that they are accurate and up-to-date.
- Check for errors: Look for any errors or mistakes that may have been made in recording transactions. For example, a transaction may have been recorded twice, or an incorrect amount may have been entered.
- Investigate outstanding transactions: Outstanding transactions, such as checks that have not yet cleared the bank, may need to be investigated to determine the cause of the difference.
- Contact the bank: If the cause of the difference cannot be determined, contact the bank to request more information about the transactions in question.
- Make adjustments: Once the cause of the difference has been identified, adjustments can be made to correct the records. For example, if an outstanding check is causing the difference, it can be subtracted from the company's records.
- Reconcile again: After making any necessary adjustments, reconcile the bank statement and the company's records again to ensure that the difference has been resolved.

It is important to resolve any differences in the bank reconciliation process as quickly as possible to ensure that the company's financial records are accurate and up-to-date.

Examples causing differences

A few examples that can possibly cause a difference:

- Your closing bank balance is incorrectly entered on the *"Reconcile Bank account"* screen (Reconciliation on the Default ribbon).
- Incorrect date entered ("*Include Items until*" field) on "*Bank account recon options"* screen (Reconciliation on the Default ribbon).
- Errors in posting - they should have been detected when your bank reconciliation was done.

- If everything else fails you may sometimes have to look at your Cash-book and link up the source documents to check if you have entered all your transactions correctly. You could also have posted an amount incorrectly e.g. as 64.00 and entered it as 46.00.

You may need to print the posted batch transactions for the period on the following options to trace the errors:

- Batch transactions per period report for the Payments and Receipt Batch and the (Reports → Batch entry) (select the period of your Bank reconciliation).
- Batch entry for the Payments batch and/or Receipts batch (Batch entry - Posted batches tab). Select the correct batch and double-click on it. Click on the Print button.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Bank import plugin

Using the Bank import plugin, you may import a valid bank statement file (downloaded from your online banking) saved on your system into a Bank account (Cash-book).

This Bank import plugin will save you time, since you do not need to physically enter the transactions manually in the Payments journal and Receipts journal.

This plug-in uses Bank references to automatically allocate or link payments and deposits, receipts, other debits. credits, etc. to the correct accounts.

It further supports the bank accounts of your debtors (customers / clients) to use the automatic receipts for debit orders, etc.

It further supports the bank accounts of your creditors (suppliers) to use the automatic payments to manage the payments to suppliers, etc.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bankimport plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices. Needs to be activated on the Setup ribbon, select Setup → System parameters.

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Access control

This option allows you to set the security options for a specific Set of Books. User passwords and access levels may also be set. You may have as many users to work on a Set of Books as you wish. You may set differing functions and restrictions for each user, in order that they are enabled to perform only the function(s) assigned to them.

Multi-User Plugin

This version of osFinancials5/TurboCASH5, may be configured and set up a Network Server for multi-users. To enable the full multi-user functionality, you need to purchase a multi-user license and register osFinancials5/TurboCASH5 as a multi-user product.

- *Multi-user installation and configuration are described in the following documentation:*
  - *Multi-user Windows installation*
  - *Multi-user Linux server install*
  - *Multi-user installation (TurboCASH website)*
- *Multi-user is limited in this edition! You will need to buy a multi-user licence.*

Other plugins for a multi-user environment:

Multi-Language accounts - Manual - Shop - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

Multi-User calendar (agenda) - Manual - Shop - Licence : Once-off -

This plugin adds the multi-user agenda (multiple agendas) to the Calendar (Planner). You can add agendas and link them as default to the current user. For every agenda a tab will appear in the agenda Calendar so you can see what the appointments, etc. are on other agendas. You can have a agenda for each employee, salesperson, user, etc. and create invoices directly from his / her agenda with a simple click. Each agenda has it's own calendar and task list.

This option allows you to set the security options for a specific Set of Books, your users, their passwords,

e-mail addresses and access levels to restrict the users to perform specific functions.

Access control may be used for single-user installations on a single device.

Some functions for persons (not using the multi-user licence) are:

- *Creating and changing passwords.*
- *Customise / Configure Document processing:*
  - *Add the Posting / Confirm and Delete buttons to the Document listing screen*
  - *Activate the Read-only Tax in Documents*
- *Customise Setup groups - Deselect (remove ticks) for Groups that you do not wish to be listed when accessing Setup → Groups. For example, if you do not want / need to use Cost centres or Projects, etc., you may deselect these not to display on the Groups Setup.*
- *Activate Cost Centres in Documents - This will allow you to select Cost centre when selecting stock items in documents.*

You may also create a password for one user only (which has all the access levels) if you have no other users. Once you have entered (or set a password), the Set of Books in which you have set up the password can only be accessed when a valid password is entered, unless the user with the system function deletes all the passwords.

If you need to send reports and documents via e-mail, you need to enter a valid e-mail address on at least any of the following options before you can set up and configure osFinancials5/TurboCASH5 for the Internet:

- *Setup → Company info - E-mail field, or;*
- *Setup → Access control to create a user and enter a valid e-mail address.*

You may have as many users to work on a Set of Books as you wish. You may set differing functions for each user. If any of the users enter a valid password, that user will only be able to access those functions you have allocated to that user. The disabled functions will be inactive or not available on the menu options and ribbons for that user.

By default, Access control to all the functions in a Set of Books is allowed when you create a user. To restrict a user from certain or specific functions, you simply have to deselect (remove the tick) from the option, function or feature you do not wish that user to have access to.

The access control options, functions or features are as follows:

- Standard security - Allow or restrict a user to System Setup, Delete Set of Books on the Start ribbon and Global processes (Clear / Reset, Reverse posted batches / documents) and Do year end on the Setup ribbon.

- Reports access - Allow or restrict a user to print or view Creditor reports, Debtor reports, General ledger reports, Stock reports or User reports.

- Batches access - Allow or restrict a user from Posting batches and/or Updating documents to the Ledger, to enter transactions in Batches (Journals) or to create and edit Documents (Invoices, Purchases, Credit notes and Supplier returns). If you allow a user to enter transactions in Batches (Journals), you may restrict a user from accessing and processing transactions in batches (journals). For example, if you have a Petty Cashier, you may allow that person to only access the Petty cash payments journal; the Cashier only has access to process receipts in the Receipts journal, etc. In addition to this, you may also restrict or block a user from accessing specific accounts.

- Others - Allow or restrict the user from access to create, edit or delete master files, such as General ledger accounts, Debtor (customer / client) accounts, Creditor (supplier / vendor) accounts, Bank accounts and/or Stock items, set the mode for the user and link the user to a salesperson. You may select to restrict the selected user from updating (posting) documents to the ledger and/or set customised limitations.

- Documents - Allows to configure document processing.

- Groups - By default, all available groups will be available. Groups that you do not wish to be listed when accessing Setup → Groups (Setup ribbon) may be deselected. For example, if you do not want / need to use Cost centres or Projects, etc., you may deselect these not to display on the Groups.

- Usertabs - Customise and manage the user navigation for a selected user on the User tab ribbon options in up to six (6} groups.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Access control - Passwords

In osFinancials5/TurboCASH5, you have the option to create and manage passwords for user authentication in the Setup → Access control menu on the Setup ribbon.

It is recommended to create at least two users with passwords, with the main user being the administrator who has access to all default functions within a Set of Books.

For additional users and any other users for whom you have created passwords (excluding the main user who is the administrator), you can utilise the User tab ribbon to customize the Set of Books in osFinancials5/TurboCASH5. You can also review and configure specific settings to personalise the use of certain functions and preferences on the Standard security, Reports access, Batches access, Others, Documents, Groups and Usertabs tabs.

In addition to the options provided on these tabs for customising functions and preferences, you can also restrict specific users from accessing or performing certain functions within osFinancials5/TurboCASH5 Set of Books.

To ensure security, it is advisable to change passwords periodically. The password field consists of eight characters, including alphanumeric and special characters. It is important to note that passwords are case-sensitive. When a user password is set, it becomes essential to enter the password correctly when performing actions such as opening or deleting a Set of Books, or executing specific functions like year-end processes.

When accessing a Set of Books, deleting a Set of Books, or performing certain functions, a login screen will prompt you to enter a valid username (if required) along with the corresponding password associated with that username.

In addition to setting passwords for osFinancials5/TurboCASH5 Set of Books, it is also recommended to implement user control and passwords for your operating system. This provides an additional layer of security for accessing the osFinancials5/TurboCASH5 software and helps protect sensitive financial information. By using user control and passwords for the operating system, you can ensure that only authorized individuals can access and use the software and its associated data.

In addition to the access control feature in osFinancials5/TurboCASH5, you have the option to set and configure passwords for your operating system and/or network. This refers to the passwords used to secure access to your computer or network infrastructure, separate from the application itself.

Setting strong and unique passwords for your operating system and network is an essential security measure to protect your osFinancials5/TurboCASH5 data and prevent unauthorized access. By implementing password policies and configurations at the operating system and network levels, you add an extra layer of security to your overall system.

Here are some considerations for setting and configuring passwords for your operating system and network:

1. *Strong Passwords: Choose passwords that are complex, combining uppercase and lowercase letters, numbers, and special characters. Avoid using easily guessable or common passwords.*
2. *Unique Passwords: Use different passwords for different accounts or systems. Reusing passwords across multiple platforms increases the risk of unauthorized access if one password is compromised.*
3. *Password Length and Complexity: Set minimum password length requirements and enforce complexity rules to ensure passwords are sufficiently robust.*

4. *Password Expiration and Renewal: Implement a password expiration policy that requires users to change their passwords at regular intervals. This practice helps mitigate the risk of password-related vulnerabilities.*
5. *Account Lockout Policies: Configure account lockout settings to automatically lock user accounts after a certain number of failed login attempts. This helps prevent brute-force attacks and unauthorized access attempts.*
6. *Two-Factor Authentication (2FA): Consider implementing two-factor authentication for your operating system or network, which adds an extra layer of security by requiring users to provide a second form of verification, such as a code sent to their mobile device.*

By ensuring strong and unique passwords, enforcing password policies, and implementing additional security measures like two-factor authentication, you can strengthen the overall security of your operating system and network. This, in turn, helps protect your osFinancials5/TurboCASH5 data and reduces the risk of unauthorized access or data breaches.

Created with the Standard Edition of HelpNDoc: Ensure High-Quality Documentation with HelpNDoc's Hyperlink and Library Item Reports

Create passwords

To use passwords, you need to create at least two (2) users.

In addition to this access control feature, you may also set and configure the passwords for your operating system and/or network.

To create a user passwords:

1. On the Setup ribbon, click on Setup → Access control.



2. Click on the Add button to create an user. An icon, will be displayed in the "*User*" area of the screen.

3. Right-click on the New user0 icon and select the Rename option on the context menu. Enter the name for this user. The user's name will be displayed next to the "Username" field.

4. Enter a Password. The E-mail address (optional) for this user and select the access levels for this user.

If you do not enter a user password, an error message is displayed:

Please type in a password for this user!

If your confirmation password does not match the user password, an error message is displayed:

Password do not match

5. You may select the options to allow or restrict a user to access on the various options on the tabs (i.e. Standard security, Reports Access, Batches Access, Others, Documents, Groups and/or User tabs.

6. Click on the Apply button to save the changes for this user.

7. Repeat the process if you have more than one user. Once finished, click on the tabs, to set the access levels for each selected user.

8. Once finished, click on the Close button to exit the "*Access control*" screen.

You may select the specific options for which you wish to restrict that user by removing the tick for the specific option the user may not access. You may move down the options with the Down Arrow or Up Arrow keys and toggle between a tick and a blank in the tick box fields with the Spacebar on your keyboard, or select it with the mouse and click on the box you want to select or deselect.

It is recommended that at least one User (Default user or System administrator) should have no restrictions on the System setup.

If you disable some menu or access options for a user, you may select to hide disabled menu items, If this option is not selected, any disabled menu items, (e.g. system setup, global processes, reconciliation, reports, edit accounts, etc.) will be displayed as an inactive option (greyed out).

User icons are displayed as follows:

- indicates that all functions are allowed to that user.

- some functions or security options are restricted or disabled.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

Delete passwords

You may delete a password for a selected user. All other users may still continue to use their passwords to open and work in a Set of Books. You could also delete the passwords for all users, in which case the security options will then be disabled.

To delete an user password:

1. On the Setup ribbon, click on Setup → Access control.



2. Make sure that the correct User is selected, or click on the User icon, which you need to delete.

3. Click on the Delete button. You may also right-click on the selected User icon and select the Delete option on the context menu.

Should you delete user system administrator and then user with restrictions, the following confirmation message is displayed:

> Not accessing the Setup system with just one user
> makes changing user privilages unposible by the program!
> Are you sure you want to continue?

4. A confirmation message is displayed:

> Warning, this will seriously affect your Set of Books! Do you still wish to continue?

5. Click on the Yes button. The selected user password and all security options and access levels for that user will be permanently removed. If you click on the No button, the user will not be removed.

6. Click on the Close button to exit the "*Access control*" screen.

If you delete the last of the users in a Set of Books, the password login will be cleared and display the information message is displayed.

> You have chosen to delete all users! Access control will now be disabled!

Click on the OK button. The Login screen will not be displayed when you Open or Delete the Set of Books.

Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Enter passwords (Login)

If you need to Open a Set of Books or Delete a Set of Books, the "*Login*" screen to allow the user to enter a valid username and password password for the Set of Books:

Enter a valid password and click on the OK button.

The password is an eight-character alphanumeric and special character field. The password is also Case sensitive. Remember if you use Capital alpha characters. Once a user password is set, you will not be able to Open a Set of Books or to Delete the Set of Books, if you do not enter the password absolutely correctly.

Should you enter an incorrect username and password, an error message is displayed:

Invalid password!

Click on the OK button and re-enter the correct password. Check that your Caps Lock key is not accidentally switched on.

After the third attempt when an invalid username and/or password is entered, the Set Books (open) screen will be automatically closed.

To use (enable) passwords, you need to create at least two (2) users with passwords.

If users have been created and passwords are set for the users, a login screen for Point-of Sale Invoicing access will be displayed on which the Cashier or Salesperson needs to enter a valid username and password.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Access control - Standard security tab

The Standard security tab in the Access control feature of osFinancials5/TurboCASH5 serves as the primary tool for managing user access and permissions. Here are the key features of the Standard security tab:

1. User management: The Standard security tab allows you to create users and set or change their passwords and email addresses. You can also disable or delete user accounts as needed.
2. Access to main functions: In the Standard security tab, you can define user access to important functions such as System setup, System menu, Global processes, and Bank reconciliation. By allowing or restricting access to these functions, you can control what users can do within the system.

3. Display of menu options: When you restrict a user's access to specific functions, all menu items are displayed by default. However, the menu options to which the user has no access will be displayed as inactive or greyed out. If desired, you can choose to hide these inactive menu options, ensuring that users only see and interact with the functions they are allowed to access.

By utilizing the Standard security tab, you can create a secure environment and tailor user access to specific functions within osFinancials5/TurboCASH5. This helps maintain control over system configuration, global processes, and critical financial functions while ensuring that users only see and access the relevant features based on their assigned permissions.

To set standard security options for an user:

1. On the Setup ribbon, click on Setup → Access control.



2. System lang - The default language set for each user for will be displayed in this field. You may set another language for each of your users. The selected language will be displayed every time a specific user opens the Set of Books.

3. Language - The languages added in the Languages tab in Groups (Setup ribbon) may be selected for the *Multi-Language accounts* plugin. Languages may also be set in the this field for debtors /creditors.

Multi-Language accounts - *Manual* - *Shop* - *Licence : Once-off* -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

4. Select an user in the "*User"* field or area of the screen.

> *Do not select the Default user with all rights (Universal administrator).*
>
> *The Universal administrator (Default user) user should not have any restrictions.*

5. By default, all options are selected (ticked), except the "*Disabled"* and "*Hide disabled"* options.

> *If an user is set to disabled, (Disabled field ticked), and the disabled user tries to log in, an error message will be displayed.*
>
> "Access control"

6. The options to set the access levels is as follows:

   a) System setup -

      i) Start ribbon - Disables the following:

         - Create Set of Books (Creation wizard).
         - Save as.
         - Delete Set of Books.

      ii) Setup ribbon - Disables all features, except the following:

         - Calculator - Can access the calculator.
         - Import - Import accounts, debtors, creditors, documents and stock from specific file formats.
         - Export - Export accounts, debtors, creditors, documents, stock and posted batches to specific file formats.

   b) Global processes -

      i) Import - Disables import of accounts, debtors, creditors, documents and stock from specific file formats.

      ii) Export - Disables export accounts, debtors, creditors, documents, stock and posted batches to specific file formats.

      iii) Setup ribbon - Disables the following seven (7) options:

- Global processes - The following four (4) options are available:
    - Clear / Reset - This option allows you to clear all the transactions and balances in a Set of Books.
    - Do year end - This option allows you to close off all the nominal accounts (income and expense accounts) and transfer the balances for the financial year to the Retained income / earnings account. The start date and the reporting dates for the financial year will also be created for the new financial year.
    - Copy from a Set of Books - This option allows you to copy the data from a selected Set of Books into the active (open) Set of Books. This will replace all the data in the active Set of Books.
    - Reverse posted batch / document - This feature allows you to reverse or cancel the transactions in posted documents and batches.

iv) Tools - Disables the following options:

- Data integrity check - Run a Data integrity check and print a Data integrity check report.
- Customise language - Customise (edit, change and translate) language files.
- Close active forms - Close any open forms (e.g. Documents, Debtors, Creditors, Stock items screens, etc.)
- Activate plugins - By default, no plugins is activated when osFinancials5/TurboCASH5 is installed. This option allows you to activate / deactivate all plugins, registered plugins or specific plugins. The activated plugins will be available from the Plugins menu.
- Plugins - By default, no plugins are listed on this menu. Only activated plugins will be listed.
- Others - Not used.

c) Reconciliation - Disables the bank reconciliation feature.

d) System menu -

i) This will disable the (Start ribbon).

- Delete Set of Books option.
- Online registration - Register the osFinancials5/TurboCASH5 program.
- Help menu - Disable the following seven (7) options:
    - Help - Launch the osFinancials Help system where you may locate topics.
    - Support - View contact information of osFinancials5/TurboCASH5 or go to the Support page via the Internet.
    - Show Welcome - By default, the Welcome to osFinancials5 / Welcome to TurboCASH5 screen displays the website. If the Welcome to osFinancials5 / Welcome to TurboCASH5 screen is not displayed, it will launch the Welcome to osFinancials5 / Welcome to TurboCASH5 screen.
    - Updates -
    - Forum - Please visit our Forum to find solutions or to post comments, etc.
    - Webshop - Please visit our webshop.
    - Bug report - View, search and report any bugs on our bug-tracking system.

ii) This will disable the following on the Default ribbon:

- Update ledger (F3) – Disables Update ledger (F3) posting of batches and documents.
- Edit menu - Disable the following three (3) options:
    - Repeating transactions - Enter / edit transactions in batches of a recurring nature.
    - Repeating invoices - Generate and process invoices of an recurring nature.
    - Delete - Delete sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and

orders).

- Input - Disable the following six (6) options:
  - Adjust stock - Access the Edit Stock screen.
  - Confirm - Confirm and convert quotes to invoices and orders to purchases.
  - Backorders - Add, edit and delete back orders for stock items.
  - Sales documents - Process / edit invoices, credit notes and quotes.
  - Purchase documents - Process / edit purchases, supplier returns and orders.
  - POS Invoice - Run and manage a point-of-sales shift and process point-of-sale invoices.

7. Select to allow or restrict a user to System Setup, Delete Set of Books on the Start ribbon and Global processes (Clear / Reset, Do year end, Reverse posted batches / documents) on the Tools ribbon. (You may press the Spacebar on your keyboard to select or deselect an option).
8. Applying changes: Click on the Apply button to save the changes for the selected user.
9. Setting access levels for other users: If necessary, select the next available user and configure their access and restrictions in the same manner.
10. Finalizing changes: Once you have finished setting the access levels for all desired users, click on the Close button to exit the "*Access control*" screen.

You may select the specific options for which you wish to restrict that user by removing the tick for the specific option the user may not access. You may move down the options with the Down Arrow or Up Arrow keys and toggle between a tick and a blank in the tick box fields with the Spacebar on your keyboard, or select it with the mouse and click on the box you want to select or deselect.

It is recommended that at least one User (Default user or System administrator) should have no restrictions on the System setup.

If you disable some menu or access options for a user, you may select to hide disabled menu items, If this option is not selected, any disabled menu items, (e.g. system setup, global processes, reconciliation,

reports, edit accounts, etc.) will be displayed as an inactive option (greyed out).

User icons are displayed as follows:

- indicates that all functions are allowed to that user.

- some functions or security options are restricted or disabled.

Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Access control - Reports access tab

The Reports access tab in the Access control feature of osFinancials5/TurboCASH5 allows you to control a user's access to printing and viewing specific reports in a Set of Books.

To set reports access options for an user:

1. On the Setup ribbon, click on the Setup → Access control menu. Then, navigate to the Reports access tab.



2. Selecting the User: Ensure that the correct user is selected for whom you want to restrict or allow access to reports. If needed, click on the User icon to select the desired user.

3. Configuring reports access: To restrict the selected user from accessing specific reports, remove the tick in the respective field. To allow access to reports, place a tick in the field to allow access to the following reports:

    a) Creditor reports - This option is not implemented, so it does not affect the user's access to

creditor reports.

b) Debtor reports - This option is not implemented, so it does not affect the user's access to debtor reports.

c) General ledger reports - Allow access to print, view and export reports from the Ledger analyser 1, Ledger analyser 2, T-Account viewer. All Ledger reports (except Ledger analyser 1) accessed from the Reports menu list on the Reports ribbon, are still available to print.

d) Stock reports - This option is not implemented, so it does not affect the user's access to stock reports.

e) User reports - This option is not implemented, so it does not affect the user's access to the User reports menu.

4. Applying changes: Click on the Apply button to save the changes for the selected user.
5. Setting access levels for other users: If necessary, select the next available user and configure their batches access and account restrictions in the same manner.
6. Finalizing changes: Once you have finished setting the access levels for all desired users, click on the Close button to exit the "*Access control*" screen.

By utilizing the Reports access tab in Welcome to osFinancials5 / Welcome to TurboCASH5, you can manage and control a user's access to specific reports, allowing you to tailor their reporting capabilities based on their responsibilities and requirements within the Set of Books.

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Access control - Batches access tab

The Batches access tab in the Access control feature of osFinancials5/TurboCASH5 allows you to manage user access to accounts and posting of transactions in batches and updating document transaction to the ledger.

The key features on the Batches access tab to control access to specific functions, is as follows:

1. Default account access: By default, all users have access to all accounts in the Set of Books. This includes General ledger accounts (Income and Expense Accounts, Capital, Assets, and Liabilities Accounts), Bank accounts, Tax accounts, Debtor accounts, and Creditor accounts.

2. Blocking specific accounts: To restrict or block access to specific accounts for a user, access the Batches access tab and you will see a list of all accounts in the Set of Books. Simply deselect (remove the tick) from each account that you wish to block access for that user. Once blocked, the user will not be able to process any transactions involving the blocked or restricted accounts.

3. Blocking access to specific batches: You may restrict a user to specific batches (journals) For example, if you have a Petty Cashier, you can allow them access to only the Petty cash payments journal. This means they will only be able to process transactions within the Petty cash payments journal and won't have access to other journals or batch types to process transactions.

4. Posting batches and updating documents: In addition to account access, the Batches access tab allows you to control user access to posting batches and updating documents to the ledger. If you allow a user to enter transactions in batches (journals), you can restrict their access to processing transactions in specific batches. This means they can only work with specific journals or transaction types based on their assigned permissions.

5. Creating and editing documents: You can also allow or restrict a user from creating and editing various types of documents, including Invoices, Purchases, Credit notes, and Supplier returns. By setting the appropriate permissions, you can control which documents the user is allowed to create and modify.

By using the Batches access tab, you can finely tune user permissions, limiting access to specific accounts and transaction functions within osFinancials5/TurboCASH5. This helps maintain control over financial transactions, ensuring that users can only work with authorized accounts and perform designated tasks based on their assigned roles and responsibilities.

To set the batches access options for an user:

1. On the Setup ribbon, click on the Setup → Access control menu. Then, navigate to the Batches access tab.



3. Selecting the user: Ensure that the correct user is selected for whom you want to restrict or allow access to batches, accounts, and processing options. If needed, click on the User icon to select the desired user.

4. Configuring batches access: To restrict the selected user from accessing and processing transactions using specific journals (batch types), remove the tick in the respective field. To allow access to specific journals (batch types), place a tick in the field.

> *You can use the Spacebar on your keyboard to select or deselect an option.*

5. Blocking specific accounts: By default, all users have access to all accounts in the Set of Books. To restrict or block access to specific accounts for a user, click on the Select accounts to block button. This will open the "*Select accounts to block*" screen, where you can see a list of all accounts in the Set of Books. Deselect (remove the tick) from each account that you wish to block access for that user. Once blocked, the user will not be able to process any transactions involving the blocked or restricted accounts.



> *You may press the Spacebar on your keyboard to select or deselect an option.*

Remember to click OK on the "Select accounts to block" screen to save your selection.

6. Posting: In addition to account access and batches access, the Batches access tab allows you to control user access to posting batches and updating documents to the ledger. If you allow a user to enter and edit transactions in batches (journals), you can restrict their access to posting transactions in batches. This means the Post option on the "*Batch entry*" screen will be inactive. Users will also have the option to create and edit transactions in batches (journals). Restricted users with the "Posting" option, will also have the option to create and edit various sales documents (such as invoices and credit notes) and purchase documents (such as purchases and supplier returns). However, the Update button on the "*Update documents*" screen will be inactive. This allows you to control which users is allowed or restricted to updating documents to the ledger.
7. Creating and editing documents: You can also allow or restrict a user from creating and editing various types of documents, including Invoices, Purchases, Credit notes, and Supplier returns. By setting the appropriate permissions, you can control which documents the user is allowed to create and modify.
6. Applying changes: Click on the Apply button to save the changes for the selected user.
7. Setting access levels for other users: If necessary, select the next available user and configure their batches access and account restrictions in the same manner.
8. Finalizing changes: Once you have finished setting the access levels for all desired users, click on the Close button to exit the "*Access control*" screen.

If a user attempts to access a batch type or journal type for which access has been disabled in osFinancials5/TurboCASH5, they will receive a warning message indicating the restriction. The message will typically state:

> "User cannot use this batch! Enable access in Setup → Access control"

To proceed, the user should click on the OK button.

If they had selected an incorrect batch, they should select the appropriate batch (journal) instead.

If the restriction persists or they believe access should be granted, they should contact their System Administrator or the person responsible for managing access control settings. The System Administrator can then review and modify the access control configuration to allow the user access to the desired batch type or journal type.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Access control - Others tab

The Others tab in the Access control feature of osFinancials5/TurboCASH5 allows you to define access options for specific users in a Set of Books. With this feature, you can control the user's access to create, edit, or delete master files, set point-of-sale settings, and apply custom limitations. Additionally, you can specify the user's mode of operation, such as Invoice/Accounting, Accounting only, or Point-of-Sale only. Furthermore, you can link the user to a salesperson for enhanced security in Point-of-Sale activities.

To set other access options for an user:

1. On the Setup ribbon, click on the Setup → Access control menu. Then, navigate to the Others tab.



2. Select the desired user: Ensure that the correct user is selected for whom you want to configure access options. If needed, click on the User icon to select the desired user.

3. Accounts - Select the following options, if necessary:

    a) Edit stock - Remove the tick to restrict the selected user from access to create, edit or delete stock items. This will set the Stock items option on the Default ribbon to inactive.

    b) Edit user report - Not implemented.

    c) Edit calendar - Not implemented.

    d) Edit accounts - Remove the tick to restrict the selected user from access to create, edit or delete general ledger accounts (general ledger / bank and tax accounts). This will set the

Setup → Accounts menu option on the Setup ribbon to inactive.

e) Edit debtors - Remove the tick to restrict the selected user from access to create, edit or delete debtor (customer / client) accounts. This will set the Debtors option on the Default ribbon to inactive.

f) Edit creditors - Remove the tick to restrict the selected user from access to create, edit or delete creditor (supplier) accounts. This will set the Creditors option on the Default ribbon to inactive.

4. Stock access type - By default, the access type is set to *'All rights*,' which grants full access to stock items. However, you also have the option to select the '*Warehouse (barcode/weight dish)'* access type. This option is useful when you want to restrict stock access to specific areas such as warehouses or when utilising barcode or weight dish functionality.

5. Link to calendar - Default is User or osFinancials5/TurboCASH5 (as in the resources table).

Multi-User calendar (agenda) - Manual - Shop - Licence : Once-off -

This plugin adds the multi-user agenda (multiple agendas) to the Calendar (Planner). You can add agendas and link them as default to the current user. For every agenda a tab will appear in the agenda Calendar so you can see what the appointments, etc. are on other agendas. You can have a agenda for each employee, salesperson, user, etc. and create invoices directly from his / her agenda with a simple click. Each agenda has it's own calendar and task list.

6. Point-of-Sale - Select the following options for the user if necessary:

a) Mode: This determines the functions available to the user. Select the desired mode for the user:

i) Invoice / Accounting: Allow all functions to the user.

ii) Accounting: Will only allow Accounting functions to the user.

iii) Point-of-Sale: Will allow only Point-of-Sale invoicing functions to the user.

b) Edit price: Remove the tick to restrict the user from editing or changing the selling prices of stock items in Point-of-Sale invoicing.

c) Edit quantity: Remove the tick to restrict the user from editing or changing the quantities of stock items in Point-of-Sale invoicing.

d) Link to salesperson: Select the salesperson from the drop-down list for the user. This allows access only to the selected user for Point-of-Sale invoicing.

7. Custom limitation - All the available menu options are listed for each user. This feature allows you to set custom access levels for specific options. You can select menu options from a list and choose to hide, show, enable, or disable them for the user. A script will be automatically generated for each custom limitation added. This custom limitation settings will only be reflected on the menu items and options when the selected user logs in on the Set of Books.

8. Applying changes: Click on the Apply button to save the changes for the selected user.

9. Setting access levels for other users: If necessary, select the next available user and configure their access options in the same manner.

10. Finalizing changes: Once you have finished setting the access levels for all desired users, click on the Close button to exit the "*Access control*" screen.

Custom limitations

To set the custom limitation for an user:

1. Click on the list to select a feature or menu.



2. Select "*Hide, Show, Enable*" or "*Disable*" from the list.

3. Click on the Add button. The script for the selected custom limitation will be displayed in the text area.



Each selected or added custom limitation is preceded by a semi-colon ; In this example, File indicates that it is an item on the File (Start), and Delete is the Delete (Set of Books) item on the Start ribbon. The option to hide, show, enable or disable the selected menu option, is indicated as follows:

- =H - the menu item will not be displayed.
- =S - the menu item will be displayed.
- =E - the menu item is enabled.
- =D - the menu item is disabled and will be displayed as an inactive menu item.

All functions (options) on the Start ribbon, is as follows:



In this example, the custom options on the Start ribbon, is as follows:



- Online registration and Delete Set of Books is hidden.

- Switch language and Save as options is disabled.

4. Click on the Apply button to save the selection or changes.

Created with the Standard Edition of HelpNDoc: Easy EBook and documentation generator

Access control - Documents tab

This option allows you to set variuos options for document processing. You may customise the access levels for each option by selecting or deselecting them based on your requirements.

For advances users, on the Limit sql tab, limitations for sql could be set for limit documents sql, limit stock sql, disable or limit actions on the document entry screen, limit debtors / creditors and limit layouts. To be advised.

To set documents access options for an user:

1. On the Setup ribbon, click on the Setup → Access control menu. Then, navigate to the Documents tab.



3. Selecting the user: Ensure that the correct user is selected for whom you want to restrict or allow configure document processing options. If needed, click on the User icon to select the desired user.

4. LimitGeneral tab settings: Select the following options based on your requirements:

   a) Documents posting - By default, the Posting and Delete buttons are not available on the Documents grid. Selecting this option allows the user to have access to the Posting and Delete buttons on the Documents grid, enabling them to delete or update (post) documents to the ledger.

> *It's important to note that for the Quotes and Orders document types, the behaviour of the "Posting" button changes. Instead of being labelled as "Posting," it is labelled as "Confirmation." This is because quotes and orders cannot be directly posted or updated to the ledger. They need to be confirmed and converted to invoices (for quotes) or purchases (for orders) before they can be posted.*

b) Auto refresh - To be advised.

c) Interval (sec.) - To be advised.

d) Search for strings - To be advised.

e) Costcenter in doc - By default, the Cost centre feature is not activated for Documents. By selecting this option, you activate the Cost Centre feature for documents. This allows the user to select cost centres when processing sales documents (invoices, credit notes, and quotes) as well as purchase documents (purchases, supplier returns, and orders).

f) Readonly tax - Set tax lookup On/Off - By default, the Tax accounts lookup is displayed when the cursor is in the Tax field of the Document line on the Document entry screen. If you want to deactivate this feature, select (tick) the "*Tax Read-only*" option.

g) Doc no - Select the salesperson from the list. This will use the salesperson or user to generate document numbers when creating new documents.

Activate the General numbers option: Additionally, to enable the generation of document numbers based on general numbering rules, you can activate the "*General numbers*" option in the Setup → Documents setup menu on the Setup ribbon. This option allows you to configure specific numbering patterns and rules for document numbering.

h) Direct edit fields - To be advised.

i) scan print mode - To be advised.

j) Start doc on - By default Invoice is selected and the Invoices document type will be launched when accessing Documents option on the Default ribbon. You may select to launch Quotes, Purchases or Orders document types as the default document type when accessing Documents option on the Default ribbon.

k) Limit discount - This field you may set the values for the limitation of discount when processing documents. You may access the calculator function to perform calculations.

6. Limit sgl tab settings: Click on the Limit sgl tab. To be advised.



7. Set the SQL limitations: Within the "Limit sql" tab, you can configure limitations for document SQL, stock SQL, actions on the document entry screen, debtor/creditor limitations, and layouts. These limitations can be defined based on the user's specific requirements or security considerations.

> *Please note that the specific steps and options for setting these limitations may vary based on the version and configuration of osFinancials5/TurboCASH5 being used. It is recommended to refer to the osFinancials5/TurboCASH5 documentation or consult with the system administrator for detailed instructions on configuring SQL limitations in the application.*

8. Applying changes: Click on the Apply button to save the changes for the selected user.

9. Customising document options for other users: If necessary, select the next available user and configure their options in the same manner.

10. Finalizing changes: Once you have finished setting the access levels for all desired users, click on the Close button to exit the "*Access control*" screen.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Access control - Groups tab

The Groups tab on Access control allows you to restrict access or allow access to specific users for the Groups to be available when accessing the Setup → Groups menu on the Setup ribbon.

By default all reporting groups such as Account group 1, Account group 2, Debtor group 1, Debtor group 2, Creditor group 1, Creditor group 2, Document group 1, Document group 2, Stock group 1, Stock group 2, Cost centre 1, Cost centre 2, Projects, Salespersons, Languages and Payment types will be available.

If you restrict a user from access to a specific groups, the users will not be able to view and add, edit, delete or disable items on these groups.

However users which is restricted to specific groups, which they cannot view and edit will still have the options and functionality to select restricted groups when printing reports and select groups when creating, editing accounts, debtors, creditors, documents and stock items.

To set groups access options for an user:

1. On the Setup ribbon, click on the Setup → Access control menu. Then, navigate to the Groups tab.



2. Selecting the user: Ensure that the correct user is selected for whom you want to restrict or allow access to batches, accounts, and processing options. If needed, click on the User icon to select the desired user.

3. Managing groups access: By default, all reporting groups such as Account group 1, Account group 2, Debtor group 1, Debtor group 2, Creditor group 1, Creditor group 2, Document group 1, Document group 2, Stock group 1, Stock group 2, Cost centre 1, Cost centre 2, Projects, Salespersons, Languages and Payment types are available for all users.

4. Restricting groups access: To restrict a user from accessing specific groups, remove the tick (deselect) from the respective group. This means that the user will not be able to view, add, edit, delete, or disable items within those restricted groups.

You can use the Spacebar on your keyboard to select or deselect an option.

5. Applying changes: Click on the Apply button to save the changes for the selected user.
6. Setting access levels for other users: If necessary, select the next available user and configure their groups access and restrictions in the same manner.
7. Finalizing changes: Once you have finished setting the access levels for all desired users, click on the Close button to exit the "*Access control*" screen.

By customizing the access to groups, you can control the level of permissions and data visibility for different users in osFinancials5/TurboCASH5. Users with restricted access to specific groups will not be able to perform any actions related to those groups, ensuring that they only have access to the necessary data and functionality within the application.

Access to selecting groups for reports

In osFinancials5/TurboCASH5, when you restrict a user from accessing specific groups using the Groups tab in the Access control feature, it means that the user will not be able to view, add, edit, delete, or disable items within those restricted groups. However, they will still be able to select the reporting groups on report options screens when printing reports.

By allowing users to select reporting groups on report parameter screens, they can filter and customize the reports based on their reporting needs, even if they don't have access to perform actions within the restricted groups. This provides flexibility in generating reports while maintaining the necessary restrictions on data manipulation and management within osFinancials5/TurboCASH5.

Access to selecting groups for documents

In osFinancials5/TurboCASH5, if users are restricted to specific Document groups using the Access control feature, they will still be able to filter and search for specific documents within the restricted groups. However, it's important to note that this functionality is subject to the document type permissions set in the Batches access tab of the Setup → Access control menu.

If a user is restricted from accessing or processing certain document types (such as Invoices, Credit Notes, Purchases, or Supplier Returns) in the Batches access tab, they will not be able to filter or search for documents of those restricted document types, even within the restricted Document groups. The document type restrictions in the Batches access tab take precedence over the Document group restrictions.

By carefully managing both Document group access and document type permissions, you can effectively control user access to specific documents and document types in osFinancials5/TurboCASH5, ensuring

users can only work with the documents relevant to their assigned permissions.

Access to selecting groups in various functions

In osFinancials5/TurboCASH5, if users are restricted to specific Account groups, Debtor groups, Creditors groups, or Stock items groups using the Access control feature, they will still have certain capabilities within those restricted groups. Here's how it works for each scenario:

1. Account groups: Users with restricted access to specific Account groups will still be able to select and change the existing account groups when creating or editing ledger accounts (Setup → Accounts menu).
2. Debtor groups: Users with restricted access to specific Debtor groups will still be able to select and change the existing debtor groups when creating or editing debtor accounts. This means they can assign debtors to the available groups. Additionally, they can filter and search for specific debtors within the restricted groups on the Debtors grid.
3. Creditor groups: Similar to debtor groups, users with restricted access to specific Creditors groups will be able to select and change the existing creditor groups when creating or editing creditor accounts. They can assign creditors to the available groups. They can also filter and search for specific creditors within the restricted groups on the Creditors grid.
4. Stock groups: Users with restricted access to specific Stock items groups will retain the ability to select and modify the existing stock item groups when creating or editing stock items. They can assign stock items to the restricted groups. Additionally, they can filter and search for specific stock items within the restricted groups on the Stock items grid.

By allowing these capabilities within the restricted groups, users can still manage and organize debtor accounts, creditor accounts, and stock items effectively, even with limited access to specific groups. This ensures that users can work with the relevant data while maintaining the necessary access controls in osFinancials5/TurboCASH5.

Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Access control - User tabs

User tab ribbon

The User tab ribbon in osFinancials5/TurboCASH5 is a customisable quick menu that allows you to manage

user navigation in up to six (6) groups within a Set of Books. This makes it convenient for users to access their frequently used features.

Activating the Auto-learn feature: The "Auto-learn" feature, when selected (ticked), automatically adds the last accessed options to the User tab ribbon in up to six (6) groups. This makes it convenient for users to access their frequently used features.

Deactivating Auto-learn feature: Once you have populated the User tab ribbon with the desired shortcuts, you can deactivate the "*Auto-learn*" feature by removing the tick from the "*Auto-learn*" field. This ensures that the User tab ribbon retains the manually selected options and doesn't automatically update based on the last accessed features.

Default ribbon: By default, when opening the Set of Books, the Default ribbon is displayed. However, if the User tab ribbon is activated and configured, it will automatically display the User tab ribbon instead of the Default ribbon upon opening the Set of Books.



Manually configure the User tab ribbon: The User tab ribbon may be changed or set manually in the Usertabs tab on the Setup → Access control (Setup ribbon).

Removing Control icons: If any of the Control icons are added, you may remove it from the "User tab". For example, "Do year-end" is only performed once a year, you may select a different feature to replace it, or simply delete it from the list.

By customizing the User tab ribbon, you can streamline user navigation, enhance efficiency, and tailor the interface to match the specific needs and preferences of each user in a Set of Books.

Configure User tab ribbon in Access control

Once you have activated the User tab ribbon in osFinancials5/TurboCASH5 and want to make edits or manually configure its options, you can utilise the Usertabs tab within the Access control feature. This tab allows you to manage the configuration of the User tab ribbon.

To set (change / edit) User ribbon in Access control:

1. On the Setup ribbon, click on the Setup → Access control menu. Then, navigate to the Usertabs tab. This tab allows you to manage the configuration of the User tab ribbon.



2. Selecting the user: Ensure that the correct user is selected for whom you want to create or add the access options on the User tab ribbon. If needed, click on the User icon to select the desired user.

3. Adding a new option to the User tab ribbon:

    - Click in the Add record icon to create a new record. Select a Control option from the available options on the list and select the Group (group 1 to 6).

    - Click on the Save record icon to add the record.

4. Removing an existing option from the User tab ribbon: To remove an existing option from the list, you can select a Control option you wish to remove from the User tab ribbon.

    - Click in the Delete record icon to remove (delete) an existing option.

    - Click on the Save record icon to save the record.

5. Rearranging options: If you want to change the order of the options on the User tab ribbon, you can achieve it by changing the group of the option. Each option is assigned to a specific group, and the order of the groups determines the order in which the options are displayed on the ribbon. This allows you to customize the layout of the ribbon to match your preferred workflow. Click on the Save record icon to save your changes.

6. Applying changes: Click on the Apply button to save the changes for the selected user.

7. Customising User tab ribbons for other users: If necessary, select the next available user and configure their options in the same manner.

8. Finalizing changes: Once you have finished setting the access levels for all desired users, click on the Close button to exit the "*Access control*" screen.

By using the Usertabs tab within the Access control feature, you have the flexibility to customize and fine-tune the User tab ribbon in osFinancials5/TurboCASH5 based on your specific preferences and requirements.

Filter options

The User tab ribbon also provides filter options, allowing you to create filter files, save them, and load them as needed. This helps in managing and organising data based on specific criteria.



Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Access control - Log report

In osFinancials5/TurboCASH5, the log report functionality provides a record of various activities performed within a Set of Books, including the opening and closing of the Set of Books, user logins and logouts, and important functions like reversing posted journals and documents, as well as year-end processes. Here's

how the log report can be useful:

1. Tracking Set of Books activity: The log report allows you to monitor when a Set of Books has been opened or closed. This information helps track the usage and access patterns of the system. It provides an audit trail of when the Set of Books was accessed, which can be valuable for monitoring and ensuring appropriate usage and security.
2. User activity monitoring: The log report also captures user login and logout activities. It records when each user has accessed the Set of Books, allowing you to monitor user activity and identify any unusual or unauthorized access. By reviewing the log report, you can track which users have interacted with the system and when, providing a level of accountability and transparency.
3. Reversal of posted journals and documents: The log report includes information on the reversal of posted journals and reversal of posted documents. This is helpful for tracking the history of corrections or adjustments made to financial transactions. By reviewing the log report, you can identify the specific instances when posted journals or documents were reversed, helping to ensure accuracy and integrity in the financial records.
4. Year-end processes: The log report captures important year-end activities performed in a Set of Books. This includes tasks such as closing the fiscal year, generating financial reports, and performing other year-end procedures. The log report helps document and verify the completion of these critical processes, which are essential for accurate financial reporting and compliance.

Overall, the log report in osFinancials5/TurboCASH5 provides a detailed record of various activities, including Set of Books opening and closing, user logins, reversal of posted transactions, and year-end processes. It serves as an audit trail, helping to monitor system usage, track user activity, and ensure the integrity of financial data. The log report can be a valuable tool for detecting errors, identifying unauthorized access, and promoting transparency and accountability within the accounting system.

Important functions such as Do year end, Reverse posted batch/document (accessed from the Global processes menu list on the Setup ribbon), will also be listed to display the date and type as well as which user performed these important actions.

To print log reports:

1. On the Setup ribbon, click on Setup → Access control.
2. Click on the Log report button. The Report parameters screen will be displayed.
3. Click on the OK button. An example of the "*Userlog report*", is as follows:



Userlog

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no. 336012345
Tax reg. no. 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Log report

Log-on	Log-off	OS user	From PC	User
2021/05/26 12:50:07	2021/05/26 12:51:44	danva	ZED_PC	Dan
2021/05/26 12:52:35	2021/05/26 12:52:55	danva	ZED_PC	Dan
2021/05/26 13:24:23	2021/05/26 17:13:21	danva	ZED_PC	Dan
2021/05/26 19:59:10	2021/05/26 20:03:21	danva	ZED_PC	Dan
2021/05/26 20:03:26	2021/05/27 06:06:16	danva	ZED_PC	Dan
2021/05/27 14:21:42	2021/05/28 05:24:53	danva	ZED_PC	Dan
2021/05/30 08:28:49	2021/05/30 08:54:03	danva	ZED_PC	Dan
2021/05/31 12:41:15	2021/05/31 12:46:53	danva	ZED_PC	Dan
2021/05/31 13:41:30	2021/05/31 13:42:22	danva	ZED_PC	Dan
2021/05/31 13:44:16	2021/05/31 13:44:54	danva	ZED_PC	Dan
2021/05/31 13:49:36	2021/05/31 13:50:52	danva	ZED_PC	Dan
2021/05/31 14:05:02	2021/05/31 14:05:44	danva	ZED_PC	Dan
2021/05/31 14:05:48	2021/05/31 14:11:18	danva	ZED_PC	Dan
Type: REVDOC	Message: Reverse doc!		Date / Time: 2021/05/31 14:06:23	ID: 10102
2021/05/31 14:11:18	2021/05/31 14:11:44	danva	ZED_PC	Dan
Type: OPENYEAR	Message: Open new year!		Date / Time: 2021/05/31 14:11:44	ID: 0
2021/05/31 14:11:49	2021/05/31 15:31:41	danva	ZED_PC	Dan
2021/06/03 04:06:26	2021/06/03 04:07:43	danva	ZED_PC	Dan
2021/06/08 05:20:55	2021/06/08 05:41:35	danva	ZED_PC	Dan
2021/06/09 21:44:02	2021/06/10 06:25:31	danva	ZED_PC	Dan
2021/06/10 16:23:10	2021/06/10 16:23:28	danva	ZED_PC	Dan
2021/06/20 07:58:40	2021/06/20 07:59:50	danva	ZED_PC	Dan
2021/06/23 19:01:15	2021/06/23 19:02:16	danva	ZED_PC	Dan
2021/06/28 14:25:09	2021/06/28 14:53:13	danva	ZED_PC	Dan
2021/08/22 15:10:42	2021/08/22 16:21:23	danva	ZED_PC	Dan
2021/08/22 16:25:39	2021/08/22 16:26:25	danva	ZED_PC	Dan
2021/08/22 16:27:23	2021/08/22 16:44:50	danva	ZED_PC	Dan
2021/08/22 16:58:25	2021/08/22 19:23:31	danva	ZED_PC	Dan
2021/08/22 19:37:43	2021/08/22 19:58:26	danva	ZED_PC	Dan
2021/08/25 19:27:15	2021/08/25 19:39:41	danva	ZED_PC	Dan
2022/04/26 05:10:13		danva	LAPTOP-6LE1L1A	Dan
2021/05/31 12:47:10	2021/05/31 13:40:13	danva	ZED_PC	Tracy
2021/05/31 13:40:17	2021/05/31 13:41:19	danva	ZED_PC	Tracy
2021/05/31 13:42:34	2021/05/31 13:42:45	danva	ZED_PC	Tracy
2021/05/31 13:43:50	2021/05/31 13:44:03	danva	ZED_PC	Tracy
2021/05/31 13:45:13	2021/05/31 13:46:27	danva	ZED_PC	Tracy
2021/05/31 13:46:34	2021/05/31 13:49:22	danva	ZED_PC	Tracy
2021/05/31 13:51:06	2021/05/31 14:03:13	danva	ZED_PC	Tracy
2021/05/31 14:03:17	2021/05/31 14:08:52	danva	ZED_PC	Tracy
2021/05/31 14:08:52	2021/08/22 16:21:54	danva	ZED_PC	Tracy
Type: REVBATC	Message: Reverse batch!		Date / Time: 2021/05/31 14:10:23	ID: 10107
2021/08/22 16:21:54	2021/08/22 16:25:29	danva	ZED_PC	Tracy
2021/08/22 19:23:45	2021/08/22 19:24:00	danva	ZED_PC	Tracy
2021/08/22 19:24:08	2021/08/22 19:25:23	danva	ZED_PC	Tracy
2021/08/22 19:25:27	2021/08/22 19:37:30	danva	ZED_PC	Tracy

Handyman Hardware Store — Printed : 2022/04/26 05:29:04
Data: C:\osfinancials5\Books\MY-COMPANY-ACCESS\books.fdb
System user: danva osFinancials user: Dan — Page: 1 / 1

The "*Log report*" displays the following:

1. Log-on - System date and time an user opens the Set of Books.
2. Log-off - System date and time an user close the Set of Books.
3. OS User - The name of the Windows user (User account).
4. From PC - The name of the computer on which the Set of Books is accessed. This is the Computer name as set in the Windows operating system.

5. User - The name of the User as set in Access control (Setup ribbon).

6. Important functions executed from the Global processes menu (Setup ribbon), will also be listed to display the date and type as well as which user and on which computer these important actions were performed. The Type of actions is as follows:

    a) OPEN YEAR - Open new year (Do year end).

    b) REVBATC - Reverse posted batch - *Reverse batch! and the Batch ID.*

    c) REVDOC - Reverse posted document - *Reverse doc! and the Batch ID.*

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Budgets

A budget is a financial plan that outlines expected income and expenses over a specific period of time, usually one year. It is a tool that helps individuals, businesses, and organizations to allocate resources efficiently and effectively by estimating the amount of money they expect to receive and the amount they plan to spend.

Budgets can be created for different purposes, such as managing personal finances, planning business operations, or organizing a project. They typically include an estimation of revenues, which may include salaries, sales, investments, or other sources of income, as well as an estimation of expenses, which may include rent, utilities, supplies, equipment, marketing, and other costs.

The main goal of a budget is to ensure that expenses do not exceed revenues and that financial goals are achieved. By tracking actual spending against budgeted amounts, individuals and organizations can adjust their plans and make informed decisions about where to allocate resources.

The budget feature is used to enter and edit budget figures in osFinancials5/TurboCASH5, which can be compared with actual income and expenses. Budgets are a guide as to what you want to achieve; for instance what income you expect to generate (sales forecasts and income from other sources) and a plan for your expenses you need to incur to achieve that income. Budget figures can be flexible so as to take into account seasonal trends in business.

The following new features have been added:

1. *Budget figures may be entered, adjusted or processed in the Budgets option on the Reports ribbon. This is in addition to the standard option to process budgets in Setup → Accounts (Setup ribbon).*

2. *The Pivot feature is introduced to analyse your Budget figures.*
3. *Budgets may be entered for any of the periods or financial years.*
4. *Budgets may be entered for a specific date - e.g. Expected once off purchases or a specific big sale, etc.*
5. *Budgets may be copied from Budget figures from the previous year.*
6. *Budgets may be copied from Actual figures from the previous year.*
7. *Budgets may be entered for Cost centres (Cost centre 1 and/or Cost centre 2), if activated.*
8. *Budgets may be entered for Projects, if activated.*

Budget figures will be displayed on the following reports (Reports ribbon):

1. Ledger analyser 1 /2:
    - Budget option for the Trial balance, Income statement, Balance sheet and Standard column balances report types. The Pivot feature is introduced to analyse your Budget figures.
    - Budget vs actual report type.
2. T-Account viewer - List the Budget figures (for all accounts or specific accounts), as entered or processed in the Budgets (Reports ribbon); or on Setup → Accounts (Setup ribbon), in the T-Account viewer. You may print these budget figures and export the budget figures in T-Account viewer to a spreadsheet.
3. Ledger - Budget vs Actual (3 periods).
4. Optional (if activated):
    - Cost centres - If Cost centres are activated and Budget figures may be entered, adjusted or processed.
    - Projects - If Projects are activated and Budget figures may be entered, adjusted or processed.

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Enter budget figures (Setup - Accounts)

To enter / change your Budget figures:

1. On the Setup ribbon, select Setup → Accounts.

2. Select the account to enter the budget figures.



3. Select the first account, i.e. "*Sales*" and enter the budget figure. Enter the annual amount of *–120 000* in the "*Total Amount"* field and click on the Set period budget button.

> *For a credit amount, insert minus sign "–". The credit amount will be indicated with a minus sign after the amount (e.g. 10,000.00– in the "Amount" column.*
>
> *For a debit amount just insert the annual amount without the minus sign "–". The amount will automatically be divided this amount into 12 months in the "Amount" field.*

> *Each month can be overwritten so that the budget can be flexed month by month to accommodate seasonal trends and spending patterns of your business. The system will keep a running total for you, so that as you are flexing the monthly budget, you can see the effect on the annual amount.*
>
> *Budget figures can also be entered for for Balance sheet accounts (Capital, Liabilities and Assets), which may be used as a guideline to control the balances on these accounts.*
>
> *See - Enter budget figures for special events.*

3. Click on the Save button (next to the account description field).

If budget figures already exist for the account, and you click on the Save button, a similar confirmation message will be displayed:

"Delete old budget for year 2022?"

Click Yes to replace the existing budget figures.

If you do not click on the Save button, any budget figures entered, or changed, will not be saved.

4. Select the next account and enter the budget figure.
5. Continue to enter your budget figures for all accounts.
6. When you are finished entering all your budget figures, click on the Close button (on the titlebar).

Created with the Standard Edition of HelpNDoc: Easily Add Encryption and Password Protection to Your PDFs

Enter budget for special events (Setup - Accounts)

Each month can be overwritten so that the budget can be flexed month by month to accommodate seasonal trends and spending patterns of your business. The system will keep a running total for you, so that as you are flexing the monthly budget, you can see the effect on the annual amount.

You may enter budget figures for specific dates and/or periods. For example, if you need to budget 5,000.00 for a special event, on 1 May 2024 - extra sales for a special promotion sale, you may add that.

To enter budget figures for special events:

1. On the Setup ribbon, select Setup → Accounts.



2. Select the "*Sales*" account. On the Budget tab, click on the button to create a new record.

3. The system date will automatically be displayed. Enter or select the date (i.e. "*2024/05/01*") for the special event.

4. Enter the amount for the budget (i.e. "*–5000*") in die "*Amount*" column.

> *For a credit amount, insert minus sign "–". The credit amount will be indicated with a minus sign after the amount (e.g. 5,000.00– in the "Amount" column.*
>
> *For a debit amount just insert the amount without the minus sign "–". The amount will automatically be divided this amount into 12 months in the "Amount" field.*

5. Enter the reference (e.g. "*Sale*") in the "*Reference*" column.

6. Enter the description (e.g. "*Special promotion*") in die "*Description*" column.

7. Click on the button to save the new budget for "*2024/05/31*".

8. Click on the Save button.

> *If you do not click on the Save button, any budget figures entered, or changed, will not be saved.*

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Budgets (Reports ribbon)

The following new features have been added:

1. *Budget figures may be entered, adjusted or processed in the Budgets option on the Reports ribbon. This is in addition to the standard option to process budgets in Setup → Accounts (Setup ribbon).*
2. *The Pivot feature is introduced to analyse your Budget figures.*
3. *Budgets may be entered for any of the periods or financial years.*
4. *Budgets may be entered for a specific date - e.g. Expected once off purchases or a specific big sale, etc.*
5. *Budgets may be copied from Budget figures from the previous year.*
6. *Budgets may be copied from Actual figures from the previous year.*
7. *Budgets may be entered for Cost centres (Cost centre 1 and/or Cost centre 2), if activated.*
8. *Budgets may be entered for Projects, if activated.*

To process your Budget figures:

1. On the Reports ribbon, select Budgets. The Budget tab will be displayed.
2. Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include budget figures. Select the period “Year” (i.e. “*2024/03/01*” to “*2025,/02/28*") to enter your budget figures for the selected period.



3. Click on the Refresh button to populate the accounts and periods. This will list all the existing ledger accounts in your "*Chart of accounts*" (existing as added, edited in the Setup → Accounts (Setup ribbon)), in the Account code sequence.

> *If you already have existing budget figures in the previous year, you may use the "Copy – From Budget Previous year" option.*
>
> *If you have already posted transactions in batches and documents in the previous year, you may use the "Copy – From Actual Previous year" option to use the transaction totals as basis for your budget.*

4. Reference – The default is "*BUDG*". You may enter your own reference, up to 15-characters, in this field. For the purposes, of this example, leave as is.

> *Options*
>
> 1. *Cost centre 1 - Budgets may be entered for Cost centres (Cost centre 1), if activated.*
> 2. *Cost centre 2 - Budgets may be entered for Cost centres (Cost centre 2), if activated.*
> 3. *Projects - Budgets may be entered for Projects, if activated.*
> 4. *Percentage - Tick this option and specify a percentage to adjust the budget figures.*
> 5. *Delete all - If any budget figures exists, a confirmation message will be displayed.*
>
> > "Delete data for this period?"
>
> *If you click Yes, the budget figures for the selected period or dates will be deleted.*
>
> 6. *Copy -*
>
> a) *From Budget Previous year - If you already have budget figures for the previous*

financial year, select this option to populate last year's budget figures.

b) *From Actual Previous year - If you already have posted batch and document transactions for the previous financial year, select this option to populate last year's the actual totals of posted transactions.*

7. *Apply to selection - Add amount to selection?If you key in a value (amount or percentage), and you click the Apply to selection button, a confirmation message will be displayed:*

" Add amount to selection?"

Click Yes to change the amount or percentage. The value (amount or percentage) will increase or decrease any existing values.

You may enter or overtype an amount. Editing an amount, e.g. editing one or more digits will produce an error message, for example;

'-13,000.00' is not a valid floating point value for field '2024/06/01 - 2024/06/30'

5. Description – The default is "*Auto budget*". You may enter your own description (up to 35 characters), in this field. Enter "*Budget 2024/2025*".

6. Select the first account, i.e. "*Sales*" and enter the monthly budget amount, i.e. –10,000 in die amount field (before the Apply to selection button) in.

The " - " (minus sign), added before the amount, indicates a credit budget amount. For a debit budget amount, add the amount without the " - " (minus sign).

7. Select the months for which you need to add the budget figures.

To select multiple periods, press the "Shift" key on your keyboard and click on the periods to select the months.

8. Click on the Apply to selection button. A confirmation message is displayed:

"Add amount to selection?"

9. Click Yes to add the monthly budget figures to the selected months.

10. Repeat this process to add your budget figures.

11. After adding your budget figures for the accounts in this documentation, the "*Budgets*" screen should display as follows:



Code	Name	2024/03/01	2024/04/01	2024/05/01	2024/06/01	2024/07/01	2024/08/01	2024/09/01	2024/10/01	2024/11/01	2024/12/01	2025/01/01	2025/02/01	Total 2024/03/01 - 2025/02/28
010000	Sales	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-120,000.00
100000	Cost of sales	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	48,000.00
200000	Bank charges	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	480.00
205000	Depreciation	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	600.00
210000	Motor vehicle expenses													
210010	Motor vehicles - Fuel & oil	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	1,200.00
210020	Motor vehicles - Maintenance	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	1,800.00
210030	Motor vehicles - Repairs	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	2,400.00
215000	Maintenance of tools													
220000	Rent	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	6,600.00
225000	Salaries and wages	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	6,000.00
230000	Stationery	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	120.00
235000	Sundry expenses													
505000	Capital													
44		-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-52,800.00

Do not enter any budget figures for the main accounts. In this example, Budget figures were not entered for the Main account "Motor vehicle expenses", but for each sub-account.

12. After finishing to process your budget figures, you may click on the Transaction details tab or Pivot tab view and explore the generated budget figures.

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Budgets - Budget tab (Reports ribbon)

To process your Budget figures:

1. On the Reports ribbon, select Budgets. The Budget tab will be displayed.

2. Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include budget figures.



Code	Name	2024/03/01	2024/04/01	2024/05/01	2024/06/01	2024/07/01	2024/08/01	2024/09/01	2024/10/01	2024/11/01	2024/12/01	2025/01/01	2025/02/01	Total 2024/03/01 - 2025/02/28
010000	Sales	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-120,000.00
100000	Cost of sales	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	48,000.00
200000	Bank charges	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	480.00
205000	Depreciation	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	600.00
210000	Motor vehicle expenses													
210010	Motor vehicles - Fuel & oil	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	1,200.00
210020	Motor vehicles - Maintenance	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	1,800.00
210030	Motor vehicles - Repairs	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	2,400.00
215000	Maintenance of tools													
220000	Rent	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	6,600.00
225000	Salaries and wages	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	6,000.00
230000	Stationery	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	120.00
235000	Sundry expenses													
505000	Capital													
44		-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-52,800.00

3. Refresh - This button will populate the Budget figures for the selected period or selected dates.

4. Cost centre 1 - Budgets may be entered for Cost centres (Cost centre 1), if activated.

5. Cost centre 2 - Budgets may be entered for Cost centres (Cost centre 2), if activated.

6. Projects - Budgets may be entered for Projects, if activated.

7. Reference - "*BUDG*" is the default reference. You may enter your own reference (up to 15 characters).

8. Description - "*Auto budget*" is the default description. You may enter your own description (up to 35 characters).

9. Percentage - Tick this option and specify a percentage to adjust the budget figures.

10. Delete all - If any budget figures exists, a confirmation message will be displayed.

    "Delete data for this period?"

    If you click Yes, the budget figures for the selected period or dates will be deleted.

11. Copy -

    a) From Budget Previous year - If you already have budget figures for the previous financial year, select this option to populate last year's budget figures.

    b) From Actual Previous year - If you already have posted batch and document transactions for the previous financial year, select this option to populate last year's the actual totals of posted transactions.

12. Apply to selection - Add amount to selection?

You may enter or overtype an amount. Editing an amount, e.g. editing one or more digits will produce an error message, for example;

" '-13,000.00' is not a valid floating point value for field '2024/06/01 - 2024/06/30' ".

Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Budgets - Enter budget figures for special events

In this example, on 1 May 2024 we need to budget 5,000.00 extra sales for a special promotion. You may enter budget figures for specific dates and/or periods to accommodate, for example, special events, fluctuations and business patterns.

To enter budget figures for special events:

1. On the Reports ribbon, select Budgets.



Code	Name	2024/03/01	2024/04/01	2024/05/01	2024/06/01	2024/07/01	2024/08/01	2024/09/01	2024/10/01	2024/11/01	2024/12/01	2025/01/01	2025/02/01	Total 2024/03/01 - 2025/02/28
010000	Sales	-10,000.00	-10,000.00	-15,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-125,000.00
100000	Cost of sales	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	48,000.00
200000	Bank charges	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	480.00
205000	Depreciation	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	600.00
210000	Motor vehicle expenses													
210010	Motor vehicles - Fuel & oil	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	1,200.00
210020	Motor vehicles - Maintenance	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	1,800.00
210030	Motor vehicles - Repairs	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	2,400.00
215000	Maintenance of tools													
220000	Rent	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	6,600.00
225000	Salaries and wages	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	6,000.00
230000	Stationery	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	120.00
235000	Sundry expenses													
505000	Capital													
44		-4,400.00	-4,400.00	-9,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-57,800.00

2. Period – Select the period "*Year*" (i.e. "*2024/03/01*" to "*2025/02/28*") to enter your budget figures for the selected period.

3. Click on the Refresh button. This will list all the existing ledger accounts in your "*Chart of accounts*" (existing as added, edited in the Setup → Accounts (Setup ribbon)), in the Account code sequence.

4. Select the "*Sales*" account and the month "*2024/05/01*" - May 2024.

5. Reference – The default or previous reference entered, will be displayed, for example, "*BUDG*". Enter "*BUDGET SALE*" to indicate that it is a sales event that is scheduled for May 2024; or that took place in

May 2024.

6. Description – The description as previously entered, is "*Budget 2024/2025*". Enter "*Budget 2024/2025 – Sale*".
7. Only enter the additional amount with which you need to increase the budget for May 2024.
8. To increase the existing amount for May 2024 from –10,000 to –15000, only enter –5000 in the amount field (before the Apply to selection button).

> *The " - " (minus sign), added before the amount, indicates a credit budget amount. For a debit budget amount, add the amount without the " - " (minus sign).*

> *In the case of Sales and trading stock items, is applicable, you may need to change the "Cost of of sales" account.*

9. Click on the Apply to selection button. A confirmation message , is displayed:

"Add amount to selection?"

10. Click Yes to save the increased budget figure for May 2024.

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

Budgets - Transactions details tab (Reports ribbon)

The Transaction details tab lists all the budget records for the selected periods or dates selected on the options section of the Budget tab.

You may overtype any amount, add or edit references and descriptions, as necessary.



id	Name	Date	Reference	Description	Amount	User	Change date	Project	Cost centre	Cost centre
1	Sales	2024/03/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:31		No group	
2	Sales	2024/04/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:34		No group	
4	Sales	2024/06/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:34		No group	
5	Sales	2024/07/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:34		No group	
6	Sales	2024/08/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:34		No group	
7	Sales	2024/09/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:34		No group	
8	Sales	2024/10/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:35		No group	
9	Sales	2024/11/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:35		No group	
10	Sales	2024/12/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:35		No group	
11	Sales	2025/01/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:35		No group	
12	Sales	2025/02/01	BUDGET	Budget 2024/2025	-10,000.00		2024/12/12 18:07:35		No group	
121	Sales	2024/05/01	BUDGET SALE	Budget 2024/2025 - Sale	-15,000.00		2024/12/12 18:15:52		No group	
13	Cost of sales	2024/03/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:25		No group	
14	Cost of sales	2024/04/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:28		No group	
15	Cost of sales	2024/05/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:28		No group	
16	Cost of sales	2024/06/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:29		No group	
17	Cost of sales	2024/07/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:29		No group	
18	Cost of sales	2024/08/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:29		No group	
19	Cost of sales	2024/09/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:29		No group	
20	Cost of sales	2024/10/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:29		No group	
21	Cost of sales	2024/11/01	BUDGET	Budget 2024/2025	4,000.00		2024/12/12 18:08:29		No group	
	120				-57,800.00					

The details of the columns, is as follows:

1. id - The ID or record ID is automatically generated for each budget entry.
2. Name - Account name or description
3. Date - The date for the period of the budget entry.
4. Reference - The default Reference "*BUDG*" or your reference as entered on the options section of the Budget tab.
5. Description - The default Description "*Auto budget*" or your description as entered on the options section of the Budget tab.
6. Amount - The amount for the budget entry. The total debit amounts an credit amounts (prefixed by a - (minus sign)) will be listed.
7. User - If Users were added in Setup → Access control (Setup ribbon), the name of the user or users will be listed.
8. Change date - The date and timestamp on which the budget amount is entered or changed.
9. Project - If budgets were entered or processed for Projects, the project code will be listed. You may select a different Project code, if required.
10. Cost centre 1 - If budgets were entered entered for Cost centres (Cost centre 1), the Cost centres for Cost centre 1 will be listed. You may select a different Cost centre 1 code, if required.
11. Cost centre 2 - If budgets were entered entered for Cost centres (Cost centre 2), the Cost centres for Cost centre 2 will be listed. You may select a different Cost centre 2 code, if required.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring

Tool

Budgets - Pivot tab (Reports ribbon)

The Pivot tab, by default, summarises the budget totals for the Income and Expense (Income statement) accounts and Capital, Assets and Liabilities (Balance sheet) accounts for which budget figures were entered for the selected period or dates.



Click on the ⊞ icon to list the budget totals for the accounts. The icon will change ⊟ to list totals for each account for which budget figures are entered.



The expanded view of the budget should display as follows:



The default filter options, which may be selected as needed, is structured on the Pivot screen in four (4) areas, "*Filter Area, Column Area, Row Area*" and "*Data Area*". The filter options is as follows:

Filter Area:



1. Reference - The default Reference "*BUDG*" or your reference as entered on the options section of the Budget tab. Select the available reference(s) on the list as filter options, as required.
2. Description - The default Description "*Auto budget*" or your description as entered on the options section of the Budget tab. Select the available description(s) on the list as filter options, as required.
3. Job code - (Projects) - If budgets were entered or processed for Projects, the project code(s) may be selected as filter options.
4. Group 1 - If budgets were entered entered for Cost centres (Cost centre 1), the Cost centres for Cost centre 1 may be selected as filter options.
5. Group 2 - If budgets were entered entered for Cost centres (Cost centre 2), the Cost centres for Cost centre 2 may be selected as filter options.

Data Area:

6. Amount - The total debit amounts a credit amounts (prefixed by a - (minus sign)) will be listed. Select the available amount(s) on the list as filter options, as required.
7. Income expense - The options is as follows:
   - True = Income and Expense (Income statement) accounts. The totals of the Income and Expense (Income statement) accounts will be displayed as True Total.
   - False = Capital, Assets and Liabilities (Balance sheet) accounts. The totals of the Capital, Assets and Liabilities (Balance sheet) accounts will be displayed as False Total.
8. Account - All accounts will be listed by Account code and description. Select the available account(s) on the list as filter options, as required.

Column Area:

9. Year - The budget totals will be listed for each calendar year. For example, if your financial year starts on 1 January 2020 and ends on 31 December 2020, only one (1) financial year will be listed, i.e. 2020. In this example the financial year starts on 1 March 2020 and ends on 28 February 2021, the totals will be listed for 2020 and 2021. Select the year on the list as filter options, as required.
10. Month - Period 0 to 12 will be listed if your Reporting dates are set for a 12 periods (Setup → Reporting dates (Setup ribbon), the period numbers will be listed. Select the period (month) on the list as filter options, as required.
11. Date - All the dates for the selected period or dates selected on the options section of the Budget tab, will be listed. Select the available date(s) on the list as filter options, as required.

Hide Pivot grid fields

Select a Pivot grid field, right-click, and select "*Hide*" on the context menu. The selected Pivot grid field will be removed from the grid. For example, if you do not use Projects, you may click on the "Job code" pivot grid field, and select "*Hide*" on the context menu to remove "*Job code*" from the Pivot Filter Area.



If you do not use Cost centres, you may hide "Group 1" for Cost centre 1 and select the "Hide" option on the context menu. To hide Cost centre 2, you may repeat the process for "Group 2" to hide Cost centre 2.

The removed Pivot grid fields will not be displayed on the "*Filter area*" of the Pivot grid, but will be added to a list in the "*Drag fields to the pivot grid*" on the "*PivotGrid Field List*" screen.

Add hidden Pivot grid fields

If a Pivot grid field is removed accidentally, you may add the Pivot grid field again.

To do this, right-click on the "*Filter Area*" and select the "*Show Field List*" option on the context menu. This will launch the "*PivotGrid Field List*" screen. On the "*Drag fields to the pivot grid*" list, select the field and drag it to the "*Filter Area*" list. You may also drag it straight onto the "*Filter Area*" of the Pivot screen itself.



Order (sequence) of columns

To arrange the sequence of Pivot grid fields, you may select a Pivot grid field, right-click, and select the following options from the "*Order*" option the context menu:

1. Move to Beginning - Move to the first Pivot grid field.
2. Move to End - Move to the last Pivot grid field.
3. Move Left - Move the selected Pivot grid field before the previous Pivot grid field to the left.
4. Move Right - Move the selected Pivot grid field after the next Pivot grid field to the right.

You may use your mouse to drag a selected Pivot grid field to the right or left to your required position.



Filters

Right-click on the Filter Area, Data Area or Column Area to access the "*Show Field List*" or the "*Show Prefilter Dialog*" options.

PivotGrid Field List



The "*PivotGrid Field List*" lists the available Pivot grid fields not displayed on the default Pivot table view. You select an available field on the list and add them to the four (4) areas (i.e. Data Area, Filter Area, Column Area or the Row Area) of the Pivot table.

You may click on the Prefilter option on a column list or click on the Prefilter button to:

1. Make a filter (add or delete conditions and groups).
2. Save a filter.
3. Open a filter.

Make a Custom Filter

To make a filter:

1. Click on the Prefilter option on a column list or click on the Prefilter button.

2. Select an operator (i.e. and, or, and not, or not).
3. Click on the Filter button (or on the ... button) and select one of the following options on the context menu:
    a) New condition
    b) New group
    c) Delete row (If you click on the Filter button, you may delete all rows (conditions and groups)).
4. Select a column from the list of available data applicable to the screen. In this example, the Date is selected.
5. Select a filter condition. If the Between option is selected, another field is opened to select another date.
6. Once you have created your conditions or groups, click on the Apply button.
7. Click on the OK button to close and exit this Make filter screen.

Conditions



1. Equal to - list or display all values which is the same as the specified value.
2. Not equal to - list or display all values which is not the same as the specified value.
3. Less than - list or display all values smaller than the specified value.
4. Less than or equal to - list or display all values smaller or equal to the specified value.
5. Greater than - list or display all values greater than the specified value.
6. Greater than or equal to - list or display all values greater or equal to the specified value.
7. is null - excludes any value entered, will not be listed or displayed.
8. is not null - is not zero - any value which is not equal to zero will be listed or displayed.
9. Between - Specify specific values, etc. to include only matching values.

10. Not between - Specify specific values, etc. to exclude values.

11. in - In a specified value.

12. Not in - Not in a specified value.

If a Date for a column condition is selected, additional conditions will be available (i.e. is this month, is this year, is next 7 days, is next week, is next 14 days, is next two weeks, is next 30 days, is next month, is future, is this week, is yesterday, is today, is last 7 days, is last week, is last 14 days, is last two weeks, is last 30 days, is last month, is last year, is past, is this week, etc.

Save Custom Filter Files

To Save a Custom Filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Save as... button. The "*Save active filter as*" screen will be displayed.

2. Select a Directory in which you wish to save the custom filter file.

3. Enter a file name.

4. Click on the Save button to save the Filter in a (*.*flt*) Filter file format. You may then at any later stage open the saved *.flt file.

Open Custom Filter Files

To Open a Saved a Custom Filter file:

1. Once you have sorted or filtered your data with the Make filter utility, click on the Open... button. The "*Open saved filter as*" screen will be displayed.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Budgets - Pivot - Ledger analyser

To view the budget figures in the Pivot view in the Ledger analyser:

1. On the Ledger analyser 1 or Ledger analyser 2,

2. Select the Trial balance, Income statement, Balance sheet or Standard column balances report types. In this example, Income statement the report type is selected.

3. Select (tick) the Budget option.

4. Select the Period or dates on the Free selection tab. In this example, the year from 1 March 2024 to 28 February 2025 is selected.

5. Click on the Report button.



Buttons 11 to 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

6. Click on the Pivot button.

You may use right-click in any area of the report to launch the context menu:



- *Show details - Launch the T-Account viewer for a selected account.*
- *Show pivot - Launch the Pivot feature based on the selected report options.*

7. The budget figures for the selected period is displayed:



You may click on any graph to display the graph for the next available data level fields.

The cursor will be displayed as a magnifying glass and move to the next dataset. In this example, "Date" is selected.



Move over graph area will display the values, e.g. "Credit for 2022/05/01 is 15000"

8. Click on the icon to Profit loss to list the budget totals for the account types (e.g. Income and Expenses financial categories for the selected period or dates. The icon will change to list totals for each financial category (i.e. Income and Expenses).

You may right-click to launch the context menu, and select the following options:



9. Once all the available columns are expanded, the Budget for the financial year should be displayed as follows:



Account type	Account group 1	Acc	Account na	March	April	May	June	July	August	Septe...	October	Novem...	Decem...	2022 Total	January	February	2023 Total	Grand Total
Proffit loss	Expenses	200000	Bank charges	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	400.00	40.00	40.00	80.00	480.00
		205000	Depreciation	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	500.00	50.00	50.00	100.00	600.00
		210010	Fuel and oil	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	1000.00	100.00	100.00	200.00	1200.00
		210020	Maintenance	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	1500.00	150.00	150.00	300.00	1800.00
		210030	Repairs	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	2000.00	200.00	200.00	400.00	2400.00
		220000	Rent	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	5500.00	550.00	550.00	1100.00	6600.00
		225000	Salaries and w...	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	5000.00	500.00	500.00	1000.00	6000.00
		230000	Stationery	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	100.00	10.00	10.00	20.00	120.00
	Expenses Total			1600.00	1600.00	1600.00	1600.00	1600.00	1600.00	1600.00	1600.00	1600.00	1600.00	16000.00	1600.00	1600.00	3200.00	19200.00
	Income	010000	Sales	-10000.00	-10000.00	-15000.00	-10000.00	-10000.00	-10000.00	-10000.00	-10000.00	-10000.00	-10000.00	-105000.00	-10000.00	-10000.00	-20000.00	-125000.00
		100000	Cost of sales	4000.00	4000.00	4000.00	4000.00	4000.00	4000.00	4000.00	4000.00	4000.00	4000.00	40000.00	4000.00	4000.00	8000.00	48000.00
	Income Total			-6000.00	-6000.00	-11000.00	-6000.00	-6000.00	-6000.00	-6000.00	-6000.00	-6000.00	-6000.00	-65000.00	-6000.00	-6000.00	-12000.00	-77000.00
Proffit loss Total				-4400.00	-4400.00	-9400.00	-4400.00	-4400.00	-4400.00	-4400.00	-4400.00	-4400.00	-4400.00	-49000.00	-4400.00	-4400.00	-8800.00	-57800.00

Default filter options

The default filter options, is as follows:

1. Transaction id - The transaction id is automatically added for posted transactions in batches and documents as well as budget entries.
2. Cost group 1 - If budgets were entered entered for Cost centres (Cost centre 1), the Cost centres for Cost centre 1 may be selected as filter options.
3. Cost group 2 - If budgets were entered entered for Cost centres (Cost centre 2), the Cost centres for Cost centre 2 may be selected as filter options.
4. Account group 2 - The groups set for Account group 2 in Setup → Groups (Setup ribbon) and linked to Accounting group 2 in Setup → Accounts (Setup ribbon).
5. Date / week - The number of the week (from 1 to 53).
6. Debit - The debit amounts.
7. Credit - The credit amounts.
8. Batch id - The batch id is auto generated for posted transactions in batches and documents. In the case of Budgets, the Batch id is "0" (zero).
9. Reference - The default Reference "*BUDG*" or your reference as entered on the options section of the Budget tab. Select the available reference(s) on the list as filter options, as required.
10. Transaction description - The default Description "*Auto budget*" or your description as entered on the options section of the Budget tab. Select the available description(s) on the list as filter options, as required.
11. Balance account - The values, are as follows:
    - 0 = Income and Expense (Income statement) accounts.
    - 1 = Ledger accounts set as Balance sheet account type. These Capital, Assets and Liabilities accounts are reported on the Balance sheet.
12. Amount - The total debit amounts an credit amounts (prefixed by a - (minus sign)) will be listed. Select the available amount(s) on the list as filter options, as required.
13. Income expense - The options is as follows:
    - True = Income and Expense (Income statement) accounts. The totals of the Income and Expense (Income statement) accounts will be displayed as True Total.

- False = Capital, Assets and Liabilities (Balance sheet) accounts. The totals of the Capital, Assets and Liabilities (Balance sheet) accounts will be displayed as False Total.

14. Account - All accounts will be listed by Account code and description. Select the available account(s) on the list as filter options, as required.

15. Year - The budget totals will be listed for each calendar year. For example, if your financial year starts on 1 January 2022 and ends on 31 December 2022, only one (1) financial year will be listed, i.e. 2022. In this example the financial year starts on 1 March 2022 and ends on 28 February 2023, the totals will be listed for 2022 and 2023. Select the year on the list as filter options, as required.

16. Month - Period 0 to 12 will be listed if your Reporting dates are set for a 12 periods (Setup → Reporting dates (Setup ribbon), the period numbers will be listed. Select the period (month) on the list as filter options, as required.

17. Date - All the dated for the selected period or dates selected on the options section of the Budget tab, will be listed. Select the available date(s) on the list as filter options, as required.

Change sequence add / remove Pivot grid fields

Hide Pivot grid fields

Select a Pivot grid field, right-click, and select Hide on the context menu. The selected Pivot grid field will be removed from the grid. For example, If you do not use Cost centres, You may hide Cost group 1 and Cost group 2.



Order

You may select a Pivot grid field, right-click, and select the following options on the context menu:

1. Move to Beginning - Move to the first Pivot grid field.
2. Move to End - Move to the last Pivot grid field.
3. Move Left - Move the selected Pivot grid field before the previous Pivot grid field to the left.
4. Move Right - Move the selected Pivot grid field after the next Pivot grid field to the right.

You may use your mouse to drag a selected Pivot grid field to the right or left to your required position.



Filters

Right-click to access the "*Show Field List*" or the "*Show Prefilter Dialog*" options.



PivotGrid Field List

Pivot grid fields



Show Prefilter Dialog

The "*Prefilter Dialog*" allows you to create custom filters for the Pivot.



Customise the graphs

Graph types

You may select the one of the following diagrams to view the graph.



Series

By default, only the Amount and Debit and Credit amount is displayed.

You may remove the tick of the series or add a tick to a series. For example, if you wish to see only the Debit and Credit amounts, tick these options; and if you do not wish to view the Amount, remove the tick.



Sort by: select the options in the series to change the sequence in which the data in the graph will be displayed.

Data groups

Data groups is empty.

Options

You may change the default values for the "*Legend, Title, Toolbox*" and "*Other (Value Hints)*" according to your requirements.



Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Budget listing reports

The "*Budget*" option, if selected, will list only the budget figures (Budget listing) in the Trial balance, Income statement, Balance sheet and Standard column balances report types.

Budget listing - Income statement options

To view and analyse budget listing:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the Trial balance, Income statement, Balance sheet or Standard column balances report types. In this example, Income statement the report type is selected.
3. Select the "*Budget*" option (tick).



Buttons 11 to 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

4. Select the period on the Per period tabs. You may click on the Free selection tab to select a specific date or a range of dates to include budget figures in the report.
5. Click on the Report button to refresh and generate the budget figures.
6. Click on the Print button.

Printed : Budget listing - Income statement

An example of the "*Budget listing*" in the "*Income statement*", is as follows:



	Totals Debit	Credit	Debit	Credit
REPORTING GROUP ROOT		57,800.00		
Income		77,000.00		
010000 Sales				125,000.00
100000 Cost of sales			48,000.00	
Expenses	19,200.00			
200000 Bank charges			480.00	
205000 Depreciation			600.00	
210000 Motor vehicle expenses	5,400.00			
210010 Motor vehicles - Fuel & oil			1,200.00	
210020 Motor vehicles - Maintenance			1,800.00	
210030 Motor vehicles - Repairs			2,400.00	
220000 Rent			6,600.00	
225000 Salaries and wages			6,000.00	
230000 Stationery			120.00	
	Totals		67,200.00	125,000.00
	Net profit		67,200.00	125,000.00
				57,800.00

If any of these budget figures need some adjustment, go to Budgets (Reports ribbon) or Setup → Accounts - Budget tab (Setup ribbon); select the applicable accounts and edit or enter or delete the figures, as necessary.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Budget performance reports

Budget performance reports

Printing the Budget vs actual report

This report will display the following:

1. Trial balance - The actual figures on the Trial balance - totals of transactions as posted (updated to the ledger) in batches (journals), sales documents (i.e. Invoices, Point-of-Sale Invoices and Credit notes) and purchase documents (i.e. Purchases and Supplier returns).
2. Budget - Once any budget figures are entered or edited (and saved), these figures will automatically

be updated to the applicable accounts and will be available in the Ledger analyser and any reports which supports budget figures.

3. Difference - The difference amount actual trial Trial balance vs the Budget figures.
4. Percentage - The difference expressed as a percentage.

To print a budget vs actual report:

1. On the Reports ribbon, select Ledger analyser 1 or 2.
2. Select the "*Budget vs actual*" report type. This option is available for the Income / Expenses, Trial balance and Balance sheet report type.



Code	Name	Trial balance		Budget		Difference	%
G010000	Sales	0.00	17,500.00	0.00	125,000.00	-107,500.00	14.00
G100000	Cost of sales	4,500.00	0.00	48,000.00	0.00	43,500.00	9.38
G200000	Bank charges	45.00	0.00	480.00	0.00	435.00	9.38
G205000	Depreciation	150.00	0.00	600.00	0.00	450.00	25.00
G210010	Motor vehicles - Fuel & oil	150.00	0.00	1,200.00	0.00	1,050.00	12.50
G210020	Motor vehicles - Maintenance	810.00	0.00	1,800.00	0.00	990.00	45.00
G210030	Motor vehicles - Repairs	1,200.00	0.00	2,400.00	0.00	1,200.00	50.00
G220000	Rent	500.00	0.00	6,600.00	0.00	6,100.00	7.58
G225000	Salaries and wages	0.00	0.00	6,000.00	0.00	6,000.00	100.00
G230000	Stationery	240.00	0.00	120.00	0.00	-120.00	200.00
G505000	Capital	0.00	5,000.00	0.00	0.00	5,000.00	100.00
G600010	Furniture & fittings @ cost	3,800.00	0.00	0.00	0.00	-3,800.00	100.00
G600020	Furniture & fittings - Accumulated depreciation	0.00	50.00	0.00	0.00	50.00	100.00
G610020	Motor vehicles - Accumulated depreciation	0.00	100.00	0.00	0.00	100.00	100.00
G700000	Debtors control	17,125.00	0.00	0.00	0.00	-17,125.00	100.00
G750000	Stock control	0.00	1,000.00	0.00	0.00	1,000.00	100.00
B810000	ABC-Bank	5,230.00	0.00	0.00	0.00	-5,230.00	100.00
B820000	Petty cash	44.00	0.00	0.00	0.00	-44.00	100.00
T860010	Output VAT - 15%	0.00	2,625.00	0.00	0.00	2,625.00	100.00
T860020	Input VAT - Standard rate -15%	1,386.00	0.00	0.00	0.00	-1,386.00	100.00
T860030	Input VAT - Capital goods -15%	120.00	0.00	0.00	0.00	-120.00	100.00
G900000	Creditors control	0.00	9,025.00	0.00	0.00	9,025.00	100.00
	Net Profit/Loss	0	9,905.00		57,800.00	-47,895.00	
	Totals		0.00		57,800.00	-57,800.00	

3. To view the annual budget figures; select "*Year*" and the period from 2024/03/01 to 2025/02/28.

Select the period from 2024/03/01 to 2024/03/31 to view the budget figures for a specific period, e.g. "*March 2024*".

4. Click on the Report button to refresh and generate the budget figures.
5. If any of these budget figures need some adjustment, click on the Setup → Accounts (Setup ribbon); select the applicable accounts and edit or enter the necessary figures.
6. Click on the Print button. The "*budgetvssimple.rep*" parameters screen will be displayed.
7. Click OK.

An example of the printed "*Budget vs actual*" report, is as follows:


budvsactsimple

Budget vs actual Period 2024/03/01 / 2025/02/28

		Trial balance		Budget			
Code	Name	Debit	Credit	Debit	Credit	Difference	%
G010000	Sales		17,500.00		125,000.00	-107,500.00	14.00
G100000	Cost of sales	4,500.00		48,000.00		43,500.00	9.38
G200000	Bank charges	45.00		480.00		435.00	9.38
G205000	Depreciation	150.00		600.00		450.00	25.00
G210010	Motor vehicles - Fuel & oil	150.00		1,200.00		1,050.00	12.50
G210020	Motor vehicles - Maintenance	810.00		1,800.00		990.00	45.00
G210030	Motor vehicles - Repairs	1,200.00		2,400.00		1,200.00	50.00
G220000	Rent	500.00		6,600.00		6,100.00	7.58
G225000	Salaries and wages			6,000.00		6,000.00	100.00
G230000	Stationery	240.00		120.00		-120.00	200.00
G505000	Capital		5,000.00			5,000.00	100.00
G600010	Furniture & fittings @ cost	3,800.00				-3,800.00	100.00
G600020	Furniture & fittings - Accumulated depreciation		50.00			50.00	100.00
G610020	Motor vehicles - Accumulated depreciation		100.00			100.00	100.00
G700000	Debtors control	17,125.00				-17,125.00	100.00
G750000	Stock control		1,000.00			1,000.00	100.00
B810000	ABC-Bank	5,230.00				-5,230.00	100.00
B820000	Petty cash	44.00				-44.00	100.00
T860010	Output VAT - 15%		2,625.00			2,625.00	100.00
T860020	Input VAT - Standard rate - 15%	1,386.00				-1,386.00	100.00
T860030	Input VAT - Capital goods - 15%	120.00				-120.00	100.00
G900000	Creditors control		9,025.00			9,025.00	100.00
	Totals	35,300.00	35,300.00	67,200.00	125,000.00	-57,800.00	
		0.00	9,905.00	0.00	57,800.00		
		Net profit		Net profit			

Printing the Budget vs actual (3 Periods) report

The Budget vs Actual (realisation - 3 periods) report lists the Income and Expense account balances and budget figures for three (3) periods as comparative figures.

Only the transactions in documents and batches which are posted (updated) to the ledger will be included in this report.

Budget figures are entered and edited in the Setup → Accounts (Setup ribbon).

If you have activated Cost centres and have entered the budget figures for Cost centres, you may select (tick) the Cost centres to print this report for your Cost centres.

To print a Budget vs actual (3 periods) report:

1. On the Reports ribbon, select Reports → Ledger → Budget.



2. Select the following options:

   a) Period - Select up to three (3) periods on the Per period tabs. You may click on the Free selection tab to select a specific date or a range of dates to include balances and budget figures in the report.

   b) Include zero balances - If this option is not selected (not ticked), it will list only the expense and income accounts which has balances and / or budget figures. Tick this option to include all accounts including those with no actual transactions and / or budget figures).

   c) Balances - If this option is not selected (not ticked), it will list the expense and income accounts which has balances and / or budget figures. If you tick this option to show only the actual transactions totals and / or budget totals of expense and income accounts for the selected period or dates.

d) Cost centre 1 - Will be listed if you have activated Cost centres and created Cost centre 1 (Groups (Setup ribbon)). You may select any of these Cost centres, to include in the report.

e) Cost centre 2 - Will be listed if you have activated Cost centres and created Cost centre 2 (Groups (Setup ribbon)). You may select any of these Cost centres, to include in the report.

3. Click on the OK button.

The "*Budget vs actual (realisation - 3 periods)*" report, should be displayed as follows:



The details, is as follows:

1. Header section - Report name and Periods as selected on the Periods in the "*Report options / parameters*" screen.

2. Expenses - A list of the accounts (created as Income and Expense account type and linked to the Expenses group / financial category). If the "*Include zero balances*" field is selected (ticked), all expense accounts will be listed (including those accounts with no actual transactions and or budget figures. If the "*Balances*" field is selected (ticked), only the "*Total - *Expenses*" will be displayed.

3. Income - A list of the accounts (created as Income and Expense account type and linked to the Income group / financial category). If the "*Include zero balances*" field is selected (ticked), all income accounts will be listed (including those accounts with no actual transactions and or budget figures). If the

"*Balances*" field is selected (ticked), only the "*Total - *Income*" will be displayed.

4. Totals -

    a) Net Profit / Net Loss: Actual - This is the total of the Expenses less the Income totals for posted batches and documents. A negative figure indicates a Net Profit and a positive figure displays a Net Loss for the selected periods (dates).

    b) Net Profit / Net Loss: Budget - This is the total of the Expenses less the Income totals for the budget figures as entered / edited (Setup → Accounts (Setup ribbon)). A negative figure indicates a Net Profit and a positive figure displays a Net Loss for the selected periods (dates).

    c) Net Profit / Net Loss: Actual - Budget - This is the total of the Net Profit / Net Loss: Actual less the Net Profit / Net Loss: Budget totals. A negative figure indicates that the posted batches and documents exceeds (overspend) the budget figures for the selected periods (dates). A positive figure indicates that the posted batches and documents is less than the budget figures (available) for the selected periods (dates).

Created with the Standard Edition of HelpNDoc: Converting Word Documents to eBooks: A Step-by-Step Guide with HelpNDoc

Budget listing - T-Account viewer

You may list the Budget figures (for all accounts or specific accounts), as entered or processed in the Budgets (Reports ribbon); or on Setup → Accounts (Setup ribbon), in the T-Account viewer. You may print these budget figures and/or export the budget figures in T-Account viewer to a spreadsheet.

To print a list of budgets in the T-Account viewer:

1. If the Budget option is selected on the "*Trial balance, Income statement*", or "*Balance sheet*" report types in the Ledger analyser 1 or 2, you may right-click and select the Show details option. This will display the budget figures in the T-Account viewer.



2. Select the dates from and to to include in the budget figures, if necessary.

> *The Batch number is displayed as "0", to indicate that this is a budget listing.*

> *The "Show contra" option will not list the Contra accounts, since no Contra accounts is available for budgets.*

3. Click on the Print button. You may also click on the Export button to export the budget figures to a spreadsheet.



Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Search - Investigator

The Investigator allows you to search for data in an open Set of Books. To search or locate data, you may enter a valid word or phrase to search for an item. This facility also allows you to define, or refine, or filter the search criteria, and select to view the details for a selected search result.

SERIAL TRACKING - If you have entered a serial number of a product (stock item) as a comment on your sales documents (Invoices, Credit notes and/or Quotes) and/or on Purchase documents (Purchases and Supplier returns and/or Orders), you may enter the serial number in the "Search for": field.

If you click on the Search now button, the Documents will be listed. You may then double-click on the selected document to preview the document.

Comments entered in document lines are searchable.

Remarks is not searchable.

To search for data using the Investigator:

1. On the Default ribbon, select Search. The "*Investigator*" screen is displayed:



2. Enter a word or phrase to search for specific data. To filter the data, you may also select to include everything or documents, batches, stock information, account names and/or account information.

3. Click on the Search now button or on the F3:Search icon. The number of items found (which matches the search criteria) will be displayed, and each of the items found will be listed.

4. Select an item type from the search results list and right-click - select "*Show detail*" option on the context menu (or double-click) to launch the options. The types is as follows:

    a) Account - Launch the T-Account viewer - You may select or enter the dates from and dates to, as well as any filters (if necessary) to view and filter the transactions. Transactions may be printed and exported to a spreadsheet file.

    b) Debtor / Creditor - Launch the Debtor accounts screen to edit or check specific details for the debtor (customer / client). If a Creditor is indicated, it will launch the specific creditor (supplier / vendor) account.

c) Stock - Launch the Stock items screen to edit or check specific details for the stock item.

d) Document - The selected document will be printed.

e) Batch - Launch the T-Account viewer - You may select or enter the dates from and dates to, as well as any filters (if necessary) to view and filter the transactions. Transactions may be printed and exported to a spreadsheet file.

For certain types (e.g. Account), the F4:Details icon will be available. If you click on this icon, the balances for general ledger accounts will be displayed for each period.

5. To close or exit this screen, click on the Close button on the title bar.

Further Search options are available to select from. If you click on the More >> link, the Advanced options will be available in which the limit for the number of records found may be set.

To refine or filter the search criteria, you may click on the Refine search link.



Payroll - Salaries and wages

Payroll plugin

Payroll - Manual - Shop - Licence : Once-off -

Supported applications: Logisal, RoosRoos and Unit 4.

Seamlessly import payroll data from supported applications like Logisal, RoosRoos, and Unit 4 directly into osFinancials5/TurboCASH5, simplifying payroll-related transactions.

Is the program you use not listed? No problem! With our commitment to customer satisfaction, simply send us an export, and we will explore the possibility of adding that import. In most cases, the addition is free of charge.

Say goodbye to manual data entry and hello to efficiency as you effortlessly generate batches or journals for payroll processing within osFinancials5/TurboCASH5.

Payroll Plugin Access - Batch entry - F9:Process - Payroll import option.

Introduction to payroll - salaries and wages

Payroll is the process by which a company pays its employees for the work they have done. Salaries and wages are the most common forms of compensation that employers use to pay their employees. Salaries are typically paid to employees who are exempt from overtime pay, such as managers and professionals, while wages are paid to non-exempt employees who are entitled to overtime pay for any hours worked over 40 hours in a week.

The payroll process involves several steps, including tracking employee time and attendance, calculating gross pay, deducting taxes and other payroll deductions, and issuing paychecks or direct deposits to employees. Payroll also involves complying with federal, state, and local laws and regulations related to employee pay and benefits, including minimum wage laws, overtime regulations, and payroll tax requirements.

The accurate and timely processing of payroll is essential for maintaining employee satisfaction and ensuring compliance with legal requirements. Mistakes in payroll processing, such as incorrect pay amounts or missed tax payments, can result in financial penalties and damage to the company's reputation.

Therefore, it is important for companies to have effective payroll processes and systems in place, and to

keep up-to-date with changing laws and regulations related to payroll. This can include using payroll software to streamline processes, working with payroll experts or outsourcing payroll functions to a third-party provider, and providing training to employees to ensure they understand their pay and benefits.

Payroll differences from country to country

Payroll processes and regulations can vary significantly from country to country, and even within countries, depending on local laws and customs. Here are some examples of payroll differences from country to country:

1. Payroll taxes: The types of payroll taxes, tax rates, and thresholds can vary widely from country to country. In some countries, employers are responsible for withholding both employee and employer payroll taxes, while in others, only the employee is responsible. Some countries also have social security taxes, pension contributions, or health insurance premiums that must be paid by the employer or employee.
2. Minimum wage: Minimum wage laws also vary widely between countries, with some countries not having a minimum wage at all. Additionally, some countries have different minimum wage rates for different industries or regions.
3. Overtime regulations: Overtime regulations also differ between countries, with some countries mandating overtime pay for hours worked over a certain number per week or per day, while others do not. Some countries also have different overtime pay rates depending on the time of day or day of the week worked.
4. Payroll processing frequencies: Payroll processing frequencies can also differ between countries. For example, in the United States, it is common to process payroll bi-weekly or semi-monthly, while in some countries, payroll is processed monthly.
5. Leave and vacation benefits: Paid leave and vacation benefits vary between countries and may be subject to local laws and regulations. In some countries, employers are required to provide paid sick leave, parental leave, or vacation time, while in others, it is not mandated by law.
6. Payroll reporting requirements: Countries have different payroll reporting requirements, including the frequency of reports and the specific information that must be reported. In some countries, employers are required to submit regular payroll reports to government agencies, while in others, reporting is not required.

It is important for companies operating in multiple countries to be aware of these payroll differences and to ensure compliance with local laws and regulations. This may require the help of local payroll experts or legal counsel to navigate the complex and changing landscape of global payroll.

What is the basic payroll accounts and transactions in the chart of accounts?

The chart of accounts for payroll includes accounts that are used to record various payroll transactions. Some of the basic payroll accounts and transactions in the chart of accounts are:

1. Salaries and Wages Payable: This account represents the amount of salaries and wages earned by employees but not yet paid. It is credited when employees earn their wages or salaries, and debited when the company pays them.
2. Employee Benefits Payable: This account represents the amounts the company owes for employee benefits such as health insurance, retirement plans, and vacation pay. It is credited when the company incurs the expense and debited when the company pays for the benefits.
3. Payroll Tax Expense: This account represents the taxes the company is required to pay on behalf of its employees, such as Social Security, Medicare, and federal and state income taxes. This account is debited as the company incurs the expense.
4. Payroll Tax Payable: This account represents the amounts the company owes for payroll taxes. It is credited when the company withholds taxes from employee pay and debited when the company remits those taxes to the government.
5. Employee Advances: This account represents any money the company has advanced to employees as an advance on their salaries or wages. It is debited when the advance is made and credited when the employee repays the advance.
6. Payroll Clearing: This account represents the net amount paid to employees after all deductions have been made. It is debited when the company pays employees and credited when employees cash their paychecks.

Each payroll transaction involves at least two accounts, with one account being debited and another being credited. For example, when an employee is paid, the Payroll Clearing account is debited for the amount of the payment, and the Salaries and Wages Payable account is credited for the amount owed to the employee.

What options is there to import payroll transactions from a payroll system into a accounting software system?

There are several options for importing payroll transactions from a payroll system into an accounting software system. Some of the most common methods include:

1. Manual entry: This involves manually entering each payroll transaction into the accounting software.

While this method is the most time-consuming and prone to errors, it is the simplest and most accessible option for smaller businesses.

2. Importing transactions as a CSV File: Many payroll systems can export transactions as a CSV file that can be imported directly into an accounting software system. This option saves time and reduces errors, but may require some formatting adjustments to ensure the data is correctly mapped to the appropriate accounts.
3. Integrating Payroll and Accounting software: Some payroll and accounting software systems have integrations that allow for the automatic transfer of payroll transactions. This option is the most efficient and eliminates the need for manual data entry or file transfers.
4. Using a third-party integration platform: There are third-party integration platforms available that can connect payroll and accounting software systems that do not have native integrations. These platforms act as a bridge between the two systems and automate the transfer of payroll transactions.

The option that is best for a company will depend on their specific needs and the payroll and accounting software they are using. Factors such as the size of the business, the volume of payroll transactions, and the level of automation desired will all influence which option is most suitable.

Can a payroll system be used in a spreadsheet?

Yes, a payroll system can be created and used in a spreadsheet program like Microsoft Excel or Google Sheets. Spreadsheets are commonly used for managing payroll because they offer a range of features such as calculations, formulas, data validation, and data analysis tools.

To create a payroll system in a spreadsheet, you can start by listing all of the employees and their corresponding salary information. You can then use formulas to calculate the gross pay, deductions, and net pay for each employee.

You can also use conditional formatting to highlight any discrepancies or errors in the data, such as missing or incorrect information. Additionally, you can create charts and graphs to visualize the payroll data and track trends over time.

However, it's important to note that using a spreadsheet for payroll has its limitations, especially for larger organizations. As the number of employees and payroll complexity increases, it may become more difficult to manage and maintain the spreadsheet. In such cases, it may be more efficient to use specialized payroll software that is designed for larger organizations.

How are salaries and wages (payroll) expenses recorded in an accounting system?

Salaries and wages expenses are typically recorded in an accounting system through a process called payroll accounting. This involves several steps, including:

1. Recording employee information: The first step in payroll accounting is to collect and record information about each employee, such as their name, address, Social Security number, tax withholding status, and salary or wage rate.
2. Calculating gross pay: Gross pay is the total amount of money an employee earns before any deductions are taken out. This includes regular wages or salary, as well as any overtime pay or bonuses earned during the pay period.
3. Deducting taxes and other withholdings: Once gross pay is calculated, payroll software will automatically deduct any taxes or other withholdings required by law, such as federal and state income taxes, Social Security taxes, and Medicare taxes.
4. Calculating net pay: Net pay is the amount of money an employee receives after all taxes and other deductions have been taken out.
5. Recording payroll expenses: The final step in payroll accounting is to record the payroll expenses in the company's accounting system. This includes debiting the appropriate expense accounts for salaries, wages, and any employer-paid taxes or benefits, and crediting the company's cash account for the net amount paid to employees.

Payroll accounting can be a complex process, especially for companies with a large number of employees or multiple locations. Many companies use payroll software or outsource their payroll processing to third-party providers to simplify the process and ensure accuracy.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Bad debts

Introduction to Bad debts

Bad debts refer to the portion of a company's accounts receivable that is deemed uncollectible and unlikely to be recovered from customers or clients. When a business extends credit to its customers or

sells products or services on credit, there is a risk that some customers may fail to make payment for various reasons, such as financial difficulties, bankruptcy, or disputes. These unpaid debts become bad debts.

Bad debts are typically recorded as an expense in the financial statements of the business, usually in the form of a provision for bad debts or a specific write-off of the individual customer's outstanding balance. By recognizing bad debts as an expense, the business acknowledges the financial loss it has incurred due to the non-payment of debts.

Accounting standards, such as IFRS (International Financial Reporting Standards) and GAAP (Generally Accepted Accounting Principles), provide guidelines on how to estimate and account for bad debts. It involves assessing the creditworthiness of customers, analysing the ageing of accounts receivable, and considering historical collection patterns to determine the amount of bad debts or provisions to be recorded.

Managing bad debts is an important aspect of credit control and financial management for businesses. By monitoring and controlling credit risk, implementing effective credit policies, conducting regular credit assessments, and taking prompt action to recover outstanding debts, businesses can minimize the impact of bad debts on their financial performance.

Consideration to manage bad debts and provision for bad debts

It's important to establish a provision for bad debts or irrecoverable debts to accurately reflect the uncertainty surrounding the collection of debts. This provision helps businesses estimate the potential losses and maintain appropriate records of the written-off amounts.

To effectively manage bad debts and estimate the provision, businesses should consider the following:

1. Credit control: Carefully assess the creditworthiness of customers before granting credit facilities. Screening debtors and setting credit limits can help mitigate the risk of bad debts.
2. Regular statements: Send debtor statements on a regular basis to remind customers of their outstanding balances and encourage timely payments.
3. Age analysis reports: Utilise debtors' age analysis reports to track overdue amounts and follow up with reminders, letters of demand, and other collection efforts.
4. Early settlement discounts: Consider offering early settlement discounts to incentivize prompt payment from debtors.

Write-off and provisions for bad debt - scope and accounting standards

Write-off and provisions for bad debt are applicable to small businesses as well as larger enterprises. The accounting treatment for bad debts and provisions may vary depending on the accounting standards followed by the business, such as IFRS (International Financial Reporting Standards), IFRS for SMEs (International Financial Reporting Standards for Small and Medium-sized Entities), and GAAP (Generally Accepted Accounting Principles).

Under these accounting standards, businesses are required to assess and recognize potential losses arising from bad debts and make provisions accordingly. The objective is to ensure that the financial statements reflect the true and fair view of the business's financial position, including the estimation of potential losses due to uncollectible debts.

The specific guidelines and requirements for recognizing and measuring provisions for bad debts may differ between the accounting standards. IFRS and IFRS for SMEs provide more detailed guidance on the recognition, measurement, and disclosure of bad debts and provisions. GAAP, on the other hand, may have its own specific principles and requirements for the treatment of bad debts.

It's important for businesses to adhere to the relevant accounting standards applicable in their jurisdiction and industry. This ensures consistency, comparability, and transparency in financial reporting, allowing stakeholders to make informed decisions based on the financial information provided. Consulting with accounting professionals or referring to the specific accounting standards and guidelines is recommended to ensure compliance and accurate financial reporting related to write-offs and provisions for bad debts.

Example of the accounts for Provision for bad debts and Recovery of bad debts in a chart of accounts

An example of the account structure for managing accounts receivable, provision for bad debts, and bad debts recovered in the current asset section of based on a 4-digit Chart of Accounts, is as follows:

1. G1200-000 Accounts receivable (Debtors control): This account is used to track the total amount owed to your business by your customers. It represents the outstanding receivables and is classified as a current asset. The debit balance of $20,000 indicates the total amount owed by your customers.
2. G1210-000 Provision for bad debts: This account is used to record the estimated amount set aside for potential bad debts. It is a contra-asset account and is subtracted from the accounts receivable balance. The provision amount represents an estimate of the potential losses from uncollectible debts.
3. G1220-000 Bad debts recovered: This account is used to record the recovered amount from

previously written-off bad debts. It is a current asset account and is used to offset the provision for bad debts when the recovered amount is received.

By including these accounts in the current assets section of your chart of accounts, you can effectively track accounts receivable, manage provisions for bad debts, and record any recoveries from previously written-off bad debts. This provides a clear picture of your outstanding receivables and the impact of bad debts on your financial statements.

Please note that the account codes (e.g., G1200-000, G1210-000, G1220-000) may vary depending on your specific accounting system or organizational preferences. It's important to use account codes that align with your chart of accounts structure.

Created with the Standard Edition of HelpNDoc: Free help authoring environment

Credit control and bad debts

Credit control and bad debts

Credit control and managing bad debts are essential aspects of financial management for businesses. Here are some key points to consider regarding credit control and handling bad debts:

1. Credit control policies: Establishing robust credit control policies and procedures is crucial. This involves assessing the creditworthiness of customers before extending credit, setting appropriate credit limits, and defining payment terms and conditions.
2. Credit checks: Conducting credit checks on potential customers can help assess their financial stability and credit history. This information assists in determining whether to grant credit and the appropriate credit limit.
3. Clear terms and conditions: Clearly communicate your payment terms and conditions to customers upfront. This includes specifying credit periods, penalties for late payments, and any applicable interest charges.
4. Invoicing and Statements: Timely and accurate invoicing is essential to ensure prompt payment. Regularly send account statements to customers to keep them informed of their outstanding balances.
5. Payment reminders: Implement a systematic process for sending payment reminders to customers as payment due dates approach. This can be done through automated reminders or personalized communications.
6. Debt collection: If customers fail to make payments within the agreed terms, initiate a structured debt

collection process. This may involve sending reminder letters, making phone calls, or engaging a debt collection agency if necessary.

7. Provision for Bad Debts: Estimate and allocate provisions for bad debts based on the likelihood of non-payment. This helps account for potential losses and maintains accurate financial reporting.
8. Write-offs: When it becomes clear that a debt is uncollectible, it may need to be written off as a bad debt. Proper documentation and accounting entries should be made to reflect this.
9. Legal options: In extreme cases where all collection efforts fail, legal action may be pursued to recover outstanding debts. Consult legal professionals to explore available options.
10. Regular review: Continuously monitor and review your credit control processes and performance. Identify areas for improvement and implement necessary adjustments to minimize bad debts.

Effective credit control practices can help mitigate the risk of bad debts and maintain healthy cash flow. Regular monitoring, proactive communication, and diligent follow-up are crucial in managing credit effectively and minimizing the impact of bad debts on your business.

When granting credit to customers, the credit screening, credit bureaus and legislation to consider?

When granting credit to customers, it is important to consider several factors related to credit screening, credit bureaus, and relevant legislation. Here's an overview of each aspect:

1. Credit screening:
    - Financial information: Assess the financial stability and creditworthiness of the customer by reviewing their financial statements, bank references, and credit references.
    - Credit history: Obtain credit references from other suppliers or vendors to gauge the customer's payment history and credit behavior.
    - Trade references: Contact the customer's previous or existing suppliers to gather information about their payment habits and creditworthiness.
    - Credit application: Require customers to complete a credit application form that includes essential details such as business information, financial statements, and references.
2. Credit bureaus:
    - Credit reports: Utilize credit reports obtained from credit bureaus that provide information on an individual or company's credit history, payment patterns, outstanding debts, and credit scores.

- Credit scores: Evaluate credit scores provided by credit bureaus to assess the risk associated with extending credit to a particular customer. Credit scores are typically based on various factors such as payment history, credit utilization, length of credit history, and public records.

3. Legislation and regulations:
    - Fair Credit Reporting Act (FCRA): Adhere to the provisions of the FCRA, which governs the collection, dissemination, and use of consumer credit information, ensuring compliance with consumer rights and privacy.
    - Equal Credit Opportunity Act (ECOA): Comply with the ECOA, which prohibits discrimination based on race, colour, religion, national origin, sex, marital status, age, or receipt of public assistance when evaluating credit applications.
    - Data Protection Laws: Abide by applicable data protection and privacy laws to safeguard customer data and ensure proper handling and storage of credit-related information.
    - Industry-Specific Regulations: Consider any industry-specific regulations or guidelines that may impact the extension of credit, such as those related to financial services, healthcare, or consumer lending.

By considering these factors, businesses can make informed decisions when granting credit to customers, mitigating the risk of defaults and ensuring compliance with relevant laws and regulations. It is advisable to establish clear credit policies and procedures, conduct thorough credit assessments, and regularly monitor the creditworthiness of customers to manage credit risks effectively.

Open item feature versus the balance brought forward - Advantages to manage debtor accounts to reduce bad debts

Managing debtor accounts using the Open Item feature can offer advantages in reducing bad debts. Here's how it can help:

1. Improved accuracy: With the Open Item feature, each transaction is treated as a separate item or entry. This allows for precise tracking of individual invoices and payments. By accurately matching payments to specific invoices, you can identify any outstanding balances more easily, ensuring that debts are promptly addressed.
2. Enhanced visibility: The Open Item feature provides a clear overview of each debtor's account, showing all outstanding invoices and payments. This visibility enables you to identify overdue invoices and take appropriate actions, such as sending reminders or initiating collection efforts promptly.
3. Proactive credit control: By regularly reviewing open items and following up with debtors, you can maintain better control over credit terms and ensure timely payments. Promptly addressing any

discrepancies or disputes can help prevent bad debts from accumulating.

4. Accurate ageing analysis: The Open Item feature enables accurate ageing analysis of outstanding invoices. By categorizing debts based on their ageing periods (e.g., current, 30 days, 60 days, etc.), you can identify problematic accounts or overdue payments more effectively. This analysis helps in prioritising collections and taking necessary actions to recover outstanding amounts.

5. Prompt dispute resolution: The detailed tracking provided by the Open Item feature facilitates faster resolution of invoice disputes. By promptly addressing and resolving any discrepancies or disputes, you can minimise the risk of bad debts arising from unresolved issues.

Overall, the Open Item feature offers greater control and visibility over debtor accounts, helping you proactively manage credit control and reduce the occurrence of bad debts. It promotes accuracy, enables effective ageing analysis, and facilitates prompt actions to address outstanding balances, enhancing your overall debt management practices.

Open item and managing of debtor accounts

The Open Item feature in osFinancials5/TurboCASH5 allows for efficient management of debtor accounts by matching transactions and tracking outstanding amounts. Here are the key aspects of the Open item feature:

1. Enabling open item: The Open item feature is selected in the "*Open item account*" of the Accounting tab in a Debtor account. It allows transactions, such as invoices, credit notes, and payments, to be matched to credit or debit transactions.

2. Processing transactions: When processing transactions in batches, journals, or documents, an Open Item selection screen displays all outstanding transactions. Here, specific transactions can be selected and linked to the current transaction.

3. Open item options on the Default ribbon:

    - Open item: This feature allows you to manage links, clear links, generate balance forward, unlink transactions, view transactions in a statement layout, and export transactions to a spreadsheet. You can select all debtor accounts or a specific debtor account.

    - Debtors - Transactions tab: The Transactions tab in debtor accounts lists all transactions or only unmatched outstanding transactions. Filtering options are available, and you can print posted batch reports or view transactions in the T-Account viewer, which also allows printing and exporting to a spreadsheet.

    - Documents: The powerful document grid for Invoices and Credit notes allows filtering and searching for specific documents with outstanding balances or documents without any

outstanding or due amounts for a particular debtor account. You may export these filter results to a spreadsheet.

4. Open item options on the Reports ribbon:

   - Transaction list reports: Transaction reports under the Reports → Debtors → Transactions menu offer options such as the Transaction list (lists a complete list of transactions) or a Transaction list - Open item (lists only the outstanding transactions) for all debtors or a selected debtor account.
   - Age analysis: Age analysis (accessed on the Reports ribbon or on the Due tab of Age analysis on the Default ribbon) generate on-screen or printed reports based on the system date or a selected date of ageing.
   - Age analysis - Reports: The Reports → Debtors → Age analysis menu provides the ability to print age analysis reports for all debtors or a selected debtor account.
   - Debtor statements: Debtor statements can be printed for all transactions or only outstanding transactions.

By utilising the Open Item feature and accessing its various options, users can effectively manage debtor accounts, match transactions, generate reports, and monitor outstanding balances for efficient credit control and bad debt reduction.

Managing credit limits

Available balances - Credit control listing

In osFinancials5/TurboCASH5, besides the age analysis reports, you have the option to print a list of debtor's available balances as of the system date. This report is available on the Reports → Debtors listing - Credit control listing (credit limit vs actual balance) as at report. This report provides information on the available balances for all debtors or for a selected debtor account or for all debtors associated with a particular debtor reporting group. Moreover, you have the option to include the contact details of the debtors in the report. Please note that this report reflects the available balances as of the current date recorded in your system.

The current balance displayed in the "Credit control listing (credit limit versus actual balance) as at " report does not include unposted transactions in batches or journals, as well as unposted documents such as invoices and credit notes. It represents the balance based on posted transactions recorded in the ledger. Please keep this in mind when reviewing the report, as any unposted transactions will not be reflected in the current balance.

The report will include the following details for each debtor:

1. Credit limit: This is the maximum amount of credit extended to the debtor.
2. Posted transactions in batches and documents: It will display the totals of the transactions that have been recorded in batches (journals) and documents.
3. Available balances: The report will show the available balance for each debtor. The available balance is calculated by subtracting the outstanding balance from the credit limit. It represents the remaining credit that the debtor has available.

By printing this report, you can have an overview of the credit limits, current balances, and available balances for your debtors. This information can help you monitor credit utilisation, identify potential risks, and make informed decisions regarding credit extensions and debt management.

Remember to review the report regularly and take appropriate actions based on the information provided to maintain healthy debtor accounts and minimize credit-related issues.

Available balances in documents - Messages

In osFinancials5/TurboCASH5, when processing sales documents such as quotes, invoices, and credit notes, the available balances (credit limit minus current balance) are shown in the document entry footer section. When you complete the document and click OK, a warning message may appear if the debtor's balance exceeds the credit limit. The warning message will indicate the amount by which the balance exceeds the credit limit, such as

> "Debtor's balance is over credit limit with: -1100."

This warning message serves as an alert to inform you that the debtor's outstanding balance has exceeded the predefined credit limit. It indicates that the debtor may have exceeded their credit terms or credit limit, and you may need to review their account and take appropriate actions, such as contacting the debtor to arrange payment or adjusting their credit limit.

It's important to address these warnings and take necessary steps to manage credit risks and ensure timely payment from debtors. This helps maintain healthy cash flow and minimizes the potential for bad debts or financial difficulties for your business.

Messages to enhance credit control

In osFinancials5/TurboCASH5, you can utilize messages to enhance credit control practices. Here are some relevant features:

1. Messages on Sales documents: Within the Setup → Documents setup, you can set up to three lines of messages that will appear on sales documents like quotes, invoices, and credit notes. These global

messages apply to all debtors and are printed on the document layout files. During document processing, you have the flexibility to modify or add additional text to the messages as needed.

2. Messages on Debtor statements: Within the Setup → Documents setup - Statements tab, you can enter a global message that will be printed on all debtor statements. This message allows you to communicate important information or reminders to your debtors. Additionally, you have the option to enter a statement message specific to a selected debtor account, which can be added on the Delivery address tab. This enables you to include personalized statements or specific instructions for individual debtors.

By utilizing these message features in osFinancials5/TurboCASH5, you can effectively communicate with your debtors, provide important information, and reinforce credit control measures. These messages serve as reminders, prompts, or additional notes on various documents and statements, enhancing your credit control practices.

Calendar - Appointments and notes

Calendar - If you need to review a credit limit or have some concerns, you may schedule up to six categories of appointments with debtors in the Calendar. On these appointments, you may add notes about the intended reason for the appointment and discussions. This feature allows you to effectively manage and review credit limits, address concerns, and track important discussions with debtors.

By utilising the calendar feature, you can effectively manage your debtor-related appointments and stay on top of credit limit reviews and other important discussions. The ability to add notes and set reminders enhances your ability to track and follow up on these appointments, ensuring efficient debtor management.

A list and detailed information of all appointments, including any notes, can be accessed on the Appointment tab of a selected debtor account in osFinancials5/TurboCASH5. This tab provides a comprehensive list of all scheduled appointments related to that particular debtor, allowing you to review and manage the details and notes associated with each appointment.

Remember to regularly check your calendar to stay updated on upcoming appointments and make necessary preparations. This feature provides a convenient way to schedule, manage, and keep track of debtor-related activities, promoting effective communication and timely follow-ups.

Disable debtor accounts

Disable debtor accounts - In osFinancials5/TurboCASH5, if you have written off bad debts for a debtor and consider them to be a credit risk, you have the option to disable their debtor account. By selecting the "*Account disabled*" option on the Accounting information tab, you can prevent any further processing and

posting of transactions for that particular debtor.

By setting a debtor account as inactive or disabling a debtor account, you ensure that no further transactions can be processed or posted for that specific debtor. This helps in managing credit risks and preventing additional financial exposure. However, it's important to note that all existing transactions and historical data related to the debtor will still be available in reports and other relevant areas of the osFinancials5/TurboCASH5 system.

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Write-off of Bad debts

Write-off of Bad Debts

Bad debts are written off when debts become irrecoverable during the financial year.

It is important to note that if you need to make provisions for bad debts, which are estimated to become irrecoverable in future financial years, you should also write off any debts that are currently irrecoverable. This is because these calculations should be based on the good book Debtor accounts.

To write off bad debts, the usual practice is to use the General journal. Since bad debts represent a loss or expense for the business, their write-off will reduce the net profit or increase the net loss. It is crucial to maintain documentary proof, such as letters of demand, to support the attempts made to recover the bad debts.

Before you can write off bad debts in osFinancials5/TurboCASH5, please ensure the following:

1. Disabled accounts: If you have disabled a debtor account and set it to inactive, you need to enable the account by setting it back to active. This will allow you to process the bad debts write-off transactions to the debtor account. Check the account settings and ensure that the debtor account is active and enabled for transactions.

2. Open item reconciliation: It is important to ensure that all outstanding amounts are correctly linked to credit transactions or credit notes. Review the open item transactions for the debtor account and ensure that any relevant credits or credit notes are properly applied to offset the outstanding amounts. This will help in accurately reflecting the bad debts write-off and maintaining proper account reconciliation.

By addressing these two points, you can ensure that the debtor account is active and ready for processing the bad debts write-off transactions, and that the outstanding amounts are reconciled correctly with

appropriate credits or credit notes.

Example : Write off Bad debts with VAT/GST/Sales tax

To write off bad debts and clear the Debtors account with the amount of irrecoverable debts (including VAT/GST/Sales Tax), follow these steps:

1. Identify the irrecoverable Debtor account and ensure you have sufficient documentary evidence of attempts to collect the debt. Only proceed with write-off after exhausting all avenues.
2. If you are a registered VAT/GST/Sales Tax vendor, identify the Interest amount and the VAT/GST/Sales Tax amount of the Output VAT/GST/Sales Tax already paid to the Tax Authorities in a previous Tax period. This is important to verify the correct VAT/GST/Sales Tax amount.

When writing off bad debts for debtor accounts on which output tax was paid to the tax authorities in a previous tax period, you may need to consider the VAT/GST or sales tax implications. However, the specific steps and requirements may vary depending on the jurisdiction and tax regulations.

Here are some general considerations:

1. *Create a Tax code: In osFinancials5/TurboCASH5, you may need to create a specific tax code or sub-account in the Setup → Accounts - Tax account type (Setup ribbon) to account for the VAT/GST or sales tax related to bad debts.*
2. *Write-off process: When writing off bad debts, you would typically credit the debtor's account with the amount of the irrecoverable debts (inclusive of VAT/GST/sales tax), debit the bad debts expense account (exclusive of VAT/GST/Sales tax), and debiting the Bad debts tax code with the VAT/GST/Sales tax amount.*
3. *Tax Return and Adjustments: The VAT/GST/sales tax amount associated with the bad debts write-off needs to be considered for the tax return. It may be reported as a tax adjustment or a deduction on the VAT/GST/Sales tax return. The specific reporting block or line may vary depending on the tax jurisdiction. By reducing the taxable amount on the return, it can potentially lower the amount payable to the tax authority.*

It's important to consult with a tax professional or refer to the tax regulations specific to your jurisdiction to ensure compliance with the VAT/GST or sales tax requirements when writing off bad debts and handling the associated tax implications.

Interest amount - Identifying the interest amount, it typically refers to determining the portion of the outstanding debt that represents interest charges.

When dealing with bad debts or debt write-offs, it's important to consider any interest charges that may have been applied to the outstanding debt. In some cases, businesses may charge interest on overdue payments, and this interest may be subject to VAT/GST or sales tax depending on the

applicable regulations in your jurisdiction.

By identifying the interest amount, you can ensure that the correct VAT/GST/sales tax amount is calculated and accounted for when writing off the bad debts. This helps in accurately determining the tax implications and complying with the tax regulations specific to your VAT/GST/sales tax system.

It's important to consult with a tax professional or refer to the tax regulations in your jurisdiction to understand the specific requirements and treatment of interest charges in relation to VAT/GST/sales tax.

3. Write off the Bad Debts in the General journal.

Procedure to write-off bad debts for a debtor account:

Example: An amount of 1,150 (including VAT at 15%) is written off.

1. In osFinancials5/TurboCASH5 navigate to the Default ribbon.

2. Select "*Batch entry*" and choose the "*General journal*" option.



3. Batch setup: Since this is a general journal that may be used for other general transactions, click F10: Setup to set the "*Options for this bath*" as follows:

    a) Standard tab - "*Contra account*" select the "*Bad debts*" expense account.



b) Advanced tab - Select the following options:



- Account lookup type - Select "*Debtors*" to only list the debtor accounts in the lookup.
- Contra account lookup type - Select "*General ledger*" to only list the general ledger account as the contra account for the balancing entries or transactions.
- Leave the rest of the settings as in the options for this batch as in the screenshots, and click OK to save your settings.

4. Change alias: By default the name of the journal is displayed as "*General journal - [General journal]*"

To make it easy to identify the specific nature of the transactions in the General journal, enter a unique name for your specific requirements, in the "*Change alias field*" and press Enter. In this example the "*Bad debts-Green*" was entered. This will change the general journals name as name of the journal is displayed as "*General journal - [Bad debts-Green]*" in the titlebar It indicates that "*Bad debts for Debtor Green*" was processed in the general journal.

5. Enter the transactions for the bad-debts:

   - Date: By default, the date of your operating system would be displayed. Select the specific date on which you need to write off the debt.
   - Reference: The default reference in a new General journal would be "*1*" . In the case of a previous processed transactions, the Description could be the related to the last reference used. Enter a valid reference.
   - Description: Enter a description for each transaction for your own requirements. In this example, the description is changed to "*Write-off bad debts -AB Green IN000005*" Note: The descriptions should make sense to understand the nature of the transactions.
   - Debtors (Accounts): Select the account of the debtor for which you need to write-off bad debts.
   - Tax: Select the VAT/GST.Sales tax code for bad debts if applicable to your jurisdiction.

VAT/GST/Sales tax - Writing off of bad debts:

It is important to note that the specific tax rules and regulations regarding bad debt write-offs can vary, and it's advisable to consult with a tax professional or refer to the tax laws in your jurisdiction to determine the exact requirements and treatment of VAT/GST/Sales tax in relation to writing off uneconomical bad debts.

If VAT/GST/Sales tax is applicable on the writing off of bad debts, you can follow the steps below to ensure proper recording and allocation of the tax:

- *Add a Tax account code for Bad debts: Create a specific Tax account code for bad debts, such as "T2400-200 - VAT-Adjustments - Bad debts." This account should be included in the structure of your VAT/GST/Sales tax control account in the current liabilities section of your Chart of Accounts. This will allow you to track and report the VAT/GST/Sales tax adjustments related to bad debts separately.*
- *Process the general journal to write off bad debts: When recording the write-off of bad debts in the general journal, select the appropriate Tax code for "Bad debts." This Tax code should be associated with the specific VAT/GST/Sales tax percentage and transactions applicable to bad debts. By selecting the appropriate Tax code, the system will calculate and allocate the VAT/GST/Sales tax amount accordingly.*

By following these steps, you can ensure that the VAT/GST/Sales tax implications of writing off bad debts are properly accounted for and reflected in your financial records and tax returns.

- Credit: Enter the amount in the credit column. If the VAT/GST/Sales tax code for bad debts was selected, it will automatically generate the VAT/GST/Sales tax percentage when balancing entries are generated.

7. After entering the write off transaction in the General journal should be displayed as follows:



Open item selection: The "Open item selection" screen will be launched for debtors whose accounts are set as Open item accou debts to be written off against specific transactions or invoices.



After selecting or linking the Bad-debts write-off transaction to an outstanding transactions, the transaction line will be displa

Finalising the batch transactions

Once you have entered or edited your transactions, you need to finalize the batch:

- Balance the batch: Click F5: Balance to generate the balancing transactions to the contra account.



- List the batch: Click F8: List to print a list of the unposted batch transactions in the batch. Review the list for any errors or discrepancies and make necessary edits before proceeding. This list may be retained for record and audit purposes.



- Post the batch: Click F6: Post to post or update the transactions in the batch.

Disable debtor accounts - After processing and writing off bad debts, and considering them to be a credit risk, you have the option to disable their debtor account. By selecting the "Account disabled" option on the Accounting information tab, you can prevent any further processing and posting of transactions for that specific debtor.

By setting a debtor account as inactive or disabling it, you ensure that no additional transactions can be

processed or posted for that particular debtor. This helps in managing credit risks and preventing additional financial exposure. It's important to note that all existing transactions and historical data related to the debtor will still be available in reports and other relevant areas of the osFinancials5/TurboCASH5 system.

Disabling debtor accounts provides an effective way to control credit risks and manage your accounts receivable effectively. By keeping inactive debtor accounts separate from active ones, you can easily identify and focus on those accounts that require attention or further action.

Please exercise caution when disabling debtor accounts and ensure that it aligns with your internal policies and procedures. Additionally, consider any legal or regulatory requirements that may affect the management and retention of debtor information.

Transactions in the ledger

The transactions is updated in all respective accounts and will be available in all reports for the accounts for the Debtor accounts and in the Bad debts expense account. These totals of the accounts will be reflected in the Trial balance in the Ledger analyser. The Debtors control account will reflect the transactions in the Balance sheet. The "*Bad debts*" expense account will be reflected on the Income statement.

T-Account viewer

In any of these report types in the Ledger analyser, you may double-click on an account or right-click and select the "*Show details*" option on the context menu. This will launch the T-Account viewer with the transaction details. You may print the transactions or export the transactions to a spreadsheet. An example of the transactions is as follows:

The T-Account viewer allows you to view transaction details for specific accounts. You can access it by double-clicking on an account or right-clicking and selecting the "*Show details*" option. In the T-Account viewer, you can double-click on the batch number, account code, or date to filter transactions.

Contra transactions are indicated by eight asterisks (********). The "*Show contra*" option displays the contra transactions. When printing the transactions the contra accounts will not be printed.

When exporting the transactions to a spreadsheet, the contra accounts will be included in column "*A*" if the "*Contra account*" option is selected.

Click on the Print button to print the transactions in the T-Account viewer.



In addition to launching the T-Account viewer from the Ledger analyser options, the T-Account viewer may also be launched separately on the Reports ribbon; or from the following options on the Default ribbon:

- *Search - Investigator - Account or Batch type searched items.*
- *Debtors - Transactions tab - Click on the Show transactions button.*
- *Creditors - Transactions tab - Click on the Show transactions button.*

By utilising the T-Account viewer and the reports in the Ledger Analyser, you can gain a detailed understanding of the transactions and their impact on the accounts involved.

Please note that the specific accounts and tax codes may vary based on your accounting system and local tax regulations. It's important to consult with a tax professional or refer to the guidelines provided by your tax authority to ensure accurate and compliant recording of write-offs including VAT/GST/sales tax.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Write-off bad debts - Uneconomical to recover

When does Bad debts become uneconomical to collect?

Determining when bad debts become uneconomical to collect depends on various factors and may vary based on individual circumstances and business practices. Here are some common indicators that may suggest bad debts are uneconomical to collect:

1. Length of delinquency: If a debt has been outstanding for an extended period without any progress in collection efforts or communication from the debtor, it could indicate that it is becoming increasingly difficult to recover the amount.
2. Lack of debtor communication: When debtors consistently ignore attempts to contact them or fail to provide viable repayment plans, it may signal that collecting the debt is unlikely.
3. Financial hardship: If the debtor is experiencing significant financial difficulties, such as bankruptcy or insolvency, it may make it impractical to pursue the debt further.
4. Insufficient assets or resources: If the debtor lacks sufficient assets or income to satisfy the debt, it may be economically unfeasible to continue collection efforts.
5. Cost-benefit analysis: Assessing the costs associated with further collection efforts, such as legal fees, time, and resources, against the potential recovery amount can help determine if it is uneconomical to continue pursuing the debt.

It's important to note that the determination of uneconomical debts is subjective and may vary among businesses. Establishing clear internal policies and guidelines, and consulting with accounting professionals or legal advisors, can help in making informed decisions regarding the write-off of bad debts.

Write-off bad debts which is uneconomical to collect for multiple debtor accounts

In osFinancials5/TurboCASH5 you may generate multiple entries in a journal to list all the debtor account balances which is less than a specified amount.

In osFinancials5/TurboCASH5, you have the capability to generate multiple entries in a journal to list all debtor account balances that are less than a specified amount. This functionality is particularly useful for identifying and dealing with bad debts that are considered uneconomical to collect.

By generating multiple entries in a journal for debtor accounts with balances below a specified amount, you can effectively identify and isolate bad debts that are uneconomical to collect. This enables you to

have a clear overview of these accounts and take appropriate actions, such as writing off the debts or pursuing alternative debt recovery methods.

Decide on the threshold amount below which debtor account balances will be considered uneconomical to collect. For example, you may choose $100 as the threshold.

Procedure to write-off bad debts multiple debtor accounts:

1. In osFinancials5/TurboCASH5 navigate to the Default ribbon.
2. Select "*Batch entry*" and choose the "*General journal*" option.



3. Batch setup: Since this is a general journal that may be used for other general transactions, click F10: Setup to set the "*Options for this bath*" as follows:

    a) Standard tab - "*Contra account*" select the "*Bad debts*" expense account.



b) Advanced tab - Select the following options:



- Account lookup type - Select "*Debtors*" to only list the debtor accounts in the lookup.
- Contra account lookup type - Select "*General ledger*" to only list the general ledger account as the contra account for the balancing entries or transactions.
- Leave the rest of the settings as in the options for this batch as in the screenshots, and click OK to save your settings.

4. On the batch entry screen, go to the F9: Process icon and select the "*Generate multiple transactions*" option on the "Process the batch" screen.



5. Click OK.



6. On the "Generate multiple transactions" screen the default option "Balance debtors with amount < x.xx" is selected. On this option, select the following:

   - Date for transactions: The date of your operating system will be displayed. Select the date on which you need to write off the bad debts which is uneconomical to recover. Note: In this example the date is the last date in the accounting period or financial year e.g. "*31 December 2021*" if you need to to include in your financial reporting and statements for the year ending on "*31 December 2021*".
   - Contra account: Select the contra account for the "*Bad debts*" expense account. This contra account is not used, but the contra account selected on the F10: Setup - "*Options for this batch*" on the Standard tab.
   - To debtors with a balance less than (amount): Specify the amount (e.g., $100.00) for debtor accounts with balances less than or equal to that amount.

7. Click OK. All debtor accounts with outstanding balances of $100.00 or less, will be imported into the general journal as on the selected date.



8. After importing the multiple transactions of debtors in the "*General journal*", The icons in the speed bar options will be inactive. Close the "*General journal*" and relaunch the batch to activate these options.

9. Edit the "*General journal*" for the imported transactions:



- Change alias: By default the name of the journal is displayed as "*General journal - [General journal]*" To make it easy to identify the specific nature of the transactions in the General journal, enter a unique name for your specific requirements, in the "*Change alias field*" and press Enter. In this example the "*Bad debts-2021*" was entered. This will change the general journals name as name of the journal is displayed as "*General journal - [Bad debts-2021]*" in the titlebar It indicates that "*Bad debts for 2021*" was processed in the general journal.

- Description: The default description for each transaction, is "*My description2021/03/31*" Change this with a description for your own requirements. In this example, the description is changed to "*Uneconomical-write-off-bad-debts-2021/12/31*" Note: The descriptions should make sense to understand the nature of the transactions.



- Edit / Delete transactions: Edit the imported transactions, ensuring that you do not write off debtor accounts with small outstanding balances that are likely to be recovered through normal business processes. Delete any transactions that should not be written off.

> *VAT/GST/Sales tax - Writing off of bad debts:*
>
> *It is important to note that the specific tax rules and regulations regarding bad debt write-offs can vary, and it's advisable to consult with a tax professional or refer to the tax laws in your jurisdiction to determine the exact requirements and treatment of VAT/GST/Sales tax in relation to writing off uneconomical bad debts.*
>
> *If VAT/GST/Sales tax is applicable on the writing off of bad debts that are uneconomical to recover, you can follow the steps below to ensure proper recording and allocation of the tax:*
>
> - *Add a Tax account code for Bad debts: Create a specific Tax account code for bad debts, such as "T2400-200 - VAT-Adjustments - Bad debts." This account should be included in the structure of your VAT/GST/Sales tax control account in the current liabilities section of your Chart of Accounts. This will allow you to track and report the VAT/GST/Sales tax adjustments related to bad debts separately.*
> - *Process the general journal to write off bad debts: When recording the write-off of bad debts in the general journal, select the appropriate Tax code for "Bad debts." This Tax code should be associated with the specific VAT/GST/Sales tax percentage and transactions applicable to bad debts. By selecting the appropriate Tax code, the system will calculate and allocate the VAT/GST/Sales tax amount accordingly.*
>
> *By following these steps, you can ensure that the VAT/GST/Sales tax implications of writing off bad debts are properly accounted for and reflected in your financial records and tax returns.*

10. Once you have edited your transactions, you need to finalize the batch:

- Balance the batch: Click F5: Balance to generate the balancing transactions to the contra

account.



- List the batch: Click F8: List to print a list of the unposted batch transactions in the batch. Review the list for any errors or discrepancies and make necessary edits before proceeding. This list may be retained for record and audit purposes.



11. Post the batch: Click F6: Post to post or update the transactions in the batch.

Disable debtor accounts - After processing and writing off bad debts that are uneconomical to recover, and considering them to be a credit risk, you have the option to disable their debtor account. By selecting the "Account disabled" option on the Accounting information tab, you can prevent any further processing and posting of transactions for that specific debtor.

By setting a debtor account as inactive or disabling it, you ensure that no additional transactions can be processed or posted for that particular debtor. This helps in managing credit risks and preventing additional financial exposure. It's important to note that all existing transactions and historical data related to the debtor will still be available in reports and other relevant areas of the osFinancials5/TurboCASH5 system.

Disabling debtor accounts provides an effective way to control credit risks and manage your accounts receivable effectively. By keeping inactive debtor accounts separate from active ones, you can easily identify and focus on those accounts that require attention or further action.

Please exercise caution when disabling debtor accounts and ensure that it aligns with your internal policies and procedures. Additionally, consider any legal or regulatory requirements that may affect the management and retention of debtor information.

Transactions in the ledger

The transactions is updated in all respective accounts and will be available in all reports for the accounts for the Debtor accounts and in the Bad debts expense account. These totals of the accounts will be reflected in the Trial balance in the Ledger analyser. The Debtors control account will reflect the transactions in the Balance sheet. The "*Bad debts*" expense account will be reflected on the Income statement.

T-Account viewer

In any of these report types in the Ledger analyser, you may double-click on an account or right-click and select the "*Show details*" option on the context menu. This will launch the T-Account viewer with the transaction details. You may print the transactions or export the transactions to a spreadsheet. An example of the transactions is as follows:



The T-Account viewer allows you to view transaction details for specific accounts. You can access it by double-clicking on an account or right-clicking and selecting the " *Show details*" option. In the T-Account viewer, you can double-click on the batch number, account code, or date to filter transactions.

Contra transactions are indicated by eight asterisks (********). The "*Show contra*" option displays the contra transactions. When printing the transactions the contra accounts will not be printed.

When exporting the transactions to a spreadsheet, the contra accounts will be included in column "*A*" if the "*Contra account*" option is selected.

Click on the Print button to print the transactions in the T-Account viewer.



In addition to launching the T-Account viewer from the Ledger analyser options, the T-Account viewer may also be launched separately on the Reports ribbon; or from the following options on the Default ribbon:

- *Search - Investigator - Account or Batch type searched items.*
- *Debtors - Transactions tab - Click on the Show transactions button.*
- *Creditors - Transactions tab - Click on the Show transactions button.*

By utilising the T-Account viewer and the reports in the Ledger Analyser, you can gain a detailed understanding of the transactions and their impact on the accounts involved.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Recovery of bad debts written-off

Recovery of bad debts written-off

There may be instances where previously written-off bad debts or irrecoverable debts are actually recovered. However, it's important to note that typically only a portion of the original amount of bad debts is recovered.

The recovery of bad debts written off refers to the process of collecting payments or receiving funds for debts that were previously deemed uncollectible and written off as losses by a business. When a business determines that a debt is unlikely to be recovered, it may choose to write off the debt as a bad debt expense, reducing the Accounts receivable (Debtor's control account) balance.

However, there are cases where the debtor later makes a payment or settles the debt, resulting in the recovery of the previously written-off amount. This recovery of bad debts written off represents the collection of funds that were once considered irrecoverable.

The recovery of bad debts written off is recorded as a separate transaction in the accounting records. It typically involves reversing the write-off entry and recognizing the recovered amount as income or reducing the provision for bad debts, depending on the accounting treatment chosen by the business.

This recovery process allows the business to improve its financial position by collecting previously uncollectible debts and potentially reducing the impact of bad debts on its financial statements.

Options to record the recovery of bad debts already written-off

To record the recovery of bad debts that have already been written off, you have several options:

1. Allocate the amount directly to the debtor's account: You can allocate the recovery amount directly to the debtor's account, which creates a credit balance in the account. This method reflects the specific debtor's account that has experienced the recovery and provides a clear record of the transaction.
2. Transfer the amount from the debtor's account to the Bad debts recovered account : After allocating the recovery amount to the debtor's account, you can then transfer the same amount from the debtor's account to a separate account called "*Bad Debts Recovered*." This transfer effectively clears the credit balance in the debtor's account and records the recovery as a current asset.
3. Use a specific income account: Alternatively, you can allocate the recovery amount directly to a designated income account such as "Bad debts recovered." This method treats the recovery as income, reflecting the increase in the financial resources of the business due to the recovery of previously written-off debts.

The choice of method depends on your specific accounting requirements and preferences. It's important to ensure that the chosen method accurately reflects the recovery of bad debts and provides a clear audit

trail of the transactions.

Options to record the recovery of bad debts already written-off

To record the recovery of bad debts that have already been written off, you have several options:

1. Allocate the amount directly to the Bad debts recovered account : You can allocate the recovery amount directly to the "*Bad Debts Recovered*" account since the debtor's account, should have a zero balance when the bad debts was written-off at the stage when the recovery of bad debts is collected. The "*Bad Debts Recovered*" account may be a current asset account or an income account, in your chart of accounts according to the accounting policies and principles that apply to your jurisdiction.
2. Transfer the amount from the Bad debts recovered account to the debtor's account : After allocating the recovery amount to a separate account called "*Bad Debts Recovered*" you can then transfer the same amount to the debtor's account. This will create a credit balance in the debtor's account. This method reflects the specific debtor's account that has experienced the recovery and provides a clear record of the transaction. This transfer effectively clears the credit balance in the "*Bad Debts Recovered*" account debtor's account and records the recovery as a current asset.

   After allocating the recovery amount to the debtor's account, you can then transfer the same amount from the debtor's account to a separate account called "*Bad Debts Recovered*." This transfer effectively clears the credit balance in the debtor's account and records the recovery as a current asset.
3. Use a specific income account: Alternatively, you can allocate the recovery amount directly to a designated income account such as "Bad debts recovered." This method treats the recovery as income, reflecting the increase in the financial resources of the business due to the recovery of previously written-off debts.

The choice of method depends on your specific accounting requirements and preferences. It's important to ensure that the chosen method accurately reflects the recovery of bad debts and provides a clear audit trail of the transactions.

Recovery of Bad debts to Debtor account

When recording the recovery of bad debts that have already been written off, the steps are generally applicable in most cases. However, the need for transferring the amount from the "*Bad Debts Recovered*" account back to the debtor's account depends on the specific circumstances and accounting practices of the business. Let's explore each option in more detail:

1. Allocate the amount directly to the "*Bad Debts Recovered*" account: In this approach, you directly allocate the recovery amount to the "*Bad Debts Recovered*" account. This method is straightforward and treats the recovery as income. The "*Bad Debts Recovered*" account could be a current asset account if

the business intends to use the funds for future operations, or it could be an income account if it represents recovered revenue. This option is generally suitable for cases where the debtor's account has been fully written off, and there is no need to update the debtor's account balance.

2. Transfer the amount from the "*Bad Debts Recovered*" account to the debtor's account: This option is appropriate when you want to reflect the recovery on the specific debtor's account. It involves allocating the recovery amount to the "*Bad Debts Recovered*" account initially and then transferring the same amount back to the debtor's account. This transfer creates a credit balance in the debtor's account, indicating that the debtor has paid off the recovered amount. The "*Bad Debts Recovered*" account will have a zero balance after the transfer.

Whether this step is necessary if the debtor has passed away, or the debtor is insolvent or liquidated, it depends on the accounting treatment followed by the business and the specific circumstances of the recovery. If the debtor is no longer alive or is insolvent or liquidated, and there is no likelihood of further transactions with the debtor, some businesses may choose to skip the transfer step and directly allocate the recovery amount to the "Bad Debts Recovered" account as income. In such cases, the recovery may be treated as a general income item and not associated with the individual debtor's account.

It is essential to consider the relevant accounting standards and regulations in your jurisdiction and consult with a qualified accountant or financial advisor to determine the best approach for recording the recovery of bad debts in your specific situation. Proper documentation and adherence to accounting principles are crucial to maintain accurate financial records and comply with relevant accounting and tax rules.

Sources of the recovery of bad debts written-off

Recovery of bad debts that have been previously written off can occur through various means, including:

1. Debt collector: The business may engage the services of a debt collection agency to recover the outstanding debt from the debtor. The debt collector will attempt to collect the debt on behalf of the business, and if successful, the recovered amount will be recorded in the Receipts journal.

2. Garnishee order: In some cases, the business may obtain a garnishee order from a court to collect the debt directly from the debtor's employer. The employer deducts the specified amount from the debtor's salary and pays it to the business, which is then recorded in the Receipts journal.

3. Insolvency or Liquidation: If the debtor becomes insolvent or is liquidated, the business may be able to recover a portion of the outstanding debt from the debtor's estate as part of the liquidation process. This recovery would also be recorded in the Receipts journal.

In all these cases, when the bad debts are recovered, the transaction should be allocated to the "*Bad debts recovered*" account to properly account for the amount received. Depending on the specific circumstances and any applicable taxes or adjustments, the business may need to take further accounting steps, such as

recording a tax adjustment or debiting the "*Bad debts recovered*" account and crediting the debtor account.

It's important for businesses to keep accurate records of all debt recovery transactions, as well as the methods used to recover the bad debts. Properly accounting for bad debt recoveries ensures that the financial statements accurately reflect the business's financial position and performance. As always, it's advisable to follow relevant accounting standards and consult with accounting or financial professionals if there are any uncertainties or complexities in the debt recovery process.

Estate distribution when a debtor passed away

In the case where a debtor has passed away, and their estate is distributing the debts, the process would typically involve the following steps:

1. Notification: The business should be notified of the debtor's passing and the appointment of an executor or administrator to handle the estate's affairs.
2. Verification: The executor or administrator of the estate will verify the outstanding debts owed by the deceased debtor to the business. This may involve reviewing records, invoices, and any existing agreements or contracts.
3. Agreement: Once the debts are verified, the executor or administrator may contact the business to agree on the settlement of the outstanding debts. This agreement will depend on the financial situation of the estate and the available assets to cover the debts.
4. Debt distribution: After reaching an agreement with the business, the executor or administrator will distribute the appropriate payments to the business for the outstanding debts. These payments will be recorded as receipts in the Receipts journal.
5. Recording transactions: The business should record the debt recovery transactions in its accounting records. The recovered amounts should be allocated to the "*Bad debts recovered*" account or the appropriate revenue or income account, depending on the nature of the debts.
6. Tax implications: Depending on the tax regulations in the relevant jurisdiction, there may be tax implications for both the estate and the business related to the debt recoveries. It's essential to follow the tax rules and properly account for any tax adjustments in the financial records.
7. Estate distribution: The executor or administrator will continue to distribute the remaining assets of the estate to the beneficiaries, following the deceased's will or the rules of intestacy if there is no will.

As with any financial transaction involving estates and legal matters, it is crucial for the business to work closely with the executor or administrator of the deceased debtor's estate and seek professional advice if needed. Proper documentation and record-keeping are vital during this process to ensure accurate accounting and compliance with legal and tax requirements.

Batch or Journal to process transactions for the recovery of bad debts written-off

The recovery of bad debts written off is typically recorded in the receipts journal when the money is received or deposited into the bank account. The receipts journal is used to record all incoming funds and their allocation to various accounts.

When a recovery of bad debts occurs, the business receives payment from the debtor or on behalf the debtor, and this payment is recorded in the receipts journal. The entry in the receipts journal will include the amount received, the debtor's account being credited (reducing the outstanding balance), and the account to which the recovered amount is allocated, such as the "*Bad debts recovered*" account or the debtor's account itself.

By recording the recovery in the receipts journal, it ensures that the transaction is properly documented and reflects the inflow of funds into the business. It also allows for accurate tracking of the recovered amounts and facilitates reconciliation with bank statements or other financial records.

Procedure for the recording of transactions for the recovery of bad debts

The procedure for entering receipt transactions for the recovery of bad debts:

1. Access the "*Batch entry*" screen by clicking on the Batch entry icon (or the Cash / Bank entry icon if you use the Bank import plugin) on the Default ribbon.
2. Select the "*Receipts journal*", ensuring you choose the correct journal if multiple bank accounts are involved.
3. Enter the recovery details, including the deposit number, transaction date, transaction details, and select the debtor account. If VAT/GST/Sales Tax was applicable when the original debt was written off, select the bad debt tax code. Enter the amount in the credit column.
4. Enter the amount received and deposited, including VAT/GST/Sales Tax, using the same reference numbers, and select the debtor account and the "*VAT/GST/Sales Tax - Bad debts*" tax code. Enter the amount in the credit column.
5. Enter the amount of bad debts recovered, excluding VAT/GST/Sales Tax, using the same reference numbers. Select the Other income account (Bad debts recovered), select the "*Empty*" option as the "*No Tax*" code, and enter the amount in the credit column.
6. To create the debit transaction to the debtor's account, use the same reference numbers, select the debtor account, select the "*Empty*" option as the "*No Tax*" code, and enter the amount (excluding

VAT/GST/Sales Tax). Since the Receipts Journal only allows a credit amount entry, enter a negative sign before typing the amount in the credit column. osFinancials5/TurboCASH5 will automatically transfer the amount to the debit column upon pressing Enter.

Once the transactions for the recovery of bad debts are entered in the receipts journal, they will be displayed accordingly. Use the F5:Balance icon or press F5 to list the batch, and osFinancials5/TurboCASH5 will generate balancing entries to the bank account and the Output VAT/GST/Sales Tax account, if applicable. It is advisable to overtype the default descriptions of these balancing entries for better traceability and reconciliation.

Finally, change the alias (batch name) using the F9:Process icon or pressing F9, list the batch using the F8:List icon or pressing F8, and post (update) the batch to the ledger using the F6:Post icon or pressing F6.

After posting the transactions, the T-Account viewer should reflect the appropriate changes in the Debtors ledger and General ledger. The debits and credits will be recorded for record purposes, and the VAT/GST/Sales Tax on bad debts should be submitted on the relevant tax return and paid to the tax authority.

To summarize the accounting equation for the recovery of bad debts written off:

Debits: Bank account

Credits: Bad Debts Recovered (Other Income account) + Output VAT/GST/Sales Tax

Debits: Current Assets Credits: Other Income + Current Liabilities (VAT/GST/Sales Tax)"

Please note that this is a general guide, and it's always recommended to consult with a professional accountant or financial advisor for specific accounting practices and procedures.

===

Example : Recovery of Bad debts already written off

Example: An amount of 1150 (including VAT at 15%) is written off.

To record the write-off of an amount of $1,150, including VAT at 15%, the example entry would depend on the specific accounts and tax codes used in your accounting system. However, here's a general example of the entry:

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Bad debts expense (excluding VAT)	*Expenses*	*$1,000*	

Debit: Bad debts Tax code (VAT)	*Current liabilities*	*$150*	
Credit: Debtor account	*Current assets*		*$1,150*

Example : Recovery of Bad debts with VAT/GST/Sales tax

To write off bad debts and clear the Debtors account with the amount of irrecoverable debts (including VAT/GST/Sales Tax), follow these steps:

1. Identify the irrecoverable Debtor account and ensure you have sufficient documentary evidence of attempts to collect the debt. Only proceed with write-off after exhausting all avenues.
2. If you are a registered VAT/GST/Sales Tax vendor, identify the Interest amount and the VAT/GST/Sales Tax amount of the Output Tax already paid to the Tax Authorities in a previous Tax period. This is important to verify the correct VAT/GST/Sales Tax amount.

When writing off bad debts for debtor accounts on which output tax was paid to the tax authorities in a previous tax period, you may need to consider the VAT/GST or sales tax implications. However, the specific steps and requirements may vary depending on the jurisdiction and tax regulations.

Here are some general considerations:

1. *Create a Tax code: In osFinancials5/TurboCASH5, you may need to create a specific tax code or sub-account in the Setup → Accounts - Tax account type (Setup ribbon) to account for the VAT/GST or sales tax related to bad debts.*
2. *Write-off process: When writing off bad debts, you would typically credit the debtor's account with the amount of the irrecoverable debts (inclusive of VAT/GST/sales tax), debit the bad debts expense account (exclusive of VAT/GST/Sales tax), and debiting the Bad debts tax code with the VAT/GST/Sales tax amount.*
3. *Tax Return and Adjustments: The VAT/GST/sales tax amount associated with the bad debts write-off needs to be considered for the tax return. It may be reported as a tax adjustment or a deduction on the VAT/GST/Sales tax return. The specific reporting block or line may vary depending on the tax jurisdiction. By reducing the taxable amount on the return, it can potentially lower the amount payable to the tax authority.*

It's important to consult with a tax professional or refer to the tax regulations specific to your jurisdiction to ensure compliance with the VAT/GST or sales tax requirements when writing off bad debts and handling the associated tax implications.

Interest amount - Identifying the interest amount, it typically refers to determining the portion of the outstanding debt that represents interest charges.

When dealing with bad debts or debt write-offs, it's important to consider any interest charges that may have been applied to the outstanding debt. In some cases, businesses may charge interest on overdue payments, and this interest may be subject to VAT/GST or sales tax depending on the applicable regulations in your jurisdiction.

By identifying the interest amount, you can ensure that the correct VAT/GST/sales tax amount is calculated and accounted for when writing off the bad debts. This helps in accurately determining the tax implications and complying with the tax regulations specific to your VAT/GST/sales tax system.

It's important to consult with a tax professional or refer to the tax regulations in your jurisdiction to understand the specific requirements and treatment of interest charges in relation to VAT/GST/sales tax.

3. Write off the Bad Debts in the General journal.

Example: An amount of 1,150 (including VAT at 15%) is written off.

Procedure to process the recovery bad debts written off for a debtor account:

1. In osFinancials5/TurboCASH5 navigate to the Default ribbon.
2. Select "*Batch entry*" and choose the "*Receipts journal*" for the bank account into which the monies were received.



3. Batch setup: Since this is a general journal that may be used for other general transactions, click F10: Setup to set the "*Options for this bath*" as follows:

    a) Standard tab - "*Contra account*" select the "*Bad debts*" expense account.



b) Advanced tab - Select the following options:



- Account lookup type - Select "*Debtors*" to only list the debtor accounts in the lookup.
- Contra account lookup type - Select "*General ledger*" to only list the general ledger account as the contra account for the balancing entries or transactions.
- Leave the rest of the settings as in the options for this batch as in the screenshots, and click OK to save your settings.

4. Change alias: By default the name of the journal is displayed as "*General journal - [General journal]*"

To make it easy to identify the specific nature of the transactions in the General journal, enter a unique name for your specific requirements, in the "*Change alias field*" and press Enter. In this example the "*Bad debts-Green*" was entered. This will change the general journals name as name of the journal is displayed as "*General journal - [Bad debts-Green]*" in the titlebar It indicates that "*Bad debts for Debtor Green*" was processed in the general journal.

5. Enter the transactions for the bad-debts:

   - Date: By default, the date of your operating system would be displayed. Select the specific date on which you need to write off the debt.
   - Reference: The default reference in a new General journal would be "*1*" . In the case of a previous processed transactions, the Description could be the related to the last reference used. Enter a valid reference.
   - Description: Enter a description for each transaction for your own requirements. In this example, the description is changed to "*Write-off bad debts -AB Green IN000005*" Note: The descriptions should make sense to understand the nature of the transactions.
   - Debtors (Accounts): Select the account of the debtor for which you need to write-off bad debts.
   - Tax: Select the VAT/GST.Sales tax code for bad debts if applicable to your jurisdiction.

VAT/GST/Sales tax - Writing off of bad debts:

It is important to note that the specific tax rules and regulations regarding bad debt write-offs can vary, and it's advisable to consult with a tax professional or refer to the tax laws in your jurisdiction to determine the exact requirements and treatment of VAT/GST/Sales tax in relation to writing off uneconomical bad debts.

If VAT/GST/Sales tax is applicable on the writing off of bad debts, you can follow the steps below to ensure proper recording and allocation of the tax:

- *Add a Tax account code for Bad debts: Create a specific Tax account code for bad debts, such as "T2400-200 - VAT-Adjustments - Bad debts." This account should be included in the structure of your VAT/GST/Sales tax control account in the current liabilities section of your Chart of Accounts. This will allow you to track and report the VAT/GST/Sales tax adjustments related to bad debts separately.*
- *Process the general journal to write off bad debts: When recording the write-off of bad debts in the general journal, select the appropriate Tax code for "Bad debts." This Tax code should be associated with the specific VAT/GST/Sales tax percentage and transactions applicable to bad debts. By selecting the appropriate Tax code, the system will calculate and allocate the VAT/GST/Sales tax amount accordingly.*

By following these steps, you can ensure that the VAT/GST/Sales tax implications of writing off bad debts are properly accounted for and reflected in your financial records and tax returns.

- Credit: Enter the amount in the credit column. If the VAT/GST/Sales tax code for bad debts was selected, it will automatically generate the VAT/GST/Sales tax percentage when balancing entries are generated.

7. After entering the write off transaction in the General journal should be displayed as follows:



Open item selection: The "Open item selection" screen will be launched for debtors whose accounts are set as Open item accou debts to be written off against specific transactions or invoices.



After selecting or linking the Bad-debts write-off transaction to an outstanding transactions, the transaction line will be displa

In this example, the bad debts expense account is debited with the amount of $1,000, representing the irrecoverable debt excluding VAT. The bad debts tax code account is debited with the VAT amount of $150. The debtor account is credited with the total amount of $1,150 to clear the outstanding debt.

Please note that the specific accounts and tax codes may vary based on your accounting system and local tax regulations. It's important to consult with a tax professional or refer to the guidelines provided by your tax authority to ensure accurate and compliant recording of write-offs including VAT/GST/sales tax.

Here's the revised entry:

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Debtor account	*Current assets*	*$1,150*	
Credit: Bad debts recovered	*Current assets*		*$1.000*
Credit: Bad debts - Tax code (VAT/GST/Sales tax)	*Current liabilities*		*$150*

Using the "Bad Debts Recovered" account helps maintain proper accounting records and provides better visibility of the recovered amount specifically related to bad debts.

===

If an amount of 1150, including VAT at 15%, is written off in a previous year and the full amount is subsequently recovered, the example entry would depend on the specific accounts and tax codes used in your accounting system. However, here's a general example of the entry:

1. Reversal of Write-off Entry: Debit: Debtor Account - 1000 Debit: VAT/GST/Sales Tax Control Account -

150 Credit: Bad Debts Expense (excluding VAT) - 1000 Credit: Bad Debts Tax Code (VAT) - 150

In this entry, the debtor account is debited with the full amount of 1150 to reverse the previous write-off. The VAT/GST/Sales Tax control account is also debited with the VAT amount of 150. The bad debts expense account (excluding VAT) is credited with 1000, and the bad debts tax code account (VAT) is credited with 150 to reverse the initial write-off entries.

2. Recovery of Debt Entry: Debit: Debtor Account - 1150 Credit: Revenue/Sales Account - 1000 Credit: VAT/GST/Sales Tax Control Account - 150

In this entry, the debtor account is debited with the recovered amount of 1150. The revenue/sales account is credited with the original amount excluding VAT (1000), and the VAT/GST/Sales Tax control account is credited with the VAT amount of 150.

Please note that these entries are general examples, and you should consult with a professional accountant or refer to the guidelines provided by your accounting software to ensure accurate recording of the recovery of a previously written-off amount, including VAT/GST/sales tax.

===

"Cashbook Line:125 Desc:Payment AB Green Recover bad debts Cannot use 2400-200 on a debtors creditors bank or other tax account!"

===

In osFinancials5/TurboCASH5, when recovery of bad debts already written off transaction is recorded in the receipts journal and tax is applicable you cannot select a debtor account with a tax. This will render an error message = "Cashbook Line:125 Desc:Payment AB Green Recover bad debts Cannot use 2400-200 on a debtors creditors bank or other tax account!"

In osFinancials5/TurboCASH5, the error message "Cashbook Line:125 Desc:Payment AB Green Recover bad debts Cannot use 2400-200 on a debtors creditors bank or other tax account!" indicates that there is an issue with selecting a tax account for a debtor account when recording a recovery of bad debts transaction in the receipts journal.

This error message occurs because tax accounts, such as 2400-200 in this case, are generally not allowed to be used on debtor or creditor accounts. Tax accounts are typically reserved for specific tax-related transactions and should not be linked to debtor or creditor accounts directly.

To resolve this issue and record the recovery of bad debts transaction correctly, you need to ensure that you are selecting the appropriate accounts for the transaction. Here's what you can do:

1. Identify the correct accounts: When recording a recovery of bad debts, you should select the relevant debtor account (AB Green in this case) for the receipt entry. The receipt entry should represent the amount received from the debtor to recover the previously written-off bad debt.

2. Use a regular income or bank account: For the transaction's account selection, use a regular income account or bank account (depending on how the money is received) instead of a tax account. The receipt of the recovered amount should be posted to an appropriate income or bank account to reflect the recovery.

3. Adjust the tax appropriately: If tax is applicable to the recovered amount, you should handle the tax calculation separately. Depending on your tax setup and regulations, you may need to calculate and account for the tax amount separately from the receipt entry.

By following these steps and selecting the correct accounts for the recovery of bad debts transaction, you should be able to avoid the error message and accurately record the transaction in osFinancials5/TurboCASH5. If you are unsure about how to handle tax-related transactions or if you encounter any difficulties, it's recommended to consult with your accounting or tax professional for specific guidance based on your company's setup and applicable tax regulations.

===

When recovery of bad debts is recorded in the Receipts journal, the transaction including the transaction should be allocated to the "Bad debts recovered account" Then I think need to decide whether to do further business with the debtor, unblock the account (is account is blocked /disabled) then have the option to record a transaction to debit "Bad debts recovered account" and credit the bad debts tax account and credit the debtor account?

Yes, you are correct. When recording the recovery of bad debts in the Receipts journal, the transaction should be allocated to the "Bad debts recovered account" to properly account for the amount received for the previously written-off bad debt.

After recording the recovery of bad debts and allocating it to the "*Bad debts recovered*" account, you have several options to handle the further business with the debtor:

1. Unblock the debtor account: If the debtor's account was previously blocked or disabled due to the bad debt, you can unblock the account after the recovery. This will allow you to continue doing business with the debtor.

2. Record a separate transaction: If you decide to do further business with the debtor and want to settle the recovered bad debt, you can record a separate transaction to debit the "*Bad debts recovered*" account and credit the debtor account. This will offset the recovery amount against the bad debt, showing that the bad debt has been fully settled.

3. Record a tax adjustment: If tax was applicable to the recovered bad debt, you can also record a tax adjustment separately. Depending on your tax regulations and setup, you may need to credit the bad debts tax account and debit the appropriate tax liability account to account for the tax amount.

By taking these steps, you can ensure that the recovery of bad debts is properly accounted for and that

your debtor accounts reflect the accurate financial position after the recovery. As always, it's essential to follow proper accounting practices and comply with relevant tax regulations when handling bad debts and their recovery. If you have any specific questions or uncertainties regarding the accounting treatment, it's advisable to consult with your accounting or financial advisor for guidance tailored to your business's individual circumstances.

===

In osFinancials5/TurboCASH5, when recovery of bad debts already written-off transaction is recorded in the receipts journal and tax is applicable you cannot select a debtor account with a tax. This will render an error message = "Cashbook Line:125 Desc:Payment AB Green Recover bad debts Cannot use 2400-200 on a debtors creditors bank or other tax account!"

In osFinancials, the error message

> "Cashbook Line:125 Desc:Payment AB Green Recover bad debts Cannot use 2400-200 on a debtors creditors bank or other tax account!"

indicates that there is an issue with selecting a tax account for a debtor account when recording a recovery of bad debts transaction in the receipts journal.

This error message occurs because tax accounts, such as 2400-200 in this case, are generally not allowed to be used on debtor or creditor accounts. Tax accounts are typically reserved for specific tax-related transactions and should not be linked to debtor or creditor accounts directly.

To resolve this issue and record the recovery of bad debts transaction correctly, you need to ensure that you are selecting the appropriate accounts for the transaction. Here's what you can do:

Identify the correct accounts: When recording a recovery of bad debts, you should select the relevant debtor account (AB Green in this case) for the receipt entry. The receipt entry should represent the amount received from the debtor to recover the previously written-off bad debt.

Use a regular income or bank account: For the transaction's account selection, use a regular income account or bank account (depending on how the money is received) instead of a tax account. The receipt of the recovered amount should be posted to an appropriate income or bank account to reflect the recovery.

Adjust the tax appropriately: If tax is applicable to the recovered amount, you should handle the tax calculation separately. Depending on your tax setup and regulations, you may need to calculate and account for the tax amount separately from the receipt entry.

By following these steps and selecting the correct accounts for the recovery of bad debts transaction, you should be able to avoid the error message and accurately record the transaction in osFinancials5/TurboCASH5. If you are unsure about how to handle tax-related transactions or if you

encounter any difficulties, it's recommended to consult with your accounting or tax professional for specific guidance based on your company's setup and applicable tax regulations.

===

When recovery of bad debts is recorded in the Receipts journal, the transaction including the transaction should be allocated to the "Bad debts recovered account" Then I think need to decide whether to do further business with the debtor, unblock the account (is account is blocked /disabled) then have the option to record a transaction to debit "Bad debts recovered account" and credit the bad debts tax account and credit the debtor account?

Yes, you are correct. When recording the recovery of bad debts in the Receipts journal, the transaction should be allocated to the"*Bad debts recovered*" account to properly account for the amount received for the previously written-off bad debt.

After recording the recovery of bad debts and allocating it to the "*Bad debts recovered*" account you have several options to handle the further business with the debtor:

1. Unblock the debtor account: If the debtor's account was previously blocked or disabled due to the bad debt, you can unblock the account after the recovery. This will allow you to continue doing business with the debtor.
2. Record a separate transaction: If you decide to do further business with the debtor and want to settle the recovered bad debt, you can record a separate transaction to debit the "Bad debts recovered account" and credit the debtor account. This will offset the recovery amount against the bad debt, showing that the bad debt has been fully settled.
3. Record a tax adjustment: If tax was applicable to the recovered bad debt, you can also record a tax adjustment separately. Depending on your tax regulations and setup, you may need to credit the bad debts tax account and debit the appropriate tax liability account to account for the tax amount.

By taking these steps, you can ensure that the recovery of bad debts is properly accounted for and that your debtor accounts reflect the accurate financial position after the recovery. As always, it's essential to follow proper accounting practices and comply with relevant tax regulations when handling bad debts and their recovery. If you have any specific questions or uncertainties regarding the accounting treatment, it's advisable to consult with your accounting or financial advisor for guidance tailored to your business's individual circumstances.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Provision for Bad debts

What is provision for bad debts?

Provision for bad debts, also known as an allowance for doubtful accounts or provision for credit losses, is an accounting concept that involves estimating and setting aside an amount of money to cover potential losses from customers' unpaid debts. It is a financial provision made by a company to account for the possibility that some portion of its accounts receivable may not be collectible.

The provision for bad debts is created to reflect the expected credit losses in a company's financial statements. It is based on the principle of conservatism, which states that companies should recognise potential losses as soon as they are probable, but not necessarily wait until they are certain.

The provision for bad debts is typically determined by considering factors such as the creditworthiness of customers, historical collection patterns, ageing of accounts receivable, economic conditions, industry trends, and any specific circumstances that may affect the collectability of outstanding debts.

Creating a provision for bad debts allows the company to match anticipated losses with the revenue earned in the same accounting period, ensuring a more accurate representation of the company's financial position and performance.

The provision for bad debts is reported as an expense on the income statement, reducing the company's profit and taxable income. It is also presented as a contra-asset on the balance sheet, offsetting the accounts receivable to reflect the net realizable value.

By establishing a provision for bad debts, companies demonstrate prudence in recognising and accounting for potential credit losses, improving the accuracy and reliability of their financial statements. It also helps in assessing the true value of accounts receivable and evaluating the overall credit risk of the business.

Summary of key points for provision of bad debts

The outline for the process of creating a provision for bad debts or doubtful debts in your accounting practices, is as follows:

1. Identifying irrecoverable debts: Before calculating the provision for bad debts, it is important to identify the debts that are deemed irrecoverable and should be written off as bad debts. This assessment helps separate the debts that are unlikely to be collected from those that still have a chance of recovery.
2. Methods for calculating the provision for bad debts:
    - Age analysis schedules: One method is to estimate or calculate the provision based on the age analysis schedules of your debtor accounts. This involves categorizing outstanding debts

by their age and applying specific percentages or rates based on historical data or industry norms.

- Total outstanding debt: Another method is to base the provision on the total outstanding debt, considering factors such as the overall creditworthiness of your customers and any specific risks associated with certain accounts.
- Total credit sales: You can also calculate the provision based on the total sales made on credit, taking into account the historical percentage of bad debts experienced in relation to credit sales.

3. Revising the provision for bad debts amount: In subsequent years, it is necessary to review and revise the provision amounts established in previous years. Changes may be required to increase or decrease the provision based on changes in credit sales, outstanding debts, economic conditions, or other relevant factors. Consistency in the chosen method is essential to ensure accurate and comparable provisions across different periods.
4. Impact on Income statement: The provision for bad debts or doubtful debts directly affects the Income Statement (Profit or Loss) of your business. It represents an expense incurred to account for potential losses from irrecoverable debts and reflects the prudent recognition of these risks in your financial statements.

By following these procedures and consistently applying the chosen method for calculating provisions, you can ensure the accuracy of your financial reporting and reflect the potential impact of bad debts on your business's profitability. It is recommended to consult with an accounting professional or adhere to accounting standards and regulations applicable in your jurisdiction to ensure compliance and accuracy in recording provisions for bad debts.

What is the frequency for provision for bad debts?

The frequency for creating a provision for bad debts can vary depending on the company's accounting policies and the specific circumstances. There is no fixed rule or standard frequency mandated by accounting regulations such as IFRS (International Financial Reporting Standards) or GAAP (Generally Accepted Accounting Principles).

Typically, the provision for bad debts is established at the end of the accounting period, which is usually annually for most companies. It is common for companies to review their accounts receivable and estimate the potential losses at the end of each financial year. This allows them to adjust the provision based on the ageing of the debts and changes in the creditworthiness of customers.

However, some companies may choose to review and update the provision more frequently, such as semi-annually, quarterly, or even on a monthly basis. This can be particularly relevant for businesses with higher

credit risk customers or industries where payment delays or defaults are more prevalent.

The frequency of provisioning is determined by factors such as the nature of the business, the volume and credit terms of sales, historical collection patterns, economic conditions, and the accuracy of credit risk assessments. It is important for companies to maintain consistency in their approach to provisioning and ensure that it aligns with their financial reporting policies and requirements.

Ultimately, the frequency of provisioning for bad debts should strike a balance between timely recognition of potential losses and the practicality of assessing and estimating the credit risk on a regular basis.

How is Provision for bad debts calculated?

Common approaches to provision of bad debts

The provision for bad debts is typically calculated by estimating the amount of accounts receivable that is expected to become uncollectible. This provision is created to account for the possibility of customers defaulting on their payment obligations. While the exact calculation method may vary depending on the company's specific policies and circumstances, here are a few commonly used approaches:

1. Ageing analysis: This method involves categorizing accounts receivable based on their age and assessing the likelihood of collection for each category. Typically, the older the debt, the higher the probability of it becoming uncollectible. The company assigns specific percentages or rates of uncollectibility to each age category and applies them to the corresponding outstanding balances to calculate the provision.
2. Percentage of total receivables: Under this approach, a predetermined percentage is applied to the total accounts receivable balance to estimate the provision. The percentage used may be based on historical data, industry averages, or management's judgment.
3. Specific analysis: In certain cases, a company may individually evaluate each customer account to determine the likelihood of non-payment. Factors such as the customer's payment history, financial condition, and creditworthiness are considered to estimate the provision for each specific account.
4. Historical loss rate: This method involves analysing historical bad debt write-offs over a certain period and applying the average loss rate to the current outstanding balances. The historical loss rate can be calculated by dividing the total bad debts written off in a specific period by the total credit sales for the same period.

It's important to note that the provision for bad debts is an estimate and may require periodic adjustments as actual collection experience differs from initial expectations. The specific calculation method chosen should be based on sound judgment, consistent application, and adherence to applicable accounting standards and regulations.

Common methods for calculation of provision for bad debts

The provision for bad debts is calculated based on the total outstanding debtors' balances. Before calculating the provision, it's necessary to identify and write off any irrecoverable bad debts that may have occurred throughout the financial year.

Typically, the provision for bad debts is established at the end of the financial year before closing the books. However, it's important to review and adjust the provision from year to year. This may involve increasing or decreasing the provision based on changes in circumstances.

There are three common methods for calculating the provision for bad debts or doubtful debts:

1. Age analysis: This method involves analysing the age of outstanding debtor accounts and estimating the provision based on different age categories. Typically, older debts have a higher probability of becoming uncollectible, so higher provision rates are applied to those categories.
2. Total outstanding debt: This method estimates the provision based on the total amount of outstanding debt owed by customers. A certain percentage or rate is applied to the total outstanding balance to calculate the provision.
3. Total credit sales: This method estimates the provision based on the total sales made on credit. A percentage or rate is applied to the total credit sales to determine the provision amount.

These methods are commonly used, and the choice of which method to use may depend on various factors such as the company's industry, historical collection data, and management's judgment. It's important to note that companies may also use a combination of these methods or other approaches based on their specific circumstances.

Creating a provision for bad debts signifies that a business has encountered difficulties in collecting funds from its debtors. It is an accounting practice to anticipate and account for potential losses due to non-payment or uncollectible debts.

When it comes to writing off bad debts or before doing so, it is indeed important to have proper documentation and evidence of the collection efforts made. These records serve as documentation of the business's attempts to recover the outstanding amounts and support the decision to write off the debts as uncollectible. This documentation may be required by tax authorities for various purposes, including income tax, VAT/GST/sales tax reporting, and other regulatory requirements.

Maintaining proper documentation helps ensure transparency, compliance with accounting standards, and accurate financial reporting. It is advisable for businesses to establish clear policies and procedures regarding the documentation of collection efforts and the process of writing off bad debts to maintain the integrity of their financial records.

In larger business entities, the provision for bad debts or doubtful debts may be calculated on a regular

basis, such as monthly or every six months. However, most businesses typically calculate the provision on an annual basis.

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Provision for bad debts - Calculation methods

After calculating the amount using your preferred method, the next step is to create a provision for bad debts. In subsequent years or accounting periods, you will need to adjust the provision by either increasing or decreasing it based on the circumstances.

Adjusting the provision for bad debts allows for the recognition of changes in the expected collectability of outstanding debts. If the creditworthiness of debtors deteriorates or there are indications that certain debts may not be recoverable, it may be necessary to increase the provision. On the other hand, if there are improvements in the collectability of outstanding debts, a decrease in the provision may be warranted.

Regularly reviewing and adjusting the provision for bad debts ensures that it accurately reflects the potential losses from uncollectible debts. This adjustment is essential for reporting purposes and helps maintain the integrity of your financial statements.

Method 1: Calculation based on Age analysis schedules

To calculate the provision for bad debts, you can begin by analysing the outstanding balances of your debtors based on the ageing periods for which these debts are outstanding. This analysis requires age analysis schedules or an age analysis report.

In osFinancials5/TurboCASH5, the ageing analysis report is particularly useful if you utilize the open item feature for debtor accounts and have resolved any disputes and correctly linked transactions.

Opening balances - If you are a new user of osFinancials5/TurboCASH5 and have recorded debtor account balances for each period when entering opening balances, you can generate a Debtor Age analysis report to base your calculations on. However, if this data is not available in osFinancials5/TurboCASH5, you will need to obtain the Debtors Age analysis schedules from your previous accounting system.

Follow these steps to calculate the provision using the Debtors Age analysis reports in osFinancials5/TurboCASH5:

1. In osFinancials, navigate to Age analysis on the Reports ribbon or the Open item link option (Due tab) on the Default ribbon. You may also print age analysis reports from the Reports → Debtors → Age analysis menu.

2. Select all your debtors and set the Date of ageing as the last day of the period you want to use for the totals, typically the last day of your financial year.
3. Click the Print or OK buttons to generate the Debtors age analysis report.

The report will display the outstanding balances categorised by ageing periods, such as current, 30 days, 60 days, and 90 days. Each balance should be considered individually, with particular attention given to accounts with the longest outstanding balances. Calculating the percentages of the ageing periods in relation to the total transactions can provide guidelines for your calculations.

Based on this age analysis, you can identify doubtful debts. The list of doubtful debts will then be used to create or adjust the provision for bad debts.

If you have accounting records from a previous system that do not include debtor accounts for each outstanding period in osFinancials, you can refer to your old accounting records to find the Debtors Age analysis schedule (summary).

Method 2: Calculation based on Credit sales

This method is useful when you have identified a trend, such as an average of 2% of the total credit sales over the past two years being bad debts. To calculate the provision for bad debts using this method, multiply the total credit sales for a specific financial year or accounting period by the estimated percentage. For example, if the total credit sales amount to $100,000, the provision for bad debts would be $2,000 (2% of $100,000).

Please note that this method provides a simple calculation or estimation for the provision for bad debts but does not consider the specific amounts owed by individual debtors.

This calculation for doubtful debts will then be used to create or adjust the provision for bad debts.

Method 3: Calculation based on Total outstanding debt

You can also use the summarised information from the age analysis schedule or report to calculate or estimate the provision for bad debts.

Take the list of outstanding debt totals for each period and add an estimated percentage for the bad debts likely to be irrecoverable. These percentages are typically determined based on trends of past bad debts written off for debts in each of these ageing periods.

For example, if the trend shows 1% for the current period, 2% for debts older than 30 days, 5% for debts older than 60 days, and approximately 10% of outstanding debts are likely to become irrecoverable, the provision for bad debts would amount to $800.

Please keep in mind that these percentages may vary depending on the nature of your business, and

implementing better credit control and debt collection practices can help reduce these percentages.

This calculation for doubtful debts will then be used to create or adjust the provision for bad debts.

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

Create Provision for Bad Debts

In osFinancials5/TurboCASH5, the batch or journal type typically used to write-off bad debts and create or adjust provisions for bad debts is the "*General journal*" type. The General journal allows for manual entry of various accounting transactions, including those related to bad debts.

When writing off bad debts, you would make a journal entry in the General journal to debit the Bad debt expense account and credit the Debtor or Accounts receivable account. This effectively removes the uncollectable debt from the debtor's account and recognizes the expense associated with the bad debt.

To create a provision for bad debts or adjust an existing provision, you would also use the General journal. The specific accounts involved may vary based on your accounting practices, but typically you would debit the Provision for bad debts account and credit the Provision Reversal account.

It's important to consult with an accountant or follow the accounting standards and guidelines applicable in your jurisdiction when determining the appropriate accounts and entries for writing off bad debts and creating or adjusting provisions.

The provided information outlines the process of creating a provision for bad debts or doubtful debts in your accounting practices. Here's a summary of the key points:

1. Identifying Irrecoverable Debts: Before calculating the provision for bad debts, it is important to identify the debts that are deemed irrecoverable and should be written off as bad debts. This assessment helps separate the debts that are unlikely to be collected from those that still have a chance of recovery.
2. Methods for Calculating the Provision:
    - Age Analysis Schedules: One method is to estimate or calculate the provision based on the age analysis schedules of your debtor accounts. This involves categorizing outstanding debts by their age and applying specific percentages or rates based on historical data or industry norms.
    - Total Outstanding Debt: Another method is to base the provision on the total outstanding

debt, considering factors such as the overall creditworthiness of your customers and any specific risks associated with certain accounts.

- Total Credit Sales: You can also calculate the provision based on the total sales made on credit, taking into account the historical percentage of bad debts experienced in relation to credit sales.

3. Revising the Provision Amount: In subsequent years, it is necessary to review and revise the provision amounts established in previous years. Changes may be required to increase or decrease the provision based on changes in credit sales, outstanding debts, economic conditions, or other relevant factors. Consistency in the chosen method is essential to ensure accurate and comparable provisions across different periods.
4. Impact on Income Statement: The provision for bad debts or doubtful debts directly affects the Income Statement (Profit or Loss) of your business. It represents an expense incurred to account for potential losses from uncollectible debts and reflects the prudent recognition of these risks in your financial statements.

By following these procedures and consistently applying the chosen method for calculating provisions, you can ensure the accuracy of your financial reporting and reflect the potential impact of bad debts on your business's profitability. It is recommended to consult with an accounting professional or adhere to accounting standards and regulations applicable in your jurisdiction to ensure compliance and accuracy in recording provisions for bad debts.

Creating a Provision for Bad Debts

When your business completes its first year or when you implement an accounting policy, it is important to create a provision for bad debts or doubtful debts.

Before estimating or calculating the provision for bad debts, it is necessary to identify the debts that are irrecoverable and should be written off as bad debts.

You can calculate the provision using the following methods:

1. Estimates or calculations based on the age analysis schedules of your debtor accounts.
2. Estimates or calculations based on the total outstanding debt.
3. Estimates or calculations based on the total credit sales.

In subsequent years, it is important to review and adjust the provision made in the previous year. This may involve increasing or decreasing the amount of the provision.

It is crucial to maintain consistency in the method used for calculating the provision in consecutive years. This ensures that the provisions are aligned with any fluctuations in credit sales and outstanding debts. The

provision will have an impact on your Income Statement (Profit or Loss).

What is the transactions to create provision for bad debts in the general journal?

To create a provision for bad debts in the general journal, you typically need to make an adjusting entry at the end of an accounting period. The specific transactions involved will depend on the method used to calculate the provision. Here are three common methods and the corresponding journal entries:

Age Analysis Schedules Method:

Debit: Bad Debts Expense

Credit: Provision for Bad Debts

To record the provision based on age analysis schedules, you need to estimate the amount of bad debts and create a provision accordingly. The Bad Debts Expense account is debited to recognize the expense, and the Provision for Bad Debts account is credited to increase the provision amount.

Total Outstanding Debt Method:

Debit: Bad Debts Expense

Credit: Provision for Bad Debts

When calculating the provision based on the total outstanding debt, you estimate a percentage of outstanding debts that are likely to be irrecoverable. The Bad Debts Expense account is debited to recognize the expense, and the Provision for Bad Debts account is credited to increase the provision amount.

Total Sales on Credit Method:

Debit: Bad Debts Expense

Credit: Provision for Bad Debts

If you use the total sales on credit method, you estimate a percentage of credit sales that will become bad debts. The Bad Debts Expense account is debited to recognize the expense, and the Provision for Bad Debts account is credited to increase the provision amount.

These entries recognize the provision for bad debts as an expense on the income statement and create a corresponding liability (provision) on the balance sheet. The specific amounts will depend on the estimates made using the chosen method.

It's important to consult with an accountant or follow the specific guidelines of your accounting system to ensure accurate recording of provision for bad debts in the general journal.

What is the transactions to adjust a decrease in the provision for bad debts in the general journal?

To adjust a decrease in the provision for bad debts in the general journal, you need to make an adjusting entry. The specific transactions involved will depend on the reason for the decrease. Here are two common scenarios and the corresponding journal entries:

1. Recovery of Previously Written-off Debt:

   Debit: Provision for Bad Debts

   Credit: Accounts Receivable

   When a previously written-off debt is recovered, you reduce the provision for bad debts and reinstate the accounts receivable. The Provision for Bad Debts account is debited to decrease the provision, and the Accounts Receivable account is credited to reflect the recovery of the debt.

2. Reassessment of Bad Debts:

   Debit: Provision for Bad Debts

   Credit: Bad Debts Expense

If you reassess the likelihood of certain debts becoming irrecoverable and determine that a lower provision is required, you need to adjust the provision for bad debts. The Provision for Bad Debts account is debited to decrease the provision, and the Bad Debts Expense account is credited to reflect the reduction in the expense.

It's important to note that adjusting the provision for bad debts involves decreasing the provision amount and adjusting the corresponding accounts accordingly. The specific amounts will depend on the circumstances and reassessment made.

Consulting with an accountant or following the guidelines of your accounting system is advisable to ensure accurate recording of the adjustment for a decrease in the provision for bad debts in the general journal.

What is the transactions to adjust a increase in the provision for bad debts in the general journal?

To adjust an increase in the provision for bad debts in the general journal, you need to make an adjusting entry. The specific transactions involved will depend on the reason for the increase. Here are two common scenarios and the corresponding journal entries:

Increased Estimate of Bad Debts:

Debit: Bad Debts Expense

Credit: Provision for Bad Debts

If you reassess the likelihood of certain debts becoming irrecoverable and determine that a higher provision is required, you need to adjust the provision for bad debts. The Bad Debts Expense account is debited to recognize the increased expense, and the Provision for Bad Debts account is credited to reflect the higher provision.

Addition of New Bad Debts:

Debit: Bad Debts Expense

Credit: Provision for Bad Debts

When you identify specific debts that are considered bad or doubtful and need to be included in the provision, you record the expense associated with these new bad debts. The Bad Debts Expense account is debited, and the Provision for Bad Debts account is credited to increase the provision.

It's important to note that adjusting the provision for bad debts involves increasing the provision amount and adjusting the corresponding accounts accordingly. The specific amounts will depend on the circumstances and reassessment made.

Consulting with an accountant or following the guidelines of your accounting system is advisable to ensure accurate recording of the adjustment for an increase in the provision for bad debts in the general journal.

Created with the Standard Edition of HelpNDoc: Keep Your PDFs Safe from Unauthorized Access with These Security Measures

Decrease Provision for Bad Debts

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Increase Provision for Bad Debts

Created with the Standard Edition of HelpNDoc: 5 Reasons Why a Help Authoring Tool is Better than Microsoft Word for Documentation

Depreciation

Depreciation : Accounting standards and Accounting method

Depreciation is applicable to both small and medium entities (SMEs) and larger entities following International Financial Reporting Standards (IFRS), including IFRS (full) and IFRS for SMEs.

Under IFRS (full) and IFRS for SMEs, entities are required to account for depreciation of their tangible assets. Depreciation is considered an important aspect of financial reporting as it helps to accurately present the financial position and performance of an entity by allocating the cost of assets over their useful lives.

As for the accounting method, depreciation is primarily associated with the accrual-based accounting method. In accrual accounting, expenses are recognized when incurred, and revenues are recognized when earned, regardless of the timing of cash flows. Depreciation is recorded as an expense over the asset's useful life, even if the cash outflow for the asset's acquisition occurred in a different accounting period.

On the other hand, the cash-based accounting method does not typically involve the recognition of depreciation. Cash-based accounting recognizes revenues and expenses when cash is received or paid, respectively, rather than when they are earned or incurred. Since depreciation is a non-cash expense, it is not recognized in the cash-based accounting method.

However, it's important to note that entities following the cash-based accounting method may still be required to account for depreciation for taxation purposes or for other reporting needs outside of their cash-based financial statements.

Activa plugin - Manual - Shop - Licence : Once-off -

The Activa plugin automates the management and processes of fixed assets and the depreciation of fixed assets in your accounts over the lifespan of the fixed assets. Periodically you will receive a notification screen, which the depreciation shown. From this screen, the depreciation(s) can directly take place.

The Activa plugin in osFinancials5/TurboCASH5 allows you to register fixed assets that need to be written off. The write-off process occurs over the lifespan of the asset and can be spread across multiple financial years.

By adding the Activa Fixed asset accounts in the plugin setup, you will receive reminders when new transactions are posted to the ledger or when Activa transactions require processing. This automation streamlines the management of depreciation allowances for fixed assets (tangible assets) in your Set of Books over the asset's lifespan.

As you record the depreciation expenses for each financial year, they will be reported in the income statement and reduce your net profit. Additionally, the plugin will provide you with the net value of your fixed assets, which is calculated as the fixed assets' cost minus the accumulated depreciation, and this information will be reflected in the balance sheet.

In summary, the Activa plugin helps automate the depreciation management process, ensures accurate

reporting of depreciation expenses, and provides visibility into the net value of fixed assets over their lifespan in both the income statement and the balance sheet.

When a fixed asset reached the end of life end process that will clear of the total write-off from the balance write-off account and the initial asset account. This will display only the remaining total on the asset account and the contra account the will be cleared of this total.

By allowing the write-off process to occur over the lifespan of the asset and providing reminders for transaction processing, the plugin further streamlines the management of depreciation allowances for fixed assets.

The accurate reporting of depreciation expenses in the income statement and the reflection of the net value of fixed assets (cost minus accumulated depreciation) in the balance sheet remain essential features of the plugin.

Furthermore, the ability to clear the total write-off from the balance write-off account and the initial asset account when a fixed asset reaches the end of its life adds to the efficiency of the process.

The Activa plugin's powerful grid, custom filtering options, and integrated pivot tables enhance the search and analysis capabilities for active fixed assets, assets requiring processing, and transaction details. The Ledger analyser allows for the printing and exporting of the trial balance, income statement, and balance sheet, while the T-Account viewer facilitates the export of transactions to spreadsheets.

The Central search feature in osFinancials5/TurboCASH5 further aids in searching for transactions related to fixed assets, providing comprehensive functionality for managing and analysing fixed asset data.

What is depreciation?

Depreciation is an accounting method used to allocate the cost of a tangible asset over its useful life. It represents the gradual decrease in the value of an asset due to factors such as wear and tear, obsolescence, or the passage of time. Depreciation is a non-cash expense, meaning it does not involve an actual outflow of cash but is recorded to reflect the decrease in the asset's value over time.

Depreciation is important in financial reporting as it helps to match the cost of an asset with the revenue it generates during its useful life. By spreading the cost over multiple accounting periods, depreciation allows businesses to reflect the consumption of the asset's value in the periods it is used to generate revenue.

There are various methods for calculating depreciation, including straight-line depreciation, declining balance depreciation, and units of production depreciation. The choice of depreciation method depends on factors such as the nature of the asset, its expected useful life, and applicable accounting standards.

It's worth noting that depreciation is primarily applicable to tangible assets such as buildings, vehicles, machinery, equipment, and furniture. Intangible assets, such as patents or trademarks, are subject to a similar concept called amortization.

Is Depreciation a long-term adjustment?

Depreciation is a long-term adjustment. It involves allocating the cost of a tangible asset over its useful life. The purpose of depreciation is to recognize the gradual wear and tear, obsolescence, or decrease in the asset's value over time. By spreading the cost of the asset over its useful life, depreciation helps to match the expense of using the asset with the revenues it generates.

Since depreciation is related to the usage of long-term assets, it is considered a long-term adjustment. It affects the financial statements over multiple accounting periods, reflecting the ongoing consumption of the asset's economic benefits. The accumulated depreciation is typically presented as a contra-asset account on the balance sheet, reducing the carrying value of the related asset.

Depreciation is important for accurately reporting an entity's financial position and profitability, as it recognizes the cost of utilizing long-term assets in generating revenue. It is a key component in determining the true cost and value of an entity's assets and impacts various financial ratios, such as return on assets and net income.

What accounts is required to record and manage depreciation?

To record and manage depreciation, the following accounts are typically used:

1. Accumulated Depreciation: This is a contra-asset account that is used to accumulate the total depreciation expense recognized on an asset over its useful life. It is presented on the balance sheet and reduces the carrying value of the related asset.
2. Depreciation Expense: This is an expense account on the income statement that represents the periodic depreciation charge for the accounting period. It is used to record the portion of an asset's cost that is expensed during the period.
3. Asset Accounts: Each individual asset that is subject to depreciation should have its own asset account. These accounts represent the cost or value of the asset and are typically classified as long-term assets on the balance sheet.

The recording of depreciation involves debiting the Depreciation Expense account and crediting the Accumulated Depreciation account. This allocation process continues over the useful life of the asset until the asset's carrying value is reduced to its estimated residual value.

Managing depreciation involves periodically reviewing and updating the estimated useful lives, residual values, and depreciation methods for assets. It also includes conducting periodic impairment assessments to ensure that the carrying value of the assets is not higher than their recoverable amounts.

It's important to note that the specific accounts and procedures for recording and managing depreciation

may vary based on the accounting standards followed (such as IFRS or GAAP) and the entity's internal policies and practices.

Is Asset accounts for each Asset main account structured into sub-accounts?

It is a common practice to use sub-accounts within the Fixed assets category in the Chart of Accounts to track the cost of the asset and the accumulated depreciation.

Typically, the main account under the Fixed assets category represents the net value or carrying value of the asset. This main account reflects the original cost of the asset minus the accumulated depreciation. It provides a snapshot of the asset's value at a specific point in time.

The sub-accounts within the Fixed assets category are used to track specific details related to the asset. In this case, the *"Asset at cost*" sub-account is used to record the original cost or value of the asset. The "Accumulated depreciation" sub-account is a contra account that is credited with the amount of depreciation expense recognized over time. By having a contra account, the net value of the asset is calculated by subtracting the accumulated depreciation from the asset's cost.

This approach allows for better visibility and tracking of the asset's cost, accumulated depreciation, and net value. It also simplifies the process of recording depreciation expenses and provides a clear picture of the asset's value on the balance sheet.

Here's an example of how the main account and sub-accounts for motor vehicles could be structured within the Fixed Assets category in the Chart of Accounts:

G1540-000	*Motor vehicles - Net Value*	*This main account "Motor Vehicles - Net Value" represents the book value or holding value of the asset and is derived by subtracting the accumulated depreciation from the asset's cost. It provides a clear reflection of the net value of the motor vehicles on the balance sheet. It consists basically of the following two sub-accounts.*
G1540-010	*Motor vehicles at cost*	*This sub-account captures the original cost of the vehicles, including the purchase price, taxes, transportation costs, and other directly attributable expenses.*
G1540-020	*Accumulated depreciation - Motor vehicles*	*This sub-account serves as a contra account to record the total accumulated depreciation of the motor vehicles over time, based on their useful life and depreciation method.*

This account structure enables proper tracking and reporting of the motor vehicles' financial information, providing insights into their historical cost, accumulated depreciation, and net value. It adheres to common

accounting principles and facilitates accurate financial statements and analysis.

By using these sub-accounts, you can track the cost of the motor vehicles, the accumulated depreciation, and the net value of the motor vehicles separately. This provides a more detailed breakdown of the motor vehicles' financial information and facilitates accurate reporting and analysis.

It's important to note that the specific account names and structure may vary based on the organization's preferences and accounting system. Therefore, it is advisable to consult with an accounting professional or follow the established guidelines and practices in your specific accounting framework or industry.

Depreciation - when is it recorded, annually, 6 months, 3 months or monthly?

The frequency of recording depreciation depends on the accounting policy and the specific requirements of the reporting entity. In general, depreciation is recorded periodically over the useful life of the asset. The most common frequency for recording depreciation is monthly or annually.

Monthly depreciation: Some businesses choose to record depreciation on a monthly basis. This approach allows for more precise allocation of the asset's cost over time and provides a more granular view of the asset's impact on the financial statements. Monthly depreciation is commonly used for assets with shorter useful lives or when more accurate tracking of depreciation expense is desired.

Annual depreciation: Many businesses opt to record depreciation on an annual basis. This means that the total depreciation expense for the year is recorded in a single transaction. Annual depreciation is commonly used for assets with longer useful lives or when the periodic impact of depreciation on the financial statements is considered less significant.

Other frequencies: In certain cases, businesses may choose to record depreciation on a different time frame, such as every six months or every three months. These alternative frequencies are less common but may be employed based on specific reporting or operational needs.

It's important to note that the chosen frequency of depreciation should be consistent and in line with the accounting policies and practices of the entity. The frequency should also adhere to the relevant accounting standards, such as International Financial Reporting Standards (IFRS) or Generally Accepted Accounting Principles (GAAP), which provide guidance on depreciation accounting.

This includes IFRS (International Financial Reporting Standards) and its specific application for small and medium-sized entities (IFRS for SMEs). IFRS for SMEs provides simplified and streamlined accounting requirements for entities that meet the definition of a small or medium-sized entity. While it contains specific provisions tailored for SMEs, it still includes guidance on depreciation accounting. Therefore, the chosen frequency of depreciation should align with the requirements and principles outlined in IFRS for SMEs when applicable.

It is important for entities to carefully consider and apply the relevant accounting standards, such as IFRS for SMEs, to ensure accurate and consistent financial reporting, including the recording of depreciation. Compliance with the applicable accounting standards helps maintain transparency and comparability in financial statements, which is essential for users of financial information.

What transactions is required to process the procurement of a fixed asset?

To process the procurement of a fixed asset, you would typically need to perform the following transactions:

1. Purchase of the Fixed asset: Create a purchase transaction to record the acquisition of the fixed asset. This transaction includes the purchase price of the asset, any applicable taxes, transportation costs, and other directly attributable costs. Debit the Fixed asset account to increase its value and credit the appropriate Cash (bank account) or Accounts payable account (creditor/supplier account to reflect the payment made.
2. Recording Depreciation: After the fixed asset is acquired, you need to record depreciation expense over its useful life. This transaction transfers a portion of the asset's value from the Fixed Asset account to the Accumulated depreciation account. The specific depreciation method and useful life of the asset will determine the amount of depreciation expense to be recorded periodically.
3. Revaluation: If the fixed asset's value changes significantly over time, you may need to perform a revaluation transaction to adjust its carrying value. This transaction involves updating the Fixed asset account with the new value of the asset and adjusting the Accumulated Depreciation account accordingly.
4. Disposal: When the fixed asset is no longer in use or is sold, a disposal transaction is recorded. This transaction removes the asset's value from the Fixed asset account and its accumulated depreciation from the Accumulated Depreciation account. Any proceeds from the sale of the asset are recorded in a separate account, such as Gain on Disposal of Fixed assets or Loss on Disposal of Fixed assets.

These transactions ensure that the procurement, depreciation, and disposal of fixed assets are accurately recorded in the financial statements, reflecting the asset's value, depreciation over time, and any changes in its carrying value.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Legislation for depreciation or wear an tear allowances

Which legislation prescribes the depreciation methods or wear and tear allowances?

The legislation that prescribes the depreciation methods or wear and tear allowances can vary depending on the country or jurisdiction in which the entity operates. In many cases, tax legislation or tax regulations govern the specific depreciation methods and wear and tear allowances that entities can use for tax purposes. These regulations are typically defined by the tax authorities and may differ from the accounting standards or frameworks.

For example, in the United States, the Internal Revenue Service (IRS) provides guidelines on depreciation methods and recovery periods through the tax code, specifically under the Modified Accelerated Cost Recovery System (MACRS). The MACRS provides rules for determining the depreciation deductions for various types of assets used in business or income-generating activities.

In other countries, similar tax regulations or legislation govern the allowable depreciation methods and rates. These regulations may specify the useful lives of different types of assets, the depreciation methods that can be used (such as straight-line, declining balance, or units of production), and any special considerations or restrictions.

It's important for entities to consider both the accounting standards and the applicable tax legislation when determining the depreciation methods or wear and tear allowances to use for their fixed assets. Compliance with both sets of regulations ensures accurate financial reporting and tax compliance. Consulting with tax professionals or experts familiar with the local tax laws can help ensure proper adherence to the relevant legislation.

Created with the Standard Edition of HelpNDoc: Effortlessly Create Professional Documentation with HelpNDoc's Clean UI

Common methods to calculate depreciation

What is the common methods used to calculate depreciation?

There are several common methods used to calculate depreciation. The choice of method depends on factors such as the nature of the asset, its expected pattern of use, and the reporting entity's accounting policies. Here are some commonly used depreciation methods:

1. Straight-line depreciation: This is the most straightforward and commonly used method. It evenly distributes the cost of an asset over its estimated useful life. The formula for straight-line depreciation is:

   ```
   Depreciation Expense = (Cost of Asset - Residual Value) / Useful Life
   ```

   The depreciable amount is allocated equally to each period, resulting in a consistent depreciation expense over the asset's useful life.

2. Declining balance depreciation: Also known as accelerated depreciation, this method assigns higher depreciation expenses in the earlier years and gradually reduces them over time. Two common declining balance methods are:

   a) Double declining balance (DDB): This method applies a fixed rate of depreciation (typically twice the straight-line rate) to the asset's net book value each year. The formula for DDB depreciation is:

      ```
      Depreciation Expense = Net Book Value * Depreciation Rate
      ```

      The net book value is reduced by the depreciation expense each year until it reaches the asset's residual value.

   b) Sum-of-years-digits (SYD): This method considers the asset's useful life and allocates higher depreciation in the earlier years. The formula for SYD depreciation is:

      ```
      Depreciation Expense = (Remaining Useful Life / Sum of Years) * (Cost of Asset - Residual Value)
      ```

      The sum of years is calculated by adding the digits of the asset's useful life (e.g., for a 5-year useful life: 5 + 4 + 3 + 2 + 1 = 15).

3. Units of production depreciation: This method is based on the actual usage or production output of the asset. It calculates depreciation based on the number of units produced, hours worked, or any other suitable production measure. The formula for units of production depreciation is:

   ```
   Depreciation Expense per Unit = (Cost of Asset - Residual Value) / Total Units of Production Depreciation Expense = Depreciation Expense per Unit * Units Produced or Utilized
   ```

   The depreciation expense varies based on the level of asset utilization or production activity.

These are just a few examples of commonly used depreciation methods. Other specialized methods, such as group depreciation or component depreciation, may also be used in specific situations. It's important to select a depreciation method that best aligns with the nature of the asset, applicable accounting standards, and relevant regulations.

Created with the Standard Edition of HelpNDoc: Effortlessly bring your documentation online with HelpNDoc

Purchase of fixed assets

What is the purchase transaction of a fixed asset?

The purchase transaction of a fixed asset typically involves the acquisition of the asset from an external party or the construction of the asset within the entity. Here are the key elements of a purchase transaction for a fixed asset:

1. Identification and selection of the asset: The entity identifies the need for a fixed asset and determines the specific type and characteristics of the asset required to meet its operational needs.
2. Vendor selection and negotiation: If the asset is purchased from an external party, the entity identifies potential vendors, evaluates their offerings, and negotiates the terms of the purchase, including the price, payment terms, warranties, and any other relevant conditions.
3. Purchase order or contract: A purchase order or contract is created to formalize the agreement between the entity and the vendor. It specifies the details of the asset, the agreed-upon price, delivery terms, and other relevant terms and conditions.
4. Receipt and acceptance of the asset: Upon delivery of the asset, the entity verifies the physical receipt of the asset, inspects it for any damage or discrepancies, and confirms that it meets the specifications outlined in the purchase order or contract. If there are any issues, they may be resolved with the vendor through a return, replacement, or adjustment in the purchase terms.
5. Record the purchase: The entity records the purchase transaction in its accounting records. This typically involves debiting the appropriate fixed asset account or category (e.g., Motor Vehicles, Buildings, Machinery) to reflect the cost of the asset acquired. The corresponding credit is usually made to a liability account or cash/bank account to reflect the payment made or the liability incurred.
6. Allocate costs: If the asset acquisition involves additional costs beyond the purchase price, such as transportation, installation, or legal fees, these costs are allocated to the appropriate accounts (e.g., Transportation Expense, Installation Expense) to reflect the total cost of the asset acquisition.

It's important to note that the specific details and accounting treatment of a purchase transaction for a fixed asset may vary depending on the entity's accounting policies, applicable accounting standards (such as IFRS or GAAP), and any specific requirements or regulations in the entity's jurisdiction.

Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with

HelpNDoc's easy CHM conversion

Fixed Asset Register

What is the Fixed Asset Register?

The Fixed Asset Register, also known as the Fixed Asset Ledger or Fixed Asset Inventory, is a record-keeping system that contains detailed information about a company's fixed assets. It serves as a centralized repository for all relevant information related to the company's fixed assets, including their acquisition, depreciation, disposal, and current status.

The Fixed Asset Register typically includes the following information for each fixed asset:

1. Asset identification: A unique identifier or code for each asset to track and differentiate it from other assets.
2. Description: A detailed description of the asset, including its specifications, model, or serial number.
3. Acquisition date: The date when the asset was acquired or put into service.
4. Cost: The original cost or purchase price of the asset, including any associated expenses such as taxes, transportation, and installation costs.
5. Depreciation method: The method used to calculate the depreciation expense for the asset, such as straight-line, declining balance, or units of production.
6. Useful life: The estimated period over which the asset is expected to provide economic benefits to the company.
7. Residual value: The estimated value of the asset at the end of its useful life, often assumed to be its salvage or scrap value.
8. Depreciation expense: The amount of depreciation charged to the company's financial statements for each reporting period.
9. Accumulated depreciation: The cumulative total of depreciation expenses recorded for the asset over its useful life.
10. Net book value: The net value of the asset, calculated as the cost of the asset minus its accumulated depreciation.
11. Location: The physical location or department where the asset is located within the company's premises.
12. Maintenance and service history: Records of maintenance activities, repairs, and any significant

events related to the asset's upkeep.

The Fixed Asset Register is essential for accurate financial reporting, internal control, and asset management. It provides an overview of the company's fixed assets, helps track their depreciation, facilitates budgeting and forecasting, and assists in making informed decisions regarding asset maintenance, replacement, or disposal.

In which formats can the Fixed Asset Register be kept?

The Fixed Asset Register can be kept in various formats, depending on the preferences and needs of the organization. Here are some common formats used to maintain the Fixed Asset Register:

1. Spreadsheet software: Spreadsheets such as Microsoft Excel or Google Sheets are commonly used to create and manage Fixed Asset Registers. Each asset can be recorded in a separate row, and the relevant information can be organized in columns. Spreadsheet software allows for easy data entry, calculations, filtering, and sorting.
2. Accounting software: Many accounting software applications have built-in modules or features specifically designed for managing fixed assets. These software solutions provide dedicated tools to create and maintain the Fixed Asset Register, automate depreciation calculations, generate reports, and integrate with other financial processes. In osFinancials5/TurboCASH5 the Activa plugin automates the management and processes of fixed assets and the depreciation of fixed assets in your accounts over the lifespan of the fixed assets.

Activa plugin - Manual - Shop - Licence : Once-off -

The Activa plugin automates the management and processes of fixed assets and the depreciation of fixed assets in your accounts over the lifespan of the fixed assets. Periodically you will receive a notification screen, which the depreciation shown. From this screen, the depreciation(s) can directly take place.

3. Database systems: Organizations may choose to create a custom database using database management software like Microsoft Access, SQL Server, or Oracle. A database allows for structured storage and retrieval of asset data and offers more advanced capabilities for data management and reporting.
4. Asset management software: There are specialized asset management software solutions available in the market that focus specifically on managing fixed assets. These software systems offer comprehensive features for asset tracking, depreciation calculation, maintenance scheduling, and reporting.

Regardless of the format chosen, it is important to ensure that the Fixed Asset Register is regularly updated, accurate, and aligned with the organization's accounting policies and practices. It should also

comply with any applicable accounting standards or regulations governing fixed asset reporting.

Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Insurance for fixed assets

Is insurance commonly obtained for fixed assets?

Insurance is commonly obtained for fixed assets. Fixed assets represent significant investments for businesses, and insuring them helps protect against potential risks and losses. Insurance coverage for fixed assets can include various types of policies, such as property insurance, casualty insurance, liability insurance, or specialized coverage for specific types of assets.

Insurance for fixed assets typically covers events like fire, theft, natural disasters, vandalism, and other unexpected incidents that could cause damage or loss to the assets. The insurance policy helps provide financial compensation or replacement for the damaged or lost assets, allowing the business to recover from such incidents without significant financial burden.

Insurance coverage for fixed assets is particularly important for assets of high value or critical importance to the business's operations. It helps mitigate the financial risks associated with potential damage or loss, giving the business peace of mind and financial protection.

Can the proper records maintained help to be penalised by insurance companies regarding to be over-insured and under-insured?

Maintaining proper records of fixed assets can help prevent penalties related to over-insurance or under-insurance by insurance companies. Accurate and up-to-date records provide essential information about the value and characteristics of fixed assets, which is crucial for determining appropriate insurance coverage.

When insuring fixed assets, it is important to accurately assess their value and determine the appropriate coverage amount. Over-insuring can lead to unnecessarily high insurance premiums, while under-insuring can result in inadequate compensation in the event of a loss.

By maintaining comprehensive records of fixed assets, including details such as acquisition cost, depreciation, improvements or upgrades, and current market value, businesses can provide accurate information to insurance companies during the underwriting process. This allows insurance companies to

assess the value of the assets and recommend appropriate coverage limits.

Proper records also help in regular insurance reviews and updates. As fixed assets may change in value or undergo significant changes over time, periodically reviewing and updating insurance coverage ensures that the coverage remains aligned with the assets' current value and risk exposure.

In case of a claim, thorough and well-maintained records can serve as evidence to support the insurance claim and help expedite the claims settlement process. Detailed records provide a clear picture of the assets' value and condition before the loss occurred, facilitating a smoother claims process and reducing the likelihood of disputes or penalties.

Overall, accurate and comprehensive records of fixed assets play a vital role in maintaining appropriate insurance coverage, avoiding penalties related to over-insurance or under-insurance, and ensuring a fair and efficient claims process.

How is insurance premiums is this recorded?

Recording insurance premiums involves categorizing them as an expense and reflecting them in the financial records of a business. Here's how insurance premiums are typically recorded:

1. Create an expense account: Set up a specific expense account in the Chart of Accounts to track insurance-related expenses. This account could be named something like "Insurance Expense" or "Insurance Premiums."
2. Record the premium payment: When the insurance premium is paid, create a journal entry to record the transaction. Debit the Insurance Expense account for the amount of the premium, reflecting the increase in expenses. Credit the Cash or Bank account to show the decrease in cash as a result of the payment.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Insurance expense / Insurance premiums	*Expenses*	*$1,200*	
Credit: Cash or bank account	*Current asset*		*$1.200*

Periodic adjustments

The periodic adjustments for allocating insurance premiums over the coverage period are typically

applicable to the accrual basis accounting method rather than the cash basis accounting method.

If your business follows the the accrual basis accounting method, you may need to consider adjusting the entries as prepaid expenses or expenses paid in advance. This adjustment would be necessary to record and allocate the recognise only portion of the insurance expenses or insurance premiums at the end of the current reporting period to the

Under the cash basis accounting method, expenses are recognized when cash is paid out, and income is recognized when cash is received.

Since insurance premiums are typically paid upfront for a specific coverage period, they would be recorded as an expense in full when the payment is made. There is no need for adjusting entries to allocate the expense over the coverage period because the cash basis accounting method does not consider the passage of time or the matching of expenses to the corresponding revenue.

On the other hand, under the accrual basis accounting method, expenses are recognized when they are incurred, regardless of when the cash payment is made. Adjusting entries are used to properly allocate expenses over the accounting periods to reflect the matching principle, which states that expenses should be recognized in the same period as the related revenue. Therefore, under accrual accounting, insurance premiums would be allocated over the coverage period through adjusting entries at the end of each accounting period.

It's important to note that the choice between the cash basis and accrual basis accounting methods depends on the specific circumstances and accounting requirements of the business. The accrual basis is generally considered more accurate and in line with generally accepted accounting principles (GAAP) and international financial reporting standards (IFRS).

Periodic adjustments: Insurance premiums are often paid for a specific coverage period (e.g., one year) and are typically recorded as an expense evenly over that period. To reflect this, you may need to make adjusting entries at the end of each accounting period to allocate the insurance expense for the portion of coverage used during that period.

For example, if you have an annual insurance premium of $1,200, and your accounting period is one month, you would record a monthly insurance expense of $100. At the end of each month, you would make an adjusting entry to recognize $100 as insurance expense and reduce the prepaid portion of the premium.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Prepaid Insurance	*Expenses*	*$100*	

Credit: Insurance expense / Insurance premiums	*Current asset*	*$100*

The adjusting entry would look like this:

Debit: Insurance Expense $100 Credit: $100

Reporting: The insurance expense recorded will be reflected in the income statement as part of the operating expenses for the specific period. It will contribute to the calculation of net income and the overall financial performance of the business.

By properly recording insurance premiums as expenses, businesses can accurately track and report their insurance-related costs, which provides insights into their financial performance and aids in budgeting and decision-making processes.

Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Disposal of fixed assets

What is disposal of a fixed assets?

Disposal of a fixed asset refers to the process of selling, scrapping, or otherwise removing a long-term tangible asset from a company's balance sheet. Fixed assets are items with a useful life greater than one accounting period and are not intended for sale as part of the company's normal business operations. Examples of fixed assets include buildings, machinery, equipment, vehicles, and furniture.

When a company decides to dispose of a fixed asset, it typically goes through the following steps:

1. Identification: The company identifies the fixed asset to be disposed of, which may be due to various reasons like the asset becoming obsolete, damaged beyond repair, or no longer needed for the company's operations.
2. Valuation: The asset is valued to determine its current worth. The valuation can be based on the original cost of the asset minus depreciation or any impairment that may have been recognized over its useful life.
3. Decision Making: The management decides on the best course of action for disposal. This could involve selling the asset, trading it in for a new asset, or simply scrapping it if it has no remaining value.

4. Disposal Method: Depending on the decision made, the asset can be sold to a third party, auctioned, traded, or salvaged for parts. If it has no value or is considered a liability, it may be discarded or recycled responsibly.
5. Accounting Entries: The accounting department records the disposal of the fixed asset on the company's books. The specific accounting treatment depends on whether the disposal resulted in a gain or loss. If the proceeds from the sale exceed the asset's book value, there will be a gain, and if the proceeds are less, there will be a loss.
    - If there is a gain on disposal, it is recorded as a credit to the income statement, increasing the company's profit.
    - If there is a loss on disposal, it is recorded as an expense on the income statement, reducing the company's profit.
6. Tax Implications: Disposing of fixed assets may have tax implications for the company. Depending on the tax laws in the company's jurisdiction, the gain or loss on disposal may be subject to taxation.
7. Reporting: The disposal of fixed assets is disclosed in the company's financial statements, usually in the notes to the financial statements or in the statement of cash flows.

It's essential for companies to carefully document and adhere to proper procedures when disposing of fixed assets to ensure accuracy in financial reporting and compliance with accounting standards and regulations.

Is the disposal of fixed assets subject to Capital Gains Tax (CGT)?

The disposal of fixed assets can be subject to Capital Gains Tax (CGT) in many countries, but the specific rules and rates vary depending on the tax laws of each jurisdiction. Capital Gains Tax is generally applicable when there is a gain on the disposal of an asset, which is calculated as the difference between the selling price (proceeds) and the original cost of the asset (adjusted for any improvements or deductions).

Here are some key points to consider regarding Capital Gains Tax and the disposal of fixed assets:

1. Tax Jurisdiction: The rules regarding CGT are specific to each country, and sometimes even different within different states or regions of a country. Companies need to adhere to the tax regulations of the jurisdiction in which the disposal takes place.
2. Exemptions and Allowances: Some jurisdictions may provide exemptions or allowances for certain types of assets or specific scenarios, such as the sale of a primary residence or small business assets up to a certain value.
3. Holding Period: In some countries, the length of time the asset was held before disposal can impact

the CGT liability. For example, a lower tax rate may apply to assets held for more extended periods.

4. Tax Rates: Capital Gains Tax rates can vary based on factors like the type of asset, the taxpayer's income, and the duration of ownership. Sometimes, different rates may apply to individuals and corporations.
5. Offsetting Losses: Capital losses from the disposal of other assets may be used to offset capital gains, reducing the overall CGT liability.
6. Roll-over Relief: Some jurisdictions may offer roll-over relief, allowing taxpayers to defer CGT when selling one asset and reinvesting the proceeds in another qualifying asset.
7. Main Residence Exemption: Many countries offer a CGT exemption for the sale of the taxpayer's primary residence, up to certain limits.
8. Proper Record-Keeping: It's essential for companies and individuals to maintain accurate records of the original cost, improvements, and selling price of the asset to calculate the correct CGT liability.

As tax laws and regulations are subject to change and can be complex, it is crucial to consult with tax professionals or advisors who are knowledgeable about the specific tax laws in the relevant jurisdiction to ensure compliance and accurate reporting of Capital Gains Tax on the disposal of fixed assets.

Journal to record the transactions relating to the profit loss at the disposal

It is not a general practice to record transactions related to the profit or loss at the disposal of fixed assets in the Depreciation journal. The Depreciation journal is typically used to record regular depreciation expenses or adjustments for fixed assets over their useful life. It is not specifically designed to handle transactions related to the disposal or sale of fixed assets.

When a fixed asset is disposed of, the transaction is usually recorded in a separate journal or module, such as the Asset Disposal or Asset Sale module. This module allows you to record the details of the asset sale, including the selling price, disposal date, any gains or losses incurred, and the allocation of the proceeds.

The disposal transaction may impact the Profit and Loss statement, as it involves recognizing any gains or losses on the sale of the asset. These gains or losses are typically recorded in the Income or Expense section of the Profit and Loss statement, depending on whether the disposal resulted in a profit or loss.

It's important to consult with your specific accounting practices and the regulations of your jurisdiction to determine the appropriate journal or module to record transactions related to the disposal of fixed assets and the treatment of associated gains or losses in the Profit and Loss statement.

What would the example transactions be for a profit on the disposal of a fixed asset?

Example transactions for a profit on the disposal of a fixed asset would typically involve recording the following entries:

1. Record the sale of the fixed asset:
    - Debit: Accounts Receivable (or Cash) - The amount received from the sale
    - Credit: Fixed Asset - The original cost of the asset
    - Credit: Accumulated Depreciation - The total depreciation accumulated on the asset until the date of disposal
2. Calculate the gain on disposal:
    - Debit: Accumulated Depreciation - The amount of depreciation accumulated on the asset until the date of disposal
    - Debit: Loss on Disposal (if applicable) - Any additional expenses incurred in the disposal process
    - Credit: Gain on Disposal - The difference between the sale price and the asset's carrying value (original cost minus accumulated depreciation)
3. Remove the fixed asset from the books:
    - Debit: Accumulated Depreciation - Any remaining balance in the accumulated depreciation account
    - Debit: Loss on Disposal (if applicable) - Any additional expenses incurred in the disposal process
    - Credit: Fixed Asset - The original cost of the asset
    - Credit: Accumulated Depreciation - The total depreciation accumulated on the asset until the date of disposal

These transactions will recognize the gain on disposal as income in the Profit and Loss statement, reflecting the profit realized from the sale of the fixed asset. The specific accounts used may vary depending on your company's chart of accounts and accounting practices.

It's important to consult with a qualified accountant or financial advisor to ensure that the transactions are recorded correctly and in compliance with applicable accounting standards and regulations.

What would the example transactions be for a loss on the disposal of a fixed asset?

Example transactions for a loss on the disposal of a fixed asset would typically involve recording the following entries:

1. Record the sale of the fixed asset:
    - Debit: Accounts Receivable (or Cash) - The amount received from the sale
    - Credit: Fixed Asset - The original cost of the asset
    - Credit: Accumulated Depreciation - The total depreciation accumulated on the asset until the date of disposal
2. Calculate the loss on disposal:
    - Debit: Loss on Disposal - The difference between the asset's carrying value (original cost minus accumulated depreciation) and the sale price
    - Credit: Accumulated Depreciation - The amount of depreciation accumulated on the asset until the date of disposal
3. Remove the fixed asset from the books:
    - Debit: Loss on Disposal - The remaining balance in the loss on disposal account
    - Credit: Fixed Asset - The original cost of the asset
    - Credit: Accumulated Depreciation - The total depreciation accumulated on the asset until the date of disposal

These transactions will recognize the loss on disposal as an expense in the Profit and Loss statement, reflecting the loss incurred from the sale of the fixed asset. The specific accounts used may vary depending on your company's chart of accounts and accounting practices.

It's important to consult with a qualified accountant or financial advisor to ensure that the transactions are recorded correctly and in compliance with applicable accounting standards and regulations.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Depreciated fixed assets - Nominal value or Token value principle

---

What is the nominal value / token value principle for fixed assets?

The nominal value or token value principle for fixed assets is a practice used to maintain a minimal or symbolic value for fixed assets that have reached the end of their useful life and are no longer in active use. Instead of fully writing off the fixed asset and removing it from the books with a zero value, companies choose to keep the asset on the books with a nominal or token value, often as low as $1 or another small amount.

The main reason for applying the nominal value principle is to avoid the administrative burden and costs associated with fully disposing of the asset and updating the fixed asset register. It simplifies the accounting process, especially when dealing with a large number of fixed assets.

Here's how the nominal value principle works:

1. End of useful life: When a fixed asset reaches the end of its useful life and is no longer in active use, it is time to dispose of the asset.
2. Nominal value entry: Instead of writing off the asset completely, a nominal value entry is made. For example, if the asset's value is fully depreciated and its net book value is $0, a journal entry may be made to credit the fixed asset account with $1 and debit an appropriate nominal value account, such as "*Nominal Value of Fixed Assets*".
3. Token value on books: The fixed asset remains on the books with a nominal value of $1 (or another small amount) instead of being fully written off. This token value allows the asset to remain in the fixed asset register, simplifying record-keeping and asset tracking.
4. No depreciation: Once the asset is set at a nominal value, no further depreciation is recorded since the asset is no longer in use, and its economic benefit to the company is considered negligible.

It's important to note that the nominal value principle is primarily a simplification technique and doesn't reflect the actual value of the asset. It is used when the administrative costs of fully disposing of the asset outweigh the benefits of keeping precise records for assets that have no substantial economic value to the company.

However, companies must comply with relevant accounting standards and regulations when applying the nominal value principle and ensure that it aligns with the principles of financial reporting and transparency. It is always recommended to consult with a qualified accountant or financial advisor to determine the appropriateness of applying this principle based on the specific circumstances and regulatory requirements.

What are the reasons for keeping fixed assets with a nominal value on the books?

Keeping fixed assets with a nominal value on the books offers several benefits and reasons for companies. Some of the main reasons include:

1. Simplified record-keeping: By assigning a nominal value (e.g., $1) to fixed assets that have reached the end of their useful life, companies simplify their record-keeping and accounting processes. Fully disposing of assets with a zero value can be administratively burdensome, especially when dealing with a large number of fixed assets. The nominal value allows the asset to remain in the fixed asset register, making it easier to track and manage.
2. Cost-effectiveness: Fully disposing of fixed assets may involve additional administrative costs, such as legal fees, documentation, and asset removal expenses. Keeping the asset on the books with a nominal value can be a cost-effective alternative, especially when the actual economic value of the asset is negligible.
3. Asset tracking: Retaining fixed assets with a nominal value facilitates better asset tracking. Even though the asset is no longer in active use, it may still be located on the company's premises or held in storage. Having it listed in the fixed asset register with a nominal value ensures that it is accounted for and easily traceable.
4. Compliance with accounting standards: In some cases, accounting standards or regulatory requirements may recommend or permit the use of nominal value for fixed assets at the end of their useful life. This practice can ensure compliance with reporting guidelines while still acknowledging that the asset has no significant remaining economic benefit.
5. Historical record: Keeping fixed assets with a nominal value can serve as a historical record of the company's past investments and asset acquisitions. This information can be valuable for financial analysis, decision-making, or audits.
6. Legal and Tax considerations: In certain jurisdictions, there may be legal or tax implications associated with fully disposing of fixed assets. Retaining the asset with a nominal value can help address these considerations while still recognising the asset's retirement.
7. Inherent Value: Some companies attach a symbolic or sentimental value to their fixed assets, even after their useful life is over. Assigning a nominal value allows the company to acknowledge the significance of the asset within the organisation, beyond its financial worth.

While keeping fixed assets with a nominal value can offer advantages, it is essential to ensure that this practice aligns with accounting principles and regulatory requirements in the company's jurisdiction. Companies should maintain transparency and accuracy in financial reporting and consult with accounting

professionals to determine the appropriateness of applying the nominal value principle based on their specific circumstances.

At the end of the use of the asset and it is disposed of, the nominal value of $1 should then be cleared when determining and processing the profit on the disposal of fixed assets?

Yes, when a fixed asset reaches the end of its useful life and is disposed of, the nominal value (e.g., $1) should be cleared from the books. The disposal of a fixed asset involves removing it from the balance sheet and recognizing any gain or loss on the disposal.

Here's how the process typically works:

1. Clearing the nominal value: Before processing the disposal, the nominal value of the asset (e.g., $1) should be written off or cleared from the books. This is usually done through a journal entry that debits the asset account (with the nominal value) and credits it to an appropriate account, such as the "Accumulated Depreciation" account, to remove the asset from the books.
2. Calculate the gain or loss: Next, the gain or loss on the disposal is calculated. The gain or loss is the difference between the disposal proceeds (the amount received from selling the asset) and the asset's net book value at the time of disposal. The net book value is the original cost of the asset minus any accumulated depreciation up to the date of disposal.
3. Journal entry for the disposal: The gain or loss on the disposal is recorded through a journal entry. If there is a gain, it is credited to the "*Gain on Disposal of Fixed assets*" account, and if there is a loss, it is debited to the "*Loss on Disposal of Fixed assets*" account. The corresponding entry will be made to the asset account to remove it completely from the books.
4. Update the fixed asset register: The fixed asset register should be updated to reflect the disposal, including the date of disposal, the proceeds received, and any gain or loss recognised.

By clearing the nominal value and recognizing any gain or loss on disposal, the company ensures that its financial records accurately reflect the outcome of the asset's disposal. This process is essential for providing transparency and accuracy in financial reporting. Again, it is essential to consult with a qualified accountant or financial advisor to ensure that the disposal of fixed assets is correctly accounted for and complies with relevant accounting principles and regulations.

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Month-end and year-end procedures

Are there any month-end procedures and year-end procedures in accounting?

Yes, there are typically month-end procedures and year-end procedures in accounting. These procedures are important for ensuring accurate financial reporting and compliance with accounting standards and regulations.

Month-end procedures may include reconciling bank accounts, reviewing and adjusting journal entries, preparing financial statements, and ensuring all transactions are properly recorded.

Year-end procedures are more extensive and involve closing out the books for the entire year. This includes reconciling all accounts, completing any necessary adjusting entries, preparing financial statements, and performing a year-end audit. Year-end procedures also involve preparing for tax reporting and compliance, including preparing tax returns and reviewing compliance with tax regulations.

Overall, both month-end and year-end procedures are critical for maintaining accurate financial records and ensuring compliance with accounting and tax regulations.

Adjustments - Cash basis accounting - when is it recorded, annually, 6 months, 3 months or monthly?

In cash basis accounting, adjustments are not typically made because the focus is on recording transactions when cash is received or paid. Cash basis accounting does not consider the timing of revenue recognition or expense allocation.

Under the cash basis, revenue is recognized when cash is received, and expenses are recorded when cash is paid. There is no need for periodic adjustments since transactions are recorded based on actual cash inflows and outflows.

However, it's important to note that cash basis accounting may not comply with generally accepted accounting principles (GAAP) or International Financial Reporting Standards (IFRS), which often require accrual basis accounting for financial reporting. Accrual basis accounting recognizes revenue when it is earned and expenses when they are incurred, regardless of the timing of cash flows.

So, in summary, adjustments are not typically made in cash basis accounting since transactions are recorded based on cash receipts and payments.

Adjustments - Accrual basis accounting - when is it recorded, annually, 6 months, 3 months or monthly?

In accrual basis accounting, adjustments are typically recorded at the end of each accounting period, which is often annually but can also be quarterly or monthly depending on the reporting requirements and internal practices of the entity.

The purpose of these adjustments is to ensure that the financial statements accurately reflect the financial position and operating results of the company for the specific accounting period. They help match revenues with expenses in the appropriate period, recognize accrued revenues or expenses, and make necessary corrections or estimates.

Common types of adjustments in accrual basis accounting include:

1. Accrued Revenues: Revenue that has been earned but not yet received or recorded. For example, if a company provides services but has not yet billed the customer, an adjustment is made to recognize the revenue in the appropriate period.
2. Accrued Expenses: Expenses that have been incurred but not yet paid or recorded. For example, if a company has received goods or services but has not yet received an invoice, an adjustment is made to recognize the expense in the appropriate period.
3. Prepaid Expenses: Expenses that have been paid in advance but have not yet been consumed or used. An adjustment is made to allocate the prepaid expense over the periods benefiting from the expenditure.
4. Deferred Revenues: Revenue that has been received but not yet earned. For example, if a company receives advance payments from customers for services to be provided in the future, an adjustment is made to defer recognizing the revenue until the services are delivered.
5. Depreciation and Amortization: Adjustments are made to allocate the cost of long-term assets over their useful lives to reflect the portion of the asset's value consumed during the accounting period.

These adjustments are made to ensure that the financial statements present a true and fair view of the company's financial performance and position. They are typically recorded at the end of the accounting period before the financial statements are prepared.

In the case of adjustments for correction of errors and disallowing private expenses - should these be done when discovered in the accounting cash and accrual basis accounting?

Yes, adjustments for the correction of errors and disallowing private expenses should be made as soon as they are discovered in both cash and accrual basis accounting.

In cash basis accounting, adjustments for correction of errors and disallowing private expenses would involve identifying the errors or inappropriate expenses and making the necessary adjustments to the cash receipts or payments. This ensures that the financial records accurately reflect the true financial position of the business.

In accrual basis accounting, adjustments for correction of errors and disallowing private expenses would involve identifying the errors or inappropriate expenses and making the necessary journal entries to correct the accounts affected. This ensures that the financial statements present a true and fair view of the business's financial performance and position.

It is important to make these adjustments as soon as they are discovered to maintain accurate and reliable financial records and to comply with accounting standards and regulations. Delaying the adjustments could result in misleading financial statements and potential issues with compliance and decision-making.

Is the month-end and year-end procedures and principles the same for GAAP and IFRS?

The month-end and year-end procedures and principles are generally similar under both Generally Accepted Accounting Principles (GAAP) and International Financial Reporting Standards (IFRS), as both sets of standards require companies to prepare financial statements at regular intervals and to adhere to certain accounting principles and practices.

However, there may be some differences in specific requirements and reporting standards between GAAP and IFRS, depending on the country or region where the company is based. It is important for companies to understand and comply with the relevant accounting standards and regulations in their jurisdiction.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Accounting method (accrual basis or cash basis)

It's important to note that the choice of accounting method (accrual basis or cash basis) depends on various factors, including legal requirements, business needs, and financial reporting purposes. Always consult with an accounting professional or refer to the accounting standards applicable to your jurisdiction for guidance on the appropriate accounting treatment based on your specific circumstances.

It's important to choose the appropriate accounting method (either accrual basis or cash basis) based on the nature and size of your business, as well as any legal or regulatory requirements. Generally, larger businesses and entities are required to use the accrual basis accounting method, while smaller businesses may opt for the cash basis method for simplicity and ease of recording transactions.

Common year-end adjustments for both cash basis and accrual basis accounting methods

When using the accrual basis accounting method, year-end adjustments are necessary to ensure that the financial statements reflect the actual income and expenses for the accounting period. Here are some common year-end adjustments for both cash basis and accrual basis accounting methods:

Cash basis accounting method:

1. Adjusting entries for depreciation: Depreciation is a non-cash expense that needs to be recorded for fixed assets, such as buildings and equipment.
2. Adjusting entries for bad debts: If you have any outstanding debts that are unlikely to be paid, you need to write them off as bad debts.
3. Recording prepaid expenses: If you have made payments for expenses that will benefit future accounting periods, such as insurance premiums, these need to be recorded as prepaid expenses.
4. Recording unearned income: If you have received payments for goods or services that you have not yet provided, these need to be recorded as unearned income.

Accrual basis accounting method:

1. Recording accrued income: If you have provided goods or services but have not yet received payment, you need to record this as accrued income.
2. Recording accrued expenses: If you have received goods or services but have not yet paid for them, you need to record this as accrued expenses.
3. Recording prepaid expenses: Similar to cash basis accounting, you need to record any payments made for expenses that will benefit future accounting periods as prepaid expenses.

4. Recording unearned income: Similar to cash basis accounting, you need to record any payments received for goods or services that have not yet been provided as unearned income.

It's important to note that each of these adjustments needs to be made before performing a year-end procedure in the osFinancials5/TurboCASH5 to ensure that the financial statements are accurate.

Is the month-end and year-end procedures and principles the same for GAAP and IFRS?

The month-end and year-end procedures and principles are generally similar under both Generally Accepted Accounting Principles (GAAP) and International Financial Reporting Standards (IFRS), as both sets of standards require companies to prepare financial statements at regular intervals and to adhere to certain accounting principles and practices.

However, there may be some differences in specific requirements and reporting standards between GAAP and IFRS, depending on the country or region where the company is based. It is important for companies to understand and comply with the relevant accounting standards and regulations in their jurisdiction.

Are provision for bad debts, prepaid expenses, accrued expenses, provision for accrued expenses, income received in advance, and accrued income short-term adjustments?

Yes, provision for bad debts, prepaid expenses, accrued expenses, provision for accrued expenses, income received in advance, and accrued income are typically considered short-term adjustments. These adjustments are made to ensure that the financial statements for a particular accounting period accurately reflect the expenses and revenues that belong to that period. They usually relate to transactions or events that occur during the current accounting period but whose impact will be felt in future periods. These adjustments are usually reversed or adjusted in the following accounting period when the related transactions or events are fully realized.

After these adjustments were made for a financial year whet entries is necessary for the next financial year?

After adjustments have been made for the previous financial year, you would typically start the next financial year with opening entries. These opening entries are necessary to bring forward the balances of certain accounts from the previous financial year to the new financial year.

For example, the balance of the retained earnings account from the previous financial year would be

brought forward as the opening balance for the new financial year. Similarly, any other account balances that need to be carried forward to the new financial year would be entered as opening entries.

The opening entries would be recorded in the general journal and posted to the relevant ledger accounts to update the balances in those accounts. Once the opening entries have been posted, you can start entering new transactions for the new financial year.

Are these adjustments accrued income, accrued expenses, prepaid expenses, unearned income doe annually at year end or can they be done on a monthly, quarterly or six months basis?

The timing of these adjustments (accrued income, accrued expenses, prepaid expenses, unearned income) may vary depending on the specific accounting policies of a company and the frequency of their accounting periods.

For example, some companies may choose to adjust their prepaid expenses or unearned income on a monthly basis, while others may do it on a quarterly or annual basis. Similarly, accrued expenses or accrued income may also be adjusted on a regular basis depending on the accounting period.

However, it is common practice to ensure that all such adjustments are made at least once a year, during the year-end procedures, to ensure that the financial statements accurately reflect the company's financial position and performance.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Accrual basis adjustments

What is year-end adjustments?

Year-end adjustments, also known as adjusting entries, are accounting entries made at the end of an accounting period to ensure that a business's financial statements accurately reflect its financial position and performance.

These adjustments are necessary because certain transactions may not have been recorded or may have been recorded incorrectly during the accounting period. Year-end adjustments are made to correct these errors and to recognize revenues and expenses in the appropriate accounting period.

Year-end adjustments may include accruals for expenses and revenues that have been incurred but not yet recorded, such as salaries and wages, interest, and rent. They may also include adjustments for prepaid

expenses, such as insurance or rent, that have been paid in advance.

Depreciation adjustments may also be made for fixed assets that have been in use during the accounting period. In addition, adjusting entries may be made to correct errors in previously recorded transactions, such as incorrect account balances or misclassified expenses.

Year-end adjustments are an important part of the accounting process and are necessary for accurate financial reporting. They ensure that a business's financial statements reflect its true financial position and performance for the accounting period.

What is the difference between the cash based and accrual based accounting?

Cash basis accounting and accrual basis accounting are two methods used to keep track of a business's financial transactions.

In cash basis accounting, revenue and expenses are recognized only when money is actually received or paid out. This means that income is recognized only when cash is received and expenses are recorded only when they are actually paid.

On the other hand, accrual basis accounting recognizes revenue when it is earned, regardless of whether payment has been received, and expenses when they are incurred, regardless of whether payment has been made. This means that revenue is recognized when the product or service is delivered, and expenses are recognized when the goods or services are received.

For example, let's say a company provides services to a client in January but does not receive payment until February. Under the cash basis accounting method, the revenue would be recognized in February when payment is received. However, under the accrual basis accounting method, the revenue would be recognized in January when the services were provided.

The choice between cash basis accounting and accrual basis accounting depends on the specific needs and goals of the business. Cash basis accounting is simpler and easier to maintain, while accrual basis accounting provides a more accurate picture of a business's financial position over time.

Do the cash based accounting need any adjustments?

While cash basis accounting is simpler than accrual basis accounting, it may still require adjustments.

One common adjustment needed is for accounts receivable and accounts payable. In cash basis accounting, revenue is recognized when cash is received and expenses are recognized when cash is paid. However, if a business has accounts receivable or accounts payable, there may be revenue or expenses that have been earned or incurred but have not yet been paid or received.

To adjust for this, a business using cash basis accounting may need to make adjustments for accruals, deferrals, and other adjustments. For example, if a business has earned revenue but has not yet received payment, an adjusting entry would be made to recognize the revenue and increase accounts receivable.

Other adjustments may include the recognition of prepaid expenses or unearned revenue, as well as the recognition of accrued expenses or revenue. These adjustments can help ensure that a business's financial statements accurately reflect its financial position and performance.

It's important to note that while adjustments may be needed for cash basis accounting, they are generally simpler and less frequent than those required for accrual basis accounting.

What is the types for adjustments of accrual bases accounting?

There are several types of adjustments that may be required for accrual basis accounting. Some common types of adjustments include:

1. Accrued expenses: Accrued expenses are expenses that have been incurred but have not yet been paid. An adjusting entry is made to recognize these expenses and to increase the corresponding liability account.
2. Accrued revenue: Accrued revenue is revenue that has been earned but has not yet been received. An adjusting entry is made to recognize this revenue and to increase the corresponding asset account.
3. Prepaid expenses: Prepaid expenses are expenses that have been paid in advance. An adjusting entry is made to recognize the portion of the expense that has been used and to decrease the corresponding asset account.
4. Unearned revenue: Unearned revenue is revenue that has been received in advance. An adjusting entry is made to recognize the portion of the revenue that has been earned and to decrease the corresponding liability account.
5. Depreciation: Depreciation is the process of allocating the cost of a long-term asset over its useful life. An adjusting entry is made to recognize the portion of the asset's cost that has been used up and to decrease the corresponding asset account.

These adjustments ensure that a business's financial statements accurately reflect its financial position and performance. They also help to ensure that revenue and expenses are recognized in the correct accounting period.

What journal types is used to process adjustments?

Accrual or year-end adjustments are typically recorded in the general journal. The general journal is a catch-all journal where transactions that do not fit into specific specialised journals are recorded.

While it is possible to create a separate journal type such as "*Adjustments*" specifically for accrual or year-end adjustments, it is not a common practice. The general journal is often used for such adjustments as it allows for flexibility in recording various types of transactions and adjustments that may arise during the accounting period.

However, in osFinancials5/TurboCASH5 you may create a specific batch or journal type in Setup → Batch types menu on the Setup ribbon depending on the company's internal accounting procedures. You may configure the settings osFinancials5/TurboCASH5 can be a useful approach to segregate and control the processing of adjustment transactions.

Using an "Adjustments" journal type and configuring the batch settings can indeed help minimize errors and streamline the tracking and reporting of adjustment entries in osFinancials5/TurboCASH5. By setting up specific batch settings for the "Adjustments" journal type, you can customise the behaviour and attributes of the batch. This includes defining default accounts, specifying required fields, setting validation rules, and enabling specific features that align with your adjustment entry process.

Configuring the batch settings for adjustments can help enforce consistency and accuracy in recording adjustment transactions. For example, you can ensure that all required fields are correctly entered before a transaction is posted to the ledger, reducing the likelihood of missing or incomplete information. You can also set up validation rules to validate the data entered in certain fields, preventing entry errors.

Furthermore, by having a designated journal type for adjustments, you can easily generate specific batch type reports that focus solely on adjustment transactions. These reports can provide a consolidated view of all adjustment entries, making it easier to review, analyse, and reconcile the adjustments made during a specific period.

Additionally, the ability to search and filter specific adjustment transactions within the Set of Books can be beneficial for tracking and auditing purposes. You can use the search and filter functionality to narrow down the displayed transactions to only those categorized as adjustments. This helps isolate and review the adjustment entries separately, providing better visibility and control over the adjustment process.

Overall, by leveraging an "Adjustments" journal type and configuring the batch settings in osFinancials5/TurboCASH5, you can enhance accuracy, streamline reporting, and improve the management of adjustment transactions within your accounting system.

In the multi-user environment of osFinancials5/TurboCASH5, you can configure the journal type and access control settings in the Setup → Access control - Batches access tab on the Setup ribbon. This allows you to define the appropriate restrictions and permissions for each user, ensuring that adjustments are recorded and managed by designated individuals.

Additionally, the ability to block selected accounts from posting can further enhance control over the adjustment process. By blocking specific accounts, you can restrict users from posting to those accounts, maintaining the integrity of the financial data and ensuring accurate recording of accrued income and other adjustments.

It is important to align these practices with your organisation's internal accounting procedures and consult with accounting professionals to ensure compliance with accounting standards and best practices.

Created with the Standard Edition of HelpNDoc: Effortlessly bring your documentation online with HelpNDoc

Accrued income / Outstanding income / Income receivable : Accounting standards and Accounting method

Accrued income, also referred to as outstanding income or income receivable, is applicable to both small and medium entities (SMEs) and larger entities following IFRS (full) or IFRS for SMEs. The recognition and treatment of accrued income are generally consistent across these frameworks.

Under IFRS (full), accrued income is recognized as an asset and is accounted for using the accrual basis of accounting. It represents revenue that has been earned but not yet received in cash or its equivalent. This typically occurs when goods or services have been provided to customers, but the payment is not yet due or has not been received. Accrued income is recognized to reflect the economic benefit that the entity has earned.

Similarly, under IFRS for SMEs, there are specific provisions for the recognition, measurement, and presentation of accrued income. The standard provides guidance on when accrued income should be recognized as an asset and how it should be measured. The disclosure requirements may also differ from IFRS (full), tailored to the needs of SMEs.

Regarding the accounting method, the treatment of accrued income would also differ between the cash basis and accrual basis of accounting. Under the cash basis, income is recognized when cash is received, and therefore, accrued income would not be applicable. In contrast, under the accrual basis, accrued income is recognized as an asset even if cash has not been received yet, based on the concept of earning revenue.

It's important to note that the recognition and measurement of accrued income may vary based on the specific circumstances and industry practices. It's advisable to consult the applicable accounting standards and guidelines, as well as any specific requirements or interpretations for your jurisdiction and entity, to ensure proper treatment and disclosure of accrued income based on the chosen accounting framework.

What is Accrued income / Outstanding income?

Accrued (outstanding) income refers to income that has been earned by a business but has not yet been received or recorded as revenue. It represents the amount of income that is due to the business for goods sold or services rendered but for which the payment has not been received.

Accrued income typically arises when a business follows the accrual basis of accounting, which recognises revenue when it is earned, regardless of when the payment is actually received. This means that even if the payment for a sale or service is expected to be received in the future, the revenue is still recognized in the period when it was earned.

Examples of accrued income include:

1. Services rendered but not yet billed: If a business provides services to a customer but has not yet issued an invoice for those services, the income earned from those services would be considered accrued income.
2. Rent or interest income: If a business owns rental properties or lends money and the payment for rent or interest is due at the end of the month or at a later date, the income for that period would be accrued until the payment is received.
3. Sales made on credit: When a business sells goods or services on credit, meaning the customer is allowed to pay at a later date, the revenue from those sales is recognized as accrued income until the payment is received.

Accrued income is recorded as a current asset on the balance sheet until it is received. It represents the right to receive payment for goods sold or services rendered. Once the payment is received, the accrued income is reversed, and the corresponding revenue is recorded.

What is the batch type for accrued (outstanding) income?

Accrual or year-end adjustments are typically recorded in the general journal. The general journal is a catch-all journal where transactions that do not fit into specific specialised journals are recorded.

While it is possible to create a separate batch or journal type such as "*Adjustments*" specifically for accrual or year-end adjustments, it is not a common practice. The general journal is often used for such adjustments as it allows for flexibility in recording various types of transactions and adjustments that may arise during the accounting period.

What is the journal entries for accrued (outstanding) income?

To record the adjustment for accrued (outstanding) income, follow these steps:

1. Identify the income that has been earned but not yet received: Review your records and identify any income that has been earned during the accounting period but has not yet been received or recorded as revenue.
2. Create an Accrued income account: Establish a liability account in your chart of accounts called "*Accrued Income*" or a similar name. Assign it a suitable account number based on your accounting system's numbering convention.

> *Sub-accounts: It is advisable to create a main account called "Accrued Income" in the current asset section of the balance sheet. This main account can serve as a summary account to track all accrued income amounts that are yet to be received or invoiced.*
>
> *Under the "Accrued Income" main account, you can create sub-accounts to categorize specific types of accrued income. For example, you can create sub-accounts for "Sales in Advance," "Rent Received in Advance," or any other specific types of accrued income relevant to your business.*
>
> *By using sub-accounts, you can provide more detailed information about the nature and source of the accrued income. It allows for better organization and tracking of the various sources of accrued income within the overall "Accrued Income" category.*
>
> *Creating sub-accounts helps in presenting a clear and comprehensive view of your accrued income in the balance sheet. It also facilitates easier analysis and monitoring of the different types of accrued income and their impact on the financial position of the business.*
>
> *Remember to consult with an accounting professional or refer to accounting standards specific to your jurisdiction to ensure accurate and compliant reporting of accrued income in your financial statements.*

3. Record the adjustment: Debit the Accrued Income account to increase the balance and recognize the amount of income that has been earned but not yet received. Credit the corresponding revenue account to reflect the income earned.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Accrued Income	*Current asset*	*$1,000*	
Credit: Revenue account	*Revenue*		*$1,000*

4. Review and adjust the accrued income: Periodically review and update the Accrued Income account to reflect any changes in the outstanding income. This could involve recording additional accrued income or adjusting for any receipts or adjustments related to the outstanding income.

By recording the accrued income, you are recognizing the revenue that has been earned but not yet

received. This adjustment ensures that the financial statements reflect the true financial position and performance of the business by including the income that has been earned, even though it has not been received in cash or recorded as revenue.

The specific accounts used and the timing of recognising the accrued income may vary based on your business's accounting policies and the nature of the transaction. Consulting with an accounting professional or referring to the accounting standards applicable to your jurisdiction can provide further guidance on the appropriate treatment of accrued income or outstanding income in your financial statements.

Treatment of accrued (outstanding) income in the new financial year

The treatment of accrued (outstanding) income in the new financial year depends on the accounting method used by the company. In some cases, it may be necessary to reverse the accrued income recorded in the previous financial year, while in other cases, it may not be required.

1. Accrual Basis Accounting:
    - If the company follows the accrual basis of accounting, where revenues are recognized when earned and not when cash is received, the accrued income recorded in the previous financial year should be reversed.
    - At the start of the new financial year, the accrued income recorded in the previous year is no longer outstanding because it has been earned and should now be recognized as revenue.
    - The reversal entry would typically involve debiting the Accrued income account and crediting the appropriate revenue account(s) to recognise the revenue earned.
2. Cash Basis Accounting:
    - If the company follows the cash basis of accounting, where revenues are recognised only when cash is received, there is no need to reverse the accrued income recorded in the previous financial year.
    - Accrued income is not recognised until the cash is actually received in the new financial year.
    - The recognition of revenue will occur when the payment is received, and the journal entry would typically involve debiting the Cash account and crediting the appropriate revenue account(s) to recognize the revenue earned.

It's important to note that the specific accounting treatment may vary based on the company's accounting policies, local regulations, and specific circumstances. It is recommended to consult with a qualified accountant or accounting professional to determine the appropriate treatment of accrued income in your

specific situation.

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Income received in advance / Unearned revenue / Deferred revenue : Accounting standards and Accounting method

The concept of income received in advance, also known as unearned revenue or deferred revenue, is applicable to both small and medium entities (SMEs) and larger entities following IFRS (full) or IFRS for SMEs. The treatment of income received in advance is generally consistent across the two frameworks.

Under IFRS (full), income received in advance is recognized as a liability and is accounted for using the accrual basis of accounting. It represents cash received from customers or clients for goods or services that are yet to be provided. The liability is recognized because the revenue has not been earned at the time of receipt. As the goods or services are delivered or performed, the liability is reduced, and the corresponding revenue is recognized.

Similarly, under IFRS for SMEs, there are specific provisions for the recognition, measurement, and presentation of income received in advance. The standard provides guidance on how to account for unearned revenue, including when it should be recognized as a liability and how it should be measured. The disclosure requirements may also differ from IFRS (full), being more streamlined and tailored to the needs of SMEs.

In terms of the accounting method, the treatment of income received in advance would also differ between the cash basis and accrual basis of accounting. Under the cash basis, income is recognized when cash is received, and therefore, income received in advance would be recognized as revenue immediately upon receipt. In contrast, under the accrual basis, income received in advance is recognized as a liability and is gradually recognized as revenue over time as the goods or services are provided.

It's important to consult the specific accounting standards and guidelines applicable to your jurisdiction and entity to ensure proper treatment and disclosure of income received in advance based on the chosen accounting framework.

What is income received in advance?

Income received in advance, also known as unearned revenue or deferred revenue, refers to payments

received from customers or clients for goods or services that have not yet been provided. It represents a liability for the business because the revenue has been received in advance of earning it.

When a business receives income in advance, it has an obligation to deliver the goods or services at a later date. Until that obligation is fulfilled, the amount received is classified as a liability on the balance sheet.

Examples of income received in advance include:

1. Subscriptions: When a customer pays for a subscription service upfront, such as an annual magazine subscription or a software subscription.
2. Rent: If a tenant pays rent for several months in advance, the portion of rent that corresponds to future periods is considered income received in advance.
3. Service contracts: When a business enters into a service contract with a customer and receives payment upfront before providing the services.
4. Membership fees: Membership-based organizations that collect fees in advance from their members.

To account for income received in advance, the business initially records it as a liability on the balance sheet. As the goods or services are provided over time, the liability is gradually recognized as revenue in the income statement. The amount recognized as revenue is based on the portion of the goods or services delivered or consumed.

Proper accounting for income received in advance ensures that revenue is recognized in the appropriate accounting periods, aligning with the matching principle in accrual accounting.

What is the batch type for Income received in advance?

Accrual or year-end adjustments are typically recorded in the general journal. The general journal is a catch-all journal where transactions that do not fit into specific specialised journals are recorded.

While it is possible to create a separate batch or journal type such as "*Adjustments*" specifically for accrual or year-end adjustments, it is not a common practice. The general journal is often used for such adjustments as it allows for flexibility in recording various types of transactions and adjustments that may arise during the accounting period.

The "*Adjustments*" batch type or journal can be used to record transactions related to income received in advance instead of using the general journal. The "*Adjustments*" batch type or journal provides flexibility for recording various types of adjustments and can be customized to suit your specific needs.

Adjustments - Income received in advance - how would this be recorded?

Adjustments - Income received in advance or unearned revenue refers to a category of adjustments made in accounting to account for revenue that has been received by a business in advance but has not yet been earned. It represents an obligation for the business to deliver goods or services in the future in order to fulfil the revenue that has been received upfront.

When a business receives payment from a customer before providing the goods or services, it is considered unearned revenue or income received in advance. The business has a liability to fulfil its obligation to the customer by delivering the promised goods or services.

The Adjustments - Income received in advance or unearned revenue entry is typically recorded at the time of receiving the payment. It involves debiting the liability account (e.g., Unearned Revenue or Income Received in Advance) and crediting the cash or bank account to reflect the inflow of funds.

As the business fulfils its obligation and earns the revenue, the unearned revenue is gradually recognized as revenue in the income statement. This is done through adjusting entries, which involve debiting the Unearned Revenue account and crediting the revenue account corresponding to the goods or services provided.

By making adjustments for income received in advance or unearned revenue, the financial statements accurately reflect the revenue that has been earned during a specific accounting period. It ensures that the recognition of revenue aligns with the actual delivery of goods or services, providing a more accurate representation of the business's financial performance.

To record the adjustment for income received in advance, follow these steps:

1. Determine the amount of income received in advance: Identify the total amount of income that has been received from customers but has not yet been earned. This could include prepayments for services or goods to be delivered in the future.
2. Create an "*Income Received in Advance*" account: Establish a liability account in your chart of accounts called "Income Received in Advance" or a similar name. Assign it a suitable account number based on your accounting system's numbering convention. This account represents the amount of unearned revenue.

Sub-accounts: Creating sub-accounts under the main account "Income received in Advance" or "Unearned revenue" in the current liability section of the balance sheet is a common and advisable practice. It provides a structured approach to track and categorize different types of unearned income or revenue received in advance.

By creating sub-accounts, you can better classify and differentiate the sources of unearned income. This allows for more detailed reporting and analysis of the specific types of unearned income, such as subscriptions, rent received in advance, or any other relevant categories for your business.

Using sub-accounts also enhances the clarity and transparency of your financial statements. It helps stakeholders understand the composition and magnitude of the unearned income and its impact on the overall financial position of the business.

When creating sub-accounts, it is important to follow accounting standards and guidelines applicable to your jurisdiction. These standards provide specific requirements and recommendations for the presentation and disclosure of unearned revenue or income received in advance in financial statements.

3. Record the adjustment: Debit the "Income Received in Advance" account for the amount of income received in advance. This entry increases the liability for unearned revenue.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Income Received in Advance	*Current liability*	*$1,000*	
Credit: Revenue account (related to the earned income)	*Revenue*		*$1,000*

This entry recognizes the decrease in the liability for unearned revenue and the increase in the income account as the revenue is earned.

4. Recognize the earned income: As the revenue is earned over time or when the related goods or services are delivered, you will need to record the corresponding revenue.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Revenue account (related to the earned income)	*Revenue*	*$1,000*	
Credit: Income Received in Advance	*Current liability*		*$1,000*

This entry reduces the liability for unearned revenue and recognizes the earned income in the appropriate income account.

By recording the adjustment for income received in advance, you are appropriately matching revenue with the related expenses and recognizing the income as it is earned over time. This adjustment ensures that your financial statements reflect the actual revenue earned during the reporting period.

The specific accounts used and the timing of recognising the earned income may vary based on your business's accounting policies and the nature of the transaction. Consulting with an accounting professional or referring to the accounting standards applicable to your jurisdiction can provide further guidance on the appropriate treatment of income received in advance in your financial statements.

Treatment of a Income received in advance (Unearned income) in the new financial year?

1. In the new financial year, the treatment of income received in advance (unearned income) depends on whether the income has been earned or not.
2. If the income has been earned in the new financial year:
    - Debit the "Income Received in Advance" account (liability) to reduce the balance.
    - Credit the appropriate income account to recognize the earned income.
3. This entry will transfer the amount from the "Income Received in Advance" account to the income account, reflecting the income that has been earned in the new financial year.
4. If the income has not been earned in the new financial year:
    - No journal entry is required as the income remains unearned and will continue to be recorded as a liability in the "Income Received in Advance" account.

It's important to review the specific circumstances and timing of the income to determine if it has been earned or not. This will guide the appropriate treatment in the new financial year.

The specific accounts used and the timing of recognising the unearned revenue or outstanding income may vary based on your business's accounting policies and the nature of the transaction. Consulting with an accounting professional or referring to the accounting standards applicable to your jurisdiction can provide further guidance on the appropriate treatment of accrued income or outstanding income in your financial statements.

Is Adjustments - Income received in advance (Unearned revenue) only applicable to the accrual basis accounting method or does it apply to the cash basis accounting methods?

The concept of "*Income received in advance*" or "*Unearned revenue*" generally applies to the accrual basis accounting method.

Under the accrual basis, revenue is recognised when it is earned, regardless of when the payment is received. If a customer pays in advance for goods or services that will be provided in the future, the payment is recorded as a liability (unearned revenue) until the revenue is earned.

In contrast, the cash basis accounting method recognises revenue when cash is received. With cash basis accounting, there is no concept of unearned revenue because revenue is only recorded when the cash is actually received.

Therefore, the specific account "*Adjustments - Income received in advance*" would typically be applicable to the accrual basis accounting method, where there is a need to record and track unearned revenue. In cash basis accounting, such adjustments may not be necessary as revenue is recognized upon receipt of cash.

It's important to note that the choice of accounting method (accrual basis or cash basis) depends on various factors, including legal requirements, business needs, and financial reporting purposes. Always consult with an accounting professional or refer to the accounting standards applicable to your jurisdiction for guidance on the appropriate accounting treatment based on your specific circumstances.

Created with the Standard Edition of HelpNDoc: Keep Your PDFs Safe from Unauthorized Access with These Security Measures

---

Accrued expenses / Outstanding expenses : Accounting standards and Accounting method

The concept of accrued expenses, also known as outstanding expenses, is applicable to both small and medium entities (SMEs) and larger entities following IFRS (full) or IFRS for SMEs. The treatment of accrued expenses is generally consistent across the two frameworks.

Under IFRS (full), accrued expenses are recognized as liabilities and are accounted for using the accrual basis of accounting. Accrued expenses represent expenses that have been incurred but not yet paid or

recorded in the financial statements. Examples of accrued expenses include salaries payable, utility bills accrued but not yet paid, or interest payable on outstanding loans. These expenses are recognized as liabilities and are subsequently recorded as expenses when they are incurred, even if payment has not been made.

Under IFRS for SMEs, there are specific provisions for the recognition, measurement, and presentation of accrued expenses. The standard provides guidance on how to account for accrued expenses, including when they should be recognized as liabilities and how they should be measured. The disclosure requirements may also differ from IFRS (full), being more streamlined and tailored to the needs of SMEs.

Regarding the accounting method (cash basis or accrual basis), the treatment of accrued expenses would generally be different. The cash basis of accounting recognizes expenses and liabilities only when cash is paid or received, and therefore, accrued expenses would not be recorded as liabilities under the cash basis. In contrast, under the accrual basis of accounting, accrued expenses are recognized as liabilities when the expenses are incurred, even if the payment has not yet been made.

It's important to consult the specific accounting standards and guidelines applicable to your jurisdiction and entity to ensure proper treatment and disclosure of accrued expenses based on the chosen accounting framework.

What is Accrued expenses / Outstanding expenses?

Accrued expenses, also known as outstanding expenses, refer to expenses that have been incurred by a business but have not yet been paid or recorded in the accounting records. These expenses are recognised and recorded in the period in which they are incurred, even if the payment is due at a later date.

Examples of accrued expenses include:

1. Salaries and wages: If employees have worked for a certain period but have not yet been paid, their salaries and wages would be considered as accrued expenses.
2. Utilities: If the business has consumed utilities such as electricity, water, or gas but has not yet received the bill or made the payment, the expenses would be accrued.
3. Rent: If rent is due at the end of the month but the payment has not yet been made, the rent expense would be accrued.
4. Interest: If the business has borrowed money and the interest expense has accrued but has not yet been paid, it would be recorded as an accrued expense.
5. Taxes: If the business has incurred taxes but the payment is due at a later date, the taxes would be considered as accrued expenses.

Accrued expenses are recorded as a liability on the balance sheet, indicating the amount owed by the business. The corresponding entry is made in the expense account on the income statement to recognize the expense for the period.

By recording accrued expenses, the financial statements provide a more accurate representation of the expenses incurred during a particular period, even if the cash outflow has not occurred yet. It ensures that the financial statements reflect the true financial position and performance of the business.

Adjustments - Accrued expenses / Outstanding expenses - how would this be recorded?

"*Adjustments - Accrued expenses / Outstanding expenses*" refers to the process of recording and adjusting the financial transactions related to expenses that have been incurred but not yet paid or recorded in the current accounting period. It involves recognising the expenses in the income statement and creating a corresponding liability on the balance sheet to reflect the amount owed for these outstanding expenses.

Accrued expenses or outstanding expenses are liabilities that arise when a business incurs expenses but has not yet paid for them. These expenses are typically recorded and recognised in the period in which they are incurred, regardless of when the actual payment occurs. By accruing the expenses, the financial statements provide a more accurate representation of the expenses for the given period.

The "*Adjustments - Accrued expenses / Outstanding expenses*" entry is used to adjust the accounts and reflect the unpaid expenses. The adjustment is made by debiting the respective expense accounts to recognize the expense in the income statement and crediting the Accrued expenses or Outstanding expenses account to record the liability.

This adjustment is necessary to ensure that the financial statements accurately reflect the expenses incurred and the corresponding liabilities as of the end of the accounting period. It helps in providing a more complete and accurate picture of the business's financial position and performance.

To record the adjustment for accrued expenses or outstanding expenses, follow these steps:

1. Identify the accrued expenses: Determine the expenses that have been incurred but not yet paid as of the end of the accounting period. These expenses could include salaries, utilities, rent, interest, or any other expenses that are recognized but unpaid.
2. Create an Accrued expenses account: Establish a liability account in your chart of accounts called "Accrued expenses" or "Outstanding expenses." Assign it a suitable account number based on your accounting system's numbering convention. This account will track the amount owed for the accrued expenses.

Sub-accounts: Creating sub-accounts under the main account "Outstanding expenses" or "Accrued expenses" in the current liability section of the balance sheet is a common and advisable practice. It provides a structured approach to track and categorize different types of accrued expenses or outstanding expenses.

By creating sub-accounts, you can better classify and differentiate the sources of accrued expenses or outstanding expenses. This allows for more detailed reporting and analysis of the specific types of accrued expenses or outstanding expenses, such as subscriptions, salaries and wages, interest, rent, or any other relevant categories for your business.

Using sub-accounts also enhances the clarity and transparency of your financial statements. It helps stakeholders understand the composition and magnitude of the accrued expenses or outstanding expenses and its impact on the overall financial position of the business.

When creating sub-accounts, it is important to follow accounting standards and guidelines applicable to your jurisdiction. These standards provide specific requirements and recommendations for the presentation and disclosure of accrued expenses or outstanding expenses in financial statements.

3. Record the adjustment: Debit the respective expense accounts for the amount of the accrued expenses. This recognizes the expense in the income statement for the period. Credit the Accrued expenses account for the same amount. This records the liability for the unpaid expenses.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Salaries and wages	*Expense*	*$2,000*	
Credit: Accrued expenses	*Current liability*		*$2,000*

4. Review and adjust the accrued expenses: Periodically review and update the Accrued expenses account to reflect any changes in the outstanding expenses. This could involve recording additional accruals or adjusting for any payments made or corrections required.

By recording the accrued expenses, you are recognizing the expenses that have been incurred but not yet paid. This adjustment ensures that the expenses are properly recognized in the income statement, even though the payment has not been made. It also creates a corresponding liability on the balance sheet to reflect the amount owed for these expenses.

The specific accounts used and the timing of recognising the accrued expenses or outstanding expenses may vary based on your business's accounting policies and the nature of the transaction. Consulting with an

accounting professional or referring to the accounting standards applicable to your jurisdiction can provide further guidance on the appropriate treatment of accrued expenses or outstanding expenses in your financial statements.

Treatment of Accrued expenses (Outstanding expenses) in the new financial year?

In the new financial year, the treatment of accrued expenses or outstanding expenses depends on the specific circumstances and accounting policies of the business. Here are some common approaches:

1. Reverse the previous year's accrual: If an expense was accrued at the end of the previous financial year but has not yet been paid, it may be appropriate to reverse the accrual entry in the new financial year. This is done by debiting the accrued expense account and crediting the corresponding expense account. By reversing the accrual, the expense is no longer recognized in the new financial year until the actual payment is made.
2. Record the actual payment: When the accrued expense is eventually paid in the new financial year, you would record the payment by debiting the relevant expense account and crediting the cash or accounts payable account, depending on the payment method. This entry recognizes the expense in the new financial year and reduces the liability associated with the outstanding expense.
3. Adjust for any changes: If there are any changes in the amount of the accrued expense or outstanding expense, adjustments should be made accordingly. For example, if the initial accrual was an estimate and the actual amount paid differs, an adjustment entry may be needed to reflect the correct expense amount.

It's important to note that the specific accounting treatment may vary based on the accounting standards, regulations, and company policies. It's recommended to consult with an accounting professional or refer to the applicable accounting guidelines to ensure accurate and compliant treatment of accrued expenses or outstanding expenses in the new financial year.

Accrued expenses (Outstanding expenses) is this applicable to cash basis accounting method?

Accrued expenses, also known as outstanding expenses, are typically associated with the accrual basis accounting method rather than the cash basis accounting method.

In accrual accounting, expenses are recognised when they are incurred, regardless of when the payment is made. This means that even if the payment for an expense has not been made yet, it is still recognized as

an expense in the accounting period in which it was incurred. Accrued expenses represent expenses that have been incurred but not yet paid.

On the other hand, the cash basis accounting method recognizes expenses only when the actual payment is made. With the cash basis, expenses are recorded when the cash outflow occurs, rather than when the expense is incurred. Therefore, accrued expenses are not applicable to the cash basis accounting method since expenses are not recognized until the cash payment is made.

It's important to choose the appropriate accounting method (either accrual basis or cash basis) based on the nature and size of your business, as well as any legal or regulatory requirements. Generally, larger businesses and entities are required to use the accrual basis accounting method, while smaller businesses may opt for the cash basis method for simplicity and ease of recording transactions.

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Prepaid expenses / Expenses paid in advace

Prepaid expenses : Accounting standards and Accounting method

The concept of prepaid expenses, also known as expenses paid in advance, is applicable to both small and medium entities (SMEs) and larger entities following IFRS (full) or IFRS for SMEs. The treatment of prepaid expenses may vary slightly between the two frameworks.

Under IFRS (full), prepaid expenses are recognized as assets and are accounted for using the accrual basis of accounting. Prepaid expenses represent payments made in advance for goods or services that will be received in the future. Examples of prepaid expenses include prepaid rent, prepaid insurance premiums, or prepaid subscriptions. These expenses are initially recorded as assets and are gradually recognized as expenses over the period to which they relate.

Under IFRS for SMEs, there are specific provisions for the recognition, measurement, and presentation of prepaid expenses. The standard provides guidance on how to account for prepaid expenses, including when they should be recognized as assets and how they should be measured. The disclosure requirements may also differ from IFRS (full), being more streamlined and tailored to the needs of SMEs.

Regarding the accounting method (cash basis or accrual basis), the treatment of prepaid expenses would generally be different. The cash basis of accounting recognizes expenses and assets only when cash is paid or received, and therefore, prepaid expenses would not be recorded as assets under the cash basis. In contrast, under the accrual basis of accounting, prepaid expenses are recognized as assets when the payment is made, and the related expenses are gradually recognized over the period to which they relate.

It's important to consult the specific accounting standards and guidelines applicable to your jurisdiction and entity to ensure proper treatment and disclosure of prepaid expenses based on the chosen accounting framework.

What is Prepaid expenses?

Prepaid expenses refer to expenses that have been paid in advance by a business but have not yet been consumed or used up. These expenses are considered assets because they represent future economic benefits that the business will receive.

When a business pays for an expense in advance, it initially records the payment as a prepaid expense on the balance sheet. This is because the payment has not yet been "*used*" or "*consumed*" to generate an expense in the relevant accounting period. Instead, it represents a future benefit that will be realised over time.

Common examples of prepaid expenses include:

1. Insurance premiums: If a business pays for insurance coverage for a future period, the portion of the premium that corresponds to the period yet to be covered is considered a prepaid expense.
2. Rent: If a business pays rent in advance for a future period, the portion of the rent that corresponds to the period yet to be occupied is considered a prepaid expense.
3. Subscriptions: If a business pays for a subscription service or membership in advance, the portion of the subscription fee that covers the future period is treated as a prepaid expense.
4. Supplies: If a business purchases supplies or inventory in advance and hasn't yet used them in its operations, the cost of those supplies is recorded as a prepaid expense.

Prepaid expenses are typically classified as current assets on the balance sheet if they will be consumed or used within one year. If the prepaid expense extends beyond one year, it is classified as a long-term asset.

As time passes and the prepaid expense is "used up" or consumed, the amount is gradually recognized as an expense in the appropriate accounting period. This is done through adjusting entries, which reduce the prepaid expense asset account and record the corresponding expense in the income statement.

Proper management and accounting for prepaid expenses are important for accurate financial reporting and ensuring that expenses are appropriately matched with the periods in which they provide economic benefits to the business.

Adjustments - Prepaid expenses - how would this be recorded?

"*Adjustments - Prepaid expenses*" refers to a category or journal type used to record adjustments related to prepaid expenses in accounting. Prepaid expenses are expenses that have been paid in advance but have

not yet been consumed or used up. They are considered assets because they represent future economic benefits that the business will receive.

When a business pays for an expense in advance, such as insurance premiums, rent, or annual subscriptions, it initially records the payment as a prepaid expense. However, over time, as the prepaid expense is consumed or utilized, it needs to be recognized as an expense in the appropriate accounting periods.

The "*Adjustments - Prepaid expenses*" category or journal type allows for the recording of adjusting entries related to prepaid expenses. These entries are made to reflect the portion of the prepaid expense that has been consumed or expired during a specific accounting period.

> For example, if a business prepaid $12,000 for a one-year insurance policy, and six months have passed, $6,000 of the prepaid expense has been consumed. To adjust the accounts, an entry would be made in the "Adjustments" journal to record the prepaid expense asset account and recognise the $6,000 as an expense in the income statement by decreasing the insurance expense or insurance premiums account.

It's important to review prepaid expenses regularly and make appropriate adjustments to ensure accurate financial reporting and the proper matching of expenses with the periods in which they are incurred or consumed.

To record the adjustment for prepaid expenses, follow these steps:

1. Identify the prepaid expenses: Determine the amount of prepaid expenses that have been paid in advance and are yet to be consumed or used up. This may include items such as prepaid insurance premiums, prepaid rent, prepaid subscriptions, or any other prepaid expenses relevant to your business.
2. Create a Prepaid expenses account: Establish a new asset account in your chart of accounts called "*Prepaid expenses*" or a similar name. Assign it a suitable account number based on your accounting system's numbering convention.

> *Sub-accounts: Creating sub-accounts under the main account "Prepaid expenses" or "Expenses paid in advance" in the current asset section of the balance sheet is a common and advisable practice. It provides a structured approach to track and categorize different types of prepaid expenses or expenses paid in advance.*
>
> *By creating sub-accounts, you can better classify and differentiate the sources of prepaid expenses or expenses paid in advance. This allows for more detailed reporting and analysis of the specific types of prepaid expenses or expenses paid in advance such as "Prepaid insurance, Prepaid rent", or "Prepaid subscriptions", depending on the nature of the expenses incurred.*
>
> *Using sub-accounts also enhances the clarity and transparency of your financial statements. It helps stakeholders understand the composition and magnitude of the prepaid expenses or*

expenses paid in advance and its impact on the overall financial position of the business.

When creating sub-accounts, it is important to follow accounting standards and guidelines applicable to your jurisdiction. These standards provide specific requirements and recommendations for the presentation and disclosure of prepaid expenses or expenses paid in advance in financial statements.

3. Record the adjustment: Debit the Prepaid expenses account for the portion of the prepaid expense that corresponds to the current accounting period. Credit the relevant expense account for the same amount. This entry recognizes the portion of the prepaid expense that has now become an expense in the current period.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Prepaid insurance	*Current asset*	*$1,000*	
Credit: Insurance premiums	*Expense*		*$1,000*

4. Review and adjust the prepaid expenses: Periodically review and update the Prepaid expenses account to reflect any changes in the prepaid expenses. This could involve recording additional prepaid expenses or adjusting for any portions that have been consumed or used up.

By recording the prepaid expenses adjustment, you are recognising the portion of the prepaid expense that corresponds to the current accounting period as an expense. This adjustment ensures that expenses are properly matched with the periods in which they provide economic benefits to the business, resulting in accurate financial reporting.

The specific accounts used and the timing of recognising the prepaid expenses may vary based on your business's accounting policies and the nature of the transaction. Consulting with an accounting professional or referring to the accounting standards applicable to your jurisdiction can provide further guidance on the appropriate treatment of prepaid expenses in your financial statements.

Treatment of Prepaid expenses in the new financial year?

In the new financial year, the treatment of prepaid expenses depends on whether the prepaid expenses are fully consumed or if there is still an unexpired portion remaining.

1. Fully consumed prepaid expenses: If the prepaid expenses have been fully consumed or used up during the previous financial year, there is no further adjustment needed in the new financial year. The

prepaid expenses account will be reduced to zero, and the entire amount would have been recognized as an expense in the previous period.

2. Unexpired portion of prepaid expenses: If there is an unexpired portion of prepaid expenses remaining at the end of the previous financial year, it represents a future economic benefit to the business. In the new financial year, you need to recognize the portion of the prepaid expenses that corresponds to the current accounting period as an expense.

To record the adjustment for the unexpired portion of prepaid expenses in the new financial year, follow these steps:

- Identify the remaining unexpired portion of prepaid expenses.
- Debit the relevant expense account for the portion of the prepaid expense that corresponds to the current accounting period.
- Credit the Prepaid expenses account for the same amount.

This entry recognises the portion of the prepaid expense that has now become an expense in the new period. The Prepaid expenses account will reflect the reduced unexpired portion.

Remember to review and adjust the prepaid expenses account periodically throughout the new financial year to reflect any changes or updates in the prepaid expenses.

The specific accounts used and the timing of recognising the prepaid expenses may vary based on your business's accounting policies and the nature of the transaction. Consulting with an accounting professional or referring to the accounting standards applicable to your jurisdiction can provide further guidance on the appropriate treatment of prepaid expenses in your financial statements.

Prepaid expenses - is this applicable to cash basis accounting method?

Prepaid expenses are typically not applicable to the cash basis accounting method.

In the cash basis accounting method, revenue and expenses are recognised when cash is received or paid, respectively. This means that expenses are recorded when the actual payment is made, rather than when the economic benefit is consumed or received.

Prepaid expenses, on the other hand, represent expenses that have been paid in advance but have not yet been consumed or utilised. They are recognised as assets on the balance sheet until they are gradually expensed over the period in which the related benefit is received.

Since the cash basis accounting method focuses on cash transactions, it does not recognise prepaid

expenses as assets or allow for their gradual recognition as expenses over time. Instead, expenses are recorded when the cash is paid, regardless of the period to which they relate.

Prepaid expenses are more commonly associated with the accrual basis accounting method, where revenue and expenses are recognized when earned or incurred, regardless of the timing of cash flows.

It's important to choose the appropriate accounting method (either accrual basis or cash basis) based on the nature and size of your business, as well as any legal or regulatory requirements. Generally, larger businesses and entities are required to use the accrual basis accounting method, while smaller businesses may opt for the cash basis method for simplicity and ease of recording transactions.

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

---

Accrued or outstanding expenses : Accounting standards and Accounting method

The concept of accrued or outstanding expenses is applicable to both small and medium entities (SMEs) and larger entities following IFRS (full) or IFRS for SMEs. The treatment of accrued expenses may vary slightly between the two frameworks.

Under IFRS (full), accrued expenses are recognized as liabilities and are accounted for using the accrual basis of accounting. Accrued expenses are expenses that have been incurred but not yet paid or recorded in the financial statements. Examples of accrued expenses include accrued salaries, accrued interest, or accrued utilities. These expenses are recognized as a liability and are typically recorded when the related goods or services have been received, regardless of whether the cash payment has been made.

Under IFRS for SMEs, there are specific provisions for the recognition, measurement, and presentation of accrued expenses. The standard provides guidance on how to account for accrued expenses, including when they should be recognized as liabilities and how they should be measured. The disclosure requirements may also differ from IFRS (full), being more streamlined and tailored to the needs of SMEs.

Regarding the accounting method (cash basis or accrual basis), the treatment of accrued expenses would generally be different. The cash basis of accounting recognizes expenses and liabilities only when cash is paid, and therefore, accrued expenses would not be recorded as liabilities under the cash basis. In contrast, under the accrual basis of accounting, accrued expenses are recognized as liabilities when the related expenses have been incurred, regardless of the cash payment.

It's important to consult the specific accounting standards and guidelines applicable to your jurisdiction and entity to ensure proper treatment and disclosure of accrued or outstanding expenses based on the chosen accounting framework.

What is accrued or outstanding expenses?

Accrued or outstanding expenses refer to expenses that have been incurred but have not yet been paid or recorded in the accounting books by the end of the accounting period. These expenses are recognised as liabilities because they represent an obligation of the business to make future payments.

Accrued expenses can include various types of costs, such as salaries and wages, interest, utilities, rent, taxes, and professional fees. They typically arise when the expense is recognized in the accounting period, but the payment is due in a subsequent period.

For example, if a business receives an invoice for utility expenses at the end of the month but has not yet paid the bill, the utility expense is considered an accrued expense. The business has incurred the expense during the month, and even though the payment has not been made, it is recorded as a liability in the financial statements.

Accrued expenses are typically recorded through an adjusting entry at the end of the accounting period to ensure that the expense is properly recognized in the period it relates to. This helps in matching expenses with the revenues they generate, providing a more accurate representation of the financial position and performance of the business.

Accrued expenses are reversed in the following accounting period when the actual payment is made. The reversal ensures that the expense is not double-counted, and the liability is removed from the books.

Accrued or outstanding expenses are relevant for both cash basis and accrual basis accounting methods, as they reflect the timing of the expense recognition and payment, regardless of the method used to track cash flows.

Adjustments - Accrued expenses (Outstanding expenses) - how would this be recorded?

To record the adjustment for accrued expenses (outstanding expenses), follow these steps:

1. Identify the accrued expenses: Determine the expenses that have been incurred but not yet paid by the end of the accounting period. This could include items like salaries, rent, utilities, or any other expenses that are accrued.
2. Create an Accrued Expenses account: Establish a liability account in your chart of accounts called "Accrued Expenses" or a similar name. Assign it a suitable account number based on your accounting

system's numbering convention.

> *Sub-accounts: Creating a main account called "Accrued expenses" or "Outstanding expenses" in the current liabilities section of the balance sheet is a common practice. This main account serves as a summary account to track all the accrued or outstanding expenses that are yet to be paid by the end of the accounting period.*
>
> *Under the "Accrued expenses" or "Outstanding expenses" main account, you can create sub-accounts to categorize specific types of accrued expenses. For example, you can create sub-accounts for "Salaries payable," "Rent payable," "Utilities payable," or any other specific types of expenses relevant to your business.*
>
> *By using sub-accounts, you can provide more detailed information about the nature and source of the accrued expenses. It allows for better organization and tracking of the various sources of accrued expenses within the overall "Accrued expenses" category.*
>
> *Creating sub-accounts helps in presenting a clear and comprehensive view of your accrued expenses in the balance sheet. It also facilitates easier analysis and monitoring of the different types of accrued expenses and their impact on the financial position of the business.*

3. Record the adjustment: Debit the appropriate expense accounts for the value of the accrued expenses. This entry recognizes the expenses incurred during the period.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Rent paid	*Expense*	*$1,000*	
Credit: Accrued expenses / Outstanding expenses	*Current liabilities*		*$1,000*

4. Review and adjust the accrued expenses: Periodically review and update the Accrued Expenses account to reflect any changes in the liabilities. This could involve recording additional accruals or adjusting for any payments made towards the accrued expenses.

By recording the accrued expenses, you are recognizing the expenses that have been incurred but not yet paid. This adjustment helps in accurately reflecting the financial obligations of the business and ensures that the expenses are properly accounted for in the financial statements.

Treatment of Accrued expenses (Outstanding expenses) in the new financial year?

When transitioning to a new financial year, the treatment of accrued expenses (outstanding expenses)

depends on whether the expenses have been paid or settled by the end of the previous financial year. Here are two scenarios to consider:

1. Unpaid Accrued Expenses:
    - If the accrued expenses from the previous financial year remain unpaid at the end of that year, they will continue to be recorded as liabilities in the new financial year.
    - Create a new entry in the new financial year to recognize the outstanding expenses and update the balances accordingly.
    - The journal entry typically involves debiting the appropriate expense account and crediting the accrued expenses account to clear the previous year's accruals.
    - This adjustment ensures that the expenses are properly recorded in the new financial year, reflecting the actual liability owed.
2. Paid Accrued Expenses:
    - If the accrued expenses from the previous financial year were paid or settled in the new financial year before finalizing the accounts, no adjustment is needed.
    - The expenses would have been recorded in the previous financial year when they were accrued, and the subsequent payment clears the liability in the new financial year.
    - Ensure that the payment is correctly recorded in the accounts, typically by debiting the corresponding expense account and crediting the cash or bank account.

In both cases, it's essential to review and reconcile the accrued expenses accounts from the previous financial year with the actual payments and expenses incurred in the new financial year to ensure accurate financial reporting.

The specific accounts used and the timing of recognising the Accrued expenses (Outstanding expenses) may vary based on your business's accounting policies and the nature of the transaction. Consulting with an accounting professional or referring to the accounting standards applicable to your jurisdiction can provide further guidance on the appropriate treatment of prepaid expenses in your financial statements.

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Consumable stores on hand

Consumable stores on hand : Accounting standards and Accounting method

The concept of consumable stores on hand is applicable to various types of entities and accounting frameworks, including small and medium entities (SMEs) under both IFRS (full) and IFRS for SMEs. However, the specific treatment and disclosure requirements may vary depending on the accounting framework and the size of the entity.

Under IFRS (full), consumable stores on hand are typically classified as inventory and are accounted for using the accrual basis of accounting. The entity is required to recognize and measure inventory at the lower of cost or net realizable value, and disclose relevant information such as the accounting policies, carrying amounts, and any impairment losses.

Under IFRS for SMEs, there is a simplified approach to accounting for inventories, which may include consumable stores on hand. The standard provides guidance on the cost formula that can be used to measure inventories, such as the weighted average cost or the first-in, first-out (FIFO) cost. Additionally, the disclosure requirements are less extensive compared to IFRS (full).

Regarding the accounting method (cash basis or accrual basis), the treatment of consumable stores on hand may differ. The cash basis of accounting recognizes transactions and events only when cash is received or paid, and inventory is not typically recorded as an asset. However, under the accrual basis of accounting, consumable stores on hand would be recognized as inventory and accounted for based on the applicable accounting framework.

It's important to consult the specific accounting standards and guidelines applicable to your jurisdiction and entity to ensure proper treatment and disclosure of consumable stores on hand.

What is Consumable stores on hand?

Consumable stores on hand is considered non-trading stock. Non-trading stock refers to inventory items that are not directly involved in the business's primary trading activities or intended for resale. These items are typically used internally by the business and are consumed in the normal course of operations.

Consumable stores, such as stationery, office supplies, cleaning materials, or maintenance supplies, fall under the category of non-trading stock. They are not purchased for the purpose of selling to customers but rather for internal use within the business.

Non-trading stock is distinguished from trading stock, which refers to inventory items that are acquired or produced with the intention of being sold to customers. Trading stock is directly related to the core business activities and represents the goods or products held for sale.

By categorising Consumable stores on hand as non-trading stock, businesses can differentiate between inventory items used for internal consumption and those held for resale. This classification helps in tracking and managing different types of inventory effectively, ensuring accurate financial reporting and inventory control.

Is Consumable stores on hand a current asset?

Consumable stores on hand is generally classified as a current asset on the balance sheet. Current assets are assets that are expected to be converted into cash or used up within a year or the operating cycle of the business, whichever is longer.

Consumable stores on hand represents inventory items that are readily available for use within the business. These items are expected to be consumed or used up in the normal course of operations within a relatively short period. Examples of consumable stores include office supplies, cleaning materials, or maintenance supplies.

As a current asset, Consumable stores on hand is reported on the balance sheet under the assets section, typically within the category of inventory or stock. It reflects the value of the inventory items that are not intended for sale but rather used internally by the business.

It's important to note that the specific classification of assets may vary depending on the accounting framework or company's accounting policies. Therefore, it's advisable to refer to the company's financial statements or consult with an accountant for the accurate classification of Consumable stores on hand in a specific context.

Adjustments - Consumable Stores on Hand - how would this be recorded?

At the end of each financial year, the business should conduct a physical count of its consumable stores on hand and adjust its accounts accordingly. This adjustment is necessary to accurately reflect the value of the assets on the balance sheet.

If there are any consumable stores on hand that have not been used or consumed by the end of the financial year, they will be carried forward as assets into the next financial year. Conversely, if any of these items are used up or consumed during the year, they should be recognized as an expense in the income statement.

The journal type

The recording of the consumable stores on hand would typically be done in the general journal. The general journal is used to record transactions and adjustments that don't fit into the specific journals like

sales journal or purchases journal.

In the general journal, you can create a separate entry specifically for the adjustment of consumable stores on hand. This entry would include the appropriate debit and credit accounts to reflect the changes in the asset balance and any associated expenses or gains.

Alternatively, some businesses may choose to create a separate journal called the "*Adjustment journal*" or "*Inventory adjustment journal*" specifically for recording adjustments related to inventory, including consumable stores on hand. This provides a dedicated journal for capturing these adjustments and helps in organizing the accounting records.

The choice of using the general journal or a specific adjustment journal may vary depending on the preferences and accounting practices of the business. Both methods are acceptable as long as the adjustments are properly recorded and documented.

The process

To record the adjustment for Consumable stores on hand, you can follow these steps:

1. Determine the value of consumable stores on hand: Conduct a physical count or inventory valuation of the consumable stores available in your business. This will give you the total value of the inventory items that are used up in the normal course of operations.
2. Create a Consumable Stores on Hand account: In your chart of accounts, set up a new asset account specifically for tracking Consumable stores on hand. You can name it "*Consumable stores on hand*" or something similar. Assign a suitable account number based on your accounting system's numbering convention.
3. Record the adjustment: Make a journal entry to record the adjustment in your accounting system. Debit the Consumable stores on hand account for the value of the consumable stores on hand. This entry recognizes the value of the inventory items that are readily available for use. On the credit side, you can select an applicable expense account that corresponds to the type of consumable items you have, such as Stationery, Office supplies, Cleaning materials, or other appropriate accounts.

Example entry:	*Account classification*	*Debit*	*Credit*	
Debit: Consumable stores on hand	*Current asset*	*$1,000*		*This entry recognizes the value of the inventory items that are readily available for use.*
Credit: Stationery	*Expense*		*$1,000*	*This recognizes the expense not consumed for the consumable stores during the year.*

4. Review and adjust periodically: Regularly review and update the Consumable Stores on Hand account to reflect any changes in the inventory. This may involve recording additional purchases, adjusting for losses or usage, or writing off damaged or expired items. By keeping the account up to date, you ensure that the balance accurately represents the value of consumable inventory on your balance sheet.

Recording the Consumable stores on hand adjustment helps in accurately tracking and managing the internal inventory used in your business. It provides visibility into the value of these consumable items and assists in effective inventory management.

Decrease in the Consumable stores on hand

If the amount of consumable stores on hand has decreased during the year due to usage or consumption, the journal entry would be as follows:

Example entry:	*Account classification*	*Debit*	*Credit*	
Debit: Stationery	*Expense*	*$1,000*		*This recognizes the expense incurred for the consumable stores used during the year.*
Credit: Consumable stores on hand	*Current asset*		*$1,000*	*This reduces the value of the consumable stores on hand, reflecting the decrease in the asset balance.*

By recording this journal entry, you are properly reflecting the decrease in the value of consumable stores on hand and recognizing the associated expense in the income statement. This ensures that the financial statements accurately reflect the usage and impact of consumable items in the business.

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Consumable stores shortages / losses

What happens if items in a consumable assets inventory is, stolen, destroyed by water damage or fire?

If items in a consumable assets inventory are stolen, destroyed by water damage, or fire, it can have

several implications for the business:

1. Loss of inventory value: The stolen or damaged items represent a loss in the value of the consumable assets. The cost of these items would need to be written off or adjusted in the accounting records to reflect the loss.
2. Insurance coverage: Depending on the insurance policies in place, the business may be able to make a claim for the stolen or damaged inventory. The insurance coverage can help mitigate the financial impact of the loss, although the actual reimbursement may not cover the full value of the inventory.
3. Reporting the loss: The loss should be documented and reported appropriately. It is important to maintain proper records and documentation, such as police reports in the case of theft or insurance claim documents. This helps in accurately reflecting the loss in the financial statements and supporting any insurance claims.
4. Adjusting financial statements: The financial statements, particularly the balance sheet, may need to be adjusted to reflect the reduced value of the consumable assets. This is typically done by recognizing a loss or expense in the income statement and reducing the value of the consumable assets on the balance sheet.
5. Internal controls and preventive measures: Incidents like theft, water damage, or fire highlight the importance of having strong internal controls and preventive measures in place. This includes implementing security measures to prevent theft, safeguarding inventory against damage, and having adequate insurance coverage.

It's crucial for businesses to have appropriate risk management strategies, including inventory control, security measures, and insurance coverage, to minimize the impact of such incidents on the financial position and operations of the business. Consulting with an accountant or financial advisor can provide specific guidance tailored to your business's circumstances.

When doing an inventory of consumable stores and a shortage is detected, should the same procedure be applicable?

Yes, if a shortage is detected during an inventory of consumable stores, a similar procedure can be followed to record and address the shortage. Here's how you can handle the situation:

1. Identify the shortage: During the inventory count, if it is discovered that there is a shortage of consumable items compared to the recorded quantities, it indicates that some items are missing or have been used without proper documentation.
2. Investigate the cause: Determine the reason for the shortage by reviewing transaction records, checking for any discrepancies in documentation, or conducting further investigations. This will help

identify if the shortage is due to theft, improper usage, errors in recording, or other factors.

3. Adjust the records: Once the cause of the shortage is determined, adjust the inventory records accordingly. This involves reducing the quantity and value of the consumable items in the accounting records to reflect the actual count.

4. Record the loss: If the shortage is due to theft or damage, it may be necessary to record a loss in the accounting records. This involves recognizing an expense or loss in the income statement to reflect the value of the missing items. The specific account used will depend on your accounting system's chart of accounts.

5. Review internal controls: Assess the internal controls related to inventory management to identify any weaknesses or gaps that may have contributed to the shortage. Strengthening controls, such as implementing stricter inventory tracking procedures, enhancing security measures, or improving documentation processes, can help prevent future shortages.

6. Take corrective actions: Depending on the findings of the investigation, take appropriate actions to address the shortage. This may involve disciplinary measures, improving supervision, revising inventory management procedures, or implementing additional security measures.

By following these steps, you can accurately reflect the shortage in the inventory records, update the financial statements, and take necessary measures to prevent similar issues in the future. Consulting with an accountant or inventory management expert can provide further guidance based on your specific business needs and circumstances.

Created with the Standard Edition of HelpNDoc: Elevate your documentation to new heights with HelpNDoc's built-in SEO

Correction of Errors / Adjustments

What is correction of errors in accounting and how can it help to combat fraud and corruption?

Correction of errors in accounting refers to the process of identifying and rectifying mistakes or inaccuracies in financial records or statements. Errors can occur due to various reasons, such as mathematical errors, data entry mistakes, omissions, or misinterpretations of accounting principles.

The correction of errors plays a crucial role in maintaining the accuracy and integrity of financial information. Here's how it can help combat fraud and corruption:

1. Enhanced transparency: By identifying and rectifying errors, financial statements become more accurate and transparent. This transparency makes it harder for fraudulent activities to go unnoticed. Errors that are left uncorrected can create opportunities for fraudsters to manipulate financial data, misrepresent the financial position, or hide fraudulent transactions. Detecting and correcting errors promptly reduces the chances of such manipulations and enhances the overall transparency of financial reporting.
2. Error detection as an Anti-fraud measure: When errors are investigated and corrected, it can uncover irregularities or discrepancies that may be indicative of fraudulent activities. In some cases, errors may be deliberately introduced as part of fraudulent schemes to divert funds or manipulate financial statements. Correcting errors involves scrutinizing the underlying transactions and identifying any anomalies or signs of fraudulent behaviour, helping to uncover potential fraud.
3. Strengthened Internal controls: The process of error correction often involves reviewing internal controls and implementing necessary improvements. Strengthening internal controls can help prevent and detect fraudulent activities by establishing proper segregation of duties, implementing checks and balances, and ensuring proper oversight of financial processes. Effective internal controls act as deterrents and make it more difficult for fraud and corruption to occur.
4. Reliable Financial information: Correcting errors leads to more accurate financial information, which is essential for decision-making and stakeholder confidence. Reliable financial information helps stakeholders, including investors, creditors, and regulatory bodies, make informed decisions. It reduces the risk of making decisions based on incorrect or manipulated data, thus mitigating the potential for fraud or corruption to go unnoticed.
5. Auditing and Compliance: Correcting errors contributes to the integrity of financial records, making them more reliable for audit purposes. Auditors rely on accurate financial information to perform their examinations and identify any red flags or irregularities. Correcting errors improves the effectiveness of auditing processes, facilitating the detection and prevention of fraud and corruption.

Overall, the correction of errors in accounting ensures the accuracy and reliability of financial information, which in turn helps combat fraud and corruption by increasing transparency, enabling error detection, strengthening internal controls, providing reliable data for decision-making, and facilitating effective auditing and compliance measures.

Could access control in Access control help in elimination errors and fraud and corruption in osFinancials?

Yes, access control plays a crucial role in eliminating errors, fraud, and corruption in osFinancials5/TurboCASH5 or any other accounting system. Access control refers to the process of

restricting and managing user access to the system and its functionalities based on their roles and responsibilities within the organization. Here's how access control can help:

1. Prevention of Unauthorized Access: By implementing access controls, you can ensure that only authorized individuals have access to sensitive financial data and functionalities. Unauthorized access can lead to errors, manipulation of data, or fraudulent activities. Access control helps prevent unauthorized users from accessing critical financial information and reduces the risk of errors and fraudulent actions.

2. Segregation of Duties: Access control enables the segregation of duties, ensuring that no single user has complete control over the entire accounting process. This segregation helps distribute responsibilities, preventing any one individual from having the ability to perpetrate fraud or manipulate financial data without detection. It establishes a system of checks and balances, reducing the risk of errors or fraudulent activities going unnoticed.

3. User Permissions and Restrictions: Access control allows you to assign specific user permissions and restrictions based on roles and responsibilities. This ensures that users only have access to the functionalities and data necessary for their job functions. By limiting access to sensitive areas, such as financial transactions or sensitive reports, you minimize the risk of errors, unauthorized changes, or fraudulent activities in those areas.

4. Audit Trails and Monitoring: Access control systems often include audit trail capabilities that track user activities within the system. These logs capture user actions, such as data modifications or system configurations, providing a record of activities for auditing purposes. By monitoring user actions, you can detect and investigate any suspicious or unauthorized activities, helping to identify errors, fraud, or corruption.

5. Password and Authentication Controls: Access control systems typically include password policies and authentication controls to ensure that users have secure and unique login credentials. This helps prevent unauthorized access to the system by unauthorized individuals. Strong password policies and multi-factor authentication methods enhance system security and reduce the risk of unauthorized access and potential fraudulent activities.

By implementing access control measures in osFinancials5/TurboCASH5 or any accounting system, you establish a framework that helps prevent errors, detect fraud, and reduce the occurrence of corrupt practices. It promotes a secure and controlled environment, safeguarding financial data and mitigating the risks associated with unauthorized access and malicious activities.

Log report

In osFinancials5/TurboCASH5, the log report functionality provides a record of various activities performed within a Set of Books, including the opening and closing of the Set of Books, user logins and logouts, and

important functions like reversing posted journals and documents, as well as year-end processes. Here's how the log report can be useful:

1. Tracking Set of Books activity: The log report allows you to monitor when a Set of Books has been opened or closed. This information helps track the usage and access patterns of the system. It provides an audit trail of when the Set of Books was accessed, which can be valuable for monitoring and ensuring appropriate usage and security.
2. User activity monitoring: The log report also captures user login and logout activities. It records when each user has accessed the Set of Books, allowing you to monitor user activity and identify any unusual or unauthorized access. By reviewing the log report, you can track which users have interacted with the system and when, providing a level of accountability and transparency.
3. Reversal of posted journals and documents: The log report includes information on the reversal of posted journals and reversal of posted documents. This is helpful for tracking the history of corrections or adjustments made to financial transactions. By reviewing the log report, you can identify the specific instances when posted journals or documents were reversed, helping to ensure accuracy and integrity in the financial records.
4. Year-end processes: The log report captures important year-end activities performed in a Set of Books. This includes tasks such as closing the fiscal year, generating financial reports, and performing other year-end procedures. The log report helps document and verify the completion of these critical processes, which are essential for accurate financial reporting and compliance.

Overall, the log report in osFinancials5/TurboCASH5 provides a detailed record of various activities, including Set of Books opening and closing, user logins, reversal of posted transactions, and year-end processes. It serves as an audit trail, helping to monitor system usage, track user activity, and ensure the integrity of financial data. The log report can be a valuable tool for detecting errors, identifying unauthorized access, and promoting transparency and accountability within the accounting system.

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Private expenses

The concept of private expenses

The concept of disallowing private expenses and recovering them applies to all businesses, regardless of whether they use the cash basis or accrual basis accounting method. Properly managing and accounting for private expenses is important for maintaining accurate financial records and ensuring fair treatment of

business expenses.

This adjustment helps in presenting a true picture of the business's financial performance and ensures proper allocation of expenses. It's important to maintain clear documentation and communication regarding the treatment of private expenses in order to comply with accounting standards and regulations. Consulting with an accounting professional can provide further guidance specific to your business and jurisdiction.

What is private expenses?

Private expenses are personal in nature and are not typically allocated or recorded in the financial records of a business.

In accounting, it is essential to separate personal expenses from business expenses to ensure accurate financial reporting. Personal expenses incurred by the owner of the business should be recorded separately as owner's drawings or distributions, depending on the legal structure of the business.

Similarly, it is important for a business or organisation to have policies and procedures in place to prevent employees from including their personal expenses within the business expense accounts. Personal expenses should be handled and recorded separately for the employees, and they should not be reimbursed or treated as business expenses.

Maintaining this separation between personal and business expenses is crucial for several reasons:

1. Accurate financial reporting: Keeping personal and business expenses separate ensures that the financial statements accurately reflect the financial position and performance of the business. It provides a clear picture of the business's income, expenses, assets, and liabilities.
2. Compliance with tax regulations: Mixing personal and business expenses can lead to complications and potential tax issues. By maintaining separate records, it becomes easier to identify and report business-related expenses for tax purposes.
3. Transparency and credibility: Separating personal and business expenses enhances the transparency and credibility of financial statements. It allows stakeholders, such as investors, lenders, and regulators, to assess the financial health and performance of the business accurately.

To maintain this separation, it is important to establish clear policies and procedures, educate employees on proper expense reporting, and conduct regular audits or reviews to ensure compliance. By doing so, businesses can maintain accurate financial records and promote integrity in their financial reporting.

Private expenses and the Business entity principle

The Business Entity Principle is applicable to all businesses, regardless of their size or the accounting

standards they follow. Whether a business is a small business or a large corporation, adhering to the Business Entity Principle is essential for accurate and reliable financial reporting.

The principle is recognized and incorporated in various accounting frameworks, including generally accepted accounting principles (GAAP), International Financial Reporting Standards (IFRS), and IFRS for Small and Medium-sized Entities (IFRS for SMEs). These frameworks provide guidelines and standards for financial reporting, and they emphasize the separation of business transactions from personal transactions.

Regardless of the accounting framework used, businesses are expected to maintain separate financial records and accounts for their business activities, ensuring that personal expenses or transactions of the owners or stakeholders, including that transactions of the employees. are not mixed with the business's financial information. This principle helps in presenting a true and fair view of the business's financial performance and position to stakeholders and facilitates transparency and comparability of financial statements.

Compliance with the Business Entity Principle is important for maintaining the integrity and reliability of financial information and is considered a fundamental aspect of sound financial management and reporting practices.

The Business Entity Principle is a fundamental concept in accounting that applies to all businesses, regardless of their size or the accounting standards they follow. It requires businesses to maintain separate financial records and accounts for their business activities, distinct from the personal transactions of the owners or stakeholders or its employees.

Adhering to the Business Entity Principle is crucial for accurate and reliable financial reporting. By keeping business transactions separate from personal transactions, businesses can present a clear and unbiased view of their financial performance and position. This separation ensures transparency, facilitates proper evaluation of the business's financial health, and allows for meaningful comparisons with other entities.

Whether a business follows specific accounting standards such as GAAP, IFRS, or other recognized frameworks, the principle remains the same. It is a fundamental principle that underlies the entire accounting process and ensures that financial information is reported in a manner that is consistent, objective, and in accordance with established accounting principles and guidelines.

In summary, all businesses, regardless of their size or the accounting standards they follow, should adhere to the Business Entity Principle to maintain accurate and reliable financial records and reporting.

Examples or occurrences of personal expenses

There are several other examples of personal expenses or occurrences that may need to be disallowed by a business. Here are a few common ones:

1. Personal use of company vehicles: If employees use company vehicles for personal purposes, the portion of expenses related to personal use should be disallowed. This can include fuel costs, maintenance, insurance, and other associated expenses.
2. Personal meals or entertainment: If employees charge personal meals or entertainment expenses to the company, the portion that is personal should be disallowed. This may occur when employees mix personal and business expenses on their company credit cards or expense reports.
3. Personal travel expenses: If employees incur travel expenses for personal reasons while on a business trip, such as extending the trip for personal vacation, the personal portion of the expenses should be disallowed.
4. Personal purchases using company accounts: If employees make personal purchases using company accounts or credit cards, the personal portion of those expenses should be disallowed.
5. Personal use of company assets: If employees use company assets, such as equipment, facilities, or supplies, for personal purposes, the corresponding expenses should be disallowed.

It's important for businesses to establish clear policies and guidelines regarding the use of company resources for personal purposes and to communicate these policies to their employees. By disallowing private expenses, the business ensures that its financial records accurately reflect only legitimate business expenses and comply with accounting principles and taxation regulations.

By disallowing private expenses, the business ensures that its financial records accurately reflect only legitimate business expenses and comply with accounting principles and taxation regulations. Consulting with an accounting professional can provide further guidance tailored to your specific business and jurisdiction.

Instances to allocate or disallow private expenses

The recording of private expenses depends on whether it is related to the business owner(s) and partnerships or the employees. Here are the key points:

1. Private Expenses for Business Owner(s) and Partnerships:
    - Private expenses incurred by the business owner(s) or partners are typically allocated to the Drawings or Distribution accounts. When owners or partners incur personal expenses that are paid directly from the business's funds, these expenses should be recorded as drawings or distributions in the respective owner's or partner's capital account. This reflects the reduction of the owner's or partner's equity in the business.
    - The recording of private expenses can occur during the payment processing, where the private expenses are pre-identified and included in the payment. In this case, the private

expenses is directly allocated to the respective Drawings or Distribution accounts.

- If private expenses are discovered or detected after the payment has been made, a separate journal entry may be required to disallow the private expenses from identified Expense account and allocated to the respective Drawings or Distribution accounts.

2. Private Expenses for Employees:
    - Private expenses incurred by employees are allocated to the Employee's Payable/Recoverable account, which is a current asset account.
    - The recording of private expenses for employees may also occur during the payment processing, where the private expenses are already included in the payment. In this case, the private expenses are allocated to the Employee's Payable/Recoverable account.
    - If private expenses are discovered or detected after the payment has been made, a separate journal entry may be required to disallow the private expenses from identified Expense account and allocated to the Employee's Payable/Recoverable account.

It's important to adapt the recording of private expenses based on the specific circumstances and policies of the business, ensuring proper separation of personal and business transactions and following the appropriate accounting principles and guidelines.

Allocate private expenses during the payment of recording and processing private expenses

When processing expense payments, and the private expenses is pre-identified and included in the payment, you may allocate these private expenses directly to the appropriate accounts. A brief summary for allocating private expenses when processing transactions in batches, is as follows:

1. Owners or Partners: When owners or partners incur personal expenses that are paid directly from the business's funds, these expenses should be recorded as drawings or distributions in the respective owner's or partner's capital account. This reflects the reduction of the owner's or partner's equity in the business.
2. Employees: If private expenses are incurred by employees and are pre-identified and included in the payment made to them, it is appropriate to allocate these expenses directly when processing the cash/bank transaction. This can be done by recording the payment with a split allocation, where the portion related to business expenses is allocated to the applicable expense account (which will be reflected in the income statement) and the portion related to private expenses is allocated to the employee's payable or recoverable account (which will be reflected in the balance sheet). The amount allocated to the employee's payable or recoverable account is owed by an employee to the business.

Reimbursement or recovery of private expenses for employees If there are private expenses owed by an employee to the business, the business can include the amount owed as a deduction in the employee's payroll. By deducting the amount from the employee's payroll, it helps to recover the private expenses owed by the employee to the business. This deduction will clear any private expense amounts that were allocated to the Employee's Payable/Recoverable account (a current asset account) when the expense payments were processed. It ensures that the employee reimburses or pays back the business for their personal expenses, maintaining the separation between personal and business transactions.

It's important to have clear policies and procedures in place to document and approve private expenses incurred by employees. This helps ensure that the reimbursement and recovery of private expenses process is accurate and transparent. Additionally, maintaining proper records of these transactions and reimbursements is important for auditing purposes and to ensure compliance with tax regulations.

Private expenses for Business Owner(s) / Partnerships: Recording and processing

The process of allocating and disallowing private expenses for business owners/partnerships, may occur in the following instances:

- The allocation of private expenses to the respective owner's or partner's drawings or distributions account reflects the reduction in their equity.
- On the other hand, if private expenses are mistakenly included in the payment of expenses and later discovered, a journal entry is processed to disallow those expenses from the owner(s) or partners, rectifying the error and ensuring accurate financial reporting.

Allocating Private Expenses for Business Owner(s) / Partnerships

When owners or partners incur personal expenses that are paid directly from the business's funds, these expenses should be recorded as drawings or distributions in the respective owner's or partner's capital account. This reflects the reduction of the owner's or partner's equity in the business.

In osFinancials5/TurboCASH5, the recording and allocation of private expenses to the owner's or partner's drawings or distributions account can be done in different circumstances, depending on the type of transaction. Here are some scenarios:

1. Cash payments: If expenses are paid in cash through the bank account, credit card, or petty cash, you can allocate the expenses directly to the owner's or partner's drawings or distributions account. This

can be done through batch entry or journal entry, or by using the Bank import plugin on the Default ribbon.

2. Purchases on credit: If expenses are procured on credit from creditors or suppliers, you can record the transaction in the purchases journal through batch entry or journal entry. In this case, you can allocate the private portion of the expense to the owner's or partner's drawings or distributions account.

3. Document entry: If you are using the purchases document type with the financial entry stock item type, you can select the owner or partner and allocate the expenses to their respective drawings or distributions account.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Drawings or Distributions accounts	*Equity*	*$100*	
Credit: Cash or bank account	*Current asset*		*$100*
Credit: Purchase journal	*Current liability*		

In cases where the private portion of the expense is included in the transaction, such as a mixed business and private expense, you may need to split the transaction. Allocate the business portion to the applicable expense account and allocate the owner's or partner's portion to their respective drawings or distributions account.

These methods in osFinancials5/TurboCASH5 allow for accurate recording and allocation of private expenses to the owner's or partner's accounts, ensuring proper tracking and reporting of business and personal transactions.

By recording the private expenses separately, you are accurately reflecting the portion of expenses that should not be attributed to the business but rather borne by the owner or partners.

Disallow Private Expenses for Business Owner(s) / Partnerships - Mistakenly included in the payment of expenses and are later discovered

If private expenses are mistakenly included in the payment of expenses and are later discovered, a journal entry should be processed to disallow those private expenses from the owner(s) or partners. This is done to rectify the error and ensure accurate financial reporting.

The journal entry to disallow private expenses would typically involve debiting an appropriate account to

reflect the disallowed expenses and crediting the respective owner's drawing account or the partner's distribution account.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Drawings or Distributions accounts	*Equity*	*$100*	
Credit: Relevant expense accounts	*Expenses*		*$100*

By recording the private expenses separately, you are accurately reflecting the portion of expenses that should not be attributed to the business but rather borne by the owner or partners.

Remember to consult with an accounting professional or refer to applicable accounting standards and regulations for specific guidance on disallowing private expenses and the appropriate accounts to use in your jurisdiction.

Private expenses for Employees: Recording and processing

The process of allocating and disallowing private expenses for employees, may occur in the following instances:

- The allocation of private expenses to the respective Employee's Payable/Recoverable account reflects the amount that is recoverable by the business and is due by the employee(s) as a current asset.
- On the other hand, if private expenses are mistakenly included in the payment of expenses and later discovered, a journal entry is processed to disallow those expenses from the relevant expense account which includes private expenses related to employee(s), rectifying the error and ensuring accurate financial reporting.

It is crucial to inform or notify the employees about the private expenses incurred and the need for reimbursement or recovery. Transparency and clear communication are essential in maintaining a healthy employer-employee relationship and ensuring compliance with financial policies.

By informing employees about the private expenses and the subsequent need for reimbursement or recovery, you establish open and honest communication channels. This allows employees to understand their obligations and responsibilities regarding the private expenses incurred on their behalf.

Clear communication helps avoid misunderstandings and ensures that employees are aware of the financial impact of their private expenses on the business. It also promotes accountability and encourages timely

reimbursement or payment, which helps maintain accurate financial records and prevents prolonged debit balances in the "Employee's Payable/Recoverable" account.

By keeping employees informed and engaged in the process, you promote a culture of financial responsibility and collaboration within the organization.

Allocating Private Expenses for Employees

In osFinancials5/TurboCASH5, the recording and allocation of private expenses to the Employee's Payable/Recoverable account can be done in different circumstances:

1. Cash payments: If expenses are paid in cash through the bank account, credit card, or petty cash, you can allocate the expenses directly to the Employee's Payable/Recoverable account using batch entry, journal entry, or the Bank import plugin.
2. Purchases on credit: If expenses are procured on credit from creditors or suppliers, you can record the transaction in the purchases journal through batch entry or journal entry. Allocate the private portion of the expense to the Employee's Payable/Recoverable account.
3. Document entry: When using the purchases document type with the financial entry stock item type, you can select and allocate the expenses directly to the Employee's Payable/Recoverable account.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Employee's Payable/Recoverable account	*Current asset*	*$100*	
Credit: Cash or bank account	*Current asset*		*$100*
Credit: Purchase journal	*Current liability*		

In cases where the private portion of the expense is included in the transaction, such as a mixed business and private expense, you may need to split the transaction. Allocate the business portion to the applicable expense account and allocate the employees' portion to their Employee's Payable/Recoverable account account.

These methods in osFinancials5/TurboCASH5 allow for accurate recording and allocation of private expenses by debiting the Employee's Payable/Recoverable account as a current asset and crediting the appropriate accounts such as Cash or Bank account or the Purchase journal.

Disallow Private Expenses for Employees - Mistakenly included in the payment of expenses and are later discovered

If private expenses are mistakenly included in the payment of expenses and are later discovered, a journal entry should be processed to disallow those private expenses from the relevant expense accounts. This is done to rectify the error and ensure accurate financial reporting.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Employee's Payable/Recoverable account	*Current asset*	*$100*	
Credit: Relevant expense accounts	*Expenses*		*$100*

The journal entry to disallow private expenses would typically involve debiting an appropriate "*Employee's Payable/Recoverable*" account to reflect the disallowed expenses that needs to be recovered and crediting the respective expense account which includes the private expenses which was incorrectly allocated as an expense.

By recording the private expenses separately, you are accurately reflecting the portion of expenses that should not be attributed to the business but rather borne by the employee(s).

Recovery of private expenses from employee(s)

Once the adjustment for private expenses is disallowed and the "*Employee's Payable/Recoverable*" account reflects a debit balance, it is important to recover the private expenses from the employees. This ensures that the business's financial records are accurate and up to date.

Recovering the private expenses from the employees involves collecting the amount owed by them and recording the transaction in the accounting records. The specific method of recovery can vary depending on the business's processes and policies.

Here are some options to record the recovery of private expenses from employees:

1. Direct payment: The employees can make a direct payment to the business to reimburse the private expenses. This involves the issue of a receipt, etc. and process the receipt transactions in the Cash or Bank account.

Example entry:	*Account classification*	*Debit*	*Credit*

Debit: Cash or Bank account	*Current asset*	*$100*	
Credit: Employee's Payable/Recoverable account	*Current asset*		*$100*

2. Payroll deduction: You can also recover the private expenses from employees via the payroll system. This involves deducting the reimbursement amount from the employee's wages or salary. The payroll system will automatically calculate the deduction and adjust the employee's net pay accordingly.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Payroll Deductions or Payroll Clearing account	*Current liability*	*$100*	
Credit: Employee's Payable/Recoverable account	*Current asset*		*$100*

3. Offset against future payments: If the employee has upcoming payments or reimbursements owed to them by the business, you can offset the private expenses against these future amounts. In this case, you would record the transaction as a deduction to reduce the payments made to the employee when processing the next payments to employees.

Example entry:	*Account classification*	*Debit*	*Credit*
Debit: Expense Reimbursement Payable	*Current liability*	*$100*	
Credit: Employee's Payable/Recoverable account	*Current asset*		*$100*

The "Expense Reimbursement Payable" account is typically classified as a current liability account. This account is used to track the amounts owed by the business to employees or other parties for expense reimbursements.

When employees or individuals incur expenses on behalf of the business and are eligible for reimbursement, the business records the expenses as liabilities in the "Expense Reimbursement Payable" account until the reimbursement is made. Once the reimbursement is processed, the liability is reduced, and the corresponding cash or bank account is debited.

It's worth noting that account classifications can vary between different accounting systems or organizations. It's important to consult the specific chart of accounts or accounting guidelines used by your business to determine the appropriate classification for the "Expense Reimbursement Payable" account.

By recording the transactions for the recovery of private expenses, you are effectively clearing the debit balance in the Employee's Payable/Recoverable account and ensuring that the business's financial records

accurately reflect the reimbursement or recovery of the private expenses.

Notes : Recovering private expenses for employees via the payroll system

Recovering private expenses for employees via the payroll system has several advantages, and one of them is to keep track and accumulate taxable totals for tax certificates, such as the IRP5 in South Africa (or W-2 forms in the United States).

By processing the reimbursement or recovery of private expenses through the payroll system, the amounts can be properly accounted for and included in the employee's taxable income. This allows for accurate reporting of the employee's income and deductions, which is necessary for tax purposes.

Recovering the private expenses through the payroll system ensures that the reimbursement amounts are reflected in the employee's payroll records and reported on their tax certificates. This helps in complying with tax regulations and providing accurate information to employees for their tax filings.

Additionally, using the payroll system allows for automation and integration of the reimbursement process, making it more efficient and reducing the administrative burden of separate cash payments for each employee's private expenses.

Overall, recovering private expenses via the payroll system helps in maintaining accurate tax records and simplifies the process of reporting and accounting for the reimbursement amounts.

Created with the Standard Edition of HelpNDoc: Experience the power of a responsive website for your documentation

---

Common Errors in Accounting

There are several common errors that can occur in accounting, including:

1. Data entry errors: These errors occur when transactions are entered incorrectly, such as transposing numbers or recording the wrong amount.
2. Timing errors: These errors occur when transactions are recorded in the wrong period, such as recording a transaction in the wrong month or year.
3. Omission errors: These errors occur when a transaction is not recorded at all, such as forgetting to record a sale or purchase.
4. Reversal errors: These errors occur when debits and credits are reversed, such as debiting an account

that should be credited.

5. Overstatement or understatement errors: These errors occur when transactions are recorded with the wrong amount, such as overstating revenue or understating expenses.
6. Duplication errors: These errors occur when a transaction is recorded twice, resulting in an overstatement of assets or income.
7. Incorrect account errors: These errors occur when a transaction is recorded in the wrong account, resulting in misstatements in financial statements.

It is important for businesses to have internal controls in place to prevent these common errors from occurring. Regular review and reconciliation of accounts can help identify and correct any errors that do occur. It is also important to have well-trained accounting staff and to use reliable accounting software, such as osFinancials5/TurboCASH5 to minimize the risk of errors.

What is the general journal used for?

The general journal is a book or computer program used in accounting to record all transactions in chronological order. It is also known as the "journal" or "journal entry book".

Each transaction recorded in the general journal includes a date, a brief description of the transaction, the accounts involved, and the amounts debited or credited. These transactions are then later transferred to the appropriate ledgers for posting and summarization.

The general journal is used to record a wide range of transactions, such as sales, purchases, expenses, and other financial transactions. It is also used to record adjusting entries and closing entries at the end of an accounting period.

By recording all transactions in the general journal, a business can keep a complete and accurate record of its financial activities. This information is then used to prepare financial statements and to analyze the financial performance of the business. The general journal is an essential tool for any business that wants to maintain accurate financial records and make informed decisions about its financial activities.

The document types is already linked to the batch types in Setup → Document setup (Setup ribbon). The batch types linked to the documents, is as follows:

Invoices - Sales journal

Credit notes - Sales journal

Purchases - Purchase journal

Supplier returns - Purchase journal

When should a general journal not be used?

A general journal should not be used in certain situations where there are specific journals designed for recording transactions. For example:

- Sales: For recording sales, specialised journals like the sales journal should be used. To record sales transactions in osFinancials5/TurboCASH5, you can use the sales journal available in the Batch entry section of the Default ribbon. The sales journal allows you to enter and manage sales-related transactions effectively.

  In addition to the sales journal, you can process invoices and credit notes using the Documents section on the Default ribbon. Invoices and credit notes can be linked to the sales journal in Setup → Documents setup (Setup ribbon). When you process invoices and credit notes, the source documents will be automatically generated, allowing you to have physical or digital copies of these documents for record-keeping purposes. These documents can be printed and reprinted as needed, enabling you to send them to your debtors (customers/clients) as required.

  Once the invoices and credit notes are updated and posted to the ledger, the corresponding transactions will be automatically processed in the sales journal. Each item included in the invoice or credit note will be recorded in the sales journal, ensuring accurate tracking of your sales transactions.

  By utilising the sales journal and linking invoices and credit notes, you can efficiently manage and maintain a comprehensive record of your sales activities in osFinancials5/TurboCASH5.

- Purchases: For recording purchases, specialised journals like the purchase journal should be used. To record purchase transactions in osFinancials5/TurboCASH5, you can use the purchase journal available in the Batch entry section of the Default ribbon. The purchase journal allows you to enter and manage purchase-related transactions effectively.

  In addition to the purchase journal, you can process purchase and supplier return documents using the Documents section on the Default ribbon. Purchases and supplier return documents can be linked to the purchase journal in Setup → Documents setup (Setup ribbon). When you process purchase and supplier return documents, the source documents will be automatically generated, allowing you to have physical or digital copies of these documents for record-keeping purposes. These documents can be printed and reprinted as needed, enabling you to send them to your creditors (suppliers/vendors) as required.

  Once the purchase and supplier return documents are updated and posted to the ledger, the corresponding transactions will be automatically processed in the purchase journal. Each item included in the purchase and supplier return documents will be recorded in the purchase journal, ensuring accurate tracking of your purchase transactions.

By utilising the purchase journal and linking purchase and supplier return documents, you can efficiently manage and maintain a comprehensive record of your purchase activities in osFinancials5/TurboCASH5.

- Cash transactions: To record cash transactions in osFinancials5/TurboCASH5, specialised journals such as the cash receipts journal and cash disbursements journal are used. In osFinancials5/TurboCASH5, when setting up bank accounts and petty cash accounts in the Setup → Accounts menu of the Setup ribbon, each account will be associated with its own unique payments journal and receipts journal.

  If the Bank import plugin is not activated in osFinancials5/TurboCASH5, you can manually process cash transactions in the respective payments journal and receipts journal associated with the bank account or petty cash account. To access these journals, you can go to the Batch entry option on the Default ribbon.

  If the Bank import plugin is activated, you have the option to process and import transactions directly into the payments journal and receipts journal associated with the bank account or petty cash account. This can be done through the Cash/Bank entry option on the Default ribbon.

  By using the appropriate journals for cash transactions, you can effectively record and manage your cash receipts and disbursements. The journals allow for accurate tracking of cash flows, providing a clear overview of your financial activities.

  Please note that the availability and functionality of specific features may depend on the configuration and settings of your Set of Books in osFinancials5/TurboCASH5.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bank import plugin is included with the osFinancials5/TurboCASH5 Business Class licence, meaning you have access to it without any additional cost or separate licence requirement.

With the plugin, you can download bank statement files from your online banking app or portal provided by your bank or financial institution. These files can be imported into the appropriate bank accounts (cash books) in osFinancials5/TurboCASH5.

You can download statements for multiple bank accounts and credit cards, as long as you have them linked to your online banking. Each bank account or credit card should have its corresponding Payments and Receipts journals set up in osFinancials5/TurboCASH5.

Importing the bank statements automatically populates the transactions into the Payments and Receipts columns, saving you time and reducing the risk of errors associated with manual entry.

The plugin offers a user-friendly interface with context menus that make it easy to locate, select, and search for specific transactions, debtors, creditors, or general ledger accounts. This simplifies the

navigation and management of your bank transactions.

You can link debit transactions to credit transactions and vice versa, allowing for accurate tracking of outstanding balances and efficient management of payments and receipts. You can also link a portion of a payment or receipt to multiple outstanding transactions if needed.

Additionally, the plugin allows you to link accounts to specific debtors, creditors, or general ledger accounts. This ensures that subsequent bank statement imports automatically allocate transactions correctly based on the predefined account linkages, improving accuracy and saving time.

The plugin utilizes bank references to automatically allocate or link various transactions to the correct accounts in your Set of Books. It supports automatic receipts for debit orders from your debtors and automatic payments for managing supplier payments.

In summary, the Bank import plugin in osFinancials5/TurboCASH5 simplifies the import of bank statements, automates transaction allocation, and efficiently manages and reconciles your bank accounts. It reduces manual data entry, improves accuracy, and streamlines your financial management processes.

- Payroll: To record payroll transactions in osFinancials, a specialised journal such as the payroll journal can be used. If you need to add the payroll journal, you can do so in the Setup → Batch types menu on the Setup ribbon.

  By processing payroll transactions in the payroll journal, you can effectively track your salary and wage expenses and payments. This allows you to have a dedicated journal specifically for recording payroll-related transactions, providing specific configuration of the payroll journal and better organisation and analysis of your payroll data.

  In addition to the payroll journal, osFinancials5/TurboCASH5 also provides the option to process repeating transactions. Repeating transactions can be accessed in the Edit → Repeating transactions menu on the Default ribbon. This feature allows you to set up and manage transactions that occur on a regular basis, such as recurring payroll entries. You can edit the repeating transactions as needed and import them into the normal payroll journal, ensuring consistency and efficiency in recording your payroll transactions.

  Using a payroll journal and taking advantage of the repeating transactions feature in osFinancials5/TurboCASH5 can streamline your payroll processing and help maintain accurate records of your payroll expenses and payments.

- Fixed assets: To record fixed asset transactions in osFinancials5/TurboCASH5, a specialized journal such as the fixed asset journal can be used. If the fixed asset journal is not already added, you can do so in the Setup → Batch types menu on the Setup ribbon.

By processing transactions for fixed assets in the fixed asset journal, you can effectively track your fixed asset-related transactions. This includes recording acquisitions, disposals, multi-year depreciation, and any transactions related to losses or profits on the disposal of fixed assets. Having a dedicated journal specifically for fixed asset transactions allows for better organization and analysis of your fixed asset data.

In addition to the fixed asset journal, osFinancials5/TurboCASH5 also provides the option to process repeating transactions. The repeating transactions feature can be accessed in the Edit → Repeating transactions menu on the Default ribbon. This feature is useful for setting up and managing transactions that occur on a regular basis, such as recurring depreciation entries for fixed assets. You can edit the repeating transactions as needed and import them into the normal fixed asset journal, ensuring consistency and efficiency in recording your fixed asset transactions.

Using the fixed asset journal and leveraging the repeating transactions feature in osFinancials5/TurboCASH5 can streamline your fixed asset processing and help maintain accurate records of your fixed asset-related transactions. This allows for better tracking and management of your fixed assets throughout their life-cycle.

It's important to note that the availability and functionality of specific features may vary depending on the configuration and settings of your Set of Books in osFinancials5/TurboCASH5.

Activa plugin - Manual - Shop - Licence : Once-off -

The Activa plugin automates the management and processes of fixed assets and the depreciation of fixed assets in your accounts over the lifespan of the fixed assets. Periodically you will receive a notification screen, which the depreciation shown. From this screen, the depreciation(s) can directly take place.

The Activa plugin in osFinancials5/TurboCASH5 allows you to register fixed assets that need to be written off. The write-off process occurs over the lifespan of the asset and can be spread across multiple financial years.

By adding the Activa Fixed asset accounts in the plugin setup, you will receive reminders when new transactions are posted to the ledger or when Activa transactions require processing. This automation streamlines the management of depreciation allowances for fixed assets (tangible assets) in your Set of Books over the asset's lifespan.

As you record the depreciation expenses for each financial year, they will be reported in the income statement and reduce your net profit. Additionally, the plugin will provide you with the net value of your fixed assets, which is calculated as the fixed assets' cost minus the accumulated depreciation, and this information will be reflected in the balance sheet.

In summary, the Activa plugin helps automate the depreciation management process, ensures accurate reporting of depreciation expenses, and provides visibility into the net value of fixed assets over their lifespan in both the income statement and the balance sheet.

When a fixed asset reached the end of life end process that will clear of the total write-off from the balance write-off account and the initial asset account. This will display only the remaining total on the asset account and the contra account the will be cleared of this total.

By allowing the write-off process to occur over the lifespan of the asset and providing reminders for transaction processing, the plugin further streamlines the management of depreciation allowances for fixed assets.

The accurate reporting of depreciation expenses in the income statement and the reflection of the net value of fixed assets (cost minus accumulated depreciation) in the balance sheet remain essential features of the plugin.

Furthermore, the ability to clear the total write-off from the balance write-off account and the initial asset account when a fixed asset reaches the end of its life adds to the efficiency of the process.

The Activa plugin's powerful grid, custom filtering options, and integrated pivot tables enhance the search and analysis capabilities for active fixed assets, assets requiring processing, and transaction details. The Ledger analyser allows for the printing and exporting of the trial balance, income statement, and balance sheet, while the T-Account viewer facilitates the export of transactions to spreadsheets.

The Central search feature in osFinancials5/TurboCASH5 further aids in searching for transactions related to fixed assets, providing comprehensive functionality for managing and analysing fixed asset data.

- Accrual-based adjustments: To record transactions for accrual-based accounting adjustments, you can add an "*Adjustments*" journal type in the Setup → Batch types menu on the Setup ribbon. By creating an adjustments journal, you can specifically configure the options for recording month-end or year-end adjustments and easily track these adjustments within your Set of Books.

  Using a dedicated adjustments journal allows you to separate these specific transactions from other routine transactions and provides better organization and visibility for accrual-based adjustments. This ensures that these adjustments are properly captured and reflected in your financial statements.

General journal: The general journal, on the other hand, is typically used for recording non-routine or unusual transactions that do not fit into other specialized journals. It is a versatile journal that can be used for various purposes, including corrections of errors. If there is no specific journal available for a particular type of transaction, using the general journal is a suitable option.

However, whenever there is a specialized journal available for a specific type of transaction, it is recommended to use that journal to ensure accuracy and efficiency in record-keeping. This helps maintain consistency and allows for easier analysis and reporting of transactions within their relevant categories.

In general, a general journal is used to record non-routine or unusual transactions that do not fit into the other specialized journals. However, if there is a specific journal available for a particular type of

transaction, it is best to use that journal to ensure accuracy and efficiency in record-keeping.

===

osFinancials5/TurboCASH5 provides a range of default journal types, including sales journal, purchase journal, general journal, payments journals, and receipt journals that are automatically linked to bank accounts or petty cash accounts. Additionally, you have the flexibility to add custom journal types, in the Setup → Batch types menu on the Setup ribbon, to meet your specific requirements.

By using dedicated journals for specific transactions, you can separate these transactions from routine ones, resulting in better organization and visibility. Each journal can be configured with standard and advanced options such as contra accounts, account and tax lookup settings, and more, ensuring accuracy when recording specific transactions and facilitating easy tracking within your Set of Books.

Furthermore, if you have multiple users, you can control their access to process transactions in specific journals. The Setup → *Access control* menu, specifically the Batches access tab, allows you to restrict or grant access to users for processing transactions in specific journals, ensuring proper segregation of duties and maintaining data integrity.

This level of customization and access control in osFinancials5/TurboCASH5 enables you to tailor your journaling process to match your specific business needs, enhance accuracy in recording transactions, and maintain a secure and organized accounting system.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Month-end procedures

Steps for the month-end process

Some general steps for the month-end process in accounting:

1. Review transactions: Review all transactions posted during the month to ensure they are complete and accurate. This includes checking for any missing or incomplete transactions, as well as correcting any errors or discrepancies.
2. Reconcile bank accounts: Reconcile all bank accounts to ensure that the balances in the accounting system match the bank statements. Any discrepancies should be investigated and corrected.
3. Review and adjust journal entries: Review and adjust any journal entries made during the month to ensure they are accurate and complete. This includes making any necessary accruals or adjustments for prepaid expenses or deferred revenue.

4. Prepare financial statements: Prepare financial statements, including the balance sheet, income statement, and statement of cash flows, for the month. These statements should be reviewed for accuracy and completeness.
5. Review accounts receivable and payable: Review the accounts receivable and payable to ensure that all invoices have been paid and all payments have been made.
6. Review inventory: Review the inventory to ensure that all items have been correctly accounted for and that the valuation is accurate.
7. Backup data: Create a backup of all data and store it in a secure location. This is important for disaster recovery and to ensure that data is not lost due to hardware failure or other issues.
8. Close the books: Close the books for the month, which involves finalizing all transactions and updating account balances. This ensures that the accounting records are up-to-date and accurate.

These are just some general steps for the month-end process. The specific steps may vary depending on the organization and its accounting procedures.

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

Year-end procedures

Depending on the accounting basis (cash basis or accrual basis) on which your accounting records or system is based, you may need to do specific adjustments before you do the year-end procedures in osFinancials5/TurboCASH5.

Examples of some of the adjustments based on the accrual accounting basis are; provision for bad debts, prepaid expenses, accrued expenses, provision for accrued expenses, income received in advance, and accrued income. Most of these adjustments are short-term adjustments, where these expenses or income relate to the next successive accounting period or financial year.

However, some adjustments may relate to the long term where the income or expenses are for more than one financial year. A good example is depreciation on fixed assets where the amounts are calculated over the life span of the assets and are apportioned over more than one year.

osFinancials5/TurboCASH5 allows you to close the previous financial year, to prevent any further posting to the previous financial year. To do this, you need to select the Setup → Reporting dates menu (Setup ribbon) option and remove the tick on the "Post to last year" field. You will still be able to generate all the available reports in osFinancials5/TurboCASH5 for that the previous financial year. Should you wish to enter transactions for the "Closed year" or last year (previous financial year), you may remove the tick in this field.

Steps for the year-end process

Some general steps for the year-end process in accounting:

1. Reconcile accounts: Reconcile all accounts, including bank accounts, accounts receivable, accounts payable, and inventory. This involves reviewing all transactions and ensuring that the account balances match the corresponding statements.
2. Adjust entries: Make any necessary adjusting entries to ensure that the accounts reflect the correct balances. This includes accruals, deferrals, and any other necessary adjustments.
3. Perform inventory valuation: Perform a physical inventory count and reconcile the results with the accounting records. This is necessary to determine the actual value of inventory at the end of the year.
4. Review fixed assets: Review the fixed assets to ensure that all items are properly accounted for and that depreciation schedules are accurate.
5. Review accounts receivable and payable: Review the accounts receivable and payable to ensure that all invoices have been paid and all payments have been made.
6. Prepare financial statements: Prepare financial statements, including the balance sheet, income statement, and statement of cash flows, for the year. These statements should be reviewed for accuracy and completeness.
7. Perform a year-end audit: Perform an audit of the financial statements to ensure that they comply with accounting standards and regulations. This is typically performed by an external auditor.
8. Prepare tax returns: Prepare tax returns and ensure compliance with tax regulations. This may involve working with a tax professional to ensure that all deductions and credits are properly accounted for.
9. Close the books: Close the books for the year, which involves finalizing all transactions and updating account balances. This ensures that the accounting records are up-to-date and accurate.

These are just some general steps for the year-end process. The specific steps may vary depending on the organization and its accounting procedures.

Year-End Procedures

After processing all your daily transactions for a specific year, you have to check the results and ensure that certain actions have been performed before the Year-end procedure can be performed.

It is important to develop a checklist to meet your specific requirements. This will ensure that you generate useful reports and that you evaluate your business performance and financial position for a specific period on correct information.

The following represent a basic list and may vary according to your circumstances:

1. All batches (journals) have been updated (posted) to the ledger.
2. All documents, invoices, credit notes and supplier returns) have been updated (posted) to the ledger.
3. Depreciation transactions have been entered and updated (posted) to the ledger.
4. Bad debts have been have written off and updated (posted) to the ledger.
5. Provision for bad debts or doubtful debts have been created or adjusted and updated (posted) to the ledger.
6. Payroll (Salaries and Wages) transactions have been entered and updated (posted) to the ledger.
7. Repeating transactions and Repeating invoices have been updated (posted) to the ledger.
8. Adjustments and Corrections have been entered and updated (posted) to the ledger.
9. Bank Reconciliation is finalised.
10. Interest on overdue debtors accounts have been entered and updated (posted) to the ledger.
11. Generate any Multiple Entries (Fixed amounts to debtor accounts, Debtors with charge amount, and Creditors with charge amount, etc.).
12. Print Reports as necessary, e.g. trial balance, income statements and balance sheets and any other reports. You need to analyse these reports and do the necessary adjustments or corrections, if necessary.
13. Print debtors statements and creditor remittance advises.
14. Create sufficient Backups of your Set of Books.

Adjustments are those transactions that occur, which usually do not involve a third party. These adjustments are usually made at the end of a financial year to adjust certain accounts to reflect the accounting policy of the business entity or to comply with the principles of the Generally Accepted Accounting Principles (GAAP) or International Financial Reporting Standards (IFRS).

Adjustments are made before the closing transactions where the nominal accounts (income and expense accounts) are transferred to the profit and loss account.

These adjustments are normally carried out in the general journal and not in the specific journals (i.e. sales journal, purchase journal, cash receipts journal, cash payments journal, etc.), and the entries are posted to the ledger accounts. Normally the description entered on the journal and / or the applicable working papers are used as the source document.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Do year end

The Log-report in Setup → Access control (Setup ribbon) will list the date and time, as well as which user and on which device, the year-end procedure was performed as OPEN YEAR - Open new year.

When opening a Set of Books, and the financial year expired, a warning confirmation message do the year end, will be displayed.



If you wish to continue, click on the Yes button.

If you do not wish to do the Year end at this stage, and continue to work in the Set of Books in the previous financial year, this confirmation message will be displayed each time the Set of Books is opened.

If you do not wish to receive this message when opening the Set of Books, click on the All button to hide this confirmation message.

When you are ready to Do the year-end, go to the Setup ribbon and select Do year end.

If you click on the Open button on the Set of Books screen, and the start of the financial year (for the Set of Books) is older than the system date, the similar confirmation message will be displayed.

If you click on the Yes button, you may proceed to do the year end.

If you click on the No button, you may go to the Do year end menu on the Setup ribbon.

This option will perform year-end processing for you. It will balance all the income/expense accounts transferring the balance of each account to the retained earnings or retained income account.

This account will then show your net profit or loss for the year. The balances of the balance sheet accounts are brought forward to the New year.

The reporting dates are updated to cater for the New Year. Once the year-end procedure is completed, you will be able to post transactions to your new financial year.

osFinancials5/TurboCASH5 stores the transactions and balances for accounts for up to two financial years (This Year and Last Year). You will still be able to view the transactions and reports for the previous closed financial year.

Before you may perform this year-end procedure to close off all your accounts for a specific financial year you need to:

- *Post any batches (journals) and update any documents to the ledger.*
- *Do any corrections, if any errors are found and do the year-end adjustments.*
- *Print the necessary reports and retain it with the necessary supporting documents for record and audit purposes.*
- *Do a Data integrity check to check that all your data is correct and in balance.*
- *Make a Backup of the Set of Books.*

It is recommended that you Disable your Screen Saver in the Windows Operating System, before starting this process. This will prevent the Screen Saver being activated while the process is running.

To do a year end:

1. On the Setup ribbon, select Do year end. The following information screen is displayed:



2. If you are absolutely sure, tick the "*I have read this instruction and understand the action!*" field. The Yes

and No buttons will be available on this screen.



If you have not made backups, click on the No button and backup your Set of Books.

3. If you click on the Yes button, a confirmation message is displayed:



4. Click on the Yes button, if you are absolutely sure you have made backups.

This is your last chance to cancel this process. If you want to abort the process, click on the Yes button.

5. Click on the No button to start the process.

It is recommended that you do not use your system for other tasks while this process is running.

6. Once the process is finished, the confirmation message is displayed:



7. Click on the OK button. You may continue to work in the new year.

Post to last year

1. It is possible to post transactions in batches (journals) and/or documents (invoices, credit notes, purchases and supplier returns) to the previous financial year. For example, if transactions in a batch includes a date that corresponds to the previous financial year (for instance, if the current financial year spans from 01/03/2022 to 28/02/2023 and the transaction date is 10/03/2021), a confirmation message will appear asking if you want to proceed with posting the batch. The message will state:

   "Do you want to continue posting? Batch contains transactions posting to last year!"

2. Check that the date is correct - Last year's date.

3. Click on the Yes button. osFinancials5/TurboCASH5 will post the transaction to the previous (last) financial year.

If the date(s) of the transactions is incorrect:

1. Click on the No button.

2. Correct the date(s) of the transaction in the batch to this year.

3. Balance the batch once again.

4. Post the batch.

It is also a good idea to restrict posting to the previous financial year. You may do this by selecting Setup → Reporting dates (Setup ribbon) and remove the tick in the "Post to last year" field.

Although you will not be able to post transactions to that financial year, you may still print reports. You may at any time select this field again should you wish to post to the previous financial year.

Do a year end in the future

Should you initiate the year end process (Do year end (Setup ribbon)) and the financial year ends in the future, a similar confirmation message to the following, will be displayed:



If you do not wish to proceed at this stage, click Yes.

Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

Year-end closing transactions

In general, the year-end closing process involves transferring the balances of temporary accounts (such as income and expense accounts) to the retained earnings account, and transferring the balances of permanent accounts (such as assets, liabilities, and equity accounts) to the new accounting period. This process is usually done annually, but the frequency can vary depending on the accounting system and business needs.

Year-end closing transactions

When you do the year-end in the Setup ribbon, osFinancials5/TurboCASH5 automatically closes off all the accounts and transfers all the:

1. General ledger accounts created as an Income / Expense account (Income statement accounts) in the Setup → Accounts to the Retained earnings account at the end or last day of the accounting period for the current financial year (This year). You will still be able to view these figures as comparative figures in the new financial year on the trial balance and income statement.
2. General Ledger Accounts created as a Balance Sheet Account (Assets, Liabilities, Capital) will be closed off and the opening balances will be transferred to the new financial year.

Debtor Accounts in the Debtors Ledger (created in Debtors on the Default ribbon) and Creditor Accounts in the Creditors Ledger (created in Creditors on the Default ribbon) menu option will be closed off and the opening balances will be transferred to the new financial year.

An example of the trial balance after the year-end closing transactions is as follows:

Note

The Income / Expense Account transactions are reflected as nil or zero balances for the new financial year (e.g. 1 March 2007 to 29 February 2008). The previous year (Last Year) figures for each of these accounts will still be available as comparative figures for the (e.g. 1 March 2006 to 28 February 2007).

Note

The Retained Earnings Account is increased in the new financial year with the net profit of the previous year. If it were a net loss (where the Expenses exceed the Income) the net loss would decrease the Retained Earnings Account.

Note

Once your Financial Statements are finalised, you may need to restrict posting to the previous financial year. You may do this by clicking on the Setup → Reporting dates menu Setup ribbon) and remove the tick in the *"Post to last year*" field. Although you will not be able to post transactions to that financial year, you may still generate reports. You may at any time select this field again should you need to post to the previous financial year.

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Reports (Reports ribbon)

The Reports ribbon is used to access all reports from the Reports, User reports, Spreadsheet reports menus. The financial statements such as the Trial balance, Income statement, Balance sheet, Standard column balances, Budget vs actual, This year vs last year as well as Column balances reports in the Ledger analyser 1 / Ledger analyser 2 and T-Accounts can be accessed and printed and even exported and opened in a Spreadsheet. It is also used to process and analyse Budgets access to the Printer setup.



Buttons 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

In addition to the Printer and Budgets options, the reports is grouped into the seven (7) options:

1. Reports - List the reports in the following groups:

    a) Ledger - You may print the Budget vs actual (3 periods) report, List the General ledger accounts (Chart of accounts) and Transaction reports.

    b) Debtors - You may print various debtor statements, age analysis reports, various listing reports, address labels and transaction reports.

    c) Creditors - You may print various creditor remittance advises, age analysis reports, various listing reports, address labels and transaction reports.

    d) Stock - Reorder reports, listing reports, stock movements, backorder reports. You may also print labels (barcodes).

    e) Contacts - Lists the details of all your contacts.

    f) Calendar - Print the appointments (events) (i.e. Appointment, Debtor appointment, Creditor appointment and Hours) that was scheduled in the Calendar / Planner.

    g) Batch entry - Print the transactions of posted invoices, credit notes purchase and supplier return documents as well as posted batch transactions (i.e. sales journal, purchase journal,

payments journals, receipts journals, general journals, etc.).

h) Documents - Lists your documents, such as invoices, credit notes, purchases, supplier returns documents, orders and quotes or a selection of documents or for a selected period.

i) Tax - If you are registered as a Tax (VAT/GST/Sales tax) vendor, you need to print and view reports for a specific period for all your Tax (VAT/GST/Sales tax) or for a specific tax code such as Input Tax (VAT/GST/Sales tax), Output Tax (VAT/GST/Sales tax), Zero-rated Tax (VAT/GST/Sales tax), etc.

j) Sales - Various reports are available to analyse your sales documents. Print Graphs, Debtors, Sales and Items reports for Invoices, Credit notes and Quotes.

k) Sales analysis - You may print reports for five (5) reporting groups (i.e. Debtor group 1, Debtor group 2, Document group 1, Document group 2 and Salespersons) for each sales documents (i.e. quotes, invoices and credit notes). You may also print sales per product for stock group 1 or stock group 2 reports for sales documents.

l) Purchases - Various reports are available to analyse your purchase documents. Print Graphs, Creditors, Purchases and Items reports for Purchase and Supplier return documents as well as Orders.

m) Purchase analysis - You may print reports for five (5) reporting groups (i.e. Creditor group 1, Creditor group 2, Document group 1, Document group 2 and Salespersons) for each purchase documents (i.e. orders, purchases and supplier returns). You may also print purchases per product for stock group 1 or stock group 2 reports for purchase documents.

n) Company info - You may print the details of the bank accounts or the company information, messages and cost of sales settings.

o) Currencies - If you process Multi-currency documents (i.e. Invoices, Credit notes and Quotes for debtors (customers / clients) or Purchases, Supplier returns and Orders for creditors (suppliers / vendors). you may print a list of the "*Currencies*" (added / edited in the Setup → Currencies menu on the Setup ribbon.

p) Plugins - Price agreement report for the Price agreement plugin.

q) Point-of-sale - Sales and Receipt reports for the plugin point-of-sale systems (if you purchased and use the HorecaPOS or RetailPOS point-of-sale systems).

2. User reports - Any other reports that are under construction. Users may add their own reports in the …\plug_ins\reports\userreports folder.

You may use Report designer on the Setup ribbon to create, add or edit document layout files and

reports. You may add your own reports to be accessible from the User reports menu.

- *User reports is stored in the ...\plug_ins\reports\userreports filder.*
- *Document layout files is stored in the ...\plug_ins\reports\DOCUMENTS\DOCUMENTS folder.*

3. Spreadsheet reports - The following reports will be opened in the powerful spreadsheet feature in osFinancials5/TurboCASH5:
   a) Creditors - The Creditors → Listing - List postal addresses report will be imported into the spreadsheet.
   b) Debtors - The Debtors → Listing - List postal addresses report will be imported into the spreadsheet.
   c) Transactions per period - List the transactions in posted batches and documents (i.e. sales documents (Invoices and Credit notes) and Purchase documents (Purchases and Supplier returns)) for a selected period in a spreadsheet.
   d) General ledger - Budget
      i) Column balances this year - Reporting group 1
      ii) Column balances this year - This year
   e) General ledger (Transaction totals)
      i) Column balances this year - Reporting group 1
      ii) Column balances this year - This year Column balances
   f) Sales analysis
      i) Stock movement
      ii) Sales per period
4. Ledger analyser 1 - Trial balance, Income statement, Balance sheet, Standard column balances (column view of the Trial balance, Income statement and Balance sheet in one report), Budget vs actual, This year vs last year as well as Column balances.

Export button for all Report types on Ledger analyser 1 / Ledger analyser 2 -

You may save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

5. Ledger analyser 2 - The same reports are available as for the Ledger analyser 1, but it gives you another option to generate. print or export different views and reports.
6. Age analysis - View and choose options for the Age analysis report on screen and print it on the Reports ribbon and on the Open item link - Due tab (Default ribbon).
7. T-Account viewer - Analyse, print and export transactions for specific accounts, etc. You may also export the transactions in the T-Account viewer to spreadsheets.

Column balances - Report types on Ledger analyser 1 / Ledger analyser 2 - The column balances report types will list the transactions of a selected account for each period of Last year and This year in a spreadsheet format.

You may select an account and double-click on any period. This will launch the T-Account viewer with a list of all the transactions for the selected period. You may be print and/or export the transactions.

The following six (6) column balances report types is available:

1. *Column balances - Lists all ledger account balances in a spreadsheet view. These are the ledger accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*
2. *Column balances debtors - Lists the balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
3. *Column balances creditors - Lists the balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*
4. *Column balances D/C - Lists all debit and credit ledger account balances in a spreadsheet view. These are the accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*

5. *Column balances debtors D/C - Lists the debit and credit account balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*

6. *Column balances creditors D/C - Lists all debit and credit balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*

8. Printer - Setup and configure the printers on your system.

9. Budgets - You may process your budget figures, copy "*Budget figures from the previous year*" or from "*Actual figures from the previous year*". You may view, filter and analyse the budget figures in the Pivot feature.

This is in addition to the standard option to process budgets in Setup → Accounts (Setup ribbon).

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Checking for unposted items

Before printing reports, you should check for unposted batches and documents. The transactions in batches and documents not posted (updated) to the ledger are not included in the reports.

Some examples, where this is important:

- *Before completing your tax returns*
- *Before sending out Debtor statements, Creditor remittance advises,, etc.*

You may also print a trial balance, income statement or balance sheet for unposted transactions in batches in the Ledger analyser - Unposted batches.

To check for unposted items:

1. On the Default ribbon, select Input → Checking unposted items
2. This will list the unposted batches and the number of documents for each document type (i.e. invoices,

credit notes, purchases and supplier returns).

If there are no unposted batches and/or documents, this screen will not be displayed.



You may move your mouse over an area at the bottom of the screen, click and drag this screen to the required size.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Settings for reports - Number format

If the "*Digit separator symbol*" setting e.g. 1 000.00 is not displayed on reports and screens, you need to change the "*Customize Format – Numbers*" format.

This is a global setting for all Sets of Books on your operating system.

You may need to set the number format of your operating system to print some reports.

When printing the "*Budget vs actual*" and "*This year vs last year*" reports, you may encounter the following error message:

"Type conversion error 'Val':Expression TRpExpression46"

The "*Customize Format – Numbers*" of your Windows operating system number format needs to be set as follows:

- Decimal symbol - set to period (.)
- Digit grouping symbol - set to comma (,) (If Digit grouping symbol is set to blank it does not print but produces an error.

This is a global setting for all Sets of Books on your operating system.

To change the number format of your operating system:

1. In any active (opened) Set of Books, select Setup → System parameters (Setup ribbon).

The Region and Language settings of your operating system should launch if you click on the Setup → Company info - Options - Set Windows date format/style button on the Setup ribbon.



2. On the "*System Parameters*" click on the DateTime settings button.



3. On the Formats tab, click on the Additional settings ... button.



4. On the Numbers tab, the default settings (as per new installaion of Windows or on some new devices), the settings that need to be changed is as follows:

   - Decimal symbol set to period (.)
   - Digit grouping symbol set to comma (,)

> *If Digit grouping symbol is set to blank; and when you click on the Print button of the "Budget vs actual" and "This year vs last year" reports; it does not print but produces same error; i.e.*
>
> "Type conversion error 'Val':Expression TrpExpression46"

5. After changing the number formats, the "*Example*" on the Numbers tab of the "*Customize Format*" screen, should display as follows:



6. Click on the Apply and OK buttons of the "*Customize Format*" - Numbers tab, as well as the "*Region*" - Formats screen.

7. You may need to exit (close) osFinancials5/TurboCASH5 for these changes to be updated when generating and printing reports.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Reports - Page headers and Page footers

Report headers

The standard data in the report headers will be displayed on all reports (except on Debtor statements,

Creditor remittance advises, Document layout files en Spreadsheet reports).



The company's contact details and registration numbers, as entered in the Setup → Company info (Setup ribbon).

Report footers

The standard data in the report footers will be displayed on all reports (except on Debtor statements, Creditor remittance advises, Document layout files and Spreadsheet reports).



At the end of each page of a report, the page footer will display the following details:

1. Name for Set of Books - The Company name as entered in Setup → Company info (Setup ribbon).
2. Printed: Your system's date and time when the report was printed.
3. Data - Name of the Set of Books and the full path of the Set of Books (e.g. ."*Data: C:\osFinancials5\books\MY-BOOKS/books.fdb*")
4. System user - The user of your computer's operating system.
5. osFinancials user / TurboCASH user - If users is added in Setup → Access control (Setup ribbon),the user name will be displayed.
6. Page: Page number and the last page number of the report.

The Two pass report setting is necessary to print reports which consists of more than one page.

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Reportman reports - Print options

Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Reportman reports - Send to printer

The report will print the reports directly to the system's default printer.



Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Reportman reports - Save as PDF

If you print any report or document layout file to the screen, you may save the report as a compressed or uncompressed PDF file from the "Reportman print preview" screen.

By default the "*Open in PDF*" option is not selected on the report options (parameter) screens.

If the "*Open in PDF*" option is selected on any report options (parameter) screen, it will print all reports on the Reports menu or User reports menu directly as a PDF file.



The PDF file will automatically be opened in your system's default PDF viewer or app.



Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Chart of accounts

From account: G010000 To: G999000 **Sequence: Account**

Code	Description	Reporting group 1	Reporting group 2	Type	Open item	Disabled
*G010000	Sales	Income	Income2	Inc / Exp	Yes	No
*G100000	Cost of sales	Income	Income2	Inc / Exp	No	No
*G200000	Bank charges	Expenses	Expenses2	Inc / Exp	No	Yes
*G205000	Depreciation	Expenses	Expenses2	Inc / Exp	No	No
*G210000	Motor vehicle expenses	Expenses	Expenses2	Inc / Exp	No	No
*G210010	Fuel and oil	Expenses	Expenses2	Inc / Exp	No	No
*G210020	Maintenance	Expenses	Expenses2	Inc / Exp	No	No
*G210030	Repairs	Expenses	Expenses2	Inc / Exp	No	No
*G215000	Maintenance of tools	Expenses	Expenses2	Inc / Exp	No	No
*G220000	Rent	Expenses	Expenses2	Inc / Exp	No	No
*G225000	Salaries and wages	Expenses	Expenses2	Inc / Exp	No	No
*G230000	Stationery	Expenses	Expenses2	Inc / Exp	No	No
*G235000	Sundry expenses	Expenses	Expenses2	Inc / Exp	No	No
G505000	Capital	Capital	Capital2		No	No
G510000	Retained income	Capital	Capital2		No	No
G520000	Installment agreements	Longterm liabilities	Longterm liabilities2		No	No
G600000	Furniture & fittings - Net value	Fixed assets	Fixed assets2		No	No
G600010	Furniture fittings @ cost	Fixed assets	Fixed assets2		No	No
G600020	Furniture fittings -Acc. deprec.	Fixed assets	Fixed assets2		No	No
G610000	Motor vehicles - Net value	Fixed assets	Fixed assets2		No	No
G610010	Motor vehicles @ cost	Fixed assets	Fixed assets2		No	No
G610020	Motor vehicles -Accum. depreciation	Fixed assets	Fixed assets2		No	No
G700000	Debtors control	Current assets	Current assets2		No	No
G735000	POS - Transfer	Current assets	Current assets2		No	No
G740000	POS - Till	Current assets	Current assets2		No	No
G745000	POS - Payment	Current assets	Current assets2		No	No
G750000	Stock control	Current assets	Current assets2		No	No
B810000	ABC - Bank	Current assets	Current assets2	Bank account	No	No
B820000	Petty cash	Current assets	Current assets2	Bank account	No	No
B830000	XYZ-Bank	Current assets	Current assets2	Bank account	No	No
G860000	VAT - Control - 15%	Current liabilities	Current liabilities2		No	No
T860010	Output VAT - 15%	Current liabilities	Current liabilities2	Tax account	No	No
T860020	Input VAT - Standard rate -15%	Current liabilities	Empty	Tax account	No	No
T860030	Input VAT - Capital goods -15%	Current liabilities	Empty	Tax account	No	No
T860040	Zero-rated VAT - 0%	Current liabilities	Current liabilities2	Tax account	No	No
G860100	VAT - Payment - 15%	Current liabilities	Current liabilities2		No	No
G900000	Creditors control	Current liabilities	Current liabilities2		No	No
G999000	Suspense	Current liabilities	Current liabilities2		Yes	No

The file name will automatically be generates as your system's date / time stamp. In this example, the format of the timestamp is "YYYY/MM/DD/hour/minute/second".

To deactivate this option, remove tick in the "Open in PDF" option on any report options (parameter) screen accessed from the Reports menu or User reports menu.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Reportman reports - Printer setup

By default, the page settings for all document layout files and reports are set to the A4 page layout size.

The Page printer and page settings (page size, margins, etc.) for specific layout files and reports may be set and configured and attached to specific printers.

The printer settings for layout files and reports may be set and configured from the following options:

1. Printer icon on the Reports ribbon or Setup → Printer menu on the Setup ribbon. Printer settings.
2. Reports → Report designer (Print preview button). Page setup and Printer settings.

This is the change where we used to have the ability to setup printers for all reports

Now its loaded from reportman

Need to configure printers in reportman and attach layout to those printers

i.e. printer 1 = document A4 printer and printer 2 = pos printer

Set layout of pos to printer2 and make sure the printer is correctly set in reportman printer setup.

In the screen second tab to set the default printer of a layout file and there is also a button configure printers with is device or user specific.

they can then set there printers accordingly to the pc they logon to - i.e. printer 1 is the same network printer for everyone, but the pos printer is specific to the point its connected to.

http://reportman.sourceforge.net/doc/dotmatrix.html

Printer settings

Page setup

To do a Page setup for reports:

1. If a layout file or a report is sent to screen (in the Report preview screen), click on the Show report print setup icon or press the F11 key.
2. On the "*Dialog*" screen, click on the Page setup button, if not already displayed.



3. You may change the default Settings, if necessary:

    a) Page size -

        § Default is the standard option.

        § Custom radio button - You may select or standard page sizes from a list.

        § User defined radio button - You may set the width and height of the paper size. This is important and may need to be specified for dot-matrix printers.

    b) Page orientation - The Default option is Portrait. You may click on the Custom radio button the set the Custom page orientation to Landscape.

    c) Page margins - You may specify the left and right margins as well as the top and bottom margins.

    d) Lines per inch - The default option is 6 lines per inch.

    e) Background color - The default colour is white. This is optional.

4. Once finished, you may click on the Print setup tab.

Print setup

On this tab, you may set the default printer of a layout file or a report and there is also a button configure printers with is device or user specific. For example, you may then set there printers accordingly to the pc users logon to - i.e. printer 1 is the same network printer for everyone, but the pos printer is specific to the point its connected to.



5. On this tab, you may set the default printer of a layout file or a report and there is also a button to configure printers which is device or user specific. For example, you may then set there printers accordingly to the pc users logon to - i.e. printer 1 is the same network printer for everyone, but the pos printer is specific to the point its connected to.

    a) Printer Fonts (Windows GDI Only) - The Microsoft Windows graphics device interface (GDI) enables reportman to use graphics and formatted text on both the screen and the printer.

    > *Windows-based applications do not access the graphics hardware directly. Instead, GDI interacts with device drivers on behalf of applications. http://msdn.microsoft.com/en-us/library/windows/desktop/dd145203%28v=vs.85%29.aspx*

    b) Report language - Default will use the Operating system's Regional and Language settings.

You may select any of the available languages from the list as the language for reportman.

All reports are already translatable via the Language files in osFinancials5/TurboCASH5 (Switch language (Start ribbon). Languages as customised in Setup → Tools → Customise language).

Languages may also be set in the Setup → Access control - Standard security tab System lang field for each user and the Language field for debtors /creditors.

c) Preview window and scale -

- § Print preview - Select Normal (default) or Maximised.
- § Scale - Select Wide (default), Normal or Page.

d) Select printer - Select one of the following printers; Default, Reporting printer, Reporting printer 2, Ticket printer, Ticket printer 2, Graphics printer, Character based printer, User printer 1 - 9, Plain text printer or Full plain text printer.

e) Paper source (Windows) - You may select Default (default option), First source, Lower source, Middle source, Manual envelope source, Automatic source, Tractor source, Small format source, Large capacity source, Cassette source or Form source.

f) Duplex option (Windows) - Select this option to print on both sides of a page (duplex printing). Note Some printers supports duplex printing; some printers supports automatic duplex printing; and some printers do not support duplex printing at all.

To check whether your printer supports duplex printing, please consult the printer manual, or check the printer's properties (Properties in the Print dialog box).

g) Configure printers button - The Dialog window will open on which you may: -

- § Select one of the following printers; Default printer, Reporting printer, Reporting printer 2, Ticket printer, Ticket printer 2, Graphics printer, Character based printer, User printer 1 - 9, Plain text printer or Full plain text printer.
- § Printer Fonts (Windows GDI Only) - The Microsoft Windows graphics device interface (GDI).
- § Text driver only - You may select a print driver from the list (i.e. "*PLAIN, EPSON, EPSON-MASTER, EPSON-ESCP, EPSON-ESCPQ, IBMPROPRINTER, EPSONTMU210, EPSONTMU210CUT, EPSONTM88II, EPSONTM88IICUT, HP-PCL, VT100*" of "*PLAINFULL*".

Oem (Original Equipment Manufacturers) tick to use the drivers from the hardware manufacturers.

§ Position adjustment - Optional - You may enter a value for the left and top of the page.

§ Operations after print -

- Cut paper -
- Open drawer -

§ Configuration file - Printer configuration file - Report Manager Designer will use a Printer configuration file, only used in printer selection.

Configuration file options - Location:

- *User configuration - e.g. - "C:\Users\danva\AppData\Roaming\reportman.ini"*
- *System configuration - e.g. - "C:\ProgramData\reportman.ini"*

This configuration file will be searched as Documents & Settings\Local Config\All Users\reporman.ini, if not found it will create or use Documents & Settings\Local Config\YourUserName\reporman.ini

h) Copies - By default the number of copies printed, is 1. You may enter the number of copies to be printed.

i) Default printer copies - If this option is selected, the Copies will be disabled. The number of the copies as set in the printer settings (Properties or Preferences) will be used.

j) Collate copies - This will determine how the printed pages of a layout file or report (which contains multiple pages) is sorted when more than one copy of the report or layout file is printed.

For example, if you print multiple copies (three copies) of a report or document layout file that is four pages long, it will print the pages as follows:

- *Collate copies enabled - Prints the first copy of the entire report (pages 1-4); then the second copy of the entire report (pages 1-4); then the last (third) copy of the*

entire report (pages 1-4).

- *Collate copies disabled - Prints all three copies of page 1, then all three copies of page 2, then all three copies of page 3 and, then all three copies of page 4. Note Collate will be inactive if you are printing multiple copies.*

k) Two pass report - This setting allows you to preview the first page before all the pages are calculated (e.g. page 1/2, etc.). This is the default setting implemented in reports and document layout files which supports multi-page and subreports in reports and document layout files. This controls the print speed and memory usage (when printing, pages printed are released from memory).

This two pass report setting must be selected (ticked) for both, "PAGECOUNT" and/or "SkipToPage" settings.

l) Print only if data available - By default this option is not selected (ticked). If no data is available to print, an error message is displayed:

"No data available to print"

When some reports, are printed, and there are no data, it will still print the report without any data. You may then need to re-run the report and select the correct parameters on the report options.

m) Open drawer before / Open drawer after - If a drawer is connected and configured correctly to your system and is also set and configured to the standard Point-of-Sales (Setup → Setup → Point-of-Sales - Peripherals - Drawer tab) or other Plugins (HorecaPOS / RetailPOS), etc., you may select to open the drawer before or after printing the invoice, etc.

n) About box in preview - Not implemented.

o) Printable margins in preview - Not implemented.

6. Click on the Options tab.

Options



Preferred save format - The default option is "*Text stream*".

To be advised.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Reportman output - Send to screen

The "*Reportman preview*" screen is displayed when printing a report to the screen. Reports and Documents are stored in the following directories (folders):

- Reports …*plug_ins**reports**systemreports*
- Documents …*plug_ins**reports/DOCUMENTS/DOCUMENTS*
- User reports …*plug_ins**reports**userreports*



The icons are grouped into five (5) sections (i.e. Navigation, Output, Settings, Zoom and Search) and the Close button. These icons are as follows:

1. Navigation -

    a) First (Home) – Goes to the first page of the report.

    b) Previous (Page up) – Goes to the previous page of the report.

    c) Page number – Displays the page number of the page in the "*Report preview*" screen. You may enter a specific page number and hit the Enter key on your keyboard to jump to that specific page.

    d) Next page (Page down) – Goes to the next page of the report.

    e) Last page (End) – Goes to the last page of the report.

2. Output -

    a) Print (Ctrl+P) – This will launch the "*Print*" screen. You may select another printer (than your system's default printer), select a specific page and change the number of copies, if necessary.

    b) Save (Ctrl+S) – This will launch the "*Save metafile as*" screen. On this screen, you need to do

the following where necessary:

i) Select the directory (folder) where you need to save this file, if necessary.

ii) Enter a file name.

iii) Select a file type if another file type than the default file type (PDF file – Compressed) is required. The following Report meta file types are available:

		File type	File type name
	-	*.rpmf	Report Metafile
		*.pdf	PDF file – Compressed (default)
	-	*.pdf	PDF file – Uncompressed
*	-	*.xls	Excel file
*	-	*.xls	Excel file (one sheet)
	-	*.txt	Text file
	-	*.bmp	Bitmap file
	-	*.html	Html file
	-	*.html	Html file (single)
	-	*.svg	Scalable Vector Graphics file
	-	*.csv	Comma Separated Value file
	-	*.txt	Custom Text file
	-	*.rpmf	Executable Meta file uncompressed
	-	*.exe	Executable meta file

* Microsoft Excel or an alternative program such as; LibreOffice, OpenOffice or UltraOffice, etc. installed to save reports (Save report as a meta file report from the Reportman Print preview screen) to an Excel spreadsheet or Excel (one sheet) spreadsheet.

c) E-mail (Ctrl+E) – This will generate a Portable Document Format (pdf) file. It will also launch a blank E-mail message (using your system's default e-mail program) and insert the report (or document) as an attachment.

> *The name of the report (or document) is automatically generated (for example, REPC526.pdf). It will also automatically be inserted in the "Subject" field and displayed in the title bar of the e-mail message.*
>
> *It is recommended that you add your own sensible subject to this in the "Subject" field. You still need to select a recipient (and other recipients, if necessary) and type a message before clicking on the Send button.*

3. Settings -

i) Show report page setup (F11) – This will display a "*Dialog*" screen on which you may do the Page setup, Print setup and Options (i.e. select the "*Preferred save format*").

ii) Show report parameters (F12)- This is the selection or options screen, on which you may select the options to include or exclude data in the report.

> *Should the report have no report parameters (when it prints directly when you click on the Print button of the Reportman screen), the report has no options to change. This icon will then be inactive.*
>
> *If the report has an active Report parameters icon, you may click on it to change the report parameters. This will change the content of the report.*

4. Zoom -

i) Shows the report in real size (F6) – This will display the report in the actual size when it is printed.

ii) Adjusting the paper to fit the window width (F7) – The report will be stretched to fit the entire Preview window. If you resize the report (e.g. click on the Maximize button or on the Restore down button of the "*Reportman preview*" screen's titlebar), it will automatically be resized.

iii) Scale to full page (F8) – This will display the full page (length and with) in the window.

iv) Zooms out the view (- numeric keypad) – Each click will reduce the size.

v) Zooms in the view (+numeric keypad) – Each click will increase the size.

5. Search (Ctrl+F3) -

Enter text, numbers, amounts, special characters, etc. to find the matching results in the report.

> *To close the Reportman preview screen, click on the Close button. Alternatively, click on the Close button of the "Reportman preview" screen's title bar.*

Created with the Standard Edition of HelpNDoc: Make Your PDFs More Secure with Encryption and Password Protection

Reportman output - Print

Print (Ctrl+P) – This will launch the "*Print*" screen. You may select another printer (than your system's default printer), select a specific page and change the number of copies, if necessary.

In this example, the "*Microsoft Print to PDF*" is the default printer.



Save the print output file.



Open the printed pdf file in your system's default PDF App.



Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Income statement Period 2021/03/01 / 2022/02/28

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT		**17,905.00**		
Income		**21,000.00**		
010000 Sales				36,000.00
100000 Cost of sales			15,000.00	
Expenses	**3,095.00**			
200000 Bank charges			45.00	
205000 Depreciation			150.00	
210000 Motor vehicle expenses	**2,160.00**			
210010 Fuel and oil			150.00	
210020 Maintenance			810.00	
210030 Repairs			1,200.00	
220000 Rent			500.00	
230000 Stationery			240.00	
		Totals	**18,095.00**	**36,000.00**
		Net profit		**17,905.00**

Handyman Hardware Store *Printed : 2022/05/21 08:57:36*
Data: C:\osfinancials5\Books\2022-HELP-DEMO\books.fdb
System user: danva osFinancials user: *Page: 1 / 1*

If the printed file does not open automatically; or if you need to open it at a later stage; you may open the file in your system's file explorer.



Created with the Standard Edition of HelpNDoc: Don't Let Unauthorized Users View Your PDFs: Learn How to Set Passwords

Reportman output - E-mail

This will generate a Portable Document Format (pdf) file. It will also launch a blank E-mail message (using your system's default e-mail program) and insert the report (or document) as an attachment.

The name of the report (or document) is automatically generated (for example, REPC526.pdf). It will also automatically be inserted in the "Subject" field and displayed in the title bar of the e-mail message.

It is recommended that you add your own sensible subject to this in the "Subject" field. You still need to select a recipient (and other recipients, if necessary) and type a message before clicking on the Send button.

To use the E-mail option, you need to have a correctly configured e-mail account on your system. You may also need to configure the following in your Set of Books:

- Setup → Company info (Setup ribbon) - Add the e-mail address for the Set of Books.
- Setup → Internet (Setup ribbon) - Configure your Internet, e-mail accounts to send reports, lists and documents via the internet or to configure a network server.
- Debtors (Default ribbon) - Correct e-mail addresses added for your debtor (customer / client)

accounts.

- Creditors (Default ribbon) - Correct e-mail addresses added for your creditor (supplier / vendor) accounts.

The following message will be displayed if you don't have a default E-mail App installed and associated on your operating system:

"Email
There is no email program associated to perform the requested action. Please install an email program or, if one is already installed, create an association in the Default Programs control panel."

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Reportman output - Save metafile as PDF

"*PDF*" is the acronym for "*Portable Document Format*". The "*PDF*" file format is generally used to save files that cannot be modified. The "PDF files can be saved as a hardcopy of reports and document layout files can be saved as a hardcopy for audit and record purposes.

PDF files can be easily shared across all devices (e.g. desktops, laptops, mobile devices (tablets, cellular phones, etc.). It is also compatible and readable with the default pdf app or pdf reader app on all operating system platforms (e.g. Windows, Linux, Mac, Android, etc.).

You may also open saved PDF files on your system, in the your system's associated default Web browser , e.g. Google Chrome, Firefox, Microsoft Edge, etc.

PDF files may easily be sent via e-mail, read, printed on demand according to your own requirements; or the recipient's requirements.

What apps or tools can be used to open pdf files?

A list of tools and apps that can be used to open PDF files, along with their cross-compatibility across different operating systems:

1. Desktop Applications
    - Adobe Acrobat Reader: Widely used and available for Windows, macOS, and Linux.
    - Foxit Reader: A fast and lightweight PDF reader available for Windows, macOS, and Linux.
    - Nitro PDF Reader: Available for Windows, it offers features like PDF creation, editing, and

conversion.

- Sumatra PDF: A free, open-source PDF reader for Windows.
- PDF-XChange Editor: Available for Windows, it offers advanced editing and annotation features.

2. Web Browsers
   - Google Chrome: Can natively open and view PDF files. Available for Windows, macOS, Linux, Android, and iOS.
   - Mozilla Firefox: Can natively open and view PDF files. Available for Windows, macOS, Linux, Android, and iOS.
   - Microsoft Edge: Can natively open and view PDF files. Available for Windows, macOS, Android, and iOS.
   - Safari: Can natively open and view PDF files. Available for macOS and iOS.
3. Online Tools
   - Google Drive: Can open and view PDF files. Accessible via any modern web browser.
   - Dropbox: Can open and view PDF files. Accessible via any modern web browser.
   - Smallpdf: An online PDF tool that allows you to view, edit, and convert PDF files. Accessible via any modern web browser.
   - PDFescape: An online PDF editor and viewer. Accessible via any modern web browser.
4. Mobile Apps
   - Adobe Acrobat Reader: Available for iOS and Android.
   - Google Drive: Available for iOS and Android.
   - Dropbox: Available for iOS and Android.
   - Microsoft OneDrive: Available for iOS and Android.
   - WPS Office: Available for iOS and Android, it includes a PDF reader and editor.
5. Command Line Tools
   - Poppler: A suite of free software tools for PDF manipulation, available for Windows, macOS, and Linux.
   - PDFtk: A command-line tool for working with PDF files, available for Windows, macOS, and Linux.

6. Text Editors
    - Visual Studio Code: With the right extensions, you can view PDF files in VS Code. Available for Windows, macOS, and Linux.
    - Sublime Text: Similar to VS Code, you can install extensions to view PDF files. Available for Windows, macOS, and Linux.
7. Other Tools
    - PDF.js: An open-source JavaScript library for rendering PDF files in web browsers. Accessible via any modern web browser.

This list should help you find the right tool for viewing and editing PDF files regardless of your operating system.

Save metafile options

To save reports or document layout files as a PDF file:

1. On the "*Reportman print preview*" screen, select Save (Ctrl+S) - This will launch the "*Save metafile as*" screen.



2. Select the directory (folder) where you need to save this file, if necessary.

3. Enter a file name.
4. Select the "*PDF File - compressed (*.pdf)*" (default option) or the "*PDF File – uncompressed (*.pdf)*" file type.
5. Click Save.

You may select the compressed or uncompressed PDF file types

"PDF File – compressed" (default) - The file size and quality may be reduced (smaller) for sending these files via e-mail, etc.

"PDF File – uncompressed"

In osFinancials5/TurboCASH5, the average file pdf file size and quality for reports and document layout files, saved to the PDF compressed or PDF uncompressed, is hardly noticeable.

The default print (Print (Ctrl+P) option where the "Print" screen is set to "Microsoft Print to PDF" option is much smaller in size (263K) than the "PDF File – compressed" size (51K) or "PDF File – uncompressed" size (59K) PDF file types "Save metafile as" option.

The PDF file format may be selected for all reports and document layout files to external recipients.

Income statement - PDF

If the saved file does not open automatically; or if you need to open it at a later stage; you may open the file in your system's file explorer.



An example of the "*Income statement*" saved as a PDF file, opened in "*Microsoft Edge*", is as follows:



income-statement.pdf | income-statement-meta-file.pdf

File | F:/print-reports/income-statement-meta-fi...

1 of 1

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Income statement Period 2021/03/01 / 2022/02/28

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT		**17,905.00**		
Income		**21,000.00**		
010000 Sales				36,000.00
100000 Cost of sales			15,000.00	
Expenses	**3,095.00**			
200000 Bank charges			45.00	
205000 Depreciation			150.00	
210000 Motor vehicle expenses	**2,160.00**			
210010 Fuel and oil			150.00	
210020 Maintenance			810.00	
210030 Repairs			1,200.00	
220000 Rent			500.00	
230000 Stationery			240.00	
		Totals	**18,095.00**	**36,000.00**
		Net profit		**17,905.00**

The PDF file format may be selected for all reports and document layout files to external recipients

Irrespective of the operating systems and apps your debtors (customers / clients) are running, Invoices, Credit notes, Quotes and Statements may be easily shared and sent to these recipients.

Irrespective of the operating systems and apps your creditors (suppliers / vendors) are running, Purchase, Supplier returns, Orders and Remittance advises may be easily shared and sent to these recipients.

Document layout file - PDF

An example of an "*Invoice*" saved as a PDF file, opened in "*Microsoft Edge*", is as follows:



Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

Reportman output - Save metafile as text file

Text files is a flat file, which contains text and has no special formatting such as bold text, *italic text*, images, etc. The text files is saved with the *. txt file extension. It is usually opened with Notepad, or any other text file editor set as default and associated with your operating system.

What apps or tools can be used to open text files?

Text files, which typically use extensions like `.txt`, `.log`, `.csv`, and others, can be opened using a wide

range of applications and tools. Here are some popular options along with their operating system compatibility:

1. Text Editors
    - Notepad: Pre-installed on Windows.
    - Notepad++: Windows.
    - Sublime Text: Windows, macOS, Linux.
    - Visual Studio Code: Windows, macOS, Linux.
    - Atom: Windows, macOS, Linux.
    - Vim: Windows, macOS, Linux.
    - Emacs: Windows, macOS, Linux.
    - TextEdit: Pre-installed on macOS.
    - Gedit: Pre-installed on many Linux distributions.
2. Office Suites
    - Microsoft Word: Windows, macOS.
    - LibreOffice Writer: Windows, macOS, Linux.
    - Google Docs: Cross-platform (accessible via any modern web browser).
    - WPS Office: Windows, macOS, Linux, Android, iOS.
3. Integrated Development Environments (IDEs)
    - Eclipse: Windows, macOS, Linux.
    - IntelliJ IDEA: Windows, macOS, Linux.
    - PyCharm: Windows, macOS, Linux.
    - Visual Studio: Windows, macOS.
4. Command Line Tools
    - cat: Available on Unix-based systems (Linux, macOS).
    - less: Available on Unix-based systems (Linux, macOS).
    - more: Available on Unix-based systems (Linux, macOS).
    - type: Available on Windows.

- more: Available on Windows.

5. Online Tools
    - Google Docs: Cross-platform (accessible via any modern web browser).
    - Microsoft OneDrive: Cross-platform (accessible via any modern web browser).
    - Dropbox Paper: Cross-platform (accessible via any modern web browser).
    - Notepad Online: Cross-platform (accessible via any modern web browser).
6. Mobile Apps
    - Google Docs: iOS, Android.
    - Microsoft OneDrive: iOS, Android.
    - Dropbox: iOS, Android.
    - WPS Office: iOS, Android.
    - Notepad+: Android.
    - Text Editor: iOS.
7. Other Tools
    - Adobe Acrobat Reader: Can open text files as well as PDF files. Available for Windows, macOS, Android, iOS.
    - Foxit Reader: Can open text files as well as PDF files. Available for Windows, macOS, Linux.

These tools should cover most of your needs for viewing and editing text files across different operating systems.

Save metafile options

To save reports or document layout files as a text file:

1. On the "*Reportman print preview*" screen, select Save (Ctrl+S) – This will launch the "*Save metafile as*" screen.
2. Select the directory (folder) where you need to save this file, if necessary.
3. Enter a file name.
4. Select "*Text file (*.txt)*" file type.

5. Click Save.

Income statement - Text file

If the saved file does not open automatically; or if you need to open it at a later stage; you may open the file in your system's file explorer.

This should automatically open the saved text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc).

An example of the "*Income statement*" saved as a text file, is as follows:



Income-statement.txt - Notepad

File Edit View

```
Handyman Hardware Store
27 Olifants Road                    Company reg. 336012345
Emmarentia                          Tax reg. no.:446010111
Johannesburg
2195

Phone:      (011) 310-1390      E-mail:      osfinancials1@gmail.com
Fax:        (011) 310-2000      Website:     osfinancials.org/en/

Income statement Period  2021/03/01 / 2022/02/28


                                  DebTotalsCredit    Debit    Credit


REPORTING GROUP ROOT                    17,905.00
  Income                                21,000.00

  010000 Sales                                                36,000.00
  100000 Cost of sales                                15,000.00


  Expenses                      3,095.00

  200000 Bank charges                                     45.00
  205000 Depreciation                                    150.00
  210000 Motor vehicle expenses 2,160.00
  210010 Fuel and oil                                    150.00

  210020 Maintenance                                     810.00
  210030 Repairs                                       1,200.00
  220000 Rent                                            500.00
  230000 Stationery                                      240.00

                                       Totals    18,095.00  36,000.00
                                  Net profit                17,905.00




Handyman Hardware Store                     Printed : 2022/05/21 16:35:05
 Data: C:\osfinancials5\Books\2022-HELP-DEMO\books.fdb
 System user: danva  osFinancials user:              Page: 1  /  1
```

Ln 54, Col 1 | 70% | Unix (LF) | UTF-8

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Reportman output - Save metafile as html

HTML (Hypertext Markup Language) files can be easily shared across all devices (e.g. desktops, laptops, mobile devices (tablets, cellular phones, etc.). It is also compatible and readable in the your system's associated default Web browser , e.g. Google Chrome, Firefox, Microsoft Edge, etc.

What apps or tools can be used to open html files?

HTML (HyperText Markup Language) files can be opened and viewed using a variety of applications and tools. Here are some popular options:

1. Web Browsers
    - Google Chrome: Available for Windows, macOS, Linux, Android, and iOS.
    - Mozilla Firefox: Available for Windows, macOS, Linux, Android, and iOS.
    - Microsoft Edge: Available for Windows, macOS, Android, and iOS.
    - Safari: Available for macOS and iOS.
    - Opera: Available for Windows, macOS, Linux, Android, and iOS.
2. Text Editors
    - Notepad: Pre-installed on Windows.
    - Notepad++: Available for Windows.
    - Sublime Text: Available for Windows, macOS, and Linux.
    - Visual Studio Code: Available for Windows, macOS, and Linux.
    - Atom: Available for Windows, macOS, and Linux.
    - Vim: Available for Windows, macOS, and Linux.
    - Emacs: Available for Windows, macOS, and Linux.
    - TextEdit: Pre-installed on macOS.
    - Gedit: Pre-installed on many Linux distributions.
3. Integrated Development Environments (IDEs)
    - Eclipse: Available for Windows, macOS, and Linux.
    - IntelliJ IDEA: Available for Windows, macOS, and Linux.

- PyCharm: Available for Windows, macOS, and Linux.
- Visual Studio: Available for Windows and macOS.

4. Online Tools
    - JSFiddle: An online code editor that allows you to write and test HTML, CSS, and JavaScript. Accessible via any modern web browser.
    - CodePen: An online code editor that allows you to write and test HTML, CSS, and JavaScript. Accessible via any modern web browser.
    - JSBin: An online code editor that allows you to write and test HTML, CSS, and JavaScript. Accessible via any modern web browser.
5. Mobile Apps
    - Dcoder: Available for Android, it allows you to write and run HTML, CSS, and JavaScript code.
    - Web Editor: Available for iOS, it allows you to write and view HTML files.
6. Command Line Tools
    - cat: Available on Unix-based systems (Linux, macOS).
    - less: Available on Unix-based systems (Linux, macOS).
    - more: Available on Unix-based systems (Linux, macOS).
    - type: Available on Windows.
    - more: Available on Windows.
7. Other Tools
    - Adobe Dreamweaver: Available for Windows and macOS, it is a professional web development tool that supports HTML.
    - Brackets: Available for Windows, macOS, and Linux, it is an open-source text editor for web development.

These tools should cover most of your needs for viewing and editing HTML files across different operating systems.

Save metafile options

To save reports or document layout files as a html file:

1. On the "*Reportman print preview*" screen, select Save (Ctrl+S) – This will launch the "*Save metafile as*" screen.
2. Select the directory (folder) where you need to save this file, if necessary.
3. Enter a file name.
4. Select "*Html file (single) (*.html)*" file type. This option is recommended for html output, as it does not save or export numbering bullets (numbering). as is the case with the "*Html file*" option.
5. Click Save.

Html file (single)

An example of the "*Trial balance*" (consisting of 2 pages) saved as a "*Html file (single)*" file type, is as follows:

Page 1 -



Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Trial balance Period 2021/03/01 / 2022/02/28

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT				
Income				
010000 Sales				36,000.00
100000 Cost of sales			15,000.00	
Expenses				
200000 Bank charges			45.00	
205000 Depreciation			150.00	
210000 Motor vehicle expenses	2,160.00			
210010 Fuel and oil			150.00	
210020 Maintenance			810.00	
210030 Repairs			1,200.00	
220000 Rent			500.00	
230000 Stationery			240.00	
Capital				
505000 Capital				5,000.00
Current liabilities				
860000 VAT - Control - 15%		4,119.00		
860010 Output VAT - 15%				5,400.00
860020 Input VAT - Standard rate -15%			1,161.00	
860030 Input VAT - Capital goods -15%			120.00	
900000 Creditors control		5,000.00		
Creditor group 1C				
2ABCOS ABC-Office-Supplies				2,700.00
2ABCSC ABC-Service-Centre				2,300.00
Fixed assets				
600000 Furniture & fittings - Net value	3,750.00			
600010 Furniture fittings @ cost			3,800.00	

Handyman Hardware Store *Printed : 2022/05/21 22:03:17*
Data: C:\osfinancials5\Books\2022-HELP-DEMO\books.fdb
System user: danva osFinancials user: *Page: 1 /2*

Page 2 - (included in the single file - Scroll down to view page 2)



Html file

An example of the "*Trial balance*" (consisting of 2 pages) saved as a "*Html file*" file type.

If a report with multiple pages is saved as an Html file format, it will save the file in separate pages (and opened in separate tabs in your web browser). For example, a Trial balance consisting of 2 pages, will be printed as follows:

html - Output folder

In this example, 186 items is saved.

- name of report and "0" added for page 1.
- name of report and "1" added for page 2.
- It will also export numbering bullets (numbering) as objects for each page. The vertical lines, separating the columns, in the "*detail*" report used to print the Trial balance, Income statement, Balance sheet, etc. is exported as bullets (numbering) objects.



Trail-balance0.html is the first page of the saved html file.

If the trial balance consists of more than one page name of report will increment to page "1" for page 2.

It will also export numbering bullets (numbering) as objects for each page.

Trail-balance0.html (first page)



detail | detail

File | F:/print-reports/html/trail-balance0.html

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Trial balance Period 2021/03/01 / 2022/02/28

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT				
Income				
010000 Sales				36,000.00
100000 Cost of sales			15,000.00	
Expenses				
200000 Bank charges			45.00	
205000 Depreciation			150.00	
210000 Motor vehicle expenses	2,160.00			
210010 Fuel and oil			150.00	
210020 Maintenance			810.00	
210030 Repairs			1,200.00	
220000 Rent			500.00	
230000 Stationery			240.00	
Capital				
505000 Capital				5,000.00
Current liabilities				
860000 VAT - Control - 15%		4,119.00		
860010 Output VAT - 15%				5,400.00
860020 Input VAT - Standard rate -15%			1,161.00	
860030 Input VAT - Capital goods -15%			120.00	
900000 Creditors control		5,000.00		
Creditor group 1C				
2ABCOS ABC-Office-Supplies				2,700.00
2ABCSC ABC-Service-Centre				2,300.00
Fixed assets				
600000 Furniture & fittings - Net value	3,750.00			
600010 Furniture fittings @ cost			3,800.00	

Handyman Hardware Store *Printed : 2022/05/21 22:03:17*
Data: C:\osfinancials5\Books\2022-HELP-DEMO\books.fdb
System user: danva osFinancials user: *Page: 1 /2*

Trail-balance1.html (second page)



Trial balance Period 2021/03/01 / 2022/02/28

	Totals Debit	Credit	Debit	Credit
600020 Furniture fittings -Acc. deprec.				50.00
610000 Motor vehicles - Net value		100.00		
610020 Motor vehicles -Accum. depreciation				100.00
Current assets				
700000 Debtors control	38,400.00			
Debtor group 1B				
1MDAVI Mr. Mike Davies			13,225.00	
1ROGSM Mr. Roger Smith			14,950.00	
Debtor group 1C				
1ABGRE Mr. AB Green			7,775.00	
1MACDS MAC Shop Decor Specialists			2,450.00	
750000 Stock control				13,000.00
810000 ABC - Bank			2,930.00	
820000 Petty cash			44.00	
		Totals	**64,550.00**	**64,550.00**
		Net profit	**18,095.00**	**36,000.00**
				17,905.00

Handyman Hardware Store *Printed : 2022/05/21 22:03:17*
Data: C:\osfinancials5\Books\2022-HELP-DEMO\books.fdb
System user: danva osFinancials user: *Page: 2 /2*

Document layout files saved as the Html file type

Before fixes



If a layout file is saved as:

- *Html file type - it will add a zero after the file name for the first page , e.g. invoice-IN0000220.html (0 added after the file name for page 1)*
- *Html (single) file type - no page numbers will be inserted after the file name.*

These issues in the HTML file type for layout files is not applicable to other file types.

Overlapping labels and expressions:

The "Delivery address" labels overlaps.

Should you need to use this html format, explore by selecting other layout file formats.

To fix this:

1. *Go to the Report designer (on the Reports ribbon; or on the Setup ribbon) and select the Document layout file. Copy and rename the layout file.*
2. *Stretch the Expressions until they fit and save the layout file.*
3. *Select the layout file and it should display as per your changes when you save the layout file in the HTML file type.*

After Fixes



These issues in the HTML file type for layout files is not applicable to other file types.

Including / excluding Rectangular objects on html output:

Shapes - The If a file is saved to html file type:

- *Rounded rectangle 'Round Rect' 'TrpShape' and 'Round Square' Expressions will not be included in the saved html file types.*
- *Rectangle 'Rectangle' 'TrpShape' Expressions shape will be included in the saved html file types.*

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Reportman output - Save metafile as Excel file

Bug - Excel file to save reports (Save report as a meta file report from the Reportman Print preview screen) or export data from the Ledger analyser, and various options to export data to an Excel spreadsheet or Excel (one sheet) spreadsheet (.xls).*

Error - Unable to set the HorizontalAlignment property of the Range class

This error is replicated in the following file formats:

Excel file (.xls)*

Excel file (one sheet) (.xls)*

"Excel file (one sheet)" - For example, a Trial balance consisting of 2 or more pages, will be opened in one sheet.

"Excel file" For example, a Trial balance consisting of 2 or more pages, will be opened in separate sheets for each page (e.g. Sheet1, Sheet2, etc.).

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Reportman output - Save metafile as csv

All reports may be saved or exported to the "*CSV*" (Comma Separated Values) file format. These data in the report is basically a text file that stores the data records in each line. The records in each line is structured in a tabular format and the fields are separated by commas, tabs, etc.

The csv files can be opened into basically any spreadsheet application in Microsoft Excel or alternative spreadsheet components of LibreOffice, OpenOffice, Ultra Office, Google Sheets, etc.

Save metafile options

To save reports or document layout files as a comma separated values file:

1. On the "*Reportman print preview*" screen, select Save (Ctrl+S) - This will launch the "*Save metafile as*" screen.
2. Select the directory (folder) where you need to save this file, if necessary.
3. Enter a file name.
4. Select the "*Comma separated values (*.csv)*" file type.
5. Click Save.

Income statement - CSV file - Microsoft Excel

An example, of the "*Income statement*" saved as a comma separated values file, and opened in "*Microsoft Excel*" is as follows:



	A	B	C	D	E	F	G	H	I	J	K	L	M	N
1		Handyman Hardware Store												
2		27 Olifants Road							Company reg. no.:			336012345		
3		Emmarentia							Tax reg. no.:			446010111		
4		Johannesburg												
5		2195												
6		Phone:		(011) 310-1390				E-mail:				osfinancials1@gmail.com		
7		Fax:		(011) 310-2000				Website:				osfinancials.org/en/		
8	Income statement Period 2021/03/01 / 2022/02/28													
9										Totals				
10							Debit				Credit		Debit	Credit
11	REPORTING GROUP ROOT										17,905.00			
12	Income										21,000.00			
13			010000 Sales											36,000.00
14			100000 Cost of sales										15,000.00	
15	Expenses						3,095.00							
16			200000 Bank charges										45	
17			205000 Depreciation										150	
18			210000 Motor vehicle expenses				2,160.00							
19			210010 Fuel and oil										150	
20			210020 Maintenance										810	
21			210030 Repairs										1,200.00	
22			220000 Rent										500	
23			230000 Stationery										240	
24					Totals								18,095.00	36,000.00
25						Net profit								17,905.00
26	Handyman Hardware Store										Printed : 2022/05/21 22:59:09			
27		Data: C:\osfinancials5\Books\2022-HELP-DEMO\books.fdb												
28		System user: danva osFinancials user:									Page: 1 /			

Income statement - CSV file - LibreOffice

An example, of the "*Income statement*" saved as a comma separated values file, and opened in "*LibreOffice Calc*" (spreadsheet) is as follows:



Select the "Separator Options", if necessary.

Click OK.

The data, according to this selection, will be displayed in the various columns.



Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-Use Tool

Reportman output - Save metafile as bitmap

The "*Bitmap File*" type extension is a Bitmap image file. The BMP file contains raster graphics data which are independent of display devices. BMP images may be uncompressed or compressed with a lossless compression method.

Saving a report or document layout as a Bitmap file is useful when you need a high-resolution, device-independent image. However, be aware that Bitmap files can be much larger than their compressed counterparts, such as PDFs. Always consider the intended use and storage requirements before choosing the Bitmap format.

This significant increase in file size is due to the uncompressed nature of Bitmap files, which store each pixel of the image individually.

What is the color of a monochrome image?

A monochrome image typically refers to an image that uses a single color or shade to represent all the pixels. The most common interpretation of a monochrome image is that it is black and white.

Key Points:

- Black and White: In a strict sense, a monochrome image is usually black and white, meaning it uses

only two colors: black and white. This is often referred to as binary or bitonal imaging.

- Grayscale: Sometimes, the term "monochrome" can also refer to images that use a range of shades of gray, from black to white. This is known as grayscale imaging. In this case, the image can have varying shades of gray, but it still uses only one color channel (gray).
- Practical Consideration:
    - Default Setting: When you select "*Monochrome*" as the color mode in the "*Bitmap properties*" screen, it typically means the image will be rendered in black and white. However, if the software allows for grayscale options within the monochrome setting, it might also include shades of gray.
    - Example:
        - Binary Monochrome: An image where every pixel is either black or white.
        - Grayscale Monochrome: An image where every pixel can be any shade of gray, but there are no colors other than shades of gray.

The default interpretation of a monochrome image is black and white. However, depending on the software and settings, it might also include shades of gray, making it a grayscale image. Always check the specific settings and documentation of the software you are using to confirm the exact behavior of the monochrome option.

What apps or tools can be used to open bitmap files?

Bitmap files, which typically have the `.bmp` file extension, can be opened and viewed using a variety of applications and tools. Here are some common options:

1. Microsoft Paint: A basic image editor that comes pre-installed with Windows.
2. Microsoft Photos: A convenient and user-friendly tool for viewing and printing BMP images. While it may not offer advanced editing features like some dedicated image editors, it is more than sufficient for basic viewing and printing tasks. This makes it a handy option for quickly reviewing and printing reports or document layout files saved as BMP images.
3. Adobe Photoshop: A professional image editing software.
4. GIMP (GNU Image Manipulation Program): A free, open-source alternative to Photoshop.
5. CorelDRAW: A vector graphics editor, but it can also import and open and edit bitmap files.
6. Microsoft Word and PowerPoint: While primarily document and presentation tools, they can also open and insert bitmap images.

7. LibreOffice Writer and Impress: A word processing application similar to Microsoft Word. LibreOffice Impress is a presentation application similar to Microsoft PowerPoint.
8. Google Photos: An online photo storage and viewing service.
9. Web Browsers: Modern web browsers like Chrome, Firefox, and Edge can display bitmap images directly.
10. Preview (macOS): A default image and PDF viewer on macOS.
11. IrfanView: A fast, compact, and innovative graphics viewer for Windows.
12. XnView: A freeware utility for viewing and converting graphic files.
13. Online Image Viewers: Various online tools that allow you to upload and view bitmap files.

Bitmap files are widely supported and can be opened using a variety of software tools, ranging from basic image viewers like Microsoft Paint to professional image editing software like Adobe Photoshop. These files can also be opened and viewed across various operating systems, including Windows, macOS, and Linux. The choice of tool depends on your specific needs, such as viewing, editing, or sharing the image.

Save metafile options

To save reports or document layout files as a bitmap file:

1. On the "*Reportman print preview*" screen, select Save (Ctrl+S) – This will launch the "*Save metafile as*" screen.
2. Select the directory (folder) where you need to save this file, if necessary.
3. Enter a file name.
4. Select the "*Bitmap File (*.bmp)"* file type.
5. Click Save. The "*Bitmap properties*" screen is displayed.



To view the OK and Cancel buttons, you need to resize the "Bitmap properties" screen

6. The default values is 100 dots per inch in both the horizontal and vertical resolution.
7. "*Monochrome*" is the default value. Leave this selected. It will create a bitmap image of the report or layout file.

These Bitmap image files may be much larger in size. For example, if an Invoice layout file is saved in the PDF file format, the size would be 277 KB (Kilobytes). The same Invoice layout file in the Bitmap format, could be as large as 3.56 MB (Megabytes).

Income statement - Bitmap file

An example of the "*Income statement*" saved as a Bitmap file, opened in "*Paint*", is as follows:



Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Reportman output - Save metafile as svg

The "*Scalable Vector Graphics file*" type SVG file type extension is a is an *Extensible Markup Language* (XML)-based *vector image format* for *two-dimensional* graphics with support for interactivity,

SVG images and their related behaviours are defined in *XML* text files, which means they can be searched, indexed, scripted, and compressed.

There are a few SVG editors available to edit SVG files.

What apps or tools can be used to open svg files?

Some of the tools and apps that can be used to open SVG files, along with their cross-compatibility across different operating systems is listed as follows:

1. Web Browsers
    - Google Chrome: Windows, macOS, Linux, Android, iOS
    - Mozilla Firefox: Windows, macOS, Linux, Android, iOS
    - Microsoft Edge: Windows, macOS, Android, iOS
    - Safari: macOS, iOS
2. Image Viewers and Editors
    - Inkscape: Windows, macOS, Linux
    - Adobe Illustrator: Windows, macOS
    - GIMP: Windows, macOS, Linux
    - CorelDRAW: Windows, macOS
3. Office Suites
    - Microsoft Office (Word, PowerPoint, Excel): Windows, macOS
    - LibreOffice (Writer, Impress, Draw): Windows, macOS, Linux
4. Online Tools
    - SVG Viewer Online: Cross-platform (accessible via any modern web browser)
    - Cloud Services (Google Drive, Dropbox): Cross-platform (accessible via any modern web browser)
5. Mobile Apps
    - Adobe Illustrator Draw: iOS, Android
    - Inkscape Viewer**: Android
6. Command Line Tools
    - ImageMagick: Windows, macOS, Linux
7. Text Editors
    - Visual Studio Code: Windows, macOS, Linux

- Sublime Text: Windows, macOS, Linux

8. Other Tools
    - SVG-Edit: Cross-platform (accessible via any modern web browser)

This list should help you find the right tool for viewing and editing SVG files regardless of your operating system.

Save metafile options

To save reports or document layout files as a Scalable Vector Graphics file:

1. On the "*Reportman print preview*" screen, select Save (Ctrl+S) – This will launch the "*Save metafile as*" screen.
2. Select the directory (folder) where you need to save this file, if necessary.
3. Enter a file name.
4. Select the "*Scalable Vector Graphics (*.svg)*" file type.
5. Click Save.

Income statement - SVG file

An example of the "*Income statement*" saved as a SVG file, opened in "*Microsoft Edge*", is as follows:



Since the Namespace links, by default renders an error as displayed in the "*Microsoft Edge*" Web browser, as per this example, as well as in other Web browsers ,such as Google Chrome, etc.), the report headers seem to be displayed correctly, but the data in the report details does not display.

Using a SVG editor such as Inkscape is professional quality vector graphics software which runs on Windows desktop, Linux, Mac OS X and most computers, the data displays correctly.



If a report is saved as a "*Scalable Vector Graphics file*" file format, it will save the file in separate pages. An example of a one page saved "*Scalable Vector Graphics file*" will also export numbering bullets (numbering) as objects for each page.

The vertical lines, separating the columns, in the "*detail*" report used to print the Trial balance, Income statement, Balance sheet, etc. is exported as bullets (numbering) objects.



Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Reportman output - Save metafile as custom text file

The custom text file option does not save any data. It creates a blank text file.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Reportman output - Save metafile as metafiles

The following Meta file file types is available to save reports or layout files:

- Report Metafile *.rpmf
- Executable Meta file uncompressed *.rpmf
- Executable meta file *.exe

These File types could not be opened, if the required applications are not available on your system.

Executable meta file *.exe may produce a system error as follows:

"System Error. Code: 2.
The system cannot find the file specified"

Created with the Standard Edition of HelpNDoc: Free EPub producer

Ledger analyser

All processed (posted) transactions will be accumulated in the Ledger analyser 1 or Ledger analyser 2 (Reports ribbon). There are various ways in which the transactions may be viewed, exported and analysed.

The options, is as follows:

1. Transactions and balances – These are the balances of transactions as posted (updated to the ledger) in batches (journals), sales documents (i.e. Invoices, Point-of-Sale Invoices and Credit notes) and purchase documents (i.e. Purchases and Supplier returns).

   There are six (6) report types, which may be selected (i.e. Trial balance, Income statement, Balance sheet, Standard column balances, Budget vs actual and This year vs last year) which may be printed and exported to spreadsheets.

   In addition to this, there are 6 report types which may be exported to spreadsheets (i.e. Column balances, Column balances Debit/Credit, Column balances debtor, Column balances creditor, Column balances debtor Debit/Credit, and Column balances creditor Debit/Credit.)

2. Budget – Budget figures as entered in Budgets (Reports ribbon) or in the Setup → Accounts (Setup ribbon). This option, if selected, will list only the budget figures (Budget listing) in the Trial balance, Income statement, Balance sheet and Standard column balances report types. The Budget vs Actual is the budget performance report. It will list and compare the budget figures versus the actual posted (updated) transactions.

3. T-Account viewer – You may select a specific account, group, etc. to view the transactions in the T-Account viewer. To do this, right-click on a selected account, and select the "*Show details*" option on the context menu.

The T-Account viewer may also be selected on the T-Account viewer on the Reports ribbon. When launching it from the Reports ribbon, you may select the following:

- *Account – Select a specific account.*
- *From date and To date – Select a specific date or a range of dates to view data.*

You may click on the following to get specific views of transactions:

- *Batch number (e.g. 10012, etc. automatically generated). This will list only the transactions for a specific batch (journal).*
- *Account code (e.g. G010000 Sales, B810000 ABC - Bank, T860010 Input VAT/GST/Sales tax, etc.). This will list the transactions for a specific account.*
- *Date – This will list the transactions for a specific date. If you double-click on a date, the "From date" and "To date" will be changed to the selected date.*

Ledger analyser options

To print reports in the Ledger analyser:

1. On the Reports ribbon, select Ledger analyser 1 / 2.



Ledger analyser 1 and Ledger analyser 2 Features implemented in osFinancials5/TurboCASH5:

- *SBR view - (Standard Business Reporting) Add SBR references for accounts and reporting groups in Setup → Accounts. Once the references are set, and generate reports on screen, click on the SBR view button, check, filter and copy to clipboard. Open your spreadsheet program, and copy the contents into your spreadsheet, save the data, etc.*
- *Pivot – View, filter and analyse your report on screen, view graphs, customise datasets and types of graphs.*
- *Zoom in / Zoom out + / - buttons added to resize (increase / decrease the font) the reports (i.e. Trial balance, Balance sheet and Income statement) on screen.*

2. Select the following options:

Option	*Description*

Report type:



1. *Trial balance – List of all accounts in the chart of accounts. This will include:*
   a) *- Income /* *- Expense;*
   b) *- Asset / Liability / Capital accounts;*
   c) *- Retained earnings / income;*
   d) *- Debtor's control; and*
   e) *- Creditor's control accounts.*
2. *Income statement -* *Income /* *Expenses – List only those accounts which is reported on the Income statement.*
3. *Balance sheet – List only those Accounts, which is reported in the Balance sheet. This will include:*
   a) *- Asset / Liability / Capital accounts;*
   b) *- Retained earnings / income;*
   c) *- Debtor's control; and*
   d) *- Creditor's control accounts.*
4. *Standard column balances – Lists the debit and credit account balances in the Trial balance and the Income statement and Balance sheet accounts in separate columns.*
5. *Budget vs actual – Lists the budget figures entered in the Setup → Accounts (Setup ribbon) versus the actual totals of all transactions in posted batches and documents.*
6. *This year vs last year – This will list the actual totals of all transactions in posted batches and documents in this year periods versus the actual totals of all transactions in posted batches and documents posted to last year periods (previous financial years).*
7. *Column balances – Lists all accounts in a spreadsheet view.*

These are the Accounts reported in the Trial balance (this includes both the accounts reported in the Trial balance, Income statement and Balance sheet).

8. *Column balances debtors – Lists the balances of all accounts which is created and maintained in the Debtors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
9. *Column balances creditors – Lists all accounts which is created and maintained in the Creditors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*
10. *Column balances D/C – Lists all debit and credit account balances in a spreadsheet view. These are the Accounts reported in the Trial balance (this includes both the accounts reported in the Trial balance, Income statement and Balance sheet).*
11. *Column balances debtors D/C – Lists the debit and credit account balances of all accounts which is created and maintained in the Debtors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
12. *Column balances creditors D/C – Lists all debit and credit account balances which is created and maintained in the Creditors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*

Budget:

This will list all accounts for which budget figures were entered (and / or edited) in Budgets (Reports ribbon) or the Setup → Accounts (Setup ribbon).

If you wish to print a list of the Budget figures, tick the "Budget option" on the following report types:



- *Trial balance*
- *Income statement*

	• *Balance sheet*
Cost centre 1 / 2:	*The Cost centres (2 Groups) will only be available, if Cost centres are added in Groups (Setup ribbon); and if activated.*
Groups:	*Select one of the following options:* • *None – This is the default. This will list all accounts for the selected Report type according to the Account numbers (codes) in numerical order.* • *Reporting group 1 – Lists all accounts according to the Account reporting group 1 as created in Groups (Setup ribbon).* • *Reporting group 2 – Lists all accounts according to the Account reporting group 2 as created in Groups (Setup ribbon).* *Reporting group 1 and 2 – The sequence in which the groups and accounts are listed, may be changed in Groups. (Setup ribbon).* *This is done by selecting the groups on the list and use the Move up or Move down buttons.*
Period:	*Select "Per period" or "Free selection"* • *Per period – Select a period (Month, 2 Months, 3 Months, 4 Months, 6 Months or Year.* • *Free selection – You may select or enter any date or dates.*
From: *To:*	*The periods will automatically filter and display the periods matching the selected option in the "Per period" radio selection options.* *On the "Free selection" tab, you may select any date or dates in the "From date" and "To date" fields.*
Ignore zero balances:	*If this field is not selected, all accounts will be listed for the selected reports type. If you select (tick) this field; only those accounts with balances will be included in the report.*
Include opening balances:	*If this option is selected (ticked), it will include the opening balances of those accounts which have opening balances. If this option is not selected; the opening balances will not be included in the report.* *(Not applicable to the Income statement report type).*

Opening balances only:	*If the "Include opening balances" option is not selected; this option will not be displayed. If this option is available; you may select (tick) this option to include only the opening balances. All other balances will then be ignored.* *(Not applicable to the Income statement and Column balances report types).*
Viewer Debtors / Creditors:	*Do not select (tick) if you only need to view the balances of the Debtor's control account and Creditor's control account only. If this field is selected (ticked), it will list all the individual accounts in the following ledgers:* · *Debtor's ledger - all debtor (customer / client) accounts.* · *Creditor's ledger - all creditor (supplier / vendor) accounts.* *(Only applicable to the Trial balance and the Balance sheet report types).*
Report button:	*This will generate the report as per your selection of the report parameters.*
Export button:	*This will export the report to a comma separated value (*.csv) file format. The exported data will automatically be opened in your system's default spreadsheet (if configured) e.g. Excel.*
Print button:	*Click to print the report.*

3. Select a group or account and right-click on it. On the context menu, select the "*Show details*" option. This will launch the T-Account viewer.

The T-Account viewer may also be selected on the T-Account viewer option (Reports ribbon).

The Ledger analyser will not be automatically updated when batches or documents are updated (posted) to the ledger.

You need to click on the Report button to rebuild (refresh) the report.

Printing unposted batches in the Ledger analyser

The Ledger analyser does not include unposted batches and documents. You may view, print and export a Trial balance, Income statement and Balance sheet for unposted as well as posted

batches from the Batch entry (F2) context menu.

Viewer Debtors / Creditors - Trial balance / Balance sheet

The Trial balance and the Balance sheet report types allows you to select the Viewer Debtors / Creditors option. This will list the individual debtor (customer / client) account balances for the Debtor's control account and the individual creditor (supplier / vendor) account balances for the Creditor's control account.

Do not select (tick) if you only need to view only the control accounts of the Debtor and Creditor accounts.

An example, in the "*Trial balance*" and "*Balance sheet*", listing the individual debtor (customer / client) and creditor (supplier / vendor) accounts, is as follows:



Export to CSV Files

The export feature of the T-Account Analyser allows you to create export files of any view of the data to the Comma Separated Value (*.csv) file format. You may then use your favourite Spreadsheet program (e.g. OpenOfficeCalc or Microsoft Excel, etc.) to analyse, sort and filter the data.

You may also build charts in your Spreadsheet program and use it to make powerful presentations in your presentation program (e.g. OpenOfficeImpress, Microsoft Powerpoint, etc.).

To create a Ledger Export report:

1. Once finished, selecting your options, click on the Report button to update the Ledger analyser screen.
2. You may then click on the Export button. This will launch the *Save as* screen.
3. Select the folder in which you wish to save the file.
4. The default file name will be *ExportLedger*. Overtype this with your own, if necessary. If you do not do this, you may replace existing (previously exported) files.
5. Select the file type *Comma Separated Value* (*.csv).
6. Click on the Save button. This will automatically open (launch) the file in the program associated with the Comma Separated Value file type (e.g. OpenOfficeCalc or Microsoft Excel, etc.).

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Ledger analyser - Trial balance

A Trial balance is a simple list of the debit and credit account balances in the general ledger. A Trial balance can be generated at any time, once the transactions are posted to the ledger accounts. It checks the arithmetic accuracy of the double entry accounting system as at a specific date. The total of all the debit balances must be equal to the total of credit balances.

The Trial balance will list all the debit and credit balances of all the Accounts (Income, Expenses, Assets, Capital and Liabilities) contained in osFinancials5/TurboCASH5 for a selected period, or as at a specified period. osFinancials5/TurboCASH5 stores all your account balances for up to two financial years. You may at any time generate a Trial balance for any accounting period for the current (This Year) and the previous financial year (Last Year), provided that you have posted (updated) transactions to the ledger accounts.

Types of Trial balances

The following Trial balances may be generated at different stages in the accounting process:

1. Pre-adjustment Trial balance - The debit and credit balances are listed, before any adjustments are made in the accounts, and it normally includes all balances of capital, assets, liabilities, income and expense accounts for any selected accounting period. For example, you may generate this Trial balance, after all your normal transactions in batches and documents have been updated and posted to the ledger. This may include any correction of errors on a general journal to correct any incorrect posted transactions.

2. Post-adjustment Trial balance - The debit and credit balances are listed, after the final adjustments are made in the accounts, and it normally includes all balances of capital, assets, liabilities, income and expense accounts.

3. Final Trial balance - The debit and credit balances are listed, after the final closing entries are done, when you have completed the Year-end process on the Do year end option (Setup ribbon). This Trial balance will not include income and expense accounts, but only the calculated net profit or loss in the Retained earnings ledger account. All nominal accounts (income and expense accounts) are closed off at the end of a financial year, and no balances are brought down to the new financial year.

This will list all accounts in the chart of accounts reported both in the Income statement (Income / Expense accounts), as well as the Balance sheet.

This will list the following account types:

- Income statement - Income / Expense accounts.
- Balance sheet - Assets, Liabilities and Capital. It includes the following account types, i.e.:
  - Bank accounts.
  - Tax accounts.
  - Retained income / earnings.
  - Creditor's control account.
  - Debtor's control account.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Trial balance options

To print a Trial balance:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the "*Trial balance*" report type.



3. Per period - Select a period (Month, 2 Months, 3 Months, 4 Months, 6 Months or Year).

> *You may click on the "Free selection" tab. You may select or enter any date or dates, which you need to include in the "Trial balance".*

4. Groups - "*None*" is the default option. You may select "*Reporting group 1*" or "*Reporting group 2*".

> *If you have created two (2) Reporting groups (Setup → Groups), you may have different views of your data. For example the Group options:*
>
> - *None - Lists all accounts according to account code.*
> - *Reporting group 1 - List all accounts according to the reporting group (e.g. Income + Expenses + Capital + Current liabilities + Fixed assets + Current assets)*
> - *Reporting group 2 - List all accounts according to the reporting group (e.g. Fixed assets + Current assets + Capital + Current liabilities + Income + Expenses)*

> *To change your view of the Accounting groups , select the groups and use the Move up and Move down buttons to change the sequence.*
>
> *This will determine the sequence in which your Groups are listed on the Setup → Accounts option on the Setup ribbon and on the Ledger analyser is displayed, when Reporting group 1 or Reporting group 2 is selected.*

5. Ignore zero balances - If this field is not selected, all accounts will be listed for the Trial balance. If you select (tick) this field; only those accounts with balances will be included in the "*Trial balance*".
6. Viewer Debtors / Creditors - Do not select (tick) if you only need to list only the control accounts of

the Debtor (customer / client) and Creditor (supplier / vendor) accounts. If this field is selected (ticked), it will list the individual debtor (customer / client) and creditor (supplier / vendor) accounts.

> *The Trial balance and the Balance sheet report types allows you to select the Viewer Debtors / Creditors option.*
>
> *Tick this option to show the break down of the Debtor (customer / client) accounts in the Debtor's control account and the break down of the Creditor (supplier / vendor) accounts in the Creditor's control account. This will list all individual debtor (customer / client) for the debtor's control account and creditor (supplier / vendor) account balances for the creditor's control account.*



7. Include opening balances - If this option is selected (ticked), it will include the opening balances of those accounts which have opening balances. If this option is not selected; the opening balances will not be included in the "*Trial balance*".

8. *Opening balances only* - This option will only be available if the "*Include opening balances*" option is selected. You can select (check) this option to include only the opening balances. All other balances will then be ignored.

9. Budget - Leave this option blank to include the actual posted (updated) transactions in the "*Trial balance*".

> *The "Budget" option, if selected, will list only the budget figures (Budget listing) in the Trial balance, Income statement, Balance sheet and Standard column balances report types (if budget figures were entered in the Budgets option (Reports ribbon) or Setup → Accounts option on the Setup ribbon).*

10. Cost centre 1 and Cost centre 2 - The Cost centres (2 Groups) will only be available, if Cost centres are added in Setup → Groups on the Setup ribbon; and if activated.

11. Click on the Report button. This will build or refresh the "*Trial balance*" with the selected options.

Example : Trial balance

An example of the "*Trial balance - Reporting group 1"* report type, is displayed as follows:



Buttons 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the

Set of Books.

If you have created two (2) Reporting groups (Setup → Groups), you may have different views of your data. For example the Group options:

- *None - Lists all accounts according to account code.*
- *Reporting group 1 - List all accounts according to the reporting group (e.g. Income + Expenses + Capital + Current liabilities + Fixed assets + Current assets)*
- *Reporting group 2 - List all accounts according to the reporting group (e.g. Fixed assets + Current assets + Capital + Current liabilities + Income + Expenses)*

To change your view of the Accounting groups , select the groups and use the Move up and Move down buttons to change the sequence.

This will determine the sequence in which your Groups are listed on the Setup → Accounts option on the Setup ribbon and on the Ledger analyser is displayed, when Reporting group 1 or Reporting group 2 is selected.

Click on the Print button.

Printed example : Trial balance

An example of the printed "*Trial balance - Reporting group 1"*, is displayed as follows:

Page 1 -


detail

Trial balance Period 2021/03/01 / 2022/02/28

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT				
Income				
010000 Sales				36,000.00
100000 Cost of sales			15,000.00	
Expenses				
200000 Bank charges			45.00	
205000 Depreciation			150.00	
210000 Motor vehicle expenses	**2,160.00**			
210010 Fuel and oil			150.00	
210020 Maintenance			810.00	
210030 Repairs			1,200.00	
220000 Rent			500.00	
230000 Stationery			240.00	
Capital				
505000 Capital				5,000.00
Current liabilities				
860000 VAT - Control - 15%		**4,119.00**		
860010 Output VAT - 15%				5,400.00
860020 Input VAT - Standard rate -15%			1,161.00	
860030 Input VAT - Capital goods -15%			120.00	
900000 Creditors control				5,000.00
Fixed assets				
600000 Furniture & fittings - Net value	**3,750.00**			
600010 Furniture fittings @ cost			3,800.00	
600020 Furniture fittings -Acc. deprec.				50.00
610000 Motor vehicles - Net value		**100.00**		
610020 Motor vehicles -Accum. depreciation				100.00
Current assets				

Page 2 -


detail

Trial balance Period 2021/03/01 / 2022/02/28

	Totals Debit	Totals Credit	Debit	Credit
700000 Debtors control			38,400.00	
750000 Stock control				13,000.00
810000 ABC - Bank			2,930.00	
820000 Petty cash			44.00	
		Totals	**64,550.00**	**64,550.00**
		Net profit	**18,095.00**	**36,000.00**
				17,905.00

To save the Trial balance as a PDF file:

1. *On the "Reportman print preview" screen, select Save (Ctrl+S)* *– This will launch the "Save metafile as" screen.*
2. *Select the directory (folder) where you need to save this file, if necessary.*
3. *Enter a file name.*
4. *Select the "PDF File – compressed" default file type.*
5. *Click Save.*

To change your view of the Accounting groups, select the groups and use the Move up and Move down buttons to change the sequence.

This will determine the sequence in which your Groups are listed on the Setup → Accounts and on the Reports → Ledger analyser 1 is displayed, when Reporting group 1 or Reporting group 2 is selected.

Spreadsheet example : Trial balance

To create a Trial balance - Export file:

1. Click on the Export button. This will launch the "*Save as*" screen.



2. Select the folder in which you wish to save the file.

3. The default file name will be "*Export.txt*". Overtype this with your own name.

> *If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.*
>
> *Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:*
>
> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

4. Click on the Save button.

5. This will automatically open (launch) the file in your system's default text editor program associated with value text file type.



	A	B	C	D	E	F	G	H	I
1	Per period	2021/03/01	Groups	Reporting group 1	Report type	Trial balance			
2	Per period	Year	Budget	FALSE					
3	Ignore zero balances	TRUE	Include opening balances	TRUE					
4	Viewer Debtors / Creditors	TRUE	Opening balances only	FALSE					
5									
6		REPORTING GROUP ROOT					0		
7			Income				0		
8			G010000	Sales				0	36,000.00
9			G100000	Cost of sales				15,000.00	0
10			Expenses				0		
11			G200000	Bank charges				45	0
12			G205000	Depreciation				150	0
13			G210000	Motor vehicle expenses			2,160.00		
14				G210010	Fuel and oil			150	0
15				G210020	Maintenance			810	0
16				G210030	Repairs			1,200.00	0
17			G220000	Rent				500	0
18			G230000	Stationery				240	0
19			Capital				0		
20			G505000	Capital				0	16,500.00
21			G510000	Retained income				0	4,200.00
22			Current liabilities				0		
23			G860000	VAT - Control - 15%			-4,219.00		
24				T860010	Output VAT - 15%			0	5,500.00
25				T860020	Input VAT - Standard rate -15%			1,161.00	0
26				T860030	Input VAT - Capital goods -15%			120	0
27			G900000	Creditors control			-6,000.00		
28					Creditor group 1B		0		
29					C2AONES	A-ONE Suppliers		0	600
30					C2BESTS	BEST Suppliers		0	400
31					Creditor group 1C		0		
32					C2ABCOS	ABC-Office-Supplies		0	2,700.00
33					C2ABCSC	ABC-Service-Centre		0	2,300.00

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Ledger analyser - Income statement

The Income statement will list all the balances of your accounts which are created as an Income / Expense type in the Setup → Accounts menu, and will reflect your net profit or loss for a specific period. The Income statement has two main sections (financial categories), i.e. Income and Expenses. When the Income exceeds the Expenses, the report will reflect the net profit. If the Expenses exceed the Income, the report will reflect a net loss.

The Income statement is used to manage and report on your businesses' income and expenses. osFinancials5/TurboCASH5 allows you to compare the actual figures in the Income statement with one of the following comparative figures:

- Last year's actual figures, if available. The financial performance of the actual figures may be compared to last year' actual figures for the selected periods.

- Budget figures, if entered in the Budgets option (Reports ribbon) or Setup → Accounts option (Setup ribbon). If the budgeted figures are entered correctly, you may compare the actual income received and expenses paid to the budgeted figures, to determine whether your income is on track, or where you are over spending or under spending.

This will list the following account types and account groups:

- Income accounts.
- Expense accounts.

> *This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.*
>
> *To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).*

Income statement options

To print an Income statement:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the "*Income statement*" report type.



3. Per period - Select a period (Month, 2 Months, 3 Months, 4 Months, 6 Months or Year).

> *You may click on the "Free selection" tab. You may select or enter any date or dates, which you need to include in the Income statement.*

4. Groups - "*None*" is the default option. You may select "*Reporting group 1*" or "*Reporting group 2*".

> *If you have created two (2) Reporting groups (Setup → Groups), you may have different views of your data. For example the Group options:*

- *None - Lists all accounts according to account code.*
- *Reporting group 1 - List all accounts according to the reporting group (e.g. Income + Expenses)*
- *Reporting group 2 - List all accounts according to the reporting group (e.g. Income + Expenses)*

To change your view of the Accounting groups , select the groups and use the Move up and Move down buttons to change the sequence.

This will determine the sequence in which your Groups are listed on the Setup → Accounts option on the Setup ribbon and on the Ledger analyser is displayed, when Reporting group 1 or Reporting group 2 is selected.

5. Ignore zero balances - If this field is not selected, all income and expense accounts will be listed for the Income statement balance. If you select (tick) this field; only those income and expense accounts with balances will be included in the Income statement.
6. Budget - Leave this option blank to include the actual posted (updated) transactions in the Income statement.

The "Budget" option, if selected, will list only the budget figures (Budget listing) in the Trial balance, Income statement, Balance sheet and Standard column balances report types (if budget figures were entered in the Budgets option (Reports ribbon) or Setup → Accounts option on the Setup ribbon).

7. Cost centre 1 and Cost centre 2 - The Cost centres (2 Groups) will only be available, if Cost centres are added in Setup → Groups on the Setup ribbon; and if activated.
8. Click on the Report button. This will build or refresh the Income statement with the selected options.

Example : Income statement

An example of the "*Income statement - Reporting group 1"* report type, is displayed as follows:



Buttons 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

Printed example : Income statement

Click on the Print button. An example of the printed "*Income statement - Reporting group 1*", is displayed as follows:



To save the Income statement as a PDF file:

1. *On the "Reportman print preview" screen, select Save (Ctrl+S)* *– This will launch the "Save metafile as" screen.*
2. *Select the directory (folder) where you need to save this file, if necessary.*
3. *Enter a file name.*
4. *Select the "PDF File – compressed" default file type.*
5. *Click Save.*

Spreadsheet example : Income statement

To create an Income statement - Export file:

1. Click on the Export button. This will launch the "*Save as*" screen.



2. Select the folder in which you wish to save the file.

3. The default file name will be "*Export.txt*". Overtype this with your own name.

> *If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.*
>
> *Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:*
>
> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

4. Click on the Save button.

5. This will automatically open (launch) the file in your system's default text editor program associated with value text file type.



	A	B	C	D	E	F	G	H
1	Per period	2021/03/01 / 2022/02/28	Groups	Reporting group 1	Report type	Income statement		
2	Per period	Year	Budget	FALSE				
3	Ignore zero bala	TRUE	Include opening balances	FALSE				
4	Viewer Debtors	FALSE	Opening balances only	FALSE				
5								
6		REPORTING GROUP ROOT				0		
7			Income			0		
8			G010000	Sales			0	36,000.00
9			G100000	Cost of sales			15,000.00	0
10			Expenses			0		
11			G200000	Bank charges			45	0
12			G205000	Depreciation			150	0
13			G210000	Motor vehicle expenses		2,160.00		
14				G210010	Fuel and oil		150	0
15				G210020	Maintenance		810	0
16				G210030	Repairs		1,200.00	0
17			G220000	Rent			500	0
18			G230000	Stationery			240	0
19								
20						Net Profit/Loss	0	0
21						Balance	0	0

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Ledger analyser - Balance sheet

The Balance sheet is a statement of all Assets and Liabilities of a business at a particular time. It has three main components, i.e. Assets, Liabilities and Capital. This report will reflect the owners' interest in the business, as well as all Liabilities and Assets.

The balancing figure is the Net Profit or Loss. A Net Profit is displayed, when the Income account balances are more than the Expense account balances. A Net Loss is displayed, when the Expense account balances are more than the Income account balances.

The Balance sheet will list all the balances of your accounts which are not created as Income / Expense types in the Setup → Accounts option on the Setup ribbon).

The Reporting groups (on the Account Group 1 tab in the Groups option on the Setup ribbon) should be linked to the Assets, Capital and Liabilities Financial categories (in the Setup → Financial categories menu on the (Setup ribbon), before this report is generated.

This will list all accounts in the chart of accounts reported only in the Balance sheet.

Balance sheet - Assets, Liabilities and Capital. It includes the following account types, i.e.:

- Bank accounts
- Tax accounts
- Retained income / earnings.
- Creditor's control account.
- Debtor's control account.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Balance sheet options

To print a Balance sheet:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the "*Balance sheet*" report type.



3. Per period - Select a period (Month, 2 Months, 3 Months, 4 Months, 6 Months or Year).

You may click on the "Free selection" tab. You may select or enter any date or dates, which you need to include the Balance sheet.

4. *Groups* - "*None*" is the default option. You may select "*Reporting group 1*" or "*Reporting group 2*".

> *If you have created two (2) Reporting groups (Setup → Groups), you may have different views of your data. For example the Group options:*
>
> - *None - Lists all accounts according to account code.*
> - *Reporting group 1 - List all accounts according to the reporting group (e.g. Capital + Current liabilities + Fixed assets + Current assets)*
> - *Reporting group 2 - List all accounts according to the reporting group (e.g. Fixed assets + Current assets + Capital + Current liabilities)*

> *To change your view of the Accounting groups , select the groups and use the Move up and Move down buttons to change the sequence.*
>
> *This will determine the sequence in which your Groups are listed on the Setup → Accounts option on the Setup ribbon and on the Ledger analyser is displayed, when Reporting group 1 or Reporting group 2 is selected.*

5. Ignore zero balances - If this field is not selected, all accounts will be listed for the Balance sheet. If you select (tick) this field; only those accounts with balances will be included in the Balance sheet.

6. Viewer Debtors / Creditors - Do not select (tick) if you only need to list only the control accounts of the Debtor (customer / client) and Creditor (supplier / vendor) accounts. If this field is selected (ticked), it will list all the individual debtor (customer / client) and creditor (supplier / vendor) accounts.

> *The Trial balance and the Balance sheet report types allows you to select the Viewer Debtors / Creditors option.*
>
> *Tick this option to show the break down of the Debtor (customer / client) accounts in the Debtor's control account and the break down of the Creditor (supplier / vendor) accounts in the Creditor's control account. This will list all individual debtor (customer / client) for the debtor's control account and creditor (supplier / vendor) account balances for the creditor's control account.*



7. Include opening balances - If this option is selected (ticked), it will include the opening balances of those accounts which have opening balances. If this option is not selected; the opening balances will not be included in the Balance sheet.

8. Opening balances only - This option will only be available if the "*Include opening balances*" option is selected. You can select (check) this option to include only the opening balances. All other balances will then be ignored.

9. Budget - Leave this option blank to include the actual posted (updated) transactions in the Balance sheet.

> *The "Budget" option, if selected, will list only the budget figures (Budget listing) in the Trial balance, Income statement, Balance sheet and Standard column balances report types (if budget figures were entered in the Budgets option (Reports ribbon) or Setup → Accounts option on the Setup ribbon).*

10. Cost centre 1 and Cost centre 2 - The Cost centres (2 Groups) will only be available, if Cost centres are added in Setup → Groups on the Setup ribbon; and if activated.

11. Click on the Report button. This will build or refresh the Balance sheet with the selected options.

Example : Balance sheet

An example of the "*Balance sheet - Reporting group 1"* report type, is displayed as follows:



Buttons 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

If you have created two (2) Reporting groups (in Setup → Groups (Setup ribbon)), you may have different views of your data. For example the Group options:

- None - Lists all accounts according to account code.
- Reporting group 1 - List all accounts according to the reporting group (e.g. Capital + Current Liabilities + Fixed Assets + Current Assets)
- Reporting group 2 - List all accounts according to the reporting group (e.g. Fixed Assets + Current Assets + Capital + Current Liabilities)

To change your view of the Accounting groups , select the groups and use the Move up and Move down buttons to change the sequence.

This will determine the sequence in which your Groups are listed on the Setup → *Accounts option on the Setup ribbon and on the Ledger analyser is displayed, when Reporting group 1 or Reporting group 2 is selected.*

Printed example : Balance sheet

Click on the Print button. An example of the printed "*Balance sheet - Reporting group 1"*, is displayed as follows:



detail

Balance sheet Period 2021/03/01 / 2022/02/28

	Totals Debit	Credit	Debit	Credit
REPORTING GROUP ROOT	**17,905.00**			
Capital		**5,000.00**		
505000 Capital				5,000.00
Current liabilities		**9,119.00**		
860000 VAT - Control - 15%		**4,119.00**		
860010 Output VAT - 15%				5,400.00
860020 Input VAT - Standard rate -15%			1,161.00	
860030 Input VAT - Capital goods -15%			120.00	
900000 Creditors control				5,000.00
Fixed assets	**3,650.00**			
600000 Furniture & fittings - Net value	**3,750.00**			
600010 Furniture fittings @ cost			3,800.00	
600020 Furniture fittings -Acc. deprec.				50.00
610000 Motor vehicles - Net value		**100.00**		
610020 Motor vehicles -Accum. depreciation				100.00
Current assets	**28,374.00**			
700000 Debtors control			38,400.00	
750000 Stock control				13,000.00
810000 ABC - Bank			2,930.00	
820000 Petty cash			44.00	
		Totals	**46,455.00**	**28,550.00**
		Net profit		**17,905.00**

To save the Balance sheet as a PDF file:

1. *On the "Reportman print preview" screen, select Save (Ctrl+S)* *– This will launch the "Save metafile as" screen.*
2. *Select the directory (folder) where you need to save this file, if necessary.*
3. *Enter a file name.*

4. *Select the "PDF File – compressed" default file type.*
5. *Click Save.*

Spreadsheet example : Balance sheet

To create a Balance sheet - Export file:

1. Click on the Export button. This will launch the "*Save as*" screen.



2. Select the folder in which you wish to save the file.
3. The default file name will be "*Export.txt*". Overtype this with your own name.

If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.

Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

4. Click on the Save button.

5. This will automatically open (launch) the file in your system's default text editor program associated with value text file type.



	A	B	C	D	E	F	G	H	I	J
1	Per period	2021/03/01 / 2022/02/28	Groups	Reporting group 1	Report type	Balance sheet				
2	Per period	Year	Budget	FALSE						
3	Ignore zero balances	TRUE	Include opening balances	FALSE						
4	Viewer Debtors / Creditors	FALSE	Opening balances only	FALSE						
5										
6		REPORTING GROUP ROOT				0				
7			Capital			0				
8			G505000	Capital			0	5,000.00		
9			Current liabilities			0				
10			G860000	VAT - Control - 15%		-4,119.00				
11				T860010	Output VAT - 15%		0	5,400.00		
12				T860020	Input VAT - Standard rate -15%		1,161.00	0		
13				T860030	Input VAT - Capital goods -15%		120	0		
14			G900000	Creditors control			0	5,000.00		
15			Fixed assets			0				
16			G600000	Furniture & fittings - Net value		3,750.00				
17				G600010	Furniture fittings @ cost		3,800.00	0		
18				G600020	Furniture fittings -Acc. deprec.		0	50		
19			G610000	Motor vehicles - Net value		-100				
20				G610020	Motor vehicles -Accum. depreciation		0	100		
21			Current assets			0				
22			G700000	Debtors control			38,400.00	0		
23			G750000	Stock control			0	13,000.00		
24			B810000	ABC - Bank			2,930.00	0		
25			B820000	Petty cash			44	0		
26										
27						Net Profit/Loss	0	0		
28						Balance	0	0		
29										

Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

Ledger analyser - Standard column balances

The "*Standard column balances*" report type displays the account debit and credit balances in the following three (3) reports, in one report:

1. Trial balance (Income, Expenses, Assets, Liabilities and Capital).

2. Income statement (Income and Expenses).

3. Balance sheet (Assets, Liabilities and Capital).

This is a breakdown of the Trial balance into the Income statement and Balance sheet.

This report will only print in the account code sequence.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Standard column balances options

To print a Standard column balances report:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the "*Standard column balances*" report type.



3. Per period - Select a period (Month, 2 Months, 3 Months, 4 Months, 6 Months or Year).

You may click on the "Free selection" tab. You may select or enter any date or dates, which you need to include the Standard column balances report.

4. Ignore zero balances - If this field is not selected, all accounts will be listed for the Standard column balances report. If you select (tick) this field; only those accounts with balances will be included in the Standard column balances report.
5. Include opening balances - If this option is selected (ticked), it will include the opening balances of those accounts which have opening balances. If this option is not selected; the opening balances will not be included in the Standard column balances report. If this field is not selected, all accounts will be listed for the "*Standard column balances*" report. If you select (tick) this field; only those accounts with balances will be included in the "*Standard column balances*" report.
6. Opening balances only - This option will only be available if the "*Include opening balances*" option is selected. You can select (check) this option to include only the opening balances. All other balances will then be ignored.

7. Budget - Leave this option blank to include the actual posted (updated) transactions in the Standard column balances report.

> *The "Budget" option, if selected, will list only the budget figures (Budget listing) in the Trial balance, Income statement, Balance sheet and Standard column balances report types (if budget figures were entered in the Budgets option (Reports ribbon) or Setup → Accounts option on the Setup ribbon).*

8. Cost centre 1 and Cost centre 2 - The Cost centres (2 Groups) will only be available, if Cost centres are added in Setup → Groups on the Setup ribbon; and if activated.

9. Click on the Report button. This will build or refresh the Standard column balances report with the selected options.

Example : Standard column balances

An example of the "*Standard column balances*" report type, is displayed as follows:



Code	Name	Trial balance		Income statement		Balance sheet	
G010000	Sales	9,500.00	45,500.00	0.00	36,000.00	0.00	0.00
G100000	Cost of sales	20,500.00	5,500.00	15,000.00	0.00	0.00	0.00
G200000	Bank charges	45.00	0.00	45.00	0.00	0.00	0.00
G205000	Depreciation	150.00	0.00	150.00	0.00	0.00	0.00
G210010	Fuel and oil	150.00	0.00	150.00	0.00	0.00	0.00
G210020	Maintenance	810.00	0.00	810.00	0.00	0.00	0.00
G210030	Repairs	1,200.00	0.00	1,200.00	0.00	0.00	0.00
G220000	Rent	500.00	0.00	500.00	0.00	0.00	0.00
G230000	Stationery	240.00	0.00	240.00	0.00	0.00	0.00
G505000	Capital	0.00	16,500.00	0.00	0.00	0.00	16,500.00
G510000	Retained income	0.00	4,200.00	0.00	0.00	0.00	4,200.00
G600010	Furniture fittings @ cost	4,807.00	0.00	0.00	0.00	4,807.00	0.00
G600020	Furniture fittings -Acc. deprec.	0.00	350.00	0.00	0.00	0.00	350.00
G610010	Motor vehicles @ cost	5,000.00	0.00	0.00	0.00	5,000.00	0.00
G610020	Motor vehicles -Accum. depreciation	0.00	600.00	0.00	0.00	0.00	600.00
G700000	Debtors control	54,125.00	13,925.00	0.00	0.00	40,200.00	0.00
G750000	Stock control	20,500.00	27,000.00	0.00	0.00	0.00	6,500.00
B810000	ABC - Bank	11,193.00	5,070.00	0.00	0.00	6,123.00	0.00
B820000	Petty cash	200.00	56.00	0.00	0.00	144.00	0.00
T860010	Output VAT - 15%	1,425.00	6,925.00	0.00	0.00	0.00	5,500.00
T860020	Input VAT - Standard rate -15%	2,136.00	975.00	0.00	0.00	1,161.00	0.00
T860030	Input VAT - Capital goods -15%	120.00	0.00	0.00	0.00	120.00	0.00
G900000	Creditors control	10,525.00	16,525.00	0.00	0.00	0.00	6,000.00
	Net Profit/Loss			17,905.00	0	0	17,905.00
	Totals	143,126.00	143,126.00	36,000.00	36,000.00	57,555.00	57,555.00

Buttons 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

The "Show details" context menu option,is not available. To access the T-Account viewer for a selected account, you need to double-click on an amount.

Printed example : Standard column balances

Click on the Print button. An example of the printed "*Standard column balances" report*, is displayed as follows:



colbalsimple

Report type: Standard column balances Period + Opening balances 2021/03/01 / 2022/02/28

Code	Name	Trial balance		Income statement		Balance sheet	
G010000	Sales	9,500.00	45,500.00	0.00	36,000.00	0.00	0.00
G100000	Cost of sales	20,500.00	5,500.00	15,000.00	0.00	0.00	0.00
G200000	Bank charges	45.00	0.00	45.00	0.00	0.00	0.00
G205000	Depreciation	150.00	0.00	150.00	0.00	0.00	0.00
G210010	Fuel and oil	150.00	0.00	150.00	0.00	0.00	0.00
G210020	Maintenance	810.00	0.00	810.00	0.00	0.00	0.00
G210030	Repairs	1,200.00	0.00	1,200.00	0.00	0.00	0.00
G220000	Rent	500.00	0.00	500.00	0.00	0.00	0.00
G230000	Stationery	240.00	0.00	240.00	0.00	0.00	0.00
G505000	Capital	0.00	16,500.00	0.00	0.00	0.00	16,500.00
G510000	Retained income	0.00	4,200.00	0.00	0.00	0.00	4,200.00
G600010	Furniture fittings @ cost	4,807.00	0.00	0.00	0.00	4,807.00	0.00
G600020	Furniture fittings -Acc. deprec.	0.00	350.00	0.00	0.00	0.00	350.00
G610010	Motor vehicles @ cost	5,000.00	0.00	0.00	0.00	5,000.00	0.00
G610020	Motor vehicles -Accum. depreciation	0.00	600.00	0.00	0.00	0.00	600.00
G700000	Debtors control	54,125.00	13,925.00	0.00	0.00	40,200.00	0.00
G750000	Stock control	20,500.00	27,000.00	0.00	0.00	0.00	6,500.00
B810000	ABC - Bank	11,193.00	5,070.00	0.00	0.00	6,123.00	0.00
B820000	Petty cash	200.00	56.00	0.00	0.00	144.00	0.00
T860010	Output VAT - 15%	1,425.00	6,925.00	0.00	0.00	0.00	5,500.00
T860020	Input VAT - Standard rate -15%	2,136.00	975.00	0.00	0.00	1,161.00	0.00
T860030	Input VAT - Capital goods -15%	120.00	0.00	0.00	0.00	120.00	0.00
G900000	Creditors control	10,525.00	16,525.00	0.00	0.00	0.00	6,000.00
	Net Profit/Loss			17,905.00	0	0	17,905.00
	Totals	143,126.00	143,126.00	36,000.00	36,000.00	57,555.00	57,555.00

To save the Standard column balances report *as a PDF file:*

1. *On the "Reportman print preview" screen, select Save (Ctrl+S)* *– This will launch the "Save metafile as" screen.*
2. *Select the directory (folder) where you need to save this file, if necessary.*
3. *Enter a file name.*
4. *Select the "PDF File – compressed" default file type.*
5. *Click Save.*

Spreadsheet example : Standard column balances

To create a Standard column balances - Export file:

1. Click on the Export button. This will launch the "*Save as*" screen.



2. Select the folder in which you wish to save the file.

3. The default file name will be "*Export.txt*". Overtype this with your own name.

> *If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.*
>
> *Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:*
>
> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

4. Click on the Save button.

5. This will automatically open (launch) the file in your system's default text editor program associated with value text file type.



Export-standard-column-balances.txt

	A	B	C	D	E	F	G	H
1	Created on	2022/05/22 17:02						
2	Per period	2021/03/01 / 2022/02/28	Groups	Reporting group 1	Report type	Standard column balances		
3	Per period	Year	Budget	FALSE				
4	Ignore zero balances	TRUE	Include opening balances	TRUE				
5	Viewer Debtors / Creditors	FALSE	Opening balances only	FALSE				
6								
7	Code	Name	Trial balance		Income statement		Balance sheet	
8	G010000	Sales	9,500.00	45,500.00	0	36,000.00	0	0
9	G100000	Cost of sales	20,500.00	5,500.00	15,000.00	0	0	0
10	G200000	Bank charges	45	0	45	0	0	0
11	G205000	Depreciation	150	0	150	0	0	0
12	G210010	Fuel and oil	150	0	150	0	0	0
13	G210020	Maintenance	810	0	810	0	0	0
14	G210030	Repairs	1,200.00	0	1,200.00	0	0	0
15	G220000	Rent	500	0	500	0	0	0
16	G230000	Stationery	240	0	240	0	0	0
17	G505000	Capital	0	16,500.00	0	0	0	16,500.00
18	G510000	Retained income	0	4,200.00	0	0	0	4,200.00
19	G600010	Furniture fittings @ cost	4,807.00	0	0	0	4,807.00	0
20	G600020	Furniture fittings -Acc. deprec.	0	350	0	0	0	350
21	G610010	Motor vehicles @ cost	5,000.00	0	0	0	5,000.00	0
22	G610020	Motor vehicles -Accum. depreciat	0	600	0	0	0	600
23	G700000	Debtors control	54,125.00	13,925.00	0	0	40,200.00	0
24	G750000	Stock control	20,500.00	27,000.00	0	0	0	6,500.00
25	B810000	ABC - Bank	11,193.00	5,070.00	0	0	6,123.00	0
26	B820000	Petty cash	200	56	0	0	144	0
27	T860010	Output VAT - 15%	1,425.00	6,925.00	0	0	0	5,500.00
28	T860020	Input VAT - Standard rate -15%	2,136.00	975	0	0	1,161.00	0
29	T860030	Input VAT - Capital goods -15%	120	0	0	0	120	0
30	G900000	Creditors control	10,525.00	16,525.00	0	0	0	6,000.00
31		0	0	0	0	0	0	0
32		Net Profit/Loss	0	0	17,905.00	0	0	17,905.00
33		Totals	143,126.00	143,126.00	36,000.00	36,000.00	57,555.00	57,555.00
34								

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

Print comparative reports for the budget

You may print the Budget vs actual report in the Ledger analyser as well as a Budget vs actual - 3 periods report to compare the budget to actual totals to determine whether your targets were met and whether you underspent or overspent and whether you have generated too little income, etc.

Budget vs actual report

The Budget vs actual report will list the budget figures as well as the actual totals of posted batches and documents for selected period(s) or date(s).

This report will display the following:

1. Trial balance – The actual figures on the Trial balance - totals of transactions as posted (updated to the ledger) in batches (journals), sales documents (i.e. Invoices, Point-of-Sale Invoices and Credit notes) and purchase documents (i.e. Purchases and Supplier returns).
2. Budget – Once any budget figures are entered or edited (and saved), these figures will automatically be updated to the applicable accounts and will be available in the Ledger analyser and any reports which supports budget figures.
3. Difference – The difference amount actual trial Trial balance vs the Budget figures.
4. Percentage – The difference expressed as a percentage.

To print this report your system's digit separator symbol need to be set to a comma and the decimal symbol needs to be set as a period. See - Suystem settings - Number format.

If these settings are not set, this report will produce an error:

```
Type conversion error 'Val':Expression TRpExpression46
```

You may access your system's Regional settings from the Setup → Company info - Options tab Set Windows date format/style button or on the DateTime settings button on the Setup → System parameters (Setup ribbon).

On your system's "Region"-screen click on the Additional settings... button to launch your system's "Customize Format" screen.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Budget vs actual options

To print a budget vs actual report:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the "*Budget vs actual*" report type.



3. Per period - Select a period (Month, 2 Months, 3 Months, 4 Months, 6 Months or Year).

> *You may click on the "Free selection" tab. You may select or enter any date or dates, which you need to include the "Budget vs actual" report.*

4. Ignore zero balances - If this field is not selected, all accounts will be listed for the "*Budget vs actual*" report. If you select (tick) this field; only those accounts with balances and or budget figures, will be included in the "*Budget vs actual*" report.

5. Include opening balances - If this option is selected (ticked), it will include the opening balances of those accounts which have opening balances. If this option is not selected; the opening balances will not be included in the "*Budget vs actual*" report.

6. Opening balances only - This option will only be available if the "*Include opening balances*" option is selected. You can select (check) this option to include only the opening balances. All other balances will then be ignored.

7. Cost centre 1 and Cost centre 2 - The Cost centres (2 Groups) will only be available, if Cost centres are added in Setup → Groups on the Setup ribbon; and if activated.

8. Click on the Report button. This will build or refresh the "*Budget vs actual*" report with the selected options.

Example : Budget vs actual

An example of the "*Budget vs actual*" report type, is displayed as follows:



Code	Name	Trial balance		Budget		Difference	%
G010000	Sales	0.00	36,000.00	0.00	125,000.00	-89,000.00	28.80
G100000	Cost of sales	15,000.00	0.00	48,000.00	0.00	33,000.00	31.25
G200000	Bank charges	45.00	0.00	480.00	0.00	435.00	9.38
G205000	Depreciation	150.00	0.00	600.00	0.00	450.00	25.00
G210010	Fuel and oil	150.00	0.00	1,200.00	0.00	1,050.00	12.50
G210020	Maintenance	810.00	0.00	1,800.00	0.00	990.00	45.00
G210030	Repairs	1,200.00	0.00	2,400.00	0.00	1,200.00	50.00
G220000	Rent	500.00	0.00	6,600.00	0.00	6,100.00	7.58
G225000	Salaries and wages	0.00	0.00	6,000.00	0.00	6,000.00	100.00
G230000	Stationery	240.00	0.00	120.00	0.00	-120.00	200.00
G505000	Capital	0.00	16,500.00	0.00	0.00	16,500.00	100.00
G510000	Retained income	0.00	4,200.00	0.00	0.00	4,200.00	100.00
G600010	Furniture fittings @ cost	4,807.00	0.00	0.00	0.00	-4,807.00	100.00
G600020	Furniture fittings -Acc. deprec.	0.00	350.00	0.00	0.00	350.00	100.00
G610010	Motor vehicles @ cost	5,000.00	0.00	0.00	0.00	-5,000.00	100.00
G610020	Motor vehicles -Accum. depreciation	0.00	600.00	0.00	0.00	600.00	100.00
G700000	Debtors control	40,200.00	0.00	0.00	0.00	-40,200.00	100.00
G750000	Stock control	0.00	6,500.00	0.00	0.00	6,500.00	100.00
B810000	ABC - Bank	6,123.00	0.00	0.00	0.00	-6,123.00	100.00
B820000	Petty cash	144.00	0.00	0.00	0.00	-144.00	100.00
T860010	Output VAT - 15%	0.00	5,500.00	0.00	0.00	5,500.00	100.00
T860020	Input VAT - Standard rate -15%	1,161.00	0.00	0.00	0.00	-1,161.00	100.00
T860030	Input VAT - Capital goods -15%	120.00	0.00	0.00	0.00	-120.00	100.00
G900000	Creditors control	0.00	6,000.00	0.00	0.00	6,000.00	100.00
	Net Profit/Loss	0	17,905.00		57,800.00	-39,895.00	
	Totals		0.00		57,800.00	-57,800.00	

Buttons 7, 6, 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

If any of the budget figures needs to be changed, you may go to the Budgets option (Reports ribbon) or Setup → Accounts option on the Setup ribbon.

Printed example : Budget vs actual

Click on the Print button. The parameter screen is displayed:



Click on OK.

An example of the printed "*Budget vs actual*" (no opening balances) report, is as follows:



budvsactsimple

Budget vs actual Period + Opening balances 2021/03/01 / 2022/02/28

		Trial balance		Budget			
Code	Name	Debit	Credit	Debit	Credit	Difference	%
G010000	Sales		36,000.00		125,000.00	-89,000.00	28.80
G100000	Cost of sales	15,000.00		48,000.00		33,000.00	31.25
G200000	Bank charges	45.00		480.00		435.00	9.38
G205000	Depreciation	150.00		600.00		450.00	25.00
G210010	Fuel and oil	150.00		1,200.00		1,050.00	12.50
G210020	Maintenance	810.00		1,800.00		990.00	45.00
G210030	Repairs	1,200.00		2,400.00		1,200.00	50.00
G220000	Rent	500.00		6,600.00		6,100.00	7.58
G225000	Salaries and wages			6,000.00		6,000.00	100.00
G230000	Stationery	240.00		120.00		-120.00	200.00
G505000	Capital		16,500.00			16,500.00	100.00
G510000	Retained income		4,200.00			4,200.00	100.00
G600010	Furniture fittings @ cost	4,807.00				-4,807.00	100.00
G600020	Furniture fittings -Acc. deprec.		350.00			350.00	100.00
G610010	Motor vehicles @ cost	5,000.00				-5,000.00	100.00
G610020	Motor vehicles -Accum. depreciation		600.00			600.00	100.00
G700000	Debtors control	40,200.00				-40,200.00	100.00
G750000	Stock control		6,500.00			6,500.00	100.00
B810000	ABC - Bank	6,123.00				-6,123.00	100.00
B820000	Petty cash	144.00				-144.00	100.00
T860010	Output VAT - 15%		5,500.00			5,500.00	100.00
T860020	Input VAT - Standard rate -15%	1,161.00				-1,161.00	100.00
T860030	Input VAT - Capital goods -15%	120.00				-120.00	100.00
G900000	Creditors control		6,000.00			6,000.00	100.00
	Totals	**75,650.00**	**75,650.00**	**67,200.00**	**125,000.00**	**-57,800.00**	
		0.00	17,905.00	0.00	57,800.00		
		Net profit		**Net profit**			

To save the ***Budget vs actual report*** *as a PDF file:*

1. *On the "Reportman print preview" screen, select Save (Ctrl+S)* *– This will launch the "Save metafile as" screen.*
2. *Select the directory (folder) where you need to save this file, if necessary.*
3. *Enter a file name.*
4. *Select the "PDF File – compressed" default file type.*
5. *Click Save.*

Spreadsheet example : Budget vs actual

To create a Budget vs actual - Export file:

1. Click on the Export button. This will launch the "*Save as*" screen.



2. Select the folder in which you wish to save the file.
3. The default file name will be "*Export.txt*". Overtype this with your own name.

If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.

Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

4. Click on the Save button.

5. This will automatically open (launch) the file in your system's default text editor program associated with value text file type.



	A	B	C	D	E	F	G	H
1	Created on	2022/05/22 17:17						
2	Per period	2021/03/01 / 2022/02/28	Groups	Reporting group 1	Report type	Budget vs actual		
3	Per period	Year	Budget	FALSE				
4	Ignore zero balances	TRUE	Include opening balances	TRUE				
5	Viewer Debtors / Creditors	FALSE	Opening balances only	FALSE				
6								
7	Code	Name	Trial balance		Budget		Difference	%
8	G010000	Sales	0	36,000.00	0	125,000.00	-89,000.00	28.8
9	G100000	Cost of sales	15,000.00	0	48,000.00	0	33,000.00	31.25
10	G200000	Bank charges	45	0	480	0	435	9.38
11	G205000	Depreciation	150	0	600	0	450	25
12	G210010	Fuel and oil	150	0	1,200.00	0	1,050.00	12.5
13	G210020	Maintenance	810	0	1,800.00	0	990	45
14	G210030	Repairs	1,200.00	0	2,400.00	0	1,200.00	50
15	G220000	Rent	500	0	6,600.00	0	6,100.00	7.58
16	G225000	Salaries and wages	0	0	6,000.00	0	6,000.00	100
17	G230000	Stationery	240	0	120	0	-120	200
18	G505000	Capital	0	16,500.00	0	0	16,500.00	100
19	G510000	Retained income	0	4,200.00	0	0	4,200.00	100
20	G600010	Furniture fittings @ cost	4,807.00	0	0	0	-4,807.00	100
21	G600020	Furniture fittings -Acc. deprec.	0	350	0	0	350	100
22	G610010	Motor vehicles @ cost	5,000.00	0	0	0	-5,000.00	100
23	G610020	Motor vehicles -Accum. depreciation	0	600	0	0	600	100
24	G700000	Debtors control	40,200.00	0	0	0	-40,200.00	100
25	G750000	Stock control	0	6,500.00	0	0	6,500.00	100
26	B810000	ABC - Bank	6,123.00	0	0	0	-6,123.00	100
27	B820000	Petty cash	144	0	0	0	-144	100
28	T860010	Output VAT - 15%	0	5,500.00	0	0	5,500.00	100
29	T860020	Input VAT - Standard rate -15%	1,161.00	0	0	0	-1,161.00	100
30	T860030	Input VAT - Capital goods -15%	120	0	0	0	-120	100
31	G900000	Creditors control	0	6,000.00	0	0	6,000.00	100
32		0	0	0	0	0	0	0
33		Net Profit/Loss	0	17,905.00	0	57,800.00	-39,895.00	0
34		Totals	0	0	0	57,800.00	-57,800.00	0

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Ledger analyser - This year vs last year

This report will display the comparative figures for up to 2 financial years or the same periods (a specific month, 2 months, 3 months, 4 months, 6 months or a year).

To print this report your system's digit separator symbol need to be set to a comma and the decimal symbol needs to be set as a period. See - Suystem settings - Number format.

If these settings are not set, this report will produce an error:

Type conversion error 'Val':Expression TRpExpression46

You may access your system's Regional settings from the Setup → Company info - Options tab Set Windows date format/style button or on the DateTime settings button on the Setup → System parameters (Setup ribbon).

On your system's "Region"-screen click on the Additional settings... button to launch your system's "Customize Format" screen.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

This year vs last year options

To print a This year vs last year report:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the "*This year vs last year*" report type.



3. Per period - Select a period (Month, 2 Months, 3 Months, 4 Months, 6 Months or Year).

You may click on the "Free selection" tab. You may select or enter any date or dates, which you need to include the "This year vs last year" report.

4. Ignore zero balances - If this field is not selected, all accounts will be listed for the "*This year vs last year*" report. If you select (tick) this field; only those accounts with balances, will be included in the "*This year vs last year*" report.
5. Include opening balances - If this option is selected (ticked), it will include the opening balances of those accounts which have opening balances. If this option is not selected; the opening balances will not be included in the "*This year vs last year*" report.
6. Opening balances only - This option will only be available if the "*Include opening balances*" option is selected. You can select (check) this option to include only the opening balances. All other balances will then be ignored.
7. Cost centre 1 and Cost centre 2 - The Cost centres (2 Groups) will only be available, if Cost centres are added in Groups on the Setup ribbon; and if activated.
8. Click on the Report button. This will build or refresh the "*This year vs last year*" report with the selected options.

Example : This year vs last year

An example of the "*This year vs last year"* report type, is displayed as follows:



Code	Name	D 2021/03/01	C 2022/02/28	D 2020/03/01	C 2021/02/28	Difference	%
G010000	Sales	0.00	36,000.00	0.00	0.00	36,000.00	100.00
G100000	Cost of sales	15,000.00	0.00	0.00	0.00	-15,000.00	100.00
G200000	Bank charges	45.00	0.00	0.00	0.00	-45.00	100.00
G205000	Depreciation	150.00	0.00	0.00	0.00	-150.00	100.00
G210010	Fuel and oil	150.00	0.00	0.00	0.00	-150.00	100.00
G210020	Maintenance	810.00	0.00	0.00	0.00	-810.00	100.00
G210030	Repairs	1,200.00	0.00	0.00	0.00	-1,200.00	100.00
G220000	Rent	500.00	0.00	0.00	0.00	-500.00	100.00
G230000	Stationery	240.00	0.00	0.00	0.00	-240.00	100.00
G505000	Capital	0.00	16,500.00	0.00	11,500.00	5,000.00	143.48
G510000	Retained income	0.00	4,200.00	0.00	0.00	4,200.00	100.00
G600010	Furniture fittings @ cost	4,807.00	0.00	1,007.00	0.00	-3,800.00	477.36
G600020	Furniture fittings -Acc. deprec.	0.00	350.00	0.00	300.00	50.00	116.67
G610010	Motor vehicles @ cost	5,000.00	0.00	5,000.00	0.00	0.00	100.00
G610020	Motor vehicles -Accum. depreciation	0.00	600.00	0.00	500.00	100.00	120.00
G700000	Debtors control	40,200.00	0.00	0.00	0.00	-40,200.00	100.00
G750000	Stock control	0.00	6,500.00	6,500.00	0.00	13,000.00	-100.00
B810000	ABC - Bank	6,123.00	0.00	3,193.00	0.00	-2,930.00	191.76
B820000	Petty cash	144.00	0.00	100.00	0.00	-44.00	144.00
T860010	Output VAT - 15%	0.00	5,500.00	0.00	100.00	5,400.00	5,500.00
T860020	Input VAT - Standard rate -15%	1,161.00	0.00	0.00	0.00	-1,161.00	100.00
T860030	Input VAT - Capital goods -15%	120.00	0.00	0.00	0.00	-120.00	100.00
G900000	Creditors control	0.00	6,000.00	0.00	0.00	6,000.00	100.00
	Net Profit/Loss	0	17,905.00		0.00	17,905.00	
	Totals		0.00	3,400.00		3,400.00	

Buttons 7, 6, 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

Printed example : This year vs last year

Click on the Print button. The parameter screen is displayed:



Click on OK.

An example of the printed "*This year vs last year*" (no opening balances) report, is as follows:



		D 2021/03/01		D 2020/03/01			
Code	Name	Debit	Credit	Debit	Credit	Difference	%
G010000	Sales		36,000.00			36,000.00	100.00
G100000	Cost of sales	15,000.00				-15,000.00	100.00
G200000	Bank charges	45.00				-45.00	100.00
G205000	Depreciation	150.00				-150.00	100.00
G210010	Fuel and oil	150.00				-150.00	100.00
G210020	Maintenance	810.00				-810.00	100.00
G210030	Repairs	1,200.00				-1,200.00	100.00
G220000	Rent	500.00				-500.00	100.00
G230000	Stationery	240.00				-240.00	100.00
G505000	Capital		16,500.00		11,500.00	5,000.00	143.48
G510000	Retained income		4,200.00			4,200.00	100.00
G600010	Furniture fittings @ cost	4,807.00		1,007.00		-3,800.00	477.36
G600020	Furniture fittings -Acc. deprec.		350.00		300.00	50.00	116.67
G610010	Motor vehicles @ cost	5,000.00		5,000.00			100.00
G610020	Motor vehicles -Accum. depreciation		600.00		500.00	100.00	120.00
G700000	Debtors control	40,200.00				-40,200.00	100.00
G750000	Stock control		6,500.00	6,500.00		13,000.00	-100.0
B810000	ABC - Bank	6,123.00		3,193.00		-2,930.00	191.76
B820000	Petty cash	144.00		100.00		-44.00	144.00
T860010	Output VAT - 15%		5,500.00		100.00	5,400.00	5,500.
T860020	Input VAT - Standard rate -15%	1,161.00				-1,161.00	100.00
T860030	Input VAT - Capital goods -15%	120.00				-120.00	100.00
G900000	Creditors control		6,000.00			6,000.00	100.00
	Totals	75,650.00	75,650.00	15,800.00	12,400.00	3,400.00	
		0.00	17,905.00	0.00	0.00		
		Net profit		Net profit			

To save the This year vs last year report as a PDF file:

1. *On the "Reportman print preview" screen, select Save (Ctrl+S)* *– This will launch the "Save metafile as" screen.*
2. *Select the directory (folder) where you need to save this file, if necessary.*
3. *Enter a file name.*
4. *Select the "PDF File – compressed" default file type.*
5. *Click Save.*

Spreadsheet example : This year vs last year

To create a This year vs last year - Export file:

1. Click on the Export button. This will launch the "*Save as*" screen.



2. Select the folder in which you wish to save the file.
3. The default file name will be "*Export.txt*". Overtype this with your own name.

If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.

Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

4. Click on the Save button.

5. This will automatically open (launch) the file in your system's default text editor program associated with value text file type.



	A	B	C	D	E	F	G	H
1	Created on	2022/05/22 17:27						
2	Per period	2021/03/01 / 2022/02/28	Groups	Reporting group 1	Report type	This year vs last year		
3	Per period	Year	Budget	FALSE				
4	Ignore zero balances	TRUE	Include opening balances	TRUE				
5	Viewer Debtors / Creditors	FALSE	Opening balances only	FALSE				
6								
7	Code	Name	D 2021/03/01	C 2022/02/28	D 2020/03/01	C 2021/02/28	Difference	%
8	G010000	Sales	0	36,000.00	0	0	36,000.00	100
9	G100000	Cost of sales	15,000.00	0	0	0	-15,000.00	100
10	G200000	Bank charges	45	0	0	0	-45	100
11	G205000	Depreciation	150	0	0	0	-150	100
12	G210010	Fuel and oil	150	0	0	0	-150	100
13	G210020	Maintenance	810	0	0	0	-810	100
14	G210030	Repairs	1,200.00	0	0	0	-1,200.00	100
15	G220000	Rent	500	0	0	0	-500	100
16	G230000	Stationery	240	0	0	0	-240	100
17	G505000	Capital	0	16,500.00	0	11,500.00	5,000.00	143.48
18	G510000	Retained income	0	4,200.00	0	0	4,200.00	100
19	G600010	Furniture fittings @ cost	4,807.00	0	1,007.00	0	-3,800.00	477.36
20	G600020	Furniture fittings -Acc. deprec.	0	350	0	300	50	116.67
21	G610010	Motor vehicles @ cost	5,000.00	0	5,000.00	0	0	100
22	G610020	Motor vehicles -Accum. depreciatio	0	600	0	500	100	120
23	G700000	Debtors control	40,200.00	0	0	0	-40,200.00	100
24	G750000	Stock control	0	6,500.00	6,500.00	0	13,000.00	-100
25	B810000	ABC - Bank	6,123.00	0	3,193.00	0	-2,930.00	191.76
26	B820000	Petty cash	144	0	100	0	-44	144
27	T860010	Output VAT - 15%	0	5,500.00	0	100	5,400.00	5,500.00
28	T860020	Input VAT - Standard rate -15%	1,161.00	0	0	0	-1,161.00	100
29	T860030	Input VAT - Capital goods -15%	120	0	0	0	-120	100
30	G900000	Creditors control	0	6,000.00	0	0	6,000.00	100
31		0	0	0	0	0	0	0
32		Net Profit/Loss	0	17,905.00	0	0	17,905.00	0
33		Totals	0	0	3,400.00	0	3,400.00	0
34								

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

Ledger analyser - Unposted batches

You may view, print and export a Trial balance, Income statement and Balance sheet for unposted as well as posted batches from the Batch entry (F2) context menu.

Unposted Invoices, Credit notes, Purchases and Supplier returns is not included in this report.

You may go to the Input → Checking unposted items (Default ribbon) to view a list of unposted transactions in batches and documents.

To print a Trial balance, Income statement or Balance sheet for unposted batches:

1. On the Default ribbon, select Batch entry (F2).

2. Right-click and select "*Trial balance*" from the context menu.



3. A confirmation message is displayed:

Unposted only?

4. Click on the Yes button.

If you click on the No button, the Trial balance, Income statement and Balance sheet for posted batches (excluding unposted documents) will be printed. These reports, as well as others, may be

printed in the Ledger analyser 1 or Ledger analyser 2 on the Reports ribbon.



When this Trial balance is launched, the Print button will not be displayed. To initialise the Print button, select Income statement or Balance sheet and then Trial balance.

If "Unposted only?" is selected, the T-Account viewer and the Pivot options will not have any data to display.

4. Click on the Print button. Only those unposted transactions (excluding unposted documents) will be printed.

Page 1 -



	Totals Debit	Credit	Debit	Credit
REPORTING GROUP ROOT				
Income				
010000 Sales				5,000.00
Expenses				
210000 Motor vehicle expenses	**1,160.00**			
210010 Fuel and oil			150.00	
210020 Maintenance			410.00	
210030 Repairs			600.00	
220000 Rent			500.00	
230000 Stationery			240.00	
Capital				
505000 Capital				16,500.00
510000 Retained income				4,200.00
Current liabilities				
860000 VAT - Control - 15%		**244.00**		
860010 Output VAT - 15%				850.00
860020 Input VAT - Standard rate -15%			486.00	
860030 Input VAT - Capital goods -15%			120.00	
900000 Creditors control				
Fixed assets				
600000 Furniture & fittings - Net value	**3,007.00**			
600010 Furniture & fittings @ cost			3,307.00	
600020 Furniture & fittings -Acc. deprec.				300.00
610000 Motor vehicles - Net value	**4,500.00**			
610010 Motor vehicles @ cost			5,000.00	
610020 Motor vehicles -Accum. depreciation				500.00
Current assets				

Page 2 -



	Totals Debit	Credit	Debit	Credit
700000 Debtors control				
750000 Stock control			6,500.00	
810000 ABC - Bank			8,468.00	
820000 Petty cash			144.00	
		Totals	**25,925.00**	**27,350.00**
		Net profit	**1,900.00**	**5,000.00**
				3,100.00

Created with the Standard Edition of HelpNDoc: Effortlessly Create Encrypted, Password-Protected PDFs

Ledger analyser - Column balances - Spreadsheets

The column balances report types will list the transactions of accounts for each period of Last year and This year in a spreadsheet format.

You may select an account and double-click on any period. This will launch the T-Account viewer with a list of all the transactions for the selected period. You may be print and/or export the transactions.

The following six (6) column balances report types is available:

1. Column balances - Lists all ledger account balances in a spreadsheet view. These are the ledger accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).
2. Column balances debtors - Lists the balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.
3. Column balances creditors - Lists the balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.
4. Column balances D/C - Lists all debit and credit ledger account balances in a spreadsheet view. These are the accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).
5. Column balances debtors D/C - Lists the debit and credit account balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.
6. Column balances creditors D/C - Lists all debit and credit balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.

You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

You may also click on the Export button of the T-Account viewer to export the transactions to a

spreadsheet.

You may select to save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Column balances

The Column balances report type will list the net balances (debits *minus* credits) for the general ledger accounts (i.e. Income, expenses, Bank accounts, Tax accounts and other ledger accounts reported in the Trial balance.

The Column balances report type allows you to list all ledger accounts in your chart of accounts, or only those accounts with balances.

This report type cannot be printed but can be exported to a spreadsheet (e.g. Microsoft Excel or OpenOfficeCalc / LibreOffice Calc, etc.).

You may generate the transactions in a spreadsheet format in the Column balances or the Column balances D/C report types on the Ledger analyser.

You may also generate the transactions in a spreadsheet format in the Column balances D/C report types on the Ledger analyser. These transaction totals may be exported to an "Export.txt file and opened in a spreadsheet.

You may select an account and double-click on a specific period to list and view the transaction details in the T-Account viewer. You may be print or export the transactions.

This report type will list all General ledger accounts (including disabled accounts) by account code.

This spreadsheet only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this spreadsheet.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Example : Column balances

The Column balances report type will list the net balances (debits *minus* credits) for the general ledger accounts (i.e. Income, expenses, Bank accounts, Tax accounts and other ledger accounts reported in the Trial balance.



Name	Opening last year	March	April	May	June	July	August	September	October	November	December	January	February		Period Total	End last year	Opening This year	March	April	May
G010000 Sales		-10,000.00	-7,500.00	-2,000.00	-16,500.00										-36,000.00	-36,000.00				
G100000 Cost of sales			4,500.00	500.00	10,000.00										15,000.00	15,000.00				
G200000 Bank charges		45.00													45.00	45.00				
G205000 Depreciation		150.00													150.00	150.00				
G210010 Fuel and oil		150.00													150.00	150.00				
G210020 Maintenance		810.00													810.00	810.00				
G210030 Repairs		1,200.00													1,200.00	1,200.00				
G220000 Rent		500.00													500.00	500.00				
G230000 Stationery		240.00													240.00	240.00				
G505000 Capital	-11,500.00	-5,000.00													-5,000.00	-16,500.00	-16,500.00			
G510000 Retained income	-4,200.00														0.00	-4,200.00	-22,105.00			
G600010 Furniture fittings @ cost	1,007.00	3,800.00													3,800.00	4,807.00	4,807.00			
G600020 Furniture fittings -Acc. deprec.	-300.00	-50.00													-50.00	-350.00	-350.00			
G610010 Motor vehicles @ cost	5,000.00														0.00	5,000.00	5,000.00			
G610020 Motor vehicles -Accum. depreciation	-500.00	-100.00													-100.00	-600.00	-600.00			
G700000 Debtors control	1,800.00	8,500.00	8,625.00	2,300.00	18,975.00										38,400.00	40,200.00	40,200.00			
G750000 Stock control	6,500.00		-1,000.00	-500.00	-11,500.00										-13,000.00	-6,500.00	-6,500.00			
B810000 ABC - Bank	3,193.00	5,230.00			-2,300.00										2,930.00	6,123.00	6,123.00			
B820000 Petty cash	100.00	44.00													44.00	144.00	144.00			
T860010 Output VAT - 15%	-100.00	-1,500.00	-1,125.00	-300.00	-2,475.00										-5,400.00	-5,500.00	-5,500.00			
T860020 Input VAT - Standard rate -15%		861.00	525.00		-225.00										1,161.00	1,161.00	1,161.00			
T860030 Input VAT - Capital goods -15%		120.00													120.00	120.00	120.00			
G900000 Creditors control	-1,000.00	-5,000.00	-4,025.00		4,025.00										-5,000.00	-6,000.00	-6,000.00			

7 6 5 4 3 2 1

Buttons 7, 6, 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

Pivot – View, filter and analyse your report on screen, view graphs, customise datasets and types of graphs.

Zoom in / Zoom out + / - buttons added to resize (increase / decrease the font) the reports (i.e. Trial balance, Balance sheet and Income statement) on screen. This is not implemented for the Column balances report types.

When you Export these Column balances report types, you may use the zoom features of your spreadsheet app.

If the "*Ignore zero balances"* field is selected (ticked); it will list only those accounts with balances.

If the "Ignore zero balances" field is not selected (not ticked); it will all accounts with balances as well as zero balances.

This report type will list all General ledger accounts (or with balances only, if the "*Ignore zero balances"* field is not selected (not ticked)) in the following columns:

1. Opening Balance Last Year - Period -1
2. Periods - This is last year periods - usually 1 to 12 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
3. Period Total - The total of the period totals for last year.
4. End Last Year - Opening Balance Last Year total and the Period Total.
5. Opening This Year - Period 0 - This should be the same as the End Last Year totals.
6. Periods - This is the current year (this year) periods - usually 14 to 25 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
7. Period Total - The total of the period totals for this year.
8. End this year - Opening Balance This Year total and the Period Total (This Year).

Export to Spreadsheet

To create an export file:

1. Click the Export button. This will launch the "*Save As*" screen:



2. Select the folder in which you wish to save the file and enter a file name.

If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.

If an existing exported file is opened, and you are trying to open a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "D:\Export\Export.txt". The process cannot access the file because it is being used by another process.

3. Select the file type. Text files (*.txt) is the default; or select CSV files (*.csv) (Comma Separated Values).

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, Apache OpenOffice, LibreOffice, Ultra Office, etc.). You may need to set the "Separator Options - Separated by" on the "Text Import" screen to "Tab" and "Trim spaces".*

4. Click on the Save button. This will automatically open (launch) the exported file in the program associated with the selected file type.

Export file opened in Microsoft Excel

In this example, the exported "*Export.txt*" file is automatically opened in "*Microsoft Excel*":



	A	B	C	D	E	F	G	H	I	J	K	L
1	Company name:	Handyman Hardware Store										
2	Address	27 Olifants Road										
3		Emmarentia										
4		Johannesburg										
5		2195										
6	Phone:	(011) 310-1390										
7	Date of report	2022/05/23 09:53										
8	Contra Accounts	Batch no.	Cost centre 2	Cost centre 1	Account	Name	Alias	Description	Reference	Date	Debit	Credit
9	G010000 Sales,T860010 Output VAT - 15%	10059	Empty	Empty	D1ABGRE	Mr. AB Green	IN000011	Invoice /D-101	IN000011	2021/06/05	1150	
10	G010000 Sales,T860010 Output VAT - 15%	10061	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000012	Invoice /C-102	IN000012	2021/06/07	3450	
11	G010000 Sales,T860010 Output VAT - 15%	10063	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000013	Invoice /C-103	IN000013	2021/06/10	1725	
12	G010000 Sales,T860010 Output VAT - 15%	10065	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000014	Invoice /D-102	IN000014	2021/06/12	2300	
13	G010000 Sales,T860010 Output VAT - 15%	10067	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000015	Invoice /D-101	IN000015	2021/06/15	1150	
14	G010000 Sales,T860010 Output VAT - 15%	10069	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000016	Invoice /C-102	IN000016	2021/06/17	3450	
15	G010000 Sales,T860010 Output VAT - 15%	10071	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000017	Invoice /C-103	IN000017	2021/06/20	2875	
16	G010000 Sales,T860010 Output VAT - 15%	10088	Empty	Empty	D1ROGSM	Mr. Roger Smith	CR000002	Credit note /D-102	CR000002	2021/06/22		2300
17	G010000 Sales,T860010 Output VAT - 15%	10073	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000018	Invoice /D-102	IN000018	2021/06/24	2300	
18	G010000 Sales,T860010 Output VAT - 15%	10086	Empty	Empty	D1ABGRE	Mr. AB Green	CR000001	Credit note /D-101	CR000001	2021/06/30		5750
19	G010000 Sales,T860010 Output VAT - 15%	10090	Empty	Empty	D1ABGRE	Mr. AB Green	CR000003	Credit note /C-103	CR000003	2021/06/30		2875
20	G010000 Sales,T860010 Output VAT - 15%	10075	Empty	Empty	D1ABGRE	Mr. AB Green	IN000019	Invoice /D-101	IN000019	2021/06/30	5750	
21	G010000 Sales,T860010 Output VAT - 15%	10077	Empty	Empty	D1ABGRE	Mr. AB Green	IN000020	Invoice /C-103	IN000020	2021/06/30	5750	

Export button

You may save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

View transactions in T-Account viewer

In this example, the T-Account viewer is launched by a double-click in the month (accounting period) " *June*" in the "*G700000 Debtors control*" account:



Show contra - By default this option is not selected.

If the Show contra is selected, it will insert (add) the Account code and Description before the batch id (batch number).

The Contra accounts will not print on the T-Account viewer ("ledgerdetail") report; but will be included in the Export file when you click on the Export button of the T-Account viewer.

Print transactions in T-Account viewer

Click on the Print button to print the selection in the T-Account viewer.



Export transactions in T-Account viewer

You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

You may also click on the Export button of the T-Account viewer to export the transactions to a spreadsheet.

You may select to save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your*

system's default spreadsheet program associated with Comma Separated Value file type (.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*



	A	B	C	D	E	F	G	H	I	J	K	L
1	Company name:	Handyman Hardware Store										
2	Address	27 Olifants Road										
3		Emmarentia										
4		Johannesburg										
5		2195										
6	Phone:	(011) 310-1390										
7	Date of report	2022/05/21 04:51										
8	Contra Accounts	Batch no.	Cost centre 2	Cost centre 1	Account	Name	Alias	Description	Reference	Date	Debit	Credit
9	G010000 Sales,T860010 Output VAT - 15%	10059	Empty	Empty	D1ABGRE	Mr. AB Green	IN000011	Invoice /D-101	IN000011	2021/06/05	1150	
10	G010000 Sales,T860010 Output VAT - 15%	10061	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000012	Invoice /C-102	IN000012	2021/06/07	3450	
11	G010000 Sales,T860010 Output VAT - 15%	10063	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000013	Invoice /C-103	IN000013	2021/06/10	1725	
12	G010000 Sales,T860010 Output VAT - 15%	10065	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000014	Invoice /D-102	IN000014	2021/06/12	2300	
13	G010000 Sales,T860010 Output VAT - 15%	10067	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000015	Invoice /D-101	IN000015	2021/06/15	1150	
14	G010000 Sales,T860010 Output VAT - 15%	10069	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000016	Invoice /C-102	IN000016	2021/06/17	3450	
15	G010000 Sales,T860010 Output VAT - 15%	10071	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000017	Invoice /C-103	IN000017	2021/06/20	2875	
16	G010000 Sales,T860010 Output VAT - 15%	10088	Empty	Empty	D1ROGSM	Mr. Roger Smith	CR000002	Credit note /D-102	CR000002	2021/06/22		2300
17	G010000 Sales,T860010 Output VAT - 15%	10073	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000018	Invoice /D-102	IN000018	2021/06/24	2300	
18	G010000 Sales,T860010 Output VAT - 15%	10086	Empty	Empty	D1ABGRE	Mr. AB Green	CR000001	Credit note /D-101	CR000001	2021/06/30		5750
19	G010000 Sales,T860010 Output VAT - 15%	10090	Empty	Empty	D1ABGRE	Mr. AB Green	CR000003	Credit note /C-103	CR000003	2021/06/30		2875
20	G010000 Sales,T860010 Output VAT - 15%	10075	Empty	Empty	D1ABGRE	Mr. AB Green	IN000019	Invoice /D-101	IN000019	2021/06/30	5750	
21	G010000 Sales,T860010 Output VAT - 15%	10077	Empty	Empty	D1ABGRE	Mr. AB Green	IN000020	Invoice /C-103	IN000020	2021/06/30	5750	
22												

Show contra - By default this option is not selected.

If the Show contra is selected, it will insert (add) the Account code and Description before the batch id (batch number).

The Contra accounts will not print on the T-Account viewer ("ledgerdetail") report; but will be included in the Export file when you click on the Export button of the T-Account viewer.

Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Column balances - Debit / Credit

The Column balances report type list the debit and credit balances of the transactions totals for the general ledger accounts (i.e. Income, expenses, Bank accounts, Tax accounts and other ledger accounts reported in the Trial balance.

The Column balances report type allows you to list all ledger accounts in your chart of accounts, or only those accounts with balances.

This report type cannot be printed but can be exported to a spreadsheet (e.g. OpenOfficeCalc /

LibreOffice Calc or Microsoft Excel, etc.).

You may generate the transactions in a spreadsheet format in the Column balances or the Column balances D/C report types on the Ledger analyser.

These transaction totals may be exported to an "*Export.txt*" file or "*Export.csv*" and opened in a spreadsheet.

This spreadsheet only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this spreadsheet.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Example : Column balances D/C

The Column balances D/C report type will list the debit and credit balances for the general ledger accounts (i.e. Income, expenses, Bank accounts, Tax accounts and other ledger accounts reported in the Trial balance.



Name	Opening last year	March D / C	April D / C	May D / C	June D / C	July D / C	August D / C	September D / C	October D / C	November D / C	December D / C	January D / C	February D / C		Period Total	End last year	Opening
G010000 Sales		0.00 / 10,000.00	0.00 / 7,500.00	0.00 / 2,000.00	9,500.00 / 26,000.00										-36,000.00	-36,000.00	
G100000 Cost of sales			4,500.00 / 0.00	500.00 / 0.00	15,500.00 / 5,500.00										15,000.00	15,000.00	
G200000 Bank charges		45.00 / 0.00													45.00	45.00	
G205000 Depreciation		150.00 / 0.00													150.00	150.00	
G210010 Fuel and oil		150.00 / 0.00													150.00	150.00	
G210020 Maintenance		810.00 / 0.00													810.00	810.00	
G210030 Repairs		1,200.00 / 0.00													1,200.00	1,200.00	
G220000 Rent		500.00 / 0.00													500.00	500.00	
G230000 Stationery		240.00 / 0.00													240.00	240.00	
G505000 Capital	-11,500.00	0.00 / 5,000.00													-5,000.00	-16,500.00	-1
G510000 Retained income	-4,200.00														0.00	-4,200.00	-2
G600010 Furniture fittings @ cost	1,007.00	3,800.00 / 0.00													3,800.00	4,807.00	
G600020 Furniture fittings -Acc. deprec.	-300.00	0.00 / 50.00													-50.00	-350.00	
G610010 Motor vehicles @ cost	5,000.00														0.00	5,000.00	
G610020 Motor vehicles -Accum. depreciation	-500.00	0.00 / 100.00													-100.00	-600.00	
G700000 Debtors control	1,800.00	11,500.00 / 3,000.00	8,625.00 / 0.00	2,300.00 / 0.00	29,900.00 / 10,925.00										38,400.00	40,200.00	4
G750000 Stock control	6,500.00		3,500.00 / 4,500.00	0.00 / 500.00	10,500.00 / 22,000.00										-13,000.00	-6,500.00	
B810000 ABC - Bank	3,193.00	8,000.00 / 2,770.00			0.00 / 2,300.00										2,930.00	6,123.00	
B820000 Petty cash	100.00	100.00 / 56.00													44.00	144.00	
T860010 Output VAT - 15%	-100.00	0.00 / 1,500.00	0.00 / 1,125.00	0.00 / 300.00	1,425.00 / 3,900.00										-5,400.00	-5,500.00	
T860020 Input VAT - Standard rate -15%		861.00 / 0.00	525.00 / 0.00		750.00 / 975.00										1,161.00	1,161.00	
T860030 Input VAT - Capital goods -15%		120.00 / 0.00													120.00	120.00	
G900000 Creditors control	-1,000.00	750.00 / 5,750.00	0.00 / 4,025.00		9,775.00 / 5,750.00										-5,000.00	-6,000.00	

6 5 4 3 2 1

Buttons 6, 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

This report type will list all General ledger accounts (or with balances only), if the "*Ignore zero balances*" field is not selected (not ticked)).

This report cannot be printed but can be exported to a spreadsheet (e.g. OpenOfficeCalc / LibreOffice Calc or Microsoft Excel, etc.).

The periods is as follows:

- Opening Last Year - The totals for opening balances of the previous year.
- Last Year Periods 1 to 12 - the totals of transactions entered or posted to the previous year.
- Period Total - Total for each period (Period 1 -12).
- End Last Year - Total for Last Year Opening Balances and the totals for each period (Period 1 -12).
- Opening Balance This Year - This should be the same as the Total for Last Year.
- Period Total - Total for each period (Period 13 -25).
- End Last Year - Total for This Year Opening Balances and the totals for each period (Period 13 -25).

View transactions in T-Account viewer

In this example, the T-Account viewer is launched by a double-click in the month (accounting period) " *June*" in the "*G700000 Debtors control*" account:



Print transactions in T-Account viewer

Click on the Print button to print the selection in the T-Account viewer.



Export transactions in T-Account viewer



	A	B	C	D	E	F	G	H	I	J	K	L
1	Company name:	Handyman Hardware Store										
2	Address	27 Olifants Road										
3		Emmarentia										
4		Johannesburg										
5		2195										
6	Phone:	(011) 310-1390										
7	Date of report	2022/05/23 09:34										
8	Contra Accounts	Batch no.	Cost centre 2	Cost centre 1	Account	Name	Alias	Description	Reference	Date	Debit	Credit
9	G010000 Sales,T860010 Output VAT - 15%	10059	Empty	Empty	D1ABGRE	Mr. AB Green	IN000011	Invoice /D-101	IN000011	2021/06/05	1150	
10	G010000 Sales,T860010 Output VAT - 15%	10061	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000012	Invoice /C-102	IN000012	2021/06/07	3450	
11	G010000 Sales,T860010 Output VAT - 15%	10063	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000013	Invoice /C-103	IN000013	2021/06/10	1725	
12	G010000 Sales,T860010 Output VAT - 15%	10065	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000014	Invoice /D-102	IN000014	2021/06/12	2300	
13	G010000 Sales,T860010 Output VAT - 15%	10067	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000015	Invoice /D-101	IN000015	2021/06/15	1150	
14	G010000 Sales,T860010 Output VAT - 15%	10069	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000016	Invoice /C-102	IN000016	2021/06/17	3450	
15	G010000 Sales,T860010 Output VAT - 15%	10071	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000017	Invoice /C-103	IN000017	2021/06/20	2875	
16	G010000 Sales,T860010 Output VAT - 15%	10088	Empty	Empty	D1ROGSM	Mr. Roger Smith	CR000002	Credit note /D-102	CR000002	2021/06/22		2300
17	G010000 Sales,T860010 Output VAT - 15%	10073	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000018	Invoice /D-102	IN000018	2021/06/24	2300	
18	G010000 Sales,T860010 Output VAT - 15%	10086	Empty	Empty	D1ABGRE	Mr. AB Green	CR000001	Credit note /D-101	CR000001	2021/06/30		5750
19	G010000 Sales,T860010 Output VAT - 15%	10090	Empty	Empty	D1ABGRE	Mr. AB Green	CR000003	Credit note /C-103	CR000003	2021/06/30		2875
20	G010000 Sales,T860010 Output VAT - 15%	10075	Empty	Empty	D1ABGRE	Mr. AB Green	IN000019	Invoice /D-101	IN000019	2021/06/30	5750	
21	G010000 Sales,T860010 Output VAT - 15%	10077	Empty	Empty	D1ABGRE	Mr. AB Green	IN000020	Invoice /C-103	IN000020	2021/06/30	5750	

You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

You may also click on the Export button of the T-Account viewer to export the transactions to a spreadsheet.

You may select to save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

Created with the Standard Edition of HelpNDoc: Free Web Help generator

Column balances debtors

The Column balances debtors report type list the net balances (debits *minus* credits) of the transactions totals for the for the individual debtor (customer / client) accounts for each period.

You may select to list all debtor (customer / client) accounts, or only those accounts with balances.

This report type cannot be printed but can be exported to a spreadsheet (e.g. OpenOfficeCalc / LibreOffice Calc or Microsoft Excel, etc.).

You may generate the transactions in a spreadsheet format in the Column balances debtors or the Column balances debtors D/C report types on the Ledger analyser.

These transaction totals may be exported to an "*Export.txt*" file or "*Export.csv*" and opened in a spreadsheet.

To view the transactions for a specific debtor customer / client) account for a specific period, simply double-click on a period. The transactions will be displayed in the T-Account viewer to filter, print or export the transactions.

In addition to the transaction reports, you may also view and filter transactions on the Transactions tab of a selected debtor (customer / client) account.

This spreadsheet only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this spreadsheet.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Example : Column balances debtors



Buttons 12, 11, 10, 9, 8, 7, 6, 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

This report cannot be printed but can be exported to a spreadsheet (e.g. OpenOfficeCalc / LibreOffice Calc or Microsoft Excel, etc.).

The periods is as follows:

1. Opening Balance Last Year - Period -1
2. Periods - This is last year periods - usually 1 to 12 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
3. Period Total - The total of the period totals for last year.
4. End Last Year - Opening Balance Last Year total and the Period Total.
5. Opening This Year - Period 0 - This should be the same as the End Last Year totals.
6. Periods - This is the current year (this year) periods - usually 14 to 25 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
7. Period Total - The total of the period totals for this year.
8. End This Year - Opening Balance This Year total and the Period Total (This Year).

View transactions in T-Account viewer

You may double-click on a specific period of an account to list and view the transaction details in the T-Account viewer. You may be print the transactions.

Print transactions in T-Account viewer



Export transactions in T-Account viewer



You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

You may also click on the Export button of the T-Account viewer to export the transactions to a spreadsheet.

You may select to save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*

- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with a Help Authoring Tool

Column balances debtors - Debit / Credit

The Column balances debtors D/C report type list the debit and credit balances of the transactions totals for the for the individual debtor (customer / client) accounts for each period.

You may select to list all debtor (customer / client) accounts, or only those accounts with balances.

This report type cannot be printed but can be exported to a spreadsheet (e.g. OpenOfficeCalc / LibreOffice Calc or Microsoft Excel, etc.).

You may generate the transactions in a spreadsheet format in the Column balances debtors or the Column balances debtors D/C report types on the Ledger analyser.

These transaction totals may be exported to an "*Export.txt*" file or "*Export.csv*" and opened in a spreadsheet.

To view the transactions for a specific debtor (customer / client) account for a specific period, simply double-click on a period. The transactions will be displayed in the T-Account viewer to filter, print or export the transactions.

In addition to the transaction reports, you may also view and filter transactions on the Transactions tab of a selected debtor (customer / client) account.

This spreadsheet only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this spreadsheet.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Example : Column balances debtors D / C



Buttons 11, 10, 9, 8, 7, 6, 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

The periods is as follows:

1. Opening Balance Last Year - Period -1
2. Periods - This is last year periods - usually 1 to 12 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
3. Period Total - The total of the period totals for last year.
4. End Last Year - Opening Balance Last Year total and the Period Total.
5. Opening This Year - Period 0 - This should be the same as the End Last Year totals.
6. Periods - This is the current year (this year) periods - usually 14 to 25 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
7. Period Total - The total of the period totals for this year.
8. End This Year - Opening Balance This Year total and the Period Total (This Year).

You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

View transactions in T-Account viewer

You may double-click on a specific period of an account to list and view the transaction details in the T-Account viewer. You may be print the transactions.

Print transactions in T-Account viewer



Export transactions in T-Account viewer



You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

You may also click on the Export button of the T-Account viewer to export the transactions to a spreadsheet.

You may select to save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with HelpNDoc's easy CHM conversion

Column balances creditors

The Column balances creditor report type list the net balances (debits *minus* credits) of the transactions totals for the for the individual creditor (supplier / vendor) accounts for each period.

You may select to list all creditor (supplier / vendor) accounts, or only those accounts with balances.

This report type cannot be printed but can be exported to a spreadsheet (e.g. OpenOfficeCalc / LibreOffice Calc or Microsoft Excel, etc.).

You may generate the transactions in a spreadsheet format in the Column balances creditors or the Column balances creditor D/C report types on the Ledger analyser.

These transaction totals may be exported to an "*Export.txt*" file or "*Export.csv*" and opened in a spreadsheet.

To view the transactions for a specific creditor (supplier / vendor) account for a specific period, simply double-click on a period. The transactions will be displayed in the T-Account viewer to filter, print or export the transactions.

In addition to the transaction reports, you may also view and filter transactions on the Transactions tab of a selected creditor (supplier / vendor) account.

This spreadsheet only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this spreadsheet.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Example : Column balances creditors



Buttons 6, 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

The periods is as follows:

1. Opening Balance Last Year - Period -1
2. Periods - This is last year periods - usually 1 to 12 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
3. Period Total - The total of the period totals for last year.
4. End Last Year - Opening Balance Last Year total and the Period Total.
5. Opening This Year - Period 0 - This should be the same as the End Last Year totals.
6. Periods - This is the current year (this year) periods - usually 14 to 25 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
7. Period Total - The total of the period totals for this year.

8. End this year - Opening Balance This Year total and the Period Total (This Year).

View transactions in T-Account viewer

You may double-click on a specific period of an account to list and view the transaction details in the T-Account viewer. You may be print the transactions.

Print transactions in T-Account viewer



Export transactions in T-Account viewer



You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

You may also click on the Export button of the T-Account viewer to export the transactions to a

spreadsheet.

You may select to save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:*

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Column balances creditors - Debit / Credit

The Column balances creditor D/C report type list the debit and credit balances of the transactions totals for the for the individual creditor (supplier / vendor) accounts for each period.

You may select to list all creditor (supplier / vendor) accounts, or only those accounts with balances.

This report type cannot be printed but can be exported to a spreadsheet (e.g. OpenOfficeCalc / LibreOffice Calc or Microsoft Excel, etc.).

You may generate the transactions in a spreadsheet format in the Column balances creditors or the Column balances creditor D/C report types on the Ledger analyser.

These transaction totals may be exported to an "*Export.txt*" file or "*Export.csv*" and opened in a spreadsheet.

To view the transactions for a specific creditor (supplier / vendor) account for a specific period, simply double-click on a period. The transactions will be displayed in the T-Account viewer to filter, print or export the transactions.

In addition to the transaction reports, you may also view and filter transactions on the Transactions tab of a selected creditor (supplier / vendor) account.

This spreadsheet only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this spreadsheet.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Example : Column balances creditors - D / C



Buttons 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

The periods is as follows:

1. Opening Balance Last Year - Period -1
2. Periods - This is last year periods - usually 1 to 12 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
3. Period Total - The total of the period totals for last year.
4. End Last Year - Opening Balance Last Year total and the Period Total.
5. Opening This Year - Period 0 - This should be the same as the End Last Year totals.
6. Periods - This is the current year (this year) periods - usually 14 to 25 (depending on the number of periods and descriptions specified and entered in Reporting dates on the Setup ribbon).
7. Period Total - The total of the period totals for this year.

8. End this year - Opening Balance This Year total and the Period Total (This Year).

View transactions in T-Account viewer

You may double-click on a specific period of an account to list and view the transaction details in the T-Account viewer. You may be print the transactions.

Print transactions in T-Account viewer



Export transactions in T-Account viewer



You may double-click on an account and/or in a specific period to list and view the transaction details in the T-Account viewer. You may be print the transactions.

You may also click on the Export button of the T-Account viewer to export the transactions to a spreadsheet.

You may select to save the export file as Text files (.txt) (default file type); or as CSV files (*.csv) (Comma*

Separated Values) file type. This will automatically open (launch) the exported file in the program associated with the selected file type:

- *Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "Text Import" options.*
- *CSV files e.g. (Export.csv) - This should automatically open the "Text Import" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).*

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

SBR (Standard Business Reporting)

What is Standard Business Reporting (SBR)?

Standard Business Reporting (SBR) is an initiative aimed at simplifying and standardizing the way businesses report their financial information to government agencies and regulatory bodies. It involves the use of digital reporting standards, such as Extensible Business Reporting Language (XBRL), to enable the seamless exchange of business information between different software systems.

SBR streamlines the reporting process by providing a common language and structure for transmitting financial and regulatory data. It eliminates the need for separate reporting formats and manual data entry, reducing the administrative burden on businesses and improving accuracy and efficiency.

The key objectives of Standard Business Reporting are:

1. Standardization: SBR promotes the use of common data formats, classifications, and definitions, ensuring consistency and comparability of business information across different reports and jurisdictions.
2. Automation: By adopting digital reporting standards like XBRL, SBR enables the automated exchange and processing of financial data, reducing manual intervention and associated errors.
3. Simplification: SBR simplifies the reporting process by providing predefined data structures, validation rules, and electronic submission mechanisms, making it easier for businesses to comply with reporting requirements.

4. Interoperability: SBR facilitates seamless information exchange between businesses and government agencies, enabling regulatory bodies to receive, process, and analyse data in a more efficient and timely manner.
5. Cost reduction: Through standardization and automation, SBR helps businesses save costs associated with report preparation, compliance, and manual data entry.

By implementing SBR, governments aim to enhance transparency, streamline regulatory compliance, and improve the overall quality and accessibility of business information. It benefits businesses by reducing the reporting burden, enhancing data accuracy, and enabling better decision-making through improved access to standardized financial data.

SBR in osFinancials5/TurboCASH5 - how is that used?

In osFinancials5/TurboCASH5, SBR (Standard Business Reporting) is used to streamline the process of reporting financial information to government agencies. It allows businesses to submit reports directly from their accounting software to government entities, such as the Australian Taxation Office (ATO), using a standardized format. This helps in reducing errors, improving accuracy, and saving time when fulfilling reporting requirements.

Is SBR related to which countries?

Standard Business Reporting (SBR) is an international effort adopted by several countries to streamline business-to-government reporting. Notable countries using SBR include:

- Netherlands: Was among the pioneers with their Dutch Taxonomy Project, later renamed to SBR.
- Australia: Adopted the SBR program to reduce regulatory costs for businesses.
- Others: Many other countries are considering or have begun using SBR for similar purposes.

How Standard Business Reporting (SBR) works and its benefits

How SBR Functions:

- Data Mapping: SBR involves mapping the financial and tax data directly from a company's accounting software to the required government format. This data is often tagged using standardized taxonomy (like XBRL - eXtensible Business Reporting Language).
- Secure Submission: The mapped data is securely transmitted to government agencies via a secure online channel.
- Validation & Acknowledgement: Government systems validate the submitted data and provide an

acknowledgement receipt to the company.

Benefits of SBR:

- Reduces Administrative Burden: Automating the reporting process reduces the time and effort required to prepare and submit reports.
- Improves Accuracy: Standardized formats minimize errors related to manual data entry.
- Increases Efficiency: Businesses can reuse financial data for multiple reports, eliminating redundancy.
- Promotes Transparency: Standardized data formats enhance the transparency and comparability of financial information.
- Cost Savings: Reduced need for third-party filing services leads to cost savings for businesses.

By integrating SBR, osFinancials5/TurboCASH5 streamlines the accounting process, making it easier for businesses to comply with their reporting obligations.

Some specific aspects of Standard Business Reporting (SBR) and how you can maximize its benefits within osFinancials5/TurboCASH5:

Key Features of SBR in osFinancials5/TurboCASH5:

- Integration with Government Portals: osFinancials5/TurboCASH5 integrates directly with government portals, making submission of reports seamless. You'll need to configure it with your local government's requirements.
- Automated Data Extraction: The system can automatically extract relevant data from your financial accounts to generate compliant reports swiftly.
- Pre-validated Reports: osFinancials5/TurboCASH5 provides pre-validation of reports to ensure compliance with government standards before submission.

Steps to Implement SBR in osFinancials5/TurboCASH5:

- Set Up Taxonomies: Ensure the correct taxonomies are set up in your osFinancials5/TurboCASH5 system based on the required taxonomy (e.g., XBRL) by your government.
- Map Data Fields: Map the data fields from your financial records to the standardized taxonomy fields.
- Generate Reports: Use the SBR features in osFinancials to generate financial reports in the required format.

Submit Reports: Transfer the reports directly to the relevant government agency through the secure online channel integrated within osFinancials5/TurboCASH5.

Maximizing the Benefits:

- Training & Support: Leverage training materials and support offered by osFinancials5/TurboCASH5 to understand how to best use SBR features.
- Stay Updated: Keep your software and taxonomies updated to ensure continued compliance with changing requirements.
- Customization: Customize the mapping and reporting functionalities to match your specific business needs and improve efficiency.

By effectively using these features and steps, you can ensure a more streamlined and accurate reporting process, ultimately saving time and reducing administrative workload.

Process of adding Standard Business Reporting (SBR) references to accounts and reporting groups in the osFinancials

SBR view - Add SBR (Standard Business Reporting) references for accounts and reporting groups in Setup → Accounts.

Once the references are set, and generate the Trial balance, Income statement or Balance sheet report types on screen, click on the SBR view button, check, filter and copy to clipboard.

Open your spreadsheet program, and copy the contents into your spreadsheet, save the data, etc.

Wikipedia - Standard Business Reporting

SBR - https://www.xbrl.org/tag/sbr/

See - https://business.gov.nl/regulation/standard-business-reporting/ -

See - https://www.sbr-nl.nl/english/sbr-international -

Add SBR to Account groups and Accounts

On the Setup ribbon, select Setup → Accounts.



Select a Account group, or an account and click on the SBR reference button.



Click on the Add new button to add a "*REFERENCE CODE, ACCOUNT CODE*" or "*DESCRIPTION*".



Click Save. Once you have entered your SBR references close the "*Accounts*" screen.

SBR View

Once the SBR references is defined, you may generate the Trial balance, Income statement or Balance sheet report types for specific periods.

Click on the SBR view button. The "*SBR View*" screen will list your defined SBR references and the Debit, Credit and Totals for the selected report type and periods.



The Trial balance, will include SBR references for all account type in the Chart of Accounts.

The Income statement will include only SBR references for Income and Expense account types.

The Balance sheet will include only SBR references for Balance sheet account types (excluding Income and Expense account types).

Click on the Copy to clipboard button.

Open a Spreadsheet and paste the contents of the "*SBR View*" screen into the spreadsheet.

Example - Paste in Microsoft Excel

Open a Microsoft Excel spreadsheet or Workbook.

Select the Column and row where you wish to paste the content of the " *SBR View*" screen into the spreadsheet.

Click Paste option or press the Ctrl+V keys. An example of the "*SBR View*" content pasted in a Microsoft Excel spreadsheet, is as follows:



	A	B	C	D	E	F	G	H
1	OSF Account	OSF Group	SBR Ref	SBR ACCOUNTCODE	SBR DESCRIPTION	Debit	Credit	Total
2		Income	SBR-05		Revenue from business activities		R22,000.00	-R22,000.00
3	G010-000 Sales	Income	SBR-10	10000	Business income		R38,500.00	-R38,500.00
4	G100-000 Cost of sales	Income	SBR-15	100-000	Cost of Sales	R16,500.00		R16,500.00
5		Expenses	SBR-20		Business expenses	R2,195.00		R2,195.00
6		Current liabilities	SBR-30		Current liabilities		R10,475.00	-R10,475.00
7		Fixed assets	SBR-60		Non-current-assets	R2,850.00		R2,850.00
8		Current assets	SBR-70		Current assets	R27,430.00		R27,430.00

Optional - Use Import Text Wizard





Delimiters - Select Tab and do not select Space.



Example - Paste in LibreOffice

Open a LibreOffice Calc spreadsheet.

Select the Column and row where you wish to paste the content of the " *SBR View*" screen into the spreadsheet.

Click Paste option or press the Ctrl+V keys. The "*Text Import*" screen will be launched.



Separator Options - Separated by - Select Tab and do not select Space.

Click OK. An example of the "*SBR View*" content pasted in a LibreOffice spreadsheet, is as follows:



Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Pivot

The pivot view of your transaction totals and/or budget totals, for the selected periods or dates, in the Ledger analyser / Ledger analyser 2.

Pivot feature is available for all of the report types in the Ledger analyser.

Pivots, by default, summarises the totals for the Income and Expense (Income statement) accounts and Capital, Assets and Liabilities (Balance sheet) accounts for which budget figures were entered, and/or transactions in batches and documents were processed, for the selected report type and period or dates.

The pivots allows you to sort, group, filter and drill down customise datasets and types of graphs.

Pivot feature is also available for Budgets (accessed from the Reports ribbon), view graphs, filter, drill down, customise datasets.

Pivots only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in pivots.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Generating Pivot tables

To view the Trial balance figures in the Pivot table in the Ledger analyser:

1. On the Ledger analyser 1 or Ledger analyser 2, select the Income statement, Trial balance or Balance sheet report type. In this example, the "*Trial balance*" is selected.
2. Select the Period or dates on the Free selection tab. In this example, the "*2 Months*" from "*1 March 2022*" to "*30 April 2022*" is selected.
3. Click on the Report button.



Buttons 5, 4, 3, 2 and 1 at the bottom of the report - is shortcut keys to the last accessed T-Account viewer options or Pivot options. These shortcuts will be cleared when you close active forms, or when you open the Set of Books.

4. Click on the Pivot button. The "*Trial balance*" figures for the selected period is displayed:



You may click on any graph to display the graph for the next available data level fields.

The cursor will be displayed as a magnifying glass and move to the next dataset. In this example, "Account type" is selected.



Move over graph area will display the values, e.g. "Profit / Loss - Credit is 17500" and "Amount for profit loss is -9905".

5. Click on the ⊞ icon to Profit loss to list the totals for the Income and Expense account types (e.g. Income and Expenses financial categories) for the selected period or dates. The icon will change ⊟ to list totals for each financial category (i.e. Income and Expenses).

You may right-click to launch the context menu, and select the following options:



6. Once the available columns are expanded, the Pivot table for the "*Trial balance*", according to the

selected options, should be displayed as follows:



Default filter options

The default filter options, which may be selected as needed, is structured on the Pivot screen in four (4) areas, "*Filter Area, Column Area, Row Area*" and "*Data Area*". The filter options is as follows:

Filter Area:

1. Transaction id – The transaction id is automatically generated for posted transactions in batches and documents.
2. Cost group 1 – If Cost centres 1 is selected in batch transactions and selected on documents, the Cost centres for Cost centre 1 will be listed.
3. Cost group 2 – If Cost centres 2 is selected in batch transactions and selected on documents, the Cost centres for Cost centre 2 will be listed.
4. Account group 2 – The groups set for Account group 2 in Setup → Groups (Setup ribbon) and linked to Accounting group 2 in Setup → Accounts (Setup ribbon).
5. Date week – The number of the week (from 1 to 53) for a calendar year.

> *In this example, March 2022 and April 2022 will be listed as week 9 to 14. Week 1 to 8 is for January 2022 and February 2022, which is not included in this Financial year (1 March 2022 to 28 February*

2023) as no transactions were posted in weeks 1 to 8.

6. Debit – The debit amounts.
7. Credit - The credit amounts.
8. Batch id – The batch id is auto generated for posted transactions in batches and documents.
9. Reference – The "*Reference*" is as follows:
    - Documents – Document number as generated when creating documents.

      In this example, and most database templates, the document numbers are prefixed with alpha characters, i.e. IN000001 = Invoices, CR000001 = Credit notes, PU000001 = Purchases and SR000001 = Supplier returns.

    - Batches – The reference as entered the "*Reference*" column of Batch entry screens.

      *The reference of Balancing entries in batches is indicated with eight (8) asterisks "********".*

10. Transaction description -
    - Documents – The document type (i.e. Invoice, Credit note, Purchase and Supplier returns) and the reference as entered in the "*Your reference*" field on "*Document entry*" screens, will be listed.

      COST OF SALES/Your reference – These are the Cost of Sales transactions generated for Invoices and Credit notes on which the stock items, default stock item type and other stock item types supporting cost of sales, were processed.

    - Batches – The description of the transaction entered in the "*Description*" column of Batch entry screens.
11. Balance account – The values, are as follows:
    - 0 = Income and Expense (Income statement) accounts.
    - 1 = Ledger accounts set as Balance sheet account type. These Capital, Assets and Liabilities accounts are reported on the Balance sheet.

Data Area:

12. Amount - The total debit amounts will be listed. Credit amounts (prefixed by a - (minus sign)) will be listed.

Row Area:

13. Account type – Lists all account types for the "*Trial balance*", and is as follows:

    a) Balans – Lists all accounts linked to the "*Balance sheet*" in the "*Account type*" field of Setup → Accounts (Setup ribbon). The "*Balance sheet*" accounts which is linked to the "*Capital*", "*Assets*" and "*Liabilities*" financial categories will be listed.

    b) Creditor – Lists all accounts added in the Creditor (Default ribbon).

    c) Debtor – Lists all accounts added in the Debtor (Default ribbon).

    d) Proffit / Loss – Lists all accounts linked to the "*Income statement*" in the "*Account type*" field of Setup → Accounts (Setup ribbon). The options is as follows:

        i) Income – The "*Income statement*" accounts which are linked to the "*Income*" financial category will be listed.

        ii) Expenses – The "*Income statement*" accounts which are linked to the "*Expenses*" financial category will be listed.

    e) Account group1 – List the Groups 1 linked to accounts added in Setup → Groups (Setup ribbon) as follows:

        i) Balans - Balance sheet accounts linked to Account group 1.

        ii) Creditor – Creditor accounts linked to Creditor group 1.

        iii) Debtor – Debtor accounts linked to Debtor group 1.

        iv) Proffit / Loss – Income and Expense accounts linked to Account group 1.

    f) Account code – All accounts will be listed by Account code.

    g) Account name – The description (name of the account).

Column Area:

14. Date year – The transaction totals will be displayed only for the year which was selected on the "*Per period*" tab of the Ledger analyser options. In this example only 2022 will be listed, since March 2022 and April 2022 were selected.

If a full financial year, for example, 1 March 2022 to 28 February 2023 is selected and transactions were processed for January 2022 and February 2022, the 2022 and 2023 years will be available.

The transaction totals will be listed for each calendar year. For example, if your financial year starts on 1 January 2022 and ends on 31 December 2022, only one (1) financial year will be listed, e.g. 2022.

> *In this example, the financial year starts on 1 March 2022 and ends on 28 February 2023, the totals will be listed for 2022. Since no transactions is posted for January 2022 and February 2022, the 2022 year will not be available at this stage.*

15. Date month – The transaction totals will be displayed only for the months which was selected on the "*Per period*" tab of the Ledger analyser options. In this example, only March and April will be listed, since March 2021 and April 2021 were selected.

Change sequence add / remove Pivot grid fields

Hide Pivot grid fields

Select a Pivot grid field, right-click, and select "*Hide*" on the context menu. The selected Pivot grid field will be removed from the grid and added to the "*PivotGrid Field List*". For example, if you do not use Cost centres, you may hide "*Cost group 1*" and "*Cost group 2*".



Order (sequence) of columns

You may select a Pivot grid field, right-click, and select the following options from the "*Order*" option on the context menu:

1. Move to Beginning - Move to the first Pivot grid field.
2. Move to End - Move to the last Pivot grid field.
3. Move Left - Move the selected Pivot grid field before the previous Pivot grid field to the left.
4. Move Right - Move the selected Pivot grid field after the next Pivot grid field to the right.

> *You may use your mouse to drag a selected Pivot grid field to the right or left to your required position.*

Filters

Right-click to access the "*Show Field List*" or the "*Show Prefilter Dialog*" options.

PivotGrid Field List

The "*PivotGrid Field List*" lists the available Pivot grid fields not displayed on the default Pivot table view. You select an available field on the list and add them to the four (4) areas (i.e. "*Data Area*", "*Filter Area*", "*Column Area*" or the "*Row Area*") of the Pivot table.



Show Prefilter Dialog

The "*Prefilter Dialog*" allows you to create custom filters for the Pivot table.



By default all data applicable to a column "Pivot grid field" is included in the initial launch of the Pivot table based on your report options.

You may click on the filter icon of a selected "Pivot grid field" to remove the tick to exclude that specific data on the list from the Pivot table.

Save custom filter files

To save a custom filter file:

1. Once you have sorted or filtered your data with the "*Make filter0*" screen, click on the Save as... button. The "*Save active filter as*" screen will be displayed.
2. Select a directory in which you wish to save the custom filter file.
3. Enter a file name.
4. Click on the Save button to save the Filter in a (*.flt) Filter File format. You may then at any later stage open the saved *.flt file.

Open custom filter files

To open a saved a custom filter file:

1. Once you have sorted or filtered your data with the "Make filter" screen, click on the Open... button. The "*Open saved filter as*" screen will be displayed.

2. Select a directory in which you have saved the custom filter file.
3. Select a valid filter file.
4. Click Open. The selected filter file's name will be displayed in the titlebar of the "*Make filter*" screen.

Conditions



1. Equal to - list or display all values which is the same as the specified value.
2. Not equal to - list or display all values which is not the same as the specified value.
3. Less than - list or display all values smaller than the specified value.
4. Less than or equal to - list or display all values smaller or equal to the specified value.
5. Greater than - list or display all values greater than the specified value.
6. Greater than or equal to - list or display all values greater or equal to the specified value.
7. is null - excludes any value entered, will not be listed or displayed.
8. is not null - is not zero - any value which is not equal to zero will be listed or displayed.
9. Between - Specify specific values, etc. to include only matching values.
10. Not between - Specify specific values, etc. to exclude values.
11. in - In a specified value.
12. Not in - Not in a specified value.

If a Date for a column condition is selected, additional conditions will be available (i.e. is this month, is this year, is next 7 days, is next week, is next 14 days, is next two weeks, is next 30 days, is next month, is future, is this week, is yesterday, is today, is last 7 days, is last week, is last 14 days, is last two weeks, is last 30 days, is last month, is last year, is past, is this week, etc.

Customise the graphs

Graph types

The default chart diagram is the "*Column diagram*". You may select the one of the following diagrams to view the graph.



Series

By default, the "*Amount*" and "*Debit*" and "*Credit*" is displayed.

You may remove the tick of the series or add a tick to a series. For example, if you wish to see only the "*Debit*" and "*Credit*" amounts, leave these as ticked; and if you do not wish to view the "*Amount*", remove the tick.

Sort by: select the options in the series to change the sequence in which the data in the graph will be displayed.



Data groups

Data groups is empty.

Options

You may change the default values for the "*Legend, Title, Toolbox*" and "*Other (Value Hints)*" according to your requirements.



Created with the Standard Edition of HelpNDoc: Effortlessly Publish Your Word Document as an eBook

Zoom in / Zoom out + / - buttons

Zoom in / Zoom out + / - buttons added to resize (increase / decrease the font) the reports (i.e. Trial balance, Balance sheet and Income statement) on screen.

These are similar to the Zoom + (Zoom in) and the Zoom - (Zoom out) buttons on the View ribbon on Spreadsheets.

- Ledger analyser - Available for Trial balance, Balance sheet and Income statement on screen. Not implemented on the other report types (i.e. Column balances, Standard column balances, This year vs last year, Budget vs actual).
- Spreadsheet reports (Reports ribbon) - All spreadsheet reports.
- Data Import / Export - Spreadsheet import button on Import / Export tab of Stock items (Default ribbon).
- Setup → Accounts - Spreadsheet icon (Setup ribbon).
- Batch entry - Spreadsheet import icon on all batches entry screens.

- Spreadsheet sales (Default ribbon).

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

T-Account viewer

The "*T-Account viewer*" may be launched (for specific accounts or periods) from the Ledger analyser 1 or Ledger analyser 2 options on the Reports ribbon (right-click or double-click on specific accounts or groups).

Column balances - The column balances report types will list the transactions of a selected account for each period of Last year and This year in a spreadsheet format.

You may select an account and double-click on any period. This will launch the T-Account viewer with a list of all the transactions for the selected period. You may be print and/or export the transactions.

The following six (6) column balances report types is available:

1. *Column balances - Lists all ledger account balances in a spreadsheet view. These are the ledger accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*
2. *Column balances debtors - Lists the balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
3. *Column balances creditors - Lists the balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*
4. *Column balances D/C - Lists all debit and credit ledger account balances in a spreadsheet view. These are the accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*
5. *Column balances debtors D/C - Lists the debit and credit account balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
6. *Column balances creditors D/C - Lists all debit and credit balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*

Account viewer - Ledger analyser

In addition to launching the T-Account viewer from the Ledger analyser options, the T-Account viewer may also be launched separately on the Reports ribbon; or from the following options on the Default ribbon:

- Search - Investigator - Account or Batch type searched items.
- Debtors - Transactions tab - Click on the Show transactions button.
- Creditors - Transactions tab - Click on the Show transactions button.

By utilising the T-Account viewer and the reports in the Ledger analyser, you can gain a detailed understanding of the transactions and their impact on the accounts involved.

You may select an account and double-click on a specific period to list and view the transaction details in the T-Account viewer. You may be print and/or export the transactions.

In this example, the T-Account viewer is launched by a double-click in the month (accounting period) " *June*" in the "*G700000 Debtors control*" account:



Show contra - By default this option is not selected.

If the Show contra is selected, it will insert (add) the Account code and Description before the batch id (batch number).

The Contra accounts will not print on the T-Account viewer ("ledgerdetail") report; but will be included in the Export file when you click on the Export button of the T-Account viewer.

Print transactions in T-Account viewer

Click on the Print button to print the selection in the T-Account viewer.



Each time you access the T-Account viewer from the Ledger analyser, it will create a shortcut button (numerical). You may then click on any of the 1, 2, 3, 4, 5 buttons, etc. to view your previous T-Account viewer selections.

If the Pivot option was selected, it will launch the Pivot feature.

These shortcuts will only be cleared if you:

- *Close and re-open the Set of Books*
- *Tools → Close active forms (Setup ribbon)*

Account viewer - Reports ribbon

To access the T-Account viewer:

1. On the Reports ribbon, select T-Account viewer. The "*T-Account viewer*" screen is displayed:



Show contra - By default this option is not selected.

If the "Show contra" is selected, it will insert (add) the Account code and Description before the batch id (batch number).

The Contra accounts will not print on the T-Account viewer ("ledgerdetail") report; but will be included in the Export file when you click on the Export button of the T-Account viewer.

2. Select the following options:

   a) Account - Select the Account on the Lookup, if this field is available.

The Account option will only be available, if the T-Account viewer is launched from the T-Account viewer on the Reports ribbon).

The Account lookup option is not available, if the T-Account viewer is launched from elsewhere.

   b) From date and To date - Enter or select the dates on the date picker.

The "From date" and "To date" fields will automatically be filled in with the date selected on the Ledger analyser report options. It will only include transactions for these dates. You may enter or select any other dates, if necessary.

If you have selected the Column balances report types, and you click on the period columns, the dates for the selected period column will automatically be selected.

If the Pivot option was selected, it will launch the Pivot feature.

3. You may also use the following options to get specific views of transactions:

a) Batch number (e.g. 10014 automatically generated). This will list only the transactions for a specific batch (journal).

b) Account code (e.g. B810000 Current Bank account, G610010 Furniture and Fittings @ Cost, G210010 Fuel & Oil, G720000 Petty cash, G220000 Rent, G225000 Salaries and Wages, T850020 Input Tax Standard Rate, T850030 Input Tax Capital Goods). This will list the transactions for a specific account.

c) Date – This will list the transactions for a specific date. If you double-click on a date, the From date and To date will be changed to the selected date.

4. Once finished, click on the Close button to exit (close) the "*T-Account viewer*" screen.

The T-Account viewer may also be accessed from the Search (Default ribbon). - Once an account is listed, and selected, double-click on it.

If the T-Account viewer is accessed from the Reports ribbon, you may select an account on the Accounts lookup.



Export T-Account viewer

To create a T-Account viewer - Export file:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select the "*Column balances*" report type. Once finished, selecting your options, click on the Report button to build, update or refresh the data for the selected report type on the Ledger analyser screen.
3. Click on the Export button. This will launch the "*Save as*" screen.



4. Select the folder in which you wish to save the file.
5. The default file name will be "*Export.txt*". Overtype this with your own name.

If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.

Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:

> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

6. Click on the Save button.

7. This will automatically open (launch) the file in your system's default spreadsheet application or program associated with comma separates value file type.



	A	B	C	D	E	F	G	H	I	J	K	L
1	Company name:	Handyman Hardware Store										
2	Address	27 Olifants Road										
3		Emmarentia										
4		Johannesburg										
5		2195										
6	Phone:	(011) 310-1390										
7	Date of report	2022/05/22 20:34										
8	Contra Accounts	Batch no.	Cost centre 2	Cost centre 1	Account	Name	Alias	Description	Reference	Date	Debit	Credit
9	D1ABGRE Mr. AB Green	10028	Empty	Empty	G010000*	Sales	Sales2103	Paint - Exterior	********	2021/03/07		1000
10	D1MACDS MAC Shop Decor Specialists	10028	Empty	Empty	G010000*	Sales	Sales2103	Install - Built-in cupboard	********	2021/03/09		1500
11	D1ABGRE Mr. AB Green	10028	Empty	Empty	G010000*	Sales	Sales2103	Paint - Exterior	********	2021/03/10		1000
12	D1MDAVI Mr. Mike Davies	10028	Empty	Empty	G010000*	Sales	Sales2103	Install - Built-in cupboard	********	2021/03/11		1500
13	D1ABGRE Mr. AB Green	10039	Empty	Empty	G010000*	Sales	IN000001	Paint - Exterior	IN000001	2021/03/13		1000
14	D1MACDS MAC Shop Decor Specialists	10040	Empty	Empty	G010000*	Sales	IN000002	Install - Built-in cupboards	IN000002	2021/03/14		1500
15	D1ABGRE Mr. AB Green	10041	Empty	Empty	G010000*	Sales	IN000003	Paint - Exterior	IN000003	2021/03/15		1000
16	D1MDAVI Mr. Mike Davies	10042	Empty	Empty	G010000*	Sales	IN000004	Install Built-in Cupboards	IN000004	2021/03/16		1500
17	D1MDAVI Mr. Mike Davies	10045	Empty	Empty	G010000*	Sales	IN000005	Drill press	IN000005	2021/04/07		1000
18	D1ROGSM Mr. Roger Smith	10047	Empty	Empty	G010000*	Sales	IN000006	Compressor	IN000006	2021/04/09		3000
19	D1MDAVI Mr. Mike Davies	10049	Empty	Empty	G010000*	Sales	IN000007	Compressor	IN000007	2021/04/10		1500
20	D1ROGSM Mr. Roger Smith	10051	Empty	Empty	G010000*	Sales	IN000008	Drill press	IN000008	2021/04/11		2000
21												

Created with the Standard Edition of HelpNDoc: Make your documentation accessible on any device with HelpNDoc

T-Account viewer- Open exported transactions in other Spreadsheet applications

Once an "*Export.txt*" file is created, the exported file will automatically open in Microsoft Excel spreadsheet (as in this documentation).

If you wish to open saved "*Export.txt*" files in another app (program) for CSV (Comma Separated Values) file type, than Microsoft Excel, you may use the spreadsheet components of other apps (programs) e.g. LibreOffice, OpenOffice or UltraOffice installed on your system.

See - System settings - Default app for csv file types.

The T-Account viewer may be launched (for specific transactions or periods) from the Ledger analyser 1 or Ledger analyser 2 options on the Reports ribbon (right-click or double-click on specific accounts or groups).

Column balances - The column balances report types will list the transactions of a selected account for each period of Last year and This year in a spreadsheet format.

You may select an account and double-click on any period. This will launch the T-Account viewer with a list of all the transactions for the selected period. You may be print and/or export the transactions.

The following six (6) column balances report types is available:

1. *Column balances - Lists all ledger account balances in a spreadsheet view. These are the ledger accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*
2. *Column balances debtors - Lists the balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
3. *Column balances creditors - Lists the balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*
4. *Column balances D/C - Lists all debit and credit ledger account balances in a spreadsheet view. These are the accounts reported in the Trial balance (this includes both the accounts reported in the Income statement and Balance sheet).*
5. *Column balances debtors D/C - Lists the debit and credit account balances of all the individual debtor (customer / client) accounts (Debtors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*
6. *Column balances creditors D/C - Lists all debit and credit balances of all the individual creditor (supplier / vendor) accounts (Creditors on the Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*

In addition to this, the T-Account viewer may also be launched separately on the Reports ribbon; or from the following options on the Default ribbon:

1. Search - Investigator - Account or Batch type searched items.
2. Debtors - Transactions tab - Click on the Show transactions button.
3. Creditors - Transactions tab - Click on the Show transactions button.

Example : Transactions in T-Account viewer

In this example, the T-Account viewer is launched by a double-click in the month (accounting period) "*June*" in the "*G700000 Debtors control*" account:



Show contra - By default this option is not selected.

If the Show contra is selected, it will insert (add) the Account code and Description before the batch id (batch number).

The Contra accounts will not print on the T-Account viewer ("ledgerdetail") report; but will be included in the Export file when you click on the Export button of the T-Account viewer.

Print transactions in T-Account viewer

Click on the Print button to print the selection in the T-Account viewer.



Export transactions in T-Account viewer

To create an Export file for transactions in the T-Account viewer:

1. Click on the Export button (on the T-account-viewer). The "*Save As*" screen will be displayed:



2. Select the file type. Text files (*.txt) is the default; or select CSV files (*.csv) (Comma Separated Values).

3. Click on the Save button. This will automatically open (launch) the exported file in the program associated with the selected file type:

    - Text files e.g. (Export.txt) - This should automatically open the exported text file of your system's default text file program associated with Text file type (*.txt) file types (e.g. Notepad, etc). You need to close the exported text file and launch your spreadsheet program. In your spreadsheet program, Open the text file to launch the "*Text Import*" options.

    - CSV files e.g. (Export.csv) - This should automatically open the "*Text Import*" options of your system's default spreadsheet program associated with Comma Separated Value file type (*.csv) file types (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).

Opened in a Text editor - Notepad

An example, of the "*Export.txt*" file opened in your systems default program associated with *.txt files *(e.g. "Notepad")* is as follows:

Open the Export.txt file in a spreadsheet

If the Comma Separated Value file type (.csv) file type for the exported file does not automatically launch in a spreadsheet program; or the incorrect program, you may change this. To do this; you need to:*

- *Select the saved *.csv file.*
- *Right-click on it and select the Open with option on your system's context-menu.*
- *If your program is not listed as one of the Recommended programs on your system's context-menu, select the Choose Default Program... option. On this screen, select your default program (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.). You may need to click on the Browse button to do this.*
- *Make sure that the Always use the selected program to open this kind of file option is selected (ticked), and click on the OK button.*

Locate the "*Export.txt*" file in your System's File Explorer



If LibreOffice and not LibreOffice Calc is selected, the "Export.txt" file will open in LibreOffice Writer as a text file.

In this example, Open with > LibreOffice Calc is selected. The "*Text Import*" screen is selected.



Separator options - Separated by

- *Comma - Do not select this option. If you have selected "Show contra" option on the T-Account viewer, the Contra accounts will be included in the exported file as column A (e.g." **G010000 Sales,T860010 Output VAT - 15%"). If the "Comma" option is selected, it will export the Contra accounts into 2 columns. The rest of the columns would be out of line with the column headings.***

- *Merge delimiters - Do not select this option. If you select the "Merge delimiters" option, the Debit and Credit totals will be merged into the Debit column.*

Select your options and click OK. The selected "*Export.txt*" file will be opened in LibreOffice Calc spreadsheet.

Spreadsheet view



	A	B	C	D	E	F	G	H	I	J	K	L
1	Company name:	Handyman Hardware Store										
2	Address	27 Olifants Road										
3		Emmarentia										
4		Johannesburg										
5		2195										
6	Phone:	(011) 310-1390										
7	Date of report	2022/05/21 04:51:36										
8	Contra Accounts	Batch no.	Cost centre 2	Cost centre 1	Account	Name	Alias	Description	Reference	Date	Debit	Credit
9	G010000 Sales,T860010 Output VAT - 15%	10059	Empty	Empty	D1ABGRE	Mr. AB Green	IN000011	Invoice /D-101	IN000011	2021/06/05	1150	
10	G010000 Sales,T860010 Output VAT - 15%	10061	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000012	Invoice /C-102	IN000012	2021/06/07	3450	
11	G010000 Sales,T860010 Output VAT - 15%	10063	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000013	Invoice /C-103	IN000013	2021/06/10	1725	
12	G010000 Sales,T860010 Output VAT - 15%	10065	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000014	Invoice /D-102	IN000014	2021/06/12	2300	
13	G010000 Sales,T860010 Output VAT - 15%	10067	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000015	Invoice /D-101	IN000015	2021/06/15	1150	
14	G010000 Sales,T860010 Output VAT - 15%	10069	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000016	Invoice /C-102	IN000016	2021/06/17	3450	
15	G010000 Sales,T860010 Output VAT - 15%	10071	Empty	Empty	D1MDAVI	Mr. Mike Davies	IN000017	Invoice /C-103	IN000017	2021/06/20	2875	
16	G010000 Sales,T860010 Output VAT - 15%	10088	Empty	Empty	D1ROGSM	Mr. Roger Smith	CR000002	Credit note /D-102	CR000002	2021/06/22		2300
17	G010000 Sales,T860010 Output VAT - 15%	10073	Empty	Empty	D1ROGSM	Mr. Roger Smith	IN000018	Invoice /D-102	IN000018	2021/06/24	2300	
18	G010000 Sales,T860010 Output VAT - 15%	10086	Empty	Empty	D1ABGRE	Mr. AB Green	CR000001	Credit note /D-101	CR000001	2021/06/30		5750
19	G010000 Sales,T860010 Output VAT - 15%	10090	Empty	Empty	D1ABGRE	Mr. AB Green	CR000003	Credit note /C-103	CR000003	2021/06/30		2875
20	G010000 Sales,T860010 Output VAT - 15%	10075	Empty	Empty	D1ABGRE	Mr. AB Green	IN000019	Invoice /D-101	IN000019	2021/06/30	5750	
21	G010000 Sales,T860010 Output VAT - 15%	10077	Empty	Empty	D1ABGRE	Mr. AB Green	IN000020	Invoice /C-103	IN000020	2021/06/30	5750	
22												

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Ledger analyser - Open exported files in other Spreadsheet applications

There are six (6) report types, which may be selected (i.e. Trial balance, Income statement, Balance sheet, Standard column balances, Budget vs actual and This year vs last year) which may be generated in the Ledger analyser and exported to spreadsheets.

When printing reports on the Ledger analyser, it is recommended that the Export button are used to export the reports as a Comma Separated Values (.csv) file, instead of saving it as a meta file form the "Reportman print preview" screen ( ) "Save metafile as" option.*

To create an Export file in the Ledger analyser:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.

2. Select the report type. Once finished, selecting your options, click on the Report button to build, update or refresh the data for the selected report type on the "*Ledger analyser*" screen.

3. Click on the Export button. This will launch the "*Save as*" screen.



4. Select the folder in which you wish to save the file.

5. The default file name will be "*Export.txt*". Overtype this with your own name.

> *If you do not enter and save the Export.txt file name, you may replace existing (previously exported) files.*
>
> *Of an existing exported file is opened, and you are trying to save a export file with the same name, a similar error message as the following will be displayed:*
>
> Cannot create file "D:\exports\Export.txt". The process cannot access the file because it is being used by another process.

6. Click on the Save button. This will automatically open (launch) the file in the program associated with the Comma Separated Value file type (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.).

Opened in a Text editor - Notepad

An example, of the "*Export.txt*" file opened in your systems default program associated with *.txt files *(e.g. "Notepad")* is as follows:



Export-trial-balance.txt - Notepad

File Edit View

```
Per period    Year   Budget False
Ignore zero balances True   Include opening balances    True
Viewer  Debtors / Creditors True   Opening balances only      False

       REPORTING GROUP ROOT                                    0.00
              Income                                                        0.00
              G010000       Sales                                                           0.00     36,000.00
              G100000       Cost of sales                                                15,000.00          0.00
              Expenses                                                      0.00
              G200000       Bank charges                                                    45.00          0.00
              G205000       Depreciation                                                   150.00          0.00
              G210000       Motor vehicle expenses                                2,160.00
                     G210010       Fuel and oil                                            150.00          0.00
                     G210020       Maintenance                                             810.00          0.00
                     G210030       Repairs                                               1,200.00          0.00
              G220000       Rent                                                            500.00          0.00
              G230000       Stationery                                                      240.00          0.00
              Capital                                                       0.00
              G505000       Capital                                                         0.00     16,500.00
              G510000       Retained income                                                 0.00      4,200.00
              Current liabilities                                           0.00
              G860000       VAT - Control - 15%                                  -4,219.00
                     T860010       Output VAT - 15%                                        0.00      5,500.00
                     T860020       Input VAT - Standard rate -15%                      1,161.00          0.00
                     T860030       Input VAT - Capital goods -15%                        120.00          0.00
              G900000       Creditors control                                    -6,000.00
                            Creditor group 1B                                0.00
                            C2AONES       A-ONE Suppliers                    0.00       600.00
                            C2BESTS       BEST Suppliers                     0.00       400.00
                            Creditor group 1C                                0.00
                            C2ABCOS       ABC-Office-Supplies                0.00     2,700.00
                            C2ABCSC       ABC-Service-Centre                 0.00     2,300.00
              Fixed assets                                                  0.00
              G600000       Furniture & fittings - Net value                     4,457.00
                     G600010       Furniture  fittings @ cost                            4,807.00          0.00
                     G600020       Furniture  fittings -Acc. deprec.                         0.00        350.00
              G610000       Motor vehicles - Net value                           4,400.00
                     G610010       Motor vehicles @ cost                                 5,000.00          0.00
                     G610020       Motor vehicles -Accum. depreciation                       0.00        600.00
              Current assets                                                0.00
              G700000       Debtors control                                     40,200.00
                            Debtor group 1B                                  0.00
                            D1MDAVI       Mr. Mike Davies               14,025.00          0.00
                            D1ROGSM       Mr. Roger Smith               15,950.00          0.00
                            Debtor group 1C                                  0.00
                            D1ABGRE       Mr. AB Green            7,775.00          0.00
                            D1MACDS       MAC Shop Decor Specialists            2,450.00          0.00
              G750000       Stock control                                                   0.00      6,500.00
              B810000       ABC - Bank                                                  6,123.00          0.00
              B820000       Petty cash                                                    144.00          0.00

                                   Net Profit/Loss             0.00          0.00
                                   Balance               0.00          0.00
```

Ln 43, Col 49 | 80% | Windows (CRLF) | UTF-8

Open the Export.txt file in a spreadsheet

If the Comma Separated Value file type (.csv) file type for the exported file does not automatically launch in a spreadsheet program; or the incorrect program, you may change this. To do this; you need to:*

- *Select the saved *.csv file.*

- *Right-click on it and select the Open with option on your system's context-menu.*
- *If your program is not listed as one of the Recommended programs on your system's context-menu, select the Choose Default Program... option. On this screen, select your default program (e.g. Microsoft Excel, LibreOffice Calc, OpenOffice Calc, Ultra Office, etc.). You may need to click on the Browse button to do this.*
- *Make sure that the Always use the selected program to open this kind of file option is selected (ticked), and click on the OK button.*

Locate the "*Export.txt*" file in your System's File Explorer.



If LibreOffice and not LibreOffice Calc is selected, the "Export.txt" file will open in LibreOffice Writer as a text file.

In this example, Open with > LibreOffice Calc is selected. The "*Text Import*" screen is displayed:



Separator options - Separated by

Tab is the only option which should be selected for the trial balance. This may differ for some other report types.

Select your options and click OK. The selected "*Export.txt*" file will be opened in LibreOffice Calc spreadsheet.

Spreadsheet view



	A	B	C	D	E	F	G	H	I	J	K
1	Per period	2021/03/01 / 2022/02/28	Groups	Reporting group 1	Report type	Trial balance					
2	Per period	Year	Budget	False							
3	Ignore zero balances	True	Include opening balances	True							
4	Viewer Debtors / Creditors	True	Opening balances only	False							
5											
6		REPORTING GROUP ROOT					0.00				
7			Income				0.00				
8			G010000	Sales				0.00	36,000.00		
9			G100000	Cost of sales				15,000.00	0.00		
10			Expenses				0.00				
11			G200000	Bank charges				45.00	0.00		
12			G205000	Depreciation				150.00	0.00		
13			G210000	Motor vehicle expenses			2,160.00				
14				G210010	Fuel and oil			150.00	0.00		
15				G210020	Maintenance			810.00	0.00		
16				G210030	Repairs			1,200.00	0.00		
17			G220000	Rent				500.00	0.00		
18			G230000	Stationery				240.00	0.00		
19			Capital				0.00				
20			G505000	Capital				0.00	16,500.00		
21			G510000	Retained income				0.00	4,200.00		
22			Current liabilities				0.00				
23			G860000	VAT - Control - 15%			-4,219.00				
24				T860010	Output VAT - 15%			0.00	5,500.00		
25				T860020	Input VAT - Standard rate -15%			1,161.00	0.00		
26				T860030	Input VAT - Capital goods -15%			120.00	0.00		
27			G900000	Creditors control			-6,000.00				
28					Creditor group 1B		0.00				
29					C2AONES	A-ONE Suppliers		0.00	600.00		
30					C2BESTS	BEST Suppliers		0.00	400.00		
31					Creditor group 1C		0.00				
32					C2ABCOS	ABC-Office-Supplies		0.00	2,700.00		
33					C2ABCSC	ABC-Service-Centre		0.00	2,300.00		
34			Fixed assets				0.00				
35			G600000	Furniture & fittings - Net value			4,457.00				
36				G600010	Furniture fittings @ cost			4,807.00	0.00		
37				G600020	Furniture fittings -Acc. deprec.			0.00	350.00		
38			G610000	Motor vehicles - Net value			4,400.00				
39				G610010	Motor vehicles @ cost			5,000.00	0.00		
40				G610020	Motor vehicles -Accum. depreciation			0.00	600.00		
41			Current assets				0.00				
42			G700000	Debtors control			40,200.00				
43					Debtor group 1B		0.00				
44					D1MDAVI	Mr. Mike Davies		14,025.00	0.00		
45					D1ROGSM	Mr. Roger Smith		15,950.00	0.00		
46					Debtor group 1C		0.00				
47					D1ABGRE	Mr. AB Green		7,775.00	0.00		
48					D1MACDS	MAC Shop Decor Specialists		2,450.00	0.00		
49			G750000	Stock control				0.00	6,500.00		

Created with the Standard Edition of HelpNDoc: Easily share your documentation with the world through a beautiful website

Reports menu

On the Reports ribbon, the Reports menu lists all the standard reports, which are required to manage the information in a Set of Books. In addition to these standard reports, you may also create your own user or custom reports in the Report designer.

These reports that are stored in the following folder:

" ...\plug_ins\reports\systemreports"

If you are creating transactions from your stock file (processing documents - invoices, credit notes,

purchases and supplier returns documents), you will need to view reports in the stock ledger, document listing, sales analysis, purchase analysis reports.

To access the Reports menu:



Click on the Reports ribbon, select Reports. A list of the seventeen (17) reports or groups of reports will be listed.

The summary of these reports, is as follows:

1. Ledger - The following reports are available to manage all the accounts in the general ledger:

    a) Budget v/s realisation 3 periods - Lists the Income and Expense account balances and budget figures for three (3) periods as comparative figures.

    b) Listing - List the General ledger accounts (Chart of Accounts).

    c) Transactions - Transactions, Transactions - Standard and Transactions - Extra details.

2. Debtors - The following reports are available to manage the accounts in the debtor's ledger:

    a) Debtor statement - Debtor statements and Debtor statements - Outstanding.

b) Age analysis - Balances detail, Balances detail history (open item) and Balances reports.

c) Listing - Contacts, Listing, List delivery address, List postal address, List details, Tax and Company registration numbers and the Credit control listing (Credit limit vs Current balance and Available balances as at the date and time of printing) report.

d) Print labels - Postal and Delivery address labels.

e) Transactions - Transactions - Open item, Transactions - Standard and Transactions - Extra details.

3. Creditors - The following reports are available to manage the accounts in the creditor's ledger:

a) Creditor remittance advises - Remittance advise and Remittance advise - Outstanding.

b) Age analysis - Balances detail, Balances detail history (open item) and Balances reports.

c) Listing - Contacts, Listing, List delivery address, List postal address, List details, Tax and Company registration numbers and the Credit control listing (Credit limit vs Current balance and Available balances as at the date and time of printing) report.

d) Print labels - Postal and Delivery address labels.

e) Transactions - Transactions - Open item, Transactions - Standard and Transactions - Extra details.

4. Sales - Various reports are available to analyse your sales documents. Print reports for, Debtors, Sales and Items reports for Invoices, Credit notes and Quotes.

5. Plugins - Price agreement report for the Price agreement plugin.

6. Stock - The following reports are available to manage the stock items:

a) Reorder - Stock Reorder Report to list only those stock items that needs to be reordered. The Current Stock Levels lists all the current stock levels.

b) Print Barcodes – Print the Barcode or the Yagoda barcodes.

c) Listing - Print lists of All selling prices report (Selling price 1 / 2 /3) and the Stock item listing report listing the Quantities Cost prices. You may select to print extra details for these reports. You may also print a list of tax classes.

d) Backorder - Print a list of Backorders.

e) Stock In / Out - The following two (2) reports:

i) Stock In / Out - Documents - Displays a summary of sales and purchase documents for each stock item. The details option will list and display the document dates and document numbers for each stock item.

ii) Stock In / Out - Displays a list of the stock items and the quantities in and out as well as the total prices. The details option will list and display the document dates and document numbers for each stock item.

7. Point-of-Sale - The Cash-up and Sales analysis report for the built-in point-of-sale (if you use point-of-sale). Sales and Receipt reports for the plugin point-of-sale systems (if you purchased and use the HorecaPOS or RetailPOS point-of-sale systems).

8. Contacts - Lists the details of all your contacts. To list only the contacts for debtor (customer / client) accounts, you need to print it in Debtors → Listing - Contacts. To list only the contacts for creditor (supplier / vendor) accounts, you need to print it in Creditors → Listing - Contacts.

9. Calendar - Print the appointments (events) (i.e. Appointment, Debtor Appointment, Creditor Appointment and Hours) that was scheduled in the Calendar / Planner.

10. Batch entry - Print the transactions of posted invoices, credit notes purchase and supplier return documents as well as posted batch transactions (i.e. sales journal, purchase journal, payments journals, receipts journals, general journals, etc.).

11. Purchases - Various reports are available to analyse your purchase documents. Print Graphs, Creditors, Purchases and Items reports for Purchase and Supplier return documents as well as Orders.

12. Company info -

    - Bank accounts List the details of the company bank accounts details "List Bank accounts" for up to two (2) bank accounts as entered / edited in the Company info (Setup ribbon).

    - Company info – Information – Lists the details of the following:

        § Information - Document heading and messages (up to 3 lines) as entered in the Documents setup (Setup ribbon) for each of the Sales documents (i.e. Invoices, Credit notes and Quotes tabs) as well as Purchase documents (i.e. Purchases, Supplier returns and Orders tabs). This information is standard and will be printed on all documents.

        § Global statement message (up to 3 lines) as entered on the Statement setup tab on Documents setup (Setup ribbon). This information will print standard on all

Statements (Reports → Debtors – Outstanding (Reports ribbon)). This is in addition to the specific messages (up to 4 lines) that can be entered in the Delivery address tab individual debtor accounts (Debtors (Default ribbon)).

§ Selling price descriptions – The descriptions of Selling price 1, Selling price 2 and Selling price 3 as entered in the Selling price descriptions fields (Stock information - Setup ribbon).

§ Cost of Sales –

- Create Cost of Sales
  - Yes - Cost of Sales is activated.
  - No - Cost of Sales is not activated.
- Average cost
  - Yes – Average Cost of Sales is activated.
  - No – Latest Cost of Sales is activated.

13. Currencies - The Currencies report will list the currencies (added / edited in the Setup → Currencies menu on the Setup ribbon).

    You may process Multi-currency documents (i.e. invoices, credit notes and quotes for debtors (customers / clients) or purchases, supplier returns and orders for creditors (suppliers).

    You may (once currency or currencies are added) select a currency when processing documents. The currency will be printed in the document layout files.

14. Documents - Lists your documents, such as invoices, credit notes, purchases, supplier returns documents, orders and quotes or a selection of documents or for a selected period.

15. Sales analysis - You may print reports for five (5) reporting groups (i.e. Debtor group 1, Debtor group 2, Document group 1, Document group 2 and Salespersons) for each of your sales document types (i.e. Invoices, Credit notes and Quotes). You may also print a Sales analysis report for each of these five (5) reporting groups which includes both posted Invoices and Credit notes.

    a) Sales documents for each document type (i.e. Invoices, Credit notes and Quotes) - You may print reports for five (5) reporting groups (i.e. Debtor group 1, Debtor group 2, Document group 1, Document group 2 and Salespersons).

    b) Invoices and Credit notes - You may print reports for five (5) reporting groups (i.e. Creditor

group 1, Creditor group 2, Document group 1, Document group 2 and Salespersons).

c) Sales per product - Stock group 1 and Stock group 2 are also available to analyse the sales (invoices) and returns (credit notes of trading stock items (default stock item type).

16. Tax - If you are registered as a VAT/GST/Sales Tax vendor, you need to print and view reports for a specific period for all your Tax (VAT/GST/Sales Tax) or for a specific tax code such as Input VAT/GST/Sales Tax, Output VAT/GST/Sales Tax, Zero-rated VAT/GST/Sales Tax, etc.

17. Purchase analysis -

a) Purchase documents for each document type (i.e. Purchases, Supplier returns and Orders) - You may print reports for five (5) reporting groups (i.e. Creditor group 1, Creditor group 2, Document group 1, Document group 2 and Salespersons).

b) Purchase and Supplier return documents - You may print reports for five (5) reporting groups (i.e. Creditor group 1, Creditor group 2, Document group 1, Document group 2 and Salespersons).

c) Purchases per Product - Stock group 1 and Stock group 2 are also available to analyse the purchases and returns for trading stock items (default stock item type).

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Ledger (Reports menu)

The following reports are available to manage the accounts in the general ledger:



1. Budget - The Budget vs actual (realization - 3 periods) report lists the Income and Expense account balances and budget figures for three (3) periods as comparative figures.

2. Listing - This report will list all accounts which are added or edited in Setup → Accounts.

3. Transactions - The following three (3) reports are available:

    a) Ledger transactions - Lists all the transactions in documents and journals which are posted (updated) to the ledger.

    b) General ledger transactions - Standard report lists all the transactions in documents and journals which are posted (updated) to the ledger.

    c) General ledger transactions - Extra details report is similar to the General ledger transactions - Standard report, but displays extra details of the Contra accounts (i.e. Account code, Account description, Contra account code and Description as well as the Tax account code and Description). For example, " *C000005 ABC-Office Sup,T860020, Input VAT-Standard rate - 15%* ", etc.

"Contra Accounts D1ABGRE Mr. AB Green,T860010 Output VAT - 15%

Created with the Standard Edition of HelpNDoc: Why Microsoft Word Isn't Cut Out for Documentation: The Benefits of a Help Authoring Tool

Budget vs actual (Reports menu)

The "*Budget v/s realisation 3 periods*" report lists the Income and Expense account balances and budget figures for three (3) periods as comparative figures.

Only the transactions in documents and batches which are posted (updated) to the ledger will be included in this report.

Budget figures are entered and edited in the following options:

1. Reports ribbon - Budgets.
2. Setup ribbon - Setup → Accounts menu (Budget tab).

If you have activated Cost centres and have entered the budget figures for Cost centres, you may select (tick) the Cost centres to print this report for your Cost centres.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Budget vs actual report options

To print a Budget vs actual report:

1. On the Reports ribbon, select Reports → Ledger → Budget.



2. Select the following options:

   a) Period - Select up to three (3) periods on the Per period tabs. You may click on the Free selection tab to select a specific date or a range of dates to include balances and budget figures in the report.

   b) Include zero balances - If this option is not selected (not ticked), it will list only the expense and income accounts which has balances and/or budget figures. Tick this option to include all accounts including those with no actual transactions and/or budget figures).

   c) Balances - If this option is not selected (not ticked), it will list the expense and income accounts which has balances and/or budget figures. Tick this option to show only the actual transactions totals and/or budget totals of expense and income accounts for the selected period or dates.

   d) Cost centre 1 - Cost centre 1 will be listed if you have activated Cost centres and created Cost Group 1 (Setup → Groups). You may select any of these Cost centres, to include in the report.

   e) Cost centre 2 - Cost centre 2 will be listed if you have activated Cost centres and created Cost

Group 2 (Setup → Groups). You may select any of these Cost centres, to include in the report.

3. Click on the OK button.

Printed : Budget vs actual (realisation - 3 periods) report

View the "*Budget v/s realisation 3 periods*" report:



The details is as follows:

1. Header section - Report name and Periods as selected on the Periods in the Report parameters screen.

2. Expenses - A list of the accounts (created as Income and Expense account type and linked to the Expenses Group / Financial category). If the Include zero balances field is selected (ticked), all expense accounts will be listed (including those accounts with no actual transactions and or budget figures. If the Balances field is selected (ticked), only the Total - *Expenses will be displayed.

3. Income - A list of the accounts (created as Income and Expense account type and linked to the Income Group / Financial category). If the Include zero balances field is selected (ticked), all income accounts will be listed (including those accounts with no actual transactions and or budget figures). If the

Balances field is selected (ticked), only the Total - *Income will be displayed.

4. Totals -

   a) Net Profit / Net Loss: Actual - This is the total of the Expenses minus the Income totals for posted batches and documents. A negative figure indicates a Net Profit and a positive figure displays a Net Loss for the selected periods (dates).

   b) Net Profit / Net Loss: Budget - This is the total of the Expenses minus the Income totals for the budget figures as entered / edited in Setup → Accounts. A negative figure indicates a Net Profit and a positive figure displays a Net Loss for the selected periods (dates).

   c) Net Profit / Net Loss: Actual - Budget - This is the total of the Net Profit / Net Loss: Actual minus the Net Profit / Net Loss: Budget totals. A negative figure indicates that the posted batches and documents exceeds (overspend) the budget figures for the selected periods (dates). A positive figure indicates that the posted batches and documents is less than the budget figures (available) for the selected periods (dates).

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Ledger - Listing (Reports menu)

This report will list all accounts which are added or edited in Setup → Accounts.

Chart of accounts report options

To print a Ledger listing (Chart of Accounts) report:

1. On the Reports ribbon, select Reports → Ledger → Listing.



2. Select the following:

    a) From account ... To... - Select the accounts to include in the report.

    b) Sequence - Select "*Account, Description, Type, Reporting group 1*" or "*Reporting group 2*".

3. Click on the OK button.

Printed : Chart of accounts report

An example of the "*Chart of accounts*" (General ledger accounts) ("*Account*" sequence), is as follows:



Chart of accounts

Chart of accounts

From account: G010000 To: G999000 **Sequence: Account**

Code	Description	Reporting group 1	Reporting group 2	Type	Open item	Disabled
*G010000	Sales	Income	Income2	Inc/ Exp	No	No
*G100000	Cost of sales	Income	Income2	Inc/ Exp	No	No
*G200000	Bank charges	Expenses	Expenses2	Inc/ Exp	No	No
*G205000	Depreciation	Expenses	Expenses2	Inc/ Exp	No	No
*G210000	Motor vehicle expenses	Expenses	Expenses2	Inc/ Exp	No	No
*G210010	Fuel and oil	Expenses	Expenses2	Inc/ Exp	No	No
*G210020	Maintenance	Expenses	Expenses2	Inc/ Exp	No	No
*G210030	Repairs	Expenses	Expenses2	Inc/ Exp	No	No
*G215000	Maintenance of tools	Expenses	Expenses2	Inc/ Exp	No	No
*G220000	Rent	Expenses	Expenses2	Inc/ Exp	No	No
*G225000	Salaries and wages	Expenses	Expenses2	Inc/ Exp	No	No
*G230000	Stationery	Expenses	Expenses2	Inc/ Exp	No	No
*G235000	Sundry expenses	Expenses	Expenses2	Inc/ Exp	No	No
G505000	Capital	Capital	Capital2		No	No
G510000	Retained income	Capital	Capital2		No	No
G520000	Installment agreements	Longterm liabilities	Longtermliabilities2		No	No
G600000	Furniture & fittings - Net value	Fixed assets	Fixed assets 2		No	No
G600010	Furniture & fittings @ cost	Fixed assets	Fixed assets 2		No	No
G600020	Furniture & fittings -Acc. deprec.	Fixed assets	Fixed assets 2		No	No
G610000	Motor vehicles - Net value	Fixed assets	Fixed assets 2		No	No
G610010	Motor vehicles @ cost	Fixed assets	Fixed assets 2		No	No
G610020	Motor vehicles -Accum depreciation	Fixed assets	Fixed assets 2		No	No
G700000	Debtors control	Current assets	Current assets2		No	No
G735000	POS - Transfer	Current assets	Current assets2		No	No
G740000	POS - Till	Current assets	Current assets2		No	No
G745000	POS - Payment	Current assets	Current assets2		No	No
G750000	Stock control	Current assets	Current assets2		No	No
B810000	ABC - Bank	Current assets	Current assets2	Bank account	No	No
B820000	Petty cash	Current assets	Current assets2	Bank account	No	No
B830000	XYZ-Bank	Current assets	Current assets2	Bank account	No	No
G850000	VAT - Control - 14%	Current liabilities	Current liabilities 2		No	Yes
T850010	Output VAT - 14%	Current liabilities	Current liabilities 2	Tax account	No	Yes
T850020	Input VAT - Standard rate - 14%	Current liabilities	Current liabilities 2	Tax account	No	Yes
T850030	Input VAT - Capital goods - 14%	Current liabilities	Current liabilities 2	Tax account	No	Yes
T850040	Zero-rated VAT - 0%	Current liabilities	Current liabilities 2	Tax account	No	Yes
G850100	VAT - Payment - 14%	Current liabilities	Current liabilities 2		No	Yes
G860000	VAT - Control - 15%	Current liabilities	Current liabilities 2		No	No
T860010	Output VAT - 15%	Current liabilities	Current liabilities 2	Tax account	No	No
T860020	Input VAT - Standard rate - 15%	Current liabilities	Current liabilities 2	Tax account	No	No
T860030	Input VAT - Capital goods -15%	Current liabilities	Current liabilities 2	Tax account	No	No
T860040	Zero-rated VAT - 0%	Current liabilities	Current liabilities 2	Tax account	No	No
G860100	VAT - Payment - 15%	Current liabilities	Current liabilities 2		No	No
G900000	Creditors control	Current liabilities	Current liabilities 2		No	No
G999000	Suspense	Current liabilities	Current liabilities 2		No	No

The details are as follows:

1. Account code - The prefixes is as follows:

    a) G - General ledger account - If the Account code is prefixed with an asterisk (*), it is an Income / Expense account type and will be reported on the Income statement. All other accounts will be reported in the Balance sheet.

    b) B - Bank account - These accounts need to be linked to its own Payments and Receipts batch.

    c) T - Tax account - These accounts contains the Tax rate for Output and Input tax. These accounts need to match your VAT/GST/Sales Tax return form's codes.

2. Type - This will indicate the type of account, i.e. Income / Expenses, Bank account and Tax account.

The Chart of Accounts includes the following three (3) important control accounts. These three (3) accounts need to be linked to the correct reporting groups, i.e.

Retained income / earnings (Capital)

Debtor's control (Current assets)

Creditor's control (Current liabilities)

3. Open item - By default, all accounts are not open item. If the *Open item account* field is set to Yes, you may use the feature to link debit and credit transactions for these accounts.

4. Disabled - If an account cannot be deleted (e.g. contains transactions and balances) and the account is no longer required, the Account may be set to "*Disabled*" in the "*Status*" field of Setup → Accounts. This will nor allow any transactions to be selected when processing transactions. Disabled (inactive) accounts are included in reports.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Ledger - Transactions (Reports menu)

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

Ledger - Transactions (Reports menu)

The Ledger transactions report lists all the transactions in documents and batches which are posted (updated) to the ledger.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

General ledger - Transactions report options

To print General ledger transactions reports:

1. On the Reports ribbon, select Reports → Ledger → Transactions.

2. Select the "*Transactions*".



3. Select the following options:

   a) Report type - Select the "*Transactions*" report.

   b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

   c) From account / To account - Select a general ledger account or a range of general ledger accounts, to include in the report.

   d) Sequence - Select "*Account*" to print the report by account code or "*Description*" to print the report by account description (name).

   e) Include opening balances - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include opening balances (closing balances before the selected periods / dates).

> *Opening Balances will not be displayed for Income and Expense account types. It will only be displayed for Balance sheet accounts.*

f) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

4. Click on the OK button.

Printed : General ledger - Transactions report

View the "*General ledger - Transactions*" report:

Page 1 -



Transactions

General ledger - Transactions

From account: G010000 To: G999000

Period: 2022/04/01 - 2022/04/30

Sequence: Account
Include opening balances: Yes
New page per account: No

G010000 Sales

Ref. no.	Date	Description	Amount	Cum	Cum total
IN000005	2022/04/07	Drill press	-1,000.00	-1,000.00	-1,000.00
IN000006	2022/04/09	Compressor	-3,000.00	-4,000.00	-4,000.00
IN000007	2022/04/10	Compressor	-1,500.00	-5,500.00	-5,500.00
IN000008	2022/04/11	Drill press	-2,000.00	-7,500.00	-7,500.00
	Total / Balance			-7,500.00	

G100000 Cost of sales

Ref. no.	Date	Description	Amount	Cum	Cum total
IN000005	2022/04/07	*COST OF SALES /D-101	500.00	500.00	-7,000.00
IN000006	2022/04/09	*COST OF SALES /C-102	2,000.00	2,500.00	-5,000.00
IN000007	2022/04/10	*COST OF SALES /C-103	1,000.00	3,500.00	-4,000.00
IN000008	2022/04/11	*COST OF SALES /D-102	1,000.00	4,500.00	-3,000.00
	Total / Balance			4,500.00	

G505000 Capital

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/03/01	OPENBAL BAL	-16,500.00	-16,500.00	-19,500.00
	Total / Balance			-16,500.00	

G510000 Retained income

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/03/31	OPENBAL RET	-11,105.00	-11,105.00	-30,605.00
	Total / Balance			-11,105.00	

G600010 Furniture & fittings @ cost

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/03/15	OPENBAL BAL	4,807.00	4,807.00	-25,798.00
	Total / Balance			4,807.00	

Page 2 -



General ledger - Transactions

From account: G010000 To: G999000

Period: 2022/04/01 - 2022/04/30

Sequence: Account
Include opening balances: Yes
New page per account: No

G600020 Furniture & fittings -Acc. deprec.

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/03/31	OPENBAL BAL	-350.00	-350.00	-26,148.00
	Total / Balance			-350.00	

G610010 Motor vehicles @ cost

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/02/28	OPENBAL BAL	5,000.00	5,000.00	-21,148.00
	Total / Balance			5,000.00	

G610020 Motor vehicles -Accum. depreciation

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/03/31	OPENBAL BAL	-600.00	-600.00	-21,748.00
	Total / Balance			-600.00	

G700000 Debtors control

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/03/16	OPENBAL DEB	10,300.00	10,300.00	-11,448.00
IN000005	2022/04/07	1MDAVI Mr. Mike Davies Invoice /D-101	1,150.00	11,450.00	-10,298.00
IN000006	2022/04/09	1ROGSM Mr. Roger Smith Invoice /C-102	3,450.00	14,900.00	-6,848.00
IN000007	2022/04/10	1MDAVI Mr. Mike Davies Invoice /C-103	1,725.00	16,625.00	-5,123.00
IN000008	2022/04/11	1ROGSM Mr. Roger Smith Invoice /D-102	2,300.00	18,925.00	-2,823.00
	Total / Balance			18,925.00	

G750000 Stock control

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/02/28	OPENBAL BAL	6,500.00	6,500.00	3,677.00
PU000003	2022/04/05	Drill press	1,500.00	8,000.00	5,177.00
PU000004	2022/04/06	Compressor	2,000.00	10,000.00	7,177.00
IN000005	2022/04/07	*COST OF SALES/D-101	-500.00	9,500.00	6,677.00
IN000006	2022/04/09	*COST OF SALES/C-102	-2,000.00	7,500.00	4,677.00
IN000007	2022/04/10	*COST OF SALES/C-103	-1,000.00	6,500.00	3,677.00
IN000008	2022/04/11	*COST OF SALES/D-102	-1,000.00	5,500.00	2,677.00
	Total / Balance			5,500.00	

B810000 ABC - Bank

Ref. no.	Date	Description	Amount	Cum	Cum total
OPENBAL	2022/03/31	OPENBAL BAL	8,423.00	8,423.00	11,100.00
	Total / Balance			8,423.00	

Page 3 (Last page) -



The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

> *If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.*

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description).

4. Detail - List the transaction details for each account.

    a) Reference - The reference number of the document (i.e. Invoices, Credit notes, Purchases and Supplier returns) or the reference number entered in the reference column on the Batch entry

screen.

> *If the "Include opening balances" is selected, the Opening balances will be included.*
>
> *In this example, it will display as follows:*
>
> - *All balance sheet accounts "OPENBAL BAL"*
> - *Debtors control account "OPENBAL DR"*
> - *Creditors control account "OPENBAL CR"*
> - *Retained earnings / income "OPENBAL RET"*

b) Date - The date of the transaction or document.

c) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. Invoices, Credit notes, Purchases and Supplier returns) or the description entered in the description column on the Batch entry screen.

d) Amount - The debit or credit transaction amount.

e) Cum - The accumulative total of the transactions included in the account.

f) Cum total - The accumulative total of the transactions and accounts included in the report.

5. Footer - Groups - Total / Balance - Displays the total / closing balance for each account.

6. Page Footer - List the following:

a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. ... \books\BOOKSNAME\Books.fdb)

b) System user and osFinanacials user (Setup → Access control).

c) Printed: The date and time of the system (computer) on which the report is printed.

d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Write EPub books for the iPad

Ledger - Transactions - Standard / Extra details (Reports menu)

The "*General ledger transactions - Standard*" report lists all the transactions in documents and batches which are posted (updated) to the ledger.

The "*General ledger transactions - Extra details*" report is similar to the "*General ledger transactions - Standard*" report, but displays extra details of the Contra accounts (i.e. Account code, Account description, Contra account code and Description as well as the Tax account code and Description). For example;

"Contra Accounts D1ABGRE Mr. AB Green,T860010 Output VAT - 15%

These reports does not include any opening balances for Income and Expense accounts reported on the Income statement.

These reports will include opening balances for all other ledger accounts (closing balances before for the selected periods / dates).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

General ledger transactions - Standard / Extra details report options

To print General ledger transactions - Standard / Extra details reports:

1. On the Reports ribbon, select Reports → Ledger → Transactions.
2. Select the "*General ledger transactions - Standard*" or "*General ledger transactions - Extra details*".



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

   b) From account / To account - Select a general ledger account or a range of general ledger accounts, to include in the report.

   c) Include zero balances - If this option is not selected (not ticked), it will list only the transactions for accounts which has transactions and/or balances. Tick this option to include opening balances (closing balances before the selected periods / dates).

   > *Opening and Closing balances will not be displayed for Income and Expense account types. It will only be displayed for Balance sheet accounts.*

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

   > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

e) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

3. Click on the OK button.

Printed : General ledger transactions - Standard report

View the "*General ledger transactions - Standard*" report:

Page 1 -



General ledger transactions - Standard

General ledger transactions - Standard

Period: 2022/04/01 - 2022/04/30

From: G010000 — New page per account: No
To: G999000 — Include zero balances: No

***G010000 Sales** — 2022/04/01 — 0.00

Date	Reference	Description	Debit	Credit	Cum
2022/04/07	IN000005	Drill press		1,000.00	-1,000.00
2022/04/09	IN000006	Compressor		3,000.00	-4,000.00
2022/04/10	IN000007	Compressor		1,500.00	-5,500.00
2022/04/11	IN000008	Drill press		2,000.00	-7,500.00

Total: *G010000 Sales — 0.00 — 7,500.00

2022/04/30 — -7,500.00

***G100000 Cost of sales** — 2022/04/01 — 0.00

Date	Reference	Description	Debit	Credit	Cum
2022/04/07	IN000005	*COST OF SALES/D-101	500.00		500.00
2022/04/09	IN000006	*COST OF SALES/C-102	2,000.00		2,500.00
2022/04/10	IN000007	*COST OF SALES/C-103	1,000.00		3,500.00
2022/04/11	IN000008	*COST OF SALES/D-102	1,000.00		4,500.00

Total: *G100000 Cost of sales — 4,500.00 — 0.00

2022/04/30 — 4,500.00

G505000 Capital			2022/04/30	-16,500.00
G510000 Retained income			2022/04/30	-11,105.00
G600010 Furniture & fittings @ cost			2022/04/30	4,807.00
G600020 Furniture & fittings-Acc. deprec.			2022/04/30	-350.00
G610010 Motor vehicles @ cost			2022/04/30	5,000.00
G610020 Motor vehicles -Accum. depreciation			2022/04/30	-600.00
G700000 Debtors control			2022/04/01	10,300.00

Date	Reference	Description	Debit	Credit	Cum
2022/04/07	IN000005	Invoice/D-101	1,150.00		11,450.00
2022/04/09	IN000006	Invoice/C-102	3,450.00		14,900.00
2022/04/10	IN000007	Invoice/C-103	1,725.00		16,625.00
2022/04/11	IN000008	Invoice/D-102	2,300.00		18,925.00

Total: G700000 Debtors control — 8,625.00

2022/04/30 — 18,925.00

G750000 Stock control — 2022/04/01 — 6,500.00

Page 2 -



General ledger transactions - Standard

General ledger transactions - Standard

Period: 2022/04/01 - 2022/04/30

From: G010000 New page per account: No
To: G999000 Include zero balances: No

Date	Reference	Description	Debit	Credit	Cum
2022/04/05	PU000003	Drill press	1,500.00		8,000.00
2022/04/06	PU000004	Compressor	2,000.00		10,000.00
2022/04/07	IN000005	*COST OF SALES/D-101		500.00	9,500.00
2022/04/09	IN000006	*COST OF SALES/C-102		2,000.00	7,500.00
2022/04/10	IN000007	*COST OF SALES/C-103		1,000.00	6,500.00
2022/04/11	IN000008	*COST OF SALES/D-102		1,000.00	5,500.00
Total: G750000 Stock control			**3,500.00**	**4,500.00**	
				2022/04/30	**5,500.00**
B810000 ABC - Bank				**2022/04/30**	**8,423.00**
B820000 Petty cash				**2022/04/30**	**144.00**
T860010 Output VAT - 15%				**2022/04/01**	**-1,600.00**
Date	**Reference**	**Description**	**Debit**	**Credit**	**Cum**
2022/04/07	IN000005	Invoice /D-101		150.00	-1,750.00
2022/04/09	IN000006	Invoice /C-102		450.00	-2,200.00
2022/04/10	IN000007	Invoice /C-103		225.00	-2,425.00
2022/04/11	IN000008	Invoice /D-102		300.00	-2,725.00
Total: T860010 Output VAT - 15%			**0.00**	**1,125.00**	
				2022/04/30	**-2,725.00**
T860020 Input VAT - Standard rate -15%				**2022/04/01**	**861.00**
Date	**Reference**	**Description**	**Debit**	**Credit**	**Cum**
2022/04/05	PU000003	Purchases /4562	225.00		1,086.00
2022/04/06	PU000004	Purchases /3532	300.00		1,386.00
Total: T860020 Input VAT - Standard rate -15%			**525.00**	**0.00**	
				2022/04/30	**1,386.00**
T860030 Input VAT - Capital goods -15%				**2022/04/30**	**120.00**
G900000 Creditors control				**2022/04/01**	**-6,000.00**
Date	**Reference**	**Description**	**Debit**	**Credit**	**Cum**
2022/04/05	PU000003	Purchases /4562		1,725.00	-7,725.00
2022/04/06	PU000004	Purchases /3532		2,300.00	-10,025.00
Total: G900000 Creditors control				**4,025.00**	
				2022/04/30	**-10,025.00**

Printed : General ledger transactions - Extra details report

View the "*General ledger transactions - Extra details*" report:

Page 1 -


General ledger transactions - Extra details
General ledger transactions - Extra details
Period: 2022/04/01 - 2022/04/30
From: G010000
To: G999000
Include zero balances: No
New page per account: No
*G010000 Sales 2022/04/01 0.00
Date Reference no. Description Debit Credit Cum
2022/04/07 IN000005 Drill press 1,000.00 -1,000.00
Contra Accounts D1MDAVI Mr. Mike Davies, T860010 Output VAT - 15%
2022/04/09 IN000006 Compressor 3,000.00 -4,000.00
Contra Accounts D1ROGSM Mr. Roger Smith, T860010 Output VAT - 15%
2022/04/10 IN000007 Compressor 1,500.00 -5,500.00
Contra Accounts D1MDAVI Mr. Mike Davies, T860010 Output VAT - 15%
2022/04/11 IN000008 Drill press 2,000.00 -7,500.00
Contra Accounts D1ROGSM Mr. Roger Smith, T860010 Output VAT - 15%
Total: *G010000 Sales 0.00 7,500.00
2022/04/30 -7,500.00
*G100000 Cost of sales 2022/04/01 0.00
Date Reference no. Description Debit Credit Cum
2022/04/07 IN000005 *COST OF SALES/D-101 500.00 500.00
Contra Accounts G750000 Stock control
2022/04/09 IN000006 *COST OF SALES/C-102 2,000.00 2,500.00
Contra Accounts G750000 Stock control
2022/04/10 IN000007 *COST OF SALES/C-103 1,000.00 3,500.00
Contra Accounts G750000 Stock control
2022/04/11 IN000008 *COST OF SALES/D-102 1,000.00 4,500.00
Contra Accounts G750000 Stock control
Total: *G100000 Cost of sales 4,500.00 0.00
2022/04/30 4,500.00
G505000 Capital 2022/04/30 -16,500.00
G510000 Retained income 2022/04/30 -11,105.00
G600010 Furniture & fittings @ cost 2022/04/30 4,807.00
G600020 Furniture & fittings - Acc. deprec. 2022/04/30 -350.00
G610010 Motor vehicles @ cost 2022/04/30 5,000.00
G610020 Motor vehicles - Accum. depreciation 2022/04/30 -600.00

Page 2 -



General ledger transactions - Extra details

Period: 2022/04/01 - 2022/04/30

From: G010000 — **Include zero balances: No**
To: G999000 — **New page per account: No**

G700000 Debtors control — 2022/04/01 — **10,300.00**

Date	Reference no.	Description	Debit	Credit	Cum
2022/04/07	IN000005	Invoice /D-101	1,150.00		11,450.00
Contra Accounts	D1MDAVI Mr. Mike Davies, G010000 Sales, T860010 Output VAT - 15%				
2022/04/09	IN000006	Invoice /C-102	3,450.00		14,900.00
Contra Accounts	D1ROGSM Mr. Roger Smith, G010000 Sales, T860010 Output VAT - 15%				
2022/04/10	IN000007	Invoice /C-103	1,725.00		16,625.00
Contra Accounts	D1MDAVI Mr. Mike Davies, G010000 Sales, T860010 Output VAT - 15%				
2022/04/11	IN000008	Invoice /D-102	2,300.00		18,925.00
Contra Accounts	D1ROGSM Mr. Roger Smith, G010000 Sales, T860010 Output VAT - 15%				

Total: G700000 Debtors control — **8,625.00**

2022/04/30 — **18,925.00**

G750000 Stock control — 2022/04/01 — **6,500.00**

Date	Reference no.	Description	Debit	Credit	Cum
2022/04/05	PU000003	Drill press	1,500.00		8,000.00
Contra Accounts	C2AONES A-ONE Suppliers, T860020 Input VAT - Standard rate -15%				
2022/04/06	PU000004	Compressor	2,000.00		10,000.00
Contra Accounts	C2BESTS BEST Suppliers, T860020 Input VAT - Standard rate -15%				
2022/04/07	IN000005	*COST OF SALES/D-101		500.00	9,500.00
Contra Accounts	G100000 Cost of sales				
2022/04/09	IN000006	*COST OF SALES/C-102		2,000.00	7,500.00
Contra Accounts	G100000 Cost of sales				
2022/04/10	IN000007	*COST OF SALES/C-103		1,000.00	6,500.00
Contra Accounts	G100000 Cost of sales				
2022/04/11	IN000008	*COST OF SALES/D-102		1,000.00	5,500.00
Contra Accounts	G100000 Cost of sales				

Total: G750000 Stock control — **3,500.00** — **4,500.00**

2022/04/30 — **5,500.00**

B810000 ABC - Bank — 2022/04/30 — **8,423.00**

B820000 Petty cash — 2022/04/30 — **144.00**

T860010 Output VAT - 15% — 2022/04/01 — **-1,600.00**

Date	Reference no.	Description	Debit	Credit	Cum
2022/04/07	IN000005	Invoice /D-101		150.00	-1,750.00
Contra Accounts	D1MDAVI Mr. Mike Davies, G010000 Sales				
2022/04/09	IN000006	Invoice /C-102		450.00	-2,200.00
Contra Accounts	D1ROGSM Mr. Roger Smith, G010000 Sales				

Page 3 -



General ledger transactions - Extra details

General ledger transactions - Extra details

Period: 2022/04/01 - 2022/04/30

From: T010000 — **Include zero balances: No**
To: T999000 — **New page per account: No**

Date	Reference no.	Description	Debit	Credit	Cum
2022/04/10	IN000007	Invoice /C-103		225.00	-2,425.00
Contra Accounts	D1MDAVI Mr. Mike Davies,G010000 Sales				
2022/04/11	IN000008	Invoice /D-102		300.00	-2,725.00
Contra Accounts	D1ROGSM Mr. Roger Smith,G010000 Sales				
Total: T860010 Output VAT - 15%			**0.00**	**1,125.00**	
				2022/04/30	**-2,725.00**
T860020 Input VAT - Standard rate -15%				**2022/04/01**	**861.00**
Date	Reference no.	Description	Debit	Credit	Cum
2022/04/05	PU000003	Purchases /4562	225.00		1,086.00
Contra Accounts	C2AONES A-ONE Suppliers,G750000 Stock control				
2022/04/06	PU000004	Purchases /3532	300.00		1,386.00
Contra Accounts	C2BESTS BEST Suppliers,G750000 Stock control				
Total: T860020 Input VAT - Standard rate -15%			**525.00**	**0.00**	
				2022/04/30	**1,386.00**
T860030 Input VAT - Capital goods -15%				**2022/04/30**	**120.00**
G900000 Creditors control				**2022/04/01**	**-6,000.00**
Date	Reference no.	Description	Debit	Credit	Cum
2022/04/05	PU000003	Purchases /4562		1,725.00	-7,725.00
Contra Accounts	C2AONES A-ONE Suppliers,G750000 Stock control,T860020 Input VAT - Standard rate - 15%				
2022/04/06	PU000004	Purchases /3532		2,300.00	-10,025.00
Contra Accounts	C2BESTS BEST Suppliers,G750000 Stock control,T860020 Input VAT - Standard rate - 15%				
Total: G900000 Creditors control				**4,025.00**	
				2022/04/30	**-10,025.00**

The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

> *If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.*

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description).

4. Detail - List the transaction details for each account.

    a) Reference - The reference number of the document (i.e. Invoices, Credit notes, Purchases and Supplier returns) or the reference number entered in the reference column on the Batch entry screen.

b) Date - The date of the transaction or document.

c) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. Invoices, Credit notes, Purchases and Supplier returns) or the description entered in the description column on the Batch entry screen.

d) Debit - The debit transaction amount.

e) Credit - The credit transaction amount.

f) Cum - The accumulative total of the transactions included in the account.

5. Footer - Groups - Total / Balance - Displays the total of the transactions and the closing balance for each account.

> *Closing balances will not be displayed for Income and Expense account types. It will only be displayed for Balance sheet accounts.*

6. Page Footer - List the following:

a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. ... \books\BOOKSNAME\Books.fdb)

b) System user and osFinancials user / TurboCASH user (Setup → Access control).

c) Printed: The date and time of the system (computer) on which the report is printed.

d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Debtors (Reports menu)

On the Reports ribbon, select Reports → Debtors.



The following reports are available to manage the accounts in the debtor's ledger:

1. Debtor statement – Debtor statements and Debtor statements - Outstanding.
2. Age analysis - Balances detail, Balances detail history (open item) and Balances reports. These reports offers different options of views to support the details of debtor statements.
3. Listing - Contacts, Listing, List delivery address, List postal address or List details, Tax and company registration numbers and the Credit control listing (Credit limit vs current balance and available balances as at the date and time of printing) report.
4. Print labels - Postal and delivery address labels.
5. Transactions - Transactions - Open item, Transactions - Standard and Transactions - Extra details.

Created with the Standard Edition of HelpNDoc: Produce electronic books easily

Debtor statements

The following debtor statements are available:

- Debtor statements - The statement will print all transactions. It does not use the Open item link.
- Debtor statements - Outstanding - This statement will print only the outstanding transactions. Transactions (e.g. invoices, etc. Transactions linked in the Open item link, will not be listed).

The credit transactions which are linked to specific debit transactions of the same value, will not be displayed. If a transaction for a different amount is linked to a specific transaction, only the outstanding

amount (difference) will be listed.

Before you wish to print Debtor statements, you may need to check the following:

- *Statement messages are entered correctly.*
- *Banking details of your company is entered in the Company info (Setup ribbon).*
- *That no outstanding transactions which is not linked in Open item processing.*

Debtor statements - Global messages

Enter global messages to print on all debtor statements:

1. On the Setup ribbon, select Documents setup.
2. Select the Statement setup tab.



3. Enter the message in up to 3 lines to display on the Debtor statements.
4. Click on the OK button.

Debtor statements - Messages for specific accounts

Enter statement messages for specific debtor accounts:

1. On the Default ribbon, select Debtors (F4).
2. Select the debtor (customer / client) account.
3. On the Delivery address tab, enter a message of up to 3 lines.
4. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Effortlessly Spot and Fix Problems in Your Documentation with HelpNDoc's Project Analyzer

Debtor statements (Reports menu)

The "*Debtor statement*" will print all transactions. It does not use Open item link.

The "*Debtor statement - Outstanding*" will print only the outstanding transactions. Transactions linked in the Open item link feature, will not be listed.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor statement options

To print Debtor statements:

1. On the Reports ribbon, select Reports → Debtors → Debtor statement.



2. Enter or select the date of the ageing.

3. Enter the number of days to display for the periods.

4. Select the Accounts to include in the Statements.

5. Click on the OK button.

Printed : Debtor statement



The information is as follows:

1. Header (Left) - Debtor Information as entered / edited on the debtor account.

2. Header (Right) - Company info as entered / edited on Setup → Company info.

3. Statement to - The date as entered (selected) on the Parameters screen. The periods number of days specified on the parameters screen is displayed. The outstanding totals for each period is displayed as a summary for the periods at the end of the transaction section.

4. Transactions - This displays the date, reference. description and amount for each transaction. The payment date for each transaction is the date of the transaction plus the number of days entered in

the Due days field on the Accounting information tab of the debtor account.

5. Credit limit - The amount as entered in the Credit limit field on the Accounting information tab of the debtor account. The Balance at is the current balance of the debtor account of all posted transactions and documents as at the date of printing of the Debtor Statements. The Available amount is calculated the Credit limit minus the Balance at amount as at the date of printing of the Debtor Statements.

6. Statement message - This consists of two (2) sections:

    a) Statement message (Left) - Up to three (3) lines as entered on the Delivery address tab of the debtor account.

    b) Statement message (Right) - Up to three (3) lines as entered on the Statement setup tab on Setup → Documents setup.

7. Due amount, Due date and Banking details - The amount payable and the date on which the payment is due. The Banking details as entered on the Setup → Company info will be displayed on the Debtor statement.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Debtor statements - Outstanding (Reports menu)

The "*Debtor statement - Outstanding*" will print only the outstanding transactions. Transactions linked in the Open item link, will not be listed. The transactions which is partially linked, will display the outstanding amount.

The debtor (customer / client) will see only the Invoices that is not settled in full or at all.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor statement - Outstanding options

To print Debtor statements - Outstanding:

1. On the Reports ribbon, select Reports → Debtors → Debtor statement.

2. Select "*Debtor statement - Outstanding*".



3. Enter or select the date of the ageing.

4. Enter the number of days to display for the periods.

5. Select the Accounts to include in the Statements.

6. Click on the OK button.

Printed : Debtor statement - Outstanding



Debtor statement - Outstanding

Mr. AB Green
PO Box 1111
Lakeside
Johannesburg
2122
South Africa

Account no. : D1ABGRE
Contact : Andrew Green
Tax reg. no. : 111111111
Company reg. no. : 222222222
Telephone 1 : (011)314-9997
Telephone 2 : (011)314-9998
Fax : (011)314-9999

E-mail : green@hismail.com
Website : osfinancials.org/en/

Handyman Hardware Store
27 Olifants Road
Emmarentia
Johannesburg
2195

Phone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Company reg. no.: 336012345
Tax reg. no.: 446010111

Statement

Statement to: 2021/04/30
Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01
Due amount: 2,600.00
Due date: 2021/05/30

Date	Reference	Description	Amount	Outstanding	Payment date
2021/03/10	INV003	Paint - Exterior	1,150.00	300.00	2021/04/09
2021/03/13	IN000001	Invoice /AB-IN110	1,150.00	1,150.00	2021/04/12
2021/03/15	IN000003	Invoice /PH-101	1,150.00	1,150.00	2021/04/14

	Due amount	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	2,600.00	0.00	2,600.00	0.00

Credit limit:	30,000.00
Balance :	2,600.00
Available :	27,400.00

Statement message:

Please refer any queries to our accounts department	2.5% INTEREST WILL BE CHARGED ON ALL OVERDUE ACCOUNTS

Due amount:	**2,600.00**	**Handyman Hardware Store - Bank account:**	
Due date:	**2021/05/30**	Bank name:	ABC Bank
		Branch code:	123-999
		Bank account no.:	99-6666-6666

NOTE - In this example, INV001 of 1,150.00 is not displayed on the Debtor statement - Outstanding, since the payment of 2,000.00 is linked to that invoice.

The balance of 850.00 (payment of 2,000.00 - INV001 of 1150.00) is linked to invoice INV003 - 1150.00. The outstanding amount is 300.00 for INV003.

The information is as follows:

1. Header (Left) - Debtor Information as entered / edited on the debtor account.
2. Header (Right) - Company info as entered / edited on Setup → Company info.
3. Statement to - The date as entered (selected) on the Parameters screen. The periods number of days

specified on the parameters screen is displayed. The outstanding totals for each period is displayed as a summary for the periods at the end of the transaction section.

4. Transactions - This displays the date, reference. description and amount for each transaction. The payment date for each transaction is the date of the transaction plus the number of days entered in the Due days field on the Accounting information tab of the debtor account.

5. Credit limit - The amount as entered in the Credit limit field on the Accounting information tab of the debtor account. The Balance at is the current balance of the debtor account of all posted transactions and documents as at the date of printing of the Debtor Statements. The Available amount is calculated the Credit limit minus the Balance at amount as at the date of printing of the Debtor Statements.

6. Statement message - This consists of two (2) sections:

    a) Statement message (Left) - Up to three (3) lines as entered on the Delivery address tab of the debtor account.

    b) Statement message (Right) - Up to three (3) lines as entered on the Statement setup tab on Setup → Documents setup.

7. Due amount, Due date and Banking details - The amount payable and the date on which the payment is due. The Banking details as entered on the Setup → Company info will be displayed on the Debtor statement.

Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Debtors - Age analysis

The Debtor age analysis report allows you to analyse your transactions with each of your debtor (customer / client) accounts according to specified accounting periods. This could be a useful tool to manage outstanding amounts owed by debtors (customers / clients).

This report will display a break down of your debtor account balances for each of the specified periods for a selected debtor account, or a range of selected debtor (customer / client) accounts.

The Debtors → Age analysis - The Debtor age analysis provides the "*Balances detail*, *Balances detail history (open item)*" and "*Balances*" reports allows you to analyse the outstanding amounts your debtors (customers / clients) owes you in specified periods such as total, 30, 60 and 90 days, or more. These reports are essential for cash flow control. You may also wish to use this facility for credit control, to send

reminders to your debtors (customers / clients), to optimise your cash flow management.

Created with the Standard Edition of HelpNDoc: Quickly and Easily Convert Your Word Document to an ePub or Kindle eBook

Debtors - Age analysis - Balances detail

The Debtor age analysis report allows you to analyse your transactions with each of your debtor (customer / client) accounts according to specified accounting periods. This could be a useful tool to manage outstanding amounts owed by debtors (customers / clients). This Report will display a break down of your debtor account balances for each of the specified periods for a selected debtor account, or a range of selected debtor (customer / client) accounts.

The following reports are available:

- Balances detail - Displays the reference, date, amount and description for each transaction. The Total outstanding as at the Date of ageing is split to the number of days specified in up to 3 periods.
- Balances detail history (open item) - This is similar to the Balances detail report, but it displays the outstanding amount and TransactionID.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor age analysis - Balances detail report options

To print Debtor age analysis - Balances detail report:

1. On the Reports ribbon, select Reports → Debtors → Age analysis.
2. Select "*Balances detail*" (default).



3. Select the following options:

   a) Date of ageing - Select or enter a date to include the transactions on or before that date.

   b) Days overdue - Enter the number of days for period 1.

   c) Number of days overdue - Enter the number of days for period 2.

   d) From account ...To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

   e) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   f) Show transactions - If this option is not selected (not ticked), it will list only the balances. Tick this option to include the transactions.

   g) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details). You may select this option, if the for the balances or transactions (Show transactions option ticked or not).

   h) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Debtor age analysis - Balances detail report

View the "*Debtor age analysis - Balances detail*" ("*Show transactions*" option not selected) report:



Balances detail

Debtor age analysis - Balances detail

From account: D1ABGRE To: D1ROGSM

Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01

Sequence: Description
Show transactions: No
Show contact details: No
New page per account: No

Debtor group: Debtor group 1B

D1MDAVI Mr. Mike Davies	Open item: Yes			
	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	7,125.00	2,875.00	3,450.00	800.00
D1ROGSM Mr. Roger Smith	Open item: No			
	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	6,750.00	5,750.00	0.00	1,000.00
Total - Debtor group: Debtor group 1B	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	13,875.00	8,625.00	3,450.00	1,800.00

Debtor group: Debtor group 1C

D1MACDS MAC Shop Decor Specialists	Open item: No			
	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	2,450.00	0.00	2,450.00	0.00
D1ABGRE Mr. AB Green	Open item: Yes			
	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	2,600.00	0.00	2,600.00	0.00
Total - Debtor group: Debtor group 1C	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	5,050.00	0.00	5,050.00	0.00
Report total:	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	18,925.00	8,625.00	8,500.00	1,800.00

Printed : Debtor age analysis - Balances detail (Show transactions / Show contact details) report

View the "*Debtor age analysis - Balances detail*" ("*Show contact details*" and "*Show transactions*" options selected) report for a specific debtor *(customer / client)* account:



The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the debtor (customer / client) account.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

Debtors - Age analysis - Balances detail (open item)

The Debtor age analysis report allows you to analyse your transactions with each of your debtor (customer / client) accounts according to specified accounting periods. This could be a useful tool to manage outstanding amounts owed by debtors (customers / clients). This Report will display a break down of your debtor account balances for each of the specified periods for a selected debtor account, or a range of selected debtor (customer / client) accounts.

Balances detail history (open item) - Displays the reference, date, amount and description for each transaction. The Total outstanding as at the Date of ageing is split to the number of days specified in up to 3 periods.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor age analysis - Balances detail history (open item) report options

To print Debtor age analysis Balances detail history (open item) report:

1. On the Reports ribbon, select Reports → Debtors → Age analysis.
2. Select "*Balances detail history (open item)*".



3. Select the following options:
    a) Date of ageing - Select or enter a date to include the transactions on or before that date.
    b) Days overdue - Enter the number of days for period 1.
    c) Number of days overdue - Enter the number of days for period 2.
    d) From account ...To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.
    e) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

f) Show transactions - If this option is not selected (not ticked), it will list only the balances. Tick this option to include the transactions.

g) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details). You may select this option, if the for the balances or transactions (Show transactions option ticked or not).

h) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.

3. Click on the OK button.

Printed : Debtor age analysis - Balances detail history (open item) report

View the "*Debtor age analysis - Balances detail history (open item)*" ("*Show transactions*" option not selected) report:

Page 1 -


Balances detail history (open item)
Debtor age analysis - Balances detail history (open item)
From account: D1ABGRE To: D1ROGSM
Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01
Sequence: Description
Show transactions: No
Show contact details: No
New page per account: No
D1MDAVI Mr. Mike Davies
Open item: Yes
Total
7,125.00
Open item: Yes
Total
7,125.00
7,125.00
Period 1 (30) 2,875.00
Period 2 (30) 3,450.00
Period 3 (60) + 800.00
D1ROGSM Mr. Roger Smith
Open item: No
Total
6,750.00
Open item: No
Total
6,750.00
6,750.00
Period 1 (30) 5,750.00
Period 2 (30) 0.00
Period 3 (60) + 1,000.00
Total - Debtor group: Debtor group 1B
13,875.00
Period 1 (30) 2,875.00
Period 2 (30) 3,450.00
Period 3 (60) + 800.00
D1MACDS MAC Shop Decor Specialists
Open item: No
Total
2,450.00
Open item: No
Total
2,450.00
2,450.00
Period 1 (30) 0.00
Period 2 (30) 2,450.00
Period 3 (60) + 0.00
D1ABGRE Mr. AB Green
Open item: Yes
Total
2,600.00
Open item: Yes
Total
2,600.00
1,450.00
Period 1 (30) 0.00
Period 2 (30) 1,450.00
Period 3 (60) + 0.00
Total - Debtor group: Debtor group 1C
5,050.00
Period 1 (30) 5,750.00
Period 2 (30) 2,450.00
Period 3 (60) + 1,000.00

Page 2-


Balances detail history (open item)
Debtor age analysis - Balances detail history (open item)
From account: D1ABGRE To: D1ROGSM
Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01
Sequence: Description
Show transactions: No
Show contact details: No
New page per account: No
Report total:
18,925.00
Period 1 (30) 8,625.00
Period 2 (30) 5,900.00
Period 3 (60) + 1,800.00

Printed : Debtor age analysis - Balances detail history (open item) (Show transactions / Show contact details) report

View the "*Debtor age analysis - Balances detail history (open item)*" ("*Show contact details*" and "*Show transactions*" options selected) report for a specific debtor *(customer / client)* account:



Balances detail history (open item)

Debtor age analysis - Balances detail history (open item)

From account: D1ABGRE To: D1ROGSM

Period 1: 2021/04/30
Period 2: 2021/03/31
Period 3: 2021/03/01

Sequence: Description
Show transactions: Yes
Show contact details: Yes
New page per account: Yes

Debtor group: Debtor group 1C

D1ABGRE Mr. AB Green — **Total 2,600.00** — **Open item: Yes**

Reference	Date	Description	Amount	Outstanding	Batch id	Transaction id
INV001	2021/03/07	Paint - Exterior	1,150.00	1,150.00	10028	324
INV003	2021/03/10	Paint - Exterior	1,150.00	0.00	10028	326
IN000001	2021/03/13	Invoice /AB-N110	1,150.00	300.00	10039	379
IN000003	2021/03/15	Invoice /PH-101	1,150.00	0.00	10041	385
D5001	2021/03/16	Payment received - Thank you	-2,000.00	0.00	10032	337
Total			**2,600.00**	**1,450.00**		

Period 1 (30)	Period 2 (30)	Period 3 (60) +
0.00	1,450.00	0.00

Postal address	*Delivery address*	*Information*
PO Box 1111	*Green Street*	*Language : English*
Lakeside	*Lakeside*	*Contact : Andrew Green*
Johannesburg	*Johannesburg*	*Telephone 1 : (011) 314-9997*
2122	*2123*	*Telephone 2 : (011) 314-9998*
South Africa		*Fax : (011) 314-9999*
		E-mail : green@hismail.com
		Website : osfinancials.org/en/
		Company reg. no. : 222222222
		Tax reg. no. : 111111111

On this report, all the transactions (for the selected period) are listed. The outstanding amount will be displayed, in this example, as follows:

The payment of 2000,00 on 16 March 2021 is linked in the Open item as follows:

- *INV003 for 1,150.00 is fully settled - Outstanding = 0.00*
- *IN000001 for 1,150.00 is partially settled as the balance of the 2,000.00 i.e. 850.00 is linked to this invoice - Outstanding = 300.00.*
- *The full credit payment of 2,000.00 is linked to Invoices - Outstanding = 0.00*

The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the debtor (customer / client) account.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's Project Analyzer

Debtors - Age analysis - Balances

The "*Balances*" report is a similar report as the "*Balances detail*" report. This report will only list the balances for each ageing period.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor age analysis - Balances report options

To print Debtor age analysis - Balances report:

1. On the Reports ribbon, select Reports → Debtors → Age analysis.
2. Select "*Balances*".



3. Select the following options:
    a) Date of ageing - Select or enter a date to include the transactions on or before that date.
    b) Days overdue - Enter the number of days for period 1.

c) Number of days overdue - Enter the number of days for period 2.

d) From account ...To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

e) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

3. Click on the OK button.

Printed : Debtor age analysis - Balances report

View the "*Debtor age analysis - Balances*" report:



Balances

Debtor age analysis - Balances

From account: D1ABGRE To: D1ROGSM

Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01

Sequence: Description

Debtor group: Debtor group 1B

Code	Name	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
D1MDAVI	Mr. Mike Davies	7,125.00	2,875.00	3,450.00	800.00
D1ROGSM	Mr. Roger Smith	6,750.00	5,750.00	0.00	1,000.00
Total - Debtor group: Debtor group 1B		**13,875.00**	**8,625.00**	**3,450.00**	**1,800.00**

Debtor group: Debtor group 1C

Code	Name	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
D1MACDS	MAC Shop Decor Specialists	2,450.00	0.00	2,450.00	0.00
D1ABGRE	Mr. AB Green	2,600.00	0.00	2,600.00	0.00
Total - Debtor group: Debtor group 1C		**5,050.00**	**0.00**	**5,050.00**	**0.00**

Report total:	Total	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	18,925.00	**8,625.00**	**8,500.00**	**1,800.00**

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Debtors - Listing (Reports menu)

On the Reports ribbon, select Reports → Debtors → Listing.

The Debtor listing allows you to print the following seven (7) reports:

1. Contacts - This report will list the Name of the Contact, Telephone 1 / 2 and the debtor (customer / client) account code and name (description) linked to the contact. Sequence - will list the contacts by contact name.
2. Listing - This report will list the Account code, Name of the Debtor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.
3. List - Delivery address - This report will list the Account code, Name of the Debtor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.
4. List - Postal address - This report will list the Account code, Name of the Debtor (account description), Postal address, Telephone 1 / 2, Fax, E-mail Address and Website.
5. List details - This report will display the Contact details, Registration details, Banking details, Reporting details, Accounting terms and information for each debtor (customer / client) account.
6. Credit control listing (Credit limit vs Current balance) as at... - This report will list the Account code, Name of the Debtor (account description), Postal address, Telephone 1 / 2, Credit limit, Current balance and the Available balance as at the date and time of printing this report.
7. Tax and Company registration numbers - This report will list the Account code and Name (description), Telephone 1 and Tax Registration Number as well as the Company Registration Number for each of your debtor (customer / client) accounts.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

Debtor listing - Contacts (Reports menu)

The "*Debtor listing - Contacts*" report will list the Name of the Contact, Telephone 1 / 2 and the debtor (customer / client) account code and name (description) linked to the contact.

Debtor listing - Contacts report options

To print a Debtor - Listing - Contacts report:

1. On the Reports ribbon, select Reports → Debtors → Listing.
2. Select "*Contacts*".



3. Select the following:

   a) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

   b) Sequence - Select "*First Name, Name (Surname), Debtor code"* or "*Description*" to print the report details in the order (sort) in which you wish to display the data.

   c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Contacts list - Debtors report

View the "*Contact list - Debtors*" report:



Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Debtor listing (Reports menu)

The Debtor listing report will list the Account code, Name of the Debtor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.

Debtor listing - Listing report options

To print a Debtor listing - Listing report:

1. On the Reports ribbon, select Reports → Debtors → Listing.

2. Select "*Listing*".



3. Select the following:

   a) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

   b) Sequence - Select "*Debtor code* or *Description*" to print the report details in the order (sort) in which you wish to display the data.

   c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Debtor list report



Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Debtor listing - Delivery address (Reports menu)

The Debtor listing - Delivery address report will list the Account code, Name of the Debtor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.

Debtor - List delivery address report options

To print a Debtor - List delivery address report:

1. On the Reports ribbon, select Reports → Debtors → Listing.

2. Select "*List delivery address*".



3. Select the following:

    a) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

    b) Sequence - Select "*Debtor code*, *Description*, *Address 3* or *Postal code*" to print the report details in the order (sort) in which you wish to display the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Debtor list: Delivery address report



Created with the Standard Edition of HelpNDoc: Effortlessly Edit and Export Markdown Documents

Debtor listing - Postal address (Reports menu)

The Debtor listing - Postal address report will list the Account code, Name of the Debtor (account description), Postal address, Telephone 1 / 2, Fax, E-mail Address and Website.

Debtor - List postal address report options

To print a Debtor - List postal address report:

1. On the Reports ribbon, select Reports → Debtors → Listing.
2. Select "*List postal address*".



3. Select the following:

    a) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

    b) Sequence - Select "*Debtor code*, *Description*, *Address 3* or *Postal code*" to print the report details in the order (sort) in which you wish to display the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Debtor list: Postal address report



Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Debtor listing - List details (Reports menu)

The "*Debtor List - Details*" report will display the Contact details, Registration details, Banking details, Reporting details, Accounting terms and information for each debtor (customer / client) account.

Debtor - List details report options

To print a Debtor listing - List details report:

1. On the Reports ribbon, select Reports → Debtors → Listing.
2. Select "*List details*".



3. Select the following:

    a) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

    b) Sequence - Select "*Debtor code*, *Description*, *Reporting group 1* or *Reporting group 2*" to print the report details in the order (sort) in which you wish to display the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Debtor list - Details report



The List details report will display the following information:

1. Contact details - Contactperson, Telephone 1 / 2, Fax, E-Mail, Website, Postal address, Delivery address and Language of the debtor (customer / client).

2. Registration details - Company Registration number and Tax registration number.

3. Banking details - Bank account type, Name of Bank account, Bank account number and Branch code.

4. Reporting details - Reporting group 1 / 2, Layout file 1 (Invoices), Layout file 2 (Credit notes) and Layout file 3 (Quotes). If no layout files are selected, the documents will be printed for the global settings in Setup → Documents setup.

5. Accounting terms and information - Statement message, Credit limit, Monthly interest rate, Customer discount rate, Due days (payment terms), account settings (i.e. Open item / Balance B/F), Account disabled, Default selling price and Salesperson.

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Debtor listing - Credit Control Listing (Reports menu)

The "*Debtor list - Credit control listing (Credit limit vs Current balance) as at...*" report will list the Account code, Name of the Debtor (account description), Postal address, Telephone 1 / 2, Credit limit, Current balance and the Available balance as at the date and time of printing this report.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor listing - Credit control listing report options

To print a Debtor listing - Credit control listing (Credit limit vs Current balance) as at... report:

1. On the Reports ribbon, select Reports → Debtors → Listing.
2. Select "*Credit control listing (Credit limit vs Current balance) as at*".



3. Select the following:
    a) From account / To account - Select a debtor (customer / client) account or a range of debtor

(customer / client) accounts, to include in the report.

b) Sequence - Select "*Debtor code Description, Credit limit* or *Disabled*" to print the report details in the order (sort) in which you wish to display the data.

c) Show contact details - You may select this option to view the postal address, delivery address, telephone numbers, Fax number, email address, website and more for each debtor account.

d) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Debtor list - Credit control listing report



Negative amounts in the Available column, prefixed with a minus sign (-), indicates that the debtor (customer / client) account(s) are exceeding the credit limit. This means that the

- *Credit limit is not entered, or may need to be increased on the Accounting information tab.*
- *The debtor (customer / client) account(s) are in arrears. You may need to send statements, reminders, etc. to receive outstanding payments debtors (customers / clients) before allowing further sales to these debtors (customers / clients). You may disable these debtor (customer / client) account on the Accounting information tab.*

Printed : Debtor list - Credit control listing (Show contact details) report

View the "*Debtor listing - Credit control listing (Credit limit vs Current balance) as at..*" (Show contact details) report:



The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the debtor (customer / client) account.

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Debtor listing - Tax and Company Registration Numbers (Reports menu)

The "*Debtor listing - Tax and Company registration numbers*" report will list the Account code and Name (description), Telephone 1 and Tax registration number as well as the Company registration number for each of your debtor (customer / client) accounts.

Debtor listing - Tax and Company registration numbers report options

To print a Debtor listing - Tax and Company registration numbers report:

1. On the Reports ribbon, select Reports → Debtors → Listing.

2. Select "*Tax and Company registration numbers*".



3. Select the following:

    a) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

    b) Sequence - Select "*Debtor code, Description, Tax registration no.*" or "*Company registration no.*" to print the report details in the order (sort) in which you wish to display the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Debtor list - Tax and Company registration numbers report



Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Debtors - Print labels (Reports menu)

The Debtor labels allows you to print the following two (2) types of labels:

1. Delivery address - This will print the Account code, Account description, Contact name and Delivery address for each selected debtor (customer / client) account.
2. Postal address - This will print the Account code, Account description, Contact name and Postal address for each selected debtor (customer / client) account.

Debtor labels options

To print Debtor labels:

1. Click on the Reports → Debtors → Print labels.
2. Select "*Delivery address labels*" (default) or "*Postal address labels*".



3. Select the following:

    a) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to print labels for.

    b) Sequence - Select "*Debtor code, Description, Address 3"* or "*Postal code*" to order (sort) the labels when printing.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The address labels will only be printed for those debtor (customer / client) accounts linked to the selected Debtor reporting group 1.

4. Click on the OK button.

Printed : Debtor - Delivery address labels



Printed : Debtor - Postal address labels



The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the debtor (customer / client) account.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Debtors - Transactions (Reports menu)

Created with the Standard Edition of HelpNDoc: Transform Your Word Document into a Professional eBook with HelpNDoc

Debtors - Transactions (Reports menu)

The "*Debtor transactions*" report lists all the transactions in documents and batches which are posted (updated) to the ledger for any specific period(s).

This report will include opening balances (closing balances before the selected periods / dates).

In addition to this, the following two (2) reports may be printed:

- Debtor Transaction List - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.
- Debtor Transaction List - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. If a debtor (customer / client) account is set as Open item account on the Accounting information tab), it will list only those transactions with outstanding amounts. Any credit amounts, which are not linked to debit transactions, should be processed in the Open item link (Default ribbon).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor - Transactions report options

To print Debtor - Transaction reports:

1. On the Reports ribbon, select Reports → Debtors → Transactions.
2. Select "*Transactions*".



3. Select the following options:

    a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

    b) From account / To - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

    c) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

    f) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

    > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

    g) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

4. Click on the OK button.

Printed : Debtor transactions report



The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

> *If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.*

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description). It also displays if the debtor (customer / client) account is an open item account.

4. Detail - List the transaction details for each account.

    a) Date - The date of the transaction or document.

    b) Batch no. - The Batch number as generated for posted batch transactions. If documents (i.e. invoices and credit notes are posted, the document number will be listed.

> *If an account has transactions prior to the selected period, the batch number will be indicated as "0" and the description will be "Opening".*

    c) Alias - The Batch name (as entered in the Alias field, or Auto-alias generated), for posted

batch transactions. If documents (i.e. invoices and credit notes are posted, the document number will be listed.

d) Reference - The reference number of the document (i.e. Invoices and Credit notes) or the reference number entered in the reference column on the Batch entry screen.

Opening balances will be indicated as Opening in the Alias, Reference, and Description columns.

e) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. Invoices and Credit notes) or the description entered in the description column on the Batch entry screen.

f) Debit - The debit transaction amount.

g) Credit - The credit transaction amount.

h) Cum - The accumulative total of the transactions included in the account.

5. Footer - Groups - Total / Balance - Displays the total of the transactions and the closing balance for each account.

6. Page Footer - List the following:

a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. … \books\BOOKSNAME\Books.fdb)

b) System user and osFinancials user / TurboCASH user (Setup → Access control).

c) Printed: The date and time of the system (computer) on which the report is printed.

d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Debtors - Transaction list reports (Reports menu)

The following two (2) reports may be printed:

- Debtors - Transaction list - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.

- Debtors - Transaction list - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. If a debtor (customer / client) account is set as Open item account (Accounting information tab), it will list only those transactions with outstanding amounts. Any credit amounts, which are not linked to debit transactions, should be processed in Open item link (Default ribbon).

These reports does not include any opening balances.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtors - Transactions list report options

To print Debtor - Transactions list reports:

1. On the Reports ribbon, select Reports → Debtors → Transactions.
2. Select "*Transaction list*" or "*Transaction list - Open item*".



3. Select the following options:

    a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

    b) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

    c) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

    d) Include zero balances - If this option is not selected (not ticked), it will list only the transactions for accounts which has transactions and/or balances. Tick this option to include opening balances (closing balances before the selected periods / dates).

    f) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

    The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.

    g) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

4. Click on the OK button.

Printed : Debtors - Transaction list report

The "*Debtors - Transaction list" report*" will list all the transactions, whether credit batch transactions or credit notes is linked to debit batch transactions and invoices, or not.



Transaction list

Debtors - Transaction list

From account: D1ABGRE To: D1ROGSM

Period: 2021/03/01 - 2022/02/28

Sequence: Description
New page per account: Yes

Cost centre 1:

Cost centre 2:

D1ABGRE Mr. AB Green

Open item: Yes

Date	Period	Batch id	Alias	Reference	Description	Debit	Credit	Cum
2021/03/07	March	10028	Sales 2103	INV001	Paint - Exterior	1,150.00		1,150.00
2021/03/10	March	10028	Sales 2103	INV003	Paint - Exterior	1,150.00		2,300.00
2021/03/13	March	10039	IN000001	IN000001	Invoice /AB-IN110	1,150.00		3,450.00
2021/03/15	March	10041	IN000003	IN000003	Invoice /PH-101	1,150.00		4,600.00
2021/03/16	March	10032	ABCReceipts 2103	D5001	Payment received - Thank you		2,000.00	2,600.00
2021/05/07	May	10056	IN000009	IN000009	Invoice /PH-101	1,150.00		3,750.00
2021/06/05	June	10059	IN000011	IN000011	Invoice /D-101	1,150.00		4,900.00
2021/06/30	June	10075	IN000019	IN000019	Invoice /D-101	5,750.00		10,650.00
2021/06/30	June	10077	IN000020	IN000020	Invoice /C-103	5,750.00		16,400.00
2021/06/30	June	10086	CR000001	CR000001	Credit note /D-101		5,750.00	10,650.00
2021/06/30	June	10090	CR000003	CR000003	Credit note /C-103		2,875.00	7,775.00
Total: D1ABGRE Mr. AB Green						7,775.00		

Printed : Debtors - Transaction list - Open item report

The "*Debtors - Transaction list - Open item*" report will list only the outstanding amounts and all transactions for which credit batch transactions or credit notes is not linked to debit batch transactions and invoices.



Transaction list - Open item

Debtor transactions - Open item

From account: D1ABGRE To: D1ROGSM

Period: 2021/03/01 - 2022/02/28

Sequence: Description
New page per account: Yes

Cost centre 1:

Cost centre 2:

D1ABGRE Mr. AB Green

Open item: Yes

Date	Period	Batch id	Alias	Reference	Description	Debit	Credit	Cum
2021/03/10	March	10028	Sales 2103	INV003	Paint - Exterior	300.00		300.00
2021/03/13	March	10039	IN000001	IN000001	Invoice /AB-IN110	1,150.00		1,450.00
2021/03/15	March	10041	IN000003	IN000003	Invoice /PH-101	1,150.00		2,600.00
2021/05/07	May	10056	IN000009	IN000009	Invoice /PH-101	1,150.00		3,750.00
2021/06/05	June	10059	IN000011	IN000011	Invoice /D-101	1,150.00		4,900.00
2021/06/30	June	10077	IN000020	IN000020	Invoice /C-103	2,875.00		7,775.00
Total:						7,775.00		

The credit transactions which are linked to specific debit transactions of the same value, will not be displayed. If a transaction

outstanding amount (difference) will be listed.


Open item link
Account 1ABGRE
Mr. AB Green
Contactperson: A
Clear links
Gen BB/F
Unlink
Process
Statement
Close
Export
Include items since 2021/03/01
Current date 2021/06/30
Use your mouse to pull a column here to group on that column
Reference
Date
Description
Amount
Outstanding
INV001 2021/03/07 Paint - Exterior 1150.00 0
2021/03/16 D5001 Payment received - Thank you -1150.00 ABCReceipts2103
INV003 2021/03/10 Paint - Exterior 1150.00 300
2021/03/16 D5001 Payment received - Thank you -850.00 ABCReceipts2103
D5001 2021/03/16 Payment received - Thank you -2000.00 0
2021/03/07 INV001 Paint - Exterior 1150.00 Sales2103
2021/03/10 INV003 Paint - Exterior 850.00 Sales2103
IN000001 2021/03/13 Invoice /AB-IN110 1150.00 1150
IN000003 2021/03/15 Invoice /PH-101 1150.00 1150
IN000009 2021/05/07 13:00:34 Invoice /PH-101 1150.00 1150
IN000011 2021/06/05 Invoice /D-101 1150.00 1150
IN000019 2021/06/30 Invoice /D-101 5750.00 0
2021/06/30 CR000001 Credit note /D-101 -5750.00 CR000001
IN000020 2021/06/30 Invoice /C-103 5750.00 2875
2021/06/30 CR000003 Credit note /C-103 -2875.00 CR000003
11 7775.00 7775.00
Over 90 days 2,600.00 60 days 1,150.00 30 days 4,025.00 Current 7,775.00 Due
Search
Filter

For example, an payment of 2,000.00 is received from the debtor (customer / client) on 2021/03/16. The payment is linked as fo

- *INV001 - 2021/03/07 - 1,150.00 is fully settled (linked to the payment of 2000.00) -*
- *The remaining balance of 850.00 is linked to INV003 as a partial settlement of INV003. An outstanding amount of 300.00 v minus the partial settlement of 850.00 = 300.00 as the outstanding amount.*

As per this example -

- *Invoice INV001 will not be printed on some reports and in other reports it will print 0.00 as the outstanding amount.*
- *INV003 will print on some reports as 300.00 as the outstanding amount.*

If the transaction for Credit note CR000003 is not linked to Invoice IN000020, both Credit note CR000003 and Invoice IN000020, "Transaction list - Open item" report as well as the "Debtor statement - Outstanding".


Transaction list - Open item

Debtor transactions - Open item

From account: D1ABGRE To: D1ROGSM

Period: 2021/03/01 - 2022/02/28

Sequence: Description
New page per account: Yes

Cost centre 1:

Cost centre 2:

D1ABGRE Mr. AB Green

Open item

Date	Period	Batch id	Alias	Reference	Description	Debit	Credit
2021/03/10	March	10028	Sales2103	INV003	Paint - Exterior	300.00	
2021/03/13	March	10039	IN000001	IN000001	Invoice /AB-IN110	1,150.00	
2021/03/15	March	10041	IN000003	IN000003	Invoice /PH-101	1,150.00	
2021/05/07	May	10056	IN000009	IN000009	Invoice /PH-101	1,150.00	
2021/06/05	June	10059	IN000011	IN000011	Invoice /D-101	1,150.00	
2021/06/30	June	10077	IN000020	IN000020	Invoice /C-103	5,750.00	
2021/06/30	June	10090	CR000003	CR000003	Credit note /C-103		2,875.00
Total:						7,775.00	

You may need to process the links on the Open item link (Default ribbon).

The credit transactions which are linked to specific debit transactions of the same value, will not be displayed. If a transaction of a different amount is linked to a specific transaction, only the outstanding amount (difference) will be listed.

The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

> *If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.*

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description). It also displays if the debtor (customer / client) account is an open item account.

4. Detail - List the transaction details for each account.

    a) Date - The date of the transaction or document.

    b) Period - This will display the accounting period's description (i.e. name of the month).

    c) Batch no. - The Batch number as generated for posted batch transactions. If documents (i.e. invoices and credit notes are posted, the document number will be listed.

    d) Alias - The Batch name (as entered in the Alias field, or Auto-alias generated), for posted batch transactions. If documents (i.e. invoices and credit notes are posted, the document number will be listed.

    e) Reference - The reference number of the document (i.e. Invoices and Credit notes) or the reference number entered in the reference column on the Batch entry screen.

    f) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. Invoices and Credit notes) or the description entered in the description column on the Batch entry screen.

    g) Debit - The debit transaction amount.

    h) Credit - The credit transaction amount.

    i) Cum - The accumulative total of the transactions included in the account.

5. Footer - Groups - Total / Balance - Displays the total of the transactions and the closing balance for each account.

6. Page Footer - List the following:

a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. ... \books\BOOKSNAME\Books.fdb)

b) System user and osFinancials user / TurboCASH user - (Setup → Access control).

c) Printed: The date and time of the system (computer) on which the report is printed.

d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Keep Your PDFs Safe from Unauthorized Access with These Security Measures

Debtors - Transactions - Standard / Extra details (Reports menu)

The "*Debtor transactions - Standard*" and "*Debtor transactions - Extra details*" report lists all the transactions in documents and batches which are posted (updated) to the ledger.

The "*Debtor transactions - Extra details*" report is similar to the "*Debtor transactions - Standard*" report, but displays extra details of the Contra accounts (i.e. Account code, Account description, Contra account code and Description as well as the Tax account code and Description). For example;

"G010000 Sales,T860010, Output VAT" - 15%"

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtor transactions - Standard / Extra details report options

To print Debtor transactions - Standard / Debtor transactions - Extra details reports:

1. On the Reports ribbon, select Reports → Debtors → Transactions.
2. Select "*Debtor transactions - Standard*" or "*Debtor transactions - Extra details*".



3. Select the following options:

    a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

    b) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

    c) Include zero balances - If this option is not selected (not ticked), it will list only the transactions for accounts which has transactions and/or balances. Tick this option to include opening balances (closing balances before the selected periods / dates).

    d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

    > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

    e) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

4. Click on the OK button.

Printed : Debtor transactions - Standard report



Printed : Debtor transactions - Extra details report



The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

> *If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.*

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description). It also displays the date and opening balances of the previous year.

4. Detail - List the transaction details for each account.

    a) Date - The date of the transaction or document.

    b) Reference - The reference number of the document (i.e. Invoices and Credit notes) or the reference number entered in the reference column on the Batch entry screen.

    c) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. Invoices and Credit notes) or the description entered in the description column on the Batch entry screen.

    d) Debit - The debit transaction amount.

    e) Credit - The credit transaction amount.

    f) Cum - The accumulative total of the transactions included in the account.

5. Footer - Groups - Total / Balance - Displays the total of the transactions and the closing balance for each account.

6. Page Footer - List the following:

    a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. ... \books\BOOKSNAME\Books.fdb)

    b) System user and osFinancials user / TurboCASH user (Setup → Access control).

    c) Printed: The date and time of the system (computer) on which the report is printed.

    d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Free help authoring environment

Creditors (Reports menu)

On the Reports ribbon, select Reports → Creditors.



The following reports are available to manage the accounts in the creditor's ledger:

1. Creditor remittance advise - Remittance advise and Remittance advise - Outstanding.
2. Age analysis - Balances detail, Balances detail history (open item) and Balances reports. These reports offers different options of views to support the details of creditor remittance advises.
3. Listing - Contacts, Listing, List delivery address, List postal address or List details, Tax and company registration numbers and the Credit control listing (Credit limit vs current balance and available balances as at the date and time of printing) report.
4. Print labels - Postal and Delivery address labels.
5. Transactions - Transactions - Open item, Transactions - Standard and Transactions - Extra details.

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Creditor remittance advises

The following Creditor remittance advises are available:

- Creditor remittance advises - The statement will print all transactions. It does not use the Open item link feature.
- Creditor remittance advises - Outstanding - The statement will print only the outstanding transactions. Transactions linked in the Open item link feature, will not be listed.

Before you wish to print Creditor remittance advises, you may need to check the following:

- *Remittance messages are entered correctly.*
- *That no outstanding transactions which is not linked in Open item processing.*

Enter statement messages for specific creditor accounts:

1. On the Default ribbon, select Creditors (F5).
2. Select the creditor (supplier / vendor) account.
3. On the Delivery address tab, enter a message of up to 3 lines.
4. Click on the Save button.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Creditor remittance advises (Reports menu)

The Creditor remittance advise will print all transactions. It does not use the Open item link feature.

The Creditor remittance advise - Outstanding will print only the outstanding transactions. Transactions linked in the Open item link feature, will not be listed.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor remittance advise options

To print Creditor remittance advises:

1. On the Reports ribbon, select Reports → Creditors → Creditor remittance advise.



2. Enter or select the date of the ageing.

3. Enter the number of days to display for the periods.

4. Select the creditor (supplier / vendor) accounts to include in the Creditor remittance advises.

5. Click on the OK button.

Printed : Creditor remittance advise



The information is as follows:

1. Header (Left) - Creditor Information as entered / edited on the creditor (supplier / vendor) account (Creditors on the Default ribbon).

2. Header (Right) - Company info as entered / edited on the Setup → Company info.

3. Remittance advise to - The date as entered (selected) on the Parameters screen. The periods number of days specified on the parameters screen is displayed. The outstanding totals for each period is displayed as a summary for the periods at the end of the transaction section.

4. Transactions - This displays the date, reference. description and amount for each transaction. The payment date for each transaction is the date of the transaction plus the number of days entered in the Due days field on the Accounting information tab of the creditor account.

5. Credit limit - The amount as entered in the Credit limit field on the Accounting information tab of the creditor account. The Balance at is the current balance of the creditor account of all posted transactions and documents as at the date of printing of the Remittance Advises. The Available amount is calculated the Credit limit minus the Balance at amount as at the date of printing of the Remittance Advises.

6. Remittance message - Up to three (3) lines as entered on the Delivery address tab of the creditor account.

7. Due amount and Due date - The amount payable and the date on which the payment is due.

Created with the Standard Edition of HelpNDoc: Single source CHM, PDF, DOC and HTML Help creation

Creditor remittance advises - Outstanding (Reports menu)

The Creditor remittance advise - Outstanding will print only the outstanding transactions. Transactions linked in the Open item link feature, will not be listed.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor remittance advise - Outstanding options

To print Creditor remittance advises - Outstanding:

1. On the Reports ribbon, select Reports → Creditors → Creditor remittance advise.

2. Select "*Creditor remittance advise - Outstanding*".



3. Enter or select the date of the ageing.

4. Enter the number of days to display for the periods.

5. Select the creditor (supplier / vendor) accounts to include in the Creditor remittance advises.

6. Click on the OK button.

Printed : Creditor remittance advise - Outstanding



Creditor remittance advise - Outstanding

ABC-Office-Supplies
PO Box 8888
Lakeview
Johannesburg
2012

Account no. : C2ABCOS
Contact : Walters Penny
Tax reg. no. : 4444444444
Company reg. no. : 5555555555
Telephone 1 : (011)312-9997
Telephone 2 : (011)312-9998
Fax : (011)312-9999

E-mail : abcoff@hismail.com
Website : osfinancials.org/en/

Handyman Hardware Store
27 Olifants Road
Emmarentia
Johannesburg
2195

Phone: (011) 310-1390
Fax: (011) 310-2000
E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Company reg. no.: 336012345
Tax reg. no.: 446010111

Creditor remittance advise

Statement to: 2021/04/30

Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01

Due amount: -2,700.00
Due date: 2021/05/30

Date	Reference	Description	Amount	Outstanding	Payment date
2021/03/06	PU002	Install - Built-in cupboards	-1,725.00	-975.00	2021/04/05
2021/03/15	PU000002	Purchases /IN0014	-1,725.00	-1,725.00	2021/04/14

	Due amount	Period 1 (30)	Period 2 (30)	Period 3 (60) +
	-2,700.00	0.00	-2,700.00	0.00

Credit limit:	-10,000.00
Balance :	-2,700.00
Available :	-7,300.00

Statement message:

2.5% Early settlement discount

Due amount: -2,700.00 **Due date: 2021/05/30**

In this example, PU002 of 1725.00 is displayed as outstanding on the Creditor remittance advise - Outstanding, since the payment of 750.00 is linked to that purchase invoice.

The balance of 975.00 is still outstanding on the Purchase invoice.

The information is as follows:

1. Header (Left) - Creditor Information as entered / edited on the creditor (supplier / vendor) account (Default → Creditors on the Default ribbon).

2. Header (Right) - Company info as entered / edited on the Setup → Company info.

3. Remittance advise to - The date as entered (selected) on the Parameters screen. The periods number of days specified on the parameters screen is displayed. The outstanding totals for each period is displayed as a summary for the periods at the end of the transaction section.

4. Transactions - This displays the date, reference. description and amount for each transaction. The payment date for each transaction is the date of the transaction plus the number of days entered in the Due days field on the Accounting information tab of the creditor account.

5. Credit limit - The amount as entered in the Credit limit field on the Accounting information tab of the creditor account. The Balance at is the current balance of the creditor account of all posted transactions and documents as at the date of printing of the Remittance Advises. The Available amount is calculated the Credit limit minus the Balance at amount as at the date of printing of the Remittance Advises.

6. Remittance message - Up to three (3) lines as entered on the Delivery address tab of the creditor account.

7. Due amount and Due date - The amount payable and the date on which the payment is due.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Creditors - Age analysis

The Creditor age analysis reports allows you to analyse the outstanding amounts you owe to your creditors (suppliers) in specified periods such as total, 30, 60 and 90 days, or more. These reports are essential for cash flow control. You may also wish to use this facility to schedule the payments to your creditors, to optimise your cash flow management.

The Creditors → Age analysis - The Creditor age analysis provides the "*Balances detail*, *Balances detail history (open item)*" and "*Balances*" reports allows you to analyse the outstanding amounts you owe to your creditors (suppliers) in specified periods such as total, 30, 60 and 90 days, or more. These reports are essential for cash flow control. You may also wish to use this facility to schedule the payments to your creditors, to optimise your cash flow management.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Creditors - Age analysis - Balances detail

The Creditor age analysis reports allows you to analyse the outstanding amounts you owe to your creditors (suppliers) in specified periods such as total, 30, 60 and 90 days, or more. These reports are essential for cash flow control. You may also wish to use this facility to schedule the payments to your

creditors, to optimise your cash flow management.

The following reports are available:

- Balances detail - Displays the reference, date, amount and description for each transaction. The Total outstanding as at the Date of ageing is split to the number of days specified in up to 3 periods.
- Balances detail history (open item) - This is similar to the Balances detail report, but it displays the outstanding amount and TransactionID.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor age analysis - Balances detail report options

To print Creditor age analysis - Balances detail report:

1. On the Reports ribbon, select Reports → Creditors → Age analysis.
2. Select "*Balances detail*" (default).



3. Select the following options:
    a) Date of ageing - Select or enter a date to include the transactions on or before that date.

b) Days overdue - Enter the number of days for period 1.

c) Number of days overdue - Enter the number of days for period 2.

d) From account ...To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

e) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

f) Show transactions - If this option is not selected (not ticked), it will list only the balances. Tick this option to include the transactions.

g) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details). You may select this option, if the for the balances or transactions (Show transactions option ticked or not).

h) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.

3. Click on the OK button.

Printed : Creditor age analysis - Balances detail report

View the "*Creditor age analysis - Balances detail*" ("*Show transactions*" option not selected) report:



Printed : Creditor age analysis - Balances detail (Show transactions / Show contact details) report

View the "*Creditor age analysis - Balances detail*" ("*Show contact details*" and "*Show transactions*" options selected) report for a specific creditor (supplier / vendor) account:



The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the creditor (supplier / vendor) account.

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Creditors - Age analysis - Balances detail (open item)

The Creditor age analysis reports allows you to analyse the outstanding amounts you owe to your creditors (suppliers) in specified periods such as total, 30, 60 and 90 days, or more. These reports are essential for cash flow control. You may also wish to use this facility to schedule the payments to your creditors, to optimise your cash flow management.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor age analysis - Balances detail (open item) report options

The following reports are available:

- Balances detail - Displays the reference, date, amount and description for each transaction. The Total outstanding as at the Date of ageing is split to the number of days specified in up to 3 periods.
- Balances detail history (open item) - This is similar to the Balances detail report, but it displays the outstanding amount and TransactionID.

To print Creditor age analysis Balances detail history (open item) report:

1. On the Reports ribbon, select Reports → Creditors → Age analysis.
2. Select "*Balances detail history (open item)*".



3. Select the following options:
    a) Date of ageing - Select or enter a date to include the transactions on or before that date.
    b) Days overdue - Enter the number of days for period 1.
    c) Number of days overdue - Enter the number of days for period 2.
    d) From account ...To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.
    e) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).
    f) Show transactions - If this option is not selected (not ticked), it will list only the balances. Tick this option to include the transactions.

g) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details). You may select this option, if the for the balances or transactions (Show transactions option ticked or not).

h) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.

3. Click on the OK button.

Printed : Creditor age analysis - Balances detail history (open item) report

View the "*Creditor age analysis - Balances detail history (open item)*" ("*Show transactions*" option not selected) report:

Page 1 -


Balances detail history (open item)
Creditor age analysis - Balances detail history (open item)
From account: C2ABCOS To: C2SUNSU
Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01
Sequence: Description
Show transactions: No
Show contact details: No
New page per account: No
C2AONES A-ONE Suppliers
Open item: Yes
Total
-2,325.00
Total -2,325.00 -2,325.00
Period 1 (30) Period 2 (30) Period 3 (60) +
-1,725.00 0.00 -600.00
C2BESTS BEST Suppliers
Open item: No
Total
-2,700.00
Total -2,700.00 -2,700.00
Period 1 (30) Period 2 (30) Period 3 (60) +
-2,300.00 0.00 -400.00
Total - Creditor group: Creditor group 1B
-5,025.00
Period 1 (30) Period 2 (30) Period 3 (60) +
-1,725.00 0.00 -600.00
C2ABCOS ABC-Office-Supplies
Open item: Yes
Total
-2,700.00
Total -2,700.00 -2,700.00
Period 1 (30) Period 2 (30) Period 3 (60) +
0.00 -2,700.00 0.00
C2ABCSC ABC-Service-Centre
Open item: No
Total
-2,300.00
Total -2,300.00 -2,300.00
Period 1 (30) Period 2 (30) Period 3 (60) +
0.00 -2,300.00 0.00
Total - Creditor group: Creditor group 1C
-5,000.00
Period 1 (30) Period 2 (30) Period 3 (60) +
-2,300.00 -2,700.00 -400.00

Page 2 -


Balances detail history (open item)
Creditor age analysis - Balances detail history (open item)
From account: C2ABCOS To: C2SUNSU
Period 1 : 2021/04/30
Period 2 : 2021/03/31
Period 3 : 2021/03/01
Sequence: Description
Show transactions: No
Show contact details: No
New page per account: No
Report total: -10,025.00
Period 1 (30) Period 2 (30) Period 3 (60) +
-4,025.00 -2,700.00 -1,000.00

Printed : Creditor age analysis - Balances detail history (open item) (Show transactions / Show contact details) report

View the "*Creditor age analysis - Balances detail history (open item)*" ("*Show contact details*" and "*Show transactions*" option not selected) report:



On this report, all the transactions (for the selected period) are listed. The outstanding amount will be displayed, in this example, as follows:

The payment of 750,00 on 30 March 2021 is linked in the Open item as follows:

- *PU002 for1 725.00 is partially settled with the payment of 750.00 linked to this supplier invoice - Outstanding = 975.00.*
- *The full debit payment of 750.00 is linked to supplier invoice - Outstanding = 0.00*

The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the creditor (supplier / vendor) account.

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Creditors - Age analysis - Balances

The "*Balances*" is a similar report as the "*Balances detail*" report. The "*Balances*" will only list the balances for each ageing period.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor age analysis - Balances report options

To print Creditor age analysis - Balances report:

1. On the Reports ribbon, select Reports → Creditors → Age analysis.
2. Select "*Balances*".



3. Select the following options:
    a) Date of ageing - Select or enter a date to include the transactions on or before that date.
    b) Days overdue - Enter the number of days for period 1.
    c) Number of days overdue - Enter the number of days for period 2.

d) From account ...To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

e) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

3. Click on the OK button.

Printed : Creditor age analysis - Balances report

View the "*Creditor age analysis - Balances*" report:



Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Creditors - Listing (Reports menu)

On the Reports ribbon, select Reports → Creditors → Listing.

The Creditor listing allows you to print the following seven (7) reports:

1. Contacts - This report will list the Name of the Contact, Telephone 1 / 2 and the creditor (supplier / vendor) account code and name (description) linked to the contact.
2. Listing - This report will list the Account code, Name of the Creditor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.
3. List - Delivery address - This report will list the Account code, Name of the Creditor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.
4. List - Postal address - This report will list the Account code, Name of the Creditor (account description), Postal address, Telephone 1 / 2, Fax, E-mail Address and Website.
5. List details - This report will display the Contact details, Registration details, Banking details, Reporting details, Accounting terms and information for each creditor (supplier account).
6. Credit control listing (Credit limit vs Current balance) as at... - This report will list the Account code, Name of the Creditor (account description), Postal address, Telephone 1 / 2, Credit limit, Current balance and the Available balance as at the date and time of printing this report.
7. Tax and Company registration numbers - This report will list the Account code and Name (description), Telephone 1 and Tax Registration Number as well as the Company Registration Number for each of your creditor (supplier / vendor) accounts.

Created with the Standard Edition of HelpNDoc: Don't Let Unauthorized Users View Your PDFs: Learn How to Set Passwords

Creditor listing - Contacts (Reports menu)

The "*Contact list - Creditors*" report will list the Name of the Contact, Telephone 1 / 2 and the creditor (supplier / vendor) account code and name (description) linked to the contact.

Creditor listing - Contacts report options

To print a Creditor listing - Contacts report:

1. On the Reports ribbon, select Reports → Creditors → Listing.
2. Select "*Contacts*".



3. Select the following:

    a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

    b) Sequence - Select "*First Name*, *Name (Surname)*, *Creditor code* or *Description*" to print the report details in the order (sort) in which you wish to list the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those creditor (supplier / vendor) accounts linked to the selected Creditor reporting group 1.

4. Click on the OK button.

Printed : Contacts list - Creditors report



Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Markdown Content with HelpNDoc

Creditor listing (Reports menu)

The Creditor listing report will list the Account code, Name of the Creditor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.

Creditor listing - Listing report options

To print a Creditor listing - Listing report:

1. On the Reports ribbon, select Reports → Creditors → Listing.
2. Select "*Listing*".



3. Select the following:
    a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.
    b) Sequence - Select "*Creditor code* or *Description*" to print the report details in the order (sort) in which you wish to list the data.
    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those creditor (supplier / vendor) accounts linked to the selected Creditor reporting group 1.
4. Click on the OK button.

Printed : Creditor list report



Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Creditor listing - Delivery address (Reports menu)

The Creditor listing - Delivery address report will list the Account code, Name of the Creditor (account description), Delivery address, Telephone 1 / 2, Fax, E-mail Address and Website.

Creditor - List delivery address report options

To print a Creditor - List delivery address report:

1. On the Reports ribbon, select Reports → Creditors → Listing.
2. Select "*List delivery address*".



3. Select the following:

    a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

    b) Sequence - Select "*Creditor code, Description, Address 3* or *Postal code*" to print the report details in the order (sort) in which you wish to list the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those creditor (supplier / vendor) accounts linked to the selected Creditor reporting group 1.

4. Click on the OK button.

Printed : Creditor list: Delivery address report



Created with the Standard Edition of HelpNDoc: Transform your help documentation into a stunning website

Creditor listing - Postal address (Reports menu)

The Creditor listing - Postal address report will list the Account code, Name of the Creditor (account description), Postal address, Telephone 1 / 2, Fax, E-mail Address and Website.

Creditor - List postal address report options

To print a Creditor - List postal address report:

1. On the Reports ribbon, select Reports → Creditors → Listing.
2. Select "*List postal address*".



3. Select the following:

    a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

    b) Sequence - Select "*Creditor code, Description, Address 3* or *Postal code*" to print the report details in the order (sort) in which you wish to list the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those creditor (supplier / vendor) accounts linked to the selected Creditor reporting group 1.

4. Click on the OK button.

Printed : Creditor list: Postal address report



Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Creditor listing - List details (Reports menu)

The Creditor listing - List details report will display the Contact details, Registration details, Banking details, Reporting details, Accounting terms and information for each creditor (supplier / vendor) account.

Creditor - List details report options

To print a Creditor listing - List details report:

1. On the Reports ribbon, select Reports → Creditors → Listing.
2. Select the "*List details*".



3. Select the following:

    a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

    b) Sequence - Select "*Creditor code, Description, Reporting group 1* or*Reporting group 2*" to print the report details in the order (sort) in which you wish to list the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those creditor (supplier / vendor) accounts linked to the selected Creditor reporting group 1.

4. Click on the OK button.

Printed : Creditor list - Details report



The List details report will display the following information:

1. Contact details - Contactperson, Telephone 1 / 2, Fax, E-Mail, Website, Postal address, Delivery address and Language of the creditor (supplier / vendor).
2. Registration details - Company Registration number and Tax registration number.
3. Banking details - Bank account type, Name of Bank account, Bank account number and Branch code.
4. Reporting details - Reporting group 1 / 2, Layout file 1 (Purchases), Layout file 2 (Supplier returns) and Layout file 3 (Orders). If no layout files are selected, the documents will be printed for the global settings in Setup → Documents setup.
5. Accounting terms and information - Remittance message, Credit limit, Due days (payment terms), Charge amount, account settings (i.e. Open item / Balance B/F) and Account disabled / inactive) as well as the Debtor code from the creditor (supplier / vendor).

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Creditor listing - Credit Control Listing (Reports menu)

The "*Creditor listing - Credit control listing (Credit limit vs Current balance) as at...*" report will list the Account code, Name of the Creditor (account description), Postal address, Telephone 1 / 2, Credit limit, Current balance and the Available balance as at the date and time of printing this report.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor listing - Credit control listing report options

To print a Creditor listing - Credit control listing (Credit limit vs Current balance) as at... report:

1. On the Reports ribbon, select Reports → Creditors → Listing.
2. Select "*Credit control listing (Credit limit vs Current balance) as at*".



3. Select the following:

   a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

   b) Sequence - Select "*Creditor code, Description, Credit limit* or *Disabled*" to print the report details in the order (sort) in which you wish to list the data.

c) Show contact details - You may select this option to view the postal address, delivery address, telephone numbers, Fax number, email address, website and more for each creditor account.

d) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those creditor (supplier / vendor) accounts linked to the selected Creditor reporting group 1.

4. Click on the OK button.

Printed : Creditor list - Credit control listing report

View the "*Creditor listing - Credit control listing (Credit limit vs Current balance) as at..*" report



Negative amounts in the Available column, not prefixed with a minus sign (-), indicates that the creditor (supplier / vendor) account(s) are exceeding the credit limit. This means that the

- *Credit limit is not entered, or may need to be increased on the Accounting information tab.*
- *The creditor (supplier / vendor) account(s) are in overdue. You may need to pay these creditors (suppliers), etc., before making any further purchases from these creditors (suppliers).*

Printed : Creditor list - Credit control listing (Show contact details) report

View the "*Creditor listing - Credit control listing (Credit limit vs Current balance) as at..*" (Show contact details) report:



The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the creditor (supplier / vendor) account.

Created with the Standard Edition of HelpNDoc: Maximize Your PDF Protection with These Simple Steps

Creditor listing - Tax and Company Registration Numbers (Reports menu)

The Creditor listing - Tax and Company registration numbers report will list the Account code and Name (description), Telephone 1 and Tax registration number as well as the Company registration number for each of your creditor (supplier / vendor) accounts.

Creditor listing - Tax and Company registration numbers report options

To print a Creditor listing - Tax and Company registration numbers report:

1. On the Reports ribbon, select Reports → Creditors → Listing.

2. Select "*Tax and Company registration numbers*".



3. Select the following:

    a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

    b) Sequence - Select "*Creditor code, Description, Tax Registration No.* or *Company Registration No.*" to print the report details in the order (sort) in which you wish to display the data.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The report will only be printed for those creditor (supplier / vendor) accounts linked to the selected Creditor reporting group 1.

4. Click on the OK button.

Printed : Creditor list - Tax and Company registration numbers report



Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

Creditors - Print labels (Reports menu)

The Creditor labels allows you to print the following two (2) types of labels:

1. Delivery address - This will print the Account code, Account description, Contact name and Delivery address for each selected creditor (supplier / vendor) account.
2. Postal address - This will print the Account code, Account description, Contact name and Postal address for each selected creditor (supplier / vendor) account.

Creditor labels options

To print creditor labels:

1. On the Reports ribbon, select Reports → Creditors → Print labels.
2. Select "*Delivery address labels*" (default) or "*Postal address labels*".



3. Select the following:

    a) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to print labels for.

    b) Sequence - Select "*Creditor code, Description, Address 3* or *Postal code*" to order (sort) the labels when printing.

    c) Reporting group 1 - Select a reporting group or more reporting groups. The address labels will only be printed for those creditor accounts linked to the selected Creditor reporting group 1.

4. Click on the OK button.

Printed : Creditor - Delivery address labels



Printed : Creditor - Postal address labels



The Contact: name of the contact person will only be displayed, if the contact is selected on the Contactperson field of the creditor (supplier / vendor) account.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Creditors - Transactions (Reports menu)

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Creditors - Transactions (Reports menu)

The Creditor transactions report lists all the transactions in documents and batches which are posted (updated) to the ledger for any specific period(s). You may select to show opening balances.

In addition to this, the following two (2) reports may be printed:

- Creditor transaction list - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.
- Creditor transaction list - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. If a creditor (supplier / vendor) account is set as Open item account on the Accounting information tab), it will list only those transactions with outstanding amounts. Any debit amounts, which are not linked to credit transactions, should be processed in Open item link (Default ribbon).

This report will include opening balances (closing balances before the selected periods / dates).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor - Transactions report options

To print Creditor - Transactions reports:

1. On the Reports ribbon, select Reports → Creditors → Transactions.

2. Select "*Transactions*".



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

   b) From account / To - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

e) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

4. Click on the OK button.

Printed : Creditor transactions report



The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

> *If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.*

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description). It also displays if the creditor (supplier / vendor) account is an open item account.

4. Detail - List the transaction details for each account.

a) Date - The date of the transaction or document.

b) Batch no. - The Batch number as generated for posted batch transactions. If documents (i.e. purchases and supplier returns are posted, the document number will be listed.

> *If an account has transactions prior to the selected period, the batch number will be indicated as "0" and the description will be "Opening".*

c) Alias - The Batch name (as entered in the Alias field, or Auto-alias generated), for posted batch transactions. If documents (i.e. purchases and supplier returns are posted, the document number will be listed.

d) Reference - The reference number of the document (i.e. purchases and supplier returns) or the reference number entered in the reference column on the Batch entry screen.

e) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. purchases and supplier returns) or the description entered in the description column on the Batch entry screen.

f) Debit - The debit transaction amount.

g) Credit - The credit transaction amount.

h) Cum - The accumulative total of the transactions included in the account.

5. Footer - Groups - Total / Balance - Displays the total of the transactions and the closing balance for each account.

6. Page Footer - List the following:

a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. ... \books\BOOKSNAME\Books.fdb)

b) System user and osFinancials user / TurboCASH user (Setup → Access control).

c) Printed: The date and time of the system (computer) on which the report is printed.

d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Elevate Your Help Documentation with a Help Authoring Tool

Creditors - Transaction list reports (Reports menu)

The following two (2) reports may be printed:

- Creditors - Transaction list - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.
- Creditors - Transaction list - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. If a creditor (supplier / vendor) account is set as Open item account (Creditors - Accounting information tab), it will list only those transactions with outstanding amounts. Any debit amounts, which are not linked to credit transactions, should be processed in Open item link (Default ribbon).

These reports does not include any opening balances.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditors - Transactions list report options

To print Creditor transactions List reports:

1. On the Reports ribbon, select Reports → Creditors → Transactions.
2. Select "*Transaction List*" or "*Transaction List - Open item*".



3. Select the following options:

    a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

    b) From account / To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

    c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

    f) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

    > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

    g) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

4. Click on the OK button.

Printed : Creditors - Transaction list report

The "*Creditors - Transaction list" report*" will list all the transactions, whether debit batch transactions or

supplier return documents is linked to credit batch transactions and purchase documents, or not.



Printed : Creditor - transactions - Open item report

The "*Creditors - Transaction list - Open item*" report will list only the outstanding amounts and all transactions for which batch transactions or supplier return documents is not linked to credit batch transactions and purchase documents.



The debit transactions which are linked to specific credit transactions of the same value, will not be displayed. If a transaction amount (difference) will be listed.



For example:

- *Payment - 108 - 2021/03/30 - 750.00 - Debit transaction in the Payments journal is linked to the supplier invoice PU002 - 2*

The outstanding amount for this transaction is 975.00 still due to the creditor (supplier / vendor). (1725.00 minus 750.00). Only

If the transaction for Supplier return SR000004 is not linked to Purchase PU000007, both Supplier return SR000004 and Purchas
listed on the "Transaction list - Open item" report as well as the "Creditor remittance advise - Outstanding".



You may need to process the links on the Open item link (Default ribbon).

The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

   If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description). It also displays if the creditor (supplier / vendor) account is an open item account.

4. Detail - List the transaction details for each account.

   a) Reference - The reference number of the document (i.e. Purchases and Supplier returns) or the reference number entered in the reference column on the Batch entry screen.

   b) Date - The date of the transaction or document.

c) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. Purchases and Supplier returns) or the description entered in the description column on the Batch entry screen.

d) Debit - The debit transaction amount.

e) Credit - The credit transaction amount.

f) Cum - The accumulative total of the transactions included in the account.

5. Footer - Groups - Total / Balance - Displays the total of the transactions and the closing balance for each account.

6. Page Footer - List the following:

a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. ... \books\BOOKSNAME\Books.fdb)

b) System user and osFinancials user (Setup → Access control).

c) Printed: The date and time of the system (computer) on which the report is printed.

d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

Creditors - Transactions - Standard / Extra details (Reports menu)

The "*Creditor transactions - Standard*" and "*Creditor transactions - Extra details*" report lists all the transactions in documents and batches which are posted (updated) to the ledger.

The "*Creditor transactions - Extra details*" report is similar to the "*Creditor transactions - Standard*" report, but displays extra details of the Contra accounts (i.e. Account code, Account description, Contra account code and Description as well as the Tax account code and Description). For example, "*G750000 Stock control,T860020, Input VAT - Standard rate - 15%*", etc.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditor transactions - Standard / Extra details report options

To print Creditor transactions - Standard / Creditor transactions - Extra details reports:

1. On the Reports ribbon, select Reports → Creditors → Transactions.

2. Select "*Creditor transactions - Standard*" or "*Creditor transactions - Extra details*".



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

   b) From ... To - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

   c) Include zero balances - If this option is not selected (not ticked), it will list only the transactions for accounts which has transactions and/or balances. Tick this option to include opening balances (closing balances before the selected periods / dates).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is*

displayed in the Page footer.

e) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

4. Click on the OK button.

Printed : Creditor transactions - Standard report



Printed : Creditor transactions - Extra details report



Creditor transactions - Extra details

Creditor transactions - Extra details

Period: 2022/04/01 - 2022/04/30

From: C2ABCOS
To: C2SUNSU

Include zero balances: No
New page per account: No

C2ABCOS ABC-Office-Supplies					2022/04/30	-2,700.00
C2ABCSC ABC-Service-Centre					2022/04/30	-2,300.00
C2AONES A-ONE Suppliers					2022/04/01	-600.00
Date	Reference no.	Description	Debit	Credit	Cum	
2022/04/05	PU000003	Purchases /4562		1,725.00	-2,325.00	
Contra Accounts	G750000 Stock control, T860020 Input VAT - Standard rate -15%					
Total: C2AONES A-ONE Suppliers			0.00	1,725.00		
					2022/04/30	-2,325.00
C2BESTS BEST Suppliers					2022/04/01	-400.00
Date	Reference no.	Description	Debit	Credit	Cum	
2022/04/06	PU000004	Purchases /3532		2,300.00	-2,700.00	
Contra Accounts	G750000 Stock control, T860020 Input VAT - Standard rate -15%					
Total: C2BESTS BEST Suppliers			0.00	2,300.00		
					2022/04/30	-2,700.00
C2COPEN Opening balances - Creditor					2022/04/30	0.00

The details on the report, is as follows:

1. Page header 1 - Company details - This will only print on the fist page.

> *If the "New page per account" option on the report parameters is selected (ticked), the Company details will not be printed in the Page header of the first page. The company name is displayed in the Page footer of all pages.*

2. Page header 2 - Report name and Parameters as selected on the Report options will display below the Company details on the first page and at the top of each subsequent page.

3. Header group - The Account code and Name (description). It also displays the date and opening balances of the previous year.

4. Detail - List the transaction details for each account.

    a) Reference - The reference number of the document (i.e. Purchases and Supplier returns) or the reference number entered in the reference column on the Batch entry screen.

    b) Date - The date of the transaction or document.

c) Description - The stock item code or the account description (if the Financial entry stock item type was selected on a document) of the document (i.e. Purchases and Supplier returns) or the description entered in the description column on the Batch entry screen.

d) Debit - The debit transaction amount.

e) Credit - The credit transaction amount.

f) Cum - The accumulative total of the transactions included in the account.

5. Footer - Groups - Total / Balance - Displays the total of the transactions and the closing balance for each account.

6. Page Footer - List the following:

a) Data - Name of the Set of Books and the full path of the Set of Books (e.g. ... \books\BOOKSNAME\Books.fdb)

b) System user and osFinancials user / TurboCASH user (Setup → Access control).

c) Printed: The date and time of the system (computer) on which the report is printed.

d) Page: Page number and the last page number of the report.

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Contacts (Reports menu)

This report lists all contacts linked to debtor (customer/client) accounts as well as creditor (supplier/vendor) accounts.

To list only the contacts for debtor (customer / client) accounts, you need to print it in Reports → Debtors → Listing - Contacts menu (Reports ribbon). This report specifically focuses on contacts related to debtors (customers/clients). It provides a listing of contacts associated with your debtor accounts.

To list only the contacts for creditor (supplier / vendor) accounts, you need to print it in Reports → Creditors → Listing - Contacts menu (Reports ribbon). This report specifically lists contacts related to creditors (suppliers/vendors). It presents a comprehensive view of contacts associated with your creditor accounts.

To add new contacts, edit or delete contacts, you may use the following options on the Default ribbon.

1. Contacts: This option will list all the contacts, where you can manage and maintain contact information for debtors (customers/clients) and creditors (suppliers/vendors). You may add new contacts, update contact details, delete contacts and print a list of all the contacts in your Set of Books.
2. Debtors - Contacts tab: This tab specifically focuses on managing contacts associated with debtor accounts. You can add, edit, or delete contacts linked to debtor accounts, ensuring that the contact details are up to date.
3. Creditors - Contacts tab: Similar to the Debtors - Contacts tab, this tab is dedicated to managing contacts associated with creditor accounts. You can modify the contact information for your suppliers/vendors to maintain accurate records.
4. Calendar - Contacts feature: provides the ability to manage contacts, ensuring that any changes made to contact information are reflected across the system. The following options on the Default ribbon allow you to create, edit, or delete contacts, with all updates being synchronized with the Contacts in the Calendar.

By utilising these options, you can conveniently manage contacts within osFinancials5/TurboCASH5, ensuring that all contact information remains consistent and accessible across different sections in a Set of Books.

Contacts report options

To print a list of all contacts:

1. On the Reports ribbon, select Reports → Contacts.



2. Sequence - Select "*First name, Name, Account"* or *"Description*".
3. Click on OK.

Printed : Contacts report



This contacts report may also be printed from the Print button on Contacts (Default ribbon).

Created with the Standard Edition of HelpNDoc: Create cross-platform Qt Help files

Batch entry (Reports menu)

Unposted batches

Batch reports for unposted batches may be printed from the F8:List option on "*Batch entry*" screens.

Posted batches

Once a batch or a document is posted (updated), batch reports may be printed from the following options:

- Reports → Batch entry (Reports ribbon).
  - Batch transactions per period - Print the transactions of posted invoices, credit notes, purchase and supplier return documents as well as posted batch transactions (i.e. sales journal, purchase journal, payments journals, receipts journals, general journals, etc.) for a specific selected period and for a selected batch type.
  - Batch type report - Documents - Print the transactions of all posted invoices, credit notes, purchase and supplier return documents for a specific selected period
- Selected posted batches and posted documents (Default ribbon).
  - Batch entry - Posted batches-Detail-tab

- Debtors - Documents-tab
- Debtors - Transactions-tab
- Creditors - Documents-tab
- Creditors - Transactions-tab
- Reverse posted batches (Global processes - Default ribbon)
- Reverse posted documents (Global processes - Default ribbon)

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

Batch report - Documents (Reports menu)

Print the transactions of all posted invoices, credit notes, purchase and supplier return documents for a specific selected period.

This report only includes document transactions which are posted. Unposted documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Batch entry - Documents report options

To print Batch entry - Documents reports:

1. On the Reports ribbon, select Reports → Batch entry.
2. Select "*Documents*", if not already selected.



3. Select the Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

4. Click on the OK button.

Printed : Batch type report - Documents report

Page 1 -


Documents
Batch type report - Documents
Period:
2022/03/01 - 2022/03/31
Period: 2022/03
IN000001 : Sales jnl. AB-IN110
Batch id Date Reference Description Account / Contra account Tax account Tax Debit Credit
10039 2022/03/13 IN000001 Paint - Exterior 010-000 1,000.00
10039 2022/03/13 IN000001 Invoice /AB-IN110 1AB-GRE 860-010 150.00 1,150.00
010-000
10039 2022/03/13 IN000001 Invoice /AB-IN110 860-010 150.00
Total amount 150.00 1,150.00 1,150.00
-150.00
IN000002 : Sales jnl. IB-101
Batch id Date Reference Description Account / Contra account Tax account Tax Debit Credit
10040 2022/03/14 IN000002 Install - Built-in cupboards 010-000 1,500.00
10040 2022/03/14 IN000002 Invoice /IB-101 1MA-CDS 860-010 225.00 1,725.00
010-000
10040 2022/03/14 IN000002 Invoice /IB-101 860-010 225.00
Total amount 375.00 2,875.00 2,875.00
-375.00
PU000001 : Purchase jnl. AAB234GP
Batch id Date Reference Description Account / Contra account Tax account Tax Debit Credit
10037 2022/03/14 PU000001 Maintenance 210-020 400.00
10037 2022/03/14 PU000001 Repairs 210-030 600.00
10037 2022/03/14 PU000001 Purchases /AAB234GP 2AB-CSC 860-020 -150.00 1,150.00
210-020
10037 2022/03/14 PU000001 Purchases /AAB234GP 860-020 150.00
Total amount 225.00 4,025.00 4,025.00
-225.00
PU000002 : Purchase jnl. IN0014
Batch id Date Reference Description Account / Contra account Tax account Tax Debit Credit
10038 2022/03/15 PU000002 Purchases /IN0014 2AB-COS 860-020 -225.00 1,725.00
600-010
10038 2022/03/15 PU000002 Furniture & fittings @ cost 600-010 1,500.00
10038 2022/03/15 PU000002 Purchases /IN0014 860-020 225.00
Total amount 0.00 5,750.00 5,750.00
IN000003 : Sales jnl. PH-101
Batch id Date Reference Description Account / Contra account Tax account Tax Debit Credit
10041 2022/03/15 IN000003 Paint - Exterior 010-000 1,000.00
10041 2022/03/15 IN000003 Invoice /PH-101 1AB-GRE 860-010 150.00 1,150.00
010-000
10041 2022/03/15 IN000003 Invoice /PH-101 860-010 150.00
Total amount 150.00 6,900.00 6,900.00
-150.00

Page 2 -


Documents
Batch type report - Documents
Period:
2022/03/01 - 2022/03/31
Period: 2022/03
IN000004 : Sales jnl. IB-102
Batch id Date Reference Description Account / Contra account Tax account Tax Debit Credit
10042 2022/03/16 IN000004 Install Built-in Cupboards 010-000 1,500.00
10042 2022/03/16 IN000004 Invoice /IB-102 1MD-AVI 860-010 225.00 1,725.00
010-000
10042 2022/03/16 IN000004 Invoice /IB-102 860-010 225.00
Total amount 375.00 8,625.00 8,625.00
-375.00
Total amount 375.00 8,625.00 8,625.00
-375.00

This report will list the following:

1. Document heading – Document number, Batch type and Reference (as entered in the "*Your reference*" field of "*Document entry*" screens).
2. Transaction details -
    a) Batch id. – The batch id or number as automatically generated.
    b) Date – Date of the transaction.
    c) Reference – The document number will be listed.
    d) Description – Document number / Your reference (as entered in the "*Your reference*" field of "*Document entry*" screens).
    e) Account – The account which was selected for documents.
    f) Contra account – The account for the document type.
    g) Tax account column – Tax account code.
    h) Tax – Tax amount.
    i) Debit column – Debit transaction amount.
    j) Credit column – Credit transaction amount.
3. Total amount – This amount is the accumulative sum of all document transactions.

The total in the Tax column, is the accumulative total of all Output tax on sales documents (Invoices and Credit notes) minus the accumulative total of all Input tax for purchase documents (Purchases and Supplier returns).

Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Batch transactions per period (Reports menu)

You may print the batch entry reports to check your batch entries of posted batch transactions and posted documents (i.e. invoices, credit notes, purchase and supplier return documents) for eacy selected batch type.

This report will display the Batch No., Date, Reference, Description, Account, Contra account, Tax account, Tax Amount, Debit and Credit transaction amounts (inclusive of Tax (VAT/GST/Sales Tax) and totals for each amount column.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Batch transactions per period report options

To print Batch entry reports:

1. On the Reports ribbon, select Reports → Batch entry.
2. Select "*Batch transactions per period*", if not already selected.



3. Select the following:
    a) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.
    b) Batch entry - Select the batch type from the list.
    c) Show Balancing Entries - By default, this option is not selected. It will only list the transactions entered into batches and/or the totals of documents and totals for each amount column. If this option is selected, it will list all the balancing entries.
4. Click on the OK button.

Printed : Batch transactions per period report

An example of the "*Batch type report*", for the "*Purchase jnl.*", ("*Show balancing entries*" not selected) report, is as follows:



Printed : Batch transactions per period (Show balancing entries) report

An example of the "*Batch type report*", for the "*Purchase jnl.*", ("*Show balancing entries*" selected) report, is as follows:



Batch transactions per period

Batch type report : Purchase jnl.

Period: 2022/03/01 - 2023/02/28 **Show balancing entries: Yes**

Period: 2022/03

Batch id	Date	Reference	Description	Account / Contra account	Tax account	Tax	Debit	Credit
10030	2022/03/05	PU001	Service - Delivery van	2AB-CSC	860-020	-60.00		460.00
				210-020				
10030	2022/03/05	*******	Service - Delivery van	860-020			60.00	
10030	2022/03/05	*******	Service - Delivery van	210-020			400.00	
10030	2022/03/05	PU001	5x New tyres - Fitting and balancing	2AB-CSC	860-020	-90.00		690.00
				210-030				
10030	2022/03/05	*******	5x New tyres - Fitting and balancing	860-020			90.00	
10030	2022/03/05	*******	5x New tyres - Fitting and balancing	210-030			600.00	
10030	2022/03/06	PU002	Install - Built-in cupboards	2AB-COS	860-020	-225.00		1,725.00
				600-010				
10030	2022/03/06	*******	Install - Built-in cupboards	860-020			225.00	
10030	2022/03/06	*******	Install - Built-in cupboards	600-010			1,500.00	
10037	2022/03/14	PU000001	Maintenance	210-020			400.00	
10037	2022/03/14	PU000001	Repairs	210-030			600.00	
10037	2022/03/14	PU000001	Purchases /AAB234GP	2AB-CSC	860-020	-150.00		1,150.00
				210-020				
10037	2022/03/14	PU000001	Purchases /AAB234GP	860-020			150.00	
10038	2022/03/15	PU000002	Purchases /IN0014	2AB-COS	860-020	-225.00		1,725.00
				600-010				
10038	2022/03/15	PU000002	Furniture & fittings @ cost	600-010			1,500.00	
10038	2022/03/15	PU000002	Purchases /IN0014	860-020			225.00	
					Total amount	-750.00	5,750.00	5,750.00
								-5,000.00

Period: 2022/04

Batch id	Date	Reference	Description	Account / Contra account	Tax account	Tax	Debit	Credit
10043	2022/04/05	PU000003	Purchases /4562	2AO-NES	860-020	-225.00		1,725.00
				750-000				
10043	2022/04/05	PU000003	Drill press	750-000			1,500.00	
10043	2022/04/05	PU000003	Purchases /4562	860-020			225.00	
10044	2022/04/06	PU000004	Purchases /3532	2BE-STS	860-020	-300.00		2,300.00
				750-000				
10044	2022/04/06	PU000004	Compressor	750-000			2,000.00	
10044	2022/04/06	PU000004	Purchases /3532	860-020			300.00	
					Total amount	-525.00	4,025.00	4,025.00
								-3,500.00

This report will list the following:

1. Batch id. - The batch id or number as automatically generated.
2. Date – Date of the transaction.
3. Alias – In the case of documents, the document number will be listed. In the case of batch transactions, the Alias as entered on each "*Batch entry*" screens will be displayed. If no Alias is entered on "*Batch entry*" screens, the Alias (Batch name) will be the same as the Batch type).
4. Account – The account which was selected for documents or in the Account lookup on "*Batch entry*" screens.

5. Contra account - The account which was selected as the Contra account on the F10:Setup on "*Batch entry*" screens.
6. Tax account column – Tax account code.
7. Debit column – Debit transaction amount.
8. Credit column – Credit transaction amount.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Tax (Reports menu)

Before you print tax reports to submit your Tax (VAT/GST/Sales tax) returns, you need to post (update) all batch transactions and documents (i.e. invoices, credit notes, purchase and supplier return documents) for the tax period.

The following tax reports are available:

1. Tax per period report – This report is used to complete the Tax (VAT/GST/Sales tax) returns. It will list a summary or the detail of the *Output tax* minus the *Input tax* and the *total tax payable / refundable*.
2. Tax report - Transactions - This report is similar to the "*Tax report - Reference / Document no.*" report. It will list the details of accounts and transactions of all posted (updated) batch and document transactions, on which Tax (VAT/GST/Sales tax is applicable. It will display the Tax code and description as well as the contra accounts for each transaction.
3. Tax report - Reference / Document no. - This report will list the details of accounts and transactions of all posted (updated) batch and document transactions, on which Tax (VAT/GST/Sales tax is applicable. It will display the Tax code and description as well as the contra accounts for each transaction.

The Tax excluded and Tax amount in the Report total of the Tax report - Reference / Document no. report, should balance with the Total - Output tax – Input tax of the Tax per period report, if the same periods are selected.

4. Tax list debtor with taxid - This report will list a total exclusive of tax, tax amount and inclusive amount of tax) for the Invoices *minus* Credit notes for debtor (customer / client) accounts for selected

period(s) or date(s). It will also display the Company and Tax registration numbers for each for debtor (customer / client) accounts.

5. Tax list creditor with tax id - This report will list a total exclusive of tax, tax amount and inclusive amount of tax) for the Purchase documents *minus* Supplier returns for creditor (supplier / vendor) accounts for selected period(s) or date(s). It will also display the Company and Tax registration numbers for each for creditor (supplier / vendor) accounts.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Tax per period (Reports menu)

Consolidate balancing - Standard tab - F10:Setup

The Tax report (Reports → Tax) does not include the Sales journal. It only includes Sales documents (i.e. Invoices an Credit notes). Transactions on other Batch types may cause similar errors.

The reason for this, is the Consolidate balancing option on the Standard tab - F10:Setup on the Options for this batch screen. When setting up the batch, an information message will be displayed.

> "Consolidating lines and using tax will mess up your tax report! Please make sure you do not use tax or do not consolidate lines!"

Click on the OK button and click on the F10:Setup icon and deselect (remove the tick) from the Consolidate balancing field on the Standard tab of the "Options for this batch" screen.

Balance the batch again.

You may print the "*Tax per period*" to check your tax transactions of posted batch transactions and posted documents (i.e. invoices, credit notes, purchase and supplier return documents).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Tax per period report options

To print Tax per period reports:

1. On the Reports ribbon, select Reports → Tax.

2. Select "*Tax per period*" report, if not already selected.



3. Select the following:

   a) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   > *For tax returns the period selected, should match the tax return date. In this example, the Tax (VAT) vendor needs to submit tax returns every second month (e.g., the period March and April).*

   b) Show details - By default, this option is not selected. It will only list the totals exclusive of Tax (VAT/GST/Sales Tax) for each tax code. If this option is selected, it will list all transactions and documents including the account code, account description, country and tax reference of the debtor or creditor account (if applicable).

   c) Show tax separately - Select this option to print each tax code on a new page.

   > *It is recommended that this option is only selected if the "Show details" option is selected.*

4. Click on the OK button.

Printed : Tax per period report

An example of the "*Tax per period*" (no details) report, is as follows:



Printed : Tax per period (Show details) report

An example of the "*Tax per period*" ("*Show details*" and "*Show tax separately*") report, is as follows:

Page 1 -



Page 2 -



Tax per period

Tax per period

Periods:
2022/03/01 - 2022/04/30

Show details: Yes
Show tax separately: Yes

T860020 Input VAT - Standard rate -15%

G210020 Maintenance

Date	Reference	Batch id	Code / Description / Country / Tax reference	Amount excl.	Tax amount
2022/03/05	******	10030	C2ABCSC ABC-Service-Centre 333333	-400.00	-60.00
2022/03/14	PU000001	10037	C2ABCSC ABC-Service-Centre 333333	-400.00	-60.00
	Total: G210020 - Maintenance			-800.00	-120.00

G210030 Repairs

Date	Reference	Batch id	Code / Description / Country / Tax reference	Amount excl.	Tax amount
2022/03/05	******	10030	C2ABCSC ABC-Service-Centre 333333	-600.00	-90.00
2022/03/14	PU000001	10037	C2ABCSC ABC-Service-Centre 333333	-600.00	-90.00
	Total: G210030 - Repairs			-1,200.00	-180.00

G220000 Rent

Date	Reference	Batch id	Code / Description / Country / Tax reference	Amount excl.	Tax amount
2022/03/30	107	10031	G220000 Rent	-500.00	-75.00
	Total: G220000 - Rent			-500.00	-75.00

G230000 Stationery

Date	Reference	Batch id	Code / Description / Country / Tax reference	Amount excl.	Tax amount
2022/03/30	110	10031	G230000 Stationery	-200.00	-30.00
2022/03/31	PCV001	10033	G230000 Stationery	-40.00	-6.00
	Total: G230000 - Stationery			-240.00	-36.00

G600010 Furniture & fittings @ cost

Date	Reference	Batch id	Code / Description / Country / Tax reference	Amount excl.	Tax amount
2022/03/06	******	10030	C2ABCOS ABC-Office-Supplies 444444	-1,500.00	-225.00
2022/03/15	PU000002	10038	C2ABCOS ABC-Office-Supplies 444444	-1,500.00	-225.00
	Total: G600010 - Furniture & fittings @ cost			-3,000.00	-450.00

G750000 Stock control

Date	Reference	Batch id	Code / Description / Country / Tax reference	Amount excl.	Tax amount
2022/04/05	PU000003	10043	C2AONES A-ONE Suppliers South Africa 906012	-1,500.00	-225.00
2022/04/06	PU000004	10044	C2BESTS BEST Suppliers South Africa 123456	-2,000.00	-300.00
	Total: G750000 - Stock control			-3,500.00	-525.00
			Input VAT - Standard rate -15% T860020	-9,240.00	-1,386.00

Page 3 -



Tax per period

Tax per period

Periods:
2022/03/01 - 2022/04/30

Show details: Yes
Show tax separately: Yes

T860030 Input VAT - Capital goods -15%

G600010 Furniture & fittings @ cost

Date	Reference	Batch id	Code / Description / Country / Tax reference	Amount excl.	Tax amount
2022/03/01	105	10031	G600010 Furniture & fittings @ cost	-500.00	-75.00
2022/03/01	106	10031	G600010 Furniture & fittings @ cost	-300.00	-45.00
	Total: G600010 - Furniture & fittings @ cost			-800.00	-120.00
			Input VAT - Capital goods -15% T860030	-800.00	-120.00
	Total: Output tax - Input tax			7,460.00	1,119.00

The Tax excluded and Tax amount in the Report total of the Tax report - Reference / Document no.

report, should balance with the Total - Output tax – Input tax of the Tax per period report, if the same periods are selected.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Tax report - Reference / Document no. (Reports menu)

You may print the "*Tax report - Reference / Document no*"., to check your tax transactions of posted batch transactions and posted documents (i.e. invoices, credit notes, purchase and supplier return documents).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Tax report - Reference / Document no. options

To print Tax report - Reference / Document no.:

1. On the Reports ribbon, select Reports → Tax.
2. Select "*Tax report - Reference / Document no.*", if not already selected.



3. Select the period on the Per period tab. You may click on the Free selection tab to select a specific

date or a range of dates.

4. Click on the OK button.

Printed : Tax report - Reference / Document no. report

An example of the printed "*Tax report - Reference / Document no.*", is as follows:

Page 1 -



Last page - Total



The Tax excluded and Tax amount in the Report total of the Tax report - Reference / Document no. report, should balance with the Total - Output tax – Input tax of the Tax per period report, if the same periods are selected.

Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Tax list debtor with taxid (Reports menu)

You may print the "*Tax list debtor with tax id*" report, to check your tax transactions of posted posted documents (i.e. invoices and credit notes).

This report will display a summary of the totals of the invoices and credit notes for each debtor account for a selected period or date(s).

Batch transactions are excluded from this report.

This report only includes document transactions which are posted. Unposted documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Tax list debtor with tax id. report options

To print Tax list debtor with tax id reports:

1. On the Reports ribbon, select Reports → Tax.

2. Select "*Tax list debtor with tax id*", if not already selected.



3. Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

4. Sequence - Select "*Debtor code, Tax reg. no.*" or "*Company reg. no.*" to print the report detail by the selected sequence (sort order).

5. Click on the OK button.

Printed : Tax list debtor with tax id. report

An example of the printed "*Tax list debtor with tax id*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Tax list creditor with taxid (Reports menu)

You may print the "*Tax list creditor with tax id*" report, to check your tax transactions of posted posted documents (i.e. purchase and supplier return documents).

This report will display a summary of the totals of the invoices and credit notes for each creditor account for a selected period or date(s).

Batch transactions are excluded from this report.

This report only includes document transactions which are posted. Unposted documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Tax list creditor with tax id. report options

To print Tax list creditor with tax id reports:

1. On the Reports ribbon, select Reports → Tax.

2. Select "*Tax list creditor with tax id*", if not already selected.



3. Select the period on the Per period tab. You may click on the Free selection tab to select a specific

date or a range of dates.

4. Sequence - Select "*Creditor code, Tax reg. no.*" or "*Company reg. no.*" to print the report detail by the selected sequence (sort order).

5. Click on the OK button.

Printed : Tax list creditor with tax id. report

An example of the printed "*Tax list creditor with tax id*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Tax - Transactions (Reports menu)

You may print the "*Tax report - Transactions*", to check your tax transactions of posted batch transactions and posted documents (i.e. invoices, credit notes, purchase and supplier return documents).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Tax - Transactions report options

To print Tax report - Transactions:

1. On the Reports ribbon, select Reports → Tax.

2. Select "*Tax report - Transactions*".



3. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

4. Click on the OK button.

Printed : Tax - Transactions report

An example of the printed "*Tax report - Transactions*", is as follows:

Page 1 -



Last page - Total



The Tax excluded and Tax amount in the Report total of the Tax report - Reference / Document no. report, should balance with the Total - Output tax – Input tax of the Tax per period report, if the same periods are selected.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Stock (Reports menu)

The following reports are available to manage the stock items:



1. Reorder - Stock Reorder Report to list only those stock items that needs to be reordered. The Current Stock Levels lists all the current stock levels.

2. Print labels – Print the Barcode or the Yagoda barcodes.

3. Stock item listing - Print the following lists:

    a) All selling prices - List all Selling price 1 / 2 /3 - (You may select to print extra details for these reports).

    b) Stock item listing - List the Quantities Cost prices. (You may select to print extra details for these reports).

    c) Tax classes - Displays a list of the Tax classes as well as the accounts linked to each of the Tax class (added / edited in the Tax classes tab on the Stock information screen. (Setup ribbon).

4. Backorder – Print a list of any stock items that are on backorder.

5. Stock In / Out - The following two (2) reports:

    a) Stock In / Out - Documents - Displays a summary of sales and purchase documents for each stock item. The details option will list and display the document dates and document numbers for each stock item.

    b) Stock In / Out - Displays a list of the stock items and the quantities in and out as well as the

total prices. The details option will list and display the document dates and document numbers for each stock item.

Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Stock - Reorder (Reports menu)

You may print the following two (2) reports to manage the reorder quantities an stock levels of your stock items.

1. Reorder report - Displays the only those stock items which are due to order.
2. Current stock levels - Displays all stock item quantities.

Created with the Standard Edition of HelpNDoc: Easy EBook and documentation generator

Stock - Reorder (Reports menu)

Reorder report - Displays the only those stock items which are due to order.

Reorder report options

To print Reorder reports:

1. On the Reports ribbon, select Reports → Stock → Reorder report.
2. Select "*Reorder report*", if not already selected.



3. Select the following:

    a) From... To... - Select the stock code(s) to include in the report.

    b) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

    c) Sequence - Select "*Stock code* or *Stock description*" to sort the order in which you need to print the data.

    d) Show details - By default, this option is not selected. It will display the reorder quantities. If this option is selected, it will display the details for each stock item.

4. Click on the OK button.

Printed : Reorder report

An example of the "*Reorder report*" (no details), is as follows:



Printed : Reorder (Show details) report

An example of the "*Reorder report*" ("*Show details*"), is as follows:



Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Stock - Reorder - Current stock levels (Reports menu)

Current Stock Levels - Displays all stock item quantities.

Reorder - Current stock levels report options

To print Reorder - Current stock levels reports:

1. On the Reports ribbon, select Reports → Stock → Reorder.
2. Select "*Current stock levels*" report, if not already selected.



3. Select the following:

    a) From... To... - Select the stock code(s) to include in the report.

    b) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

    c) Sequence - Select "*Stock code* or *Stock description*" to sort the order in which you need to print the data.

    d) Show details - By default, this option is not selected. It will display the reorder quantities. If this option is selected, it will display the details for each stock item.

4. Click on the OK button.

Printed : Reorder - Current stock levels report

An example of the "*Reorder report - Current stock levels*" (no details), is as follows:



Printed : Reorder - Current stock levels (Show details) report

An example of the"*Reorder report - Current stock levels*" ("*Show details*" selected), is as follows:



Created with the Standard Edition of HelpNDoc: Free help authoring tool

Stock - Print labels (Barcodes) (Reports menu)

You may print the following two (2) barcodes for stock items.

1. Barcode - Displays the stock code and stock description and the barcode.
2. Yagoda barcode - Displays the stock code, stock description and barcode as well as the selling price (exclusive of Tax (VAT/GST/Sales Tax)).

Print labels options

To print Barcodes for Stock items:

1. On the Reports ribbon, select Reports → Stock → Print labels.
2. Select the "*Barcode*" (default) or "*Yagoda barcode*".



3. Select the following:

    a) From... To... - Select the stock code(s) to print barcodes for.

    b) Sequence - Select "*Stock code* or *Stock description*" to sort the order in which you need to print the labels.

    c) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

4. Click on the OK button.

Printed : Barcode labels

An example of the "*Barcode*", is as follows:

Printed : Yagoda barcode labels

An example of the "*Yagoda barcode*", is as follows:



Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Stock - Stock item listing (Reports menu)

You may print the following two (2) reports to manage the stock items.

1. All selling prices - Displays a list of Selling prices 1 / 2 / 3. The details option will display the Extra description, Manufacturer, Gross and net weight.
2. Stock item listing - Displays a list of the stock items and the quantities and cost prices. The details option will display the Extra description, Manufacturer, Unit size, Gross and net weight, Selling price 1 / 2 / 3, Average cost, Unit cost, Barcode, Reporting group 1 / 2, Preferred supplier 1 and Supplier 1's Stock code.
3. Tax classes - Displays a list of the Tax classes as well as the accounts linked to each of the Tax class (added / edited in the Tax classes tab on the Stock information screen (Setup ribbon).

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Stock - Stock item listing - All selling prices (Reports menu)

You may print the following two (2) reports to manage the stock items.

1. All selling prices - Displays a list of Selling prices 1 / 2 / 3. The details option will display the Extra description, Manufacturer, Gross and Net weight.
2. Stock item listing - Displays a list of the stock items and the quantities and cost prices. The details

option will display the Extra description, Manufacturer, Unit size, Gross and net weight, Selling price 1 / 2 / 3, Average cost, Unit cost, Barcode, Reporting group 1 / 2, Preferred supplier 1 and Supplier 1's Stock code.

Stock item listing - All selling prices report options

To print Stock item listing - All selling prices reports:

1. On the Reports ribbon, select Reports → Stock → Stock item listing.
2. Select "*All selling prices*" report.



3. Select the following:
    a) From... To... - Select the stock code(s) to include in the report.
    b) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.
    c) Show details - By default, this option is not selected. If this option is selected, it will display the details for each stock item.
4. Click on the OK button.

Printed : Stock item listing - All selling prices report

An example of the "*All selling prices*" (no details) report, is as follows:



Printed : Stock item listing - All selling prices (Show details) report

An example of the "*All selling prices*" (Show details) report, is as follows:



Created with the Standard Edition of HelpNDoc: Easily create EBooks

Stock - Stock item listing (Reports menu)

Stock item listing - Displays a list of the stock items and the quantities and cost prices. The details option will display the Extra description, Manufacturer, Unit size, Gross and net weight, Selling price 1 / 2 / 3, Average cost, Unit cost, Barcode, Reporting group 1 / 2, Preferred supplier 1 and Supplier 1's Stock code.

Stock item listing report options

To print Stock item listing reports:

1. On the Reports ribbon, select Reports → Stock → Stock item listing.
2. Select "*Stock item listing*" report.



3. Select the following:

    a) From... To... - Select the stock code(s) to include in the report.

    b) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

    c) Show details - By default, this option is not selected. If this option is selected, it will display the details for each stock item.

    d) New Page per Item - This option is only applicable to the Stock item listing report.

4. Click on the OK button.

Printed : Stock item listing report

An example of the "*Stock item listing*" (no details) report, is as follows:



Printed : Stock item listing (Show details) report

An example of the "*Stock item listing*" ("*Show details*") report, is as follows:



Stock item listing

Stock item listing

From stock code: 3COMP **To: 3DRILL**

Sequence: Stock description **Show details: Yes**
New page per item: No

Code	Description	Units	On hand - Unposted	Quantities On hand	Value
3COMP	Compressor	Each	1	5	4,800.00
Extra description		Manufacturer		Net weight	Gross weight
		CMP		0	0
Selling price 1	Selling price 2	Selling price 3	Average cost		Unit cost
1,500.00	1,600.00	1,700.00	0.00		960.00
Barcode		Reporting group 1	Reporting group 2		
3456789123		Power tools	Unallocated		
Preferred supplier1		*Preferred supplier2*			
C2AONES A-ONE Suppliers		C2BESTS BEST Suppliers			
A1-12345		B-12345			
3DRILL	Drill press	Each	6	10	5,000.00
Extra description		Manufacturer		Net weight	Gross weight
850 Watts + 6 drill bits		Bosch		0	0
Selling price 1	Selling price 2	Selling price 3	Average cost		Unit cost
1,000.00	1,100.00	1,200.00	0.00		500.00
Barcode		Reporting group 1	Reporting group 2		
1234567890		Power tools	Unallocated		
Preferred supplier1		*Preferred supplier2*			
C2AONES A-ONE Suppliers		C2BESTS BEST Suppliers			
A-12345		B-12345			

Total Value: 9,800.00

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Stock - Stock item listing - Tax classes (Reports menu)

Stock item listing - Tax classes - Displays a list of the Tax classes as well as the accounts linked to each of the Tax class (added / edited in the Tax classes tab on the Stock information screen (Setup ribbon).

When creating or editing stock items, the Tax classes you may select a Tax class to automatically link the set of five (5) accounts (linked to the Ledger tab of the Stock screen (Default ribbon) for a selected stock item.

When a stock item is linked to a tax class, it will disable the Lookup button on the Ledger tab of the Stock screen for a selected stock item. It will automatically set the Input and Output Tax, Sales, Cost of sales and Stock control account fields without having to select them for each stock item.

Stock item listing - Tax classes report options

To print Stock item listing - Tax classes reports:

1. On the Reports ribbon, select Reports → Stock → Stock item listing.

2. Select "*Tax classes*" report.



3. Select the Sequence (i.e. ID (record Id) or description) for the sequence to list the tax classes.

4. Click on the OK button.

Printed : Stock item listing - Tax classes report

An example of the "*Tax class - Listing*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Stock - Backorder (Reports menu)

The backorder report will display any stock items that are on backorder. Backorders are usually added for

the difference on the Quantity Order and Quantity Shipped fields on the Document entry screen. When processing invoices and credit notes, and a backorder exists for the debtor (customer / client) a screen on which you may select the items on backorder is displayed.

You may also add, edit or delete backorders on the Input → Documents → Backorders, or on the Backorders tab of the Stock items and Debtor (Default ribbon).

Backorder report options

To print a Backorder report:

1. On the Reports ribbon, select Reports → Stock → Backorder.



2. Select the following:

    a) From... To... - Select the stock code(s) to include in the report.

    b) Sequence - Select "*Stock code* or *Stock description*" to sort the order in which you need to print the data.

3. Click on the OK button.

Printed : Backorder report

An example of the Backorder report, is as follows:



It will display the following information:

1. Debtor - Account number and name
2. Referral Source - The Document number and the reference added in the "*Your reference*" field of the Document entry screen.
3. On Hand - The quantity of the stock item on hand.
4. Qty - Quantity on backorder.
5. Selling price - The selling price per item (exclusive of Tax (VAT/GST/Sales Tax).
6. Disc% - The discount percentage if the "*Apply invoice discount*" field is selected (ticked) for the Stock item and Customer discount percentage is specified on the Accounting information tab for the debtor (customer / client). It my also be entered or edited when processing invoices.
7. Price - The selling price per item minus the discount percentage (exclusive of Tax (VAT/GST/Sales Tax).

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Stock - In / Out (Reports menu)

You may print the following two (2) reports to manage stock items.

1. Stock In / Out - Documents - Displays a summary of sales and purchase documents for each stock item. The details option will list and display the document dates and document numbers for each stock item.
2. Stock In / Out - Displays a list of the stock items and the quantities in and out as well as the total prices. The details option will list and display the document dates and document numbers for each

stock item.

Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

Stock - In / Out - Documents (Reports menu)

Stock In / Out - Documents - Displays a summary of sales and purchase documents for each stock item. The details option will list and display the document dates and document numbers for each stock item.

This report only includes document transactions which are posted. Unposted documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Stock In / Out - Documents report options

To print Stock In / Out - Documents reports:

1. On the Reports ribbon, select Reports → Stock → Stock In / Out.
2. Select "*Documents*" report, if not already selected.



3. Select the following:

    a) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

    b) From... To... - Select the stock code(s) to include in the report.

    c) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

    d) Show details - By default, this option is not selected. If this option is selected, it will display the details for each stock item.

    e) New Page per Item - If this option is selected (ticked), it will print the transactions for each stock item on a new page.

    > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

4. Click on the OK button.

Printed : Stock In / Out - Documents report

An example of the "*Stock In / Out - Documents*" (no details) report, is as follows:



Printed : Stock In / Out - Documents (Show details) report

An example of the "*Stock In / Out - Documents*" report ("*Show details*" and "*New page per item*"), is as follows:

Page 1- Compressor



Page 2 - Drill press



Stock In / Out - Documents

From stock code: 3COMP **To: SALES-NS**

Period: 2021/03/01 - 2022/02/28

Sequence: Stock code
Show details: Yes
New page per item: Yes

Code	Description	Units
3DRILL	Drill press	Each

Date	Document no.	Qty	*Document reference*	Selling price / Cost price	Document type
2021/04/01	OR000002	3	4562	1 500,00	Order
2021/04/01	QU000002	1	D-101	1 000,00	Quote
2021/04/05	PU000003	3	4562	1 500,00	Purchases
2021/04/07	IN000005	1	D-101	1 000,00	Invoice
2021/04/11	IN000008	2	D-102	2 000,00	Invoice
2021/05/07	ST00002	5	Shortage		Stock in
2021/05/07	ST00001	-15	Surplus		Stock in
2021/05/08	IN000010	1		1 000,00	Invoice
2021/05/30	OR000004	3	4562	1 500,00	Order
2021/06/05	IN000011	1	D-101	1 000,00	Invoice
2021/06/12	IN000014	2	D-102	2 000,00	Invoice
2021/06/15	IN000015	1	D-101	1 000,00	Invoice
2021/06/17	SR000002	3	4562	1 500,00	Supplier returns
2021/06/19	SR000003	3	4562	1 500,00	Supplier returns
2021/06/20	IN000017	1	C-103	1 000,00	Invoice
2021/06/20	QU000004	1	D-102	1 000,00	Quote
2021/06/22	CR000002	2	D-102	2 000,00	Credit notes
2021/06/24	IN000018	2	D-102	2 000,00	Invoice
2021/06/24	QU000005	2	C-103	2 000,00	Quote
2021/06/25	PU000007	3	4562	1 500,00	Purchases
2021/06/26	PU000005	3	4562	1 500,00	Purchases
2021/06/26	SR000004	3	4562-A	1 500,00	Supplier returns
2021/06/30	IN000019	2	D-101	2 000,00	Invoice
2021/06/30	IN000020	2	A-103-2	2 000,00	Invoice
2021/06/30	CR000001	2	D-101	2 000,00	Credit notes
2021/06/30	CR000003	1	C-103	1 000,00	Credit notes
2021/06/30	IN000021	2	C-103	2 000,00	Invoice
2021/06/30	IN000022	2	C-103	2 000,00	Invoice

Invoice	19	19 000,00
Credit notes	-5	-5 000,00
Purchases	-9	-4 500,00
Supplier returns	9	**4 500,00**
Orders	4	4 000,00
Quotes	6	3 000,00
Adjustment	-10	0,00
Total	**14**	**21 000,00**



Documents

Stock In / Out - Documents

From stock code: 3COMP — To: SALES-NS

Period: 2021/03/01 - 2022/02/28

Sequence: Stock code
Show details: Yes
New page per item: Yes

Code	Description	Units
3DRILL	Drill press	Each

Date	Document no.	Qty	Selling price / Cost price	Document type
2021/04/01	OR000002	3	1,500.00	Order
2021/04/01	QU000002	1	1,000.00	Quote
2021/04/05	PU000003	3	1,500.00	Purchases
2021/04/07	IN000005	1	1,000.00	Invoice
2021/04/11	IN000008	2	2,000.00	Invoice
2021/05/07	ST00002	5		Stock in
2021/05/07	ST00001	-15		Stock in
2021/05/08	IN000010	1	1,000.00	Invoice
2021/05/30	OR000004	3	1,500.00	Order
2021/06/05	IN000011	1	1,000.00	Invoice
2021/06/12	IN000014	2	2,000.00	Invoice
2021/06/15	IN000015	1	1,000.00	Invoice
2021/06/17	SR000002	3	1,500.00	Supplier returns
2021/06/19	SR000003	3	1,500.00	Supplier returns
2021/06/20	IN000017	1	1,000.00	Invoice
2021/06/20	QU000004	1	1,000.00	Quote
2021/06/22	CR000002	2	2,000.00	Credit notes
2021/06/24	IN000018	2	2,000.00	Invoice
2021/06/24	QU000005	2	2,000.00	Quote
2021/06/25	PU000007	3	1,500.00	Purchases
2021/06/26	PU000005	3	1,500.00	Purchases
2021/06/26	SR000004	3	1,500.00	Supplier returns
2021/06/30	IN000019	2	2,000.00	Invoice
2021/06/30	IN000020	2	2,000.00	Invoice
2021/06/30	CR000001	2	2,000.00	Credit notes
2021/06/30	CR000003	1	1,000.00	Credit notes
2021/06/30	IN000022	2	2,000.00	Invoice
2021/06/30	IN000021	2	2,000.00	Invoice

Invoice	19	19,000.00
Credit notes	-5	-5,000.00
Purchases	-9	-4,500.00
Supplier returns	9	4,500.00
Orders	4	4,000.00
Quotes	6	3,000.00
Adjustment	-10	0.00
Total	14	21,000.00

The document numbers for Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders, as prefixed in the Documents setup (Setup ribbon), makes it easy to identify the document type.

In addition to these standard document numbers, the following documents may be included:

- *Stock adjustments - Document numbers prefixed with "ST" is a 7-digit document number. These are automatically generated when doing stock adjustments (changes in the quantities on hand). These stock adjustments does not show any transactions and it prints a blank Posted batch type reports.*
- *BOM (Production) stock type - Assemble / Disassemble context menu options - Document numbers prefixed with"SA" will be a 7-digit number.*
- *Project Quote - Document numbers prefixed with"D" will be a 7-digit number.*

Created with the Standard Edition of HelpNDoc: Make Your PDFs More Secure with Encryption and Password Protection

Stock - In / Out (Reports menu)

Stock In / Out - Displays a list of the stock items and the quantities in and out as well as the total prices. The details option will list and display the document dates and document numbers for each stock item.

This report only includes document transactions which are posted. Unposted documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Stock In / Out report options

To print Stock In / Out reports:

1. On the Reports ribbon, select Reports → Stock → Stock In / Out.
2. Select "*Stock In / Out*" report, if not already selected.



3. Select the following:

    a) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

    b) From... To... - Select the stock code(s) to include in the report.

    c) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

    d) Show details - By default, this option is not selected. If this option is selected, it will display the details for each stock item.

    e) New Page per Item - If this option is selected (ticked), it will print the transactions for each stock item on a new page.

    > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

4. Click on the OK button.

Printed : Stock In / Out report

An example of the "*Stock In / Out*" (no details) report, is as follows:



Printed : Stock In / Out (Show details) report

An example of the "*Stock In / Out*" report ("*Show details*" and "*New page per item*"), is as follows:

Page 1 - Compressor



Page 2 - Drill press



Stock In / Out

Stock In / Out

From stock code: 3COMP **To: SALES-NS**

Period: 2021/03/01 - 2022/02/28

Sequence: Stock code
Show details: Yes
New page per item: Yes

Code	Description	Units	Quantities	Value
3DRILL	Drill press	Each	0	5 010,53

Date	Document no.	Document reference	Qty	Cost price	Selling price / Cost price	Document type
2021/03/01	Opening balances	0				
2021/04/05	PU000003	4562	3	500,00	500,00	Purchases
2021/04/07	IN000005	D-101	-1	500,00	1 000,00	Invoice
2021/04/11	IN000008	D-102	-2	500,00	1 000,00	Invoice
2021/05/07	ST00002	Shortage	-5	0,00	500,00	Stock in
2021/05/07	ST00001	Surplus	15	0,00	500,00	Stock in
2021/05/08	IN000010		-1	500,00	1 000,00	Invoice
2021/06/05	IN000011	D-101	-1	500,00	1 000,00	Invoice
2021/06/12	IN000014	D-102	-2	500,00	1 000,00	Invoice
2021/06/15	IN000015	D-101	-1	500,00	1 000,00	Invoice
2021/06/17	SR000002	4562	-3	500,00	500,00	Supplier returns
2021/06/19	SR000003	4562	-3	500,00	500,00	Supplier returns
2021/06/20	IN000017	C-103	-1	500,00	1 000,00	Invoice
2021/06/22	CR000002	D-102	2	500,00	1 000,00	Credit notes
2021/06/24	IN000018	D-102	-2	500,00	1 000,00	Invoice
2021/06/25	PU000007	4562	3	520,00	500,00	Purchases
2021/06/26	PU000005	4562	3	500,00	500,00	Purchases
2021/06/26	SR000004	4562-A	-3	500,00	500,00	Supplier returns
2021/06/29	CR000001	D-101	2	500,00	1 000,00	Credit notes
2021/06/30	IN000019	D-101	-2	500,00	1 000,00	Invoice
2021/06/30	IN000020	A-103-2	-2	500,00	1 000,00	Invoice
2021/06/30	CR000003	C-103	1	500,00	1 000,00	Credit notes

Report total **10 010,53**

The document numbers for Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders, as prefixed in the Documents setup (Setup ribbon), makes it easy to identify the document type.

In addition to these standard document numbers, the following documents may be included:

- *Stock adjustments - Document numbers prefixed with "ST" is a 7-digit document number. These are automatically generated when doing stock adjustments (changes in the quantities on hand). These stock adjustments does not show any transactions and it prints a blank Posted batch type reports.*
- *BOM (Production) stock type - Assemble / Disassemble context menu options - Document numbers prefixed with"SA" will be a 7-digit number.*
- *Project Quote - Document numbers prefixed with"D" will be a 7-digit number.*

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Documents (Reports menu)

The following reports are available to print lists of documents:



1. Document listing – Select Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders.
2. Document listing per account
    a) Sales documents – Select to list only posted or unposted Invoices or Credit notes or unconfirmed / open / confirmed Quotes.
    b) Purchase documents – Select to list only posted or unposted Purchases or Supplier returns or unconfirmed / open / confirmed Orders.
3. Unprinted document listing – This is similar to the Document listing per account reports. It will list all documents which have not yet been printed.
    a) Sales documents – Select to list the posted and unposted sales documents (i.e. Invoices, Credit notes and Quotes) for selected debtor (customer / client) account(s), which is not printed.

b) Purchase documents – Select to list the posted and unposted purchase documents (i.e. Purchase documents, Supplier returns and Orders) for selected creditor (supplier / vendor) account(s), which is not printed.

Created with the Standard Edition of HelpNDoc: Eliminate the Struggles of Documentation with a Help Authoring Tool

Document listing (Reports menu)

This option allows you to print a list of all posted and unposted sales documents (i.e. Invoices, Credit notes or Quotes) by debtor (customer / client) account and purchase documents (i.e. Purchases, Supplier returns or Orders) by creditor (supplier / vendor) account.

Document listing report options

To print Document listing reports:

1. On the Reports ribbon, select Reports → Documents → Document listing.



2. Select the following:

a) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

b) Document type - By default, Invoice is selected. Select sales documents (i.e. Credit note or Quotes) or purchase documents (i.e. Purchase, Supplier return or Order).

c) Sequence - Select "*Document no., Date, Tax inclusive, Tax exclusive, Link tax, Posted, Unposted* or *Your reference*" to sort the order in which you need to print the document listing.

3. Click on the OK button.

Printed : Document listing report - Invoices

An example of the "*Document listing - Invoices*" report, is as follows:



Documents listing

Documents listing - Invoice

Periods: 2021/03/01 - 2022/02/28

Sequence: Date

Doc. no.	Date	Your reference Link tax	Posted	Printed	Excl. amt.	Incl. amt.	Tax
IN000020	2021/06/30	A-103-2 Output VAT - 15%	Yes	16	5,000.00	5,750.00	750.00
IN000021	2021/06/30	C-103 Output VAT - 15%	No	1	5,000.00	5,750.00	750.00
IN000022	2021/06/30	C-103 Output VAT - 15%	No	47	5,000.00	5,750.00	750.00
IN000019	2021/06/30	D-101 Output VAT - 15%	Yes	0	5,000.00	5,750.00	750.00
IN000018	2021/06/24	D-102 Output VAT - 15%	Yes	0	2,000.00	2,300.00	300.00
IN000017	2021/06/20	C-103 Output VAT - 15%	Yes	0	2,500.00	2,875.00	375.00
IN000016	2021/06/17	C-102 Output VAT - 15%	Yes	0	3,000.00	3,450.00	450.00
IN000015	2021/06/15	D-101 Output VAT - 15%	Yes	0	1,000.00	1,150.00	150.00
IN000014	2021/06/12	D-102 Output VAT - 15%	Yes	0	2,000.00	2,300.00	300.00
IN000013	2021/06/10	C-103 Output VAT - 15%	Yes	0	1,500.00	1,725.00	225.00
IN000012	2021/06/07	C-102 Output VAT - 15%	Yes	0	3,000.00	3,450.00	450.00
IN000011	2021/06/05	D-101 Output VAT - 15%	Yes	0	1,000.00	1,150.00	150.00
IN000010	2021/05/08	Output VAT - 15%	Yes	0	1,000.00	1,150.00	150.00
IN000009	2021/05/07	PH-101 Output VAT - 15%	Yes	3	1,000.00	1,150.00	150.00
IN000008	2021/04/11	D-102 Output VAT - 15%	Yes	2	2,000.00	2,300.00	300.00
IN000007	2021/04/10	C-103 Output VAT - 15%	Yes	0	1,500.00	1,725.00	225.00
IN000006	2021/04/09	C-102 Output VAT - 15%	Yes	2	3,000.00	3,450.00	450.00
IN000005	2021/04/07	D-101 Output VAT - 15%	Yes	0	1,000.00	1,150.00	150.00
IN000004	2021/03/16	IB-102 Output VAT - 15%	Yes	0	1,500.00	1,725.00	225.00
IN000003	2021/03/15	PH-101 Output VAT - 15%	Yes	0	1,000.00	1,150.00	150.00
IN000002	2021/03/14	IB-101 Output VAT - 15%	Yes	0	1,500.00	1,725.00	225.00
IN000001	2021/03/13	AB-IN110 Output VAT - 15%	Yes	0	1,000.00	1,150.00	150.00
Total: Invoice		Periods: 2021/03/01 - 2022/02/28			50,500.00	58,075.00	7,575.00

Created with the Standard Edition of HelpNDoc: Elevate Your Documentation with HelpNDoc's Project Analyzer Features

Document listing per account (Reports menu)

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Document listing per account - Sales documents (Reports menu)

This option allows you to print a list of all posted or unposted sales documents (i.e. Invoices, Credit notes and Quotes) for selected debtor (customer / client) account(s).

Document listing per account - Sales documents report options

To print Document listing per account reports:

1. On the Reports ribbon, select Reports → Documents → Document listing per account → Sales documents.



2. Select the following:

    a) Report - By default, Invoices is selected. Select sales documents (i.e. Credit notes or Quotes).

    b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

    c) From... To... - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in this report.

    d) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

    e) Posted - By default, this field is not selected (not ticked). It will list only the unposted invoices (or unposted credit notes or unconfirmed (open) quotes). If this field is selected (ticked), it will

list only the posted invoices (or posted credit notes or confirmed (posted) quotes).

> *If Quotes is selected, the "Posted" option will change to "Confirmed".*

f) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Document listing per account - Sales documents report - Invoices

An example of the "*Document listing per account - Invoices*" ("*not posted*") report, is as follows:



Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Document listing per account - Purchase documents (Reports menu)

This option allows you to print a list of all posted or unposted purchase documents (i.e. Purchases,

Supplier returns or Orders) for selected creditor (supplier / vendor) account(s).

Document listing per account - Purchase documents report options

To print Document listing per account reports:

1. On the Reports ribbon, select Reports → Documents → Document listing per account → Purchase documents.



2. Select the following:

    a) Report - By default, Purchases is selected. Select purchase documents (i.e. Supplier returns or Orders).

    b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

    c) From... To... - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in this report.

    d) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

    e) Posted - By default, this field is not selected (not ticked). It will list only the unposted purchase documents (or unposted supplier return documents or unconfirmed (open) orders). If this field is selected (ticked), it will list only the posted purchase documents (or posted supplier return documents or confirmed (posted) orders).

If Orders is selected, the "Posted" option will change to "Confirmed".

f) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.

3. Click on the OK button.

Printed : Document listing per account - Purchase documents report - Purchases

An example of the "*Document listing per account - Purchases*" ("*Posted*") report, is as follows:



Purchases

Document listing per account - Purchases

From account: C2ABCOS To: C2SUNSU

Period: 2021/03/01 - 2022/02/28

Sequence: Creditor code
Posted: Yes
New page per account: No

C2ABCOS ABC-Office-Supplies

Doc. no.	Date	Item code / Item description	Quantity	Discount	Excl. amt.	Tax	Incl. amt.	Printed
PU000002	2021/03/15	GL-CODE General ledger	1.00	0.00	1,500.00	225.00	1,725.00	4
PU000007	2021/06/25	3DRILL Drill press	3.00	0.00	1,500.00	225.00	1,725.00	0
Total:				0.00	3,000.00	450.00	3,450.00	

C2ABCSC ABC-Service-Centre

Doc. no.	Date	Item code / Item description	Quantity	Discount	Excl. amt.	Tax	Incl. amt.	Printed
PU000001	2021/03/14	GL-CODE General ledger	1.00	0.00	600.00	90.00	690.00	0
PU000001	2021/03/14	GL-CODE General ledger	1.00	0.00	400.00	60.00	460.00	0
Total:				0.00	1,000.00	150.00	1,150.00	

C2AONES A-ONE Suppliers

Doc. no.	Date	Item code / Item description	Quantity	Discount	Excl. amt.	Tax	Incl. amt.	Printed
PU000003	2021/04/05	3DRILL Drill press	3.00	0.00	1,500.00	225.00	1,725.00	0
PU000005	2021/06/26	3DRILL Drill press	3.00	0.00	1,500.00	225.00	1,725.00	1
PU000006	2021/06/09	3COMP Compressor	2.00	0.00	2,000.00	300.00	2,300.00	2
Total:				0.00	5,000.00	750.00	5,750.00	

C2BESTS BEST Suppliers

Doc. no.	Date	Item code / Item description	Quantity	Discount	Excl. amt.	Tax	Incl. amt.	Printed
PU000004	2021/04/06	3COMP Compressor	2.00	0.00	2,000.00	300.00	2,300.00	0
Total:				0.00	2,000.00	300.00	2,300.00	

Report total: 11,000.00 1,650.00 12,650.00

Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Unprinted document listing (Reports menu)

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Unprinted document listing - Sales documents (Reports menu)

This option allows you to print a list of all posted and unposted sales documents (i.e. Invoices, Credit notes and Quotes) for selected debtor (customer / client) account(s), which is not printed.

Unprinted document listing - Sales documents report options

To print Unprinted document listing per account reports:

1. On the Reports ribbon, select Reports → Documents → Unprinted document listing → Sales documents.



2. Select the following:

    a) Report - By default, Invoices is selected. Select sales documents (i.e. Credit notes or Quotes).

    b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

    c) From... To... - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in this report.

    d) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

    e) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is*

displayed in the Page footer.

3. Click on the OK button.

Printed : Unprinted document listing - Sales documents report - Invoices

An example of the "*Unprinted document listing - Invoices*" report for the 2 month period "*May 2021*" to "June 2021", is as follows:



Invoices

Unprinted document listing - Invoices

From account: D1ABGRE To: D1MDAVI

Period: 2021/05/01 - 2021/06/30
Sequence: Debtor code
New page per account: No

D1ABGRE Mr. AB Green

Doc. no.	Date	Item code / Item description	Quantity	Discount	Excl. amt.	Tax	Incl. amt.	Posted
IN000011	2021/06/05	3DRILL Drill press	1.00	0.00	1,000.00	150.00	1,150.00	Yes
IN000019	2021/06/30	3COMP Compressor	2.00	0.00	3,000.00	450.00	3,450.00	Yes
IN000019	2021/06/30	3DRILL Drill press	2.00	0.00	2,000.00	300.00	2,300.00	Yes
Total:				0.00	6,000.00	900.00	6,900.00	

D1MDAVI Mr. Mike Davies

Doc. no.	Date	Item code / Item description	Quantity	Discount	Excl. amt.	Tax	Incl. amt.	Posted
IN000010	2021/05/08	3DRILL Drill press	1.00	0.00	1,000.00	150.00	1,150.00	Yes
IN000013	2021/06/10	3COMP Compressor	1.00	0.00	1,500.00	225.00	1,725.00	Yes
IN000015	2021/06/15	3DRILL Drill press	1.00	0.00	1,000.00	150.00	1,150.00	Yes
IN000017	2021/06/20	3COMP Compressor	1.00	0.00	1,500.00	225.00	1,725.00	Yes
IN000017	2021/06/20	3DRILL Drill press	1.00	0.00	1,000.00	150.00	1,150.00	Yes
Total:				0.00	6,000.00	900.00	6,900.00	

Report total: 12,000.00 1,800.00 13,800.00

Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Unprinted document listing - Purchase documents (Reports menu)

This option allows you to print a list of all posted and unposted purchase documents (i.e. Purchase documents, Supplier returns and Orders) for selected creditor (supplier / vendor) account(s), which is not

printed.

Unprinted document listing - Purchase documents report options

To print Unprinted document listing per account reports:

1. On the Reports ribbon, select Reports → Documents → Unprinted document listing → Purchase documents.



2. Select the following:

   a) Report - By default, Purchases is selected. Select purchase documents (i.e. Supplier returns or Orders).

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) From... To... - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in this report.

   d) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   e) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is*

displayed in the Page footer.

3. Click on the OK button.

Printed : Unprinted document listing - Purchase documents report - Purchases

An example of the "*Unprinted document listing - Purchases*" report, is as follows:



Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Sales - (Reports menu)

Various reports are available on the Reports → Sales menu to analyse each of the sales documents (i.e. Quotes, Invoices and Credit notes). The reports for Invoices are as follows:

1. D



ebtors – Debtor – Invoices per period – Quantities.

2. Sales – Invoices per period – Quantities

3. Items - Items per period.

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Review with HelpNDoc's Project Analyzer

Sales - Invoices (Reports menu)

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Invoices - Debtors (Reports menu)

The Debtor - Invoices per period - Quantities report displays the Stock code, Stock description, Quantities, Selling prices and Cost prices (if applicable to stock items) for each debtor (customer / client) account.

This report only includes Invoices which are posted. Unposted Invoices will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtors - Invoices per period - Quantities report options

To print a Debtor - Invoices per period - Quantities report:

1. On the Reports ribbon, select Reports → Sales → Invoices → Debtors.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates. page.

3. Click on the OK button.

Printed : Debtors - Invoices per period - Quantities report

An example of the "*Debtors - Invoices per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Invoices - Sales (Reports menu)

This option allows you to print the posted "*Invoices per period - Quantities*" or the "*Invoices per period - Turnover*" report. It displays the Stock code, Stock description, Quantities, Selling prices and Cost prices (if applicable to stock items).

This report only includes Invoices which are posted. Unposted Invoices will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Invoices per period - Quantities report options

To print Invoices per period reports:

1. On the Reports ribbon, select Reports → Sales → Invoices → Sales.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Invoices per period - Quantities report

An example of the "*Invoices per period - Quantities*" report, is as follows:



Code	Item description	Quantities	Selling price	Cost price	Profit/Loss	P/L %
3DRILL	Drill press	15.00	15,000.00	7,500.00	-7,500.00	50.00
3COMP	Compressor	13.00	19,500.00	13,000.00	-6,500.00	33.33
4L-INSTCUP	Install - Built-in cupboards	6.00	3,000.00	0.00	-3,000.00	100.00
4L-PAINT-E	Paint - Exterior	6.00	3,000.00	0.00	-3,000.00	100.00
Report total:		40.00	40,500.00	20,500.00	-20,000.00	70.83

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Invoices - Items (Reports menu)

The Invoices - Items per period report displays the Stock code, Stock description and totals (i.e. Quantities and Selling prices) for each stock item.

This report only includes Invoices which are posted. Unposted Invoices will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Invoices - Items per period report options

To print an Invoices - Items per period report:

1. On the Reports ribbon, select Reports → Sales → Invoices → Items.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Invoices - Items per period report

An example of the "*Invoices - Items per period*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Sales - Credit notes (Reports menu)

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Credit notes - Debtors (Reports menu)

The Debtor - Credit notes per period - Quantities report displays the Stock code, Stock description, Quantities, Selling prices and Cost prices (if applicable to stock items) for each debtor (customer / client) account.

This report only includes Credit notes which are posted. Unposted Credit notes will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtors - Credit notes per period - Quantities report options

To print a Debtor - Credit notes per period - Quantities report:

1. On the Reports ribbon, select Reports → Sales → Credit notes → Debtors.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Debtors - Credit notes per period - Quantities report

An example of the "*Debtor - Credit notes per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Free EPub producer

Credit notes - Sales (Reports menu)

This option allows you to print the posted Credit notes per period report. It displays the Stock code, Stock description, Quantities, Selling prices and Cost prices (if applicable to stock items).

This report only includes Credit notes which are posted. Unposted Credit notes will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Credit notes per period - Quantities report options

To print Credit notes per period reports:

1. On the Reports ribbon, select Reports → Sales → Credit notes → Sales.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Credit notes per period - Quantities report

An example of the "*Credit notes per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Credit notes - Items (Reports menu)

The Credit notes - Items per period report displays the Stock code, Stock description and totals (i.e. Quantities and Selling prices) for each stock item.

This report only includes Credit notes which are posted and/or confirmed. Unconfirmed (open) Credit notes will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Credit notes - Items per period report options

To print a Credit notes - Items per period report :

1. On the Reports ribbon, select Reports → Sales → Credit notes → Items.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Credit notes - Items per period report

An example of the "*Credit notes - Items per period*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of a Help Authoring Tool

Sales - Quotes (Reports menu)

Created with the Standard Edition of HelpNDoc: Easy to use tool to create HTML Help files and Help web sites

Quotes - Debtors (Reports menu)

The Debtor - Quotes per period - Quantities report displays the Stock code, Stock description, Quantities, Selling prices for each debtor (customer / client) account.

This report only includes Quotes which are posted and/or confirmed. Unconfirmed (open) Quotes will be NOT be included in this report.

Debtors - Quotes per period - Quantities report options

To print a Debtors - Quotes per period - Quantities report:

1. On the Reports ribbon, select Reports → Sales → Quotes → Debtors.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Debtors - Quotes per period - Quantities report

An example of the "*Debtors - Quotes per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Quotes - Sales (Reports menu)

This option allows you to print the posted Quotes per period report. It displays the Stock code, Stock description, Quantities, Selling prices and Cost prices (if applicable to stock items).

This report only includes Quotes which are posted and/or confirmed. Unconfirmed (open) Quotes will be NOT be included in this report.

Quotes per period - Quantities report options

To print Quotes per period reports:

1. On the Reports ribbon, select Reports → Sales → Quotes → Sales.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Quotes per period - Quantities report

An example of the "*Quotes per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Quotes - Items (Reports menu)

The Quotes - Items per period report displays the Stock code, Stock description and totals (i.e. Quantities and Selling prices) for each stock item.

This report only includes Quotes which are posted and/or confirmed. Unconfirmed (open) Quotes will be NOT be included in this report.

Quotes - Items per period report options

To print a Quotes - Items per period report:

1. On the Reports ribbon, select Reports → Sales → Quotes → Items.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Quotes - Items per period report

An example of the "*Quotes - Items per period*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Elevate Your Documentation Process with HelpNDoc's Advanced Features

Sales analysis (Reports menu)

Various reports are available on the Reports → Sales analysis menu to analyse sales documents.

Sales documents per period (Reporting groups):

Five (5) reporting groups (i.e. Debtor group 1, Debtor group 2, Document group 1, Document group 2 and Salespersons):



1. Sales per period – This will list both the transaction details of posted invoices and credit notes for a selected period or date(s).

2. Invoices per period – This will list the transaction details of posted invoices only for a selected period

or date(s).

3. Credit notes per period – This will list the transaction details of posted credit notes only for a selected period or date(s).

4. Quotes per period – This will list the transaction details of confirmed (posted) quotes only for a selected period or date(s).

5. Sales per product - Stock group 1 and Stock group 2 are also available to analyse the sales and returns of trading stock items (default stock type).

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Quotes per period (Reports menu)

The following five (5) reports are available to analyse quotes:

1. Quotes per period - Debtor group 1 - List the quotes by debtor (customer / client) reporting group 1 linked to debtor (customer / client) accounts on Debtors (Default ribbon).

2. Quotes per period - Debtor group 2 - List the quotes by debtor (customer / client) reporting group 2 linked to debtor (customer / client) accounts on Debtors (Default ribbon).

3. Quotes per period - Document group 1 - List the quotes by document reporting group 1.

4. Quotes per period - Document group 2 - List the quotes by document reporting group 2.

5. Quotes per period - Salesperson - List the quotes by salesperson (person who processed the quote).

This report only includes Quotes which are posted and/or confirmed. Unconfirmed (open) Quotes will be NOT be included in this report.

Sales analysis - Quotes per period report options

To print Quotes by Reporting groups reports:

1. On the Reports ribbon, select Reports → Sales analysis → Quotes per period.



2. Select the following:

   a) Report - Select the Quotes per period - Debtor group 1 (default), Quotes per period - Debtor group 2, Quotes per period - Document group 1, Quotes per period - Document group 2 or Quotes per period - Salesperson report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.

3. Click on the OK button.

Printed : Sales analysis - Quotes per period - Debtor group 1 report

An example of the "*Quotes per period - Debtor group 1*" report, is as follows:

Page 1 -



Each Reporting group will start on a new page.

Page 2 -



Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Invoices per period (Reports menu)

The following five (5) reports are available to analyse invoices:

1. Invoices per period - Debtor group 1 - List the invoices by debtor (customer / client) reporting group 1 linked to debtor (customer / client) accounts on Debtors (Default ribbon).
2. Invoices per period - Debtor group 2 - List the invoices by debtor (customer / client) reporting group 2 linked to debtor (customer / client) accounts on Debtors (Default ribbon).
3. Invoices per period - Document group 1 - List the invoices by document reporting group 1.
4. Invoices per period - Document group 2 - List the invoices by document reporting group 2.
5. Invoices per period - Salesperson - List the invoices by salesperson (person who processed the invoice).

This report only includes Invoices which are posted. Unposted Invoices will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Sales analysis - Invoices per period report options

To print Invoices by Reporting groups reports:

1. On the Reports ribbon, select Reports → Sales analysis → Invoices per period.



2. Select the following:

   a) Report - Select the Invoices per period - Debtor group 1 (default), Invoices per period - Debtor group 2, Invoices per period - Document group 1, Invoices per period - Document group 2 or Invoices per period - Salesperson report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Sales analysis - Invoices per period - Debtor group 1 report

An example of the "*Invoices per period - Debtor group 1*" report, is as follows:

Page 1 -



Each Reporting group will start on a new page.

Page 2 -



Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Credit notes per period (Reports menu)

The following five (5) reports are available to analyse credit notes:

1. Credit notes per period - Debtor group 1 - List the credit notes by debtor (customer / client) reporting group 1 linked to debtor (customer / client) accounts on Debtors (Default ribbon).
2. Credit notes per period - Debtor group 2 - List the credit notes by debtor (customer / client) reporting group 2 linked to debtor (customer / client) accounts on Debtors (Default ribbon).
3. Credit notes per period - Document group 1 - List the credit notes by document reporting group 1.
4. Credit notes per period - Document group 2 - List the credit notes by document reporting group 2.
5. Credit notes per period - Salesperson - List the credit notes by salesperson (person who processed the credit note).

This report only includes Credit notes which are posted. Unposted Credit notes will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Sales analysis - Credit notes per period report options

To print Credit notes by Reporting groups reports:

1. On the Reports ribbon, select Reports → Sales analysis → Credit notes per period.



2. Select the following:

a) Report - Select the Credit notes per period - Debtor group 1 (default), Credit notes per period - Debtor group 2, Credit notes per period - Document group 1, Credit notes per period - Document group 2 or Credit notes per period - Salesperson report.

b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

c) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Sales analysis - Credit notes per period - Debtor group 1 report

An example of the "*Credit notes per period - Debtor group 1*" report, is as follows:



Each Reporting group will start on a new page.

Page 2 -



If this report contains more than one reporting group, each Reporting group will start on a new page.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Sales per period (Reports menu)

The following five (5) reports are available to analyse posted invoices and credit notes:

1. Sales per period - Debtor group 1 - List the invoices by debtor (customer / client) reporting group 1 linked to debtor (customer / client) accounts on Debtors (Default ribbon).
2. Sales per period - Debtor group 2 - List the invoices by debtor (customer / client) reporting group 2 linked to debtor (customer / client) accounts on Debtors (Default ribbon).
3. Sales per period - Document group 1 - List the invoices by document reporting group 1.
4. Sales per period - Document group 2 - List the invoices by document reporting group 2.
5. Sales per period - Salesperson - List the invoices by salesperson (person who processed the invoice).

This report only includes Invoices and Credit notes which are posted. Unposted Invoices and Credit notes will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Sales analysis - Sales per period report options

To print Sales documents by Reporting groups reports:

1. On the Reports ribbon, select Reports → Sales analysis → Sales per period.



2. Select the following:

   a) Report - Select the Sales per period - Debtor group 1 (default), Sales per period - Debtor group 2, Sales per period - Document group 1, Sales per period - Document group 2 or Sales per period - Salesperson report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Sales analysis - Sales per period - Debtor group 1 report

An example of the "*Sales per period - Debtor group 1*" report, is as follows:

Page 1 -



Sales per period - Debtor group 1

Sales per period - Debtor group 1

Period: 2021/03/01 - 2022/02/28
Sequence: Debtor code
New page per account: No

Group1: Debtor group 1B

D1MDAVI Mr. Mike Davies

Code	Item description	Quantities	Selling price	Cost price	Profit/Loss	P/L %
3COMP	Compressor	3.00	4,500.00	3,000.00	1,500.00	33.33
3DRILL	Drill press	4.00	4,000.00	2,000.00	2,000.00	50.00
4L-INSTCUP	Install - Built-in cupboards	3.00	1,500.00	0.00	1,500.00	100.00
Total:		**10.00**	**10,000.00**	**5,000.00**	**5,000.00**	**50.00**

D1ROGSM Mr. Roger Smith

Code	Item description	Quantities	Selling price	Cost price	Profit/Loss	P/L %
3COMP	Compressor	6.00	9,000.00	6,000.00	3,000.00	33.33
3DRILL	Drill press	6.00	6,000.00	3,000.00	3,000.00	50.00
Credit notes 3DRILL	Drill press	-2.00	-2,000.00	-1,000.00	-1,000.00	-50.00
Total:		**10.00**	**13,000.00**	**8,000.00**	**5,000.00**	**38.46**

Total: Group1: Debtor group 1B	**20.00**	**23,000.00**	**13,000.00**	**10,000.00**	**43.48**

Each Reporting group will start on a new page.

Page 2 -



Sales per period - Debtor group 1

Sales per period - Debtor group 1

Period: 2021/03/01 - 2022/02/28
Sequence: Debtor code
New page per account: No

Group1: Debtor group 1C

D1ABGRE Mr. AB Green

Code	Item description	Quantities	Selling price	Cost price	Profit/Loss	P/L %
3COMP	Compressor	4.00	6,000.00	4,000.00	2,000.00	33.33
3DRILL	Drill press	5.00	5,000.00	2,500.00	2,500.00	50.00
4L-PAINT-E	Paint - Exterior	6.00	3,000.00	0.00	3,000.00	100.00
Credit notes 3COMP	Compressor	-3.00	-4,500.00	-3,000.00	-1,500.00	-33.33
Credit notes 3DRILL	Drill press	-3.00	-3,000.00	-1,500.00	-1,500.00	-50.00
Total:		**9.00**	**6,500.00**	**2,000.00**	**4,500.00**	**69.23**

D1MACDS MAC Shop Decor Specialists

Code	Item description	Quantities	Selling price	Cost price	Profit/Loss	P/L %
4L-INSTCUP	Install - Built-in cupboards	3.00	1,500.00	0.00	1,500.00	100.00
Total:		**3.00**	**1,500.00**	**0.00**	**1,500.00**	**100.00**

Total: Group1: Debtor group 1C	**12.00**	**8,000.00**	**2,000.00**	**6,000.00**	**75.00**
Report total:	**32.00**	**31,000.00**	**15,000.00**	**16,000.00**	**51.61**

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Sales per product (Reports menu)

You may print the following two (2) reports to analyse your invoices and credit notes.

1. Sales per product - Stock group 1
2. Sales per product - Stock group 2

This report only includes Invoices and Credit notes which are posted. Unposted Invoices and Credit notes will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

This report only includes the "Default" stock item type. It does not include any other stock item types (e.g. ten (10) stock item types i.e. Sales, Sales (no stock), Purchases, Purchases (no stock), Financial entry, Option item, Option item (no stock), BOM (Bills of Materials), BOM (Production), Linked Sale).

Sales analysis - Sales per product report options

To print Product by Stock group reports:

1. On the Reports ribbon, select Reports → Sales analysis → Sales per product.



2. Select the following:

   a) Report - Select the Sales per product - Stock group 1 (default) or Sales per product - Stock group 2 report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) From... To... - Select the stock code(s) to include in the report.

   d) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

   e) Sequence - Select "*Stock code* or *Stock description*" to sort the order in which you need to print the data.

   f) Show details - By default, this option is not selected. It will display the total quantities, selling

prices, cost prices, profit / loss and profit loss percentage of each stock item in posted invoices and credit notes. If this option is selected, it will display a list of document numbers, account code and description and the quantities, selling prices and cost prices for each document.

g) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

> *It is recommended that this option is only selected if the Show details option is selected.*

3. Click on the OK button.

Printed : Sales analysis - Sales per product - Stock group 1 report

An example of the "*Sales per product - Stock group 1*" (no details) report, is as follows:



Printed : Sales analysis - Sales per product - Stock group 1 (Show details) report

An example of the "*Sales per product - Stock group 1*" ("*Show details*") report, is as follows:

Page 1 - Compressor invoices



Page 2 - Compressor credit notes



Page 3 - Drill press invoices


Sales per product - Stock group 1

Sales per product - Stock group 1

From stock code: 3COMP To: SALES-NS

Period: 2021/03/01 - 2022/02/28

Sequence: Stock description
Show details: Yes
New page per item: Yes

Power tools

Code - Description	Quantities	Selling price	Cost price	Profit/Loss	P/L %
3DRILL - Drill press	15	15,000.00	7,500.00	7,500.00	100
Document no. / Account	**Quantities**	**Selling price**	**Cost price**		
IN000005 D1MDAVI Mr. Mike Davies	1	1,000.00	500.00		
IN000008 D1ROGSM Mr. Roger Smith	2	2,000.00	500.00		
IN000010 D1MDAVI Mr. Mike Davies	1	1,000.00	500.00		
IN000011 D1ABGRE Mr. AB Green	1	1,000.00	500.00		
IN000014 D1ROGSM Mr. Roger Smith	2	2,000.00	500.00		
IN000015 D1MDAVI Mr. Mike Davies	1	1,000.00	500.00		
IN000017 D1MDAVI Mr. Mike Davies	1	1,000.00	500.00		
IN000018 D1ROGSM Mr. Roger Smith	2	2,000.00	500.00		
IN000020 D1ABGRE Mr. AB Green	2	2,000.00	500.00		
IN000019 D1ABGRE Mr. AB Green	2	2,000.00	500.00		

Page 4 - Drill press credit notes and report totals


Sales per product - Stock group 1

Sales per product - Stock group 1

From stock code: 3COMP To: SALES-NS

Period: 2021/03/01 - 2022/02/28

Sequence: Stock description
Show details: Yes
New page per item: Yes

Power tools

Code - Description	Quantities	Selling price	Cost price	Profit/Loss	P/L %
Credit notes 3DRILL - Drill press	-5	-5,000.00	-2,500.00	-2,500.00	100
Document no. / Account	**Quantities**	**Selling price**	**Cost price**		
CR000002 D1ROGSM Mr. Roger Smith	-2	-2,000.00	500.00		
CR000001 D1ABGRE Mr. AB Green	-2	-2,000.00	500.00		
CR000003 D1ABGRE Mr. AB Green	-1	-1,000.00	500.00		
Total: Power tools	**20**	**25,000.00**	**15,000.00**	**10,000.00**	**67**
Invoice totals:	28	34,500.00	20,500.00	14,000.00	0
Credit note totals:	-8	-9,500.00	-5,500.00	-4,000.00	-67
Report total:	**20**	**25,000.00**	**15,000.00**	**10,000.00**	**67**

Created with the Standard Edition of HelpNDoc: Free Qt Help documentation generator

Purchases (Reports menu)

Various reports are available on the Reports → Purchases menu to analyse each of the sales documents

(i.e. Purchases, Supplier returns and Orders). The reports for Purchases are as follows:



1. Creditors – Creditor – Purchases per period – Quantities

2. Items - Items per period.

3. Purchases – Purchases per period – Quantities.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with a Help Authoring Tool

Purchase - Purchases (Reports menu)

Created with the Standard Edition of HelpNDoc: Qt Help documentation made easy

Purchases - Creditors (Reports menu)

The Creditor - Purchases per period - Quantities report displays the Stock code, Stock description, Quantities and Cost prices (if applicable to stock items) for each creditor (supplier / vendor) account.

This report only includes Purchase documents which are posted. Unposted Purchase documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditors - Purchases per period - Quantities report options

To print a Creditors - Purchases per period - Quantities report :

1. On the Reports ribbon, select Reports → Purchases → Purchase documents → Creditors .



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific

date or a range of dates.

3. Click on the OK button.

Printed : Creditors - Purchases per period - Quantities report

An example of the "*Creditors - Purchases per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with HelpNDoc's easy CHM conversion

Purchases - Items (Reports menu)

The Purchases - Items per period report displays the Stock code, Stock description and totals (i.e. Quantities and Cost prices) for each stock item.

This report only includes Purchase documents which are posted. Unposted Purchase documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Purchases - Items per period report options

To print a Purchases - Items per period report:

1. On the Reports ribbon, select Reports → Purchases → Purchase documents → Items.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Purchases - Items per period report

An example of the "*Purchases - Items per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with a Help Authoring Tool

Purchases - Purchases (Reports menu)

This option allows you to print the posted Purchase documents per period report. It displays the Stock code, Stock description, Quantities, Selling prices and Cost prices (if applicable to stock items).

This report only includes Purchase documents which are posted. Unposted Purchase documents will be NOT be included in this report.

Purchases per period - Quantities report options

To print Purchases per period reports:

1. On the Reports ribbon, select Reports → Purchases → Purchase documents → Purchases.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Purchases per period - Quantities report

An example of the "*Purchases per period - Quantities*", report is as follows:



Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of a Help Authoring Tool

Purchase - Orders (Reports menu)

Created with the Standard Edition of HelpNDoc: Easy Qt Help documentation editor

Orders - Creditors (Reports menu)

The Creditor - Orders per period - Quantities report displays the Stock code, Stock description, Quantities, Cost prices for each creditor (supplier / vendor) account.

This report only includes Orders which are posted and/or confirmed. Unconfirmed (open) Orders will be NOT be included in this report.

Creditor - Orders per period - Quantities report options

To print a Creditor - Orders per period - Quantities report:

1. On the Reports ribbon, select Reports → Purchases → Orders → Creditor.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Creditor - Orders per period - Quantities report

An example of the "*Creditors - Orders per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Orders - Items (Reports menu)

The Orders - Items per period report displays the Stock code, Stock description and totals (i.e. Quantities and Cost prices) for each stock item.

This report only includes Orders which are posted and/or confirmed. Unconfirmed (open) Orders will be NOT be included in this report.

Orders - Items per period report options

To print Orders - Items per period reports:

1. On the Reports ribbon, select Reports → Purchases → Orders → Items.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Orders - Items per period report

An example of the "*Orders - Items per period*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Easily create Help documents

Orders - Purchases (Reports menu)

The Orders per period - Quantities and Orders per period - Cost reports displays the Stock code, Stock description and totals (i.e. Quantities and Cost prices) for each stock item.

This report only includes Orders which are posted and/or confirmed. Unconfirmed (open) Orders will be NOT be included in this report.

Orders per period - Quantities report options

To print Orders per period - Quantities reports:

1. On the Reports ribbon, select Reports → Purchases → Orders → Purchases.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Orders per period - Quantities report

An example of the "*Orders per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Purchase - Supplier returns (Reports menu)

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Supplier returns - Creditors (Reports menu)

The Creditor - Purchases per period - Quantities report displays the Stock code, Stock description, Quantities and Cost prices (if applicable to stock items) for each creditor (supplier / vendor) account.

This report only includes Supplier return documents which are posted. Unposted Supplier return documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditors - Supplier returns per period - Quantities report options

To print Creditors - Supplier returns per period - Quantities reports:

1. On the Reports ribbon, select Reports → Purchases → Supplier returns → Creditors.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Creditors - Supplier returns per period - Quantities report

An example of the "*Creditors - Supplier returns per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Free help authoring environment

Supplier returns - Items (Reports menu)

The Supplier returns - Items per period report displays the Stock code, Stock description and totals (i.e. Quantities and Cost prices) for each stock item.

This report only includes Supplier return documents which are posted. Unposted Supplier returns will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Supplier returns - Items per period report options

To print a Supplier returns - Items per period report :

1. On the Reports ribbon, select Reports → Purchases → Supplier returns → Items.



2. Select the following:

   a) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   b) Sequence - Select "*Stock code, Stock description, Quantities, Cost price* or *Unit cost*" to sort the order in which you need to print the data.

3. Click on the OK button.

Printed : Supplier returns - Items per period report

An example of the "*Supplier returns - Items per period*", is as follows:



Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Supplier returns - Purchases (Reports menu)

This option allows you to print the following two (2) reports:

1. Supplier returns per period - Quantities - displays the Stock code, Stock description, Quantities and Cost prices (if applicable to stock items).

2. Supplier returns per period - Turnover - displays the Stock code, Stock description, Quantities and Cost prices.

This report only includes Supplier returns which are posted. Unposted Supplier returns will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Supplier returns per period - Quantities report options

To print Supplier returns per period - Quantities reports:

1. On the Reports ribbon, select Reports → Purchases → Supplier returns → Purchases .



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. Click on the OK button.

Printed : Supplier returns per period - Quantities report

An example of the "*Supplier returns per period - Quantities*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with HelpNDoc's Clean and Efficient User Interface

Purchase analysis (Reports menu)

Various reports are available on the Reports → Purchase analysis menu to analyse purchase documents.

Purchase documents per period (Reporting groups):

Five (5) reporting groups (i.e. Creditor group 1, Creditor group 2, Document group 1, Document group 2 and Salespersons):



1. Purchases and supplier returns per period – This will list both the transaction details of posted purchases and supplier returns for a selected period or date(s).

2. Purchases per period – This will list the transaction details of posted purchases only for a selected period or date(s).

3. Supplier returns per period – This will list the transaction details of posted supplier returns only for a selected period or date(s).

4. Orders per period – This will list the transaction details of confirmed (posted) orders only for a

selected period or date(s).

5. Purchases per product - Stock group 1 and Stock group 2 are also available to analyse the purchases and supplier returns of trading stock items (default stock type).

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Purchases and Supplier returns per period (Reports menu)

The following five (5) reports are available to analyse posted purchase and supplier return documents:

1. Purchase documents per period - Creditor group 1 - List the purchase and supplier return documents by creditor (supplier / vendor) reporting group 1 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).

2. Purchase documents per period - Creditor group 2 - List the purchase and supplier return documents by creditor (supplier / vendor) reporting group 2 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).

3. Purchase documents per period - Document group 1 - List the purchase and supplier return documents by document reporting group 1.

4. Purchase documents per period - Document group 2 - List the purchase and supplier return documents by document reporting group 2.

5. Purchase documents per period - Salesperson - List the purchase and supplier return documents by salesperson (person who processed the purchase document).

This report only includes purchase and supplier return documents which are posted. Unposted purchase and supplier return documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Purchase documents by Reporting groups options

To print Purchase documents by Reporting groups reports:

1. On the Reports ribbon, select Reports → Purchase analysis → Purchase and Supplier returns per period.



2. Select the following:

   a) Report - Select the Purchase documents per period - Creditor group 1 (default), Purchase documents per period - Creditor group 2, Purchase documents per period - Document group 1, Purchase documents per period - Document group 2 or Purchase documents per period - Salesperson report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each

account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Purchase documents by Reporting groups

An example of the "*Purchase documents per period - Creditor group 1*" report, is as follows:

Page 1 -



Each Reporting group will start on a new page.

Page 2 -



Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Orders per period (Reports menu)

The following five (5) reports are available to analyse orders:

1. Orders per period - Creditor group 1 - List the orders by creditor (supplier / vendor) reporting group 1 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).
2. Orders per period - Creditor group 2 - List the orders by creditor (supplier / vendor) reporting group 2 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).
3. Orders per period - Document group 1 - List the orders by document reporting group 1.
4. Orders per period - Document group 2 - List the orders by document reporting group 2.
5. Orders per period - Salesperson - List the orders by salesperson (person who placed or processed the order).

This report only includes Orders which are posted and/or confirmed. Unconfirmed (open) Orders will be NOT be included in this report.

Purchase analysis - Orders per period report options

To print Orders by Reporting groups reports:

1. On the Reports ribbon, select Reports → Purchase analysis → Orders per period.



2. Select the following:

   a) Report - Select the Orders per period - Creditor group 1 (default), Orders per period - Creditor group 2, Orders per period - Document group 1, Orders per period - Document group 2 or Orders per period - Salesperson report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

   > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Purchase analysis - Orders per period - Creditor group 1 report

An example of the "*Orders per period - Creditor group 1*" report, is as follows:

Page 1 -



Each Reporting group will start on a new page.

Page 2 -



Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Purchases per period (Reports menu)

The following five (5) reports are available to analyse purchase documents:

1. Purchases per period - Creditor group 1 - List the purchase documents by creditor (supplier / vendor) reporting group 1 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).
2. Purchases per period - Creditor group 2 - List the purchase documents by creditor (supplier / vendor) reporting group 2 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).
3. Purchases per period - Document group 1 - List the purchase documents by document reporting group 1.
4. Purchases per period - Document group 2 - List the purchase documents by document reporting group 2.
5. Purchases per period - Salesperson - List the purchase documents by salesperson (person who processed the purchase document).

This report only includes purchase documents which are posted. Unposted purchase documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Purchase analysis - Purchases per period report options

To print Purchases by Reporting groups reports:

1. On the Reports ribbon, select Reports → Purchase analysis → Purchases per period.



2. Select the following:

   a) Report - Select the Purchases per period - Creditor group 1 (default), Purchases per period - Creditor group 2, Purchases per period - Document group 1, Purchases per period - Document group 2 or Purchases per period - Salesperson report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Purchase analysis - Purchases per period - Creditor group 1 report

An example of the "*Purchases per period - Creditor group 1*" report, is as follows:

Page 1 -


Purchases per period - Creditor group 1

Purchases per period - Creditor group 1

Period: 2021/03/01 - 2022/02/28
Sequence: Creditor code
New page per account: No

Group1: Creditor group 1B

C2AONES A-ONE Suppliers

Code	Item description	Quantity	Unit cost	Cost price
3COMP	Compressor	2.00	1,000.00	2,000.00
3DRILL	Drill press	6.00	500.00	3,000.00
Total:		8.00		5,000.00

C2BESTS BEST Suppliers

Code	Item description	Quantity	Unit cost	Cost price
3COMP	Compressor	2.00	1,000.00	2,000.00
Total:		2.00		2,000.00

Total: Group1: Creditor group 1B			7,000.00

Each Reporting group will start on a new page.

Page 2 -


Purchases per period - Creditor group 1

Purchases per period - Creditor group 1

Period: 2021/03/01 - 2022/02/28
Sequence: Creditor code
New page per account: No

Group1: Creditor group 1C

C2ABCOS ABC-Office-Supplies

Code	Item description	Quantity	Unit cost	Cost price
3DRILL	Drill press	3.00	500.00	1,500.00
GL-CODE	General ledger	1.00	0.00	1,500.00
Total:		4.00		3,000.00

C2ABCSC ABC-Service-Centre

Code	Item description	Quantity	Unit cost	Cost price
GL-CODE	General ledger	2.00	0.00	1,000.00
Total:		2.00		1,000.00

Total: Group1: Creditor group 1C			4,000.00
Report total:		16.00	11,000.00

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Supplier returns per period (Reports menu)

The following five (5) reports are available to analyse Supplier return documents:

1. Supplier returns per period - Creditor group 1 - List the Supplier returns by creditor (supplier / vendor) reporting group 1 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).
2. Supplier returns per period - Creditor group 2 - List the Supplier returns by creditor (supplier / vendor) reporting group 2 linked to creditor (supplier / vendor) accounts on Creditors (Default ribbon).
3. Supplier returns per period - Document group 1 - List the Supplier returns by document reporting group 1 linked to the Supplier return.
4. Supplier returns per period - Document group 2 - List the Supplier returns by document reporting group 2 linked to the Supplier return.
5. Supplier returns per period - Salesperson - List the Supplier returns by salesperson (person who processed the Supplier return document).

This report only includes Supplier return documents which are posted. Unposted Supplier return documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Purchase analysis - Supplier returns per period report options

To print Supplier returns by Reporting groups reports:

1. On the Reports ribbon, select Reports → Purchase analysis → Supplier returns per period.



2. Select the following:

   a) Report - Select the Supplier returns per period - Creditor group 1 (default), Supplier returns per period - Creditor group 2, Supplier returns per period - Document group 1, Supplier returns per period - Document group 2 or Supplier returns per period - Salesperson report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

3. Click on the OK button.

Printed : Purchase analysis - Supplier returns per period - Creditor group 1 report

An example of the "*Supplier returns per period - Creditor group 1*" report, is as follows:

Page 1 -


Supplier returns per period - Creditor group 1

Supplier returns per period - Creditor group 1

Period: 2021/03/01 - 2022/02/28
Sequence: Creditor code
New page per account: No

Group1: Creditor group 1B

C2AONES A-ONE Suppliers

Code	Item description	Quantity	Unit cost	Cost price
3DRILL	Drill press	6.00	500.00	3,000.00
Total:		6.00		3,000.00

C2BESTS BEST Suppliers

Code	Item description	Quantity	Unit cost	Cost price
3COMP	Compressor	2.00	1,000.00	2,000.00
Total:		2.00		2,000.00
Total: Group1: Creditor group 1B		8.00		5,000.00

Page 2 -


Supplier returns per period - Creditor group 1

Supplier returns per period - Creditor group 1

Period: 2021/03/01 - 2022/02/28
Sequence: Creditor code
New page per account: No

Group1: Creditor group 1C

C2ABCOS ABC-Office-Supplies

Code	Item description	Quantity	Unit cost	Cost price
3DRILL	Drill press	3.00	500.00	1,500.00
Total:		3.00		1,500.00
Total: Group1: Creditor group 1C		3.00		1,500.00
Report total:		11.00		6,500.00

If this report contains more than one reporting group, each Reporting group will start on a new page.

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Purchases per product (Reports menu)

You may print the following two (2) reports to analyse the purchase and supplier return documents to

analyse your purchases.

1. Purchases per Product - Stock group 1

2. Purchases per Product - Stock group 2

This report only includes Purchase and Supplier return documents which are posted. Unposted Purchase and Supplier return documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

This report only includes the "Default" stock item type. It does not include any other stock item types (e.g. ten (10) stock item types i.e. Sales, Sales (no stock), Purchases, Purchases (no stock), Financial entry, Option item, Option item (no stock), BOM (Bills of Materials), BOM (Production), Linked Sale).

Purchase analysis - Purchases per product - Stock group 1 report options

To print Product by Stock group reports:

1. On the Reports ribbon, select Reports → Purchase analysis → Purchases per product .



2. Select the following:

   a) Report - Select the Purchases per product - Stock group 1 (default) or Purchases per product - Stock group 2 report.

   b) Period - Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

   c) From... To... - Select the stock code(s) to include in the report.

   d) Reporting group 1 - This is optional and by default not selected (not ticked). You may select (tick) the reporting group(s) to include in the report.

   e) Sequence - Select "*Stock code* or *Stock description*" to sort the order in which you need to print the data.

   f) Show details - By default, this option is not selected. It will display the total quantities and cost prices of each stock item in posted purchase and supplier return documents. If this option is selected, it will display a list of document numbers, account code and description and the quantities and cost prices for each document.

   g) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.

It is recommended that this option is only selected if the Show details option is selected.

3. Click on the OK button.

Printed : Purchase analysis - Purchases per product - Stock group 1 report

An example of the "*Purchases per product - Stock group 1*" (no details) report, is as follows:



Purchases per product - Stock group 1

Purchases per product - Stock group 1

From stock code: 3COMP — To: SALES-NS

Period: 2021/03/01 - 2022/02/28

Sequence: Stock description
Show details: No
New page per item: No

Power tools

Code - Description	Quantities	Cost price	Cost price
3COMP - Compressor	4	4,000.00	4,000.00
Supplier returns 3COMP - Compressor	-2	-2,000.00	-2,000.00
3DRILL - Drill press	9	4,500.00	4,680.00
Supplier returns 3DRLL - Drill press	-9	-4,500.00	-4,500.00
Total: Power tools	**2**	**2,000.00**	**2,180.00**
Purchase totals :	13	8,500.00	8,680.00
Supplier return totals :	-11	-6,500.00	-6,500.00
Report total:	**2**	**2,000.00**	**2,180.00**

Printed : Purchase analysis - Purchases per product - Stock group 1 (Show details) report

An example of the "*Purchases per product - Stock group 1*" ("*Show details*") report, is as follows:



Purchases per product - Stock group 1

Purchases per product - Stock group 1

From stock code: 3COMP — To: SALES-NS

Period: 2021/03/01 - 2022/02/28
Sequence: Stock description
Show details: Yes
New page per item: No

Power tools

Code - Description	Quantities	Cost price	Cost price
3COMP - Compressor	4	4,000.00	4,000.00
Document no. / Account	**Quantities**	**Selling price**	**Cost price**
PU000004 C2BESTS BEST Suppliers	2	2,000.00	1,000.00
PU000006 C2AONES A-ONE Suppliers	2	2,000.00	1,000.00
Supplier returns 3COMP - Compressor	-2	-2,000.00	-2,000.00
Document no. / Account	**Quantities**	**Selling price**	**Cost price**
SR000001 C2BESTS BEST Suppliers	-2	-2,000.00	1,000.00
3DRILL - Drill press	9	4,500.00	4,680.00
Document no. / Account	**Quantities**	**Selling price**	**Cost price**
PU000003 C2AONES A-ONE Suppliers	3	1,500.00	500.00
PU000007 C2ABCOS ABC-Office-Supplies	3	1,500.00	520.00
PU000005 C2AONES A-ONE Suppliers	3	1,500.00	500.00
Supplier returns 3DRILL - Drill press	-9	-4,500.00	-4,500.00
Document no. / Account	**Quantities**	**Selling price**	**Cost price**
SR000002 C2AONES A-ONE Suppliers	-3	-1,500.00	500.00
SR000003 C2AONES A-ONE Suppliers	-3	-1,500.00	500.00
SR000004 C2ABCOS ABC-Office-Supplies	-3	-1,500.00	500.00
Total: Power tools	**2**	**2,000.00**	**2,180.00**
Purchase totals :	13	8,500.00	8,680.00
Supplier return totals :	-11	-6,500.00	-6,500.00
Report total:	**2**	**2,000.00**	**2,180.00**

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Calendar (Reports menu)

The "*Calendar - Hours*" report allows you to print the categories of events (i.e. Appointments (General), Debtor appointments (up to six categories), Creditor appointments and Hours) scheduled in the Calendar.

Multi-User calendar (agenda) - Manual - Shop - Licence : Once-off -

This plugin adds the multi-user agenda (multiple agendas) to the Calendar (Planner). You can add agendas and link them as default to the current user. For every agenda a tab will appear in the agenda Calendar so you can see what the appointments, etc. are on other agendas. You can have a agenda for each employee, salesperson, user, etc. and create invoices directly from his / her agenda with a simple click. Each agenda has it's own calendar and task list.

Calendar - Hours report options

To print Calendar - Hours reports:

1. On the Reports ribbon, select Reports → Calendar.



2. Select the period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates.

3. By choosing the desired categories, you can generate a printed report that encompasses the selected events from the calendar. This provides a comprehensive overview of the scheduled activities, appointments, and invoicing details associated with debtors, creditors, and general events. Select the following options:

    a) Agenda - Selecting this option will include general events such as meetings, appointments, and other scheduled activities.

    b) Debtor appointment - By selecting this option, you can include the appointments (all six debtor appointment categories) specifically related to debtor (customer/client) accounts. These appointments are also listed in the Appointment tab of the respective debtor accounts.

    c) Creditor appointment - By selecting this option, allows you to include the appointments associated with creditor (supplier/vendor) accounts. Similarly, these appointments can be found in the Appointment tab of the corresponding creditor accounts.

    d) Hours - This option will list appointments for the "*Hours*" event category. The are scheduled appointments for which quotes are generated and confirmed to invoices. When selecting this

option, appointments scheduled for the "*Hours*" event category will be included in the report. These appointments typically represent scheduled hours for which quotes have been generated.

4. Click on the OK button.

Printed : Calendar - Hours report

An example of the "*Calendar - Hours*" (all events) report, is as follows:



The colours for the events in the following categories:

- Agenda / Appointment (General): This category lists scheduled general appointments, such as meetings with a bank manager or lunches with clients or colleagues.
- Repeating invoices: The repeating or recurring invoices will not be included in this report.
- Hours: This category lists scheduled services rendered on an hourly basis. Once the hours are scheduled, you have the option to generate Quotes based on the scheduled hours. These Quotes can be edited if necessary to ensure accuracy. After finalizing the Quotes, you can convert them into Invoices.
- Debtors appointment: This category lists up to six different categories of appointments with debtors

(customers/clients).

- Creditors appointment: This category lists scheduled appointments with creditors (suppliers/vendors).

Bulk time entries - Bulk time entries added for selected debtors (customers / clients) will be printed on this report as hours.

When you use the Bulk time entry feature to add time entries for a selected debtor account, those entries are initially recorded but not directly listed on the "Debtor accounts - Appointment" tab. However, once you proceed to generate quotes for the hours using the "Create invoices for hours" button on the Calendar, the bulk time entries will be transformed into quotes.

Therefore, to see the bulk time entries reflected on the "Debtor accounts - Appointment" tab, it is necessary to generate quotes for those hours using the "Create invoices for hours" button in osFinancials5/TurboCASH5.

At this point, the quotes created from the bulk time entries will be listed on the "Debtor accounts - Appointment" tab.

See video on Bulk time entries

Repeating invoices events are not included in this report.

Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Company info (reports menu)

The following two (2) reports are available to print information for the Set of Books:

- Company info – Bank accounts - Lists the details of the company bank accounts details as entered in Setup → Company info.

- Company info - Information - Lists the document headings and messages for each document type as well as statement message as specified or entered in Setup → Documents setup. It also lists the Selling price descriptions and Cost of sales settings as entered and set on the Setup → Stock information.

Company info report options

To print Company info reports:

1. On the Reports ribbon, select Reports → Company info.



2. "*Bank accounts*" is the default report. You may select the "*Information*" report.

3. Click OK.

Printed : Company info - Bank accounts report

An example of the "*Bank accounts*" report, is as follows:



The details (Bank name, Bank account number and the Branch code) for Bank account 1 and/or Bank account 2 as entered in Setup → Company info (Setup ribbon).

You may also enter the following, if required:

SWIFT - (Society for Worldwide Interbank Financial Telecommunication) See
http://en.wikipedia.org/wiki/SWIFT / http://www.theswiftcodes.com/

IBAN - (International Bank Account Number) See
http://en.wikipedia.org/wiki/International_Bank_Account_Number

BIC - (Bank Identifier Code)

The information of your bank account 1 will print on Invoices (Invoice Bank details if selected when printing invoices) and on Debtor statements.

The banking details may be added to your specific layout files or custom reports.

Printed : Company info - Information

An example of the "*Information*" report, is as follows:



Lists the details of the following:

- Information - Document heading and messages (up to 3 lines) as entered in the Documents setup

(Setup ribbon) for each of the Sales documents (i.e. Invoices, Credit notes and Quotes tabs) as well as Purchase documents (i.e. Purchases, Supplier returns and Orders tabs). This information is standard and will be printed on all documents.

- Global statement message (up to 3 lines) as entered on the Statement setup tab on Documents setup (Setup ribbon). This information will print standard on all Statements (Reports → Debtors – Outstanding (Reports ribbon)). This is in addition to the specific messages (up to 4 lines) that can be entered in the Delivery address tab individual debtor accounts (Debtors - Default ribbon).
- Selling price descriptions – The descriptions of Selling price 1, Selling price 2 and Selling price 3 as entered in the Selling price descriptions fields (Stock information - Setup ribbon).
- Cost of Sales –
    - Create Cost of Sales - Yes - Cost of Sales is activated.

      - No - Cost of Sales is not activated.
    - Average cost - Yes - Average Cost of Sales is activated.

      - No - Latest Cost of Sales is activated.

Created with the Standard Edition of HelpNDoc: Maximize Your PDF Protection with These Simple Steps

Currencies (Reports menu)

The "*Currencies - Listing*" report will list the currencies (added / edited in the Setup → Currencies menu on the Setup ribbon).

You may process Multi-currency documents (i.e. invoices, credit notes and quotes for debtors (customers / clients) or purchases, supplier returns and orders for creditors (suppliers). The selected currency will be printed in the document layout files.

osFinancials5/TurboCASH5 supports a wide range of currencies, with a total of 180 available currency rates. As these currency rates can fluctuate daily, and sometimes even hourly, users must ensure they regularly update and maintain their currency list before processing any documents. This ensures that accurate exchange rates are used when dealing with foreign currencies on sales documents (invoices, credit notes, and quotes) or purchase documents (purchases, supplier returns, and orders).

Currencies - Listing report options

To print Currencies listing reports:

1. On the Reports ribbon, select Reports → Currencies.



2. Select the Sequence (i.e. ID (record number), Description or Rate).

3. Click on the OK button.

Printed : Currencies - Listing report

An example of the "*Currencies - Listing*" report, is as follows:



Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Plugins (Reports menu)

Reports for the following two (2) plugins are available:

Price agreement plugin - Manual - Shop

With this plugin you can have quantity and discount for up to four (4) levels. These prices will overrule the

default selling price 1 till 3 and can be set per debtor (customer / client) and/or creditor (supplier / vendor).

You can also set a special price for specific debtor (customer / client) and/or creditor (supplier / vendor) per product, which overrule the default product price.

These also a special field available in which you can add the suppliers product number. Also possible for multiple suppliers.

This field can also be used for information text why this debtor (customer / client) and/or creditor (supplier / vendor) has a special price.

This option allows you to print the Price agreements for debtor (customer / client) and creditor (supplier / vendor) accounts.

Serials / location / batch - Manual - Shop

With this plugin, you can track your stock items in locations, bins and serial numbers or codes where the stock items are kept. Some stock items may also have expiry dates, etc.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Spreadsheets

Spreadsheet reports osFinancials5/TurboCASH5 and the power of Spreadsheets

- Spreadsheet sales (Default ribbon)

- Spreadsheet reports (Reports ribbon)

See video on Spreadsheet reports.

Excel Export / Import -

See video on Improved Export/Import -

The Excel Export / Import spreadsheet feature allows to easily export data into spreadsheets, edit the data and import it.

Excel Export / Import is available in the following options:

Setup ribbon:

- *Setup → Accounts*
- *Setup → Groups*
- *Import Accounts, Debtors/Creditors, Stock*

Default ribbon

- *Batch entry (all batches)*
- *Edit → Repeating transactions*
- *Stock (Import / Export tab)*

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's HTML5 template

Spreadsheet reports

Spreadsheet reports osFinancialsTurboCASH and the power of Spreadsheets

- Spreadsheet sales (Default ribbon).

- Spreadsheet reports (Reports ribbon).

See Video on Spreadsheet reports.

Spreadsheet reports - Reports in a Excel spreadsheet. These spreadsheet reports are stored in the ... \plug_ins\reports\excelreports folder.



The following reports will be opened in the powerful spreadsheet feature in osFinancials5/TurboCASH5:

1. Creditors - The Creditors → Listing - List postal addresses report will be imported into the spreadsheet.
2. Debtors - The Debtors → Listing - List postal addresses report will be imported into the spreadsheet.
3. Transactions per period - List the transactions in posted batches and documents (i.e. sales documents (Invoices and Credit notes) and Purchase documents (Purchases and Supplier returns)) for a selected period in a spreadsheet.
4. General ledger - Budget
    a) Column balances this year - Reporting group 1
    b) Column balances this year - This year
5. General ledger (Transaction totals)
    a) Column balances this year - Reporting group 1
    b) Column balances this year - This year Column balances will import the transaction totals in two (2) tabs:
        i) Column balances - The totals for each period in separate columns
        ii) Settings - The totals for each period in rows per period.
6. Sales analysis
    a) Stock movement
    b) Sales per period

F9 to recalculate the spreadsheet

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Spreadsheet - Debtors

The Spreadsheet report - Debtors will list all the debtor (customer / client) accounts in a spreadsheet.

The data in this spreadsheet is the same as the Debtor listing - "*List postal addresses*" report (Reports → Debtors → Listing (Reports ribbon)).

To import the debtor (customer / client) accounts:

On the Reports ribbon, select Spreadsheet reports → Debtors.



Disabled (inactive) debtor (customer / client) accounts will be included in this spreadsheet report.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Spreadsheet - Creditors

The Spreadsheet report - Creditors will list all the creditor (supplier / vendor) accounts in a spreadsheet.

The data in this spreadsheet is the same as the Creditor listing - "*List postal addresses*" report (Reports → Creditors → Listing (Reports ribbon)).

To import the creditor (supplier / vendor) accounts:

On the Reports ribbon, select Spreadsheet reports → Creditors.



Disabled (inactive) creditor (supplier / vendor) accounts will be included in this spreadsheet report.

Created with the Standard Edition of HelpNDoc: Effortlessly Spot and Fix Problems in Your Documentation with HelpNDoc's Project Analyzer

Spreadsheet - Transactions per period

You may import the transactions in batches and documents (i.e. sales documents (Invoices and Credit notes) and Purchase documents (Purchases and Supplier returns)), which have been posted (updated) to the ledger, for a selected period.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

To import posted transactions into a spreadsheet:

1. On the Reports ribbon, select Spreadsheet reports → Transactions → Per period.

2. On the parameters ("*params*")" screen, Select the period or date(s) and click OK. The transactions for the selected period or dates will will be listed in the spreadsheet:



Transaction id	Batch id	Line	Reference	Date	Batch type	Transaction details	ID	Account	Account information	Amount		
326	10028	3	INV003	2022/03/10	Sales jnl.	Paint - Exterior	54	D1ABGRE	Mr. AB Green		1,150.00	150.00
332	10028	9	********	2022/03/10	Sales jnl.	Paint - Exterior	66	T860010	Output VAT - 15%		- 150.00	-
335	10028	12	********	2022/03/12	Sales jnl.	Install - Built-in cupboard	1	G010000	Sales		- 1,500.00	- 1,500.00
327	10028	4	INV004	2022/03/12	Sales jnl.	Install - Built-in cupboard	27	D1MDAVI	Mr. Mike Davies		1,725.00	225.00
334	10028	11	********	2022/03/12	Sales jnl.	Install - Built-in cupboard	66	T860010	Output VAT - 15%		- 225.00	-
349	10039	1	IN000001	2022/03/13	Sales jnl.	Paint - Exterior	1	G010000	Sales		- 1,000.00	- 1,000.00
350	10039	2	IN000001	2022/03/13	Sales jnl.	Invoice /AB-IN110	54	D1ABGRE	Mr. AB Green		1,150.00	150.00
351	10039	3	IN000001	2022/03/13	Sales jnl.	Invoice /AB-IN110	66	T860010	Output VAT - 15%		- 150.00	-
353	10040	2	IN000002	2022/03/14	Sales jnl.	Invoice /IB-101	56	D1MACDS	MAC Shop Decor Specialists		1,725.00	1,725.00
354	10040	3	IN000002	2022/03/14	Sales jnl.	Invoice /IB-101	66	T860010	Output VAT - 15%		- 225.00	1,500.00
352	10040	1	IN000002	2022/03/14	Sales jnl.	Install - Built-in cupboards	1	G010000	Sales		- 1,500.00	-
343	10037	2	PU000001	2022/03/14	Purchase jnl.	Repairs	57	G210030	Repairs		600.00	600.00
344	10037	3	PU000001	2022/03/14	Purchase jnl.	Purchases /AAB234GP	55	C2ABCSC	ABC-Service-Centre		- 1,150.00	- 550.00
345	10037	4	PU000001	2022/03/14	Purchase jnl.	Purchases /AAB234GP	65	T860020	Input VAT - Standard rate -15%		150.00	- 400.00
342	10037	1	PU000001	2022/03/14	Purchase jnl.	Maintenance	7	G210020	Maintenance		400.00	-
355	10041	1	IN000003	2022/03/15	Sales jnl.	Paint - Exterior	1	G010000	Sales		- 1,000.00	- 1,000.00
356	10041	2	IN000003	2022/03/15	Sales jnl.	Invoice /PH-101	54	D1ABGRE	Mr. AB Green		1,150.00	150.00
357	10041	3	IN000003	2022/03/15	Sales jnl.	Invoice /PH-101	66	T860010	Output VAT - 15%		- 150.00	-
346	10038	1	PU000002	2022/03/15	Purchase jnl.	Purchases /IN0014	53	C2ABCOS	ABC-Office-Supplies		- 1,725.00	- 1,725.00
348	10038	3	PU000002	2022/03/15	Purchase jnl.	Purchases /IN0014	65	T860020	Input VAT - Standard rate -15%		225.00	- 1,500.00
347	10038	2	PU000002	2022/03/15	Purchase jnl.	Furniture & fittings @ cost	31	G600010	Furniture & fittings @ cost		1,500.00	-
388	10032	2	D5001	2022/03/16	ABC-Receipts	Payment received - Thank you	54	D1ABGRE	Mr. AB Green		- 2,000.00	- 2,000.00

This spreadsheet will list the transaction details in the following columns:

1. A - Transaction id - The ID of the transaction which was automatically created when the batch or the document was posted (updated) to the ledger.

2. B - Batch id - The ID of the batch which was automatically created when the batch or the document was posted (updated) to the ledger.

3. C - Line - The line number for each transaction in a batch or transaction generated in documents.

4. D - Reference - In the case of batch transactions, the reference as entered for each transaction in the "*Reference*" column in "*Batch entry*" screens will be displayed. Balancing transactions in batches will be displayed with eight (8) asterisks (e.g. "********").

   In the case of documents, the document number for Invoices, Credit notes, Purchases and Supplier returns will be listed.

5. E - Date - The date of the transaction. The date as entered in the "*Date*" column of "*Batch entry*" screens. In the case of documents, it will display the date on which a document was generated.

6. F - Batch type - In the case of batch transactions, the name of the Batch type will be displayed.

No aliases will be displayed as entered on each "*Batch entry*" screen.

In the case of documents, it will display the name of the Batch type as linked to each document type in the Setup → Documents setup screen for each document type.

7. G - Transaction details - The description of the transaction as entered in the "Description" column of batches. In the case of documents, it is the document type description (i.e. Invoice, Credit note, Purchase or Supplier returns) and the reference number (as entered in the "*Your reference*" field of documents.
8. H - ID - The ID of the account applicable to each transaction.
9. I - Account - The Account code or number applicable to each transaction.

Prefixed character in the account code indicates the account type:

G = General ledger

B = Bank account

C= Creditor

D = Debtor

T = Tax

10. J - Account information - The name (description) of the account applicable to the transaction.
11. K - Amount - The amount of the transaction. If Tax (VAT/GST/Sales tax) is applicable to a transaction, three (3) transactions should be listed:
    - Tax inclusive – The full amount of the transaction, including Tax.
    - Tax exclusive – The amount of the transaction, excluding Tax.
    - Tax amount – Only the tax amount applicable to the transaction.
12. L - The cumulative amounts for each transaction. After taking the contra accounts into consideration, the cumulative total for each transaction, should reflect zero.

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Spreadsheet - General ledger - Budget - Column Balances

Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with HelpNDoc's easy CHM conversion

Spreadsheet - General ledger - Budget - Column balances - Reporting group 1

You may import the budget totals (for accounts linked to the Reporting group 1), which have been added or edited on the Budget tab for selected accounts in Setup → Accounts (Setup ribbon) or on the Budgets icon (Reports ribbon), into a spreadsheet.

To import budget totals for reporting group 1 into a spreadsheet:

1. On the Reports ribbon, select Spreadsheet reports → General ledger → Budget → Column balances → Reporting group 1. The budget totals linked to the Reporting group 1 will be listed in the spreadsheet:



	ID	Description	Name	PERIOD0	PERIOD1	PERIOD2	PERIOD3	PERIOD4	PERIOD5	PERIOD6	PERIOD7	PERIOD8	PERIOD9	PERIOD10	PERIOD11	PERIOD12	Total
2	7	Capital	Capital	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3	2	Current assets	Current assets	-	-	-	-	-	-	-	-	-	-	-	-	-	-
4	3	Current liabilities	Current liabilities	-	-	-	-	-	-	-	-	-	-	-	-	-	-
5	5	Expenses	Expenses	-	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	1,600.00	19,200.00
6	6	Fixed assets	Fixed assets	-	-	-	-	-	-	-	-	-	-	-	-	-	-
7	4	Income	Income	-	- 6,000.00	- 6,000.00	- 11,000.0	- 6,000.00	- 6,000.0	- 6,000.0	- 6,000.0	- 6,000.00	- 6,000.00	- 6,000.00	- 6,000.00	- 6,000.00	- 77,000.00
8	11	Longterm liabilities	Longterm liabilities	-	-	-	-	-	-	-	-	-	-	-	-	-	-

This spreadsheet will summarise the total of the budget figures for each Account group 1 (Reporting group 1) in the following columns:

- Period 0 (Opening Last Year) - The totals of the opening budget totals for the previous year.
- Periods 1 to 12 - The totals of budget figures entered in the respective periods for this year.
- Total - Total for each period (Period 1 -12) plus Period 0.

In this example, budget totals for Income and Expense account groups, is included in this Spreadsheet report. The Budget figures were only processed for Income and Expense accounts linked to Income and Expense Reporting group 1, in this documentation.

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Spreadsheet - General ledger - Budget - Column balances - This year

---

You may import the budget totals, which have been added or edited on the Budget tab for selected accounts in Setup → Accounts (Setup ribbon) or on the Budgets icon (Reports ribbon), into a spreadsheet.

Reports for Budgets may also be printed on the Reports → Ledger → Budget menu; or on the Budget listing reports on Ledger analyser 1 or Ledger analyser 2 selecting the "*Budget*" option.

To import a budget for This year into a spreadsheet:

1. On the Reports ribbon, select Spreadsheet reports → General ledger → Budget → Column balances → This year. The budget totals for each of this year periods will be listed in the "*Settings*" sheet of the spreadsheet:



	A	B	C	D
1	Period	From reporting date	To date	Net Profit/Loss
2	1	01-03-2022	31-03-2022	-4400
3	2	01-04-2022	30-04-2022	-4400
4	3	01-05-2022	31-05-2022	-9400
5	4	01-06-2022	30-06-2022	-4400
6	5	01-07-2022	31-07-2022	-4400
7	6	01-08-2022	31-08-2022	-4400
8	7	01-09-2022	30-09-2022	-4400
9	8	01-10-2022	31-10-2022	-4400
10	9	01-11-2022	30-11-2022	-4400
11	10	01-12-2022	31-12-2022	-4400
12	11	01-01-2023	31-01-2023	-4400
13	12	01-02-2023	28-02-2023	-4400

2. To view the budget figures for each account, click on the "*Column balances*" sheet of the spreadsheet:



	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
1	ID	Code	Description	PERIOD0	PERIOD1	PERIOD2	PERIOD3	PERIOD4	PERIOD5	PERIOD6	PERIOD7	PERIOD8	PERIOD9	PERIOD10	PERIOD11	PERIOD12	Total
2	1	010000	Sales	-	- 10,000.00	- 10,000.00	- 15,000.00	- 10,000.00	- 10,000.00	- 10,000.00	- 10,000.00	- 10,000.00	- 10,000.00	- 10,000.00	- 10,000.00	- 10,000.00	- 125,000.00
3	2	100000	Cost of sales	-	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	48,000.00
4	3	200000	Bank charges	-	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	480.00
5	4	205000	Depreciation	-	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	600.00
6	5	210000	Motor vehicle expenses	-	450.00	450.00	450.00	450.00	450.00	450.00	450.00	450.00	450.00	450.00	450.00	450.00	5,400.00
7	6	210010	Fuel and oil	-	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	1,200.00
8	7	210020	Maintenance	-	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	150.00	1,800.00
9	57	210030	Repairs	-	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	2,400.00
10	38	215000	Maintenance of tools	-	-	-	-	-	-	-	-	-	-	-	-	-	-
11	9	220000	Rent	-	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	550.00	6,600.00
12	10	225000	Salaries and wages	-	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	500.00	6,000.00
13	11	230000	Stationery	-	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	10.00	120.00

This spreadsheet lists the totals for the main account as well as sub-accounts. In this example, note the following:

210000 - Motor vehicle - main account = 450.00 - The total of the following sub-accounts:

210010 - Fuel and oil - sub account = 100.00

210020 - Maintenance - sub account = 150.00

210030 - Repairs - sub account = 200.00

The "*Column balances*" sheet of the spreadsheet will summarise the total of the budget figures for each general ledger account in the following columns:

- Period 0 (Opening Last Year) - The totals of the opening budget totals for the previous year.
- Periods 1 to 12 - The totals of budget figures entered in the respective periods for this year.
- Total - Total for each period (Period 1 -12) plus Period 0.

Created with the Standard Edition of HelpNDoc: Effortlessly optimize your documentation website for search engines

Spreadsheet - General ledger- Column balances

Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

Spreadsheet - General ledger - Column balances - Reporting group 1

You may import the transaction totals (for accounts linked to the Reporting group 1), which have been

posted (updated) to the ledger, into a spreadsheet.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

To import posted transactions for reporting group 1 into a spreadsheet:

1. On the Reports ribbon, select Spreadsheet reports → General ledger → Column balances → Reporting group 1. The transaction totals linked to the Reporting group 1 will be listed in the spreadsheet:



	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q
1	ID	Description	Name	PERIOD0	PERIOD1	PERIOD2	PERIOD3	PERIOD4	PERIOD5	PERIOD6	PERIOD7	PERIOD8	PERIOD9	PERIOD10	PERIOD11	PERIOD12	Total
2	7	Capital	Capital	- 12,500.00	- 10,000.00	- 4,025.00	-	-	-	-	-	-	-	-	-	-	- 26,525.00
3	2	Current assets	Current assets	11,593.00	13,774.00	7,625.00	-	-	-	-	-	-	-	-	-	-	32,992.00
4	3	Current liabilities	Current liabilities	- 1,100.00	- 5,519.00	- 4,625.00	-	-	-	-	-	-	-	-	-	-	- 11,244.00
5	5	Expenses	Expenses	-	3,095.00	-	-	-	-	-	-	-	-	-	-	-	3,095.00
6	6	Fixed assets	Fixed assets	5,207.00	3,650.00	-	-	-	-	-	-	-	-	-	-	-	8,857.00
7	4	Income	Income	-	- 10,000.00	- 3,000.00	-	-	-	-	-	-	-	-	-	-	- 13,000.00
8	11	Longterm liabilities	Longterm liabilities	-	-	-	-	-	-	-	-	-	-	-	-	-	-
9																	

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Spreadsheet - General ledger- Column balances - This year

You may import the transaction totals, which have been posted (updated) to the ledger, into a spreadsheet.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

To import posted transactions for This year into a spreadsheet:

1. On the Reports ribbon, select Spreadsheet reports → General ledger → Column balances → This year. The transaction totals for each of this year periods will be listed in the "*Settings*" sheet of the spreadsheet:



2. To view the transaction totals for each account, click on the " *Column balances*" sheet of the spreadsheet:



This spreadsheet lists the totals for the main account as well as sub-accounts. In this example (period for full

year), note the following:

210000 - Motor vehicle - main account = 2,160.00 - The total of the following sub-accounts:

210010 - Fuel and oil - sub account = 150.00

210020 - Maintenance - sub account = 810.00

210030 - Repairs - sub account = 1,200.00

The "*Column balances*" sheet of the spreadsheet will summarise the total of the posted transactions for each general ledger account in the following columns:

- Period 0 (Opening Last Year) - The totals of the opening balance totals for the previous year.
- Periods 1 to 12 - The totals of the posted transactions in the respective periods for this year.
- Total - Total for each period (Period 1 -12) plus Period 0.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Spreadsheet - Sales analysis

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Spreadsheet - Sales analysis - Stock movement

The Spreadsheet report - Stock movement will list the total stock quantities for each stock item in and out for the selected period.

The data in this spreadsheet is similar to the "*Stock In / Out*" report (Reports → Stock items → Stock In / Out - (Reports ribbon)).

The following will be included in the spreadsheet:

- *Only documents (i.e. invoices, credit notes, purchase and supplier return documents) which is posted*

(updated to the ledger) will be included.

- *Only the default stock type (trading stock items (Stock item type = 0)) will be included.*

The following will be excluded from the spreadsheet:

- *All the other ten (10) stock types (e.g. Sales, Sales (no stock), Purchases, Purchases (no stock), Financial entry, Option item, Option item (no stock), BOM, BOM (Production) and Linked item) will be excluded in the spreadsheet import.*

This report only includes document transactions which are posted. Unposted documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

To import Stock movements (Stock In / Out) into a spreadsheet:

1. On the Reports ribbon, select Spreadsheet reports → Sales analysis → Stock movement .
2. On the parameters ("*Params*") screen, select the period and click OK. The total quantities for each stock item will be listed in the spreadsheet:



	A	B	C	D	E
1	ID	Code	Description	Total	Document type
2	4	3COMP	Compressor	3	11
3	4	3COMP	Compressor	4	12
4	4	3COMP	Compressor	9	16
5	4	3COMP	Compressor	-13	10
6	4	3COMP	Compressor	-2	13
7	3	3DRILL	Drill press	5	11
8	3	3DRILL	Drill press	9	12
9	3	3DRILL	Drill press	10	16
10	3	3DRILL	Drill press	-15	10
11	3	3DRILL	Drill press	-9	13
12					

The Document type in column, E is as follows:

10 - Invoice

11 - Credit note

12 - Purchase

13 - Supplier return

14 - Quote

15 - Order

16 - Adjustment

Quotes and Orders will be excluded in the spreadsheet import.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Spreadsheet - Sales analysis - Sales per period

The Spreadsheet report - Stock - Sales per period will list the total sales amount excluding as well as including tax (VAT/GST/ Sales tax) for each of the selected periods.

This report only includes document transactions which are posted. Unposted documents will be NOT be included in this report.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

To import Sales per period into a spreadsheet:

1. On the Reports ribbon, select Spreadsheet reports → Sales analysis → Sales per period.
2. On the parameters ("*Params*") screen, select the period and click OK. The total sales amount, excluding as well as including tax (VAT/GST/ Sales tax), for each period will be listed in the spreadsheet:



Month (Column B)

This is the number of the month in the Calendar year, e.g.:

3 = March

4 = April

5 = May, etc.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

Spreadsheet sales

Spreadsheet reports osFinancials5/TurboCASH5 and the power of Spreadsheets

- Spreadsheet sales (Default ribbon)

- Spreadsheet reports (Reports ribbon)

See Video on Spreadsheet reports.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

User reports (Reports ribbon)

The reports on the User reports menu is included in osFinancials5/TurboCASH5.

Users may add their own reports in the *...\plug_ins\reports\userreports* folder.



The following user reports is included in osFinancials5/TurboCASH5:

1. Custom reports – This is custom sales and purchase reports.

    a) 2cred-sku-det - Lists the Purchase and Supplier return documents for a selected creditor (supplier / vendor).

    b) 2deb-sku-det - Lists the Invoice and Credit note documents for a selected debtor (customer / client).

2. Tax - List the Tax type account codes and the tax rates which is added / edited in Setup → Accounts (Setup ribbon). This report is useful to check your tax percentages after import of ledger accounts or if you customise your in Set of Books.

3. Debtors - Outstanding - "*Due date*" and "*Debtors outstanding at date*" reports. These reports will list all the transactions before and on a selected period (date). It will list the details for each transaction (i.e. Reference No., Date, Due date, Debit, Credit and the accumulative balance for each of the debtor (customer / client) account.

4. Creditors - Outstanding - "*Due date*" and "*Creditors outstanding at date*" reports. These reports will list all the transactions before and on a selected period (date). It will list the details for each transaction (i.e. Reference No., Date, Due date, Debit, Credit and the accumulative balance for each of the creditor (supplier) account.

5. Graphs -

    a) Graphs per week -

        i) Ledger - The "*Graph - Profit / Loss per week*" displays the Net Profit / Loss per week in

a bar chart.

ii) Debtors - The "*Graph - Debtors per week*" displays the debit and credit transaction totals of all debtor (customer / client) accounts per week in a bar chart.

iii) Creditors - The "*Graph - Creditors per week*" displays the debit and credit transaction totals of all creditor (supplier) accounts per week in a bar chart.

iv) Sales -

- Quotes per week - Quantities and Quotes per week - Amount
- Credit notes per week - Quantities and Credit notes per week - Amount
- Invoices per week - Quantities and Invoices per week - Amount
- Sales per week - Invoices minus Credit notes - Quantities and Invoices minus Credit notes - Amount

v) Purchases -

- Orders per week - Quantities and Orders per week – Amount
- Purchases per week – Purchases minus Supplier returns - Quantities and Purchases minus Supplier returns per week - Amount
- Supplier returns per week - Quantities and Supplier returns per week – Amount
- Purchases per week - Quantities and Purchases per week - Amount

b) Graphs per month -

i) Ledger - The "*Graph - Profit / Loss per month*" displays the Net Profit / Loss per week in a bar chart.

ii) Debtors - The "*Graph - Debtors per month*" displays the debit and credit transaction totals of all debtor (customer / client) accounts per week in a bar chart.

iii) Creditors - The "*Graph - Creditors per month*" displays the debit and credit transaction totals of all creditor (supplier) accounts per week in a bar chart.

iv) Sales -

- Quotes per month - Quantities and Quotes per month - Amount
- Credit notes per month - Quantities and Credit notes per month - Amount

- Invoices per month - Quantities and Invoices per month - Amount
- Sales per month - Invoices minus Credit notes - Quantities and Invoices minus Credit notes - Amount

v) Purchases -

- Orders per month - Quantities and Orders per month – Amount
- Purchases per month - Quantities and Purchases per month - Amount
- Supplier returns per month - Quantities and Supplier returns per month – Amount
- Purchases per month – Purchases minus Supplier returns - Quantities and Purchases minus Supplier returns per month - Amount

6. Tutorial reports - These are basic guidelines to create and edit reports with Reportman. This is some basics to create debtor listing and creditor listing reports with the Report designer (Reportman).

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Custom reports

The Custom reports is an example of reports designed in Report designer. The following two (2) reports is available:

- **2cred-sku-det** - **Creditors - Purchases per period - Custom** report will list all posted Purchase documents (Purchases and Supplier returns) as well Orders for a selected Creditor (supplier / vendor) account for a selected period or dates.
- **2deb-sku-det** - **Debtors - Sales per period - Custom** report will list all posted Sales documents (Invoices and Credit notes) as well Quotes for a selected Debtor (customer / client) account for a selected period or dates.

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Purchases per period - Custom report

An example of the "*Creditors - Purchases per period - Custom*" report, is as follows:





2cred-sku-det

Creditors - Purchases per period - Custom

Period:
2021/03/01 - 2022/02/28

C2AONES A-ONE Suppliers

Purchases / Supplier returns

Code	Item description	Document no.	Unit price Cost price	Qty	Total Cost price
3COMP	Compressor	PU000006	1,000.00	2.00	2,000.00
3DRILL	Drill press	SR000002	500.00	-3.00	1,500.00
3DRILL	Drill press	SR000003	500.00	-3.00	1,500.00
3DRILL	Drill press	PU000003	500.00	3.00	1,500.00
3DRILL	Drill press	PU000005	500.00	3.00	1,500.00
Total: C2AONES A-ONE Suppliers				**2.00**	**8,000.00**

Orders

Code	Item description	Document no.	Unit price Cost price	Qty	Total Cost price
3DRILL	Drill press	OR000002	500.00	3.00	1,500.00
3DRILL	Drill press	OR000004	500.00	3.00	1,500.00
Total - Orders: C2AONES A-ONE Suppliers				**6.00**	**3,000.00**

Sales per period - Custom report

An example of the "*Debtors - Sales per period - Custom*" report, is as follows:





Created with the Standard Edition of HelpNDoc: Effortlessly create a professional-quality documentation website with HelpNDoc

Tax (Tax codes - Tax rates)

The Tax report is added to the User reports menu to check the Tax percentages and Tax code status (Active (Enabled) or Inactive (Disabled)).

You may print this report to check your tax rates or tax percentages for Tax (VAT/GST/Sales tax) codes :

- Download a Firebird database type Set of Books (template) on the Downloads screen in the - "*Let osFinancials help you to create a Set of Books?*" option on the Creation wizard. - You may need to change the descriptions, tax rates, etc. in Setup → Accounts.
- Create a new blank database for Firebird or Microsoft SQL Server database types using the "Create a Set of Books (Advanced)?" option on the Creation wizard. Should you import the Accounts (e.g. from an exported Tab Delimited text file exported from another Set of Books), this report may reveal some issues, for example Zero-rated tax (VAT/GST/Sales tax) may be displayed as a blank tax percentage, etc.

Tax codes - Tax rates report options

To print Tax list report:

1. On the Reports ribbon, select User reports → Tax.



2. Select the sequence (order) to list the "*Tax codes*" by Tax code (account code) or "*Description*".
3. Click OK.

Printed : Tax codes - Tax rates report

An example of the "*Tax codes - Tax rates*" report, is as follows:



Should you need to change tax rates and/or Tax accounts/Tax codes go to Setup → Accounts.

After Accounts import

Disabled (Inactive) Accounts

If the status of Accounts were set as Disabled in the source Set of Books from which the Export file was exported, the Disabled accounts will be imported as "*Enabled*". You may need to:

- Delete the "*Disabled*" accounts, if you do not wish to keep these accounts; or
- Keep the Status of these Accounts as "Enabled" (active); or set the Status of these Accounts as "*Disabled*" (inactive).

Tax (VAT/GST/Sales tax) Accounts / Codes

It is important to check the Tax (VAT/GST/Sales tax accounts and Tax percentages, before you process any transactions in batches and/or documents.

Zero -rated Tax (VAT/GST/Sales tax) accounts - Confirm Zero percentage

Zero- rated Tax (VAT/GST/Sales tax) with a Tax percentage of "*0%*" may be blank.

On the Tax codes - Tax rates report (User reports → Tax on the Reports ribbon), Tax percentages with a zero-rate will be Imported as a blank percentage.

This may cause the Zero rated Tax (VAT/GST/Sales tax) selected in processing transactions in Batches and/or Documents not to display correctly on Tax reports.



To fix this; select the Zero-rated Tax (VAT/GST/Sales tax) account.

Overtype the Tax percentage with "*0*"



After confirming Zero-rated "0" tax percentages (tax rates) the Tax rates should be correctly listed as "*0*" percentage.



Recreate Tax (VAT/GST/Sales tax codes with missing Tax tab

The Tax tab on the first Tax code (e.g. Output VAT - 14% (T850010) and Output VAT - 15% (T850010) is missing after Import.



Select the Tax code (e.g. T860010) and Copy the Description (e.g. Output VAT - 15%) to your clipboard.

Click on the Delete icon.

Select the Tax control account (e.g. VAT - Control - Output VAT - 15%) (main account).

Click on the Add icon.



A new Ledger account will be added. Select the following:

- Account type - Select Tax.
- Account number - Change the "*000*" in the Sub-account section with "*010*". You may use the same sub account code as the deleted Tax account.
- Description - Enter the name of your Output tax account (or paste from your clipboard).
- On the Tax tab, enter the Tax percentage (e.g. 15) and click on the Save button.

Created with the Standard Edition of HelpNDoc: Bring your WinHelp HLP help files into the present with HelpNDoc's easy CHM conversion

Debtors

Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Debtors - Outstanding

The Debtors outstanding allows you to print the following reports:

- Due date - This report will list all the transactions before and on a selected period (date). It will list the details for each transaction (i.e. Reference No., Date, Due date, Debit, Credit and the accumulative balance for each of the debtor (customer / client) accounts.
- Debtors Outstanding at date - This report is similar than the Due date report. It will not list the Due date column in the transactions details column.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Debtors - Outstanding - Due date

Due date - This report will list all the transactions before and on a selected period (date). It will list the details for each transaction (i.e. Reference No., Date, Due date, Debit, Credit and the accumulative balance for each of the debtor (customer / client) accounts.

If a debtor (customer / client) account is set as Open item account on the Accounting information tab, it will list only those transactions with outstanding amounts. Any credit amounts, which are not linked to debit transactions, should be processed in the Open item link (Default ribbon).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtors - Due date report options

To print Debtor - Due date reports:

1. On the Reports ribbon, select User reports → Debtors → Outstanding.
2. Select "*Due date*" report.



3. Select the following options:

   a) Report type - Select the Due date or the Debtors Outstanding at date report.

   b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report. All the transactions which are outstanding on or before the end date of the periods will be listed.

   c) From account ...To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

   d) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   e) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details).

   f) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

g) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

3. Click on the OK button.

Printed : Debtors - Due date report

View the "*Debtors - Due date*" report:



Printed : Debtors - Due date (Show contact details) report

View the "*Debtors - Due date*" ("*Show contact details*" option) report:



Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Debtors - Outstanding - Outstanding at date

Debtors outstanding at date - This report is similar than the Due date report. It will not list the Due date column in the transactions details column.

If a debtor (customer / client) account is set as Open item account on the Accounting information tab),it will list only those transactions with outstanding amounts. Any credit amounts, which are not linked to debit transactions, should be processed in the Open item link (Default ribbon).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Debtors outstanding at date report options

To print Debtors outstanding at date reports:

1. On the Reports ribbon, select User reports → Debtors → Outstanding.

2. Select "*Debtors outstanding at date*" report.



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report. All the transactions which are outstanding on or before the end date of the periods will be listed.

   b) From account ...To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

   c) Sequence - Select "*Debtor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details).

e) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

> *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

f) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

3. Click on the OK button.

Printed : Debtors outstanding at date report

View the "*Debtors outstanding at date*" report:



Printed : Debtors outstanding at date (Show contact details) report

View the "*Debtors outstanding at date*" ("*Show contact details*" option) report:



Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Creditors

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Creditors - Outstanding

The Creditors Outstanding allows you to print the following reports:

- Due date - This report will list all the transactions before and on a selected period (date). It will list the details for each transaction (i.e. Reference No., Date, Due date, Debit, Credit and the accumulative balance for each of the creditor (supplier / vendor) accounts.
- Creditors outstanding at date - This report is similar than the Due date report. It will not list the Due date column in the transactions details column.

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Creditors - Outstanding - Due date

Due date - This report will list all the transactions before and on a selected period (date). It will list the details for each transaction (i.e. Reference No., Date, Due date, Debit, Credit and the accumulative balance for each of the creditor (supplier / vendor) accounts.

If a creditor (supplier / vendor) account is set as Open item account (Creditors - Accounting information tab), it will list only those transactions with outstanding amounts. Any credit amounts, which are not linked to debit transactions, should be processed in the Open item link (Default ribbon).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditors - Due date report options

To print Creditor - Due date reports:

1. On the Reports ribbon, select User reports → Creditors → Outstanding.
2. Select "*Due date*" report.



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report. All the transactions which are outstanding on or before the end date of the periods will be listed.

   b) From account ...To account - Select a creditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

   c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details).

   e) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

   > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

   f) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

3. Click on the OK button.

Printed : Creditors - Due date report

View the "*Creditors - Due date*" report:



Printed : Creditors - Due date (Show contact details) report

View the "*Creditors - Due date*" ("*Show contact details*" option) report:



Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Creditors - Outstanding - Outstanding at date

Creditors outstanding at date - This report is similar than the Due date report. It will not list the Due date column in the transactions details column.

If a creditor (supplier / vendor) account is set as Open item account (Creditors - Accounting information tab), it will list only those transactions with outstanding amounts. Any credit amounts, which are not linked to debit transactions, should be processed in the Open item link (Default ribbon).

This report only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this report.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Creditors outstanding at date report options

To print Creditors outstanding at date reports:

1. On the Reports ribbon, select User reports → Creditors → Outstanding.
2. Select "*Creditors outstanding at date*" report.



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report. All the transactions which are outstanding on or before the end date of the periods will be listed.

   b) From account ...To account - Select acreditor (supplier / vendor) account or a range of creditor (supplier / vendor) accounts, to include in the report.

   c) Sequence - Select "*Creditor code*" to print the report by account code or "*Description*" to print the report by account description (name).

   d) Show contact details - If this option is not selected (not ticked), it will list only the transactions. Tick this option to include the details (i.e. postal address, delivery address, and contact details).

   e) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

   > *The Company details will not be printed as in the Page header. The company name is displayed in the Page footer.*

   f) Cost centre 1 / 2 - If you have activated Cost centres, you may select the Cost centres.

3. Click on the OK button.

Printed : Creditors outstanding at date report

View the "*Creditors - Outstanding at date*" report:



Printed : Creditors outstanding at date (Show contact details) report

View the "*Creditors - Outstanding at date*" ("*Show contact details*" option) report:



Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

Graphs

Graphs per week and Graphs per month is available to view the data in a graph on the User reports menu.

Graphs per week:

1. Graphs → Ledger → Profit / Loss per week
2. Graphs → Debtors → Debtors per week
3. Graphs → Creditors → Creditors per week
4. Graphs → Graphs per week → Sales menu:
    a) Sales (Invoices - Credit notes) per week
    b) Invoices per week

c) Credit notes per week

d) Quotes per week

5. Graphs → Graphs per week → Purchases menu:

a) Purchases (Purchases - Supplier returns) per week

b) Purchases per week

c) Supplier returns per week

d) Orders per week

Graphs per month:

1. Graphs → Ledger → Profit / Loss per month
2. Graphs → Debtors → Debtors per month
3. Graphs → Creditors → Creditors per month
4. Graphs → Graphs per month → Sales menu:

e) Sales (Invoices - Credit notes) per month

f) Invoices per month

g) Credit notes per month

h) Quotes per month

5. Graphs → Graphs per month → Purchases menu:

a) Purchases (Purchase - Supplier returns) per month

b) Purchases per month

c) Supplier returns per month

d) Orders per month

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Markdown Content with HelpNDoc

Graphs per week

In addition to the Graph feature for each document type, in Documents on the Default ribbon, you may also print Graphs per week or Graphs per month for posted document types on the User reports menu:

1. Graphs → Graphs per week → Sales menu:

a) Sales (Invoices - Credit notes) per week

b) Invoices per week

c) Credit notes per week

d) Quotes per week

2. Graphs → Graphs per week → Purchases menu:

a) Purchases (Purchases - Supplier returns) per week

b) Purchases per week

c) Supplier returns per week

d) Orders per week

3. Graphs → Graphs per month → Sales menu:

a) Sales (Invoices - Credit notes) per month

b) Invoices per month

c) Credit notes per month

d) Quotes per month

4. Graphs → Graphs per month → Purchases menu:

a) Purchases (Purchase - Supplier returns) per month

b) Purchases per month

c) Supplier returns per month

d) Orders per month

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Graph - Profit / Loss per week

The "*Graph - Profit / Loss per week*" displays the Net Profit and Loss per week in a bar chart.

This graph only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this graph.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input →

Checking unposted items (*Default ribbon*).

Graph - Profit / Loss per week options

To print a Ledger - Graph report:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Ledger.



2. Select the Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Profit / Loss per week

An example of the "*Graph - Profit / Loss per week*", is as follows:



The net profit / loss should balance with the net profit / loss on the trial balance and income statement, if the same periods are selected.

The details are as follows:

1. Vertical Axis - Positive amounts are Income (sales, etc.) and negative amounts are expenses, etc.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Income / Expenses / Net Profit Loss - The figures for the selected period. Net Profit is a positive figure and Net Loss is a negative figure.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

Graph - Debtors per week

The Graph - Debtors per week displays the debit and credit transaction totals of all debtor (customer / client) accounts per week in a bar chart.

This graph only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this graph.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Debtors per week options

To print a Graph - Debtors per week:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Debtors.



2. Select the Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Debtors per week

An example of the "*Graph - Debtors per week*", is as follows:



The Outstanding amount should balance with the Debtor's control account on all reports, if the same periods are selected. Opening balances will be excluded from this graph.

The details are as follows:

1. Vertical Axis -

    a) Positive amounts - Invoices and debit batch transactions (e.g. take on opening balances, adjustments, refunds (payments to debtors), Generate multiple transactions (i.e. Interest on overdue debtor accounts, fixed amounts to all debtors and charge amounts), etc. per week.

    b) Negative amounts - Credit notes, receipts (payments received from debtors) and other credit transactions (e.g. adjustments, bad debts written off, Multiple Transactions (i.e. Balance Debtors with amount less than a specified amount), etc. per week.

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals

    a) Invoices/ Debit Transactions - The total amount value of debit transactions for the entire period.

    b) Receipts/Credit notes/Credit Transactions - The total amount value of credit transactions for the entire period.

c) Outstanding - This is the difference (movement) of the debit and credit transactions. A positive figure indicates that there are more Invoices and debit transactions than credit notes, receipts and credit transactions for the period.

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Graph - Creditors per week

The Graph - Creditors per week displays the debit and credit transaction totals of all creditor (supplier / vendor) accounts per week in a bar chart.

This graph only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this graph.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Creditors per week options

To print a Graph - Creditors per week:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Creditors.



2. Select the Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Creditors per week

An example of the "*Graph - Creditors per week*", is as follows:



The Outstanding amount should balance with the Creditor's control account on all reports, if the same periods are selected. Opening balances will be excluded from this graph.

The details are as follows:

1. Vertical Axis -

    a) Negative amounts - Purchase documents and credit batch transactions (e.g. take on opening balances, adjustments, refunds (payments received from creditors), Generate multiple transactions (i.e. Creditors with charge amount), etc. per week.

    b) Positive amounts - Supplier returns, payments and other debit transactions (e.g. adjustments, etc. per week).

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals

a) Purchases/Credit Transactions - The total amount value of Purchase documents and credit transactions for the entire period.

b) Payments/Supplier returns/Debit Transactions - The total amount value of Supplier return documents and debit transactions for the entire period.

c) Outstanding - This is the difference (movement) of the debit and credit transactions. A negative figure indicates that there are more Purchases and credit transactions than Supplier returns, payments and debit transactions for the period.

Created with the Standard Edition of HelpNDoc: Revolutionize your documentation process with HelpNDoc's online capabilities

Sales - Graphs per week

In addition to the Graph feature for each document type, in Documents on the Default ribbon, you may also print Graphs per week or Graphs per month for posted document types on the User reports menu:

1. Graphs → Graphs per week → Sales menu:
    a) Sales (Invoices - Credit notes) per week
    b) Invoices per week
    c) Credit notes per week
    d) Quotes per week
2. Graphs → Graphs per month → Sales menu:
    a) Sales (Invoices - Credit notes) per month
    b) Invoices per month
    c) Credit notes per month
    d) Quotes per month

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Graph - Sales (Invoices - Credit notes) per week

The Graph feature for each document type (i.e Invoices or Credit notes) in Documents on the Default ribbon, allows you to filter, analyse and view your Invoices or Credit notes in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Invoices or Credit notes document type.*
- *Document status - Select All, Posted or Unposted Invoices or Credit notes.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Invoices for a specific period, may be printed:

- Graph - Invoices - Credit notes per week - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Invoices and Credit notes per week in a bar chart.
- Graph - Invoices - Credit notes per week - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Invoices and Credit notes per week in a bar chart.

This graph only includes Invoices and Credit notes which are posted. Unposted Invoices and Credit notes will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Invoices - Credit notes per week options

To print Graph - Invoices - Credit notes per week reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Sales → Sales per period.



2. Select the following:

    a) Report - Select the Graph - Invoices - Credit notes per week - Quantities or Graph - Invoices - Credit notes per week - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Invoices - Credit notes per week - Quantities

An example of the "*Graph - Invoices - Credit notes per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Invoices and Credit notes per week.

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals - Quantities - The total quantities of all Invoices and Credit notes for the selected period.

Printed : Graph - Invoices - Credit notes per week - Amount

An example of the "*Graph - Invoices - Credit notes per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Invoices and Credit notes per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all posted Invoices minus posted Credit notes for the selected period.

Created with the Standard Edition of HelpNDoc: Easy EPub and documentation editor

Graph - Invoices per week

The Graph feature for each document type (i.e Invoices) in Documents on the Default ribbon, allows you to filter, analyse and view your Invoices in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Invoices document type.*
- *Document status - Select All, Posted or Unposted Invoices.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Invoices for a specific period, may be printed:

- Graph - Invoices per week - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Invoices per week in a bar chart.
- Graph - Invoices per week - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Invoices per week in a bar chart.

This graph only includes Invoices which are posted. Unposted Invoices will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Invoices per week options

To print Graph - Invoices per week reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Sales → Invoices per period.



2. Select the following:

    a) Report - Select the Graph - Invoices per week - Quantities or Graph - Invoices per week - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Invoices per week - Quantities

An example of the "*Graph - Invoices per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Invoices per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Totals - Quantities - The total quantities of all Invoices for the selected period.

Printed : Graph - Invoices per week - Amount

An example of the "*Graph - Invoices per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Invoices per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all posted Invoices for the selected period.

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Graph - Credit notes per week

The Graph feature for each document type (i.e Credit notes) in Documents on the Default ribbon, allows you to filter, analyse and view your Credit notes in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Credit notes document type.*
- *Document status - Select All, Posted or Unposted Credit notes.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Credit notes for a specific period, may be printed:

- Graph - Credit notes per week - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Credit notes per week in a bar chart.
- Graph - Credit notes per week - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Credit notes per week in a bar chart.

This graph only includes Credit notes which are posted. Unposted Credit notes will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Credit notes per week options

To print Graph - Credit notes per week reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Sales → Credit notes per period.



2. Select the following:

    a) Report - Select the Graph - Credit notes per week - Quantities or Graph - Credit notes per week - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Credit notes per week - Quantities

An example of the "*Graph - Credit notes per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Credit notes per week.

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals - Quantities - The total quantities of all Credit notes for the selected period.

Printed : Graph - Credit notes per week - Amount

An example of the "*Graph - Credit notes per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Credit notes per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all posted Credit notes for the selected period.

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

Graph - Quotes per week

The Graph feature for each document type (i.e Quotes) in Documents on the Default ribbon, allows you to filter, analyse and view your Quotes in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Quotes document type.*
- *Document status - Select All, Posted, Unposted (Open), Confirmed Quotes.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse Quotes, which are posted and/or confirmed, for a specific period, may be printed:

- Graph - Quotes per week - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Quotes per week in a bar chart.
- Graph - Quotes per week - Amount - displays the total selling price amount (exclusive of tax (VAT/GST/Sales tax)) of Quotes per week in a bar chart.

This graph only includes Quotes which are posted and/or confirmed. Unconfirmed or open Quotes will be NOT be included in this graph.

Graph - Quotes per week options

To print Graph - Quotes per week reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Sales → Quotes per period.



2. Select the following:

    a) Report - Select the Graph - Quotes per week - Quantities or Graph - Quotes per week - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Quotes per week - Quantities

An example of the "*Graph - Quotes per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Quotes per week.

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals - Quantities - The total quantities of all Quotes for the selected period.

Printed : Graph - Quotes per week - Amount

An example of the "*Graph - Quotes per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Quotes per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Quotes for the selected period.

Created with the Standard Edition of HelpNDoc: Generate Kindle eBooks with ease

Purchases - Graphs per week

In addition to the Graph feature for each document type, in Documents on the Default ribbon, you may also print Graphs per week or Graphs per month for posted document types on the User reports menu:

1. Graphs → Graphs per week → Purchases menu:
    a) Purchases (Purchases - Supplier returns) per week
    b) Purchases per week
    c) Supplier returns per week
    d) Orders per week

2. Graphs → Graphs per month → Purchases menu:

    a) Purchases (Purchase - Supplier returns) per month

    b) Purchases per month

    c) Supplier returns per month

    d) Orders per month

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Graph - Purchases - (Purchases - Supplier returns) per week

The Graph feature for each document type (i.e Purchases or Supplier returns) in Documents on the Default ribbon, allows you to filter, analyse and view your Purchases or Supplier returns in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Purchases or Supplier returns document type.*
- *Document status - Select All, Posted or Unposted Purchases or Supplier returns.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Purchases, which are posted, for a specific period, may be printed:

- Graph - Purchases per week - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Purchase documents (Purchases and Supplier returns) per week in a bar chart.
- Graph - Purchases per week - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Purchase documents (Purchases and Supplier returns) per week in a bar chart.

This graph only includes Purchase documents (Purchases and Supplier returns) which are posted. Unposted Purchase documents (Purchases and Supplier returns) will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Purchases - Supplier returns per week options

To print Graph - Purchases - Supplier returns per week reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Purchases → Purchases .



2. Select the following:

    a) Report - Select the Graph - Purchases - Supplier returns per week - Quantities or Graph - Purchases - Supplier returns per week - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Purchases - Supplier returns per week - Quantities

An example of the "*Graph - Purchases - Supplier returns per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Purchase documents (Purchases and Supplier returns) per week.

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals - Quantities - The total quantities of all Purchase documents (Purchases and Supplier returns) for the selected period.

Printed : Graph - Purchases - Supplier returns per week - Amount

An example of the "*Graph - Purchases - Supplier returns per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Purchase documents (Purchases and Supplier returns) per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Purchase documents (Purchases and Supplier returns) for the selected period.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

Graph - Purchases per week

The Graph feature for each document type (i.e Purchases) in Documents on the Default ribbon, allows you to filter, analyse and view your Purchases in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Purchases document type.*
- *Document status - Select All, Posted or Unposted Purchases.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Purchases, which are posted, for a specific period, may be printed:

- Graph - Purchases per week - Quantities - displays the total quantities of items on the Quantity Shipped field of Purchase documents per week in a bar chart.
- Graph - Purchases per month - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Purchase documents per week in a bar chart.

This graph only includes Purchases which are posted. Unposted Purchases will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Purchases per week options

To print Graph - Purchases per week reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Purchases → Purchases .



2. Select the following:

    a) Report - Select the Graph - Purchases per month - Quantities or Graph - Purchases per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Purchases per week - Quantities

An example of the "*Graph - Purchases per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Purchase documents per week.

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals - Quantities - The total quantities of all Purchase documents for the selected period.

Printed : Graph - Purchases per week - Amount

An example of the "*Graph - Purchases per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Purchase documents per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Purchase documents for the selected period.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Graph - Supplier returns per week

The Graph feature for each document type (i.e Supplier returns) in Documents on the Default ribbon, allows you to filter, analyse and view your Supplier returns in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Supplier returns document type.*
- *Document status - Select All, Posted or Unposted Supplier returns.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Supplier returns, which are posted, for a specific period, may be printed:

- Graph - Supplier returns per week - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Supplier return documents per week in a bar chart.
- Graph - Supplier returns per week - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Supplier return documents per week in a bar chart.

This graph only includes Supplier returns which are posted. Unposted Supplier returns will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Supplier returns per week options

To print Graph - Supplier returns per week reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Purchases → Supplier returns per period.



2. Select the following:

    a) Report - Select the Graph - Supplier returns per week - Quantities or Graph - Supplier returns per week - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Supplier returns per week - Quantities

An example of the "*Graph - Supplier returns per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Supplier return documents per week.

2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).

3. Totals - Quantities - The total quantities of all Supplier return documents for the selected period.

Printed : Graph - Supplier returns per week - Amount

An example of the "*Graph - Supplier returns per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Supplier return documents per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Supplier return documents for the selected period.

Created with the Standard Edition of HelpNDoc: Easily convert your WinHelp HLP help files to CHM with HelpNDoc's step-by-step guide

Graph - Orders per week

The Graph feature for each document type (i.e Orders) in Documents on the Default ribbon, allows you to filter, analyse and view your Orders in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Orders document type.*
- *Document status - Select All, Posted, Unposted (Open), Confirmed Orders.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse Orders, which are posted and/or confirmed, for a specific period, may be printed:

- Graph - Orders per week - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Orders per week in a bar chart.
- Graph - Orders per week - Amount - displays the total cost price amount (exclusive of tax (VAT/GST/Sales tax)) of Orders per week in a bar chart.

This graph only includes Orders which are posted and/or confirmed. Unconfirmed or open Orders will be NOT be included in this graph.

Graph - Orders per week options

To print a Graph - Orders per week:

1. On the Reports ribbon, select User reports → Graphs → Graphs per week → Purchases → Orders per period.



2. Select the following:

    a) Report - Select the Graph - Orders per week - Quantities or Graph - Orders per week - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Orders per week - Quantities

An example of the "*Graph - Orders per week - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Orders per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Totals - Quantities - The total quantities of all Orders for the selected period.

Printed : Graph - Orders per week - Amount

An example of the "*Graph - Orders per week - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Orders per week.
2. Horizontal Axis - This is the Number of the Week in the calendar year (1 to 52).
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Orders for the selected period.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Graphs per month

In addition to the Graph feature for each document type, in Documents on the Default ribbon, you may also print Graphs per week or Graphs per month for posted document types on the User reports menu:

1. Graphs → Graphs per week → Sales menu:
    a) Sales (Invoices - Credit notes) per week
    b) Invoices per week
    c) Credit notes per week
    d) Quotes per week

2. Graphs → Graphs per week → Purchases menu:
    a) Purchases (Purchases - Supplier returns) per week
    b) Purchases per week
    c) Supplier returns per week
    d) Orders per week
3. Graphs → Graphs per month → Sales menu:
    a) Sales (Invoices - Credit notes) per month
    b) Invoices per month
    c) Credit notes per month
    d) Quotes per month
4. Graphs → Graphs per month → Purchases menu:
    a) Purchases (Purchase - Supplier returns) per month
    b) Purchases per month
    c) Supplier returns per month
    d) Orders per month

Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

Graph - Profit / Loss per month

The "*Graph - Profit / Loss per month*" displays the Net Profit and Loss per month in a bar chart.

This graph only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this graph.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Profit / Loss per month options

To print a Graph - Profit / Loss per month report:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Ledger .



2. Select the Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Profit / Loss per month

An example of the "*Graph - Profit / Loss per month*", is as follows:



The net profit / loss should balance with the net profit / loss on the trial balance and income statement, if the same periods are selected.+

The details are as follows:

1. Vertical Axis - Positive amounts are Income (sales, etc.) and negative amounts are expenses, etc.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Income / Expenses / Net Profit Loss - The figures for the selected period. Net Profit is a positive figure and Net Loss is a negative figure.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Graph - Debtors per month

The Graph - Debtors per week displays the debit and credit transaction totals of all debtor (customer / client) accounts per month in a bar chart.

This graph only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this graph.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Debtors per month options

To print a Graph - Debtors per month report:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Debtors .



2. Select the Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Debtors per month

An example of the "*Graph - Debtors per month*", is as follows:



The Outstanding amount should balance with the Debtor's control account on all reports, if the same periods are selected. Opening balances will be excluded from this graph.

The details are as follows:

1. Vertical Axis -

    a) Positive amounts - Invoices and debit batch transactions (e.g. take on opening balances, adjustments, refunds (payments to debtors), Generate multiple transactions (i.e. Interest on overdue debtor accounts, fixed amounts to all debtors and charge amounts), etc. per month.

    b) Negative amounts - Credit notes, receipts (payments received from debtors) and other credit transactions (e.g. adjustments, bad debts written off, Multiple Transactions (i.e. Balance Debtors with amount less than a specified amount), etc. per month.

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Totals

    a) Invoices/ Debit Transactions - The total amount value of debit transactions for the entire period.

    b) Receipts/Credit notes/Credit Transactions - The total amount value of credit transactions for the entire period.

c) Outstanding - This is the difference (movement) of the debit and credit transactions. A positive figure indicates that there are more Invoices and debit transactions than credit notes, receipts and credit transactions for the period.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Graph - Creditors per month

The Graph - Creditors per month displays the debit and credit transaction totals of all creditor (supplier / vendor) accounts per month in a bar chart.

This graph only includes batch and document transactions which are posted. Unposted batches and documents will be NOT be included in this graph.

To view a list of unposted batches and documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Creditors per month options

To print a Graph - Creditors per month:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Creditors.



2. Select the Period - Select a period on the Per period tab. You may click on the Free selection tab to

select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Creditors per month

An example of the "*Graph - Creditors per month*", is as follows:



The Outstanding amount should balance with the Creditor's control account on all reports, if the same periods are selected. Opening balances will be excluded from this graph.

The details are as follows:

1. Vertical Axis -

    a) Negative amounts - Purchase documents and credit batch transactions (e.g. take on opening balances, adjustments, refunds (payments received from creditors), Generate multiple transactions (i.e. Creditors with charge amount), etc. per month.

    b) Positive amounts - Supplier returns, payments and other debit transactions (e.g. adjustments, etc. per month).

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Totals

    a) Purchases/Credit Transactions - The total amount value of Purchase documents and credit transactions for the entire period.

    b) Payments/Supplier returns/Debit Transactions - The total amount value of Supplier return documents and debit transactions for the entire period.

    c) Outstanding - This is the difference (movement) of the debit and credit transactions. A negative figure indicates that there are more Purchases and credit transactions than Supplier returns, payments and debit transactions for the period.

Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with a Help Authoring Tool

Sales - Graphs per month

In addition to the Graph feature for each document type, in Documents on the Default ribbon, you may also print Graphs per week or Graphs per month for posted document types on the User reports menu:

1. Graphs → Graphs per week → Sales menu:

    a) Sales (Invoices - Credit notes) per week

    b) Invoices per week

    c) Credit notes per week

    d) Quotes per week

2. Graphs → Graphs per month → Sales menu:

    a) Sales (Invoices - Credit notes) per month

    b) Invoices per month

    c) Credit notes per month

    d) Quotes per month

Created with the Standard Edition of HelpNDoc: Elevate Your Documentation Process with HelpNDoc's Advanced Features

Graph - Sales (Invoices - Credit notes) per month

The Graph feature for each document type (i.e Invoices or Credit notes) in Documents on the Default ribbon, allows you to filter, analyse and view your Invoices or Credit notes in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Invoices or Credit notes document type.*
- *Document status - Select All, Posted or Unposted Invoices or Credit notes.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Invoices for a specific period, may be printed:

- Graph - Invoices - Credit notes per month - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Invoices and Credit notes per month in a bar chart.
- Graph - Invoices - Credit notes per month - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Invoices and Credit notes per month in a bar chart.

This graph only includes Invoices and Credit notes which are posted. Unposted Invoices and Credit notes will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Invoices - Credit notes per month options

To print Graph - Invoices - Credit notes per month reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Sales → Sales per period.



2. Select the following:

    a) Report - Select the Graph - Invoices - Credit notes per month - Quantities or Graph - Invoices - Credit notes per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Invoices - Credit notes per month - Quantities

An example of the "*Graph - Invoices - Credit notes per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Invoices and Credit notes per month.

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Totals - Quantities - The total quantities of all Invoices minus Credit notes for the selected period.

Printed : Graph - Invoices - Credit notes per month - Amount

An example of the "*Graph - Invoices - Credit notes per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Invoices and Credit notes per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all posted Invoices minus posted Credit notes for the selected period.

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Graph - Invoices per month

The Graph feature for each document type (i.e Invoices) in Documents on the Default ribbon, allows you to filter, analyse and view your Invoices in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Invoices document type.*
- *Document status - Select All, Posted or Unposted Invoices.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Invoices for a specific period, may be printed:

- Graph - Invoices per month - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Invoices per month in a bar chart.
- Graph - Invoices per month - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Invoices per month in a bar chart.

This graph only includes Invoices which are posted. Unposted Invoices will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Invoices per month options

To print Graph - Invoices per month reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Sales → Invoices per period.



2. Select the following:

    a) Report - Select the Graph - Invoices per month - Quantities or Graph - Invoices per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Invoices per month - Quantities

An example of the "*Graph - Invoices per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Invoices per month.

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Totals - Quantities - The total quantities of items on all posted Invoices for the selected period.

Printed : Graph - Invoices per month - Amount

An example of the "*Graph - Invoices per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Invoices per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all posted Invoices for the selected period.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Graph - Credit notes per month

The Graph feature for each document type (i.e Credit notes) in Documents on the Default ribbon, allows you to filter, analyse and view your Credit notes in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Credit notes document type.*
- *Document status - Select All, Posted or Unposted Credit notes.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Credit notes for a specific period, may be printed:

- Graph - Credit notes per month - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Credit notes per month in a bar chart.
- Graph - Credit notes per month - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Credit notes per month in a bar chart.

This graph only includes Credit notes which are posted. Unposted Credit notes will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Credit notes per month options

To print Graph - Credit notes per month reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Sales → Credit notes per period.



2. Select the following:

    a) Report - Select the Graph - Credit notes per month - Quantities or Graph - Credit notes per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Credit notes per month - Quantities

An example of the "*Graph - Credit notes per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Credit notes per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Totals - Quantities - The total quantities of all Credit notes for the selected period.

Printed : Graph - Credit notes per month - Amount

An example of the "*Graph - Credit notes per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Credit notes per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Credit notes for the selected period.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Graph - Quotes per month

The Graph feature for each document type (i.e Quotes) in Documents on the Default ribbon, allows you to filter, analyse and view your Quotes in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Quotes document type.*
- *Document status - Select All, Posted, Unposted (Open), Confirmed Quotes.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse Quotes, which are posted and/or confirmed, for a specific period, may be printed:

- Graph - Quotes per month - Quantities - displays the total quantities of items on the "*Quantity shipped*" field of Quotes per month in a bar chart.
- Graph - Quotes per month - Turnover - displays the total selling price amount (exclusive of tax (VAT/GST/Sales tax)) of Quotes per month in a bar chart.

This graph only includes Quotes which are posted and/or confirmed. Unconfirmed or open Quotes will be NOT be included in this graph.

Graph - Quotes per month options

To print Graph - Quotes per month reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Sales → Quotes per period.



2. Select the following:

    a) Report - Select the Graph - Quotes per month - Quantities or Graph - Quotes per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Quotes per month - Quantities

An example of the "*Graph - Quotes per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Quotes per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Totals - Quantities - The total quantities of all Quotes for the selected period.

Printed : Graph - Quotes per month - Amount

An example of the "*Graph - Quotes per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Quotes per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Quotes for the selected period.

Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Purchases - Graphs per month

In addition to the Graph feature for each document type, in Documents on the Default ribbon, you may also print Graphs per week or Graphs per month for posted document types on the User reports menu:

1. Graphs → Graphs per week → Purchases menu:
    a) Purchases (Purchases - Supplier returns) per week
    b) Purchases per week
    c) Supplier returns per week
    d) Orders per week

2. Graphs → Graphs per month → Purchases menu:

    a) Purchases (Purchase - Supplier returns) per month

    b) Purchases per month

    c) Supplier returns per month

    d) Orders per month

Created with the Standard Edition of HelpNDoc: iPhone web sites made easy

Graph - Purchases - (Purchases - Supplier returns) per month

The Graph feature for each document type (i.e Purchases or Supplier returns) in Documents on the Default ribbon, allows you to filter, analyse and view your Purchases or Supplier returns in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Purchases or Supplier returns document type.*
- *Document status - Select All, Posted or Unposted Purchases or Supplier returns.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Purchases, which are posted, for a specific period, may be printed:

- Graph - Purchases - Supplier returns per month - Quantities - displays the total quantities of items on the Quantity Shipped field of Purchase documents (Purchases and Supplier returns) per month in a bar chart.
- Graph - Purchases - Supplier returns per month - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Purchase documents (Purchases and Supplier returns) per month in a bar chart.

This graph only includes Purchase documents which are posted. Unposted Purchase documents (Purchases and Supplier returns) will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Purchases - Supplier returns per month options

To print Graph - Purchases - Supplier returns per month reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Purchases → Purchases.



2. Select the following:

    a) Report - Select the Graph - Purchases - Supplier returns per month - Quantities or Graph - Purchases - Supplier returns per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Purchases - Supplier returns per month - Quantities

An example of the "*Graph - Purchases - Supplier returns per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Purchase documents (Purchases and Supplier returns) per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Totals - Quantities - The total quantities of all Purchase documents (Purchases and Supplier returns) for the selected period.

Printed : Graph - Purchases - Supplier returns per month - Amount

An example of the "*Graph - Purchases - Supplier returns per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Purchase documents (Purchases and Supplier returns) per month.

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Purchase documents (Purchases and Supplier returns) for the selected period.

Created with the Standard Edition of HelpNDoc: Easy EBook and documentation generator

Graph - Purchases per month

The Graph feature for each document type (i.e Purchases) in Documents on the Default ribbon, allows you to filter, analyse and view your Purchases in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Purchases document type.*
- *Document status - Select All, Posted or Unposted Purchases.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Purchases, which are posted, for a specific period, may be printed:

- Graph - Purchases per month - Quantities - displays the total quantities of items on the Quantity Shipped field of Purchase documents per month in a bar chart.
- Graph - Purchases per month - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Purchase documents per month in a bar chart.

This graph only includes Purchase documents which are posted. Unposted Purchase documents will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Purchases per month options

To print Graph - Purchases per month reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Purchases → Purchases per period.



2. Select the following:

    a) Report - Select the Graph - Purchases per month - Quantities or Graph - Purchases per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Purchases per month - Quantities

An example of the "*Graph - Purchases per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Purchase documents per month.

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Totals - Quantities - The total quantities of all Purchase documents for the selected period.

Printed : Graph - Purchases per month - Amount

An example of the "*Graph - Purchases per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Purchase documents per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Purchase documents for the selected period.

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Graph - Supplier returns per month

The Graph feature for each document type (i.e Supplier returns) in Documents on the Default ribbon, allows you to filter, analyse and view your Supplier returns in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Supplier returns document type.*
- *Document status - Select All, Posted or Unposted Supplier returns.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse your Supplier returns, which are posted, for a specific period, may be printed:

- Graph - Supplier returns per month - Quantities - displays the total quantities of items on the Quantity Shipped field of Supplier return documents per month in a bar chart.
- Graph - Supplier returns per month - Amount - displays the total amount (exclusive of tax (VAT/GST/Sales tax)) of Supplier return documents per month in a bar chart.

This graph only includes Supplier return documents which are posted. Unposted Supplier return documents will be NOT be included in this graph.

To view a list of unposted documents, which is not updated to the ledger, go to Input → Checking unposted items (Default ribbon).

Graph - Supplier returns per month options

To print Graph - Supplier returns per month reports:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Purchases → Supplier returns per period.



2. Select the following:

    a) Report - Select the Graph - Supplier returns per month - Quantities or Graph - Supplier returns per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Supplier returns per month - Quantities

An example of the "*Graph - Supplier returns per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Supplier return documents per month.

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Totals - Quantities - The total quantities of all Supplier return documents for the selected period.

Printed : Graph - Supplier returns per month - Amount

An example of the "*Graph - Supplier returns per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Supplier return documents per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Supplier return documents for the selected period.

Created with the Standard Edition of HelpNDoc: Experience the Power and Simplicity of HelpNDoc's User Interface

Graph - Orders per month

The Graph feature for each document type (i.e Orders) in Documents on the Default ribbon, allows you to filter, analyse and view your Orders in a graph using various options to include or exclude in the graph, i.e.:

- *Document types - Select the Orders document type.*
- *Document status - Select All, Posted, Unposted (Open), Confirmed Orders.*
- *Filter options - Select the various options to include or exclude data to be included in the graph, etc.*

The following two (2) graph reports to analyse Orders, which are posted and/or confirmed, for a specific period, may be printed:

- Graph - Orders per month - Quantities - displays the total quantities of items on the Quantity Shipped field of Orders per month in a bar chart.
- Graph - Orders per month - Amount - displays the total cost price amount (exclusive of tax (VAT/GST/Sales tax)) of Orders per month in a bar chart.

This graph only includes Orders which are posted and/or confirmed. Unconfirmed or open Orders will be NOT be included in this graph.

Graph - Orders per month options

To print a Graph - Orders per month:

1. On the Reports ribbon, select User reports → Graphs → Graphs per month → Purchases → Orders per period.



2. Select the following:

    a) Report - Select the Graph - Orders per month - Quantities or Graph - Orders per month - Amount report.

    b) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include in the graph.

3. Click on the OK button.

Printed : Graph - Orders per month - Quantities

An example of the "*Graph - Orders per month - Quantities*", is as follows:



The details is as follows:

1. Vertical Axis - The total quantities on Orders per month.

2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.

3. Totals - Quantities - The total quantities of all Orders for the selected period.

Printed : Graph - Orders per month - Amount

An example of the "*Graph - Orders per month - Amount*", is as follows:



The details is as follows:

1. Vertical Axis - The total amount for Orders per month.
2. Horizontal Axis - This is the Year and Month ("*YYYYMM*" format) in the calendar year.
3. Exclusive total - The total amount (exclusive of tax (VAT/GST/Sales tax)) of all Orders for the selected period.

Created with the Standard Edition of HelpNDoc: Free help authoring tool

Report designer (Reportman)

The Report designer in osFinancials5/TurboCASH5 provides a powerful tool for creating and customising reports according to your specific needs. It is integrated and customised within osFinancials5, utilising the Reportman reporting engine. The Report designer offers a wide range of components, functions, and features to design and modify reports and document layout files. You can add your own reports in the User Reports menu and print these reports.

Report designer report types

All reports and document layout files included in your osFinancials5/TurboCASH5 installation are created

using the Report manager designer. These reports and layout files are built on the Firebird database type and should also support other database types such as MSSQL.

The reports and document layout files are organized in a file structure in various folders within the following directory of your osFinancials5/TurboCASH5 installation:

```
"... \plug_ins\reports"
```

Here are the commonly used report categories:

1. Document layout files: The document layout files in osFinancials5/TurboCASH5 are stored in the following folder.

   ```
   "...\plug_ins\reports\DOCUMENTS\DOCUMENTS"
   ```

   Among the shipped document layout files are the "*Layout file, Document layout, Document layout (15-code)*" and "*Delivery note*" layout files. These layout files can be translated using language files.

   The "*Layout file, Document layout, Document layout (15-code)*" files are designed to support various types of sales documents and purchase documents, such as invoices, credit notes, quotes, delivery notes, purchases, supplier returns, and orders. When you open your Set of Books, the layout files will be printed in the language associated with that Set of Books. If you choose to change the language in osFinancials5/TurboCASH5, the layout files will be printed in the selected language.

   Furthermore, you have the flexibility to select from different layout files for printing or reprinting your sales documents and purchase documents. You can even create copies of existing layout files and customize their appearance and format to align with your business branding or meet specific requirements. This allows you to tailor the document layout files according to your preferences and ensure they reflect your desired visual style.

2. Reports menu: The Reports menu in osFinancials5 provides access to a comprehensive range of standard reports that are essential for managing various aspects of your business. These reports cover areas such as the ledger, debtors, creditors, stock items, documents, sales, sales analysis, purchases, purchase analysis, and more.

   All of these standard reports are stored in the following folder:

   ```
   " ...\plug_ins\reports\systemreports"
   ```

   The reports are organized into folders and subfolders within this directory to facilitate easy navigation and retrieval.

   To access these reports, you can simply go to the Reports menu on the Reports ribbon. From there, you can explore the different menu options and sub-menu options to locate the specific report you need. The Reports menu provides a convenient and centralised hub for accessing the wide range of

reports available in osFinancials5/TurboCASH5, making it easier for you to generate the necessary financial and operational insights for your business.

3. User reports menu: The User reports menu in osFinancials5 provides a dedicated space for storing and accessing custom reports that you create or customize according to your specific needs. These User reports are stored in the following folder:

   "...\plug_ins\reports\userreports" ,

   The User reports is separate from the standard reports folder.

   To add your own custom reports, you should place them in the "*userreports*" folder. This folder serves as a repository for your personalised reports, allowing you to organize and manage them effectively.

   Once your custom reports are added to the "*userreports*" folder, you can access them from the User reports menu on the Reports ribbon. This menu provides a convenient structure for accessing and printing your custom reports.

   The User reports menu includes a range of pre-defined reports such, as Graphs per week or month for Custom reports, Debtors, Creditors, Tax listing, etc. Additionally, there are basic sample reports like Debtor listing and Creditor listing, which serve as tutorials to guide you in creating new reports using the Report designer in the osFinancials5/TurboCASH5 environment. These sample reports demonstrate various features, including parameters, lookups, and more.

   The User reports menu empowers you to tailor your reporting capabilities to suit your unique business requirements, allowing you to create, access, and print custom reports seamlessly within the osFinancials5/TurboCASH5 system.

4. Ledger analyser: On the Reports ribbon in osFinancials5/TurboCASH5, you will find the Ledger analyser options, namely Ledger analyser 1, Ledger analyser 2, and T-Account viewer. These options provide a range of report types for generating and printing various financial statements and analyses.

   The available reports include the Trial balance, Income statement, Balance sheet, Standard column balances, This year vs last year, Budget vs actual, Budget listing and the transactions in the T-Account viewer. These reports offer valuable insights into your financial data and help you analyse the performance and financial position of your business.

   The reports within the Ledger analyser options are stored in the following folder:

   "...\plug_ins\reports\GENERAL\ledgerview"

   It's important to note that these reports are preset and should not be customised. They are designed to provide standard financial analyses and should be used as intended.

Additionally, the reports generated through the Ledger analyser options can be exported and opened in spreadsheet applications, allowing for further analysis and customisation of the data.

By utilising the Ledger analyser options, you can easily generate and access a variety of essential financial reports and analyses within osFinancials5/TurboCASH5, providing valuable insights into your company's financial performance.

5. Spreadsheet reports menu: The Spreadsheet reports menu on the Reports ribbon in osFinancials5/TurboCASH5 provides access to reports that open in the integrated spreadsheet component. These reports are stored and organized in the following folder:

   "...\plug_ins\reports\excelreports" .

   Each report consists of a base.xlsx file, SQL files, and possibly parameter files. It's important to note that these spreadsheet reports cannot be edited using the Report designer tool. The available shipped spreadsheet reports include Creditors listing, Debtors listing, Transactions per period, General ledger - Budget, General ledger (Transaction totals), Sales analysis, and Stock movement.

The Report designer utilises different tables in osFinancials5/TurboCASH5 to generate reports. The document outlines the commonly used tables and their relationships to help you build reports effectively.

Overall, the Report designer in osFinancials5/TurboCASH5 provides a flexible and comprehensive solution for creating, customising, and managing reports to meet your specific reporting requirements.

Report Designer Help

To customize or create your own document layout files and reports using the Report designer within the Setup ribbon, you can follow these steps:

1. Refer to Documentation: To get started, you can refer to the "*Report designer*" section within the osFinancials5/TurboCASH5 help file. Additionally, you can access online documentation related to the Report designer on the osFinancials5/TurboCASH5 website.

2. Utilize Offline Documentation: Apart from the topics covered in this documentation, there is a comprehensive offline set of resources available in the "*.../plug_ins/reportman/doc*" folder of your osFinancials5 installation directory. You can access this offline documentation by opening the "*index.html*" file located at "*.../plug_ins/reportman/doc/index.html*" in your web browser.

3. Visit Online Resources: For further insights, the official online documentation for the "*Report Manager*" can be found at https://reportman.sourceforge.io/. This online documentation offers additional resources and information specifically about the Report Manager, providing valuable guidance as you work on your customization and design endeavours.

By following these steps and utilizing the available resources, you can effectively navigate the Report

designer in osFinancials5/TurboCASH5 and create customized document layout files and reports to meet your specific requirements.

Connections

The connections, interactions, and relationships between datasets and database connections have been enhanced in osFinancials5/TurboCASH5 to integrate seamlessly with Reportman. The Zeos Database Objects connection is used, which ensures smooth communication with the database and confirms successful connection.

Overall, the Report designer in osFinancials5/TurboCASH5 provides a flexible and comprehensive solution for creating, customizing, and managing reports to meet your specific reporting requirements.



If you encounter connection issues and are unable to establish a successful connection in osFinancials5/TurboCASH5, it could indicate that certain aspects require attention. Here are some potential factors to consider:

1. Installation of osFinancials5: It's possible that the Firebird database engine was not installed during the osFinancials5/TurboCASH5 installation process. Make sure you have installed the necessary

components, including the database engine, and ensure they are properly configured.

After installing osFinancials5, you will find optional additional components included in the "installs" folder within the root installation directory. These components include:

- *Firebird Version 2.1: This is an optional component primarily intended for advanced users. Installing Firebird Version 2.1 allows for further functionality and customization within osFinancials5/TurboCASH5.*

  It's important to note that later releases of Firebird, such as Versions 3 and 4, are currently not supported in osFinancials5/TurboCASH5 databases (Sets of Books).

- *FlameRobin Version 0.9.3: FlameRobin is a Database Admin software that provides tools to manage and explore your osFinancials5 databases (Sets of Books). To utilize FlameRobin, you will need to install Firebird Version 2.1 as well. FlameRobin offers additional functionalities for database management and administration purposes.*

2. Reportman (.rep) files: If there are multiple aliases or poorly designed reports or document layout files in the reportman (.rep) files, it may lead to connection problems. Review and adjust the aliases and ensure the reports and document layout files are correctly structured.
3. Corrupted data: Corruption within the database can also cause connection issues. Check for any signs of data corruption and take appropriate measures to address it, such as restoring from a backup.
4. Data compatibility: The data within the database, including date formats, currencies, and time, is influenced by the system's locale or regional and language settings. Ensure that the database settings align with the desired system locale to avoid conflicts and compatibility issues.

By addressing these potential issues, you can troubleshoot and resolve connection problems in osFinancials5/TurboCASH5 effectively.

If osFinancials5 have been installed on a Windows machine, the Language and Regional settings may be changed if you click on the Set the Windows date/format/style button located in Setup → Company info - Options or on the DateTime settings button located on the Setup → System parameters (Setup ribbon). In Windows operating you may change this in the Control Panel (Regional and Language settings). This will for example display the correct date format as per your countries' regional settings on all reports output and screens in osFinancials5/TurboCASH5.

See - Settings for reports - Number-format.

To develop or edit reports in osFinancials5, you need to use the built in Reportman in osFinancials5/TurboCASH5. Some extra functions have been added to Reportman in osFinancials5. Some of these extra functions are; 'GETTEXTLANG' , 'RETURNSQL' , 'NUMBERTOWORDS' , 'GETPRICE', etc. Another important feature is Data access configuration.

In osFinancials5, all reports, including document layout files designed in Reportman, are fully translatable using the '*GETTEXTLANG*' function. This means that they can be displayed in any language by changing the language setting in the Switch language option (Start ribbon).

To customize the language files, you can access the Tools menu and select Customise language in the Setup ribbon. The language files are stored in the "*.../bin/languages*" folder.

When designing reports in Reportman, all objects are added to a selected page structure. For example, in the "*Tutorial-Invoice.rep*" report, the Page header contains expressions from the '*COMPANYINFO*' and *'DOCUMENTHEAD'* datasets, an image (company logo) from the COMPANYINFO dataset, and static text labels such as Telephone, Fax, and E-mail address.

To edit the objects in the report, you can click on a selected object in the list, and it will be displayed on the grid. From there, you can easily edit, move, resize, or set properties for the object.

If you encounter an error while printing or previewing the report, make note of the name and number of the object (expression, etc.). This information will be helpful in locating the specific object in the Report designer and resolving the error.

By utilizing the Report designer and following these steps, you can effectively customize and troubleshoot reports in osFinancials5/TurboCASH5.

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

Report man interface options

All document layout files and reports are installed and stored in the *...\plug_ins\reports* folder of your osFinancials5/TurboCASH5 installation directory.

To access the Report designer:

On the Setup ribbon, select Report designer. The Report designer will list all layout files and report folders as follows:



The buttons and options is as follows:

1. Copy report - If you need to edit a layout file or report, you need to select a file. If you click on a report or layout file, and you click on the Copy report button, it will create an exact copy (e.g. Copy of Reportname) of the report *.rep and the parameters *.dfm (if the report has parameters) file(s).

> *It is recommended that you do not edit an existing layout file or report, but create a copy and edit the copy until you get the required results.*

> *You may then rename the report. If you have any customised reports, you may create folders in the ...\plug_ins\reports\userreports\ folder and copy your reports to your folder. These reports may then be accessed from the Reports → User reports.*

Document layout files cannot be printed from any other folder than the ... \plug_ins\reports\DOCUMENTS\DOCUMENTS folder.

2. Edit - Launches the Report manager designer screen, where you may edit an existing report or layout file or create or edit a new report or layout file.
3. Delete - This will delete a selected layout file or report (*.rep) file (and the parameter (*.dfm) file, if applicable).

Please make sure that the correct report is selected. Deleting the incorrect report, it will be permanently lost.

4. New report – This will launch a blank report with no datasets using the ...\plug_ins\reports\New.rep template file. When you save the New.rep file, it will save it as New.rep in the folder in which the New report button was clicked on.

You may click on the New.rep and click again to rename the report.

If the New.rep is in the Reportman designer screen, you may use the File → Save as menu to save the report with your own name.

5. New folder – This will create a New folder in the selected folder. You need to double-click to rename the New folder.
6. Explorer folder - If a report is selected it and you click on this button, the folder containing that report will be launched in Windows Explorer or your system's default file browser.
7. Refresh - This will refresh the display (list of folders and files) in the Report man screen.

The No refresh after save option is by default selected (ticked). If this ticked is removed, it will automatically refresh the Report man screen when a report or layout file is selected. This may slow down your system.

8. Help - This button is inactive. The offline Reportman help can be accessed from the .../plug_ins/reportman/doc/indexes.html file in the osFinancials5/TurboCASH5 installation directory.

You may access the online help at http://reportman.sourceforge.net/

If you focus on a specific area of the Reportman designer screen, a ? will be added to the cursor, it will launch the specific topic at sourceforge (e.g. http://reportman.sourceforge.net/doc/refcommon.html).

9. Parameters - If a report has parameters, and you click on the Parameters button, the Parameters

screen for the selected report will be launched. An example of the Ledger Transactions report, is as follows:



10. Create parameters and open - This will launch the Report manager designer screen on which you may edit the Parameters (Report → Parameter definition menu) and Datasets (Report → Data access configuration menu).

> *If a report has no parameters and you click on this button, it will display an error message, e.g.*
>
> "No params found. create one first C:
> \osFinancials5\plug_ins\reports\userreports\Custom Reports\New.dfm"
>
> *You then need to close this message and click on the Parameters button to create parameters.*
>
> *If you find another report with similar parameters, you may copy the parameter *.dfm file to the folder of your report and rename it to the name of your report.*
>
> *You then need to edit the parameters and report.*

11. Preview - Click to preview a document layout file or a report. If a report has parameters, it will launch

the report parameters screen on which you may select the options to preview the data in the report.

Spreadsheet reports - stored in the "... \plug_ins\reports\excelreports" folder.

These reports will open in the integrated spreadsheet component in osFinancials5/TurboCASH5.

You cannot open, edit or preview these Spreadsheet reports in "Report man".

While editing a document layout file or a report, you may click on the Preview icon of the Report manager designer screen.

12. Select test document id button - If you click on the Preview button if document layout files (in the ... \plug_ins\reports\DOCUMENTS\DOCUMENTS folder) are selected the last document processed or printed will be previewed. If you click on this button you may select any other posted or unposted document to preview.

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Reports - File structure

The Report designer folder / file structure

All document layout files and reports are installed and stored in the ...\plug_ins\reports folder of your installation directory.

Access select Report designer:

On the Setup ribbon, select Report designer. The Report designer will list all layout files and report

folders as follows:



1. Document printing - All the layout files for printing documents are stored in the ... *\plug_ins\reports\DOCUMENTS\DOCUMENTS* folder.
2. Reports menu (Reports ribbon) - These reports are stored in the ... *\plug_ins\reports\systemreports* folder.
3. User reports menu (Reports ribbon) - These reports are stored in the "*userreports*" folder. Users are encouraged to create and/or edit existing reports, but it is recommended that these be copied and stored in the ... *\plug_ins\reports\userreports* folder.
4. Spreadsheet reports menu (Reports ribbon) - These reports are stored in the ... *\plug_ins\reports\excelreports* folder.
5. Ledger analyser and Reports - T-Account viewer (Reports ribbon) - Seven (7) reports are stored in the ...*\plug_ins\reports\GENERAL\ledgerview* folder. These are:
    a) budgetvsactsimple - Budget vs actual and This year vs last year report types.
    b) colbal - Not used.

c) colbalopen - Not used.

d) colbalopenonly - Not used.

e) colbalsimple - Standard column balances report type.

f) detail - Trial balance, Income statement and the Balance sheet report types.

g) ledgerdetail - Print button on the T-Account viewer.

h) openitemdays - Print Age analysis reports for current date or a selected date of ageing from Open item link - Due tab or Age analysis icon on the Reports ribbon.

6. Reports generated from inside the osFinancials5/TurboCASH5 on various screens are stored in the *...\plug_ins\reports\GENERAL\documents* folder. These are:

a) Batch Processing - Batch entry (F2) on the Default ribbon):

i) abbreviations - Abbreviation Definitions as set in the Batch entry – F9:Process option. If you click on the Print button of the Abbreviation screen, a list of Abbreviation definitions will be printed. The abbreviations listed on this report, may be used to automatically fill the description column in the document lines when processing documents (invoices, credit notes, quotes, purchases, supplier returns and orders).

ii) batch - Batch Listing on the Batch entry - F8:List - This will print a list of all transactions in an unposted batch.

iii) postedbatch - Batch Listing on the Batch entry - Posted batches - Details tab - Print button - This will print a list of all transactions in a posted batch.

iv) paycreditor - Prints the "*Automatic payments*" report when clicking on the Print button in the Payments Debtors / Creditors option (Batch entry - F9:Process).

v) paydebtor - Prints the "*Automatic receipts*" report Debtor payments report when clicking on the Print button in the Receive Payments / Creditors option (Batch entry – F9:Process).

vi) receipt - Prints a receipt if the "*Create receipts*" option is selected for Receipt batches in the Batch entry - F9:Process (and if the Print option is ticked).

vii) recon - Prints the Bank reconciliation report when clicking on the Report icon of the "*Reconcile Bank account*" screen (Cash/Bank entry on the Default ribbon).

b) Documents - Documents (F6)) menu (Default ribbon):

i) barcodes - context menu - Quick link to print the barcodes of the stock items selected on documents.

ii) labels - context menu - Quick link to print the postal address labels (and Contact name) of the debtors (customers / clients) selected on sales documents or creditors (suppliers) selected on purchase documents.

iii) labelsdelivery - Not implemented yet. This is similar than the labels report, but should print delivery addresses in stead of postal addresses.

c) Point-of-Sales (Standard) - Input - POS Invoice (Ctrl + F6) menu (Default tab):

i) oldpossales - This report prints from the Process - Reports or Cashup option on the POS Invoicing screen.

ii) oldposcashup - This report prints from the Process - Reports or Cashup option on the Input → POS Invoicing screen (Default ribbon).

d) Others:

i) datacheck - Prints the Data integrity check report from Tools - Data integrity check (Setup ribbon).

ii) groups - Prints the list of the Account group 1 / 2, Debtor group 1 / 2, Creditor group 1 / 2, Stock group 1 / 2, Document group 1 / 2, etc. when clicking on the Print button of a selected group on Setup → Groups (Setup ribbon).

iii) payments - Prints a Receipts / Payments advise when the "*Receive payment*" context menu option is selected (and the Print option is ticked) on the Open item link menu Transactions tab or on the Open item link screen (Default ribbon) for a debtor (customer / client) or creditor (supplier / vendor) account.

iv) Userlog - Prints the "*Userlog report*" when clicking on the Log report button on Setup → Access control (Setup ribbon).

7. REPORTS:

a) CREDITOR - (Creditors (F5) on the Default ribbon) – Selected Creditor Label (Postal address) and Selected Creditor Delivery Label (Delivery address). Print when you right-click on a selected creditor (supplier / vendor) account from the list.

b) DEBTOR - (Debtors (F4) on the Default ribbon) – Selected Debtor Label (Postal address) and Selected Debtor Delivery Label (Delivery address). Print when you right-click on a selected debtor (customer / client) account from the list.

c) STOCK - (Stock items (F12) on the Default ribbon) – Barcode and Yagoda barcode. Print when you right-click on a selected stock item or stock items from the list.

d) PROJECTS - If projects have been activated, and transactions have been entered in batches and documents, you may print five (5) reports (i.e. Transactions, Hours, Stock items,

Statements and the Total report). Budgets can also be entered for Projects, but it needs to be added to these reports.

e) HORECAPOS - This folder contains the reports for the HORECAPOS and RETAILPOS Plugins.

f) SUBSCRIPT - This folder contains the Subscriptions report. (See the Subscriptions folder – This folder contains the report, emailtemplates, layouts and Sql for the Subscriptions Plugin).

g) REPORTS FOLDER (Discontinued Reports) - The BATCHREPORT, CONTACTS, COSTCENTER, GL and TAX folders contains old reports not used in odFinancials5.

8. Folders and reports for Plugins:

a) EmailInvoice and debcred folders are used for the E-MailPro plugin.

b) parcel - This is not used at this stage – It is reserved for a Send Parcel plugin.

c) remittance - This contains the list report, emailtemplates and layouts for the Reminders plugin.

d) Subscriptions - This folder contains the report, emailtemplates, layouts and Sql for the Subscriptions Plugin.

Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

Reports - systemreports - Reports menu file names

The standard reports on the Reports menu is stored in the "*...\plug_ins\reports\systemreports*" folder of your installation directory.

When printing reports using the "*Material*" theme, the icons in the "*Material*" theme folder will be displayed in menus and the icons in the "*Classic*" theme folder will be displayed on the report parameters screens and in Report man.

To access the Report designer:

1. On the Setup ribbon, select Report designer. The Report designer will list all "*systemreports*" files and report folders as follows:



Reports menu - File structure and file names

When printing reports using the "*Material*" theme, the icons in the "*Material*" theme folder will be displayed in menus and the icons in the "*Classic*" theme folder will be displayed on the report parameters screens and in "*Report man*".

For your convenience, a list of the file names and structure of the reports in the Reports menu (Reports ribbon) is as follows:

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
Ledger			TRN_1372			
	Budget		TRN_1027			
			Budget vs actual (3 periods)	TRN_3372.rep		
	Listing		TRN_66			
			Chart of Accounts	TRN_73.rep		
	Transactions		TRN_74			
			Transactions	TRN_74.rep		
			Transactions - Standard	TRN_906110.rep		
			Transactions - Extra details	TRN_906111.rep		
Debtors			TRN_160			
	Debtor statement		TRN_1090			
			Debtor Statements	TRN_1090.rep		
			Debtors statement - Outstanding	TRN_906552.rep		
	Age analysis		TRN_65			
			Balances detail	TRN_906142.rep		
			Balances detail history (open item)	TRN_906143.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Balances	TRN_906147.rep		
	Listing		TRN_66			
			Contacts	TRN_2876.rep		
			Listing	TRN_66.rep		
			List delivery address	TRN_906138.rep		
			List postal address	TRN_906139.rep		
			List details	TRN_906140.rep		
			Credit control listing (Credit limit vs Current balance)	TRN_906338.rep		
			Tax and Company registration numbers	TRN_906339.rep		
	Print labels		TRN_68			
			Delivery address labels	TRN_906064.rep		
			Postal address labels	TRN_906137.rep		
	Transactions		TRN_74			
			Transactions	TRN_74.rep		
			Transaction List - Open item	TRN_906061.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Transactions - Standard	TRN_906106.rep		
			Transactions - Extra details	TRN_906107.rep		
			Transaction List	TRN_906440.rep		
Creditors			TRN_161			
	Creditor remittance advises		TRN_1089			
			Creditor remittance advise	TRN_1089.rep		
			Creditor remittance advise - Outstanding	TRN_906551.rep		
	Age analysis		TRN_65			
			Balances detail	TRN_906142.rep		
			Balances detail history (open item)	TRN_906143.rep		
			Balances	TRN_906147.rep		
	Listing		TRN_66			
			Contacts	TRN_2876.rep		
			Listing	TRN_66.rep		
			List delivery address	TRN_90613		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
				8.rep		
			List postal address	TRN_906139.rep		
			List details	TRN_906140.rep		
			Credit control listing (Credit limit vs Current balance)	TRN_906338.rep		
			Tax and Company registration numbers	TRN_906339.rep		
	Print labels		TRN_68			
			Delivery address labels	TRN_906064.rep		
			Postal address labels	TRN_906137.rep		
	Transactions		TRN_74			
			Transactions	TRN_74.rep		
			Transaction List - Open item	TRN_906061.rep		
			Transactions - Standard	TRN_906108.rep		
			Transactions - Extra details	TRN_906109.rep		
			Transaction List	TRN_906440.rep		
Sales			TRN_1792			

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
	Quotes		TRN_1870			
		Debtors	TRN_160			
			Quotes per period - Quantities	TRN_906315.rep		
		Sales	TRN_1792			
			Quotes per period - Quantities	TRN_906315.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
	Invoices		TRN_300			
		Debtors	TRN_160			
			Invoices per period - Quantities	TRN_906155.rep		
		Sales	TRN_1792			
			Invoices per period - Quantities	TRN_906155.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
	Credit notes		TRN_47			
		Debtors	TRN_160			

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Credit notes per period - Quantities	TRN_906311.rep		
		Sales	TRN_1792			
			Credit notes per period - Quantities	TRN_906311.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
Plugins			TRN_1805			
	Price agreement		TRN_3380			
			Debtor – Price agreement	TRN_906035.rep		
			Creditor – Price agreement	TRN_906088.rep		
	Location-Serials-Batches		TRN_3398			
			On hand	TRN_1777.rep		
			Stock movement	TRN_906038.rep		
			Outdated batch	TRN_906554.rep		
			Batch bought from supplier	TRN_906555.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Batch sold to customer	TRN_906556.rep		
Stock			TRN_1999			
	Reorder		TRN_1778			
			Reorder report	TRN_83.rep		
			Current stock levels	TRN_906268.rep		
	Print labels		TRN_68			
			Barcode	TRN_1774.rep		
			Yagoda barcode	TRN_906040.rep		
	Stock item listing		TRN_84			
			All selling prices	TRN_1056.rep		
			Tax classes	TRN_3465.rep		
			Stock item listing	TRN_84.rep		
	Backorder		TRN_906050			
			Backorder	TRN_906050.rep		
	Stock In / Out		TRN_906112			
			Stock In / Out - Documents	TRN_38.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Stock In / Out	TRN_906112.rep		
Point-of-Sale			TRN_2200			
	Standard		TRN_1990			
			Sales	TRN_1792.rep		
			Receipts	TRN_182.rep		
	Cash slip printer		TRN_906160			
			Sales	TRN_1792.rep		
			Receipts	TRN_182.rep		
Contacts			TRN_2876			
			Contacts	TRN_2876.rep		
Calendar			TRN_2879			
			Hours	TRN_2330.rep		
Batch entry			TRN_298			
			Documents	TRN_38.rep		
			Batch transactions per period	TRN_906141.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
Purchases			TRN_49			
	Purchase documents		TRN_1269			
		Creditors	TRN_161			
			Purchases per period - Quantities	TRN_906150.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
		Purchases	TRN_302			
			Purchases per period - Quantities	TRN_906150.rep		
	Orders		TRN_1871			
		Creditors	TRN_161			
			Orders per period - Quantities	TRN_906317.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
		Purchases	TRN_302			
			Orders per period - Quantities	TRN_906317.rep		
	Supplier returns		TRN_303			

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
		Creditors	TRN_161			
			Supplier returns per period - Quantities	TRN_906313.rep		
		Items	TRN_2052			
			Items per period	TRN_906115.rep		
		Purchases	TRN_302			
			Supplier returns per period - Quantities	TRN_906313.rep		
Company info			TRN_320			
			Bank accounts	TRN_183.rep		
			Information	TRN_629.rep		
Currencies			TRN_3470			
			Currencies	TRN_3470.rep		
Documents			TRN_38			
	Document listing		TRN_45			
			Document listing	TRN_45.rep		
	Document listing per account		TRN_906161			

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
		Sales documents	TRN_1268			
			Invoices	TRN_300.rep		
			Quotes	TRN_418.rep		
			Credit notes	TRN_706.rep		
		Purchase documents	TRN_1269			
			Purchases	TRN_302.rep		
			Supplier returns	TRN_303.rep		
			Orders	TRN_798.rep		
	Unprinted document listing		TRN_906162			
		Sales documents	TRN_1268			
			Invoices	TRN_300.rep		
			Quotes	TRN_418.rep		
			Credit notes	TRN_706.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
		Purchase documents	TRN_1269			
			Purchases	TRN_302.rep		
			Supplier returns	TRN_303.rep		
			Orders	TRN_798.rep		
Sales analysis			TRN_85			
	Quotes per period		TRN_3568			
			Quotes per period - Debtor group 1	TRN_906301.rep		
			Quotes per period - Debtor group 2	TRN_906302.rep		
			Quotes per period - Document group 1	TRN_906303.rep		
			Quotes per period - Document group 2	TRN_906304.rep		
			Quotes per period - Salesperson	TRN_906305.rep		
	Invoices per period		TRN_3570			
			Invoices per period - Debtor group 1	TRN_906157.rep		
			Invoices per period - Debtor group 2	TRN_906158.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Invoices per period - Document group 1	TRN_906159.rep		
			Invoices per period - Document group 2	TRN_906165.rep		
			Invoices per period - Salesperson	TRN_906166.rep		
	Credit notes per period		TRN_3569			
			Credit notes per period - Debtor group 1	TRN_906291.rep		
			Credit notes per period - Debtor group 2	TRN_906292.rep		
			Credit notes per period - Document group 1	TRN_906293.rep		
			Credit notes per period - Document group 2	TRN_906294.rep		
			Credit notes per period - Salesperson	TRN_906295.rep		
	Sales per product		TRN_3571			
			Sales per product - Stock group 1	TRN_906174.rep		
			Sales per product - Stock group 2	TRN_906175.rep		
	Sales per period		TRN_906122			
			Sales per period - Debtor group 1	TRN_906332.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Sales per period - Debtor group 2	TRN_906333.rep		
			Sales per period - Document group 1	TRN_906334.rep		
			Sales per period - Document group 2	TRN_906335.rep		
			Sales per period - Salesperson	TRN_906336.rep		
Tax			TRN_906020			
			Transactions	TRN_20069.rep		
			Tax list debtor with tax id	TRN_3675.rep		
			Tax per period	TRN_906105.rep		
			Tax report - Reference / Document no.	TRN_906550.rep		
			Tax list creditor with tax id	TRN_906553.rep		
Purchase analysis			TRN_977			
	Orders per period		TRN_3572			
			Orders per period - Creditor group 1	TRN_906306.rep		
			Orders per period - Creditor group 2	TRN_906307.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Orders per period - Document group 1	TRN_906308.rep		
			Orders per period - Document group 2	TRN_906309.rep		
			Orders per period - Salesperson	TRN_906310.rep		
	Purchases per period		TRN_3573			
			Purchases per period - Creditor group 1	TRN_906152.rep		
			Purchases per period - Creditor group 2	TRN_906153.rep		
			Purchases per period - Document group 1	TRN_906154.rep		
			Purchases per period - Document group 2	TRN_906163.rep		
			Purchases per period - Salesperson	TRN_906164.rep		
	Supplier returns per period		TRN_3574			
			Supplier returns per period - Creditor group 1	TRN_906296.rep		
			Supplier returns per period - Creditor group 2	TRN_906297.rep		
			Supplier returns per period - Document group 1	TRN_906298.rep		

Folder	Sub-folder1	Sub-folder2	Internal folder name / Report name	Internal report name	Classic	Material
			Supplier returns per period - Document group 2	TRN_906299.rep		
			Supplier returns per period - Salesperson	TRN_906300.rep		
	Purchases per product		TRN_3575			
			Purchases per product - Stock group 1	TRN_906172.rep		
			Purchases per product - Stock group 2	TRN_906173.rep		
	Purchases and Supplier returns per period		TRN_906337			
			Purchases documents per period - Creditor group 1	TRN_906327.rep		
			Purchases documents per period - Creditor group 2	TRN_906328.rep		
			Purchases documents per period - Document group 1	TRN_906329.rep		
			Purchases documents per period - Document group 2	TRN_906330.rep		
			Purchases documents per period - Salesperson	TRN_906331.rep		

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Reports - excelreports - Spreadsheet reports menu file names

Spreadsheet reports menu

Spreadsheet reports osFinancials5/TurboCASH5 and the power of Spreadsheets

- Spreadsheet_sales (Default ribbon).

- Spreadsheet_reports (Reports ribbon).

See - Video on Spreadsheet reports.

These spreadsheet reports are stored in the "*...\plug_ins\reports\excelreports*" folder of your installation directory.

Selected reports will be opened in the powerful spreadsheet feature in osFinancials5/TurboCASH5.



When printing reports using the "*Material*" theme, the icons in the "*Material*" theme folder will be displayed in menus and the icons in the "*Classic*" theme folder will be displayed on the report parameters screens and in "*Report man*".

Spreadsheet reports menu - File structure and file names



These Spreadsheet reports cannot be edited, previewed and opened in the Report designer or from the "Report man" screen.

For your convenience, a list of the file names and structure of the reports in the Spreadsheet reports menu (Reports ribbon) is as follows:

Menu item	*Sub-menu item 1*	*Sub-menu item 2*	*Internal file name*	*Classic theme*	*Material theme*
Debtors			*TRN_160*		
Creditors			*TRN_161*		
Transactions			*TRN_20069*		
	Per period		*TRN_3314*		

Menu item	*Sub-menu item 1*	*Sub-menu item 2*	*Internal file name*	*Classic theme*	*Material theme*
General ledger			*TRN_32*		
	Budget		*TRN_1027*		
		This year	*TRN_603*		
		Reporting group 1	*TRN_1323*		
	Column balances		*TRN_3106*		
		This year	*TRN_603*		
		Reporting group 1	*TRN_1323*		
Sales analysis			*TRN_85*		
	Stock movement		*TRN_906038*		
	Sales per period		*TRN_906122*		

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Reports - userreports - User reports menu fille names

User reports menu

These user reports are stored in the "...*plug_ins**reports**userreports*" folder of your installation directory.

When printing reports using the "*Material*" theme, the icons in the "*Material*" theme folder will be displayed in menus and the icons in the "*Classic*" theme folder will be displayed on the report parameters screens and in "*Report man*". For your convenience, a list of the file names and structure of the reports in the User reports menu (Reports ribbon) is as follows:



To access the Report designer:

1. On the Setup ribbon, select Report designer.

2. The Report designer will list all "*userreports*" files and report folders as follows:



User reports menu - File names

Menu item	*Sub-menu item 1*	*Internal folder name / Report name*	*Internal report name*	*Classic theme*	*Material theme*
Custom reports			*2cred-sku-det.rep* *2deb-sku-det.rep*		

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
Tax		TRN_906583	Tax codes - Tax rates		
Debtors		TRN_160			
	Outstanding	TRN_947			
		Due date	TRN_2222.rep		
		Debtors Outstanding at date	TRN_906104.rep		
Creditors		TRN_161			
	Outstanding	TRN_947			
		Due date	TRN_2222.rep		
		Creditors Outstanding at date	TRN_906103.rep		
Graphs		TRN_906557			
	Graphs per week	TRN_906558			
	Graphs per month	TRN_906559			
Tutorial reports		Debtors and Creditor Listing - Reportman basic examples			

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

Reports - userreports - Graphs file names

User reports - Graphs menu

These user reports are stored in the "*...\plug_ins\reports\userreports*" folder of your installation directory. These user reports are included in the osFinancials5.1 installation.

When printing reports using the "*Material*" theme, the icons in the "*Material*" theme folder will be displayed in menus and the icons in the "Classic" theme folder will be displayed on the report parameters screens and in "*Report man*".

For your convenience, a list of the file names and structure of the reports in the User reports menu (Reports ribbon) is as follows:



To access the Report designer:

1. On the Setup ribbon, select Report designer.
2. The Report designer will list all userreports files and report folders as follows:



User reports menu - File names

Graphs (TRN_906557) - File names

Graphs is currently added in the User reports menu.

Graphs per week (TRN_906558)

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
Ledger	TRN_1372				
		Graph - Profit Loss per week	TRN_906169.rep		
Debtors	TRN_160				
		Graph - Debtors per week	TRN_906168.rep		
Creditors	TRN_161				
		Graph - Creditors per week	TRN_906167.rep		
Sales	TRN_1792				
	Quotes per period	TRN_3568			
		Graph - Quotes per week - Quantities	TRN_906323.rep		
		Graph - Quotes per week - Amount	TRN_906324.rep		
	Credit notes per period	TRN_3569			
		Graph - Credit notes per week - Quantities	TRN_906319.rep		
		Graph - Credit notes per week - Amount	TRN_906320.rep		
	Invoices per period	TRN-3570			
		Graph - Invoices per week - Quantities	TRN_906170.rep		

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
		Graph - Invoices per week - Amount	TRN_906171.rep		
	Sales per period	TRN_906122			
		Graph - Invoices - Credit notes per week - Quantities	TRN_906579.rep		
		Graph - Invoices - Credit notes per week - Amount	TRN_906580.rep		
Purchases		TRN_302			
	Purchases				
		Graph - Purchases - Supplier returns per week - Quantities	TRN_906581		
		Graph - Purchases - Supplier returns per week - Amount	TRN_906582		
	Orders per period				
		Graph - Orders per week - Quantities	TRN_906325.rep		
		Graph - Orders per week - Amount	TRN_906326.rep		
	Supplier returns per period				
		Graph - Supplier returns per week - Quantities	TRN_906321.rep		
		Graph - Supplier returns per week - Amount	TRN_906322.rep		
	Purchases per period				

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
		Graph - Purchases per week - Quantities	TRN_906289.rep		
		Graph - Purchases per week - Amount	TRN_906290.rep		

Graphs per month (TRN_906559)

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
Ledger	TRN_1372				
		Graph - Profit Loss per month	TRN_906560.rep		
Debtors	TRN_160				
		Graph - Debtors per month	TRN_906561.rep		
Creditors	TRN_161				
		Graph - Creditors per month	TRN_906562.rep		
Sales	TRN_1792				
	Quotes per period	TRN_3568			
		Graph - Quotes per month - Quantities	TRN_906563.rep		
		Graph - Quotes per month - Amount	TRN_906564.rep		
	Credit notes per period	TRN_3569			

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
		Graph - Credit notes per month - Quantities	TRN_906565.rep		
		Graph - Credit notes per month - Amount	TRN_906566.rep		
	Invoices per period	TRN-3570			
		Graph - Invoices per month - Quantities	TRN_906567.rep		
		Graph - Invoices per month - Amount	TRN_906568.rep		
	Sales per period	TRN_906122			
		Graph - Invoices - Credit notes per month - Quantities	TRN_906569.rep		
		Graph - Invoices - Credit notes per month - Amount	TRN_906570.rep		
Purchases		TRN_302			
	Purchases				
		Graph - Purchases - Supplier returns per month - Quantities	TRN_906571.rep		
		Graph - Purchases - Supplier returns per month - Amount	TRN_906572.rep		
	Orders per period				
		Graph - Orders per month - Quantities	TRN_906574.rep		
		Graph - Orders per month -	TRN_906573.rep		

Menu item	Sub-menu item 1	Internal folder name / Report name	Internal report name	Classic theme	Material theme
		Amount			
	Supplier returns per period				
		Graph - Supplier returns per month - Quantities	*TRN_906576.rep*		
		Graph - Supplier returns per month - Amount	*TRN_906575.rep*		
	Purchases per period				
		Graph - Purchases per month - Quantities	*TRN_906578.rep*		
		Graph - Purchases per month - Amount	*TRN_906577.rep*		

Created with the Standard Edition of HelpNDoc: Powerful and User-Friendly Help Authoring Tool for Markdown Documents

Report designer menu structure

The "*Report manager designer*" is launched from the "*Report man*" screen.

The "*Report manager designer*" interface an menu structure provides all the options and tools to create and edit reports document layout files as well as reports and templates used for Plugins.

File menu



The options is as follows:

1. Libraries - Configure libraries - On the "*Edit connections*" screen, you may add new connections, manage connections and delete connections. In the osFinancials5/TurboCASH5 setup this is not used, since the reports and database connections is already configured and available.

2. Save as... - This will launch the Save as screen where you may save the active report.

> *It will only save the *.rep file of the active report. If a report contains parameters, the parameters *.dfm file will not be saved. To Save a report (*.rep), as well as the parameters (*.dfm) files, Use the Copy report option on the "Report man" screen and rename the report.*

3. Page setup -

4. Print preview -

5. Print -

6. Printer setup... -

7. Exit - This will close the "Report manager designer" screen.

> *Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will*

	be discarded (lost).

8. Recent reports opened -

Report menu



Report → Add



Add - You may select to add a Page header, Page footer, Group header and footer, Subreport or Detail to the structure of the report.

You may also click on the icon on the Structure tab.



Edit menu



To Delete or Cut more than one object, select more than one (1) object (using the Shift + mouse click).

Edit → Select menu



All - This will select all objects on the report.

All text - This will select only the text objects and expressions, excluding simple drawings, shapes and images.

Edit → Move menu



This will move a selected object one space to the left, right, up or down.

To move more than one object, select more than one (1) object (using the Shift + mouse click).

To move all, first select Edit → Select → All option.

To move all the text objects and expressions, excluding simple drawings, shapes and images., first select Edit → Select → All text option.

Edit → Align menu



To activate the align objects, you must select more than one (1) object (using the Shift + mouse click) or Edit → Select → All / All Text menu options.

Help menu



Documentation

In addition to the Reportman topics, in this documentation, a set of offline documentation is stored in the " ... \plug_ins\reportman\doc " folder of your osFinancials5/TurboCASH5 installation directory.

You may launch the index.html file (... / plug_ins/reportman/doc/index.html) in your web browser.

The official online documentation of the Report Manager is available at https://reportman.sourceforge.io/ .

If you focus on a specific area of the fields on the "Report manager designer" screen, a question mark ? will appear attached to the mouse pointer ("cursor").

This will launch and display the specific topic (for example, https://reportman.sourceforge.io/doc/refexpression.html) in your system's default internet browser.

System information



About Report manager



Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

Report designer - Add / Insert objects

For your convenience, the properties of the objects as at the back of this book.

1. Objects – The following most commonly used objects are added to a section of the report structure:

   a) TRpImage – This is used to display your company logo on the reports and document layout files. The Company Logo dataset is COMPANYINFO.LOGO (or COMPANYDATA.LOGO). The logo is stored in the database as a BLOB (Binary Large Object) and will be displayed if loaded in Setup → Company info - Options screen (Setup ribbon).

   b) TRpShape – Inserts a shape (i.e. rectangle, square, rounded rectangle, rounded square, ellipse, circle, horizontal line, vertical line, oblique 1 and oblique 2). These may be configured (formatted) using Pen Style, Pen Color, Pen Width, Brush Style and Brush Color. In most of the document layout files (excluding the Plain range), the rounded rectangle shape with a clear

brush, is used to group blocks of data.

c) TRpLabel – Add static text object to the report. Examples on the above picture are, Tax Invoice, Delivery address, Telephone, Fax, E-mail Address, etc.

d) TRpExpression – This will add an expression object to the report. If you click on the Data tab (on the left pane), Select a dataset (e.g. COMPANYINFO) and the datafield (e.g. COMPANYINFO.COMANYNAME) and simply drag it to the section of the report where you need to display it.

2. Other objects which may be added to reports are as follows:

a) TRpBarcode – This will add a barcode object to the report.

b) TRpChart – This add a chart object to the report. The Graphs per week en Graphs per month repost is examples where this object is used.

Created with the Standard Edition of HelpNDoc: Maximize Your PDF Protection with These Simple Steps

Report designer - Edit / Move / Align objects

Objects may be selected and edited or moved. These icons will only be active when an object is selected.

1. Editing Icons (also available on the Edit menu)

a) Select - Select an object on the report.

b) Delete - This icon will delete a selected object. (Keyboard: Ctrl + Del).

c) Cut - This will cut a selected object. (Keyboard: Alt + X).

d) Copy - This will place a copy of the selected object on the clipboard. (Keyboard: Alt + C).

e) Paste - This will paste (insert) the object from the clipboard. (Keyboard: Alt + X).

2. Moving Object Icons (also available on the Edit → Move menu)

a) Move left - Each click moves the selected object one space to the left. (Keyboard: Ctrl + Left).

b) Move right - Each click moves the selected object one space to the right. (Keyboard: Ctrl + Right).

c) Move up - Each click moves the selected object one space to the up. (Keyboard: Ctrl + Up).

d) Move down - Each click moves the selected object one space to the down. (Keyboard: Ctrl + Down).

3. Aligning Object icons (also available on the Edit → Align menu) - To activate the align objects, you must select more than one (1) object (using the Shift + mouse click) or Edit → Select → All / All Text menu options.

a) Align left - Aligns selection to the left.

b) Align right - Aligns selection to the right.

c) Align top - Aligns selection to the top.

d) Align bottom - Aligns selection to the bottom.

e) Align horizontal space - Aligns selection distributing horizontal space.

f) Align vertical space - Aligns selection distributing vertical space.

Created with the Standard Edition of HelpNDoc: Easily create PDF Help documents

Report designer - Add / Insert expressions

Once you have selected a section of the report, where you need to add data, click on the Data tab. It will list all your datasets and variables. Select a dataset (in this example the DOCUMENTHEAD dataset is selected). The dataset consists of various datafields or columns. After each database field, the properties (i.e. Data type and Database field length) is displayed.



There are two (2) basic steps to add database fields or expression objects to the report (i.e. drag and drop or manually adding expression objects). These are:

1. Draging and Dropping fields – After testing datasets and connections, you can select a database field, drag and drop it easily to report sections. This will add an expression object to the report.

2. Manually Adding Expressions – Should you need to build an expression consisting of more than one database field, and need one condition, for example (IIF(condition,Value is true,Value is false), etc., you need to click on the icon on the icon toolbar.

This will launch the Dialog screen, with a basic default expression (i.e. 2+2). When you click on the Show data button it will return a result of 4.

On this Dialog screen, you may add values (Operation) for the various Categories (i.e. Database fields, Functions, Variables, Constants and Operators) to define an expression object.

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Report designer - Report Structure and Data

The left pane consists of the following two (2) tabs:

1. Structure – On this tab you need to select the report section (i.e. subreport, headers, footers, detail, etc.) to which you may add / edit objects (i.e. images, shapes, labels, expressions, barcodes, charts and variables).

2. Data – On this tab you need to select the dataset. You may easily add / edit objects (i.e. images, shapes, labels, expressions, barcodes, charts and variables) to include in your report or document layout file.

The right pane consists of the report document in the designer mode.

Created with the Standard Edition of HelpNDoc: Full-featured Documentation generator

Report designer - Structure tab

If you click on Subreport-0. The setting for the object is linked to the DOCUMENTLINE dataset. This means that for each record, the column detail is printed.

If you define a new group, it will when the groups field, the group footer will be printed followed by the new group header.



In this report, the report footer is linked to Subreport-1



If you select the footer, you may view the properties of the link to the Subreport-0(DOCUMENTLINE).

The Footer – MAINGROUP(Subreport-1) is a Child Subreport of the Subreport-0(DOCUMENTLINE).

You may also link a detail row to a subreport. In combination with the masterdataset, you may link the masterdetail.

In the object inspector you may define settings and formats for the different objects. These object properties will be discussed briefly later in this document.

Created with the Standard Edition of HelpNDoc: Create help files for the Qt Help Framework

Report designer - Data tab

Created with the Standard Edition of HelpNDoc: Make the switch to CHM with HelpNDoc's hassle-free WinHelp HLP to CHM conversion tool

Report designer - Data objects

Created with the Standard Edition of HelpNDoc: Quickly and Easily Convert Your Word Document to an ePub or Kindle eBook

Report designer - Data access configuration

The Database connections and datasets is the heart of the Report manager. Parameters needs to be passed from osFinancials5/TurboCASH5 to Reportman for the various reports.

For documents, the *TCVAR_DOCID* parameter is used. This parameter contains the document number in the Dochead table.



For example, in the case of Stock reports, you may need to use the SQL parameter for the data in Stock items (Default ribbon) to activate your search action. This will enable you to define and add various

criteria to be used in a report.

To access this you may click on the icon on icon toolbar or go to the Report → Data access configuration menu.





Here you may define your SQL, relationships and parameters to be used for the report.

Here you may define your SQL, relationships and parameters to be used for the report.

Created with the Standard Edition of HelpNDoc: Free CHM Help documentation generator

Report designer - Writing SQL

To write SQL is actually very simple, for example, “select data from table”, where data is a valid field name (e.g. ScompanyName Company Name) in the table and table is a valid table name (e.g. Sysvars).

To call the company name and Fax number (as entered in the Company info (Setup ribbon) screen (it is stored in the sysvars table)), you may simply write *select SCompanyName CompanyName, SFaxNumber Fax from Sysvars*.

Select YOUR DATA FIELDS from sysvars

An example of the SQL for the COMPANYINFO dataset is as follows:

SQL Text	*Data on Screens*
select *SCompanyName CompanyName,* *BlobLogo Logo,* *SAddress1 Address1,* *SAddress2 Address2,* *SAddress3 Address3,* *SPostCode Postcode,* *SPhoneNumber Telephone,* *SFaxNumber Fax,* *SEmailAddress EMailAddress,* *SCompanyRegNo CompanyRegNo,* *STaxRegNo TaxRegNo,* *SBANKNAME1 BankName1,* *SBANKNAME2 BankName2,* *SBANKNUMBER1 BankNo1,* *SBANKNUMBER2 BankNo2,* *SBANKSWIFT1 BankSwift1,*	*Setup Company info*

SQL Text	Data on Screens
SBANKSWIFT2 BankSwift2, SBANKIBAN1 BankIBAN1, SBANKIBAN2 BankIBAN2, SBANKACCOUNTNAME1 BankAccountName1, SBANKACCOUNTNAME2 BankAccountName2, SInvoiceHeading InvoceHead, SInvoicesMessage1 InvoiceMessage1, SInvoicesMessage2 InvoiceMessage2, SInvoicesMessage3 InvoiceMessage3,	Setup Documents (Invoices)
SCreditNoteHeading CreditNoteHead, SCreditNoteMessage1 CreditNoteMessage1, SCreditNoteMessage2 CreditNoteMessage2, SCreditNoteMessage3 CreditNoteMessage3,	Setup Documents (Credit notes)
SQuoteHeading QuoteHead, SQuoteMessage1 QuoteMessage1, SQuoteMessage2 QuoteMessage2, SQuoteMessage3 QuoteMessage3,	Setup Documents (Quotes)
SPurchaseHeading PurchaseHead, SPurchasesMessage1 PurchaseMessage1, SPurchasesMessage2 PurchaseMessage2, SPurchasesMessage3 PurchaseMessage3,	Setup Documents (Purchases)
SGoodsReturnedHeading SupplierReturnHead, SGoodsReturnedMessage1 SupplierReturnMessage1, SGoodsReturnedMessage2 SupplierReturnMessage2, SGoodsReturnedMessage3 SupplierReturnMessage3,	Setup Documents (Supplier returns)
SOrderHeading OrderHead, SOrderMessage1 OrderMessage1,	Setup Documents (Orders)

SQL Text	Data on Screens
SOrderMessage2 OrderMessage2, SOrderMessage3 OrderMessage3, SStatementMessage1 StatementMessage1, SStatementMessage2 StatementMessage2, SStatementMessage3 StatementMessage3,	Setup Statements
SSellingPriceName1 SellingPrice1, SSellingPriceName2 SellingPrice2, SSellingPriceName3 SellingPrice3,	Setup Stock information (selling prices)
SAccountReportName1 LedgerRepGroup1, SAccountReportName1 LedgerRepGroup2,	Setup Account groups
SDebtorReportName1 DebtorRepGroup1, SDebtorReportName2 DebtorRepGroup2,	Setup Debtor groups
SCreditorReportName1 CreditorRepGroup1, SCreditorReportName2 CreditorRepGroup2,	Setup Creditor groups
SStockReportName1 StockRepGroup1, SStockReportName1 StockRepGroup2,	Setup Stock groups
WRetainedIncomeID RetainedIncomeAccId, WDebtorsControlID DebtorsControlAccId, WCreditorsControlID CreditorControlAccId	Control accounts linked to the books (default per Set of Books template selected or specified in the Create Set of Books (Advanced) option on the creation wizard.
from sysvars	

Created with the Standard Edition of HelpNDoc: Maximize Your Productivity with HelpNDoc's CHM Help File Creation Features

Report designer - Add a Dataset

Additional fields any be added using the FreeFields Plugin / Extension. The SYSVARSEXT table is already present in all Sets of Books.

To add your data to the report, simply do the following:

1. Enter your data in the Setup → Company info - Additional Data - (Setup ribbon) section, if these fields are blank.

2. Launch the Report designer from the Setup ribbon.
3. Select MyInvoice.rep and double-click on it (or click on the Edit button of the Report man screen).
4. On the Report manager designer screen, go to Report → Data access configuration menu and add the Dataset *SYSVARSEXT* as a new Dataset.
5. Copy the following SQL text to the text box:

```
Select
SCONTACTNAME  ContactName,
SMOBILE  MobileNo
from Sysvarsext
```

6. Click on the Show data button. Your data (as entered in the Setup → Company info - Additional data section (Setup ribbon) will now be displayed.
7. Close the "*Data* preview" screen. Click on the OK button of the" *Data access configuration"* screen to save the changes.
8. In the Structure tab of the Report manager designer screen, select the section of the Report where you wish to add this data.
9. Click on the Data tab.
10. Select the "*SYSVARSEXT"* Dataset and expand the tree. Select the "*SContactName*" field and drag it to the section of the report. Also drag the "*Smobile*" Data field and drag it to the report section.

11. Click on the Preview button of the Report manager designer screen to view your data.

12. You may wish to add Labels (Static Text) objects to the labels. This newly added data will be displayed on the new layout file.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Report designer - View Dataset

To view the datasets:

1. On the "*Report manager designer*" screen, click on the Data access configuration icon

2. Select the Dataset from the list and click on the Show data button.



3. In this example, the Data (for the "*COMPANYINFO*" Dataset) is as follows:

If you click on the Exit button, you will return to the "*Database connections and datasets"* screen.

You may view other Datasets.

4. For example, if you view the "*DOCUMENTLINE*" Dataset, and you have more than one line in the document (transactions and/or comments), you may click on the Next and First record buttons to view the transactions / and or comments.

5. Click on the OK button of the "*Database connections and datasets"* screen.

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Report man interface

To make it easier to introduce Reportman and to get started with editing customising document layout files, we start with a practice task. The Data structures and complex stuff will be added at the end of this Document for reference purposes.

It is not necessary to use parameters for reports, but it is useful in the case of document layout files.

The first step is to understand the ease of use of the Reportman interface and configuring Reportman. To do this, we have created a TestInvoice.rep in the latest update.

Follow these easy steps to explore and see the Reportman:

1. Once the Report man screen is opened (default DOCUMENTS/DOCUMENTS), select the TestInvoice.rep in the list of Documents.

2. Click on the Explorer folder button.

3. Copy the TestInvoice.rep (in the File Explorer folder) and rename it to MyInvoice.rep.



4. Click on the Refresh button and select the MyInvoice.rep. You may double-click (or click on the Edit button) to open the Invoice in the Report manager designer screen.



Document layout file - Structure

SubReport-0(DOCUMENTLINE)

These are the fields that print at the top of the document layout file as well as the document headings that appear for the item(s) in the document lines.

SubReport-1(TAX)

These are the Totals and the fields that print at the bottom of the document layout file.

SubReport-2(SERIALS)

It lists the series and serial numbers as well as location selected with the Place Series Batch plugin on the document lines.

SubReport-3(OPTIONS)

It lists the options selected for the option items and option items (no stock) stock item types selected on the document lines.

Created with the Standard Edition of HelpNDoc: Easy EBook and documentation generator

Reportman output

Output Icons – See Data access configuration. If you cannot establish a database connection, you will not be able to preview or print the report.

- Preview – View the report on the screen.
- Print – Opens the Print dialog on which you may select a printer, printer properties, select pages (if required).

Preview

Once you can view data (using the Show data button), you may click on the Preview icon on the icon toolbar of the "*Report manager designer*" screen to preview the report or document layout file.



Preview in PDF format

It may be important to check your document layout file in PDF format, as PDF format for document layout files, may in most cases, be sent to debtors (customers / clients) and to creditors (suppliers / vendors).

If there are any adjustments, you can edit the document.

The data displayed in the preview of the invoice, should be your own data as entered in the Company info (Setup ribbon) and Debtors (Default ribbon), and in your document header and document lines file.

Created with the Standard Edition of HelpNDoc: Make Help Documentation a Breeze with a Help Authoring Tool

Reportman - Select test document id

You can regularly preview your document layout file on screen. This will point out possible errors as well as where you can make the document layout file neater by moving fields, enlarging, setting the font properties, etc.

When you want to preview a document layout file, the last or most recently processed document will be available for you to view or when you:

- click on the Print preview button from the "*Report man*" screen, or
- click the Preview report on screen icon) from the "*Report manager designer*" screen.

When you are editing a document layout file and you want to preview the document layout file, you can click on the Select test document id button to select a specific document layout file.

You can select any sales documents (i.e. Quotes, Invoices and Credit notes) or purchase documents (i.e. Orders, Purchases and Supplier returns) document type.

These document types may be posted or unposted, confirmed or unconfirmed.



In the case of sales documents (i.e. Quotes, Invoices and Credit notes), the document number, debtor (customer / client) account and total will list the document.

In the case of purchase documents (i.e. Orders, Purchases and Supplier returns), the document number, creditor (supplier / vendor) account and total will list the document.

The selected document id (which was automatically generated when documents were created, copied or imported) will be displayed, for example 72 - IN000022.

Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Reportman output - Transparent setting

Preview document layout file in PDF-format

If there are any adjustments, you can edit the document, as PDF format for document layout files may in most cases be sent to debtors (customers / clients) and to creditors (suppliers / vendors).

To preview the document layout file in the PDF format:

When you click on the Print preview button from the "*Report man*" screen, select the "*Open in PDF*"-option and click OK.



An example of the document layout file opened in the PDF format of your system's default PDF application (in this example, "*Microsoft Edge*"):



Transparent setting

The Transparent setting if set to "*False*" for an object (e.g. Static text, Expression, etc.) will print and display correctly when you click on the Print preview button from the "*Report man*" screen, or on the the Preview report on screen icon) from the "*Report manager designer*" screen.

Should you Print the document layout file, in the PDF format the "Transparent" setting, if set to "False", will display a rectangular lines around the object (e.g. Expression, Static text, etc.).

To change the transparent setting:

Select the document layout file end click on Edit button of the "*Report man*" screen.

Select the Expression. In this example, it is the Comments displaying a rectangular border.

On the Text tab, Transparent is set to "*False*".

Change the Transparent to "*True*".



Close the "Report manager designer" screen, and save the report.

Click on the Print preview button from the "*Report man*" screen, select the "*Open in PDF*"-option and click OK.

An example of the document layout file (with the Transparent setting set to " *True*") opened in the PDF format of your system's default PDF application (in this example, "*Microsoft Edge*"):



Created with the Standard Edition of HelpNDoc: Easily create Web Help sites

Report designer - Customise layout files

Report designer - Customise layout files

In osFinancials5/TurboCASH5, you have the option to further customise document layout files using the Report designer feature available on the Setup ribbon. This functionality provides users with additional flexibility and control over the appearance and content of their financial documents.

Here's how you can customise document layout files using the Report designer:

1. Select Existing Layout or Your Own Layout File: In osFinancials5/TurboCASH5, the Report designer allows you to choose from existing layout files or create your own layout from scratch. You can select a pre-defined layout file that closely matches your requirements and then make modifications as needed. Alternatively, you have the freedom to start with a blank layout file and build it according to

your specific preferences.

2. Customize Layout Elements: Using the Report designer, you can customize various elements of the document layout. This includes adjusting the placement and formatting of fields, headers, footers, company logo, transaction details, and any other relevant content.
3. Add or Remove Fields: You can add or remove fields as necessary to display the information you want on the document. This allows you to include or exclude specific details that are relevant to your business and industry.
4. Formatting and Styling: The Report designer provides options to format and style the document layout. You can choose font styles, colors, borders, and other visual elements to match your branding and create a professional look.
5. Preview and Test: As you make changes in the Report designer, you can preview how the document will look before finalizing the layout. This allows you to test the design and ensure that it meets your expectations.
6. Save and Apply Layout: Once you are satisfied with the customizations, you can save the layout and apply it to the respective document type. The modified layout will then be used when generating documents of that type in osFinancials5/TurboCASH5.

By providing the option to customize document layout files using the Report designer, osFinancials5/TurboCASH5 empowers businesses to create personalized and professional financial documents that align with their unique needs and preferences. This feature adds another layer of adaptability and customization to the accounting software, enhancing the user experience and ensuring that documents reflect the company's branding and style.

Created with the Standard Edition of HelpNDoc: Free EPub and documentation generator

---

Designing custom layout files for documents

When designing custom layout files for documents such as invoices or any other types of documents in osFinancials5/TurboCASH5 Report designer (Setup ribbon), it's crucial to consider the requirements of your tax jurisdiction. This includes not only the content of the document but also its appearance and formatting.

Here are a few points to keep in mind when designing custom layout files for documents, especially invoices, while considering tax jurisdiction requirements:

1. Document Name: The name of the document may need to include specific terms like "*Invoice*","*Tax Invoice*" or "*VAT Invoice*," based on the requirements of your tax jurisdiction. Ensure that the document name aligns with the regulations.
2. Mandatory Information: Different tax jurisdictions may require specific information to be present on invoices, such as your business details, customer details, itemised list of products or services, quantities, prices, applicable taxes, and total amount. Make sure all the necessary information is included and properly formatted.
3. Tax Details: Invoices should clearly display tax-related details, including the tax rate, tax amount, and any tax identification numbers required by your tax authority.
4. Currency: If you conduct transactions in multiple currencies, consider including the currency in which the transaction is conducted.
5. Formatting: Ensure that the layout is clear, well-organized, and easy to read. Follow any specific formatting guidelines prescribed by your tax jurisdiction.
6. Localisation: If your business operates in multiple countries or regions with different tax regulations, consider creating different layouts or templates tailored to each jurisdiction's requirements.
7. Logo and Branding: Your company logo and branding should still be prominently displayed on the layout, maintaining your professional identity.
8. Language: If required, provide translations or multilingual options to accommodate different languages spoken in your region.
9. Accessibility: Ensure that the layout is accessible to people with disabilities, complying with accessibility standards if applicable.
10. Testing and Adjusting: Ensure to thoroughly test the document layout file by printing it and generating it in PDF format. This helps to verify the alignment and presentation of the content. If needed, make adjustments to ensure the layout appears as intended and meets the necessary requirements.

By carefully considering the tax jurisdiction requirements and integrating them into your document layout design, you can help ensure that your invoices and other documents meet legal and regulatory standards while maintaining a professional and consistent appearance for your business communications.

Created with the Standard Edition of HelpNDoc: Free Web Help generator

Report designer - Company logo

The Company logo image "*TRpImage*" is included in all on Document layout files and Debtor statements as well as on Creditor remittance advises. It is basically a place holder over the Company contact information on the Page headers.

Example : Company logo as Image

In this example a company logo may also be added as an image in the layout file. In this example, you do not need to load the

Company info (Setup ribbon).

You need to load your Company logo on the Options screen of Setup → Company info (Setup ribbon). The selected Company logo will print on Document layout files and Debtor statements as well as on Creditor remittance advises.

The company logo, should include the address, telephone number, fax number and e-mail address, since it will replace the text in the Page headers of Document layout files and Debtor statements as well as on Creditor remittance advises.



Company logo - Image sizes

The Image size for the Company logo included on the or TRpImage on most Document layout files (COMPANYDATA.LOGO) and Debtor statements as well as on Creditor remittance advises (COMPANYDATA.BLOBLOGO), is as follows:

		Measurement in Sample logo used in documentation - Draw Style = Stretch		
Size	*Unit*	*Pixels (px)*	*Centimetres (cm)*	*Inches*
Height	*9.5 Twips*	*318 pixels*	*8.41cm*	*3.31 inches*
Width	*4.3 Twips*	*138 pixels*	*3.65 cm*	*1.44 inches*

The following document layout files are set at a different size:

- POSSTARTSP100 (TRN_906183) = 6.906 x 2.434
- Layout file (TRN_1910) = 8.601 x 3.5 = x 0.5734

A twip (abbreviating "twentieth of a point", "twentieth of an inch point", [*Twip - Wikipedia*]

To Front setting

The "*To Front*" setting is a commonly missed setting when new to report manager designer. The details of the Company data (Company name, address, telephone number, fax number and e-mail address) is printed on top of the Company logo. - https://sourceforge.net/p/turbocash/discussion/294751/thread/c51abbe9/?limit=25#aa28 -



Select the image and click To Front



Created with the Standard Edition of HelpNDoc: Revolutionize Your CHM Help File Output with HelpNDoc

Report designer - Add unit descriptions to layout files

The Unit description can be added to document layout files.

Before changing a layout file, it is recommended that you select your report, and click on the Copy report button (on the "Report man" screen). It will create a Copy of your layout file. If you have customised a layout file, save it with a different name. This will prevent loosing your layout file, being over-written by reinstalling or installing osFinancials5/TurboCASH5.

To add the Stock unit description to layout files:

1. Click on the Setup ribbon, select Report designer.

2. Select the document layout file (it is recommended that you edit a copy of the document layout file).

3. Click on the Report menu and select Database connections and datasets.

4. On the Database connections and datasets, click on the Add icon.

5. On the new Dataset screen, enter SUNIT in the Alias Name field.

6. Click on the OK button. The SUNIT data set will be added to the Datasets tab.



7. Select the SUNIT dataset and link it to the DOCUMENTLINE on the Master dataset field.

8. Paste the following sql in the SUNIT sql box:

```
Select * from unit where cast(WUnitid as varchar(10)) = :SUNIT
```

9. Click on the Show data button to test the data. The data as entered in the Stock information - Units tab (Setup ribbon) will be displayed (if the Units is linked to a stock item included in the Preview document).



10. Click on the Close button to exit the Data screen.

11. Click on the OK button of the "*Database connections and datasets*" screen to save the SQL.

12. Select the Detail section of the document lines. To insert the expression, simply drag the "*SUNIT.SDESCRIPTION*" field to the place to be displayed on the layout file.

13. Add the text Unit to the heading for the added expression.



14. Click on the Preview icon to preview the document. The Unit descriptions should be displayed.



15. Close the "Preview" screen and close "*Report man*" screen.

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Reportman - Create new empty reports from Empty report

Create new reports

All reports consists of the three (3) basic sections in the report structure, i.e. Page header, Detail and Page

footer.

You have two (2) options to create a new report, i.e.:

1. Empty report - This is the basic report, with the company dataset included in the Page header and the basic expressions in the Page footer.
2. New report - This is an empty blank report without any datasets. You need to add the COMPANYDATA dataset in the Page header and add the details in the Page footer.

Edit a copy of an existing report - Select a report which is close to your requirements and create a copy of the report. You may then edit the copy of the report.

Create a new empty report

Once you have created a "Copy of Empty.rep", it is recommended that you use the "Copy of Empty.rep" report to add or build your own report or layout files. Do not use the "Empty.rep".

To create a new Empty report:

1. On the Setup ribbon, select Report designer.



2. On the "*Report man*" screen, select the Empty report.
3. Click on the Copy report button.
4. Select Copy of Empty report and click Edit (You may also double-click).

Empty report

The Empty.rep already includes the following:

- Page header - COMPANYDATA Dataset as used in all reports in the "*systemreports*" folder (accessed from the Reports menu).
- Detail - Empty. You need to add a "Main Dataset" define tables and insert the data fields onto the Detail section of the Report Structure.
- Page footer - Company name, Date and timestamp, Path of the Set of Books and user names as well as page numbers.



The COMPANYDATA dataset includes

- Fields
- Dynamic text labels (translatable text via the language files). These translatable labels, are:

Field	*Translatable dynamic text label expression*
Company registration no.	*CUSTOM('GETTEXTLANG',316,'COMPANY REG nr',0,0,0)+': '*
Tax registration number	*CUSTOM('GETTEXTLANG',317,'TAX nr',0,0,0)+': '*
Telephone 1 number	*CUSTOM('GETTEXTLANG',974,'Phone',0,0,0)*
Fax number	*CUSTOM('GETTEXTLANG',189,'Fax',0,0,0)+': '*
Email address	*CUSTOM('GETTEXTLANG',191,'Email',0,0,0)+': '*
Website	*CUSTOM('GETTEXTLANG',3212,'Website',0,0,0)+': '*

You may delete the dynamic text labels (translatable via the language files) and use static text (not translatable via the language files).

For example, if you do not use Fax, Email or a Website, you may simply select and delete that labels and delete them as well as the Company data fields.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Page header - COMPANYDATA

The Data in the Page headers on the "*Empty.rep*" as well as all reports on the Reports menu and User reports menu; except on Document layout files and Debtor statements as well as on Creditor remittance advises, is as follows:



The Company dataset is included the "*Empty.rep*" report. It contains the data entered in the Setup → Company info menu on the Setup ribbon.

If you are choosing the "*New.rep*" report, and need to include some details of your company, you need to add the Company dataset to include the details already included Setup → Company info menu on the Setup ribbon.



Page header Company Data

The Company dataset is included the "*Empty.rep*" report. It contains the data entered in the Setup → Company info option on the Setup ribbon.



The Page header (as on the "*Empty.rep*" consists of the following expressions:

Expression	*SQL*	*Description*
TRpShape0	*Horizontal line*	*Horizontal line*
TRpShape1	*Horizontal line*	*Horizontal line*
TRpExpression0	*COMPANYDATA.SCOMPANYNAME*	
TRpExpression1	*COMPANYDATA.SADDRESS1*	
TRpExpression2	*COMPANYDATA.SADDRESS2*	
TrpExpression3	*COMPANYDATA.SADDRESS3*	
TRpExpression4	*COMPANYDATA.SPOSTCODE*	

TRpExpression5	*CUSTOM('GETTEXTLANG',316,'COMPANY REG nr',0,0,0)+': '*
TRpExpression6	*CUSTOM('GETTEXTLANG',317,'TAX nr',0,0,0)+': '*
TRpExpression7	*COMPANYDATA.SCOMPANYREGNO*
TRpExpression8	*COMPANYDATA.STAXREGNO*
TRpExpression9	*COMPANYDATA.SPHONENUMBER*
TRpExpression10	*CUSTOM('GETTEXTLANG',974,'Phone',0,0,0)*
TRpExpression11	*CUSTOM('GETTEXTLANG',189,'Fax',0,0,0)+': '*
TRpExpression12	*CUSTOM('GETTEXTLANG',191,'Email',0,0,0)+': '*
TRpExpression13	*CUSTOM('GETTEXTLANG',3212,'Website',0,0,0)+': '*
TRpExpression14	*COMPANYDATA.SWEBSITE*
TRpExpression15	*COMPANYDATA.SEMAILADDRESS*
TRpExpression16	*COMPANYDATA.SFAXNUMBER*

COMPANYDATA SQL

The company data SQL consists of two (2) tables (i.e. SYSVARS and SYSVARSEXT) tables in the Database.

To write SQL is actually very simple, for example, "*select data from table*", where data is a valid field name (e.g. ScompanyName Company name) in the table and table is a valid table name (e.g. Sysvars). To call the company name and Fax number (as entered in the Company info (Setup ribbon) screen (it is stored in the sysvars table)), you may simply write:

```
select SCompanyName CompanyName, SFaxNumber Fax from Sysvars
```

The SQL for the COMPANYDATA dataset included in the "*Empty.rep*" is as follows:

SQL Text	*Data on Company info*	
Select a.,*	*Company name*	
SCompanyName ,	*Company registration number*	
SCompanyRegNo ,		
SEmailAddress ,	*E-mail*	
SAddress1 ,	*Address line 1*	
SAddress2 ,	*Address line 2*	
SAddress3 ,	*Address line 3*	
SPostCode ,	*Postal code*	
SPhoneNumber ,	*Telephone number*	
SFaxNumber ,	*Fax number*	
STaxRegNo ,	*Tax registration number*	
BLOBLOGO,	*Company logo (Options tab)*	
SAccountReportName1 ,	*Account group 1*	
SAccountReportName2 ,	*Account group 2*	
SDebtorReportName1 ,	*Debtor group 1*	
SDebtorReportName2 ,	*Debtor group 2*	
SCreditorReportName1 ,	*Creditor group 1*	
SCreditorReportNa	*Creditor group 2*	
	Stock group 1	
	Stock group 2	
	Bank name 1	

SQL Text	Data on Company info	
me2 , SStockReportName 1 , SStockReportName 2 , SBANKNAME1, SBANKNAME2, SBANKNUMBER2, SBANKNUMBER1, SBANKSWIFT1, SBANKIBAN1, SBANKSWIFT2, SBANKIBAN2, SBANKACCOUNT NAME1, SBANKACCOUNT NAME2, SBANKBIC1, SBANKBIC2 from Sysvars , sysvarsext a	Bank name 2 Bank account number 1 Bank account number 2 SWIFT 1 IBAN 1 SWIFT 2 IBAN 2 Bank account name 1 Bank account name 2 BIC 1 BIC 2	SWIFT - (Society for Worldwide Interbank Financial Telecommunication) IBAN - (International Bank Account Number) BIC - (Bank Identifier Code)

The *SYSVARSEXT* table is joined to the SYSVARS table in the COMPANYDATA Dataset.

```
SCONTACTNAME  ContactName,
SMOBILE  MobileNo
from Sysvarsext
```



Click on the Show data button.



Click on the Close icon.

Created with the Standard Edition of HelpNDoc: Transform Your Help Documentation Process with a Help Authoring Tool

Page footer - Information

The Data in the Page footers on the "*Empty.rep*" as well as all reports on the Reports menu and User reports menu; except on Document layout files and Debtor statements as well as on Creditor remittance advises, is as follows:

1. Company name – In the case of multi page reports, where the company details (on Page header) is only printed on the first page of a report.
2. The data path – The full path (location and folders) in which the Set of Books is stored on your system

or network.

3. System user of your Operating system and the osFinancials user / TurboCASH user set in Setup → Access control (Setup ribbon) who printed the report.
4. Date stamp – System date and time the report is printed.
5. Page number and last page number to indicate the expected number of pages.

An example of the page footer, included in the "*Empty.rep*" is as follows:



Add data to Page footers

Select any other report and in the Page footer section of the report, select all the fields (including the Horizontal line).

Select the horizontal line and press the Shift key and while keeping the Shift key down, click on all fields.



The Page footer (as on the "*Empty.rep*" consists of the following expressions:

Expression	*SQL*	*Description*
TRpShape2	*Horizontal line*	*Horizontal line*
TRpExpression17	*COMPANYDATA.SCOMPANYNAME*	*Company name - In the case of multi page reports, where the company details (on Page header) is only printed on the first page of a report.*
TRpExpression19	*CUSTOM('GETTEXTLANG',1296,'Data',0,0,0)+': ' + CUSTOM('GETINFO_BOOKS',1252,'Phone',0,0,0)*	*The data path - The full path (location and folders) in which the Set of Books is stored on your system or network.*
TRpExpression20	*CUSTOM('GETTEXTLANG',906176,'WindowsUser',0,0,0) + ': ' + CUSTOM('GETINFO_WINUSER',2964,'User',0,0,0) +' '+CUSTOM('GETTEXTLANG',906177,'ProgramUser',0,0,0) + ': ' + CUSTOM('GETINFO_USER',2964,'Printed',0,0,0)*	*System user of your Operating system and the osFinancials user / TurboCASH user set in Setup → Access control) who printed the report.*

TrpExpression18	*CUSTOM('GETTEXTLANG',2964,'Printed',0,0,0) +' : ' + FORMATSTR('',now)*	*Date stamp - System date and time when the report is printed.*
TRpExpression21	*+' '+CUSTOM('GETTEXTLANG',1024,'Page',0,0,0)+': ' +Str(M.PAGENUM)+ ' / '*	*Page number and last page number to indicate the expected number of pages.*

You may select the "*Empty.rep*" and copy all the expressions in the Page footer section and paste it in the footer section of your new report.

To copy the expressions to another report:

1. Press the Shift key and use your mouse to click on the Expressions (including the Horizontal line)
2. Select Edit → Copy (Alt+C) or press the (Alt+C) keys.
3. Close the selected report to copy from. Do not save the report.
4. Open the report on which you need to copy (add) the Page footer.
5. Select the Page footer section of your report.
6. Select Edit → Paste (Alt+V) or press the (Alt+V) keys.

You may need to resize the page footer vertically.

Click on the Preview icon to check your report.



Take note of the following important settings relating to page footers and multiple page reports:

Force print setting - The Page footer may print on the first page only. It may not print on the last page or on consecutive pages, if it is a multi-page report.

Two pass report setting - This setting must be selected (ticked) for both, PAGECOUNT and/or SkipToPage settings.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

Reportman - Save reports

Whenever you exit or close a report or a document layout file in the "*Report manager designer*" screen, a confirmation message will be displayed:

"Save report?"

Click on the Yes button.

If you click on No, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Free Web Help generator

Reportman - Create new blank reports from New report

Create a new blank report

All reports consists of the three (3) basic sections in the report structure, i.e. Page header, Detail and Page footer.

You have two (2) options to create a new report, i.e.:

1. Empty report - This is the basic report, with the company dataset included in the Page header and the basic expressions in the Page footer.
2. New report - This is an empty blank report without any datasets. You need to add the COMPANYDATA dataset in the Page header and add the details in the Page footer.

Edit a copy of an existing report - Select a report which is close to your requirements and create a copy of the report. You may then edit the copy of the report.

Create a new blank report

Once you have created a "Copy of New.rep", it is recommended that you use the "Copy of New.rep" report to add or build your own report or layout files. Do not use the "New.rep".

To create a New blank report:

1. On the Setup ribbon, select Report designer.



2. On the "*Report man*" screen, select the New report.
3. Click on the Copy report button.
4. Select Copy of New report and click Edit (You may also double-click).

New report

The new report does not contain the COMPANYDATA dataset. It also contains no data in the Page footer.

It only contains the blank Page header, Detail and Page footer sections of the report structure.



If you intend to use the New report and need to add details of your company, you need to add a new dataset (i.e. COMPANYDATA).

Or you could use the Empty report. The Empty report contains the COMPANYDATA dataset with dynamic text labels (translatable text via the language files).

Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Reportman - Add COMANYDATA Dataset

The process to add the Company dataset and to add the references data fields from the tables to the report, is basically as follows:

1. Add the COMANYDATA Dataset
2. Add the SQL for the Company information to be available in the dataset.
3. Add or drag the fields (columns) from the COMPANY Dataset onto the report.
4. Add labels describing data fields (Expressions) on the report.

In this topic of the documentation, the **A** *Static text - is dealt with to add plain text labels.*

You may add [ab] *Expressions which is translatable labels to reference the language id. This will use the language files to translate the labels the languages are changed (Switch language on the Start ribbon).*

5. Tidy the report - Format expressions and labels, insert a horizontal lines, etc.

Add COMANYDATA Dataset

The company data SQL consists of two (2) tables (i.e. SYSVARS and SYSVARSEXT) tables in the Database.

To write SQL is actually very simple, for example, "*select data from table*", where data is a valid field name (e.g. ScompanyName Company name) in the table and table is a valid table name (e.g. Sysvars). To call the company name and Fax number (as entered in the Setup → Company info (Setup ribbon) screen (it is stored in the sysvars table)), you may simply write:

```
select SCompanyName CompanyName, SFaxNumber Fax from Sysvars.
```

To add the Company Dataset:

1. On the "Report man" screen, select a report. In this example, the "*Copy of New.rep*" is selected.
2. On the "*Report manager designer*" screen for the selected report, click on the Database connections and datasets icon.
3. On the "*Database connections and datasets*" screen, select Datasets tab and click on the Add icon.



4. On the "*New dataset*" screen, Enter "*COMPANYDATA*" as the Alias Name and click Ok.

The next step is to add the SQL for the data in the SYSVARS and the SYSVARSEXT tables.

ADD COMPANYDATA SQL

The next step is to add the SQL for the data in the SYSVARS and the SYSVARSEXT tables. The data as stored in these two tables is mainly added in the Company info (Setup ribbon) and the Reporting groups names as set in the Groups (Setup ribbon).

To add SQL for the Company Dataset:

1. On the Datasets tab select the "*COMPANYDATA*" dataset. The "*COMPANYDATA*" dataset is empty at this stage. You need to copy or add the SQL from the "*SYSVARS*" and "*SYSVARSEXT*" tables.



2. To add the tables, copy or enter the following SQL in the SQL box:

```
Select a.*, SCompanyName ,
SCompanyRegNo ,
SEmailAddress ,
SAddress1 ,
SAddress2 ,
SAddress3 ,
SPostCode ,
SPhoneNumber ,
SFaxNumber ,
STaxRegNo ,
BLOBLOGO,
SAccountReportName1 ,
SAccountReportName2 ,
SDebtorReportName1 ,
```

```
SDebtorReportName2 ,
SCreditorReportName1 ,
SCreditorReportName2 ,
SStockReportName1 ,
SStockReportName2 ,
SBANKNAME1,
SBANKNAME2,
SBANKNUMBER2,
SBANKNUMBER1,
SBANKSWIFT1,
SBANKIBAN1,
SBANKSWIFT2,
SBANKIBAN2,
SBANKACCOUNTNAME1,
SBANKACCOUNTNAME2,
SBANKBIC1,
SBANKBIC2
from Sysvars
, sysvarsext a
```

3. Click on the Show data button. The data should be displayed correctly.



4. Click on the Close icon to close the "*Data*" screen.

5. Click OK on the "*Database connections and datasets*" screen.

> *The next step is to add or drag the data from the SYSVARS and the SYSVARSEXT tables onto the report (Page header as in this example.*

6. If you close the "*Report manager designer*" screen, remember to Save the report.

> *Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).*

Add Expressions (fields from tables)

Once you have added the Company data dataset, the tables of the SYSVARS and SYSVARSEXT will be available.

To print the data from these tables, you need to drag these to the Page header.

To add Expressions from the COMPANYDATA Dataset to the Page header:

1. Click on the Data tab and select the COMPANYDATA Dataset.
2. Click on the "*Detail*" section of the report structure and drag it downwards to add space for the Page header.



3. Select and drag (drag and drop) the data Expressions you wish to display (print) on the Page header section of the report.



When selecting the String Data type the default number of characters (including spaces and Special characters (e.g. the Ampersand & , The Underscore _ , etc. will be counted for a character). This is the field length and the size is indicated with a numeric value in brackets (e.g. (30), etc.). This will by default determine the width of the field when data is dragged and dropped on the section of the report.

4. Drag all the fields from the Company dataset, you need to print on the Report header.

5. Once all required data expressions is added, you may click on the Print preview icon.

On the report there are a lot of different numbers displayed (e.g. Telephone and Fax number as well as the Company registration number).

This may be confusing to the end-user of the report. You may need to add some labels to explain what these numbers mean.

6. Take note of the labels you wish to add to describe the data on the printed report, where necessary.

7. Close the "*Print preview*" screen.

The next step is to add labels, describing the data, to print on the report where necessary.

Add labels to the report

The labels will add a description to the fields (data) printed in the Page header.

There are 2 methods of adding labels to a report:

- Static text - Add plain text labels.
- Expressions - Add translatable expression labels to reference the language id. This will use the language files to translate the labels the languages are changed (Switch language on the Start ribbon).

Add COMPANYDATA Static text labels

All reports and most of the document layout files is translatable via the language files.

The static text labels is used in the "*Tutorial-Invoice*" layout file.

To add static labels to the report:

1. Move and drag the data fields to create some space for the text labels.
2. Select the Text icon to insert static text.
3. Click and drag it to the required size and space on the report (e.g. Page header).



4. On the Label tab, enter the Text you need to display for the field (e.g. Telephone).

5. Repeat the process for all labels.

6. Click on the Print preview icon to view if the labels do not overlap, etc.



7. Take note of the layout and presentation on the "*Print preview*" screen.

8. Close the "*Print preview*" screen and do the necessary changes, if required.

Format text

You may wish to set the Text properties (e.g. Font, font size, bold, italic, etc.) for specific expressions

(fields).

On the Text tab, you may set the alignment, fonts, etc. You may click on the " *WFont Name*" or "*Font Style*" field to set the font properties.



Insert a Simple drawing Horizontal line

To insert a Simple drawing (horizontal line), select the Simple drawing icon.

On the required section, click and draw the length of the shape. By default rectangle shape will be inserted.

On the Shape field, select Horizontal line.



Tidy the Page header - You may need to stretch and move the expressions and labels around, until you are happy with the layout.

You may click on the *Print preview icon and save your report in the available output formats (select Save (Ctrl+S)* *- "Save metafile as" screen). You may open the saved report in your systems default associated program (app) to check how the report will be displayed in the selected file format. For example, if you wish to use the report in a the Html format to display in web browsers, some expressions and labels may not be displayed correctly. You then may need to move or stretch the objects (labels, expressions).*

Transparent setting

If you print the PDF format of your report, the "Transparent" setting, if set to "False", will display a rectangular border around the object (eg Static text, Expression, etc.). You can fix this by setting the "Transparent" setting to "True".

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: News and information about help authoring tools and software

Reportman - Add footer data

The Data in the Page footers on the "*Empty.rep*" as well as all reports on the Reports menu and User reports menu; except on Document layout files and Debtor statements as well as on Creditor remittance advises, is as follows:

1. Company name – In the case of multi page reports, where the company details (on Page header) is only printed on the first page of a report.
2. Data – The full path (location and folders) in which the Set of Books is stored on your system or network.
3. System user of your Operating system and the osFinancials user / TurboCASH user set in Setup → Access control (Setup ribbon) who printed the report.
4. Date stamp – System date and time the report is printed.
5. Page number and last page number to indicate the expected number of pages.

An example of the page footer, included in the "*Empty.rep*" is as follows:



Add data to Page footers

Select the "*Empty.rep*" or any other report and in the Page footer section of the report, select all the fields (including the Horizontal line).

Select the horizontal line and press the Shift key and while keeping the Shift key down, click on all fields.



The Page footer (as on the "*Empty.rep*" consists of the following expressions:

Expression	*SQL*	*Description*
TRpShape2	*Horizontal line*	*Horizontal line*
TRpExpression17	*COMPANYDATA.SCOMPANYNAME*	*Company name – In the case of multi page reports, where the company details (on Page header) is only printed on the first page of a report.*
TRpExpression19	*CUSTOM('GETTEXTLANG',1296,'Data',0,0,0)+': ' + CUSTOM('GETINFO_BOOKS',1252,'Phone',0,0,0)*	*The data path – The full path (location and folders) in which the Set of Books is stored on your system or network.*
TRpExpression20	*CUSTOM('GETTEXTLANG',906176,'WindowsUser',0,0,0) + ': ' + CUSTOM('GETINFO_WINUSER',2964,'User',0,0,0) +' '+CUSTOM('GETTEXTLANG',906177,'ProgramUser',0,0,0) + ': ' + CUSTOM('GETINFO_USER',2964,'Printed',0,0,0)*	*System user of your Operating system and the osFinancials user / TurboCASH user set in Access control) who printed the report.*
TrpExpression18	*CUSTOM('GETTEXTLANG',2964,'Printed',0,0,0) +' : ' + FORMATSTR('',now)*	*Date stamp – System date and time the report is printed.*
TRpExpres	*+' '+CUSTOM('GETTEXTLANG',1024,'Page',0,0,0)+': '*	*Page number and last page number to*

sion21	*+Str(M.PAGENUM)+ ' / '*	*indicate the expected number of pages.*

You may select the "*Empty.rep*" and copy all the expressions in the Page footer section and paste it in the footer section of your new report.

To copy the expressions to another report:

1. Press the Shift key and use your mouse to click on the Expressions (including the Horizontal line)
2. Select Edit → Copy (Alt+C) or press the (Alt+C) keys.
3. Close the selected report to copy from. Do not save the report.
4. Open the report on which you need to copy (add) the Page footer.
5. Select the Page footer section of your report.
6. Select Edit → Paste (Alt+V) or press the (Alt+V) keys.



You may need to resize the page footer vertically.

Click on the Preview icon to check your report.



Take note of the following important settings relating to page footers and multiple page reports:

Force print setting - The Page footer may print on the first page only. It may not print on the last page or on consecutive pages, if it is a multi-page report. You need to set "Force print" to True

Two pass report setting - This setting must be selected (ticked) for both, PAGECOUNT and/or SkipToPage settings.

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Reportman - Print settings

Created with the Standard Edition of HelpNDoc: Experience a User-Friendly Interface with HelpNDoc's Documentation Tool

Reportman - Two pass report setting

The Two pass report setting allows you to preview the first page before all the pages are calculated (e.g. page 1/2, etc.). This is the default setting implemented in reports and document layout files which supports multi-page and subreports in reports and document layout files. This controls the print speed and memory usage (when printing, pages printed are released from memory).

This two pass report setting must be selected (ticked) for both, PAGECOUNT and/or SkipToPage settings.

Your report or document layout file will produce the following message:

> “Two pass report needed-Page setup”

Click OK.

If this error is encountered in the "*Report manager designer*" screen, go to File → Page setup menu and on the Print setup tab, tick the "*Two pass*" report field.



Click OK.

If this error is encountered when printing the report on screen, click on the *"Show report page setup" icon or press the F11 key.*

On the Print setup tab, tick the "Two pass report" field.

Click OK.

Created with the Standard Edition of HelpNDoc: Enhance Your Documentation with HelpNDoc's Advanced Project Analyzer

Reportman - Force print setting

The Page footer may print on the first page only. It may not print on the last page or on consecutive pages, if it is a multi-page report.

If this is the case, the default Force print setting for the Page footer is set to False.

You need to set the Force print setting to True.



Created with the Standard Edition of HelpNDoc: Converting Word Documents to eBooks: A Step-by-Step Guide with HelpNDoc

Reportman - Print-only if data is available

To prevent printing empty reports, you need to set the Report main structure to print the report only when data is available in the "*Report manager designer*" when you edit the report.

If this setting is not set, it will print blank reports.

If there is no data to print, only the Company info in the page header and the data in the Page footer will be printed in most reports.

The "*Main Dataset*" linked to the SubReport in the report "Structure" is by default set to "*False*" when designing reports.



"*P.Only data avail.*" (Print only data available) set to "*True*". If an invalid selection is made on the parameters; or if there is no data in the "*ACCOUNT*" dataset to print, the following error message will be produced:

> "No data available to print!"

If the "*P.Only data avail.*" (Print only data available) set to "*False*", the report will print only the Page headers and Page footers if no data is available on the "*Main Dataset*".

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Reportman - Add content - Detail

If you have created your own reports, from the following templates:

- Empty.rep - This report includes a standardised Page header (COMPANYDATA dataset) and a standardised Page footer. The Detail section of the Report Structure is blank.
- New.rep - This report includes a blank Page header, Detail section and Page footer. The entire report is blank. Need to add the COMPANYDATA dataset in the Page header and add the details in the Page footer.

Whichever template your own new report is based on, the report will not print any data from the active Sets of Books.

You need to add the details (content of the report), which must include a "*Main Dataset*" containing SQL to reference the tables and the fields to be available for the report.

Thereafter, you may select the data fields from the table(s) and drag it onto the report.

REPORT DETAIL

To create a new report from scratch, the debtor listing report will be used to illustrate the basics based on the "*Empty.rep*". This example will also illustrate to add parameters to the report.

To create a new report based on and existing report, the debtor listing report, is used as basis to create a creditor listing report.

Add a New dataset

You need to add the details (content of the report), which must include a "*Main Dataset*" containing SQL to reference the tables and the fields to be available for the report.

To add a new Main Dataset:

1. On the "*Report manager designer*" screen, launch the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu).



2. On the "*Database connections and datasets*" screen, click on the Add+ icon to add a New dataset.

3. Enter i.e. "*ACCOUNT*" and click Ok.



On Datasets tab, you may use the Database browser to view the tables. (The ACCOUNT and DEBTOR tables).

4. On the new Dataset "*ACCOUNT*" type the following Sql:

   "Select * from account"

   This will add all fields (*) in the ACCOUNT table.

   Then add the join from the DEBTOR table.

   "join debtor on account.waccountid = debtor.waccountid"

   The Sql should as follows:

   "Select * from account join debtor on account.waccountid = debtor.waccountid"

5. Click on the Show data button to preview the data tables (Dataset).



Each time you click on the Next and Previous buttons the accounts will be listed from the account id (WACCOUNTID) field.

6. Close the "*Data*" screen.

7. Click OK on the "*Database connections and datasets*" screen.

The next step is to link the ACCOUNT dataset as the Main Dataset to the report.

Link the ACCOUNT Dataset to the SubReport-0

Once you have added the dataset, e.g. ACCOUNT as in this example, you need to link the Dataset to the Main Dataset. You may need to set the dataset to print only if data is available. This will prevent printing blank reports, which may only print the Page header and Page footer.

To link the Dataset to the SubReport:

1. On the report Structure tab, select the SubReport-0.
2. Link the SubReport-0(No Dataset) to the Main Dataset (i.e. "*ACCOUNT*").



3. "*P.Only data avail.*" (Print only data available) set to "*True*".

If an invalid selection is made on the parameters; or if there is no data in the "ACCOUNT" dataset to print, the following error message will be produced:

> "No data available to print!"

If the "P.Only data avail." (Print only data available) set to "False", the report will print only the Page headers and Page footers if no data is available on the "Main Dataset".

The next step is to add the data in the ACCOUNT table to the Detail section of the report.

Add data to the Detail section of the report

Once the Dataset is set and the tables are defined, you may proceed to select the data from the tables you need to print on the report.

To add data from the Main Dataset to the report detail:

1. On the Data tab, expand the ACCOUNT table. Add the data you wish to print.

> *You could drag and drop the fields from the ACCOUNT table onto the Detail section of the report.*



2. Add (drag) all the data fields (expressions), as required onto ("*Detail*" section of the Report structure) the report.

3. Click on the Print preview icon.



4. If data is entered on the relevant fields of the forms (screens), as per this example, the Account code, Account name (description), Telephone 1, Telephone 2, Postal address and Delivery address will be displayed in the Detail section of this report.

> *The sequence, in which the debtor (customer / client) accounts is listed, does not really makes sense on the printed report.*
>
> *The reason for this, is that the accounts is by default sorted according to the record number (id) on the ACCOUNT table.*

> *The next step is to change the default sort order (sequence) to account code or description in which the data in the ACCOUNT table should be listed in the Detail section of the report.*

Set the sequence (order) of the data in the report

By default, the report, will list the data according to the sequence (order) of the account id (WACCOUNTID) as in this example.

To change this, for example, to debtor code or debtor description, you may set the SQL to change the

sequence (order) of the report.

The sequence, in which the debtor (customer / client) accounts is listed, does not really makes sense on the printed report.

At this stage, in the (report design stage), you can set a specific sequence in which the data is displayed, for example account code or description.

You may add the sequence parameter which will add an option to the report options screen. The sequence in which the data on the report is listed can be selected when the report is printed or reprinted.

To set the default Account sequence for the report:

1. On the "*Report manager designer*" screen, launch the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu).
2. On the Datasets tab, select the ACCOUNT dataset.
3. Click the Show data button.



4. Note the Data's number (e.g. WACCOUNTID = 1; SACCOUNTCODE = 2; SMAINACCOUNTCODE =3; SSUBACCOUNTCODE = 4; SDESCRIPTION = 5; etc.).

5. To list the accounts, according to the account name or description, you need to enter the following SQL"

   “Order by 5”

   This will print the report according to the debtor (customer / client) account description.

   To print the report according to the debtor code, you may set the Sql to change the sequence (order) of the report.

   Change the number 5 to 2 in the Sql

   “Order by 2”

   This will print the report according to the debtor code.

5. Close the "*Data*" screen.

6. Click on the OK button of the "*Database connections and datasets*" screen.

7. Click on the Print preview icon. An example of the printed report according to the account description (Order by 5), is as follows:



8. Close the "Print preview" screen.

The next step is to add descriptive headings for the data in the Detail section of the report.

Add headings to the Data on the Details section of the report

From a user's point of view, the data on the report would not make sense.

As per this example, the Account code, Account name (description), Telephone 1, Fax, Postal address and Delivery address will be displayed in the Detail section of this report.

There are 2 methods of adding labels to a report:

- Static text - Add plain text labels.
- Expressions - Add translatable expression labels to reference the language id. This will use the language files to translate the labels the languages are changed (Switch language on the Start

ribbon).

To add static text (labels):

1. Select the "*Detail*" section of the report structure.

2. Select the Text icon to insert static text and drag it to the required space on the report. It will add the "*TrpLabel0*", etc. for each static text field.



3. On the Label tab, replace the "*Text*" with your own, e.g. "*Account code*".

4. Repeat the process for all labels. Once all the static text labels are added, you may need to change the font.

> *To select all the labels you need to format, select a label (e.g. Code); and while keeping the Shift key in; use the mouse to select the rest of the labels for which you wish to change the font properties.*

5. Click on the Text tab or All tab.



6. Select your options to change or set the properties, and click OK on the "*Font*" screen.

7. Click the Preview icon.



8. In the example of this Preview, 2 issues need some attention:

- There is no space between the "*Description / Telephone 1 / Telephone 2*" label and the "*Postal address*" label. The Postal address label and expressions may be moved to the right; or line breaks could be added in the Text label.
- The static text headings is repeated for each account. To solve this by printing these Heading labels on each page once only, you may need to add another Page header and set a Print condition.

PAGE HEADERS

To print the headings only once on the page, you may:

- Stretch the Page header and cut the headings from the Detail section of the report and Paste it on the Page header, or;
- You may add (insert) another Page header and cut the headings from the Detail section of the report and Paste it on the Page header.

For longer reports (multi-page reports), where the Company data only needs to print on the first page and the headings on each page, a new Page header is recommended for the headings.

Add (insert) Page header

To insert another Page header:

1. Select Page header and on the Structure tab, click on the Add icon and select Page header from the list.



2. This will insert a new Page header to the top of the existing Page header (before the Page header containing the information from the COMPANYDATA Data set.

3. On the Structure tab, select the new (blank) Page header and click on the Down arrow to move the section down.



4. Once the blank inserted Page header is moved, you may add the Headings from the Detail section to the new page header.



Add Heading Detail to Page header

If you need to add headings to the Page header section, you may add them manually.

Refer to Add headings to the Data on the Details section of the report in this document.

If you have already added detail in another report section (e.g. Detail section), you may cut and paste the detail (e.g. heading labels) to the new Page header.

To move the Heading Expressions to the Page header:

1. Select the Detail section of the report structure.
2. Select the label e.g. "*Account code*"; and while keeping the Shift key in; use the mouse to select the rest of the labels.



3. Select Edit → Cut (Alt+X) or press the (Alt+X) keys.
4. Select the new Page header section of the report.
5. Select Edit → Paste (Alt+V) or press the (Alt+V) keys.

Add a name for the report

It is recommended to add a name or description to the report.

To add a name for the report:

1. Move the pasted fields a bit down to add a name of your report in the Page header section.
2. Select the Text icon to insert static text and drag it to the required space on the Page header section of the report.
3. On the Label tab, enter "*Debtor list*" in the "*Text*" field.



4. Resize the Page header.
5. You may wish to add (insert) a Simple drawing (horizontal line).
6. Tidy the Detail section
7. Move the fields as required.
8. Resize the Detail section.
9. Click on the Print preview button to check the layout.



10. The layout of the report seems to be fine on a one page report. To test the "*Print preview*" on more than one page, the Company detail on the First header will be printed on each consecutive page.

> *If you do not have enough data to test the multi-page report headers, you may stretch the second Page header or the Detail sections of the report. If it works remember to resize the report sections back.*

Page header - Print company details only on the first page

If the report is printed on more pages than 1 page, the Page headers, will by default be printed on the next pages of the report.

You may set it to print only on the fist page.

To set a print condition for the Page header:

1. Select the Page header (with Company details).
2. On the Data tab, select the Variables Dataset.
3. Check for the M.PAGE setting.



4. On the All tab, select the Print condition and click on the ... icon.
5. On the "*Dialog*" screen, select the "*Category*" - "*Functions*" and select "*M.PAGE*".
6. Click on the Add selection button (or double-click) and type "= *1*" after the "*M.PAGE*" operation. The SQL on the "*Dialog*" should read as follows:

   "M.PAGE=1"

7. If you click on the Show details button, the result should be "*False*".
8. Click Ok on the "*Information*" screen.
9. Click on the Print preview button.
10. The first Page header (Company data) will print on Page 1 only. The second page header will print on page 1 as well as any consecutive pages.

If you do not have enough data to test the multi-page report headers, you may stretch the second Page header or the Detail sections of the report. If it works remember to resize the report sections back.

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Easy CHM and documentation editor

Reportman - Translatable label expressions

TRANSLATIONS OF LABELS VIA THE LANGUAGE FILES

Expressions for translation of text and labels

By default, on the "*Empty.rep*" report, the labels on already automatically translated via the language files.

1. Page header - COMPANYDATA - It contains the data for the Company details, that will print on the Page header of each report (except document layout files. debtor statements and creditor remittance advises).
2. Page footer - Company name, Path of the Set of Books, User names, page numbers and date time stamp.

If you have copied the Page footer from another report, the labels are also automatically translated via the language files.

Labels for reports are added as follows:

1. - This icon will insert a static text label "TRpLabels", which is not translatable via the language files. In the Text tab you need to enter the text to print on the report. The static text labels added in the Detail section of the report structure is not translatable via the language files.
2. - This icon will insert a blank expression "TRpExpression", which by default is "*2+2*". To add a translatable label, you need to add (replace) the basic SQL with the standard SQL as follows:

```
CUSTOM('GETTEXTLANG',1252,'Telephone  1',0,0,0)
```

In this example, to make Telephone 1 translatable, is as follows:

- *1252 = The language id as in the language files.*
- *Telephone 1 = Language description. This description will by default be displayed on the report, if the translation id is invalid.*

You may copy the expression and paste it on your report. You only need to change the language id (number) and description for new labels.

Identify the required labels

You may identify the labels needed from the printed report, or when the report is designed or edited.

On your report, you need to make a list of all the expressions, for which you need to add translatable labels. Most of the required labels can be easily identified in the Expression names (database field names).

As per this example, the labels (static text) needed to translate.

Expression (TRpExpressions) (database fields added)	*Untranslatable labels (Static TRpLabel expressions)*	*Language id*
	Debtor list (report name)	*906045*
ACCOUNT.SACCOUNTCODE	*Code*	*605*
ACCOUNT.SDESCRIPTION	*Description*	*1708*
ACCOUNT.STELEPHONE1	*Telephone 1*	*1252*
ACCOUNT.STELEPHONE2	*Telephone 2*	*1253*
ACCOUNT.SPOSTAL1 *ACCOUNT.SPOSTAL2* *ACCOUNT.SPOSTAL3* *ACCOUNT.SPOSTALCODE*	*Postal address*	*235*
ACCOUNT.SDELIVERY1 *ACCOUNT.SDELIVERY2* *ACCOUNT.SDELIVERY3* *ACCOUNT.SDELIVERYCODE*	*Delivery address*	*199*

Before you start adding translatable expressions using the language files, you need to save your report.

If you are busy to design or edit the report, close the "*Report manager designer*" screen. Remember to Save the report.

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Find labels in the language file

To find labels in the language file:

1. On the Setup ribbon, select Tools → Customise language.



If you type phone the label ID 974 - Phone: includes a colon - This colon is not needed in the label. In this case you may select Telephone or Telephone 1.

2. Search for labels and note the Language id's. As per this example, the labels (static text) needed to translate is noted:

Expression	*Untranslatable labels*	*Language id*
	Debtor list (report name)	*906045*
ACCOUNT.SACCOUNTCODE	*Code*	*605*
ACCOUNT.SDESCRIPTION	*Description*	*1708*
ACCOUNT.STELEPHONE1	*Telephone1*	*1252*

ACCOUNT.STELEPHONE2	*Telephone2*	*1253*
ACCOUNT.SPOSTAL1 *ACCOUNT.SPOSTAL2* *ACCOUNT.SPOSTAL3* *ACCOUNT.SPOSTALCODE*	*Postal address*	*235*
ACCOUNT.SDELIVERY1 *ACCOUNT.SDELIVERY2* *ACCOUNT.SDELIVERY3* *ACCOUNT.SDELIVERYCODE*	*Delivery address*	*199*

3. Close the "*Customise language*" screen.

Add translation expressions to the report

To add the translatable label expressions to the report:

1. On the "*Report man*" screen, select your report.
2. Select the Expression icon to insert a basic expression. The default is "*2+2*"
3. Select the Expression and click on the ... icon of the Expression tab.



4. Add the language SQL to the report, referencing the language id and description.

You may copy the Phone on the Page header expression and its contents "CUSTOM('GETTEXTLANG',974,'Phone',0,0,0)" in the SQL area of the "Dialog" screen.

Simply reference the language id 974 to the new language id and type in the description. For Debtor list (as per this example), the SQL should be;

```
CUSTOM('GETTEXTLANG',906045,'Debtor list',0,0,0)
```

5. Click on the Show Result button.
6. Click Ok on the "*Information*" screen.
7. Click OK on the "*Dialog*" screen.
8. Repeat the process for all labels.
9. Once finished, click on the Print preview icon to check the report.
10. Close the "*Print preview*" screen.
11. Close the "*Report manager designer*" screen. Remember to Save the report.

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Reportman - Auto Expand / Auto Contract setting

If an account is listed, as in this example, and have no data to print (such as telephone numbers, postal address and delivery address details as in this example), it will print blank spaces.

To set the Auto Expand / Auto Contract options for a report:

1. On the "*Report manager designer*" screen, click on the Print preview icon.
2. In this example, identify the section in the Report Structure where the blank spaces is printed.



3. Close the "*Print preview*" screen.

4. Select the Detail section of the Report Structure.

5. Set the "*Auto Expand*" and "*Auto Contract*" to "*True*" (default is "*False*"). This will rid the printed report of the extra unnecessary spaces (lines).

6. Click on the Print preview icon to check if the report prints correctly.



7. Close the "*Print preview*" screen.

8. Close the "*Report manager designer*" screen. Remember to Save the report.

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's Project Analyzer

Parameters (Report options)

Parameters allows specific selections (choices) in how the data is printed and the data that need to be included or excluded from the report.

When creating a parameter, a *Delphi Form* *.dfm parameter file will be created with the same name as your report.

In the Report man screen, the default report icon will change once a parameter is added:

Icon - Before parameters is added



Icon - After parameters is added



Once parameters is added, the report will consist of two (2) files (the report file (*.rep) and the parameter file (*.dfm). If you need to copy a report you need to copy both files.

When you click on the Refresh button, the icon will change in the Report man screen. This indicates that the report consists of two (2) files (for example if parameters is added to the "*Copy of Empty.rep*" report):

- Copy of Empty.rep
- Copy of Empty.dfm

When copy the report to a folder in the File explorer, you need to copy both these files.

When renaming the report in the File explorer, you need to rename both these files with the same name.

In this example, the following parameters is documented:

1. Sort sequences parameters - Allows to change the sequence in which the data is displayed on a report.
2. Lookup parameters - Allows to lookup a specific account or a range of accounts to include in the report.
3. Groups parameters - Allows a list box in to select a group or groups to include in the report.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Creation with a Help Authoring Tool

Parameters - Sort sequences

The report only lists the data according to the Debtor account name (Description).

You may create or add parameters to select the sequence (order) in which the debtor accounts are listed on a printed report.

Currently the new report only consists of a single file (e.g. Copy of Empty.rep) which is a report file.

Remember to make a copy of your report in case something goes wrong.

To add the sequence (sort) parameter:

1. On the "*Report man*" screen, select your report and click on the Parameters button. It will automatically create a *.dfm (Delphi form parameter screen file) (e.g. "*Copy of Empty.dfm*").



2. On the parameters screen for your report, click on the Add button.



3. Select the options as follows:

   a) Type of control - Select IL ComboBox.

b) Size and position - Enter the values for the Left, Width, Top and Height properties to position your parameter.

c) Translation - Click on the ... icon and search for the language label. Select your label (in this example, "*Sequence*" is selected) and click Ok.

d) Column origin – Enter "*SEQ*".

e) SQL section – Enter or copy the following Sql:

```
select 2 Id , 2218 TRN from rdb$database
union
select 5 Id , 178 from rdb$database
```

Select 2 Id is the Account code and 2218 is the language id for Debtor code.

Select 5 Id is the Debtor description and 178 is the language id for Description.

4. Click on the Save and rebuild button. This will position and populate the Sequence ComboBox on the Parameter screen with valid SQL.



5. Click on the Save button to save your parameter and to close exit the parameters screen.

If you do not click on the Save button, your parameter or any changes to the parameter will be discarded (lost).

Preview the parameter

Once the report parameter is added, you may check the layout of the parameter.

To check the Sequence parameter:

1. On the "*Report man*" screen, select your report.



2. Click on the Print preview button. The "*Sequence*" will be listed on the report parameters.



3. The "*Sequence*" parameter will not work at this stage. You need to add and reference the parameter in the report.

Add the Sequence (Order) Parameter to the report

You need to add the following three (3) Sequence parameters

Parameter	*Data type*	*Sets this parameter to*	*Data*	*Description*
SEQ	*String*		*Order id*	*Order id*
SEQTX	*String*		*Order code*	*Debtor code / Description*
SEQTX2	*String Substitute*	*@ORDER*	*Order id*	*Order id*

Add SEQ String parameter

To add the Sequence string parameter to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).

2. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.



3. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.

4. On the "*New param*" screen, enter "*SEQ*".

> *The name if this parameter must be entered exactly as entered in the "Column origin" field for the "Sequence" parameter (i.e. "SEQ") on the parameter design screen.*

5. Click Ok. This will add the parameter.

6. Select the "*SEQ*" parameter.



8. On the "*SEQ*" parameter select and configure the options as follows:

    a) Data type - Select "*String*".

    b) Properties - "*Visible*" and "*Never visible*" as well as "*Allow Nulls*" fields may be ticked. The other options may be left blank.

    c) Description - Enter a description ("*Sequence*" as per this example).

9. You may proceed to add the "SEQ2TX"parameter.

Should you wish to add the next parameter at a later stage, you need to click OK on both the "Parameter definition" as well as the "Database connections and datasets" screens. If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).

Add SEQTX String parameter

To add the Sequence string parameter to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).
2. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.



3. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.
4. On the "*New param*" screen, enter "*SEQTX*".

> *The name if this parameter must be entered exactly as entered in the "Column origin" field for the "Sequence" parameter, followed by TX (i.e. "SEQTX") on the parameter design screen.*

5. Click Ok. This will add the parameter.
6. Select the "*SEQTX*" parameter.



8. On the "*SEQTX*" parameter, select and configure the options as follows:

    a) Data type - Select "*String*".

    b) Properties - "*Visible*" and "*Never visible*" as well as "*Allow Nulls*" fields may be ticked. The other options may be left blank.

    c) Description - Enter a description ("*To account*" as per this example).

9. You may proceed to add the next of "*Sequence*" parameters.

Should you wish to add the next parameter at a later stage, you need to click OK on both the "Parameter definition" as well as the "Database connections and datasets" screens. If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).

Add SEQTX2 String Substitute parameter

To add the Sequence string substitute parameter to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).
2. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.



3. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.
4. On the "*New param*" screen, enter "*SEQTX2*".

> *The name if this parameter must be entered exactly as entered in the "Column origin" field for the "Sequence" parameter, followed by TX (i.e. "SEQTX") on the parameter design screen.*

5. Click Ok. This will add the parameter.
6. Select the "*SEQTX2*" parameter.



8. On the "*SEQTX2*" parameter, select and configure the options as follows:

   a) Data type - Select "*String Substi*" (String substitute).

   b) Properties - "*Visible*" and "*Never visible*" as well as "*Allow Nulls*" fields may be ticked. The other options may be left blank.

   > *The Null value field must not be selected (ticked). If selected (ticked), the following error will be produced:*
   >
   > "ACCOUNT:Could not convert variant of type (Null) into type (OleStr)"

   c) Description - Enter a description ("*Sequence*" as per this example).

   d) Sets this parameter to - Enter "*@ORDER*".

   e) Assign to datasets – Select the "*ACCOUNT*" dataset and click on the > icon.

9. Click OK on the "*Parameter definition*" screen.

Should you wish to add the next parameter at a later stage, you need to click OK on both the "Parameter definition" as well as the "Database connections and datasets" screens. If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).

Add @ORDER Sequence parameter to the Dataset Sql

Refer to the section - Set the sequence (order) of the data in the report – in this document.

On the "*Database and connections datasets*" screen, select the ACCOUNT Dataset and change the

“Order by 5”

to

“Order by @ORDER”

If you click on the Show data button to view the data or on the Print preview icon, at this stage the following error message may be produced:



If the SEQTX2 parameter is not assigned (linked) to the "ACCOUNT" dataset, a similar error message will be displayed:

ACCOUNT:Dynamic SQL Error
SQL error code = -104
Token unknown - line 2, column 1
@

Click OK and check the SEQTX2 parameter and assign (link) to the "ACCOUNT" dataset

The reason for this, is that the Sequence parameter need to be selected on the Report parameter screen.

Click OK and Save the report on exit.

Test the Sequence parameter on the report

Once this is completed, you may need to test if the Sequence parameter works on the report.

On the "*Report man*" screen, select the report and click on the Print preview button.



Report listed by code



On this parameter screen, you may select the sequence (i.e. Debtor code or Description) and click OK. If this parameter works, your data (Debtors) should be listed in different sequences (order).



Report listed by description





Add the Sequence parameter to the report printout

The sequence changes as per your selection on the report parameter. It is a good idea to add the parameter selection on the report printout.

A user will exactly read on the report page headers in which sequence (order) the data is displayed (listed).

Refer to the section - Reportman - Translatable label expressions in this document.

To add the Sequence (Sort) parameter to the report:

1. On the "*Report man*" screen, select your report.
2. Select the Expression icon to insert a basic expression. The default is “2+2”.



3. Replace the Expression “2+2” with a label Description - Sequence: (translatable language id and description).

```
CUSTOM('GETTEXTLANG',247,'Sequence',0,0,0) + ':  '
```

Then add the Variable

```
+ M.SEQTX
```

> *You may type a + and then select the M.SEQTX from the Variables section by clicking on the Add selection button.*

> *NOTE - The M.SEQ, M.SEQTX and M.SEQTX2 variables is automatically added to the Variables category or Dataset when adding parameters.*

The Expression's Sql should then be as follows:

```
CUSTOM('GETTEXTLANG',247,'Sequence',0,0,0) + ':  ' + M.SEQTX
```

Refer to the section - Reportman - Translatable label expressions in this document.

4. Click on the Show Result button. The information should read "*Sequence: Description*".

If the report was printed before using the Debtor code, the information should read "Sequence: Debtor code".

5. Click Ok on the "*Information*" and OK on the "*Dialog*" screens.

6. You may set font properties (e.g. Bold, size, etc.).

7. Click on the Print preview button to preview the report.



8. Exit the report and Save the report.

If you do not click on the Save button, any changes to the report will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's

HTML5 template

Parameters - Move / resize

If you already added a parameter or wish to resize parameters, to align them with other reports, you may wish to resize the layout of the parameter selection fields.

It is a good idea to note the position (i.e. Left and Top), and the size properties (i.e. Length, Width, Height and size) of other report parameters.

To size and position the sequence parameter:

1. On the "*Report man*" screen, select your report and click on the Parameters button.



2. On the parameters screen for your report, click on the "*Sequence*" parameter.



3. Edit the values of the position (i.e. Left and Top), and the size properties (i.e. Length, Width, Height and Size).



4. Click on the Save and rebuild button. This will position and populate the Sequence ComboBox on the Parameter screen with valid SQL.

5. Once you are happy with the new layout, you may proceed to add other new parameters.

Before you exit or close the parameters screen, remember to click on theSave button. If you do not click on the Save button, your parameter or any changes to the parameter will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Parameters - Lookup

Lookup Parameters - FROM ACCOUNT ... TO ACCOUNT

It s recommended that you create a copy of the existing report before adding parameters. If something goes wrong you can revert back to your original report.

In the Report man screen, select your report and click on the Copy report button.

If you already added a parameter or wish to move or resize parameters, to align them with other reports, you may wish to resize the layout of the parameter selection fields.

It is a good idea to note the position (i.e. Left and Top), and the size properties (i.e. Length, Width, Height and size) of other report parameters.

Add lookup parameters

On the copy of your report, click on the Print preview button to print some data on screen.

Click on the Parameters button.

The Lookup parameters will launch the lookup for the selected account type. On the lookup you may select a specific account or a range of accounts to be included in your report.

To do this, you need to create (add) two (2) parameters.

1. From account
2. To account

Once the Lookup parameter is added, you need to add some basic SQL to the report to add the functionality to the report.

In this example, the Debtors lookup will be added.

Add From account parameter

To add the lookup parameters:

1. On the "*Report man*" screen, select your report and click on the Parameters button.



2. On the parameters screen for your report, click on the Add button.



3. Select the options as follows:

    a) Size and position - Enter the values for the Left, Width, Top and Height properties to position your parameter.

    b) Translation - Click on the ... icon and search for the language label. Select your label (in this example, "*From account*" is selected) and click Ok.

4. Click on the Save and rebuild button. This will position the new parameter and add the translation on the Parameter screen.



5. Enter the following options:

   a) Type of control - Select "*OD Lookup Debtors*".

   b) Size and position - Check and edit the values for the Left, Width, Top and Height properties to position your parameter, if necessary.

   c) Column origin - To link the account code, you need to assign a valid column (database field) SACCOUNTCODE.

> *Note the SQL field is not available at this stage.*

6. Click on the Save and rebuild button.

7. Click on the Save button to save your parameter and to close exit the parameters screen.

> *If you do not click on the Save button, your parameter or any changes to the parameter will be*

discarded (lost).

8. Reopen the parameters screen.

9. Click on the "*From account*" parameter. The SQL area will be added to the parameters.



10. Enter the following SQL:

```
“ALL and WAccountTypeid = 1”
```

All needs to be in the UPPERCASE (i.e. “ALL and WAccountTypeid = 1”).

If "All" is in the lower case (i.e. “All and WAccountTypeid = 1”), the lookup will produce the following error:

```
"Dynamic SQL Error
SQL error code = -104
Token unknown - line 3, column 1
```

All"

11. Click on the Save and rebuild button.

12. You may proceed to add the "*To account*" parameter.

If you need to exit the parameters screen at this stage, click on the Save button. If you do not click on the Save button, your parameter or any changes to the parameter will be discarded (lost).

Add To account parameter

To add the lookup parameters:

1. On the parameters screen for your report, click on the Add button.



2. Select and or enter the options for the "*To account*" parameter.



3. Select the options as follows:

   a) Type of control - Select "*OD Lookup Debtors*".

   b) Size and position - Enter the values for the Left, Width, Top and Height and Size properties to position your parameter.

   c) Translation - Click on the ... icon and search for the language label. Select your label (in this example, "*To account*" is selected) and click Ok.

   d) Column origin - To link the account code, you need to assign a valid column (database field) SACCOUNTCODETO.

> *Note the SQL field is not available at this stage.*

4. Click on the Save and rebuild button. This will position the new parameter and add the translation on

the parameter screen.



5. Click on the Save button to save your parameter and to close exit the parameters screen.

> *If you do not click on the Save button, your parameter or any changes to the parameter will be discarded (lost).*

6. Reopen the parameters screen.

7. Click on the "*To account*" parameter. The SQL area will be added to the parameters.



8. Enter the following SQL:

```
“ALL and WAccountTypeid = 1”
```

> *All needs to be in the UPPERCASE (i.e. “ALL and WAccountTypeid = 1”).*
>
> *If "All" is in the lower case (i.e. “All and WAccountTypeid = 1”), the lookup will produce the following error:*
>
> ```
> "Dynamic SQL Error
> SQL error code = -104
> Token unknown - line 3, column 1
> All"
> ```

9. Click on the Save and rebuild button.

10. Click the Save button. This will save and close the report parameter design screen.

If you do not click on the Save button, your parameter or any changes to the parameter will be discarded (lost).

The Parameters are available on the Parameters screen but will not work at this stage.

You need to add the parameters and some SQL to the report.

You will still be able to preview the report at this stage without using the lookup parameters.

Add lookup parameters to reports

Add lookup (From account and To account) parameters to report

You basically need tot add the following parameters to the report parameters:

From account parameters

Parameter	*Data type*	*Sets this parameter to*	*Data*
SACCOUNTCODE	*String*		*Account id*
SACCOUNTCODETX	*String Substitute*	*@SACCOUNTCODETX*	*Account code*

To account parameters

Parameter	*Data type*	*Sets this parameter to*	*Data*
SACCOUNTCODETO	*String*		*Account id*
SACCOUNTCODETOTX	*String Substitute*	*@SACCOUNTCODETOTX*	*Account code*

Add From account (SACCOUNTCODE) String parameter

To add the From account string parameter to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).

2. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.



3. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.

4. On the "*New param*" screen, enter "*SACCOUNTCODE*".

> *The name if this parameter must be entered exactly as entered in the "Column origin" field for the "From account" parameter (i.e. "SACCOUNTCODE") on the parameter design screen.*

5. Click Ok. This will add the parameter.

6. Select the "*SACCOUNTCODE*" parameter.



8. On the "*SACCOUNTCODE*" parameter, select and configure the options as follows:

    a) Data type - Select "*String*".

    b) Properties - "*Visible*" and "*Never visible*" as well as "*Allow Nulls*" fields may be ticked. The other options may be left blank.

    c) Description - Enter a description ("*From account*" as per this example).

9. You may proceed to add the String substitute parameter ("*SACCOUNTCODETX*") for the "*From account*" lookup parameter.

Should you wish to add the next parameter at a later stage, you need to click OK on both the "Parameter definition" as well as the "Database connections and datasets" screens. If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).

Add From account (SACCOUNTCODETX) String Substitute parameter

To add the From account string parameter to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).
2. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.



3. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.
4. On the "*New param*" screen, enter "*SACCOUNTCODETX*".
5. Click Ok. This will add the parameter.
6. Select the "*SACCOUNTCODETX*" parameter.



8. On the "*SACCOUNTCODETX*" parameter, select and configure the options as follows:

    a) Data type - Select "*String Substi*" (String substitute).

    b) Properties - "*Visible*" and "*Never visible*" as well as "*Allow Nulls*" fields may be ticked. The other options may be left blank.

    c) Description - Enter a description ("*From account*" as per this example).

    d) Sets this parameter to - Enter "*@SACCOUNTCODETX*".

    e) Assign to datasets – Select the ACCOUNT dataset and click on the > icon.

9. You may proceed to add the "*To account*" lookup parameters.

Should you wish to add the next parameter at a later stage, you need to click OK on both the "Parameter definition" as well as the "Database connections and datasets" screens. If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be

discarded (lost).

Add To Account (SACCOUNTCODETO) String parameter

To add the To account string parameter to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).
2. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.



3. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.
4. On the "*New param*" screen, enter "*SACCOUNTCODETO*".

> *The name if this parameter must be entered exactly as entered in the "Column origin" field for the "To account" parameter (i.e. "SACCOUNTCODETO") on the parameter design screen.*

5. Click Ok. This will add the parameter.

6. Select the "*SACCOUNTCODETO*" parameter.



8. On the "*SACCOUNTCODETO*" parameter, select and configure the options as follows:

    a) Data type - Select "*String*".

    b) Properties - "*Visible*" and "*Never visible*" as well as "*Allow Nulls*" fields may be ticked. The other options may be left blank.

    c) Description - Enter a description ("*To account*" as per this example).

9. You may proceed to add the String substitute parameter ("*SACCOUNTCODETOTX*") for the "*From account*" lookup parameter.

Should you wish to add the next parameter at a later stage, you need to click OK on both the "Parameter definition" as well as the "Database connections and datasets" screens. If you do not click on the OK button

of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).

Add To account (SACCOUNTCODETX) String Substitute parameter

To add the To account string parameter to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).
2. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.



3. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.
4. On the "*New param*" screen, enter "*SACCOUNTCODETOTX*".

5. Click Ok. This will add the parameter.

6. Select the "*SACCOUNTCODETOTX*" parameter.



8. On the "*SACCOUNTCODETOTX*" parameter, select and configure the options as follows:

    a) Data type - Select "*String Substi*" (String substitute).

    b) Properties - "*Visible*" and "*Never visible*" as well as "*Allow Nulls*" fields may be ticked. The other options may be left blank.

    c) Description - Enter a description ("*To account*" as per this example).

    d) Sets this parameter to - Enter "*@SACCOUNTCODETOTX*".

    e) Assign to datasets – Select the "*ACCOUNT*" dataset and click on the > icon.

9. You may proceed to add the "*To account*" lookup parameters to the report.

Should you wish to add the next parameter at a later stage, you need to click OK on both the "Parameter definition" as well as the "Database connections and datasets" screens. If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).

Add From ... To account lookup parameters SQL to the report

After adding the parameters to the report dataset, you need to add the SQL to the dataset (e.g. "*ACCOUNT*").

1. On the "*Database and connections datasets*" screen (accessed from the first icon or from the Report → Data access configuration menu), click the Parameters button.
2. On the Database connections and datasets screen, select the "*ACCOUNT*" dataset and add the SQL for the Account lookup.

   MSSQL - SQL not supported in Previous documentation before osFinancials5/TurboCASH5

   ```
   “and SAccountcode <= trim(substring('@SACCOUNTCODETOTX ' from 2 for {if mysql}
   if{else}IIF{endif}(position (' ' in '@SACCOUNTCODETOTX ')=0,0,position (' ' in
   '@SACCOUNTCODETOTX ')-1)) )
   and SAccountcode >= trim(substring('@SACCOUNTCODETX ' from 2 for {if mysql}
   if{else}IIF{endif}(position (' ' in '@SACCOUNTCODETX ')=0,0,position (' ' in
   '@SACCOUNTCODETX ')-1)))”
   ```

   To include support for MSSQL Server for the lookup feature, it is recommended that the following SQL is added to the "ACCOUNT" dataset:

   ```
   and SAccountcode <= trim(substring('@SACCOUNTCODETOTX ' {ssfrom} 2 {ssfor} {iif}
   ({pos} (' ' {posin} '@SACCOUNTCODETOTX ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETOTX ')-1)) )
   and SAccountcode >= trim(substring('@SACCOUNTCODETX ' {ssfrom} 2 {ssfor}
   IIF ({pos} (' ' {posin} '@SACCOUNTCODETX ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETX ')-1)))
   ```

3. On the Database connections and datasets screen, select the "*ACCOUNT*" dataset and add the above SQL:



This must be added before the Order by SQL.

"Order by @ORDER"

NOTE - The Show data button will not display any data at this stage. You need to click on the OK button and close (exit) the report.

If you click on the Print preview icon on the Report manager designer screen, the data will also not be available to print. An error message will be displayed:

"No data available to print!"

You need to click on the Print preview button and select the From account ... To Account lookups from the parameter screen and click OK.

4. Click on the OK button of the "*Database connections and datasets*" screen.

If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).

5. Close the report and Save the report.

If you do not click on the Save button, your parameter or any changes to the parameter will be discarded (lost).

Test / Print the new report with the From account and To account parameter

The report should print all accounts From account ... To account (according to your selection on the Parameter screen). If you have selected the same Debtor account in the From account and the same Debtor account in the To account lookup, only the data of the selected Debtor account should be included in the report.

To test and preview the lookup parameters:

1. On the "*Report man*" screen, select your report, and click the Print preview button.



2. Select the accounts to include in the report the From account ... To Account lookup screens.



3. Select the "*Sequence*" (i.e. Debtor code or Description) if not correct.

4. Click on the OK button of the "*Report options*" screen. An example of the printed report, is as follows:



Copy of Empty

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Debtor list **Sequence: Debtor code**

Code	Description / Telephone 1 / Telephone 2	Postal address	Delivery address
1ABGRE	Mr. AB Green (011)314-9997 (011)314-9999	PO Box 1111 Lakeside Johannesburg 2122	Green Street Lakeside Johannesburg 2123
1CASHC	CASH CUSTOMERS		
1DOPEN	Opening Balances - Debtor		
1MACDS	MAC Shop Decor Specialists (011)314-5557 (011)314-5559	PO Box 5555 Morningside Johannesburg 2222	Black Street Morningside Johannesburg 2223
1MDAVI	Mr. Mike Davies (011) 315-1225 (011) 315-1226	P O Box 333 Halfway House 1685	195 AZ Street Eastern Areas Halfway House 1686
1ROGSM	Mr. Roger Smith (011) 310-1677 (011) 310-1678	Plot 539 Boxer Road Glen Austin Ext 3 Midrand 1685	Plot 539 Boxer Road Glen Austin Ext 3 Midrand 1686

You may wish to add the "From account … To account" selection to print on the report (similar to the "Sequence" parameter option).

Add From account … To Account parameters to the printout

The From account and To account parameters allow you to print the report for all debtor accounts, a selected range of Debtor accounts or a specific debtor account as per your selection on the report parameter. It is a good idea to add the parameter selection on the report printout.

A user will exactly read on the report page headers in which which account or accounts are included in the report.

Refer to the section - Reportman - Translatable label expressions in this document.

To add the lookup parameters to the report print:

1. On the "*Report man*" screen, select your report, and click the Edit button (You may also double-click on the selected report).
2. Select the second Page header in the report structure.
3. Select the Expression icon to insert a basic expression. The default expression is "*2+2*".



4. On the Expression tab, click on the … icon to edit the expression.

5. Select the "*Variables*" in the "*Category*" section.

> *These Variables is automatically added when adding parameters Datasets.*
>
> - *From account - M.SACCOUNTCODE and M.SACCOUNTCODETX,*
> - *To account - M.SACCOUNTCODETO and M.SACCOUNTCODETOTX*
> - *Sequence - M.SEQ, M.SEQTX and M.SEQTX2*

6. Remove the default "*2+2*" SQL in the expression.

7. Select the *M.SACCOUNTCODETX* string substitute ("*From account*") parameter and click on the Add selection button (or double-click on the selected operator) to add the operator to the SQL section.

8. Select the *M.SACCOUNTCODETOTX* string substitute ("*To account*") parameter and click on the Add selection button (or double-click on the selected operator) to add the operator to the SQL section.

9. Join these two variables by typing the + ' - '+ after the first variable (This will insert a space and a hyphen followed by a space). The expression should be as follows:

```
M.SACCOUNTCODETX + ' -  '+
M.SACCOUNTCODETOTX
```

10. Click on the Show Result button to check if it is displayed correctly. The "*From account*" and the "*To account*" to will display correctly on the "*Information*" screen according to your previous selection on the Report options.

11. Click Ok on the "*Information*" screen and OK on the "*Dialog*" screen to save the expression.

Add labels for From account ... To Account parameters to the printout

At this stage, only the Account codes will be printed on the report. To describe these codes on the printed report, you need to add labels.

Add labels to the From account and To account expressions:

1. On the "*Report man*" screen, select your report, and click the Edit button (You may also double-click on the selected report).

2. Select the "*M.SACCOUNTCODETX*" expression and click on the Expression tab to edit the expression.

3. On the Expression tab, click on the ... icon to edit the expression.



The required label id's from the Language files were already selected (in the "Translation" field) when the Parameters were designed:

- *From account - SACCOUNTCODE - (translatable language id 246).*
- *To account - SACCOUNTCODETO - (translatable language id 2011).*

4. Add a label From account : (translatable language id 246 and description).
5. Add a label To account : (translatable language id 2011 and description). The completed Sql for the From and To account is as follows:

```
CUSTOM('GETTEXTLANG',246,'From  account',0,0,0)
+ ':  ' +
M.SACCOUNTCODETX + ' -  '+
CUSTOM('GETTEXTLANG',2011,'To',0,0,0)
+ ' :  ' +
M.SACCOUNTCODETOTX
```

6. Click on the Show Result button.

Take note the spaces of the colon on the "Information" screen. From account: (no space) and To : includes a space.

You may decide to add a space after From account : or to remove the space after To :

7. Click OK on the "*Information*" and the "*Dialog*" screens.
8. Click on the Print preview icon to preview the report. The Debtor accounts selected in the report parameters will display your selection on the report printout.



You may wish to :

- *Set font properties (e.g. Bold, size, etc.).*
- *Insert a Horizontal line*
- *Move the Sequence parameter down.*

9. Close the "*Print preview*" screen.
10. Add the necessary touches to tidy the report layout.
11. Click on the Print preview icon to preview the report.



12. Close the "*Print preview*" screen.

13. Close the "*Report manager designer*" screen. Remember to Save the report.

> *Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).*

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Parameters - Groups

You may add a parameter to select and print a list of the debtor (customer / client) accounts which are linked to specific reporting groups only.



To add the Check list box parameter for Reporting group 1:

1. On the "*Report man*" screen, select your report and click on the Parameters button.



2. On the parameters screen for your report, click on the Add button.



3. Select the options as follows:

    a) Type of control - Select "*IC CheckListBox*".

    b) Size and position - Enter the values for the Left, Width, Top and Height properties to position your parameter.

    c) Translation - Click on the ... icon and search for the language label. Select your label (in this example, "*Reporting group 1*" is selected) and click Ok.

4. Click on the Save and rebuild button. This will position an empty CheckListBox on the Parameter screen.



5. Enter the following options:

   a) Column origin - To link the groups, you need to assign a valid column (database field) WREPORTINGGROUP1ID

   b) SQL - Enter "*GROUPS22*". This is the "WTYPEID" for "*Debtor group 1*" in the "*V_TYPES*" table.

> *Note the SQL must be entered in the Plural followed by 22 and entered in UPPERCASE i.e. GROUPS22. If this is not entered correctly, it will not list the "Debtor groups 1", but display "SQL error".*

> *See - Reportman - References - Groups for a list of all Reporting groups in the V_TYPES table.*

6. Click on the Save and rebuild button. This will populate the Reporting group 1 for debtor (customer / client) accounts, if the SQL and the reporting group ID is assigned correctly.

7. Click on the Save button to save your parameter and to close exit the parameters screen.

> *If you do not click on the Save button, your parameter or any changes to the parameter will be discarded (lost).*

Add Groups parameter to the report

Once the Parameter is set on the report options screen, you need to add and define the parameter in the report.

The basic process is as follows:

1. Add a String substitute parameter and assign the parameter to a dataset.
2. On the dataset, you need to add SQL ("*@REPOGROUP1@*") to reference Report group 1.

To add the Check list box parameter for Reporting group 1 to the report:

1. On the "*Report man*" screen, select your report and click on the Edit button. (You may also double-click on your report).



2. Click on the Database connections and datasets icon.
3. Click in the Parameters button.
4. On the "*Parameter definition*" screen, select the "*ACCOUNT*" dataset and click on the Add icon.
5. On the "*New param*" screen, enter "WREPORTINGGROUP1ID".

> *This is the ID to Reporting group 1 as set in the Column origin field of the Parameters. This needs to be entered in the UPPERCASE without any spaces (i.e. WREPORTINGGROUP1ID). If this is not entered correctly, it will display "SQL errors".*

6. Click Ok. This will add the parameter.
7. Select the "WREPORTINGGROUP1ID" parameter.



8. On the "WREPORTINGGROUP1ID" parameter select and configure the options as follows:
    a) Data type - Select "*String Substi.*" (String substitute).

b) Properties - Select (tick) the "*Never visible*" option. The other options may be left blank.

c) Description - Enter a description ("*Reporting group 1*" as per this example).

d) Sets this parameter to - Enter "*@REPOGROUP1@*".

e) Assign to datasets - Assign to the ACCOUNT dataset.

9. Click OK on the "*Parameter definition*" screen.

10. On the "*ACCOUNT*" dataset, enter "*@REPOGROUP1@"* as defined in the "*Sets this parameter to*" field of the "*Parameter definition*" screen.



The "@REPOGROUP1@" in the "ACCOUNTS" must be entered BEFORE the "Order by @ORDER" sort sequence SQL. If entered AFTER the "Order by @ORDER" sort sequence SQL, it will produce a similar SQL error:

"ACCOUNT :Dynamic SQL Error
SQL error code = -104
Token unknown - line 8, column 2
and

11. To verify that this parameter SQL is entered correctly and on the right place, you may click on the Show data button of the "*Database connections and datasets*" screen.

12. Click OK on the "*Database connections and datasets*" screen.

> *If you do not click on the OK button of the "Database connections and datasets" screen, your parameter or any changes to the parameter will be discarded (lost).*

13. Close the "*Report manager designer*" screen. Remember to Save the report.

> *Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).*

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Expressions - Add Account type

The Account type prefix is already implemented on most reports. This will indicate whether it is a debtor, or creditor, or other account types.

The Account type is automatically displayed in the "*From account*" and "*To*" in the report parameters; but it is not displayed in the "*Detail*" section of the report structure for the "*ACCOUNT.SACCOUNTCODE*" expression.

Account type id	*Account type prefix*	*Description*
0	*G*	*General ledger (Balance sheet and Income / Expense accounts)*
1	*D*	*Debtor accounts*
2	*C*	*Creditor accounts*
3	*B*	*Bank accounts*
4	*T*	*Tax accounts*

In the account code field the code expression "*ACCOUNT.SACCOUNTCODE*" excludes the Account type id.



To add the Account type prefix to an Expression:

1. On the "*Report manager designer*" screen, select the Expression and click on the ... icon.



2. On the "*Dialog*" screen, the Database fields for the ACCOUNT contains the ACCOUNT.WACCOUNTTYPEID field. Add the following SQL before the Expression – "*ACCOUNT.SACCOUNTCODE*":

```
IIF(ACCOUNT.WACCOUNTTYPEID=0,'G','')+
IIF(ACCOUNT.WACCOUNTTYPEID=1,'D','')+
IIF(ACCOUNT.WACCOUNTTYPEID=2,'C','')+
IIF(ACCOUNT.WACCOUNTTYPEID=3,'B','')+
IIF(ACCOUNT.WACCOUNTTYPEID=4,'T','')+
```

3. Click on the Show Result button. The Account prefix or account type id is added to the Account code on the "*Information*" screen.

4. Click Ok to exit (close) the "*Information*" screen and OK to save the updated SQL for the Expression.

> *NOTE – ACCOUNT is the Dataset and refers to this report. If you use this SQL on other reports, you may need to check that the correct Dataset is referenced. If the dataset is not correctly referenced, SQL errors will be produced.*

5. Click on the Print preview icon to check the report.



The account type prefix (WACCOUNTTYPEID) is correctly defined and printed in the "Detail" section of the report. It is consistent with the data in From account ... To expression on the Page header section of the report.

6. Close the "*Print preview*" screen.

7. Close the "*Report manager designer*" screen. Remember to Save the report.

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Expressions - Add line break / new line

If you wish to display each label in a single line, two options is available:

1. Create 3 expressions for each label and add these expressions underneath each other.

2. Add a line break "+#10+#13+" after the first label. The second part of the expression (label) will print on a new line.

For example, Description / Telephone1 / Telephone 2 expression is joined by the +' / ' +

```
CUSTOM('GETTEXTLANG',1708,'Description',0,0,0)+' /  ' + CUSTOM('GETTEXTLANG',1252,'Telephone1',0,0,0)
+' /  ' + CUSTOM('GETTEXTLANG',1253,'Telephone2',0,0,0)
```

To insert a line break in an Expression:

1. On the "*Report manager designer*" screen, identify the Expression for which you need to insert a line break.



2. Select the Expression. On the "*Dialog*" screen, you may click on the Show Result button to view how the data should display on printed reports.

3. The SQL on the "*Dialog*" screen, prints the expression in a single line, e.g.

```
CUSTOM('GETTEXTLANG',1708,'Description',0,0,0)+' /  ' +
CUSTOM('GETTEXTLANG',1252,'Telephone1',0,0,0)+' /  ' +
CUSTOM('GETTEXTLANG',1253,'Telephone2',0,0,0)
```

4. To print each label in the expression on a new line, insert the SQL "*#10+#13+*", after each part of the Expression, to force a line break:

```
CUSTOM('GETTEXTLANG',1708,'Description',0,0,0)+' / ' + #10+#13+
CUSTOM('GETTEXTLANG',1252,'Telephone1',0,0,0)+' / ' + #10+#13+
CUSTOM('GETTEXTLANG',1253,'Telephone2',0,0,0)
```



5. On the "*Dialog*" screen, you may click on the Show Result button to view how the data should display on printed reports.

6. Click on the Print preview icon to check the report. If there are not enough space, the label may overlap with the data or other labels in the report.



7. Close the "*Print preview*" screen. To fix this, you may drag the section of the report for example, the "*Detail*" section down to allow the label to print properly.



8. Click on the Print preview icon to check the report.

9. Close the "*Print preview*" screen.

10. Close the "*Report manager designer*" screen. Remember to Save the report.

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Created with the Standard Edition of HelpNDoc: Make Documentation a Breeze with a Help Authoring Tool

Add new report to User reports menu

Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).

Once the report is saved, it is recommended that you check the report.

To do this you may use the Print preview button on the Report man screen.

You may add your own reports to the User reports menu. You may then proceed to print your report(s) from the User reports menu (Reports ribbon).

To add the report to the User reports menu:

1. On the "*Report man*" screen, select your report.



2. Click on the Explorer folder button.



3. In the Explorer folder where your reports are located, select and copy both files (e.g. "*Copy of report.dfm*" and "*Copy of report.rep*") (if parameters were created for the report as in this example).

4. Navigate to the userreports folder in the Explorer folder and create a new folder (e.g. "*My reports*") to add a menu item to User reports menu.

5. Paste the selected files inside your folder (e.g. "*My reports*") inside the .../plugins/reports/userreports folder.



6. Close and restart osFinancials5/TurboCASH5. Open a Set of Books and click on the Reports ribbon.

This will reload the reports.

7. Click on User reports. Your new report will be available and ready to print.



Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's HTML5 template

Rename reports

You may rename a report from the user reports menu, or your own reports.

If a report, which contains parameters, is renamed both the report (*.rep) and parameter (*.dfm) files will be renamed.

All reports which are required to manage the reporting is listed Reports - File structure and should not be deleted or changed.

Do not select any of the standard reports in the Reports menu (stored in the .../plug_ins\reports\systemreports folder). See Reports - System reports - File names should not be deleted or renamed.

To rename a report:

1. On the "*Report man*" screen, select the report you wish to rename.



2. Click twice (2x) on the report. The name of the report is editable. Overtype the report name with your own.



3. Click on the Refresh button.

> *You may rename a report in the Explorer folder.*
>
> *To do this:*
>
> - *Select your report and right-click. On the Explorer folder's context menu, select Rename. You may press the F2 key to rename the report).*
> - *Enter the name of your report.*
>
> *If the report includes a parameter, you may select both report (*.rep) and the parameter (*.dfm) file to rename both files at once.*
>
> *The names for the report and parameter file should be exactly the same.*

> *You may select your new report and click on the Print preview button to check and test your report.*

4. You may exit the report man screen and access your new renamed report from the User reports menu (Reports ribbon).



You may make the report directories and reports translatable via the language files.

See Reports - System reports - File names for a structured list of the file names for folders and reports available in the Reports menu.

To rename folders:

Find translatable language id's in the Tools → Customise language menu (Setup ribbon).

In the Explorer folder rename the Folders with a language file id as TRN_160 for Debtors, TRN_161 for Creditors, etc.

To rename reports:

Select the report you wish to be translatable. Rename both the report (.rep) as well as the parameter (*.dfm) (if parameters is applicable) with the id number prefixed with TRN_ (underscore).*

For example, TRN_906045 for Debtor list, TRN_906046 for Creditor list, etc.

Once you have renamed your folders and/or reports; restart osFinancials5/TurboCASH5 and Open a Set of Books. When you click on the Reports ribbon, the reports menus will be refreshed.

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

Delete reports

You may delete a report from the User reports menu, or your own reports.

If a report, which contains parameters, is deleted both the report (*.rep) and parameter (*.dfm) files will be deleted.

All reports which are required to manage the reporting is listed Reports - File structure and should not be deleted or changed.

Do not select any of the standard reports in the Reports menu (stored in the .../plug_ins\reports\systemreports folder). See Reports - System reports - File names should not be deleted or renamed.

To delete a report:

1. On the "*Report man*" screen, select the report you wish to delete.



2. Click on the Delete button. A confirmation message will be displayed.

"Are you sure?"

3. Only if you are absolutely sure, click Yes to delete the selected report.

Once a report is deleted, the report is lost.

Created with the Standard Edition of HelpNDoc: Make CHM Help File Creation a Breeze with HelpNDoc

Create a new report from an existing report

Create a copy of a report

If you have a report, or find a report that is close to your needs, you may copy the report. You may then use the new copy of the report and change or edit it.

If the selected report includes parameters (report options), you may need to edit the parameters as well.

In this example, the new report "*My Debtor List*" will be used to create the same report for Creditors.

To create a copy of a report:

1. On the "*Report man*" screen, select the report you wish to copy.



2. Click on the Copy report button. An exact copy of the selected report, e.g. "*Copy of My Debtor List*", will be created.



3. Click twice on the "*Copy of My Debtor List*" report and rename the report, e.g. "*My Creditor List*".

> *You may select your new report and click on the Print preview button to check and test your report. It should work exactly as the source report from which it is copied.*

> *You may proceed to edit your copied report.*

Edit the report and parameters

There are two options to edit the copied report:

1. Edit the parameters first and edit the report after the parameters; or
2. First edit the report and then the parameters

In this example the parameters will be edited first and the report last.

The parameters need to be changed from debtors to creditors.

In this example, the report will be printed for debtor (customer / client) accounts. The basic layout and parameters needs to be edited to print the details for creditor (supplier / vendor) accounts. To do this some SQL needs to be changed on some Datasets in the report and on the parameters.

Edit the parameters

In this example, the following parameters needs to edited (changed):

1. Sequence - Edit the list combo box parameter from "*Debtor code*" to "*Creditor code*".
2. Groups - Replace "*Reporting group 1*" list combo box parameter "*Debtor groups 1*" with "*Creditor groups 1*".
3. From account ... To - Change the Account lookups from "*OD Lookup Debtors*" to "*OC lookup creditors*".

To edit the parameters:

1. On the "*Report man*" screen, select the report from which you need to edit the parameters.



2. Click on the Parameters button. This will launch the "*Report options*" parameter screen for the selected report.

Edit the Sequence parameter

Edit the list combo box parameter from "*Debtor code*" to "*Creditor code*".

To edit the Sequence parameter:

1. On the "*Report options*" parameter screen, select the "*Sequence*" parameter.



2. In the Sql section – Change the language id "*Debtor code*" "*2218*" to "*Creditor code*" language id "*2219*". After changing the SQL, the SQL should read as follows:

```
"select 2 Id , 2219  TRN from rdb$database
union
select 5 Id , 178 from rdb$database"
```

3. Click on the Save and rebuild button. This will replace "*Debtor code*" with "*Creditor code*".

4. You could proceed to edit (change) the Reporting group 1 parameters or click Save and reopen the Parameter screen.

Edit the Groups parameter

In this example, the "*Reporting group 1*" parameter needs to be changed from "*Debtor groups 1*" to "*Creditor groups 1*".

To edit the Reporting group 1 parameter:

1. On the "*Report options*" parameter screen, select the "*Reporting group 1*" parameter.



2. In the Sql section – Change the GROUPS22 ("*Debtor group 1*") to GROUPS24 ("*Creditor group 1*"). After changing the SQL, the SQL should read as follows:

```
"GROUPS24"
```

> *22 after GROUPS is the WTYPEID = 22 for Debtor group 1 (SDESCRIPTION). These WTYPEID's is located in the V_TYPES table.*
>
> *Changing this to GROUPS24 will replace and list Creditor group 1.*

> *See - Reportman - References - Groups for a list of all Reporting groups in the V_TYPES table.*

3. Click on the Save and rebuild button. This will replace list of the "*Debtor groups 1*" with "*Creditor groups 1*".
4. You could proceed to edit (change) the Lookup parameters or click Save and reopen the Parameter screen.

Edit the Lookup parameters

In this example, the Account lookups from " *OD Lookup Debtors*" to "*OC lookup creditors*" and Account types in the SQL needs to be changed.

To edit the From account ... To parameters:

1. On the "*Report options*" parameter screen, select the "*From account*" parameter.
2. SQL section – Change the account type id in the SQL from

   "ALL and WAccountTypeid = 1"

   to

   ALL and WAccountTypeid = 2"

   This will only list all the Creditor accounts Account type 2.
3. Select the To account parameter and set the Account type to 2.
4. Type of control – Change the "*OD Lookup Debtors*" to "*OC lookup creditors*" in the To account parameter. Change the Type of control in the From account parameter.



5. Click on the Save and rebuild button.

> *If you have selected the Type of control and click on the Save and rebuild button, before changing the Account types in the SQL section, for both the From account and To account parameters, the SQL section will not be available.*
>
> *You need to click on the Save button.*
>
> *Then you need to click on the Parameters button of the "Report man" screen to set the Account type from 1 to 2.*

6. You should be able to click on the lookup buttons to check if the "Creditors" lookup is launched.



7. Click on the Save button.

You may proceed to edit your copied report.

Edit the report

In this example, the report will be printed for debtor (customer / client) accounts. The basic layout and parameters needs to be edited to print the details for creditor (supplier / vendor) accounts. Once the parameters (report options) is saved, some SQL needs to be changed on some Datasets in the report.

To edit the copy of a report:

1. On the "*Report man*" screen, select the report you wish to edit.



2. Click Edit button. (You may double-click on the selected report (e.g. "*My Creditor List*") report).

3. This will launch the "*Report manager designer*" screen for the selected report.

Edit ACCOUNT Dataset

On the "*ACCOUNT*" Dataset need to replace the debtor table with the creditor table.

To edit the ACCOUNT dataset:

1. On the "*Report manager designer*" screen for the selected report, click on the Database connections and datasets icon.

2. Select the "*ACCOUNT*" dataset.



3. On the Dataset "*ACCOUNT*" you need to replace the debtor table with the creditor table.

   The existing SQL is as follows:

   > "Select * from account join debtor on account.waccountid = debtor.waccountid"

   The changed SQL should be as follows:

   > "Select * from account join creditor on account.waccountid = creditor.waccountid"

4. If you click on the Show data button, the data from the creditor table will be listed.



5. Close the "*Data*" screen.

6. Click OK on the "*Database connections and datasets*" screen.

7. Click on the Print preview icon. The Creditor data is displayed on the report.



If no selection was made, and the Show data button does not show any data, and you click on the Print preview icon (on the "Report manager designer" screen, the following error message will be displayed:

"No data available to print!"

Click OK on the message screen. Exit the report and remember to Save the report.

On the "Report man" screen select your report and click on the Print preview button. Select the options on the parameters screen.

On the "Report man" screen select your report and click on the Edit button. The data should be available to preview.

8. The data of the creditor (supplier / vendor) accounts is displayed on the report. The only change that is required on this report is the report name in the second Page header.

9. To change the Expression for the report name, select the expression and edit the SQL:

   Report name – Debtor list – Expression:

   CUSTOM('GETTEXTLANG',906045,'Debtor list',0,0,0)

Change to – Creditor list – Expression:

```
CUSTOM('GETTEXTLANG',906046,'Creditor list',0,0,0)
```

10. Close the report preview screen.

11. Close the report. Remember to Save the report.

> *Whenever you close the "Report manager designer" screen, after editing your report, remember save the report. If you click on No, on the "Save report?" confirmation message, your changes will be discarded (lost).*

Test the report and parameters

The final stage is to test the parameters to check if it works correctly and to check the general layout of the printed report.

To test the print preview of the report:

1. On the "*Report man*" screen, select the report you wish to test.



2. Click on the Print preview button. The report options (parameters) is displayed:



3. Select the options:

   a) From account … To account - This will launch the Creditors lookup. Select the creditor customer (supplier / vendor) (account(s) to include in the report.



   b) Sequence - Select "*Creditor code*" or "*Description*".

c) Reporting group 1 - Leave blank to list all accounts. You may tick a specific group or groups on the list in Reporting group 1 list box to print only those accounts linked to the specific reporting group.

4. Click OK. An example of the printed report is as follows:


My Creditor List

Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: osfinancials1@gmail.com
Website: osfinancials.org/en/

Creditor list

From account: C2ABCOS - To: C2SUNSU **Sequence: Description**

Code	Description / Telephone 1 / Telephone 2	Postal address	Delivery address
C2AONES	A-ONE Suppliers (011) 838-9221 (011) 838-9223	P O Box 31318 Marshalltown Johannesburg 2000	Austin Street Marshalltown Johannesburg 2001
C2ABCOS	ABC-Office-Supplies (011)312-9997 (011)312-9999	PO Box 8888 Lakeview Johannesburg 2012	Lake Street 444 Lakeview Johannesburg 2013
C2ABCSC	ABC-Service-Centre (011)313-9997 (011)313-9999	PO Box 9999 Lakeside Johannesburg 2122	Metro Building Lake Street Lakeside 2123
C2BESTS	BEST Suppliers (011) 310-3110 (011) 310-3111	P O Box 45532 Halfway House 1685	Best Street Halfway House 1686
C2COPEN	Opening balances - Creditor		
C2SUNSU	SUNDRY SUPPLIERS		

5. Close the "*Print preview*" of the report and close the report options screen.

You may proceed to print the report from the User reports menu (Reports ribbon).

Check the report in PDF format

Once you are satisfied that your report is displayed correctly in the printed format, you may check the layout and presentation in PDF format. Should you wish to make any changes, you may edit the report.

To check the report in PDF format:

On the Report options screen, select the "*Open in PDF*" option.



Select the options to include in the report and click OK. The report will be opened in your system's default PDF-program (In this example, it is "*Microsoft Edge*"):



Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Reportman - References - Data structure

Visual Query Editor

Good SQL queries can be much easier with a visual editor. You may download the FlySpeed Query

software (free version (supports only a single database) or purchase a version which supports multiple databases) from:

http://www.activedbsoft.com/overview-querytool.html

With this tool you may connect to the database of a Set of Books. To do this, select the Firebird or Interbase driver and then select the books.fdb database file.

Once you connect to the database, all tables for the selected Set of Books will be listed – i.e. Queries, Tables, System Tables and Views.

Access Error: – "The process cannot access the file because it is being used by another process." This usually means that you are accessing or connecting a Set of Books that is already opened.

To resolve this – close the Set of Books in osFinancials5/TurboCASH5.

Data structure - Accounts

The definitions of a ledger, debtor of creditor accounts are contained in the Account table. The links to other tables are outlined briefly as follows:

Table	*Key*	*Keys to other tables*	*Remarks*
ACCOUNT	*WACCOUNTID*	*WREPORTINGGROUP1ID = GROUPS.WGROUPID WREPORTINGGROUP2ID = GROUPS.WGROUPID*	*All accounts (i.e. Debtors=1, Creditors=2, Tax=4, Bank=3 and Ledger=0)*
DEBTOR	*WACCOUNTID*	*WACCOUNTID = ACCOUNT.WACCOUNTID*	*The information and settings of debtors.*
CREDITOR	*WACCOUNTID*	*WACCOUNTID = ACCOUNT.WACCOUNTID*	*The information and settings of creditors.*
TAX	*WACCOUNTID*	*WACCOUNTID = ACCOUNT.WACCOUNTID*	*Tax percentage and info of linked Tax accounts (VAT/GST/Sales Tax).*
BANK	*WACCOUNTID*	*WACCOUNTID = ACCOUNT.WACCOUNTID*	*The Payments and Receipt batch id linked to the Bank accounts.* *Should you set the bank reconciliation method to activate*

		WRECEIPTSID = BATTYPES.WBATCHTYPEID *WPAYMENTSID = BATTYPES.WBATCHTYPEID*	*the Dutch Bank method, then the BANK.WRECEIPTSID is the same as the BANK. WPAYMENTSID.*
GROUPS	*WGROUPID*		*Groups are used to link accounts and to structure the reports. Accounts must be lined to Account Group1 and/or Account group2. These Account groups are then linked to Financial categories. This will enable you to create and print reports using groups.* *See - Reportman - References - Groups for a list of all Reporting groups in the V_TYPES table.*
BATTYPES	*WBATCHTYPEID*		*This table contains the values for the settings of each batch.*



Data structure - Stock (Inventory)

The Stock data contains links to the Account table. This links the Sales, Cost of Sales, Stock Control, Input Tax, Output Tax, default Supplier1 and default Supplier2 AccountID to the stock items.

Table	*Key*	*Keys to other tables*	*Remarks*
STOCK	*WSTOCKID*	*WREPORTINGGROUP1ID = GROUPS.WGROUPID* *WREPORTINGGROUP2ID = GROUPS.WGROUPID* *WUNITID = UNIIT.WUNITID* *WCOSTACCOUNTID = ACCOUNT.WACCOUNTID* *WSALESACCOUNTID = ACCOUNT.WACCOUNTID* *WSTOCKACCOUNTID = ACCOUNT.WACCOUNTID* *WINPUTTAXID = ACCOUNT.WACCOUNTID* *WSUPPLIER1ID = ACCOUNT.WACCOUNTID* *WSUPPLIER2ID = ACCOUNT.WACCOUNTID*	*The Stock table are used to select the stock items (products or services) when creating or editing documents.*
STOCK_DESCRIPTIONS	*WSTOCKID, WLANGUAGEID*	*WSTOCKID =STOCK.WSTOCKID* *WLANGUAGEID = GROUPS.WGROUPID*	*Different languages for one stock item (product).*



Data structure - Financial

All transactions are recorded on accounts. These updated data are contained in 2 tables (i.e. 1 for all details and 1 for all totals).

The budget figures for ledger accounts are also contained in the Totals table.

Table	*Key*	*Keys to other tables*	*Remarks*
TOTALS	*WACCOUNTID, WPERIODID, BACTUAL*	*WACCOUNTID = ACCOUNT.WACCOUNTID WPERIODID = PERIODS.WPERIODID*	*All totals of accounts per period. Also contains Budget figures (BACTUAL = 0)*
PERIODS	*WYEARID, WPERIODID*	*WYEARID = YEARS.WYEARID*	*Information for the periods. Year 1 period -1 = Opening Balances previous year. Year 1 period 1 until and including 13 = Period balances previous year. Year 2 period 0 = Opening balances this year (current year). Year 2 period 14 until and including 26 - Period balances this year (current year)*

TRANSACT	*WTRANSACTIONID*	*WBATCHID = BATCON.WBATCHID* *WBATCHTYPEID = BATTYPES.WBATCHTYPEID* *WACCOUNTID = ACCOUNT.WACCOUNTID* *WPERIODID =PERIODS.WPERIODID* *WYEARID = YEARS.WYEARID* *WTAXACCOUNTID = ACCOUNT.WACCOUNTID* *WDESCRIPTIONID = MESSAGES.WMESSAGEID* *WREPORTINGGROUP1ID = GROUPS.WGROUPID* *WREPORTINGGROUP2ID = GROUPS.WGROUPID* *WDOCID =DOCHEAD.WDOCID*	*Transactions at detail level. In this table, all individual transactions booking is listed.* *It will display the debit as well as the credit bookings.*
YEARS	*WYEARID*		*Different years in osFinancials*
BATCON	*WBATCHID*	*WBATCHTYPEID = BATTYPES.WBATCHTYPEID*	*For each processing of a transactions (in a journal or a document) an unique number (processing number) is generated. This number is used in the Transaction table to record and group the balances of the processed transactions.*



Data structure - Text

The text in the transaction and in the documents tables (dochead en docline) are contained in one table.

This allows you to reuse the text in the text fields. This reduces the number of similar text to be repeated in the database. It also reduces the size of the database.

The disadvantage of this is that you first need to identify the message id (number) before you can see the actual description or message. For example, if you view the Transact table, you will notice a number in the WDESCRIPTIONID column which refers to the Messages table. In the Message table, you will find the text displayed in the fields of the interface screens or fields on the reports.

The same linking is used in the DOCHEAD and DOCLINE tables.

Table	*Key*	*Keys to other tables*	*Remarks*
MESSAGES	*WMESSAGEID*		*Text of transaction descriptions in the dochead and docline tables.*

Data structure - Documents

The data structure of documents (invoices, credit notes, quotes, purchases, supplier returns and orders) are located in the DOCHEAD table. The DOCLINE table contains the transaction or comment detail in lines of stock items as selected or as comments added to documents. The details of the Stock Items are located in the STOCK table.

Table	*Key*	*Keys to other tables*	*Remarks*
DOCHEAD	*WDOCID*	*WTYPEID = TYPES.WTYPEID* *WACCOUNTID = ACCOUNT.WACCOUNTID* *WPOSTAL1ID = MESSAGES.WMESSAGEID* *WPOSTAL2ID = MESSAGES.WMESSAGEID* *WPOSTAL3ID = MESSAGES.WMESSAGEID* *WPOSCOUNTRIES_ID = COUNTRIES.COUNTRIES_ID* *WPOSTALCODEID = MESSAGES.WMESSAGEID* *WMESSAGE1ID = MESSAGES.WMESSAGEID* *WMESSAGE2ID = MESSAGES.WMESSAGEID*	*The dochead table contains the information of the document header fields / lines. Most of this text is located in the messages table. The values of the WTYPEID are as follows:* *10 = Invoice* *11 = Credit note* *12 = Purchase* *13 = Supplier return* *14 = Quote*

		WMESSAGE3ID = MESSAGES.WMESSAGEID *WSALESMANID = GROUPS.WGROUPID* *WDELADDRESS1ID = MESSAGES.WMESSAGEID* *WDELADDRESS2ID = MESSAGES.WMESSAGEID* *WDELADDRESS3ID = MESSAGES.WMESSAGEID* *WDELCOUNTRIES_ID = COUNTRIES.COUNTRIES_ID* *WDELCODEID = MESSAGES.WMESSAGEID* *WREPORTINGGROUP1ID = GROUPS.WGROUPID* *WREPORTINGGROUP2ID = GROUPS.WGROUPID* *WUSERID = USERS.WUSERID*	*15 = Order* *16 = Manual - Adjustments (via Stock)*
DOCLINE	*WDOCID,* *WDOCLINEID*	*WDOCID = DOCHEAD.WDOCID* *WSTOCKID =STOCK.WSTOCKID* *WLINETYPEID = TYPES.WTYPEID* *WDESCRIPTIONID = MESSAGES.WMESSAGEID* *WTAXID = ACCOUNT.WACCOUNTID* *WACCOUNTID = ACCOUNT.WACCOUNTID*	*The docline table contains the transaction details (document lines / rows). These may include comment lines.* *Wlinetypeid may include the following values:* *90 = Stock item - Excl.* *91 = Comments* *93 = Payment* *94 = Stock item - Incl.* *If the Waccountid contains values, these accounts were selected using the Accounts lookup for the Financial entry (Stock item type). Updating the ledger for this stock item type will not the standard contra account of the document.*
DOCLINEOPTIONS	*WDOCLINEOPTIONSID*	*WDOCID = DOCLINE.WDOCID* *WLINEID = DOCLINE.WDOCLINEID* *WITEMOPTIONVALUE1ID = ITEMOPTIONSVALUES.WITEMOPTIONVALUEID* *WITEMOPTIONVALUE2ID = ITEMOPTIONSVALUES.WITEMOPTIONVALUEID* *WITEMOPTIONVALUE3ID =*	*The details of Options (Stock item type) is located in this table.*

		ITEMOPTIONSVALUES.WITEMOPTIONVALUEID *WITEMOPTIONVALUE4ID = ITEMOPTIONSVALUES.WITEMOPTIONVALUEID* *WITEMOPTIONVALUE5ID = ITEMOPTIONSVALUES.WITEMOPTIONVALUEID* *WDESCRIPTIONID = MESSAGES.WMESSAGEID*	
STOCK	*WSTOCKID*	*STOCK.WREPORTINGGROUP1ID = GROUPS.WGROUPID* *STOCK.WREPORTINGGROUP2ID = GROUPS.WGROUPID* *WCOSTACCOUNTID = ACCOUNT.WACCOUNTID* *WSALESACCOUNTID = ACCOUNT.WACCOUNTID* *WSTOCKACCOUNTID = ACCOUNT.WACCOUNTID* *WINPUTTAXID = ACCOUNT.WACCOUNTID* *WSUPPLIER1ID = ACCOUNT.WACCOUNTID* *WSUPPLIER2ID = ACCOUNT.WACCOUNTID*	*Stock group 1* *Stock group 2* *Cost of sales account* *Sales account* *Stock control account* *Default Tax account* *Default Supplier account 1* *Default Supplier account 2*



Created with the Standard Edition of HelpNDoc: Easy EBook and documentation generator

Reportman - References - Groups

Reporting groups 1 and Reporting groups 2 (for Accounts, Debtors, Creditors, Stock, Documents and Cost centres) is added in Groups on the Setup ribbon. Salespersons, payment types, Projects and Languages is also added in Groups on the Setup ribbon.



Each of these groups contains a WTYPEID and a SDESCRIPTION in the V_TYPES table.

These WTYPEID in the V_TYPES table were used to add Reporting group 1 to the Parameters (Report options).

WTYPEID (V_TYPES table)	*Description*
20	*Account group 1*
21	*Account group 2*
22	*Debtor group 1*
23	*Debtor group 2*
24	*Creditor group 1*

25	*Creditor group 2*
26	*Stock group 1*
27	*Stock group 2*
28	*Document group 1*
29	*Document group 2*
30	*Payment types*
31	*Salesperson*
1000	*Projects*
1002	*Cost centre 1*
1003	*Cost centre 2*
1004	*Language*

For example, to reference these Groups in the V_TYPES table, you need to add "GROUPS22"

Note this must be Entered in the Plural followed by 22 and entered in UPPERCASE i.e. GROUPS22. If this is not entered correctly, it will not list the Debtor groups, but display "SQL error".

In the SQL Browser, you may view the Groups in the TYPES table. Groups are set as 2 in the WTYPEPARENT column



Created with the Standard Edition of HelpNDoc: Write eBooks for the Kindle

Reportman - SQL Changelog for MSSQL

From ... To account lookup parameters SQL to Dataset

MSSQL - SQL not supported in Previous documentation before osFinancials5/TurboCASH5

```
“and SAccountcode <= trim(substring('@SACCOUNTCODETOTX ' from 2 for {if mysql}if{else}
IIF{endif}(position (' ' in '@SACCOUNTCODETOTX ')=0,0,position (' ' in '@SACCOUNTCODETOTX
')-1)) )
and SAccountcode >= trim(substring('@SACCOUNTCODETX ' from 2 for  {if mysql}if{else}
IIF{endif}(position (' ' in '@SACCOUNTCODETX ')=0,0,position (' ' in '@SACCOUNTCODETX ')-
1)))”
```

To include support for MSSQL Server for the lookup feature, it is recommended that the following SQL is added to the "*ACCOUNT*" dataset:

```
and SAccountcode <= trim(substring('@SACCOUNTCODETOTX ' {ssfrom} 2 {ssfor} {iif}
({pos} (' ' {posin} '@SACCOUNTCODETOTX ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETOTX ')-1)) )
and SAccountcode >= trim(substring('@SACCOUNTCODETX ' {ssfrom} 2 {ssfor}
IIF ({pos} (' ' {posin} '@SACCOUNTCODETX ')=0,0,{pos} (' ' {posin} '@SACCOUNTCODETX ')-1)))
```

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Multi-currency

In osFinancials5/TurboCASH5, users have the capability to engage in international transactions, purchasing goods from foreign suppliers and selling goods to customers in foreign countries. osFinancials5/TurboCASH5 allows users to process and print documents in foreign currencies. However, before they can do so, it is necessary to add and/or update the currencies in the Set of Books.

The Currencies feature in osFinancials5/TurboCASH5 is particularly beneficial for businesses dealing with international transactions, streamlining financial processes for processing and printing sales documents and purchase documents in various currencies.

Currencies functionality overview

Here's a breakdown of the functionalities:

1. Add / Edit / Delete Currencies: osFinancials5/TurboCASH5 allows users to manage a list of currencies. You may add new currencies, edit existing ones (e.g., update exchange rates), and also remove currencies that are no longer needed.
2. Processing Multi-currency Documents: Once the currencies is added and or updated, users can select the currency applicable to their debtors (customers/clients) when processing sales documents such as invoices, credit notes, and quotes. When processing purchase documents such as purchases, supplier returns, and orders, users can select or specify the currency applicable to their for creditors (suppliers / vendors).
3. Printing Currency in Document Layouts: Once a currency is selected for a specific document, osFinancials5/TurboCASH5 incorporates this information into the document layout files. This means that the selected currency will be visibly printed on the documents, ensuring clarity and transparency in financial transactions.
4. Printing a List of Currencies in Reports: You may print a "*Currencies - Listing*" report in the Reports → Currencies menu.

Overall, this currency management and multi-currency document handling feature set are valuable for businesses and organizations that deal with international transactions and need to manage financial records in different currencies. It streamlines the process, ensures accuracy, and facilitates transparency in financial dealings.

osFinancials supports a wide range of currencies, with a total of 180 available currency rates. As these currency rates can fluctuate daily, and sometimes even hourly, users must ensure they regularly update and maintain their currency list before processing any documents. This ensures that accurate exchange rates are used when dealing with foreign currencies on sales documents (invoices, credit notes, and quotes) or purchase documents (purchases, supplier returns, and orders).

To account for gains and losses that may arise due to currency rate fluctuations, users are advised to create a specific account called "Currencies - Gains / Loss account" in the Chart of Accounts (Setup → Accounts menu on the Setup ribbon). This account will be used to record the financial transactions related to currency rate fluctuations.

However, it's essential for users to consult their country's tax legislation and any other relevant regulations before engaging in international transactions and handling foreign currencies. This is to ensure compliance with all legal requirements and to understand any specific rules or guidelines that may apply to their particular business and location.

Overall, osFinancials5/TurboCASH5 offers a comprehensive solution for businesses involved in international trade, allowing them to seamlessly process transactions in foreign currencies, keep track of currency rate fluctuations, and accurately record gains and losses through the designated account. It's crucial for users to stay updated on currency rates and comply with applicable regulations to manage their international financial activities effectively.

Add multi-currencies

To add currencies:

1. On the Setup ribbon, select Setup → Currencies.



2. Click on the add icon to create a new record.

3. Enter the description, currency symbol and currency rate.

> *Alt Code Shortcuts for Currency Symbols - Example Works if the Alt+0165 for the Japanese Yen, etc.*

4. Click on the save icon.

> *A currency rate larger than the base currency rate = 1, should translate to a gain on foreign currency.*
>
> *A currency rate smaller than the base currency rate = 1, should translate to a loss on foreign currency.*
>
> *Currency rates supports all the necessary number of decimal digits.*
>
> *In this example, only 1 decimal symbol is used for illustrative purposes.*

> *You may print a report for the currencies on the Reports → Currencies menu (Reports ribbon)*

Delete currencies

To delete the currencies, select the currency and click on the *icon. A confirmation message will be displayed:*

> Delete record?

Click on OK to remove the selected currency.

The base currency "No. 0 - Default " cannot be deleted.

Process multi-currency documents

1. Create an Invoice as usual.

2. Select the Currency.



Once documents (e.g. Invoices are updated (posted to the ledger), you cannot change the currency rate.

You need to make sure that the documents are printed at the correct currency rate before you post (update) the documents to the ledger.

An example, where the Invoice document layout file is printed in the default base currency e.g. ZAR = 1, the amounts will be displayed similar to a normal invoice printed with the base currency or in Set of Books with no currency:



At the bottom of the document layout files,a time stamp (Date and time) indicates when the document is printed or reprinted.

Invoice example printed in USD $

An example, where the Invoice document layout file is printed in the USD currency which is higher than the base currency e.g. ZAR = 1 and USD = 11 for illustration purposes, the amounts and $ currency symbol will be displayed. The normal selling price is calculated with the currency rate as entered (or edited) in the Setup → Currencies (Setup ribbon):



Invoice example printed in Euro €

An example, where the Invoice document layout file is printed in the USD currency which is higher than the base currency e.g. ZAR = 1 and Euro = 0.9, for illustration purposes, the amounts and € currency symbol will be displayed. The normal selling price is calculated with the currency rate as entered (or edited) in the Setup → Currencies (Setup ribbon):



Receiving payment

The payment from a different country may differ from the original invoice (e.g. Invoice 1265.00 and payment received 1300.00) due to currency fluctuations.

In this example, the transaction for the payment received is recorded to the Currencies - Gains / Loss account.





Allocate payment received to the debtor (customer / client) account



The amount received in the bank account, is 1300.00 and the debtor invoice is 1150.00. The outstanding debtors amount for the receipt need to be transferred (allocated) to the debtor (customer / client) account.



Transactions in Currencies - Gains / Loss account



Created with the Standard Edition of HelpNDoc: Effortlessly Create Encrypted, Password-Protected PDFs

Cost centres

Introduction to Cost Centres

osFinancials5/TurboCASH5 provides support for up to two cost centre groups, allowing you to effectively organize and analyse your financial data based on cost centres within your organization.

With the capability to define and assign cost centre groups in osFinancials5/TurboCASH5, you can categorize your expenses, revenues, and other financial transactions according to different cost centres. This enables you to track and analyse the financial performance of specific departments, projects, locations, or any other divisions within your organization.

By assigning transactions to appropriate cost centres, you can generate reports and statements that provide detailed insights into the financial activities and performance of each cost centre group. This information can be valuable for budgeting, decision-making, and evaluating the profitability or efficiency of different areas within your organization.

Whether you need to allocate costs, track expenses, or analyse financial data across multiple cost centres, osFinancials' support for up to two cost centre groups provides you with the flexibility and capability to effectively manage and analyse your organization's financial information.

The use of Cost centres is optional. By default cost centres are not activated.

Budget and Transactions in this Example

To check and illustrate the use of Cost centres in osFinancials5/TurboCASH5, the budget figures and transactions are based on the following Sets of Books "bin/Tutorials/COST-CENTRES:

1. COST-CENTRES-A - Unposted transactions in batches and documents.
2. COST-CENTRES-B - Posted transactions in batches and documents.

For your convenience, the budget figures, transactions in batches, purchase documents and sales documents are listed.

Budget figures

In this example, the entire budget is allocated split and allocated into the 2 Cost centres (added in "*Cost centre 1*" group), e.g. "*Cost centre A1*" and "*Cost centre B1*".

Total Budget				*Cost centre A1*		*Cost centre B1*	
Account Allocation	*Description*	*Annual*	*Monthly*	*Annual*	*Monthly*	*Annual*	*Monthly*
010-000	*Sales*	*-180 000*	*-15 000*	*-120 000*	*-10 000*	*-60 000*	*-5 000*
100-000	*Cost of sales*	*60 000*	*5 000*	*60 000*	*5 000*		
GROSS PROFIT		*120 000*	*10 000*	*-60 000*	*-5 000*	*-60 000*	*-5 000*
200-000	*Bank charges*	*600*	*50*	*600*	*50*		
210-010	*Fuel & oil*	*1 200*	*100*	*1 200*	*100*		
210-020	*Maintenance*	*2 400*	*200*	*2 400*	*200*		
210-030	*Repairs*	*1 200*	*100*	*1 200*	*100*		
220-000	*Rent*	*6 000*	*500*	*2 400*	*200*	*3 600*	*300*
225-000	*Salaries and wages*	*7 200*	*600*	*3 600*	*300*	*3 600*	*300*
TOTAL EXPENSES		*18 600*	*1 550*	*11 400*	*950*	*7 200*	*500*
NET PROFIT		*-101 400*	*-8 450*	*-48 600*	*-4 050*	*-52 800*	*-4 400*

Posted Transactions in Batches

For the purposes of this illustration, the following 3 payments were made, and allocated to cost centres (in the ABC-Payments batch) as follows:

Ref. no.	Date	Description	Account	Cost centre 1	Tax	Dr
105	2024/03/30	Petrol - Bakkie	Fuel & Oil	Cost centre A1	No tax	120,00
106	2024/03/30	Rent March 2024	Rent	Cost centre A1	Input Tax- 15%	345,00
106	2024/03/30	Rent March 2024	Rent	Cost centre B1	Input Tax- 15%	230,00
107	2024/03/30	Salary March 2024	Salaries and wages	Cost centre A1	No tax	300,00
107	2024/03/30	Salary March 2024	Salaries and wages	Cost centre B1	No tax	300,00

Posted Transactions in Documents

Purchase documents

For the purposes of this illustration, the following Purchase documents were processed, allocated to "*Cost centre A1*" cost centres, and posted (updated) to the ledger:

Salesperson - Russell	Salesperson - Tracy	Salesperson - Russell	Salesperson - Russell
2024/03/14 Purchase PU000001	2024/03/15 Purchase PU000002	2024/03/17 Purchase PU000003	2024/03/18 Purchase PU000004
From: ABC-Service-Centre	From: ABC-Office Supplies	From: A-ONE Suppliers	From: BEST Suppliers
Reference: AAB234GP	Reference: IN0014	Reference: 4562	Reference: 3532
Service - Delivery van 400,00			
5 x New Tyres			
Fitting and balancing	Install - Built-in cupboard 1 500,00	3 Drill presses 1 500,00	2 Compressors 2 000,00

600,00 Total Excluding Input Tax 1 000,00 Input Tax - 15% 150,00			
Total 1 150,00	Total 1 725,00	Total 1 725,00	Total 2 300,00

Sales documents

For the purposes of this illustration, the following Invoices were processed, allocated to "*Cost centre B1*" and posted (updated) to the ledger:

Salesperson - Russell	Salesperson - Tracy	Salesperson - Russell	Salesperson - Tracy
2024/03/13 Invoice IN000001	2024/03/14 Invoice IN000002	2024/03/15 Invoice IN000003	2024/03/16 Invoice IN000004
To: Mr. AB Green Reference: AB-IN-110 Comment: Paint - White Paint outside of house 1 000,00 Output Tax - 15% 150,00	To: MAC Shop Decor Specialists Reference: IB-101 Comment: 3 White cupboards with 6 drawers Install - Built-in cupboard 1 500,00 Output Tax - 15% 225,00	To: Mr. AB Green Reference: PH-101 Comment: Paint - Green Paint outside of house 1 000,00 Output Tax - 15% 150,00	To: Mr. Mike Davies Reference: IB-102 Comment: Install 6 cupboards Install - Built-in cupboard 1 500,00 Output Tax - 15% 225,00
Total 1 150,00	Total 1 725,00	Total 1 150,00	Total 1 725,00

For the purposes of this illustration, the following Invoices were processed, allocated to "*Cost centre A1*"

and posted (updated) to the ledger:

Salesperson - Russell	*Salesperson - Tracy*	*Salesperson - Russell*	*Salesperson - Tracy*
2024/03/17 Invoice IN000005	*2024/03/18 Invoice IN000006*	*2024/03/19 Invoice IN000007*	*2024/03/20 Invoice IN000008*
To: Mr. Mike Davies *Reference: D-101*	*To: Mr. Roger Smith* *Reference: C-102*	*To: Mr. Mike Davies* *Reference: C-103*	*To: Mr. Roger Smith* *Reference: D-102*
1 Drill press 1 000,00 *Output Tax - 15% - 150,00*	*2 Compressors 3 000,00* *Output Tax - 15% - 450,00*	*1 Compressor 1 500,00* *Output Tax - 15% - 225,00*	*2 Drill presses 2 000,00* *Output Tax - 15% - 300,00*
Total 1 150,00	*Total 3 450,00*	*Total 1 725,00*	*Total 2 300,00*

Configuring Cost centres

Before you may use this option in osFinancials5/TurboCASH5, you first need to create cost codes (cost groups, or cost centres).

Once this is done; you may activate these in specific batches (journals) and documents. Processing transactions in batches and/or documents, allows you to select specific cost centres for each transaction.

You may then print various reports for these cost centres (Cost centre 1 and/or Cost centre 2).

Create Groups for Cost centres

You may create up to two Reporting groups for Cost centres. These Cost centres may be activated in batches (journals) and/or documents. If you create only 1 Reporting group for Cost centres, only one (1) Cost centre group will be available in batches and/or documents.

Once the batches and/or documents are posted (updated to the ledger), you may print reports for each Cost centre from the Reports ribbon.

Some examples of reporting groups for cost centres:

1. Departments: You can create reporting groups based on different departments within your organization. For example, you can have reporting groups for Sales, Marketing, Finance, Human Resources, or Operations. This allows you to track and analyse expenses and performance for each department separately.
2. Projects: If your organization undertakes various projects, you can create reporting groups based on different project names or codes. This helps in monitoring the expenses, progress, and profitability of each project individually.
3. Locations: If your organization operates in multiple locations or branches, you can create reporting groups based on different locations. For example, you can have reporting groups for Head Office, Branch A, Branch B, or Regional Offices. This enables you to analyse the expenses and performance of each location separately.
4. Cost types: You can create reporting groups based on different types of costs incurred by the organization. For example, you can have reporting groups for Direct Costs, Indirect Costs, Fixed Costs, Variable Costs, or Overhead Costs. This allows you to analyse the cost structure and identify areas where cost savings can be made.
5. Profit centres: If you use profit centres to evaluate the profitability of different business segments, you can assign cost centres to reporting groups based on the relevant profit centres. This helps in monitoring the expenses and profitability of each profit centre individually.

These examples demonstrate how reporting groups for cost centres in osFinancials5/TurboCASH5 can be used to categorize and analyse cost data. By assigning cost centres to appropriate groups, you can track expenses, monitor performance, and make informed decisions regarding resource allocation and cost management within your organization.

To create groups for cost centres:

1. Click on Setup → Groups (Setup ribbon).
2. Click on the Cost centre 1.
3. Select the "*REPORTING GROUP ROOT*" and click on the New button.
4. Enter the name of your Cost centre (e.g. Cost centre A, Job cost name, etc., according to your requirements).



If you have created a Set of Books from scratch (using the "Create Set of Books (Advanced)" option for Firebird database types or the "Create Set of Books (Advanced)" option for MSSQL database types), the Cost centre 1 and Cost centre 2 groups will not be available.

You need to manually add the Project group to the TYPES table

See topics in this Help file : -

- *Steps after creating the Set of Books (Advanced) - Add missing Groups and Paper types in the Types table.*
- *Reportman - References - Groups.*

5. Repeat the process until you have entered all your Cost centres for "*Cost centre 1*".
6. You may also repeat the process to add Cost centres for "*Cost centre 2*", if applicable.
7. Click on OK to save your changes.

You may click on the Print button to print a list of your Cost centres.

Activate Cost centres

After creating Cost centres, the Cost centres need to activated in batches (journals) and/or documents.

Activate Cost centres in Batches (Journals)

Once you have created the "*Cost centre 1*" and/or "*Cost centre 2*", Cost centres needs to be activated in each batch type (required to process transactions). If activated for a specific Batch type, the "*Cost centre 1*" and/or "*Cost centre 2*" column will be displayed after the "*Account*" column; and (before the "*Tax*" column, if the "*No tax*" option, is not selected on the Standard tab of the "*Options for this batch*" screen) before the "*Debit*" column.

To activate cost centres for a specific batch:

1. Press F2, or click on Batch entry on the Default ribbon.
2. Select the specific Batch type, in which you need to activate Cost centres.
3. Click on the F10: Setup icon to set the Options for the selected batch.

You may also:-

- *Click on the Batch types on the Setup ribbon.*
- *Select the Batch type and click on the Edit button to access the "Options for this batch" screen.*

4. Click on the Advanced tab.



5. To activate the cost centres, tick the "*Cost centres*" tick box.
6. In the "*Cost centre*" field, you may select the default Cost centre. This will auto-complete (auto-select) the cost centre column with the default cost centre for this batch. When processing transactions, you

may select a different cost centre, if necessary.

7. Click on the OK button. The selected batch entry screen will be opened and the "*Cost centre 1*" and/or "*Cost centre 2*" column will be inserted in the batch.

> *To deactivate Cost centres in a specific batch, simply repeat this process and remove the tick in the "Cost centres" tick box.*



If cost centres have been selected, in "*Cost centre 1*" column, balancing entries will be created for "*Cost centre 1*", as per this example.



Click on F8:List to print a list of the transactions.



The selected cost centre, is listed underneath the "*Description*" of each transaction entered. It is also displayed underneath the balancing entry (indicated by 8 asterisks ********) for each transaction.

Activate Cost centres in Documents

Once you have created "*Cost centre 1*" and/or "*Cost centre 2*", Cost centres needs to be activated in Documents (to process documents for Cost centres). If activated, the "*Cost centre 1*" and/or "*Cost centre 2*" column will be displayed after the "*Account*" column; and (before the "*Tax*" column).

> *Cost centres are globally activated for all document types (i.e. purchase documents (purchases, supplier returns and orders) and sales documents (invoices, credit notes and quotes)).*

This will insert an additional lookup list when selecting the stock items for transactions.

To activate Cost centres for documents:

1. Click on Setup → Access Control (Setup ribbon).

2. Click on the Documents tab.

3. Select (tick) the Cost centre in documents ("*Costcenter in doc*") field.

4. Click on the Apply button.



5. Click on the Close button. "*Cost centre 1*" column, will be added globally to all documents.

This will add the Cost centre column in the document lines.



> *To deactivate Cost centres for all document types, simply repeat this process and remove the tick in the Cost centre in documents ("Costcenter in doc") tick box.*

Default Cost Centre Setting for Stock Items

If "*Cost centre 1*" and/or "*Cost centre 2*", have been created, you may set the default "*Cost centre*" each of your stock items.

This will auto-complete (auto-select) the "*Cost centre 1*" column with the default cost centre, when selecting

the stock item, while processing documents. You may select a different cost centre, if necessary.

Link default Cost centre to Stock items on the Stock item list screen

A "*Cost centre*" column, will automatically be inserted (the very last column) in the Stock items list screen. Drag the "*Cost centre*" column to the position, where it is comfortable for you to work with.

In this example, the "*Cost centre*" column is dragged to the left of "*Stock group 1*" column.

To set default Cost centres for Stock items:

1. Click on Stock items (**Default** ribbon).
2. Select a Stock item.
3. Click on the "*Cost centre*" column.



4. In the "*Cost centre*" column, select the default Cost centre from the list.
5. Click on the Save button to save the changes to the stock item.
6. Repeat the process until you have linked all your stock items to Cost centres.

Link default Cost centre to Stock items on the Ledger tab

The linking of stock items to Cost centres, may also be set on the "*Ledger*" tab.

To set default Cost centres for Stock items:

1. Click on Stock items (**Default** ribbon).
2. Select a Stock item.
3. Click on the Ledger tab.



4. In the "*Cost centre*" field, you may select the default Cost centre from the list.

5. Click on the Save button.

Add / Edit Budgets for Cost centres

Once the Cost centres are activated, you may add (enter / edit) your budget figures for Cost centres.

For the purpose of this example, enter the following budget:In this example, the entire budget is allocated split and allocated into the 2 Cost centres (added in "*Cost centre 1*" group), e.g. "*Cost centre A1*" and "*Cost centre B1*".

Total Budget				*Cost centre A1*		*Cost centre B1*	
Account Allocation	*Description*	*Annual*	*Monthly*	*Annual*	*Monthly*	*Annual*	*Monthly*
010-000	*Sales*	*-180 000*	*-15 000*	*-120 000*	*-10 000*	*-60 000*	*-5 000*
100-000	*Cost of sales*	*60 000*	*5 000*	*60 000*	*5 000*		
GROSS PROFIT		*120 000*	*10 000*	*-60 000*	*-5 000*	*-60 000*	*-5 000*

200-000	*Bank charges*	*600*	*50*	*600*	*50*		
210-010	*Fuel & oil*	*1 200*	*100*	*1 200*	*100*		
210-020	*Maintenance*	*2 400*	*200*	*2 400*	*200*		
210-030	*Repairs*	*1 200*	*100*	*1 200*	*100*		
220-000	*Rent*	*6 000*	*500*	*2 400*	*200*	*3 600*	*300*
225-000	*Salaries and wages*	*7 200*	*600*	*3 600*	*300*	*3 600*	*300*
TOTAL EXPENSES		*18 600*	*1 550*	*11 400*	*950*	*7 200*	*500*
NET PROFIT		*-101 400*	*-8 450*	*-48 600*	*-4 050*	*-52 800*	*-4 400*

The entire budget is allocated split and allocated into the 2 Cost centres (added in "*Cost centre 1*" group), e.g. "*Cost centre A1*" and "*Cost centre B1*".

Enter Budget figures for Cost centres

Budgets for Cost centres may also be added / edited and deleted on the on Setup → Accounts (Setup ribbon).

To Add / Edit Budgets for Cost centres:

1. On the Reports ribbon, select Budgets.
2. Select the period for which you need to enter the budget figures.
3. Select "*Cost centre A1*" or "*Cost centre B1*" in "*Cost centre 1*" column.
4. Click on the Refresh button to populate any budget figures for the selected period.

   If you wish to delete any existing budget figures for a selected cost centre for the selected period, click on the Delete all button.

5. The "*Reference*" field is by default set to "*BUDG*". Add your own reference to suit your requirements.
6. The "*Description*" field is by default set to "*Auto-budget*". Add your own description to suit your requirements.



7. Select the Account (or sub-account) and a periods to enter the budget figures.

> *To add a budget figure to more than one period (e.g. month):*
>
> - *Enter the amount.*
> - *Select the account and period in a row.*
> - *Press the Shift key and use your mouse to select multiple columns.*
> - *Click the Apply to selection button.*

8. Enter the amount for the budget (in this example the monthly amount is entered).

> *For credit budget figures (e.g. Sales) you need to prefix the amount with a negative "-" sign.*

9. Click on the Apply to selection button. A confirmation message is displayed:

> "Add amount to selection?"

10. Click the Yes button to add the amounts to the selected periods.
11. Repeat the process to add all the budget figures for the selected "*Cost centre A1*".
12. Select "*Cost centre A2*" to enter the budget figures.

After all the budget figures for "*Cost centre A1*" for the financial year, the budget should display as follows:



Code	Name	2024/03/01	2024/04/01	2024/05/01	2024/06/01	2024/07/01	2024/08/01	2024/09/01	2024/10/01	2024/11/01	2024/12/01	2025/01/01	2025/02/01	Total 2024/03/01 - 2025/02/28
010000	Sales	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-10,000.00	-120,000.00
100000	Cost of sales	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	60,000.00
200000	Bank charges	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	50.00	600.00
205000	Depreciation													
210000	Motor vehicle expenses													
210010	Fuel and oil	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	1,200.00
210020	Maintenance	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	2,400.00
210030	Repairs	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	100.00	1,200.00
215000	Maintenance of tools													
220000	Rent	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	200.00	2,400.00
225000	Salaries and wages	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	3,600.00
230000	Stationery													
235000	Sundry expenses													
505000	Capital													
510000	Retained income													
520000	Installment agreements													
44		-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-4,050.00	-48,600.00

Main accounts – Budget figures need to be entered for each sub account. The total of the sub-accounts will add up to the Main account.

In this example, if you have added a budget figure by mistake to the incorrect account, e.g. "Maintenance of tools" account of 100 per accounting period, you need to enter -100 and select the accounting periods. When you click on the Apply to selection button, the budget figures will be set to 0.00 for all selected accounting periods.

After all the budget figures for "*Cost centre B1*" for the financial year, the budget should display as follows:



Code	Name	2024/03/01	2024/04/01	2024/05/01	2024/06/01	2024/07/01	2024/08/01	2024/09/01	2024/10/01	2024/11/01	2024/12/01	2025/01/01	2025/02/01	Total 2024/03/01 - 2025/02/28
010000	Sales	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-5,000.00	-60,000.00
100000	Cost of sales													
200000	Bank charges													
205000	Depreciation													
210000	Motor vehicle expenses													
210010	Fuel and oil													
210020	Maintenance													
210030	Repairs													
215000	Maintenance of tools													
220000	Rent	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	3,600.00
225000	Salaries and wages	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	300.00	3,600.00
230000	Stationery													
235000	Sundry expenses													
505000	Capital													
510000	Retained income													
520000	Installment agreements													
44		-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-4,400.00	-52,800.00

Transaction view of budget figures

The Transactions tab lists all the budget figures for each period for all the cost centres.



id	Name	Date	Reference	Description	Amount	User	Change date	Project	Cost centre 1	Cost centre 2
875	Sales	2024/03/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
876	Sales	2024/04/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
877	Sales	2024/05/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
878	Sales	2024/06/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
879	Sales	2024/07/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
880	Sales	2024/08/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
881	Sales	2024/09/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
882	Sales	2024/10/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
883	Sales	2024/11/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:54		Cost centre A1	
884	Sales	2024/12/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:55		Cost centre A1	
885	Sales	2025/01/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:55		Cost centre A1	
886	Sales	2025/02/01	BUDG	Budget - Cost Centre A1	-10,000.00		2024/11/10 05:55:55		Cost centre A1	
887	Sales	2024/03/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:05		Cost centre B1	
888	Sales	2024/04/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
889	Sales	2024/05/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
890	Sales	2024/06/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
891	Sales	2024/07/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
892	Sales	2024/08/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
893	Sales	2024/09/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
894	Sales	2024/10/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
895	Sales	2024/11/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
896	Sales	2024/12/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
897	Sales	2025/01/01	BUDG	Budget - Cost Centre B1	-5,000.00		2024/11/10 05:57:09		Cost centre B1	
		132			-101,400.00					

The Reference ("*BUDG*") and Description ("*Auto budget*") columns displays your own description as entered before Apply to selection button.

You may click on the headings to sort the columns in an ascending or descending sequence.

Pivot table view of the budget figures

The Pivot tab, by default, summarises the budget totals for the Income and Expense (Income statement) accounts and Capital, Assets and Liabilities (Balance sheet) accounts for which budget figures were entered for the selected period or dates.

In this example, the budget figures were only captured for Income and Expense accounts.



In this example, the financial year starts on 1 March 2024 and ends on 28 February 2025. The financial year is, by default, split into to calendar years, e.g.:

2024 – 1 March 2024 to 31 December 2024 (Months 3 to 12 for the 2024 calendar year)

2025 – 1 January 2025 to 28 February 2025 (Months 1 to 2 for the 2025 calendar year)

This includes the entire budget figures which includes all cost centres. To view the Budget figures for a specific cost centre only, you may click on the filter icon on "*Group 1*" field list to select a cost centre.



If you have more than two cost centres, you may select more than one cost centres to be included and which to exclude.

After all the budget figures for "*Cost centre A1*" for the financial year, the budgeted net profit, should display as follows:



After all the budget figures for "*Cost centre B1*" for the financial year, the budgeted net profit, should display as follows:



Click on the ⊞ icon to list the budget totals for the accounts. The icon will change ⊟ to list totals for each account for which budget figures are entered.



Budget with 2025 calendar year expanded for all cost centres



The filter options is as follows:

Filter Area:

1. Reference - The default Reference "*BUDG*" or your reference as entered on the options section of the Budget tab. Select the available reference(s) on the list as filter options, as required.
2. Description - The default Description "*Auto budget*" or your description as entered on the options section of the Budget tab. Select the available description(s) on the list as filter options, as required.
3. Job code - (Projects) - If budgets were entered or processed for Projects, the project code(s) may be selected as filter options.
4. Group 1 – All cost centres will by default be selected. Since budgets were entered entered for Cost centres (Cost centre 1), the Cost centres for Cost centre 1 may be selected as filter options.
5. Group 2 - If budgets were entered entered for Cost centres (Cost centre 2), the Cost centres for Cost centre 2 may be selected as filter options.

Data Area:

6. Amount - The total debit amounts a credit amounts (prefixed by a - (minus sign)) will be listed. Select the available amount(s) on the list as filter options, as required.

Row Area:

7. Income expense - The options is as follows:
    - True = Income and Expense (Income statement) accounts. The totals of the Income and Expense (Income statement) accounts will be displayed as True Total.
    - False = Capital, Assets and Liabilities (Balance sheet) accounts. The totals of the Capital, Assets and Liabilities (Balance sheet) accounts will be displayed as False Total.
8. Account - All accounts will be listed by Account code and description. Select the available account(s) on the list as filter options, as required.

Column Area:

9. Year - The budget totals will be listed for each calendar year. For example, if your financial year starts on 1 January 2022 and ends on 31 December 2022, only one (1) financial year will be listed, i.e. 2022. In this example the financial year starts on 1 March 2022 and ends on 28 February 2023, the totals will be listed for 2022 and 2023. Select the year on the list as filter options, as required.
10. Month - Period 0 to 12 will be listed if your Reporting dates are set for a 12 periods (Setup → Reporting dates (Setup ribbon), the period numbers will be listed. Select the period (month) on the list as filter options, as required.
11. Date - All the dated for the selected period or dates selected on the options section of the Budget

tab, will be listed. Select the available date(s) on the list as filter options, as required.

Printing Budget listing figures for Cost centres

Once the budget figures is entered in Budgets (Reports ribbon) or Setup → Accounts (Setup ribbon), the budget figures (Budget listing) may be printed in the Trial balance, Income statement, Balance sheet and Standard column balances report types.

The "*Empty*" option, will print the full budget for the entire Set of Books (this includes the budget for both "*Cost centre A1*" and "*Cost centre B1*", if Cost centres were selected, when entering Budgets).

You may select to list only the budget for "*Cost centre A1"* or "*Cost centre B1*".

To view, print and analyse budget listing:

1. On the Reports ribbon, select Ledger analyser 1.



The buttons 1, 2, etc. is added when you launch the T-Account viewer or the Pivot table double-click or right-click on an account in the Ledger analyser 1 / 2.



2. Select the "*Budget*" option (tick).

> *This option is available for the Income statement, Trial balance and Balance sheet report type.*

3. Select the period from 2024/03/01 to 2025/02/28 to view the annual budget figures.

> *Select the period from 2024/03/01 to 2024/03/31 to view the budget figures for a specific period, e.g. "March 2024".*

4. Click on the Report button to refresh and generate the budget figures.

> *To view the budget figures for sub-accounts, e.g. click on the ⊞ icon next to G210-000 Motor vehicle expenses. This will display the figures for each sub-account.*

5. If any of these budget figures need some adjustment, click on Budgets (Reports ribbon) or on (Setup → Accounts (Setup ribbon); and select the applicable accounts and edit or enter the necessary figures.

6. Click on the Print button.

An example of the "*Income statement*", listing the total budget (including "*Cost centre A1*" and "*Cost centre B1*") for the financial year, is as follows:



An example, of the "*Income statement*", listing "*Cost centre A1*" budget for the financial year, is as follows:



An example, of the "*Income statement*", listing "*Cost centre B1*" budget for the financial year, is as follows:



The "Net profit" for the monthly budget figures; for the financial year, is as follows:

Total Budget (including "Cost centre A1" and "Cost centre B1") *101 400*

Only "Cost centre A1" *48 600*

Only "Cost centre B1" *52 800*

Processing Transactions

Processing Transactions for Cost Centres in Batches

Once the Cost centres are activated for a specific batch type, you may select the cost centre, after selecting the account.

For the purposes of this illustration, the following 3 payments were made, and allocated to cost centres (in the ABC-Payments batch) as follows:

Ref. no.	Date	Description	Account	Cost centre 1	Tax	Dr
105	2024/03/30	Petrol - Bakkie	Fuel & Oil	Cost centre A1	No tax	120,00
106	2024/03/30	Rent March 2024	Rent	Cost centre A1	Input Tax- 15%	345,00
106	2024/03/30	Rent March 2024	Rent	Cost centre B1	Input Tax- 15%	230,00
107	2024/03/30	Salary March 2024	Salaries and wages	Cost centre A1	No tax	300,00
107	2024/03/30	Salary March 2024	Salaries and wages	Cost centre B1	No tax	300,00

Note payment reference 106 and 107 were apportioned and allocated to different cost centres.

- *106 Rent March 2024 paid 500,00 (Exclusive of Input Tax at 15%)*
- *107 Salaries March 2024 paid 600,00 (No tax).*



In this example, the monthly payments in the Payments batch is allocated to different cost centres, is as follows:

- *220-000 Rent 500*

- Cost centre A1 300
- Cost centre B1 200

· 225-000 Salaries and wages 600

- Cost centre A1 300
- Cost centre B1 300

Processing Transactions for Cost Centres in Documents

Once you have created "*Cost centre 1*" and/or "*Cost centre 2*", Cost centres needs to be activated in Documents (to process documents for Cost centres). If activated, the "*Cost centre 1*" and/or "*Cost centre 2*" column will be displayed after the "*Account*" column; and (before the "*Tax*" column).

Cost centres are globally activated for all document types (i.e. purchase documents (purchases, supplier returns and orders) and sales documents (invoices, credit notes and quotes)).

Purchase documents

For the purposes of this illustration, the following Purchase documents were processed, allocated to "*Cost centre A1*" cost centres, and posted (updated) to the ledger:

Salesperson - Russell	*Salesperson - Tracy*	*Salesperson - Russell*	*Salesperson - Russell*
2024/03/14 Purchase PU000001	*2024/03/15 Purchase PU000002*	*2024/03/17 Purchase PU000003*	*2024/03/18 Purchase PU000004*
From: ABC-Service-Centre *Reference: AAB234GP* *Service - Delivery van 400,00* *5 x New Tyres* *Fitting and balancing 600,00* *Total Excluding Input Tax 1 000,00*	*From: ABC-Office Supplies* *Reference: IN0014* *Install - Built-in cupboard 1 500,00*	*From: A-ONE Suppliers* *Reference: 4562* *3 Drill presses 1 500,00*	*From: BEST Suppliers* *Reference: 3532* *2 Compressors 2 000,00*

Input Tax - 15% - *150,00*	*Input Tax - 15%* - *225,00*	*Input Tax - 15%* - *225,00*	*Input Tax - 15%* - *300,00*
Total 1 *150,00*	*Total* 1 *725,00*	*Total* 1 *725,00*	*Total* 2 *300,00*

Invoices (Sales documents)

For the purposes of this illustration, the following Invoices were processed, allocated to "*Cost centre B1*" and posted (updated) to the ledger:

Salesperson - Russell	*Salesperson - Tracy*	*Salesperson - Russell*	*Salesperson - Tracy*
2024/03/13 Invoice IN000001	*2024/03/14 Invoice IN000002*	*2024/03/15 Invoice IN000003*	*2024/03/16 Invoice IN000004*
To: Mr. AB Green	*To: MAC Shop Decor Specialists*	*To: Mr. AB Green*	*To: Mr. Mike Davies*
Reference: AB-IN-110	*Reference: IB-101*	*Reference: PH-101*	*Reference: IB-102*
Comment: *Paint - White*	*Comment:* *3 White cupboards with 6 drawers*	*Comment:* *Paint - Green*	*Comment:* *Install 6 cupboards*
Paint outside of house *1 000,00*	*Install - Built-in cupboard* *1 500,00*	*Paint outside of house* *1 000,00*	*Install - Built-in cupboard* *1 500,00*
Output Tax - 15% *150,00*	*Output Tax - 15%* - *225,00*	*Output Tax - 15%* *150,00*	*Output Tax - 15%* *225,00*
Total 1 *150,00*	*Total* 1 *725,00*	*Total* 1 *150,00*	*Total* 1 *725,00*

For the purposes of this illustration, the following Invoices were processed, allocated to "*Cost centre A1*" and posted (updated) to the ledger:

Salesperson - Russell	*Salesperson - Tracy*	*Salesperson - Russell*	*Salesperson - Tracy*
2024/03/17 Invoice	*2024/03/18 Invoice*	*2024/03/19 Invoice*	*2024/03/20 Invoice*

IN000005	*IN000006*	*IN000007*	*IN000008*
To: Mr. Mike Davies *Reference: D-101* *1 Drill press 1* *000,00* *Output Tax - 15%* *150,00*	*To: Mr. Roger Smith* *Reference: C-102* *2 Compressors 3* *000,00* *Output Tax - 15% _* *450,00*	*To: Mr. Mike Davies* *Reference: C-103* *1 Compressor 1* *500,00* *Output Tax - 15%* *225,00*	*To: Mr. Roger Smith* *Reference: D-102* *2 Drill presses 2* *000,00* *Output Tax - 15% _* *300,00*
Total 1 *150,00*	*Total 3* *450,00*	*Total 1* *725,00*	*Total 2* *300,00*

Invoices for cost centres may also be processed for Hours and Debtor appointments in the Calendar (Default ribbon).



Reports for Cost centres

In addition to the Budget listing in the Trial balance, Income statement, Balance sheet and Standard column balances in the Ledger Analyser, other reports may also be printed for cost centres.

The following financial reports is available to print and export for the entire Set of Books or for selected cost centres:

1. Budget vs actual (Realisation 3 Periods)
2. Ledger analyser
    a) Trial balance
    b) Income statement
    c) Balance sheet
    d) Standard column balances
    e) Budget vs actual
    f) This year vs last year

Pivot feature is also available for all of the report types in the Ledger analyser.

Pivots, by default, summarises the totals for the Income and Expense (Income statement) accounts and Capital, Assets and Liabilities (Balance sheet) accounts for which budget figures were entered, and/or transactions in batches and documents were processed, for the selected report type and period or dates.

The pivots allows you to sort, group, filter and drill down the data of your report.

Income statement

The "*Income statement*" displays the account debit and credit balances for Income statement type accounts linked to Income and Expenses financial categories.



The buttons 1, 2, 3, etc. is added when you launch the T-Account viewer or the Pivot table double-click or right-click on an account in the Ledger analyser 1 / 2.

An example of the "*Income statement*", listing the totals of all posted transactions in batches and documents (including "*Cost centre A1*" and "*Cost centre B1*") for the financial year, is as follows:



An example of the "*Income statement*", listing the totals of all posted transactions in batches and

documents for "*Cost centre A1*" only, for the financial year, is as follows:



detail

Income statement Period 2024/03/01 / 2025/02/28
Cost centre 1 - Cost centre A1
Cost centre 2 -

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT		4,280.00		
010000 Sales				10,500.00
100000 Cost of sales			4,500.00	
210000 Motor vehicle expenses	1,120.00			
210010 Fuel and oil			120.00	
210020 Maintenance			400.00	
210030 Repairs			600.00	
220000 Rent			300.00	
225000 Salaries and wages			300.00	
		Totals	6,220.00	10,500.00
		Net profit		4,280.00

An example of the "*Income statement*", listing the totals of all posted transactions in batches and documents for "*Cost centre B1*" only, for the financial year, is as follows:



detail

Income statement Period 2024/03/01 / 2025/02/28
Cost centre 1 - Cost centre B1
Cost centre 2 -

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT		6,500.00		
010000 Sales				7,000.00
220000 Rent			200.00	
225000 Salaries and wages			300.00	
		Totals	500.00	7,000.00
		Net profit		6,500.00

Balances – Transactions

The "Net profit" for the actual posted (updated to the ledger) transactions (in Batches and Documents); for the selected period "2024/03/01" to "2024/03/31", is as follows:

Total Income and Expenses (including "Cost centre A1" and "Cost centre B1") 10 780

Only "Cost centre A1" *4 280*

Only "Cost centre B1" *6 500*

Trial balance

The "*Trial balance*" displays the account debit and credit balances for Income statement type accounts

linked to Income and Expenses financial categories; as well as Balance sheet type accounts linked to Assets, Liabilities and Capital financial categories.



An example of the "*Trial balance*", listing the totals of all posted transactions in batches and documents (including "*Cost centre A1*" and "*Cost centre B1*") for the financial year, is as follows:



An example of the "*Trial balance*", listing the totals of all posted transactions in batches and documents for "*Cost centre A1*" only, for the financial year, is as follows:



detail

Trial balance Period 2024/03/01 / 2025/02/28
Cost centre 1 - Cost centre A1
Cost centre 2 -

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT				
010000 Sales				10,500.00
100000 Cost of sales			4,500.00	
210000 Motor vehicle expenses	1,120.00			
210010 Fuel and oil			120.00	
210020 Maintenance			400.00	
210030 Repairs			600.00	
220000 Rent			300.00	
225000 Salaries and wages			300.00	
600000 Furniture & fittings - Net value	1,500.00			
600010 Furniture & fittings @ cost			1,500.00	
700000 Debtors control			12,075.00	
750000 Stock control				1,000.00
810000 ABC - Bank				765.00
860000 VAT - Control - 15%		630.00		
860010 Output VAT - 15%				1,575.00
860020 Input VAT - Standard rate -15%			945.00	
900000 Creditors control				6,900.00
	Totals		20,740.00	20,740.00
	Net profit		6,220.00	10,500.00
				4,280.00

An example of the "*Trial balance*", listing the totals of all posted transactions in batches and documents for "*Cost centre B1*" only, for the financial year, is as follows:



detail

Trial balance Period 2024/03/01 / 2025/02/28
Cost centre 1 - Cost centre B1
Cost centre 2 -

	Totals Debit	Totals Credit	Debit	Credit
REPORTING GROUP ROOT				
010000 Sales				7 000,00
220000 Rent			200,00	
225000 Salaries and wages			300,00	
700000 Debtors control			8 050,00	
810000 ABC - Bank				530,00
860000 VAT - Control - 15%		1 020,00		
860010 Output VAT - 15%				1 050,00
860020 Input VAT - Standard rate - 15%			30,00	
900000 Creditors control				
	Totals		8 580,00	8 580,00
	Net profit		500,00	7 000,00
				6 500,00

Balances – Transactions

The "Net profit" for the actual posted (updated to the ledger) transactions (in Batches and Documents); for the

selected period "2024/03/01" to "2025/02/28", is as follows:

Total Income and Expenses (including "Cost centre A1" and "Cost centre B1") 10 780

Only "Cost centre A1" *4 280*

Only "Cost centre B1" *6 500*

Balance sheet

The "*Balance sheet*" displays the account debit and credit balances for Balance sheet type accounts linked to Assets, Liabilities and Capital financial categories.



An example of the "*Balance sheet*", listing the totals of all posted transactions in batches and documents (including "*Cost centre A1*" and "*Cost centre B1*") for the financial year, is as follows:



An example of the "*Balance sheet*", listing the totals of all posted transactions in batches and documents for "*Cost centre A1*" only, for the financial year, is as follows:



An example of the "*Balance sheet*", listing the totals of all posted transactions in batches and documents for "*Cost centre B1*" only, for the financial year, is as follows:



Balances – Transactions

The "Net profit" for the actual posted (updated to the ledger) transactions (in Batches and Documents); for the selected period "2024/03/01" to "2025/02/28", is as follows:

Total Income and Expenses (including "Cost centre A1" and "Cost centre B1") 10 780

Only "Cost centre A1" *4 280*

Only "Cost centre B1" *6 500*

Standard column balances

The "*Standard column balances*" displays the account debit and credit balances in the following three (3) reports, in one report:

1. Trial balance (Income, Expenses, Assets, Liabilities and Capital).
2. Income statement (Income and Expenses).
3. Balance sheet (Assets, Liabilities and Capital).

This is a breakdown of the Trial balance into the Income statement and Balance sheet.



Code	Trial balance		Income statement		Balance sheet	
G010000	0.00	17,500.00	0.00	17,500.00	0.00	0.00
G100000	4,500.00	0.00	4,500.00	0.00	0.00	0.00
G210010	120.00	0.00	120.00	0.00	0.00	0.00
G210020	400.00	0.00	400.00	0.00	0.00	0.00
G210030	600.00	0.00	600.00	0.00	0.00	0.00
G220000	500.00	0.00	500.00	0.00	0.00	0.00
G225000	600.00	0.00	600.00	0.00	0.00	0.00
G510000	0.00	0.00	0.00	0.00	0.00	0.00
G600010	1,500.00	0.00	0.00	0.00	1,500.00	0.00
G700000	20,125.00	0.00	0.00	0.00	20,125.00	0.00
G750000	3,500.00	4,500.00	0.00	0.00	0.00	1,000.00
B810000	0.00	1,295.00	0.00	0.00	0.00	1,295.00
T860010	0.00	2,625.00	0.00	0.00	0.00	2,625.00
T860020	975.00	0.00	0.00	0.00	975.00	0.00
G900000	0.00	6,900.00	0.00	0.00	0.00	6,900.00
			10,780.00	0	0	10,780.00
	32,820.00	32,820.00	17,500.00	17,500.00	22,600.00	22,600.00

An example of the "*Standard column balances"* listing the totals of all posted transactions in batches and documents (including "*Cost centre A1*" and "*Cost centre B1*") for the financial year, is as follows:



Code	Name	Trial balance		Income statement		Balance sheet	
G010000	Sales	0.00	17,500.00	0.00	17,500.00	0.00	0.00
G100000	Cost of sales	4,500.00	0.00	4,500.00	0.00	0.00	0.00
G210010	Fuel and oil	120.00	0.00	120.00	0.00	0.00	0.00
G210020	Maintenance	400.00	0.00	400.00	0.00	0.00	0.00
G210030	Repairs	600.00	0.00	600.00	0.00	0.00	0.00
G220000	Rent	500.00	0.00	500.00	0.00	0.00	0.00
G225000	Salaries and wages	600.00	0.00	600.00	0.00	0.00	0.00
G510000	Retained income	0.00	0.00	0.00	0.00	0.00	0.00
G600010	Furniture & fittings @ cost	1,500.00	0.00	0.00	0.00	1,500.00	0.00
G700000	Debtors control	20,125.00	0.00	0.00	0.00	20,125.00	0.00
G750000	Stock control	3,500.00	4,500.00	0.00	0.00	0.00	1,000.00
B810000	ABC - Bank	0.00	1,295.00	0.00	0.00	0.00	1,295.00
T860010	Output VAT - 15%	0.00	2,625.00	0.00	0.00	0.00	2,625.00
T860020	Input VAT - Standard rate - 15%	975.00	0.00	0.00	0.00	975.00	0.00
G900000	Creditors control	0.00	6,900.00	0.00	0.00	0.00	6,900.00
	Net Profit/Loss			10,780.00	0	0	10,780.00
	Totals	32,820.00	32,820.00	17,500.00	17,500.00	22,600.00	22,600.00

The printed "*Standard column balances*" report, for "*Cost centre A1*" selected, should be displayed as

follows:



Code	Name	Trial balance		Income statement		Balance sheet	
G010000	Sales	0.00	10,500.00	0.00	10,500.00	0.00	0.00
G100000	Cost of sales	4,500.00	0.00	4,500.00	0.00	0.00	0.00
G210010	Fuel and oil	120.00	0.00	120.00	0.00	0.00	0.00
G210020	Maintenance	400.00	0.00	400.00	0.00	0.00	0.00
G210030	Repairs	600.00	0.00	600.00	0.00	0.00	0.00
G220000	Rent	300.00	0.00	300.00	0.00	0.00	0.00
G225000	Salaries and wages	300.00	0.00	300.00	0.00	0.00	0.00
G510000	Retained income	0.00	0.00	0.00	0.00	0.00	0.00
G800010	Furniture & fittings @ cost	1,500.00	0.00	0.00	0.00	1,500.00	0.00
G700000	Debtors control	12,075.00	0.00	0.00	0.00	12,075.00	0.00
G750000	Stock control	3,500.00	4,500.00	0.00	0.00	0.00	1,000.00
B810000	ABC - Bank	0.00	765.00	0.00	0.00	0.00	765.00
T860010	Output VAT - 15%	0.00	1,575.00	0.00	0.00	0.00	1,575.00
T860020	Input VAT - Standard rate -15%	945.00	0.00	0.00	0.00	945.00	0.00
G900000	Creditors control	0.00	6,900.00	0.00	0.00	0.00	6,900.00
	Net Profit/Loss			4,280.00	0	0	4,280.00
	Totals	24,240.00	24,240.00	10,500.00	10,500.00	14,520.00	14,520.00

The printed "*Standard column balances*" report, for "*Cost centre B1*" selected, should be displayed as follows:



Code	Name	Trial balance		Income statement		Balance sheet	
G010000	Sales	0.00	7,000.00	0.00	7,000.00	0.00	0.00
G220000	Rent	200.00	0.00	200.00	0.00	0.00	0.00
G225000	Salaries and wages	300.00	0.00	300.00	0.00	0.00	0.00
G510000	Retained income	0.00	0.00	0.00	0.00	0.00	0.00
G700000	Debtors control	8,050.00	0.00	0.00	0.00	8,050.00	0.00
B810000	ABC - Bank	0.00	530.00	0.00	0.00	0.00	530.00
T860010	Output VAT - 15%	0.00	1,050.00	0.00	0.00	0.00	1,050.00
T860020	Input VAT - Standard rate -15%	30.00	0.00	0.00	0.00	30.00	0.00
	Net Profit/Loss			6,500.00	0	0	6,500.00
	Totals	8,580.00	8,580.00	7,000.00	7,000.00	8,080.00	8,080.00

Balances – Transactions

The "Net profit" for the actual posted (updated to the ledger) transactions (in Batches and Documents); for the selected period "2024/03/01" to "2025/02/28", is as follows:

Total Income and Expenses (including "Cost centre A1" and "Cost centre B1") 10 780

Only "Cost centre A1" *4 280*

Only "Cost centre B1" *6 500*

This year vs last year

This report will display the comparative figures for up to 2 financial years or the same periods (a specific month, 2 months, 3 months, 4 months, 6 months or a year).



Code	Name	D 2024/03/01	C 2025/02/28	D 2023/03/01	C 2024/02/29	Difference	%
G010000	Sales	0.00	17,500.00	0.00	0.00	17,500.00	100.00
G100000	Cost of sales	4,500.00	0.00	0.00	0.00	-4,500.00	100.00
G210010	Fuel and oil	120.00	0.00	0.00	0.00	-120.00	100.00
G210020	Maintenance	400.00	0.00	0.00	0.00	-400.00	100.00
G210030	Repairs	600.00	0.00	0.00	0.00	-600.00	100.00
G220000	Rent	500.00	0.00	0.00	0.00	-500.00	100.00
G225000	Salaries and wages	600.00	0.00	0.00	0.00	-600.00	100.00
G505000	Capital	0.00	0.00	0.00	11,500.00	-11,500.00	100.00
G600010	Furniture & fittings @ cost	1,500.00	0.00	1,007.00	0.00	-493.00	148.96
G600020	Furniture & fittings -Acc. deprec.	0.00	0.00	0.00	300.00	-300.00	100.00
G610010	Motor vehicles @ cost	0.00	0.00	5,000.00	0.00	5,000.00	100.00
G610020	Motor vehicles -Accum. depreciation	0.00	0.00	0.00	500.00	-500.00	100.00
G700000	Debtors control	20,125.00	0.00	0.00	0.00	-20,125.00	100.00
G750000	Stock control	0.00	1,000.00	6,500.00	0.00	7,500.00	-15.38
B810000	ABC - Bank	0.00	1,295.00	3,193.00	0.00	4,488.00	-40.56
B820000	Petty cash	0.00	0.00	100.00	0.00	100.00	100.00
T860010	Output VAT - 15%	0.00	2,625.00	0.00	100.00	2,525.00	2,625.00
T860020	Input VAT - Standard rate -15%	975.00	0.00	0.00	0.00	-975.00	100.00
G900000	Creditors control	0.00	6,900.00	0.00	0.00	6,900.00	100.00
	Net Profit/Loss	0	10,780.00		0.00	10,780.00	
	Totals		0.00	3,400.00		3,400.00	

The "*This year vs last year*" report (no Cost centres selected), should be displayed as follows:



		D 2024/03/01		D 2023/03/01			
Code	Name	Debit	Credit	Debit	Credit	Difference	%
G010000	Sales		17,500.00			17,500.00	100.00
G100000	Cost of sales	4,500.00				-4,500.00	100.00
G210010	Fuel and oil	120.00				-120.00	100.00
G210020	Maintenance	400.00				-400.00	100.00
G210030	Repairs	600.00				-600.00	100.00
G220000	Rent	500.00				-500.00	100.00
G225000	Salaries and wages	600.00				-600.00	100.00
G505000	Capital				11,500.00	-11,500.00	100.00
G600010	Furniture & fittings @ cost	1,500.00		1,007.00		-493.00	148.96
G600020	Furniture & fittings -Acc. deprec.				300.00	-300.00	100.00
G610010	Motor vehicles @ cost			5,000.00		5,000.00	100.00
G610020	Motor vehicles -Accum depreciation				500.00	-500.00	100.00
G700000	Debtors control	20,125.00				-20,125.00	100.00
G750000	Stock control		1,000.00	6,500.00		7,500.00	-15.38
B810000	ABC - Bank		1,295.00	3,193.00		4,488.00	-40.56
B820000	Petty cash			100.00		100.00	100.00
T860010	Output VAT - 15%		2,625.00		100.00	2,525.00	2,625.
T860020	Input VAT - Standard rate - 15%	975.00				-975.00	100.00
G900000	Creditors control		6,900.00			6,900.00	100.00
	Totals	**29,320.00**	**29,320.00**	**15,800.00**	**12,400.00**	**3,400.00**	
		0.00	10,780.00	0.00	0.00		
		Net profit		**Net profit**			

The "*This year vs last year*" report, for "*Cost centre A1*" selected, should be displayed as follows:



The "*This year vs last year*" report, for "*Cost centre B1*" selected, should be displayed as follows:



Balances – Transactions

The "Net profit" for the actual posted (updated to the ledger) transactions (in Batches and Documents); for the selected period "2024/03/01" to "2025/02/28", is as follows:

Total Income and Expenses (including "Cost centre A1" and "Cost centre B1") 10 780

	Only "Cost centre A1"	*4 280*
	Only "Cost centre B1"	*6 500*

Budget Performance reports

Budget vs actual

The "*Budget vs actual*" report will display the difference between the actual posted transaction totals and the budget (as entered) as a percentage for the selected period.



Code	Name	Trial balance		Budget		Difference	%
G010000	Sales	0.00	17,500.00	0.00	15,000.00	2,500.00	116.67
G100000	Cost of sales	4,500.00	0.00	5,000.00	0.00	500.00	90.00
G200000	Bank charges	0.00	0.00	50.00	0.00	50.00	100.00
G210010	Fuel and oil	120.00	0.00	100.00	0.00	-20.00	120.00
G210020	Maintenance	400.00	0.00	200.00	0.00	-200.00	200.00
G210030	Repairs	600.00	0.00	100.00	0.00	-500.00	600.00
G220000	Rent	500.00	0.00	500.00	0.00	0.00	100.00
G225000	Salaries and wages	600.00	0.00	600.00	0.00	0.00	100.00
G600010	Furniture & fittings @ cost	1,500.00	0.00	0.00	0.00	-1,500.00	100.00
G700000	Debtors control	20,125.00	0.00	0.00	0.00	-20,125.00	100.00
G750000	Stock control	0.00	1,000.00	0.00	0.00	1,000.00	100.00
B810000	ABC - Bank	0.00	1,295.00	0.00	0.00	1,295.00	100.00
T860010	Output VAT - 15%	0.00	2,625.00	0.00	0.00	2,625.00	100.00
T860020	Input VAT - Standard rate -15%	975.00	0.00	0.00	0.00	-975.00	100.00
G900000	Creditors control	0.00	6,900.00	0.00	0.00	6,900.00	100.00
	Net Profit/Loss	0	10,780.00		8,450.00	2,330.00	
	Totals		0.00		8,450.00	-8,450.00	

The printed "*Budget vs actual*" report (no Cost centres selected), should be displayed as follows:



budvsactsimple

Budget vs actual Period 2024/03/01 / 2024/03/31
Cost centre 1 - Empty
Cost centre 2 -

		Trial balance		Budget			
Code	Name	Debit	Credit	Debit	Credit	Difference	%
G010000	Sales		17,500.00		15,000.00	2,500.00	116.67
G100000	Cost of sales	4,500.00		5,000.00		500.00	90.00
G200000	Bank charges			50.00		50.00	100.00
G210010	Fuel and oil	120.00		100.00		-20.00	120.00
G210020	Maintenance	400.00		200.00		-200.00	200.00
G210030	Repairs	600.00		100.00		-500.00	600.00
G220000	Rent	500.00		500.00			100.00
G225000	Salaries and w ages	600.00		600.00			100.00
G600010	Furniture & fittings @ cost	1,500.00				-1,500.00	100.00
G700000	Debtors control	20,125.00				-20,125.00	100.00
G750000	Stock control		1,000.00			1,000.00	100.00
B810000	ABC - Bank		1,295.00			1,295.00	100.00
T860010	Output VAT - 15%		2,625.00			2,625.00	100.00
T860020	Input VAT - Standard rate - 15%	975.00				-975.00	100.00
G900000	Creditors control		6,900.00			6,900.00	100.00
	Totals	**29,320.00**	**29,320.00**	**6,550.00**	**15,000.00**	**-8,450.00**	
		0.00	10,780.00	0.00	8,450.00		
		Net profit		**Net profit**			

The printed "*Budget vs actual*" report, for "*Cost centre A1*" selected, should be displayed as follows:



budvsactsimple

Budget vs actual Period 2024/03/01 / 2024/03/31
Cost centre 1 - Cost centre A1
Cost centre 2 -

		Trial balance		Budget			
Code	Name	Debit	Credit	Debit	Credit	Difference	%
G010000	Sales		10,500.00		10,000.00	500.00	105.00
G100000	Cost of sales	4,500.00		5,000.00		500.00	90.00
G200000	Bank charges			50.00		50.00	100.00
G210010	Fuel and oil	120.00		100.00		-20.00	120.00
G210020	Maintenance	400.00		200.00		-200.00	200.00
G210030	Repairs	600.00		100.00		-500.00	600.00
G220000	Rent	300.00		200.00		-100.00	150.00
G225000	Salaries and w ages	300.00		300.00			100.00
G600010	Furniture & fittings @ cost	1,500.00				-1,500.00	100.00
G700000	Debtors control	12,075.00				-12,075.00	100.00
G750000	Stock control		1,000.00			1,000.00	100.00
B810000	ABC - Bank		765.00			765.00	100.00
T860010	Output VAT - 15%		1,575.00			1,575.00	100.00
T860020	Input VAT - Standard rate - 15%	945.00				-945.00	100.00
G900000	Creditors control		6,900.00			6,900.00	100.00
	Totals	**20,740.00**	**20,740.00**	**5,950.00**	**10,000.00**	**-4,050.00**	
		0.00	4,280.00	0.00	4,050.00		
		Net profit		**Net profit**			

The printed "*Budget vs actual*" report, for "*Cost centre B1*" selected, should be displayed as follows:


budvsactsimple

This year vs last year Period 2024/03/01 / 2025/02/28
Cost centre 1 - Cost centre B1
Cost centre 2 -

		D 2024/03/01		D 2023/03/01			
Code	Name	Debit	Credit	Debit	Credit	Difference	%
G010000	Sales		7,000.00			7,000.00	100.00
G220000	Rent	200.00				-200.00	100.00
G225000	Salaries and w ages	300.00				-300.00	100.00
G700000	Debtors control	8,050.00				-8,050.00	100.00
B810000	ABC - Bank		530.00			530.00	100.00
T860010	Output VAT - 15%		1,050.00			1,050.00	100.00
T860020	Input VAT - Standard rate -15%	30.00				-30.00	100.00
	Totals	8,580.00	8,580.00	0.00	0.00	0.00	
		0.00	6,500.00	0.00	0.00		
		Net profit		Net profit			

Balances – Budget

The "Net profit" for the monthly budget figures; for the selected period "2024/03/01" to "2025/03/31" is as follows:

Total Budget (including "Cost centre A1" and "Cost centre B1") 8 450

Only "Cost centre A1" *4 050*

Only "Cost centre B1" *4 400*

Balances – Transactions

The "Net profit" for the actual posted (updated to the ledger) transactions (in Batches and Documents); for the selected period "2024/03/01" to "2024/03/31", is as follows:

Total Income and Expenses (including "Cost centre A1" and "Cost centre B1") 10 780

Only "Cost centre A1" *4 280*

Only "Cost centre B1" *6 500*

Budget vs actual (3 Periods) report

The Budget vs Actual (realisation - 3 periods) report lists the Income and Expense account balances and budget figures for three (3) periods as comparative figures.

Only the transactions in documents and batches which are posted (updated) to the ledger will be included in this report.

Budget figures are entered and edited in Budgets (Reports ribbon) or Setup → Accounts (Setup ribbon).

If you have activated Cost centres and have entered the budget figures; and processed transactions in batches and documents for Cost centres, you may select (tick) the Cost centres to print this report for your specific Cost centres.

To print a Budget vs actual (3 periods) report:

1. On the Reports ribbon, select Reports → Ledger → Budget.



2. Select the following options:

   a) Period - Select up to three (3) periods on the Per period tabs. You may click on the Free selection tab to select a specific date or a range of dates to include balances and budget figures in the report.

   b) Include zero balances - If this option is not selected (not ticked), it will list only the expense and income accounts which has balances and/or budget figures. Tick this option to include all accounts including those with no actual transactions and/or budget figures).

   c) Balances - If this option is not selected (not ticked), it will list the expense and income accounts which has balances and/or budget figures. Tick this option to show only the actual transactions totals and/or budget totals of expense and income accounts for the selected period or dates.

   d) Cost centre 1 - Will be listed, as Cost centres have been added to "*Cost centre 1*" (Setup → Groups (Setup ribbon)). You may select these Cost centres, to include in the report.

e) Cost centre 2 – The “Empty” tick box and no cost centres will be listed, since no Cost centres were added in ”*Cost centre 2*” (Setup → Groups (Setup ribbon)).

3. Click on the OK button.

The printed “*Budget vs actual (realisation - 3 periods)*” report (no Cost centres selected), should be displayed as follows:



The “*Budget vs actual (realisation - 3 periods)*” report, for “*Cost centre A1*” selected, should be displayed as follows:



The printed "*Budget vs actual (realisation - 3 periods)*" report, for "*Cost centre B1*" selected, should be displayed as follows:



Budget vs actual

Budget v/s realisation 3 periods — Include zero balances: No — Balances: No

Periods	01-03-2024 31-03-2024		01-04-2024 30-04-2024		01-05-2024 31-05-2024	
Cost centre 1 — Empty@Cost centre B1	Cost centre 2					
***Expenses**						
Account no. / Description	Actual	Budget	Actual	Budget	Actual	Budget
220000 Rent	200.00	300.00	0.00	300.00	0.00	300.00
225000 Salaries and wages	300.00	300.00	0.00	300.00	0.00	300.00
Total - *Expenses	500.00	600.00	0.00	600.00	0.00	600.00
Actual - Budget	-100.00		-600.00		-600.00	
***Income**						
Account no. / Description	Actual	Budget	Actual	Budget	Actual	Budget
010000 Sales	-7,000.00	-5,000.00	0.00	-5,000.00	0.00	-5,000.00
Total - *Income	-7,000.00	-5,000.00	0.00	-5,000.00	0.00	-5,000.00
Actual - Budget	-2,000.00		5,000.00		5,000.00	
Net profit / Net loss: Actual	-6,500.00		0.00		0.00	
Net profit / Net loss: Budget	-4,400.00		-4,400.00		-4,400.00	
Net profit / Net loss: Actual - Budget	-2,100.00		4,400.00		4,400.00	

Balances – Budget

The "Net profit" for the monthly budget figures; for the selected period "2024/03/01" to "2024/03/31" is as follows:

Total Budget (including "Cost centre A1" and "Cost centre B1") 8 450

Only "Cost centre A1" 4 050

Only "Cost centre B1" 4 400

Balances – Transactions

The "Net profit" for the actual posted (updated to the ledger) transactions (in Batches and Documents); for the selected period "2024/03/01" to "2024/03/31", is as follows:

Total Income and Expenses (including "Cost centre A1" and "Cost centre B1") 10 780

Only "Cost centre A1" 4 280

Only "Cost centre B1" 6 500

Batch Reports

Cost centres, if selected in batches and in documents, will be displayed in the following batch listing

reports, printed from the Batch entry (Default ribbon):

1. Unposted batches
2. Posted batches

On the Reports → Batch entry menu (Reports ribbon), cost centres are not included in the "Batch transactions per period" and "Documents" reports.

Cost centres are included in the posted batch reports and may be printed for selected batches and/or documents (on the Default ribbon) from the following options:

1. *Batch entry - Posted batches tab.*
2. *Debtor / Creditor from Documents and Transaction tabs.*

Batch List Unposted Batches

Once transactions have been entered in batches (Batch entry (Default ribbon); and the transactions have not yet been posted (updated) to the ledger; you may click on the F8:List icon on the Batch entry screen to print the list of the transactions in the unposted batch.


F:\osfinancials5-MERGE-2\plug_ins\reports\GENERAL\documents\batch.rep

List batch - Unposted batch

Batch name ABC-Payments
Alias (batch name) ABCPayments2403

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/30	105	Petrol bakkie	G210-010		0.00	120.00	
		Cost centre A1,	B810-000				
2024/03/30	*******	*Petrol bakkie	B810-000		0.00		120.00
		Cost centre A1,	810-000				
2024/03/30	106	Rent March 2024	G220-000	T860-020	45.00	300.00	
		Cost centre A1,	B810-000				
2024/03/30	*******	*Rent March 2024	T860-020		0.00	45.00	
		Cost centre A1,	860-020				
2024/03/30	*******	*Rent March 2024	B810-000		0.00		345.00
		Cost centre A1,	810-000				
2024/03/30	106	Rent March 2024	G220-000	T860-020	30.00	200.00	
		Cost centre B1,	B810-000				
2024/03/30	*******	*Rent March 2024	T860-020		0.00	30.00	
		Cost centre B1,	860-020				
2024/03/30	*******	*Rent March 2024	B810-000		0.00		230.00
		Cost centre B1,	810-000				
2024/03/30	107	Salary March 2024	G225-000		0.00	300.00	
		Cost centre A1,	B810-000				
2024/03/30	*******	*Salary March 2024	B810-000		0.00		300.00
		Cost centre A1,	810-000				
2024/03/30	107	Salary March 2024	G225-000		0.00	300.00	
		Cost centre B1,	B810-000				
2024/03/30	*******	*Salary March 2024	B810-000		0.00		300.00
		Cost centre B1,	810-000				
				Total		1,295.00	1,295.00

*The selected cost centre, is listed underneath the "Description" of each transaction entered. It is also displayed underneath the balancing entry (indicated by 8 asterisks ********) for each transaction.*

Note payment reference 106 and 107 were apportioned and allocated to different cost centres.

- *106 Rent March 2024 paid 500,00 (Exclusive of Input Tax at 15%)*
- *107 Salaries March 2024 paid 600,00 (No tax).*

Batch – Posted Batches

Once transactions have been entered in batches (Batch entry (Default ribbon); and/or documents (Documents (Default ribbon); and the transactions have been posted (updated) to the ledger; you may print the list of the transactions in the posted batches.

On the Reports → Batch entry menu (Reports ribbon), cost centres are not included in the "Batch transactions per period" and "Documents" reports.

Cost centres are included in the posted batch reports and may be printed for selected batches and/or documents (on the Default ribbon) from the following options:

- *Batch entry - Posted batches tab.*
- *Debtor / Creditor from Documents and Transaction tabs.*

Print a Posted Batch report from the Batch entry screens

The batch type for documents are set in the Documents setup (Setup ribbon).

Invoices and Credit notes will be listed in the Sales batch .

Purchases and Supplier returns will be listed in the Purchase batch.

To print a posted batch list report:

1. Click on the Batch entry (Default ribbon).
2. Select a batch type on the "*Batch type*" screen.
3. Click on the Posted batches tab.



4. On the Batch entry tab, (list of posted batches and documents), select a batch; or a document; and double-click to display the Details tab.



5. Click on the Print button.



Transaction reports

The following transaction reports, may be printed for Cost centres:

1. Ledger - Transactions - Standard
2. Ledger - Transactions - Extra details
3. Debtor - Transactions - Standard
4. Debtor - Transactions - Extra details
5. Creditor - Transactions - Standard
6. Creditor - Transactions - Extra details

Ledger - Transactions - Standard / Extra details

The "*General ledger transactions - Extra details*" report is similar to the "*General ledger transactions - Standard*" report, but displays extra details of the Contra accounts (i.e. Account code, Account description, Contra account code and Description as well as the Tax account code and Description). For example,

> "D1ABGRE Mr. AB. Green,T860010, Output Tax - 15%", etc.

To print General ledger transactions - Standard / Extra details reports:

1. On the Reports ribbon, select Reports → Ledger → Transactions.
2. Select the "*General ledger transactions - Standard*" or "*General ledger transactions - Extra details*" report.



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

   b) From account / To account - Select a general ledger account or a range of general ledger accounts, to include in the report.

   c) Sequence - Select "*Account*" to print the report by account code or "*Description*" to print the report by account description (name). You may also select "*Reporting group 1*" or "*Reporting group 2*" to print the accounts according to the "*Account group 1*" or "*Account group 2*" as added in Setup → Groups (Setup ribbon) and linked to the Setup → Accounts (Setup ribbon).

   d) Include zero balances - If this option is not selected (not ticked), it will list only the transactions for accounts which has transactions and/or balances. Tick this option to include opening balances (closing balances before the selected periods / dates).

      Opening and Closing balances will not be displayed for Income and Expense account types. It will only be displayed for Balance sheet accounts.

   e) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

f) Cost centre 1 - Will be listed, as Cost centres have been added to "*Cost centre 1*" (Setup → Groups (Setup ribbon)). You may select these Cost centres, to include in the report.

g) Cost centre 2 – The "Empty" tick box and no cost centres will be listed, since no Cost centres were added in "*Cost centre 2*" (Setup → Groups (Setup ribbon)).

4. Click on the OK button.

View the "*General ledger transactions – Extra details*" (no Cost centres selected) for the "*Sales*" account:



General ledger transactions - Extra details

General ledger transactions - Extra details

Period: 2024/03/01 - 2025/02/28

From: G010000 **Include zero balances:** No
To: G999000 **New page per account:** Yes

***G010000 Sales** 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/07	******	Paint - Exterior		1,000.00	-1,000.00
Contra Accounts	D1ABGRE	Mr. AB Green,T860010 Output VAT - 15%			
2024/03/09	******	Install - Built-in cupboard		1,500.00	-2,500.00
Contra Accounts	D1MACDS	MAC Shop Decor Specialists,T860010 Output VAT - 15%			
2024/03/10	******	Paint - Exterior		1,000.00	-3,500.00
Contra Accounts	D1ABGRE	Mr. AB Green,T860010 Output VAT - 15%			
2024/03/12	******	Install - Built-in cupboard		1,500.00	-5,000.00
Contra Accounts	D1MDAVI	Mr. Mike Davies,T860010 Output VAT - 15%			
2024/03/13	IN000001	Paint - Exterior		1,000.00	-6,000.00
Contra Accounts	D1ABGRE	Mr. AB Green,T860010 Output VAT - 15%			
2024/03/14	IN000002	Install - Built-in cupboards		1,500.00	-7,500.00
Contra Accounts	D1MACDS	MAC Shop Decor Specialists,T860010 Output VAT - 15%			
2024/03/15	IN000003	Paint - Exterior		1,000.00	-8,500.00
Contra Accounts	D1ABGRE	Mr. AB Green,T860010 Output VAT - 15%			
2024/03/16	IN000004	Install Built-in Cupboards		1,500.00	-10,000.00
Contra Accounts	D1MDAVI	Mr. Mike Davies,T860010 Output VAT - 15%			
2024/03/17	IN000005	Drill press		1,000.00	-11,000.00
Contra Accounts	D1MDAVI	Mr. Mike Davies,T860010 Output VAT - 15%			
2024/03/18	IN000006	Compressor		3,000.00	-14,000.00
Contra Accounts	D1ROGSM	Mr. Roger Smith,T860010 Output VAT - 15%			
2024/03/20	IN000008	Drill press		2,000.00	-16,000.00
Contra Accounts	D1ROGSM	Mr. Roger Smith,T860010 Output VAT - 15%			
2024/03/20	IN000007	Compressor		1,500.00	-17,500.00
Contra Accounts	D1MDAVI	Mr. Mike Davies,T860010 Output VAT - 15%			

Total: *G010000 Sales 0.00 17,500.00

2025/02/28 -17,500.00

View the "*General ledger transactions – Extra details*", for "*Cost centre A1*" selected, for the "*Sales*" account:



General ledger transactions - Extra details

General ledger transactions - Extra details

Period: 2024/03/01 - 2025/02/28 -> Cost centre 1: Cost centre A1

From: G010000 — Include zero balances: No
To: G999000 — New page per account: Yes

***G010000 Sales** 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/09	******	Install - Built-in cupboard		1,500.00	-1,500.00
Contra Accounts	D1MACDS	MAC Shop Decor Specialists ,T860010 Output VAT - 15%			
2024/03/12	******	Install - Built-in cupboard		1,500.00	-3,000.00
Contra Accounts	D1MDAVI	Mr. Mike Davies ,T860010 Output VAT - 15%			
2024/03/17	N000005	Drill press		1,000.00	-4,000.00
Contra Accounts	D1MDAVI	Mr. Mike Davies ,T860010 Output VAT - 15%			
2024/03/18	N000006	Compressor		3,000.00	-7,000.00
Contra Accounts	D1ROGSM	Mr. Roger Smith, T860010 Output VAT - 15%			
2024/03/20	N000008	Drill press		2,000.00	-9,000.00
Contra Accounts	D1ROGSM	Mr. Roger Smith, T860010 Output VAT - 15%			
2024/03/20	N000007	Compressor		1,500.00	-10,500.00
Contra Accounts	D1MDAVI	Mr. Mike Davies ,T860010 Output VAT - 15%			

Total: *G010000 Sales 0.00 10,500.00

2025/02/28 -10,500.00

View the "*General ledger transactions – Extra details*", for "*Cost centre B1*" selected, for the "*Sales*" account:



General ledger transactions - Extra details

General ledger transactions - Extra details

Period: 2024/03/01 - 2025/02/28 -> Cost centre 1: Cost centre B1

From: G010000 — Include zero balances: No
To: G999000 — New page per account: Yes

***G010000 Sales** 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/07	******	Paint - Exterior		1,000.00	-1,000.00
Contra Accounts	D1ABGRE	Mr. A B Green, T860010 Output VAT - 15%			
2024/03/10	******	Paint - Exterior		1,000.00	-2,000.00
Contra Accounts	D1ABGRE	Mr. A B Green, T860010 Output VAT - 15%			
2024/03/13	N000001	Paint - Exterior		1,000.00	-3,000.00
Contra Accounts	D1ABGRE	Mr. A B Green, T860010 Output VAT - 15%			
2024/03/14	N000002	Install - Built-in cupboards		1,500.00	-4,500.00
Contra Accounts	D1MACDS	MAC Shop Decor Specialists ,T860010 Output VAT - 15%			
2024/03/15	N000003	Paint - Exterior		1,000.00	-5,500.00
Contra Accounts	D1ABGRE	Mr. A B Green, T860010 Output VAT - 15%			
2024/03/16	N000004	Install Built-in Cupboards		1,500.00	-7,000.00
Contra Accounts	D1MDAVI	Mr. Mike Davies ,T860010 Output VAT - 15%			

Total: *G010000 Sales 0.00 7,000.00

2025/02/28 -7,000.00

Balances – Ledger Transactions - Sales account

The "Sales" account balance for the actual posted (updated to the ledger) transactions (in Batches and Documents); is as follows:

Total Sales (including "Cost centre A1" and "Cost centre B1") *17 500*

Only "Cost centre A1" *10 500*

Only "Cost centre B1"	*7 000*

The Cost of Sales account has transactions of 4 500 for "Cost centre A1", as no trading stock items were sold by "Cost centre B1"

Debtors / Creditors → Transactions

The following transaction reports for Debtors may be printed for Cost centres:

1. Debtor - Transactions
2. Debtor - Transactions - Standard
3. Debtor - Transactions - Extra details
4. Debtor - Transaction list
5. Debtor - Transaction list - Open item

Creditor reports will not be discussed in this document, since creditor reports are similar to debtor reports.

The following transaction reports for Creditors, may be printed for Cost centres:

1. *Creditor - Transactions*
2. *Creditor - Transactions - Standard*
3. *Creditor - Transactions - Extra details*
4. *Creditor - Transaction list*
5. *Creditor - Transaction list - Open item*

Balances – Debtor Transactions

The "Debtor's control" account balance for the actual posted (updated to the ledger) transactions (in batches and documents); is as follows:

Total Debtor's control (including "Cost centre A1" and "Cost centre B1")	*20 125*
Only "Cost centre A1"	*12 075*
Only "Cost centre B1"	*8 050*

Debtor – Transactions report

The "*Debtor transactions*" report lists all the transactions in documents and batches which are posted (updated) to the ledger for any specific period(s).

This report will include opening balances (closing balances before the selected periods / dates).

In addition to this, the following two (2) reports may be printed:

- Debtor transaction list - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.
- Debtor transaction list - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. If a debtor (customer / client) account is set as Open item account (Debtor - Accounting information tab on the Default ribbon), it will list only those transactions with outstanding amounts. Any credit amounts, which are not linked to debit transactions, should be processed in "*Open item link*" (Default ribbon).

To print Debtor transaction reports:

1. On the Reports ribbon, select Reports → Debtors → Transactions.
2. Select the "*Debtor transactions*" report.



3. Select the following options:
    a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

b) From account / To - Select a debtor account or a range of debtor accounts, to include in the report.

c) Sequence - Select "*Debtor*" to print the report by account code or "*Description*" to print the report by account description (name). You may also select "*Reporting group 1*" or "*Reporting group 2*" to print the accounts according to the "*Debtor group 1*" or " *Debtor group 2*" as added in Setup → Groups (Setup ribbon) and linked to the Debtor (Default ribbon).

d) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

e) Cost centre 1 - Will be listed, as Cost centres have been added to "*Cost centre* 1" (Setup → Groups (Setup ribbon)). You may select these Cost centres, to include in the report.

f) Cost centre 2 – The "Empty" tick box and no cost centres will be listed, since no Cost centres were added in "*Cost centre 2*" (Setup → Groups (Setup ribbon)).

4. Click on the OK button.

Balances – Debtor Transactions

The "Debtor's control" account balance for the actual posted (updated to the ledger) transactions (in batches and documents); is as follows:

Total Debtor's control (including "Cost centre A1" and "Cost centre B1")	*20 125*
Only "Cost centre A1"	*12 075*
Only "Cost centre B1"	*8 050*

The "*Debtor transactions*" report, no Cost centres selected, should be displayed as follows:



The "*Debtor transactions*" report, "*Cost centre A1*" selected, should be displayed as follows:



Balances – Debtor Transactions – "Cost centre A1"

The account balances for the actual posted (updated to the ledger) transactions (in Batches and Documents); is as follows:

Total Debtor's transactions for "Cost centre A1"	*12 075*
"MAC Decor Specialists"	*1 725*
"Mike Davies"	*4 600*
"Roger Smith"	*5 750*

The "*Debtor transactions*" report, "*Cost centre B1*" selected, should be displayed as follows:



Balances – Debtor Transactions – "Cost centre B1"

The account balances for the actual posted (updated to the ledger) transactions (in Batches and Documents); is as follows:

Total Debtor's transactions for "Cost centre B1" *8 050*

"MAC Decor Specialists" *1 725*

"AB Green" *4 600*

"Mike Davies" *1 725*

Debtor - Transactions - Standard / Extra Details

The "*Debtor transactions - Extra details*" report is similar to the "*Debtor transactions - Standard*" report, but displays extra details of the Contra accounts (i.e. Account code, Account description, Contra account code and Description as well as the Tax account code and Description). For example,

" G010000 Sales,T860010, Output Tax" - 15%", etc.

Balances – Debtor Transactions

The "Debtor's control" account balance for the actual posted (updated to the ledger) transactions (in batches

and documents); is as follows:

Total Debtor's control (including "Cost centre A1" and "Cost centre B1") 20 125

Only "Cost centre A1" 12 075

Only "Cost centre B1" 8 050

To print Debtor transactions - Standard or Extra details reports:

1. On the Reports ribbon, select Reports → Debtors → Transactions.
2. Select the "*Debtor transactions - Standard*" or "*Debtor transactions - Extra details*" report.



3. Select the following options:

   a) Period - Select a period on the Per period tab. You may click on the Free selection tab to select a specific date or a range of dates to include transactions in the report.

   b) From account / To account - Select a debtor (customer / client) account or a range of debtor (customer / client) accounts, to include in the report.

   c) Sequence - Select "*Debtor*" to print the report by account code or "*Description*" to print the report by account description (name). You may also select "*Reporting group 1*" or "*Reporting group 2*" to print the accounts according to the "*Debtor group 1*" or " *Debtor group 2*" as added in Setup → Groups (Setup ribbon) and linked to the Debtor (Default ribbon).

   d) Include zero balances - If this option is not selected (not ticked), it will list only the transactions for accounts which has transactions and/or balances. Tick this option to include

opening balances (closing balances before the selected periods / dates).

e) New page per account - If this option is selected (ticked), it will print the transactions for each account on a new page.

f) Cost centre 1 - Will be listed, as Cost centres have been added to "*Cost centre* 1" (Setup → Groups (Setup ribbon)). You may select these Cost centres, to include in the report.

g) Cost centre 2 – The "Empty" tick box and no cost centres will be listed, since no Cost centres were added in "*Cost centre 2*" (Setup → Groups (Setup ribbon)).

4. Click on the OK button.

Balances – Debtor Transactions

The "Debtor's control" account balance for the actual posted (updated to the ledger) transactions (in batches and documents); is as follows:

Total Debtor's control (including "Cost centre A1" and "Cost centre B1")	*20 125*
Only "Cost centre A1"	*12 075*
Only "Cost centre B1"	*8 050*

The "*Debtor transactions - Extra details*" report, no Cost centres selected, should be displayed as follows:

Page 1 -


Debtor transactions - Extra details
Debtor transactions - Extra details
Period: 2024/03/01 - 2024/03/31
From: D1ABGRE
To: D1ROG SM
Include zero balances: No
New page per account: No
D1ABGRE Mr. AB Green 2024/03/01 0.00
Date Reference no. Description Debit Credit Cum
2024/03/07 NV001 Paint - Exterior 1,150.00 1,150.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/10 NV003 Paint - Exterior 1,150.00 2,300.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/13 N000001 Invoice /AB-IN110 1,150.00 3,450.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/15 N000003 Invoice /FH-101 1,150.00 4,600.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
Total: D1ABGRE Mr. AB Green 4,600.00 0.00
2024/03/31 4,600.00
D1MACDS MAC Shop Decor Specialists 2024/03/01 0.00
Date Reference no. Description Debit Credit Cum
2024/03/09 NV002 Install - Built-in cupboard 1,725.00 1,725.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/14 N000002 Invoice /IB-101 1,725.00 3,450.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
Total: D1MACDS MAC Shop Decor Specialists 3,450.00 0.00
2024/03/31 3,450.00
D1MDAVI Mr. Mike Davies 2024/03/01 0.00
Date Reference no. Description Debit Credit Cum
2024/03/12 NV004 Install - Built-in cupboard 1,725.00 1,725.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/16 N000004 Invoice /IB-102 1,725.00 3,450.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/17 N000005 Invoice /D-101 1,150.00 4,600.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/20 N000007 Invoice /C-103 1,725.00 6,325.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
Total: D1MDAVI Mr. Mike Davies 6,325.00 0.00
2024/03/31 6,325.00

Page 2 -


Debtor transactions - Extra details
Debtor transactions - Extra details
Period: 2024/03/01 - 2024/03/31
From: D1ABGRE
To: D1ROG SM
Include zero balances: No
New page per account: No
D1ROG SM Mr. Roger Smith 2024/03/01 0.00
Date Reference no. Description Debit Credit Cum
2024/03/18 N000006 Invoice /C-102 3,450.00 3,450.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
2024/03/20 N000008 Invoice /D-102 2,300.00 5,750.00
Contra Accounts G010000 Sales,T860010 Output VAT - 15%
Total: D1ROG SM Mr. Roger Smith 5,750.00 0.00
2024/03/31 5,750.00

The "*Debtor transactions - Extra details*" report, "*Cost centre A1*" selected, should be displayed as follows:



Debtor transactions - Extra details

Period: 2024/03/01 - 2024/03/31 -> Cost centre 1: Cost centre A1

From: D1ABGRE
To: D1ROG SM

Include zero balances: No
New page per account: No

D1MACDS MAC Shop Decor Specialists 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/09	NV002	Install - Built-in cupboard	1,725.00		1,725.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			

Total: D1MACDS MAC Shop Decor Specialists 1,725.00 0.00

2024/03/31 1,725.00

D1MDAVI Mr. Mike Davies 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/12	NV004	Install - Built-in cupboard	1,725.00		1,725.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			
2024/03/17	N000005	Invoice /D-101	1,150.00		2,875.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			
2024/03/20	N000007	Invoice /C-103	1,725.00		4,600.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			

Total: D1MDAVI Mr. Mike Davies 4,600.00 0.00

2024/03/31 4,600.00

D1ROG SM Mr. Roger Smith 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/18	N000006	Invoice /C-102	3,450.00		3,450.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			
2024/03/20	N000008	Invoice /D-102	2,300.00		5,750.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			

Total: D1ROG SM Mr. Roger Smith 5,750.00 0.00

2024/03/31 5,750.00

Balances – Debtor Transactions – Standard / Extra details "Cost centre A1"

The account balances for the actual posted (updated to the ledger) transactions (in Batches and Documents); is as follows:

Total Debtor's transactions for "Cost centre A1" *12 075*

"MAC Decor Specialists" *1 725*

"Mike Davies" *4 600*

"Roger Smith" *5 750*

The "*Debtor transactions - Extra details*" report, "*Cost centre B1*" selected, should be displayed as follows:



Debtor transactions - Extra details

Debtor transactions - Extra details

Period: 2024/03/01 - 2024/03/31 -> Cost centre 1: Cost centre B1

From: D1ABGRE
To: D1ROGSM

Include zero balances: No
New page per account: No

D1ABGRE Mr. AB Green 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/07	NV001	Paint - Exterior	1,150.00		1,150.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			
2024/03/10	NV003	Paint - Exterior	1,150.00		2,300.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			
2024/03/13	N000001	Invoice /AB-IN110	1,150.00		3,450.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			
2024/03/15	N000003	Invoice /FH-101	1,150.00		4,600.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			

Total: D1ABGRE Mr. AB Green 4,600.00 0.00

2024/03/31 4,600.00

D1MACDS MAC Shop Decor Specialists 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/14	N000002	Invoice /IB-101	1,725.00		1,725.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			

Total: D1MACDS MAC Shop Decor Specialists 1,725.00 0.00

2024/03/31 1,725.00

D1MDAVI Mr. Mike Davies 2024/03/01 0.00

Date	Reference no.	Description	Debit	Credit	Cum
2024/03/16	N000004	Invoice /IB-102	1,725.00		1,725.00
Contra Accounts	G010000	Sales, T860010 Output VAT - 15%			

Total: D1MDAVI Mr. Mike Davies 1,725.00 0.00

2024/03/31 1,725.00

Balances – Debtor Transactions – Standard / Extra details - "Cost centre B1"

The account balances for the actual posted (updated to the ledger) transactions (in Batches and Documents); is as follows:

Total Debtor's transactions for "Cost centre B1" 8 050

"AB Green" 4 600

"MAC Decor Specialists" 1 725

"Mike Davies" 1 725

T-Account viewer

Accessing and viewing transactions in the T-Account viewer

Cost centres are included in the posted batch reports and may be printed for selected batches and/or documents (on the Default ribbon) from the following options:

- *Batch entry - Posted batches tab.*
- *Debtor / Creditor from Documents and Transaction tabs.*

Re-allocating Cost centre budgets and transactions

In this example, the "*Rent*" was budgeted and paid for the cost centres as follows:

Cost centre	*Rent - Budget*	*Rent - Expense paid*
Cost centre - A1	*200*	*300*
Cost centre - B1	*300*	*200*

This could possibly indicate the following:

- Budget figures entered incorrectly.
- Expense paid allocated incorrectly.

Editing / changing Cost centre budgets

Budget figures are entered and edited in Budgets (Reports ribbon) or Setup → Accounts (Setup ribbon). In addition to editing / changing budget figures, in these options, you may also change or re-allocate the budget figures in the "*T-Account viewer*".

See - "Enter Budget figures for Cost Centres"

To change / reallocate budget figures for cost centres in the T-account viewer:

1. On the Reports ribbon, select "*Ledger analyser 1*" or "*T- Ledger analyser 2.*
2. Select the *"Trial balance, Income statement, Balance sheet"* or *"Standard column balances"* report type.
3. Tick the "*Budget*" option.
4. Click on the Report button.



5. Select the account and right-click on the selected account (e.g. “*Rent*”).

6. Click on the “*Show details*” context menu.



You may click on the Print button to print the budget figures in the T-Account viewer.

The Batch number is displayed as 0 if the “Budget” option is selected.

The "Show contra" option on the T-Account viewer is not applicable to budget figures.

7. In the “*T-account viewer*” for the selected transaction, right-click on “*CostGroup1*” and select “*Cost centre A1*”.

8. The following confirmation message is displayed:

> “Set reporting group 1”

9. Click on the Yes button to proceed.

10. The budget will be changed from “*Cost centre B1*” to “*Cost centre A1*”.

11. Click on the OK button. The budget, for the selected periods in the "*T-Account-viewer*" for the Fuel and oil expense account for "*Cost centre B1*", will be cleared.
12. Repeat the process for "*Cost centre A1*" for the amount of 200 and allocate to "*Cost centre B1*" .
13. Click Cancel to close "*T-Account-viewer*" screen.

In this example, the budgeted profit will change as this is an Expense account, the net profit for both the cost centres will be changed, e.g.:

- *"Cost centre A1" - Budgeted net profit from 4 050,00 to 3 950,00 (Decrease of 100,00)*
- *"Cost centre B1" - Budgeted net profit from 4 400,00 to 4 500,00 (Increase of 100,00)*

Editing / changing Cost centre transactions

Once transactions have been posted, and an incorrect cost centre has been selected, you may change the cost centre.

It is not necessary to reverse or cancel a posted batch to change the cost centre, if:

- Transaction(s) is not allocated to a cost centre.
- Transaction(s) is allocated to an incorrect cost centre.

For example, a payment of 300,00 for Rent is allocated to the "*Rent*" expense account "*G220-000*" and allocated to "*Cost centre A1*". The 300,00 expense for "*Rent*" is included in all the reports for "*Cost centre A1*".

The allocation to the "*Cost centre A1*" is incorrect and need to be re-allocated to "*Cost centre B1*".

To change transactions for cost centres:

1. On the Reports ribbon, select "*Ledger analyser 1*" or "*Ledger analyser 2.*



2. Select the account and right-click on the selected account (e.g. "*Rent*").

3. Click on the "*Show details*" context menu.

4. In the "*T-account viewer*" for the selected transaction, right-click on "*CostGroup1*" and select "*Cost centre A1*".



You may click on the Print button to print the transactions in the T-Account viewer.

The Batch number is automatically generated (e.g. 10034 for the Rent transactions), when transactions in batches and documents is posted (updated) to the ledger.

You may select the "Show contra" option on the T-account viewer to view the transactions to contra accounts.

These contra accounts will not be printed in the T-account viewer report, but will be included when you export (Export button) these transactions to a spreadsheet.

If the "Budget" option is selected, the Batch number will be displayed as "0".

If you select a cost centre to change, the associated contra accounts and balancing entries, for the selected transaction will be listed in the T-Account viewer.



5. The following confirmation message is displayed:

> "Set reporting group 1"

6. Click on the Yes button to proceed.

7. The balancing entries (indicated by 8 asterisks (********) in the case of posted batches) for the selected transaction will be listed. Both the transaction as well as the balancing entry will be changed from "*Cost centre B1*" to "*Cost centre A1*".

8. Click on the OK button. The transactions in the "*T-Account-viewer*" for the "*Rent*" expense account for "*Cost centre B1*", will be cleared.

9. Click Cancel to close "*T-Account-viewer*" screen.

In this example, as this is an Expense account, the net profit for both the cost centres will be changed, e.g.:

- *"Cost centre A1" - Net profit from 4 080,00 to 4 180,00 (Increase of 100,00)*
- *"Cost centre B1" - Net profit from 6 500,00 to 6 400,00 (Decrease of 100,00)*

Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Projects

Introduction to Projects

osFinancials5/TurboCASH5 provides support for projects, allowing you to effectively track and manage

financial activities and expenses associated with specific projects within your organization.

With osFinancials' project functionality, you can create and define individual projects, assign relevant financial transactions and expenses to each project, and track the financial performance and progress of each one.

This feature enables you to accurately allocate costs, track project-related expenses, and monitor the profitability of each project or job. You can easily generate reports and statements that provide detailed insights into the financial status, budget utilization, and overall performance of your projects or jobs.

By utilizing osFinancials' project capabilities, you can make informed decisions, effectively manage resources, and ensure that your projects are on track financially. This functionality is particularly beneficial for organizations that engage in project-based work, such as construction companies, consulting firms, or any business that needs to track and manage financial activities at a project level.

With osFinancials' support for projects or job costing, you can enhance your financial management processes and gain better visibility into the financial aspects of your organization's projects.

Key features:

- You may create Reporting groups for Projects. These Projects may be activated in batches and documents.
- You may select to process batch transactions and generate sales documents (i.e. Quotes, Invoices and Credit notes) as well as purchase documents (i.e. Orders, Purchases and Supplier returns) for projects.
- You may use the Calendar / Planner to schedule events (appointments) create quotes for hours and convert them to invoices. You may schedule events (appointments) for creditors (suppliers / vendors) as well as up to six (6) categories of appointments with your debtors (customers / clients).

The Bulk time entries feature in the Calendar may be used to schedule and process documents for a selected Project

To check and illustrate the use of Projects in osFinancials5/TurboCASH5, the figures and transactions are based on the following Sets of Books ".../bin/Tutorials/PROJECTS:

1. *PROJECTS-A - Unposted transactions in batches and documents.*
2. *PROJECTS-B - Posted transactions in batches and documents.*

Activate Projects

You need to activate the projects in the Setup → System parameters menu (Setup ribbon).

To activate projects:

1. Click on the Setup → System parameters (Setup ribbon).



2. Select (tick) the "*Projects*" option in the "*Special settings*" section of the screen.

3. Click OK to save your changes.

4. Close the Set of Books and re-open the Set of Books (Start ribbon) again. Projects (Default ribbon) will be activated.



5. The next step is to add your projects to the Project group.

Create Projects

You need to create Reporting groups for Projects. These Projects may be activated in documents and/or specific batches and documents.

Examples of Project Groups

Some examples of reporting groups for projects:

1. Project types: You can create reporting groups based on different types of projects your organization undertakes. For example, you can have reporting groups for Research and Development (R&D) projects, Marketing campaigns, Infrastructure projects, or Client-specific projects. This allows you to track and analyse expenses, revenue, and performance for each project type separately.
2. Project phases: If your projects go through different phases, you can create reporting groups based on these phases. For example, you can have reporting groups for Project Planning, Design, Implementation, Testing, and Completion. This helps in monitoring the progress and expenses incurred during each phase of the project.
3. Project locations: If your projects are carried out in different geographical locations, you can create reporting groups based on these locations. For example, you can have reporting groups for Local projects, National projects, or International projects. This enables you to analyse the performance and expenses associated with projects in each location.
4. Key clients: If you have significant clients or customers for whom you undertake projects, you can create reporting groups based on these key clients. This allows you to track the performance and profitability of projects associated with each client separately.
5. Project managers: If you have multiple project managers overseeing different projects, you can create reporting groups based on these project managers. This helps in monitoring the performance, resource allocation, and profitability of projects managed by each individual.

These examples illustrate how reporting groups for projects in osFinancials5/TurboCASH5 can be used to categorize and analyse project-related data. By assigning projects to appropriate groups, you can track expenses, revenue, resource utilization, and profitability for each project category. This information can assist in project management, decision-making, and resource allocation within your organization.

Create Project Groups

Once the batches and/or documents are posted (updated to the ledger), you may generate various reports for each Project on the "*Sidebar*" of Projects (Default ribbon).

To create Project groups:

1. Click on Setup → Groups (Setup ribbon).
2. Click Projects.



If you have created a Set of Books from scratch (using the "Create Set of Books (Advanced)" option for Firebird database types or the "Create Set of Books (Advanced)" option for MSSQL database types), the Project group will not be available.

You need to manually add the Project group to the TYPES table

See topics in this Help file : -

- *Steps after creating the Set of Books (Advanced) - Add missing Groups and Paper types in the Types table.*
- *Reportman - References - Groups.*

3. To add a new Project to the root directory or list, select the "*REPORTING GROUP ROOT*" on the list and click on the New button.
4. Enter the name of your Project (e.g. "*Project 1A*") and click on "*REPORTING GROUP ROOT*" again.
5. Repeat the process until you have entered all the Projects.
6. Click on the OK button to save your changes and close the "*Groups*" screen.

You may click on the Print button to print a list of your Projects.

You may set the background and font colours for your projects, if necessary.

In addition to this, you may create and set colours for up to 2 reporting groups for "Stock group 1", "Stock group 2" and/or "Document group 1", " Document group 2".

The next step is to create your projects and link the projects to the Project groups.

Create / Add New Projects

Add new projects

To create a project:

1. Click on Projects (Default ribbon). The "*Projects*" screen (list view) is displayed:



2. Click on the New button. A new "*Project code*" 8-digit numerical code, e.g. ("*00000001*") will automatically generated. The "*Projects*" screen will change as follows:



3. Enter or select the following:

a) Code – This code is automatically generated. When clicking on the New button, it will automatically generate the next Project code.

> *You may overtype the Project code with your own code. This code may be alpha numerical. Up to 8 characters is recommended.*

b) Enabled – This is by default selected (ticked).

> *You will not be allowed to close a project (remove the tick in the "Enabled" field) and click on the Save button, if there are any unposted documents.*

c) Description – Enter the name or a description for the Project.

d) Start date – Enter or select a date on which the Project commences.

e) To – Enter or select a date on which the Project ends (should be completed).

f) Status – Select a Project from the list (added / created in Projects (Groups on the Setup ribbon).

g) Budget – Enter the budget (estimated project cost) for the Project.

> *Budget figures for projects may also be added for selected accounts in Accounts (Setup ribbon).*

h) Debtor – Select a default debtor (customer / client) account.

> *If the default debtor (customer / client) account is selected, the Project Quote tab will be added.*

You may need to add a default debtor (customer / client) account in Debtor (Default ribbon).

4. Click on the Save button to save the record (Project). The Project will be added to the list.

If the default debtor (customer / client) account is selected, purchase documents (Purchases, Supplier returns and Orders) and sales documents (Invoices, Credit notes and Quotes) for the Project can only be processed for the default debtor (customer / client) account.

To remove a selected default debtor (customer / client) account, click on the Lookup icon on the "Debtor" field and enter a space and close the Lookup screen. The default debtor (customer / client) account as well as the Project Quote tab will be removed.

Project Screens Overview

Project list screen

This screen will list all projects created with the New button and as edited with the Edit button will be listed.



The details of this screen, is as follows:

1. Sidebar

    a) New – Add or create a new project.

    b) Delete – Delete a selected project.

    c) Edit – Edit a selected project.

d) Save – Save changes to selected project.

e) Cancel – Aborts any changes without saving any edited / changed details of a selected project

2. Reports – Select and print the following reports:

a) Transactions – Prints the transactions of documents and batches which is posted (updated) to the ledger.

b) Hours – Prints the Hours report for documents created / edited for the Hours event and Invoices created for debtor (customer / client) appointments.

c) Stock items – Prints the details of each stock item

d) Statements – Prints the statement of the project.

e) Totals – Prints the summary of the project totals

3. Search / Filter – Search for a project by project code or project description. You may also filter by selecting specific project groups.

4. Columns – List the projects.

a) Code – Project code

b) Description – Project description

c) Start date – The date entered or selected on which the project commenced.

d) Ends on – The end date entered or selected on which the project will / should be completed.

e) Enabled – "*1*" = Enabled and "*0*" = Disabled.

f) Status – This is the selected group as added on the "*Projects*" option (Groups on the Setup ribbon).

Selected Project screen

The selected project screen allows you to edit a project details and to manage a selected project on the Documents, Transactions and Project Quotes tabs.

Documents tab

The Documents tab, lists all the document types; i.e. purchase documents (Purchases, Supplier returns and Orders) as well as sales documents (Invoices, Credit notes and Quotes) which are processed for the selected Project.

The documents on this list include posted as well as unposted documents.



The options, is as follows:

1. Type – Select a purchase document (Purchase, Supplier return or Order) or a sales document (Invoice, Credit note or Quote).
2. New – Create a new document for the selected document type.
3. Edit – Opens the selected document on the list in the "*Document entry*" screen.
    a) Unposted document – You may edit the document, if necessary.
    b) Posted document – This document cannot be edited.

The "Reference" column displays the reference as added in the "Your reference" field in the Document header.

Transactions tab

Only the transactions in documents and/or batches, which are posted (updated) to the ledger, will be listed.



These posted (updated) transactions will be included in the "Transactions" report.

The transactions will be listed in the "*Debit*" or "*Credit*" sections. A brief summary of the transactions in the "*Debit*" or "*Credit*" sections, is as follows:

1. Debit – Invoices and Supplier return documents will be listed for the Debtor or Creditor account. The contra accounts (e.g. Sales and Stock control and Tax accounts) will be listed in the "*Credit*" credit section.

2. Credit – Credit notes and Purchase documents will be listed for the Debtor or Creditor account. The contra accounts (e.g. Sales and Stock control and Tax accounts) will be listed in the "*Debit*" credit section.

*Balancing entries for posted (updated) transactions in batches, is displayed as 8 asterisks (e.g. "********").*

Context menu

Right-click on selected transactions to access the context menu.



- Delete selected transaction(s) from a project.

- Add selected transaction(s) to a project.

SEE - REMOVE / ADD PROJECT TRANSACTIONS

Note if a document, e.g. "D000001" is processed in the Project Quote tab of the selected project, it is included in the "All" document types selection on the "Update ledger" screen.

If you have posted (updated) the ledger using the "All" document types selection on the "Update ledger" screen, these Project Quotes may post incorrect transactions to the ledger.

These "Project Quotes" will then be listed in the Transactions tab.

Project Quote tab

SEE - PROJECT QUOTES – KNOWN ISSUES

The Project Quote tab will only be activated, if a Debtor account is selected.



The options, is as follows:

1. New – Create a new "*Project Quote*" for the selected document type.
2. Edit – Opens the selected "*Project Quote*" on the list in the "*Document entry*" screen.
    a) Unposted document – You may edit the document, if necessary.
    b) Posted document – This document cannot be edited.

Note if a document, e.g. "D000001" is processed in the Project Quote tab of the selected project, it is included in the "All" document types selection on the "Update ledger" screen.

If you have posted (updated) the ledger using the "All" document types selection on the "Update ledger" screen, these Project Quotes may post incorrect transactions to the ledger.

The "Reference" column displays the reference as added in the "Your reference" field in the Document header.

DOCUMENT PROCESSING FOR PROJECTS

The following options are available to process transactions in purchase documents (Purchases, Supplier returns and Orders) and sales documents (Invoices, Credit notes and Quotes) for Projects:

1. Projects (Documents tab)
2. Document entry
3. Calendar:
    - Hours event
    - Create Invoices for debtor (customer / client) appointments.

Selecting Project for Documents:

When processing documents from the Documents tab of a selected Project, the option to select a Project in the Document head available. The project code is automatically linked to the selected Project.



When processing documents, launched from Documents (Default ribbon), you may select a project in the Document header se

If any project is already associated with a selected document, the Project will be automatically displayed.



Create Project Quotes

You may create a quote or quotes for a project.

The Project Quote tab will only be activated, if a Debtor account is selected for the project.

Quotes may be processed on the Documents tab of a selected project.

Quotes may also be processed from Documents (Default ribbon).

The "Quotes" on the Project Quote tab will not be included on the Documents tab of the selected project.

The "Quotes" on the Project Quote tab will be included as Projects on the "Stock items" and "Statements" reports.

To create a project quote:

1. On the Default ribbon, select Projects.
2. Select a project from the list.
3. Click on the Project Quote tab.

The Project Quote tab will only be activated, if a Debtor account is selected.



4. Click on the New button.



5. Enter a reference in the "*Your reference*" field.

> *The reference number is added to projects and is useful when searching for a specific document or a project.*

6. Check and edit the messages in the "*Message*" field, if necessary.

7. Select the "*Stock item*" and check the rest of the fields.

Additional information may be added to stock items on documents:

- *Remarks – Add remarks on the + icon before the stock item.*
- *Comments – F9:Comment to add comments to a stock item.*

8. Click OK to close and save the Quote. The Quote will be added to the Project Quote tab of the selected project.

9. Click on the Yes button to print the quote.



If the Project Quote is printed on the Universal layout files, for all document types, it will display "Projects" as the document name instead of "Quote".

"Projects" as the Document type will be displayed, if the Layout file on Setup → Documents setup on the (Setup ribbon) or on the "Layout file 3" field on the Delivery address tab of Debtor accounts (Default ribbon) is selected, as "Layout file", or the following "Document layout" files is selected:



10. After checking or editing the project quote, the "*Document entry*" screen will be displayed, listing the "*Project Quote*".



11. Click on the Close button or the Cancel button to close and exit the "*Document entry*" screen.

These project quotes will not be listed, if the "Document entry" screen is accessed from Documents on the Default ribbon.

The default document number for is prefixed with a "D" followed by a 6-digit numerical number; e.g. ("D000001"). The "Project Quote" document number cannot be changed.

The default document numbers is set to begin with 000001 (prefixed by 2 alphabetical characters IN for Invoices, CR for Credit notes, PU for Purchase documents, SR for Supplier returns documents, OR for Orders and QU for Quotes).

These document number pre-fixes will automatically be used in Projects if documents are processed from the Documents tab or on the Documents (Default ribbon).

Create Documents for a Project

Once a Projects is activated and Project codes are created, all purchase documents (Purchases, Supplier returns and Orders) and sales documents (Invoices, Credit notes and Quotes) could be processed as follows:

- For a selected Project in Projects (Default ribbon)
- Any new documents may also be created (generated) in the Documents (Default ribbon). You may then select the Project code.
- If any documents have not yet been posted, you may select and process them in the normal Documents option Documents (Default ribbon). You may then edit them and select a different project.

If the default debtor (customer / client) account is selected for the Project, purchase documents (Purchases, Supplier returns and Orders) and sales documents (Invoices, Credit notes and Quotes) for the Project can only be processed for the default debtor (customer / client) account. The Debtor accounts or Creditor accounts screens will not be displayed.

If the "No print confirmation" setting in the Stock information (Setup ribbon) is not selected (not ticked), the confirmation message "Do you wish to Print the Invoice now?" will be displayed. Click on the Yes button to print the Invoice (or on the No button not to Print the Invoice at this stage).

To create documents for a selected project:

1. On the Default ribbon, select Projects.
2. Select a project from the list.
3. Click on the Documents tab.



4. On the "*Type*" field, select a purchase document (Purchase, Supplier return or Order) or sales documents (Invoice, Credit note or Quote).

5. Click on the New button.



6. Enter a reference in the "*Your reference*" field.

> *The reference number is added to projects and is useful when searching for a specific document or a project.*

7. Check and edit the messages in the "*Message*" field, if necessary.

8. Select the "*Stock item*" and check the rest of the fields.

Additional information may be added to stock items on documents:

- *Remarks – Add remarks on the + icon before the stock item.*
- *Comments – F9:Comment to add comments to a stock item.*

9. Click OK to close and save the Invoice. The Invoice will be added to the Documents tab of the selected project.

10. Click on the Yes button to print the Invoice.



11. After checking or editing the project quote, the "*Document entry*" screen will be displayed, listing the "*Project Invoice*".



12. Click on the Close button or the Cancel button to close and exit the "*Document entry*" screen.

Create Invoices in the Calendar for Projects

The Calendar / Planner allows you to create invoices for Projects. The following options are available:

1. Hours – Create quotes for a selected debtor (customer / client) account. The quote will be added to the Documents tab of a selected Project. The quotes may be edited and converted to an Invoice.
2. Create invoices for scheduled debtor (customer / client) appointments. You may create up to 6 categories of debtor (customer / client) appointments.

Once the quotes or invoices are generated, and the project is selected, these documents will be added to the Documents tab of a selected Project.

Create Invoices for Hours

Should you need to invoice a debtor (customer / client) for services rendered on an hourly basis (e.g. consulting, etc.), you may use the "*Hours*" category to schedule and process quotes (invoices) with a few mouse-clicks. The Calendar (Planner) is the electronic diary, time sheet, which integrates the billing of your debtors (customers / clients).

This option generates Quotes and not Invoices. The reason for this, is:

- *Quotes are used to schedule the hourly services in the future.*

- *Once the service is rendered, the Quotes are edited and confirmed (converted to Invoices).*

You may also view and print the Invoice on the Documents tab of the Debtor account (Debtors on the Default ribbon). Once the Invoice is posted (updated to the ledger), it will be listed as a debit transaction on the Transactions tab of the Debtor account.

You may also select a specific person (salesperson) which will render these services.

Processing Invoices for Hours

If you use the "*Hours*" category to schedule and process quotes, for your debtors (customers / clients), it will create quotes when you create invoices for hours. These quotes need to be confirmed and converted to an invoice.

To process invoices for hours:

1. If the Calendar is not automatically displayed, click on the Calendar (Default ribbon).
2. Select the day and a time slot to schedule the hours and right-click on a time slot.
3. On the context menu, select the "*Add Event...*" option. The "*Untitled – Event*" screen will be displayed.



4. On the "*Untitled Event*" screen, enter and/or select the following:

    a) Subject - Leave blank. This will automatically be filled in with the debtor (customer / client) account code, description and Salesperson when selecting it.

b) Category - Select "*Hours*" (Magenta colour).

c) Hours - Click on the Hours field. Select a debtor customer account.

d) Projects - Empty is the default project. Select a project from the list.

e) Salesperson- Select a salesperson.

f) All day event - Leave blank.

g) Start time - This is the date and time as selected on the Calendar from where the "*Untitled - Event*" screen was launched. If this date is not correct, you may select the correct date. Enter or select the time slot, if not correct.

h) End time - Enter the time expected to finish the project.

i) Appointment recurrence - The default is "*None*". Cannot be selected for Hours.

j) Repeat until - Field disabled. Cannot be selected for Hours.

k) Reminder - You may activate it and set the "*Minutes*", "*Hours*" or "*Days*" to remind you in advance to process invoices for hours.

> *The Subject in the Titlebar will display the debtor (customer / client) account code and name, the name of the salesperson as well as the Project code and description.*

l) Notes - You may enter notes below the "*Reminder*" section of the "*Event*" screen (e.g. "*Paint – white exterior – 6 hours*"), etc.

> This additional information will be displayed in the "Notes" column on the Appointment tab for the debtor (customer / client) account (Debtor on the *Default ribbon*).

5. Click on the OK button to register and save the "*Hours*" event.

> *The Subject in the Titlebar will display the debtor (customer / client) account code and name, the name of the salesperson as well as the Project code and description.*

6. On the Calendar topbar, click on the Create invoices for hours button.



The following options screen is displayed:



7. Select the date from and date to in which the hourly rate is to be charged (e.g. 2022/05/11).
8. Click on the Lookup icon and select the stock item.
9. Click on the OK button to create the quote. The information screen "*Quote(s) generated*" will be displayed.
10. Click on the OK button.

This Quote may be viewed on the following options:

Document Entry screen as Unposted (i.e. Not converted to an Invoice).

- *Projects (Default ribbon) on the list of a selected Project.*
- *Documents tab of the Debtor account (Default ribbon). Once the Quote is confirmed (converted to an invoice and the Invoice is posted (updated to the ledger), it will be listed as a debit transaction on the Transactions tab of the Debtor account.*

You may need to edit the quote, e.g. add comments, change the hours, etc. change the Project code, before converting it to an Invoice.

Edit / Convert Quotes to Invoices

Once quotes are generated for the "*Hours*" events n the "Calendar" for debtor (customer / client) accounts, you may convert these quotes to invoices.

To convert the quote for hours to invoices:

1. Exit or close the Projects (if active).
2. On the Default ribbon, select Documents.
3. Select "*Quote*".



4. Select the specific "*Quote*" and right-click. On the context menu, select Documents → Confirm quotes and orders.

5. A confirmation message is displayed:

> "Do you wish to: (1) Quote Confirmation"

6. Click Yes. Another confirmation message "Do you wish to delete this Quote?"

7. Click No.

> *If you click on Yes, the Quote will be removed from the "Document entry" screen as well as the Documents tab on the selected Project.*

8. Another confirmation message is displayed:

> "Document(s) created! IN000003 PR-PAINT2 1ROGSM Mr. Roger Smith"

9. Click OK.

To edit the converted invoice for hours:

1. Exit or close the Projects (if active).

2. On the Default ribbon, select Projects or Documents.

3. Select the "*Invoice*".



> *This Invoice is selected from the Documents tab on the selected Project.*
>
> *If the Invoice was selected from the Document entry" screen, the Project may be changed.*

4. Enter a reference in the "*Your reference*" field.

> *The reference number is added to projects and is useful when searching for a specific document or a project.*

5. Check and edit the messages in the "*Message*" field, if necessary.
6. Edit the rest of the fields as necessary, if required.
7. Click OK to close the Invoice.

Creating Invoices for Debtor Appointments

Once up to 6 categories of debtor (customer / client) appointments have been scheduled, you may create invoices.

Schedule Debtor Appointments

To schedule debtor appointments:

1. If the Calendar is not automatically displayed, click on the Calendar (Default ribbon).
2. Select the day and a time slot to schedule the debtor (customer / client) appointment and right-click on a time slot.
3. On the context menu, select the "*Add Event...*" option. The "*Untitled – Event*" screen will be displayed.



4. On the "*Untitled Event*" screen, enter and/or select the following:
5. Subject - Leave blank. This will automatically be filled in with the debtor (customer / client) account code, description and salesperson when selecting it.
6. Category – Select any of the 6 categories of Debtor appointments.
7. Hours - Click on the Hours field. Select a debtor customer account.

8. Projects - Empty is the default project. Select a Project from the list.
9. Salesperson- Select a salesperson.
10. All day event - Leave blank.
11. Start time - This is the date and time as selected on the Calendar from where the "*Untitled - Event*" screen was launched. If this date is not correct, you may select the correct date. Enter or select the time slot, if not correct.
12. End time - Enter the time expected to finish the project.
13. Appointment recurrence - The default is "*None*".
14. Repeat until - Field disabled. If any other option than "*None*" on the "*Appointment recurrence*" field is selected, you may select or enter a date.
15. Reminder - You may activate it and set the "*Minutes*", "*Hours*" or "*Days*" to remind you in advance to process invoices for hours.
16. Notes - You may enter notes below the "*Reminder*" section of the "*Event*" screen.

> *This additional information will be displayed in the "Notes" column on the Appointment tab for the debtor (customer / client) account (Debtor on the Default ribbon).*

17. Click on the OK button.

> *The Subject in the Titlebar will display the debtor (customer / client) account code and name, the name of the salesperson as well as the Project code and description.*

18. Click on the OK button to register and save the "*Debtor appointment*" event.

Create Invoices for Debtor appointments

Once the Debtor appointment is scheduled, you may create an invoice.

To process invoices for debtor appointments:

1. If the Calendar is not automatically displayed, click on the Calendar (Default ribbon).
2. Select the day and a time slot in which any of the 6 categories for debtor (customer / client) appointments is scheduled, and right-click.



3. On the context menu, select the "*Create Invoice*" option. A new "*Invoice*" screen for the selected debtor (customer / client) will be displayed.



4. Select the Project from the list in the "*Projects*" field.

5. Enter a reference in the "*Your reference*" field.

> *The reference number is added to projects and is useful when searching for a specific document or a project.*

6. Check and edit the messages in the "*Message*" field, if necessary.

7. Edit the rest of the fields as necessary, if required.

8. Select the "*Stock item*" and check the rest of the fields.

> *Additional information may be added to stock items on documents:*
>
> - *Remarks – Add remarks on the + icon before the stock item.*
> - *Comments – F9:Comment to add comments to a stock item.*

9. Click OK to close and save the Invoice. The Invoice will be added to the Documents tab of the "*Project*" screen.

Update (Post) Documents to the Ledger

Once the documents for the project is processed, you may update (post) the documents to the ledger.

Once the documents are updated (posted) to the ledger, these documents will be added to the Transactions tab of the project(s).

To post or update your documents:

1. On the Default ribbon, select Update ledger (F3). The "*Update Invoice"* screen will be displayed.



2. Select each document type *(i.e. "Purchase, Supplier return, Invoice" and "Credit note").*

DO NOT SELECT the "All" option. If the "All" option is selected, the Project Quote will also be posted (updated) to the ledge

It will incorrectly post (update) transactions as follows:



Note document "D000001" is processed in the Project Quote tab of the selected project, and only included in the "All" document types selection on the "Update ledger" screen.

SEE - PROJECT QUOTES – KNOWN ISSUES

3. Click on the Update button for each document type *(i.e. "Purchase, Supplier return, Invoice" and "Credit note")*.

Note if a document, e.g. "D000001" is processed in the Project Quote tab of the selected project, it is included in the "All" document types selection on the "Update ledger" screen.

If you have posted (updated) the ledger using the "All" document types selection on the "Update ledger" screen, these Project Quotes may post incorrect transactions to the ledger.

BATCH (JOURNAL) PROCESSING FOR PROJECTS

By default, projects are not activated in Batches. Projects needs to be activated for each batch, in which you need to process transactions for specific projects.

Activate Projects in Batches (Journals)

Once you have activated Projects in a specific batch, the "*Project*" column will be displayed after the "*Account*" column; and (before the "*Tax*" column, if the "*No tax*" option is not selected on the Advanced tab of the "*Options for this batch*" screen) before the "*Debit*" column.

When processing transactions, you may select the "*Projects*" from the "*Projects*" lookup.

To activate projects in batches:

1. On the Default ribbon, select Batch entry.
2. Select the specific "*Batch type*" in which you need to activate Projects.
3. Click on the F10: Setup icon to set the Options for the selected batch.
4. Click on the Advanced tab.



5. To activate "*Projects*", select (tick) Projects.

6. Click on the OK button. The selected batch entry screen will be opened and the "*Projects*" column will be inserted in the batch.



To deactivate "Projects" in a specific batch, simply repeat this process and remove the tick in the "Projects" tick box.

Process Transactions for Projects in Batches

When processing transactions, you may select the "*Projects*" from the "*Projects*" lookup.

To process transactions in batches:

1. Click on Batch entry (Default ribbon).
2. Select the specific "*Batch type*" in which you need to process transactions for Projects.
3. Enter the transactions and select the Project from the Project lookup.



4. Balance the batch.
5. Click on F8:List to print a list of the unposted transactions in the batch.



6. Click on F6:Post to update the transactions to the ledger.
7. Once the batch transactions are updated (posted) to the ledger, these batch transactions will be added to the Transactions tab of the project(s).

Project Reports

There are five (5) reports available for Projects. These reports are created and maintained in "*Reportman*" accessed in Report designer on the Reports or Setup ribbon.

These reports are stored in the "*...\plug_ins\reports\REPORTS\PROJECTS*" directory, and is follows:

Label ID Description (Report name)

1. TRN_27 Stock Item
2. TRN_354 Statement
3. TRN_960 Total
4. TRN_2330 Hours
5. TRN_20069 Transactions

This will translate depending on your Language selection when launchingosFinancials5/TurboCASH5 for the first time (after installation); or the language selected in the Switch language (Start ribbon).

For example; English (default), en-South Africa, en-UK will refer to "*Stock items*" and if you select the en-American language, it will display as "*Inventory items*" on the list of reports.

To print reports for projects:

1. Click on Projects (Default ribbon). The "*Projects*" screen (list view) is displayed:
2. The "*Projects*" screen (list view) will be displayed.
3. Select a Project.
4. Select a report on the list, and click on the Report button.

The "Stock items" and the "Statements" reports includes documents and/or transactions which are not posted (updated to the ledger).

If a project is not setup / configured correctly, you may encounter the following error messages, when printing reports:

Error - No data to print

"D:\osfinancials5\plug_ins\reports\REPORTS\documents\..\PROJECTS\TRN_20069.rep

has errors No data available to print!"

Errors - No project / Project not setup / configured correctly

"D:\osfinancials5\plug_ins\reports\REPORTS\documents\..\PROJECTS\TRN_27.rep

has errors PROJECT:"" is not a valid integer value"

Project - Transactions

This report will list all transactions in posted batches and/or posted documents. These transactions are listed in the selected project's Transactions tab.

The "Transactions" report does not include documents and/or transactions which are not posted (updated to the ledger).

Page 1 -



Transactions

Projects - Transactions

Code:	PR-PAINT1			**Enabled:**	V
Description:	Project - Paint			**Status**	Project 1A
Start date:	2022/05/01	**Ends on:**	2022/06/30	**Budget:**	6,000.00

Reference	Description	Date	Amount
**G010000 Sales*			
IN000001	Paint - Exterior	2022/05/10	-5,000.00
IN000003	11-05-2022 Russel	2022/05/30	-3,000.00
IN000002	Paint - Exterior	2022/05/30	-500.00
IN000004	Paint - Exterior	2022/05/30	-500.00
CR000001	Paint - Exterior	2022/05/30	3,000.00
	*Total: *G010000 Sales*		*-6,000.00*
D1ROGSM Mr. Roger Smith			
PU000001	Purchases /PR-PAINT2	2022/05/10	-1,150.00
IN000001	Invoice /PR-PAINT2	2022/05/10	5,750.00
CR000001	Credit note /PR-PAINT2	2022/05/30	-3,450.00
IN000002	Invoice /PR-PAINT2	2022/05/30	575.00
IN000003	Invoice /PR-PAINT2	2022/05/30	3,450.00
IN000004	Invoice /PR-PAINT2	2022/05/30	575.00
SR000001	Supplier returns /PR-PAINT2	2022/05/30	1,150.00
5001	Payment received - Thank you	2022/05/31	-1,000.00
	Total: D1ROGSM Mr. Roger Smith		*5,900.00*
G750000 Stock control			
PU000001	Compressor	2022/05/10	1,000.00
SR000001	Compressor	2022/05/30	-1,000.00
	Total: G750000 Stock control		*0.00*
B810000 ABC - Bank			
******	Payment received - Thank you	2022/05/31	1,000.00
	Total: B810000 ABC - Bank		*1,000.00*
T860010 Output VAT - 15%			
IN000001	Invoice /PR-PAINT2	2022/05/10	-750.00
CR000001	Credit note /PR-PAINT2	2022/05/30	450.00
IN000002	Invoice /PR-PAINT2	2022/05/30	-75.00
IN000003	Invoice /PR-PAINT2	2022/05/30	-450.00
IN000004	Invoice /PR-PAINT2	2022/05/30	-75.00
	Total: T860010 Output VAT - 15%		*-900.00*
T860020 Input VAT - Standard rate -15%			
PU000001	Purchases /PR-PAINT2	2022/05/10	150.00
SR000001	Supplier returns /PR-PAINT2	2022/05/30	-150.00
	Total: T860020 Input VAT - Standard rate -15%		*0.00*

Page 2 -



SEE - PROJECT QUOTES – KNOWN ISSUES

Note if a document, e.g. "D000001" is processed in the Project Quote tab of the selected project, it is included in the "All" document types selection on the "Update ledger" screen.

If you have posted (updated) the ledger using the "All" document types selection on the "Update ledger" screen, these Project Quotes may post incorrect transactions to the ledger.

The "*Projects - Transactions*" report will list the details of each transaction for each account.

Finally, the totals of the accounts are summarised for each account type, as follows:

1. Balance - The total of the transactions allocated to balance sheet type accounts.
2. Income statement – The total of the transactions for income received and expenses paid allocated to income statement type accounts.
3. Debtor - The total of all transactions for debtor (customer / client) accounts.
4. Creditor – The total of all transactions for creditor (supplier / vendor) accounts.
5. Cash/Bank entry – The total of the receipt transactions minus payment transactions into and out of Bank accounts and Petty cash accounts.
6. Tax – The total of the Output TAX (VAT/GST/Sales tax) accounts minus the total of the Input TAX (VAT/GST/Sales tax) accounts.

Project – Hours

This report will list the following documents, which have been processed in the Calendar:

- Hours – Create quotes for a selected debtor (customer / client) account. The quote will be added to the Documents tab of a selected Project. The quotes may be edited and converted to an Invoice.
- Create invoices for scheduled debtor (customer / client) appointments. You may create up to 6 categories of debtor (customer / client) appointments.

The report will list the date, start and end time as well as the number of hours spent on a project.

The "Hours" report includes documents and/or transactions which are posted (updated to the ledger).



A similar report may also be printed from the Reports → Calendar menu on the Reports ribbon.



This report will not display the project information.

It will display the minutes instead of hours.



Project - Stock items

This will list the details of the stock items and hours (created via the Calendar).

This will list the totals of all Invoices, Credit notes, Purchases and Supplier returns as well as a list of each of these documents. It will also list the Stock code, Document number, Stock description, Date and Exclusive amount for each stock item selected on a document.

The “Stock items” report includes documents and/or transactions which are posted (updated to the ledger).

Page 1 -



Page 2 -



Projects at the end of this report will list all "Project Quotes" for the selected debtor (customer / client) account, added on the Project Quote tab.

Project – Statements

This will list the totals of all Invoices, Credit notes, Purchases and Supplier returns as well as a list of each of these documents. It will also list all Quotes and/or Orders.

The "Statements" report includes documents and/or transactions which are posted (updated to the ledger).

Page 1 -



Page 2 -



Projects at the end of this report will list all "Project Quotes" for the selected debtor (customer / client) account, added on the Project Quote tab.

Project – Totals

This report will list the totals of transactions (debit and credit) for all accounts selected in posted batches and/or posted documents.

The "Totals" report does not include documents and/or transactions which are not posted (updated to the ledger).



The "*Projects - Total*" report will list the details of each transaction for each account.

Finally, the totals of the accounts are summarised for each account type, as follows:

1. Balance - The total of the transactions allocated to balance sheet type accounts.

2. Income statement – The total of the transactions for income received and expenses paid allocated to income statement type accounts.
3. Debtor - The total of all transactions for debtor (customer / client) accounts.
4. Creditor – The total of all transactions for creditor (supplier / vendor) accounts.
5. Cash/Bank entry – The total of the receipt transactions minus payment transactions into and out of Bank accounts and Petty cash accounts.
6. Tax – The total of the Output TAX (VAT/GST/Sales tax) accounts minus the total of the Input TAX (VAT/GST/Sales tax) accounts.

PROJECT BUDGET

In addition to the Project budget (estimated project cost) for the Project, entered in the "*Budget*" field when a selected project is created and/or edited, budget figures may also be added for selected accounts (Accounts on the Setup ribbon).

Add / Edit Budget for selected accounts

To add / edit budget figures for projects:

1. Click on Accounts (Setup ribbon).
2. Select the Account (or sub-account).
3. Click on the Budget tab (if not displayed by default).



4. Select the period and enter or edit the existing budget figure, if necessary.

5. Click on the button to create a new record.

6. Enter the date and amount.

> *Enter a reference and description. This will print on reports.*

7. Select the project in the "*Project*" column.

8. Click on the button to save the budget record.

9. Repeat the process for each month.

10. Click on the Save (record button).

11. Click on the Save button.

12. Repeat the process for all accounts for which you need to enter budgets for projects.

Print budget figures in the T-Account viewer

1. On the Reports ribbon, select T-Account analyser 1 or T-Account analyser 2.
2. Select the Trial balance, Income statement, or Standard column balances report type.
3. Select (tick) the Budget option.
4. Click on the Report button.
5. Select an account, e.g. "*Sales*", and right-click. On the context menu, click the "*Show details*" option.



6. Click on the Print button.



Search / Find / Print Documents and Transactions for Projects

Debtor accounts

Once documents and/or batch transactions are processed, you may view, analyse, and print transactions and/or documents for a selected debtor (customer / client) account.

The tabs on which documents and/or batch transactions ("*Appointment, Documents, Transactions*" and "*Stock items*") are listed, is briefly discussed.

Similar tabs as for Debtor accounts is also available for Creditor accounts.

Projects tab

By default, any active projects allocated to a debtor (customer / client) account will be listed.



To include inactive (completed) projects, you may select (tick) the "*Show disabled*" field.

The "*Total budget*" displays the amount entered on the "*Budget*" field for a selected project.

Budget figures may also be entered for selected accounts in the Setup → Accounts (Setup ribbon).

The "*Status*" column displays the name of the Project as set in the "Projects" option on Setup → Groups (Setup ribbon).

Appointment tab

The following events added in the Calendar (Setup ribbon), for the selected debtor (customer / client) account, is listed on the Appointment tab:

- Hours – Create quotes for a selected debtor (customer / client) account. The quote will be added to the Documents tab of a selected Project. The quotes may be edited and converted to an Invoice.

- Create invoices for scheduled debtor (customer / client) appointments. You may create up to 6 categories of debtor (customer / client) appointments.



The project code and description will be displayed after the salesperson, e.g. "Russell".

This detail will be included the Hours report, printed in Projects (Default ribbon) and Reports → Calendar (Reports ribbon).

Documents tab

All documents processed for the selected debtor (customer / client) account will be listed. This includes quotes and orders as well as unposted documents.



SEE - PROJECT QUOTES – KNOWN ISSUES

The quote ("D000001"), which was created (processed) in the Project Quote tab (Projects on the Default ribbon), will also be listed.

The "Project Quote" is linked to the "Layout file point-of-sale" on Documents setup (Setup ribbon).

You may select a Quote layout file to print "Project Quote" in the correct layout file.

Note if a document, e.g. "D000001" is processed in the Project Quote tab of the selected project, it is included in the "All" document types selection on the "Update ledger" screen.

The "Show transactions" context menu should not list any transactions on the "Transactions" screen.

If you have posted (updated) the ledger using the "All" document types selection on the "Update ledger" screen, these Project Quotes may post incorrect transactions to the ledger.

Print documents

You may click on the Print (button or double-click) on a selected document to print the document.

Documents will be printed in the default global layout file as set in Documents setup (Setup ribbon), unless it is set on the Delivery address tab of the debtor (customer / client) account (Debtor on the Default ribbon).

You may select a different layout file, if necessary.

Show transactions context menu

Select a posted document on the list, and right-click. The "*Show transactions*" on the context menu, will list the "*Transactions*" screen (e.g. Invoice "*IN000001*")



If a quote or an order as well as a unposted document, is selected, the "Transactions" screen will be blank.

Click on the Print button to view a list of transactions in the "*Batch type report – Posted batch*".



Transactions tab

All transactions which have been processed (posted documents and posted batches) for the selected debtor (customer / client) account will be listed.

It will list transactions as follows:

1. Debit - Documents (i.e. Invoices and POS Invoices), Sales journal, Generate multiple transactions (Interest on overdue debtors, Debtors with charge amount, Fixed amount to all debtors), Opening Balances take-on, etc. It will list any transactions, for which amounts are entered in the "*Debit*" column of batches.

2. Credit - Documents (i.e. Credit notes), Sales returns journal, Receipts journal, Generate multiple transactions (Balance debtors with amount), etc. It will list any transactions, for which amounts are entered in the "*Credit*" column of batches.



See - Open item processing :

By default, the "All" option (tick box) is not selected. If any payment received and credit note transactions were fully linked to invoices, etc. those transactions will not be listed. Only those transactions with outstanding amounts will be listed.

SEE - PROJECT QUOTES – KNOWN ISSUES

Note if a document, e.g. "D000001" is processed in the Project Quote tab of the selected project, it is included in the "All" document types selection on the "Update ledger" screen.

If you have posted (updated) the ledger using the "All" document types selection on the "Update ledger" screen, these Project Quotes may post incorrect transactions to the ledger.

Show transactions button

Click on the "*Show transactions*" button.

You may enter or select a start date and an end date, if necessary.



You may click on the Print button to print the transactions in the T-Account viewer.

The Batch number is automatically generated (e.g. 10054 for the IN00001 transactions), when transactions in batches and documents is posted (updated) to the ledger.

You may select the "Show contra" option on the T-account viewer to view the transactions to contra accounts.

These contra accounts will not be printed in the T-account viewer report, but will be included when you export (Export button) these transactions to a spreadsheet.

Click on the Print button to print the transactions.



Show transactions context menu

Select a document or a batch transaction on the list ("*Debit*" or "*Credit*" section) and right-click. The "*Show transactions*" on the context menu, will list the "*Transactions*" screen (e.g. Invoice "*IN000001*")



Click on the Print button to view a list of transactions in the "*Batch type report – Posted batch*".



Stock items tab

This tab will list all the posted as well as unposted sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders) for the selected debtor (customer / client) account.



The quote ("D000001"), which was created (processed) in the Project Quote tab (Projects on the Default ribbon), will also be listed.

Stock items – Document groups tab

Once documents and/or batch transactions are processed, you may view, analyse, and print documents for

a selected stock item.

This tab will list all the posted as well as unposted sales documents (i.e. invoices, credit notes and quotes) and purchase documents (i.e. purchases, supplier returns and orders) for a selected stock item.



Date	Items	Document no	Description	Price	Discount	Exclusive	Inclusive	Unit price	Units	Description	Number	Name	Document type	Posted
2022/05/30	1	IN000002	Paint - Exterior	500.00	0	500.00	575.00	500.00	1	Hours	1ROGSM	Mr. Roger Smith	Invoice	1
2022/05/30	1	IN000004	Paint - Exterior	500.00	0	500.00	575.00	500.00	1	Hours	1ROGSM	Mr. Roger Smith	Invoice	1
2022/05/30	6	CR000001	Paint - Exterior	500.00	0	3000.00	3450.00	500.00	1	Hours	1ROGSM	Mr. Roger Smith	Credit notes	1
2022/05/30	6	IN000003	11-05-2022 Russell	500.00	0	3000.00	3450.00	500.00			1ROGSM	Mr. Roger Smith	Invoice	1
2022/05/11	6	QU000001	11-05-2022 Russell	500.00	0	3000.00	3450.00	500.00			1ROGSM	Mr. Roger Smith	Quotes	1
2022/05/10	10	IN000001	Paint - Exterior	500.00	0	5000.00	5750.00	500.00	1	Hours	1ROGSM	Mr. Roger Smith	Invoice	1
2022/05/01	10	D000001	Paint - Exterior	500.00	0	5000.00	5750.00	500.00	1	Hours	1ROGSM	Mr. Roger Smith		0
7	40.00					20,000.00	23,000.00							

The quote ("D000001"), which was created (processed) in the Project Quote tab (Projects on the Default ribbon), will also be listed.

You may double-click on a selected document, to print the document.

If the document is printed in the incorrect layout file, for example, a credit note is printed in the invoice layout file, open the selected document from the list.

When the document is closed it will print in the correct layout file for the document type.

Open a posted document

Right-click on a selected document, and on the context menu, select the " *Open document*" option. The selected document entry screen will be displayed.



In the posted document entry screen, the OK button and the processing icons is not displayed.

Open an unposted document



Search - Investigator

The Investigator allows you to search for data in an open Set of Books. To search or locate data, you may enter a valid word or phrase to search for an item. This feature also allows you to define, or refine, or filter the search criteria, and select to view the details for a selected search result.

SERIAL TRACKING - If you have entered a serial number of a product (stock item) as a comment on your sales documents (Invoices, Credit notes and/or Quotes) and/or on purchase documents (Purchases, Supplier returns and/or Orders), you may enter the serial number in the "Search For:" field.

If you click on the Search now button, the Documents will be listed. You may then double-click on the selected document to preview the document.

Comments entered in document lines are searchable.

Remarks is not searchable, but prints on invoices and other documents.

To search for data using the Investigator:

1. On the Default ribbon, select Search.



2. Enter a word or phrase to search for specific data. To filter the data, you may also select to include everything or documents, batches, stock information, account names and/or account information.

3. Click on the Search now button or on the F3:Search icon. The number of items found (which matches the search criteria) will be displayed, and each of the items found will be listed.

4. Select an item type from the search results list and right-click - select "*Show detail*" option on the context menu (or double-click) to launch the options. The types is as follows:

    a) Account - Launch the "*T-Account viewer*" - You may enter the dates from and dates to, as well as any filters (if necessary) to view and filter the transactions. Transactions may be printed and exported to a spreadsheet file.

    b) Debtor / Creditor - Launch the "*Debtor*" accounts screen to edit or check specific details for the debtor (customer / client). If a "*Creditor*" is indicated, it will launch the specific creditor (supplier / vendor) account.

    c) Stock - Launch the "*Stock item*" screen to edit or check specific details for the stock item.

    d) Document - The selected document will be printed.

> *The quote ("D000001"), which was created (processed) in the Project Quote tab (Projects on the Default ribbon), will also be listed.*
>
> *The "Project Quote" is linked to the "Layout file point-of-sale" on Documents setup (Setup*

ribbon).

You may select a Quote layout file to print "Project Quote" in the correct layout file.

e) Batch - Launch the "*T-Account viewer*" - You may enter the dates from and dates to, as well as any filters (if necessary) to view and filter the transactions. Transactions may be printed and exported to a spreadsheet file.

For certain types (e.g. "Account"), the F4:Details icon will be available. If you click on this icon, the balances for general ledger accounts will be displayed.

5. To close or exit this screen, click on the Close button on the title bar.

Further "*Search*" options are available to select from. If you click on the More >> link, the "*Advanced*" options will be available in which the limit for the number of records found may be set.

To refine or filter the search criteria, you may click on the Refine search link.



Remove / Add Project Transactions

Remove Transactions from a Project

The Transactions tab lists all posted (updated) transactions to the ledger.

In this example, Invoice IN000004, needs to be deleted from the project.



To delete a transaction from the project:

1. Select the transaction, in the "*Debit*" section.

> *You may use the Ctrl button and a mouse-click to select more than 1 transaction to remove from the project.*

2. Right-click. On the context menu, select the Delete from project option.

3. A confirmation message is displayed:

> "Do you wish to continue?"

4. Click on the Yes button. The transaction will be removed from the project.

5. In the "*Credit*" section, select the Contra-accounts and repeat the process for the contra-accounts.

This will remove the transactions and the contra-accounts' transactions from the following reports:

1. Transactions

2. Totals

The deleted documents will not be removed, and still be included in the following reports:

1. Stock items

2. Statements

Add Removed Transactions to a Project

Right-click and select the Add to project option on the context menu.

The "*T-account viewer*" screen will be displayed. It will list the transactions which was removed from the project.



Select the transaction(s).

> *You may use the Ctrl button and a mouse-click to select more than 1 transaction to add to the project.*

DELETE PROJECTS

You may delete a project. This will not have any effect on the transactions and/or documents, for the Set of Books.

> *Deleting Projects from your Set of Books cannot be undone.*
>
> *You need to make absolutely sure that the correct Project is selected.*

Delete a Project

To delete a Project:

1. Click on Projects (Default ribbon). The "*Projects*" screen (list view) is displayed:



2. Select the project and click on the Delete button. A confirmation message is displayed:

> "There is document(s) associated with this project! Do you wish to continue ? All project data will be lost!"

3. Click on the Yes button.

4. Another confirmation message is displayed:

> "There is transaction(s) associated with this project! Do you wish to continue ? All project data will be lost!"

5. Click on the Yes button.

6. A final confirmation message is displayed:

> "Do you wish to continue?"

7. If you are absolutely sure, click on the Yes button.

Delete Project Quotes

Once a project is deleted, there may be some Project Quotes which is not deleted.

SEE - PROJECT QUOTES – KNOWN ISSUES

To delete the "Project Quote" documents:

1. On the Default ribbon, select Edit → Delete.

2. Select Documents.



3. Select the document type "*All*".



4. Click the Delete button. A confirmation message,is displayed:

> "Do you want to delete?"

5. Click on the Yes button.

Project Quotes – Known Issues

Print documents in the POS Layout file

The "*Project Quote*" is linked to the "*Layout file point-of-sale*" on Documents setup (Setup ribbon).



Printing the "*Project Quote*" will print by default to the "*POS-STARTSP100*" layout file.



Delete / Remove Transactions Incorrectly Updated in Project Quotes

The "Project Quote - D000001" on the Project Quote tab is posted as an invoice when selecting the "All" option on the Update ledger (Default ribbon).

It is not listed in the Documents – Invoicing (or any other document types, i.e. Quote, Credit note, Purchase or Supplier return):



Identify the posted transactions incorrectly affecting the Set of Books

SEE - Update (Post) Documents to the Ledger

The "*Project Quote - D000001*" on the Project Quote tab is included in the "*All*" option, when documents were posted (updated) to the ledger.



The "*Project Quote - D000001*" on the Project Quote tab is not included in the "*Invoice*," (or other

document types, i.e. "*Credit note*", "*Purchase*" or "*Supplier return*") option, when documents were posted (updated) to the ledger.



The "*Project Quote - D000001*" on the Project Quote tab is posted as an invoice when selecting the "*All*" option on the Update ledger (Default ribbon).

The transactions can be viewed and printed in the "Sales jnl." batch on the "Batch entry" screen – Posted batches tab. The "Sales jnl." is linked to the Invoice document type (Documents setup (Setup ribbon).

To view and print the transactions for the project quote in the sales journal (batch):

1. Click on Batch entry (Default ribbon).
2. Select the specific "*Sales jnl.*"
3. Click on the Posted batches tab. All the posted batches will be listed.



4. Identify and select the batch (e.g. "*10059*" - "*Alias batch name*" (Document number "*D000001*").

5. Double-click on the selected batch. The Details tab will list all the transactions posted (updated) to the ledger.



6. Click on the Print button.



Fix the incorrect posted transactions for the Set of Books

The transactions for the Project Quote, affect the global balances in the Set of Books. These transactions need to be cancelled.



To cancel / reverse the incorrect posted transactions:

1. On the Setup ribbon, select Tools → Global processes → Reverse posted batch/document .



2. On the "*Reverse posted batch/document*" screen, click on the Documents tab.



3. Select the incorrect transaction, i.e. "*Project Quote – D000001*"; and double-click on the selected document. The "Details" tab will list all the posted transactions.



4. Click on the Print button.



5. Click on the Reverse posted document button.

> *A Warning message is displayed:*
>
> "This will radically alter your data! We recommend that you stop and make a backup!"
>
> *Before you click on the Yes button, you need to make absolutely sure that the correct transactions is selected.*

6. Once ready, click Yes. The document will be removed, but not deleted.

7. Close the "*Reverse posted batch/document*" screen.

The document is not available to edit, as is the case with all other documents.

It is available for reposting.



Delete the Project Quote document

To totally remove the “Project Quote” document, you need to delete the document.

To totally delete the “Project Quote” document:

1. On the Default ribbon, select Edit → Delete.
2. Select Documents.



3. Select the document type “*All*”.



4. Click the Delete button. A confirmation message, is displayed:

   "Do you want to delete?"

5. Click on the Yes button.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Blockchain

What is blockchain?

Blockchain is a decentralized digital ledger technology that allows for secure and transparent record-keeping of data across a network of computers. It was originally developed for the cryptocurrency Bitcoin, but has since been adapted for use in many other applications.

In a blockchain network, transactions are recorded in blocks and each block is linked to the previous block in a chain, forming a chronological and immutable record of all transactions that have taken place. This makes it very difficult for any one party to modify or tamper with the data, ensuring that the system is secure and reliable.

Blockchains are typically maintained by a network of nodes, which can be run by anyone with the appropriate hardware and software. Transactions are validated and added to the blockchain by nodes using complex algorithms, and nodes are incentivized to maintain the system through rewards such as

cryptocurrency.

Blockchains have a wide range of potential applications beyond cryptocurrency, including in supply chain management, voting systems, identity verification, and more. They offer a way to securely and transparently store and transmit data without the need for intermediaries, and could have a significant impact on many industries in the coming years.

See video on osFinancials and Blockchain.

Activate Blockchain in osFinancials

Blockchain - By default, Blockchain is not activated. Blockchain needs to be activated in the Setup → System parameters on the Setup ribbon.

On the Setup ribbon, go to Setup → System parameters.



Select (tick) "*Enable Blockchain*".

Click OK.

Reopen the Set of Books to activate Blockchain.

Access Blockchain

Once Blockchain is activated, you may access Blockchain from the Tools → Blockchain menu on the Setup ribbon.



Setting options to launch Blockchain:

Close Set of Books or Exit osFinancials5/TurboCASH5 will automatically launch if the "Check on close books for Admins" setting is selected (ticked).

Check every

- *Always*
- *Every day*
- *Every week*
- *Every month*
- *Every 3 months*
- *Every 6 months*
- *Every 1 year*

Chain data delay

- *Chain all*
- *Chain 1 day ago*
- *Chain 1 week*

- *Chain 1 month*
- *Chain 3 months*
- *Chain 6 months*
- *Chain 1 year*

Blockchain - Data tab

The Data tab will list all posted transactions in batches (journals) and sales documents (i.e. invoices and credit notes) as well as purchase documents (i.e. purchases and supplier returns) in the Transactions table.



ID	ACCOUNTID	WACCOUNTTYPEID	ACC	DATE	REFERENCE	AMOUNT	DESCRIPTION	CURRENCYID	USERID	BLOCKCHAIN
383	28	1	1ROGSM	2022/04/11	IN000008	2300	Invoice /D-102	0	0	
384	68	4	860010	2022/04/11	IN000008	-300	Invoice /D-102	0	0	
385	2	0	100000	2022/04/11	IN000008	1000	*COST OF SALES /D-102	0	0	
386	20	0	750000	2022/04/11	IN000008	-1000	*COST OF SALES/D-102	0	0	
387	13	0	505000	2022/03/01	D5000	-5000	Cash received from owner	0	0	
388	54	1	1ABGRE	2022/03/16	D5001	-2000	Payment received - Thank you	0	0	
389	56	1	1MACDS	2022/03/16	D5001	-1000	Payment received - Thank you	0	0	
390	21	3	810000	2022/03/01	********	5000	Cash received from owner	0	0	
391	21	3	810000	2022/03/16	********	2000	Payment received - Thank you	0	0	
392	21	3	810000	2022/03/16	********	1000	Payment received - Thank you	0	0	
393	31	0	600010	2022/03/01	105	500	1 x Desk	0	0	
394	31	0	600010	2022/03/01	106	300	2 x Chairs	0	0	
395	9	0	220000	2022/03/30	107	500	Rent - April	0	0	
396	53	2	2ABCOS	2022/03/30	108	750	Payment on account	0	0	
397	6	0	210010	2022/03/30	109	150	Petrol - Mercedez Benz	0	0	
398	11	0	230000	2022/03/30	110	200	Waltons - Paper and pens	0	0	
399	58	3	820000	2022/03/30	111	100	Petty cash - Increase float	0	0	
400	70	4	860030	2022/03/01	********	75	1 x Desk	0	0	
401	21	3	810000	2022/03/01	********	-575	1 x Desk	0	0	
402	70	4	860030	2022/03/01	********	45	2 x Chairs	0	0	
403	21	3	810000	2022/03/01	********	-345	2 x Chairs	0	0	
404	69	4	860020	2022/03/30	********	75	Rent - April	0	0	
405	21	3	810000	2022/03/30	********	-575	Rent - April	0	0	
406	21	3	810000	2022/03/30	********	-750	Payment on account	0	0	
407	21	3	810000	2022/03/30	********	-150	Petrol - Mercedez Benz	0	0	
408	69	4	860020	2022/03/30	********	30	Waltons - Paper and pens	0	0	
409	21	3	810000	2022/03/30	********	-230	Waltons - Paper and pens	0	0	
410	21	3	810000	2022/03/30	********	-100	Petty cash - Increase float	0	0	
411	11	0	230000	2022/03/31	PCV001	40	Waltons - Paper	0	0	
412	7	0	210020	2022/03/31	PCV002	10	ABC - Service Station -Fix puncture	0	0	
413	69	4	860020	2022/03/31	********	6	Waltons - Paper	0	0	
414	58	3	820000	2022/03/31	********	-46	Waltons - Paper	0	0	
415	58	3	820000	2022/03/31	********	-10	ABC - Service Station -Fix puncture	0	0	
416	3	0	200000	2022/03/31	BS5	45	Bank charges - Bank statement no.	0	0	
417	21	3	810000	2022/03/31	********	-45	Bank charges - Bank statement no.	0	0	

The details of each transaction will be listed in eleven (11) columns and is as follows:

1. ID - Transaction ID generated for each transaction.

2. WACCOUNTID - Account ID of each account
3. WACCOUNTTYPEID - The Account type Id is as follows:
4. ACC - Account code -
5. DATE - Date of the transaction
6. REFERENCE - The Reference of the transaction as entered in the "*Reference*" column of "Batch entry" screens. Balancing entries (generated when batches is balanced) is displayed with eight (8) asterisks (i.e. ********). In the case of sales documents (i.e. invoices and credit notes) as well as purchase documents (i.e. purchases and supplier returns) as generated when processing documents.
7. AMOUNT - Amount of the transaction.
8. DESCRIPTION - Description as entered in the "*Description*" column of "Batch entry" screens. In the case of sales documents (i.e. invoices and credit notes) as well as purchase documents (i.e. purchases and supplier returns), the Document number as well as the reference entered in the "Your reference" field in the document header.
9. CURRENCYID -
10. USERID -
11. BLOCKCHAIN -

Blockchain - Log tab

Blockchain - Checks tab



Check every

1. Always
2. Every day
3. Every week
4. Every month
5. Every 3 months
6. Every 6 months
7. Every 1 year

Chain data delay

1. Chain all
2. Chain 1 day ago
3. Chain 1 week
4. Chain 1 month
5. Chain 3 months
6. Chain 6 months
7. Chain 1 year

Blockchain - Info tab

Blockchain technology allows you to verify the data is not changed

without the blockchain check failing and it allows external checking of the data integrity.



The first block md5 will be

'00000000000000000000000000000000'

Then in sequence transactions are checksummed using

```
last MD5 + '|' + 'WTRANSACTIONID' + '|' + 'WACCOUNTID + '|' +
 'waccounttypeid'  + '|' + 'ACC'    + '|' + 'DDATE'  + '|' + 'SREFERENCE'+ '|' +
   'FAMOUNT' + '|' + 'SDESCRIPTION'+ '|' + 'WCURRENCYID'
     + '|' + 'WUSERID'
```

Example lines

```
00000000000000000000000000000000|2015|213|2|EASYH|200601040000|jan/01|-33.32|Factuurnummer 35178|0|0
      1069812D4A20E3CAA61C35C458946EE9
1069812D4A20E3CAA61C35C458946EE9|2016|334|2|TILLA|200601110000|jan/02|-150.00|factuurnummer 001|0|0
      15691EC6711430B06F81E55B2C03E054
```

The MD5 hash function was originally designed for use as a secure cryptographic hash algorithm for authenticating digital signatures. But MD5 has been deprecated for uses other than as a noncryptographic checksum to verify data integrity and detect unintentional data corruption.

The MD5 hash function was originally designed for use as a secure cryptographic hash algorithm for authenticating digital signatures. But MD5 has been deprecated for uses other than as a noncryptographic checksum to verify data integrity and detect unintentional data corruption.

Blockchain - Export for audit

Blockchain data can be exported for audit purposes.

One example of this is the use of blockchain explorers, which are web-based tools that allow users to view the data stored on a blockchain in a user-friendly format. These explorers can be used to export transaction data and other information from the blockchain, which can then be analysed and audited by third parties.

For example, a company using a blockchain-based supply chain management system might use a blockchain explorer to export data on all of the transactions that have taken place on the network. This data could then be analysed by auditors to ensure that all of the transactions are accurate and that there are no discrepancies or irregularities.

Another approach to exporting blockchain data for audit purposes is to use specialized audit tools and software that are designed to work with specific blockchain networks. These tools can provide detailed analytics and reporting on blockchain activity, making it easier for auditors to identify potential issues or areas of concern.

Overall, exporting blockchain data for audit purposes requires specialised tools and expertise, but it can be an effective way to ensure the security and reliability of blockchain-based systems.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

Plugins

---

osFinancials5/TurboCASH5 Plugins and Products

osFinancials5/TurboCASH5, is a comprehensive accounting software designed to meet your specific business needs. The osFinancials5/TurboCASH5 Subscription already includes three plugins. (ie; Bank Import, Document Email Pro and Budgets).

Enhance your experience with our suite of products and plug-ins, which can be seamlessly integrated into osFinancials to extend its functionality beyond core features.

Our plugins are categorized into seven main groups: Document plugins, External system links, Financial tools, Generic plugins, Point-of-Sale, Stock plugins, and Tools.

Whether you need enhanced reporting, task automation, industry-specific solutions or integration with other software, our plug-in programs offer flexibility and customization options to tailor osFinancials5/TurboCASH5 to your unique requirements.

Visit our webshop to explore our products, including multi-user options, support, other products and more, and to optimize your osFinancials5/TurboCASH5 experience.

Included in the registered version of osFinancials5/TurboCASH5 - Business Class

osFinancials5 Subscription /TurboCASH Subscription

Process unlimited (more than 500) transactions and documents.

Every time an unregistered version osFinancials5/TurboCASH5 is started, the following confirmation message will be displayed:

> This software is limited to 500 transactions or 500 documents. Please register and buy a licence for osFinancials
> This copy of osFinancials is not registered! Do you wish to register it now?

Unregistered versions will allow you to process up to 500 transactions and /or documents. Once this limit is reached, osFinancials5/TurboCASH5 will not allow any processing of transactions, in batches and/or documents.

Once you have registered osFinancials5/TurboCASH5, you will receive an unlocking code and will be able to process further transactions and or documents.

Bank import

Bank Import Plugin Licence

The Bank Import Plugin is included with the osFinancials5/TurboCASH5 Business class subscription. With a registered osFinancials5/TurboCASH5 Business class subscription, you gain access to import and process unlimited statements for each of your bank accounts.

Upon purchasing the osFinancials5/TurboCASH5 Business class subscription, you will receive an email containing registration (activation) codes and detailed instructions.

For unregistered versions of osFinancials5, a message may appear:

> *"This demo plugin allows %s records to be entered. If you need more, please buy the product at https://www.osfinancials.org/en/webshop".*

We encourage users to support osFinancials by purchasing the osFinancials5/TurboCASH5 Business class subscription. This not only unlocks the full functionality of the Bank Import Plugin but also supports ongoing development and improvements.

For users of osFinancials4, TurboCASH4, the Bank Import Licence is available for purchase from our osFinancials webshop.

Documentation : Help topic.
Documentation : osFinancials website - Bank import plugin -
Documentation : osFinancials website - Bank Reconciliations Plugin

The Bank Import plugin included with the osFinancials5/TurboCASH5 Subscription is a handy tool for managing and processing the transactions in your bank and credit card accounts. You can download electronic bank statement files directly from your online banking services at your bank or financial institution. After that, you can use the Bank Import plugin to import these bank statements into your bank accounts. This process saves you a lot of time and effort as you do not have to manually enter and process the transactions of your bank accounts and credit card accounts in separate Payment journals and Receipt Jjurnals.

Additionally, the Bank Import Plugin has the ability to use bank references to automatically assign transactions to the appropriate accounts, This automation not only saves time, but also reduces the risk of human error associated with manual data entry. Overall, using this Bank Import plugin is a smart choice for businesses or individuals who want to optimize their financial workflow within osFinancials5/TurboCASH5.

Document E-mail Pro

Document E-mail Pro Plugin - Shop - Licence : Included in osFinancials5 Subscription.

Documentation : Help topic.

Documentation : osFinancials website - Document email pro plugin -

Document E-mail Pro Plugin - Streamline your document handling and communication processes with our Document Email Pro Plugin. With a licence which is included in osFinancials5 Subscription, you can effortlessly email invoices, quotes, and more directly from the program.

Customise email layouts to match the document type, ensuring a professional and tailored communication experience for your clients and suppliers. Send multiple documents simultaneously with ease, simplifying your workflow and saving valuable time.

Experience the convenience of sending digital sales and purchase documents in PDF format, enhancing efficiency and communication with customers and suppliers alike. Upgrade your document management with Document Email Pro Plugin.

Budget Plugin

Budget Plugin - Manual - Shop - Licence : Included in osFinancials5/TurboCASH5 Subscription.

Documentation : Help topic.

Effortlessly manage budgets for accounts, cost centres, and projects with the Budget Plugin, now included as a standard feature in the osFinancials5/TurboCASH5 Subscription. Access the Budgets option on the Reports ribbon for seamless integration.

Key Features:

- Flexible Budget Entry: Easily input budgets for accounts, cost centres, and projects directly within the osFinancials5 interface. Copy budget figures from the previous year of actual account balances.
- Comprehensive Budgeting: Cover all aspects of financial planning by setting budgets for various entities, including accounts, cost centres, and projects.
- Integrated Solution: Seamlessly integrate budget management into your overall financial workflow within osFinancials5/TurboCASH5.
- Advanced Filtering and Pivot Options: Utilize advanced filtering and pivot functionalities to analyse budget data effectively and gain deeper insights into your financial performance.

- Streamlined Processes: Simplify budgeting tasks and ensure accuracy by leveraging the intuitive interface and advanced features of the Budget Plugin.
- Comprehensive Reporting: Generate budget listing reports (Trial balance, Income statement, Balance sheet, or Standard column balances report types) and budget performance reports (Budget vs Actual to compare the budget figures versus the actual posted transactions). Export reports to spreadsheets and utilize powerful pivot features for in-depth analysis. Print and export budgets in the T-Account viewer.

Enhance your financial planning capabilities and streamline your budgeting processes with the Budget Plugin, empowering you to make informed decisions and drive financial success within your organisation.

Plugin activation and Plugins menu

1. Activate plugins - Allows you to manage plugins listed in the Plugins menu on the Setup ribbon. Clicking on the Activate plugins button in the Setup ribbon allows you to add plugins to the Plugins menu. To remove a plugin from the menu, click on the Deactivate plugin button.
2. Plugins menu - This menu displays only the activated plugins.
3. Register plugins - Upon purchasing plugin licences, you will receive the licence codes via email along with instructions for activation. Simply add the licence codes provided to access the licenced version of the plugin.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Activate plugins

Plugin activation

Plugins are included in the osFinancials5/TurboCASH5 installation. By default, some Plugins are not available from the Plugins menu on the Setup ribbon.

To add plugins to the Plugins menu, you need to activate the plugins, you require. This will update the "*Plugins load list*". Activated Plugins will be available on the Plugins menu.

To activate plugins:

1. On the Setup ribbon, select Tools → Activate plugins.

2. On the "*Plugin load list*" screen, you may select to activate / deactivate, the plugins you have purchased on the list.



3. Click on the Close button.

4. The selected plugins will be added to the Plugins menu on the Setup ribbon.

5. Plugins needs a licence before these can be activated. Some plugins, if not registered (purchased on the Webshop), can be used for a number of transactions or records only.

Using plugins

Once the plug-ins are activated, you must enable (enable) the plug-ins you purchased in the Plugins menu (Setup ribbon).

Some plug-ins must be activated for each Set of Books in osFinancials5/TurboCASH5.

All plug-ins are enabled in the Tools → Activate plugins (Setup ribbon) and will be available in the Plug-ins menu. However, there are two exceptions:

1. Bank Import Plugin - This plugin must be enabled in the Setup → System parameters (Setup ribbon).

2. Payroll Import Plugin - This plugin is accessed in the Process batch option (F9:Process), provided you have a valid, and you have a valid input file from a supported payroll software.

Start osFinancials5/TurboCASH5 again to fully activate the enabled plugins.

Retrieving plugin licences

To retrieve plugin licences:

1. Go to the Start ribbon (tab). Then click on Online registration.

2. On the "*Register your osFinancials / Register your TurboCASH*" screen, click on the Get it online button.

3. On the next screen, enter your username and password for this website.

4. Then click Send (bottom of screen) and your plugin codes are retrieved from our servers.

5. You will see all the plugins you purchased or plugins you have asked for a trial.

At the bottom of the "Your registration is successful!" with your registration codes section of the "Register your osFinancials / Register your TurboCASH" screen, your purchased plugin(s) will show the name of the plug-in(s) well as the maximum number of times you can retrieve the plug-in(s) and the end date on which the licence expires (in the case of time licence plug-ins) are displayed.

If the counter of the number of remaining times to renew the licence is at 0, then the plugin is blocked. To reset the counter, you can send us an email with the request to reactivate the plugins.

If the plugins are about to expire, you will be notified. osFinancials5/TurboCASH5 will automatically send a quotation for extending the usage period.

This will happen before the actual expiry date.

So if the quotation is paid, the plugin(s) are extended in period after the original expired date.

So you won't need to see the notice messages until the expiry date.

6. Click on the Close button.

You only can use plugins with the serial number/account of the osFinancials account that you purchased the plugins with.

The plugins can not be combined with other plugins purchased using a different account.

This could happen if you have registered multiple-times.

Created with the Standard Edition of HelpNDoc: Upgrade your help files and your workflow with HelpNDoc's WinHelp HLP to CHM conversion

Register plugins

Plugin activation / Plugin menu / Plugin Registration

1. Activate plugins - Allows you to manage plugins listed in the Plugins menu on the Setup ribbon. Clicking on the Activate plugins button in the Setup ribbon allows you to add plugins to the Plugins menu. To remove a plugin from the menu, click on the Deactivate plugin button.
2. Plugins menu - This menu displays only the activated plugins.
3. Register plugins - Upon purchasing plugin licences, you will receive the licence codes via email along with instructions for activation. Simply add the licence codes provided to access the licenced version of the plugin.

Register Plugins

Upon purchasing plugin licences, you will receive the licence codes via email along with instructions for activation. Simply add the licence codes provided to access the licenced version of the plugin.

To register plugins:

1. On the Setup ribbon, select Plugins → Tools → Register plugins.



2. Enter or copy the provided licence code into the designated field.
3. Click on the Add button to register the plugin. The registered plugin will be added to the "*Registered*" list.
4. After registering, click Close. To ensure the registered plugin takes effect, you may need to close and restart osFinancials5/TurboCASH5.

Created with the Standard Edition of HelpNDoc: Effortlessly Create Professional Documentation with HelpNDoc's Clean UI

Plugins menu (Setup ribbon)

Plugins menu structure

Plugins are included in the osFinancials5/TurboCASH5 installation. By default, some Plugins are not

available from the Plugins menu on the Setup ribbon.

The following plugins in the osFinancials5/TurboCASH5 subscription, are activated (updated in the "*Plugins load list*") and will be available on the Plugins menu on the Setup ribbon:

1. Document plugins → Document E-mail Pro

2. Generic plugins → Multimedia

Access to the Plugins menu

On the Setup ribbon, select Plugins.



If the plugins menu is not listing the plugins in your selected language or the language associated with your Set of Books, you can simply open and close the the Activate plugins screen (on the Setup ribbon, select Tools → Activate plugins).

When all Plugins are activated from the Tools → Activate plugins option on the Setup ribbon, the Plugins menu is structured and grouped into seven categories: Document plugins, External system links, Financial tools, Generic plugins, Point-of-Sale, Stock plugins, and Tools.

Any other Plugins, except the Bank import plugin, needs to be activated to be listed on Tools → Activate plugins menu on the Setup ribbon. This will update the "*Plugins load list*".

Some of the Plugins has a nag screen, some plugins are limited to a number of records, etc. Plugins need to purchased from the osFinancials online shop and need to be registered (on the Setup ribbon, select Tools → Activate plugins), before you can use them.

Some plugins need to be activated for each Set of Books. If you have purchased a plugin, you may use it in any Set of Books.

Bank import plugin - Bank Reconciliations Plugin Manual - *BankImport Plugin Manual* - Shop - *Tutorial* - *Licence : Once-off*

- Bundled with theosFinancials5/TurboCASH5 subscription.

The Bankimport plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices.

Needs to be activated on the Setup ribbon, select Setup → System Parameters.

Plugins included in the osFinancials5/TurboCASH5 subscription

Bank import

Bank Import Plugin Licence

The Bank Import Plugin is included with the osFinancials5/TurboCASH5 Business class subscription. With a registered osFinancials5/TurboCASH5 Business class subscription, you gain access to import and process unlimited statements for each of your bank accounts.

Upon purchasing the osFinancials5/TurboCASH5 Business class subscription, you will receive an email containing registration (activation) codes and detailed instructions.

For unregistered versions of osFinancials5, a message may appear:

> *"This demo plugin allows %s records to be entered. If you need more, please buy the product at https://www.osfinancials.org/en/webshop".*

We encourage users to support osFinancials5/TurboCASH5 by purchasing the osFinancials5/TurboCASH5 Business class subscription. This not only unlocks the full functionality of the Bank Import Plugin but also supports ongoing development and improvements.

For users of osFinancials4 / TurboCASH4, the Bank Import Licence is available for purchase from our osFinancials webshop.

Documentation : Help topic.
Documentation : osFinancials website - Bank import plugin -
Documentation : osFinancials website - Bank Reconciliations Plugin

The Bank Import plugin included with the osFinancials5/TurboCASH5 Subscription is a handy tool for managing and processing the transactions in your bank and credit card accounts. You can download

electronic bank statement files directly from your online banking services at your bank or financial institution. After that, you can use the Bank Import plugin to import these bank statements into your bank accounts. This process saves you a lot of time and effort as you do not have to manually enter and process the transactions of your bank accounts and credit card accounts in separate Payment journals and Receipt journals.

Additionally, the Bank Import Plugin has the ability to use bank references to automatically assign transactions to the appropriate accounts, This automation not only saves time, but also reduces the risk of human error associated with manual data entry. Overall, using this Bank Import plugin is a smart choice for businesses or individuals who want to optimize their financial workflow within osFinancials5/TurboCASH5.

Document E-mail Pro

Document E-mail Pro Plugin - Shop - Licence : Included in osFinancials5/TurboCASH5 Subscription.

Documentation : Help topic.

Documentation : osFinancials website - Document email pro plugin -

Document E-mail Pro Plugin - Streamline your document handling and communication processes with our Document Email Pro Plugin. With a licence which is included in osFinancials5 osFinancials5/TurboCASH5, you can effortlessly email invoices, quotes, and more directly from the program.

Customise email layouts to match the document type, ensuring a professional and tailored communication experience for your clients and suppliers. Send multiple documents simultaneously with ease, simplifying your workflow and saving valuable time.

Experience the convenience of sending digital sales and purchase documents in PDF format, enhancing efficiency and communication with customers and suppliers alike. Upgrade your document management with Document Email Pro Plugin.

Budget Plugin

Budget Plugin - Manual - Shop - Licence : Included in osFinancials5/TurboCASH5 Subscription.

Documentation : Help topic.

Effortlessly manage budgets for accounts, cost centres, and projects with the Budget Plugin, now included as a standard feature in the osFinancials5/TurboCASH5 Subscription. Access the Budgets option on the Reports ribbon for seamless integration.

Key Features:

- Flexible Budget Entry: Easily input budgets for accounts, cost centres, and projects directly within the osFinancials5/TurboCASH5 interface. Copy budget figures from the previous year of actual account balances.
- Comprehensive Budgeting: Cover all aspects of financial planning by setting budgets for various entities, including accounts, cost centres, and projects.
- Integrated Solution: Seamlessly integrate budget management into your overall financial workflow within osFinancials5/TurboCASH5.
- Advanced Filtering and Pivot Options: Utilize advanced filtering and pivot functionalities to analyse budget data effectively and gain deeper insights into your financial performance.
- Streamlined Processes: Simplify budgeting tasks and ensure accuracy by leveraging the intuitive interface and advanced features of the Budget Plugin.
- Comprehensive Reporting: Generate budget listing reports (Trial balance, Income statement, Balance sheet, or Standard column balances report types) and budget performance reports (Budget vs Actual to compare the budget figures versus the actual posted transactions). Export reports to spreadsheets and utilize powerful pivot features for in-depth analysis. Print and export budgets in the T-Account viewer.

Enhance your financial planning capabilities and streamline your budgeting processes with the Budget Plugin, empowering you to make informed decisions and drive financial success within your organisation.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Plugins menu - Document plugins

Document EMail Pro Plugin

Document EMail Pro Plugin - Manual - Shop - Licence : Once-off - This Plugin is included in the osFinancials5/TurboCASH5 subscription.

Documentation : Help documentation

Translations : Outstanding

Streamline your document handling and communication processes with our Document Email Pro Plugin.

With a one-time licence, you can effortlessly email invoices, quotes, and more directly from the program.

Customise email layouts to match the document type, ensuring a professional and tailored communication experience for your clients and suppliers. Send multiple documents simultaneously with ease, simplifying your workflow and saving valuable time.

Experience the convenience of sending digital sales and purchase documents in PDF format, enhancing efficiency and communication with customers and suppliers alike. Upgrade your document management with Document Email Pro Plugin.

Document Export / Import Plugin

Document Export / Import Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Translations : Outstanding

The Document Export/Import plugin offers a convenient method for exporting and importing documents in osFinancials5/TurboCASH5. It enhances the functionality by adding an additional context menu item under Other options → Export to facilitate the export of selected documents or multiple documents from the Documents grid.

Price Agreement Plugin

Price Agreement Plugin - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Translations : Outstanding

Maximize your pricing flexibility and competitiveness with our Price Agreement Plugin. With a convenient one-time licence, unlock the ability to offer quantity discounts on four levels, tailored to individual debtors or creditors.

Define your price agreements effortlessly, whether it's discounts on default sales prices, percentages based on cost prices, or specific amounts per item. Set special prices for select customers or suppliers, overriding default product prices, and include additional details like supplier product numbers and informational text.

Enjoy the convenience of setting start and end dates for agreements, and link prices from stock groups to debtor groups for streamlined management of larger groups. Elevate your pricing strategy and enhance customer relationships with the Price Agreement Plugin.

Subscriptions

Subscriptions - Manual - Shop - Licence : Annual licence -

Documentation : Help documentation

Translations : Outstanding

Elevate your subscription-based business with our Subscriptions Plugin. Perfect for magazine publishers, gymnasiums, rental services, and more, this plugin ensures you never miss charging your members for their subscriptions again.

With the Subscriptions Plugin, effortlessly manage member details such as purchased products/services, repeating frequencies, and warning periods for renewal notices. Stay on top of renewals with automatic reminders and easily generate invoices with just a click.

Track renewal dates, invoicing history, and subscription details at a glance, and streamline communication with automated invoice emails. Plus, efficiently search for specific products/services and view subscription details for each member.

Optimize your subscription management process and enhance customer satisfaction with the Subscriptions Plugin.

Woodsales / Volume Sales Plugin

Woodsales / Volume Sales Plugin - Manual - Shop - Licence : Once-off

Empower your wood wholesale trading with our Woodsales/Volume Sales Plugin. Tailored specifically for the timber industry, this plugin revolutionizes invoice processing by enabling you to specify measurements such as meters length, height, width, and cubic meters effortlessly.

With a simple one-time licence, unlock the ability to manage wood sales with precision and efficiency. Say goodbye to manual calculations and hello to streamlined invoicing processes with the Woodsales/Volume Sales Plugin.

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Document e-mail pro plugin

Document E-mail Pro plugin - Manual - Shop - Licence : Once-off -

This plugin is included in the osFinancials5/TurboCASH5 Business class subscription or can be purchased separately with a once-off licence.

The Document E-mail Pro plugin in osFinancials5/TurboCASH5 allows you to send documents by email directly from the program. With the Document E-mail Pro plugin, you can easily send documents such as invoices, quotes, credit notes, and order lists to customers or wholesalers. Different email templates can be created to match the specific document being sent. For example, the email text sent to a customer with an invoice will differ from the text sent to a wholesaler with an order list.

The Document E-mail Pro plugin can also be used in conjunction with other plugins like remittance, subscriptions and newsletter.

Email Pro Plugin - File Formats

When sending documents as email attachments, you have the option to choose different file formats, including PDF and UBL 2.1. Here's an explanation of each format:

1. PDF (Portable Document Format): PDF is a widely used file format that preserves the formatting, fonts, and layout of a document. It ensures that the recipient sees the document exactly as intended, regardless of their software or operating system. PDF files are typically read-only, allowing recipients to view and print the document but not easily edit its content. Sending documents as PDF attachments guarantees compatibility and easy viewing for recipients.
2. UBL 2.1 (Universal Business Language): UBL is an XML-based standard for exchanging business documents electronically. UBL 2.1 is a specific version of the UBL standard. UBL files follow a predefined structure and contain structured information about various business documents such as invoices, purchase orders, and payment instructions. UBL files are commonly used in business-to-business (B2B) transactions to facilitate automated processing and interoperability between different software systems. By sending documents as UBL 2.1 attachments, you provide recipients with machine-readable data that can be easily processed by their business systems.

When emailing documents, you can attach both a PDF file for human-readable viewing and a UBL 2.1 file for machine-readable data. This offers flexibility to the recipient in interacting with the information based on their specific needs and systems.

Email Pro Plugin - Send Email Options

You can send email(s) in osFinancials from the following options:

- Setup Email Pro - (Setup ribbon) Send a Test Document to test your email settings and configuration.
- Documents grid
    - Send emails with the Email Pro context menu to selected debtor (client/customer).
    - Send mass emails with the Email Pro 2 context menu to multiple debtors (clients/customers).
- Debtors grid
    - Send emails with the Email Pro context menu to selected debtor (client/customer).
    - Send mass emails with the Email Pro context menu to multiple debtors (clients/customers).
- Debtor account - Email Pro tab
- Creditor account - Email Pro tab

Activate the Document E-mail Pro Plugin in a Set Of Books

The Document E-mail Pro needs to be activated in each set of Books, you require to use this plugin.

To activate the Document E-mail Pro plugin:

1. On the Setup ribbon, select Plugins → Document plugins → Document E-mail Pro. If this plugin is not listed under Plugins → Document plugins, activate it via Tools → Activate plugins.
2. The "*Setup E-mail Pro*" screen is displayed:



3. Click the On option to enable it.

   a) Base folder – Enter "*EmailInvoice/en*". This is the "*Base folder*" in which the default files are stored. It contains the test.html and test.txt files. These files are located in the "*EMailInvoice/en*" folder in the "*…\plug_ins\reports*" directory.

   b) Base folder debtor/creditor - Enter "*EmailInvoice/en*". This is the "*Base folder debtor/creditor*" in which the default files are stored. It contains the test.html and test.txt files. These files are located in the "*EMailInvoice/en*" folder in the "*…\plug_ins\reports*" directory.

   c) Report name – Select a document layout file, e.g. "*Layout*" file. This file changes to each document type (i.e. for sales documents (Quotes / Invoices / Credit notes) or for purchase documents (Orders / Purchases / Supplier returns)).

If the "Base folder" or the "Base folder debtor/creditor" is entered correctly, the background for these fields will be displayed in a GREEN background colour.

If the Base folder or the "Base folder debtor/creditor" is not entered correctly, the background for these fields will be displayed in a RED background colour.



In this example, the "Base folder debtor/creditor" is entered as "EMailInvoice". Since the folder does not contain valid files in the "…\plug_ins\reports" folder, it is displayed in a RED background colour.

If you enter "EMailInvoice/en" as the folder, which contains the English templates, the background for these fields will change to the a GREEN background colour.

Massmail button – This button will launch the following message:

" This feature needs a separate serial please request your trail at

https://www.osfinancials.org/en/webshop/ "

4. Limit HTML on type (prefix with type) - By default this option is not selected. This will list all the available templates in the EmailInvoice/en (or /af for Afrikaans, etc.).
5. If you select (tick) this option, only the "*Default*" option will be available.
6. You may click on the Save button to store you base folders and close this screen.

> *To configure your e-mail settings, you may click on the Test e-mail buttons next to the "Base folder" and/or the "Base folder debtor/creditor" fields.*

Testing and Configuration the E-Mail Settings

To configure your e-mail settings, you may click on the Test e-mail buttons next to

Once the valid folder names are entered for "*Base folder*" and the "*Base folder debtor/creditor*" fields, you may test and configure your e-mail settings.

To do this:

1. Launch the "*Setup E-mail Pro*" (On the Setup ribbon, select Plugins → Document plugins → Document E-mail Pro).
2. Click on the Test E-mail button (next to the "*Base folder*" field). The following screen is displayed:



3. Select the document layout file to send sales documents (i.e. quotes, invoices and credit notes) or to send purchase documents (i.e. orders, purchases or supplier returns).
4. Select a template from the list, if the "*Limit HTML on type (prefix with type)*" option on the "*Setup E-Mail Pro*" screen, is not selected.

You may add your own templates or modify the existing ones according to your own requirements.

5. Click on the Close button. The "*Send E-mail*" screen (Free text tab) is displayed:



6. Click on the Settings tab. This will allow you to setup and configure your E-mail account with your Internet Service Provider (ISP).

See the next section to configure and setup your email account.

7. Click on the Send E-mail(s) button to send the test to your own e-mail address. If your settings are correct, the Send E-mail screen will automatically close.

If it does not close, click on the Settings tab of the Send E-mail screen, and check your settings. You may then retry to send your e-mail.

8. Once you have received the e-mail (test), your settings and configuration should be completed.

9. Click on the Save button of the Setup E-mail Pro screen. The basic E-mail Pro setup should be configured and ready to use.

Configuring and Setup E-mail

The Send E-mail - Settings and Free Text tabs (screens) will be displayed, when:

- Launch the Setup E-mail Pro screen and you click on the Test E-mail button and thereafter on the Close button after selecting the Select Layout and Select Template fields.
- Documents – Listing screen context menu (right-click) Plugin action → E-mailPro menu.

> *The Send E-mail - Settings and Free Text tabs (screens) will NOT be displayed, when launched from the context menu (right-click) Plugin mass action → E-mailPro 2 menu.*

Settings tab

Once your e-mail is setup properly, you may test the e-mails, customise or add your own e-mail templates.

This screen consists of two different tabs; "*Settings*" and "*Free text*". In the Settings tab, a number of settings must be entered once.

To Configure and Setup E-mail Pro:

1. On the "*Send E-mail*" screen, click the Settings tab:



2. Enter or select the following, if necessary:

Field	*Description*
Path to the HTML Files:	*The default path is displayed as:* "D:\osFinancials5\plug_ins\reports\EMailInvoice\en\emailtemplates\" *If you have installed osFinancials5/TurboCASH5 into a different folder, you may need to overtype this.* *Here you specify the path where the files for the document email pro plugin are located, you can change this path to your own liking to have a personal set of files.*
POP username:	*Enter the POP username as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
POP password:	*Enter the POP Password as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
POP server:	*Enter the POP server as registered with your ISP (Internet Service Provider) for your e-mail account settings.*

SMTP port:	*The default port is "25". This is determined by the default configuration of your operating system.*
SMTP server:	*Enter a valid SMTP as registered with your ISP (Internet Service Provider) for your e-mail account settings.* *Note with POP before SMTP (usually if you do not send e-mails via your provider) it is best to create an e-mail box that no one else will read.* *This is because if mail is read with multiple Internet Service Providers (IPS) on the mailbox, the POP for SMTP will not work properly.* *It is best to use an account that is not used by anyone else.*
SMTP username:	*Enter the SMTP username as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
SMTP password:	*Enter the SMTP password as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
Return e-mail:	*Here you can enter your own email address to which the recipient can mail back, if desired.*
Return name:	*Here you can enter your own name that will allow the recipient to see who you are.*
CC: (multiple separate with ;)	*This abbreviation CC "Carbon Copy" indicates secondary recipients of a message. Those recipients who are to receive a copy of a message directed to another. The list of recipients in the CC field is visible to all other recipients of the message.* *Enter a valid e-mail address, if necessary.*
BCC: (multiple separate with ;)	*This abbreviation BCC "Blind Carbon Copy" allows you to send a copy of your correspondence to a third party when you do not want to let the recipient know that you are doing this (or when you do not want the recipient to know the third party's e-mail address). You may also wish to enter this filed, when sending an e-mail to multiple recipients, you can hide their e-mail addresses from each other.* *Enter a valid e-mail address, if necessary.*
Send max mail:	*The default is "100". You may use the scroll buttons or enter the number of the maximum emails required to send in a batch. This will limit the number of email messages.*

Timer threshold in sec:	*The default is "10" seconds. This is determined by the default configuration of your operating system. It is not recommend ed to change this, but you could experiment by changing the values.*
Default:	*Select "Default" or "HTML only".*
alt methode:	*Alternative mode*
Send receipt notification:	*Tick if you need a confirmation notification when the email has arrived (no read confirmation!).*
SASL and TLS:	*Simple Authentication and Security Layer (SASL) and Transport Layer Security (TLS) https://en.wikipedia.org/wiki/Simple_Authentication_and_Security_Layer.* *SASL typically also support Transport Layer Security (TLS) to complement the services offered by SASL.*
Priority:	*The default option is "Normal". You may increase the priority to "High" and "Highest". You may decrease the priority to "Low" and "Belowlow"*
SSL/TSL version:	*Select the version for the Simple Authentication and Security Layer (SASL) Transport Layer Security (TLS) from the list.*
Sign any PDF:	*Optional. You can sign any pdf with this button (also the ones send to you). This will allows you to select a pdf file.*
Find certificate:	*If you have a certificate, click in this button. You can browse for your security certificate so that it will be used for the security of the sent PDF files.* *You may use add Digital signatures to the PDF (portable document format) files (e.g. OpenSSL pkcs12.pxf) to your e-mail received by your recipients (e.g. debtors (customers) or creditors (suppliers)). Find certificate: With this button* *See:* • *http://www.openssl.org/* • *PKCS #12: Personal Information Exchange Syntax Standard*
Certificate password:	*If you have selected a certificate, you need to enter a valid password for that certificate.*
UBL:	*From osFinancials version 4.0.0.1102 and TurboCASH5.2 (365) it is possible to send UBL2.0 files with the document.* *The option can be enabled on the settings tab and has 3 settings*

	• *None (default) This option will not send UBL* • *Always send a UBL* • *Based on a UBL field in the dataset that contains the value T.* *The output can be checked for validity via this website* *https://peppol.helger.com/public/locale-en_US/menuitem-validation-bis2* *By default, EUR is used for currency exports.* *For item unit standard SK is used or the first 2 letters of the item unit.*
UBL test:	*This button will generate a UBL file in the *.xml format.*
Save UBL def:	*This button will save a UBL definition file in the *.xml format.*
Show current sql:	*This button displays the current SQL in the memo used for the query. The sql which will be displayed, is the email.txt in the sql folder.*
Reload:	*This button will reload the sql from the memo (to test what an adjustment would do).*
Gen text from HTML:	*This button will generate text from HTML.*

3. Once the E-mail Pro is properly configured and set, you may click on the Send test mails button.

Some messages, e.g. may be displayed in the text area (on the lower right-hand side) of the "Settings" screen. An example may be "your e-mail address Login failed". This may indicate that something is not correctly entered on the settings.

If the email has been sent successfully, the message should display as follows:

```
Sending email using SMTP...
IdSMTP1-ST2-Connected.
IdSMTP1-ST5-Encoding text
IdSMTP1-ST5-Encoding text
IdSMTP1-ST5-Encoding attachment
IdSMTP1-ST5-Encoding attachment
IdSMTP1-ST3-Disconnecting.
IdSMTP1-ST4-Disconnected.
Sending email test Done please check you email adres...
```

Sending Test E-mails

Preview the Test mail message

The test mails sent from the Send test mails button on the Settings tab – confirms that the mail is properly configured and you can proceed to mail your debtors (customers/clients) and/or creditors (suppliers/vendors).



The Subject of the email message is the *.ini file for the document type.

Email header text= “Invoice <#SDOCNO#> from <#FROMCOMPANYNAME#> ”

This is for the test mail purposes only. The correct document number and your company's name will only be displayed when sending documents via e-mail.

Two images will be attached:

- Background1.Jpg - Located in the) folder:

  " ... / bin / themes / (selected theme "

- logo.jpg – Located in the root directory of your osFinancials5/TurboCASH5 installation.

Free text tab (Testing – Sending E-mail)

Once everything has been entered correctly, a (test) e-mail can be sent. To do this, go to the Free text tab. The e-mail is actually sent from here.

As explained earlier in the manual, a corresponding message is sent in addition to the document. There are a number of sample messages that can be used. These messages are set in the selected in "*Mail template*".



E-mail header text – The content of the *.ini file for the selected template is displayed.

Free text – In addition to the standard messages included in the selected template, you may enter any additional text in the Free text area to be included in the email message in.

E-mail address – To send a test e-mail, enter a test e-mail address (own e-mail address) in the heading "*E-mail address*" (see red mouse cursor).

Now the test e-mail can be sent by clicking the Send e-mail(s) button.

The options, is as follows:

Field	*Description*
Show in browser:	*This button will allow you to preview the message of the email in your web browser.*
Preview att:	*This button will allow you to preview the file (e.g. invoice.pdf) which will be sent with the email.*
Test E-mail to Extra CC:	*This button will allow you to test the email to be sent with file by sending it to the specified email address (your own email address)*
Extra CC:	*Here you enter your own email address to send the email to yourself as a test, or as an extra recipient of the email to be sent.*
Extra attachment:	*This button will allow you to add an extra file from your system to be attached to the mail.*
E-mail header:	*The text for the subject (header) of your mail. This E-mail header text is contained in the *.ini file of the e-mail header's last line.* EHeaderText=Invoice <#SDOCNO#> from <#FROMCOMPANYNAME#> *Each email template has its own *.ini file and depending on the template you choose, the document type (that is; Invoice, Quote, Credit note, Purchase, Order or Supplier Return) will be automatically displayed.*
Free text:	*Here you can enter additional text (in html), which are not in the template text, for example, this can be an extra text for this recipient only. This free text will be included in the message section of the mail message.*
Mail template:	*A list of the available templates available in the "... \plug_ins\reports\EMailInvoice\en\emailtemplates\" folder of osFinancials5/TurboCASH5 is as follows:* *10 Invoice.html* *11 Credit note.html*

	12 Purchase.html *13 Supplier return.html* *14 Quote.html* *15 Order.html* *Each template consists of a *.html, *.txt and *.ini file. The prefixes 10 to 15 indicate the document type in section 'TYPES' table.* *Choose a different template for the message, if necessary.* *You can create your own custom templates and place them in the following folder:* "...\plug_ins\reports\EMailInvoice\en\emailtemplates\"
Edit:	*This button allows you to open the folder containing the selected template. You may then edit it, if necessary.*
Send e-mail(s):	*This button will send the email(s).*

Send mail columns: This contains information about the recipient and is as follows:

- Send: At 0, the email has not yet been sent. The email has been sent at 1. If -1 is displayed, there is an error with sending mail. You need to go back to the "*Settings*" tab to reconfigure your mail settings.
- E-mail address: The e-mail address of the recipient, which can be adjusted on the spot for the e-mail that is being sent at that time.
- No.: The Account id, for the debtor or creditor account.

Sending E-mail(S)

In the document form, the E-mail Pro icon is available.



When you click on the Email Pro icon and select the " *E-mail Pro*" option will display the following information message:

" Email can be sent via the context menu in the Document list."

Click OK and navigate to the document grid to send the document by email.

Once your Document e-mail Pro is correctly configured, you may send e-mail or e-mails from documents.

Sending E-mails from Document entry

To send e-mail for documents:

1. On the Default ribbon, select Documents. The Document entry screen, listing your Invoices, will be displayed.

2. Select a document or documents, and right-click on it. On the context menu, select “Plugin action → E-mail Pro”.



3. The “*E-mail Pro*” screen, will open again.



4. The options is as follows:

- Select layout - Choose the Layout file. The following document layout files can be used for all document types for sales documents (Quotes, Invoices and Credit notes) or for purchase documents (Order, Purchase and Supplier returns). Universal document layout files (such as," *Layout file, Document layout, Document layout (15 code)*', etc.), supports all document types and translations via the language files.
- Select template - Depending on the document type, you have selected on the Documents grid, the available templates for the selected document type, will be available to choose from.

5. Then click Close. The "*Send E-mail*" screen will open.



6. E-mail header text – The content of the *.ini file for the selected template is displayed.
7. Free text – In addition to the standard messages included in the selected template, you may enter any additional text in the Free text area to be included in the email message in.
8. E-mail address – This e-mail address is the e-mail address as entered on your debtor / creditor account and included or entered in the document entry screen, will be displayed here.
9. Then click on Send e-mail(s) to send the email. The selected invoice(s) will be sent as an attachment to the recipient(s). The "*Document E-mail Pro*" screen will automatically be closed.

Once again, the options, is as follows:

Field	*Description*
Show in browser:	*This button will allow you to preview the message of the email in your web browser.*
Preview att:	*This button will allow you to preview the file (e.g. invoice.pdf) which will be sent with the email.*
Test E-mail to Extra CC:	*This button will allow you to test the email to be sent with file by sending it to the specified email address (your own email address)*
Extra CC:	*Here you enter your own email address to send the email to yourself, or as an extra recipient of the email to be sent.*
Extra attachment:	*This button will allow you to add an extra file from your system to be attached to the e-mail.*
E-mail header:	*Here you enter text for the subject (header) of your mail.*
Free text:	*Here you can enter additional text (in html), which are not in the template text, for example, this can be an extra text for this recipient only. This free text will be included in the message section of the mail message.*
Mail template:	*A list of the available templates. Select another template for the message, if required.*
Edit:	*This button allows you to open the folder containing the selected template. You may then edit it, if necessary.*
Send e-mail(s):	*This button will send the email.*

Send mail columns: This contains information about the recipient and is as follows:

- Send: At 0, the email has not yet been sent. The email has been sent at 1. If -1 is displayed, there is an error with sending mail. You need to go back to the "*Settings*" tab to reconfigure your mail settings.
- E-mail address: The e-mail address of the recipient, which can be adjusted on the spot for the e-mail that is being sent at that time.
- No.: The Account id, for the debtor or creditor account.

Sending mass e-mails

To send mass e-mails for documents:

1. On the Default ribbon, select Documents. The Document entry screen, listing your Invoices, will be displayed.
2. Select the documents, and right-click on it. On the context menu, select "Plugin mass action → E-mail Pro".
3. A confirmation message will be displayed.

   "Do you wish to continue?"

4. Click Yes to continue.

Sending E-mails from E-Mail Pro tab - Debtor / Creditor accounts

View Mail Messages

Document attachment

The selected documents will automatically be attached as a Portable Document Format (*.pdf) file.

UBL attachment

If the UBL setting is selected, the xml file will be generated and sent to the recipient as an attachment to the e-mail message.

When a business generates an invoice using UBL, the invoice data is structured in an XML format that adheres to the UBL schema. This XML file can then be electronically transmitted to the recipient, who can process it using compatible software. The recipient's system can automatically extract and process the invoice data, ensuring a smooth and efficient transaction.

In summary, UBL files, such as those for invoices, are electronic documents designed to transmit business data in a standardised and efficient manner, facilitating seamless communication between different systems and organisations.

Settings tab

On the settings tab, the UBL setting is by default set to none. You may select the "*All*" option or "*With SQL field UBL*".



UBL test button – Save a testUBL.xml file to a selected folder on your system.

Save UBL def button – Save the UBL definition.

UBL Attachment

When the UBL setting is selected, an XML file is generated and attached to the email sent to the recipient.

Settings Tab

On the Settings tab, the UBL setting defaults to "*None*." You can choose either the "All" option or "*With SQL field UBL*".

What is the difference "With SQL field UBL or Normal UBL?

The difference between "*normal UBL*" and "*With SQL field UBL*" typically relates to how the UBL (Universal Business Language) data is generated and structured within the XML file. Here's a breakdown of the differences:

- Normal UBL
  - Standard Generation: The UBL XML file is generated based on standard business data fields.
  - Predefined Structure: The structure of the XML follows the standard UBL schema, which is predefined and widely accepted in business transactions.
  - General Use: Suitable for most standard business transactions where the data fields are straightforward and well-defined.
- With SQL field UBL
  - Custom Data Fields: The UBL XML file includes additional data fields that are retrieved from a SQL database.
  - Dynamic Content: The content of the XML can be dynamically populated based on the data stored in the SQL database, allowing for more customized and specific information.
  - Advanced Use: Ideal for scenarios where the business data is complex and requires specific, non-standard fields that are not covered by the standard UBL schema.

Summary

- Normal UBL: Standard, predefined structure suitable for general business transactions.
- With SQL field UBL: Includes custom data fields retrieved from a SQL database, suitable for more complex and specific business needs.

By selecting "*With SQL field UBL*," you can tailor the XML content to include detailed, database-specific information, whereas "normal UBL" provides a more standardized and straightforward representation of business data.

Example : UBL2 file

A section of the UBL file (*.xml) is as follows:



E-Mail Pro Folders in the Set of Books Directory

files folder

All email messages are stored in the files folder for the Set of Books. The emails are stored in sub folders for each period e.g. "*YYYY/MM*".

In this example, these emails were sent in "*December 2020*" ("*2020/12*"), etc.

Email message File names

The file name of the email messages is stored as follows:

- 1_ incremented number for each email sent
- Document number – The document number for which the email is sent.
- Email timestamp YYYY/MM/DD followed by Hour minute and second on which the email was sent.
- File extension (file type) *.eml



Searching for email messages in the File explorer

In the search box in your system's file explorer, enter a name, contact any part of an address, postal code, contact, any text entered on the < #FREETEXT# > section of your message, etc. and hover your mouse over the list.



The details of your template used to sent the message will be displayed.

Once you have found what you are looking for, double-click and the message will be opened in your system's default e-mail program.

You may also right-click on a selected e-mail message and select the available options to open the mail message with.

Templates

The templates in osFinancials5/TurboCASH5 consists for the following language folders:

- nl – Netherlands (only in osFinancials)
- en – English
- en-us – English – United States of America
- af – Afrikaans

Templates for each language, are structured in two (2) folders:

1. emailtemplates – Contains three template files for each document type (i.e. sales documents (quotes, invoices, and credit notes) and purchase documents (orders, purchases and supplier returns)). The

template files for each document type consists of the following files:

a) *.ini file – This contains the content for the "*E-mail header text*" which will display as the Subject in the e-mail message of the recipient. In addition to this, it can also contains specific settings to override the configuration and

b) *.txt file – This is the plain text version of the messages in the body of the e-mail message.

c) *.html file – This should have the exact same content as the plain text version of the messages in the body of the email message, but with the hypertext markup language (html) commands and tags to render properly in webpages or html format output.

Besides the .html version of the e-mail template, you also need a "plain text" variant.

The reason for this, is that the e-mail program that the recipient of your email uses, can choose which of the 2 emails is actually used. This is dependent on the e-mail configuration and settings.

In addition, the recipient may also have chosen to have his program work with only 1 variant.

One program can "handle" both variants, other programs only one.

The difference between the "plain text" and the "html" variant is the use of the html commands and tags.

These should all be removed for the "plain text" variant.

2. Sql – The sql folder contains various corresponding sql files to load and render your selection and processes from the Set of Books (database) to the Document E-mail Pro plugin in the *.txt and *.html files.

For the purpose of this documentation, the English templates will be discussed.

Template names and storage

The templates for the e-mail pro plugin, is stored in the following folder:

" ...\plug_ins\reports \EMailInvoice\en\emailtemplates\ "

To open the template folder:

On the Free text tab, click the Edit button.



The folder for the files entered in the Setup E-Mail Pro screen (Plugins → Email Pro on the Setup ribbon) will be opened.

Three (3) files for each document type is included in the folder for each document type:



A preview0.html file will be generated if you click on the Preview in browser button on the Free text tab. This preview0.html file is a temporary file and will be refreshed with content in your browser each time you click on the Preview in browser button. This file be opened in your system's default web browser.

It is a good idea to always create 3 files for each template:

1. ini - template name.ini – This will fill the recipients e-mail Subject with the document number and company name (e.g. “Invoice <#SDOCNO#> from <#FROMCOMPANYNAME#>” In the .ini file you can enter the settings that have priority over the settings in the plugin itself.
2. html - template name.html – In the html version you can put the html texts for your template.
3. txt - template name.txt – In the txt version you can put the plain text (no html tags).

> *The “preview0.html file is not included in the install. It will be automatically added if you click on the Preview in browser button.*

After launching, the “*Document E-mail pro*”, the following screen is displayed:



The options, is as follows:

- Select layout - Choose the Layout file. The following document layout files can be used for all document types for sales documents (Quotes, Invoices and Credit notes) or for purchase documents (Order, Purchase and Supplier returns). Universal document layout files (such as," Layout file, Document layout, Document layout (15 code)", etc.), supports all document types and translations via the language files.
- Select template - Depending on the document type, you have selected on the Documents grid, the available templates for the selected document type, will be available to choose from. The number prefix for each document type, is the number type in the database for each document type.

Adding Free text

All templates consists of a <#FREETEXT#> field tag.

The text is optional and you may add additional text to the selected template. This free text will be added to the message section of the recipient’s e-mail message.



To add a line break enter the html tag <br/> next to the sentence entered. If you need an extra space enter the

*

 tag twice (2X) for a blank line.*

If you double click on the Free text box

Preview of Invoice template (HTML version)

To pre-check your mail message, click on the Preview in browser button.



This will open a preview of your template in your system's default web browser. The preview of the "*10 Invoice.html*" template, is as follows:



Comments and Remarks in documents:

- *Comments is included.*
- *Remarks is excluded.*

SQL files need no translation, except for the Description, Price, Quantity, Excl. and Incl., if required.

These sql files are:

- *doclines.txt - select 0 id, 'Description','Price','Quantity','Excl.','Incl.'*
- *HTMdoclines.txt - select 0 id, '<B>Description</B>','<P ALIGN=RIGHT><B>Price</B></P>','<P ALIGN=RIGHT><B>Quantity</B></P>','<P ALIGN=RIGHT><B>Excl.</B></P>','<P ALIGN=RIGHT><B>Incl.</B></P>'*

Section	*Description*	*Field tags <#XXXX#> (no Spaces and UPPERCASE only)*
Your invoice :	*The document number of the selected document (i.e. Invoice)*	*< #SDOCNO# >*
Your reference :		*< #SREFERENCE# >*
Address :	*Debtor Name, Address 1 Address 2, Address 3 and Postal code.*	*Address :* *< #COMPANY# >* *< #POSTAL1# >* *< #POSTAL2# >* *< #POSTAL3# >* *< #POSTALCODE# >*

Contact :	*Contact name, telephone number.*	*Contact :* *< #CONTACT# >* *< #STELEPHONE1# >*
E-mail address :	*The email address is by default loaded from the e-mail address in the Document entry screen or as over typed in the section of the "Free text" tab:* 	*< #REGISTERS_EMAIL# >*
Summary of products :	*Description : Stock item description and comments in a separate row. Comments does not display the next 3 columns.* *Note : Remarks entered on the Invoice is not displayed here.* *Price : Unit price - Exclusive of Tax (VAT/GST/Sales tax)* *Quantity : Quantity or number of Stock items* *Excl. : Unit price X Quantity - Exclusive of Tax (VAT/GST/Sales tax)* *Incl. : Inclusive price X Quantity - Inclusive of Tax (VAT/GST/Sales tax)*	
Free text :	*The free text entered on the Free text tab when sending e-mail.*	*< #FREETEXT# >*
Delivery address	*Debtor account, Contactperson, Delivery address 1, Delivery address 2, Delivery address 3 and Delivery postal code.*	*Delivery address :*

:		< #DELCOMPANY# > < #DELCONTACT# > < #DELPOSTAL1# > < #DELPOSTAL2# > < #DELPOSTAL3# > < #DELPOSTALCODE# >
Company details :	Company name, Company address 1, Company address 2, Company address 3, and Postal code. (The details entered on Setup → Company info (Setup ribbon))	< #@LS@companyname.txt= border="0" WIDTH=300px CELLPADDING=0 CELLSPACING=0 # > <@LS@ # >
Company logo :	The image loaded on the Options tab of Setup → Company info (Setup ribbon)	< #@LS@logo.txt=border="0" WIDTH=300px CELLPADDING=0 CELLSPACING=0 # > <

```
                                                                    @LS@ # >
```

Invoice template (HTML version)

```
<body>

Your invoice : <#SDOCNO#> <br/>

Your reference: <#SREFERENCE#><br/>

<br/>

Address :</br>

<#COMPANY#><br/>

<#POSTAL1#><br/>

<#POSTAL2#><br/>

<#POSTAL3#><br/>

<#POSTALCODE#><br/></br>

Contact :<br/>

<#CONTACT#><br/>

<#STELEPHONE1#><br/>

<#REGISTERS_EMAIL#><br/>

<br/>

Dear Sir / Madam,<br/>

<br/>

In the attachment you will find your invoice - <#SDOCNO#>.<br/>

<br/>

The summary of the products, is as follows :

<br/>

<#@LS@doclines.txt=border="1" WIDTH=700px CELLPADDING=2 CELLSPACING=2#> <@LS@#>

<br/>

<br/>

<#FREETEXT#><br/>

<br/>
```

```
If you have any questions, please contact us.<br/>

<br/>

Delivery address :<br/>

<#DELCOMPANY#><br/>

<#DELCONTACT#><br/>

<#DELPOSTAL1#><br/>

<#DELPOSTAL2#><br/>

<#DELPOSTAL3#><br/>

<#DELPOSTALCODE#><br/>

<br/>

Sincerely,<br/>

<br/>

<#@LS@companyname.txt=border="0" WIDTH=300px CELLPADDING=0 CELLSPACING=0#> <@LS@#>


<#@LS@logo.txt=border="0" WIDTH=300px CELLPADDING=0 CELLSPACING=0#> <@LS@#>

</body>
```

Invoice template (Text version)

The plain text version does not contain any html commands or tags.

```
Your invoice : <#SDOCNO#>

Your reference : <#SREFERENCE#>

Address :

<#COMPANY#>

<#POSTAL1#>

<#POSTAL2#>

<#POSTAL3#>

<#POSTALCODE#>

Contact :

<#CONTACT#>
```

<#STELEPHONE1#>

<#REGISTERS_EMAIL#>

Dear Sir / Madam,

In the attachment you will find your invoice - <#SDOCNO#>.

The summary of the products, is as follows :

<#@LS@doclines.txt=border="1" WIDTH=700px CELLPADDING=2 CELLSPACING=2#> <@LS@#>

<#FREETEXT#>

If you have any questions, please contact us.

Delivery address :

<#DELCOMPANY#>

<#DELCONTACT#>

<#DELPOSTAL1#>

<#DELPOSTAL2#>

<#DELPOSTAL3#>

<#DELPOSTALCODE#>

Sincerely,

<#@LS@companyname.txt=border="0" WIDTH=300px CELLPADDING=0 CELLSPACING=0#> <@LS@#>

Note the plain text version does not contain the logo:

< #@LS@logo.txt=border="0" WIDTH=300px CELLPADDING=0 CELLSPACING=0# > < @LS@# >

The INI Template

The "*10 Invoice.ini*", is as follows:

The settings entered in the .ini file will have a priority over the setting you entered the Settings tab in the plugin itself.

The standard template .ini files contains the following lines:

EPopUsername=

EPopPassword=

EPopMailserver=

Esmtport=

ESMTPServer=

EReturnAdres=

EReturnName=

ECC=

EBcc=

EHeaderText=Invoice <#SDOCNO#> from <#FROMCOMPANYNAME#>

These .ini files contain the following lines:

EPopUsername=	*The username you use to sign up for your (incoming) email*
EPopPassword=	*The associated password*
EPopMailserver=	*The mail server from where you receive the email*
Esmtport=	*25 (only adjust if your provider uses something else)*
ESMTPUsername=	*The SMTP username (outgoing email)*
ESMTPPassword=	*The associated password*
ESMTPServer=	*smtp.uwprovider.nl*
EReturnAdres=	*youremailaddress@yourdomainname.com*
EReturnName=	*Your name*

ECertPassword =	*The password for your certificate with which you can certify the PDF*
ESignCertificate =	*The location of the certificate*
ECC=	*Your email address if you want to receive a copy of the email yourself and the customer is allowed to see it.*
EBcc=	*Your email address if you want to receive a copy of the email yourself and the customer is not allowed to see it.*
cbPRiority=	*2 (specifies the priority of the email 2 = default)* *cbRecieptActnow = 0 (A 1 indicates that you want to receive a read receipt, if the recipient allows it)*
EHeaderText=	*Invoice <#SDOCNO#> from <#FROMCOMPANYNAME#>*

Again, not all fields need to be filled.

The fields with a value are the minimum settings.

You may need to enter more as provided by your service provider.

Reference – SQL English templates

In the sql folder you will find the corresponding SQL files with which you can retrieve more or different information from the database to use in your e-mails. The following sql folder is included in your osFinancials5/TurboCASH5 installation:

" … \ plug_ins \ reports \ EMailInvoice \en \ sql \ "



Some of the sql file sets consists of sql files in both, the plain text and the HTM version which includes Hypertext markup language commands and tags.

SQL file – email.txt

If you click on the show current sql button of the Settings tab on the E-mail Pro screen, the SQL – email.txt



sql file will be listed.

The document id for the selected document will also be displayed (e.g. 46).

```
SELECT first 1 0  REGISTERS_SEND ,

Trim(COALESCE(d.x_customers_email_address,b.sEmail)  )    REGISTERS_EMAIL,



c.WAccountId REGISTERS_ID,

c.WAccountId ,

c.WAccountTypeId ,

cast('' as char(500)) REGISTER_ATT ,

'test'  as  HTMLLAYOUTx,

c.SAccountCode ,

c.SAccountCode  Code,

c.SDescription,

SPassword,

STelephone1,

STelephone2,

SFax,

SEmail,

SBranchCode,

SBankAccountNumber,

SBankAccountName,
```

```
WDueDays,

d.SDOCNO,

cast(d.ddate as date) ddate,

d.DDUEDATE,

d.WTypeid,

d.SEXTERNALID,

d.Sreference,

d.Wdocid,

sysvars.SCOMPANYNAME as FROMCOMPANYNAME,

d.Wdocid TCVAR_DOCID,

cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)) DOCTOTAL,

cast(cast(d.FTAXAMOUNT as numeric (12,2))as varchar(16)) DOCTAX,

SUBSTRING(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)) from 1 for
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)))-3)

|| ','||

SUBSTRING(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)) from
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)))-1 for 2) DOCTOTDUTCH,

poscon.SDescription Contact,

poscomp.SDescription Company,

delcon.SDescription delContact,

delcomp.SDescription DelCompany ,

DelPostid1.SDescription as DelPostal1,

DelPostid2.SDescription as DelPostal2,

DelPostid3.SDescription as DelPostal3,

DelPostCode.SDescription as DelPostalCode,

Postid1.SDescription as Postal1,

Postid2.SDescription as Postal2,

Postid3.SDescription as Postal3,

PostCode.SDescription as PostalCode

 ,IIF(DC.COUNTRIES_ISO_CODE_2='DE',
```

```
'?d=DE/#!/'

,IIF(DC.COUNTRIES_ISO_CODE_2='BE','?d=BE/#!/','#!/'))   HTMLPJVURL

from debtor b

 join Account c on b.WAccountId = c.WAccountId

join dochead d on b.WAccountId = d.WAccountId

left join messages poscon on (d.WPOSTALCONTACT = poscon.WMessageId)

left join messages poscomp on (d.WPOSTALNAME = poscomp.WMessageId)

left join Messages Postid1 on (d.WPostal1ID = Postid1.WMessageID)

left join Messages Postid2 on (d.WPostal2ID = Postid2.WMessageID)

left join Messages Postid3 on (d.WPostal3ID = Postid3.WMessageID)

left join Messages Postcode on (d.WPostalCodeID = Postcode.WMessageID)

left join messages delcon on (d.WDELCONTACT = delcon.WMessageId)

left join messages delcomp on (d.WDELNAME = delcomp.WMessageId)

left join Messages DelPostid1 on (d.WDelAddress1ID = DelPostid1.WMessageID)

left join Messages DelPostid2 on (d.WDelAddress2ID = DelPostid2.WMessageID)

left join Messages DelPostid3 on (d.WDelAddress3ID = DelPostid3.WMessageID)

left join Messages DelPostcode on (d.WDelCodeID = DelPostcode.WMessageID)

 left join countries dc on d.WDELCOUNTRIES_ID  = dc.COUNTRIES_ID,

sysvars

where  d.WDocid = <@WDOCID@>

union

SELECT first 1 0  REGISTERS_SEND ,

Trim(COALESCE(d.x_customers_email_address,b.sEmail)  )    REGISTERS_EMAIL,

 c.WAccountId REGISTERS_ID,

c.WAccountId ,

c.WAccountTypeId ,

cast('' as char(500)) REGISTER_ATT ,

'test'  as  HTMLLAYOUTx,

c.SAccountCode ,
```

```
c.SAccountCode Code,

c.SDescription,

SPassword,

 STelephone1,

STelephone2,

SFax,

SEmail,

SBranchCode,

SBankAccountNumber,

SBankAccountName,

WDueDays,

d.SDOCNO,

cast(d.ddate as date) ddate ,

d.DDUEDATE,

d.WTypeid,

d.SEXTERNALID,

d.Sreference,

d.Wdocid,

sysvars.SCOMPANYNAME as FROMCOMPANYNAME,

d.Wdocid TCVAR_DOCID,

cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)) DOCTOTAL,

cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)) DOCTAX,

SUBSTRING(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)) from 1 for
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)))-3)

|| ','||

SUBSTRING(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)) from
CHAR_LENGTH(cast(cast(d.FDOCAMOUNT as numeric (12,2))as varchar(16)))-1 for 2) DOCTOTDUTCH

,

poscon.SDescription Contact,

poscomp.SDescription Company,
```

```
delcon.SDescription delContact,
delcomp.SDescription DelCompany ,
DelPostid1.SDescription as DelPostal1,
DelPostid2.SDescription as DelPostal2,
DelPostid3.SDescription as DelPostal3,
DelPostCode.SDescription as DelPostalCode,
Postid1.SDescription as Postal1,
Postid2.SDescription as Postal2,
Postid3.SDescription as Postal3,
PostCode.SDescription as PostalCode
 ,IIF(DC.COUNTRIES_ISO_CODE_2='DE',
'?d=DE/#!/'
,IIF(DC.COUNTRIES_ISO_CODE_2='BE','?d=BE/#!/','#!/'))   HTMLPJVURL
from creditor b
 join Account c on b.WAccountId = c.WAccountId
join dochead d on b.WAccountId = d.WAccountId
left join messages poscon on (d.WPOSTALCONTACT = poscon.WMessageId)
left join messages poscomp on (d.WPOSTALNAME = poscomp.WMessageId)
left join Messages Postid1 on (d.WPostal1ID = Postid1.WMessageID)
left join Messages Postid2 on (d.WPostal2ID = Postid2.WMessageID)
left join Messages Postid3 on (d.WPostal3ID = Postid3.WMessageID)
left join Messages Postcode on (d.WPostalCodeID = Postcode.WMessageID)
left join messages delcon on (d.WDELCONTACT = delcon.WMessageId)
left join messages delcomp on (d.WDELNAME = delcomp.WMessageId)
left join Messages DelPostid1 on (d.WDelAddress1ID = DelPostid1.WMessageID)
left join Messages DelPostid2 on (d.WDelAddress2ID = DelPostid2.WMessageID)
left join Messages DelPostid3 on (d.WDelAddress3ID = DelPostid3.WMessageID)
left join Messages DelPostcode on (d.WDelCodeID = DelPostcode.WMessageID)
 left join countries dc on d.WDELCOUNTRIES_ID = dc.COUNTRIES_ID,
```

```
sysvars

where  d.WDocid = <@WDOCID@>
```

SQL file – ExtraFiles.txt

Allows to select an extra attachment file to be included in the mail message of the recipient.




```
select 'XXXc:\test.txt' AFILE from rdb$database
```

SQL file – selectLayout.txt

The selectLayout.txt will list all valid document layout report (*.rep) files in the ... plugins \ reports \ DOCUMENTS \ DOCUMENTS \ folder where all layout files are stored.

It lists the document types and also contains the settings for the default layout file 1, layout file 2 and layout file 3 for debtor and creditor accounts.

```
select '\DOCUMENTS\DOCUMENTS\' ||soptionValue , 2 a from opreport where stroption =
'SDocLayoutNameCreditNote'and  :WTYPEID=11

union select '\DOCUMENTS\DOCUMENTS\' ||soptionValue , 2 a from opreport where stroption =
'SDocLayoutNameGret'and :WTYPEID=13

union select '\DOCUMENTS\DOCUMENTS\' ||soptionValue , 2 a from opreport where stroption =
'SDocLayoutNameQuote'and :WTYPEID=14

union select '\DOCUMENTS\DOCUMENTS\' ||soptionValue , 2 a from opreport where stroption =
'SDocLayoutNameOrder'and :WTYPEID=15

union select '\DOCUMENTS\DOCUMENTS\' ||soptionValue , 2 a from opreport where stroption =
'SDocLayoutNameInv'and  :WTYPEID=10

union select '\DOCUMENTS\DOCUMENTS\' ||soptionValue , 2 a from opreport where stroption =
'SDocLayoutNamePurchases'and  :WTYPEID=12
```

```
union select '\DOCUMENTS\DOCUMENTS\' || SLAYOUTINVOICE , 1 from debtor where waccountid = :WACCOUNTID and SLAYOUTINVOICE <> '' and :WTYPEID=10

union select '\DOCUMENTS\DOCUMENTS\' || SLAYOUTINVOICE , 1 from creditor where waccountid = :WACCOUNTID and SLAYOUTINVOICE <> '' and :WTYPEID=12

union select '\DOCUMENTS\DOCUMENTS\' || SLAYOUTCREDITNOTE , 1 from debtor where waccountid = :WACCOUNTID and SLAYOUTCREDITNOTE <> '' and :WTYPEID=11

union select '\DOCUMENTS\DOCUMENTS\' || SLAYOUTCREDITNOTE , 1 from creditor where waccountid = :WACCOUNTID and SLAYOUTCREDITNOTE <> '' and :WTYPEID=13

union select '\DOCUMENTS\DOCUMENTS\' || SLAYOUTQUOTE , 1 from debtor where waccountid = :WACCOUNTID and SLAYOUTQUOTE <> '' and :WTYPEID=14

union select '\DOCUMENTS\DOCUMENTS\' || SLAYOUTQUOTE , 1 from creditor where waccountid = :WACCOUNTID and SLAYOUTQUOTE <> '' and :WTYPEID=15


order by 2
```

SQL file – Upd.txt

When a document is not printed, the value is “0”. Once a document is printed, the value is set to “1” and each time after a document is printed, the value is incremented.

The upd.sql set a document as printed and increment the value for each time a pdf file is generated in the Document E-mail Pro plugin.

```
Update dochead set bprinted = bprinted + 1 where Wdocid = :wdocid
```

SQL file – logo.txt

This will load the image as loaded on the Options tab of Setup → Company info (Setup ribbon).

```
Select bloblogo as IMG FROM SYSVARS
```

SQL file – companyname.txt

This will load the Company name and 3 address lines well as the postal code entered on Setup → Company info (Setup ribbon).

companyname.txt (plain text)

```
Select SCompanyName || ascii_char(13) || ascii_char(10)
|| sysvars.SADDRESS1
```

HTMcompanyname.txt (html version)

```
Select SCompanyName || '<br/>'
|| sysvars.SADDRESS1 || '<br/>'
```

```
|| ascii_char(13) || ascii_char(10)
||  sysvars.SADDRESS2
||  sysvars.SADDRESS3
||  sysvars.SPOSTCODE
|| ascii_char(13) || ascii_char(10)
||  sysvars.SPHONENUMBER
 from sysvars
```

```
|| sysvars.SADDRESS2 || '<br/>'
|| sysvars.SADDRESS3 || '<br/>'
|| sysvars.SPOSTCODE || '<br/>'
|| sysvars.SPHONENUMBER || '<br/>'
 from sysvars
```

SQL file – doclines.txt

The highlighted text in these sql files are the only text in these two (2) sql files that may need translation for your templates.

doclines.txt (plain text)

```
select 0 id, 'Description','Price','Quantity','Excl.','Incl.' from
RDB$DATABASE

union

Select a.WSortno,  m.Sdescription ||
COALESCE(m.SEXTRADESCRIPTION,'') Description ,

IIF(a.WLINETYPEID = 91,'',cast(cast(a.FSELLINGPRICE as
numeric (12,2))as varchar(16)))  Sellingprice ,

IIF(a.WLINETYPEID = 91,'',cast(cast(a.FQTYSHIPPED as
numeric (12,0))as varchar(16)))  Shipped ,

 IIF(a.WLINETYPEID = 91,'',cast(cast(a.FEXCLUSIVEAMT
as numeric (12,2))as varchar(16))) Exclamount,

IIF(a.WLINETYPEID = 91,'',cast(cast(a.FINCLUSIVEAMT as
numeric (12,2))as varchar(16))) IncAmount

from docline a left

join stock b on  a.WStockid = b.WStockid

join Messages m on a.WDESCRIPTIONID =
m.WMessageID

where a.Wdocid = :wdocid

order by 1
```

HTMdoclines.txt (html version)

```
select 0 id,  '<B>Description</B>','<P
ALIGN=RIGHT><B>Price</B></P>','<P
ALIGN=RIGHT><B>Quantity</B></P>','<P
ALIGN=RIGHT><B>Excl.</B></P>','<P
ALIGN=RIGHT><B>Incl.</B></P>' from
RDB$DATABASE

union

Select a.WSortno,m.Sdescription ||
COALESCE(m.SEXTRADESCRIPTION,'') Description ,

'<P ALIGN=RIGHT>' || IIF(a.WLINETYPEID =
91,'',cast(cast(a.FSELLINGPRICE as numeric (12,2))as
varchar(16))) || '</P>' Sellingprice ,

'<P ALIGN=RIGHT>' || IIF(a.WLINETYPEID =
91,'',cast(cast(a.FQTYSHIPPED as numeric (12,0))as
varchar(16))) || '</P>' Shipped ,

'<P ALIGN=RIGHT>' || IIF(a.WLINETYPEID =
91,'',cast(cast(a.FEXCLUSIVEAMT as numeric (12,2))as
varchar(16))) || '</P>'Exclamount,

'<P ALIGN=RIGHT>' ||IIF(a.WLINETYPEID =
91,'',cast(cast(a.FINCLUSIVEAMT as numeric (12,2))as
```

```
varchar(16))) || '</P>'IncAmount

from docline a left

join stock b on  a.WStockid = b.WStockid

join Messages m on a.WDESCRIPTIONID =
m.WMessageID

where a.Wdocid = :wdocid

order by 1
```

Created with the Standard Edition of HelpNDoc: Transform Your Word Document into a Professional eBook with HelpNDoc

Document Export / Import plugin

Document Export / Import plugin - Manual - Shop - Licence: Once-off

The Document Export/Import plugin offers a convenient method for exporting and importing documents in osFinancials5/TurboCASH5. It enhances the functionality by adding an additional context menu item under Other options → Export to facilitate the export of selected documents or multiple documents from the Documents grid.

Activation

To activate the Document Export / Import plugin:

1. Navigate to Plugins → Document plugins → Document Export / Import (Setup ribbon). If this plugin is not listed under Plugins → Document plugins, activate it via Tools → Activate plugins.



2. Select "Enable export import"

3. Click the Close button

Exporting documents

To Export documents:

1. Select the document type (e.g., invoices, credit notes, quotes, purchases, supplier returns, orders) on the documents grid. Utilize the filter and search options to narrow down documents based on specific criteria.

2. Choose the document(s) you wish to include in the export file.

3. Access the additional context menu item under Other options → Export to initiate the export process.



4. On the "*Save as*" screen, the default option is the Comma Separated Value (CSV) file format. Alternatively, you can select the TurboCASH exchange file (TXF) format.



5. The default file name is "*Export.csv*" or "*Export.txf*" depending on your choice of file format. Key in name for your export file.

6. Click the Save button.

Importing documents

To importing documents:

1. Select the appropriate document type (e.g., invoices, credit notes, quotes, purchases, supplier returns, orders) on the documents grid.

2. Navigate to the context menu item under Other options → Import to choose the export file.



3. On the "*Open*" screen, locate the exported document file. If necessary, select the CSV or TXF file format.



4. Click the Open button. The imported document(s) will be available as unposted documents.

5. If a sales document type is selected, you'll be directed to the "*Debtor accounts*" screen to choose a debtor account. For purchase document types, the "*Creditor accounts*" screen will appear for selecting a creditor account.

After import

After importing documents, you may need to make edits before updating (posting) them to the ledger. Depending on the source of the exported documents and/or the file format (CSV or TXF), pay special

attention to the following:

- Changing Debtor or Creditor Accounts: The first document, if multiple documents are imported, may be assigned to the selected account. Subsequent documents included in the exported file may be imported to existing accounts. If an incorrect debtor or creditor account was selected and included in the exported file, you can select the document and choose another debtor or creditor account from the Documents → Change account context menu.
- Adjusting Salesperson, Document Groups, and Messages: You have the flexibility to modify the salesperson, document groups, and messages in the document header as needed.
- Date: The date of the imported documents may reflect the date of the source document included in the exported file. You may need to change this to the system date or a date according to your requirements.
- References:
    - In the case of importing an exported file from the TXF file format, the source document number from the exported file may be appended to the "Your reference" field before existing references.
    - In the case of an exported file from the CSV file format, the source document number from the exported file will not be appended to the "Your reference" field.
- Selling Prices, Purchase Prices, and Quantities: These can be adjusted as necessary. Additional items can be added or existing ones removed from the imported document.
- Discount Percentage:
    - In the case of importing an exported file from the TXF file format, no discount percentage will be included.
    - In the case of importing an exported file from the CSV file format, a discount percentage (e.g., 2%) may be included. If no discount applies, set this to 0 or add a specific percentage according to your requirements.
- Tax (VAT/GST/Sales Tax): Confirm and select the correct output tax or input tax applicable to the imported items.
- Comments and Remarks: Comments will be imported, but remarks will not. Add remarks if necessary, especially for special references like serial numbers, guarantees, or warranties.

Examples of Imported Documents in the TXF and CSV File Formats

To better understand how imported documents appear in different file formats, view the examples below:

Example: Imported Invoice in TXF File Format:



Example: Imported Invoice in CSV File Format:



These examples provide visual representations of how invoices look when imported from different file formats. Understanding these differences can aid in effectively managing imported documents within your Set of Books.

Created with the Standard Edition of HelpNDoc: Full-featured Help generator

Price agreement plugin

Price agreement plugin - Manual - Shop - Licence : Once-off -

The Price agreement plugin is a useful tool for managing quantity discounts and special pricing for customers and suppliers. It allows you to set up to five (5) levels of quantity discounts that can be applied to specific debtors or groups of debtors. Additionally, you can set a special price for individual debtors per product. These prices will overrule the default Selling price 1 / 2 / 3 and can be set per debtor (customer / client).

The plugin also includes a field for adding the supplier's product number, making it easy to manage multiple suppliers. You can also add information text explaining why a debtor has a special price.

Discount percentages are used to show customers the discount they are getting, based on the default

price you have set for the debtor. The plugin also allows you to link prices from stock group to debtor group, making it easy to maintain price agreements for larger groups.

You can set up price agreements in a variety of ways, including discount on the default sales price, percentage of the average cost price, percentage of the latest cost price, and amount per item. The Price agreement plugin also allows you to set start and end dates for the agreement.

Once the plugin is activated, it creates a Price agreement tab for each of your stock items, debtor accounts, and creditor accounts (if the creditors module is activated). This makes it easy to manage price agreements across your entire business.

Setup of Price agreements

Activate Price agreement

Once activated, you can access the Price agreement tab for stock items, debtor accounts, and creditor accounts to set up quantity discounts and special pricing. You can define price agreements in various ways, including discount on the default sales price, percentage of the average cost price, percentage of the latest cost price, and amount per item. You can also set start and end dates for the agreement and link prices from stock group to debtor group.

To set up price agreements and activate the Price agreement plugin, follow these steps:

1. Click on the Setup ribbon and select Plugins → Document plugins → Price agreement. If this plugin is not listed under Plugins → Document plugins, activate it via Tools → Activate plugins.



2. Select the On option to activate the plugin. This will create a Price agreement tab for stock items, debtor accounts, and creditor accounts (if applicable).
3. If necessary, select the following options:

    a) Calc discount - If selected, the plugin will calculate the discount for stock items and display the percentage discount on document layout files.

    > *If this option is not selected, no discount will be calculated on documents and layout files. The unit price will be displayed as set for the quantities.*

    b) Price Agreement on On Groups - This option applies price agreements to debtor groups.

    c) Price - Select one of the three (3) prices on the list.

    d) Create on Value on purchase selling price on this account - Select a General ledger account, if applicable. Create on Value on purchase selling price on this account: Select a General ledger account, if applicable.

    e) Export - This option creates a tab-delimited text file that can be opened in a text editor or spreadsheet program.

    f) Import - This option imports a valid tab-delimited text file created using the Export option.

    g) Copy from debtor to - Select a stock item from the list. Copy from debtor to: Select a stock

item from the list to copy price agreements from a debtor to a stock item.

h) Copy from creditor to - Select a stock item from the list. Copy from creditor to: Select a stock item from the list to copy price agreements from a creditor to a stock item.

i) Product and Debtor groups - This option may be used to assign selected products (stock items) to debtor (customer / client) accounts linked to selected debtor / customer / client groups. Product and Debtor groups: Use this option to assign selected products (stock items) to debtor accounts linked to selected debtor groups.

4. Click on the Save button to activate the Price agreement plugin.

Product and Debtor groups

To manage stock groups and debtor groups for price agreements, you may click on the Product and Debtor groups button of the "*Price agreement*" setup screen.

Before you can use the "Group links" Product and debtor groups option, the "Product and Debtor groups" option must be selected (marked) to set the price agreements on debtor groups.



Red - Font / Column colours

If the date in the "To date" field and the "To date" column is expired (earlier than today's system date, the record will be displayed in a Red - Font / Column colour.

Setup Groups

You can create up to two (2) Report groups for inventory items (products), debtors (customers / clients) and creditors (suppliers / vendors). These debtor (customer / client) and creditor (supplier / vendor) groups can be selected when selecting on the Price agreement tab of a selected stock item (product).

The use of these groups is optional, but it will provide the facility to view the price agreements, discount,

etc. set and analyse per group.

Before report groups can be linked, the following report groups must already exist:

- Debtor group - Manage groups for debtors (customers / clients).
- Creditor group - Manage groups for creditors (suppliers / vendors).
- Stock group - Manage groups for stock items (products).

Price agreement tabs

Price agreement tab Stock items

Price agreement tab Stock items - Sales

You may manage price agreements from the Price agreement tab of the Stock items screen. Price agreements may be added, edited or deleted for debtors (customer / client) accounts and for creditor (supplier / vendor) accounts.

To set Price agreements for Stock items:

1. On the Default ribbon, select Stock items.
2. Select a specific Stock item (product).
3. Click on the Edit button. (Alternatively, you may double-click on the selected stock item).
4. Click on the Price agreement tab.
5. Select Sales (default) for debtor (customer / client) accounts.



6. Click on the Lookup button to select the debtor (customer / client) account(s).

7. To manage the Price agreements, you first need to decide what Price type you need to select. This will change the descriptions for Price 1, Price 2, Price 3, Price 4 and Price 5. This will then determine the values you need to enter for each of the price types. Select one of the following Price types and enter the values and until quantities as follows:

    a) Price: Debtor - Enter the actual selling prices (usually lower than the default selling price of the debtor (customer / client)) and quantities.

    b) Percentage of avg. cost price - Enter the percentages of the average cost price.

    c) Latest cost - Enter the actual cost prices

    d) Disc % - Enter the percentage of the discount quantities.

    e) Historical - Enter the prices based on historical value and the quantities.

8. External product code - Enter the product code for the debtor (customer / client), if available.

9. Groups - You may select a debtor (customer / client) group).

10. Valid from ... To date - Select the date of when the price agreement is valid. If the Price Agreement is only valid for a specific period, select the date on which the price agreement will expire.

11. Click on the Post edit record button to save the changes.

12. Click on the Save button of the stock item screen.

Price agreement tab Stock items - Purchases

You may manage price agreements from the Price agreements tab of the Stock items screen. Price agreements may be added, edited or deleted for debtors (customer / client) accounts and for creditor (supplier / vendor) accounts.

To set Price agreements for Stock items:

1. On the Default ribbon, select Stock items.

2. Select a specific Stock item (product).

3. Click on the Edit button. (Alternatively, you may double-click on the selected stock item).

4. Click on the Price agreement tab.

5. Select Purchases for creditor (supplier / vendor) account(s).



6. Click on the Lookup button to select the creditor (supplier / vendor) account(s).

7. To manage the Price agreements, you first need to decide what Price type you need to select. This will change the descriptions for Price 1, Price 2, Price 3, Price 4 and Price 5. This will then determine the values you need to enter for each of the price types. Select one of the following Price types and enter the values and until quantities as follows:

    a) Price: - Creditor – Enter the actual cost prices (usually lower than the cost price of the creditor (supplier / vendor)) and quantities.

    b) Percentage of avg. cost price - Enter the percentages of the average cost price.

    c) Latest cost - Enter the actual cost prices.

    d) Disc % - Enter the percentage of the discount quantities.

    e) Historical - Enter the prices based on historical value and the quantities.

8. External product code - Enter the product code for the creditor (supplier / vendor), if available.

9. Groups - You may select a creditor (supplier / vendor) group (if Purchases is selected).

10. Valid from ... To date - Select the date of when the price agreement is valid. If the Price Agreement is only valid for a specific period, select the date on which the price agreement will expire.

11. Click on the Post edit ✔ record button to save the changes.

12. Click on the Save button of the stock item screen.

Price agreement tab - Debtors (Customers / Clients)

You may manage price agreements from the Price agreements tab of the debtor (customer / client) screen. Price agreements may be added, edited or deleted for stock items.

To set Price agreements for Debtors (Customers / Clients):

1. On the Default ribbon, select Debtor.
2. Select a debtor (customer / client) account on the list.
3. Click on the Edit button. (Alternatively, you may double-click on the selected debtor (customer / client) account).
4. Click on the Price agreement tab.



> *Red - Font / Column colours*
>
> *If the date in the "To date" field and the "To date" column is expired (earlier than today's system date, the record will be displayed in a Red - Font / Column colour.*

5. Click on the Lookup button to select the stock item.
6. To manage the Price agreements, you first need to decide what Price type you need to select. This will change the descriptions for Price 1, Price 2, Price 3, Price 4 and Price 5. This will then determine the values you need to enter for each of the price types. Select one of the following Price types and enter the values and until quantities as follows:
    a) Price - Enter the actual selling prices (usually lower than the default selling price of the debtor (customer / client)) and quantities.
    b) Percentage of avg. cost price - Enter the percentages of the average cost price.
    c) Latest cost - Enter the actual cost prices.
    d) Disc % - Enter the percentage of the discount quantities.
    e) Historical - Enter the prices based on historical value and the quantities.
7. External product code - Enter the product code for the debtor (customer / client), if available.

8. Groups - You may select a stock group from the list.

9. Valid from ... To date - Select the date of when the price agreement is valid. If the Price Agreement is only valid for a specific period, select the date on which the price agreement will expire.

10. Click on the Post edit record button to save the changes.

11. Click on the Save button of the debtor (customer / client) account screen.

Price agreement tab - Creditors (Suppliers)

You may manage price agreements from the Price agreements tab of the creditor (supplier / vendor) screen. Price agreements may be added, edited or deleted for stock items.

To set Price agreements for Creditors (Suppliers):

1. On the Default ribbon, select Creditor.

2. Select a creditor (supplier / vendor) account on the list.

3. Click on the Edit button. (Alternatively, you may double-click on the selected creditor (supplier / vendor) account).

4. Click on the Price agreement tab.



Red - Font / Column colours

If the date in the "To date" field and the "To date" column is expired (earlier than today's system date, the record will be displayed in a Red - Font / Column colour.

5. Click on the Lookup button to select the stock item.

6. To manage the Price agreements, you first need to decide what Price type you need to select. This will change the descriptions for Price 1, Price 2, Price 3, Price 4 and Price 5. This will then determine the

values you need to enter for each of the price types. Select one of the following Price types and enter the values and until quantities as follows:

a) Price - Enter the actual cost prices (usually lower than the cost price of the creditor (supplier / vendor)) and quantities.

b) Percentage of avg. cost price - Enter the percentages of the average cost price.

c) Latest cost - Enter the actual cost prices.

d) Disc % - Enter the percentage of the discount quantities.

e) Historical - Enter the prices based on historical value and the quantities.

7. External product code - Enter the product code for the or creditor (supplier / vendor), if available.
8. Groups - You may select a stock group from the list.
9. Valid from ... To date - Select the date of when the price agreement is valid. If the Price Agreement is only valid for a specific period, select the date on which the price agreement will expire.
10. Click on the Post edit record button to save the changes.
11. Click on the Save button of the creditor (supplier / vendor) screen.

Processing Documents for Price agreements

Price agreements may be used when processing documents:

- Normal document processing
- Standard POS
- RetailPOS plugin
- HorecaPOS plugin

When processing sales documents (i.e. invoices, credit notes and quotes) and quantities are entered which match your price agreement settings, it will automatically calculate the discount.

Calc discount setting

Depending on the "*Calc discount*" setting (on Plugins → Document plugins → Price agreement (Setup ribbon)), the processing and printing of layout files will be displayed as follows:

Calc discount setting on

The Unit price is always displayed as the actual unit price for 1 unit. The percentage discount is automatically calculated on the number of quantities specified in the " *Ship*" field and the total net price, after discount is taken into account, is listed in the "*Amount exclusive*" or "*Amount inclusive*" column. The

discount amount is displayed in the "*Total discount*" field of the document footer.





Calc discount setting off

The Unit price is displayed as the actual price for the unit quantities specified in the "*Ship*" field. No

discount amount is displayed in the "Total discount" field of the document footer.





When processing purchase documents (i.e. purchases, supplier returns and orders) and quantities are entered which match your price agreement settings, it will automatically calculate the discount.

Price agreement reports

You may print lists of the price agreements.

Print Price agreements for Debtors (Customers / Clients)

To print Price agreement reports for debtors (customers / clients):

1. On the Reports ribbon, select Reports → Plugins → Price agreement.
2. Select the "*Debtor - Price agreement*" report (default option).



3. Select the debtor (customer / client) account or creditor (supplier / vendor) account.
4. Enter up to 5 quantities.
5. Click on the OK button.

An example of the "*Debtor Price agreement*" report, is as follows:



Print single item context menu option on Stock items (Default tab)

Select the "Price list - Large retail - Sales" report option.

Select the Stock item (product) and right-click - select Print single item option on the context menu.



Print Price agreements for Creditors (Suppliers / Vendors)

To print Price agreement reports for creditors (suppliers / vendors):

1. On the Reports ribbon, select Reports → Plugins → Price agreement.
2. The "*Debtor - Price agreement*" is the default option. Select the "*Creditor - Price agreement*" report.



3. Select the creditor (supplier / vendor) account.
4. Enter up to 5 quantities.
5. Click on the OK button.

An example of the "*Creditor Price agreement*" report, is as follows:



Print single item context menu option on Stock items (Default tab)

Select the "Price list - Large retail - Purchases" report option.

Select the Stock item (product) and right-click - select Print single item option on the context menu.



Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help

Authoring Tool

Subscriptions plugin

Subscriptions plugin - Manual - Shop - Licence : Annual fee

Introduction to the Subscriptions plugin

Subscriptions plugin is developed for those businesses which sell subscriptions, e.g. magazines, newspapers, membership fees, gymnasiums, etc. This Subscriptions plugin could also be used for rental industries, renting items to their customers on for example a monthly basis.

With this plugin you'll never forget to charge your members for a subscription.

You can define for each member:

- Which product or service they bought.
- The repeating frequency (x times per day, week, month, etc.).
- A warning period in which you get automatically reminded to send the customer a notice for continuing using your services (i.e. 31 days before the invoicing date).
  So you'll always get reminded to remind your customer to renew his/her subscriptions.
- The quantity of days before or after the renewal date, allows you to create the invoice(s) by a click on a button.
- A different contract period (i.e. 1 year) with the invoicing period (i.e. per month).

You also can:

- See when the next renewal date will be.
- See when the last invoiced date was.
- Send an automated invoice by email.
- Search through the subscriptions for a specific product/service and see who has a subscription to it.

The number of days before or after the renewal date osFinancials5/TurboCASH5 let you create the invoice with the click on a button. A different contract period (i.e. 1 year) with the invoicing period (i.e. per month).

Overview to use the Subscriptions plugin

To use the Subscriptions plugin, follow these basic steps:

- Activate Subscriptions:
  - Enable the plugin as global settings.
  - Configure default settings for invoice periods, contract periods, and other global plugin options.
- Setup Subscriptions:
  - Manage subscription stock items (products).
  - Assign subscriptions to debtor (customer/client) accounts.
- Process Subscriptions:
  - Without Email: Process warnings and subscriptions without sending email notifications.
  - With Email: Process warnings and subscriptions, including sending email notifications.
- Processed subscriptions - Invoices and Quotes:
  - Edit and print process invoices.
  - Edit and print process quotes.
- Generate Subscriptions Reports:
  - Print reports to manage subscriptions for all debtor (customer/client) accounts.
- Copy and Paste Subscriptions:
  - Duplicate subscriptions from one debtor account to another.
- Subscriptions - Search options: You may filter and search for specific documents (invoices an quotes) related to subscriptions.

Created with the Standard Edition of HelpNDoc: Upgrade Your Documentation Process with a Help Authoring Tool

Activate subscriptions

Activate subscriptions

On the Setup ribbon, click on Document plugins → Plugins → Subscriptions. If this plugin is not listed under Plugins → Document plugins, activate it via Tools → Activate plugins.

Setup subscription - Setup tab



The options is as follows:

- Activate - turn the plugin on or off.
- Defaults - You may set the default global settings for all subscriptions. You may adjust it when creating a new subscription.
- The upper part Invoice period is about the contract period, the lower part is about the billing period. So you can for example, specify that the contract period is 1 year, which you filled in the days when "*Duedays*" for (a positive number) or after (a negative number) the contract date will receive a billing notice.
- There beside specify e.g. the billing period Contract period is 1 time per month, and that you know the number of days filled with "*Warning*" for (a positive number) or after (a negative number) the billing date, a warning message will be displayed. You may also use other periods.
- Build reference string - Uncheck "*Build reference string*" ensures that you record, which is used as reference for the bill to make. A "*reference*" to the created subscriptions. You fill in the subscription end the "Reference" field. If you have multiple subscriptions on the same invoice, fill in only one.
- Add description - This option will include or exclude any comments generated when processing documents (Invoices and Quotes).
    - Not selected - If this option is not selected, only the Stock item code and description for each item will be included in Invoices and Quotes and printed on document layout files. No comments will be generated and print on document layout files.
    - Selected - You need to select this option to print the subscription details such as the Period and last run to next run, for example, "*Period 2023/05/01/2023/05/31*" generated. This would be included as Comments when processing Documents for the subscriptions plugin and will print on document layout files.
- Add description on top - This option determines the placement of comments. This is similar to the "*Append notes after item*" on Documents setup. The options is as follows:
    - Not Selected - This will print any comments after the stock code and stock description.
    - Selected - This will print any comments before the stock code and stock description.
- Base folder - Subscriptions is the folder for the e-mail templates, layout files, etc. The Subscriptions folder consists of the following language options:
    - English - " ...\plug_ins\reports\Subscriptions\en "

- Afrikaans - " ...\plug_ins\reports\Subscriptions\af "
- Netherlands - " ...\plug_ins\reports\Subscriptions\nl "

You may need to specify your option. for example, if you choose English, you need to add the language prefix folder as " *en* \ " Subscriptions\en\.

- Default date - You may specify the default date. When adding a subscription, this date will be used to set the start of a subscription, You may need to change this as necessary.
- Show for this user -
  - Not selected - If the "*Show for this user*" field is not selected, you may launch the Subscriptions plugin from the Subscriptions icon on the Default ribbon.
  - Selected - If the "*Show for this user*" field on Plugin → Document plugins → Subscriptions (Setup ribbon), is selected, the Subscriptions plugin will automatically be launched if you open the Set of Books and any subscriptions need processing.

Click on the Save button. You may need to reopen your Set of Books. This will add a Subscriptions icon to the Default ribbon to allow easy access to the Subscriptions plugin.



Colour conditions

You may set any colour conditions for valid expressions to display in the lines field.

To be advised.



Created with the Standard Edition of HelpNDoc: Save time and frustration with HelpNDoc's WinHelp HLP to CHM conversion feature

Setup subscriptions

Once Subscriptions have been activated, the Subscriptions screen will be displayed when you open the Set of Books, if any subscriptions need processing.

To add the subscriptions, you need to do the following:

- Create Stock items for Subscriptions (if these do not already exist).
- Add subscriptions to Debtors (customer) accounts.

Once this is done, you may proceed to process subscriptions.

Add Stock items for subscriptions

You may need to add groups for your subscriptions. This will allow you to assign your stock items (products) to specific stock groups.

To add Subscriptions for Stock items (products):

1. On the Default ribbon, select Stock items.
2. Select a specific Stock item (product) account on the list. You may click on the New button to create a new item or copy an existing stock item.
3. Click on the Edit button. (Alternatively, you may double-click on the selected stock item (product).

Add subscriptions to debtors (customers)

To add Subscriptions for debtors (customers):

1. On the Default ribbon, select Debtor.
2. Select a specific Debtor (customer) account on the list.
3. Click on the Edit button. (Alternatively, you may double-click on the selected debtor (customer / client) account).
4. Click on the Subscriptions tab. Initially the Subscriptions tab will be empty for a debtor account, if no subscriptions were added.



5. Click on the Add button.



The default term as set when activating the Subscriptions plugin will be displayed. You may change this for each subscription.

6. Select and or enter the following options:

   a) Stock code - Click on the lookup > button and select the stock item (product).

   b) Enabled - This will activate or deactivate the Subscription of this product for this debtor. If the tick is removed from this field, no further subscriptions will be processed.

   c) Send warning - Uncheck "Warning send" ensures that you check .....

   d) Status - This will indicate the status of the plugin (i.e. None, running or E-mailed).

   e) id - The id is the subscription record id. It will automatically be generated when the added subscription is saved.

   f) Interval - The "interval" field determines how often subscriptions should be processed. During the chosen period invoiced The "Warning in days for subscription"

   g) Warning in days before subscription date - Enter the number of days before or after the "next process" in which the first warning message is shown in the popup plugins.

   h) Invoice in days before subscription date - Enter the number of days before or after the

"next process" in which the billing message is shown in the popup plugins.

i) Interval type – Select the frequency when the subscription is due (i.e. Day, Week, Month, 3 Months, 6 Months or Year).

j) Description – The description of the selected stock item will be displayed. You may add to the existing stock description or overtype the description, if necessary. This will be displayed in the invoices / quotes.

k) Start date - The default date is today, but can be adjusted if desired. This is the date from which the subscription or contract starts. The Last run and Next run fields will automatically be updated. This is the date from the start date plus the number of days entered in the Invoice in days before subscription date field. If the subscription has already been billed, you will see the last billing date in the Next run field. With the "*number*" field.

The Period indicating the last run to next run, for example, "Period 2023/05/01/2023/05/31" would be generated as comments when processing documents for the subscriptions plugin and will print on document layout files.

l) Items – The number of stock items for the debtor that is included and processed for this subscription. You may enter the number (quantity) subscription products.

m) Reference – Enter the reference text which is used on the invoice / quote. In this field, we can also use data fields. This reference will be displayed on the "*Your reference*" field on invoices / quotes.

n) Contract term not the same – This field allows you to set the 2nd set of settings for a period contracts. If selected (ticked), it will add the Interval and Interval type options (fields) at the bottom (underneath the "*Reference*" field) of the Subscriptions tab. You may set the options if the field differs from the main subscription.

7. Click on the List button to save the subscription.

8. Click on the Save button on the Edit Debtor screen to save your changes.

9. Select the next debtor (customer / client) account, if necessary.

Delete subscriptions

To permanently remove an existing subscription, you may click on the Delete button.

It is important to ensure that you can set a subscription to disabled by removing the tick in the Enabled field.

If the subscription needs to be activated at a later point in time be enabled again, you may tick the Enabled field.

View processed transactions

Once subscriptions have been processed, an extra Processed tab will be added. If you click on the Processed tab, the quotes and invoices will be listed.



You may double-click on a quote or an invoice to print the document.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Process subscriptions

Process subscriptions

If the "*Show for this user*" field on Plugin → Document plugins → Subscriptions (Setup ribbon), is selected, the Subscriptions plugin will automatically be launched if you open the Set of Books and any subscriptions need processing.

If the "*Show for this user*" field is not selected, you may launch the Subscriptions plugin from the Subscriptions icon on the Default ribbon.

To manage subscriptions:

If the Subscriptions plugin is not automatically launched, click on the Subscriptions icon on the Default ribbon. The Subscriptions (Warnings) plugin screen is displayed:



The Warnings option for subscriptions will list the warnings of subscriptions.

Only those debtor accounts for which the "*Send warnings*" field is selected on the Detail form, will be included on this list.

Filter / Search for Subscriptions

Click on the Browse button.



Click on the Search button. By default, no options should be selected, but you may select the criteria to filter or locate specific subscriptions.

Post warnings per invoice

The Process warning per invoice option for subscriptions will list the warnings of subscriptions.

Only those debtor accounts for which the "*Send warnings*" field is selected on the Detail form, will be included on this list.



Process warnings

The Process warnings option for subscriptions will process the warnings of subscriptions.

Only those debtor accounts for which the "*Send warnings*" field is selected on the Detail form, will be processed.



Process selected - Tick this option to process selected subscriptions. If this option is not selected, all subscriptions will be listed.

Quote - Tick this option to process warnings as a Quote. If this field is not selected, Invoices will be generated.

Document layout - The default layout file is stored in the following folder:

" ...\plug_ins\reports\Subscriptions\en\layouts "

Log file – The details of the debtor account(s) and subscription(s) will be displayed. An example, is as follows:

Processing warning for account D1MD-AVI Mr. Mike Davies
Processing warning for account D1AB-GRE Mr. AB Green

Subscriptions to process

The Subscriptions to process option for subscriptions will list the debtor accounts which subscriptions need processing.

The number of subscriptions, in this example is (5). In this example, this means that one debtor account has 2 subscriptions and the other debtor account has 3 subscriptions.



You may double-click on a selected debtor account to view a list of the subscriptions. The Subscriptions form consists of two tabs and is as follows:

- Subscriptions tab - You may view the details of the selected subscription, you may click on the Detail button to view and or edit, if necessary.
- Processed tab - You may view a list of the processed transactions and double-click to print a selected invoice or quote.

Process subscriptions

The Process subscriptions option allows you to process Invoices or Quotes or No document (already invoiced) for subscriptions. You have the option to process subscriptions via e-mail manually (snail-mail via postal services or courier).



Process selected - Tick this option to process selected subscriptions. If this option is not selected, all subscriptions will be listed.

Invoices - Invoices is the default option. You may select to process Quotes or No document (already invoiced) options.

Send e-mail - If this option is not ticked, you may add print the documents manually. If this option is selected (ticked), the e-mail documents (invoices or quotes) will be attached as an attachment to the e-mail message to the respectable debtor accounts.

You may add or customize the email templates to be displayed in the e-mail message.

Process – This button will process the subscriptions.

Process Post warnings per invoice – This button will process and post the warnings per invoice.

Log file – The details of the debtor account(s) and subscription(s) will be displayed. An example, is as follows:

```
Processing warning for account D1MD-AVI Mr. Mike Davies
Processing warning for account D1AB-GRE Mr. AB Green
```

Details and Processed subscriptions

You may click double-click on a subscription on the list in the Warnings, Post warning per invoice, Subscriptions to process and Browse screens, to edit a subscription or to view and print quotes and invoices for processed subscriptions.

Subscriptions - List



Subscriptions - Detail



Subscriptions - Processed

View processed subscriptions. The documents on this list will list all subscriptions processed with the Subscriptions plugin as Unposted Invoices or Quotes. Each document will list the each subscription included in the document.

The documents will be processed as an unposted Invoice or Quote, which have not been updated (posted) to the ledger.



Date	Document no.	Amount inclusive	Amount exclusive	Transaction date	Stock code	Item description
2023/03/01	IN000013	345	300	2023/03/01	S-COMPRESSOR	Subscription - Rental - Compressor
2023/03/01	IN000013	115	100	2023/03/01	S-MAGAZINE	Subscription - Magazine
2023/03/01	IN000013	115	100	2023/03/01	S-CLUB-FEES	Subscription - Club fees
2023/03/09	QU000004	345	300	2023/04/01	S-COMPRESSOR	Subscription - Rental - Compressor
2023/03/09	QU000004	115	100	2023/03/08	S-MAGAZINE	Subscription - Magazine
2023/03/09	QU000004	115	100	2023/04/01	S-CLUB-FEES	Subscription - Club fees
2023/05/01	IN000015	345	300	2023/05/01	S-COMPRESSOR	Subscription - Rental - Compressor
2023/05/01	IN000015	115	100	2023/03/15	S-MAGAZINE	Subscription - Magazine
2023/05/01	IN000015	115	100	2023/05/01	S-CLUB-FEES	Subscription - Club fees

To access these documents, you may go to Documents (Default ribbon) and select the Document type Invoices or Quotes.

Double-click on a subscription. The document (Invoice or Quote) will be printed.



Created with the Standard Edition of HelpNDoc: Achieve Professional Documentation Results with a Help Authoring Tool

Process subscriptions - E-mail setup - configuration

Process Subscriptions via E-mail

Process subscriptions - E-mail subscriptions

If you have selected the "*Send e-mail*" option on the Process subscriptions screen, the e-mail option will be launched.

The e-mail documents (invoices or quotes) will be attached as an attachment to the e-mail message to the respectable debtor accounts. If the "*No document (already invoiced)*" option is selected on the Process subscriptions screen, no document will be attached to the e-mail message.

You may add or customise the email templates to be displayed in the e-mail message.

Process Subscriptions - Configure E-mail

Before you can Process subscriptions, you have the following options:

Process selected: This option will help you to choose whether to process all subscriptions or specific selected subscriptions. The options is as follows:

- Not selected - If this field is not selected (not ticked), all subscriptions on the Subscriptions to process list will be processed.
- Selected - If this field is selected (ticked), you may select specific subscriptions on the Subscriptions to process list. Only the selected subscriptions on the Subscriptions to process will be processed.



Process Subscriptions - E-mail account setup

Before you can send e-mails, you need to configure your e-mail account in the Set of Books. This is only a once off configuration. Unless your requirements change.

To do this, you need to click on the E-mail or E-mail selected button.

Then click on the Settings tab.



Select or enter the following, where applicable:

Field	*Description*
Path to the HTML file:	*The default path is displayed as:* "C:\osfinancials5\plug_ins\reports\Subscriptions\en\emailtemplatesInvoice" *If you have installed osFinancials5/TurboCASH5 into a different folder, you may need to overtype this. Specifies the path where the files for the Subscriptions plugin is located. This path may be edited for your own requirements if you have a personal set of files.*
POP username:	*Enter the POP username as registered with your ISP (Internet Service Provider) for your e-mail account settings, if required.*
POP password:	*Enter the POP Password as registered with your ISP (Internet Service Provider) for your e-mail account settings, if required.*
POP server:	*Enter the POP server as registered with your ISP (Internet Service Provider) for your e-mail account settings, if required.*
SMTP port:	*The default is "25" seconds. This is determined by the default configuration of your operating system.*
SMTP server:	*Enter a valid SMTP as registered with your ISP (Internet Service Provider) for your e-mail account settings.* *Note when POP before SMTP (usually when you are not using your provider sent emails) you can create an e-mail box which nobody reads. This is because if there are multiple ISP's on the mail box mail is read, the POP for SMTP is not working properly.* *It is best to use an account that is further used by anyone.*
SMTP username:	*Enter the SMTP username as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
SMTP password:	*Enter the SMTP password as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
Return e-mail:	*This field is optional. You may enter your own e-mail address.*
Return name:	*This field is optional. You may enter your own name to be displayed on the message to be displayed on the email field of the recipients e-mail or if the message is returned by your ISP in the case of an invalid e-mail address.*

Field	Description
CC: (multiple separate with ;)	This abbreviation CC “Carbon Copy” indicates secondary recipients of a message. Those recipients who are to receive a copy of a message directed to another. The list of recipients in the CC field is visible to all other recipients of the message. Enter a valid e-mail address, if necessary. Note you need to add a space before and after the semi-colon. If you do not add spaces, the first digit of the second and subsequent e-mail addresses may cut off. This could result in an undelivered mail error.
BCC: (multiple separate with ;)	This abbreviation BCC “Blind Carbon Copy” allows you to send a copy of your correspondence to a third party when you do not want to let the recipient know that you are doing this (or when you do not want the recipient to know the third party's e-mail address). You may also wish to enter this filed, when sending an e-mail to multiple recipients, you can hide their e-mail addresses from each other. Enter a valid e-mail address, if necessary. Note you need to add a space before and after the semi-colon. If you do not add spaces, the first digit of the second and subsequent e-mail addresses may cut off. This could result in an undelivered mail error.
Send max mail:	The default is “100”. You may use the scroll buttons or enter the number of the maximum emails required to send in a batch. This will limit the number of email messages.
Timer threshold in sec:	The default is “10” seconds. This is determined by the default configuration of your operating system. It is not recommended to change this, but you could experiment by changing the values.
Default:	Default is the standard option. You may select the html only option.
Alt methode:	Tick to select the alternative mode.
Send receipt notification:	If this field is selected (ticked), a read receipt will be requested by the recipient.
Priority:	Normal is the default priority. You may select Highest, High, Low or Below low option. This is the priority in which e-mails will be sent.
Sign any PDF:	Optional should be you can sign any pdf with this button (also the ones send to you).
Find certificate:	If you have a certificate, click in this button to locate it and add it to this plugin. You may use add Digital signatures to the PDF (portable document format) files (e.g. OpenSSL pkcs12.pxf) to your e-mail received by your recipients (e.g. debtors (customers). See:

Field	*Description*
	· *http://www.openssl.org/* · *PKCS #12: Personal Information Exchange Syntax Standard*
Certificate password:	*If you have selected a certificate, you need to enter a valid password for that certificate.*
Send test mails:	*You may click on the Send test mails button to check that the configuration is correct.*

- The box (on the lower right-hand side) - Some messages, e.g. may be displayed in the text area of the Settings screen. An example may be “your e-mail address *Login failed”*. This may indicate that something is not correctly entered on the settings.
- Show current sql – The sql, is used to add the debtors, etc. for the Subscriptions plugin.

Send test mails

You may click on the Send test mails button to check that the configuration is correct.



The Subject of the email message is the *.ini file:

```
EHeaderText=Your subscription
```

This will print in the Subject field for the test mail purposes. The correct document number and your company's name will only be displayed when sending documents via e-mail.

Two images will be attached:

- Background1.Jpg - Located in the .../ bin / themes / (selected theme) folder.
- logo.jpg - Located in the root directory of your osFinancials5/TurboCASH5 installation.

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Process subscriptions warnings - E-mail

Process Subscriptions via E-mail

Process subscriptions - E-mail subscriptions

If you have selected the "*Send e-mail*" option on the Process subscriptions screen, the e-mail option will be launched.

The e-mail documents (invoices or quotes) will be attached as an attachment to the e-mail message to the respectable debtor accounts. If the "*No document (already invoiced)*" option is selected on the Process subscriptions screen, no document will be attached to the e-mail message.

You may add or customise the email templates to be displayed in the e-mail message.

Process Subscriptions warnings - Select accounts

By default, all warnings for subscriptions for all debtor (customer/client) will be sent.

Before you can Process warnings for subscriptions, you have the following options:

Process selected: This option will help you to choose whether to process all subscriptions or specific selected subscriptions. The options is as follows:

- Not selected - If this field is not selected (not ticked), all subscriptions on the Warnings option will be processed when you Process warnings for subscriptions:
- Selected - If this field is selected (ticked), you may select specific subscriptions on the Warnings list. Only the selected subscriptions on the Process warnings will be processed.



To send warnings for selected debtor (customer/client) account(s), the "*Process selected*"-field is selected

(ticked) on the Process warnings option. You may select specific subscriptions on the Warnings list. Only the selected subscriptions on the Process warnings will be processed.



You may press the Ctrl key and use your mouse to select specific debtor (customer/client) accounts.

Navigate to the Process warnings option to process warnings for subscriptions of selected debtor (customer/client) accounts.

When processing warnings for subscriptions the log file, is as follows:

```
Skip processing for accountD1MD-AVI Mr. Mike Davies
Skip processing for accountD1RO-GSM Mr. Roger Smith
Skip processing for accountD1AB-GRE Mr. AB Green
Skip processing for account D1MD-AVI Mr. Mike Davies
Processing warning for account D1RO-GSM Mr. Roger Smith
Skip processing for account D1AB-GRE Mr. AB Green
```

The processing of warnings for subscriptions, will list only the selected debtor (customer/client) account(s) as "*Processing*".

All other selected debtor (customer/client) account(s) which was not selected, will be included in the log file as "*Skip*".

Subscriptions - Warnings - Send E-mail

Once your e-mail is properly setup and configured, you may proceed to send warnings via e-mail.

The "*Send e-mail*" option needs to be selected on the Process subscriptions option. This will launch the Send E-mail screen with the default - Send E-mail tab to process warnings.



Each subscription for a debtor (customer/client) account will be listed and emails will be sent separately.

Subscriptions - Warnings - Send E-mail - Free text tab

Click on the Free text tab to enter Free text to be included in your e-mail message and explore more options.



On the Free text tab, you may have the following options:

- Free text - Add any additional information to be included in the message to your debtors customers/clients).
- Preview in browser - Click on this button. This will add a temporary "*preview0.html*" file and will be opened in your system's default web browser.



- Preview att - Click on this button to preview the warning message included in the email message before you send e-mail(s).



- Test E-mail to Extra CC - Before you click on this button, you need to add a valid e-mail address in the "*Extra CC*" field. This will send an e-mail to the recipients in the "*Extra CC*" field. If you send it to yourself, you may preview the email message including free text entered and attachments.



- Extra attachment - Click on this button to include extra files to include in the e-mail(s) send to the recipients.

Once you are satisfied with your selection, you may click on the Send E-mail(s) button to send the warnings to your debtors (customers/clients).

Email messages in Recipients Email Inbox

The e-mail for processed warnings of subscriptions will land in the Inbox of the Recipient's (debtor (customer/client) account.



Open Attachments

The layout files for warnings if subscriptions, will be attached as a pdf file and the recipient can open these files in their system's default pdf-application or program.



Edit the layout files

You may edit the layout files in the Report designer (Setup ribbon).



The layout files for warnings of subscriptions is located in the following folder:

" ...\plug_ins\reports\Subscriptions\en\layouts "

Click on the Edit button. (Alternatively, you may double-click on the report).



Select the message and edit it as necessary. To do this, click on the 'TRpLabel0' and on the Label tab type your own text. The default Label text is as follows:

> The following subscriptions will soon end. You will receive a invoice soon for the next period.

For a next sentence you may copy the expression to type another message. Repeat as necessary

Some features you may need to explore:

Move text:

- Drag it to the desired place.

Delete text or expressions:

- Select the object and go to Edit - Delete

Add static text:

- TRpLabel – Add static text object to the report.
- Add the messages or text to display on the report.

Add company logo:

- TRpImage: Click on this icon and click on the space and drag to insert a blank image object.
    - Enter “COMPANYDATA.BLOBLOGO” in the Expression field.

- This is used to display your company logo on the reports and document layout files. The Company Logo dataset is COMPANYDATA.BLOBLOGO. The logo is stored in the database as a BLOB (Binary Large Object) and will be displayed printed on remittance layout files if loaded in Company info - Options screen (Default ribbon).

- Add a static picture:
  - TRpImage – Click on this icon and click on the space and drag to insert a blank image object.
  - Right-click on the image object and select the Open option on the context menu.

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Process Subscriptions via E-mail

Process subscriptions - E-mail subscriptions

If you have selected the "*Send e-mail*" option on the Process subscriptions screen, the e-mail option will be launched.

The e-mail documents (invoices or quotes) will be attached as an attachment to the e-mail message to the respectable debtor accounts. If the "*No document (already invoiced)*" option is selected on the Process subscriptions screen, no document will be attached to the e-mail message.

You may add or customise the email templates to be displayed in the e-mail message.

Process Subscriptions - Select subscriptions to process

Before you can process subscriptions via e-mail, make sure that the "*Send e-mail*" option is selected.

If your e-mail is not setup or configured correctly, please refer to the Process subscriptions - E-mail setup - configuration section of this documentation.

You can select which subscriptions will be processed. To select subscriptions to process. you need to pay specific attention to the following:

- Not selected - If this field is not selected (not ticked), all subscriptions on the Subscriptions to process list will be processed.
- Selected - If this field is selected (ticked), you may select specific subscriptions on the Subscriptions to process list. Only the selected subscriptions on the Subscriptions to process will be processed.



Subscriptions - Send Email

Once your E-mail is set and configured in your Set of Books, you may proceed to send emails from the Process subscriptions option.



Send e-mail - If this option is selected, it will launch the Send E-mail (default tab). Before you can your subscriptions via email, you may need to go to the Settings tab to set an configure your mail before you can successfully send e-mails. If this "*Send e-mail*" field is not selected, you may manually send your subscriptions via email or via snail-mail, such as postal services or couriers.

Process selected - By default this option is not selected.

Invoice - This is the default option. You may select the following options:

- Invoice - This will generate Invoices for the subscriptions.
- Quote - This will generate Quotes for the processed subscriptions.
- No document (Already invoiced) - This option will not generate any documents Invoices or Quotes.

Process-button - This will generate Invoices or Quotes, depending on your selection.

Process Post warnings per invoice button -

Log file - Examples

```
Processing accountD1MD-AVI Mr. Mike Davies
Adding subscription Subscription - Rental - Compressor
Adding subscription Subscription - Magazine
Adding subscription Subscription - Club fees
Skip processing for accountD1RO-GSM Mr. Roger Smith
Skip processing for accountD1AB-GRE Mr. AB Green
```

If subscriptions have already been processed for the debtors, (or have not been selected removed tick in the "*Process selected*" field) these accounts may be not be processed. An example of this will be displayed in the log file, as follows:

```
Skip processing for accountD1RO-GSM Mr. Roger Smith
Skip processing for accountD1AB-GRE Mr. AB Green
```

Process Subscriptions - Free text tab



E-mail header text - Type the text to be displayed as the Subject field of your operating system's default

e-mail program.

Free text – Enter additional text to be included in the e-mail message.

Preview in browser button – This will display the mail template in your system's default. This is the e-mail template which will be displayed as the e-mail message. You may create and customise e-mail templates and select a email template. The e-mail templates are stored in the following folder:

" ...\plug_ins\reports\Subscriptions\en\emailtemplatesInvoice) "



Preview att button - This will display the document layout file (invoice or quote).



Test E-mail to extra CC - Test the mail to the extra e-mail address entered in the Extra CC field.



Open the invoice or quote in the test e-mail



Extra attachment button - In addition to the document (invoice or quote), which will be automatically be attached to the e-mail, you may attach another file as an extra attachment.

Send e-mail(s) button – This will start to send e-mails and the attachments to the debtor accounts on the list.

Process Subscriptions - Customise E-mail templates

Preview in browser button – This will display the mail template in your system's default. This is the e-mail template which will be displayed as the e-mail message. You may create and customise e-mail templates and select a email template. The e-mail templates are stored in the following folder:

"...\plug_ins\reports\Subscriptions\en\emailtemplatesInvoice "



Customise Templates

If you click on the Edit button, the following folder will be opened:

" ...\plug_ins\reports\Subscriptions\en\emailtemplatesInvoice "



To create your own template it is easy and you may create as many templates, as required.

It is recommended that you copy the test.html file and rename it to your own needs.

The basic email.html template is as follows:



You may change all text as necessary. Please take note of the following two (2) fields:

- <#SDESCRIPTION#> - This will add the name for the respective debtor accounts to the e-mail message.
- <#FREETEXT#> - This will add the text as entered for the e-mail messages, as entered on the Free text field on the Free text tab.

You may preview the template when you click on the Preview in browser button on the Free text tab.

Process Subscriptions - Recipient's E-Mail Message

All debtor (customer / client) accounts (which have a valid e-mail address) will receive an e-mail message (based on the e-mail template and the free text) with the Invoice or quote as a Potable Document Format (pdf file) as an attachment. An example of the e-mail message received by the recipient(s), is as follows:



Customise / Edit the layout files

You may edit the layout files in the Report designer (Setup ribbon).



The layout files for processing of subscriptions is located in the following folder:

" ...\plug_ins\reports\Subscriptions\en\layouts "

Click on the Edit button. (Alternatively, you may double-click on the report).



Select the message and edit it as necessary. To do this, click on the '*TRpLabel0*' and on the Label tab type your own text. The default Label text is as follows:

> The following subscriptions will soon end. You will receive a invoice soon for the next period.

For a next sentence you may copy the expression to type another message. Repeat as necessary

Some features you may need to explore:

Move text:

- Drag it to the desired place.

Delete text or expressions:

- Select the object and go to Edit - Delete

Add static text:

- TRpLabel – Add static text object to the report.
- Add the messages or text to display on the report.

Add company logo:

- TRpImage: Click on this icon and click on the space and drag to insert a blank image object.
    - Enter “COMPANYDATA.BLOBLOGO” in the Expression field.

- This is used to display your company logo on the reports and document layout files. The Company Logo dataset is COMPANYDATA.BLOBLOGO. The logo is stored in the database as a BLOB (Binary Large Object) and will be displayed printed on remittance layout files if loaded in Company info - Options screen (Default ribbon).

- Add a static picture:
  - TRpImage - Click on this icon and click on the space and drag to insert a blank image object.
  - Right-click on the image object and select the Open option on the context menu.

Created with the Standard Edition of HelpNDoc: Streamline Your CHM Help File Creation with HelpNDoc

Processed subscriptions - Invoices and Quotes

All invoices and quotes processed using the Process subscriptions option, will be generated as unposted documents.

Invoices - These Invoices is not updated (posted) to the ledger.

Quotes - The quotes is not yet confirmed (converted to an invoice).

Invoices

These Invoices is not updated (posted) to the ledger. Before you update (post) these invoices generated by the process subscriptions to the ledger, you may need to edit these Invoices.

Once you are satisfied, you may proceed to update (post) these invoices to the ledger.

Invoice form

To select an Invoice:

On the Documents (Default ribbon), select Invoices.

You may need to select the document status as "*Unposted*" and use the filtering and sort options on the documents grid to search and filter for specific documents.

Click on Edit button to open the invoice form. (Alternatively, you may double-click on the invoice).



You may need to focus on the following:

- Document header
  - Your reference - The first line of the "*Reference*" field will be included for example "Monthly rental" of the first subscription on the list. You may change this, as necessary.
  - RUN - Underneath the email address of the debtor form's document header will be generated, for example, *'RUN:20231001202321031'*.
  - Messages - The default message lines as selected for the Invoices on Documents setup (Setup ribbon) , is not included in the Document header. You may add up to 3 lines of your own messages.
  - Salesperson - The default salesperson as set in the debtor (customer (client) account, will be displayed. You may change this, if needed.
  - Document group 1 / Document group 2 - If no document groups is selected, you may select the appropriate groups.
- Document lines
  - Comments - Comments is automatically generated if the "*Add description*" on the Setup subscriptions is selected. If not selected, no comments will be inserted.

Example : Printed Invoice


Document layout (15 code)

Invoice Page no.: 1 / 1

Mr. Mike Davies
P O Box 333
Halfway House
1685

Delivery address
195 AZ Street
Eastern Areas
Halfway House
1685

Handyman Hardware Store
27 Olifants Road
Emmarentia
Johannesburg
2195
Company reg. no.: 336012345
Tax reg. no.: 446010111
Telephone: (011) 310-1390
Fax: (011) 310-2000
E-mail: mymail@myisp.net
Website: osfinancials.org

Invoice: IN000022 **Date: 2023/10/01** **Account no.: D1MDAVI**

Code / Description	Units	Qty	Price	Disc%	Exclusive	Tax%	Tax	Inclusive
S-COMPRESSOR Subscription - Rental - Compressor *Period 2023/10/01/2023/10/31*		1	300,00		300,00	15,00%	45,00	345,00
S-MAGAZINE Subscription - Magazine *Period 2023/04/19/2023/04/25*		1	100,00		100,00	15,00%	15,00	115,00
S-CLUB-FEES Subscription - Club fees *Period 2023/10/01/2023/10/31*		1	100,00		100,00	15,00%	15,00	115,00
Total					**500,00**		**75,00**	**575,00**

Bank name: ABC Bank
Holder's name: Handyman Harware Store
Bank account no.: 1234567890
IBAN:
SWIFT:
BIC:

Due date: 2023/10/31
Your reference: Monthly rental
Tax reference: 336012345
Message:

Salesperson: Russell

Invoice accepted:
Name: _____
Date: _____
Signature: _____

Printed/Reprinted 2024/10/29 04:46:24

Quotes

Quotes will be generated if Quotes is selected on the Process subscriptions option.

The quotes is not yet confirmed (converted to an invoice). Before you confirm (convert to an invoice) these quotes generated by the process subscriptions to the ledger, you may need to edit these quotes.

Once you are satisfied, you may proceed to confirm (convert to an invoice). Once these quotes is confirmed you may proceed to update (post) the converted quotes as invoices to the ledger.

Quote form

To select a Quote:

On the Documents (Default ribbon), select Quotes.

You may need to select the document status as "*Open*" and use the filtering and sort options on the documents grid to search and filter for specific quotes.

Click on Edit button to open the quote form. (Alternatively, you may double-click on the quote).



You may need to focus on the following:

- Document header
  - Your reference - The first line of the "*Reference*" field will be included for example "*Monthly rental*" of the first subscription on the list. You may change this, as necessary.
  - RUN - Underneath the email address of the debtor form's document header will be generated, for example, *'RUN:202308012023010801'*.
  - Messages - The default message lines as selected for the quotes on Documents setup (Setup ribbon) is not included in the Document header. You may add up to 3 lines of your own messages.
  - Salesperson - The default salesperson as set in the debtor (customer (client) account, will be displayed. You may change this, if needed.
  - Document group 1 / Document group 2 - If no document groups is selected, you may select the appropriate groups.

- Document lines
  - Comments - Comments is automatically generated if the "*Add description*" on the Setup subscriptions is selected. If not selected, no comments will be inserted.

Example : Printed Quote



Created with the Standard Edition of HelpNDoc: Effortlessly bring your documentation online with HelpNDoc

Subscriptions - Reports

Subscription - Report

In the Report option, you may print four subscription reports.

Select one of the following reports:

- Reporting group 1 - This will print your subscriptions linked to Stock group 1.
- Reporting group 2 - This will print your subscriptions linked to Stock group 2.
- Subscriptions - This will print your subscriptions.
- Subscriptions list - This will print a list of your subscriptions.

Click on the Show button.

The report parameter screen will be displayed for three reports (i.e. Reporting group 1, Reporting group 2, and Subscriptions list)



Select the "*From date*" and "*To date*" and click OK.

Example : Reporting group 1



Example : Reporting group 2



Example : Subscriptions



Example : Subscription list



The report will list the subscriptions and the next run (dates for which subscriptions need to be processed).

These reports is stored in the following folder:

" ...\plug_ins\reports\Subscriptions\reports "

Subscription - Reports Debtors grid

On the Debtors grid (Default ribbon), you may select a debtor account.

On the context menu, select Reports → Subscriptions.



Example : Subscriptions - Debtors - Context menu



Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Subscriptions - Copy / Paste - Debtors

Copy and Paste / Subscriptions

You may copy a subscription from a selected debtor account and paste it to another debtor account.

Copy Subscriptions

On the Debtors grid (Default ribbon), select a debtor account and right-click on the account.

On the context menu, select Copy from plugin → Subscriptions.



Paste subscriptions

Once you have copied subscriptions, go to the Debtors grid (Default ribbon), select a debtor account and right-click on the account.

On the context menu, select Paste from plugin → Subscriptions.



A similar confirmation message will be displayed:

Erase old data and copy for plugin &Subscriptions from accountD1MD-AVI Mr. Mike Davies

Click Yes to proceed or No to cancel the Paste option.

Check / Edit Copied Subscriptions

Once Subscriptions is copied, it will add all the details of existing subscriptions to the Subscriptions tab of the Debtor account.



Id	Stock code	Start date	Last run	Quantity	Next run	Description	Interval type	Interval	Warning in days I	Invoice in da
9	S-COMPRESSOR	2023/03/01	2023/08/01	1	2023/09/01	Subscription - Rental - Compressor	Month	1	14	7
8	S-MAGAZINE	2023/01/01	2023/04/05	1	2023/04/12	Subscription - Magazine	Week	1	14	7
7	S-CLUB-FEES	2023/03/01	2023/08/01	1	2023/09/01	Subscription - Club fees	Month	1	14	7
12	S-COMPRESSOR	2023/03/01	2023/08/01	1	2023/09/01	Subscription - Rental - Compressor	Month	1	14	7
11	S-MAGAZINE	2023/01/01	2023/04/05	1	2023/04/12	Subscription - Magazine	Week	1	14	7
10	S-CLUB-FEES	2023/03/01	2023/08/01	1	2023/09/01	Subscription - Club fees	Month	1	14	7

You need to review the copied subscriptions:

Delete subscriptions which is not applicable to the debtor account.

Edit copied subscriptions applicable to the debtor account:

Select a subscription and check or edit the subscription. On the Details option of the selected subscription, different start date and settings may need to be changed. Change these where necessary.

Created with the Standard Edition of HelpNDoc: Easily create CHM Help documents

Subscriptions - Search options

Subscriptions - Browse options

Click on the Browse button.



Click on the Search button. By default, no options should be selected, but you may select the criteria to filter or locate specific subscriptions.

Subscriptions - Central search

On the central search Search (Default ribbon) option you may search for subscriptions meeting your search criteria.



The Subscriptions plugin in osFinancials5/TurboCASH5 is a powerful tool that allows you to manage and search for subscription-based products and related documents. Here's a breakdown of how the central

search feature works:

Central Search Options

- Stock:
  - Function: This option allows you to search for stock items (products) that meet your specified criteria.
  - Action: When you double-click on a specific stock item from the search results, it will open the Stock item (product) edit form.
  - Additional Functionality: Within the edit form, you can navigate to the Document groups tab to print both unposted and posted documents related to that stock item.
- Document:
  - Function: This option lists documents (such as invoices or quotes) that include subscription-based stock items.
  - Action: Double-clicking on a document from the search results will allow you to print the selected document.
- Comments Search:
  - Function: You can search for documents based on specific comments, such as "Period 2023/05".
  - Result: This will list only the documents that are associated with the specified period, in this case, May 2023.
- Practical Examples
  - Stock Search Example:
    - Search Criteria: "Monthly Subscription"
    - Result: The search will list all stock items that match "Monthly Subscription".
    - Action: Double-clicking on one of the listed items will open the edit form, where you can manage the product details and print related documents.
  - Document Search Example:
    - Search Criteria: "Subscription Invoice"
    - Result: The search will list all documents that include subscription stock items.
    - Action: Double-clicking on a document will allow you to print it directly.

- Comments Search Example:
    - § Search Criteria: "Period 2023/05"
    - § Result: The search will list all documents specifically for the period of May 2023.
    - § Action: You can review and print these documents as needed.

The Subscriptions plugin in osFinancials5/TurboCASH5 provides a comprehensive way to manage subscription-based products and related documents. The central search feature allows you to efficiently find and manage stock items, documents, and specific periods, streamlining your workflow and ensuring that you can easily access the information you need.

Subscriptions - Set of Books - Subscription Files

Email Folder

The processed subscriptions, including processed warnings, are stored in your system's default file explorer within two folders: the *'Email folder'* and the *'Files folder*'.



- Email Folder: The *'Email folder'* is located within the Set of Books folder. It contains:
    - o Processed Invoices and Quotes: These files are named after the document number.
    - o Processed Warnings: These files are named after the debtor account name.

Both types of files are generated as PDF documents and can be printed using your system's default PDF application or any program associated with PDF files.

- Printing and Previewing
  - Select an Invoice or Quote: Double-click to print the selected document.
  - Preview: If the Preview feature is enabled in your file explorer, you can preview the document before printing.

Example : Printed invoice



Example : Printed Warning layout



Files Folder

The Files folder stores your email messages in sub-directories organised by the year and month in which the emails were sent.



Some key features is:

- Document Files (Invoices or Quotes): These files are named to include the document number.
- Warning Files: These files are named with a date-time stamp and do not include a document number.

- Accessing and Searching
  - Opening an Email: Double-click on a selected item to open the email message using your system's default application or program associated with the *.eml file type.
  - Searching: Use the search box in your file explorer to find specific email messages. For example, you can search by:
    - Document number
    - Debtor's name
    - Month, etc.

The file explorer will display only the email messages that match your search criteria.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Plugins menu - External system links

E-Commerce Plugin

E-Commerce Plugin - E-Commerce manual - osCommerce manual - Shop - Licence : Annual licence

Transform your online business operations with our E-Commerce Plugin. Seamlessly integrate multiple branded webshops with osFinancials5/TurboCASH5 using our annual licenced solution.

Effortlessly exchange data between your webshops and accounting software, enabling smooth synchronisation of transactions and inventory. Our E-Commerce Plugin currently, supports various systems including osCommerce (also every fork of osCommerce), Zen Cart, Virtuemart, X-cart, Onestopwebshop.nl, Magento, OpenCart, Tomato Cart, Presta shop, offering flexibility and compatibility for your e-commerce needs.

Unlock the power of efficient data exchange and streamline your online business management with the E-Commerce Plugin.

Mijnwinkel Plugin / MyShop

Mijnwinkel Plugin / MyShop - Manual - Shop - Licence : Once-off

Enhance your e-commerce experience with our MyShop Plugin. With a one-time licence, unlock powerful features designed to streamline product management and order processing between osFinancials and myshop.com.

Effortlessly export selected products to a CSV file, automate uploads to myshop.com, and manage product images with ease. Plus, take advantage of additional services such as FTP hosting for seamless integration.

Simplify order processing by importing orders, customer information, and order statuses directly into osFinancials5/TurboCASH5. Keep your inventory up-to-date by uploading product lists for stock quantity updates in myshop.com.

Whether you're starting fresh or have an existing myshop.com webshop, our plugin makes it easy to generate and sync products between osFinancials and myshop.com, ensuring a smooth and efficient e-commerce operation.

Web Export Plugin

Web Export Plugin - Manual - Shop - Licence : Once-off -

Empower your online presence with our Web Export Plugin. With a one-time licence, effortlessly create exports for your website, streamlining the process of updating and maintaining your online content.

Key Features:

- Simplified export process for websites.
- One-time licence for convenience.
- Seamless integration with your existing website platforms.
- Enhance efficiency in updating and maintaining online content.

Take control of your online presence and elevate your website with the Web Export Plugin.

Dutch Plugins

If activated in the Tools → Activate plugins, the following plugins will be listed on the Plugins menu:

External system links

Postalcode / tax id / reg. no. lookup Plugin

Postalcode / tax id / reg. no. lookup Plugin - (Postal Code / Tax ID / Registration Number Lookup) - Shop - Licence : Supported language: Netherlands

This Dutch plugin enables users to perform lookup checks for KVK numbers, allowing for quick and efficient verification of postal codes, tax IDs, and registration numbers.

Key Features:

- KVK Number Verification: Seamlessly verify KVK (Kamer van Koophandel) numbers to ensure accuracy and legitimacy of business entities.
- Postal Code Validation: Validate postal codes to ensure correct addressing and compliance with postal regulations.
- Tax ID Verification: Verify tax identification numbers (BTW/VAT numbers) for tax compliance and accuracy.
- Registration Number Lookup: Efficiently lookup and validate registration numbers to ensure compliance with regulatory requirements.

With the Postal Code / Tax ID / Registration Number Lookup plugin, users can enhance data accuracy, streamline processes, and ensure compliance with Dutch regulations.

Promeetec Export Plugin

Promeetec Export Plugin - Shop - Licence : Annual subscription.

Supported language: Netherlands. Once activated, you can access this plugin from the Plugins → External system links → Promeetec menu.

Streamline your healthcare administration with our Promeetec Export Plugin, tailored specifically for

Netherlands-based healthcare administration. Developed in collaboration with experts in healthcare administration, this plugin simplifies the selection of criteria, reconciliation, and exporting in Promeetec format, enabling easy claiming via email.

Key Features:

- Select open items based on criteria
- Reconcile selected items
- Export in Promeetec format
- Generate reports on processed batches
- Future development potential: Parsing return messages for detecting deviations.

Optimize your healthcare administration processes with our Promeetec Export Plugin, designed to meet the unique needs of Netherlands-based healthcare administration.

Send Package Plugin

Send Package Plugin - Manual - Shop - Licence : Once-off -

Streamline your shipping process with our Send Package Plugin, designed specifically for the Dutch market. With a one-time licence, seamlessly integrate with Dutch and German couriers including GLS, Parcelware, DPD, PACKS, UPS, DHL EasyShip, and Shops unlimited.

Key Features:

- Simplified shipping process.
- Integration with Dutch and German couriers.
- Supports GLS, Parcelware, DPD, PACKS, UPS, DHL EasyShip, and Shops unlimited.
- Designed for the Dutch market.

Optimise your shipping operations and improve efficiency with our Send Package Plugin, tailored for the unique needs of the Dutch market.

Created with the Standard Edition of HelpNDoc: Produce online help for Qt applications

Plugins menu - Financial tools

Activa Plugin

Activa Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Maximize your accounting efficiency with our Activa Plugin. Designed for managing fixed assets, this plugin automates the depreciation process in your accounts, ensuring accurate and timely calculations.

Key Features:

- Streamlined depreciation management for fixed assets
- Periodic notifications for new asset purchases and depreciation processing
- Asset registration for automated depreciation allowances
- Simplified management of fixed asset depreciation within your Set of Books

Optimize your accounting practices and ensure compliance with depreciation regulations with the Activa Plugin.This plugin will help you with the depreciation of fixed assets in your accounts. Periodically you will receive a notification screen, to list the new purchases of assets as well as those assets, you need to calculate and process depreciation.

Charter

Charter Plugin - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Translations : Outstanding

Unlock powerful visualization capabilities with our Charter plugin. Seamlessly generate insightful charts and graphs directly from your Set of Books data, empowering you to make informed decisions and communicate key insights effectively. Save charts as image files for integration into documents, presentations, spreadsheets, and more.

The Charter Plugin enhances your experience by adding a Charter tab on the Debtor accounts, Creditor accounts, and Stock items. This allows you to build and customise charts effortlessly. Within the Debtors grid, Creditors grid, and Stock item grid, simply right-click to launch the "*Charter*" screen from the Plugin action → Charter context menu.

In the Documents grid, you can also access the "*Charter*" screen by right-clicking and selecting the Plugin action → Charter context menu. This feature enables you to launch the " *Doc value*" or "*Debtors*" charts.

Additionally, in document entry screens for both posted and unposted sales documents such as invoices, credit notes, quotes, purchases, supplier returns, and orders, an icon will be available to launch the "*Charter*" screen.

Furthermore, the "*Charter*" plugin seamlessly integrates with other plugins supporting the "*Charter*" functionality.

DrillDown

DrillDown plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Translations : Outstanding

The "*TC DrillDown*" plugin for osFinancials5/TurboCASH5 streamlines data analysis and reporting. With robust features, it offers quick access to transaction details, customer invoices, and sales data through customizable views. Its intuitive interface includes powerful grid search and filter options, along with visual charts for sales analysis. Additionally, users can export data to XML, HTML, Excel, or Text files, facilitating further analysis or integration with other tools. This makes it a valuable tool for efficient financial management and decision-making.

Office Pro

Office Pro - Manual - Shop - Licence : Annual subscription -

Translations : Outstanding

Remittance

Remittance - Shop - Licence : Once-off -

Documentation : osFinancials website - Manual

Documentation : Help documentation

Translations : Outstanding

The Remittance Plugin in osFinancials5/TurboCASH5 facilitates the streamlined management of outstanding items. With this plugin, you can efficiently send reminder emails to all debtors regarding their outstanding amounts and totals. Additionally, the plugin enables you to review unpaid invoices of your customers and

send them reminders with detailed open amounts.

You have the flexibility to customize the layout of these reminders according to your preferences or specific requirements, and the option to utilize multiple layouts for different purposes. Simplify your accounts receivable process and enhance communication with debtors using the Remittance plugin.

Financial tools - Nederlands en Belgium

BtwBE - Belgische BTW Plugin

BtwBE - Belgische BTW Plugin - Manual - Shop - Licence : Supported language: Netherlands

The Belgian VAT Plugin provides support for the specific VAT regulations in Belgium. With this plugin, you can easily and accurately perform VAT calculations according to Belgian regulations and reporting requirements.

XML Audit file Plugin

XML Audit file Plugin - Shop - Licence : Supported language: Netherlands

The XML Auditfile Plugin, tailored for the Dutch market, facilitates the seamless export and import of ledger, debtor, creditor, and transaction data in XML format. This standardized format ensures that transaction data remains accessible by any system capable of reading XML, promoting interoperability across various platforms and applications.

Recognized by the Dutch government, the XML Auditfile serves as a valid backup for electronic transaction data, meeting regulatory requirements and enhancing data security practices.

Furthermore, the widespread adoption of this format has led to the emergence of complementary products in the Dutch market. Software solutions designed to generate comprehensive yearly overviews can now import data seamlessly, while other financial software offerings provide export and import capabilities, allowing users the flexibility to access and analyse data in their preferred programs. Experience enhanced data management and interoperability with the XML Auditfile Plugin.

Created with the Standard Edition of HelpNDoc: Make Documentation Review a Breeze with HelpNDoc's

Activa plugin

Activa plugin - Manual - Shop - Licence : Once-off -

The Activa plugin automates the management and processes of fixed assets and the depreciation of fixed assets in your accounts over the lifespan of the fixed assets. Periodically you will receive a notification screen, which the depreciation shown. From this screen, the depreciation(s) can directly take place.

Translations : Outstanding

Introduction to Activa plugin

The Activa plugin in osFinancials5/TurboCASH5 allows you to register fixed assets that need to be written off. The write-off process occurs over the lifespan of the asset and can be spread across multiple financial years.

By adding the Activa Fixed asset accounts in the plugin setup, you will receive reminders when new transactions are posted to the ledger or when Activa transactions require processing. This automation streamlines the management of depreciation allowances for fixed assets (tangible assets) in your Set of Books over the asset's lifespan.

As you record the depreciation expenses for each financial year, they will be reported in the income statement and reduce your net profit. Additionally, the plugin will provide you with the net value of your fixed assets, which is calculated as the fixed assets' cost minus the accumulated depreciation, and this information will be reflected in the balance sheet.

In summary, the Activa plugin helps automate the depreciation management process, ensures accurate reporting of depreciation expenses, and provides visibility into the net value of fixed assets over their lifespan in both the income statement and the balance sheet.

When a fixed asset reached the end of life end process that will clear of the total write-off from the balance write-off account and the initial asset account. This will display only the remaining total on the asset account and the contra account the will be cleared of this total.

By allowing the write-off process to occur over the lifespan of the asset and providing reminders for transaction processing, the plugin further streamlines the management of depreciation allowances for fixed assets.

The accurate reporting of depreciation expenses in the income statement and the reflection of the net value of fixed assets (cost minus accumulated depreciation) in the balance sheet remain essential features

of the plugin.

Furthermore, the ability to clear the total write-off from the balance write-off account and the initial asset account when a fixed asset reaches the end of its life adds to the efficiency of the process.

The Activa plugin's powerful grid, custom filtering options, and integrated pivot tables enhance the search and analysis capabilities for active fixed assets, assets requiring processing, and transaction details. The Ledger analyser allows for the printing and exporting of the trial balance, income statement, and balance sheet, while the T-Account viewer facilitates the export of transactions to spreadsheets.

The Central search feature in osFinancials5/TurboCASH5 further aids in searching for transactions related to fixed assets, providing comprehensive functionality for managing and analysing fixed asset data.

If you have created new accounts for your assets in the, select Setup → Accounts (Setup ribbon), you need to launch the Activ
new asset accounts.

Fixed assets is usually recorded as follows in the Trial balance as follows:



Depreciation expense account (Income statement)

The total expense of depreciation transactions written-off in the selected financial period.

Fixed assets accounts (Balance sheet)

The Main account of the asset displays the net value of the asset. This is the cost price minus the accumulated depreciation o span of the asset. Thus is the NETT VALUE of the asset class.

The Asset at cost price displays the purchase price and may include any additional cost incurred to make the asset useful for costs).

The Asset accumulated depreciation account displays the total amount written-off over the lifespan of the asset as at the sp the depreciation transactions over the lifespan of the asset (which includes previous financial years.

When a fixed asset reached the end of life end process that will clear of the total write-off from the balance write-off account and the initial asset account. This will display only the remaining total on the asset account and the contra account the will be cleared of this total.

Activa - Reports tab - Pivots tab Activa - Reports tab and Data tab allows you to filter and analyse your purchase, write-off and end of life transactions during the life span of fixed assets.

Processing Activa transactions

The process for the management of Activa transactions, is as follows:

1. Activate the Activa plugin and setup.
    - Link the Fixed asset accounts for each fixed asset.
    - Add and link a Batch to process the write-off transactions.
2. Add Activa transactions
    - New transactions - All new transactions which is allocated to the Transactions - Fixed assets at cost account will be listed when purchase transactions in batches and purchase documents is posted (updated) to the ledger. You need to add the new transactions to the Activa - List tab.
    - Add manual - You may also add Fixed assets manually.

Each time you Open the Set of Books, the Activa plugin will be launched, when:

1. *Transactions need processing - If there is any depreciation allowances to write-off. If you have already processed the transactions, it will be launched at the next processing date.*
2. *New transactions - All new transactions in posted batches (e.g. Purchase journal, Purchase returns journal, Payments journal, etc.) and purchase documents (e.g. Purchase and Supplier returns) (using the Financial Stock item type) is posted (updated) to the ledger.*

3. Specify the details of a fixed asset on the Activa - Details tab the write-off details. This is basically a once-off process for each fixed asset in which you need to specify the write-off method (percentage or amount) which will determine the number of years and calculations for the life span of the Fixed asset. This will schedule the next write-off date when transactions need processing.
4. Process the depreciation transactions - On the Activa - List tab, you need to process the write-off transactions. This will calculate and update the depreciation, book value, and write-off amounts, etc., for the fixed asset.

5. Activa - Reports tab - Pivots tab Activa - Reports tab and Data tab allows you to filter, view, sort and analyse your purchase, write-off and end of life transactions during the life span of fixed assets.

Created with the Standard Edition of HelpNDoc: Experience a User-Friendly Interface with HelpNDoc's Documentation Tool

Activate the Activa plugin and setup

Activa setup

Before you start with the Activa Setup, it is recommended that you:

1. Create (add) a batch type for the Activa transactions (e.g. Activa journal).
2. Check your Assets for any combined transactions (e.g. opening balances) and split them to the correct asset items. You may have purchased for example 2 or more motor vehicles but have entered them as a combined balance. You may need to correct this as separate entries (e.g. using the General journal or Activa journal). Obtain the following details (in the Asset register) for each of these assets:
    - Description
    - Purchase date
    - Purchase amount
    - Write-off type (Percentage or amount per period)
    - Write-off period (per month, quarter, 6 months or per annum)
    - Rest amount (Salvage value, scrap value or trade-in value, etc.).
    - Current Amount - the book value of the asset as per last write-off)
    - Any extra information (you may add these extra text).
    - Life span of the asset and method of depreciation.

Activate the Activa plugin

This Plugin will need to be activated for each Set of Books, if you need to use this plugin in other Sets of Books.

To activate the Activa plugin:

1. On the Setup ribbon, select Plugins → Financial tools → Activa. If this plugin is not listed under Plugins → Financial tools, activate it via Tools → Activate plugins.

2. Click on the On radio button and click on the Save button. The Activa screen will be closed.

3. Relaunch the Activa plugin (from the Plugins → Financial tools → Activa menu (see step 1). The Activa tab and the General tab will be displayed.



You may use the record buttons to save and manage records.

You may click on any of the column headings (i.e. Transactions, Balance or Income statement) and drag it to the left or right to change the sequence in which to display the columns.

4. You need to select the following 3 accounts for each of your assets:

   a) Transactions - Select the Asset account (the account on which all assets are purchased). This should be reported in the Balance sheet.

   b) Balance - Select the Asset's Accumulated depreciation account (the contra account on which the asset's depreciation are recorded). This should be reported in the Balance sheet.

   c) Income statement - Select the account for the expenses to write-off (e.g. Depreciation account). This should be reported in the Income statement.

If you have created new accounts for your assets in the Setup ribbon, select Setup → Accounts menu, you need to the new asset accounts.

Fixed assets is usually recorded as follows in the Trial balance as follows:



Depreciation expense account (Income statement)

The total expense of depreciation transactions written-off in the selected financial period.

Fixed assets accounts (Balance sheet)

The Main account of the asset displays the net value of the asset. This is the cost price minus the accumulated d span of the asset. Thus is the NETT VALUE of the asset class.

The Asset at cost price displays the purchase price and may include any additional cost incurred to make the ass

costs).

The Asset accumulated depreciation account displays the total amount written-off over the lifespan of the asse

the depreciation transactions over the lifespan of the asset (which includes previous financial years.

5. Click on the General tab.



6. Select a batch (journal) (e.g. General journal, Activa journal) for your depreciation transactions.

If you did not select a batch and you are trying to add an Activa assets or manually add an Asset an error message will be displayed.

"No batch selected please select batch in setup!"

You then need to click on the OK button and select a batch to process activa transactions.

If you wish to use a specific batch type (not available on this list), e.g. Depreciation journal (or any other batch type) you may add it in the Setup → Batch types (Setup ribbon). To do this you need to click on the Save button and add the batch type.

Should there be any transactions in the batch type (selected from this list), e.g. General journal, an error message will be displayed.

"Batch is not empty!"

You then need to click on the OK button and process the transactions in the selected batch. To avoid this, it is recommended that you create (add) a separate batch for the Activa plugin transactions.

7. Select the Show for this user option. The Activa plugin may be deactivated for other users in a multi-user environment.
8. Click on the Save button.
9. Reopen the Set of Books to add the Activa icon on the Default ribbon.



Created with the Standard Edition of HelpNDoc: Why Microsoft Word Isn't Cut Out for Documentation: The Benefits of a Help Authoring Tool

Add Fixed assets to the Activa plugin

New transactions tab

The New transactions tab within the Activa-plugin is designed to display new transactions associated with specific accounts, particularly fixed asset accounts. It's activated under two conditions:

1. New Fixed Asset Accounts: If you add new fixed asset accounts to the Activa Setup Aciva tab, the New transactions tab will automatically appear. This ensures that you can immediately track any transactions related to these newly added assets.
2. New Transactions in Existing Accounts: If any of your existing fixed asset accounts, receive new transactions, the New transactions tab will also become visible. This allows you to promptly review and process these incoming transactions.

Additional Features:

- Automatic Updates: The New transactions tab updates automatically as new transactions are recorded in the Set of Books. This means you don't have to manually launch the tab to see the latest information.
- Filtering Options: The tab may provide filtering options to help you narrow down the displayed transactions based on specific criteria, such as date range, accounts, amounts, reference and decription of the transaction.
- Transaction Details: Clicking on a transaction listed in the tab typically provides detailed information about that transaction, including its date, amount, description, and associated account.

Overall, the New transactions tab is a valuable tool for effectively managing and monitoring transactions related to fixed assets and other accounts within the Activa-plugin.



Context menu - Add consolidated:

If you wish to consolidate (merge) more than one transaction to one (1) record, you may right-click and select the Add consolidated option. This will add the selected transactions as one (1) transaction on the Activa - List tab.

This would normally be the case where a specific asset consists of more than one transaction (e.g. Purchase transaction of the asset and any other transactions, for example to install that asset and make it usable and operational).

Once transactions in batches and documents is posted (updated) to the ledger, the transactions will be added to the Activa - New transactions tab.

You need to add these new transactions to the Activa - List tab by clicking on the Add (selected) lines button.

Activa - List tab

Once the Fixed assets is added from the the Activa - New transactions tab (Add (selected) lines button) add these new transactions is added to the Activa - List tab.

Add manual button - You may also Add manual transactions and set up and configure these transactions manually on the blank Activa - Details tab.

Stop check for 7 Days button - The default value is 7 days. The Fixed assets which need processing (on the "*Next process date*") will automatically launch after 7 days from that date. You may set the number of days according to your specific needs.

Before you start to process any Activa lines, you need to make absolutely sure that each of your Fixed

assets is correctly set and configured. If any information is incorrect, or you need to change the information listed in the columns of the Activa - List tab, click on the Activa - Details tab of the selected Fixed asset.

Once you click on the on the Process (selected) lines button, this will process the Activa write-off transactions and automatically post (update) these transactions to the ledger.



Activa - Details tab

Once the new transactions is added to the Activa - List tab, you need to specify the settings and options for each fixed asset type on the Activa - Details tab. This is a once-off process for each fixed asset during the life span of the Fixed asset.



Tax Legislation, Companies Act and accounting standards in some countries may prescribe different methods to write off depreciation (wear and tear allowances) over the life span for the types of fixed assets.

When you add Fixed assets, you need to decide the method on which depreciation is calculated for the assets. These values only needs to be set once for a Fixed asset on the Details tab of the Activa plugin. The depreciation will be written-off each period over the life span of the fixed asset.

Some of these methods to calculate depreciation is:

1. *Straight-line method (fixed instalment method)*
2. *Declining balance method (Reducing-value method)*
3. *Double-declining balance*
4. *Production method*
5. *Sum-of-years digits*

In addition to these methods, items (assets purchased for less than a prescribed amount) may be written-off in full.

The on the Activa - Details tab need to check and include the following for the fixed asset depreciation transactions:

1. Description - The description of the transaction consists of the Purchase document number and item description.
2. Extra description - Add additional text (up to 50 characters) for the fixed asset depreciation transactions.
3. Purchase amount - The purchase amount (cost amount), excluding Tax (VAT/GST/Sales tax) of the fixed asset will automatically be displayed. Check the Purchase amount. If you have entered any opening balances, please make sure that you enter the correct value of the asset here.

If you wish to consolidate (merge) more than one transaction to one (1) record, you may right-click and select the Add consolidated option on the Activa - New transactions tab. This will add the selected transactions as one (1) transaction on the Activa - List tab.

This would normally be the case where a specific asset consists of more than one transaction (e.g. Purchase transaction of the asset and any other transactions, for example to install that asset and make it usable and operational).

4. Purchase date - The date of the purchase transaction in batches or purchase documents.
5. Next process date - This date will be automatically calculated as determined by the Write-off period (e.g Months, 3 Months, 6 Months or Year).
6. Rest amount - The Rest amount, is by default zero "0". Enter the salvage value amount, scrap value, trade-in value) at the end of the fixed asset's life span (after all depreciation amounts is written-off) if

applicable.

7. Current value - The Current value is the Purchase amount minus any Rest value, if applicable to the Fixed asset. In subsequent periods (years as in this example) after depreciation transactions is processed, the value would reduce by the write-off transactions. Once the last depreciation transactions is processed at the end of the fixed assets life span, the current value should be the dame as the "Rest amount". If no "Rest amount" is specified, the current value would be zero.
8. Enabled - By default all Fixed assets are active, if there is any write-off transactions. Once you have done the final write-off, the Fixed asset will be set to inactive.

Once the final depreciation or write-off amount is reached, the following confirmation message will be displayed:

"Write off for Asset description ended do you want to clear the activa accounts?"

If select Yes to you clear the Activa account, the "End of life" entry will be displayed.

9. Write-off type - Select Percentage or Amount.
10. Percentage / Amount - Enter the percentage or the amount (depending on the selection in the "*Write-off type*" options).
11. Write-off period - Select Month, 3 Months, 6 Months or Year.
12. Next write-off amount -

Once finished, click on the Save record button to refresh the calculations and save your changes.

You may click on the Activa - List tab to select a another Fixed asset to configure the Fixed asset.

Once finished you may click on the OK button to exit the Activa screen.

Created with the Standard Edition of HelpNDoc: Free EBook and documentation generator

Process Fixed assets in the Activa plugin

Activa processing

Once the Activa plugin is activated, you may access the Activa plugin manually on the Default ribbon.



The Activa plugin will launch automatically when:

New transactions tab - Purchase or any transaction is allocated and posted top the ledger to the Asset at cost account.

Next process date - If an asset needs processing and the processing date is due to write off depreciation.

Once the Activa plugin is activated, and you launch it for the first time, you need to add the new transactions.

The Activa - New transactions tab will list all existing transactions in posted batches and documents allocated to the accounts as selected on the Activa setup.



Select the transaction and click in the Add (selected) lines button. The transactions will be removed from the New transactions tab added to the List tab.

Multi-select records:

Press the Ctrl key and click on the transactions.

Context menu - Add consolidated:

If you wish to consolidate (merge) more than one transaction to one (1) record, you may right-click and select the Add consolidated option. This will add the selected transactions as one (1) transaction on the Activa -

List tab.

This would normally be the case where a specific asset consists of more than one transaction (e.g. Purchase transaction of the asset and any other transactions, for example to install that asset and make it usable and operational).

Once finished, adding the transactions, you need to select the items from the list and check and change the details as necessary on the Activa - Details tab.

If there are no new posted transactions in batches and or documents the New transactions tab will not be displayed.

When any further transactions in batches and documents are posted (updated) to the ledger, it will automatically be added to the New transactions tab.

When opening the Set of Books and any new transactions are added (posted or updated to the ledger), the Activa plugin New transactions tab will automatically be launched.

Activa - List and Details

Once the Fixed assets is added from the the Activa - New transactions tab (Add (selected) lines button) add these new transactions is added to the Activa - List tab.

Add manual button - You may also Add manual transactions and set up and configure these transactions manually on the blank Activa - Details tab.

Stop check for 7 Days button - The default value is 7 days. The Fixed assets which need processing (on the "*Next process date*") will automatically launch after 7 days from that date. You may set the number of days according to your specific needs.

Before you start to process any Activa lines, you need to make absolutely sure that each of your Fixed assets is correctly set and configured. If any information is incorrect, or you need to change the information listed in the columns of the Activa - List tab, click on the Activa - Details tab of the selected Fixed asset.

Once you click on the on the Process (selected) lines button, this will process the Activa write-off transactions and automatically post (update) these transactions to the ledger.

Once new purchase transactions is allocated to the "*Transactions*" account (Asset at cost account) and the transactions is posted in batch transactions (e.g. Purchase journal) or Items selected in documents updated to the ledger, the transactions will be listed on the New transactions tab of the Activa plugin.

Once the selected lines is added to the List tab, you need to specify the necessary information and values

of each asset.

Tax Legislation, Companies Act and accounting standards in some countries may prescribe different methods to write off depreciation (wear and tear allowances) over the life span for the types of fixed assets.

When you add Fixed assets, you need to decide the method on which depreciation is calculated for the assets. These values only needs to be set once for a Fixed asset on the Details tab of the Activa plugin. The depreciation will be written-off each period over the life span of the fixed asset.

Some of these methods is:

1. *Straight-line method (fixed instalment method)*
2. *Declining balance method (Reducing-value method)*
3. *Double-declining balance*
4. *Production method*
5. *Sum-of-years digits*

In addition to these methods, items (assets purchased for less than a prescribed amount) may be written-off in full.

1. Once you have activated the Activa plugin, you may click on the Activa icon on the Default ribbon. The Activa - List screen is displayed:



All transactions (including opening balances) will automatically be imported in this list. All unprocessed transactions will be indicated in red row.

Once these have been processed, these will be indicated in a white background.

Filter - Use the following Filter options to locate an asset record:

- *All is the default option. It will list all records.*
- *Need processing - This option will list only the assets that need processing (automatic journals).*
- *Active - This option will list all the active records only. If asset records are inactive (Active field not*

selected (not ticked) on the Activa - Details screen, it will not be listed.

2. The details for each of these asset transactions, will be displayed in the following columns:

   a) Next process date - By default this will be the system date. Later when processing the transactions, it will be the date as set in the write-off period.

   b) Description - The transaction reference and description as entered in batches which are updated (posted) to the ledger. In the case of documents, this will be the document number and the item description.

   c) Purchase amount - The purchase amount of the posted transaction in batches and documents. Note this should be exclusive of VAT/GST/Sales Tax).

   d) Current value - This is calculated as the current value minus any transactions processed in the Activa journals.

   e) Extra description - The extra text or descriptions entered on the Activa - Detail tab. The extra descriptions can contain up to 50 characters.

   For example, asset number on your asset register (Asset inventory), the method for calculation of Depreciation, reference to the Management's write-off authorisation (decision), reference to the section of the Tax Act of Tax Practice Note, etc.

   f) Purchase date - The date of the purchase transaction is the document date or the date in journals to updated (posted) the ledger.

   g) Write-off type - The values are as follows:

      § Amount per Period

      § Percentage per Period.

   h) Write-off period - The values are as follows:

      § 1 Month

      § Quarter (3 Months)

      § Half year (6 Months)

      § Year (12 Months)

   i) Enabled - The values are as follows:

      § 1 = Enabled (active)

      § 0 = Inactive (Enabled) not selected on the Activa - Details tab).

Once the final depreciation or write-off amount is reached, the following confirmation message will be displayed:

"Write off for Asset description ended do you want to clear the activa accounts?"

If select Yes to you clear the Activa account, the "End of life" entry will be displayed.

j) Linked transaction - The transaction id number as automatically generated.

k) Rest amount - This is the nominal value, scrap value, trade-in value, etc. of the assets at the end of its life span, that needs to be reflected in the balance sheet.

Tax Legislation and accounting standards in some countries may require a nominal value (e.g. 1.00) to be displayed. This simply means that the Asset is completely written-off, still on the business books or in use. Once that asset is disposed of, the nominal value will be written-off when determining the profit or loss with the sale of the fixed asset.

l) Write-off percentage – If the write-off type is set to Write-off percentage, the Write-off percentage (e.g. per month, quarter (3 months), 6 months (half-year) or year (12 months)) will be displayed.

m) Write-off amount – If the write-off type is set to Write-off amount, the write-off amount (e.g. per month, quarter (3 months), 6 months (half-year) or year (12 months)) will be displayed.

n) Next Write-off amount - This will automatically be calculated.

o) Total Write-off on ledger - This amount will automatically be calculated. It accumulates the total of all transactions posted to the write-off account.

3. Once you have located an entry on the Activa - List tab, click on the Details tab. The following screen is displayed:



You may use the record buttons to save and manage records.

4. Enter and/or select the following options:

   a) Description - This is the description of the transaction.

   b) Extra description - Add additional text for the depreciation transactions.

   c) Purchase amount - The purchase amount (cost amount), excluding Tax (VAT/GST/Sales tax) of the fixed asset will automatically be displayed. Check the Purchase amount. If you have entered any opening balances, please make sure that you enter the correct value of the asset here.

   d) Purchase date - The date of the purchase transaction is the document date or as entered in batches which are updated (posted) to the ledger The date of the purchase transaction is the document date or as entered in batches which are updated (posted) to the ledger

   e) Next process date - The date on which the next depreciation is scheduled for processing.

   f) Rest amount - The Rest amount, is by default 0. Enter the rest amount, scrap value (trade-in value) of the asset, if applicable.

g) Current value - The current book value or holding value.

h) Write-off type - Select Percentage or Amount.

i) Percentage / Amount - Enter the percentage or the amount (depending on the selection in the "*Write-off type*" options).

j) Write-off period - Select month, 3 months, 6 months or year.

k) Next write-off amount - The next amount of depreciation that will be processed.

5. Once finished, click on the OK button.

Process Activa records

Before you need to process depreciation (wear and tear allowances) make absolutely sure that the correct settings and details is listed for each asset class. You may need to consult the tax guidelines and practice notes issued by your tax authorities or other legislation applicable to your specific country.

If this is not correct at this stage, select the asset and click on the Details tab to edit the necessary fields.

To process transactions for depreciation (wear and tear allowances):

1. On the Activa - List screen, use the Filter options to list the asset records the need processing.



2. Select an asset record and make absolutely sure that the asset's details is correct.

Multi-select records:

Press the Ctrl key and click on the transactions.

3. Click on the Process (selected) lines button. The Activa plugin will generate the necessary transactions in the selected batch (e.g. Activa journal) and update (post) these transactions to the ledger.

Once the final depreciation or write-off amount is reached, the following confirmation message will be displayed:

"Write off for Asset description ended do you want to clear the activa accounts?"

If select Yes to you clear the Activa account, the "End of life" entry will be displayed.

If the "Next process date" is scheduled and the New Financial year is not opened for the scheduled process date, an error message will be displayed:

"Process failed please check batch!"

Click OK. When the Year-end process is finalised, you may proceed to process the selected Fixed assets.

4. Select the next Activa record, and repeat his process. Each of the processed lines for a selected asset in the Activa plugin will list the transactions in the "*Posted transactions*" section of the Activa - Details tab. This will keep track of all transactions and amounts written-off over the life span of the asset.



5. Once this is done, click on the OK button to exit close the Activa plugin.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Activa reports

Activa Transactions and Reports

Activa transactions

The transactions generated by the Activa plugin are as follows:

- Purchase - The purchase transactions can be processed in journals and documents. You must update (post) these transactions in documents to the general ledger. After that, you need to set up each asset's details correctly.
- Depreciation - The transactions for writing off transactions for depreciation (value reduction) are entered in the Activa journal or other unique journal that you have selected for the Activa plugin in the setup. These transactions are automatically calculated according to the details and percentages or amounts you specified for each asset. When these transactions are processed in the Activa plugin, this journal will automatically update to the ledger.

All updated transactions will be included in all reports for the specific fixed asset accounts, depreciation (reduction in value) accounts, creditors' (supplier's) accounts as well as Tax (VAT/GST/Sales tax) accounts.

Other Report options

The Activa - Report - Pivot tab allows you to group, sort, filter the totals and fixed asset transactions generated with the Activa plugin according to your specific requirements.. You can also analyse your transactions in the Pivot functionality on the Ledger analyser 1 or Ledger analyser 2 to analyse your data and build advanced filters.

In addition to the reports on the Reports menu and User reports menu (Reports ribbon), documents and reports can also be found and printed on other functionalities in osFinancials5/TurboCASH5. Some of these options include:

- Ledger analyser 1 or Ledger analyser 2 - Trial Balance, Balance Sheet and Income Statement, etc. You can also use the Pivot functionality on theLedger analyser 1 or Ledger analyser 2 to analyse your transactions and data You may build advanced custom filters.
- Search (Investigator) -
    - Document type - Print a document for purchase transactions.
    - Batch type Initiate the T-Accounts. You can print your transactions for depreciation in the T-Accounts. You can even print the transactions for a specific asset's accumulated depreciation

(depreciation) or the creditors' (suppliers') accounts and even VAT accounts. In addition, you can filter the transactions per account over the period of the life of the assets and export them to a spreadsheet.

- Creditor (Supplier) accounts -
  - Documents tab - You can print specific documents for the purchase transactions.
  - Transactions tab - For specific transactions, you can right-click to select the Show transactions context-menu option. This will display the selected transactions on the Transactions screen. You can then print the Posted journal transactions.
  - Stock item tab - This will list all the assets that have been purchased.
- Stock items - You can select a document on the Document groups tab and print the document.
- Spreadsheet reports - You can display the Transactions per period or even for a period spanning the life of the assets and use the Save as options to open the transactions in your favourite spreadsheet program.
- T-Accounts - You can print your transactions for depreciation in the T-Accounts. You can even print the transactions for a specific asset's accumulated depreciation (depreciation) or the creditors' (suppliers') accounts and even Tax (VAT/GST/Sales tax) accounts. In addition, you can filter the transactions per account over the period of the life of the assets and export them to a spreadsheet.

Activa transactions - Reports tab

Activa - Reports - Pivot tab - Processed transactions

The Activa - Reports - Pivot tab allows you to group, sort, filter Activa totals and transactions, according to your specific requirements. The Activa - Reports - Pivot tab is a powerful tool for analysing and summarizing your fixed asset transactions. It allows you to group, sort, and filter data to meet your specific needs.

If a new asset is purchased, it will only list the purchase transactions type. Once the depreciation transactions is processed, the Write-off transactions for the asset will be listed.

To view the details of an asset, expand a transaction, click on the icon and to collapse (hide) click on the icon.





The default view of the Pivot for the Activa plugin, is grouped in four sections (i.e. Filter Area, Data Area, Row Area and Column Area) and is as follows:

Filter Area:

1. Reference - The “*Reference*” is as follows:
    - Documents - Document number as generated when creating documents.
    - Batches - The "*Reference*" - as generated when the transactions (lines) on the Activa - List tab were processed ("*Write off*" or "*End of life*") transactions is generated. If Purchase transactions of Assets is processed on different dates, it will create new "*Reference*" for each asset.

*If asset purchases is processed in "Batch entry" screens, the reference as entered the “Reference” column of "Batch entry" screens will be listed. The reference of Balancing entries in batches is indicated with eight (8) asterisks “********”.*

2. Description - Transaction description
    - Documents - The document type (i.e. Purchase and Supplier returns) and the description of the Asset item or description of the asset as entered in the "*Description*" column of the document lines.
    - Batches - The description of the transaction entered in the “*Description*” column of "*Batch entry*" screens. The reference of Balancing entries in batches is indicated with eight (8) asterisks “********”.

*If asset purchases is processed in "Batch entry" screens, the reference as entered the “Description” column of "Batch entry" screens will be listed. The reference of Balancing entries in batches is indicated with eight (8) asterisks “********” and is added to the "Description".*

3. Account name - The account name or account description of the Asset account at cost and Asset accumulated depreciation account (Balance sheet) or Depreciation (Income Statement) account.
4. Date week - The number of the week (from 1 to 53) for a calendar year.
5. Account type - Balance sheet or Income statement.
6. Rest amount - The amounts entered for the scrap value (trade-in value) of the asset at the end of the asset's life cycle (in the "*Rest value*" field of the Asset's detail form.

Data Area:

7. Amount - The debit amounts will be listed. Credit amounts (prefixed by a - (minus sign)) will be listed.

Row Area:

8. Activa - The Purchase document number and the description of the Asset item or description of the asset as entered in the "*Description*" column of the document lines.

9. Transaction type - "*Purchase, Write-off*" or "*End of life*".
10. Account code - The account code of the Asset account at cost (Balance sheet) or Depreciation (Income Statement) account.

Column Area:

11. Date year - The transaction totals will be displayed only for the year which on which purchase and write off transactions were processed. In this example 2021 will be listed for transactions processed for March 2021 and transactions were processed in February 2022.
12. Date month - The transaction totals will be displayed only for the months in which transactions were processed.

PivotGrid Field List

You may right-click on any of the three sections (i.e. Filter Area, Data Area and Column Area) to launch the context menu.



By default, all data fields is listed on the Pivot table. The "Show Filed List" context menu option, will list the empty "PivotGrid Fi fields onto the "PivotGrid Filed List" screen. The selected data field will removed from the Pivot and listed in the be listed "PivotG



You may add it to the "Row Area, Column Area, Filter Area" and "Data Area".

PivotGrid Field List

You may rignt-click on any of the three sections (i.e. Filter Area, Data Area and Column Area) to launch the context menu.



By default, all data filelds is listed on the Pivot table. The "Show Filed List" context menu option, will list the empty "PivotGrid Fi fileds onto the "PivotGrid Filed List" screen. The selected data field will removed from the Pivot and listed in the be listed "PivotG

You may add it to the "Row Area, Column Area, Filter Area" and "Data Area".

Activa - Reports - Data tab - Processed transactions

The Activa - Reports - Data tab lists all purchase transactions of the Fixed assets added and processed as well as the write off transactions over the life span of Fixed assets.



To view the details of an asset, expand a transaction, click on the ⊞ icon and to collapse (hide) click on the ⊟ icon.



Trancation type	Date	Amount	Reference	Description	Account code	Account description	Account type	Rest amount
⊞ Activa : PU000001 Chairs x 12								
⊞ Activa : PU000001 Filing cabinets x 24								
⊟ Activa : PU000002 Computer								
Write off	2022/02/28	-3000	0222	PU000002 Computer	620020	IT Equipment Accum. Depreciation	Balance	0
Write off	2022/02/28	3000	0222	PU000002 Computer	240000	Depreciation	Income expens	0
Write off	2023/02/28	-3000	0223	PU000002 Computer	620020	IT Equipment Accum. Depreciation	Balance	0
Write off	2023/02/28	3000	0223	PU000002 Computer	240000	Depreciation	Income expens	0
Write off	2024/02/28	-3000	0224	PU000002 Computer	620020	IT Equipment Accum. Depreciation	Balance	0
Write off	2024/02/28	3000	0224	PU000002 Computer	240000	Depreciation	Income expens	0
End of life	2024/02/28	-9000	0224	PU000002 Computer	620010	IT Equipment at Cost	Balance	0
End of life	2024/02/28	9000	0224	PU000002 Computer	620020	IT Equipment Accum. Depreciation	Balance	0
Purchase	2021/03/01	9000	PU000002	Computer	620010	IT Equipment at Cost	Balance	0
⊞ Activa : PU000002 Computer software								
⊞ Activa : PU000002 Main frame / Server								
⊟ Activa : PU000003 Delivery van								
Write off	2022/02/28	-7500	0222	PU000003 Delivery van	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2022/02/28	7500	0222	PU000003 Delivery van	240000	Depreciation	Income expens	10000
Write off	2023/02/28	-7500	0223	PU000003 Delivery van	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2023/02/28	7500	0223	PU000003 Delivery van	240000	Depreciation	Income expens	10000
Write off	2024/02/28	-7500	0224	PU000003 Delivery van	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2024/02/28	7500	0224	PU000003 Delivery van	240000	Depreciation	Income expens	10000
Write off	2025/02/28	-7500	0225	PU000003 Delivery van	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2025/02/28	7500	0225	PU000003 Delivery van	240000	Depreciation	Income expens	10000
End of life	2025/02/28	-30000	0225	PU000003 Delivery van	630010	Motor Vehicles at Cost	Balance	10000
End of life	2025/02/28	30000	0225	PU000003 Delivery van	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Purchase	2021/03/01	40000	PU000003	Delivery van	630010	Motor Vehicles at Cost	Balance	10000
⊟ Activa : PU000003 Mercedez-Benz								
Write off	2022/02/28	-6000	0222	PU000003 Mercedez-Benz	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2022/02/28	6000	0222	PU000003 Mercedez-Benz	240000	Depreciation	Income expens	10000
Write off	2023/02/28	-6000	0223	PU000003 Mercedez-Benz	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2023/02/28	6000	0223	PU000003 Mercedez-Benz	240000	Depreciation	Income expens	10000
Write off	2024/02/28	-6000	0224	PU000003 Mercedez-Benz	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2024/02/28	6000	0224	PU000003 Mercedez-Benz	240000	Depreciation	Income expens	10000
Write off	2025/02/28	-6000	0225	PU000003 Mercedez-Benz	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2025/02/28	6000	0225	PU000003 Mercedez-Benz	240000	Depreciation	Income expens	10000
Write off	2026/02/28	-6000	0226	PU000003 Mercedez-Benz	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Write off	2026/02/28	6000	0226	PU000003 Mercedez-Benz	240000	Depreciation	Income expens	10000
End of life	2026/02/28	-30000	0226	PU000003 Mercedez-Benz	630010	Motor Vehicles at Cost	Balance	10000
End of life	2026/02/28	30000	0226	PU000003 Mercedez-Benz	630020	Motor Vehicles Accum. Depreciation	Balance	10000
Purchase	2021/03/01	40000	PU000003	Mercedez-Benz	630010	Motor Vehicles at Cost	Balance	10000
⊟ Activa : PU000004 IT-Equipment								
Write off	2021/03/01	-5000	0321	PU000004 IT-Equipment	620020	IT Equipment Accum. Depreciation	Balance	0
Write off	2021/03/01	5000	0321	PU000004 IT-Equipment	240000	Depreciation	Income expens	0
End of life	2021/03/01	-5000	0321	PU000004 IT-Equipment	620010	IT Equipment at Cost	Balance	0
End of life	2021/03/01	5000	0321	PU000004 IT-Equipment	620020	IT Equipment Accum. Depreciation	Balance	0
Purchase	2021/03/01	5000	PU000004	IT-Equipment	620010	IT Equipment at Cost	Balance	0

The columns is as follows:

1. Transaction type - "*Purchase, Write off*" or "*End of life*". Purchase transactions is the assets at cost price. Write off transactions will be posted to the Accumulated depreciation (Balance sheet) account as a credit amount and to the Depreciation (Income statement) account type as a debit amount.

2. Date - The transaction date for the Purchase transaction. When write off transactions is processed it will be the date when the transactions on scheduled write off date is processed.

3. Amount - Purchases of Fixed assets Purchase transactions is the assets at cost price is a debit amount. Write off transactions will be posted to the Accumulated depreciation (Balance sheet) account as a credit amount and to the Depreciation (Income statement) account type as a debit amount. Credit

amounts (prefixed by a - (minus sign)).

4. Reference - Documents - The document number on which the asset was purchased. When write off transactions is processed it will be the "*Reference*" automatically generated for the write off transactions. If more than one date is applicable to the transactions on scheduled write off date, it will generate the same reference number for all transactions with the same processing date and another reference number for another scheduled write off date.
5. Description - Transaction description Documents - The document number for the document type (i.e. Purchase and Supplier returns) and the description of the Asset item or description of the asset as entered in the "*Description*" column of the document lines.
6. Account code - The account code of the Asset account at cost for purchases of fixed assets and Asset accumulated depreciation account (Balance sheet) for write off transactions or Depreciation (Income Statement) account.
7. Account description - The account name or account description of the Asset account at cost for purchases of fixed assets and Asset accumulated depreciation account (Balance sheet) for write off transactions or Depreciation (Income Statement) account.
8. Account type - Balance sheet or Income statement.
9. Rest amount - The amounts entered for the scrap value (trade-in value) of the asset at the end of the asset's life cycle (in the "*Rest value*" field of the Asset's detail form.

Activa - Reports - Custom filters

You can use advanced filters to view and filter, sort, group and analyse the transactions in respect of your fixed assets.

In addition to the Pivot tab and Data tab of the Activa plugin, you can also use the Pivot functionality on the Trial Balance, Balance Sheet and Income Statement in the Ledger analyser 1 or Ledger analyser 2 to analyse your data and build advanced filters of your transactions.

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Efficiency with a Help Authoring Tool

Types of fixed assets

Fixed assets

Fixed assets or tangible assets is a long-term asset which is used in a business to generate income over the life span of the fixed asset.

Fixed Asset Register

The fixed asset register (FAR) (Inventory of fixed assets) is supplementary accounting records and the accounting method used to record and keep track of the assets of a business. The fixed asset registers is used or the to keep record and track the fixed assets used in the the process of the business activities production of goods or rendering services. These assets are not sold as trading stock in the normal course of the business activities.

For example, a hardware store may sell tools to its customers but may also purchase tools to produce goods for customer requirements. For example, if it sells boards and circular saws to its customers, it may need a circular saw to cut these boards to size according to the customer's specific requirements. The circular saw it uses to cut the boards are fixed assets and needs to be recorded in the fixed asset register. The boards which is sold to customers, are trading stock and needs to be recorded in the stock (inventory) records.

The fixed asset register needs to record the following for each fixed asset for each accounting period:

- The value of assets – The value (opening balance) as at the start of the financial (tax) year. It should also include the depreciation written-off as well as the value of the assets as at the end of the financial (tax) year (closing balance).
- Date of acquisition – The date on which the asset is procured (purchased).
- Period - The acceptable period over which the write-off of depreciation is prescribed.
- Other details necessary to calculate depreciation and tax allowances.

Some reasons to keep accurate records of the fixed assets (non-current assets) of the business are;

- Fixed asset management and preventative maintenance.
- Tracking and deterring theft of fixed assets.
- Tax purposes – The Depreciation (Wear and Tear Allowances) which the tax authorities allow you to claim as a business expense.
- Insurance – Accurate records and valuations to assist with insuring the assets. These records may help to prevent the asses from being over-insured or under-insured. This may result in disputes if penalties

being imposed by the insurance company when a claim is processed.

There are two groups of Fixed assets; i.e.;

1. Tangible assets (which can be physically touched). In these cases you may write-off depreciation or wear and tear over the lifespan of the Fixed assets. Some examples, are;
    - Land and buildings (This asset type usually appreciates in value over the years).
    - Furniture and fittings
    - Office equipment
    - IT equipment (computers, etc.)
    - Motor vehicles
    - Plant and machinery
    - Tools
2. Intangible assets (which cannot be physically touched). The allowances and depreciation is referred to as amortization for intangible assets. Some examples, are;
    - Goodwill
    - Intellectual capital
    - Intellectual property
    - Brand
    - Copyright
    - Patent
    - Patent valuation
    - Trademark
3. Capital Gains Tax (CGT)
4. Accelerated Depreciation may apply to businesses, for example, Urban Development Zones (UDZ).

The statutory requirements, prescriptions and guidelines, etc. may differ from country to country. The format and the requirements, for fixed assets must be followed as prescribed by the various tax authorities, accounting standards, (e.g. Generally Accepted Accounting Principles (GAAP,), International Accounting Standards (IAS), etc.) and various acts relating the the type of ownership (e.g. Companies act, etc.).

Created with the Standard Edition of HelpNDoc: Revolutionize Your Documentation Output with HelpNDoc's Stunning User Interface

Methods to calculate depreciation

Calculate Depreciation

There are various methods according to which depreciation can be calculated. The most commonly used methods are the fixed instalment and the diminishing amount methods.

Tax Legislation, Companies Act and accounting standards in some countries may prescribe different methods to write off depreciation (wear and tear allowances) over the life span for the types of fixed assets.

When you add Fixed assets, you need to decide the method on which depreciation is calculated for the assets. These values only needs to be set once for a Fixed asset on the Details tab of the Activa plugin. The depreciation will be written-off each period over the life span of the fixed asset.

Some of these methods is:

1. *Straight-line method (fixed instalment method)*
2. *Declining balance method (Reducing-value method)*
3. *Double-declining balance*
4. *Production method*
5. *Sum-of-years digits*

In addition to these methods, items (assets purchased for less than a prescribed amount) may be written-off in full.

Straight-line method

According to the fixed instalment method, or cost price method, a fixed amount of depreciation is written-off annually.

The amount of depreciation will be same every year. It is calculated according to the life span of a fixed asset.

For example, as prescribed by the South African Revenue Services (SARS) a delivery vehicle's life span is four (4) years. The cost price of the asset will be written off over a period of four (4) years. The depreciation can be calculated by dividing the cost price by 4 years, or 25% per annum.

For example, as prescribed by the South African Revenue Services (SARS) a passenger car's life span is five

(5) years. The cost price of the asset will be written off over a period of five years. The depreciation can be calculated by dividing the cost price by 5 years, or 20% per annum.

The following worksheet is used to illustrate how to calculate the depreciation on a delivery van over 4 years:

Depreciation – Straight-line method

Date of Purchase:	*1 March 2021*	*Delivery van (Cost Price):*	*40,000*		
Write-off period :	*4 Years*	*Less : Trade-in (Scrap value) :*	*10,000*		
Depreciation Percentage:	*25%*	*Depreciation calculated on:*	*30,000*		
Year	*Year ended*	*Calculate depreciation on Amount*	*Depreciation Amount*	*Accumulated Depreciation*	*Book Value*
1	*28 February 2022*	*30,000*	*7,500*	*7,500*	*32,500*
2	*28 February 2023*	*30,000*	*7,500*	*15,000*	*25,000*
3	*28 February 2024*	*30,000*	*7,500*	*22,500*	*17,500*
4	*28 February 2025*	*30,000*	*7,500*	*30,000*	*10,000*

The depreciation is calculated on the cost price, less the trade in or scrap value at the end of the life span of the delivery van.

For the first year, calculate the depreciation on the cost price of 40,000 less the trade in or scrap value of 10,000. The depreciation will therefore be calculated as 25% of 30,000, which is 7,500 per annum.

This amount of 7,500 will be depreciated in four equal instalments for the years during the life span of the delivery van.

After the end of the fourth year, the book value will be 10,000, which is the trade-in or scrap value of the vehicle. Over the life span of the vehicle, the depreciation will total to 30,000.

The following worksheet is used to illustrate how to calculate the depreciation on a Passenger vehicle over 5 years:

Depreciation – Straight-line method

Date of Purchase:	*1 March 2021*	*Mercedez-Benz (Cost Price):*	*40,000*		
Write-off period :	*5 Years*	*Less : Trade-in (Scrap value) :*	*10,000*		
Depreciation Percentage:	*20%*	*Depreciation calculated on:*	*30,000*		
Year	*Year ended*	*Calculate depreciation on Amount*	*Depreciation Amount*	*Accumulated Depreciation*	*Book Value*
1	*28 February 2022*	*30,000*	*6,000*	*6,000*	*34,000*
2	*28 February 2023*	*30,000*	*6,000*	*12,000*	*28,000*
3	*28 February 2024*	*30,000*	*6,000*	*18,000*	*22,000*
4	*28 February 2025*	*30,000*	*6,000*	*24,000*	*16,000*
5	*28 February 2026*	*30,000*	*6,000*	*30,000*	*10,000*

The depreciation is calculated on the cost price, less the trade in or scrap value at the end of the life span of the passenger vehicle.

For the first year, calculate the depreciation on the cost price of 40,000 less the trade in or scrap value of 10,000. The depreciation will therefore be calculated as 20% of 30,000, which is 6,000 per annum.

This amount of 6,000 will be depreciated in five equal instalments for the years during the life span of the passenger vehicle.

After the end of the fifth year, the book value will be 10,000, which is the trade-in or scrap value of the vehicle. Over the life span of the vehicle, the depreciation will total to 30,000.

Diminishing-value method

If compared to the straight-line (fixed instalment) method, where a fixed amount is written-off over the life span of the fixed asset per year; the diminishing-value method amount of depreciation will differ from year to year and will decrease from year to year.

According to the diminishing-value method, most of the fixed asset's value will diminish, or be written-off in the first year, and a lesser amount in the second year, and even lesser amounts in the successive years.

Using the diminishing-value method, depreciation is calculated on the book value (tax value) of the asset at the end of each year. Depreciation is calculated on the purchase (cost) price, less any depreciation already claimed in previous years (accumulated depreciation).

The book value reduces or diminishes rapidly up to 40% in the first year and a lesser percentage in the second and successive years. This is why it is also referred to as the accelerated method.

There are two basic formulas that may be used to calculate depreciation when the diminishing balance method is used. These methods are: -

1. Fixed percentage on the diminishing (reducing) balance method.
2. The Sum-of-the-digits method.

Fixed percentage on the diminishing (reducing) - value method

A fixed percentage of the book value is used to calculate the depreciation, which must be written off each year.

If the life span of an asset is for instance, five years, and is normally calculated as 20%, the percentage needs to be doubled to 40% in this case. The fixed percentage must be used to calculate the percentage on the reduced (diminished) balance at the beginning of the applicable year.

According to the straight-line method, the annual depreciation rate over 5 years, is 20% per year.

Using the double-declining-balance method, double the annual depreciation rate, from 20% to 40%. The 40% depreciation rate is used to calculate the depreciation for each year on the purchase (cost) price less the accumulated depreciation.

For example, a Passenger vehicle purchased at 40,000 with a life span of 5 years, is as follows:

Depreciation – Fixed Percentage on Diminishing Balance method

Date of Purchase:	*1 March 2021*	*Passenger vehicle (Cost Price):*	*40,000*
Write-off period :	*5 Years*	*Less : Trade-in (Scrap value) :*	*10,000*
Depreciation Percentage:	*20%*	*Depreciation calculated on:*	*30,000*

Year	*Year ended*	*Calculation*	*Depreciation Amount*	*Accumulated Depreciation*	*Book Value*
1	*28 February 2022*	*40% of 40,000*	*16,000.00*	*16,000.00*	*24,000.00*
2	*28 February 2023*	*40% of 24,000*	*9,600.00*	*25,600.00*	*14,400.00*
3	*28 February 2024*	*40% of 14,400*	*5.760.00*	*31,360.00*	*8,640.00*
4	*28 February 2025*	*40% of 8,640*	*3,456.00*	*34,816.00*	*5,184.00*
5	*28 February 2026*	*40% of 5,184*	*2,076.60*	*36,889.60*	*3,110.40*

The depreciation is calculated on the full cost price. The trade in value or scrap value at the end of the life span of the delivery van is not taken into account for calculating depreciation according to this method.

According to the Diminishing-value method, the book value at the end of the fixed asset's life span can never be zero. The remaining balance at the end of the fixed asset's life span (last year of depreciation) is the scrap value.

This remaining balance, at the end of the fixed asset's life span, needs to be taken into account when an asset is disposed of (calculate the profit / loss on the sale of the fixed asset).

Sum-of-the-years-digits method

Sum-of-the-Years-Digits Method of Depreciation

The sum-of-the-years-digits (SYD) method is an accelerated depreciation technique that allocates a larger depreciation expense in the earlier years of an asset's useful life and less in the later years. This method is useful for assets that lose value more quickly in their initial years.

Steps to Calculate Depreciation Using SYD

1. Determine the Lifespan of the Asset: Identify the total number of years the asset will be depreciated.
2. Calculate the Sum of the Digits: For an asset with a lifespan of n years, the sum of the digits is calculated as follows:

   Sum=1+2+3+…+n=n(n+1)2Sum=1+2+3+…+n=2n(n+1)

Sum=1+2+3+…+n=2n(n+1)

   For a 5-year lifespan:

   Sum=1+2+3+4+5=15Sum=1+2+3+4+5=15

3. Calculate the Depreciation Factor : This is done by taking the cost of the asset minus the salvage value and dividing it by the sum of the digits:

   Depreciation Factor=Cost Price−Salvage

Depreciation Factor=1550,000−10,000=1540,000≈2,666.67

   ValueSum of the Years DigitsDepreciation Factor=Sum of the Years DigitsCost Price−Salvage Value

   For a delivery van purchased at $50,000 with a salvage value of $10,000:

   Depreciation Factor=50,000−10,00015=40,00015≈2,666.67Depreciation Factor=1550,000−10,000 =1540,000≈2,666.67

4. Calculate Annual Depreciation: Multiply the depreciation factor by the remaining years of the asset's life:
   - Year 1: 2,666.67×4=10,666.682,666.67×4=10,666.68
   - Year 2: 2,666.67×3=8,000.012,666.67×3=8,000.01
   - Year 3: 2,666.67×2=5,333.342,666.67×2=5,333.34
   - Year 4: 2,666.67×1=2,666.672,666.67×1=2,666.67

Example Calculation

5. Let's apply this to your example using a delivery van purchased for $50,000, with a life span of 4 years and a salvage value of $10,000.
6. Lifespan: 4 years
7. Sum of the Years: 1+2+3+4=101+2+3+4=10
8. Depreciation Factor: 50,000−10,00010=40,00010=4,0001050,000−10,000=1040,000=4,000
9. Annual Depreciation Calculations:
   - Year 1: 4,000×4=16,0004,000×4=16,000
   - Year 2: 4,000×3=12,0004,000×3=12,000
   - Year 3: 4,000×2=8,0004,000×2=8,000

- Year 4: 4,000×1=4,0004,000×1=4,000

Summary Table

Year	*Year Ended*	*Calculation*	*Depreciation Amount*	*Accumulated Depreciation*	*Book Value*
1	*28 February 2022*	*4,000×44,000×4*	*$16,000*	*$16,000*	*$34,000*
2	*28 February 2023*	*4,000×34,000×3*	*$12,000*	*$28,000*	*$22,000*
3	*28 February 2024*	*4,000×24,000×2*	*$8,000*	*$36,000*	*$14,000*
4	*28 February 2025*	*4,000×14,000×1*	*$4,000*	*$40,000*	*$10,000*

At the end of the asset's life, the book value should match the salvage value, which is $10,000 in this case. This final balance is important for calculating any profit or loss when the asset is disposed of.

If this method is used, the total of the number of years of the life span of the fixed asset is divided by the cost price less, the expected salvage value (trade-in or scrap value) of the fixed asset.

In the first year, the amount is then multiplied by the highest number of years (last year) of the life span of the fixed asset.

For the second year, the second last year number of the life span of the asset is used, and so on.

In the last year, the first year's number is used.

The sum of the years must be added up.

For example if the fixed asset is depreciated over a life span of five years, the digits for each of the number of years must be added up.

For five years we will add up 1+2+3+4 = 10.

The number 10 is then divided into the cost price of the fixed asset.

The annual depreciation is calculated on the Purchase (cost) price less the salvage value (trade-in or scrap value) of 10,000, i.e. 40,000 divided by 10 = 4,000. This is the factor, which we will use through the entire life span of the passenger vehicle.

1. In year 1 - Use 4,000 x 4. This is the very first year in the delivery van's life span.
2. In year 2 - Use 4,000 x 3. This is the second year in the delivery van's life span.
3. In year 3 - Use 4,000 x 2. This is the third year in the delivery van's life span.
4. In year 4 - Use 4,000 x 1. This is the last year in the delivery van's life span.

For example, a Delivery van purchased at 40,000 with a life span of 4 years, is as follows:

For example, a Delivery van, purchased at 50,000 with a life span of 4 years; and a trade-in (scrap value) of 10,000; is as follows:

Depreciation – Fixed Percentage on Diminishing Balance Method

The diminishing balance method (also known as the declining balance method) is an accelerated depreciation method where a fixed percentage is applied to the book value of the asset each year. This results in a higher depreciation expense in the earlier years and progressively smaller expenses in later years.

Calculation Steps

1. Determine the Depreciation Rate: In this case, the depreciation rate is 40%.
2. Calculate Depreciation for Each Year: The depreciation for each year is computed as:
   Depreciation Amount=Book Value at Beginning of Year×Depreciation RateDepreciation Amount=Book Value at Beginning of Year×Depreciation Rate
3. Update the Book Value: After calculating the depreciation expense for the year, subtract it from the book value to get the new book value for the next year:
   New Book Value=Previous Book Value−Depreciation AmountNew Book Value=Previous Book Value−Depreciation Amount

Example Calculation

Let's break down the depreciation calculation for a delivery van using the diminishing balance method.
Initial Cost: $50,000
Salvage Value: $10,000
Depreciation Rate: 40%

Summary Table

Year	*Year Ended*	*Calculation*	*Depreciation Amount*	*Accumulated Depreciation*	*Book Value*
1	*28 February 2022*	*40%×50,000*	*$20,000*	*$20,000*	*$30,000*
2	*28 February 2023*	*40%×30,000*	*$12,000*	*$32,000*	*$18,000*
3	*28 February 2024*	*40%×18,000*	*$7,200*	*$39,200*	*$10,800*
4	*28 February 2025*	*40%×10,800*	*$4,320*	*$43,520*	*$6,480*

Explanation of Each Year

1. Year 1:
   - Calculation: 40%×50,000=20,00040%×50,000=20,000
   - Book Value at End of Year: 50,000−20,000=30,00050,000−20,000=30,000
2. Year 2:
   - Calculation: 40%×30,000=12,00040%×30,000=12,000
   - Book Value at End of Year: 30,000−12,000=18,00030,000−12,000=18,000
3. Year 3:
   - Calculation: 40%×18,000=7,20040%×18,000=7,200
   - Book Value at End of Year: 18,000−7,200=10,80018,000−7,200=10,800
4. Year 4:
   - Calculation: 40%×10,800=4,32040%×10,800=4,320
   - Book Value at End of Year: 10,800−4,320=6,48010,800−4,320=6,480

Final Considerations

At the end of the asset's life, the book value should ideally approach the salvage value. In this case, further depreciation in Year 4 results in a book value of $6,480, which is below the salvage value of $10,000. This scenario emphasizes the importance of considering the salvage value when determining depreciation, as well as the need to adjust calculations if the book value falls below the salvage value. When an asset is disposed of, any remaining book value compared to the sale price will help determine if there is a profit or loss on the sale, which is essential for accurate financial reporting.

Year	*Year ended*	*Calculation*	*Depreciation Amount*	*Accumulated Depreciation*	*Book Value*
1	*28 February 2022*	*40% x 30,000*	*12,000.00*	*16,000.00*	*34,000.00*
2	*28 February 2023*	*3 x 4,000*	*12,000.00*	*28,000.00*	*22,000.00*
3	*28 February 2024*	*2 x 4,000*	*8,000.00*	*36,000.00*	*14,000.00*
4	*28 February 2025*	*1 x 4,000*	*4,000.00*	*40,000.00*	*10,000.00*

The depreciation is calculated on the full cost price less trade in value or scrap value, i.e. 40,000. At the end of the life span of the delivery van, the book value should be the trade-in (scrap value), i.e. 10,000.

This remaining balance, at the end of the fixed asset's life span, needs to be taken into account when an asset is disposed of (calculate the profit / loss on the sale of the fixed asset).

sum-of-the-years-digit method

- https://www.calculatorsoup.com/calculators/financial/depreciation-sum-of-years.php -

The following formula may also be used to find the sum-of-the-years-digit:

The formulae

$$\frac{J = N\,(1 + N)}{2}$$

J = The estimated life span of the asset
N = The total of the series

Some calculations based on the formulae:

If the life span is 5 years

$$\frac{J = N\,(1 + N)}{2}$$

$$= 5\ \frac{(1+5)}{2}$$

$$= 5 \times 3$$

$$\therefore J = 15$$

If the life span is 3 years

$$\frac{J = N\,(1 + N)}{2}$$

$$= 3\ \frac{(1+3)}{2}$$

$$= 3 \times 2$$

$$\therefore J = 6$$

Depreciation - Sum-of-Years

Date of Purchase:	*1 March 2021*	*Delivery van (Cost Price):*	*40,000*
Write-off period :	*4 Years*	*Less : Trade-in (Scrap value) :*	*10,000*
Depreciation Percentage :	*Variable*	*Depreciation calculated on:*	*30,000*

Year	*Year ended*	*Book value Year Start*	*Depreciation percentage*	*Depreciation expense*	*Accumulated Depreciatio*	*Book Value*

					n	
1	*28 February 2022*	*30,000*	*40%*	*12,000*	*12,500*	*28,000*
2	*28 February 2023*	*28,000*	*30%*	*9,000*	*21,000*	*19,000*
3	*28 February 2024*	*19,000*	*20%*	*6,000*	*27,000*	*13,000*
4	*28 February 2025*	*13,000*	*10%*	*3,000*	*30,000*	*10,000*

Production method

The Units of Production Method is a depreciation approach that allocates the cost of a fixed asset based on its actual usage rather than the passage of time. This method is particularly useful for assets whose wear and tear is more closely related to their output or production levels, making it a popular choice in manufacturing and similar industries.

Key Features

- Usage-Based Depreciation: Unlike other methods that spread depreciation evenly over time, the Units of Production Method ties the depreciation expense directly to the asset's output. This means that the more an asset is used, the higher the depreciation expense for that period.
- Calculation: To calculate depreciation using this method, you first determine the asset's depreciable cost (the initial cost minus its salvage value) and then divide it by the total expected production over the asset's useful life. The formula can be expressed as:

```
Depreciation Expense = (Depreciable Cost / Total Estimated Production) × Actual Production for the Period
```

This formula ensures that the depreciation expense reflects the actual usage of the asset.

Applications

The Units of Production Method is particularly effective for assets like machinery, vehicles, or equipment that have a direct correlation between their usage and wear. For example, if a piece of machinery is expected to produce 100,000 units over its lifetime and costs $50,000 with a salvage value of $5,000, the

depreciation per unit would be calculated as follows:

1. Depreciable Cost: $50,000 - $5,000 = $45,000
2. Depreciation per Unit: $45,000 / 100,000 units = $0.45 per unit

If the machinery produces 10,000 units in a year, the depreciation expense for that year would be:

```
Depreciation Expense = $0.45 × 10,000 = $4,500
```

This method allows businesses to match their expenses with the revenues generated from the asset, providing a more accurate financial picture.

Conclusion

In summary, the Units of Production Method is a valuable tool for businesses that want to align their asset depreciation with actual usage. By focusing on output rather than time, this method provides a more precise reflection of an asset's value over its useful life.

Fixed Assets (Small items) Purchased for Less than a Prescribed Amount

Writing Off Small Fixed Assets

When it comes to small fixed assets purchased for less than a specified prescribed amount, businesses may have the option to write off these assets in full. This means that instead of depreciating the asset over its useful life, the entire cost can be expensed in the year of purchase. The specific threshold for this write-off is determined by legislation and can vary based on updates from tax authorities.

Depreciation Legislation

The depreciation amount for fixed assets is often prescribed by tax legislation, which can change over time. Therefore, businesses must stay informed about any new legislation or practice notes issued by tax authorities that may affect how they account for these assets. In summary, small fixed assets can be fully written off if they fall below a certain cost threshold, and businesses should regularly check for updates in tax regulations that might influence their accounting practices.

Created with the Standard Edition of HelpNDoc: Modernize your help files with HelpNDoc's WinHelp HLP to CHM conversion tool

Activa transactions

Posted batches

Once the depreciation transactions in the Activa plugin have been processed it will automatically post or

update the transactions to the ledger, as well as update all reports.

Each process line (Asset on the Activa - List tab) will be processed in its own batch. The batch numbers (Batch ID) is automatically generated.

To view and print a posted batch report:

Select the Activa or Depreciation batch type.

Click on the Posted batches tab. The Batch entry tab on the Posted batches tab, will list all processed Activa transactions posted to the ledger.



Select a batch and double-click. On the Details tab, the Debit and Credit transaction details will be listed.



Click on the Print button. An example of the "*Batch type report - Posted batch*", is as follows:



Central Search

The Investigator allows you to search for data in an open Set of Books. To search or locate data, you may enter a valid word or phrase to search for an item. This facility also allows you to define, or refine, or filter the search criteria, and select to view the details for a selected search result.

SERIAL TRACKING - If you have entered a serial number of a product (stock item) as a comment on your sales documents (Invoices, Credit notes and/or Quotes) and/or on Purchase documents (Purchases and Supplier returns and/or Orders), you may enter the serial number in the "Search for": field.

If you click on the Search now button, the Documents will be listed. You may then double-click on the selected document to preview the document.

Comments entered in document lines are searchable.

Remarks is not searchable.

To search for data using the Investigator:

1. On the Default ribbon, select Search. The "*Investigator*" screen is displayed:



2. Enter a word or phrase to search for specific data. To filter the data, you may also select to include everything or documents, batches, stock information, account names and/or account information.

3. Click on the Search now button or on the F3:Search icon. The number of items found (which matches the search criteria) will be displayed, and each of the items found will be listed.

4. Select an item type from the search results list and right-click - select "*Show detail*" option on the context menu (or double-click) to launch the options. The types is as follows:

    a) Account - Launch the T-Account viewer - You may select or enter the dates from and dates to, as well as any filters (if necessary) to view and filter the transactions. Transactions may be printed and exported to a spreadsheet file.

    b) Debtor / Creditor - Launch the Debtor accounts screen to edit or check specific details for the debtor (customer / client). If a Creditor is indicated, it will launch the specific creditor (supplier / vendor) account.

    c) Stock - Launch the Stock items screen to edit or check specific details for the stock item.

    d) Document - The selected document will be printed.

    e) Batch - Launch the T-Account viewer - You may select or enter the dates from and dates to, as well as any filters (if necessary) to view and filter the transactions. Transactions may be printed and exported to a spreadsheet file.

    For certain types (e.g. Account), the F4:Details icon will be available. If you click on this icon, the balances for general ledger accounts will be displayed for each period.

5. To close or exit this screen, click on the Close button on the title bar.

Further Search options are available to select from. If you click on the More >> link, the Advanced options will be available in which the limit for the number of records found may be set.

To refine or filter the search criteria, you may click on the Refine search link.



Created with the Standard Edition of HelpNDoc: Create Professional CHM Help Files with HelpNDoc's Easy-to-Use Tool

Activa transactions in Ledger analyser

Trial balance

Once the depreciation transactions in the Activa plugin have been processed it will automatically post or update the transactions to the ledger.

To Print a trial balance:



Pivot view of Activa transactions

You may use the Pivot feature Ledger analyser, to filter for Fixed assets and Depreciation transactions on the following report types.

- Trail balance - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type.
- Balance sheet - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts).

- Income statement - Depreciation - Income expense account type.
- Standard column balances - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type.
- This year vs last year - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type.
- Budget vs actual - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type.



Created with the Standard Edition of HelpNDoc: Easily create Help documents

Activa transactions in the T-Account viewer

T-Account view of Activa transactions

You may use the T-Account viewer feature Ledger analyser, to filter for Fixed assets and Depreciation transactions, print the transactions and or export the transactions to a spreadsheet on the following report types.

- Trail balance - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub-accounts} and the Depreciation - Income expense account type.
- Balance sheet - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts).
- Income statement - Depreciation account - Income expense account type.
- Standard column balances - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type.
- This year vs last year - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type.
- Budget vs actual - Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type.

In addition to these report types, you may also print and export transactions in the T-Account viewer to a spreadsheet for Fixed assets main accounts (Fixed assets at cost and/or Fixed assets accumulated depreciation sub- accounts} and the Depreciation - Income expense account type form the Column balances and Column balances D/C report types.

An example of the purchases transactions for and write-off transactions processed with the Activa plugin, is for all periods during the life span of assets, as follows:



From date ... To date

The default view of the Dates is automatically displayed for the selected period from which you launch the T-account viewer in the Ledger analyser. To view the Activa transactions over the life span of the Fixed assets or Depreciation account, you may select the dates. For example, the dates may be selected from date 2021/03/01 to 2027/02/28 to list all transactions for a specific fixed assets or depreciation accounts.

Show contra - By default this option is not selected.

If the Show contra is selected, it will insert (add) the Account code and Description before the batch id (batch number).

The Contra accounts will not print on the T-Account viewer ("ledgerdetail") report; but will be included in the Export file when you click on the Export button of the T-Account viewer.

Options to filter transactions

1. *From date ... To date - Select the dates to filter transactions for a specific date or period.*
2. *In addition to this, you may double-click on the following details on the list of transactions to print specific transactions:*
    - *Batch id - (e.g. 68 to 78 as in this example)*
    - *Account code - To list only transactions for a specific account.*
    - *Date - To list only transactions for a specific date.*

You may click on the Print button to print the transactions:




ledgerdetail
T-Account viewer
G610010 Furniture and Fittings at Cost
Debit Credit Cum
68 2021/03/01 FU000001 Chairs x 12 12 000,00 -126 000,00
FU000001 ,
68 2021/03/01 FU000001 Filing cabinets x 24 24 000,00 -102 000,00
FU000001 ,
Totals 36 000,00
36 000,00
T-Account viewer
G610020 Furniture and Fittings Accum. Depr.
Debit Credit Cum
72 2022/02/28 0222 FU000001 Chairs x 12 2 000,00 -104 000,00
ACTIVA ,
73 2022/02/28 0222 FU000001 Filing cabinets x 24 4 000,00 -108 000,00
ACTIVA ,
Totals 6 000,00
6 000,00
T-Account viewer
G620010 IT Equipment at Cost
Debit Credit Cum
80 2021/03/01 0321 FU000004 IT-Equipment 5 000,00 -113 000,00
ACTIVA ,
69 2021/03/01 FU000002 Main frame / Server 10 000,00 -103 000,00
FU000002 ,
69 2021/03/01 FU000002 Computer 9 000,00 -94 000,00
FU000002 ,
69 2021/03/01 FU000002 Computer software 10 000,00 -84 000,00
FU000002 ,
71 2021/03/01 FU000004 IT-Equipment 5 000,00 -79 000,00
FU000004 ,
Totals 34 000,00 5 000,00
29 000,00
T-Account viewer
G620020 IT Equipment Accum. Depreciation
Debit Credit Cum
79 2021/03/01 0321 FU000004 IT-Equipment 5 000,00 -84 000,00
ACTIVA ,
80 2021/03/01 0321 FU000004 IT-Equipment 5 000,00 -79 000,00
ACTIVA ,
74 2022/02/28 0222 FU000002 Computer 3 000,00 -82 000,00
ACTIVA ,
75 2022/02/28 0222 FU000002 Computer software 5 000,00 -87 000,00
ACTIVA ,
76 2022/02/28 0222 FU000002 Main frame / Server 2 000,00 -89 000,00
ACTIVA ,
Totals 5 000,00 15 000,00
10 000,00



An example of the purchases transactions for and write off transactions processed with the Activa plugin exported to a spreadsheet, is as follows:



Created with the Standard Edition of HelpNDoc: Easily create Qt Help files

Charter plugin

Charter Plugin - Manual - Shop - Licence : Once-off

Documentation : Help documentation

Unlock powerful visualization capabilities with our Charter plugin. Seamlessly generate insightful charts and graphs directly from your Set of Books data, empowering you to make informed decisions and communicate key insights effectively. Save charts as image files for integration into documents, presentations, spreadsheets, and more.

The Charter Plugin enhances your experience by adding a Charter tab on the Debtor accounts, Creditor accounts, and Stock items. This allows you to build and customise charts effortlessly. Within the Debtors grid, Creditors grid, and Stock item grid, simply right-click to launch the "*Charter*" screen from the Plugin action → Charter context menu.

In the Documents grid, you can also access the "*Charter*" screen by right-clicking and selecting the Plugin action → Charter context menu. This feature enables you to launch the " *Doc value*" or "*Debtors*" charts. Additionally, in document entry screens for both posted and unposted sales documents such as invoices, credit notes, quotes, purchases, supplier returns, and orders, an icon will be available to launch the "*Charter*" screen.

Furthermore, the "*Charter*" plugin seamlessly integrates with other plugins supporting the "*Charter*" functionality.

Activate the Charter plugin

To launch the Charter:

1. On the Setup ribbon, select Plugins → Financial tools → Charter. If this plugin is not listed under Plugins → Financial tools, activate it via Tools → Activate plugins.

If the Charter plugin is not available from the Plug-ins → Financial tools → Charter menu, you need to Activate the Charter plugin. To do this go to the Tools → Activate plugins on the Setup ribbon.



When you reopen the Set of Books, the Charter icon will be added to the Default ribbon. This will only be added for the act



2. When you reopen the Set of Books, the "*Charter*" plugin can be accessed on the Default ribbon.

Launch the Charter plugin (Default ribbon)

To launch the Charter:

1. On the Default ribbon, select the Charter icon.



2. Type - Select the following report types:
    a) GL Debtor creditor cashflow
    b) Account main digit
3. Date from - Select the date from.
4. Click on the Build button. The chart will be generated. You may adjust the looks and layout of the chart using the following options:
    a) 3D - Selected (ticked) it will display the chart in a 3 dimensional view. If not selected (not ticked), it will display the Chart in a 2D (2 dimensional) view.
    b) Size - Decrease the size by clicking on the minus button or increase the size by clicking on the plus button.
    c) Legend - The legend is by default displayed. You may deselect it (remove the tick) to hide the legend.
    d) Rotate - There are four buttons, which may be used to change or set the angles of the chart.
5. Once you are happy with your layout, you may click on the Save as image button. This will save the chart as an image in the following two (2) file types:
    a) Bitmap file (*.bmp)
    b) Paintbrush Picture (*.wmf).
6. Click on the Close button to exit (close) the Charter screen.

GL Debtor creditor cashflow

This chart type will display the totals of your sales and purchases.

Sales / Purchase cash flow: Profit , debtor (sales) and creditor (purchases) and cash flow in one graph.



Account main digit

Main accounts: Totals per account



Launch the Charter plugin (Charter tabs)

In addition to the Chart icon on the Default ribbon, the Charter plugin, will add a Charter tab on the Debtor accounts, Creditor accounts and Stock items from where you may build and customise charts.

Within the Debtors grid, Creditors grid and Stock item grid, you may right-click to launch the "*Charter*" screen from the on the Plugin action → Charter context menu.

Within the Documents grid - You may right-click to launch the "*Charter*" screen from the on the Plugin action → Charter context menu to launch the "*Doc value*" or "*Debtors*" chart. In the document entry screen for posted and unposted sales documents such as invoices, credit notes and quotes as well as purchase documents such as purchases, supplier returns and orders, an icon will be available to launch the "*Charter*" screen.

Charter Plugin integration

The "*Charter*" plugin is also available in other plugins in supporting the "*Charter*" plugin.

Debtors - Charter tab

Debtors

Context menu access: From the Debtors item grid, similar charts may be generated on the Plugin action → Charter context menu for a selected debtor (customer / client) account.

Creditors - Charter tab

Creditors

Creditor detail

Creditor Group current value

Context menu access: From the Creditors item grid, similar charts may be generated on the Plugin action → Charter context menu for a selected creditor (supplier / vendor) account.

Stock - Charter tab

Stock value

Stock Days

Stock Sales

Creditor Group current value

Creditor

Creditor detail

Context menu access: From the Stock item grid, Similar charts may be generated on the Plugin action → Charter context menu for a selected stock item

Documents - Plugin action - Charter

Doc value

Debtor (Note on Sales documents such as Invoices, credit notes and quotes this is option displays charts. On purchase documents such as purchases, supplier returns and orders the charts does not display any detail in charts.

Charter Plugin integration

The "*Charter*" plugin is also available in other plugins in supporting the "*Charter*" plugin.

Other Graph features in osFinancials5/TurboCASH5

In addition to the charts generated by the Charter plugin, you have the flexibility to produce your own graphs using various tools within osFinancials:

- Ledger analyser - Export data to Comma Separated Value files (*.csv) and build your own charts (graphs) from exported data in your favourite spreadsheet program.
- Documents - Graphs - Search filter, and customise your views for each document type according to your needs, and use the Graphs option to visualise your sales documents (Invoices, ,Point-of-Sales invoices, Credit notes and Quotes) and your purchase documents (Purchases, Supplier returns and Orders).
- Drill Down plugin - Charts of your Sales per day and Quantities per day. You may also filter and export other data and build your own charts (graphs) in spreadsheets.
- Reports - Graphs - Graphs per week and Graphs per month.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Introduction to the DrillDown plugin

DrillDown plugin - Manual - Shop - Licence : Once-off -

This TC Drill Down plugin enables you to review all your filtered data and export it to i.e. MS Excel.

The "*TC Drill Down*" plugin for osFinancials5/TurboCASH5 offers a robust solution for delving into your data and creating customised reports quickly and efficiently. Whether you're looking to analyse transactions, track customer invoices, or monitor stock item sales, the DrillDown plugin provides powerful features to streamline your processes. Here's an introduction to its key functionalities:

Transactions

All the transactions in the Set of Books will be populated in the transactions view. You may filter and sort the views in the powerful grid to build your own custom views of the transactions.

Customers → Invoices

Here you can locate your customer and see his invoices. The invoices show the items the items that where both. It has a good a quick navigation interface the helps you hunt down any invoice. The key element here is that you know what client has this invoice. You may print specific invoices directly from the interface by double-clicking on them.

Invoices → Stock item

Here you can find all you invoices and the stock items that were sold on the invoice. It is a fast way of just finding that invoice if the invoice number is what you got. You may print specific invoices directly from the interface by double-clicking on them.

Stock item → Invoice

See what invoices where used to sell this stock item. Giving you the ability to find an invoice if you now the stock item. Just find that item and if it was sold you will find the invoice with that.

Charts

The Charts view of your sales documents, during the selected dates will visually display the sales data in the following graphs:

- Total sales:
  - Total sales : Your total sales per day are displayed in a pie chart. Your inventory items or products are displayed as parts in different colors per day. It will visually display at a glance the day or days in which the most sales occurred.
  - Total sales per day : Your total amount of sales per day is indicated in a bar graph. It will visually display as amounts the day or days in which the most sales occurred at a glance.
- Total quantities:

- Total sales quantities : Displays the total quantities of your inventory items or products sold during the selected dates in a pie chart. The total quantities of your inventory items or products sold will be displayed as parts in different colors per day. It will visually display at a glance the inventory items or products that are the top sellers during the selected dates.
- Total sales quantities per day: The total quantities of your stock items or products sold during the selected dates are visually represented in a bar graph. It will visually display at a glance the number of inventory items or products that are the top sellers during the selected dates. It will graphically display how certain days affect the quantities of inventory items or products.

Export data

You may export data from all views (except the Charts-option) to XML, HTML, Excel, or Text files, facilitating further analysis or integration with other tools.

Using the DrillDown

To use this option, you need to open a Set of Books. When the DrillDown is launched, it will by default list all the transactions in the database of the active (opened) Set of Books.

To launch the TC Drill Down:

1. On the Setup ribbon, select Plugins → Financial tools → DrillDown. If this plugin is not listed under Plugins → Financial tools, activate it via Tools → Activate plugins.

> *If the DrillDown plugin is not available from the Plug-ins → Financial tools → DrillDown menu, you need to Activate the Drill down plugin. To do this go to the Tools → Activate plugins on the Setup ribbon.*



Optional - You may select to "Show on ribbon" option to add the TC Drill Down icon to theDefault ribbon. This will only be



2. Click on the View data button to launch the "*TC Drill Down*" plugin (Transactions).



3. You may use various options to sort and/or filter your data.

4. For example, if you need to check your sales for a specific date, select the date in the date column, and the sales in the account column.

Transactions

The default view when TC Drill Down is launched, is Transactions.

When you launch the "*TC Drill Down*" plugin, the default view is the Transactions view. This view provides an overview of all transactions within your Set of Books.



Here's how you can customize and utilize filter options within the Transactions view to meet your specific requirements:

1. Customize Data Columns:
    - You can customize the data columns displayed in the Transactions view according to your preferences.
    - Choose which columns to display based on the information relevant to your analysis.
2. Utilize Filter Options:
    - The plugin offers various filter options to refine the displayed data according to specific criteria.
    - Filters allow you to focus on transactions that meet certain conditions, such as date range, account type, transaction type, etc.
3. Export Data:
    - Once you've customized the view and applied filters to display the desired subset of transactions, you can export this data.
    - Only the data visible in the customized view, along with the selected sequence of data columns and applied filters, will be included in the exported files.
4. Further Analysis and Actions:
    - After exporting the data, you can perform further analysis using external tools such as Microsoft Excel or LibreOffice Calc.

- Identify trends, anomalies, or specific transaction details to inform decision-making or address any issues within your financial records.

By leveraging the customization and filter options within the Transactions view of the " *TC Drill Down*" plugin, you can tailor your analysis to focus on the specific data elements and criteria relevant to your needs. This flexibility allows for efficient data exploration and analysis within your osFinancials5/TurboCASH5 Set of Books.

Show / hide / move columns

By default, all columns, except the "*Transaction no., Batch no., Debit tax*" and "*Credit tax*" columns) is not available.

You may add these manually by selecting those columns. You may select only those columns you need to see.

Visible columns (Options → Columns menu)



*Default * Click here to show/hide/move columns*



Sorted (selected) - Alphabetical list

Hidden columns will not be included in an export files.

In the Transactions option of the "*TC Drill Down*" plugin, you have the ability to show, hide, or move columns according to your preferences. By default, only certain columns are visible, but you can manually

add or remove columns as needed.

Here's an overview of the available columns and their descriptions:

1. Account Type - There are five (5) account types (i.e. Bank, Creditor, Debtor, General ledger and Tax).
2. Transaction no. - The number of the Transaction in the Transaction table of the database.
3. Batch no. - This is the number of the batch (journal) as allocated by osFinancials5/TurboCASH5. The last column (i.e. "*Journaal*") displays a more friendly version of the Batch no.
4. Date - The date of the transaction.
5. Period - The accounting period (e.g. Month) of the transaction. "*Last year*" is the previous financial year.
6. Account no. - The account code for Bank, Creditor, Debtor, General Ledger and Tax accounts.
7. Account - The description or account name.
8. Group1 - Account group 1 for Bank, General Ledger and Tax accounts. Creditor Group 1 for Creditor accounts and Debtor Group 1 for Debtor accounts.
9. Group2 - Account group 1 for Bank, General Ledger and Tax accounts. Creditor group 1 for Creditor accounts and Debtor group 1 for Debtor accounts.
10. Reference - The reference as entered in the Reference column of batches and in the case of sales documents (i.e. Invoices, Point-of-Sales Invoices and Credit notes) and purchase documents (i.e. Purchases and Supplier returns), the document number will be displayed.
11. Description - The description as entered in the Description column of batches. In the case of documents, the description is as follows:
    a) Sales account - Stock Item's description.
    b) Cost of Sales and Stock Control account - COST OF SALES/Document number.
    c) Creditor account - Document type/Document number.
    d) Debtor account - Document type/Document number.
    e) Tax (Input and Output Tax) - Document Type/Document number.
12. Debit - Amounts entered or generated as balancing entries in the Debit column of batches. In the case of documents, the description is as follows:
    a) Debit tax - Amounts entered or generated as balancing entries in the Debit column of batches. In the case of documents, the description is as follows:
    b) Debit Outstanding - Outstanding amounts in the Debit column. This is usually the same, as

the Debit amount, unless a credit transaction have been linked to the debit transaction to an Open Item account.

13. Credit - Amounts entered or generated as balancing entries in the Credit column of batches. In the case of documents, the description is as follows:

    a) Credit tax - Amounts entered or generated as balancing entries in the Debit column of batches. In the case of documents, the description is as follows:

    b) Credit Outstanding - Outstanding amounts in the Credit column. This is usually the same, as the Credit amount, unless a debit transaction have been linked to the credit transaction to an Open item account.

14. Journaal - This is the Alias (Batch name). If the "*Change alias*" option on batches were used before posting batches, the Alias will be displayed. Should the aliases of batches not be used, more than one batch (with the same name) will be listed. You may then need to use the Batch no. to filter for a specific batch. In the case of documents, the Document no. will be displayed.

You can customise the visibility and order of these columns using the "*Visible columns*" option in the menu. Hidden columns will not be included in export files, ensuring that only relevant data is exported. This flexibility allows you to tailor the view to your specific needs, facilitating efficient analysis and reporting within the Transactions option of the "*TC Drill Down*" plugin.

Move column sequence

In the Transactions option of the "*TC Drill Down*" plugin, you have the ability to change the sequence in which the data in the columns is displayed. This feature allows you to customize the layout of your data according to your preferences.

In addition to the option in the "*Visible columns*" screen (Options → Columns menu) you can change the order (sequence) in which the data is displayed in the columns, by simply clicking on a selected column and drag it to the desired position (left or right.



By moving column headings in the Transactions option, you can organize your data in a way that makes it easier to analyse and interpret. This customisation feature allows you to prioritise the display of information based on its relevance to your analysis, enhancing your workflow efficiency within the "*TC Drill Down*" plugin.

Group / Ungroup columns

Select a column and click on it. While holding the mouse button down, drag it to the column header bar "*Use your mouse to pull a column here to group on that column*". Select any other column to drag and drop it on column header bar. You may select as many columns, as necessary, to group your data.

You may also drag and drop these columns to the right or left to change the grouping of these columns.

In the Transactions option of the "*TC Drill Down*" plugin, you have the ability to group and ungroup columns to organize your data according to specific criteria.



Remove grouped columns

To remove a column from column header bar "*Use your mouse to pull a column here to group on that column*", you may use the following two (2) options:



1. Select the column heading (e.g., “*Account*”) on column header bar "*Use your mouse to pull a column here to group on that column*", and drag it to the first line (above the column headings). When the mouse pointer change to a big X, drop it. The column will automatically be placed in the correct default sequence (or the place of the previous grid layout).
2. If you wish to change the column to a specific place, select the column heading (e.g., “*Account*”) on column header bar "*Use your mouse to pull a column here to group on that column*", and drag it to the first line (column headings). When you drop it, the column will be added to the selected position or sequence of the columns.

By utilising the group and ungroup column features, you can organize your data effectively within the Transactions option of the "*TC Drill Down*" plugin. This allows for better analysis and visualization of your financial information based on specific criteria and groupings.

Sort sequences

All the data is, by default, displayed ascending; from the smallest to the highest value (e.g. a-z or 0-9) according to the Period (e.g. April, February, March, etc.).

To change the sort order from ascending (e.g. a-z or 0-9) to descending (e.g. z-a or 9-0) select a column which you need to sort) and click on it. If you click on the same column again, it will change back to ascending sequence.

In the Transactions option of the "*TC Drill Down*" plugin, you have the ability to sort data sequences to facilitate easier analysis and interpretation. By default, data is displayed in ascending order, but you can change the sort order to descending if needed.

By adjusting the sort sequence in the Transactions option of the "*TC Drill Down*" plugin, you can organise your data according to your preferences, making it easier to analyse and interpret information effectively. This feature enhances the usability of the plugin, allowing for more efficient data exploration and analysis within osFinancials5/TurboCASH5.

Filter options in column headings

While viewing and analysing the data you may sort and filter the data, in each column of the active or loaded table. To do this, select the column and click on the filter icon. A list displaying the data, as well as an "*All*" option and a "*(Custom...)*" option in the selected column will be displayed.
For example, the "*Account*" column, is selected, a list of all "*Accounts*" will be displayed.



You may select those account you wish to list. Only the transactions for the selected account(s) will be listed.

To adjust a filter in a column, select the "*(Custom...)*" option in the selected column. The "*Adjust filter*" will be displayed:



In the Transactions option of the "*TC Drill Down*" plugin, you have the capability to apply filters to column headings, allowing you to refine and focus your data analysis.

The type of filter options/conditions available for data manipulation can vary depending on the nature of the data contained within the column. Some common Filter options is as follows:

a) Equal to - Lists or displays all values that are exactly the same as the specified value.

b) Not equal to - Lists or displays all values that are not exactly the same as the specified value.

c) Less than - Lists or displays all values smaller than the specified value.

d) Less than or equal to - Lists or displays all values smaller than or equal to the specified value.

e) Greater than - Lists or displays all values greater than the specified value.

f) Greater than or equal to - Lists or displays all values greater than or equal to the specified value.

g) Like - Lists all values in the table similar to the specified value using pattern matching (often with wildcard characters).

h) Not like - Lists all values in the table not similar to the specified value using pattern matching.

i) Is null - Excludes any rows where the value is missing (NULL), meaning they will not be listed or displayed.

j) Is not null - Lists or displays any rows where the value is not missing (NULL).

k) Start with - Lists or displays values where the text starts with the specified string.

l) End with - Lists or displays values where the text ends with the specified string.

m) Include - Lists or displays all values that match any of the specified values. This option is useful when you want to filter for multiple specific values.

n) Not include - Lists or displays all values that do not match any of the specified values. This option is useful when you want to exclude specific values from the result set.

By utilising the filter options in column headings, you can refine your data analysis within the Transactions option of the"*TC Drill Down*" plugin, allowing for more focused and insightful examination of your financial data.

Adjusting filter options based on the data type ensures that you have access to the most relevant and effective tools for manipulating and analysing your data. This flexibility enhances usability and allows for more efficient data exploration and decision-making.

Working with custom filters

Once you have selected an option on a list, the your selection will be displayed at the bottom section of the"*TC Drill Down*" screen as follows:



The selected filters will be listed. You may select any filters for quick access to previous filter options. You may click on the Customise button to:

- Make a filter (add or delete conditions and groups).
- Save a filter.
- Open a filter.



To make a filter:

1. Select a column and click on the Filter button (or on the ... button) and select one of the following options on the context menu:
    a) New condition
    b) New group
2. Delete row (If you click on the Filter button, you may delete the rows (conditions and groups).
3. Select the or option to set a filter value. The following options are available:
    a) New condition
    b) New group
4. Once you have created your conditions or groups, click on the Apply button.
5. Click on the OK button to close and exit this "*Make filter*" screen.

To save a custom filter file:

1. Once you have sorted or filtered your data with the "*Make filter*" screen, click on the Save as.. button. The "*Save active filter*" screen will be displayed.
2. Select a directory in which you wish to save the custom filter file.
3. Enter a file name.
4. Click on the Save button to save the Filter in a (*.flt) Filter file format. You may then at any later stage open the saved *.flt file.

To open a saved a custom filter file:

1. Once you have sorted or filtered your data with the "*Make filter*" screen, click on the Open... button. The "*Open a saved filter*" screen will be displayed.

2. Select a directory in which you have saved the custom filter file.
3. Select a valid filter file.
4. Click on the Open button. The selected filter file's name will be displayed in the titlebar of the "*Make filter*" screen.

Working with custom filters in the "*TC Drill Down*" plugin allows you to refine and save filter settings for quick access to specific data views.

By utilizing custom filters, you can save time and effort by quickly accessing predefined filter settings for your data analysis needs. Whether you're refining data views for specific criteria or reusing previously defined filters, the "*TC Drill Down*" plugin offers flexibility and efficiency in managing your data within osFinancials5/TurboCASH5.

Customer invoice

The "Customer → Invoice" option in the "*TC Drill Down*" plugin lists all customers and their respective invoices, allowing you to sort, filter and view quantities of ordered and shipped stock items along with total invoice amounts, and to print invoices directly from the interface.



The Customer invoice option lists all your customers (debtors or clients). For each customer account, it displays up to three address lines and the total of all invoices (excluding tax, tax amount, and including tax). You can sort columns or use custom filters to search for a specific customer.

Expanding a specific customer account reveals all posted and unposted invoices. Each invoice displays quantities of ordered and shipped stock items, along with the total amount (excluding tax, tax amount, and including tax) in columns. You can also sort columns or use custom filters to search for an inventory item or product.

Additionally, you can print specific invoices directly from the interface by double-clicking on them.

By leveraging the Customer invoice option of the "*TC Drill Down*" plugin, you can efficiently manage customer transactions, track sales, and maintain clear communication with customers regarding their invoices. This feature enhances your ability to provide excellent customer service and ensures accuracy in your financial records within osFinancials5/TurboCASH5.

Invoice stock Item

In the Invoice stock item option of the "*TC Drill Down*" plugin, you can quickly find invoices and the stock items that were sold on each invoice. This functionality allows for efficient tracking of invoices based on invoice numbers and provides insight into the items sold within each invoice.



The Invoice stock item option displays all inventory items or products, showing which items were sold in each invoice. It includes details such as stock code, description, quantities, and total invoice amounts, allowing sorting and custom filtering for specific items.

Expanding a specific item reveals all invoices, posted and unposted, with quantities and total amounts displayed for each invoice, and provides options for sorting and custom filtering.

Additionally, you can print specific invoices directly from the interface by double-clicking on them.

By utilizing the Invoices stock item option of the "*TC Drill Down*" plugin, you can efficiently find invoices based on invoice numbers and gain insight into the stock items sold within each invoice. This feature enhances your ability to manage sales transactions, track inventory, and analyse sales performance within osFinancials5/TurboCASH5.

Stock item invoice

In the Stock item invoice section of the "*TC Drill Down*" plugin, allows you to quickly locate invoices associated with the sale of a particular item. In this option of the "*TC Drill Down*" plugin, you can track which invoices issued to which debtors (customers / clients) and were used to sell specific stock items, facilitating quick access to associated sales records.



Customer	Invoice no.	Date	Excl. amt.	Tax amount	Incl. amt.
Mr. AB Green	IN000009	2021/05/07 13:00:	1,000.00	150.00	1,150.00
Mr. Mike Davies	IN000010	2021/05/08	1,000.00	150.00	1,150.00
Mr. AB Green	IN000011	2021/06/05	1,000.00	150.00	1,150.00
Mr. Roger Smith	IN000012	2021/06/07	3,000.00	450.00	3,450.00
Mr. Mike Davies	IN000013	2021/06/10	1,500.00	225.00	1,725.00
Mr. Roger Smith	IN000014	2021/06/12	2,000.00	300.00	2,300.00
Mr. Mike Davies	IN000015	2021/06/15	1,000.00	150.00	1,150.00
Mr. Roger Smith	IN000016	2021/06/17	3,000.00	450.00	3,450.00
Mr. Mike Davies	IN000017	2021/06/20	2,500.00	375.00	2,875.00
Mr. Roger Smith	IN000018	2021/06/24	2,000.00	300.00	2,300.00
Mr. AB Green	IN000019	2021/06/30	5,000.00	750.00	5,750.00
Mr. AB Green	IN000020	2021/06/30	5,000.00	750.00	5,750.00
Mr. AB Green	IN000021	2021/06/30	5,000.00	750.00	5,750.00
Mr. AB Green	IN000022	2021/06/30	5,000.00	750.00	5,750.00
			50,500.00	€ 7,575.00	€ 58,075.00

Description	Qty ship	Qty order	Excl. amt.	Tax amount	Incl
Drill press	2	2	2,000.00	300.00	€ 2,300.00
Compressor	2	2	3,000.00	450.00	€ 3,450.00
			5,000.00	€ 750.00	€ 5,750.00

In the Stock item invoice option of the "*TC Drill Down*" plugin, you can track which invoices were used to sell specific stock items, facilitating quick access to associated sales records. This feature lists all customer accounts with both posted and unposted invoices, detailing items sold in each invoice. It provides invoice numbers, dates, and total amounts, and enables sorting and filtering for efficient invoice management.

Expanding invoices reveals listed stock items with quantities and total amounts, allowing further sorting and filtering for inventory items. This functionality enhances tracking of customer invoices and stock item movements, facilitating effective sales analysis within osFinancials5/TurboCASH5.

By leveraging the Stock item invoice option of the "*TC Drill Down*" plugin, you can efficiently track sales of

individual invoices stock items, identify associated customer (debtor or client) accounts, and gain insights into your stock management and sales processes within osFinancials5/TurboCASH5.

Charts

In the Charts option of the "*TC Drill Down*" plugin, you can visualise your sales data in various formats to gain insights into your business performance. The graphs are as follows:

- Total sales:
  - Total sales : Your total sales per day are displayed in a pie chart. Your inventory items or products are displayed as parts in different colors per day. It will visually display at a glance the day or days in which the most sales occurred.
  - Total sales per day : Your total amount of sales per day is indicated in a bar graph. It will visually display as amounts the day or days in which the most sales occurred at a glance.
- Total quantities:
  - Total sales quantities : Displays the total quantities of your inventory items or products sold during the selected dates in a pie chart. The total quantities of your inventory items or products sold will be displayed as parts in different colors per day. It will visually display at a glance the inventory items or products that are the top sellers during the selected dates.
  - Total sales quantities per day: The total quantities of your stock items or products sold during the selected dates are visually represented in a bar graph. It will visually display at a glance the number of inventory items or products that are the top sellers during the selected dates. It will graphically display how certain days affect the quantities of inventory items or products.



By using the Charts section of the "*TC Drill Down*" plugin and exporting the data, you can effectively analyse your sales performance, identify trends and make informed business decisions based on the insights gained by visualizing your data.

Export the Data

Except the Charts option of the "*TC Drill Down*" plugin, all other options (i.e Transactions, Customer invoice, Invoice stock item, Stock item invoice) in the "*TC Drill Down*" plugin can be exported to a spreadsheet.

Once you have sorted and filtered your criteria, you can export the data in exactly the same order as displayed in the "*TC Drill Down*" screen.

1. Once you have sorted or filtered your data, click on the File → Export menu.
2. The "*Save as*" screen will be displayed.
3. Select a directory in which you wish to export the selected data.
4. Enter a file name.
5. Select one of the following file formats:
    a) XML - Extensible Mark-up Language

b) HTML - HyperText Mark-up Language

c) Excel - Microsoft Excel Spreadsheet

d) Text - Text file

6. Click on the Save button.

Once exported, you can locate the file and open it in your preferred software, such as Microsoft Excel or LibreOffice Calc, to further analyse and visualize the data.

For example, you may use it to build graphs in or Microsoft Excel, LibreOffice Calc spreadsheets, and make powerful presentations of your data in or Microsoft PowerPoint or LibreOffice Impress.

By utilising the Charts section of the"*TC Drill Down*" plugin and exporting the data, you can effectively analyse your sales performance, identify trends, and make informed business decisions based on the insights gained from visualising your data.

Spreadsheets

The exported data can be easily used to build custom pivot tables and charts in spreadsheets. The following is an example of exported data in Microsoft Excel spreadsheet with charts for income and expenses exported using the "*TC Drill Down*":



By using pivot tables and charts in Excel, you can analyse and visualise your expenses data exported from the "*TC Drill Down*" plugin effectively. These tools allow you to gain insights into your spending patterns, identify areas for cost optimization, and make informed financial decisions for your business.

Created with the Standard Edition of HelpNDoc: Elevate Your CHM Help Files with HelpNDoc's Advanced Customization Options

Remittance plugin

Remittance plugin - Manual - Shop - License : Once-off -

Translations : Outstanding

With the remittance plugin allows you to easily manage your outstanding items. You may send an e-mail to all debtors to remind them their outstanding amounts and totals.

You may also print outstanding (arrears) accounts and send them by post.

By also purchasing the Multimedia plugin, you can immediately see which e-mails and reminders you have sent.

The setup and configuration process is briefly as follows:

1. Activate – Enable the Remittance plugin in a Set of Books.
2. Configure the e-mail with the settings and details from your Internet Service Provider (ISP).
3. Creating e-mail templates to be displayed in your system's default e-mail program. You may create any number of email templates for your requirements.
4. Customise the remittance / reminder layout files for your specific needs. These layout files will automatically generate the list of outstanding transactions and the total for each debtor account. The remittance / reminder layout files will be attached to each debtor e-mail.

After the setup and configuration process, using the Remittance plugin is briefly as follows:

1. Access the Remittance plugin. (An option is available to automatically launch this plugin if transactions are outstanding).
2. Check the selection criteria on the Remittance plugin. (You may select and preview remittance layout files).
3. Print selected or all debtors.
4. To send e-mails:
    - Emails may be sent from the Documents grid on the E-mail Pro tab on Debtors accounts (Default ribbon).
    - Enter the e-mail text header (topic / subject)
    - Select an e-mail template. (You may preview the template or the remittance layout file)
    - Enter additional text (free text) to be added to the e-mail template. (An extra file can be attached – in addition to the Remittance layout file).
    - Click on the Send button to fire off the e-mails.

Activation

On the Setup ribbon, select Plugins → Financial tools → Remittance. If this plugin is not listed under Plugins → Financial tools, activate it via Tools → Activate plugins.

The activation screen for the Remittance plugin is launched.



The options are as follows:

1. Enabled: Select the On radio button option to enable the Remittance plugin.
2. Popup if there are transactions (check box): By default, this field is not checked. When you reopen the Set of Books, the Remittance icon (additional icon) will be available on the Default ribbon from where you can manually launch the Remittance plugin. If you select (check) the "*Popup if there are transactions*" checkbox, the Remittance plugin will be launched automatically to remind you when reminders are due.
3. Document style - This option provides 2 interfaces for the Remittance plugin. By default, this option is not checked. If you check or uncheck, the "*Document style*" option, and reopen the Set of Books, the Remittance screen will be initiated from the Remittance icon on the Default ribbon:
4. List button: This will launch the following Remittance screen:



If you do not check the "*Document style*" option, and reopen the Set of Books, the Reminders screen will be initiated from the Remittance icon on the Default ribbon, similar to how the List button is initiated.

5. Save button: If you have clicked on the List button, you need to click on the Close (X) icon on the title bar of the above Remittance screen (this screen will be discussed in the next sections).

6. Reopen the Set of Books. Alternatively, you may close active forms (Tools → Close active forms (Setup ribbon)) and relaunch the Remittance plugin from the Default ribbon to switch between the "*Document style*" option, not selected or selected in Remittance setup.

Document style modes

You may switch to the different modes for processing transactions in the Remittance plugin in Plugins → Financial tools → Remittance (Setup ribbon} . After changing the "*Document style*" option, you may need to:

- Reopen the Set of Books.
- Alternatively, you may close active forms (Tools → Close active forms (Setup ribbon)) and relaunch the Remittance plugin from the Default ribbon to switch between the "*Document style*" option, not selected or selected in Remittance setup.

Document style option - Not selected

If you do not select the "*Document style*" option in Plugins → Financial tools → Remittance (Setup ribbon}, the Remittance screen will display as follows:



The screen consists of four (4) sections as well as the data (columns section):

Selection

1. Open item since pay date from - Enter or select the date.
2. With a remittance date from and to - Enter or select the date.
3. No auto payment - Hide the debtors for which automatic payments have been scheduled.

4. E-mail filter – If this field is not selected, all debtor accounts (including those without e-mail addresses will be listed. Select (tick) this option to hide debtors without e-mail addresses. If selected, only those Debtors with e-mail addresses entered in the E-mail field of the Debtor accounts screen will be listed.

5. Refresh button – After selecting these dates, you may click on this button to list only those transactions matching your selection criteria.

Customise -

1. Adjust remittance date of selection to - Enter or select the date. This will set the date "last reminder" for the selected debtor (or all debtors) to the date selected.

2. Selection button - If you click on this button, the following confirmation message will be displayed:

   "This action will adjust the last date remittance at the "selected" debtors! Do you wish to continue?"

3. All button – If you click on this button, the following confirmation message will be displayed:

   "This action will adjust the last date remittance at the "ALL VISIBLE" debtors! Do you wish to continue?"

Print -

1. Print all button – This will print the Remittance (reminder) layout file for all debtor accounts in the list to the default system printer. These layout files are stored in the following folder:

   " ...\plug_ins\reports\remittance\layouts "

2. Print selected button – This will print the Remittance (reminder) layout file for a selected debtor account in the list to the default system printer. These layout files are stored in the following folder:

   " ...\plug_ins\reports\remittance\layouts "

3. Print preview button - This will print the Remittance (reminder) layout file for a selected debtor account in the list in the Reportman preview screen.

   " ....\plug_ins\reports\remittance\layouts "

4. Edit remittance button - This will open the Remittance (reminder) layout file in the Report designer. You may then edit the Remittance layout files. These layout files are stored in the following folder:

   " ...\plug_ins\reports\remittance\layouts "

5. Edit report - This will open the Remittance (listing all debtor accounts) report in the Report designer. You may then edit the report. These reports are stored in the following folder:

   " ...\plug_ins\reports\remittance\layouts\list.rep "

6. Show report - This will print the Remittance (listing all debtor accounts) report for a selected debtor account in the list in the Reportman preview screen located in the following directory:

   " ...\plug_ins\reports\remittance\list.rep "

7. E-mail selected – This will send the Remittance report as an e-mail attachment for a selected debtor account. To use the E-mail functionality, you need to setup and configure your email settings.

8. E-mail - This will send the Remittance report as an e-mail attachment for all debtor accounts in the list.

Setup options – This section consists of two (2) tabs (i.e. Layout file and General tabs).

- Layout file tab
  - Document layout files – You may select up to 4 remittance (reminder) reports.These reports are stored in the following directory:

    " ...\plug_ins\reports\remittance\layouts "

    You may add your own remittance, reminder reports and edit these reports using the Report designer to suit your specific requirements.
  - You may also specify (enter) the number of days for which the reports must be printed.
- General tab -
  - Advanced options – This is an advanced search filter in which you may enter extra text to filter the debtors on the list. For example, to list only debtor accounts for a specific postal code, enter " *and SPostalCode = '2222' ".* Then click on the Refresh button. This will only list those debtors with postal code *"2222"* on the list.
  - Update in Multimedia - By default all e-mail will be updated in the Multimedia feature of this plugin. Should you wish to send the reminders via the Print selected or the Print all button, you need to select this option, if you need to archive these documents in the Multimedia component of this Plugin.
  - Default days no remittance - Enter the number of days for processing reminders.

Columns - You may click on the * before the column headings. The columns is as follows:



You may click on the (Sorted) option to list and view the columns alphabetically.

Document style option - Selected

If you select the "*Document style*" option in Plugins → Financial tools → Remittance (Setup ribbon}, the Remittance screen will display as follows:



The screen consists of the main section as well as the data (columns section):

Main section

- Email selected button - Once you have selected a debtor account, and you click on this button, it will launch the "*Send Email*" screen. The "*Send Email*" screen, will launch the Free text tab. Before you can send emails for the first time, you need to configure your email settings on the Settings tab from your Internet Service Provider (ISP). The Email settings for the Remittance plugin, only needs to be done

once, unless your requirements changes.

- Show all tick-box -

- Show print button - Once you have selected a debtor account, and you click on this button, This will print the "*Open Item selection*" document layout file. An example of the printed "*Open Item selection*" document layout file,is as follows:



These document layout files are stored in the following folder:

- Edit button - You may edit the statement messages on the following screen:



- Set checked button -
- Document layout - You may select up to four Document layout files for the Remittance plugin. These document layout files are stored in the following folder:

  " \plug_ins\reports\remittance\doctype\layouts "

- Default days no remittance - Enter the default number of days. By default, the number of days entered in the "*Due days*" field on the Accounting informationtab of the Debtors form (Default ribbon), will be displayed.

Columns - You may click on the * before the column headings. The columns is as follows:



You may click on the (Sorted) option to list and view the columns alphabetically.

Important notes to optimise the Remittance plugin

To use this plugin, the exact same principles (good accounting practice) as applicable to all reports should be applied.

You need to check that all transactions for the debtors are posted (updated to the ledger) and check that the correct debit transactions are linked to the correct credit transactions.

If you do not see a list of debtors, the incorrect date is probably selected.

To get back the original list, you can perform this operation:

- The date of the field "*Not since reminded*" puts you on a date, for example, two years later than the date on which it now stands.
- And the field "Customizing the date selection to for example, 2 years back in time.

Unposted batches and documents

Make sure that all:

- Unposted transactions in documents are updated (posted) to the ledger.
- All unposted transactions in batches are updated (posted) to the ledger.
- All unposted transactions in bank accounts (receipts and payments batches) are updated (posted) to the ledger. In the case of using the Bank import plugin – make sure that your bank statements are correctly imported and processed (including updated (posted) to the ledger).
- If you use repeating transactions in batches make sure that these are processed (Repeating transactions) are imported and processed in a normal batch and posted (updated) to the ledger.
- If you are using the Calendar (Planner) make sure that Repeating invoices, Invoices for hours, bulk time entries, etc. are processed (including updated (posted) to the ledger).
- If you need to generate multiple transactions in batches (i.e. Interest on overdue debtor accounts, Balances with outstanding amount less than a specified amount, Fixed amount to all debtors, Charge amounts for debtor accounts (you need to process and post (update) to the ledger.

Open item / Balance brought forward processing

Basic principles:

- Open item processing for debtor accounts will list only those transactions in journals (batches) and documents which is outstanding. Transactions / Invoices which are fully settled (paid) and/or credited

with a credit note (or other batch transactions) will not be listed.

- Balance brought forward processing for debtor accounts will list all the transactions / documents which is recorded (posted (updated) to the ledger). Transactions / Invoices irrespective whether these are fully settled (paid) and/or credited with a credit note (or other batch transactions) will be listed.

Open item processing (recommended)

To check the outstanding items on debtor accounts:

On the Default ribbon, click on the Open item link icon.

On the Totals tab, select Debtors and click on the Filter button. All debtor accounts (set as an open item account on the Accounting information tab), should be linked.

Note - If there are any outstanding items (debit transaction(s) which are not linked to a credit transaction(s)), the line colour will display in an orange colour.



For example, Mr. AB Green, is displayed in an orange font colour. Double-click on that account, it will list the debit as well as credit transactions separately.



If the payment (receipt) and credit notes are linked to the correct transactions, the credit transactions will be cleared and only those invoices with outstanding amounts, will be listed.



In this example, invoice IN000018 will not be listed, as IN000018 is cancelled with credit note CR000001. Invoice IN000022 has a an outstanding amount of 4600,00 as credit note CR000003 of 2875,00 is linked a part of IN000022 to the amount of 7475,00.

Open item reports

In addition to the Open item reports available on the Due tab of the Open item link functionality (Default ribbon), you can also use the following reports to manage open item transactions:

1. Reports menu
    - Transaction reports -
        - Transaction list - Open item - This report lists only those outstanding transactions in documents and batches which are posted (updated) to the ledger. It will list only those transactions with outstanding amounts. Any debit amounts, which are not linked to credit transactions, should be processed in Open item link (Default ribbon).
        - Transaction list - This report lists all the transactions in documents and batches which are posted (updated) to the ledger. All transactions will be listed irrespective of open item links.
    - Debtor statements -
        - Debtor statements - The statement will print all transactions. It does not use the "*Open item*" feature.
        - Debtor statements - Outstanding The statement will print only the transactions with outstanding amounts.
    - Age analysis reports -
        - Age analysis - Balances detail - Displays the reference, date, amount and description for each transaction. The Total outstanding as at the Date of ageing is split to the number of days specified in up to 3 periods.
        - Age analysis - Balances detail history (open item) - This is similar to the "*Balances detail*" report, but it displays the outstanding amount and TransactionID.
        - Age analysis - Balances - This is a similar report as the "*Balances detail*" report. It will only list the balances for each ageing period.

Configuration and setup

If the Remittance plugin is not already configured or automatically launched, you may click on the,

Remittance icon (additional icon) on the Default ribbon.



E-mail account setup

Before you can send e-mails, you need to configure your e-mail account in the Set of Books. This is only a once off configuration. Unless your requirements change.

To do this, you need to click on the E-mail or E-mail selected button.

Settings tab

Then click on the Settings tab.



Select or enter the following, where applicable:

Field	*Description*
Path to the HTML file:	*The default path is displayed as"* "C:\osFinancials5\plug_ins\reports\remittance\emailtemplates\" *If you have installed osFinancials5/TurboCASH5 into a different folder, you may need to overtype this. Specifies the path where the files for the Reminders plugin is located. This path may be edited for your own requirements if you have a personal set of files.*
POP username:	*Enter the POP username as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
POP password:	*Enter the POP Password as registered with your ISP (Internet Service Provider) for your e-mail account settings.*
POP server:	*Enter the POP server as registered with your ISP (Internet Service Provider) for your e-mail account settings.*

Field	Description
SMTP port:	The default port is “25”. This is determined by the default configuration of your operating system and as provided by your ISP (Internet Service Provider) for your e-mail account settings.
SMTP server:	Enter a valid SMTP as registered with your ISP (Internet Service Provider) for your e-mail account settings. Note when POP before SMTP (usually when you are not using your provider sent emails) you can create an e-mail box which nobody reads. This is because if there are multiple ISP's on the mail box mail is read, the POP for SMTP is not working properly. It is best to use an account that is further used by anyone.
SMTP username:	Enter the SMTP username as registered with your ISP (Internet Service Provider) for your e-mail account settings.
SMTP password:	Enter the SMTP password as registered with your ISP (Internet Service Provider) for your e-mail account settings.
Return e-mail:	This field is optional. You may enter your own e-mail address.
Return name:	This field is optional. You may enter your own name ro be displayed on the message to be displayed on the email field of the recipients e-mail or if the message is returned by your ISP in the case of an invalid e-mail address.
E-mail header text:	Type the text to be displayed as the Subject field of your operating system's default e-mail program.
CC: (multiple separate with ;)	This abbreviation CC “Carbon Copy” indicates secondary recipients of a message. Those recipients who are to receive a copy of a message directed to another. The list of recipients in the CC field is visible to all other recipients of the message. Enter a valid e-mail address, if necessary. Note you need to add a space before and after the semi-colon. If you do not add spaces, the first digit of the second and subsequent e-mail addresses may cut off. This could result in an undelivered mail error.
BCC: (multiple separate with ;)	This abbreviation BCC “Blind Carbon Copy” allows you to send a copy of your correspondence to a third party when you do not want to let the recipient know that you are doing this (or when you do not want the recipient to know the third party's e-mail address). You may also wish to enter this filed, when sending an e-mail to multiple recipients, you can hide their e-mail addresses from each other. Enter a valid e-mail address, if necessary. Note you need to add a space before and after the semi-colon. If you do not add spaces, the first digit of the second and subsequent e-mail

Field	*Description*
	addresses may cut off. This could result in an undelivered mail error.
Send max mail:	*The default is "100". You may use the scroll buttons or enter the number of the maximum emails required to send in a batch. This will limit the number of email messages.*
Timer threshold in sec:	*The default is "10" seconds. This is determined by the default configuration of your operating system. It is not recommend ed to change this, but you could experiment by changing the values.*
Default:	*Default is the standard option. You may select the html only option.*
Alt methode:	*Tick to select the alternative mode.*
Send receipt notification:	*If this field is selected (ticked), a read receipt will be requested by the recipient.*
Priority:	*Normal is the default priority. You may select Highest, High, Low or Below low option. This is the priority in which e-mails will be sent.*
Sign any PDF:	*Optional should be you can sign any pdf with this button (also the ones send to you).*
Find certificate:	*If you have a certificate, click in this button to locate it and add it to this plugin.* *You may use add Digital signatures to the PDF (portable document format) files (e.g. OpenSSL pkcs12.pxf) to your e-mail received by your recipients (e.g. debtors (customers).* *See:* · *http://www.openssl.org/* · *PKCS #12: Personal Information Exchange Syntax Standard*
Certificate password:	*If you have selected a certificate, you need to enter a valid password for that certificate.*
Send test mails button:	*You may send test e-mails to check that the configuration is correct.*

- The box (on the lower right-hand side) - Some messages, e.g. may be displayed in the text area of the Settings screen. An example may be "your e-mail address *Login failed"*. This may indicate that something is not correctly entered on the settings.
- Show current sql button - The sql, is used to add the debtors, etc. for the Remittance plugin.

Send E-mail tab

A list of all the debtor accounts matching your criteria for which you will send e-mails will be listed.



Mail template – This is the text which will be displayed in the e-mail message sent to the debtor account(s). At current only one (1) mail template (test.html) is shipped for the English language. You may add your own mail templates as necessary.

The mail template are stored in the following folder

" ...\plug_ins\reports\remittance\emailtemplates "

Once you have created or added your templates, you may select the template.

Edit button – If you click on this button, the ...\plug_ins\reports\remittance\emailtemplates folder will be opened in Windows explorer or your system's default file browser.



To create your own template it is easy and you may create as many templates, as required.

It is recommended that you copy the test.html file and rename it to your own needs.

The basic test.html template is as follows:



You may change all text as necessary. Please take note of the following two (2) fields:

- <#SDESCRIPTION#> - This will add the name for the respective debtor accounts to the e-mail message.
- <#FREETEXT#> - This will add the text as entered for the e-mail messages, as entered on the Free text field on the Free text tab.

You may preview the template when you click on the Preview in browser button on the Free text tab.



Free text tab



Preview in browser button – This will display the mail template in your system's default.



Preview att button – This will display the remittance (reminder) layout file (...\plug_ins\reports\remittance\layouts) in your system's default pdf reader.



Test E-mail to extra CC – Test the mail to the extra e-mail address entered in the Extra CC field. Note if

the remittance (reminder) layout file is opened using the Preview att button an error “Error sending e-mail” message may be displayed.

Extra attachment button – In addition to the remittance (reminder) layout file (... \plug_ins\reports\remittance\layouts) which will be automatically be attached to the e-mail, you may attach another file as an extra attachment. Please note that this attachment will be sent to all debtor accounts on your list.

Send e-mail(s) button – This will start to send e-mails and the attachments to the debtor accounts on the list.

Resume e-mail(s) button - If you have clicked on the Stop e-mail(s) button, this button will start sending the rest of the e-mails.

Stop e-mail(s) button – This will stop the e-mails from sending. You may click on the Resume e-mail(s) button to start sending the rest of the e-mails.

E-mail reminders

Once you have selected your criteria, you may e-mail the reminders to your debtors (customers). To do this, you may click on the following two (2) buttons:

- E-mail selected - click to send e-mail to a selected debtor (customer / client).

Tip : To select more than one debtor (customer / client) on the list, press the Ctrl key on your keyboard and select other debtors (customers) on the list and click on the E-mail selected button.

- Email - click to send e-mails to all the debtors (customers) in the list. This will not send e-mails to all the other debtors (customers) which are excluded from your search and filter criteria.

Recipient's E-Mail message

All debtor (customer / client) accounts (which have a valid e-mail address) will receive an email message with the reminder as a Potable Document Format (pdf file) as an attachment. An example of the e-mail message received by the recipient(s), is as follows:



Note : Remember to check and enter the subject (topic) in the E-mail header text field on the Settings tab. Type the text to be displayed as the Subject field of your operating system's default e-mail program. (In this example, "*Remittance 1-4*" was entered.

Customise remittance layout files



Change the text on the file:

Click on a text object (field) (red rectangles as per this example) and select the Label tab. Overtype the text as necessary.

Move text – drag it to the desired place.

Delete text or expressions.

Adding text

- TRpLabel – Add static text object to the report. Examples on the above picture are, , Telephone:, Fax:, E-mail:, Website:, Company registration no.:, Tax registration no.: address, etc.
- Add the messages or text to display on the report.

Add company logo

TRpImage – Click on this icon and click on the space and drag to insert a blank image object.



Enter “COMPANYDATA.BLOBLOGO” in the Expression field.

This is used to display your company logo on the reports and document layout files. The Company Logo dataset is COMPANYDATA.BLOBLOGO. The logo is stored in the database as a BLOB (Binary Large Object) and will be displayed printed on remittance layout files if loaded in Company info - Options screen (Default ribbon).

Add a static picture

TRpImage – Click on this icon and click on the space and drag to insert a blank image object.

Right-click on the image object and select the Open option on the context menu.

Created with the Standard Edition of HelpNDoc: Experience the Power and Ease of Use of HelpNDoc for CHM Help File Generation

Plugins menu - Generic plugins

CRM

CRM - Customer Relations Management - Manual - Shop - Licence : Annual licence -

Translations : Outstanding

CRM Customer relations management plugin for osFinancials and TurboCASH.

Freefields

Freefields plugin - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Translations : Outstanding

Unlock endless customization possibilities with our Freefields Plugin. With a one-time licence, effortlessly add custom fields to stock items, creditors, debtors, and documents, tailoring your data management to your specific needs.

Key Features:

- Add custom fields to stock items, creditors, debtors, and documents.
- Enter data into custom fields for use in reports and layout files.
- Ideal for product name translation and multi-language invoices.
- Create personalised customer fields without the need for a full CRM application.
- Share custom fields with other Freefields Plugin users.
- Add the Freefields data in reports and layout files with the Report designer.

Enhance your data management and reporting capabilities with the Freefields Plugin, empowering you to create a customised financial environment tailored to your business requirements.

Multi-User Calendar (Agenda)

Multi-User Calendar (Agenda) - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Translations : Outstanding

Effortlessly manage appointments and tasks across your team with our Multi-User Calendar (Agenda) Plugin. With a one-time licence, easily add multiple agendas for users, employees, and salespersons to your calendar, streamlining coordination and boosting productivity.

Key Features:

- Add personalized agendas for each user.
- Each user can manage up to 10 categories of appointments and tasks
- Generate invoices directly from agendas
- Each agenda includes its own calendar and task list
- Bulk time entries create offers a streamlined solution for scheduling and managing multiple appointments for salespersons and debtors. It simplifies the process of creating quotes, transitioning to invoices, and efficiently tracking and billing services.

Optimize scheduling and task management with the Multi-User Calendar (Agenda) Plugin, ensuring efficient coordination and productivity throughout your organization.

Multimedia

Multimedia - Shop - Licence : Once-off -

Documentation : osFinancials website - Manual

Documentation : Help documentation

Translations : Outstanding

Unlock the power of versatility with our Multimedia Plugin. With a one-time licence, seamlessly integrate documents (such as invoices). images, movies, emails, and more into your stock items, debtors, creditors, and documents, enhancing your data management capabilities.

Key Features:

- Add various types of files to stock items, debtors, creditors, and documents.
- Link images, documents, and emails to enhance data organization.
- Link signed and scanned documents to debtors.
- Seamless integration with other plugins such as Email Pro for enhanced email management.
- Outlook Link Plugin integration for automatic email linking to debtors and creditors.

Simplify data management and streamline your workflow with the Multimedia Plugin, providing you with a comprehensive solution for organizing and accessing multimedia content within your program.

Other Generic Plugins

Multimedia Pack

Multi Media Pack - Shop - Licence: Once-off -

Documentation : Help topic.

Documentation : osFinancials website - Multimedia plugin -

The Multimedia Plugin offers versatile functionality, allowing users to link various files within osFinancials5/TurboCASH5. Users can link files to debtors, creditors, stock items, and document groups. For instance, you can attach images to stock items or debtors, as well as link signed and scanned documents to debtors. Additionally,

if you have the Email Pro plugin, emails sent can also be linked to the corresponding documents and debtors, simplifying the process of locating emails related to specific clients. Furthermore, the Outlook Link Plugin can scan through your Outlook inbox and outbox to identify emails using the client's email address, automatically copying relevant emails to the multimedia section of the respective debtor or creditor for easy access.

Paperless Office Multimedia Plugin

Paperless Office Multimedia Plugin - Shop - Licence : Once-off -

Go beyond traditional paperwork and embrace the future of office management with our Paperless Office Multimedia Plugin. With a simple one-time licence, enhance your workflow by seamlessly attaching documents, images, videos, emails, and more to your products, creditors/debtors, and documents like invoices.

Effortlessly organize and access essential files directly within osFinancials5/TurboCASH5, streamlining your operations and maximizing productivity. Say goodbye to clutter and hello to a more efficient, digital workspace with Paperless Office Multimedia Plugin.

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

Multi-user Agenda plugin

Multi-user Agenda plugin - Manual - Shop - Licence : Commercial : Once-off payment -

With this plugin you have the possibility the run multiple agenda in osFinancials5/TurboCASH5.

You can have a agenda for each employee and create invoices directly from out his/hers agenda with a simple click.

Each agenda has it's own calendar and task list.

Introduction to Multi-user Agenda plugin

This plugin enhances multi-user agenda (multiple agendas) on the Calendar. You can add agendas and link them as default to the current user. For every agenda a tab will appear in the agenda in osFinancials so you can see what the other agenda's have for appointments. You may also create invoices for each of these all agendas.

You can have a agenda for each employee, salesperson, user, etc. and create invoices directly from his / her agenda with a simple click. Each agenda has it's own calendar and task list.

If you create users in the Setup → Access control menu, you may link each of these users to their own Agenda on the *Access Control - Others* tab.

There are ten (10) main categories of events which you can manage (add, edit, delete or change dates of events) for each users agenda. These are:

- Appointment (general - i.e. with bank manager, lunches, etc.)
- Repeating invoices - schedule when you need to copy / process repeating invoices.
- Debtors appointment - schedule any of the six (6) categories of appointments with debtors / customers for specials, accounts, etc.
- Creditors appointment - schedule appointments with creditors / suppliers for orders, accounts, etc.
- Hours - schedule the hours (time) to invoice debtors / customers. Once these are set you may generate Quotes for the hours. Once these Quotes are generated, you may edit them (if necessary) and convert them to Invoices.

An example of the Multi-user Agenda screen is as follows:



- User dates - Displays only for the selected user.
- General dates - Displays for all users.
- Appointments- Appointments (events) scheduled for this day
- Flexi-time - Time may be set different for each working day. You may also use colours to display the working hours for each different working day. For example, on Tuesdays, the user may work longer hours e.g. from 6:00 - 17:00 while working from 08:00 - 16:00 on other days.
- Tasks - Each user has its own task list. Once a task is completed, the user may tick the task as completed. The task will be displayed with a line through the text. Overdue (unattended) tasks will be indicated in a red font colour.

Activate the Multi-user Agenda plugin

To Activate the Multi-user calendar plugin:

1. On the Setup ribbon, select Plugins → Generic → Multi-user Agenda. If this plugin is not listed under Plugins → Generic, activate it via Tools → Activate plugins.



If you have not purchased and registered this Plugin, and launch this plugin from the Tools → Activate plugins menu Setup ribbon), following message is displayed:

> You will need to purchase this plugin to enable it.

2. On the "*Register plugins*" screen, select (tick) the "*Enable multyuser agenda'* option to activate it.



3. Click on the Close button. At first only the osFinancials tab / TurboCASH tab is added to the Calendar.

Adding users to the Multi-user Agenda plugin

To add users to the Multi-user Agenda plugin:

1. On the Calendar, click on the add / edit button. The Resource Maintenance screen is displayed:



2. Click on the ✚ button to add a user.



3. Enter the name for the User. You may also add additional text for the user, if necessary.
4. Select (tick) the "*Use as default for this user*" option to load the user when launching the calandar.
5. Click on the OK button to save this resource.
6. If you need to set colours or add / edit delete special day events for the user, click on the Edit special day events button.
7. Click on the Agenda button.
8. Click on the Tasks button or on the osFinancials tab / TurboCASH tab (or any of the User tabs, if already created). This will add the new user's tab for each resource added..



9. Click on the New User's tab to view his / her agenda. An example of the Multi-user Agenda (after a users have been added), is displayed as follows:

Change events to another user

By default, all existing events scheduled before adding users to the Multi-user agenda plugin, will be available under the main resource, i.e. osFinancials5/TurboCASH5. You may need to select these and assign or change these to specific users.

You may assign an event / appointment from a user to another user.

To do this, select an event / appointment and right-click.

On the context menu, select the Change to option.





Select an user and click on OK.

The selected event will be removed from the existing user and added to the selected user.



Colour coding also makes it easier to identify the category of the event, when displayed in the Calendar.

Editing General and Special dates

To edit General and Special dates:

1. On the the Calendar, select a User on the tabs.
2. Click on the Edit special days button to change the colors and to add, edit or delete user dates for the selected user. You may also change the colors and to add, edit or delete days applicable to all users on the General dates tab.



3. To select the colours, click on the Select color button.



4. Once finished, click on the Save button.

5. Click on the Tasks or Agenda button. The resources will be changed for the selected user.

The standard colours will be displayed. To select different shades or customise your colours, click on the Define Custom Colors button. You may drag the slider up or down, etc. to select your own color. Once you have decided upon a color, click on the Add Custom Colors button and on the OK button. This will

generate and insert the color code into the Special days screen.

Delete a user

This operation cannot be undone. Make absolutely sure that this is the correct user, before deleting. Should you delete the incorrect user, you need to recreate the user that was erroneously deleted.

To delete a user from the Multi-user Agenda

1. Launch the *Calendar*, if not already displayed.
2. Select the correct User on the tabs, if the correct user is not already selected.
3. Click on the add / edit button. The *Resource Maintenance* screen will be displayed.
4. Make absolutely sure that this is the correct user. If not, select a user from the *Resource* list or click on the correct User tab.
5. Click on the button to delete a user. The User will be removed from the list and the User tabs.

Bulk time entries

Users may create hours events for a selected debtor (customer / client). To do this, click on the Bulk time entry.



On the Bulk time entry screen, The User will be displayed.



Select and enter the start dates and number of hours.

Select a stock item (usually sales no stock type)

Select the debtor (customer / client) account.

Click on the Create entries button. A confirmation message will be displayed.

"Entries created!"



Once the entries are created, these entries will be listed in the calendar.

You may then edit the Hours event, if necessary. You need to click on the Create invoices for hours button on top of the Calendar to generate invoices.

These Bulk time entries will be listed on the Appointment tab of the selected debtor (customer / client) account.

Reports for the Calendar

The Calendar report allows you to print the categories of events (i.e. Appointments, Debtor appointments, Creditor appointments and Hours) scheduled in the Calendar (Planner).

To print Calendar - Hours report:

1. On the Reports ribbon, select Reports → Calendar.



2. Select the period on the Per period tab. You may click on the Per date(s) tab to select a specific date or a range of dates.

3. Select the the following options:

    a) Agenda - Select to include the general events (e.g. meetings, appointments, etc.).

    b) Debtor appointment - Select to include the appointments for debtor (customer / client) accounts. All appointments are also listed in the Appointment tab of the Debtors (Default ribbon).

    c) Creditor appointment - Select to include the appointments for creditor (supplier / vendor) accounts. All appointments are also listed in the Appointment tab of the Creditors (Default ribbon).

    d) Hours - Select to include the appointments for the hours event category. The are scheduled appointments for which quotes are generated and confirmed to invoices.

4. Click on the OK button.

An example of the "*Calendar - Hours*" (all events) report, is as follows:



The colours for the events are as follows:

Repeating invoices are not included in this report.

In addition to osFinancials5/TurboCASH5 resource, will be replaced when using the Multi-user Agenda plugin with the name of the Resource (User). This report will be printed for each user.

The resource can also be linked to an user in the Others tab of the Setup → Access control menu.

Settings for the Calendar

Set the Calendar as default

By default, the Welcome screen will be launched when opening a Set of Books. You may activate the Calendar to be displayed when opening a Set of Books.

When launching osFinancials5/TurboCASH5 and you open the Set of Books, the Welcome screen will be displayed. When opening the Set of Books again, the Calendar will automatically be displayed.

To set the calendar as the default option when opening the Set of Books:

1. On the Setup ribbon, select Setup → System parameters.
2. Select (tick) the "*Show calendar*" field.
3. Click on the OK button.

Access control settings

To add users and settings for the Multi-user Agenda:

1. On the Setup ribbon, select Access control.
2. Add users, if necessary.
3. Click on the Others tab.
    - Link to calendar - The resource can also be linked to an user in the Others tab of the Setup → Access control menu.
    - Edit calendar - Allow or block user to add evens, tasks, contacts, etc. to the calendar.
4. Click on the OK button.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

*Freefields plugin

Freefields plugin - Manual - Shop - Licence : Once-off -

Translations : Outstanding

Unlock endless customization possibilities with our Freefields Plugin. With a one-time licence, effortlessly add custom fields to stock items, creditors, debtors, and documents, tailoring your data management to your specific needs.

Key Features:

- Add custom fields to stock items, creditors, debtors, and documents.
- Enter data into custom fields for use in reports and layout files.
- Ideal for product name translation and multi-language invoices.
- Create personalised customer fields without the need for a full CRM application.
- Share custom fields with other Freefields Plugin users.
- Add the Freefields data in reports and layout files with the Report designer.

Enhance your data management and reporting capabilities with the Freefields Plugin, empowering you to create a customised financial environment tailored to your business requirements.

Using the Free Fields Plugin

Usage:

In the plugin you can define fields which can than be used to be filled with data.

In reports you can get the information of these fields.

Tips:

You can use it for productname translation, for multi-user language invoices.

Not up to a full CRM application yet? Create your own customer fields in osFinancials5/TurboCASH5.

Share your free fields with other osF free field users.

The free fields plugin allows you to create custom fields for basically any form (screen) in osFinancials5/TurboCASH5. The intention is that data will have their own table. This optimization is possible through the use of indexes. Referential integrity is also applied so that the data is and stays consistent. All benefits of a database is preserved and can be optimized locally. Using reportman you may add the data in a reports. These are fairly technical matters but you can try it before hiring our help.

Important:

Please make a backup of your Set of Books before using the Freefields pluin.

The possibilities in the Freefields plugin is endless. The data can be exported and imported. This can also be used for external data (from the other systems).

For example, using the Freefields plugin in osFinancials5/TurboCASH5, you could Add the make, model, year, of a motor vehicle, lessons a student can follow, credit details of a debtor (customer / client), etc.

The user of the system just enjoy updates to the core and Freefields and needs for standard frameworks which only some attributes are different or extra.

Special custom fields and powerful solutions can be added to the database at a fraction of normal development costs.

Activation

On the Setup ribbon, select Plugins → Generic → Freefields. If this plugin is not listed under Plugins → Financial tools, activate it via Tools → Activate plugins.



Select On to activate the Freefields plugin. You can activate Freefields and maintenance of search screens (Design search fields) and dialog (Design edit fields).

Design edit fields

If you click on the *Design edit fields* button you will see the following screen.

You probably have less free field definitions, but you can add more.



If you double-click on "*SYSVARS*" or click on the Edit fields button, you may add extra field. For example, if you click on the "*Contact name*" field, the options and settings for that field is displayed.



The options is as follows:

- Cancel: Cancel and go to the list.
- Save: Saves the layout in the database. If new fields are created, this process can not be undone. Pay close attention to the type and length of the field. These can not be readily modified once the field is created.
- Add: Adds a new control to these field and you can then edit.
- Remove: Delete active control.
- Save and rebuild: Save Input settings below so that you see it. When creating a new field (Colomn origin that does not exist), a field of type in Field type created. This is not just to remove this editor. We refer you to a database management tool like FlameRobin. FlameRobin allows you drop the fields. Alternatively, you may execute this by using SQL by example the command alter table mytable to enter the correct value. drop out mycolumn

- Type of control: You can choose from different types of controls so that interaction with that space is affected. Types are explained in the appendix at the back of this document. Choose the type of control for the correct data type. For example, A checkbox is a SMALLINT, a numeric value with decimal places a FLOAT, etc.
- Size: Set the size (width) adjusting this field is great for a text or numeric field (like big) once the field is defined in the database has no effect You will then have to build the large field in the database itself.

- Translation: Choose an existing translation or add one to the current database and use it. When you change the Language, the translated text or label will be displayed on the form.
- Column origin: Enter your new field name when creating a new control or choose from an existing list columns. For example, if you have a table designed, you can choose from this list the fields you want to edit.
- Field type: A new field (not existing name in Column origin) is used as this type is created. Depending on the type is then also taken along the Size.
- Default value: Default value may be a set. (For example, "select current_timestamp from rdb $ database" creates a date field – today as the default value for this field. This is usually combined with the head type a to-many relationship.
- Left, Width, Top, Height: Controls to set the width increases etc., Some controls do not have all the values. For example, you may set a memo type to enter multiple lines. When doing an edit, the height has no effect.
- Enabled: Set the field (temporarily). This usually comes at a migration in which old data e x a time are still visible.
- Sql and extra data: For some field types, this field is used, for example to build. The sql of a list with This is a dropdown filled with the correct value. For example, dressings can be used to build up a choice list. Think of a list box in a document that knows which debtor has been chosen and therefore can be used to limit. The list of possible choices the free fields of debtor.

The input fields for "*Sysvars*" is found in Setup → Company info.


Company info
Address
Options
Company name
Handyman Hardware Store
Address
27 Olifants Road
Emmarentia
Johannesburg
Postal code
2195
Company reg. no.
336012345
Tax reg. no.
446010111
Tel
(011) 310-1390
Fax
(011) 310-2000
E-mail
mymail@myisp.net
Bank name 1
Holder's name 1
Bank account no. 1
SWIFT nr
IBAN nr
BIC
Bank name 2
Holder's name 2
Bank account no. 2
SWIFT nr
IBAN nr
BIC
Additional Data
Contact name
Digidan
Mobile
079555555
Website
OK
Close

Create freefields a more complex example



We will now take a more complex example. A new one to many relationship for a debtor. Here we create fields for the date and a memo field for the call.

Click the Add button and enter the following information.

- Formname: An internal name must be unique.
- Displayname: The name used for this tab. You can have multiple tabs with a single entity. this may then also contain a variety of relationships.
- Master table: The table to which this free fields are linked. When creating it is also used for reference integrity.
- Linked key: The key used in that table (primary key)
- Table: If this does not exist it will be created.
- PrimaryKey: The Primary key for a one to many relationship like this can be linked to the key for a one many will own generator should be used.
- Sql for next id: For one to many using the text "select GEN_ID (GEN_TESTID 1) from RDB $ DATABASE" as in the picture above.

If it's a one on one relationship space (dummy value) can be used to observe the linked key. Primary key equal.

If you have done this, press Save. A confirmation message to create the new table will be displayed.

You get that whether you want to create this table. Press Yes to add the table. The new fields this You can also select No hence, your input is not lost and you will be given the choice to create the table next time.

If the table is created, we can continue to add new fields by clicking the Edit fields button or double-clicking the name in the list.



To add the next control and enter the following:

- Type of control: D TDateTimepicker
- Size: Does not matter in this type
- Translation: Open the screen and looking to date.
- Column origin: ddate this is the name of the new field in the database.
- Field type: Date Time

- Default value: select current_timestamp from rdb $ database

Now press Save above the type of control. You will then whether the field can be created. Press Yes and move the control down slightly. Then press again Add new control to a second control to add.

- Type of control: M Memo Field
- Size: to 0 = infinite
- Translation: Look for Remark
- Column origin: SMEMO this is the name of the new field in the database.
- Field Type: Blob
- Default value: blank
- Left top width and height 120, 300, 18, 300, we want the input level increases.

Even with this, you answer Yes. Then press Save at the top and your work is saved.

Close active windows

Now close all windows of the free fields plugin. To do this, on the Setup ribbon, go to Tools → Close active forms.

Creating generator

You must now create the generator for generating a unique number for the table.

Open the Handy tools via Plugins → Generic → Handy tools, choose the "*Run SQL*" tab and enter it in the text

create generator GEN_TESTID;



Sql create generator GEN_TESTID processed!

If you press the Execute button, you have the generator created.

See the results

Open new window and select the debtors a debtor in the list. Press Edit to edit the Freefields tab in the tabs at the bottom of the debtor.



You should now see where you can enter multiple records. Extra tab there If you press the + sign, go to the detail screen.

Here you can contact moments capture and directly enter a new record or the current store.

Freefields Entities

With free fields can now associate the following entities to a free field layout.

- STOCK: Stock chart
- STOCK_DESCRIPTIONS: Inventory Description Table
- DEBTOR: Accounts Receivable
- CREDITOR: Creditors
- JOBCOST: Projects
- GROUPS: Groups
- GROUPS_DESCRIPTIONS: Group descriptions.
- EVENTS: Agenda appointments
- SYSVARS: Your company data or fixed dates.

There you can use different field types with different controls.

Special types are:

- STOCK_DESCRIPTIONS: a language is to define a layout. This so that a dropdown in a screen the English translations can pick up and the Dutch of the Dutch translation.
- GROUPS: For each group type is to define a layout. Group 1 in stock so other data can only be introduced by a group of debtors. This is mainly used to capture additional data for a webshop with product groups to think here at Search words etc.
- For these types, the language (STOCK_DESCRIPTIONS) id from GROUPS and GROUPS the WGROUPTYPEID of the specific group should be placed after the creation of the screen.

Freefields Controls

There are several controls available below the declarations and the use of it.

- M Memo - This control allows you to enter large blocks of text. Whether this is a STRING type and size length or a BLOB type with an endless length. With this control, it is possible to give up. An altitude

Field Type: STRING, BLOB

- B CheckBox - With this control you can make a checkbox function. This is the best type smallint but an integer or nummeric may also.

  Field Type: Narrow Ribbon, Integer, Numeric

- IC CheckListBox - This control, you can create a checklist feature. The list is stored as a string, so you need to reserve enough space for the list.

  Field Type: String

- IL ComboBox - Allows you to produce a dropdown list. This control can use different types of fields to write the data. Way in Usually, this lookup and so it is the type field is equal to that of the key from the lookup field and that is usually, but integer string may be:

  Field Type: Integer, Narrow Ribbon, Float, String

- D TdateTimePicker - Date Control field type datetime, timestamp

  Field type datetime, timestamp, String, float

- T Time - Time control field type datetime, timestamp

  Field type datetime, timestamp, String, float

- Edit (text) - Text control for text input

  Field Type String

- N Number - Enter numerical values (with a limit on the number of decimal places)

  Field Type: Float

- F Float (numeric) - Enter numerical values with a number of decimal places

  Field Type: Float

- OC lookup creditors - Special lookup for osFinancials5/TurboCASH5 to link creditors. This is a quick search screen that are always stored in numeric fields.

  Field Type: Integer

- OD Lookup Debtors - Special lookup for osFinancials5/TurboCASH5 to link debtors. This is a quick search screen that are always stored in numeric fields.

  Field Type: Integer

- OG Lookup GL accounts - Special lookup for osFinancials5/TurboCASH5 to link general ledger

accounts. This is a quick search screen that are always stored in numeric fields.

Field Type: Integer

- IP Lookup tax account - Special lookup for osFinancials5/TurboCASH5 to link Tax (VAT/GST/Sales tax) accounts.

  Field Type: Integer

- DB Lookup Bank Account - Special lookup for osFinancials5/TurboCASH5 to link Bank accounts. This is a quick search screen that are always stored in numeric fields.

  Field Type: Integer

- OS Lookup Stock accounts - Special lookup for osFinancials5/TurboCASH5 to link stock items. This is a quick search screen that are always stored in numeric fields.

  Field type: Integer

- OA Lookup all GL accounts - Special lookup for osFinancials5/TurboCASH5 to link all accounts This is a quick search screen that are always stored in numeric fields.

  Field Type: Integer

Created with the Standard Edition of HelpNDoc: Don't Let Unauthorized Users View Your PDFs: Learn How to Set Passwords

Multimedia plugin

Multimedia plugin - Manual - Shop - Licence : Once-off -

Introducing the Multimedia Plugin for osFinancials5/TurboCASH5

The Multimedia plugin empowers you to seamlessly integrate various file types (e.g., Word, PDF, images, videos, emails) into your Set of Books in osFinancials5/TurboCASH5 data. These multimedia files can be associated with:

- Stock Items: Enrich product information with brochures, images, tutorials, and more.
- Creditors: Store scanned invoices, contracts, and other relevant documents.

- Debtors: Attach credit agreements, photos, and other customer-related files.
- Sales and Purchase Documents: Add supporting files to specific transactions.
- Batch Entries: Add multimedia to journal entries.
- Groups: Add multimedia files based on reporting groups.

How to Add Multimedia: You can add files to the database using various methods:

- To Database: Directly upload the file.
- Link File: Create a link to an existing file.
- Copy File: Create a copy of the file in the database.
- URL: Link to a file on the internet.
- Paste from Clipboard: Paste a copied file directly.

Benefits of the Multimedia Plugin:

- Centralized Storage: Keep all relevant documents in one place.
- Easy Access: Quickly view, edit, and print files as needed.
- Enhanced Record-Keeping: Improve organization and traceability.
- Enriched Information: Provide more context and detail for better decision-making.

By leveraging the Multimedia plugin, you can streamline your workflows, improve data accuracy, and enhance overall business efficiency.

License

The multimedia plug-in is a versatile product. You can link files in divergent forms of osFinancials5/TurboCASH5.

Examples are debtor, creditor, stock items, batches (journals), documents and groups. You can link a image to stock items or debtors but also link signed and scanned documents to debtors.

If you also have the email pro email send will also be linked to the document that was send and the debtor. This makes finding that email to the client with great ease. The outlook link plugin can scan true your outlook in and out box to see if there is email that uses the clients email address. If so it copies the email to the multimedia of that debtor / creditor.

If you have a TWAIN device then you can directly scan from the device to the multimedia.

TWAIN is supported by Web cams, scanners and other image devices.

Other plugins can be used with the Multimedia plugin

Plugins that make use of the multimedia

E-Mail Invoice Pro plugin

The E-mailPro plugin is bundled with the Multimedia plugin only for use with the E-mailPro plugin. To enable and use the Multimedia plugin for all other features, you need to purchase and activate it separately.

If you also have the E-mailPro plugin, it will also be linked to the document that was sent to the debtor (customer / client) / creditor (supplier / vendor). This makes finding that email to the client with great ease. The outlook link plugin can scan through your outlook in and out box to see if there is e-mail that uses the clients e-mail address. If so it copies the e-mail to the multimedia of that debtor (customer / client) / creditor (supplier / vendor).

Reminders / Remittance plugin

The Reminders plugin is bundled with the Multimedia plugin only for use with the Reminders plugin. To enable and use the Multimedia plugin for all other features, you need to purchase and activate it separately.

More Plugins that make use of the multimedia

- E-commerce: Add product images, specifications, and user manuals to online listings.
- Outlook sync: Synchronize emails from Outlook with osFinancials5/TurboCASH5 records and attach them to the Multimedia plugin.
- CRM: Customer Relationship Management: Add files, such as, customer-related documents, such as contracts, proposals, and correspondence.

Note: The E-mail Invoice Pro and Remittance plugins are bundled with the Multimedia plugin for specific functionalities.

To enable and use the Multimedia plugin for its full range of features, you may need to purchase and activate it separately. To find the perfect plugin combination for your specific needs, please visit our webshop.

Activate the Multimedia plugin

The Multimedia plugin needs to be activated in each Set of Books.

To activate the multimedia plugin:

1. On the Setup ribbon, select Plugins → Generic → Multimedia. If this plugin is not listed under Plugins → Generic, activate it via Tools → Activate plugins (Setup ribbon).

2. The Multimedia - General tab screen is displayed:



3. Click On option to enable it.

4. The General options is as follows:

   a) Defaultgroups – Links the input to default extensions to group types. Add default groups for file types. Enter a line like this .jpg=testgroup 1 and on the next line *.bmp=testgroup 2*".

If you double-click in the Defaultgroups box it will be populated with the following:

```
.jpg=products_image
.gif=products_image
.png=products_image
STOCKGROUPNEXT.JPG=1
STOCKGROUPNEXT.GIF=1
STOCKGROUPNEXT.PNG=1
```

> *All files with the extension .jpg will be placed in the first group of the list (products_image for default stock images) the line 'STOCKGROUPNEXT.JPG' makes sure the next unique value will be automatic selected from the list of groups. You add groups by simply typing in your group name.*

b) Export stock – This button will launch the "*Save As*" screen. With the function export files to stock you can add images quickly with a file that contains a stock code and a full image path.

c) Import files to Stock – This button will launch the "*Open*" screen. This file must be a "*tab delimited*" file format. You may import files.

d) Import files to std group – This button will launch the "*Open*" screen. You may import files.

e) Extract Files from db to file - This button extracts the files from the active Set of Books to the database and creates a file .creates a file.

f) Show search list – By default this option is not selected. Select this option to add the Multimedia icon to the Default ribbon. This will allow you to filter and search for multimedia files.

5. Click on the Image tab.



6. The options is as follows:

a) Image to Jpg – Tick this option to convert a "*GIF / PNG / BMP / WMF / EMF*" image to the Jpg file format. You may specify the minimum compression ratio from 1 ... 100.

> *Before selecting the Image to Jpg conversion, it is recommended that you have a copy your images somewhere on your system. If it happens, that the conversion and compression does not work properly, you are covered.*

b) Show preview – Tick this option if you have an image file.

c) Select fill color – The default color is "*White*". This button launches the "*Color*" screen, on which you may pick from the standard colors or define your own custom colors. This will allow you to convert images to the same size filling up the spaces with a predefined color. It also allows you to see an example adjust and then preview the result until you are satisfied.

d) Make all same size – Tick this option, if you wish to convert all images to the same size.

e) Max size on convert – You may tick this option to convert all images to a specific size. The default size is 400 x 400. You may enter your preferred size.

f) Watermark – If you wish to add a watermark to your images, you may enter text. You may also specify the shading of the watermark from light to dark.

7. Click on the Save button. This will add the "*Multimedia"* tab to the following screens (i.e. Stock items (Products), Creditors (suppliers/vendors) and Debtors (customers/clients)). On the screens for Document grid (i.e. Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders) you have the option to add and manage multimedia files. The Multimedia icon will be added to the Documents form which you can add and manage and edit the multimedia files in unposted documents.

Managing Multimedia Files

If you have ticked the "*Show search list*" tick box in the Plugins → Generic → Multimedia (Setup ribbon). the Multimedia icon will be added to the Default ribbon. This will allow you to filter and search for multimedia files.

The "*Show search list*" field is by default not selected, or if you deselect the "*Show search list*" field at the later stage the Multimedia icon will be removed from the Default ribbon. Whatever option you have selected in the "*Show search list*" field, you may access the Multimedia plugin from the following options:

1. Multimedia tab on the following screens:

a) Creditors (suppliers/vendors).

b) Debtors (customers/clients).

c) Stock items (Inventory items/products).

2. Multimedia icon from which you may manage and edit the multimedia files on the following screens for Documents:

   a) Debtor (customer/client) documents (i.e. Invoices, Credit notes, Quotes).

   b) Creditor (supplier/vendor) documents (i.e. Purchases, Supplier returns and Orders).

3. Multimedia in Batches (Journals) - Context menu on Batch entry screens.

4. Multimedia in Groups - Context menu on Reporting group 1 or Reporting group 2 for all available reporting groups.

Multimedia Basics

In this example, the Multimedia tab for Stock items is used to illustrate the options for working with Multimedia files. The basics are similar to those Multimedia tabs and screens launched from other forms.

Adding Multimedia files

Go to the Multimedia tab of your stock item, debtors, creditors, documents.

The default view is the "*List*" view.

In this example, Multimedia plugin for Stock items is shown. Similar features is available for debtors, creditors, documents, etc.



You may click on the column headings (i.e. Groups, Description, File location and original file name to change the sequence of the multimedia files on the list.

To add a multimedia file, click on the Add icon.



This will list five options in which you can add Multimedia files in your Set of Books:

1. Copy file file - These files are stored in the files folder in sub folders for the year and month. You want to ensure that the file is always available, even without an internet connection.
2. To database - This option embeds the file directly into the Set of Books database for seamless integration with other data. The file is stored in the database of the Set of Books.
3. URL - This option to provide the direct link to the file. Only the Hyperlink or other URL link is stored. This option will reference a file hosted on a website or cloud storage service. This saves storage space and allows for easy access from different devices. This option requires an internet connection to access the file. You may experience potential for broken links, if the file is moved or deleted online, the link becomes invalid.
4. Link file - Use this option to reference the file's location. The full path where the selected file is stored on your system.
5. Paste from clipboard - The file name of the file pasted from your systems clipboard. The file is copied from your clipboard and pasted directly into your Set of Books.

Select one of the above options. The "*Open"* screen will be displayed for the "*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options. Select a valid file format and click on the Open button. The file will be added to the list. You may then enter or edit the Groups and Descriptions on the list, as necessary.

> *If you select the Add – URL option, the Show details option will be displayed. You then need to enter the Groups, Description, File Location (i.e. ftp or web address of the file) and the original name of the file.*

View/Edit Multimedia files

To view or edit the details, click on the Show details button.

1. Cancel icon - The Cancel icon is by default inactive. If this icon is activated during a process, you may abort the process.

2. Delete icon - Select a file and click on the Delete icon. The file will be removed from the list.

> *Make absolutely sure that the correct entry is selected. This delete cannot be undone.*

3. Show details icon - To view or edit the details of a selected item on the list, click on the Show details button.



   - Groups – Select a group from the list, if necessary. You may also enter (type) a group name, if not on the list. Once this is done, you need to click on the Save icon. The newly entered group, will only be added to the list, once you click on the Save button of the form.
   - Description – You may change it if necessary.
   - File location – If the "*File location*" displays the file name preceded by type e.g. link for a linked file; and file for a copied file, you may click on the > ("*Open folder*") button to open the file location folder for the selected file.
   - Original file name - The name of the original file as added to the multimedia plugin.
   - File date – Your operating system's date and time will automatically be added for the "*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options.

4. View/Edit icon - Click on the View/Edit button to open a file and view it in the default program associated with the file type on your operating system.

   - You may print and/or edit the file.
   - Once you have viewed and or edited the file; and the file is closed, a confirmation message, will be displayed.

> "Press OK when you are done editing the file to save it to the database!"

- Click on the OK button to save the file to the database.
- Click on the Save button.

5. Navigation
   - < Previous icon - Click to navigate to the previous record.
   - Next icon > - Click to navigate to the next record.
6. Save icon - Once you have changed (edited) any of the available fields, this Save button will be activated. Click to save your changes.

> *You still need to click the Save button of the form, e.g. Stock items, Debtor / Creditor, etc.*
>
> *If you do not save the form, your added files, or any changes may be lost.*

7. Scan icon - If you have a TWAIN device configured and setup on your system, then you can directly scan from the device to the Multimedia plugin. TWAIN is Technology for an Accessible Imaging Interchange Standard. It's a standard protocol for image scanning and transfer between applications.

   TWAIN is supported by Web cams, scanners and other image devices. ("Technology Without An Interesting Name" humorous).

   The "*Select Source*" screen will be displayed on which you may select a device.

Multimedia Search List

The Multimedia search list is by default this option is not selected. To add the Multimedia icon to the Default ribbon, you need to select (tick) the "*Show search list*" option on the General tab when activating the Multimedia plugin (Plugins → Generic → Multimedia on the Setup ribbon). This will allow you to filter and search for multimedia files.



On the Default ribbon, select Multimedia.



Multimedia Search – Types

The "*Types*" of Multimedia files are grouped in four (4) basic types:

1. DEBCR – Multimedia files added on the Multimedia tab of Debtor / Creditor accounts.
2. STOCK – Multimedia files added on the Multimedia tab of Stock items.
3. BATCH – Multimedia files added to Batch entry and Document entry screens. The multimedia files added in Batch entry and Document entry screens will only be updated (added) to the Search list, once Batches and Documents are posted (updated) to the ledger.
4. GROUP – Multimedia files added for Reporting groups 1 and/or Reporting groups 2 in Setup → Groups (Setup ribbon)).

Multimedia – Groups

In addition to the "*Link image*" option on the Reporting groups (for example Stock group1 or Stock group2) you may add files ("*To database*", "*Link file*" and "*Copy file*" or "*URL*" options), using the Multimedia plugin for your Reporting groups.

To add Multimedia files to Reporting groups:

1. On the Setup ribbon; select Setup → Groups.
2. Select the Reporting group.
3. Select the group in the list of groups.
4. Right-click and select "*Multimedia*" from the context menu.



5. The "*List view*" of the "*Multimedia*" screen will be displayed.



6. Click on the Add button and select the "*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options.
7. Click on the OK button to save the multimedia files to the selected group.

GROUP - Multimedia search list

If you have added multimedia files for your reporting groups, such as Stock groups, Salespersons), it will

be available under GROUP type on the "*Multimedia search list*" (Multimedia icon on Default ribbon).

Add and Manage Multimedia files for Debtors (customers/clients)

In addition to the "*Link image*" option on the Reporting groups (for example Debtor group1 or Debtor group2) you may add files ("*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options), using the Multimedia plugin for your Reporting groups.

Some examples of multimedia files for debtors

Some types of documents that could be added to the multimedia plugin for debtors (customers/clients):

Customer Information:

- Customer Profiles: Detailed information about each customer, including contact information, purchase history, and preferences.
- Customer Agreements: Contracts or agreements outlining the terms and conditions of business relationships with customers.
- Sales targets: You can empower your sales teams to achieve their goals, improve performance, and drive revenue growth.

Sales and Invoicing Documents:

- Invoices: Detailed invoices for products or services sold to customers.
- Sales Orders: Documents confirming the purchase of products or services by customers.
- Credit Notes: Documents issued to customers for refunds or credits.

Marketing Materials:

- Customer Newsletters: Regular newsletters with company news, product updates, and promotional offers.
- Marketing Brochures: Marketing materials promoting products or services to customers.

Other Relevant Documents:

- Delivery Notes: Documents confirming the delivery of products to customers.
- Return Authorizations: Authorizations for customers to return products.

By including these types of documents, businesses can improve customer service, streamline operations, and enhance the overall customer experience.

Add Multimedia files for Debtors (customers/clients)

The Multimedia plugin will add a Multimedia tab to all Debtor (customer / client) accounts.

To add multimedia files to debtors (customers):

1. On the Default ribbon, select Debtors.
2. Select a specific Debtor (customer / client) account and click Edit button. Alternatively, you may double-click on the account.
3. Click on the Multimedia tab. The "*List view*" of the "*Multimedia*" screen will be displayed.



4. Click on the Add button and select the "*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options.

DEBCR - Multimedia search list

If you have added multimedia files for debtors (customers/clients), it will be available under DEBCR type on the "*Multimedia search list*" (Multimedia icon on Default ribbon).

Add and Manage Multimedia files for Creditors (suppliers/vendors)

In addition to the "*Link image*" option on the Reporting groups (for example Creditor group1 or Creditor group2) you may add files ("*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options), using the Multimedia plugin for your Reporting groups.

The Multimedia plugin will add a Multimedia tab to all Creditor (supplier / vendor) accounts.

Some examples of multimedia files for creditors

Here are some types of documents that could be added to the multimedia plugin for creditors (suppliers/vendors):

Supplier Information:

- Supplier Profiles: Detailed information about each supplier, including contact information, product offerings, and performance metrics.
- Supplier Agreements: Contracts or agreements outlining the terms and conditions of business relationships with suppliers.

Purchasing and Invoicing Documents:

- Purchase Orders: Documents confirming the purchase of products or services from suppliers.
- Supplier Invoices: Invoices received from suppliers for products or services purchased.
- Credit Notes: Documents issued to suppliers for refunds or credits.

Payment and Reconciliation Documents:

- Payment Remittance Advice: Documents confirming the payment of supplier invoices.
- Bank Statements: Bank statements showing payments made to suppliers.
- Supplier Reconciliations: Documents reconciling supplier accounts and identifying any discrepancies.

Other Relevant Documents:

- Delivery Notes: Documents confirming the delivery of products from suppliers.
- Quality Control Reports: Reports on the quality of products or services received from suppliers.

By including these types of documents, businesses can improve supplier relationships, streamline procurement processes, and optimize cash flow.

Add Multimedia files for Creditors (suppliers/vendors)

To add multimedia files to creditors (suppliers/vendors):

1. On the Default ribbon, select Creditors.
2. Select a specific Creditor (supplier / vendor) account and click Edit button. Alternatively, you may

double-click on the account.

3. Click on the Multimedia tab. The "*List view*" of the "*Multimedia*" screen will be displayed.



4. Click on the Add button and select the "*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options.

DEBCR - Multimedia search list

If you have added multimedia files for creditors (suppliers/vendors), it will be available under DEBCR type on the "*Multimedia search list*" (Multimedia icon on Default ribbon).

Multimedia – Stock items (Inventory items/Products)

The Multimedia plugin supports various file formats such as documents, images, videos and more.

Some examples of multimedia files for stock items (Inventory items/Products)

Some types of documents that could be added to the multimedia plugin for stock items/inventory items/products:

Product Information:

- Product Specifications: Detailed information about the product's features, dimensions, materials, etc.
- Product Datasheets: Comprehensive technical information, including performance data, maintenance instructions, and troubleshooting guides.
- Product Catalogs: Digital catalogs showcasing a range of products, including images, descriptions,

and pricing information.

Guarantees and Warranties:

- Warranty Certificates: Official documents outlining the terms and conditions of the warranty, including coverage, duration, and claims procedures.
- Guarantee Letters: Letters from the manufacturer or supplier assuring the quality and performance of the product.

Operator's Manuals:

- User Manuals: Step-by-step instructions on how to use and operate the product.
- Installation Guides: Detailed instructions for assembling and installing the product.
- Maintenance Manuals: Guidelines for regular maintenance and troubleshooting.

Safety Data Sheets (SDS):

- SDS Documents: Information on the potential hazards associated with the product, including safety precautions, handling instructions, and first aid measures.

Marketing Materials:

- Product Brochures: Marketing materials promoting the product, including key features, benefits, and pricing information.
- Product Videos: Demonstrations, tutorials, or unboxing videos to showcase the product's features and benefits.

By including these types of documents, businesses can provide customers with comprehensive information about their products, enhancing their understanding and confidence in making purchasing decisions.

Add Multimedia – Stock items (Inventory items/Products)

To add multimedia files to stock items (products):

1. On the Default ribbon, select Stock items.
2. Select the stock item (inventory item/product).
3. Click on the Multimedia tab. The "*List view*" of the "*Multimedia*" will be displayed.



4. Click on the Add button and select the "*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options.

View/Edit - Multimedia – Stock items (Inventory items/Products)

Once your multimedia files have been added, you may view these multimedia files.

To view and edit the Multimedia files:

Select a stock item (inventory item/product) on the list and click on the Edit button. Alternatively, you may double-click on a selected stock item (inventory item/product).

All the multimedia files will be listed for a selected stock item (product).

Click on the View/Edit button. On the Multimedia screen you may use the filter and grouping options, to locate a specific item.

To view a specific multimedia file, you may click on the View/Edit button. The file will be opened in your system's default application program associated with the file type extension (for example *.pdf).

Multimedia – Transactions

Multimedia – Documents

The multimedia files added in Document forms will only be updated (added) to the Multimedia search list, if the Documents are not yet updated (unposted) to the ledger.

Added multimedia files will only be available in the Multimedia search list if the Documents are updated

(posted) to the ledger.

Added multimedia files will not be saved in posted documents.

This plugin may be used to manage multimedia files on the following documents:

- Sales documents (i.e. Invoices, Credit notes and Quotes).
- Purchase documents (i.e. Purchases, Supplier returns and Orders).

Multimedia – Unposted Documents

To add Multimedia files on Documents:

1. On the Default ribbon, select Documents. The "*Document entry*" listing "*Invoices*" will be displayed. If necessary, select the document type you wish to process.
2. To edit a selected document click Edit / or New to create a new document.
3. Click on the Multimedia icon. The "*List view*" of the "*Multimedia*" screen will be displayed.



4. Click on the Add button and select the "*To database*", "*Link file*" and "*Copy file*" or "*URL*" options..

> *If you need to add multimedia files for more than one stock item (product), you need them all on the document.*

5. Click OK on "Multimedia screen.
6. Click OK on the Document form.

BATCH - Multimedia search list

If you have added multimedia files in unposted documents, it will only be available under BATCH type on the "*Multimedia search list*" (Multimedia icon on Default ribbon) once the document(s) have been updated (posted) to the ledger.

To view the Multimedia files added to stock item:

Select the stock item (product) and click on the Multimedia icon. The Multimedia list view screen will list the multimedia files for the stock item (inventory item/product).

Multimedia - Posted documents

Multimedia files attached to a posted document, may be viewed.

To do this;

1. Select a posted document and double click.
2. Click on the Multimedia icon. The "*List view*" of the "*Multimedia*" screen will be displayed.



3. Show details this will display the details for the multimedia file. If you click on the > Open folder button (on the right side of the If the "File location" displays the file name preceded by type e.g. link for a linked file; and file for a copied file, you may click on the > ("*Open folder*") button to open the file location folder for the selected file.
4. Click on the View/Edit button to open a file and view it in the default program associated with the file type on your operating system.

5. You may print and/or view the file.
6. Click on the OK button to close the Multimedia screen.
7. Click on the Cancel button of the Document form.

> *If you add a multimedia file or delete the multimedia file on a Posted document, your changes will not be saved. The reason for this, is that you cannot edit a posted document.*

Copy documents

If you copy a selected document, the Multimedia files will not be copied. You need to decide whether to include these multimedia files, or select other multimedia files, if required.

Cancel / Reverse posted documents

Multimedia files will be removed when you cancel or reverse a sales document (Invoices and Credit notes) or a purchase document (Purchases or Supplier returns)), in the Global processes → Reverse posted batch/document menu on the Setup ribbon. Once a document is reversed you may access the document as an unposted document in Documents on the Default ribbon.

On the Document form, you may edit the document. When editing the document, you may add the Multimedia files for the stock items/inventory items/products), as necessary.

Multimedia – Batches

If the multimedia files added to transactions in Batch entry screens, it will only be updated (added) to the "*Multimedia search list*", once the batches are posted (updated) to the ledger.

Unposted journals (batches) will not be available in the Multimedia Search feature.

Add Multimedia files to a Batch (Journal)

To add Multimedia files to Batch transactions:

1. Select the batch type. Once you have entered a transaction, you may add Multimedia files.
2. On a selected transaction in the Batch entry screen, right-click on a transaction.
3. On the context menu, select the "*Plugin action → Multimedia*" option.



4. The "*List view*" of the "*Multimedia*" screen will be displayed.



5. On the Multimedia screen, click on the Add button and select the "*To database*", "*Link file*", "*Copy file*", "*URL*" and "*Paste from clipboard*" options.

6. Click OK on the multimedia screen.

To view the Multimedia files added to transactions in an unposted batch

Select the transaction and double-click on it. The Multimedia list view screen will list the multimedia files for the transaction.



Show details button. This will show the detail such as the Group, Description, File location, original file name and File date.



View/List button - This will launch the selected multimedia file in your system's default application or program associated with the file type.

BATCH - Multimedia Search Type

If you have added multimedia files in unposted batches (journals), it will only be available under BATCH type on the "*Multimedia search list*" (Multimedia icon on Default ribbon) once the batches (journals) have been updated (posted) to the ledger.

Cancel / Reverse posted batches (journals)

Multimedia files will be removed when you cancel or reverse a posted batch (journal). in the Global processes → Reverse posted batch/document menu on the Setup ribbon. Once a batch (journal) is reversed you may access the batch (journal) as an unposted batch (journal) in Batch entry on the Default ribbon.

On the Batch entry form, you may edit the batch (journal). When editing the batch (journal), you may add the Multimedia files for the transactions, as necessary.

Multimedia - Calendar (Planner)

Currently the Multimedia is not supported in the Calendar (Default ribbon). Once you have created documents from the Calendar, these documents will be generated as an unposted document. You may add Multimedia files for your stock items (inventory items/products) in these unposted documents

Multimedia – Projects

If you have activated Projects (on Setup → System parameters (Setup ribbon)), and created Projects on the Input → Projects menu, the Multimedia plugin will add a tab to the Projects.

Search Multimedia files

To add the Multimedia icon to the Default ribbon, you need to select (tick) the "*Show search list*" option on the General tab when activating the Multimedia plugin (Plugins → Generic → Multimedia on the Setup ribbon).

Multimedia Search - Types

You may search an filter Multimedia files in the STOCK, DEBTORS, CREDITORS, BATCH and GROUP categories on the "*Multimedia search list*" (Multimedia icon on Default ribbon).



Added Multimedia files can be searched, filtered and sorted by "*Type*" to manage your multimedia files in the following categories:

- STOCK - Multimedia files added in the Multimedia tab of Stock items (Default ribbon).
- DEBCR - Multimedia files added in the Multimedia tab of each debtor (customer/client) account in the Debtors / Creditors (Default ribbon).
    - Debtors (Default ribbon) - Multimedia files added in the Multimedia tab of each debtor (customer/client) account.
    - Creditors (Default ribbon) - Multimedia files added in the Multimedia tab of each creditor (supplier/vendor) account.
- BATCH - Multimedia files added in the following options:
    - Batches (Journals) (Default ribbon) - You may add multimedia files for the transactions, according to your specific needs. Only the batch (journal) transactions linked to multimedia files will be listed, if the batch (journal) is posted (updated) to the ledger.
    - Documents - You may add multimedia files for the Stock items (Inventory items/Products)

according to your specific needs. All document types for sales documents (Quotes, Invoices and Credit notes) and purchase documents (Orders, Purchases and Supplier returns) and support multimedia files. Only the documents linked to multimedia files will be listed, if the document is posted (updated) to the ledger.

- GROUPS - Multimedia files added in the Setup → Groups menu (Setup ribbon) for your reporting groups.

Multimedia Search – Filter options

In addition to the standard filters ("*Type*" and "*File date*") you may enter a name or a description to search for.

You may drag a column next to the Change date and File date to group the multimedia files for the selected column.

You may also build custom filters (adjusted filters).



Multimedia Search – View files

To view and edit the Multimedia files:

Select an item on the list and double-click on it. The Multimedia screen, listing all the available files of your selection, will be launched.



On the Multimedia screen you may use the filter and grouping options, to locate a specific item.

To view a specific multimedia file, you may click on the View/Edit button. The file will be opened in your system's default application program associated with the file extension (for example *.pdf,).

Multimedia Files Storage

Multimedia files are stored in the files folder within the Set of Books directory, for example:

```
E:\osfinancials5\books\MY-BOOKS\files\2024\11
```

Within the files folder, the Multimedia files are stored in the Year/Month folders. In this example, the files are included in the Year *'2024'* and the month '11' which is November.

Each file will be prefixed with a numeric number for example, *'1_Filename'* and file type extension.

Multimedia files added with the following options is not stored in this folder:

- To Database -The file is embedded and sored in the database of the Set of Books.
- Link file - The file is linked to location, elswere on your system or network.
- URL - The path or webaddress is set to a link on the internet where the files are stored.

Understanding the Multimedia File Storage Structure

Key Points:

- Year and Month Organization: Files are categorized by year and month for easy retrieval.
- Numeric Prefix: This ensures files are sorted in a specific order, which can be useful for various purposes (e.g., chronological order, importance).
- File Extension: The file extension indicates the file type, allowing for proper handling and display.

Potential Use Cases:

- Document Management: Storing and organizing various document types like PDFs, Word documents, and presentations.
- Image and Video Storage: Centralizing images and videos for easy access and reference.
- Backup and Recovery: Implementing a backup strategy to safeguard important multimedia files.

By understanding this structure, you can effectively manage and access your multimedia files within the specified directory.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

CRM plugin

CRM Plugin (Customer Relations Management) plugin

CRM Plugin (Customer Relations Management) plugin - Manual - Shop - Licence : Annual licence

Translations : Outstanding

CRM reports

CRM Plugin in mostly translatable - but reports only in Nederlands. Need to add translatable reports.

These may be selected on All accounts - Mass contacts tab to print these files and to email these emaillltemplates.

actlayout1 folder

Location : ...\plug_ins\reports\CRM\actlayout1

1. act 1.rep
2. act 2.rep

3. layout 1.rep

4. remote support.rep

These 4 reports replicates similar error

> Type conversion error 'Round':Expression TRpExpression27

actlayout2 folder

Location : ...\plug_ins\reports\CRM\actlayout2

1. act 1.rep

2. act 2.rep

3. layout1.rep

Prints intern nummer and a barcode

printouts folder

Location : ...\plug_ins\reports\CRM\printouts

1. act 1.rep

2. act 2.rep

3. layout1.rep

Prints news letter in dutch

Emails templates

Emails templates only supports the Nederlands language.

email1

Location : ...\plug_ins\reports\CRM\emails\email1

emailaction

Location : ...\plug_ins\reports\CRM\emailaction\emailtemplates

CRM Plugin

Enhance your customer relationship management with our CRM plugin for osFinancials and TurboCASH.

With an annual licence, gain access to powerful features designed to streamline lead management and customer interactions.

Key Features:

- Lead Management: Easily add and manage leads within the system for efficient tracking and follow-up.
- Flexible Data Import: Import leads effortlessly by loading a file and defining custom data fields. Supported file formats include comma or tab-delimited files.
- Customizable Fields: Define your own data fields based on your specific requirements. No fields are compulsory, providing flexibility in data entry.
- Tagging System: Tag leads and existing clients for easy categorization and organization.
- Contact Management: Record contact moments such as phone calls, emails, or meetings, enabling comprehensive communication tracking.
- Document Integration: Attach documents to leads or client profiles using the multimedia plugin. Additionally, upload images for visual identification, such as group photos or individual portraits.
- Visual Identification: View attached images or documents directly within the debtor profiles, facilitating quick identification and reference.

Streamline your CRM processes, enhance lead management, and improve customer interactions with the CRM plugin for osFinancials and TurboCASH.

CRM allows you to add leads - Easy way to (load in a file and define a definition yourself) It must be a separated file - i.e. comma or tab delimited

non of the fields are compulsory

you can add tags to leads and existing clients

add contact moments - i.e. phoning him or he phones you

add documents through multimedia plugin or a image of the person (group name photo)

this image can then be viewed at debtors (like stock item) or in the plugin

CRM Plugin - Tab Dashbord view

Article Index

CRM Plugin

Activate the CRM plugin

Starting the CRM plugin

The CRM Plugin is managaged in the following tabs:

Dashbord view - View the Group activities and Group leads in a Totals view or a Tree view

Leads tab

- Search,
- Import / Export (Add, Delete, Pull from Outlook from a selected date)
- Mas tag
- Conversion

Activities

- Search
- Invoicing
- Delete

All accounts

Search tab - Filter group options,

Mass tags Add and manage Mass tags, start and end date time, by CRM activity, CRM activity status.

Mass activity

Mass contacts - Send e-mails

Billing matrix

Activities

Calendar

On the CRM screen, the totals for the selected periods is displayed.

CRM Plugin - Tab Dashbord view

- CRM Plugin
- Activate the CRM plugin

- Starting the CRM plugin
- Tab Dashbord view
- Tab Leads
- Tab Activities
- Tab All accounts
- Tab billing matrix
- Tab Activities

On the CRM screen, the totals for the selected periods is displayed.



CRM Plugin - Tab Leads



CRM Plugin - Tab Activities



CRM Plugin - Tab All accounts



CRM Plugin - Tab billing matrix


CRM
Dashbord view
Leads
Activities
All accounts
Billing matrix
Calendar
Username
<No data to display>
Use your mouse to pull a column here to group on that column
CRM Activity
Inventory Item
Minimum bill m
Increment bil
<No data to display>

CRM - Calendar tab



Created with the Standard Edition of HelpNDoc: What is a Help Authoring tool?

Plugins menu - Point-of-Sale

CCV Pin

CCV Pin - PIN transaction integration for CCV a dutch pin equipment builder. - Shop - Licence :

Secure your transactions seamlessly with our CCV Pin Plugin. Designed for integration with CCV, a Dutch pin equipment builder, this plugin ensures smooth PIN transaction processing within your system.

Key Features:

- Seamless integration with CCV pin equipment
- Streamline PIN transaction processing
- Enhance security and reliability in transactions

Ensure secure and reliable transactions with the CCV Pin Plugin, tailored specifically for Dutch pin equipment from CCV.

Customer on hold

Customer on hold - Manual - Shop - Licence : Once-off -

Enhance your Point-of-Sale (POS) experience with our Customer on Hold Plugin. Designed for the Standard free POS module, this plugin allows you to put POS invoices on hold, enabling you to add products to the invoice later, making it ideal for businesses like bars or restaurants.

Key Features:

- Put POS invoices on hold for later modification.
- Ideal for bars, restaurants, and similar businesses.
- Specifically designed for the Standard free POS module.

Streamline your POS operations and improve customer service with the Customer on Hold Plugin, exclusively available for the Standard free POS module.

The HorecaPOS and RetailPOS system, do not support this plugin.

HORECAPOS

HORECAPOS - Shop - Licence : Annual subscription - The HORECAPOS Plugin is sold with the support contract and multi-user plugin for free.

See Video of the latest version(Dutch) Video of an older version(Dutch) .

Elevate your catering experience with our HORECAPOS Plugin, offering a tailored checkout system specifically designed for the hospitality industry. Speed up customer service with handheld computers while maintaining control over ordered products.

Key Features:

- Customize checkout system for catering establishments
- Utilize handheld computers for efficient customer service
- Print orders directly to kitchen, bar, or POS printers
- Specify products as "kitchen" or "bar" items for appropriate printing
- Offer product options for customer preferences
- Quick product selection through search or icon-based interface
- Manage table layout and place settings on floor plan
- Split or merge tables with ease
- Split total orders effortlessly
- Hold orders for processing later

Get the HORECAPOS Plugin, including support and a free multi-user plugin for enhanced functionality. Streamline your hospitality operations and provide top-notch service to your customers.

HorecaPOS addition quantity on hand adjustment

HorecaPOS addition quantity on hand adjustment - Manual - Shop - Licence : Annual subscription -

The HorecaPOS Addition Quantity on Hand Adjustment Plugin, available through an annual subscription, empowers employees to conveniently update the quantity on hand for specific items within the HorecaPOS system. This functionality enables seamless management of inventory levels, allowing employees to accurately track stock movements in real-time. For instance, employees can input the quantity of pies retrieved from the freezer or steaks prepared for baking, ensuring that inventory records remain up-to-date and reflective of actual stock levels.

POSDisplay Plugin

POSDisplay Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help topic

The POS Display plugin enhances the customer experience during checkout by utilizing a second monitor

(minimum 600x800 resolution) to display detailed invoices. Customers can easily view their purchases and the corresponding prices per item, as well as the total amount due.

Additionally, the plugin enables you to showcase product images on the second monitor while customers wait to check out. These images can be set to rotate at specified intervals, attracting attention to special offers or promotions. Rotation options include displaying images at the top, left, or right side of the invoices.

POS Points

POS Points - Customer loyalty points - Manual - Shop - Licence: Once-off

Boost customer loyalty with our POS Points Plugin. With a one-time licence, easily set up a customer loyalty program where a percentage of each sale is converted into points. Customers accumulate points with each purchase, which can then be redeemed for discounts on future purchases.

Key Features:

- Set percentage of sales to be converted into points
- Accumulate points with each purchase
- Redeem points for discounts on future purchases
- Enhance customer loyalty and satisfaction

With the POS Points Plugin, you can incentivize repeat purchases and foster long-term relationships with your customers, ultimately driving business growth and success.

RetailPOS

RetailPOS - Manual - Shop - Licence: Annual subscription

Transform your retail operations with our RetailPOS Plugin, designed specifically for the retail industry. With an annual subscription, enjoy comprehensive Point-of-Sales functionality, including support for touch screen monitors, barcode scanners, and wireless access control via RF-ID.

Key Features:

- Point-of-Sales functionality tailored for retail and rental industries

- Support for touch screen monitors and barcode scanners
- Restrict login access controlled by RF-ID
- Sell directly from the shop floor with handheld computers (PDAs)
- Compatibility with other plugins, including Price Agreements, Serial/Batches/Locations

Elevate your retail experience with the RetailPOS Plugin, offering seamless integration of essential features to streamline operations and enhance customer service.

Created with the Standard Edition of HelpNDoc: Experience a User-Friendly Interface with HelpNDoc's Documentation Tool

POSDisplay plugin

POSDisplay Plugin - Manual - Shop - Licence : Once-off -

Documentation : Help topic

The POS Display plugin enhances the customer experience during checkout by utilizing a second monitor (minimum 600x800 resolution) to display detailed invoices. Customers can easily view their purchases and the corresponding prices per item, as well as the total amount due.

Additionally, the plugin enables you to showcase product images on the second monitor while customers wait to check out. These images can be set to rotate at specified intervals, attracting attention to special offers or promotions. Rotation options include displaying images at the top, left, or right side of the invoices.

Activate and test POSdisplay

1. On the Setup ribbon, select Plugins → Point-of-Sale → PosDisplay. If this plugin is not listed under Plugins → Point-of-Sale, activate it via Tools → Activate plugins.



2. To load images, simply open the folder on the system where your pictures or image files are stored.
3. Drag the files to the Left Images, Top Images and Right Image columns.
4. Click on the Save and Close button.

Display

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

RetailPOS plugin

RetailPOS plugin - Licence : Manual - Shop - Annual subscription -

The rules with a green color are already available.
The rules with a black color are development requests.
The rules with a blue color are being developed.

The Retail POS plugin is designed to enhance the functionality of osFinancials specifically for retail businesses. It provides features tailored to meet the needs of the retail industry. Here are the functional requirements and features of the Retail POS plugin:

1. Quantity Totalization: When multiple quantities of the same item are purchased, the plugin totalizes them on a single line, simplifying the presentation of the receipt.
2. Product Options: The plugin supports the use of product options, allowing for customization or selection of different variations or features of a product.
3. Additional Options: The plugin provides the capability to handle additional options such as money handling or waste disposal stations, enabling seamless integration with specific retail requirements.
4. Rental Functionality: The plugin includes functionality for handling rental items, allowing businesses to manage rentals and associated transactions within the point-of-sale system.
5. Orders on Hold: The plugin supports placing orders on hold, allowing users to save incomplete orders and retrieve them later for further processing.
6. Order Splitting: Users can split orders into separate transactions, which is useful for customers making partial payments or dividing the purchase between different payment methods.
7. Flexible Payment Methods: The plugin enables the configuration of specific payment methods to be used at the point of sale, providing flexibility to accommodate various payment options accepted by the retail business.
8. Price Agreements: Retail businesses can utilize price agreements within the Retail POS system to offer special pricing or discounts to specific customers or customer groups.
9. Real-Time Sales Reporting: The plugin provides real-time sales results in the form of charts or graphs, allowing businesses to monitor and analyze sales performance.
10. Touchscreen Support: The Retail POS plugin is designed to work seamlessly with touchscreen monitors, providing an intuitive and user-friendly interface for sales transactions.
11. Groups and Color Schemes: Users can organize products into groups and utilize color schemes for efficient categorization and visual differentiation.
12. Comments in Sales: The plugin allows users to add comments or notes to sales transactions, providing additional information or instructions.

13. Serial Numbers/Batch/Locations: The Retail POS system supports the use of serial numbers, batch numbers, and location tracking for inventory management and tracking purposes.
14. Real-Time Salesman Switching: Users can switch between salesmen in real-time within the Retail POS system, facilitating seamless transition and continuity during sales transactions.
15. RF-ID Login Control: The plugin offers login restriction and control using RF-ID (Wireless Access) technology, enhancing security and access control.
16. Customer Selection: Users can choose an existing customer with each sale, allowing for personalized service and tracking of customer transactions.
17. Prepayment Capability: The plugin supports prepayment functionality, allowing customers to make payments in advance and providing proof of payment at the checkout.
18. Handheld Computer (PDA) Support: The Retail POS system is compatible with handheld computers (PDAs), enabling sales transactions directly from the shop floor, enhancing mobility and customer service.
19. Customer Creation: The plugin allows for customer creation directly within the POS system, facilitating efficient customer onboarding and data management.
20. Customer Search by Postal Code: The POS system provides a search function to find customers based on their postal code and home number, streamlining customer identification.
21. Previous Sales/Product Search: Users can search for previous sales or products that were already purchased within the POS system, enabling quick access to customer history and previous transactions.
22. Barcode Selection: When multiple barcodes match a scan, the system presents a selection screen with additional product information, assisting in accurate product identification.
23. Change Display: The plugin continues to display the change amount even when the cash drawer is opened, ensuring visibility and transparency during cash transactions.

Please note that the mentioned features are specific to the Retail POS plugin within osFinancials. The plugin provides a comprehensive set of functionalities to meet the specific requirements of retail businesses, streamline sales processes, and enhance customer service.

Created with the Standard Edition of HelpNDoc: Streamline your documentation process with HelpNDoc's WinHelp HLP to CHM conversion feature

HorecaPOS

HorecaPOS plugin - Video of the latest version(Dutch) Video of an older version(Dutch) - Shop -Licence : Annual subscription -

The Horeca POS plugin is a specialized checkout system designed specifically for catering establishments, such as restaurants, cafes, and bars. This plugin enhances the functionality of osFinancials by providing features tailored to the needs of the hospitality industry.

Here are some key features and functionalities of the Horeca POS plugin:

1. Handheld Computer Support: The plugin supports the use of handheld computers, which can speed up the process of serving customers and provide better control over the ordered products. Staff can take orders directly at the table using handheld devices.
2. Ticket Printing: After an order is recorded at a table, the plugin enables the printing of order tickets specific to the kitchen, bar, or the main point of sale (POS) computer. The printer specified for each product type will be used to print the order details.
3. Product Options: The plugin allows for the use of product options, such as specifying additional items like butter, mustard, or bread, to customize orders based on customer preferences or requirements.
4. Quick Search Function: Products can be easily selected through a quick search function based on the starting letter of the product name, making it efficient to locate and add items to the order.
5. Visual Product Selection: The plugin offers an icon-based interface that allows users to navigate through product groups and select products using visual representations. This can be particularly useful for quick and intuitive selection, especially in high-pressure environments.
6. Floor Plan Management: With the floor plan feature, the plugin enables the management of tables and seating arrangements. Users can indicate which tables are in use and how many place settings are occupied. Tables can be split or merged as needed, and the total order can be split into separate bills with the press of a button.
7. Hold Orders: After closing the active screen, orders can be placed on hold, allowing flexibility and the ability to manage multiple orders simultaneously.

The Horeca POS plugin is available for purchase with a support contract, and the multi-user plugin is provided for free. Upon payment, users will receive an unlocking code via email to activate the purchased plugin.

HorecaPOS addition quantity on hand adjustment

- *Manual* - *Shop* - Annual subscription - This plugin is available as part of an annual subscription plan, providing continuous access to the quantity on hand adjustment functionality.

This plugin provides functionality for employees to manually adjust the quantity on hand for specific items in the HorecaPOS system. This plugin is designed to streamline inventory management processes in the hospitality industry, allowing for accurate tracking of stock levels.

Here are the key features and details of the HorecaPOS addition quantity on hand adjustment plugin:

1. Manual Quantity Adjustment: The plugin enables employees to manually adjust the quantity on hand for specific items within the HorecaPOS system. This adjustment can be made based on actual stock counts or inventory movements.
2. Shop-Level Functionality: The plugin operates at the shop or location level, allowing adjustments to be made specifically for the inventory of that particular shop or location.
3. Use Cases: The plugin is particularly useful for situations where employees need to update the quantity on hand for specific items. For example, it can be used when items are taken out of the freezer, prepared for cooking, or made available for immediate use.

By utilising the HorecaPOS addition quantity on hand adjustment plugin, businesses in the hospitality industry can ensure accurate inventory management, avoid stockouts or overstocking, and maintain control over their stock levels. The plugin enhances the functionality of the HorecaPOS system by providing a streamlined process for manual adjustments to the quantity on hand for specific items.

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

---

Localisation-Batches-Serials

Localisation-Batches-Serials - Manual - Shop - Licence: Once-off

Documentation : Help documentation

Translations : Outstanding

Efficiently manage your product inventory with our Localisation-Batches-Serials Plugin. With a one-time licence, this plugin enables you to track the location, batches, or serial numbers of your stock items when processing documents such as purchases and invoices.

Key Features:

- Track product location, batches, or serial numbers

- Enhance inventory management during document processing
- Ideal for maintaining accurate records of stock items

Reports: Access several reports under Reports → Plugins → Locations-Batches-Serials, including:

- On hand: Lists serials or batches available for sale to customers.
- Stock movement: Lists serials or batches purchased from suppliers and sold to customers.
- Bought from supplier: Lists serials or batches purchased from suppliers.
- Sold to customer: Lists serials or batches sold to customers.
- Outdated batch: Lists serials or batches that are still on hand but past the maximum sales date.

This plugin provides comprehensive inventory tracking and management capabilities within the osFinancials5/TurboCASH5 software, ensuring efficient control over your stock items.

Quick Order

Quick Order - Manual - Shop - Licence: Once-off

Translations : Translations outstanding

Documentation : Help documentation

Translations : Outstanding

Simplify your product ordering process with our "*Quick Order*" plugin. This plugin offers a quick and convenient method for ordering products from your PC or using a handheld PC or smart phone (through Remote Desktop / Terminal Services or RDP).

- You walk with a handheld through your warehouse, and scan or selected the product to order while standing next to the shelf.
- You see immediately actual stock numbers so that a good decision of the quantity to order can be made.
- After pressing a button it creates an order with the specified numbers.
- After which only a few clicks of the mouse will break down the order by vendor.

Optimize your ordering workflow with the "*Quick Order*" plugin, providing you with a seamless and efficient solution for managing your product orders.

Stock check / Stock correction plugin

Stock check / Stock correction - Manual - Shop - Licence: Once-off

Translations : Translations outstanding

Documentation : Help documentation

Translations : Outstanding

This "*Stock correction*" plugin allows users to perform inventory counts conveniently from various devices such as PCs, handheld PCs, or smartphones. This can be done either through Remote Desktop (RDP) or Terminal Services.

Upon pressing a Generate document button, the plugin automatically generates a credit note with the incorrect numbers. This feature helps in documenting discrepancies in stock counts. After the credit note is generated, the plugin proceeds to correct the stock numbers based on the inventory count performed. This ensures that the inventory records are accurate and up to date.

New Android Stock Count.

The "*New Android Stock Count*" at an extra cost of 200,00 euros, excluding tax, allows users to connect to the plugin via their local network using an Android device. The Android version of the plugin supports barcode scanning functionality. Users can use a Bluetooth-enabled barcode scanner to scan barcodes of the stock items, which facilitates faster and more accurate stock counting.

Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Serials-Batches-Location plugin

Serials-Batches-Location plugin - Manual - Shop - Licence : Once-off -

Added the Serials and Batches to document layout files and 2 reports (i.e. On hand and Stock movement report).

Translations : Translations outstanding

The "*Serials-Batches-Location*" plugin in osFinancials5/TurboCASH5 appears to be a tool designed to manage and track inventory, specifically serial numbers, batches, and locations. *Here's a summary of the key features and steps to activate and use this plugin:*

Features:

1. Serial : Allows for tracking individual serial numbers, suitable for items like phones or computers. You can track manufacturing dates or production dates and sell by dates or expiry dates.
2. Batch/Location : Enter batch numbers and quantities and have the possibility to move between locations. You can track manufacturing dates or production dates and sell by dates or expiry dates.
3. Location : Just location management. Focuses on managing item locations in your shop, store, or warehouse. You can add locations (e.g., bin, aisle number, row) where you store stock items if needed.

Activate in Stock Items:

- In the Stock items section, a new tab called "*Location-Serials-Batches*" is added for each stock item.
- By default, this feature is set to "Off" for all stock items.
- You can activate it for specific items and choose one of the three tracking types: Serial, Batch/Location, or Location.

Processing Documents:

- For purchases, you can enter new batches or serials after selecting the product. The system automatically updates the quantities when you enter serial numbers. Similar functionality is available for supplier returns.
- For sales invoices, you can select from the list of locations, serials, and batches of the selected product. Similar functionality is available for credit notes.

Printing Documents:

- Serial numbers or batch numbers will appear on delivery notes, invoices, credit notes, delivery notes, purchases, and supplier returns.

Search for Serial Numbers:

- You can search for serial numbers using the Search function on the Default ribbon.
- Enter the serial number or other criteria in the "*Search for*" field.
- You can search for documents or stock items matching your criteria.

Reports:

- There are several reports available under Reports → Plugins → Locations-Batches-Serials, including:
    - On hand: Lists serials or batches available to sell to customers.
    - Stock movement: Lists serials or batches purchased from suppliers and sold to customers.

- Bought from supplier: Lists serials or batches purchased from suppliers.
- Sold to customer: Lists serials or batches sold to customers.
- Outdated batch: Lists serials or batches that are still on hand but past the maximum sales date.

This plugin seems to provide comprehensive inventory tracking and management capabilities within the osFinancials or TurboCASH software.

Introduction

The "*Serials-Batches-Location*" plugin allows you to purchase and sell products (stock items) and keep track of serial numbers, batches and locations.

In addition to serials, batches and locations, you may keep track of a manufacturing and sell by date.

You can select 3 different types of tracking.

1. Serial : Allows for tracking individual serial numbers, suitable for items like phones or computers. You can track manufacturing dates or production dates and sell by dates or expiry dates.
2. Batch/Location : Enter batch numbers and quantities and have the possibility to move between locations. You can track manufacturing dates or production dates and sell by dates or expiry dates.
3. Location : Just location management. Focuses on managing item locations in your shop, store, or warehouse. You can add locations (e.g., bin, aisle number, row) where you store stock items if needed.

Activation

In osFinancials5/TurboCASH5:

Go to the Setup ribbon tab, select Plugins → Stock plugins → Location-Serials-Batches . If this plugin is not listed under Plugins → Stock plugins, activate it via Tools → Activate plugins.



You will see the setup screen for the plugin : Set Activate to on and press Save.



You may add Locations (Bin, Isle number row) as the place where you keep the stock items in your shop, store, warehouse, if necessary.



If locations were added, remember to click on the Save button.

Close the Set of Books or restart osFinancials or TurboCASH!

Activate in Stock items - Location-Batches-Serial tab

Go to Stock items (on the Default ribbon tab). If you select any stock item, a new tab "*Location-Serials-Batches*" is added.



By default, the "*Location-Serials-Batches*" is set to Off (not activated) for all stock items.

You can select 3 different types of tracking.

1. Serial : Allows for tracking individual serial numbers, suitable for items like phones or computers. You can track manufacturing dates or production dates and sell by dates or expiry dates.

2. Batch/Location : Enter batch numbers and quantities and have the possibility to move between

locations. You can track manufacturing dates or production dates and sell by dates or expiry dates.

3. Location : Just location management. Focuses on managing item locations in your shop, store, or warehouse. You can add locations (e.g., bin, aisle number, row) where you store stock items if needed.

Press Add to add a new record to enter products you already have like a start position. Do not enter products you still are going to purchase and enter in documents.

Filter - Once purchase documents and sales documents have been processed, the options is as follows:

- All: This will list all the available Serials, Batches/Locations or Locations which is Enabled (available for selling) as well as Disabled (already sold).
- Enabled: This will list the available Serials, Batches/Locations or Locations which is available for selling.This would usually be the processed purchase documents.
- Disabled: This will list the Serials, Batches/Locations or Locations which is already sold. This would usually be the processed sales documents. This would be listed in a RED font or row background colour.

Serial

Serial option - Fast mode on (default view)



Serial option - Fast mode off



Serial option - Add



Batch / location

Also you can move and correct quantities here, if the need arises.

Batch / location option - Fast mode on (default view)



Batch / location - Fast mode off



Batch / location - Add



The quantities adjusted will reflect on then quantity on hand for the stock item after saving the stock item.

Location

Location option - Fast mode on (default view)



Location - Fast mode off



Location - Add



Processing documents

Purchases

If you do a purchase you can enter new batches or serials after selecting the product.

The number of items (products) with serial numbers will automatically update the quantities in the document lines field.





If you enter serial numbers in the From and To fields, and you click on the Add all button, a similar confirmation message will be displayed.

> "Continue action Add 5 Serial ?"

A similar lookup screen will be displayed for serial input when processing supplier returns.

Sales

At sales you can select from the list of locations serials and batches of the product selected.





A similar lookup screen will be displayed for serial input when processing credit notes.

Printing documents

The serial numbers will print on Delivery notes, Invoices, Credit notes, Delivery notes, Purchases and Supplier returns.



Search for Serial numbers

On the Default ribbon, select Search.



Enter the serial number, etc. in the Search for field. In this example, only the first (prefix) of the serial numbers, is entered in the "*Search for:*" field.

If a document number is prefixed with "*ST*" followed by 5 numeric digits, as in this example, "*ST00002*", it is a posted document ("*Stock*" document type) generated when you save a stock item as an "*Adjustment*" after a serial, batch or location quantities is changed.



The description you have entered in the "*Change remark*" screen will be displayed in the "*Description*" column of the Document groups tab and in the "*Reference*" column of the Transactions tab.

Type

- Document - The document details will list all documents matching your search criteria. If you double-click on it (or right-click and select Show details option on the context menu), you may print the selected document.



- Stock - The Stock items matching your search criteria will be listed. If you double-click on it (or right-click and select Show details option on the context menu), the selected Stock item form will be opened.



By default, only the "*Enabled*" items will be listed on the "*Location-Serials-Batches*" tab. You may click on the "*All*" filter option to view all items.

By default, only the "*fastmode*" is selected. To view more details, remove the tick in the "*fastmode*" tick box.

If any documents is not posted, these will be listed in the "*Search - Investigator*" search results.

Reports

On the Reports ribbon, select Reports → Plugins → Locations-Batches-Serials.



On hand report

The "*Location-Serials-Batches - On hand*" report lists those serials or batches which is still available to sell to debtors (customers / clients)..



Stock movement report

The "*Location-Serials-Batches - Stock Movement*" report is a valuable tool for tracking the movement of serials or batches of products in your inventory.



Specifically, this report lists the serials or batches that have been purchased from creditors (suppliers or vendors) and subsequently sold to debtors (customers or clients). Here's how this report can be helpful:

1. Inventory Tracking: The report provides a comprehensive overview of the movement of specific products, including their serials or batches. It allows you to see which items have been acquired from suppliers and then sold to customers.
2. Transaction History: You can view the complete transaction history for each product, including purchase dates, supplier information, sale dates, and customer details.
3. Stock Accuracy: By tracking the flow of products from suppliers to customers, you can ensure the accuracy of your inventory records. This helps prevent overstocking or under-stocking of items.
4. Quality Control: The report helps in quality control by allowing you to trace products back to their source. If there are issues with product quality or recalls, you can quickly identify affected items.
5. Order Fulfilment: It aids in order fulfilment by verifying that you have the necessary stock on hand to

meet customer demands.

6. Supplier Performance: You can assess the performance of your suppliers by tracking the movement of their products. This information can be useful for supplier evaluations and negotiations.
7. Customer Service: When customers inquire about specific products or orders, you can use the report to provide accurate and detailed information about the products they purchased.
8. Returns and Exchanges: If customers need to return or exchange products, you can use the report to identify the exact serials or batches that were sold to them, making the process more efficient.
9. Accounting and Financial Reporting: The report provides data that can be useful for accounting purposes, including tracking the cost of goods sold (COGS) and calculating profit margins.

Overall, the "*Location-Serials-Batches - Stock Movement*" report enhances your ability to manage inventory, track product history, and provide better customer service by offering detailed insights into the movement of products from suppliers to customers.

Warranty and Guarantee Management

the "*Serial Tracking*" feature is essential for keeping track of individual serial numbers for items like phones or computers. Here's why it's important and how it can support warranty and guarantee management:

Purchase and Supplier Returns:

- When you purchase products from suppliers, each item can have a unique serial number associated with it.
- Serial tracking allows you to record which specific items you received from suppliers and when.
- If you need to return products to the supplier for any reason, you can accurately identify and track the items using their serial numbers.

Sales and Customer Returns:

- When selling products to customers, you can associate a serial number with each item sold.
- This helps you keep a record of which product was sold to which customer and when.
- If customers need to return items due to warranty claims or defects, you can easily identify the specific product using its serial number.

Warranty and Guarantee Management:

- Serial tracking is instrumental in managing warranties and guarantees effectively.
- You can associate warranty or guarantee information with each product based on its serial number.

- This includes details such as the warranty period, terms and conditions, and contact information for warranty support.
- When customers request warranty service or have issues with a product, you can quickly access the warranty details associated with the serial number and provide the necessary support.

By using the "Serial Tracking" feature, businesses can maintain a detailed and organized record of individual products throughout their life-cycle, from purchase to sale and potential returns. This not only enhances inventory management but also streamlines warranty and guarantee processes, improving customer satisfaction and operational efficiency.

Bought from supplier

The "*Location-Serials-Batches - Batch bought from supplier*" report lists those serials or batches which is purchased from creditors (suppliers / vendors).



The "*Location-Serials-Batches - Batch Bought from Supplier*" report is a specific type of inventory report that lists the serials or batches of products that have been purchased from creditors (suppliers or vendors). This report serves several important purposes:

1. Purchase Tracking: It provides a detailed record of the batches or serials acquired from suppliers. This information helps in tracking the products you have received from different suppliers.
2. Supplier Relations: By maintaining a record of batches bought from suppliers, you can assess the performance and reliability of your suppliers. This data can be useful in supplier negotiations and evaluations.
3. Quality Control: The report helps in monitoring the quality of products received from suppliers. If there are issues with a specific batch or serial, you can identify it through this report.
4. Inventory Accuracy: It contributes to the accuracy of your inventory records. By knowing which batches were received from suppliers, you can manage your stock levels effectively.
5. Accounting and Cost Analysis: The report assists in cost analysis and financial reporting. You can calculate the cost of goods sold (COGS) by referencing the batches bought from suppliers, which is essential for accurate financial statements.
6. Product Traceability: If there are recalls or safety concerns related to specific batches of products, you can use this report to trace back to the source and identify affected items.
7. Reorder Management: It helps in identifying when specific batches need to be reordered from suppliers based on sales trends and inventory levels.
8. Documentation: When dealing with regulatory requirements or audits, having a clear record of batches bought from suppliers is essential for compliance and documentation purposes.

In summary, the "Location-Serials-Batches - Batch Bought from Supplier" report is a valuable tool for businesses that rely on batch or serial tracking to manage their inventory effectively, assess supplier performance, and maintain accurate financial records. It provides transparency and traceability in your supply chain processes.

Sold to customer

The "*Location-Serials-Batches - Batch sold to customer*" report lists those serials or batches which is sold to debtors (customers / clients).



The "*Location-Serials-Batches - Batch Sold to Customer*" report is a valuable inventory management tool that lists the serials or batches of products that have been sold to debtors, including customers or clients. This report offers several important benefits:

1. Sales Tracking: The report provides a comprehensive record of the batches or serials that have been sold to customers. This information helps you track the sales history of specific products.
2. Customer Service: When customers have inquiries about their purchased items, returns, or warranty claims, this report enables you to quickly and accurately identify the exact serials or batches associated with their transactions. It enhances customer service by providing detailed information.
3. Inventory Accuracy: It contributes to maintaining accurate inventory records. By knowing which batches have been sold, you can keep track of your remaining stock and plan for restocking when necessary.
4. Quality Control: The report helps in quality control by allowing you to trace products back to specific batches. If there are quality issues or recalls, you can identify affected items through this report.
5. Returns and Exchanges: When customers need to return or exchange products, you can use the report to verify which serials or batches were sold to them, streamlining the return process.
6. Warranty and Support: For products with warranties or guarantees, you can use the report to confirm warranty coverage for specific items based on their serials or batches.
7. Accounting and Financial Reporting : The report is useful for accounting purposes, including tracking

the revenue generated from the sale of specific batches and calculating profit margins.

8. Product Traceability: If there are regulatory compliance requirements or safety concerns related to specific batches, this report helps you trace the products back to their source and identify affected items.

9. Marketing and Sales Analysis: By understanding which batches or serials are selling well, you can make informed decisions regarding marketing strategies and product promotions.

Overall, the "Location-Serials-Batches - Batch Sold to Customer" report enhances your ability to manage inventory, provide excellent customer service, ensure product quality, and meet regulatory requirements. It offers transparency and traceability in your sales processes and supports various aspects of your business operations.

Outdated batch

The "*Location-Serials-Batches - Outdated batch*" report lists only those serials or batches which is still on hand, but which is past the maximum sales date.



The "*Location-Serials-Batches - Outdated Batch*" report plays a crucial role in helping businesses manage expired items effectively. Here's how this report can be beneficial in managing expired items:

1. Identifying Expired Items:
    - The report identifies and lists all serials or batches that have passed their maximum sales date.
    - It provides a clear and concise overview of which products are no longer fit for sale due to expiration.
2. Preventing Sale of Expired Items:
    - By having a list of expired items at hand, businesses can prevent the accidental sale of

products that are past their sell-by or expiry dates.

- This helps maintain product quality and ensures that customers receive fresh and safe products.

3. Reducing Wastage:
   - Businesses can take proactive measures to address expired items, such as removing them from shelves or disposing of them appropriately.
   - This reduces the risk of keeping expired products in inventory, which can lead to financial losses.
4. Inventory Management:
   - The report aids in efficient inventory management by highlighting items that need attention.
   - It allows businesses to make informed decisions regarding restocking, discounts, or disposal of expired items.
5. Compliance and Liability:
   - For items with legal or regulatory requirements, like food or pharmaceuticals, tracking expiration dates is essential to comply with safety standards.
   - Having an accurate record of expired items can also protect businesses from liability issues.
6. Customer Satisfaction:
   - Avoiding the sale of expired items enhances customer satisfaction and trust in your business.
   - It demonstrates your commitment to providing fresh and safe products to customers.
7. Cost Savings:
   - Efficiently managing expired items reduces financial losses associated with wastage.
   - Businesses can potentially plan better for purchasing and stocking items to minimize overstocking of perishable goods.

In summary, the "*Location-Serials-Batches - Outdated Batch*" report is a valuable tool for businesses to proactively manage and mitigate the risks associated with expired products. It supports compliance, reduces wastage, and ensures that customers receive quality goods, ultimately contributing to the overall success of the business.

Common practice - Specific steps to dispose of these items and to returns to suppliers

The specific steps for disposing of or returning expired items identified on the "*Location-Serials-Batches -*

Outdated Batch" report may vary depending on your business processes, the type of products involved, and any applicable regulations or agreements with suppliers. However, here are some common practices that you can consider when dealing with expired items:

For Disposal:

1. Separation: Physically separate expired items from non-expired inventory to avoid accidental sale.
2. Record: Document the details of the expired items, including their serial or batch numbers and quantities.
3. Dispose Properly: Dispose of the expired items according to local regulations and environmental guidelines. This may involve recycling, donating non-perishable items if possible, or disposing of perishables in an environmentally responsible manner.
4. Adjust Inventory: Update your inventory management system to reflect the disposal of expired items. This ensures accurate tracking of your remaining stock.
5. Review and Adjust: Analyse why these items expired. Adjust your inventory management practices or purchasing strategies to minimize future wastage.

For Returns to Suppliers:

1. Verification: Ensure that the items marked as expired are indeed within the warranty or return period specified by the supplier. Check your purchase records and supplier agreements.
2. Contact Supplier: Reach out to the supplier or vendor from whom you purchased the items. Inform them of the expired items and request return instructions.
3. Return Authorization: Obtain a return authorization or an RMA (Return Merchandise Authorization) from the supplier if required.
4. Packaging: Properly package the expired items for return. Include any required documentation, such as the RMA, along with a clear explanation of why the items are being returned.
5. Shipping: Arrange for the return shipment, following the supplier's preferred shipping method or instructions.
6. Tracking: Keep a record of the return shipment's tracking information for reference.
7. Credit or Replacement: Once the supplier receives and processes the returned items, they may offer a credit or replacement, depending on their policies and the condition of the items.
8. Inventory Update: Update your inventory management system to reflect the returned items and any credit received.

It's essential to have clear internal procedures for handling expired items and returns to suppliers.

Communication with suppliers is key, as their specific return policies and procedures may vary. Additionally, maintaining accurate records of these transactions is crucial for accountability and compliance.

Importance to check the expiry dates

Checking the expiry dates of products when receiving them from suppliers is a crucial part of effective inventory management, especially if your business deals with perishable goods or products with limited shelf life. Here are some key reasons why it's essential:

1. Quality Assurance: Verifying expiry dates ensures that the products you receive are fresh and safe for your customers. It helps maintain the quality and safety of the items you sell.
2. Minimize Waste: By being aware of expiry dates, you can avoid receiving products that are close to or have already passed their expiration date. This reduces the risk of inventory becoming obsolete or being wasted.
3. Compliance: Depending on your industry, there may be regulatory requirements related to handling and selling products within their specified shelf life. Compliance with these regulations is critical to avoid legal issues.
4. Customer Satisfaction: Customers expect to purchase products with reasonable shelf life. Selling expired items can lead to dissatisfied customers, returns, and damage to your business's reputation.
5. Inventory Turnover: Understanding expiry dates helps you manage your inventory turnover effectively. You can prioritize the sale of items that are closer to expiration to minimize the risk of unsold stock.

Managing Expiry Dates

To effectively manage expiry dates when receiving products from suppliers, consider the following practices:

1. Inspect Shipments: Inspect incoming shipments carefully and check the expiry dates on each product. Ensure that the products received have sufficient shelf life for your expected sales.
2. First-In-First-Out (FIFO): Implement a FIFO inventory system, where you sell the oldest items first. This ensures that products with shorter shelf lives are sold before newer ones.
3. Communication with Suppliers: Maintain open communication with your suppliers. Make them aware of your requirements regarding product shelf life and expectations for fresh inventory.
4. Storage Practices: Store products with shorter shelf lives in a way that ensures they are used or sold before items with longer shelf lives.

5. Inventory Tracking: Use an inventory management system that tracks expiry dates and provides alerts or reports on items approaching their expiry.
6. Regular Audits: Conduct regular audits of your inventory to identify and address any items nearing expiration.
7. Training: Train your staff to be vigilant about checking expiry dates during the receiving process and when restocking shelves.

By incorporating these practices into your inventory management processes, you can minimize waste, provide high-quality products to your customers, and maintain efficient inventory turnover. This, in turn, contributes to the success and reputation of your business.

Created with the Standard Edition of HelpNDoc: Effortlessly upgrade your WinHelp HLP help files to CHM with HelpNDoc

Stock check

Stock check / Stock correction plugin

Stock check / Stock correction - Manual - Shop - Licence: Once-off -

Translations : Translations outstanding

This "*Stock correction*" plugin allows users to perform inventory counts conveniently from various devices such as PCs, handheld PCs, or smartphones. This can be done either through Remote Desktop (RDP) or Terminal Services.

Upon pressing a Generate document button, the plugin automatically generates a credit note with the incorrect numbers. This feature helps in documenting discrepancies in stock counts. After the credit note is generated, the plugin proceeds to correct the stock numbers based on the inventory count performed. This ensures that the inventory records are accurate and up to date.

New Android Stock Count.

Android Stock Count - Manual - Shop - Licence: Once-off -

The "*New Android Stock Count*" at an extra cost of 200,00 euros, excluding tax, allows users to connect to

the plugin via their local network using an Android device. The Android version of the plugin supports barcode scanning functionality. Users can use a Bluetooth-enabled barcode scanner to scan barcodes of the stock items, which facilitates faster and more accurate stock counting.


05:09
123
Barcode
DRILBOOR Drilboor
Huidig
1.0 / 1.0
Geteld
2
Opslaan
- + . 1 2 3
* / , 4 5 6 Gereed
( ) = 7 8 9
* 0 #

Activation

To activate the StockCheck plugin:

1. On the Setup ribbon, go to Plugins → Stock plugins → StockCheck. If this plugin is not listed under Plugins → Stock plugins, activate it via Tools → Activate plugins.



2. In the Setup StockCheck, select On and click Save. Reopen the "*Setup stockcheck*" screen to change additional settings.

3. If "*Activate for this user*" is selected,the StockCheck plugin will automatically launch when you reopen the Set of Books. To disable this and manually launch the StckCheck plugin, uncheck the "*Activate for this user*" field. You can then manually launch the StockCheck plugin from the StockCheck icon on the Default ribbon.

4. Click Save. Reopen your Set of Books for these settings to take effect.

Default ribbon icon

Once you have reopened your Set of Books, the "*Voorraad controle*" StockCheck icon will be available on the Default ribbon.

- If "Activate for this user" is selected in the Setup StockCheck, the StockCheck plugin will

automatically launch when you open your Set of Books.

- If "Activate for this user" is not selected, or if you have closed the StockCheck plugin, you can manually launch it from the "*Voorraad controle*" StockCheck icon on the Default ribbon.



Stock check

List tab

Once you have accessed the StockCheck plugin, the List tab will be displayed.

-

· Click the Search button to list all your stock items (products). You may filter and search by options such as Reporting Group 1 (Stock Group 1) or Reporting Group 2 (Stock Group 2). For example, if you select "Powertools" as Reporting Group 1, the list will focus specifically on items linked to "Powertools."



- Once your stock items are listed, you may use the following columns to sort and filter your list of stock items:
  - Code: Stock code
  - Barcode: Barcode of the stock item
  - Description: Stock item description
  - Extra Description: Additional description of the stock item
  - Inactive: Status of the stock item (active or inactive)
  - Supplier Code: Supplier's stock code (if set for the default supplier)
  - ID: Stock item ID (record number)
  - Unit: Unit description for purchase and sale
- Filter: You may choose to filter your items by Uncounted or Counted.
- For the selected stock item, the current quantity is displayed. In the Counted Quantity field, enter the quantity of the physical stock count. Click OK → Next to move to the next stock item.
- For each counted stock item, the Date of Count will include the timestamp of when the stock count was done.

- View/Edit button: To view a stock item, click the View/Edit button. This will open the Stock Item form with the Ledger tab in a separate window, allowing you to view and edit details if necessary.

Finally, once you have finished your stock count, you may proceed to process the corrections on the Correctie (Corrections) tab.

Correctie (Corrections) tab

Once you have finished your stock count on the List tab, you may proceed to process the corrections on the Correctie (Corrections) tab.

- To generate credit notes for your stock count, click the Genereer document (Generate document) button.
- The "*Debtor accounts*" screen will appear, allowing you to choose an account. If no account exists, you may create a new account, for example, a Stock Count account.
- The Debtor Accounts screen will appear
- A log will display the list of stock item codes and quantities ordered, followed by the message "*Correction credit note Ready!*"



Example text for generated document:

```
Stock code 3DRILL diverence -6
Stock code 3COMP diverence 1
Correction credit note Ready!
```

Delete Stock Checks

- To clear the stock check table, click the Tabel schonen (Clear table) button.

- The following confirmation message will be displayed:

  "Delete all stock checks? Warning this cannot be reversed!"

- If you are sure, click Yes.

Accessing generated Credit notes

Once the credit notes are generated:

- Navigate to Documents on the Default ribbon.
- Select "*Credit note*" as the document type. The generated credit notes will be listed as "*Unposted*" in the Documents grid.

Editing credit notes

You may need to edit the credit notes and change the details where necessary. Pay special attention to the following:



Document Header:

- Your Reference: "*Correction*" will be displayed.

- Document Group 1 / Document Group 2: Select the appropriate document groups.
- Salesperson: Select the salesperson or the person who handled the stock count.
- Date: The system date on which the credit note was generated.
- Message: Enter up to 3 lines if necessary.

Tip: If you need to change the Document Group 1 / Document Group 2, or the Salesperson, you may use the context menu on the Documents grid for the "*Credit note*" document type.

Document Lines:

- Stock Item: The stock code and stock item description will be displayed as "*Stock count correction*".
- Order / Ship: The quantity is the difference between the current quantity and the counted quantity. If the counted quantity is lower than the current quantity, the quantity will be negative (prefixed by a minus sign).
- Remarks and Comments: Add any remarks and comments if necessary.
- Discount: Add any discount if necessary.

Once you are satisfied with your generated credit notes, you may post or update these credit notes to the ledger.

Note: If the "*Auto-post document on print*" setting on the Documents setup in the Setup menu (accessible via the Setup ribbon) is not activated, or if you have not yet printed the document, you will need to manually post the Stock in and Stock out documents.

To Access the StockCheck Correction Documents

In addition to the filter and search options on the Documents grid for the credit note document type, you can also locate these credit note documents using the following options:



- Stock item form → Document groups tab: Use the context menu "*Open document*".
- Stock item form → Transactions tab: Use the context menu "*Open document*".

Printing options

Printing Options

In addition to the print options on the Documents grid for the credit note document type, you can also print documents using the following options:

- Debtor Form: Documents tab. Double-click. You may select a layout file. Note : If the document layout file "*Layout file*" is selected, it may will print the Stock code but the stock description as "*Stock count correction*". To include the Stock code, select the "*Document layout (15 code)*" layout file.
- Stock Item Form:
  - Document Groups tab: Double-click the document.
  - Transactions tab: Double-click the document.
- Search (Default ribbon): Use the central search to find the reference ("*Correction*") or description (e.g., "*Stock count correction*"). If you use prefixes for documents, such as "CR" for credit notes, it will be easier to locate these credit notes. Double-click on the document. The document type will be indicated as "*Credit note Details*".

StockCheck - Credit note transactions

When credit notes are generated using the *StockCount / Stock correction* plugin, an unposted credit note is created. When these credit notes are posted or updated to the ledger, the cost of sales journal will generate transactions. You have the following options to view these transactions:

Batch entry (Default ribbon)

1. On the Default ribbon, select Batch Entry or press F2.
2. Open the Cost of Sales journal and click on the Posted Batches tab.



3. In the Posted Batches - Batch entry tab, select the batch and double-click it. Note: The default alias batch name is "COS*DOC*". The list of transactions is displayed in the Details tab.



4. On the Details tab, the reference will list the document number of the credit note, and the description of the transaction will be "**COST OF SALES / Correction*".
5. To print the "Batch Type - Posted Batch" report for the credit note transactions, click the Print button.

Example of the "Batch type - Posted batch" Report for Credit Note Transactions:



Debtor account - Documents tab

On the Documents tab of the debtor account, select the credit note and right-click to select "*Show transactions*" from the context menu.



The transactions will be listed in the "*Transactions*" screen, which is similar to the Posted batches - Batch entry tab form the Batch entry option.



Note : Print button will produce a *"No data to print!"* error. To print the "*Batch type - Posted batch*" report for these credit note transactions, navigate to the Batch Entry or press F2. and open the Cost of Sales

journal and click on the Posted Batches tab.

T-Account viewer

On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 1 / 2. Generate a Trial balance or an Income statement. Select the Cost of sales account or the Stock control account and right-click to select "*Show details*" from the context menu. The T-account viewer will list all posted transactions for the selected account.

Select the credit note with a description "*COST OF SALES / Correction*" and double click on the Batch id generated by osFinancials5/TurboCASH5.



Click the Print button to print the transactions in the T-Account viewer.



Bulkcheck tab

To be advised.

The Post difference button, generate blank credit notes with no adjustments or corrections on the unposted credit notes.



Delete line - No Confirmation message



Confirmation message

> There ao check active do you want to see this? No wil make a new check and all current check data will be lost!

Post difference log entry on Correctie tab

> Correction credit note Done!

Confirmation message Post difference button.

> Are you sure you want to post the new inventory data?

Post difference button - Access violation error on Bulk check tab

This is replicated by typing text, e.g. "*Drill*" and enter. The when click in the Check button or the Post

difference button the Access violation error occurs.

> violation of FOREIGN KEY constraint "FK_DOCLINE_STOCK" on table "DOCLINE"
> Foreign key reference target does not exist

The Post difference button, generate blank credit notes with no adjustments or corrections on the unposted credit notes.



Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

QuickOrder

Quick Order - Manual - Shop - Licence: Once-off -

Translations : Translations outstanding

Simplify your product ordering process with our "*Quick Order*" plugin. This plugin offers a quick and convenient method for ordering products from your PC or using a handheld PC or smart phone (through Remote Desktop / Terminal Services or RDP).

- You walk with a handheld through your warehouse, and scan or selected the product to order while standing next to the shelf.

- You see immediately actual stock numbers so that a good decision of the quantity to order can be made.
- After pressing a button it creates an order with the specified numbers.
- After which only a few clicks of the mouse will break down the order by vendor.

Optimize your ordering workflow with the "*Quick Order*" plugin, providing you with a seamless and efficient solution for managing your product orders.

Activation

To activate the QuickOrder plugin:

1. On the Setup ribbon, select Plugins → Stock plugins → QuickOrder. If this plugin is not listed under Plugins → Stock plugins, activate it via Tools → Activate plugins.

2. On the Setup OuickOrder select On and click Save. Reopen the "*Setup QuickOrder*" screen to change additional settings.

3. The configure options, is as follows:

   a) Auto popup: By default, the QuickOrder screen launches when you reopen the Set of Books. To disable this and manually launch the QuickOrder screen, uncheck the "*Auto popup*" field. You

can then manually launch the QuickOrder plugin from the Quick order icon on the Default ribbon.

b) Just quickorder: If this option is not selected, the entire QuickOrder module (comprising three tabs: List, Generate documents, and Orders) will launch. If selected, only the Orders option will launch.

4. Click Save. Reopen your Set of Books for these settings to take effect.

Drop data

If there are no items ordered in the List tab, you have the option to drop the data in the "*QUICKORDER*" table.

To drop data:

1. On the Setup ribbon, select Plugins → Stock plugins → QuickOrder. On the "*Setup QuickOrder*" screen, click the Drop data button. A confirmation message will be displayed:

   "Are you sure you want to delete all data ?"

2. If you are absolutely sure, click Yes. Another confirmation message will be displayed:

   "Warning you are about to delete table QUICKORDER with 1 records realy continue? "

3. If you are still sure, click Yes.

NOTE: If the message indicates there are records (e.g., "1 record" as in the example), you may encounter an error message like:

"Unsuccessful metadata update.
Object QUICKORDER is in use."

To resolve this:

- First, delete the records in the List tab.
- Reopen your Set of Books.
- Once the Set of Books is reopened, you can proceed to drop the data (delete the "*QUICKORDER*" table).

Default ribbon icon

Once you have reopened your Set of Books, the Quick order icon will be available on the Default ribbon.

- If "*Auto popup*" is selected in the Setup QuickOrder, the QuickOrder will automatically launch when you open your Set of Books.
- If "*Auto popup*" is not selected, or if you have closed the QuickOrder plugin, you can manually launch it from the Quick order icon on the Default ribbon.



QuickOrder

When the Quick order plugin is initiated, and the "*Just quickorder*" option on the "*Setup QuickOrder*" screen is not selected, the entire QuickOrder module (comprising three tabs: List, Generate documents, and Orders) will be available.

List tab

- *Click the Search button to list all your stock items (products). You may filter and search by options such as Reporting Group 1 (Stock Group 1) or Reporting Group 2 (Stock Group 2). For example, if you select "Powertools" as Reporting Group 1, the list will focus specifically on items linked to "Powertools."*



- The details for each stock item will be listed in the following columns:
  - Code - Stock code
  - Quantity on hand (Aantal voorraad) - The current quantity of stock items available
  - Reorder at (Trigger aantal) - The quantity at which the item should be reordered
  - Reorder level (Aantal aanvullen tot) - The replenish quantity
  - Under stock (Onder voorraad)
  - Quantity of stock calculated (Aantal voorraad berekend) -

- Barcode - Barcode of the stock item
- Description - Stock item description
- Extra description - Additional description of the stock item
- Inactive - Status of the stock item (active or inactive)
- Supplier code - Supplier's stock code (if set for the default supplier). Note: If no supplier code exists in this column, it may generate the order to an "Empty account". You may click on the Bekijk (View) button to add the preferred supplier and the supplier's stock code on the Stock form.
- id - Stock item ID (record number)
- Unit - Unit description for purchase and sale

- To order the reorder quantity to the "*Reorder level*", select an item from the list and click the Bestel tot nivo (Order to level) button.
- To increment the order quantity, use the Bestel +1 (Order +1), Bestel +5 (Order +5), or Bestel +10 (Order +10) buttons.
- Clicking on the order buttons will add the stock items to the bottom half of the QuickOrder screen, with details in the following columns:
  - Code - Stock code
  - Quantity (Aantal) - Quantity of stock calculated, updated by ordered quantities
  - Date (Datum) - System date and time stamp
  - Total stock after ordering (Totaal voorraad na bestellen) - Quantities on order

Adding QuickOrder items and quantities on the QuickOrder - List tab will add a Voorraadtelling (StockCount) tab as a fourth tab to the QuickOrder plugin.

Delete an item from the list

Click the Verwijder (Delete) button. A confirmation message will be displayed:

> "Weet u het zeker? "

If you are sure, click Yes.

View Stock Item form

To view a stock item, click the Bekijk (View) button. This will open the Stock Item form with the Ledger tab

in a separate window, allowing you to view and edit details if necessary.

Generate tab (Aanmaken tab)

Once you are satisfied with the quantities to order on the List tab, navigate to the Generate (Aanmaken) tab.

Click the Genereer dokument(en) (Generate document(s)) button. A log will display the list of stock item codes and quantities ordered, followed by "*Orders generated!*"



Example text for generated document:

voorraad code 3DRILL	aantal 14 document A-ONE Suppliers
voorraad code 3COMP	aantal 16 document Empty account
Bestelling aangemaakt!	

Orders will be generated for the default supplier as set in the "*Preferred supplier1*" field of the Stock item form. Note: If no "*Preferred supplier1*" is set, the order will be generated to an "*Empty account*".

Accessing generated orders

Once the orders are generated, navigate to Documents on the Default ribbon and select "*Order*" as the document type. These generated orders will be listed as "*Unposted*" in the Documents grid.

Editing orders

You may need to edit the orders and change the details where necessary.



Special attention may be needed for the following:

Document Header:

- Your reference: The supplier's account name will be displayed.
- Document group 1 / Document group 2: Select the appropriate document groups.
- Salesperson: Select the salesperson or the person who handles the orders.
- Date: The system date on which the order was generated.
- Message: Enter up to 3 lines if necessary.

Tip: If you need to change the Document Group 1 / Document Group 2 , or the Salesperson, you may use the context menu on the Documents grid for the "*Ordeer*" document type.

Document Lines:

- The supplier's stock code will precede the stock code (in brackets), and the quantities and tax will already be calculated based on the quantities ordered on the QuickOrder List tab. You may edit these quantities if necessary or add additional items.
- Remarks and Comments: Add any remarks and comments if necessary.
- Discount: Add any discount if necessary.

Once you are satisfied with your generated orders, you may print and send these orders to your suppliers. When the supplier delivers these items, you can confirm these orders and convert them to a purchase.

Changing account

If an order is generated to an "*Empty account*":

- Go to Documents → Change account in the context menu and select the appropriate supplier account.
- To prevent future occurrences of orders being generated to Empty accounts, navigate to the Stock item form, choose a default supplier in the "*Preferred supplier1*" field, and add a supplier stock code.



The "*Reference*" column for these orders, which did not contain a default supplier ("*Preferred supplier1*") generated by the QuickOrder plugin, will be indicated as "*Empty account*." To change this "*Empty account*" reference, edit the "*Your reference*" field on the order document entry screen.

If the "*Your reference*" field is left as "*Empty account*", it will reflect in all relevant reports, such as Reports → Stock → Stock in/out - Documents, in the Documents reference as "*Empty account*".

Preferred supplier 1 (Default supplier 1) setting

To prevent future occurrences of orders being generated to Empty accounts, navigate to the Stock item form, choose a default supplier in the "*Preferred supplier1*" field, and add a supplier stock code.



Voorraadtelling (StockCount) tab

Adding QuickOrder items and quantities on the QuickOrder - List tab will add a Voorraadtelling (StockCount) tab as a fourth tab to the QuickOrder plugin.



The Voorraadtelling (StockCount) tab will list the stock items with opening balances and closing balances between two dates. These dates correspond to the start and end dates of your financial year:

- Openingbalans datum (Opening balance date)
- Eind balans datum (Closing balance date)

The tab also includes the following two buttons:

- Initializeer (Initialize)
- Corrigeer (Correction)

The Voorraadtelling (StockCount) tab will list the stock items in the following columns:

- Artikel (Item)
- Aantal op startdatum (Quantity on start date)
- Aantal op einddatum (Quantity on end date)
- Huidig aantal (Current quantity)

Changing the stock quantity in the Aantal op einddatum (Quantity on end date) column and clicking the Corrigeer (Correct) button updates the quantity in the Aantal op einddatum (Quantity on end date) column.

This action will create a posted document with "*Actief-Q-cor*" in the "*Your reference*" field in the document entry screen. The description in the document lines will automatically be generated as "*Actief-Q-cor*" for the stock item for which the quantity was changed.

The account will be an "*Empty account*" as this document correction is only meant to change the stock quantities and is not associated with a specific supplier or creditor account.

The document number will automatically be generated and consists of 7 digits, for example, "ST00001" the first two digits prefixed by "ST" and the document type will be "Stock-"

These stock correction documents will reflect in all relevant reports, such as Reports → Stock → Stock In/Out. in the Documents *generated with the QuickOeder Stock coumt tab will list te document number and the reference as* generated as "*Actief-Q-cor*".

To access the posted stock correction document:

- Stock item form - Document groups tab (context menu "Open document")
- Stock item form - Transactions tab (context menu "Open document")

To access print stock correction document:

- Stock item form - Document groups tab (double-click)
- Stock item form - Transactions tab (double-click)
- Search - Central search on Default ribbon. Find the reference, document number or prefix and double-click on the document (Document type) The document type will be indicated as " *Sock out Details*".

Voorraadtelling (StockCount) tab - Corrections tab

Changing the stock quantity in the Aantal op einddatum (Quantity on end date) column and clicking the Corrigeer (Correct) button updates the quantity in the Aantal op einddatum (Quantity on end date) column.

This action will create a posted document with "*Actief-Q-cor*" in the "*Your reference*" field in the document entry screen. The description in the document lines will automatically be generated as "*Actief-Q-cor*" for the stock item for which the quantity was changed. The account will be an " *Empty account*" as this document correction is only meant to change the stock quantities and is not associated with a specific supplier or creditor account.

The document number will be automatically generated and consists of 7 digits, prefixed with "*ST*" (e.g., "*ST00001*"), and the document type will be "*Stock-*".

These stock correction documents will reflect in all relevant reports, such as Reports → Stock → Stock In/Out. Documents generated with the QuickOrder StockCount tab will list the document number and the reference as "*Actief-Q-cor*".

The "*Actief-Q-cor*" reference or stock description in document entry screens, specific columns in certain tabs of the stock item, document layout files, and reports indicates that this is generated by the QuickOrder plugin for corrections of stock quantities.

To Access the Posted Stock Correction Document:

- Stock item form → Document groups tab: Use the context menu "*Open document*".
- Stock item form → Transactions tab: Use the context menu "*Open document*".



To Print the Stock Correction Document:

- Stock item form → Document groups tab: Double-click the document.
- Stock item form → Transactions tab: Double-click the document.
- Search (Default ribbon): On the central search, find the reference ("*Actief-Q-cor*"), document number, or prefix ("*ST*"), and double-click on the document. The document type will be indicated as "*Stock out Details*".



Error - Closed Dataset

ZQGenSearch: Cannot perform this operation on a closed dataset error is replicated when clicking on the Voorraadtelling tab.



Orders tab

When the Quick order plugin is initiated, and the "*Just quickorder*" option on the "*Setup QuickOrder*" screen is not selected, the entire QuickOrder module (comprising three tabs: List, Generate documents, and Orders) will be available. You may click on the Orders tab.

When the Quick order plugin is initiated, and the "*Just quickorder*" option on the "*Setup QuickOrder*" screen is selected, only the Orders component of the entire QuickOrder plugin module will be available.



Nuwe - Selecteer rekening (lookup titlebar caption)

Type action

- Move 21022
- Copy 3293 / 21010

Dubbleclick = action

Edit qty and price

Columns

- (All) 20055
- (Sorted)
- WDOCID

- Factuur btw
- Afgedrukt 2964

Created with the Standard Edition of HelpNDoc: Add an Extra Layer of Security to Your PDFs with Encryption

Plugins menu - Tools

AndroidConnector

AndroidConnector - Install manual - App manual - Shop - Licence: Once-off -

Connect your Android device seamlessly with your osFinancials5/TurboCASH5 Set of Books using our AndroidConnector. With a one-time licence, this adaptor facilitates a smooth connection between our Android software and your financial records.

Key Features:

- Enable connection between Android devices and osFinancials5/TurboCASH5
- Streamline data exchange between platforms

Simplify your data management and enhance connectivity across your devices with AndroidConnector.

DYNADBREG

This DYNADBREG consists of several Plug-in programs that are purchased and activated individually from our Webshop.

FileANDXMLExportImport

FileandXML Export Import - Manual - Shop - Licence: Once-off -

Effortlessly manage file and XML imports with our FileandXML Export Import Plugin. With a one-time licence, this plugin provides an editor mode where you can create custom file and XML imports tailored to your specific needs.

Key Features:

- Create custom file and XML imports
- Ideal for managing price lists with suppliers and other data imports
- Option for personalized import creation services by our team

Streamline your import processes and customise data imports according to your requirements with FileandXML Export Import Plugin.

Export / Import

Export / Import - Manual - Shop - Licence: Once-off -

Efficiently manage your data transfers with our Export/Import Plugin. With a one-time licence, this plugin enables seamless export and import operations to platforms like Vtiger and others.

Key Features:

- Export data to platforms like Vtiger
- Import data from various sources
- Streamline data transfer processes

Simplify your data management and ensure smooth integration with external platforms using the Export/Import Plugin.

HandyTools

HandyTools - Licence : Free.

Caution: Make backups of your Set of Books before use

Translations : Outstanding

Unlock advanced functionality with our HandyTools Plugin, available for free. Designed for advanced users, this plugin provides additional tools for enhanced functionality within your osFinancials5/TurboCASH5 software.

Key Features:

- Advanced tools for specialized tasks
- Free of charge
- Recommended for advanced users
- Caution: Make backups of your Set of Books before use

Advanced software capabilities with the HandyTools Plugin, but remember to proceed with caution and make backups to safeguard your data.

Register plugins

Register plugins - When you have purchased a plugin and you have received the registration code, you need to enter and add the codes to "*Register the plugins*"-screen.

Report designer

Reportman - Manual - Licence : Free.

Accessible from the Report designer icon on the Setup ribbon

Translations : Translations outstanding

Unlock the power of report generation and customization with our Report designer plugin, provided free of charge. Accessible from the Report designer icon on the Setup ribbon, this plugin empowers users to design and print reports and document layout files effortlessly. All reports and document layout files included in the osFinancials5/TurboCASH5 installation are designed with the powerful Report designer plugin.

Compatibility with Database Types:

The Report designer plugin seamlessly integrates with osFinancials5/TurboCASH5, allowing users to edit and write reports and document layout files across different database types. Whether your Set of Books in osFinancials5/TurboCASH5 relies on Firebird or MSSQL database types, the Reportman plugin ensures smooth functionality and compatibility.

Key Features:

- Powerful report generator and designer
- Customize existing reports or create your own
- Design document layout files for various sales and purchase documents
- Includes default layout files and reports in the osFinancials5/TurboCASH5 installation

Best Practices:

- Always make a copy of a report or layout file before editing. You can always fall back on the original report or layout if things go wrong.
- Rename your layouts or reports to prevent overwriting during reinstallation or during installation of osFinancials5/TurboCASH5 updates.

- Add your customised reports to the User reports menu

Documentation and Resources:

- osFinancials Help and Online documentation: Comprehensive detailed information provided in the "*Working with Reportman*" section of the osFinancials5/TurboCASH5 Help file and on the osFinancials website in English and Afrikaans.
- Official offline documentation: Navigate to the "...\plug_ins\reportman\doc" folder within your osFinancials5/TurboCASH5 installation directory. Open the index.html file located at ".../plug_ins/reportman/doc/index.html" in your web browser to access this resource.
- Official online documentation: For additional resources and information regarding the Report Manager, refer to the official online documentation available at https://reportman.sourceforge.io/. This online documentation offers comprehensive guidance and support for maximizing the functionality of the Report Manager.

Harness the capabilities of the Reportman Plugin to create tailored reports and document layouts while maintaining flexibility and control over your printing needs.

SQLBrowser

SQLBrowser - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Translations : Outstanding

The SQL Browser plugin in osFinancials empowers users with a robust tool for interacting with their data using Structured Query Language (SQL). Tailored for users familiar with SQL, this feature enables the execution of custom queries, effortless grouping, filtering, and sorting of results.
You can save their SQL Script files for future use and export data to various formats including XML (Extensible Markup Language), HTML (Hypertext Markup Language), Microsoft Excel, and Text File formats. Additionally, users can seamlessly export data to "*JSON*"-files and create a new table from a "*JSON*"-file, expanding the flexibility and capabilities of data management within osFinancials5/TurboCASH5.

Compatibility with Database Types

The SQL Browser plugin seamlessly integrates with any Set of Books utilizing either Firebird or MSSQL database types. Whether your organisation relies on Firebird or MSSQL for database management, the SQL Browser provides a unified platform for accessing and manipulating data.

This flexibility allows users to leverage the SQL Browser's powerful features across different database environments, ensuring consistent functionality and ease of use regardless of the underlying database technology.

Created with the Standard Edition of HelpNDoc: Elevate Your Documentation Process with HelpNDoc's Advanced Features

SQL Browser plugin

SQL Browser - Manual - Shop - Licence : Once-off - This program is licenced under a commercial licence. A nag screen will be displayed when this plugin is launched and will pop up with regular intervals.

SQL Browser is used to add cost and project groups and paper types after creating a new blank Set of Books from scratch:

- *Create Set of Books (Advanced) option for Firebird Database types*
- *Create Set of Books (Advanced) option for MSSQL Database types*

Introduction to the SQL Browser

The SQL Browser plugin in osFinancials5/TurboCASH5 provides users with a powerful tool to interact with their data using Structured Query Language (SQL). This feature is especially beneficial for users familiar with SQL and enables them to run custom queries, group, filter, and sort results effortlessly. Additionally, users can export data to "*JASON*"- files for further analysis or documentation purposes.

Compatibility with Database Types

The SQL Browser plugin is designed to seamlessly integrate with any Set of Books utilizing either Firebird or MSSQL database types. Whether your organization relies on Firebird or MSSQL for database management, the SQL Browser provides a unified platform for accessing and manipulating data.

This flexibility allows users to leverage the SQL Browser's powerful features across different database environments, ensuring consistent functionality and ease of use regardless of the underlying database technology.

Overview : Step-by-step guide on how to use the SQL Browser in osFinancials:

1. Accessing SQL Browser:
    - Navigate to the Setup ribbon and click on Plug-ins → Tools → SQLBrowser.
2. Selecting a Table:
    - Once in the SQL Browser, a list of tables in the active Set of Books will be displayed.
    - Select a table from the list.

3. Viewing Table Data:
    - Right-click on the selected table and choose the "Open" option. This action loads the data from the table into the bottom half of the SQL Browser screen.
4. Working with Data:
    - Utilize context menus to perform various actions such as opening, dropping, or emptying tables.
    - Use the Script Editor to write or edit SQL scripts.
    - Navigate and manipulate records using the Records section.
    - Apply filters, groups, and configure columns as needed.
5. Exporting Data:
    - Export data to XML, HTML, Excel, or Text formats (File menu).
    - Export data to JSON files Create tables from JSON files (Export import menu).
    - Save SQL queries for future use.
6. Exiting SQL Browser:
    - To exit the SQL Browser, click on the File → Exit menu or close the window.

Additionally, the SQL Browser menu system provides options for managing queries efficiently, customizing font settings, and handling records effectively. Users can write SQL scripts to filter and search data based on various criteria such as date, reference number, document number, or amount.

Furthermore, users can customize the display of columns, sort data in ascending or descending order, and apply filters to refine search results. Options for custom filtering allow users to specify conditions such as equal to, not equal to, less than, greater than, like, and more.

Overall, the SQL Browser in osFinancials5/TurboCASH5 empowers users to interact with their data in a flexible and efficient manner, making it a valuable tool for both novice and expert users alike.

Backup Recommendation

Before utilizing advanced features within the SQL Browser, such as dropping tables, executing or running scripts, creating a new table from a "JSON"-file, or any other advanced options, it is highly recommended to create a backup copy of your Set of Books. This precautionary measure helps safeguard against accidental data loss or unintended modifications.

If you are more than expert than the average user and you know how to write SQL (Structured Query Language) then you will love the SQL Browser. Make any valid SQL query and run it.

The return or result of your SQL rows can be grouped, filtered and sorted with just a few mouse clicks. This SQL browser also allows drag and drop features, which make it easy to work with.

Anything can be exported to the XML (Extensible Mark-up Language), HTML (Hypertext Mark-up

Language), Microsoft Excel, or Text File formats. This powerful tool will empower you to produce your own custom view of your data in TurboCASH5 and osFinancials5.

Anything can be exported to JSON-file format. This powerful tool will empower you to produce your own custom view of your data in osFinancials and TurboCASH.

Even if you are not an expert in the details or file structure of osFinancials5/TurboCASH5, you can also use this SQL Browser to filter and sort to see what you need to see. You may also use the SQL Browser to filter, sort and analyse your data.

This option allows you to generate queries and connect to the Database of a selected Set of Books using the Structured Query Language (SQL) standard. This Browse will list all the Firebird Database Files (*.fdb File extension) for the Set of Books.

Using the SQLBrowser

To use this option, you need to open a Set of Books. The SQL Browser will list all the tables in the database of the active (opened) Set of Books.

To Access and Use the SQLBrowser:

1. On the Setup ribbon, click on the Plug-ins → Tools → SQLBrowser. The "*SQL Browser*" screen will list all the tables of the active Set of Books.

   If the SQL Browser is not available from the Plug-ins → Tools → SQLBrowser menu, you need to Activate the SQL Browser plugin. To do this go to the Tools → Activate plugins on the Setup ribbon.

2. Select a table from the list.

3. Right-click on the selected table and select the Open option from the context menu. The data for the selected table will be loaded in the bottom half of the "*SQL Browser*" screen. In this documentation, the "*TRANSACT*" table is opened. The transactions will be displayed as follows:



You may click on the > icon on the list to expand and view the list of columns on the selected table (e.g. TRANSACT as in this example).

** Click here to show/hide/move columns*

Click on the asterisk of the column headings to view a list of the column names.



If you tick "(Sorted)" option, the columns on this list will listed alphabetically in the ascending sequence.

4. You may use the context menu's on each of the sections to work with your data, if necessary:

    a) Tables – Open, Drop or Empty a selected table. You may also extract data (i.e. all Table names or the entire table including the properties (i.e. datatype and width) in the wiki format to the Script Editor all the Table names in a Set of Books. This can be copied and used in documentation and for development.

    b) Script Editor – You may write or edit SQL script in this section. If the entire table or a selected record is exported as SQL script in the Records section, it will also be displayed in this section. You may also configure the editor font.

    c) Records – This is the records in a table. For example, each line in a posted batch will shows a record in the TRANSACT (Transaction) table. In this section, you may configure columns, filters, groups to view the data in a table. You may also export the entire table or a selected record as SQL script to the SQL Editor.

5. Once you are done, you may Export, Save SQL and Load SQL.

6. To exit the SQLBrowser, click on the File → Exit menu; or click on the Close button on the titlebar.

SQL Browser Menu System

File menu



Options menu



Speedbar



The buttons on the speedbar, is as follows:

- Run SQL
- Browse older executed SQL (previous)
- Browse older executed SQL (next)
- Insert a new tab (i.e. TS2, TS3, etc.)
- Run script
- Run script set term

SQL Script Editor

Writing SQL Script

1. On the top half of the SQL Browser screen, the following SQL script is displayed:

   Select * FROM followed by the name of the selected (active / opened) table. In this example,

   Select * FROM TRANSACT represents the TRANSACT (Transaction) table.

2. After the name of the table, leave a space, type where and leave a space and type the name of the column, (e.g. to list only those transactions for a specific date, type DDATE).

3. Leave a space and type an Operator symbol (e.g. to list all transactions equal to the value that needs to be entered, type =)

4. Leave a space and type a valid value (e.g. for the date, type '2021/03/16') This value must start and end with an apostrophe.

5. Click on the Run icon (or press the Enter key on your keyboard) to run the script.

Here is an example SQL script to select the date from the Transaction table ("*TRANSACT*"):

`sql`

```sql
SELECT * FROM TRANSACT
WHERE DDATE = '2021/03/16';
```

In this example:

- `SELECT *` retrieves all columns from the table TRANSACT.
- `FROM TRANSACT` specifies the table named TRANSACT from which to retrieve the data.
- `WHERE DDATE = '2021/03/16'` filters the results to only include rows where the value in the column DDATE is equal to `'2021/03/16'`.

You can replace `'2021/03/16'` with any valid value depending on your data. Remember to follow the formatting conventions, such as surrounding date values with apostrophes.

Similarly you can replace DDATE column name with any valid column name, for example "SREFERENCE" to specify a reference number in journals, or a document number.

5. When finished writing your SQL script, click on the Run icon (or press the Enter key on your keyboard) to run the script.

Font Editor

You may also customise the font in which the query data is to be displayed on the SQL Script Editor.

To Edit the Font:

1. Right-click on the "*SQL Script Editor*" section of this screen and select the Editor Font ... option. Alternatively, click on the Options → Editor Font menu.
2. Change the font, font style, size, effects and colour as necessary.
3. Click on the OK button. The text in the "*SQL Script Editor*" will be displayed in the selected font settings.

Tables - Records

The data for the selected table will be loaded in the bottom half of the SQL Browser screen.

Data records context menu

If you right-click on the records (table data) the following context menu is displayed:



Columns - Configure (Show / hide) columns / change sequence of columns.

Filters - This will add a filter icon to hide or show the data and filter data.

Grouping - Apply grouping to the data.

Export as SQL insert - This will run and export the entire selected table to SQL script.

Export record as SQL insert - This will run and export the selected record(s) to SQL script.

Extract update or insert on field1- This will extract the update or insert SQL script.

Buttons to manage records

The following buttons may be used to navigate and manage the records:

- First - Go to the first record.
- Previous - Go to the previous record.
- Next - Go to the next record.

- Last - Go to the last record.

- Add - Add a new record.

- Delete - Delete a record. Once you click on this button, a confirmation message is displayed:

Make absolutely sure that the correct record before you click on the OK button. If it is not the correct record, click on the No button and select the correct record.

- Action - This will activate the Save or Delete buttons.

- Save - Save the changes to the record.

- Cancel - Cancel changes to the record.

- Undo - Undo the latest changes.

Show / hide Columns

The SQLBrowser displays all the columns for the selected table by default. You may filter (hide) or show

only those columns you need to see.

To configure columns:



1. The SQL Browser displays all the columns for the selected table by default. Should you wish to hide any of these columns, you may click on the Options → Columns menu of the SQL Browser.
2. Select the following options, if necessary:
    a) Show / Hide Columns – You may de-select (remove the tick) the columns which you do not wish to view by simply removing the tick from the selected column.
    b) Sequence – Should you wish to change the sequence in which the columns are displayed, you may click on Down or Up buttons.

You may click on the All button to select all columns.

To clear all remove all the columns, click on the Clear button.

You may then select (place a tick) only in those columns to be displayed in the SQL Browser. To select (tick) or de-select (remove the tick), you may use the Spacebar and use the Down and or Up keys to select a column.

3. Once your selection is finished click on the OK button to apply these changes to the data in the SQL Browser.

Move Columns using the mouse:

You may also click on a column and drag it to the right (or to the left) to change the sequence in which you prefer the columns to be displayed.

Remove Columns using the mouse:

If you wish to delete or remove a column, simply click on the column and drag it down and leave the mouse button.

Sequence of Data in Rows

All the data is by default displayed ascending; from the smallest to the highest value (e.g. a-z or 0-9) according to the record number or record ID (e.g. Accounts.DB table it would be the AccountID, in the TRANSACT table, it would be the TRANSACTIONID, etc.)

To change the sort order from ascending (e.g. a-z or 0-9) to descending (e.g. z-a or 9-0) select a column and click on it. If you click on it again it will change back to ascending sequence.

Filter Options in Column Headings

While viewing and analysing the data you may sort and filter the data, in each column of the active or loaded table. To do this, select the column and click on the drop-down arrow. A list displaying the data as well as an All option and a customise option in the selected column will be displayed.

For example, the Reference column (i.e. SREFERENCE) of the Transaction table (i.e. TRANSACT) will display as follows:



The filter for this column (as per example) will list all reference numbers as entered in batches (journals) example, the reference for balancing entries (i,e, 8 asterisks ********) Reference column (i.e. SReference) of the Transaction Database table (i.e. TransAct.DB).

Custom Filter

You have the following options to sort or filter the data:

1. Select a specific entry from the list - only those entries which match the selection in the table, will be listed, e.g. with the same reference number.
2. All - Select to display all the entries in the selected table.

3. Custom - This will launch a screen on which you may set further criteria to filter the data.



The type of filter options/conditions available for data manipulation can vary depending on the nature of the data contained within the column. Some common Filter options is as follows:

a) Equal to - Lists or displays all values that are exactly the same as the specified value.

b) Not equal to - Lists or displays all values that are not exactly the same as the specified value.

c) Less than - Lists or displays all values smaller than the specified value.

d) Less than or equal to - Lists or displays all values smaller than or equal to the specified value.

e) Greater than - Lists or displays all values greater than the specified value.

f) Greater than or equal to - Lists or displays all values greater than or equal to the specified value.

g) Like - Lists all values in the table similar to the specified value using pattern matching (often with wildcard characters).

h) Not like - Lists all values in the table not similar to the specified value using pattern matching.

i) Is null - Excludes any rows where the value is missing (NULL), meaning they will not be listed or displayed.

j) Is not null - Lists or displays any rows where the value is not missing (NULL).

k) Start with - Lists or displays values where the text starts with the specified string.

l) End with - Lists or displays values where the text ends with the specified string.

m) Include - Lists or displays all values that match any of the specified values. This option is useful when you want to filter for multiple specific values.

n) Not include - Lists or displays all values that do not match any of the specified values. This option is useful when you want to exclude specific values from the result set.

These options provide a comprehensive set of conditions for filtering data in columns, allowing for precise control over the displayed dataset.

Adjusting filter options based on the data type ensures that you have access to the most relevant and effective tools for manipulating and analysing your data. This flexibility enhances usability and allows for more efficient data exploration and decision-making.

Date Filter

In date columns, a date picker or date selection screen will be available for ease of selection.

Export data

Export to files

On the File menu, you may select the Export option to export your saved data data to XML, HTML, Excel, or Texts formats.

Once you have sorted and filtered your criteria, you may:

1. Export the data in exactly the same sequence as displayed in the bottom half of the "*SQLBrowser*" screen to any of the following file formats:
    a) XML - Extensible Mark-up Language
    b) HTML - HyperText Mark-up Language
    c) Excel - Microsoft Excel Spreadsheet
    d) Text - Text file
2. Save the SQL in a (*.sql) SQL file format. You may then at any later stage open the saved *.sql file in the SQL Browser.

Export to JSON file / Create from JSON file

A JSON (JavaScript Object Notation) file is a lightweight data interchange format that is easy for humans to read and write and easy for machines to parse and generate. It is often used for transmitting data between a server and a web application as an alternative to XML.
JSON files are commonly used in various applications and scenarios such as web APIs, configuration files, and data storage. They are flexible and easy to work with, making them a popular choice for data interchange.

On the Export import menu, you may export data from a selected table and export it to a "*JASON*"-file.



You may also Create a new table from a "*JASON*"-file.



Table names in a Set of Books

All tables in the Set of Books may be extracted form the "*Extract all table names*" in the context menu (right-click on "*Tables*") option.

ABREVIAT
ACCOUNT
ACCOUNTREF
ADDRESSPERACCOUNT
ASSETMAS
BACKORD
BANK
BAT0T1
BAT0T2
BAT0T23
BAT0T3
BAT0T4

BATCON
BATRBT0T4
BATTYPES
BOM
CONTACTS
COUNTRIES
CREDITOR
CURRENCY
DEBTOR
DNLBANKS
DOCBATCH_0_0
DOCHEAD
DOCLINE
EMPMAS
EMPSOURCE
EVENTS
EVENTSPECIALDAYS
FLOWTMP
GLOBAL
GROUPS
GROUPSSTATUS
IMP_LINK

IMP_SOURCE
IMP_STOCKACCOUNTS
IMP_TOTALS
JOBPROJECT
KEYSCONT
LABSPECS
LOCATIONS
LOGENTRY
LOGGEDIN
MANUFACD
MANUFACH
MESSAGES
MULTIMEDIA
MULTIMEDIABLOB
OILINKS
OPREPORT
OSF_EDIT_FIELDS
OSF_EDIT_FORM
OSF_SEARCH_FIELDS
PAYCON
PAYTRANS
PERIODS

POSTBATCH_0_0
PRINTERS
PROFILES
RDB$CHARACTER_SETS
RDB$CHECK_CONSTRAINTS
RDB$COLLATIONS
RDB$DATABASE
RDB$DEPENDENCIES
RDB$EXCEPTIONS
RDB$FIELDS
RDB$FIELD_DIMENSIONS
RDB$FILES
RDB$FILTERS
RDB$FORMATS
RDB$FUNCTIONS
RDB$FUNCTION_ARGUMENTS
RDB$GENERATORS
RDB$INDEX_SEGMENTS
RDB$INDICES
RDB$LOG_FILES
RDB$PAGES
RDB$PROCEDURES

RDB$PROCEDURE_PARAMETERS
RDB$REF_CONSTRAINTS
RDB$RELATIONS
RDB$RELATION_CONSTRAINTS
RDB$RELATION_FIELDS
RDB$ROLES
RDB$SECURITY_CLASSES
RDB$TRANSACTIONS
RDB$TRIGGERS
RDB$TRIGGER_MESSAGES
RDB$TYPES
RDB$USER_PRIVILEGES
RDB$VIEW_RELATIONS
RECON0
RECONBANK
REPCELLS
REPCOLS
REPHEAD
REPLINE
REPORTOP
REPTBAT
REPTDOCS

RESOURCES
STOCK
STOCKPUB
STOCKTRN
SYSPARAMS
SYSVARS
SYSVARSEXT
TASKACTION
TASKS
TAX
TEMP1
TMPAGEAN
TOTALS
TRANSACT
TRANSACTASBATCH
TYPES
UNIT
USERS
V_OPENDOCAMOUNT
V_TRANSACTASBATCHWITHTRANSID
V_TRANSACTTAXENTRIES
YEARS

Created with the Standard Edition of HelpNDoc: Maximize Your CHM Help File Capabilities with HelpNDoc

Other Plugins / Products

Books / Manuals

osFinancials Manual (Netherlands)

osFinancials manual - Shop - Licence - Once-off -

The osFinancials manual provides comprehensive guidance on using the osFinancials software, offering step-by-step instructions in Dutch. This manual covers various aspects, including setting up accounting processes, implementing daily tasks, and navigating the features of osFinancials. Whether you're new to the software or seeking to enhance your proficiency, the osFinancials manual equips users with the knowledge needed to effectively utilize the platform for financial management purposes.

Documentation -

English and Afrikaans Online Help

osFinancials5/TurboCASH5 accounting software provides a comprehensive online help system in both English and Afrikaans. This help system is designed to assist users in understanding and navigating the osFinancials5/TurboCASH5 accounting software, as well as to provide guidance on accounting principles and practices. Whether you are new to accounting or an experienced professional, the help system offers a wealth of information to help you get the most out of osFinancials5/TurboCASH5. With easy-to-follow instructions and detailed explanations, the help system is an invaluable resource for anyone using osFinancials5/TurboCASH5 for their accounting needs.

Hands-on Tutorials

osFinancials5/TurboCASH5 installation provides tutorial Sets of Books in both English and Afrikaans. These tutorial books allow users to explore different settings, transactions, and reports within the software. Here are the available tutorial sets:

Accounting Made Easy

English tutorials (using separate receipt and payments journals for banking / cash transactions)



The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\ENGLISH\" folder:

- *HANDYMAN (No transactions)*
- *HANDYMAN-A (Unposted transactions)*
- *HANDYMAN-B (Posted transactions)*

Accounting Made Easy - Bank Import

English tutorials (using the BankImport plugin for banking / cash transactions)

The following Set of Books based on this tutorial, is installed in the "…\bin\Tutorials\BANK-IMPORT\" folder:

- *HANDY-BANK (No transactions).*
- *HANDY-BANK-A (Unposted transactions)*
- *HANDY-BANK-B (Posted transactions).*
- *HANDY-BANK-UNPOSTED-BANK-STATEMENT – Posted transactions, excluding bank / cash transactions. Bank statement needs to be imported from the "…\bin\Tutorials\BANK-IMPORT\BANK-STATEMENTS" folder.*

Rekeningkunde Met Gemak (Afrikaans)

Afrikaanse handleidings (gebruik aparte ontvangste- en betalingsjoernale vir bank- / kontanttransaksies)

Die volgende Stel Boeke gebaseer op die Afrikaanse handleidings, is in die "…\bin\Tutorials\AFRIKAANS\"-lêergids geïnstalleer:

- *NUTSMAN (Geen transaksies).*
- *NUTSMAN-A (Ongeposteerde transaksies)*
- *NUTSMAN-B (Geposteerde transaksies).*

To open the tutorial Sets of Books, installed in the "*bin / Tutorials*" directory, you need to click on the Open icon on the Start ribbon. On the "*Set of Books*" screen, click on the Browse icon and select the desired tutorial Set of Books that you wish to follow.

Other plugins

Project Hours Registration Plugin

Project Hours Registration - Shop - Licence: Once-off -

This plugin allows you to register hours for projects and generate quotes and/or invoices if you have activated Projects.

Efficiently track project hours and streamline invoicing with our Project Hours Registration Plugin. Available for a one-time license fee, this plugin seamlessly integrates with the Projects feature in osFinancials5/TurboCASH5, enhancing its functionality with multi-user agenda and hour registration capabilities.

Key Features:

- Hour Tracking: Easily register and monitor hours spent on various projects directly within the osFinancials5/TurboCASH5 interface.
- Quote and Invoice Generation: Generate quotes and invoices based on recorded project hours, facilitating accurate billing and client communication.
- Enhanced Projects Functionality: Complement the existing Projects feature in osFinancials5/TurboCASH5 with additional options for multi-user agenda management and hour registration.
- Improved Collaboration: Enable multiple users to collaborate on projects by tracking their respective hours and contributions.
- Streamlined Workflow: Simplify project management processes by centralizing hour registration and invoicing within the osFinancials5/TurboCASH5 platform.

Maximise productivity, improve project tracking, and enhance invoicing accuracy with the Project Hours Registration Plugin for osFinancials5/TurboCASH5.

Small adjustments

Quantities based on dates 1 and 2 plugin

Quantities based on dates 1 and 2 Plugin - Shop - Licence: Once-off -

Quantities based on dates 1 and 2 plugin

Multiplies the item total amount based on the quantity and period between date field 1 and date field 2.

The "Quantities based on dates 1 and 2" plugin in osFinancials calculates quantities based on two dates and then multiplies the item total amount by the quantity and the period between those dates. This could be useful for scenarios like calculating expenses over a specific time period or determining the quantity of items needed for a project based on the duration.

This plugin would likely need inputs for the item total amount, the quantity, date field 1, and date field 2. Then, it would calculate the period between the two dates, multiply it by the quantity, and finally, multiply the result by the item total amount to give the final amount.

Netherlands text

"*Aantallen op basis van datum 1 en 2*
Vermenigvuldigd het artikel totaal bedrag op basis van het aantal en de periode tussen datum veld 1 en datumveld 2".

Unit Sales and Purchases Plugins

Unit Sales Plugin

Unit Sales Plugin - Shop - Licence: Once-off -

The Unit Sales Plugin streamlines the process of selling units to your customers, such as packs of items. Easily manage unit quantities and sales within osFinancials with this intuitive plugin.

Key Features:

- Bulk Sales: Simplify the selling of items in predetermined units, such as packs or bundles, to customers.
- Unit Management: Add units and their quantities directly within osFinancials to facilitate sales

of packaged items like 6-packs or other bundled units.

- Efficient Sales Process: Simplify the sales process by seamlessly integrating unit sales management into your osFinancials workflow.
- Improved Inventory Control: Maintain better control over inventory levels by accurately tracking unit quantities and sales transactions.
- Enhanced Customer Experience: Provide customers with the convenience of purchasing packaged units, improving satisfaction and loyalty.

With the Unit Sales Plugin, optimize your sales operations and offer customers the flexibility to purchase units tailored to their needs.

Unit Purchase Plugin

Unit Purchase Plugin - Shop - Licence: Once-off -

The Unit Purchase Plugin facilitates the procurement of units from suppliers, streamlining processes such as bulk purchasing, package deals, or bundled acquisitions, akin to buying items in specific quantities such as six-packs. With this plugin, users can effortlessly manage unit-based purchases within osFinancials5/TurboCASH5.

Key Features:

- Bulk Procurement: Simplify the procurement of items in predetermined units, such as packs or bundles, from suppliers.
- Quantity Management: Easily add units and specify their quantities within osFinancials5/TurboCASH5, ensuring accurate inventory tracking and purchasing.
- Supplier Integration: Seamlessly integrate unit purchases with supplier transactions, enhancing procurement efficiency and supplier relationship management.
- Inventory Optimization: Streamline inventory management by aligning purchasing activities with predefined units, optimizing stock levels and reducing procurement complexities.
- Customization Options: Tailor the plugin settings to accommodate specific unit-based purchasing requirements, offering flexibility and adaptability to diverse procurement needs.

By leveraging the Unit Purchase Plugin, organizations can enhance their procurement processes, improve inventory management, and optimize purchasing efficiency within osFinancials5/TurboCASH5.

Payroll plugin

Payroll - Manual - Shop - Licence : Once-off -

Supported applications: Logisal, RoosRoos and Unit 4.

Seamlessly import payroll data from supported applications like Logisal, RoosRoos, and Unit 4 directly into osFinancials5/TurboCASH5, simplifying payroll-related transactions.

Is the program you use not listed? No problem! With our commitment to customer satisfaction, simply send us an export, and we will explore the possibility of adding that import. In most cases, the addition is free of charge.

Say goodbye to manual data entry and hello to efficiency as you effortlessly generate batches or journals for payroll processing within osFinancials5/TurboCASH5.

Payroll Plugin Access - Batch entry - F9:Process - Payroll import option.

Multi-Language accounts plugin

Multi-Language accounts - Manual - Shop - Licence : Once-off -

Documentation : Help documentation

Break down language barriers in accounting with our Multi-Language Accounts plugin. Now, not only can you select different interface languages, but you can also seamlessly translate ledger and group names into multiple languages, ensuring clarity and ease of use for every user.

Each user can operate in their preferred language, facilitating efficient and accurate accounting practices. Plus, with the ability to view Sets of Books in various languages, collaboration across teams becomes smoother than ever. Whether it's English, Afrikaans, Dutch, or any other language, our plugin ensures that everyone can work comfortably and effectively within osFinancials5/TurboCASH5. Say goodbye to language limitations and embrace global collaboration with Multi-Language Accounts plugin.

Workflow plugin

Workflow - Manual - Shop - Licence : Once-off -

Workflow Bank Import Plugin - Shop - Licence: Once-off -

Workflow Editor Plugin - Shop - Licence: Once-off -

Documentation : Help documentation

Unlock the power of streamlined task management with our Workflow plugin. Seamlessly record every step and process, whether it's inventory management, debtor/creditor tracking, or document handling, within osFinancials5/TurboCASH5. Visualize your workflow at a glance, gaining instant insights into each stage of progress.

Assign tasks or steps to specific users, track outstanding steps, and effortlessly manage transitions between stages. Our Workflow Plugin isn't just a tool - it's a knowledge system, empowering you to formalise and share business processes efficiently. Gain better control over your operations, with historical data readily available for informed decision-making. Say hello to optimized processes and enhanced productivity with the Workflow Plugin.

Workflow Bank Import Plugin

Workflow Bank Import Plugin - Shop - Licence : Once-off -

The Workflow Bank Import plugin provides users with a guided step-by-step process for importing downloaded bank transactions and posting them to the appropriate journal or batch. This streamlined workflow ensures efficiency and accuracy in handling bank transactions within osFinancials5/TurboCASH5.

Workflow Editor Plugin

Workflow Editor Plugin - Shop - Licence : Once-off

Use workflow to create you own processes. With the Workflow Editor plugin, you can customize and create your own processes tailored to your specific needs. Whether it's automating tasks, managing approvals, or streamlining workflows, this tool empowers you to design efficient processes that align with your business requirements.

Branch Specific Plugins from our Webshop

Medical industry

Open Dental Plugin

Open Dental Plugin - Manual - Shop - Licence: Annual licence -

The Open Dental Plugin offers seamless integration between your dental application and osFinancials. With

just a click of a button, you can effortlessly import invoicing data from your dental application into osFinancials. Similarly, after receiving payments, you can conveniently close outstanding amounts in the dental application with another simple click. This plugin provides you with a comprehensive overview of outstanding amounts owed by your patients, ensuring efficient management of dental finances while minimizing manual tasks. Streamline your dental practice's financial workflow with the Open Dental plugin.

Promeetec Export Plugin

Promeetec Export Plugin - Shop - Licence : Annual subscriiption.

Supported language: Netherlands. Once activated, you can access this pluging from the Plugins → External system links → Promeetec menu.

Streamline your healthcare administration with our Promeetec Export Plugin, tailored specifically for Netherlands-based healthcare administration. Developed in collaboration with experts in healthcare administration, this plugin simplifies the selection of criteria, reconciliation, and exporting in Promeetec format, enabling easy claiming via email.

Key Features:

- Select open items based on criteria
- Reconcile selected items
- Export in Promeetec format
- Generate reports on processed batches
- Future development potential: Parsing return messages for detecting deviations.

Optimize your healthcare administration processes with our Promeetec Export Plugin, designed to meet the unique needs of Netherlands-based healthcare administration.

Woodsales / Volume Sales Plugin

Woodsales / Volume Sales Plugin - Manual - Shop - Licence : Once-off -

Empower your wood wholesale trading with our Woodsales/Volume Sales Plugin. Tailored specifically for the timber industry, this plugin revolutionizes invoice processing by enabling you to specify measurements such as meters length, height, width, and cubic meters effortlessly.

With a simple one-time license, unlock the ability to manage wood sales with precision and efficiency. Say goodbye to manual calculations and hello to streamlined invoicing processes with the Woodsales/Volume Sales Plugin.

osFinancials PAB 2.0 Plugin

osFinancials PAB 2.0 Plugin - Shop - Licence: Annual subscription

The osFinancials PAB 2.0 Plugin is a powerful addition to your osFinancials software, designed to enhance productivity and streamline your financial management processes. PAB stands for "*Payment Authorization Bureau*", and this plugin offers comprehensive features to facilitate secure and efficient payment authorisation workflows.

The Payment Authorization Bureau (PAB) plugin is designed to facilitate payment authorization workflows within osFinancials software. As such, its applicability is not limited to specific countries but rather extends to any organization or business entity that utilizes osFinancials for financial management purposes.

While osFinancials itself is a versatile accounting and financial management platform that can be used by organizations worldwide, the PAB plugin's effectiveness may vary depending on local regulations, banking systems, and business practices in different countries.

Therefore, the PAB plugin can be adapted and configured to meet the specific payment authorization requirements of various countries and regions, providing flexibility and customization options to accommodate diverse organizational needs. However, organizations should ensure compliance with relevant legal and regulatory frameworks governing payment authorization processes in their respective jurisdictions.

Key Features:

- Secure Payment Authorization: Ensure the security of your payment authorisation process with robust encryption and authentication mechanisms.
- Streamlined Workflow: Simplify and expedite payment authorisation workflows with intuitive tools and user-friendly interfaces.
- Multi-level Approval: Enable multi-level approval processes for payment authorisation,

allowing for hierarchical review and authorisation by designated personnel.

- Audit Trail: Maintain a detailed audit trail of all payment authorization activities, including approvals, rejections, and modifications, for comprehensive record-keeping and compliance purposes.
- Integration Capabilities: Seamlessly integrate the PAB 2.0 Plugin with other osFinancials modules and external systems to streamline data exchange and enhance interoperability.
- Customizable Configuration: Tailor the configuration of the plugin to align with your organisation's specific payment authorization policies, rules, and requirements.
- Reporting and Analytics: Access insightful reports and analytics to gain visibility into payment authorisation trends, performance metrics, and compliance adherence.
- User Permissions: Assign granular user permissions to control access to sensitive payment authorisation functionalities and data, ensuring data security and compliance with regulatory requirements.

The osFinancials PAB 2.0 Plugin empowers your organisation with robust tools and capabilities to optimize payment authorisation processes, mitigate risks, and drive operational efficiency in your financial management operations.

Driving School Plugin

Driving School Plugin - Shop - Licence :

Driving School Plugin This a comprehensive plugin for a driving school management system. This Plugin includes the FreeFieds Plugin and Multimedia Plugin.

Key Features:

- Multimedia Plugin for Candidate Photos: This feature allows candidates to capture their photos via webcam for identification purposes. It ensures that each candidate has a personalized photo associated with their profile.
- Multimedia Plugin for ID Scan: Candidates can scan or upload images of their identification documents, such as driver's licenses or IDs, to verify their identity and eligibility for the program.
- Multimedia Plugin for Theory Lists: Candidates can upload or scan documents related to

their theoretical knowledge, such as study materials or test results. This helps instructors track each student's progress in theoretical learning.

- Free Fields for Importing CBR Files: This feature enables the import of CBR (Candidate Booking Request) files, allowing for easy integration of candidate data into the system. It streamlines the process of adding new candidates to the database.
- Integration with osF Agenda for Examination Dates: The plugin integrates with the osF agenda to schedule and manage examination dates for students. Instructors can easily view and update examination schedules within the driving school system.
- Integration with osF Agenda for Lesson Dates and Times: Similarly, the plugin integrates with the osFinancials agenda to schedule and manage lesson dates and times for students. Instructors can efficiently plan and track the progress of each student's driving lessons.

These features collectively enhance the functionality of the driving school management system, providing instructors with tools to efficiently manage candidate data, schedule appointments, and monitor student progress.

Accountancy plugins

Spreadsheet Plugin

Spreadsheet Plugin - Shop - Licence : Once-off -

The osFinancials Spreadsheet plugin is a powerful tool for integrating financial data directly into Excel spreadsheets, streamlining the process of analysing and reporting financial information. By enabling users to leverage functions ranging from simple totals to more complex SQL queries, it offers flexibility in how data is presented and analysed within the familiar Excel environment.

The ability to add multiple aliases for different Sets of Books and consolidate the results in Excel is particularly useful for organizations managing multiple accounting entities or subsidiaries.

The osFinancials Spreadsheet plugin is already included in osFinancials5/TurboCASH5, eliminating the need for separate downloads. Upon payment, you'll receive an unlocking code via email for seamless activation.

Created with the Standard Edition of HelpNDoc: Easily create EBooks

Support products

Support Contract and Extra Tickets

Support Contract and Extra Tickets - Shop - Annual subscription -

Support Contract:

The support contract grants you direct access to our team for issue resolution, subject to a "*fair use*" policy. Support is provided via telephone and/or email. Additionally, you'll receive interim updates of osFinancials5/TurboCASH5 where bugs are fixed and new features introduced.

Extra Tickets:

Additional support tickets beyond the "*fair use*" allocation can be purchased at a discounted rate for contract holders.

Please note that development or modification of osFinancials5/TurboCASH5 and document layouts are not included in the support contract.

Support Ticket - Basic

Support Ticket Basic - Shop - Payment per hour -

Support tickets for questions about osFinancials.

A support ticket can be purchased for a period of 1 hour, half an hour or a quarter of an hour. Often a support ticket will be purchased at our request.

If your question is more advanced, a support ticket Advanced will have to be purchased.

Support Ticket - Advanced

Support Ticket Advanced - Shop - Payment per hour -

Support requests

osFinancials Adjusting the active year

osFinancials Adjusting the active year - Shop - Payment per request-

osFinancials5/TurboCASH5 support - osFinancials Period correction osFinancials/TurboCASH Adjusting the active year After receiving your set of books, we can turn back the active year to the current year. For example, if you accidentally opened additional years.

osFinancials Period correction

osFinancials Period correction - Shop - Payment per request -

osFinancials Period correction osFinancials Adjusting the active year After receiving your set of books, we can turn back the active year to the current year. For example, if you accidentally opened additional years.

Set of Books checkup

Set of Books checkup - Shop - Payment per request -

Set of Books checkup - After receiving your Set of Books, we can check and fix issues in your Sets of Books database.

Database repair

Database repair - Shop - Payment per request -

Database repair - After receiving your Set of Books, we can check and fix issues in your Sets of Books database.

Reset password for your Set of Books

Reset password for your Set of Books - Shop - Payment per request -

Did you forgot the password to open your Set of Books?

We can reset it for you.

After we receive the payment you'll get instructions how to upload your Set of Books.

osFinancials Field length

osFinancials Field length - Shop - Payment per request-

osFinancials Field length - With this tool you can change the field length of:

- The product code
- The product description
- Debtor name
- Creditor name
- In the documents, and batch entries but also with the import of osCommerce.

osFinancials Workshops

osFinancials Workshop Basic

osFinancials Workshop Basic - Shop - Payment per hour -

This workshop is a one on one, remote workshop. With a software program your desktop will be shared with us. That way you can see the movements we make or perform the actions yourself while we watch during the workshop.

At start you submit the items you want to have support on or you can choose to have the step by step

explanation.

The step by stem explanation means:

- Starting your accounting.
- Creating a chart of accounts.
- Working with osFinancials.
- Any question that comes up during the workshop.

The workshop is based upon a hour price.

osFinancials Workshop Advanced

osFinancials Workshop Advanced - Shop - Payment per hour -

This workshop is meant for the trained osFinancials user, or accountant.

Online "*workshop*", with a shared desktop we interactive set up osFinancials or give explanation about the procedures.

This is a workshop based upon a hour price, so you need to buy as many as you think is needed, or what our consultants advise.

Conversion

If you need to convert your data from other accounting packages, the following options is available on the osFinancials Webshop:

Conversion Basic

Conversion Basic - Shop - Payment per hour -

With this product one of our technical consultants will convert the files of your present Set of Books to osFinancials with the maximum of time for 1 hour.

The files that will be converted are:

- Debtor file
- Creditor file
- Stock file

Please note: This conversion doesn't include the ledger accounts.

The submitted file must be in csv, xls, txt, or wk1 format.

If you want to submit an other format, please contact us.

Conversion Extensive

Conversion Extensive - Shop - Payment per request -

With this product one of our technical consultants will convert the files of your present Set of Books to osFinancials5/TurboCASH5.

Converting data from various other accounting software packages to osFinancials5/TurboCASH5. Here's a breakdown of the process and what's involved:

1. Conversion Service: The conversion service offered by osFinancials5/TurboCASH5 involves one of their technical consultants converting files from your current accounting software to osFinancials5/TurboCASH5. This service has a maximum time limit of 2 hours.
2. Supported Formats: Data from your existing accounting software can be converted if it can be provided in CSV, XLS, TXT, or WK1 format. These are common file formats for exporting data from accounting software.
3. Converted Files: The following types of files can be converted as part of the service:
    - Debtor file: Information about your customers or clients.
    - Creditor file: Information about your suppliers or vendors.
    - Stock file: Details about your inventory or stock items.
    - Ledger accounts: Your financial accounts, including income, expenses, assets, and liabilities.
    - Mutations: Changes or transactions recorded in your accounting system.
4. Supported Software Packages: The service supports conversion from several Dutch accounting software packages, including:
    - Accountview
    - ADBPlus

- Davilex
- Exact
- Muis
- Nedsof

5. Contact for Inquiry: If you're unsure whether your data can be converted or if you have any questions about the conversion process, you can contact osFinancials5/TurboCASH5 for clarification.

If you're considering migrating your accounting data to osFinancials5/TurboCASH5 and your current software is one of the supported packages, this conversion service could streamline the transition process for you. It's always a good idea to reach out to osFinancials directly for specific details about the conversion process and any requirements or considerations specific to your situation.

Conversion to Microsoft SQL Server database

Conversion to Microsoft SQL Server database - Shop - Payment per request -

Convert Sets of Books to Microsoft SQL Server database.

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Field length

---

osFinancials5/TurboCASH5 Field length

osFinancials Field length - Shop - Payment per request -

With this tool you can change the field length of:

- Product code
- Product description
- Debtor name
- Creditor name

- In the documents, and batch entries but also with the import of osCommerce.

osFinancials offering field length customization as a paid service for osFinancials5/TurboCASH5. This is a valuable option for businesses that have very specific needs beyond the standard account structures. osFinancials goes even further by providing a dedicated "Field Length" where you can request and pay for specific field length adjustments.

What it implies:

- Flexibility for Unique Needs: Businesses often have unique chart of account structures, reporting requirements, or industry-specific categorizations that go beyond typical account numbering schemes. The Field Length Shop allows osFinancials to adapt to these non-standard needs, as well as other important fields.
- Control and Precision: Customization gives businesses greater control over their financial data. They can tailor the system to match their exact processes and ensure that the software accurately reflects their financial activities.
- Scalability: As a business grows or its needs evolve, the ability to adjust field lengths can be crucial for accommodating new data elements without requiring a complete system overhaul.
- Professional Service: Offering this as a paid service through the Field Length indicates that osFinancials provides professional support and expertise to ensure that the customization is done correctly and efficiently. This can be especially valuable for businesses that lack in-house technical expertise.
- Specific Customization Options: Through the Field Length Shop, osFinancials allows you to change the field length of key elements, including:
  - Product Code
  - Product Description
  - Debtor Name
  - Creditor Name
- Comprehensive Application: These field length changes apply not only to documents and batch entries within osFinancials but also extend to data imported from osCommerce. This is a significant advantage for businesses using both platforms.
- Potential Costs: While customization offers flexibility, it's important for businesses to understand the associated costs. They should get a clear understanding of the pricing structure and any potential ongoing maintenance fees *before* making a request through the Field Length Shop.

Key Considerations for Businesses:

- Clearly Define Requirements: Before requesting a field length change, businesses should clearly define their specific requirements. This includes identifying which fields need to be adjusted and the

desired length for each field. The more specific you are, the smoother the process will be.

- Evaluate Alternatives: Businesses should also consider whether there are alternative solutions, such as using prefixes, suffixes, or custom fields, that might achieve the desired result without requiring a formal request through the Field Length.
- Get a Quote: Contact osFinancials directly through the Field Length process to get a detailed quote for the customization service, including any potential costs for implementation, testing, and ongoing support.
- Document Changes: Ensure that all customizations are properly documented. This will be crucial for future upgrades, maintenance, and troubleshooting.

By offering this customization service, and especially by providing the Field Length , osFinancials demonstrates a commitment to meeting the diverse needs of its osFinancials5/TurboCASH5 customers. It empowers businesses to leverage the software effectively, even with non-standard data requirements or integrations with other platforms like osCommerce.

Created with the Standard Edition of HelpNDoc: Leave the tedious WinHelp HLP to CHM conversion process behind with HelpNDoc

Shipping plugins

Shipping costs separately on invoice plugin

Shipping costs separately on invoice plugin - Shop - Licence : Once-off -

Enable : "Dynareg - Documentten - Verzenden als apart onderdeel"

Documentation : Help documentation

Shipping plugins - For the Dutch market

osFinancials shippers lite Plugin

osFinancials shippers lite Plugin - Shop - One time fee -

Shipping options for the Dutch market only.

osFinancials Parcelware plugin

osFinancials Parcelware plugin - Shop - One time fee -

Plugin usable for Dutch market only.

osFinancials GLS plugin

osFinancials GLS plugin - Shop - One time fee -

Plugin usable for Dutch market only.

GLS Send Package Extra

GLS Send Package Extra plugin - Shop - One time fee -

Plugin usable for Dutch market only.

osFinancials DPD plugin

osFinancials DPD plugin - Shop - One time fee -

Plugin usable for Dutch market only.

osFinancials DPD plugin

osFinancials DPD plugin - Shop - One time fee -

Plugin usable for Dutch market only.

osFinancials Packs plugin

osFinancials Packs plugin - Shop - One time fee -

Plugin usable for Dutch market only.

Parcel picklist layout default

Parcel picklist layout default - Shop - Annual subscription -

Default layout for Parcel picking list.

Created with the Standard Edition of HelpNDoc: Full-featured Kindle eBooks generator

E-mail plugins

Document EMail Pro Plugin

Document EMail Pro Plugin - Manual - Shop - Licence : Once-off - This Plugin is included in the osFinancials5/TurboCASH5 subscription.

Streamline your document handling and communication processes with our Document Email Pro Plugin. With a one-time licence, you can effortlessly email invoices, quotes, and more directly from the program.

Customise email layouts to match the document type, ensuring a professional and tailored communication experience for your clients and suppliers. Send multiple documents simultaneously with ease, simplifying your workflow and saving valuable time.

Experience the convenience of sending digital sales and purchase documents in PDF format, enhancing efficiency and communication with customers and suppliers alike. Upgrade your document management with Document Email Pro Plugin.

Document email pro plugin Newsletter

Document email pro plugin Newsletter - Shop - Licence : Once-off -

The "*Document email pro plugin Newsletter*" plugin for osFinancials5/TurboCASH5 enhances your communication capabilities by allowing you to send documents via email seamlessly. This documentation specifically focuses on the newsletter functionality of the plugin, providing a detailed guide on its features and usage.

Key Features:

- Document Email Integration:
  - Send documents such as invoices or quotations directly via email.
  - Option to choose between HTML or plain text format.
  - Define unlimited email layouts tailored to your preferences.
  - Add custom text entries for individual customers or email recipients.
- Email Template Management:
  - Separate email template management for easy customization.
  - Configure email data sets independently for each template.
- SMTP Server Integration:
  - Support for SMTP server with password access for secure email delivery.
- Recipient Management:
  - Retrieve recipients from osFinancials5/TurboCASH5 database for newsletter distribution.
  - Integration with E-Commerce plugin allows inclusion of users from your shop or CRM system.
- Usage Method:
  - Document Email Creation:
    - Right-click on the document (e.g., invoice or quotation, which is sent as a pdf attachment) to initiate email creation.
    - In the second selection field of the email template that the email body text.
    - Optionally, in the shipping screen, where you also can add additional text not

included in the template condition.

- § Additional Text Entry:
  - Provide extra text during email composition, not included in the template.
  - Opportunity to include personalized messages for recipients.
- § Preview and Trial:
  - Preview email in the browser before sending.
  - Send a trial version to CC/BCC email addresses for review.
- § Finalizing and Sending:
  - Review the email content before sending.
  - After sending, display confirmation message for reference.

- o Installation:
  - § The plugin comes pre-installed with osFinancials5/TurboCASH5 and does not require separate downloads.
  - § Upon payment confirmation, receive the plugin code and unlocking instructions via email.
  - § Initiate plugin activation directly from osFinancials5/TurboCASH5 with a simple button push.
  - § Activation typically occurs within one working day after payment receipt.

The Email Pro plugin's newsletter functionality enhances your communication efficiency by integrating document emailing and newsletter distribution seamlessly within the osFinancials5/TurboCASH5 system. With its intuitive interface and versatile features, stay connected with your customers effortlessly.

Created with the Standard Edition of HelpNDoc: Free help authoring environment

Bank import plugin

Introduction to the Bank Import Plugin

Bank Import Plugin Licence

The Bank Import Plugin is included with the osFinancials5/TurboCASH5 Business class subscription. With a registered osFinancials5/TurboCASH5 Business class subscription, you gain access to import and process unlimited statements for each of your bank accounts.

Upon purchasing the osFinancials5/TurboCASH5 Business class subscription, you will receive an email containing registration (activation) codes and detailed instructions.

For unregistered versions of osFinancials5/TurboCASH5, a message may appear:

> *"This demo plugin allows %s records to be entered. If you need more, please buy the product at https://www.osfinancials.org/en/webshop".*

We encourage users to support osFinancials by purchasing the osFinancials5/TurboCASH5 Business class subscription. This not only unlocks the full functionality of the Bank Import Plugin but also supports ongoing development and improvements.

For users of osFinancials 4 / TurboCASH4, the Bank Import Licence is available for purchase from our osFinancials webshop.

The Bank Import Plugin in osFinancials5/TurboCASH5 empowers you to seamlessly download bank statement files from your online banking platform, provided by your bank or financial institution. These downloaded statements can then be effortlessly imported into the corresponding bank accounts, referred to as cash books within osFinancials5/TurboCASH5.

This plugin supports the download of statements for multiple bank accounts and credit cards, accommodating users with diverse banking needs. It's essential to have the corresponding Payments and Receipts journals set up for each bank or credit card account within osFinancials5/TurboCASH5.

By importing bank statements, transactions are automatically populated into the Payments and Receipts columns, eliminating the need for manual data entry. This automation not only saves time but also minimizes the risk of errors inherent in manual input.

The user-friendly interface of the Bank Import Plugin includes context menus that facilitate the location, selection, and search for specific transactions, debtors, creditors, or general ledger accounts. This enhances the navigation and management of bank transactions, contributing to efficient financial data handling.

Setting debtors, creditors, or general ledger accounts as open item accounts enables precise linking of debit and credit transactions, ensuring accurate tracking of outstanding balances and facilitating efficient payment and receipt management. The plugin allows flexibility in linking portions of payments or receipts to multiple outstanding transactions as needed.

Furthermore, the plugin enables the linking of accounts to specific debtors, creditors, or general ledger accounts, ensuring subsequent bank statement imports automatically allocate transactions correctly based on predefined account linkages. This feature streamlines transaction allocation, enhancing the accuracy of financial records and saving time.

Utilizing bank references, the plugin automatically allocates or links various transactions, such as payments,

deposits, receipts, and other debits/credits, to the correct accounts within your Set of Books. This automation simplifies processes and reduces the need for manual intervention.

In summary, the Bank Import Plugin in osFinancials5/TurboCASH5 offers a comprehensive solution for importing bank statements, automating transaction allocation, and efficiently managing and reconciling bank accounts within your accounting system. With its array of features and functionalities, it not only reduces manual data entry but also enhances the accuracy and effectiveness of financial management processes.

Managing Bank Statements

Download and Save your Bank Statement

Before you can use this Bank import plugin, you need to download your Bank Statement from your financial institution and save it in a valid file format.

When downloading a bank statement; from your bank or financial institution; you may need to:

- Sequence to list your transactions, e.g. Date, Amount or Description.
- Select the correct start and end dates, for your requirements.

You may download bank statements for more than one bank account; credit card statements; etc.; provided that:

- You are registered for online banking at your bank or financial institution.
- Have a created separate Bank, Credit card accounts, etc. which is linked to its own Payments and Receipt journals).

If you have created and use the Petty Cash account as a Bank Account, you may still enter the transactions manually, if required.

Different Methods for Tracking Bank Transactions

You can keep track of your bank bookings in different ways, in this manual we will discuss the 2 most common ones.

1. Statement method, where you make your bookings per statement from the bank.
    - Benefits :
        - You have a good check of the balances: the final amounts on the statement.
    - Cons :

- The bank balances are not "up to date", you always fall behind "today" depending on the shear frequency.
- It is possible that there are 2 statements with the same date
- In the download, you will always download all bookings from that date
- These "extra" bookings must be deleted either before importing, or immediately after the import in the screen for assigning the reference

2. Date method, in which you record the bookings by date.
   - Benefits :
     - The bank balances are "up to date", you are one day behind today.
     - No corrections on downloads, with bookings of the same date appearing on 2 statements.
   - Cons :
     - None as far as known.

Enter cash / bank details according to the "statement method"

You prepare statement no. 1 to verify the data.

You now have 2 options for entering the transactions:

1. You can download the statement and process it electronically via electronic banking.
2. You can enter the statement manually.

Configuring the Set of Books for the Bank Import plugin

Activating the Bank Import Plugin

To activate the Bank Import Plugin's features, you must first check or confirm the setting. The Bank Import plugin uses a combined payment and receipt journal into a single journal for each bank account.

To activate the Bank Import plugin:

1. Go to the Setup ribbon and select Setup → System parameters.
2. Deselect (remove the tick) on the “*Default bank reconciliation*” to activate this plugin.



3. Click OK. This will save your setting.

Settings for the bank account batch

Firstly, you will need to check and confirm the settings of the Bank entry batch.

1. Go to the Default ribbon and select Cash/Bank entry . The "*Bank statement options*" screen is displayed:



2. Select the "*Bank account*" into which you need to import your bank statement. In this example, " *ABC-Bank*" is selected.

3. Click Open. The "*Batch entry*" screen, is displayed, as follows:



4. Click F10: Setup . The "*Options for this batch*" - "*Standard*" tab is displayed:



5. Check the following items:
   - The contra account is the Account code (number) of your bank account in your ledger.
   - The check mark "*No tax*" should be 'on'. If you are not registered as a VAT (GST/Sales tax vendor you may leave this option unticked.
6. Then click on the "*Advanced*" tab and accept the settings as below.



7. Click on OK. if the settings are selected correctly. This will save your options and close the "*Options for this batch*" screen.

Working with the bank import plugin

Now all settings are checked/set correctly, transactions can be imported with the bank import plug-in.

Import Bank statements

On the Default ribbon and select Cash/Bank entry . The "*Bank statements options*" screen will list your previous processed transactions.



NOTE : The PETTYCASH REPLENISHMENT (first transaction on the Bank statement options screen, indicates the existing transaction posted to the Petty cash account.



Select the "*Bank account*" into which you need to import your bank statement.

For the purposes of this tutorial, select "*ABC – Bank*".

Click Open. The "*Batch entry*" screen, is displayed, as follows:



Click on the "*Import bank statement*" . The "*Import bank statement*" screen is displayed:



Select a file format. You may select a Country to list the available file formats supported for a specific country. See - Supported bank import file formats.

For the purposes of this tutorial, select the "*INT-OFC / OFX standaard 2*" file format.



Then click on "*Import*".



Select the "*Show details*" option. If the "*Show details*" is not selected (not ticked), the "*Check*" screen will not be launched.

The "Open" screen is displayed. Select the correct bank statement saved on your system.



Click on Open. The transactions included in the bank statement file will be imported.

If the "Show details" option is not selected (not ticked) on the "Import" tab of the "Import bank statement" screen, the "Check" screen will not be launched.



Check here if the transactions are correct. If a transaction is incorrect, this can be removed with the "*Delete line*" button. If a line is yellow, there is a change this transaction has already been imported into a previous import.

Check this transaction carefully!

Explanation of the "*Check*" screen:

Delete line	*This removes a selected line. For example, if it has been imported before.*

Split	*With this button, an amount can be split, for example, if one amount has been paid, but there are two VAT rates or one payment is made for more than one items, which need to be allocated to different accounts.*
Merge	*With this button amounts can be merged, for example if two payments are actually one invoice or need to be allocated to one account.*
Statement reference	*The reference is entered here, so that the payment can easily be retrieved later. Entering the statement reference it is not necessary, but you may need to enter for your specific requirements.*
Apply	*With the apply button, the reference is adjusted.*

If all statements are correct, click on Close. The screen below is displayed. In this screen, the imported bank statement(s), are listed.



The details displayed on the "Import Bank Statement" screen is as follows:

1. *Transaction no. - This will be the transaction number generated and would consist basically of the date yyyy/mm/dd format; followed a time stamp and a reference number. This may differ from your operating system's regional and date settings.*
2. *Total - This is the net value Credit (Deposits / Receipts) minus the Debit (Payments) amounts. If the Credit (Deposits / Receipts) is more than the Debit (Payments) this will display a positive amount. Should the Debit (Payments be more than the Credit (Deposits / Receipts) this amount should be displayed as a negative (" -") amount.*
3. *From - The start date as selected while downloading (exporting) the bank statement from your bank or financial institution.*

4. *Until - The end date until when transactions would be included in the downloaded (exported bank statement).*

5. *Posted - The default value is "0". This means that the transactions have not yet been posted (updated to the ledger). Once you have allocated (selected) Accounts and/or Tax accounts (where applicable) a value of "1" as posted (processed) will be displayed.*

If the bank import is done, the font colour will change to green. The colour of the font for this line will change from black to blue after the journal is updated or posted to the ledger. If the next bank statement is entered, the font colour will change to green.

Click Close again to import the transactions in the bank statement into the batch. This closes the "*Import bank statement*" screen. The bank statement transactions is imported into the "*Batch entry*" screen for the selected bank account:



If there is already a reference on the Bank links tab for ledger accounts and on the Bank accounts tab for debtor accounts and creditor accounts that exactly matches the reference field of the bank statement, the transactions from the imported bank statement will automatically be allocated against the correct accounts.

This information will be displayed on the Match log tab of the journal.

In this example, the transactions listed in the Match log tab, indicates that the imported transactions in lines 6, 8 and 9, is matched.

This means that the bank references in the the "*Account code*" column on the *"Import bank statement - Check"* screen, matches the existing references on the Bank links tab for these ledger accounts.

Managing bank references with VAT (GST/Sales tax)

If a matching "*References*" is entered in the Bank links tab of a ledger account, and there is an exact match on the bank reference on an imported bank statement, the account will be allocated to the correct account in the "*Account*"column of the "*Batch entry*" screen,

If VAT (GST/Sales tax) is applicable to transactions included in the import file of the bank statement, you need to link a Tax code from the "*Link tax*" list. This will ensure that the tax-code will be allocated to the correct account in the "*Tax*"column of the "*Batch entry*" screen.



This setup streamlines the process of reconciling bank transactions by automating the allocation of transactions based on predefined references and tax codes, reducing manual effort and potential errors. It's a helpful feature for businesses dealing with a large volume of transactions and complex tax requirements.

Change the name of the Batch entry

Change the name of the batch (alias) (i.e. “*ABC-Payments ABC-Bank*) of the Batch. In this example, "*ABC-Bank-St.5*" is entered in the “*Change alias*” field. This will identify the specific Bank statement for which bank is processed in the specific batch.



If you have imported an incorrect bank statement, you can click on the ^D: Delete statement icon. This will delete all imported transactions in the journal.

Allocating transactions to ledgers / debtors / creditors

In the next step each transaction must be specified with an account (debtor / creditor / ledger) which belongs to the transaction.

This account can be allocated in the account column. There are different ways to link a transaction to an account.

1. The account is looked up by account name.
2. The account is looked up by looking up the corresponding document.
3. The account is looked up by looking for a debtor or creditor account.
4. The account is entered automatically, because it is linked to the (bank) account number (i.e. the debtor is entered because the debtor himself and his / her bank account are linked).



Account looked up by account name

The details on a bank statement will be available in the batch entry screen for the bank account. These details will be displayed, for each selected transaction, in the following options of the batch entry screen:

1. Underneath the icons the descriptions as entered or processed by the bank.
2. Description column.

These descriptions or details provide an important guide to identify and select the correct applicable account.

To allocate an account to a transaction by name:

1. Select a transaction.
2. Click on the Account column and enter a few characters of the descriptions. In this example, "*ba*" is entered. All the accounts containing "*ba*" is listed.
3. Select "*Bank charges*".



The account looked up by searching for the corresponding document

This way of allocating account to the transaction is only possible if there is a document (invoice / quote / credit note / purchase / purchase return / order).

If the transaction belongs to a journal entry, this option cannot be used.

To allocate an account to a transaction by document number:

1. Select a transaction. In this example, "*IN000003*" is selected. The details from the imported bank statement displays 2 key details. You can now choose to select either "*Document lookup*", "*Document lookup with amount*" or "L*ookup debtor*".

2. Right-click on the transaction line and select "*Document lookup*" or "*Lookup document with amount*" on the context menu. The document entry listing all invoices will be listed.



3. Select "*IN000003*" for "*Mr. AB Green*".

4. Double-click to transfer the selected "*Document*" to the "*Batch entry*" screen.

In the "*Lookup document*" or "*Lookup document with amount*":

- With the first option, the "*Document entry*" screen will be opened and the correct document can be searched for.

- With the second option, "*Lookup document with amount*", a document with a corresponding amount will be searched for.

You may use the filter options, to filter for a specific document. If the document you are searching for is still unposted, it will not be listed if "Posted" is selected. You may then select "All or "Unposted" options to list unposted documents.

With the double-click, the "*Open item selection*" screen will automatically be launched (if the Debtor account is set as an "*Open item*" account) . In the example of "*Mr. AB Green*", the transaction can be directly linked (matched) to the specific invoice.



The payment details and the invoice, (i.e. invoice "*IN000003*") is displayed. Since the 2,000.00 payment is more than the payment, you can select to link other outstanding invoices, e.g. "*INV001*" (Batch entry invoice) for the balance of the payment received.

The account looked up by searching for the Debtors / Creditors account

If a debtor or creditor name is in the details of the batch entry screen, you may select from the context menu to lookup a debtor or creditor account.

To allocate an account to a transaction by creditor account:

1. Select a transaction. In this example, "*PAYMENT ABC-OFFICE SUPPLIES*" is selected.

2. Right-click on the transaction line and select "*Lookup creditor*" on the context menu. The "*Creditor accounts*" listing all creditors (suppliers) will be listed.



3. Select "*ABC-Office supplies*".

4. Double-click to transfer the selected creditor account to the batch entry screen.

With the double-click, the "*Open item selection*" screen will automatically be opened (if the Creditor account is set as an "*Open item*" account. In the example of "*ABC-Office Supplies*", the payment transaction can be linked (matched) to the batch transactions or documents.



Select "*PU002*" (batch purchase) as the purchase transaction, for which this payment was made.

Press the Enter key and the linked transaction will updated in the "*Batch entry*" screen.

Account automatically selected as it is linked to the bank account number

It is also possible to link an account number to debtors/creditor/ledger account.
With this, transactions in the bank import are directly linked to the correct account. This linking can be done in several ways:

1. If the number of the bank account of a debtor or creditor is known, this can be entered into the details of the relevant debtor/ledger/creditor.
   The transactions with the same bank account number entered for the debtor / creditor will be linked to the correct account in the "*Account*" column.

2. It is also possible to link a bank account from a transaction. Stand on a transaction. The account (debtor, creditor or ledger) must be entered here for the first time.
   Then click the right mouse button and choose "*Link bank account*". With the next transaction from this account, the account will be filled in automatically.

Managing Bank Accounts and Account Bank References

When Bank statements are imported, it will automatically import all transactions into the Batch entry screen (combined Payments and Receipts journal). You need to allocate the transactions to the correct accounts, as the bank statement does not know which accounts in osFinancials5/TurboCASH5 is matched to items on

the bank statement.

osFinancials allows you to manage these references to specific accounts. When importing a bank statement, and the account links are correct, it will automatically allocate the bank statement transactions to the correct accounts.

When importing statements and these are not linked, e.g. new receipts, payments, etc., these will then be set to "*Empty*" in the Accounts column of the Bank accounts Batch entry screen.

To automate the process for allocating (selecting accounts) to an imported bank statement, please take not of the following settings:

General ledger accounts

- Bank References – This needs to be correctly entered on the Bank links tab. If this is correctly entered (edited), it will match the references as imported from bank statements.
- Tax (VAT / GST / Sales Tax) - If you are registered as a VAT / GST / Sales Tax Vendor, and VAT is applicable to the specific account, you need to link that account to the correct Input or Output Tax (VAT / GST / Sales Tax) account.

Debtor accounts

- Bank references - This needs to be correctly entered on the Bank accounts tab. If this is correctly entered (edited), it will match the references as imported from bank statements.
- Bank accounts – The Banking details for the Debtor (customer / client) account needs to be correctly maintained on the Accounting information tab of the Debtor account. This may be used to manage debit orders, refund debtors, etc. via the automated payments system. BIC (Bank Identifier Code) and IBAN (International Bank Account Number) accounts are also supported.

Creditor accounts

- Bank references - This needs to be correctly entered on the Bank accounts tab. If this is correctly entered (edited), it will match the references as imported from bank statements.
- Bank accounts – The Banking details of the creditor (supplier / vendor) account needs to be correctly maintained on the Accounting information tab. This may be used to pay creditors (suppliers) via the automated payments system. BIC (Bank Identifier Code) and IBAN (International Bank Account Number) accounts are also supported.

Account bank references - Details



Account bank references - List



Reference	Account	Description
BANK Charges ADMIN FEE	200000	Bank charges
CHAIRS	600010	Furniture & fittings @ cost
Capital	505000	Capital
DESK	600010	Furniture & fittings @ cost
FUEL	210010	Motor vehicles - Fuel & oil
PAYMENT	1MACDS	MAC Shop Decor Specialists
PAYMENT AB GREEN	1ABGRE	Mr. AB Green
PAYMENT ABC-OFFICE SUPPLIES	2ABCOS	ABC-Office-Supplies
PETTYCASH REPLENISHMENT	820000	Petty cash
Rent ERF 2192	220000	Rent
STATIONERY	230000	Stationery

Account bank references - Check



Account bank references - Batch entry - Match log tab

List the transactions in the batch

Click on the F8: List icon to print a list of the imported and allocated transactions in the unposted bank account batch.

To include Tax (VAT/GST/Sales tax) amounts in the List batch - Unposted batch report,you need to balance the batch first.

To do this, you need to go to F9:Process and choose the Balance batch.

It will generate balancing entries and include the Tax (VAT/GST/Sales tax) amounts on the List batch - Unposted batch report .


F:\osfinancials5-MERGE-1\plug_ins\reports\GENERAL\documents\batch.rep

List batch - Unposted batch

Batch name ABC-Payments
Alias (batch name) ABC-Bank-St.5

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/01	24042101	CHAIRS 1234567890202403303	G600-010 B810-000	T860-030	45,00	300,00	
2024/03/01	24042101	DESK 123456789020240301 3	G600-010 B810-000	T860-030	75,00	500,00	
2024/03/01	24042101	Capital Jack Daniels 12345678902024	G505-000 B810-000		0,00		5 000,00
					Total	800,00	5 000,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/16	24042101	PAYMENT AB GREEN IN000003 123456789	D1AB-GRE B810-000		0,00		2 000,00
2024/03/16	24042101	PAYMENT MAC Shop Decor Specialists	D1MA-CDS B810-000		0,00		1 000,00
					Total	0,00	3 000,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/30	24042101	PETTY CASH REPLENISHMENT 12345678902	B820-000 B810-000		0,00	100,00	
2024/03/30	24042101	WALTONS PENS AND PAPER STATIONERY 1	G230-000 B810-000	T860-020	30,00	200,00	
2024/03/30	24042101	ABC Service Station PETROL 12345678	G210-010 B810-000		0,00	150,00	
2024/03/30	24042101	PAYMENT ABC-OFFICE SUPPLIES 1234567	C2AB-COS B810-000		0,00	750,00	
2024/03/30	24042101	Rent ERF 2192 1234567890202403306	G220-000 B810-000	T860-020	75,00	500,00	
					Total	1 700,00	0,00

Date	Reference	Description	Account / Contra account	Tax	Tax amount	Debit	Credit
2024/03/31	24042101	Bank Charges ADMIN FEE 123456789020	G200-000 B810-000		0,00	45,00	
					Total	45,00	0,00

It is a good idea to list the batch, and check the entries on the batch thoroughly. If there are any errors, you may edit the batch, before posting the batch.

Post (Update) the transactions to the ledger

If all the transactions are correctly allocated to the correct accounts, the imported bank transactions can be posted (updated) to the ledger.

Click on the F6: Post icon.



Since a transaction is posted from this bank account to another bank account (e.g. Petty cash) is posted, the following confirmation message, is displayed:

> You are putting cash from a bank/cash directly to a bank/cash account! Do you wish to continue?
> Line : 24042101 PETTYCASH REPLENISHMENT 12345678902 810000 ABC-Bank to 820000 Petty cash

Click OK on the confirmation message. The "*Batch entry*" screen will automatically be closed.

The "*Bank statement options*" screen is displayed:



All the imported and processed bank statement transactions, which are posted (updated) to the ledger, will be listed.

Bank Import Check screen options

Before you close the "*Import bank statement - Check*" screen, you may delete a line, merge or split transactions.

Splitting transactions

If there any transactions on the "*Import bank statement - Check*" screen, you may split the transaction into two (2) or more entries.

You may need to do this, if a payment or receipt needs to be allocated to different accounts.

To do this on the "*Import bank statement – Check*" screen:

1. Click on the transaction to split.
2. Click in the Split button. You may also right-click and select the "*Split*" option on the context menu. The "*Split*" amount screen will be displayed.
3. Enter the amount for the amount to split. It will insert another transaction with the same details as the

selected transaction with the remaining amount.

4. Click OK. Repeat the process, if necessary.

If this is not done at this stage (on the "*Import bank statement – Check*" screen), you may add it later on the Batch entry screen for the Bank account.

To do this on the "*Batch entry*" screen:

1. Select the transaction and click on the ^N:Insert icon. In the blank row, enter the transaction details and the new amount.
2. On the selected transaction to split, over type it with required amount. Repeat as necessary.

Merge transactions

If there are a few transactions on the "*Import bank statement – Check*" screen, you may merge (consolidate) it into one (1) entry.

To do this on the "*Import bank statement – Check*" screen:

1. Press the Ctrl key and while holding your mouse down, click on the transactions to merge (consolidate).
2. Click in the Merge button. You may also right-click and select the "*Merge*" option on the context menu.

To do this on the Batch entry screen:

1. Select the transaction to be merged and over type the amount with the total of the transactions to be merged.
2. Select the transaction to be deleted and click on the ^D:Delete icon. Repeat, as necessary.

Batch entry – Context menu options

This context menu offers advanced options to facilitate the editing, assignment of transactions to accounts,

and management of imported transactions from bank statements within the "*Batch entry*" screen:



1. ^D:Delete: Remove selected transactions from the "*Batch entry*" screen.
2. Update bank account: Update references in the "*Reknr*" column to:
    - Bank links tab of Ledger accounts (Setup → Accounts).
    - Bank account references on the Bank accounts tab of debtor (customer/client) accounts (Debtors).
    - Bank account references on the Bank accounts tab of creditor (supplier/vendor) accounts (Creditors).
3. Lookup document: Locate a specific document using advanced search and filter options.
4. Lookup document with amount: Locate a specific document by amount using advanced search and filter options.
5. Lookup debtor: Find and locate existing debtor accounts. You may edit existing debtor accounts or create new ones if needed.
6. Lookup creditor: Find and locate existing creditor accounts. You may edit existing creditor accounts or create new ones if needed.
7. Link bank account from import to accounts: Update accounts with bank references from imported bank statements to ensure accurate transaction allocation.
8. Link all records with current account bank accounts : Update accounts with bank references from imported bank statements.
9. Show references for account: View, add, edit, or delete references for accounts, updating Bank links tab of ledger accounts and the Bank accounts tab of debtor and creditor accounts.
10. Select from account open item list: Display transactions on the "*Open item selection*" screen for the selected account to link transactions in the "*Batch entry*" screen.
11. Open item link: Launch the "*Open item*" screen for the selected account to select transactions or

manage links to transactions.

12. Search by amount: Search for transactions by amount.
13. Find with central search: Launch the Search (Investigator) feature on the Default ribbon, allowing efficient search for specific accounts, documents, transactions, and more within the Set of Books.
14. Match Ideal Bank @*@: A specific feature integrating iDEAL online payment method for payments or transactions within the Bank-import plugin.

Debtor account - Context menu options:

- Go to document: List the document grid with the selected document.
- Create Invoices / Credit notes: Create an invoice or a credit note for transactions imported from the bank statement if none is available.
- Payment divergence: Launch the Receive payment screen to process adjustments or receipt transactions if a payment recorded in the bank statement does not match any existing transaction in the accounts.

Creditor account - Context menu options:

- Create Purchases / Supplier returns: Create a purchase or a supplier return document for transactions imported from the bank statement if none is available.
- Payment divergence: Launch the Receive payment screen to process adjustments or receipt transactions if a payment recorded in the bank statement does not match any existing transaction in the accounts.

Supported bank import file formats

If your bank or financial institution's available file formats, is not currently supported (cannot be imported in this Bank import plugin), please send us one downloaded file, and we will implement support for your bank or financial institution's bank statement format.

Country specific formats

Country	*File*	*Comment 1*	*Remarks*
Belgium			
BE	*Fortis bank*	*Comma separated*	

BE	*ING*	*Comma separated*	
BE	*KCB*		
BE	*KCB*	*Comma separated*	
BE	*Paypal*		
BE	*Recordbank*	*Comma separated*	
France			
FR	*INT-ofx general format*	*OFX [Open Financial eXchange file]*	
Netherlands			
NL	*ABN-AMRO*	*Tab delimited*	
NL	*Afterpay*		
NL	*Fortis bank*	*Tab delimited*	
NL	*Frieslandbank*	*Comma separated*	
NL	*Icepay*		
NL	*iDeal*	*Comma separated*	*Download from Dashboard*
NL	*iDeal*	*Comma separated*	*Email from dashboard (rapport)*
NL	*ING*	*Comma separated*	
NL	*Mastercard Creditcard*	*TSV*	
NL	*MCG*		*New*
NL	*MT940*	*General format*	
NL	*MT940*	*General format*	*On booking date*
NL	*MT940 Rabobank*		
NL	*MT940 SNS bank*		
NL	*MT940 Triodos bank*		

NL	*Multi Safe pay*	*MT940 (General format)*	
NL	*Paypal*		
NL	*Postbank*	*Comma separated (CSV)*	
NL	*Postbank*	*Comma separated (CSV)*	*New*
NL	*Rabobank*	*Comma separated (CSV)*	*Fixed length*
NL	*Rabobank*	*Comma separated (CSV)*	*ideal payment id*
Spain			
SP	*SP-MT940 Triodosbank*		
United Kingdom			
UK	*UK-HSBC UK Transaction File*		
United Sates of America			
USA	*Bank of America – Quicken QIF 4 digit*	*QIF [Quicken Interchange Format]*	
USA	*Bank of America – Comma separated*	*Comma separated (CSV)*	

International (universal) formats

In addition to a various file formats for the Belgium, Netherlands, France, Spain, United Kingdom and United States of America environments, the following file formats are currently supported for the international banking environments:

Country	*File*	*Comment 1*	*Comment 2*	*Remarks*
INT	*INT-MT940 (algemeen formaat (SEPA proof))*			
	INT-PayPal			
	INT-OFC/OFX standaard	*OFC [Open Financial Connectivity file] /* *OFX [Open Financial eXchange file]*		

INT-Simple comma separated column Date dd/mm/yyyy, description, Amount . is thousandseperator	*Simple comma seperated*	*Comma separated (CSV)*
INT-OFX bankexport	*OFX [Open Financial eXchange]*	
INT-QIF format (mm-dd-yyyy)	*QIF [Quicken Interchange Format]*	
INT-OFC / OFX standaard 2	*OFC [Open Financial Connectivity file] /* *OFX [Open Financial eXchange file]*	
INT 053 CAMT file format		

T-Account View - Transactions Imported Bank Statement

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, printed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select "*Trial balance*" report type and click on the Report button.
3. On the "*Trial balance*", select the "*B810-000 ABC – Bank*" account.
4. Double-click on the selected account; or right-click and select Show details on the context menu.
5. Click on the following to get specific views of transactions:
    - Batch id (e.g. 11 automatically generated). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. G505-000 Capital account, B810-000 ABC - Bank, D1AB-GRE Mr. AB Green, D1MA-CDS MAC Shop Decor Specialists), etc. This will list the transactions for a specific account.
    - Date – This will list the transactions for a specific date. If you double-click on a date, the "*From date"* and "*To date*" will be changed to the selected date.

T-Account view of transactions in the Bank account

After posting the transactions in the Receipts journal, the transactions should display as follows in the T-Account viewer:

Batch view



Show contra – You may select (tick) this option to view the Contra account code and account description in the first two (2) columns of the T-Account viewer. This will not print on the T-account viewer report, but will be included in the Exported file (which you can open in a spreadsheet).

BANK ACCOUNT - Account view

ABC – Bank

B810000 ABC-Bank				Debit	Credit
11 ABC-Bank-St.5	2024/03/01	*******	CHAIRS 1234567890202403303 .		345,00
11 ABC-Bank-St.5	2024/03/01	*******	DESK 123456789020240313 .		575,00
11 ABC-Bank-St.5	2024/03/01	*******	Capital Jack Daniels 12345678902024 .	5 000,00	
11 ABC-Bank-St.5	2024/03/16	*******	PAYMENT AB GREEN IN000003 123456789 .	2 000,00	
11 ABC-Bank-St.5	2024/03/16	*******	PAYMENT MAC Shop Decor Specialists .	1 000,00	
11 ABC-Bank-St.5	2024/03/30	*******	PETTYCASH REPLENISHMENT 12345678902 .		100,00
11 ABC-Bank-St.5	2024/03/30	*******	WALTONS PENS AND PAPER STATIONERY 1 .		230,00
11 ABC-Bank-St.5	2024/03/30	*******	ABC Service Station PETROL 12345678 .		150,00
11 ABC-Bank-St.5	2024/03/30	*******	PAYMENT ABC-OFFICE SUPPLIES 1234567 .		750,00
11 ABC-Bank-St.5	2024/03/30	*******	Rent ERF 2192 1234567890202403306 .		575,00
11 ABC-Bank-St.5	2024/03/31	*******	Bank Charges ADMIN FEE 123456789020 .		45,00
			Totals	8 000,00	2 770,00

T-Account view of Receipt transactions in the Bank account

The credit transactions in the "*Amount entry*" column and "*Receipt*" column of the "*Batch entry*" screen for the "*ABC-Bank*" is as follows:

RECEIPT TRANSACTIONS – Account view

Credit transactions in the Debtor's ledger:

Mr. AB Green

D1ABGRE Mr. AB Green

				Debit	Credit
11	2024/03/16	24042101	PAYMENT AB GREEN IN000003 123456789		2 000,00
ABC-Bank-St.5			.		
			Totals		2 000,00

MAC Shop Decor Specialists

D1MACDS MAC Shop Decor Specialists

				Debit	Credit
11	2024/03/16	24042101	PAYMENT MAC Shop Decor Specialists		1 000,00
ABC-Bank-St.5			.		
			Totals		1 000,00

Credit transactions in the General ledger:

Capital

G505000 Capital

				Debit	Credit
11	2024/03/01	24042101	Capital Jack Daniels 12345678902024		5 000,00
ABC-Bank-St.5			.		
			Totals		5 000,00

T-Account view of Payment transactions in the Bank account

The debit transactions in the "*Amount entry*" column and "*Payment*" column of the "*Batch entry*" screen for the "*ABC-Bank*" is as follows:

PAYMENT TRANSACTIONS – Account view

Debit transactions in the Creditor's ledger:

ABC-Office-Supplies

C2ABCOS ABC-Office-Supplies

				Debit	Credit
11	2024/03/30	24042101	PAYMENT ABC-OFFICE SUPPLIES 1234567	750,00	
ABC-Bank-St.5			.		
			Totals	750,00	

Debit transactions in the General ledger:

Furniture and fittings @ cost

G600010 Furniture & fittings @ cost				Debit	Credit
11 ABC-Bank-St 5	2024/03/01	24042101	CHAIRS 1234567890202403303 .	300,00	
11 ABC-Bank-St 5	2024/03/01	24042101	DESK 1234567890202403013 .	500,00	
			Totals	800,00	

Bank charges

G200000* Bank charges				Debit	Credit
11 ABC-Bank-St 5	2024/03/31	24042101	Bank Charges ADMIN FEE 123456789020 .	45,00	
			Totals	45,00	
				45,00	

Motor vehicles - Fuel and oil

G210010* Motor vehicles - Fuel & oil				Debit	Credit
11 ABC-Bank-St 5	2024/03/30	24042101	ABC Service Station PETROL 12345678 .	150,00	
			Totals	150,00	

Rent

G220000* Rent				Debit	Credit
11 ABC-Bank-St 5	2024/03/30	24042101	Rent ERF 2192 1234567890202403306 .	500,00	
			Totals	500,00	

Stationery

G230000* Stationery				Debit	Credit
11 ABC-Bank-St 5	2024/03/30	24042101	WALTONS PENS AND PAPER STATIONERY 1 .	200,00	
			Totals	200,00	

Petty cash

B820000 Petty cash

				Debit	Credit
11 ABC-Bank-St.5	2024/03/30	24042101	PETTYCASH REPLENISHMENT 12345678902 .	100,00	
			Totals	100,00	

Input Tax – Standard rate - 15%

T860020 Input VAT - Standard rate -15%

				Debit	Credit
11 ABC-Bank-St.5	2024/03/30	*******	WALTONS PENS AND PAPER STATIONERY 1 .	30,00	
11 ABC-Bank-St.5	2024/03/30	*******	Rent ERF 2192 1234567890202403306 .	75,00	
			Totals	105,00	

Input Tax – Capital goods - 15%

T860030 Input VAT - Capital goods -15%

				Debit	Credit
11 ABC-Bank-St.5	2024/03/01	*******	CHAIRS 1234567890202403303 .	45,00	
11 ABC-Bank-St.5	2024/03/01	*******	DESK 1234567890202403013 .	75,00	
			Totals	120,00	

Accounting equation

RECEIPTS

Debits = Credits

Debit transactions in the General ledger (i.e . Bank account).

=

Credit transactions in the General ledger (i.e. Capital account) + Debtor's ledger (i.e. individual Debtor accounts).

PAYMENTS

Debits = *Credits*

Debit transactions in the General ledger (i.e. *Petty cash +* *Furniture and fittings +* *Expenses +* *Tax (Input VAT/GST/Sales tax)) +* *Creditor's ledger (i.e. individual Creditor accounts.*

=

Credit transactions (i.e. payment transactions from the *Bank account).*

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Bank import plugin - Petty cash transactions (Manual entry)

Bank Import plugin Petty Cash transactions

Since the Petty Cash account is included in the templates of osFinancials5/TurboCASH5 as a Bank account type. It is recommended that Petty Cash accounts should be added or created as a Bank account type. Once the BankImport plugin is activated, the Petty cash payments batch and receipts batch will be combined into one "*Batch entry*" screen.

Petty cash payments should be used as a bank account. If it is used as a normal General ledger – Balance sheet account, it could cause problems on the Tax Reports (Input VAT/GST/Sales tax).

Entering your petty cash payments (Manual entry)

There are basically two (2) ways to capture the petty cash transactions:

- Enter the transactions manually from your petty cash slips or petty cash vouchers.
- Importing the transactions from a petty cash register as a Comma Separated Value (*.csv) file as a delimited file import.

For the purpose of this example, we assume that you have paid the following expenses from your petty cash:


Handyman Hardware Store
Petty Cash Voucher No. PCV001
Date: 31 March 2024
Waltons - Paper (VAT Incl.) ------4600
Total: ------46.00
Account: Stationery - Acc 230
Petty Cashier: Authorised:


Handyman Hardware Store
Petty Cash Voucher No. PCV002
Date: 31 March 2024
ABC Service Station - Fix Puncture ------1000
Total: ------1000
Account: Motor Vehicle Repairs - Acc 210-020
Petty Cashier: Authorised:

To enter your petty cash payment transactions:

1. Go to the Default ribbon and select Cash/Bank entry . The "*Bank statements options*" screen will list your previous processed transactions.



2. Select the Petty cash as the "*Bank account*" and click Open.
3. Enter the alias (batch name) in the "*Change alias"* field. In this example, enter *''PettyCash2403''* to indicate that the Petty cash of March 2024 was entered in this Petty cash payments batch.

The alias option allows you to identify a batch by a unique name. You will be able to select the batch by alias or batch name if you need to reverse the posted batch or import a posted batch.



4. Click on the F10:Setup icon to set your batch up. This is a once-off action, unless your requirements change. The *"Options for this batch"* screen is displayed:



The contra account is by default set to the Bank account.

You cannot change this in the Payments journal or Petty cash Payments journal.

5. Once setup; click on the Advanced tab.



6. Leave all fields blank, and make sure that the default option, "*Account lookup type*", is set to "*All*" for this exercise.

7. Once setup; click OK. You are now ready to record your first petty cash payment.

8. Capture your petty cash vouchers from your petty cash voucher book or from your requisitions. Use your petty cash voucher number as the reference number.

Ref. no.	*Date*	*Description*	*Account*	*Tax*	*Amount*
PCV001	*2024/03/31*	*Paper - Waltons*	*Stationery*	*Input Tax - 15%*	*46.00*
PCV002	*2024/03/31*	*Fix puncture - ABC Service Station*	*Maintenance*	*No tax*	*10.00*

9. After capturing your first two petty cash payment vouchers, the Petty cash payments journal is displayed as follows:



The F5: Balance icon is not available on the "Batch entry" screen for the imported transactions form your bank statements.

Balancing entries will automatically be generated for the imported transactions form your bank statements when you post (update) the imported bank statement transactions to the ledger.

Posting the petty cash batch

Once you have completed entering these petty cash payments, and you are sure they are correct, you may proceed to finalise the batch. The recommended process, is as follows:

1. Click on the F8:List icon to print a list of the transactions in the batch.

To include Tax (VAT/GST/Sales tax) amounts in the List batch - Unposted batch report,you need to balance the batch first.

To do this, you need to go to F9:Process and choose the Balance batch.

It will generate balancing entries and include the Tax (VAT/GST/Sales tax) amounts on the List batch - Unposted batch report .



> *It is recommended that the source documents (e.g. petty cash vouchers and/or invoices, slips, etc. received from suppliers, etc.) be attached to this List of the transactions and that it be retained for record and audit purposes.*

2. Click on the F6:Post icon to post (update) the batch to the ledger. Posting the transactions will automatically generate the necessary balancing entries. The "*Batch entry*" screen will automatically be closed. The "*Bank statement options*" screen is displayed:



3. All the imported and processed petty cash transactions, which are posted (updated) to the ledger, will be listed.

4. Click Close.

T-Account view of transactions

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.

2. Select "*Trial balance*" report type and click on the Report button.

3. On the "*Trial balance*", select the "*B820-000 Petty cash*" account.

4. Double-click on the selected account; or right-click and select Show details on the context menu.

5. Click on the following to get specific views of transactions:

    - Batch id (e.g. 32 automatically generated). This will list only the transactions for a specific batch (journal).

- Account code (e.g. B820-000 Petty cash, G210-020 Motor vehicle - Maintenance G230-000 Stationery, T860-020 Input Tax Standard - 15%). This will list the transactions for a specific account.
- Date - This will list the transactions for a specific date. If you double-click on a date, the “From date” and “To date” will be changed to the selected date.

After posting the transactions in the Petty cash journal, the transactions should display as follows in the T-Account viewer:

Batch view



Show contra - You may select (tick) this option to view the Contra account code and account description in the first two (2) columns of the T-Account viewer. This will not print on the T-account viewer report, but will be included in the Exported file (which you can open in a spreadsheet).

Account view

Debit transactions in the General ledger:

Motor vehicles - Maintenance

G210020* Motor vehicles - Maintenance

				Debit	Credit
32 Petty cash	2024/03/31	PCV002	ABC-Service Station - Fix puncture .	10,00	
			Totals	10,00	

Stationery

G230000* Stationery

				Debit	Credit
32 Petty cash	2024/03/31	PCV001	Waltons - Paper .	40,00	
			Totals	40,00	

Input VAT – Standard rate - 15%

T860020 Input VAT - Standard rate -15%

				Debit	Credit
32 Petty cash	2024/03/31	******	Waltons - Paper .	6,00	
			Totals	6,00	

Credit transactions in the General ledger

Petty cash

B820000 Petty cash

				Debit	Credit
32 Petty cash	2024/03/31	******	Waltons - Paper .		46,00
32 Petty cash	2024/03/31	******	ABC-Service Station - Fix puncture .		10,00
			Totals		56,00

Accounting equation

Debits = *Credits*

=

Debit transactions (i.e. Expenses + Tax (Input VAT/GST/Sales tax)).

Credit transactions (i.e. payment transactions from the *Petty cash account).*

Created with the Standard Edition of HelpNDoc: Create HTML Help, DOC, PDF and print manuals from 1 single source

Bank import plugin - Petty cash transactions (Import - CSV)

Introduction to Petty Cash

Receipt and Payment batch journal – Bank accounts

The use of cheques or electronic transfers (banking transactions) should be used for all transactions. The handling of cash should be limited as far as possible. Any amounts received from debtors (customers / clients) for cash sales or payments on accounts, should be banked as soon as possible.

These cash received by a business, should not be used for purchases, etc.

Cash, if not controlled and safeguarded properly, will create a climate for theft and fraud.

Any cash and payments received should be deposited in the bank account of the business. In osFinancials5/TurboCASH5 the receipts should be recorded in the Receipts batch (journal).

Any payments made should be paid out of the bank account of the business. In osFinancials5/TurboCASH5 the payments should be recorded in the Payments batch (journal).

Receipt and Payment batches - Petty Cash

A business may need to pay cash for smaller items and items needed urgently. For this reason, a business may need to keep a certain amount of cash (petty cash float) on hand to pay for these smaller necessary or urgent purchases.

Petty cash is a minimum amount of cash kept on hand for small purchases or reimbursements.

Petty cash money and payments or reimbursements must be safeguarded and properly documented to ensure that theft and fraud do not happen.

Petty cash payments (reimbursements) may be handled in the following:

- Employees may be required to fill in a form (e.g. Petty cash voucher) to receive the cash from the petty

cash. Directly after the purchase, the employee must submit a receipt or acceptable supporting documentation as proof of the purchase and return any change if applicable.

- Employees may be asked to make purchases themselves and then get reimbursed from the fund after submitting a receipts and/or acceptable supporting documentation as proof of the purchase.

The Petty cash receipts batch is hardly ever used. Any Petty cash float and/or replenishment is recorded in the Payment batch of the bank account from which the Petty cash float is recorded.

All petty cash payments or reimbursements is recorded in the Petty Cash Payments batch.

Petty cash guidelines

Some guidelines for using Petty cash, is as follows:

1. Appointing a Petty cashier – Only one person may have assess to the Petty cash. The petty cash cashier, must make sure that nobody else has access to the cash.
2. The petty cashier should be responsible for any cash shortages or a lack of receipts and/or acceptable supporting documentation as proof of the purchase.
3. Calculating the amount of float – The petty cash float should not have large amounts. It should be calculated for the average petty cash expenses for a period, monthly, fortnightly or weekly according to the needs of the business.
4. Another person needs to be appointed to check, on a regular basis, in the presence of the petty cashier, that the petty cash is correct.
5. Clear guidelines or policies and limits:
    a) Purchases or reimbursements from the Petty cash should only be allowed for valid business expenses (not anything else which are regarded as private expenses).
    b) Receipts and/or acceptable supporting documentation as proof of the purchase or reimbursement must be submitted.
    c) Restrict the Petty cash payments or reimbursements to specific employees.
    d) Implement a clear list of allowed purchases or reimbursements.
    e) Limit the amount for which purchases reimbursed.
    f) Make the petty cash guidelines and policies available to all employees.
6. If Tax (VAT/GST/Sales tax) is charged on a reimbursed purchase, the Tax should also be recorded as Input tax.

Petty cash can be recorded in in a pre-printed Petty cash register, or done in a spreadsheet. The spreadsheet can be used to record and control petty cash payments or reimbursements as well as to import the transactions as a Comma Separated Value (*.csv) – Tab delimited file into osFinancials5/TurboCASH5.

Recording Petty Cash transactions

The following options are available to record petty cash transactions:

1. Manually enter the transactions in a batch.
2. Petty Cash Register - Import the Petty cash transactions from Comma Separated Value (*.csv) – Tab delimited file into batches. This is very useful for bringing in external data without having to recapture it. This allows us to easily develop add on systems in Spreadsheet format and to synch them with osFinancials5/TurboCASH5.

Petty Cash Register

Depending on your requirements, the petty cash register may be designed for the necessary controls to keep accurate track cash in the petty cash and moneys paid for expenses / reimbursements.

The Petty Cash Register, in a spreadsheet format, can be used to implement the necessary controls and keep track of your expenses, payments and reimbursements. Transactions in the Petty Cash Register can be saved in a comma separated value (*.csv) -Tab delimited file format. These transactions can then be imported into a Petty Cash payments batch and updated to the ledger.

Delimited file import

The CSV format has been around for many years as a means of transferring data between datasets.

osFinancials5/TurboCASH5 can import CSV files into batches. This is very useful for bringing in external data without having to recapture it. This allows us to easily develop add on systems in Spreadsheet format and to synch them with osFinancials5/TurboCASH5.

OpenOffice 4 / LibreOffice 5

There are a number of contenders for the Office Software Market, Microsoft Office, OpenOffice LibreOffice. I have found OpenOffice to be the best at handling CSV files. You can use their packages, but I sincerely recommend you take advantage of the FREE Download of Open Office at *www.openoffice.org* and use OpenOffice for working with the data you are going to import into osFinancials5/TurboCASH5.

LibreOffice can be downloaded at *http://www.libreoffice.org/*

Get the Data Ready in OpenOffice / LibreOffice

osFinancials5/TurboCASH5 is particular about the CSV format that it will accept. osFinancials5/TurboCASH5 accepts the Tab delimited csv files.

If the CSV file is not EXACTLY the format that osFinancials accepts it will generate an error:

"List index out of bounds (3)".

If the Date is not entered as "31/03/2024", and is entered as "2024/03/31", depending on your system settings, and the delimited file import in osFinancials is imported, the dates may be imported as 1899/12/31. Irrespective of your operating system's date and regional settings, if the date is entered as "31/03/2024" the date should be, by default, be imported correctly according to the format of your operating system's date and regional settings.

Petty Cash Register Template

You may find these sample templates in " *...\bin\Tutorials\PETTY-CASH-TEMPALTES* " folder. These templates were created in the Open Document Spreadsheet format used in LibreOffice Calc. It consists of the following two folders:

- BATCHES - This contains the CSV file (PETTYCASH-2024-03.csv) generated by save the CVS tab of the Petty cash register in the TEMLATES folder. This CSV file is used to use the "*Import Delimited file*" option in the "*Process options for this batch*".
- TEMPLATES - This contains the sample Petty cash register file (PETTYCASH-TEMPLATE.ods). This sample file is used to generate transactions in the Petty cash register to save the CVS tab of the Fixed Asset register in the BATCHES folder.

This sample Template can be used in normal Petty cash batches (Batch entry) as well as in Petty cash bank accounts using the Bank Import plugin.

Open the PETTYCASH-TEMPLATE.ods

Open the PETTYCASHTEMPLATE.ods (Open Document Spreadsheet).

Petty Cash Register Template

Open the Petty Cash Register Template

Open the PETTYCASHTEMPLATE.ods (Open Document Spreadsheet).



Enter the name of your business and the period.

The default sheet (Sheet1), consists of Receipts and Payments / Reimbursements:

1. Receipts – Column A – D - The Petty cash advances and replenishment as well as any shortages refunded should be entered in these columns. The transactions for the Petty Cash advances and replenishments, does not need to be recorded in TurboCASH, since these will be recorded in the Payments batch of the Bank account from which the petty cash float amount is paid.

2. Payments / Reimbursements – Column E – H – All payments or reimbursements must be entered in these columns. These transactions must be recorded in the Petty Cash batch (journal). These transactions will be updated in the CSV sheet. Once the transactions is added, the CSV sheet, may be saved as a comma separated value – Tab delimited file type. The transactions may then be imported into osFinancials5/TurboCASH5 as a delimited file import.



To add more transactions, you may select a row, e.g. Row 9, and insert the required rows.

Balancing the Petty Cash

Petty cash funds must be periodically checked to ensure that the balance of the petty cash fund is correct.

The petty cash float must always be in balance with the cash on hand plus the receipt or acceptable supporting documentation as proof of the purchase.

If it does not balance and you have checked that you have counted the cash at hand correctly, and that the petty cash payment transactions are entered correctly.

If it is correctly counted and entered, a difference indicates a surplus or a shortage:

- *Surplus - This is where the amount in the petty cash, and the petty cash vouchers and/or slips exceeds the amount of the float.*
- *Shortage - This is where the amount in the petty cash, and the petty cash vouchers and/or slips is less than the amount of the float.*

Updating the CSV sheet to a Tab delimited file

Once the transactions is added in Sheet1, click on the CSV sheet.

To add more transactions in the CSV sheet, as added in Sheet1, copy the formulas in Columns A – H to the next rows.

This will update the CSV sheet with the transactions as entered in the Payments / Reimbursements – Column E – H of Sheet1.



The values of the columns is as follows:

1. Column A – Reference =Sheet1.E8 Reference as entered in column E Row 8 of Sheet1.

2. Column B – Date =Sheet1.F8 the Date as entered in column F Row 8 of Sheet1.

> *If the Date is not entered as "31/03/2024", and is entered as "2024/03/31", depending on your system settings, and the delimited file import in TurboCASH is imported, the dates may be imported as 1899/12/31. Irrespective of your operating system's date and regional settings, if the date is entered as "31/03/2024" the date should be, by default, be imported correctly according to the format of your operating system's date and regional settings.*

3. Column C – Description =Sheet1.G8 the Description as entered in column G Row 8 of Sheet1.

4. Column D – Account = The default expense / purchase account which will be imported into the batch.

> *You may enter an existing default account, e.g. "G999-000" – Suspense account or a "Petty cash control" account (added in Accounts (Default ribbon)). Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you need to select the correct account for each transaction.*

> *You need to type the account type prefix e.g. "G" followed by the main account code e.g. "230" and the sub-account, separated by a hyphen "-" for example, "G230-000" for the Stationery account.*
>
> *Income and expense accounts (starting with the "G" prefix for General ledger accounts) are prefixed with an "*" (asterisk). If the "*" asterisk is also entered in this column, the account will not be imported into the delimited file batch.*

> *You may type the correct account in this column from the printed Chart of accounts from Reports → Ledger → Listing (Reports ribbon), e.g. "G230-000" – Printing, Postage and Stationery account. Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you can check and confirm the correct account for each transaction.*

5. Column E – Contra account – The default value is "*T*". Do not delete this column and leave the value as "*T*".

6. Column F – Tax account – The default value is "*T*". Leave the value as "*T*", unless Tax (VAT/GST/Sales tax) is applicable to the transaction.

> *You may leave the default as "T".*
>
> *Once the csv file (Delimited file import) of the petty cash transactions in the petty cash batch is imported, you need to select the correct tax account for each transaction on which Tax (VAT/GST/Sales tax) is applicable.*

> *If Tax (VAT/GST/Sales tax) is applicable to the transaction, you may type the account type prefix e.g. "T" followed by the main account code e.g. "950" and the sub-account, separated by a hyphen "-" for example, "T860-015" for the Input VAT – Standard rate – 15% account.*

7. Column G – Amount – =VALUE(Sheet1.H8) – The amount of the transaction (expense / payment / reimbursement).

> *The amount should be a positive amount, since the transactions need to be imported as a debit transaction into the Petty cash batch (journal).*
>
> *If the amount is negative (prefixed by a minus "-" sign) amount, it will be imported as a credit amount into imported into the delimited file batch.*

8. Column H – The default value is "*FALSE*". Once the transactions is imported, and you select an account (i.e. Debtor (customer/client), Creditor (supplier/vendor) and/or a Ledger account), which is set as Open item account and the account has processed transactions to be linked, the "*Open item selection*" screen will be displayed.

Save the CSV sheet to a Tab delimited file

Once the transactions is updated in the CSV sheet, the CSV sheet, need to be saved as a comma separated value – Tab delimited file type. The transactions may then be imported into osFinancials as a delimited file import.

> *Before proceeding with the next step, remember to SAVE the PETTYCASH-TEMPLATE.ods (Open Document Spreadsheet).*

To save the Transactions in the CSV tab to a Tab delimited file:

1. On the "*PETTYCASHTEMPLATE.ods*" (Open Document Spreadsheet), click on the CSV sheet, if not already selected.
2. Select the rows and columns on the CSV sheet.



3. Enter the name for the Batch file, (e.g. "*PettyCASH-2024-03*". In this example, it will indicate the petty cash transactions for "*March 2016*".

4. Save as type: - Select the "*Text CSV (.csv) (*.csv)*" as the file type. The "*Edit filter settings*" field (tick box) will be activated for the "*Text CSV (.csv)*" file type.

> *It is important to select (tick) the "Edit filter settings" field. This will launch the "Export Text file" screen on which the TAB field delimiter needs to be selected.*

5. Edit filter settings – Tick this option.

6. Click Save.



7. On the "*Confirm File Format*" screen, click Use Text CSV Format button. The "*Export Text File*" screen is displayed:



8. Select the following options:

   a) Field delimiter: - Select {TAB}.

   > *If this option is not selected, the delimited file import in osFinancials will fail. The Tab delimited CSV import file is required by osFinancials5/TurboCASH5.*

   b) Save cell content as shown – Select (tick) this option. If this option is not selected (not ticked), formula values will be imported and may produce REF (Reference) errors.

9. Click the OK button. LibreOffice will produce a Warning message that only the active sheet was saved (CSV sheet). A similar warning message is as follows:

   Warning saving the document PETTYCASH-2024-03:
   Only the active sheet was saved.

10. Click the OK button.

11. Close the "*PettyCASH-2024-03.csv*" file.

> *If the csv file is opened (active) on your system, the following error message will be displayed:*
>
> *"Cannot open file "...\Spreadsheets\PettyCASH\PettyCASH-2024-03.csv". The process cannot access the file because it is being used by another process.".*
>
> *Close the file in which it is open, e.g. Excel / OpenOffice / LibreOffice and import the file again.*

Delimited File Import - CSV file into osFinancials5/TurboCASH5

Once the transactions is saved as a comma separated value – Tab delimited file type, the petty cash transactions can be imported into osFinancials5/TurboCASH5 as a delimited file import.

To Import Petty Cash Transactions from the CSV - Tab delimited file:

1. Go to the Default ribbon and select Cash/Bank entry .The "*Bank statements options*" screen will list your previous processed transactions.



2. .Select the Petty cash as the "*Bank account*" and click Open.

3. Enter the alias (batch name) in the "*Change alias"* field. In this example, enter *''PettyCash2403''* to indicate that the Petty cash of March 2024 was entered in this Petty cash payments batch.

> *The alias option allows you to identify a batch by a unique name. You will be able to select the batch by alias or batch name if you need to reverse the posted batch or import a posted batch.*



4. Click on the F10:Setup icon to set your batch up. This is a once-off action, unless your requirements change. The *"Options for this batch"* screen is displayed:



The contra account is by default set to the Bank account.

You cannot change this in the Payments journal or Petty cash Payments journal.

On the Standard tab, check that the "Consolidate balancing" option, is not selected.

If the "Consolidate balancing" option, is selected the following error message will be displayed:



An information message will be displayed:

> Consolidating lines and using tax will mess up your tax report! Please make sure you do not use tax or do not consolidate lines!

Click OK and remove the tick from the "Consolidate balancing" field.

5. Once setup; click on the Advanced tab.



6. Leave all fields blank, and make sure that the default option, "*Account lookup type*", is set to "*All*" for

this exercise.

4. Click on the OK button.

5. Click on F9:Process icon and select the "*Delimited file import*" option and click OK.



The "*Open*" screen will be displayed.



7. Navigate and select the Petty cash batch file (e.g. "*PETTYCASH-2024-03.csv*") to import and click Open.

Warning saving the document PETTYCASH-2024-03:

Only the active sheet was saved.



8. After importing the petty cash transactions, you may need to change / edit the imported petty cash transactions:

    a) Reference – The Petty cash voucher or reference number as entered in Column E of Sheet1 and updated in Column A of the CSV sheet in the Petty Cash Register.

    b) Date – The date as entered in Column F of Sheet1 and updated in Column B of the CSV sheet in the Petty Cash Register.

> *If the Date (in Sheet1 of the Petty Cash Register) is not entered as "31/03/2024", and is entered as "2024/03/31", depending on your system settings, and the delimited file import in TurboCASH is imported, the dates may be imported as 1899/12/31. Irrespective of your operating system's date and regional settings, if the date is entered as "31/03/2024" the date should be, by default, be imported correctly according to the format of your operating system's date and regional settings.*

    c) Description – The descriptions as entered in Column G of Sheet1 and updated in Column C of the CSV sheet in the Petty Cash Register.

    d) Account – The account code as entered in Column D of the CSV sheet in the Petty Cash Register. Each payment or reimbursement transaction needs to be linked (allocated) to the correct account.

> *If you have entered an existing default account, e.g. "G999-000" – Suspense account or a "Petty cash control" account (added in Accounts (Default ribbon)). Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you need to select the correct account for each transaction.*

> *You need to type the account type prefix e.g. "G" followed by the main account code e.g. "230" and the sub-account, separated by a hyphen "-" for example, "G230-000" for the*

Stationery account.

Income and expense accounts (starting with the "G" prefix for General ledger accounts) are prefixed with an "" (asterisk). If the "*" asterisk is also entered in this column, the account will not be imported into the delimited file batch.*

You may type the correct account in this column from the printed Chart of accounts from Reports → Ledger → Listing (Reports ribbon), e.g. "G230-000" – Stationery account. Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you can check and confirm the correct account for each transaction.

e) Tax account – The correct tax account (code) must be selected, if Tax (VAT / GST / Sales tax) is applicable to the transaction. The Tax account code as entered in Column F of the CSV sheet in the Petty Cash Register.

The tax column will only be displayed if the "No Tax" option is left blank (not ticked) in the F10:Setup option in the Batch entry screen.

If no Tax (VAT/GST/Sales Tax) is applicable to all the transactions in the Petty Cash Register; or if you are not registered for Tax (VAT/GST/Sales Tax) you may select to hide the tax column will only be displayed if the "No Tax" option is left blank (not ticked) in the F10:Setup option in the Batch entry screen.

f) Debit – Positive amounts – The amount of the transaction (expense / payment / reimbursement) as entered in Column H of Sheet1 and updated in Column G of the CSV sheet in the Petty Cash Register.

g) Credit – Negative amounts –

The amount should be a positive amount, since the transactions need to be imported as a debit transaction into the Petty cash batch (journal).

If the amount is negative (prefixed by a minus "-" sign) amount, it will be imported as a credit amount into imported into the delimited file batch.

h) Open item – If an account (i.e. Debtor (customer/client), Creditor (supplier/vendor) and/or a Ledger account), which is set as Open item account and the account has processed transactions to be linked, the "*Open item selection*" screen will be displayed. On this "*Open item selection*" screen, you may select to link a payment transaction to a credit transaction, ode a receipt (deposit) transaction to a debit transaction.

Posting the petty cash batch

Once you have completed entering these petty cash payments, and you are sure they are correct, you may proceed to finalise the batch. The recommended process, is as follows:

1. Click on the F8:List icon to print a list of the transactions in the batch.

> ***To include Tax (VAT/GST/Sales tax) amounts in the List batch - Unposted batch report,you need to balance the batch first.***
>
> ***To do this, you need to go to F9:Process and choose the Balance batch.***
>
> ***It will generate balancing entries and include the Tax (VAT/GST/Sales tax) amounts on the List batch - Unposted batch report .***

2. Click on the F5:Balance icon. This will generate balancing transactions to the Petty cash bank account.



3. Click on the F8:List icon to print a list of the transactions in the unposted batch.

> ***To include Tax (VAT/GST/Sales tax) amounts in the List batch - Unposted batch report,you need to balance the batch first.***
>
> ***To do this, you need to go to F9:Process and choose the Balance batch.***
>
> ***It will generate balancing entries and include the Tax (VAT/GST/Sales tax) amounts on the List batch - Unposted batch report .***



4. Click on the F6:Post icon to update (post) the transactions to the ledger.

T-Account-view of Transactions

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select "*Trial balance*" report type and click on the Report button.
3. On the "*Trial balance*", select the "*B820-000 Petty cash*" account.
4. Double-click on the selected account; or right-click and select Show details on the context menu.
5. Click on the following to get specific views of transactions:
    - Batch id (e.g. 38 automatically generated). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. B820-000 Petty cash, G210-030 Repairs G230-000 Stationery, T860-020 Input Tax Standard - 15%). This will list the transactions for a specific account.
    - Date - This will list the transactions for a specific date. If you double-click on a date, the "From date" and "To date" will be changed to the selected date.

After posting the transactions in the Petty cash journal, the transactions should display as follows in the T-Account viewer:

T-Account view of transactions in the Petty cash account

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in

which the transactions may be viewed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select "*Trial balance*" report type and click on the Report button.
3. On the "*Trial balance*", select the "*B820-000 Petty cash*" account.
4. Double-click on the selected account; or right-click and select Show details on the context menu.
5. Click on the following to get specific views of transactions:
    - Batch id (e.g. 38 automatically generated). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. B820-000 Petty cash, G210-030 Motor vehicle - Repairs G230-000 Stationery, T860-020 Input Tax Standard - 15%). This will list the transactions for a specific account.
    - Date - This will list the transactions for a specific date. If you double-click on a date, the "From date" and "To date" will be changed to the selected date.

After posting the transactions in the Petty cash journal, the transactions should display as follows in the T-Account viewer:

Batch view



Show contra – You may select (tick) this option to view the Contra account code and account description in the first two (2) columns of the T-Account viewer. This will not print on the T-account viewer report, but will be included in the Exported file (which you can open in a spreadsheet).

T-Account view of Receipt transactions in the Petty Cash - Bank account

The updated (posted) transactions for the "*Petty cash*" account, is as follows:



Accounting equation

Debits = Credits

Debit General ledger (i.e. Expenses + Input Tax)

=

Credit General ledger (i.e. payment transactions from the Petty cash (Bank account)) - (Inclusive of Input VAT/GST/Sales Tax).

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Petty cash transactions (Import - CSV)

Introduction to Petty Cash

Receipt and Payment batch journal – Bank accounts

The use of cheques or electronic transfers (banking transactions) should be used for all transactions. The handling of cash should be limited as far as possible. Any amounts received from debtors (customers / clients) for cash sales or payments on accounts, should be banked as soon as possible.

These cash received by a business, should not be used for purchases, etc.

Cash, if not controlled and safeguarded properly, will create a climate for theft and fraud.

Any cash and payments received should be deposited in the bank account of the business. In osFinancials5/TurboCASH5 the receipts should be recorded in the Receipts batch (journal).

Any payments made should be paid out of the bank account of the business. In osFinancials5/TurboCASH5 the payments should be recorded in the Payments batch (journal).

Receipt and Payment batches - Petty Cash

A business may need to pay cash for smaller items and items needed urgently. For this reason, a business may need to keep a certain amount of cash (petty cash float) on hand to pay for these smaller necessary or urgent purchases.

Petty cash is a minimum amount of cash kept on hand for small purchases or reimbursements.

Petty cash money and payments or reimbursements must be safeguarded and properly documented to ensure that theft and fraud do not happen.

Petty cash payments (reimbursements) may be handled in the following:

- Employees may be required to fill in a form (e.g. Petty cash voucher) to receive the cash from the petty

cash. Directly after the purchase, the employee must submit a receipt or acceptable supporting documentation as proof of the purchase and return any change if applicable.

- Employees may be asked to make purchases themselves and then get reimbursed from the fund after submitting a receipts and/or acceptable supporting documentation as proof of the purchase.

The Petty cash receipts batch is hardly ever used. Any Petty cash float and/or replenishment is recorded in the Payment batch of the bank account from which the Petty cash float is recorded.

All petty cash payments or reimbursements is recorded in the Petty Cash Payments batch.

Petty cash guidelines

Some guidelines for using Petty cash, is as follows:

1. Appointing a Petty cashier – Only one person may have assess to the Petty cash. The petty cash cashier, must make sure that nobody else has access to the cash.
2. The petty cashier should be responsible for any cash shortages or a lack of receipts and/or acceptable supporting documentation as proof of the purchase.
3. Calculating the amount of float – The petty cash float should not have large amounts. It should be calculated for the average petty cash expenses for a period, monthly, fortnightly or weekly according to the needs of the business.
4. Another person needs to be appointed to check, on a regular basis, in the presence of the petty cashier, that the petty cash is correct.
5. Clear guidelines or policies and limits:
    a) Purchases or reimbursements from the Petty cash should only be allowed for valid business expenses (not anything else which are regarded as private expenses).
    b) Receipts and/or acceptable supporting documentation as proof of the purchase or reimbursement must be submitted.
    c) Restrict the Petty cash payments or reimbursements to specific employees.
    d) Implement a clear list of allowed purchases or reimbursements.
    e) Limit the amount for which purchases reimbursed.
    f) Make the petty cash guidelines and policies available to all employees.
6. If Tax (VAT/GST/Sales tax) is charged on a reimbursed purchase, the Tax should also be recorded as Input tax.

Petty cash can be recorded in in a pre-printed Petty cash register, or done in a spreadsheet. The spreadsheet can be used to record and control petty cash payments or reimbursements as well as to import the transactions as a Comma Separated Value (*.csv) – Tab delimited file into osFinancials5/TurboCASH5.

Recording Petty Cash transactions

The following options are available to record petty cash transactions:

1. Manually enter the transactions in a batch.
2. Petty Cash Register - Import the Petty cash transactions from Comma Separated Value (*.csv) – Tab delimited file into batches. This is very useful for bringing in external data without having to recapture it. This allows us to easily develop add on systems in Spreadsheet format and to synch them with osFinancials5/TurboCASH5.

Petty Cash Register

Depending on your requirements, the petty cash register may be designed for the necessary controls to keep accurate track cash in the petty cash and moneys paid for expenses / reimbursements.

The Petty Cash Register, in a spreadsheet format, can be used to implement the necessary controls and keep track of your expenses, payments and reimbursements. Transactions in the Petty Cash Register can be saved in a comma separated value (*.csv) -Tab delimited file format. These transactions can then be imported into a Petty Cash payments batch and updated to the ledger.

Delimited file import

The CSV format has been around for many years as a means of transferring data between datasets.

osFinancials5/TurboCASH5 can import CSV files into batches. This is very useful for bringing in external data without having to recapture it. This allows us to easily develop add on systems in Spreadsheet format and to synch them with osFinancials5/TurboCASH5.

OpenOffice 4 / LibreOffice 5

There are a number of contenders for the Office Software Market, Microsoft Office, OpenOffice LibreOffice. I have found OpenOffice to be the best at handling CSV files. You can use their packages, but I sincerely recommend you take advantage of the FREE Download of Open Office at *www.openoffice.org* and use OpenOffice for working with the data you are going to import into osFinancials5/TurboCASH5.

LibreOffice can be downloaded at *http://www.libreoffice.org/*

Get the Data Ready in OpenOffice / LibreOffice

osFinancials5/TurboCASH5 is particular about the CSV format that it will accept. osFinancials5/TurboCASH5 accepts the Tab delimited csv files.

If the CSV file is not EXACTLY the format that osFinancials accepts it will generate an error:

"List index out of bounds (3)".

If the Date is not entered as "31/03/2024", and is entered as "2024/03/31", depending on your system settings, and the delimited file import in • osFinancials5/TurboCASH5 is imported, the dates may be imported as 1899/12/31. Irrespective of your operating system's date and regional settings, if the date is entered as "31/03/2024" the date should be, by default, be imported correctly according to the format of your operating system's date and regional settings.

Petty Cash Register Template

You may find these sample templates in " *...\bin\Tutorials\PETTY-CASH-TEMPALTES* " folder. These templates were created in the Open Document Spreadsheet format used in LibreOffice Calc. It consists of the following two folders:

- BATCHES - This contains the CSV file (PETTYCASH-2024-03.csv) generated by save the CVS tab of the Petty cash register in the TEMLATES folder. This CSV file is used to use the "*Import Delimited file*" option in the "*Process options for this batch*".
- TEMPLATES - This contains the sample Petty cash register file (PETTYCASH-TEMPLATE.ods). This sample file is used to generate transactions in the Petty cash register to save the CVS tab of the Fixed Asset register in the BATCHES folder.

This sample Template can be used in normal Petty cash batches (Batch entry) as well as in Petty cash bank accounts using the Bank Import plugin.

Open the PETTYCASH-TEMPLATE.ods

Open the PETTYCASHTEMPLATE.ods (Open Document Spreadsheet).



Enter the name of your business and the period.

The default sheet (Sheet1), consists of Receipts and Payments / Reimbursements:

1. Receipts – Column A – D - The Petty cash advances and replenishment as well as any shortages refunded should be entered in these columns. The transactions for the Petty Cash advances and replenishments, does not need to be recorded in TurboCASH, since these will be recorded in the Payments batch of the Bank account from which the petty cash float amount is paid.

2. Payments / Reimbursements – Column E – H – All payments or reimbursements must be entered in these columns. These transactions must be recorded in the Petty Cash batch (journal). These transactions will be updated in the CSV sheet. Once the transactions is added, the CSV sheet, may be saved as a comma separated value – Tab delimited file type. The transactions may then be imported into osFinancials5/TurboCASH5 as a delimited file import.



To add more transactions, you may select a row, e.g. Row 9, and insert the required rows.

Balancing the Petty Cash

Petty cash funds must be periodically checked to ensure that the balance of the petty cash fund is correct.

The petty cash float must always be in balance with the cash on hand plus the receipt or acceptable supporting documentation as proof of the purchase.

If it does not balance and you have checked that you have counted the cash at hand correctly, and that the petty cash payment transactions are entered correctly.

If it is correctly counted and entered, a difference indicates a surplus or a shortage:

- *Surplus - This is where the amount in the petty cash, and the petty cash vouchers and/or slips exceeds the amount of the float.*
- *Shortage - This is where the amount in the petty cash, and the petty cash vouchers and/or slips is less than the amount of the float.*

Updating the CSV sheet to a Tab delimited file

Once the transactions is added in Sheet1, click on the CSV sheet.

To add more transactions in the CSV sheet, as added in Sheet1, copy the formulas in Columns A – H to the next rows.

This will update the CSV sheet with the transactions as entered in the Payments / Reimbursements – Column E – H of Sheet1.



The values of the columns is as follows:

1. Column A – Reference =Sheet1.E8 Reference as entered in column E Row 8 of Sheet1.

2. Column B – Date =Sheet1.F8 the Date as entered in column F Row 8 of Sheet1.

> *If the Date is not entered as "31/03/2024", and is entered as "2024/03/31", depending on your system settings, and the delimited file import in TurboCASH is imported, the dates may be imported as 1899/12/31. Irrespective of your operating system's date and regional settings, if the date is entered as "31/03/2024" the date should be, by default, be imported correctly according to the format of your operating system's date and regional settings.*

3. Column C – Description =Sheet1.G8 the Description as entered in column G Row 8 of Sheet1.

4. Column D – Account = The default expense / purchase account which will be imported into the batch.

> *You may enter an existing default account, e.g. "G999-000" – Suspense account or a "Petty cash control" account (added in Accounts (Default ribbon)). Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you need to select the correct account for each transaction.*

> *You need to type the account type prefix e.g. "G" followed by the main account code e.g. "230" and the sub-account, separated by a hyphen "-" for example, "G230-000" for the Stationery account.*
>
> *Income and expense accounts (starting with the "G" prefix for General ledger accounts) are prefixed with an "*" (asterisk). If the "*" asterisk is also entered in this column, the account will not be imported into the delimited file batch.*

> *You may type the correct account in this column from the printed Chart of accounts from Reports → Ledger → Listing (Reports ribbon), e.g. "G230-000" – Printing, Postage and Stationery account. Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you can check and confirm the correct account for each transaction.*

5. Column E – Contra account – The default value is "*T*". Do not delete this column and leave the value as "*T*".

6. Column F – Tax account – The default value is "*T*". Leave the value as "*T*", unless Tax (VAT/GST/Sales tax) is applicable to the transaction.

> *You may leave the default as "T".*
>
> *Once the csv file (Delimited file import) of the petty cash transactions in the petty cash batch is imported, you need to select the correct tax account for each transaction on which Tax (VAT/GST/Sales tax) is applicable.*

> *If Tax (VAT/GST/Sales tax) is applicable to the transaction, you may type the account type prefix e.g. "T" followed by the main account code e.g. "950" and the sub-account, separated by a hyphen "-" for example, "T860-015" for the Input VAT – Standard rate – 15% account.*

7. Column G – Amount – =VALUE(Sheet1.H8) – The amount of the transaction (expense / payment / reimbursement).

> *The amount should be a positive amount, since the transactions need to be imported as a debit transaction into the Petty cash batch (journal).*
>
> *If the amount is negative (prefixed by a minus "-" sign) amount, it will be imported as a credit amount into imported into the delimited file batch.*

8. Column H – The default value is "*FALSE*". Once the transactions is imported, and you select an account (i.e. Debtor (customer/client), Creditor (supplier/vendor) and/or a Ledger account), which is set as Open item account and the account has processed transactions to be linked, the "*Open item selection*" screen will be displayed.

Save the CSV sheet to a Tab delimited file

Once the transactions is updated in the CSV sheet, the CSV sheet, need to be saved as a comma separated value – Tab delimited file type. The transactions may then be imported into osFinancials5/TurboCASH5 as a delimited file import.

> *Before proceeding with the next step, remember to SAVE the PETTYCASHTEMPLATE.ods (Open Document Spreadsheet).*

To save the Transactions in the CSV tab to a Tab delimited file:

1. On the "*PETTYCASHTEMPLATE.ods*" (Open Document Spreadsheet), click on the CSV sheet, if not already selected.
2. Select the rows and columns on the CSV sheet.



3. Enter the name for the Batch file, (e.g. "*PettyCASH-2024-03*". In this example, it will indicate the petty cash transactions for "*March 2016*".

4. Save as type: - Select the "*Text CSV (.csv) (*.csv)*" as the file type. The "*Edit filter settings*" field (tick box) will be activated for the "*Text CSV (.csv)*" file type.

> *It is important to select (tick) the "Edit filter settings" field. This will launch the "Export Text file" screen on which the TAB field delimiter needs to be selected.*

5. Edit filter settings – Tick this option.

6. Click Save.



7. On the "*Confirm File Format*" screen, click Use Text CSV Format button. The "*Export Text File*" screen is displayed:



8. Select the following options:

   a) Field delimiter: - Select {TAB}.

   > *If this option is not selected, the delimited file import in osFinancials will fail. The Tab delimited CSV import file is required by • osFinancials5/TurboCASH5.*

   b) Save cell content as shown – Select (tick) this option. If this option is not selected (not ticked), formula values will be imported and may produce REF (Reference) errors.

9. Click the OK button. LibreOffice will produce a Warning message that only the active sheet was saved (CSV sheet). A similar warning message is as follows:

   > Warning saving the document PETTYCASH-2024-03:
   > Only the active sheet was saved.

10. Click the OK button.

11. Close the "*PettyCASH-2024-03.csv*" file.

> *If the csv file is opened (active) on your system, the following error message will be displayed:*
>
> *"Cannot open file "...\Spreadsheets\PettyCASH\PettyCASH-2024-03.csv". The process cannot access the file because it is being used by another process.".*
>
> *Close the file in which it is open, e.g. Excel / OpenOffice / LibreOffice and import the file again.*

Delimited File Import - CSV file into osFinancials5/TurboCASH5

Once the transactions is saved as a comma separated value – Tab delimited file type, the petty cash transactions can be imported into osFinancials5/TurboCASH5 as a delimited file import.

To Import Petty Cash Transactions from the CSV - Tab delimited file:

1. On the Default ribbon, select Batch entry (F2).
2. Select the Payments batch to which the Petty Cash account is linked.



3. Click on the Open button. The Batch entry transaction screen for the Payments batch to which the Petty Cash bank account is linked will be displayed.
4. On the F10:Setup icon to check the settings for the batch.

> *On the Standard tab, check that the "Consolidate balancing" option, is not selected.*
>
> *If the "Consolidate balancing" option, is selected the following error message will be displayed:*



An information message will be displayed:

> Consolidating lines and using tax will mess up your tax report! Please make sure you do not use tax or do not consolidate lines!

Click OK and remove the tick from the "Consolidate balancing" field.

5. Click on F9:Process icon and select the "*Delimited file import*" option and click OK.



The "*Open*" screen will be displayed.



6. Navigate and select the Petty cash batch file (e.g. "*PETTYCASH-2024-03.csv*") to import and click Open.

Warning saving the document PETTYCASH-2024-03:
Only the active sheet was saved.



7. Enter the Alias (batch name) in the "*Change alias*" field.

8. After importing the petty cash transactions, you may need to change / edit the imported petty cash transactions:

   a) Reference – The Petty cash voucher or reference number as entered in Column E of Sheet1 and updated in Column A of the CSV sheet in the Petty Cash Register.

   b) Date – The date as entered in Column F of Sheet1 and updated in Column B of the CSV sheet in the Petty Cash Register.

> *If the Date (in Sheet1 of the Petty Cash Register) is not entered as "31/03/2024", and is entered as "2024/03/31", depending on your system settings, and the delimited file import*

in TurboCASH is imported, the dates may be imported as 1899/12/31. Irrespective of your operating system's date and regional settings, if the date is entered as "31/03/2024" the date should be, by default, be imported correctly according to the format of your operating system's date and regional settings.

c) Description – The descriptions as entered in Column G of Sheet1 and updated in Column C of the CSV sheet in the Petty Cash Register.

d) Account – The account code as entered in Column D of the CSV sheet in the Petty Cash Register. Each payment or reimbursement transaction needs to be linked (allocated) to the correct account.

If you have entered an existing default account, e.g. "G999-000" – Suspense account or a "Petty cash control" account (added in Accounts (Default ribbon)). Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you need to select the correct account for each transaction.

You need to type the account type prefix e.g. "G" followed by the main account code e.g. "230" and the sub-account, separated by a hyphen "-" for example, "G230-000" for the Stationery account.

Income and expense accounts (starting with the "G" prefix for General ledger accounts) are prefixed with an "" (asterisk). If the "*" asterisk is also entered in this column, the account will not be imported into the delimited file batch.*

You may type the correct account in this column from the printed Chart of accounts from Reports → Ledger → Listing (Reports ribbon), e.g. "G230-000" – Stationery account. Once the csv file (Delimited file import) of the petty cash transactions in batch is imported, you can check and confirm the correct account for each transaction.

e) Tax account – The correct tax account (code) must be selected, if Tax (VAT / GST / Sales tax) is applicable to the transaction. The Tax account code as entered in Column F of the CSV sheet in the Petty Cash Register.

The tax column will only be displayed if the "No Tax" option is left blank (not ticked) in the F10:Setup option in the Batch entry screen.

If no Tax (VAT/GST/Sales Tax) is applicable to all the transactions in the Petty Cash Register; or if you are not registered for Tax (VAT/GST/Sales Tax) you may select to hide the tax column will only be displayed if the "No Tax" option is left blank (not ticked) in the F10:Setup option in the Batch entry screen.

f) Debit – Positive amounts – The amount of the transaction (expense / payment / reimbursement) as entered in Column H of Sheet1 and updated in Column G of the CSV sheet in the Petty Cash Register.

g) Credit – Negative amounts –

> *The amount should be a positive amount, since the transactions need to be imported as a debit transaction into the Petty cash batch (journal).*
>
> *If the amount is negative (prefixed by a minus "-" sign) amount, it will be imported as a credit amount into imported into the delimited file batch.*

h) Open item – If an account (i.e. Debtor (customer/client), Creditor (supplier/vendor) and/or a Ledger account), which is set as Open item account and the account has processed transactions to be linked, the "*Open item selection*" screen will be displayed. On this "*Open item selection*" screen, you may select to link a payment transaction to a credit transaction, ode a receipt (deposit) transaction to a debit transaction.

9. Click on the F5:Balance icon. This will generate balancing transactions to the Petty cash bank account.



10. Click on the F8:List icon to print a list of the transactions in the unposted batch.



11. Click on the F6:Post icon to update (post) the transactions to the ledger.

T-Account view of transactions in the Petty cash account

All processed (posted) transactions will be accumulated in the Ledger analyser. There are various ways in which the transactions may be viewed, exported and analysed.

To access the T-Account view of the transactions:

1. On the Reports ribbon, select Ledger analyser 1 or Ledger analyser 2.
2. Select "*Trial balance*" report type and click on the Report button.
3. On the "*Trial balance*", select the "*B820-000 Petty cash*" account.
4. Double-click on the selected account; or right-click and select Show details on the context menu.
5. Click on the following to get specific views of transactions:
    - Batch id (e.g. 40 automatically generated). This will list only the transactions for a specific batch (journal).
    - Account code (e.g. B820-000 Petty cash, G210-030 Motor vehicle - Repairs G230-000 Stationery, T860-020 Input Tax Standard - 15%). This will list the transactions for a specific account.
    - Date - This will list the transactions for a specific date. If you double-click on a date, the "From date" and "To date" will be changed to the selected date.

After posting the transactions in the Petty cash journal, the transactions should display as follows in the T-Account viewer:

Batch view



Show contra – You may select (tick) this option to view the Contra account code and account description in the first two (2) columns of the T-Account viewer. This will not print on the T-account viewer report, but will be included in the Exported file (which you can open in a spreadsheet).

T-Account view of Receipt transactions in the Petty Cash - Bank account

The updated (posted) transactions for the "*Petty cash*" account, is as follows:



Accounting equation

Debits = Credits

Debit General ledger (i.e. Expenses + Input Tax)

=

Credit General ledger (i.e. payment transactions from the Petty cash (Bank account)) - (Inclusive of Input VAT/GST/Sales Tax).

Created with the Standard Edition of HelpNDoc: Import and export Markdown documents

Multi-user plugins

Multi-user plugins

Multi-workstation

Multi-workstation - Shop - Licence: Once-off -

Documentation : TurboCASH website - Multi User Installation -
Documentation : osFinancials website -osFinancials5/TurboCASH5 multi user setup - Windows server
Documentation : osFinancials website - Multi Werkplek (linux server) Plugin - Linux server (Dutch only)

Do you want to use osFinancials5 or TurboCASH5 with multiple users at the same time? That is possible with the Multi-workstation plugin. The number of users is unlimited, as long as the hardware sustains. To use the Multi-workstation a network with a shared folder is required.

The plugin doesn't need to be downloaded. It will be activated by a code.

You will receive the code(s) and instructions through mail within two workdays after payment.

Using osFinancials or TurboCASH with multiple users simultaneously via the Multi-workstation plugin sounds like a convenient solution for collaborative financial management.

Unlimited user capability, contingent on hardware capabilities, provides scalability. Activation via a code simplifies the process, and instructions delivered via mail streamline setup.

This approach ensures efficient utilization of resources while accommodating diverse user needs.

osFinancials5/TurboCASH5 Multi-User Plugin

osFinancials5/TurboCASH5 Multi-User Plugin - Shop - Licence: Annual licence

- *Documentation : TurboCASH website - Multi User Installation -*
- *Documentation : osFinancials website - osFinancials5/TurboCASH5 multi user setup - Windows server*
- *Documentation : osFinancials website - Multi Werkplek (linux server) Plugin - Linux server (Dutch only)*
- *Documentation : Help topic - Multi User Linux Server install - Linux server (English only)*
- *Documentation : Help topic - Multi User Windows Server install - Windows server*

Unlock the power of collaboration with our Multi-User Plugin! Whether you are running your server on Windows or Linux, our plugin seamlessly integrates into your network environment, allowing multiple concurrent osFinancials5/TurboCASH5 sessions.

No more limitations - choose any PC to serve as your network server, and experience the freedom of collaborative finance management. With an easy manual installation process and an annual license, elevate your teamwork and productivity to new heights. The number of users is unlimited, as long as the hardware sustains.

The Multi-User Plugin for osFinancials5/TurboCASH5 offers the capability to configure and set up a network server to accommodate multiple users. However, to unlock the full functionality for multi-user access, purchasing a multi-user licence and registering osFinancials5/TurboCASH5 as a multi-user product is necessary.

Documentation is provided for installing and configuring multi-user setups on both Windows and Linux servers, which can assist users in setting up their network environment effectively.

It's important to note that the multi-user functionality is limited in this edition, indicating that additional licensing is required to fully utilize it. Therefore, acquiring a multi-user licence is essential for organizations or teams requiring simultaneous access to osFinancials5/TurboCASH5.

osFinancials5/TurboCASH5 Online

osFinancials / TurboCASH Online

Experience ultimate convenience and flexibility with our • osFinancials5/TurboCASH5 Online offerings:

1. Online Account:- Manual - Shop - 14 Days trial, 6 months account or year account - Gain 24/7 access to your osFinancials5/TurboCASH5 Set of Books hosted on our servers. Whether you're at the office or at home, manage your administration effortlessly. Collaborate with your accountant or co-workers with ease, and utilize Open Office for added versatility. Plus, enjoy ample 1 GB of disk space with the option to expand as needed. With flexible subscription options and straightforward invoicing, it's never been easier to stay on top of your finances. It's only possible to access your set of books with one session at the time. If you want multi user access, than you can buy " *addition nodes*".

2. Online Extra Set of Books: Manual - Shop - Depending on the number of the Sets of Books ordered. Expand your online toolkit with additional Sets of Books tailored to your needs. Choose the number of sets required and enjoy seamless access to your finances anytime, anywhere.

3. Online Account with Plugin Bundle: Manual - Shop - 14 Days trial, 6 months account or year

account. Elevate your online experience with our Plugin Bundle, adding even more functionality to your osFinancials5/TurboCASH5 Set of Books. Enjoy all the benefits of our Online Account offering, plus access to a suite of plugins to enhance your financial management capabilities. Customize your subscription to fit your needs, with multi-user access options available for seamless collaboration.

Unlock the power of online finance management with osFinancials5/TurboCASH5 Online today.

osF Local Webserver

osF Local Webserver: - Manual - Shop -

Experience the convenience of accessing osFinancials5/TurboCASH5 through your web browser with our local web server solution. With a simplified interface, you can effortlessly manage your finances using just a tablet, no matter where you are.

Plus, all data entered through the web server is seamlessly integrated into the same database as your desktop version, ensuring consistency and accessibility across platforms. Enjoy the power of osFinancials5/TurboCASH5 in the palm of your hand with osF Local Webserver.

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Word Doc to an eBook: A Step-by-Step Guide

Multi-user Windows install

---

osFinancials5/TurboCASH5 Multi user Plugin

• *osFinancials5/TurboCASH5 Multi userPlugin - Shop - Licence : Annual licence*

Documentation : osFinancials website - Manual

Documentation : Help topic

1a Installation of osFinancials5/TurboCASH5 on the server:

If you wish to use osFinancials5/TurboCASH5 in a network environment, you will have to decide first which PC will be your server.

If you have determined witch PC to use you can do a full osFinancials5/TurboCASH5 installation.

Take care and install osFinancials5/TurboCASH5 in a separate folder so the root folder can be shared

between users.

```
c:\osf\osfinancials\
```

or

```
c:\tcash\turbocash\
```

Share the folder c:\osf (or c:\tcash) using windows folder sharing and give the correct user rights.

Open osFinancials5/TurboCASH5 so the set of books list will be filled.

Close osFinancials5/TurboCASH5.

Use the Windows explorer to open the folder c:\osf\osfinancials\books (or c:\tcash\turbocash\books) to serverbooks.

Important:

If you wish to use simultaneous users with osFinancials5/TurboCASH5 you MUST add users in Access control.

Create a user for everyone that will be using osFinancials5/TurboCASH5 in "*Access control*". The fist user will be the user that hands out numbering for invoices, etc. You can set one ore more users to user there own numbering.

1b Firebird installation on the server

Install Firebird on the server:

We use the Firebird version 2.1. The install file (firebird.exe) is included in the full installation of osFinancials5/TurboCASH5 installation folder.

This version of Firebird support recursive selects so you need this as a minimum.

Select full installation in the Firebird install.



Tick all ticks and make sure its running as a service.



!!! Firebird uses port 3050 make sure its open in your firewall. !!!

1c Correcting the set of books on the server:

If you reopen osFinancials5/TurboCASH5 and select the (red) set of books.

You need to press Properties to change the folder to the new serverbooks

```
c:\osf\osfinancials\serverbooks\youradmin\books.fdb
```

in the field Set of Books path

we also need the name or ip of this server PC

Start CMD prompt and type ipconfig /all

Try to find the hostname or, if that is not there the ip-address

Type this information into the field "Servername".

Adding additional databases / set of books on the server:

Use the Windows Explorer to find the serverbooks folder then copy an existing folder of a set of books and change the folder name.

Start up osFinancials5/TurboCASH5 and use the Search button. Search for your copied set of books and locate the books.fdb.

Now check all the properties as explained in section "Correcting the set of books on the server".

Set of books located on a other server then the server that was used for the installation of osFinancials5/TurboCASH5.

The remote access to a set of books database is always referenced from the severs point of view.

Client installation:

The easiest way is to make a share to the server on the client PC.

There is no need to install osFinancials / TurboCASH on the client PC. You can just start osFinancials5/TurboCASH5 by making a shortcut to the executable.

Note: If you have trouble connecting make sure the port 3050 is open on both the server and client.

osFinancials5/TurboCASH5 on a Microsoft Server 2008

If you use a server 2008 it can be you need to exclude osFinancials5/TurboCASH5 from DEP protection.



Select "Advanced system settings"



Select the tab "Advanced" tab.

And click on the “Settings” button.



Check if the settings for DEP is either turned of or osFinancials5/TurboCASH5 is excluded from DEP.



Browse to where osFinancials / TurboCASH is installed.



And select osFinancials.exe / TCASH5.exe or Accounting.exe and press Open.



This will add osFinancials5/TurboCASH5 to the exclude list.

Testing of the connection with FlameRobin

This is a optional feature and is not needed for osFinancials5/TurboCASH5 to work correct.

But it does serve as a good way to test connections with the database.

The installation file, flamerobin.exe, is also in the osFinancials5/TurboCASH5 installation folder.

Add a new server if you are on the client machine (you also need the client install of Firebird for this) of just use localhost if flame is running on the server.

1. Start FlameRobin and click on Home.

2. Using the right mouse button, select the Register server... option from the context menu.



3. Enter the following:

    a) Display name: - Enter an arbitrary name to recognize the server with and in the “Hostname” the IP-address of the server.

    b) Hostname: - Enter the IP-address (as found in the previous step using ipconfig).

    c) Port number: - Leave this field empty (default).

4. Using the right mouse button, you can now select *Register existing database...* from the context menu on the newly added server. The next screen is displayed:



5. Enter the following:

    a) Display name: - Enter the name you want to use for this particular set of books

    b) Database path: - Enter the full server path to the books.fdb

    c) Username: - Default username is sysdba

    d) Password: - Default password is masterkey.

6. Click on the Save button and double-click on the added database. The database tables should now be reflected.



7. You may click on the tables in the list to see the data of your Set of Books.

8. If there is no connection problems you just successfully tested the database connection.

Creating users in Access control

If you database is set up properly there is still a need to create users in osFinancials5/TurboCASH5 to make sure there is no conflicts when entering data.

Create user on the Standard security tab in Access control



Use the Add button to add a new user.

Change the name of New user0 and enter a password for the new user.

Press Apply to save the changes.

You can limit rights for the new users in the tabs.

Adjusting the default password (Firebird)

This is for the experienced user that has knowledge of database management.

This will change the default password in Firebird and FlameRobin. This will not change the Password to Open a Set of Books in TurboCASH multi-user.

To change the standard (default) password of the standard username, i.e. sysdba on the database server, you need to use the gsec program of Firebird (located in C:\Program Files\Firebird\Firebird_2_1\bin folder).

Once you have completed the standard installation of osFinancials5/TurboCASH5 and the Firebird database server is completed, you may launch the gsec application (i.e. C:\Program Files\Firebird\Firebird_2_1\bin\gsec.exe).

You can control the users and their passwords. In the gsec application, you may access the security database, by executing the following task via Windows Menu Start->Run:

```
"C:\Program Files\Firebird\Firebird_2_1\bin\gsec.exe" -database "C:\Program Files\Firebird\Firebird_2_1\security.fdb" - user sysdba -password masterkey
```

Or for the remote database

```
"C:\Program Files\Firebird\Firebird_2_1\bin\gsec.exe" -database "192.168.2.21:C:\Program Files\Firebird\Firebird_2_1\security.fdb" -user sysdba -password masterkey
```

(Note you need to enter the correct IP-address of the remote database). If you need to change the standard (default) password (i.e. masterkey), you may enter the command as follows:

```
modify sysdba -pw mypassword
```

This will set or change the master password to mypassword (as in this example).

Firebird can accommodate case sensitive passwords to the maximum of up to 8 characters. The rest of the characters (more than 8) is ignored when enterted (e.g. 10 character password mypassword). As per this 10 character password, you may enter up 8 characters, e.g. mypasswo, the last 2 characters will be ignored.

You may also add other users, and manage the user-rights over the database tables in TurboCASH. This is not covered in this documentation. You may find comprehensive information on the various commands

and features at the Firebird website, i.e. http://www.firebirdsql.org/manual/.

Firebird tuning

The firebird.conf file can be edited manually to optimise the performance of the Firebird Database Server.

For example, if you have set that the application to run on two processors, or the initial allocated memory before the database is loaded, etc.

By default, it just uses 1 processor and the allocated memory is not much. These adjustments should make it faster if you have more data and can use the multiprocessor in the server to its full extend.

In the firebird.conf file you will find some basic guidelines (documentation) about the parameters working and settings. This section includes some tips to increase the performance.

1 - Number of cashed database pages

Number of cached database pages

#

This sets the number of pages from any one database that can be held

in cache at once. If you increase this value, the engine will

allocate more pages to the cache for every database. By default, the

SuperServer allocates 2048 pages for each database and the classic

allocates 75 pages per client connection per database.

#

Type: integer

#

#DefaultDbCachePages = 2048

To change the setting:

After the Type: integer line, you may add your name preceded by the comment # symbol and a description e.g. Adjusting Server Performance

|# Danie Adjusting Server Performance

Change the value if necessary, e.g. 2048

|DefaultDbCachePages = 8192

You may use the following KB to Bytes Conversion table (located at the end of the firebird.conf file) to select the correct values:

```
########################################
#
# KB to Bytes Conversion table
#
########################################
#
#    KB     Bytes        KB     Bytes
#  ----    ---------    ----    ---------
#     1    1024          32    32768
#     2    2048          64    65536
#     4    4096         128    131072
#     8    8192         256    262144
#    16    16384        512    524288
#
########################################
```

2 - Which CPUs should be used (Windows Only)

```
# In an SMP system, sets which processors can be used by the server.
# The value is taken from a bit map in which each bit represents a CPU.
# Thus, to use only the first processor, the value is 1. To use both
# CPU 1 and CPU 2, the value is 3. To use CPU 2 and CPU 3, the value
```

is 6. The default value is 1.

#

Type: integer

#

#CpuAffinityMask = 1

To change the setting:

After the Type: integer line, you may add your name preceded by the comment # symbol and a description e.g. Adjusting Server Performance

|# Danie Adjusting Server Performance

Change the value if necessary, e.g. 3

|CpuAffinityMask = 3

Created with the Standard Edition of HelpNDoc: Effortlessly Spot and Fix Problems in Your Documentation with HelpNDoc's Project Analyzer

Multi-user Linux Server install

Introduction

Licence

Annual licence

Order: here

For the multi-user use of TurboCASH / osFinancials in combination with *nix (Linux, *BSD, etc.) server, there are several scenarios which may be configured.

Please read the advantages for and disadvantages of the several scenarios given for the installation and configuration.

Advantages and Disadvantages

Scenario 1: Only the databases on the server - client on separate Windows machine

Advantages:

- The Set of Books has been centrally stored on the server and walks along in the regular backups.
- Everyone uses the same dates which real-time to all client are offered.
- This situation is handy if one works with several Point-of-Sales (POS) on several locations.

Disadvantages:

- Reports, application configuration and application program installed on every PC.
- The management of configuration and upgrades very time consuming.

Scenario 2: Database on server and client on samba share of server

Advantages:

- The Set of Books has been centrally stored on the server and walks along in the regular backups.
- Everyone uses the dates which is real-time to all clients.
- Reports, application configuration and application program are stored on the server.
- The management of configuration and upgrades happens once-off on the server and not for every client.

Disadvantages:

- Start up of application takes sometimes longer, depending on the network speed.
- Network goes through load - application loads by means of network.

Installation and configuration

Scenario 1: Only the databases on the server - client on separate Windows machine

To use the database server, it is sufficient to place the database file on the server and to give the Firebird server full rights.

We assume that the Firebird Database is already installed and operational. For clarity, it is easiest to make a separate directory and save the Sets of Books in separate folders.

Keep in mind that all Unix variants are case-sensitive, so the file named test.txt is another file Test.txt.

Activities on the server

- Add a directory on the server for the Set of Books. For example /mnt/files/booksname.
- Set the full rights for the user on Firebird - with chown - R firebird /mnt/files/booksname.
- Copy the database file to the server and place it in the directory or subdirectory of the directories you just created. This file can be found in the Windows folder c: \ TCASH5 \ books \ booksname \ books.fdb. The copy can be done via FTP, FileShare, e-mail or removable media such as a floppy disk or USB stick. It is recommended to use a separate folder for each set of books.
- Check the permissions for security. The Firebird user should at least have read and write (rw) rights on the Set of Books file.

The configuration to the server should then be ready.

Activities on the client

- Install TurboCASH/osFinancials. At some point you will be prompted to install Firebird server. Choose to install client only. This will then not install the complete database.
- Start TurboCASH / osFinancials
- Click in the Open Set of Books window, select Add - Select Set of Books directory.
- In the first field Enter the name of the Set of Books, enter the name of for the Set of Books.
- In the Server field, enter the dns name or the ip-address of the server. This depends of the configuration of network.

- In the Enter the path where the books are stored field, enter the full path to the Set of Books, including the name of the database file. For example, /mnt/files/books/nameofbooks/books.FDB. Keep the uppercase and lowercase letters of the files and directories in mind.
- Enter the Username of the user who is in Firebird administrator. (The default username is SYSDBA).
- Enter the Password of the Firebird administrator. (Default password is masterkey).
- Click Change, and the Set of Books is added to the Open Set of Books window.

If all rights, file paths and login details are correctly entered, the Set of Books can simply open as an ordinary Set of Books.

The activities on the client machine will have to be performed for each workstation.

Scenario 2: Database on server and client on samba share of server

This scenario is in fact a continuation on the first scenario with only the databases on the server. The advantage is that the updates, reports, layouts and institutions centrally are stored. This makes it easier for an administrator for everything to be updated.

Working method

After completion of the first scenario and testing it, you should perform the following operations:

- On the server, if necessary, add file share and give users of TurboCASH / osFinancials read, write and execute permissions.
- If necessary your production network disk for the work stations by means of the login script. As TurboCASH / osFinancials in an existing share installed, check the rights for this share. In our example everything will be stored in a network disk F:
- If necessary, create a network for the workstations using the login script. If TurboCASH / osFinancials is installed in an existing share, check the permissions for this share. For example, everything will be saved to a network drive F:
- Install TurboCASH / osFinancials normally on a workstation without the Firebird server.
- Open Windows Explorer and copy the entire folder C: \ TCASH5 or C: \ osFinancials to the network drive F: \.
- Open the folder F: \ TCASH5 \ Books or F: \ osFinancials \ Books

- Remove all matters in the Books folder on the server and close the Windows Explorer.
- Find the shortcut that is created for starting TurboCASH / osFinancials and right-click with the mouse. Set the following options:
    - In the Target field, the path will have to be adjusted from C: \ TCASH5 \ TCASH5.exe to F: \ TCASH5 \ TCASH5.exe or C: \ osFinancials \ osFinancials.exe to F: \ osFinancials \ osFinancials.exe
    - In the Run field, the drive letter needs to be changed from C: \ osFinancials to F: \ osFinancials or C: \ osFinancials to F: \ osFinancials
- Click OK and test or start TurboCASH / osFinancials with the shortcut.
- If everything works, copy the shortcut also to the network.
- Set the access to the Set of Books as described in scenario 1.
- Tests if everything works well. If it does not work well, it is possible that there are a problem with the rights. Test that everything is working properly. If things are not working properly, it is possible that there are a problem with the rights.

Continuation on the remaining client

- Install TurboCASH / osFinancials to all client machines, but put the shortcuts and save the installation of the Firebird server.
- Copy the saved shortcut TurboCASH / osFinancials from the server to the desktop of the client.
- Verify if the logged in user have the network disk and if the rights are set.
- Start TurboCASH / osFinancials from the client. If it's correct, you can log on to the Set of Books that you previously added in the list.
- If everything works well, set the access control that will be appropriate for each user in TurboCASH/osFinancials. (multi-user).

The installation is now ready.

Created with the Standard Edition of HelpNDoc: Full-featured multi-format Help generator

Translations - Plugins - Dynareg

Dynareg plugins not on shop

Could not find the following dynareg plugins which can be enabled:

1. Documenten - Email adrs per document - Enabled : Documentation : Help documentation
   WARNING: Disabling the "E-mail address per document" plugin may result in a range of errors.
2. Documenten - Toon inactive artikelen in documenten - Enable : "*Documenten - Toon inactive artikelen in documenten*" Documantation : Help documentation - NOTE - The "*Inactive*" checkbox on the Stock lookup is standard when processing documents. Tick "*Inactive*" checkbox on stock lookup to list disabled items when processing documents.
3. Documenten - Free lookup plugin - Enable : "*Documenten - Vrije keuzenlijst*" Documantation : Help documentation - Activating the "*Free lookup*" list will add a "*Free lookup*" column as a checkbox in documents. The name of the "*Free lookup*" column can be edited or translated or customised the description of this column and add your own groups in Setup → Groups. NOTE There is no lookup available.
4. *Documenten - Transitorisch boeken* - Enable : "*Transitorisch boeken*" Documantation : Help documentation. NOTE: Disable / Enable does not seem to work
5. *Ecommerce - Eerste email check - Shop - Licence : Once-off license* - Enable : "*Eerste email check*"
6. *Ecommerce - Tweede email aankondiging verwijderen - Shop - Licence : Once-off* - Enable : "Tweede email aankondiging verwijderen."
7. *Gratis kassa plugin - Shop - Licence : Once-off* - Enable : "Gratis kassa - On click debiteuren lijst"

Dynareg plugins Enabled by Default

Email address per document

Email adrs per document plugin -

Enabled : "Documenten -Email adrs per document"

WARNING: Disabling the "E-mail address per document" plugin may result in a range of errors.

Documentation : Help documentation

Email adrs per document.

Een extra veld voor email adres bij een document.

Translation

Email address per document.

An extra field for email address in a document.

This plugin is by default registered

E-Mail address per account - Active=True

Disable confirmation message

> Dropping this will delete all data for this column continue?

Should you click Yes to disable this plugin, you may encounter errors.



WARNING: Disabling the "E-mail address per document" plugin may result in the following errors:

Error

> Dynamic SQL Error
> SQL error code = -206
> Column unknown

DOCHEAD.X_CUSTOMERS_EMAIL_ADDRESS
At line 68, column 13

Access violation

Access violation at address 656F0082 in module 'rtl290.bpl'. Read of address 00000004.

Pointer operation error

Invalid pointer operation.

If you accidentally disable this plugin and encounter these errors, follow these steps:

1. *Navigate to Plugins → Tools → DYNADBREG.*
2. *Enable the 'E-mail address per document' plugin again and reopen your Set of Books.*

Dynareg plugins Enabled - Not tested and found

Save contact ID with billing address

Save contact ID with billing address - Shop - Licence : One time fee

Enabled : "Documenten - Contact id bewaren bij factuur adres"

Documentation : Help documentation

Dynareg Save contact id at billing address

"*Contact id bewaren bij factuur adres.*

Bewaar de contact id bij een factuur adres zodat per bestelling een contact kan worden gekoppeld die u ook met een rapport kunt ophalen. (anders is deze de standaard bij de debiteur) u dient hiervoor wel de layout aan te passen."

Translation

Save contact ID with billing address.

Save the contact ID with a billing address so that a contact can be linked per order that you can also retrieve with a report, otherwise this is the default for the debtor. You must adjust the layout for this.

Free lookup

Dynareg Fee lookup plugin

Enable : "Documenten - Vrije keuzenlijst"

Documentation : Help documentation

Vrije keuzenlijst

Vrije keuzen lijst in een document

Translation

Free selection list

Free selection list in a document

NOTE : Activating the "*Free lookup*" list will add a "*Free lookup*" column as a checkbox in documentsThe name of the "*Free lookup*" column can be edited or translated or customised the description of this column and add your own groups in Setup → Groups. NOTE There is no lookup available, only a checkbox.

Quantities of multipliers

Aantallen multipliers

Berekend aantallen op basis van het een invoerveld

Translation

Quantities of multipliers

Calculates quantities based on an input field

Outer packaging

Omverpakking verkoop

Gebruik omverpakking in documenten om een dozijn gemakkelijk te kunnen bestelen. De omreken factor kan worden ingesteld bij instellen->Administratie->Voorraad beheer.

Translation

Outer packaging

Use outer packaging in documents to easily order a dozen. The conversion factor can be set at Setup->Administration->Inventory management.

Secondary packaging or outer packaging. It serves as an additional layer of packaging that surrounds the primary sales packaging. Unlike primary packaging, which directly holds the product, secondary packaging is not essential for reasons of hygiene, preservation, or protection against damage or soiling. Instead, it provides an extra layer of containment around the primary packaging for delivery to the end consumer.

Documenten links

Document koppelingen

Document koppeling

Translation

Document links

Shows inactive items in a document

Toont inactive artikelen in een document

Toon inactive artikelen in documenten

Translation

Shows inactive items in a document

Shows inactive items in a document

Confirmation messages

Confirmation messages Enable item (plugin).

"Add new item?"

Another confirmation message.

"Script executed!"

Deregister a plugin confirmation message

Dropping this will delete all data for this column continue?

Tables not found

tblDocHeader: Field 'WSHIPSTOCKID' not found

Document entry grid

* Click here to show/hide/move columns (Mouse over) second asterisk



(All)

(Sorted)

Trans details

Free lookup - Activating the Free lookup list in document will add the "*Free lookup*" in Setup - Groups. You may change translate or customise the description of this column and add your own groups.

Delivery address 3 (last one) should be Delivery address 4 as activated by "*Vrijedatum4"*)

Dynareg - Documents plugins

Free selection list

"*Vrije keuzen lijst*

Vrije keuzen lijst in een document"

Translation

Free selection list

Free selection list in a document

Activating the Free lookup list in document will add the "*Free lookup*" in Setup → Groups. You may change translate or customise the description of this column and add your own groups.

Free lookup - Delivery date 2 / Delivery date 3

Could this Free lookup column not be moved before or after Delivery dates.



Delivery dates

Delivery date 1/2/3/4 - Documentation : Help documentation -

Delivery date 1

Dynareg Delivery date 1 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Aflever datum in dokument regels"

Documentation : Help documentation -

"*Aflever datum in document regels*

Geeft een extra datum veld in document regels waar u een datum kunt invoeren deze kan bewerkt worden ook al heeft u het document verwerkt."

Translation

Delivery date in document lines

Provides an additional date field in document lines where you can enter a date that can be edited even after you have processed the document.

Delivery date 2 - Shop -

Dynareg Delivery date 2 plugin - Shop - Licence : Once-off -

Enable : "Documenten - 2e Aflever datum in dokument regels"

Documentation : Help documentation -

"*2e Aflever datum in document regels*

Geeft nog een extra datum veld in document regels waar u een datum kunt invoeren deze kan bewerkt worden ook al heeft u het document verwerkt."

Translation

Second Delivery date in document lines

Provides a second additional date field in document lines where you can enter a date that can be edited even after you have processed the document.

Delivery date 3

Dynareg Delivery date 3 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Vrijedatum 3"

Documentation : Help documentation -

"*Vrijedatum 3*

Geeft een extra datum veld in document regels waar u een datum kunt invoeren deze kan bewerkt worden ook al heeft u het document verwerkt."

Translation

Free date 3 -> Third Delivery date in document lines

Provides an additional third date field in document lines where you can enter a date that can be edited even after you have processed the document.

Delivery date 4

Dynareg Delivery date 4 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Vrijedatum 4"

Documentation : Help documentation -

"*Vrijedatum 4 ->*

Geeft een extra datum veld in document regels waar u een datum kunt invoeren deze kan bewerkt worden ook al heeft u het document verwerkt.."

"Dynareg Delivery date 4 plugin

In your documents you now have a 4th date field per item line. This allows you to indicate a delivery or collection date on your invoices.

Translation

Free date 3 -> Fourth Delivery date in document lines

Provides an additional fourth date field in document lines where you can enter a date that can be edited even after you have processed the document.

Vrijedatum 4 - Adds Delivery date 3 - should read Delivery date 4

Edit date

Set date

Could possible be changed to => Change date 2352 / 2367



Check box in document line

Dynareg Checkbox in document lines plugin - Shop - Licence : Once-off -

Enable : "Documenten - Check box in documentregel"

Documentation : Help documentation -

"*Check box in documentregel*"

"*Geeft een checkbox veld in document regels deze kan bewerkt worden ook al heeft u het document verwerkt*"

Bug Can only edit the ticks in unposted documents, Posted docyments tick cannot be removed or added.

Translation

Check box in document line

Provides a checkbox field in document lines that can be edited even after you have processed the document.

Gross profit in documents

Dynareg Bruto margin in documents plugin - Shop - Licence : Once-off -

Enable : "Documenten - Bruto winst in documenten"

Documentation : Help documentation

"*Bruto winst in documenten*

Toont de totalen costprijs en winst bij verkoop documenten" - Shop -

Translation

Gross profit in documents

Shows the total cost price and profit in sales documents.

Inc / Exp in English = Ink / Uit in Afrikaans 1188 (This label is in the Chart of Accounts or Reports → Ledger → Listing report

Maybe it could be changed to => Cost price 414 / 3286

Shows only the cost price

No profit is shown needs to be calculated manually.

Numbers based on date and date 2

Dynareg Numbers based on date and date 2 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Aantalen op basis van datum en datum 2"

Documentation : Help documentation - NEED TO UPDATE AND TEST

Aantalen op basis van datum en datum 2

Berekend aantallen op basis van het datum veld

Shop

Aantallen op basis van datum 1 en 2

Vermenigvuldigd het artikel totaal bedrag op basis van het aantal en de periode tussen datum veld 1 en datumveld 2.

Translation

Numbers based on date and date 2

Calculate quantities based on the date field

Shop

Numbers based on dates 1 and 2

Multiplies the item total amount based on the quantity and period between date field 1 and date field 2.

Documentation : Not tested.

Selling price in purchase documents

Dynareg - Directly Edit Sales Prices in Purchase Documents Plugin - Shop - Licence : Once-off -

Enable : "Documenten - Verkoopprijs bij inkoop documenten"

Documentation : Help documentation

"*Verkoopprijs bij inkoop documenten*"

"*Bewerk direct de verkoop prijzen vanuit een in een inkoop document.*

Hier kunt u dan de 3 verkoop prijzen uit osfinancials bewerken bij een gekozen artikel."

Translation

Selling price in purchasing documents

Edit sales prices directly from a purchase document.

Here you can edit the 3 sales prices from osfinancials for a selected item.

Screens outstanding translations



Directly edit the sales prices in a purchase documents plugin

Here you can edit the 3 sales prices within a purchase document (purchase, supplier return and order) for a selected item. The Selling prices will be updated in the Ledger tab of the stock item.

You may edit the prices inclusive or exclusive of Tax VAT/GSTSales tax).

Outstanding label translations

def supp - Default supplier -

Plugins - button -

Print label - button

Inc or Excl button

Selling prices may be user defined selling price 1 / 2 / 3 descriptions (Setup - Stock information)

Price 1

Price 2

Price 3

Purchase (price) cost price

No purchase price

Geen inkoopprijs

Bewerk direct de verkoop prijzen vanuit een in een inkoop document. Hier kunt u dan de 3 verkoop prijzen uit osfinancials bewerken bij een gekozen artikel.

Translation

No purchase price
Edit sales prices directly from a purchasing document. Here you can edit the 3 sales prices from osfinancials for a selected item.

Documentation : Not tested. Could not find on Shop.

Edit order quantities and sales per 30 60 90 days

Bewerken bestel aantallen en verkopen per 30 60 90 dagen

Gebruik deze plugin om het bestel ,Minimum en trigger aantal aan te passen tijdens inkoop. Ook ziet u hoe veel producten er in de afgelopen 30 60 90 dagen zijn verkocht. Alleen de verkopen worden daarbij geteld en niet de credit notas.

Translation

Edit order quantities and sales per 30 60 90 days
Use this plugin to adjust the order, minimum and trigger quantity during purchasing. You can also see how many products have been sold in the past 30, 60, 90 days. Only sales are counted and not credit notes.

Documentation : Not tested. Could not find on Shop.

Payment discount

Dynareg Payment discount invoice plugin - Shop - Licence : Once-off -

Enable : "Documenten - Betalings korting in factuur"

Documentation : Help documentation -

"*Betalings korting in factuur*"

"Vul een betalings korting artikel in bij instellen voorraad dan kunt u een percentage opgeven voor de betalings korting."

Translation

Payment discount in documents (Also available in other document types, including invoices)

Enter a payment discount item when setting up stock and you can specify a percentage for the payment

discount.

Outstanding translation labels

Payment discount

Payment discount percentage



Shipping cost

Shipping costs separately on invoice plugin - Shop - Licence : Once-off -

Enable : "Documenten - Verzenden als apart onderdeel"

Documentation : Help documentation -

"*Verzenden als appart onderdeel*"

"Verzendkosten als dropdownkeuzen in document bij instellen voorraad kunt u een artikel groote aangeven welke gebruikt wordt vooor de lijst met verzendkosten."

NOTE: Shipping costs separately on invoice plugin - can be used for sales documents such as invoices, credit notes and quotes. This plugin can also be used for purchase documents such as purchase, supplier return and orders.

Translation

Shipped as a separate part
Shipping costs as drop-down choices in document when setting stock, you can indicate an item size which will be used for the shipping costs list

Outstanding translation labels

Shipment

Shipment amt



Setup - Stock information



Dyna plugins

1. Payment discount debtor - Also lookup Titlebar caption "*Select stock*"

2. Payment discount creditor - Also lookup Titlebar caption "*Select stock*"

3. Ship cost unit price + "*Disable*" on list

Other older translations outstanding

1. Production Contra account - Also lookup Titlebar caption "*Select account*"
2. No calc for backorders to deliver
3. No calc for qty unposted

Inactive stock

> *Dynareg Show inactive items in documents plugin - Shop - Licence : Once-off -*
>
> *Enable : "Documenten - Toon inactive artikelen in documenten"*
>
> *Documentation : Help documentation*

When processing documents, you're required to choose the stock item within the document lines section. By default, only the active stock items are displayed. If a stock item is marked as inactive (disabled) on the Stock form, it won't appear in the Stock lookup. This ensures that only active or enabled items are available for selection in the documents.

Toon inactive artikelen in documenten

Toont inactive artikelen in een document

Translation

Show inactive items in documents

Shows inactive items in a document

NOTE : The "Inactive" checkbox option to show items in a document is available on the Stock lookup works in any Set of Books without this plugin being enabled or disabled.

Inactive - By default only the active items is listed in the Stock lookup lookup. If you select the " *Inactive*" option, it will include Inactive or disabled stock items in the Stock lookup.

You will still be able to update (post) the transactions of inactive (disabled) items included in the document.



Inactive

multilang

Transitional booking

> *Dynareg - Transitional Posting in Documents plugin - Shop - Licence : Once-off -*
>
> *Enable : "Documenten - Transitorisch boeken"*
>
> *Documentation : Help documentation*

"*Transitorisch boeken*

Transitorisch boeken in documenten.

Een extra kolom met subscherm om de transitorische data in te voeren."

Translation

Transitional booking

Transitional posting in documents.

An extra column with sub-screen to enter the transitory data.



Outstanding label translations

Trans details

Transitional items

Spread type

Non

Month start

Month end

Week

Trans account (Maybe need a lookup button but double=click works)

Select account - Lookup - titlebar caption

From date 286

To date 287



Known issue - Adjustments, Stock in and Stock out - layout files

Previous stock adjustments - Stock out document type

- Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating this plugin, will be listed on the document grid under the Stock out document type.

- These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid .
- The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.
- Duplicate document number - The first Stock out document created, also starts with "*ST00001*" which is a duplication of previous stock adjustments before activating Enable this plugin.



Separate item issue (Stock in / Stock out document types)

Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

Enable : "Aparte artikel uitgifte"

Documentation : Help documentation

Apparte artikel uitgifte

Geeft 2 extra documenten waarmee artikel in en uitgifte kan worden ingeboekt. Deze verwerkt dan aantallen en eventueele kosten van verkoop. Met de andere documenten worden dan alleen posten omzet en btw geboekt en geen aantallen meer.

Translation

Separate item issue

Provides 2 additional document types (Stock in and Stock out) with which items can be entered and issued. This then processes quantities and any costs of sales. With the other documents, only turnover and Tax

(VAT/GST/Sales tax) items are recorded and no more quantities.

BUG labels

- Input → Stock in menu should read Stock out as it launches the "*Stock out*" document type. On Documents grid document type Stock in launches creditors.
- Input → Stock out menu should read Stock in as it launches the "*Stock in*" document type. On Documents grid document type Stock out launches debtors.
- Update ledger / Delete documents - Titlebar captions
    - Update documents - Stock in - Delete supplier returns
    - Update documents - Stock out - Delete orders
    - Delete documents - Stock in - Delete supplier returns
    - Delete documents - Stock out - Delete orders
- Update documents - Stock in - Delete supplier returns
- Delete documents - Stock in - Delete supplier returns

Extra stock of correction document Stock in / Out

Dynareg - Extra stock of correction document - Shop - Licence : Once-off -

Extra stock of correction document plugin add the "Stock in / out" as an additional document type.

Enable : "Documenten - Extra stock of correction document"

Documentation : Help documentation - Stock in and Stock out document type

Documentation : Help documentation - Stock in document type

Extra voorraad correctiedocument

Een extra document type om voorraad correcties of eigen verbruik te verklaren.

Translation

Extra stock of correction document

An additional document type to declare stock corrections or self-consumption.

Creates a Stock in / Stock out document type

Separate item issue (Stock in document type only)

Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

To activate the "Dynareg Only purchase via new type" plugin and enable the "Stock in" as an additional document type, you'll need to enable the following plugins:

Enable : "Aparte artickel uitgifte"

Enable : "Alleen inkoop"

Enable : "Verminder herbestel by doorboeken inkoop"

Documentation : Help documentation

BUG : Stock item - Ledger disabled - cannot create new items

Alleen inkoop

Alleen inkoop

Geeft maar 1 extra documenten waarmee artikel innamen kan worden ingeboekt. Deze verwerkt dan aantallen en eventueele kosten van verkoop.

Translation

Purchasing only
Provides only 1 additional document type (stock in) with which item intakes can be booked. This then processes quantities and any costs of sales.

Verminder herbestel by doorboeken inkoop

Verminder herbestel by doorboeken inkoop

Bij doorboeken van een inkoop verlagen van de herbestel

(2ehands winkel)

Translation

Reduce reorders by rebooking purchases
When transferring a purchase, reduce the reorder quantity.
(2nd hand store)
BUG labels

- Input → Stock out menu should read Stock in as it launches the "Stock in" document type. On Documents grid document type Stock in launches creditors.
- Update ledger / Delete documents - Titlebar captions

- Update documents - Stock in - Delete supplier returns
- Delete documents - Stock in - Delete supplier returns

Dynareg - Ecommerce / osCommerce

Ecommerce events

osCommerce - Events voor ecommerce - Shop - Licence : Once-off -

Enable : "Ecommerce - Events voor ecommerce"

"Events voor ecommerce

De events tabel voor Ecommerce."

"*Events plugin basis*

Shop web description

met deze basis plugin kunt u de events functionaliteiten laten toevoegen. Bij de prijs zit de osCommerce plugin, multi-user en het support contract inbegrepen. Dit is de basis voor het geautomatiseerd verwerken van gegevens in osfinancials. U kunt hierdoor complexe omgevingen creëren die uw bedrijfsprocessen ondersteunen en geautomatiseerde verwerking van bijvoorbeeld Afdrukken van uw documenten - Updaten van statussen naar een webshop - Versturen van email - Updaten / omzetten van document type - Herinnering email naar klanten die nog niet hebben gereageerd op hun offerte - Door de structuur van ons product kunnen wij verschillende scenario's implementeren en zijn wij flexibel genoeg om elk bedrijfsproces te optimaliseren."

Translation

Ecommerce events

The events table for Ecommerce.

Events plugin base

Shop web description

With this basic plugin you can add the events functionalities. The price includes the osCommerce plugin, multi-user and the support contract. This is the basis for the automated processing of data in osfinancials. This allows you to create complex environments that support your business processes and automated processing of, for example, Printing your documents - Updating statuses to a webshop - Sending email - Updating / converting document type - Reminder email to customers who have not yet responded to their quote - The structure of our product allows us to implement different scenarios and is flexible enough to optimize any business process.

Documentation : Not tested. Probably need osCommerce or E-Commerce enabled.

Email documents

osCommerce - Email documenten - Shop - Licence : Once-off -

Enable : "Ecommerce - Email documenten"

"Email documenten

Event automatisch emailen documenten"

Translation

Email documents

Event automatically emailing documents

Documentation : Not tested. Probably need osCommerce or E-Commerce enabled.

Update status

osCommerce - Update status - Shop - Licence : Once-off -

Enable : "Ecommerce - Update status"

"*Update status*

Update document status in osCommerce"

Translation

Update status

Update document status in osCommerce

Documentation : Not tested. Probably need osCommerce or E-Commerce enabled.

Update document

osCommerce - Update document - Shop - Licence : Once-off -

Enable : "Ecommerce - Update document"

"*Update document*

Converteerd een document (b.v. offerte) naar een factuur als deze b.v. met ideal is betaald."

Translation

Update document

Converts a document (e.g. quote) to an invoice if this is e.g. payment was made with ideal.

Documentation : Not tested. Probably need osCommerce or E-Commerce enabled.

First email check

osCommerce - Eerste email check - Shop - Licence : Once-off -

Enable : "Ecommerce - Eerste email check"

"*Eerste email check*

Eerste email naar de klant over zijn offerte 7 dagen na datum"

Translation

First email check

First email to the customer about his quote 7 days after date

Documentation : Not tested. Probably need osCommerce or E-Commerce enabled.

Second email announcement

osCommerce - Tweede email aankondiging verwijderen - Shop - Licence : Once-off -

Enable : "Ecommerce - Tweede email aankondiging verwijderen."

"*Tweede email aankondiging verwijderen.*

De tweede email neer de gebruiker dat zijn oder wordt geannuleerd."

Translation

Second email announcement.

The second email informs the user that his quote is being cancelled.

Documentation : Not tested. Probably need osCommerce or E-Commerce enabled.

Delete quote

Delete quote plugin - Shop - Licence : Once-off -

Enable : "Ecommerce - Verwijderen offerte"

"*Verwijderen offerte*

Offerte verwijderen uit osFinancials"

"*Deze event verwijdert automatisch een offerte als deze een status heeft en ouder is dan een bepaalde datum.*

Hierin kunnen afwijkende keuzes worden gemaakt en de event kan worden herhaalt waardoor er veel mogelijkheden zijn."

Translation

Delete quote

Remove quote from osFinancials

This event automatically deletes a quote if it has a status and is older than a certain date. Different choices can be made and the event can be repeated, offering many possibilities.

Documentation : Not tested. Probably need osCommerce or E-Commerce enabled.

Dynareg - Stock

Stock -> Limit on creditor with stock lookup

Dynareg Limit by Creditor with selection list plugin - Shop - Licence : Once-off -

Enable : "Voorraad - Limiteer crediteur met keuze"

Documentation : Help documentation -

Voorraad -> Limiteer op crediteur met keuze

Limiteer op crediter met keuzen lijst,

Translation

Stock -> Limit on creditor with stock lookup

Limit on creditor with selection list,

Inactive stock in documents

"*Inactive vooraad in documenten*

Verbergt de inactive artikelen in de selectie lijst."

Translation

Inactive stock in documents

Hides the inactive items in the selection list.

Does not seem to work - lists only active stock items - (set inactive on Stock item form, does not include inactive items on the Stock lookup).

Dynareg - bank import

Dynareg bank import - Shop - Licence : Once-off -

Enable : "bank import - Match ideal op omschrijving"

Documentation : Help documentatio - Bank import plugin -

"b*ank import*

Match ideal on omschrywing

Kan de ideal betalingen die op een bank gebeuren matchen op document nummer."

Translation

Bank import

Match ideal on description

Can match the ideal payments made at a bank by document number.

Shop description

Bank and Ideal payments match

With this addition to the bank import plugin , payment on your bank account can automatically been matched. The matching is done by text description/document number. The matching is not only available for ' normal' bank payment, but also for Ideal payments. Matching Ideal payments is only possible when there are individual payment lines on your bank account instead of batch payments.

The plugin doesn't has to be downloaded. It will be activated by a code. You will receive the code(s) and instructions through mail within two workdays after payment.

NOTE : Match Ideal Bank @*@: A specific feature integrating iDEAL online payment method for payments or transactions within the Bank-import plugin. This context menu item is already available in Batch entry screens within the Bank-import plugin whether this Dynareg "*bank import - Match ideal on omschrywing"* is enabled or disabled.

Dynareg - Free fields

These files looks like they exists in the " *BIN\SQL\FIREBIRD* " folder
Also some files with a x prefixed in the file name:

xCUST_CUSTITEMSEARCH.txt"

xCUST_FREEDESCLOOKUPRESULT.txt"

xCUST_FREEDESCLOOKUPTYPE.txt"

xCUST_FREEFIELDFINDCRBARCODE.txt"

xCUST_FREEFIELDFINDCRBARCODE_old.txt"

xCUST_FREEFIELDFINDCRCODE.txt"

xCUST_FREEFIELDFINDCRCODE_old.txt"

xCUST_GETSUPCODE.txt"

xCUST_PURCHASEAFTERSAVE.TXT"

xCUST_PURCHASEAFTERSAVE_old.TXT"

xCUST_SELECTDISCOUNTSTOCKCRED.TXT"

xCUST_SELECTREORD.TXT"

xCUST_SELECTREORDBEST.TXT"

xCUST_SELECTREORDBEST_ORD.TXT"

xCUST_SELECTREORDSUP.TXT"

XCUST_SELECTSUPPPRICE.TXT"

xCUST_SELECTUNITONCRED.TXT"

xCUSTITEMSEARCH.txt"

xFREESTOCKLOOKUP.TXT"

xFREESTOCKLOOKUPCR.TXT"

Creditors codes

Crediteuren codes

Crediteuren code in vrije velden met prijs barcode en voorraadcode

Translation

Creditors codes
Creditor code in free fields with price barcode and stock code

Documentation : Not tested.

File for free lookup codes.

Bestand voor vrij opzoeken code's

Bestand om de vrij in te vullen codes te kunnen doorzoeken in een document.

Translation

File for free lookup codes.

File for searching free entered codes in a document.

Error

File saved!
BIN\SQL\FIREBIRD\CR_FREESTOCKLOOKUP.TXT

Documentation : Not tested.

Select for the adjusted prices.

Select voor de aangepaste prijzen.

Met deze sql worden de prijzen die zijn ingevoerd gebruikt bij een inkoop.

Translation

Select for the adjusted prices.

With this SQL, the prices entered are used for a purchase.

Error

File saved!
BIN\SQL\FIREBIRD\CR_CUST_SELECTREORDBEST.TXT

List of items to be updated for supplier 1.

Lijst met te update artikelen voor 1 leverancier.

De lijst voor het verwerken van een artikel lijzt bij herbestelen.

Translation

List of items to be updated for supplier 1.

The list for processing an item is available when reordering.

Error

File saved!
BIN\SQL\FIREBIRD\CR_CUST_SELECTREORDSUP.TXT

Documentation : Not tested.

List of items to order

Lijst met te bestellen artikelen

Lijst voor aangepast selectie artikelen.

Translation

List of items to order

List for custom selection items.

Error

> File saved!
> BIN\SQL\FIREBIRD\CR_CUST_SELECTREORD.TXT

Documentation : Not tested.

Edit unit and creditor price automatically

Bewerk prijs unit en crediteur automatisch

Crediteuren code in vrije velden met prijs barcode en voorraadcode

Translation

Edit unit and creditor price automatically

Creditor code in free fields with price barcode and stock code

Error

> File saved!
> BIN\SQL\FIREBIRD\CR_CUST_PURCHASEAFTERSAVE.TXT

Documentation : Not tested.

Item packaging per supplier

Artikel verpakking per leverancier

Crediteuren code in vrije velden met prijs barcode en voorraadcode

Translation

Item packaging per supplier

Creditor code in free fields with price barcode and stock code

Error

File saved!
BIN\SQL\FIREBIRD\CR_CUST_SELECTUNITONCRED.TXT

Documentation : Not tested.

Creditor code for purchasing

Crediteuren code bij inkoop

Crediteuren code bij inkoop document types (inkoop, bestelling, retourzending)

Translation

Creditor code for purchasing

Creditor code for purchasing document types (purchase, order, return shipment)

Error

File saved!
BIN\SQL\FIREBIRD\CR_CUST_GETSUPCODE.TXT

Documentation : Not tested.

Dynareg - Document layouts

G-accounts plugin - Shop - Licence : Once-off -

Enable : "Document layouts - G-rekeningen"

"*G-rekeningen*

G-rekeningen invoer velden voor een aangepaste layout.

Deze kunnen worden ingesteld bij instellen->Administratie-Bedrijfs gegevens."

Translation

Document layouts

G-accounts

G-accounts input fields for a customized layout.

These can be set at Setup -> Company information.

Documentation : Not tested.

Dynareg - Point-of-Sale - Free POS -Plugins

Gratis kassa plugin - Shop - Licence : Once-off -

Enable : "Gratis kassa - On click debiteuren lijst"

"*Gratis kassa*

On click debiteuren lijst

Met een drup op F5 gelijk de klanten lijst krijgen i.p.v. het tussen scherm. Hierdoor is het invullen van de extra data niet meer mogelijk."

Translation

Free POS

On click debtor list
With a press of F5 you immediately get the customer list instead of the intermediate screen. This means that it is no longer possible to enter the additional data.

Documentation : Not tested.

Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

Dynareg plugins

The DYNADBREG Plugin cannot be removed from the Plugins → Tools menu, as it is necessary for the functioning of certain features in osFinancials5 and TurboCASH5.

The Dyna reg Plugins can be accessed from the Plugins menu under the Setup ribbon, provided they are activated in the Tools → Activate plugins menu. This collection comprises additional plugins for documents, e-commerce, bank import, free fields stock, document layouts, and Free POS (Standard POS). These plugins are available for purchase from our online shop and can be enabled accordingly.

Activation of Dynareg Plugins

Once you have purchased plugins from our shop, follow these steps to enable them:

1. Navigate to Plugins → Tools → DYNADBREG.



2. Select the desired option and click the Enable button. A confirmation message will appear.

   "Add new item?"

3. Click OK. Another confirmation message will appear.

   "Script executed!"

4. Click OK.

5. Click Close and reopen the Set of Books for this plugin to take effect.

For more information and to purchase plugins, visit: [osFinancials Webshop - Small Adjustments](#).

Created with the Standard Edition of HelpNDoc: Effortlessly Support Your Windows Applications with HelpNDoc's CHM Generation

Dynareg - Email address per document

The "*E-mail address per document"* plugin is by default activated and enabled. The functionality of the "*E-mail address per document"* plugin available on the header document entry screens of all unposted sales documents such as invoices, credit notes, and quotes, as well as purchase documents such as purchases, supplier returns, and orders. This feature is already activated and enabled by default for all Sets of Books, including options for creating new Sets of Books for both Firebird and MSSQL database types. Users don't need to enable this plugin separately.



This functionality enhances document management by allowing users to enter multiple email addresses separated by semicolons in the email address field of the document header. In existing documents with one email address, users can simply add a semicolon after the existing address and input a valid second email address.

Disable confirmation message

> Dropping this will delete all data for this column continue?

Should you click Yes to disable this plugin, you may encounter errors.



WARNING: Disabling the "E-mail address per document" plugin may result in the following errors:

Error

> Dynamic SQL Error
> SQL error code = -206
> Column unknown
> DOCHEAD.X_CUSTOMERS_EMAIL_ADDRESS
> At line 68, column 13

Access violation

> Access violation at address 656F0082 in module 'rtl290.bpl'. Read of address 00000004.

Pointer operation error

> Invalid pointer operation.

If you accidentally disable this plugin and encounter these errors, follow these steps:

1. *Navigate to Plugins → Tools → DYNADBREG.*
2. *Enable the 'E-mail address per document' plugin again and reopen your Set of Books.*

Created with the Standard Edition of HelpNDoc: Full-featured EBook editor

Dynareg - Delivery dates

Dynareg Delivery date plugins

Dynareg Delivery date plugins is a series of four plugins. Each successive plugin in the series, including Dynareg Delivery date 2, Dynareg Delivery date 3, and Dynareg Delivery date 4, offers the ability to add an additional delivery date field to document lines within osFinancials5/TurboCASH5.

By providing the option to add up to four delivery dates on document lines, these plugins offer significant flexibility for businesses to track and manage multiple aspects of their delivery schedules. Users can customize each delivery date field according to their specific requirements, allowing for more granular control over delivery management processes.



With this capability, users can handle complex scenarios such as staggered deliveries, partial shipments, or multiple stages in the delivery process more effectively. Additionally, it provides a comprehensive solution for businesses that require detailed tracking and reporting on various delivery dates associated with their sales and purchase transactions.

You may adjust or edit these date by selecting the dates in unposted documents.

In posted documents you need to enter a date on the "*Edit date*" screen.



In posted documents, cannot select a date, but you may enter or edit a date.



Dynareg Delivery date 1 plugin

Dynareg Delivery date 1 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Aflever datum in dokument regels"

The "*Dynareg Delivery date 1"* plugin will add a "*Delivery date*" column in the document lines in sales documents, (invoices, credit notes and quotes).

The "*Delivery date*" column in the document lines is also available in purchase documents (purchases, supplier returns and orders).



Provides an additional date field in document lines where you can enter a delevery date that can be edited even after you have processed the document.

Overall, the "*Dynareg Delivery date 1*" plugin likely aims to improve order management and logistics within osFinancials5/TurboCASH5 by introducing features related to specifying, tracking, and managing delivery dates for orders and transactions.

The "*Dynareg Delivery date 1*" plugin is designed to enhance document management in sales and purchase processes. Specifically, it adds a "*Delivery date*" column to the document lines within sales documents such as invoices, credit notes, and quotes.

Additionally, this column is also made available in purchase documents like purchases, supplier returns, and orders. This functionality likely streamlines tracking and managing delivery dates for both outgoing and incoming goods or services.

Dynareg Delivery date 2 plugin

Dynareg Delivery date 2 plugin - Shop - Licence : Once-off -

Enable : "Documenten - 2e Aflever datum in dokument regels"

In your documents you now have a 2nd date field per line. In combination with the "*Delivery Date*" plugin, you can, for example, indicate a delivery period between date 1 and date 2 on your invoices.



The "*Dynareg Delivery date 2*" plugin builds upon the functionality of the first delivery date, "*Dynareg Delivery date 1*" plugin by providing an additional delivery date field in document lines. This new field allows users to enter and edit delivery dates even after the document has been processed. This enhancement likely offers more flexibility and control in managing delivery schedules for sales documents such as invoices, credit notes, and quotes, as well as in purchase documents like purchases, supplier returns, and orders.

The plugin extends its features to both sales and purchase processes, adding the "*Delivery date 2*" column to document lines in sales documents such as invoices, credit notes, and quotes, as well as in purchase documents like purchases, supplier returns, and orders. By offering an extra date column, it further streamlines the process of tracking and managing delivery dates for both outbound and inbound items or services.

Dynareg Delivery date 3 plugin

Dynareg Delivery date 3 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Vrijedatum 3"

The "*Dynareg Delivery date 3*" plugin builds upon the functionality of the first two delivery dates, "*Dynareg Delivery date 1*" plugin and "*Dynareg Delivery date 2*" plugin by providing an additional delivery date field in document lines. This new field allows users to enter and edit delivery dates even after the document has been processed. This enhancement likely offers more flexibility and control in managing delivery schedules for sales documents such as invoices, credit notes, and quotes, as well as in purchase documents like purchases, supplier returns, and orders.

Dynareg Delivery date 4 plugin

Dynareg Delivery date 4 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Vrijedatum 4"

The "*Dynareg Delivery date 4*" plugin builds upon the functionality of the first three delivery dates, "*Dynareg Delivery date 1*" plugin, "*Dynareg Delivery date 2*" plugin and "*Dynareg Delivery date 3*" plugin by providing an additional delivery date field in document lines. This new field allows users to enter and edit delivery

dates even after the document has been processed. This enhancement likely offers more flexibility and control in managing delivery schedules for sales documents such as invoices, credit notes, and quotes, as well as in purchase documents like purchases, supplier returns, and orders.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

Dynareg - Numbers based on date and date 2

Dynareg Numbers based on date and date 2 plugin - Shop - Licence : Once-off -

Enable : "Documenten - Aantalen op basis van datum en datum 2"

Calculate quantities based on the date field

Shop

Numbers based on dates 1 and 2

Multiplies the item total amount based on the quantity and period between date field 1 and date field 2.

Created with the Standard Edition of HelpNDoc: Free PDF documentation generator

Dynareg - Checkbox in documents

Dynareg - Checkbox in document lines plugin

Dynareg Checkbox in document lines plugin - Shop - Licence : Once-off -

Enable : "Documenten - Check box in documentregel"

The "*Dynareg - Checkbox in document lines*" plugin adds a "*Check*" column to the lines in the document entry screen, allowing users to tick or untick checkboxes for selected items. These checkboxes are available for both sales and purchase documents (invoices, credit notes, quotes, purchases, supplier returns, and orders).



This plugin ensures that the selected checkboxes are saved and retained even after copying or converting documents. However, it's worth noting that checkboxes for comments will not be retained after copying or converting documents.

Advantages of checkboxes

Having a check column for items in the document entry screen offers several advantages:

1. Easier Control with Many Items: When dealing with documents containing numerous items, such as invoices with multiple line items, having a check column allows users to easily keep track of which items have been processed, verified, or attended to. This can streamline workflows and reduce the likelihood of overlooking items.

2. Improved Accuracy and Accountability: By providing a visual indicator (such as a checked box) next to each item, users can quickly verify that all necessary actions have been taken for each item. This can enhance accuracy in document processing and help ensure that no items are missed or duplicated.

3. Efficient Order Fulfillment: In scenarios like purchase orders or sales orders, the check column can be used to mark items as collected or fulfilled. This is particularly useful in retail or warehouse environments where goods need to be checked off as they are picked up or shipped out. It helps in ensuring that all items are accounted for before finalizing the transaction.

4. Enhanced User Experience: The check column provides a straightforward and intuitive interface for users to manage document entries. It reduces the cognitive load by offering a visual cue for item status, making the overall process more user-friendly.

5. Audit Trail and Documentation: The checkboxes serve as a form of documentation, indicating which actions have been completed or which items have been processed. This can be valuable for audit purposes or for tracing the history of document entries.

Overall, the check column in the document entry screen offers convenience, accuracy, and efficiency in managing documents with multiple items, contributing to smoother operations and improved user experience.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Dynareg - Additional field for an account in documents

Dynareg Additional field for an account in documents plugin - Shop - Licence : Once-off -

Enable : "Documenten - Extra rekening veld in documentregel"

The "*Dynareg Additional field for an account in documents*" plugin for osFinancials5/TurboCASH5 adds a debtor account in the last column of the lines in the document entry screen.

The debtor accounts can be selected in column for "*Debtors*" accounts in the last column of each line. The column for "*Debtors*" accounts is available in both sales documents, (invoices, credit notes and quotes) and purchase documents (purchases, supplier returns and orders).



To add a debtor account, you need to double-click on the "*Debtors*" column heading.

The item code (stock code) will add the account code of the selected debtor account in the "*Item no.*" column.

In posted documents, you cannot add or change the debtor account.

Overall, the "*Dynareg Additional field for an account in documents*" plugin enhances the functionality of osFinancials5/TurboCASH5 by providing a convenient way to input and track debtor account information within document entries, contributing to improved accuracy and efficiency in financial management processes.\

Created with the Standard Edition of HelpNDoc: Easily create iPhone documentation

Dynareg - Payment discount invoice plugin

Dynareg Payment discount invoice plugin - Shop - Licence : Once-off -

Enable : "Betalings korting in factuur"

The "*Dynareg Payment discount invoice*" plugin is designed to facilitate and process upfront discount percentages for sales documents (invoices, credit notes) to customers.

This versatile plugin can also be configured and utilised for purchase discounts (purchases, supplier returns, and orders) to suppliers.

By providing the ability to apply discounts strategically in both sales and purchase transactions, businesses can enhance cash flow management and foster stronger relationships with both customers and suppliers.

Activation of the "*Dynareg Payment discount invoice*" plugin

To activate the "Dynareg Payment discount invoice" plugin follow these steps:

1.

1. Access Plugins: Navigate to Plugins → Tools → DYNADBREG menu.
2. Enable the plugin: Select the "*Betalings korting in factuur*" option and click Enable.
3. Reopen Set of Books: Once you've enbaled the DYNADBREG, reopen your Set of Books. This step is essential for the changes to take effect.

Configuring your Set of Books for the "*Dynareg Payment discount invoice*" plugin

Before you can use this plugin, the need to enable the "Payment discount invoice" plugin in Plugins → Tools → DYNADBREG and reopen your Set of Books.
Once activated, you need to check and configure your Set of Books. The basic settings is as follows:

- Ledger accounts - Setup → Accounts (Setup ribbon).
  - Payment discount account for sales - Locate a Payment discount for sales in your chart of accounts. If no account is available, you need to add a new account.
  - Payment discount account for purchases - To use this plugin for Payment discounts for purchase documents (purchases, supplier returns and orders) you need to locate a Payment discount for purchases. If no account is available, you need to add a new account.
- Stock item - Stock items on Default ribbon).
  - Payment discount for sales documents - Add a "*Payment discount*" as a "*Sales (no stock)*" stock item type for sales documents, such as invoices, credit notes and quotes.
    - § You need to link the default ledger account to record the discount to the "Payment discount" account.
    - § Do not enter selling prices, as the specified discount percentage added in the "*Document entry*" screen will automatically calculate the discount amount on the total

price of the other selected items included in the sales documents.



- Payment discount for purchase documents - Add a "*Payment discount*" as a Purchase (no stock) stock item type for purchase documents, such as purchases, supplier returns, and orders.
  - § You need to link the default ledger account to record the discount to the "Payment discount" account.
  - § No purchase prices or cost prices should be entered as the specified discount percentage added in the "Document entry" screen will automatically calculate the discount amount on the total price of the other selected items included in the purchase document.



- Link Payment Discounts Stock Items - Setup → Stock information (Setup ribbon).
  - Payment discount debtor - Link your Payment discounts stock items for sales documents in the "*Payment discount debtor*" field.
  - Payment discount creditor - Link your Payment discounts stock items for purchase documents in the "*Payment discount creditor*" field.



Once these configurations are completed, you are ready to utilise the "*Dynareg Payment discount invoice*" plugin for both sales documents, including invoices, credit notes and quotes; and purchase documents, including purchases, supplier returns, and orders. These settings ensure that the plugin functions correctly and records payment discounts accurately in your Set of Books.

Processing Sales documents - Payment discount

Once the "*Dynareg Payment discount invoice*" plugin is correctly configured, you can process sales documents such as invoices, credit notes, and quotes. In the Payment discount tab on the document header, enter the "*Payment discount percentage*".

When invoices and credit notes are posted or updated to the ledger, the payment discount transactions will be included in the "Payment discount" account. However, quotes cannot be posted or updated to the ledger and will not generate any transactions. Once a quote is accepted and confirmed, it will be converted to an invoice. These converted quotes can then be posted or updated to the ledger as invoices.

If you choose not to apply a payment discount to the invoice, simply leave the "*Payment discount percentage*" as "0". Please note that the invoices, credit notes, and quotes will not print the payment discount on the document layout file.

Examples Sales Document Processing Layout and Transaction Screenshots

Now, let's explore an example layout file for invoice, credit note, and quote processing, along with screenshots of the related transactions.

Processing Invoices - Payment discount debtors

When processing invoices, a Payment discount tab is included in the document header. Here, you can enter a percentage discount. This will incorporate the Payment discount into the printed invoice document layout file. The stock item "*Payment discount - debtor*" will be added, and the discount will be calculated based on the total of all items included in the invoice.



If the invoice has not been posted (updated to the ledger), you can simply edit the invoice without needing to process a credit note. In such cases, there's no necessity to issue a credit note. However, if you have edited an invoice, make sure that the edited or changed invoice is forwarded to the customer.

Example : Printed - Invoice with Payment discount applied



Example : Transactions - T-accounts - Posted Invoice with Payment discount applied



Processing Credit notes - Payment discount debtors

When processing credit notes to cancel an invoice, remove an item, or adjust the selling price, ensure that the correct payment discount percentage is included. If a payment discount was applied to the original invoice and it has already been posted to the ledger, it's important to reflect this accurately in the credit note.



Example : Printed - Credit note with Payment discount applied



Example : Transactions - T-accounts - Posted Credit note with Payment discount applied



Example : Printed - Quote with Payment discount applied



Processing Purchase documents - Payment discount

Once the "*Dynareg Payment discount invoice*" plugin is correctly configured, you can process purchase documents such as purchases, supplier returns, and orders. In the Payment discount tab on the document header, enter the "*Payment discount percentage*".

When purchases and supplier returns are posted or updated to the ledger, the payment discount transactions will be included in the "*Payment discount*" account. However, orders cannot be posted or updated to the ledger and will not generate any transactions. Once an order is accepted and confirmed, it will be converted to a purchase. These converted orders can then be posted or updated to the ledger as purchases.

If you choose not to apply a payment discount to the purchases, supplier returns, and orders, simply leave the "*Payment discount percentage*" as "0". Please note that the purchases, supplier returns, and orders will not print the payment discount on the document layout file.

Example Purchase Document Processing Layout and Transaction Screenshots

Now, let's explore an example layout file for purchase, supplier return and order processing, along with screenshots of the related transactions.

Processing Purchase - Payment discount creditors

When processing invoices, a Payment discount tab is included in the document header. Here, you can enter a percentage discount. This will incorporate the Payment discount into the printed purchase document layout file. The stock item "*Payment discount - creditor*" will be added, and the discount will be calculated based on the total of all items included in the purchase.



If the purchase has not been posted (updated to the ledger), you can simply edit the purchase without needing to process asupplier return. In such cases, there's no necessity to issue a supplier return. However, if you have edited an purchase, make sure that the edited or changed purchase is forwarded to the supplier.

Example : Printed - Purchase with Payment discount applied



Example : Transactions - T-accounts - Posted Purchase with Payment discount applied



Processing Supplier returns - Payment discount creditors

When processing a supplier return to cancel a purchase, remove an item, or adjust the purchase or cost price, ensure that the correct payment discount percentage is included. If a payment discount was applied to the original purchase and it has already been posted to the ledger, it's important to reflect this accurately in the a supplier return.



Example : Printed - Supplier return with Payment discount applied



Example : Transactions - T-accounts - Posted supplier return with Payment discount applied



Example : Printed - Order with Payment discount applied



Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Dynareg - Shipping costs separately on invoice plugin

Shipping costs separately on invoice plugin - Shop - Licence : Once-off -

Enable : "Verzenden als apart onderdeel"

After processing shipping costs on an invoice using the "Shipping costs separately on invoice" plugin, it's important to reopen your Set of Books after disabling the plugin. Failure to do so may result in encountering an error message when accessing any document type:

```
tblDocHeader: Field 'WSHIPSTOCKID' not found
```

This error indicates that the 'WSHIPSTOCKID' field is missing from the 'tblDocHeader' table.

To resolve this issue, simply reopen your Set of Books. Alternatively, if you intend to continue using this plugin, you may re-enable it.

The "*Dyna - Shipping costs separately on invoice*" plugin will add a "*Shipment*" option in the document header. Once you have added your stock items or products in your document, and you wish to add shipment cost to the document, simply select the shipment item from the drop-down list and enter the shipment amount.

The shipment item and shipment cost will be included when printing document layout file for sales documents (invoices, credit notes and quotes).

When the Invoices and Credit notes is posted (updated to the ledger), it will include the shipping cost transactions.

This option is available on both sales documents (invoices, credit notes, and quotes) as well as purchase documents (purchases, supplier returns and orders).

Activation of the "Dyna - Shipping costs separately on invoice" plugin

To activate the "Dyna - Shipping costs separately on invoice" plugin follow these steps:

1. Access Plugins: Navigate to Plugins → Tools → DYNADBREG menu.
2. Enable the plugin: Select the "*Verzenden als apart onderdeel*" option and click Enable.
3. Reopen Set of Books: Once you've enabled the DYNADBREG, reopen your Set of Books. This step is essential for the changes to take effect.

Configuration Set of Books for the "Dyna - Shipping costs separately on invoice" plugin

After activating the "*Dyna - Shipping costs separately on invoice" plugin*, you need to reopen your Set of Books for the plugin to take effect. Once you have reopened your Set of Books, follow these steps to set up your configuration:

1. Setup Shipcost Unit Type:
    - After reopening your Set of Books, go to Setup → Stock Information (Setup ribbon).
    - You'll notice a new option labeled "*Shipcost unit type*" added to the Stock Information setup.



- Initially, the setting is likely to be "*Disabled*."
- To enable the plugin, select a unit description from the list. If there's no suitable unit available, you may need to add a new unit (Units tab on Stock Information screen). For example, you can add "*Shipping*" as a unit.

2. Setup Ledger Accounts:
   - Locate the appropriate ledger accounts for shipping costs associated with sales and purchases in your chart of accounts to record transactions related to shipping costs for both sales and purchases. You can locate the shipping cost accounts in your Trial Balance. If you cannot find the appropriate accounts for shipping costs, you may create or add them in Setup → Accounts on the Setup ribbon.
   - These accounts will be linked to a stock items for shipping costs in the next step.
3. Add Stock Items for Shipment:
   - Add stock items for shipment in the Stock items (Default ribbon).
   - Link these stock items to the "*Shipping*" unit that you've added or selected.
     - Shipping cost for sales - Select the appropriate ledger account to record the

transactions for sales related to shipping cost.



§ Shipping cost for purchases - Select the appropriate ledger account to record the transactions for purchases related to shipping cost.



- If Tax VAT/GST/Sales tax applies to shipping costs in your jurisdiction, it is important to select the correct tax code. For shipping costs on sales documents, Output Tax may be applicable. For shipping costs on purchase documents, Input Tax may be applicable.

  IMPORTANT: In these simplified examples, for processing shipping costs on sales documents and purchase documents, Tax is not included on shipping cost transactions.

Once these configurations are completed, you are ready to utilise the "*Dyna - Shipping costs separately on invoice*" plugin for both sales documents, including invoices, credit notes and quotes; and purchase documents, including purchases, supplier returns, and orders. These settings ensure that the plugin functions correctly and records shipping accurately in your Set of Books.

Processing Shipping Costs in Sales Documents

Once the "*Dyna - Shipping costs separately on invoice*" plugin is correctly configured, it will add a "*Shipment*" option in the document header, You can process sales documents such as invoices, credit notes, and quotes. In the Shipment section on the document header, select the relevant shipping cost stock item from the drop-down list and enter the "*Shipment amount*".

When invoices and credit notes are posted or updated to the ledger, the transactions shipment will be included in the "*Shipping cost*" account. However, quotes cannot be posted or updated to the ledger and will not generate any transactions. Once a quote is accepted and confirmed, it will be converted to an

invoice. These converted quotes can then be posted or updated to the ledger as invoices.

If you choose not to apply a shipping cost to the invoice, simply leave the "*Shipment amount*" as "0". Please note that the invoices, credit notes, and quotes will not print the shipping cost on the document layout file.

Examples Sales Document Processing Layout and Transaction Screenshots

Now, let's explore an example layout file for invoice, credit note, and quote processing, along with screenshots of the related transactions.

Processing Shipping Costs in Invoices



If the amount entered in the Shipment amount field of the document entry screen is 0, no shipping cost will be included in the invoice.

If the invoice has not been posted (updated to the ledger), you can simply edit the invoice without needing to process a credit note. In such cases, there's no necessity to issue a credit note. However, if you have edited an invoice, make sure that the edited or changed invoice is forwarded to the customer.

Example : Printed - Invoice with Shipping cost

If you have selected a product and a shipment stock item, and entered a shipment amount, the shipping stock item will be added to the document layout file. In the case of an invoice, the debtor (customer/client) will be invoiced to pay for the selected stock items (products) and the shipping costs.



If the amount entered in the Shipping amount field of the document entry screen is 0, no shipping cost will be included in the invoice.

Example : Transactions - Invoice with Shipping cost



Processing Shipping Costs in Credit notes

When processing credit notes to cancel an invoice, remove an item, or adjust the selling price, ensure that the correct shipping cost is included. If a shipment cost was applied to the original invoice and it has already been posted to the ledger, it's important to reflect this accurately in the credit note.



Example : Printed - Credit note with Shipping cost



Example : Transactions - Credit note with Shipping cost



Example : Printed - Quote with Shipping cost



Processing Purchase documents - Shipping cost

Once the "*Dyna - Shipping costs separately on invoice*" plugin is correctly configured, it will add a "*Shipment*" option in the document header, You can process purchase documents such as purchases, supplier returns, and orders. In the Shipment section on the document header, select the relevant shipping cost stock item from the drop-down list and enter the "*Shipment amount*".

When purchases and supplier returns are posted or updated to the ledger, the transactions shipment will be included in the "*Shipping cost*" account. However, orders cannot be posted or updated to the ledger and will not generate any transactions. Once an order is accepted and confirmed, it will be converted to a purchase. These converted orders can then be posted or updated to the ledger as purchases.

If you choose not to apply a shipping cost to purchases, supplier returns, and orders, simply leave the "*Shipment amount*" as "0". Please note that the purchases, supplier returns, and orders will not print the shipping cost on the document layout file.

Example Purchase Document Processing Layout and Transaction Screenshots

Now, let's explore an example layout file for purchase, supplier return and order processing, along with screenshots of the related transactions.

Processing Purchase with Shipping cost on purchases

When processing invoices, a Payment discount tab is included in the document header. Here, you can enter a percentage discount. This will incorporate the Payment discount into the printed purchase document layout file. The stock item "*Payment discount - creditor*" will be added, and the discount will be calculated based on the total of all items included in the purchase.



If the purchase has not been posted (updated to the ledger), you can simply edit the purchase without needing to process a supplier return. In such cases, there's no necessity to issue a supplier return. However, if you have edited an purchase, make sure that the edited or changed purchase is forwarded to the supplier.

Example : Printed - Purchase with Shipping cost on purchases



Example : Transactions - T-accounts - Posted Purchase with Shipping cost on purchases



Processing Supplier returns with Shipping cost on purchases

When processing a supplier return to cancel a purchase, remove an item, or adjust the purchase or cost price, ensure that the correct shipment cost is included. If a shipment cost was included to the original purchase and it has already been posted to the ledger, it's important to reflect this accurately in the a supplier return.



Example : Printed - Supplier return with Shipping cost on purchases



Example : Transactions - T-accounts - Posted supplier return with Shipping cost on purchases



Example : Printed - Order with Shipping cost on purchases



Created with the Standard Edition of HelpNDoc: Say Goodbye to Documentation Headaches with a Help Authoring Tool

Dynareg - Bruto margin in documents plugin

Dynareg Bruto margin in documents plugin - Shop - Licence : Once-off -

Enable : "Bruto winst in documenten"

The "*Dynareg Bruto Margin in Documents*" plugin for osFinancials5/TurboCASH5 is a valuable tool for businesses looking to manage their margins more effectively. By providing an additional column in sales documents, (invoices, credit notes and quotes) that displays the average purchase price or latest cost price of a product. The gross margin is the difference between the selling price and the average purchase price

or latest cost price of a product, it offers users the ability to assess the impact of discounts or reductions on their overall margins.



This column will not be available on purchase documents (purchases, supplier returns and orders).

This real-time adjustment feature is particularly useful, as it enables businesses to instantly see how changes in margins per line affect the total margin of all products. This level of visibility can help businesses make more informed decisions about pricing strategies and discounting practices, ultimately leading to better financial performance.

Overall, it seems like a plugin that could greatly enhance the analytical capabilities of osFinancials5/TurboCASH5 users, providing them with valuable insights into their margins and helping them optimize their pricing strategies.

Created with the Standard Edition of HelpNDoc: Step-by-Step Guide: How to Turn Your Word Document into an eBook

Dynareg - Selling prices in purchase documents plugin

Dynareg - Directly Edit Sales Prices in Purchase Documents Plugin - Shop - Licence : Once-off - Enable : "Verkoopprijs bij inkoop documenten"

This plugin allows you to edit the three sales prices within a purchase document (purchase, supplier return, and order) for a selected item. The updated selling prices will be reflected in the Ledger tab of the stock item.



You can edit the prices inclusive or exclusive of Tax (VAT/GST/Sales tax). Additionally:

- Default Supplier: You may choose to apply these changes for the default supplier, if one is set for the selected stock item.
- Plugins button: If any supported activated plugins are available for the selling price feature, such as the "*Charter plugin*", you may launch them from the Plugins button.

Please note that this option is not available for sales documents (invoices, credit notes, and quotes).

Created with the Standard Edition of HelpNDoc: Free HTML Help documentation generator

Dynareg - Free lookup

Dynareg Fee lookup plugin

Enable : "Documenten - Vrije keuzenlijst"

When activated, the "Free selection list" plugin adds "*Free lookup*" checkboxes in the document lines. These checkboxes are available in all unposted sales documents such as invoices, credit notes, and quotes, as well as purchase documents such as purchases, supplier returns, and orders.



The "*Free lookup*" will be added as a "*Reporting group*" in Setup → Groups. You have the option to translate or edit the Group name "*Free lookup*" to suit your specific requirements. Additionally, you can create groups tailored to your specific needs.



Created with the Standard Edition of HelpNDoc: HelpNDoc's Project Analyzer: Incredible documentation assistant

Dynareg - Inactive items

Dynareg - Show inactive items in documents plugin

Dynareg Show inactive items in documents plugin - Shop - Licence : Once-off -

Enable : "Documenten - Toon inactive artikelen in documenten"

When processing documents, you're required to choose the stock item within the document lines section. By default, only the active stock items are displayed. If a stock item is marked as inactive (disabled) on the Stock form, it won't appear in the Stock lookup. This ensures that only active or enabled items are available for selection in the documents.



If you need to select disabled items in documents, simply check the "*Inactive*" box and click the Search button. This action will include inactive or disabled stock items in the lookup results.



If you've selected an inactive (disabled) item and included it in your sales or purchase documents, you'll still be able to update (post) the transactions involving inactive items that are part of the document.

Created with the Standard Edition of HelpNDoc: Effortlessly Convert Your Markdown Content with HelpNDoc

Dynareg - Transitional data

Dynareg - Transitional Posting in Documents Plugin

Dynareg - Transitional Posting in Documents plugin - Shop - Licence : Once-off -

Enable : "Documenten - Transitorisch boeken"

The "*Dyna Transitional Posting in Documents*" plugin for osFinancials5/TurboCASH5 introduces an additional column with a sub-screen to input transitory data within documents. This feature streamlines the management of transitional or temporary information linked with each line item in the document.

Once this plugin is enabled and your Set of Books is reopened, it will incorporate the "*Trans details*" column in sales and purchase document entry screens.



Within each document line, you can select the stock item and double-click on the " *Trans details*" column. This action opens the "*Transitional items*" screen.



Here you can specify:

- Spread type: Choose between "*Month start*", "*Month end*", or "*Week*".
- Trans account: Select a transitional account. Note that only Balance sheet type ledger accounts

(excluding Bank accounts and Tax codes) will be available for selection.

- Dates: Confirm or choose the "*From date*" and "*To date*".

Clicking OK saves the transitional data. Upon moving to another line, an "*X*" appears in the "*Trans details*" column for the item, indicating the presence of transitional data.

If you need to edit the transitional data for the item, simply double-click on the "*Trans details*" column or click the "*Lookup*" icon at the end of the column.

Overall, the "*Dyna Transitional Posting in Documents*" plugin enhances osFinancials5/TurboCASH5 by offering a convenient method to manage and record transitory data within documents, contributing to improved organization and detail.

Transitory data refers to temporary or short-lived information not intended for permanent storage or retention. It is typically used for immediate processing or transmission purposes and is often discarded once its purpose is fulfilled.

Created with the Standard Edition of HelpNDoc: Free EPub producer

Dynareg - Extra document types

Dynareg - Plugins - Extra document types - BUG - Stock

BUG - Disables the Ledger tab of all Stock items- See - Dynareg - Extra documnent types - BUG - Stock items -



Enable any of the following Dynareg plugins will disable the Ledger tab of all Stock items and the option to create new stock items:

Document grid	*Extra document types*	*Document grid id*	*Disable ledger tab*	*Default to output filled document*

		Adjustment type name
	*Stock in + Stock out* *Enable : "Documenten -> Aparte artickel uitgifte" Provides 2 additional document types i.e. Stock in for purchase documents and Stock out for Sales documents with which items can be entered and issued - Documentation : Dynareg - Stock in and Stock out document type -*	STOCK-OUT-001 > Stock out Stock in Stock

+ (Stock item tab)

BOM Production on on Stock in / St

o c k o u t r e p o r t

S I S I n t 0 p a 0 u t 0 t e 0 - m 1 > e S S n t t o o c c k k i o u t



Stock in

Enable : "Documenten -> Verminder herbestel bij doorboeken inkoop"
This plugin specifically adds the "Stock in" document type. Note that the "Stock out" document type, which is added when you enable the previous two plugins, will be removed.

Enable : "Documenten -> Alleen inkoop"

Documentation : Dynareg - Stock in document type -

S I S I n t 0 p a 0 u t 0 t e 0 - m 1 > e S S n t t o o c c k k i o

Stock-Out Stock-in-Create Invoice

Invoice not available

b
l
e
o
n

D
o
c
u
m
e
n
t
s
g
r
i
d

U
p
d
a
t
e
l
e
d
g
e
r
(
c
a
n
n
o
t
p
o

s
t
)

D
e
l
e
t
e
d
o
c
u
m
e
n
t
s
(
c
a
n
n
o
t
d
e
l
e
t
e
)

S
t
o
c
k
t
a
b
-

Disassemble(Stockitemtype)

Assemble(Stocki

t
e
m
t
y
p
e
)

B
O
M
P
r
o
d
u
c
t
i
o
n
o
n
S
t
o
c
k
i
n
/
S
t
o
c
k
o
u
t
r

	*Stock in / Out* *Enable : "Documenten -> Extra voorraad correctiedocument" Cannot locate on shop.* *Documentation : Dynareg - Extra stock of correction document (Stock in / Stock out document type) -*	*STO0001Stock In / Out*	*Adjustment Export*

Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Dynareg - Extra documnent types - BUG - Stock items

Enable any of the following Dynareg plugins will disable the Ledger tab of all Stock items and the option to create new stock items:

Document grid	*Extra document types*	*Doc up*	*Inp ut*	*Def a*

menugrid	menutext	ulayoutfiledocumenttypename

o i
u n
t

S
t
o
c
k
i
n

S
t
o
c
k *+* *(*
S
t
o
c
k
i
t
e
m
t
a
b
)

B
O
M
P
r
o
d
u

c
t
i
o
n
o
n
S
t
o
c
k
i
n
/
S
t
o
c
k
o
u
t
r
e
p
o
r
t

S I S
I n t
0 p a
0 u t
0 t e
0 - m
1 > e
S S n
t t t
o o
c c
k k



Stock in

Enable : "Documenten -> Verminder herbestel bij doorboeken inkoop"
This plugin specifically adds the "Stock in" document type. Note that the "Stock out" document type, which is added when you enable the previous two plugins, will be removed.

Enable : "Documenten -> Alleen inkoop"

Documentation : Dynareg - Stock in document type -

in out

SI0000 Input -> Stock in

Stock in - Creates Invoice

Invoicenotavailableon

Documentsgrid

Upd

atledger(cannotpost)

Deletedocuments(cann

otdeIete)

Stocktab-Disassembleie(Stockitemty

p
e
)

A
s
s
e
m
b
l
e
(
S
t
o
c
k
i
t
e
m
t
y
p
e
)

B
O
M
P
r
o
d
u
c
t
i
o
n
o

Stock in / Out report



Stock in / Out

Enable : "Documenten -> Extra voorraad correctiedocument" Cannot locate on shop.

Documentation : Dynareg - Extra stock of correction document (Stock in / Stock out document type) -

STD0001 Stock In/Out Adjustment

u

t

Dynareg - Plugins - Extra document types - Activation options



Stock item screen after any of these plugins were enabled

Previous stock adjustments - Before any of these plugins is enabled

- Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating these plugins, will be included on the document grid as an extra document type under the Stock out document type. The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.
- These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid . These Stock adjustments made before enable these plugins does not affect the stock item functionality.

Stock item functionality - After any of these plugins is enabled

After these plugins is enabled, the following issues is replicated in the Stock item form:

- Ledger tab is disabled for all Stock items.
- New button - Not available - Cannot create a new Stock item.



- Copy from item - The only way to add a new stock item but with issues:
  - Main form - Stock code can enter a new Stock code and save the copied stock item. After saving most of the fields is not editable on the main form. You cannot change the stock item description, but you can change the Barcode, Stock type and Units.
  - Ledger tab cannot be edited such as selling prices, cost prices, etc.

Created with the Standard Edition of HelpNDoc: Easily create Help documents

Dynareg - Stock in and Stock out document type

Separate item issue (Stock In + Stock Out)

Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

Enable : "Documenten -> Aparte artickel uitgifte"

BUG - Disables the Ledger tab of all Stock items- See - Dynareg - Extra documnent types - BUG - Stock items -



Known issues

Previous stock adjustments - Stock out document type

- Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating this plugin, will be listed on the document grid under the Stock out document type.
- These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid.
- The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.
- Duplicate document number - The first Stock out document created, also starts with "ST00001" which is a duplication of previous stock adjustments before activating Enable this plugin.



Input menu

Input → Stock in menu - launches Stock out can process debtors instead of creditors. On Documents grid document type Stock in launches creditors.

Input → Stock out menu- launches Stock in can process creditors instead of debtors. On Documents grid document type Stock out launches debtors.

Print posted transactions - Cannot print posted transactions for Stock in

- Debtors - Documents tab - "*Show transactions*" context menu. can view and print "*Transactions*" screen "*Batch type report - Posted batches*" report. Only prints the Cost of Sales transactions. When create Stock out Document - Output tax is included in the selected stock item.
- Creditors - Documents tab - "*Show transactions*" context menu. Cannot view and print "Transactions" screen "*Batch type report - Posted batches*" report. Transactions screen is empty and "*No data to print*!" error. When create Stock in Document - Output tax is included in the selected stock item and not Input tax. In Ledger analyser cannot trace and print the transactions for the Stock in document type.

Right-click and select "*Show transactions*" on the context menu. This lists the transactions on a "*Transactions*" screen for the selected document. Note: For the Stock out document type, the quantities will be adjusted, and the transactions for cost of sales will be adjusted in a journal. Additionally, for the Stock in document type, the "*Transactions*" screen may be empty, as it primarily adjusts quantities. For the Stock out document type, the cost of sales transactions, will be listed the "*Transactions*" screen.

Update ledger / Delete documents - Titlebar captions

- Update documents - Stock in - Delete supplier returns
- Update documents - Stock out - Delete orders
- Delete documents - Stock in - Delete supplier returns
- Delete documents - Stock out - Delete orders

Print layout files

Layout files added for Stock in / Stock out document types

To fix this, added two translatable Document layout files from the Stock in / Stock out document types:

Stock in (TRN_906178) This layout file may be selected on the Documents grid or Creditors - Documents tab



Stock out (TRN_906179) This layout file may be selected on the Documents grid or Debtors - Documents

tab



Layout file document names issues

The plugin prints the layout file selected in the "*Layout file point-of-sale*" field within Setup → Documents setup. This setting does not work for the "*Stock in*" or "*Stock out*" document types By default, the "*Stock in*" or "*Stock out*" will print the till slip layout file "*POS Tax invoice*".

In the central search (Search on the Default ribbon), it will print this POS - START-SP100 (TRN_906183). If any other layout file, is selected. the name of the report is not translated, but will display for example TRN_906183 in Setup → Point of-Sale - Printers tab



Changing the layout file in Setup → Documents setup will update the layout file in Setup → Point of-Sale - Printers tab but it still prints Stock in and Stock out using the POS - START-SP100 (TRN_906183)layout file.



NOTE If "*Layout file*" is selected as the option within Documents setup for other document types, the "*Default*" option on Document grid does not work. You need to select the "*Layout file*" or other layout file.

You have the option to choose a different layout file for "*Stock in*" or "*Stock out*" document types.

Layout file - The default "*Layout file*" for all document types, will print the headings in the Types on Tools → Customise language.

Stock out - Adjustment



Stock in - Statement



Separate Item Issue Plugin

Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

Enable : "Aparte artickel uitgifte"

BUG - Disables the Ledger tab of all Stock items- See - Dynareg - Extra documnent types - BUG - Stock items -

"Provides 2 additional document types i.e. Stock in for purchase documents and Stock out for Sales documents with which items can be entered and issued.

This then processes quantities and any costs of sales. With the other documents, only turnover and VAT items are recorded and no more quantities.

"*Dynareg - Separate Item Issue*" plugin enhances osFinancials by providing two additional document types: Stock in for purchase documents and Stock out for sales documents. With these document types, items

can be entered and issued, enabling precise tracking of quantities and associated costs of sales.

Enable the "*Dyna - Separate item issue*" plugin

To activate the "*Dyna - Separate item issue*" plugin follow these steps:

1.

1. Access Plugins: Navigate to Plugins → Tools → DYNADBREG menu.
2. Enable the plugin: Select the "*Aparte artickel uitgifte*" option and click Enable.
3. Reopen Set of Books: Once you've enabled this plugin, reopen your Set of Books. This step is essential for the changes to take effect.

Access to Stock in and Stock out document types

In addition to the standard document types, this plugin adds Stock in and Stock out document types, each serving distinct purposes:

- Stock in is added alongside the existing purchase document types: purchases, supplier returns, and orders. Document numbers for Stock in start with SI00001.
- Stock out is added alongside the existing sales document types: invoices, credit notes, and quotes. Document numbers for Stock out start with ST00001.

Accessing the Additional Document Types: You may access these two additional document types via the following options:

1. Default ribbon: Navigate to Documents and select either the standard document types or the Stock in and Stock out document types. This launches the document entry screen as an integrated part of the document grid.



2. Input menu: Choose from the standard document types or the Stock in and Stock out document types from the Input menu. This launches the document entry screen as a separate screen.



Additionally, the "*Stock in*" and "*Stock out*" document types are available as options on the context menu of the document grid, accessible via Documents → Copy to → Stock in and Documents → Copy to → Stock out.

Layout file setting

The plugin prints the layout file selected in the "*Layout file point-of-sale*" field within Documents setup. By default, the "*Stock in*" or "*Stock out*" will print the till slip layout file "*POSTax invoice*". You have the option to choose a different layout file for "*Stock in*" or "*Stock out*" document types.



On the Documents screen, you can select "*Layout file*". The "*Layout File*" document layout supports all

document type descriptions, whether they are sales documents like invoices, credit notes, and quotes, or purchase documents like purchases, supplier returns, and orders. If documents for the "*Stock in*" or "*Stock out*" document type are printed, the heading will be displayed as "*Adjustment*" document type.

Document grid - Search and Filter options

Previous stock adjustments

Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating this plugin, will be listed on the document grid under the Stock out document type.

These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid.

The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.



Filter and Search options

For the Stock in and Stock out document types, utilize the powerful grid for filtering and searching. Some of the available options include:

- Document status: Filter by Unposted, Posted, or view All documents.
- Groups: Filter for specific document groups.
- Document details: Access all available document details, including references, dates, and more.

Additionally, you can build custom filters tailored to your specific needs.

Stock in

The "*Stock in*" document type resembles the "*Purchase*" document type. To create a new document for the Stock in document type, click New. On the "*Creditor accounts*" screen, select a creditor (supplier/vendor) account and click Open. If no account exists, you may create a new creditor account.



On the Stock in document entry screen, select the stock item. You may enter references in the "*Your reference*" field in the document header. Additionally, you can include remarks and comments:

- Remarks: Beneath each stock item, you can add remarks. These remarks will print in document layout files but are not searchable in the central search.
- Comments: Use the F9: Comment option to enter comments for each item.

The document references entered in the "*Your reference*" field in the document header, along with the comments, are searchable using the central search option (accessible via the Search on the Default ribbon).

Stock out

The "*Stock out*" document type resembles the "*Invoice*" document type. To create a new document for the Stock out document type, click New. On the "*Debtor accounts*" screen, select a debtor (customer/client) account and click Open. If no account exists, you may create a new debtor account.



On the Stock out document entry screen, select the stock item. You may enter references in the "*Your reference*" field in the document header. Additionally, you can include remarks and comments:

- Remarks: Beneath each stock item, you can add remarks. These remarks will print in document layout files but are not searchable in the central search.
- Comments: Use the F9: Comment option to enter comments for each item.

The document references entered in the "*Your reference*" field in the document header, along with the comments, are searchable using the central search option (accessible via the Search on the Default ribbon).

Update to ledger

If the "*Auto-post document on print*" setting on the Documents setup in the Setup menu (accessible via the Setup ribbon) is not activated, or if you have not yet printed the document, you will need to manually post the Stock in and Stock out documents.

To do this, press F3 or select Update Ledger on the Default ribbon. The "*Update Invoices*" screen is displayed:



- Select the Stock out document type and click Update.
- Repeat the process for the Stock in document type if necessary.

View the posted transactions

Once the Stock in and Stock out documents have been posted (updated to the ledger), you may view the transactions in the following options:

Stock items (Default ribbon)

Includes the Stock in and / or Stock out document types if processed for the selected stock item.

Document groups tab

This will include posted as well as unposted documents for the Stock in and Stock out document types.

- Double-click to print the selected document or choose a different layout file.
- Right-click to open the document entry screen in a separate window. Note that both posted and unposted documents cannot be edited.

Transactions tab

This will only include posted documents for the Stock in and Stock out document types.

- Right-click and select "*Open document*" from the context menu. Note that posted documents cannot be

edited.

Debtors (Default Ribbon)

The Stock out document type should be listed since you can only select a debtor account.

Documents tab



- Includes both posted and unposted documents for the Stock out document type.
- Here, you may:
  - Print the document layout file: Double-click to print the selected document or click the Print button. You may select a different layout file.
  - View and Print transactions: Right-click and select "*Show transactions*" on the context menu. This lists the transactions on a "*Transactions*" screen for the selected document. Note: For the Stock out document type, the quantities will be adjusted, and the transactions for cost of sales will be adjusted in a journal. Additionally, for the Stock in document type, the "*Transactions*" screen may be empty, as it primarily adjusts quantities. For the Stock out document type, the cost of sales transactions, will be listed the "*Transactions*" screen.



Clicking the Print button will print a "*Batch type report - Posted batches*". If an unposted batch is selected, the "*Transactions*" screen will be blank.



Stock item tab

- Includes both posted and unposted documents for the Stock out document type.
- The stock out document type numbers will consist of 7 digits of which the first two is prefixed with "ST" .The document type for the Stock out is indicated as "Stock+"

Creditors (Default Ribbon)

The Stock in document type should be listed since you can only select a creditor account.

Documents tab



- Includes both posted and unposted documents for the Stock in document type.
- Here, you may:
  - Print the document layout file: Double-click to print the selected document or click the Print button. You may select a different layout file.
  - View and Print transactions: Right-click and select "*Show transactions*" on the context menu.

This lists the transactions on a "*Transactions*" screen for the selected document. Note: for Stock In document type, the "*Transactions*" screen may be empty, as it primarily adjusts quantities.

Stock item tab

- Includes both posted and unposted documents for the Stock in document type.
- The stock in document type numbers will consist of 7 digits of which the first two is prefixed with "*SI*" .The document type for the Stock in is indicated as "*Stock-*"

Created with the Standard Edition of HelpNDoc: Effortlessly Create Professional Documentation with HelpNDoc's Clean UI

Dynareg - Extra stock of correction document (Stock in / Stock out) document type)

Extra stock of correction document

Dynareg - Extra stock of correction document - Shop - Licence : Once-off -

Extra stock of correction document plugin add the "Stock in / out" as an additional document type.

Enable : "Documenten - Extra stock of correction document"

Documentation : Help documentation - Stock in and Stock out document types

Documentation : Help documentation - Stock in document type

BUG - Disables the Ledger tab of all Stock items- See - Dynareg - Extra documnent types - BUG - Stock items -



Extra voorraad correctiedocument

Een extra document type om voorraad correcties of eigen verbruik te verklaren.

Translation

Extra stock of correction document

An additional document type to declare stock corrections or self-consumption.

Creates a Stock in / Stock out document type

Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

Enable : "Aparte artickel uitgifte"

Document grid - Search and Filter options

Previous stock adjustments

Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating this plugin, will be listed on the document grid under the Stock In / Out document type.

These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid.

The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.



Filter and Search options

For the Stock in and Stock out document types, utilize the powerful grid for filtering and searching. Some of the available options include:

- Document status: Filter by Unposted, Posted, or view All documents.
- Groups: Filter for specific document groups.
- Document details: Access all available document details, including references, dates, and more.

Additionally, you can build custom filters tailored to your specific needs.

Stock In / Out document type

The "*Stock In / Out*" document type resembles the "*Invoice*" document type. To create a new document for the Stock In / Out document type, click New. On the "*Debtor accounts*" screen, select a debtor (customer/client) account and click Open. If no account exists, you may create a new debtor account.



NOTE : Selling price - No selling prices 1 / 2 / 3. Shows cost prices for Purchases.

On the Stock In / Out document entry screen, select the stock item. You may enter references in the "*Your reference*" field in the document header. Additionally, you can include remarks and comments:

- Remarks: Beneath each stock item, you can add remarks. These remarks will print in document layout files but are not searchable in the central search.
- Comments: Use the F9: Comment option to enter comments for each item.

The document references entered in the "*Your reference*" field in the document header, along with the comments, are searchable using the central search option (accessible via the Search on the Default ribbon).

Input → Stock in menu (Stock in / Out document type)

Input → Stock in menu launches a stand-alone screen.

Document entry loose standing grid

NOTE :

- The existing documents created for the Stock In / Out document type using the Input → Stock in menu, within the Stock items grid is not listed.
- New document - Select the "Debtor accounts"
- Document number - Invoice document number is created for example "IN000025" (an 8 digit document number) and not for example "ST00001" (a 7 digit document number) as is created for the Stock In / Out document type within the Stock items grid.



Document entry - New document



NOTE :

- Stock In document can be printed
- Stock In document entry lines - cannot select stock item sometimes a double click works but +Open fast add easy select and add an item.
- Selling price - No selling prices 1 / 2 / 3.
- Stock item - Unposted document number available - The Stock In / Out document created from the Input → Stock in menu cannot be posted, but is available as an unposted document in the Document groups tab of the Stock item. You may:
    - Print the document - Double-click to print the document.
    - Open document - Right-click to open the document. NOTE - The unposted document entry screen cannot be edited from this option.
- Debtors - Unposted document number available -
    - Stock items tab NOTE : Refers to Assemble in the "*Document type*" column. Should refer to Stock In / Out as the document type.



NOTE : This also reflect as the BOM (Production) stock item type in Reports → Stock → Stock In / Out - "*Documents*" report:



This report includes both posted and unposted documents processed with the Stock In / Stock out document type. Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating this plugin, will be listed on the document grid under the Stock In / Out document type. These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid. The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.

NOTE : The posted StockIn / Out Stock item type reflects the "Stock in" stock item type in Reports → Stock → Stock In / Out - "*Stock In / Out*" report:



- Documents tab

- Document number not available - The Stock In / Out document created from the Input → Stock in menu can not be found on the following:
  - Stock item grid - all document types, including the Stock In / Out document type.
  - Input → Update documents (F3) - Title bar caption refers to "*Delete orders*" Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating this plugin, will be listed on the document grid under the Stock In / Out document type. These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid. The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.



  - Edit → Delete documents - Title bar caption refers to "*Delete orders*". Any stock adjustments, including Auto correction, Surpluses, and Shortages, processed before activating this plugin, will be listed on the document grid under the Stock In / Out document type. These adjustments would have been made using the Input → Adjust stock menu or by manually changing stock quantities on the stock item grid. The document numbers for these stock adjustments consist of 7 digits and include '*ST*' as the prefix.



Update to ledger

If the "*Auto-post document on print*" setting on the Documents setup in the Setup menu (accessible via the Setup ribbon) is not activated, or if you have not yet printed the document, you will need to manually post the Stock In / Out documents.

To do this, press F3 or select Update Ledger on the Default ribbon. The "*Update Invoices*" screen is displayed:



Select the Stock In / Out document type and click Update.

View the posted transactions

Once the Stock in and Stock out documents have been posted (updated to the ledger), you may view the transactions in the following options:

Stock items (Default ribbon)

Includes the Stock in and / or Stock out document types if processed for the selected stock item.

Document groups tab

This will include posted as well as unposted documents for the Stock in and Stock out document types.

- Double-click to print the selected document or choose a different layout file.
- Right-click to open the document entry screen in a separate window. Note that both posted and unposted documents cannot be edited.

Transactions tab

This will only include posted documents for the Stock in and Stock out document types.

- Right-click and select "*Open document*" from the context menu. Note that posted documents cannot be edited.

Debtors (Default Ribbon)

The Stock out document type should be listed since you can only select a debtor account.

Documents tab



- Includes both posted and unposted documents for the Stock out document type.
- Here, you may:
  - Print the document layout file: Double-click to print the selected document or click the Print button. You may select a different layout file.
  - View and Print transactions: Right-click and select "*Show transactions*" on the context menu. This lists the transactions on a "*Transactions*" screen for the selected document. Note: For the Stock out document type, the quantities will be adjusted, and the transactions for cost of sales will be adjusted in a journal. Additionally, for the Stock in document type, the "*Transactions*" screen may be empty, as it primarily adjusts quantities. For the Stock out document type, the cost of sales transactions, will be listed the "*Transactions*" screen.



Clicking the Print button will print a "*Batch type report - Posted batches*". If an unposted batch is selected, the "*Transactions*" screen will be blank.



Stock item tab

- Includes both posted and unposted documents for the Stock out document type.
- The stock out document type numbers will consist of 7 digits of which the first two is prefixed with "ST" .The document type for the Stock out is indicated as "Stock+"

Creditors (Default Ribbon)

The Stock in document type should be listed since you can only select a creditor account.

Documents tab



- Includes both posted and unposted documents for the Stock in document type.
- Here, you may:
  - Print the document layout file: Double-click to print the selected document or click the Print button. You may select a different layout file.
  - View and Print transactions: Right-click and select "*Show transactions*" on the context menu.

This lists the transactions on a "*Transactions*" screen for the selected document. Note: for Stock In document type, the "*Transactions*" screen may be empty, as it primarily adjusts quantities.

Stock item tab

- Includes both posted and unposted documents for the Stock in document type.
- The stock in document type numbers will consist of 7 digits of which the first two is prefixed with "*SI*" .The document type for the Stock in is indicated as "*Stock-*"

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Dynareg - Stock in document type

Dynareg - Separate Item Issue Plugin

Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

Enable : "Documenten - Aparte artickel uitgifte"

Enable : "Documenten -> Alleen inkoop"

Enable : "Documenten -> Verminder herbestel by doorboeken inkoop"

BUG - Disables the Ledger tab of all Stock items- See - Dynareg - Extra documnent types - BUG - Stock items -



Known issues

Input menu

Input menu - Stock out - launches Stock in can process creditors. On Documents grid document type Stock in launches creditors.



Print posted transactions - Cannot print posted transactions for Stock in

Creditors - Documents tab - "*Show transactions*" context menu. Cannot view and print "Transactions" screen "*Batch type report - Posted batches*" report. Transactions screen is empty and "*No data to print*!" error. When create Stock in Document - Output tax is included in the selected stock item and not Input tax. In Ledger analyser cannot trace and print the transactions for the Stock in document type.

"Right-click and select "*Show transactions*" on the context menu. This lists the transactions on a "*Transactions*" screen for the selected document. Note: For the Stock out document type, the quantities will be adjusted, and the transactions for cost of sales will be adjusted in a journal. Additionally, for the Stock in document type, the "*Transactions*" screen may be empty, as it primarily adjusts quantities. For the Stock out document type, the cost of sales transactions, will be listed the "*Transactions*" screen."

Update ledger / Delete documents - Titlebar captions

- Update documents - Stock in - Delete supplier returns
- Delete documents - Stock in - Delete supplier returns

Print layout files

The plugin prints the layout file selected in the "*Layout file point-of-sale*" field within Documents setup. This setting does not work for the "*Stock in*" document type By default, the "*Stock in*" will print the till slip layout file "*POS Tax invoice*".



NOTE If "*Layout file*" is selected as the option within Documents setup for other document types, the "*Default*" option on Document grid does not work. You need to select the "*Layout file*" or other layout file.

You have the option to choose a different layout file for "*Stock in*" document types.

Layout file - The default "*Layout file*" for all document types, will print the headings in the Types on Tools → Customise language.

Stock in - Statement



Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

Enable : "Documenten - Aparte artickel uitgifte"

Enable : "Documenten -> Alleen inkoop"

Enable : "Documenten -> Verminder herbestel by doorboeken inkoop"

Activation of the "*Dynareg Only purchase via new type*" plugin

To activate the "*Dynareg Only purchase via new type*" plugin and enable the "*Stock in*" as an additional document type, you'll need to follow these steps:

1. Enable the "*Aparte artickel uitgifte*" plugin. This plugin adds the "*Stock in*" and "*Stock out*" document types.
2. Enable the "*Alleen inkoop"* plugin. This plugin also adds the "*Stock in*" and "*Stock out*" document types.
3. Enable the "*Verminder herbestel by doorboeken inkoop*" plugin. This plugin specifically adds the "*Stock*

in" document type. Note that the "Stock out" document type, which is added when you enable the previous two plugins, will be removed.

After enabling each of these plugins, be sure to reopen your Set of Books. This step is crucial to ensure that the changes take effect properly.



Dynareg - Separate Item Issue Plugin - Shop - Licence : Once-off -

Enable : "Documenten -> Aparte artickel uitgifte"

Enable : "Documenten -> Alleen inkoop"

Enable : "Documenten -> Verminder herbestel by doorboeken inkoop"

Reduce reorders when rebooking purchases

When transferring a purchase, reduce the reorder. (2nd hand store)

Access to Stock in document type

In addition to the standard document types, this plugin adds Stock in document type, serving distinct purpose.

The Stock in is added alongside the existing purchase document types: purchases, supplier returns, and orders. Document numbers for Stock in start with "*SI00001*".

Accessing the Stock in additional document type:

You may access the Stock in additional document types via the following options:

1. Default ribbon: Navigate to Documents and select either the standard document types or the Stock in document type. This launches the document entry screen as an integrated part of the document grid.



2. Input menu: Choose from the standard document types or the Stock in document type from the Input menu. This launches the document entry screen as a separate screen.



Additionally, the "*Stock in*" document type is available as options on the context menu of the document grid, accessible via Documents → Copy to → Stock in.

Document grid - Search and Filter options

Filter and Search options

For the Stock in document type, utilize the powerful grid for filtering and searching. Some of the available options include:

- Document status: Filter by Unposted, Posted, or view All documents.
- Groups: Filter for specific document groups.

- Document details: Access all available document details, including references, dates, and more.

Additionally, you can build custom filters tailored to your specific needs.

Stock in

The "*Stock in*" document type resembles the "*Purchase*" document type. To create a new document for the Stock in document type, click New. On the "*Creditor accounts*" screen, select a creditor (supplier/vendor) account and click Open. If no account exists, you may create a new creditor account.



On the Stock in document entry screen, select the stock item. You may enter references in the "*Your reference*" field in the document header. Additionally, you can include remarks and comments:

- Remarks: Beneath each stock item, you can add remarks. These remarks will print in document layout files but are not searchable in the central search.
- Comments: Use the F9: Comment option to enter comments for each item.

The document references entered in the "*Your reference*" field in the document header, along with the comments, are searchable using the central search option (accessible via the Search on the Default ribbon).

Update to ledger

If the "*Auto-post document on print*" setting on the Documents setup in the Setup menu (accessible via the

Setup ribbon) is not activated, or if you have not yet printed the document, you will need to manually post the Stock in documents.

To do this, press F3 or select Update Ledger on the Default ribbon. The "*Update Invoices*" screen is displayed:



- Select the Stock in document type and click Update.

View the posted transactions

Once the Stock in documents have been posted (updated to the ledger), you may view the transactions in the following options:

Stock items (Default ribbon)

Includes the Stock in document types if processed for the selected stock item.

Document groups tab

This tab will include posted as well as unposted documents for the Stock in document type.

- Double-click to print the selected document or choose a different layout file.
- Right-click to open the document entry screen in a separate window. Note that both posted and unposted documents cannot be edited.

Transactions tab

This tab will only include posted documents for the Stock in document types.

- Right-click and select "*Open document*" from the context menu. Note that posted documents cannot be edited.

Creditors (Default Ribbon)

The Stock in document type should be listed since you can only select a creditor account.

Documents tab



- Includes both posted and unposted documents for the Stock In document type.
- Here, you may:
  - Print the document layout file: Double-click to print the selected document or click the Print button. You may select a different layout file.
  - View and Print transactions: Right-click and select "*Show transactions*" on the context menu. This lists the transactions on a "*Transactions*" screen for the selected document. Note: for Stock In document type, the "*Transactions*" screen may be empty, as it primarily adjusts quantities.

Stock item tab

- Includes both posted and unposted documents for the Stock in document type type.
- The stock in document type numbers will consist of 7 digits of which the first two is prefixed with "*SI*" .The document type for the Stock out is indicated as "*Stock-*"

Input → Stock out menu

Input → Stock out menu should read Stock in - See document type on the Documents grid.

The Input → Stock out menu launches the Document entry in a separate window. New Invoice will create an Invoice "X IN000025, etc. instead of a Stock in document type with document number "SI00001"



The invoice on document entry



NOTE : This document "Invoice" only listed from the Input → Stock out menu and is not available on:

- Documents grid (both Invoices and Stock in document types)
- Update ledger (cannot post)
- Delete documents (cannot delete)
- Print uses the *"Layout file point-of-sale" field setting* within Setup → Documents setup.

Stock type

Stock tab - Disassemble (Stock item type)



Disassemble (Stock item type)

BOM Production on Stock in / Stock out report



Created with the Standard Edition of HelpNDoc: Quickly and Easily Convert Your Word Document to an ePub or Kindle eBook

Dynareg - Numbers based on multiplication factor

Dynareg - Numbers based on multiplication factor plugin - Shop - Licence : Once-off -

Enable : "Aantalen multiplieer"

Aantallen op basis van vermenigvuldigings factor

Vermenigvuldigd het artikel totaal bedrag opbasis van het aantal en een vrije vermenigvuldigings factor.

Quantities based on multiplication factor plugin

This "*Dynareg - Numbers based on multiplication factor*" plugin is available in sales documents (invoices, credit notes and quotes. as well as purchase documents (purchase, supplier return and orders).

Multiplies the item total amount based on the quantity and a specified free multiplication factor.

When the "*Dynareg - Quantities based on multiplication factor*" plugin, will when enabled, add an extra column "*X*" in the document lines,

The default value in the multiplication factor "X" column is always 1. This means that the quantity entered in the quantity ship column for an item, multiplied by the Unit price (exclusive or inclusive of Tax (VAT/GST/Sales tax)).

- Increase multiplication factor - This will increase the Total exclusive amount price by the number specified in the X column.
- Decrease multiplication factor - If you enter a number as a decimal, e,g, 0,5, it will reduce the Total exclusive amount price by the number specified price by the number specified in the X column.

The "*Dynareg - Numbers based on multiplication factor*" plugin provides functionality to automatically adjust the total amount of items in sales and purchase documents based on a multiplication factor specified in an extra column called "*X*".

Key features:

1.

- Availability: The plugin is available in various types of sales documents (invoices, credit notes, and quotes) as well as purchase documents (purchase, supplier return, and orders).
- Multiplication Factor: It multiplies the item total amount based on the quantity and a specified multiplication factor. The default value for the multiplication factor column "X" is always 1.

- Extra Column: When enabled, the plugin adds an extra column "X" in the document lines where users can input the multiplication factor.

- Adjustment: Users can increase or decrease the multiplication factor, which affects the total exclusive amount price accordingly. Increasing the multiplication factor increases the total exclusive amount price by the specified number in the "*X*" column, while decreasing it reduces the total exclusive amount price by the specified number if a decimal is used.

- Printing Layout Files: The layout files for sales and purchase documents is designed dynamically to incorporate the multiplication factor. This involves ensuring that the total amounts displayed on the printed documents are calculated based on the quantity, unit price, and multiplication factor entered in the document entry screens.

This functionality seems useful for scenarios where users need to apply a consistent multiplier to item prices in sales and purchase documents. It provides flexibility by allowing users to adjust the multiplier as needed, potentially saving time and reducing errors in manual calculations.

When you print layout files of sales and purchase documents any adjustments made using the multiplication factor in the document entry screens will be reflected in printed layout files. Additionally, the tax (VAT/GST/Sales tax) calculations would also be updated accordingly based on the modified total amounts.



Let's visualize this scenario with an example using a screenshot of an invoice:

Invoice Example:

1.

1. Drill Press:
    - Description: Drill press equipment.
    - Unit Price (Exclusive of Tax): $1000 per unit.
    - Quantity Shipped: 1 unit.
    - Multiplication Factor (X): 1 (default).
    - Amount (Exclusive of Tax): $1000 (1 unit * $1000/unit).

    In this case, the multiplication factor is 1, which means the total amount remains the same as the unit price multiplied by the quantity shipped. The total amount is $1000 exclusive of tax.

2. Compressor:
    - Description: Air compressor.
    - Unit Price (Exclusive of Tax): $1500 per unit.
    - Quantity Shipped: 1 unit.
    - Multiplication Factor (X): 2.
    - Amount (Exclusive of Tax): $3000 (1 unit * $1500/unit * 2).

    Here, the multiplication factor is set to 2. As a result, the total amount is adjusted to $3000, which is double the original amount. This reflects the applied multiplication factor, resulting in a higher total amount.

Summary:

- The invoice displays two items: Drill Press and Compressor.
- For Drill Press, the default multiplication factor (1) doesn't alter the total amount.
- For Compressor, the multiplication factor (2) doubles the total amount.

This example illustrates how the multiplication factor specified in the "X" column affects the total amount for each item on the invoice. It provides a clear demonstration of how adjustments made in the document entry screens are accurately reflected in the printed invoice.

Example printed invoice:



Created with the Standard Edition of HelpNDoc: Easily create EPub books

Dynareg - Numbers based on division factor

Dynareg - Numbers based on divide factor plugin - Shop - Licence : Once-off -

Enable : "Aantalen multiplieer" - Help documentation : Dynareg - Numbers based on multiplication factor plugin

Enable : "Gebruik veld als delen door" - Help documentation : Dynareg - Numbers based on divide factor plugin

Multiplies the item total amount based on the quantity and divides a free factor by factor.

The "*Dynareg - Nunbers based on divide factor*" plugin is based on the "*Dynareg - Numbers based on multiplication factor*" plugin provides functionality to automatically adjust the total amount of items in sales and purchase documents based on a division factor specified in an extra column called "*X*".

Key features:

1.

- Availability: The plugin is available in various types of sales documents (invoices, credit notes, and quotes) as well as purchase documents (purchase, supplier return, and orders).
- Division Factor: It divides the item total amount based on the quantity and a specified division factor. The default value for the division factor column "X" is always 1.
- Extra Column: When enabled, the plugin adds an extra column "*X*" in the document lines where users can input the division factor.
- Adjustment: Users can decrease the division factor, which affects the total exclusive amount price accordingly. Increasing the division factor increases the total exclusive amount price by the specified number in the "*X*" column, while decreasing it reduces the total exclusive amount price by the specified number if a decimal is used.
- Printing Layout Files: The layout files for sales and purchase documents are dynamically designed to incorporate the division factor. This ensures that the total amounts displayed on the printed documents are calculated based on the quantity, unit price, and division factor entered in the document entry screens.

This functionality is useful for scenarios where users need to apply a consistent divider to item prices in sales and purchase documents. It provides flexibility by allowing users to adjust the divider as needed, potentially saving time and reducing errors in manual calculations.

This example illustrates how the division factor specified in the "*X*" column affects the total amount for each item on the invoice. It provides a clear demonstration of how adjustments made in the document entry screens are accurately reflected in the printed invoice.

When you print layout files of sales and purchase documents any adjustments made using the divider factor in the document entry screens will be reflected in printed layout files. Additionally, the tax (VAT/GST/Sales tax) calculations would also be updated accordingly based on the modified total amounts.



Let's visualize this scenario with an example using a screenshot of an invoice:

Invoice Example:

1.

1. Drill Press:
    - Description: Drill press equipment.
    - Unit Price (Exclusive of Tax): $1000 per unit.
    - Quantity Shipped: 1 unit.
    - Multiplication Factor (X): 1 (default).
    - Amount (Exclusive of Tax): $1000 (1 unit / $1000/unit).

    In this case, the multiplication factor is 1, which means the total amount remains the same as the unit price multiplied by the quantity shipped. The total amount is $1000 exclusive of tax.

2. Compressor:
    - Description: Air compressor.
    - Unit Price (Exclusive of Tax): $1500 per unit.
    - Quantity Shipped: 1 unit.
    - Division Factor (X): 2.
    - Amount (Exclusive of Tax): $750 (1 unit / $1500/unit / 2).

Here, the division factor is set to 2. As a result, the total amount is adjusted to $750, which is halves the original amount. This reflects the applied division factor, resulting in a reduced total amount.

Summary:

- The invoice displays two items: Drill Press and Compressor.
- For Drill Press, the default division factor (1) doesn't alter the total amount.
- For Compressor, the division factor (2) halves the total amount.

This example illustrates how the division factor specified in the "X" column affects the total amount for each item on the invoice. It provides a clear demonstration of how adjustments made in the document entry screens are accurately reflected in the printed invoice.

Example printed invoice:



Created with the Standard Edition of HelpNDoc: Produce Kindle eBooks easily

Dynareg - Limit by Creditor with selection list plugin

Dynareg Limit by Creditor with selection list plugin - Shop - Licence : Once-off -

Enable : "Voorraad - Limiteer crediteur met keuze"

The "*Dynareg Limit by Creditor with selection list*" plugin for osFinancials5/TurboCASH5 offer an enhancement to the stock lookup screen by introducing an additional field for selecting a creditor (supplier) account.

When processing purchase documents (purchases, supplier returns and orders) and you select a stock item or product to include in a document, the stock lookup will, by default, list all of your stock items or products.



If you have linked stock items to supplier code, you may select the creditor account to list only those stock items linked to the supplier.



This feature can be particularly beneficial for businesses that deal with multiple suppliers and want to track their stock items based on the supplier from whom they were purchased.

By adding this extra field, users can easily filter and view stock items based on their respective suppliers, providing a more organised and efficient way to manage inventory. This capability can be especially useful for businesses that need to monitor stock levels, reorder products, or analyse purchasing patterns on a supplier-by-supplier basis.

Overall, the plugin seems is a practical addition to osFinancials5/TurboCASH5, enhancing its functionality and usability for businesses that rely on managing stock items from multiple creditors or suppliers.

Created with the Standard Edition of HelpNDoc: Create iPhone web-based documentation

Multi-language accounts

Multi-language Set of Books plugin

Multi-language Set of Books plugin - Manual - Shop - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

The new multi-language ledgers, groups, types and batches is probably best feature implemented in osFinancials5/TurboCASH5.

This makes it possible for an international company to work in different languages on the same set of books.

This helps to show local investors in their language the balances and turnover of the company.

The multi-language feature allows different users to use the same set of books in the user language interface. The translation of ledger accounts need to be purchased from the shop.

By default, each Set of Books will run in the language associated with the Set of Books when opening a Set of Books. You may, if necessary (i.e. incorrect language is selected) or when you need to work in a different language, use Start → Switch language to change the language.

Any language may be customised / edited for your specific requirements on the Setup ribbon, select Tools → Customise language.

In addition to this, you may activate the Multi-Language feature (using any of the available languages in the Start → Switch language) in a Set of Books to:

· Create a Multi-Language User Interface. This makes it possible for a multi-lingual company to work in

different languages on the same set of books.

- Create a Multi-Language Accounts (Chart of accounts) - This helps to show local investors in their language the balances and turnover of the company.

This makes it possible for an international company to work in different languages on the same set of books.

This helps to show local investors in their language the balances and turnover of the company.

The multi-language feature allows different users to use the same set of books in the user language interface. The translation of ledger accounts need to be purchased from the shop.

By default, each Set of Books will run in the selected language when you Open a Set of Books.. You may, if necessary (i.e. incorrect language is selected) or when you need to work in a different language, use Start → Switch language to change the language.

System Language will list all the available languages in the Start → Switch Language menu.

Any language may be customised / edited for your specific requirements on the Setup → Tools → Customise Language menu.

The available languages is stored in the ... \ bin \ languages folder of your osFinancials5/TurboCASH5 installation directory. The default language is selected "System lang" field on the Standard tab of Setup → Access control . This is the language in which osFinacials5 will open the Set of Books.

Any language may be customised / edited for your specific requirements on Setup → Tools → Customise language.

In addition to this, you may activate the Multi-language feature (using any of the available languages in Start → Switch language) in a Set of Books to:

- Create a Multi-Language User Interface. This makes it possible for a multi-lingual company to work in different languages on the same set of books.
- Create a Multi-Language Accounts (Chart of Accounts) - This helps to show local investors in their language the balances and turnover of the company.

Multi-language setup

Add Multi-language groups

Add Multi-language users

Translate Multi-language groups

Translate Multi-language types

Translate Multi-language batch types

Translate Multi-language stock descriptions

Translate Multi-language chart of accounts

Once the Multi-language set of Books is configured and translated, the osFinancials user interface, reports, will be displayed in the system language and the Language set for the user.

Financial reports

The following financial statements may be printed and exported in the language set for a user using the Multi-language feature

1. *Trial balance* – *(Example of the Trial balance printed in 2 languages).*
2. *Income statement* -
3. *Balance sheet* –
4. *Standard column balances* –
5. *Budget vs actual* –
6. *This year vs last year* –

Print layout files in other languages

Languages may also be set for debtors and/or creditors to print layout files in their preferred language. Translatable document layout files, may be selected.

Print documents in debtor (customer / client) language

Print documents in creditor (supplier / vendor) language

Created with the Standard Edition of HelpNDoc: Transform Your Documentation Process with HelpNDoc's Project Analyzer

The Multi-Language Accounts Setup enables international companies to operate in different languages within a single set of books, facilitating communication with local investors and stakeholders. This feature allows users to customize the language interface and translate ledger accounts. Users can easily switch between languages or customize them according to their specific needs. Additionally, the plugin supports multi-language user interfaces and enables the presentation of financial data in local languages, enhancing accessibility and comprehension for diverse audiences.

===

The multi-language ledgers, groups, types and journals (batches) makes it possible for an international company to work in different languages on the same set of books.

This helps to show local investors in their language the balances and turnover of the company.

The multi-language feature allows different users to use the same set of books in the user language interface. The translation of ledger accounts need to be purchased from the shop.

By default, each Set of Books will run in the selected language when launching osFinancials for the first time (new installation). You may, if necessary (i.e. incorrect language is selected) or when you need to work in a different language, use Start → Switch language to change the language.

Any language may be customised / edited for your specific requirements on Setup → Tools → Customise language.

In addition to this, you may activate the Multi-Language feature (using any of the available languages in Start → Switch language) in a Set of Books to:

- Create a Multi-Language User Interface. This makes it possible for a multi-lingual company to work in different languages on the same set of books.
- Create a Multi-Language Accounts (Chart of Accounts) - This helps to show local investors in their language the balances and turnover of the company.

Created with the Standard Edition of HelpNDoc: Free iPhone documentation generator

Add Multi-language users

By adding users and selecting different system language, and User language for each user, you may login to different languages.

The MULTI-LANG-DEMO Books is included in the ...\Bin\Tutorials\ folder. To use this login with e (Username and Password) for English and a (Username and Password) for Afrikaans.

To add Multi-language users:

1. Go to Setup → Access control menu.
2. Click on the Add button and rename the User.
3. Enter a Password for the User.
4. Click on the Others tab.



5. Select the System Language.

> *System Language will list all the available languages in the Start → Switch Language menu.*
>
> *Any language may be customised / edited for your specific requirements on the Setup → Tools → Customise Language menu.*
>
> *The available languages is stored in the ... \ bin \ languages folder of your osFinancials5/TurboCASH5 installation directory. The default language is selected "System lang" field. This is the language in which osFinacials5 will open the Set of Books.*

6. Select the User Language.

> *Language will list all languages created / added in Setup → Groups - Languages tab.*

7. Click on the Apply button.
8. Click on the Add button to add the next User and rename the User.
9. Enter a Password for the User.
10. Click on the Others tab.



11. Select the System Language for the user interface. The language set in the "*System lang*" field, will be displayed as the osFinancials in interface. In this example, the osFinancials user interface will be displayed in Afrikaans if User "a" opens the Set of Books.

12. Select the User Language.

13. Click on the Apply button.

14. Click on the Close button.

Access control - log report - It will list when the users logged in and out, on which device, etc.

Important functions executed from the Tools → Global processes menu (Setup ribbon), will also be listed to display the date and type as well as which user and on which computer these important actions were performed. The Type of actions is as follows:

1. *OPEN YEAR - Open new year (Do year end).*
2. *REVBATC - Reverse posted batch - Reverse batch! and the Batch ID.*
3. *REVDOC - Reverse posted document - Reverse doc! and the Batch ID.*

Created with the Standard Edition of HelpNDoc: Easily create EPub books

Add Multi-language groups

By creating / adding languages, languages may be translated on various screens.

To add / activate Multi-language feature:

1. Go to Setup → Groups.

2. Click on the Languages tab.



3. Click on the REPORTING GROUP ROOT and click on the New button.

4. Enter the Name and Description for the Language (e.g. English, Afrikaans, etc.).

5. Repeat the process to add all required languages.

6. Select the Language and right-click and select the Languages on the context menu.



7. Enter the Name and Description for each language.



8. Click on the OK button.

9. Repeat the process for all Languages.

10. Click on the OK button of the Groups screen.

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Translate Multi-language groups

The names or descriptions for Groups, as entered / edited in the Setup → Groups menu for all the Groups tabs, are by default displayed on screens, lookups, documents, reports, etc.

To use multi-language Groups, Language Groups need to be created / added in Setup → Groups - Languages tab.

The following groups need to be translated, where necessary:

- Account group 1
- Account group 2
- Debtor group 1
- Debtor group 2
- Creditor group 1

- Creditor group 2
- Stock group 1
- Stock group 2
- Document group 1
- Document group 2
- Payment types
- Salesperson
- Projects
- Cost centre 1
- Cost centre 2

To translate groups:

1. Go to Setup → Groups menu.
2. Click on the Account Group 1 tab.



3. Select a Group (e.g. Income, etc.) on the list and right-click to select the Languages on the context menu.
4. Enter the Name and Description for the Account group 1 item.
5. Click on the OK button.
6. Repeat the process to add all required items on Account group 1.
7. Repeat the process for all other Groups (e.g. Account group 2, etc.) where required.
8. Click on the OK button to save your changes and to close the "*Groups*" screen.

After translation

After translations added, the group names will be displayed in the Language set for the logged in user.

Logged in as English user



To print the groups, click on the Print button.



Logged in as Afrikaans user



The group items will be listed in the default language (as in this example, English).

To print a list of the groups, the groups, click on the Print button. The translated groups will be listed.



Created with the Standard Edition of HelpNDoc: Easily create HTML Help documents

Translate Multi-language types

The names or descriptions for Types, as entered / edited in the Tools → Customise language - Types tab (Setup ribbon), is by default displayed on screens, lookups, documents, reports, etc.

To use Multi-language Types, Language Groups need to be created / added in Setup → Groups - Languages tab.

1. Document types - Documents - Default ribbon).
    a) Invoice
    b) Credit note
    c) Quotes
    d) Purchase
    e) Supplier return
    f) Order

If you need to print the Universal Documentlayout files (One (1) Layout file for all document types), it is recommended that these Document type be edited and/or translated to the singular.

For example if you print an Invoice, it should display Invoice and not Invoices on the printed layout file.

2. Account types
    a) General ledger
    b) Debtor
    c) Creditor
    d) Bank
    e) Tax
3. Group types
    a) Account group 1
    b) Account group 2
    c) Debtor group 1
    d) Debtor group 2
    e) Creditor group 1
    f) Creditor group 2
    g) Stock group 1

h) Stock group 2

i) Document group 1

j) Document group 2

k) Payment types

l) Salesperson group

m) Status group (Used for Projects)

n) Cost group 1 (Used for Cost centres)

o) Cost Group 2 (Used for Cost Centres)

p) Languages

4. Paper types

a) Preprinted

b) Plain A4

c) Service

d) Plain Eyeline

e) Forty

f) Till Slip

5. Other / Miscellaneous

a) This Year

b) Last Year

c) Stock item

d) Comment

e) Serial number

f) Financial entry

6. User reports

Optional - The following items in the "Types" is not applicable to osFinancials5/TurboCASH5, and do not need to be translated:

a) *Account*

b) *Blank*

c) *Column Line 1*

d) *Group1*

e) *Group1 Detail*

f) *Group2*

g) *Group2 Detail*

h) *Single Line*

i) *Text*

j) *Budget*

k) *Formula*

7. Colours / Theme Types

It is not necessary to translate the colours, (i.e. Classic, Pastel, Keywest, NewSA and Windows Default). These are not used in osFinancials5/TurboCASH5.

To add translations to types:

1. On the Setup ribbon, select Tools → Customise language.
2. Click on the Types tab.



3. Select the Language and enter the name and description for each language.
4. Repeat the process for all Types.

5. Click on the Rest tab.



6. For the "*Description of Zero account*", select the Language and enter the name (description) for each language.

7. For the "*Groups empty account*", select the Language and enter the name (description) for each language.

8. Repeat the process for all Types.

9. Click on the Close button.

After translation

After translations added, the document types will be displayed in the Language set for the logged in user.

Logged in as English user



Logged in as Afrikaans user



Created with the Standard Edition of HelpNDoc: Easily convert your WinHelp HLP help files to CHM with HelpNDoc's step-by-step guide

Translate Multi-language batch types

The Batch type names or descriptions, as entered in the Setup → Batch Types menu, are by default displayed on the following options: launched from the Default ribbon:

- Batch Entry menu.
- Edit → Repeating transactions.

It also displays on various reports, lookup and parameter screens.

To use multi-language Batch types, Language groups need to be created / added in Setup → Groups - Languages tab.

To add translations to batch types:

1. On the Setup ribbon, select Setup → Batch types.
2. Select the Batch type.



3. Click on the translations button.



4. Select the Language and enter the name or description for each language.
5. Click on the save icon to save the record.
6. Click on the Close button (on the translations screen).
7. Repeat the process for all Batch types.
8. When the process is completed, click on the Close button on the "*Batch type*" screen.

Selecting batches

After translations added, the batch names will be displayed in the Language set for the logged in user.

Logged in as English user



Logged in as Afrikaans user



Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Help Documentation with a Help Authoring Tool

Translate Multi-language chart of accounts

The names or descriptions for Groups, as entered / edited in Setup → Groups for Account Group 1 / 2 tabs, are by default displayed on screens, lookups, documents, reports, etc.

To use multi-language Chart of accounts, Language groups need to be created / added in Setup → Groups - Languages tab.

Once these Language groups is created, the Account group 1 (and / or Account group 2) needs to be translated.

Translate Chart of accounts

To translate the Chart of accounts into Multi-languages:

1. On the Setup ribbon, select Setup → Accounts.
2. Select an account (e.g. Sales, etc.) on the list and click on the Translations tab.



3. Enter the description (account name) of the account in the other language (e.g. Afrikaans).

> *If you select the next account, the changes to translated language(s) will not be saved.*
>
> *To activate the Save button, click on any field, e.g, "Description" and add a space and remove the space.*

4. Click on the Save button.
5. Repeat the process to translate all account descriptions.
6. Click on the Close button (on the titlebar).

> *Once the translations of the multi-language Chart of accounts and Account groups is finished you may print the Chart of accounts in the user to which a different language is assigned.*
>
> *See sample of the Chart of accounts printed in English and in Afrikaans for the same Set of Books.*

Created with the Standard Edition of HelpNDoc: Make your documentation accessible on any device with HelpNDoc

Translate Multi-language stock descriptions

The Stock Item descriptions, as entered in the Description field of the Edit Stock Items screen, are by default displayed on document layout files.

To use multi-language Stock Descriptions, Language Groups need to be created / added in Setup → Groups - Languages tab.

The translated stock item descriptions should print on layout files.

To Add Translations to Stock Items:

1. On the Default ribbon, select Stock items.
2. Select the Stock item.
3. Click on the Edit button (or double-click on the stock item).
4. Click on the Languages tab.



5. Select the Language and enter the name (description) for each language.
6. Click on the Save button.
7. Repeat the process for all stock items.

If you have OpenOffice installed on your system, you may double-click in the Description field of any language, to launch Open



Write your text and use OpenOffice to format your text, etc., if necessary. A message will be displayed:

"Press ok if you are done with the document to continue!

Once finished, click the OK button to transfer your text to the "Description" field.

Created with the Standard Edition of HelpNDoc: Effortlessly Create High-Quality Documentation with a Help Authoring Tool

Multi-Language reports

The Trial balance, Income statement, Balance sheet, Standard column balances, Budget vs actual, and This year vs last year report types in the Ledger analyser 1.

Financial statements

The following financial statements may be printed and exported in the language set for a user using the Multi-language feature

1. *Trial balance* – *(Example of the Trial balance printed in 2 languages).*
2. *Income statement* -
3. *Balance sheet* –
4. *Standard column balances* –

5. *Budget vs actual* –

6. *This year vs last year* –

Budget listing

This will list all accounts for which budget figures were entered (and / or edited) in Budgets (Reports ribbon) or the Setup → Accounts (Setup ribbon).

If you wish to print a list of the Budget figures, tick the "Budget option" on the following report types:



- Trial balance
- Income statement
- Balance sheet

Export column balances

The following report types in the Ledger analyser 1 or Ledger analyser 2 cannot be printed, but may be exported to a spreadsheet. The language of the logged in user will be exported.

The following six (6) column balances report types is available:

1. *Column balances* – *Lists all accounts in a spreadsheet view. These are the Accounts reported in the Trial balance (this includes both the accounts reported in the Trial balance, Income statement and Balance sheet).*

2. *Column balances debtors* – *Lists the balances of all accounts which is created and maintained in the Debtors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*

3. *Column balances creditors* – *Lists all accounts which is created and maintained in the Creditors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*

4. *Column balances D/C* – *Lists all debit and credit account balances in a spreadsheet view. These are the Accounts reported in the Trial balance (this includes both the accounts reported in the Trial balance, Income statement and Balance sheet).*

5. *Column balances debtors D/C* – *Lists the debit and credit account balances of all accounts which is created and maintained in the Debtors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Debtor's control account on the Trial balance and the Balance sheet.*

6. *Column balances creditors D/C* – *Lists all debit and credit account balances which is created and maintained in the Creditors (Default ribbon) in a spreadsheet view. The total of these accounts are reported in the Creditor's control account on the Trial balance and the Balance sheet.*

Created with the Standard Edition of HelpNDoc: Benefits of a Help Authoring Tool

Multi-language - Chart of accounts listing

Print the Chart of accounts

After translations added, the report options and printed reports will be displayed in the Language set for the logged in user.

To check the translated Chart of accounts into the translated language:

1. Click on the Open icon (Start ribbon).
2. Select the Set of Books and click on the Open button.
3. On the Login screen, enter the username and password for the different language.
4. Click on the OK button. The osFinancials5/TurboCASH5 interface and Set of Books will open in the user's language (as per this example in Afrikaans.
5. Print the Chart of accounts and check if it is correct.
6. Print the Account Group 1 / 2 report and check that the groups are correct.

Logged in as English user





Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: myname@myisp.net
Website: osfinancials.org/en/

Chart of accounts

From account: G010000 To: G999000 **Sequence: Account**

Code	Description	Reporting group 1	Reporting group 2	Type	Open item	Disabled
*G010000	Sales	Income	Income2	Inc / Exp	No	No
*G100000	Cost of sales	Income	Income2	Inc / Exp	No	No
*G200000	Bank charges	Expenses	Expenses2	Inc / Exp	No	No
*G205000	Depreciation	Expenses	Expenses2	Inc / Exp	No	No
*G210000	Motor vehicle expenses	Expenses	Expenses2	Inc / Exp	No	No
*G210010	Fuel and Oil	Expenses	Expenses2	Inc / Exp	No	No
*G210020	Maintenance	Expenses	Expenses2	Inc / Exp	No	No
*G210030	Repairs	Expenses	Expenses2	Inc / Exp	No	No
*G215000	Maintenance of tools	Expenses	Expenses2	Inc / Exp	No	No
*G220000	Rent	Expenses	Expenses2	Inc / Exp	No	No
*G225000	Salaries & Wages	Expenses	Expenses2	Inc / Exp	No	No
*G230000	Stationery	Expenses	Expenses2	Inc / Exp	No	No
*G235000	Sundry expenses	Expenses	Expenses2	Inc / Exp	No	No
G505000	Capital	Capital	Capital2		No	No
G510000	Retained income	Capital	Capital2		No	No
G520000	Installment agreements	Longterm liabilities	Longterm liabilities2		No	No
G600000	Furniture & Fittings - Net value	Fixed assets	Fixed assets2		No	No
G600010	Furniture & Fittings @ Cost	Fixed assets	Fixed assets2		No	No
G600020	Furniture & Fittin - Acc. Deprec.	Fixed assets	Fixed assets2		No	No
G610000	Motor Vehicles - Net value	Fixed assets	Fixed assets2		No	No
G610010	Motor vehicles @ Cost	Fixed assets	Fixed assets2		No	No
G610020	Motor Vehicles -Accum Depreciation	Fixed assets	Fixed assets2		No	No
G700000	Debtors control account	Current assets	Current assets2		No	No
G735000	POS Transfer account	Current assets	Current assets2		No	No
G740000	POS Till account	Current assets	Current assets2		No	No
G745000	POS Cheque account	Current assets	Current assets2		No	No
G750000	Stock control account	Current assets	Current assets2		No	No
B810000	Current Bank account	Current assets	Current assets2	Bank account	No	No
B820000	Petty cash	Current assets	Current assets2	Bank account	No	No
B830000	Call account	Current assets	Current assets2	Bank account	No	No
G850000	VAT Control account	Current liabilities	Current liabilities2		No	No
T850010	Output VAT	Current liabilities	Current liabilities2	Tax account	No	No
T850020	Input VAT - Standard rate	Current liabilities	Current liabilities2	Tax account	No	No
T850030	Input VAT - Capital goods	Current liabilities	Current liabilities2	Tax account	No	No
G850100	VAT Payment	Current liabilities	Current liabilities2		No	No
G900000	Creditors control account	Current liabilities	Current liabilities2		No	No
G999000	Suspense account	Current liabilities	Current liabilities2		No	No

Handyman Hardware Store *Printed : 2022/06/23 11:20:17*

Data: C:\osfinancials5\books\MULTI-LANGDEMO-POSTED\books.fdb
System user: danva osFinancials user: e *Page: 1 / 1*

Logged in as Afrikaans user





Created with the Standard Edition of HelpNDoc: Easily create EBooks

Multi-language - Trial balance

Trial balance

Logged in as English user





Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Company reg. no.: 336012345
Tax reg. no.: 446010111

Phone: (011) 310-1390
Fax: (011) 310-2000

E-mail: myname@myisp.net
Website: osfinancials.org/en/

Trial balance Period 2022/03/01 / 2023/02/28

	Debit	Credit	Totals Debit	Totals Credit
REPORTING GROUP ROOT				
Income				
010000 Sales				19,850.00
100000 Cost of sales			6,000.00	
Expenses				
200000 Bank charges			45.00	
210000 Motor vehicle expenses	1,160.00			
210010 Fuel and Oil			150.00	
210020 Maintenance			410.00	
210030 Repairs			600.00	
220000 Rent			500.00	
230000 Stationery			240.00	
Capital				
505000 Capital				5,000.00
Current liabilities				
850000 VAT Control account		1,846.50		
850010 Output VAT				2,775.00
850020 Input VAT - Standard rate			808.50	
850030 Input VAT - Capital goods			120.00	
900000 Creditors control account				6,150.00
Fixed Assets				
600000 Furniture & Fittings - Net value	2,300.00			
600010 Furniture & Fittings @ Cost			2,300.00	
Current assets				
700000 Debtors control account			19,827.50	
750000 Stock control account				2,500.00
810000 Current Bank account			5,230.00	

Handyman Hardware Store — *Printed : 2022/06/23 00:09:15*
Data: C\osfinancials5\books\2022-MULTI-LANF-POSTED\Books.fdb
System user: danva osFinancials user: e — *Page: 1 / 2*



Logged in as Afrikaans user


Begin
Verstek
Verslae
Opstel
Gebruiker
Verslae
Gebruikerverslae
Ontledingstaat verslae
Grootboekontleder 1
Grootboekontleder 2
Ouderdomsontleding
T-Rekeninge
Drukker
Budgets
Verslae
Per periode
Per datum(s)
Verslag
Uitvoer
Druk
Vertoon
2022/03/01 / 2023/02/28
Periodes
Maand
2 Maande
3 Maande
4 Maande
6 Maande
Jaar
Groepe
Verslaggroep 1
Verslagtipe
Proefbalans
Ignoreer nulbalanse
Wys Debiteure / Krediteure
Sluit openingsbalanse in
Slegs openingsbalanse
Begroting
Kostesentrum 1
Kostesentrum 2
SBR view
Pivot
+
-
VERSLAGGROEP OORSPRONG 0.00 |
#Inkomste | 13,850.00
*G010000 Verkope | 19,850.00
*G100000 Koste van verkope 6,000.00 |
#Uitgawes 1,945.00 |
*G200000 Bankkoste 45.00 |
*G210000 Motorvoertuig uitgawes 1,160.00 |
*G210010 Brandstof 150.00 |
*G210020 Onderhoud 410.00 |
*G210030 Herstelwerk 600.00 |
*G220000 Huur 500.00 |
*G230000 Skryfbehoeftes 240.00 |
#Kapitaal | 5,000.00
G505000 Kapitaal | 5,000.00
#Bedryfslaste | 7,996.50
G850000 BTW-Kontrolerekening | 1,846.50
T850010 Uitset BTW | 2,775.00
T850020 Inset BTW - Standaardkoers 808.50 |
Netto Wins/Verlies C -11,905.00
Balans D 11,905.00



Handyman Hardware Store

27 Olifants Road
Emmarentia
Johannesburg
2195

Registrasienr.: 336012345
BTW-registrasienr.: 446010111

Telefoon: (011) 310-1390
Faks: (011) 310-2000

E-pos: myname@myisp.net
Webtuiste: osfinancials.org/en/

Proefbalans Periode 2022/03/01 / 2023/02/28

	Debiet	Totale Krediet	Debiet	Krediet
VERSLAGGROEP OORSPRONG				
Inkomste				
010000 Verkope				19,850.00
100000 Koste van verkope			6,000.00	
Uitgawes				
200000 Bankkoste			45.00	
210000 Motorvoertuig uitgawes	1,160.00			
210010 Brandstof			150.00	
210020 Onderhoud			410.00	
210030 Herstelwerk			600.00	
220000 Huur			500.00	
230000 Skryfbehoeftes			240.00	
Kapitaal				
505000 Kapitaal				5,000.00
Bedryfslaste				
850000 BTW-Kontrolerekening		1,846.50		
850010 Uitset BTW				2,775.00
850020 Inset BTW - Standaardkoers			808.50	
850030 Inset BTW - Kapitaalgoedere			120.00	
900000 Krediteurekontrolerekening				6,150.00
Vaste Bates				
600000 Meublement - Netto Waarde	2,300.00			
600010 Meublement @ Kosprys			2,300.00	
Bedryfsbates				
700000 Debiteurekontrolerekening			19,827.50	
750000 Voorraadkontrolerekening				2,500.00
810000 Lopende Bankrekening			5,230.00	

Handyman Hardware Store *Gedruk : 2022/06/23 00:01:26*
Data: C\osfinancials5\books\2022-MULTI-LANF-POSTED\Books.fdb
Stelselgebruiker: danva osFinancials gebruiker: a *Bladsy: 1 / 2*



Logged in as Afrikaans user - Exported Trial balance



	A	B	C	D	E	F	G	H
1	Per periode	2022/03/(	Groepe	Verslaggroep 1	Verslagtipe	Proefbalans		
2	Per periode	Jaar	Begroting	FALSE				
3	Ignoreer nulbalanse	TRUE	Sluit openingsbalanse in	FALSE				
4	Wys Debiteure / Krediteure	FALSE	Slegs openingsbalanse	FALSE				
5								
6		VERSLAGGROEP OORSPRONG				0		
7			Inkomste			0		
8			G010000	Verkope			0	18,500.00
9			G100000	Koste van verkope			5,000.00	0
10			Uitgawes			0		
11			G200000	Bankkoste			45	0
12			G210000	Motorvoertuig uitgawes		1,160.00		
13				G210010	Brandstof		150	0
14				G210020	Onderhoud		410	0
15				G210030	Herstelwerk		600	0
16			G220000	Huur			500	0
17			G230000	Skryfbehoeftes			240	0
18			Kapitaal			0		
19			G505000	Kapitaal			0	5,000.00
20			Bedryfslaste			0		
21			G850000	BTW-Kontrolerekening		-1,644.00		
22				T850010	Uitset BTW		0	2,775.00
23				T850020	Inset BTW - Standaardkoers		1,011.00	0
24				T850030	Inset BTW - Kapitaalgoedere		120	0
25			G900000	Krediteurekontrolerekening			0	6,150.00
26			Vaste bates			0		
27			G600000	Meublement - Netto Waarde		2,300.00		
28				G600010	Meublement @ Kosprys		2,300.00	0
29			Bedryfsbates			0		
30			G700000	Debiteurekontrolerekening			18,275.00	0
31			G750000	Voorraadkontrolerekening			0	1,500.00

Created with the Standard Edition of HelpNDoc: Generate EPub eBooks with ease

Print documents in debtor (customer / client) language

Set debtor (customer / client) language

To select / set / change a debtors (customers / clients) preferred language:

1. Click on the Default ribbon, select Debtors; or press the F4 key.
2. Select the debtor (customer / client) account and click on the Edit button; or double-click on a selected debtor (customer / client) account.



3. Select the Debtor's Language.
4. Click on the Save or OK button.

On the Delivery address tab Layout file 1 (Invoice), Layout file 2 (Credit note) and Layout file 3 (Quote) is empty for this this debtor customer / client) account.

The layout files , selected on the "Layout file" field in the Setup → Documents setup on the Setup ribbon, for these document types, will be used for printing documents.

If you have specific or your own custom layout files, you may select your own layout files.

Layout files printed in debtor (customer / client) language:

See examples of translatable layout files.

Example : Invoice - Afrikaans



The Description of the stock item, (i.e. "Kompressor") is a translation of Compressor as defined in the Languages tab of the Stock item.

Print documents in Creditor (supplier/ vendor) language

Print documents in creditor (supplier / vendor) language

Set creditor (supplier / vendor) language

To select / set / change a creditors (supplier / vendor) preferred language:

1. Click on the Default ribbon, select Creditors; or press the F5 key.
2. Select the creditor (supplier / vendor) account and click on the Edit button; or double-click on a selected creditor (supplier / vendor) account account.



3. Select the Creditor's Language.
4. Click on the Save or OK button.

On the Delivery address tab Layout file 1 (Purchase), Layout file 2 (Supplier return) and Layout file 3 (Order) is empty for this this creditor (supplier / vendor) account.

The layout files, selected on the "Layout file" field in the Setup → Documents setup on the Setup ribbon, for

these document types, will be used for printing documents.

If you have specific or your own custom layout files, you may select your own layout files.

Layout files printed in creditor (supplier / vendor) language:

Example : Purchase - Afrikaans

See examples of translatable layout files.



The Description of the stock item, (i.e. "Kompressor") is a translation of Compressor as defined in the Languages tab of the Stock item.

Created with the Standard Edition of HelpNDoc: Make Your PDFs More Secure with Encryption and Password Protection

Workflow plugin

Workflow - Manual - Shop - Licence: Once-off -

Workflow Bank Import Plugin - Shop - Licence: Once-off -

Workflow Editor Plugin - Shop - Licence: Once-off -

Unlock the power of streamlined task management with our Workflow plugin. Seamlessly record every step and process, whether it's inventory management, debtor/creditor tracking, or document handling, within osFinancials5/TurboCASH5. Visualize your workflow at a glance, gaining instant insights into each stage of progress.

Assign tasks or steps to specific users, track outstanding steps, and effortlessly manage transitions between stages. Our Workflow Plugin isn't just a tool - it's a knowledge system, empowering you to formalise and share business processes efficiently. Gain better control over your operations, with historical data readily available for informed decision-making. Say hello to optimized processes and enhanced productivity with the Workflow Plugin.

Workflow Bank Import Plugin

Workflow Bank Import Plugin - Shop - Licence : Once-off

The Workflow Bank Import plugin provides users with a guided step-by-step process for importing downloaded bank transactions and posting them to the appropriate journal or batch. This streamlined workflow ensures efficiency and accuracy in handling bank transactions within osFinancials5/TurboCASH5.

Workflow Editor Plugin

Workflow Editor Plugin - Shop - Licence : Once-off

Use workflow to create you own processes. With the Workflow Editor plugin, you can customize and create your own processes tailored to your specific needs. Whether it's automating tasks, managing approvals, or streamlining workflows, this tool empowers you to design efficient processes that align with your business requirements.

Older Workflow documentation

The workflow plugin allows you to record the steps or processes of a task.

You can also gain knowledge of a process through easier to go through the various tutorials and record the steps.

The different screens osFinancials5/TurboCASH5 can be created such as the stock screen or debtors / creditors and documents. But also websites, or for example, Excel documents appear in the active window with a description. This allows you to record almost every conceivable process, visualize and gain instant insight wherever you are in the process and what steps have been taken before.

A step can be assigned to a user and an administrator can see all workflow steps not done (outstanding steps) and possibly assign a task to a user. Outstanding transitions that are possible after showing the step. A transition is one step to another step. If there is only one valid transition, you will not have any choices.

A transition may include a condition that must be met.

Workflow is a knowledge system that can gain your knowledge or just to share it with others. This allows you to formalize your business and capture the steps in an automated system.

Another advantage is that you retain a better overview of your running processes and you have historical data at hand.

Setup / Activate Workflow

In the standard Set of Books, there are already workflows but if you have an older database, you may import a workflow file from another database using the Workflow editor.



Editor

Workflow list

In the Workflow list, you can create workflow, edit save or load or assign rights.

Rights

Select users (added in Setup → Access control) who are allowed to start this workflow.



Save / load file

With these capabilities, you can easily copy workflow file (*.wfd file type) from one Set of Books to another.

Please note that some selected parameters are not the same in the records which reads your

workflow.

Use Workflow designer

With the designer, you can add steps and see the connections (transitions) visually.



Workflow Add / Edit Steps

Each step is identified by a step name which can be assigned to a screen type. The screen types may be assigned to specific users.

If you edit a step, you will see the following tabs.

1. Stepname: The name of the step.
2. Screen type: Various screens from which you can choose to see a step by step explanation types.

3. User: All users is the default. If you have added users (in Setup → Access control), you may assign this step to a specific to process this step. If a step is set (assigned) to a specific user, then this step will put someone else performing the transition to the user.

Screen type

If you select a screen type, is some documentation on the parameters in the Document groups (Extra) tab. The screen types are as follows:

- report-manager: show reportman reports.
- groups: Groups maintenance screen.
- groups-plugins: Plugins a group.
- stock: Stock screen.
- stock-plugins: Plugins for stock.
- debtor-creditor-plugins: Plugins for debtors creditors.
- debtor-creditor: Debtors or creditors screen.
- planner: Agenda.
- totalviewer: Totals list.
- batch-entry: Journal (batch) entry.
- documents: Documents.
- documents-plugins: Plugins for documents.
- openitem: Open item screen.
- projects: Projects screen.
- workflow-selecteddata: Show selected dates (confirm a selection).
- Workflow-dialog: Dialog (question text with possibly different answers).
- Workflow-webbrowser: Internet Explorer (IE) Web Browser imbedded with which you can go for example to a specific page.

- workflow-olecontainer: Ole container to open different mime types and edit as an Excel document, or displaying a PDF with Acrobad reader.
- workflow-mobilestep: not implemented yet reserved for taking steps via a mobile device.
- workflow-splittask: not implemented yet reserved for splitting a task to two tasks.
- workflow-selectiondata: Make a selection screen with free sql or use one of the standard options.
- main-plugins: Plugins for the main program.
- setup-data: Screens for settings.
- main: Main functions - currently only closes year / open new year.

Step data tab



- Status: reserved
- Duration: The duration of the interval which should be completed within the task.

- Interval: The interval is the maximum duration for a task (step).
- Comments: The text to explain the task (step). This will float as a comment when the mouse is moved over or focus on a step in the Workflow designer. When the Workflow steps are performed, the comments entered here will be displayed when a step (screen) is launched.
- Memo underneath: The SQL to display the line in the workflow list.

Step Reporting groups (Extra) tab



The fields are as follows:

- Params: Parameters for the screen.
- Active param name: the name of the selected parameter.
- lookup value: for some parameters a selection screen is available to select the correct value for this screen.
- Sql step: sql start at step.

- Sql step back: reserved.

- Make this workflow start at documenttype: Fill in the edit box the document type id that you want to use as it is created to start this workflow automatically. If you enter document type 14, for quotes this will create a quote for this workflow. Thus, you can keep progress of the delivery (quote accepted) status process in the different stages and track that different people together can complete a job.

- The document types is as follows:

  10 – Invoice

  11 – Credit note

  12 – Purchase

  13 – Supplier return

  14 – Quote

  15 - Order

Workflow Transition tab



Transitions are the flow to the next step. You may add, delete or edit transitions.



In a transition, you can still make various settings.

- Name: Name of the button in the selection of transitions.
- From: Select the step.
- Workflow: this field is set to empty = current.
- To step: Select the next step where is the transition to.
- Offset left: The left position of the transition to the step.
- Offset top: The upper position of the transition to the step.
- Offset left end: The left position of the transition to the step.
- Offset top end: The upper position of the transition to the step.
- Condition: sql condition, for example; “Select * from dochead where wdocid = <@KEY@>” it produces a record then the transition can proceed.

Workflow useage

Workflow list

In this list you will see the active tasks that still need to be handled, or you can start a new task.

View historical data of a job and looking for completed tasks.

If you are an administrator, you can also edit same workflow.





With your right mouse button, you can also assign tasks to other users.

- Type: The type of workflow that you start when you press on the New icon.
- New: Create a new workflow.
- Process: Show execution screen. This will launch the screens in TurboCASH / osFinancials as assigned to each step.
- History: Shows the history of the task. You may right-click on a selected step to launch the “Where am I?” feature.
- Edit: If you are an administrator, you can quickly edit the workflow.
- Show closed: Shows finished or partially completed workflow steps for a task from date from date field. If you click on the View closed icon, the Open tasks will be listed.
- Where am I?: A screen that shows you where you are currently in the process.

Process workflow

In the output screen shows the current screen or the choice of transitions. The upper part is always displayed and the set screen appears in the lower right by this step. If several transition opportunities as they are executed through selection buttons. You can then choose from the various transitions.

If you click on Continue button the next screen will be lauched.

For example, the Setup workflow is as follows:



Click OK and the Setup company information screen is displayed.



Enter / edit the necessary details, and click OK to save the changes. Click Continue to proceed to the next step.



Add users and assign rights, if necessary, and click Apply to save the changes. Click Continue to proceed to the next step.



Check and set the periods (Start of financial year) and click OK to save the changes. Click Continue to proceed to the next step.



Add, delete or change the batch (journal) names as necessary. Click Continue to proceed to the next step.



Add / edit / delete accounts as necessary. Remember to save the changes. Click Continue to proceed to the next step.



Add / edit / accounts for debtors (customers) as necessary. Click Continue to proceed to the next step.



Add / edit / accounts for creditors (suppliers) as necessary. Click Continue to proceed to the next step.



Where am I

In which I can see where you are in the process screen and what steps have been dealt with when and by whom.



Created with the Standard Edition of HelpNDoc: Transform Your Word Doc into a Professional-Quality eBook with HelpNDoc

Taxonomies and XBRL

What is Taxonomies and relationship to accounting?

In the context of accounting and financial reporting, a taxonomy refers to a standardized classification system or framework that defines the elements, relationships, and concepts used to organize and represent financial information. It provides a structured and consistent way to describe and categorize data elements in financial statements, making it easier to analyse and compare financial information across different companies and jurisdictions.

Taxonomies play a crucial role in the field of accounting as they provide a common language and framework for reporting financial data in a standardized manner. They define the specific elements or concepts that are relevant to financial reporting, such as assets, liabilities, equity, revenue, expenses, and other financial statement items.

The relationship between taxonomies and accounting lies in their ability to facilitate accurate and consistent financial reporting. Accounting standards, such as Generally Accepted Accounting Principles (GAAP) or International Financial Reporting Standards (IFRS), provide the foundation for preparing financial statements. Taxonomies are developed based on these accounting standards to provide a structured framework for reporting financial information in a machine-readable format.

By using a standardized taxonomy, companies can ensure that their financial statements adhere to the prescribed accounting principles and guidelines. It enables the consistent representation of financial data, making it easier for regulators, investors, analysts, and other stakeholders to interpret and compare financial information across different entities and periods.

Taxonomies are typically represented using the eXtensible Business Reporting Language (XBRL), which is an XML-based language designed for the electronic communication of business and financial data. XBRL taxonomies provide a standardized structure for tagging and exchanging financial information, allowing for efficient and accurate reporting, analysis, and regulatory compliance.

In summary, taxonomies provide the framework and structure for organizing, classifying, and reporting financial information in a standardized manner. They are essential in ensuring consistency, comparability, and transparency in financial reporting, and they facilitate the exchange and analysis of financial data across different systems and jurisdictions.

What is a Taxonomy?

In general, a taxonomy is a system for organizing and classifying things into categories based on shared

characteristics.

In the context of finance and accounting, a taxonomy refers to a standardized system of codes and labels used to classify financial and business data. Taxonomies are often used in financial reporting, such as when preparing financial statements, and they provide a common language for businesses, regulators, and investors to communicate financial information.

One example of a financial taxonomy is the eXtensible Business Reporting Language (XBRL), which is a global standard for exchanging business information electronically. XBRL uses a standardized taxonomy to classify financial data and make it easier to analyze and compare across different companies and industries

Which countries use Taxonomies?

Many countries around the world use a financial taxonomy, particularly for financial reporting purposes. The eXtensible Business Reporting Language (XBRL) is one example of a financial taxonomy that is used globally.

In the United States, the Securities and Exchange Commission (SEC) requires public companies to use XBRL when submitting financial statements. The U.S. GAAP Taxonomy is used to standardize financial reporting for companies operating in accordance with the Generally Accepted Accounting Principles (GAAP).

In Europe, the European Banking Authority (EBA) has implemented its own taxonomy, the European Banking Authority Reporting Framework (EBAF), which is used by banks across the European Union. This taxonomy helps harmonize financial reporting and facilitates the exchange of information among banks and regulatory authorities.

Other countries have also implemented their own taxonomies for financial reporting purposes. For example, in Australia, the Australian Securities and Investments Commission (ASIC) requires companies to submit financial reports in XBRL format using the Australian Reporting Taxonomy. In Japan, the Financial Services Agency (FSA) and Financial Accounting Standards Foundation (FASF) have developed the Japanese Taxonomy (J-GAAP) for financial reporting. In India, the Ministry of Corporate Affairs (MCA) has introduced the Indian Accounting Standards (Ind-AS) taxonomy for companies reporting under Indian accounting standards.

These are just a few examples of how taxonomies, particularly XBRL-based taxonomies, are used in various countries for financial reporting. They help standardize financial data, improve accuracy and comparability of financial statements, and facilitate regulatory compliance.

Which countries use Taxonomies?

Taxonomies are used in various countries as part of financial reporting and regulatory frameworks. While

the specific adoption and implementation of taxonomies may vary, here are some countries that use taxonomies:

1. United States: The United States Financial Accounting Standards Board (FASB) uses the US GAAP Taxonomy for reporting financial statements in XBRL format.
2. United Kingdom: The UK HM Revenue & Customs (HMRC) uses taxonomies for electronic filing of tax returns, such as the Corporation Tax and VAT taxonomies.
3. Australia: The Australian Taxation Office (ATO) uses taxonomies for electronic lodgment of tax returns, including the Business Activity Statement (BAS) and Tax File Number (TFN) taxonomies.
4. European Union: The European Banking Authority (EBA), European Insurance and Occupational Pensions Authority (EIOPA), and European Securities and Markets Authority (ESMA) use taxonomies for reporting financial information in the banking, insurance, and securities sectors, respectively.
5. Japan: The Financial Services Agency (FSA) and Financial Accounting Standards Foundation (FASF) in Japan use taxonomies for financial reporting by companies.
6. Netherlands: The Dutch Tax and Customs Administration uses taxonomies for electronic filing of tax returns, such as the Dutch Taxonomy (NT).
7. Singapore: The Inland Revenue Authority of Singapore (IRAS) uses taxonomies for filing tax returns, including the Singapore Financial Reporting Standard (FRS) taxonomies.

These are just a few examples, and taxonomies are utilized in various other countries globally for financial reporting, tax filing, and regulatory purposes. The specific taxonomies used and their application may vary depending on the country and the specific reporting requirements of regulatory bodies and tax authorities.

What is XBRL and relationship to accounting?

XBRL stands for eXtensible Business Reporting Language. It is a standardized, XML-based language that is used for the electronic communication of business and financial data. XBRL provides a structured format for representing and exchanging financial information in a machine-readable format.

The relationship between XBRL and accounting is closely intertwined. XBRL is specifically designed to enhance the efficiency, accuracy, and transparency of financial reporting and analysis. It allows for the standardized tagging and exchange of financial data, making it easier to understand, compare, and analyze financial information across different entities and periods.

XBRL facilitates the communication of financial information by assigning unique tags to individual data elements within financial statements. These tags identify the specific concepts or items being reported, such as assets, liabilities, revenue, expenses, and other financial statement elements. By using XBRL,

companies can provide structured and consistent data that can be easily interpreted and processed by various stakeholders, including regulators, investors, analysts, and software applications.

One of the key benefits of XBRL in accounting is the automation of data collection and analysis. By tagging financial data using XBRL, companies can streamline the process of preparing and submitting financial reports to regulatory authorities. It enables efficient and accurate extraction, aggregation, and analysis of financial information, reducing manual data entry errors and enhancing the speed and reliability of financial reporting.

XBRL also supports the standardization of accounting information across different jurisdictions and reporting frameworks. It provides a common language for reporting financial data, allowing for better comparability and consistency in financial reporting practices globally. XBRL taxonomies, which define the structure and meaning of the data elements, are developed based on accounting standards such as Generally Accepted Accounting Principles (GAAP) or International Financial Reporting Standards (IFRS).

Overall, XBRL plays a vital role in modernizing and improving the efficiency of accounting processes. It enhances the accuracy, transparency, and comparability of financial information, enabling stakeholders to make better-informed decisions based on standardized and machine-readable data.

Is XBRL and Taxonomies related in accounting ?

Yes, XBRL and taxonomies are closely related in accounting. XBRL provides a standardized language and framework for representing financial information, while taxonomies define the specific elements and relationships within that framework.

In XBRL, taxonomies serve as the foundation for tagging financial data. A taxonomy is a structured dictionary or classification system that defines the specific data elements, their meanings, and the relationships between them. It provides a standardized set of tags or codes that can be applied to individual data points in financial statements.

Taxonomies are developed based on accounting standards such as Generally Accepted Accounting Principles (GAAP) or International Financial Reporting Standards (IFRS). They define the specific elements and concepts used in financial reporting, such as assets, liabilities, revenue, expenses, and other financial statement items.

By using the appropriate taxonomy, companies can tag their financial data with the relevant codes, ensuring consistency and standardization in reporting. This allows for the seamless exchange and analysis of financial information across different entities, jurisdictions, and reporting frameworks.

Taxonomies also enable data consumers, such as regulators, investors, and analysts, to interpret and understand the financial data more effectively. They provide a common language and structure for financial reporting, facilitating the comparison and analysis of financial information from various sources.

In summary, taxonomies play a crucial role in XBRL-based financial reporting. They define the standardized elements and relationships within the XBRL framework, ensuring consistency, comparability, and interoperability of financial data across different accounting standards and reporting entities.

Which countries use XBRL?

XBRL (eXtensible Business Reporting Language) is used by numerous countries worldwide for financial reporting and regulatory purposes. Some of the countries that have adopted XBRL include:

1. United States: The Securities and Exchange Commission (SEC) requires public companies to submit their financial statements in XBRL format.
2. United Kingdom: XBRL is used for filing financial statements with Companies House and the Financial Conduct Authority (FCA).
3. Australia: The Australian Securities and Investments Commission (ASIC) mandates the use of XBRL for financial reporting by companies.
4. Japan: XBRL is widely used in Japan for financial reporting and disclosure purposes by companies listed on the Tokyo Stock Exchange.
5. European Union: The European Securities and Markets Authority (ESMA) requires XBRL-based reporting for listed companies in EU member states.
6. Singapore: XBRL is used by companies in Singapore for submitting financial statements to the Accounting and Corporate Regulatory Authority (ACRA).
7. China: XBRL is utilized by the China Securities Regulatory Commission (CSRC) for reporting financial information by listed companies.
8. South Korea: The Financial Supervisory Service (FSS) in South Korea requires companies to submit financial statements in XBRL format.
9. India: The Ministry of Corporate Affairs (MCA) in India has implemented XBRL for reporting by certain categories of companies.

These are just a few examples, and there are many other countries around the world that have adopted XBRL or are in the process of doing so. The adoption and usage of XBRL may vary in terms of the scope of reporting, regulatory requirements, and specific implementation details in each country.

Resources

- Taxonomy 101: The Basics and Getting Started with Taxonomies -

- Taxonomy - Wikipedia -

- Learn more about improving reporting with XBRL -

- More iXBRL tools come to market -

- XBRL and Taxonomies -

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with a Help Authoring Tool

Database types

In addition to the Firebird database type, osFinancials5/TurboCASH5 also supports MSSQL database type.

Created with the Standard Edition of HelpNDoc: Full-featured EPub generator

Firebird databases

---

osFinancials5/TurboCASH5 supports 79 different languages and counties / tax regimes languages liked to 87 Sets of Books (firebird database-types) which may be downloaded and customised to meet your requirements.

If the set of books for your language and or country, is not available in the books directory, you may select any of the available Firebird Sets of Books and linked languages available as a free download.

All firebird database types available for download (Create a Set of Books -default option), is upgraded from Firebird version 1.5 (ODS version - 10.1) to Firebird version 2.1 - (ODS version - 11.1)

For those advanced users, which may wish to explore the database tables and version, etc., you may install Firebird and FlameRobin which is included in the installs folder of your osFiinancials 5 installation folder.



Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

Firebird install

Copy Firebird client library to <system> directory = Tick

Firebird 1.5 creates databases with an ODS (On-Disk Structure) version of 10.1.

Firebird 2.1 creates databases with an ODS (On-Disk Structure) version of 11.1.

Select the "*Firebird.exe*" file in installs folder of the osFinancials5/TurboCASH5 installation directory.



Setup - Firebird
Welcome to the Firebird Setup Wizard
This will install Firebird 2.1.3.18185 (Win32) on your computer.
It is recommended that you close all other applications before continuing.
Click Next to continue, or Cancel to exit Setup.
Next >
Cancel


Setup - Firebird
License Agreement
Please read the following important information before continuing.
Please read the following License Agreement. You must accept the terms of this agreement before continuing with the installation.
INTERBASE PUBLIC LICENSE
Version 1.0
1. Definitions.
1.0.1. "Commercial Use" means distribution or otherwise making the Covered Code available to a third party.
1.1. "Contributor" means each entity that creates or contributes to the creation of Modifications.
1.2. "Contributor Version" means the combination of the Original Code, prior Modifications used by a Contributor, and the Modifications made by that particular Contributor.
1.3. "Covered Code" means the Original Code or Modifications or the combination of
I accept the agreement
I do not accept the agreement
English
< Back
Next >
Cancel


Setup - Firebird
Information
Please read the following important information before continuing.
When you are ready to continue with Setup, click Next.
Firebird Database Server 2.1
==========
This document is a guide to installing this package of
Firebird 2.1 on the Windows platform. These notes refer
to the installation package itself, rather than
Firebird 2.1 in general. In addition, these notes are
primarily aimed at users of the binary installer.
It is assumed that readers of this document are already
familiar with Firebird 2.0. If you are evaluating
Firebird 2.1 as part of a migration from Fb 1.5 you are
advised to review the Fb 2.0 documentation to
English
< Back
Next >
Cancel


Setup - Firebird
Select Destination Location
Where should Firebird be installed?
Setup will install Firebird into the following folder.
To continue, click Next. If you would like to select a different folder, click Browse.
C:\Program Files (x86)\Firebird\Firebird_2_1
Browse...
At least 1.4 MB of free disk space is required.
English
< Back
Next >
Cancel


Setup - Firebird
Select Components
Which components should be installed?
Select the components you want to install; clear the components you do not want to install. Click Next when you are ready to continue.
Full installation of Server and development tools.
Server components 6.9 MB
Classic Server binary 2.6 MB
Super Server binary 2.7 MB
Developer and admin tools components 8.5 MB
Client components 0.7 MB
Current selection requires at least 21.0 MB of disk space.
English
< Back
Next >
Cancel


Setup - Firebird
Select Start Menu Folder
Where should Setup place the program's shortcuts?
Setup will create the program's shortcuts in the following Start Menu folder.
To continue, click Next. If you would like to select a different folder, click Browse.
Firebird 2.1 (Win32)
Browse...
Don't create a Start Menu folder
English
< Back
Next >
Cancel



Important : Copy Firebird client library to <system> directory ? = Tick




Setup - Firebird
Information
Please read the following important information before continuing.
When you are ready to continue with Setup, click Next.
Firebird 2.1.3 (Windows Build)
o Introduction
o Intended Users
o Known Issues
o Features in this release (all platforms)
o Installation
o Reporting Bugs
English
Next >

Setup - Firebird
Completing the Firebird Setup Wizard
Setup has finished installing Firebird on your computer. The application may be launched by selecting the installed icons.
Click Finish to exit Setup.
Start Firebird Service now?
After installation - What Next?
< Back
Finish

FlameRobin install

Install FlameRobin

Select the "flamerobin.exe" file in installs folder of the osFinancials5/TurboCASH5 installation directory.




Setup - FlameRobin
License Agreement
Please read the following important information before continuing.
Please read the following License Agreement. You must accept the terms of this agreement before continuing with the installation.
Copyright (c) 2004-2008 The FlameRobin Development Team
Permission is hereby granted, free of charge, to any person obtaining a copy of this software and associated documentation files (the "Software"), to deal in the Software without restriction, including without limitation the rights to use, copy, modify, merge, publish, distribute, sublicense, and/or sell copies of the Software, and to permit persons to whom the Software is furnished to do so, subject to the following conditions:
The above copyright notice and this permission notice shall be included
I accept the agreement
I do not accept the agreement
< Back
Next >
Cancel


Setup - FlameRobin
Select Destination Location
Where should FlameRobin be installed?
Setup will install FlameRobin into the following folder.
To continue, click Next. If you would like to select a different folder, click Browse.
C:\Program Files (x86)\FlameRobin
Browse...
At least 1.7 MB of free disk space is required.
< Back
Next >
Cancel


Setup - FlameRobin
Select Start Menu Folder
Where should Setup place the program's shortcuts?
Setup will create the program's shortcuts in the following Start Menu folder.
To continue, click Next. If you would like to select a different folder, click Browse.
FlameRobin
Browse...
Don't create a Start Menu folder
< Back
Next >
Cancel


Setup - FlameRobin
Select Additional Tasks
Which additional tasks should be performed?
Select the additional tasks you would like Setup to perform while installing FlameRobin, then click Next.
Additional icons:
Create a desktop icon
Create a Quick Launch icon
< Back
Next >
Cancel


Setup - FlameRobin
Ready to Install
Setup is now ready to begin installing FlameRobin on your computer.
Click Install to continue with the installation, or click Back if you want to review or change any settings.
Destination location:
C:\Program Files (x86)\FlameRobin
Start Menu folder:
FlameRobin
Additional tasks:
Additional icons:
Create a desktop icon
Create a Quick Launch icon
< Back
Install
Cancel


Setup - FlameRobin
Completing the FlameRobin Setup Wizard
Setup has finished installing FlameRobin on your computer. The application may be launched by selecting the installed icons.
Click Finish to exit Setup.
Launch FlameRobin
Show Release Notes
Finish





Created with the Standard Edition of HelpNDoc: From Word to ePub or Kindle eBook: A Comprehensive Guide

Flame Robin - Firebird connection

FlameRobin and Firebird Databases

To use FlameRobin, you need to have Firebird installed. FlameRobin is a graphical database administration tool specifically designed to work with Firebird databases. It allows users to manage Firebird databases, execute SQL queries, and perform various administrative tasks such as creating and modifying database objects.

FlameRobin interacts with Firebird servers to perform these tasks. Therefore, you must have Firebird installed and running either locally or on a remote server that you can connect to with FlameRobin.

You can download and install Firebird separately from FlameRobin. Once Firebird is installed and configured, you can then install FlameRobin to manage your Firebird databases.

Firebird 2.1 and FlameRobin is included in the installs folder of your osFiinancials5/TurboCASH5 installation folder.

Testing the Connection with FlameRobin

If you experience connection issues with Firebird and FlameReobin, check and allow permissions for these apps in your Windows Firewall settings

While optional, testing the connection with FlameRobin can serve as a useful diagnostic tool. It's not necessary for osFinancials5/TurboCASH5 to function correctly, but it's handy for verifying database connectivity.

Add a new server if you are on the client machine (you also need the client install of Firebird for this) of just use localhost if flame is running on the server.

1. Launch FlameRobin and navigate to the "*Home*" tab.
2. Right-click and select "*Register server...*" from the context menu.



3. Enter the following:
    a) Display name: - Assign an arbitrary name to recognise the server.

b) Hostname: - Enter the IP address or hostname of the server (you can find this using '*ipconfig*' in the command prompt).

c) Port number: - Leave this field empty (default).

4. Right-click the newly added server and choose "*Register existing database...*" from the context menu.



5. Enter the following:

a) Display name: - Enter the name you want to use for this particular set of books.

b) Database path: - Enter the full server path to the books.fdb file or select a database file on your system.

c) Username: - Default is *sysdba*

d) Password: - Default is *masterkey*.

6. Click "*Save*" and double-click the added database. This will confirm if the database tables are visible.



7. You can browse through the tables to view the data of your Set of Books. A successful connection indicates no issues.

Checking the Firebird version with FlameRobin

Firebird 1.5 databases have an ODS (On-Disk Structure) version of 10.1, while Firebird 2.1 databases have an ODS version of 11.1.

To check the Firebird version:

Right-click on the Server name (e.g. "*localhost*") and select "*Retrieve server version*" from the context menu or the Server menu.



This process confirms compatibility with Firebird 2.1, which is included in the installs folder of your osFinancials5/TurboCASH5 installation. The Firebird databases of the templates for Sets of Books and linked languages, available as a free download, are upgraded to Firebird 2.1 with ODS version 11.1.

NOTE: In TurboCASH5-2 and earlier versions, Sets of Books templates in the bin/Repository and bin/Tutorials folder are still Firebird databases from version 1.5 (ODS 10.1).

Created with the Standard Edition of HelpNDoc: Transform Your CHM Help File Creation Process with HelpNDoc

Firebird database upgrade

Before you upgrade please Backup the Database, use the make a copy or backup of the Set of Books to be Restored and upgraded.

Firebird Database Sets of Books in osFinancials5.1/TurboCASH5-3

All sets of books for use with osFinancials5.1 and TurboCASH5-3 have been updated from Firebird databases version 1.5 (ODS 10.1) to version 2.1 (ODS 11.1) and are available in the following options:

- osFinancials databases are available on the webserver. Download them via "Let osFinancials help you create a Set of Books?" or "Let TurboCASH5-3 help you create a Set of Books?" in Create Set of Books

on the Start ribbon (Press F10). For year-end tasks, set your financial year start in Setup → Reporting dates.

- TurboCASH5-3 Sets of Books templates are stored in the following folders:
    - bin/Repository: Various templates based on country and language choices during installation.
    - bin/4-DIGIT-BOOKS
    - bin/CHINESE
    - bin/CUSTOMISE-EMPTY-BOOKS
    - bin/Tutorials

NOTE: In TurboCASH5-2 and earlier versions, Sets of Books templates in the bin/Repository and bin/Tutorials folder are still Firebird databases from version 1.5 (ODS 10.1).

Is it optional for existing users of previous versions of osFinancials/TurboCASH databases version 1.5 (ODS 10.1) to upgrade your Firebird databases from version 1.5 (ODS 10.1) to version 2.1 (ODS 11.1)?

Existing users of previous versions of osFinancials/TurboCASH support Firebird databases version 1.5 (ODS 10.1). When Migrating their Set of Books to osFinancials5.1/TurboCASH5-3 their Set of Books may be using Firebird databases version 1.5 (ODS 10.1).

The decision to upgrade your Firebird databases from version 1.5 (ODS 10.1) to version 2.1 (ODS 11.1) depends on several factors, including your specific use case, the requirements of your software (osFinancials or TurboCASH), and your long-term goals. Here's a detailed breakdown to help you decide:

When Upgrading is Optional

Upgrading is optional if:

- Your Current Setup Works Fine:
    - If your existing Firebird 1.5 databases are functioning correctly with your current version of osFinancials or TurboCASH, and you have no immediate need for new features or improvements, you can continue using the older version.
- You Are Not Facing Performance or Security Issues:

- If your database performance is acceptable and you are not concerned about potential security vulnerabilities in Firebird 1.5, upgrading may not be urgent.

- You Are Not Planning to Upgrade Your Software:
  - If you do not plan to upgrade to osFinancials 5.1 or TurboCASH 5.3 (which are designed for Firebird 2.1), there is no immediate need to upgrade the database.

When Upgrading is Recommended or Required

Upgrading is recommended or required if:

- You Are Upgrading Your Software:
  - If you plan to upgrade to osFinancials 5.1 or TurboCASH 5.3, you must upgrade your Firebird databases to version 2.1 (ODS 11.1). These newer software versions are designed to work with Firebird 2.1 and may not be compatible with Firebird 1.5.

- You Need Better Performance:
  - Firebird 2.1 includes significant performance improvements over Firebird 1.5. If your database operations are slow or inefficient, upgrading can help.

- You Require Enhanced Security:
  - Firebird 2.1 includes security enhancements that are not available in Firebird 1.5. If your database contains sensitive information, upgrading is strongly recommended.

- You Want Access to New Features:
  - Firebird 2.1 introduces new features and capabilities that may be beneficial for your application or workflow.

- You Need Ongoing Support:
  - Firebird 1.5 is an outdated version and is no longer supported by the Firebird project. Upgrading to Firebird 2.1 ensures that you have access to support, bug fixes, and updates.

- You Are Migrating to a New Environment:
  - If you are moving your database to a new server or environment, it is a good opportunity to upgrade to the latest supported stable version of Firebird.

Risks of Not Upgrading

If you choose not to upgrade, be aware of the following risks:

- Compatibility Issues:
  - Future updates to osFinancials or TurboCASH may not support Firebird 1.5, leaving you unable to upgrade your software.
- Security Vulnerabilities:
  - Firebird 1.5 may have unpatched security vulnerabilities, putting your data at risk.
- Performance Limitations:
  - You may miss out on performance optimizations available in Firebird 2.1.
- Lack of Support:
  - If you encounter issues with Firebird 1.5, you may not be able to find support or solutions.

Conclusion

- Optional: If you are satisfied with your current setup and do not plan to upgrade your software, you can continue using Firebird 1.5 (ODS 10.1).
- Recommended/Required: If you are upgrading to osFinancials 5.1 or TurboCASH 5.3, or if you want better performance, security, and support, you should upgrade your Firebird databases to version 2.1 (ODS 11.1).

Before upgrading, always back up your databases and test the upgraded environment to ensure compatibility with your applications. If you are unsure, consult the documentation for osFinancials, TurboCASH, or Firebird, or seek assistance from a qualified database administrator.

FlameRobin Process to Upgrade Firebird Databases

In FlameRobin, after registering an existing database using the Register existing database option, you can verify the Firebird version of the database.

To accomplish this, connect to the database and select Database Properties from the Database menu or from the context menu.

For reference:

- Firebird database ODS version 10.1 corresponds to Firebird version 1.5.



If you wish to upgrade the database (Set of Books) from Firebird1.5 (ODS Version 10.1) to Firebird2.1 (ODS Version 11.1), you need to do the following:

1. Disconnect the database in FlameRobin.
2. Right-click and select the Backup database...



3. Backup the Database.

4. Enter a "*Backup file*" name to back up the database.



5. Restore the Database - Use the same "*Backup file*" name to restore the database.



6. Connect to the database and verify it's Firebird ODS version 11.1, corresponding to Firebird version 2.1.



Created with the Standard Edition of HelpNDoc: Transform Your Documentation Workflow with HelpNDoc's Intuitive UI

Microsoft SQL Server (MSSQL) Databases

MSSQL Server configuration, settings and Firewall settings to open a Set of Books

When opening an MSSQL database type Set of Books in osFinancials5/TurboCASH5, there are certain server, account control, and firewall settings that need to be configured correctly. These settings ensure that osFinancials5/TurboCASH5 can establish a connection to the MSSQL Server and access the database.

Here are some considerations regarding the server, account control, and firewall settings:

1. MSSQL Server Configuration: The MSSQL Server needs to be properly installed and configured on the server machine. This includes ensuring that the server is running, the necessary services are active, and the database is accessible.
2. Server Name and Credentials: When opening an MSSQL database type Set of Books, you need to provide the correct server name or IP address along with the appropriate credentials (username and password) to establish a connection to the MSSQL Server. These details should be provided during the Set of Books setup process.
3. Account Control Settings: Depending on the security settings of your MSSQL Server, you may need to ensure that the user account used to access the database has the necessary permissions and privileges. This includes granting the account appropriate access rights to the database.
4. Firewall Settings: If your server machine has a firewall enabled, you may need to configure the firewall to allow incoming connections to the MSSQL Server. This involves opening the necessary ports (e.g., port 1433 for MSSQL) to allow communication between osFinancials5/TurboCASH5 and the database server.

It's important to consult with your IT administrator or database administrator to ensure that the server, account control, and firewall settings are properly configured to enable the opening of an MSSQL database type Set of Books in osFinancials5/TurboCASH5.

Created with the Standard Edition of HelpNDoc: Don't be left in the past: convert your WinHelp HLP help files to CHM with HelpNDoc

Create Set of Books (Advanced - MSSQL)

---

osFinancials5/TurboCASH5 Set of Books Microsoft SQL Server database type

Before creating an MSSQL database type (Set of Books), you must add an empty database in "*Microsoft SQL Server*".

This option allows you to create your own Set of Books for the MSSQL database type from scratch without using any of the Set of Books (templates) already available for osFinancials5/TurboCASH5 and customize them according to your needs.

When you create a Set of Books for the MSSQL database type consists of 2 parts:

1. Create a new blank database for osFinancials5/TurboCASH5 on "*MSQL Server*"
2. Create a new Set of Books in osFinancials5/TurboCASH5 for the "*MSQL Server*" database type.

Create a new bank database in Microsoft SQL Server

Before creating a MSSQL Database type (Set of Books) in osFinancials5/TurboCASH5, it is necessary to add a blank database in Microsoft SQL Server. This database will serve as the foundation for your Set of Books and will store all the financial data and information.

To add a blank database in Microsoft SQL Server, follow these steps:

1. Open Microsoft SQL Server Management Studio.
2. Connect to your SQL Server instance using the appropriate credentials.
3. In the Object Explorer, right-click on "*Databases*" and select "New Database..."



4. Provide a name for your new database and configure any additional settings, such as file locations and sizes.

5. Click "OK" to create the blank database.



Once you have successfully added the blank database, make note of the Server name (and instance if applicable) and the name of your newly created database. These details will be required during the process of creating a new Set of Books in osFinancials5/TurboCASH5 using the "*Customise your own Set of*

Books (Advanced)?" option.

By having a blank database in place, you can start building your Set of Books from scratch and tailor it to meet your specific needs and requirements within the MSSQL database type (Microsoft SQL Server).

Create a new Set of Books in osFinancials5/TurboCASH5 for the "*MSQL Server*" database type

In osFinancials5/TurboCASH5, when creating a Set of Books from scratch using the "*Customise your own Set of Books (Advanced)?*" option in the "*Creation wizard*", you have the flexibility to define your chart of accounts according to your specific needs and requirements.

When creating a Set of Books using the "*Customise your own Set of Books (Advanced)?*" option, you begin with a clean slate and have to build your chart of accounts from scratch. The initial setup process will only include three main control accounts: the Debtor's control account, Creditor's control account, and Retained earnings account.

As part of this customisation process, you will have the opportunity to set the number of main digits for your accounts, ranging from 3 to 8 digits. Additionally, you will specify the account numbers for three main control accounts: the Creditors control account, Debtors control account, and Retained earnings account.

1. *The Creditors control account is a general ledger account that represents the total amount owed to the company by its creditors or suppliers. It serves as a summary account for all individual creditor accounts and helps track the company's outstanding payables.*
2. *The Debtors control account, on the other hand, is a general ledger account that represents the total amount owed to the company by its debtors or customers. It acts as a summary account for all individual debtor accounts and aids in monitoring the company's receivables.*
3. *The Retained earnings account, reflects the cumulative net earnings or profits of the company that have been retained and reinvested in the business. It represents the portion of equity that is derived from the company's profitability and serves as a financial record of the accumulated profits over time.*

By defining these main control accounts during the Set of Books creation process, you can structure your chart of accounts and design the account numbering system that aligns with your specific accounting practices and reporting requirements.

To complete the setup and create a comprehensive chart of accounts, you will need to define and link all the necessary accounts in your organisation. This includes creating and setting up Ledger accounts, Bank accounts, Creditor accounts, Debtor accounts, and Tax accounts. You have the flexibility to customize the account structure and naming conventions based on your specific requirements.

Additionally, you will also need to create and configure other elements such as Batch types, Groups, and any other accounts or settings that are relevant to your business operations. This allows you to tailor the

Set of Books to suit your organisation's needs and ensure accurate financial management and reporting.

By going through the setup process and defining the necessary accounts, you establish the foundation for recording and managing financial transactions within osFinancials5/TurboCASH5, enabling you to effectively track and analyse your company's financial activities.

Choosing the number of digits for main accounts

See - Chart of Accounts - Optimising 4-,5-,6-,7- and 8-digit main accounts - Some recommendations and tips to plan your Chart of Accounts according to your selection on the number of Main account digits -

Choosing the appropriate number of digits for main accounts is an important consideration when setting up your Chart of Accounts in osFinancials5/TurboCASH5. The number of digits determines the level of detail and granularity in your account numbering system.

When creating your Set of Books, you will be prompted to select the number of main account digits. For example, if you choose a 4-digit main accounts Chart of Accounts, the and you have initially assigned the following account numbers: 1100 for the Debtor's control account, 2100 for the Creditor's control account, and 3100 for the Retained earnings account. These are default account codes that can be modified later if needed.

The selection of main account digits impacts the structure and organization of your Chart of Accounts. Here are some recommendations and tips to consider:

- 4-digit main accounts: This option provides a concise and compact Chart of Accounts, it can be suitable for small and medium enterprises as well as larger organizations that need to comply with various accounting frameworks and standards such as GAAP US, GAAP UK, SA GAAP, NZ GAAP, IFRS (full), IFRS for SMEs, and others based on their jurisdiction and accounting needs. However, it's important to note that this option may have limitations in accommodating detailed account classifications or sub-categories.
- 5 to 8-digit main accounts: These options offer greater offer greater flexibility and granularity in your Chart of Accounts. These options allow for more detailed account classifications and sub-categories, making them beneficial for larger organizations or those with complex accounting requirements. With these options, you can design a Chart of Accounts that aligns precisely with your financial reporting needs and internal management requirements.

It's crucial to consider your organization's size, complexity, and reporting needs when choosing the number of main account digits. By selecting the appropriate option, you can ensure that your Chart of Accounts supports accurate financial reporting, compliance with accounting standards, and effective management of your organization's financial data.

When creating a Set of Books with the option to choose the number of digits for main accounts, you have the flexibility to select a structure that suits your needs. Here are the available options and the corresponding number of digits for the general ledger main accounts:

4-Digit General ledger main accounts: Enter a 4-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100, 1100, and 3100). This option includes 3-digit sub-accounts as well as 7-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger.

5-Digit General ledger main accounts: Enter a 5-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000, 11000, and 31000). This option includes 3-digit sub-accounts as well as 8-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

6-Digit General ledger main accounts: Enter a 6-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 210000, 110000, and 310000). This option includes 3-digit sub-accounts as well as 9-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

7-Digit General ledger main accounts: Enter a 7-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100000, 1100000, and 3100000). This option includes 3-digit sub-accounts as well as 10-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

8-Digit General ledger main accounts: Enter an 8-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000000, 11000000, and 31000000). This option includes 3-digit sub-accounts as well as 11-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

When planning your Chart of Accounts, it's important to carefully consider and define the codes or numbers for these accounts based on the structure you have chosen. This will help ensure consistency and organization in your financial reporting and analysis.

After creating your Set of Books, you still have the flexibility to change the account codes or numbers in the Chart of Accounts. In the Setup → Accounts menu on the Setup ribbon, you can modify the account codes to align with your specific requirements, including the codes for the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100, 1100, and 3100 in the example of the 4-Digit General ledger main accounts). This initial stage allows you to plan and design your chart of accounts according to your needs.

However, it's important to note that once you start processing functions such as entering transactions or budgets, you may not be allowed to change the account codes or numbers. Therefore, careful consideration and planning during the initial setup stage is crucial to ensure accurate financial structure and reporting.

By carefully selecting the number of main account digits and customizing the account codes in the Chart of Accounts, you can optimize the organization and usability of your financial data within osFinancials5/TurboCASH5.

Defining Account groups and Financial categories

Before creating and setting up Ledger accounts, Bank accounts, Creditor accounts, Debtor accounts, and Tax accounts in osFinancials5/TurboCASH5, it is recommended to define the basic classification of accounts using Account Group 1 or Account Group 2. This helps organize and categorize your accounts based on their nature or function.

In the Setup → Groups menu on the Setup ribbon, you can add Account Group 1 or Account Group 2 and assign them meaningful names that represent different account classifications. For example, you can create groups for fixed assets, cash and receivables, current assets, current liabilities, equity, operating expenses, operating revenue, non-operating expenses, non-operating revenue, etc. These groups provide a structured framework for organising your accounts.

After creating the account groups, you can map or link them to the five financial categories: Assets, Liabilities, Equity, Income, and Expenses in the Setup → Financial categories menu on the Setup ribbon. This mapping ensures that the accounts are correctly classified within the financial framework of your organisation.

When you proceed to create and set up Ledger accounts, Bank accounts, and Tax accounts in the Setup → Accounts menu, you will have the option to select the appropriate Account Group 1 and/or Account Group 2 for each account. By associating the accounts with their respective account groups, you establish a hierarchical structure that allows for easier navigation and analysis of financial information.

By properly defining and linking account groups, you lay the foundation for accurate financial reporting and analysis within osFinancials5/TurboCASH5, enabling you to effectively track and manage your organisation's financial data.

Customize your own Set of Books (Advanced) option for MSSQL database type

The "*Customize your own Set of Books (Advanced)?*" option in osFinancials provides a powerful capability to create a customized Set of Books tailored to your specific requirements. In addition to the default Firebird database type, osFinancials5/TurboCASH5 also offers the option to create a Set of Books for the MSSQL database type.

By selecting the MSSQL database type, you can take advantage of the features and benefits offered by Microsoft SQL Server. This includes robust data management, scalability, and integration capabilities,

making it an ideal choice for organisations that prefer to utilize SQL Server as their database platform.

With the "*Customize your own Set of Books (Advanced)?*" option for MSSQL database type, you have the freedom to design and build your Set of Books from scratch, ensuring it aligns perfectly with your financial structure and reporting needs. This allows you to define your own chart of accounts, configure account settings, set up ledger accounts, bank accounts, tax accounts and establish various parameters according to your specific business requirements.

Let's explore the process of creating a Set of Books using the "Customize your own Set of Books (Advanced)" option for the MSSQL database type, empowering you to create a comprehensive financial management system tailored to your organization's needs.

Process to create a Set of Books using the Customize your own Set of Books (Advanced) option

To create a Set of Books using the Advanced option:

1. On the Start ribbon, you can select the Create Set of Books option or simply press the F10 key on your keyboard.



2. osFinancials5/TurboCASH5 automatically defaults to the option "*Let osFinancials help you to create a Set*

of Books?", as this is the recommended option for most users. Select the "*Create a Set of Books (Advanced)?*" option.

3. Click on the Next button.



4. Enter the name for your Set of Books for the blank database that you have created in the Microsoft SQL Server.

It's important to note that when selecting the "MSSQL" option, you should have already set up a blank database in Microsoft SQL Server, and have the necessary credentials and information to establish the connection with the SQL Server instance.

The Directory in which you create the Set of Books is displayed underneath the Location Browse button. It will usually be the default directory (e.g. "C: \ osfinancials5 \ books" folder in which osFinancials is installed or directory, which you have specified when you installed osFinancials5/TurboCASH5. If you wish to create your Set of Books in any other directory or location on your system, you may click on the Browse button, if desired, to select any folder or drive on the "Pick a directory" screen.

5. Database type: By default, osFinancials uses the "*Firebird (default)*" database type. However, if you prefer to create a Microsoft SQL Server database for your Set of Books, you can choose the "*MSSQL*"

option. Selecting the "*MSSQL*" option ensures that the database is specifically configured to work with Microsoft SQL Server. This allows you to take advantage of the features and capabilities provided by the SQL Server platform.

6. Check the database type is set to the "*MSSQL*" option, and click on the Next button.



7. Account digits: The default number of account Digits is 3. Select the desired number of digits for your general ledger main accounts. This will determine the structure and length of the account codes for the Creditor's control, Debtor's control, and Retained income/earnings accounts.

8. Account codes: Enter the numeric code for each of these accounts based on the chosen number of digits. For example, in a 4-digit structure, you would enter codes like 2100, 1100, and 3100.

When creating a Set of Books with the option to choose the number of digits for main accounts, you have the flexibility to select a structure that suits your needs. Here are the available options and the corresponding number of digits for the general ledger main accounts:

4-Digit General ledger main accounts: Enter a 4-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100, 1100, and 3100). This option includes 3-digit sub-accounts as well as 7-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger.

5-Digit General ledger main accounts: Enter a 5-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000, 11000, and 31000). This option includes 3-digit sub-accounts as well as 8-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

6-Digit General ledger main accounts: Enter a 6-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 210000, 110000, and 310000). This option includes 3-digit sub-accounts as well as 9-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

7-Digit General ledger main accounts: Enter a 7-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 2100000, 1100000, and 3100000). This option includes 3-digit sub-accounts as well as 10-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

8-Digit General ledger main accounts: Enter an 8-digit numeric code for each of the Creditor's control, Debtor's control, and Retained income/earnings accounts (e.g., 21000000, 11000000, and 31000000). This option includes 3-digit sub-accounts as well as 11-Digit account codes for Debtor accounts in the debtors ledger and Creditor accounts in the creditors ledger

When planning your Chart of Accounts, it's important to carefully consider and define the codes or numbers for these accounts based on the structure you have chosen. This will help ensure consistency and organization in your financial reporting and analysis.

However, it's important to note that once you start processing functions such as entering transactions or budgets, you may not be allowed to change the account codes or numbers. Therefore, careful consideration and planning during the initial setup stage is crucial to ensure accurate financial structure and reporting.

9. Click on the Next button and Enter the name of the Server (and instance if required).



10. Click OK and enter the name of your Database (already added in MSSQL Server).



11. Click OK.

12. Click on the Next button to initiate each of the set up options listed on the right-hand side of the "Creation wizard" screen. Enter and select the necessary information and settings for the following screens:

    a) Company info - Enter all your business' details such as the address, e-mail address, contact numbers and Company and Tax Registration numbers, which you need to display on all documents, reports, and lists. You may also select the Tax method applicable to your VAT/GST/Sales Tax registration, whether your default output option for documents, reports and lists are on: screen, printer, file, e-mail or fax. You may also load a logo picture to be displayed on your reports or documents, and set your Windows operating system's default date and currency formats.

    b) Reporting dates - This option allows you to set up the number of reporting dates required, and the start date of your financial year period. The periods or dates will be displayed in the format in which you have set your Windows Operating System's default date on the previous screen.

    The start date of the financial year is the first day of the calendar month in which the Set of Books (Advanced option) is created.

    For example, it it is created on 20 August 2021, the Start date is 1 August 2021, etc.

    Before the "Reporting dates" screen is launched, a message will be displayed.

    Periods are not there

    Click on OK to launch the "Reporting dates" screen.

    c) Batch types - This option allows you to create, delete an existing batch type, or change the name of an existing batch type in which you wish to enter and update or post your transactions to the ledger.

    d) Groups - This option allows you to set two Reporting groups for your General ledger accounts, Debtors, Creditors, Stock and Document groups.

    e) Salesperson - This option allows you to enter the salespersons names who will be selling your stock items, or selling services.

    f) Documents setup - This option allows you to set up your documents Invoices, Credit notes, Quotes, Orders, Purchases and Supplier return documents, you wish to hand to customers

(debtors) or suppliers (creditors) when you sell, or quote, or order and purchase, physical stock items and services set up in your stock item code file.

g) Stock information - The option allows you to define the units of stock you sell and the selling price descriptions and to set the Cost of sales parameters. This option should only be used if you use stock and/or wish to generate documents (Invoices, Credit notes, Quotes, Orders, Purchases and Supplier returns).

13. After the last setup screen (i.e. Stock information) is closed, the Next button will change to the Finish button.



14. Click on the Finish button. The new Set of Books will automatically be opened automatically and now ready to work in.

Before you begin processing transactions, make sure to create your general ledger accounts, bank accounts, tax accounts, debtor accounts, creditor accounts, and review or modify your settings and parameters to ensure accuracy and efficiency.

Taking the time to properly set up your osFinancials5/TurboCASH5 program and customize your Chart of Accounts will contribute to the success of your financial processing and reporting.

Steps after creating the Set of Books (Advanced)

Deactivate / Activate the Bank import plugin

By default, the Bank import plugin setting is activated.

The "*Default bank reconciliation*"field in Setup → System parameters (Setup ribbon) is not selected.

Bank import plugin - Bank Reconciliations Plugin Manual - BankImport Plugin Manual - Shop - The Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

The Bankimport plugin will import bank transactions and save you hours of data entry. You can simply link transactions to your debtors, creditors or other accounts. And with a simple mouse click link the payments to the right invoices.

Needs to be activated on the Setup ribbon, select Setup → System parameters

If you do not intend to wish to use the Bank import plugin at this stage, you need to turn the Bank import plugin off (Tick (select) the "*Default bank reconciliation*" option on Setup → System parameters (Setup ribbon).

The Bank import plugin can be activated as the Bank import plugin is included in the osFinancials5/TurboCASH5 subscription.

If bank Bank import plugin is not activated, separate Payments and Receipt batches will be created on the Bank tab when you create (add) Bank accounts in Setup → Accounts (Setup ribbon).

Customise labels for Document types

You may need to customise labels and fix records.

Change the descriptions on the Types tab on Tools → Customise languages (Setup ribbon). If you have a different language than English, you need to translate the descriptions for your language or specific requirements.

Document types5



"*Goods Returned*" - change to Supplier return to be consistent with the other labels in the language file.





The Document type (i.e. Invoice, Credit note, Quote, Purchase, Supplier return or Order) is stored and edited 1n the Tools → Customize language (Setup ribbon).

It should print the Document type (i.e. Invoice, Credit note, Quote, Purchase, Supplier return or Order) as this is more correct for the recipient of these documents.

If you need to print documents using the document layout files supporting one (1) Layout file for all document types), it is recommended that the Document types are edited and/or translated to the singular in the Types tab Tools → Customize language menu (Setup ribbon).

Change Edit Groups

Change the reporting group names (descriptions) of the Groups (Setup ribbon).

You may also add groups for reporting groups, if necessary.



The name must not already exist and may not be longer than 50 characters. This name will help you to identify the Set of Books on your system. You will need to select this name whenever you need to open the Set of Books or perform some other functions on the Set of Books.

The following groups are not included if the Set of Books was created using Create Set of Books (Advanced) option:

- Projects - You may create groups for Projects. These Projects may be activated in batches and documents. Once the batches and/or documents are posted (updated to the ledger), you may generate various reports for each Projects on the Sidebar of the Default menu.
- Cost centre 1 and/or Cost centre 2 -
- Languages - Multi-Language accounts -

Multi-Language accounts - Manual - Shop - Licence : Once-off -

This plugin makes it possible to translate the ledger and group names in multiple languages. It is already possible to choose different languages for the interface (the buttons). But this plugin makes it possible to do the accounting in different languages. Per user you can select a language, so the user can account in his/her own language. The set of books can be viewed in different languages, therefore it is possible an employee enters information into an English Set of Books and a bookkeeper, auditor, etc. can see the set of books in a set language, e.g. Afrikaans, Dutch, etc.

Add missing Groups and Paper types in the Types table

To add missing groups:

If you intend to use Projects, Cost centres and/or Multi-language Set of Books, you need to add these Groups manually:

1. Activate the SQLBrowser plugin in Tools → Activate plugins (Setup ribbon)
2. Launch the SQLBrowser plug-in Plugins → Tools → SQLBrowser (Setup ribbon).
3. Select the "*TYPES*" table.
4. Right-click and select "*Open*" on the context menu.



5. Select the last record WTYPEID - 93 in the TYPES table. Insert or Add a new record (you may also use the down arrow on your keyboard).
6. Add Groups - Optional - If you are planning to use any of the following features in

osFinancials5/TurboCASH5, you may add the groups, as required. To do this, type the following records and type 2 in the WTYPEPARENT column:

- 1000 - Projects
- 1002 - Cost centre 1
- 1003 - Cost centre 2
- 1004 - Languages

7. Add Paper types - Type the following records and type 5 in the WTYPEPARENT column:
   - 55 - Till slip
   - 56 - New plain
8. Close the SQLBrowser

> *SQLBrowser - Manual - Shop - Licence : Once-off -*
>
> *Activate the SQLBrowser plug-in Tools → Activate Plugins (select Tools → SQLBrowser and click Activate plugin) on the Setup ribbon.*

The groups will be added on Setup → Groups



Before you can start any processing, you need to set up your general ledger accounts, bank account, tax accounts, accounts receivable (debtor accounts), accounts payable (creditor accounts), etc. create and check or change your settings and parameters. This should not take much time, but can save you a lot of extra work and frustration, as the key to success in your processing and reports is in setting up the osFinancials5/TurboCASH5 program.

Customise your own Set of Books (Advanced)? - Set Books - Properties

Length of description fields and the basic control accounts

The basic features of your customized Set of Books with the "*Customise your own Set of Books (Advanced)?*" -option should be as follows:

1. Length of description fields - The default length of description fields for accounts is 64 characters and groups are up to 30 characters for group names. The group descriptions are more than 50 characters.
2. Account codes - Character length and the default control accounts. Depending on your choice of the number of digits for account codes, during the creation of your own Set of Books, the number of characters for the control accounts and the debtor accounts as well as the creditor accounts will be as follows:

Number of digits *Account code*	*Retained earnings*	*Debtors control*	*Creditors control*	*Number of account code digits - Debtor accounts*	*Number of account code digits - Creditor accounts*
3X3-DIGITS	*G510-000*	*G700-000*	*G900-000*	*D + 5-characters D00001*	*C + 5-characters C00000*
4X3-DIGITS	*G3100-000*	*G1100-000*	*G2000-000*	*D + 6-characters D000001*	*C + 6-characters C000000*
5X3-DIGITS	*G31000-000*	*G11000-000*	*G20000-000*	*D + 7-characters D0000001*	*C+ 7-characters C0000000*
6X3-DIGITS	*G310000-000*	*G110000-000*	*G200000-000*	*D + 8-characters D00000001*	*C + 8-characters C00000000*
7X3-DIGITS	*G3100000-*	*G1100000-*	*G2000000-000*	*D + 9-characters*	*C + 9-characters -*

	000	*000*		*D000000001*	*C000000000*
8X3-DIGITS	*G31000000-000*	*G11000000-000*	*G20000000-000*	*D + 10-characters - D0000000001*	*C + 10-characters - C0000000000*

Customise your own Set of Books - Configure Set of Books

Language settings

If you have created your custom Set of Books in "*English*" as the default language, the osFinancials5/TurboCASH5 interface will be displayed in "*English*". If the osFinancials interface is displayed in the language of your choice, you can select a different available language in the "*Switch language*" (Start ribbon).

Set the default language for your Set Books - You can choose your language and country in Setup → Access control. When you reopen your Set of Books, the language in the osFinancials5/TurboCASH5 interface, reports, etc. will be displayed in your selected language.

Customise your own language

If you want to customise your own language, you can select your language in Tools → Customise language (Setup ribbon).

It is strongly recommended that the label, which is edited or entered, is not longer than the default "English" labels' length. If your label is too long, it may cause some options in the program not to function or display properly. Do not use the Delete button to remove any of the existing edited labels.

Care must be taken to ensure that existing labels or descriptions in the main language, i.e. "English" not be modified. You must create a copy of the "English" or other selected language and rename it with a new name. You may use your own language file to edit.

If you decide to adapt a selected language file for your own specific industry or specific needs and want to modify these labels accordingly, it is important that you use a copy of the language file. This will prevent your language file from being overwritten when you reinstall osFinancials5/TurboCASH5, or install osFinancials update download files, or install osFinancials updates through the Help menu.

Customise the "TYPES"-tab

The entries on the "*Types*"-tab in Tools → Customise language (Setup ribbon) is database specific and will update the "*TYPES*" table in your Set of Books. You may edit, translate or change the descriptions as

necessary.

- Reporting groups - The default descriptions for the reporting groups is available in English as "*Account Reporting Group1 Name*", etc, , After adding the 4 reporting groups for Projects, Cost centre 1, Cost centre 2 and Languages, these 16 reporting groups, you may change, edit, translate these descriptions on the "*Types*"-tab in Tools → Customise language (Setup ribbon). These reporting group names may also be reviewed, changes, edited, translated in Setup → Groups according to your specific requirements for your country language or industry. The common reporting group names in most databases, is "Account group 1, Account group 2, Debtor group 1, Debtor group 2, Creditor group 1, Creditor group 2, Stock group 1, Stock group 2, Document group 1, Document group 2, Payment types, Salespersons, Projects, Cost centre 1, Cost centre 2 and Languages".

- Document types - The default descriptions for the standard 6 document types is "*Invoice", "Credit note", "Purchase", "Goods Returned*", "*Quote",* and "*Order*" . You may change, edit, translate the descriptions for the standard 6 document types for sales documents (Invoices, Credit notes and Quotes and for purchase documents (Purchases, Supplier returns and Orders) to match your specific requirements for your country language, tax regime or industry in the Types tab.

  In your language file, you may search and edit / translate the language labels for each of these document types. These matching descriptions are also displayed in the "*English*" language file. If you want to change or edit the labels according to your personal needs, you can make a copy of the "*English*" language file and feel free to translate the language labels for the document types according to your specific requirements, preferences and industry. You then also search for and modify and adapt the language labels for each of these document types in your own language file.

- Tax terminology - Tax account is the default description for VAT/GST/Sales tax/Consumption tax in the Types tab. You may change this description for your country language, tax regime or industry. In your language file, you may search and edit / translate the language labels for the for the tax terminology.

Customise the "Rest"-tab

The Customize language - Rest tab entries on this tab is database specific.

Change descriptions of the "*Description of Zero account*" and "*Group empty account*". The 2 change buttons only saves 1 description. Work around change both to "*Empty*".

General ledger accounts

Accounts Setup → Accounts - Only the 3 control accounts (i.e. Debtors control + Creditors control + Retained earnings) accounts in the Chart of Accounts is included in the Chart of Accounts.

You cannot delete these 3 control accounts. An error message will be displayed:

"You cannot delete a control account!"

You can edit the account code and description for each of these 3 control accounts, if necessary.

Depending on your choice of the number of digits for account codes, during the creation of your own Set of Books, the number of characters for the control accounts will be as follows:

Number of digits Account code	*Retained earnings*	*Debtors control*	*Creditors control*
3X3-DIGITS	*G510-000*	*G700-000*	*G900-000*
4X3-DIGITS	*G3100-000*	*G1100-000*	*G2000-000*
5X3-DIGITS	*G31000-000*	*G11000-000*	*G20000-000*
6X3-DIGITS	*G310000-000*	*G110000-000*	*G200000-000*
7X3-DIGITS	*G3100000-000*	*G1100000-000*	*G2000000-000*
8X3-DIGITS	*G31000000-000*	*G11000000-000*	*G20000000-000*

Control accounts - You can edit the account code and account description for each of these 3 control accounts.

It is important to note that you need to keep in mind that these control accounts need to be linked to account groups and financial categories:

Control account name	*Financial category*	*Account groups*
Retained earnings	*Capital*	*Equity / Capital*
Debtors control	*Assets*	*Current assets*
Creditors control	*Liabilities*	*Current liabilities*

If you import general ledger accounts from a Tab delimited file, you may:

- Change the account codes and descriptions to meet your specific requirements and needs. In the case of accounts, which contains sub-accounts, you cannot change the sub-accounts account codes. You first need to delete the sub-accounts and rename the account codes and account descriptions and recreate sub-accounts where necessary.
- Review your imported ledger accounts descriptions. You may use longer account descriptions (longer than the default 35-characters or 64-characters) , where necessary.
- Disabled (inactive) accounts imported - review and decide to keep these disabled (inactive) accounts or delete them if not required.
- Tax (VAT/GST/Sales tax) accounts - The first sub-account (tax code) may not include the Tax tab and Tax percentage - You need to delete and recreate the tax account (tax code) as a Tax account. Zero-rated Tax codes. You need to confirm the percentage.
- If Account groups 1 and / or Account group 2 is imported, these account groups may not be linked to the five financial categories. You may need to link these account groups to the 5 financial categories.

Imported or copied text in osFinancials screens from external files - Account / Group descriptions in Accounts description lines in batches

When importing or copying text for account. group descriptions or any other screens, or forms, the fields from external programs such as spreadsheet, word documents, etc. the hyphenation character "–" may be displayed as a pipe character " | " in lookups and some screens or as " " in some screens and in reports, document layout files, etc.

For example, Motor vehicles Net value if copied or imported into Setup - Accounts as Motor vehicles – Net value (with the hyphenation format) it will be displayed as Motor vehicles Net value on some screens and in reports and as Motor vehicles | Net value on lookup screens.

You need to use the dash sign "-" to be displayed correctly.

Solution:

To ensure hyphens display correctly in osFinancials5/TurboCASH5, use the standard dash character ("-") instead of the hyphenation character when copying or importing text from external files.

Debtor / Creditor accounts

Depending on your choice of the number of digits for account codes, during the creation of your own Set of Books, the number of digits for the account codes of debtor accounts and creditor accounts will be as follows:

Number of digits Account code	*Number of account code digits - Debtor accounts*	*Number of account code digits - Creditor accounts*
3X3-DIGITS	*D + 5-characters D00001*	*C + 5-characters C00000*
4X3-DIGITS	*D + 6-characters D000001*	*C + 6-characters C000000*
5X3-DIGITS	*D + 7-characters D0000001*	*C+ 7-characters C0000000*
6X3-DIGITS	*D + 8-characters D00000001*	*C + 8-characters C00000000*
7X3-DIGITS	*D + 9-characters D000000001*	*C + 9-characters - C000000000*
8X3-DIGITS	*D + 10-characters - D0000000001*	*C + 10-characters - C0000000000*

When creating or adding Debtor accounts and Creditor accounts, it is important that you use a different prefix for the account codes:

The first Debtor code (e.g. D00001, etc.), will automatically be generated. It is important to prefix Debtor codes with a unique prefix. In this documentation, the accounts is prefixed as follows:

- *Debtor code = 1*
- *Creditor code = 2*

The reason for this, is that the account prefix is not always available when selecting accounts on some screens and reports. For example, if a Debtor code is D00001 and a Creditor code is C00001, and you select the Debtor code, it may set the Creditor code when selecting the contra account in the "Options for this batch" (F10:Setup) on "Batch entry" screens on "Batch entry" screens.

Company information

Only "*osFinancials5.1.0.227 / TurboCASH5.1.0.227)* / (osFinancials5/TurboCASH5 and the version number) will be displayed in the title bar, unless you have already entered your company name in the Company info screen during the creation of the Set of Books. Review and enter the name and contact details as well as the relevant registration numbers of your business in the Setup → Company info (Setup ribbon).

Financial year and accounting periods

The default start of the financial year is on the first day of the month in which you created your set of books. For example, if you created your Set of Books on 20 March 2024, the start of the financial year will automatically be set as "*1 March 2024*". You can change this in Setup → Reporting dates for the beginning of your financial year and set the accounting periods.

If you selected a different language than the English languages, for example, "*Afrikaans*" as the language to create your Set of Books in, the months of the year should already be displayed in "*Afrikaans*". You may need to review and edit or translate the months of your financial year, if necessary.

Batches (Journals)

No batch types (journal types) are included in your customised Set Books. You will need to add your own batch types (journal types) in Setup → Batch types (Setup ribbon) to meet your specific needs and requirements. The basic journals, are the "*Sales journal*", "*Purchase journal*" and the "*General journal*".

> *Receipts journals and Payments journals for Bank accounts and Petty cash accounts*
>
> *When you add or create a Bank account and Petty cash account, the Receipts journals and Payments journals will be created and added and linked to each Bank account and Petty cash account.*

The "*Sales journal*", should be linked to the Invoices and Credit notes document types in Documents setup. This will update the transactions generated with the Invoices and Credit notes in the Sales journal to the ledger.
The "*Purchase journal*", should be linked to the Purchases and Supplier returns document types in the Documents setup. This will update the transactions generated with the Purchases and Supplier returns in the Purchase journal to the general ledger.
You can use any number of journal types as you deem necessary to group and process your transactions. In addition to the general journal, you may add specific journals for; cost of sales, adjustments, depreciation, payroll, etc. to accommodate your specific needs and requirements.

Documents setup

The defaults settings in the Setup → Documents setup is as follows:

1. Global settings - Documents setup
    - Layout file point-of-sale : "*DefaultA4*" is the default setting and is not available in the " ... *\plug_ins\reports\DOCUMENTS\DOCUMENTS*" folder. You may change the default layout file to "*POS - STARTSP100*".
    - Append notes below item: By default this option is selected. The default sequence in which the document lines will be displayed on document entry forms and printed in document layout files, is Item/Remark/Comment. If you deselect this option, the sequence in which the document lines will be displayed on document entry forms and printed in document layout files, will be Comment, Item, Remark.
    - Auto-post documents on print: By default this option is not selected. This means that you need to manually launch the Update ledger option to post or update documents to the

ledger.

2. Settings for specific document types. The basic configuration for each document type, is as follows:

Field	*Sales documents*			*Purchase documents*		
Document type	*Invoice*	*Credit note*	*Quote*	*Purchase*	*Purchase returns*	*Orders*
Next Document number	*I0N000001*	*C0000001*	*Q0000001*	*P0000001*	*R0000001*	*OR000001*
Batch type						
Layout file						
Layout file 2	-	-	-	-	-	-
Heading	*Tax Invoice no.*	*Credit note no.*	*Quote No*	*GRV No*	*Goods Returned No*	*Order No*
Message 1/2/3	-	-	-	-	-	-

Customise / translate notes:

You may need to customise, change and translate the following to suit your specific preferences and needs:

- Next Document number - This is an 8-character alphanumeric field. You may use prefixes for each document type. Prefixes will make it easier to identify the document type in searches and filters, on reports and on exported data in spreadsheets. The character prefixes for each document number are in English. You can change the document numbers for each type of document to suit your specific preferences and needs.

- Batch types - No batch types or journals are available at this stage. You will need to select the default journals in which the documents will be posted (updated) to the ledger. If you have already created journals earlier during the creation of your advanced Set of Books, you can select the "*Sales journal*" for Invoices and Credit notes and the "*Purchase journal*" for Purchases and Supplier returns. If not, you will first need to create the journal types in Setup → Batch types (Setup ribbon) such as "*Sales journal*" and "*Purchase journal*". Journals do not apply to Quotes and Orders.

- Layout file - You can select "*Layout file*" at this stage for all document types. The "Layout file" is one

standard generic layout file that applies to all document types (Invoices, Credit notes, Quotes, Purchases, Supplier returns and Orders) and is translated via the language files. The layout file selected is a global setting. You may also select custom or other layout files as defaults for specific debtor or creditor accounts.

- Layout file 2 - This option is not selected. You may select other layout files or the delivery note to print after the Layout file.
- Headings - You may change the headings of each document headings to match your country language, tax regime or industry.
- Messages - No messages is available at this stage. You may enter up to 3 lines as a global message (for each document type) that will be displayed on the "*Message*" fields of the document entry screens and printed on document layout files for each document type. Custom messages may be set as default for specific debtor or creditor accounts.
- Statement message - You can enter up to 3 lines of statement messages in the Statement setup tab. This is a global standard message that will appear on all debtor account statements.

Additional settings for documents

Post / Confirm and Delete buttons on Documents grid - By default, only the New, Edit and Print buttons are available on the Documents grid screen's sidebar. You may add the Posting and Delete buttons underneath the Print button. To add the Posting and Delete buttons to the Document grid screen, select (tick) the "*Document posting*" field on the Documents tab in Setup → Access control.

Stock items / Inventory items

Before you add or import your stock items / inventory items / products you may need to configure some important basic settings such as Cost of sales, Create tax classes / account classes and Selling prices.

At this point, your chart of accounts (general ledger accounts) should have already been finalised.

Activate Cost of Sales

By default cost of sales is not activated. You need to configure cost of sales as follows:

1. Cost of Sales journal - Create a cost of sales batch (journal) type (Setup → Batch types) to update the transactions for cost of sales to the ledger when you post documents.
2. Cost of sales settings (Setup → Stock information) - Select the following:
    - Create cost of sales - To activate cost of sales, select (tick) the "*Create cost of sales*" tick box.
    - Cost of sales batch - Select the Cost of sales batch (journal) in which the cost of sales transactions will be posted.

- Use “*Average cost*” or “*Latest cost*” option.

> *The method you use to calculate the value of your stock is crucial for determining its impact on your profit and loss figures. It is important to consider whether to use the “average cost” or the “latest cost” method.*
>
> *If you are unsure which method to use, it is recommended that you seek guidance from your accountant.*

Create tax classes / account classes

At this point, your chart of accounts (general ledger accounts) should have already been finalised.

You need to link each stock item / inventory item / product to the applicable ledger accounts (i.e. Input tax, Output tax, Sales account, Cost of sales account and Stock control account).

Tax classes may be set and linked to each category of tax and various tax rates such as Output tax, Input tax - Standard rate, Input tax - Capital goods, Zero rated goods, Exempt supplies applicable to the stock items / inventory items / products in your country and tax jurisdiction, etc.

Tax classes is defined and managed in the Tax classes tab in Setup → Stock information. When you create add or import your stock items / inventory items / products you may select a pre-configured Tax class to automatically link the five accounts (i.e. Input tax, Output tax, Sales account, Cost of sales account and Stock control account) applicable to the stock item / inventory item / product.

Selling prices

osFinancials supports up to 3 selling prices (i.e. Selling price 1, Selling price 2 and Selling price 3). You may change the descriptions of these selling prices on the "*Selling price descriptions*" section of the Default tab of Setup → Stock information to suit your specific requirements and set one of these Selling prices as the default Selling price (global setting) for your Set of Books.

In addition to this, you may set one of these Selling prices as the default Selling price on the Accounting information tab for specific debtor (customer / client) accounts.

> *Price agreement plugin - Manual - Shop - Licence : Once-off -*
>
> *In addition to the standard 3 selling prices in odFinancials, Price agreement plugin, allows you to set up to five (5) levels of quantity discounts that can be applied to specific debtors or groups of debtors. Additionally, you can set a special price for individual debtors per product. These prices will overrule the default Selling price 1 / 2 / 3 and can be set per debtor (customer / client). The price agreement may also be activated for creditor (supplier / vendor) accounts.*

Units of stock

Add and define the units such as each, hours, etc. for your stock items / inventory / products. You may add these descriptions on the Units tab in Setup → Stock information.

Reporting groups - Stock group 1 / Stock group 2

In osFinancials, you have the option to set up to 2 reporting groups for your stock items / inventory items / products, allowing you to categorise search, filter and report on your products more effectively. These reporting groups provide a way to organize and analyse your inventory based on specific criteria.

You may add these Stock groups in Setup → Groups can be linked to each stock item (inventory item / product).

Set the Calendar as default

You have the option to activate the Calendar to be launched instead of the Welcome screen whenever you open a Set of Books, This means that the Calendar will be automatically displayed as the default screen.

Created with the Standard Edition of HelpNDoc: Experience a User-Friendly Interface with HelpNDoc's Documentation Tool

MSSQL Server's backup and restore options

If you are running a Set of Books as a Microsoft SQL Server (MSSQL) database type, MSSQL Server includes its own options to backup and restore the database.

MSSQL Server provides built-in features and tools to perform backups and restores, ensuring the reliability and integrity of your database. These features include:

1. SQL Server Management Studio (SSMS): SSMS is a graphical tool provided by Microsoft for managing MSSQL Server. It includes options to perform backups and restores through its user interface. You can access these options by connecting to your MSSQL Server instance using SSMS and navigating to the appropriate database.
2. Transact-SQL Commands: MSSQL Server supports Transact-SQL (T-SQL), a programming language used for managing and querying databases. T-SQL provides specific commands for performing backups and restores, such as BACKUP DATABASE and RESTORE DATABASE. These commands can be executed using an SQL client or through scripts.

By utilizing MSSQL Server's backup and restore options, you can create backups of your Set of Books

database at regular intervals and restore them when needed. Backups can be stored locally or on remote storage devices for added data protection.

It's important to understand the backup and restore process specific to MSSQL Server and follow best practices to ensure the integrity and availability of your database. Consulting the MSSQL Server documentation or seeking guidance from database administrators familiar with MSSQL Server will provide you with detailed instructions and considerations for performing backups and restores.

Created with the Standard Edition of HelpNDoc: Streamline Your Documentation Process with HelpNDoc's Project Analyzer

Development - MySQL and Postgress databases

The following online documentation is available for osfinancials (Build 913 and later):

- *Open Android documentation*
- *Open Postgress server setup documentation*
- *Open MySQL server setup documentation*

Created with the Standard Edition of HelpNDoc: Maximize Your Documentation Capabilities with HelpNDoc's Project Analyzer

Banking abbreviations / acronyms in osFinancials

Banking

Bank account type

- 11-Proof - See http://nl.wikipedia.org/wiki/Elfproef - Proof, also known as the "11-test" or "Elfproef" in Dutch, is a mathematical test used in the Netherlands to validate the accuracy of bank account numbers. The test is based on the principle of modulo 11 arithmetic and is used to detect errors in bank account numbers, such as transpositions or missing digits.

  The Proof test involves multiplying each digit of the bank account number by a corresponding weight, then summing the products and calculating the remainder when divided by 11. If the remainder is zero,

the bank account number is considered valid. If the remainder is not zero, the bank account number is considered invalid and may contain an error that needs to be corrected.

The Proof test is commonly used in the Netherlands by banks, businesses, and government agencies to validate the accuracy of bank account numbers before processing transactions. The test helps to prevent errors and ensure that funds are transferred to the correct account. However, it should be noted that the Proof test is not foolproof and may not detect all errors in bank account numbers.

- Arbitrair - Random - not controlled Arbitrair refers to an arbitrary bank account number (such as one that is not validated), the selection of these options could have implications for how the bank treats the account.
    - Accounting information tab of Default → Debtor / Creditor accounts.

BIC - (Bank Identifier Code) - BIC stands for Bank Identifier Code, which is a unique identifier assigned to financial institutions, primarily for international money transfers. The BIC is also known as the SWIFT code, as it is assigned by the Society for Worldwide Interbank Financial Telecommunication (SWIFT).

The BIC consists of a series of eight or eleven alphanumeric characters that identify a specific financial institution. The first four characters of the BIC identify the bank or financial institution, while the next two characters identify the country code. The last two or five characters are optional and represent the branch code of the financial institution.

The BIC is used in conjunction with the International Bank Account Number (IBAN) to facilitate international money transfers. Together, the IBAN and BIC provide a standardized and secure means of identifying the correct recipient and financial institution for international transactions.

The BIC is widely used around the world and is recognized by most financial institutions and banks. It is an essential part of the global financial system and facilitates the efficient and secure transfer of funds across borders.

- Setup → Company info
- Accounting information tab of Default → Debtor / Creditor accounts

IBAN - (International Bank Account Number) See http://en.wikipedia.org/wiki/International_Bank_Account_Number IBAN stands for International Bank Account Number, which is a standardized international format for bank account numbers used for international money transfers. The IBAN was developed by the International Organization for Standardization (ISO) to facilitate cross-border transactions and to make international payments more efficient.

The IBAN is a unique identifier that includes the country code, check digits, and the account number. The

country code and check digits help to validate the accuracy of the account number and ensure that the money is transferred to the correct recipient. The IBAN is used in conjunction with the Bank Identifier Code (BIC) to facilitate international money transfers.

The IBAN is used in many countries around the world, particularly in Europe, but it is not used universally. Some countries, such as the United States, Canada, and Australia, do not use IBANs for their domestic banking transactions. However, when making international payments to countries that use IBANs, it is generally required to include the recipient's IBAN in order for the transaction to be processed successfully.

- Setup → Company info

- Accounting information tab of Default → Debtor / Creditor accounts

SWIFT - (Society for Worldwide Interbank Financial Telecommunication) See http://en.wikipedia.org/wiki/SWIFT / http://www.theswiftcodes.com/ SWIFT (Society for Worldwide Interbank Financial Telecommunication) is a global network used by banks and other financial institutions to securely transmit financial messages and information. The SWIFT network provides a standardized and secure means for financial institutions to communicate with each other, enabling them to send and receive payments, foreign exchange trades, securities transactions, and other financial messages.

SWIFT operates a messaging platform that allows banks to exchange financial information with one another in a secure and standardized format. Each financial institution that participates in the SWIFT network has a unique Bank Identifier Code (BIC), which identifies the institution's name, location, and country code. The SWIFT network is used by over 11,000 financial institutions in more than 200 countries, making it the largest financial messaging network in the world.

SWIFT messages are sent through the network in a standardized format that includes information about the sender, the recipient, and the transaction. This information is transmitted securely and is only accessible to the authorized parties involved in the transaction. SWIFT messages can be used for a variety of financial transactions, including payments, foreign exchange trades, securities transactions, and other financial messages.

- Setup → Company info

SEPA - (Single Euro Payments Area) - See - http://en.wikipedia.org/wiki/Single_Euro_Payments_Area - SEPA stands for Single Euro Payments Area, which is a European Union initiative aimed at harmonizing electronic euro payments across participating countries. The SEPA initiative allows individuals and businesses to make payments in euros to any other bank account located in the SEPA area, regardless of whether the recipient's bank is located in their home country or in another SEPA country.

SEPA covers the 27 EU member states, as well as Iceland, Liechtenstein, Norway, Switzerland, Monaco, and

San Marino. SEPA has standardized the format of euro payments across participating countries, which has made cross-border transactions more efficient and cost-effective. SEPA payments are processed using the International Bank Account Number (IBAN) and the Bank Identifier Code (BIC).

- Signature and Signature date fields - Accounting information tab of Default → Debtor / Creditor accounts.

Other common banking abbreviations/acronyms

Here are some other common banking abbreviations/acronyms:

1. ATM: Automated Teller Machine - A machine that allows customers to perform various banking transactions, such as withdrawing cash, depositing money, transferring funds, and checking account balances, without the need for a bank teller.
2. ACH: Automated Clearing House - A payment system that allows electronic funds transfers between bank accounts in the United States.
3. BSB: Bank State Branch - A unique identifier used in Australia to specify both the bank and the branch where an account is held.
4. CC: Credit Card - A payment card issued by a bank or financial institution that allows users to make purchases and borrow money up to a certain credit limit.
5. CEO: Chief Executive Officer - The highest-ranking executive in a company or organization responsible for making major corporate decisions and managing overall operations.
6. CFPB: Consumer Financial Protection Bureau - An agency of the United States government responsible for protecting consumers in the financial sector by enforcing consumer protection laws and providing education and resources to consumers.
7. CTR: Currency Transaction Report - A report that financial institutions are required to file with the government for any cash transaction over $10,000 in the United States.
8. EFT: Electronic Funds Transfer - The electronic transfer of funds from one bank account to another, usually initiated through online banking or a mobile app.
9. FDIC: Federal Deposit Insurance Corporation - A United States government agency that provides insurance to depositors in case their bank fails, up to a certain amount.
10. KYC: Know Your Customer - The process banks and other financial institutions use to verify the identity of their customers and assess their potential risk for illegal activities such as money laundering and terrorism financing.
11. POS: Point of Sale - The location where a customer makes a payment for goods or services, typically

at a physical retail store or restaurant.

12. RTGS: Real-Time Gross Settlement - A payment system that allows for the real-time transfer of funds between bank accounts, typically used for high-value transactions.
13. PIN: Personal Identification Number - A numeric code used to verify the identity of a customer when making a transaction, typically associated with a debit or credit card.
14. OD: Overdraft - A financial arrangement where a bank allows a customer to withdraw more money than they have in their account, up to a certain limit, usually with associated fees and interest.
15. NEFT: National Electronic Funds Transfer - A payment system used in India that allows for the electronic transfer of funds between bank accounts.
16. MICR: Magnetic Ink Character Recognition - A technology used by banks to encode and process checks with a magnetic ink line at the bottom of the check.
17. IMPS: Immediate Payment Service - A payment system in India that allows for the instant transfer of funds between bank accounts, typically through a mobile app.

Created with the Standard Edition of HelpNDoc: Quickly and Easily Convert Your Word Document to an ePub or Kindle eBook